



Table of Contents

EXECUTIVE SUMMARY	i
1.0 INTRODUCTION.....	1
1.1 Site Description.....	1
1.2 Proposed Site Development Plan.....	1
1.3 Organization of Report.....	2
1.4 List of Contributing Authors	3
2.0 SITE INVESTIGATION METHODOLOGY	4
2.1 Cone Penetration Testing.....	4
2.2 Borehole Drilling Program.....	4
2.2.1 Deep Borehole Investigation Locations: 12-1 through 12-4 and 13-5 through 13-7	4
2.2.2 Shallow Borehole Investigation Locations: 13-8 through 13-25	7
2.3 Detailed Geological Logging.....	8
2.4 Geotechnical Laboratory Testing.....	8
2.5 Monitoring Well Installation and Elevation Surveying Program.....	8
2.5.1 Bedrock and VSP Monitoring Well Installations	8
2.5.2 Overburden Monitoring Well Installations.....	9
2.5.3 Elevation Survey Program	9
2.6 Groundwater and Surface Water Testing Program.....	10
2.6.1 Groundwater Level Monitoring.....	10
2.6.2 Groundwater Sampling	10
2.6.2.1 On-Site Groundwater Sampling Program	10
2.6.2.1.1 Background Groundwater Quality Monitoring.....	10
2.6.2.1.2 Isotopic Analysis of Groundwater.....	10
2.6.2.2 Residential Well Sampling Program	11
2.6.3 Background Surface Water Quality Monitoring	12
2.6.4 Quality Assurance/Quality Control	12
2.7 Hydraulic Conductivity Testing.....	12
2.7.1 Laboratory Permeability Tests	12



2.7.2	Slug Testing	12
2.8	Geophysical Testing	13
3.0	GEOLOGICAL SETTING.....	14
3.1	Regional Geological Conditions.....	14
3.1.1	Regional Bedrock Geology	14
3.1.2	Regional Surficial Geology.....	16
3.2	Local Geological Conditions	16
3.2.1	Local Bedrock Geology.....	16
3.2.1.1	Bedrock Surface Topography	18
3.2.1.2	Local Bedrock Geology Map.....	18
3.2.1.3	Bedrock Stratigraphic Sequence	20
3.2.1.4	Fault Structures	23
3.2.2	Local Surficial Geology	25
3.3	CRRRC Site Geological Conditions.....	25
3.3.1	Site Bedrock Geology	25
3.3.2	Site Surficial Geology.....	26
4.0	REGIONAL TECTONICS.....	28
4.1	Seismicity	28
4.2	Present Day State of Stress.....	30
5.0	TOPOGRAPHY AND SURFACE DRAINAGE.....	31
5.1	Local Topography.....	31
5.2	Surface Water Drainage	31
5.2.1	Natural Watercourses	31
5.2.2	Constructed Watercourses.....	32
5.2.3	Existing Surface Water Outlet Points	33
6.0	SITE SUBSURFACE CONDITIONS	34
6.1	Topsoil/Peat.....	34
6.2	Surficial Silty Sand and Silt.....	34
6.3	Silty Clay.....	35
6.4	Glacial Till.....	39



6.5	Bedrock	40
6.6	Geophysical Testing	40
6.7	Additional Borehole Investigations.....	41
7.0	HYDROGEOLOGY CONDITIONS.....	42
7.1	Local Hydrogeology	42
7.2	Site Hydrogeology	43
7.2.1	Groundwater Level Data and Flow Directions.....	43
7.2.1.1	Surficial Silty Sand Layer.....	43
7.2.1.2	Silty Layer.....	44
7.2.1.3	Silty Clay.....	44
7.2.1.4	Glacial Till.....	44
7.2.1.5	Upper Bedrock Zone.....	45
7.2.2	Hydraulic Gradients.....	45
7.2.2.1	Vertical Component.....	45
7.2.2.2	Horizontal Component.....	46
7.2.3	Vertical Hydraulic Conductivity.....	46
7.2.4	Horizontal Hydraulic Conductivity	46
7.2.5	Groundwater Flux.....	48
7.2.6	Average Linear Groundwater Velocity.....	49
7.2.7	Groundwater Residence Time	50
8.0	BACKGROUND GROUNDWATER AND SURFACE WATER QUALITY	51
8.1	Monitoring Well Program	51
8.2	Residential Well Program	52
8.3	Surface Water Program	53
9.0	EVALUATION OF POTENTIAL GEOLOGICAL IMPACTS.....	55
9.1	Fault Rupture.....	55
9.2	Assessment of Potential for Fault Rupture at CRRRC Site	56
9.3	Assessment of Potential Subsurface Settlement from Earthquake Ground Shaking.....	57
10.0	DESCRIPTION OF SITE DESIGN	59
10.1	Site Access, Entrance Facilities and Roads	59



10.2	Small Load Drop-Off.....	59
10.3	C&D Processing Facility	59
10.4	Material Recovery Facility.....	60
10.5	Organics Processing Facility and Compost Processing and Storage Pad.....	60
10.6	Petroleum Hydrocarbon Contaminated Soil Treatment	61
10.7	Surplus Soil Management.....	61
10.8	Landfill	62
10.9	Stormwater Management	63
10.10	Screening Berms	64
11.0	GEOTECHNICAL CONSIDERATIONS OF SITE DESIGN.....	65
11.1	Stability Analyses.....	65
11.1.1	Static Slope Stability Results	68
11.1.2	Static Stability Guidelines for Related Site Features	69
11.2	Seismic Assessment.....	70
11.3	Settlement Analyses	71
11.4	Potential Geological and Geotechnical Related Effects on Landfill Design and Performance	74
11.5	Geotechnical Monitoring Program	75
11.6	Buildings and Site Grading	76
12.0	GROUNDWATER MODELLING AND ASSESSMENT OF LONG-TERM GROUNDWATER IMPACTS.....	77
12.1	Hydrogeological Conceptual Model	77
12.1.1	Site Geological Setting.....	77
12.1.2	Hydrostratigraphy.....	77
12.1.3	Groundwater Flow Directions and Hydraulic Gradients.....	79
12.1.4	Effect of Clay Consolidation on Groundwater Flow	79
12.2	Three-Dimensional Numerical Groundwater Flow Model	80
12.2.1	Model Construction and Grid Discretization	80
12.2.2	Boundary Conditions.....	82
12.2.3	Material Properties.....	82
12.2.4	Model Calibration	83
12.2.5	Predictive Simulations.....	83



12.2.6	Results	85
12.3	Assessment of Long-Term Groundwater Impacts.....	85
12.3.1	Regulatory Objectives	85
12.3.2	Geological/Hydrogeological Conditions Modelled Beneath the Landfill.....	86
12.3.3	Landfill Modelling Approach	88
12.3.4	Landfill Leachate Generation Rates	88
12.3.5	Landfill Key Contaminants and Associated Transport Parameters	89
12.3.6	Service Life of Landfill Leachate Control System Components.....	92
12.3.7	Landfill Leachate Mound Height.....	93
12.3.8	Vertical Leakage Rates	94
12.3.9	Results of Contaminant Transport Modelling	94
12.3.10	Landfill Contaminating Lifespan	96
12.3.10.1	Sensitivity Analyses	97
12.3.10.2	All Contaminants Going to the Silty Layer	97
12.3.10.3	Settlement	97
12.3.10.4	Early Failure of the Leachate Collection System Beneath the Waste.....	98
12.4	Summary	98
13.0	GROUNDWATER AND SURFACE WATER MONITORING PROGRAMS AND TRIGGER MECHANISMS	100
13.1	Objectives of Monitoring Program.....	100
13.2	Groundwater Monitoring Program.....	100
13.2.1	Monitoring Locations	100
13.2.2	Monitoring Frequency	105
13.2.3	Parameters	105
13.2.4	Monitoring System Maintenance	107
13.3	Surface Water Quality Monitoring Program	107
13.3.1	Monitoring Locations	107
13.3.2	Monitoring Frequency	107
13.3.3	Parameters	107
13.4	Leachate Monitoring Program.....	109
13.4.1	Monitoring Locations	109



13.4.2 Monitoring Frequency 109

13.4.3 Parameters 109

13.4.4 Leachate Level Measurement 110

13.5 Future Modifications to Monitoring Program 111

13.6 Objectives of Trigger Mechanism 111

13.7 Compliance Evaluation Parameters and Trigger Concentrations 111

13.7.1 Preamble 111

13.7.2 Groundwater 113

13.7.3 Surface Water 119

13.8 Trigger Formats 120

13.8.1 Groundwater Trigger 120

13.8.2 Surface Water Trigger 121

13.9 Trigger Locations 122

13.9.1 North, West and South Boundaries 122

13.9.2 East Boundary 123

13.9.2.1 Surficial Silty Sand 123

13.9.2.2 Silty Layer 123

13.9.2.3 Glacial Till 123

13.9.2.4 Bedrock 123

13.10 Modification to Trigger Mechanism 123

14.0 GROUNDWATER AND SURFACE WATER CONTINGENCY MEASURE 124

14.1 Groundwater 124

14.2 Surface Water 124

15.0 LIMITATIONS AND USE OF REPORT 125

REFERENCES 126



TABLES

Table 2-1: Summary of Deep Borehole Investigation: Locations 12-1 through 12-4 and 13-5 through 13-7 6

Table 2-2: Summary of Shallow Borehole Investigation: Locations 13-8 through 13-25 7

Table 4-1: Major Historical Earthquakes ($M \geq 5.0$) with Epicentres located within about 200 kilometres of the CRRRC Site 29

Table 5-1: Municipal Drain Details for the CRRRC Site 33

Table 6-1: Summary of Oedometer Consolidation Tests..... 36

Table 6-2: Summary of Secondary Compression Oedometer Consolidation Tests 37

Table 6-3: Summary of Porewater Pressure Dissipation Tests 38

Table 6-4: Summary of Cored Bedrock Boreholes..... 40

Table 7-1: Horizontal Gradients at CRRRC Site 46

Table 7-2: Vertical Hydraulic Conductivity Testing Results 46

Table 7-3: Horizontal Hydraulic Conductivity Testing Results..... 47

Table 7-4: Summary of Average Linear Groundwater Velocities across the CRRRC Site 49

Table 7-5: Tritium Results 50

Table 8-1: Parameters Consistently Exceeding ODWQS in On-Site Monitoring Wells 51

Table 8-2: Parameters Consistently Not Meeting PWQO..... 54

Table 11-1: Summary of Soil Parameters 67

Table 11-2: Summary of Static Slope Stability Results 68

Table 12-1: Calibrated Recharge Rates..... 82

Table 12-2: Summary of Hydraulic Parameters Assigned in the Calibrated Numerical Model..... 82

Table 12-3: Summary of Hydraulic Parameters Assigned in the Post-development Numerical Model 84

Table 12-4: Input Parameters for Modelling Leachate Generation Rate Using HELP Model 89

Table 12-5: Key Contaminants and Associated Soil Transport Parameters – Silty Layer 91

Table 12-6: Average Darcy Fluxes 94

Table 12-7: Predicted Concentrations of Key Leachate Contaminants in the Silty Layer from the CRRRC Landfill 95

Table 12-8: Early Failure of Leachate Collection System..... 98

Table 13-1: Proposed Groundwater Monitoring Program for the Process and Treatment Facilities..... 101

Table 13-2: Proposed Groundwater Monitoring Program for the Landfill 102

Table 13-3: Proposed Groundwater Monitoring Parameters 105

Table 13-4: Proposed Surface Water Monitoring Stations 107

Table 13-5: Proposed Surface Water Monitoring Program Parameters 108

Table 13-6: Proposed Leachate Monitoring Parameters..... 109

Table 13-7: Groundwater Quality for Leachate Indicator Parameters in the Surficial Silty Sand..... 113

Table 13-8: Groundwater Quality for Leachate Indicator Parameters in the Silty Layer 114



Table 13-9: Groundwater Quality for Leachate Indicator Parameters in the Glacial Till Deposit..... 115
Table 13-10: Groundwater Quality for Leachate Indicator Parameters in the Upper Bedrock..... 116
Table 13-11: Groundwater Reasonable Use Performance Objectives and Trigger Concentrations for Surficial Silty Sand..... 117
Table 13-12: Groundwater Reasonable Use Performance Objectives and Trigger Concentrations for the Silty Layer..... 117
Table 13-13: Groundwater Reasonable Use Performance Objectives and Trigger Concentrations for the Glacial Till..... 118
Table 13-14: Groundwater Reasonable Use Performance Objectives and Trigger Concentrations for the Upper Bedrock 118
Table 13-15: Surface Water Quality for Leachate Indicator Parameters 119
Table 13-16: Surface Water Compliance and Trigger Concentrations 120

FIGURES

Figure 1-1: Key Plan
Figure 2-1: Site Plan
Figure 2-2: Surface Water Monitoring Locations and Constructed Surface Water Features
Figure 3-1: Regional Bedrock Geology
Figure 3-2: Regional Bedrock Geology Cross-Sections A-A' and B-B'
Figure 3-3: Regional Surficial Geology
Figure 3-4: Gas Exploration Well Locations
Figure 3-5: Local Bedrock Surface Elevation Map
Figure 3-6: Interpreted Local Bedrock Geology Map
Figure 3-7: Local Structural Geologic Cross-Section C-C'
Figure 3-8: Elevation of Queenston Formation Basal Contact at Russell Quarry
Figure 3-9: Local Overburden Thickness Map
Figure 3-10: Local Surficial Geology
Figure 3-11: Local Geologic Cross-Section D-D'
Figure 3-12: Site Bedrock Surface Elevation and Bedrock Geology Maps
Figure 3-13: Site Overburden Thickness and Surficial Geology Maps
Figure 3-14: Site Cross-Section E-E'
Figure 3-15: Site Cross-Section F-F'
Figure 3-16: Site Surficial Geology Isopach Maps (Surficial Silty Sand and Silty Clay)
Figure 3-17: Site Surficial Geology Isopach Maps (Silty Layer and Glacial Till)
Figure 4-1: Seismicity near the CRRRC Site
Figure 4-2: Orientation of the Stress Field Near the CRRRC Site
Figure 4-3: Regional Stress Map
Figure 5-1: Topography



- Figure 5-2: Surface Water Subwatersheds
- Figure 5-3: Existing Site Drainage
- Figure 7-1: Surficial Silty Sand Groundwater Flow
- Figure 7-2: Silty Layer Groundwater Flow
- Figure 7-3: Middle Silty Clay Groundwater Flow
- Figure 7-4: Glacial Till Groundwater Flow
- Figure 7-5: Upper Bedrock Groundwater Flow
- Figure 8-1: Groundwater Quality Monitoring Locations
- Figure 9-1: Paleo-Channels
- Figure 10-1: Site Development Plan
- Figure 10-2: Leachate Collection and LDSCS Piping Layout Plan
- Figure 11-1A: Stability Analysis – Eastern Side of Landfill Adjacent to SWMP
- Figure 11-1B: Stability Analysis – Eastern Side of Landfill Adjacent to SWMP
(3x Vertical Exaggeration)
- Figure 11-2A: Stability Analysis – Northern End of Landfill Adjacent to Simpson Drain
- Figure 11-2B: Stability Analysis – Northern End of Landfill Adjacent to Simpson Drain (3x Vertical Exaggeration)
- Figure 11-3A: Stability Analysis – Interim Waste Slope
- Figure 11-3B: Stability Analysis – Interim Waste Slope (3x Vertical Exaggeration)
- Figure 11-4: Calculated Range of Total Settlement, Settlement Versus Time – 25-Metre High Landfill
- Figure 11-5: Calculated Range of Total Settlement, Settlement Versus Time – 13.5-Metre High Landfill
- Figure 11-6: Calculated Range of Total Settlement, Total Settlement Versus Landfill Thickness – 100 Years
- Figure 12-1: Hydraulic Head Development During Consolidation
- Figure 12-2: 3-D Numerical Groundwater Model Domain
- Figure 12-3: Boundary Conditions 3-D Numerical Groundwater Model
- Figure 12-4: Hydraulic Conductivity Distribution 3-D Numerical Groundwater Model
- Figure 12-5: Comparison of Simulated and Measured Groundwater Elevations
- Figure 12-6: Simulated Post-Development Cross-Section
- Figure 12-7: Simulated Post-Development Post-Settlement Cross-Section
- Figure 12-8: Simulated Pre-Failure Groundwater Drawdown (PS1: pre-settlement)
- Figure 12-9: Simulated Pre-Failure Groundwater Drawdown (PS2: post-settlement)
- Figure 12-10: Simulated Post-Failure Groundwater Elevation (PS3: post-settlement)
- Figure 12-11: Simulated Post-Failure Hydraulic Head (PS3: post-settlement)
- Figure 12-12: Simplified Cross-Sections for Contaminant Transport Model
- Figure 12-13: Results of Contaminant Transport Model
- Figure 13-1: Proposed Groundwater and Surface Water Monitoring Locations



APPENDICES

APPENDIX A

Borehole Records

APPENDIX B

CPT Profiles

APPENDIX C

Grain Size Curves

APPENDIX D

Undrained Shear Strength Profiles

APPENDIX E

Summary of Silty Clay Sensitivity

APPENDIX F

Plasticity Charts, Consolidation Test Results and Secondary Compression Test Results

APPENDIX G

Summary of Measured/Interpreted Coefficients of Vertical and Horizontal Consolidation

APPENDIX H

Summary of Engineering Properties

APPENDIX I

Photographs of Direct Push Soil Samples

APPENDIX J

Photographs of Bedrock Core Samples

APPENDIX K

Technical Memorandum – Results of VSP Testing

APPENDIX L

Groundwater Level Monitoring Program

APPENDIX M

Technical Memorandum – Dug Well Assessment

APPENDIX N

Laboratory and In-Situ Hydraulic Conductivity Testing Results

APPENDIX O

Background Groundwater Quality Data

APPENDIX P

Background Surface Water Quality Data

APPENDIX Q

Technical Memorandum – Seismic Stability Dynamic Analyses

APPENDIX R

Contaminant Transport Model