



**December 2014**

## **VOLUME IV**

# **Design and Operations Report Capital Region Resource Recovery Centre**

**REPORT**



**Report Number:** 12-1125-0045/4500/vol IV





## Table of Contents

<b>1.0 INTRODUCTION.....</b>	<b>1</b>
1.1 Purpose and Scope .....	1
1.2 Regulatory Requirements .....	1
1.2.1 Environmental Protection Act (EPA) .....	2
1.2.1.1 Guideline for the Production of Compost in Ontario.....	2
1.2.1.2 Ontario Regulation 101/94 – Recycling and Composting of Municipal Waste .....	2
1.2.1.3 Ontario Regulation 232/98 – Landfill Sites.....	2
1.2.1.4 Ontario Water Resources Act (OWRA).....	2
1.3 Related Documentation .....	3
<b>2.0 EXISTING SITE CONDITIONS .....</b>	<b>4</b>
2.1 Site Location and Legal Description .....	4
2.2 Land Use .....	4
2.3 Adjacent Land Use .....	4
2.4 Topography.....	5
2.5 Hydrology .....	5
2.6 Geology/Hydrogeology .....	5
<b>3.0 CRRRC SITE DESCRIPTION.....</b>	<b>7</b>
3.1 Waste Stream.....	7
3.1.1 Service Area .....	7
3.1.2 Waste Characteristics .....	7
3.1.3 Waste Quantities.....	7
3.2 Site Layout.....	8
<b>4.0 ASSESSMENT OF POTENTIAL IMPACTS .....</b>	<b>9</b>
4.1 Groundwater Assessment .....	9
4.2 Surface Water Assessment .....	9
4.3 Noise Assessment.....	10
4.3.1 Criteria and Guidelines.....	10
4.3.2 Receptor Summary Locations.....	11



4.3.3	Compliance .....	12
4.4	Air Quality and Odour Assessment.....	12
4.5	Lateral Gas Migration Assessment.....	16
4.6	Biological Assessment.....	17
<b>5.0</b>	<b>SITE DESIGN .....</b>	<b>18</b>
5.1	Site Access, Entrance Facilities and Roads .....	18
5.2	Buffers .....	19
5.3	Visual and Noise Screening.....	19
5.4	Stormwater Management .....	20
5.5	Construction and Demolition Processing Facility.....	20
5.6	Materials Recovery Facility.....	21
5.7	Organics Processing Facility.....	21
5.8	Compost Processing and Storage Area.....	23
5.9	Petroleum Hydrocarbon (PHC) Contaminated Soil Treatment.....	23
5.10	Surplus Soil Management.....	23
5.11	Landfill Component.....	24
5.12	Leachate Pre-treatment Facility .....	25
5.13	Flare and Power Generation Area .....	26
5.13.1	Extraction Plant.....	26
5.13.1.1	Centrifugal Blower .....	26
5.13.1.2	LFG Treatment Facilities .....	27
5.13.1.3	Monitoring Instrumentation and Controls.....	27
5.13.1.4	Air Compressor.....	27
5.13.2	Flare.....	27
5.13.3	Utilization Facility .....	28
<b>6.0</b>	<b>SITE OPERATIONS.....</b>	<b>29</b>
6.1	General Site Operations .....	29
6.1.1	Hours of Operation.....	29
6.1.2	Site Staffing.....	29
6.1.3	Waste Acceptance Procedures.....	29



6.1.4	Handling of Suspect Waste.....	30
6.1.5	Leachate Detection and Secondary Containment System.....	30
6.1.6	Housekeeping and Controls.....	30
6.1.6.1	Dust (Dust Management Plan) .....	30
6.1.6.2	Noise .....	30
6.1.6.3	Litter.....	32
6.1.6.4	Vectors and Vermin .....	32
6.1.7	Complaints Procedure.....	33
6.1.8	Record Keeping .....	34
6.1.9	Winter/Wet Weather Operational Considerations .....	35
6.1.10	Site Equipment.....	35
6.1.11	Fencing .....	35
6.1.12	Signage.....	36
6.1.13	General Site Inspections and Maintenance.....	36
6.1.14	Environmental Emergency and Contingency Plan .....	37
6.1.14.1	Spills.....	37
6.1.14.2	Fire .....	37
<b>7.0</b>	<b>SITE MONITORING AND REPORTING PROGRAMS.....</b>	<b>38</b>
7.1	Groundwater and Leachate Monitoring.....	38
7.2	Surface Water Monitoring .....	38
7.3	Biological Monitoring.....	39
7.4	Noise Monitoring.....	39
7.5	Dust Monitoring.....	40
7.6	Geotechnical Monitoring .....	41
<b>8.0</b>	<b>CONTINGENCY MEASURES AND TRIGGER MECHANISMS .....</b>	<b>42</b>
8.1	Groundwater .....	42
8.2	Surface Water.....	42
8.3	Leachate Pre-Treatment Facility .....	43
<b>9.0</b>	<b>SITE CLOSURE PLAN .....</b>	<b>44</b>
9.1	General Site Closure Plan .....	44



9.1.1 Landfill Final Cover and Seeding ..... 44

9.1.2 Post-Closure Monitoring, Reporting and Maintenance Requirements ..... 45

9.1.3 End Use ..... 45

**10.0 LIMITATIONS AND USE OF REPORT ..... 46**

**11.0 CLOSURE..... 47**

**REFERENCES..... 48**

**TABLES**

Table 1: Waste Quantities ..... 8

Table 2: Description of Receptor Locations..... 11

Table 3: Summary of Sources Assessed as part of the Compliance Assessment ..... 14

Table 4: Predicted Compliance Air Quality Concentrations at POI..... 16

Table 5: Sound Power Data for Landfilling Operations Noise Sources ..... 31

Table 6: Sound Power Data for Ancillary Facilities Noise Sources ..... 31

Table 7: Site Equipment..... 35

Table 8: Leachate Pre-treatment Facility Contingencies ..... 43

**FIGURES**

- Figure 1: Key Plan
- Figure 2: Legal Survey
- Figure 3: Land Use
- Figure 4: Current Zoning
- Figure 5: Topography
- Figure 6: Site Development Plan
- Figure 7: Site Operations Flow Chart
- Figure 8: Noise Screening Berm Locations
- Figure 9: Flare and Power Generation Area Plan
- Figure 10: Proposed Groundwater and Surface Water Monitoring Locations
- Figure 11: Proposed Noise Monitoring Locations



**APPENDICES**

**APPENDIX A**

Stormwater Management System Design Report

**APPENDIX B**

Acoustic Assessment Report

**APPENDIX C**

Emission Summary and Dispersion Modelling Report

**APPENDIX D**

Construction and Demolition Processing Facility Design and Operations

**APPENDIX E**

Materials Recovery Facility Design and Operations

**APPENDIX F**

Organics Processing Facility Design and Operations

**APPENDIX G**

Compost Processing and Storage Area Design and Operations

**APPENDIX H**

Petroleum Hydrocarbon Contaminated Soil Treatment Design and Operations

**APPENDIX I**

Landfill Design and Operations

**APPENDIX J**

On-Site Leachate Pre-treatment Design Report