



IBI GROUP
400–333 Preston Street
Ottawa ON K1S 5N4 Canada
tel 613 225 1311 fax 613 225 9868
ibigroup.com

Memorandum

To/Attention Sakto Corporation **Date** January 10, 2019
From IBI Group **Project No** 100795
cc
Subject Adelaide Expansion (17 Aberdeen Street) - Transportation Overview
Addendum #1

1. Overview

This document serves as an Addendum to a Transportation Overview prepared by IBI Group in August 2016 in support of a Site Plan Application for a proposed residential expansion to the 158-unit *Adelaide* apartment building at 17 Aberdeen Street, located within the Preston Square mixed-use complex. Following the approval of the Site Plan Application, subsequent changes have been made to the development plan triggering the need for a re-submission.

The proposed changes to the site plan are as follows:

- The proposed residential building has been increased in height from 23 storeys to 30 storeys.
- The number of new apartment units has been increased from 197 units to 252 units - an increase of 55 units.

The purpose of this Addendum is to identify the net change in peak hour site-generated traffic associated with the updated site plan and determine if there are any additional impacts as a result.

2. Updated Development-Generated Traffic

For consistency with the previous analysis undertaken for this site, the assumptions used in the Transportation Overview have been carried forward in the estimation of revised site-generated traffic volumes. In recognition of the proximity to rapid transit (Trillium Line), the trip generation values shall be considered conservative.

The 2016 Transportation Overview referenced Institute of Transportation Engineers (ITE) trip generation rates for Land Use Code 220: Apartment. To express the trip generation in terms of person-trips, it was assumed that the data included an inherent 95% driver mode share with an auto-occupancy of 1.2 persons per vehicle resulting in a vehicle to person trip conversion factor of 1.28.

Sakto Corporation – January 10, 2019

Despite the proximity to an existing rapid transit station (Carling) and within the area of influence of the future Gladstone station, the mode share considered for the development was based on the mode share distribution for the Ottawa Inner Area Traffic Assessment Zone (TAZ), as indicated in the 2011 NCR Household Origin-Destination Survey. The mode share distribution for this TAZ is summarized below:

- Auto Driver: 33%
- Auto Passenger: 10%
- Transit: 19%
- Non-Auto: 39%

Based on the above assumptions, the resulting net increase in site-generated traffic during the weekday morning and afternoon peak hours is in the order of 15 and 17 two-way trips, respectively. As indicated in the 2016 study, site-generated traffic is distributed amongst 4 access points to the site on all three of the site's boundary streets and will therefore have a negligible impact on the adjacent road network.

3. On-Site Circulation, Parking & Loading

3.1. On-Site Circulation

The proposed changes to the Adelaide Expansion will require modification to the turning circle at the interior of the site. As indicated on the attached site plan, the building is now proposed to extend over the drive aisle with a punch-through for vehicle circulation. As the turning circle forms part of the site's Fire Route, it has been designed to include a clear 6m drive aisle. Through the design process, vehicle swept-path analyses were undertaken to confirm that the minimum turning radius requirements were exceeded. Pedestrian accessibility will be improved between Tower 1 and Tower 2 with the incorporation of a raised pedestrian pathway.

3.2. Loading

The Loading Zone for the existing Tower 1 (Block 'A') has been reconfigured to permit only LSU (light, single-unit) trucks. This vehicle type represents a typical mail-courier vehicle and is the most common heavy vehicle servicing Tower 1. The loading space has been designed in conformance with minimum by-law requirements (Part 4 of By-Law 2008-250) and will permit this vehicle type to park while not obstructing the fire route. Larger delivery vehicles will be directed to the existing primary loading dock located at Tower 2 (Block 'C').

3.3. Parking

The reconfiguration of the turning circle has resulted in the loss of 4 short-term surface parking spaces as compared with the previous submission. In addition to this, the extended building footprint will impact the below-grade parking facilities due to the requirement for additional support columns, resulting in a further loss of parking spaces. The original transportation study indicated that the proposed development would result in an overall net loss of 26 parking spaces. The total parking supply of the Preston Square Complex will be reduced from the existing 1,068 spaces to 1,015 spaces under the revised design, equating to a net loss of 53 parking spaces.

Sakto Corporation – January 10, 2019

As confirmed by the Parking Study undertaken in support of the 2016 Site Plan Application, the below-grade parking facilities were found to be under-utilized with a peak demand of 77%. The reduction in parking supply would increase this figure to approximately 81%, which remains below the practical capacity of a parking facility. As the site is within proximity of a major LRT station, as indicated by Area Z in By-law 2008-250, the proposed residential development will not require any additional residential parking and may only provide up to 30 visitor parking spaces, many of which already exist.


4. Conclusion

Based on a review of the updated site plan, the proposed increase of 55 units may generate up to 20 additional two-way vehicular trips during the weekday morning and afternoon peak hours, respectively. With consideration that site-generated traffic will be distributed amongst 4 access driveways onto the three boundary streets, the impact of this additional site-generated traffic on the adjacent road network can be considered negligible.

It is the overall opinion of IBI Group that the increase in density proposed for the Adelaide apartment building will have no significant transportation impact. The original study conclusions remain valid and therefore the proposed development can be safely accommodated by the adjacent transportation network.



David Hook, P.Eng.



EXTERIOR PARKING COUNT:

NUMBER OF EXISTING PARKING SPACES:	26
NUMBER OF SPACES TO BE REMOVED:	13
PROPOSED NUMBER OF NEW PARKING SPACES:	09
TOTAL PROPOSED EXTERIOR PARKING SPACES:	22
NET CHANGE IN EXTERIOR PARKING:	-04

LEGEND

- FIRE HYDRANT (FH)
- SIAMESE CONNECTION (SC)
- PROPOSED SIAMESE CONNECTION (SC)
- FIRE DEPARTMENT CONNECTION (FD)

PRESTON SQUARE ZONING TABLE

Current Zoning	TM (2188) H (24.5), TM (2188) H (18.54), MC (107) H (50), MC (107) h (148) ASL, MC (107) H (91) ASL
Site Area	21 060.97 m ²
Dwelling Units	158 Existing / 252 Proposed (228 + 24) (41 928.84m ²)
Existing Retail GFA	854.7m ² (273.6m ² + 425.3m ² + 156.2m ²)
Existing Restaurant GFA	1,539.3m ²
Existing Personal Service GFA	208m ²
Existing Training Centre GFA	412.16m ²
Existing Office GFA	140,910.52m ² (9,854.04m ² in the TM zone + 30,146.48m ² in the MC zone)
Total Existing City GFA	10,179.3m ²
Total Proposed City GFA	14,689.737m ²

	REQUIRED	PROVIDED
Setbacks	No minimum on all sides	N/A
Building Height	Minimum: 6.7m Maximum: 148m ASL	87.975m 152.452m ASL
Amenity Area	Total: 1,182m ² Communal: 591m ²	Indoor Amenity Space: 856.00m ² Outdoor Amenity Space: 338.548m ² Balconies: 0m ² TOTAL: 1194.6m ² (1194.6m ² communal)
Minimum Parking (per By-Law 2016-2490)	30 spaces	1,015 spaces
Residential Visitor	0.1dwelling unit excluding the first 12 units up to a maximum of 30 spaces	
Maximum Parking (per By-Law 2016-2490)	Maximum Permitted: Residential + Visitor: 621 spaces Retail: 31 spaces Office: 75dwelling unit Restaurant: No maximum Personal Service: No maximum Training Centre: No maximum	1,015 spaces
Barrier-Free Parking	500 or more spaces: 6 spaces	15 spaces (included in total count above)
Bicycle Parking	Residential: 0.5dwelling unit 90% can be vertical 25% of residential spaces must be indoors	Existing Spaces: 217 spaces Required for new units: 99 spaces Total new spaces: 108 Vertical: 43 Horizontal: 53+12(Outdoors) % of indoors: 89%
Loading Space	No requirements for residential uses.	N/A
Lot Coverage	(percentage of the site covered by new building footprint)	Site Area 21,061m ² / New Building Footprint 485.97m ² 2.31% coverage
Overall Lot Coverage	(percentage of the site covered by all buildings footprint)	Site Area 21,061m ² / New Building Footprint 9357.3m ² 44.4% coverage
Number of parking spaces being assigned to the residential uses	1,056 total existing, 110 existing residential assigned, 100 additional residential to be assigned for new units as well as 30 spaces for visitor parking for a total of 240 spaces	

CLIENT
SAKTO CORPORATION
910-333 Preston Street, Ottawa, ON, K1S 5N4

COPYRIGHT
The drawings have been prepared solely for the intended use. They are not to be used for any other purpose without the written consent of IBI Group Inc. IBI Group Inc. is not responsible for any errors or omissions in the drawings. The drawings are the property of IBI Group Inc. and shall remain confidential. No part of these drawings may be reproduced, stored in a retrieval system, or transmitted in any form or by any means, electronic, mechanical, photocopying, recording, or by any information storage and retrieval system, without the prior written permission of IBI Group Inc. Any unauthorized use of these drawings is strictly prohibited.

ISSUES

NO.	DESCRIPTION	DATE
1	CLIENT REVIEW	2016-09-19
2	SITE PLAN APPROVAL	2016-09-20
3	SITE PLAN APPROVAL	2017-01-24
4	RE-ISSUED FOR SITE PLAN APPROVAL	2017-05-29
5	ISSUED FOR PLANNING REVIEW	2018-11-30
6	ISSUED FOR REVISED SITE PLAN APPLICATION	2019-01-11

KEYPLAN

CONSULTANTS

PRIME CONSULTANT
IBI GROUP
400-333 Preston Street
Ottawa, ON, K1S 5N4, Canada
416-525-1311 / 1-813-225-9888
ibigroup.com

PROJECT
ADELAIDE TOWER EXPANSION
17 Aberdeen Street
Ottawa, Ontario, Canada
K1S 3J3

PROJECT NO.: 112516

DRAWN BY: IBI
CHECKED BY: H. SEMPLE
PROJECT MGR: IBI
APPROVED BY: Approver
SCALE: As Indicated
DATE: 11/15/18

SHEET TITLE: SITE PLAN

SHEET NUMBER: A003
ISSUE: 6

11/02/2019 3:30:53 PM

C:\Users\Michael.Dougherty\Documents\REV172018\STATE-04-NEW\BLDGE-16_Michael.Dougherty