

NOTES:
1. REMOVE STAKES AND RODENT GUARD AFTER ONE YEAR OR UNTIL TAKEOVER, UNLESS OTHERWISE DIRECTED BY THE LANDSCAPE ARCHITECT.
2. TOPSOIL MIXTURE AND SHREDDED MULCH AS PER SPECIFICATION
3. REMOVE TREE WRAP AFTER PLANTING
4. CALIPER TO BE MEASURED AT THE BASE OF TREE AT ROOT BALL.

1 DECIDUOUS TREE PLANTING
N.T.S.



NOTES:
1. REMOVE STAKES AFTER ONE YEAR OR UNTIL TAKEOVER UNLESS OTHERWISE DIRECTED BY THE LANDSCAPE ARCHITECT.
2. TOPSOIL MIXTURE AND SHREDDED MULCH AS PER SPECIFICATION

2 CONIFEROUS TREE PLANTING ON SLOPE
N.T.S.



NOTES:
1. TOPSOIL MIXTURE AND SHREDDED MULCH AS PER SPECIFICATION.
2. SHRUBS SPECIFIED BARE ROOT (B.R.) TO BE PLANTED SO THAT ROOTS ARE FULLY EXTENDED IN PLANTING HOLE WITH SOIL MIX BACKFILLED CAREFULLY TO PREVENT ROOT DAMAGE.
3. PROVIDE 100mm HIGH EARTH SAUCER AROUND SHRUB BED.
4. STAKES TO BE REMOVED AFTER ONE YEAR OR UNTIL TAKEOVER UNLESS OTHERWISE DIRECTED BY LANDSCAPE ARCHITECT.

3 CONTINUOUS SHRUB BED PLANTING
N.T.S.



NOTES:
1. TOPSOIL MIXTURE AND SHREDDED MULCH AS PER SPECIFICATION.
2. PLANT ALL SPECIMENS SLIGHTLY HIGHER THAN ADJACENT GRADE.
3. ENSURE THE PLANT IS VERTICAL AND ADEQUATELY SUPPORTED.
4. BARE ROOT (B.R.) SPECIMENS:
   - INSTALL PLANT MATERIAL SO THAT ROOTS ARE FULLY EXTENDED IN PLANTING HOLE WITH SOIL MIX BACKFILLED CAREFULLY TO PREVENT ROOT DAMAGE.
   - PROTECT ROOTS FROM WIND AND SUN EXPOSURE, AND BE KEPT MOIST.
   - SOAK ROOTS COMPLETELY PRIOR TO PLANTING AND PLANTED IMMEDIATELY
   - PLANT DURING THE DORMANT SEASON, PREFERABLY PLANT ON CLOUDY, COOL HUMID DAYS.
5. PROVIDE 100mm HIGH EARTH SAUCER AROUND SHRUB BED.
6. STAKES AND RODENT GUARD TO BE REMOVED AFTER ONE YEAR UNLESS OTHERWISE DIRECTED BY LANDSCAPE ARCHITECT.

4 CONTINUOUS SHRUB BED PLANTING SLOPE
N.T.S.



NOTES:
1. TOPSOIL MIXTURE AND SHREDDED MULCH AS PER SPECIFICATION.
2. PROVIDE 100mm HIGH EARTH SAUCER AROUND SHRUB BED.
3. STAKES TO BE REMOVED AFTER ONE YEAR OR UNTIL TAKEOVER UNLESS OTHERWISE DIRECTED BY LANDSCAPE ARCHITECT.

5 MULTI-STEM TREE
N.T.S.



NOTES:
1. TOPSOIL MIXTURE AND SHREDDED MULCH AS PER SPECIFICATION.
2. PROVIDE 100mm HIGH EARTH SAUCER AROUND PERENNIAL/GRASS BED.

6 PERENNIAL AND ORNAMENTAL GRASS PLANTING
N.T.S.



NOTES:
1. BARE ROOT SHOULD BE PLANTED DURING THE DORMANT SEASON. PREFERABLY PLANT ON CLOUDY, COOL HUMID DAYS.
2. PROTECT ROOTS FROM WIND AND SUN EXPOSURE. BARE ROOTS SHOULD BE KEPT MOIST AND PLANTED IMMEDIATELY.
3. SOAK ROOTS COMPLETELY PRIOR TO PLANTING.
4. ENSURE THE PLANT IS VERTICAL AND ADEQUATELY SUPPORTED.
5. REMOVE STAKES AND RODENT GUARD AFTER ONE YEAR OR UNTIL TAKEOVER, UNLESS OTHERWISE DIRECTED BY THE LANDSCAPE ARCHITECT.
6. TOPSOIL MIXTURE AND SHREDDED MULCH AS PER SPECIFICATION
7. REMOVE TREE WRAP AFTER PLANTING

7 DECIDUOUS WHIP PLANTING
N.T.S.



8 CONCRETE SIDEWALK
N.T.S.

MAGLIN
ICONIC COLLECTION: MBR-2300-00001 BIKE RACK



9 BIKE RACK
N.T.S.



SECTION VIEW

NOTES:
1. CONTRACTOR TO REFER TO ARCHITECTURAL SPECIFICATIONS FOR COLOUR, FINISH AND ADDED VALUE FEATURES
2. SUBMIT COLOUR AND FINISH SAMPLES FOR APPROVAL
3. WEIGHT OF CUBIC CU TILT BENCH – 1900lbs



ELEVATION VIEW

10 CU-TILT CONCRETE BENCH
N.T.S.



NOTES:
1. FOR PAVER TYPE REFER TO SPECIFICATIONS. PAVERS SHALL BE INSTALLED IN STRICT ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS WITH TIGHT BUTT JOINTS OF APPROXIMATELY 3mm, ON A SAND BASE. SAW CUT PAVERS AS REQUIRED. USE AN APPROVED VIBRATORY COMPACTOR IN A CIRCULAR PATTERN.
2. ALL DAMAGED OR CHIPPED PAVERS MUST BE REPLACED AT THE CONTRACTOR'S COST.
3. EXCAVATE AND REMOVE ALL TOPSOIL AND UNSTABLE MATERIALS OFF SITE. SUBGRADE TO BE GRADED TO SIMILAR CONTOURS AS FINISH GRADE. COMPACT SUBGRADE TO 95% S.P.D. PLACE 150mm LAYER OF GRANULAR 'A' COMPACTED TO 100% S.P.D.
4. PLACE MAXIMUM 25mm UNCOMPACTED SAND FOR LEVELLING COURSE.
5. INSTALL PAVING UNITS IN THE PATTERN AS SPECIFIED PER MANUFACTURER'S PATTERN RECOMMENDATION AND SPECIFICATIONS.
6. RETAIN EDGING WITH RIGID PAVER EDGE RESTRAINTS AS PER SPECIFICATIONS.

11 LIGHT DUTY UNIT PAVING
N.T.S.



Contractor shall check all dimensions on the work and report any discrepancy to the Landscape Architect before proceeding. All drawings and specifications are the property of the Landscape Architect and must be returned at the completion of the work. This drawing is not to be used for construction until signed by the Landscape Architect.

Key Plan


FUTURE COMMERCIAL
FUTURE COMMERCIAL
FUTURE COMMERCIAL