

4497 O’Keefe Court

Transportation Impact Assessment

Step 1 Screening Report

Step 2 Scoping Report

Step 3 Strategy Report

Prepared for:

Mattamy Homes Canada
50 Hines Road, Suite 100
Ottawa, ON K2K 2M5

Prepared by:



6 Plaza Court
Ottawa, ON K2H 7W1

September 2024

PN: 2023-105

Table of Contents

| | | |
|-------|--|----|
| 1 | Screening | 1 |
| 2 | Existing and Planned Conditions | 1 |
| 2.1 | Proposed Development..... | 1 |
| 2.2 | Existing Conditions | 3 |
| 2.2.1 | Area Road Network..... | 3 |
| 2.2.2 | Existing Intersections | 3 |
| 2.2.3 | Existing Driveways | 4 |
| 2.2.4 | Cycling and Pedestrian Facilities..... | 4 |
| 2.2.5 | Existing Transit..... | 7 |
| 2.2.6 | Existing Area Traffic Management Measures..... | 8 |
| 2.2.7 | Existing Peak Hour Travel Demand..... | 8 |
| 2.2.8 | Collision Analysis..... | 11 |
| 2.3 | Planned Conditions..... | 14 |
| 2.3.1 | Changes to the Area Transportation Network | 14 |
| 2.3.2 | Other Study Area Developments | 14 |
| 3 | Study Area and Time Periods | 15 |
| 3.1 | Study Area | 15 |
| 3.2 | Time Periods | 16 |
| 3.3 | Horizon Years..... | 16 |
| 4 | Development-Generated Travel Demand | 16 |
| 4.1 | Mode Shares..... | 16 |
| 4.1.1 | Typical Area Mode Shares | 16 |
| 4.1.2 | Proposed Development Mode Shares | 16 |
| 4.2 | Trip Generation | 18 |
| 4.3 | Trip Distribution..... | 20 |
| 4.4 | Trip Assignment..... | 20 |
| 5 | Exemption Review | 22 |
| 6 | Development Design | 24 |
| 6.1 | Design for Sustainable Modes | 24 |
| 6.2 | New Street Networks | 26 |
| 6.2.1 | New Collector Road | 26 |
| 6.2.2 | New Local Roads..... | 27 |
| 6.2.3 | Traffic Calming | 27 |
| 7 | Transportation Demand Management | 28 |
| 7.1 | Context for TDM | 28 |
| 7.2 | Need and Opportunity..... | 29 |
| 7.3 | TDM Program | 29 |
| 8 | Background Network Travel Demands..... | 29 |
| 8.1 | Transportation Network Plans | 29 |
| 8.2 | Background Growth..... | 29 |
| 8.3 | Other Developments | 30 |
| 9 | Demand Rationalization | 30 |

| | | |
|--------|---|----|
| 9.1 | 2038 Future Background Operations | 30 |
| 9.1.1 | Future Background 2038 Mitigation Measures | 33 |
| 9.2 | 2038 Future Total Operations | 34 |
| 9.2.1 | Future Total 2038 Mitigation Measures | 37 |
| 9.3 | Demand Rationalization Conclusions | 38 |
| 9.3.1 | Background Travel Demand | 38 |
| 9.3.2 | Development Travel Demand | 38 |
| 10 | Transit | 38 |
| 10.1 | Route Capacity | 38 |
| 10.2 | Transit Priority | 41 |
| 11 | Network Concept | 42 |
| 12 | Intersection Design | 43 |
| 12.1 | Intersection Control | 43 |
| 12.2 | Intersection Design | 44 |
| 12.2.1 | 2038 Future Total Intersection Operations | 44 |
| 12.2.2 | Intersection MMLOS | 44 |
| 12.2.3 | Recommended Design Elements | 44 |
| 13 | Summary of Improvements Indicated and Modifications Options | 45 |
| 14 | Conclusion | 49 |

List of Figures

| | |
|--|----|
| Figure 1: Area Context Plan | 1 |
| Figure 2: Concept Plan | 2 |
| Figure 3: Study Area Pedestrian Facilities | 5 |
| Figure 4: Study Area Cycling Facilities | 5 |
| Figure 5: Existing Pedestrian Volumes | 6 |
| Figure 6: Existing Cyclist Volumes | 6 |
| Figure 7: Existing Study Area Transit Service | 7 |
| Figure 8: Existing Study Area Transit Stops | 8 |
| Figure 9: Existing Traffic Counts | 9 |
| Figure 10: Study Area Collision Records, 2018-2022 | 12 |
| Figure 11: New Site Generation Auto Volumes | 21 |
| Figure 12: Pass-by Auto Volumes | 22 |
| Figure 13: Internal Pedestrian and Cycling Network | 25 |
| Figure 14: Area Active Transportation Connections | 26 |
| Figure 15: Main Street Cross-Section | 27 |
| Figure 16: Designing Neighbourhood Collector Streets Cross-Section 26A | 27 |
| Figure 17: Proposed Key Traffic Calming Measures | 28 |
| Figure 18: 2038 Future Background Volumes | 31 |
| Figure 19: 2038 Future Total Volumes | 35 |
| Figure 20: Proposed Transit Routes | 39 |
| Figure 21: Proposed Bus Stop Locations | 41 |

Table of Tables

| | |
|--|----|
| Table 1: Intersection Count Data..... | 8 |
| Table 2: Existing Intersection Operations..... | 9 |
| Table 3: Study Area Collision Summary, 2018-2022 | 11 |
| Table 4: Summary of Collision Locations, 2018-2022 | 12 |
| Table 5: Fallowfield Road at Strandherd Drive Collision Summary | 13 |
| Table 6: Fallowfield Road at Cedarview Road Collision Summary | 13 |
| Table 7: TRANS Trip Generation Manual Recommended Mode Shares – South Nepean | 16 |
| Table 8: Proposed Development Mode Shares – Locally-Oriented Community..... | 17 |
| Table 9: Trip Generation Person Trip Rates by Peak Period..... | 18 |
| Table 10: Total Residential Person Trip Generation by Peak Period | 18 |
| Table 11: Internal Capture Rates | 18 |
| Table 12: Trip Generation by Mode | 19 |
| Table 13: OD Survey Distribution – South Nepean | 20 |
| Table 14: Exemption Review | 22 |
| Table 15: TRANS Regional Model Projections – Study Area Growth Rates..... | 30 |
| Table 16: Recommended Area Growth Rates | 30 |
| Table 17: 2038 Future Background Intersection Operations | 31 |
| Table 18: 2038 Future Background Intersection Operations – Mitigated..... | 33 |
| Table 19: 2038 Future Total Intersection Operations | 35 |
| Table 20: 2038 Future Total Intersection Operations – Mitigated..... | 37 |
| Table 21: Trip Generation by Transit Mode | 39 |
| Table 22: Cedarview Forecasted Transit Service – Minimum Bus Requirements..... | 40 |
| Table 23: AM Peak Hour Directional Screenline Analysis..... | 42 |
| Table 24: Study Area Intersection MMLOS Analysis | 44 |

List of Appendices

| |
|--|
| Appendix A – TIA Screening Form and Certification Form |
| Appendix B – Turning Movement Count Data |
| Appendix C – Synchro Intersection Worksheets – Existing Conditions |
| Appendix D – Signal Warrant |
| Appendix E – Collision Data |
| Appendix F – TDM Checklist |
| Appendix G – TRANS Model Plots |
| Appendix H – Background Development Volumes |
| Appendix I – Synchro Intersection Worksheets – 2038 Future Background Conditions |
| Appendix J – Turn-Lane Warrants |
| Appendix K – Synchro Intersection Worksheets –Future Background 2038 Mitigation Measures |
| Appendix L – Synchro Intersection Worksheets – 2038 Future Total Conditions |
| Appendix M – Synchro Intersection Worksheets –Future Total 2038 Mitigation Measures |
| Appendix N – TRANS Screenline 9 |
| Appendix O – MMLOS Analysis |

1 Screening

This study has been prepared according to the City of Ottawa's 2017 Transportation Impact Assessment (TIA) Guidelines, incorporating the 2023 Revision to Transportation Impact Assessment Guidelines. Accordingly, a Step 1 Screening Form has been prepared and is included as Appendix A, along with the Certification Form for the TIA Study PM. As shown in the Screening Form, a TIA is required including the Design Review component and the Network Impact Component. This study has been prepared to support an Official Plan Amendment.


2 Existing and Planned Conditions

2.1 Proposed Development

The development site is located at 4497 O'Keefe Court is currently zoned as Rural Zones (RR4, RR4 [647, 648, 649r]), Open Space and Leisure Zones (O1, O1A), and Environmental Zone (EP3). The development concept is for a new urban community comprising a mix of densities, from detached dwellings to mid-rise condo blocks. Residential-supportive land uses are proposed as being integrated into the community's higher density southern area, where a fifteen-minute community is envisioned. A new collector road serving the community is proposed to connect O'Keefe Court to Onassa Circle.

Figure 1 illustrates the study area context. Figure 2 illustrates the proposed concept plan.

Figure 1: Area Context Plan



Source: <http://maps.ottawa.ca/geoOttawa/> Accessed: May 28, 2024

Figure 2: Concept Plan



2.2 Existing Conditions

2.2.1 Area Road Network

Fallowfield Road: Fallowfield Road is a City of Ottawa arterial road with a four-lane rural cross-section west of Citigate Drive, and a two-lane rural cross-section including paved shoulders north of Strandherd Drive. A multi-use pathway (MUP) is provided on the west side of the road between O'Keefe Court and Forager Street, with an off-road MUP continuing from O'Keefe Court to Cedarview Road on the north side of Fallowfield Road. The posted speed limit is 60 km/h north of Strandherd Drive and 80 km/h west of Citigate Drive. The Ottawa Official Plan reserves a 44.5 metre right-of-way north of Strandherd Drive within the study area and the measured right-of-way is 48.0 metres west of Citigate Drive. Fallowfield Road is designated as a truck route.

Strandherd Drive: Strandherd Drive is a City of Ottawa arterial road with a four-lane, divided urban cross-section including cycletracks and sidewalks on both sides of the road. The posted speed limit is 80 km/h and the Ottawa Official Plan reserves a 44.5 metre right of way within the study area. Strandherd Drive is designated as a truck route.

Cedarview Road: Cedarview Road is a City of Ottawa arterial road north of Fallowfield Road, a major collector road between Fallowfield Road and Jockvale Road, a collector road south of Jockvale Road and a local road south of Kennevale Road. Cedarview Road has a two-lane rural cross-section, with paved shoulders north of Fallowfield Drive, and gravel shoulders to the south. South of Fallowfield Road, a MUP is provided on the east side of the road. The posted speed limit is 60 km/h north of Fallowfield Road and 40 km/h south of Fallowfield Road. The Ottawa Official Plan reserves a 37.5 metre right of way north of Fallowfield Road, a 26.0 metre right of way between Fallowfield Road and Jockvale Road, and a 24.0 metre right of way south of Jockvale Road. Cedarview Road is designated as a truck route north of Fallowfield Road.

Citigate Drive: Citigate Drive is a City of Ottawa major collector road with a two-lane urban cross-section. A sidewalk is provided along the west side of the road and a MUP is provided on the east side of the road South of CrossKeys Place. The unposted speed limit is assumed to be 50 km/h and the existing right of way is 24.0 metres north of CrossKeys Place, and 26.0 metres south of CrossKeys Place.

O'Keefe Court: O'Keefe Court is a City of Ottawa local road with a two-lane rural cross-section including gravel shoulders. An off-road MUP is provided on the north side of O'Keefe Court between Fallowfield Road and Lytle Park. The unposted speed limit is assumed to be 50 km/h and the existing right of way varies between 30.0 metres and 31.0 metres within the study area.

Cobble Hill Drive: Cobble Hill Drive is a City of Ottawa local road with a two-lane urban cross-section. Sidewalks are provided on both sides of the road. The unposted speed limit is assumed to be 50 km/h and the existing right of way is 21.5 metres.

Onassa Circle: Onassa Circle is a City of Ottawa local road with a two-lane rural cross-section. The posted speed limit is 40 km/h and the existing right of way is 20.0 metres.

2.2.2 Existing Intersections

The key study area intersections have been summarized below:

Cedarview Road at Onassa Circle

The intersection of Cedarview Road at Onassa Circle is an unsignalized T-intersection with stop control on the minor approach of Onassa Circle. The northbound approach consists of a shared left-turn/through lane, and the southbound approach consists of a shared through/right-turn lane. The eastbound approach consists of a shared

all-movements lane which is separated from the receiving lane on this leg by a median. No turn restrictions were noted.

Fallowfield Road/Citigate Drive at Strandherd Drive

The intersection of Fallowfield Road/Citigate Drive at Strandherd Drive is a signalized intersection. The northbound approach of Citigate Drive consists of two auxiliary left-turn lanes and a shared through/right-turn lane, and the southbound approach of Fallowfield Road consists of an auxiliary left-turn lane, a through lane, and an auxiliary channelized right-turn lane. The eastbound approach of Fallowfield Road consists of two auxiliary left-turn lanes, two through lanes, an auxiliary right-turn lane, and a cycletrack, and the westbound approach of Strandherd Drive consists of an auxiliary left-turn lane, two through lanes, an auxiliary right-turn lane, and a cycletrack. No turn restrictions were noted.

Fallowfield Road at O'Keefe Court/Cobble Hill Drive

The intersection of Fallowfield Road at O'Keefe Court/Cobble Hill Drive is an unsignalized intersection with stop control on the minor approaches of O'Keefe Court and Cobble Hill Drive. The northbound approach, considered as Cobble Hill Drive within this TIA consists of a shared all-movements lane and the southbound approach of O'Keefe Court consists of an auxiliary left-turn lane and a shared through/right-turn lane. The eastbound approach of Fallowfield Road consists of an auxiliary left-turn lane, a through lane, and a right-turn lane, and the westbound approach of Fallowfield Road consists of an auxiliary left-turn lane, a through lane, a pocket bike lane, and an auxiliary right-turn lane. No turn restrictions were noted.

Fallowfield Road at Cedarview Road

The intersection of Fallowfield Road at Cedarview Road is a signalized intersection. The northbound approach consists of an auxiliary left-turn lane, a through lane, and an auxiliary right-turn lane, and the southbound approach consists of an auxiliary left-turn lane and a shared through/right-turn lane. The eastbound and westbound approaches each consist of an auxiliary left-turn lane, a through lane, and an auxiliary right-turn lane. No turn restrictions were noted.

2.2.3 Existing Driveways

Within 200 metres of the proposed site accesses, driveways to four detached dwellings are present on Trilby Court. Just beyond 200 metres from the proposed connection to O'Keefe Court, a driveway to Lytle Park is present.

2.2.4 Cycling and Pedestrian Facilities


Figure 3 illustrates the pedestrian facilities in the study area and Figure 4 illustrates the cycling facilities.

Sidewalks are provided along both sides of Strandherd Drive and Cobble Hill Drive, and along the west side of Citigate Drive. A sidewalk is provided on the south side of Fallowfield Road for approximately 155 metres west of Citigate Drive.

Cycling facilities include cycletracks along both sides of Strandherd Drive, and a cycletrack on the south side of Fallowfield Road for approximately 155 metres west of Citigate Drive. Paved shoulders are provided along Fallowfield Road north of Strandherd Drive and Cedarview Road north of Fallowfield Road within the study area. A MUP is present along the east side of Cedarview Road south of Fallowfield Road and on the east side of Citigate


Drive south of CrossKeys Place. An off-road MUP also exists on the north side of Fallowfield Road west of Cedarview Road, continuing along O'Keefe Court to Lytle Park. This MUP circulates Lytle Park and continues as a gravel pathway is along the western edge of the 4497 O'Keefe Court parcel and along the hydro corridor to connect to Lytle Avenue. Within the 2023 Transportation Master Plan – Part 1, Strandherd Drive is designated as a cross-town bikeway.

Figure 3: Study Area Pedestrian Facilities



Source: <http://maps.ottawa.ca/geoOttawa/> Accessed: May 28, 2024

Figure 4: Study Area Cycling Facilities



Source: <http://maps.ottawa.ca/geoOttawa/> Accessed: May 28, 2024

Pedestrian and cyclist volumes included in study area intersection counts, presented in Section 2.2.7, have been compiled and are illustrated in Figure 5 and Figure 6, respectively.

Figure 5: Existing Pedestrian Volumes





Figure 6: Existing Cyclist Volumes




2.2.5 Existing Transit

Figure 7 illustrates the transit system map in the study area and Figure 8 illustrates the transit stops within one kilometre from the centroid of the site. All transit information is from May 28, 2024 and is included for general information purposes and context to the surrounding area.

Within the study area, the route #110 travels along Strandherd Drive and the route #272 travels along Cobble Hill Drive. Routes presently service the Citigate employment lands are routes #99 and #170. None of these routes presently stop within walking distance of the proposed development. The frequency of these routes based on May 28, 2024 service levels are:


- Route # 99 – Two morning buses and two late evening buses per day
- Route # 110 – 30-minute service all-day
- Route # 170 – 30-minute service all-day
- Route # 272 – Six morning buses and eight afternoon/evening buses per day in the peak direction

Figure 7: Existing Study Area Transit Service



Source: <http://www.octranspo.com/> Accessed: May 28, 2024

Figure 8: Existing Study Area Transit Stops



Source: <http://www.octranspo.com/> Accessed: May 30, 2024

2.2.6 Existing Area Traffic Management Measures

There are no existing area traffic management measures within the study area.

2.2.7 Existing Peak Hour Travel Demand

Existing turning movement counts were acquired from the City of Ottawa and Accu-Traffic Inc. for the existing study area intersections. Table 1 summarizes the intersection count dates.

Table 1: Intersection Count Date

| Intersection | Count Date | Source |
|---|--------------------------|-------------------|
| Cedarview Road at Onassa Circle | Wednesday, July 18, 2023 | Accu-Traffic Inc. |
| Fallowfield Road at Cedarview Road | Tuesday, January 7, 2020 | City of Ottawa |
| Fallowfield Road at O'Keefe Court/ Cobble Hill Drive | Wednesday, June 7, 2020 | City of Ottawa |
| Fallowfield Road/Citigate Drive at Strandherd Drive | Wednesday, July 18, 2023 | Accu-Traffic Inc. |

Figure 9 illustrates the existing traffic counts and Table 2 summarizes the existing intersection operations. The level of service for signalized intersections is based on volume to capacity ratio (v/c) calculations for individual lane movements and HCM 2000 v/c calculations for the overall intersection, and average delay for unsignalized intersections. Detailed turning movement count data is included in Appendix B and the Synchro worksheets are provided in Appendix C.

Figure 9: Existing Traffic Counts




Table 2: Existing Intersection Operations

| Intersection | Lane | AM Peak Hour | | | | PM Peak Hour | | | |
|--|---------|--------------|------|-----------|-----------------------|--------------|------|-----------|-----------------------|
| | | LOS | V/C | Delay (s) | Q (95 th) | LOS | V/C | Delay (s) | Q (95 th) |
| Cedarview Road at Onassa Circle <i>Unsignalized</i> | EBL/R | B | 0.05 | 12.6 | 0.8 | B | 0.08 | 14.5 | 1.5 |
| | NBL/T | A | 0.01 | 7.9 | 0.0 | A | 0.00 | 8.6 | 0.0 |
| | SBT/R | - | - | - | - | - | - | - | - |
| | Overall | A | - | 0.6 | - | A | - | 0.6 | - |

| Intersection | Lane | AM Peak Hour | | | | PM Peak Hour | | | |
|--|----------------|--------------|-------------|-------------|-----------------------|--------------|-------------|-------------|-----------------------|
| | | LOS | V/C | Delay (s) | Q (95 th) | LOS | V/C | Delay (s) | Q (95 th) |
| Fallowfield Road/Citigate Drive at Strandherd Drive <i>Signalized</i> | EBL | C | 0.77 | 54.7 | 66.7 | D | 0.81 | 62.4 | #75.9 |
| | EBT | A | 0.36 | 11.9 | 84.5 | D | 0.86 | 36.9 | #246.5 |
| | EBR | A | 0.12 | 1.6 | 6.2 | A | 0.25 | 6.8 | 21.4 |
| | WBL | A | 0.12 | 57.2 | 7.3 | A | 0.07 | 56.2 | 4.6 |
| | WBT | F | 1.07 | 81.7 | #295.0 | F | 1.24 | 155.3 | #227.6 |
| | WBR | A | 0.08 | 0.2 | 0.0 | A | 0.22 | 2.8 | 5.3 |
| | NBL | A | 0.22 | 56.5 | 9.7 | A | 0.52 | 50.3 | #60.3 |
| | NBT/R | A | 0.13 | 47.9 | 11.6 | A | 0.58 | 59.0 | 41.2 |
| | SBL | A | 0.22 | 44.5 | 22.8 | A | 0.31 | 40.3 | 39.7 |
| | SBT | A | 0.16 | 45.4 | 14.4 | A | 0.28 | 42.2 | 25.7 |
| | SBR | D | 0.83 | 20.9 | 41.8 | D | 0.88 | 29.8 | 63.4 |
| | Overall | D | 0.89 | 48.3 | - | E | 0.91 | 69.0 | - |
| Fallowfield Road at O'Keefe Court/Cobble Hill Drive <i>Unsignalized</i> | EBL | A | 0.02 | 8.6 | 0.8 | A | 0.03 | 9.3 | 0.8 |
| | EBT | - | - | - | - | - | - | - | - |
| | EBR | - | - | - | - | - | - | - | - |
| | WBL | A | 0.02 | 8.9 | 0.8 | A | 0.06 | 9.0 | 1.5 |
| | WBT | - | - | - | - | - | - | - | - |
| | WBR | - | - | - | - | - | - | - | - |
| | NB | D | 0.35 | 25.3 | 11.3 | D | 0.38 | 33.5 | 12.0 |
| | SBL | E | 0.06 | 37.0 | 1.5 | E | 0.09 | 48.8 | 2.3 |
| | SBT/R | B | 0.06 | 14.9 | 1.5 | C | 0.07 | 17.7 | 1.5 |
| | Overall | A | - | 2.6 | - | A | - | 2.7 | - |
| Fallowfield Road at Cedarview Road <i>Signalized</i> | EBL | A | 0.10 | 9.0 | 9.3 | A | 0.15 | 14.9 | 7.6 |
| | EBT | C | 0.73 | 18.4 | #172.1 | A | 0.49 | 16.6 | 72.8 |
| | EBR | A | 0.01 | 0.0 | 0.0 | A | 0.04 | 2.4 | 2.9 |
| | WBL | A | 0.14 | 10.6 | 7.8 | A | 0.40 | 17.8 | 31.3 |
| | WBT | A | 0.42 | 11.0 | 65.9 | D | 0.82 | 28.0 | #168.1 |
| | WBR | A | 0.20 | 2.0 | 8.9 | A | 0.11 | 3.7 | 7.3 |
| | NBL | A | 0.20 | 26.2 | 14.8 | A | 0.21 | 24.8 | 8.6 |
| | NBT | C | 0.71 | 39.7 | 59.6 | A | 0.17 | 20.2 | 21.3 |
| | NBR | A | 0.49 | 14.4 | 26.4 | A | 0.13 | 5.7 | 8.0 |
| | SBL | B | 0.65 | 47.2 | 30.3 | B | 0.69 | 34.3 | 63.0 |
| | SBT/R | A | 0.22 | 22.6 | 18.3 | D | 0.89 | 46.5 | #125.9 |
| | Overall | C | 0.72 | 19.1 | - | D | 0.85 | 27.5 | - |

Notes: Saturation flow rate of 1800 veh/h/lane
Queue is measured in metres
Peak Hour Factor = 0.90

Delay = average vehicle delay in seconds
m = metered queue
= volume for the 95th %ile cycle exceeds capacity

At the intersection of Fallowfield Road/Citigate Drive at Strandherd Drive, during the AM peak hour, the westbound through movement is over theoretical capacity and may be subject to high delays and extended queues. During the PM peak hour at this intersection, the westbound through movement is over theoretical capacity and may be subject to high delays and extended queues, and extended queues may be observed on the eastbound left, eastbound through, and northbound left movements.

At the intersection of Fallowfield Road at Cedarview Road, extended queues may be observed on the eastbound through movement during the AM peak hour, and on the westbound through and southbound through/right movements during the PM peak hour.

The intersection of Fallowfield Road at O'Keefe Court/Cobble Hill Drive is understood be under monitoring by City staff for signal implementation. A signal warrant analysis was performed for the intersection of Fallowfield Road at O'Keefe Court/ Cobble Hill Drive for the existing conditions, which was found not to meet warrants. Signal warrants are provided in Appendix D.

2.2.8 Collision Analysis

Collision data have been acquired from the City of Ottawa open data website (data.ottawa.ca) for five years prior to the commencement of this TIA for the surrounding study area road network. Table 3 summarizes the collision types and conditions in the study area, Figure 10 illustrates the area collisions, and Table 4 summarizes the total collisions for each of the locations analyzed. Collision data are included in Appendix E.

Table 3: Study Area Collision Summary, 2018-2022

| | | Number | % |
|-------------------------------|-----------------------------|-----------|-------------|
| Total Collisions | | 74 | 100% |
| Classification | Fatality | 0 | 0% |
| | Non-Fatal Injury | 15 | 20% |
| | Property Damage Only | 59 | 80% |
| Initial Impact Type | Angle | 7 | 9% |
| | Rear end | 39 | 53% |
| | Sideswipe | 7 | 9% |
| | Turning Movement | 9 | 12% |
| | SMV Other | 11 | 15% |
| | Other | 1 | 1% |
| Road Surface Condition | Dry | 52 | 70% |
| | Wet | 12 | 16% |
| | Loose Snow | 5 | 7% |
| | Slush | 2 | 3% |
| | Packed Snow | 2 | 3% |
| | Ice | 1 | 1% |
| Pedestrian Involved | | 0 | 0% |
| Cyclists Involved | | 0 | 0% |

Figure 10: Study Area Collision Records, 2018-2022




Table 4: Summary of Collision Locations, 2018-2022

| Intersections / Segments | Number | % |
|---|-----------|-------------|
| Fallowfield Road at Strandherd Drive | 74 | 100% |
| Fallowfield Road at Cedarview Road | 42 | 57% |
| Cedarview Road between Fallowfield Road and Woodsia Avenue | 21 | 28% |
| Fallowfield Road at O'Keefe Court/Cobble Hill Drive | 4 | 5% |
| Fallowfield Road between Cedarview Road and O'Keefe Court | 3 | 4% |
| O'Keefe Court between Foxtail Avenue and End | 2 | 3% |
| Cedarview Road between Cedarhill Drive and Lyle Avenue | 1 | 1% |

Within the study area, the intersections of Fallowfield Road at Strandherd Drive and Fallowfield Road at Cedarview Road are noted to have experienced higher collisions than other locations. Table 5 and Table 6 summarize the collision types and conditions for each of the locations.

Table 5: Fallowfield Road at Strandherd Drive Collision Summary

| Total Collisions | | Number | % |
|------------------------|----------------------|-----------|-------------|
| | | 42 | 100% |
| Classification | Fatality | 0 | 0% |
| | Non-Fatal Injury | 7 | 17% |
| | Property Damage Only | 35 | 83% |
| Initial Impact Type | Angle | 4 | 10% |
| | Rear end | 27 | 64% |
| | Sideswipe | 6 | 14% |
| | Turning Movement | 2 | 5% |
| | SMV Other | 3 | 7% |
| Road Surface Condition | Dry | 29 | 69% |
| | Wet | 5 | 12% |
| | Loose Snow | 4 | 10% |
| | Slush | 2 | 5% |
| | Packed Snow | 1 | 2% |
| | Ice | 1 | 2% |
| Pedestrian Involved | | 0 | 0% |
| Cyclists Involved | | 0 | 0% |

The Fallowfield Road at Strandherd Drive intersection had a total of 42 collisions during the 2018-2022 time period, with 35 involving property damage only and the remaining seven having non-fatal injuries. The collision types are most represented by rear end 27 with collisions, followed by six sideswipe collisions, four angle collisions, three SMV other collisions, and the remaining two turning movement collisions. Rear end and sideswipe collisions are typically associated with congestion, and no other patterns are noted. Weather conditions do not affect collisions at this location. No further review of collisions at this location is required as part of this study.

Table 6: Fallowfield Road at Cedarview Road Collision Summary

| Total Collisions | | Number | % |
|------------------------|----------------------|-----------|-------------|
| | | 21 | 100% |
| Classification | Fatality | 0 | 0% |
| | Non-Fatal Injury | 4 | 19% |
| | Property Damage Only | 17 | 81% |
| Initial Impact Type | Angle | 3 | 14% |
| | Rear end | 10 | 48% |
| | Sideswipe | 1 | 5% |
| | Turning Movement | 6 | 29% |
| | Other | 1 | 5% |
| Road Surface Condition | Dry | 15 | 71% |
| | Wet | 5 | 24% |
| | Loose Snow | 1 | 5% |
| Pedestrian Involved | | 0 | 0% |
| Cyclists Involved | | 0 | 0% |

The Fallowfield Road at Cedarview Road intersection had a total of 21 collisions during the 2018-2022 time period, with 17 involving property damage only and the remaining four having non-fatal injuries. The collision types are most represented by rear end with ten collisions, followed by six turning movement collisions, three angle collisions, and one collision each for sideswipe and other type collisions. As previously stated, rear end collisions are typically associated with congestion. Five of the six turning movement collisions were recorded in 2018, with

one recorded in 2019 and none recorded in the following three years. Weather conditions do not affect collisions at this location and no further examination is required as part of this study.

2.3 Planned Conditions

2.3.1 Changes to the Area Transportation Network

2.3.1.1 *Signalization of Fallowfield Road at O'Keefe Court/Cobble Hill Drive*

The intersection of Fallowfield Road at O'Keefe Court/Cobble Hill Drive is planned for signalization in the future based on monitoring by the City. No additional modifications beyond the intersection control are understood to be planned at this time. It is anticipated that once warrants are met, this modification will be undertaken by the City.

2.3.1.2 *Barnsdale Interchange*

The environmental assessment study and preliminary design for an interchange at the intersection of Highway 416 and Barnsdale Road was completed in September 2023. The ultimate configuration is a partial cloverleaf interchange on the south side of Barnsdale Road, a 4-lane bridge over Highway 416. The interim configurations will be subject to traffic demands and it is expected that the free flow ramps on the north side of Barnsdale Road will not be constructed as part of this configuration and are a long-term improvement once warranted. The new interchange will be an effective highway access point for most residents and businesses in Barrhaven South, and reduce demands associated with the Fallowfield interchange. The interim buildout horizon for the new facility is understood to be 2029.

2.3.1.3 *Chapman Mills Drive BRT*

The median BRT corridor along the Chapman Mills Drive will be extended across the Kennedy-Burnett Stormwater Management Facility to the 90-degree bend of Chapman Mills Drive, and to continue westward as a dedicated BRT corridor to meet Barnsdale Road. This facility is anticipated to be completed before 2038.

2.3.1.4 *Realigned Greenbank Road and BRT*

Greenbank Road is planned to be realigned south of the existing Jockvale Road and to connect to Cambrian Road in an interim horizon, and to Barnsdale Road in the ultimate conditions. The cross-section will include median BRT which will connect to the existing BRT line at Barrhaven Town Centre. It assumed that this improvement will not be completed by 2038, and confirmation from the City of any anticipated timelines is requested.

2.3.1.5 *Stage 3 LRT*

The future extension of the LRT line from Baseline Station is part of the Ultimate Transit Network, as depicted in Schedule C2 of the Official Plan. This improvement will replace the existing BRT service with LRT service between Barrhaven Town Centre, which will include a transfer station to from the new LRT line to the BRT lines to the east, west, and south of this point. No timeline for implementation is currently known for this project, which will be confirmed through the upcoming TMP Part 2. It is assumed that buildout will occur after 2038.

2.3.2 Other Study Area Developments

115 Lusk Street

The proposed development application includes a site plan to construct a 3,014 sq. ft restaurant and a 6,103 sq. ft medical office. The development was forecast to be built out in 2023, though is yet to be constructed, and to generate 13 new AM and 32 new PM peak hour two-way auto trips. (IBI Group, 2021)

135 Lusk Street

The proposed development application includes a site plan to construct a 99 rooms hotel. The development was forecast to be built out in 2023, though is yet to be constructed, and to generate 42 new AM and 53 new PM peak hour two-way auto trips. (IBI Group, 2021)

140 Lusk Street

The proposed development application includes a site plan to construct a hotel with 88 rooms. The development was forecast to be built out in 2023, though is yet to be constructed, and to generate 36 new AM and 45 new PM two-way peak-hour auto trips. (IBI Group, 2022)

4451 Fallowfield Road

The proposed development application includes a site plan to construct a self-storage facility with shared office space and ground floor retail space. The development is forecast to be built out in 2025 and to generate 98 AM and 85 PM peak hour two-way auto trips. (CGH, 2023)

2740 Cedarview Road, 4190-4236 Fallowfield Road

The proposed development application includes plan of subdivision to include six (6) four-storey apartment buildings comprising a total of 108 units, three (3) four-storey back-to-back terrace homes comprising 48 units, and two (2) three-storey stacked townhomes comprising a total of 24 units, and one terrace home comprising eight units. No TIA was available for this development.

444 Citigate Drive, 560 Dealership Drive

The proposed development application includes zoning by-law amendment and plan of subdivision to construct six industrial/warehouse buildings for a total of 1,174,800. A traffic memo supporting the plan of subdivision application states that forecasted auto trips for the development area will be 623 two-way AM and 548 two-way PM peak hour trips, and that the forecasted person trips for the development will be 780 fewer AM and 880 fewer PM peak hour two-way person trips than forecast within the CTS for the development area. (Novatech, 2022)

4433 Strandherd Drive

The proposed development application includes a site plan to construct a new 99 room, 5 storey hotel, providing 5,413 sq. m of GFA. The development was initially forecast to be built out in 2020 to generate 48 new AM and 53 new PM peak hour two-way auto trips, it is currently under construction and is anticipated to be occupied in 2024. (Novatech, 2018)

Citigate Employment Lands

The overall development application for the Citigate Employment lands included a shopping centre with 350,000 sq. ft of gross floor area (GFA), a hotel, 16.56 hectares of Business Park, 67.65 hectares of Prestige Business Park, and 10.5 hectares of car dealerships. It is noted that dealerships on the east south corner, Amazon, and retail stores on the north side have been constructed and captured in the existing counts. Approximately half completed, the entire development area was initially forecast to be built out in 2029 and to generate approximately 4100 new AM and 4400 new PM peak hour two-way auto trips. (Novatech, 2012)

3 Study Area and Time Periods

3.1 Study Area

The study area will include the intersections of:

- Fallowfield Road at:
 - Cedarview Road

- O'Keefe Court/Cobble Hill Drive
- Strandherd Drive & Citigate Drive
- Cedarview Road at:
 - Onassa Circle
- O'Keefe Court at:
 - Future Collector Road

No roads bound the site, and no boundary roads will be considered in this study. TRANS Screenline SL9 is located within the greenbelt north of the site and north of Fallowfield Road and will be reviewed as part of this study.

3.2 Time Periods

As the proposed development is composed primarily of residential units, the AM and PM peak hours will be examined.

3.3 Horizon Years

The anticipated build-out year is 2038. No additional horizons will be evaluated as part of this study given the distant nature of the site build-out.

4 Development-Generated Travel Demand

4.1 Mode Shares

4.1.1 Typical Area Mode Shares

Examining the mode shares recommended in the TRANS Trip Generation Manual (2020) for the subject district, derived from the most recent National Capital Region Origin-Destination survey (OD Survey), the existing average district mode shares by land use for South Nepean have been summarized in Table 7.

Table 7: TRANS Trip Generation Manual Recommended Mode Shares – South Nepean

| Travel Mode | Single-Detached | | Multi-Unit (Low-Rise) | | Multi-Unit (High-Rise) | | Commercial Generator | |
|--------------------|-----------------|-------------|-----------------------|-------------|------------------------|-------------|----------------------|-------------|
| | AM | PM | AM | PM | AM | PM | AM | PM |
| Auto Driver | 51% | 53% | 49% | 49% | 58% | 54% | 74% | 61% |
| Auto Pass. | 14% | 19% | 13% | 13% | 6% | 15% | 14% | 27% |
| Transit | 25% | 18% | 26% | 24% | 30% | 25% | 1% | 1% |
| Cycling | 1% | 1% | 2% | 2% | 2% | 0% | 0% | 0% |
| Walking | 9% | 10% | 9% | 12% | 4% | 7% | 11% | 11% |
| Virtual | 0% | 0% | 0% | 0% | 0% | 0% | 0% | 0% |
| Total | 100% | 100% | 100% | 100% | 100% | 100% | 100% | 100% |

4.1.2 Proposed Development Mode Shares

A number of factors are anticipated to impact the proposed development's modal shares.

4.1.2.1 Evolving Context for Trip Generation

While travel demands have evolved across changing social and technological landscapes, the pre-/post-pandemic era divide represents a watershed in the ubiquity of remote access for daily activities.

The trip generation methodologies and trends documented by ITE and employed within the TRANS Trip Generation Manual (2020) represent the historical mobility context, and rapid evolution is still occurring in how people get connected with products, services, and employment. Especially on the subject development's timeline, site design, and traffic forecasting on its basis, should account for this opportunity.

Virtual travel describes trips that were previously made by auto travel and other modes being captured by internet and telecommunication technologies. These trips include those reduced by work from home, either full-time or part-time, online services such as fitness, banking, medical, or consultation appointments, and e-commerce which converts retail trips during the peak hours into off-peak deliveries.

When applied to the existing trip generation rates, virtual travel can be thought of as a new mode of transportation. As future travel surveys are conducted, and the measured trip generation of a land use simply does not capture trips made virtually, this mode will no longer be necessary. In the interim, a virtual travel mode is a useful concept for accounting for these trends in long-term planning.

While these trends are anticipated to impact background traffic, specific design elements employed for the community can enable this shift for the subject development. Examples of such elements include fibreoptic internet and 5G wireless connectivity, dwelling design that includes spaces such as dens for home office use, the provision of supportive amenity spaces, and the presence of cafés and co-working spaces within walking distance. It is noted that the nearby proposed development at 4451 Strandherd Drive includes such co-working space as part of the concept plan.

4.1.2.2 Community Vision

Informed by the 15-Minute Community design concept, the community is proposed to include local residential-supportive land uses within the community core which will be accessible by a high degree of pedestrian connectivity both along road corridors and via a system of pathways. Providing direct active transportation connections to the network serving the high density of commercial and employment land uses immediately to the south of the development area will permit higher uptake of active modes and reduce auto dependence.

4.1.2.3 Transit Service Vision

A detailed description of the proposed transit routing and service is provided in Section 10.1. A short description of which is that the community is intended to be served by 15-minute transit service all-day, with increases in service frequency during the peak periods. The development's transit routing is proposed to be synergized with existing routes through the Citigate Employment Lands and may optionally provide opportunities for connections for these lands to other nodes in the City. It is expected that the proposed transit service will permit the development to meet the typical South Nepean recommended transit shares.

4.1.2.4 Modified Mode Shares

Given the foregoing trends and development characteristics, and accounting for virtual travel, modified mode share targets are proposed for the development and are summarized in Table 8.

Table 8: Proposed Development Mode Shares – Locally-Oriented Community

| Travel Mode | Single-Detached | | Multi-Unit (Low-Rise) | | Multi-Unit (High-Rise) | | Commercial Generator | |
|--------------------|-----------------|-------------|-----------------------|-------------|------------------------|-------------|----------------------|-------------|
| | AM | PM | AM | PM | AM | PM | AM | PM |
| Auto Driver | 26% | 28% | 24% | 24% | 33% | 29% | 54% | 41% |
| Auto Pass. | 9% | 13% | 8% | 7% | 1% | 9% | 9% | 22% |
| Transit | 25% | 18% | 26% | 24% | 30% | 25% | 16% | 16% |
| Cycling | 3% | 3% | 4% | 4% | 4% | 2% | 0% | 0% |
| Walking | 17% | 18% | 18% | 21% | 12% | 15% | 11% | 11% |
| Virtual | 20% | 20% | 20% | 20% | 20% | 20% | 10% | 10% |
| Total | 100% | 100% | 100% | 100% | 100% | 100% | 100% | 100% |

These mode shares represent an approximate doubling of the walking and cycling uptake and a halving of the auto travel compared to the typical Barrhaven suburban travel patterns. Beyond the opportunities for active transportation uptake presented by the immediate area context of the development as discussed in the preceding

sections, these changes are partly the result of the reduction in regional travel demands mitigated by the shift to virtual travel. The proposed mode shares are consistent with more locally-oriented travel and modal selection.

4.2 Trip Generation

This TIA has been prepared using the vehicle and person trip rates for the residential dwellings using the TRANS Trip Generation Manual (2020) and the vehicle trip rates and derived person trip rates for commercial component from the ITE Trip Generation Manual 11th Edition (2021) using the City-prescribed conversion factor of 1.28. Table 9 summarizes the person trip rates for the proposed residential land uses for each peak period and the person trip rates for the non-residential land uses by peak hour.

Table 9: Trip Generation Person Trip Rates by Peak Period

| Land Use | Land Use Code | Peak Period | Vehicle Trip Rate | Person Trip Rates |
|------------------------|-------------------|-------------|-------------------|-------------------|
| Single-Detached | 210 (TRANS) | AM | - | 2.05 |
| | | PM | - | 2.48 |
| Multi-Unit (Low-Rise) | 220 (TRANS) | AM | - | 1.35 |
| | | PM | - | 1.58 |
| Multi-Unit (High-Rise) | 221 & 222 (TRANS) | AM | - | 0.80 |
| | | PM | - | 0.90 |
| Land Use | Land Use Code | Peak Hour | Vehicle Trip Rate | Person Trip Rates |
| Retail (<40k sq ft) | 822 (ITE) | AM | 1.89 | 2.42 |
| | | PM | 5.44 | 6.96 |

Using the above person trip rates, the total person trip generation has been estimated. Given the 15-minute community vision, only 70% of the commercial component is considered as destination retail, where 30% of the commercial development is assumed to serve the immediate surrounding community of over 1,500 dwellings. Table 10 summarizes the total person trip generation for the residential land uses by peak period and for the non-residential land uses by peak hour.

Table 10: Total Residential Person Trip Generation by Peak Period

| Land Use | Units | AM Peak Period | | | PM Peak Period | | |
|------------------------|---------------|----------------|------|-------|----------------|-----|-------|
| | | In | Out | Total | In | Out | Total |
| Single-Detached | 342 | 210 | 491 | 701 | 526 | 322 | 848 |
| Multi-Unit (Low-Rise) | 1209 | 490 | 1142 | 1632 | 1070 | 840 | 1910 |
| Multi-Unit (High-Rise) | 128 | 32 | 70 | 102 | 67 | 48 | 115 |
| Land Use | GFA (sq. ft.) | AM Peak Hour | | | PM Peak Hour | | |
| | | In | Out | Total | In | Out | Total |
| Retail (<40k sq ft) | 34,453 | 50 | 33 | 83 | 120 | 120 | 240 |

Internal capture rates from the ITE Trip Generation Handbook 3rd Edition have been assigned to the development's retail component for mixed-use developments. The rates summarized in Table 11 represent the percentage of trips to/from the retail use based on the residential component.

Table 11: Internal Capture Rates

| Land Use | AM | | PM | |
|--|-----|-----|-----|-----|
| | In | Out | In | Out |
| Residential to/from Strip Retail Plaza | 17% | 14% | 10% | 26% |

Pass-by reductions applied to the retail trip generation at a rate of 40% have been included using the recommended value presented in the ITE Trip Generation Manual 11th Edition (2021) for the most similar land

use with a recommended rate, "Retail (40k – 150k sq ft)". The application of the pass-by percentage to O'Keefe Court would not be considered to reflect the expected pass-by component of the site trips and accordingly, the analysis will forgo the application of diverted trips and will apply the 40% pass-by to the major movements at the along each Cedarview Road and Fallowfield Road.

Using the above mode share targets for the community, the internal capture and pass-by rates, and the person trip rates, the person trips by mode have been projected. Trip generation by peak hour has been forecasted using the prescribed peak period conversion factors presented in the TRANS Trip Generation Manual (2020) for the residential component. Table 12 summarizes the residential trip generation and the non-residential trip generation by mode and peak hour.

Table 12: Trip Generation by Mode

| Travel Mode | | AM Peak Hour | | | | PM Peak Hour | | | |
|------------------------|------------------|--------------|------------|------------|------------|--------------|------------|------------|------------|
| | | Mode Share | In | Out | Total | Mode Share | In | Out | Total |
| Single-Detached | Auto Driver | 26% | 26 | 61 | 87 | 28% | 64 | 40 | 104 |
| | Auto Passenger | 9% | 9 | 21 | 30 | 13% | 30 | 18 | 48 |
| | Transit | 25% | 29 | 67 | 96 | 18% | 45 | 27 | 72 |
| | Cycling | 3% | 4 | 8 | 12 | 3% | 7 | 5 | 12 |
| | Walking | 17% | 21 | 48 | 69 | 18% | 50 | 30 | 80 |
| | Virtual | 20% | 24 | 57 | 81 | 20% | 55 | 33 | 88 |
| | Total | 100% | 113 | 262 | 375 | 100% | 251 | 153 | 404 |
| Multi-Unit (Low-Rise) | Auto Driver | 24% | 56 | 132 | 188 | 24% | 113 | 89 | 202 |
| | Auto Passenger | 8% | 19 | 44 | 63 | 7% | 33 | 26 | 59 |
| | Transit | 26% | 70 | 163 | 233 | 24% | 120 | 95 | 215 |
| | Cycling | 4% | 11 | 27 | 38 | 4% | 20 | 16 | 36 |
| | Walking | 18% | 51 | 120 | 171 | 21% | 117 | 92 | 209 |
| | Virtual | 20% | 57 | 132 | 189 | 20% | 111 | 88 | 199 |
| | Total | 100% | 264 | 618 | 882 | 100% | 514 | 406 | 920 |
| Multi-Unit (High-Rise) | Auto Driver | 33% | 5 | 11 | 16 | 29% | 8 | 7 | 15 |
| | Auto Passenger | 1% | 0 | 0 | 0 | 9% | 2 | 2 | 4 |
| | Transit | 30% | 5 | 12 | 17 | 25% | 8 | 6 | 14 |
| | Cycling | 4% | 1 | 1 | 2 | 2% | 1 | 0 | 1 |
| | Walking | 12% | 2 | 5 | 7 | 15% | 5 | 4 | 9 |
| | Virtual | 20% | 4 | 8 | 12 | 20% | 7 | 5 | 12 |
| | Total | 100% | 17 | 37 | 54 | 100% | 31 | 24 | 55 |
| Strip Retail Plaza | Auto Driver | 54% | 13 | 9 | 22 | 41% | 26 | 21 | 49 |
| | Auto Passenger | 9% | 4 | 3 | 6 | 22% | 24 | 20 | 43 |
| | Transit | 16% | 7 | 4 | 11 | 16% | 17 | 14 | 32 |
| | Cycling | 0% | 0 | 0 | 0 | 0% | 0 | 0 | 0 |
| | Walking | 11% | 5 | 3 | 8 | 11% | 12 | 10 | 22 |
| | Virtual | 10% | 4 | 3 | 7 | 10% | 11 | 9 | 20 |
| | Pass-by | 40% | -9 | -6 | -15 | 40% | -18 | -15 | -32 |
| | Internal Capture | varies | -9 | -5 | -14 | varies | -12 | -31 | -43 |
| | Total | 100% | 33 | 22 | 54 | 100% | 90 | 74 | 166 |

| Travel Mode | | AM Peak Hour | | | | PM Peak Hour | | | |
|--------------|----------------|--------------|------------|------------|-------------|--------------|------------|------------|-------------|
| | | Mode Share | In | Out | Total | Mode Share | In | Out | Total |
| Total | Auto Driver | - | 100 | 213 | 313 | - | 211 | 157 | 370 |
| | Auto Passenger | - | 32 | 68 | 99 | - | 89 | 66 | 154 |
| | Transit | - | 111 | 246 | 357 | - | 190 | 142 | 333 |
| | Cycling | - | 16 | 36 | 52 | - | 28 | 21 | 49 |
| | Walking | - | 79 | 176 | 255 | - | 184 | 136 | 320 |
| | Virtual | - | 89 | 200 | 289 | - | 184 | 135 | 319 |
| | Total | - | 427 | 939 | 1365 | - | 886 | 657 | 1545 |

As shown above, a total of 313 AM and 370 PM new peak hour two-way vehicle trips are projected as a result of the proposed development.

4.3 Trip Distribution

To understand the travel patterns of the subject development, the OD Survey has been reviewed to determine the travel for the residential component, and these patterns were applied based on the build-out of South Nepean. The virtual travel component has specifically been reduced from the proportion of regional trips. Table 13 below summarizes the distributions.

Table 13: OD Survey Distribution – South Nepean

| To/From | % of Trips | Via |
|--------------|-------------|---|
| North | 30% | 20% Cedarview Rd (N), 10% Fallowfield Rd (W), |
| South | 10% | 10% Citigate Dr (S) |
| East | 55% | 45% Fallowfield Rd (E), 10% Strandherd Dr (E), |
| West | 5% | 5% Fallowfield Rd (W) |
| Total | 100% | |

4.4 Trip Assignment

Using the distribution outlined above, turning movement splits, and access to major transportation infrastructure, the trips generated by the site have been assigned to the study area road network. Figure 11 illustrates the new site generated volumes and Figure 12 illustrates the pass-by auto volumes.

Figure 11: New Site Generation Auto Volumes





Figure 12: Pass-by Auto Volumes



5 Exemption Review

Table 14 summarizes the exemptions for this TIA.

Table 14: Exemption Review

| Module | Element | Explanation | Exempt/Required |
|-------------------------------|------------------------------|--|-----------------|
| Site Design and TDM | | | |
| 4.1 Development Design | 4.1.2 Circulation and Access | Only required for site plan and zoning by-law applications | Exempt |
| | 4.1.3 New Street Networks | Only required for plans of subdivision | Required |
| 4.2 Parking | 4.2.1 Parking Supply | Only required for site plan and zoning by-law applications | Exempt |

| Module | Element | Explanation | Exempt/Required |
|---|-------------------------------------|--|----------------------------|
| 4.3 Boundary Street Design | | All applications | Exempt – No boundary roads |
| 4.5 Transportation Demand Management | All Elements | Only required when the development generates more than 60 person-trips | Required |
| Network Impact | | | |
| 3.2 Background Network Travel Demand | All Elements | Only required when one or more other Network Impact Modules are triggered | Required |
| 3.3 Demand Rationalization | | Only required when one or more other Network Impact Modules are triggered | Required |
| 4.6 Neighbourhood Traffic Calming | 4.6.1 Adjacent Neighbourhoods | <p>If the development meets all of the following criteria along the route(s) site generated traffic is expected to utilize between an arterial road and the site's access:</p> <ol style="list-style-type: none"> 1. Access to Collector or Local; 2. "Significant sensitive land use presence" exists, where there is at least two of the following adjacent to the subject street segment: <ul style="list-style-type: none"> • School (within 250m walking distance); • Park; • Retirement / Older Adult Facility (i.e. long-term care and retirement homes); • Licenced Child Care Centre; • Community Centre; or • 50%, or greater, of adjacent property along the route(s) is occupied by residential lands and a minimum of 10 occupied residential units are present on the route. 3. Application is for Zoning By-Law Amendment or Draft Plan of Subdivision; 4. At least 75 site-generated auto trips; 5. Site Trip Infiltration is expected. Site traffic will increase peak hour vehicle volumes along the route by 50% or more. | Exempt |
| 4.7 Transit | 4.7.1 Transit Route Capacity | Only required when the development generates more than 75 transit trips | Required |
| | 4.7.2 Transit Priority Requirements | Only required when the development generates more than 75 auto trips | Required |
| 4.8 Network Concept | | Only required when proposed development generates more than 200 | Required |

| Module | Element | Explanation | Exempt/Required |
|--------------------------------|----------------------------|--|-----------------|
| | | person-trips during the peak hour in excess of equivalent volume permitted by established zoning | |
| 4.9 Intersection Design | 4.9.1 Intersection Control | Only required when the development generates more than 75 auto trips | Required |
| | 4.9.2 Intersection Design | Only required when the development generates more than 75 auto trips | Required |

6 Development Design

6.1 Design for Sustainable Modes

The proposed development is a residential subdivision with a mix of densities and unit types between single detached houses and mid-rise condo units. Sidewalks and cycletracks are proposed on each side of a collector road through the subdivision which is proposed to connect to O'Keefe Court to Onassa Circle. Sidewalks are proposed along at least one side of all local roads throughout the subdivision, and paving of the existing crushed stone multi-use pathway along the hydro corridor is proposed as part of the development. Pedestrian crossovers (Type C) are proposed at each of the three intersections of the MUP and the collector road.


A main street section is located centrally alongside the highest density areas, which is anticipated to have an enhanced public realm with space for additional public use. Figure 13 illustrates the major internal pedestrian and cycling network for the subdivision.

Figure 13: Internal Pedestrian and Cycling Network



Active transportation facilities are proposed be extended beyond the new community. To the south, an extension of the MUP to the existing MUP on O'Keefe Court and cycling routes on Lusk Street is proposed. This route would connect the community to the intersection of Strandherd Drive at Fallowfield Road/Citigate Drive more directly than using the facilities along the road network. These facilities would also improve connectivity for the surrounding area. To the north, the MUP is proposed to be extended along the north side of Lytle Avenue, continuing on the west side of Cedarview Road to the south side of the driveway to the Log Farm located in the Greenbelt, up to the bridge across the 416. Through this northern MUP extension and connection to the Log Farm, the community will be able to access to the NCC trail system. Figure 14 illustrates the area active transportation connections including the newly proposed external active transportation facilities.

Figure 14: Area Active Transportation Connections



6.2 New Street Networks

6.2.1 New Collector Road

The subdivision will include a new 26.0-metre-wide collector cross-section through the development area connecting O'Keefe Court to Onassa Circle. It is proposed that the sidewalk and cycling facilities within the new collector's cross-section integrate with the MUP where it meets the current terminus of Onassa Circle. Active modes would continue north on the MUP to Lytle Avenue.

The new collector road cross-sections will be context sensitive to the adjacent land uses through the proposed subdivision. Along the densest development areas, a main street cross-section proposed, including enhanced pedestrian realms, cycletracks, and parking on both sides of the road. Throughout the remainder of the

development, a 26A cross-section from the Designing Neighbourhood Collector Streets guidance is proposed, modified to increase increased boulevard space where lots front only one side of the road. The main street cross section is illustrated in Figure 15 and cross-section 26A from the Designing Neighbourhood Collector Streets guidance is illustrated in Figure 16.

Figure 15: Main Street Cross-Section





Figure 16: Designing Neighbourhood Collector Streets Cross-Section 26A



6.2.2 New Local Roads


Typical local roads of 18.0-metre rights-of-way are proposed throughout the development, as City standard 18.0-metre local cross-sections with sidewalks on one side of most roads and on both sides where appropriate. Local roads are proposed to be posted as 30 km/h and internal road intersections are recommended to be stop-controlled on the minor approaches of all intersections.

6.2.3 Traffic Calming

Traffic calming measures in line with the 30 km/h toolbox will be applied throughout the community. Horizontal deflection measures including bulb-outs, which are proposed to narrow roadways and intersections at strategic locations to reduce vehicle speeds on straight stretches. Vertical deflection measures including speed humps, are proposed along local roads are proposed to reduce vehicle speeds on straight stretches. The location of speed humps is subject to minor changes and will need to be refined as part of the detailed engineering submission once the locations of the driveway, stormwater flows, surface ponding, and servicing elements, such as utilities and fire hydrants, have been established. On-street parking will also be a key traffic calming feature of the new community and is generally included as part of all typical roadway cross-sections, and on both sides of the main street.

Figure 17 illustrates the conceptual key locations for traffic calming features within the new community.

Figure 17: Proposed Key Traffic Calming Measures



7 Transportation Demand Management

7.1 Context for TDM

The mode shares used within the TIA represent a reduction in auto travel and an increase in walking, commensurate with the local urban design and broader social trends. Overall, meeting the modal share targets are contingent on the successful implementation of the community design, however supporting TDM measures should be provided to help ensure these targets are met.

The subject site is not within a design priority area and the total bedrooms within the development is subject to the final unit breakdown and layout selections by purchasers. No age restrictions are noted.

7.2 Need and Opportunity

As previously stated, the mode share targets have been driven by the proposed community's area context, the urban design, and social trends. It is anticipated that the proposed targets will be met due to this robust set of factors. The role of transportation demand management measures will be aimed at providing awareness of travel mode options, reducing the need for vehicle ownership, and driving the adoption of transit for regional travel early in the development buildout. Any existing or forecast capacity issues are anticipated to further drive sustainable transportation adoption.

7.3 TDM Program

The "suite of post occupancy TDM measures" has been summarized in the TDM checklists for the residential and retail land uses. The checklist is provided in Appendix F. The key TDM measures recommended include:

- Display relevant walking and cycling maps along with transit schedules and route maps at major residential and retail entrances
- Provide a multimodal travel option information package to new residents and employees
- Contract with provider to install on-site carshare vehicles and promote their use by residents
- Contract with OC Transpo to provide early transit services until regular services are warranted by occupancy levels

8 Background Network Travel Demands

8.1 Transportation Network Plans

The transportation network plans were discussed in Section 2.3. The interim buildout of the Barnsdale Road highway 416 interchange is understood to be 2029, the extension of Chapman Mills Drive BRT is anticipated by the 2038 horizon. No extension of the LRT to Barrhaven will be assumed to be complete by the 2038 horizon, and the completion of Greenbank Road is not anticipated by this horizon, and the timing for the signalization of Cobble Hill Drive will be analyzed within the operations section.

Once completed, the Barnsdale Interchange is expected to reduce the pressure on Strandherd Drive and the Highway 416-Fallowfield Road interchange from development in Barrhaven South. Local to the subject development lands, the direct impact is expected to be lowering the overall demand on the east-west travel at the Strandherd Drive at Fallowfield Road/Citigate Drive intersection. Similarly, the Chapman Mills Drive BRT is anticipated to reduce growth-related pressures on Strandherd Drive. In the background growth for the future horizon, the nominal growth rates have been included on Strandherd Drive and the expected development related growth is assumed to be accommodated through the Barnsdale Interchange and Chapman Mills BRT corridor.

8.2 Background Growth

Other area traffic studies employed a 1%-2% annual background growth rate on Strandherd Drive and Fallowfield Road in addition to other explicitly considered background developments.

A review of the background projections from the City's TRANS Regional Model for the 2011 and 2031 horizons was completed to determine the anticipated background growth for each of the study area roadways. It is assumed that the expected growth will continue beyond the 2031 horizon to the build-out horizon. The

background TRANS model growth rates are summarized in Table 15, and Table 16 summarizes the recommended growth rates to be considered within the study area. The TRANS model plots are provided in Appendix G.

Table 15: TRANS Regional Model Projections – Study Area Growth Rates

| Street | TRANS Rate | |
|---------------------------------------|------------|------------|
| | Eastbound | Westbound |
| Fallowfield Rd north of Strandherd Dr | 0.34% | 0.11% |
| Fallowfield Rd west of Citigate Dr | 2.14% | 1.98% |
| Strandherd Dr | 3.46% | 2.17% |
| | Northbound | Southbound |
| Cedarview Rd north of Fallowfield Rd | 1.07% | 5.06% |
| Cedarview Rd south of Fallowfield Rd | 2.31% | 5.05% |

Table 16: Recommended Area Growth Rates

| Street | AM Peak Hour | | PM Peak Hour | |
|------------------------------------|--------------|------------|--------------|------------|
| | Eastbound | Westbound | Eastbound | Westbound |
| Fallowfield Rd north of Strandherd | 0.50% | 0.25% | 0.25% | 0.50% |
| Fallowfield Rd west of Citigate | 2.25% | 2.00% | 2.00% | 2.25% |
| Strandherd Dr | 3.50% | 2.25% | 2.25% | 3.50% |
| | Northbound | Southbound | Northbound | Southbound |
| Cedarview Rd north of Fallowfield | 1.00% | 5.00% | 5.00% | 1.00% |
| Cedarview Rd south of Fallowfield | 2.50% | 5.00% | 5.00% | 2.50% |

8.3 Other Developments

The background developments explicitly considered in the background conditions (Section 8.2) include:

- 115 Lusk Street
- 135 Lusk Street
- 140 Lusk Street
- 4451 Fallowfield Road
- 4433 Strandherd Drive
- CitiGate
- 444 Citigate, 560 Dealership Drive

Traffic from the remaining Citigate Employment Lands development areas were taken from the trip generation information in the 444 Citigate, 560 Dealership Drive TIA. The background development volumes within the study area have been provided in Appendix H.

9 Demand Rationalization

9.1 2038 Future Background Operations

Figure 18 illustrates the 2038 background volumes and Table 17 summarizes the 2038 background intersection operations. The level of service for signalized intersections is based on v/c calculations for individual lane movements and HCM 2000 v/c calculations for the overall intersection, and average delay for unsignalized intersections. The synchro worksheets for the 2038 future background horizon are provided in Appendix I.

Figure 18: 2038 Future Background Volumes




Table 17: 2038 Future Background Intersection Operations

| Intersection | Lane | AM Peak Hour | | | | PM Peak Hour | | | |
|--|---------|--------------|------|-------|-----------------------|--------------|------|-------|-----------------------|
| | | LOS | V/C | Delay | Q (95 th) | LOS | V/C | Delay | Q (95 th) |
| Cedarview Road at Onassa Circle Unsignalized | EBL/R | C | 0.05 | 15.3 | 1.5 | C | 0.09 | 17.2 | 2.3 |
| | NBL/T | A | 0.01 | 8.4 | 0.0 | A | 0.00 | 8.6 | 0.0 |
| | SBT/R | - | - | - | - | - | - | - | - |
| | Overall | A | - | 0.4 | - | A | - | 0.5 | - |

| Intersection | Lane | AM Peak Hour | | | | PM Peak Hour | | | |
|--|----------------|--------------|-------------|--------------|-----------------------|--------------|-------------|--------------|-----------------------|
| | | LOS | V/C | Delay | Q (95 th) | LOS | V/C | Delay | Q (95 th) |
| Fallowfield Road/Citigate Drive at Strandherd Drive <i>Signalized</i> | EBL | C | 0.77 | 54.0 | 70.7 | D | 0.88 | 70.2 | #79.9 |
| | EBT | C | 0.74 | 29.7 | #219.2 | F | 1.23 | 140.4 | #343.9 |
| | EBR | A | 0.29 | 4.7 | 19.4 | A | 0.31 | 8.9 | 27.9 |
| | WBL | A | 0.37 | 62.2 | 19.5 | A | 0.16 | 58.8 | 7.8 |
| | WBT | F | 1.46 | 239.5 | #416.8 | F | 2.50 | 701.7 | #428.7 |
| | WBR | A | 0.12 | 0.3 | 0.0 | A | 0.25 | 3.4 | 6.0 |
| | NBL | A | 0.34 | 57.4 | 14.6 | A | 0.57 | 49.3 | #92.8 |
| | NBT/R | A | 0.34 | 49.6 | 19.4 | C | 0.74 | 59.7 | 66.2 |
| | SBL | A | 0.29 | 47.8 | 22.4 | A | 0.33 | 43.5 | 45.3 |
| | SBT | A | 0.53 | 53.7 | 40.9 | A | 0.28 | 40.1 | 27.4 |
| | SBR | D | 0.83 | 22.7 | 47.9 | D | 0.89 | 31.1 | 70.1 |
| | Overall | F | 1.07 | 113.2 | - | F | 1.34 | 292.9 | - |
| Fallowfield Road at O'Keefe Court/Cobble Hill Drive <i>Unsignalized</i> | EBL | A | 0.10 | 9.3 | 2.3 | A | 0.09 | 9.7 | 2.3 |
| | EBT | - | - | - | - | - | - | - | - |
| | EBR | - | - | - | - | - | - | - | - |
| | WBL | A | 0.02 | 8.9 | 0.0 | A | 0.06 | 9.1 | 1.5 |
| | WBT | - | - | - | - | - | - | - | - |
| | WBR | - | - | - | - | - | - | - | - |
| | NB | E | 0.48 | 41.0 | 17.3 | F | 0.48 | 50.5 | 16.5 |
| | SBL | F | 0.42 | 83.2 | 12.8 | F | 0.73 | 145.2 | 24.8 |
| | SBT/R | C | 0.08 | 19.2 | 2.3 | C | 0.10 | 22.5 | 2.3 |
| | Overall | A | - | 5.2 | - | A | - | 7.4 | - |
| Fallowfield Road at Cedarview Road <i>Signalized</i> | EBL | A | 0.15 | 13.7 | 10.5 | A | 0.20 | 17.4 | 7.8 |
| | EBT | D | 0.87 | 32.3 | #192.4 | B | 0.64 | 20.5 | 94.7 |
| | EBR | A | 0.01 | 0.0 | 0.0 | A | 0.04 | 2.0 | 2.5 |
| | WBL | A | 0.23 | 17.9 | 9.7 | A | 0.54 | 24.1 | 35.5 |
| | WBT | B | 0.61 | 18.9 | 100.0 | D | 0.90 | 36.3 | #179.7 |
| | WBR | A | 0.21 | 2.7 | 9.7 | A | 0.11 | 4.1 | 7.6 |
| | NBL | A | 0.13 | 20.0 | 12.8 | A | 0.28 | 31.2 | 9.2 |
| | NBT | B | 0.66 | 30.7 | 73.4 | A | 0.30 | 21.5 | 37.1 |
| | NBR | A | 0.51 | 15.0 | 38.0 | A | 0.22 | 4.7 | 10.8 |
| | SBL | E | 0.97 | 84.8 | #69.0 | C | 0.72 | 36.2 | #76.1 |
| | SBT/R | A | 0.26 | 21.0 | 28.2 | F | 1.05 | 77.7 | #177.4 |
| | Overall | E | 0.91 | 28.0 | - | E | 0.91 | 38.1 | - |

Notes: Saturation flow rate of 1800 veh/h/lane
Queue is measured in metres
Peak Hour Factor = 1.00

Delay = average vehicle delay in seconds
m = metered queue
= volume for the 95th %ile cycle exceeds capacity

At the 2038 future background horizon, the study area intersections are anticipated to operate worse than in the existing conditions with the background growth and development volumes impacting specific movements.

At the intersection of Fallowfield Road/Citigate Drive at Strandherd Drive, during both peak hours, the westbound through movement is expected to incur further capacity, delay, and queueing issues. During the AM peak hour, the overall intersection is forecast be over theoretical capacity and may be subject to high delays, and the eastbound through movement may exhibit extended queues. During the PM peak hour, the eastbound through movement is forecast to be over theoretical capacity and may be subject to high delays, and the overall intersection is anticipated to be over theoretical capacity with high delays.

At the intersection of Fallowfield Road at O'Keefe Court/ Cobble Hill Drive, southbound left movement is anticipated to have high delays during both peak hours, and the northbound movement is anticipated to have high delays during the PM peak hour.

At the intersection of Fallowfield Road at Cedarview Road, high delays and extended queues may be observed on southbound left movement during the AM peak hour, and extended queueing may be present on the movement during the PM peak hour. Also during the PM peak hour, the southbound through/right movement is anticipated to be over theoretical capacity.

9.1.1 Future Background 2038 Mitigation Measures

Signal warrant analysis was performed for the intersections of Cedarview Road at Onassa Circle and Fallowfield Road at O'Keefe Court/ Cobble Hill Drive for the 2038 future background conditions and neither intersection was found to meet warrants. Signal warrants are provided in Appendix D.

Turn-lane warrant analysis was performed for the northbound left-turn at the intersection of Cedarview Road at Onassa Circle. The northbound approach was found to warrant a left-turn lane at the future background 2038 horizon, however no turn-lane would be recommended for implementation based on the low total volumes of the movement. Turn-lane warrants are provided in Appendix J.

Although the signal warrant does not meet at intersection of Fallowfield Road at O'Keefe Court/Cobble Hill Drive, to address the background delays, it is recommended that this intersection to be signalized by 2038. Also, to address the capacity issues during the PM peak hour at the intersection of Fallowfield Road at Cedarview Road, signal timing adjustments are proposed. The operations associated with these changes are summarized for the 2038 future background horizon in Table 18. The synchro worksheets for the future background 2038 mitigation measures are provided in Appendix K.

Table 18: 2038 Future Background Intersection Operations – Mitigated

| Intersection | Lane | AM Peak Hour | | | | PM Peak Hour | | | |
|--|----------------|--------------|-------------|-------------|-----------------------|--------------|-------------|------------|-----------------------|
| | | LOS | V/C | Delay | Q (95 th) | LOS | V/C | Delay | Q (95 th) |
| Fallowfield Road at O'Keefe Court/ Cobble Hill Drive Signalized | EBL | A | 0.21 | 9.4 | 16.5 | A | 0.21 | 8.9 | 14.3 |
| | EBT | A | 0.50 | 10.2 | 94.4 | A | 0.47 | 8.9 | 90.2 |
| | EBR | A | 0.01 | 0.5 | 0.5 | A | 0.06 | 2.3 | 4.8 |
| | WBL | A | 0.03 | 7.8 | 3.7 | A | 0.10 | 7.2 | 9.1 |
| | WBT | A | 0.50 | 10.3 | 94.5 | A | 0.57 | 10.7 | 122.4 |
| | WBR | A | 0.01 | 0.5 | 0.5 | A | 0.02 | 2.9 | 2.6 |
| | NB | A | 0.17 | 9.9 | 13.5 | A | 0.15 | 11.6 | 12.9 |
| | SBL | A | 0.09 | 17.0 | 9.6 | A | 0.11 | 19.9 | 14.5 |
| | SBT/R | A | 0.04 | 9.9 | 5.2 | A | 0.05 | 12.1 | 6.1 |
| | Overall | A | 0.54 | 10.2 | - | B | 0.62 | 9.7 | - |

| Intersection | Lane | AM Peak Hour | | | | PM Peak Hour | | | |
|--|----------------|------------------------|-----|-------|-----------------------|--------------|-------------|-------------|-----------------------|
| | | LOS | V/C | Delay | Q (95 th) | LOS | V/C | Delay | Q (95 th) |
| Fallowfield Road at Cedarview Road <i>Signalized</i> | EBL | No mitigation required | | | | A | 0.24 | 21.5 | 8.8 |
| | EBT | | | | | B | 0.66 | 23.0 | 103.2 |
| | EBR | | | | | A | 0.04 | 2.5 | 2.9 |
| | WBL | | | | | A | 0.58 | 28.6 | 40.2 |
| | WBT | | | | | E | 0.93 | 42.8 | #193.3 |
| | WBR | | | | | A | 0.12 | 5.1 | 8.6 |
| | NBL | | | | | A | 0.28 | 31.3 | 9.5 |
| | NBT | | | | | A | 0.28 | 20.9 | 37.3 |
| | NBR | | | | | A | 0.21 | 4.4 | 10.6 |
| | SBL | | | | | B | 0.68 | 32.8 | 69.9 |
| | SBT/R | | | | | E | 0.98 | 59.1 | #177.6 |
| | Overall | | | | | E | 0.95 | 36.0 | - |

Notes: Saturation flow rate of 1800 veh/h/lane
Queue is measured in metres
Peak Hour Factor = 1.00

Delay = average vehicle delay in seconds
m = metered queue
= volume for the 95th %ile cycle exceeds capacity

With the signalization of the intersection of Fallowfield Road at O'Keefe Court/Cobble Hill Drive at the 2038 future background horizon, the intersection is forecast to operate well during both peak hours. No capacity issues are noted.

At the intersection of Fallowfield Road at Cedarview Road, with signal timing adjustments, during the PM peak hour at the 2038 future background horizon, the operations are anticipated to be similar as in the existing conditions. No capacity issues are noted.

9.2 2038 Future Total Operations

As O'Keefe court terminates immediately west of the proposed collector road intersection, this access intersection effectively constitutes a bend in the road, no delays or capacity issues will be present, and the traffic operations will not be analyzed.

Figure 19 illustrates the 2038 future total volumes and Table 19 summarizes the 2038 future total intersection operations. The level of service for signalized intersections is based on v/c calculations for individual lane movements and HCM 2000 v/c calculations for the overall intersection, and average delay for unsignalized intersections. The synchro worksheets for the 2038 future total horizon are provided in Appendix L.

Figure 19: 2038 Future Total Volumes




Table 19: 2038 Future Total Intersection Operations

| Intersection | Lane | AM Peak Hour | | | | PM Peak Hour | | | |
|---|---------|--------------|------|-------|-----------------------|--------------|------|-------|-----------------------|
| | | LOS | V/C | Delay | Q (95 th) | LOS | V/C | Delay | Q (95 th) |
| Cedarview Road at Onassa Circle Unsignalized | EBL/R | C | 0.28 | 19.5 | 8.3 | D | 0.35 | 27.6 | 11.3 |
| | NBL/T | A | 0.02 | 8.7 | 0.8 | A | 0.04 | 9.1 | 0.8 |
| | SBT/R | - | - | - | - | - | - | - | - |
| | Overall | A | - | 2.2 | - | A | - | 2.2 | - |

| Intersection | Lane | AM Peak Hour | | | | PM Peak Hour | | | |
|---|----------------|--------------|-------------|--------------|-----------------------|--------------|-------------|--------------|-----------------------|
| | | LOS | V/C | Delay | Q (95 th) | LOS | V/C | Delay | Q (95 th) |
| Fallowfield Road/Citigate Drive at Strandherd Drive <i>Signalized</i> | EBL | E | 0.91 | 69.9 | #89.6 | E | 0.99 | 92.2 | #88.8 |
| | EBT | D | 0.84 | 39.9 | #220.8 | F | 1.25 | 150.4 | #343.9 |
| | EBR | A | 0.34 | 5.6 | 20.1 | A | 0.32 | 9.1 | 28.2 |
| | WBL | A | 0.55 | 84.1 | #25.4 | A | 0.16 | 58.8 | 7.8 |
| | WBT | F | 1.75 | 370.2 | #416.8 | F | 2.50 | 702.6 | #428.7 |
| | WBR | A | 0.16 | 0.6 | 0.0 | A | 0.33 | 5.9 | 11.1 |
| | NBL | A | 0.41 | 62.5 | 15.2 | C | 0.77 | 62.5 | #99.1 |
| | NBT/R | A | 0.16 | 26.3 | 16.6 | A | 0.54 | 39.3 | 62.2 |
| | SBL | B | 0.70 | 86.5 | #49.0 | A | 0.59 | 62.6 | #83.4 |
| | SBT | A | 0.36 | 37.0 | 41.2 | A | 0.25 | 33.9 | 30.6 |
| | SBR | C | 0.76 | 16.1 | 53.2 | D | 0.86 | 26.6 | 81.3 |
| | Overall | F | 1.18 | 165.0 | - | F | 1.39 | 292.1 | - |
| Fallowfield Road at O'Keefe Court/ Cobble Hill Drive <i>Unsignalized</i> | EBL | A | 0.15 | 9.9 | 3.8 | B | 0.20 | 11.1 | 5.3 |
| | EBT | - | - | - | - | - | - | - | - |
| | EBR | - | - | - | - | - | - | - | - |
| | WBL | A | 0.02 | 9.0 | 0.8 | A | 0.06 | 9.4 | 1.5 |
| | WBT | - | - | - | - | - | - | - | - |
| | WBR | - | - | - | - | - | - | - | - |
| | NB | F | 0.75 | 96.3 | 31.5 | F | 0.97 | 196.8 | 37.5 |
| | SBL | F | 1.91 | 582.1 | 79.5 | F | 2.71 | 981.5 | 91.5 |
| | SBT/R | C | 0.25 | 18.4 | 7.5 | C | 0.28 | 24.0 | 8.3 |
| | Overall | C | - | 45.0 | - | C | - | 65.6 | - |
| Fallowfield Road at Cedarview Road <i>Signalized</i> | EBL | A | 0.20 | 15.1 | 11.9 | A | 0.44 | 35.1 | #16.8 |
| | EBT | E | 1.00 | 53.2 | #220.1 | B | 0.70 | 22.6 | 109.8 |
| | EBR | A | 0.02 | 0.1 | 0.0 | A | 0.04 | 2.2 | 2.9 |
| | WBL | A | 0.43 | 36.3 | #16.3 | B | 0.63 | 31.3 | #45.5 |
| | WBT | B | 0.67 | 21.3 | 109.6 | E | 0.99 | 52.2 | #206.8 |
| | WBR | A | 0.24 | 2.8 | 9.9 | A | 0.15 | 4.5 | 9.2 |
| | NBL | A | 0.13 | 19.7 | 12.9 | A | 0.30 | 32.7 | 10.1 |
| | NBT | B | 0.62 | 28.5 | 73.3 | A | 0.30 | 21.5 | 36.7 |
| | NBR | A | 0.52 | 18.1 | 44.2 | A | 0.23 | 4.8 | 10.9 |
| | SBL | E | 0.97 | 81.9 | #76.2 | C | 0.78 | 40.6 | #83.5 |
| | SBT/R | A | 0.27 | 19.7 | 29.4 | F | 1.06 | 81.1 | #179.9 |
| | Overall | E | 0.98 | 35.2 | - | F | 1.02 | 44.0 | - |

Notes: Saturation flow rate of 1800 veh/h/lane
Queue is measured in metres
Peak Hour Factor = 1.00

Delay = average vehicle delay in seconds
m = metered queue
= volume for the 95th %ile cycle exceeds capacity

At the 2038 future total horizon, the study area intersections are anticipated to operate similarly to the 2038 future background conditions.

At the intersection of Fallowfield Road/Citigate Drive at Strandherd Drive, with the addition of site traffic, the westbound left and southbound left movements may be subject to high delays and extended queues, and the eastbound left movement may exhibit extended queues during the AM peak hour. During the PM peak hour, the eastbound left movement is approaching theoretical capacity and may be subject to high delays.

At the intersection of Fallowfield Road at O'Keefe Court/ Cobble Hill Drive, during the AM peak hour the southbound left movement is anticipated to be over theoretical capacity and to experience a large increase in delay, and the northbound movement may be subject to high delays. During the PM peak hour at the intersection

the southbound left movement is anticipated to be over theoretical capacity and this movement and the northbound movement are anticipated to experience large increases in delay.

At the intersection of Fallowfield Road at Cedarview Road, the westbound left movement may exhibit extended queues during both peak hours.

9.2.1 Future Total 2038 Mitigation Measures

Signal warrant analysis was performed for the intersections of Cedarview Road at Onassa Circle and Fallowfield Road at O'Keefe Court/ Cobble Hill Drive for the 2038 future total conditions and neither intersection was found to meet warrants. Signal warrants are provided in Appendix D.

Turn-lane warrants were performed for the northbound left-turn at the intersection of Cedarview Road at Onassa Circle. The northbound approach was found to warrant a left-turn lane at the 2038 future total horizon, and to support the development it is recommended that one be provided.

As in the background conditions, Fallowfield Road at O'Keefe Court/Cobble Hill Drive will be evaluated as a signalized intersection to determine the operations once signals are installed. Also as in the background conditions, at the intersection of Fallowfield Road at Cedarview Road, signal timing adjustments have been implemented to address capacity issues associated with unbalanced phasing. The operations associated with these changes are summarized for the 2038 future total horizon are illustrated in Table 20. The synchro worksheets for the future total 2038 mitigation measures are provided in Appendix M.

Table 20: 2038 Future Total Intersection Operations – Mitigated

| Intersection | Lane | AM Peak Hour | | | | PM Peak Hour | | | |
|--|----------------|------------------------|-------------|-------------|-----------------------|--------------|-------------|-------------|-----------------------|
| | | LOS | V/C | Delay | Q (95 th) | LOS | V/C | Delay | Q (95 th) |
| Fallowfield Road at O'Keefe Court/ Cobble Hill Drive <i>Signalized</i> | EBL | A | 0.43 | 16.6 | 26.6 | A | 0.55 | 21.8 | 38.7 |
| | EBT | A | 0.58 | 13.2 | 94.5 | A | 0.58 | 12.7 | 99.6 |
| | EBR | A | 0.01 | 0.4 | 0.4 | A | 0.07 | 2.6 | 4.9 |
| | WBL | A | 0.04 | 8.5 | 3.6 | A | 0.14 | 9.3 | 9.3 |
| | WBT | B | 0.65 | 15.1 | 115.7 | B | 0.68 | 15.5 | 131.4 |
| | WBR | A | 0.06 | 4.4 | 5.4 | A | 0.11 | 4.0 | 8.6 |
| | NB | A | 0.20 | 12.3 | 15.5 | A | 0.16 | 12.5 | 13.1 |
| | SBL | A | 0.39 | 26.3 | 31.3 | A | 0.28 | 24.3 | 29.6 |
| | SBT/R | A | 0.18 | 7.4 | 10.9 | A | 0.16 | 8.2 | 10.5 |
| | Overall | B | 0.67 | 14.3 | - | B | 0.67 | 14.0 | - |
| Fallowfield Road at Cedarview Road <i>Signalized</i> | EBL | No mitigation required | | | | A | 0.55 | 54.3 | #22.2 |
| | EBT | | | | | C | 0.72 | 27.0 | 144.8 |
| | EBR | | | | | A | 0.04 | 3.9 | 4.1 |
| | WBL | | | | | B | 0.69 | 40.1 | #57.3 |
| | WBT | | | | | E | 0.99 | 56.0 | #262.7 |
| | WBR | | | | | A | 0.15 | 6.8 | 12.8 |
| | NBL | | | | | A | 0.40 | 49.0 | #14.2 |
| | NBT | | | | | A | 0.28 | 25.6 | 44.2 |
| | NBR | | | | | A | 0.22 | 4.9 | 11.9 |
| | SBL | | | | | C | 0.76 | 44.4 | #98.4 |
| | SBT/R | | | | | E | 1.00 | 71.6 | #213.9 |
| | Overall | | | | | E | 0.99 | 45.2 | - |

Notes: Saturation flow rate of 1800 veh/h/lane
Queue is measured in metres
Peak Hour Factor = 1.00

Delay = average vehicle delay in seconds
m = metered queue
= volume for the 95th %ile cycle exceeds capacity

With the signalization of the intersection of Fallowfield Road at O'Keefe Court/Cobble Hill Drive at the 2038 future total horizon, the intersection operates similarly to the background conditions with the signalization during both peak hours. No capacity issues are noted.

At the intersection of Fallowfield Road at Cedarview Road, with signal timing adjustments, during the PM peak hour at the 2038 future total horizon, the operations are similar to the 2038 background conditions. With the addition of site traffic, extended queueing may be observed on the eastbound left movement, the westbound left movement, the northbound left movement, and the southbound left movement. No capacity issues are noted.

9.3 Demand Rationalization Conclusions

9.3.1 Background Travel Demand

Capacity issues have been noted at the intersection of Strandherd Drive at Fallowfield Road/Citigate Drive on the eastbound through and westbound through movements in the background conditions. These movements facilitate access to Highway 416 for the majority of the Barrhaven community. Additional background traffic on these movements over the existing volumes are largely anticipated to be a result of remaining growth in the Barrhaven South area. Once the interchange at Barnsdale Road is constructed, it is assumed that most of the forecasted background growth and a proportion of the existing volumes will reduce on these movements.

9.3.2 Development Travel Demand

The proposed development does not generate additional traffic on the overcapacity eastbound through and westbound through movements at the intersection of Strandherd Drive at Fallowfield Road/Citigate Drive. As this proposed community is situated adjacent to high density of employment and commercial development and proposes 15-minute neighbourhood design and high-quality transit service, and only minor traffic impacts are forecast, rationalization for site travel demand is not required.

10 Transit

10.1 Route Capacity

Traditional peak direction transit trips, north to (AM)/from (PM) the city's inner area, is proposed to be synergistic with transit service to the Citigate Employment Lands as extensions of existing and/or future planned routes. For example, during the AM peak period, it would be anticipated that as commuters from the rest of Barrhaven alight within the Citigate Employment Lands, buses on these routes will have low passenger loads to permit a large number of boardings within the Cedarview Community as the routes continue on to Fallowfield Station, or potentially Bells Corners and Moodie Station as determined appropriate by OC Transpo. This model will rely on routes that are understood to be presently underutilized, furthermore leaving future residual capacity for these existing routes' travel based on the synergistic ridership anticipated to result between the differing residential and employment land use patterns. Routing of existing express routes during the peak periods through the subject lands is also recommended.

Travel in the traditional off-peak direction, south to (AM)/from (PM) the rest of Barrhaven is anticipated to have appreciably high demand as trips within Barrhaven, to/from Citigate and beyond along Strandherd Drive will serve the connection of residents to local employment, commercial, and recreational destinations. This traditionally off-peak travel may be synergistic with transit service connecting Bells Corners and Moodie Station to Barrhaven, during the peak periods as determined appropriate by OC Transpo, and may additionally or alternatively provide connectivity east along Fallowfield Road to Fallowfield Station at all times of the day.

Routes travelling to/from Fallowfield Station along Fallowfield Road, through the community, continuing south through Citigate and ultimately along Strandherd Drive to Downtown Barrhaven would provide local connections to other existing and planned communities in Barrhaven including to and for the O'Keefe Court commercial lands.

The proposed transit routing options are illustrated in Figure 20. It is noted that a loop formed by a route travelling through the community continuing along Cedarview Road and connecting to Fallowfield Station would provide the adjacent Cedarhill community with transit connections.

Figure 20: Proposed Transit Routes



As Citigate builds out the transit demands are anticipated to increase and service to be expanded. This increase in demand will support increases in bus frequencies in the study area and along potential route extensions through the subject community.

In Section 5.1 the trip generation by mode was estimated, including an estimate of the number of transit trips that will be generated by the proposed development. Table 21 summarizes the transit trip generation.

Table 21: Trip Generation by Transit Mode

| Travel Mode | Residential Mode Share | AM Peak Hour | | | PM Peak Hour | | |
|-------------|------------------------|--------------|-----|-------|--------------|-----|-------|
| | | In | Out | Total | In | Out | Total |
| Transit | 18%-30% | 111 | 246 | 357 | 190 | 142 | 333 |

The development is anticipated to generate 357 AM and 333 PM peak hour two-way transit trips at full build-out.

Based on these forecasted values, Table 30 summarizes the theoretical bus requirements to meet travel demands in the traditional peak and off-peak directions.

Table 22: Cedarview Forecasted Transit Service – Minimum Bus Requirements


| Peak Hour | Direction of Travel | Bus and Service Type | | |
|-----------|---------------------|--------------------------------|-------------------------------------|---------------------------------------|
| | | Single Capacity: 45 passengers | Articulated Capacity: 70 passengers | Double Decker Capacity: 90 passengers |
| AM | To the north/east | 2 | 1 | 1 |
| | To the south | 2 | 2 | 1 |
| PM | From the north/east | 4 | 2 | 2 |
| | From the south | 6 | 4 | 3 |

Note: Bus and service time ranges assume capacity at 80% load

The intention of the site is to ultimately be serviced by frequent transit (15-minute service) and therefore, it is recommended that bus capacities be selected on this basis when considering the potential loads with which the routes arrive to and depart from the community. As shown above, the target transit demands, derived from the application of a more locally-oriented service model for the recommended transit mode shares from the TRANS trip generation manual for Nepean South, are supportive of frequencies better than 15-minute service in the peak periods.

As illustrated in Figure 20, transit service is envisioned to be routed along the internal collector road from O'Keefe Court to Onassa Circle continuing to Cedarview Road. To provide the entire community with access to these transit routes, the proposed bus stop locations, with 300-metre radii representing approximate 400-metre walking distances, are illustrated in Figure 21.

Figure 21: Proposed Bus Stop Locations



10.2 Transit Priority

Transit movements at the intersection of Fallowfield Road/Citigate Drive at Strandherd Drive for existing routes are the eastbound and westbound through movements, the westbound left and northbound right movements, and the northbound through and southbound through movements. The recommended transit routes proposed in section 10.1 would utilize the northbound through and southbound through movement, and potentially eliminate the northbound right and westbound left movements depending on future combination of existing routes with new routes for the subject development. All transit movements at the intersection are anticipated to operate with transit LOS F at the future background and total horizons. All existing routes are forecast to be subject to delays at this intersection and proposed routes may be subject to lower delays with any shifts from the westbound left movement to the northbound through movement. It is anticipated that once the Barnsdale Road Highway 416 interchange is built out, delays at the intersection will be reduced.

At the intersection of Fallowfield Drive at O'Keefe Court/Cobble Hill Drive, the existing transit movements are the eastbound and westbound through movements, and proposed transit movements are the eastbound left and southbound right movements. All movements at this intersection are anticipated to operate with Transit LOS C or better with the exception of the southbound right movement during the PM peak hour which is forecast to operate with transit LOS D in the future background and total conditions.

At the intersection of Fallowfield Road at Cedarview Road, the existing routes utilize the eastbound through and westbound through movements which are anticipated to operate with more delay in the future total than the background conditions, increasing by one transit LOS letter grade. The proposed transit routes would utilize the westbound right and southbound left movements, with the westbound right forecast to operate with transit LOS B and the southbound left forecast to operate with transit LOS F.

Notwithstanding the foregoing, the transit routes within the study area do not have transit LOS targets, not being existing transit priority corridors and peak period delays are typical of Barrhaven arterial intersections.

11 Network Concept

A screenline analysis was conducted on TRANS Screenline 9 to determine the total capacities of the roadways without and without the study area. Table 35 summarizes the results of the screenline analysis. The relevant data were provided by the City of Ottawa for TRANS Screenline 9, and are provided in Appendix N.

Table 23: AM Peak Hour Directional Screenline Analysis

| Screenline 9 | Roads | Lane Capacity [vphpl] | Lanes per Direction | Capacity [vph] | Background Volumes | Site Traffic | Total Traffic |
|--------------|--|-----------------------|---------------------|----------------|--------------------|--------------|---------------|
| Northbound | Moodie north of Fallowfield | 1,000 | 1 | 1,000 | 505 | 0 | 505 |
| | Borrisokane South of Jock River Bridge | 1,000 | 1 | 1,000 | 569 | 0 | 569 |
| | Cedarview North of Lytle | 1,000 | 1 | 1,000 | 497 | 43 | 540 |
| | Greenbank North of Fallowfield | 1,000 | 1 | 1,000 | 1,234 | 0 | 1,234 |
| | Greenbank South of Jock River | 800 | 1 | 800 | 677 | 0 | 677 |
| | Hwy 416 North of Strandherd | 1,800 | 2 | 3,600 | 2,614 | 32 | 2,646 |
| | Hwy 416 South of Jock River Bridge | 1,800 | 2 | 3,600 | 1,847 | 0 | 1,847 |
| | Longfields South of Jock River Bridge | 1,000 | 2 | 2,000 | 1,178 | 0 | 1,178 |
| | Merivale North of Fallowfield | 1,000 | 1 | 1,000 | 1,375 | 0 | 1,375 |
| | Moodie South of Jock River Bridge | 1,000 | 1 | 1,000 | 271 | 0 | 271 |
| | Prince of Wales South of Jock River Bridge | 1,000 | 2 | 2,000 | 1,546 | 0 | 1,546 |
| | Prince of Wales North of Fallowfield | 1,000 | 1 | 1,000 | 922 | 0 | 922 |
| | Richmond South of Hope Side | 1,000 | 1 | 1,000 | 245 | 0 | 245 |

| Screenline 9 | Roads | Lane Capacity [vphpl] | Lanes per Direction | Capacity [vph] | Background Volumes | Site Traffic | Total Traffic |
|-------------------|--|-----------------------|---------------------|----------------|--------------------|--------------|---------------|
| | Woodroffe North of Fallowfield Transit Station | 1,000 | 2 | 2,000 | 2,233 | 0 | 2,233 |
| | Total | - | 19 | 22,000 | 15,713 | 75 | 15,788 |
| Southbound | Moodie north of Fallowfield | 1,000 | 1 | 1,000 | 230 | 0 | 230 |
| | Borrisokane South of Jock River Bridge | 1,000 | 1 | 1,000 | 231 | 0 | 231 |
| | Cedarview North of Lytle | 1,000 | 1 | 1,000 | 244 | 20 | 264 |
| | Greenbank North of Fallowfield | 1,000 | 1 | 1,000 | 463 | 0 | 463 |
| | Greenbank South of Jock River | 800 | 1 | 8,00 | 238 | 0 | 238 |
| | Hwy 416 North of Strandherd | 1,800 | 2 | 3,600 | 1,048 | 15 | 1,063 |
| | Hwy 416 South of Jock River Bridge | 1,800 | 2 | 3,600 | 727 | 0 | 727 |
| | Longfields South of Jock River Bridge | 1,000 | 2 | 2,000 | 451 | 0 | 451 |
| | Merivale North of Fallowfield | 1,000 | 1 | 1,000 | 221 | 0 | 221 |
| | Moodie South of Jock River Bridge | 1,000 | 1 | 1,000 | 157 | 0 | 0 |
| | Prince of Wales South of Jock River Bridge | 1,000 | 2 | 2,000 | 521 | 0 | 0 |
| | Prince of Wales North of Fallowfield | 1,000 | 1 | 1,000 | 277 | 0 | 0 |
| | Richmond South of Hope Side | 1,000 | 1 | 1,000 | 287 | 0 | 0 |
| | Woodroffe North of Fallowfield Transit Station | 1,000 | 2 | 2,000 | 521 | 0 | 0 |
| | Total | - | 19 | 22,000 | 5,616 | 35 | 6,651 |

As a whole, screenline 9 has residual capacity in both the background conditions and with site traffic. Greenbank Road, Merivale Road, and Woodroffe Avenue are over their theoretical capacities in the peak direction in the background conditions, and site traffic is not anticipated to impact these roads. Therefore, forecasted site traffic can be accommodated from a network perspective.

12 Intersection Design

12.1 Intersection Control

It is recommended that the intersection of Fallowfield Road at O'Keefe Court/Cobble Hill Drive be signalized by 2038 to address the background conditions, as per current City monitoring.

While the build-out horizon is distant and background volumes are considered conservative, signal timing adjustments may be required to improve operations at the intersection of Fallowfield Road at Cedarview Road in the future.

No signalization of site access intersections, or other changes to network intersection control are recommended as part of this study.

12.2 Intersection Design

12.2.1 2038 Future Total Intersection Operations

The operations are noted in Section 9.2. The study area intersections operate similarly in the total condition to the background conditions. With signals at the intersection of Fallowfield Road at O'Keefe Court/Cobble Hill Drive required to address background conditions, and mitigation through signal timing adjustments to balance operations at the intersection of Fallowfield Road at Cedarview Road, no transportation network modifications are required to support the development.

12.2.2 Intersection MMLOS

Table 24 summarizes the MMLOS analysis for the signalized intersections of Fallowfield Road at Cedarview Road and Fallowfield Road/Citigate Drive at Strandherd Drive. The existing and future conditions for the intersections will be the same and are considered in one row. The intersection analysis is based on the policy area of Developing Community. The MMLOS worksheets has been provided in Appendix O.

Table 24: Study Area Intersection MMLOS Analysis

| Intersection | Pedestrian LOS | | Bicycle LOS | | Transit LOS | | Truck LOS | | Auto LOS | |
|--|----------------|--------|-------------|--------|-------------|--------|-----------|--------|----------|--------|
| | PLOS | Target | BLOS | Target | TLOS | Target | TrLOS | Target | ALOS | Target |
| Fallowfield Road at Cedarview Road | F | C | F | C | N/A | N/A | E | D | F | D |
| Fallowfield Road/Citigate Drive at Strandherd Drive | F | C | F | C | N/A | N/A | B | D | F | D |

The pedestrian LOS targets will not be met at the study area intersections. To meet pedestrian LOS targets, crossing distances would need to be less than two lane widths on all crossings. Given the nature of arterial roadways, it is not feasible to meet the given targets.

The bicycle LOS targets will not be met at the study area intersections. To meet bicycle LOS targets, segregated facilities and two-stage left turns or left-turn boxes would be required on all approaches at the intersection of Fallowfield Road at Cedarview, and segregated facilities would be required on the southbound approach at the intersection of Fallowfield Road/Citigate Drive at Strandherd Drive.

The truck LOS targets will not be met at the intersection of Fallowfield Road at Cedarview Road. To meet truck LOS targets, effective corner radius would need to be greater than 15 metres or the number of receiving lanes would need at least two lanes.

The auto LOS targets will not be met at the study area intersections. Section 10 includes recommendations to improve the auto LOS at the intersection of Fallowfield Road at Cedarview Road.

12.2.3 Recommended Design Elements

The access intersection of Cedarview Road at Onassa Circle is proposed to have an inbound northbound left-turn lane added on Cedarview Road. The recommended storage length for the lane will be confirmed through subsequent TIA revisions.

No network intersection design elements are anticipated to be required outside of those listed in the TIA to support the proposed development.

13 Summary of Improvements Indicated and Modifications Options

The following summarizes the analysis and results presented in this TIA report:

Proposed Site and Screening

- The community is proposed as comprising a mix of densities, from detached dwellings to mid-rise condo blocks
- A new collector road serving the community is proposed to connect O'Keefe Court to Onassa Circle
- The trip generation trigger was met for the TIA Screening

Existing Conditions

- Fallowfield Road, Strandherd Drive, Cedarview Road north of Fallowfield Road are arterial roads, Cedarview Road between Fallowfield Road and Jockvale Road is a major collector road, and south of Jockvale Road south of Jockvale Road is a collector road in the study area
- O'Keefe Court, Cobble Hill Drive, Citigate Drive, Onassa Circle are local roads
- Sidewalks are provided along both sides of Strandherd Drive and Cobble Hill Drive, along the west side of Citigate Drive, and along the south side of Fallowfield Road for approximately 155 metres west of Citigate Drive
- Cycletracks are provided along both sides of Strandherd Drive, on the south side of Fallowfield Road for approximately 155 metres west of Citigate Drive
- MUPs are provided along the east side of Cedarview Road south of Fallowfield Road, on the east side of Citigate Drive south of CrossKeys Place, and on the north side of Fallowfield Road west of Cedarview Road continuing along O'Keefe Court to Lytle Park
- Strandherd Drive is designated as a cross-town bikeway within the 2023 Transportation Master Plan – Part 1
- Capacity issues have been noted on the westbound through movements during both peak hours in the existing condition
- The intersections of Fallowfield Road at Strandherd Drive and Fallowfield Road at Cedarview Road are noted to have experienced higher collisions than other locations within the study area
- Collisions at the Fallowfield Road at Strandherd Drive intersection are typically associated with congestion, and no further review of collisions at this location is required
- Collisions at the Fallowfield Road at Cedarview Road intersection
- The collisions at the intersections of Fallowfield Road at Strandherd Drive and Fallowfield Road at Cedarview Road are typically associated with congestion, and no further review of collisions are required at these locations

Planned Conditions

- A new Highway 416 interchange at Barnsdale Road is planned which will mitigate volumes on the Strandherd Drive and Fallowfield Road corridors from the Barrhaven South community
- The intersection of Fallowfield Road at O'Keefe Court/Cobble Hill Drive is understood to be planned for signalization in the future based on monitoring by the City

- Chapman Mills Drive BRT is planned to be extended to Highway 416 and this improvement is anticipated before 2038
- Greenbank Road is to be realigned and include median BRT, and these improvements are anticipated outside of the study horizons
- The BRT line from Baseline Station to Barrhaven Town Centre is to be converted to LRT and this improvement will be subject to timing determined by the TMP Part 2
- 115 Lusk Street, 135 Lusk Street, 140 Lusk Street, 4451 Fallowfield Road, 4433 Strandherd Drive, CitiGate, 444 Citigate, and 560 Dealership Drive are background developments within the study area

Development Generated Travel Demand

- Future travel trends enabled by urban design and infrastructure should be considered for this development which is anticipated to be built out in 2038
- The community is proposed to be informed by 15-Minute Neighbourhood design philosophy, and will include residential-supportive land uses internally and provide high-quality and direct active transportation links to surrounding employment and commercial land uses
- Fifteen-minute transit service or better is envisioned for the development
- Mode shares accounting for these aspects of the community are proposed in line with reductions in regional auto travel
- The proposed development is forecasted produce 1365 two-way people trips during the AM peak hour and 1545 two-way people trips during the PM peak hour
- Of the forecasted people trips, 313 two-way trips will be vehicle trips during the AM peak hour and 370 two-way trips will be vehicle trips during the PM peak hour
- Of the forecasted trips, 30 % are anticipated to travel north, 10 % to the south, 55 % to the east, and 5% to both the west and south

Development Design

- The subdivision will include a new 26.0-metre-wide collector cross-section through the development area connecting O'Keefe Court to Onassa Circle
- Sidewalks and cycletracks will be on each side of the collector road through the subdivision
- Sidewalks will be along one side of all local roads throughout the subdivision, and paving of the existing crushed stone mixed-use pathway along the hydro corridor is proposed as part of the development
- Pedestrian crossovers (Type C) are proposed at each of the three intersections of the MUP and the collector road
- MUPs are proposed to extend to both the north and south
- Typical local roads of 18.0-metre rights-of-way are proposed throughout the development
- Traffic calming measures are proposed including bulb-outs and speed humps
- The local roads are proposed to be posted as 30 km/h

TDM

- Supportive TDM measures to be included within the proposed development should include:
 - Display relevant walking and cycling maps along with transit schedules and route maps at major residential and retail entrances
 - Provide a multimodal travel option information package to new residents and employees
 - Contract with provider to install on-site carshare vehicles and promote their use by residents

- Contract with OC Transpo to provide early transit services until regular services are warranted by occupancy levels

Background Conditions

- Other area traffic studies employed a 1%-2% annual background growth rate on Strandherd Drive and Fallowfield Road in addition to other explicitly considered background developments
- To account for the Barnsdale Road interchange and the Chapman Mills BRT reducing volumes along Strandherd Drive, background growth based on the TRANS volume models will be applied
- The background developments were explicitly included in the background conditions, along with background growths along Fallowfield Road, Strandherd Drive, and Cedarview Road
- At the 2038 future background horizon, the study area intersections are anticipated to operate worse than in the existing conditions with the background growth and development volumes impacting specific movements
- Capacity issues have been noted at the intersection of Strandherd Drive at Fallowfield Road/Citigate Drive on the eastbound through and westbound through movements in the background conditions
- Once the interchange at Barnsdale Road is constructed, it is assumed that most of the forecasted background growth and a proportion of the existing volumes will reduce on these movements
- Both Cedarview Road at Onassa Circle and Fallowfield Road at O'Keefe Court/ Cobble Hill Drive intersections do not meet the signal warrant for the 2038 future background conditions
- It is recommended that the intersection of Fallowfield Road at O'Keefe Court/Cobble Hill Drive to be signalized by 2038
- The northbound approach was found to warrant a left-turn lane at the future background 2038 horizon at the intersection of Cedarview Road at Onassa Circle
- No turn-lane would be recommended for implementation at the intersection of Cedarview Road at Onassa Circle based on the low total volumes of the movement

Transit

- Traditional peak direction transit trips, north to (AM)/from (PM) the city's inner area is proposed to be synergistic with transit service to the Citigate Employment Lands as extensions of existing and/or future planned routes
- This travel is proposed to rely on potentially underutilized routes, and the synergistic land use patterns would be expected to leave residual capacity for existing ridership to grow along these routes
- Internal routes travelling to/from Fallowfield Station along Fallowfield Road, through the community, continuing south through Citigate and ultimately along Strandherd Drive to Downtown Barrhaven would provide local connections to other existing and planned communities in Barrhaven
- As Citigate builds out the transit demands are anticipated to increase and will support increases in bus frequencies in the study area and along potential route extensions through the subject community
- The development is anticipated to generate 357 AM and 333 PM peak hour two-way transit trips at full build-out
- It is recommended that bus capacities be selected on this basis when considering the potential loads with which the routes arrive to and depart from the community
- Transit routes have been proposed to be routed along the internal collector road from O'Keefe Court to Onassa Circle continuing to Cedarview Road

- All existing routes are forecast to be subject to delays at the intersection of Fallowfield Road/Citigate Drive at Strandherd Drive and proposed routes may be subject to lower delays with route changes from the westbound left movement to the northbound through movement
- It is anticipated that once the Barnsdale Road Highway 416 interchange is built out, delays at the intersection of Fallowfield Road/Citigate Drive at Strandherd Drive will be reduced
- All movements at the intersection of Fallowfield Drive at O'Keefe Court/Cobble Hill Drive are anticipated to operate with Transit LOS C or better with the exception of the southbound right movement during the PM peak hour which is forecast to operate with transit LOS D in the future background and total conditions
- The existing routes utilize the eastbound through and westbound through movements at the intersection of Fallowfield Road at Cedarview Road are anticipated to increase the transit LOS by one letter grade compared to the background conditions

Network Concept

- Screenline 9 has residual capacity in both the background conditions and with site traffic
- Forecasted site traffic can be accommodated from a network perspective

Intersection Design

- The study area intersections at the 2038 future total horizon are anticipated to operate similarly to the 2038 future background conditions
- Signal timing adjustments may be required to improve operations at the intersection of Fallowfield Road at Cedarview Road in the future
- Both Cedarview Road at Onassa Circle and Fallowfield Road at O'Keefe Court/ Cobble Hill Drive intersections do not meet the signal warrant for the 2038 future total conditions
- Similar to the background conditions, it is recommended that the intersection of Fallowfield Road at O'Keefe Court/Cobble Hill Drive to be signalized by 2038
- The access intersection of Cedarview Road at Onassa Circle is proposed to have an inbound northbound left-turn lane added on Cedarview Road
- As this proposed community is situated adjacent to high density of employment and commercial development and proposes 15-minute neighbourhood design and high quality transit service, and only minor traffic impacts are forecast, rationalization for site travel demand is not required
- The pedestrian LOS targets will not be met at the study area intersections and would need to be less than two lane widths on all crossings to meet the targets
- The bicycle LOS targets will not be met at the study area intersections
- Segregated facilities, two-stage left turns or left-turn boxes would be required on all approaches at the intersection of Fallowfield Road at Cedarview, and segregated facilities would be required on the southbound approach at the intersection of Fallowfield Road/Citigate Drive at Strandherd Drive in order to meet the bicycle LOS targets
- The truck LOS targets will not be met at the intersection of Fallowfield Road at Cedarview Road, and effective corner radius would need to be greater than 15 metres or the number of receiving lanes would need at least two lanes to meet the targets

14 Conclusion

It is recommended that, from a transportation perspective, the proposed development applications proceed.

Prepared By:



John Kingsley
Transportation Engineering-Intern

Reviewed By:



Christopher Gordon, P.Eng.
Senior Transportation Engineer

Appendix A

TIA Screening Form and PM Certification Form

City of Ottawa 2023 Revisions to 2017 TIA Guidelines
Step 1 - Screening Form

Date: 30-May-24
Project Number: 2023-105
Project Reference: 4497 O'Keefe Court

| 1.1 Description of Proposed Development | |
|---|---|
| Municipal Address | 4497 O'Keefe Court |
| Description of Location | Between Cedarview Road, O'Keefe Court, and Highway 416 |
| Land Use Classification | Rural Zones (RR4, RR4 [647, 648, 649r]), Open Space and Leisure Zones (O1, O1A), Environmental Zone (EP3) |
| Development Size | 342 Single-Detached, 1,209 low-rise dwellings, 128 |
| Accesses | Access via Onassa Circle and O'Keefe Court |
| Phase of Development | Multiple |
| Buildout Year | 2038 |
| TIA Requirement | Full TIA Required |

| 1.2 Trip Generation Trigger | |
|-----------------------------|-------------------------|
| Land Use Type | Multi-Family (Low-Rise) |
| Development Size | 1209 Units |
| Trip Generation Trigger | Yes |

| 1.3 Location Triggers | |
|--|----|
| Does the development propose a new driveway to a boundary street that is designated as part of the Transit Priority Network, Rapid Transit network or Cross-Town Bikeways? | No |
| Is the development in a Hub, a Protected Major Transit Station Area (PMTSA), or a Design Priority Area (DPA)? | No |
| Location Trigger | No |

| 1.4. Safety Triggers | |
|---|----|
| Are posted speed limits on a boundary street 80 km/hr or greater? | No |
| Are there any horizontal/vertical curvatures on a boundary street limits sight lines at a proposed driveway? | No |
| Is the proposed driveway within the area of influence of an adjacent traffic signal or roundabout (i.e. within 300 m of intersection in rural conditions, or within 150 m of intersection in urban/ suburban conditions)? | No |
| Is the proposed driveway within auxiliary lanes of an intersection? | No |
| Does the proposed driveway make use of an existing median break that serves an existing site? | No |
| Is there is a documented history of traffic operations or safety concerns on the boundary streets within 500 m of the development? | No |
| Does the development include a drive-thru facility? | No |
| Safety Trigger | No |



Certification Form for TIA Study PM

TIA Plan Reports

On April 14, 2022, the Province's Bill 109 received Royal Assent providing legislative direction to implement the More Homes for Everyone Act, 2022 aiming to increase the supply of a range of housing options to make housing more affordable. Revisions have been made to the TIA guidelines to comply with Bill 109 and streamline the process for applicants and staff.

Individuals submitting TIA reports will be responsible for all aspects of development-related transportation assessment and reporting, and undertaking such work, in accordance and compliance with the City of Ottawa's Official Plan, the Transportation Master Plan and the Transportation Impact Assessment (2017) Guidelines.

By submitting the attached TIA report (and any associated documents) and signing this document, the individual acknowledges that they meet the four criteria listed below.

CERTIFICATION

I have reviewed and have a sound understanding of the objectives, needs and requirements of the City of Ottawa's Official Plan, Transportation Master Plan and the Transportation Impact Assessment (2017) Guidelines; (Update effective July 2023)

I have a sound knowledge of industry standard practice with respect to the preparation of transportation impact assessment reports, including multi modal level of service review;

I have substantial experience (more than 5 years) in undertaking and delivering transportation impact studies (analysis, reporting and geometric design) with strong background knowledge in transportation planning, engineering or traffic operations; and

I am either a licensed or registered¹ professional in good standing, whose field of expertise

is either transportation engineering

or transportation planning.

¹ License of registration body that oversees the profession is required to have a code of conduct and ethics guidelines that will ensure appropriate conduct and representation for transportation planning and/or transportation engineering works.

Dated at _____ this _____ day of _____, 20____.
(City)

Name :

Professional title:



Signature of individual certifier that s/he/they meet the above criteria

| |
|--|
| Office Contact Information (Please Print) |
| Address: |
| City / Postal Code: |
| Telephone / Extension: |
| Email Address: |

Stamp



Revision Date: June 2023

Appendix B



Turning Movement Counts



| Morning Peak Diagram | | Specified Period From: 7:00:00 To: 10:00:00 | One Hour Peak From: 8:15:00 To: 9:15:00 | | | | | | | | | | | | |
|---|--|---|--|---|--|-------------------|--|--|--|--|--|-----------------|--|--|--|
| Municipality: Ottawa Site #: 2317800002 Intersection: Cedarview Rd & Onassa Cir TFR File #: 1 Count date: 19-Jul-23 | | Weather conditions: Person counted: Person prepared: Person checked: | | | | | | | | | | | | | |
| ** Non-Signalized Intersection ** | | Major Road: Cedarview Rd runs N/S | | | | | | | | | | | | | |
| <table border="1"><tr><td>North Leg Total: 572 North Entering: 220 North Peds: 0 Peds Cross: </td><td>Cyclists 0 0 Trucks 2 5 Cars 10 203 Totals 12 208</td><td>0 7 213 </td><td>Cyclists 6 Trucks 5 Cars 341 Totals 352</td></tr><tr><td colspan="4"><p>Cyclists Trucks Cars Totals</p><p>0 3 18 21</p><p></p><p>Onassa Cir</p><p></p><p>Cyclists Trucks Cars Totals</p><p>0 2 12 14</p><p>0 0 6 6</p><p>0 2 18</p><p>Cedarview Rd</p><p></p><p>Cars 209 Trucks 5 Cyclists 0 Totals 214</p><p>Cars 8 329 Trucks 1 3 Cyclists 0 6 Totals 9 338</p><p>337 4 6</p><p>Peds Cross: </p><p>West Peds: 0 West Entering: 20 West Leg Total: 41</p><p>South Peds: 0 South Entering: 347 South Leg Total: 561</p></td></tr><tr><td colspan="4">Comments</td></tr></table> | | | | North Leg Total: 572 North Entering: 220 North Peds: 0 Peds Cross: | Cyclists 0 0 Trucks 2 5 Cars 10 203 Totals 12 208 | 0 7 213 | Cyclists 6 Trucks 5 Cars 341 Totals 352 | <p>Cyclists Trucks Cars Totals</p> <p>0 3 18 21</p> <p></p> <p>Onassa Cir</p> <p></p> <p>Cyclists Trucks Cars Totals</p> <p>0 2 12 14</p> <p>0 0 6 6</p> <p>0 2 18</p> <p>Cedarview Rd</p> <p></p> <p>Cars 209 Trucks 5 Cyclists 0 Totals 214</p> <p>Cars 8 329 Trucks 1 3 Cyclists 0 6 Totals 9 338</p> <p>337 4 6</p> <p>Peds Cross: </p> <p>West Peds: 0 West Entering: 20 West Leg Total: 41</p> <p>South Peds: 0 South Entering: 347 South Leg Total: 561</p> | | | | Comments | | | |
| North Leg Total: 572 North Entering: 220 North Peds: 0 Peds Cross: | Cyclists 0 0 Trucks 2 5 Cars 10 203 Totals 12 208 | 0 7 213 | Cyclists 6 Trucks 5 Cars 341 Totals 352 | | | | | | | | | | | | |
| <p>Cyclists Trucks Cars Totals</p> <p>0 3 18 21</p> <p></p> <p>Onassa Cir</p> <p></p> <p>Cyclists Trucks Cars Totals</p> <p>0 2 12 14</p> <p>0 0 6 6</p> <p>0 2 18</p> <p>Cedarview Rd</p> <p></p> <p>Cars 209 Trucks 5 Cyclists 0 Totals 214</p> <p>Cars 8 329 Trucks 1 3 Cyclists 0 6 Totals 9 338</p> <p>337 4 6</p> <p>Peds Cross: </p> <p>West Peds: 0 West Entering: 20 West Leg Total: 41</p> <p>South Peds: 0 South Entering: 347 South Leg Total: 561</p> | | | | | | | | | | | | | | | |
| Comments | | | | | | | | | | | | | | | |



| Mid-day Peak Diagram | | Specified Period From: 11:30:00 To: 13:30:00 | One Hour Peak From: 12:00:00 To: 13:00:00 | | | | | | | | | | | | |
|---|--|---|--|---|--|-------------------|--|--|--|--|--|-----------------|--|--|--|
| Municipality: Ottawa Site #: 2317800002 Intersection: Cedarview Rd & Onassa Cir TFR File #: 1 Count date: 19-Jul-23 | | Weather conditions: Person counted: Person prepared: Person checked: | | | | | | | | | | | | | |
| ** Non-Signalized Intersection ** | | Major Road: Cedarview Rd runs N/S | | | | | | | | | | | | | |
| <table border="1"><tr><td>North Leg Total: 499 North Entering: 315 North Peds: 0 Peds Cross: </td><td>Cyclists 1 2 Trucks 1 2 Cars 10 299 Totals 12 303</td><td>3 3 309 </td><td>Cyclists 3 Trucks 1 Cars 180 Totals 184</td></tr><tr><td colspan="4"><p>Cyclists Trucks Cars Totals</p><p>1 1 24 26</p><p></p><p>Onassa Cir</p><p></p><p>Cyclists Trucks Cars Totals</p><p>0 0 6 6</p><p>0 0 9 9</p><p>0 0 15</p><p>Cedarview Rd</p><p></p><p>Cars 308 Trucks 2 Cyclists 2 Totals 312</p><p>Cars 14 174 Trucks 0 1 Cyclists 0 3 Totals 14 178</p><p>188 1 3</p><p>Peds Cross: </p><p>West Peds: 0 West Entering: 15 West Leg Total: 41</p><p>South Peds: 0 South Entering: 192 South Leg Total: 504</p></td></tr><tr><td colspan="4">Comments</td></tr></table> | | | | North Leg Total: 499 North Entering: 315 North Peds: 0 Peds Cross: | Cyclists 1 2 Trucks 1 2 Cars 10 299 Totals 12 303 | 3 3 309 | Cyclists 3 Trucks 1 Cars 180 Totals 184 | <p>Cyclists Trucks Cars Totals</p> <p>1 1 24 26</p> <p></p> <p>Onassa Cir</p> <p></p> <p>Cyclists Trucks Cars Totals</p> <p>0 0 6 6</p> <p>0 0 9 9</p> <p>0 0 15</p> <p>Cedarview Rd</p> <p></p> <p>Cars 308 Trucks 2 Cyclists 2 Totals 312</p> <p>Cars 14 174 Trucks 0 1 Cyclists 0 3 Totals 14 178</p> <p>188 1 3</p> <p>Peds Cross: </p> <p>West Peds: 0 West Entering: 15 West Leg Total: 41</p> <p>South Peds: 0 South Entering: 192 South Leg Total: 504</p> | | | | Comments | | | |
| North Leg Total: 499 North Entering: 315 North Peds: 0 Peds Cross: | Cyclists 1 2 Trucks 1 2 Cars 10 299 Totals 12 303 | 3 3 309 | Cyclists 3 Trucks 1 Cars 180 Totals 184 | | | | | | | | | | | | |
| <p>Cyclists Trucks Cars Totals</p> <p>1 1 24 26</p> <p></p> <p>Onassa Cir</p> <p></p> <p>Cyclists Trucks Cars Totals</p> <p>0 0 6 6</p> <p>0 0 9 9</p> <p>0 0 15</p> <p>Cedarview Rd</p> <p></p> <p>Cars 308 Trucks 2 Cyclists 2 Totals 312</p> <p>Cars 14 174 Trucks 0 1 Cyclists 0 3 Totals 14 178</p> <p>188 1 3</p> <p>Peds Cross: </p> <p>West Peds: 0 West Entering: 15 West Leg Total: 41</p> <p>South Peds: 0 South Entering: 192 South Leg Total: 504</p> | | | | | | | | | | | | | | | |
| Comments | | | | | | | | | | | | | | | |





Traffic Count Summary

| Intersection: Cedarview Rd & Onassa Cir | | | | | Count Date: 19-Jul-23 | | Municipality: Ottawa | | | | | |
|---|-----------------------------------|------|-------|----------------|-----------------------|------------------------------------|----------------------------|-----------------------------------|-------|-------|----------------|---------------|
| North Approach Totals | | | | | | North/South Total Approaches | South Approach Totals | | | | | |
| Hour Ending | Includes Cars, Trucks, & Cyclists | | | | Total Peds | | Hour Ending | Includes Cars, Trucks, & Cyclists | | | | Total Peds |
| | Left | Thru | Right | Grand Total | | | | Left | Thru | Right | Grand Total | |
| 7:00:00 | 0 | 0 | 0 | 0 | 0 | 0 | 7:00:00 | 0 | 0 | 0 | 0 | 0 |
| 8:00:00 | 0 | 171 | 16 | 187 | 0 | 448 | 8:00:00 | 7 | 254 | 0 | 261 | 0 |
| 9:00:00 | 0 | 202 | 12 | 214 | 0 | 568 | 9:00:00 | 12 | 342 | 0 | 354 | 0 |
| 10:00:00 | 0 | 195 | 13 | 208 | 0 | 479 | 10:00:00 | 9 | 262 | 0 | 271 | 0 |
| 12:00:00 | 0 | 129 | 2 | 131 | 0 | 230 | 12:00:00 | 2 | 97 | 0 | 99 | 0 |
| 13:00:00 | 0 | 303 | 12 | 315 | 0 | 507 | 13:00:00 | 14 | 178 | 0 | 192 | 0 |
| 15:00:00 | 0 | 132 | 1 | 133 | 0 | 247 | 15:00:00 | 5 | 109 | 0 | 114 | 0 |
| 16:00:00 | 0 | 404 | 7 | 411 | 0 | 660 | 16:00:00 | 9 | 240 | 0 | 249 | 0 |
| 17:00:00 | 0 | 499 | 9 | 508 | 0 | 758 | 17:00:00 | 4 | 246 | 0 | 250 | 0 |
| 18:00:00 | 0 | 480 | 5 | 485 | 0 | 721 | 18:00:00 | 3 | 233 | 0 | 236 | 0 |
| Totals: 0 2515 77 2592 0 | | | | | | 4618 | S Totals: 65 1961 0 2026 0 | | | | | |
| East Approach Totals | | | | | | East/West Total Approaches | West Approach Totals | | | | | |
| Hour Ending | Includes Cars, Trucks, & Cyclists | | | | Total Peds | | Hour Ending | Includes Cars, Trucks, & Cyclists | | | | Total Peds |
| | Left | Thru | Right | Grand Total | | | | Left | Thru | Right | Grand Total | |
| 7:00:00 | 0 | 0 | 0 | 0 | 0 | 0 | 7:00:00 | 0 | 0 | 0 | 0 | 0 |
| 8:00:00 | 0 | 0 | 0 | 0 | 0 | 10 | 8:00:00 | 6 | 0 | 4 | 10 | 1 |
| 9:00:00 | 0 | 0 | 0 | 0 | 0 | 9 | 9:00:00 | 4 | 0 | 5 | 9 | 0 |
| 10:00:00 | 0 | 0 | 0 | 0 | 0 | 24 | 10:00:00 | 16 | 0 | 8 | 24 | 0 |
| 12:00:00 | 0 | 0 | 0 | 0 | 0 | 19 | 12:00:00 | 12 | 0 | 7 | 19 | 0 |
| 13:00:00 | 0 | 0 | 0 | 0 | 0 | 15 | 13:00:00 | 6 | 0 | 9 | 15 | 0 |
| 15:00:00 | 0 | 0 | 0 | 0 | 0 | 10 | 15:00:00 | 9 | 0 | 1 | 10 | 0 |
| 16:00:00 | 0 | 0 | 0 | 0 | 0 | 16 | 16:00:00 | 9 | 0 | 7 | 16 | 0 |
| 17:00:00 | 0 | 0 | 0 | 0 | 0 | 28 | 17:00:00 | 13 | 0 | 15 | 28 | 0 |
| 18:00:00 | 0 | 0 | 0 | 0 | 0 | 14 | 18:00:00 | 7 | 0 | 7 | 14 | 0 |
| Totals: 0 0 0 0 0 | | | | | | 145 | W Totals: 82 0 63 145 1 | | | | | |
| Calculated Values for Traffic Crossing Major Street | | | | | | | | | | | | |
| Hours Ending: | | 8:00 | 10:00 | 12:00 | 13:00 | 15:00 | 16:00 | 17:00 | 18:00 | | | |
| Crossing Values: | | 6 | 16 | 12 | 6 | 9 | 9 | 13 | 7 | | | |



| Count Date: 19-Jul-23 Site #: 2317800002 | | | | | | | | | | | | | | | | | | | | |
|--|---------------------------------|------|------|------|-------|------|-------------------------|------|------|------|-------|------|---------------------------|------|------|------|-------|------|-------------|------|
| Interval Time | Passenger Cars - North Approach | | | | | | Trucks - North Approach | | | | | | Cyclists - North Approach | | | | | | Pedestrians | |
| | Left | | Thru | | Right | | Left | | Thru | | Right | | Left | | Thru | | Right | | North Cross | |
| | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr |
| 7:00:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 7:15:00 | 0 | 0 | 32 | 32 | 4 | 4 | 0 | 0 | 0 | 0 | 1 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 7:30:00 | 0 | 0 | 82 | 50 | 9 | 5 | 0 | 0 | 1 | 1 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 7:45:00 | 0 | 0 | 120 | 38 | 12 | 3 | 0 | 0 | 3 | 2 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 8:00:00 | 0 | 0 | 164 | 44 | 15 | 3 | 0 | 0 | 6 | 3 | 1 | 0 | 0 | 0 | 1 | 1 | 0 | 0 | 0 | 0 |
| 8:15:00 | 0 | 0 | 211 | 47 | 18 | 3 | 0 | 0 | 6 | 0 | 2 | 1 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 |
| 8:30:00 | 0 | 0 | 258 | 47 | 21 | 3 | 0 | 0 | 8 | 2 | 3 | 1 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 |
| 8:45:00 | 0 | 0 | 312 | 54 | 24 | 3 | 0 | 0 | 9 | 1 | 3 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 |
| 9:00:00 | 0 | 0 | 361 | 49 | 25 | 1 | 0 | 0 | 11 | 2 | 3 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 |
| 9:15:00 | 0 | 0 | 414 | 53 | 28 | 3 | 0 | 0 | 11 | 0 | 4 | 1 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 |
| 9:30:00 | 0 | 0 | 463 | 49 | 33 | 5 | 0 | 0 | 12 | 1 | 4 | 0 | 0 | 0 | 1 | 0 | 1 | 1 | 0 | 0 |
| 9:45:00 | 0 | 0 | 508 | 45 | 35 | 2 | 0 | 0 | 14 | 2 | 4 | 0 | 0 | 0 | 1 | 0 | 1 | 0 | 0 | 0 |
| 10:00:00 | 0 | 0 | 552 | 44 | 36 | 1 | 0 | 0 | 15 | 1 | 4 | 0 | 0 | 0 | 1 | 0 | 1 | 0 | 0 | 0 |
| 10:15:00 | 0 | 0 | 552 | 0 | 36 | 0 | 0 | 0 | 15 | 0 | 4 | 0 | 0 | 0 | 1 | 0 | 1 | 0 | 0 | 0 |
| 11:30:00 | 0 | 0 | 552 | 0 | 36 | 0 | 0 | 0 | 15 | 0 | 4 | 0 | 0 | 0 | 1 | 0 | 1 | 0 | 0 | 0 |
| 11:45:00 | 0 | 0 | 612 | 60 | 37 | 1 | 0 | 0 | 15 | 0 | 4 | 0 | 0 | 0 | 1 | 0 | 1 | 0 | 0 | 0 |
| 12:00:00 | 0 | 0 | 678 | 66 | 38 | 1 | 0 | 0 | 18 | 3 | 4 | 0 | 0 | 0 | 1 | 0 | 1 | 0 | 0 | 0 |
| 12:15:00 | 0 | 0 | 749 | 71 | 40 | 2 | 0 | 0 | 18 | 0 | 4 | 0 | 0 | 0 | 2 | 1 | 1 | 0 | 0 | 0 |
| 12:30:00 | 0 | 0 | 831 | 82 | 45 | 5 | 0 | 0 | 18 | 0 | 5 | 1 | 0 | 0 | 2 | 0 | 1 | 0 | 0 | 0 |
| 12:45:00 | 0 | 0 | 908 | 77 | 46 | 1 | 0 | 0 | 19 | 0 | 5 | 0 | 0 | 0 | 3 | 0 | 1 | 0 | 0 | 0 |
| 13:00:00 | 0 | 0 | 977 | 69 | 48 | 2 | 0 | 0 | 20 | 1 | 5 | 0 | 0 | 0 | 3 | 0 | 2 | 1 | 0 | 0 |
| 13:15:00 | 0 | 0 | 1037 | 60 | 49 | 1 | 0 | 0 | 23 | 3 | 5 | 0 | 0 | 0 | 3 | 0 | 2 | 0 | 0 | 0 |
| 13:30:00 | 0 | 0 | 1104 | 67 | 49 | 0 | 0 | 0 | 25 | 2 | 5 | 0 | 0 | 0 | 3 | 0 | 2 | 0 | 0 | 0 |
| 13:45:00 | 0 | 0 | 1104 | 0 | 49 | 0 | 0 | 0 | 25 | 0 | 5 | 0 | 0 | 0 | 3 | 0 | 2 | 0 | 0 | 0 |
| 15:00:00 | 0 | 0 | 1104 | 0 | 49 | 0 | 0 | 0 | 25 | 0 | 5 | 0 | 0 | 0 | 3 | 0 | 2 | 0 | 0 | 0 |
| 15:15:00 | 0 | 0 | 1194 | 90 | 49 | 0 | 0 | 0 | 25 | 0 | 5 | 0 | 0 | 0 | 3 | 0 | 2 | 0 | 0 | 0 |
| 15:30:00 | 0 | 0 | 1301 | 107 | 50 | 1 | 0 | 0 | 25 | 0 | 5 | 0 | 0 | 0 | 3 | 0 | 2 | 0 | 0 | 0 |
| 15:45:00 | 0 | 0 | 1397 | 96 | 53 | 3 | 0 | 0 | 26 | 1 | 5 | 0 | 0 | 0 | 3 | 0 | 2 | 0 | 0 | 0 |
| 16:00:00 | 0 | 0 | 1507 | 110 | 56 | 3 | 0 | 0 | 26 | 0 | 5 | 0 | 0 | 0 | 3 | 0 | 2 | 0 | 0 | 0 |
| 16:15:00 | 0 | 0 | 1627 | 120 | 58 | 2 | 0 | 0 | 26 | 0 | 5 | 0 | 0 | 0 | 4 | 0 | 2 | 0 | 0 | 0 |
| 16:30:00 | 0 | 0 | 1746 | 119 | 60 | 2 | 0 | 0 | 26 | 0 | 5 | 0 | 0 | 0 | 4 | 0 | 2 | 0 | 0 | 0 |
| 16:45:00 | 0 | 0 | 1882 | 136 | 62 | 2 | 0 | 0 | 27 | 1 | 5 | 0 | 0 | 0 | 5 | 1 | 2 | 0 | 0 | 0 |
| 17:00:00 | 0 | 0 | 2001 | 119 | 64 | 2 | 0 | 0 | 28 | 1 | 5 | 0 | 0 | 0 | 6 | 1 | 3 | 1 | 0 | 0 |
| 17:15:00 | 0 | 0 | 2114 | 113 | 65 | 1 | 0 | 0 | 28 | 0 | 5 | 0 | 0 | 0 | 6 | 0 | 3 | 0 | 0 | 0 |
| 17:30:00 | 0 | 0 | 2237 | 123 | 66 | 1 | 0 | 0 | 28 | 0 | 5 | 0 | 0 | 0 | 6 | 0 | 3 | 0 | 0 | 0 |
| 17:45:00 | 0 | 0 | 2350 | 113 | 68 | 2 | 0 | 0 | 28 | 0 | 5 | 0 | 0 | 0 | 8 | 2 | 3 | 0 | 0 | 0 |
| 18:00:00 | 0 | 0 | 2478 | 128 | 69 | 1 | 0 | 0 | 28 | 0 | 5 | 0 | 0 | 0 | 9 | 1 | 3 | 0 | 0 | 0 |
| 18:15:00 | 0 | 0 | 2478 | 0 | 69 | 0 | 0 | 0 | 28 | 0 | 5 | 0 | 0 | 0 | 9 | 0 | 3 | 0 | 0 | 0 |
| 18:15:15 | 0 | 0 | 2478 | 0 | 69 | 0 | 0 | 0 | 28 | 0 | 5 | 0 | 0 | 0 | 9 | 0 | 3 | 0 | 0 | 0 |



Count Date: 19-Jul-23 Site #: 2317800002

| Interval Time | Passenger Cars - East Approach | | | | | | Trucks - East Approach | | | | | | Cyclists - East Approach | | | | | | Pedestrians | |
|---------------|--------------------------------|------|------|------|-------|------|------------------------|------|------|------|-------|------|--------------------------|------|------|------|-------|------|-------------|------|
| | Left | | Thru | | Right | | Left | | Thru | | Right | | Left | | Thru | | Right | | East Cross | |
| | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr |
| 7:00:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 7:15:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 7:30:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 7:45:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 8:00:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 8:15:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 8:30:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 8:45:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 9:00:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 9:15:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 9:30:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 9:45:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 10:00:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 10:15:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 11:30:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 11:45:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 12:00:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 12:15:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 12:30:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 12:45:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 13:00:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 13:15:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 13:30:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 13:45:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 15:00:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 15:15:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 15:30:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 15:45:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 16:00:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 16:15:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 16:30:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 16:45:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 17:00:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 17:15:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 17:30:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 17:45:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 18:00:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 18:15:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 18:15:15 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |



Count Date: 19-Jul-23 Site #: 2317800002

| Interval Time | Passenger Cars - South Approach | | | | | | Trucks - South Approach | | | | | | Cyclists - South Approach | | | | | | Pedestrians | |
|---------------|---------------------------------|------|------|------|-------|------|-------------------------|------|------|------|-------|------|---------------------------|------|------|------|-------|------|-------------|------|
| | Left | | Thru | | Right | | Left | | Thru | | Right | | Left | | Thru | | Right | | South Cross | |
| | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr |
| 7:00:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 7:15:00 | 3 | 3 | 39 | 39 | 0 | 0 | 1 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 7:30:00 | 5 | 2 | 99 | 60 | 0 | 0 | 1 | 0 | 1 | 1 | 0 | 0 | 0 | 0 | 2 | 2 | 0 | 0 | 0 | 0 |
| 7:45:00 | 6 | 1 | 166 | 67 | 0 | 0 | 1 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 4 | 4 | 0 | 0 | 0 | 0 |
| 8:00:00 | 6 | 0 | 249 | 83 | 0 | 0 | 1 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 4 | 0 | 0 | 0 | 0 | 0 |
| 8:15:00 | 10 | 4 | 307 | 58 | 0 | 0 | 1 | 0 | 3 | 2 | 0 | 0 | 0 | 0 | 6 | 2 | 0 | 0 | 0 | 0 |
| 8:30:00 | 11 | 1 | 399 | 92 | 0 | 0 | 1 | 0 | 5 | 2 | 0 | 0 | 0 | 0 | 8 | 2 | 0 | 0 | 0 | 0 |
| 8:45:00 | 14 | 3 | 481 | 82 | 0 | 0 | 1 | 0 | 5 | 0 | 0 | 0 | 0 | 0 | 10 | 2 | 0 | 0 | 0 | 0 |
| 9:00:00 | 17 | 3 | 580 | 99 | 0 | 0 | 2 | 1 | 6 | 1 | 0 | 0 | 0 | 0 | 10 | 0 | 0 | 0 | 0 | 0 |
| 9:15:00 | 18 | 1 | 636 | 56 | 0 | 0 | 2 | 0 | 6 | 0 | 0 | 0 | 0 | 0 | 12 | 2 | 0 | 0 | 0 | 0 |
| 9:30:00 | 21 | 3 | 704 | 68 | 0 | 0 | 3 | 1 | 7 | 1 | 0 | 0 | 0 | 0 | 13 | 1 | 0 | 0 | 0 | 0 |
| 9:45:00 | 23 | 2 | 773 | 69 | 0 | 0 | 3 | 0 | 7 | 0 | 0 | 0 | 0 | 0 | 15 | 2 | 0 | 0 | 0 | 0 |
| 10:00:00 | 25 | 2 | 834 | 61 | 0 | 0 | 3 | 0 | 7 | 0 | 0 | 0 | 0 | 0 | 17 | 2 | 0 | 0 | 0 | 0 |
| 10:15:00 | 25 | 0 | 834 | 0 | 0 | 0 | 3 | 0 | 7 | 0 | 0 | 0 | 0 | 0 | 17 | 0 | 0 | 0 | 0 | 0 |
| 11:30:00 | 25 | 0 | 834 | 0 | 0 | 0 | 3 | 0 | 7 | 0 | 0 | 0 | 0 | 0 | 17 | 0 | 0 | 0 | 0 | 0 |
| 11:45:00 | 26 | 1 | 881 | 47 | 0 | 0 | 3 | 0 | 7 | 0 | 0 | 0 | 0 | 0 | 17 | 0 | 0 | 0 | 0 | 0 |
| 12:00:00 | 27 | 1 | 931 | 50 | 0 | 0 | 3 | 0 | 7 | 0 | 0 | 0 | 0 | 0 | 17 | 0 | 0 | 0 | 0 | 0 |
| 12:15:00 | 29 | 2 | 978 | 47 | 0 | 0 | 3 | 0 | 7 | 0 | 0 | 0 | 0 | 0 | 17 | 0 | 0 | 0 | 0 | 0 |
| 12:30:00 | 34 | 5 | 1012 | 34 | 0 | 0 | 3 | 0 | 7 | 0 | 0 | 0 | 0 | 0 | 18 | 1 | 0 | 0 | 0 | 0 |
| 12:45:00 | 38 | 4 | 1053 | 41 | 0 | 0 | 3 | 0 | 8 | 1 | 0 | 0 | 0 | 0 | 19 | 1 | 0 | 0 | 0 | 0 |
| 13:00:00 | 41 | 3 | 1105 | 52 | 0 | 0 | 3 | 0 | 8 | 0 | 0 | 0 | 0 | 0 | 20 | 2 | 0 | 0 | 0 | 0 |
| 13:15:00 | 43 | 2 | 1158 | 53 | 0 | 0 | 4 | 1 | 9 | 1 | 0 | 0 | 0 | 0 | 21 | 1 | 0 | 0 | 0 | 0 |
| 13:30:00 | 45 | 2 | 1212 | 54 | 0 | 0 | 4 | 0 | 9 | 0 | 0 | 0 | 0 | 0 | 21 | 0 | 0 | 0 | 0 | 0 |
| 13:45:00 | 45 | 0 | 1212 | 0 | 0 | 0 | 4 | 0 | 9 | 0 | 0 | 0 | 0 | 0 | 21 | 0 | 0 | 0 | 0 | 0 |
| 15:00:00 | 45 | 0 | 1212 | 0 | 0 | 0 | 4 | 0 | 9 | 0 | 0 | 0 | 0 | 0 | 21 | 0 | 0 | 0 | 0 | 0 |
| 15:15:00 | 46 | 1 | 1260 | 48 | 0 | 0 | 5 | 1 | 10 | 1 | 0 | 0 | 0 | 0 | 21 | 0 | 0 | 0 | 0 | 0 |
| 15:30:00 | 47 | 1 | 1304 | 44 | 0 | 0 | 5 | 0 | 12 | 2 | 0 | 0 | 0 | 0 | 22 | 1 | 0 | 0 | 0 | 0 |
| 15:45:00 | 53 | 6 | 1377 | 73 | 0 | 0 | 5 | 0 | 12 | 0 | 0 | 0 | 0 | 0 | 23 | 1 | 0 | 0 | 0 | 0 |
| 16:00:00 | 53 | 0 | 1446 | 69 | 0 | 0 | 5 | 0 | 12 | 0 | 0 | 0 | 0 | 0 | 24 | 1 | 0 | 0 | 0 | 0 |
| 16:15:00 | 53 | 0 | 1491 | 45 | 0 | 0 | 5 | 0 | 14 | 2 | 0 | 0 | 0 | 0 | 24 | 2 | 0 | 0 | 0 | 0 |
| 16:30:00 | 54 | 1 | 1553 | 62 | 0 | 0 | 5 | 0 | 15 | 0 | 0 | 0 | 0 | 0 | 25 | 1 | 0 | 0 | 0 | 0 |
| 16:45:00 | 56 | 2 | 1619 | 66 | 0 | 0 | 5 | 0 | 15 | 0 | 0 | 0 | 0 | 0 | 26 | 1 | 0 | 0 | 0 | 0 |
| 17:00:00 | 57 | 1 | 1686 | 67 | 0 | 0 | 5 | 0 | 16 | 1 | 0 | 0 | 0 | 0 | 26 | 0 | 0 | 0 | 0 | 0 |
| 17:15:00 | 58 | 1 | 1738 | 52 | 0 | 0 | 5 | 0 | 19 | 2 | 0 | 0 | 0 | 0 | 27 | 1 | 0 | 0 | 0 | 0 |
| 17:30:00 | 58 | 0 | 1794 | 56 | 0 | 0 | 5 | 0 | 19 | 0 | 0 | 0 | 0 | 0 | 28 | 1 | 0 | 0 | 0 | 0 |
| 17:45:00 | 60 | 2 | 1856 | 62 | 0 | 0 | 5 | 0 | 19 | 0 | 0 | 0 | 0 | 0 | 30 | 2 | 0 | 0 | 0 | 0 |
| 18:00:00 | 60 | 0 | 1910 | 54 | 0 | 0 | 5 | 0 | 19 | 0 | 0 | 0 | 0 | 0 | 32 | 2 | 0 | 0 | 0 | 0 |
| 18:15:00 | 60 | 0 | 1910 | 0 | 0 | 0 | 5 | 0 | 19 | 0 | 0 | 0 | 0 | 0 | 32 | 0 | 0 | 0 | 0 | 0 |
| 18:15:15 | 60 | 0 | 1910 | 0 | 0 | 0 | 5 | 0 | 19 | 0 | 0 | 0 | 0 | 0 | 32 | 0 | 0 | 0 | 0 | 0 |



Transportation Services - Traffic Services

Turning Movement Count - Study Results

CEDARVIEW RD @ FALLOWFIELD RD

Survey Date: Tuesday, January 07, 2020

Start Time: 07:00


WO No: 39248

Device: Miovision

Full Study Diagram

Count Date: 19-Jul-23 Site #: 2317800002

| Interval Time | Passenger Cars - West Approach | | | | | | | | Trucks - West Approach | | | | | | | | Cyclists - West Approach | | | | | | | | Pedestrians | |
|---------------|--------------------------------|------|-----|------|------|------|-----|------|------------------------|------|-----|------|------|------|-----|------|--------------------------|------|-----|------|------|------|-----|------|-------------|------|
| | Left | | | | Thru | | | | Left | | | | Thru | | | | Right | | | | Thru | | | | West Cross | |
| | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr |
| 7:00:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 7:15:00 | 3 | 3 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 7:30:00 | 4 | 1 | 0 | 0 | 1 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 7:45:00 | 5 | 1 | 0 | 0 | 2 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 8:00:00 | 5 | 0 | 0 | 0 | 4 | 2 | 1 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 1 |
| 8:15:00 | 5 | 0 | 0 | 0 | 7 | 3 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 |
| 8:30:00 | 6 | 1 | 0 | 0 | 7 | 0 | 2 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 |
| 8:45:00 | 8 | 2 | 0 | 0 | 7 | 0 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 |
| 9:00:00 | 8 | 0 | 0 | 0 | 9 | 2 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 |
| 9:15:00 | 17 | 9 | 0 | 0 | 13 | 4 | 3 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 |
| 9:30:00 | 18 | 1 | 0 | 0 | 14 | 1 | 5 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 |
| 9:45:00 | 18 | 0 | 0 | 0 | 16 | 2 | 5 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 |
| 10:00:00 | 21 | 3 | 0 | 0 | 16 | 0 | 5 | 0 | 0 | 0 | 0 | 1 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 |
| 10:15:00 | 21 | 0 | 0 | 0 | 16 | 0 | 5 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 |
| 11:30:00 | 21 | 0 | 0 | 0 | 16 | 0 | 5 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 |
| 11:45:00 | 27 | 6 | 0 | 0 | 20 | 4 | 6 | 1 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 |
| 12:00:00 | 32 | 5 | 0 | 0 | 23 | 3 | 6 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 |
| 12:15:00 | 33 | 1 | 0 | 0 | 26 | 3 | 6 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 |
| 12:30:00 | 36 | 3 | 0 | 0 | 27 | 1 | 6 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 |
| 12:45:00 | 37 | 1 | 0 | 0 | 31 | 4 | 6 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 |
| 13:00:00 | 38 | 1 | 0 | 0 | 32 | 1 | 6 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 |
| 13:15:00 | 41 | 3 | 0 | 0 | 32 | 0 | 7 | 1 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 |
| 13:30:00 | 46 | 5 | 0 | 0 | 32 | 0 | 7 | 0 | 0 | 0 | 0 | 2 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 |
| 13:45:00 | 46 | 0 | 0 | 0 | 32 | 0 | 7 | 0 | 0 | 0 | 0 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 |
| 15:00:00 | 46 | 0 | 0 | 0 | 32 | 0 | 7 | 0 | 0 | 0 | 0 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 |
| 15:15:00 | 46 | 0 | 0 | 0 | 34 | 2 | 8 | 1 | 0 | 0 | 0 | 3 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 |
| 15:30:00 | 49 | 3 | 0 | 0 | 35 | 1 | 8 | 0 | 0 | 0 | 0 | 3 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 |
| 15:45:00 | 53 | 4 | 0 | 0 | 37 | 2 | 8 | 0 | 0 | 0 | 0 | 3 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 |
| 16:00:00 | 54 | 1 | 0 | 0 | 38 | 1 | 8 | 0 | 0 | 0 | 0 | 3 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 |
| 16:15:00 | 56 | 2 | 0 | 0 | 42 | 4 | 8 | 0 | 0 | 0 | 0 | 3 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 |
| 16:30:00 | 61 | 5 | 0 | 0 | 46 | 4 | 8 | 0 | 0 | 0 | 0 | 4 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 |
| 16:45:00 | 64 | 3 | 0 | 0 | 52 | 6 | 9 | 0 | 0 | 0 | 0 | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 |
| 17:00:00 | 66 | 2 | 0 | 0 | 52 | 0 | 9 | 0 | 0 | 0 | 0 | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 |
| 17:15:00 | 66 | 0 | 0 | 0 | 54 | 2 | 9 | 0 | 0 | 0 | 0 | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 |
| 17:30:00 | 69 | 3 | 0 | 0 | 56 | 2 | 9 | 0 | 0 | 0 | 0 | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 |
| 17:45:00 | 73 | 4 | 0 | 0 | 57 | 1 | 9 | 0 | 0 | 0 | 0 | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 |
| 18:00:00 | 73 | 0 | 0 | 0 | 59 | 2 | 9 | 0 | 0 | 0 | 0 | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 |
| 18:15:00 | 73 | 0 | 0 | 0 | 59 | 0 | 9 | 0 | 0 | 0 | 0 | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 |
| 18:15:15 | 73 | 0 | 0 | 0 | 59 | 0 | 9 | 0 | 0 | 0 | 0 | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 |





Transportation Services - Traffic Services

Turning Movement Count - Study Results

CEDARVIEW RD @ FALLOWFIELD RD


Survey Date: Tuesday, January 07, 2020

WO No: 39248

Start Time: 07:00

Device: Miovision

Full Study Peak Hour Diagram



5469190 - TUE JAN 07 2020 - 8HRS - LORETTA



Transportation Services - Traffic Services

Turning Movement Count - Peak Hour Diagram


CEDARVIEW RD @ FALLOWFIELD RD

Survey Date: Tuesday, January 07, 2020

WO No: 39248

Start Time: 07:00

Device: Miovision



Comments 5469190 - TUE JAN 07 2020 - 8HRS - LORETTA



Transportation Services - Traffic Services

Turning Movement Count - Peak Hour Diagram


CEDARVIEW RD @ FALLOWFIELD RD

Survey Date: Tuesday, January 07, 2020

Start Time: 07:00

WO No: 39248

Device: Miovision



Comments 5469190 - TUE JAN 07 2020 - 8HRS - LORETTA



Transportation Services - Traffic Services

Turning Movement Count - Peak Hour Diagram


CEDARVIEW RD @ FALLOWFIELD RD

Survey Date: Tuesday, January 07, 2020

Start Time: 07:00

WO No: 39248

Device: Miovision



Comments 5469190 - TUE JAN 07 2020 - 8HRS - LORETTA



Transportation Services - Traffic Services

Turning Movement Count - Study Results

CEDARVIEW RD @ FALLOWFIELD RD

Survey Date: Tuesday, January 07, 2020

WO No: 39248

Start Time: 07:00

Device: Miovision

Full Study Summary (8 HR Standard)

Survey Date: Tuesday, January 07, 2020

Total Observed U-Turns

AADT Factor

Northbound: 0 Southbound: 0

1.10

Eastbound: 0 Westbound: 0

| CEDARVIEW RD | | | | | | | | | | FALLOWFIELD RD | | | | | | | | | |
|---|-----|------|------|--------|------------|------|-----|--------|---------|----------------|------|-----|--------|------|-----------|------|--------|---------|-------------|
| Northbound | | | | | Southbound | | | | | Eastbound | | | | | Westbound | | | | |
| Period | LT | ST | RT | NB TOT | LT | ST | RT | SB TOT | STR TOT | LT | ST | RT | EB TOT | LT | ST | RT | WB TOT | STR TOT | Grand Total |
| 07:00 08:00 | 38 | 233 | 186 | 457 | 75 | 50 | 10 | 135 | 592 | 45 | 684 | 10 | 739 | 25 | 331 | 149 | 505 | 1244 | 1836 |
| 08:00 09:00 | 47 | 229 | 170 | 446 | 100 | 71 | 11 | 182 | 628 | 37 | 497 | 14 | 548 | 48 | 409 | 190 | 647 | 1195 | 1823 |
| 09:00 10:00 | 27 | 132 | 102 | 261 | 45 | 67 | 17 | 129 | 390 | 30 | 267 | 16 | 313 | 57 | 279 | 101 | 437 | 750 | 1140 |
| 11:30 12:30 | 14 | 81 | 69 | 164 | 64 | 110 | 32 | 206 | 370 | 22 | 257 | 17 | 296 | 60 | 274 | 60 | 394 | 690 | 1060 |
| 12:30 13:30 | 17 | 93 | 57 | 167 | 63 | 123 | 32 | 218 | 385 | 25 | 258 | 11 | 294 | 60 | 278 | 58 | 396 | 690 | 1075 |
| 15:00 16:00 | 32 | 88 | 96 | 216 | 176 | 252 | 36 | 464 | 680 | 25 | 318 | 31 | 374 | 118 | 540 | 71 | 729 | 1103 | 1783 |
| 16:00 17:00 | 21 | 89 | 63 | 173 | 247 | 412 | 46 | 705 | 878 | 24 | 398 | 30 | 452 | 137 | 652 | 77 | 866 | 1318 | 2196 |
| 17:00 18:00 | 18 | 93 | 78 | 189 | 201 | 387 | 32 | 620 | 809 | 21 | 383 | 40 | 444 | 138 | 522 | 51 | 711 | 1155 | 1964 |
| Sub Total | 214 | 1038 | 821 | 2073 | 971 | 1472 | 216 | 2659 | 4732 | 229 | 3062 | 169 | 3460 | 643 | 3285 | 757 | 4685 | 8145 | 12877 |
| U Turns | 0 | | | | 0 | | | | 0 | 0 | | | | 0 | | | | 0 | 0 |
| Total | 214 | 1038 | 821 | 2073 | 971 | 1472 | 216 | 2659 | 4732 | 229 | 3062 | 169 | 3460 | 643 | 3285 | 757 | 4685 | 8145 | 12877 |
| EQ 12Hr | 297 | 1443 | 1141 | 2881 | 1350 | 2046 | 300 | 3696 | 6577 | 318 | 4256 | 235 | 4809 | 894 | 4566 | 1052 | 6512 | 11322 | 17899 |
| Note: These values are calculated by multiplying the totals by the appropriate expansion factor. | | | | | | | | | | 1.39 | | | | | | | | | |
| AVG 12Hr | 327 | 1587 | 1255 | 3169 | 1485 | 2948 | 433 | 4066 | 7235 | 350 | 4682 | 258 | 5290 | 983 | 5023 | 1157 | 7163 | 12454 | 19689 |
| Note: These volumes are calculated by multiplying the Equivalent 12 hr. totals by the AADT factor. | | | | | | | | | | 1.10 | | | | | | | | | |
| AVG 24Hr | 428 | 2079 | 1644 | 4151 | 1945 | 3862 | 567 | 5326 | 9478 | 458 | 6133 | 338 | 6930 | 1288 | 6580 | 1516 | 9384 | 16315 | 25793 |
| Note: These volumes are calculated by multiplying the Average Daily 12 hr. totals by 12 to 24 expansion factor. | | | | | | | | | | 1.31 | | | | | | | | | |
| Note: U-Turns provided for approach totals. Refer to 'U-Turn' Report for specific breakdown. | | | | | | | | | | | | | | | | | | | |



Transportation Services - Traffic Services

Turning Movement Count - Study Results

CEDARVIEW RD @ FALLOWFIELD RD

Survey Date: Tuesday, January 07, 2020

WO No: 39248

Start Time: 07:00

Device: Miovision

Full Study 15 Minute Increments

| CEDARVIEW RD | | | | | | | | | | FALLOWFIELD RD | | | | | | | | | |
|--------------|-----|------|-----|-------|------------|------|-----|-------|---------|----------------|------|-----|-------|-----|-----------|-----|-------|---------|-------------|
| Northbound | | | | | Southbound | | | | | Eastbound | | | | | Westbound | | | | |
| Time Period | LT | ST | RT | N TOT | LT | ST | RT | S TOT | STR TOT | LT | ST | RT | E TOT | LT | ST | RT | W TOT | STR TOT | Grand Total |
| 07:00 07:15 | 4 | 47 | 48 | 99 | 5 | 6 | 0 | 11 | 110 | 8 | 141 | 3 | 152 | 4 | 42 | 26 | 72 | 224 | 334 |
| 07:15 07:30 | 8 | 62 | 43 | 113 | 21 | 7 | 3 | 31 | 144 | 18 | 201 | 2 | 221 | 6 | 90 | 39 | 135 | 356 | 500 |
| 07:30 07:45 | 12 | 61 | 55 | 128 | 27 | 20 | 3 | 50 | 178 | 11 | 177 | 4 | 192 | 7 | 98 | 42 | 147 | 339 | 517 |
| 07:45 08:00 | 14 | 63 | 40 | 117 | 22 | 17 | 4 | 43 | 160 | 8 | 165 | 1 | 174 | 8 | 101 | 42 | 151 | 325 | 485 |
| 08:00 08:15 | 15 | 62 | 54 | 131 | 28 | 18 | 2 | 48 | 179 | 7 | 149 | 3 | 159 | 10 | 111 | 51 | 172 | 331 | 510 |
| 08:15 08:30 | 13 | 57 | 47 | 117 | 20 | 14 | 4 | 38 | 155 | 11 | 139 | 2 | 152 | 7 | 91 | 40 | 138 | 290 | 445 |
| 08:30 08:45 | 11 | 61 | 39 | 111 | 24 | 16 | 2 | 42 | 153 | 10 | 113 | 2 | 125 | 14 | 120 | 53 | 187 | 312 | 465 |
| 08:45 09:00 | 8 | 49 | 30 | 87 | 28 | 23 | 3 | 54 | 141 | 9 | 96 | 7 | 112 | 17 | 87 | 46 | 150 | 262 | 403 |
| 09:00 09:15 | 15 | 49 | 33 | 97 | 19 | 20 | 3 | 42 | 139 | 14 | 87 | 6 | 107 | 22 | 110 | 33 | 165 | 272 | 411 |
| 09:15 09:30 | 6 | 30 | 26 | 62 | 10 | 17 | 4 | 31 | 93 | 4 | 70 | 1 | 75 | 16 | 67 | 26 | 109 | 184 | 277 |
| 09:30 09:45 | 4 | 22 | 24 | 50 | 8 | 14 | 7 | 29 | 79 | 8 | 56 | 5 | 69 | 10 | 58 | 26 | 94 | 163 | 242 |
| 09:45 10:00 | 2 | 31 | 19 | 52 | 8 | 16 | 3 | 27 | 79 | 4 | 54 | 4 | 62 | 9 | 44 | 16 | 69 | 131 | 210 |
| 11:30 11:45 | 3 | 21 | 15 | 39 | 22 | 28 | 4 | 54 | 93 | 3 | 60 | 5 | 68 | 15 | 69 | 14 | 98 | 166 | 259 |
| 11:45 12:00 | 3 | 25 | 17 | 45 | 10 | 27 | 7 | 44 | 89 | 6 | 68 | 3 | 77 | 15 | 74 | 12 | 101 | 178 | 267 |
| 12:00 12:15 | 3 | 21 | 18 | 42 | 20 | 32 | 13 | 65 | 107 | 6 | 53 | 7 | 66 | 12 | 62 | 20 | 94 | 160 | 267 |
| 12:15 12:30 | 5 | 14 | 19 | 38 | 12 | 23 | 8 | 43 | 81 | 7 | 76 | 2 | 85 | 18 | 69 | 14 | 101 | 186 | 267 |
| 12:30 12:45 | 4 | 35 | 12 | 51 | 17 | 35 | 8 | 60 | 111 | 8 | 65 | 1 | 74 | 9 | 63 | 14 | 86 | 160 | 271 |
| 12:45 13:00 | 7 | 19 | 13 | 39 | 17 | 37 | 4 | 58 | 97 | 9 | 67 | 2 | 78 | 13 | 66 | 13 | 92 | 170 | 267 |
| 13:00 13:15 | 4 | 21 | 17 | 42 | 17 | 25 | 7 | 49 | 91 | 1 | 52 | 3 | 56 | 21 | 66 | 19 | 106 | 162 | 253 |
| 13:15 13:30 | 2 | 18 | 15 | 35 | 12 | 26 | 13 | 51 | 86 | 7 | 74 | 5 | 86 | 17 | 83 | 12 | 112 | 198 | 284 |
| 15:00 15:15 | 7 | 19 | 21 | 47 | 47 | 52 | 8 | 107 | 154 | 7 | 72 | 6 | 85 | 33 | 114 | 23 | 170 | 255 | 409 |
| 15:15 15:30 | 5 | 35 | 17 | 57 | 43 | 65 | 7 | 115 | 172 | 4 | 69 | 6 | 79 | 19 | 134 | 16 | 169 | 248 | 420 |
| 15:30 15:45 | 11 | 16 | 20 | 47 | 27 | 57 | 6 | 90 | 137 | 6 | 87 | 10 | 103 | 30 | 150 | 13 | 193 | 296 | 433 |
| 15:45 16:00 | 9 | 18 | 38 | 65 | 59 | 78 | 15 | 152 | 217 | 8 | 90 | 9 | 107 | 36 | 142 | 19 | 197 | 304 | 521 |
| 16:00 16:15 | 11 | 14 | 16 | 41 | 51 | 97 | 12 | 160 | 201 | 6 | 96 | 7 | 109 | 35 | 168 | 21 | 224 | 333 | 534 |
| 16:15 16:30 | 5 | 30 | 10 | 45 | 74 | 126 | 12 | 212 | 257 | 5 | 92 | 9 | 106 | 37 | 158 | 17 | 212 | 318 | 575 |
| 16:30 16:45 | 4 | 28 | 17 | 49 | 43 | 85 | 14 | 142 | 191 | 8 | 104 | 6 | 118 | 33 | 171 | 23 | 227 | 345 | 536 |
| 16:45 17:00 | 1 | 17 | 20 | 38 | 79 | 104 | 8 | 191 | 229 | 5 | 106 | 8 | 119 | 32 | 155 | 16 | 203 | 322 | 551 |
| 17:00 17:15 | 8 | 32 | 13 | 53 | 49 | 105 | 8 | 162 | 215 | 5 | 100 | 11 | 116 | 28 | 139 | 14 | 181 | 297 | 512 |
| 17:15 17:30 | 5 | 13 | 17 | 35 | 49 | 106 | 14 | 169 | 204 | 9 | 112 | 15 | 136 | 42 | 136 | 10 | 188 | 324 | 528 |
| 17:30 17:45 | 2 | 24 | 28 | 54 | 52 | 98 | 6 | 156 | 210 | 4 | 93 | 7 | 104 | 38 | 134 | 16 | 188 | 292 | 502 |
| 17:45 18:00 | 3 | 24 | 20 | 47 | 51 | 78 | 4 | 133 | 180 | 3 | 78 | 7 | 88 | 30 | 113 | 11 | 154 | 242 | 422 |
| Total: | 214 | 1038 | 821 | 2073 | 971 | 1472 | 216 | 2659 | 4732 | 229 | 3062 | 169 | 3460 | 643 | 3285 | 757 | 4685 | 8145 | 12877 |

Note: U-Turns are included in Totals.



Transportation Services - Traffic Services

Turning Movement Count - Study Results

CEDARVIEW RD @ FALLOWFIELD RD

Survey Date: Tuesday, January 07, 2020

WO No: 39248

Start Time: 07:00

Device: Miovision

Full Study Cyclist Volume

| | CEDARVIEW RD | | | FALLOWFIELD RD | | | |
|-------------|--------------|------------|--------------|----------------|-----------|--------------|-------------|
| Time Period | Northbound | Southbound | Street Total | Eastbound | Westbound | Street Total | Grand Total |
| 07:00 07:15 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 07:15 07:30 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 07:30 07:45 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 07:45 08:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 08:00 08:15 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 08:15 08:30 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 08:30 08:45 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 08:45 09:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 09:00 09:15 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 09:15 09:30 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 09:30 09:45 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 09:45 10:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 11:30 11:45 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 11:45 12:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 12:00 12:15 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 12:15 12:30 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 12:30 12:45 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 12:45 13:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 13:00 13:15 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 13:15 13:30 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 15:00 15:15 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 15:15 15:30 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 15:30 15:45 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 15:45 16:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 16:00 16:15 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 16:15 16:30 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 16:30 16:45 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 16:45 17:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 17:00 17:15 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 17:15 17:30 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 17:30 17:45 | 1 | 0 | 1 | 0 | 0 | 0 | 1 |
| 17:45 18:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Total | 1 | 0 | 1 | 0 | 0 | 0 | 1 |



Transportation Services - Traffic Services

Turning Movement Count - Study Results

CEDARVIEW RD @ FALLOWFIELD RD

Survey Date: Tuesday, January 07, 2020

WO No: 39248

Start Time: 07:00

Device: Miovision

Full Study Pedestrian Volume

| CEDARVIEW RD | | | | FALLOWFIELD RD | | | | |
|--------------|----------------------------------|----------------------------------|-------|----------------------------------|----------------------------------|-------|-------------|--|
| Time Period | NB Approach (E or W Crossing) | SB Approach (E or W Crossing) | Total | EB Approach (N or S Crossing) | WB Approach (N or S Crossing) | Total | Grand Total | |
| 07:00 07:15 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| 07:15 07:30 | 1 | 0 | 1 | 0 | 0 | 0 | 1 | |
| 07:30 07:45 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| 07:45 08:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| 08:00 08:15 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| 08:15 08:30 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| 08:30 08:45 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| 08:45 09:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| 09:00 09:15 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| 09:15 09:30 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| 09:30 09:45 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| 09:45 10:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| 11:30 11:45 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| 11:45 12:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| 12:00 12:15 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| 12:15 12:30 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| 12:30 12:45 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| 12:45 13:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| 13:00 13:15 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| 13:15 13:30 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| 15:00 15:15 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| 15:15 15:30 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| 15:30 15:45 | 0 | 0 | 0 | 0 | 1 | 1 | 1 | |
| 15:45 16:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| 16:00 16:15 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| 16:15 16:30 | 0 | 1 | 1 | 0 | 0 | 0 | 1 | |
| 16:30 16:45 | 0 | 0 | 0 | 1 | 0 | 1 | 1 | |
| 16:45 17:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| 17:00 17:15 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| 17:15 17:30 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| 17:30 17:45 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| 17:45 18:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Total | 1 | 1 | 2 | 1 | 1 | 2 | 4 | |

5469190 - TUE JAN 07 2020 - 8HRS - LORETTA



Transportation Services - Traffic Services

Turning Movement Count - Study Results

CEDARVIEW RD @ FALLOWFIELD RD

Survey Date: Tuesday, January 07, 2020

WO No: 39248

Start Time: 07:00

Device: Miovision

Full Study Heavy Vehicles

| CEDARVIEW RD | | | | | | | | | | FALLOWFIELD RD | | | | | | | | | | | | |
|--------------|-------|----|----|-------|------------|----|----|-------|---------|----------------|----|-----|-------|-----|-----------|-----|-------|---------|-------------|-----|--|--|
| Northbound | | | | | Southbound | | | | | Eastbound | | | | | Westbound | | | | | | | |
| Time Period | LT | ST | RT | N TOT | LT | ST | RT | S TOT | STR TOT | LT | ST | RT | E TOT | LT | ST | RT | W TOT | STR TOT | Grand Total | | | |
| 07:00 | 07:15 | 0 | 0 | 3 | 6 | 0 | 0 | 0 | 0 | 6 | 0 | 5 | 2 | 9 | 1 | 2 | 0 | 11 | 20 | 13 | | |
| 07:15 | 07:30 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 1 | 0 | 7 | 0 | 11 | 0 | 4 | 1 | 12 | 23 | 12 | | |
| 07:30 | 07:45 | 0 | 0 | 3 | 6 | 1 | 0 | 0 | 2 | 8 | 0 | 7 | 2 | 11 | 1 | 2 | 1 | 15 | 26 | 17 | | |
| 07:45 | 08:00 | 0 | 0 | 0 | 1 | 0 | 1 | 0 | 1 | 2 | 0 | 7 | 0 | 11 | 0 | 4 | 0 | 11 | 22 | 12 | | |
| 08:00 | 08:15 | 1 | 1 | 3 | 8 | 2 | 1 | 2 | 7 | 15 | 1 | 4 | 0 | 10 | 2 | 2 | 0 | 13 | 23 | 19 | | |
| 08:15 | 08:30 | 1 | 1 | 0 | 2 | 0 | 0 | 0 | 4 | 6 | 1 | 7 | 0 | 11 | 0 | 2 | 2 | 11 | 22 | 14 | | |
| 08:30 | 08:45 | 0 | 0 | 2 | 5 | 0 | 2 | 0 | 2 | 7 | 0 | 6 | 0 | 9 | 1 | 3 | 0 | 12 | 21 | 14 | | |
| 08:45 | 09:00 | 1 | 0 | 0 | 4 | 0 | 0 | 0 | 0 | 4 | 0 | 3 | 2 | 14 | 1 | 8 | 0 | 12 | 26 | 15 | | |
| 09:00 | 09:15 | 9 | 3 | 3 | 17 | 0 | 0 | 1 | 4 | 21 | 0 | 2 | 0 | 29 | 2 | 17 | 0 | 24 | 53 | 37 | | |
| 09:15 | 09:30 | 0 | 1 | 0 | 1 | 1 | 0 | 0 | 3 | 4 | 0 | 6 | 0 | 13 | 0 | 7 | 1 | 15 | 28 | 16 | | |
| 09:30 | 09:45 | 0 | 1 | 1 | 4 | 0 | 1 | 0 | 4 | 8 | 1 | 2 | 0 | 5 | 1 | 2 | 1 | 7 | 12 | 10 | | |
| 09:45 | 10:00 | 0 | 0 | 0 | 1 | 0 | 1 | 1 | 4 | 5 | 0 | 5 | 0 | 7 | 0 | 1 | 2 | 8 | 15 | 10 | | |
| 11:30 | 11:45 | 0 | 0 | 1 | 2 | 1 | 0 | 0 | 1 | 3 | 0 | 7 | 0 | 12 | 1 | 5 | 0 | 15 | 27 | 15 | | |
| 11:45 | 12:00 | 0 | 3 | 0 | 6 | 0 | 1 | 1 | 5 | 11 | 0 | 3 | 1 | 11 | 1 | 6 | 0 | 10 | 21 | 16 | | |
| 12:00 | 12:15 | 0 | 0 | 2 | 4 | 0 | 1 | 0 | 2 | 6 | 0 | 5 | 0 | 5 | 1 | 0 | 1 | 9 | 14 | 10 | | |
| 12:15 | 12:30 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | 0 | 5 | 0 | 3 | 0 | 5 | 10 | 5 | | |
| 12:30 | 12:45 | 0 | 1 | 2 | 6 | 0 | 1 | 0 | 3 | 9 | 1 | 2 | 0 | 7 | 2 | 4 | 0 | 10 | 17 | 13 | | |
| 12:45 | 13:00 | 1 | 0 | 0 | 1 | 0 | 0 | 1 | 2 | 3 | 1 | 4 | 0 | 9 | 0 | 2 | 0 | 6 | 15 | 9 | | |
| 13:00 | 13:15 | 0 | 1 | 1 | 3 | 0 | 0 | 0 | 1 | 4 | 0 | 5 | 0 | 9 | 1 | 4 | 0 | 11 | 20 | 12 | | |
| 13:15 | 13:30 | 0 | 0 | 0 | 1 | 0 | 1 | 1 | 2 | 3 | 0 | 7 | 0 | 16 | 0 | 8 | 0 | 15 | 31 | 17 | | |
| 15:00 | 15:15 | 0 | 0 | 0 | 2 | 1 | 0 | 0 | 1 | 3 | 0 | 6 | 1 | 14 | 1 | 7 | 0 | 15 | 29 | 16 | | |
| 15:15 | 15:30 | 0 | 1 | 0 | 4 | 0 | 1 | 0 | 2 | 6 | 0 | 4 | 1 | 8 | 1 | 3 | 0 | 8 | 16 | 11 | | |
| 15:30 | 15:45 | 0 | 0 | 1 | 4 | 0 | 0 | 0 | 0 | 4 | 0 | 2 | 2 | 6 | 1 | 2 | 0 | 6 | 12 | 8 | | |
| 15:45 | 16:00 | 1 | 0 | 2 | 8 | 0 | 2 | 0 | 3 | 11 | 1 | 1 | 0 | 5 | 3 | 2 | 0 | 8 | 13 | 12 | | |
| 16:00 | 16:15 | 1 | 0 | 1 | 2 | 0 | 0 | 0 | 0 | 2 | 0 | 2 | 0 | 9 | 0 | 6 | 0 | 9 | 18 | 10 | | |
| 16:15 | 16:30 | 1 | 0 | 0 | 2 | 0 | 0 | 0 | 0 | 2 | 0 | 2 | 0 | 8 | 1 | 5 | 0 | 8 | 16 | 9 | | |
| 16:30 | 16:45 | 0 | 2 | 1 | 5 | 0 | 0 | 1 | 3 | 8 | 0 | 2 | 0 | 10 | 2 | 7 | 0 | 12 | 22 | 15 | | |
| 16:45 | 17:00 | 0 | 1 | 0 | 3 | 2 | 1 | 0 | 4 | 7 | 0 | 2 | 0 | 3 | 1 | 1 | 0 | 6 | 9 | 8 | | |
| 17:00 | 17:15 | 0 | 1 | 1 | 4 | 0 | 1 | 0 | 2 | 6 | 0 | 3 | 0 | 4 | 1 | 1 | 0 | 6 | 10 | 8 | | |
| 17:15 | 17:30 | 1 | 0 | 0 | 4 | 0 | 0 | 0 | 1 | 5 | 1 | 1 | 0 | 3 | 3 | 0 | 0 | 4 | 7 | 6 | | |
| 17:30 | 17:45 | 0 | 2 | 1 | 5 | 0 | 0 | 0 | 2 | 7 | 0 | 2 | 0 | 5 | 2 | 3 | 0 | 8 | 13 | 10 | | |
| 17:45 | 18:00 | 0 | 0 | 1 | 2 | 0 | 0 | 0 | 1 | 3 | 1 | 2 | 0 | 4 | 1 | 1 | 0 | 5 | 9 | 6 | | |
| Total: | None | 17 | 19 | 29 | 123 | 8 | 15 | 8 | 67 | 190 | 8 | 125 | 11 | 293 | 32 | 124 | 9 | 327 | 620 | 405 | | |



Transportation Services - Traffic Services

Turning Movement Count - Study Results

CEDARVIEW RD @ FALLOWFIELD RD

Survey Date: Tuesday, January 07, 2020

WO No: 39248

Start Time: 07:00

Device: Miovision

Full Study 15 Minute U-Turn Total

| CEDARVIEW RD | | | | FALLOWFIELD RD | | | |
|--------------|-------|----------------------------|----------------------------|---------------------------|---------------------------|-------|--|
| Time Period | | Northbound U-Turn Total | Southbound U-Turn Total | Eastbound U-Turn Total | Westbound U-Turn Total | Total | |
| 07:00 | 07:15 | 0 | 0 | 0 | 0 | 0 | |
| 07:15 | 07:30 | 0 | 0 | 0 | 0 | 0 | |
| 07:30 | 07:45 | 0 | 0 | 0 | 0 | 0 | |
| 07:45 | 08:00 | 0 | 0 | 0 | 0 | 0 | |
| 08:00 | 08:15 | 0 | 0 | 0 | 0 | 0 | |
| 08:15 | 08:30 | 0 | 0 | 0 | 0 | 0 | |
| 08:30 | 08:45 | 0 | 0 | 0 | 0 | 0 | |
| 08:45 | 09:00 | 0 | 0 | 0 | 0 | 0 | |
| 09:00 | 09:15 | 0 | 0 | 0 | 0 | 0 | |
| 09:15 | 09:30 | 0 | 0 | 0 | 0 | 0 | |
| 09:30 | 09:45 | 0 | 0 | 0 | 0 | 0 | |
| 09:45 | 10:00 | 0 | 0 | 0 | 0 | 0 | |
| 11:30 | 11:45 | 0 | 0 | 0 | 0 | 0 | |
| 11:45 | 12:00 | 0 | 0 | 0 | 0 | 0 | |
| 12:00 | 12:15 | 0 | 0 | 0 | 0 | 0 | |
| 12:15 | 12:30 | 0 | 0 | 0 | 0 | 0 | |
| 12:30 | 12:45 | 0 | 0 | 0 | 0 | 0 | |
| 12:45 | 13:00 | 0 | 0 | 0 | 0 | 0 | |
| 13:00 | 13:15 | 0 | 0 | 0 | 0 | 0 | |
| 13:15 | 13:30 | 0 | 0 | 0 | 0 | 0 | |
| 15:00 | 15:15 | 0 | 0 | 0 | 0 | 0 | |
| 15:15 | 15:30 | 0 | 0 | 0 | 0 | 0 | |
| 15:30 | 15:45 | 0 | 0 | 0 | 0 | 0 | |
| 15:45 | 16:00 | 0 | 0 | 0 | 0 | 0 | |
| 16:00 | 16:15 | 0 | 0 | 0 | 0 | 0 | |
| 16:15 | 16:30 | 0 | 0 | 0 | 0 | 0 | |
| 16:30 | 16:45 | 0 | 0 | 0 | 0 | 0 | |
| 16:45 | 17:00 | 0 | 0 | 0 | 0 | 0 | |
| 17:00 | 17:15 | 0 | 0 | 0 | 0 | 0 | |
| 17:15 | 17:30 | 0 | 0 | 0 | 0 | 0 | |
| 17:30 | 17:45 | 0 | 0 | 0 | 0 | 0 | |
| 17:45 | 18:00 | 0 | 0 | 0 | 0 | 0 | |
| Total | | 0 | 0 | 0 | 0 | 0 | |



Transportation Services - Traffic Services

Turning Movement Count - Study Results

FALLOWFIELD RD @ O'KEEFE CRT


Survey Date: Wednesday, June 07, 2023

WO No: 40986

Start Time: 07:00

Device: Miovision

Full Study Diagram



Transportation Services - Traffic Services

Turning Movement Count - Study Results

FALLOWFIELD RD @ O'KEEFE CRT


Survey Date: Wednesday, June 07, 2023

WO No: 40986

Start Time: 07:00

Device: Miovision

Full Study Peak Hour Diagram





Transportation Services - Traffic Services

Turning Movement Count - Peak Hour Diagram


FALLOWFIELD RD @ O'KEEFE CRT

Survey Date: Wednesday, June 07, 2023

Start Time: 07:00

WO No: 40986

Device: Miovision



Comments



Transportation Services - Traffic Services

Turning Movement Count - Peak Hour Diagram


FALLOWFIELD RD @ O'KEEFE CRT

Survey Date: Wednesday, June 07, 2023

Start Time: 07:00

WO No: 40986

Device: Miovision



Comments



Transportation Services - Traffic Services

Turning Movement Count - Peak Hour Diagram


FALLOWFIELD RD @ O'KEEFE CRT

Survey Date: Wednesday, June 07, 2023

Start Time: 07:00

WO No: 40986

Device: Miovision



Comments



Transportation Services - Traffic Services

Turning Movement Count - Study Results

FALLOWFIELD RD @ O'KEEFE CRT

Survey Date: Wednesday, June 07, 2023

Start Time: 07:00

WO No: 40986

Device: Miovision

Full Study Summary (8 HR Standard)

Survey Date: Wednesday, June 07, 2023

Total Observed U-Turns

AADT Factor

Northbound: 1 Southbound: 0
Eastbound: 1 Westbound: 2

.90

| O'KEEFE CRT | | | | | | | | | | FALLOWFIELD RD | | | | | | | | | | |
|--|------------|----|-----|--------|------------|----|-----|--------|-----------|----------------|------|-----|-----------|------|------|-----|--------|---------|-------------|--|
| Period | Northbound | | | | Southbound | | | | Eastbound | | | | Westbound | | | | WB TOT | STR TOT | Grand Total | |
| | LT | ST | RT | NB TOT | LT | ST | RT | SB TOT | STR TOT | LT | ST | RT | EB TOT | LT | ST | RT | | | | |
| 07:00-08:00 | 27 | 1 | 42 | 70 | 20 | 1 | 18 | 39 | 109 | 18 | 453 | 13 | 484 | 6 | 411 | 8 | 425 | 909 | 1018 | |
| 08:00-09:00 | 33 | 2 | 51 | 86 | 9 | 6 | 16 | 31 | 117 | 12 | 497 | 13 | 522 | 19 | 437 | 7 | 463 | 985 | 1102 | |
| 09:00-10:00 | 20 | 3 | 34 | 57 | 9 | 3 | 13 | 25 | 82 | 9 | 340 | 17 | 366 | 24 | 417 | 12 | 453 | 819 | 901 | |
| 11:30-12:30 | 13 | 4 | 21 | 38 | 10 | 3 | 22 | 35 | 73 | 18 | 309 | 12 | 339 | 22 | 359 | 9 | 390 | 729 | 802 | |
| 12:30-13:30 | 14 | 2 | 30 | 46 | 13 | 3 | 15 | 31 | 77 | 9 | 325 | 12 | 346 | 20 | 408 | 7 | 435 | 781 | 858 | |
| 15:00-16:00 | 14 | 4 | 37 | 55 | 6 | 2 | 5 | 13 | 68 | 25 | 414 | 31 | 470 | 38 | 563 | 7 | 608 | 1078 | 1146 | |
| 16:00-17:00 | 21 | 3 | 44 | 68 | 7 | 3 | 16 | 26 | 94 | 19 | 499 | 66 | 584 | 52 | 611 | 17 | 680 | 1264 | 1358 | |
| 17:00-18:00 | 18 | 4 | 39 | 61 | 8 | 3 | 16 | 27 | 88 | 20 | 462 | 41 | 523 | 54 | 539 | 8 | 601 | 1124 | 1212 | |
| Sub Total | 160 | 23 | 298 | 481 | 82 | 24 | 121 | 227 | 708 | 130 | 3299 | 205 | 3634 | 235 | 3745 | 75 | 4055 | 7689 | 8397 | |
| U Turns | 1 | | | | 0 | | | | 1 | 1 | | | | 2 | | | | 3 | 4 | |
| Total | 160 | 23 | 298 | 482 | 82 | 24 | 121 | 227 | 709 | 130 | 3299 | 205 | 3635 | 235 | 3745 | 75 | 4057 | 7692 | 8401 | |
| EQ 12Hr | 222 | 32 | 414 | 670 | 114 | 33 | 168 | 316 | 986 | 181 | 4586 | 285 | 5053 | 327 | 5206 | 104 | 5639 | 10692 | 11677 | |
| Note: These values are calculated by multiplying the totals by the appropriate expansion factor. | | | | | | | | | | | | | | 1.39 | | | | | | |
| AVG 12Hr | 200 | 29 | 373 | 603 | 103 | 39 | 198 | 284 | 887 | 163 | 4127 | 256 | 4548 | 294 | 4685 | 94 | 5075 | 9623 | 10509 | |
| Note: These volumes are calculated by multiplying the Equivalent 12 hr. totals by the AADT factor. | | | | | | | | | | | | | | .90 | | | | | | |
| AVG 24Hr | 262 | 38 | 489 | 790 | 135 | 51 | 259 | 372 | 1162 | 214 | 5406 | 335 | 5958 | 385 | 6137 | 123 | 6648 | 12606 | 13767 | |

Note: These values are calculated by multiplying the totals by the appropriate expansion factor.

1.39

Note: These volumes are calculated by multiplying the Equivalent 12 hr. totals by the AADT factor.

.90

Note: These volumes are calculated by multiplying the Average Daily 12 hr. totals by 12 to 24 expansion factor.

1.31

Note: U-Turns provided for approach totals. Refer to 'U-Turn' Report for specific breakdown.



Transportation Services - Traffic Services

Turning Movement Count - Study Results

FALLOWFIELD RD @ O'KEEFE CRT

Survey Date: Wednesday, June 07, 2023

WO No: 40986

Start Time: 07:00

Device: Miovision

Full Study 15 Minute Increments

O'KEEFE CRT

FALLOWFIELD RD

| | Northbound | | | | Southbound | | | | Eastbound | | | | Westbound | | | | | | | |
|-------------|------------|-----|----|-------|------------|----|----|-------|-----------|-----|-----|------|-----------|------|-----|------|-------|---------|-------------|-------|
| Time Period | LT | ST | RT | N TOT | LT | ST | RT | S TOT | STR TOT | LT | ST | RT | E TOT | LT | ST | RT | W TOT | STR TOT | Grand Total | |
| 07:00 | 07:15 | 5 | 1 | 15 | 21 | 5 | 0 | 2 | 7 | 28 | 3 | 68 | 3 | 74 | 2 | 95 | 0 | 97 | 171 | 199 |
| 07:15 | 07:30 | 8 | 0 | 7 | 15 | 7 | 1 | 3 | 11 | 26 | 2 | 98 | 3 | 103 | 3 | 96 | 4 | 103 | 206 | 232 |
| 07:30 | 07:45 | 9 | 0 | 11 | 20 | 7 | 0 | 7 | 14 | 34 | 5 | 134 | 3 | 142 | 1 | 109 | 1 | 111 | 253 | 287 |
| 07:45 | 08:00 | 5 | 0 | 9 | 14 | 1 | 0 | 6 | 7 | 21 | 8 | 153 | 4 | 165 | 0 | 111 | 3 | 114 | 279 | 300 |
| 08:00 | 08:15 | 7 | 0 | 15 | 22 | 2 | 2 | 1 | 5 | 27 | 4 | 136 | 1 | 141 | 4 | 85 | 0 | 89 | 230 | 257 |
| 08:15 | 08:30 | 10 | 1 | 15 | 26 | 3 | 1 | 5 | 9 | 35 | 4 | 144 | 4 | 152 | 5 | 103 | 1 | 109 | 261 | 296 |
| 08:30 | 08:45 | 8 | 1 | 13 | 22 | 0 | 0 | 4 | 4 | 26 | 2 | 110 | 2 | 114 | 6 | 140 | 3 | 149 | 263 | 289 |
| 08:45 | 09:00 | 8 | 0 | 8 | 16 | 4 | 3 | 6 | 13 | 29 | 2 | 107 | 6 | 115 | 4 | 109 | 3 | 116 | 231 | 260 |
| 09:00 | 09:15 | 5 | 0 | 11 | 17 | 2 | 0 | 5 | 7 | 24 | 2 | 84 | 1 | 87 | 7 | 106 | 3 | 116 | 203 | 227 |
| 09:15 | 09:30 | 7 | 0 | 4 | 11 | 0 | 1 | 3 | 4 | 15 | 3 | 95 | 12 | 110 | 8 | 121 | 3 | 132 | 242 | 257 |
| 09:30 | 09:45 | 4 | 2 | 10 | 16 | 2 | 1 | 1 | 4 | 20 | 2 | 89 | 1 | 92 | 7 | 118 | 4 | 129 | 221 | 241 |
| 09:45 | 10:00 | 4 | 1 | 9 | 14 | 5 | 1 | 4 | 10 | 24 | 2 | 72 | 3 | 77 | 2 | 72 | 2 | 76 | 153 | 177 |
| 11:30 | 11:45 | 3 | 0 | 4 | 7 | 0 | 0 | 2 | 2 | 9 | 3 | 86 | 1 | 90 | 4 | 103 | 1 | 109 | 199 | 208 |
| 11:45 | 12:00 | 3 | 3 | 5 | 11 | 5 | 1 | 10 | 16 | 27 | 3 | 67 | 4 | 74 | 8 | 92 | 4 | 104 | 178 | 205 |
| 12:00 | 12:15 | 5 | 1 | 5 | 11 | 2 | 0 | 3 | 5 | 16 | 7 | 74 | 4 | 85 | 5 | 93 | 3 | 101 | 186 | 202 |
| 12:15 | 12:30 | 2 | 0 | 7 | 9 | 3 | 2 | 7 | 12 | 21 | 5 | 82 | 3 | 90 | 5 | 71 | 1 | 77 | 167 | 188 |
| 12:30 | 12:45 | 2 | 1 | 8 | 11 | 5 | 0 | 1 | 6 | 17 | 4 | 86 | 1 | 91 | 4 | 119 | 2 | 125 | 216 | 233 |
| 12:45 | 13:00 | 3 | 0 | 6 | 9 | 5 | 1 | 8 | 14 | 23 | 2 | 86 | 3 | 91 | 7 | 92 | 2 | 101 | 192 | 215 |
| 13:00 | 13:15 | 5 | 1 | 12 | 18 | 0 | 1 | 1 | 2 | 20 | 3 | 69 | 3 | 75 | 4 | 112 | 0 | 116 | 191 | 211 |
| 13:15 | 13:30 | 4 | 0 | 4 | 8 | 3 | 1 | 5 | 9 | 17 | 0 | 84 | 5 | 89 | 5 | 85 | 3 | 93 | 182 | 199 |
| 15:00 | 15:15 | 2 | 1 | 4 | 7 | 1 | 0 | 0 | 1 | 8 | 7 | 90 | 7 | 104 | 8 | 144 | 2 | 155 | 259 | 267 |
| 15:15 | 15:30 | 3 | 0 | 10 | 13 | 3 | 1 | 1 | 5 | 18 | 8 | 97 | 6 | 111 | 8 | 156 | 2 | 166 | 277 | 295 |
| 15:30 | 15:45 | 2 | 1 | 15 | 18 | 2 | 0 | 1 | 3 | 21 | 7 | 107 | 7 | 122 | 10 | 131 | 0 | 141 | 263 | 284 |
| 15:45 | 16:00 | 7 | 2 | 8 | 17 | 0 | 1 | 3 | 4 | 21 | 3 | 120 | 11 | 134 | 12 | 132 | 3 | 147 | 281 | 302 |
| 16:00 | 16:15 | 3 | 0 | 9 | 12 | 1 | 1 | 4 | 6 | 18 | 8 | 129 | 20 | 157 | 13 | 160 | 8 | 181 | 338 | 356 |
| 16:15 | 16:30 | 8 | 0 | 16 | 24 | 3 | 1 | 3 | 7 | 31 | 2 | 123 | 20 | 145 | 8 | 176 | 2 | 186 | 331 | 362 |
| 16:30 | 16:45 | 2 | 3 | 12 | 17 | 1 | 1 | 6 | 8 | 25 | 5 | 124 | 10 | 139 | 11 | 117 | 4 | 132 | 271 | 296 |
| 16:45 | 17:00 | 8 | 0 | 7 | 15 | 2 | 0 | 3 | 5 | 20 | 4 | 123 | 16 | 143 | 20 | 158 | 3 | 181 | 324 | 344 |
| 17:00 | 17:15 | 8 | 0 | 4 | 12 | 2 | 0 | 2 | 4 | 16 | 6 | 115 | 9 | 130 | 19 | 125 | 2 | 146 | 276 | 292 |
| 17:15 | 17:30 | 2 | 2 | 11 | 15 | 5 | 0 | 5 | 10 | 25 | 2 | 118 | 14 | 134 | 15 | 170 | 2 | 187 | 321 | 346 |
| 17:30 | 17:45 | 4 | 0 | 16 | 20 | 1 | 1 | 5 | 7 | 27 | 5 | 123 | 10 | 138 | 11 | 123 | 1 | 135 | 273 | 300 |
| 17:45 | 18:00 | 4 | 2 | 8 | 14 | 0 | 2 | 4 | 6 | 20 | 7 | 106 | 8 | 121 | 9 | 121 | 3 | 133 | 254 | 274 |
| Total: | | 160 | 23 | 298 | 482 | 82 | 24 | 121 | 227 | 709 | 130 | 3299 | 205 | 3635 | 235 | 3745 | 75 | 4057 | 7692 | 8,401 |

Note: U-Turns are included in Totals.



Transportation Services - Traffic Services

Turning Movement Count - Study Results

FALLOWFIELD RD @ O'KEEFE CRT

Survey Date: Wednesday, June 07, 2023

WO No: 40986

Start Time: 07:00

Device: Miovision

Full Study Cyclist Volume

O'KEEFE CRT

FALLOWFIELD RD

| Time Period | | Northbound | Southbound | Street Total | Eastbound | Westbound | Street Total | Grand Total |
|-------------|-------|------------|------------|--------------|-----------|-----------|--------------|-------------|
| 07:00 | 07:15 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 07:15 | 07:30 | 0 | 0 | 0 | 0 | 1 | 1 | 1 |
| 07:30 | 07:45 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 07:45 | 08:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 08:00 | 08:15 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 08:15 | 08:30 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 08:30 | 08:45 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 08:45 | 09:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 09:00 | 09:15 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 09:15 | 09:30 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 09:30 | 09:45 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 09:45 | 10:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 11:30 | 11:45 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 11:45 | 12:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 12:00 | 12:15 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 12:15 | 12:30 | 0 | 0 | 0 | 1 | 0 | 1 | 1 |
| 12:30 | 12:45 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 12:45 | 13:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 13:00 | 13:15 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 13:15 | 13:30 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 15:00 | 15:15 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 15:15 | 15:30 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 15:30 | 15:45 | 2 | 0 | 2 | 0 | 0 | 0 | 2 |
| 15:45 | 16:00 | 0 | 0 | 0 | 0 | 1 | 1 | 1 |
| 16:00 | 16:15 | 0 | 0 | 0 | 1 | 0 | 1 | 1 |
| 16:15 | 16:30 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 16:30 | 16:45 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 16:45 | 17:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 17:00 | 17:15 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 17:15 | 17:30 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 17:30 | 17:45 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 17:45 | 18:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Total | | 2 | 0 | 2 | 2 | 2 | 4 | 6 |



Transportation Services - Traffic Services

Turning Movement Count - Study Results

FALLOWFIELD RD @ O'KEEFE CRT

Survey Date: Wednesday, June 07, 2023

WO No: 40986

Start Time: 07:00

Device: Miovision

Full Study Pedestrian Volume

O'KEEFE CRT

FALLOWFIELD RD

| Time Period | NB Approach (E or W Crossing) | SB Approach (E or W Crossing) | Total | EB Approach (N or S Crossing) | WB Approach (N or S Crossing) | Total | Grand Total |
|-------------|----------------------------------|----------------------------------|-------|----------------------------------|----------------------------------|-------|-------------|
| 07:00 07:15 | 0 | 0 | 0 | 1 | 1 | 2 | 2 |
| 07:15 07:30 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 07:30 07:45 | 0 | 0 | 0 | 1 | 0 | 1 | 1 |
| 07:45 08:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 08:00 08:15 | 0 | 0 | 0 | 0 | 1 | 1 | 1 |
| 08:15 08:30 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 08:30 08:45 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 08:45 09:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 09:00 09:15 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 09:15 09:30 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 09:30 09:45 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 09:45 10:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 11:30 11:45 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 11:45 12:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 12:00 12:15 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 12:15 12:30 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 12:30 12:45 | 0 | 0 | 0 | 0 | 1 | 1 | 1 |
| 12:45 13:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 13:00 13:15 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 13:15 13:30 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 15:00 15:15 | 0 | 0 | 0 | 1 | 0 | 1 | 1 |
| 15:15 15:30 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 15:30 15:45 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 15:45 16:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 16:00 16:15 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 16:15 16:30 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 16:30 16:45 | 0 | 0 | 0 | 0 | 1 | 1 | 1 |
| 16:45 17:00 | 1 | 0 | 1 | 0 | 1 | 1 | 2 |
| 17:00 17:15 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 17:15 17:30 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 17:30 17:45 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 17:45 18:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Total | 1 | 0 | 1 | 3 | 5 | 8 | 9 |



Transportation Services - Traffic Services

Turning Movement Count - Study Results

FALLOWFIELD RD @ O'KEEFE CRT

Survey Date: Wednesday, June 07, 2023

WO No: 40986

Start Time: 07:00

Device: Miovision

Full Study Heavy Vehicles

O'KEEFE CRT

FALLOWFIELD RD

| Time Period | Northbound | | | | Southbound | | | | Eastbound | | | | Westbound | | | | Grand Total | | | |
|-------------|------------|----|----|-------|------------|----|----|-------|-----------|----|----|-----|-----------|-----|----|-----|-------------|-------|---------|-----|
| | LT | ST | RT | N TOT | LT | ST | RT | S TOT | STR TOT | LT | ST | RT | E TOT | LT | ST | RT | | W TOT | STR TOT | |
| 07:00 | 07:15 | 0 | 1 | 0 | 1 | 1 | 0 | 0 | 2 | 3 | 0 | 9 | 0 | 16 | 0 | 7 | 0 | 17 | 33 | 18 |
| 07:15 | 07:30 | 0 | 0 | 0 | 2 | 1 | 0 | 0 | 1 | 3 | 0 | 8 | 1 | 11 | 1 | 2 | 0 | 12 | 23 | 13 |
| 07:30 | 07:45 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | 2 | 1 | 10 | 0 | 15 | 0 | 4 | 1 | 15 | 30 | 16 |
| 07:45 | 08:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 1 | 1 | 3 | 0 | 9 | 0 | 5 | 0 | 8 | 17 | 9 |
| 08:00 | 08:15 | 0 | 0 | 0 | 2 | 0 | 1 | 0 | 2 | 4 | 1 | 4 | 0 | 7 | 1 | 2 | 0 | 7 | 14 | 9 |
| 08:15 | 08:30 | 0 | 0 | 1 | 3 | 2 | 1 | 0 | 3 | 6 | 0 | 7 | 1 | 15 | 0 | 7 | 0 | 17 | 32 | 19 |
| 08:30 | 08:45 | 0 | 1 | 0 | 1 | 0 | 0 | 0 | 2 | 3 | 0 | 9 | 0 | 17 | 0 | 8 | 1 | 18 | 35 | 19 |
| 08:45 | 09:00 | 0 | 0 | 1 | 3 | 0 | 2 | 0 | 2 | 5 | 0 | 6 | 0 | 7 | 0 | 1 | 0 | 8 | 15 | 10 |
| 09:00 | 09:15 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 7 | 0 | 31 | 0 | 24 | 0 | 31 | 62 | 31 |
| 09:15 | 09:30 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 1 | 1 | 3 | 0 | 13 | 0 | 9 | 0 | 12 | 25 | 13 |
| 09:30 | 09:45 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 6 | 0 | 16 | 0 | 10 | 0 | 16 | 32 | 16 |
| 09:45 | 10:00 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 2 | 2 | 0 | 4 | 0 | 8 | 0 | 4 | 1 | 10 | 18 | 10 |
| 11:30 | 11:45 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 1 | 1 | 7 | 0 | 17 | 0 | 9 | 0 | 16 | 33 | 17 |
| 11:45 | 12:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 4 | 0 | 11 | 0 | 7 | 0 | 11 | 22 | 11 |
| 12:00 | 12:15 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 6 | 0 | 11 | 0 | 5 | 0 | 11 | 22 | 11 |
| 12:15 | 12:30 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 1 | 1 | 3 | 0 | 9 | 0 | 5 | 0 | 8 | 17 | 9 |
| 12:30 | 12:45 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 1 | 1 | 0 | 8 | 0 | 17 | 0 | 9 | 0 | 18 | 35 | 18 |
| 12:45 | 13:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 7 | 0 | 12 | 0 | 5 | 0 | 12 | 24 | 12 |
| 13:00 | 13:15 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 1 | 1 | 2 | 0 | 12 | 0 | 9 | 0 | 11 | 23 | 12 |
| 13:15 | 13:30 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 6 | 0 | 11 | 0 | 5 | 0 | 11 | 22 | 11 |
| 15:00 | 15:15 | 0 | 1 | 0 | 2 | 0 | 0 | 0 | 1 | 3 | 0 | 5 | 0 | 12 | 1 | 7 | 0 | 13 | 25 | 14 |
| 15:15 | 15:30 | 0 | 0 | 1 | 1 | 1 | 0 | 0 | 2 | 3 | 1 | 6 | 0 | 13 | 0 | 6 | 0 | 14 | 27 | 15 |
| 15:30 | 15:45 | 0 | 1 | 0 | 1 | 0 | 0 | 0 | 1 | 2 | 0 | 14 | 0 | 17 | 0 | 3 | 0 | 17 | 34 | 18 |
| 15:45 | 16:00 | 0 | 0 | 1 | 3 | 0 | 0 | 1 | 1 | 4 | 0 | 7 | 1 | 17 | 1 | 8 | 0 | 17 | 34 | 19 |
| 16:00 | 16:15 | 1 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 1 | 0 | 5 | 0 | 17 | 0 | 11 | 0 | 16 | 33 | 17 |
| 16:15 | 16:30 | 3 | 0 | 1 | 4 | 0 | 0 | 1 | 2 | 6 | 1 | 4 | 0 | 22 | 0 | 13 | 0 | 18 | 40 | 23 |
| 16:30 | 16:45 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 2 | 2 | 1 | 2 | 0 | 8 | 0 | 4 | 0 | 6 | 14 | 8 |
| 16:45 | 17:00 | 1 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 1 | 0 | 3 | 0 | 9 | 0 | 5 | 0 | 8 | 17 | 9 |
| 17:00 | 17:15 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 5 | 0 | 5 | 0 | 5 | 10 | 5 |
| 17:15 | 17:30 | 0 | 0 | 2 | 2 | 0 | 0 | 1 | 1 | 3 | 0 | 3 | 0 | 4 | 0 | 0 | 0 | 5 | 9 | 6 |
| 17:30 | 17:45 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 4 | 0 | 3 | 0 | 4 | 8 | 4 |
| 17:45 | 18:00 | 1 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 1 | 0 | 1 | 0 | 4 | 0 | 2 | 0 | 3 | 7 | 4 |
| Total: | None | 6 | 4 | 7 | 28 | 7 | 4 | 4 | 32 | 60 | 10 | 170 | 3 | 397 | 4 | 204 | 3 | 395 | 792 | 426 |



Transportation Services - Traffic Services

Turning Movement Count - Study Results

FALLOWFIELD RD @ O'KEEFE CRT

Survey Date: Wednesday, June 07, 2023

WO No: 40986

Start Time: 07:00

Device: Miovision

Full Study 15 Minute U-Turn Total O'KEEFE CRT FALLOWFIELD RD

| Time Period | Northbound U-Turn Total | Southbound U-Turn Total | Eastbound U-Turn Total | Westbound U-Turn Total | Total |
|-------------|----------------------------|----------------------------|---------------------------|---------------------------|-------|
| 07:00 07:15 | 0 | 0 | 0 | 0 | 0 |
| 07:15 07:30 | 0 | 0 | 0 | 0 | 0 |
| 07:30 07:45 | 0 | 0 | 0 | 0 | 0 |
| 07:45 08:00 | 0 | 0 | 0 | 0 | 0 |
| 08:00 08:15 | 0 | 0 | 0 | 0 | 0 |
| 08:15 08:30 | 0 | 0 | 0 | 0 | 0 |
| 08:30 08:45 | 0 | 0 | 0 | 0 | 0 |
| 08:45 09:00 | 0 | 0 | 0 | 0 | 0 |
| 09:00 09:15 | 1 | 0 | 0 | 0 | 1 |
| 09:15 09:30 | 0 | 0 | 0 | 0 | 0 |
| 09:30 09:45 | 0 | 0 | 0 | 0 | 0 |
| 09:45 10:00 | 0 | 0 | 0 | 0 | 0 |
| 11:30 11:45 | 0 | 0 | 0 | 1 | 1 |
| 11:45 12:00 | 0 | 0 | 0 | 0 | 0 |
| 12:00 12:15 | 0 | 0 | 0 | 0 | 0 |
| 12:15 12:30 | 0 | 0 | 0 | 0 | 0 |
| 12:30 12:45 | 0 | 0 | 0 | 0 | 0 |
| 12:45 13:00 | 0 | 0 | 0 | 0 | 0 |
| 13:00 13:15 | 0 | 0 | 0 | 0 | 0 |
| 13:15 13:30 | 0 | 0 | 0 | 0 | 0 |
| 15:00 15:15 | 0 | 0 | 0 | 1 | 1 |
| 15:15 15:30 | 0 | 0 | 0 | 0 | 0 |
| 15:30 15:45 | 0 | 0 | 1 | 0 | 1 |
| 15:45 16:00 | 0 | 0 | 0 | 0 | 0 |
| 16:00 16:15 | 0 | 0 | 0 | 0 | 0 |
| 16:15 16:30 | 0 | 0 | 0 | 0 | 0 |
| 16:30 16:45 | 0 | 0 | 0 | 0 | 0 |
| 16:45 17:00 | 0 | 0 | 0 | 0 | 0 |
| 17:00 17:15 | 0 | 0 | 0 | 0 | 0 |
| 17:15 17:30 | 0 | 0 | 0 | 0 | 0 |
| 17:30 17:45 | 0 | 0 | 0 | 0 | 0 |
| 17:45 18:00 | 0 | 0 | 0 | 0 | 0 |
| Total | 1 | 0 | 1 | 2 | 4 |



Morning Peak Diagram

Specified Period

From: 7:00:00

To: 10:00:00

One Hour Peak

From: 7:45:00

To: 8:45:00


Municipality: Ottawa
Site #: 2317800001
Intersection: Strandherd Dr & Citigate Dr
TFR File #: 1
Count date: 19-Jul-23

Weather conditions:



Person counted:
Person prepared:
Person checked:

** Signalized Intersection **







Major Road: Strandherd Dr runs W/E



Comments



Total Count Diagram

| | | | |
|--|---|---|---|
| Municipality: Ottawa Site #: 2317800001 Intersection: Strandherd Dr & Citigate Dr TFR File #: 1 Count date: 19-Jul-23 | | Weather conditions: Person counted: Person prepared: Person checked: | |
| ** Signalized Intersection ** | | Major Road: Strandherd Dr runs W/E | |
| North Leg Total: 7499 North Entering: 4080 North Peds: 8 Peds Cross:  | Cyclists 3 0 0 3 Trucks 120 28 13 161 Cars 2753 421 742 3916 Totals 2876 449 755 | Cyclists 1 Trucks 153 Cars 3265 Totals 3419 | East Leg Total: 16127 East Entering: 8516 East Peds: 4 Peds Cross:  |
| Cyclists Trucks Cars Totals 3 570 11095 11668 |  | | Cars Trucks Cyclists Totals 661 14 1 676 7418 368 0 7786 37 17 0 54 8116 399 1 |
| Cyclists Trucks Cars Totals 0 114 2352 2466 0 350 6455 6805 0 83 1114 1197 0 547 9921 |  | | Cars Trucks Cyclists Totals 7238 373 0 7611 |
| Peds Cross:  West Peds: 5 West Entering: 10468 West Leg Total: 22136 | Cars 1572 Trucks 128 Cyclists 0 Totals 1700 | Cars 924 252 41 1217 Trucks 82 25 10 117 Cyclists 0 0 0 0 Totals 1006 277 51 | Peds Cross:  South Peds: 16 South Entering: 1334 South Leg Total: 3034 |

Comments

Traffic Count Summary

| Intersection: Strandherd Dr & Citigate Dr | | | | | Count Date: 19-Jul-23 | | Municipality: Ottawa | | | | |
|---|-----------------------------------|-------|-------|----------------|-----------------------|------------------------------------|-----------------------|-----------------------------------|-------|-------|----------------|
| North Approach Totals | | | | | | North/South Total Approaches | South Approach Totals | | | | |
| Hour Ending | Includes Cars, Trucks, & Cyclists | | | | Total Peds | | Hour Ending | Includes Cars, Trucks, & Cyclists | | | |
| | Left | Thru | Right | Grand Total | | | | Left | Thru | Right | Grand Total |
| 7:00:00 | 0 | 0 | 0 | 0 | 0 | 0 | 7:00:00 | 0 | 0 | 0 | 0 |
| 8:00:00 | 41 | 91 | 302 | 434 | 1 | 530 | 8:00:00 | 67 | 25 | 4 | 96 |
| 9:00:00 | 55 | 25 | 394 | 474 | 2 | 528 | 9:00:00 | 40 | 11 | 3 | 54 |
| 10:00:00 | 91 | 52 | 350 | 493 | 0 | 581 | 10:00:00 | 69 | 14 | 5 | 88 |
| 12:00:00 | 55 | 23 | 156 | 234 | 0 | 303 | 12:00:00 | 49 | 17 | 3 | 69 |
| 13:00:00 | 105 | 66 | 253 | 424 | 1 | 581 | 13:00:00 | 122 | 30 | 5 | 157 |
| 15:00:00 | 61 | 14 | 128 | 203 | 0 | 285 | 15:00:00 | 65 | 16 | 1 | 82 |
| 16:00:00 | 112 | 39 | 395 | 546 | 3 | 724 | 16:00:00 | 137 | 31 | 10 | 178 |
| 17:00:00 | 124 | 60 | 489 | 673 | 1 | 934 | 17:00:00 | 206 | 43 | 12 | 261 |
| 18:00:00 | 111 | 79 | 409 | 599 | 0 | 948 | 18:00:00 | 251 | 90 | 8 | 349 |
| Totals: | 755 | 449 | 2876 | 4080 | 8 | 5414 | S Totals: | 1006 | 277 | 51 | 1334 |
| | | | | | | | | | | | |
| East Approach Totals | | | | | | East/West Total Approaches | West Approach Totals | | | | |
| Hour Ending | Includes Cars, Trucks, & Cyclists | | | | Total Peds | | Hour Ending | Includes Cars, Trucks, & Cyclists | | | |
| | Left | Thru | Right | Grand Total | | | | Left | Thru | Right | Grand Total |
| 7:00:00 | 0 | 0 | 0 | 0 | 0 | 0 | 7:00:00 | 0 | 0 | 0 | 0 |
| 8:00:00 | 17 | 1055 | 38 | 1110 | 1 | 2259 | 8:00:00 | 336 | 591 | 222 | 1149 |
| 9:00:00 | 5 | 1232 | 65 | 1302 | 2 | 2455 | 9:00:00 | 376 | 654 | 123 | 1153 |
| 10:00:00 | 6 | 886 | 69 | 961 | 0 | 2045 | 10:00:00 | 252 | 728 | 104 | 1084 |
| 12:00:00 | 3 | 435 | 68 | 506 | 1 | 1083 | 12:00:00 | 127 | 374 | 76 | 577 |
| 13:00:00 | 8 | 824 | 103 | 935 | 0 | 2104 | 13:00:00 | 231 | 787 | 151 | 1169 |
| 15:00:00 | 3 | 445 | 45 | 493 | 0 | 1060 | 15:00:00 | 113 | 384 | 70 | 567 |
| 16:00:00 | 5 | 919 | 95 | 1019 | 0 | 2447 | 16:00:00 | 311 | 978 | 139 | 1428 |
| 17:00:00 | 3 | 1017 | 101 | 1121 | 0 | 2761 | 17:00:00 | 362 | 1128 | 150 | 1640 |
| 18:00:00 | 4 | 973 | 92 | 1069 | 0 | 2770 | 18:00:00 | 358 | 1181 | 162 | 1701 |
| Totals: | 54 | 7786 | 676 | 8516 | 4 | 18984 | W Totals: | 2466 | 6805 | 1197 | 10468 |
| Calculated Values for Traffic Crossing Major Street | | | | | | | | | | | |
| Hours Ending: | 8:00 | 10:00 | 12:00 | 13:00 | | | 15:00 | 16:00 | 17:00 | 18:00 | |
| Crossing Values: | 202 | 213 | 128 | 294 | | | 142 | 289 | 390 | 452 | |



Count Date: 19-Jul-23 Site #: 2317800001

| Interval Time | Passenger Cars - North Approach | | | | | | Trucks - North Approach | | | | | | Cyclists - North Approach | | | | | | Pedestrians | | |
|---------------|---------------------------------|------|------|------|-------|------|-------------------------|------|------|------|-------|------|---------------------------|------|------|------|-------|------|-------------|---|---|
| | Left | | Thru | | Right | | Left | | Thru | | Right | | Left | | Thru | | Right | | | | |
| | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr | | | |
| 7:00:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| 7:15:00 | 10 | 10 | 29 | 29 | 44 | 44 | 2 | 2 | 1 | 1 | 2 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| 7:30:00 | 16 | 6 | 67 | 38 | 102 | 58 | 2 | 0 | 1 | 0 | 3 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 1 | |
| 7:45:00 | 23 | 7 | 78 | 11 | 202 | 100 | 3 | 1 | 2 | 1 | 4 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | |
| 8:00:00 | 38 | 15 | 89 | 11 | 295 | 93 | 3 | 0 | 2 | 0 | 7 | 3 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | |
| 8:15:00 | 50 | 12 | 92 | 3 | 385 | 90 | 4 | 1 | 3 | 1 | 10 | 3 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | |
| 8:30:00 | 64 | 14 | 97 | 5 | 466 | 81 | 4 | 0 | 3 | 0 | 12 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | |
| 8:45:00 | 74 | 10 | 105 | 8 | 591 | 125 | 4 | 0 | 4 | 1 | 15 | 3 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | |
| 9:00:00 | 91 | 17 | 112 | 7 | 677 | 86 | 5 | 1 | 4 | 0 | 19 | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 2 | |
| 9:15:00 | 126 | 35 | 124 | 12 | 757 | 80 | 6 | 1 | 6 | 2 | 21 | 2 | 0 | 0 | 0 | 0 | 1 | 1 | 3 | 0 | |
| 9:30:00 | 141 | 15 | 135 | 11 | 845 | 88 | 6 | 0 | 8 | 2 | 23 | 2 | 0 | 0 | 0 | 0 | 2 | 1 | 3 | 0 | |
| 9:45:00 | 162 | 21 | 145 | 10 | 927 | 82 | 6 | 0 | 9 | 1 | 26 | 3 | 0 | 0 | 0 | 0 | 2 | 0 | 3 | 0 | |
| 10:00:00 | 179 | 17 | 158 | 13 | 1009 | 82 | 8 | 2 | 10 | 1 | 35 | 9 | 0 | 0 | 0 | 0 | 2 | 0 | 3 | 0 | |
| 10:15:00 | 179 | 0 | 158 | 0 | 1009 | 0 | 8 | 0 | 10 | 0 | 35 | 0 | 0 | 0 | 0 | 0 | 2 | 0 | 3 | 0 | |
| 11:30:00 | 179 | 0 | 158 | 0 | 1009 | 0 | 8 | 0 | 10 | 0 | 35 | 0 | 0 | 0 | 0 | 0 | 2 | 0 | 3 | 0 | |
| 11:45:00 | 201 | 22 | 167 | 9 | 1084 | 75 | 8 | 0 | 13 | 3 | 42 | 7 | 0 | 0 | 0 | 0 | 2 | 0 | 3 | 0 | |
| 12:00:00 | 233 | 32 | 178 | 11 | 1151 | 67 | 9 | 1 | 13 | 0 | 49 | 7 | 0 | 0 | 0 | 0 | 2 | 0 | 3 | 0 | |
| 12:15:00 | 271 | 38 | 191 | 13 | 1214 | 63 | 9 | 0 | 15 | 2 | 52 | 3 | 0 | 0 | 0 | 0 | 2 | 0 | 3 | 0 | |
| 12:30:00 | 294 | 23 | 213 | 22 | 1277 | 63 | 9 | 0 | 15 | 0 | 54 | 2 | 0 | 0 | 0 | 0 | 0 | 3 | 1 | 3 | 0 |
| 12:45:00 | 314 | 20 | 229 | 16 | 1338 | 61 | 10 | 1 | 16 | 1 | 56 | 2 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 4 | 1 |
| 13:00:00 | 337 | 23 | 240 | 11 | 1393 | 55 | 10 | 0 | 17 | 1 | 59 | 3 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 4 | 0 |
| 13:15:00 | 372 | 35 | 245 | 5 | 1460 | 67 | 12 | 2 | 18 | 1 | 61 | 2 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 4 | 0 |
| 13:30:00 | 396 | 24 | 253 | 8 | 1510 | 50 | 12 | 0 | 18 | 0 | 70 | 9 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 4 | 0 |
| 13:45:00 | 396 | 0 | 253 | 0 | 1510 | 0 | 12 | 0 | 18 | 0 | 70 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 4 | 0 |
| 15:00:00 | 396 | 0 | 253 | 0 | 1510 | 0 | 12 | 0 | 18 | 0 | 70 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 4 | 0 |
| 15:15:00 | 422 | 26 | 263 | 10 | 1617 | 107 | 12 | 0 | 19 | 1 | 79 | 9 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 5 | 1 |
| 15:30:00 | 448 | 26 | 275 | 12 | 1698 | 81 | 12 | 0 | 19 | 0 | 84 | 5 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 6 | 1 |
| 15:45:00 | 475 | 27 | 281 | 6 | 1788 | 90 | 13 | 1 | 21 | 2 | 90 | 6 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 6 | 0 |
| 16:00:00 | 507 | 32 | 289 | 8 | 1883 | 95 | 13 | 0 | 21 | 0 | 92 | 2 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 7 | 1 |
| 16:15:00 | 549 | 42 | 308 | 19 | 2003 | 120 | 13 | 0 | 22 | 1 | 94 | 2 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 7 | 0 |
| 16:30:00 | 577 | 28 | 321 | 13 | 2135 | 132 | 13 | 0 | 22 | 0 | 98 | 4 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 8 | 1 |
| 16:45:00 | 606 | 29 | 332 | 11 | 2256 | 121 | 13 | 0 | 23 | 1 | 99 | 1 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 8 | 0 |
| 17:00:00 | 631 | 25 | 345 | 13 | 2355 | 99 | 13 | 0 | 25 | 2 | 109 | 10 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 8 | 0 |
| 17:15:00 | 658 | 27 | 360 | 15 | 2466 | 111 | 13 | 0 | 27 | 2 | 112 | 3 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 8 | 0 |
| 17:30:00 | 680 | 22 | 377 | 17 | 2572 | 106 | 13 | 0 | 27 | 0 | 115 | 3 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 8 | 0 |
| 17:45:00 | 714 | 34 | 398 | 21 | 2671 | 99 | 13 | 0 | 28 | 1 | 117 | 2 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 8 | 0 |
| 18:00:00 | 742 | 28 | 421 | 23 | 2753 | 82 | 13 | 0 | 28 | 0 | 120 | 3 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 8 | 0 |
| 18:15:00 | 742 | 0 | 421 | 0 | 2753 | 0 | 13 | 0 | 28 | 0 | 120 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 8 | 0 |
| 18:15:15 | 742 | 0 | 421 | 0 | 2753 | 0 | 13 | 0 | 28 | 0 | 120 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 8 | 0 |



Count Date: 19-Jul-23 Site #: 2317800001

| Interval Time | Passenger Cars - East Approach | | | | | | Trucks - East Approach | | | | | | Cyclists - East Approach | | | | | | Pedestrians | | | |
|---------------|--------------------------------|------|------|------|-------|------|------------------------|------|------|------|-------|------|--------------------------|------|------|------|-------|------|-------------|---|------------|------|
| | Left | | Thru | | Right | | Left | | Thru | | Right | | Left | | Thru | | Right | | | | East Cross | |
| | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr | | | Cum | Incr |
| 7:00:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| 7:15:00 | 7 | 7 | 199 | 199 | 3 | 3 | 0 | 0 | 7 | 7 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| 7:30:00 | 9 | 2 | 457 | 258 | 12 | 9 | 2 | 2 | 15 | 8 | 1 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 1 | |
| 7:45:00 | 11 | 2 | 727 | 270 | 25 | 13 | 2 | 0 | 32 | 17 | 2 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | |
| 8:00:00 | 14 | 3 | 1010 | 283 | 36 | 11 | 3 | 1 | 45 | 13 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| 8:15:00 | 16 | 2 | 1289 | 279 | 54 | 18 | 3 | 0 | 59 | 14 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | |
| 8:30:00 | 16 | 0 | 1591 | 302 | 67 | 13 | 4 | 1 | 74 | 15 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | |
| 8:45:00 | 17 | 1 | 1900 | 309 | 80 | 13 | 5 | 1 | 91 | 17 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | |
| 9:00:00 | 17 | 0 | 2186 | 286 | 100 | 20 | 5 | 1 | 101 | 10 | 3 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 2 | |
| 9:15:00 | 20 | 3 | 2378 | 192 | 117 | 17 | 5 | 0 | 117 | 16 | 4 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | |
| 9:30:00 | 21 | 1 | 2615 | 237 | 134 | 17 | 6 | 1 | 128 | 11 | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | |
| 9:45:00 | 21 | 0 | 2811 | 196 | 150 | 16 | 6 | 0 | 144 | 16 | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | |
| 10:00:00 | 21 | 0 | 3016 | 205 | 167 | 17 | 7 | 1 | 157 | 13 | 5 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | |
| 10:15:00 | 21 | 0 | 3016 | 0 | 167 | 0 | 7 | 0 | 157 | 0 | 5 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | |
| 11:30:00 | 21 | 0 | 3016 | 0 | 167 | 0 | 7 | 0 | 157 | 0 | 5 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | |
| 11:45:00 | 23 | 2 | 3222 | 206 | 203 | 36 | 7 | 0 | 175 | 18 | 6 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | |
| 12:00:00 | 23 | 0 | 3417 | 195 | 233 | 30 | 8 | 1 | 191 | 16 | 7 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 4 | 1 | |
| 12:15:00 | 24 | 1 | 3587 | 170 | 254 | 21 | 8 | 0 | 201 | 10 | 7 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 4 | 0 | |
| 12:30:00 | 26 | 2 | 3778 | 191 | 277 | 23 | 9 | 1 | 209 | 8 | 9 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 4 | 0 | |
| 12:45:00 | 27 | 1 | 4000 | 222 | 311 | 34 | 9 | 0 | 223 | 14 | 11 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 4 | 0 | |
| 13:00:00 | 29 | 2 | 4192 | 192 | 332 | 21 | 10 | 1 | 240 | 17 | 11 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 4 | 0 | |
| 13:15:00 | 31 | 2 | 4413 | 221 | 359 | 27 | 10 | 0 | 258 | 18 | 12 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 4 | 0 | |
| 13:30:00 | 31 | 0 | 4605 | 192 | 374 | 15 | 11 | 1 | 272 | 14 | 13 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 1 | 4 | 0 |
| 13:45:00 | 31 | 0 | 4605 | 0 | 374 | 0 | 11 | 0 | 272 | 0 | 13 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 4 | 0 |
| 15:00:00 | 31 | 0 | 4605 | 0 | 374 | 0 | 11 | 0 | 272 | 0 | 13 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 4 | 0 |
| 15:15:00 | 32 | 1 | 4800 | 195 | 397 | 23 | 11 | 0 | 283 | 11 | 13 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 4 | 0 |
| 15:30:00 | 34 | 2 | 5033 | 233 | 418 | 21 | 12 | 1 | 291 | 8 | 13 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 4 | 0 |
| 15:45:00 | 34 | 0 | 5255 | 222 | 444 | 26 | 12 | 0 | 302 | 11 | 13 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 4 | 0 |
| 16:00:00 | 34 | 0 | 5490 | 235 | 468 | 24 | 13 | 1 | 306 | 4 | 14 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 4 | 0 |
| 16:15:00 | 34 | 0 | 5713 | 223 | 487 | 19 | 13 | 0 | 322 | 16 | 14 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 4 | 0 |
| 16:30:00 | 34 | 0 | 5963 | 250 | 514 | 27 | 14 | 1 | 333 | 11 | 14 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 4 | 0 |
| 16:45:00 | 34 | 0 | 6209 | 246 | 540 | 26 | 14 | 0 | 346 | 13 | 14 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 4 | 0 |
| 17:00:00 | 35 | 1 | 6464 | 255 | 569 | 29 | 15 | 1 | 349 | 3 | 14 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 4 | 0 |
| 17:15:00 | 35 | 0 | 6703 | 239 | 589 | 20 | 15 | 0 | 355 | 6 | 14 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 4 | 0 |
| 17:30:00 | 36 | 1 | 6926 | 223 | 620 | 31 | 16 | 1 | 362 | 7 | 14 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 4 | 0 |
| 17:45:00 | 36 | 0 | 7180 | 254 | 642 | 22 | 16 | 0 | 363 | 1 | 14 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 4 | 0 |
| 18:00:00 | 37 | 1 | 7418 | 238 | 661 | 19 | 17 | 1 | 368 | 5 | 14 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 4 | 0 |
| 18:15:00 | 37 | 0 | 7418 | 0 | 661 | 0 | 17 | 0 | 368 | 0 | 14 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 4 | 0 |
| 18:15:15 | 37 | 0 | 7418 | 0 | 661 | 0 | 17 | 0 | 368 | 0 | 14 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 4 | 0 |



Count Date: 19-Jul-23 Site #: 2317800001

| Interval Time | Passenger Cars - South Approach | | | | | | Trucks - South Approach | | | | | | Cyclists - South Approach | | | | | | Pedestrians | |
|---------------|---------------------------------|------|------|------|-------|------|-------------------------|------|------|------|-------|------|---------------------------|------|------|------|-------|------|-------------|------|
| | Left | | Thru | | Right | | Left | | Thru | | Right | | Left | | Thru | | Right | | | |
| | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr |
| 7:00:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 7:15:00 | 22 | 22 | 5 | 5 | 1 | 1 | 3 | 3 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 1 |
| 7:30:00 | 36 | 14 | 14 | 9 | 2 | 1 | 4 | 1 | 2 | 2 | 1 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | 1 |
| 7:45:00 | 57 | 21 | 17 | 3 | 2 | 0 | 4 | 0 | 2 | 0 | 2 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | 0 |
| 8:00:00 | 62 | 5 | 22 | 5 | 2 | 0 | 5 | 1 | 3 | 1 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 1 |
| 8:15:00 | 69 | 7 | 23 | 1 | 2 | 0 | 8 | 3 | 3 | 0 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 0 |
| 8:30:00 | 77 | 8 | 27 | 4 | 3 | 1 | 8 | 0 | 3 | 0 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 0 |
| 8:45:00 | 86 | 9 | 29 | 2 | 4 | 1 | 8 | 0 | 5 | 2 | 3 | 3 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 0 |
| 9:00:00 | 96 | 10 | 30 | 1 | 4 | 0 | 11 | 3 | 6 | 1 | 3 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 0 |
| 9:15:00 | 112 | 16 | 31 | 1 | 5 | 1 | 12 | 1 | 7 | 1 | 3 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 0 |
| 9:30:00 | 125 | 13 | 32 | 1 | 6 | 1 | 14 | 2 | 9 | 2 | 3 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 0 |
| 9:45:00 | 143 | 18 | 35 | 3 | 7 | 1 | 19 | 5 | 10 | 1 | 4 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 0 |
| 10:00:00 | 154 | 11 | 39 | 4 | 8 | 1 | 22 | 3 | 11 | 1 | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 4 | 1 |
| 10:15:00 | 154 | 0 | 39 | 0 | 8 | 0 | 22 | 0 | 11 | 0 | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 4 | 0 |
| 11:30:00 | 154 | 0 | 39 | 0 | 8 | 0 | 22 | 0 | 11 | 0 | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 4 | 0 |
| 11:45:00 | 175 | 21 | 49 | 10 | 10 | 2 | 23 | 1 | 11 | 0 | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 4 | 0 |
| 12:00:00 | 200 | 25 | 55 | 6 | 11 | 1 | 25 | 2 | 12 | 1 | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 5 | 1 |
| 12:15:00 | 215 | 15 | 61 | 6 | 12 | 1 | 28 | 3 | 12 | 0 | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 6 | 1 |
| 12:30:00 | 239 | 24 | 71 | 10 | 13 | 1 | 31 | 3 | 13 | 1 | 5 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 9 | 3 |
| 12:45:00 | 276 | 37 | 76 | 5 | 14 | 1 | 38 | 7 | 14 | 1 | 5 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 9 | 0 |
| 13:00:00 | 305 | 29 | 82 | 6 | 15 | 1 | 42 | 4 | 15 | 1 | 5 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 12 | 3 |
| 13:15:00 | 337 | 32 | 93 | 11 | 16 | 1 | 49 | 7 | 16 | 1 | 5 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 12 | 0 |
| 13:30:00 | 361 | 24 | 96 | 3 | 16 | 0 | 51 | 2 | 17 | 1 | 5 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 12 | 0 |
| 13:45:00 | 361 | 0 | 96 | 0 | 16 | 0 | 51 | 0 | 17 | 0 | 5 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 12 | 0 |
| 15:00:00 | 361 | 0 | 96 | 0 | 16 | 0 | 51 | 0 | 17 | 0 | 5 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 12 | 0 |
| 15:15:00 | 400 | 39 | 103 | 7 | 16 | 0 | 56 | 5 | 17 | 0 | 6 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 12 | 0 |
| 15:30:00 | 430 | 30 | 110 | 7 | 16 | 0 | 58 | 2 | 18 | 1 | 6 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 12 | 0 |
| 15:45:00 | 463 | 33 | 121 | 11 | 21 | 5 | 59 | 1 | 18 | 0 | 8 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 12 | 0 |
| 16:00:00 | 488 | 25 | 125 | 4 | 23 | 2 | 61 | 2 | 19 | 1 | 8 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 13 | 1 |
| 16:15:00 | 541 | 53 | 133 | 8 | 25 | 2 | 64 | 3 | 20 | 1 | 8 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 13 | 0 |
| 16:30:00 | 578 | 37 | 139 | 6 | 27 | 2 | 65 | 1 | 20 | 0 | 8 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 13 | 0 |
| 16:45:00 | 632 | 54 | 151 | 12 | 29 | 2 | 68 | 3 | 21 | 1 | 8 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 13 | 0 |
| 17:00:00 | 682 | 50 | 165 | 14 | 34 | 5 | 73 | 5 | 22 | 1 | 9 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 14 | 1 |
| 17:15:00 | 739 | 57 | 182 | 17 | 36 | 2 | 73 | 0 | 22 | 0 | 9 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 15 | 1 |
| 17:30:00 | 777 | 38 | 189 | 7 | 38 | 2 | 76 | 3 | 23 | 1 | 9 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 15 | 0 |
| 17:45:00 | 883 | 106 | 236 | 47 | 41 | 3 | 78 | 2 | 24 | 1 | 10 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 15 | 0 |
| 18:00:00 | 924 | 41 | 252 | 16 | 41 | 0 | 82 | 4 | 25 | 1 | 10 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 16 | 1 |
| 18:15:00 | 924 | 0 | 252 | 0 | 41 | 0 | 82 | 0 | 25 | 0 | 10 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 16 | 0 |
| 18:15:15 | 924 | 0 | 252 | 0 | 41 | 0 | 82 | 0 | 25 | 0 | 10 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 16 | 0 |



Count Date: 19-Jul-23 Site #: 2317800001

| Interval Time | Passenger Cars - West Approach | | | | | | Trucks - West Approach | | | | | | Cyclists - West Approach | | | | | | Pedestrians | |
|---------------|--------------------------------|------|------|------|-------|------|------------------------|------|------|------|-------|------|--------------------------|------|------|------|-------|------|-------------|--|
| | Left | | Thru | | Right | | Left | | Thru | | Right | | Left | | Thru | | Right | | | |
| | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr | Cum | Incr | West Cross | |
| 7:00:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| 7:15:00 | 54 | 54 | 90 | 90 | 71 | 71 | 5 | 5 | 13 | 13 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| 7:30:00 | 121 | 67 | 231 | 141 | 153 | 82 | 14 | 9 | 27 | 14 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | |
| 7:45:00 | 207 | 86 | 348 | 117 | 187 | 34 | 20 | 6 | 47 | 20 | 6 | 6 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | |
| 8:00:00 | 307 | 100 | 527 | 179 | 212 | 25 | 29 | 9 | 64 | 17 | 10 | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | |
| 8:15:00 | 401 | 94 | 672 | 145 | 245 | 33 | 37 | 8 | 80 | 16 | 13 | 3 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | |
| 8:30:00 | 489 | 88 | 803 | 131 | 275 | 30 | 43 | 6 | 89 | 9 | 14 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | |
| 8:45:00 | 583 | 94 | 964 | 161 | 295 | 20 | 50 | 7 | 106 | 17 | 16 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | |
| 9:00:00 | 659 | 76 | 1124 | 160 | 325 | 30 | 53 | 3 | 121 | 15 | 20 | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | |
| 9:15:00 | 733 | 74 | 1288 | 164 | 346 | 21 | 56 | 3 | 144 | 23 | 23 | 3 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | |
| 9:30:00 | 796 | 63 | 1485 | 197 | 370 | 24 | 62 | 6 | 164 | 20 | 26 | 3 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | |
| 9:45:00 | 845 | 49 | 1641 | 156 | 390 | 20 | 67 | 5 | 174 | 10 | 27 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | |
| 10:00:00 | 896 | 51 | 1787 | 146 | 420 | 30 | 68 | 1 | 186 | 12 | 29 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | |
| 10:15:00 | 896 | 0 | 1787 | 0 | 420 | 0 | 68 | 0 | 186 | 0 | 29 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | |
| 11:30:00 | 896 | 0 | 1787 | 0 | 420 | 0 | 68 | 0 | 186 | 0 | 29 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | |
| 11:45:00 | 948 | 52 | 1960 | 173 | 452 | 32 | 69 | 1 | 206 | 20 | 38 | 9 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | |
| 12:00:00 | 1020 | 72 | 2130 | 170 | 483 | 31 | 71 | 2 | 217 | 11 | 42 | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | |
| 12:15:00 | 1076 | 56 | 2304 | 174 | 517 | 34 | 75 | 4 | 225 | 8 | 48 | 6 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | |
| 12:30:00 | 1140 | 64 | 2491 | 187 | 552 | 35 | 77 | 2 | 236 | 11 | 55 | 7 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | |
| 12:45:00 | 1164 | 24 | 2657 | 166 | 580 | 28 | 80 | 3 | 253 | 17 | 58 | 3 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | |
| 13:00:00 | 1236 | 72 | 2867 | 210 | 618 | 38 | 86 | 6 | 267 | 14 | 58 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 4 | |
| 13:15:00 | 1282 | 46 | 3035 | 168 | 643 | 25 | 91 | 5 | 277 | 10 | 58 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 4 | |
| 13:30:00 | 1343 | 61 | 3232 | 197 | 682 | 39 | 92 | 1 | 286 | 9 | 64 | 6 | 0 | 0 | 0 | 0 | 0 | 0 | 4 | |
| 13:45:00 | 1343 | 0 | 3232 | 0 | 682 | 0 | 92 | 0 | 286 | 0 | 64 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 4 | |
| 15:00:00 | 1343 | 0 | 3232 | 0 | 682 | 0 | 92 | 0 | 286 | 0 | 64 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 4 | |
| 15:15:00 | 1396 | 53 | 3434 | 202 | 714 | 32 | 94 | 2 | 296 | 10 | 67 | 3 | 0 | 0 | 0 | 0 | 0 | 0 | 4 | |
| 15:30:00 | 1477 | 81 | 3689 | 255 | 744 | 30 | 95 | 1 | 302 | 6 | 68 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 4 | |
| 15:45:00 | 1546 | 69 | 3930 | 241 | 774 | 30 | 99 | 4 | 305 | 3 | 68 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 4 | |
| 16:00:00 | 1644 | 98 | 4179 | 249 | 815 | 41 | 102 | 3 | 317 | 12 | 70 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 5 | |
| 16:15:00 | 1710 | 66 | 4440 | 261 | 846 | 31 | 105 | 3 | 324 | 7 | 74 | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 5 | |
| 16:30:00 | 1826 | 116 | 4735 | 295 | 886 | 40 | 105 | 0 | 328 | 4 | 75 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 5 | |
| 16:45:00 | 1912 | 86 | 5005 | 270 | 919 | 33 | 108 | 3 | 337 | 9 | 78 | 3 | 0 | 0 | 0 | 0 | 0 | 0 | 5 | |
| 17:00:00 | 1997 | 85 | 5295 | 280 | 957 | 38 | 111 | 3 | 339 | 2 | 78 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 5 | |
| 17:15:00 | 2078 | 81 | 5555 | 270 | 996 | 39 | 111 | 0 | 341 | 2 | 80 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 5 | |
| 17:30:00 | 2182 | 104 | 5893 | 338 | 1039 | 43 | 112 | 1 | 343 | 2 | 83 | 3 | 0 | 0 | 0 | 0 | 0 | 0 | 5 | |
| 17:45:00 | 2270 | 88 | 6164 | 271 | 1081 | 42 | 114 | 2 | 348 | 5 | 83 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 5 | |
| 18:00:00 | 2352 | 82 | 6455 | 291 | 1114 | 33 | 114 | 0 | 350 | 2 | 83 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 5 | |
| 18:15:00 | 2352 | 0 | 6455 | 0 | 1114 | 0 | 114 | 0 | 350 | 0 | 83 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 5 | |
| 18:15:15 | 2352 | 0 | 6455 | 0 | 1114 | 0 | 114 | 0 | 350 | 0 | 83 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 5 | |

Appendix C

Synchro Intersection Worksheets – Existing Conditions

HCM 2010 TWSC
1: Cedarview & Onassa

Existing AM Peak Hour
4497 O'Keefe Court

| Intersection | | | | | | |
|--------------------------|------|------|------|------|------|------|
| Int Delay, s/veh | 0.6 | | | | | |
| Movement | EBL | EBR | NBL | NBT | SBT | SBR |
| Lane Configurations | W | | | W | W | |
| Traffic Vol, veh/h | 14 | 6 | 9 | 332 | 208 | 12 |
| Future Vol, veh/h | 14 | 6 | 9 | 332 | 208 | 12 |
| Conflicting Peds, #/hr | 0 | 0 | 0 | 0 | 0 | 0 |
| Sign Control | Stop | Stop | Free | Free | Free | Free |
| RT Channelized | - | None | - | None | - | None |
| Storage Length | 0 | - | - | - | - | - |
| Veh in Median Storage, # | 0 | - | - | 0 | 0 | - |
| Grade, % | 0 | - | - | 0 | 0 | - |
| Peak Hour Factor | 90 | 90 | 90 | 90 | 90 | 90 |
| Heavy Vehicles, % | 14 | 2 | 11 | 2 | 2 | 17 |
| Mvmt Flow | 16 | 7 | 10 | 369 | 231 | 13 |

| Major/Minor | Minor2 | Major1 | Major2 |
|----------------------|--------|--------|--------|
| Conflicting Flow All | 627 | 238 | 244 |
| Stage 1 | 238 | - | - |
| Stage 2 | 389 | - | - |
| Critical Hdwy | 6.54 | 6.22 | 4.21 |
| Critical Hdwy Stg 1 | 5.54 | - | - |
| Critical Hdwy Stg 2 | 5.54 | - | - |
| Follow-up Hdwy | 3.626 | 3.318 | 2.299 |
| Pot Cap-1 Maneuver | 429 | 801 | 1271 |
| Stage 1 | 774 | - | - |
| Stage 2 | 659 | - | - |
| Platoon blocked, % | - | - | - |
| Mov Cap-1 Maneuver | 425 | 801 | 1271 |
| Mov Cap-2 Maneuver | 425 | - | - |
| Stage 1 | 766 | - | - |
| Stage 2 | 659 | - | - |

| Approach | EB | NB | SB |
|----------------------|------|-----|----|
| HCM Control Delay, s | 12.6 | 0.2 | 0 |
| HCM LOS | B | | |

| Minor Lane/Major Mvmt | NBL | NBT | EBLn1 | SBT | SBR |
|-----------------------|-------|-----|-------|-----|-----|
| Capacity (veh/h) | 1271 | - | 495 | - | - |
| HCM Lane V/C Ratio | 0.008 | - | 0.045 | - | - |
| HCM Control Delay (s) | 7.9 | 0 | 12.6 | - | - |
| HCM Lane LOS | A | A | B | - | - |
| HCM 95th %tile Q(veh) | 0 | - | 0.1 | - | - |

Lanes, Volumes, Timings
2: Citigate & Fallowfield & Strandherd

Existing AM Peak Hour
4497 O'Keefe Court

| Lane Group | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|-------|-------|-------|-------|--------|-------|-------|-------|-----|-------|-------|-------|
| Lane Configurations | W | W | W | W | W | W | W | W | W | W | W | W |
| Traffic Volume (vph) | 406 | 675 | 118 | 8 | 1232 | 55 | 33 | 15 | 3 | 52 | 29 | 400 |
| Future Volume (vph) | 406 | 675 | 118 | 8 | 1232 | 55 | 33 | 15 | 3 | 52 | 29 | 400 |
| Satd. Flow (prot) | 3066 | 3103 | 1401 | 1353 | 3221 | 1483 | 2929 | 1426 | 0 | 1658 | 1664 | 1469 |
| Fit Permitted | 0.950 | | | 0.950 | | | 0.950 | | | 0.950 | | |
| Satd. Flow (perm) | 3066 | 3103 | 1401 | 1353 | 3221 | 1483 | 2927 | 1426 | 0 | 1658 | 1664 | 1450 |
| Satd. Flow (RTOR) | | | 131 | | | 225 | | 3 | | | | 405 |
| Lane Group Flow (vph) | 451 | 750 | 131 | 9 | 1369 | 61 | 37 | 20 | 0 | 58 | 32 | 444 |
| Turn Type | Prot | NA | pm+ov | Prot | NA | Perm | Prot | NA | | Prot | NA | Perm |
| Protected Phases | 13 | 10 2 | 7 | 9 | 6 | 6 | 7 | 4 | | 3 | 8 | 8 |
| Permitted Phases | | | 10 2 | | | 6 | | | | | | 8 |
| Detector Phase | 13 | 10 2 | 7 | 9 | 6 | 6 | 7 | 4 | | 3 | 8 | 8 |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 5.0 | | 5.0 | 5.0 | 10.0 | 10.0 | 5.0 | 10.0 | | 5.0 | 10.0 | 10.0 |
| Minimum Split (s) | 12.1 | | 11.5 | 12.1 | 29.9 | 29.9 | 11.5 | 48.0 | | 11.5 | 48.0 | 48.0 |
| Total Split (s) | 28.0 | | 13.0 | 13.0 | 31.0 | 31.0 | 13.0 | 48.0 | | 13.0 | 48.0 | 48.0 |
| Total Split (%) | 23.3% | | 10.8% | 10.8% | 25.8% | 25.8% | 10.8% | 40.0% | | 10.8% | 40.0% | 40.0% |
| Yellow Time (s) | 4.6 | | 3.7 | 4.6 | 4.6 | 4.6 | 3.7 | 3.7 | | 3.7 | 3.7 | 3.7 |
| All-Red Time (s) | 2.5 | | 2.8 | 2.5 | 2.3 | 2.3 | 2.8 | 3.3 | | 2.8 | 3.3 | 3.3 |
| Lost Time Adjust (s) | 0.0 | | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 |
| Total Lost Time (s) | 7.1 | | 6.5 | 7.1 | 6.9 | 6.9 | 6.5 | 7.0 | | 6.5 | 7.0 | 7.0 |
| Lead/Lag | | | Lag | Lead | | | Lag | Lead | | Lag | Lead | Lead |
| Lead-Lag Optimize? | | | Yes | Yes | | | Yes | Yes | | Yes | Yes | Yes |
| Recall Mode | None | | None | None | C-Max | C-Max | None | None | | None | None | None |
| Act Effct Green (s) | 23.1 | 79.7 | 87.4 | 6.4 | 47.7 | 47.7 | 7.0 | 12.4 | | 18.7 | 14.8 | 14.8 |
| Actuated g/C Ratio | 0.19 | 0.66 | 0.73 | 0.05 | 0.40 | 0.40 | 0.06 | 0.10 | | 0.16 | 0.12 | 0.12 |
| v/c Ratio | 0.77 | 0.36 | 0.12 | 0.12 | 1.07 | 0.08 | 0.22 | 0.13 | | 0.22 | 0.16 | 0.83 |
| Control Delay | 54.7 | 11.9 | 1.6 | 57.2 | 81.7 | 0.2 | 56.5 | 47.9 | | 44.5 | 45.4 | 20.9 |
| Queue Delay | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 |
| Total Delay | 54.7 | 11.9 | 1.6 | 57.2 | 81.7 | 0.2 | 56.5 | 47.9 | | 44.5 | 45.4 | 20.9 |
| LOS | D | B | A | E | F | A | E | D | | D | D | C |
| Approach Delay | | 25.4 | | | 78.1 | | | 53.5 | | | 24.9 | |
| Approach LOS | | C | | | E | | | D | | | C | |
| Queue Length 50th (m) | 52.2 | 29.0 | 0.0 | 2.1 | 163.3 | 0.0 | 4.3 | 3.8 | | 11.4 | 7.2 | 8.8 |
| Queue Length 95th (m) | 66.7 | 84.5 | 6.2 | 7.3 | #295.0 | 0.0 | 9.7 | 11.6 | | 22.8 | 14.4 | 41.8 |
| Internal Link Dist (m) | | 441.7 | | | 233.3 | | | 132.8 | | | 356.4 | |
| Turn Bay Length (m) | 127.0 | | 96.5 | 95.0 | | 90.0 | 90.0 | | | 140.0 | | 125.0 |
| Base Capacity (vph) | 605 | 2055 | 1031 | 74 | 1279 | 724 | 176 | 489 | | 259 | 568 | 762 |
| Starvation Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | 0 |
| Spillback Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | 0 |
| Storage Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | 0 |
| Reduced v/c Ratio | 0.75 | 0.36 | 0.13 | 0.12 | 1.07 | 0.08 | 0.21 | 0.04 | | 0.22 | 0.06 | 0.58 |

| Intersection Summary | |
|--|--|
| Cycle Length: 120 | |
| Actuated Cycle Length: 120 | |
| Offset: 101 (84%), Referenced to phase 2:EBT and 6:WBT, Start of Green | |
| Natural Cycle: 145 | |
| Control Type: Actuated-Coordinated | |

Lanes, Volumes, Timings
2: Citigate & Fallowfield & Strandherd

Existing AM Peak Hour
4497 O'Keefe Court


| Lane Group | Ø2 | Ø10 |
|------------------------|-------|------|
| Lane Configurations | | |
| Traffic Volume (vph) | | |
| Future Volume (vph) | | |
| Satd. Flow (prot) | | |
| Flt Permitted | | |
| Satd. Flow (perm) | | |
| Satd. Flow (RTOR) | | |
| Lane Group Flow (vph) | | |
| Turn Type | | |
| Protected Phases | 2 | 10 |
| Permitted Phases | | |
| Detector Phase | | |
| Switch Phase | | |
| Minimum Initial (s) | 10.0 | 10.0 |
| Minimum Split (s) | 29.9 | 12.0 |
| Total Split (s) | 31.0 | 15.0 |
| Total Split (%) | 26% | 13% |
| Yellow Time (s) | 4.6 | 2.0 |
| All-Red Time (s) | 2.3 | 0.0 |
| Lost Time Adjust (s) | | |
| Total Lost Time (s) | | |
| Lead/Lag | | Lag |
| Lead-Lag Optimize? | | Yes |
| Recall Mode | C-Max | None |
| Act Effct Green (s) | | |
| Actuated g/C Ratio | | |
| v/c Ratio | | |
| Control Delay | | |
| Queue Delay | | |
| Total Delay | | |
| LOS | | |
| Approach Delay | | |
| Approach LOS | | |
| Queue Length 50th (m) | | |
| Queue Length 95th (m) | | |
| Internal Link Dist (m) | | |
| Turn Bay Length (m) | | |
| Base Capacity (vph) | | |
| Starvation Cap Reductn | | |
| Spillback Cap Reductn | | |
| Storage Cap Reductn | | |
| Reduced v/c Ratio | | |
| Intersection Summary | | |

Lanes, Volumes, Timings
2: Citigate & Fallowfield & Strandherd

Existing AM Peak Hour
4497 O'Keefe Court

| | |
|---|------------------------|
| Maximum v/c Ratio: 1.07 | |
| Intersection Signal Delay: 48.3 | Intersection LOS: D |
| Intersection Capacity Utilization 83.6% | ICU Level of Service E |
| Analysis Period (min) 15 | |
| # 95th percentile volume exceeds capacity, queue may be longer. | |
| Queue shown is maximum after two cycles. | |

Splits and Phases: 2: Citigate & Fallowfield & Strandherd



HCM 2010 TWSC
3: Cobble Hill/O'Keefe & Fallowfield

Existing AM Peak Hour
4497 O'Keefe Court

| Intersection | | | | | | | | | | | | |
|--------------------------|-------|------|------|------|------|------|------|------|------|------|------|------|
| Int Delay, s/veh | 2.6 | | | | | | | | | | | |
| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
| Lane Configurations | ↰ | ↑ | ↱ | ↰ | ↑ | ↱ | | ↰ | ↑ | ↱ | ↰ | ↑ |
| Traffic Vol, veh/h | 18 | 543 | 11 | 15 | 439 | 7 | 30 | 2 | 52 | 6 | 3 | 16 |
| Future Vol, veh/h | 18 | 543 | 11 | 15 | 439 | 7 | 30 | 2 | 52 | 6 | 3 | 16 |
| Conflicting Peds, #/hr | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 1 | 0 | 0 |
| Sign Control | Free | Free | Free | Free | Free | Free | Stop | Stop | Stop | Stop | Stop | Stop |
| RT Channelized | - | - | None | - | - | None | - | - | None | - | - | None |
| Storage Length | 147.5 | - | 0 | - | - | 30.5 | - | - | - | 42.5 | - | - |
| Veh in Median Storage, # | - | 0 | - | - | 0 | - | - | 0 | - | - | 0 | - |
| Grade, % | - | 0 | - | - | 0 | - | - | 0 | - | - | 0 | - |
| Peak Hour Factor | 90 | 90 | 90 | 90 | 90 | 90 | 90 | 90 | 90 | 90 | 90 | 90 |
| Heavy Vehicles, % | 11 | 4 | 9 | 7 | 5 | 14 | 2 | 50 | 2 | 33 | 67 | 2 |
| Mvmt Flow | 20 | 603 | 12 | 17 | 488 | 8 | 33 | 2 | 58 | 7 | 3 | 18 |

| Major/Minor | Major1 | Major2 | Minor1 | Minor2 | | | | | | | | |
|----------------------|--------|--------|--------|--------|---|---|-------|------|-------|-------|-------|-------|
| Conflicting Flow All | 496 | 0 | 0 | 615 | 0 | 0 | 1180 | 1173 | 604 | 1202 | 1177 | 488 |
| Stage 1 | - | - | - | - | - | - | 643 | 643 | - | 522 | 522 | - |
| Stage 2 | - | - | - | - | - | - | 537 | 530 | - | 680 | 655 | - |
| Critical Hdwy | 4.21 | - | - | 4.17 | - | - | 7.12 | 7 | 6.22 | 7.43 | 7.17 | 6.22 |
| Critical Hdwy Stg 1 | - | - | - | - | - | - | 6.12 | 6 | - | 6.43 | 6.17 | - |
| Critical Hdwy Stg 2 | - | - | - | - | - | - | 6.12 | 6 | - | 6.43 | 6.17 | - |
| Follow-up Hdwy | 2.299 | - | - | 2.263 | - | - | 3.518 | 4.45 | 3.318 | 3.797 | 4.603 | 3.318 |
| Pot Cap-1 Maneuver | 1023 | - | - | 941 | - | - | 167 | 157 | 498 | 140 | 145 | 580 |
| Stage 1 | - | - | - | - | - | - | 462 | 402 | - | 485 | 438 | - |
| Stage 2 | - | - | - | - | - | - | 528 | 456 | - | 394 | 376 | - |
| Platoon blocked, % | - | - | - | - | - | - | - | - | - | - | - | - |
| Mov Cap-1 Maneuver | 1023 | - | - | 941 | - | - | 154 | 151 | 498 | 119 | 139 | 580 |
| Mov Cap-2 Maneuver | - | - | - | - | - | - | 154 | 151 | - | 119 | 139 | - |
| Stage 1 | - | - | - | - | - | - | 453 | 394 | - | 475 | 430 | - |
| Stage 2 | - | - | - | - | - | - | 499 | 448 | - | 339 | 368 | - |

| Approach | EB | WB | NB | SB |
|----------------------|-----|-----|------|------|
| HCM Control Delay, s | 0.3 | 0.3 | 25.3 | 20.2 |
| HCM LOS | | | D | C |

| Minor Lane/Major Mvmt | NBLn1 | EBL | EBT | EBR | WBL | WBT | WBR | SBLn1 | SBLn2 |
|-----------------------|-------|------|-----|-----|-------|-----|-----|-------|-------|
| Capacity (veh/h) | 269 | 1023 | - | - | 941 | - | - | 119 | 386 |
| HCM Lane V/C Ratio | 0.347 | 0.02 | - | - | 0.018 | - | - | 0.056 | 0.055 |
| HCM Control Delay (s) | 25.3 | 8.6 | - | - | 8.9 | - | - | 37 | 14.9 |
| HCM Lane LOS | D | A | - | - | A | - | - | E | B |
| HCM 95th %tile Q(veh) | 1.5 | 0.1 | - | - | 0.1 | - | - | 0.2 | 0.2 |

Lanes, Volumes, Timings
4: Cedarview & Fallowfield

Existing AM Peak Hour
4497 O'Keefe Court

| Lane Group | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|-------|--------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-----|
| Lane Configurations | ↰ | ↑ | ↱ | ↰ | ↑ | ↱ | ↰ | ↑ | ↱ | ↰ | ↑ | ↱ |
| Traffic Volume (vph) | 44 | 692 | 10 | 31 | 400 | 174 | 49 | 248 | 192 | 98 | 62 | 12 |
| Future Volume (vph) | 44 | 692 | 10 | 31 | 400 | 174 | 49 | 248 | 192 | 98 | 62 | 12 |
| Satd. Flow (prot) | 1658 | 1712 | 1261 | 1537 | 1728 | 1483 | 1658 | 1745 | 1469 | 1642 | 1651 | 0 |
| Fit Permitted | 0.467 | | | 0.248 | | | 0.704 | | | 0.431 | | |
| Satd. Flow (perm) | 815 | 1712 | 1234 | 401 | 1728 | 1483 | 1229 | 1745 | 1469 | 745 | 1651 | 0 |
| Satd. Flow (RTOR) | | | 49 | | | 193 | | | 134 | | | 12 |
| Lane Group Flow (vph) | 49 | 769 | 11 | 34 | 444 | 193 | 54 | 276 | 213 | 109 | 82 | 0 |
| Turn Type | Perm | NA | Perm | Perm | NA | Perm | Perm | NA | Perm | Perm | NA | |
| Protected Phases | 2 | | | 6 | | 6 | 4 | | 4 | 8 | | |
| Permitted Phases | 2 | 2 | 2 | 6 | 6 | 6 | 4 | 4 | 4 | 8 | 8 | |
| Detector Phase | 2 | 2 | 2 | 6 | 6 | 6 | 4 | 4 | 4 | 8 | 8 | |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | |
| Minimum Split (s) | 48.0 | 48.0 | 48.0 | 48.0 | 48.0 | 48.0 | 37.0 | 37.0 | 37.0 | 37.0 | 37.0 | |
| Total Split (s) | 48.0 | 48.0 | 48.0 | 48.0 | 48.0 | 48.0 | 37.0 | 37.0 | 37.0 | 37.0 | 37.0 | |
| Total Split (%) | 56.5% | 56.5% | 56.5% | 56.5% | 56.5% | 56.5% | 43.5% | 43.5% | 43.5% | 43.5% | 43.5% | |
| Yellow Time (s) | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | |
| All-Red Time (s) | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.8 | 3.8 | 3.8 | 3.8 | 3.8 | |
| Lost Time Adjust (s) | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | |
| Total Lost Time (s) | 6.7 | 6.7 | 6.7 | 6.7 | 6.7 | 6.7 | 6.8 | 6.8 | 6.8 | 6.8 | 6.8 | |
| Lead/Lag | | | | | | | | | | | | |
| Lead-Lag Optimize? | | | | | | | | | | | | |
| Recall Mode | C-Max | C-Max | C-Max | C-Max | C-Max | C-Max | None | None | None | None | None | |
| Act Effct Green (s) | 52.4 | 52.4 | 52.4 | 52.4 | 52.4 | 52.4 | 19.1 | 19.1 | 19.1 | 19.1 | 19.1 | |
| Actuated g/C Ratio | 0.62 | 0.62 | 0.62 | 0.62 | 0.62 | 0.62 | 0.22 | 0.22 | 0.22 | 0.22 | 0.22 | |
| v/c Ratio | 0.10 | 0.73 | 0.01 | 0.14 | 0.42 | 0.20 | 0.20 | 0.71 | 0.49 | 0.65 | 0.22 | |
| Control Delay | 9.0 | 18.4 | 0.0 | 10.6 | 11.0 | 2.0 | 26.2 | 39.7 | 14.4 | 47.2 | 22.6 | |
| Queue Delay | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | |
| Total Delay | 9.0 | 18.4 | 0.0 | 10.6 | 11.0 | 2.0 | 26.2 | 39.7 | 14.4 | 47.2 | 22.6 | |
| LOS | A | B | A | B | B | A | C | D | B | D | C | |
| Approach Delay | | 17.6 | | | 8.4 | | | 28.4 | | | 36.7 | |
| Approach LOS | | B | | | A | | | C | | | D | |
| Queue Length 50th (m) | 2.9 | 77.7 | 0.0 | 2.1 | 33.2 | 0.0 | 7.2 | 41.7 | 10.6 | 16.2 | 9.3 | |
| Queue Length 95th (m) | 9.3 | #172.1 | 0.0 | 7.8 | 65.9 | 8.9 | 14.8 | 59.6 | 26.4 | 30.3 | 18.3 | |
| Internal Link Dist (m) | | 561.2 | | | 452.7 | | | 444.3 | | | 482.1 | |
| Turn Bay Length (m) | 60.0 | | 55.0 | 60.0 | | 55.0 | 180.0 | | 80.0 | 45.5 | | |
| Base Capacity (vph) | 502 | 1055 | 779 | 247 | 1065 | 988 | 436 | 619 | 608 | 264 | 594 | |
| Starvation Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Spillback Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Storage Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Reduced v/c Ratio | 0.10 | 0.73 | 0.01 | 0.14 | 0.42 | 0.20 | 0.12 | 0.45 | 0.35 | 0.41 | 0.14 | |

| Intersection Summary | | | | | | | | | | | | |
|---|--|--|--|--|--|--|--|--|--|--|--|--|
| Cycle Length: 85 | | | | | | | | | | | | |
| Actuated Cycle Length: 85 | | | | | | | | | | | | |
| Offset: 40 (47%), Referenced to phase 2:EBTL and 6:WBTL, Start of Green | | | | | | | | | | | | |
| Natural Cycle: 85 | | | | | | | | | | | | |
| Control Type: Actuated-Coordinated | | | | | | | | | | | | |

Lanes, Volumes, Timings
4: Cedarview & Fallowfield

Existing AM Peak Hour
4497 O'Keefe Court

Maximum v/c Ratio: 0.73

Intersection Signal Delay: 19.1

Intersection LOS: B

Intersection Capacity Utilization 77.6%


ICU Level of Service D

Analysis Period (min) 15

95th percentile volume exceeds capacity, queue may be longer.

Queue shown is maximum after two cycles.

Splits and Phases: 4: Cedarview & Fallowfield



HCM 2010 TWSC
1: Cedarview & Onassa

Existing PM Peak Hour
4497 O'Keefe Court

Intersection

Int Delay, s/veh 0.6

| Movement | EBL | EBR | NBL | NBT | SBT | SBR |
|--------------------------|------|------|------|------|------|------|
| Lane Configurations | W | | | W | W | |
| Traffic Vol, veh/h | 13 | 15 | 4 | 244 | 496 | 8 |
| Future Vol, veh/h | 13 | 15 | 4 | 244 | 496 | 8 |
| Conflicting Peds, #/hr | 0 | 0 | 0 | 0 | 0 | 0 |
| Sign Control | Stop | Stop | Free | Free | Free | Free |
| RT Channelized | - | None | - | None | - | None |
| Storage Length | 0 | - | - | - | - | - |
| Veh in Median Storage, # | 0 | - | - | 0 | 0 | - |
| Grade, % | 0 | - | - | 0 | 0 | - |
| Peak Hour Factor | 90 | 90 | 90 | 90 | 90 | 90 |
| Heavy Vehicles, % | 8 | 7 | 2 | 2 | 2 | 2 |
| Mvmt Flow | 14 | 17 | 4 | 271 | 551 | 9 |

| Major/Minor | Minor2 | Major1 | Major2 |
|----------------------|--------|--------|--------|
| Conflicting Flow All | 835 | 556 | 560 |
| Stage 1 | 556 | - | - |
| Stage 2 | 279 | - | - |
| Critical Hdwy | 6.48 | 6.27 | 4.12 |
| Critical Hdwy Stg 1 | 5.48 | - | - |
| Critical Hdwy Stg 2 | 5.48 | - | - |
| Follow-up Hdwy | 3.572 | 3.363 | 2.218 |
| Pot Cap-1 Maneuver | 330 | 521 | 1011 |
| Stage 1 | 563 | - | - |
| Stage 2 | 755 | - | - |
| Platoon blocked, % | - | - | - |
| Mov Cap-1 Maneuver | 328 | 521 | 1011 |
| Mov Cap-2 Maneuver | 328 | - | - |
| Stage 1 | 560 | - | - |
| Stage 2 | 755 | - | - |

| Approach | EB | NB | SB |
|----------------------|------|-----|----|
| HCM Control Delay, s | 14.5 | 0.1 | 0 |
| HCM LOS | B | | |

| Minor Lane/Major Mvmt | NBL | NBT EBLn1 | SBT | SBR |
|-----------------------|-------|-----------|-------|-----|
| Capacity (veh/h) | 1011 | - | 409 | - |
| HCM Lane V/C Ratio | 0.004 | - | 0.076 | - |
| HCM Control Delay (s) | 8.6 | 0 | 14.5 | - |
| HCM Lane LOS | A | A | B | - |
| HCM 95th %tile Q(veh) | 0 | - | 0.2 | - |

Lanes, Volumes, Timings
2: Citigate & Fallowfield & Strandherd

Existing PM Peak Hour
4497 O'Keefe Court

| Lane Group | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|-------|--------|-------|-------|--------|-------|-------|-------|------|-------|-------|-------|
| Lane Configurations | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ |
| Traffic Volume (vph) | 364 | 1170 | 167 | 4 | 988 | 102 | 261 | 88 | 14 | 108 | 71 | 433 |
| Future Volume (vph) | 364 | 1170 | 167 | 4 | 988 | 102 | 261 | 88 | 14 | 108 | 71 | 433 |
| Satd. Flow (prot) | 3216 | 3316 | 1469 | 1127 | 3316 | 1483 | 3154 | 1667 | 0 | 1658 | 1664 | 1455 |
| Flt Permitted | 0.950 | | | 0.950 | | | 0.950 | | | 0.950 | | |
| Satd. Flow (perm) | 3216 | 3316 | 1432 | 1126 | 3316 | 1483 | 3154 | 1667 | 0 | 1658 | 1664 | 1455 |
| Satd. Flow (RTOR) | | | 160 | | | 160 | | 7 | | | | 359 |
| Lane Group Flow (vph) | 404 | 1300 | 186 | 4 | 1098 | 113 | 290 | 114 | 0 | 120 | 79 | 481 |
| Turn Type | Prot | NA | Perm | Prot | NA | Perm | Prot | NA | Prot | NA | Perm | |
| Protected Phases | 13 | 2 | | 9 | 6 | | 7 | 4 | | 3 | 8 | |
| Permitted Phases | | | 2 | | | 6 | | | | | | 8 |
| Detector Phase | 13 | 2 | 2 | 9 | 6 | 6 | 7 | 4 | | 3 | 8 | 8 |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 5.0 | 10.0 | 10.0 | 5.0 | 10.0 | 10.0 | 5.0 | 10.0 | | 5.0 | 10.0 | 10.0 |
| Minimum Split (s) | 12.1 | 29.9 | 29.9 | 12.1 | 29.9 | 29.9 | 11.5 | 48.0 | | 11.5 | 48.0 | 48.0 |
| Total Split (s) | 24.0 | 34.0 | 34.0 | 24.0 | 34.0 | 34.0 | 14.0 | 48.0 | | 14.0 | 48.0 | 48.0 |
| Total Split (%) | 20.0% | 28.3% | 28.3% | 20.0% | 28.3% | 28.3% | 11.7% | 40.0% | | 11.7% | 40.0% | 40.0% |
| Yellow Time (s) | 4.6 | 4.6 | 4.6 | 4.6 | 4.6 | 4.6 | 3.7 | 3.7 | | 3.7 | 3.7 | 3.7 |
| All-Red Time (s) | 2.5 | 2.3 | 2.3 | 2.5 | 2.3 | 2.3 | 2.8 | 3.3 | | 2.8 | 3.3 | 3.3 |
| Lost Time Adjust (s) | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 |
| Total Lost Time (s) | 7.1 | 6.9 | 6.9 | 7.1 | 6.9 | 6.9 | 6.5 | 7.0 | | 6.5 | 7.0 | 7.0 |
| Lead/Lag | | | | | | | Lag | Lead | | Lag | Lead | Lead |
| Lead-Lag Optimize? | | | | | | | Yes | Yes | | Yes | Yes | Yes |
| Recall Mode | None | C-Max | C-Max | None | C-Max | C-Max | None | None | | None | None | None |
| Act Effct Green (s) | 18.7 | 55.0 | 55.0 | 6.1 | 32.1 | 32.1 | 21.2 | 13.6 | | 28.2 | 20.6 | 20.6 |
| Actuated g/C Ratio | 0.16 | 0.46 | 0.46 | 0.05 | 0.27 | 0.27 | 0.18 | 0.11 | | 0.24 | 0.17 | 0.17 |
| v/c Ratio | 0.81 | 0.86 | 0.25 | 0.07 | 1.24 | 0.22 | 0.52 | 0.58 | | 0.31 | 0.28 | 0.88 |
| Control Delay | 62.4 | 36.9 | 6.8 | 56.2 | 155.3 | 2.8 | 50.3 | 59.0 | | 40.3 | 42.2 | 29.8 |
| Queue Delay | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 |
| Total Delay | 62.4 | 36.9 | 6.8 | 56.2 | 155.3 | 2.8 | 50.3 | 59.0 | | 40.3 | 42.2 | 29.8 |
| LOS | E | D | A | E | F | A | D | E | | D | D | C |
| Approach Delay | | 39.4 | | | 140.7 | | | 52.8 | | | 33.1 | |
| Approach LOS | | D | | | F | | | D | | | C | |
| Queue Length 50th (m) | 46.5 | 127.7 | 3.0 | 0.9 | ~169.8 | 0.0 | 32.4 | 24.4 | | 24.0 | 16.7 | 29.9 |
| Queue Length 95th (m) | #75.9 | #246.5 | 21.4 | 4.6 | #227.6 | 5.3 | #60.3 | 41.2 | | 39.7 | 25.7 | 63.4 |
| Internal Link Dist (m) | | 441.7 | | | 233.3 | | | 132.8 | | | 356.4 | |
| Turn Bay Length (m) | 127.0 | | 96.5 | 95.0 | | 90.0 | 90.0 | | | 140.0 | | 125.0 |
| Base Capacity (vph) | 503 | 1519 | 743 | 158 | 886 | 513 | 556 | 574 | | 389 | 568 | 733 |
| Starvation Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | 0 |
| Spillback Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | 0 |
| Storage Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | 0 |
| Reduced v/c Ratio | 0.80 | 0.86 | 0.25 | 0.03 | 1.24 | 0.22 | 0.52 | 0.20 | | 0.31 | 0.14 | 0.66 |

Intersection Summary

Cycle Length: 120

Actuated Cycle Length: 120

Offset: 0 (0%), Referenced to phase 2:EBT and 6:WBT, Start of Green

Natural Cycle: 145

Control Type: Actuated-Coordinated

08/17/2023
MC


CGH Transportation
Page 3

Lanes, Volumes, Timings
2: Citigate & Fallowfield & Strandherd

Existing PM Peak Hour
4497 O'Keefe Court

| | |
|---|------------------------|
| Maximum v/c Ratio: 1.24 | |
| Intersection Signal Delay: 69.0 | Intersection LOS: E |
| Intersection Capacity Utilization 82.0% | ICU Level of Service D |
| Analysis Period (min) 15 | |
| ~ Volume exceeds capacity, queue is theoretically infinite. | |
| Queue shown is maximum after two cycles. | |
| # 95th percentile volume exceeds capacity, queue may be longer. | |
| Queue shown is maximum after two cycles. | |

Splits and Phases: 2: Citigate & Fallowfield & Strandherd



08/17/2023
MC

CGH Transportation
Page 4

HCM 2010 TWSC
3: Cobble Hill/O'Keefe & Fallowfield

Existing PM Peak Hour
4497 O'Keefe Court

| Intersection | | | | | | | | | | | | |
|--------------------------|-------|------|------|------|------|------|------|------|------|------|------|------|
| Int Delay, s/veh | 2.7 | | | | | | | | | | | |
| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
| Lane Configurations | ↰ | ↑ | ↱ | ↰ | ↑ | ↱ | | ↰ | ↑ | ↱ | ↰ | ↑ |
| Traffic Vol, veh/h | 19 | 499 | 66 | 52 | 611 | 17 | 21 | 3 | 44 | 7 | 3 | 16 |
| Future Vol, veh/h | 19 | 499 | 66 | 52 | 611 | 17 | 21 | 3 | 44 | 7 | 3 | 16 |
| Conflicting Peds, #/hr | 0 | 0 | 1 | 1 | 0 | 0 | 0 | 0 | 2 | 2 | 0 | 0 |
| Sign Control | Free | Free | Free | Free | Free | Free | Stop | Stop | Stop | Stop | Stop | Stop |
| RT Channelized | - | - | None | - | - | None | - | - | None | - | - | None |
| Storage Length | 147.5 | - | 0 | - | - | 30.5 | - | - | - | 42.5 | - | - |
| Veh in Median Storage, # | - | 0 | - | - | 0 | - | - | 0 | - | - | 0 | - |
| Grade, % | - | 0 | - | - | 0 | - | - | 0 | - | - | 0 | - |
| Peak Hour Factor | 90 | 90 | 90 | 90 | 90 | 90 | 90 | 90 | 90 | 90 | 90 | 90 |
| Heavy Vehicles, % | 11 | 3 | 2 | 2 | 5 | 2 | 24 | 2 | 2 | 2 | 2 | 13 |
| Mvmt Flow | 21 | 554 | 73 | 58 | 679 | 19 | 23 | 3 | 49 | 8 | 3 | 18 |

| Major/Minor | Major1 | Major2 | Minor1 | Minor2 | | | | | | | | |
|----------------------|--------|--------|--------|--------|---|---|-------|-------|-------|-------|-------|-------|
| Conflicting Flow All | 698 | 0 | 0 | 628 | 0 | 0 | 1412 | 1411 | 557 | 1456 | 1465 | 679 |
| Stage 1 | - | - | - | - | - | - | 597 | 597 | - | 795 | 795 | - |
| Stage 2 | - | - | - | - | - | - | 815 | 814 | - | 661 | 670 | - |
| Critical Hdwy | 4.21 | - | - | 4.12 | - | - | 7.34 | 6.52 | 6.22 | 7.12 | 6.52 | 6.33 |
| Critical Hdwy Stg 1 | - | - | - | - | - | - | 6.34 | 5.52 | - | 6.12 | 5.52 | - |
| Critical Hdwy Stg 2 | - | - | - | - | - | - | 6.34 | 5.52 | - | 6.12 | 5.52 | - |
| Follow-up Hdwy | 2.299 | - | - | 2.218 | - | - | 3.716 | 4.018 | 3.318 | 3.518 | 4.018 | 3.417 |
| Pot Cap-1 Maneuver | 858 | - | - | 954 | - | - | 103 | 138 | 530 | 108 | 128 | 433 |
| Stage 1 | - | - | - | - | - | - | 454 | 491 | - | 381 | 399 | - |
| Stage 2 | - | - | - | - | - | - | 341 | 391 | - | 452 | 455 | - |
| Platoon blocked, % | - | - | - | - | - | - | - | - | - | - | - | - |
| Mov Cap-1 Maneuver | 858 | - | - | 953 | - | - | 90 | 126 | 529 | 90 | 117 | 433 |
| Mov Cap-2 Maneuver | - | - | - | - | - | - | 90 | 126 | - | 90 | 117 | - |
| Stage 1 | - | - | - | - | - | - | 443 | 479 | - | 372 | 375 | - |
| Stage 2 | - | - | - | - | - | - | 304 | 367 | - | 397 | 444 | - |

| Approach | EB | WB | NB | SB |
|----------------------|-----|-----|------|------|
| HCM Control Delay, s | 0.3 | 0.7 | 33.5 | 26.1 |
| HCM LOS | | | D | D |

| Minor Lane/Major Mvmt | NBLn1 | EBL | EBT | EBR | WBL | WBT | WBR | SBLn1 | SBLn2 |
|-----------------------|-------|-------|-----|-----|-------|-----|-----|-------|-------|
| Capacity (veh/h) | 200 | 858 | - | - | 953 | - | - | 90 | 304 |
| HCM Lane V/C Ratio | 0.378 | 0.025 | - | - | 0.061 | - | - | 0.086 | 0.069 |
| HCM Control Delay (s) | 33.5 | 9.3 | - | - | 9 | - | - | 48.8 | 17.7 |
| HCM Lane LOS | D | A | - | - | A | - | - | E | C |
| HCM 95th %tile Q(veh) | 1.6 | 0.1 | - | - | 0.2 | - | - | 0.3 | 0.2 |

Lanes, Volumes, Timings
4: Cedarview & Fallowfield

Existing PM Peak Hour
4497 O'Keefe Court

| Lane Group | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|-------|-------|-------|-------|--------|-------|-------|-------|-------|-------|--------|-----|
| Lane Configurations | ↰ | ↑ | ↱ | ↰ | ↑ | ↱ | ↰ | ↑ | ↱ | ↰ | ↑ | ↱ |
| Traffic Volume (vph) | 24 | 398 | 30 | 137 | 652 | 77 | 21 | 89 | 63 | 247 | 412 | 46 |
| Future Volume (vph) | 24 | 398 | 30 | 137 | 652 | 77 | 21 | 89 | 63 | 247 | 412 | 46 |
| Satd. Flow (prot) | 1658 | 1745 | 1483 | 1642 | 1728 | 1483 | 1537 | 1728 | 1469 | 1658 | 1717 | 0 |
| Fit Permitted | 0.200 | | | 0.427 | | | 0.210 | | | 0.693 | | |
| Satd. Flow (perm) | 349 | 1745 | 1483 | 738 | 1728 | 1451 | 340 | 1728 | 1469 | 1209 | 1717 | 0 |
| Satd. Flow (RTOR) | | | 49 | | | 81 | | | 70 | | | 7 |
| Lane Group Flow (vph) | 27 | 442 | 33 | 152 | 724 | 86 | 23 | 99 | 70 | 274 | 509 | 0 |
| Turn Type | Perm | NA | Perm | Perm | NA | Perm | Perm | NA | Perm | Perm | NA | |
| Protected Phases | 2 | 2 | 2 | 6 | 6 | 6 | 4 | 4 | 4 | 8 | 8 | |
| Permitted Phases | 2 | | | 6 | | 6 | 4 | | 4 | 8 | | |
| Detector Phase | 2 | 2 | 2 | 6 | 6 | 6 | 4 | 4 | 4 | 8 | 8 | |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | |
| Minimum Split (s) | 48.0 | 48.0 | 48.0 | 48.0 | 48.0 | 48.0 | 37.0 | 37.0 | 37.0 | 37.0 | 37.0 | |
| Total Split (s) | 48.0 | 48.0 | 48.0 | 48.0 | 48.0 | 48.0 | 37.0 | 37.0 | 37.0 | 37.0 | 37.0 | |
| Total Split (%) | 56.5% | 56.5% | 56.5% | 56.5% | 56.5% | 56.5% | 43.5% | 43.5% | 43.5% | 43.5% | 43.5% | |
| Yellow Time (s) | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | |
| All-Red Time (s) | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.8 | 3.8 | 3.8 | 3.8 | 3.8 | |
| Lost Time Adjust (s) | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | |
| Total Lost Time (s) | 6.7 | 6.7 | 6.7 | 6.7 | 6.7 | 6.7 | 6.8 | 6.8 | 6.8 | 6.8 | 6.8 | |
| Lead/Lag | | | | | | | | | | | | |
| Lead-Lag Optimize? | | | | | | | | | | | | |
| Recall Mode | C-Max | C-Max | C-Max | C-Max | C-Max | C-Max | None | None | None | None | None | |
| Act Effct Green (s) | 43.5 | 43.5 | 43.5 | 43.5 | 43.5 | 43.5 | 28.0 | 28.0 | 28.0 | 28.0 | 28.0 | |
| Actuated g/C Ratio | 0.51 | 0.51 | 0.51 | 0.51 | 0.51 | 0.51 | 0.33 | 0.33 | 0.33 | 0.33 | 0.33 | |
| v/c Ratio | 0.15 | 0.49 | 0.04 | 0.40 | 0.82 | 0.11 | 0.21 | 0.17 | 0.13 | 0.69 | 0.89 | |
| Control Delay | 14.9 | 16.6 | 2.4 | 17.8 | 28.0 | 3.7 | 24.8 | 20.2 | 5.7 | 34.3 | 46.5 | |
| Queue Delay | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | |
| Total Delay | 14.9 | 16.6 | 2.4 | 17.8 | 28.0 | 3.7 | 24.8 | 20.2 | 5.7 | 34.3 | 46.5 | |
| LOS | B | B | A | B | C | A | C | C | A | C | D | |
| Approach Delay | 15.6 | | | | 24.2 | | 15.5 | | | 42.2 | | |
| Approach LOS | B | | | | C | | B | | | D | | |
| Queue Length 50th (m) | 2.3 | 47.2 | 0.0 | 15.3 | 99.3 | 0.4 | 2.6 | 10.8 | 0.0 | 36.5 | 73.4 | |
| Queue Length 95th (m) | 7.6 | 72.8 | 2.9 | 31.3 | #168.1 | 7.3 | 8.6 | 21.3 | 8.0 | 63.0 | #125.9 | |
| Internal Link Dist (m) | | 561.2 | | | 452.7 | | | 444.3 | | | 482.1 | |
| Turn Bay Length (m) | 60.0 | | 55.0 | 60.0 | | 55.0 | 180.0 | | 80.0 | 45.5 | | |
| Base Capacity (vph) | 178 | 893 | 783 | 377 | 885 | 782 | 120 | 613 | 567 | 429 | 614 | |
| Starvation Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Spillback Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Storage Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Reduced v/c Ratio | 0.15 | 0.49 | 0.04 | 0.40 | 0.82 | 0.11 | 0.19 | 0.16 | 0.12 | 0.64 | 0.83 | |

| Intersection Summary | | | | | | | | | | | | |
|---|--|--|--|--|--|--|--|--|--|--|--|--|
| Cycle Length: 85 | | | | | | | | | | | | |
| Actuated Cycle Length: 85 | | | | | | | | | | | | |
| Offset: 40 (47%), Referenced to phase 2:EBTL and 6:WBTL, Start of Green | | | | | | | | | | | | |
| Natural Cycle: 85 | | | | | | | | | | | | |
| Control Type: Actuated-Coordinated | | | | | | | | | | | | |

| | |
|---|------------------------|
| Maximum v/c Ratio: 0.89 | |
| Intersection Signal Delay: 27.5 | Intersection LOS: C |
| Intersection Capacity Utilization 87.2% | ICU Level of Service E |
| Analysis Period (min) 15 | |
| # 95th percentile volume exceeds capacity, queue may be longer. | |
| Queue shown is maximum after two cycles. | |



Appendix D

Signal Warrant

O'Keefe @ Fallowfield
Existing

Justification #7

| Justification | Description | Minimum Requirement | | Minimum Requirement | | Compliance | | Signal | |
|-----------------------------|---|---------------------|-------------|---------------------|-------------|------------|-----|--------|----|
| | | 1 Lane Highway | | 2 or More Lanes | | Sectional | | | |
| | | Free Flow | Restr. Flow | Free Flow | Restr. Flow | Numerical | % | | |
| 1. Minimum Vehicular Volume | A. Vehicle volume, all approaches (average hour) | 480 | 720 | 600 | 900 | 625 | 87% | 30% | No |
| | B. Vehicle volume, along minor streets (average hour) | 120 | 170 | 120 | 170 | 51 | 30% | | |
| 2. Delay to Cross Traffic | A. Vehicle volumes, major street (average hour) | 480 | 720 | 600 | 900 | 574 | 80% | 23% | No |
| | B. Combined vehicle and pedestrian volume crossing artery from minor streets (average hour) | 50 | 75 | 50 | 75 | 18 | 23% | | |

Notes

1. Refer to OTM Book 12, pg 92, Mar 2012
2. Lowest section percentage governs justification
3. Average hourly volumes estimated from peak hour volumes, $AHV = PM/2$ or $(AM + PM) / 4$, including amplification factors
4. T-intersection factor corrected, applies only to 1B

O'Keefe @ Fallowfield
FB2038

Justification #7

| Justification | Description | Minimum Requirement | | Minimum Requirement | | Compliance | | | Signal |
|-----------------------------|---|---------------------|-------------|---------------------|-------------|------------|------|----------|--------|
| | | 1 Lane Highway | | 2 or More Lanes | | Sectional | | Entire % | |
| | | Free Flow | Restr. Flow | Free Flow | Restr. Flow | Numerical | % | | |
| 1. Minimum Vehicular Volume | A. Vehicle volume, all approaches (average hour) | 480 | 720 | 600 | 900 | 780 | 108% | 42% | No |
| | B. Vehicle volume, along minor streets (average hour) | 120 | 170 | 120 | 170 | 71 | 42% | | |
| 2. Delay to Cross Traffic | A. Vehicle volumes, major street (average hour) | 480 | 720 | 600 | 900 | 709 | 98% | 49% | No |
| | B. Combined vehicle and pedestrian volume crossing artery from minor streets (average hour) | 50 | 75 | 50 | 75 | 37 | 49% | | |

Notes

1. Refer to OTM Book 12, pg 92, Mar 2012
2. Lowest section percentage governs justification
3. Average hourly volumes estimated from peak hour volumes, $AHV = PM/2$ or $(AM + PM) / 4$, including amplification factors
4. T-intersection factor corrected, applies only to 1B

O'Keefe @ Fallowfield
FT2038

Justification #7

| Justification | Description | Minimum Requirement | | Minimum Requirement | | Compliance | | | Signal |
|-----------------------------|---|---------------------|-------------|---------------------|-------------|------------|------|----------|--------|
| | | 1 Lane Highway | | 2 or More Lanes | | Sectional | | Entire % | |
| | | Free Flow | Restr. Flow | Free Flow | Restr. Flow | Numerical | % | | |
| 1. Minimum Vehicular Volume | A. Vehicle volume, all approaches (average hour) | 480 | 720 | 600 | 900 | 945 | 131% | 80% | No |
| | B. Vehicle volume, along minor streets (average hour) | 120 | 170 | 120 | 170 | 136 | 80% | | |
| 2. Delay to Cross Traffic | A. Vehicle volumes, major street (average hour) | 480 | 720 | 600 | 900 | 809 | 112% | 96% | No |
| | B. Combined vehicle and pedestrian volume crossing artery from minor streets (average hour) | 50 | 75 | 50 | 75 | 72 | 96% | | |

Notes

1. Refer to OTM Book 12, pg 92, Mar 2012
2. Lowest section percentage governs justification
3. Average hourly volumes estimated from peak hour volumes, $AHV = PM/2$ or $(AM + PM) / 4$, including amplification factors
4. T-intersection factor corrected, applies only to 1B

Appendix E

Collision Data

| Accident Date | Accident Year | Accident Time | Location | Environment Condition | Light | Traffic Control | Traffic Control Condition | Classification Of Accident | Initial Impact Type | Road Surface Condition | # Vehicles | # Motorcycles | # Bicycles | # Pedestrians |
|---------------|---------------|---------------|---|-----------------------|---------------|---------------------|---------------------------|----------------------------|-----------------------|------------------------|------------|---------------|------------|---------------|
| 7/31/2020 | 2020 | 3:34 | FALLOWFIELD RD @ O'KEEFE CRT (0010311) | 01 - Clear | 07 - Dark | 02 - Stop sign | 0 | 02 - Non-fatal injury | 07 - SMV other | 01 - Dry | 0 | 0 | 0 | 0 |
| 12/24/2021 | 2021 | 9:39 | FALLOWFIELD RD @ O'KEEFE CRT (0010311) | 01 - Clear | 01 - Daylight | 02 - Stop sign | 0 | 03 - P.D. only | 07 - SMV other | 02 - Dry | 0 | 0 | 0 | 0 |
| 2/17/2022 | 2022 | 22:08 | FALLOWFIELD RD @ O'KEEFE CRT (0010311) | 03 - Snow | 07 - Dark | 02 - Stop sign | 0 | 03 - P.D. only | 07 - SMV other | 05 - Packed snow | 0 | 0 | 0 | 0 |
| 8/4/2019 | 2019 | 0:18 | O'KEEFE CRT btwn END & FOXTAIL AVE (_32A114) | 01 - Clear | 07 - Dark | 10 - No control | 0 | 03 - P.D. only | 07 - SMV other | 01 - Dry | 0 | 0 | 0 | 0 |
| 6/18/2019 | 2019 | 21:30 | FALLOWFIELD RD btwn CEDARVIEW RD & O'KEEFE CRT (_32A4Y8) | 01 - Clear | 07 - Dark | 10 - No control | 0 | 03 - P.D. only | 07 - SMV other | 01 - Dry | 0 | 0 | 0 | 0 |
| 11/17/2020 | 2020 | 3:15 | FALLOWFIELD RD btwn CEDARVIEW RD & O'KEEFE CRT (_32A4Y8) | 01 - Clear | 07 - Dark | 10 - No control | 0 | 02 - Non-fatal injury | 07 - SMV other | 01 - Dry | 0 | 0 | 0 | 0 |
| 1/8/2018 | 2018 | 12:55 | FALLOWFIELD RD @ STRANDHERO DR (0005238) | 03 - Snow | 01 - Daylight | 01 - Traffic signal | 0 | 02 - Non-fatal injury | 03 - Rear end | 04 - Slush | 0 | 0 | 0 | 0 |
| 2/16/2018 | 2018 | 15:35 | FALLOWFIELD RD @ STRANDHERO DR (0005238) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 0 | 03 - P.D. only | 03 - Rear end | 01 - Dry | 0 | 0 | 0 | 0 |
| 2/8/2018 | 2018 | 15:46 | FALLOWFIELD RD @ STRANDHERO DR (0005238) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 0 | 03 - P.D. only | 02 - Angle | 01 - Dry | 0 | 0 | 0 | 0 |
| 2/8/2018 | 2018 | 17:45 | FALLOWFIELD RD @ STRANDHERO DR (0005238) | 01 - Clear | 07 - Dark | 01 - Traffic signal | 0 | 03 - P.D. only | 03 - Rear end | 02 - Wet | 0 | 0 | 0 | 0 |
| 3/9/2018 | 2018 | 10:55 | FALLOWFIELD RD @ STRANDHERO DR (0005238) | 03 - Snow | 01 - Daylight | 01 - Traffic signal | 0 | 02 - Non-fatal injury | 02 - Angle | 02 - Wet | 0 | 0 | 0 | 0 |
| 4/26/2018 | 2018 | 16:11 | FALLOWFIELD RD @ STRANDHERO DR (0005238) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 0 | 03 - P.D. only | 03 - Rear end | 01 - Dry | 0 | 0 | 0 | 0 |
| 6/19/2018 | 2018 | 21:05 | FALLOWFIELD RD @ STRANDHERO DR (0005238) | 01 - Clear | 05 - Dusk | 01 - Traffic signal | 0 | 02 - Non-fatal injury | 02 - Angle | 01 - Dry | 0 | 1 | 0 | 0 |
| 6/24/2018 | 2018 | 14:01 | FALLOWFIELD RD @ STRANDHERO DR (0005238) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 0 | 03 - P.D. only | 03 - Rear end | 01 - Dry | 0 | 0 | 0 | 0 |
| 8/16/2018 | 2018 | 12:28 | FALLOWFIELD RD @ STRANDHERO DR (0005238) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 0 | 03 - P.D. only | 03 - Rear end | 01 - Dry | 0 | 0 | 0 | 0 |
| 9/10/2018 | 2018 | 7:45 | FALLOWFIELD RD @ STRANDHERO DR (0005238) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 0 | 03 - P.D. only | 04 - Sideswipe | 01 - Dry | 0 | 0 | 0 | 0 |
| 9/17/2018 | 2018 | 14:10 | FALLOWFIELD RD @ STRANDHERO DR (0005238) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 0 | 03 - P.D. only | 03 - Rear end | 01 - Dry | 0 | 0 | 0 | 0 |
| 10/24/2018 | 2018 | 8:45 | FALLOWFIELD RD @ STRANDHERO DR (0005238) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 0 | 02 - Non-fatal injury | 03 - Rear end | 01 - Dry | 0 | 0 | 0 | 0 |
| 12/22/2018 | 2018 | 8:04 | FALLOWFIELD RD @ STRANDHERO DR (0005238) | 03 - Snow | 01 - Daylight | 01 - Traffic signal | 0 | 03 - P.D. only | 05 - Turning movement | 03 - Loose snow | 0 | 0 | 0 | 0 |
| 1/1/2019 | 2019 | 19:29 | FALLOWFIELD RD @ STRANDHERO DR (0005238) | 01 - Clear | 07 - Dark | 01 - Traffic signal | 0 | 03 - P.D. only | 04 - Sideswipe | 01 - Dry | 0 | 0 | 0 | 0 |
| 1/31/2019 | 2019 | 16:32 | FALLOWFIELD RD @ STRANDHERO DR (0005238) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 0 | 03 - P.D. only | 03 - Rear end | 05 - Packed snow | 0 | 0 | 0 | 0 |
| 1/29/2019 | 2019 | 8:35 | FALLOWFIELD RD @ STRANDHERO DR (0005238) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 0 | 03 - P.D. only | 03 - Rear end | 03 - Loose snow | 0 | 0 | 0 | 0 |
| 2/25/2019 | 2019 | 21:05 | FALLOWFIELD RD @ STRANDHERO DR (0005238) | 01 - Clear | 07 - Dark | 01 - Traffic signal | 0 | 03 - P.D. only | 05 - Turning movement | 01 - Dry | 0 | 0 | 0 | 0 |
| 3/5/2019 | 2019 | 16:30 | FALLOWFIELD RD @ STRANDHERO DR (0005238) | 03 - Snow | 01 - Daylight | 01 - Traffic signal | 0 | 03 - P.D. only | 03 - Rear end | 03 - Loose snow | 0 | 0 | 0 | 0 |
| 5/4/2019 | 2019 | 10:30 | FALLOWFIELD RD @ STRANDHERO DR (0005238) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 0 | 03 - P.D. only | 03 - Rear end | 01 - Dry | 0 | 0 | 0 | 0 |
| 4/24/2019 | 2019 | 18:20 | FALLOWFIELD RD @ STRANDHERO DR (0005238) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 0 | 03 - P.D. only | 03 - Rear end | 01 - Dry | 0 | 0 | 0 | 0 |
| 7/30/2019 | 2019 | 8:03 | FALLOWFIELD RD @ STRANDHERO DR (0005238) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 0 | 03 - P.D. only | 04 - Sideswipe | 01 - Dry | 0 | 0 | 0 | 0 |
| 9/14/2019 | 2019 | 15:00 | FALLOWFIELD RD @ STRANDHERO DR (0005238) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 0 | 03 - P.D. only | 03 - Rear end | 01 - Dry | 0 | 0 | 0 | 0 |
| 9/16/2019 | 2019 | 8:35 | FALLOWFIELD RD @ STRANDHERO DR (0005238) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 0 | 03 - P.D. only | 03 - Rear end | 01 - Dry | 0 | 0 | 0 | 0 |
| 11/16/2019 | 2019 | 13:41 | FALLOWFIELD RD @ STRANDHERO DR (0005238) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 0 | 03 - P.D. only | 03 - Rear end | 01 - Dry | 0 | 0 | 0 | 0 |
| 1/31/2020 | 2020 | 11:01 | FALLOWFIELD RD @ STRANDHERO DR (0005238) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 0 | 02 - Non-fatal injury | 02 - Angle | 01 - Dry | 0 | 0 | 0 | 0 |
| 3/8/2020 | 2020 | 10:29 | FALLOWFIELD RD @ STRANDHERO DR (0005238) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 0 | 03 - P.D. only | 03 - Rear end | 01 - Dry | 0 | 0 | 0 | 0 |
| 2/20/2020 | 2020 | 7:15 | FALLOWFIELD RD @ STRANDHERO DR (0005238) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 0 | 03 - P.D. only | 03 - Rear end | 01 - Dry | 0 | 0 | 0 | 0 |
| 6/5/2020 | 2020 | 15:10 | FALLOWFIELD RD @ STRANDHERO DR (0005238) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 0 | 03 - P.D. only | 03 - Rear end | 01 - Dry | 0 | 0 | 0 | 0 |
| 7/27/2020 | 2020 | 16:27 | FALLOWFIELD RD @ STRANDHERO DR (0005238) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 0 | 03 - P.D. only | 03 - Rear end | 01 - Dry | 0 | 0 | 0 | 0 |
| 10/1/2020 | 2020 | 11:26 | FALLOWFIELD RD @ STRANDHERO DR (0005238) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 0 | 03 - P.D. only | 03 - Rear end | 01 - Dry | 0 | 0 | 0 | 0 |
| 1/19/2021 | 2021 | 6:46 | FALLOWFIELD RD @ STRANDHERO DR (0005238) | 01 - Clear | 07 - Dark | 01 - Traffic signal | 0 | 03 - P.D. only | 03 - Rear end | 01 - Dry | 0 | 0 | 0 | 0 |
| 12/28/2020 | 2020 | 18:51 | FALLOWFIELD RD @ STRANDHERO DR (0005238) | 01 - Clear | 07 - Dark | 01 - Traffic signal | 0 | 03 - P.D. only | 04 - Sideswipe | 02 - Wet | 0 | 0 | 0 | 0 |
| 2/27/2021 | 2021 | 14:21 | FALLOWFIELD RD @ STRANDHERO DR (0005238) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 0 | 02 - Non-fatal injury | 07 - SMV other | 04 - Slush | 0 | 0 | 0 | 0 |
| 2/18/2021 | 2021 | 8:20 | FALLOWFIELD RD @ STRANDHERO DR (0005238) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 0 | 03 - P.D. only | 03 - Rear end | 06 - Ice | 0 | 0 | 0 | 0 |
| 3/1/2021 | 2021 | 8:49 | FALLOWFIELD RD @ STRANDHERO DR (0005238) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 0 | 03 - P.D. only | 03 - Rear end | 01 - Dry | 0 | 0 | 0 | 0 |
| 7/20/2021 | 2021 | 16:30 | FALLOWFIELD RD @ STRANDHERO DR (0005238) | 02 - Rain | 01 - Daylight | 01 - Traffic signal | 0 | 03 - P.D. only | 04 - Sideswipe | 02 - Wet | 0 | 0 | 0 | 0 |
| 8/27/2021 | 2021 | 16:04 | FALLOWFIELD RD @ STRANDHERO DR (0005238) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 0 | 03 - P.D. only | 04 - Sideswipe | 01 - Dry | 0 | 0 | 0 | 0 |
| 10/31/2021 | 2021 | 3:00 | FALLOWFIELD RD @ STRANDHERO DR (0005238) | 01 - Clear | 07 - Dark | 01 - Traffic signal | 0 | 03 - P.D. only | 07 - SMV other | 01 - Dry | 0 | 0 | 0 | 0 |
| 10/31/2021 | 2021 | 4:27 | FALLOWFIELD RD @ STRANDHERO DR (0005238) | 01 - Clear | 07 - Dark | 01 - Traffic signal | 0 | 03 - P.D. only | 07 - SMV other | 02 - Wet | 0 | 0 | 0 | 0 |
| 11/21/2021 | 2021 | 14:45 | FALLOWFIELD RD @ STRANDHERO DR (0005238) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 0 | 03 - P.D. only | 03 - Rear end | 01 - Dry | 0 | 0 | 0 | 0 |
| 12/15/2021 | 2021 | 11:55 | FALLOWFIELD RD @ STRANDHERO DR (0005238) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 0 | 03 - P.D. only | 03 - Rear end | 01 - Dry | 0 | 0 | 0 | 0 |
| 3/7/2022 | 2022 | 19:45 | FALLOWFIELD RD @ STRANDHERO DR (0005238) | 03 - Snow | 07 - Dark | 01 - Traffic signal | 0 | 03 - P.D. only | 03 - Rear end | 03 - Loose snow | 0 | 0 | 0 | 0 |
| 1/22/2018 | 2018 | 18:13 | CEDARVIEW RD @ FALLOWFIELD RD (0001603) | 03 - Snow | 07 - Dark | 01 - Traffic signal | 0 | 03 - P.D. only | 05 - Turning movement | 03 - Loose snow | 0 | 0 | 0 | 0 |
| 5/22/2018 | 2018 | 8:18 | CEDARVIEW RD @ FALLOWFIELD RD (0001603) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 0 | 03 - P.D. only | 05 - Turning movement | 01 - Dry | 0 | 0 | 0 | 0 |
| 6/14/2018 | 2018 | 8:35 | CEDARVIEW RD @ FALLOWFIELD RD (0001603) | 02 - Rain | 01 - Daylight | 01 - Traffic signal | 0 | 03 - P.D. only | 03 - Rear end | 02 - Wet | 0 | 0 | 0 | 0 |
| 7/9/2018 | 2018 | 11:21 | CEDARVIEW RD @ FALLOWFIELD RD (0001603) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 0 | 03 - P.D. only | 03 - Rear end | 01 - Dry | 0 | 0 | 0 | 0 |
| 6/22/2018 | 2018 | 8:35 | CEDARVIEW RD @ FALLOWFIELD RD (0001603) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 0 | 03 - P.D. only | 05 - Turning movement | 01 - Dry | 0 | 0 | 0 | 0 |
| 8/16/2018 | 2018 | 8:29 | CEDARVIEW RD @ FALLOWFIELD RD (0001603) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 0 | 03 - P.D. only | 03 - Rear end | 01 - Dry | 0 | 0 | 0 | 0 |
| 7/30/2018 | 2018 | 13:56 | CEDARVIEW RD @ FALLOWFIELD RD (0001603) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 0 | 03 - P.D. only | 05 - Turning movement | 01 - Dry | 0 | 0 | 0 | 0 |
| 3/13/2019 | 2019 | 16:21 | CEDARVIEW RD @ FALLOWFIELD RD (0001603) | 02 - Rain | 01 - Daylight | 01 - Traffic signal | 0 | 03 - P.D. only | 03 - Rear end | 02 - Wet | 0 | 0 | 0 | 0 |
| 3/22/2019 | 2019 | 7:50 | CEDARVIEW RD @ FALLOWFIELD RD (0001603) | 02 - Rain | 01 - Daylight | 01 - Traffic signal | 0 | 02 - Non-fatal injury | 05 - Turning movement | 02 - Wet | 0 | 0 | 0 | 0 |
| 4/12/2019 | 2019 | 12:00 | CEDARVIEW RD @ FALLOWFIELD RD (0001603) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 0 | 03 - P.D. only | 99 - Other | 01 - Dry | 0 | 0 | 0 | 0 |
| 6/9/2019 | 2019 | 11:34 | CEDARVIEW RD @ FALLOWFIELD RD (0001603) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 0 | 03 - P.D. only | 03 - Rear end | 01 - Dry | 0 | 0 | 0 | 0 |
| 9/1/2019 | 2019 | 13:10 | CEDARVIEW RD @ FALLOWFIELD RD (0001603) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 0 | 03 - P.D. only | 02 - Angle | 01 - Dry | 0 | 0 | 0 | 0 |
| 9/16/2019 | 2019 | 15:30 | CEDARVIEW RD @ FALLOWFIELD RD (0001603) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 0 | 03 - P.D. only | 03 - Rear end | 01 - Dry | 0 | 0 | 0 | 0 |
| 1/13/2020 | 2020 | 7:30 | CEDARVIEW RD @ FALLOWFIELD RD (0001603) | 01 - Clear | 03 - Down | 01 - Traffic signal | 0 | 03 - P.D. only | 03 - Rear end | 02 - Wet | 0 | 0 | 0 | 0 |
| 2/22/2020 | 2020 | 16:01 | CEDARVIEW RD @ FALLOWFIELD RD (0001603) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 0 | 02 - Non-fatal injury | 03 - Rear end | 01 - Dry | 0 | 0 | 0 | 0 |
| 6/22/2020 | 2020 | 16:55 | CEDARVIEW RD @ FALLOWFIELD RD (0001603) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 0 | 02 - Non-fatal injury | 02 - Angle | 01 - Dry | 0 | 0 | 0 | 0 |
| 8/13/2021 | 2021 | 15:00 | CEDARVIEW RD @ FALLOWFIELD RD (0001603) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 0 | 03 - P.D. only | 03 - Rear end | 01 - Dry | 0 | 0 | 0 | 0 |
| 11/3/2021 | 2021 | 17:18 | CEDARVIEW RD @ FALLOWFIELD RD (0001603) | 01 - Clear | 05 - Dusk | 01 - Traffic signal | 0 | 03 - P.D. only | 02 - Angle | 01 - Dry | 0 | 0 | 0 | 0 |
| 1/5/2022 | 2022 | 22:00 | CEDARVIEW RD @ FALLOWFIELD RD (0001603) | 01 - Clear | 07 - Dark | 01 - Traffic signal | 0 | 03 - P.D. only | 04 - Sideswipe | 02 - Wet | 0 | 0 | 0 | 0 |
| 7/20/2022 | 2022 | 14:07 | CEDARVIEW RD @ FALLOWFIELD RD (0001603) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 0 | 02 - Non-fatal injury | 05 - Turning movement | 01 - Dry | 0 | 0 | 0 | 0 |
| 9/30/2022 | 2022 | 7:41 | CEDARVIEW RD @ FALLOWFIELD RD (0001603) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 0 | 03 - P.D. only | 03 - Rear end | 01 - Dry | 0 | 0 | 0 | 0 |
| 10/29/2018 | 2018 | 6:10 | CEDARVIEW RD btwn FALLOWFIELD RD & WOODSIA AVE (_32A4Y7) | 02 - Rain | 07 - Dark | 10 - No control | 0 | 02 - Non-fatal injury | 07 - SMV other | 02 - Wet | 0 | 0 | 0 | 0 |
| 11/9/2018 | 2018 | 19:20 | CEDARVIEW RD btwn FALLOWFIELD RD & WOODSIA AVE (_32A4Y7) | 03 - Snow | 07 - Dark | 10 - No control | 0 | 03 - P.D. only | 03 - Rear end | 02 - Wet | 0 | 0 | 0 | 0 |
| 9/4/2019 | 2019 | 17:30 | CEDARVIEW RD btwn FALLOWFIELD RD & WOODSIA AVE (_32A4Y7) | 01 - Clear | 01 - Daylight | 10 - No control | 0 | 03 - P.D. only | 03 - Rear end | 01 - Dry | 0 | 0 | 0 | 0 |
| 12/25/2019 | 2019 | 20:01 | CEDARVIEW RD btwn FALLOWFIELD RD & WOODSIA AVE (_32A4Y7) | 01 - Clear | 07 - Dark | 10 - No control | 0 | 02 - Non-fatal injury | 05 - Turning movement | 01 - Dry | 0 | 0 | 0 | 0 |
| 9/16/2020 | 2020 | 16:10 | CEDARVIEW RD btwn CEDARHILL DR & LYTLE AVE (_32A4XG) | 01 - Clear | 01 - Daylight | 10 - No control | 0 | 03 - P.D. only | 07 - SMV other | 01 - Dry | 0 | 0 | 0 | 0 |

Appendix F

TDM Checklist

TDM Measures Checklist:

Non-Residential Developments (office, institutional, retail or industrial)

Legend

- BASIC** The measure is generally feasible and effective, and in most cases would benefit the development and its users
- BETTER** The measure could maximize support for users of sustainable modes, and optimize development performance
- ★** The measure is one of the most dependably effective tools to encourage the use of sustainable modes

| TDM measures: <i>Non-residential developments</i> | | Check if proposed & add descriptions |
|---|---|--------------------------------------|
| 1. TDM PROGRAM MANAGEMENT | | |
| 1.1 Program coordinator | | |
| BASIC ★ | 1.1.1 Designate an internal coordinator, or contract with an external coordinator | <input type="checkbox"/> |
| 1.2 Travel surveys | | |
| BETTER | 1.2.1 Conduct periodic surveys to identify travel-related behaviours, attitudes, challenges and solutions, and to track progress | <input type="checkbox"/> |
| 2. WALKING AND CYCLING | | |
| 2.1 Information on walking/cycling routes & destinations | | |
| BASIC | 2.1.1 Display local area maps with walking/cycling access routes and key destinations at major entrances | <input checked="" type="checkbox"/> |
| 2.2 Bicycle skills training | | |
| <i>Commuter travel</i> | | |
| BETTER ★ | 2.2.1 Offer on-site cycling courses for commuters, or subsidize off-site courses | <input type="checkbox"/> |
| 2.3 Valet bike parking | | |
| <i>Visitor travel</i> | | |
| BETTER | 2.3.1 Offer secure valet bike parking during public events when demand exceeds fixed supply (e.g. for festivals, concerts, games) | <input type="checkbox"/> |

| TDM measures: <i>Non-residential developments</i> | | Check if proposed & add descriptions |
|---|---|--------------------------------------|
| 3. TRANSIT | | |
| 3.1 Transit information | | |
| BASIC | 3.1.1 Display relevant transit schedules and route maps at entrances | <input checked="" type="checkbox"/> |
| BASIC | 3.1.2 Provide online links to OC Transpo and STO information | <input type="checkbox"/> |
| BETTER | 3.1.3 Provide real-time arrival information display at entrances | <input type="checkbox"/> |
| 3.2 Transit fare incentives | | |
| <i>Commuter travel</i> | | |
| BETTER | 3.2.1 Offer preloaded PRESTO cards to encourage commuters to use transit | <input type="checkbox"/> |
| BETTER ★ | 3.2.2 Subsidize or reimburse monthly transit pass purchases by employees | <input type="checkbox"/> |
| <i>Visitor travel</i> | | |
| BETTER | 3.2.3 Arrange inclusion of same-day transit fare in price of tickets (e.g. for festivals, concerts, games) | <input type="checkbox"/> |
| 3.3 Enhanced public transit service | | |
| <i>Commuter travel</i> | | |
| BETTER | 3.3.1 Contract with OC Transpo to provide enhanced transit services (e.g. for shift changes, weekends) | <input type="checkbox"/> |
| <i>Visitor travel</i> | | |
| BETTER | 3.3.2 Contract with OC Transpo to provide enhanced transit services (e.g. for festivals, concerts, games) | <input type="checkbox"/> |
| 3.4 Private transit service | | |
| <i>Commuter travel</i> | | |
| BETTER | 3.4.1 Provide shuttle service when OC Transpo cannot offer sufficient quality or capacity to serve demand (e.g. for shift changes, weekends) | <input type="checkbox"/> |
| <i>Visitor travel</i> | | |
| BETTER | 3.4.2 Provide shuttle service when OC Transpo cannot offer sufficient quality or capacity to serve demand (e.g. for festivals, concerts, games) | <input type="checkbox"/> |

| TDM measures: <i>Non-residential developments</i> | | Check if proposed & add descriptions |
|---|---|--------------------------------------|
| 4. RIDESHARING | | |
| 4.1 Ridematching service | | |
| <i>Commuter travel</i> | | |
| BASIC ★ | 4.1.1 Provide a dedicated ridematching portal at OttawaRideMatch.com | <input type="checkbox"/> |
| 4.2 Carpool parking price incentives | | |
| <i>Commuter travel</i> | | |
| BETTER | 4.2.1 Provide discounts on parking costs for registered carpools | <input type="checkbox"/> |
| 4.3 Vanpool service | | |
| <i>Commuter travel</i> | | |
| BETTER | 4.3.1 Provide a vanpooling service for long-distance commuters | <input type="checkbox"/> |
| 5. CARSHARING & BIKESHARING | | |
| 5.1 Bikeshare stations & memberships | | |
| BETTER | 5.1.1 Contract with provider to install on-site bikeshare station for use by commuters and visitors | <input type="checkbox"/> |
| <i>Commuter travel</i> | | |
| BETTER | 5.1.2 Provide employees with bikeshare memberships for local business travel | <input type="checkbox"/> |
| 5.2 Carshare vehicles & memberships | | |
| <i>Commuter travel</i> | | |
| BETTER | 5.2.1 Contract with provider to install on-site carshare vehicles and promote their use by tenants | <input type="checkbox"/> |
| BETTER | 5.2.2 Provide employees with carshare memberships for local business travel | <input type="checkbox"/> |
| 6. PARKING | | |
| 6.1 Priced parking | | |
| <i>Commuter travel</i> | | |
| BASIC ★ | 6.1.1 Charge for long-term parking (daily, weekly, monthly) | <input type="checkbox"/> |
| BASIC | 6.1.2 Unbundle parking cost from lease rates at multi-tenant sites | <input type="checkbox"/> |
| <i>Visitor travel</i> | | |
| BETTER | 6.1.3 Charge for short-term parking (hourly) | <input type="checkbox"/> |

| TDM measures: <i>Non-residential developments</i> | | Check if proposed & add descriptions |
|---|---|--------------------------------------|
| 7. TDM MARKETING & COMMUNICATIONS | | |
| 7.1 Multimodal travel information | | |
| <i>Commuter travel</i> | | |
| BASIC ★ | 7.1.1 Provide a multimodal travel option information package to new/relocating employees and students | <input checked="" type="checkbox"/> |
| <i>Visitor travel</i> | | |
| BETTER ★ | 7.1.2 Include multimodal travel option information in invitations or advertising that attract visitors or customers (e.g. for festivals, concerts, games) | <input type="checkbox"/> |
| 7.2 Personalized trip planning | | |
| <i>Commuter travel</i> | | |
| BETTER ★ | 7.2.1 Offer personalized trip planning to new/relocating employees | <input type="checkbox"/> |
| 7.3 Promotions | | |
| <i>Commuter travel</i> | | |
| BETTER | 7.3.1 Deliver promotions and incentives to maintain awareness, build understanding, and encourage trial of sustainable modes | <input type="checkbox"/> |
| 8. OTHER INCENTIVES & AMENITIES | | |
| 8.1 Emergency ride home | | |
| <i>Commuter travel</i> | | |
| BETTER ★ | 8.1.1 Provide emergency ride home service to non-driving commuters | <input type="checkbox"/> |
| 8.2 Alternative work arrangements | | |
| <i>Commuter travel</i> | | |
| BASIC ★ | 8.2.1 Encourage flexible work hours | <input type="checkbox"/> |
| BETTER | 8.2.2 Encourage compressed workweeks | <input type="checkbox"/> |
| BETTER ★ | 8.2.3 Encourage telework | <input type="checkbox"/> |
| 8.3 Local business travel options | | |
| <i>Commuter travel</i> | | |
| BASIC ★ | 8.3.1 Provide local business travel options that minimize the need for employees to bring a personal car to work | <input type="checkbox"/> |
| 8.4 Commuter incentives | | |
| <i>Commuter travel</i> | | |
| BETTER | 8.4.1 Offer employees a taxable, mode-neutral commuting allowance | <input type="checkbox"/> |
| 8.5 On-site amenities | | |
| <i>Commuter travel</i> | | |
| BETTER | 8.5.1 Provide on-site amenities/services to minimize mid-day or mid-commute errands | <input type="checkbox"/> |

TDM Measures Checklist:

Residential Developments (multi-family, condominium or subdivision)

| Legend | |
|---------------|--|
| BASIC | The measure is generally feasible and effective, and in most cases would benefit the development and its users |
| BETTER | The measure could maximize support for users of sustainable modes, and optimize development performance |
| ★ | The measure is one of the most dependably effective tools to encourage the use of sustainable modes |

| TDM measures: Residential developments | | Check if proposed & add descriptions |
|---|---|--------------------------------------|
| 1. TDM PROGRAM MANAGEMENT | | |
| 1.1 Program coordinator | | |
| BASIC ★ | 1.1.1 Designate an internal coordinator, or contract with an external coordinator | <input type="checkbox"/> |
| 1.2 Travel surveys | | |
| BETTER | 1.2.1 Conduct periodic surveys to identify travel-related behaviours, attitudes, challenges and solutions, and to track progress | <input type="checkbox"/> |
| 2. WALKING AND CYCLING | | |
| 2.1 Information on walking/cycling routes & destinations | | |
| BASIC | 2.1.1 Display local area maps with walking/cycling access routes and key destinations at major entrances (<i>multi-family, condominium</i>) | <input checked="" type="checkbox"/> |
| 2.2 Bicycle skills training | | |
| BETTER | 2.2.1 Offer on-site cycling courses for residents, or subsidize off-site courses | <input type="checkbox"/> |

| TDM measures: Residential developments | | Check if proposed & add descriptions |
|---|--|--------------------------------------|
| 3. TRANSIT | | |
| 3.1 Transit information | | |
| BASIC | 3.1.1 Display relevant transit schedules and route maps at entrances (<i>multi-family, condominium</i>) | <input checked="" type="checkbox"/> |
| BETTER | 3.1.2 Provide real-time arrival information display at entrances (<i>multi-family, condominium</i>) | <input type="checkbox"/> |
| 3.2 Transit fare incentives | | |
| BASIC ★ | 3.2.1 Offer PRESTO cards preloaded with one monthly transit pass on residence purchase/move-in, to encourage residents to use transit | <input type="checkbox"/> |
| BETTER | 3.2.2 Offer at least one year of free monthly transit passes on residence purchase/move-in | <input type="checkbox"/> |
| 3.3 Enhanced public transit service | | |
| BETTER ★ | 3.3.1 Contract with OC Transpo to provide early transit services until regular services are warranted by occupancy levels (<i>subdivision</i>) | <input checked="" type="checkbox"/> |
| 3.4 Private transit service | | |
| BETTER | 3.4.1 Provide shuttle service for seniors homes or lifestyle communities (e.g. scheduled mall or supermarket runs) | <input type="checkbox"/> |
| 4. CARSHARING & BIKESHARING | | |
| 4.1 Bikeshare stations & memberships | | |
| BETTER | 4.1.1 Contract with provider to install on-site bikeshare station (<i>multi-family</i>) | <input type="checkbox"/> |
| BETTER | 4.1.2 Provide residents with bikeshare memberships, either free or subsidized (<i>multi-family</i>) | <input type="checkbox"/> |
| 4.2 Carshare vehicles & memberships | | |
| BETTER | 4.2.1 Contract with provider to install on-site carshare vehicles and promote their use by residents | <input checked="" type="checkbox"/> |
| BETTER | 4.2.2 Provide residents with carshare memberships, either free or subsidized | <input type="checkbox"/> |
| 5. PARKING | | |
| 5.1 Priced parking | | |
| BASIC ★ | 5.1.1 Unbundle parking cost from purchase price (<i>condominium</i>) | <input type="checkbox"/> |
| BASIC ★ | 5.1.2 Unbundle parking cost from monthly rent (<i>multi-family</i>) | <input type="checkbox"/> |

| TDM measures: <i>Residential developments</i> | | Check if proposed & add descriptions |
|---|---|--------------------------------------|
| 6. TDM MARKETING & COMMUNICATIONS | | |
| 6.1 Multimodal travel information | | |
| BASIC ★ | 6.1.1 Provide a multimodal travel option information package to new residents | <input checked="" type="checkbox"/> |
| 6.2 Personalized trip planning | | |
| BETTER ★ | 6.2.1 Offer personalized trip planning to new residents | <input type="checkbox"/> |

Appendix G

TRANS Model Plots

TRANS Regional Model

Version 2.15 - Assigned June 16, 2020




AM Peak Hour Total Traffic Volume
Cedarview Road Area

2011 Model - Basecase
N/A

User Initials: MANS
Plot Prepared: July 24, 2023
EMME Scenario: 21713



Legend



The TRANS model is continuously refined & maintained, and all information is provided in good faith. However, model outputs are provided "as is", and no warranty or guarantee is provided as to the accuracy, reliability or reasonableness of the results. In using this data, you agree to accept any and all risks arising from any incorrect, incomplete, or misleading information.

Recipients are required to use caution and professional judgement in using and interpreting model outputs. In particular, caution should be used when focusing on a geographically limited area (such as a single road or intersection), as the model is primarily designed to simulate regional-scale phenomena and has been calibrated at a regional level.

As general good practice, it is recommended that the user confirm the network coding within the area of interest, and compare base year forecasts against traffic count data to assess the extent to which the model may be over- or under-estimating the travel demand.

TRANS Regional Model

Version 2.15 - Assigned June 16, 2020



AM Peak Hour Total Traffic Volume
Cedarview Road Area

2031 Model - Basecase
N/A

User Initials: MANS
Plot Prepared: July 24, 2023
EMME Scenario: 21717




Legend



The TRANS model is continuously refined & maintained, and all information is provided in good faith. However, model outputs are provided "as is", and no warranty or guarantee is provided as to the accuracy, reliability or reasonableness of the results. In using this data, you agree to accept any and all risks arising from any incorrect, incomplete, or misleading information.



Recipients are required to use caution and professional judgement in using and interpreting model outputs. In particular, caution should be used when focusing on a geographically limited area (such as a single road or intersection), as the model is primarily designed to simulate regional-scale phenomena and has been calibrated at a regional level.

As general good practice, it is recommended that the user confirm the network coding within the area of interest, and compare base year forecasts against traffic count data to assess the extent to which the model may be over- or under-estimating the travel demand.



Appendix H

Background Development Volumes



115 Lusk Street
Transportation Impact Assessment

Exhibit 4:
Site-Generated
AM & PM Peak Hour
Traffic


PROJECT No. 122508
DATE: January 2021
SCALE: N.T.S.



135 Lusk Street
Transportation Impact Assessment

Exhibit 6 - Site-Generated
Traffic

PROJECT No. 135639
SCALE: N.T.S.



LEGEND

- Permitted Movements
- Weekday AM (PM) Peak Hour Vehicular Volume

Figure 4: Site Generated Traffic Volumes





Figure 12: New Site Generation Auto Volumes



4.3 Other CitiGate Traffic

Trips generated by the car dealerships as well as developments at 4175/4149 Strandherd Drive (Blocks 3 and 4) are anticipated to generate traffic to/from Strandherd Drive and not utilize the internal Business Park intersections. The following table shows person trips generated by the proposed/future uses within the CitiGate Business Park that are anticipated to generate traffic at the internal intersections.

Peak hour of site traffic for the neighboring Amazon facility is anticipated to occur at 6:00AM-7:00AM and 5:30PM-6:30PM, due to the nature of shift work anticipated at this facility. Based on the recent traffic counts, the weekday peak hour of adjacent road traffic along Strandherd Drive typically occurs between 7:45AM-8:45AM and from 4:00PM-5:00PM. While Amazon site traffic and peak hour of road traffic are not expected to coincide, the Amazon site traffic has been superimposed on peak hour of road traffic for this memo. This will result in a more conservative and robust analysis.

Table 4: Other CitiGate Traffic - Person Trips

| Land Use | ITE Code | Size | AM Peak | | | PM Peak | | |
|---|----------|---------------|---------|-----|------|---------|-----|------|
| | | | IN | OUT | TOT | IN | OUT | TOT |
| Amazon Distribution Facility | | | | | | | | |
| Distribution Facility | - | 2,728,000 ft² | 519 | 538 | 1057 | 679 | 691 | 1370 |
| Proposed Hotel – 101 CitiGate | | | | | | | | |
| Phase 1 – Hotel | 310 | 99 rooms | 34 | 23 | 57 | 32 | 30 | 62 |
| Phase 2 – Hotel | 310 | 85 rooms | 26 | 19 | 45 | 23 | 22 | 45 |
| Future Hotel – 4433 Strandherd | | | | | | | | |
| Phase 1 – Hotel | 310 | 120 rooms | 37 | 31 | 68 | 40 | 38 | 78 |
| Phase 1 – Restaurant | 932 | 5,000 ft² | 33 | 28 | 61 | 35 | 23 | 58 |
| Phase 2 – Hotel | 310 | 135 rooms | 44 | 33 | 77 | 47 | 45 | 92 |
| Phase 2 – Restaurant | 932 | 5,000 ft² | 33 | 28 | 61 | 35 | 23 | 58 |
| Future Warehouse - 575 Dealership | | | | | | | | |
| Warehouse | 150 | 320,000 ft² | 54 | 15 | 69 | 20 | 54 | 74 |
| Future Prestige Business Park (lands south of Dealership Drive) | | | | | | | | |
| Office Park | 750 | 500,000 ft² | 756 | 95 | 851 | 116 | 718 | 834 |
| Future Business Park (lands south of Dealership Drive) | | | | | | | | |
| Business Park | 770 | 275,000 ft² | 388 | 68 | 456 | 119 | 338 | 457 |

Modal shares are anticipated to be consistent with recent traffic studies prepared for the above developments or the overall 2012 CitiGate CTS. Vehicle trips generated by the proposed/future uses within the CitiGate Business Park are shown in **Table 5**.

Trips generated by the Amazon facility and the proposed hotel at 101 CitiGate Drive have been assigned using the assumptions outlined in their respective traffic studies. Trips generated by the hotel at 4433 Strandherd Drive have been assigned in a similar manner to the traffic study for the hotel at 101 CitiGate Drive. Trips generated by the future warehouse, prestige business park and business park lands have been assigned in a manner consistent with the 2012 CTS.

The Amazon facility and proposed hotel at 101 CitiGate Drive have been assumed to be in place for the subject site buildout year. For the ultimate development scenario, the McKenna Casey Drive realignment is anticipated to be in place and 5% of Amazon traffic destined to the west has been reassigned to this connection. All other developments and the McKenna Casey Drive realignment are assumed to be in place for the ultimate condition.

Table 5: Other CitiGate Traffic – Vehicle Trips

| Land Use | Auto Driver Share | Size | AM Peak | | | PM Peak | | |
|---|-------------------|----------------------------------|---------|-----|-----|---------|-----|-----|
| | | | IN | OUT | TOT | IN | OUT | TOT |
| Amazon Distribution Facility | | | | | | | | |
| Distribution Facility | 56% | 2,728,000 ft² | 284 | 295 | 579 | 375 | 381 | 756 |
| Proposed Hotel – 101 CitiGate | | | | | | | | |
| Phases 1 and 2 (two hotels) | 85% | 184 rooms | 51 | 36 | 87 | 47 | 44 | 91 |
| Future Hotel – 4433 Strandherd | | | | | | | | |
| Phases 1 and 2 (two hotels and two restaurants) | 85% | 255 rooms, 10,000 ft² restaurant | 125 | 102 | 227 | 133 | 110 | 243 |
| Future Warehouse - 575 Dealership | | | | | | | | |
| Warehouse | 56% | 320,000 ft² | 30 | 8 | 38 | 11 | 30 | 41 |
| Future Prestige Business Park (lands south of Dealership Drive) | | | | | | | | |
| Office Park | 56% | 500,000 ft² | 423 | 53 | 476 | 65 | 402 | 467 |
| Future Business Park (lands south of Dealership Drive) | | | | | | | | |
| Business Park | 56% | 275,000 ft² | 217 | 38 | 255 | 67 | 189 | 256 |

Background and total traffic volumes are shown in the following figures:

- **Figure 6** shows the background traffic (not including subject site) for the buildout year.
- **Figure 7** shows the background traffic (not including the subject site) for the ultimate condition.
- **Figure 8** shows the total traffic (including the subject site) for the buildout year.
- **Figure 9** shows the total traffic (including the subject site) for the ultimate condition.

Figure 6: Background Traffic - Buildout Year






Figure 7: Background Traffic – Ultimate




M:\2022\122003\DATA\REPORTS\TRAFFIC\2022\1129-TRAFFIC.DOCX

Figure 4: Site Traffic - Buildout Year



M:\2022\122003\DATA\REPORTS\TRAFFIC\2022\1129-TRAFFIC.DOCX

Figure 5: Site Traffic – Ultimate



M:\2022\122003\DATA\REPORTS\TRAFFIC\20221129-TRAFFIC.DOCX

Appendix I

Synchro Intersection Worksheets – 2038 Future Background Conditions

HCM 2010 TWSC
1: Cedarview & Onassa

2028 Future BackgroundAM Peak Hour
4497 O'Keefe Court

| Intersection | | | | | | |
|--------------------------|--------|--------|--------|------|------|------|
| Int Delay, s/veh | 0.4 | | | | | |
| Movement | EBL | EBR | NBL | NBT | SBT | SBR |
| Lane Configurations | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ |
| Traffic Vol, veh/h | 14 | 6 | 9 | 385 | 432 | 12 |
| Future Vol, veh/h | 14 | 6 | 9 | 385 | 432 | 12 |
| Conflicting Peds, #/hr | 0 | 0 | 0 | 0 | 0 | 0 |
| Sign Control | Stop | Stop | Free | Free | Free | Free |
| RT Channelized | - | None | - | None | - | None |
| Storage Length | 0 | - | - | - | - | - |
| Veh in Median Storage, # | 0 | - | - | 0 | 0 | - |
| Grade, % | 0 | - | - | 0 | 0 | - |
| Peak Hour Factor | 100 | 100 | 100 | 100 | 100 | 100 |
| Heavy Vehicles, % | 14 | 2 | 11 | 2 | 2 | 17 |
| Mvmt Flow | 14 | 6 | 9 | 385 | 432 | 12 |
| Major/Minor | Minor2 | Major1 | Major2 | | | |
| Conflicting Flow All | 841 | 438 | 444 | 0 | - | 0 |
| Stage 1 | 438 | - | - | - | - | - |
| Stage 2 | 403 | - | - | - | - | - |
| Critical Hdwy | 6.54 | 6.22 | 4.21 | - | - | - |
| Critical Hdwy Stg 1 | 5.54 | - | - | - | - | - |
| Critical Hdwy Stg 2 | 5.54 | - | - | - | - | - |
| Follow-up Hdwy | 3.626 | 3.318 | 2.299 | - | - | - |
| Pot Cap-1 Maneuver | 319 | 619 | 1070 | - | - | - |
| Stage 1 | 626 | - | - | - | - | - |
| Stage 2 | 650 | - | - | - | - | - |
| Platoon blocked, % | - | - | - | - | - | - |
| Mov Cap-1 Maneuver | 315 | 619 | 1070 | - | - | - |
| Mov Cap-2 Maneuver | 315 | - | - | - | - | - |
| Stage 1 | 619 | - | - | - | - | - |
| Stage 2 | 650 | - | - | - | - | - |
| Approach | EB | NB | SB | | | |
| HCM Control Delay, s | 15.3 | 0.2 | 0 | | | |
| HCM LOS | C | | | | | |
| Minor Lane/Major Mvmt | NBL | NBT | EBLn1 | SBT | SBR | |
| Capacity (veh/h) | 1070 | - | 369 | - | - | |
| HCM Lane V/C Ratio | 0.008 | - | 0.054 | - | - | |
| HCM Control Delay (s) | 8.4 | 0 | 15.3 | - | - | |
| HCM Lane LOS | A | A | C | - | - | |
| HCM 95th %tile Q(veh) | 0 | - | 0.2 | - | - | |

Lanes, Volumes, Timings
2: Citigate & Fallowfield & Strandherd

2028 Future BackgroundAM Peak Hour
4497 O'Keefe Court

| Lane Group | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|--|-------|--------|-------|-------|--------|-------|-------|-------|-----|-------|-------|-------|
| Lane Configurations | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ |
| Traffic Volume (vph) | 476 | 1201 | 249 | 38 | 1775 | 83 | 66 | 35 | 10 | 59 | 125 | 437 |
| Future Volume (vph) | 476 | 1201 | 249 | 38 | 1775 | 83 | 66 | 35 | 10 | 59 | 125 | 437 |
| Satd. Flow (prot) | 3066 | 3103 | 1401 | 1353 | 3221 | 1483 | 2929 | 1401 | 0 | 1658 | 1664 | 1469 |
| Fit Permitted | 0.950 | | | 0.950 | | | 0.950 | | | 0.950 | | |
| Satd. Flow (perm) | 3066 | 3103 | 1401 | 1353 | 3221 | 1483 | 2927 | 1401 | 0 | 1658 | 1664 | 1450 |
| Satd. Flow (RTOR) | | | 240 | | | 225 | | 10 | | | | 371 |
| Lane Group Flow (vph) | 476 | 1201 | 249 | 38 | 1775 | 83 | 66 | 45 | 0 | 59 | 125 | 437 |
| Turn Type | Prot | NA | Perm | Prot | NA | Perm | Prot | NA | | Prot | NA | Perm |
| Protected Phases | 13 | 2 | 2 | 9 | 6 | 6 | 7 | 4 | | 3 | 8 | 8 |
| Permitted Phases | | | 2 | | | 6 | | | | | | 8 |
| Detector Phase | 13 | 2 | 2 | 9 | 6 | 6 | 7 | 4 | | 3 | 8 | 8 |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 5.0 | 10.0 | 10.0 | 5.0 | 10.0 | 10.0 | 5.0 | 10.0 | | 5.0 | 10.0 | 10.0 |
| Minimum Split (s) | 12.1 | 29.9 | 29.9 | 12.1 | 29.9 | 29.9 | 11.5 | 48.0 | | 11.5 | 48.0 | 48.0 |
| Total Split (s) | 28.0 | 46.0 | 46.0 | 13.0 | 31.0 | 31.0 | 13.0 | 48.0 | | 13.0 | 48.0 | 48.0 |
| Total Split (%) | 23.3% | 38.3% | 38.3% | 10.8% | 25.8% | 25.8% | 10.8% | 40.0% | | 10.8% | 40.0% | 40.0% |
| Yellow Time (s) | 4.6 | 4.6 | 4.6 | 4.6 | 4.6 | 4.6 | 3.7 | 3.7 | | 3.7 | 3.7 | 3.7 |
| All-Red Time (s) | 2.5 | 2.3 | 2.3 | 2.5 | 2.3 | 2.3 | 2.8 | 3.3 | | 2.8 | 3.3 | 3.3 |
| Lost Time Adjust (s) | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 |
| Total Lost Time (s) | 7.1 | 6.9 | 6.9 | 7.1 | 6.9 | 6.9 | 6.5 | 7.0 | | 6.5 | 7.0 | 7.0 |
| Lead/Lag | | | | | | | Lag | Lead | | Lag | Lead | Lead |
| Lead-Lag Optimize? | | | | | | | Yes | Yes | | Yes | Yes | Yes |
| Recall Mode | None | C-Max | C-Max | None | C-Max | C-Max | None | None | | None | None | None |
| Act Effct Green (s) | 24.2 | 63.1 | 63.1 | 9.1 | 45.4 | 45.4 | 8.1 | 10.5 | | 14.9 | 17.2 | 17.2 |
| Actuated g/C Ratio | 0.20 | 0.53 | 0.53 | 0.08 | 0.38 | 0.38 | 0.07 | 0.09 | | 0.12 | 0.14 | 0.14 |
| v/c Ratio | 0.77 | 0.74 | 0.29 | 0.37 | 1.46 | 0.12 | 0.34 | 0.34 | | 0.29 | 0.53 | 0.83 |
| Control Delay | 54.0 | 29.7 | 4.7 | 62.2 | 239.5 | 0.3 | 57.4 | 49.6 | | 47.8 | 53.7 | 22.7 |
| Queue Delay | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 |
| Total Delay | 54.0 | 29.7 | 4.7 | 62.2 | 239.5 | 0.3 | 57.4 | 49.6 | | 47.8 | 53.7 | 22.7 |
| LOS | D | C | A | E | F | A | E | D | | D | D | C |
| Approach Delay | | 32.5 | | | 225.4 | | | 54.2 | | | 31.4 | |
| Approach LOS | | C | | | F | | | D | | | C | |
| Queue Length 50th (m) | 54.6 | 115.7 | 1.0 | 8.7 | ~301.3 | 0.0 | 7.7 | 7.9 | | 13.1 | 28.4 | 14.5 |
| Queue Length 95th (m) | 70.7 | #219.2 | 19.4 | 19.5 | #416.8 | 0.0 | 14.6 | 19.4 | | 22.4 | 40.9 | 47.9 |
| Internal Link Dist (m) | | 441.7 | | | 233.3 | | | 132.8 | | | 356.4 | |
| Turn Bay Length (m) | 127.0 | | 96.5 | 95.0 | | 90.0 | 90.0 | | | 140.0 | | 125.0 |
| Base Capacity (vph) | 627 | 1632 | 850 | 102 | 1219 | 701 | 200 | 485 | | 206 | 568 | 739 |
| Starvation Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | 0 |
| Spillback Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | 0 |
| Storage Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | 0 |
| Reduced v/c Ratio | 0.76 | 0.74 | 0.29 | 0.37 | 1.46 | 0.12 | 0.33 | 0.09 | | 0.29 | 0.22 | 0.59 |
| Intersection Summary | | | | | | | | | | | | |
| Cycle Length: 120 | | | | | | | | | | | | |
| Actuated Cycle Length: 120 | | | | | | | | | | | | |
| Offset: 101 (84%), Referenced to phase 2:EBT and 6:WBT, Start of Green | | | | | | | | | | | | |
| Natural Cycle: 145 | | | | | | | | | | | | |
| Control Type: Actuated-Coordinated | | | | | | | | | | | | |

Lanes, Volumes, Timings
2: Citigate & Fallowfield & Strandherd

2028 Future BackgroundAM Peak Hour
4497 O'Keefe Court

Maximum v/c Ratio: 1.46

Intersection Signal Delay: 113.2

Intersection LOS: F

Intersection Capacity Utilization 102.4%

ICU Level of Service G

Analysis Period (min) 15


~ Volume exceeds capacity, queue is theoretically infinite.

Queue shown is maximum after two cycles.

95th percentile volume exceeds capacity, queue may be longer.

Queue shown is maximum after two cycles.

Splits and Phases: 2: Citigate & Fallowfield & Strandherd



HCM 2010 TWSC
3: Cobble Hill/O'Keefe & Fallowfield

2028 Future BackgroundAM Peak Hour
4497 O'Keefe Court

Intersection

Int Delay, s/veh 5.2

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|--------------------------|-------|------|------|------|------|------|------|------|------|------|------|------|
| Lane Configurations | ↰ | ↑ | ↱ | ↰ | ↑ | ↱ | ↰ | ↑ | ↱ | ↰ | ↑ | ↱ |
| Traffic Vol, veh/h | 92 | 597 | 11 | 15 | 593 | 11 | 34 | 2 | 52 | 32 | 4 | 18 |
| Future Vol, veh/h | 92 | 597 | 11 | 15 | 593 | 11 | 34 | 2 | 52 | 32 | 4 | 18 |
| Conflicting Peds, #/hr | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 1 | 0 | 0 |
| Sign Control | Free | Free | Free | Free | Free | Free | Stop | Stop | Stop | Stop | Stop | Stop |
| RT Channelized | - | - | None | - | - | None | - | - | None | - | - | None |
| Storage Length | 147.5 | - | 0 | - | - | 30.5 | - | - | - | 42.5 | - | - |
| Veh in Median Storage, # | - | 0 | - | - | 0 | - | - | 0 | - | - | 0 | - |
| Grade, % | - | 0 | - | - | 0 | - | - | 0 | - | - | 0 | - |
| Peak Hour Factor | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| Heavy Vehicles, % | 11 | 4 | 9 | 7 | 5 | 14 | 2 | 50 | 2 | 33 | 67 | 2 |
| Mvmt Flow | 92 | 597 | 11 | 15 | 593 | 11 | 34 | 2 | 52 | 32 | 4 | 18 |

| Major/Minor | Major1 | Major2 | Minor1 | Minor2 |
|----------------------|--------|--------|--------|--------|
| Conflicting Flow All | 604 | 0 | 0 | 608 |
| Stage 1 | - | - | - | - |
| Stage 2 | - | - | - | - |
| Critical Hdwy | 4.21 | - | 4.17 | - |
| Critical Hdwy Stg 1 | - | - | - | - |
| Critical Hdwy Stg 2 | - | - | - | - |
| Follow-up Hdwy | 2.299 | - | 2.263 | - |
| Pot Cap-1 Maneuver | 931 | - | 946 | - |
| Stage 1 | - | - | - | - |
| Stage 2 | - | - | - | - |
| Platoon blocked, % | - | - | - | - |
| Mov Cap-1 Maneuver | 931 | - | 946 | - |
| Mov Cap-2 Maneuver | - | - | - | - |
| Stage 1 | - | - | - | - |
| Stage 2 | - | - | - | - |

| Approach | EB | WB | NB | SB |
|----------------------|-----|-----|----|------|
| HCM Control Delay, s | 1.2 | 0.2 | 41 | 57.1 |
| HCM LOS | - | - | E | F |

| Minor Lane/Major Mvmt | NBLn1 | EBL | EBT | EBR | WBL | WBT | WBR | SBLn1 | SBLn2 |
|-----------------------|-------|-------|-----|-----|-------|-----|-----|-------|-------|
| Capacity (veh/h) | 185 | 931 | - | - | 946 | - | - | 76 | 275 |
| HCM Lane V/C Ratio | 0.476 | 0.099 | - | - | 0.016 | - | - | 0.421 | 0.08 |
| HCM Control Delay (s) | 41 | 9.3 | - | - | 8.9 | - | - | 83.2 | 19.2 |
| HCM Lane LOS | E | A | - | - | A | - | - | F | C |
| HCM 95th %tile Q(veh) | 2.3 | 0.3 | - | - | 0 | - | - | 1.7 | 0.3 |

Lanes, Volumes, Timings
4: Cedarview & Fallowfield

2028 Future BackgroundAM Peak Hour
4497 O'Keefe Court

| Lane Group | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|-------|--------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-----|
| Lane Configurations | ↰ | ↑ | ↱ | ↰ | ↑ | ↱ | ↰ | ↑ | ↱ | ↰ | ↑ | ↱ |
| Traffic Volume (vph) | 47 | 787 | 10 | 32 | 556 | 181 | 49 | 359 | 278 | 204 | 129 | 12 |
| Future Volume (vph) | 47 | 787 | 10 | 32 | 556 | 181 | 49 | 359 | 278 | 204 | 129 | 12 |
| Satd. Flow (prot) | 1658 | 1712 | 1261 | 1537 | 1728 | 1483 | 1658 | 1745 | 1469 | 1642 | 1686 | 0 |
| Flt Permitted | 0.341 | | | 0.166 | | | 0.667 | | | 0.389 | | |
| Satd. Flow (perm) | 595 | 1712 | 1234 | 269 | 1728 | 1483 | 1164 | 1745 | 1469 | 672 | 1686 | 0 |
| Satd. Flow (RTOR) | | | 49 | | | 181 | | | 128 | | 6 | |
| Lane Group Flow (vph) | 47 | 787 | 10 | 32 | 556 | 181 | 49 | 359 | 278 | 204 | 141 | 0 |
| Turn Type | Perm | NA | Perm | Perm | NA | Perm | Perm | NA | Perm | Perm | NA | |
| Protected Phases | | 2 | | | 6 | | | 4 | | | 8 | |
| Permitted Phases | 2 | | 2 | 6 | | 6 | 4 | | 4 | 8 | | |
| Detector Phase | 2 | 2 | 2 | 6 | 6 | 6 | 4 | 4 | 4 | 8 | 8 | |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | |
| Minimum Split (s) | 48.0 | 48.0 | 48.0 | 48.0 | 48.0 | 48.0 | 37.0 | 37.0 | 37.0 | 37.0 | 37.0 | |
| Total Split (s) | 48.0 | 48.0 | 48.0 | 48.0 | 48.0 | 48.0 | 37.0 | 37.0 | 37.0 | 37.0 | 37.0 | |
| Total Split (%) | 56.5% | 56.5% | 56.5% | 56.5% | 56.5% | 56.5% | 43.5% | 43.5% | 43.5% | 43.5% | 43.5% | |
| Yellow Time (s) | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | |
| All-Red Time (s) | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.8 | 3.8 | 3.8 | 3.8 | 3.8 | |
| Lost Time Adjust (s) | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | |
| Total Lost Time (s) | 6.7 | 6.7 | 6.7 | 6.7 | 6.7 | 6.7 | 6.8 | 6.8 | 6.8 | 6.8 | 6.8 | |
| Lead/Lag | | | | | | | | | | | | |
| Lead-Lag Optimize? | | | | | | | | | | | | |
| Recall Mode | C-Max | C-Max | C-Max | C-Max | C-Max | C-Max | None | None | None | None | None | |
| Act Effct Green (s) | 44.8 | 44.8 | 44.8 | 44.8 | 44.8 | 44.8 | 26.7 | 26.7 | 26.7 | 26.7 | 26.7 | |
| Actuated g/C Ratio | 0.53 | 0.53 | 0.53 | 0.53 | 0.53 | 0.53 | 0.31 | 0.31 | 0.31 | 0.31 | 0.31 | |
| v/c Ratio | 0.15 | 0.87 | 0.01 | 0.23 | 0.61 | 0.21 | 0.13 | 0.66 | 0.51 | 0.97 | 0.26 | |
| Control Delay | 13.7 | 32.3 | 0.0 | 17.9 | 18.9 | 2.7 | 20.0 | 30.7 | 15.0 | 84.8 | 21.0 | |
| Queue Delay | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | |
| Total Delay | 13.7 | 32.3 | 0.0 | 17.9 | 18.9 | 2.7 | 20.0 | 30.7 | 15.0 | 84.8 | 21.0 | |
| LOS | B | C | A | B | B | A | B | C | B | F | C | |
| Approach Delay | | 30.9 | | | 15.0 | | | 23.5 | | | 58.7 | |
| Approach LOS | | C | | | B | | | C | | | E | |
| Queue Length 50th (m) | 4.1 | 116.1 | 0.0 | 2.9 | 65.3 | 0.0 | 5.3 | 46.6 | 17.2 | 30.2 | 15.1 | |
| Queue Length 95th (m) | 10.5 | #192.4 | 0.0 | 9.7 | 100.0 | 9.7 | 12.8 | 73.4 | 38.0 | #69.0 | 28.2 | |
| Internal Link Dist (m) | | 561.2 | | | 452.7 | | | 444.3 | | | 482.1 | |
| Turn Bay Length (m) | 60.0 | | 55.0 | 60.0 | | 55.0 | 180.0 | | 80.0 | 45.5 | | |
| Base Capacity (vph) | 313 | 901 | 673 | 141 | 910 | 866 | 413 | 619 | 604 | 238 | 602 | |
| Starvation Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Spillback Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Storage Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Reduced v/c Ratio | 0.15 | 0.87 | 0.01 | 0.23 | 0.61 | 0.21 | 0.12 | 0.58 | 0.46 | 0.86 | 0.23 | |

Intersection Summary

Cycle Length: 85

Actuated Cycle Length: 85

Offset: 40 (47%), Referenced to phase 2:EBTL and 6:WBTL, Start of Green

Natural Cycle: 85

Control Type: Actuated-Coordinated

Lanes, Volumes, Timings
4: Cedarview & Fallowfield

2028 Future BackgroundAM Peak Hour
4497 O'Keefe Court

Maximum v/c Ratio: 0.97

Intersection Signal Delay: 28.0

Intersection LOS: C

Intersection Capacity Utilization 92.5%


ICU Level of Service F

Analysis Period (min) 15

95th percentile volume exceeds capacity, queue may be longer.

Queue shown is maximum after two cycles.

Splits and Phases: 4: Cedarview & Fallowfield



HCM 2010 TWSC
1: Cedarview & Onassa

2038 Future Background PM Peak Hour
4497 O'Keefe Court

| Intersection | | | | | | |
|--------------------------|------|------|------|------|------|------|
| Int Delay, s/veh | 0.5 | | | | | |
| Movement | EBL | EBR | NBL | NBT | SBT | SBR |
| Lane Configurations | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ |
| Traffic Vol, veh/h | 13 | 15 | 4 | 507 | 576 | 8 |
| Future Vol, veh/h | 13 | 15 | 4 | 507 | 576 | 8 |
| Conflicting Peds, #/hr | 0 | 0 | 0 | 0 | 0 | 0 |
| Sign Control | Stop | Stop | Free | Free | Free | Free |
| RT Channelized | - | None | - | None | - | None |
| Storage Length | 0 | - | - | - | - | - |
| Veh in Median Storage, # | 0 | - | - | 0 | 0 | - |
| Grade, % | 0 | - | - | 0 | 0 | - |
| Peak Hour Factor | 100 | 100 | 100 | 100 | 100 | 100 |
| Heavy Vehicles, % | 8 | 7 | 2 | 2 | 2 | 2 |
| Mvmt Flow | 13 | 15 | 4 | 507 | 576 | 8 |

| Major/Minor | Minor2 | Major1 | Major2 |
|----------------------|--------|--------|--------|
| Conflicting Flow All | 1095 | 580 | 584 |
| Stage 1 | 580 | - | - |
| Stage 2 | 515 | - | - |
| Critical Hdwy | 6.48 | 6.27 | 4.12 |
| Critical Hdwy Stg 1 | 5.48 | - | - |
| Critical Hdwy Stg 2 | 5.48 | - | - |
| Follow-up Hdwy | 3.572 | 3.363 | 2.218 |
| Pot Cap-1 Maneuver | 230 | 505 | 991 |
| Stage 1 | 548 | - | - |
| Stage 2 | 588 | - | - |
| Platoon blocked, % | - | - | - |
| Mov Cap-1 Maneuver | 229 | 505 | 991 |
| Mov Cap-2 Maneuver | 229 | - | - |
| Stage 1 | 545 | - | - |
| Stage 2 | 588 | - | - |

| Approach | EB | NB | SB |
|----------------------|------|-----|----|
| HCM Control Delay, s | 17.2 | 0.1 | 0 |
| HCM LOS | C | | |

| Minor Lane/Major Mvmt | NBL | NBT | EBLn1 | SBT | SBR |
|-----------------------|-------|-----|-------|-----|-----|
| Capacity (veh/h) | 991 | - | 324 | - | - |
| HCM Lane V/C Ratio | 0.004 | - | 0.086 | - | - |
| HCM Control Delay (s) | 8.6 | 0 | 17.2 | - | - |
| HCM Lane LOS | A | A | C | - | - |
| HCM 95th %tile Q(veh) | 0 | - | 0.3 | - | - |

Lanes, Volumes, Timings
2: Citigate & Fallowfield & Strandherd

2038 Future Background PM Peak Hour
4497 O'Keefe Court

| Lane Group | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|-------|--------|-------|-------|--------|-------|-------|-------|------|-------|-------|-------|
| Lane Configurations | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ |
| Traffic Volume (vph) | 419 | 1655 | 208 | 10 | 1873 | 116 | 371 | 168 | 43 | 124 | 89 | 505 |
| Future Volume (vph) | 419 | 1655 | 208 | 10 | 1873 | 116 | 371 | 168 | 43 | 124 | 89 | 505 |
| Satd. Flow (prot) | 3216 | 3316 | 1469 | 1127 | 3316 | 1483 | 3154 | 1639 | 0 | 1658 | 1664 | 1455 |
| Fit Permitted | 0.950 | | | 0.950 | | | 0.950 | | | 0.950 | | |
| Satd. Flow (perm) | 3216 | 3316 | 1432 | 1127 | 3316 | 1483 | 3154 | 1639 | 0 | 1658 | 1664 | 1455 |
| Satd. Flow (RTOR) | | | 160 | | | 160 | | | 12 | | | 358 |
| Lane Group Flow (vph) | 419 | 1655 | 208 | 10 | 1873 | 116 | 371 | 211 | 0 | 124 | 89 | 505 |
| Turn Type | Prot | NA | Perm | Prot | NA | Perm | Prot | NA | Prot | NA | Perm | Perm |
| Protected Phases | 13 | 2 | 2 | 9 | 6 | 6 | 7 | 4 | | 3 | 8 | 8 |
| Permitted Phases | | | 2 | | | 6 | | | | | | 8 |
| Detector Phase | 13 | 2 | 2 | 9 | 6 | 6 | 7 | 4 | | 3 | 8 | 8 |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 5.0 | 10.0 | 10.0 | 5.0 | 10.0 | 10.0 | 5.0 | 10.0 | | 5.0 | 10.0 | 10.0 |
| Minimum Split (s) | 12.1 | 29.9 | 29.9 | 12.1 | 29.9 | 29.9 | 11.5 | 48.0 | | 11.5 | 48.0 | 48.0 |
| Total Split (s) | 24.0 | 34.0 | 34.0 | 24.0 | 34.0 | 34.0 | 14.0 | 48.0 | | 14.0 | 48.0 | 48.0 |
| Total Split (%) | 20.0% | 28.3% | 28.3% | 20.0% | 28.3% | 28.3% | 11.7% | 40.0% | | 11.7% | 40.0% | 40.0% |
| Yellow Time (s) | 4.6 | 4.6 | 4.6 | 4.6 | 4.6 | 4.6 | 3.7 | 3.7 | | 3.7 | 3.7 | 3.7 |
| All-Red Time (s) | 2.5 | 2.3 | 2.3 | 2.5 | 2.3 | 2.3 | 2.8 | 3.3 | | 2.8 | 3.3 | 3.3 |
| Lost Time Adjust (s) | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 |
| Total Lost Time (s) | 7.1 | 6.9 | 6.9 | 7.1 | 6.9 | 6.9 | 6.5 | 7.0 | | 6.5 | 7.0 | 7.0 |
| Lead/Lag | | | | | | | Lag | Lead | | Lag | Lead | Lead |
| Lead-Lag Optimize? | | | | | | | Yes | Yes | | Yes | Yes | Yes |
| Recall Mode | None | C-Max | C-Max | None | C-Max | C-Max | None | None | | None | None | None |
| Act Effct Green (s) | 17.9 | 48.9 | 48.9 | 6.8 | 27.1 | 27.1 | 24.6 | 20.2 | | 27.4 | 22.9 | 22.9 |
| Actuated g/C Ratio | 0.15 | 0.41 | 0.41 | 0.06 | 0.23 | 0.23 | 0.20 | 0.17 | | 0.23 | 0.19 | 0.19 |
| v/c Ratio | 0.88 | 1.23 | 0.31 | 0.16 | 2.50 | 0.25 | 0.57 | 0.74 | | 0.33 | 0.28 | 0.89 |
| Control Delay | 70.2 | 140.4 | 8.9 | 58.8 | 701.7 | 3.4 | 49.3 | 59.7 | | 43.5 | 40.1 | 31.1 |
| Queue Delay | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 |
| Total Delay | 70.2 | 140.4 | 8.9 | 58.8 | 701.7 | 3.4 | 49.3 | 59.7 | | 43.5 | 40.1 | 31.1 |
| LOS | E | F | A | E | F | A | D | E | | D | D | C |
| Approach Delay | | 115.5 | | | 658.0 | | | 53.0 | | | 34.4 | |
| Approach LOS | | F | | | F | | | D | | | C | |
| Queue Length 50th (m) | 50.2 | ~240.4 | 6.5 | 2.3 | ~386.4 | 0.0 | 40.4 | 45.1 | | 24.6 | 18.4 | 37.0 |
| Queue Length 95th (m) | #79.9 | #343.9 | 27.9 | 7.8 | #428.7 | 6.0 | #92.8 | 66.2 | | 45.3 | 27.4 | 70.1 |
| Internal Link Dist (m) | | 441.7 | | | 233.3 | | | 132.8 | | | 356.4 | |
| Turn Bay Length (m) | 127.0 | | 96.5 | 95.0 | | 90.0 | 90.0 | | | 140.0 | | 125.0 |
| Base Capacity (vph) | 478 | 1351 | 678 | 158 | 749 | 458 | 646 | 567 | | 378 | 568 | 732 |
| Starvation Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | 0 |
| Spillback Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | 0 |
| Storage Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | 0 |
| Reduced v/c Ratio | 0.88 | 1.23 | 0.31 | 0.06 | 2.50 | 0.25 | 0.57 | 0.37 | | 0.33 | 0.16 | 0.69 |

| Intersection Summary | |
|---|--|
| Cycle Length: 120 | |
| Actuated Cycle Length: 120 | |
| Offset: 0 (0%), Referenced to phase 2:EBT and 6:WBT, Start of Green | |
| Natural Cycle: 145 | |
| Control Type: Actuated-Coordinated | |

Lanes, Volumes, Timings
2: Citigate & Fallowfield & Strandherd

2038 Future BackgroundPM Peak Hour
4497 O'Keefe Court

Maximum v/c Ratio: 2.50

Intersection Signal Delay: 292.9

Intersection LOS: F

Intersection Capacity Utilization 115.8%

ICU Level of Service H

Analysis Period (min) 15


~ Volume exceeds capacity, queue is theoretically infinite.

Queue shown is maximum after two cycles.

95th percentile volume exceeds capacity, queue may be longer.

Queue shown is maximum after two cycles.

Splits and Phases: 2: Citigate & Fallowfield & Strandherd



HCM 2010 TWSC
3: Cobble Hill/O'Keefe & Fallowfield

2038 Future BackgroundPM Peak Hour
4497 O'Keefe Court

Intersection

Int Delay, s/veh 7.4

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|--------------------------|-------|------|------|------|------|------|------|------|------|------|------|------|
| Lane Configurations | ↰ | ↑ | ↱ | ↰ | ↑ | ↱ | ↰ | ↱ | ↱ | ↰ | ↱ | ↱ |
| Traffic Vol, veh/h | 77 | 594 | 66 | 52 | 706 | 22 | 23 | 3 | 44 | 48 | 5 | 18 |
| Future Vol, veh/h | 77 | 594 | 66 | 52 | 706 | 22 | 23 | 3 | 44 | 48 | 5 | 18 |
| Conflicting Peds, #/hr | 0 | 0 | 1 | 1 | 0 | 0 | 0 | 0 | 2 | 2 | 0 | 0 |
| Sign Control | Free | Free | Free | Free | Free | Free | Stop | Stop | Stop | Stop | Stop | Stop |
| RT Channelized | - | - | None | - | - | None | - | - | None | - | - | None |
| Storage Length | 147.5 | - | 0 | - | - | 30.5 | - | - | - | 42.5 | - | - |
| Veh in Median Storage, # | - | 0 | - | - | 0 | - | - | 0 | - | - | 0 | - |
| Grade, % | - | 0 | - | - | 0 | - | - | 0 | - | - | 0 | - |
| Peak Hour Factor | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| Heavy Vehicles, % | 11 | 3 | 2 | 2 | 5 | 2 | 24 | 2 | 2 | 2 | 2 | 13 |
| Mvmt Flow | 77 | 594 | 66 | 52 | 706 | 22 | 23 | 3 | 44 | 48 | 5 | 18 |

| Major/Minor | Major1 | Major2 | Minor1 | Minor2 |
|----------------------|--------|--------|--------|--------|
| Conflicting Flow All | 728 | 0 | 0 | 661 |
| Stage 1 | - | - | - | - |
| Stage 2 | - | - | - | - |
| Critical Hdwy | 4.21 | - | - | 4.12 |
| Critical Hdwy Stg 1 | - | - | - | - |
| Critical Hdwy Stg 2 | - | - | - | - |
| Follow-up Hdwy | 2.299 | - | - | 2.218 |
| Pot Cap-1 Maneuver | 836 | - | - | 927 |
| Stage 1 | - | - | - | - |
| Stage 2 | - | - | - | - |
| Platoon blocked, % | - | - | - | - |
| Mov Cap-1 Maneuver | 836 | - | - | 926 |
| Mov Cap-2 Maneuver | - | - | - | - |
| Stage 1 | - | - | - | - |
| Stage 2 | - | - | - | - |

| Approach | EB | WB | NB | SB |
|----------------------|----|-----|------|-------|
| HCM Control Delay, s | 1 | 0.6 | 50.5 | 105.5 |
| HCM LOS | | | F | F |

| Minor Lane/Major Mvmt | NBLn1 | EBL | EBT | EBR | WBL | WBT | WBR | SBLn1 | SBLn2 |
|-----------------------|-------|-------|-----|-----|-------|-----|-----|-------|-------|
| Capacity (veh/h) | 146 | 836 | - | - | 926 | - | - | 66 | 229 |
| HCM Lane V/C Ratio | 0.479 | 0.092 | - | - | 0.056 | - | - | 0.727 | 0.1 |
| HCM Control Delay (s) | 50.5 | 9.7 | - | - | 9.1 | - | - | 145.2 | 22.5 |
| HCM Lane LOS | F | A | - | - | A | - | - | F | C |
| HCM 95th %tile Q(veh) | 2.2 | 0.3 | - | - | 0.2 | - | - | 3.3 | 0.3 |

Lanes, Volumes, Timings
4: Cedarview & Fallowfield

2038 Future BackgroundPM Peak Hour
4497 O'Keefe Court


| Lane Group | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|---|-------|-------|-------|-------|--------|-------|-------|-------|-------|-------|--------|-----|
| Lane Configurations | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ |
| Traffic Volume (vph) | 25 | 538 | 30 | 148 | 756 | 83 | 21 | 185 | 131 | 287 | 597 | 46 |
| Future Volume (vph) | 25 | 538 | 30 | 148 | 756 | 83 | 21 | 185 | 131 | 287 | 597 | 46 |
| Satd. Flow (prot) | 1658 | 1745 | 1483 | 1642 | 1728 | 1483 | 1537 | 1728 | 1469 | 1658 | 1724 | 0 |
| Flt Permitted | 0.150 | | | 0.330 | | | 0.132 | | | 0.641 | | |
| Satd. Flow (perm) | 262 | 1745 | 1483 | 570 | 1728 | 1451 | 214 | 1728 | 1469 | 1119 | 1724 | 0 |
| Satd. Flow (RTOR) | | | 49 | | | 74 | | | 131 | | 5 | |
| Lane Group Flow (vph) | 25 | 538 | 30 | 148 | 756 | 83 | 21 | 185 | 131 | 287 | 643 | 0 |
| Turn Type | Perm | NA | Perm | Perm | NA | Perm | Perm | NA | Perm | Perm | NA | |
| Protected Phases | | 2 | | | 6 | | | 4 | | | 8 | |
| Permitted Phases | 2 | | 2 | 6 | | 6 | 4 | | 4 | 8 | | |
| Detector Phase | 2 | 2 | 2 | 6 | 6 | 6 | 4 | 4 | 4 | 8 | 8 | |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | |
| Minimum Split (s) | 48.0 | 48.0 | 48.0 | 48.0 | 48.0 | 48.0 | 37.0 | 37.0 | 37.0 | 37.0 | 37.0 | |
| Total Split (s) | 48.0 | 48.0 | 48.0 | 48.0 | 48.0 | 48.0 | 37.0 | 37.0 | 37.0 | 37.0 | 37.0 | |
| Total Split (%) | 56.5% | 56.5% | 56.5% | 56.5% | 56.5% | 56.5% | 43.5% | 43.5% | 43.5% | 43.5% | 43.5% | |
| Yellow Time (s) | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | |
| All-Red Time (s) | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.8 | 3.8 | 3.8 | 3.8 | 3.8 | |
| Lost Time Adjust (s) | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | |
| Total Lost Time (s) | 6.7 | 6.7 | 6.7 | 6.7 | 6.7 | 6.7 | 6.8 | 6.8 | 6.8 | 6.8 | 6.8 | |
| Lead/Lag | | | | | | | | | | | | |
| Lead-Lag Optimize? | | | | | | | | | | | | |
| Recall Mode | C-Max | C-Max | C-Max | C-Max | C-Max | C-Max | None | None | None | None | None | |
| Act Effct Green (s) | 41.3 | 41.3 | 41.3 | 41.3 | 41.3 | 41.3 | 30.2 | 30.2 | 30.2 | 30.2 | 30.2 | |
| Actuated g/C Ratio | 0.49 | 0.49 | 0.49 | 0.49 | 0.49 | 0.49 | 0.36 | 0.36 | 0.36 | 0.36 | 0.36 | |
| v/c Ratio | 0.20 | 0.64 | 0.04 | 0.54 | 0.90 | 0.11 | 0.28 | 0.30 | 0.22 | 0.72 | 1.05 | |
| Control Delay | 17.4 | 20.5 | 2.0 | 24.1 | 36.3 | 4.1 | 31.2 | 21.5 | 4.7 | 36.2 | 77.7 | |
| Queue Delay | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | |
| Total Delay | 17.4 | 20.5 | 2.0 | 24.1 | 36.3 | 4.1 | 31.2 | 21.5 | 4.7 | 36.2 | 77.7 | |
| LOS | B | C | A | C | D | A | C | C | A | D | E | |
| Approach Delay | | 19.4 | | | 31.8 | | | 15.6 | | | 64.9 | |
| Approach LOS | | B | | | C | | | B | | | E | |
| Queue Length 50th (m) | 2.2 | 62.0 | 0.0 | 15.9 | 107.0 | 0.7 | 2.4 | 21.3 | 0.0 | 39.8 | ~114.4 | |
| Queue Length 95th (m) | 7.8 | 94.7 | 2.5 | 35.5 | #179.7 | 7.6 | 9.2 | 37.1 | 10.8 | #76.1 | #177.4 | |
| Internal Link Dist (m) | | 561.2 | | | 452.7 | | | 444.3 | | | 482.1 | |
| Turn Bay Length (m) | 60.0 | | 55.0 | 60.0 | | 55.0 | 180.0 | | 80.0 | 45.5 | | |
| Base Capacity (vph) | 127 | 847 | 745 | 276 | 839 | 743 | 76 | 613 | 606 | 397 | 615 | |
| Starvation Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Spillback Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Storage Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Reduced v/c Ratio | 0.20 | 0.64 | 0.04 | 0.54 | 0.90 | 0.11 | 0.28 | 0.30 | 0.22 | 0.72 | 1.05 | |
| Intersection Summary | | | | | | | | | | | | |
| Cycle Length: 85 | | | | | | | | | | | | |
| Actuated Cycle Length: 85 | | | | | | | | | | | | |
| Offset: 40 (47%), Referenced to phase 2:EBTL and 6:WBTL, Start of Green | | | | | | | | | | | | |
| Natural Cycle: 85 | | | | | | | | | | | | |
| Control Type: Actuated-Coordinated | | | | | | | | | | | | |

Lanes, Volumes, Timings
4: Cedarview & Fallowfield

2038 Future BackgroundPM Peak Hour
4497 O'Keefe Court

| | |
|---|------------------------|
| Maximum v/c Ratio: 1.05 | |
| Intersection Signal Delay: 38.1 | Intersection LOS: D |
| Intersection Capacity Utilization 117.3% | ICU Level of Service H |
| Analysis Period (min) 15 | |
| ~ Volume exceeds capacity, queue is theoretically infinite. | |
| Queue shown is maximum after two cycles. | |
| # 95th percentile volume exceeds capacity, queue may be longer. | |
| Queue shown is maximum after two cycles. | |

Splits and Phases: 4: Cedarview & Fallowfield




Appendix J



Turn-Lane Warrants

Cedarview Road at Onassa Circle



Existing – Northbound Left



FB2038 – Northbound Left



FT2038 – Northbound Left



Appendix K

Synchro Intersection Worksheets –Future Background 2038 Mitigation Measures

Lanes, Volumes, Timings
3: Cobble Hill/O'Keefe & Fallowfield

2028 Future BackgroundAM Peak Hour
4497 O'Keefe Court

| Lane Group | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|-------|-------|-------|-------|-------|-------|-------|-------|------|-------|-------|-----|
| Lane Configurations | ↰ | ↑ | ↱ | ↰ | ↑ | ↱ | ↰ | ↱ | ↰ | ↱ | ↰ | ↱ |
| Traffic Volume (vph) | 92 | 597 | 11 | 15 | 593 | 11 | 34 | 2 | 52 | 32 | 4 | 18 |
| Future Volume (vph) | 92 | 597 | 11 | 15 | 593 | 11 | 34 | 2 | 52 | 32 | 4 | 18 |
| Satd. Flow (prot) | 1523 | 1712 | 1388 | 1580 | 1695 | 1327 | 0 | 1538 | 0 | 1271 | 1372 | 0 |
| Flt Permitted | 0.386 | | | 0.383 | | | | 0.864 | | 0.700 | | |
| Satd. Flow (perm) | 619 | 1712 | 1388 | 637 | 1695 | 1327 | 0 | 1355 | 0 | 935 | 1372 | 0 |
| Satd. Flow (RTOR) | | | 35 | | | 35 | | 52 | | | 18 | |
| Lane Group Flow (vph) | 92 | 597 | 11 | 15 | 593 | 11 | 0 | 88 | 0 | 32 | 22 | 0 |
| Turn Type | Perm | NA | Perm | Perm | NA | Perm | Perm | NA | Perm | NA | NA | |
| Protected Phases | 2 | | | | 6 | | | 8 | | | 4 | |
| Permitted Phases | 2 | | 2 | 6 | | 6 | 8 | | | 4 | | |
| Detector Phase | 2 | 2 | 2 | 6 | 6 | 6 | 8 | 8 | | 4 | 4 | |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | | 10.0 | 10.0 | |
| Minimum Split (s) | 38.2 | 38.2 | 38.2 | 38.2 | 38.2 | 38.2 | 30.9 | 30.9 | | 30.9 | 30.9 | |
| Total Split (s) | 59.0 | 59.0 | 59.0 | 59.0 | 59.0 | 59.0 | 31.0 | 31.0 | | 31.0 | 31.0 | |
| Total Split (%) | 65.6% | 65.6% | 65.6% | 65.6% | 65.6% | 65.6% | 34.4% | 34.4% | | 34.4% | 34.4% | |
| Yellow Time (s) | 3.3 | 3.3 | 3.3 | 3.3 | 3.3 | 3.3 | 3.7 | 3.7 | | 3.7 | 3.7 | |
| All-Red Time (s) | 2.9 | 2.9 | 2.9 | 2.9 | 2.9 | 2.9 | 2.2 | 2.2 | | 2.2 | 2.2 | |
| Lost Time Adjust (s) | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | |
| Total Lost Time (s) | 6.2 | 6.2 | 6.2 | 6.2 | 6.2 | 6.2 | | 5.9 | | 5.9 | 5.9 | |
| Lead/Lag | | | | | | | | | | | | |
| Lead-Lag Optimize? | | | | | | | | | | | | |
| Recall Mode | None | None | None | None | None | None | None | None | | None | None | |
| Act Effct Green (s) | 28.6 | 28.6 | 28.6 | 28.6 | 28.6 | 28.6 | | 15.1 | | 15.1 | 15.1 | |
| Actuated g/C Ratio | 0.70 | 0.70 | 0.70 | 0.70 | 0.70 | 0.70 | | 0.37 | | 0.37 | 0.37 | |
| v/c Ratio | 0.21 | 0.50 | 0.01 | 0.03 | 0.50 | 0.01 | | 0.17 | | 0.09 | 0.04 | |
| Control Delay | 9.4 | 10.2 | 0.5 | 7.8 | 10.3 | 0.5 | | 9.9 | | 17.0 | 9.9 | |
| Queue Delay | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | 0.0 | | 0.0 | 0.0 | |
| Total Delay | 9.4 | 10.2 | 0.5 | 7.8 | 10.3 | 0.5 | | 9.9 | | 17.0 | 9.9 | |
| LOS | A | B | A | A | B | A | | A | | B | A | |
| Approach Delay | | 10.0 | | | 10.1 | | | 9.9 | | | 14.1 | |
| Approach LOS | | A | | | B | | | A | | | B | |
| Queue Length 50th (m) | 3.7 | 31.2 | 0.0 | 0.5 | 31.0 | 0.0 | | 2.0 | | 1.8 | 0.3 | |
| Queue Length 95th (m) | 16.5 | 94.4 | 0.5 | 3.7 | 94.5 | 0.5 | | 13.5 | | 9.6 | 5.2 | |
| Internal Link Dist (m) | | 356.4 | | | 561.2 | | | 133.0 | | | 776.8 | |
| Turn Bay Length (m) | 147.5 | | | 60.0 | | 30.5 | | | | 42.5 | | |
| Base Capacity (vph) | 578 | 1599 | 1298 | 595 | 1583 | 1241 | | 959 | | 650 | 960 | |
| Starvation Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | | 0 | | 0 | 0 | |
| Spillback Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | | 0 | | 0 | 0 | |
| Storage Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | | 0 | | 0 | 0 | |
| Reduced v/c Ratio | 0.16 | 0.37 | 0.01 | 0.03 | 0.37 | 0.01 | | 0.09 | | 0.05 | 0.02 | |

Intersection Summary


Cycle Length: 90
Actuated Cycle Length: 40.8
Natural Cycle: 70
Control Type: Actuated-Uncoordinated
Maximum v/c Ratio: 0.50

Lanes, Volumes, Timings
3: Cobble Hill/O'Keefe & Fallowfield

2028 Future BackgroundAM Peak Hour
4497 O'Keefe Court

| | |
|---|------------------------|
| Intersection Signal Delay: 10.2 | Intersection LOS: B |
| Intersection Capacity Utilization 69.2% | ICU Level of Service C |
| Analysis Period (min) 15 | |

Splits and Phases: 3: Cobble Hill/O'Keefe & Fallowfield



Lanes, Volumes, Timings
3: Cobble Hill/O'Keefe & Fallowfield

2038 Future BackgroundPM Peak Hour
4497 O'Keefe Court

| Lane Group | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|-------|-------|-------|-------|-------|-------|-------|-------|------|-------|-------|-----|
| Lane Configurations | ↰ | ↑ | ↱ | ↰ | ↑ | ↱ | ↰ | ↱ | ↰ | ↱ | ↰ | ↱ |
| Traffic Volume (vph) | 77 | 594 | 66 | 52 | 706 | 22 | 23 | 3 | 44 | 48 | 5 | 18 |
| Future Volume (vph) | 77 | 594 | 66 | 52 | 706 | 22 | 23 | 3 | 44 | 48 | 5 | 18 |
| Satd. Flow (prot) | 1523 | 1728 | 1483 | 1658 | 1695 | 1483 | 0 | 1444 | 0 | 1658 | 1421 | 0 |
| Flt Permitted | 0.315 | | | 0.395 | | | | 0.881 | | 0.711 | | |
| Satd. Flow (perm) | 505 | 1728 | 1450 | 689 | 1695 | 1483 | 0 | 1293 | 0 | 1236 | 1421 | 0 |
| Satd. Flow (RTOR) | | | 66 | | | 26 | | 44 | | | 18 | |
| Lane Group Flow (vph) | 77 | 594 | 66 | 52 | 706 | 22 | 0 | 70 | 0 | 48 | 23 | 0 |
| Turn Type | Perm | NA | Perm | Perm | NA | Perm | Perm | NA | Perm | NA | NA | |
| Protected Phases | 2 | | | | 6 | | | 8 | | | 4 | |
| Permitted Phases | 2 | | 2 | 6 | | 6 | 8 | | | 4 | | |
| Detector Phase | 2 | 2 | 2 | 6 | 6 | 6 | 8 | 8 | | 4 | 4 | |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | | 10.0 | 10.0 | |
| Minimum Split (s) | 38.2 | 38.2 | 38.2 | 60.5 | 60.5 | 60.5 | 30.9 | 30.9 | | 30.9 | 30.9 | |
| Total Split (s) | 88.0 | 88.0 | 88.0 | 88.0 | 88.0 | 88.0 | 32.0 | 32.0 | | 32.0 | 32.0 | |
| Total Split (%) | 73.3% | 73.3% | 73.3% | 73.3% | 73.3% | 73.3% | 26.7% | 26.7% | | 26.7% | 26.7% | |
| Yellow Time (s) | 3.3 | 3.3 | 3.3 | 3.3 | 3.3 | 3.3 | 3.7 | 3.7 | | 3.7 | 3.7 | |
| All-Red Time (s) | 2.9 | 2.9 | 2.9 | 2.9 | 2.9 | 2.9 | 2.2 | 2.2 | | 2.2 | 2.2 | |
| Lost Time Adjust (s) | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | | | 0.0 | 0.0 | |
| Total Lost Time (s) | 6.2 | 6.2 | 6.2 | 6.2 | 6.2 | 6.2 | | 5.9 | | 5.9 | 5.9 | |
| Lead/Lag | | | | | | | | | | | | |
| Lead-Lag Optimize? | | | | | | | | | | | | |
| Recall Mode | None | None | None | None | None | None | None | None | | None | None | |
| Act Effct Green (s) | 33.3 | 33.3 | 33.3 | 33.3 | 33.3 | 33.3 | | 15.4 | | 15.4 | 15.4 | |
| Actuated g/C Ratio | 0.73 | 0.73 | 0.73 | 0.73 | 0.73 | 0.73 | | 0.34 | | 0.34 | 0.34 | |
| v/c Ratio | 0.21 | 0.47 | 0.06 | 0.10 | 0.57 | 0.02 | | 0.15 | | 0.11 | 0.05 | |
| Control Delay | 8.9 | 8.9 | 2.3 | 7.2 | 10.7 | 2.9 | | 11.6 | | 19.9 | 12.1 | |
| Queue Delay | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | 0.0 | | 0.0 | 0.0 | |
| Total Delay | 8.9 | 8.9 | 2.3 | 7.2 | 10.7 | 2.9 | | 11.6 | | 19.9 | 12.1 | |
| LOS | A | A | A | A | A | A | | B | | B | B | |
| Approach Delay | | 8.3 | | | 10.2 | | | 11.6 | | | 17.4 | |
| Approach LOS | | A | | | B | | | B | | | B | |
| Queue Length 50th (m) | 3.1 | 30.8 | 0.0 | 1.9 | 41.2 | 0.0 | | 1.7 | | 3.2 | 0.3 | |
| Queue Length 95th (m) | 14.3 | 90.2 | 4.8 | 9.1 | 122.4 | 2.6 | | 12.9 | | 14.5 | 6.1 | |
| Internal Link Dist (m) | | 356.4 | | | 561.2 | | | 133.0 | | | 776.8 | |
| Turn Bay Length (m) | 147.5 | | | 60.0 | | 30.5 | | | | 42.5 | | |
| Base Capacity (vph) | 497 | 1701 | 1429 | 678 | 1669 | 1461 | | 887 | | 834 | 965 | |
| Starvation Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | | 0 | | 0 | 0 | |
| Spillback Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | | 0 | | 0 | 0 | |
| Storage Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | | 0 | | 0 | 0 | |
| Reduced v/c Ratio | 0.15 | 0.35 | 0.05 | 0.08 | 0.42 | 0.02 | | 0.08 | | 0.06 | 0.02 | |

Intersection Summary

Cycle Length: 120
Actuated Cycle Length: 45.5
Natural Cycle: 95
Control Type: Actuated-Uncoordinated
Maximum v/c Ratio: 0.57


Lanes, Volumes, Timings
3: Cobble Hill/O'Keefe & Fallowfield

2038 Future BackgroundPM Peak Hour
4497 O'Keefe Court

Intersection Signal Delay: 9.7
Intersection Capacity Utilization 74.6%
Analysis Period (min) 15

Intersection LOS: A
ICU Level of Service D

Splits and Phases: 3: Cobble Hill/O'Keefe & Fallowfield



Lanes, Volumes, Timings
4: Cedarview & Fallowfield

2038 Future BackgroundPM Peak Hour
4497 O'Keefe Court

| | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|-------|-------|-------|-------|--------|-------|-------|-------|-------|-------|--------|-----|
| Lane Group | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
| Lane Configurations | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ |
| Traffic Volume (vph) | 25 | 538 | 30 | 148 | 756 | 83 | 21 | 185 | 131 | 287 | 597 | 46 |
| Future Volume (vph) | 25 | 538 | 30 | 148 | 756 | 83 | 21 | 185 | 131 | 287 | 597 | 46 |
| Satd. Flow (prot) | 1658 | 1745 | 1483 | 1642 | 1728 | 1483 | 1537 | 1728 | 1469 | 1658 | 1724 | 0 |
| Flt Permitted | 0.129 | | | 0.314 | | | 0.123 | | | 0.641 | | |
| Satd. Flow (perm) | 225 | 1745 | 1483 | 543 | 1728 | 1451 | 199 | 1728 | 1469 | 1119 | 1724 | 0 |
| Satd. Flow (RTOR) | | | 46 | | | 68 | | | 131 | | 5 | |
| Lane Group Flow (vph) | 25 | 538 | 30 | 148 | 756 | 83 | 21 | 185 | 131 | 287 | 643 | 0 |
| Turn Type | Perm | NA | Perm | Perm | NA | Perm | Perm | NA | Perm | Perm | NA | |
| Protected Phases | | 2 | | | 6 | | | 4 | | | 8 | |
| Permitted Phases | 2 | | 2 | 6 | | 6 | 4 | | 4 | 8 | | |
| Detector Phase | 2 | 2 | 2 | 6 | 6 | 6 | 4 | 4 | 4 | 8 | 8 | |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | |
| Minimum Split (s) | 48.0 | 48.0 | 48.0 | 48.0 | 48.0 | 48.0 | 37.0 | 37.0 | 37.0 | 37.0 | 37.0 | |
| Total Split (s) | 49.0 | 49.0 | 49.0 | 49.0 | 49.0 | 49.0 | 41.0 | 41.0 | 41.0 | 41.0 | 41.0 | |
| Total Split (%) | 54.4% | 54.4% | 54.4% | 54.4% | 54.4% | 54.4% | 45.6% | 45.6% | 45.6% | 45.6% | 45.6% | |
| Yellow Time (s) | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | |
| All-Red Time (s) | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.8 | 3.8 | 3.8 | 3.8 | 3.8 | |
| Lost Time Adjust (s) | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | |
| Total Lost Time (s) | 6.7 | 6.7 | 6.7 | 6.7 | 6.7 | 6.7 | 6.8 | 6.8 | 6.8 | 6.8 | 6.8 | |
| Lead/Lag | | | | | | | | | | | | |
| Lead-Lag Optimize? | | | | | | | | | | | | |
| Recall Mode | C-Max | C-Max | C-Max | C-Max | C-Max | C-Max | None | None | None | None | None | |
| Act Effct Green (s) | 42.3 | 42.3 | 42.3 | 42.3 | 42.3 | 42.3 | 34.2 | 34.2 | 34.2 | 34.2 | 34.2 | |
| Actuated g/C Ratio | 0.47 | 0.47 | 0.47 | 0.47 | 0.47 | 0.47 | 0.38 | 0.38 | 0.38 | 0.38 | 0.38 | |
| v/c Ratio | 0.24 | 0.66 | 0.04 | 0.58 | 0.93 | 0.12 | 0.28 | 0.28 | 0.21 | 0.68 | 0.98 | |
| Control Delay | 21.5 | 23.0 | 2.5 | 28.6 | 42.8 | 5.1 | 31.3 | 20.9 | 4.4 | 32.8 | 59.1 | |
| Queue Delay | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | |
| Total Delay | 21.5 | 23.0 | 2.5 | 28.6 | 42.8 | 5.1 | 31.3 | 20.9 | 4.4 | 32.8 | 59.1 | |
| LOS | C | C | A | C | D | A | C | C | A | C | E | |
| Approach Delay | | 21.9 | | | 37.5 | | | 15.1 | | | 50.9 | |
| Approach LOS | | C | | | D | | | B | | | D | |
| Queue Length 50th (m) | 2.5 | 68.6 | 0.0 | 17.9 | 118.4 | 1.3 | 2.5 | 21.8 | 0.0 | 40.6 | 107.0 | |
| Queue Length 95th (m) | 8.8 | 103.2 | 2.9 | 40.2 | #193.3 | 8.6 | 9.5 | 37.3 | 10.6 | 69.9 | #177.6 | |
| Internal Link Dist (m) | | 561.2 | | | 452.7 | | | 444.3 | | | 482.1 | |
| Turn Bay Length (m) | 60.0 | | 55.0 | 60.0 | | 55.0 | 180.0 | | 80.0 | 45.5 | | |
| Base Capacity (vph) | 105 | 820 | 721 | 255 | 812 | 718 | 75 | 656 | 639 | 425 | 658 | |
| Starvation Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Spillback Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Storage Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Reduced v/c Ratio | 0.24 | 0.66 | 0.04 | 0.58 | 0.93 | 0.12 | 0.28 | 0.28 | 0.21 | 0.68 | 0.98 | |

Intersection Summary

Cycle Length: 90

Actuated Cycle Length: 90

Offset: 0 (0%), Referenced to phase 2:EBTL and 6:WBTL, Start of Green

Natural Cycle: 85

Control Type: Actuated-Coordinated

08-29-2023
MC

CGH Transportation
Page 3

Lanes, Volumes, Timings
4: Cedarview & Fallowfield

2038 Future BackgroundPM Peak Hour
4497 O'Keefe Court

Maximum v/c Ratio: 0.98

Intersection Signal Delay: 36.0

Intersection LOS: D

Intersection Capacity Utilization 117.3%


ICU Level of Service H

Analysis Period (min) 15

95th percentile volume exceeds capacity, queue may be longer.

Queue shown is maximum after two cycles.

Splits and Phases: 4: Cedarview & Fallowfield



08-29-2023
MC

CGH Transportation
Page 4

Appendix L

Synchro Intersection Worksheets – 2038 Future Total Conditions

HCM 2010 TWSC
1: Cedarview & Onassa

2038 Future TotalAM Peak Hour
4497 O'Keefe Court

| Intersection | | | | | | |
|--------------------------|--------|--------|--------|------|------|------|
| Int Delay, s/veh | 2.2 | | | | | |
| Movement | EBL | EBR | NBL | NBT | SBT | SBR |
| Lane Configurations | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ |
| Traffic Vol, veh/h | 59 | 38 | 24 | 383 | 430 | 34 |
| Future Vol, veh/h | 59 | 38 | 24 | 383 | 430 | 34 |
| Conflicting Peds, #/hr | 0 | 0 | 26 | 0 | 0 | 26 |
| Sign Control | Stop | Stop | Free | Free | Free | Free |
| RT Channelized | - | None | - | None | - | None |
| Storage Length | 0 | - | - | - | - | - |
| Veh in Median Storage, # | 0 | - | - | 0 | 0 | - |
| Grade, % | 0 | - | - | 0 | 0 | - |
| Peak Hour Factor | 100 | 100 | 100 | 100 | 100 | 100 |
| Heavy Vehicles, % | 14 | 2 | 11 | 2 | 2 | 17 |
| Mvmt Flow | 59 | 38 | 24 | 383 | 430 | 34 |
| Major/Minor | Minor2 | Major1 | Major2 | | | |
| Conflicting Flow All | 904 | 473 | 490 | 0 | - | 0 |
| Stage 1 | 473 | - | - | - | - | - |
| Stage 2 | 431 | - | - | - | - | - |
| Critical Hdwy | 6.54 | 6.22 | 4.21 | - | - | - |
| Critical Hdwy Stg 1 | 5.54 | - | - | - | - | - |
| Critical Hdwy Stg 2 | 5.54 | - | - | - | - | - |
| Follow-up Hdwy | 3.626 | 3.318 | 2.299 | - | - | - |
| Pot Cap-1 Maneuver | 293 | 591 | 1028 | - | - | - |
| Stage 1 | 603 | - | - | - | - | - |
| Stage 2 | 631 | - | - | - | - | - |
| Platoon blocked, % | - | - | - | - | - | - |
| Mov Cap-1 Maneuver | 273 | 579 | 1007 | - | - | - |
| Mov Cap-2 Maneuver | 273 | - | - | - | - | - |
| Stage 1 | 573 | - | - | - | - | - |
| Stage 2 | 618 | - | - | - | - | - |
| Approach | EB | NB | SB | | | |
| HCM Control Delay, s | 19.5 | 0.5 | 0 | | | |
| HCM LOS | C | | | | | |
| Minor Lane/Major Mvmt | NBL | NBT | EBLn1 | SBT | SBR | |
| Capacity (veh/h) | 1007 | - | 344 | - | - | |
| HCM Lane V/C Ratio | 0.024 | - | 0.282 | - | - | |
| HCM Control Delay (s) | 8.7 | 0 | 19.5 | - | - | |
| HCM Lane LOS | A | A | C | - | - | |
| HCM 95th %tile Q(veh) | 0.1 | - | 1.1 | - | - | |

Lanes, Volumes, Timings
2: Citigate & Fallowfield & Strandherd

2038 Future TotalAM Peak Hour
4497 O'Keefe Court

| Lane Group | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBR |
|--|-------|--------|-------|-------|--------|-------|-------|-------|-----|-------|-------|
| Lane Configurations | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ |
| Traffic Volume (vph) | 491 | 1201 | 249 | 38 | 1775 | 93 | 66 | 45 | 10 | 80 | 146 |
| Future Volume (vph) | 491 | 1201 | 249 | 38 | 1775 | 93 | 66 | 45 | 10 | 80 | 146 |
| Satd. Flow (prot) | 3066 | 3103 | 1401 | 1353 | 3221 | 1483 | 2929 | 1405 | 0 | 1658 | 1664 |
| Fit Permitted | 0.950 | | | 0.950 | | | 0.950 | | | 0.950 | |
| Satd. Flow (perm) | 3031 | 3103 | 1323 | 1343 | 3221 | 1347 | 2874 | 1405 | 0 | 1623 | 1664 |
| Satd. Flow (RTOR) | | | 240 | | | 225 | | 10 | | | |
| Lane Group Flow (vph) | 491 | 1201 | 249 | 38 | 1775 | 93 | 66 | 55 | 0 | 80 | 146 |
| Turn Type | Prot | NA | Perm | Prot | NA | Perm | Prot | NA | | Prot | NA |
| Protected Phases | 13 | 2 | 2 | 9 | 6 | 6 | 7 | 4 | | 3 | 8 |
| Permitted Phases | | | 2 | | | 6 | | | | | 8 |
| Detector Phase | 13 | 2 | 2 | 9 | 6 | 6 | 7 | 4 | | 3 | 8 |
| Switch Phase | | | | | | | | | | | |
| Minimum Initial (s) | 5.0 | 10.0 | 10.0 | 5.0 | 10.0 | 10.0 | 5.0 | 10.0 | | 5.0 | 10.0 |
| Minimum Split (s) | 12.1 | 29.9 | 29.9 | 12.1 | 29.9 | 29.9 | 11.5 | 48.0 | | 11.5 | 48.0 |
| Total Split (s) | 28.0 | 46.0 | 46.0 | 13.0 | 31.0 | 31.0 | 13.0 | 48.0 | | 13.0 | 48.0 |
| Total Split (%) | 23.3% | 38.3% | 38.3% | 10.8% | 25.8% | 25.8% | 10.8% | 40.0% | | 10.8% | 40.0% |
| Yellow Time (s) | 4.6 | 4.6 | 4.6 | 4.6 | 4.6 | 4.6 | 3.7 | 3.7 | | 3.7 | 3.7 |
| All-Red Time (s) | 2.5 | 2.3 | 2.3 | 2.5 | 2.3 | 2.3 | 2.8 | 3.3 | | 2.8 | 3.3 |
| Lost Time Adjust (s) | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 |
| Total Lost Time (s) | 7.1 | 6.9 | 6.9 | 7.1 | 6.9 | 6.9 | 6.5 | 7.0 | | 6.5 | 7.0 |
| Lead/Lag | | | | | | | Lag | Lead | | Lag | Lead |
| Lead-Lag Optimize? | | | | | | | Yes | Yes | | Yes | Yes |
| Recall Mode | None | C-Max | C-Max | None | C-Max | C-Max | None | None | | None | None |
| Act Effct Green (s) | 21.3 | 55.4 | 55.4 | 6.2 | 37.7 | 37.7 | 6.7 | 28.6 | | 8.3 | 29.3 |
| Actuated g/C Ratio | 0.18 | 0.46 | 0.46 | 0.05 | 0.31 | 0.31 | 0.06 | 0.24 | | 0.07 | 0.24 |
| v/c Ratio | 0.91 | 0.84 | 0.34 | 0.55 | 1.75 | 0.16 | 0.41 | 0.16 | | 0.70 | 0.36 |
| Control Delay | 69.9 | 39.9 | 5.6 | 84.1 | 370.2 | 0.6 | 62.5 | 26.3 | | 86.5 | 37.0 |
| Queue Delay | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 |
| Total Delay | 69.9 | 39.9 | 5.6 | 84.1 | 370.2 | 0.6 | 62.5 | 26.3 | | 86.5 | 37.0 |
| LOS | E | D | A | F | F | A | E | C | | F | D |
| Approach Delay | | 43.1 | | | 346.4 | | | 46.1 | | | 28.6 |
| Approach LOS | | D | | | F | | | D | | | C |
| Queue Length 50th (m) | 59.2 | ~179.3 | 1.5 | 8.9 | ~374.3 | 0.0 | 7.9 | 7.2 | | 19.1 | 24.7 |
| Queue Length 95th (m) | #89.6 | #220.8 | 20.1 | #25.4 | #416.8 | 0.0 | 15.2 | 16.6 | | #49.0 | 41.2 |
| Internal Link Dist (m) | | 441.7 | | | 233.3 | | | 132.8 | | | 356.4 |
| Turn Bay Length (m) | 127.0 | | 96.5 | 95.0 | | 90.0 | 90.0 | | | 140.0 | 125.0 |
| Base Capacity (vph) | 546 | 1432 | 739 | 70 | 1012 | 578 | 166 | 486 | | 114 | 568 |
| Starvation Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | 0 | 0 |
| Spillback Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | 0 | 0 |
| Storage Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | 0 | 0 |
| Reduced v/c Ratio | 0.90 | 0.84 | 0.34 | 0.54 | 1.75 | 0.16 | 0.40 | 0.11 | | 0.70 | 0.26 |
| Intersection Summary | | | | | | | | | | | |
| Cycle Length: 120 | | | | | | | | | | | |
| Actuated Cycle Length: 120 | | | | | | | | | | | |
| Offset: 101 (84%), Referenced to phase 2:EBT and 6:WBT, Start of Green | | | | | | | | | | | |
| Natural Cycle: 145 | | | | | | | | | | | |
| Control Type: Actuated-Coordinated | | | | | | | | | | | |

Lanes, Volumes, Timings
2: Citigate & Fallowfield & Strandherd

2038 Future TotalAM Peak Hour
4497 O'Keefe Court

Maximum v/c Ratio: 1.75

Intersection Signal Delay: 165.0

Intersection LOS: F

Intersection Capacity Utilization 116.4%

ICU Level of Service H

Analysis Period (min) 15


~ Volume exceeds capacity, queue is theoretically infinite.

Queue shown is maximum after two cycles.

95th percentile volume exceeds capacity, queue may be longer.

Queue shown is maximum after two cycles.

Splits and Phases: 2: Citigate & Fallowfield & Strandherd



HCM 2010 TWSC
3: Cobble Hill/O'Keefe & Fallowfield

2038 Future TotalAM Peak Hour
4497 O'Keefe Court

Intersection

Int Delay, s/veh 45

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|--------------------------|-------|------|------|------|------|------|------|------|------|------|------|------|
| Lane Configurations | ↰ | ↑ | ↱ | ↰ | ↑ | ↱ | ↰ | ↑ | ↱ | ↰ | ↑ | ↱ |
| Traffic Vol, veh/h | 124 | 600 | 11 | 15 | 602 | 50 | 34 | 2 | 52 | 111 | 4 | 84 |
| Future Vol, veh/h | 124 | 600 | 11 | 15 | 602 | 50 | 34 | 2 | 52 | 111 | 4 | 84 |
| Conflicting Peds, #/hr | 26 | 0 | 26 | 26 | 0 | 26 | 26 | 0 | 14 | 14 | 0 | 26 |
| Sign Control | Free | Free | Free | Free | Free | Free | Stop | Stop | Stop | Stop | Stop | Stop |
| RT Channelized | - | - | None | - | - | None | - | - | None | - | - | None |
| Storage Length | 147.5 | - | 0 | - | - | 30.5 | - | - | - | 42.5 | - | - |
| Veh in Median Storage, # | - | 0 | - | - | 0 | - | - | 0 | - | - | 0 | - |
| Grade, % | - | 0 | - | - | 0 | - | - | 0 | - | - | 0 | - |
| Peak Hour Factor | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| Heavy Vehicles, % | 11 | 4 | 9 | 7 | 5 | 14 | 2 | 50 | 2 | 33 | 67 | 2 |
| Mvmt Flow | 124 | 600 | 11 | 15 | 602 | 50 | 34 | 2 | 52 | 111 | 4 | 84 |

| Major/Minor | Major1 | Major2 | Minor1 | Minor2 |
|----------------------|--------|--------|--------|--------|
| Conflicting Flow All | 678 | 0 | 0 | 637 |
| Stage 1 | - | - | - | - |
| Stage 2 | - | - | - | - |
| Critical Hdwy | 4.21 | - | - | 4.17 |
| Critical Hdwy Stg 1 | - | - | - | - |
| Critical Hdwy Stg 2 | - | - | - | - |
| Follow-up Hdwy | 2.299 | - | - | 2.263 |
| Pot Cap-1 Maneuver | 873 | - | - | 923 |
| Stage 1 | - | - | - | - |
| Stage 2 | - | - | - | - |
| Platoon blocked, % | - | - | - | - |
| Mov Cap-1 Maneuver | 855 | - | - | 904 |
| Mov Cap-2 Maneuver | - | - | - | - |
| Stage 1 | - | - | - | - |
| Stage 2 | - | - | - | - |

| Approach | EB | WB | NB | SB |
|----------------------|-----|-----|------|----------|
| HCM Control Delay, s | 1.7 | 0.2 | 96.3 | \$ 332.8 |
| HCM LOS | | | F | F |

| Minor Lane/Major Mvmt | NBLn1 | EBL | EBT | EBR | WBL | WBT | WBR | SBLn1 | SBLn2 |
|-----------------------|-------|-------|-----|-----|-------|-----|-----|----------|-------|
| Capacity (veh/h) | 117 | 855 | - | - | 904 | - | - | 58 | 356 |
| HCM Lane V/C Ratio | 0.752 | 0.145 | - | - | 0.017 | - | - | 1.914 | 0.247 |
| HCM Control Delay (s) | 96.3 | 9.9 | - | - | 9 | - | - | \$ 582.1 | 18.4 |
| HCM Lane LOS | F | A | - | - | A | - | - | F | C |
| HCM 95th %tile Q(veh) | 4.2 | 0.5 | - | - | 0.1 | - | - | 10.6 | 1 |

Notes

~: Volume exceeds capacity \$: Delay exceeds 300s +: Computation Not Defined *: All major volume in platoon

Lanes, Volumes, Timings
4: Cedarview & Fallowfield

2038 Future TotalAM Peak Hour
4497 O'Keefe Court

| | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|-------|--------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-----|
| Lane Group | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
| Lane Configurations | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ |
| Traffic Volume (vph) | 52 | 863 | 11 | 32 | 591 | 191 | 50 | 358 | 278 | 224 | 128 | 23 |
| Future Volume (vph) | 52 | 863 | 11 | 32 | 591 | 191 | 50 | 358 | 278 | 224 | 128 | 23 |
| Satd. Flow (prot) | 1658 | 1712 | 1261 | 1537 | 1728 | 1483 | 1658 | 1745 | 1469 | 1642 | 1647 | 0 |
| Flt Permitted | 0.300 | | | 0.093 | | | 0.661 | | | 0.407 | | |
| Satd. Flow (perm) | 517 | 1712 | 1209 | 150 | 1728 | 1396 | 1139 | 1745 | 1402 | 694 | 1647 | 0 |
| Satd. Flow (RTOR) | | | 49 | | | 191 | | | 95 | | 12 | |
| Lane Group Flow (vph) | 52 | 863 | 11 | 32 | 591 | 191 | 50 | 358 | 278 | 224 | 151 | 0 |
| Turn Type | Perm | NA | Perm | Perm | NA | Perm | Perm | NA | Perm | Perm | NA | |
| Protected Phases | | 2 | | | 6 | | | 4 | | | 8 | |
| Permitted Phases | 2 | | 2 | 6 | | 6 | 4 | | 4 | 8 | | |
| Detector Phase | 2 | 2 | 2 | 6 | 6 | 6 | 4 | 4 | 4 | 8 | 8 | |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | |
| Minimum Split (s) | 48.0 | 48.0 | 48.0 | 48.0 | 48.0 | 48.0 | 37.0 | 37.0 | 37.0 | 37.0 | 37.0 | |
| Total Split (s) | 48.0 | 48.0 | 48.0 | 48.0 | 48.0 | 48.0 | 37.0 | 37.0 | 37.0 | 37.0 | 37.0 | |
| Total Split (%) | 56.5% | 56.5% | 56.5% | 56.5% | 56.5% | 56.5% | 43.5% | 43.5% | 43.5% | 43.5% | 43.5% | |
| Yellow Time (s) | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | |
| All-Red Time (s) | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.8 | 3.8 | 3.8 | 3.8 | 3.8 | |
| Lost Time Adjust (s) | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | |
| Total Lost Time (s) | 6.7 | 6.7 | 6.7 | 6.7 | 6.7 | 6.7 | 6.8 | 6.8 | 6.8 | 6.8 | 6.8 | |
| Lead/Lag | | | | | | | | | | | | |
| Lead-Lag Optimize? | | | | | | | | | | | | |
| Recall Mode | C-Max | C-Max | C-Max | C-Max | C-Max | C-Max | None | None | None | None | None | |
| Act Effct Green (s) | 43.1 | 43.1 | 43.1 | 43.1 | 43.1 | 43.1 | 28.4 | 28.4 | 28.4 | 28.4 | 28.4 | |
| Actuated g/C Ratio | 0.51 | 0.51 | 0.51 | 0.51 | 0.51 | 0.51 | 0.33 | 0.33 | 0.33 | 0.33 | 0.33 | |
| v/c Ratio | 0.20 | 1.00 | 0.02 | 0.43 | 0.67 | 0.24 | 0.13 | 0.62 | 0.52 | 0.97 | 0.27 | |
| Control Delay | 15.1 | 53.2 | 0.1 | 36.3 | 21.3 | 2.8 | 19.7 | 28.5 | 18.1 | 81.9 | 19.7 | |
| Queue Delay | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | |
| Total Delay | 15.1 | 53.2 | 0.1 | 36.3 | 21.3 | 2.8 | 19.7 | 28.5 | 18.1 | 81.9 | 19.7 | |
| LOS | B | D | A | D | C | A | B | C | B | F | B | |
| Approach Delay | | 50.5 | | | 17.5 | | | 23.6 | | | 56.9 | |
| Approach LOS | | D | | | B | | | C | | | E | |
| Queue Length 50th (m) | 4.6 | ~153.0 | 0.0 | 3.2 | 71.6 | 0.0 | 5.4 | 46.5 | 22.0 | 34.1 | 15.6 | |
| Queue Length 95th (m) | 11.9 | #220.1 | 0.0 | #16.3 | 109.6 | 9.9 | 12.9 | 73.3 | 44.2 | #76.2 | 29.4 | |
| Internal Link Dist (m) | | 561.2 | | | 452.7 | | | 444.3 | | | 482.1 | |
| Turn Bay Length (m) | 60.0 | | 55.0 | 60.0 | | 55.0 | 180.0 | | 80.0 | 45.5 | | |
| Base Capacity (vph) | 262 | 867 | 637 | 75 | 876 | 802 | 404 | 619 | 559 | 246 | 592 | |
| Starvation Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Spillback Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Storage Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Reduced v/c Ratio | 0.20 | 1.00 | 0.02 | 0.43 | 0.67 | 0.24 | 0.12 | 0.58 | 0.50 | 0.91 | 0.26 | |

Intersection Summary

Cycle Length: 85

Actuated Cycle Length: 85

Offset: 40 (47%), Referenced to phase 2:EBTL and 6:WBTL, Start of Green

Natural Cycle: 85

Control Type: Actuated-Coordinated

08-29-2023
MC

CGH Transportation
Page 7

Lanes, Volumes, Timings
4: Cedarview & Fallowfield

2038 Future TotalAM Peak Hour
4497 O'Keefe Court

| | |
|---|------------------------|
| Maximum v/c Ratio: 1.00 | |
| Intersection Signal Delay: 35.2 | Intersection LOS: D |
| Intersection Capacity Utilization 97.8% | ICU Level of Service F |
| Analysis Period (min) 15 | |
| ~ Volume exceeds capacity, queue is theoretically infinite. | |
| Queue shown is maximum after two cycles. | |
| # 95th percentile volume exceeds capacity, queue may be longer. | |
| Queue shown is maximum after two cycles. | |

Splits and Phases: 4: Cedarview & Fallowfield



08-29-2023
MC

CGH Transportation
Page 8

HCM 2010 TWSC
1: Cedarview & Onassa

2038 Future TotalPM Peak Hour
4497 O'Keefe Court

| Intersection | | | | | | |
|--------------------------|------|------|------|------|------|------|
| Int Delay, s/veh | 2.2 | | | | | |
| Movement | EBL | EBR | NBL | NBT | SBT | SBR |
| Lane Configurations | W | | | W | W | |
| Traffic Vol, veh/h | 47 | 39 | 37 | 504 | 572 | 54 |
| Future Vol, veh/h | 47 | 39 | 37 | 504 | 572 | 54 |
| Conflicting Peds, #/hr | 0 | 0 | 32 | 0 | 0 | 32 |
| Sign Control | Stop | Stop | Free | Free | Free | Free |
| RT Channelized | - | None | - | None | - | None |
| Storage Length | 0 | - | - | - | - | - |
| Veh in Median Storage, # | 0 | - | - | 0 | 0 | - |
| Grade, % | 0 | - | - | 0 | 0 | - |
| Peak Hour Factor | 100 | 100 | 100 | 100 | 100 | 100 |
| Heavy Vehicles, % | 8 | 7 | 2 | 2 | 2 | 2 |
| Mvmt Flow | 47 | 39 | 37 | 504 | 572 | 54 |

| Major/Minor | Minor2 | Major1 | Major2 |
|----------------------|--------|--------|--------|
| Conflicting Flow All | 1209 | 631 | 658 |
| Stage 1 | 631 | - | - |
| Stage 2 | 578 | - | - |
| Critical Hdwy | 6.48 | 6.27 | 4.12 |
| Critical Hdwy Stg 1 | 5.48 | - | - |
| Critical Hdwy Stg 2 | 5.48 | - | - |
| Follow-up Hdwy | 3.572 | 3.363 | 2.218 |
| Pot Cap-1 Maneuver | 196 | 472 | 930 |
| Stage 1 | 519 | - | - |
| Stage 2 | 549 | - | - |
| Platoon blocked, % | - | - | - |
| Mov Cap-1 Maneuver | 176 | 460 | 907 |
| Mov Cap-2 Maneuver | 176 | - | - |
| Stage 1 | 477 | - | - |
| Stage 2 | 535 | - | - |

| Approach | EB | NB | SB |
|----------------------|------|-----|----|
| HCM Control Delay, s | 27.6 | 0.6 | 0 |
| HCM LOS | D | | |

| Minor Lane/Major Mvmt | NBL | NBT | EBLn1 | SBT | SBR |
|-----------------------|-------|-----|-------|-----|-----|
| Capacity (veh/h) | 907 | - | 244 | - | - |
| HCM Lane V/C Ratio | 0.041 | - | 0.352 | - | - |
| HCM Control Delay (s) | 9.1 | 0 | 27.6 | - | - |
| HCM Lane LOS | A | A | D | - | - |
| HCM 95th %tile Q(veh) | 0.1 | - | 1.5 | - | - |

Lanes, Volumes, Timings
2: Citigate & Fallowfield & Strandherd

2038 Future TotalPM Peak Hour
4497 O'Keefe Court

| Lane Group | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|-------|--------|-------|-------|--------|-------|-------|-------|-----|-------|-------|-------|
| Lane Configurations | W | W | W | W | W | W | W | W | W | W | W | W |
| Traffic Volume (vph) | 451 | 1655 | 208 | 10 | 1873 | 137 | 371 | 189 | 43 | 140 | 105 | 529 |
| Future Volume (vph) | 451 | 1655 | 208 | 10 | 1873 | 137 | 371 | 189 | 43 | 140 | 105 | 529 |
| Satd. Flow (prot) | 3216 | 3316 | 1469 | 1127 | 3316 | 1483 | 3154 | 1632 | 0 | 1658 | 1664 | 1455 |
| Fit Permitted | 0.950 | | | 0.950 | | | 0.950 | | | 0.950 | | |
| Satd. Flow (perm) | 3176 | 3316 | 1372 | 1122 | 3316 | 1315 | 3078 | 1632 | 0 | 1624 | 1664 | 1383 |
| Satd. Flow (RTOR) | | | 160 | | | 160 | | 10 | | | | 358 |
| Lane Group Flow (vph) | 451 | 1655 | 208 | 10 | 1873 | 137 | 371 | 232 | 0 | 140 | 105 | 529 |
| Turn Type | Prot | NA | Perm | Prot | NA | Perm | Prot | NA | | Prot | NA | Perm |
| Protected Phases | 13 | 2 | | 9 | 6 | | 7 | 4 | | 3 | 8 | |
| Permitted Phases | | | 2 | | | 6 | | | | | | 8 |
| Detector Phase | 13 | 2 | 2 | 9 | 6 | 6 | 7 | 4 | | 3 | 8 | 8 |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 5.0 | 10.0 | 10.0 | 5.0 | 10.0 | 10.0 | 5.0 | 10.0 | | 5.0 | 10.0 | 10.0 |
| Minimum Split (s) | 12.1 | 29.9 | 29.9 | 12.1 | 29.9 | 29.9 | 11.5 | 48.0 | | 11.5 | 48.0 | 48.0 |
| Total Split (s) | 24.0 | 34.0 | 34.0 | 24.0 | 34.0 | 34.0 | 14.0 | 48.0 | | 14.0 | 48.0 | 48.0 |
| Total Split (%) | 20.0% | 28.3% | 28.3% | 20.0% | 28.3% | 28.3% | 11.7% | 40.0% | | 11.7% | 40.0% | 40.0% |
| Yellow Time (s) | 4.6 | 4.6 | 4.6 | 4.6 | 4.6 | 4.6 | 3.7 | 3.7 | | 3.7 | 3.7 | 3.7 |
| All-Red Time (s) | 2.5 | 2.3 | 2.3 | 2.5 | 2.3 | 2.3 | 2.8 | 3.3 | | 2.8 | 3.3 | 3.3 |
| Lost Time Adjust (s) | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 |
| Total Lost Time (s) | 7.1 | 6.9 | 6.9 | 7.1 | 6.9 | 6.9 | 6.5 | 7.0 | | 6.5 | 7.0 | 7.0 |
| Lead/Lag | | | | | | | Lag | Lead | | Lag | Lead | Lead |
| Lead-Lag Optimize? | | | | | | | Yes | Yes | | Yes | Yes | Yes |
| Recall Mode | None | C-Max | C-Max | None | C-Max | C-Max | None | None | | None | None | None |
| Act Effct Green (s) | 17.0 | 48.0 | 48.0 | 6.8 | 27.1 | 27.1 | 18.3 | 31.1 | | 17.3 | 30.1 | 30.1 |
| Actuated g/C Ratio | 0.14 | 0.40 | 0.40 | 0.06 | 0.23 | 0.23 | 0.15 | 0.26 | | 0.14 | 0.25 | 0.25 |
| v/c Ratio | 0.99 | 1.25 | 0.32 | 0.16 | 2.50 | 0.33 | 0.77 | 0.54 | | 0.59 | 0.25 | 0.86 |
| Control Delay | 92.2 | 150.4 | 9.1 | 58.8 | 702.6 | 5.9 | 62.5 | 39.3 | | 62.6 | 33.9 | 26.6 |
| Queue Delay | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 |
| Total Delay | 92.2 | 150.4 | 9.1 | 58.8 | 702.6 | 5.9 | 62.5 | 39.3 | | 62.6 | 33.9 | 26.6 |
| LOS | F | F | A | E | F | A | E | D | | E | C | C |
| Approach Delay | | 126.4 | | | 652.1 | | | 53.6 | | | 34.1 | |
| Approach LOS | | F | | | F | | | D | | | C | |
| Queue Length 50th (m) | 55.4 | ~244.7 | 6.6 | 2.3 | ~386.4 | 0.0 | ~68.8 | 39.7 | | ~43.2 | 17.3 | 35.4 |
| Queue Length 95th (m) | #88.8 | #343.9 | 28.2 | 7.8 | #428.7 | 11.1 | #99.1 | 62.2 | | #83.4 | 30.6 | 81.3 |
| Internal Link Dist (m) | | 441.7 | | | 233.3 | | | 132.8 | | | 356.4 | |
| Turn Bay Length (m) | 127.0 | | 96.5 | 95.0 | | 90.0 | 90.0 | | | 140.0 | | 125.0 |
| Base Capacity (vph) | 454 | 1326 | 645 | 158 | 748 | 420 | 480 | 564 | | 239 | 568 | 708 |
| Starvation Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | 0 |
| Spillback Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | 0 |
| Storage Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | 0 |
| Reduced v/c Ratio | 0.99 | 1.25 | 0.32 | 0.06 | 2.50 | 0.33 | 0.77 | 0.41 | | 0.59 | 0.18 | 0.75 |

| Intersection Summary | |
|---|--|
| Cycle Length: 120 | |
| Actuated Cycle Length: 120 | |
| Offset: 0 (0%), Referenced to phase 2:EBT and 6:WBT, Start of Green | |
| Natural Cycle: 145 | |
| Control Type: Actuated-Coordinated | |

Lanes, Volumes, Timings
2: Citigate & Fallowfield & Strandherd

2038 Future TotalPM Peak Hour
4497 O'Keefe Court

Maximum v/c Ratio: 2.50

Intersection Signal Delay: 292.1

Intersection LOS: F

Intersection Capacity Utilization 127.6%

ICU Level of Service H

Analysis Period (min) 15

~ Volume exceeds capacity, queue is theoretically infinite.

Queue shown is maximum after two cycles.

95th percentile volume exceeds capacity, queue may be longer.

Queue shown is maximum after two cycles.

Splits and Phases: 2: Citigate & Fallowfield & Strandherd



HCM 2010 TWSC
3: Cobble Hill/O'Keefe & Fallowfield

2038 Future TotalPM Peak Hour
4497 O'Keefe Court

Intersection

Int Delay, s/veh 65.6

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|--------------------------|-------|------|------|------|------|------|------|------|------|------|------|------|
| Lane Configurations | ↰ | ↑ | ↱ | ↰ | ↑ | ↱ | ↰ | ↑ | ↱ | ↰ | ↑ | ↱ |
| Traffic Vol, veh/h | 145 | 601 | 66 | 52 | 709 | 103 | 23 | 3 | 44 | 111 | 5 | 70 |
| Future Vol, veh/h | 145 | 601 | 66 | 52 | 709 | 103 | 23 | 3 | 44 | 111 | 5 | 70 |
| Conflicting Peds, #/hr | 32 | 0 | 33 | 33 | 0 | 32 | 32 | 0 | 18 | 18 | 0 | 32 |
| Sign Control | Free | Free | Free | Free | Free | Free | Stop | Stop | Stop | Stop | Stop | Stop |
| RT Channelized | - | - | None | - | - | None | - | - | None | - | - | None |
| Storage Length | 147.5 | - | 0 | - | - | 30.5 | - | - | - | 42.5 | - | - |
| Veh in Median Storage, # | - | 0 | - | - | 0 | - | - | 0 | - | - | 0 | - |
| Grade, % | - | 0 | - | - | 0 | - | - | 0 | - | - | 0 | - |
| Peak Hour Factor | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| Heavy Vehicles, % | 11 | 3 | 2 | 2 | 5 | 2 | 24 | 2 | 2 | 2 | 2 | 13 |
| Mvmt Flow | 145 | 601 | 66 | 52 | 709 | 103 | 23 | 3 | 44 | 111 | 5 | 70 |

| Major/Minor | Major1 | Major2 | Minor1 | Minor2 |
|----------------------|--------|--------|--------|--------|
| Conflicting Flow All | 844 | 0 | 0 | 700 |
| Stage 1 | - | - | - | - |
| Stage 2 | - | - | - | - |
| Critical Hdwy | 4.21 | - | 4.12 | - |
| Critical Hdwy Stg 1 | - | - | - | - |
| Critical Hdwy Stg 2 | - | - | - | - |
| Follow-up Hdwy | 2.299 | - | 2.218 | - |
| Pot Cap-1 Maneuver | 755 | - | 897 | - |
| Stage 1 | - | - | - | - |
| Stage 2 | - | - | - | - |
| Platoon blocked, % | - | - | - | - |
| Mov Cap-1 Maneuver | 736 | - | 874 | - |
| Mov Cap-2 Maneuver | - | - | - | - |
| Stage 1 | - | - | - | - |
| Stage 2 | - | - | - | - |

| Approach | EB | WB | NB | SB |
|----------------------|----|-----|-------|----------|
| HCM Control Delay, s | 2 | 0.6 | 196.8 | \$ 595.4 |
| HCM LOS | | | F | F |

| Minor Lane/Major Mvmt | NBLn1 | EBL | EBT | EBR | WBL | WBT | WBR | SBLn1 | SBLn2 |
|-----------------------|-------|-------|-----|-----|-------|-----|-----|----------|-------|
| Capacity (veh/h) | 72 | 736 | - | - | 874 | - | - | 41 | 264 |
| HCM Lane V/C Ratio | 0.972 | 0.197 | - | - | 0.059 | - | - | 2.707 | 0.284 |
| HCM Control Delay (s) | 196.8 | 11.1 | - | - | 9.4 | - | - | \$ 981.5 | 24 |
| HCM Lane LOS | F | B | - | - | A | - | - | F | C |
| HCM 95th %tile Q(veh) | 5 | 0.7 | - | - | 0.2 | - | - | 12.2 | 1.1 |

Notes

~: Volume exceeds capacity \$: Delay exceeds 300s +: Computation Not Defined *: All major volume in platoon

Lanes, Volumes, Timings
4: Cedarview & Fallowfield

2038 Future TotalPM Peak Hour
4497 O'Keefe Court

| Lane Group | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|-------|-------|-------|-------|--------|-------|-------|-------|-------|-------|--------|-----|
| Lane Configurations | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ |
| Traffic Volume (vph) | 36 | 595 | 32 | 148 | 830 | 104 | 23 | 183 | 131 | 301 | 595 | 54 |
| Future Volume (vph) | 36 | 595 | 32 | 148 | 830 | 104 | 23 | 183 | 131 | 301 | 595 | 54 |
| Satd. Flow (prot) | 1658 | 1745 | 1483 | 1642 | 1728 | 1483 | 1537 | 1728 | 1469 | 1658 | 1720 | 0 |
| Flt Permitted | 0.097 | | | 0.281 | | | 0.132 | | | 0.642 | | |
| Satd. Flow (perm) | 169 | 1745 | 1418 | 482 | 1728 | 1381 | 214 | 1728 | 1393 | 1092 | 1720 | 0 |
| Satd. Flow (RTOR) | | | 49 | | | 85 | | | 131 | | 6 | |
| Lane Group Flow (vph) | 36 | 595 | 32 | 148 | 830 | 104 | 23 | 183 | 131 | 301 | 649 | 0 |
| Turn Type | Perm | NA | Perm | Perm | NA | Perm | Perm | NA | Perm | Perm | NA | |
| Protected Phases | | 2 | | | 6 | | | 4 | | | 8 | |
| Permitted Phases | 2 | | 2 | 6 | | 6 | 4 | | 4 | 8 | | |
| Detector Phase | 2 | 2 | 2 | 6 | 6 | 6 | 4 | 4 | 4 | 8 | 8 | |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | |
| Minimum Split (s) | 48.0 | 48.0 | 48.0 | 48.0 | 48.0 | 48.0 | 37.0 | 37.0 | 37.0 | 37.0 | 37.0 | |
| Total Split (s) | 48.0 | 48.0 | 48.0 | 48.0 | 48.0 | 48.0 | 37.0 | 37.0 | 37.0 | 37.0 | 37.0 | |
| Total Split (%) | 56.5% | 56.5% | 56.5% | 56.5% | 56.5% | 56.5% | 43.5% | 43.5% | 43.5% | 43.5% | 43.5% | |
| Yellow Time (s) | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | |
| All-Red Time (s) | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.8 | 3.8 | 3.8 | 3.8 | 3.8 | |
| Lost Time Adjust (s) | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | |
| Total Lost Time (s) | 6.7 | 6.7 | 6.7 | 6.7 | 6.7 | 6.7 | 6.8 | 6.8 | 6.8 | 6.8 | 6.8 | |
| Lead/Lag | | | | | | | | | | | | |
| Lead-Lag Optimize? | | | | | | | | | | | | |
| Recall Mode | C-Max | C-Max | C-Max | C-Max | C-Max | C-Max | None | None | None | None | None | |
| Act Effct Green (s) | 41.3 | 41.3 | 41.3 | 41.3 | 41.3 | 41.3 | 30.2 | 30.2 | 30.2 | 30.2 | 30.2 | |
| Actuated g/C Ratio | 0.49 | 0.49 | 0.49 | 0.49 | 0.49 | 0.49 | 0.36 | 0.36 | 0.36 | 0.36 | 0.36 | |
| v/c Ratio | 0.44 | 0.70 | 0.04 | 0.63 | 0.99 | 0.15 | 0.30 | 0.30 | 0.23 | 0.78 | 1.06 | |
| Control Delay | 35.1 | 22.6 | 2.2 | 31.3 | 52.2 | 4.5 | 32.7 | 21.5 | 4.8 | 40.6 | 81.1 | |
| Queue Delay | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | |
| Total Delay | 35.1 | 22.6 | 2.2 | 31.3 | 52.2 | 4.5 | 32.7 | 21.5 | 4.8 | 40.6 | 81.1 | |
| LOS | D | C | A | C | D | A | C | C | A | D | F | |
| Approach Delay | | 22.3 | | | 44.8 | | | 15.7 | | | 68.3 | |
| Approach LOS | | C | | | D | | | B | | | E | |
| Queue Length 50th (m) | 3.6 | 71.9 | 0.0 | 17.0 | 127.1 | 1.5 | 2.7 | 21.1 | 0.0 | 42.9 | ~116.5 | |
| Queue Length 95th (m) | #16.8 | 109.8 | 2.9 | #45.5 | #206.8 | 9.2 | 10.1 | 36.7 | 10.9 | #83.5 | #179.9 | |
| Internal Link Dist (m) | | 561.2 | | | 452.7 | | | 444.3 | | | 482.1 | |
| Turn Bay Length (m) | 60.0 | | 55.0 | 60.0 | | 55.0 | 180.0 | | 80.0 | 45.5 | | |
| Base Capacity (vph) | 82 | 847 | 714 | 234 | 839 | 714 | 76 | 613 | 579 | 387 | 614 | |
| Starvation Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Spillback Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Storage Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Reduced v/c Ratio | 0.44 | 0.70 | 0.04 | 0.63 | 0.99 | 0.15 | 0.30 | 0.30 | 0.23 | 0.78 | 1.06 | |

Intersection Summary

Cycle Length: 85

Actuated Cycle Length: 85

Offset: 40 (47%), Referenced to phase 2:EBTL and 6:WBTL, Start of Green

Natural Cycle: 85

Control Type: Actuated-Coordinated

08-29-2023
MC

CGH Transportation
Page 7

Lanes, Volumes, Timings
4: Cedarview & Fallowfield

2038 Future TotalPM Peak Hour
4497 O'Keefe Court

| | |
|---|------------------------|
| Maximum v/c Ratio: 1.06 | |
| Intersection Signal Delay: 44.0 | Intersection LOS: D |
| Intersection Capacity Utilization 121.9% | ICU Level of Service H |
| Analysis Period (min) 15 | |
| ~ Volume exceeds capacity, queue is theoretically infinite. | |
| Queue shown is maximum after two cycles. | |
| # 95th percentile volume exceeds capacity, queue may be longer. | |
| Queue shown is maximum after two cycles. | |

Splits and Phases: 4: Cedarview & Fallowfield



08-29-2023
MC

CGH Transportation
Page 8

Appendix M

Synchro Intersection Worksheets –Future Total 2038 Mitigation Measures

Lanes, Volumes, Timings

3: Cobble Hill/O'Keefe & Fallowfield

2038 Future TotalAM Peak Hour

4497 O'Keefe Court

| Lane Group | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|-------|-------|-------|-------|-------|-------|-------|-------|-----|-------|-------|-----|
| Lane Configurations | ↰ | ↑ | ↱ | ↰ | ↑ | ↱ | ↰ | ↱ | ↰ | ↱ | ↰ | ↱ |
| Traffic Volume (vph) | 124 | 611 | 11 | 15 | 686 | 50 | 34 | 2 | 52 | 111 | 4 | 84 |
| Future Volume (vph) | 124 | 611 | 11 | 15 | 686 | 50 | 34 | 2 | 52 | 111 | 4 | 84 |
| Satd. Flow (prot) | 1523 | 1712 | 1388 | 1580 | 1695 | 1327 | 0 | 1517 | 0 | 1271 | 1362 | 0 |
| Flt Permitted | 0.292 | | | 0.347 | | | | 0.847 | | 0.700 | | |
| Satd. Flow (perm) | 463 | 1712 | 1311 | 570 | 1695 | 1253 | 0 | 1289 | 0 | 916 | 1362 | 0 |
| Satd. Flow (RTOR) | | | 35 | | | 35 | | 52 | | | 84 | |
| Lane Group Flow (vph) | 124 | 611 | 11 | 15 | 686 | 50 | 0 | 88 | 0 | 111 | 88 | 0 |
| Turn Type | Perm | NA | Perm | Perm | NA | Perm | Perm | NA | | Perm | NA | |
| Protected Phases | 2 | | | | 6 | | | 8 | | | 4 | |
| Permitted Phases | 2 | | 2 | 6 | | 6 | 8 | | | 4 | | |
| Detector Phase | 2 | 2 | 2 | 6 | 6 | 6 | 8 | 8 | | 4 | 4 | |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | | 10.0 | 10.0 | |
| Minimum Split (s) | 38.2 | 38.2 | 38.2 | 38.2 | 38.2 | 38.2 | 30.9 | 30.9 | | 30.9 | 30.9 | |
| Total Split (s) | 59.0 | 59.0 | 59.0 | 59.0 | 59.0 | 59.0 | 31.0 | 31.0 | | 31.0 | 31.0 | |
| Total Split (%) | 65.6% | 65.6% | 65.6% | 65.6% | 65.6% | 65.6% | 34.4% | 34.4% | | 34.4% | 34.4% | |
| Yellow Time (s) | 3.3 | 3.3 | 3.3 | 3.3 | 3.3 | 3.3 | 3.7 | 3.7 | | 3.7 | 3.7 | |
| All-Red Time (s) | 2.9 | 2.9 | 2.9 | 2.9 | 2.9 | 2.9 | 2.2 | 2.2 | | 2.2 | 2.2 | |
| Lost Time Adjust (s) | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | |
| Total Lost Time (s) | 6.2 | 6.2 | 6.2 | 6.2 | 6.2 | 6.2 | 5.9 | 5.9 | | 5.9 | 5.9 | |
| Lead/Lag | | | | | | | | | | | | |
| Lead-Lag Optimize? | | | | | | | | | | | | |
| Recall Mode | None | None | None | None | None | None | None | None | | None | None | |
| Act Effct Green (s) | 34.5 | 34.5 | 34.5 | 34.5 | 34.5 | 34.5 | 17.3 | 17.3 | | 17.3 | 17.3 | |
| Actuated g/C Ratio | 0.62 | 0.62 | 0.62 | 0.62 | 0.62 | 0.62 | 0.31 | 0.31 | | 0.31 | 0.31 | |
| v/c Ratio | 0.43 | 0.58 | 0.01 | 0.04 | 0.65 | 0.06 | 0.20 | 0.39 | | 0.39 | 0.18 | |
| Control Delay | 16.6 | 13.2 | 0.4 | 8.5 | 15.1 | 4.4 | 12.3 | 26.3 | | 7.4 | | |
| Queue Delay | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | |
| Total Delay | 16.6 | 13.2 | 0.4 | 8.5 | 15.1 | 4.4 | 12.3 | 26.3 | | 7.4 | | |
| LOS | B | B | A | A | B | A | B | C | | A | | |
| Approach Delay | 13.6 | | | | 14.2 | | 12.3 | | | 17.9 | | |
| Approach LOS | B | | | | B | | B | | | B | | |
| Queue Length 50th (m) | 6.3 | 35.3 | 0.0 | 0.6 | 43.0 | 0.6 | 2.5 | 8.6 | | 0.3 | | |
| Queue Length 95th (m) | 26.6 | 94.5 | 0.4 | 3.6 | 115.7 | 5.4 | 15.5 | 31.3 | | 10.9 | | |
| Internal Link Dist (m) | | 356.4 | | | 561.2 | | 133.0 | | | 776.8 | | |
| Turn Bay Length (m) | 147.5 | | | 60.0 | | 30.5 | | 42.5 | | | | |
| Base Capacity (vph) | 396 | 1465 | 1127 | 488 | 1451 | 1077 | 724 | 498 | | 779 | | |
| Starvation Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | |
| Spillback Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | |
| Storage Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | |
| Reduced v/c Ratio | 0.31 | 0.42 | 0.01 | 0.03 | 0.47 | 0.05 | 0.12 | 0.22 | | 0.11 | | |

Intersection Summary

Cycle Length: 90

Actuated Cycle Length: 55.7

Natural Cycle: 70

Control Type: Actuated-Uncoordinated

Maximum v/c Ratio: 0.65

08-29-2023
MCCGH Transportation
Page 1

Lanes, Volumes, Timings

3: Cobble Hill/O'Keefe & Fallowfield

2038 Future TotalAM Peak Hour

4497 O'Keefe Court

Intersection Signal Delay: 14.3

Intersection LOS: B

Intersection Capacity Utilization 79.3%

ICU Level of Service D

Analysis Period (min) 15

Splits and Phases: 3: Cobble Hill/O'Keefe & Fallowfield

08-29-2023
MCCGH Transportation
Page 2

Lanes, Volumes, Timings
3: Cobble Hill/O'Keefe & Fallowfield

2038 Future TotalPM Peak Hour
4497 O'Keefe Court

| | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|-------|-------|-------|-------|-------|-------|-------|-------|------|-------|-------|-----|
| Lane Group | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
| Lane Configurations | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ |
| Traffic Volume (vph) | 145 | 635 | 66 | 52 | 737 | 103 | 23 | 3 | 44 | 111 | 5 | 70 |
| Future Volume (vph) | 145 | 635 | 66 | 52 | 737 | 103 | 23 | 3 | 44 | 111 | 5 | 70 |
| Satd. Flow (prot) | 1523 | 1728 | 1483 | 1658 | 1695 | 1483 | 0 | 1426 | 0 | 1658 | 1280 | 0 |
| Flt Permitted | 0.261 | | | 0.334 | | | | 0.879 | | 0.711 | | |
| Satd. Flow (perm) | 414 | 1728 | 1385 | 574 | 1695 | 1388 | 0 | 1256 | 0 | 1212 | 1280 | 0 |
| Satd. Flow (RTOR) | | | 66 | | | 68 | | 44 | | | 70 | |
| Lane Group Flow (vph) | 145 | 635 | 66 | 52 | 737 | 103 | 0 | 70 | 0 | 111 | 75 | 0 |
| Turn Type | Perm | NA | Perm | Perm | NA | Perm | Perm | NA | Perm | NA | NA | |
| Protected Phases | 2 | | | | 6 | | | 8 | | | 4 | |
| Permitted Phases | 2 | | 2 | 6 | | 6 | 8 | | | 4 | | |
| Detector Phase | 2 | 2 | 2 | 6 | 6 | 6 | 8 | 8 | | 4 | 4 | |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | | 10.0 | 10.0 | |
| Minimum Split (s) | 38.2 | 38.2 | 38.2 | 38.2 | 38.2 | 38.2 | 30.9 | 30.9 | | 30.9 | 30.9 | |
| Total Split (s) | 59.1 | 59.1 | 59.1 | 59.1 | 59.1 | 59.1 | 30.9 | 30.9 | | 30.9 | 30.9 | |
| Total Split (%) | 65.7% | 65.7% | 65.7% | 65.7% | 65.7% | 65.7% | 34.3% | 34.3% | | 34.3% | 34.3% | |
| Yellow Time (s) | 3.3 | 3.3 | 3.3 | 3.3 | 3.3 | 3.3 | 3.7 | 3.7 | | 3.7 | 3.7 | |
| All-Red Time (s) | 2.9 | 2.9 | 2.9 | 2.9 | 2.9 | 2.9 | 2.2 | 2.2 | | 2.2 | 2.2 | |
| Lost Time Adjust (s) | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | |
| Total Lost Time (s) | 6.2 | 6.2 | 6.2 | 6.2 | 6.2 | 6.2 | 5.9 | 5.9 | | 5.9 | 5.9 | |
| Lead/Lag | | | | | | | | | | | | |
| Lead-Lag Optimize? | | | | | | | | | | | | |
| Recall Mode | None | None | None | None | None | None | None | None | | None | None | |
| Act Effct Green (s) | 36.0 | 36.0 | 36.0 | 36.0 | 36.0 | 36.0 | | 18.5 | | 18.5 | 18.5 | |
| Actuated g/C Ratio | 0.64 | 0.64 | 0.64 | 0.64 | 0.64 | 0.64 | | 0.33 | | 0.33 | 0.33 | |
| v/c Ratio | 0.55 | 0.58 | 0.07 | 0.14 | 0.68 | 0.11 | | 0.16 | | 0.28 | 0.16 | |
| Control Delay | 21.8 | 12.7 | 2.6 | 9.3 | 15.5 | 4.0 | | 12.5 | | 24.3 | 8.2 | |
| Queue Delay | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | 0.0 | | 0.0 | 0.0 | |
| Total Delay | 21.8 | 12.7 | 2.6 | 9.3 | 15.5 | 4.0 | | 12.5 | | 24.3 | 8.2 | |
| LOS | C | B | A | A | B | A | | B | | C | A | |
| Approach Delay | | 13.5 | | | 13.8 | | | 12.5 | | | 17.8 | |
| Approach LOS | | B | | | B | | | B | | | B | |
| Queue Length 50th (m) | 7.9 | 35.3 | 0.0 | 2.0 | 46.0 | 1.3 | | 1.9 | | 8.6 | 0.4 | |
| Queue Length 95th (m) | 38.7 | 99.6 | 4.9 | 9.3 | 131.4 | 8.6 | | 13.1 | | 29.6 | 10.5 | |
| Internal Link Dist (m) | | 356.4 | | | 561.2 | | | 133.0 | | | 776.8 | |
| Turn Bay Length (m) | 147.5 | | | 60.0 | | 30.5 | | | | 42.5 | | |
| Base Capacity (vph) | 350 | 1460 | 1180 | 485 | 1432 | 1183 | | 687 | | 643 | 712 | |
| Starvation Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | | 0 | | 0 | 0 | |
| Spillback Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | | 0 | | 0 | 0 | |
| Storage Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | | 0 | | 0 | 0 | |
| Reduced v/c Ratio | 0.41 | 0.43 | 0.06 | 0.11 | 0.51 | 0.09 | | 0.10 | | 0.17 | 0.11 | |

Intersection Summary

Cycle Length: 90
Actuated Cycle Length: 56.6
Natural Cycle: 80
Control Type: Actuated-Uncoordinated
Maximum v/c Ratio: 0.68

Lanes, Volumes, Timings
3: Cobble Hill/O'Keefe & Fallowfield

2038 Future TotalPM Peak Hour
4497 O'Keefe Court

| | |
|---|------------------------|
| Intersection Signal Delay: 14.0 | Intersection LOS: B |
| Intersection Capacity Utilization 82.3% | ICU Level of Service E |
| Analysis Period (min) 15 | |

Splits and Phases: 3: Cobble Hill/O'Keefe & Fallowfield



Lanes, Volumes, Timings
4: Cedarview & Fallowfield

2038 Future TotalPM Peak Hour
4497 O'Keefe Court

| | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|---|-------|-------|-------|-------|--------|-------|-------|-------|-------|-------|--------|-----|
| Lane Group | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
| Lane Configurations | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ |
| Traffic Volume (vph) | 36 | 629 | 32 | 148 | 858 | 104 | 23 | 183 | 131 | 301 | 595 | 54 |
| Future Volume (vph) | 36 | 629 | 32 | 148 | 858 | 104 | 23 | 183 | 131 | 301 | 595 | 54 |
| Satd. Flow (prot) | 1658 | 1745 | 1483 | 1642 | 1728 | 1483 | 1537 | 1728 | 1469 | 1658 | 1719 | 0 |
| Flt Permitted | 0.076 | | | 0.251 | | | 0.097 | | | 0.627 | | |
| Satd. Flow (perm) | 133 | 1745 | 1408 | 430 | 1728 | 1359 | 157 | 1728 | 1379 | 1059 | 1719 | 0 |
| Satd. Flow (RTOR) | | | 38 | | | 66 | | | 131 | | 5 | |
| Lane Group Flow (vph) | 36 | 629 | 32 | 148 | 858 | 104 | 23 | 183 | 131 | 301 | 649 | 0 |
| Turn Type | Perm | NA | Perm | Perm | NA | Perm | Perm | NA | Perm | Perm | NA | |
| Protected Phases | | 2 | | | 6 | | | 4 | | | 8 | |
| Permitted Phases | 2 | | 2 | 6 | | 6 | 4 | | 4 | 8 | | |
| Detector Phase | 2 | 2 | 2 | 6 | 6 | 6 | 4 | 4 | 4 | 8 | 8 | |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | |
| Minimum Split (s) | 48.0 | 48.0 | 48.0 | 48.0 | 48.0 | 48.0 | 37.0 | 37.0 | 37.0 | 37.0 | 37.0 | |
| Total Split (s) | 62.0 | 62.0 | 62.0 | 62.0 | 62.0 | 62.0 | 48.0 | 48.0 | 48.0 | 48.0 | 48.0 | |
| Total Split (%) | 56.4% | 56.4% | 56.4% | 56.4% | 56.4% | 56.4% | 43.6% | 43.6% | 43.6% | 43.6% | 43.6% | |
| Yellow Time (s) | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | |
| All-Red Time (s) | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.8 | 3.8 | 3.8 | 3.8 | 3.8 | |
| Lost Time Adjust (s) | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | |
| Total Lost Time (s) | 6.7 | 6.7 | 6.7 | 6.7 | 6.7 | 6.7 | 6.8 | 6.8 | 6.8 | 6.8 | 6.8 | |
| Lead/Lag | | | | | | | | | | | | |
| Lead-Lag Optimize? | | | | | | | | | | | | |
| Recall Mode | C-Max | C-Max | C-Max | C-Max | C-Max | C-Max | None | None | None | None | None | |
| Act Effct Green (s) | 55.3 | 55.3 | 55.3 | 55.3 | 55.3 | 55.3 | 41.2 | 41.2 | 41.2 | 41.2 | 41.2 | |
| Actuated g/C Ratio | 0.50 | 0.50 | 0.50 | 0.50 | 0.50 | 0.50 | 0.37 | 0.37 | 0.37 | 0.37 | 0.37 | |
| v/c Ratio | 0.55 | 0.72 | 0.04 | 0.69 | 0.99 | 0.15 | 0.40 | 0.28 | 0.22 | 0.76 | 1.00 | |
| Control Delay | 54.3 | 27.0 | 3.9 | 40.1 | 56.0 | 6.8 | 49.0 | 25.6 | 4.9 | 44.4 | 71.6 | |
| Queue Delay | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | |
| Total Delay | 54.3 | 27.0 | 3.9 | 40.1 | 56.0 | 6.8 | 49.0 | 25.6 | 4.9 | 44.4 | 71.6 | |
| LOS | D | C | A | D | E | A | D | C | A | D | E | |
| Approach Delay | | 27.4 | | | 49.2 | | | 19.2 | | | 62.9 | |
| Approach LOS | | C | | | D | | | B | | | E | |
| Queue Length 50th (m) | 5.1 | 101.1 | 0.0 | 23.2 | 175.4 | 4.0 | 3.6 | 27.2 | 0.0 | 55.8 | ~137.9 | |
| Queue Length 95th (m) | #22.2 | 144.8 | 4.1 | #57.3 | #262.7 | 12.8 | #14.2 | 44.2 | 11.9 | #98.4 | #213.9 | |
| Internal Link Dist (m) | | 561.2 | | | 452.7 | | | 444.3 | | | 482.1 | |
| Turn Bay Length (m) | 60.0 | | 55.0 | 60.0 | | 55.0 | 180.0 | | 80.0 | 45.5 | | |
| Base Capacity (vph) | 66 | 877 | 726 | 216 | 868 | 716 | 58 | 647 | 598 | 396 | 646 | |
| Starvation Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Spillback Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Storage Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Reduced v/c Ratio | 0.55 | 0.72 | 0.04 | 0.69 | 0.99 | 0.15 | 0.40 | 0.28 | 0.22 | 0.76 | 1.00 | |
| Intersection Summary | | | | | | | | | | | | |
| Cycle Length: 110 | | | | | | | | | | | | |
| Actuated Cycle Length: 110 | | | | | | | | | | | | |
| Offset: 0 (0%), Referenced to phase 2:EBTL and 6:WBTL, Start of Green | | | | | | | | | | | | |
| Natural Cycle: 95 | | | | | | | | | | | | |
| Control Type: Actuated-Coordinated | | | | | | | | | | | | |

Lanes, Volumes, Timings
4: Cedarview & Fallowfield

2038 Future TotalPM Peak Hour
4497 O'Keefe Court

| | |
|---|------------------------|
| Maximum v/c Ratio: 1.00 | |
| Intersection Signal Delay: 45.2 | Intersection LOS: D |
| Intersection Capacity Utilization 123.5% | ICU Level of Service H |
| Analysis Period (min) 15 | |
| ~ Volume exceeds capacity, queue is theoretically infinite. | |
| Queue shown is maximum after two cycles. | |
| # 95th percentile volume exceeds capacity, queue may be longer. | |
| Queue shown is maximum after two cycles. | |

Splits and Phases: 4: Cedarview & Fallowfield



Appendix N

TRANS Screenline 9

TRANS Regional Model

Version 2.15 - Assigned June 16, 2020

AM Network Coding - Lane and Capacity

Barrhaven Area

2011 Model


N/A

User Initials: TIMW
Plot Prepared: August 24, 2021
EMME Scenario: 21713



Legend

- Lane Capacity
- 200 vphpl
 - 400 vphpl
 - 600 vphpl
 - 800 vphpl
 - 1000 vphpl
 - 1200 vphpl
 - 1400 vphpl
 - 1600 vphpl
 - 1800 vphpl
 - all other



The TRANS model is continuously refined & maintained, and all information is provided in good faith. However, model outputs are provided "as is", and no warranty or guarantee is provided as to the accuracy, reliability or reasonableness of the results. In using this data, you agree to accept any and all risks arising from any incorrect, incomplete, or misleading information.

Recipients are required to use caution and professional judgement in using and interpreting model outputs. In particular, caution should be used when focusing on a geographically limited area (such as a single road or intersection), as the model is primarily designed to simulate regional-scale phenomena and has been calibrated at a regional level.

As a general good practice, it is recommended that the user confirm the network coding within the area of interest, and compare base year forecasts against traffic count data to assess the extent to which the model may be over- or under-estimating the travel demand.

TRANS Regional Model

Version 2.15 - Assigned June 16, 2020

AM Network Coding - Lane and Capacity

Barrhaven Area

2031 Model


N/A

User Initials: TIMW
Plot Prepared: August 24, 2021
EMME Scenario: 21711



Legend

- Lane Capacity
- 200 vphpl
 - 400 vphpl
 - 600 vphpl
 - 800 vphpl
 - 1000 vphpl
 - 1200 vphpl
 - 1400 vphpl
 - 1600 vphpl
 - 1800 vphpl
 - all other



The TRANS model is continuously refined & maintained, and all information is provided in good faith. However, model outputs are provided "as is", and no warranty or guarantee is provided as to the accuracy, reliability or reasonableness of the results. In using this data, you agree to accept any and all risks arising from any incorrect, incomplete, or misleading information.

Recipients are required to use caution and professional judgement in using and interpreting model outputs. In particular, caution should be used when focusing on a geographically limited area (such as a single road or intersection), as the model is primarily designed to simulate regional-scale phenomena and has been calibrated at a regional level.

As a general good practice, it is recommended that the user confirm the network coding within the area of interest, and compare base year forecasts against traffic count data to assess the extent to which the model may be over- or under-estimating the travel demand.

| Screenline | Station ID | Station Location | direction | flow_motorcycles | flow_cars | flow_light_goods | flow_buses | flow_single_trucks | flow_articulated_trucks | flow_bicycles |
|------------|------------|--|------------|------------------|-----------|------------------|------------|--------------------|-------------------------|---------------|
| 49 | 1101 | Moodie Imm South of Jock River Bridge | Southbound | 0 | 60 | 26 | 0 | 64 | 7 | 0 |
| 49 | 1101 | Moodie Imm South of Jock River Bridge | Northbound | 0 | 143 | 53 | 2 | 65 | 8 | 0 |
| 49 | 1310 | Longfields Imm. South of Jock River Bridge | Southbound | 0 | 359 | 59 | 27 | 5 | 1 | 0 |
| 49 | 1310 | Longfields Imm. South of Jock River Bridge | Northbound | 0 | 1060 | 82 | 21 | 11 | 2 | 2 |
| 49 | 50017 | Prince of Wales Imm South of Jock River Bridge | Southbound | 0 | 428 | 64 | 8 | 16 | 5 | 0 |
| 49 | 50017 | Prince of Wales Imm South of Jock River Bridge | Northbound | 0 | 1365 | 162 | 2 | 9 | 8 | 0 |
| 49 | 50052 | Hwy 416 Imm. South of Jock River Bridge | Southbound | 0 | 530 | 129 | 2 | 28 | 38 | 0 |
| 49 | 50052 | Hwy 416 Imm. South of Jock River Bridge | Northbound | 0 | 1425 | 321 | 3 | 41 | 57 | 0 |
| 49 | 50826 | Greenbank Imm South of Jock River | Southbound | 0 | 203 | 26 | 8 | 1 | 0 | 0 |
| 49 | 50826 | Greenbank Imm South of Jock River | Northbound | 0 | 607 | 49 | 19 | 1 | 1 | 0 |
| 49 | 50827 | Borrisokane Imm South of Jock River Bridge | Southbound | 0 | 154 | 31 | 1 | 42 | 3 | 0 |
| 49 | 50827 | Borrisokane Imm South of Jock River Bridge | Northbound | 0 | 481 | 46 | 1 | 41 | 0 | 0 |
| 9 | 1102 | Moodie Imm. North of Fallowfield | Southbound | 0 | 66 | 83 | 2 | 75 | 4 | 0 |
| 9 | 1102 | Moodie Imm. North of Fallowfield | Northbound | 1 | 334 | 126 | 4 | 38 | 2 | 0 |
| 9 | 1312 | Greenbank Imm North of Fallowfield | Southbound | 0 | 405 | 39 | 6 | 12 | 1 | 0 |
| 9 | 1312 | Greenbank Imm North of Fallowfield | Northbound | 3 | 1142 | 76 | 3 | 9 | 1 | 0 |
| 9 | 1502 | Woodroffe Imm North of Fallowfield Transit Station | Southbound | 0 | 452 | 53 | 6 | 7 | 1 | 2 |
| 9 | 1502 | Woodroffe Imm North of Fallowfield Transit Station | Northbound | 1 | 2042 | 163 | 8 | 16 | 1 | 2 |
| 9 | 1702 | Merivale Imm North of Fallowfield | Southbound | 0 | 167 | 37 | 4 | 11 | 2 | 0 |
| 9 | 1702 | Merivale Imm North of Fallowfield | Northbound | 1 | 1229 | 113 | 9 | 15 | 5 | 3 |
| 9 | 2301 | Cedarview Imm. North of Lytle | Southbound | 0 | 205 | 29 | 1 | 8 | 1 | 0 |
| 9 | 2301 | Cedarview Imm. North of Lytle | Northbound | 1 | 455 | 34 | 2 | 3 | 0 | 2 |
| 9 | 50030 | Prince of Wales North of Fallowfield | Southbound | 1 | 220 | 34 | 6 | 10 | 6 | 0 |
| 9 | 50030 | Prince of Wales North of Fallowfield | Northbound | 2 | 830 | 72 | 2 | 6 | 4 | 6 |
| 9 | 50051 | Hwy 416 Imm. North of Strandherd | Southbound | 0 | 793 | 129 | 5 | 74 | 47 | 0 |
| 9 | 50051 | Hwy 416 Imm. North of Strandherd | Northbound | 1 | 2382 | 98 | 8 | 73 | 52 | 0 |
| 9 | 5901 | Richmond Imm. South of Hopeside | Southbound | 0 | 240 | 37 | 2 | 8 | 0 | 0 |
| 9 | 5901 | Richmond Imm. South of Hopeside | Northbound | 2 | 192 | 30 | 5 | 12 | 4 | 0 |

Appendix O

MMLOS Analysis

Multi-Modal Level of Service - Intersections Form

Consultant

CGH Transportation

Scenario

Existing/Future

Comments

Project Date

2023-105
5/30/2024

| INTERSECTIONS | | Fallowfield Road at Cedarview Road | | | | Fallowfield Road/Citigate Drive at Strandherd Drive | | | | |
|------------------|--|------------------------------------|-----------------------------|-----------------------------|-----------------------------|---|-----------------------------|-----------------------------------|-----------------------------------|---|
| Crossing Side | | NORTH | SOUTH | EAST | WEST | NORTH | SOUTH | EAST | WEST | |
| Pedestrian | Lanes | 6 | 6 | 6 | 6 | 10+ | 7 | 10+ | 9 | |
| | Median | No Median - 2.4 m | No Median - 2.4 m | No Median - 2.4 m | No Median - 2.4 m | No Median - 2.4 m | No Median - 2.4 m | No Median - 2.4 m | No Median - 2.4 m | |
| | Conflicting Left Turns | Permissive | Permissive | Permissive | Permissive | Protected | Protected | Protected | Protected | |
| | Conflicting Right Turns | Permissive or yield control | Permissive or yield control | Permissive or yield control | Permissive or yield control | Permissive or yield control | Permissive or yield control | Permissive or yield control | Permissive or yield control | |
| | Right Turns on Red (RTorR) ? | RTOR allowed | RTOR allowed | RTOR allowed | RTOR allowed | RTOR allowed | RTOR allowed | RTOR allowed | RTOR allowed | |
| | Ped Signal Leading Interval? | No | No | No | No | No | No | No | No | |
| | Right Turn Channel | No Channel | No Channel | No Channel | No Channel | Conventional with Receiving Lane | No Channel | No Channel | No Channel | |
| | Corner Radius | 10-15m | 10-15m | 10-15m | 10-15m | >25m | 10-15m | 10-15m | 10-15m | |
| | Crosswalk Type | Std transverse markings | Std transverse markings | Std transverse markings | Std transverse markings | Std transverse markings | Std transverse markings | Std transverse markings | Std transverse markings | |
| | PETSI Score | 20 | 20 | 20 | 20 | -39 | 12 | -37 | -21 | |
| | Ped. Exposure to Traffic LoS | F | F | F | F | F | F | F | F | |
| | Cycle Length | 85 | 85 | 85 | 85 | 120 | 120 | 120 | 120 | |
| | Effective Walk Time | 16 | 16 | 19 | 19 | 7 | 7 | 8 | 8 | |
| | Average Pedestrian Delay | 28 | 28 | 26 | 26 | 53 | 53 | 52 | 52 | |
| | Pedestrian Delay LoS | C | C | C | C | E | E | E | E | |
| Level of Service | F | F | F | F | F | F | F | F | F | |
| | F | | | | F | | | | | |
| Approach From | | NORTH | SOUTH | EAST | WEST | NORTH | SOUTH | EAST | WEST | |
| Bicycle | Bicycle Lane Arrangement on Approach | Mixed Traffic | Mixed Traffic | Mixed Traffic | Mixed Traffic | Mixed Traffic | Mixed Traffic | Curb Bike Lane, Cycletrack or MUP | Curb Bike Lane, Cycletrack or MUP | |
| | Right Turn Lane Configuration | | > 50 m | > 50 m | > 50 m | > 50 m | > 50 m | Not Applicable | Not Applicable | |
| | Right Turning Speed | | ≤ 25 km/h | ≤ 25 km/h | ≤ 25 km/h | >25 km/h | ≤ 25 km/h | Not Applicable | Not Applicable | |
| | Cyclist relative to RT motorists | #N/A | F | F | F | F | F | Not Applicable | Not Applicable | |
| | Separated or Mixed Traffic | Mixed Traffic | Mixed Traffic | Mixed Traffic | Mixed Traffic | Mixed Traffic | Mixed Traffic | Separated | Separated | |
| | Left Turn Approach | One lane crossed | ≥ 2 lanes crossed | ≥ 2 lanes crossed | ≥ 2 lanes crossed | ≥ 2 lanes crossed | One lane crossed | Other LT config | 2-stage, LT box | |
| | Operating Speed | ≥ 60 km/h | > 40 to ≤ 50 km/h | ≥ 60 km/h | ≥ 60 km/h | ≥ 60 km/h | ≥ 60 km/h | ≥ 60 km/h | ≥ 60 km/h | |
| | Left Turning Cyclist | F | E | F | F | F | F | F | A | |
| | Level of Service | #N/A | F | F | F | F | F | F | F | A |
| | | #N/A | | | | F | | | | |
| Transit | Average Signal Delay | | | | | | | | | |
| | Level of Service | - | - | - | - | - | - | - | - | |
| | | - | | | | - | | | | |
| Truck | Effective Corner Radius | 10 - 15 m | | | | > 15 m | | 10 - 15 m | | |
| | Number of Receiving Lanes on Departure from Intersection | 1 | | | | ≥ 2 | | ≥ 2 | | |
| | Level of Service | - | - | E | - | A | - | B | - | |
| | | E | | | | B | | | | |
| Auto | Volume to Capacity Ratio | | | | | | | | | |
| | Level of Service | - | | | | - | | | | |