

EAST URBAN COMMUNITY MIXED-USE CENTRE AREA PARKS PLAN

October 2018

City of Ottawa RICHCRAFT | Group of Companies Glenview Homes (Innes Ltd.)



STUDY OBJECTIVE

This Area Parks Plan (APP) is a blueprint intended to provide direction for the development of parks and open spaces within a portion of the East Urban Community Mixed Use Center (EUC-MUC). The guiding objective of this study is to ensure that the future local residents are afforded access to a comprehensive offering of active and passive recreation opportunities.

This document will be a useful planning tool for City staff, Council, the development community and their consultants as they undertake detailed design activities for individual parks in fulfillment of subsequent subdivision agreements.

The APP has been completed concurrently and as an adjunct to the Community Design Plan for the EUC-MUC. This high-level planning document explores and makes recommendations for an appropriate distribution of parks within the study area, while considering pedestrian connectivity. It seeks to balance the size, distribution, physical characteristics and development budgets for parkland against an appropriate program of facilities.

METHODOLOGY

There is a total of seven (7) parks within the EUC-MUC, however only five (5) are within the scope of this APP; two (2) Neighbourhood Parks, a Community Park and two (2) Parkettes. *The City of Ottawa Park Development Manual (2nd Edition, 2017)* may be referenced for a detailed description of each park classification.

Park and Pathways Plan

An overall Park and Pathways Plan provides an overview for the distribution of parks and open space and the network of recreational connections across the study boundaries. The *Pedestrian and Cyclist Facilities Plan* prepared by Fotenn adequately demonstrates this.

Park Amenities Matrix

The Park Amenities Matrix offers a snapshot of the recreational amenities that are proposed to be offered throughout the EUC-MUC. The list was developed in consultation with City of Ottawa Park Planners and is based on the projected needs of the population within the study boundaries. The Matrix also summarizes a balanced overall budget amongst the parks considered in this APP. The funding formula will be indexed annually to allow for inflation over an indeterminate period of development.


Facility Fit Plans

Facility Fit Plans (FFP) for each individual park schematically illustrate how the desired amenities could potentially be arranged on a site while respecting existing site conditions such as topography and natural features. Accompanying each FFP is a narrative describing the physical characteristics of the site and the proposed program for development. Unless otherwise noted, the dimensions and minimum setback required of all facilities comply with the standards established in the City's *Ottawa Park Development Manual (2nd Edition, 2017)*.



An Opinion of Probable Cost (OPC) confirms the design and construction budget for each park based on the current funding formula of \$504,865 per hectare as established by the City. The per hectare budget is based applicable in 2017/18 and will be updated with the current rate at time of park development for each park. The new rate is available in August of each year. The developers will enter into a cost sharing agreement prior to subdivision approval to ensure the realization of these parks. It should be noted that the FFPs are intended as demonstration plans only and should not be considered as the final park design. Amenities and designs for each park may be revised following staff review and public consultation of the concept plans.





EAST URBAN COMMUNITY MIXED-USE CENTRE

AREA PARKS PLAN

PARK AMMENITIES MATRIX

	EAS	T URBAN COMMUNI	TY PARKS		
Amenities	Park #1 1.82 ha Neighbourhood Park	Park #2 1.29 ha Neighbourhood Park	Park #3 0.56 ha Parkette	Park #4 4.65 ha Community Park	Park #5 0.46 ha Parkette
Attractive Landscaping / Tree Planting	✓	✓	✓	✓	✓
Interesting Landforms / Berms	✓	✓	✓	✓	✓
Interpretive Signage		✓			
Pathway Circuit	✓	✓	✓	✓	✓
Seating Areas / Benches	✓	✓	✓	✓	✓
Park Shelter with Picnic Tables	✓			✓	
Park Shade Structure with Benches		✓	✓		✓
Electrical Outlet	✓			✓	
Multipurpose Open Space	✓	✓	✓	✓	✓
Fitness Structures		✓ or			
Fitness Signage		✓			
Park Sign	✓	✓	✓	✓	✓
Bike Racks	✓	✓	✓	✓	✓
Waste Receptacles	✓	✓	✓	✓	✓
Sliding Hill / Toboggan Hill	✓			✓	
Toddler Play Structure			✓	✓	✓
Sandbox with Play Element		✓		✓	✓
Toddler Swings		✓		✓	✓
Junior Play Structure	✓	✓	✓	✓	✓
Junior Swings		✓	✓	✓	✓
Saucer Swing	✓			✓	✓
Senior Play Structure	✓	✓	✓	✓	✓
Senior Swings		✓		✓	✓
Large Electronic Splashpad				✓	
Small Hydraulic Splashpad	✓				
Integrated Skateboard Components				√	
Puddle Rink (with light)	✓			✓	
Permanent Boarded Rink /				√	
Multi-sport Court (with lights)					
Rink Bunker	√			✓	
Seasonal Boarded Rink	√				
Games Tables	√				
Mini Soccer	✓				
Senior Baseball Diamond (with				✓	
conduit for future lighting)					
Tennis / Pickleball Courts	√				
Footprint for Future Fieldhouse				✓	
Parking Lot				✓	

FUTURE EAST URBAN COMMUNITY PARKS					
Park #6	Park #7				
1.5 ha	0.5 ha				
Parkette	Parkette				
✓	✓				
✓	✓				
✓	✓				
✓	✓				
✓	✓				
✓	✓				
✓	✓				
✓	✓				
✓	✓				
	✓				
✓	✓				
√ √ √					
✓					
✓					
✓					

OVER / UNDER BUDGET SUMMARY

	OVER / UNDER E	3UE	GET SUMMARY			
No.	PARK NAME		PARK BUDGET (per facility fit plans - includes R.O.W. works)		TARGET BUDGET (per City of Ottawa per hectare park budget allowance)	BALANCE
1	Park #1 - NEIGHBOURHOOD PARK (Glenview/Caivan)	\$	985,497.21	\$	918,854.30	\$ (66,642.91)
2	Park #2 - NEIGHBOURHOOD PARK	\$	476,514.37	\$	651,275.85	\$ 174,761.48
3	Park #3 - PARKETTE	\$	311,714.85	\$	282,724.40	\$ (28,990.45)
4	Park #4 - COMMUNITY PARK	\$	2,324,555.29	\$	2,347,622.25	\$ 23,066.96
5	Park #5 - PARKETTE	\$	307,431.04	\$	232,237.90	\$ (75,193.14)
	TOTALS:	\$	4,405,712.77	\$	4,432,714.70	\$ 27,001.93
			PE	RC	ENTAGE OVER/UNDER:	0.61%
6	Park #6 - PARKETTE (REIT 4200 Innes)	\$	276,966.90	\$	757,297.50	\$ 480,330.60
7	Park #7 - PARKETTE (Orleans Health Hub)	\$	92,322.30	\$	252,432.50	\$ 160,110.20



PARK #1

SIZE / CLASSIFICATION:

1.82 hectares / Neighbourhood Park

SITE DESCRIPTION:

As this park straddles the Western boundary of the EUC-MUC lands, the adjacent landowners have been consulted in the creation of this facility fit plan. The site is located within a residential area, with a storm pond to the south. Some deciduous trees are scattered across the site. The park has approximately 170m of street frontage on its northern edge.

PROPOSED FACILITIES:

walking paths mini soccer pitch senior play area

waste receptacles tennis courts saucer swing

bicycle rack seasonal boarded puddle rink, toboggan hill

benches complete with lighting and storage bunker low berms

picnic tables puddle rink park sign

games tables small, hydraulic splash pad new tree planting

medium shade structure junior play area

DESCRIPTION OF PARK FACILITIES:

This neighbourhood park features a seasonal boarded rink, a puddle rink, a mini soccer pitch, tennis courts, a small hydraulic splashpad, a junior play area, a senior play area, a saucer swing, and a shade structure. Accessible asphalt paths connect these features and provide a route through the park, with the potential to connect to the storm pond to the south. Low berms are used to create visual interest and provide casual seating, and a larger berm provides a toboggan hill for children in the winter. Picnic tables, games tables, and benches are located close to other park amenities to create places for people to sit and enjoy the park. A large open space provides an area for casual active play.


NOTE:





Glenview Homes (Innes Ltd.)





DATE: April 2018 DO NOT SCALE DRAWING

NEIGHBOURHOOD PARK #1

PARK #1

OPINION OF PROBABLE COSTS:

Park Size: 1.5	82	ha
----------------	----	----

Park Budget:	\$	918,854.30	(based on \$504,865/ha)
--------------	----	------------	-------------------------

ITEN	1 Inities	UNIT	QTY.	UNIT (\$)	SUB-TOTAL (S
.1	SOCCER PITCH - MINI	ea.	1	34,910.00	34,910.00
.2	TENNIS COURTS (2)	ea.	1	139,252.00	139,252.00
.3	SEASONAL BOARDED PUDDLE RINK	ea.	i	51,150.00	51,150.00
.4	PUDDLE RINK	ea.	1	5,975.00	5,975.00
.5	SPLASHPAD - HYDRAULIC	ea.	1	63,325.00	63,325.00
.6	JUNIOR PLAY - SMALL	ea.	1	21,200.00	21,200.00
.7	SENIOR PLAY - SMALL	ea.	1	38,950.00	38,950.00
.8	SWINGS - 1 SAUCER SWING	ea.	1	9,425.00	9,425.00
.9	SHADE STRUCTURE - MEDIUM	ea.	1	46,000.00	46,000.00
				SUB-TOTAL	\$410,187.00
	WORKS & HARDSCAPE				
.1	Rough grading	m^2	18170	3.00	54,510.00
.2	Supplemental drainage (sub-drains, area drains, etc.)	ha	1.82	25,000.00	45,425.00
.3	Heavy duty asphalt paths	m ²	400	65.00	26,000.00
				SUB-TOTAL	\$125,935.00
SITE	FURNISHINGS				
.1	Benches	ea.	6	2,300.00	13,800.00
.2	Picnic tables	ea.	2	1,900.00	3,800.00
.3	Waste receptacles	ea.	2	1,600.00	3,200.00
.4	Bicycle racks (6 capacity, incl. concrete pad)	ea.	1	1,800.00	1,800.00
.5	Park sign (City Standard 2-post model)	ea.	1	4,000.00	4,000.00
.6	Storage bunker with full interior fit up	ea.	1	24,000.00	24,000.00
.7	City Standard Water Supply Vault (Meter)	ea.	1	25,000.00	25,000.00
.8	City Standard Flectrical Service	ea.	. i	15,000.00	15,000.00
.9	Games Table (including concrete footing)	ea.	2	4,000.00	8,000.00
			•	SUB-TOTAL	\$98,600.00
SOF	TSCAPE & PLANTING				
.1	Deciduous shade (70mm cal.)	ea.	20	600.00	12,000.00
.2	Coniferous trees (175cm ht.)	ea.	14	400.00	5,600.00
.3	Sod & Seeded areas (includes topsoil)	m^2	13,023	7.50	97,672.50
				SUB-TOTAL	\$115,272.50
			CONSTRU	CTION SUB-TOTAL	\$749,994.50
SOF	T COSTS				
.1	15% Contingency (on construction sub-total)	%	15	112,499.18	112,499.18
.2	City admistrative recovery fee (4% on total park budget)	%	4	36,754.17	36,754.17
	Professional design fees (on construction budget +	%	10	86,249.37	86,249.37
		7/0			
.3	contingency)	70	10	-	

PARK PROJECT TOTAL		\$985,497.21
TARGET BUDGET	\$	918,854.30
BALANCE	-\$	66,642.91



PARK #2

SIZE / CLASSIFICATION:

1.29 hectares / Neighbourhood Park

SITE DESCRIPTION:

This park is located close to the center of the northern boundary of the EUC-MUC, and is adjacent to a rock barren that is protected snake habitat. There is a 5m buffer zone along and within the parks northern edge to protect the habitat. The park site is relatively flat, sloping gently from north to south, with existing deciduous trees covering a large portion of the site. The park has approximately 239m of street frontage along its southern edge.

PROPOSED FACILITIES:

walking paths interpretive signage swings (toddler, junior, senior)

waste receptacles fitness signage / structures park sign

bicycle rack sand play area new tree planting

benches junior play area retained trees / natural area

small shade structure senior play area

DESCRIPTION OF PARK FACILITIES:

Since this linear park is located adjacent to a natural area and snake habitat, the decision to retain some of the natural areas within the park block was made to better integrate the park with the natural area. Connections to existing trails within the natural area will offer additional connections to the natural area. Interpretive signage is provided to inform and educate park visitors about the natural area and snake habitat. A walking route is provided across the site, punctuated with benches for seating and fitness signage / structures for exercise based on available budget. Toddler, junior, and senior play equipment is provided within the play areas, which visible and accessible from the street frontage. A shade structure is located close to the toddler and junior play equipment.

NOTE:





PARK #2

OPINION OF PROBABLE COSTS:

Park Budget:	\$	651,275.85	(based on \$504,865/ha)
--------------	----	------------	-------------------------

		Park Budget:	2	051,275.85	(based on \$504,865,	/na)
	ITEM		UNIT	QTY.	UNIT (\$)	SUB-TOTAL (\$
1	AMEI .1	NITIES FITNESS SIGNAGE		6	1,850.00	11,100.00
	.1 .2	JUNIOR PLAY - SMALL	ea.	1	21,200.00	21,200.00
	.2	SENIOR PLAY - SMALL	ea. ea.	1	38,950.00	38,950.00
	.4	SWINGS - 3 BAYS (TODDLER, JUNIOR, SENIOR)	ea.	1	15,740.00	15,740.00
	.5	SAND PLAY	ea.	1	5,000.00	5,000.00
	.6	SHADE STRUCTURE - SMALL	ea.	1	40,000.00	40,000.00
					SUB-TOTAL	\$131,990.00
2	SITE	WORKS & HARDSCAPE				
	.1	Rough grading	m²	10290	3.00	30,870.00
	.2	Supplemental drainage (sub-drains, area drains, etc.)	ha	1.03	25,000.00	25,725.00
	.3	Heavy duty asphalt paths	m^2	610	65.00	39,650.00
					SUB-TOTAL	\$96,245.00
}	SITE	FURNISHINGS				
	.1	Benches	ea.	8	2,300.00	18,400.00
	.2	Waste receptacles	ea.	2	1,600.00	3,200.00
	.3	Bicycle racks (6 capacity, incl. concrete pad)	ea.	1	1,800.00	1,800.00
	.4	Interpretive sign (City Standard 1-post model)	ea.	2	3,000.00	6,000.00
	.5	Park sign (City Standard 2-post model)	ea.	1	4,000.00	4,000.00
					SUB-TOTAL	\$33,400.00
ļ	SOFT	SCAPE & PLANTING				
	.1	Deciduous shade (70mm cal.)	ea.	18	600.00	10,800.00
	.2	Coniferous trees (175cm ht.)	ea.	7	400.00	2,800.00
	.4	Naturalized hedgerows (incl. caliper, small container and whip size plants, mulch, soil, cedar posts)	m²	260	52.00	13,520.00
	.5	Sod & Seeded areas (includes topsoil)	m²	8,979	7.50	67,342.50
					SUB-TOTAL	\$94,462.50
				CONSTRI	JCTION SUB-TOTAL	\$356,097.50
5	SOFT	COSTS				
	.1	15% Contingency (on construction sub-total)	%	15	53,414.63	53,414.63
	.2	City admistrative recovery fee (4% on total park budget)	%	4	26,051.03	26,051.03
	.3	Professional design fees (on construction budget + contingency)	%	10	40,951.21	40,951.21
				SOFT	COSTS SUB-TOTAL	\$120,416.87

PARK PROJECT TOTAL	\$476,514.37
TARGET BUDGET	\$ 651,275.85
BALANCE	\$ 174 761 48



PARK #3

SIZE / CLASSIFICATION:

0.56 hectares / Parkette

SITE DESCRIPTION:

This park small parkette is centrally located within the EUC-MUC, surrounded by residential development. The site is relatively flat with a ditch running from north to south through the eastern side of the site, and some existing deciduous trees. The existing ditch will be filled and existing trees removed to accommodate the proposed facilities. The park has approximately 84m of street frontage on both its northern and southern edges (168m total).

PROPOSED FACILITIES:

walking paths small shade structure low berms

waste receptacles toddler / junior play area park sign

bicycle rack (spring toys for toddlers) new tree planting

benches senior play area

relicites

swings

DESCRIPTION OF PARK FACILITIES:

With street frontage on the north and south sides, pedestrian access across the small neighbourhood park seems like a natural fit. Asphalt walking paths extend from four corners towards the center of the site, where junior and senior play areas are provided along with seating and a shade structure. Low berms are used here to provide interest, casual seating, and to frame the central play area and open space.

NOTE:





RICHCRAFT | Group of Companies Glenview Homes (Innes Ltd.)







DATE: April 2018 DO NOT SCALE DRAWING MIXED-USE CENTRE

AREA PARKS PLAN

PARKETTE #3

PARK #3

OPINION OF PROBABLE COSTS:

Park Size: 0.56 ha

Park Budget: \$ 282,724.40 (based on \$504,865/ha)

	r ark budget.	Ψ	202,124.40	(basea on \$504,000)	iiu)
ITEM	1	UNIT	QTY.	UNIT (\$)	SUB-TOTAL (\$
AME	NITIES			(1)	
.1	TODDLER / JUNIOR PLAY (MEDIUM)	ea.	1	32,575.00	32,575.00
.2	SENIOR PLAY - SMALL	ea.	1	38,950.00	38,950.00
.3	SWINGS - 2 BAYS (JUNIOR)	ea.	1	10,750.00	10,750.00
.4	SHADE STRUCTURE - SMALL	ea.	1	40,000.00	40,000.00
				SUB-TOTAL	\$122,275.00
SITE	WORKS & HARDSCAPE				
.1	Rough grading	m ²	5575	3.00	16,725.00
.2	Supplemental drainage (sub-drains, area drains, etc.)	ha	0.56	25,000.00	13,937.50
.3	Heavy duty asphalt paths	m²	400	65.00	26,000.00
				SUB-TOTAL	\$56,662.50
SITE	FURNISHINGS				
.1	Benches	ea.	2	2,300.00	4,600.00
.2	Waste receptacles	ea.	2	1,600.00	3,200.00
.3	Bicycle racks (6 capacity, incl. concrete pad)	ea.	1	1,800.00	1,800.00
.4	Park sign (City Standard 2-post model)	ea.	1	4,000.00	4,000.00
				SUB-TOTAL	\$13,600.00
SOF	TSCAPE & PLANTING				
.1	Deciduous shade (70mm cal.)	ea.	10	600.00	6,000.00
.2	Coniferous trees (175cm ht.)	ea.	8	400.00	3,200.00
.3	Sod & Seeded areas (includes topsoil)	m²	4,765	7.50	35,737.50
				SUB-TOTAL	\$44,937.50
			CONSTRU	JCTION SUB-TOTAL	\$237,475.00
SOF	T COSTS				
.1	15% Contingency (on construction sub-total)	%	15	35,621.25	35,621.25
.2	City admistrative recovery fee (4% on total park budget)	%	4	11,308.98	11,308.98
.3	Professional design fees (on construction budget + contingency)	%	10	27,309.63	27,309.63

PARK PROJECT	TOTAL	\$311,714.85

 TARGET BUDGET
 \$ 282,724.40

 BALANCE
 -\$ 28,990.45



PARK #4

SIZE / CLASSIFICATION:

4.65 hectares / Community Park

SITE DESCRIPTION:

This large park is in the southeast quadrant of the EUC-MUC and is surrounded by an existing snow disposal facility to the east, future employment area to the north, future residential to the west, and the hydro corridor to the south. The site is partially forested with deciduous trees, and relatively flat sloping from north to south. The park has approximately 247m of street frontage along its western edge.

PROPOSED FACILITIES:

walking paths junior play area waste receptacles senior play area

bicycle rack swings (toddler, junior, senior)

benches saucer swing

picnic tables large electronic splash pad

medium shade structure skateboard park with sand play area skateboard park with

toddler play area puddle rink

permanent boarded rink / multi-use courts with lighting

and storage bunker

baseball diamond

toboggan hill

small parking lot

park sign low berms

new tree planting

DESCRIPTION OF PARK FACILITIES:

The Community Park will offer a variety of play and sports facilities, attracting a broad range of park visitors. A twenty-stall parking lot will be provided in the south west corner of the site; the access to the parking lot will be aligned with the intersection in this area. Park services will also be provided in this location, which is fairly central to the future field house location, the proposed splashpad, and the permanent boarded rink / multi-use sport court. A skatepark with integrated elements is proposed adjacent to the multi-use court, grouping together facilities that will attract older children and teenagers. Play elements in this park include a large splash pad and toddler, junior, and senior age play equipment. A shade structure is centrally located between play areas to provide shade for children and care givers in view of play activity. A senior baseball diamond with dugout shelters is located on the northern part of the site, ideally oriented on a north south access, which conveniently places the home plate and dugouts closest to the street. The location for the future construction of a fieldhouse is also located close to the back stop, between the parking lot and the baseball diamond. A good deal of open space has been provided in this park for casual sport activities, and land forming is used for interest and to create a toboggan hill on the eastern boundary of the site. Deciduous and coniferous trees are scattered across the site providing shade and visual interest. A network of asphalt walking paths connects the park facilities.

NOTE:





PARK #4

OPINION OF PROBABLE COSTS:

Park Size: 4.65 ha

Park Budget: \$	2,347,622.25	(based on \$504,865/ha)
-----------------	--------------	-------------------------

ITEM 1 AME	I Nities	UNIT	QTY.	UNIT (\$)	SUB-TOTAL (\$)
.1	BASEBALL DIAMOND (NO LIGHTING - ELECTRICAL	ea.	1	321,065.00	321,065.00
	DISTRIBUTION ONLY)				
.2	INTEGRATED SKATEBOARD ELEMENTS - ADVANCED	ea.	1	100,000.00	100,000.00
.3	PERMANENT BOARDED RINK/MULTI-USE COURT	ea.	1	225,700.00	225,700.00 5,975.00
.4 .5	PUDDLE RINK SPLASHPAD - LARGE	ea. ea.	1 1	5,975.00 200,300.00	200.300.00
.6	JUNIOR PLAY - MEDIUM	ea.	1	32,575.00	32,575.00
.7	TODDLER PLAY - SMALL	ea.	i 1	16,200.00	16,200.00
.8	SENIOR PLAY - MEDIUM	ea.	1	56,525.00	56,525.00
.9	SWING - 3 BAYS (TODDLER, JUNIOR, SENIOR)	ea.	1	15,740.00	15,740.00
.10	SWINGS - 1 SAUCER SWING	ea.	1	9,425.00	9,425.00
.11	SAND PLAY	ea.	1	5,000.00	5,000.00
.12	SHADE STRUCTURE - MEDIUM	ea.	1	46,000.00	46,000.00
.13	PARKING	ea.	20	2,070.00	41,400.00
.14	PARKING LOT ENTRANCE	l.s.	1	5,000.00	5,000.00
				SUB-TOTAL	\$1,080,905.00
	WORKS & HARDSCAPE	0	40500	0.00	100 500 00
.1	Rough grading	m²	46500	3.00	139,500.00
.2	Supplemental drainage (sub-drains, area drains, etc.)	ha °	4.65	25,000.00	116,250.00
.3	Heavy duty asphalt paths	m²	580	65.00	37,700.00
				SUB-TOTAL	\$293,450.00
	FURNISHINGS				
.1	Benches	ea.	6	2,300.00	13,800.00
.2	Picnic tables	ea.	4	1,900.00	7,600.00
.3	Waste receptacles	ea.	3	1,600.00	4,800.00
.4	Bicycle racks (6 capacity, incl. concrete pad)	ea.	1	1,800.00	1,800.00
.5	Park sign (City Standard 2-post model)	ea.	1	4,000.00	4,000.00
.6	Storage bunker with full interior fit up	ea.	1	24,000.00	24,000.00
.7	City Standard Water Supply Vault (Meter)	ea.	1	25,000.00	25,000.00
.8	City Standard Electrical Service	ea.	1	15,000.00	15,000.00
				SUB-TOTAL	\$96,000.00
	TSCAPE & PLANTING			200.00	10,000,00
.1	Deciduous shade (70mm cal.)	ea.	28	600.00	16,800.00
.2	Coniferous trees (175cm ht.)	ea.	22	400.00	8,800.00
.3	Sod & Seeded areas (includes topsoil)	m ²	35,654	7.50	267,405.00
				SUB-TOTAL	\$293,005.00
			CONSTRL	ICTION SUB-TOTAL	\$1,763,360.00
5 SOF	I COSTS				
.1	15% Contingency (on construction sub-total)	%	15	264,504.00	264,504.00
.2	City admistrative recovery fee (4% on total park budget)	%	4	93,904.89	93,904.89
.3	Professional design fees (on construction budget + contingency)	%	10	202,786.40	202,786.40
			SOFT	COSTS SUB-TOTAL	\$561,195.29
			PARK F	PROJECT TOTAL	\$2,324,555.2

 TARGET BUDGET
 \$ 2,347,622.25

 BALANCE
 \$ 23,066.96

PARK #5

SIZE / CLASSIFICATION:

0.46 hectares / Parkette

SITE DESCRIPTION:

This small parkette is located in the residential development area south of Brian Coburn Blvd. The site is relatively flat with few trees. The park has approximately 83m of street frontage along it's southern edge.

PROPOSED FACILITIES:

walking paths toddler play area sand play

waste receptacles junior play area low berms

bicycle rack senior play area park sign

benches swings (toddler, junior, senior) new tree planting

small shade structure saucer swing

DESCRIPTION OF PARK FACILITIES:

This small neighbourhood park features an asphalt walking loop, a junior play area, a senior play area, swings, and a shade structure. Low berms are used to create visual interest, provide casual seating, and to add variation in grades for the walking loop. Benches are provided beneath the shade structure and deciduous trees, which are also scattered across the site along with coniferous trees. A small open space area is provided for casual active play.

NOTE:





PARK #5

OPINION OF PROBABLE COSTS:

Park Siz	e: 0	.4	6	ha
----------	------	----	---	----

Park Budget:	\$	232,237.90	(based on \$504,865/ha)
--------------	----	------------	-------------------------

ITEM		UNIT	QTY.	UNIT (\$)	SUB-TOTAL (\$
AMENITIES					
	DLER / JUNIOR PLAY - MEDIUM	ea.	1	32,575.00	32,575.00
	OR PLAY - SMALL	ea.	1	38,950.00	38,950.00
	NGS - 2 BAYS (TODDLER, JUNIOR, SENIOR)	ea.	1	10,750.00	10,750.00
	NGS - 1 SAUCER SWING	ea.	1	9,425.00	9,425.00
	D PLAY	ea.	1	5,000.00	5,000.00
.6 SHA	DE STRUCTURE - SMALL	ea.	1	40,000.00	40,000.00
				SUB-TOTAL	\$136,700.00
	S & HARDSCAPE				
	gh grading	m^2	4610	3.00	13,830.00
	plemental drainage (sub-drains, area drains, etc.)	ha	0.46	25,000.00	11,525.00
.3 Heav	y duty asphalt paths	m ²	320	65.00	20,800.00
				SUB-TOTAL	\$46,155.00
SITE FURN					
.1 Bend	ches	ea.	3	2,300.00	6,900.00
.2 Was	te receptacles	ea.	2	1,600.00	3,200.00
.3 Bicy	cle racks (6 capacity, incl. concrete pad)	ea.	1	1,800.00	1,800.00
.4 Park	sign (City Standard 1-post model)	ea.	1	2,000.00	2,000.00
				SUB-TOTAL	\$13,900.00
SOFTSCAP	E & PLANTING				
.1 Deci	duous shade (70mm cal.)	ea.	12	600.00	7,200.00
.2 Coni	ferous trees (175cm ht.)	ea.	8	400.00	3,200.00
	& Seeded areas (includes topsoil)	m^2	3,804	7.50	28,530.00
				SUB-TOTAL	\$38,930.00
			CONSTRU	ICTION SUB-TOTAL	\$235,685.00
SOFT COST	īS				
	Contingency (on construction sub-total)	%	15	35,352.75	35,352.75
.2 City	admistrative recovery fee (4% on total park budget)	%	4	9,289.52	9,289.52
	essional design fees (on construction budget + ingency)	%	10	27,103.78	27,103.78
cont					674 740 04
cont			SOFT	COSTS SUB-TOTAL	\$71,746.04
cont				PROJECT TOTAL	\$71,746.04

PARK PROJECT TOTAL	\$307,431.04		
TARGET BUDGET	\$	232,237.90	
BALANCE	-\$	75,193.14	

