



APPROVED SED

APPROVED SED

CATCH BASIN SEDIMENT BARRI
TYPE "A" AND "B"
N.T.S.

NOTES:

- 1) TO BE USED UNDER APPROPRIATE DRAINAGE CIRCUMSTANCES, DURING THE CONSTRUCTION PERIOD.
- 2) WOVEN GEOTEXTILE TO HAVE A MINIMUM EQUIVALENT OPENING SIZE OF 0.15mm AND A MAXIMUM EQUIVALENT OPENING SIZE OF 0.25mm.
- 3) WOVEN GEOTEXTILE TO BE REPLACED PERIODICALLY WHEN ACCUMULATED SEDIMENTS INTERFERE WITH DRAINAGE.
- 4) ALL DIMENSIONS ARE IN MILLIMETRES UNLESS OTHERWISE SHOWN.

ROADSIDE CATCH BASIN SEDIMENT
PROTECTION DETAIL
N.T.S.



T.L. MAK ENGINEERING CONSULTANTS LTD

PROJECT No.	DATE	DRAWING No.
817-37	DECEMBER 2017	ESC-1

ESC-1

D07-12-17-0161