

| 75 mm DIA. I | IDPE DR1 | 7 WATERMA | AIN FOR W1 TO W5 TA | BLE | 50 mm DIA. | HDPE DR | 1 |
|-------------------|----------|-----------------------|--|------------------------------|------------|---------|---|
| WATERMAIN LINE | STATION | PROPOSED ELEVATION | PROPOSED TOP OF WATERMAIN / SERVICE | DESCRIPTION | WATERMAIN | STATION | ľ |
| W1 | 0+000 | 78.20 | 75.80 | N/A | | | Ļ |
| | 0+003.3 | 78.20 | 75.80 | 45 DEG. HORZ. BEND | W10 | 0+000 | Ļ |
| | 0+015.8 | 77.20 | 74.80 | 45 DEG. HORZ. BEND | | 0+050 | ļ |
| | 0+050 | 77.15 | 74.75 | N/A | | 0+053 | ļ |
| | 0+060 | 77.15 | 74.75 | TEE CONNECTION AT W2 AND W10 | W12 | 0+000 | ļ |
| W2 | 0+000 | 77.15 | 74.75 | TEE CONNECTION AT W1 AND W10 | | 0+050 | ļ |
| | 0+004.8 | 77.14 | 74.74 | MINOR BEND | | 0+100 | ļ |
| | 0+038.7 | 77.11 | 74.71 | MINOR BEND | | 0+134.1 | ļ |
| | 0+050 | 77.12 | 74.72 | N/A | | 0+136.9 | ļ |
| | 0+085.6 | 77.14 | 74.74 | MINOR BEND | | 0+150 | L |
| | 0+095.4 | 77.15 | 74.75 | TEE CONNECTION AT W3 AND W11 | | 0+170.2 | |
| W3 | 0+000 | 77.15 | 74.75 | TEE CONNECTION AT W2 AND W11 | W13 | 0+000 | l |
| | 0+050 | 76.95 | 74.55 | N/A | | 0+050 | L |
| | 0+076.3 | 76.90 | 74.50 | MINOR BEND | | 0+100 | l |
| | 0+100 | 76.84 | 74.44 | N/A | | 0+134.1 | l |
| | 0+102.3 | 76.85 | 74.45 | TEE CONNECTION AT W4 AND W9 | | 0+136.9 | L |
| W4 | 0+000 | 76.85 | 74.45 | TEE CONNECTION AT W3 AND W9 | | 0+150 | l |
| | 0+050 | 76.75 | 74.35 | N/A | | 0+187.8 | |
| | 0+100 | 76.67 | 74.27 | MINOE BEND | W14 | 0+000 | Γ |
| | 0+127.5 | 76.80 | 74.40 | TEE CONNECTION AT W5 AND W12 | | 0+050 | |
| W5 | 0+000 | 76.80 | 74.40 | TEE CONNECTION AT W4 AND W12 | | 0+064.6 | |
| | 0+050 | 76.60 | 74.20 | N/A | | 0+067.4 | |
| | 0+100 | 76.60 | 74.20 | N/A | | 0+070 | |
| | 0+150 | 76.60 | 74.20 | N/A | W15 | 0+000 | Γ |
| | 0+199.8 | 76.60 | 74.20 | TEE CONNECTION AT W6 AND W13 | | 0+050 | Γ |
| | | | | | | 0+100 | Γ |

| 50 mm DIA. H | IDPE DR1 | .7 WATERMA | AIN FOR W6 TO W8 TA | BLE | |
|--------------|----------|--------------------------|---------------------|-------------------------------|--|
| WATERMAIN | STATION | PROPOSED PROPOSED TOP OF | | DESCRIPTION | |
| LINE | STATION | ELEVATION | WATERMAIN / SERVICE | DESCRIPTION | |
| W6 | 0+000 | 76.60 | 74.20 | TEE CONNECTION AT W5 AND W13 | |
| | 0+050 | 76.60 | 74.20 | N/A | |
| | 0+100 | 76.60 | 74.20 | N/A | |
| | 0+150 | 76.60 | 74.20 | N/A | |
| | 0+168.5 | 76.60 | 74.20 | TEE CONNECTION AT W7 AND W8 | |
| W7 | 0+000 | 76.60 | 74.20 | TEE CONNECTION AT W6 AND W8 | |
| | 0+050 | 76.60 | 74.20 | N/A | |
| | 0+100 | 76.60 | 74.20 | N/A | |
| | 0+126.4 | 76.60 | 74.20 | TEE CONNECTION AT W14 AND W15 | |
| W8 | 0+000 | 76.60 | 74.20 | TEE CONNECTION AT W6 AND W7 | |
| | 0+050 | 76.94 | 74.54 | N/A | |
| | 0+083.6 | 76.50 | 74.10 | 45 DEG. HORZ. BEND | |
| | 0+091.9 | 76.50 | 74.10 | 45 DEG. HORZ. BEND | |
| | 0+100 | 77.45 | 75.05 | N/A | |
| | 0+150 | 77.10 | 74.70 | N/A | |
| | 0+170.2 | 77.15 | 74.75 | TEE CONNECTION AT W16 AND W17 | |

| WATERMAIN | CTATION | PROPOSED PROPOSED TOP OF | | DESCRIPTION | |
|-----------|---------|--------------------------|---------------------|-----------------------------|--|
| LINE | STATION | ELEVATION | WATERMAIN / SERVICE | DESCRIPTION | |
| W9 | 0+000 | 76.85 | 74.45 | TEE CONNECTION AT W3 AND W4 | |
| | 0+048.5 | 77.10 | 74.70 | MINOR BEND | |
| | 0+050 | 77.10 | 74.70 | N/A | |
| | 0+100 | 76.90 | 74.50 | N/A | |
| | 0+150 | 76.70 | 74.30 | N/A | |
| | 0+200 | 76.50 | 74.10 | N/A | |
| | 0+203.2 | 76.48 | 74.08 | MINOR BEND | |
| | 0+204.8 | 76.48 | 74.08 | MINOR BEND | |
| | 0+221.8 | 76.75 | 74.35 | MINOR BEND | |
| | 0+247 | 76.90 | 74.50 | W18 | |

| 50 mm DIA. | HDPE DR | 17 WATER S | ERVICE FOR W10, W12 T | O W17 TABLE |
|------------|------------------|----------------|-----------------------|-----------------------------------|
| WATERMAIN | STATION | PROPOSED | PROPOSED TOP OF | DESCRIPTION |
| LINE | STATION | ELEVATION | WATERMAIN / SERVICE | DESCRIPTION |
| W10 | 0+000 | 78.15 | 75.75 | TEE CONNECTION AT W1 AND W2 |
| | 0+050 | 77.33 | 74.93 | N/A |
| | 0+053 | 77.48 | 75.08 | CONNECTION AT BUILDING |
| W12 | 0+000 | 76.80 | 74.40 | TEE CONNECTION AT W4 AND W5 |
| | 0+050 | 77.35 | 74.95 | N/A |
| | 0+100 | 77.35 | 74.95 | N/A |
| | 0+134.1 | 77.35 | 74.95 | 45 DEG. HORZ. BEND |
| | 0+136.9 | 77.25 | 74.85 | 45 DEG. HORZ. BEND |
| | 0+150 | 77.25 | 74.85 | TEE CONNECTION AT W3 AND W11 |
| | 0+170.2 | 77.27 | 74.87 | CONNECTION AT BUILDING |
| W13 | 0+000 | 76.60 | 74.20 | TEE CONNECTION AT W5 AND W6 |
| | 0+050 | 77.00 77.30 | 74.60 | N/A |
| | 0+100 0+134.1 | 77.08 | 74.90 74.68 | N/A 45 DEG. HORZ. BEND |
| | 0+134.1 | 77.05 | 74.65 | 45 DEG. HORZ. BEND |
| | 0+150.5 | 77.05 | 74.65 | N/A |
| | 0+130 | 77.05 | 74.65 | CONNECTION AT BUILDING |
| W14 | 0+000 | 76.60 | 74.20 | TEE CONNECTION AT W7 AND W15 |
| | 0+050 | 76.85 | 74.45 | N/A |
| | 0+064.6 | 76.85 | 74.45 | 45 DEG. HORZ. BEND |
| | 0+067.4 | 76.85 | 74.45 | 45 DEG. HORZ. BEND |
| | 0+070 | 76.90 | 74.50 | CONNECTION AT BUILDING |
| W15 | 0+000 | 76.60 | 74.20 | TEE CONNECTION AT W7 AND W14 |
| | 0+050 | 76.55 | 74.15 | N/A |
| | 0+100 | 76.45 | 74.05 | N/A |
| | 0+122.7 | 76.55 | 74.15 | 45 DEG. HORZ. BEND |
| | 0+125.5 | 76.55 | 74.15 | 45 DEG. HORZ. BEND |
| | 0+150 | 76.65 | 74.25 | N/A |
| | 0+200 | 76.70 | 74.30 | N/A |
| | 0+237.1 | 76.65 | 74.25 | 45 DEG. HORZ. BEND |
| | 0+239.9 | 76.35 | 73.95 | 45 DEG. HORZ. BEND |
| | 0+250 0+281.6 | 76.50 77.00 | 74.10 74.60 | N/A CONNECTION AT BUILDING |
| W16 | 0+281.8 | 77.15 | 74.80 | TEE CONNECTION AT BOILDING |
| VV10 | 0+000 0+024 | 77.40 | 75.00 | CONNECTION AT BUILDING |
| W17 | 0+024 | 77.15 | 74.75 | TEE CONNECTION AT W8 AND W16 |
| | 0+050 | 77.15 | 74.75 | N/A |
| | 0+100 | 77.15 | 74.75 | N/A |
| | 0+150 | 76.77 | 74.37 | N/A |
| | 0+151.8 | 73.77 | 71.37 | 45 DEG. HORZ. BEND |
| | 0+180.8 | 76.77 | 74.37 | 45 DEG. HORZ. BEND |
| | 0+185.8 | 76.80 | 74.40 | CONNECTION AT BUILDING |
| W20 | 0+000 | 77.70 | 75.30 | CONNECTION AT WATER METER CHAMBER |
| | 0+002.8 | 77.70 | 75.30 | 45 DEG. HORZ. BEND |
| | 0+005.6 | 77.70 | 75.30 | 45 DEG. HORZ. BEND |
| | 0+020.7 | 77.70 | 75.30 | 45 DEG. HORZ. BEND |
| | 0+023.5 | 77.70 | 75.30 | 45 DEG. HORZ. BEND |
| | 0+050 0+100 | 77.70 77.75 | 75.30 75.35 | N/A N/A |
| | 0+100 | 77.65 | 75.25 | 46 DEG. HORZ. BEND |
| | 0+150 | 77.60 | 75.20 | MINOR BEND |
| | 0+185.8 | 77.60 | 75.20 | N/A |
| | 0+242.1 | 77.60 | 75.20 | MINOR BEND |
| | 0+250 | 77.60 | 75.20 | N/A |
| | 0+300 | 77.60 | 75.20 | N/A |
| | 0+350 | 77.55 | 75.15 | N/A |
| | 0+400 | 77.45 | 75.05 | N/A |
| | 0+457 | 77.40 | 75.00 | 45 DEG. HORZ. BEND |
| | 0+459.8 | 77.40 | 75.00 | 45 DEG. HORZ. BEND |
| | 0+480.1 | 78.20 | 75.80 | 45 DEG. HORZ. BEND |
| | 0+483 | 78.20 | 75.80 | 45 DEG. HORZ. BEND |
| | 0+485.9 | 78.20 | 75.80 | CONNECTION AT CISTERN |

| 1 | 2018-06-15 | ISSUED FOR FOR SITE PLAN APPROVAL | SWT | MLF | DVK |
|------|------------|-----------------------------------|----------|----------|-------|
| REV. | YYYY-MM-DD | DESCRIPTION | DESIGNED | PREPARED | REVIE |

| 19 mm DIA. HDPE DR 17 WATER SERVICE FOR W11 AND W18 TABLE | | | | | | |
|---|------------------|--------------------------------------|--|------------------------------|--|--|
| WATERMAIN | STATION | PROPOSED | PROPOSED TOP OF | DESCRIPTION | | |
| LINE | STATION | ELEVATION | WATERMAIN / SERVICE | DESCRIPTION | | |
| W11 0 | 000+0 | 77.15 | 74.75 | TEE CONNECTION AT W2 AND W3 | | |
| 0 | 0+009.7 | 77.35 | 74.95 | CONNECTION AT BUILDING | | |
| W18 0 | 000+0 | 76.90 | 74.50 | W9 | | |
| 0 | 0+005.7 | 77.15 | 74.75 | CONNECTION AT BUILDING | | |
| LINE S W11 0 W18 0 | 0+009.7 0+000 | ELEVATION 77.15 77.35 76.90 | WATERMAIN / SERVICE 74.75 74.95 74.50 | CONNECTION AT BUILDING W9 | | |

| PIPE RE | PIPE REFERENCE TABLE FOR F1 TO F7 | | | |
|---------|--------------------------------------|--|--|--|
| F1 | 374.0 m - 250 mm DIA. HDPE DR17 PIPE | | | |
| F2 | 118.0 m - 300 mm DIA. HDPE DR17 PIPE | | | |
| F3 | 3.0 m - 375 mm DIA. HDPE DR17 PIPE | | | |
| F4 | 192.0 m - 250 mm DIA. HDPE DR17 PIPE | | | |
| F5 | 164.0 m - 250 mm DIA. HDPE DR17 PIPE | | | |
| F6 | 216.0 m - 300 mm DIA. HDPE DR17 PIPE | | | |
| F7 | 5.0 m - 150 mm DIA. HDPE DR17 PIPE | | | |

| SE | ΔΙ | |
|----|----|--|



CLIENT TAGGART MILLER ENVIRONMENTAL SERVICES

CONSULTANT



GOLDER ASSOCIATES LTD. 1931 ROBERSON ROAD OTTAWA, ONTARIO CANADA [+1] (613) 592 9600 www.golder.com

EVIEWED APPROVED

DVK

| | PROPERTY BOUNDARY |
|--|--|
| | EXISTING CONTOUR (0.25 m INTERVAL) |
| | TERRACING (SLOPE AS INDICATED) |
| | RIP-RAP 200 mmØ, 300 M THICK (NOMINAL) |
| 8000 | AS PER OPSD 810.010 TYPE 'B DITCH |
| | 600 mmØ CULVERT OR AS NOTED |
| | EXISTING CULVERT AS NOTED |
| — F — F — F — | PROPOSED FIRE PROTECTION |
| — w— w— w— | |
| | PROPOSED WATERMAIN VALVE |
| • | CATCH BASIN (OPSD 705.010 C/W 600 mm SUMP) |
| • | MAINTENANCE HOLE (OPSD 707.020) |
| | STORM SEWER LOCATION |
| > | PROPOSED SIAMESE CONNECTION |
| • | PROPOSED FIRE HYDRANT |
| \$ | PROPOSED DRY HYDRANT |
| | |
| ONTARIO PROVI ONTARIO PROVI AVAILABLE. ALL | FIRE SERVICE I SHALL BE IN ACCORDANCE WITH CITY STANDARDS AND SPECIFICATIONS AND NCIAL STANDARD DRAWINGS AND SPECIFICATIONS WHERE APPLICABLE. NCIAL STANDARDS SHALL APPLY WHERE NO CITY STANDARDS ARE DRAWINGS TO BE CHECKED FOR CONFIRMATION WITH APPLICABLE BUILDING ERATION OR GRADING OF SITE IS TO OCCUR PRIOR TO APPROVAL BY CITY. |
| ENGINEERING A TO SEWERS ANI TENDERING ANI | OR IS RESPONSIBLE FOR ALL REMOVALS NECESSARY TO SATISFY ND LANDSCAPE WORKS. CONTRACTOR TO OBTAIN PERMIT FOR CONNECTING D CONNECTION TO WATERMAIN. CONTRACTOR TO VISIT SITE PRIOR TO D CONFIRM SITE CONDITIONS. CONTRACTOR IS RESPONSIBLE FOR OBTAINING EQUIRED AND BEAR COST OF SAME. |
| WORKS THAT AF | ERVICES ARE NOT ALL SHOWN. LOCATION OF UTILITIES AND UNDERGROUND RE SHOWN ARE APPROXIMATE. CONTRACTOR TO VERIFY LOCATION AND ALL SERVICES, UTILITIES AND UNDERGROUND STRUCTURES PRIOR TO ANY I. THE CONTRACTOR IS RESPONSIBLE FOR PROTECTION AND REINSTATEMENT. |
| AS PER THE CIT INCLUDING THE SUPPLY AND INS A MINIMUM 2400 TO FREEZING. T DRAWING OR OT | OR SHALL CONSTRUCT WATER SERVICE, CONNECTION, AND APPURTENANCES Y SPECIFICATIONS AND SHALL COORDINATE AND PAY ALL RELATED COSTS COST OF CONNECTION, INSPECTION, DISINFECTION AND WATER METER STALLATION BY CITY PERSONNEL. SERVICE CONNECTION SHALL BE INSTALLED mm FROM ANY CATCH BASIN, MANHOLE OR OBJECT THAT MAY CONTRIBUTE HERMAL INSULATION SHALL ONLY BE INSTALLED WHERE SHOWN ON THE FILERWISE APPROVED BY THE CITY AS PER THE CITY SPECIFICATIONS W21, WATER METER AND APPURTENANCES AS PER W-30, 31 AND 32) |
| REINSTATEMEN | AREAS TO BE REINSTATED TO EQUAL OR BETTER CONDITION. PAVEMENT T FOR UTILITY CUTS SHALL BE IN ACCORDANCE WITH R10. ALL NEW WORK ITO EXISTING (TO BE APPROVED BY CONSULTANT). |
| SCALED BY THE | S ARE IN METRES UNLESS OTHERWISE STATED. DRAWINGS SHOULD NOT BE CONTRACTOR. ANY MISSING OR QUESTIONABLE DIMENSIONS ARE TO BE I'H THE CONSULTANT IN WRITING. |
| , | ONTRACTOR IS RESPONSIBLE FOR ALL WORKS, UTILITY AND SERVICE TO THE BUILDING. CONNECTIONS TO BE COORDINATED WITH BUILDING |
| ARCHITECTURA | OR SHOULD ENSURE THAT THESE DRAWINGS ARE SUPPLEMENTED FOR L, AND STRUCTURAL HEATING/AIR CONDITIONING, AND ELECTRICAL, TO SUIT MUNICIPAL, AND PROVINCIAL REQUIREMENTS. |
| REQUIREMENTS | EXCAVATIONS SHOULD BE SLOPED IN ACCORDANCE WITH THE OF ONT. REG. 213/91 UNDER THE OCCUPATIONAL HEALTH AND SAFETY ACT. FECHNICAL REPORT FOR CONSTRUCTION DETAILS. |
| | |
| | 0 100 200 1:2,000 METRES |
| PROJECT | GION RESOURCE RECOVERY CENTRE |
| TITLE | |

OVERALL SITE SERVICING PLAN

| PROJECT NO. | CONTROL | REV. | of | DRAWING |
|-------------|---------|------|----|---------|
| 1787048 | 0007 | 1 | | SS1 |