




Stantec Consulting Ltd. 400 - 1331 Clyde Avenue Ottawa ON


Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that



authorized by Stantec is forbidden

PROPOSED DECIDUOUS TREE





PROPOSED DECIDUOUS SHRUBS

PROPOSED CONIFEROUS SHRUBS

PROPOSED PERENNIAL BED PLANTING




PROPOSED ORNAMENTAL GRASSES



PROPOSED PLANTING BED



PLANT SPECIES/QUANTITY KEY TOPSOIL AND SOD



LIGHT STANDARD

0333 ONTARIO INC.

5 MILLCREEK COURT, NEPEAN, ON K2G 6Y7 STANTEC CONSULTING INC.

1331 CLYDE AVENUE, OTTAWA ON K2C 3G4 STANTEC GEOMETRICS LTD.

1331 CLYDE AVENUE, OTTAWA, ON K2C 3G4 MCROBIE ARCHITECTS + INTERIOR DESIGNERS

66 QUEEN STREET, OTTAWA, ON K1P 5C6 LANDSCAPE ARCHITECT: STANTEC CONSULTING INC

4	REVISED AS PER CITY COMMENTS	LZ	ILL	18.08
3	REVISED SITE PLAN	AMO	ILL	18.02
2	REVISED SITE PLAN	AMO	ILL	17.11
1	ISSUED FOR COMMENTS	MS	ILL	17.04
0	ISSUED FOR SITE PLAN CONTROL APPLICATION	MS	ILL	17.04
Revision		Ву	Appd.	YY.MIV

Dwn. Chkd. Dsgn. YY.MM.DD

Permit-Seal



Client/Project

2520333 ONTARIO INC.

PROPOSED COMMERCIAL DEVELOPMENT 3500 HAWTHORNE ROAD OTTAWA, ON

LANDSCAPE PLAN

Project No. 160401302 Drawing No. Sheet Revision 2of 2

LANDSCAPE NOTES

AND BE PROTECTED BEFORE, DURING, AND AFTER CONSTRUCTION.

SUBSOIL TO BE SCARIFIED PRIOR TO

REMOVE ALL NURSERY TAGS

BED AREAS)

APPLICABLE

UNDISTURBED SOIL

SOIL MIXTURE (TRIPLE MIX)

FINISHED GRADE

BORE TO PREVIOUS EXISTING GRADE

100mm SHREDDED BARK MULCH

SHRUBS SHALL BEAR SAME RELATION TO FINISHED GRADE AS IT

100mm HIGH SAUCER (EXCEPT IN PLANTING

TOPSOIL TAMPED TO PREVENT SETTLEMENT

SUBSOIL SCARIFIED PRIOR TO PLANTING

POT TO BE CUT & REMOVED FROM ROOT BALL WHERE

- 1. REFER TO TREE PRESERVATION PLAN FOR INFORMATION RELATED TO TREE REMOVAL / TREE PROTECTION DIRECTIONS. EXISTING VEGETATED AREAS ON ADJACENT PROPERTIES SHALL REMAIN
- NO VEGETATION REMOVAL SHALL OCCUR BETWEEN MAY 1 AND JULY 15 OF ANY YEARS TO PROTECT BREEDING MIGRATORY BIRDS, AS WELL AS AT RISK BAT SPECIES. SHALL TREE REMOVAL DURING THIS PERIOD BY UNAVOIDABLE, THE CONTRACTOR IS REQUIRED TO CONDUCT A NESTING SURVEY BY A REGISTERED PROFESSIONAL AVIAN BIOLOGIST TO IDENTIFY AND ENSURE NO NESTING ACTIVITY ARE PRESENT. TREE REMOVAL WILL BE ALLOWED WITHIN FIVE (5) DAYS OF CONDUCTING THE SURVEY.
- 3. REFER TO "LOT GRADING, DRAINAGE, SEDIMENT & EROSION CONTROL PLAN" FOR PROPOSED
- 4. REFER TO "SITE SERVICING & UTILITY PLAN" FOR LOCATION AND DETAILS OF PROPOSED UNDERGROUND SERVICES.
- 5. SOD SHALL BE KENTUCKY BLUEGRASS SOD INSTALLED OVER 135mm OF TOPSOIL. SOD SHALL BE INSTALLED THROUGHOUT WITHIN LIMIT OF WORK AND IN ALL DISTURBED AREAS OUTSIDE THE LIMIT OF WORK. SOD SHALL BE INSTALLED AS PER OPSS 803.
- CONTRACTOR TO LOCATE AND STAKE ALL UTILITIES PRIOR TO ANY WORK ON THE SITE. DO NOT PLANT DIRECTLY ABOVE UNDERGROUND UTILITIES. REPORT ANY DISCREPANCIES TO THE LANDSCAPE ARCHITECT FOR DIRECTION.
- 7. MAINTAIN A MINIMUM DISTANCE OF 2.0m FROM ALL UNDERGROUND UTILITIES.

- 8. NO TREES SHALL BE PLANTED UNDER OVERHEAD WIRES.
- 9. THE LANDSCAPE ARCHITECT MAY ADJUST THE LOCATION OF TREES PRIOR TO PLANTING TO MINIMIZE CONFLICTS WITH UTILITIES, DRIVEWAYS AND INTERSECTION VISIBILITY.
- 10. CONTRACTOR SHALL SUPPLY ALL MATERIALS IN QUANTITIES SUFFICIENT TO COMPLETE WORK SHOWN ON THESE DRAWINGS. ANY DISCREPANCIES SHALL BE REPORTED TO THE LANDSCAPE ARCHITECT FOR DIRECTION.
- 11. DO NOT MAKE SUBSTITUTIONS OF MATERIALS, PRODUCTS OR QUANTITIES WITHOUT PRIOR WRITTEN PERMISSION OF THE LANDSCAPE ARCHITECT.

MATERIALS FROM THE SITE. KEEP THE SITE CLEAN AND USEABLE AT ALL TIMES.

- 12. THE CONTRACTOR TO MAKE GOOD TO THE SATISFACTION OF THE LANDSCAPE ARCHITECT ANY AREAS DAMAGED BY THE WORK.
- 13. UPON THE COMPLETION OF WORK EACH DAY, REMOVE ALL DEBRIS, GARBAGE AND SURPLUS
- 14. ALL WORKMANSHIP AND MATERIALS (INCLUDING PLANTS) TO BE GUARANTEED FOR ONE FULL YEAR
- FOLLOWING FINAL ACCEPTANCE OF THE PROJECT.
- 15. THE CONTRACTOR SHALL REMOVE ALL T-BAR AND WOODEN TREE STAKES PRIOR TO ASSUMPTION
- 16. AT THE TIME OF INSPECTION FOR ACCEPTANCE ALL TREE PITS SHALL BE CULTIVATED, FREE OR

PLANTING NOTES

- 1. THE DETAILS ON THIS SHEET DO NOT REPRESENT ANY PARTICULAR SPECIES.
- 2. TREES AND SHRUBS AS INDICATED IN THE DETAILS REPRESENT BOTH CONIFEROUS AND DECIDUOUS
- 3. MATERIAL PLANTED IN GROUP SHALL BE SET IN CONTINUOUS PLANTING BEDS.
- 4. CENTRE LINE OF SHRUBS SHALL NOT BE CLOSER THAN 2.4m FROM BUILDING FACE TO PROTECT BUILDING FOOTINGS AND INSULATION.
- 5. PRUNING TO SUIT SPECIES PRUNE BRANCHES BY 1/3 TO REMOVE DAMAGED OR OBJECTIONABLE BRANCHES FOLLOWING PROPER HORTICULTURAL PRACTICE. DO NOT PRUNE LEADERS.
- 6. FIRMLY COMPACT BACKFILLED PLANTING MIXTURE TO ELIMINATE AIR POCKETS OR PREVENT SETTLEMENT.

- 7. PLANTING MATERIAL QUALITY STANDARDS:
- -- ALL PLANT MATERIALS TO CONFORM TO THE CANADIAN NURSERY LANDSCAPE ASSOCIATION FOR VARIETY, SIZE AND CONDITION;
- PLANT MATERIAL COLLECTED FROM WILD SOURCES WILL NOT BE ACCEPTED; -- LANDSCAPE ARCHITECT RESERVES THE RIGHT TO REFUSE ACCEPTANCE OF ANY PLANT
- DISPLAYING POOR GROWTH HABITS, INJURY OR DISEASE; ANY PLANTS THAT DO NOT CONFORM TO THE ABOVE STANDARDS WILL BE PROMPTLY REMOVED FROM THE SITE BY THE CONTRACTOR AND REPLACED WITH MATERIAL OF ACCEPTABLE QUALITY AT NO ADDITIONAL COST TO THE PROJECT.

WEEDS, LEAVES, BROKEN BRANCHES AND DEBRIS.

DECIDUOUS TREE PLANTING DETAIL

SHRUB AND PERENNIAL PLANTING DETAIL