

Environmental Impact Study

2225 Mer Bleue Road, Ottawa, Ontario

FINAL REPORT

Project Number: OTT-00239983-A0

Prepared By: EXP Services Inc. 1595 Clark Boulevard Brampton, ON L6T 4V1 Canada T: 905.793.9800 F: 905.793.0641 www.exp.com

Prepared For: Montfort Hospital c/o ZW Project Management Inc. 150 Richmond Road Ottawa, Ontario K1Z 6W2

Submitted On: September 2018

Legal Notification

This report was prepared by **EXP Services Inc**. (EXP) for **Montfort Hospital** (Client). Any use which a third party makes of this report, or any reliance on or decisions to be made based on it, are the responsibility of such third parties unless a reliance letter has been addressed to, or otherwise provides reliance to, such third party. EXP accepts no responsibility for damages, if any, suffered by any third party as a result of decisions made or actions based on this report.

Professional judgment was exercised in gathering and analyzing information obtained and in the formulation of the conclusions. Like all professional persons rendering advice, we do not act as absolute insurers of the conclusions we reach, but we commit ourselves to care and competence in reaching those conclusions.

In order to properly understand the suggestions, recommendations and opinions expressed in the report, reference must be made to the report in its entirety. EXP is not responsible for use by any part of portions of the report. In addition, EXP makes no representation about the compatibility of digital files associated with the report with the Client's current or future software and hardware systems. Regardless of format, the documents described herein are EXP's instruments of professional service and shall not be altered without the written consent of EXP.



Table of Contents

			Page	Э
1	Intro	ductio	n 1	1
2	Stud	у Аррі	oach 1	I
	2.1	Backg	ound Review 1	
	2.2	Agenc	y Consultation 1	
	2.3	Field S	Surveys	2
	2.4	Analys	is of Significance	2
	2.5	Impact	Assessment 2	2
3	Meth	odolo	gy2	2
	3.1	Vegeta	ation 2	2
	3.2	Wildlife		3
	3.3	Wildlife	e Habitat	3
	3.4	Rare S	pecies	3
	3.5	Surficia	al Geology and Topography 3	3
	3.6	Surfac	e Hydrology 3	3
4	Exis	ting Co	onditions	3
	4.1	Site De	escription	3
	4.2	Adjace	nt Land Use	ŀ
	4.3	Desigr	ated Natural Features 4	ŀ
	4.4	Biophy	sical Features	ŀ
		4.4.1	Vegetation4	ŀ
		4.4.2	Wildlife and Wildlife Habitat5	5
		4.4.3	Rare Species	3
		4.4.4	Surficial Geology and Topography 7	7
		4.4.5	Surface Hydrology 7	7
	4.5	Signific	cant Natural Features 8	3
		4.5.1	Species At Risk Habitat 8	3
		4.5.2	Significant Wildlife Habitat	3
		4.5.3	Wetlands)
5	Desc	riptior	of the Proposed Development9)
6	Pote	ntial In	npacts and Mitigation10)
	6.1	Potent	ial Impacts)
		6.1.1	Direct Impacts)



		6.1.2	Indirect Impacts	10
	6.2	Mitigatio	on	11
		6.2.1	Direct Impacts	11
		6.2.2	Indirect Impacts	11
7	Cond	clusion	s and Recommendations	11
8	Gene	eral Lim	nitations	13
9	Clos	ure		13
10	Refe	rences		14

List of Tables

Table 1:	Site Visit Details	.2
Table 2:	SAR Identified From Background Review and Field Surveys	.6

List of Appendices

Appendix A: Figures

- Figure 1 Site Location
- Figure 2 Ecological Land Classification
- Figure 3 Surface Hydrology
- Figure 4 Significant Features
- Figure 5 Proposed Development
- Figure 6 Mitigation and Protection Measures
- Figure 7 Wildlife Escape Gate
- Appendix B: Agency Response
- Appendix C: Field Survey Forms
- Appendix D: Site Photographs
- Appendix E: Species Lists
- Appendix F: Species List Terms and Definitions



1 Introduction

ZW Project Management Inc. retained exp Services Inc. (**exp**) to complete an Environmental Impact Study (EIS) for the proposed land development located at 2225 Mer Bleue Road, Ottawa, Ontario (**Figure 1 - Appendix A**).

Approval is being sought to permit development of a proposed Health Care Facility. The Site is within the headwaters of McKinnons Creek and falls within the jurisdiction of the South Nation Conservation Authority (SNCA). According to the City of Ottawa Official Plan (OP), an EIS is required for any development and site alteration proposed in or within 30m of elements of the natural heritage system feature in the urban area not designated on Schedule A or B. The City of Ottawa also has records of Bobolink in the vicinity of the Site that was identified during previous transportation studies in the area, which also triggered the City's requirement for an EIS. No other natural heritage features or environmental constraints were identified in local and regional policy documents.

The purpose of the EIS is to determine if the proposed development will have negative impacts on the natural heritage features and functions identified on and adjacent to the Site in accordance with local and provincial natural heritage policy and applicable legislation. More specifically, the Scoped EIS was undertaken to define and characterize ecological features and functions associated with the Site; evaluate rarity, significance and sensitivity of natural features; and assess, avoid and mitigate potential environmental impacts that may occur from the proposed development.

2 Study Approach

2.1 Background Review

A background review of existing natural heritage information was conducted to assist with preparation of the EIS. The information was also reviewed to determine if there were any existing designated natural features or areas associated with the Site as well as to refine the study approach and supplement field data collected for the Site. The key information sources that were reviewed included the following:

- City of Ottawa Official Plan policies and mapping
- DFO Aquatic Species at Risk Distribution Maps
- Government species at risk websites and documentation
- NHIC Natural Heritage Mapping Web Application
- Kemptville District MNRF Natural Heritage Records
- Characterization of Ottawa's Watersheds (City of Ottawa, 2011)
- Urban Natural Areas Environmental Evaluation Study (Muncater Planning, 2005)
- Ottawa Bird Count
- Ontario Breeding Bird Atlas
- Ontario Reptile and Amphibian Atlas
- Ontario Butterfly Atlas
- Various Online Databases (FishNet2, FrogWatch, eBird, etc.)

2.2 Agency Consultation

South Nation Conservation Authority (SNCA) and the Ministry of Natural Resources and Forestry (MNRF) Kemptville District Office were consulted to acquire any records of rare species, fisheries, significant wildlife habitat and other natural heritage occurrences on or in the vicinity of the Site. These records were used to help determine the likelihood of species and habitat occurring on or adjacent to the Site as part of the background review. A copy of the MNRF's response is provided in **Appendix B**. No formal response was received from the SNCA.



2.3 Field Surveys

Field surveys were conducted to identify, map and inventory existing features on the Site including vegetation, wildlife, surface hydrology and any rare, sensitive or significant species or natural features. Detailed field surveys were primarily limited to the Site due to property access issues on the adjacent lands. Adjacent lands and the interaction between the Site and surrounding landscape was assessed from the Site boundary aided with use of binoculars and by using remote sensing and background data sources. A description of the methods for the field studies that were completed for the Scoped EIS is provided in Section 3. A summary of site visit details is provided in **Table 1** and copies of the field survey forms are provided in **Appendix C**.

Date	Start/End Time	Field Surveys	Weather Conditions	Ecologist
June 7, 2017	6:50-10:15	 Vegetation Breeding Birds Incidental Wildlife Observations General Wildlife Habitat Species at Risk Habitat 	Temperature: 11°C Wind (Beaufort Scale): 3 Cloud Cover: 0%	M. Ross, B.Sc.
June 20, 2017	6:15-6:41	Breeding BirdsIncidental Wildlife Observations	Temperature: 17°C Wind (Beaufort Scale): 3 Cloud Cover: 100%	M. Ross, B.Sc.

Table 1: Site Visit Details

2.4 Analysis of Significance

Evaluation of natural features to determine their significance was based on local and provincial natural heritage policy and guidelines. Identification of potentially significant wildlife habitat followed the guidance of the Significant Wildlife Habitat Technical Guide (MNR 2000) and SWH Criteria Schedules - Ecoregion 6E (MNRF 2015b) as well as habitat descriptions for species of conservation concern. Other natural features were evaluated based on the Natural Heritage Reference Manual (MNR 2010).

2.5 Impact Assessment

Direct and indirect potential ecological impacts were evaluated by comparing natural features and functions identified on and adjacent to the Site with the proposed development. Measures to avoid or reduce significant impacts as well as recommendations on ecological enhancement and monitoring were then considered. MNRF (2014a) was used to assess mitigation options for potential impacts to significant wildlife habitat.

3 Methodology

3.1 Vegetation

Distinct vegetation communities were mapped as polygons onto a 2016 aerial imagery of the Site and later verified in the field. A botanical inventory of each vegetation community was conducted on June 7th of 2017. Vegetation communities were defined according to the Ecological Land Classification (ELC) System for Southern Ontario (Lee et al. 1998).

Vegetation communities and plants were summarized and checked for rarity and status. Plant species rarity and nomenclature was cross-referenced with the Ontario Vascular Plants List (MNRF 2016a). Vegetation



communities less than 0.5 hectares were not mapped unless they were provincially rare vegetation communities, contained rare plant species, or provided an important ecological function.

3.2 Wildlife

Breeding bird surveys were completed on June 7 and 20, 2017 under suitable weather conditions and were undertaken following the Ontario Breeding Bird Atlas survey protocol (BSC 2001). Bird breeding calls as well as visual detection and signs of breeding evidence (e.g. egg shells, nest, etc.) were recorded.

Incidental observations of other herpetofauna, mammals, fish, and invertebrates were recorded during the vegetation and bird surveys. All wildlife (including tracks and other sign) were recorded according to the vegetation community where the animal was observed.

Amphibian breeding surveys were not conducted due to the timing of field visits falling outside the prime breeding period for anurans. In addition, it was determined that the Site and adjacent lands did not likely contain suitable breeding habitat for amphibian species based on the surface hydrology and hydroperiod on the Site.

3.3 Wildlife Habitat

Wildlife habitat on the Site was assessed based on ELC mapping, natural features mapping, wildlife habitat requirements and field observations. Localized wildlife habitat features (e.g. amphibian breeding pond, turtle nest site, fish spawning site, hibernation site, etc.) were mapped and the location recorded using GPS as required. Identification and general classification of wildlife habitat was identified following the Significant Wildlife Habitat Technical Guide (MNR 2000) and supporting documentation.

3.4 Rare Species

The possible presence of Species at Risk (SAR) and their habitat within and adjacent to the Site was assessed based on information obtained from the background data review, agency consultation and observations made during the EIS field surveys. Provincially and regionally rare species and vegetation communities were also assessed. This included species or communities with conservation status ranks of S1, S2 or S3 assigned by the Natural Heritage Information Centre (NHIC).

3.5 Surficial Geology and Topography

Information regarding soils and surficial geology for the Site was obtained from field observations, online resources and results of the preliminary geotechnical investigations conducted by exp Services (2017) at the Site in the spring of 2017 that was completed as part of the proposed development.

3.6 Surface Hydrology

Surface water features and site drainage were assessed based on field observations, elevation mapping for the Site and information provided in other study reports completed for the proposed development.

4 Existing Conditions

4.1 Site Description

The Site fronts onto Mer Bleue Road and is located within the southern portion of the suburb of Orleans on the east side of the City of Ottawa. The Site is 9.2 hectares in size and is currently vacant. Prior to 2008, the Site operated as a farmstead with a house, shed, barn and agricultural fields which are no longer present. The agricultural fields have become overgrown with vegetation and site drainage has been left unmaintained such that wetland conditions have established throughout much of the Site. There is a meadow marsh occupying the majority of the south and west portion of the Site and a thicket swamp and cultural woodland in the northern portion of the Site (**Photos 1, 2 and 3 - Appendix D).** No built structures



currently exist on the Site. The Site is zoned 'Mixed Use Centre' and 'General Urban Area' in the City of Ottawa OP.

4.2 Adjacent Land Use

Land use adjacent to the Site includes a hydro transmission right of way to the north, residential area to the east and agricultural lands to the south and west. The City OP indicates that surrounding lands are zoned 'Mixed Use Centre', 'General Urban Area' and 'Employment Area'.

4.3 Designated Natural Features

This section discusses existing designated natural features and areas occurring on or adjacent to the Site that were identified from the background review.

The Site is in the McKinnons Creek subwatershed and falls under the jurisdiction of South Nation Conservation Authority (SNCA). The SNCA currently does not have any regulated area mapping for the Site but they indicated that any watercourses on the Site would be subject to the requirements of Ontario Regulation 172/06 (Development, Interference with Wetlands and Alterations to Shorelines and Watercourses Regulation). Under the *Conservation Authorities Act*, a "watercourse" is defined as an identifiable depression in the ground in which a flow of water regularly or continuously occurs. Some of the drainage features on the Site could be subject to Ontario Regulation 170/06 and require SNCA review and permitting.

Based on the background review, no other existing designated natural features or areas were identified on or within 120m adjacent to the Site.

4.4 **Biophysical Features**

4.4.1 Vegetation

The Site contains three (3) ecological land classification (vegetation community) types, which include: Meadow Marsh (MAM2-2), Thicket Swamp (SWT2-2) and Cultural Woodland (CUW) (**Figure 2 - Appendix A**).

A description of each vegetation community type is provided below. A list of plant species recorded in each community as well as the rarity and status of each plant is presented in **Appendix E**. Definitions for the terms used in the plant species list is provided in **Appendix F**.

Reed Canary Grass Meadow Marsh (MAM2-2)

This vegetation community is located in the south and west sections of the Site adjacent to Brian Coburn Boulevard and Mer Bleue Road and comprises the majority of the Site. A total of 17 plants were inventoried in this feature. Six (35%) of the plant species in this community are non-native, one of which, European White Poplar, is an invasive species. Reed Canary Grass dominates the feature while Bird's-foot Trefoil is abundant. Other species that are commonly associated with this community type, such as Broad-leaved Cattail, Wool Grass and Fox Sedge, as well as other herbaceous species associated with old fields such as Cow Vetch, Common Milkweed and Ox-eye Daisy were also observed in drier areas.

This vegetation community is of low quality and has established following past clearing, human disturbance and agricultural practices. The underlying soil structure is silty clay resulting in poor drainage and formation of standing water that supports conditions for water tolerant plant species.



Willow Thicket Swamp (SWT2-2)

This community type is located in the northern portion of the Site. Half of the community occurs within the Site, while the remainder extends to the north, immediately adjacent to the Site. The northern two thirds of this community contains larger and more mature Slender and Bebb's Willow plants than the southern third, likely due to the more recent abandonment of the agricultural lands where the southern portion of the community occurs.

A total of 17 plants were identified in this feature. Two (12%) of the plant species in this community are nonnative. Slender Willow is dominant in this feature, while Reed Canary Grass and Wool Grass are abundant. Bebb's Willow, Red-osier Dogwood, Graceful Sedge, Pointed Broom Sedge and Fox Sedge were also present but occasional in occurrence. Some species associated with old fields such as Tall Buttercup, Cow Vetch and Kentucky Blue Grass were also observed in drier areas, although uncommon in occurrence.

This community is the result of natural vegetation that established following human disturbance and agricultural land use. As with the previous vegetation community, the soil structure and hydrology of the Site has contributed to the gradual establishment of water tolerant plants.

Cultural Woodland (CUW)

This community type is located within the northern end of the Site. Only a portion of the community occurs on the Site. Much of the community extends to the north, immediately adjacent to the Site.

A total of 23 plants were identified in this feature. Five (22%) of the plant species in this community are nonnative, one of which, European White Poplar, is an invasive species. European White Poplar and Eastern Cottonwood are dominant in the canopy layer, while Trembling Aspen is abundant in this layer. In the understory, Red-osier Dogwood is abundant, while Slender Willow and Bebb's Willow occur occasionally. The ground vegetation consists of a combination of old field (Bird's-foot Trefoil, Kentucky Blue Grass, Canada Goldenrod, Wild Carrot, Cow Vetch) and wetland plants (Pointed Broom Sedge, Fringed Sedge, Reed Canary Grass), where the old field species were generally higher in abundance.

This community is also the result of early-successional regeneration following human disturbance and land use for agricultural purposes. Interspersed throughout the cultural woodland are old asphalt laneways, associated with the previous farmstead. Evidence of trespassing and dumping were present as garbage, broken bottles and fire pits were observed occasionally within the community. As with the previous vegetation communities, the soil structure and hydrology of the Site is likely contributing to the presence of water tolerant plants.

No Butternut was identified within or adjacent to the Cultural Woodland or other portions of the Site during the vegetation surreys.

4.4.2 Wildlife and Wildlife Habitat

The species groups and total number of wildlife in each group that were inventoried during the field surveys were as follows: birds (20) and invertebrates (1). A list of wildlife species and the location where they were observed on and adjacent to the Site is provided in **Appendix E**. Definitions for the terms used in the wildlife species list is provided in **Appendix F**. There was no incidental observations of mammals, reptiles, amphibians or fish during the site visits.

Evidence of bird breeding activity on and adjacent to the Site was confirmed. Breeding evidence documented for bird species was as follows: 8 Possible, 10 Probable, and 1 Confirmed. The majority of the breeding activity was observed in the cultural woodland (CUW) in the northern portion of the Site and immediately adjacent to the north end of the Site. In general, thirteen of the 19 species (68%) of birds for which breeding evidence was documented were observed in the cultural woodland. Territories were identified for American Goldfinch, Least Flycatcher and Warbling Vireo, while Wilson's Snipe were observed displaying above and flushed from within the sparsely treed areas of the cultural woodland; Yellow Warbler was observed exhibiting agitated behaviour. Songs and calls of males were heard for Hairy Woodpecker, American Robin, American Crow, House Wren, Veery, Gray Catbird and Common Yellowthroat. Tree Swallows were seen foraging above and adjacent to the cultural woodland and perching in the trees.



Nine of the 19 species (47%) exhibiting breeding evidence were observed in the meadow marsh (MAM2-2) that comprises the majority of the Site. A female mallard with recently fledged young was observed in the drainage ditch running east to west in the southern portion of this community (**Figure 2 - Appendix A**). Territories were identified for Killdeer, Wilson's Snipe, Swamp Sparrow, Song Sparrow, Red-winged Blackbird and American Goldfinch. Yellow Warbler was observed exhibiting agitated behaviour, while the songs and calls of Common Yellowthroat were heard.

The remaining seven of the 19 species (37%) for which breeding evidence was documented were observed in the thicket swamp (SWT2-2) that occupies most of the northern portion of the Site. Territories were identified for Willow Flycatcher, Swamp Sparrow and Red-winged Blackbird. Yellow Warbler and Song Sparrow were observed exhibiting agitated behaviour, while the songs and calls of American Robin and American Goldfinch were heard. Although not observed exhibiting evidence of breeding, a Green Heron was seen flying overhead during the field investigations in the thicket swamp.

Cabbage White Butterflies were observed foraging in the meadow marsh (MAM2-2) and is a common species that is considered resident to the area.

The Site and adjacent lands, as currently observed, are unlikely to provide suitable breeding habitat for amphibian species based on past land use and current surface hydrology (refer to Section 4.4.4) on the Site. Prior to 2008 there was expectedly no amphibian breeding habitat since most of the Site contained agricultural fields and site drainage was maintained. Since then, poor site drainage has resulted in water tolerant plants establishing creating wetland habitats. This year has seen unprecedented amounts of rain resulting in unusually wetter than normal conditions on the Site. However, observations by **exp** staff have shown that the standing water quickly dries up at the Site within several days. Breeding amphibians generally require two or more months for larva to develop and mature to adults. Although water tolerant plants have established on the Site, the hydroperiod currently observed on the site is not sufficient to support amphibian breeding habitat.

4.4.3 Rare Species

SAR and their habitat as well as Provincially rare species and vegetation communities identified during the EIS are discussed in this section. Provincially listed Endangered and Threatened SAR and their habitat have specific protection under Section 9 and 10 of the ESA, while Special Concern species do not have individual or habitat protection under the Act but may be afforded protection under the Provincial Policy Statement (PPS) through Significant Wildlife Habitat and other legislation (e.g. Migratory Birds Convention Act, Fish and Wildlife Conservation Act).

Based on the background review, the Ontario distribution of 23 Species At Risk (SAR) overlap with the Ottawa region. Based on SAR habitat requirements, potential suitable habitat for 2 of the SAR was identified on or adjacent to the Site. The 2 SAR are listed in **Table 2**. No SAR were observed during the field investigations. A discussion of the SAR in **Table 2** and potential suitable habitat on Site is discussed below.

Species Group	Common Name	Scientific Name	ESA ¹	SARA ²	NHIC ³
Reptiles	Eastern Milksnake	Lampropeltis triangulum	-	SC	S4
Insects	Monarch	Danaus plexippus	SC	END	S2N, S4B
¹ Ontario Endangered Species Act (ESA): END = Endangered; THR= Threatened; SC = Special Concern; "-" = No Status					
² Federal Species At Risk Act (SARA): END = Endangered; THR= Threatened; SC = Special Concern; "-" = No Status					
³ Ontario Natural Heritage Information Centre (NHIC): S1 = Extremely rare; S2 = Very rare; S3 = Rare to uncommon; S4 = Common; S5 = Very common; SE = Exotic; S#S# = range of uncertainty between ranks; SH = Possibly extirpated; SX= Extirpated; SNR = Not yet ranked; SNA = Not suitable for conservation; SU = Insufficient data					

Table 2: SAR Identified From	Background Review and Field Surveys
Table 2. SAN lucilliteu Lioni	Dackyrounu neview anu i leiu Sulveys



Eastern Milksnake is a habitat generalist and can be found in a variety of terrestrial habitat types. The species has been documented in open habitats such as prairies, meadows and pastures, rock outcrops and rocky hillsides and open forests such as deciduous, coniferous, mixed forests and pine plantations. In rural areas, the snake frequently occurs in and around barns, sheds and old buildings in search of prey (e.g. rodents) and shelter. Milksnakes prefer open and edge habitats (compared to closed-canopy habitats) since these habitat characteristics aid in thermoregulation. It is usually found close to a water source and under suitable cover objects including large planks, debris, stumps, decaying logs, rocks and rock piles, stones, bark, rubbish, tar paper, iron sheets, and damp trash. Suitable hibernation sites include mammal burrows, old building foundations, crawl spaces, old wells and cisterns, stone walls, dirt banks, hollow logs, rotting stumps or rock crevices. Suitable habitat for Milksnake on and adjacent to the Site includes the cultural woodland (CUW) and drier areas of the meadow marsh (MAM2-2). Milksnake was not detected during the site visits. A couple of areas of remnant concrete foundation were observed in the meadow marsh (MAM2-2) and old, broken asphalt laneways were present in the cultural woodland (CUW). These features could possibly provide suitable habitat for a snake hibernaculum. Due to the reclusiveness of snakes, numerous site visits would be required to confirm the presence of this species on the Site. Therefore, a more practical approach to determine the presence of Milksnake (as well as other snakes) is based on the presence of suitable habitat.

Monarchs use three different types of habitat during their lifetime - overwintering, breeding, staging areas and nectaring habitat. Only the larva feed on milkweed plants (*Asclepias syriaca*) and therefore are confined to meadows, fields, and other open areas where milkweed grows. Adult butterflies are found in more diverse habitats where they feed on nectar from a variety of wildflowers. No Monarchs were observed during the field investigations. However, the meadow marsh (MAM2-2) and the cultural woodland (CUW) on and adjacent to the Site could provide both potentially suitable breeding and foraging habitat due to the presence of milkweed plants and other wildflowers in these vegetation communities.

The City of Ottawa has records of Bobolink (*Dolichonyx oryzivorus*) that were identified in proximity to the Site during recent transportation studies completed for Mer Bleue Road and Brian Coburn Boulevard. Based on the field investigations for the EIS, vegetation communities mapped on Site do not provide suitable nesting habitat for Bobolink. Bobolink was not identified during the breeding bird surveys.

No other provincially rare species or vegetation communities were identified during the field investigations.

4.4.4 Surficial Geology and Topography

The Site falls within an area of glacio-marine deposits of clay, silty clay and silt. Fill material is present in the area of the former residence on the west edge of the Site. At this location, approximately 1.5 m of sand fill and 0.2 m of sand and gravel fill were found. The majority of the Site contains silty clay to a maximum depth of 16 m below ground surface. The silty clay is underlain by grey, limestone bedrock. Groundwater ranges in depth from approximately 0.3 m to 2.4 m below surface. Inferred groundwater flow is southwest to northeast across the Site. The Site is considerably flat with minimal topographic relief.

4.4.5 Surface Hydrology

The Site is relatively flat and generally drains towards the south of the Site (**Figure 3** - **Appendix A**). Based on Ontario soil mapping (OMAFRA, 2017), soils on the Site are defined as Poorly Drained. Drainage ditches in the north and southwest sections of the Site convey storm water from the Site west into the drain along Mer Bleue Road.

At the time of field investigations, a substantial volume of water was present on the Site due to recent rain events (**Photo 4 - Attachment B**). The drainage ditches on the Site contained water and rainwater was pooled in low lying areas throughout the Site, although much of the water was actively draining from the site via the drainage ditches and entering the drain along Mer Bleue Road. These observations verify the silty clay soil conditions and indicate that most water accumulated on the Site likely does not remain for a prolonged period. The spring and summer of 2017 have also seen more frequent and intense rain events than in previous years and therefore the Site has remained saturated for longer than usual. The surface



hydrology of the Site, combined with the existing drains on and adjacent to the Site, serve to rapidly drain the Site and under average precipitation amounts the Site would expectedly dry up within a couple of weeks.

McKinnons Creek is the only natural surface water feature in proximity to the Site (**Figure 1 - Appendix A**). A tributary of the creek originates from an area approximately 300 m northeast of the Site and historically continued south of Brian Coburn Boulevard connecting to the main branch of McKinnons Creek. Since then, significant land development has occurred east and southeast of the Site and it appears the tributary now flows into the municipal stormwater system associated with the residential area east of the Site.

4.5 Significant Natural Features

This section discusses potential and confirmed significant natural heritage features and areas on or adjacent to the Site that were identified from the background review, field surveys and evaluation of natural features. Additional information relating to the significant features is provided in the previous subsections. The locations of the significant features are shown in **Figure 4 - Appendix A**. Significant features identified on or adjacent to the Site include the following:

- Species At Risk Habitat
- Significant Wildlife Habitat
- Wetlands

4.5.1 Species At Risk Habitat

According to the Provincial Policy Statement (PPS, 2014), development and site alteration is not permitted in the habitat of endangered and threatened species, except in accordance with provincial and federal requirements. Species listed as Endangered or Threatened provincially are protected under the ESA. Only aquatic and migratory bird SAR on private land that are listed as Endangered or Threatened federally are protected under SARA. Species listed as Special Concern do not receive species or habitat protection under the ESA. Special Concern species are plant and wildlife do however. Habitat for endangered and threatened species that were identified on the Site is discussed below.

The cultural woodland (CUW) and drier areas of the meadow marsh (MAM2-2) may provide suitable summer / foraging habitat for Milksnake. Due to excessive precipitation in the last two years, the meadow marsh has become wetter than previous years and currently is unlikely to provide suitable foraging habitat for Milksnake, which prefer drier environments. Multiple field surveys would be required to confirm the presence-absence of Milksnake (and other snakes) due to its reclusiveness and difficulty to detect. Milksnake is listed as Special Concern and does not have habitat protection under the ESA.

The meadow marsh (MAM2-2) and flowering plants in the cultural woodland (CUW) could provide potentially suitable breeding and foraging habitat for Monarchs. Monarch was not observed during the field investigations. Monarch is listed as Special Concern and does not have habitat protection under the ESA.

4.5.2 Significant Wildlife Habitat

There are four main types of significant wildlife habitat (SWH): Seasonal Concentration Areas; Rare and Specialized Habitat; Habitat for Species of Conservation Concern (excluding Endangered or Threatened Species); and, Animal Movement Corridors. Within each main SWH, there are specific wildlife habitat types (e.g. Waterfowl Stopover and Staging Areas, Turtle Nesting Areas, Marsh Bird Breeding Habitat, etc.). SWH that was identified on or adjacent to the Site is discussed below.

Habitat for Species of Conservation Concern

Species of conservation concern include wildlife species that are listed as Special Concern under the ESA and provincially rare plant and wildlife species (S1 - S3). The potential habitat of species of conservation concern on the Site is associated with the applicable rare species discussed in Section 4.4.3 and previously in this section. No other habitat of species of conservation concern was identified.



4.5.3 Wetlands

The meadow marsh (MAM2-2) and thicket swamp (SWT2-2) are wetlands based on the dominance of wetland plants present in these vegetation communities and according to the guidelines in MNRF (2014b). The establishment of wetlands on Site due to poor drainage associated with previous agricultural practices does not exempt the vegetation communities from being identified as wetlands (MNRF, 2014b). The wetlands are not currently designated in the City OP or shown in MNRF wetland mapping for the area (MNRF, 2015a). The wetlands on Site are however within 750m to other unevaluated wetlands mapped by the MNRF west of the Site. Wetlands within 750m of another wetland (generally within the same watershed or catchment area) can be complexed into a single wetland unit. If the unevaluated wetlands west of the Site are determined by the MNRF to be Provincially Significant Wetland (PSW), the wetlands on Site potentially may also be included as PSW based on the 750m wetland complexing rule. The wetlands on Site currently would not meet the criteria to be classified a PSW if evaluated based on MNRF (2014b).

Any change or interference to the wetlands on Site may require a permit from the South Nation Conservation Authority, under the Ontario Regulation 170/06. The final determination for classifying a wetland as a PSW would be the responsibility of the local MNRF.

5 Description of the Proposed Development

The Site is being planned for development of an urgent care facility (Montford Hospital) that will include construction of a multi-storey main building / hub, access roads, parking areas, landscaped areas and stormwater infrastructure (**Figure 5 - Appendix A**). The proposed development will occupy around 4.6 ha of the 9.2 ha Site. The remainder of the Site is planned for future development that will include a parking area expansion, road extension, a park and other development. The urgent care facility will have two access points and entrances – the west entrance off Mer Bleue Road and the east entrance off Brian Coburn Boulevard.

The site will be serviced by municipal water and sanitary sewer. Minimal grading and placement of fill is expected due to the flat terrain across the Site. Stormwater on the Site will be collected in catchbasins that connect to the Avalon West (Neighborhood 5) Western Trunk Sewer and conveyed to a Stormwater Management Facility located approximately 500m southeast of the Site. Stormwater in the facility will then discharge into McKinnons Creek. A summary of the proposed SWM for the site is as follows (Additional details can be obtained from the Stormwater Management & Servicing Report prepared by EXP for the development):

- SWM for the proposed development will be achieved by restricting all storms up to the 100 year post development flows to the allowable release rate determined during the design of Avalon West (Neighborhood 5) Western Trunk Sewer and Stormwater Management Facility
- Onsite stormwater storage is provided up to the 100-year design storms with maximum allowable ponding depths of 300mm on the ground surface and 150mm on the roof
- Quality control of stormwater will be provided by the existing Stormwater Management Facility for Neighbourhood 5 to provide 80% TSS removal
- Overland flow routes have been provided for the subject site



6 Potential Impacts and Mitigation

6.1 Potential Impacts

6.1.1 Direct Impacts

Most of the Site will be directly impacted from the proposed development and the future planned development on the Site (**Figure 5 - Attachment A**). Based on the proposed development, all of the meadow marsh (MAM2-2), thicket Swamp (SWT2-2) and cultural woodland (CUW) on the Site will be removed. These vegetation communities provide wildlife habitat however the habitat was assessed and not considered significant based on provincial guidelines.

The meadow marsh (MAM2-2) and cultural woodland (CUW) may also provide habitat for Monarch and Milksnake respectfully, which are both listed as Special Concern species under the ESA. There is currently no habitat protection for Special Concern species and therefore no permitting under the Act is required. However, best management practices can be implemented to minimize impacts to the species and its habitat. Past land use activities / disturbance and the early-successional state of the vegetation communities has, for the most part, limited the presence of significant ecological features and functions throughout most of the Site.

The wetlands on Site (MAM2-2 and SWT2-2) may be classified PSW if the wetlands are complexed with other unevaluated wetlands west of the Site. The wetlands on Site did not provide any significant biological function and would not qualify as PSW as a standalone wetland based on MNRF (2014b). Any disturbance or removal of the wetlands would require approval by the SNCA and MNRF.

The intermittent drainage ditches on the Site will be removed due to the construction of the proposed parking and buildings (**Figures 3 and 5 - Appendix A**). The drainage ditches did not provide significant wildlife habitat or habitat for endangered or rare aquatic species. The short hydroperiod in the drainage features limits the biological function of the ditches. No fish were observed in the drainage ditches. Surface water drainage contribution to downstream waterbodies (i.e. McKinnons Creek) will be maintained through the proposed SWM for the Site. Removal of the ditches may require permits from the SNCA if they deem that the ditch meets the definition of a watercourse as per the *Conservation Authorities Act*.

6.1.2 Indirect Impacts

Indirect impacts to natural features from construction activity (noise, dust, sedimentation, spills, etc.) can occur. Noise from construction machinery can interfere with wildlife during sensitive periods (e.g. breeding, spawning, etc.). Dust can be created by machinery and settle on the surrounding vegetation causing stress to plants. Sedimentation to offsite waterbodies can occur if proper sediment and erosion control measures are not implemented during site clearing, grading and construction. Potential chemical spills (fuel, hydraulics, lubricants, etc.) during construction can also occur. Potential impacts from dewatering activities that may be required to construct the main building are not expected since no aquatic features (stream, river, etc.) is on or adjacent to the Site.

Impermeable surfaces (building, parking areas, etc.) created from the development are not expected to negatively affect groundwater due to the existing impervious soils and poor drainage across the Site. No information on stormwater management for the development was available during the EIS and therefore potential stormwater impacts could not be assessed. Due to existing soil and drainage conditions, Low Impact Designs (LID) are not likely feasible. In general, chloride and sodium from de-icing salts applied to the access roads, parking and other areas during winter can enter the stormwater system and eventually make its way into receiving waterbodies. Chloride is persistent in the environment and high concentrations can be toxic to aquatic organisms, particularly during the spring melt from salt-laden snow storage areas.



6.2 Mitigation

6.2.1 Direct Impacts

The Site did not contain SAR. Potential habitat associated with the Special Concern SAR on and adjacent to the Site is not protected under the ESA. However, best management practices should be considered to offset potential harm to SAR that may occur on Site during construction. These measures would also serve to avoid direct harm and impacts to non-protected wildlife species.

Timing windows for construction activities (site clearing, grubbing) on site will be implemented to minimize disturbing and harming wildlife during sensitive or active periods. The guidelines in the City of Ottawa's Protocol for Wildlife Protection During Construction (City of Ottawa, 2015) should be adhered to for the development. This requires no vegetation clearing between April 15 and July 31 and that undisturbed portions of the site should be inspected by a qualified biologist or environmental consultant prior to each day that site clearing is scheduled to assure that no nesting birds or other wildlife are harmed from construction activity. This will assure that the project is in adherence with applicable legislation such as the ESA, *Migratory Birds Convention Act* (MBCA) and *Fish & Wildlife Conservation Act* (FWCA).

The future development area and parking expansion in the north half of the Site (**Figure 5** - **Appendix A**) should be designed to retain as much of the cultural woodland (CUW), meadow marsh (MAM2-2) and thicket swamp (SWT2-2) (**Figure 2** - **Attachment A**) within and adjacent to these development areas that is feasible to preserve natural features on the Site. These retained areas could also be used to transplant and compensate for loss of Milkweed plants for Monarch Butterfly, which is the only plant used by Monarch for larval development.

Disturbance and/or removal of the wetlands on Site will require review and approval by the SNCA.

6.2.2 Indirect Impacts

Indirect impacts caused during construction such as noise, dust, sediment and chemical spills will be mitigated through implementation of provincial standard best management practices for construction sites such as the Ontario Provincial Standard Specifications (OPSS) and that are typically required as condition of development approval. Dust suppressants (i.e. water) will be used to manage airborne dust during dry months if required. Erosion control fencing will be installed around the Site to contain any sediment runoff. A Spills Prevention and Management Program should be implemented to prevent contamination of environmental receptors (soil, groundwater, offsite drains, etc.) during construction.

An ecological buffer should be established along the north boundary of the Site to minimize potential indirect impacts caused by the future parking and development area on the natural features north of the Site. The buffer would also will help to retain portions of the cultural woodland and thicket swamp on the Site. No significant ecological features and functions were identified in the cultural woodland and thicket swamp along the north boundary of the Site. A minimum buffer width of at least 15m shall be implemented to minimize indirect impacts from the development.

Measures to minimize impacts from de-icing salts on groundwater and potential downstream receiving natural systems can include implementing a salt management plan for the medical facility to reduce overall use of de-icing salts. This could include applying sand-salt mix to reduce chloride concentration and limiting application of de-icing salt to high risk areas. The location and management of snow storage for the access roads and parking areas could be planned so that salt-laden meltwater from snow piles is treated so downstream systems are not adversely impacted. Other measures to mitigate potential stormwater impacts can be assessed when stormwater management plans for the Site become available.

7 Conclusions and Recommendations

Based on the field surveys and impact assessment, the proposed development can occur without causing negative impacts to natural features identified on and adjacent to the Site. This conclusion takes into consideration implementation of the recommendations and mitigation measures discussed in Sections 6.2,



which are summarized as follows (the list is separated into different development stages to assist with planning and implementation):

Pre-construction

- 1. Establish a 15-metre buffer along the north boundary of the Site to help mitigate potential indirect impacts on the adjacent natural areas north of the Site (**Figure 6 Attachment A**). The buffer should remain in a natural undisturbed state indefinitely.
- 2. Configure site plans to minimize loss of the vegetation communities that fall within the proposed future parking expansion and development area in the north half of the Site.
- 3. Retain portions of vegetation communities that fall outside of the proposed development footprint shown in **Figure 6 Attachment A** and allow retained areas to remain undisturbed and naturalize / enhance with native plantings as needed.
- 4. The SNCA should be consulted prior to any disturbance or removal of the wetlands and ditches on the Site which could be subject to Ontario Regulation 170/06.
- 5. The MNRF Kemptville District Office should be consulted to further evaluate the possibility of the wetlands on Site being designated PSW based on the 750m wetland complexing rule.

During-construction

- 6. The guidelines in the City of Ottawa Protocol for Wildlife Protection During Construction (2016) shall be applied, which states no clearing of vegetation is to occur between April 15 and July 31 unless a qualified biologist has determined that no nesting is occurring within 5 days prior to the clearing. This mitigation measure will also help protect local wildlife during sensitive times such as spring and early summer when many animals are reproducing. Vegetation clearing should be undertaken such that existing connections to adjacent areas of natural habitat are maintained until the final stage of clearing so that wildlife can use the these connections to leave the site.
- 7. Install and maintain silt fencing around the perimeter of the development area prior to start of site construction. The fencing would follow the boundary of the 15-metre buffer recommended along the north boundary of the Site. The bottom of the silt fence should be firmly anchored or secured to the ground to avoid sediment from passing under the fence. The fencing would also serve as exclusion fencing to deter wildlife from entering the construction site.
- 8. Conduct site inspections of undisturbed areas on the Site at the start of each day that site clearing is scheduled. If wildlife (snake, turtle, mammal) are found, it should be gently 'herded' out of the construction area into the adjacent natural areas north of the Site. Removal of wildlife from the Site during site clearing and site inspections can be facilitated by creating 'wildlife escape gates' in sections of the silt fencing along the north Site boundary as illustrated in Figure 7 Appendix A. The gates (1m wide) should be opened and closed at the start and end of each day that site clearing is undertaken. The funnel design helps guide wildlife within the construction area to the gate. The proposed location of the wildlife escape gates are shown in Figure 6 Appendix A.
- 9. All onsite workers should be trained so they are aware of what species may be encountered, how to identify those species and safe handling procedures.
- 10. Implement standard best management practices (e.g. OPS 182, 518, 807) to mitigate potential noise, dust, erosion and pollution impacts for construction sites. This should include a Spills Prevention and Management Plan to prevent contamination of any environmental receptors. The plan would lay out requirements for preventing and responding to spills and leaks (i.e. designated refuelling areas, primary



and secondary fuel containment, sill clean-up kits, machinery maintenance program, spill absorption booms, etc.).

Post-construction

- 11. The retained portions of the existing vegetation communities on the Site that fall outside of the development footprint (Figure 6 Attachment A) can function as donor sites for transplanting and compensating the loss of Common Milkweed for Monarch Butterfly. This mitigation measure can be guided through development of a Milkweed Salvage and Transplanting Plan.
- 12. Implement a low-salt management plan and other best management practices to reduce use of deicing salts and chloride impacts to environmental receptors.

The above listed recommendations and mitigation measures should be considered as conditions of development approval, or other planning approval mechanism, to protect and conserve natural heritage features adjacent to and within the Site to the extent possible.

8 General Limitations

Information in this report is considered to be privileged and confidential and has been prepared exclusively for **Montfort Hospital** and **ZW Project Management**. The information presented in this document is based on baseline data designed to provide ecological information to support the client in proceeding forward with their proposed development application. The conclusions and recommendations presented within this report reflect Site conditions existing at the time of the investigation. Should changes occur that potentially impact the condition of the Site, the conclusions presented by EXP may require re-evaluation.

9 Closure

We trust this report is satisfactory for your purposes. Should you have any questions, please do not hesitate to contact this office.

Yours truly,

EXP Services Inc.

Angela Zhou, B.E.S. Biologist Environmental Services

Les Misch, B.E.S., Env. Tech. Senior Ecologist, Team Lead Environmental Services



10 References

- Bakowsky, W.D. 1996. Natural Heritage Resources of Southern Ontario: Vegetation Communities of Southern Ontario. Ontario Ministry of Natural Resources, Natural Heritage Information Centre.
- BSC. 2001. Ontario Breeding Bird Atlas Guide for Participants. Bird Studies Canada.
- BSC. 2008. Marsh Monitoring Program Participant's Handbook Surveying Amphibians. 2008 Edition. 20 pages. Published by Bird Studies Canada in cooperation with Environment Canada and the U.S. Environmental Protection Agency. February 2008.
- Cadman, M.D., D.A. Sutherland, G.G. Beck, D. Lepage, and A.R. Couturier (eds.). 2007. Atlas of the Breeding Birds of Ontario, 2001-2005. Bird Studies Canada, Environment Canada, Ontario Field Ornithologists, Ontario Ministry of Natural Resources, and Ontario Nature, Toronto, xxii + 706 pp.
- City of Ottawa. 2011. Characterization of Ottawa's Watersheds: An Environmental Foundation Document with Supporting Information Base. City of Ottawa.
- City of Ottawa. 2003. City of Ottawa Official Plan. Retrieved from http://ottawa.ca/en/city-hall/planningand-development/official-plan-and-master-plans/official-plan
- COSEWIC. 2012. COSEWIC. 2012. COSEWIC assessment and status report on the Eastern Wood-pewee Contopus virens in Canada. Committee on the Status of Endangered Wildlife in Canada. Ottawa. x + 39 pp. (www.registrelep-sararegistry.gc.ca/default_e.cfm).

Harding, J.H. 1997. Amphibians and Reptiles of the Great Lakes Region. University of Michigan Press.

- Lee, H.T, W.D. Bakowsky, J.L. Riley, J. Bowles, M. Puddister, P. Uhlig, and S. McMurray. 1998. Ecological Land Classification for Southern Ontario: First Approximation and its Application. Ontario Ministry of Natural Resources, Southcentral Region, Science Development and Transfer Branch. Technical Manual ELC-005.
- MNR (Ontario Ministry of Natural Resources). 2000. Significant Wildlife Habitat Technical Guide. Fish and Wildlife Branch, Wildlife Section. Science Development and Transfer Branch, Southcentral Sciences Section.
- MNR. 2010. Natural Heritage Reference Manual for Natural Heritage Policies of the Provincial Policy Statement, 2005. Second Edition. Toronto: Queen's Printer for Ontario. 248 pp.
- MNR. 2012. Categorizing and Protecting Habitat under the Endangered Species Act. 2007. Ministry of Natural Resources, Species at Risk Branch, Peterborough, Ontario.
- MNRF (Ontario Ministry of Natural Resources and Forestry). 2014a. Significant Wildlife Habitat Mitigation Support Tool. Version 2014. Ontario Ministry of Natural Resources and Forestry, Resources Section.
- MNRF. 2014b. Ontario Wetland Evaluation System Southern Manual. 3rd Edition (Version 3.3). Ontario Ministry of Natural Resources and Forestry. Queen's Printer for Ontario.



- MNRF. 2015a. Natural Heritage Mapping Web Application. Natural Heritage Information Centre. http://www.giscoeapp.lrc.gov.on.ca/web/MNR/NHLUPS/NaturalHeritage/Viewer/Viewer.html
- MNRF. 2015b. Significant Wildlife Habitat Criteria Schedules for Ecoregion 6E. 2015. Addendum to Significant Wildlife Habitat Technical Guide. Ontario Ministry of Natural Resources and Forestry, Peterborough, Ontario.
- MNRF. 2016a. Ontario Vascular Plants List. Natural Heritage Information Centre. 26 August 2016 version. Available online at https://www.ontario.ca/page/get-natural-heritage-information
- MNRF. 2016b. Survey Protocol for Ontario's Species at Risk Snakes. Ontario Ministry of Natural Resources and Forestry, Species Conservation Policy Branch. Peterborough, Ontario. ii + 17 pp.
- Muncaster Environmental Planning and Brunton Consulting. 2005. City of Ottawa Urban Natural Areas Environmental Evaluation Study (Final Report). A report prepared for the Environmental Management Division, Planning & Growth Management Department, City of Ottawa.

Oldham, M. J., W. D. Bakowsky and D. A. Sutherland. 1995. Floristic Quality Assessment System for Southern Ontario. Natural Heritage Information Centre, Ministry of Natural Resources. Peterborough, Ontario.


- OMAFRA (Ontario Ministry of Agriculture, Food and Rural Affairs). 2017. Agricultural Information Atlas. https://www.gisapplication.lrc.gov.on.ca/AIA/index.html?viewer=AIA.AIA&locale=en-US
- Ontario Nature. 2017. Reptiles and Amphibians of Ontario. Retrieved from https://www.ontarionature.org/protect/species/reptiles_and_amphibians/index.php#top



2225 Mer Bleue Road, Ottawa, Ontario Environmental Impact Study OTT-00239983-A0 September 2018


Appendix A: Figures







X:\DRAWINGS\239000\239983\239983\239883\239883\239883\2012Y 14 2017\OTT-00239983-A0.dwg














2225 Mer Bleue Road, Ottawa, Ontario Environmental Impact Study OTT-00239983-A0 September 2018

Appendix B: Agency Response



Kemptville District

10 Campus Drive Postal Box 2002 Kemptville ON K0G 1J0 Tel.: 613 258-8204 Fax: 613 258-3920

Ministère des Richesses naturelles et des Forêts

District de Kemptville

10, promenade Campus Case postale, 2002 Kemptville ON K0G 1J0 Tél.: 613 258-8204 Téléc.: 613 258-3920



Tue. Jul 18, 2017

Matthew Ross exp Services Inc. 1595 Clark Boulevard Brampton, Ontario L6T 4V1 (905) 793-9800 matt.ross@exp.com

Attention: Matthew Ross

Subject:Information Request - DevelopmentsProject Name:Montfort Hospital EISSite Address:2225 Mer-Bleue Road, Orleans, ONOur File No.2017_CUM-4096

Natural Heritage Values

The Ministry of Natural Resources and Forestry (MNRF) Kemptville District has carried out a preliminary review of the above mentioned area in order to identify any potential natural resource and natural heritage values.

The following Natural Heritage values were identified for the general subject area:

• Stream, McKinnons Creek

Municipal Official Plans contain information related to natural heritage features. Please see the local municipal Official Plan for more information, such as specific policies and direction pertaining to activities which may impact natural heritage features. For planning advice or Official Plan interpretation, please contact the local municipality. Many municipalities require environmental impact studies and other supporting studies be carried out as part of the development application process to allow the municipality to make planning decisions which are consistent with the Provincial Policy Statement (PPS, 2014).

The MNRF strongly encourages all proponents to contact partner agencies and appropriate municipalities early on in the planning process. This provides the proponent with early knowledge regarding agency requirements, authorizations and approval timelines; Ministry of the Environment and Climate Change (MOECC) and the local Conservation Authority may require approvals and permitting where natural values and natural hazards (e.g., floodplains) exist.

Kemptville District

10 Campus Drive Postal Box 2002 Kemptville ON K0G 1J0 Tel.: 613 258-8204 Fax: 613 258-3920 Ministère des Richesses naturelles et des Forêts

District de Kemptville



10, promenade Campus Case postale, 2002 Kemptville ON K0G 1J0 Tél.: 613 258-8204 Téléc.: 613 258-3920

As per the Natural Heritage Reference Manual (NHRM, 2010) the MNRF strongly recommends that an ecological site assessment be carried out to determine the presence of natural heritage features and species at risk and their habitat on site. The MNRF can provide survey methodology for particular species at risk and their habitats.

The NHRM also recommends that cumulative effects of development projects on the integrity of natural heritage features and areas be given due consideration. This includes the evaluation of the past, present and possible future impacts of development in the surrounding area that may occur as a result of demand created by the presently proposed project.

In Addition, the following Fish species were identified: Carps and Minnows, Sunfishes ,bluegill, bluntnose minnow, brassy minnow, brook stickleback, brown bullhead, central mudminnow, common shiner, creek chub, emerald shiner, fathead minnow, finescale dace, golden shiner, johnny darter, johnny darter/tesselated darter, logperch, longnose dace, mimic shiner, muskellunge, northern pike, northern redbelly dace, pearl dace, pumpkinseed, rock bass, rosyface shiner, trout-perch, white sucker.

Wildland Fire

MNRF woodland data shows that the site contains woodlands. The lands should be assessed for the risk of wildland fire as per PPS 2014, Section 3.1.8 "Development shall generally be directed to areas outside of lands that are unsafe for development due to the presence of hazardous forest types for wildland fire. Development may however be permitted in lands with hazardous forest types for wildland fire where the risk is mitigated in accordance with wildland fire assessment and mitigation standards". Further discussion with the local municipality should be carried out to address how the risks associated with wildland fire will be covered for such a development proposal. Please see the Wildland Fire Risk Assessment and Mitigation Guidebook (2016) for more information.

Significant Woodlands

Section 2.1.5 b) of the PPS states: Development and site alteration shall not be permitted in significant woodlands unless it has been demonstrated that there will be no negative impacts on the natural features or their ecological functions. The 2014 PPS directs that significant woodlands must be identified following criteria established by the Ontario Ministry of Natural Resources and Forestry, i.e. the Natural Heritage Reference Manual (NHRM), 2010. Where the local or County Official Plan has not yet updated significant woodland mapping to reflect the 2014 PPS, all wooded areas should be reviewed on a site specific basis for significance. The MNRF Kemptville District modelled locations of significant woodlands in 2011 based on NHRM criteria. The

Kemptville District

10 Campus Drive Postal Box 2002 Kemptville ON K0G 1J0 Tel.: 613 258-8204 Fax: 613 258-3920 Ministère des Richesses naturelles et des Forêts

District de Kemptville



10, promenade Campus Case postale, 2002 Kemptville ON K0G 1J0 Tél.: 613 258-8204 Téléc.: 613 258-3920

presence of significant woodland on site or within 120 metres should trigger an assessment of the impacts to the feature and its function from the proposed development.

Significant Wildlife Habitat

Section 2.1.5 d) of the PPS states: Development and site alteration shall not be permitted in significant wildlife habitat unless it has been demonstrated that there will be no negative impacts on the natural features or their ecological functions. It is the responsibility of the approval authority to identify significant wildlife habitat or require its identification. The MNRF has several guiding documents which may be useful in identification of significant wildlife habitat and characterization of impacts and mitigation options:

- Significant Wildlife Habitat Technical Guide, 2000
- The Natural Heritage Reference Manual, 2010
- Significant Wildlife Habitat Mitigation Support Tool, 2014
- Significant Wildlife Habitat Criteria Schedule for Ecoregion 5E and 6E, 2015

The habitat of special concern species (as identified by the Species at Risk in Ontario list) and Natural Heritage Information Centre tracked species with a conservation status rank of S1, S2 and S3 may be significant wildlife habitat and should be assessed accordingly.

Water

If any in-water works are to occur, there are timing windows for which work in water should not take place (see below). Appropriate measures should be taken to minimize and mitigate impact on water quality and fish habitat, including:

- installation of sediment and erosion control measures;
- avoiding the removal, alteration, or covering of substrates used for fish spawning, feeding, over-wintering or nursery areas; and
- debris control measures to manage falling debris (e.g. spalling).

Timing windows (no in-water works) in MNRF Kemptville District*:

Warmwater and cool water	\rightarrow March 15 – June 30
St. Lawrence River & Ottawa River	\rightarrow March 15 – July 15
Coldwater	→ October 1 – May 31
Big Rideau Lake & Charleston Lake	→ October 1 – June 30

* Please note: Additional timing restrictions may apply as they relate to endangered and threatened species for works in both water and wetland areas.

Timing windows when in-water work is restricted – based on species presence:

Kemptville District

10 Campus Drive Postal Box 2002 Kemptville ON K0G 1J0 Tel.: 613 258-8204 Fax: 613 258-3920

Ministère des Richesses naturelles et des Forêts

District de Kemptville



10, promenade Campus Case postale, 2002 Kemptville ON K0G 1J0 Tél.: 613 258-8204 Téléc.: 613 258-3920

	FISH SPECIES	TIMING WINDOW (No in-water works)
Spring:	Walleye	March 15 to May 31
	Northern Pike	March 15 to May 31
	Lake Sturgeon	May 1 to June 30
	Muskellunge	March 15 to May 31
	Largemouth/Smallmouth Bass	May 1 to July 15
	Rainbow Trout	March 15 to June 15
	Other /Unknown Spring Spawning Species	March 15 to July 15

Fall:

FISH SPECIES	TIMING WINDOW (No in-water works)	
Lake Trout	October 1 to May 31	
Brook Trout	October 1 to May 31	
Pacific Salmon	September 15 to May 31	
Lake Whitefish	October 15 to May 31	
Lake Herring	October 15 to May 31	
Other /Unknown Fall Spawning Species	October 1 to May 31	

Additional approvals and permits may be required under the Fisheries Act. Please contact Fisheries and Oceans Canada to determine requirements and next steps. There may also be approvals required by the local Conservation Authority or Transport Canada. As the MNRF is responsible for the management of provincial fish populations, we request ongoing involvement in such discussions in order to ensure population conservation.

Species at Risk

A review of the Natural Heritage Information Centre (NHIC) and internal records indicate that there is a potential for the following threatened (THR) and/or endangered (END) species on the site or in proximity to it:

- Bobolink (THR)
- Butternut (END)
- Eastern Meadowlark (THR)
- Henslow's Sparrow (END)
- Sensitive Species (END)
- Barn Swallow (THR)
- Little Brown Bat (END)
- Northern Long-eared Bat (END)
- Tri-Colored Bat (END)

Kemptville District

10 Campus Drive Postal Box 2002 Kemptville ON K0G 1J0 Tel.: 613 258-8204 Fax: 613 258-3920 Ministère des Richesses naturelles et des Forêts

District de Kemptville



10, promenade Campus Case postale, 2002 Kemptville ON K0G 1J0 Tél.: 613 258-8204 Téléc.: 613 258-3920

All endangered and threatened species receive individual protection under section 9 of the ESA and receive general habitat protection under Section 10 of the ESA, 2007. Thus any potential works should consider disturbance to the individuals as well as their habitat (e.g. nesting sites). General habitat protection applies to all threatened and endangered species. Note some species in Kemptville District receive regulated habitat protection. The habitat of these listed species is protected from damage and destruction and certain activities may require authorization(s) under the ESA. For more on how species at risk and their habitat is protected, please see: https://www.ontario.ca/page/how-species-risk-are-protected.

If the proposed activity is known to have an impact on any endangered or threatened species at risk (SAR), or their habitat, an authorization under the ESA may be required. It is recommended that MNRF Kemptville be contacted prior to any activities being carried out to discuss potential survey protocols to follow during the early planning stages of a project, as well as mitigation measures to avoid contravention of the ESA. Where there is potential for species at risk or their habitat on the property, an Information Gathering Form should be submitted to Kemptville MNRF at <u>sar.kemptville@ontario.ca</u>.

The Information Gathering Form may be found here: <u>http://www.forms.ssb.gov.on.ca/mbs/ssb/forms/ssbforms.nsf/FormDetail?OpenForm&ACT=RDR&T</u> <u>AB=PROFILE&ENV=WWE&NO=018-0180E</u>

For more information on the ESA authorization process, please see: https://www.ontario.ca/page/how-get-endangered-species-act-permit-or-authorization

One or more special concern species has been documented to occur either on the site or nearby. Species listed as special concern are not protected under the ESA, 2007. However, please note that some of these species may be protected under the Fish and Wildlife Conservation Act and/or Migratory Birds Convention Act. Again, the habitat of special concern species may be significant wildlife habitat and should be assessed accordingly. Species of special concern for consideration:

- Common Nighthawk (SC)
- Short-eared Owl (SC)
- Snapping Turtle (SC)

If any of these or any other species at risk are discovered throughout the course of the work, and/or should any species at risk or their habitat be potentially impacted by on site activities, MNRF should be contacted and operations be modified to avoid any negative impacts to species at risk or their habitat until further direction is provided by MNRF.

Kemptville District

10 Campus Drive Postal Box 2002 Kemptville ON K0G 1J0 Tel.: 613 258-8204 Fax: 613 258-3920 Ministère des Richesses naturelles et des Forêts

District de Kemptville



10, promenade Campus Case postale, 2002 Kemptville ON K0G 1J0 Tél.: 613 258-8204 Téléc.: 613 258-3920

Please note that information regarding species at risk is based largely on documented occurrences and does not necessarily include an interpretation of potential habitat within or in proximity to the site in question. Although this data represents the MNRF's best current available information, it is important to note that a lack of information for a site does not mean that additional features and values are not present. It is the responsibility of the proponent to ensure that species at risk are not killed, harmed, or harassed, and that their habitat is not damaged or destroyed through the activities carried out on the site.

The MNRF continues to strongly encourage ecological site assessments to determine the potential for SAR habitat and occurrences. When a SAR or potential habitat for a SAR does occur on a site, it is recommended that the proponent contact the MNRF for technical advice and to discuss what activities can occur without contravention of the Act. For specific questions regarding the Endangered Species Act (2007) or SAR, please contact MNRF Kemptville District at sar.kemptville@ontario.ca.

The approvals processes for a number of activities that have the potential to impact SAR or their habitat have recently changed. For information regarding regulatory exemptions and associated online registration of certain activities, please refer to the following website: https://www.ontario.ca/page/how-get-endangered-species-act-permit-or-authorization.

Please note: The advice in this letter may become invalid if:

- The Committee on the Status of Species at Risk in Ontario (COSSARO) re-assesses the status of the above-named species OR adds a species to the SARO List such that the section 9 and/or 10 protection provisions apply to those species; or
- Additional occurrences of species are discovered on or in proximity to the site.

This letter is valid until: Wed. Jul 18, 2018

The MNRF would like to request that we continue to be circulated on information with regards to this project. If you have any questions or require clarification please do not hesitate to contact me.

Sincerely,

Dom Ferland Management Biologist dom.ferland@ontario.ca

Encl.\ -ESA Infosheet

Kemptville District

10 Campus Drive Postal Box 2002 Kemptville ON K0G 1J0 Tel.: 613 258-8204 Fax: 613 258-3920

Ministère des Richesses naturelles et des Forêts

District de Kemptville

10, promenade Campus Case postale, 2002 Kemptville ON K0G 1J0 Tél.: 613 258-8204 Téléc.: 613 258-3920



-NHIC/LIO Infosheet

2225 Mer Bleue Road, Ottawa, Ontario Environmental Impact Study OTT-00239983-A0 September 2018

Appendix C: Field Survey Forms



Breeding Bird Point Count Survey Form Project Number: Project Name: Date: Mer-Bleue JUNE 7/17-239983 Start Time (24hr): End Time (24hr): 739Surveyor: M.Ross 6:50 Wind Code¹: Precip. last 24hrs: Precip. Code²: Temp. (°C): Cloud Cover (%): 🗹 Yes 1 O O¹ Wind Codes (Beaufort Wind Scale) Status Codes † - Rare species § - Colonial Species Wind Speed (km/h) Description Visual Cues 0 **Breeding Codes** <1 Calm Smoke rises vertically OBSERVED 1-5 Light 1 Smoke drifts X - Species observed in its breeding season (no evidence of breeding) 2 Light Breeze POSSIBLE: 6-11 Leaves rustle H - Species observed in breeding season in suitable nesting habitat 3 12-19 Gentle Breeze Lighter branches sway - Singing male present or breeding calls heard in breeding season in s suitable nesting habitat 4 20-28 Moderate Breeze Dust rises, branches move PROBABLE: P - Pair observed in their breeding season in suitable nesting habitat 5 29-38 Fresh Breeze Small trees sway T - Permanent territory presumed through registration of territorial song or presence of adult bird in breeding habitat on at least 2 days, one week or 6 39-48 Strong Breeze Larger branches move more apart at the same place. D - Courtship or display between a male and a female or 2 mates including courtship feeding or copulation ² Precipitation Codes V - Visiting probable nest site A - Agitated behaviour or anxiety calls of an adult 0 No precipitation 4 Thunderstorm B - Brood Patch on adult female or cloacal protuberance on adult male Fog/Mist 5 Snow 1 N - Nest building or excavation of nest hole 2 Light rain 6 Freezing rain CONFIRMED: 3 Heavy rain DD - Distraction display or injury feigning NU - Used nest or egg shell found (occupied/laid during atlas period) FY - Recently fledged young or downy young AE - Adults leaving or entering nest site in circumstances indicating occupied nest FS - Adult carrying faecal sac CF - Adult carrying food for young NE - Nest containing eggs NY - Nest with young seen or heard Station#: Start time: 658 - 7:08 Feature: 1 Direction: UTM: 0461063 - 5032701 NE Species Count & distance(m) Breeding <50 50-100 >100 evidence 66 YWAR. 5 RWBL H H KILL Sof 2 2 • B SWSP 56 ρ 2 WIFL INIFL 4 i 4 4 AM60 Rua YUAR At160 (WAIS *е* 505Р Susp KILL

Date: JUNE 7/17

WIFL " SOSP " RWBL " WISN SWSP SOSE YMAR " TWAR	*		Breeding evidence S A A A D, U S S S A A S S	NE SWSP WIFE FUBL YMAR FINGO YWAR YWAR SOFF SOFF
WIFL SOSP PWBL WISN SWSP SOSP YMAR YWAR	¢		S A A A A S S	SWSP WIFL FUBL HUAR AMGO HUAR HUAR Starsp
SOSP RWBL WISN SWSP SOSP YWAR YWAR	• • • • • • • • • • • • • • • • • • •		A A A D V S S S A S	SWSP WIFL FUBL YWAR AMGO YWAR YWAR Sousp
RWBL ": WISN SWSP SOSP YWAR YWAR	• • • •		A A D. U S S A A S	SWSP WIFL FUBL YMAR AMGO YWAR YWAR Souspe
KWBC WISN SWJP SOSE YMAR YWAR	•		A D. U S S A S	YWAR YWAR Sorge
WISN SWSP SOSP YWAR YWAR	0		S S A S	YWAR YWAR Sorge
SWSP SOSP YWAR YWAR	<i>₽</i>		S S A S	YWAR YWAR Sorge
Sose Yhar " YWAR			A S	YWAR YWAR Sorge
YWAR "			A S	YWAR YWAR Sosp
YWAR			2	TWAK YEAR Storyp
AM 65 *			5	
				Sold Sold Sold Sold Sold Sold Sold Sold
			1	
	1			
				CUISA
TM: Species	Count & dis	tance(m)	Breeding	
	50 50-10		evidence	
			··· ··· ···	
		-		
-				
	* 		1	

				• • • • • • • • • • • • • • • • • • •
···				
			+	
1			+	
			+	
·····				
		1		

·

Surveyor's Initials:

MR.

Date: JUNE 7/17

Breeding Bird Survey Form (Southern Ontario)



Project Name: Mer - Ble	Lul		Project Number: 239983	Dat	e: June 7/17
Surveyor: M. Ross		S	Start Time (24hr):	End	 Time (24hr): の:15
Temp. (°C):	Wind Code1:	Cloud Cover	(%): Precip. last	: 24hrs: □ No	Precip. Code ² :

.

<u> </u>		Br	eedir	ig Co	de ³			Br	eedir	ng Co	de ³
Species	Polygon(s)	OB	PO	PR	со	Species	Polygon(s)	OB	PO	PR	СО
Canada Goose						Yellow-billed Cuckoo					
Wood Duck						Black-billed Cuckoo					
Mallard					FY	Eastern Screech-Owl					
Green-winged Teal						Great Horned Owl					
Ring-necked Pheasant						Common Nighthawk					
Ruffed Grouse						Chimney Swift				1	
Wild Turkey						Ruby-throated Hummingbird					
American Bittern						Belted Kingfisher					
Great Blue Heron						Red-headed Woodpecker					
Great Egret						Red-bellied Woodpecker					
Green Heron						Yellow-bellied Sapsucker		ĺ			
Black-crowned Nt-Heron						Downy Woodpecker					
Turkey Vulture	<u></u>					Hairy Woodpecker	3		Н		
Osprey						Northern Flicker		· · · · ·		İ –	
Bald Eagle						Pileated Woodpecker				+	<u> </u>
Northern Harrier				······		Eastern Wood-Pewee					
Sharp-shinned Hawk						Alder Flycatcher					
Cooper's Hawk						Willow Flycatcher	2		S		
Red-shouldered Hawk						Least Flycatcher	3		5		<u> </u>
Broad-winged Hawk						Eastern Phoebe					
Red-tailed Hawk						Great Crested Flycatcher					
American Kestrel						Eastern Kingbird					
Merlin						Warbling Vireo	3		5		1
Peregrine Falcon						Philadelphia Vireo					1
Virginia Rail				1		Red-eyed Vireo			<u> </u>		-
Sora						Gray Jay					1
American Coot						Blue Jay					1
Sandhill Crane		·····				American Crow	3	1	H		<u> </u>
Killdeer	1		Н			Common Raven				1	
Spotted Sandpiper			<u> </u>			Horned Lark				1	
Upland Sandpiper						Purple Martin			<u> </u>	1	
Wilson's Snipe	1,3		Ð			Tree Swallow	3		Н	1	
American Woodcock						N. Rough-winged Swallow			1		
Ring-billed Gull						Bank Swallow					
Herring Gull			·			Cliff Swallow		<u> </u>			
Common Tern						Barn Swallow	1				1
Rock Pigeon			<u> </u>			BI-capped Chickadee			-		-
Mourning Dove			1			Red-breasted Nuthatch					†
White-breasted Nuthatch			···			Common Yellowthroat	1,3		5		ĺ

Breeding Bird Survey Form (Cont'd)

Species	Polygon(s)	OB	PO	PR	CO	Species	Polygon(s)	OB	PO	PR	CO
Brown Creeper						Scarlet Tanager					
Carolina Wren						Eastern Towhee					
House Wren	3		2			Chipping Sparrow					
Winter Wren						Field Sparrow					
Marsh Wren						Vesper Sparrow					
Blue-gray Gnatcatcher						Savannah Sparrow					
Eastern Bluebird						Grasshopper Sparrow					
Veery	3		5			Song Sparrow	1,2		A		
Swainson's Thrush						Swamp Sparrow	1,2	:	S		
Hermit Thrush						White-throated Sparrow					
Wood Thrush						Dark-eyed Junco					
American Robin	2		Н			Northern Cardinal					
Gray Catbird	3		Н			Rose-breasted Grosbeak					
Northern Mockingbird						Indigo Bunting					
Brown Thrasher						Bobolink					
European Starling						Red-winged Blackbird	1,2		A		
Cedar Waxwing						Eastern Meadowlark					
Blue-winged Warbler						Common Grackle					
Golden-winged Warbler						Brown-headed Cowbird					
Nashville Warbler						Baltimore Oriole					
Yellow Warbler	3,1,2		and the second second	A		House Finch					
Chestnut-sided Warbler	, ,					American Goldfinch	3,1,2		2		
Black-thr. Blue Warbler				}		House Sparrow					
Yellow-rumped Warbler											
Black-thr. Gr. Warbler				1		Additional Species:	Polygon(s)	ОВ	PO	PR	со
Black-and-white Warbler						-ttz	1		1-1-1-		
American Redstart											
Ovenbird									1		
Northern Waterthrush											
Mourning Warbler											

1	Vind Codes (Beaufort Win	d Scale)	
<u> </u>	Wind Speed (km/h)	Description	Visual Cues
0	<1	Calm	Smoke rises vertically
1	1-5	Light	Smoke drifts
2	6-11	Light Breeze	Leaves rustle
3	12-19	Gentle Breeze	Lighter branches sway
4	20-28	Moderate Breeze	Dust rises, branches move
5	29-38	Fresh Breeze	Small trees sway
6	39-48	Strong Breeze	Larger branches move

² P	recipitation Codes		
0	No precipitation	4	Thunderstorm
1	Fog/Mist	5	Snow
2	Light rain	6	Freezing rain
3	Heavy rain		

Status Codes s § - Colonial Species † - Rare species

Breeding Codes

- OBSERVED: X - Species observed in its breeding season (no evidence of breeding) POSSIBLE:
- A Species observed in breeding season in suitable nesting habitat
 S Singing male present or breeding calls heard in breeding season in
- suitable nesting habitat
- PROBABLE:
- P Pair observed in their breeding season in suitable nesting habitat
 T Permanent territory presumed through registration of territorial song or presence of adult bird in breeding habitat on at least 2 days, one week or more apart at the same place.
- D Courtship or display between a male and a female or 2 males including courtship feeding or copulation
- V Visiting probable nest site
- A Agitated behaviour or anxiety calls of an adult
 B Brood Patch on adult female or cloacal protuberance on adult male

- B Brood Paten on addit tensile or cloacal protuberance on addit mate
 N Nest building or excavation of nest hole
 CONFIRMED:
 DD Distraction display or injury feigning
 NU Used nest or egg shell found (occupied/laid during atlas period)
 FY Recently fledged young or downy young
 AE Adults leaving or entering nest site in


- circumstances indicating occupied nest

- CFC + Adult carrying faceal sac CF + Adult carrying food for young NE Nest containing eggs NY Nest with young seen or heard

MK

Date: _____ due 7/17

Montfort Hospital EIS



2225 Mer-Bleue Rd., Ottawa, ON

< 1 = Photo location / Directron



• Polygon ID		CV	W					2	Sup	pleme	ntal	Plar	nt Sp	ecie	s Lis	t		Page / of /
Date	J	Une	.7.	/17	L			1	Waypoint(s)									· · · · · · · · · · · · · · · · · · ·
'ime	9.	'3E)	•					Photo(s)									
lant species list for ele									plant species list fo									
O species code		>10	2-10	0.5-2	0,5-0	0	0-0,5	>0,5	species co	de	>10	2-10	0.5-2	0,5-0	0	0-0,5	>0.5	Notes:
POPTREM		A					<u> </u>		*******									old asphalt
ACENEFU CORSTOL			R															pathways thro
CORSTOL				A								L						polygon;
PARTHERLOCK	5.150	۲.			O		ļ											old asphalt pathways thro polygon; Pome govbage
FRAVIR.G					A													. 0 0
EQUARIE					A													
LOTCORN					A													
VICCRAC					0													
PORDELT	м. С	D																
SALPETT			0					-										
SALDEBB PHARUN BPALBA			0															
PHAARUN				A														
OPALBA		6	Ò															
DAUCARO					6													
VITRIPA					R													
onlicera sp				0			· · · ·											
SOLCAN					A													
Comm M. Itweed	<u></u> λ				Ø								1					
CARERIN				0														
CARSCOP				Ø														
JUM AMER			R	\circ														
BARAT				A							···							
A-ICCERT					ð	-						<u> </u>						
CHRLEUC					R							<u> </u>						
												$\left \right $	 					
												<u> </u>						
											+		1	<u> </u>				
		-		 							-							
														-				
		-		 														
											<u> </u>							
												<u> </u>	<u> </u>				$\left - \right $	
											<u> </u>	<u> </u>		<u> </u>	<u> </u>			
											-						 	

•

. . .

• .

• Polygon		Sv	J	2-	2				Su	ppleme	ntal	Plan	t Sp	ecie	s Lis	t		Page of /
Polygon Date	Jen	7	-/1	7				 1	Waypoint(s)									
Time	7:	29		·					Photo(s)									
plant species list fo	L								plant species list fo	or element #								
Species control			2-10	0,5-2	0,5-0	0	0-0,5	>0,5		and the second sec		2-10	0.5-2	0,5-0	0	0-0.5	>0,5	Notes:
SALPETI			D		1													orcasional
PHAARUN				A														Occasional pooling of c
SEICTE				A														, in the second
N.L. Mendan	iswet			0					-									
<u> </u>		timesee a		1-5														
CAPGRAC				0														
GARSCOP				Ø														
VICCRAC				2	R													
Galiomsp FRAVIRG				0	0													
POAPRAT					0													
				R	<u> </u>													
Tall Butter	1			·[
Cicuta Sp.	a Z I		<u> </u>	R														
TYPLATI)			0														
Dock sp.				0														
EQUARVE	In the f				0													
SALDEBB			Ø			 												
CORSTOL			ļ	0			ļ											
CARVULP				ļ	0													
				<u> </u>														-
																		- ·
																,		ļ
LULL																		
																		1
																		4
			1															1
											<u> </u>							1
																		1
				<u> </u>														
				<u> </u>														-
												<u> </u>	<u> </u>					-
												<u> </u>	<u> </u>	<u></u>				-
					1		1										1	

Polygon ID Date	(Dr	NA	M	2-7	}_				Sur	pleme	ntal	Plan	it Sp	ecie	s Lis	t		Page of
Date	Jun	27	2/[7					Waypoint(s)									
Time	7:	10		<u>.</u>					Photo(s)									
plant species list for e					•				plant species list fo									
species code	and from many sector and and a	>10	2-10	NY ACON NY	0,5-0	Q	0-0,5	>0,5	species co	de	>10	2-10	0,5-2	0,5-0	O	0-0,5	>0.5	Notes:
PHAARUN	[D														occ. wate
PHRAUST				R	_													pooling
TYPLATI				0														floodly O
TYPLATI POPALBA			R															Pooling; Ploveling; Ploveling @ South and poly gon
VICGRAC					0													20/2 gon
SCICYPE				0														[°°) 0
PHLPRAT				R														
Common milk	weed				0													
-COTCORN		-			A													
COMMON MILK - COTCORN SOLCANO				0														
CARVULP		1			0								l					
FRAURE					0													
EOLIARUE					Ø	·							1					
Cicula se	£. 4			0														
EQUARVE CICULA SP.	1				R													
CHRLEUC			· ·		0													
CARGRAC				0	0									[· ·	
				<u> </u>														
																<u> </u>		
																	· · ·	
		<u> </u>																
													<u> </u>					
													-					
			-															
			-			 								<u> </u>		<u> </u>		
				 							<u> </u>		<u> </u>			<u> </u>		
						<u> </u>					<u> </u>		<u> </u>					
			ļ			<u> </u>					<u> </u>	ļ	ļ	<u> </u>				
				ļ	ļ	ļ									ļ	<u> </u>		
					<u> </u>						<u> </u>			ļ	<u> </u>			
														<u> </u>	<u> </u>			

Wildlife Habitat Survey Form*

Wildlife Habitat Survey For	m*						*exp
Project Name: Mer-Bleve Kd						Date: Ju	
Project Number: 239983	Survey	or Name	· M.Ko.	55	titt an tha da dha Tartan an Inn an an an ann an an dùr ann an	Site ID: /	(MAM 2 -
Seasonal Concentration Areas							
	Potent	ial C	onfirmed			Potential	Confirmed
Deer yarding / congregation area (DY)	0		0	🔀 Snake hibernad	culum (SH)	\otimes	\bigcirc
Wild turkey winter habitat (WW)	0		0	Bat maternity r	roost / colony (BM)	\circ	\bigcirc
Raptor wintering area (RW)	0		0		g bird habitat (CN)	0	\bigcirc
Turtle wintering area (TW)	0		0		atory stopover (SS)	0	\bigcirc
Bat hibernaculum (BH)	Õ		Õ		over/staging area (W	\sim	Õ
Specialized Habitat							
	Potent	ial C	onfirmed			Potential	Confirmed
Area-sensitive species habitat (AS)	C	1	0	Materfowl nec	ting habitat (WN)	\circ	0
Woodland raptor nesting (WR)		1	ŏ	_		õ	Õ
	\bigcirc		\smile		Eagle habitat (OB)	000	00000
 High plant / animal diversity (HD) Foraging area with abundant mast (FA) 					eding habitat (AB)	\tilde{O}	$\tilde{\circ}$
				Turtle nesting		$\tilde{\circ}$	$\tilde{\circ}$
Mature forest stand (MF)	- [Fish habitat (F		$\tilde{\mathbf{O}}$	$\tilde{\circ}$
High habitat diversity (HD): (Select all that apply below)				Mink denning s		0	\bigcirc
Forest stratification	ning site	/snags		licro/macro-topography owned woody debris/log	Deer/wildli Supercano		to mate to the function of the second
Habitat of Species of Conservation	Conce	rn					
						Potential	Confirmed
Marsh breeding bird habitat (MB)						O	0
Woodland area-sensitive bird breeding ha	abitat (\	NB)				\bigcirc	0
Open country bird breeding habitat (OC)						Ö	Ö
Shrub/early successional bird breeding h	abitat (f	EB)				Q	Ö
Special concern and rare species habitat	(SC)					${}^{\textcircled{\stateset}}$	0
Terrestrial crayfish habitat (TC)							
Linkages and Movement Corridors							
						Potential	Confirmed
Close proximity to other natural features	(CP)		🗍 Man	nmal movement corridor	(MC)	\bigcirc	\bigcirc
Natural linkage/ecological stepping stone	e (NL)		_	etofauna movement cor		\circ	\bigcirc
Incidental Wildlife Observations	EV	POL				EV	POLYGON
Cabbage white	OB	l					
				·			
	· · · · · · · · · · · · · · · · · · ·			Evidence Codes (EV): SM - Singing male DD - Distraction T- Territory A - Anxiety D- Display	NE - Eggs AE - Nest entry NU - Used Nest NY - Young FY - Fledged young	OB - Observ DP - Distinc TK - Tracks VO - Vocali HO - House	tive parts zation

*Habitat features based on SWHTG (MNR 2000). 'Potential' and 'Confirmed' used for features that may or may not be identifiable durine survey. With exception to Habitat of Species of Conservation Concern, 'Confirmed' refers to presence of habitat and not 'Confirmed SWH' as defined in MNR (2000 & Draft 2012).

Broading Rind Daint Count Survey Form

Bre	eding B	ird Poir	nt Cou	nt Surve	ey Form			[«] exp.
Project N 97	lame: Mer-	Blene R	ZJ			Project I	Number:	Date: June 20/17
Surveyo	" M.Ross					Start Tin	ne (24hr):	End Time (24hr):
Temp. (°		Wind	Code ¹ :		Cloud Cove		Precip. last 24hrs	
	14		3		100	. ,	E Yes D No	1 -
L	odes (Beaufort Wi	ind Scale)			·····	Γ	† - Rare species	Status Codes
Wind	Speed (km/h)	Descrip	tion	Visual	Cues		i - Kare species	§ - Colonial Species
0	<1	Calm		Smoke	e rises vertically		BSERVED:	treeding Codes
1	1-5	Light		Smoke		:	X - Species observed in its bree	ding season (no evidence of breeding)
2	6-11	Light Br			s rustle	I ,	POSSIBLE: H - Species observed in breedin	g season in suitable nesting habitat
3	12-19	Gentle E	Breeze	Lighter	r branches swa		S - Singing male present or bree	ading calls heard in breeding season in
4	20-28		e Breeze		ses, branches	1 1	suitable nesting habitat PROBABLE:	
5	29-38	Fresh B		*	trees sway		F - Permanent territory presume	ng season in suitable nesting habitat ad through registration of territorial song or
6	39-48	Strong E	Breeze	Larger	branches mov	1	more apart at the same place	
2 Procini	tation Codes		·····.				 Courtship or display betwee including courtship feeding 	n a male and a female or 2 males or copulation
· · ·	recipitation	4 Thunder	storm				 V - Visiting probable nest site A - Agitated behaviour or anxie 	ly calls of an adult
1 Fog/		5 Snow	stonn			E	Brood Patch on adult female	or cloacal protuberance on adult male
2 Light		6 Freezing	rain				N - Nest building or excavation CONFIRMED:	of nest hole
3 Heav	y rain					1 1	DD - Distraction display or inju	ry feigning nd (occupied/laid during allas period)
						E	 Y - Recently fledged young or AE - Adults leaving or entering chreumstances indicating o Y - Adult carrying faceal sac Y - Adult carrying food for you Vest containing eggs Y - Nest with young seen or h 	nest site in
	: 1 61063-503:		$\hat{\mathcal{T}}$	Start tir			Direction):
					:15 · 6;	2 C 4 A		
Speci		nt & distan	· · · · · · · · · · · · · · · · · · ·	Breeding			NE	
Curch	<50	50-100	>100	evidence	-		1	
SWSF				5	_			
SOSP				7	_	/		
KIU.				T				
RWBL		te		Ś	_	1.50	USP RWBL	WISA
WISN MIGO				D	4 /		NV-	
-				M	- /		SWSP	
RWBL				Ŧ	- /		/ Rubi	
YWAR	· · · · · · · · · · · · · · · · · · ·	_	ļ	7	4 /			45 5057 Mees
		·	<u> </u>					Mes
					-		RWBL	
			<u> </u>		4			KILL
			<u> </u>		- \		TWAR	124
		<u> </u>	<u> </u>		- \			
			ļ		- \			
		<u> </u>			`	\backslash	T T	
						\backslash		
					4	\sim		
		ļ			_			

Surveyor's Initials:

-

Date: June 20/7

le.

<50 50-100 >100 evidence SWSP / / / / AMIR0 / / / / AMIR0 / / / / Image: Swsp / / / / Image: Swsp / / / / Swsp / / / / Amira A / / / Image: Swsp / / / / / Image: Swsp	tation#: TM: <u>46</u> 12	20 <u>0 - 50</u>					
SWSP Image: SwSP NIFL Image: SwSP SWSP At SwSP SwSP SwSP <th>Species</th> <th>Cou</th> <th>nt & distan</th> <th></th> <th>Breeding</th> <th></th> <th>NE</th>	Species	Cou	nt & distan		Breeding		NE
Ruber T YWAR T SwSP A YWAR A YWAR A AMUR0 S WAR A AMUR0 S Ware A AMUR0 S Ware A AMUR0 S Ware A AMUR0 S Ware S Ware <td>71 I AF</td> <td><50</td> <td>50-100</td> <td>>100</td> <td>evidence</td> <td></td> <td>L</td>	71 I AF	<50	50-100	>100	evidence		L
Ruber Image: Transmitted in the second sec	SWSP						
YWAR YWAR YWAR YWAR SWSP A YWAR A AMIRO S SwsP S AMIRO S Breeding Direction:	WIFL			<u> </u>	-		
SWSP A YWAR A A MUR o S A MUR o S Image: Superior of the second secon	KWBL			-			
SWSP A YWAR A A MUR o S A MUR o S Image: Superior of the second secon	YWAR_				Ţ.		
YWAR A AMR0 · AMR0 · <td< td=""><td><u>brhe</u></td><td></td><td></td><td></td><td>X</td><td></td><td></td></td<>	<u>brhe</u>				X		
Implies	<u>SWSP</u>						
Implies	IWAK_				A	/	YWAR WSP ROW
Image: Start time: Image: Direction: Image: Start time: Image: Direction: Image: Start time: Image: Direction:	HM/K0		<u> </u>		<u>></u>		WIFL
tation#: Feature: Start time: Direction: TM: Species Count & distance(m) Breeding	~~~~~						
tation#: Feature: Start time: TM: Direction:						AMR0	KAGE
tation#: Feature: Start time: Direction: TM: Species Count & distance(m) Breeding		_		 			
tation#: Feature: Start time: Direction: TM: Species Count & distance(m) Breeding						1 1	sause /
TM: Species Count & distance(m) Breeding							
TM: Species Count & distance(m) Breeding						\backslash	
TM: Species Count & distance(m) Breeding						\backslash	
TM: Species Count & distance(m) Breeding							
TM: Species Count & distance(m) Breeding			+	1			
TM: Species Count & distance(m) Breeding		_		1	1		
Species Count & distance(m) Breeding evidence 50 50-100 >100 <	tation#						Direction
<50 50-100 >100 evidence	Station#: JTM:				Start time:		Direction:
	JTM:	Cou	nt & distan	ce(m)	Breeding		Direction:
	JTM:	Cou <50	nt & distan	ce(m) >100	Breeding		Direction:
	JTM:	Cou <50	nt & distan	ce(m) >100	Breeding		Direction:
	JTM:	Cou <50	nt & distan	ce(m) >100	Breeding		Direction:
	JTM:	Cou <50	nt & distan	ce(m) >100	Breeding		Direction:
	ITM:	Cou <50	nt & distan	ce(m) >100	Breeding		Direction:
	ITM:	Cou <50	nt & distan	ce(m) >100	Breeding		Direction:
	ITM:	Cou <50	nt & distan	ce(m) >100	Breeding		Direction:
	ITM:	Cou <50	nt & distan	ce(m) >100	Breeding		Direction:
	ITM:	Cou <50	nt & distan	ce(m) >100	Breeding		Direction:
	ITM:	Cou <50	nt & distan	ce(m) >100	Breeding		Direction:
	ITM:	Cou <50	nt & distan	ce(m) >100	Breeding		Direction:
	ITM:	Cou <50	nt & distan	ce(m) >100	Breeding		Direction:
	ITM:	Cou <50	nt & distan	ce(m) >100	Breeding		Direction:
	JTM:	Cou <50	nt & distan	ce(m) >100	Breeding		Direction:
	ITM:	Cou <50	nt & distan	ce(m) >100	Breeding		Direction:
	ITM:	Cou <50	nt & distan	ce(m) >100	Breeding		Direction:
	TM:	Cou <50	nt & distan	ce(m) >100	Breeding		Direction:

Surveyor's Initials:

MR

Date: June 20/17

Þ

Breeding Bird Survey Form (Southern Ontario)



Project Name: Mor_Blec	ne			Number:		Date: Jure 20/17
surveyor: M.Ro	22		6:10			End Time (24hr): 6:45
Temp. (°C): [7	Wind Code ¹ :	Cloud Cove (00	er (%):	Precip. last	24hrs: 🛛 No	• • • • •

,.....

Species	Polygon(s)	Breeding Code ³			de³	Species	Bolugon(a)	Breeding Code ³			
		OB	PO	PR	со	Species	Polygon(s)	OB	PO	PR	СО
Canada Goose						Yellow-billed Cuckoo					<u> </u>
Wood Duck			L			Black-billed Cuckoo			1	 	†
Mallard						Eastern Screech-Owl				<u> </u>	1
Green-winged Teal						Great Horned Owl					<u> </u>
Ring-necked Pheasant				1	1	Common Nighthawk					<u> </u>
Ruffed Grouse						Chimney Swift			<u> </u>		<u>+</u>
Wild Turkey						Ruby-throated Hummingbird					
American Bittern						Belted Kingfisher					<u> </u>
Great Blue Heron						Red-headed Woodpecker					<u> </u>
Great Egret		,				Red-bellied Woodpecker				··	
Green Heron	2	Х				Yellow-bellied Sapsucker			~~~~~~		
Black-crowned Nt-Heron						Downy Woodpecker					
Turkey Vulture						Hairy Woodpecker					<u>`</u> ,
Osprey						Northern Flicker				·	
Bald Eagle						Pileated Woodpecker					
Northern Harrier						Eastern Wood-Pewee	-				
Sharp-shinned Hawk						Alder Flycatcher					
Cooper's Hawk						Willow Flycatcher	2				
Red-shouldered Hawk						Least Flycatcher	2			+	
Broad-winged Hawk						Eastern Phoebe					
Red-tailed Hawk						Great Crested Flycatcher					·
American Kestrel						Eastern Kingbird					
Merlin						Warbling Vireo	3				
Peregrine Falcon						Philadelphia Vireo					
Virginia Rail			1			Red-eyed Vireo	·[<u> </u>	
Sora						Gray Jay				{	
American Coot			-			Blue Jay					
Sandhill Crane						American Crow					
Killdeer	1			71		Common Raven					
Spotted Sandpiper				-		Horned Lark					
Upland Sandpiper						Purple Martin	<u> </u>				
Wilson's Snipe						Tree Swallow				[
American Woodcock			-			N. Rough-winged Swallow					
Ring-billed Gull						Bank Swallow	<u>├</u> ───┼				——
Herring Gull						Cliff Swallow	<u>├</u> ──				
Common Tern				ł-		Barn Swallow					
Rock Pigeon						BI-capped Chickadee	<u> </u>				
Mourning Dove		$\neg \uparrow$				Red-breasted Nuthatch	<u>├</u> ──── <u></u>				{
White-breasted Nuthatch				-+	—	Common Yellowthroat					

Breeding Bird Survey Form (Cont'd)

Species	Polygon(s)	OB	PO	PR	CO	Species	Polygon(s)	ÓВ	PO	PR	CO
Brown Creeper						Scarlet Tanager					
Carolina Wren						Eastern Towhee					
House Wren						Chipping Sparrow					
Winter Wren						Field Sparrow					
Marsh Wren						Vesper Sparrow		~~~~			
Blue-gray Gnatcatcher						Savannah Sparrow					
Eastern Bluebird						Grasshopper Sparrow					
Veery						Song Sparrow	1			T	
Swainson's Thrush						Swamp Sparrow	1,2			AT	
Hermit Thrush						White-throated Sparrow				,	
Wood Thrush						Dark-eyed Junco					
American Robin	3		5			Northern Cardinal					ĺ
Gray Catbird						Rose-breasted Grosbeak					
Northern Mockingbird						Indigo Bunting					
Brown Thrasher						Bobolink					
European Starling						Red-winged Blackbird	1,2			T	
Cedar Waxwing						Eastern Meadowlark	1				
Blue-winged Warbler						Common Grackle					
Golden-winged Warbler						Brown-headed Cowbird			1		
Nashville Warbler						Baltimore Oriole					
Yellow Warbler	1.2			A		House Finch					
Chestnut-sided Warbler	,					American Goldfinch	-			T	
Black-thr. Blue Warbler						House Sparrow					
Yellow-rumped Warbler											
Black-thr. Gr. Warbler						Additional Species:	Polygon(s)	OB	PO	PR	со
Black-and-white Warbler											
American Redstart											
Ovenbird											
Northern Waterthrush											
Mourning Warbler											

1 v	¹ Wind Codes (Beaufort Wind Scale)								
	Wind Speed (km/h)	Description	Visual Cues						
0	<1	Calm	Smoke rises vertically						
1	1-5	Light	Smoke drifts						
2	6-11	Light Breeze	Leaves rustle						
3	12-19	Gentle Breeze	Lighter branches sway						
4	20-28	Moderate Breeze	Dust rises, branches move						
5	29-38	Fresh Breeze	Small trees sway						
6	39-48	Strong Breeze	Larger branches move						

² P	² Precipitation Codes								
0	No precipitation	4	Thunderstorm						
1	Fog/Mist	5	Snow						
2	Light rain	6	Freezing rain						
3	Heavy rain								

Status Codes s § - Colonial Species

† - Rare species

Breeding Codes

OBSERVED: X - Species observed in its breeding season (no evidence of breeding) POSSIBLE:

- H Species observed in breeding season in suitable nesting habitat
 S Singing male present or breeding calls heard in breeding season in suitable nesting habitat
- PROBABLE:
- P Pair observed in their breeding season in suitable nesting habitat
- P Fair observed in their oresume through registration of territorial song or presence of adult bird in breeding habitat on at least 2 days, one week or more apart at the same place.
 D Courtship or display between a male and a female or 2 males including courtship feeding or copulation
 Ministranschelle near the
- V Visiting probable nest site
- A Agitated behaviour or anxiety calls of an adult
- B Brood Patch on adult female or cloacal protuberance on adult male

- N Nest building or excavation of nest hole
 CONFIRMED:
 DD Distraction display or injury feigning
 NU Used nest or egg shell found (occupied/laid during atlas period)
 FY Recently fledged young or downy young
 A Adde logistic neutring negativity for an entering negativity.
- AE Adults leaving or entering nest site in eircumstances indicating occupied nest FS Adult carrying faecal sac CF Adult carrying food for young

- NE Nest containing eggs
- NY Nest with young seen or heard

Date: June 20/17

2225 Mer Bleue Road, Ottawa, Ontario Environmental Impact Study OTT-00239983-A0 September 2018

Appendix D: Site Photographs





Photo 1 – Looking east across site at meadow marsh (foreground) and cultural woodland (background) (June 2017)



Photo 2 – Looking northeast at meadow marsh (foreground) and cultural woodland (background) (June 2017)



Photo 3 – Looking northeast at thicket swamp from west edge of swamp (June 2017)



Photo 4 – Temporary pooling in north half of site following rain event (June 2017)

2225 Mer Bleue Road, Ottawa, Ontario Environmental Impact Study OTT-00239983-A0 September 2018

Appendix E: Species Lists



Plant Species Observed During Field Surveys*

			Vegeta	ation Com	munity ¹	Rari	ty / Statu	IS ²				
#	Scientific Name	Common Name			0.111/	National	Prov	incial	WETNESS ³	SENSITIVITY ⁴	WEEDINESS ⁵	
			MAM2-2	SWT2-2	CUW	SARA	ESA	NHIC				
1	Acer negundo	Manitoba Maple			R			S 5	-2	0		
2	Asclepias syriaca	Common Milkweed	0		0			S5	5	0		Located in drier areas of M
3	Carex crinita	Fringed Sedge			0			S5	-4	6		
4	Carex gracillima	Graceful Sedge	0	0				S5	3	4		
5	Carex scoparia	Pointed Broom Sedge		0	0			S5	-3	5		
6	Carex vulpinoidea	Fox Sedge	0	0				S5	-5	3		
7	Chrysanthemum leucanthemum	Ox-eye Daisy	0		0			SE5	5	0	-1	
8	Cicuta sp	Water-hemlock Species	0	R								
9	Cornus stolonifera	Red-osier Dogwood		0	А			S5	-3	2		
10	Daucus carota	Wild Carrot			0			SE5	5	0	-2	
11	Equisetum arvense	Field Horsetail	0	0	A			S5	0	0		
12	Fragaria virginiana ssp. virginiana	Common Strawberry	0	0	А			S5	1	2		
13	Galium sp	Bedstraw Species		0								
14	Lonicera sp	Honeysuckle Species			0							
15	Lotus corniculatus	Bird's-foot Trefoil	A		А			SE5	1	0	-2	
16	Parthenocissus sp	Virginia Creeper Species			0							
17	Phalaris arundinacea	Reed Canary Grass	D	А	A			S5	-4	0		
18	Phleum pratense	Timothy	R					SE5	3	0	-1	
19	Phragmites australis	Common Reed	R					S5	-4	0		
20	Poa pratensis ssp. pratensis	Kentucky Blue Grass		0	А			S5	1	0		
21	Populus alba	European White Poplar	R		D			SE5	5	0	-3	
22	Populus deltoides ssp. deltoides	Eastern Cottonwood			D			S5	-1	4		
23	Populus tremuloides	Trembling Aspen			A			S5	0	2		
24	Ranunculus acris	Tall Buttercup		R				SE5	-2	0	-2	
25	Salix bebbiana	Bebb's Willow		0	0			S5	-4	4		
26	Salix petiolaris	Slender Willow		D	0			S5	-4	3		
27	Scirpus cyperinus	Wool Grass	0	А				S5	-5	4		
28	Solidago canadensis	Canada Goldenrod	0		A			S5	3	1		
29	Spiraea alba	Narrow-leaved Meadowsweet		0				S5	-4	3		
30	Trifolium pratense	Red Clover	R					SE5	2	0	-2	
31	Typha latifolia	Broad-leaved Cattail	0	0				S5	-5	3		
32	Ulmus americana	White Elm			R			S5	-2	3		
33	Vicia cracca	Cow Vetch	0	R	0			SE5	5	0	-1	
34	Vitis riparia	Riverbank Grape			R			S5	-2	0		

* Refer to Appendix D for definition of terms used in wildlife species list table.

Comments	
MAM2-2	

Wildlife Species Observed During Field Surveys*

		Rarity / Status ¹									
Common Name	Scientific Name	National	Prov	incial	Loca	ition Obs	erved	BE ²	Comments		
		SARA	ESA	NHIC	MAM2-2	SWT2-2	CUW		Commente		
MAMMALS	AMMALS										
No mammals recorded											
BIRDS											
Mallard	Anas platyrhynchos			S5	х			со	Adult female with young in drain ditch		
Green Heron	Butorides virescens			S4		х		NE	Flew overhead		
Killdeer	Charadrius vociferus			S5	х			PR			
Wilson's Snipe	Gallinago delicata			S5	х		х	PR	Several birds in both communities		
Hairy Woodpecker	Picoides villosus			S5			х	PO			
Willow Flycatcher	Empidonax traillii			S5		х		PR			
Least Flycatcher	Empidonax minimus			S5			х	PR			
Warbling Vireo	Vireo gilvus			S5			х	PR			
American Crow	Corvus brachyrhynchos			S5			х	PO			
Tree Swallow	Tachycineta bicolor			S4			х	PO			
House Wren	Troglodytes aedon			S5			х	PO			
Veery	Catharus fuscescens			S4			х	PO			
American Robin	Turdus migratorius			S5		х	х	PO			
Gray Catbird	Dumetella carolinensis			S5			х	PO			
Yellow Warbler	Dendroica petechia			S5	х	х	х	PR			
Common Yellowthroat	Geothlypis trichas			S5	х		х	PO			
Song Sparrow	Melospiza melodia			S5	х	х		PR			
Swamp Sparrow	Melospiza georgiana			S5	х	х		PR			
Red-winged Blackbird	Agelaius phoeniceus			S5	х	х		PR			
American Goldfinch	Spinus tristis			S5	х	х	х	PR			
REPTILES											
No reptiles recorded											
AMPHIBIANS											
No amphibians recorded											
FISH											
No fish recorded											

Common Name	Scientific Name	Rarity / Status ¹ National Provincial		Location Observed			BE ²	Comments	
		SARA	ESA	NHIC	MAM2-2	SWT2-2	CUW		
BUTTERFLIES					-				
Cabbage White	Pieris rapae			SE	х			RS	
ODONATA									
No odonata recorded									

* Refer to Appendix D for definition of terms

used in wildlife species list table.

Total Number of Species

Mammals:	0	Amphibians:	0
Birds:	20	Fish:	0
Reptiles:	0	Invertebrates:	1

Appendix F: Species List Terms and Definitions



PLANT SPECIES LIST TERMS AND DEFINITIONS:

¹ <u>RELATIVE ABUNDANCE OF PLANT SPECIES ASSOCIATED WITH EACH VEGETATION COMMUNITY*</u>

D - dominant	Represented by large numbers of individuals or clumps; visually more abundant than other plant species
A - abundant	Represented in the vegetation community by large numbers of individuals or clumps
O - occasional	Present as scattered individuals or represented by one or more large clumps of many individuals
R - rare	Represented in the vegetation community by less than three to five individuals or small clumps

* Based on Ecological Land Classificaton for Southern Ontario (MNR 1998)

² RARITY / POPULATION STATUS

National	Prov	incial	Regional				
SARA	ESA	NHIC	Negional				
END - Endangered	END - Endangered	S1 - Critically imperiled	Municipal - Rare in county or regional				
THR - Threatened	THR - Threatened	S2 - Imperiled	municipality as determined by the municipality				
EXP - Extirpated	EXP - Extirpated	S3 - Vulnerable					
SC - Special Concern	SC - Special Concern	S4 - Apparently secure	CA - Rare in regional watershed as determined by the local				
NAR - Not at Risk	NAR - Not at Risk	S5 - Secure	conservation authority (CA)				
DD - Data Deficient	DD - Data Deficient	SE - Exotic (non-native)					
		? - uncertain about status					

³ WETNESS*

-5	Obligate Wetland	occurs almost always in wetlands under natural conditions (>99% probability)
-2 to -4	Facultative Wetland	usually occurs in wetlands, but occasionally found in non-wetlands (67-99% probability)
1 to -1	Facultative	equally likely to occur in wetlands or non-wetlands (34-66% probability)
2 to 4	Facultative Upland	occasionally occurs in wetlands, but usually occurs in non-wetlands (1-33% probability)
5	Obligate Upland	occurs alomost never in wetlands under natural conditions (<1% probability)

* Based on Floristic Quality Assessment System (MNR 1995)

⁴ PLANT SPECIES SENSITIVITY*

- 0 3 Plants found in a wide variety of communities, including disturbed sites
- 4 6 Plants typically associated with a specific plant community, but tolerate moderate disturbance
- 7-8 Plants associated with a community in an advanced successional stage that has undergone minor disturbance
- 9-10 Plants with a high degree of fidelity to a narrow range of specific habitats or ecological conditions

* Values and terminology derived from Floristic Quality Assessment (MNR 1995)

⁵ WEEDINESS*

- -1 Non-native plants with little or no impact on natural areas
- -2 Non-native plants that sometimes cause problems, but only infrequently or in localized areas
- -3 Non-native highly invasive plants that can become serious problems in natural areas by displacing native flora

* Based on Floristic Quality Assessment (MNR 1995)

WILDLIFE SPECIES LIST TERMS AND DEFINITIONS:

¹ RARITY / POPULATION STATUS

National	Provincial		Deviewel
SARA	ESA	NHIC ^a	Regional
END - Endangered	END - Endangered	S1 - Critically imperiled	Municipal - Rare in county or regional
THR - Threatened	THR - Threatened	S2 - Imperiled	municipality as determined by the municipality
EXP - Extirpated	EXP - Extirpated	S3 - Vulnerable	
SC - Special Concern	SC - Special Concern	S4 - Apparently secure	CA - Rare in regional watershed as determined by the local conservation authority (CA)
NAR - Not at Risk	NAR - Not at Risk	S5 - Secure	
DD - Data Deficient	DD - Data Deficient	SE - Exotic (non-native)	
		? - uncertain about status	

² BE (BREEDING EVIDENCE)**

Anurans (Frogs and Toads) Breeding Call Levels:

L1 - Call Level 1 Calls	s of individual frogs or toads do not overlap and individuals can be counted
L2 - Call Level 2 Calls	s of individuals sometimes overlap but the number of individuals can reasonably be counted
L3 - Call Level 3 Calls	s are continous and overlapping and a count estimate is not possible
Birds:	
NE - No Evidence	Species observed in its breeding season, but no breeding evidence observed
PO - Possible	Indicated by presence of species or singing male during the breeding season in suitable habitat
PR - Probable	Indicated by territorial/courtship displays, presence of mating pair, agitated behavior or nest building
C - Confirmed	Indicated by presence of eggs, fledlings, distraction displays, active nest, fecal/food carrying, etc.
NH - No Suitable Habitat	Species observed during mating season, but no suitable breeding habitat in study area
OB - Observed	Species observed outside of the breeding season
NB - Non-breeding Migrant	Migrant species (breeds outside of region containing study area)
Other Wildlife:	
CO - Confirmed	Indicated by presence of ease large young defensive behavior food carpying active peet/den/redd, etc.

CO - Confirmed	Indicated by presence of eggs, larvae, young, defensive behavior, food carrying, active nest/den/redd, etc.
RS - Resident Species	Species expected to be breeding within the study area due to localized territory

* Breeding evidence terminology for anurans is based on Marsh Monitoring Program and for birds is derived from Ontario Breeding Bird Atlas