

Orleans Family Health Hub

Stormwater Management & Servicing Report

Type of Document: Site Plan Application

Project Name: Orleans Family Health Hub (OFHH)

Project Number OTT-00240132-A0

Prepared By: exp Services Inc. 100-2650 Queensview Drive Ottawa, ON K2B 8H6 Canada

Date Submitted April 5, 2018 Rev Nov 2, 2018

Orleans Family Health Hub

Stormwater Management and Servicing Report

Type of Document: Site Plan Application

Project Name: Orleans Family Health Hub (OFHH)

Project Number: OTT-00240132-A0

Prepared By: exp Service Inc. 100-2650 Queensview Drive Ottawa, ON K2B 8H6 Canada T: 613 688-1899 F: 613 225-7337 www.exp.com

Marc Lafleur, P. Eng. Project Engineer Infrastructure Services

Date Submitted: April 5, 2018 Revised November 2, 2018



Alam Ansari, M.Sc., P. Eng. Senior Project Manager Infrastructure Services

100



Legal Notification

This report was prepared by EXP Services Inc. for the account of HDR

Any use which a third party makes of this report, or any reliance on or decisions to be made based on it, are the responsibility of such third parties. EXP Services Inc. accepts no responsibility for damages, if any, suffered by any third party as a result of decisions made or actions based on this project



Table of Contents

Page

1	Intro	oduction	1
2	Site	Overview	1
3	Wat	er Servicing	2
4	San	itary Sewer Design	3
5	Stor	m Sewer Design	4
2 S 3 W 4 S 5 S 6 S 6. 6. 6. 6. 6. 6. 7 E	Stor	mwater Management Design	4
	6.1	Allowable Release Rate	5
	6.2	Design Criteria	5
	6.3	Runoff Coefficients	6
	6.4	Calculation of Post-Development Runoff	6
	6.5	Flow Control Method	7
	6.6	Storage Requirements	8
	6.7	City Stress Test	8
	6.8	Stormwater Quality Control	9
7	Eros	sion and Sediment Control	9
8	Con	clusions1	0



List of Appendices

Appendix A	 SWM Design Sheets IBI Group Report Exerpts (Table 4.4 – Summary of Minor System Capture & Figure 4 – Avalon West Drainage Area Plan Storm Sewer Design Sheet
Appendix B	 Email-HGL Boundary Conditions from City of Ottawa Pressure Check Under Max Day + Fire Flow



1 Introduction

Exp Services Inc. (exp) was retained by HDR to prepare site servicing and stormwater management report or the proposed Orleans Family Health Hub. The subject site is approximately 9 has in area and is e located at 225 Mer Bleue Road in the City of Ottawa (Orleans), Ontario. This report outlines the servicing and stormwater management strategy for the subject property.

2 Site Overview

The proposed development is located north-east of the intersection of Mer Bleue Road and Brian Coburn Blvd. in the City of Ottawa. The site is 9.16 has in area and is within the Neighborhood 5 of the Mer Bleue Community Design Plan. Access to the site will be provided from both Mer Bleue Road to the West and Brian Coburn Blvd. to the south. The proposed development comprises of a healthcare building with access roads, surface parking and outdoor landscape areas.

The development has been designed in accordance with the recommendations and guidelines provided in the following documents:

- Infrastructure Servicing Brief Chaperal Phase 4, July 19, 2012 revisions 2 (exp Services Inc.)
- Avalon West (Neighbourhood 5), Western Trunk Storm Sewer and Interim Stormwater Management Report, Revision 2, February 2012 (IBI Group)
- Avalon West (Neighbourhood 5), Stormwater Management Facility Design, Revision 2, October 2012 (IBI Group)
- Sewer Design Guidelines, Second Edition, Document SDG002, October 2012, City of Ottawa (Guidelines) including:
- Technical Bulletin ISDTB-2012-4 (20 June 2012)
- Technical Bulletin ISDTB-2014-01 (05 February 2014)
- Technical Bulletin PIEDTB-2016-01 (September 6, 2016)
- Ontario Ministry of Transportation (MTO) Drainage Manual, 1995-1997
- Stormwater Management Planning and Design Manual, Ontario Ministry of the Environment and Climate Change, March 2003 (SMPDM)



3 Water Servicing

The development will be serviced by a new 200mm diameter looped water main which will be connected to the existing 300mm diameter water main on Brian Coburn Blvd to the south and the existing 400mm diameter water main on Gerry Lalonde Drive to the east. Two additional 200mm diameter water service stubs will be provided to service the future development on the north side of the property and the future park at the south-east corner.

The building will be provided with a sprinkler system for firefighting. Sprinkler water demand provided by the Mechanical Engineer is 32 L/s. The fire flow demand calculations were prepared based on the Fire Underwriters Survey criteria (FUS, 1999). The fire flow demand was calculated to be 66.7L/s, refer to Appendix B for detailed calculations. There are 2 new fire hydrants proposed on the site. There is a fire hydrant proposed near the main entrance on the west side of the building near the Fire Department connection and a second hydrant near the entrance on the north side of the proposed building.

The Institutional water demands for the facility were calculated in accordance with City of Ottawa Water Distribution Design Guidelines and are as follows:

Institutional Water Demand

Average daily demand: =50 000 l/ha/day =9.16 ha x 50 000 L/ha/day x (1/86,400 s/day) = 5.3 L/s

Maximum daily demand:

=1.5 x avg. day =1.5 x 5.3 L/s =8.0 L/s

Maximum hourly daily demand:

=1.8 x avg. day =1.8 x 8.0 L/s =14.4 L/s

The following boundary conditions were provided by the City of Ottawa (refer to Appendix B)

Brian Coburn Blvd. (ground Elevation = 88.58m):

Maximum HGL = 130.4m

Peak Hour HGL = 125.8 m

Max Day (8 L/s) + FireFlow (66.7L/s) = 126.2m



Gerry Lalonde Dr. (ground Elevation = 88.43m):

Maximum HGL = 130.3m

Peak Hour HGL = 125.6 m

Max Day (8 L/s) + Fire Flow (66.7L/s) = 126.2m

Based on the HGL for max day + fire flow, a pressure analysis was performed to calculate the residual pressure at the building. Based in these calculations residual pressure of 44.7 psi (358kPa) was estimated for the connection off Brian Coburn Blvd and 43.2 psi (349 kPa) for the connection off Gerry Lalonde Drive. Refer to Appendix B for calculations. The estimated residual water pressure is greater than the minimum requirement of 20psi (140kPa) as per the City of Ottawa Design Guidelines. Therefore, the existing municipal water supply system will have adequate capacity to meet the domestic and fire demands for the proposed development.

4 Sanitary Sewer Design

The development will be serviced by a new 200mm sanitary service which will be connected to the existing 375mm diameter sewer main on Gerry Lalonde Drive. A 200mm diameter sanitary stub will be also provided to service the future development towards the north of the property.

The design flows of the site have been determined as follows: Design Flow forCommercial Use:50,000 L/day/ha or 0.5787 L/s/haPeaking Factor:1.5Site Area:9.16 hasExtraneous Flow:0.28 L/s/haPeak Design Flow:= (0.5787 L/s/ha)(9.16 ha)(1.5) + (9.16 ha)(0.28 L/s/ha)= 7.9 L/s

The proposed on-site sanitary sewer will be installed at a minimum grade of 0.5%. At this slope, a 200 mm diameter sanitary sewer has a capacity of 23 L/s and a full flow velocity of 0.74 m/s. The proposed sanitary sewer will therefore have sufficient capacity to service the site.

The sanitary sewer system was designed to accommodate flows from future development on the property on the north side of the site. The flows from the site will ultimately drain to the Tenth Line Sanitary Trunk Sewer and Pump Station.



5 Storm Sewer Design

The proposed development is within the Avalon West Neighbourhood 5 which drains to McKinnon's Creek approximately 800m south of the site. The development will be serviced by the existing trunk sewer along Gerry Lalonde Drive. During the development of the adjacent subdivision, a 1350mm diameter storm sewer stub was installed for servicing the development. This service stub will be utilized for conveying the storm water flows from the site and the flows from the external drainage area to the north of the site.

The on site storm sewer system has been designed for ultimate build out conditions and includes the future development on the north side of the site.

6 Stormwater Management Design

An on-site storm water system has been designed to convey the storm water flows from the site to the existing 1350mm diameter storm sewer stub which is connected to the 1650mm diameter trunk sewer on Gerry Lalonde Blvd. Quantity control will be achieved by limiting the stormwater runoff to the allowable release rate determined during the Avalon West Neighbourhood 5 Western Trunk Storm Sewer Design. Flows from the external drainage on the north side of the site have been accounted for in the Stormwater Management design. Storm water flows from the site will be restricted to allowable release rates by installation of inlet control devices (ICDs) and using flow control roof drains. Storm water quality control will be provided by the Neighbourhood 5 SWM facility. A 750mm diameter storm sewer will be provided to service the future development on the property towards the north side of the site. A 300mm diameter stub will be provided to service the future park on the south-east side of the property.

The site grading has been designed to limit the maximum ponding under 100-year storm events to 300mm. Overland flow paths have been provided to convey the excess run off towards the municipal roads. Overland flow from the parking lot on the north side will sheet drain towards Mer Bleue Road. Overland flow from the rest of the current phase of development will sheet drain towards Brian Coburn Boulevard. Overland flows from the areas earmarked for future expansion of the Facility and from the external drainage area to the north will sheet drain towards Gerry Lalnonde Drive through the existing easement. Until such time the future development area is fully developed, there will be minimal or no overland flow from it. Following the development of this area, overland flow will be directed towards Brian Coburn Boulevard.



6.1 Allowable Release Rate

The allowable release rate for the site was established during the design of Avalon West (Neighborhood 5) Western Trunk Sewer and Stormwater Management Facility. The allowable release rate is of 85 L/s/ha up to the 100-year storm event. Reference Table 4.4 and Figure 4 of the IBI report (Revision 2, 2012) included in Appendix A. The release rate for the OFHH site in IBI's report for up to the 100-year events is **778.6 L/s.** This release rate has been used for the SWM design of the OFHH.

The on site storm sewer system has been designed for ultimate build out conditions and includes the future development on the north side of the site. There is a 0.5 ha block of land within the site which has been designated for a future park. The 0.5 ha park will be controlled separately from the rest of the site. Applying the allowable release rate of 85 L/s/ha, the Park will have an allowable release rate of 42.5 L/s up to the 100-year storm event. The allowable release rate for the Orleans Health Hub Site excluding the park is therefore **736.1 L/s** up to the 100-year event (778.6-42.5 L/s).

6.2 Design Criteria

The storm sewer system was designed in conformance with the latest version of the City of Ottawa Design Guidelines (October 2012).

Minor System Design Criteria

- The storm sewers and service laterals have been designed and sized based on the Rational Method and the Manning's Equation under free flow conditions for the 5-year storm using a 10-minute inlet time.
- Inflow rates into the minor system are limited to the allowable release rates determined in the Avalon West (Neighborhood 5) IBI Group Western Trunk Sewer and Stormwater Management Facility reports.

Major System Design Criteria

- The major system has been designed to accommodate onsite detention with sufficient capacity to attenuate the 100-year design storm. Excess runoff above the 100-year event will flow overland offsite.
- Onsite storage is provided for up to the 100-year design storm with maximum allowable ponding depth of 300mm on the ground surface and 150mm on the building roof. Calculations for the required onsite storage volumes are provided in Appendix A.
- Calculations of the required storage volumes have been prepared based on the Modified Rational Method as identified in Section 8.3.10.3 of the City's Sewer Guidelines. The depth and extent of surface storage is illustrated on the Site Servicing and Grading plan.



6.3 Runoff Coefficients

Runoff coefficients used for post-development conditions were based on actual areas measured in AutoCAD. Runoff coefficients for impervious surfaces (roofs, asphalt, and concrete) were taken as 0.90, whereas pervious surfaces (grass/landscaping) were taken as 0.20. Runoff coefficients were increased by 25% during the 100-year storm event, with a maximum of 1.0.

6.4 Calculation of Post-Development Runoff

Refer to the storm drainage plan drawing C003 for the post-development storm drainage areas. There will be small portions of the site that will be subject to free flow conditions due to site constraints and for matching existing grades at the perimeter of the site. There will be some uncontrolled flow from the western side of the site towards the Mer Bleue ROW and from the southern edge of the site towards the Brian Coburn Blvd ROW (Post4). The drainage from the loading dock (Post-5) area will also flow uncontrolled into the storm sewer network. The easement along the south side of the futre park will also flow uncontrolled (Post-6). All other drainage areas will be over controlled up to the 100-year event in order to satisfy the total allowable release rate from the site.

Based on the storm drainage areas presented on the storm drainage plan drawing C003, the 5year and 100-year post-development peak flows are calculated based on the Rational Method and are summarized in the Table 6.1 below with detailed calculations provided in Appendix A.

			S	torm = 5-yea	ar	Storm = 100-year			
Area No	Location/description	Area (ha)	Cavg	Q (L/sec)	Q _{CAP} (L/sec)	CAVG	Q (L/sec)	Q _{CAP} (L/sec)	
Post-1	Roof	0.79	0.90	206.1	23.0	1.00	392.2	23.0	
Post-2	Parking/Roads	2.89	0.80	673.7	184.0	1.00	1434.1	184	
Post-3	Future Dev Area	4.50	0.21	277.2	277.2	0.27	593.2	354	
Post-4	ROW Uncontrolled	0.21	0.34	20.6	20.6	0.42	44.0	44.0	
Post-5	Loading Dock Uncontrolled	0.07	0.90	18.3	18.3	1.00	34.7	34.7	
Post-6	Easement Uncontrolled	0.2	0.36	20.7	20.7	0.45	44.4	44.4	
Post-7	Fututre Park	0.5	0.22	31.4	31.4	0.27	67.3	42.5	
Total		9.16		1248	467.5		2609.8	726.6	

Table 6.1:	Summar	y of Post-Development Flows

Flows in **bold** under Q_{CAP} denotes flows that are controlled. The flow from the Park is controlled to 42.5 L/s based on the allowable 85 L/s/ha. The other drainage areas that are controlled are over controlled in order to compensate for the uncontrolled drainage areas.



The total runoff (controlled and uncontrolled) from the 9.16 ha site will be restricted to 726.6 L/sec up to the 100-year events which is less than the allowable 778.6 L/s. Further details regarding the onsite detention and storage methods are provided in the proceeding section.

6.5 Flow Control Method

It will be necessary to control runoff to the allowable rate; therefore, runoff will be detained using inlet control devices (ICDs) within the storm system as well as flow control roof drains. The following Table 6.2 summarizes the ICDs that are proposed.

Area No	ICD Location	Controlled Rate (L/sec)	Orifice Centre Elev. (m)	Max Elev. (m)	Head (m)	ICD Type / Model
Post-1	Roof Drains	23	NA	NA	0.15	By Mechanical Eng.
Post-2	CBMH221	184	85.39	88.70	3.31	195mm diameter Plug Type Orifice
Post-3	CBMH227	354	86.08	88.00	1.92	350mm diameter Plug Type Orifice
Post-7	CBMH 224	42.5	85.30	88.30	3.0	100 mm diameter Plug Type Orifice

 Table 6.2:
 Summary of ICDs

The discharge rate for the two ICDs was calculated based on the Orifice Equation, assuming it was fully submerged, as follows:

 $Q_{ORF} = C * A * \sqrt{2gH}$

where:

=	Flow through orifice, m ³ /sec
=	Discharge Coefficient [0.61]
=	Area of orifice (m ²)
=	Acceleration due to gravity, m/sec ² [9.81]
=	Head above centerline of orifice, m
	= =



6.6 Storage Requirements

Stormwater storage requirements and associated controlled release rates within the site are summarized below in Table 6.3. Detailed calculations using the Modified Rational Method of the onsite storage requirements are provided in Appendix A.

Area No	Controlled Rate (L/sec)	Storage Volume Required (m ³)	Storage Volume Provided (m ³)	Adequate Storage Provided
Post-1	23	364	375	Yes
Post-2	184	1007	1073	Yes
Post-3	354	627	144	Yes
Post-7	42.5	41.6	90.6	Yes

 Table 6.3: Summary of Storage Requirements and Release Rates

The storage provided on the surface areas were estimated using the prism formula as follows:

V = 1/3 x A x d

where:

0.		
V	=	storage volume (cu.m.)
А	=	storage area (sq.m.)
d	=	maximum storage depth (m)

The depth is the difference in elevation between the low point elevation and the maximum water level. A maximum depth of 0.3m was used for storms up to the 100-year storm event. Since there is adequate storage provide for all controlled drainage areas, the maximum surface ponding depth up to the 100-year storm event will be less than 0.3m. Refer to Appendix A for storage volume calculation details.

6.7 City Stress Test

As per Technical Bulletin ISDTB-2012-1 issued by the City of Ottawa, it is now a requirement that all drainage systems be stress tested using design storms calculated on the basis of a 20% increase of the City's IDF curves rainfall values. Modifications to the drainage system would be required if severe flooding to properties is identified.



As indicated previously, stormwater is to be stored on site for storms up to and including the 100 year storm events. An increase of 20% of the 100 year storm event will result in excess water following the overland flow route and spilling onto the City Right-of-Way before impacting the building. The building finished floor elevation has been established to maintain a minimum of 300mm freeboard from the spill elevation for each ponding area to the Finished Floor Elevation of for 100 year and larger storm events.

6.8 Stormwater Quality Control

Water quality control requirements for the Neighborhood 5 development area was determined in the approved "Mer Bleue Community Design Plan – Infrastructure Servicing Study (2006 CDP). Stormwater quality control for the proposed health hub will be provided by the existing stormwater management facility designed to provide 80% TSS removal for Neighborhood 5. Therefore, no on-site water quality control measures will be provided.

7 Erosion and Sediment Control

During all construction activities, erosion and sedimentation shall be controlled by the following techniques:

- extent of exposed soils shall be limited at any given time,
- exposed areas shall be re-vegetated as soon as possible,
- filter cloth shall be installed between frame and cover of all new catch basins and catch basin manholes,
- filter cloth shall be installed between frame and cover of the existing catch basins and catch basin manholes as identified on the site grading and erosion control plan,
- light duty silt fencing will be used to control runoff around the construction area. Silt fencing locations are identified on the site grading and erosion control plan.
- visual inspection shall be completed daily on sediment control barriers and any damage repaired immediately. Care will be taken to prevent damage during construction operations,
- In some cases barriers may be removed temporarily to accommodate the construction operations. The affected barriers will be reinstated at night when construction is completed,
- Sediment control devices will be cleaned of accumulated silt as required. The deposits will be disposed of as per the requirements of the contract,
- during the course of construction, if the engineer believes that additional prevention methods are required to control erosion and sedimentation, the contractor will install additional silt fences or other methods as required to the satisfaction of the engineer, and
- Construction and maintenance requirements for erosion and sediment controls are to comply with Ontario Provincial Standard Specification (OPSS) OPSS 805, and City of Ottawa specifications



8 Conclusions

The following conclusions are provided:

- A 200mm diameter looped water service connected to the 300mm diameter municipal watermain on Brian Coburn Blvd and the 400mm diameter watermain on Gerry Lalonde Drive will adequately service the proposed development.
- Two Fire Hydrants will be installed to provide fire protection for the proposed development.
- A 200mm diameter sanitary service connected to the municipal sanitary sewer system will adequately service the proposed building.
- SWM for the proposed development will be achieved by restricting all storms up to the 100 year post development flows to the allowable release rate determined during the design of Avalon West (Neighborhood 5) Western Trunk Sewer and Stormwater Management Facility.
- Onsite stormwater storage is provided up to the 100-year design storms with maximum allowable ponding depths of 300mm on the ground surface and 150mm on the roof.
- Quality control of stormwater will be provided by the existing Stormwater Management Facilty for Neighbourhood 5 to provide 80% TSS removal
- Temporary erosion and sediment control measures for the subject site have been identified.
- Overland flow routes have been provided for the subject site.



Appendix A –

SWM Design Sheets

IBI Group Report Exerpts (Table 4.4 – Summary of Minor System Capture & Figure 4 – Avalon West Drainage Area Plan

Storm Sewer Design Sheet



Table A1 CALCULATION OF AVERAGE RUNOFF COEFFICIENTS (POST-DEVELOPMENT)

		Asphalt Areas		Roof Areas		Gravel Areas		Grassed Areas			Total	
Area No.	Area Description	Area (m ²)	A * C	Area (m ²)	A * C	Area (m ²)	A * C	Area (m ²)	A * C	Sum AC	Area	C_{AVG}
		C=0	.90	C=0	0.90	C=0	.90	C=0.	20		(m ²)	
Post-1	Roof			7900.0	7110.0					7110.0	7900	0.90
Post-2	Parking	24941.0	22446.9					3949.0	789.8	23236.7	28890	0.80
Post-3	Future DEV	800.0	720.0					44200.0	8840.0	9560.0	45000	0.21
Post-4	ROW Free Flow	410.0	369.0					1700.0	340.0	709.0	2110	0.34
Post-5	Loading Dock	700.0	630.0							630.0	700	0.90
Post-6	Easement Free Flow	450.0	405.0					1550.0	310.0	715.0	2000	0.36
Post-7	Future Park	120.0	108.0					4880.0	976.0	1084.0	5000	0.22
	Average Runoff Coeff = C _{AVG} = 4											

Table A2 SUMMARY OF POST DEVELOPMENT RUNOFF (UNCONTROLLED AND CONTROLLED)

			Time of		Storm :	= 5-year			Storm =	10-year		Storm = 100-year			
Area No	Outlet Location	Area (ha)	Conc. T _c (min)	C _{AVG}	l₅(mm/hr)	Q (L/sec)	Q _{CAP} (L/sec)	C_{AVG}	I ₁₀ (mm/hr)	Q (L/sec)	Q _{CAP} (L/sec)	C _{AVG}	I ₁₀₀ (mm/hr)	Q (L/sec)	Q _{CAP} (L/sec)
Post-1	Roof	0.790	10	0.90	104.29	206.1	23.0	0.90	122.14	241.4	23.0	1.00	178.56	392.2	23.0
Post-2	Parking	2.889	10	0.80	104.29	673.7	184.0	0.80	122.14	789.0	184.0	1.00	178.56	1434.1	184.0
Post-3	Future DEV	4.500	10	0.21	104.29	277.2	277.2	0.21	122.14	324.6	324.6	0.27	178.56	593.2	354.0
Post-4	ROW Free Flow	0.211	10	0.34	104.29	20.6	20.6	0.34	122.14	24.1	24.1	0.42	178.56	44.0	44.0
Post-5	Loading Dock	0.070	10	0.90	104.29	18.3	18.3	0.90	122.14	21.4	21.4	1.00	178.56	34.7	34.7
Post-6	Easement Free Flow	0.200	10	0.36	104.29	20.7	20.7	0.36	122.14	24.3	24.3	0.45	178.56	44.4	44.4
Post-7	Future Park	0.500	10	0.22	104.29	31.4	31.4	0.22	122.14	36.8	36.8	0.27	178.56	67.3	42.5
Total		9.160				1248.0	575.1			1461.6	638.2			2609.8	726.6
Intensity, $I_5 = 998.071/(Tc+6.035)^{0.814}$ (5-year, City of Ottawa) 1248.0 575.1 1461.6 638.2 2609.8 726.6 Notes 1) Intensity, $I_5 = 998.071/(Tc+6.035)^{0.814}$ (5-year, City of Ottawa) 2) Intensity, $I_{10} = 1174.184/(Tc+6.045)^{0.816}$ (10-year, City of Ottawa) 3) Intensity, $I_{100} = 1735.688/(Tc+6.014)^{0.820}$ (100-year, City of Ottawa) 4) Time of Concentration: $T_c=10min (5.4.5.2, City of Ottawa)$ 4) Time of Concentration: $T_c=10min (5.4.5.2, City of Ottawa)$ 4) Flows under column Q_{CAP} which are bold , denotes flows that are controlled.															

Table A3 Estimate of Storage Required for 5-yr and 100-yr Storms (Modified Rational Method)

	Area No: Post 1 Roof $C_{AVG} =$ 0.90 (2-yr, 5-yr) $C_{AVG} =$ 1.00 (100-yr +25%) Time Interval = 5 (mins) Drainage Area = 0.7900 (hectares)												
	Rele	ase Rate =	23.0	(L/sec)		Relea	ase Rate =	23.0	(L/sec)				
	Retu	rn Period =	5	(years)		Retur	n Period =	100	(years)				
D	IDF Parar	IDF Parameters, A = 998.071				IDF Paran	neters, A =			0.820			
		(=	A/(T _D +C) ^B	, C =	6.053		(=	A/(T _D +C) ^B	, C =	6.014			
	Rainfall Intensity, I (mm/hr)	Peak Flow (L/sec)	Release Rate (L/sec)	Storage Rate (L/sec)	Storage (m ³)	Rainfall Intensity, I (mm/hr)	Peak Flow (L/sec)	Release Rate (L/sec)	Storage Rate (L/sec)	Storage (m ³)			
0	230.5	455.6	23.00	432.6	0	398.6	875.4	23.000	852.4	0.0			
5	141.2	279.1	23.00	256.1	77	242.7	533.0	23.000	510.0	153.0			
10	104.2	205.9	23.00	182.9	110	178.6	392.2	23.000	369.2	221.5			
15	83.6	165.2	23.00	142.2	128	142.9	313.8	23.000	290.8	261.7			
20	70.3	138.9	23.00	115.9	139	120.0	263.4	23.000	240.4	288.5			
25	60.9	120.4	23.00	97.4	146	103.8	228.1	23.000	205.1	307.6			
30	53.9	106.6	23.00	83.6	150	91.9	201.8	23.000	178.8	321.8			
35	48.5	95.9	23.00	72.9	153	82.6	181.4	23.000	158.4	332.6			
40	44.2	87.3	23.00	64.3	154	75.1	165.0	23.000	142.0	340.9			
45	40.6	80.3	23.00	57.3	155	69.1	151.6	23.000	128.6	347.4			
50	37.7	74.4	23.00	51.4	154	64.0	140.5	23.000	117.5	352.4			
55	35.1	69.4	23.00	46.4	153	59.6	130.9	23.000	107.9	356.2			
60	32.9	65.1	23.00	42.1	152	55.9	122.8	23.000	99.8	359.1			
65	31.0	61.4	23.00	38.4	150	52.6	115.6	23.000	92.6	361.2			
70	29.4	58.1	23.00	35.1	147	49.8	109.3	23.000	86.3	362.7			
75	27.9	55.1	23.00	32.1	145	47.3	103.8	23.000	80.8	363.5			
80	26.6	52.5	23.00	29.5	142	45.0	98.8	23.000	75.8	363.9			
85	25.4	50.1	23.00	27.1	138	43.0	94.3	23.000	71.3	363.8			
90	24.3	48.0	23.00	25.0	135	41.1	90.3	23.000	67.3	363.4			
95	23.3	46.1	23.00	23.1	131	39.4	86.6	23.000	63.6	362.6			
100	22.4	44.3	23.00	21.3	128	37.9	83.2	23.000	60.2	361.5			
105	21.6	42.7	23.00	19.7	124	36.5	80.2	23.000	57.2	360.1			
Maximum S Notes	storage Req	uried =			154.7					363.9			

Notes

1) Peak flow is equal to the product of 2.78 x C x I x A

2) Rainfall Intensity, $I = A/(T_D + C)^B$, where $T_D =$ storm duration (mins)

3) Release Rate = Desired Capture (Release) Rate

4) Storage Rate = Peak Flow - Release Rate

5) Storage = Duration x Storage Rate

6) Maximium Storage = Max Storage Over Duration

Table A4 Estimate of Storage Required for 5-yr and 100-yr Storms (Modified Rational Method)

	Area No:	Post 2	Parking										
	C _{AVG} =	0.80	(2-yr, 5-yr)										
	C _{AVG} =	1.00	(100-yr +2	5%)									
Tim	e Interval =	5	(mins)										
Drain	Drainage Area = <u>2.8890</u> (hectares)												
		ase Rate =	184.0	(L/sec)		Relea	ase Rate =	184.0	(L/sec)				
		rn Period =	5	(years)			n Period =	100	(years)				
Duration,	IDF Parar	meters, A =		, B =	0.814	IDF Paran	neters, A =		-	0.820			
T_D (min)		(=	A/(T _D +C) ^B	, C =	6.053		(=	A/(T _D +C) ^B	, C =	6.014			
()	Rainfall	Peak	Release	Storage	Storage	Rainfall	Peak	Release	Storage	Storage			
	Intensity, I	Flow	Rate	Rate	(m ³)	Intensity, I	Flow	Rate	Rate	(m ³)			
	(mm/hr)	(L/sec)	(L/sec)	(L/sec)	(11)	(mm/hr)	(L/sec)	(L/sec)	(L/sec)	(11)			
0	230.5	1488.9	184.00	1304.9	0	398.6	3201.5	184.000	3017.5	0.0			
5	141.2	912.0	184.00	728.0	218	242.7	1949.3	184.000	1765.3	529.6			
10	104.2	673.1	184.00	489.1	293	178.6	1434.1	184.000	1250.1	750.0			
15	83.6	539.8	184.00	355.8	320	142.9	1147.6	184.000	963.6	867.3			
20	70.3	453.8	184.00	269.8	324	120.0	963.4	184.000	779.4	935.2			
25	60.9	393.4	184.00	209.4	314	103.8	834.0	184.000	650.0	975.1			
30	53.9	348.4	184.00	164.4	296	91.9	737.8	184.000	553.8	996.9			
35	48.5	313.4	184.00	129.4	272	82.6	663.2	184.000	479.2	1006.4			
40	44.2	285.4	184.00	101.4	243	75.1	603.5	184.000	419.5	1006.9			
45	40.6	262.5	184.00	78.5	212	69.1	554.6	184.000	370.6	1000.5			
50	37.7	243.2	184.00	59.2	178	64.0	513.6	184.000	329.6	988.9			
55	35.1	226.9	184.00	42.9	142	59.6	478.9	184.000	294.9	973.0			
60	32.9	212.8	184.00	28.8	104	55.9	448.9	184.000	264.9	953.7			
65	31.0	200.5	184.00	16.5	64	52.6	422.8	184.000	238.8	931.4			
70	29.4	189.7	184.00	5.7	24	49.8	399.9	184.000	215.9	906.7			
75	27.9	180.2	184.00	-3.8	-17	47.3	379.5	184.000	195.5	879.9			
80	26.6	171.6	184.00	-12.4	-60	45.0	361.3	184.000	177.3	851.2			
85	25.4	163.9	184.00	-20.1	-103	43.0	345.0	184.000	161.0	821.0			
90	24.3	156.9	184.00	-27.1	-146	41.1	330.2	184.000	146.2	789.4			
95	23.3	150.5	184.00	-33.5	-191	39.4	316.7	184.000	132.7	756.5			
100	22.4	144.7	184.00	-39.3	-236	37.9	304.4	184.000	120.4	722.5			
105	21.6	139.4	184.00	-44.6	-281	36.5	293.1	184.000	109.1	687.5			
Maximum S	Storage Req	uried =			323.8					1006.9			
Notos													

Notes

1) Peak flow is equal to the product of 2.78 x C x I x A

2) Rainfall Intensity, $I = A/(T_D + C)^B$, where $T_D =$ storm duration (mins)

3) Release Rate = Desired Capture (Release) Rate

4) Storage Rate = Peak Flow - Release Rate

5) Storage = Duration x Storage Rate

6) Maximium Storage = Max Storage Over Duration

Table A5 Estimate of Storage Required for 5-yr and 100-yr Storms (Modified Rational Method)

	Area No:	Post 3		elopment A	Area					
	C _{AVG} =	0.21	(2-yr, 5-yr)							
	C _{AVG} =		(100-yr +2	5%)						
	e Interval =		(mins)							
Drain	age Area =	4.5000	(hectares)							
Release Rate =										
	Retu	rn Period =	5	(years)		Retu	rn Period =	100	(years)	
	IDF Parar	meters, A =	998.071	, B =	0.814	IDF Paran	neters, A =			0.820
Duration, T _D (min)		(=	A/(T _D +C) ^B	, C =	6.053		(=	A/(T _D +C) ^B	, C =	6.014
1 _D (11111)	Rainfall	Peak	Release	Storage	Ctorero	Rainfall	Peak	Release	Storage	Ctorogo
	Intensity, I	Flow	Rate	Rate	Storage	Intensity, I	Flow	Rate	Rate	Storage
	(mm/hr)	(L/sec)	(L/sec)	(L/sec)	(m ³)	(mm/hr)	(L/sec)	(L/sec)	(L/sec)	(m ³)
0	230.5	612.5	354.00	258.5	0	398.6	1324.3	354.000	970.3	0.0
5	141.2	375.2	354.00	21.2	6	242.7	806.3	354.000	452.3	135.7
10	104.2	276.9	354.00	-77.1	-46	178.6	593.2	354.000	239.2	143.5
15	83.6	222.1	354.00	-131.9	-119	142.9	474.7	354.000	120.7	108.6
20	70.3	186.7	354.00	-167.3	-201	120.0	398.5	354.000	44.5	53.4
25	60.9	161.8	354.00	-192.2	-288	103.8	345.0	354.000	-9.0	-13.5
30	53.9	143.3	354.00	-210.7	-379	91.9	305.2	354.000	-48.8	-87.8
35	48.5	128.9	354.00	-225.1	-473	82.6	274.3	354.000	-79.7	-167.3
40	44.2	117.4	354.00	-236.6	-568	75.1	249.6	354.000	-104.4	-250.5
45	40.6	108.0	354.00	-246.0	-664	69.1	229.4	354.000	-124.6	-336.4
50	37.7	100.1	354.00	-253.9	-762	64.0	212.5	354.000	-141.5	-424.6
55	35.1	93.3	354.00	-260.7	-860	59.6	198.1	354.000	-155.9	-514.5
60	32.9	87.6	354.00	-266.4	-959	55.9	185.7	354.000	-168.3	-605.9
65	31.0	82.5	354.00	-271.5	-1059	52.6	174.9	354.000	-179.1	-698.5
70	29.4	78.1	354.00	-275.9	-1159	49.8	165.4	354.000	-188.6	-792.1
75	27.9	74.1	354.00	-279.9	-1259	47.3	157.0	354.000	-197.0	-886.6
80	26.6	70.6	354.00	-283.4	-1360	45.0	149.5	354.000	-204.5	-981.8
85	25.4	67.4	354.00	-286.6	-1462	43.0	142.7	354.000	-211.3	-1077.6
90	24.3	64.6	354.00	-289.4	-1563	41.1	136.6	354.000	-217.4	-1174.1
95	23.3	61.9	354.00	-292.1	-1665	39.4	131.0	354.000	-223.0	-1271.1
100	22.4	59.6	354.00	-294.4	-1767	37.9	125.9	354.000	-228.1	-1368.5
105	21.6	57.4	354.00	-296.6	-1869	36.5	121.2	354.000	-232.8	-1466.3
	Storage Req	luried =			6.4					143.5
Notes										

1) Peak flow is equal to the product of 2.78 x C x I x A

2) Rainfall Intensity, $I = A/(T_D + C)^B$, where $T_D =$ storm duration (mins)

3) Release Rate = Desired Capture (Release) Rate

4) Storage Rate = Peak Flow - Release Rate

5) Storage = Duration x Storage Rate

6) Maximium Storage = Max Storage Over Duration

Table A6 Estimate of Storage Required for 5-yr and 100-yr Storms (Modified Rational Method)

Area No:Post 7Future Park Area $C_{AVG} =$ 0.36(2-yr, 5-yr) $C_{AVG} =$ 0.45(100-yr +25%)Time Interval =5(mins)										
Drainage Area = <u>0.5000</u> (hectares)										
Release Rate = 42.5 (L/sec) Release Rate = 42.5 (L/sec)										
		rn Period =		(years)			n Period =		(years)	
		neters, A =	-	, B =	0.814		neters, A =		,	0.820
Duration,			A/(T _D +C) ^B	, C =	6.053			A/(T _D +C) ^B	, C =	6.014
T _D (min)	Rainfall Intensity, I (mm/hr)	Peak Flow (L/sec)	Release Rate (L/sec)	Storage Rate (L/sec)	Storage (m ³)	Rainfall Intensity, I (mm/hr)	Peak Flow (L/sec)	Release Rate (L/sec)	Storage Rate (L/sec)	Storage (m ³)
0	230.5	114.5	42.50	72.0	0	398.6	247.6	42.500	205.1	0.0
5	141.2	70.2	42.50	27.7	8	242.7	150.8	42.500	108.3	32.5
10	104.2	51.8	42.50	9.3	6	178.6	110.9	42.500	68.4	41.0
15	83.6	41.5	42.50	-1.0	-1	142.9	88.8	42.500	46.3	41.6
20	70.3	34.9	42.50	-7.6	-9	120.0	74.5	42.500	32.0	38.4
25	60.9	30.3	42.50	-12.2	-18	103.8	64.5	42.500	22.0	33.0
30	53.9	26.8	42.50	-15.7	-28	91.9	57.1	42.500	14.6	26.2
35	48.5	24.1	42.50	-18.4	-39	82.6	51.3	42.500	8.8	18.5
40	44.2	22.0	42.50	-20.5	-49	75.1	46.7	42.500	4.2	10.0
45	40.6	20.2	42.50	-22.3	-60	69.1	42.9	42.500	0.4	1.1
50	37.7	18.7	42.50	-23.8	-71	64.0	39.7	42.500	-2.8	-8.3
55	35.1	17.5	42.50	-25.0	-83	59.6	37.0	42.500	-5.5	-18.0
60	32.9	16.4	42.50	-26.1	-94	55.9	34.7	42.500	-7.8	-28.0
65	31.0	15.4	42.50	-27.1	-106	52.6	32.7	42.500	-9.8	-38.2
70	29.4	14.6	42.50	-27.9	-117	49.8	30.9	42.500	-11.6	-48.6
75	27.9	13.9	42.50	-28.6	-129	47.3	29.4	42.500	-13.1	-59.2
80	26.6	13.2	42.50	-29.3	-141	45.0	27.9	42.500	-14.6	-69.9
85	25.4	12.6	42.50	-29.9	-152	43.0	26.7	42.500	-15.8	-80.7
90	24.3	12.1	42.50	-30.4	-164	41.1	25.5	42.500	-17.0	-91.6
95	23.3	11.6	42.50	-30.9	-176	39.4	24.5	42.500	-18.0	-102.6
100	22.4	11.1	42.50	-31.4	-188	37.9	23.5	42.500	-19.0	-113.7
105	21.6	10.7	42.50	-31.8	-200	36.5	22.7	42.500	-19.8	-124.9
Maximum S Notes	torage Req	uried =			8.3					41.6

1) Peak flow is equal to the product of 2.78 x C x I x A

2) Rainfall Intensity, I = A/ $(T_D + C)^B$, where T_D = storm duration (mins)

3) Release Rate = Desired Capture (Release) Rate

4) Storage Rate = Peak Flow - Release Rate

5) Storage = Duration x Storage Rate

6) Maximium Storage = Max Storage Over Duration

Table A7 CALCULATION OF AVAILABLE SURFACE STORAGE

Drainage Area	Location	Min W/L or T/G (m)	Indiv Spill Elev (m)	System Spill Elev (m)	¹ Max Depth (m)	Area (m²)	Max Volume (m ³)	Volume Required (m ³)	Adequate Storage Provided
Post 1	Roof				0.15	7500	375.0	363.9	Yes
Post 2	Parking	88.40	88.70	88.65	0.25	12879	1073.2	1006.9	Yes
Post 3	Future Dev	87.70	88.00	88.52	0.30	6270	627.0	143.5	Yes
Post 7	Future Park	88.00	88.30	88.00	0.30	906	90.6	41.6	Yes
Total							2165.8	1555.9	

¹The Max Depth is is the distance from the Min W/L (T/G) and the lower of the Indiv Spill or System Spill Elev

Storage volume is: V= Area x depth x 1/3

Parking Area Drainage Area 2

Orifice Sizing

CBMH221					
				SQUARE	CIRC
Event	Flow (L/s)	Head (m)	AREA(m ²)	1-side mm	(mmØ)
100 Year	183.8	3 31	0.038	195	220

Orifice Control Sizing

Q = 0.6 x A x (2gh)1/2 Where: Q is the release rate in m^3/s A is the orifice area in m^2 g is the acceleration due to gravity, 9.81m/s² h is the head of water above the orifice centre in m d is the diameter of the orifice in m

Pipe Invert =	84.74	m
Ponding Elevation =	88.65	m
Top of CB Elevation =	88.4	m

Future Development Drainage Area POST 3

Orifice Sizing

CBMH227					
			-	SQUARE	CIRC
Event	Flow (L/s)	Head (m)	AREA(m ²)	1-side mm	(mmØ)
	- (-)				(

Orifice Control Sizing

Q = 0.6 x A x (2gh)1/2 Where: Q is the release rate in m^3/s A is the orifice area in m^2 g is the acceleration due to gravity, 9.81m/s² h is the head of water above the orifice centre in m d is the diameter of the orifice in m

Pipe Invert =	85.71	m
Ponding Elevation =	88	m
Top of CB Elevation =	87.7	m

Future Park Drainage Area POST 7


Orifice Sizing

CBMH224					
				SQUARE	CIRC
Event	Flow (L/s)	Head (m)	AREA(m ²)	1-side mm	(mmØ)
100 Year	36.2	3.00	0.008	89	100

Orifice Control Sizing

Q = 0.6 x A x (2gh)1/2 Where: Q is the release rate in m^3/s A is the orifice area in m^2 g is the acceleration due to gravity, 9.81m/s² h is the head of water above the orifice centre in m d is the diameter of the orifice in m

Pipe Invert =	85.15	m
Ponding Elevation =	88.3	m
Top of CB Elevation =	88	m



	LEGEND:		
	MERCHEOU SOUNDARY	Y	
-	EXISTING TRUNK SE	WER	
		WER	
	TRUNK SE	WER	
		BOUNDARIES TRUNK DRAINAGE	
	AREA CON	TRIBUTED MAJOR	
	(MINOR TO	EASTERN TRUNK)	
	(70 AREA ID		
	1.51ha AREA (ha)	ORM SEWER	
	MANHOLE		
		TVITY OF HMENT MANHOLE	
	NOTE:		
	1. FOR ADDITIONAL DETAILS F SWMHYMO SCHEMATIC IN I	FIGURE 5	
	2. AREA 1 RUN OFF WILL BE C A DITCH INLET AT MH 690 A THE SWM FACILITY.	onveyed to ND enter	
	14		
	13		
	11		
	9		
	7		
	5		
	4 3 REVISED AS PER CIT	Y COMMENTS P.S. 12/10/01	
	2 REVISED AS PER CIT	Y COMMENTS P.S. 2/08/14 P.S. 2/05/30	
	No. REVISI		
	NHO IN CONTRACTOR		
	TRI 333 Towe Ottay	Presion Street r 1, Suite 400 va, Ontario da KIS 5N4	
	GROUP Tel (da KIS 5N4 613)225-1311 (613)225-9868	
10 M H			
		VEST (N5)	
		MANAGEMENT	
		- 1. W	
32	Orawing Title		1000
	AVALO	N WEST	
×	DRAINAGE	AREA PLAN	
A 2時	Scale	and the state of the	
	1:3000		
	Design	Date	
	R.B.	FEB. 2012 Checked	2
	S.V. Projeci No.	P.S. Drawing No.	
	30113	FIGURE 4	

C

Minto Communities Inc. AVALON WEST (NEIGHBOURHOOD 5) STORMWATER MANAGEMENT FACILITY DESIGN

Draina	ge Area	Flow (I/S) Weighted Runoff	3)	Manhole (XPSWMM	Saved Hy (SWMH)	ow from drograph (MO) – 3 cago (I/s)				
ID	Area (ha)	Coefficient	220 I/s/ha	Rational Method 10 Year 10 Min	Other Restriction (refer to Table 4.2)*	ID)	5 Year [†]	100 year [†]		
			E	astern Trunk						
HE3	3.61	n/a	0	0	30	MH 605				
TW3	1.45	0.70	0	344.7	0	(S605)	1015	1017		
	4.35	0.76	0	0	645.7	(3003)				
41	2.83	0.76	0	0	420.1	MH 607 (S607)	419	419		
HE2	6.40	n/a	0	0	30		1			
TW2	2.80	0.70	0	665.5	0	MH 612B	005	4000		
43	1.49	0.62	0	0	180.4	(S612B)	965	1002		
42	1.08	0.62	0	0	130.8					
22A	2.03	0.76	0	0	172.6	MH 602 (S602)	172	173		
22B	3.62	0.59	0	0	307.7	MH 617 (S617)	306	308		
23	3.16	n/a	0	0	268	MH 103 (S103)	106	267		
21A	4.62	0.59	0	0	392.7					
21D	3.28	0.59	0	0	278.8	1	2778			
24	8.86	0.57	0	0	753.1	MH 102		2782		
25	4.85	0.80	0	0	412.3	(S102)				
11	11.12	0.57	0	0	945.2	1				
BCB- E	3.02	0.70	0	717.8	0	MH 100	595	595	595	867
S1	0.68	0.76	149.6	0	0	(S100)				
51	1.53	0.76	335.5	0	0	141.004				
52	3.26	0.63	717.2	0	0	MH 201	807	1131		
S2	0.36	0.66	79.2	0	0	(S201)				
56	2.21	0.66	486.2	0	0	1411000				
58	2.66	0.71	585.2	0	0	MH 203	797	1123		
S3	0.24	0.66	52.8	0	0	(S203)				
57	2.01	0.41	442.2	0	0	MH 204				
S4	0.44	0.66	96.8	0	0	(S204)	222	538		
59	3.86	0.61	849.2	0	0	MH 205				
S5	0.62	0.62	136.4	0	0	(S205)	577	985		
61	2.27	0.63	499.4	0	0	,	- 10 JA			
62	11.32	0.68	2489.3	0	0	MH 206				
53	4.78	0.66	1051.6	0	0	(S206)	2391	4094		
S6	0.29	0.62	63.8	0	0					
10L	2.25	0.70	0	534.8	0	E-FS	369	535		
			-	estern Trunk	-		000			
31	2.06	0.59	0	0	353.2			300 - 0400 - 0400 - 00		
HE1	3.51	0.27	Ō	0	220.1	236				
TW1	1.75	0.70	Õ	416.0	0	(S236)	1442	1767		
30	9.16	0.66	Ő	0	778.6	1				
68	0.99	0.76	0	0	217.9	237	1033	1474		

Table 4.4Summary of Minor System Capture
(SWMHYMO Output 30113-D6.dat/out)

Minto Communities Inc. AVALON WEST (NEIGHBOURHOOD 5) STORMWATER MANAGEMENT FACILITY DESIGN

Draina	ge Area	Weighted Runoff		Flow (I/s)		Manhole (XPSWMM	Saved Hy (SWMH)	ow from /drograph /MO) – 3 cago (I/s)
ID	Area (ha)	Coefficient	220 l/s/ha	Rational Method 10 Year 10 Min	Other Restriction (refer to Table 4.2)*	ID)	5 Year [†]	100 year ^t
MB1	1.35	0.70	0	320.9	0	(S237)		
BCB- W	2.54	0.70	0	603.7	0			
70	1.51	0.66	332.2	0	0	1		
71	7.08	0.69	1654.4	0	0	630	1101	4074
78	1.05	0.66	231.0	0	0	(\$630)	1191	1874
77	0.53	0.65	116.6	0	0	607 (S607A)	92	167
80	0.76	0.66	167.2	0	0	631A (S631A)	128	167
73	8.14	0.63	1790.8	0	0	658	4440	0005
81	1.01	0.63	222.2	0	0	(S658)	1119	2005
82	0.93	0.62	204.6	0	0	659 (S659)	146	204
MB2	2.45	0.70	0	582.3	0			
79	6.08	0.59	1337.6	0	0	690	4070	2040
83	0.35	0.62	77.0	0	0	(\$690)	1070	2049
Area 1	103.4	n/a		Unrestrict	ed			
72	2.42	0.68	531.9	0	0			
74	6.35	0.66	1397.0	0	0	770	2200	4070
75	5.84	0.44	1284.8	0	0] (S770)	2388	4272
60	4.84	0.62	1064.8	0	0			

Table 4.4 cont.

Note: Refer to Table 4.2 for reference to other restriction rates.

† Results from the 5 and 100 year 3 hour Chicago evaluation from 30113-D6.dat/out as presented in Appendix B.

The inlet control restriction was set to match flow as indicated in **Table 4.4**. The results of the SWMHYMO evaluation indicate that when applying the inlet control restriction and storage requirements as indicated in **Table 4.4**, there is cascading flow from existing areas and some future areas north of BCB. The future development areas south of BCB are self-contained with some instances where major flow is conveyed via some drainage areas to the stormwater facility. It is anticipated that detail evaluation of the major system for the future development will be completed as part of detailed subdivision design submission. The evaluation should account for the conveyance of major flow from the existing upstream areas. As part of the detailed evaluation of the major system, the total ponding in low points is not to exceed a depth of 0.3 m under static or dynamic conditions. The surface ponding design has to ensure that emergency overflow paths are maintained and flows are conveyed safely to the end-of-pipe stormwater management facility. A safety board of 0.3 m above the emergency overflow high point and lowest house opening should be provided.

Major System

Based on the hydrological modeling undertaken for the entire site on a semi-lumped basis, there are some instances of cascading major flow from already constructed areas north of BCB and from arterial roadways within the subdivision area. The following table summarizes the estimated major flow within the site based on semi-lumped areas. It should be noted that as part of detailed evaluation of the subdivision areas, the total ponding in low points is not to exceed a depth of 0.3 m under static or dynamic conditions. The surface ponding design has to ensure that emergency overflow paths are maintained and flows are conveyed safely to the



5 year Free Flow Storm Sewer D	esign Sheet
--------------------------------	-------------

LOCA	ΓΙΟΝ	Area				TIME	RAINFALL	BLDG	PEAK	PIPE	PIPE			FULL FLOW	TIME OF	EXCESS	
FROM	то	(ha)	R=	INDIV 2.78 AR	ACCUM 2.78 AR	OF CONC.	INTENSITY I	FLOW Q (I/s)	FLOW Q (I/s)	SIZE (mm)	SLOPE (%)	LENGTH (m)	CAPACITY (I/s)	VELOCITY (m/s)	FLOW (min.)	CAPACITY (I/s)	Q/Qfull
CB101	CBMH203	0.05	0.90	0.14	0.14	10.00	104.19		14.08	200.0	0.50	26.0	23.22	0.74	0.59	9.14	0.61
CBMH203	CBMH202	0.04	0.90	0.11	0.24	10.59	101.19		24.56	250.0	0.50	26.0	42.09	0.86	0.51	17.53	0.58
00400	0004	0.04	0.00	0.44	0.44	40.00	404.40		44.47	250.0	0.50	00.0	40.00	0.00	0.54	20.00	0.07
CB102 CBMH201	CBMH201 CBMH202	0.04	0.90 0.90	0.11	0.11 0.24	10.00 10.51	104.19 101.59		11.47 23.89	250.0 250.0	0.50 0.50	26.0 26.0	42.09 42.09	0.86 0.86	0.51 0.51	30.62 18.20	0.27 0.57
CDIVITIZOT	CBIVII 1202	0.05	0.90	0.13	0.24	10.51	101.59		23.09	230.0	0.30	20.0	42.09	0.80	0.51	10.20	0.57
CBMH202	CBMH205	0.05	0.90	0.12	0.60	11.01	99.14		59.03	900.0	0.10	18.3	573.05	0.90	0.34	514.02	0.10
CB103	CBMH204	0.04	0.90	0.10	0.10	10.00	104.19		10.69	250.0	0.50	26.0	42.09	0.86	0.51	31.40	0.25
CBMH204	CBMH 205	0.03	0.90	0.08	0.18	10.51	101.59		18.56	250.0	0.50	26.0	42.09	0.86	0.51	23.54	0.44
	_																
CB104	CBMH206	0.04	0.90	0.09	0.09	10.00	104.19		9.65	250.0	0.50	26.0	42.09	0.86	0.51	32.45	0.23
CBMH206	CBMH205	0.04	0.90	0.09	0.19	10.51	101.59		18.81	250.0	0.50	26.0	42.09	0.86	0.51	23.28	0.45
CBMH 205	CBMH208	0.03	0.90	0.09	1.05	11.35	97.56		102.28	900.0	0.10	15.3	573.05	0.90	0.28	470.77	0.18
CDIVIT 203	CDIVIT 1200	0.00	0.90	0.09	1.00	11.00	97.50		102.20	900.0	0.10	10.0	575.05	0.90	0.20	470.77	0.10
CB105	CBMH209	0.06	0.90	0.15	0.15	10.00	104.19		15.64	250.0	0.50	26.0	42.09	0.86	0.51	26.45	0.37
CBMH209	CBMH208	0.05	0.90	0.13	0.28	10.51	101.59		27.96	250.0	0.50	26.0	42.09	0.86	0.51	14.13	0.66
CB106	CBMH207	0.05	0.90	0.13	0.13	10.00	104.19		13.03	250.0	0.50	26.0	42.09	0.86	0.51	29.06	0.31
CBMH207	CBMH208	0.05	0.90	0.13	0.25	10.51	101.59		25.42	250.0	0.50	26.0	42.09	0.86	0.51	16.67	0.60
		0.05	0.00	0.40	4.70	44.00	00.00		400.50	000.0	0.10	40.4	570 05	0.00	0.05	400.47	0.00
CBMH208	CBMH211	0.05	0.90	0.13	1.70	11.63	96.29		163.58	900.0	0.10	19.1	573.05	0.90	0.35	409.47	0.29
CB107	CBMH210	0.06	0.90	0.15	0.15	10.00	104.19		15.64	250.0	0.50	26.0	42.09	0.86	0.51	26.45	0.37
CBMH210	CBMH211	0.05	0.90	0.13	0.28	10.51	101.59		27.96	250.0	0.50	26.0	42.09	0.86	0.51	14.13	0.66
CB108	CBMH212	0.05	0.90	0.13	0.13	10.00	104.19		13.03	250.0	0.50	26.00	42.09	0.86	0.51	29.06	0.31
CBMH212	CBMH211	0.05	0.90	0.13	0.25	10.51	101.59		25.42	250.0	0.50	26.00	42.09	0.86	0.51	16.67	0.60
CBMH211	CBMH213	0.05	0.90	0.13	2.35	11.99	94.75		222.60	900.0	0.10	19.20	573.05	0.90	0.36	350.45	0.39
																	
																	L

CMMH216	CBMH215	0.14	0.90	0.35	0.35	10.00	104.19		36.50	450.0	0.20	60.00	127.63	0.80	1.25	91.14	0.29
											0.20	50.00					
CB110	CBMH214	0.04	0.90	0.10	0.10	10.00	104.19		10.43	250.0	0.50	27.50	42.09	0.86	0.54	31.66	0.25
CBM H214	CBMH25	0.17	0.90	0.43	0.53	10.54	101.45		53.30	450.0	0.20	52.00	127.63	0.80	1.08	74.33	0.42
CBMH215	CBMH213	0.19	0.90	0.48	1.35	11.62	96.37		130.20	525.0	0.20	100.80	192.52	0.89	1.89	62.32	0.68
CBMH213	CBMH222	0.23	0.90	0.58	4.28	13.51	88.71		379.33	1050.0	0.10	82.50	864.40	1.00	1.38	485.07	0.44
CBMH222	CBMH221	0.05	0.90	0.13	4.40	14.89	83.93		369.37	1050.0	0.10	50.00	864.40	1.00	0.84	495.03	0.43
00141047	000411040	0.00	0.70	0.54	0.54	40.00	101.10		50.77	450.0	0.00	20.00	407.00	0.00	0.70	70.00	0.44
CBMH217	CBMH218	0.28	0.70	0.54	0.54	10.00	104.19		56.77	450.0	0.20	38.00	127.63	0.80	0.79	70.86	0.44
		0.20	0.60	0.22	0.99	10.70	100.00		00.00	525.0	0.20	62.00	100 50	0.90	1 16	104 50	0.46
CBMH218	CBMH219	0.20	0.60	0.33	0.88	10.79	100.20		88.02	525.0	0.20	62.00	192.52	0.89	1.16	104.50	0.46
CBMH219	CBMH220	0.12	0.60	0.20	1.62	11.95	94.90		154.07	525.0	0.20	91.60	192.52	0.89	1.72	38.46	0.80
OBMINZ 10	ODIVITIZZO	0.12	0.00	0.20	1.02	11.00	04.00		104.07	525.0	0.20	51.00	102.02	0.00	1.72	00.40	0.00
CBMH220	CBMH221	0.35	0.60	0.58	2.21	13.67	88.11		194.49	600.0	0.20	68.00	274.87	0.97	1.17	80.38	0.71
BUILDING	CBMH229	0.79	0.90	1.98	1.98	10.00	104.19	23.00	23.00	450.0	0.20	25.00	127.63	0.80	0.52	104.63	0.18
CBMH229	CBMH331	0.00	0.90	0.00	0.00	10.52	101.53		23.00	450.0	0.20	7.50	127.63	0.80	0.16	104.63	0.18
CBMH231	CBMH230	0.07	0.90	0.18	0.18	10.68	100.75		40.65	525.0	0.20	23.50	192.52	0.89	0.44	151.88	0.21
CBMH227	CBMH230	4.50	0.21	2.63	2.63	10.00	104.19		273.73	900.0	0.20	130.00	810.41	1.27	1.70	536.69	0.34
CBMH230	CBMH225	0.00	0.00	0.00	2.80	11.70	95.99		268.97	750.0	0.20	24.00	498.38	1.13	0.35	229.40	0.54
00141004	0004110005	0.00	0.00	0.00	0.04	45.70	04.00		507.04	1200.0	0.10	45.00	4004.40	1.00	0.00	000.00	0.44
CBMH221	CBMH225	0.00	0.00	0.00	6.61	15.72	81.30		537.24	1200.0	0.10	15.00	1234.13	1.09	0.23	696.89	0.44
CBMH225	CBMH223	0.10	0.36	0.10	9.51	15.95	80.61		766.62	1200.0	0.10	73.50	1234.13	1.09	1.12	467.51	0.62
		0.10	0.50	0.10	9.01	10.80	00.01		100.02	1200.0	0.10	73.50	1204.10	1.09	1.12	407.31	0.02
		0.50	0.22	0.31	0.31	10.00	104.19		31.86	300.0	2.00	14.30	136.89	1.93	0.12	105.03	0.23
CBMH224		0.00	5.22	0.01	0.01				01.00	000.0	2.00	1 7.50		1.00	0.12		0.20
CBMH224	CBMH223								1							l	
CBMH224 CBMH223	Existing MH	0.10	0.36	0.10	9.92	17.07	77.40		767.58	1200.0	0.10	45.00	1234.13	1.09	0.69	466.56	0.62
		0.10	0.36	0.10	9.92	17.07	77.40		767.58	1200.0	0.10	45.00	1234.13	1.09	0.69	466.56	0.62
		0.10	0.36	0.10	9.92	17.07	77.40		767.58	1200.0	0.10	45.00	1234.13	1.09	0.69	466.56	0.62
		0.10	0.36	0.10	9.92	17.07	77.40		767.58	1200.0	0.10	45.00	1234.13	1.09	0.69	466.56	0.62
		0.10	0.36	0.10	9.92	17.07	77.40		767.58	1200.0	0.10	45.00	1234.13	1.09	0.69	466.56	0.62

Appendix B –

Email-Boundary Conditions Provided by the City of Ottawa

Pressure Check Under Max Day + FireFlow



2225 Mer Bleue Road - Boundary Conditions

Information Provided:

Date provided: 16 May 2018

	Demand						
Scenario	L/min	L/s					
Average Daily Demand	318	5.3					
Maximum Daily Demand	480	8.0					
Peak Hour	864	14.4					
Fire Flow Demand # 1	4,000	66.7					

Location:



Results:

Connection 1 - Brian Coburn Blvd

Demand Scenario	Head (m)	Pressure ¹ (psi)
Maximum HGL	130.4	59.4
Peak Hour	125.8	53.0
Max Day plus Fire (4,000 l/min)	126.2	53.5

¹ Ground Elevation = 88.58 m

Connection 2 - Gerry Lalonder Dr

Demand Scenario	Head (m)	Pressure ¹ (psi)
Maximum HGL	130.3	60.1
Peak Hour	125.6	53.4
Max Day plus Fire (4,000 l/min)	126.2	54.2

¹ Ground Elevation = 88.43 m

Notes:

- 1) As per the Ontario Building Code in areas that may be occupied, the static pressure at any fixture shall not exceed 552 kPa (80 psi.) Pressure control measures to be considered are as follows, in order of preference:
 - a) If possible, systems to be designed to residual pressures of 345 to 552 kPa (50 to 80 psi) in all occupied areas outside of the public right-of-way without special pressure control equipment.
 - b) Pressure reducing valves to be installed immediately downstream of the isolation valve in the home/ building, located downstream of the meter so it is owner maintained.
- 2) Fire flow was requested to be 3,700 L/min, however, modelled at 4,000 L/min due to a minor discrepancy noticed in the FUS submitted to the City of Ottawa.

Disclaimer

The boundary condition information is based on current operation of the city water distribution system. The computer model simulation is based on the best information available at the time. The operation of the water distribution system can change on a regular basis, resulting in a variation in boundary conditions. The physical properties of watermains deteriorate over time, as such must be assumed in the absence of actual field test data. The variation in physical watermain properties can therefore alter the results of the computer model simulation. Fire Flow analysis is a reflection of available flow in the watermain; there may be additional restrictions that occur between the watermain and the hydrant that the model cannot take into account.

Fire Flow Design Sheet

Project No. OTT-00240132



8-May-18

Date:

Building Design Assumptions - Sprinklered, Non-Combustible

1. An estimate of the Fire Flow required for a given fire area may be estimated by: $F = 220 \text{ C} \sqrt{A}$

F = required fire flow in litres per minute

C = coefficient related to the type of construction

1.5 for wood construction (structure essentially combustible)

1.0 for ordinary construction (brick or other masonry walls, combustible floor and interior)

- 0.8 for noncombustible construction (unprotected metal structural components, masonry or metal walls)
- 0.6 for fire-resistive construction (fully protected frame, floors, roof)

A = total floor area in square metres (including all storeys, but excluding basements at least 50% below grade) A = 9043 m^2

C = 0.8

F = 16736.2 L/min

rounded off to 17,000 L/min (min value of 2000 L/min)

2. The value obtained in 1. may be reduced by as much as 25% for occupancies having a low contents fire hazard.

Non-combustible	-25%		
Limited Combustible	-15%		
Combustible	0%		
Free Burning	15%		
Rapid Burning	25%		
Reduction due to low occupa	ncy hazard	-15% x 17,000 = 14,450 L/min	

3. The value obtained in 2. may be reduced by as much as 75% for buildings equipped with automatic sprinkler protection.

Non-combustible c/w Automatic Spri	-75%	
Combustible c/w Automatic Sprinkler	-50%	
No Automatic Sprinkler System	0%	
Reduction due to Sprinkler System	-75% x 14,450	= 3,613 L/min

4. The value obtained in 3. may be increased for structures exposed within 45 metres by the fire area under consideration.

3.1 10.1 20.1	Daration 0 to 3 m to 10 m to 20 m to 30 m to 45 m	<u>Charge</u> 25% 20% 15% 10% 5%				
Side 1 Side 2 Side 3 Side 4	70 85 100 100	0% 0% 0%	north side east side south side west side	(Total shall r	not exceed 75%)	
Increas	se due to	separation	0% x	3,613 =	3,613 L/min	
The fire	flow requ	irement is or or or		L/min L/sec gpm (us) gpm (uk)		

Water Pressure Analysis at Building for Max Day + Fireflow

Max day (8L/s) + FireFlow Max day (8L/s) + FireFlow			126.2 126.2		Brian Col Gerry Lal																		
Description	From	То	Flow (L/sec)	Pipe Dia (mm)	Dia (m)	Q (m³/sec)	Area (m2)	c	Vel (m/s)	Slope of HGL (m/m)		Frictional Head Loss hf (m)	Equivalent Pipe Length of Fittings (m)	Minor Loss of Fittings hь (m)		Start Ground Elev(m)	End Ground Elev (m)	Static Head (m)	Pressure kPa		Press kPa	ure To (psi)	Pressure Drop (psi)
Max Day + Fire Flow	Brian Coburn Blvd	Building	74.7	200	0.200	0.0747	0.0314159	125	2.3778	0.0290	153	4.432234003	39.8	1.15296	5.58519	88.58	89.20	-0.62	368.9	(53.5)	308.1	(44.7)	8.8
Max Day + Fire Flow	Gerry Lalonde Dr	Building	74.7	200	0.200	0.0747	0.0314159	125	2.3778	0.0290	201.3	5.831429443	27.0	0.78216	6.61359	88.43	89.20	-0.77	370.4	(53.7)	298.0	(43.2)	10.5
																						+	

Resistance of Fittings and Valves for 200mm WM from Brian Coburn Blvd to Building Resistance of Fittings and Valves for 200mm WM from Gerry Lalonde Dr to Building

	Loss in Equiv.					LOSS IN EQUIV.	Equiv.		Iotai	
	Length in Pipe	Equiv. Length		Total Equiv.		Length in Pipe	Length	Quantity	Equiv.	
Fittings	Diameters	(metres)	Quantity (each)	Length (m)	Fittings	Diameters	(metres)	(each)	Length	
Standard 90 ⁰ Elbow	32	6.40	3	19.2	Standard 90	32	6.40	3	19.2	
11.25 Degree Elbow	4	0.80	0	0	11.25 Degre	4	0.80	0	0	
45 Degree Elbow	16	3.20	4	12.8	45 Degree E	16	3.20	0	0	
Gate Valve Full -Open	13	2.60	3	7.8	Gate Valve	13	2.60	3	7.8	
		Total:	10	39.8			Total:	6	27	

Marc Alain Lafleur

From:	Darrell Noseworthy < Darrell.Noseworthy@smithandandersen.com>
Sent:	Tuesday, November 21, 2017 10:30 AM
То:	Marc Alain Lafleur; Havers, Christopher
Cc:	Alam Ansari; Kevin Sharples
Subject:	RE: OHH

Hi Marc/Chris,

The sprinkler demand for this building will be approximately 360 gpm.

Note that this value will be confirmed at the beginning of construction once the fire protection engineer completes his/her hydraulic calculations.

Regards,

Smith + Andersen

Darrell Noseworthy P.Eng., LEED AP Associate d 613 691 0272 m 613 325 7166

From: Marc Alain Lafleur [mailto:MarcAlain.Lafleur@exp.com]
Sent: November-16-17 3:47 PM
To: Havers, Christopher <Christopher.Havers@hdrinc.com>
Cc: Darrell Noseworthy <Darrell.Noseworthy@smithandandersen.com>; Alam Ansari <alam.ansari@exp.com>
Subject: OHH

Goo afternoon Chris,

Please note that we will require the sprinkler demand for the OHH facility. I have already spoken to Darrel regarding this request.

Furthermore, we will require the roof plan layout showing roof drain locations.

Thank you, Marc

'exμ

Marc Alain Lafleur, M.Eng., P.Eng. Project Engineer, Infrastructure exp Services Inc. t: +1.613.688.1899 x3298 | e: <u>marcalain.lafleur@exp.com</u> 100-2650 Queensview Drive Ottawa, ON K2B 8H6 Canada

<u>exp.com | legal disclaimer</u> keep it green, read from the screen

<u>exp.com</u> has been re-engineered! Visit the new **<u>exp.com</u>** today.