



**Stormwater Management & Servicing Report
KMA Mosque and Community Centre
351 Sandhill Road, Ottawa, Ontario**

Client:

Kanata Muslim Association
351 Sandhill Road
Ottawa, Ontario K2K 1X7

Project Number:

OTT-00238564-A0

Site Plan Application Number:

D07-12-17-0119

Prepared By: Marc Lafleur, M.Eng.

Reviewed By: Alam Ansari, M.Sc., P. Eng.

EXP Services Inc.
100-2650 Queensview Drive
Ottawa, ON K2B 8H6

Date Submitted:

September 13, 2017

July 3, 2018

November 23, 2018

Stormwater Management & Servicing Report **KMA Mosque and Community Centre, 351 Sandhill Road, Ottawa**

Type of Document:
Stormwater Management & Servicing Report

Client:
Kanata Muslim Association
351 Sandhill Road
Ottawa, Ontario K2K 1X7

Project Number:
OTT-00238504-A0

Prepared By:
exp Services Inc.
100-2650 Queensview Drive
Ottawa, Ontario K2B 8H6
Canada
T: 613 688-1899
F: 613 225-7337
www.exp.com




Aly Elgayar, M.A.Sc.
Engineering Designer
Infrastructure Services


Alam Ansari, M.Sc., P. Eng.
Senior Project Manager
Infrastructure Services

Date Submitted:
September 13, 2017
July 3, 2018
November 23, 2018

Legal Notification

This report was prepared by **EXP** Services Inc. for the account of Kanata Muslim Association. Any use which a third party makes of this report, or any reliance on or decisions to be made based on it, are the responsibility of such third parties. **EXP** Services Inc. accepts no responsibility for damages, if any, suffered by any third party as a result of decisions made or actions based on this project.

Table of Contents

| | | |
|----------|------------------------------------------|----------|
| 1 | Introduction | 1 |
| 2 | References | 2 |
| 3 | Regulatory Approvals | 2 |
| 4 | Geotechnical Considerations | 2 |
| 5 | Sanitary Sewer Design..... | 3 |
| 5.1 | Type of Establishment..... | 3 |
| 5.2 | Peak Design Flow | 3 |
| 5.3 | Downstream System | 3 |
| 6 | Watermain Design | 4 |
| 6.1 | Phase 1 Watermain Design..... | 4 |
| 6.2 | Phase 2 Watermain Design..... | 4 |
| 6.3 | Fire Hydrant | 5 |
| 7 | Stormwater Management..... | 5 |
| 7.1 | Storm Design Criteria | 5 |
| 7.2 | Pre-Development Conditions | 6 |
| 7.3 | Allowable Release Rate | 6 |
| 7.4 | Post-Development Conditions..... | 6 |
| 7.4.1 | Storage Requirements and Allocation..... | 7 |
| 7.4.2 | Flow Control Device Sizing | 7 |
| 7.4.3 | Summary of Proposed SWM System..... | 7 |
| 7.4.4 | Quality Control..... | 9 |
| 8 | Erosion and Sediment Control..... | 9 |
| 9 | Conclusions..... | 9 |

List of Appendices

Appendix A – Supporting Documents & Drawings
Appendix B1 – SWM Phase 1 Design Sheets
Appendix B2 – SWM Phase 2 Design Sheets
Appendix C – Water
Appendix D – Sewer Design Sheets
Appendix E – Drawings

1 Introduction

EXP Services Inc. was retained by **KMA** to prepare a Stormwater Management & Servicing Report in support of an application for Zoning By-law Amendment and Site Plan Control, to facilitate the use of the subject property as a place of worship (mosque and community centre) and for the conversion of the existing single detached dwelling for that use and the ultimate construction of an additional 2 storey, plus basement structure on the parcel of land municipally known as 351 Sandhill Road in City Ward 4-Kanata North.

This report provides a stormwater management and servicing design brief in support of the proposed phased development. The 0.8 ha site is generally flat with a gentle slope from west to east towards Sandhill Road. There is an existing single detached dwelling and a storage shed on the property. The dwelling will be converted for use as a mosque. The first phase of development will consist of converting the existing building into a place of worship and constructing a new parking lot on the west side of the existing building and a new access to the parking lot. The second phase of development will consist of a new 2 storey building constructed adjacent to the existing building. The 2 storey building which will include a basement will serve as a place of worship and a Community Centre.

There is an existing single detached, one floor dwelling on-site. The driveway entrance is along the frontage of Sandhill road with the asphalt driveway providing an access route to the southeast side of the dwelling. Remainder of the site is vegetation. The site is currently serviced by on-site water wells and a septic system. One of the three water wells is not in service and has been abandoned. The other two wells are currently in use to meet the domestic water supply and heating/cooling requirements of the existing dwelling. Refer to FIG-2 and the Existing Conditions plan in Appendix E for the pre-development conditions of the site.

The proposed development will be connected to the municipal services on Sandhill Road. The existing septic system will be removed. The two existing water wells will be used for the heating/cooling requirements of the existing building.

This servicing design brief will address SWM requirements for the phased development of the 0.8ha site and how the proposed phased development will be serviced with sanitary, storm and water services. Servicing, Grading and drainage and SWM plans for both phases of development are included with this report.

2 References

Various documents were referred to in preparing the current report including:

- City of Ottawa Sewer Design Guidelines Revision 2, October 2012 (SDG002)
 - Technical Bulletins ISDTB-2012-4, ISDTB-2014-01, PIEDTB-2016-01, ISTB-2018-01 and ISTB-2018-04
- City of Ottawa Water Distribution Design Guidelines, July 2010 (WDG001)
 - Technical Bulletins ISDTB-2014-02 and ISTB-2018-02
- Stormwater Management Planning and Design Manual, Ontario Ministry of the Environment, March 2003 (MOE SMPDM)
- Brookside Subdivision Infrastructure Study prepared by NOVATECH, November 2006
- Morgan's Creek Site Servicing Brief prepared by J.L. Richards & Associates, August 2011
- Geotechnical Investigation Report prepared by Paterson Group, November 2018

3 Regulatory Approvals

Approval from the MVCA is not required as per the communication from the City reviewer. No quality controls are required. Refer to the email in Appendix B1. An extension for the municipal sanitary sewer on Sandhill Road is proposed and as such approval is required from the MOECP. An ECA application will be submitted to acquire the approval.

4 Geotechnical Considerations

The following conclusions and recommendations from the geotechnical investigation report prepared by Paterson Group were taken into consideration:

- The subject site has a determined permissible grade raise restriction of 2 meters above the existing ground surface;
- Long-term ground water table is anticipated to be between 5 to 6 meters in depth;
- Development is recommended to have perimeter foundation and underslab drainage systems; however, the foundations design must be completed before drainage systems can be designed.

5 Sanitary Sewer Design

5.1 Type of Establishment

The ultimate development is to be a mosque and community center. The development will provide areas of worship and proposed amenities that include kitchens, meeting rooms and a gymnasium. Refer to the pre-consultation meeting notes in Appendix A.

The function of the proposed establishment is a place of worship and community center and thus is similar to a church or an Assembly hall as listed in Appendix 4-A of the City of Ottawa Sewer Design Guidelines (SDG02, 2012). The daily sewage flow for a church with kitchen facilities is selected.

5.2 Peak Design Flow

The site is currently serviced by an on-site septic system, which will be decommissioned. The existing 250mm diameter sanitary sewer on Sandhill Road is proposed to be extended and the proposed development will be serviced by a new sanitary sewer connected to the proposed municipal sanitary sewer extension. The anticipated peak sanitary flow from the existing building and the proposed addition has been calculated as per the City of Ottawa Sewer Design Guidelines (SDG02, 2012) and Technical Bulletin ISTB-2018-01. Peak flows were calculated for the ultimate site plan, refer to the pre-consultation notes in Appendix A. Occupancy loads provide by the architect, refer to the email in Appendix D. The anticipated peak sanitary flow is calculated as follows:

Design Flows

| | |
|-----------------------------------|-------------------------------------------------------------------------------------------------------------|
| Design Flow for Establishment: | 30 L/sanctuary seat (person) |
| Site Area: | 0.818 hectares |
| Peak Factor: | 1.5 |
| Existing Building Occupancy Load: | 180 persons |
| Proposed Addition Occupancy Load: | 1,271 persons |
| Extraneous Flow: | 0.33 L/s/ha |
| Peak Design Flow: | $=(30\text{L/person/day})(1451\text{persons})(1.5)+(0.818\text{ha})(0.33\text{L/s/ha})$ =1.03 L/s |

The new 2-storey building and the existing building will be serviced by two new 200mm diameter sanitary service. The proposed on-site sanitary sewer will be installed at a minimum grade of 0.5%. At this slope, the 200mm diameter sanitary sewer will have a capacity of 23.5 L/s and a full flow velocity of 0.86 m/s, which will be sufficient to service the site under both phases of development. The City of Ottawa Sewer Design Guidelines recommend a flow velocity between 0.8m/s to 3m/s. Refer to Appendix D for detailed calculations and Appendix E for Phase 1 & Phase 2 layout details on the Site Servicing plans (dwg nos. SS-1 & SS-2).

5.3 Downstream System

The downstream existing 250mm diameter municipal sanitary sewers on Sandhill road have approximately 19.22 L/sec available capacity. Thus, the existing municipal sewers have adequate capacity to accommodate the 1.03 L/sec peak flow from the site. Refer to the JLR and IBI sanitary design sheets and the IBI sanitary drainage area plan in Appendix A.

6 Watermain Design

6.1 Phase 1 Watermain Design

The site will be serviced by a new 200mm diameter watermain which will be connected to the existing 305mm diameter municipal watermain on Sandhill Road to meet the domestic and fire flow requirements for the site. The existing building will be serviced by a new 150mm diameter water service lateral connected to the new 200mm diameter watermain. The on-site existing wells will be decommissioned in phase 2 prior to construction. These wells will only be used for providing heating/cooling to the existing building in the interim. Design of the domestic water distribution system in phase 1 will ensure that there is no cross connection between the municipal and well water systems. Before occupancy, the mechanical engineer will provide written confirmation to the City that two systems are completely independent and there is no cross connection. Phase 1 domestic and fire flow demands were not calculated as per the pre-consultation meeting notes with the City. Determination of the demands and capacity of the system are based on the ultimate site plan. Refer to the pre-consultation notes in Appendix A.

6.2 Phase 2 Watermain Design

The proposed building will be serviced by a new 150mm diameter watermain extending from the internal 150mm diameter water service of the existing dwelling. Phase 2 domestic and fire flow demands were determined as follows:

Fire Flow Demand

The fire flow demand calculations were prepared based on the Fire Underwriters Survey (FUS, 1999) criteria. The new addition will be sprinklered and will be a non-combustible steel frame construction. The existing dwelling is combustible wood construction and is not sprinklered. Based on technical bulletin ISTB-2018-02 the classification for mixed construction rule of non-combustible construction applies, where 66.7% or over of the total wall, floor and roof area constructed are defined as non-combustible. Credits for sprinkler protection applied for the percentage of the floor area protected by sprinklers. Refer to Appendix C for detailed fire flow demand calculations and the type of construction confirmation from the architect.

The domestic water demands for the proposed site were calculated as per the City of Ottawa Water Distribution Guidelines and Technical Bulletin 2018-02.

Institutional Water Demand

Average daily demand:

$$\begin{aligned} &= 28,000 \text{ L/ha/day} \\ &= 0.818 \text{ ha} \times 28,000 \text{ L/ha/day} \times (1/86,400 \text{ s/day}) \\ &= 0.27 \text{ L/s} \end{aligned}$$

Maximum daily demand:

$$\begin{aligned} &= 1.5 \times \text{avg. day} \\ &= 1.5 \times 0.27 \text{ L/s} \\ &= 0.41 \text{ L/s} \end{aligned}$$

Maximum hourly daily demand:

$$\begin{aligned} &= 1.8 \times \text{max. day} \\ &= 1.8 \times 0.41 \text{ L/s} \\ &= 0.74 \text{ L/s} \end{aligned}$$

The site is located in the MG water distribution network pressure zone and the following boundary conditions were provided by the City of Ottawa (refer to Appendix C):

Peak Hour HGL = 124.2m

Maximum HGL = 131.2m

Max Day (0.41 L/s) + FireFlow (66.7L/s) = 125.1m

Based on the HGL of 124.2m for the peak hour scenario, 131.2m for the maximum HGL scenario, and 125.1m for the max day + fire flow scenario, pressure analyses were performed and residual pressures of 67.3 psi (463.9 kPa), 77.7 psi (535.5 kPa), and 66.5 psi (458.5 kPa), respectively, were estimated at the proposed 2 storey building. Refer to Appendix C for calculation details. The residual water pressures during the three scenarios are greater than the minimum requirement of 20psi (140kPa) as per the City of Ottawa Design Guidelines. The existing water supply system will therefore have adequate capacity to meet the domestic and fire demands for the proposed development.

6.3 Fire Hydrant

The fire flow demand for both buildings was calculated to be 67 L/s. An existing fire hydrant located across the proposed building on Sandhill road will provide fire protection for the proposed development. The unobstructed distance between the existing fire hydrant and the Siamese connection of the proposed building is 42m.

The existing fire hydrant has light blue colored cap that indicates it has a maximum flow of 95 L/sec at a residual pressure of 20 psi as rated by the City of Ottawa. Thus, the existing fire hydrant has adequate capacity to meet the site's fire flow demand. Table 5.3-1 below lists the minimum number of fire hydrants needed to deliver the required fire flow for the proposed building.

Table 6.3-1 – Minimum Number of Fire Hydrants for Required Fire Flow

| Block | Fire Flow Demand (L/min) | Fire Hydrant(s) within 75m | Fire Hydrant(s) within 150m |
|-------------------|--------------------------|----------------------------|-----------------------------|
| 351 Sandhill Road | 4000 | 1 | 0 |

7 Stormwater Management

7.1 Storm Design Criteria

The storm sewer system was designed in conformance with the City of Ottawa Sewer Design Guidelines (SDG02, 2012). The stormwater servicing design criteria for the proposed development is as follows:

- The proposed on-site storm sewer network / minor system, is designed using Rational Method and Manning's Equation to convey runoff under free flow conditions for the 5-year return period.

- Maximum allowable ponding depth is 300 mm.
- No surface ponding during 2 year storm events
- Flows from storms events greater than the 100-year return period will be directed overland towards Sandhill Rd.
- Average runoff coefficients were calculated for each inlet drainage area using a runoff coefficient of 0.20 for pervious surfaces and 0.90 for impervious surfaces.
- Estimated storage volumes are based on the Modified Rational Method.
- 100-year minor system flows to the sewer on Sandhill Rd must be controlled to the allowable release rate criteria of 85L/s/ha.
- Water quality will be provided by the existing off-site Briar Ridge Stormwater Management Facility.
- Minimum freeboard of 0.3m between the 100-year overland flow elevation and finished floor.

7.2 Pre-Development Conditions

The site is generally flat with a gentle slope from west to east towards Sandhill Road. There is no existing storm sewer system on the site. The stormwater runoff currently sheet drains overland towards Sandhill Road.

7.3 Allowable Release Rate

Minor system flows from the site to the 675mm diameter stormsewer on Sandhill Rd will be restricted to 85L/s/ha for up to the 100-year event. The allowable release rate criteria of 85L/s/ha was established as part of the Briar Ridge Phase 2 Subdivision. Refer to email from the City dated April 28, 2017 and the exert page from the Brookside Subdivision Infrastructure Study in Appendix A. The ICDs have been sized to ensure that there is no surface ponding during 2-year storm events. The allowable post development release rates from the site up to the 100-year storm events will be controlled to a release rate of 48.74 L/s for phase 1 of development. The allowable release rate for phase 1 is based on a development area of 0.57ha since only 0.57ha will be developed during phase 1. The allowable post development release rate for phase 2 for up to the 100-year storm events will be controlled to 68.8 L/s based on the entire site area of 0.81ha.

7.4 Post-Development Conditions

Stormwater will be controlled and released at a rate less than the allowable release rate for storms up to and including the 100-year storm event during both phases of development. An overland flow route is provided for storms greater than the 100-year event. Flow control devices will be installed in roof drains of the proposed 2 storey building and various catchbasins/manholes in order to control stormwater prior to its release from the site. The site under phase 1 and 2 post development conditions have been divided into 4 drainage areas, refer to Stormwater Management drawing SWM-1 and SWM-2 in Appendix E.

7.4.1 Storage Requirements and Allocation

Post development runoff will be detained on-site for storms up to and including the 100-year storm. The required SWM storage volumes will be achieved using the surface storage in the parking-lots and storage on the roof of the new building for storms up to the 100-year event. Underground pipe and structure storage volumes will be utilized to meet the criteria of no surface ponding during the 2-year storm events.

Surface ponding volumes over catch basins and catch basin manholes were determined by applying the pyramid volume equation of one-third of the depth multiplied by the surface area of the pond. Ponding depths for the subject site must be equal to or less than 300 mm for the 100-year storm event. There will be no surface ponding for 2-year storm events. Major overland flows from storms greater than the 100-year event will be directed to Sandhill Rd.

The volume of storage required was calculated for both the 2-year and 100-year storm events using the Rational Method. Since more storage is available than will be required in both the 2-year and 100-year events, the ponding level will be less than 300mm for the 100-year event. There will be no surface ponding during 2 year storm events.

For phase 1 of development, the 100-year on-site required and available storage volumes were estimated to be 180.9 m³ and 218.8 m³, respectively. The 2-year on-site required and available storage volumes were determined to be 34.3 m³ and 35.1m³, respectively.

For phase 2 of development, the 100-year on-site required and available storage volumes were determined to be 246.8 m³ and 275.8 m³, respectively. The 2-year on-site required and available storage volumes were determined to be 49 m³ and 92.1 m³, respectively.

Detailed stormwater management calculations are shown in Appendix B, including storage requirements and storage quantities provided. Appendix B1 contains the stormwater management calculations for phase 1 of development and Appendix B2 contains the calculations for phase 2 of development. Ponding levels and drainage areas for the site are shown on the post-development storm drainage plan SWM-1 and SWM-2 for Phase 1 and Phase 2, respectively. Refer to the drawings in Appendix E.

7.4.2 Flow Control Device Sizing

There are 2 Hydrovex-type ICDs proposed at the site. ICDs and their locations are shown on the Site Servicing plans and the Stormwater Management plans for both phase 1 and phase 2 of development, refer to drawings SS-1, SS-2, SWM-1 and SWM-2 in Appendix E. During the 100-year and 2-year storm events, CBMH203 will have design heads of 3.9m and 3.6m and allowable flowrates of 29.5L/sec and 28.0 L/sec, respectively. During the 100-year and 2-year storm events, CB101 will have design heads of 3.6m and 3.3m and allowable flowrates of 17.6 L/sec and 11.0 L/sec, respectively. Based on those criteria, Hydrovex ICD model 125VHV-2 is selected for CBMH203 and model 100-VHV-1 for CB101.

Refer to the Hydrovex selection graph in Appendix B1.

7.4.3 Summary of Proposed SWM System

A summary of the release rates for the controlled and uncontrolled drainage areas and corresponding storage details for phase 1 of development is provided in Table 6-1 below. Refer to Appendix B1 for detailed stormwater management spreadsheet calculations. The Post development 100-year controlled release rate from the site is of 47.1 L/s, which is less than the allowable limit of 48.74 L/s.

Table 7-1: Phase 1 Summary of Proposed On-Site SWM System

| Area ID | Area (ha) | Runoff Coefficient 'C' | 2 Year Release (L/s) | 2 Year storage required (m³) | 2 Year underground storage provided (m³) | 100 Year Release (L/s) | 100 Year storage required (m³) | 100 Year surface storage provided (m³) |
|---------------------------------------|-----------|------------------------|----------------------|------------------------------|------------------------------------------|------------------------|--------------------------------|----------------------------------------|
| PH1A | 0.486 | 0.79 | 28.0 | 34.3 | 35.1 | 29.5 | 139.7 | 193.5 |
| PH1B | 0.088 | 0.73 | 11.0 | 0.0 | 0.0 | 17.6 | 10.1 | 25.3 |
| TOTAL | | 0.57 | | | | | | |
| Totals: | | | 39.0 | 34.3 | 35.1 | 47.1 | 180.9 | 218.8 |
| Total Allowable Release (L/s): | | | 48.74 | | | | | |

A summary of the release rates for the controlled and uncontrolled drainage areas and corresponding storage details for phase 2 of development is provided in Table 6-2 below. Refer to Appendix B2 for detailed stormwater management spreadsheet calculations and refer to Appendix D for the sewer design sheet. The Post development 100-year controlled release rate from the Site is of 67.4L/s, which is less than the allowable limit of 68.85L/s.

Table 7-2: Phase 2 Summary of Proposed On-Site SWM System

| Area ID | Area (ha) | Runoff Coefficient 'C' | 2 Year Release (L/s) | 2 Year storage required (m³) | 2 Year underground storage provided (m³) | 100 Year Release (L/s) | 100 Year storage required (m³) | 100 Year surface storage provided (m³) |
|------------------------------------|-----------|------------------------|----------------------|------------------------------|------------------------------------------|------------------------|--------------------------------|----------------------------------------|
| PH2A | 0.498 | 0.78 | 28.0 | 35.1 | 35.1 | 29.5 | 173.3 | 193.5 |
| PH2B | 0.118 | 0.77 | 15.6 | 0.0 | 0.0 | 17.6 | 24.9 | 25.3 |
| PH2C | 0.145 | 0.90 | 7.0 | 13.9 | 57.0 | 10.0 | 48.7 | 57.0 |
| PH2D | 0.045 | 0.46 | 3.5 | 0.0 | 0.0 | 10.2 | 0.0 | 0.0 |
| TOTAL | | 0.81 | | | | | | |
| Totals: | | | 54.2 | 49.0 | 92.1 | 67.4 | 246.8 | 275.8 |
| Total Allowable Release L/s | | | 68.85 | | | | | |

As per the Morgan's Creek Site Servicing Brief, the HGL of the existing 675mm diameter storm sewer on Sandhill Road has an HGL equal to the invert of the pipe, which is 73.105. The proposed building's basement elevation is 74.20; thus, there is more than adequate clearance to satisfy the requirement of the HGL being a minimum of 0.3m below the underside of the footing. Refer to the 100-year storm sewer design sheet by J.L. Richards dated July 2011 in Appendix A.

7.4.4 Quality Control

The site is located in catchment area C-3, which is part of the overall drainage area collected by the existing Brookside Pond-C SWF. Moreover, Stormwater quality control will be provided by the existing Brookside Pond-C SWF since the facility provides level 2 water quality control as per the guidelines of the MOECP SWM planning and Design Manual. Therefore, no other water quality measures are proposed. Refer to email from the City dated April 28, 2017 in Appendix B1, exert pages and Figure-3 from the Brookside Subdivision Infrastructure Study and SWM Facilities Storm Drainage Area Plan in Appendix A.

8 Erosion and Sediment Control

During all construction activities, erosion and sedimentation shall be controlled by the following techniques:

- Extent of exposed soils shall be limited at any given time;
- Exposed areas shall be re-vegetated as soon as possible;
- Minimize the area to be cleared and disruption of adjacent areas;
- Siltsack or approved equivalent shall be installed inside all catch basins, catch basin manholes, and storm manholes as identified on the erosion and sediment control plan;
- Visual inspection shall be completed daily on sediment control barriers and any damage repaired immediately. Care will be taken to prevent damage during construction operations;
- In some cases, barriers may be removed temporarily to accommodate the construction operations. The affected barriers will be reinstated at night when construction is completed;
- Sediment control devices will be cleaned of accumulated silt as required. The deposits will be disposed of as per the requirements of the contract;
- During construction, if the engineer believes that additional prevention methods are required to control erosion and sedimentation, the contractor will install additional silt fences or other methods as required to the satisfaction of the engineer; and,
- Construction and maintenance requirements for erosion and sediment controls are to comply with Ontario Provincial Standard Specification (OPSS) 805.

9 Conclusions

This report addresses the adequacy of the existing municipal services to service the proposed development at 351 Sandhill Rd, Ottawa, Ontario. Based on the analysis provided in this report, the conclusions are as follows:

- A 200mm diameter water service connected to the 300mm municipal water main on Sandhill Road will adequately service the proposed development.
- A 200mm diameter sanitary service connected to the 250mm diameter municipal sanitary sewer extension on Sandhill Road will adequately service the proposed development.

- SWM for the proposed phased development will be achieved by restricting all storms up to the 100-year post development flow to the allowable release rate. The allowable release rate criteria of 85L/s/ha was established as part of the Briar Ridge Phase 2 Subdivision.
- Required on-site SWM storage volumes will be achieved using the surface storage in the parking-lots and storage on the roof of the new building for storms up to the 100 year event.
- Quality control will be provided by the existing Brookside Pond-C SWF, which receives flows from the 675mm storm sewer on Sandhill Road. No other water quality measures are proposed.
- Temporary erosion and sediment control measures for the subject site have been identified.
- Overland flow routes have been provided for the subject site.
- During all construction activities, erosion and sedimentation shall be controlled.

Appendix A – Supporting Documents & Drawings

3.2 Storm Drainage

Storm drainage for development within the Klondike Road Lands will be designed pursuant to the major-minor system philosophy. In this manner, right-of-way drainage will be collected through a series of roadway inlet catch basins and conveyed through a storm sewer system to a water quality and quantity treatment facility located downstream.

3.2.1 Minor System

Storm sewers will be sized to permit free flow conveyance of runoff generated from 1:5 year design storm using City of Ottawa IDF data. Flow restrictors will be installed at each inlet to the minor system to control inflows to a maximum rate of 85 L/s/ha to prevent storm sewer surcharging for the protection of dwellings and to balance the distribution of rainfall runoff stored on-site versus that released into the SWM facilities.

The design criteria used to determine the size of the storm sewers are as follows:

| | | |
|-------------------|---|-----------------|
| Minimum pipe size | = | 300 mm diameter |
| Minimum velocity | = | 0.8 m/s |
| Maximum velocity | = | 3.0 m/s |

The minor systems for both the Brookside Subdivision (Area D) and the south shore (Area C) areas will outlet to one of two proposed SWM facilities located immediately upstream of March Valley Road on the north side and south side of Shirley's brook, respectively.

The minor system for the west shore (Area A), including 5.8 ha of March Road, will outlet to a proposed SWM facility located between March Road and Shirley's Brook near the confluence of the northwest and southwest branches.

Detailed design calculations and drawings for the Brookside Subdivision (Areas D-2 and D-3) are available in the *Brookside Subdivision Infrastructure Servicing Study* (NECL, November 2006).

3.2.2 Major System

Major systems will be designed to convey flows in excess of the minor system capacity via overland flow routes within the public ROW to Shirley's Brook. On-site major system storage will be provided within road sags for runoff rates that exceed the capacity of the inlet control devices. Major system storage for Areas D-1 and D-2 has been calculated at 47 m³/ha, based on the detailed grading design of the Brookside Subdivision, and has been approximated at 50 m³/ha in the remaining areas for hydrologic modeling purposes. Runoff volumes exceeding the available on-site major system storage will be conveyed overland along the major system flow routes to Shirley's Brook. The major overland flow route for the Brookside Subdivision is shown on Drawing 103106-STM2.

The inflow rate to the minor system will be controlled using inlet control devices, with the objective of minimizing ponding for the 1:5 year storm event. In this way, major overland flow along roadways will only occur during infrequent rainfall events (> 1:5 year). Ponding will be restricted to a maximum depth of 0.30m in the right-of-way.

SWM facility 'D' has been sized to provide Level 2 water quality control as per the guidelines provided in *MOE SWM Planning and Design Manual*, and erosion control for all storms up to the 1:5 year event based on a target erosion control rate of 8-14 L/s/ha (from Table 4 of the Kanata North EMP).

The stage-storage-discharge curve for SWM Facility 'D' used in the post-development SWMHYMO model is provided in Table 7.1-1.

Table 7.1-1 SWM Facility 'D' - Stage-Storage-Discharge Curve

| Component | Elevation (m) | Volume | | | | Release Rate (L/s) |
|----------------------------|---------------|---------------------------|-----------------------------|--------------------------------|---------------------------------|--------------------|
| | | Forebay (m ³) | Main Cell (m ³) | Total Volume (m ³) | Active Volume (m ³) | |
| Pond Bottom | 65.00 | 0 | 0 | 0 | 0 | - |
| | 65.55 | 460 | 1,330 | 1,790 | 0 | - |
| Top of Forebay Berm | 65.75 | 730 | 2,120 | 2,850 | 0 | - |
| Normal Water Level | 66.05 | - | 4,330 | 4,330 | 0 | - |
| | 66.25 | - | 5,420 | 5,420 | 1,090 | 20 |
| Extended Detention | 66.45 | - | 6,530 | 6,530 | 2,200 | 29 |
| | 66.75 | - | 8,270 | 8,270 | 3,940 | 100 |
| | 67.00 | - | 9,810 | 9,810 | 5,480 | 210 |
| Erosion Control (1:5 year) | 67.25 | - | 11,420 | 11,420 | 7,090 | 300 |
| | 67.50 | - | 13,130 | 13,130 | 8,800 | 3,000 |


7.2 SWM Facility 'C'

SWM Facility 'C' will service Areas C-1, C-2 and C-3 shown on Figure 3. The total drainage area to this facility will be approximately 26.2 ha with an average imperviousness of 53% (see calculations in Appendix D).

Minor system flows from the upstream drainage area will ultimately be conveyed by storm sewers along Klondike Road to SWM Facility 'C'. Until such time as Klondike Road is fully urbanized east of the OCR crossing, the Klondike Road storm sewer will outlet into a temporary open channel along Klondike Road, which will convey minor system flows from the upstream drainage area to SWM Facility 'C'.

SWM facility 'C' has been sized to provide Level 2 water quality control as per the guidelines provided in *MOE SWM Planning and Design Manual*, and erosion control for all storms up to the 1:5 year event based on a target erosion control rate of 8-14 L/s/ha (from Table 4 of the Kanata North EMP).

The stage-storage-discharge curve for SWMF 'C' used in the post-development SWMHYMO model is provided in Table 7.2-1.



NOVATECH
ENGINEERING
CONSULTANTS LTD.
ENGINEERS & PLANNERS
 Suite 200, 240 Michael Cowpland Drive
 Ottawa, Ontario, Canada
 K2M 1P6
 Telephone (613) 254-9643
 Facsimile (613) 254-5867
 Email: novatech@novatech-eng.com

FIGURE 3
 KLONDIKE ROAD LANDS
 DRAINAGE AREA DELINEATION

103106 MAY 2006 N.T.S.

351 Sandhill Road: Pre-application Consultation Notes

July 7, 2016, Room 4103E

2:30 – 3:30pm

In attendance: Kathy Rygus (Planner, City of Ottawa), Nadege Balima (Project Manager, City of Ottawa), Mark Young (Design, City of Ottawa), John Bernier (Planner, City of Ottawa), Riley Carter (Transportation, City of Ottawa), Mark Richardson (Forester, City of Ottawa), Fredrick VanRooyen (Student Planner, City of Ottawa), Bill Holzman (Holzman Consultants Inc.), Stephanie Morris (Holzman Consultants Inc.), Virginia Robinson (LRL Associates Ltd.), Mehmood Shaikh (Kanata Muslim Association), Moinuddin Siddiqui (Kanata Muslim Association)

Proposal Summary


- Kanata Muslim Association community of worshipers in the Kanata North area are looking for a site for a new mosque. Current facility in a strip mall on March Road with other venues such as schools and gyms rented on an ongoing basis for large prayer services and Saturday school sessions
- The site at 351 Sandhill would be developed in three phases:
 - Phase 1: make the existing building structurally sound and undertake interior changes to use the space for a worship area; add required surface parking (20-30 spaces).
 - Phase 2: build an addition at rear of the existing building (2 storey multi use facility) and provide additional parking.
 - Phase 3: demolish existing building; full build out of new mosque, with worship and multiple purpose facilities.
- As the Kanata Muslim Association is a non-for-profit organization, fundraising is ongoing and it could be 5 to 10 years before mosque is built.
- Site is ideal due to surrounding institutional uses and convenient location to the Muslim community in Kanata North.
- Friday sessions and child care will still be accommodated at a larger venue.

Staff's preliminary comments on the proposal:

Servicing & Engineering (Nadege Balima)

- The site currently is privately serviced with well and septic system.
- Water, storm and sanitary pipes are located within Sandhill Road.
- The sanitary pipe was extended by Minto to serve their property immediately to the south of 351 Sandhill. The sanitary pipe does not extend to the property line. Sanitary is also available from Klondike Road. Staff were unable to find the design of Klondike Road sanitary sewer.
- If the sanitary line was not included in the design of Sandhill Road, extending the sewer would be needed and justification for capacity would be required. The as builts for the adjacent Minto site show that the sanitary is at the corner and would need to be extended. Capacity of the system should be based on the ultimate.
- If sanitary line needs to come from Klondike Road, municipal consent would be required. The City does not manage cost sharing and there would be no conditions or agreements for cost recovery from other owners to contribute.
- Ministry Of Environment Application would be required with a sanitary extension (transfer of review application).
- **Action:** Nadege Balima will search for any further infrastructure design to confirm the location of the sanitary line.
- Because the site is located within the urban area, municipal services are required to be installed at the time of the Phase 1 development, with the establishment of the parking lot.
- With a phased development, the engineering consultant will need to show how each phase will work independently as well as at the ultimate build-out.

Transportation (Riley Carter)



NOTE:
THE POSITION OF ALL POLE LINES, CONDUITS, WATERMAINS,
SEWERS AND OTHER UNDERGROUND AND OVERGROUND
UTILITIES AND STRUCTURES IS NOT NECESSARILY
SHOWN ON THE CONTRACT DRAWINGS, AND WHERE
SHOWN, THE ACCURACY OF THE POSITION OF SUCH
UTILITIES AND STRUCTURES IS NOT GUARANTEED
BEFORE STARTING WORK, DETERMINE THE EXACT
LOCATION OF ALL SUCH UTILITIES AND STRUCTURES
AND ASSUME ALL LIABILITY FOR DAMAGE TO THEM.

| NO. | REVISION | DATE | BY | NO. | REVISION | DATE | BY |
|-------|----------|------|----|-----|-----------------------------|-----------|-----|
| 1 | | | | 7 | ISSUED TO CLIENT | OCT 10/06 | MAB |
| 2 | | | | 8 | ISSUED FOR CONSTRUCTION | AUG 17/06 | MAB |
| 3 | | | | 9 | ISSUED WITH MOE APPLICATION | AUG 09/06 | MAB |
| 4 | | | | 10 | ISSUED FOR TENDER | MAY 26/06 | MAB |
| 5 | | | | 11 | ISSUED FOR MOE APPROVAL | MAY 01/06 | MAB |
| 6 | | | | 12 | REVISED PER CITY COMMENTS | APR 24/06 | MAB |
| 7 | | | | 13 | ISSUED TO CITY FOR REVIEW | MAR 20/06 | MAB |
| 8 | | | | 14 | | | |
| 9 | | | | 15 | | | |
| 10 | | | | 16 | | | |
| 11 | | | | 17 | | | |
| 12 | | | | 18 | | | |
| 13 | | | | 19 | | | |
| 14 | | | | 20 | | | |
| 15 | | | | 21 | | | |
| 16 | | | | 22 | | | |
| 17 | | | | 23 | | | |
| 18 | | | | 24 | | | |
| 19 | | | | 25 | | | |
| 20 | | | | 26 | | | |
| 21 | | | | 27 | | | |
| 22 | | | | 28 | | | |
| 23 | | | | 29 | | | |
| 24 | | | | 30 | | | |
| 25 | | | | 31 | | | |
| 26 | | | | 32 | | | |
| 27 | | | | 33 | | | |
| 28 | | | | 34 | | | |
| 29 | | | | 35 | | | |
| 30 | | | | 36 | | | |
| 31 | | | | 37 | | | |
| 32 | | | | 38 | | | |
| 33 | | | | 39 | | | |
| 34 | | | | 40 | | | |
| 35 | | | | 41 | | | |
| 36 | | | | 42 | | | |
| 37 | | | | 43 | | | |
| 38 | | | | 44 | | | |
| 39 | | | | 45 | | | |
| 40 | | | | 46 | | | |
| 41 | | | | 47 | | | |
| 42 | | | | 48 | | | |
| 43 | | | | 49 | | | |
| 44 | | | | 50 | | | |
| 45 | | | | 51 | | | |
| 46 | | | | 52 | | | |
| 47 | | | | 53 | | | |
| 48 | | | | 54 | | | |
| 49 | | | | 55 | | | |
| 50 | | | | 56 | | | |
| 51 | | | | 57 | | | |
| 52 | | | | 58 | | | |
| 53 | | | | 59 | | | |
| 54 | | | | 60 | | | |
| 55 | | | | 61 | | | |
| 56 | | | | 62 | | | |
| 57 | | | | 63 | | | |
| 58 | | | | 64 | | | |
| 59 | | | | 65 | | | |
| 60 | | | | 66 | | | |
| 61 | | | | 67 | | | |
| 62 | | | | 68 | | | |
| 63 | | | | 69 | | | |
| 64 | | | | 70 | | | |
| 65 | | | | 71 | | | |
| 66 | | | | 72 | | | |
| 67 | | | | 73 | | | |
| 68 | | | | 74 | | | |
| 69 | | | | 75 | | | |
| 70 | | | | 76 | | | |
| 71 | | | | 77 | | | |
| 72 | | | | 78 | | | |
| 73 | | | | 79 | | | |
| 74 | | | | 80 | | | |
| 75 | | | | 81 | | | |
| 76 | | | | 82 | | | |
| 77 | | | | 83 | | | |
| 78 | | | | 84 | | | |
| 79 | | | | 85 | | | |
| 80 | | | | 86 | | | |
| 81 | | | | 87 | | | |
| 82 | | | | 88 | | | |
| 83 | | | | 89 | | | |
| 84 | | | | 90 | | | |
| 85 | | | | 91 | | | |
| 86 | | | | 92 | | | |
| 87 | | | | 93 | | | |
| 88 | | | | 94 | | | |
| 89 | | | | 95 | | | |
| 90 | | | | 96 | | | |
| 91 | | | | 97 | | | |
| 92 | | | | 98 | | | |
| 93 | | | | 99 | | | |
| 94 | | | | 100 | | | |
| 95 | | | | 101 | | | |
| 96 | | | | 102 | | | |
| 97 | | | | 103 | | | |
| 98 | | | | 104 | | | |
| 99 | | | | 105 | | | |
| 100 | | | | 106 | | | |
| 101 | | | | 107 | | | |
| 102 | | | | 108 | | | |
| 103 | | | | 109 | | | |
| 104 | | | | 110 | | | |
| 105 | | | | 111 | | | |
| 106 | | | | 112 | | | |
| 107 | | | | 113 | | | |
| 108 | | | | 114 | | | |
| 109 | | | | 115 | | | |
| 110 | | | | 116 | | | |
| 111 | | | | 117 | | | |
| 112 | | | | 118 | | | |
| 113 | | | | 119 | | | |
| 114 | | | | 120 | | | |
| 115 | | | | 121 | | | |
| 116 | | | | 122 | | | |
| 117 | | | | 123 | | | |
| 118 | | | | 124 | | | |
| 119 | | | | 125 | | | |
| 120 | | | | 126 | | | |
| 121 | | | | 127 | | | |
| 122 | | | | 128 | | | |
| 123 | | | | 129 | | | |
| 124 | | | | 130 | | | |
| 125 | | | | 131 | | | |
| 126 | | | | 132 | | | |
| 127 | | | | 133 | | | |
| 128 | | | | 134 | | | |
| 129 | | | | 135 | | | |
| 130 | | | | 136 | | | |
| 131 | | | | 137 | | | |
| 132 | | | | 138 | | | |
| 133 | | | | 139 | | | |
| 134 | | | | 140 | | | |
| 135 | | | | 141 | | | |
| 136 | | | | 142 | | | |
| 137 | | | | 143 | | | |
| 138 | | | | 144 | | | |
| 139 | | | | 145 | | | |
| 140 | | | | 146 | | | |
| 141 | | | | 147 | | | |
| 142 | | | | 148 | | | |
| 143 | | | | 149 | | | |
| 144 | | | | 150 | | | |
| 145 | | | | 151 | | | |
| 146 | | | | 152 | | | |
| 147 | | | | 153 | | | |
| 148 | | | | 154 | | | |
| 149 | | | | 155 | | | |
| 150 | | | | 156 | | | |
| 151 | | | | 157 | | | |
| 152 | | | | 158 | | | |
| 153 | | | | 159 | | | |
| 154 | | | | 160 | | | |
| 155 | | | | 161 | | | |
| 156 | | | | 162 | | | |
| 157 | | | | 163 | | | |
| 158 | | | | 164 | | | |
| 159 | | | | 165 | | | |
| 160 | | | | 166 | | | |
| 161 | | | | 167 | | | |
| 162 | | | | 168 | | | |
| 163 | | | | 169 | | | |
| 164 | | | | 170 | | | |
| 165 | | | | 171 | | | |
| 166 | | | | 172 | | | |
| 167 | | | | 173 | | | |
| 168 | | | | 174 | | | |
| 169 | | | | 175 | | | |
| 170 | | | | 176 | | | |
| 171 | | | | 177 | | | |
| 172 | | | | 178 | | | |
| 173 | | | | 179 | | | |
| 174 | | | | 180 | | | |
| 175 | | | | 181 | | | |
| 176 | | | | 182 | | | |
| 177 | | | | 183 | | | |
| 178 | | | | 184 | | | |
| 179 | | | | 185 | | | |
| 180 | | | | 186 | | | |
| 181 | | | | 187 | | | |
| 182 | | | | 188 | | | |
| 183 | | | | 189 | | | |
| 184 | | | | 190 | | | |
| 185 | | | | 191 | | | |
| 186 | | | | 192 | | | |
| 187 | | | | 193 | | | |
| 188 | | | | 194 | | | |
| 189 | | | | 195 | | | |
| 190 | | | | 196 | | | |
| 191 | | | | 197 | | | |
| 192 | | | | 198 | | | |
| 193 | | | | 199 | | | |
| 194 | | | | 200 | | | |
| 195 | | | | 201 | | | |
| 196 | | | | 202 | | | |
| 197 | | | | 203 | | | |
| 198 | | | | 204 | | | |
| 199 | | | | 205 | | | |
| 200 | | | | 206 | | | |
| 201 | | | | 207 | | | |
| 202 | | | | 208 | | | |
| 203 | | | | 209 | | | |
| 204 | | | | 210 | | | |
| 205 | | | | 211 | | | |
| 206 | | | | 212 | | | |
| 207 | | | | 213 | | | |
| 208 | | | | 214 | | | |
| 209 | | | | 215 | | | |
| 210 | | | | 216 | | | |
| 211 | | | | 217 | | | |
| 212 | | | | 218 | | | |
| 213 | | | | 219 | | | |
| 214 | | | | 220 | | | |
| 215 | | | | 221 | | | |
| 216 | | | | 222 | | | |
| 217 | | | | 223 | | | |
| 218 | | | | 224 | | | |
| 219 | | | | 225 | | | |
| 220 | | | | 226 | | | |
| 221 | | | | 227 | | | |
| 222 | | | | 228 | | | |
| 223 | | | | 229 | | | |
| 224 | | | | 230 | | | |
| 225 | | | | 231 | | | |
| 226 | | | | 232 | | | |
| 227 | | | | 233 | | | |
| 228 | | | | 234 | | | |
| 229 | | | | 235 | | | |
| 230 | | | | 236 | | | |
| 231 | | | | 237 | | | |
| 232 | | | | 238 | | | |
| 233 | | | | 239 | | | |
| 234 | | | | 240 | | | |
| 235 | | | | 241 | | | |
| 236 | | | | 242 | | | |
| 237 | | | | 243 | | | |
| 238 | | | | 244 | | | |
| 239 | | | | 245 | | | |
| 240 | | | | 246 | | | |
| 241 | | | | 247 | | | |
| 242 | | | | 248 | | | |
| 243 | | | | 249 | | | |
| 244 | | | | 250 | | | |
| 245 | | | | 251 | | | |
| 246 | | | | 252 | | | |
| 247 | | | | 253 | | | |
| 248 | | | | 254 | | | |
| 249 | | | | 255 | | | |
| 250 | | | | 256 | | | |
| 251 | | | | 257 | | | |
| 252 | | | | 258 | | | |
| 253 | | | | 259 | | | |
| 254 | | | | 260 | | | |
| 255 | | | | 261 | | | |
| 256 | | | | 262 | | | |
| 257 | | | | 263 | | | |
| 258 | | | | 264 | | | |
| 259 | | | | 265 | | | |
| 260 | | | | 266 | | | |
| 261 | | | | 267 | | | |
| 262 | | | | 268 | | | |
| 263 | | | | 269 | | | |
| 264 | | | | 270 | | | |
| 265 | | | | 271 | | | |
| 266 | | | | 272 | | | |
| 267 | | | | 273 | | | |
| 268 | | | | 274 | | | |
| 269 | | | | 275 | | | |
| 270 | | | | 276 | | | |
| 271 | | | | 277 | | | |
| 272 | | | | 278 | | | |
| 273 | | | | 279 | | | |
| 274 | | | | 280 | | | |
| 275 | | | | 281 | | | |
| 276 | | | | 282 | | | |
| 277 | | | | 283 | | | |
| 278 | | | | 284 | | | |
| 279 | | | | 285 | | | |
| 280 | | | | 286 | | | |
| 281 | | | | 287 | | | |
| 282 | | | | 288 | | | |
| 283</ | | | | | | | |


100 YEAR IDF CURVE
Manning's Coefficient (n) = 0.013

Filename: V:\24566.LD Minto Lands\Design\SAN & STORM DESIGN SHEETS\STORM DES SHEET_Morgan's Creek_REV 1.XLS



PROJECT: Briar Ridge Phase 2 - Sandhill Road
LOCATION: City of Ottawa
CLIENT: Tenth Line Development Inc.

J:\10518 BriarRdg\215.7 Calculations\CCS_Sanitary Sewer Design Sheet_2009-03-05 05/10/2010 1:56 PM



LEGEND:


| | |
|------|------------------|
| 7.49 | AREA IN HECTARES |
| 770 | POPULATION |

| | | | |
|-----|---------------------|----|----------|
| 14 | | | |
| 13 | | | |
| 12 | | | |
| 11 | | | |
| 10 | | | |
| 9 | | | |
| 8 | | | |
| 7 | | | |
| 6 | | | |
| 5 | | | |
| 4 | | | |
| 3 | | | |
| 2 | | | |
| 1 | ISSUED FOR APPROVAL | | 06.03.04 |
| No. | REVISIONS | By | Date |

TENTH LINE DEVELOPMENT INC.

IBI GROUP
1770 Woodward Drive
Suite 100
Ottawa, Ontario
Canada K2C 0P6
Tel: (613) 225-1311
Fax: (613) 225-9968

Project Title
**BRIAR RIDGE
PHASE 2**



Drawing Title
**SANITARY DRAINAGE
AREA PLAN
SANDHILL ROAD**

Scale
1:1000

| | | | |
|-------------|--------|-------------|-----------|
| Design | L.M.E. | Date | MARCH '09 |
| Drawn | M.M. | Checked | R.W.W. |
| Project No. | 10518 | Drawing No. | 501-1 |



MORGAN'S CREEK
CITY OF OTTAWA
MINTO COMMUNITIES INC.
JLR PROJECT NO.: 24566

| | | |
|---------------------------------|--------|-----------|
| Commercial/Institutional Flow = | 50,000 | L/s/ha |
| q = | 350 | L/cap/d |
| i = | 0.28 | L/s/ha |
| TOWNS HOUSING | 2.7 | pers/unit |
| STACKS HOUSING | 2.7 | pers/unit |
| SINGLES HOUSING | 3.4 | pers/unit |
| Manning's Coefficient (n) = | 0.013 | |

SANITARY SEWER DESIGN SHEET
Designed: K.F.
Checked By: L.D.

Date: August 2011

| STREET | SAN MH # | | RESIDENTIAL | | | | | | | | | COM/INST | | | RES+ COM + INFILTR. | | SEWER DATA | | | | | UPSTREAM | | | | | DOWNSTREAM | | | | | |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------|--------------|-----------------|-----------|---------|-----------|---------|------------|-------|----------------|---------------|----------|---------------|-------------------|---------------------|--------------------|----------------------------------------------------------------------------------------|---------|------------|-----------------|----------|-------------|-------------|--------|--------|-------|-------------|-------|--------|--------|-------|------|
| | | | NUMBER OF UNITS | | | | | CUMULATIVE | | PEAKING FACTOR | POP. FLOW L/s | AREA ha | CUM. AREA L/s | COM/INST FLOW L/s | PEAK EXTR. FLOW L/s | PEAK DES. FLOW L/s | DIA. mm | SLOPE % | CAPAC. L/s | VEL. (full) m/s | LENGTH m | Center Line | Obvert Drop | Obvert | Invert | Cover | Center Line | | Obvert | Invert | Cover | |
| | SINGLES units | STACKS units | TOWNS units | POP. pers | AREA ha | POP. pers | AREA ha | | | | | | | | | | | | | | | | | | | | | | | | | |
| FLOW TO 250mmØ SANITARY - SANDHILL ROAD | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Private Road | 7 | 6 | 12 | | | 32 | 0.20 | 32 | 0.20 | 4.00 | 0.53 | | | | | 0.05 | 0.58 | 200 | 0.33 | 19.66 | 0.61 | 21.80 | 76.70 | 0.02 | 74.65 | 74.45 | 2.05 | 76.60 | | 74.58 | 74.38 | 2.02 |
| Private Road | 6 | 5 | 24 | | | 65 | 0.25 | 97 | 0.45 | 4.00 | 1.58 | | | | | 0.12 | 1.70 | 200 | 0.33 | 19.66 | 0.61 | 36.10 | 76.60 | 0.02 | 74.56 | 74.36 | 2.04 | 76.90 | | 74.44 | 74.24 | 2.46 |
| Private Road | 5 | 4 | 24 | | | 65 | 0.43 | 162 | 0.88 | 4.00 | 2.63 | | | | | 0.25 | 2.87 | 200 | 0.33 | 19.66 | 0.61 | 55.40 | 76.90 | 0.02 | 74.42 | 74.22 | 2.48 | 76.80 | | 74.24 | 74.04 | 2.56 |
| Private Road | 4 | 3 | 12 | | | 32 | 0.11 | 194 | 0.99 | 4.00 | 3.15 | | | | | 0.28 | 3.43 | 200 | 0.33 | 19.66 | 0.61 | 22.00 | 76.80 | | 74.22 | 74.02 | 2.58 | 76.50 | | 74.15 | 73.95 | 2.35 |
| Private Road | 3 | 2 | 12 | | | 32 | 0.16 | 227 | 1.15 | 4.00 | 3.68 | | | | | 0.32 | 4.00 | 200 | 0.33 | 19.66 | 0.61 | 34.70 | 76.50 | 0.04 | 74.15 | 73.95 | 2.35 | 76.90 | | 74.03 | 73.83 | 2.87 |
| Private Road | 2 | 1 | 16 | | | 43 | 0.28 | 270 | 1.43 | 4.00 | 4.38 | | | | | 0.40 | 4.78 | 200 | 0.33 | 19.66 | 0.61 | 59.70 | 76.90 | | 73.99 | 73.79 | 2.91 | 76.70 | | 73.79 | 73.59 | 2.91 |
| Private Road | 8 | 1 | | 4 | | 11 | 0.11 | 11 | 0.11 | 4.00 | 0.18 | | | | | 0.03 | 0.21 | 200 | 2.50 | 54.10 | 1.67 | 32.00 | 77.25 | 0.06 | 74.65 | 74.45 | 2.60 | 76.70 | | 73.85 | 73.65 | 2.85 |
| Private Road/ Sandhill Road | 1 | EX. 300A | | | | | 0.02 | 281 | 1.56 | 4.00 | 4.55 | | | | | 0.44 | 4.99 | 200 | 0.33 | 19.66 | 0.61 | 36.00 | 76.70 | | 73.79 | 73.59 | 2.91 | 76.80 | | 73.68 | 73.48 | 3.13 |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | 100 | 4 | 281 | 1.56 | | | | | | | | | | | | | | | | | | | | | | | | | |
| <div>SANDHILL ROAD- AS BUILT INFORMATION</div> <div>Ex. Inv @ SANMH 300A (SE)73.425</div> <div>Ex. Obv @ SANMH 300A(SE)73.675</div> <div>Information taken from IBI Group As-Built Plans - Briar Ridge Phase 2</div> <div>DWG No. 109-1, Rev 5 (As-built) - Sandhill Road (Sta. 1+000 to Klondike)</div> | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| FLOW TO SANITARY - MARCH ROAD/ MERSEY DRIVE | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Private Road | 11 | 10 | 56 | | | 151 | 0.71 | 151 | 0.71 | 4.00 | 2.45 | | | | | 0.20 | 2.65 | 200 | 0.50 | 24.19 | 0.75 | 74.90 | 78.60 | 0.06 | 76.57 | 76.37 | 2.03 | 78.50 | | 76.20 | 76.00 | 2.30 |
| Private Road | 10 | 9 | | | | | 0.05 | 151 | 0.76 | 4.00 | 2.45 | | | | | 0.21 | 2.66 | 200 | 0.50 | 24.19 | 0.75 | 34.50 | 78.50 | 0.06 | 76.14 | 75.94 | 2.36 | 78.40 | | 75.97 | 75.77 | 2.43 |
| Commercial Site - 788 March RD | Future Site | 9 | | | | | | | | | | 0.83 | 0.83 | 0.72 | 0.23 | 0.95 | Detailed Design of Commercial Site located at 788 March Road to be completed in future | | | | | | | | | | | | | | | |
| Private Rd /March Rd/ Mersey Dr | 9 | 12 | | | | | | 151 | 0.76 | 4.00 | 2.45 | | 0.83 | 0.72 | 0.45 | 3.62 | 200 | 0.67 | 28.04 | 0.86 | 47.08 | 78.40 | 0.03 | 75.91 | 75.71 | 2.49 | 78.70 | | 75.59 | 75.39 | 3.11 | |
| Mersey Drive | 12 | 13 | | | | | | 151 | 0.76 | 4.00 | 2.45 | | 0.83 | 0.72 | 0.45 | 3.62 | 200 | 0.35 | 20.24 | 0.62 | 38.80 | 78.70 | | 75.56 | 75.36 | 3.14 | 79.02 | | 75.42 | 75.22 | 3.59 | |
| Mersey Drive | 124 | 13 | | | | 4 | 0.14 | 4 | 0.14 | 4.00 | 0.06 | | | | | 0.04 | 0.10 | 200 | 0.55 | 25.38 | 0.78 | 33.00 | 79.27 | | 75.60 | 75.40 | 3.66 | 79.02 | | 75.42 | 75.22 | 3.60 |
| Mersey Drive | 13 | 123 | | | | 24 | 0.30 | 179 | 1.20 | 4.00 | 2.90 | | 0.83 | 0.72 | 0.57 | 4.19 | 200 | 0.55 | 25.38 | 0.78 | 63.30 | 79.02 | | 75.42 | 75.22 | 3.60 | 79.46 | | 75.07 | 74.87 | 4.39 | |
| Mersey Drive | 123 | 108 | | | | 32 | 0.42 | 211 | 1.62 | 4.00 | 3.42 | | | | | 0.45 | 3.88 | 200 | 0.59 | 26.28 | 0.81 | 109.20 | 79.46 | | 75.07 | 74.87 | 4.40 | 80.00 | | 74.42 | 74.22 | 5.58 |
| Mersey Drive | 122 | 121 | | | | 24 | 0.38 | 24 | 0.38 | 4.00 | 0.39 | | | | | 0.11 | 0.50 | 200 | 3.78 | 66.52 | 2.05 | 63.50 | 84.45 | | 80.40 | 80.20 | 4.05 | 81.82 | | 78.00 | 77.80 | 3.82 |
| Mersey Drive | 121 | 120 | | | | 24 | 0.28 | 48 | 0.66 | 4.00 | 0.78 | | | | | 0.18 | 0.96 | 200 | 2.53 | 54.43 | 1.68 | 68.00 | 81.82 | | 77.90 | 77.70 | 3.92 | 80.27 | | 76.18 | 75.98 | 4.09 |
| Residential Private Road | 3 | 2 | 12 | | | 32 | 0.26 | 32 | 0.26 | 4.00 | 0.53 | | | | | 0.07 | 0.60 | 200 | 0.90 | 32.46 | 1.00 | 52.70 | 84.25 | 0.06 | 81.66 | 81.46 | 2.59 | 84.20 | | 81.19 | 80.99 | 3.01 |
| Residential Private Road | 2 | 1A | | 16 | | 43 | 0.33 | 76 | 0.59 | 4.00 | 1.23 | | | | | 0.17 | 1.39 | 200 | 0.90 | 32.46 | 1.00 | 89.20 | 84.20 | 0.60 | 81.13 | 80.93 | 3.07 | 82.45 | | 80.33 | 80.13 | 2.12 |
| Residential Private Road | 3 | 4 | 28 | | | 76 | 0.41 | 76 | 0.41 | 4.00 | 1.23 | | | | | 0.11 | 1.34 | 200 | 0.90 | 32.46 | 1.00 | 69.30 | 84.25 | 0.06 | 80.71 | 80.51 | 3.54 | 82.80 | | 80.09 | 79.89 | 2.71 |
| Residential Private Road | 4 | 1A | 20 | | | 54 | 0.28 | 130 | 0.69 | 4.00 | 2.10 | | | | | 0.19 | 2.29 | 200 | 0.40 | 21.64 | 0.67 | 74.90 | 82.80 | | 80.03 | 79.83 | 2.77 | 82.45 | | 79.73 | 79.53 | 2.72 |
| Residential Private Road | 1A | 1 | | | | | 0.02 | 205 | 1.30 | 4.00 | 3.33 | | | | | 0.36 | 3.69 | 200 | 0.90 | 32.46 | 1.00 | 18.50 | 82.45 | 0.50 | 79.73 | 79.53 | 2.72 | 82.45 | | 79.56 | 79.36 | 2.89 |
| Commercial Plaza | 1 | 120A | | | | | | 205 | 1.30 | 4.00 | 3.33 | | | | | 0.36 | 3.69 | 250 | 0.98 | 61.42 | 1.21 | 44.80 | 82.45 | 3.05 | 79.11 | 78.86 | 3.34 | 80.39 | | 78.67 | 78.42 | 1.72 |
| Klondike Rd/ MG Phase 13/ Commercial Plza | Upstream | 120A | | | | | | 2432 | 38.86 | 3.52 | 34.66 | 1.69 | 4.62 | 4.01 | 12.18 | 50.85 | 300 | 0.30 | 55.26 | | | | | | | | | 80.39 | | 75.61 | 75.31 | 4.78 |
| Klondike Commercial Plaza | 120A | 120 | | | | | | 2637 | 40.16 | 3.49 | 37.28 | | 4.62 | 4.01 | 12.54 | 53.83 | 300 | 0.97 | 99.36 | 1.36 | 15.80 | 80.39 | | 75.62 | 75.31 | 4.77 | 80.25 | | 75.47 | 75.17 | 4.78 | |
| Westmoreland Avenue | 120 | 117 | | | | 20 | 0.33 | 2705 | 41.15 | 3.48 | 38.14 | | 4.62 | 4.01 | 12.82 | 54.96 | 300 | 0.42 | 65.32 | 0.90 | 70.60 | 80.27 | 0.01 | 75.47 | 75.17 | 4.80 | 80.40 | | 75.17 | 74.87 | 5.23 | |
| Whithorn Avenue | 116 | 119 | | | | 8 | 0.14 | 8 | 0.14 | 4.00 | 0.13 | | | | | 0.04 | 0.17 | 200 | 2.00 | 48.39 | 1.49 | 8.10 | 83.34 | 0.10 | 79.26 | 79.06 | 4.08 | 83.30 | | 79.10 | 78.90 | 4.20 |
| Whithorn Avenue | 119 | 118 | | | | 24 | 0.22 | 32 | 0.36 | 4.00 | 0.52 | | | | | 0.10 | 0.62 | 200 | 2.69 | 56.11 | 1.73 | 37.20 | 83.30 | 0.30 | 79.00 | 78.80 | 4.30 | 82.32 | | 78.00 | 77.80 | 4.32 |
| Whithorn Avenue | 118 | 117 | | | | 44 | 0.50 | 76 | 0.86 | 4.00 | 1.23 | | | | | 0.24 | 1.47 | 200 | 2.21 | 50.87 | 1.57 | 81.10 | 82.32 | 0.75 | 77.70 | 77.50 | 4.62 | 80.40 | | 75.91 | 75.71 | 4.49 |
| Westmoreland Avenue | 117 | 110 | | | | 24 | 0.31 | 2805 | 42.32 | 3.47 | 39.40 | | 4.62 | 4.01 | 13.14 | 56.55 | 300 | 0.42 | 65.50 | 0.90 | 68.80 | 80.40 | 0.03 | 75.16 | 74.86 | 5.24 | 80.80 | | 74.87 | 74.57 | 5.93 | |
| Spalding Avenue | 111 | 110 | | | | 12 | 0.33 | 12 | 0.33 | 4.00 | 0.19 | | | | | 0.09 | 0.29 | 200 | 1.91 | 47.29 | 1.46 | 46.00 | 81.25 | 0.78 | 76.50 | 76.30 | 4.75 | 80.80 | | 75.62 | 75.42 | 5.18 |
| Westmoreland Avenue | 110 | 109 | | | | 16 | 0.30 | 2833 | 42.95 | 3.46 | 39.75 | | 4.62 | 4.01 | 13.32 | 57.08 | 300 | 0.36 | 60.32 | 0.83 | 66.30 | 80.80 | 0.02 | 74.84 | 74.54 | 5.96 | 80.80 | | 74.60 | 74.30 | 6.20 | |
| Mersey Drive | Upstream | 109 | | | | 120 | 2.01 | 120 | 2.01 | 4.00 | 1.94 | | | | | 0.56 | 2.51 | 200 | 1.00 | 34.22 | | | | | | | | 81.85 | | 77.20 | 77.00 | 4.65 |

Appendix B1 – SWM Phase 1 Design Sheets

Marc Alain Lafleur

From: Balima, Nadege <Nadege.Balima@ottawa.ca>
Sent: Friday, April 28, 2017 10:35 AM
To: Marc Alain Lafleur
Cc: Alam Ansari
Subject: RE: KMA 351 Sandhill Road - SWM design criteria

Hi Marc,

Yes, this is correct as there is currently an end of pipe stormwater management facilities and this rate appear to meet existing criteria for the area.

Regards,

Nadège Balima, P.Eng., M.P.M., LEED Green Assoc.

Project Manager, Infrastructure Approvals
Development Review Services (West)

☎ 613.580.2424 ext. 13477

From: Marc Alain Lafleur [mailto:MarcAlain.Lafleur@exp.com]
Sent: Friday, April 28, 2017 10:03 AM
To: Balima, Nadege
Cc: Alam Ansari
Subject: RE: KMA 351 Sandhill Road - SWM design criteria

Good morning Nadège,

Can you kindly confirm the SWM criteria to be use for the site at 351 Sandhill Rd.?:

- Restricted release rate to the minor system of 85L/s/ha up to the 100-year event.
- No quality control required.

Thank you,

Marc Alain Lafleur, M.Eng. | exp

EIT-Design Engineer, Infrastructure

exp Services Inc.

t: +1.613.688.1899 x3298 | e: marcalain.lafleur@exp.com

100-2650 Queensview Drive

Ottawa, ON K2B 8H6

Canada

exp.com | [legal disclaimer](#)

keep it green, read from the screen

From: Marc Alain Lafleur
Sent: Wednesday, April 26, 2017 3:23 PM
To: 'Balima, Nadege' <Nadege.Balima@ottawa.ca>
Cc: Alam Ansari <alam.ansari@exp.com>
Subject: RE: KMA 351 Sandhill Road - SWM design criteria

Hi Nadège,

Table D1

CALCULATION OF AVERAGE RUNOFF COEFFICIENTS (POST-DEVELOPMENT)

| Area No. | Area | Asphalt & Concrete Areas | | Roof Areas | | Gravel Areas | | Grassed Areas | | Runoff Type | Sum AC | Total Area (m ²) | C _{AVG} | 100-YR C _{AVG} |
|------------------------|-------------|--------------------------|--------|------------------------|-------|------------------------|-------|------------------------|-------|--------------------|--------------------|------------------------------|------------------|-------------------------|
| | | Area (m ²) | A * C | Area (m ²) | A * C | Area (m ²) | A * C | Area (m ²) | A * C | | | | | |
| | | C=0.90 | | C=0.90 | | C=0.90 | | C=0.20 | | | | | | |
| PH1A | Parking Lot | 3872.0 | 3484.8 | 245.0 | 220.5 | | | 738.0 | 147.6 | Controlled | 3852.9 | 4855 | 0.79 | 1.00 |
| PH1B | Access Rd | 533.0 | 479.7 | 127.0 | 114.3 | | | 219.0 | 43.8 | Controlled | 637.8 | 879 | 0.73 | 1.00 |
| Average Runoff Coeff = | | | | | | | | | | C _{AVG} = | C _{AVG} = | 4,531 5,795 = 0.78 | | |

Table D2

SUMMARY OF POST DEVELOPMENT RUNOFF (UNCONTROLLED AND CONTROLLED)

| Area No | Outlet Location | Area (ha) | Time of Conc. T _c (min) | Storm = 2-year | | | | Storm = 5-year | | | | Storm = 100-year | | | |
|-----------------|-----------------|-----------|------------------------------------|------------------|------------------------|-----------|--------------------------|------------------|------------------------|-----------|--------------------------|------------------|--------------------------|-----------|--------------------------|
| | | | | C _{AVG} | I ₂ (mm/hr) | Q (L/sec) | Q _{CAP} (L/sec) | C _{AVG} | I ₅ (mm/hr) | Q (L/sec) | Q _{CAP} (L/sec) | C _{AVG} | I ₁₀₀ (mm/hr) | Q (L/sec) | Q _{CAP} (L/sec) |
| PH1A | Parking Lot | 0.486 | 15 | 0.79 | 61.77 | 66.2 | 28.0 | 0.79 | 83.56 | 89.5 | 29.5 | 0.99 | 142.89 | 191.3 | 29.5 |
| PH1B | Access Rd | 0.088 | 15 | 0.73 | 61.77 | 11.0 | 11.0 | 0.73 | 83.56 | 14.8 | 17.6 | 0.91 | 142.89 | 31.7 | 17.6 |
| Total Pre-Flows | | 0.573 | | | | 77.1 | 39.0 | | | 104.3 | 47.1 | | | 223.0 | 47.1 |

Notes

- 1) Intensity, I₂ = 732.951/(Tc+6.199)^{0.810} (2-year, City of Ottawa)
- 2) Intensity, I₅ = 998.071/(Tc+6.035)^{0.814} (5-year, City of Ottawa)
- 3) Intensity, I₁₀₀ = 1735.688/(Tc+6.014)^{0.820} (100-year, City of Ottawa)
- 4) Time of Concentration: T_c=10min (5.4.5.2, City of Ottawa)
- 4) Flows under column Q_{CAP} which are **bold**, denotes flows that are controlled.

Estimate of Storage Required for 2-yr and 100-yr Storms (Modified Rational Method)

| | | |
|--------------------------------------------------------------------------------------------------------------|------|-------|
| Maximum Storage Required = | 32.3 | 139.7 |
| Notes | | |
| 1) Peak flow is equal to the product of 2.78 x C x I x A | | |
| 2) Rainfall Intensity, I = A/(T _D +C) ^B , where T _D = storm duration (mins) | | |
| 3) Release Rate = Desired Capture (Release) Rate | | |
| 4) Storage Rate = Peak Flow - Release Rate | | |
| 5) Storage = Duration x Storage Rate | | |
| 6) Maximum Storage = Max Storage Over Duration | | |
| 7) A,B,C are IDF Parameters for City of Ottawa. From Ottawa Sewer Design Guidelines, Section 5.4.2. | | |

Estimate of Storage Required for 2-yr and 100-yr Storms (Modified Rational Method)

| | | | | | | | | | | |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------|----------------------------|----------------------------|----------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------|----------------------------|----------------------------|----------------------|
| Area No: <u>PH1B</u> Access Road $C_{AVG} = \frac{0.84}{(2\text{-yr, } 100\text{-yr})}$ $C_{AVG} = \frac{1.00}{(100\text{-yr} + 25\%)}$ Time Interval = <u>15</u> (mins) Drainage Area = <u>0.0727</u> (hectares) | | | | | | | | | | |
| Duration, T_D (min) | Release Rate = <u>10.4</u> (L/sec) Return Period = <u>2</u> (years) IDF Parameters, $A = 732.951$, $B = \frac{0.810}{6.199}$ ($I = A/(T_D + C)^B$), $C =$ | | | | | Release Rate = <u>17.6</u> (L/sec) Return Period = <u>100</u> (years) IDF Parameters, $A = 1735.688$, $C = \frac{0.820}{6.014}$ ($I = A/(T_D + C)^B$), $C =$ | | | | |
| | Rainfall Intensity, I (mm/hr) | Peak Flow (L/sec) | Release Rate (L/sec) | Storage Rate (L/sec) | Storage (m^3) | Rainfall Intensity, I (mm/hr) | Peak Flow (L/sec) | Release Rate (L/sec) | Storage Rate (L/sec) | Storage (m^3) |
| | 0 | 167.2 | 28.2 | 10.43 | 17.8 | 0 | 398.6 | 80.6 | 17.612 | 63.0 |
| 15 | 61.8 | 10.4 | 10.43 | 0.0 | 0 | 142.9 | 28.9 | 17.612 | 11.3 | 10.1 |
| 30 | 40.0 | 6.8 | 10.43 | -3.7 | -7 | 91.9 | 18.6 | 17.612 | 1.0 | 1.7 |
| 45 | 30.2 | 5.1 | 10.43 | -5.3 | -14 | 69.1 | 14.0 | 17.612 | -3.7 | -9.9 |
| 60 | 24.6 | 4.1 | 10.43 | -6.3 | -23 | 55.9 | 11.3 | 17.612 | -6.3 | -22.7 |
| 75 | 20.8 | 3.5 | 10.43 | -6.9 | -31 | 47.3 | 9.6 | 17.612 | -8.1 | -36.3 |
| 90 | 18.1 | 3.1 | 10.43 | -7.4 | -40 | 41.1 | 8.3 | 17.612 | -9.3 | -50.2 |
| 105 | 16.1 | 2.7 | 10.43 | -7.7 | -49 | 36.5 | 7.4 | 17.612 | -10.2 | -64.5 |
| 120 | 14.6 | 2.5 | 10.43 | -8.0 | -57 | 32.9 | 6.6 | 17.612 | -11.0 | -78.9 |
| 135 | 13.3 | 2.2 | 10.43 | -8.2 | -66 | 30.0 | 6.1 | 17.612 | -11.5 | -93.5 |
| 150 | 12.3 | 2.1 | 10.43 | -8.4 | -75 | 27.6 | 5.6 | 17.612 | -12.0 | -108.3 |
| 165 | 11.4 | 1.9 | 10.43 | -8.5 | -84 | 25.6 | 5.2 | 17.612 | -12.4 | -123.1 |
| 180 | 10.6 | 1.8 | 10.43 | -8.6 | -93 | 23.9 | 4.8 | 17.612 | -12.8 | -138.0 |
| 195 | 10.0 | 1.7 | 10.43 | -8.7 | -102 | 22.4 | 4.5 | 17.612 | -13.1 | -153.0 |
| 210 | 9.4 | 1.6 | 10.43 | -8.8 | -111 | 21.1 | 4.3 | 17.612 | -13.3 | -168.1 |
| 225 | 8.9 | 1.5 | 10.43 | -8.9 | -120 | 20.0 | 4.0 | 17.612 | -13.6 | -183.2 |
| 240 | 8.5 | 1.4 | 10.43 | -9.0 | -130 | 19.0 | 3.8 | 17.612 | -13.8 | -198.3 |
| 255 | 8.1 | 1.4 | 10.43 | -9.1 | -139 | 18.1 | 3.7 | 17.612 | -14.0 | -213.5 |
| 270 | 7.7 | 1.3 | 10.43 | -9.1 | -148 | 17.3 | 3.5 | 17.612 | -14.1 | -228.7 |
| 285 | 7.4 | 1.2 | 10.43 | -9.2 | -157 | 16.6 | 3.3 | 17.612 | -14.3 | -243.9 |
| 300 | 7.1 | 1.2 | 10.43 | -9.2 | -166 | 15.9 | 3.2 | 17.612 | -14.4 | -259.2 |
| 315 | 6.8 | 1.2 | 10.43 | -9.3 | -175 | 15.3 | 3.1 | 17.612 | -14.5 | -274.5 |
| Maximum Storage Required = | | | | | 0.0 | 10.1 | | | | |
| Notes | | | | | | | | | | |
| 1) Peak flow is equal to the product of $2.78 \times C \times I \times A$ | | | | | | | | | | |
| 2) Rainfall Intensity, $I = A/(T_D + C)^B$, where T_D = storm duration (mins) | | | | | | | | | | |
| 3) Release Rate = Desired Capture (Release) Rate | | | | | | | | | | |
| 4) Storage Rate = Peak Flow - Release Rate | | | | | | | | | | |
| 5) Storage = Duration x Storage Rate | | | | | | | | | | |
| 6) Maximum Storage = Max Storage Over Duration | | | | | | | | | | |
| 7) A,B,C are IDF Parameters for City of Ottawa. From Ottawa Sewer Design Guidelines, Section 5.4.2. | | | | | | | | | | |

Table D5
Estimate of Provided Storage for 2-yr and 100-yr Storms

Total 2 Year Storage = 35.1 m³
Total 100 Year Storage= 218.8 m³

2 Year Catch Basin Storage

| CB ID | Area (m2) | Depth (m) | Volume (m3) |
|---------------------|-----------|-----------|-------------|
| CB 102 | 0.36 | 2.1 | 0.77 |
| CB 103 | 0.36 | 2.1 | 0.77 |
| CB 104 | 0.36 | 2.1 | 0.77 |
| CB 105 | 0.36 | 2.1 | 0.77 |
| CB 106 | 0.36 | 2.1 | 0.77 |
| CB 107 | 0.36 | 2.1 | 0.77 |
| CB 108 | 0.36 | 2.1 | 0.77 |
| Total Volume | | | 5.4 |

2 Year Catch Basin Manhole Storage

| MH ID | Diameter (mm) | Area (m2) | Depth (m) | Volume (m3) |
|---------------------|---------------|-----------|-----------|-------------|
| CBMH 203 | 1200 | 1.13 | 3.00 | 3.39 |
| CBMH 204 | 1200 | 1.13 | 3.20 | 3.62 |
| CBMH 205 | 1200 | 1.13 | 3.00 | 3.39 |
| Total Volume | | | | 7.0 |

2 Year Underground Pipe Storage

| Diameter (mm) | Area (m2) | Length (m) | Volume (m3) |
|---------------------|-----------|------------|-------------|
| 200 | 0.031 | 119.6 | 3.8 |
| 600 | 0.283 | 67.0 | 18.9 |
| Total Volume | | | 22.7 |

100 Year Surface Ponding Volumes PH1A

| Ponding Location | Surface Area (m2) | Ponding Depth (m) | Volume (m3) |
|---------------------|-------------------|-------------------|--------------|
| CB102 | 132 | 0.30 | 13.2 |
| CB103 | 368.00 | 0.30 | 36.8 |
| CB104 | 342.00 | 0.30 | 34.2 |
| CB105 | 86.0 | 0.30 | 8.6 |
| CB106 | 82.0 | 0.30 | 8.2 |
| CB107 | 309.0 | 0.30 | 30.9 |
| CB108 | 401.0 | 0.30 | 40.1 |
| CBMH203 | 184 | 0.35 | 21.5 |
| Total Volume | | | 193.5 |

100 Year Surface Ponding Volumes PH1B

| Ponding Location | Surface Area (m2) | Ponding Depth (m) | Volume (m3) |
|---------------------|-------------------|-------------------|-------------|
| CB101 | 217 | 0.35 | 25.3 |
| Total Volume | | | 25.3 |

Figure 3 : HYDROVEX® VHV/SVHV Selection Chart

CBMH203

100-Year Allowable flow= 29.5 L/sec

Head= 3.9m

Hydrovex Model 125 VHV-2

CBMH203

2-Year Allowable flow= 28.0 L/sec

Head= 3.6m

Hydrovex Model 125 VHV-2





Figure 3 : HYDROVEX® VHV/SVHV Selection Chart

CB101
 100-Year Allowable Flow= 17.6 L/sec
 Head= 3.6m
 Hydrovex Model 100 VHV-1

CB101
 2-Year Allowable Flow= 11.0 L/sec
 Head= 3.3m
 Hydrovex Model 100 VHV-1



Appendix B2 – SWM Phase 2 Design Sheets

Table D8
CALCULATION OF AVERAGE RUNOFF COEFFICIENTS (POST-DEVELOPMENT)

| Area No. | Area | Asphalt & Concrete Areas | | Roof Areas | | Gravel Areas | | Grassed Areas | | Sum AC | Total Area (m ²) | C _{AVG} | 100-YR C _{AVG} |
|------------------------|-------------|--------------------------|--------|------------------------|--------|------------------------|-------|------------------------|-------|--------------------|------------------------------|------------------|-------------------------|
| | | Area (m ²) | A * C | Area (m ²) | A * C | Area (m ²) | A * C | Area (m ²) | A * C | | | | |
| | | C=0.90 | | C=0.90 | | C=0.90 | | C=0.20 | | | | | |
| PH2A | Parking Lot | 3910.0 | 3519.0 | 245.0 | 220.5 | | | 826.4 | 165.3 | 3904.8 | 4981 | 0.78 | 0.98 |
| PH2B | Access Rd | 837.0 | 753.3 | 127.0 | 114.3 | | | 219.0 | 43.8 | 911.4 | 1183 | 0.77 | 0.96 |
| PH2C | New Bld | | | 1450.0 | 1305.0 | | | | | 1305.0 | 1450 | 0.90 | 1.00 |
| PH2D | Free Flow | 165.7 | 149.1 | | | | | 284.3 | 56.9 | 206.0 | 450 | 0.46 | 0.57 |
| Average Runoff Coeff = | | | | | | | | | | C _{AVG} = | $\frac{6,368}{8,125}$ | = 0.78 | |

Table D9
SUMMARY OF POST DEVELOPMENT RUNOFF (UNCONTROLLED AND CONTROLLED)

| Area No | Outlet Location | Area (ha) | Time of Conc. T _c (min) | Storm = 2-year | | | | Storm = 100-year | | | |
|---------|-----------------|-----------|------------------------------------|------------------|------------------------|-----------|--------------------------|------------------|--------------------------|-----------|--------------------------|
| | | | | C _{AVG} | I ₂ (mm/hr) | Q (L/sec) | Q _{CAP} (L/sec) | C _{AVG} | I ₁₀₀ (mm/hr) | Q (L/sec) | Q _{CAP} (L/sec) |
| PH2A | Parking Lot | 0.498 | 15 | 0.78 | 61.77 | 67.1 | 28.0 | 0.98 | 142.89 | 193.9 | 29.5 |
| PH2B | Access Rd | 0.118 | 15 | 0.77 | 61.77 | 15.6 | 15.6 | 0.96 | 142.89 | 45.3 | 17.6 |
| PH2C | New Bld | 0.145 | 15 | 0.90 | 61.77 | 22.4 | 7.0 | 1.00 | 142.89 | 57.6 | 10.0 |
| PH2D | Free Flow | 0.045 | 15 | 0.46 | 61.77 | 3.5 | 3.5 | 0.57 | 142.89 | 10.2 | 10.2 |
| Total | | 0.616 | | | | 82.7 | 54.2 | | | 239.2 | 67.4 |

Notes

- 1) Intensity, I₂ = 732.951/(Tc+6.199)^{0.810} (2-year, City of Ottawa)
- 2) Intensity, I₅ = 998.071/(Tc+6.035)^{0.814} (5-year, City of Ottawa)
- 3) Intensity, I₁₀₀ = 1735.688/(Tc+6.014)^{0.820} (100-year, City of Ottawa)
- 4) Time of Concentration: T_c=10min (5.4.5.2, City of Ottawa)
- 4) Flows under column Q_{CAP} which are **bold**, denotes flows that are controlled.

Estimate of Storage Required for 2-yr and 100-yr Storms (Modified Rational Method)

Area No: PH2A Parking Lot

$C_{AVG} =$ 0.78 (2-yr, 5-yr)

$C_{AVG} =$ 0.98 (100-yr +25%)

Time Interval = 15 (mins)

Drainage Area = 0.4981 (hectares)

| Duration, T_D (min) | Release Rate = <u>28.0</u> (L/sec) Return Period = <u>2</u> (years) IDF Parameters, $A = 732.951$, $B = 0.810$ $(I = A/(T_D+C)^B)$, $C = 6.199$ | | | | | Release Rate = <u>29.5</u> (L/sec) Return Period = <u>100</u> (years) IDF Parameters, $A = 1735.688$, $C = 6.014$ $(I = A/(T_D+C)^B)$ | | | | |
|-----------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------|----------------------------|----------------------------|----------------------|-------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------|----------------------------|----------------------------|----------------------|
| | Rainfall Intensity, I (mm/hr) | Peak Flow (L/sec) | Release Rate (L/sec) | Storage Rate (L/sec) | Storage (m^3) | Rainfall Intensity, I (mm/hr) | Peak Flow (L/sec) | Release Rate (L/sec) | Storage Rate (L/sec) | Storage (m^3) |
| 0 | 167.2 | 181.5 | 28.04 | 153.5 | 0 | 398.6 | 540.9 | 29.527 | 511.4 | 0.0 |
| 15 | 61.8 | 67.1 | 28.04 | 39.0 | 35 | 142.9 | 193.9 | 29.527 | 164.4 | 147.9 |
| 30 | 40.0 | 43.5 | 28.04 | 15.4 | 28 | 91.9 | 124.7 | 29.527 | 95.1 | 171.2 |
| 45 | 30.2 | 32.8 | 28.04 | 4.8 | 13 | 69.1 | 93.7 | 29.527 | 64.2 | 173.3 |
| 60 | 24.6 | 26.7 | 28.04 | -1.4 | -5 | 55.9 | 75.8 | 29.527 | 46.3 | 166.7 |
| 75 | 20.8 | 22.6 | 28.04 | -5.4 | -24 | 47.3 | 64.1 | 29.527 | 34.6 | 155.7 |
| 90 | 18.1 | 19.7 | 28.04 | -8.3 | -45 | 41.1 | 55.8 | 29.527 | 26.3 | 141.8 |
| 105 | 16.1 | 17.5 | 28.04 | -10.5 | -66 | 36.5 | 49.5 | 29.527 | 20.0 | 126.0 |
| 120 | 14.6 | 15.8 | 28.04 | -12.2 | -88 | 32.9 | 44.6 | 29.527 | 15.1 | 108.8 |
| 135 | 13.3 | 14.4 | 28.04 | -13.6 | -110 | 30.0 | 40.7 | 29.527 | 11.2 | 90.5 |
| 150 | 12.3 | 13.3 | 28.04 | -14.7 | -133 | 27.6 | 37.5 | 29.527 | 7.9 | 71.4 |
| 165 | 11.4 | 12.3 | 28.04 | -15.7 | -155 | 25.6 | 34.7 | 29.527 | 5.2 | 51.7 |
| 180 | 10.6 | 11.5 | 28.04 | -16.5 | -178 | 23.9 | 32.4 | 29.527 | 2.9 | 31.4 |
| 195 | 10.0 | 10.8 | 28.04 | -17.2 | -201 | 22.4 | 30.4 | 29.527 | 0.9 | 10.6 |
| 210 | 9.4 | 10.2 | 28.04 | -17.8 | -224 | 21.1 | 28.7 | 29.527 | -0.8 | -10.5 |
| 225 | 8.9 | 9.7 | 28.04 | -18.4 | -248 | 20.0 | 27.2 | 29.527 | -2.4 | -32.0 |
| 240 | 8.5 | 9.2 | 28.04 | -18.8 | -271 | 19.0 | 25.8 | 29.527 | -3.7 | -53.8 |
| 255 | 8.1 | 8.8 | 28.04 | -19.3 | -295 | 18.1 | 24.6 | 29.527 | -5.0 | -75.9 |
| 270 | 7.7 | 8.4 | 28.04 | -19.7 | -318 | 17.3 | 23.5 | 29.527 | -6.1 | -98.2 |
| 285 | 7.4 | 8.0 | 28.04 | -20.0 | -342 | 16.6 | 22.5 | 29.527 | -7.1 | -120.7 |
| 300 | 7.1 | 7.7 | 28.04 | -20.3 | -366 | 15.9 | 21.6 | 29.527 | -8.0 | -143.4 |
| 315 | 6.8 | 7.4 | 28.04 | -20.6 | -390 | 15.3 | 20.7 | 29.527 | -8.8 | -166.2 |
| Maximum Storage Required = | | | | | 35.1 | 173.3 | | | | |

Notes

1) Peak flow is equal to the product of $2.78 \times C \times I \times A$

2) Rainfall Intensity, $I = A/(T_D+C)^B$, where T_D = storm duration (mins)

3) Release Rate = Desired Capture (Release) Rate

4) Storage Rate = Peak Flow - Release Rate

5) Storage = Duration x Storage Rate

6) Maximum Storage = Max Storage Over Duration

7) A,B,C are IDF Parameters for City of Ottawa. From Ottawa Sewer Design Guidelines, Section 5.4.2.

Estimate of Storage Required for 2-yr and 100-yr Storms (Modified Rational Method)

| | | | | | | | | | | |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------|----------------------------|----------------------------|----------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------|----------------------------|----------------------------|----------------------|
| Area No: <u>PH2B</u> Access Road $C_{AVG} = \frac{0.77}{(2\text{-yr, 5-yr})}$ $C_{AVG} = \frac{0.96}{(100\text{-yr} + 25\%)}$ Time Interval = <u>15</u> (mins) Drainage Area = <u>0.1183</u> (hectares) | | | | | | | | | | |
| Duration, T_D (min) | Release Rate = <u>15.6</u> (L/sec) Return Period = <u>2</u> (years) IDF Parameters, $A = 732.951$, $B = \frac{0.810}{(I = A/(T_D+C)^B)}$, $C = \frac{0.810}{6.199}$ | | | | | Release Rate = <u>17.6</u> (L/sec) Return Period = <u>100</u> (years) IDF Parameters, $A = 1735.688$, $C = \frac{0.820}{(I = A/(T_D+C)^B)}$, $C = \frac{0.820}{6.014}$ | | | | |
| | Rainfall Intensity, I (mm/hr) | Peak Flow (L/sec) | Release Rate (L/sec) | Storage Rate (L/sec) | Storage (m^3) | Rainfall Intensity, I (mm/hr) | Peak Flow (L/sec) | Release Rate (L/sec) | Storage Rate (L/sec) | Storage (m^3) |
| | 0 | 167.2 | 42.4 | 15.65 | 26.7 | 0 | 398.6 | 126.2 | 17.612 | 108.6 |
| 15 | 61.8 | 15.6 | 15.65 | 0.0 | 0 | 142.9 | 45.3 | 17.612 | 27.6 | 24.9 |
| 30 | 40.0 | 10.1 | 15.65 | -5.5 | -10 | 91.9 | 29.1 | 17.612 | 11.5 | 20.7 |
| 45 | 30.2 | 7.7 | 15.65 | -8.0 | -22 | 69.1 | 21.9 | 17.612 | 4.3 | 11.5 |
| 60 | 24.6 | 6.2 | 15.65 | -9.4 | -34 | 55.9 | 17.7 | 17.612 | 0.1 | 0.3 |
| 75 | 20.8 | 5.3 | 15.65 | -10.4 | -47 | 47.3 | 15.0 | 17.612 | -2.6 | -11.9 |
| 90 | 18.1 | 4.6 | 15.65 | -11.1 | -60 | 41.1 | 13.0 | 17.612 | -4.6 | -24.8 |
| 105 | 16.1 | 4.1 | 15.65 | -11.6 | -73 | 36.5 | 11.6 | 17.612 | -6.1 | -38.1 |
| 120 | 14.6 | 3.7 | 15.65 | -12.0 | -86 | 32.9 | 10.4 | 17.612 | -7.2 | -51.8 |
| 135 | 13.3 | 3.4 | 15.65 | -12.3 | -99 | 30.0 | 9.5 | 17.612 | -8.1 | -65.7 |
| 150 | 12.3 | 3.1 | 15.65 | -12.5 | -113 | 27.6 | 8.7 | 17.612 | -8.9 | -79.8 |
| 165 | 11.4 | 2.9 | 15.65 | -12.8 | -126 | 25.6 | 8.1 | 17.612 | -9.5 | -94.1 |
| 180 | 10.6 | 2.7 | 15.65 | -13.0 | -140 | 23.9 | 7.6 | 17.612 | -10.0 | -108.4 |
| 195 | 10.0 | 2.5 | 15.65 | -13.1 | -154 | 22.4 | 7.1 | 17.612 | -10.5 | -122.9 |
| 210 | 9.4 | 2.4 | 15.65 | -13.3 | -167 | 21.1 | 6.7 | 17.612 | -10.9 | -137.5 |
| 225 | 8.9 | 2.3 | 15.65 | -13.4 | -181 | 20.0 | 6.3 | 17.612 | -11.3 | -152.2 |
| 240 | 8.5 | 2.1 | 15.65 | -13.5 | -194 | 19.0 | 6.0 | 17.612 | -11.6 | -166.9 |
| 255 | 8.1 | 2.0 | 15.65 | -13.6 | -208 | 18.1 | 5.7 | 17.612 | -11.9 | -181.7 |
| 270 | 7.7 | 2.0 | 15.65 | -13.7 | -222 | 17.3 | 5.5 | 17.612 | -12.1 | -196.6 |
| 285 | 7.4 | 1.9 | 15.65 | -13.8 | -236 | 16.6 | 5.2 | 17.612 | -12.4 | -211.5 |
| 300 | 7.1 | 1.8 | 15.65 | -13.9 | -249 | 15.9 | 5.0 | 17.612 | -12.6 | -226.4 |
| 315 | 6.8 | 1.7 | 15.65 | -13.9 | -263 | 15.3 | 4.8 | 17.612 | -12.8 | -241.4 |
| Maximum Storage Required = | | | | | 0.0 | 24.9 | | | | |
| Notes | | | | | | | | | | |
| 1) Peak flow is equal to the product of $2.78 \times C \times I \times A$ | | | | | | | | | | |
| 2) Rainfall Intensity, $I = A/(T_D+C)^B$, where T_D = storm duration (mins) | | | | | | | | | | |
| 3) Release Rate = Desired Capture (Release) Rate | | | | | | | | | | |
| 4) Storage Rate = Peak Flow - Release Rate | | | | | | | | | | |
| 5) Storage = Duration x Storage Rate | | | | | | | | | | |
| 6) Maximum Storage = Max Storage Over Duration | | | | | | | | | | |
| 7) A,B,C are IDF Parameters for City of Ottawa. From Ottawa Sewer Design Guidelines, Section 5.4.2. | | | | | | | | | | |

Estimate of Storage Required for 2-yr and 100-yr Storms (Modified Rational Method)

| | | | | | | | | | | | |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------|----------------------------|----------------------------|----------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------|----------------------------|----------------------------|----------------------|-------------|
| Area No: <u>PH2C</u> Roof $C_{AVG} = \frac{0.90}{(2\text{-yr, 5-yr})}$ $C_{AVG} = \frac{1.00}{(100\text{-yr} + 25\%)}$ Time Interval = <u>15</u> (mins) Drainage Area = <u>0.1450</u> (hectares) | | | | | | | | | | | |
| Duration, T_D (min) | Release Rate = <u>7.0</u> (L/sec) Return Period = <u>2</u> (years) IDF Parameters, $A = 732.951$, $B = \frac{0.810}{(I = A/(T_D+C)^B)}$, $C = \frac{6.199}{6.199}$ | | | | | Release Rate = <u>10.0</u> (L/sec) Return Period = <u>100</u> (years) IDF Parameters, $A = 1735.688$, $B = \frac{0.820}{(I = A/(T_D+C)^B)}$, $C = \frac{6.014}{6.014}$ | | | | | |
| | Rainfall Intensity, I (mm/hr) | Peak Flow (L/sec) | Release Rate (L/sec) | Storage Rate (L/sec) | Storage (m^3) | Rainfall Intensity, I (mm/hr) | Peak Flow (L/sec) | Release Rate (L/sec) | Storage Rate (L/sec) | Storage (m^3) | |
| | 0 | 167.2 | 60.7 | 7.00 | 53.7 | 0 | 398.6 | 160.7 | 10.000 | 150.7 | 0.0 |
| 15 | 61.8 | 22.4 | 7.00 | 15.4 | 14 | 142.9 | 57.6 | 10.000 | 47.6 | 42.8 | |
| 30 | 40.0 | 14.5 | 7.00 | 7.5 | 14 | 91.9 | 37.0 | 10.000 | 27.0 | 48.7 | |
| 45 | 30.2 | 11.0 | 7.00 | 4.0 | 11 | 69.1 | 27.8 | 10.000 | 17.8 | 48.2 | |
| 60 | 24.6 | 8.9 | 7.00 | 1.9 | 7 | 55.9 | 22.5 | 10.000 | 12.5 | 45.1 | |
| 75 | 20.8 | 7.6 | 7.00 | 0.6 | 2 | 47.3 | 19.0 | 10.000 | 9.0 | 40.7 | |
| 90 | 18.1 | 6.6 | 7.00 | -0.4 | -2 | 41.1 | 16.6 | 10.000 | 6.6 | 35.5 | |
| 105 | 16.1 | 5.9 | 7.00 | -1.1 | -7 | 36.5 | 14.7 | 10.000 | 4.7 | 29.7 | |
| 120 | 14.6 | 5.3 | 7.00 | -1.7 | -12 | 32.9 | 13.3 | 10.000 | 3.3 | 23.5 | |
| 135 | 13.3 | 4.8 | 7.00 | -2.2 | -18 | 30.0 | 12.1 | 10.000 | 2.1 | 16.9 | |
| 150 | 12.3 | 4.4 | 7.00 | -2.6 | -23 | 27.6 | 11.1 | 10.000 | 1.1 | 10.2 | |
| 165 | 11.4 | 4.1 | 7.00 | -2.9 | -28 | 25.6 | 10.3 | 10.000 | 0.3 | 3.2 | |
| 180 | 10.6 | 3.9 | 7.00 | -3.1 | -34 | 23.9 | 9.6 | 10.000 | -0.4 | -3.9 | |
| 195 | 10.0 | 3.6 | 7.00 | -3.4 | -40 | 22.4 | 9.0 | 10.000 | -1.0 | -11.2 | |
| 210 | 9.4 | 3.4 | 7.00 | -3.6 | -45 | 21.1 | 8.5 | 10.000 | -1.5 | -18.6 | |
| 225 | 8.9 | 3.2 | 7.00 | -3.8 | -51 | 20.0 | 8.1 | 10.000 | -1.9 | -26.1 | |
| 240 | 8.5 | 3.1 | 7.00 | -3.9 | -57 | 19.0 | 7.7 | 10.000 | -2.3 | -33.7 | |
| 255 | 8.1 | 2.9 | 7.00 | -4.1 | -62 | 18.1 | 7.3 | 10.000 | -2.7 | -41.3 | |
| 270 | 7.7 | 2.8 | 7.00 | -4.2 | -68 | 17.3 | 7.0 | 10.000 | -3.0 | -49.1 | |
| 285 | 7.4 | 2.7 | 7.00 | -4.3 | -74 | 16.6 | 6.7 | 10.000 | -3.3 | -56.9 | |
| 300 | 7.1 | 2.6 | 7.00 | -4.4 | -80 | 15.9 | 6.4 | 10.000 | -3.6 | -64.7 | |
| 315 | 6.8 | 2.5 | 7.00 | -4.5 | -85 | 15.3 | 6.2 | 10.000 | -3.8 | -72.6 | |
| Maximum Storage Required = | | | | | 13.9 | | | | | | 48.7 |
| Notes | | | | | | | | | | | |
| 1) Peak flow is equal to the product of $2.78 \times C \times I \times A$ | | | | | | | | | | | |
| 2) Rainfall Intensity, $I = A/(T_D+C)^B$, where T_D = storm duration (mins) | | | | | | | | | | | |
| 3) Release Rate = Desired Capture (Release) Rate | | | | | | | | | | | |
| 4) Storage Rate = Peak Flow - Release Rate | | | | | | | | | | | |
| 5) Storage = Duration x Storage Rate | | | | | | | | | | | |
| 6) Maximum Storage = Max Storage Over Duration | | | | | | | | | | | |
| 7) A,B,C are IDF Parameters for City of Ottawa. From Ottawa Sewer Design Guidelines, Section 5.4.2. | | | | | | | | | | | |

Table D13
Estimate of Provided Storage for 2-yr and 100-yr Storms

Total 2 Year Storage = 35.1 m³
Total 100 Year Storage 275.8 m³

2 Year Catch Basin Storage

| CB ID | Area ID | Area (m2) | Depth (m) | Volume (m3) |
|---------------------|---------|-----------|-----------|-------------|
| CB 102 | PH2A | 0.36 | 2.1 | 0.77 |
| CB 103 | PH2A | 0.36 | 2.1 | 0.77 |
| CB 104 | PH2A | 0.36 | 2.1 | 0.77 |
| CB 105 | PH2A | 0.36 | 2.1 | 0.77 |
| CB 106 | PH2A | 0.36 | 2.1 | 0.77 |
| CB 107 | PH2A | 0.36 | 2.1 | 0.77 |
| CB 108 | PH2A | 0.36 | 2.1 | 0.77 |
| Total Volume | | | | 5.4 |

2 Year Catch Basin Manhole Storage

| MH ID | Area ID | Diameter (mm) | Area (m2) | Depth (m) | Volume (m3) |
|---------------------|---------|---------------|-----------|-----------|-------------|
| CBMH 203 | PH2A | 1200 | 1.13 | 3.0 | 3.39 |
| CBMH 204 | PH2A | 1200 | 1.13 | 3.2 | 3.62 |
| CBMH 205 | PH2A | 1200 | 1.13 | 3.0 | 3.39 |
| Total Volume | | | | | 7.0 |

2 Year Underground Pipe Storage

| Diameter (mm) | Area ID | Area (m2) | Length (m) | Volume (m3) |
|---------------------|---------|-----------|------------|-------------|
| 200 | PH2A | 0.031 | 119.6 | 3.8 |
| 600 | PH2B | 0.283 | 67.0 | 18.9 |
| Total Volume | | | | 22.7 |

100 Year Surface Ponding Volumes PH1A

| Ponding Location | Surface Area (m2) | Ponding Depth | Volume (m3) |
|---------------------|-------------------|---------------|--------------|
| CB102 | 132 | 0.30 | 13.2 |
| CB103 | 368.00 | 0.30 | 36.8 |
| CB104 | 342.00 | 0.30 | 34.2 |
| CB105 | 86.0 | 0.30 | 8.6 |
| CB106 | 82.0 | 0.30 | 8.2 |
| CB107 | 309.0 | 0.30 | 30.9 |
| CB108 | 401.0 | 0.30 | 40.1 |
| CBMH203 | 184 | 0.35 | 21.5 |
| Total Volume | | | 193.5 |

100 Year Surface Ponding Volumes PH1C

| Ponding Location | Surface Area (m2) | Ponding Depth | Volume (m3) |
|---------------------|-------------------|---------------|-------------|
| Roof | 1140 | 0.15 | 57 |
| Total Volume | | | 57.0 |

100 Year Surface Ponding Volumes PH1B

| Ponding Location | Surface Area (m2) | Ponding Depth | Volume (m3) |
|---------------------|-------------------|---------------|-------------|
| CB101 | 217 | 0.35 | 25.3 |
| Total Volume | | | 25.3 |

Appendix C – Water

BOUNDARY CONDITIONS



Boundary Conditions For: 351 Sandhill Rd

Date of Boundary Conditions: 2018-Jul-09

Provided Information:

| Scenario | Demand | |
|----------------------|--------|------|
| | L/min | L/s |
| Average Daily Demand | 16.2 | 0.3 |
| Maximum Daily Demand | 24.6 | 0.4 |
| Peak Hour | 44.4 | 0.7 |
| Fire Flow #1 Demand | 4,000 | 66.7 |

Number Of Connections: 1

Location:



BOUNDARY CONDITIONS



Results:

Connection #: 1

| Demand Scenario | Head (m) | Pressure ¹ (psi) |
|------------------------------------|----------|-----------------------------|
| Maximum HGL | 131.5 | 80.7 |
| Peak Hour | 124.2 | 70.3 |
| Max Day Plus Fire (4,000) L/min | 125.1 | 71.6 |

¹Elevation: **74.73 m**

Notes:

1) As per the Ontario Building Code in areas that may be occupied, the static pressure at any fixture shall not exceed 552 kPa (80 psi.) Pressure control measures to be considered are as follows, in order of preference:

- a) If possible, systems to be designed to residual pressures of 345 to 552 kPa (50 to 80 psi) in all occupied areas outside of the public right-of-way without special pressure control equipment.
- b) Pressure reducing valves to be installed immediately downstream of the isolation valve in the home/ building, located downstream of the meter so it is owner maintained.

2) Connection Location is always selected to be at watermain major intersections to provide best and most accurate results.

Disclaimer

The boundary condition information is based on current operation of the city water distribution system. The computer model simulation is based on the best information available at the time. The operation of the water distribution system can change on a regular basis, resulting in a variation in boundary conditions. The physical properties of watermains deteriorate over time, as such must be assumed in the absence of actual field test data. The variation in physical watermain properties can therefore alter the results of the computer model simulation. Fire Flow analysis is a reflection of available flow in the watermain; there may be additional restrictions that occur between the watermain and the hydrant that the model cannot take into account.

From: Ahmed Aref <aaref@aplus-arch.com>
Sent: Monday, November 12, 2018 1:46 PM
To: Aly Elgayar
Cc: Alam Ansari; Marc Alain Lafleur
Subject: Re: KMA Mosque – Type of Construction Confirmation
Attachments: image001.png

Steel frame on concrete shallow foundations. Exterior cladding of combustible and non combustible construction.

Ahmed Aref, Architect, OAA, MRAIC, LEED Green Assoc.
Principal

A+ Architecture Inc.

555 Legget Drive, Tower A, Suite 304, Kanata, ON K2K 2X3

T. (613) 699-6860 | F. (613) 800-2204 | C. (613) 854-5008

aaref@aplus-arch.com | www.aplus-arch.com

On Mon, Nov 12, 2018, 10:58 AM Aly Elgayar <Aly.ElGayar@exp.com> wrote:

Good Morning Ahmed,

Can you please confirm the proposed building's type of construction?

I require documentation for the SWM report as per the City comments.

Regards,

TABLE 1: FIRE FLOW REQUIREMENTS BASED ON FIRE UNDERWRITERS SURVEY(FUS) 1999

Project No.: OTT-00238504-A0

Project Name: KMA Mosque & Community Center



An estimate of the Fire Flow required for a given fire area may be estimated by:

$$F = 220 * C * \text{SQRT}(A)$$

where:

F = required fire flow in litres per minute

A = total floor area in m² (including all storeys, but excluding basements at least 50% below grade)

C = coefficient related to the type of construction

| Task | Options | Multiplier | Input | Value Used | Fire Flow Total (L/min) |
|--------------------------------|---------------------------------------------------|------------|------------------------------|-----------------------|-------------------------|
| Choose Building Frame (C) | Wood Frame | 1.5 | Non-combustible Construction | 0.8 | |
| | Ordinary Construction | 1 | | | |
| | Non-combustible Construction | 0.8 | | | |
| | Fire Resistive Construction | 0.6 | | | |
| Input Building Floor Areas (A) | Floor 3 | | 586.4 1696 0 | 2282.4 m ² | |
| | Floor 2 | | | | |
| | Floor 1 | | | | |
| | Basement (At least 50% below grade, not included) | | | | |
| Fire Flow (F) | F = 220 * C * SQRT(A) | | | | 8,408 |
| Fire Flow (F) | Rounded to nearest 1,000 | | | | 8,000 |

Reductions/Increases Due to Factors Effecting Burning

| Task | Options | Multiplier | | | Input | | | | | | Value Used | Fire Flow Change (L/min) | Fire Flow Total (L/min) | |
|--------------------------------------------|------------------------------------------------------------------------------|---------------------|--------|---------------------|------------------------------------------------------------------------------|---------------------|---------------|---------------------|---------------|------------|------------------|-------------------------------|-------------------------|-----------------------------------|
| Choose Combustibility of Building Contents | Non-combustible | -25% | | | Limited Combustible | | | | | | -15% | -1,200 | 6,800 | |
| | Limited Combustible | -15% | | | | | | | | | | | | |
| | Combustible | 0% | | | | | | | | | | | | |
| | Free Burning | 15% | | | | | | | | | | | | |
| | Rapid Burning | 25% | | | | | | | | | | | | |
| Choose Reduction Due to Sprinkler System | Adequate Sprinkler Conforms to NFPA13 | -30% | | | Adequate Sprinkler Conforms to NFPA13 | | | | | | -23% | -1,591 | 5,209 | |
| | No Sprinkler | 0% | | | Standard Water Supply for Fire Department Hose Line and for Sprinkler System | | | | | | -8% | -530 | 4,678 | |
| | Standard Water Supply for Fire Department Hose Line and for Sprinkler System | -10% | | | | | | | | | | | | |
| | Not Standard Water Supply or Unavailable | 0% | | | | | | | | | | | | |
| | Fully Supervised Sprinkler System | -10% | | | | | | | | | | | | Fully Supervised Sprinkler System |
| | Not Fully Supervised or N/A | 0% | | | | | | | | | | | | |
| Choose Structure Exposure Distance | Exposures | Separation Dist (m) | Cond | Separation Conditon | Exposing Wall type | Exposed Wall Length | | | | | | | | |
| | | | | | | Length (m) | No of Storeys | Lenth-height Factor | Sub-Condition | Charge (%) | Total Charge (%) | Total Exposure Charge (L/min) | | |
| | Side 1 | 80.5 | 6 | > 45.1 | Type A | 29 | 1 | 29 | 6 | 0% | 0% | 0 | 4,148 | |
| | Side 2 | 100 | 6 | > 45.1 | Type A | 0 | 0 | 0 | 6 | 0% | | | | |
| | Front | 62.5 | 6 | > 45.1 | Type A | 16.4 | 2 | 32.8 | 6 | 0% | | | | |
| Back | 100 | 6 | > 45.1 | Type A | 0 | 0 | 0 | 6 | 0% | | | | | |
| Obtain Required Fire Flow | Total Required Fire Flow, Rounded to the Nearest 1,000 L/min = | | | | | | | | | | | | | 4,000 |
| | Total Required Fire Flow, L/s = | | | | | | | | | | | | | 67 |

Exposure Charges for Exposing Walls of Wood Frame Construcion (from Table G5)

| | |
|--------|----------------------------------------------------------|
| Type A | Wood-Frame or non-combustible |
| Type B | Ordinary or fire-resisitive with unprotected openings |
| Type C | Ordinary or fire-resisitive with semi-protected openings |
| Type D | Ordinary or fire-resisitive with nblank wall |

Conditons for Separation

| Separation Dist | Condition |
|-----------------|-----------|
| 0m to 3m | 1 |
| 3.1m to 10m | 2 |
| 10.1m to 20m | 3 |
| 20.1m to 30m | 4 |
| 30.1m to 45m | 5 |
| > 45.1m | 6 |

KMA MOSQUE AND COMMUNITY CENTRE
Client:KANATA MUSLIM ASSOCIATION
Project: OTT-00238504-A0

Prepared By: A. Elgayar
Date: July 2018

Max day(0.41L/s) + FireFlow(67L/s) HGL= 125.1 m
Max HGL= 131.5 m
Peak Hour= 124.2 m

Table C1 Pressure Analysis

| Description | From | To | Flow (L/sec) | Pipe Dia (mm) | Dia (m) | Q (m³/sec) | Area (m2) | C | Velocit y V (m/s) | Slope of HGL (m/m) | Pipe Length (m) | Frictional Head Loss hf (m) | Equivalent Pipe Length of Fittings (m) | Minor Loss of Fittings hb (m) | Total Losses (m) hb + hf | Start Ground Elev(m) | End Ground Elev (m) | Static Head (m) | Pressure From | | Pressure To | | Pressure Drop (psi) |
|---------------------|------|----------|-----------------|------------------|---------|---------------|--------------|-----|-------------------------|--------------------------|-----------------------|--------------------------------|----------------------------------------------|-------------------------------------|-----------------------------|----------------------------|---------------------------|-----------------------|---------------|--------|-------------|--------|------------------------|
| | | | | | | | | | | | | | | | | | | | kPa | (psi) | kPa | (psi) | |
| Max Day + Fire Flow | Main | Building | 67 | 200 | 0.200 | 0.067 | 0.0314159 | 110 | 2.1327 | 0.0300 | 35 | 1.050311609 | 13.2 | 0.39612 | 1.44643 | 74.73 | 76.90 | -2.17 | 494.0 | (71.6) | 458.5 | (66.5) | 5.1 |
| Max HGL | Main | Building | 0.3 | 200 | 0.200 | 0.0003 | 0.0314159 | 110 | 0.0095 | 0.0000 | 35 | 4.68874E-05 | 13.2 | 0.00002 | 0.00006 | 74.73 | 76.90 | -2.17 | 556.7 | (80.7) | 535.5 | (77.7) | 3.1 |
| Peak Hour | Main | Building | 0.7 | 200 | 0.200 | 0.0007 | 0.0314159 | 110 | 0.0223 | 0.0000 | 35 | 0.00022519 | 13.2 | 0.00008 | 0.00031 | 74.73 | 76.90 | -2.17 | 485.2 | (70.4) | 463.9 | (67.3) | 3.1 |
| | | | | | | | | | | | | | | | | | | | | | | | |

V=Q/A
Slope of HGL= $\left(\frac{3.59}{C}\right)^{1.852} \frac{Q^{1.852}}{D^{4.87}}$

hf = Slope of HGL * Pipe Length

Resistance of Fittings and Valves for 200mm WM

| Fittings | Loss in | | | |
|-----------------------|-----------|---------------|----------|--------------|
| | Equiv. | | | |
| | Length in | Equiv. | Quantity | Total Equiv. |
| | Pipe | Length | (each) | Length (m) |
| | Diameters | (metres) | | |
| Standard 90° Elbow | 32 | 6.40 | 1 | 6.4 |
| 11.25 Degree Elbow | 8 | 1.60 | 1 | 1.6 |
| 45 Degree Elbow | 16 | 3.20 | 0 | 0 |
| Gate Valve Full -Open | 13 | 2.60 | 2 | 5.2 |
| | | Total: | 4 | 13.2 |

Appendix D – Sewer Design Sheets

From: Ahmed Aref <aaref@aplus-arch.com>
Sent: Thursday, November 15, 2018 1:26 PM
To: Aly Elgayar
Cc: Mehmood Shaikh; Alam Ansari
Subject: KMA Mosque & Community Centre: Occupant Load Calculations

Hi Aly,

As requested, here is a breakdown of the proposed occupant load for the buildings:

- Existing Building: 180 persons
- New Building: 1,271 persons (assuming the gymnasium hall will be used as an assembly space).

Let me know if you have any questions.

Thanks,

Ahmed Aref, Architect, OAA, MRAIC, LEED Green Assoc.

Principal

A+ Architecture Inc.

555 Legget Drive, Tower A, Suite 304, Kanata, ON K2K 2X3



| | | | | | | | | | | |
|-----------------------------------------------|---------|------------------------------------|-------|------------------|------------------------------------|---------------------------------------------|------------------|---------------------|--------------------------|---------------------------------|
| Residential Avg. Daily Flow, q (L/p/day) = | 280 | Commercial Peak Factor = | 1.5 | (when area >20%) | Peak Population Flow, (L/sec) = | $P \cdot q \cdot M / 86.4$ | <u>Unti Type</u> | <u>Persons/Unit</u> | Designed: | Project: |
| Commercial Avg. Daily Flow (L/gross ha/day) = | 28,000 | | 1.0 | (when area <20%) | Peak Extraneous Flow, (L/sec) = | $I \cdot A_c$ | Singles | 3.4 | A. Elgayar, M.A.Sc. | KMA Mosque and Community Center |
| or L/gross ha/sec = | 0.324 | | | | Residential Peaking Factor, M = | $1 + (14 / (4 + P^{0.5})) \cdot K$ | Semi-Detached | 5.7 | | |
| Institutional Avg. Daily Flow (L/s/ha) = | 28,000 | Institutional Peak Factor = | 1.5 | (when area >20%) | A_c = Cumulative Area (hectares) | | Townhomes | 2.7 | Checked: | Location: |
| or L/gross ha/sec = | 0.324 | | 1.0 | (when area <20%) | P = Population (thousands) | | Single Apt. Unit | 1.4 | | |
| Light Industrial Flow (L/gross ha/day) = | 35,000 | | | | | | 2-bed Apt. Unit | 2.1 | A. Ansari, P.Eng. | Ottawa, Ontario |
| or L/gross ha/sec = | 0.40509 | Residential Correction Factor, K = | 0.80 | | Sewer Capacity, Qcap (L/sec) = | $1/N \cdot S^{1/4} \cdot R^{2/3} \cdot A_c$ | 3-bed Apt. Unit | 3.1 | | |
| Light Industrial Flow (L/gross ha/day) = | 55,000 | Manning N = | 0.013 | | (Manning's Equation) | | 4-bed Apt. Unit | 3.8 | File Reference: | Page No: |
| or L/gross ha/sec = | 0.637 | Peak extraneous flow, I (L/s/ha) = | 0.33 | (Total I/I) | | | | | 238504 - SAN Design.xlsx | 1 of 1 |

TABLE C-1: 5-YEAR STORM SEWER CALCULATION SHEET




Return Period Storm = 5 (5-year)
Default Inlet Time= 10 (minutes)
Manning Coefficient = 0.013 (dimensionless)

| LOCATION | | | AREA (hectares) | | | FLOW (UNRESTRICTED) | | | | | | SEWER DATA | | | | | | | | | | | |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------|----------|-----------------|-----------|-----------|------------------------------------------------------------------------------------------------------|-----------------|-----------|----------|---------------|-----------|-------------------------------------|------------------|------|-----------|-----------------------------------------|------------------|----------------|------|----------------------------|------------------|-------|--|
| Location | From Node | To Node | Area No. | Area (ha) | Average R | Indiv. 2.78*A*R | Accum. 2.78*A*R | Tc (mins) | I (mm/h) | Return Period | Q (L/sec) | Dia (mm) Actual | Dia (mm) Nominal | Type | Slope (%) | Length (m) | Capacity (L/sec) | Velocity (m/s) | | Time in Pipe, Tt (min) | Hydraulic Ratios | | |
| | | | | | | | | | | | | | | | | | | Vf | Va | | Qa/Qf | Va/Vf | |
| | | | | | | | | | | | | | | | | | | | | | | | |
| 351 Sandhill Road | CB105 | CBMH205 | PH2A | 0.0300 | 0.78 | 0.07 | 0.07 | 10.00 | 104.19 | 5.00 | 6.8 | 201.16 | 200 | PVC | 1.00 | 17.40 | 33.3 | 1.04 | 0.69 | 0.42 | 0.20 | 0.66 | |
| | CB106 | CBMH205 | PH2A | 0.0450 | 0.78 | 0.10 | 0.10 | 10.00 | 104.19 | 5.00 | 10.2 | 201.16 | 200 | PVC | 1.00 | 19.60 | 33.3 | 1.04 | 0.73 | 0.45 | 0.31 | 0.70 | |
| | CB104 | CBMH205 | PH2A | 0.060 | 0.78 | 0.13 | 0.13 | 10.00 | 104.19 | 5.00 | 13.6 | 201.16 | 200 | PVC | 1.00 | 15.30 | 33.3 | 1.04 | 0.74 | 0.35 | 0.41 | 0.71 | |
| | CB107 | CBMH205 | PH2A | 0.080 | 0.78 | 0.17 | 0.17 | 10.00 | 104.19 | 5.00 | 18.1 | 201.16 | 200 | PVC | 1.00 | 14.60 | 33.3 | 1.04 | 0.74 | 0.33 | 0.54 | 0.71 | |
| | CB103 | CBMH205 | PH2A | 0.090 | 0.78 | 0.20 | 0.20 | 10.00 | 104.19 | 5.00 | 20.3 | 201.16 | 200 | PVC | 1.00 | 15.30 | 33.3 | 1.04 | 0.95 | 0.27 | 0.61 | 0.91 | |
| | CB108 | CBMH205 | PH2A | 0.100 | 0.78 | 0.22 | 0.22 | 10.00 | 104.19 | 5.00 | 22.6 | 201.16 | 200 | PVC | 1.00 | 18.40 | 33.3 | 1.04 | 0.88 | 0.35 | 0.68 | 0.84 | |
| | | | | | | | | | | | | | | | | | | | | | | | |
| | CBMH205 | CBMH204 | | | | | 0.88 | 10.42 | 102.02 | 5.00 | 89.6 | 610 | 600 | CONC | 0.50 | 44.60 | 453.7 | 1.54 | 1.03 | 0.72 | 0.20 | 0.67 | |
| | | | | | | | | | | | | | | | | | | | | | | | |
| | CB102 | CBMH204 | PH2A | 0.047 | 0.78 | 0.10 | 0.10 | 10.00 | 104.19 | 5.00 | 10.6 | 201.16 | 200 | PVC | 1.00 | 15.50 | 33.3 | 1.04 | 0.73 | 0.35 | 0.32 | 0.70 | |
| | | | | | | | | | | | | | | | | | | | | | | | |
| | CBMH204 | CBMH203 | | | | | 0.98 | 11.14 | 98.52 | 5.00 | 96.6 | 610 | 600 | CONC | 0.50 | 23.20 | 453.7 | 1.54 | 1.01 | 0.38 | 0.21 | 0.66 | |
| | | | | | | | | | | | | | | | | | | | | | | | |
| | CB101 | CBMH203 | PH2B | 0.120 | 0.77 | 0.26 | 0.26 | 10.00 | 104.19 | 5.00 | 26.8 | 201.16 | 200 | PVC | 1.00 | 2.70 | 33.3 | 1.04 | 1.02 | 0.04 | 0.80 | 0.98 | |
| | ROOF | CBMH203 | PH2C | 0.150 | 0.90 | 0.38 | 0.38 | 10.00 | 104.19 | 5.00 | 39.1 | 251.46 | 250 | PVC | 0.50 | 15.00 | 42.7 | 0.86 | 0.86 | 0.29 | 0.92 | 1.00 | |
| | | | | | | | | | | | | | | | | | | | | | | | |
| | CBMH203 | STMMH202 | | | | | 1.61 | 11.52 | 96.77 | 5.00 | 156.0 | 610 | 600 | CONC | 0.50 | 67.00 | 453.7 | 1.54 | 1.07 | 1.04 | 0.34 | 0.70 | |
| | | | | | | | | | | | | | | | | | | | | | | | |
| | STMMH202 | STMMH201 | | | | | 1.61 | 12.56 | 92.35 | 5.00 | 148.9 | 610 | 600 | CONC | 0.50 | 15.00 | 453.7 | 1.54 | 1.07 | 0.23 | 0.33 | 0.70 | |
| | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | |
| TOTALS = | | | | | | 283.60 | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | |
| Definitions: Q = 2.78*AIR, where Q = Peak Flow in Litres per second (L/s) A = Watershed Area (hectares) I = Rainfall Intensity (mm/h) R = Runoff Coefficients (dimensionless) | | | | | | Notes: Ottawa Rainfall Intensity Values: a = 998.071 From Sewer Desing Guidelines, 2004 | | | | | | Designed: A. Elgayar | | | | Project: 351 Sand Hill Road | | | | | | | |
| | | | | | | | | | | | | Checked: A. Ansari, PEng. | | | | Location: Ottawa, Ontario | | | | | | | |
| | | | | | | | | | | | | Dwg Reference: SSGP-2 | | | | File Ref: 238504 - STM Design | | | | Sheet No: 1 of 1 | | | |


Appendix E – Drawings


Filename: P:\Projects\Civil Engineering Services\238000\OTT-00238504-A0 - KMA Mosque and Community Centre\60-EXECUTION\64-DWG\Sketches & Figures\FIG-1 - Pre-develop Aerial.dwg
Last Saved: Nov 11, 2018 1:09 PM Last Plotted: Nov 11, 2018 1:10 PM Plotted by: Edgavara




| | | | | | |
|-----------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------|---------|-----------------|------------------------------------------------------------------|----------------|
| exp Services Inc. 100-2650 Queensview Drive Ottawa, ON K2B 8H6 www.exp.com |  | DESIGN | AE | KMA MOSQUE AND COMMUNITY CENTRE 351 SANDHILL ROAD, OTTAWA, ON | SCALE N.T.S |
| | | DRAWN | AE | | SKETCH NO |
| | | DATE | NOV 2018 | PRE-DEVELOPMENT AERIAL IMAGE | FIG-1 |
| | | FILE NO | OTT-00238504-A0 | | |

Filename: P:\Projects\Civil Engineering Services\238000\OTT-00238504-A0 - KMA Mosque and Community Centre\60-EXECUTION\64-DWG\Sketches & Figures\Fig-2 - Phasing Plan.dwg
Last Saved: Nov 11, 2018 12:41 PM Last Plotted: Nov 11, 2018 12:59 PM Plotted by: Edayara




| | | | | | | |
|-----------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------|---------|-----------------|------------------------------------------------------------------|--------------|-----------|
| <div>exp Services Inc.</div> <div>100-2650 Queensview Drive Ottawa, ON K2B 8H6</div> <div>www.exp.com</div> |  | DESIGN | AE | KMA MOSQUE AND COMMUNITY CENTRE 351 SANDHILL ROAD, OTTAWA, ON | SCALE | 1:400 |
| | | DRAWN | AE | | PHASING PLAN | SKETCH NO |
| | | DATE | SEPT 2018 | | | |
| | | FILE NO | OTT-00238504-A0 | | | |




LEGEND

| | |
|-----|----------------------------------|
| SB | STANDARD IRON BAR |
| IB | IRON BAR |
| CB | CATCH-BASIN |
| MH | MANHOLE |
| WMH | WATER MANHOLE |
| LS | LAMP STANDARD |
| UP | UTILITY POLE |
| WV | WATER VALVE |
| PH | FIRE HYDRANT |
| W | WELL |
| ... | GUY WIRE AND ANCHOR |
| --- | WATERMAIN |
| --- | OVERHEAD UTILITY WIRES |
| --- | UNDERGROUND HYDRO |
| --- | UNDERGROUND BELL |
| --- | GAS MAIN |
| --- | CABLE (ROGERS) |
| --- | STREET LIGHT |
| --- | STORM SEWER |
| --- | SANITARY SEWER |
| --- | CURB |
| --- | PROPERTY LINE |
| --- | EXISTING ELEVATION |
| ==> | EXISTING OVERLAND FLOW DIRECTION |



PRELIMINARY
NOT FOR CONSTRUCTION

| NO. | REVISION DESCRIPTION | DATE | BY | APPD |
|-----|-----------------------------|----------|----|------|
| 1 | ISSUED FOR SITE APPLICATION | 02/11/18 | AE | AA |



DESIGNED BY

REVIEWED BY

CLIENT

KANATA MUSLIM ASSOCIATION
832 MARCH ROAD, OTTAWA, ON.
K2W 0C9
613.973.5000

exp. SERVICES INC.
2111 10th Avenue, Suite 100
Ottawa, ON K1M 1B8
Canada
www.exp.ca
• BUILDINGS • EARTH & ENVIRONMENT • ENERGY •
• INDUSTRIAL • INFRASTRUCTURE • SUSTAINABILITY •

PROJECT MANAGER

AA

PROJECT NO. OTT-00238504-A0
SURVEY F M & W
DATE 2018-08-20
DRAWING NO. EX
EXISTING CONDITIONS


CAUTION
THE POSITION OF ALL POLE LINES, CONDUITS, WATERMANS, SEWERS AND OTHER UNDERGROUND AND OVERGROUND UTILITIES AND STRUCTURES IS NOT NECESSARILY SHOWN ON THE CONTRACT DRAWINGS, AND WHERE SHOWN, THE ACCURACY OF THE POSITION OF SUCH UTILITIES AND STRUCTURES IS NOT GUARANTEED. BEFORE STARTING WORK, DETERMINE THE EXACT LOCATION OF ALL SUCH UTILITIES AND STRUCTURES AND ASSUME ALL LIABILITY FOR DAMAGE TO THEM.

1. CONTRACTOR IS RESPONSIBLE FOR ALL LAYOUT FOR CONSTRUCTION.
2. ALL ELEVATIONS ARE GEODETIC AND UTILIZE METRIC UNITS.
3. JOB BENCH MARK -- CONFIRM WITH exp SERVICES INC. PRIOR TO UTILIZATION.
4. ALL DIMENSIONS ARE IN METERS UNLESS OTHERWISE STATED. ALL DRAWINGS SHOULD NOT BE SCALED BY THE CONTRACTOR. ANY MISSING OR QUESTIONABLE DIMENSIONS ARE TO BE CONFIRMED WITH THE CONSULTANT IN WRITING.
5. CONSTRUCTION SHALL BE IN ACCORDANCE WITH CITY OF OTTAWA AND ONTARIO PROVINCIAL STANDARD DRAWING SUPPLEMENTS WHERE APPLICABLE AND ONTARIO PROVINCIAL STANDARDS SHALL APPLY WHERE NO CITY STANDARDS ARE AVAILABLE.
6. ANY DISCREPANCIES, INTERPRETATIONS, CHANGES AND ADDITIONS TO THESE DRAWINGS MUST BE BROUGHT TO THE ATTENTION OF THE ENGINEER, WHEN NOTED AND BEFORE PROCEEDING WITH CONSTRUCTION WORKS.
7. REFER TO ARCHITECT'S SITE PLAN FOR BUILDING DIMENSIONS AND SITE LAYOUT. DIMENSIONS AND LAYOUT INFORMATION SHALL BE CONFIRMED PRIOR TO COMMENCEMENT OF CONSTRUCTION.
8. REFER TO THE LANDSCAPE ARCHITECT'S PLAN FOR SIDEWALK, PATHWAYS, PLANTING AND OTHER LANDSCAPE FEATURE MATERIALS AND LOCATIONS.
9. FOR GEOTECHNICAL INFORMATION REFER TO THE GEOTECHNICAL INVESTIGATION REPORT PREPARED BY PATERSON GROUP DATED NOVEMBER 2018.
10. ALL OBTURBED AREAS TO BE REINSTATED TO EQUAL OR BETTER CONDITION. ALL NEW WORK SHALL BE INTO EXISTING.
11. ALL GROUND SURFACES SHALL BE EVENLY GRADED WITHOUT PONDING AREAS AND WITHOUT LOW POINTS EXCEPT WHERE APPROVED SWALE OR CATCHBASIN OUTLETS ARE PROVIDED.
12. ALL EDGES OF OBTURBED PAVEMENT SHALL BE SAWCUT TO FORM A NEAT AND STRAIGHT LINE PRIOR TO PLACING NEW PAVEMENT.
13. CONTRACTOR IS TO COMPLY WITH THE CITY OF OTTAWA REQUIREMENTS FOR TRAFFIC CONTROL WHEN WORKING ON CITY STREETS.
14. ALL MATERIAL SUPPLIED AND PLACED FOR PARKING LOT AND ACCESS ROAD CONSTRUCTION SHALL BE TO CITY OF OTTAWA AND OPSS STANDARDS AND SPECIFICATIONS UNLESS OTHERWISE NOTED: MATERIALS OPSS 206, 310 & 314 MATERIALS OPSS 1001, 1003 & 1010).

15. THE CONTRACTOR SHALL CONSIDER LOCATIONS AND ELEVATIONS OF EXISTING SERVICES AND STRUCTURES TO BE CONNECTED TO AND EXISTING SERVICES THAT MAY BE DAMAGED OR CAUSE CONFLICTS PRIOR TO CONSTRUCTION OF ANY NEW SEWER, WATER AND/OR STORM WATER CONDUIT. THE ENGINEER SHALL BE INFORMED IMMEDIATELY OF ANY ERRORS, OISCREPANCIES, CONFLICTS, OMISSIONS etc. THAT ARE FOUND. DO NOT CONTINUE CONSTRUCTION IN AREAS WHERE DISCREPANCIES APPEAR UNTIL SUCH DISCREPANCIES HAVE BEEN RESOLVED.
16. THE CONTRACTOR SHALL PROTECT ANY SUCH EXISTING SERVICES & FACILITIES. SUCH PROTECTION MEASURES INCLUDE, BUT ARE NOT LIMITED TO: ENSURE ALL CONCERNED UTILITIES HAVE LOCATED THEIR PLANT PRIOR TO ANY EXCAVATING, LOCATE AND FLAG/PAINT THE LOCATIONS OF ANY U/G PLANT WHICH MIGHT BE DAMAGED BY EXCAVATION AND CONSTRUCTION TRAFFIC AND DIG IN PROXIMITY TO EXISTING BURIED SERVICES TO LOCATE THEM WITHOUT ANY RESULTING DAMAGE, BRACE AND SUPPORT WHERE REQUIRED.
17. THE CONTRACTOR SHALL IMPLEMENT BEST MANAGEMENT PRACTICES FOR THE PROTECTION OF THE AREA'S DRAINAGE SYSTEM AND THE RECEIVING WATERCOURSE DURING CONSTRUCTION ACTIVITIES. THIS INCLUDES LIMITING THE LOSS OF EROSION SOIL AND SILT FILTERS UNDER GRATES OF CATCHBASINS AND MANHOLES AND INSTALLING SILT FENCES AND OTHER EFFECTIVE SEDIMENT TRAPS. THE CONTRACTOR ACKNOWLEDGES THAT FAILURE TO IMPLEMENT APPROPRIATE EROSION AND SEDIMENT CONTROL MEASURES MAY BE SUBJECT TO PENALTIES IMPOSED BY ANY APPLICABLE REGULATORY AGENCY.
18. DESIGN ELEVATIONS GIVEN ON THESE PLANS ARE TO BE ADHERED TO WITH NO CHANGES WITHOUT PRIOR WRITTEN APPROVAL BY exp. SERVICES INC. SURFACE PONDING STORAGE VOLUMES AND INLET CONTROL DEVICE DESIGN MUST BE APPROVED BY THE DESIGN REPORT PREPARED BY exp. SERVICES INC FOR THIS PROJECT.
19. THE CONTRACTOR IS RESPONSIBLE FOR AND SHALL PROVIDE FOR DEWATERING, SUPPORT AND PROTECTION OF EXCAVATIONS AND TRENCHING AS WELL AS RELEASE OF ANY PUMPED GROUND WATER IN A CONTROLLED AND APPROVED MANNER. THE CONTRACTOR SHALL APPLY FOR A PERMIT TO EXCAVATE WITHIN THE MINIMUM OF EROSION IF MORE THAN 50,000 LITRES PER DAY OF GROUNDWATER IS PUMPED FOR CONSTRUCTION ACTIVITIES.
20. FOR TOPOGRAPHICAL INFORMATION REFER TO PLAN PREPARED BY FAIRHALL MOFFATT & WOOLLAND LTD. FOR LEGAL PROPERTY LINE DESCRIPTIONS.
21. CITY INSPECTOR IS TO NOTIFIED OF ANY WORKS IN THE ROW WITH SUFFICIENT NOTICE.
22. CLAY SEAL TO BE AS PER OPSO 802.D95.

23. SHOULD ANY CONDITIONS AT THE SITE BE ENCOUNTERED WHICH DIFFER FROM THE TEST LOCATIONS IDENTIFIED IN THE GEOTECHNICAL REPORT, PATERSON'S GEOTECHNICAL ENGINEER IS TO BE NOTIFIED IMMEDIATELY IN ORDER TO PERMIT REASSESSMENT OF THE GEOTECHNICAL RECOMMENDATIONS.

1. ASPHALT REINSTATEMENT AS PER CITY OF OTTAWA STANDARD DRAWING R10.
2. CURBS TO BE CONCRETE BARRIER CURBS AS PER CITY OF OTTAWA STANDARD DRAWING SC1.1.
3. THE CONTRACTOR SHALL COMPLETE ALL RESTORATION WITHIN CITY ROW TO A CONDITION EQUAL TO ORIGINAL OR BETTER AND TO THE SATISFACTION OF THE MUNICIPAL AUTHORITIES.



NOTES:

REMOVE ALL ORGANICS AND DELETERIOUS MATERIALS UNDERLYING PAVEMENT CONSTRUCTION. SUPPLY AND INSTALL SUBGRADE FILL THAT HAS PRIOR APPROVAL BY GEOTECHNICAL CONSULTANT. PLACE AND COMPACT SUBGRADE FILL IN MAX 300mm LIFTS. COMPACT TO MIN. 96% SPMD.

PROOF ROLL SUBGRADE IN PRESENCE OF GEOTECHNICAL CONSULTANT.


EXCAVATE AND REPLACE AREAS WITH APPROVED PLATIVE OR GRANULAR MATERIAL AS DIRECTED BY GEOTECHNICAL CONSULTANT.

COMPACT GRANULARS TO MIN. 98% SPMD. SUPPLY AND PLACE WATER NECESSARY TO ACHIEVE SPECIFIED COMPACTION. INSTALL GRANULAR "B" TO BE APPROVED BY GEOTECHNICAL CONSULTANT PRIOR TO INSTALLATION OF ASPHALT.

MINIMUM PERFORMANCE GRADE 58-3 ASPHALT CEMENT TO BE USED. INSTALL GRANULAR "A" SHALL BE APPROVED BY GEOTECHNICAL CONSULTANT PRIOR TO INSTALLATION OF ASPHALT.

PAVEMENT MAKE-UP AND INSTALLATION TO COMPLY WITH THE GEOTECHNICAL REPORT REPORT


PAVEMENT DETAIL



THE POSITION OF ALL POLE LINES, CONDUITS, WATERMAINS, SEWERS AND OTHER UNDERGROUND AND OVERGROUND UTILITIES AND STRUCTURES IS NOT NECESSARILY SHOWN ON THE CONTRACT DRAWINGS, AND WHERE SHOWN, THE ACCURACY OF THE POSITION OF SUCH UTILITIES AND STRUCTURES IS NOT GUARANTEED. BEFORE STARTING WORK, DETERMINE THE EXACT LOCATION OF ALL SUCH UTILITIES AND STRUCTURES AND ASSUME ALL LIABILITY FOR DAMAGE TO THEM.

PRELIMINARY
NOT FOR CONSTRUCTION

| 3 | REVISED AS PER CITY COMMENTS | 02/11/18 | AE | AA | |
|-----|-------------------------------|----------|----|------|--|
| 2 | ISSUED FOR SITE PLAN APPROVAL | 29/06/18 | AE | AA | |
| 1 | ISSUED FOR SITE PLAN APPROVAL | 13/09/17 | ML | AA | |
| NO. | REVISION DESCRIPTION | DATE | BY | APPD | |



DESIGNED BY

REVIEWED BY

M.A. Ansari

LICENSED PROFESSIONAL ENGINEER

M.A. ANSARI


23/11/2018

PROVINCE OF ONTARIO

CLIENT
KANATA MUSLIM ASSOCIATION
832 MARCH ROAD, OTTAWA, ON.
K2W 0C9
613.973.5000

 **exp.** **Services Inc.**
t +1.613.888.1869 | f +1.613.225.7330
2050 Queenwood Drive, Unit 100
Ottawa, ON K2B 8H0
Canada
www.exp.com
• BUILDINGS • EARTH & ENVIRONMENT • ENERGY

| | | | | | | | | |
|----------------------------------------------------------------------------------------------------------------------------------------------------------|----------|----------------------------|-----------------|----|----------|----|-------------------------------------------------------------------------------------------|---------------------------------------|
| <table border="1"> <tr> <td>BASEPLAN</td> <td>ML</td> </tr> <tr> <td>DESIGN</td> <td>ML</td> </tr> <tr> <td>CHECKED</td> <td>AA</td> </tr> </table> | BASEPLAN | ML | DESIGN | ML | CHECKED | AA | PROJECT KMA MOSQUE AND COMMUNITY CENTRE 351 SANDHILL ROAD, OTTAWA, ON | PROJECT No. OTT-00238504-AC |
| BASEPLAN | ML | | | | | | | |
| DESIGN | ML | | | | | | | |
| CHECKED | AA | | | | | | | |
| <table border="1"> <tr> <td>CAD</td> <td>ML</td> </tr> <tr> <td>PROJECT MANAGER</td> <td>AA</td> </tr> <tr> <td>APPROVED</td> <td>AA</td> </tr> </table> | CAD | ML | PROJECT MANAGER | AA | APPROVED | AA | SURVEY F M & W DATE 2016-12-09 | |
| CAD | ML | | | | | | | |
| PROJECT MANAGER | AA | | | | | | | |
| APPROVED | AA | | | | | | | |
| TITLE GRADING PLAN PHASE 1 | | DRAWING No. GP-1 | | | | | | |



LEGEND

- SIB — STANDARD IRON BAR
 IB — IRON BAR
 CB — CATCH BASIN
 MH — MANHOLE
 WMH — WATER MANHOLE
 LS — LAMP STANDARD
 UP — UTILITY POLE
 WV — WATER VALVE
 FH — FIRE HYDRANT
 W — WELL
 — GUY WIRE AND ANCHOR
 — WATERMAIN
 — OVERHEAD UTILITY WIRES
 — UNDERGROUND HYDRO
 — UNDERGROUND BELL
 — GAS MAIN
 — CABLE (ROGERS)
 — STREET LIGHT
 — STORM SEWER
 — SANITARY SEWER
 — CURB
 — PROPOSED CURB
 — PROPOSED WATERMAIN
 — PROPOSED STORM SEWER
 — PROPOSED SANITARY SEWER
 — PROPOSED CLAY SEAL AT 60m INTERVALS
 — PROPOSED SANITARY MANHOLE
 — PROPOSED STORM MANHOLE
 — PROPOSED STORM CATCHBASIN MANHOLE
 — PROPOSED STORM CATCHBASIN
 — PROPOSED FIRE HYDRANT
 — PROPOSED VALVE & VALVE BOX
 — PROPOSED SIAMSE CONNECTION
 — PROPOSED WATER METER
 — PROPOSED REMOTE WATER METER
 — PROPOSED LIGHT STANDARD
 76.40 — PROPOSED ELEVATION
 4'-10" — EXISTING ELEVATION
 — PROPOSED HEAVY DUTY PAVEMENT
 — PROPOSED LIGHT DUTY PAVEMENT
 — PROPOSED CONCRETE SIDEWALK
 HP — HIGH POINT
 — OVERLAND FLOW DIRECTION

APPROVED ☐ REFUSED ☐

THIS DAY OF 20

DERRICK MOOOIE, MANAGER
DEVELOPMENT REVIEW WEST
PLANNING INFRASTRUCTURE AND ECONOMIC
DEVELOPMENT DEPARTMENT, CITY OF OTTAWA.

WATERMAIN

1. ALL WATERMAIN AND WATER SERVICE MATERIALS AND INSTALLATION SHALL CONFORM TO THE CURRENT CITY OF OTTAWA STANDARD DRAWINGS AND SPECIFICATIONS.
2. ALL WATERMAIN TO BE INSTALLED AT MINIMUM COVER OF 2.4m. THERMAL INSULATION SHALL BE INSTALLED WHERE ADEQUATE SEPARATION CANNOT BE ACHIEVED AS PER CITY STANDARD W21, W22 AND W23.
3. ALL WATERMAIN WORK AND MATERIAL SHALL BE IN ACCORDANCE WITH CITY OF OTTAWA STANDARDS. NO WORK SHALL COMMENCE UNLESS A CITY WATER WORKS INSPECTOR IS ON SITE. WATERMAIN CONNECTIONS BY CITY OF OTTAWA FORCES WITH ALL EXCAVATION BACKFILL AND ROAD REINSTATEMENT BY CONTRACTOR.
4. WATERMAIN IS TO BE PVC DR18 WITH TRACER WIRE AS PER CITY OF OTTAWA DETAIL W36 UNLESS OTHERWISE NOTED.
5. VALVE BOXES AS PER CITY OF OTTAWA DETAIL W24.
6. ALL FIRE HYDRANTS TO BE INSTALLED AS PER CITY STANDARD W19 AND LOCATED AS PER CITY STANDARD W18 AND/OR CITY STANDARD CROSS SECTIONS.
7. WATERMAIN BEDDING IS TO BE AS PER CITY OF OTTAWA DETAIL W17.
8. THRUST BLOCKS AND RESTRAINT AS PER CITY OF OTTAWA DWGS: W25.3, W25.4, W25.5 AND W25.6.
9. CATHODIC PROTECTION REQUIRED FOR ALL IRON FITTINGS PER CITY OF OTTAWA DWGS: W39, W40, W41.
10. IF WATERMAIN MUST BE DEFLECTED TO MEET ALIGNMENT, ENSURE THAT THE AMOUNT OF DEFLECTION USED IS LESS THAN HALF THAT RECOMMENDED BY THE MANUFACTURER.
11. DISINFECTION AND TESTING OF WATERMAIN TO BE IN ACCORDANCE WITH CITY OF OTTAWA STANDARDS.
12. WATER SERVICES TO BE INSTALLED AS PER CITY OF OTTAWA STANDARD W26 AND W35.
13. WITHIN THE FROST ZONE, THE BACKFILL IN THE SERVICE TRENCHES SHOULD MATCH THE SOIL ON

SIDES TO MINIMIZE DIFFERENTIAL FROST HEAVING IN THE SUBGRADE.

14. INSTALLATION OF WATER METER AND REMOTE RECEPTACLE SHALL BE IN ACCORDANCE WITH CITY OF OTTAWA STANDARDS.


STORM AND SANITARY SEWERS

1. SANITARY AND STORM SEWER MATERIALS AND INSTALLATION SHALL CONFORM TO THE CURRENT CITY OF OTTAWA STANDARD DRAWINGS AND SPECIFICATIONS AND OPS 407 AND 410.
2. SEWER BEDDING AS PER CITY STANDARD S6 & S7.
3. ALL SANITARY SEWERS ARE TO BE THE SIZES INDICATED AND THE MATERIAL SHALL BE PVC SDR35.
4. ALL STORM SEWERS ARE TO BE THE SIZES INDICATED AND THE MATERIAL SHALL BE PVC SDR35 OR REINFORCED CONCRETE IN ACCORDANCE WITH CSA STANDARDS A257.2 AND A257.3 (JOINTS).
5. ALL MANHOLES, CATCHBASINS AND CATCH-BASIN MANHOLES TO BE BACKFILLED WITH MIN. 0.3m HORIZONTAL THICKNESS GRANULAR 'A'.
6. SUPPLY AND INSTALL ALL PIPING AND APPURTENANCES AS SHOWN TO WITHIN 1.0m OF BUILDING WALLS AND PROVIDE TEMPORARY CAPS.
7. THE CONTRACTOR SHALL CONDUCT INFILTRATION/EXFILTRATION (AS PER CURRENT OPS) TESTING ON ALL NEWLY INSTALLED SANITARY SEWERS. THE TEST SHALL BE PERFORMED IMMEDIATELY AFTER SEWER INSTALLATION AND SUPERVISED BY THE ENGINEER.
8. THE CONTRACTOR SHALL CONDUCT CCTV INSPECTION OF ALL NEWLY INSTALLED STORM AND SANITARY SEWERS AND EXISTING SEWERS CONNECTED TO THE TEST SHALL BE PERFORMED IMMEDIATELY AFTER SEWERS INSTALLED AND SUPERVISED BY THE ENGINEER.
9. ALL SERVICE CONNECTIONS TO BE CONSTRUCTED AS PER CITY STANDARD S11 & S11.1.
10. ALL SANITARY BUILDING DRAINS TO BE EQUIPPED WITH SANITARY BACKWATER VALVES INSTALLED PER CITY OF OTTAWA STANDARD DRAWING S14.1.
11. MINIMUM SOIL COVER TO BE 2.0m TO PROTECT SEWERS FROM FROST DAMAGE. IN AREAS WHERE ADEQUATE COVER CANNOT BE ACHIEVED, THERMAL INSULATION TO BE INSTALLED AS PER OPSD 514.010.


| STRUCTURE TABLE | | | |
|-----------------|---------------|------------------------------------|--------------------------------|
| STRUCTURE LABEL | SIZE | STRUCTURE OPSD No. OR CITY STD DWG | FRAME OPSD No. OR CITY STD DWG |
| SANMH 301 | 1200mmØ | 701.010 | 401.010-A |
| SANMH 302 | 1200mmØ | 701.010 | 401.010-A |
| SANMH 303 | 1200mmØ | 701.010 | 401.010-A |
| CBs | 600mm x 600mm | 705.010 | 400.020 |
| | 1800mmØ | 701.010 | 401.010-B |
| STMMH 201 | 1200mmØ | 701.010 | 401.010-B |
| STMMH 202 | 1200mmØ | 701.010 | 401.010-B |
| CBMH 204 | 1200mmØ | 701.010 | 401.010-B |
| CBMH 205 | 1200mmØ | 701.010 | 401.010-B |


| WATERMAIN TABLE | | | |
|-----------------|-----------|-----------|--------------------------------------------|
| STATION | FIN/GRADE | T/W GRADE | COMMENT |
| 0+000 | 76.45 | 74.05 | TIE INTO EXISTING WATERMAIN ON SANDHILL RD |
| 0+001.8 | 76.45 | 74.05 | STM CROSSING |
| 0+004.2 | 76.45 | 74.28 | SAN CROSSING |
| 0+012.5 | 76.51 | 73.50 | VALVE AND VALVE BOX |
| 0+016.9 | 76.60 | 73.30 | THRUST BLOCK |
| 0+022.2 | 76.60 | 73.14 | SAN CROSSING |
| 0+024.2 | 76.54 | 73.58 | STM CROSSING |
| 0+025.2 | 76.53 | 73.54 | STM CROSSING |
| 0+035 | 76.60 | 73.60 | TOP OF WATERMAIN |
| 0+045 | 76.60 | 73.80 | TOP OF WATERMAIN |
| 0+052.8 | 76.50 | 74.00 | THRUST BLOCK AND 150mmØ WM CONNECTION |
| 0+053.8 | 76.55 | 74.00 | WM CAPPED |

| WATERMAIN / SEWER CROSSING TABLE | | | | | | | | | | | |
|----------------------------------|----------------|-----------|-------------|-------------|-----------|-------------|-------------|-----------|-------------|-------------------|------|
| LOCATION | SANITARY SEWER | | | STORM SEWER | | | WATERMAIN | | | CLEARANCES | |
| | Invert Elev | Dia. (mm) | Obvert Elev | Invert Elev | Dia. (mm) | Obvert Elev | Invert Elev | Dia. (mm) | Obvert Elev | (mm) | (mm) |
| 1 | 73.46 | 250 | 73.71 | 72.65 | 675 | 73.33 | | | | 130mm (STM Below) | |
| 2 | 73.49 | 250 | 73.74 | 72.39 | 250 | 72.64 | | | | 850mm (STM Below) | |
| 3 | | | | 72.33 | 675 | 73.01 | 73.85 | 200 | 74.05 | 890mm (STM Below) | |
| 4 | 73.58 | 250 | 73.83 | | | | 74.08 | 200 | 74.28 | 250mm (SAN Below) | |
| 5 | 73.55 | 250 | 73.80 | 72.77 | 600 | 73.37 | | | | 180mm (STM Below) | |
| 6 | 73.64 | 200 | 73.84 | | | | 72.94 | 200 | 73.14 | 500mm (WM Below) | |
| 7 | 73.63 | 200 | 73.83 | | | | | | | 170mm (STM Below) | |
| 8 | | | | 72.86 | 600 | 73.46 | | | | 250mm (STM Below) | |
| 9 | | | | 72.86 | 250 | 73.13 | 73.38 | 200 | 73.58 | 250mm (STM Below) | |
| 10 | 73.83 | 200 | 74.03 | 73.00 | 200 | 73.20 | 73.34 | 200 | 73.54 | 250mm (STM Below) | |
| 11 | 74.44 | 200 | 74.64 | 73.03 | 600 | 73.63 | | | | 630mm (STM Below) | |
| | | | | | | | | | | 810mm (STM Below) | |





| LEGEND | |
|-------------------------------------|-------------------------------------|
| SB | STANDARD IRON BAR |
| IB | IRON BAR |
| CB | CATCH BASIN |
| MB | MANHOLE |
| WMH | WATER MANHOLE |
| LS | LAMP STANDARD |
| UP | UTILITY POLE |
| WV | WATER VALVE |
| PH | FIRE HYDRANT |
| W | WELL |
| W&A | GUY WIRE AND ANCHOR |
| W | WATERMAIN |
| UW | OVERHEAD UTILITY WIRES |
| UB | UNDERGROUND HYDRO |
| UB | UNDERGROUND BELL |
| C | CAS MAIN |
| C | CABLE (ROGERS) |
| SL | STREET LIGHT |
| ST | STORM SEWER |
| S | SANITARY SEWER |
| CURB | CURB |
| PROPOSED CURB | PROPOSED CURB |
| PROPOSED WATERMAIN | PROPOSED WATERMAIN |
| PROPOSED SANITARY SEWER | PROPOSED SANITARY SEWER |
| PROPOSED CLAY SEAL AT 60m INTERVALS | PROPOSED CLAY SEAL AT 60m INTERVALS |
| PROPOSED SANITARY MANHOLE | PROPOSED SANITARY MANHOLE |
| PROPOSED STORM MANHOLE | PROPOSED STORM MANHOLE |
| PROPOSED STORM CATCHBASIN | PROPOSED STORM CATCHBASIN |
| PROPOSED STORM CATCHBASIN | PROPOSED STORM CATCHBASIN |
| PROPOSED FIRE HYDRANT | PROPOSED FIRE HYDRANT |
| PROPOSED VALVE & VALVE BOX | PROPOSED VALVE & VALVE BOX |
| PROPOSED SAMESE CONNECTION | PROPOSED SAMESE CONNECTION |
| PROPOSED WATER METER | PROPOSED WATER METER |
| PROPOSED REMOTE WATER METER | PROPOSED REMOTE WATER METER |
| PROPOSED LIGHT STANDARD | PROPOSED LIGHT STANDARD |
| PROPOSED ELEVATION | PROPOSED ELEVATION |
| EXISTING ELEVATION | EXISTING ELEVATION |
| PROPOSED HEAVY DUTY PAVEMENT | PROPOSED HEAVY DUTY PAVEMENT |
| PROPOSED LIGHT DUTY PAVEMENT | PROPOSED LIGHT DUTY PAVEMENT |
| PROPOSED CONCRETE SIDEWALK | PROPOSED CONCRETE SIDEWALK |





LEGEND

| | |
|-------------|-----------------------------------|
| 1/2" = 1'0" | STANDARD IRON BAR |
| 1/4" = 1'0" | IRON BAR |
| 1/8" = 1'0" | CATCH BASIN |
| 1/4" = 1'0" | MANHOLE |
| 1/8" = 1'0" | WATER MANHOLE |
| 1/4" = 1'0" | LAMP STANDARD |
| 1/8" = 1'0" | UTILITY POLE |
| 1/4" = 1'0" | WATER VALVE |
| 1/8" = 1'0" | FIRE HYDRANT |
| 1/4" = 1'0" | WELL |
| 1/8" = 1'0" | GUY WIRE AND ANCHOR |
| 1/4" = 1'0" | WATERMAIN |
| 1/8" = 1'0" | OVERHEAD UTILITY WIRES |
| 1/4" = 1'0" | UNDERGROUND HYDRO |
| 1/8" = 1'0" | UNDERGROUND BELL |
| 1/4" = 1'0" | CABLE (ROGERS) |
| 1/8" = 1'0" | STREET LIGHT |
| 1/4" = 1'0" | STORM SEWER |
| 1/8" = 1'0" | SANITARY SEWER |
| 1/4" = 1'0" | CURB |
| 1/8" = 1'0" | PROPOSED CURB |
| 1/4" = 1'0" | PROPOSED WATERMAIN |
| 1/8" = 1'0" | PROPOSED STORM SEWER |
| 1/4" = 1'0" | PROPOSED SANITARY SEWER |
| 1/8" = 1'0" | PROPOSED SANITARY MANHOLE |
| 1/4" = 1'0" | PROPOSED STORM MANHOLE |
| 1/8" = 1'0" | PROPOSED STORM CATCHBASIN MANHOLE |
| 1/4" = 1'0" | PROPOSED FIRE HYDRANT |
| 1/8" = 1'0" | PROPOSED VALVE & VALVE BOX |
| 1/4" = 1'0" | PROPOSED SIAMSESE CONNECTION |
| 1/8" = 1'0" | PROPOSED WATER METER |
| 1/4" = 1'0" | PROPOSED REMOTE WATER METER |
| 1/8" = 1'0" | PROPOSED HEAVY DUTY PAVEMENT |
| 1/4" = 1'0" | PROPOSED LIGHT DUTY PAVEMENT |
| 1/8" = 1'0" | PROPOSED CONCRETE SIDEWALK |
| 1/4" = 1'0" | TERRACING 3:1 MAX |
| 1/8" = 1'0" | 150mm PERFORATED SUBDRAIN |



APPROVED ☐ REFUSED ☐


THIS _____ DAY OF _____, 20____

DERRICK MOODIE, MANAGER
DEVELOPMENT REVIEW WEST
PLANNING INFRASTRUCTURE AND ECONOMIC
DEVELOPMENT DEPARTMENT, CITY OF OTTAWA

CAUTION
THE POSITION OF ALL POLE LINES,
CONDUITS, WATERMANS, SEWERS AND OTHER
UNDERGROUND AND OVERGROUND UTILITIES
AND STRUCTURES IS NOT NECESSARILY
SHOWN ON THE CONTRACT DRAWINGS, AND
WHERE SHOWN, THE ACCURACY OF THE
POSITION OF SUCH UTILITIES AND
STRUCTURES IS NOT GUARANTEED. BEFORE
STARTING WORK, DETERMINE THE EXACT
LOCATION OF ALL SUCH UTILITIES AND
STRUCTURES AND ASSUME ALL LIABILITY FOR
DAMAGE TO THEM.

PRELIMINARY
NOT FOR CONSTRUCTION

| NO. | REVISION | DESCRIPTION | DATE | BY | APPRO |
|-----|-----------------------------|-------------|------|----|-------|
| 1 | ISSUED FOR SITE APPLICATION | 02/11/18 | AE | AA | |



DESIGNED BY

REVIEWED BY

exp Services Inc.
1111 1111 1111 1111 1111 1111
2800 Queenway Drive, Unit 100
Ottawa, ON K2H 8H6
Canada
www.exp.com
• BUILDINGS • EARTH & ENVIRONMENT • ENERGY •
• INDUSTRIAL • INFRASTRUCTURE • SUSTAINABILITY •

CLIENT
KANATA MUSLIM ASSOCIATION
832 MARCH ROAD, OTTAWA, ON.
K2W 0C9
613.973.5000

DESIGN
AE
CHECKED
AA
GAD
AE
PROJECT MANAGER
AA
APPROVED
AA

PROJECT
KMA MOSQUE AND COMMUNITY CENTRE
351 SANDHILL ROAD, OTTAWA, ON

TITLE
MUNICIPAL SANITARY EXTENSION
PLAN AND PROFILE

PROJECT No.
OTT-00238504-A0

SURVEY
F M & W

DATE
2016-11-12

DRAWING No.
PP

PHASE 1 STORMWATER MANAGEMENT SUMMARY




| Area ID | Area (ha) | Runoff Coefficient 'C' | 2 Year Release (L/s) | 2 Year storage required (m³) | 2 Year underground storage provided (m³) | 100 Year Release (L/s) | 100 Year storage required (m³) | 100 Year surface storage provided (m³) |
|----------------|-------------|------------------------|---------------------------------------------|------------------------------|------------------------------------------|------------------------|--------------------------------|----------------------------------------|
| PH1A | 0.486 | 0.79 | 28.0 | 34.3 | 35.1 | 29.5 | 168.3 | 193.5 |
| PH1B | 0.088 | 0.73 | 11.0 | 0.0 | 0.0 | 17.6 | 12.7 | 25.3 |
| TOTAL | 0.57 | | | | | | | |
| Totals: | | | 39.0 | 34.3 | 35.1 | 47.1 | 180.9 | 218.8 |
| | | | Total Allowable Release (L/s): 48.74 | | | | | |

PH1A - 100 YEAR SURFACE STORAGE VOLUMES

| Ponding Location | Surface Area (m²) | Ponding Depth (m) | Volume (m³) |
|---------------------|-------------------|-------------------|--------------|
| CB102 | 132 | 0.30 | 13.2 |
| CB103 | 368.00 | 0.30 | 36.8 |
| CB104 | 342.00 | 0.30 | 34.2 |
| CB105 | 86.0 | 0.30 | 8.6 |
| CB106 | 82.0 | 0.30 | 8.2 |
| CB107 | 309.0 | 0.30 | 30.9 |
| CB108 | 401.0 | 0.30 | 40.1 |
| CBMH203 | 184 | 0.35 | 21.5 |
| Total Volume | | | 193.5 |

PH1B - 100 YEAR SURFACE STORAGE VOLUMES

| Ponding Location | Surface Area (m²) | Ponding Depth (m) | Volume (m³) |
|---------------------|-------------------|-------------------|-------------|
| CB101 | 217 | 0.35 | 25.3 |
| Total Volume | | | 25.3 |



APPROVED ☐ REFUSED ☐


THIS _____ DAY OF _____, 20____

DERRICK MOODIE, MANAGER
DEVELOPMENT REVIEW WEST
PLANNING INFRASTRUCTURE AND ECONOMIC
DEVELOPMENT DEPARTMENT, CITY OF OTTAWA

CAUTION
THE POSITION OF ALL POLE LINES, CONDUITS, WATERMANS, SEWERS AND OTHER UNDERGROUND AND OVERGROUND UTILITIES AND STRUCTURES IS NOT NECESSARILY SHOWN ON THE CONTRACT DRAWINGS, AND WHERE SHOWN, THE ACCURACY OF THE POSITION OF SUCH UTILITIES AND STRUCTURES IS NOT GUARANTEED. BEFORE STARTING WORK, DETERMINE THE EXACT LOCATION OF ALL SUCH UTILITIES AND STRUCTURES AND ASSUME ALL LIABILITY FOR DAMAGE TO THEM.

PRELIMINARY
NOT FOR CONSTRUCTION

| NO. | REVISION DESCRIPTION | DATE | BY | APPD |
|-----|-------------------------------|----------|----|------|
| 3 | REVISED AS PER CITY COMMENTS | 02/11/18 | AE | AA |
| 2 | ISSUED FOR SITE PLAN APPROVAL | 29/06/18 | AE | AA |
| 1 | ISSUED FOR SITE PLAN APPROVAL | 13/09/17 | ML | AA |




| | | | |
|-------------|------------|---------|---------------------------------|
| DESIGNED BY | ML | PROJECT | KMA MOSQUE AND COMMUNITY CENTRE |
| CHECKED BY | ML | PROJECT | 351 SANDHILL ROAD, OTTAWA, ON |
| DATE | 2016-12-09 | PROJECT | STORMWATER MANAGEMENT PLAN |
| DATE | 2016-12-09 | PROJECT | PHASE 1 |
| DATE | 2016-12-09 | PROJECT | SWM-1 |

URING ALL CONSTRUCTION ACTIVITIES, EROSION AND SEDIMENTATION SHALL BE CONTROLLED BY THE FOLLOWING TECHNIQUES:






























11. EROSION AND SEDIMENT CONTROL MEASURES MAY BE MODIFIED ON-SITE AT THE DISCRETION OF THE CITY OF OTTAWA INSPECTOR OR THE MISSISSIPPI VALLEY CONSERVATION AUTHORITY. CONTRACTOR IS RESPONSIBLE TO INSTALL MODIFICATIONS AS REQUIRED TO THE SATISFACTION OF THE APPROPRIATE AUTHORITIES.
12. IN ACCORDANCE WITH BEST MANAGEMENT PRACTICES FOR EROSION AND SEDIMENT CONTROL, GEOSYNTHETIC SYSTEMS SLOTTASKRIP OR APPROVED EQUIVALENT IS TO BE PLACED INSIDE ALL STORM MANHOLE CATCHBASINS AND CATCHBASINS. INSTALLATION, INSPECTION AND CLEANOUT ARE AS PER MANUFACTURER'S RECOMMENDATIONS.



1. POSTS TO BE SPACED AT 2.3 METRES CENTRE TO CENTRE.
2. WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN EACH OTHER THEY SHALL BE OVERLAPPED BY A MINIMUM OF 500mm.
3. MAINTENANCE SHALL BE PERFORMED AS NEEDED AND MATERIAL REMOVED WHEN "BULGES" DEVELOP IN THE SILT FENCE.
4. WOOD POSTS TO BE HARDWOOD TYPE (50mm x 50mm).
5. GEOTEXTILE TO BE EMBEDDED 200 mm INTO GROUND.
6. GEOTEXTILE TO CONFORM TO OPSS 805 STANDARDS.
7. SILT FENCE MUST BE INSTALLED BEFORE COMMENCEMENT OF CONSTRUCTION AND IN ACCORDANCE WITH DETAIL. SILT FENCE CAN BE REMOVED AFTER LANDSCAPING IS COMPLETE.
8. SEDIMENTS MUST BE CLEARED AWAY WHEN THEY REACH HALF THE HEIGHT OF THE FENCE.




LEGEND

-  -- STANDARD IRON BAR
 -- IRON BAR
 -- CATCH BASIN
 -- MANHOLE
 -- WATER MANHOLE
 -- LAMP STANDARD
 -- UTILITY POLE
 -- WATER VALVE
 -- FIRE HYDRANT
 -- WELL
 -- GUY WIRE AND ANCHOR
 -- WATER MAIN
 -- OVERHEAD UTILITY WIRES
 -- UNDERGROUND HYDRO
 -- UNDERGROUND BELL
 -- GAS MAIN
 -- CABLE (ROGERS)
 -- STREET LIGHT
 -- STORM SEWER
 -- SANITARY SEWER
 -- CURB
 -- PROPOSED CURB
 -- PROPOSED STORM SEWER
 -- PROPOSED STORM MANHOLE
 -- PROPOSED STORM CATCHBASIN MANHOLE
 -- PROPOSED LIGHT STANDARD
 -- PROPOSED ELEVATION
 -- EXISTING ELEVATION
 -- PROPOSED SILT FENCE

CAUTION
THE POSITION OF ALL POLE LINES, CONDUITS, WATERMAINS, SEWERS AND OTHER UNDERGROUND AND OVERGROUND UTILITIES AND STRUCTURES IS NOT NECESSARILY SHOWN ON THE CONTRACT DRAWINGS, AND WHERE SHOWN, THE ACCURACY OF THE POSITION OF SUCH UTILITIES AND STRUCTURES IS NOT GUARANTEED. BEFORE STARTING WORK, DETERMINE THE EXACT LOCATION OF ALL SUCH UTILITIES AND STRUCTURES AND ASSUME ALL LIABILITY FOR DAMAGE TO THEM.

PRELIMINARY
NOT FOR CONSTRUCTION

| 3 | REVISED AS PER CITY COMMENTS | 02/11/18 | AE | AA | | | | | |
|-----|-------------------------------|----------|----|------|--|--|--|--|--|
| 2 | ISSUED FOR SITE PLAN APPROVAL | 29/06/18 | AE | AA | | | | | |
| 1 | ISSUED FOR SITE PLAN APPROVAL | 13/09/17 | ML | AA | | | | | |
| NO. | REVISION DESCRIPTION | DATE | BY | APPD | | | | | |



DESIGNED BY

REVIEWED BY



CLIENT **KANATA MUSLIM ASSOCIATION**
832 MARCH ROAD, OTTAWA, ON.
K2W DC9
613.973.5000



| | |
|-----------------------|----------------------------------------------------------------------------------------|
| BASEPLAN ML | PROJECT KMA MOSQUE AND COMMUNITY CENTRE 351 SANDHILL ROAD, OTTAWA, ON |
| DESIGN ML | |
| CHECKED AA | |
| CAD ML | TITLE |
| PROJECT MANAGER AA | EROSION & SEDIMENT CONTROL PLAN PHASE 1 |

| | |
|-------------|-----------------|
| PROJECT No. | OTT-00238504-A0 |
| SURVEY | F M & W |
| DATE | 201B-12-09 |
| DRAWING No. | ESCP-1 |

GENERAL NOTES





- CONTRACTOR IS RESPONSIBLE FOR ALL LAYOUT FOR CONSTRUCTION.
- ALL ELEVATIONS ARE GEODETIC AND UTILIZE METRIC UNITS.
- JOB BENCH MARK - CONFIRM WITH exp SERVICES INC. PRIOR TO UTILIZATION.
- ALL DIMENSIONS ARE IN METERS UNLESS OTHERWISE STATED. ALL DRAWINGS SHOULD NOT BE SCALED BY THE CONTRACTOR. ANY MISSING OR QUESTIONABLE DIMENSIONS ARE TO BE CONFIRMED WITH THE CONSULTANT IN WRITING.
- CONSTRUCTION SHALL BE IN ACCORDANCE WITH CITY OF OTTAWA AND ONTARIO PROVINCIAL STANDARD DRAWING SUPPLEMENTS WHERE APPLICABLE AND ONTARIO PROVINCIAL STANDARDS SHALL APPLY WHERE NO CITY STANDARDS ARE AVAILABLE.
- ANY DISCREPANCIES, INTERPRETATIONS, CHANGES AND ADDITIONS TO THESE DRAWINGS MUST BE BROUGHT TO THE ATTENTION OF THE ENGINEER, WHEN NOTED AND BEFORE PROCEEDING WITH CONSTRUCTION WORKS.
- REFER TO ARCHITECT'S SITE PLAN FOR BUILDING DIMENSIONS AND SITE LAYOUT. DIMENSIONS AND LAYOUT INFORMATION SHALL BE CONFIRMED PRIOR TO COMMENCEMENT OF CONSTRUCTION.
- REFER TO THE LANDSCAPE ARCHITECT'S PLAN FOR SIDEWALK, PATHWAYS, PLANTING AND OTHER LANDSCAPE FEATURE MATERIALS AND LOCATIONS.
- FOR GEOTECHNICAL INFORMATION REFER TO THE GEOTECHNICAL INVESTIGATION REPORT PREPARED BY PATERSON GROUP DATED NOVEMBER 2018.
- ALL DISTURBED AREAS TO BE REINSTATED TO EQUAL OR BETTER CONDITION. ALL NEW WORK SHALL TIE INTO EXISTING.
- ALL GROUND SURFACES SHALL BE EVENLY GRADED WITHOUT PONDING AREAS AND WITHOUT LOW POINTS EXCEPT WHERE APPROVED SWALE OR CATCHBASIN OUTLETS ARE PROVIDED.
- ALL EDGES OF DISTURBED PAVEMENT SHALL BE SAWCUT TO FORM A NEAT AND STRAIGHT LINE PRIOR TO PLACING NEW PAVEMENT.
- CONTRACTOR IS TO COMPLY WITH THE CITY OF OTTAWA REQUIREMENTS FOR TRAFFIC CONTROL WHEN WORKING ON CITY STREETS.
- ALL MATERIAL SUPPLIED AND PLACED FOR PARKING LOT AND ACCESS ROAD CONSTRUCTION SHALL BE TO CITY OF OTTAWA OPSS STANDARDS AND SPECIFICATIONS UNLESS OTHERWISE NOTED (CONSTRUCTION OPSS 206, 310 & 314 MATERIALS OPSS 1001, 1003 & 1010).

- THE CONTRACTOR SHALL CONFIRM LOCATIONS AND ELEVATIONS OF EXISTING SERVICES AND STRUCTURES TO BE CONNECTED TO AND EXISTING SERVICES THAT MAY BE DAMAGED OR CAUSE CONFLICTS PRIOR TO CONSTRUCTION OF ANY NEW SEWER, WATER AND/OR STORM WATER WORKS. THE ENGINEER SHALL BE INFORMED IMMEDIATELY OF ANY ERRORS, DISCREPANCIES, CONFLICTS, OMISSIONS etc THAT ARE FOUND. DO NOT CONTINUE CONSTRUCTION IN AREAS WHERE DISCREPANCIES APPEAR UNTIL SUCH DISCREPANCIES HAVE BEEN RESOLVED.
- THE CONTRACTOR SHALL PROTECT ANY SUCH EXISTING SERVICES & FACILITIES. SUCH REQUIRED MEASURES INCLUDE, BUT ARE NOT LIMITED TO: ENSURE ALL CONCERNED UTILITIES HAVE LOCATED THEIR PLANT PRIOR TO ANY EXCAVATING, LOCATE AND FLAG/PAINT THE LOCATIONS OF OTHER U/G PLANT WHICH MIGHT BE DAMAGED BY EXCAVATION AND CONSTRUCTION TRAFFIC, HAND DIG IN PROXIMITY TO EXISTING BURIED SERVICES TO LOCATE THEM WITHOUT ANY RESULTING DAMAGE, BRIDE AND SUPPORT WHERE REQUIRED.
- THE CONTRACTOR SHALL IMPLEMENT BEST MANAGEMENT PRACTICES FOR THE PROTECTION OF THE AREA'S DRAINAGE SYSTEM AND THE RECEIVING WATERCOURSE DURING CONSTRUCTION ACTIVITIES. THIS INCLUDES LIMITING THE AMOUNT OF EXPOSED SOIL, USING FILTER CLOTH UNDER GRATES OF CATCHBASINS AND MANHOLES AND INSTALLING SILT FENCES AND OTHER EFFECTIVE SEDIMENT TRAPS. THE CONTRACTOR ACKNOWLEDGES THAT FAILURE TO IMPLEMENT APPROPRIATE EROSION AND SEDIMENT CONTROL MEASURES MAY BE SUBJECT TO PENALTIES IMPOSED BY ANY APPLICABLE REGULATORY AGENCY.
- DESIGN ELEVATIONS GIVEN ON THESE PLANS ARE TO BE ADHERED TO WITH NO CHANGES WITHOUT PRIOR WRITTEN APPROVAL BY exp SERVICES INC. SURFACE PONDING STORAGE VOLUMES AND INLET CONTROL DEVICE DIMENSIONS MUST COMPLY WITH THE DESIGN REPORT PREPARED BY exp SERVICES INC FOR THIS PROJECT.
- THE CONTRACTOR IS RESPONSIBLE FOR AND SHALL PROVIDE FOR DEMATERING, SUPPORT AND PROTECTION OF EXCAVATIONS AND TRENCHING AS WELL AS RELEASE OF ANY PUMPED GROUND WATER IN A CONTROLLED AND APPROVED MANNER. THE CONTRACTOR SHALL APPLY FOR A PERMIT TO TAKE WATER FROM THE MINISTRY OF ENVIRONMENT IF MORE THAN 50,000 LITRES PER/DAY OF GROUNDWATER IS PUMPED FOR CONSTRUCTION ACTIVITIES.
- FOR TOPOGRAPHICAL INFORMATION REFER TO PLAN PREPARED BY FAIRHALL MOFFATT & WOODLAND LTD. FOR LEGAL PROPERTY LINE DESCRIPTIONS.
- CITY INSPECTOR IS TO NOTIFIED OF ANY WORKS IN THE ROW WITH SUFFICIENT NOTICE.
- CLAY SEAL TO BE AS PER OPSD 802.095.

- SHOULD ANY CONDITIONS AT THE SITE BE ENCOUNTERED WHICH DIFFER FROM THE TEST LOCATIONS IDENTIFIED IN THE GEOTECHNICAL REPORT, PATERSON'S GEOTECHNICAL ENGINEER IS TO BE NOTIFIED IMMEDIATELY IN ORDER TO PERMIT REASSESSMENT OF THE GEOTECHNICAL RECOMMENDATIONS.

ROADWAYS & CURBS

- ASPHALT REINSTATEMENT AS PER CITY OF OTTAWA STANDARD DRAWING R10.
- CURBS TO BE CONCRETE BARRIER CURBS AS PER CITY OF OTTAWA STANDARD DRAWING SC1.1.
- THE CONTRACTOR SHALL COMPLETE ALL RESTORATION WITHIN CITY ROW'S TO A CONDITION EQUAL TO ORIGINAL OR BETTER AND TO THE SATISFACTION OF THE MUNICIPAL AUTHORITIES.
- THE EXISTING PRIVATE APPROACH IS TO BE REMOVED AS PART OF PHASE 2 WORK. RIGHT-OF-WAY TO BE REINSTATED TO THE SATISFACTION OF THE CITY OF OTTAWA.




WATERMAIN

1. ALL WATERMAIN AND WATER SERVICE MATERIALS AND INSTALLATION SHALL CONFORM TO THE CURRENT CITY OF OTTAWA STANDARD DRAWINGS AND SPECIFICATIONS.
2. ALL WATERMAIN TO BE INSTALLED AT MINIMUM COVER OF 2.4m. THERMAL INSULATION SHALL BE INSTALLED WHERE ADEQUATE SEPARATION CANNOT BE ACHIEVED AS PER CITY STANDARD W21, W22 AND W23.
3. ALL WATERMAIN WORK AND MATERIAL SHALL BE IN ACCORDANCE WITH CITY OF OTTAWA STANDARDS. NO WORK SHALL COMMENCE UNLESS A CITY WATER WORKS INSPECTOR IS ON SITE. WATERMAIN CONNECTIONS BY CITY OF OTTAWA FORCES WITH ALL EXCAVATION BACKFILL AND ROAD REINSTATEMENT BY CONTRACTOR.
4. WATERMAIN IS TO BE PVC DR18 WITH TRACER WIRE AS PER CITY OF OTTAWA STANDARD W38 UNLESS OTHERWISE NOTED.
5. VALVE BOXES AS PER CITY OF OTTAWA DETAIL W24.
6. ALL FIRE HYDRANTS TO BE INSTALLED AS PER CITY STANDARD W19 AND LOCATED AS PER CITY STANDARD W19 AND/OR CITY STANDARD CROSS SECTIONS.
7. WATERMAIN BEDDING IS TO BE AS PER CITY OF OTTAWA DETAIL W17.
8. THRUST BLOCKS AND RESTRAINT AS PER CITY OF OTTAWA DWGS: W25.3, W25.4, W25.5 AND W25.6.
9. CATHODIC PROTECTION REQUIRED FOR ALL IRON FITTINGS PER CITY OF OTTAWA DWGS: W39, W40, W41.
10. IF WATERMAIN MUST BE DEFLECTED TO MEET ALIGNMENT, ENSURE THAT THE AMOUNT OF DEFLECTION USED IS LESS THAN HALF THAT RECOMMENDED BY THE MANUFACTURER.
11. DISINFECTION AND TESTING OF WATERMAIN TO BE IN ACCORDANCE WITH CITY OF OTTAWA STANDARDS.


STORM AND SANITARY SEWERS

1. SANITARY AND STORM SEWER MATERIALS AND INSTALLATION SHALL CONFORM TO THE CURRENT CITY OF OTTAWA STANDARD DRAWINGS AND SPECIFICATIONS AND CPSS 407 AND 410.
2. SEWER BEDDING AS PER CITY STANDARD S6 & S7.
3. ALL SANITARY SEWERS ARE TO BE THE SIZES INDICATED AND THE MATERIAL SHALL BE PVC SDR35.
4. ALL STORM SEWERS ARE TO BE THE SIZES INDICATED AND THE MATERIAL SHALL BE PVC SDR35 OR REINFORCED CONCRETE IN ACCORDANCE WITH CSA STANDARDS A257.2 AND A257.3 (JOINTS).
5. ALL MANHOLES, CATCHBASINS AND CATCHBASIN MANHOLES TO BE BACKFILLED WITH MIN. 0.3m HORIZONTAL THICKNESS GRANULAR 'A'.
6. SUPPLY AND INSTALL ALL PIPING AND APPURTENANCES AS SHOWN TO WITHIN 1.0m OF BUILDING WALLS AND PROVIDE TEMPORARY CAPS.
7. THE CONTRACTOR SHALL CONDUCT INFILTRATION/EXFILTRATION (AS PER CURRENT CPSS) TESTING ON ALL NEWLY INSTALLED SANITARY SEWERS. THE TEST SHALL BE PERFORMED IMMEDIATELY AFTER SEWER INSTALLATION AND SUPERVISED BY THE ENGINEER.
8. THE CONTRACTOR SHALL CONDUCT CCTV INSPECTION OF ALL NEWLY INSTALLED STORM AND SANITARY SEWERS AND EXISTING SEWERS CONNECTED TO THE TEST SHALL BE PERFORMED IMMEDIATELY AFTER SEWERS INSTALLED AND SUPERVISED BY THE ENGINEER.
9. ALL SERVICE CONNECTIONS TO BE CONSTRUCTED AS PER CITY STANDARD S11 & S11.1.
10. ALL SANITARY BUILDING DRAINS TO BE EQUIPPED WITH SANITARY BACKWATER VALVES INSTALLED PER CITY OF OTTAWA STANDARD DRAWING S14.1.
11. MINIMUM SOIL COVER TO BE 2.0m TO PROTECT SEWERS FROM FROST DAMAGE. IN AREAS WHERE ADEQUATE COVER CANNOT BE ACHIEVED, THERMAL INSULATION TO BE INSTALLED AS PER CPSS 514.010.

| WATERMAIN TABLE | | | |
|-----------------|-----------|-----------|------------------------------------------|
| STATION | FIN/GRADE | T/W GRADE | COMMENT |
| 0+003.5 | 76.65 | 74.25 | TIE INTO EXISTING WATERMAIN PHASE 1 STUB |
| 0+010 | 76.63 | 74.23 | TOP OF WATERMAIN |
| 0+021.5 | 76.70 | 74.30 | THRUST BLOCK |
| 0+026.1 | 76.72 | 74.32 | THRUST BLOCK |
| 0+030.6 | 76.90 | 74.50 | WM CAPPED |



| LEGEND | |
|--------|-----------------------------------|
| | STANDARD IRON BAR |
| | CATCH BASIN |
| | MANHOLE |
| | WATER MANHOLE |
| | LAMP STANDARD |
| | UTILITY POLE |
| | WATER VALVE |
| | FIRE HYDRANT |
| | WELL |
| | GUY WIRE AND ANCHOR |
| | WATERMAIN |
| | OVERHEAD UTILITY WIRES |
| | UNDERGROUND HYDRO |
| | UNDERGROUND BELL |
| | GAS MAIN |
| | CABLE (ROGERS) |
| | STREET LIGHT |
| | STORM SEWER |
| | SANITARY SEWER |
| | CURB |
| | PROPOSED CURB |
| | PROPOSED WATERMAIN |
| | PROPOSED STORM SEWER |
| | PROPOSED SANITARY SEWER |
| | PROPOSED SANITARY MANHOLE |
| | PROPOSED STORM MANHOLE |
| | PROPOSED STORM CATCHBASIN MANHOLE |
| | PROPOSED FIRE HYDRANT |
| | PROPOSED VALVE & VALVE BOX |
| | PROPOSED SIAMESE CONNECTION |
| | PROPOSED REMOTE WATER METER |
| | PROPOSED LIGHT STANDARD |
| | PROPOSED ELEVATION |
| | EXISTING ELEVATION |
| | PROPOSED HEAVY DUTY PAVEMENT |
| | PROPOSED LIGHT DUTY PAVEMENT |
| | PROPOSED CONCRETE SIDEWALK |



PHASE 2 STORMWATER MANAGEMENT SUMMARY

| Area ID | Area (ha) | Runoff Coefficient 'C' | 2 Year Release (L/s) | 2 Year storage required (m³) | 2 Year underground storage provided (m³) | 100 Year Release (L/s) | 100 Year storage required (m³) | 100 Year surface storage provided (m³) |
|-----------------------------|-----------|------------------------|----------------------|------------------------------|------------------------------------------|------------------------|--------------------------------|----------------------------------------|
| PH2A | 0.498 | 0.78 | 28.0 | 35.1 | 35.1 | 29.5 | 173.3 | 193.5 |
| PH2B | 0.118 | 0.77 | 15.6 | 0.0 | 0.0 | 17.6 | 24.9 | 25.3 |
| PH2C | 0.145 | 0.90 | 7.0 | 13.9 | 57.0 | 10.0 | 48.7 | 57.0 |
| PH2D | 0.045 | 0.46 | 3.5 | 0.0 | 0.0 | 10.2 | 0.0 | 0.0 |
| TOTAL | 0.81 | | | | | | | |
| Totals: | | | 54.2 | 49.0 | 92.1 | 67.4 | 246.8 | 275.8 |
| Total Allowable Release L/s | | | 68.55 | | | | | |

PH2A - 100 YEAR SURFACE STORAGE VOLUMES




| Ponding Location | Surface Area (m²) | Ponding Depth (m) | Volume (m³) |
|------------------|-------------------|-------------------|-------------|
| CB102 | 132 | 0.30 | 13.2 |
| CB103 | 368.00 | 0.30 | 39.8 |
| CB104 | 342.00 | 0.30 | 34.2 |
| CB105 | 86.0 | 0.30 | 8.6 |
| CB106 | 82.0 | 0.30 | 8.2 |
| CB107 | 309.0 | 0.30 | 30.9 |
| CB108 | 401.0 | 0.30 | 40.1 |
| CBMH203 | 184 | 0.35 | 21.5 |
| Total Volume | | | 193.5 |

PH2B - 100 YEAR SURFACE STORAGE VOLUMES

| Ponding Location | Surface Area (m²) | Ponding Depth (m) | Volume (m³) |
|------------------|-------------------|-------------------|-------------|
| CB101 | 217 | 0.35 | 25.3 |
| Total Volume | | | 25.3 |

PH2C - 100 YEAR SURFACE STORAGE VOLUMES



| Ponding Location | Surface Area (m²) | Ponding Depth (m) | Volume (m³) |
|------------------|-------------------|-------------------|-------------|
| Roof | 1140 | 0.15 | 57 |
| Total Volume | | | 57.0 |



CAUTION
THE POSITION OF ALL POLE LINES, CONDUITS, WATERMANS, SEWERS AND OTHER UNDERGROUND AND OVERGROUND UTILITIES AND STRUCTURES IS NOT NECESSARILY SHOWN ON THE CONTRACT DRAWINGS, AND WHERE SHOWN, THE ACCURACY OF THE POSITION OF SUCH UTILITIES AND STRUCTURES IS NOT GUARANTEED. BEFORE STARTING WORK, DETERMINE THE EXACT LOCATION OF ALL SUCH UTILITIES AND STRUCTURES AND ASSUME ALL LIABILITY FOR DAMAGE TO THEM.

PRELIMINARY
NOT FOR CONSTRUCTION

| NO. | REVISION DESCRIPTION | DATE | BY | APPD |
|-----|-------------------------------|----------|----|------|
| 3 | REVISED AS PER CITY COMMENTS | 02/11/18 | AE | AA |
| 2 | ISSUED FOR SITE PLAN APPROVAL | 29/06/18 | AE | AA |
| 1 | ISSUED FOR SITE PLAN APPROVAL | 13/09/17 | ML | AA |



KANATA MUSLIM ASSOCIATION
832 MARCH ROAD, OTTAWA, ON.
K2W 0C9
613.973.5000

exp.

exp. Services Inc.
1-877-888-1888 (Toll Free)
2880 Queen Mary Drive, Unit 100
Ottawa, ON K2M 0K6
Canada
www.exp.ca
• BUILDINGS • EARTH & ENVIRONMENT • ENERGY •
• INDUSTRIAL • INFRASTRUCTURE • SUSTAINABILITY •

| DESIGN | ML | PROJECT | KMA MOSQUE AND COMMUNITY CENTRE | PROJECT No. | OTT-00238504-AD |
|-----------------|----|---------|---------------------------------|-------------|-----------------|
| CHECKED | AA | DATE | 2018-12-09 | SURVEY | F M & W |
| CAD | ML | TITLE | STORMWATER MANAGEMENT PLAN | DRAWING No. | SWM-2 |
| PROJECT MANAGER | AA | | PHASE 2 | | |
| APPROVED | AA | | | | |


APPROVED ☐ REFUSED ☐
THIS _____ DAY OF _____, 20____
DERRICK MOODIE, MANAGER
DEVELOPMENT REVIEW WEST
PLANNING INFRASTRUCTURE AND ECONOMIC
DEVELOPMENT DEPARTMENT, CITY OF OTTAWA

EROSION AND SEDIMENT CONTROLS DURING CONSTRUCTION

DURING ALL CONSTRUCTION ACTIVITIES, EROSION AND SEDIMENTATION SHALL BE CONTROLLED BY THE FOLLOWING TECHNIQUES:




1. LIMITING THE EXTENT OF EXPOSED SOILS AT ANY GIVEN TIME.
2. RE-VEGETATION OF EXPOSED AREAS AS SOON AS POSSIBLE.
3. MINIMIZING THE AREA TO BE CLEARED AND DISRUPTION TO ADJACENT AREAS.
4. A SILT FENCE BARRIER (OPSD 219.110) TO BE INSTALLED AS SHOWN ON THIS DRAWING.
5. A VISUAL INSPECTION SHALL BE COMPLETED DAILY ON SEDIMENT CONTROL BARRIERS AND ANY DAMAGE REPAIRED IMMEDIATELY. CARE WILL BE TAKEN TO PREVENT DAMAGE DURING CONSTRUCTION OPERATIONS.
6. IN SOME CASES SOME BARRIERS MAY BE REMOVED TEMPORARILY TO ACCOMMODATE THE CONSTRUCTION OPERATIONS. THE AFFECTED BARRIERS WILL BE REINSTATED AT NIGHT WHEN CONSTRUCTION IS COMPLETED.
7. THE SEDIMENT CONTROL DEVICES WILL BE CLEANED OF ACCUMULATED SILT AS REQUIRED. THE DEPOSITS WILL BE DISPOSED OF AS PER THE REQUIREMENTS OF THE CONTRACT.
8. DURING THE COURSE OF CONSTRUCTION IF THE ENGINEER BELIEVES THAT ADDITIONAL PREVENTION METHODS ARE REQUIRED TO CONTROL EROSION AND SEDIMENTATION, THE CONTRACTOR WILL INSTALL ADDITIONAL SILT FENCES OR OTHER METHODS AS REQUIRED TO THE SATISFACTION OF THE ENGINEER.
9. CONSTRUCTION AND MAINTENANCE REQUIREMENTS FOR EROSION AND SEDIMENT CONTROLS TO COMPLY WITH ONTARIO PROVINCIAL STANDARD SPECIFICATION (OPSS) OPSS 805, AND CITY OF OTTAWA SPECIFICATIONS.
10. MUD MAT TO BE LOCATED AT THE CONSTRUCTION ENTRANCE, AS INDICATED ON THE PLAN, AND SHALL CONSIST OF 50mm CRUSHER RUN CLEAR STONE 300mm DEEP TO PREVENT MUD TRACKING ON TO MUNICIPAL ROADS. THE ENTRANCE SHALL BE MAINTAINED IN CLEAN CONDITION THROUGHOUT THE CONSTRUCTION PERIOD.

11. EROSION AND SEDIMENT CONTROL MEASURES MAY BE MODIFIED ON-SITE AT THE DISCRETION OF THE CITY OF OTTAWA INSPECTOR OR THE MISSISSIPPI VALLEY CONSERVATION AUTHORITY. CONTRACTOR IS RESPONSIBLE TO INSTALL MODIFICATIONS AS REQUIRED TO THE SATISFACTION OF THE APPROPRIATE AUTHORITIES.
12. IN ACCORDANCE WITH BEST MANAGEMENT PRACTICES FOR EROSION AND SEDIMENT CONTROL, GEOSYNTHETIC SYSTEMS SILTSCREEN OR APPROVED EQUIVALENT IS TO BE PLACED INSIDE ALL STORM MANHOLE CATCHBASINS AND CATCHBASINS. INSTALLATION, INSPECTION AND CLEANOUT ARE AS PER MANUFACTURER'S RECOMMENDATIONS.



SILT FENCE NOTES:

1. POSTS TO BE SPACED AT 2.3 METRES CENTRE TO CENTRE.
2. WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN EACH OTHER THEY SHALL BE OVERLAPPED BY A MINIMUM OF 500mm.
3. MAINTENANCE SHALL BE PERFORMED AS NEEDED AND MATERIAL REMOVED WHEN "BULGES" DEVELOP IN THE SILT FENCE.
4. WOOD POSTS TO BE HARDWOOD TYPE (50mm x 50mm).
5. GEOTEXTILE TO BE EMBEDDED 200 mm INTO GROUND.
6. GEOTEXTILE TO CONFORM TO OPSS 805 STANDARDS.
7. SILT FENCE MUST BE INSTALLED BEFORE COMMENCEMENT OF CONSTRUCTION AND IN ACCORDANCE WITH DETAIL. SILT FENCE CAN BE REMOVED AFTER LANDSCAPING IS COMPLETE.
8. SEDIMENTS MUST BE CLEARED AWAY WHEN THEY REACH HALF THE HEIGHT OF THE FENCE.



APPROVED ☐ REFUSED ☐
THIS _____ DAY OF _____, 20____
DERRICK MOODIE, MANAGER
DEVELOPMENT REVIEW WEST
PLANNING INFRASTRUCTURE AND ECONOMIC
DEVELOPMENT DEPARTMENT, CITY OF OTTAWA

CAUTION
THE POSITION OF ALL POLE LINES, CONDUITS, WATERMANS, SEWERS AND OTHER UNDERGROUND AND OVERGROUND UTILITIES AND STRUCTURES IS NOT NECESSARILY SHOWN ON THE CONTRACT DRAWINGS, AND WHERE SHOWN, THE ACCURACY OF THE POSITION OF SUCH UTILITIES AND STRUCTURES IS NOT GUARANTEED. BEFORE STARTING WORK, DETERMINE THE EXACT LOCATION OF ALL SUCH UTILITIES AND STRUCTURES AND ASSUME ALL LIABILITY FOR DAMAGE TO THEM.

PRELIMINARY
NOT FOR CONSTRUCTION

| NO. | REVISION DESCRIPTION | DATE | BY | APPD |
|-----|-------------------------------|----------|----|------|
| 3 | REVISED AS PER CITY COMMENTS | 02/11/18 | AE | AA |
| 2 | ISSUED FOR SITE PLAN APPROVAL | 29/06/18 | AE | AA |
| 1 | ISSUED FOR SITE PLAN APPROVAL | 13/09/17 | ML | AA |

DESIGNED BY
REVIEWED BY
CLIENT
KANA MUSLIM ASSOCIATION
832 MARCH ROAD, OTTAWA, ON.
K2W 0C9
613.973.5000

exp. Services Inc.
2000 Queen Mary Drive, Unit 100
Ottawa, ON K2M 0K6
Canada
• BUILDINGS • EARTH & ENVIRONMENT • ENERGY •
• INDUSTRIAL • INFRASTRUCTURE • SUSTAINABILITY •

| PROJECT | ML |
|-----------------|----|
| DESIGN | ML |
| CHECKED | AA |
| CAD | ML |
| PROJECT MANAGER | AA |
| APPROVED | AA |

PROJECT No. OTT-00238504-AD
SURVEY F M & W
DATE 2018-12-09
DRAWING No. ESCP-2