



SITE DESCRIPTION:

THE SITE INCLUDES AN EXISTING 2-STORY OFFICE BUILDING WITH ASPHALT ACCESS DRIVE AND PARKING AREAS AND UNIT PAVED PATHWAYS. THE ENTRANCE AREAS AND PERIMETER OF THE EXISTING BUILDING ARE MAINTAINED AS MOWN GRASS LAWNS WITH MATURE CONIFERS WITH PERIMETER AREAS OF UNMAINTAINED WOODLOT TO THE WEST AND SOUTH OF THE SITE. THE SITE IS GENERALLY FLAT WITH A SHORT BANK ALONG THE SOUTHERN BOUNDARY AT AKERSON ROAD AND THE ASPHALT MUP.

THE SOUTHERN BOUNDARY OF THE SITE IS BORDERED BY A 5-8m WIDE STRIP OF MOWN GRASS BETWEEN THE WOODLOT EDGE AND EXISTING MULTI-USE PATHWAY.

THE SURROUNDING DEVELOPMENT INCLUDES A MIX OF COMMERCIAL AND RESIDENTIAL DEVELOPMENT TO THE NORTH AND EAST ALONG EAGLESON ROAD WITH RESIDENTIAL DEVELOPMENT AND KRISTINA KISS PARK EXTENDING TO THE WEST. THE ADJACENT LOT TO THE EAST (10 COPE DR.) IS A PROPOSED COMMERCIAL DEVELOPMENT BY OTHERS.

THE SITE IS NOT CONSIDERED OF PRIMARY OR SUPPORTING SIGNIFICANCE AS NATURAL LANDS IN THE GREENSPACE MASTER PLAN.

GENERAL NOTES:


CURRENT SITE BOUNDARY / AREA IS 20,699m2. THIS DEVELOPMENT PROPOSES THE FOLLOWING:

- EXISTING CONDITIONS
- APPROXIMATELY 1,394m2 OF EXISTING BUILDING
 - APPROXIMATELY 6,936m2 OF EXISTING HARD / NON-PERMEABLE PAVING

- PROPOSED DEVELOPMENT
- APPROXIMATELY 1,455m2 OF NEW BUILDING
 - APPROXIMATELY 5,169m2 OF NEW HARD / NON-PERMEABLE PAVING

- DEVELOPMENT TOTALS
- APPROXIMATELY 2,849m2 TOTAL BUILDING AREA
 - APPROXIMATELY 9,421m2 TOTAL HARD / NON-PERMEABLE PAVING
 - PLANTING OF 60 NEW DECIDUOUS TREES
 - PLANTING OF 40 NEW CONIFEROUS TREES

THE PROPOSED DEVELOPMENT REQUIRES THE REMOVAL OF APPROX. 6135m2 WOODLOT. THE LOCATION FOR NEW TREE PLANTING HAS BEEN DETERMINED TO ALLOW FOR MAXIMUM SOIL VOLUMES AND MINIMAL CONFLICTS TO ALLOW FOR THE ESTABLISHMENT OF LARGE MATURE TREES TO OVER A LONG PERIOD OF TIME.



VEGETATION AREAS:

AREA A: (APPROX. 8,460 m²)

SPECIES DISTRIBUTION:

THERE IS EVIDENCE (GOOGLE EARTH, AND REMAINING DEAD TREES AND STUMPS) THAT THE ORIGINAL WOODLOT INCLUDED APPROX 40% FRAXINUS SPECIES (ASH) THAT HAVE RECENTLY DIED AND/OR BEEN REMOVED. THE REMAINING SPECIES DISTRIBUTION IS AS FOLLOWS:

- 60% ACER NEGUNDO (MANITOBA MAPLE)
- 20% POPULUS SPECIES (POPLAR)
- 10% ACER SACCHARINUM (SILVER MAPLE)
- 10% SALIX SPECIES (WILLOW)
- <5% PINUS RESINOSA (RED PINE)
- <5% PICEA GLAUCA (WHITE SPRUCE)

SIZE AND DENSITY: THE SILVER MAPLES AND WILLOW TREES ARE THE LARGEST TREES IN THIS AREA GENERALLY RANGING 40-80cm IN DIAMETER WITH THE MAPLES HAVING CO-DOMINANT STEMS FROM THE BASE. TREE OCCURRENCE IS NOT EVENLY SPACED AS THERE IS EVIDENCE THAT A LARGE NUMBER OF TREES WITHIN THE WOODLOT HAVE DIED/BEN REMOVED. THE SILVER MAPLE ARE GENERALLY IN THE NORTHWEST CORNER OF THE AREA.

THE UNDERSTORY GROWTH IS THICK WITH PREDOMINANTLY MANOTIBA MAPLE SAPPLINGS.

TREE #	BOTANICAL NAME	COMMON NAME	CALIPER (cm)	CONDITION	HIGH QUALITY TREE	RARE TREE	COMMENTS	TO BE PRE-SERVED
1	Picea glauca	White Spruce	22	Good	No	No	Co-dominant stem at 4m, some die back & thinner branches on bldg. side	Yes
2	Picea glauca	White Spruce	20	Good	No	No	Some die back and thinner branches on west side of tree.	Yes
3	Picea pungens	Colorado spruce	18	Good	No	No	Some die back and thinner branches on west side of tree.	Yes
4	Picea pungens	Colorado spruce	17	Good	No	No	Some die back on lower branches.	Yes
5	Picea pungens	Colorado spruce	16	Good	No	No	Some die back on lower branches.	Yes
6	Picea pungens	Colorado spruce	18	Mod./Good	No	No	Significant die back on lower branches due to shrub growth at ground level.	Yes
7	Malus species	Crabapple	15	Moderate	No	No	Some die back on lower branches	No
8	Malus species	Crabapple	12	Mod./ Poor	No	No	Slight lean, some die back in crown	No
9	Malus species	Crabapple	15	Poor	No	No	Significant lean, significant die back, split in trunk	No
10	Pinus resinosa	Red pine	25	Good	No	No	Co-dom. stem at 10m, die back lower branches due to shrub growth below	Yes
11	Pinus resinosa	Red pine	18	Good	No	No	Die back lower branches due to shrub growth below	Yes
12	Picea pungens	Colorado spruce	22	Good	No	No	Die back lower branches due to shrub growth below	Yes
13	Picea pungens	Colorado spruce	25	Good	No	No	Die back lower branches due to shrub growth below	Yes
14	Picea pungens	Colorado spruce	25	Good	No	No	Die back lower branches due to shrub growth below	Yes



PROJECT TEAM

OWNER/APPLICANT

CANADA CLEAN ROOM
20 COPE DRIVE, KANATA, ON K2M 2V8
TEL.: (613) 457-5127
E-MAIL: INFO@CCRCANADA.COM

PROJECT MANAGER

FARMHOUSE INVESTMENTS INC.

701 REVERIE PRIVATE, OTTAWA, ON K2S 0T9
TEL.: (613) 878-5061
E-MAIL: JEN@FARMHOUSEINVESTMENTS.CA

CONSTRUCTION MANAGER

ARGUE CONSTRUCTION LTD.

2900 CARP ROAD, CARP, ON K0A 1L0
TEL.: (613) 831-7044
E-MAIL: INFO@ARGUECONSTRUCTION.CA

LAND SURVEYOR

FAIRHALL, MOFFATT AND WOODLAND LIMITED

100-400 TERRY FOX DRIVE, KANATA, ON K2L 4B6
TEL.: (613) 591-2580
E-MAIL: INFO@FMW.ON.CA

ARCHITECT

A+ ARCHITECTURE INC.

304-555 LEGGET DRIVE, KANATA, ON K2K 2X3
TEL.: (613) 699-6860
E-MAIL: INFO@APLUS-ARCH.COM

CIVIL ENGINEER

IBI GROUP

400-333 PRESTON STREET, OTTAWA, ON K1S 5N4
TEL.: (613) 225-1311
E-MAIL: DYANNOULOPOULOS@IBIGROUP.COM

ELECTRICAL ENGINEER


M&E ENGINEERING

205 KINCARDINE DRIVE, KANATA, ON K2V 1C5
TEL.: (613) 836-3420
E-MAIL: FARZAD@MEENGINEERING.CA

LANDSCAPE ARCHITECT

CSW LANDSCAPE ARCHITECTS

502-319 MCRAE AVENUE, OTTAWA, ON K1Z 0B9
TEL.: (613) 729-4536
E-MAIL: EDWARDS@CSW.CA



No.	Revision	Date
05	ISSUED FOR SPA	05/02/2019
04	ISSUED FOR SPA	18/12/2018
03	ISSUED FOR SPA	11/09/2018
02	ISSUED FOR REVIEW	27/07/2018
01	ISSUED FOR REVIEW	24/07/2018

North:

Stamp:

Landscape Architecture
Urban Design
Site Planning
Recreation and Park Planning
Project Management

319 McRae Avenue, Suite 502, Ottawa, Ontario K1Z 0B9
Tel: (613) 729-4536

- All measurements in millimeters unless specified otherwise. Do not scale drawing. All drawings to be read in conjunction with written specifications.
- Copyright reserved. This drawing is the exclusive property of CSW Landscape Architects Ltd. and shall not be used without the consent thereof.
- This Drawing may not be used for construction until signed by the landscape architect. It is the responsibility of the contractor to:
 - check and verify all dimensions on site;
 - report all errors and/or omissions to the landscape architect;
 - comply with all pertinent codes and by-laws;
 - check and verify locations of all underground services with all local utilities prior to any digging.

Project:

CCR WAREHOUSE
ADDITION & OFFICE RENO

20 COPE DRIVE, KANATA, ON
OTTAWA, ONTARIO

Drawing:

TREE CONSERVATION PLAN
EXISTING CONDITIONS

Scale: 1:400 Date: JULY 2018

Design By: SE Drawn By: SE

Project Number: 1998-01 Sheet Number: TCP 1.0