

IME: H:\01 Project - Proposals\2018 Jobs\CP\0CP-18-0170 BBS_Sysco Building_2390 Stevenage Drive\Civil\15 - Drawings\CP-18-0170_Pre <u>AVED</u>: Tuesday, March 05, 2019_LAST SAVED BY: p.kirkimtzis uCTTED: Tuesday, March 05, 2019_CTB FILE USED: ----

GENERAL NOTES

- THE ORIGINAL TOPOGRAPHY, GROUND FLEVATION AND SURVEY DATA SHOWN ARE SUPPLIED FOR INFORMATION PURPOSES ONLY, AND IMPLY NO GUARANTEE OF ACCURACY. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO VERIFY ALL INFORMATION SHOWN.
- THIS PLAN IS NOT A CADASTRAL SURVEY SHOWING LEGAL PROPERTY BOUNDARIES AND EASEMENTS. THE PROPERTY BOUNDARIES SHOWN HEREON HAVE BEEN DERIVED INFORMATION SUPPLIED BY (OR SHOWN ON) ANNIS, O'SULLIVAN, VOLLEBEKK LTD. SURVEY PLAN #18929-18, DATED SEPTEMBER 4, 2018 AND CANNOT BE RELIED UPON TO BE ACCURATE OR COMPLETE. THE PRECISE LOCATION OF THE CURRENT PROPERTY BOUNDARIES AND EASEMENTS CAN ONLY BE DETERMINED BY AN UP-TO-DATE LAND TITLES SEARCH AND A SUBSEQUENT CADASTRAL SURVEY PERFORMED AND CERTIFIED BY AN ONTARIO LAND SURVEYOR
- THE CONTRACTOR IS TO OBTAIN AND PAY FOR ALL NECESSARY PERMITS AND APPROVALS FROM THE CITY OR TOWNSHIP BEFORE COMMENCING CONSTRUCTION.
- THE CONTRACTOR IS RESPONSIBLE FOR ALL LAYOUT.
- THE CONTRACTOR IS TO DETERMINE THE EXACT LOCATION, SIZE, MATERIAL AND ELEVATION OF ALL EXISTING UTILITIES PRIOR TO COMMENCING CONSTRUCTION. PROTECT AND ASSUME ALL RESPONSIBILITY FOR EXISTING UTILITIES WHETHER OR NOT SHOWN ON THESE DRAWINGS IF THERE IS ANY DISCREPANCY THE CONTRACTOR IS TO NOTIFY THE ENGINEER PROMPTLY. RESTORE ALL TRENCHES AND SURFACES OF PUBLIC ROAD ALLOWANCES TO CONDITION EQUAL OR BETTER THAN ORIGINAL CONDITION AND TO THE SATISFACTION OF THE CITY OR
- TOWNSHIP AUTHORITIES. EXCAVATE AND DISPOSE OF ALL EXCESS EXCAVATED MATERIAL, SUCH AS ASPHALT, CURBING
- AND DEBRIS. OFF SITE AS DIRECTED BY THE ENGINEER AND THE CITY OR TOWNSHIP. TOPSOIL TO BE STRIPPED AND STOCKPILED FOR REHABILITATION. CLEAN FILL TO BE PLACED IN
- FILL AREAS AND COMPACTED TO 95% STANDARD PROCTOR DENSITY. ALL DISTURBED AREAS TO BE RESTORED TO ORIGINAL CONDITION OR BETTER UNLESS OTHERWISE SPECIFIED.
- 10. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL TRAFFIC CONTROL AND SAFETY MEASURES DURING THE CONSTRUCTION PERIOD, INCLUDING THE SUPPLY, INSTALLATION, AND REMOVAL OF ALL NECESSARY SIGNAGE, DELINEATORS, MARKERS AND BARRIERS.
- 11. DO NOT ALTER GRADING OF THE SITE WITHOUT PRIOR APPROVAL OF THE CITY OR TOWNSHIP. 12. ALL ROADWAY, PARKING LOT, AND GRADING WORKS TO BE UNDERTAKEN IN ACCORDANCE WITH CITY OR TOWNSHIP STANDARDS AND SPECIFICATIONS. THE CONTRACTOR IS TO PROVIDE POSITIVE DRAINAGE AWAY FROM THE BUILDING.
- 13. CONTACT THE CITY OR TOWNSHIP FOR INSPECTION OF ROUGH GRADING OF PARKING LOTS, ROADWAYS AND LANDSCAPED AREAS PRIOR TO PLACEMENT OF ASPHALT AND TOPSOIL, ALI DEFICIENCIES NOTED SHALL BE RECTIFIED TO THE CITY OR TOWNSHIP SATISFACTION PRIOR TO PLACEMENT OF ANY ASPHALT, TOPSOIL, SEED & MULCH AND/OR SOD.
- 14. ALL DIMENSIONS AND INVERTS MUST BE VERIFIED PRIOR TO CONSTRUCTION, IF THERE IS ANY DISCREPANCY THE CONTRACTOR IS TO NOTIFY THE ENGINEER PROMPTLY
- 15. ELECTRICAL, GAS, TELEPHONE AND TELEVISION SERVICE LOCATIONS ARE SUBJECT TO THE
- INDIVIDUAL AGENCY: • ELECTRICAL SERVICE - HYDRO OTTAWA, GAS SERVICE - ENBRIDGE • TELEPHONE SERVICE - BELL CANADA, • TELEVISION SERVICE - ROGERS.
- INSTALLATION TO BE IN ACCORDANCE WITH CURRENT CODES AND STANDARDS OF APPROVAL AGENCIES HYDRO OTTAWA, BELL AND THE CITY OR TOWNSHIP.
- 18. ALL PROPOSED CURB SHALL BE CONCRETE BARRIER CURB UNLESS SPECIFIED. 19. ALL EXISTING REDUNDANT PRIVATE APPROACHES FRONTING THIS DEVELOPMENT MUST BE REMOVED TO THE SATISFACTION OF THE CITY OR TOWNSHIP.
- 20. THIS PLAN MUST BE READ IN CONJUNCTION WITH THE GEOTECHNICAL INVESTIGATION BY PATERSON GROUP. DATED JULY 30. 2018 REPORT #PG4583-1 AND THE SITE SERVICING & STORMWATER MANAGEMENT REPORT BY MCINTOSH PERRY REPORT #CP-18-0170, DATED SEPTEMBER 10, 2018

SEWER NOTES

- CONSTRUCT ALL SEWERS AND APPURTENANCES TO CITY OR TOWNSHIP STANDARDS (IF AVAILABLE) OR AS PER OPSD STANDARDS.
- SEWER TRENCHING AND BEDDING SHALL CONFORM TO OPSD 802.010 AND 802.013 UNLESS NOTED OTHERWISE.
- BEDDING SHALL BE A MINIMUM 150mm OF GRANULAR "A", COMPACTED TO MINIMUM 95%
- STANDARD PROCTOR DRY DENSITY. CLEAR STONE BEDDING SHALL NOT BE PERMITTED. 4. SUB-BEDDING, IF REQUIRED SHALL BE AS PER THE DIRECTION OF A GEOTECHNICAL ENGINEER.
- BACKFILL TO AT LEAST 300mm ABOVE TOP OF PIPE WITH GRANULAR "A" OR SAND.
- TO MINIMIZE DIFFERENTIAL FROST HEAVING, TRENCH BACKFILL (FROM PAVEMENT SUBGRADE TO 2.0m BELOW FINISHED GRADE) SHALL MATCH EXISTING SOIL CONDITIONS. SEWERS AND CONNECTIONS 150mm DIAMETER AND SMALLER TO BE PVC SDR 28 OR
- APPROVED EQUIVALENT. SEWERS AND CONNECTIONS 200mm DIAMETER AND LARGER TO BE PVC SDR 35 OR APPROVED EQUIVALENT SEWER CONNECTIONS ARE TO BE MADE ABOVE THE SPRINGLINE OF THE SEWERMAIN AS PER CITY OF OTTAWA STANDARD DRAWINGS S11, S11.1 & S11.2.
- INSULATE ALL SEWERS AND/OR SERVICES THAT HAVE LESS THAN 1.5m OF COVER WITH THERMAL INSULATION AS PER OPSD 1109.030.
- 10. SUPPLY AND INSTALL ALL PIPING AND APPURTENANCES AS SHOWN AND DETAILED TO WITHIN 1.0m OF BUILDING. ALL ENDS OF SERVICES TO BE PROPERLY CAPPED AND LOCATED WITH 2"x4"x8' LONG MARKER.
- 11. CONTRACTOR TO TELEVISE (CCTV) ALL PROPOSED SEWERS ONSITE, OUTLET CONNECTION TO THE MAIN AND PIPES 150mm OR GREATER PRIOR TO BASE COURSE ASPHALT. UPON COMPLETION OF CONTRACT, THE CONTRACTOR IS RESPONSIBLE TO FLUSH AND CLEAN ALL SEWERS & APPURTENANCES.
- 12. DYE TESTING IS TO BE COMPLETED ON SANITARY SERVICE TO CONFIRM PROPER CONNECTION TO THE SANITARY SEWER MAIN.
- 13. ALL CATCHBASIN AND CATHCBASIN MANHOLE LEADS ARE TO BE MINIMUM 200mmØ WITH MINIMUM 1.0% SLOPE UNLESS OTHERWISE NOTED
- 14. ALL CATCHBASINS EXCLUDING LANDSCAPE CATCHBASINS ARE TO HAVE 150 mm@ PERFORATED PIPE FOR 3.0m ON ALL AVAILABLE SIDES AS PER CITY OF OTTAWA STANDARD
- 15. FOUNDATION BACKWATER VALVES AND SANITARY BACKWATER VALVES ARE TO BE INSTALLED AS PER CITY OF OTTAWA STANDARD DRAWINGS S14, S14.1 & S14.2.


WATERMAIN NOTES


DRAWING 'R1

- CONSTRUCT ALL WATERMAINS AND APPURTENANCES IN ACCORDANCE WITH OPSD STANDARDS AND SPECIFICATIONS, AS WELL AS CITY OR TOWNSHIP STANDARDS.
- INDUSTRIAL/COMMERCIAL SERVICE CONNECTIONS TO BE 50mm COPPER PIPING AND SHALL CONFORM TO ASTM B88 TYPE 'K' SOFT.
- WATERMAINS AND/OR WATER SERVICES ARE TO HAVE A MINIMUM COVER OF 2.4m. OTHERWISE THERMAL INSULATION IS REQUIRED AS PER CITY OR TOWNSHIP STANDARDS (IF
- AVAILABLE) OR OPSD 1109.030. IF THE WATERMAIN MUST BE DEFLECTED TO MEET ALIGNMENT, ENSURE THAT THE AMOUNT OF DEFLECTION USED IS EQUAL TO OR LESS THAN THAT WHICH IS RECOMMENDED BY THE MANUFACTURER.
- USE APPROVED SADDLE CONNECTION WITH MAIN (CORPORATION) STOP AS PER CITY OF OTTAWA STANDARD DRAWING 'W26'.
- CONNECTION TO EXISTING BY CITY OR TOWNSHIP FORCES. EXCAVATION, BACKFILLING AND
- REINSTATEMENT IS TO BE COMPLETED BY THE CONTRACTOR. THERMAL INSULATION OF WATERMAINS AT OPEN STRUCTURES AS PER CITY OR TOWNSHIP
- STANDARDS (IF AVAILABLE) OR OPSD 1109.030.

STANDARDS (II AVAILABLE) ON OF 3D 1105.050.
THERMAL INSULATION OF WATERMAINS UNDER ROAD SIDE DITCHES AS PER CITY OF OTTAWA STANDARD DRAWING 'W21'.


	WATE	R COVER TA	BLE		
LOCATION	STATION	FINISHED GRADE	TOP OF PIPE	DEPTH OF PIPE	NAME
A - 300 x 300 TEE	1+000.00	82.29	79.89	2.40	
VALVE & BOX	1+007.17	82.38	79.98	2.40	CB1
B - 300 x 150 TEE	1+080.67	82.01	79.61	2.40	
C - 300 x 50 TEE	1+148.62	82.55	80.15	2.40	CB2
VALVE & BOX	1+153.12	82.24	79.84	2.40	
45° BEND	1+247.00	82.15	79.75	2.40	CB3
45° BEND	1+251.24	82.11	79.71	2.40	
D - 300 x 150 TEE	1+302.49	81.92	79.52	2.40	
3.9° DEFLECTION	1+309.37	81.98	79.58	2.40	CB4
22.5° BEND	1+393.69	82.21	79.81	2.40	
22.5° BEND	1+400.41	82.02	79.62	2.40	CB5
22.5° BEND	1+406.95	82.01	79.61	2.40	
22.5° BEND	1+421.47	82.13	79.73	2.40	CB6
VALVE & BOX	1+453.12	82.48	80.08	2.40	
E - 300 x 300 TEE	1+466.54	82.61	80.21	2.40	687
F - 300 x 150 TEE	1+493.65	82.58	80.18	2.40	CB7
3.9° DEFLECTION	1+532.43	82.58	80.18	2.40	
VALVE & BOX	1+669.01	83.20	80.80	2.40	CB10
22.5° BEND	1+670.36	83.17	80.77	2.40	
G - 300 x 300 TEE	1+676.11	83.15	80.75	2.40	CB11
B - 300 x 150 TEE	2+000.00	82.01	79.61	2.40	
VALVE & BOX	2+001.30	81.83	79.43	2.40	CB20
HYDRANT	2+011.67	82.20	79.80	2.40	CD20
C - 300 x 50 TEE	3+000.00	82.25	79.85	2.40	
VALVE	3+001.00	82.21	79.81	2.40	CBMH13
BUILDING	3+021.94	81.70	79.30	2.40	
D - 300 x 150 TEE	4+000.00	81.92	79.52	2.40	CBMH14
VALVE & BOX	4+001.00	81.93	79.53	2.40	
HYDRANT	4+005.13	81.07	78.67	2.40	CBMH15
E - 300 x 300 TEE	5+000.00	82.61	80.21	2.40	
VALVE & BOX	5+001.00	82.66	80.21	2.40	
BUILDING	5+005.32	82.82	80.42	2.40	CBMH18
F - 300 x 150 TEE	6+000.00	82.58	80.18	2.40	
VALVE & BOX	6+001.00	82.53	80.13	2.40	NOTES: • ALL S
HYDRANT	6+002.78	82.69	80.29	2.40	
H - BUILDING	7+000.00	81.70	79.30	2.40	ELEVA CROS
45° BEND	7+018.32	82.07	79.67	2.40	WATE STAN
45° BEND	7+021.32	82.17	79.77	2.40	
45° BEND	7+112.46	82.15	79.75	2.40	PAVEMEN •• L
45° BEND	7+115.46	82.11	79.71	2.40	
3.9° DEFLECTION	7+113.40	81.78	79.38	2.40	
22.5° BEND	7+257.12	82.25	79.85	2.40	●●
22.5° BEND	7+263.64	82.23	79.78	2.40	
22.5° BEND	7+267.35	81.97	79.78	2.40	L
22.5° BEND	7+287.55	82.17	79.37	2.40	
45° BEND	7+285.91	82.62	80.22	2.40	
45° BEND	7+323.03	82.74	80.22	2.40	
I - BUILDING	7+328.03	82.82	80.42	2.40	
	-	82.82	00.72	2.70	





101 Project - Proposals/2018 Jobs/CP/0CP-18-0170 BBS_Sysco Building_2390 Stevenage Drive\Civil\15 - Drawings\CP-18-01 uesday, March 05, 2019 LAST SAVED BY: p.kirkimtzis v. Tuocday, March 05, 2019 CTB EUE FILEED......

	LOCATION PLAN LEGEND DC DC MOUNTABLE CUB CURB DEPRESION MOUNTABLE CUB CURB DEPRESION MOUNTABLE CUB CURB DEPRESION MOUNTABLE CUB EASEMENT HEAVY DUTY AS CONCRETE SIDE PAVING STONE STORM MANHO CATCHBASIN OF CB6 DI6 CATCHBASIN OF ANITARY MAN PERFORATED PI WATER VAVLE/ FIRE HYDRANT W WATER METER W REMOTE METER W REMOTE METER SLOPING AT 311 (UNLESS SPECIF PS.94 PS.94 SVALE ELEVATION SLOPING AT 311 (UNLESS SPECIF PS.94 SVALE ELEVATION SLOPING AT 311 (UNLESS SPECIF SLOPING AT 311 (UNLESS SPECIF (UNLESS	SILT FENCE SILT FENCE (AS PER OPSD 219.130) STRAW BALE CHECK DAM (AS PER OPSD 219.130) STRAW BALE CHECK DAM (AS PER OPSD 219.180) ROOF DRAIN LOCATION ROOF SUPPER LOCATION SUPPER LOCATION F SWALE DF DITCH CI LEVATION VALL ELEVATION VALL ELEVATION VALL ELEVATION VOERLAND			
	••••••				
	3 REVISED PER CITY C	COMMENTS MAR. 4, 2019			
EROSION AND SEDIMENT CONTROL	2 REVISED PER CITY C	COMMENTS JAN. 10, 2019			
1. THE CONTRACTOR SHALL IMPLEMENT BEST MANAGEMENT PRACTICES, TO PROVIDE FOR PROTECTION OF THE AREA DRAINAGE SYSTEM AND THE RECEIVING WATERCOURSE, DURING	1 ISSUED FOR SITE PL	PLAN CONTROL SEPT. 10, 2018			
CONSTRUCTION ACTIVITIES. THE CONTRACTOR ACKNOWLEDGES THAT FAILURE TO IMPLEMENT APPROPRIATE EROSION AND SEDIMENT CONTROL MEASURES MAY BE SUBJECT TO PENALTIES IMPOSED BY ANY APPLICABLE REGULATORY AGENCY. THIS INCLUDES LIMITING THE AMOUNT OF EXPOSED SOIL, TEMPORARY SEDIMENT CONTROL (GEOSOCK INSERTS WITH AN OVERFLOW	No. Check and verify all dimens	Revisions Date			
UNDER GRATE OR COVER) TO BE IMPLEMENTED DURING CONSTRUCTION ON ALL PROPOSED ROAD CATCHBASINS, REARYARD CATCHBASINS AND CATCHBASIN MANHOLES AND OTHER SEDIMENT TRAPS. NO RECYCLED GEOSOCK MATERIAL SHALL BE PERMITTED FOR USE ON SITE.	before proceeding with the	e work Do not scale drawings			
2. AT THE DISCRETION OF THE PROJECT MANAGER OR MUNICIPAL STAFF, ADDITIONAL SILT CONTROL DEVICES SHALL BE INSTALLED AT DESIGNATED LOCATIONS.	SCALE 1:750	25 50 75 Metres			
 TABLE 3. EXCEPT AS PROVIDED IN PARAGRAPHS 4.1., and 4.2. BELOW, STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS FEASIBLE IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED, BUT IN NO CASE MORE THAN 14 DAYS AFTER THE CONSTRUCTION ACTIVITY HAS TEMPORARILY OR PERMANENTLY CEASED. WHERE THE INITIATION OF STABILIZATION MEASURES BY THE 14TH DAY AFTER CONSTRUCTION ACTIVITY TEMPORARILY OR PERMANENTLY CEASE IS PRECLUDED BY SNOW COVER, STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS FEASIBLE. WHERE CONSTRUCTION ACTIVITY WILL RESUME ON A PORTION OF THE SITE WITHIN 21 DAYS FROM WHEN ACTIVITIES CEASED, (E.G. THE TOTAL TIME PERIOD THAT CONSTRUCTION ACTIVITY IS TEMPORARILY CEASED IS LESS THAN 21 DAYS) THEN 	EXCEPT AS PROVIDED IN PARAGRAPHS 4.1., and 4.2. BELOW, STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS FEASIBLE IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED, BUT IN NO CASE MORE THAN 14 DAYS AFTER THE CONSTRUCTION ACTIVITY HAS TEMPORARILY OR PERMANENTLY CEASED. .1. WHERE THE INITIATION OF STABILIZATION MEASURES BY THE 14TH DAY AFTER CONSTRUCTION ACTIVITY TEMPORARILY OR PERMANENTLY CEASE IS PRECLUDED BY SNOW COVER, STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS FEASIBLE. .2. WHERE CONSTRUCTION ACTIVITY WILL RESUME ON A PORTION OF THE SITE WITHIN 21 DAYS FROM WHEN ACTIVITIES CEASED, (E.G. THE TOTAL TIME PERIOD THAT				
 STABILIZATION MEASURES DO NOT HAVE TO BE INITIATED ON THAT PORTION OF SITE BY THE 14TH DAY AFTER CONSTRUCTION ACTIVITY TEMPORARILY CEASED. SEDIMENT THAT IS ACCUMULATED BY THE TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES SHALL BE REMOVED IN A MANNER THAT AVOIDS ESCAPE OF THE SEDIMENT TO THE DOWNSTREAM SIDE OF THE CONTROL MEASURE AND AVOIDS DAMAGE TO THE CONTROL MEASURE. SEDIMENT SHALL BE REMOVED TO THE LEVEL OF THE GRADE EXISTING AT THE TIME THE CONTROL MEASURE WAS CONSTRUCTED AND BE ACCORDING TO THE FOLLOWING: 5.1. FOR LIGHT-DUTY SEDIMENT BARRIERS, ACCUMULATED SEDIMENT SHALL BE REMOVED ONCE IT REACHES THE LESSER OF THE FOLLOWING: 5.1.1. A DEPTH OF ONE-HALF THE EFFECTIVE HEIGHT OF THE CONTROL MEASURE. 5.1.2. A DEPTH OF 300 MM IMMEDIATELY UPSTREAM OF THE CONTROL MEASURE. 5.2. FOR ALL CONTROL MEASURES, ACCUMULATED SEDIMENT SHALL BE REMOVED AS NECESSARY TO PERFORM MAINTENANCE REPAIRS. 5.3. ACCUMULATED SEDIMENT SHALL BE REMOVED PRIOR TO THE REMOVAL OF THE CONTROL MEASURE. 	~	Stamp Stattamp Sta			
 5.4. ACCUMULATED SEDIMENT IS TO BE REMOVED AND DISPOSED OF AS PER OPSS 180. 6. ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES SHALL BE MONITORED TO ENSURE THEY ARE IN EFFECTIVE WORKING ORDER. THE CONDITION OF THE CONTROL MEASURES SHALL BE MONITORED PRIOR TO ANY FORECAST STORM EVENT AND FOLLOWING A STORM EVENT. 	1	CONSTRUCTION LTD. 1805 WOODWARD DRIVE OTTAWA, ON K2C 0P9			
 DUST CONTROL MEASURES SHOULD BE CONSIDERED PRIOR TO CLEARING AND GRADING. THE USE OF WATER, CALCIUM CHLORIDE FLAKES/SOLUTION OR MAGNESIUM CHLORIDE FLAKES/SOLUTION SHALL BE USED AS DUST SUPPRESSANTS AS PER OPSS 506. THIS IS TO LIMIT WIND EROSION OF SOILS WHICH MAY TRANSPORT SEDIMENTS OFFSITE, WHERE THEY MAY BE WASHED INTO THE RECEIVING WATER BY THE NEXT RAINSTORM. ALL 'GREEN AREAS' TO BE TREATED WITH 150mm TOPSOIL AND SOD AS SOON AS FEASIBLE, AS PER OPSS 570. TOPSOIL TO BE STRIPPED AND STOCKPILED FOR REHABILITATION. CLEAN FILL TO BE PLACED IN FILL AREAS AND COMPACTED TO 95% STANDARD PROCTOR DENSITY. ALL DISTURBED AREAS TO BE RESTORED TO ORIGINAL CONDITION OR BETTER UNLESS OTHERWISE SPECIFIED. 	Project: SYSCO TANNIS - FACILITY EXPANSION 2390 STEVENAGE DRIVE OTTAWA, ON K1G 3W3				
 STOCKPILED MATERIAL IS TO BE STORED AWAY FROM POTENTIAL RECEIVERS (E.G. STORM CATCHBASINS, MANHOLES), AND BE SURROUNDED BY EROSION CONTROL MEASURES WHERE MATERIAL IS LEFT IN PLACE IN EXCESS OF 14 DAYS. IF REQUIRED, DEWATERING/SETTLING BASINS SHALL BE CONSTRUCTED AS PER OPSD 219.240 AND LOCATED ON FLAT GRADE UPSTREAM OF OTHER EXISTING MITIGATION MEASURES. WATERCOURSES SHALL NOT BE DIVERTED, OR BLOCKED, AND TEMPORARY WATERCOURSES CROSSINGS SHALL NOT BE CONSTRUCTED OR UTILIZED, UNLESS OTHERWISE SPECIFIED IN THE 	Drawing Title: SEDIMENT & EROSION CONTROL PLAN				
CONTRACT. IF CLOSURE OF ANY PERMANENT WATER PASSAGE IS NECESSARY, THE CONTRACTOR SHALL RELEASE ANY STRANDED FISH TO THE OPEN PORTION OF THE WATERCOURSE WITHOUT HARM.	Scale: 1:750	Project Number:			
13. ALL EROSION AND SEDIMENT CONTROL MEASURES SHALL CONFORM TO OPSS 577 14. WHERE DEWATERING IS REQUIRED, THE DISCHARGED WATER SHALL BE CONTROLLED IN	Drawn By: P.G.K.	CP-18-0170			
 WHERE DEWATERING IS REQUIRED, THE DISCHARGED WATER SHALL BE CONTROLLED IN ACCORDANCE WITH OPSS 518. ALL SETTLING/FILTRATION BASINS SHALL BE EQUIPPED WITH TERRAFIX 270R GEOTEXTILE (OR 	Checked By: R.P.K.				
APPROVED EQUIVALENT) AND SHALL BE CLEANED AND REPLACED AS REQUIRED.	Designed By: P.G.K.	C103			



LENAME: H:\01 Project - Proposals\2018 Jobs\CP\0CP-18-0170 BBS_Sysco Building_2390 Stevenage Drive\Civil\15 - Drawings\CP-18-0170_Pr <u>\5T SAVED</u>: Tuesday, March 05, 2019_LAST SAVED BY: p.kirkimtzis <u>\5T PLOTTED</u>: Tuesday, March 05, 2019_<u>CTB FILE USED</u>: ----