

---

# SITE SERVICING AND STORMWATER MANAGEMENT BRIEF

---

DATE: 2018-09-24

EMAIL

TO: City of Ottawa IAD Review Officer

SUBJECT: **Proposed Amendment to 5754 Hazeldean Road/ 24 Iber Road/ 5734  
Hazeldean Road Site Plan Application  
Previously Approved City File Number: D07-12-17-0186**

OUR FILE: DSEL Project No.19-1133

ATTACHMENTS:

- Site Plan, SP-1, by Hobin Architecture, Dated August 29<sup>th</sup>, 2019 (Proposed Amendment)
- Site Plan, SP-1, by Hobin Architecture, Dated March 8<sup>th</sup>, 2019 (Previously Approved)
- Storm Calculation Sheet, by DSEL, Dated March 27<sup>th</sup>, 2018 (Previously Approved)
- Stormwater Management Plan, SWM-1, by DSEL, Dated Sept 20<sup>th</sup>, 2019 (Proposed Amendment)
- Storm Calculation Sheet, by DSEL, Dated September 2019 (Proposed Amendment)
- Triton Stormwater Solutions Sizing Specifications, printed September 20<sup>th</sup>, 2019
- Water Demand Calculation Sheet, by DSEL, Dated March 27<sup>th</sup>, 2019 (Previously Approved)
- Water Demand Calculation Sheet, by DSEL, Dated Sept 20<sup>th</sup> 2019 (Proposed Amendment)
- City of Ottawa Boundary Conditions Dated March 7<sup>th</sup>, 2018
- Wastewater Calculation Sheet, by DSEL, Dated March 28<sup>th</sup>, 2019 (Previously Approved)
- Wastewater Calculation Sheet, by DSEL, Dated Sept 20<sup>th</sup>, 2019 (Proposed Amendment)

---

## 1.0 INTRODUCTION

Unity Square Limited Partnership has retained DSEL to prepare a servicing memo in support of the proposed amendment to the previously approved site plan application for the subject site located at 5754 Hazeldean Road, 24 Iber Road, 5734 Hazeldean Road (D07-12-17-0186). Please see proposed amended site plan (**SP-1**) dated August 29<sup>th</sup>, 2019, included along with this memo.

The following memo addresses the impact of the updated site plan on the previously approved Functional Servicing and Stormwater Management brief (**FSB, 2019**) prepared by David Schaeffer Engineering Ltd and dated July 17<sup>th</sup>, 2019.

The previously approved Site Plan proposed **10,690 m<sup>2</sup>** of commercial space. The updated Site Plan proposes a decrease in building area as a result of the revised Building D design. The total commercial space for the amended development is **10,337 m<sup>2</sup>**, a reduction of approximately **353 m<sup>2</sup>**.

Based on the previously approved Site Servicing Plan, **SSP-1**, dated July 17<sup>th</sup>, 2019, the development was proposed to be serviced via the existing sewers and watermain within the Iber Road right-of-way and the existing watermain within the Fringewood Drive right-of-way. As shown by the revised Site Servicing Plan, **SSP-1**, there are no proposed changes.

## 2.0 WATER SUPPLY SERVICING

**FSB, 2019** proposed the design of a private 200 mm diameter internal watermain to service the development. The internal network is connected to both the 305 mm diameter watermain and 203 mm diameter watermain within Iber Road and Fringewood Drive, respectively. Building D was contemplated to connect to the internal watermain via a 150 mm diameter service lateral. As per **SSP-1**, Building D will utilize the existing 150 mm diameter service stub. Refer to drawing **SSP-1** for a detailed servicing layout.

**Table 1**, below, summarizes the **Water Supply Guidelines** employed in the preparation of the preliminary water demand estimate.

**Table 1 – Water Supply Design Criteria**

| Design Parameter                                                                                                                                                                                                                                            | Value                                         |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------|
| Commercial Retail                                                                                                                                                                                                                                           | 2.5 L/m <sup>2</sup> /d                       |
| Commercial Maximum Daily Demand                                                                                                                                                                                                                             | 1.5 x avg. day                                |
| Commercial Maximum Hour Demand                                                                                                                                                                                                                              | 1.8 x max. day                                |
| Minimum Watermain Size                                                                                                                                                                                                                                      | 150 mm diameter                               |
| Minimum Depth of Cover                                                                                                                                                                                                                                      | 2.4 m from top of watermain to finished grade |
| During normal operating conditions desired operating pressure is within                                                                                                                                                                                     | 350 kPa and 480 kPa                           |
| During normal operating conditions pressure must not drop below                                                                                                                                                                                             | 275 kPa                                       |
| During normal operating conditions pressure must not exceed                                                                                                                                                                                                 | 552 kPa                                       |
| During fire flow operating pressure must not drop below                                                                                                                                                                                                     | 140 kPa                                       |
| *Daily average based on Appendix 4-A from <b>Water Supply Guidelines</b><br>** Residential Max. Daily and Max. Hourly peaking factors per MOE Guidelines for Drinking-Water Systems Table 3-3 for 0 to 500 persons.<br>-Table updated to reflect ISD-2010-2 |                                               |



**Table 2**, below, summarizes the water supply demand and boundary conditions for the approved based on the **Water Supply Guidelines**.

**Table 2 – Previously Approved Water Demand and Boundary Conditions**

| Design Parameter                                                                                                                                                                                                                                                                                                        | Approved Estimated Demand <sup>1</sup><br>(L/min) | Boundary Condition <sup>2</sup><br>Fringewood<br>(m H <sub>2</sub> O / kPa) |       | Boundary Condition <sup>2</sup><br>Iber Rd<br>(m H <sub>2</sub> O / kPa) |       |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------|-----------------------------------------------------------------------------|-------|--------------------------------------------------------------------------|-------|
| Average Daily Demand                                                                                                                                                                                                                                                                                                    | 18.6                                              | 56.6                                                                        | 555.2 | 58.1                                                                     | 570.0 |
| Max Day + Fire Flow                                                                                                                                                                                                                                                                                                     | 27.8 + 7,000 = 7,027.8                            | 53.3                                                                        | 522.9 | 54.8                                                                     | 537.6 |
| Peak Hour                                                                                                                                                                                                                                                                                                               | 50.1                                              | 54.5                                                                        | 534.6 | 55.8                                                                     | 547.4 |
| 1) Water demand calculation per <b>Water Supply Guidelines</b> . See <b>Appendix B</b> for detailed calculations.<br>2) Boundary conditions supplied by the City of Ottawa for demands as indicated in correspondence. Assumed ground elevation: Fringewood Drive=104.5 m, Iber Road = 103.1 m. See <b>Appendix B</b> . |                                                   |                                                                             |       |                                                                          |       |

As summarized in *Section 1.0*, the updated Site Plan results in a decrease in total commercial area. As a result, the previously approved water demand will be decreased by approximately **3%**, as shown by the water demand calculation sheet included in **Appendix B**.

**Table 3**, below, summarizes the estimated water supply demand for the amended site plan.

**Table 3 –Proposed Amended Water Demand Summary**

| Design Parameter                                                                                                | Proposed Estimated Demand <sup>1</sup><br>(L/min) |
|-----------------------------------------------------------------------------------------------------------------|---------------------------------------------------|
| Average Daily Demand                                                                                            | 17.9                                              |
| Max Day + Fire Flow                                                                                             | 26.9                                              |
| Peak Hour                                                                                                       | 48.5                                              |
| 1) Water demand calculation per <b>Water Supply Guidelines</b> . See <b>Appendix</b> for detailed calculations. |                                                   |

Fire flow requirements are to be determined in accordance with Local Guidelines (**ISDTB-2018-02**), City of Ottawa **Water Supply Guidelines**, and the Ontario Building Code.

Using the Technical Bulletin **ISDTB-2018-02** method, a conservative estimation of fire flow had been established. As coordinated with the building architect, the following assumptions were made:

- Type of construction – Non-Combustible Construction
- Occupancy type – Non-Combustible
- Sprinkler Protection – Supervised Sprinkler System

As shown by **Table 2**, above, the maximum fire flow for the development was estimated to be **7,000 L/s**. The previously approved fire flow for Building D was estimated to be **4,000 L/s**. Due to the reduction in floor area, the estimated fire flow demand for Building D has been reduced to **2,000 L/s**. Detailed calculations can be found in **Appendix B**.

The City provided both the anticipated minimum and maximum water pressures, as well as, the estimated water pressure during fire flow demand for the previously approved demands, as indicated by the correspondence in **Appendix B**. The minimum and maximum pressures fall

within the required range identified in **Table 1**, above. As a result, the municipal system is capable of providing sufficient water supply during fire flow conditions.

Based on the updated Site Plan, the estimated water demand for the site decreased by approximately 3%. It is not anticipated to have a significant impact on the previously provided boundary conditions.

The previously approved EPAnet model was updated based on the proposed amended demands to ensure adequate pressure within the internal watermain network and at each building connection. As shown by the hydraulic modelling included in **Appendix B**, the revised demands resulted in an insignificant change in pressure.

### 3.0 WASTEWATER SERVICING

**FSB, 2019** proposed the design of a private 250 mm diameter internal sanitary sewer to service the development. The internal network is tributary to the newly extended 250 mm diameter sanitary sewer within Iber Road. Building D was contemplated to connect to the internal sewer via a 200 mm diameter service lateral. As per **SSP-1**, Building D will utilize the existing 200 mm diameter service lateral stub. Refer to drawing **SSP-1** for a detailed servicing layout.

Based on **FSB, 2019**, the internal sanitary sewer network has sufficient capacity to support the previously approved development. The private sewer network is tributary to the existing 250 mm diameter sewer within Iber road, which was sufficiently sized to accommodate the previously approved development.

**Table 4**, below, summarizes the **City Standards** employed in the design of the proposed wastewater sewer system for the previously approved and proposed amendment.

**Table 4 – Wastewater Design Criteria**

| Design Parameter                                                                                                                                                       | Value                                                         |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------|
| Commercial Floor Space                                                                                                                                                 | 5 L/m <sup>2</sup> /d                                         |
| Infiltration and Inflow Allowance                                                                                                                                      | 0.05 L/s/ha (Dry)<br>0.28 L/s/ha (Wet)<br>0.33 L/s/ha (Total) |
| Sanitary sewers are to be sized employing the Manning's Equation                                                                                                       | $Q = \frac{1}{n} AR^{\frac{2}{3}} S^{\frac{1}{2}}$            |
| Minimum Sewer Size                                                                                                                                                     | 200 mm diameter                                               |
| Minimum Manning's 'n'                                                                                                                                                  | 0.013                                                         |
| Minimum Depth of Cover                                                                                                                                                 | 2.5 m from crown of sewer to grade                            |
| Minimum Full Flowing Velocity                                                                                                                                          | 0.6 m/s                                                       |
| Maximum Full Flowing Velocity                                                                                                                                          | 3.0 m/s                                                       |
| Extracted from Sections 4 and 6 of the City of Ottawa Sewer Design Guidelines, October 2012.<br>*Revised design parameters outlined in Technical Bulletin ISTB-2018-01 |                                                               |

**Table 5**, below, demonstrates the estimated peak flow from the previously approved development. Refer to **Appendix C** for associated calculations.

**Table 5 – Previously Approved Wastewater Demand Summary**

| Design Parameter                   | Estimated Demand <sup>1</sup><br>(L/min) |
|------------------------------------|------------------------------------------|
| Estimated Average Dry Weather Flow | 1.46                                     |
| Estimated Peak Dry Weather Flow    | 2.08                                     |
| Estimated Peak Wet Weather Flow    | 3.32                                     |

**Table 6**, below, demonstrates the estimated peak flow from the proposed development. Refer to **Appendix C** for associated calculations.

**Table 6 – Proposed Amendment Wastewater Demand Summary**

| Design Parameter                   | Estimated Demand <sup>1</sup><br>(L/min) |
|------------------------------------|------------------------------------------|
| Estimated Average Dry Weather Flow | 1.42                                     |
| Estimated Peak Dry Weather Flow    | 2.02                                     |
| Estimated Peak Wet Weather Flow    | 3.26                                     |

As demonstrated by **Table 5** and **Table 6**, due to the reduction in commercial floor area the estimated wastewater flow for the proposed development has been reduced by approximately 3% from the previously approved wastewater flow. As a result, sufficient capacity is available within the internal private sanitary sewer as well as the 250 mm diameter sanitary sewer within Iber Road to accommodate the amended development.

#### 4.0 STORMWATER MANAGEMENT

**FSB, 2019** proposed the design of a private internal storm sewer to service the development. The internal network is tributary to the existing Hazeldean Tributary. Building D was contemplated to connect to the internal sewer via a 200 mm diameter service lateral. As per **SSP-1**, Building D will utilize the existing 200 mm diameter service lateral stub. Refer to drawing **SSP-1** for a detailed servicing layout.

Based on consultation with the City of Ottawa staff, the 5-year and 100-year allowable release rates established for the approved development are **271.6 L/s** and **463.6 L/s**, respectively. An existing **291 mm** diameter ICD, installed within storm maintenance structure STM101A, is utilized to restrict flow leaving the site to meet the specified allowable release rates. The previously approved storm calculation sheets dated March 27<sup>th</sup>, are included for reference in **Appendix D**.

To meet the stormwater objectives, **FSB, 2019** proposed a combination of sub-surface and surface storage. Subsurface storage is provided within maintenance structures, storm sewers, and a **76 m<sup>3</sup>** underground storage chamber. Surface storage is provided through rooftop storage as well as through surface ponding within parking areas.

**Table 7**, summarizes the available storage for the approved and proposed amendments for the development.

**Table 7 – Available Stormwater Storage**

|                 | Surface<br>Storage<br>(m <sup>3</sup> ) | Roof<br>Storage<br>(m <sup>3</sup> ) | Underground<br>Storage<br>(m <sup>3</sup> ) | Maintenance<br>Structures<br>and Sewers<br>(m <sup>3</sup> ) | Total<br>Storage<br>(m <sup>3</sup> ) |
|-----------------|-----------------------------------------|--------------------------------------|---------------------------------------------|--------------------------------------------------------------|---------------------------------------|
| <b>Approved</b> | 857.6                                   | 679.2                                | 76                                          | 217.0                                                        | <b>1829.8</b>                         |
| <b>Proposed</b> | 784.7                                   | 598.9                                | 157                                         | 217.9                                                        | <b>1758.5</b>                         |

Due to the changes in the site plan, Building D's footprint has decreased. Further, due to changes in the parking area surrounding Building D the site ponding volume was reduced. In order to compensate for a reduction in available rooftop and surface storage, an additional **81 m<sup>3</sup>** underground storage system is proposed to attenuate flow to the 5-year and 100-year allowable stormwater release rate of **271.6 L/s** and **463.6 L/s**, respectively.

**Table 8**, below, summarizes the approved release rates and onsite storage required to meet established target release rates in accordance with the approved stormwater management plan.

**Table 8 - Previously Approved SWM Summary**

| Control Area                                                                                                                                                                                                                                                                    | 5-Year<br>Release<br>Rate<br>(L/s) | 5-Year<br>Storage<br>(m <sup>3</sup> ) | 100-Year<br>Release<br>Rate<br>(L/s) | 100-Year<br>Storage<br>(m <sup>3</sup> ) | Storage<br>Available<br>(m <sup>3</sup> ) |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------|----------------------------------------|--------------------------------------|------------------------------------------|-------------------------------------------|
| U1                                                                                                                                                                                                                                                                              | 37.3                               | 0.0                                    | 79.7                                 | 0.0                                      | 0.0                                       |
| U2                                                                                                                                                                                                                                                                              | 10.6                               | 0.0                                    | 22.7                                 | 0.0                                      | 0.0                                       |
| U3                                                                                                                                                                                                                                                                              | 3.2                                | 0.0                                    | 6.1                                  | 0.0                                      | 0.0                                       |
| Attenuated Areas *                                                                                                                                                                                                                                                              | 216.4                              | 331.2                                  | 182.1                                | 1134.0                                   | 1150.7                                    |
| <b>Total</b>                                                                                                                                                                                                                                                                    | <b>267.5</b>                       | <b>331.2</b>                           | <b>290.6</b>                         | <b>1134.0</b>                            | <b>1150.7</b>                             |
| * Attenuated Areas includes controlled flow from BLDG A-G.<br>1. Release rate is established using the critical time of concentration producing the highest peak cumulative runoff for the site.<br>2. Total release rate calculated using attenuated areas+ unattenuated areas |                                    |                                        |                                      |                                          |                                           |

**Table 9**, below, summarizes the estimated release rates and onsite storage required to meet the established target release rates based on updates to the amended Site Plan.

**Table 9 - Proposed Amendment SWM Summary**

| Control Area                                                                                                                                                                                                                                                                                                          | 5-Year<br>Release<br>Rate<br>(L/s) | 5-Year<br>Storage<br>(m <sup>3</sup> ) | 100-Year<br>Release<br>Rate<br>(L/s) | 100-Year<br>Storage<br>(m <sup>3</sup> ) | Storage<br>Available<br>(m <sup>3</sup> ) |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------|----------------------------------------|--------------------------------------|------------------------------------------|-------------------------------------------|
| U1                                                                                                                                                                                                                                                                                                                    | 37.3                               | 0.0                                    | 79.7                                 | 0.0                                      | 0.0                                       |
| U2                                                                                                                                                                                                                                                                                                                    | 10.6                               | 0.0                                    | 22.7                                 | 0.0                                      | 0.0                                       |
| U3                                                                                                                                                                                                                                                                                                                    | 3.2                                | 0.0                                    | 6.1                                  | 0.0                                      | 0.0                                       |
| Attenuated Areas *                                                                                                                                                                                                                                                                                                    | 191.7                              | 375.0                                  | 182.0                                | 1162.8                                   | 1182.2                                    |
| <b>Total</b>                                                                                                                                                                                                                                                                                                          | <b>242.8</b>                       | <b>375.0</b>                           | <b>290.5</b>                         | <b>1162.8</b>                            | <b>1182.2</b>                             |
| * Attenuated Areas includes controlled flow from BLDG A-G and the uncontrolled flow from BLDG D.<br>1. Release rate is established using the critical time of concentration producing the highest peak cumulative runoff for the site.<br>2. Total release rate calculated using attenuated areas+ unattenuated areas |                                    |                                        |                                      |                                          |                                           |

Area A1 to A32, shown by drawing **SWM-1**, are tributary to the existing Hazeldean Tributary. An additional **81.0 m<sup>3</sup>** of underground storage provided via a Triton M-6 underground storage systems or an approved equivalent is proposed in order to maintain the release rate from the site. Stormwater flow will continue to be attenuated by the existing **291 mm diameter ICD** installed at the outlet side of STM101A. The attached storm calculation sheets illustrate the existing approved plan and proposed amendment. An updated **SWM-1** drawing dated September 2019 and calculation sheets are included in **Appendix D**.

## 5.0 CONCLUSION

Unity Square Limited Partnership has retained DSEL to prepare a servicing memo in support of the proposed amendment to the previously approved site plan application for the subject site located at 5754 Hazeldean Road, 24 Iber Road, 5734 Hazeldean Road (D07-12-17-0186). The updated Site Plan proposes a revised Building D design including the parking areas, and drive aisles, resulting in a reduction of approximately **353 m<sup>2</sup>** of commercial space.

An extension to the previously approved service connections will be required to service Building D. No changes to the internal watermain and sanitary networks are proposed. A minor update to the storm sewer network, south of Building D is proposed to accommodate the amended Site Plan.

The City of Ottawa was contacted to obtain boundary conditions associated with the estimated water demand as indicated in the boundary request correspondence included in **Appendix B**. The City provided both the anticipated minimum and maximum water pressures, as well as, the estimated water pressure during fire flow demand; the minimum and maximum pressures fall within the required range identified in the **Water Supply Guidelines**. As a result, the municipal system is capable of providing sufficient water supply during fire flow conditions.

Based on the revised Site Plan prepared by Hobin Architecture Inc. the estimated wastewater flow from the proposed development has decreased by approximately 3%. As a result, the existing private internal sanitary sewer has sufficient capacity to support the proposed amendment.

Based on the revised calculations the established allowable release rate has been maintained as **271.6 L/s** and **463.6 L/s**, for the 5-year and 100-year allowable release rates, respectively. Due to the revised Building D footprint and a reduction in surface storage it is estimated that an additional **81.0 m<sup>3</sup>** of storage, provided via an underground storage system, will be required to maintain this release rate.

DSEL trusts that the above will be sufficient to support an amendment to the previously approved stormwater management plan, water supply servicing and wastewater servicing to allow the proposed amendment to proceed. Please contact the undersigned should there be any questions.

Prepared by,  
**David Schaeffer Engineering Ltd.**

Reviewed by,  
**David Schaeffer Engineering Ltd.**



Per: Charlotte M. Kelly, EIT



Per: Alison J. Gosling, EIT.

Reviewed by,  
**David Schaeffer Engineering Ltd.**



Per: Robert D. Freel, P.Eng.

---

---

## ***APPENDIX A***

### ***Pre-Consultation***

---

---





# DEVELOPMENT SERVICING STUDY CHECKLIST

19-1133

24/09/2019

## 4.1 General Content

|                                     |                                                                                                                                                                                                                                                                                                                                                                                                                             |                          |
|-------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------|
| <input type="checkbox"/>            | Executive Summary (for larger reports only).                                                                                                                                                                                                                                                                                                                                                                                | N/A                      |
| <input checked="" type="checkbox"/> | Date and revision number of the report.                                                                                                                                                                                                                                                                                                                                                                                     | Design Brief Cover Sheet |
| <input type="checkbox"/>            | Location map and plan showing municipal address, boundary, and layout of proposed development.                                                                                                                                                                                                                                                                                                                              | N/A                      |
| <input checked="" type="checkbox"/> | Plan showing the site and location of all existing services.                                                                                                                                                                                                                                                                                                                                                                | SSP-1                    |
| <input type="checkbox"/>            | Development statistics, land use, density, adherence to zoning and official plan, and reference to applicable subwatershed and watershed plans that provide context to applicable subwatershed and watershed plans that provide context to which individual developments must adhere.                                                                                                                                       | N/A                      |
| <input type="checkbox"/>            | Summary of Pre-consultation Meetings with City and other approval agencies.                                                                                                                                                                                                                                                                                                                                                 | N/A                      |
| <input type="checkbox"/>            | Reference and confirm conformance to higher level studies and reports (Master Servicing Studies, Environmental Assessments, Community Design Plans), or in the case where it is not in conformance, the proponent must provide justification and develop a defensible design criteria.                                                                                                                                      | N/A                      |
| <input checked="" type="checkbox"/> | Statement of objectives and servicing criteria.                                                                                                                                                                                                                                                                                                                                                                             | Section 1.0              |
| <input checked="" type="checkbox"/> | Identification of existing and proposed infrastructure available in the immediate area.                                                                                                                                                                                                                                                                                                                                     | Sections 2.0, 3.0, 4.0   |
| <input type="checkbox"/>            | Identification of Environmentally Significant Areas, watercourses and Municipal Drains potentially impacted by the proposed development (Reference can be made to the Natural Heritage Studies, if available).                                                                                                                                                                                                              | N/A                      |
| <input checked="" type="checkbox"/> | Concept level master grading plan to confirm existing and proposed grades in the development. This is required to confirm the feasibility of proposed stormwater management and drainage, soil removal and fill constraints, and potential impacts to neighbouring properties. This is also required to confirm that the proposed grading will not impede existing major system flow paths.                                 | GP-1                     |
| <input type="checkbox"/>            | Identification of potential impacts of proposed piped services on private services (such as wells and septic fields on adjacent lands) and mitigation required to address potential impacts.                                                                                                                                                                                                                                | N/A                      |
| <input type="checkbox"/>            | Proposed phasing of the development, if applicable.                                                                                                                                                                                                                                                                                                                                                                         | N/A                      |
| <input type="checkbox"/>            | Reference to geotechnical studies and recommendations concerning servicing.                                                                                                                                                                                                                                                                                                                                                 | N/A                      |
| <input checked="" type="checkbox"/> | All preliminary and formal site plan submissions should have the following information:<br>-Metric scale<br>-North arrow (including construction North)<br>-Key plan<br>-Name and contact information of applicant and property owner<br>-Property limits including bearings and dimensions<br>-Existing and proposed structures and parking areas<br>-Easements, road widening and rights-of-way<br>-Adjacent street names | SSP-1                    |

## 4.2 Development Servicing Report: Water

|                                     |                                                                       |             |
|-------------------------------------|-----------------------------------------------------------------------|-------------|
| <input type="checkbox"/>            | Confirm consistency with Master Servicing Study, if available         | N/A         |
| <input checked="" type="checkbox"/> | Availability of public infrastructure to service proposed development | Section 2.0 |
| <input checked="" type="checkbox"/> | Identification of system constraints                                  | Section 2.0 |
| <input checked="" type="checkbox"/> | Identify boundary conditions                                          | Section 2.0 |
| <input checked="" type="checkbox"/> | Confirmation of adequate domestic supply and pressure                 | Section 2.0 |

|                                     |                                                                                                                                                                                                                                                                                                          |             |
|-------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------|
| <input checked="" type="checkbox"/> | Confirmation of adequate fire flow protection and confirmation that fire flow is calculated as per the Fire Underwriter's Survey. Output should show available fire flow at locations throughout the development.                                                                                        | Section 2.0 |
| <input type="checkbox"/>            | Provide a check of high pressures. If pressure is found to be high, an assessment is required to confirm the application of pressure reducing valves.                                                                                                                                                    | N/A         |
| <input type="checkbox"/>            | Definition of phasing constraints. Hydraulic modeling is required to confirm servicing for all defined phases of the project including the ultimate design                                                                                                                                               | N/A         |
| <input type="checkbox"/>            | Address reliability requirements such as appropriate location of shut-off valves                                                                                                                                                                                                                         | N/A         |
| <input type="checkbox"/>            | Check on the necessity of a pressure zone boundary modification                                                                                                                                                                                                                                          | N/A         |
| <input checked="" type="checkbox"/> | Reference to water supply analysis to show that major infrastructure is capable of delivering sufficient water for the proposed land use. This includes data that shows that the expected demands under average day, peak hour and fire flow conditions provide water within the required pressure range | Section 2.0 |
| <input type="checkbox"/>            | Description of the proposed water distribution network, including locations of proposed connections to the existing system, provisions for necessary looping, and appurtenances (valves, pressure reducing valves, valve chambers, and fire hydrants) including special metering provisions.             | N/A         |
| <input type="checkbox"/>            | Description of off-site required feeder mains, booster pumping stations, and other water infrastructure that will be ultimately required to service proposed development, including financing, interim facilities, and timing of implementation.                                                         | N/A         |
| <input checked="" type="checkbox"/> | Confirmation that water demands are calculated based on the City of Ottawa Design Guidelines.                                                                                                                                                                                                            | Section 2.0 |
| <input type="checkbox"/>            | Provision of a model schematic showing the boundary conditions locations, streets, parcels, and building locations for reference.                                                                                                                                                                        | N/A         |

#### 4.3 Development Servicing Report: Wastewater

|                                     |                                                                                                                                                                                                                                                                                                                        |                         |
|-------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------|
| <input checked="" type="checkbox"/> | Summary of proposed design criteria (Note: Wet-weather flow criteria should not deviate from the City of Ottawa Sewer Design Guidelines. Monitored flow data from relatively new infrastructure cannot be used to justify capacity requirements for proposed infrastructure).                                          | Section 3.0             |
| <input type="checkbox"/>            | Confirm consistency with Master Servicing Study and/or justifications for deviations.                                                                                                                                                                                                                                  | N/A                     |
| <input type="checkbox"/>            | Consideration of local conditions that may contribute to extraneous flows that are higher than the recommended flows in the guidelines. This includes groundwater and soil conditions, and age and condition of sewers.                                                                                                | N/A                     |
| <input checked="" type="checkbox"/> | Description of existing sanitary sewer available for discharge of wastewater from proposed development.                                                                                                                                                                                                                | Section 3.0             |
| <input checked="" type="checkbox"/> | Verify available capacity in downstream sanitary sewer and/or identification of upgrades necessary to service the proposed development. (Reference can be made to previously completed Master Servicing Study if applicable)                                                                                           | Section 3.0             |
| <input checked="" type="checkbox"/> | Calculations related to dry-weather and wet-weather flow rates from the development in standard MOE sanitary sewer design table (Appendix 'C') format.                                                                                                                                                                 | Section 3.0, Appendix C |
| <input checked="" type="checkbox"/> | Description of proposed sewer network including sewers, pumping stations, and forcemains.                                                                                                                                                                                                                              | Section 3.0             |
| <input type="checkbox"/>            | Discussion of previously identified environmental constraints and impact on servicing (environmental constraints are related to limitations imposed on the development in order to preserve the physical condition of watercourses, vegetation, soil cover, as well as protecting against water quantity and quality). | N/A                     |

|                          |                                                                                                                                                                          |     |
|--------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|
| <input type="checkbox"/> | Pumping stations: impacts of proposed development on existing pumping stations or requirements for new pumping station to service development.                           | N/A |
| <input type="checkbox"/> | Forcemain capacity in terms of operational redundancy, surge pressure and maximum flow velocity.                                                                         | N/A |
| <input type="checkbox"/> | Identification and implementation of the emergency overflow from sanitary pumping stations in relation to the hydraulic grade line to protect against basement flooding. | N/A |
| <input type="checkbox"/> | Special considerations such as contamination, corrosive environment etc.                                                                                                 | N/A |

#### 4.4 Development Servicing Report: Stormwater Checklist

|                                     |                                                                                                                                                                                                                                                                                                                                                                                                                                          |                         |
|-------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------|
| <input checked="" type="checkbox"/> | Description of drainage outlets and downstream constraints including legality of outlets (i.e. municipal drain, right-of-way, watercourse, or private property)                                                                                                                                                                                                                                                                          | Section 4.0             |
| <input checked="" type="checkbox"/> | Analysis of available capacity in existing public infrastructure.                                                                                                                                                                                                                                                                                                                                                                        | Section 4.0, Appendix D |
| <input checked="" type="checkbox"/> | A drawing showing the subject lands, its surroundings, the receiving watercourse, existing drainage patterns, and proposed drainage pattern.                                                                                                                                                                                                                                                                                             | Drawings/Figures        |
| <input checked="" type="checkbox"/> | Water quantity control objective (e.g. controlling post-development peak flows to pre-development level for storm events ranging from the 2 or 5 year event (dependent on the receiving sewer design) to 100 year return period); if other objectives are being applied, a rationale must be included with reference to hydrologic analyses of the potentially affected subwatersheds, taking into account long-term cumulative effects. | Section 4.0             |
| <input checked="" type="checkbox"/> | Water Quality control objective (basic, normal or enhanced level of protection based on the sensitivities of the receiving watercourse) and storage requirements.                                                                                                                                                                                                                                                                        | Section 4.0             |
| <input checked="" type="checkbox"/> | Description of the stormwater management concept with facility locations and descriptions with references and supporting information                                                                                                                                                                                                                                                                                                     | Section 4.0             |
| <input type="checkbox"/>            | Set-back from private sewage disposal systems.                                                                                                                                                                                                                                                                                                                                                                                           | N/A                     |
| <input type="checkbox"/>            | Watercourse and hazard lands setbacks.                                                                                                                                                                                                                                                                                                                                                                                                   | N/A                     |
| <input checked="" type="checkbox"/> | Record of pre-consultation with the Ontario Ministry of Environment and the Conservation Authority that has jurisdiction on the affected watershed.                                                                                                                                                                                                                                                                                      | Appendix A              |
| <input type="checkbox"/>            | Confirm consistency with sub-watershed and Master Servicing Study, if applicable study exists.                                                                                                                                                                                                                                                                                                                                           | N/A                     |
| <input checked="" type="checkbox"/> | Storage requirements (complete with calculations) and conveyance capacity for minor events (1:5 year return period) and major events (1:100 year return period).                                                                                                                                                                                                                                                                         | Section 4.0             |
| <input type="checkbox"/>            | Identification of watercourses within the proposed development and how watercourses will be protected, or, if necessary, altered by the proposed development with applicable approvals.                                                                                                                                                                                                                                                  | N/A                     |
| <input checked="" type="checkbox"/> | Calculate pre and post development peak flow rates including a description of existing site conditions and proposed impervious areas and drainage catchments in comparison to existing conditions.                                                                                                                                                                                                                                       | Section 4.0             |
| <input type="checkbox"/>            | Any proposed diversion of drainage catchment areas from one outlet to another.                                                                                                                                                                                                                                                                                                                                                           | N/A                     |
| <input type="checkbox"/>            | Proposed minor and major systems including locations and sizes of stormwater trunk sewers, and stormwater management facilities.                                                                                                                                                                                                                                                                                                         | N/A                     |
| <input type="checkbox"/>            | If quantity control is not proposed, demonstration that downstream system has adequate capacity for the post-development flows up to and including the 100-year return period storm event.                                                                                                                                                                                                                                               | N/A                     |
| <input type="checkbox"/>            | Identification of potential impacts to receiving watercourses                                                                                                                                                                                                                                                                                                                                                                            | N/A                     |
| <input type="checkbox"/>            | Identification of municipal drains and related approval requirements.                                                                                                                                                                                                                                                                                                                                                                    | N/A                     |

|                                     |                                                                                                                                                                                                                                                                                                                                               |             |
|-------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------|
| <input checked="" type="checkbox"/> | Descriptions of how the conveyance and storage capacity will be achieved for the development.                                                                                                                                                                                                                                                 | Section 4.0 |
| <input type="checkbox"/>            | 100 year flood levels and major flow routing to protect proposed development from flooding for establishing minimum building elevations (MBE) and overall grading.                                                                                                                                                                            | N/A         |
| <input type="checkbox"/>            | Inclusion of hydraulic analysis including hydraulic grade line elevations.                                                                                                                                                                                                                                                                    | N/A         |
| <input type="checkbox"/>            | Description of approach to erosion and sediment control during construction for the protection of receiving watercourse or drainage corridors.                                                                                                                                                                                                | N/A         |
| <input type="checkbox"/>            | Identification of floodplains – proponent to obtain relevant floodplain information from the appropriate Conservation Authority. The proponent may be required to delineate floodplain elevations to the satisfaction of the Conservation Authority if such information is not available or if information does not match current conditions. | N/A         |
| <input type="checkbox"/>            | Identification of fill constraints related to floodplain and geotechnical investigation.                                                                                                                                                                                                                                                      | N/A         |

#### 4.5 Approval and Permit Requirements: Checklist

|                          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |     |
|--------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|
| <input type="checkbox"/> | Conservation Authority as the designated approval agency for modification of floodplain, potential impact on fish habitat, proposed works in or adjacent to a watercourse, cut/fill permits and Approval under Lakes and Rivers Improvement Act. The Conservation Authority is not the approval authority for the Lakes and Rivers Improvement ct. Where there are Conservation Authority regulations in place, approval under the Lakes and Rivers Improvement Act is not required, except in cases of dams as defined in the Act. | N/A |
| <input type="checkbox"/> | Application for Certificate of Approval (CofA) under the Ontario Water Resources Act.                                                                                                                                                                                                                                                                                                                                                                                                                                               | N/A |
| <input type="checkbox"/> | Changes to Municipal Drains.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | N/A |
| <input type="checkbox"/> | Other permits (National Capital Commission, Parks Canada, Public Works and Government Services Canada, Ministry of Transportation etc.)                                                                                                                                                                                                                                                                                                                                                                                             | N/A |

#### 4.6 Conclusion Checklist

|                                     |                                                                                                                                                                               |             |
|-------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------|
| <input checked="" type="checkbox"/> | Clearly stated conclusions and recommendations                                                                                                                                | Section 5.0 |
| <input type="checkbox"/>            | Comments received from review agencies including the City of Ottawa and information on how the comments were addressed. Final sign-off from the responsible reviewing agency. |             |
| <input type="checkbox"/>            | All draft and final reports shall be signed and stamped by a professional Engineer registered in Ontario                                                                      |             |

## Robert Freel

---

**From:** Matt Wingate <mwingate@dsel.ca>  
**Sent:** November-28-12 2:35 PM  
**To:** 'Robert Freel'  
**Subject:** FW: Preconsultation 4 Iber Road

Pre-consultation notes, including engineering comments, below

---

**From:** Derek Noble [mailto:[dnoble@huntingtonproperties.ca](mailto:dnoble@huntingtonproperties.ca)]  
**Sent:** Tuesday, November 20, 2012 10:44 AM  
**To:** Matt Wingate  
**Cc:** Miguel Tremblay; Matt McElligott  
**Subject:** Fwd: Preconsultation 4 Iber Road

Matt Wingate - you should be aware of the issues below. You were not included in the distribution.

Derek D. Noble, CA  
Vice-President - Development & Construction  
Huntington Properties  
O - 613 592 1818 ext.26  
C - 613 447 4735  
[dnoble@huntingtonproperties.ca](mailto:dnoble@huntingtonproperties.ca)  
[www.huntingtonproperties.ca](http://www.huntingtonproperties.ca)

Sent from my iPhone4.

Begin forwarded message:

**From:** "Hayley, Matthew" <[Matthew.Hayley@ottawa.ca](mailto:Matthew.Hayley@ottawa.ca)>  
**Date:** 20 November, 2012 8:27:01 AM EST  
**To:** "Moore, Sean" <[Sean.Moore@ottawa.ca](mailto:Sean.Moore@ottawa.ca)>, Miguel Tremblay <[tremblay@fotenn.com](mailto:tremblay@fotenn.com)>, Derek Noble <[dnoble@huntingtonproperties.ca](mailto:dnoble@huntingtonproperties.ca)>  
**Cc:** "Young, Mark" <[Mark.Young@ottawa.ca](mailto:Mark.Young@ottawa.ca)>, "Shen, Stream" <[Stream.Shen@ottawa.ca](mailto:Stream.Shen@ottawa.ca)>, "Whittaker, Damien" <[Damien.Whittaker@ottawa.ca](mailto:Damien.Whittaker@ottawa.ca)>  
**Subject:** RE: Preconsultation 4 Iber Road

Miguel,

I know that you have Bernie working on this already but I wanted to add this to Sean's email since I didn't see it under the Required Studies List. The study is described in the OP Section 4.7.3 and pertains to the watercourse alignment and setback. The relocation of the watercourse will need to be supported by a study which meets the requirements of the OP Section 4.7.3 Policy 7 (pasted below for your convenience);

7. Where an exception to the setback is requested under Policy 6, an alternate setback will be considered by the City in consultation with the Conservation Authority on the basis of a study that addresses the following criteria: [Amendment #96, February 22, 2012]

- a. Slope of the bank and geotechnical considerations related to unstable slopes, as addressed in Council's Slope Stability Guidelines for Development Applications in the City of Ottawa, 2004;
- b. Natural vegetation and the ecological function of the setback area;
- c. The nature of the abutting water body, including the presence of a flood plain;
- d. The need to demonstrate that there will be no negative impacts on adjacent fish habitat. [OMB decision #1754, May 10, 2006]

If you have any questions please let me know.

Thanks

Matthew

Matthew Hayley  
Development Review  
Planning and Growth Management  
City of Ottawa  
100 Laurier Ave West, 4th Floor,  
Ottawa ON K1P 1J1  
Tel: 613-580-2424  
Fax: 613-580-2576

---

**From:** Moore, Sean  
**Sent:** November 19, 2012 4:35 PM  
**To:** Miguel Tremblay; Derek Noble  
**Cc:** Young, Mark; Shen, Stream; Whittaker, Damien; Hayley, Matthew  
**Subject:** RE: Preconsultation 4 Iber Road

Miguel,

Please also submit a **Planning Rationale** (4 copies) to accompany the Zoning By-law Amendment.

Thanks.

Sean.

---

**From:** Moore, Sean  
**Sent:** November 19, 2012 4:23 PM  
**To:** Miguel Tremblay; 'Derek Noble'  
**Cc:** Young, Mark; Shen, Stream; Whittaker, Damien; Hayley, Matthew  
**Subject:** Preconsultation 4 Iber Road

Miguel,

As per our pre-consultation meeting on November 15, I have summarized our meeting and added the submission requirements for your two proposed applications. If you have any questions with the below don't hesitate to contact either myself or Mark Young.

## **Site Plan**

### **Application Type:**

- Manager Approval, Public Consultation \$18,223.64
- Conservation Authority Fee \$860.00
- Design Review and Inspection Fee (depends on the amount of infrastructure/landscaping – please see application)

Site Plan Control application:

[https://ottawa.ca/online\\_services/forms/ds/Application\\_for\\_Site\\_Plan\\_Control\\_en.pdf](https://ottawa.ca/online_services/forms/ds/Application_for_Site_Plan_Control_en.pdf)

### **Required Plans:**

- Site Plan (55 copies)
- Landscape Plan (55 copies)
- Grading Plan (55 copies)
- Site Servicing Plan (55 copies)
- Architectural Elevations – full size b/w drawings (5 copies)
- Architectural Elevations - 11x17 colour (2 copies)
- Survey Plan (2 copies)
- Cd with all required plans and studies in pdf

### **Required Studies:**

- Transportation Impact Study (9 copies)
- RMA – changes to road RoW be shown on Site Plan
- Site Servicing Brief & Stormwater Management Report (6 copies)
- Geotechnical Study (4 copies)
- Erosion and Sediment Control Plan (8 copies)
- Phase 1 ESA (4 copies)
- Phase 2 ESA (4 copies) \*if identified as required from Phase 1
- Tree Conservation Report

### **Design Comments:**

- Urban Design Review Panel submission is required for the Site Plan (see link below for Agenda times and requirements)
- Link into Hazeldean Road with unit paver nodes and street furniture/lighting (see pdfs)
- Buildings to have frontage along Hazeldean Road, links to main entry's and real glazing along the street frontages

Urban Design Review Panel:

[http://ottawa.ca/en/city\\_hall/planningprojectsreports/planning/dev\\_review\\_process/urban\\_design/](http://ottawa.ca/en/city_hall/planningprojectsreports/planning/dev_review_process/urban_design/)

### **Engineering Comments:**

- Water service – a 305 mm dia. PVC water pipe exists in Fringewood Drive and Iber Road. The applicant should connect to that pipe. The applicant should not connect directly to the water main in Hazelean Road.
- Sanitary – as stated in the meeting the applicant intends to send sanitary flows to a private sanitary pumping station in Iber Road and to the Fringewood sanitary pumping station. The applicant should connect to the manhole in Fringewood- not to the pumping station directly.
- Storm – no storm pipes cross or are adjacent to the application.
- Monitoring manholes are required for both sanitary and storm sewers, as per clause 4.4.4.6 and 6.3.2 of the *Sewer Design Guidelines*, Second Edition, Document SDG002, October 2012, City of Ottawa (*Guidelines*)
- Post-development should limit flows to a runoff coefficient 'c' of 0.5 is required for stormwater quantity control, as per clause 5.4.5.2 of the *Guidelines*, or greater if documentation direction

exists. Electronic copies of the *Guidelines* are available, please contact [StandardsSection@ottawa.ca](mailto:StandardsSection@ottawa.ca)

- Quality control for stormwater runoff should be to at least 70% removal of TSS.
- Driving entrances, also referred to as private approaches, require a fee before registration.
- Please contact Charles Goulet of (Ontario) Ministry of the Environment, 613-521-3450, x246 for any requirements that the provincial agency may have.
- Exterior site lighting shall require certification by a qualified engineer confirming the design complies with the following criteria:
  1. It must be designed using only fixtures that meet the criteria for Full Cut-Off (Sharp cut-off) Classification, as recognized by the Illuminating Engineering Society of North America (IESNA or IES), and;
  2. It must result in minimal light spillage onto adjacent properties. As a guideline, 0.5 foot-candle is normally the maximum allowable spillage.

The location of the fixtures, fixture type/s (as in make, model and part number and the mounting heights) must be shown on one of the approved plans.

- Schedule E of the Official Plan of the City of Ottawa shows Iber Road as a major collector. The annexes table 1 states that collectors should have a R.O.W. width of 26m. The existing R.O.W. width is 26m

## **Zoning By-law Amendment**

### **Application Type:**

- Major, \$13,942.00
- Conservation Authority Fee \$310.00

### **Requirements:**

- Concept Plan (20 copies)

### **Comments/Issues:**

- Zoning will be submitted in early December to start the circulation process (not subject to urban design panel review)
- Site Plan will be submitted in early 2013 and the urban design panel review process will be a part of the application
- Site Plan will need to 'catch-up' to zoning to ensure provisions being requested are tailored to the site plan (i.e. setbacks from re-aligned creek will be important to work out through the site plan and incorporated in the zoning)
- Zoning must respect Employment Designation intent (ancillary uses are permitted and must be minimal or capped at a smaller size) – with primary office or other permitted land uses as the primary use within the Employment Designation.
- Zoning should use an Arterial Mainstreet designation that implements our intentions of Hazeldean Road (i.e. AM7)
- On site water course relocation needs to be further investigated to ensure it does not adversely impact the adjacent Fire Station and our Right of Way along Iber Road
- Quality treatment will be conducted through rooftop and underground storage
- Can we create one joint ditch for both the relocated watercourse and well as the city owned roadside drainage?
- Would the location of the joint ditch pose as an issue if there was in the future to be a road widening on Iber Road? (Becomes a potential additional cost that the City have to incur in the future)
- Would it be better to pipe the drainage underground?
- If the water course is relocated, the fire station to the south of the subject property would fall out of conformity with the current ZBL due an insufficient setback from waterway
- Is there a watershed study for Carp River that reduces the required setback for the fire station?
- Need to schedule meeting with RPAM to consult on the issue to determine if a reduced setback will negatively impact the fire station



- Trees on site is a part of a registered subdivision agreement as a buffer and berm
- The original intention are for the trees to act as a buffer between commercial and office uses against the neighbouring residential uses on the west side
- No longer a issue now that Huntington Property has purchased the adjacent property
- How to legally remove them as a condition within the registered subdivision agreement

Link to application:

[https://ottawa.ca/online\\_services/forms/ds/Application\\_for\\_Zoning\\_Amendment\\_en.pdf](https://ottawa.ca/online_services/forms/ds/Application_for_Zoning_Amendment_en.pdf)

Regards,

**Sean Moore** | Planner II | MCIP, RPP  
 Development Review - Suburban Services Branch  
 West Unit - Kanata, Stittsville & Barrhaven  
 Planning & Growth Management Department  
 City of Ottawa

Ph. 613.580.2424 ext. 16481

Fax 613.560.6006

[www.ottawa.ca/en/city\\_hall/planningprojectsreports/planning/](http://www.ottawa.ca/en/city_hall/planningprojectsreports/planning/)

This e-mail originates from the City of Ottawa e-mail system. Any distribution, use or copying of this e-mail or the information it contains by other than the intended recipient(s) is unauthorized. If you are not the intended recipient, please notify me at the telephone number shown above or by return e-mail and delete this communication and any copy immediately. Thank you.

Le présent courriel a été expédié par le système de courriels de la Ville d'Ottawa. Toute distribution, utilisation ou reproduction du courriel ou des renseignements qui s'y trouvent par une personne autre que son destinataire prévu est interdite. Si vous avez reçu le message par erreur, veuillez m'en aviser par téléphone (au numéro précité) ou par courriel, puis supprimer sans délai la version originale de la communication ainsi que toutes ses copies. Je vous remercie de votre collaboration.



---

---

## ***APPENDIX B***

### ***Water Supply***

---

---



---

---

***Functional Servicing and Stormwater Management Report  
For Iber Hazeldean Land Limited***

***5754 Hazeldean Road / 24 Iber Road / 5734 Hazeldean Road  
July 2019 – REV 12***

*Previously Approved Appendix B – Water Supply*

---

---



PREVIOUSLY APPROVED (D07-12-17-0186)

Water Demand Design Flows per Zoning  
 City of Ottawa - Water Distribution Guidelines, July 2010



#### Institutional / Commercial / Industrial Demand

| Property Type            | Unit Rate                 | Units  | Avg. Daily        |             | Max Day           |             | Peak Hour         |             |
|--------------------------|---------------------------|--------|-------------------|-------------|-------------------|-------------|-------------------|-------------|
|                          |                           |        | m <sup>3</sup> /d | L/min       | m <sup>3</sup> /d | L/min       | m <sup>3</sup> /d | L/min       |
| Commercial floor space   | 2.5 L/m <sup>2</sup> /d   | 10,690 | 26.73             | 18.6        | 40.1              | 27.8        | 72.2              | 50.1        |
| Office                   | 75 L/9.3m <sup>2</sup> /d |        | 0.00              | 0.0         | 0.0               | 0.0         | 0.0               | 0.0         |
| Industrial - Light       | 35,000 L/gross ha/d       |        | 0.00              | 0.0         | 0.0               | 0.0         | 0.0               | 0.0         |
| Other -Commercial        | 28,000 L/gross ha/d       |        | 0.00              | 0.0         | 0.0               | 0.0         | 0.0               | 0.0         |
| <b>Total I/CI Demand</b> |                           |        | <b>26.7</b>       | <b>18.6</b> | <b>40.1</b>       | <b>27.8</b> | <b>72.2</b>       | <b>50.1</b> |
| <b>Total Demand</b>      |                           |        | <b>26.7</b>       | <b>18.6</b> | <b>40.1</b>       | <b>27.8</b> | <b>72.2</b>       | <b>50.1</b> |

PREVIOUSLY APPROVED (D07-12-17-0186)

## Fire Flow Estimation per Fire Underwriters Survey

Water Supply For Public Fire Protection - 1999



### Fire Flow Required

#### 1. Base Requirement

$$F = 220C\sqrt{A} \text{ L/min} \quad \text{Where } F \text{ is the fire flow, } C \text{ is the Type of construction and } A \text{ is the Total floor area}$$

Type of Construction: **Non-Combustible Construction**

**C** 0.8 Type of Construction Coefficient per FUS Part II, Section 1  
**A** 2145.0 m<sup>2</sup> Total floor area based on FUS Part II section 1

|           |                                                        |
|-----------|--------------------------------------------------------|
| Fire Flow | 8151.3 L/min                                           |
|           | <b>8000.0 L/min</b> rounded to the nearest 1,000 L/min |

### Adjustments

#### 2. Reduction for Occupancy Type

**Non-Combustible** -25%

|           |                     |
|-----------|---------------------|
| Fire Flow | <b>6000.0 L/min</b> |
|-----------|---------------------|

#### 3. Reduction for Sprinkler Protection

**Sprinklered** -50%

|           |                    |
|-----------|--------------------|
| Reduction | <b>-3000 L/min</b> |
|-----------|--------------------|

#### 4. Increase for Separation Distance

|                    |     |
|--------------------|-----|
| <b>N</b> >45m      | 0%  |
| <b>S</b> 10.1m-20m | 15% |
| <b>E</b> >45m      | 0%  |
| <b>W</b> >45m      | 0%  |

|            |            |                                                    |
|------------|------------|----------------------------------------------------|
| % Increase | <b>15%</b> | value not to exceed 75% per FUS Part II, Section 4 |
|------------|------------|----------------------------------------------------|

|          |                    |
|----------|--------------------|
| Increase | <b>900.0 L/min</b> |
|----------|--------------------|

### Total Fire Flow

|           |                     |                                                                                   |
|-----------|---------------------|-----------------------------------------------------------------------------------|
| Fire Flow | 3900.0 L/min        | fire flow not to exceed 45,000 L/min nor be less than 2,000 L/min per FUS Section |
|           | <b>4000.0 L/min</b> | rounded to the nearest 1,000 L/min                                                |

#### Notes:

- Type of construction, Occupancy Type and Sprinkler Protection information provided by \_\_\_\_\_.
- Calculations based on Fire Underwriters Survey - Part II



PREVIOUSLY APPROVED (D07-12-17-0186)

## Fire Flow Estimation per Fire Underwriters Survey

Water Supply For Public Fire Protection - 1999



### Fire Flow Required

#### 1. Base Requirement

$$F = 220C\sqrt{A} \text{ L/min} \quad \text{Where } F \text{ is the fire flow, } C \text{ is the Type of construction and } A \text{ is the Total floor area}$$

Type of Construction: **Non-Combustible Construction**

**C** 0.8 Type of Construction Coefficient per FUS Part II, Section 1  
**A** 1395.0 m<sup>2</sup> Total floor area based on FUS Part II section 1

|           |                                                        |
|-----------|--------------------------------------------------------|
| Fire Flow | 6573.5 L/min                                           |
|           | <b>7000.0 L/min</b> rounded to the nearest 1,000 L/min |

### Adjustments

#### 2. Reduction for Occupancy Type

**Non-Combustible** -25%

|           |                     |
|-----------|---------------------|
| Fire Flow | <b>5250.0 L/min</b> |
|-----------|---------------------|

#### 3. Reduction for Sprinkler Protection

**Sprinklered** -50%

|           |                    |
|-----------|--------------------|
| Reduction | <b>-2625 L/min</b> |
|-----------|--------------------|

#### 4. Increase for Separation Distance

|                    |     |
|--------------------|-----|
| <b>N</b> >45m      | 0%  |
| <b>S</b> 10.1m-20m | 15% |
| <b>E</b> 10.1m-20m | 15% |
| <b>W</b> >45m      | 0%  |

|            |            |                                                    |
|------------|------------|----------------------------------------------------|
| % Increase | <b>30%</b> | value not to exceed 75% per FUS Part II, Section 4 |
|------------|------------|----------------------------------------------------|

|          |                     |
|----------|---------------------|
| Increase | <b>1575.0 L/min</b> |
|----------|---------------------|

### Total Fire Flow

|           |                     |                                                                                   |
|-----------|---------------------|-----------------------------------------------------------------------------------|
| Fire Flow | 4200.0 L/min        | fire flow not to exceed 45,000 L/min nor be less than 2,000 L/min per FUS Section |
|           | <b>4000.0 L/min</b> | rounded to the nearest 1,000 L/min                                                |

#### Notes:

- Type of construction, Occupancy Type and Sprinkler Protection information provided by \_\_\_\_\_.
- Calculations based on Fire Underwriters Survey - Part II

PREVIOUSLY APPROVED (D07-12-17-0186)

## Fire Flow Estimation per Fire Underwriters Survey

Water Supply For Public Fire Protection - 1999



### Fire Flow Required

#### 1. Base Requirement

$$F = 220C\sqrt{A} \text{ L/min} \quad \text{Where } F \text{ is the fire flow, } C \text{ is the Type of construction and } A \text{ is the Total floor area}$$

Type of Construction: **Non-Combustible Construction**

**C** 0.8 Type of Construction Coefficient per FUS Part II, Section 1  
**A** 375.0 m<sup>2</sup> Total floor area based on FUS Part II section 1

|           |                                                        |
|-----------|--------------------------------------------------------|
| Fire Flow | 3408.2 L/min                                           |
|           | <b>3000.0 L/min</b> rounded to the nearest 1,000 L/min |

### Adjustments

#### 2. Reduction for Occupancy Type

**Non-Combustible** -25%

|           |                     |
|-----------|---------------------|
| Fire Flow | <b>2250.0 L/min</b> |
|-----------|---------------------|

#### 3. Reduction for Sprinkler Protection

**Sprinklered** -50%

|           |                    |
|-----------|--------------------|
| Reduction | <b>-1125 L/min</b> |
|-----------|--------------------|

#### 4. Increase for Separation Distance

|                    |     |
|--------------------|-----|
| <b>N</b> 10.1m-20m | 15% |
| <b>S</b> >45m      | 0%  |
| <b>E</b> 10.1m-20m | 15% |
| <b>W</b> >45m      | 0%  |

|            |            |                                                    |
|------------|------------|----------------------------------------------------|
| % Increase | <b>30%</b> | value not to exceed 75% per FUS Part II, Section 4 |
|------------|------------|----------------------------------------------------|

|          |                    |
|----------|--------------------|
| Increase | <b>675.0 L/min</b> |
|----------|--------------------|

### Total Fire Flow

|           |                     |                                                                                   |
|-----------|---------------------|-----------------------------------------------------------------------------------|
| Fire Flow | 2000.0 L/min        | fire flow not to exceed 45,000 L/min nor be less than 2,000 L/min per FUS Section |
|           | <b>2000.0 L/min</b> | rounded to the nearest 1,000 L/min                                                |

#### Notes:

- Type of construction, Occupancy Type and Sprinkler Protection information provided by \_\_\_\_\_.
- Calculations based on Fire Underwriters Survey - Part II

PREVIOUSLY APPROVED (D07-12-17-0186)

## Fire Flow Estimation per Fire Underwriters Survey

Water Supply For Public Fire Protection - 1999



### Fire Flow Required

#### 1. Base Requirement

$$F = 220C\sqrt{A} \text{ L/min} \quad \text{Where } F \text{ is the fire flow, } C \text{ is the Type of construction and } A \text{ is the Total floor area}$$

Type of Construction: **Non-Combustible Construction**

**C** 0.8 Type of Construction Coefficient per FUS Part II, Section 1  
**A** 2886.0 m<sup>2</sup> Total floor area based on FUS Part II section 1

|           |                                                        |
|-----------|--------------------------------------------------------|
| Fire Flow | 9455.0 L/min                                           |
|           | <b>9000.0 L/min</b> rounded to the nearest 1,000 L/min |

### Adjustments

#### 2. Reduction for Occupancy Type

**Non-Combustible** -25%

|           |                     |
|-----------|---------------------|
| Fire Flow | <b>6750.0 L/min</b> |
|-----------|---------------------|

#### 3. Reduction for Sprinkler Protection

**Sprinklered** -50%

|           |                    |
|-----------|--------------------|
| Reduction | <b>-3375 L/min</b> |
|-----------|--------------------|

#### 4. Increase for Separation Distance

|                    |     |
|--------------------|-----|
| <b>N</b> 3.1m-10m  | 20% |
| <b>S</b> 20.1m-30m | 10% |
| <b>E</b> 20.1m-30m | 10% |
| <b>W</b> 10.1m-20m | 15% |

|            |            |                                                    |
|------------|------------|----------------------------------------------------|
| % Increase | <b>55%</b> | value not to exceed 75% per FUS Part II, Section 4 |
|------------|------------|----------------------------------------------------|

|          |                     |
|----------|---------------------|
| Increase | <b>3712.5 L/min</b> |
|----------|---------------------|

### Total Fire Flow

|           |                     |                                                                                   |
|-----------|---------------------|-----------------------------------------------------------------------------------|
| Fire Flow | 7087.5 L/min        | fire flow not to exceed 45,000 L/min nor be less than 2,000 L/min per FUS Section |
|           | <b>7000.0 L/min</b> | rounded to the nearest 1,000 L/min                                                |

#### Notes:

- Type of construction, Occupancy Type and Sprinkler Protection information provided by \_\_\_\_\_.
- Calculations based on Fire Underwriters Survey - Part II

PREVIOUSLY APPROVED (D07-12-17-0186)

## Fire Flow Estimation per Fire Underwriters Survey

Water Supply For Public Fire Protection - 1999



### Fire Flow Required

#### 1. Base Requirement

$$F = 220C\sqrt{A} \text{ L/min} \quad \text{Where } F \text{ is the fire flow, } C \text{ is the Type of construction and } A \text{ is the Total floor area}$$

Type of Construction: **Non-Combustible Construction**

**C** 0.8 Type of Construction Coefficient per FUS Part II, Section 1  
**A** 2150.0 m<sup>2</sup> Total floor area based on FUS Part II section 1

|           |                                                        |
|-----------|--------------------------------------------------------|
| Fire Flow | 8160.8 L/min                                           |
|           | <b>8000.0 L/min</b> rounded to the nearest 1,000 L/min |

### Adjustments

#### 2. Reduction for Occupancy Type

**Non-Combustible** -25%

|           |                     |
|-----------|---------------------|
| Fire Flow | <b>6000.0 L/min</b> |
|-----------|---------------------|

#### 3. Reduction for Sprinkler Protection

**Sprinklered** -50%

|           |                    |
|-----------|--------------------|
| Reduction | <b>-3000 L/min</b> |
|-----------|--------------------|

#### 4. Increase for Separation Distance

|                    |     |
|--------------------|-----|
| <b>N</b> 10.1m-20m | 15% |
| <b>S</b> >45m      | 0%  |
| <b>E</b> >45m      | 0%  |
| <b>W</b> >45m      | 0%  |

|            |            |                                                    |
|------------|------------|----------------------------------------------------|
| % Increase | <b>15%</b> | value not to exceed 75% per FUS Part II, Section 4 |
|------------|------------|----------------------------------------------------|

|          |                    |
|----------|--------------------|
| Increase | <b>900.0 L/min</b> |
|----------|--------------------|

### Total Fire Flow

|           |                     |                                                                                   |
|-----------|---------------------|-----------------------------------------------------------------------------------|
| Fire Flow | 3900.0 L/min        | fire flow not to exceed 45,000 L/min nor be less than 2,000 L/min per FUS Section |
|           | <b>4000.0 L/min</b> | rounded to the nearest 1,000 L/min                                                |

### Notes:

- Type of construction, Occupancy Type and Sprinkler Protection information provided by \_\_\_\_\_.
- Calculations based on Fire Underwriters Survey - Part II

PREVIOUSLY APPROVED (D07-12-17-0186)

## Fire Flow Estimation per Fire Underwriters Survey

Water Supply For Public Fire Protection - 1999



### Fire Flow Required

#### 1. Base Requirement

$$F = 220C\sqrt{A} \text{ L/min} \quad \text{Where } F \text{ is the fire flow, } C \text{ is the Type of construction and } A \text{ is the Total floor area}$$

Type of Construction: **Non-Combustible Construction**

**C** 0.8 Type of Construction Coefficient per FUS Part II, Section 1  
**A** 2150.0 m<sup>2</sup> Total floor area based on FUS Part II section 1

|           |                                                        |
|-----------|--------------------------------------------------------|
| Fire Flow | 8160.8 L/min                                           |
|           | <b>8000.0 L/min</b> rounded to the nearest 1,000 L/min |

### Adjustments

#### 2. Reduction for Occupancy Type

**Non-Combustible** -25%

|           |                     |
|-----------|---------------------|
| Fire Flow | <b>6000.0 L/min</b> |
|-----------|---------------------|

#### 3. Reduction for Sprinkler Protection

**Sprinklered** -50%

|           |                    |
|-----------|--------------------|
| Reduction | <b>-3000 L/min</b> |
|-----------|--------------------|

#### 4. Increase for Separation Distance

|                    |    |
|--------------------|----|
| <b>N</b> >45m      | 0% |
| <b>S</b> 30.1m-45m | 5% |
| <b>E</b> >45m      | 0% |
| <b>W</b> >45m      | 0% |

|            |           |                                                    |
|------------|-----------|----------------------------------------------------|
| % Increase | <b>5%</b> | value not to exceed 75% per FUS Part II, Section 4 |
|------------|-----------|----------------------------------------------------|

|          |                    |
|----------|--------------------|
| Increase | <b>300.0 L/min</b> |
|----------|--------------------|

### Total Fire Flow

|           |                     |                                                                                   |
|-----------|---------------------|-----------------------------------------------------------------------------------|
| Fire Flow | 3300.0 L/min        | fire flow not to exceed 45,000 L/min nor be less than 2,000 L/min per FUS Section |
|           | <b>3000.0 L/min</b> | rounded to the nearest 1,000 L/min                                                |

#### Notes:

- Type of construction, Occupancy Type and Sprinkler Protection information provided by \_\_\_\_\_.
- Calculations based on Fire Underwriters Survey - Part II

PREVIOUSLY APPROVED (D07-12-17-0186)

Boundary Conditions Unit Conversion

**Fringewood Connection (Connection 1)**

|           | Height (m) | Elevation (m) | m H <sub>2</sub> O | PSI  | kPa   |           | L/s   | L/min |
|-----------|------------|---------------|--------------------|------|-------|-----------|-------|-------|
| Max HGL   | 161.1      | 104.5         | 56.6               | 80.5 | 555.2 | Fire Flow | 116.7 | 7000  |
| Fire Flow | 157.8      | 104.5         | 53.3               | 75.8 | 522.9 |           |       |       |
| Peak Hour | 159.0      | 104.5         | 54.5               | 77.5 | 534.6 |           |       |       |

**Iber Rd Connection (Connection 2)**

|           | Height (m) | Elevation (m) | m H <sub>2</sub> O | PSI  | kPa   |           | L/s   | L/min |
|-----------|------------|---------------|--------------------|------|-------|-----------|-------|-------|
| Max HGL   | 161.2      | 103.1         | 58.1               | 82.7 | 570.0 | Fire Flow | 116.7 | 7000  |
| Fire Flow | 157.9      | 103.1         | 54.8               | 78.0 | 537.6 |           |       |       |
| Peak Hour | 158.9      | 103.1         | 55.8               | 79.4 | 547.4 |           |       |       |

**PREVIOUSLY APPROVED (D07-12-17-0186)**

**Minor Loss Coefficients**

| Fitting                       | Loss Coefficient |
|-------------------------------|------------------|
| Globe valve, fully open       | 10               |
| Angle valve, fully open       | 5                |
| Swing check valve, fully open | 2.5              |
| Gate valve, fully open        | 0.2              |
| Short-radius elbow            | 0.9              |
| Medium-radius elbow           | 0.8              |
| Long-radius elbow             | 0.6              |
| 45 degree elbow               | 0.4              |
| Closed return bend            | 2.2              |
| Standard tee - flow through   | 0.6              |
| Standard tee - flow through   | 1.8              |
| Square Entrance               | 0.5              |
| Exit                          | 1                |

\*Minor loss coefficients based on EPANET 2 USERS MANUAL, dated September 2000

**Pipe Diameter vs. "C" Factor**

| Pipe Diameter (m) | C-Factor |
|-------------------|----------|
| 150               | 100      |
| 200 to 250        | 110      |
| 300 to 600        | 120      |
| Over 600          | 130      |

**Node Pressures**

| Kpa     | Pressure (kPa) | Pressure (m H2O) |
|---------|----------------|------------------|
| Max     | 552            | 56.3             |
| Rec Max | 480            | 49.0             |
| Rec Min | 350            | 35.7             |
| Min     | 275            | 28.1             |

| Location | Average Day<br>(kPa) | Max Day + Fire<br>Flow (Fire Flow<br>at Critical Node)<br>(kPa) | Max Day + Fire<br>Flow (Fire Flow<br>at Node)<br>(kPa) | Peak Hour<br>(kPa) |
|----------|----------------------|-----------------------------------------------------------------|--------------------------------------------------------|--------------------|
| FH1      | 589.6                | 557.1                                                           | 375.4                                                  | 567.0              |
| FH3      | 586.6                | 212.9                                                           | 266.4                                                  | 566.0              |
| FH4      | 583.3                | 406.9                                                           | 275.4                                                  | 562.7              |
| FH5      | 583.5                | 473.0                                                           | 359.3                                                  | 562.9              |
| FH6      | 590.1                | 431.2                                                           | 316.9                                                  | 569.5              |

| Location | Average Day<br>(kPa) | Max Day + Fire<br>Flow<br>(kPa) | Peak Hour<br>(kPa) |
|----------|----------------------|---------------------------------|--------------------|
| 1        | 588.6                | 556.1                           | 566.0              |
| 2        | 587.6                | 555.1                           | 565.1              |
| 3        | 590.1                | 557.6                           | 567.5              |
| 4        | 589.1                | 466.8                           | 568.5              |
| 5        | 588.6                | 556.0                           | 566.0              |
| 6        | 588.6                | 454.1                           | 568.0              |
| 7        | 588.6                | 429.8                           | 568.0              |
| 8        | 587.8                | 374.7                           | 567.2              |
| 9        | 586.6                | 354.7                           | 566.0              |
| 10       | 583.3                | 406.9                           | 562.7              |
| 11       | 582.9                | 512.6                           | 562.3              |
| 12       | 578.7                | 527.1                           | 558.1              |
| 13       | 582.5                | 472.1                           | 561.9              |
| 16       | 586.6                | 554.1                           | 564.1              |
| 20       | 588.6                | 556.1                           | 566.0              |
| BLDGA    | 579.8                | 509.4                           | 559.2              |
| BLDGB    | 584.7                | 552.1                           | 562.1              |
| BLDGGB   | 587.6                | 555.0                           | 565.1              |
| BLDGC    | 581.2                | 529.6                           | 560.6              |
| BLDGD    | 587.6                | 555.1                           | 565.1              |
| BLDGG    | 587.6                | 555.1                           | 565.1              |
| FH1      | 589.6                | 557.1                           | 567.0              |
| FH3      | 586.6                | 212.9                           | 566.0              |
| FH4      | 583.3                | 406.9                           | 562.7              |
| FH5      | 583.5                | 473.0                           | 562.9              |
| FH6      | 590.1                | 431.2                           | 569.5              |

PREVIOUSLY APPROVED (D07-12-17-0186)

Adjusted Pressures at Building FFE

| Location | Average Day<br>(kPa) | Max Day + Fire<br>Flow<br>(kPa) | Peak Hour<br>(kPa) |
|----------|----------------------|---------------------------------|--------------------|
| BLDGA    | 555.7                | 485.4                           | 535.1              |
| BLDGB    | 560.6                | 528.0                           | 538.0              |
| BLDGBB   | 563.5                | 531.0                           | 541.0              |
| BLDGC    | 557.1                | 505.6                           | 536.6              |
| BLDGD    | 563.5                | 531.1                           | 541.0              |
| BLDGG    | 563.5                | 531.1                           | 541.0              |



## Boundary Conditions 5734 – 5754 Hazeldean Road, 24 Iber Road

### Information Provided

Date provided: 07 March 2018

#### Provided Information:

| Scenario             | Demand |       |
|----------------------|--------|-------|
|                      | L/min  | L/s   |
| Average Daily Demand | 19.3   | 0.3   |
| Maximum Daily Demand | 28.9   | 0.5   |
| Peak Hour            | 52     | 0.9   |
| Fire Flow Demand     | 7000   | 116.7 |

# of connections

2

### Location



## Results

### Connection 1 - Fringewood Dr.

| Demand Scenario                 | Head (m) | Pressure <sup>1</sup> (psi) |
|---------------------------------|----------|-----------------------------|
| Maximum HGL                     | 161.1    | 80.4                        |
| Peak Hour                       | 157.8    | 75.7                        |
| Max Day plus Fire (7,000 l/min) | 159.0    | 77.4                        |

<sup>1</sup> Ground Elevation = 104.56 m

### Connection 2 - Iber Rd.

| Demand Scenario                 | Head (m) | Pressure <sup>1</sup> (psi) |
|---------------------------------|----------|-----------------------------|
| Maximum HGL                     | 161.2    | 82.6                        |
| Peak Hour                       | 157.9    | 77.7                        |
| Max Day plus Fire (7,000 l/min) | 158.9    | 79.3                        |

<sup>1</sup> Ground Elevation = 103.11 m

- 1) As per the Ontario Building Code in areas that may be occupied, the static pressure at any fixture shall not exceed 552 kPa (80 psi.) Pressure control measures to be considered are as follows, in order of preference:
  - a) If possible, systems to be designed to residual pressures of 345 to 552 kPa (50 to 80 psi) in all occupied areas outside of the public right-of-way without special pressure control equipment.
  - b) Pressure reducing valves to be installed immediately downstream of the isolation valve in the home/ building, located downstream of the meter so it is owner maintained.

## Disclaimer

*The boundary condition information is based on current operation of the city water distribution system. The computer model simulation is based on the best information available at the time. The operation of the water distribution system can change on a regular basis, resulting in a variation in boundary conditions. The physical properties of watermains deteriorate over time, as such must be assumed in the absence of actual field test data. The variation in physical watermain properties can therefore alter the results of the computer model simulation. Fire Flow analysis is a reflection of available flow in the watermain; there may be additional restrictions that occur between the watermain and the hydrant that the model cannot take into account.*

# Boundary Condition for 2 Iber Rd and 5734-5754 Fringewood Dr





---

***Site Servicing and Stormwater Management Brief  
For Iber Hazeldean Land Limited***

***5754 Hazeldean Road / 24 Iber Road / 5734 Hazeldean Road  
September 2019 – REV 1***

***Proposed Amended Appendix B – Water Supply***

---



Water Demand Design Flows per Zoning  
City of Ottawa - Water Distribution Guidelines, July 2010



Institutional / Commercial / Industrial Demand

| Property Type                | Unit Rate |                        | Units  | Avg. Daily        |       | Max Day           |       | Peak Hour         |       |
|------------------------------|-----------|------------------------|--------|-------------------|-------|-------------------|-------|-------------------|-------|
|                              |           |                        |        | m <sup>3</sup> /d | L/min | m <sup>3</sup> /d | L/min | m <sup>3</sup> /d | L/min |
| Total Commercial floor space | 2.5       | L/m <sup>2</sup> /d    | 10,337 | 25.84             | 17.9  | 38.8              | 26.9  | 69.8              | 48.5  |
| Office                       | 75        | L/9.3m <sup>2</sup> /d |        | 0.00              | 0.0   | 0.0               | 0.0   | 0.0               | 0.0   |
| Industrial - Light           | 35,000    | L/gross ha/d           |        | 0.00              | 0.0   | 0.0               | 0.0   | 0.0               | 0.0   |
| Other -Commercial            | 28,000    | L/gross ha/d           |        | 0.00              | 0.0   | 0.0               | 0.0   | 0.0               | 0.0   |
| Total I/CI Demand            |           |                        |        | 25.8              | 17.9  | 38.8              | 26.9  | 69.8              | 48.5  |
| Total Demand                 |           |                        |        | 25.8              | 17.9  | 38.8              | 26.9  | 69.8              | 48.5  |

Fire Flow Estimation per Fire Underwriters Survey

Water Supply For Public Fire Protection - 1999



Fire Flow Required

1. Base Requirement

$F = 220C\sqrt{A}$

L/min      Where **F** is the fire flow, **C** is the Type of construction and **A** is the Total floor area

Type of Construction:      Non-Combustible Construction

**C**      0.8      Type of Construction Coefficient per FUS Part II, Section 1  
**A**      661.8      m<sup>2</sup>      Total floor area based on FUS Part II section 1

|           |                                                 |
|-----------|-------------------------------------------------|
| Fire Flow | 4527.7 L/min                                    |
|           | 5000.0 L/min rounded to the nearest 1,000 L/min |

Adjustments

2. Reduction for Occupancy Type

Non-Combustible      -25%

|           |              |
|-----------|--------------|
| Fire Flow | 3750.0 L/min |
|-----------|--------------|

3. Reduction for Sprinkler Protection

Sprinklered - Supervised      -50%

|           |             |
|-----------|-------------|
| Reduction | -1875 L/min |
|-----------|-------------|

4. Increase for Separation Distance

| Cons. of Exposed Wall | S.D       | Lw | Ha | LH | EC |                            |
|-----------------------|-----------|----|----|----|----|----------------------------|
| N Non-Combustible     | 20.1m-30m | 0  | 0  | 0  | 0  | 8%                         |
| S Non-Combustible     | >45m      | 0  | 0  | 0  | 0  | 0%                         |
| E Non-Combustible     | >45m      | 0  | 0  | 0  | 0  | 0%                         |
| W Non-Combustible     | >45m      | 0  | 0  | 0  | 0  | 0%                         |
| % Increase            |           |    |    |    |    | 8% value not to exceed 75% |

|          |             |
|----------|-------------|
| Increase | 300.0 L/min |
|----------|-------------|

Lw = Length of the Exposed Wall  
Ha = number of storeys of the adjacent structure. Max 5 stories  
LH = Length-height factor of exposed wall. Value rounded up.  
EC = Exposure Charge

Total Fire Flow

|           |              |                                                                                                                      |
|-----------|--------------|----------------------------------------------------------------------------------------------------------------------|
| Fire Flow | 2175.0 L/min | fire flow not to exceed 45,000 L/min nor be less than 2,000 L/min per FUS Section rounded to the nearest 1,000 L/min |
|           | 2000.0 L/min |                                                                                                                      |

Notes:

- Type of construction, Occupancy Type and Sprinkler Protection information provided by \_\_\_\_\_.
- Calculations based on Fire Underwriters Survey - Part II



Minor Loss Coefficients

| Fitting                       | Loss Coefficient |
|-------------------------------|------------------|
| Globe valve, fully open       | 10               |
| Angle valve, fully open       | 5                |
| Swing check valve, fully open | 2.5              |
| Gate valve, fully open        | 0.2              |
| Short-radius elbow            | 0.9              |
| Medium-radius elbow           | 0.8              |
| Long-radius elbow             | 0.6              |
| 45 degree elbow               | 0.4              |
| Closed return bend            | 2.2              |
| Standard tee - flow through   | 0.6              |
| Standard tee - flow through   | 1.8              |
| Square Entrance               | 0.5              |
| Exit                          | 1                |

\*Minor loss coefficients based on EPANET 2 USERS MANUAL, dated September 2000

Pipe Diameter vs. "C" Factor

| Pipe Diameter (m) | C-Factor |
|-------------------|----------|
| 150               | 100      |
| 200 to 250        | 110      |
| 300 to 600        | 120      |
| Over 600          | 130      |

Node Pressures

| Kpa     | Pressure (kPa) | Pressure (m H2O) |
|---------|----------------|------------------|
| Max     | 552            | 56.3             |
| Rec Max | 480            | 49.0             |
| Rec Min | 350            | 35.7             |
| Min     | 275            | 28.1             |

| Location | Average Day (kPa) | Max Day + Fire Flow (Fire Flow at Critical Node) (kPa) | Max Day + Fire Flow (Fire Flow at Node) (kPa) | Peak Hour (kPa) |
|----------|-------------------|--------------------------------------------------------|-----------------------------------------------|-----------------|
| FH1      | 589.6             | 557.1                                                  | 317.4                                         | 567.0           |
| FH3      | 586.6             | 212.9                                                  | 212.9                                         | 566.0           |
| FH4      | 583.3             | 406.9                                                  | 224.8                                         | 562.7           |
| FH5      | 583.5             | 473.0                                                  | 312.3                                         | 562.9           |
| FH6      | 590.1             | 431.2                                                  | 257.9                                         | 569.5           |


| Location | Average Day (kPa) | Max Day + Fire Flow (kPa) | Peak Hour (kPa) |
|----------|-------------------|---------------------------|-----------------|
| 1        | 588.6             | 556.1                     | 566.0           |
| 2        | 587.6             | 555.1                     | 565.1           |
| 3        | 590.1             | 557.6                     | 567.5           |
| 4        | 589.1             | 466.8                     | 568.5           |
| 5        | 588.6             | 556.0                     | 566.0           |
| 6        | 588.6             | 454.1                     | 568.0           |
| 7        | 588.6             | 429.8                     | 568.0           |
| 8        | 587.8             | 374.7                     | 567.2           |
| 9        | 586.6             | 354.7                     | 566.0           |
| 10       | 583.3             | 406.9                     | 562.7           |
| 11       | 582.9             | 512.5                     | 562.3           |
| 12       | 578.7             | 527.1                     | 558.1           |
| 13       | 582.5             | 472.1                     | 561.9           |
| 16       | 586.6             | 554.1                     | 564.1           |
| 20       | 588.6             | 556.1                     | 566.0           |
| BLDGA    | 579.8             | 509.3                     | 559.2           |
| BLDGB    | 584.7             | 552.1                     | 562.1           |
| BLDG BB  | 587.6             | 555.0                     | 565.1           |
| BLDGC    | 581.2             | 529.6                     | 560.6           |
| BLDGD    | 587.6             | 555.1                     | 565.1           |
| BLDGG    | 587.6             | 555.1                     | 565.1           |
| FH1      | 589.6             | 557.1                     | 567.0           |
| FH3      | 586.6             | 212.9                     | 566.0           |
| FH4      | 583.3             | 406.9                     | 562.7           |
| FH5      | 583.5             | 473.0                     | 562.9           |
| FH6      | 590.1             | 431.2                     | 569.5           |

Adjusted Pressures at Building FFE

| Location | Average Day<br>(kPa) | Max Day + Fire<br>Flow<br>(kPa) | Peak Hour<br>(kPa) |
|----------|----------------------|---------------------------------|--------------------|
| BLDGA    | 555.7                | 485.3                           | 535.1              |
| BLDGB    | 560.6                | 528.0                           | 538.0              |
| BLDGBB   | 563.5                | 531.0                           | 541.0              |
| BLDGC    | 557.1                | 505.6                           | 536.6              |
| BLDGD    | 563.5                | 531.1                           | 541.0              |
| BLDGG    | 563.5                | 531.1                           | 541.0              |

WATERMAIN ANALYSIS - AVERAGE DAY DEMAND

Day 1, 12:00 AM





```

*****
*                               E P A N E T                               *
*                               Hydraulic and Water Quality                 *
*                               Analysis for Pipe Networks                   *
*                               Version 2.0                                 *
*****

```

Input File: 2019-09-20\_558\_AVERAGE.net

Link - Node Table:

| Link ID | Start Node | End Node | Length m | Diameter mm |
|---------|------------|----------|----------|-------------|
| 1       | J01        | 1        | 92.30    | 200         |
| 2       | FH1        | 1        | 6.1      | 150         |
| 5       | 3          | 2        | 54.33    | 200         |
| 12      | 7          | 8        | 40.1     | 150         |
| 16      | 9          | 10       | 54.9     | 150         |
| 17      | FH4        | 10       | 2.6      | 150         |
| 18      | 10         | 13       | 55       | 150         |
| 19      | FH5        | 13       | 8        | 150         |
| 25      | 11         | BLDGA    | 35.5     | 150         |
| 26      | 11         | 12       | 6.97     | 200         |
| 14      | 8          | 9        | 8        | 150         |
| 10      | 7          | 6        | 9.4      | 150         |
| 4       | 13         | 4        | 44.6     | 200         |
| 6       | 4          | 6        | 39.6     | 200         |
| 7       | 6          | 5        | 39       | 200         |
| 9       | 5          | 16       | 20       | 150         |
| 11      | 16         | BLDGB    | 48       | 150         |
| 13      | 16         | BLDGGB   | 4        | 150         |
| 20      | 7          | FH6      | 4        | 150         |
| 27      | 9          | FH3      | 4        | 150         |
| 28      | 2          | BLDGD    | 13.7     | 150         |
| 29      | 5          | 2        | 17.88    | 200         |
| 30      | 11         | 13       | 40.5     | 200         |
| 31      | BLDGG      | 20       | 10.3     | 150         |
| 32      | 1          | 20       | 4.81     | 200         |
| 33      | 20         | 3        | 4.39     | 200         |
| 3       | 12         | BLDGC    | 7.49     | 200         |
| 8       | J02        | 12       | 7.49     | 200         |



| Node<br>ID | Demand<br>LPM | Head<br>m | Pressure<br>m | Quality        |
|------------|---------------|-----------|---------------|----------------|
| FH1        | 0.00          | 161.20    | 60.10         | 0.00           |
| 1          | 0.00          | 161.20    | 60.00         | 0.00           |
| 3          | 0.00          | 161.20    | 60.15         | 0.00           |
| 4          | 0.00          | 161.10    | 60.05         | 0.00           |
| 6          | 0.00          | 161.10    | 60.00         | 0.00           |
| FH6        | 0.00          | 161.10    | 60.15         | 0.00           |
| 7          | 0.00          | 161.10    | 60.00         | 0.00           |
| 8          | 0.00          | 161.10    | 59.92         | 0.00           |
| FH3        | 0.00          | 161.10    | 59.80         | 0.00           |
| FH4        | 0.00          | 161.10    | 59.46         | 0.00           |
| 10         | 0.00          | 161.10    | 59.46         | 0.00           |
| FH5        | 0.00          | 161.10    | 59.48         | 0.00           |
| 13         | 0.00          | 161.10    | 59.38         | 0.00           |
| 11         | 0.00          | 161.10    | 59.42         | 0.00           |
| BLDGA      | 3.57          | 161.10    | 59.10         | 0.00           |
| 9          | 0.00          | 161.10    | 59.80         | 0.00           |
| 2          | 0.00          | 161.20    | 59.90         | 0.00           |
| 5          | 0.00          | 161.20    | 60.00         | 0.00           |
| BLDGB      | 2.65          | 161.20    | 59.60         | 0.00           |
| BLDGBB     | 0.72          | 161.20    | 59.90         | 0.00           |
| 16         | 0.00          | 161.20    | 59.80         | 0.00           |
| BLDGC      | 5.61          | 161.10    | 59.25         | 0.00           |
| BLDGD      | 1.29          | 161.20    | 59.90         | 0.00           |
| BLDGG      | 4.11          | 161.20    | 59.90         | 0.00           |
| 20         | 0.00          | 161.20    | 60.00         | 0.00           |
| 12         | 0.00          | 161.10    | 58.99         | 0.00           |
| J01        | -20.36        | 161.20    | 0.00          | 0.00 Reservoir |
| J02        | 2.40          | 161.10    | 0.00          | 0.00 Reservoir |

#### Link Results:

| Link<br>ID | Flow<br>LPM | Velocity<br>m/s | Unit<br>Headloss<br>m/km | Status |
|------------|-------------|-----------------|--------------------------|--------|
| 1          | 20.36       | 0.01            | 0.00                     | Open   |
| 2          | 0.00        | 0.00            | 0.00                     | Open   |
| 5          | 16.25       | 0.01            | 0.00                     | Open   |
| 12         | 2.63        | 0.00            | 0.00                     | Open   |
| 16         | 2.63        | 0.00            | 0.00                     | Open   |
| 17         | 0.00        | 0.00            | 0.00                     | Open   |
| 18         | 2.63        | 0.00            | 0.00                     | Open   |
| 19         | 0.00        | 0.00            | 0.00                     | Open   |
| 25         | 3.57        | 0.00            | 0.00                     | Open   |
| 26         | 8.01        | 0.00            | 0.00                     | Open   |
| 14         | 2.63        | 0.00            | 0.00                     | Open   |
| 10         | -2.63       | 0.00            | 0.00                     | Open   |

|   |       |      |      |      |
|---|-------|------|------|------|
| 4 | -8.95 | 0.00 | 0.00 | Open |
|---|-------|------|------|------|



Page 3

Link Results: (continued)

| Link<br>ID | Flow<br>LPM | Velocity<br>m/s | Unit Headloss<br>m/km | Status |
|------------|-------------|-----------------|-----------------------|--------|
| 6          | -8.95       | 0.00            | 0.00                  | Open   |
| 7          | -11.59      | 0.01            | 2.55                  | Open   |
| 9          | 3.37        | 0.00            | 0.00                  | Open   |
| 11         | 2.65        | 0.00            | 0.00                  | Open   |
| 13         | 0.72        | 0.00            | 0.00                  | Open   |
| 20         | 0.00        | 0.00            | 0.00                  | Open   |
| 27         | 0.00        | 0.00            | 0.00                  | Open   |
| 28         | 1.29        | 0.00            | 0.00                  | Open   |
| 29         | -14.96      | 0.01            | 0.00                  | Open   |
| 30         | -11.58      | 0.01            | 0.00                  | Open   |
| 31         | -4.11       | 0.00            | 0.00                  | Open   |
| 32         | 20.36       | 0.01            | 0.00                  | Open   |
| 33         | 16.25       | 0.01            | 0.00                  | Open   |
| 3          | 5.61        | 0.00            | 0.00                  | Open   |
| 8          | -2.40       | 0.00            | 0.00                  | Open   |








WATERMAIN ANALYSIS - MAX DAY + FF DEMAND

Day 1, 12:00 AM





```

*****
*                               E P A N E T                               *
*                               Hydraulic and Water Quality                 *
*                               Analysis for Pipe Networks                   *
*                               Version 2.0                                 *
*****

```

Input File: 2019-09-20\_558\_MAX \_ FF.net

Link - Node Table:

| Link ID | Start Node | End Node | Length m | Diameter mm |
|---------|------------|----------|----------|-------------|
| 1       | J01        | 1        | 92.30    | 200         |
| 2       | FH1        | 1        | 6.1      | 150         |
| 5       | 3          | 2        | 54.33    | 200         |
| 12      | 7          | 8        | 40.1     | 150         |
| 16      | 9          | 10       | 54.9     | 150         |
| 17      | FH4        | 10       | 2.6      | 150         |
| 18      | 10         | 13       | 55       | 150         |
| 19      | FH5        | 13       | 8        | 150         |
| 25      | 11         | BLDGA    | 35.5     | 150         |
| 26      | 11         | 12       | 6.97     | 200         |
| 14      | 8          | 9        | 8        | 150         |
| 10      | 7          | 6        | 9.4      | 150         |
| 4       | 13         | 4        | 44.6     | 200         |
| 6       | 4          | 6        | 39.6     | 200         |
| 7       | 6          | 5        | 39       | 200         |
| 9       | 5          | 16       | 20       | 150         |
| 11      | 16         | BLDGB    | 48       | 150         |
| 13      | 16         | BLDGBB   | 4        | 150         |
| 20      | 7          | FH6      | 4        | 150         |
| 27      | 9          | FH3      | 4        | 150         |
| 28      | 2          | BLDGD    | 13.7     | 150         |
| 29      | 5          | 2        | 17.88    | 200         |
| 30      | 11         | 13       | 40.5     | 200         |
| 31      | BLDGG      | 20       | 10.3     | 150         |
| 32      | 1          | 20       | 4.81     | 200         |
| 33      | 20         | 3        | 4.39     | 200         |
| 3       | 12         | BLDGC    | 7.49     | 200         |
| 8       | J02        | 12       | 7.49     | 200         |



| Node<br>ID | Demand<br>LPM | Head<br>m | Pressure<br>m | Quality        |
|------------|---------------|-----------|---------------|----------------|
| FH1        | 0.00          | 157.89    | 56.79         | 0.00           |
| 1          | 0.00          | 157.89    | 56.69         | 0.00           |
| 3          | 0.00          | 157.89    | 56.84         | 0.00           |
| 4          | 0.00          | 148.63    | 47.58         | 0.00           |
| 6          | 0.00          | 147.39    | 46.29         | 0.00           |
| FH6        | 0.00          | 144.91    | 43.96         | 0.00           |
| 7          | 0.00          | 144.91    | 43.81         | 0.00           |
| 8          | 0.00          | 139.38    | 38.20         | 0.00           |
| FH3        | 7000.00       | 123.00    | 21.70         | 0.00           |
| FH4        | 0.00          | 143.12    | 41.48         | 0.00           |
| 10         | 0.00          | 143.12    | 41.48         | 0.00           |
| FH5        | 0.00          | 149.84    | 48.22         | 0.00           |
| 13         | 0.00          | 149.84    | 48.12         | 0.00           |
| 11         | 0.00          | 153.92    | 52.24         | 0.00           |
| BLDGA      | 5.36          | 153.92    | 51.92         | 0.00           |
| 9          | 0.00          | 137.46    | 36.16         | 0.00           |
| 2          | 0.00          | 157.89    | 56.59         | 0.00           |
| 5          | 0.00          | 157.88    | 56.68         | 0.00           |
| BLDGB      | 3.98          | 157.88    | 56.28         | 0.00           |
| BLDGBB     | 1.08          | 157.88    | 56.58         | 0.00           |
| 16         | 0.00          | 157.88    | 56.48         | 0.00           |
| BLDGC      | 8.41          | 155.84    | 53.99         | 0.00           |
| BLDGD      | 1.93          | 157.89    | 56.59         | 0.00           |
| BLDGG      | 6.16          | 157.89    | 56.59         | 0.00           |
| 20         | 0.00          | 157.89    | 56.69         | 0.00           |
| 12         | 0.00          | 155.84    | 53.73         | 0.00           |
| J01        | -156.37       | 157.90    | 0.00          | 0.00 Reservoir |
| J02        | -6870.55      | 157.80    | 0.00          | 0.00 Reservoir |

#### Link Results:

| Link<br>ID | Flow<br>LPM | Velocity<br>m/s | Unit Headloss<br>m/km | Status |
|------------|-------------|-----------------|-----------------------|--------|
| 1          | 156.37      | 0.08            | 0.08                  | Open   |
| 2          | 0.00        | 0.00            | 0.00                  | Open   |
| 5          | 150.21      | 0.08            | 0.08                  | Open   |
| 12         | 3755.06     | 3.54            | 137.90                | Open   |
| 16         | -3244.94    | 3.06            | 103.14                | Open   |
| 17         | 0.00        | 0.00            | 0.00                  | Open   |
| 18         | -3244.94    | 3.06            | 122.22                | Open   |
| 19         | 0.00        | 0.00            | 0.00                  | Open   |
| 25         | 5.36        | 0.01            | 0.00                  | Open   |
| 26         | -6862.14    | 3.64            | 274.64                | Open   |
| 14         | 3755.06     | 3.54            | 240.15                | Open   |
| 10         | -3755.06    | 3.54            | 264.28                | Open   |

|   |         |      |       |      |
|---|---------|------|-------|------|
| 4 | 3611.84 | 1.92 | 27.17 | Open |
|---|---------|------|-------|------|



Page 3


Link Results: (continued)

| Link ID | Flow LPM | Velocity m/s | Unit Headloss m/km | Status |
|---------|----------|--------------|--------------------|--------|
| 6       | 3611.84  | 1.92         | 31.26              | Open   |
| 7       | -143.22  | 0.08         | 268.99             | Open   |
| 9       | 5.06     | 0.00         | 0.00               | Open   |
| 11      | 3.98     | 0.00         | 0.00               | Open   |
| 13      | 1.08     | 0.00         | 0.00               | Open   |
| 20      | 0.00     | 0.00         | 0.00               | Open   |
| 27      | 7000.00  | 6.60         | 3615.77            | Open   |
| 28      | 1.93     | 0.00         | 0.00               | Open   |
| 29      | -148.28  | 0.08         | 0.10               | Open   |
| 30      | 6856.78  | 3.64         | 100.77             | Open   |
| 31      | -6.16    | 0.01         | 0.00               | Open   |
| 32      | 156.37   | 0.08         | 0.22               | Open   |
| 33      | 150.21   | 0.08         | 0.25               | Open   |
| 3       | 8.41     | 0.00         | 0.00               | Open   |
| 8       | 6870.55  | 3.64         | 261.81             | Open   |



WATERMAIN ANALYSIS - PEAK HOUR DEMAND

Day 1, 12:00 AM







```

*****
*                               E P A N E T                               *
*                               Hydraulic and Water Quality                 *
*                               Analysis for Pipe Networks                   *
*                               Version 2.0                                 *
*****

```

Input File: 2019-09-20\_558\_PEAK-HOUR.net

Link - Node Table:

| Link ID | Start Node | End Node | Length m | Diameter mm |
|---------|------------|----------|----------|-------------|
| 1       | J01        | 1        | 92.30    | 200         |
| 2       | FH1        | 1        | 6.1      | 150         |
| 5       | 3          | 2        | 54.33    | 200         |
| 12      | 7          | 8        | 40.1     | 150         |
| 16      | 9          | 10       | 54.9     | 150         |
| 17      | FH4        | 10       | 2.6      | 150         |
| 18      | 10         | 13       | 55       | 150         |
| 19      | FH5        | 13       | 8        | 150         |
| 25      | 11         | BLDGA    | 35.5     | 150         |
| 26      | 11         | 12       | 6.97     | 200         |
| 14      | 8          | 9        | 8        | 150         |
| 10      | 7          | 6        | 9.4      | 150         |
| 4       | 13         | 4        | 44.6     | 200         |
| 6       | 4          | 6        | 39.6     | 200         |
| 7       | 6          | 5        | 39       | 200         |
| 9       | 5          | 16       | 20       | 150         |
| 11      | 16         | BLDGB    | 48       | 150         |
| 13      | 16         | BLDGGB   | 4        | 150         |
| 20      | 7          | FH6      | 4        | 150         |
| 27      | 9          | FH3      | 4        | 150         |
| 28      | 2          | BLDGD    | 13.7     | 150         |
| 29      | 5          | 2        | 17.88    | 200         |
| 30      | 11         | 13       | 40.5     | 200         |
| 31      | BLDGG      | 20       | 10.3     | 150         |
| 32      | 1          | 20       | 4.81     | 200         |
| 33      | 20         | 3        | 4.39     | 200         |
| 3       | 12         | BLDGC    | 7.49     | 200         |
| 8       | J02        | 12       | 7.49     | 200         |



| Node<br>ID | Demand<br>LPM | Head<br>m | Pressure<br>m | Quality        |
|------------|---------------|-----------|---------------|----------------|
| FH1        | 0.00          | 158.90    | 57.80         | 0.00           |
| 1          | 0.00          | 158.90    | 57.70         | 0.00           |
| 3          | 0.00          | 158.90    | 57.85         | 0.00           |
| 4          | 0.00          | 159.00    | 57.95         | 0.00           |
| 6          | 0.00          | 159.00    | 57.90         | 0.00           |
| FH6        | 0.00          | 159.00    | 58.05         | 0.00           |
| 7          | 0.00          | 159.00    | 57.90         | 0.00           |
| 8          | 0.00          | 159.00    | 57.82         | 0.00           |
| FH3        | 0.00          | 159.00    | 57.70         | 0.00           |
| FH4        | 0.00          | 159.00    | 57.36         | 0.00           |
| 10         | 0.00          | 159.00    | 57.36         | 0.00           |
| FH5        | 0.00          | 159.00    | 57.38         | 0.00           |
| 13         | 0.00          | 159.00    | 57.28         | 0.00           |
| 11         | 0.00          | 159.00    | 57.32         | 0.00           |
| BLDGA      | 9.64          | 159.00    | 57.00         | 0.00           |
| 9          | 0.00          | 159.00    | 57.70         | 0.00           |
| 2          | 0.00          | 158.90    | 57.60         | 0.00           |
| 5          | 0.00          | 158.90    | 57.70         | 0.00           |
| BLDGB      | 7.17          | 158.90    | 57.30         | 0.00           |
| BLDGBB     | 1.94          | 158.90    | 57.60         | 0.00           |
| 16         | 0.00          | 158.90    | 57.50         | 0.00           |
| BLDGC      | 15.14         | 159.00    | 57.15         | 0.00           |
| BLDGD      | 3.47          | 158.90    | 57.60         | 0.00           |
| BLDGG      | 11.10         | 158.90    | 57.60         | 0.00           |
| 20         | 0.00          | 158.90    | 57.70         | 0.00           |
| 12         | 0.00          | 159.00    | 56.89         | 0.00           |
| J01        | -12.08        | 158.90    | 0.00          | 0.00 Reservoir |
| J02        | -36.39        | 159.00    | 0.00          | 0.00 Reservoir |

#### Link Results:

| Link<br>ID | Flow<br>LPM | Velocity<br>m/s | Unit<br>Headloss<br>m/km | Status |
|------------|-------------|-----------------|--------------------------|--------|
| 1          | 12.08       | 0.01            | 0.00                     | Open   |
| 2          | 0.00        | 0.00            | 0.00                     | Open   |
| 5          | 0.98        | 0.00            | 0.00                     | Open   |
| 12         | -2.64       | 0.00            | 0.00                     | Open   |
| 16         | -2.64       | 0.00            | 0.00                     | Open   |
| 17         | 0.00        | 0.00            | 0.00                     | Open   |
| 18         | -2.64       | 0.00            | 0.00                     | Open   |
| 19         | 0.00        | 0.00            | 0.00                     | Open   |
| 25         | 9.64        | 0.01            | 0.00                     | Open   |
| 26         | -21.25      | 0.01            | 0.01                     | Open   |
| 14         | -2.64       | 0.00            | 0.00                     | Open   |
| 10         | 2.64        | 0.00            | 0.00                     | Open   |

|   |      |      |      |      |
|---|------|------|------|------|
| 4 | 8.97 | 0.00 | 0.00 | Open |
|---|------|------|------|------|



Page 3

Link Results: (continued)

| Link ID | Flow LPM | Velocity m/s | Unit Headloss m/km | Status |
|---------|----------|--------------|--------------------|--------|
| 6       | 8.97     | 0.00         | 0.00               | Open   |
| 7       | 11.60    | 0.01         | 2.56               | Open   |
| 9       | 9.11     | 0.01         | 0.00               | Open   |
| 11      | 7.17     | 0.01         | 0.00               | Open   |
| 13      | 1.94     | 0.00         | 0.00               | Open   |
| 20      | 0.00     | 0.00         | 0.00               | Open   |
| 27      | 0.00     | 0.00         | 0.00               | Open   |
| 28      | 3.47     | 0.00         | 0.00               | Open   |
| 29      | 2.49     | 0.00         | 0.00               | Open   |
| 30      | 11.61    | 0.01         | 0.00               | Open   |
| 31      | -11.10   | 0.01         | 0.01               | Open   |
| 32      | 12.08    | 0.01         | 0.00               | Open   |
| 33      | 0.98     | 0.00         | 0.00               | Open   |
| 3       | 15.14    | 0.01         | 0.00               | Open   |
| 8       | 36.39    | 0.02         | 0.01               | Open   |



---

---

## ***APPENDIX C***

### ***Wastewater Collection***

---

---



---

---

***Functional Servicing and Stormwater Management Report  
For Iber Hazeldean Land Limited***

***5754 Hazeldean Road / 24 Iber Road / 5734 Hazeldean Road  
July 2019 – REV 12***

*Previously Approved Appendix C – Wastewater Collection*

---

---





**Iber Hazeldean Land Limited**  
**5734-5754 Hazelden Road/24 Iber Road**  
**Proposed Site Conditions**

**PREVIOUSLY APPROVED (D07-12-17-0186)**

**Wastewater Design Flows per Unit Count**  
**City of Ottawa Sewer Design Guidelines, 2004**



**Site Area** 4.437 ha

**Extraneous Flow Allowances**

|                                      |                 |
|--------------------------------------|-----------------|
| <b>Infiltration / Inflow (Dry)</b>   | <b>0.22 L/s</b> |
| <b>Infiltration / Inflow (Wet)</b>   | <b>1.24 L/s</b> |
| <b>Infiltration / Inflow (Total)</b> | <b>1.46 L/s</b> |

**Institutional / Commercial / Industrial Contributions**

| <b>Property Type</b>    | <b>Unit Rate</b>      | <b>No. of Units</b> | <b>Avg Wastewater (L/s)</b> |
|-------------------------|-----------------------|---------------------|-----------------------------|
| Commercial floor space* | 5 L/m <sup>2</sup> /d | 10,690              | 1.24                        |
| Hospitals               | 900 L/bed/d           |                     | 0.00                        |
| School                  | 70 L/student/d        |                     | 0.00                        |
| Industrial - Light**    | 35,000 L/gross ha/d   |                     | 0.00                        |
| Industrial - Heavy**    | 55,000 L/gross ha/d   |                     | 0.00                        |

**Average I/C/I Flow** **1.24**

**Peak Institutional / Commercial Flow** 1.86

**Peak Industrial Flow\*\*** 0.00

**Peak I/C/I Flow** **1.86**

\* assuming a 12 hour commercial operation

\*\* peak industrial flow per City of Ottawa Sewer Design Guidelines Appendix 4B

|                                                      |                 |
|------------------------------------------------------|-----------------|
| <b>Total Estimated Average Dry Weather Flow Rate</b> | <b>1.46 L/s</b> |
| <b>Total Estimated Peak Dry Weather Flow Rate</b>    | <b>2.08 L/s</b> |
| <b>Total Estimated Peak Wet Weather Flow Rate</b>    | <b>3.32 L/s</b> |



ON-SITE SANITARY SEWER CALCULATION SHEET

PREVIOUSLY APPROVED (D07-12-17-0186)

PROJECT: Iber Hazeldean Land Limited  
LOCATION: 5734-5754 Hazeldean Road/24 Iber Road  
FILE REF: 12-558  
DATE: 29-Mar-19

DESIGN PARAMETERS  
Commercial floor space  
Industrial - Light

5 Lm<sup>2</sup>/d  
35,000 L/gross ha/d

Peak Fact Res. Per Harmons: Min = 2.0, Max =4.0  
Peak Fact. Comm. 1.5  
Peak Fact. Industrial 7

Infiltration / Inflow  
Min. Pipe Velocity  
Max. Pipe Velocity  
Manning's N

0.33 L/s/ha  
0.60 m/s full flowing  
3.00 m/s full flowing  
0.013



| Location                        |                    | Residential Area and Population |           |                         |        |        |      |                      |                 |                        |                        | Commercial              |                        | Institutional           |           | Industrial |                        | Infiltration    |                         | Pipe Data        |          |           |            |                                          |       |                |                        |                |
|---------------------------------|--------------------|---------------------------------|-----------|-------------------------|--------|--------|------|----------------------|-----------------|------------------------|------------------------|-------------------------|------------------------|-------------------------|-----------|------------|------------------------|-----------------|-------------------------|------------------|----------|-----------|------------|------------------------------------------|-------|----------------|------------------------|----------------|
| Drainage Area ID                | Sanitary Structure |                                 | Area (ha) | Number of Units by type |        |        | Pop. | Cumulative Area (ha) | Peak. Fact. (-) | Q <sub>res</sub> (L/s) | Area (m <sup>2</sup> ) | Accu. (m <sup>2</sup> ) | Area (m <sup>2</sup> ) | Accu. (m <sup>2</sup> ) | Area (ha) | Accu. (ha) | Q <sub>C-H</sub> (L/s) | Total Area (ha) | Infiltration Flow (L/s) | Total Flow (L/s) | D/A (mm) | Slope (%) | Length (m) | A <sub>hydraulic</sub> (m <sup>2</sup> ) | R (m) | Velocity (m/s) | Q <sub>cap</sub> (L/s) | Q / Q full (-) |
|                                 | Up Stream MH       | Down Stream MH                  |           | Singles                 | Semi's | Town's |      |                      |                 |                        |                        |                         |                        |                         |           |            |                        |                 |                         |                  |          |           |            |                                          |       |                |                        |                |
| Building A<br>Building C        | SAN4B              | SAN4                            | 4.437     |                         |        |        | 0.0  | 4.437                | 0.0             | 0.00                   | 4724.0                 |                         | 0.00                   |                         |           | 0.00       | 0.41                   | 4.437           | 1.464                   | 1.87             | 250      | 0.23      | 39.9       | 0.049                                    | 0.063 | 0.58           | 28.5                   | 0.07           |
|                                 | SAN4               | SAN4A                           | 0.000     |                         |        |        | 0.0  | 0.000                | 0.0             | 0.00                   | 4724.0                 |                         | 0.00                   |                         | 0.00      | 0.00       | 0.41                   | 0.000           | 0.000                   | 0.41             | 250      | 0.27      | 33.0       | 0.049                                    | 0.063 | 0.63           | 30.9                   | 0.01           |
|                                 | SAN4               | SAN3                            | 0.000     |                         |        |        | 0.0  | 4.437                | 0.0             | 0.00                   | 4724.0                 |                         | 0.00                   |                         | 0.00      | 0.00       | 0.41                   | 0.000           | 1.464                   | 1.87             | 250      | 0.27      | 75.0       | 0.049                                    | 0.063 | 0.63           | 30.9                   | 0.06           |
|                                 | SAN3               | SAN2                            | 0.000     |                         |        |        | 0.0  | 0.000                | 0.0             | 0.00                   | 4724.0                 |                         | 0.00                   |                         | 0.00      | 0.00       | 0.41                   | 0.000           | 0.000                   | 0.41             | 250      | 0.25      | 36.1       | 0.049                                    | 0.063 | 0.61           | 29.7                   | 0.01           |
| Building B, BB<br>Building D, G | SAN5               | SAN2                            | 0.000     |                         |        |        | 0.0  | 0.000                | 0.0             | 0.00                   | 1736.0                 |                         | 0.00                   |                         |           | 0.00       | 0.15                   | 0.000           | 0.000                   | 0.15             | 250      | 0.25      | 61.5       | 0.049                                    | 0.063 | 0.61           | 29.7                   | 0.01           |
|                                 | SAN6               | SAN2                            | 0.000     |                         |        |        | 0.0  | 0.000                | 0.0             | 0.00                   | 4230.0                 |                         | 0.00                   |                         |           | 0.00       | 0.37                   | 0.000           | 0.000                   | 0.37             | 250      | 0.24      | 42.0       | 0.049                                    | 0.063 | 0.59           | 29.1                   | 0.01           |
|                                 | SAN2               | SAN1                            | 0.000     |                         |        |        | 0.0  | 0.000                | 0.0             | 0.00                   | 10690.0                |                         | 0.00                   |                         |           | 0.00       | 0.93                   | 0.000           | 0.000                   | 0.93             | 250      | 0.25      | 77.4       | 0.049                                    | 0.063 | 0.61           | 29.7                   | 0.03           |
|                                 | SAN1               | SAN7                            | 0.000     |                         |        |        | 0.0  | 0.000                | 0.0             | 0.00                   | 10690.0                |                         | 0.00                   |                         |           | 0.00       | 0.93                   | 0.000           | 0.000                   | 0.93             | 250      | 1.00      | 14.3       | 0.049                                    | 0.063 | 1.21           | 59.5                   | 0.02           |

\*\*Refer to drawing Fig-2, Flow based on existing zoning





CLIENT: Iber Hazeldean Land Limited  
LOCATION: Iber Road Sanitary Extension  
FILE REF: 12-558  
DATE: 28-Mar-19

DESIGN PARAMETERS

Avg. Daily Flow Res. 280 L/p/d  
Avg. Daily Flow Comm. 50,000 L/ha/d  
Avg. Daily Flow Instit. 50,000 L/ha/d  
Avg. Daily Flow Indust. 35,000 L/ha/d

Peak Fact Res. Per Hammons: Min = 2.0, Max =4.0  
Peak Fact. Comm. 1.5  
Peak Fact. Instit. 1  
Peak Fact. Indust. per MOE graph

Infiltration / Inflow  
Min. Pipe Velocity  
Max. Pipe Velocity  
Mannings N

0.33 L/s/ha  
0.60 m/s full flowing  
3.00 m/s full flowing  
0.013



| Location |          | Residential Area and Population |              |                            |        | Commercial |                            | Institutional        |                           | Industrial   |               | Infiltration |               | Pipe Data                 |                       |                               |                        |             |              |               |                                             |          |                   |                           |                   |
|----------|----------|---------------------------------|--------------|----------------------------|--------|------------|----------------------------|----------------------|---------------------------|--------------|---------------|--------------|---------------|---------------------------|-----------------------|-------------------------------|------------------------|-------------|--------------|---------------|---------------------------------------------|----------|-------------------|---------------------------|-------------------|
| Area ID  | Up       | Down                            | Area<br>(ha) | Number of Units<br>by type |        | Pop.       | Cumulative<br>Area<br>(ha) | Peak<br>Fact.<br>(-) | Q <sub>res</sub><br>(L/s) | Area<br>(ha) | Accu.<br>(ha) | Area<br>(ha) | Accu.<br>(ha) | Q <sub>C+H</sub><br>(L/s) | Total<br>Area<br>(ha) | Infiltration<br>Flow<br>(L/s) | Total<br>Flow<br>(L/s) | DIA<br>(mm) | Slope<br>(%) | Length<br>(m) | A <sub>hydraulic</sub><br>(m <sup>2</sup> ) | R<br>(m) | Velocity<br>(m/s) | Q <sub>cap</sub><br>(L/s) | Q / Q full<br>(-) |
|          |          |                                 |              | Singles                    | Semi's |            |                            |                      |                           |              |               |              |               |                           |                       |                               |                        |             |              |               |                                             |          |                   |                           |                   |
| S5,S6    | FUT.SAN8 | SAN7                            | 2.410        |                            |        | 0.0        | 2.410                      | 0.0                  | 4.00                      | 0.00         | 0.00          | 0.00         | 2.41          | 2.41                      | 2.0                   | 2.410                         | 2.410                  | 2.75        | 250          | 0.50          | 41.9                                        | 0.049    | 0.063             | 42.0                      | 0.07              |
| S1,S2    | SAN7     | EX.MH3A                         | 6.677        |                            |        | 0.0        | 9.087                      | 0.0                  | 4.00                      | 0.00         | 1.07          | 0.00         | 2.24          | 4.65                      | 4.7                   | 9.087                         | 9.087                  | 7.69        | 250          | 0.50          | 42.1                                        | 0.049    | 0.063             | 42.0                      | 0.18              |
| S3,S4    | EX.MH3A  | EX.MH4A                         | 1.449        |                            |        | 0.0        | 10.536                     | 0.0                  | 4.00                      | 0.00         | 0.00          | 0.00         | 1.45          | 6.10                      | 4.9                   | 10.536                        | 10.536                 | 8.42        | 250          | 0.28          | 40.0                                        | 0.049    | 0.063             | 31.5                      | 0.27              |

\*Commercial Peaking Factor and Infiltration/Inflow from Technical Bulletin ISTB-2018-01.  
\*\*EX.MH3A to EX.MH4A Per As Built 1313-28 dated June 2009 by Novatech Engineering Consultants Ltd.

Refer to drawing SAN-1 for Sanitary Drainage Area Plan indicated by the Sanitary Extension Design Brief prepared by DSEL dated November 16, 2018 and included in Appendix C for reference.



---

***Site Servicing and Stormwater Management Brief  
For Iber Hazeldean Land Limited***

***5754 Hazeldean Road / 24 Iber Road / 5734 Hazeldean Road  
September 2019 – REV 1***

***Proposed Amended Appendix C – Wastewater Collection***

---





**Wastewater Design Flows per Unit Count**  
**City of Ottawa Sewer Design Guidelines, 2004**



**Site Area** 4.437 ha

**Extraneous Flow Allowances**

|                                      |                 |
|--------------------------------------|-----------------|
| <b>Infiltration / Inflow (Dry)</b>   | <b>0.22 L/s</b> |
| <b>Infiltration / Inflow (Wet)</b>   | <b>1.24 L/s</b> |
| <b>Infiltration / Inflow (Total)</b> | <b>1.46 L/s</b> |

**Institutional / Commercial / Industrial Contributions**

| <b>Property Type</b>    | <b>Unit Rate</b>      | <b>No. of Units</b> | <b>Avg Wastewater (L/s)</b> |
|-------------------------|-----------------------|---------------------|-----------------------------|
| Commercial floor space* | 5 L/m <sup>2</sup> /d | 10,337              | 1.20                        |
| Hospitals               | 900 L/bed/d           |                     | 0.00                        |
| School                  | 70 L/student/d        |                     | 0.00                        |
| Industrial - Light**    | 35,000 L/gross ha/d   |                     | 0.00                        |
| Industrial - Heavy**    | 55,000 L/gross ha/d   |                     | 0.00                        |

**Average I/C/I Flow** **1.20**

**Peak Institutional / Commercial Flow** 1.79

**Peak Industrial Flow\*\*** 0.00

**Peak I/C/I Flow** **1.79**

\* assuming a 12 hour commercial operation

\*\* peak industrial flow per City of Ottawa Sewer Design Guidelines Appendix 4B

|                                                      |                 |
|------------------------------------------------------|-----------------|
| <b>Total Estimated Average Dry Weather Flow Rate</b> | <b>1.42 L/s</b> |
| <b>Total Estimated Peak Dry Weather Flow Rate</b>    | <b>2.02 L/s</b> |
| <b>Total Estimated Peak Wet Weather Flow Rate</b>    | <b>3.26 L/s</b> |



PROJECT: Unity Square Limited Partnership  
LOCATION: 5734-5754 Hazeldean Road/24 Iber Road  
FILE REF: 19-1133  
DATE: 20-Sep-19

DESIGN PARAMETERS

Commercial floor space  
Industrial - Light

Peak Fact Res. Per Harmons: Min = 2.0, Max =4.0  
Peak Fact. Comm. 1.5  
Peak Fact. Industrial 7

Infiltration / Inflow  
Min. Pipe Velocity  
Max. Pipe Velocity  
Manning's N

0.33 L/s/ha  
0.60 m/s full flowing  
3.00 m/s full flowing  
0.013



| Location         |                    |                | Residential Area and Population |                 |        |        |      |                      |                | Commercial             |                        | Institutional                |           | Industrial      |                          | Infiltration    |                         | Pipe Data        |          |           |            |                                          |       |                |                        |                |      |
|------------------|--------------------|----------------|---------------------------------|-----------------|--------|--------|------|----------------------|----------------|------------------------|------------------------|------------------------------|-----------|-----------------|--------------------------|-----------------|-------------------------|------------------|----------|-----------|------------|------------------------------------------|-------|----------------|------------------------|----------------|------|
| Drainage Area ID | Sanitary Structure |                | Area (ha)                       | Number of Units |        |        | Pop. | Cumulative Area (ha) | Peak Fact. (-) | Q <sub>res</sub> (L/s) | Area (m <sup>2</sup> ) | Accu. Area (m <sup>2</sup> ) | Area (ha) | Accu. Area (ha) | Q <sub>C+I+I</sub> (L/s) | Total Area (ha) | Infiltration Flow (L/s) | Total Flow (L/s) | DIA (mm) | Slope (%) | Length (m) | A <sub>hydraulic</sub> (m <sup>2</sup> ) | R (m) | Velocity (m/s) | Q <sub>cap</sub> (L/s) | Q / Q full (-) |      |
|                  | Stream MH Up       | Stream MH Down |                                 | Singles         | Semi's | Town's |      |                      |                |                        |                        |                              |           |                 |                          |                 |                         |                  |          |           |            |                                          |       |                |                        |                |      |
| Building A       |                    | SAN4B          | 4.437                           |                 |        |        | 0.0  | 4.437                | 0.0            | 0.00                   |                        | 0.00                         |           | 0.00            | 0.41                     | 4.437           | 4.437                   | 1.464            | 1.87     | 250       | 0.23       |                                          | 0.049 |                | 0.58                   | 28.5           | 0.07 |
|                  |                    | SAN4           | 0.000                           |                 |        |        | 0.0  | 0.000                | 0.0            | 0.00                   |                        | 0.00                         |           | 0.00            | 0.41                     | 0.000           | 0.000                   | 0.000            | 0.41     | 250       | 0.27       |                                          | 0.049 |                | 0.63                   | 30.9           | 0.01 |
|                  |                    | SAN4A          | 0.000                           |                 |        |        | 0.0  | 4.437                | 0.0            | 0.00                   |                        | 4724.0                       |           | 0.00            | 0.41                     | 0.000           | 4.437                   | 1.464            | 1.87     | 250       | 0.27       |                                          | 0.049 |                | 0.63                   | 30.9           | 0.06 |
|                  |                    | SAN3           | 0.000                           |                 |        |        | 0.0  | 0.000                | 0.0            | 0.00                   |                        | 0.00                         |           | 0.00            | 0.41                     | 0.000           | 0.000                   | 0.000            | 0.41     | 250       | 0.25       |                                          | 0.049 |                | 0.61                   | 29.7           | 0.01 |
|                  |                    | SAN2           |                                 |                 |        |        |      |                      |                |                        |                        |                              |           |                 |                          |                 |                         |                  |          |           |            |                                          |       |                |                        |                |      |
| Building B, BB   |                    | SAN5           | 0.000                           |                 |        |        | 0.0  | 0.000                | 0.0            | 0.00                   |                        | 0.00                         |           | 0.00            | 0.15                     | 0.000           | 0.000                   | 0.000            | 0.15     | 250       | 0.25       |                                          | 0.049 |                | 0.61                   | 29.7           | 0.01 |
|                  |                    | SAN6           |                                 |                 |        |        |      |                      |                |                        |                        |                              |           |                 |                          |                 |                         |                  |          |           |            |                                          |       |                |                        |                |      |
|                  |                    | SAN2           | 0.000                           |                 |        |        | 0.0  | 0.000                | 0.0            | 0.00                   |                        | 0.00                         |           | 0.00            | 0.23                     | 0.000           | 0.000                   | 0.000            | 0.23     | 250       | 0.24       |                                          | 0.049 |                | 0.59                   | 29.1           | 0.01 |
|                  |                    | SAN2           |                                 |                 |        |        |      |                      |                |                        |                        |                              |           |                 |                          |                 |                         |                  |          |           |            |                                          |       |                |                        |                |      |
|                  |                    | SAN1           | 0.000                           |                 |        |        | 0.0  | 0.000                | 0.0            | 0.00                   |                        | 0.00                         |           | 0.00            | 0.79                     | 0.000           | 0.000                   | 0.000            | 0.79     | 250       | 0.25       |                                          | 0.049 |                | 0.61                   | 29.7           | 0.03 |
|                  |                    | SAN7           | 0.000                           |                 |        |        | 0.0  | 0.000                | 0.0            | 0.00                   |                        | 0.00                         |           | 0.00            | 0.79                     | 0.000           | 0.000                   | 0.000            | 0.79     | 250       | 1.00       |                                          | 0.049 |                | 1.21                   | 59.5           | 0.01 |

\*\*Refer to drawing Fig-2. Flow based on existing zoning



---

---

***APPENDIX D***

***Stormwater Management***

---

---



---

---

***Functional Servicing and Stormwater Management Report  
For Iber Hazeldean Land Limited***

***5754 Hazeldean Road / 24 Iber Road / 5734 Hazeldean Road  
July 2019 – REV 12***

*Previously Approved Appendix D – Stormwater Management*

---

---





PREVIOUSLY APPROVED (D07-12-17-0186)

**Estimated Peak Stormwater Flow Rate**  
City of Ottawa Sewer Design Guidelines, 2004



**Existing Drainage Area Characteristics**

|                      |                                         |
|----------------------|-----------------------------------------|
| <b>Area</b>          | 4.44 ha                                 |
| <b>C</b>             | 0.33 Rational Method runoff coefficient |
| <b>t<sub>c</sub></b> | 21.4 min                                |

**Rational Method Coefficient**

|             | <b>Imp.</b> | <b>Perv.</b> | <b>Total</b> |
|-------------|-------------|--------------|--------------|
| <b>Area</b> | 0.301       | 4.136        | 4.437        |
| <b>C*</b>   | 0.7         | 0.3          | 0.33         |

**Estimated Peak Flow**

|          | <b>2-year</b> | <b>5-year</b> | <b>100-year</b> |
|----------|---------------|---------------|-----------------|
| <b>i</b> | 49.9          | 67.4          | 115.0 mm/hr     |
| <b>Q</b> | 201.3         | 271.6         | 463.6 L/s       |

\* C value calculated as a composite value based on existing site soil conditions and topography.  
value derived using Table 5.7 Runoff Coefficients for Various Soil Conditions from the Ottawa Sewer Design Guidelines,

**Drainage Basin Characteristics**

|                 |        |
|-----------------|--------|
| <b>Area ID</b>  |        |
| <b>A (ha)</b>   | 4.44   |
| <b>L (m)</b>    | 232    |
| <b>Up Elev</b>  | 104.44 |
| <b>Dn Elev</b>  | 101.71 |
| <b>S (%)</b>    | 1.2    |
| <b>CN (-)</b>   | 83     |
| <b>Tc (min)</b> | 21.4   |

Time of Concentration per SCS lag equation

$$t_c = \frac{100L^{0.8} \left[ \left( \frac{1000}{CN} \right) - 9 \right]^{0.7}}{1900S^{0.5}}$$

L, length in ft

CN, SCS runoff curve number

S, average watershed slope in (%)

**PREVIOUSLY APPROVED (D07-12-17-0186)**

Stormwater - Proposed Development  
City of Ottawa Sewer Design Guidelines, 2012



**Target Flow Rate**

|           |                                         | 5-year                  |              | 100-year                     |                              |
|-----------|-----------------------------------------|-------------------------|--------------|------------------------------|------------------------------|
|           |                                         | t <sub>c</sub><br>(min) | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>actual</sub><br>(L/s) |
| Site Area | 4.44 ha                                 |                         |              |                              |                              |
| C         | 0.74 Rational Method runoff coefficient | 21.4                    | 67.4         | 271.6                        | 115.0                        |
|           |                                         |                         |              |                              | 463.6                        |

**Estimated Post Development Peak Flow from Unattenuated Areas**

Area ID U1  
Total Area 0.679 ha  
C 0.24 Rational Method runoff coefficient

| 5-year                  |              |                              |                               |                              |                                          | 100-year     |                              |                               |                              |                                          |
|-------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|
| t <sub>c</sub><br>(min) | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) |
| 15.1                    | 83.2         | 37.3                         | 37.3                          | 0.0                          | 0.0                                      | 142.4        | 79.7                         | 79.7                          | 0.0                          | 0.0                                      |

Area ID U2  
Total Area 0.079 ha  
C 0.59 Rational Method runoff coefficient

| 5-year                  |              |                              |                               |                              |                                          | 100-year     |                              |                               |                              |                                          |
|-------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|
| t <sub>c</sub><br>(min) | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) |
| 15.1                    | 83.2         | 10.6                         | 10.6                          | 0.0                          | 0.0                                      | 142.4        | 22.7                         | 22.7                          | 0.0                          | 0.0                                      |

Area ID U3  
Total Area 0.015 ha  
C 0.90 Rational Method runoff coefficient

| 5-year                  |              |                              |                               |                              |                                          | 100-year     |                              |                               |                              |                                          |
|-------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|
| t <sub>c</sub><br>(min) | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) |
| 15.1                    | 83.2         | 3.2                          | 3.2                           | 0.0                          | 0.0                                      | 142.4        | 6.1                          | 6.1                           | 0.0                          | 0.0                                      |

**PREVIOUSLY APPROVED (D07-12-17-0186)**

**Estimated Post Development Storage Requirement**

|                           |                                                      |
|---------------------------|------------------------------------------------------|
| <b>Building ID</b>        | <b>BLDG A</b>                                        |
| <b>Roof Area</b>          | 0.190 ha                                             |
| <b>Avail Storage Area</b> | 0.180                                                |
| <b>C</b>                  | 0.90 Rational Method runoff coefficient              |
| <b>t<sub>c</sub></b>      | 10 min, t <sub>c</sub> at outlet without restriction |

*Note: Rational Method Coefficient "C" increased by 25% for 100-year calculations*

**Estimated Number of Roof Drains**

|                              |                                                                         |
|------------------------------|-------------------------------------------------------------------------|
| <b>Building Length</b>       | 86.6                                                                    |
| <b>Building Width</b>        | 22.3                                                                    |
| <b>Number of Drains</b>      | 9                                                                       |
| <b>m<sup>2</sup> / Drain</b> | 200.1 max 232.25m <sup>2</sup> /notch as recommended by Zurn for Ottawa |

| Roof Top Rating Curve per Zurn Model Z-105-5 |                   |                   |                    |                    |                   |                       |
|----------------------------------------------|-------------------|-------------------|--------------------|--------------------|-------------------|-----------------------|
| d                                            | A                 | V <sub>acc</sub>  | V <sub>avail</sub> | Q <sub>notch</sub> | Q <sub>roof</sub> | V <sub>drawdown</sub> |
| (m)                                          | (m <sup>2</sup> ) | (m <sup>3</sup> ) | (m <sup>3</sup> )  | (L/s)              | (L/s)             | (hr)                  |
| 0.000                                        | 0                 | 0.0               | 0.0                | 0.00               | 0.00              | 0.00                  |
| 0.025                                        | 112.6             | 0.9               | 0.9                | 0.38               | 3.42              | 0.08                  |
| 0.050                                        | 450.3             | 6.6               | 7.5                | 0.77               | 6.93              | 0.34                  |
| 0.075                                        | 1013.1            | 17.8              | 25.3               | 1.14               | 10.26             | 0.82                  |
| 0.100                                        | 1801.0            | 34.7              | 60.0               | 1.52               | 13.68             | 1.53                  |
| 0.125                                        | 1801.0            | 45.0              | 105.1              | 1.90               | 17.10             | 2.26                  |
| 0.150                                        | 1801.0            | 45.0              | 150.1              | 2.28               | 20.52             | 2.87                  |

\* Assumes one notch opening per drain, assumes maximum slope of 10cm

| t <sub>c</sub><br>(min) | 5-year       |                              |                               |                              |                                          | 100-year     |                              |                               |                              |                                          |
|-------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|
|                         | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) |
| 10                      | 104.2        | 49.4                         | 10.5                          | 38.9                         | 23.3                                     | 178.6        | 94.0                         | 13.8                          | 80.2                         | 48.1                                     |
| 15                      | 83.6         | 39.6                         | 10.5                          | 29.1                         | 26.2                                     | 142.9        | 75.3                         | 13.8                          | 61.4                         | 55.3                                     |
| 20                      | 70.3         | 33.3                         | 10.5                          | 22.8                         | 27.4                                     | 120.0        | 63.2                         | 13.8                          | 49.3                         | 59.2                                     |
| 25                      | 60.9         | 28.9                         | 10.5                          | 18.4                         | 27.6                                     | 103.8        | 54.7                         | 13.8                          | 40.8                         | 61.3                                     |
| 30                      | 53.9         | 25.6                         | 10.5                          | 15.1                         | 27.1                                     | 91.9         | 48.4                         | 13.8                          | 34.5                         | 62.2                                     |
| 35                      | 48.5         | 23.0                         | 10.5                          | 12.5                         | 26.3                                     | 82.6         | 43.5                         | 13.8                          | 29.6                         | 62.2                                     |
| 40                      | 44.2         | 20.9                         | 10.5                          | 10.5                         | 25.1                                     | 75.1         | 39.6                         | 13.8                          | 25.7                         | 61.7                                     |
| 45                      | 40.6         | 19.3                         | 10.5                          | 8.8                          | 23.7                                     | 69.1         | 36.4                         | 13.8                          | 22.5                         | 60.8                                     |
| 50                      | 37.7         | 17.8                         | 10.5                          | 7.4                          | 22.1                                     | 64.0         | 33.7                         | 13.8                          | 19.8                         | 59.5                                     |
| 55                      | 35.1         | 16.6                         | 10.5                          | 6.2                          | 20.3                                     | 59.6         | 31.4                         | 13.8                          | 17.6                         | 57.9                                     |
| 60                      | 32.9         | 15.6                         | 10.5                          | 5.1                          | 18.5                                     | 55.9         | 29.4                         | 13.8                          | 15.6                         | 56.1                                     |
| 65                      | 31.0         | 14.7                         | 10.5                          | 4.2                          | 16.5                                     | 52.6         | 27.7                         | 13.8                          | 13.9                         | 54.1                                     |
| 70                      | 29.4         | 13.9                         | 10.5                          | 3.4                          | 14.4                                     | 49.8         | 26.2                         | 13.8                          | 12.4                         | 52.0                                     |
| 75                      | 27.9         | 13.2                         | 10.5                          | 2.7                          | 12.3                                     | 47.3         | 24.9                         | 13.8                          | 11.0                         | 49.7                                     |
| 80                      | 26.6         | 12.6                         | 10.5                          | 2.1                          | 10.1                                     | 45.0         | 23.7                         | 13.8                          | 9.8                          | 47.3                                     |
| 85                      | 25.4         | 12.0                         | 10.5                          | 1.5                          | 7.9                                      | 43.0         | 22.6                         | 13.8                          | 8.8                          | 44.7                                     |
| 90                      | 24.3         | 11.5                         | 10.5                          | 1.0                          | 5.6                                      | 41.1         | 21.6                         | 13.8                          | 7.8                          | 42.1                                     |
| 95                      | 23.3         | 11.0                         | 10.5                          | 0.6                          | 3.2                                      | 39.4         | 20.8                         | 13.8                          | 6.9                          | 39.4                                     |
| 100                     | 22.4         | 10.6                         | 10.5                          | 0.1                          | 0.8                                      | 37.9         | 20.0                         | 13.8                          | 6.1                          | 36.7                                     |
| 105                     | 21.6         | 10.2                         | 10.2                          | 0.0                          | 0.0                                      | 36.5         | 19.2                         | 13.8                          | 5.4                          | 33.8                                     |
| 110                     | 20.8         | 9.9                          | 9.9                           | 0.0                          | 0.0                                      | 35.2         | 18.5                         | 13.8                          | 4.7                          | 31.0                                     |

|                                       |                           |                                         |                           |
|---------------------------------------|---------------------------|-----------------------------------------|---------------------------|
| <b>5-year Q<sub>roof</sub></b>        | <b>10.48 L/s</b>          | <b>100-year Q<sub>roof</sub></b>        | <b>13.85 L/s</b>          |
| <b>5-year Max. Storage Required</b>   | <b>27.6 m<sup>3</sup></b> | <b>100-year Max. Storage Required</b>   | <b>62.2 m<sup>3</sup></b> |
| <b>5-year Storage Depth</b>           | <b>0.077 m</b>            | <b>100-year Storage Depth</b>           | <b>0.101 m</b>            |
| <b>5-year Estimated Drawdown Time</b> | <b>0.87 hr</b>            | <b>100-year Estimated Drawdown Time</b> | <b>1.56 hr</b>            |

**PREVIOUSLY APPROVED (D07-12-17-0186)**

|                    |                                                      |
|--------------------|------------------------------------------------------|
| Building ID        | BLDG B                                               |
| Roof Area          | 0.140 ha                                             |
| Avail Storage Area | 0.133                                                |
| C                  | 0.90 Rational Method runoff coefficient              |
| t <sub>c</sub>     | 10 min, t <sub>c</sub> at outlet without restriction |

*Note: Rational Method Coefficient "C" increased by 25% for 100-year calculations*

**Estimated Number of Roof Drains**

|                        |                                                                         |
|------------------------|-------------------------------------------------------------------------|
| Building Length        | 58.0                                                                    |
| Building Width         | 24.0                                                                    |
| Number of Drains       | 6                                                                       |
| m <sup>2</sup> / Drain | 222.3 max 232.25m <sup>2</sup> /notch as recommended by Zurn for Ottawa |

| Roof Top Rating Curve per Zurn Model Z-105-5 |                   |                   |                    |                    |                   |                       |
|----------------------------------------------|-------------------|-------------------|--------------------|--------------------|-------------------|-----------------------|
| d                                            | A                 | V <sub>acc</sub>  | V <sub>avail</sub> | Q <sub>notch</sub> | Q <sub>roof</sub> | V <sub>drawdown</sub> |
| (m)                                          | (m <sup>2</sup> ) | (m <sup>3</sup> ) | (m <sup>3</sup> )  | (L/s)              | (L/s)             | (hr)                  |
| 0.000                                        | 0                 | 0.0               | 0.0                | 0.00               | 0.00              | 0.00                  |
| 0.025                                        | 83.4              | 0.7               | 0.7                | 0.38               | 2.28              | 0.08                  |
| 0.050                                        | 333.5             | 4.9               | 5.6                | 0.77               | 4.62              | 0.38                  |
| 0.075                                        | 750.3             | 13.2              | 18.8               | 1.14               | 6.84              | 0.91                  |
| 0.100                                        | 1333.9            | 25.7              | 44.5               | 1.52               | 9.12              | 1.70                  |
| 0.125                                        | 1333.9            | 33.3              | 77.8               | 1.90               | 11.40             | 2.51                  |
| 0.150                                        | 1333.9            | 33.3              | 111.2              | 2.28               | 13.68             | 3.19                  |

\* Assumes one notch opening per drain, assumes maximum slope of 10cm

| t <sub>c</sub><br>(min) | 5-year       |                              |                               |                              |                                          | 100-year     |                              |                               |                              |                                          |
|-------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|
|                         | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) |
| 10                      | 104.2        | 36.6                         | 7.1                           | 29.5                         | 17.7                                     | 178.6        | 69.6                         | 9.4                           | 60.3                         | 36.2                                     |
| 15                      | 83.6         | 29.3                         | 7.1                           | 22.3                         | 20.0                                     | 142.9        | 55.7                         | 9.4                           | 46.4                         | 41.7                                     |
| 20                      | 70.3         | 24.7                         | 7.1                           | 17.6                         | 21.1                                     | 120.0        | 46.8                         | 9.4                           | 37.4                         | 44.9                                     |
| 25                      | 60.9         | 21.4                         | 7.1                           | 14.3                         | 21.4                                     | 103.8        | 40.5                         | 9.4                           | 31.1                         | 46.7                                     |
| 30                      | 53.9         | 18.9                         | 7.1                           | 11.9                         | 21.3                                     | 91.9         | 35.8                         | 9.4                           | 26.5                         | 47.6                                     |
| 35                      | 48.5         | 17.0                         | 7.1                           | 10.0                         | 20.9                                     | 82.6         | 32.2                         | 9.4                           | 22.8                         | 48.0                                     |
| 40                      | 44.2         | 15.5                         | 7.1                           | 8.4                          | 20.2                                     | 75.1         | 29.3                         | 9.4                           | 19.9                         | 47.9                                     |
| 45                      | 40.6         | 14.3                         | 7.1                           | 7.2                          | 19.4                                     | 69.1         | 26.9                         | 9.4                           | 17.6                         | 47.4                                     |
| 50                      | 37.7         | 13.2                         | 7.1                           | 6.1                          | 18.4                                     | 64.0         | 24.9                         | 9.4                           | 15.6                         | 46.8                                     |
| 55                      | 35.1         | 12.3                         | 7.1                           | 5.3                          | 17.3                                     | 59.6         | 23.3                         | 9.4                           | 13.9                         | 45.9                                     |
| 60                      | 32.9         | 11.6                         | 7.1                           | 4.5                          | 16.1                                     | 55.9         | 21.8                         | 9.4                           | 12.4                         | 44.8                                     |
| 65                      | 31.0         | 10.9                         | 7.1                           | 3.8                          | 14.9                                     | 52.6         | 20.5                         | 9.4                           | 11.2                         | 43.6                                     |
| 70                      | 29.4         | 10.3                         | 7.1                           | 3.2                          | 13.6                                     | 49.8         | 19.4                         | 9.4                           | 10.1                         | 42.2                                     |
| 75                      | 27.9         | 9.8                          | 7.1                           | 2.7                          | 12.2                                     | 47.3         | 18.4                         | 9.4                           | 9.1                          | 40.8                                     |
| 80                      | 26.6         | 9.3                          | 7.1                           | 2.2                          | 10.8                                     | 45.0         | 17.5                         | 9.4                           | 8.2                          | 39.3                                     |
| 85                      | 25.4         | 8.9                          | 7.1                           | 1.8                          | 9.3                                      | 43.0         | 16.8                         | 9.4                           | 7.4                          | 37.7                                     |
| 90                      | 24.3         | 8.5                          | 7.1                           | 1.4                          | 7.8                                      | 41.1         | 16.0                         | 9.4                           | 6.7                          | 36.0                                     |
| 95                      | 23.3         | 8.2                          | 7.1                           | 1.1                          | 6.3                                      | 39.4         | 15.4                         | 9.4                           | 6.0                          | 34.3                                     |
| 100                     | 22.4         | 7.9                          | 7.1                           | 0.8                          | 4.7                                      | 37.9         | 14.8                         | 9.4                           | 5.4                          | 32.5                                     |
| 105                     | 21.6         | 7.6                          | 7.1                           | 0.5                          | 3.1                                      | 36.5         | 14.2                         | 9.4                           | 4.9                          | 30.7                                     |
| 110                     | 20.8         | 7.3                          | 7.1                           | 0.2                          | 1.5                                      | 35.2         | 13.7                         | 9.4                           | 4.4                          | 28.8                                     |

|                                |                     |                                  |                     |
|--------------------------------|---------------------|----------------------------------|---------------------|
| 5-year Q <sub>roof</sub>       | 7.08 L/s            | 100-year Q <sub>roof</sub>       | 9.36 L/s            |
| 5-year Max. Storage Required   | 21.4 m <sup>3</sup> | 100-year Max. Storage Required   | 48.0 m <sup>3</sup> |
| 5-year Storage Depth           | 0.078 m             | 100-year Storage Depth           | 0.103 m             |
| 5-year Estimated Drawdown Time | 1.00 hr             | 100-year Estimated Drawdown Time | 1.78 hr             |

**PREVIOUSLY APPROVED (D07-12-17-0186)**

|                    |                                                      |
|--------------------|------------------------------------------------------|
| Building ID        | BLDG BB                                              |
| Roof Area          | 0.041 ha                                             |
| Avail Storage Area | 0.039                                                |
| C                  | 0.90 Rational Method runoff coefficient              |
| t <sub>c</sub>     | 10 min, t <sub>c</sub> at outlet without restriction |

*Note: Rational Method Coefficient "C" increased by 25% for 100-year calculations*

**Estimated Number of Roof Drains**

|                        |                                                                         |
|------------------------|-------------------------------------------------------------------------|
| Building Length        | 15.5                                                                    |
| Building Width         | 24.0                                                                    |
| Number of Drains       | 2                                                                       |
| m <sup>2</sup> / Drain | 194.7 max 232.25m <sup>2</sup> /notch as recommended by Zurn for Ottawa |

| Roof Top Rating Curve per Zurn Model Z-105-5 |                   |                   |                    |                    |                   |                       |
|----------------------------------------------|-------------------|-------------------|--------------------|--------------------|-------------------|-----------------------|
| d                                            | A                 | V <sub>acc</sub>  | V <sub>avail</sub> | Q <sub>notch</sub> | Q <sub>roof</sub> | V <sub>drawdown</sub> |
| (m)                                          | (m <sup>2</sup> ) | (m <sup>3</sup> ) | (m <sup>3</sup> )  | (L/s)              | (L/s)             | (hr)                  |
| 0.000                                        | 0                 | 0.0               | 0.0                | 0.00               | 0.00              | 0.00                  |
| 0.025                                        | 24.3              | 0.2               | 0.2                | 0.38               | 0.76              | 0.07                  |
| 0.050                                        | 97.3              | 1.4               | 1.6                | 0.77               | 1.54              | 0.33                  |
| 0.075                                        | 219.0             | 3.9               | 5.5                | 1.14               | 2.28              | 0.80                  |
| 0.100                                        | 389.3             | 7.5               | 13.0               | 1.52               | 3.04              | 1.49                  |
| 0.125                                        | 389.3             | 9.7               | 22.7               | 1.90               | 3.80              | 2.20                  |
| 0.150                                        | 389.3             | 9.7               | 32.4               | 2.28               | 4.56              | 2.79                  |

\* Assumes one notch opening per drain, assumes maximum slope of 10cm

| t <sub>c</sub><br>(min) | 5-year       |                              |                               |                              |                                          | 100-year     |                              |                               |                              |                                          |
|-------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|
|                         | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) |
| 10                      | 104.2        | 10.7                         | 2.3                           | 8.4                          | 5.0                                      | 178.6        | 20.3                         | 3.1                           | 17.3                         | 10.4                                     |
| 15                      | 83.6         | 8.6                          | 2.3                           | 6.2                          | 5.6                                      | 142.9        | 16.3                         | 3.1                           | 13.2                         | 11.9                                     |
| 20                      | 70.3         | 7.2                          | 2.3                           | 4.9                          | 5.9                                      | 120.0        | 13.7                         | 3.1                           | 10.6                         | 12.7                                     |
| 25                      | 60.9         | 6.2                          | 2.3                           | 3.9                          | 5.9                                      | 103.8        | 11.8                         | 3.1                           | 8.8                          | 13.1                                     |
| 30                      | 53.9         | 5.5                          | 2.3                           | 3.2                          | 5.8                                      | 91.9         | 10.5                         | 3.1                           | 7.4                          | 13.3                                     |
| 35                      | 48.5         | 5.0                          | 2.3                           | 2.7                          | 5.6                                      | 82.6         | 9.4                          | 3.1                           | 6.3                          | 13.3                                     |
| 40                      | 44.2         | 4.5                          | 2.3                           | 2.2                          | 5.3                                      | 75.1         | 8.6                          | 3.1                           | 5.5                          | 13.2                                     |
| 45                      | 40.6         | 4.2                          | 2.3                           | 1.8                          | 5.0                                      | 69.1         | 7.9                          | 3.1                           | 4.8                          | 12.9                                     |
| 50                      | 37.7         | 3.9                          | 2.3                           | 1.5                          | 4.6                                      | 64.0         | 7.3                          | 3.1                           | 4.2                          | 12.6                                     |
| 55                      | 35.1         | 3.6                          | 2.3                           | 1.3                          | 4.2                                      | 59.6         | 6.8                          | 3.1                           | 3.7                          | 12.3                                     |
| 60                      | 32.9         | 3.4                          | 2.3                           | 1.1                          | 3.8                                      | 55.9         | 6.4                          | 3.1                           | 3.3                          | 11.9                                     |
| 65                      | 31.0         | 3.2                          | 2.3                           | 0.9                          | 3.4                                      | 52.6         | 6.0                          | 3.1                           | 2.9                          | 11.4                                     |
| 70                      | 29.4         | 3.0                          | 2.3                           | 0.7                          | 2.9                                      | 49.8         | 5.7                          | 3.1                           | 2.6                          | 10.9                                     |
| 75                      | 27.9         | 2.9                          | 2.3                           | 0.5                          | 2.4                                      | 47.3         | 5.4                          | 3.1                           | 2.3                          | 10.4                                     |
| 80                      | 26.6         | 2.7                          | 2.3                           | 0.4                          | 1.9                                      | 45.0         | 5.1                          | 3.1                           | 2.1                          | 9.9                                      |
| 85                      | 25.4         | 2.6                          | 2.3                           | 0.3                          | 1.4                                      | 43.0         | 4.9                          | 3.1                           | 1.8                          | 9.3                                      |
| 90                      | 24.3         | 2.5                          | 2.3                           | 0.2                          | 0.9                                      | 41.1         | 4.7                          | 3.1                           | 1.6                          | 8.7                                      |
| 95                      | 23.3         | 2.4                          | 2.3                           | 0.1                          | 0.4                                      | 39.4         | 4.5                          | 3.1                           | 1.4                          | 8.1                                      |
| 100                     | 22.4         | 2.3                          | 2.3                           | 0.0                          | 0.0                                      | 37.9         | 4.3                          | 3.1                           | 1.2                          | 7.5                                      |
| 105                     | 21.6         | 2.2                          | 2.2                           | 0.0                          | 0.0                                      | 36.5         | 4.2                          | 3.1                           | 1.1                          | 6.9                                      |
| 110                     | 20.8         | 2.1                          | 2.1                           | 0.0                          | 0.0                                      | 35.2         | 4.0                          | 3.1                           | 0.9                          | 6.2                                      |

|                                |                    |                                  |                     |
|--------------------------------|--------------------|----------------------------------|---------------------|
| 5-year Q <sub>roof</sub>       | 2.32 L/s           | 100-year Q <sub>roof</sub>       | 3.07 L/s            |
| 5-year Max. Storage Required   | 5.9 m <sup>3</sup> | 100-year Max. Storage Required   | 13.3 m <sup>3</sup> |
| 5-year Storage Depth           | 0.076 m            | 100-year Storage Depth           | 0.101 m             |
| 5-year Estimated Drawdown Time | 0.84 hr            | 100-year Estimated Drawdown Time | 1.51 hr             |

**PREVIOUSLY APPROVED (D07-12-17-0186)**

|                    |                                                      |
|--------------------|------------------------------------------------------|
| Building ID        | BLDG C                                               |
| Roof Area          | 0.288 ha                                             |
| Avail Storage Area | 0.274                                                |
| C                  | 0.90 Rational Method runoff coefficient              |
| t <sub>c</sub>     | 10 min, t <sub>c</sub> at outlet without restriction |

*Note: Rational Method Coefficient "C" increased by 25% for 100-year calculations*

**Estimated Number of Roof Drains**

|                        |                                                                         |
|------------------------|-------------------------------------------------------------------------|
| Building Length        | 64.2                                                                    |
| Building Width         | 43.8                                                                    |
| Number of Drains       | 12                                                                      |
| m <sup>2</sup> / Drain | 228.4 max 232.25m <sup>2</sup> /notch as recommended by Zurn for Ottawa |

| Roof Top Rating Curve per Zurn Model Z-105-5 |                   |                   |                    |                    |                   |                       |
|----------------------------------------------|-------------------|-------------------|--------------------|--------------------|-------------------|-----------------------|
| d                                            | A                 | V <sub>acc</sub>  | V <sub>avail</sub> | Q <sub>notch</sub> | Q <sub>roof</sub> | V <sub>drawdown</sub> |
| (m)                                          | (m <sup>2</sup> ) | (m <sup>3</sup> ) | (m <sup>3</sup> )  | (L/s)              | (L/s)             | (hr)                  |
| 0.000                                        | 0                 | 0.0               | 0.0                | 0.00               | 0.00              | 0.00                  |
| 0.025                                        | 171.3             | 1.4               | 1.4                | 0.38               | 4.56              | 0.09                  |
| 0.050                                        | 685.1             | 10.0              | 11.4               | 0.77               | 9.24              | 0.39                  |
| 0.075                                        | 1541.4            | 27.1              | 38.5               | 1.14               | 13.68             | 0.94                  |
| 0.100                                        | 2740.3            | 52.8              | 91.3               | 1.52               | 18.24             | 1.74                  |
| 0.125                                        | 2740.3            | 68.5              | 159.9              | 1.90               | 22.80             | 2.58                  |
| 0.150                                        | 2740.3            | 68.5              | 228.4              | 2.28               | 27.36             | 3.27                  |

\* Assumes one notch opening per drain, assumes maximum slope of 10cm

| t <sub>c</sub><br>(min) | 5-year       |                              |                               |                              |                                          |  | 100-year     |                              |                               |                              |                                          |  |
|-------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|--|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|--|
|                         | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) |  | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) |  |
| 10                      | 104.2        | 75.1                         | 14.2                          | 60.9                         | 36.6                                     |  | 178.6        | 143.1                        | 18.8                          | 124.3                        | 74.6                                     |  |
| 15                      | 83.6         | 60.3                         | 14.2                          | 46.1                         | 41.4                                     |  | 142.9        | 114.5                        | 18.8                          | 95.7                         | 86.1                                     |  |
| 20                      | 70.3         | 50.7                         | 14.2                          | 36.5                         | 43.8                                     |  | 120.0        | 96.1                         | 18.8                          | 77.3                         | 92.8                                     |  |
| 25                      | 60.9         | 43.9                         | 14.2                          | 29.7                         | 44.6                                     |  | 103.8        | 83.2                         | 18.8                          | 64.4                         | 96.6                                     |  |
| 30                      | 53.9         | 38.9                         | 14.2                          | 24.7                         | 44.4                                     |  | 91.9         | 73.6                         | 18.8                          | 54.8                         | 98.7                                     |  |
| 35                      | 48.5         | 35.0                         | 14.2                          | 20.8                         | 43.7                                     |  | 82.6         | 66.2                         | 18.8                          | 47.4                         | 99.5                                     |  |
| 40                      | 44.2         | 31.9                         | 14.2                          | 17.7                         | 42.4                                     |  | 75.1         | 60.2                         | 18.8                          | 41.4                         | 99.4                                     |  |
| 45                      | 40.6         | 29.3                         | 14.2                          | 15.1                         | 40.8                                     |  | 69.1         | 55.3                         | 18.8                          | 36.5                         | 98.7                                     |  |
| 50                      | 37.7         | 27.2                         | 14.2                          | 13.0                         | 38.9                                     |  | 64.0         | 51.2                         | 18.8                          | 32.5                         | 97.4                                     |  |
| 55                      | 35.1         | 25.3                         | 14.2                          | 11.1                         | 36.7                                     |  | 59.6         | 47.8                         | 18.8                          | 29.0                         | 95.7                                     |  |
| 60                      | 32.9         | 23.8                         | 14.2                          | 9.6                          | 34.4                                     |  | 55.9         | 44.8                         | 18.8                          | 26.0                         | 93.6                                     |  |
| 65                      | 31.0         | 22.4                         | 14.2                          | 8.2                          | 31.9                                     |  | 52.6         | 42.2                         | 18.8                          | 23.4                         | 91.3                                     |  |
| 70                      | 29.4         | 21.2                         | 14.2                          | 7.0                          | 29.3                                     |  | 49.8         | 39.9                         | 18.8                          | 21.1                         | 88.7                                     |  |
| 75                      | 27.9         | 20.1                         | 14.2                          | 5.9                          | 26.6                                     |  | 47.3         | 37.9                         | 18.8                          | 19.1                         | 85.9                                     |  |
| 80                      | 26.6         | 19.2                         | 14.2                          | 5.0                          | 23.8                                     |  | 45.0         | 36.0                         | 18.8                          | 17.3                         | 82.9                                     |  |
| 85                      | 25.4         | 18.3                         | 14.2                          | 4.1                          | 20.9                                     |  | 43.0         | 34.4                         | 18.8                          | 15.6                         | 79.7                                     |  |
| 90                      | 24.3         | 17.5                         | 14.2                          | 3.3                          | 17.9                                     |  | 41.1         | 32.9                         | 18.8                          | 14.2                         | 76.4                                     |  |
| 95                      | 23.3         | 16.8                         | 14.2                          | 2.6                          | 14.8                                     |  | 39.4         | 31.6                         | 18.8                          | 12.8                         | 73.0                                     |  |
| 100                     | 22.4         | 16.2                         | 14.2                          | 2.0                          | 11.7                                     |  | 37.9         | 30.4                         | 18.8                          | 11.6                         | 69.5                                     |  |
| 105                     | 21.6         | 15.6                         | 14.2                          | 1.4                          | 8.6                                      |  | 36.5         | 29.2                         | 18.8                          | 10.5                         | 65.9                                     |  |
| 110                     | 20.8         | 15.0                         | 14.2                          | 0.8                          | 5.4                                      |  | 35.2         | 28.2                         | 18.8                          | 9.4                          | 62.2                                     |  |

|                                |                     |                                  |                     |
|--------------------------------|---------------------|----------------------------------|---------------------|
| 5-year Q <sub>roof</sub>       | 14.20 L/s           | 100-year Q <sub>roof</sub>       | 18.78 L/s           |
| 5-year Max. Storage Required   | 44.6 m <sup>3</sup> | 100-year Max. Storage Required   | 99.5 m <sup>3</sup> |
| 5-year Storage Depth           | 0.078 m             | 100-year Storage Depth           | 0.103 m             |
| 5-year Estimated Drawdown Time | 1.03 hr             | 100-year Estimated Drawdown Time | 1.84 hr             |

**PREVIOUSLY APPROVED (D07-12-17-0186)**

Building ID **BLDG D**  
Roof Area 0.101 ha  
Avail Storage Area 0.096  
C 0.90 Rational Method runoff coefficient *Note: Rational Method Coefficient "C" increased by 25% for 100-year calculations*  
t<sub>c</sub> 10 min, t<sub>c</sub> at outlet without restriction

**Estimated Number of Roof Drains**

Building Length 20.2  
Building Width 53.1  
Number of Drains 5  
m<sup>2</sup> / Drain 192.7 max 232.25m<sup>2</sup>/notch as recommended by Zurn for Ottawa

| Roof Top Rating Curve per Zurn Model Z-105-5 |                   |                   |                    |                    |                   |                       |
|----------------------------------------------|-------------------|-------------------|--------------------|--------------------|-------------------|-----------------------|
| d                                            | A                 | V <sub>acc</sub>  | V <sub>avail</sub> | Q <sub>notch</sub> | Q <sub>roof</sub> | V <sub>drawdown</sub> |
| (m)                                          | (m <sup>2</sup> ) | (m <sup>3</sup> ) | (m <sup>3</sup> )  | (L/s)              | (L/s)             | (hr)                  |
| 0.000                                        | 0                 | 0.0               | 0.0                | 0.00               | 0.00              | 0.00                  |
| 0.025                                        | 60.2              | 0.5               | 0.5                | 0.38               | 1.90              | 0.07                  |
| 0.050                                        | 240.9             | 3.5               | 4.0                | 0.77               | 3.85              | 0.33                  |
| 0.075                                        | 542.0             | 9.5               | 13.6               | 1.14               | 5.70              | 0.79                  |
| 0.100                                        | 963.6             | 18.6              | 32.1               | 1.52               | 7.60              | 1.47                  |
| 0.125                                        | 963.6             | 24.1              | 56.2               | 1.90               | 9.50              | 2.17                  |
| 0.150                                        | 963.6             | 24.1              | 80.3               | 2.28               | 11.40             | 2.76                  |

\* Assumes one notch opening per drain, assumes maximum slope of 10cm

| t <sub>c</sub><br>(min) | 5-year       |                              |                               |                              |                                          | 100-year     |                              |                               |                              |                                          |
|-------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|
|                         | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) |
| 10                      | 104.2        | 26.4                         | 5.8                           | 20.6                         | 12.4                                     | 178.6        | 50.3                         | 7.7                           | 42.7                         | 25.6                                     |
| 15                      | 83.6         | 21.2                         | 5.8                           | 15.4                         | 13.9                                     | 142.9        | 40.3                         | 7.7                           | 32.6                         | 29.3                                     |
| 20                      | 70.3         | 17.8                         | 5.8                           | 12.0                         | 14.4                                     | 120.0        | 33.8                         | 7.7                           | 26.1                         | 31.4                                     |
| 25                      | 60.9         | 15.4                         | 5.8                           | 9.6                          | 14.5                                     | 103.8        | 29.3                         | 7.7                           | 21.6                         | 32.4                                     |
| 30                      | 53.9         | 13.7                         | 5.8                           | 7.9                          | 14.2                                     | 91.9         | 25.9                         | 7.7                           | 18.2                         | 32.8                                     |
| 35                      | 48.5         | 12.3                         | 5.8                           | 6.5                          | 13.7                                     | 82.6         | 23.3                         | 7.7                           | 15.6                         | 32.8                                     |
| 40                      | 44.2         | 11.2                         | 5.8                           | 5.4                          | 13.0                                     | 75.1         | 21.2                         | 7.7                           | 13.5                         | 32.4                                     |
| 45                      | 40.6         | 10.3                         | 5.8                           | 4.5                          | 12.2                                     | 69.1         | 19.5                         | 7.7                           | 11.8                         | 31.9                                     |
| 50                      | 37.7         | 9.5                          | 5.8                           | 3.8                          | 11.3                                     | 64.0         | 18.0                         | 7.7                           | 10.4                         | 31.1                                     |
| 55                      | 35.1         | 8.9                          | 5.8                           | 3.1                          | 10.3                                     | 59.6         | 16.8                         | 7.7                           | 9.1                          | 30.2                                     |
| 60                      | 32.9         | 8.4                          | 5.8                           | 2.6                          | 9.2                                      | 55.9         | 15.7                         | 7.7                           | 8.1                          | 29.1                                     |
| 65                      | 31.0         | 7.9                          | 5.8                           | 2.1                          | 8.1                                      | 52.6         | 14.8                         | 7.7                           | 7.2                          | 28.0                                     |
| 70                      | 29.4         | 7.4                          | 5.8                           | 1.7                          | 6.9                                      | 49.8         | 14.0                         | 7.7                           | 6.4                          | 26.8                                     |
| 75                      | 27.9         | 7.1                          | 5.8                           | 1.3                          | 5.8                                      | 47.3         | 13.3                         | 7.7                           | 5.7                          | 25.5                                     |
| 80                      | 26.6         | 6.7                          | 5.8                           | 0.9                          | 4.5                                      | 45.0         | 12.7                         | 7.7                           | 5.0                          | 24.1                                     |
| 85                      | 25.4         | 6.4                          | 5.8                           | 0.6                          | 3.3                                      | 43.0         | 12.1                         | 7.7                           | 4.4                          | 22.7                                     |
| 90                      | 24.3         | 6.2                          | 5.8                           | 0.4                          | 2.0                                      | 41.1         | 11.6                         | 7.7                           | 3.9                          | 21.2                                     |
| 95                      | 23.3         | 5.9                          | 5.8                           | 0.1                          | 0.7                                      | 39.4         | 11.1                         | 7.7                           | 3.5                          | 19.7                                     |
| 100                     | 22.4         | 5.7                          | 5.7                           | 0.0                          | 0.0                                      | 37.9         | 10.7                         | 7.7                           | 3.0                          | 18.1                                     |
| 105                     | 21.6         | 5.5                          | 5.5                           | 0.0                          | 0.0                                      | 36.5         | 10.3                         | 7.7                           | 2.6                          | 16.6                                     |
| 110                     | 20.8         | 5.3                          | 5.3                           | 0.0                          | 0.0                                      | 35.2         | 9.9                          | 7.7                           | 2.3                          | 14.9                                     |

|                                       |                           |                                         |                           |
|---------------------------------------|---------------------------|-----------------------------------------|---------------------------|
| <b>5-year Q<sub>roof</sub></b>        | <b>5.79 L/s</b>           | <b>100-year Q<sub>roof</sub></b>        | <b>7.65 L/s</b>           |
| <b>5-year Max. Storage Required</b>   | <b>14.5 m<sup>3</sup></b> | <b>100-year Max. Storage Required</b>   | <b>32.8 m<sup>3</sup></b> |
| <b>5-year Storage Depth</b>           | <b>0.076 m</b>            | <b>100-year Storage Depth</b>           | <b>0.101 m</b>            |
| <b>5-year Estimated Drawdown Time</b> | <b>0.83 hr</b>            | <b>100-year Estimated Drawdown Time</b> | <b>1.49 hr</b>            |

**PREVIOUSLY APPROVED (D07-12-17-0186)**

**Building ID: UT. BLDG G**

|                    |                                                      |                                                                                  |
|--------------------|------------------------------------------------------|----------------------------------------------------------------------------------|
| Roof Area          | 0.097 ha                                             |                                                                                  |
| Avail Storage Area | 0.092                                                |                                                                                  |
| C                  | 0.90 Rational Method runoff coefficient              | Note: Rational Method Coefficient "C" increased by 25% for 100-year calculations |
| t <sub>c</sub>     | 10 min, t <sub>c</sub> at outlet without restriction |                                                                                  |

**Estimated Number of Roof Drains**

|                        |                                                                         |
|------------------------|-------------------------------------------------------------------------|
| Building Length        | 20.2                                                                    |
| Building Width         | 53.1                                                                    |
| Number of Drains       | 5                                                                       |
| m <sup>2</sup> / Drain | 184.4 max 232.25m <sup>2</sup> /notch as recommended by Zurn for Ottawa |

| Roof Top Rating Curve per Zurn Model Z-105-5 |                   |                   |                    |                    |                   |                       |
|----------------------------------------------|-------------------|-------------------|--------------------|--------------------|-------------------|-----------------------|
| d                                            | A                 | V <sub>acc</sub>  | V <sub>avail</sub> | Q <sub>notch</sub> | Q <sub>roof</sub> | V <sub>drawdown</sub> |
| (m)                                          | (m <sup>2</sup> ) | (m <sup>3</sup> ) | (m <sup>3</sup> )  | (L/s)              | (L/s)             | (hr)                  |
| 0.000                                        | 0                 | 0.0               | 0.0                | 0.00               | 0.00              | 0.00                  |
| 0.025                                        | 57.6              | 0.5               | 0.5                | 0.38               | 1.90              | 0.07                  |
| 0.050                                        | 230.4             | 3.4               | 3.8                | 0.77               | 3.85              | 0.31                  |
| 0.075                                        | 518.5             | 9.1               | 13.0               | 1.14               | 5.70              | 0.76                  |
| 0.100                                        | 921.8             | 17.8              | 30.7               | 1.52               | 7.60              | 1.41                  |
| 0.125                                        | 921.8             | 23.0              | 53.8               | 1.90               | 9.50              | 2.08                  |
| 0.150                                        | 921.8             | 23.0              | 76.8               | 2.28               | 11.40             | 2.64                  |

\* Assumes one notch opening per drain, assumes maximum slope of 10cm

| t <sub>c</sub><br>(min) | 5-year       |                              |                               |                              |                                          |  | 100-year     |                              |                               |                              |                                          |  |
|-------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|--|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|--|
|                         | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) |  | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) |  |
| 10                      | 104.2        | 25.3                         | 5.8                           | 19.5                         | 11.7                                     |  | 178.6        | 48.1                         | 7.6                           | 40.5                         | 24.3                                     |  |
| 15                      | 83.6         | 20.3                         | 5.8                           | 14.5                         | 13.1                                     |  | 142.9        | 38.5                         | 7.6                           | 30.9                         | 27.8                                     |  |
| 20                      | 70.3         | 17.0                         | 5.8                           | 11.3                         | 13.5                                     |  | 120.0        | 32.3                         | 7.6                           | 24.7                         | 29.7                                     |  |
| 25                      | 60.9         | 14.8                         | 5.8                           | 9.0                          | 13.5                                     |  | 103.8        | 28.0                         | 7.6                           | 20.4                         | 30.6                                     |  |
| 30                      | 53.9         | 13.1                         | 5.8                           | 7.3                          | 13.2                                     |  | 91.9         | 24.8                         | 7.6                           | 17.1                         | 30.9                                     |  |
| 35                      | 48.5         | 11.8                         | 5.8                           | 6.0                          | 12.6                                     |  | 82.6         | 22.3                         | 7.6                           | 14.6                         | 30.8                                     |  |
| 40                      | 44.2         | 10.7                         | 5.8                           | 5.0                          | 11.9                                     |  | 75.1         | 20.3                         | 7.6                           | 12.6                         | 30.3                                     |  |
| 45                      | 40.6         | 9.9                          | 5.8                           | 4.1                          | 11.1                                     |  | 69.1         | 18.6                         | 7.6                           | 11.0                         | 29.7                                     |  |
| 50                      | 37.7         | 9.1                          | 5.8                           | 3.4                          | 10.1                                     |  | 64.0         | 17.2                         | 7.6                           | 9.6                          | 28.9                                     |  |
| 55                      | 35.1         | 8.5                          | 5.8                           | 2.8                          | 9.1                                      |  | 59.6         | 16.1                         | 7.6                           | 8.5                          | 27.9                                     |  |
| 60                      | 32.9         | 8.0                          | 5.8                           | 2.2                          | 8.0                                      |  | 55.9         | 15.1                         | 7.6                           | 7.5                          | 26.8                                     |  |
| 65                      | 31.0         | 7.5                          | 5.8                           | 1.8                          | 6.9                                      |  | 52.6         | 14.2                         | 7.6                           | 6.6                          | 25.7                                     |  |
| 70                      | 29.4         | 7.1                          | 5.8                           | 1.4                          | 5.7                                      |  | 49.8         | 13.4                         | 7.6                           | 5.8                          | 24.4                                     |  |
| 75                      | 27.9         | 6.8                          | 5.8                           | 1.0                          | 4.5                                      |  | 47.3         | 12.7                         | 7.6                           | 5.1                          | 23.1                                     |  |
| 80                      | 26.6         | 6.4                          | 5.8                           | 0.7                          | 3.3                                      |  | 45.0         | 12.1                         | 7.6                           | 4.5                          | 21.7                                     |  |
| 85                      | 25.4         | 6.2                          | 5.8                           | 0.4                          | 2.0                                      |  | 43.0         | 11.6                         | 7.6                           | 4.0                          | 20.2                                     |  |
| 90                      | 24.3         | 5.9                          | 5.8                           | 0.1                          | 0.7                                      |  | 41.1         | 11.1                         | 7.6                           | 3.5                          | 18.7                                     |  |
| 95                      | 23.3         | 5.7                          | 5.7                           | 0.0                          | 0.0                                      |  | 39.4         | 10.6                         | 7.6                           | 3.0                          | 17.2                                     |  |
| 100                     | 22.4         | 5.4                          | 5.4                           | 0.0                          | 0.0                                      |  | 37.9         | 10.2                         | 7.6                           | 2.6                          | 15.6                                     |  |
| 105                     | 21.6         | 5.2                          | 5.2                           | 0.0                          | 0.0                                      |  | 36.5         | 9.8                          | 7.6                           | 2.2                          | 14.0                                     |  |
| 110                     | 20.8         | 5.1                          | 5.1                           | 0.0                          | 0.0                                      |  | 35.2         | 9.5                          | 7.6                           | 1.9                          | 12.4                                     |  |

|                                       |                           |                                         |                           |
|---------------------------------------|---------------------------|-----------------------------------------|---------------------------|
| <b>5-year Q<sub>roof</sub></b>        | <b>5.76 L/s</b>           | <b>100-year Q<sub>roof</sub></b>        | <b>7.61 L/s</b>           |
| <b>5-year Max. Storage Required</b>   | <b>13.5 m<sup>3</sup></b> | <b>100-year Max. Storage Required</b>   | <b>30.9 m<sup>3</sup></b> |
| <b>5-year Storage Depth</b>           | <b>0.076 m</b>            | <b>100-year Storage Depth</b>           | <b>0.100 m</b>            |
| <b>5-year Estimated Drawdown Time</b> | <b>0.78 hr</b>            | <b>100-year Estimated Drawdown Time</b> | <b>1.41 hr</b>            |



**PREVIOUSLY APPROVED (D07-12-17-0186)**

**Estimated Post Development Peak Flow from Attenuated Areas**

Area ID A  
Available Sub-surface Storage

Total U/G Storage Volume (m<sup>3</sup>) 76.0

**Stage Attenuated Areas Storage Summary**

|               | Stage<br>(m) | Surface Storage              |                       |                | Surface and Subsurface Storage |                                          |                                 |                               |
|---------------|--------------|------------------------------|-----------------------|----------------|--------------------------------|------------------------------------------|---------------------------------|-------------------------------|
|               |              | Ponding<br>(m <sup>2</sup> ) | h <sub>o</sub><br>(m) | delta d<br>(m) | V*<br>(m <sup>3</sup> )        | V <sub>acc</sub> **<br>(m <sup>3</sup> ) | Q <sub>release</sub> †<br>(L/s) | V <sub>drawdown</sub><br>(hr) |
| Orifice INV   | 101.44       | -                            | 0.00                  |                |                                | 0.0                                      | 0.0                             | 0.00                          |
| Cistern INV   | 101.99       | -                            | 0.55                  | 0.55           | 38.0                           | 38.0                                     | 133.3                           | 0.08                          |
| Cistern OBV   | 102.63       | -                            | 1.19                  | 0.64           | 38.0                           | 76.0                                     | 195.6                           | 0.11                          |
| T/L1          | 103.25       | 0.4                          | 1.81                  | 0.63           | 0.1                            | 76.1                                     | 241.8                           | 0.09                          |
| T/L2          | 103.30       | 150.3                        | 1.86                  | 0.05           | 2.6                            | 78.7                                     | 245.1                           | 0.09                          |
| T/L3          | 103.35       | 795.8                        | 1.91                  | 0.05           | 21.5                           | 100.3                                    | 248.4                           | 0.11                          |
| 0.15m Ponding | 103.40       | 2067.2                       | 1.96                  | 0.05           | 69.1                           | 169.3                                    | 251.6                           | 0.19                          |
| Max Ponding   | 103.55       | 8923.7                       | 2.11                  | 0.15           | 764.3                          | 933.6                                    | 261.0                           | 0.99                          |

\* V=Incremental storage volume

\*\*V<sub>acc</sub>=Total surface and sub-surface

† Q<sub>release</sub> = Release rate calculated from orifice equation

$$Q = C_d \times A \times \sqrt{2 \times g \times h_o}$$

Where Q = Release rate (cms)

C<sub>d</sub> = Discharge Coefficient (0.61)

A = Area of the orifice (m<sup>2</sup>)

g = gravitational constant (9.81 m/s<sup>2</sup>)

h<sub>o eff</sub> = Effective head above the orifice due to waterlevel at outlet

Orifice Location STM101 Dia 291

Total Area 2.81 ha

C

0.81 Rational Method runoff coefficient

Note: Rational Method Coefficient "C" increased by 25% for 100-year calculations

| t <sub>c</sub><br>(min) | 5-year       |                                |                               |                              |                                          | 100-year     |                                |                               |                              |                                          |
|-------------------------|--------------|--------------------------------|-------------------------------|------------------------------|------------------------------------------|--------------|--------------------------------|-------------------------------|------------------------------|------------------------------------------|
|                         | i<br>(mm/hr) | Q <sub>actual</sub> †<br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) | i<br>(mm/hr) | Q <sub>actual</sub> †<br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) |
| 5                       | 141.2        | 943.4                          | 253.1                         | 690.3                        | 207.1                                    | 242.7        | 1954.7                         | 261.0                         | 1693.7                       | 508.1                                    |
| 10                      | 104.2        | 708.2                          | 253.1                         | 455.1                        | 273.1                                    | 178.6        | 1454.0                         | 261.0                         | 1193.0                       | 715.8                                    |
| 15                      | 83.6         | 577.0                          | 253.1                         | 323.9                        | 291.5                                    | 142.9        | 1175.7                         | 261.0                         | 914.6                        | 823.2                                    |
| 20                      | 70.3         | 492.4                          | 253.1                         | 239.3                        | 287.1                                    | 120.0        | 996.6                          | 261.0                         | 735.6                        | 882.7                                    |
| 25                      | 60.9         | 432.9                          | 253.1                         | 179.8                        | 269.7                                    | 103.8        | 870.9                          | 261.0                         | 609.9                        | 914.8                                    |
| 30                      | 53.9         | 388.6                          | 253.1                         | 135.5                        | 243.8                                    | 91.9         | 777.4                          | 261.0                         | 516.4                        | 929.5                                    |
| 35                      | 48.5         | 354.2                          | 253.1                         | 101.1                        | 212.2                                    | 82.6         | 704.9                          | 261.0                         | 443.9                        | 932.1                                    |
| 40                      | 44.2         | 326.6                          | 253.1                         | 73.5                         | 176.4                                    | 75.1         | 646.9                          | 261.0                         | 385.8                        | 926.0                                    |
| 45                      | 40.6         | 304.0                          | 253.1                         | 50.9                         | 137.4                                    | 69.1         | 599.3                          | 261.0                         | 338.3                        | 913.3                                    |
| 50                      | 37.7         | 285.1                          | 253.1                         | 32.0                         | 95.9                                     | 64.0         | 559.5                          | 261.0                         | 298.5                        | 895.5                                    |
| 55                      | 35.1         | 269.0                          | 253.1                         | 15.9                         | 52.4                                     | 59.6         | 525.7                          | 261.0                         | 264.7                        | 873.5                                    |
| 60                      | 32.9         | 255.1                          | 253.1                         | 2.0                          | 7.3                                      | 55.9         | 496.6                          | 261.0                         | 235.6                        | 848.1                                    |
| 65                      | 31.0         | 243.0                          | 243.0                         | 0.0                          | 0.0                                      | 52.6         | 471.2                          | 261.0                         | 210.2                        | 819.9                                    |
| 70                      | 29.4         | 232.4                          | 232.4                         | 0.0                          | 0.0                                      | 49.8         | 448.9                          | 261.0                         | 187.9                        | 789.3                                    |
| 75                      | 27.9         | 223.0                          | 223.0                         | 0.0                          | 0.0                                      | 47.3         | 429.2                          | 261.0                         | 168.2                        | 756.7                                    |
| 80                      | 26.6         | 214.5                          | 214.5                         | 0.0                          | 0.0                                      | 45.0         | 411.5                          | 261.0                         | 150.5                        | 722.3                                    |
| 85                      | 25.4         | 207.0                          | 207.0                         | 0.0                          | 0.0                                      | 43.0         | 395.6                          | 261.0                         | 134.6                        | 686.3                                    |
| 90                      | 24.3         | 200.1                          | 200.1                         | 0.0                          | 0.0                                      | 41.1         | 381.2                          | 261.0                         | 120.2                        | 649.0                                    |
| 95                      | 23.3         | 193.8                          | 193.8                         | 0.0                          | 0.0                                      | 39.4         | 368.1                          | 261.0                         | 107.1                        | 610.5                                    |
| 100                     | 22.4         | 188.1                          | 188.1                         | 0.0                          | 0.0                                      | 37.9         | 356.2                          | 261.0                         | 95.2                         | 570.9                                    |
| 105                     | 21.6         | 182.9                          | 182.9                         | 0.0                          | 0.0                                      | 36.5         | 345.2                          | 261.0                         | 84.2                         | 530.3                                    |

† Includes controlled flow from BLDG A-G

5-year Q<sub>attenuated</sub> 253.1 L/s  
5-year Max. Storage Required 291.5 m<sup>3</sup>  
Est. 5-year Storage Elevation 103.42 m

100-year Q<sub>attenuated</sub> 261.0 L/s  
100-year Max. Storage Required 932.1 m<sup>3</sup>  
Est. 100-year Storage Elevation 103.55 m

**Summary of Release Rates and Storage Volumes**

| Control Area | 5-Year<br>Required<br>Storage<br>(m <sup>3</sup> ) | 100-Year<br>Required<br>Storage<br>(m <sup>3</sup> ) | 100-Year<br>Available<br>Storage*<br>(m <sup>3</sup> ) |
|--------------|----------------------------------------------------|------------------------------------------------------|--------------------------------------------------------|
| U1           | 0.0                                                | 0.0                                                  | 0.0                                                    |
| U2           | 0.0                                                | 0.0                                                  | 0.0                                                    |
| U3           | 0.0                                                | 0.0                                                  | 0.0                                                    |
| A1           | 291.5                                              | 932.1                                                | 933.6                                                  |
| <b>Total</b> | <b>291.5</b>                                       | <b>932.1</b>                                         | <b>933.6</b>                                           |

\*Note Available Storage Not Including Structure and Sewer Storage

**PREVIOUSLY APPROVED (D07-12-17-0186)**

Stormwater - Proposed Development  
City of Ottawa Sewer Design Guidelines, 2012



**Target Flow Rate**

| Site Area |                                                    | 5-year         |                |                       | 100-year       |                       |
|-----------|----------------------------------------------------|----------------|----------------|-----------------------|----------------|-----------------------|
|           |                                                    | $t_c$<br>(min) | $i$<br>(mm/hr) | $Q_{actual}$<br>(L/s) | $i$<br>(mm/hr) | $Q_{actual}$<br>(L/s) |
| C         | 4.44 ha<br>0.74 Rational Method runoff coefficient | 21.4           | 67.4           | 271.6                 | 115.0          | 463.6                 |

**Estimated Post Development Peak Flow from Unattenuated Areas**

Area ID U1

Total Area 0.679 ha  
C 0.24 Rational Method runoff coefficient

| 5-year         |                |                       |                        |                       |                                   | 100-year       |                       |                        |                       |                                   |
|----------------|----------------|-----------------------|------------------------|-----------------------|-----------------------------------|----------------|-----------------------|------------------------|-----------------------|-----------------------------------|
| $t_c$<br>(min) | $i$<br>(mm/hr) | $Q_{actual}$<br>(L/s) | $Q_{release}$<br>(L/s) | $Q_{stored}$<br>(L/s) | $V_{stored}$<br>(m <sup>3</sup> ) | $i$<br>(mm/hr) | $Q_{actual}$<br>(L/s) | $Q_{release}$<br>(L/s) | $Q_{stored}$<br>(L/s) | $V_{stored}$<br>(m <sup>3</sup> ) |
| 15.1           | 83.2           | 37.3                  | 37.3                   | 0.0                   | 0.0                               | 142.4          | 79.7                  | 79.7                   | 0.0                   | 0.0                               |

Area ID U2

Total Area 0.079 ha  
C 0.59 Rational Method runoff coefficient

| 5-year         |                |                       |                        |                       |                                   | 100-year       |                       |                        |                       |                                   |
|----------------|----------------|-----------------------|------------------------|-----------------------|-----------------------------------|----------------|-----------------------|------------------------|-----------------------|-----------------------------------|
| $t_c$<br>(min) | $i$<br>(mm/hr) | $Q_{actual}$<br>(L/s) | $Q_{release}$<br>(L/s) | $Q_{stored}$<br>(L/s) | $V_{stored}$<br>(m <sup>3</sup> ) | $i$<br>(mm/hr) | $Q_{actual}$<br>(L/s) | $Q_{release}$<br>(L/s) | $Q_{stored}$<br>(L/s) | $V_{stored}$<br>(m <sup>3</sup> ) |
| 15.1           | 83.2           | 10.6                  | 10.6                   | 0.0                   | 0.0                               | 142.4          | 22.7                  | 22.7                   | 0.0                   | 0.0                               |

Area ID U3

Total Area 0.015 ha  
C 0.90 Rational Method runoff coefficient

| 5-year         |                |                       |                        |                       |                                   | 100-year       |                       |                        |                       |                                   |
|----------------|----------------|-----------------------|------------------------|-----------------------|-----------------------------------|----------------|-----------------------|------------------------|-----------------------|-----------------------------------|
| $t_c$<br>(min) | $i$<br>(mm/hr) | $Q_{actual}$<br>(L/s) | $Q_{release}$<br>(L/s) | $Q_{stored}$<br>(L/s) | $V_{stored}$<br>(m <sup>3</sup> ) | $i$<br>(mm/hr) | $Q_{actual}$<br>(L/s) | $Q_{release}$<br>(L/s) | $Q_{stored}$<br>(L/s) | $V_{stored}$<br>(m <sup>3</sup> ) |
| 15.1           | 83.2           | 3.2                   | 3.2                    | 0.0                   | 0.0                               | 142.4          | 6.1                   | 6.1                    | 0.0                   | 0.0                               |

**PREVIOUSLY APPROVED (D07-12-17-0186)**

**Estimated Post Development Storage Requirement**

|                           |                                                      |
|---------------------------|------------------------------------------------------|
| <b>Building ID</b>        | <b>BLDG A</b>                                        |
| <b>Roof Area</b>          | 0.190 ha                                             |
| <b>Avail Storage Area</b> | 0.180                                                |
| <b>C</b>                  | 0.90 Rational Method runoff coefficient              |
| <b>t<sub>c</sub></b>      | 10 min, t <sub>c</sub> at outlet without restriction |

*Note: Rational Method Coefficient "C" increased by 25% for 100-year calculations*

**Estimated Number of Roof Drains**

|                              |                                                                         |
|------------------------------|-------------------------------------------------------------------------|
| <b>Building Length</b>       | 86.6                                                                    |
| <b>Building Width</b>        | 22.3                                                                    |
| <b>Number of Drains</b>      | 9                                                                       |
| <b>m<sup>2</sup> / Drain</b> | 200.1 max 232.25m <sup>2</sup> /notch as recommended by Zurn for Ottawa |

| Roof Top Rating Curve per Zurn Model Z-105-5 |                   |                   |                    |                    |                   |                       |
|----------------------------------------------|-------------------|-------------------|--------------------|--------------------|-------------------|-----------------------|
| d                                            | A                 | V <sub>acc</sub>  | V <sub>avail</sub> | Q <sub>notch</sub> | Q <sub>roof</sub> | V <sub>drawdown</sub> |
| (m)                                          | (m <sup>2</sup> ) | (m <sup>3</sup> ) | (m <sup>3</sup> )  | (L/s)              | (L/s)             | (hr)                  |
| 0.000                                        | 0                 | 0.0               | 0.0                | 0.00               | 0.00              | 0.00                  |
| 0.025                                        | 112.6             | 0.9               | 0.9                | 0.38               | 3.42              | 0.08                  |
| 0.050                                        | 450.3             | 6.6               | 7.5                | 0.77               | 6.93              | 0.34                  |
| 0.075                                        | 1013.1            | 17.8              | 25.3               | 1.14               | 10.26             | 0.82                  |
| 0.100                                        | 1801.0            | 34.7              | 60.0               | 1.52               | 13.68             | 1.53                  |
| 0.125                                        | 1801.0            | 45.0              | 105.1              | 1.90               | 17.10             | 2.26                  |
| 0.150                                        | 1801.0            | 45.0              | 150.1              | 2.28               | 20.52             | 2.87                  |

\* Assumes one notch opening per drain, assumes maximum slope of 10cm

| t <sub>c</sub><br>(min) | 5-year       |                              |                               |                              |                                          | 100-year     |                              |                               |                              |                                          |
|-------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|
|                         | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) |
| 10                      | 104.2        | 49.4                         | 10.5                          | 38.9                         | 23.3                                     | 178.6        | 94.0                         | 13.8                          | 80.2                         | 48.1                                     |
| 15                      | 83.6         | 39.6                         | 10.5                          | 29.1                         | 26.2                                     | 142.9        | 75.3                         | 13.8                          | 61.4                         | 55.3                                     |
| 20                      | 70.3         | 33.3                         | 10.5                          | 22.8                         | 27.4                                     | 120.0        | 63.2                         | 13.8                          | 49.3                         | 59.2                                     |
| 25                      | 60.9         | 28.9                         | 10.5                          | 18.4                         | 27.6                                     | 103.8        | 54.7                         | 13.8                          | 40.8                         | 61.3                                     |
| 30                      | 53.9         | 25.6                         | 10.5                          | 15.1                         | 27.1                                     | 91.9         | 48.4                         | 13.8                          | 34.5                         | 62.2                                     |
| 35                      | 48.5         | 23.0                         | 10.5                          | 12.5                         | 26.3                                     | 82.6         | 43.5                         | 13.8                          | 29.6                         | 62.2                                     |
| 40                      | 44.2         | 20.9                         | 10.5                          | 10.5                         | 25.1                                     | 75.1         | 39.6                         | 13.8                          | 25.7                         | 61.7                                     |
| 45                      | 40.6         | 19.3                         | 10.5                          | 8.8                          | 23.7                                     | 69.1         | 36.4                         | 13.8                          | 22.5                         | 60.8                                     |
| 50                      | 37.7         | 17.8                         | 10.5                          | 7.4                          | 22.1                                     | 64.0         | 33.7                         | 13.8                          | 19.8                         | 59.5                                     |
| 55                      | 35.1         | 16.6                         | 10.5                          | 6.2                          | 20.3                                     | 59.6         | 31.4                         | 13.8                          | 17.6                         | 57.9                                     |
| 60                      | 32.9         | 15.6                         | 10.5                          | 5.1                          | 18.5                                     | 55.9         | 29.4                         | 13.8                          | 15.6                         | 56.1                                     |
| 65                      | 31.0         | 14.7                         | 10.5                          | 4.2                          | 16.5                                     | 52.6         | 27.7                         | 13.8                          | 13.9                         | 54.1                                     |
| 70                      | 29.4         | 13.9                         | 10.5                          | 3.4                          | 14.4                                     | 49.8         | 26.2                         | 13.8                          | 12.4                         | 52.0                                     |
| 75                      | 27.9         | 13.2                         | 10.5                          | 2.7                          | 12.3                                     | 47.3         | 24.9                         | 13.8                          | 11.0                         | 49.7                                     |
| 80                      | 26.6         | 12.6                         | 10.5                          | 2.1                          | 10.1                                     | 45.0         | 23.7                         | 13.8                          | 9.8                          | 47.3                                     |
| 85                      | 25.4         | 12.0                         | 10.5                          | 1.5                          | 7.9                                      | 43.0         | 22.6                         | 13.8                          | 8.8                          | 44.7                                     |
| 90                      | 24.3         | 11.5                         | 10.5                          | 1.0                          | 5.6                                      | 41.1         | 21.6                         | 13.8                          | 7.8                          | 42.1                                     |
| 95                      | 23.3         | 11.0                         | 10.5                          | 0.6                          | 3.2                                      | 39.4         | 20.8                         | 13.8                          | 6.9                          | 39.4                                     |
| 100                     | 22.4         | 10.6                         | 10.5                          | 0.1                          | 0.8                                      | 37.9         | 20.0                         | 13.8                          | 6.1                          | 36.7                                     |
| 105                     | 21.6         | 10.2                         | 10.2                          | 0.0                          | 0.0                                      | 36.5         | 19.2                         | 13.8                          | 5.4                          | 33.8                                     |
| 110                     | 20.8         | 9.9                          | 9.9                           | 0.0                          | 0.0                                      | 35.2         | 18.5                         | 13.8                          | 4.7                          | 31.0                                     |

5-year Q<sub>roof</sub> 10.48 L/s  
5-year Max. Storage Required 27.6 m<sup>3</sup>  
5-year Storage Depth 0.077 m  
5-year Estimated Drawdown Time 0.87 hr

100-year Q<sub>roof</sub> 13.85 L/s  
100-year Max. Storage Required 62.2 m<sup>3</sup>  
100-year Storage Depth 0.101 m  
100-year Estimated Drawdown Time 1.56 hr

**PREVIOUSLY APPROVED (D07-12-17-0186)**

|                    |                                                      |
|--------------------|------------------------------------------------------|
| Building ID        | BLDG B                                               |
| Roof Area          | 0.140 ha                                             |
| Avail Storage Area | 0.133                                                |
| C                  | 0.90 Rational Method runoff coefficient              |
| t <sub>c</sub>     | 10 min, t <sub>c</sub> at outlet without restriction |

*Note: Rational Method Coefficient "C" increased by 25% for 100-year calculations*

**Estimated Number of Roof Drains**

|                        |                                                                         |
|------------------------|-------------------------------------------------------------------------|
| Building Length        | 58.0                                                                    |
| Building Width         | 24.0                                                                    |
| Number of Drains       | 6                                                                       |
| m <sup>2</sup> / Drain | 222.3 max 232.25m <sup>2</sup> /notch as recommended by Zurn for Ottawa |

| Roof Top Rating Curve per Zurn Model Z-105-5 |                   |                   |                    |                    |                   |                       |
|----------------------------------------------|-------------------|-------------------|--------------------|--------------------|-------------------|-----------------------|
| d                                            | A                 | V <sub>acc</sub>  | V <sub>avail</sub> | Q <sub>notch</sub> | Q <sub>roof</sub> | V <sub>drawdown</sub> |
| (m)                                          | (m <sup>2</sup> ) | (m <sup>3</sup> ) | (m <sup>3</sup> )  | (L/s)              | (L/s)             | (hr)                  |
| 0.000                                        | 0                 | 0.0               | 0.0                | 0.00               | 0.00              | 0.00                  |
| 0.025                                        | 83.4              | 0.7               | 0.7                | 0.38               | 2.28              | 0.08                  |
| 0.050                                        | 333.5             | 4.9               | 5.6                | 0.77               | 4.62              | 0.38                  |
| 0.075                                        | 750.3             | 13.2              | 18.8               | 1.14               | 6.84              | 0.91                  |
| 0.100                                        | 1333.9            | 25.7              | 44.5               | 1.52               | 9.12              | 1.70                  |
| 0.125                                        | 1333.9            | 33.3              | 77.8               | 1.90               | 11.40             | 2.51                  |
| 0.150                                        | 1333.9            | 33.3              | 111.2              | 2.28               | 13.68             | 3.19                  |

\* Assumes one notch opening per drain, assumes maximum slope of 10cm

| 5-year                  |              |                              |                               |                              |                                          | 100-year     |                              |                               |                              |                                          |
|-------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|
| t <sub>c</sub><br>(min) | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) |
| 10                      | 104.2        | 36.6                         | 7.1                           | 29.5                         | 17.7                                     | 178.6        | 69.6                         | 9.4                           | 60.3                         | 36.2                                     |
| 15                      | 83.6         | 29.3                         | 7.1                           | 22.3                         | 20.0                                     | 142.9        | 55.7                         | 9.4                           | 46.4                         | 41.7                                     |
| 20                      | 70.3         | 24.7                         | 7.1                           | 17.6                         | 21.1                                     | 120.0        | 46.8                         | 9.4                           | 37.4                         | 44.9                                     |
| 25                      | 60.9         | 21.4                         | 7.1                           | 14.3                         | 21.4                                     | 103.8        | 40.5                         | 9.4                           | 31.1                         | 46.7                                     |
| 30                      | 53.9         | 18.9                         | 7.1                           | 11.9                         | 21.3                                     | 91.9         | 35.8                         | 9.4                           | 26.5                         | 47.6                                     |
| 35                      | 48.5         | 17.0                         | 7.1                           | 10.0                         | 20.9                                     | 82.6         | 32.2                         | 9.4                           | 22.8                         | 48.0                                     |
| 40                      | 44.2         | 15.5                         | 7.1                           | 8.4                          | 20.2                                     | 75.1         | 29.3                         | 9.4                           | 19.9                         | 47.9                                     |
| 45                      | 40.6         | 14.3                         | 7.1                           | 7.2                          | 19.4                                     | 69.1         | 26.9                         | 9.4                           | 17.6                         | 47.4                                     |
| 50                      | 37.7         | 13.2                         | 7.1                           | 6.1                          | 18.4                                     | 64.0         | 24.9                         | 9.4                           | 15.6                         | 46.8                                     |
| 55                      | 35.1         | 12.3                         | 7.1                           | 5.3                          | 17.3                                     | 59.6         | 23.3                         | 9.4                           | 13.9                         | 45.9                                     |
| 60                      | 32.9         | 11.6                         | 7.1                           | 4.5                          | 16.1                                     | 55.9         | 21.8                         | 9.4                           | 12.4                         | 44.8                                     |
| 65                      | 31.0         | 10.9                         | 7.1                           | 3.8                          | 14.9                                     | 52.6         | 20.5                         | 9.4                           | 11.2                         | 43.6                                     |
| 70                      | 29.4         | 10.3                         | 7.1                           | 3.2                          | 13.6                                     | 49.8         | 19.4                         | 9.4                           | 10.1                         | 42.2                                     |
| 75                      | 27.9         | 9.8                          | 7.1                           | 2.7                          | 12.2                                     | 47.3         | 18.4                         | 9.4                           | 9.1                          | 40.8                                     |
| 80                      | 26.6         | 9.3                          | 7.1                           | 2.2                          | 10.8                                     | 45.0         | 17.5                         | 9.4                           | 8.2                          | 39.3                                     |
| 85                      | 25.4         | 8.9                          | 7.1                           | 1.8                          | 9.3                                      | 43.0         | 16.8                         | 9.4                           | 7.4                          | 37.7                                     |
| 90                      | 24.3         | 8.5                          | 7.1                           | 1.4                          | 7.8                                      | 41.1         | 16.0                         | 9.4                           | 6.7                          | 36.0                                     |
| 95                      | 23.3         | 8.2                          | 7.1                           | 1.1                          | 6.3                                      | 39.4         | 15.4                         | 9.4                           | 6.0                          | 34.3                                     |
| 100                     | 22.4         | 7.9                          | 7.1                           | 0.8                          | 4.7                                      | 37.9         | 14.8                         | 9.4                           | 5.4                          | 32.5                                     |
| 105                     | 21.6         | 7.6                          | 7.1                           | 0.5                          | 3.1                                      | 36.5         | 14.2                         | 9.4                           | 4.9                          | 30.7                                     |
| 110                     | 20.8         | 7.3                          | 7.1                           | 0.2                          | 1.5                                      | 35.2         | 13.7                         | 9.4                           | 4.4                          | 28.8                                     |

5-year Q<sub>roof</sub> 7.08 L/s  
5-year Max. Storage Required 21.4 m<sup>3</sup>  
5-year Storage Depth 0.078 m  
5-year Estimated Drawdown Time 1.00 hr

100-year Q<sub>roof</sub> 9.36 L/s  
100-year Max. Storage Required 48.0 m<sup>3</sup>  
100-year Storage Depth 0.103 m  
100-year Estimated Drawdown Time 1.78 hr

**PREVIOUSLY APPROVED (D07-12-17-0186)**

|                    |                                                      |
|--------------------|------------------------------------------------------|
| Building ID        | BLDG BB                                              |
| Roof Area          | 0.041 ha                                             |
| Avail Storage Area | 0.039                                                |
| C                  | 0.90 Rational Method runoff coefficient              |
| t <sub>c</sub>     | 10 min, t <sub>c</sub> at outlet without restriction |

*Note: Rational Method Coefficient "C" increased by 25% for 100-year calculations*

**Estimated Number of Roof Drains**

|                        |                                                                         |
|------------------------|-------------------------------------------------------------------------|
| Building Length        | 15.5                                                                    |
| Building Width         | 24.0                                                                    |
| Number of Drains       | 2                                                                       |
| m <sup>2</sup> / Drain | 194.7 max 232.25m <sup>2</sup> /notch as recommended by Zurn for Ottawa |

| Roof Top Rating Curve per Zurn Model Z-105-5 |                   |                   |                    |                    |                   |                       |
|----------------------------------------------|-------------------|-------------------|--------------------|--------------------|-------------------|-----------------------|
| d                                            | A                 | V <sub>acc</sub>  | V <sub>avail</sub> | Q <sub>notch</sub> | Q <sub>roof</sub> | V <sub>drawdown</sub> |
| (m)                                          | (m <sup>2</sup> ) | (m <sup>3</sup> ) | (m <sup>3</sup> )  | (L/s)              | (L/s)             | (hr)                  |
| 0.000                                        | 0                 | 0.0               | 0.0                | 0.00               | 0.00              | 0.00                  |
| 0.025                                        | 24.3              | 0.2               | 0.2                | 0.38               | 0.76              | 0.07                  |
| 0.050                                        | 97.3              | 1.4               | 1.6                | 0.77               | 1.54              | 0.33                  |
| 0.075                                        | 219.0             | 3.9               | 5.5                | 1.14               | 2.28              | 0.80                  |
| 0.100                                        | 389.3             | 7.5               | 13.0               | 1.52               | 3.04              | 1.49                  |
| 0.125                                        | 389.3             | 9.7               | 22.7               | 1.90               | 3.80              | 2.20                  |
| 0.150                                        | 389.3             | 9.7               | 32.4               | 2.28               | 4.56              | 2.79                  |

\* Assumes one notch opening per drain, assumes maximum slope of 10cm

| t <sub>c</sub><br>(min) | 5-year       |                              |                               |                              |                                          | 100-year     |                              |                               |                              |                                          |
|-------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|
|                         | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) |
| 10                      | 104.2        | 10.7                         | 2.3                           | 8.4                          | 5.0                                      | 178.6        | 20.3                         | 3.1                           | 17.3                         | 10.4                                     |
| 15                      | 83.6         | 8.6                          | 2.3                           | 6.2                          | 5.6                                      | 142.9        | 16.3                         | 3.1                           | 13.2                         | 11.9                                     |
| 20                      | 70.3         | 7.2                          | 2.3                           | 4.9                          | 5.9                                      | 120.0        | 13.7                         | 3.1                           | 10.6                         | 12.7                                     |
| 25                      | 60.9         | 6.2                          | 2.3                           | 3.9                          | 5.9                                      | 103.8        | 11.8                         | 3.1                           | 8.8                          | 13.1                                     |
| 30                      | 53.9         | 5.5                          | 2.3                           | 3.2                          | 5.8                                      | 91.9         | 10.5                         | 3.1                           | 7.4                          | 13.3                                     |
| 35                      | 48.5         | 5.0                          | 2.3                           | 2.7                          | 5.6                                      | 82.6         | 9.4                          | 3.1                           | 6.3                          | 13.3                                     |
| 40                      | 44.2         | 4.5                          | 2.3                           | 2.2                          | 5.3                                      | 75.1         | 8.6                          | 3.1                           | 5.5                          | 13.2                                     |
| 45                      | 40.6         | 4.2                          | 2.3                           | 1.8                          | 5.0                                      | 69.1         | 7.9                          | 3.1                           | 4.8                          | 12.9                                     |
| 50                      | 37.7         | 3.9                          | 2.3                           | 1.5                          | 4.6                                      | 64.0         | 7.3                          | 3.1                           | 4.2                          | 12.6                                     |
| 55                      | 35.1         | 3.6                          | 2.3                           | 1.3                          | 4.2                                      | 59.6         | 6.8                          | 3.1                           | 3.7                          | 12.3                                     |
| 60                      | 32.9         | 3.4                          | 2.3                           | 1.1                          | 3.8                                      | 55.9         | 6.4                          | 3.1                           | 3.3                          | 11.9                                     |
| 65                      | 31.0         | 3.2                          | 2.3                           | 0.9                          | 3.4                                      | 52.6         | 6.0                          | 3.1                           | 2.9                          | 11.4                                     |
| 70                      | 29.4         | 3.0                          | 2.3                           | 0.7                          | 2.9                                      | 49.8         | 5.7                          | 3.1                           | 2.6                          | 10.9                                     |
| 75                      | 27.9         | 2.9                          | 2.3                           | 0.5                          | 2.4                                      | 47.3         | 5.4                          | 3.1                           | 2.3                          | 10.4                                     |
| 80                      | 26.6         | 2.7                          | 2.3                           | 0.4                          | 1.9                                      | 45.0         | 5.1                          | 3.1                           | 2.1                          | 9.9                                      |
| 85                      | 25.4         | 2.6                          | 2.3                           | 0.3                          | 1.4                                      | 43.0         | 4.9                          | 3.1                           | 1.8                          | 9.3                                      |
| 90                      | 24.3         | 2.5                          | 2.3                           | 0.2                          | 0.9                                      | 41.1         | 4.7                          | 3.1                           | 1.6                          | 8.7                                      |
| 95                      | 23.3         | 2.4                          | 2.3                           | 0.1                          | 0.4                                      | 39.4         | 4.5                          | 3.1                           | 1.4                          | 8.1                                      |
| 100                     | 22.4         | 2.3                          | 2.3                           | 0.0                          | 0.0                                      | 37.9         | 4.3                          | 3.1                           | 1.2                          | 7.5                                      |
| 105                     | 21.6         | 2.2                          | 2.2                           | 0.0                          | 0.0                                      | 36.5         | 4.2                          | 3.1                           | 1.1                          | 6.9                                      |
| 110                     | 20.8         | 2.1                          | 2.1                           | 0.0                          | 0.0                                      | 35.2         | 4.0                          | 3.1                           | 0.9                          | 6.2                                      |

5-year Q<sub>roof</sub> 2.32 L/s  
5-year Max. Storage Required 5.9 m<sup>3</sup>  
5-year Storage Depth 0.076 m  
5-year Estimated Drawdown Time 0.84 hr

100-year Q<sub>roof</sub> 3.07 L/s  
100-year Max. Storage Required 13.3 m<sup>3</sup>  
100-year Storage Depth 0.101 m  
100-year Estimated Drawdown Time 1.51 hr

**PREVIOUSLY APPROVED (D07-12-17-0186)**

|                    |                                                      |
|--------------------|------------------------------------------------------|
| Building ID        | BLDG C                                               |
| Roof Area          | 0.288 ha                                             |
| Avail Storage Area | 0.274                                                |
| C                  | 0.90 Rational Method runoff coefficient              |
| t <sub>c</sub>     | 10 min, t <sub>c</sub> at outlet without restriction |

*Note: Rational Method Coefficient "C" increased by 25% for 100-year calculations*

**Estimated Number of Roof Drains**

|                        |                                                                         |
|------------------------|-------------------------------------------------------------------------|
| Building Length        | 64.2                                                                    |
| Building Width         | 43.8                                                                    |
| Number of Drains       | 12                                                                      |
| m <sup>2</sup> / Drain | 228.4 max 232.25m <sup>2</sup> /notch as recommended by Zurn for Ottawa |

| Roof Top Rating Curve per Zurn Model Z-105-5 |                   |                   |                    |                    |                   |                       |
|----------------------------------------------|-------------------|-------------------|--------------------|--------------------|-------------------|-----------------------|
| d                                            | A                 | V <sub>acc</sub>  | V <sub>avail</sub> | Q <sub>notch</sub> | Q <sub>roof</sub> | V <sub>drawdown</sub> |
| (m)                                          | (m <sup>2</sup> ) | (m <sup>3</sup> ) | (m <sup>3</sup> )  | (L/s)              | (L/s)             | (hr)                  |
| 0.000                                        | 0                 | 0.0               | 0.0                | 0.00               | 0.00              | 0.00                  |
| 0.025                                        | 171.3             | 1.4               | 1.4                | 0.38               | 4.56              | 0.09                  |
| 0.050                                        | 685.1             | 10.0              | 11.4               | 0.77               | 9.24              | 0.39                  |
| 0.075                                        | 1541.4            | 27.1              | 38.5               | 1.14               | 13.68             | 0.94                  |
| 0.100                                        | 2740.3            | 52.8              | 91.3               | 1.52               | 18.24             | 1.74                  |
| 0.125                                        | 2740.3            | 68.5              | 159.9              | 1.90               | 22.80             | 2.58                  |
| 0.150                                        | 2740.3            | 68.5              | 228.4              | 2.28               | 27.36             | 3.27                  |

\* Assumes one notch opening per drain, assumes maximum slope of 10cm

| t <sub>c</sub><br>(min) | 5-year       |                              |                               |                              |                                          | 100-year     |                              |                               |                              |                                          |
|-------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|
|                         | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) |
| 10                      | 104.2        | 75.1                         | 14.2                          | 60.9                         | 36.6                                     | 178.6        | 143.1                        | 18.8                          | 124.3                        | 74.6                                     |
| 15                      | 83.6         | 60.3                         | 14.2                          | 46.1                         | 41.4                                     | 142.9        | 114.5                        | 18.8                          | 95.7                         | 86.1                                     |
| 20                      | 70.3         | 50.7                         | 14.2                          | 36.5                         | 43.8                                     | 120.0        | 96.1                         | 18.8                          | 77.3                         | 92.8                                     |
| 25                      | 60.9         | 43.9                         | 14.2                          | 29.7                         | 44.6                                     | 103.8        | 83.2                         | 18.8                          | 64.4                         | 96.6                                     |
| 30                      | 53.9         | 38.9                         | 14.2                          | 24.7                         | 44.4                                     | 91.9         | 73.6                         | 18.8                          | 54.8                         | 98.7                                     |
| 35                      | 48.5         | 35.0                         | 14.2                          | 20.8                         | 43.7                                     | 82.6         | 66.2                         | 18.8                          | 47.4                         | 99.5                                     |
| 40                      | 44.2         | 31.9                         | 14.2                          | 17.7                         | 42.4                                     | 75.1         | 60.2                         | 18.8                          | 41.4                         | 99.4                                     |
| 45                      | 40.6         | 29.3                         | 14.2                          | 15.1                         | 40.8                                     | 69.1         | 55.3                         | 18.8                          | 36.5                         | 98.7                                     |
| 50                      | 37.7         | 27.2                         | 14.2                          | 13.0                         | 38.9                                     | 64.0         | 51.2                         | 18.8                          | 32.5                         | 97.4                                     |
| 55                      | 35.1         | 25.3                         | 14.2                          | 11.1                         | 36.7                                     | 59.6         | 47.8                         | 18.8                          | 29.0                         | 95.7                                     |
| 60                      | 32.9         | 23.8                         | 14.2                          | 9.6                          | 34.4                                     | 55.9         | 44.8                         | 18.8                          | 26.0                         | 93.6                                     |
| 65                      | 31.0         | 22.4                         | 14.2                          | 8.2                          | 31.9                                     | 52.6         | 42.2                         | 18.8                          | 23.4                         | 91.3                                     |
| 70                      | 29.4         | 21.2                         | 14.2                          | 7.0                          | 29.3                                     | 49.8         | 39.9                         | 18.8                          | 21.1                         | 88.7                                     |
| 75                      | 27.9         | 20.1                         | 14.2                          | 5.9                          | 26.6                                     | 47.3         | 37.9                         | 18.8                          | 19.1                         | 85.9                                     |
| 80                      | 26.6         | 19.2                         | 14.2                          | 5.0                          | 23.8                                     | 45.0         | 36.0                         | 18.8                          | 17.3                         | 82.9                                     |
| 85                      | 25.4         | 18.3                         | 14.2                          | 4.1                          | 20.9                                     | 43.0         | 34.4                         | 18.8                          | 15.6                         | 79.7                                     |
| 90                      | 24.3         | 17.5                         | 14.2                          | 3.3                          | 17.9                                     | 41.1         | 32.9                         | 18.8                          | 14.2                         | 76.4                                     |
| 95                      | 23.3         | 16.8                         | 14.2                          | 2.6                          | 14.8                                     | 39.4         | 31.6                         | 18.8                          | 12.8                         | 73.0                                     |
| 100                     | 22.4         | 16.2                         | 14.2                          | 2.0                          | 11.7                                     | 37.9         | 30.4                         | 18.8                          | 11.6                         | 69.5                                     |
| 105                     | 21.6         | 15.6                         | 14.2                          | 1.4                          | 8.6                                      | 36.5         | 29.2                         | 18.8                          | 10.5                         | 65.9                                     |
| 110                     | 20.8         | 15.0                         | 14.2                          | 0.8                          | 5.4                                      | 35.2         | 28.2                         | 18.8                          | 9.4                          | 62.2                                     |

5-year Q<sub>roof</sub> 14.20 L/s  
5-year Max. Storage Required 44.6 m<sup>3</sup>  
5-year Storage Depth 0.078 m  
5-year Estimated Drawdown Time 1.03 hr

100-year Q<sub>roof</sub> 18.78 L/s  
100-year Max. Storage Required 99.5 m<sup>3</sup>  
100-year Storage Depth 0.103 m  
100-year Estimated Drawdown Time 1.84 hr

**PREVIOUSLY APPROVED (D07-12-17-0186)**

|                    |                                                      |
|--------------------|------------------------------------------------------|
| Building ID        | BLDG D                                               |
| Roof Area          | 0.101 ha                                             |
| Avail Storage Area | 0.096                                                |
| C                  | 0.90 Rational Method runoff coefficient              |
| t <sub>c</sub>     | 10 min, t <sub>c</sub> at outlet without restriction |

*Note: Rational Method Coefficient "C" increased by 25% for 100-year calculations*

**Estimated Number of Roof Drains**

|                        |                                                                         |
|------------------------|-------------------------------------------------------------------------|
| Building Length        | 20.2                                                                    |
| Building Width         | 53.1                                                                    |
| Number of Drains       | 5                                                                       |
| m <sup>2</sup> / Drain | 192.7 max 232.25m <sup>2</sup> /notch as recommended by Zurn for Ottawa |

| Roof Top Rating Curve per Zurn Model Z-105-5 |                   |                   |                    |                    |                   |                       |
|----------------------------------------------|-------------------|-------------------|--------------------|--------------------|-------------------|-----------------------|
| d                                            | A                 | V <sub>acc</sub>  | V <sub>avail</sub> | Q <sub>notch</sub> | Q <sub>roof</sub> | V <sub>drawdown</sub> |
| (m)                                          | (m <sup>2</sup> ) | (m <sup>3</sup> ) | (m <sup>3</sup> )  | (L/s)              | (L/s)             | (hr)                  |
| 0.000                                        | 0                 | 0.0               | 0.0                | 0.00               | 0.00              | 0.00                  |
| 0.025                                        | 60.2              | 0.5               | 0.5                | 0.38               | 1.90              | 0.07                  |
| 0.050                                        | 240.9             | 3.5               | 4.0                | 0.77               | 3.85              | 0.33                  |
| 0.075                                        | 542.0             | 9.5               | 13.6               | 1.14               | 5.70              | 0.79                  |
| 0.100                                        | 963.6             | 18.6              | 32.1               | 1.52               | 7.60              | 1.47                  |
| 0.125                                        | 963.6             | 24.1              | 56.2               | 1.90               | 9.50              | 2.17                  |
| 0.150                                        | 963.6             | 24.1              | 80.3               | 2.28               | 11.40             | 2.76                  |

\* Assumes one notch opening per drain, assumes maximum slope of 10cm

| t <sub>c</sub><br>(min) | 5-year       |                              |                               |                              |                                          | 100-year     |                              |                               |                              |                                          |
|-------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|
|                         | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) |
| 10                      | 104.2        | 26.4                         | 5.8                           | 20.6                         | 12.4                                     | 178.6        | 50.3                         | 7.7                           | 42.7                         | 25.6                                     |
| 15                      | 83.6         | 21.2                         | 5.8                           | 15.4                         | 13.9                                     | 142.9        | 40.3                         | 7.7                           | 32.6                         | 29.3                                     |
| 20                      | 70.3         | 17.8                         | 5.8                           | 12.0                         | 14.4                                     | 120.0        | 33.8                         | 7.7                           | 26.1                         | 31.4                                     |
| 25                      | 60.9         | 15.4                         | 5.8                           | 9.6                          | 14.5                                     | 103.8        | 29.3                         | 7.7                           | 21.6                         | 32.4                                     |
| 30                      | 53.9         | 13.7                         | 5.8                           | 7.9                          | 14.2                                     | 91.9         | 25.9                         | 7.7                           | 18.2                         | 32.8                                     |
| 35                      | 48.5         | 12.3                         | 5.8                           | 6.5                          | 13.7                                     | 82.6         | 23.3                         | 7.7                           | 15.6                         | 32.8                                     |
| 40                      | 44.2         | 11.2                         | 5.8                           | 5.4                          | 13.0                                     | 75.1         | 21.2                         | 7.7                           | 13.5                         | 32.4                                     |
| 45                      | 40.6         | 10.3                         | 5.8                           | 4.5                          | 12.2                                     | 69.1         | 19.5                         | 7.7                           | 11.8                         | 31.9                                     |
| 50                      | 37.7         | 9.5                          | 5.8                           | 3.8                          | 11.3                                     | 64.0         | 18.0                         | 7.7                           | 10.4                         | 31.1                                     |
| 55                      | 35.1         | 8.9                          | 5.8                           | 3.1                          | 10.3                                     | 59.6         | 16.8                         | 7.7                           | 9.1                          | 30.2                                     |
| 60                      | 32.9         | 8.4                          | 5.8                           | 2.6                          | 9.2                                      | 55.9         | 15.7                         | 7.7                           | 8.1                          | 29.1                                     |
| 65                      | 31.0         | 7.9                          | 5.8                           | 2.1                          | 8.1                                      | 52.6         | 14.8                         | 7.7                           | 7.2                          | 28.0                                     |
| 70                      | 29.4         | 7.4                          | 5.8                           | 1.7                          | 6.9                                      | 49.8         | 14.0                         | 7.7                           | 6.4                          | 26.8                                     |
| 75                      | 27.9         | 7.1                          | 5.8                           | 1.3                          | 5.8                                      | 47.3         | 13.3                         | 7.7                           | 5.7                          | 25.5                                     |
| 80                      | 26.6         | 6.7                          | 5.8                           | 0.9                          | 4.5                                      | 45.0         | 12.7                         | 7.7                           | 5.0                          | 24.1                                     |
| 85                      | 25.4         | 6.4                          | 5.8                           | 0.6                          | 3.3                                      | 43.0         | 12.1                         | 7.7                           | 4.4                          | 22.7                                     |
| 90                      | 24.3         | 6.2                          | 5.8                           | 0.4                          | 2.0                                      | 41.1         | 11.6                         | 7.7                           | 3.9                          | 21.2                                     |
| 95                      | 23.3         | 5.9                          | 5.8                           | 0.1                          | 0.7                                      | 39.4         | 11.1                         | 7.7                           | 3.5                          | 19.7                                     |
| 100                     | 22.4         | 5.7                          | 5.7                           | 0.0                          | 0.0                                      | 37.9         | 10.7                         | 7.7                           | 3.0                          | 18.1                                     |
| 105                     | 21.6         | 5.5                          | 5.5                           | 0.0                          | 0.0                                      | 36.5         | 10.3                         | 7.7                           | 2.6                          | 16.6                                     |
| 110                     | 20.8         | 5.3                          | 5.3                           | 0.0                          | 0.0                                      | 35.2         | 9.9                          | 7.7                           | 2.3                          | 14.9                                     |

5-year Q<sub>roof</sub> 5.79 L/s  
5-year Max. Storage Required 14.5 m<sup>3</sup>  
5-year Storage Depth 0.076 m  
5-year Estimated Drawdown Time 0.83 hr

100-year Q<sub>roof</sub> 7.65 L/s  
100-year Max. Storage Required 32.8 m<sup>3</sup>  
100-year Storage Depth 0.101 m  
100-year Estimated Drawdown Time 1.49 hr

**PREVIOUSLY APPROVED (D07-12-17-0186)**

Building ID FUT. BLDG G  
Roof Area 0.097 ha  
Avail Storage Area 0.092  
C 0.90 Rational Method runoff coefficient *Note: Rational Method Coefficient "C" increased by 25% for 100-year calculations*  
t<sub>c</sub> 10 min, t<sub>c</sub> at outlet without restriction

**Estimated Number of Roof Drains**

Building Length 20.2  
Building Width 53.1  
Number of Drains 5  
m<sup>2</sup> / Drain 184.4 max 232.25m<sup>2</sup>/notch as recommended by Zurn for Ottawa

| Roof Top Rating Curve per Zurn Model Z-105-5 |                   |                   |                    |                    |                   |                       |
|----------------------------------------------|-------------------|-------------------|--------------------|--------------------|-------------------|-----------------------|
| d                                            | A                 | V <sub>acc</sub>  | V <sub>avail</sub> | Q <sub>notch</sub> | Q <sub>roof</sub> | V <sub>drawdown</sub> |
| (m)                                          | (m <sup>2</sup> ) | (m <sup>3</sup> ) | (m <sup>3</sup> )  | (L/s)              | (L/s)             | (hr)                  |
| 0.000                                        | 0                 | 0.0               | 0.0                | 0.00               | 0.00              | 0.00                  |
| 0.025                                        | 57.6              | 0.5               | 0.5                | 0.38               | 1.90              | 0.07                  |
| 0.050                                        | 230.4             | 3.4               | 3.8                | 0.77               | 3.85              | 0.31                  |
| 0.075                                        | 518.5             | 9.1               | 13.0               | 1.14               | 5.70              | 0.76                  |
| 0.100                                        | 921.8             | 17.8              | 30.7               | 1.52               | 7.60              | 1.41                  |
| 0.125                                        | 921.8             | 23.0              | 53.8               | 1.90               | 9.50              | 2.08                  |
| 0.150                                        | 921.8             | 23.0              | 76.8               | 2.28               | 11.40             | 2.64                  |

\* Assumes one notch opening per drain, assumes maximum slope of 10cm

| t <sub>c</sub><br>(min) | 5-year       |                              |                               |                              |                                          | 100-year     |                              |                               |                              |                                          |
|-------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|
|                         | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) |
| 10                      | 104.2        | 25.3                         | 5.8                           | 19.5                         | 11.7                                     | 178.6        | 48.1                         | 7.6                           | 40.5                         | 24.3                                     |
| 15                      | 83.6         | 20.3                         | 5.8                           | 14.5                         | 13.1                                     | 142.9        | 38.5                         | 7.6                           | 30.9                         | 27.8                                     |
| 20                      | 70.3         | 17.0                         | 5.8                           | 11.3                         | 13.5                                     | 120.0        | 32.3                         | 7.6                           | 24.7                         | 29.7                                     |
| 25                      | 60.9         | 14.8                         | 5.8                           | 9.0                          | 13.5                                     | 103.8        | 28.0                         | 7.6                           | 20.4                         | 30.6                                     |
| 30                      | 53.9         | 13.1                         | 5.8                           | 7.3                          | 13.2                                     | 91.9         | 24.8                         | 7.6                           | 17.1                         | 30.9                                     |
| 35                      | 48.5         | 11.8                         | 5.8                           | 6.0                          | 12.6                                     | 82.6         | 22.3                         | 7.6                           | 14.6                         | 30.8                                     |
| 40                      | 44.2         | 10.7                         | 5.8                           | 5.0                          | 11.9                                     | 75.1         | 20.3                         | 7.6                           | 12.6                         | 30.3                                     |
| 45                      | 40.6         | 9.9                          | 5.8                           | 4.1                          | 11.1                                     | 69.1         | 18.6                         | 7.6                           | 11.0                         | 29.7                                     |
| 50                      | 37.7         | 9.1                          | 5.8                           | 3.4                          | 10.1                                     | 64.0         | 17.2                         | 7.6                           | 9.6                          | 28.9                                     |
| 55                      | 35.1         | 8.5                          | 5.8                           | 2.8                          | 9.1                                      | 59.6         | 16.1                         | 7.6                           | 8.5                          | 27.9                                     |
| 60                      | 32.9         | 8.0                          | 5.8                           | 2.2                          | 8.0                                      | 55.9         | 15.1                         | 7.6                           | 7.5                          | 26.8                                     |
| 65                      | 31.0         | 7.5                          | 5.8                           | 1.8                          | 6.9                                      | 52.6         | 14.2                         | 7.6                           | 6.6                          | 25.7                                     |
| 70                      | 29.4         | 7.1                          | 5.8                           | 1.4                          | 5.7                                      | 49.8         | 13.4                         | 7.6                           | 5.8                          | 24.4                                     |
| 75                      | 27.9         | 6.8                          | 5.8                           | 1.0                          | 4.5                                      | 47.3         | 12.7                         | 7.6                           | 5.1                          | 23.1                                     |
| 80                      | 26.6         | 6.4                          | 5.8                           | 0.7                          | 3.3                                      | 45.0         | 12.1                         | 7.6                           | 4.5                          | 21.7                                     |
| 85                      | 25.4         | 6.2                          | 5.8                           | 0.4                          | 2.0                                      | 43.0         | 11.6                         | 7.6                           | 4.0                          | 20.2                                     |
| 90                      | 24.3         | 5.9                          | 5.8                           | 0.1                          | 0.7                                      | 41.1         | 11.1                         | 7.6                           | 3.5                          | 18.7                                     |
| 95                      | 23.3         | 5.7                          | 5.7                           | 0.0                          | 0.0                                      | 39.4         | 10.6                         | 7.6                           | 3.0                          | 17.2                                     |
| 100                     | 22.4         | 5.4                          | 5.4                           | 0.0                          | 0.0                                      | 37.9         | 10.2                         | 7.6                           | 2.6                          | 15.6                                     |
| 105                     | 21.6         | 5.2                          | 5.2                           | 0.0                          | 0.0                                      | 36.5         | 9.8                          | 7.6                           | 2.2                          | 14.0                                     |
| 110                     | 20.8         | 5.1                          | 5.1                           | 0.0                          | 0.0                                      | 35.2         | 9.5                          | 7.6                           | 1.9                          | 12.4                                     |

|                                |                     |                                  |                     |
|--------------------------------|---------------------|----------------------------------|---------------------|
| 5-year Q <sub>roof</sub>       | 5.76 L/s            | 100-year Q <sub>roof</sub>       | 7.61 L/s            |
| 5-year Max. Storage Required   | 13.5 m <sup>3</sup> | 100-year Max. Storage Required   | 30.9 m <sup>3</sup> |
| 5-year Storage Depth           | 0.076 m             | 100-year Storage Depth           | 0.100 m             |
| 5-year Estimated Drawdown Time | 0.78 hr             | 100-year Estimated Drawdown Time | 1.41 hr             |



**PREVIOUSLY APPROVED (D07-12-17-0186)**

**Estimated Post Development Peak Flow from Attenuated Areas**

Area ID

A

Total Subsurface Storage (m<sup>3</sup>) 293.0

**Stage Attenuated Areas Storage Summary**

|               | Surface Storage |                   |                |         | Surface and Subsurface Storage |                     |                             |                               |            |              |                         |                           |
|---------------|-----------------|-------------------|----------------|---------|--------------------------------|---------------------|-----------------------------|-------------------------------|------------|--------------|-------------------------|---------------------------|
|               | Stage           | Ponding           | h <sub>o</sub> | delta d | V*                             | V <sub>acc</sub> ** | 5-yr Q <sub>release</sub> † | 100-yr Q <sub>release</sub> † | 5-yr Elev. | 100-yr Elev. | h <sub>o, eff</sub> 5yr | h <sub>o, eff</sub> 100yr |
|               | (m)             | (m <sup>2</sup> ) | (m)            | (m)     | (m <sup>3</sup> )              | (m <sup>3</sup> )   | (L/s)                       | (L/s)                         | (m)        | (m)          | (m)                     | (m)                       |
| Orifice INV   | 101.44          | -                 | 0.00           |         |                                | 0.0                 | 0.0                         | 0.0                           | 101.91     | 102.52       | 0.00                    | 0.00                      |
| Cistern INV   | 101.99          | -                 | 0.55           | 0.55    | 146.5                          | 146.5               | 0.0                         | 0.0                           | 101.91     | 102.52       | 0.00                    | 0.00                      |
| Cistern OBV   | 102.63          | -                 | 1.19           | 0.64    | 146.5                          | 293.0               | 152.0                       | 0.0                           | 101.91     | 102.52       | 0.72                    | 0.00                      |
| T/L1          | 103.25          | 0.4               | 1.81           | 0.63    | 0.1                            | 293.1               | 208.0                       | 153.5                         | 101.91     | 102.52       | 1.34                    | 0.73                      |
| T/L2          | 103.30          | 150.3             | 1.86           | 0.05    | 2.6                            | 295.7               | 211.9                       | 158.7                         | 101.91     | 102.52       | 1.39                    | 0.78                      |
| T/L3          | 103.35          | 795.8             | 1.91           | 0.05    | 21.5                           | 317.3               | 215.6                       | 163.7                         | 101.91     | 102.52       | 1.44                    | 0.83                      |
| 0.15m Ponding | 103.40          | 2067.2            | 1.96           | 0.05    | 69.1                           | 386.4               | 219.4                       | 168.6                         | 101.91     | 102.52       | 1.49                    | 0.88                      |
| Max Ponding   | 103.55          | 8923.7            | 2.11           | 0.15    | 764.3                          | 1150.7              | 230.1                       | 182.4                         | 101.91     | 102.52       | 1.64                    | 1.03                      |

\* V=Incremental storage volume

Note: 5 and 100 year water elevations provided by JFSA

\*\*V<sub>acc</sub>=Total surface and sub-surface

† Q<sub>release</sub> = Release rate calculated from orifice equation accounting for backwater using the 5-year and 100-year waterlevels respectively

$$Q = C_d \times A \times \sqrt{2 \times g \times h_o}$$

Where Q = Release rate (cms)

C<sub>d</sub> = Discharge Coefficient (0.61)

A = Area of the orifice (m<sup>2</sup>)

g = gravitational constant (9.81m/s<sup>2</sup>)

h<sub>o eff</sub> = Effective head above the orifice due to waterlevel at outlet

Orifice Location

STM101

Dia

291

Total Area

2.810 ha

C

0.81 Rational Method runoff coefficient

Note: Rational Method Coefficient "C" increased by 25% for 100-year calculations

| t <sub>c</sub><br>(min) | 5-year       |                                |                               |                              |                                          | 100-year     |                                |                               |                              |                                          |
|-------------------------|--------------|--------------------------------|-------------------------------|------------------------------|------------------------------------------|--------------|--------------------------------|-------------------------------|------------------------------|------------------------------------------|
|                         | i<br>(mm/hr) | Q <sub>actual</sub> ‡<br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) | i<br>(mm/hr) | Q <sub>actual</sub> ‡<br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) |
| 5                       | 141.2        | 943.4                          | 216.4                         | 727.0                        | 218.1                                    | 242.7        | 1954.7                         | 182.1                         | 1772.6                       | 531.8                                    |
| 10                      | 104.2        | 708.2                          | 216.4                         | 491.8                        | 295.1                                    | 178.6        | 1454.0                         | 182.1                         | 1272.0                       | 763.2                                    |
| 15                      | 83.6         | 577.0                          | 216.4                         | 360.6                        | 324.5                                    | 142.9        | 1175.7                         | 182.1                         | 993.6                        | 894.2                                    |
| 20                      | 70.3         | 492.4                          | 216.4                         | 276.0                        | 331.2                                    | 120.0        | 996.6                          | 182.1                         | 814.5                        | 977.4                                    |
| 25                      | 60.9         | 432.9                          | 216.4                         | 216.5                        | 324.7                                    | 103.8        | 870.9                          | 182.1                         | 688.8                        | 1033.2                                   |
| 30                      | 53.9         | 388.6                          | 216.4                         | 172.2                        | 309.9                                    | 91.9         | 777.4                          | 182.1                         | 595.3                        | 1071.5                                   |
| 35                      | 48.5         | 354.2                          | 216.4                         | 137.8                        | 289.3                                    | 82.6         | 704.9                          | 182.1                         | 522.8                        | 1097.9                                   |
| 40                      | 44.2         | 326.6                          | 216.4                         | 110.2                        | 264.5                                    | 75.1         | 646.9                          | 182.1                         | 464.8                        | 1115.5                                   |
| 45                      | 40.6         | 304.0                          | 216.4                         | 87.6                         | 236.5                                    | 69.1         | 599.3                          | 182.1                         | 417.2                        | 1126.5                                   |
| 50                      | 37.7         | 285.1                          | 216.4                         | 68.7                         | 206.0                                    | 64.0         | 559.5                          | 182.1                         | 377.4                        | 1132.3                                   |
| 55                      | 35.1         | 269.0                          | 216.4                         | 52.6                         | 173.6                                    | 59.6         | 525.7                          | 182.1                         | 343.6                        | 1134.0                                   |
| 60                      | 32.9         | 255.1                          | 216.4                         | 38.7                         | 139.4                                    | 55.9         | 496.6                          | 182.1                         | 314.5                        | 1132.3                                   |
| 65                      | 31.0         | 243.0                          | 216.4                         | 26.7                         | 103.9                                    | 52.6         | 471.2                          | 182.1                         | 289.2                        | 1127.8                                   |
| 70                      | 29.4         | 232.4                          | 216.4                         | 16.0                         | 67.3                                     | 49.8         | 448.9                          | 182.1                         | 266.9                        | 1120.8                                   |
| 75                      | 27.9         | 223.0                          | 216.4                         | 6.6                          | 29.6                                     | 47.3         | 429.2                          | 182.1                         | 247.1                        | 1111.9                                   |
| 80                      | 26.6         | 214.5                          | 214.5                         | 0.0                          | 0.0                                      | 45.0         | 411.5                          | 182.1                         | 229.4                        | 1101.2                                   |
| 85                      | 25.4         | 207.0                          | 207.0                         | 0.0                          | 0.0                                      | 43.0         | 395.6                          | 182.1                         | 213.5                        | 1088.9                                   |
| 90                      | 24.3         | 200.1                          | 200.1                         | 0.0                          | 0.0                                      | 41.1         | 381.2                          | 182.1                         | 199.1                        | 1075.3                                   |
| 95                      | 23.3         | 193.8                          | 193.8                         | 0.0                          | 0.0                                      | 39.4         | 368.1                          | 182.1                         | 186.0                        | 1060.5                                   |
| 100                     | 22.4         | 188.1                          | 188.1                         | 0.0                          | 0.0                                      | 37.9         | 356.2                          | 182.1                         | 174.1                        | 1044.5                                   |
| 105                     | 21.6         | 182.9                          | 182.9                         | 0.0                          | 0.0                                      | 36.5         | 345.2                          | 182.1                         | 163.1                        | 1027.6                                   |

‡ Includes controlled flow from BLDG A-G

5-year Q<sub>attenuated</sub> 216.39 L/s  
5-year Max. Storage Required 331.2 m<sup>3</sup>  
Est. 5-year Storage Elevation 103.36 m

100-year Q<sub>attenuated</sub> 182.08 L/s  
100-year Max. Storage Required 1134.0 m<sup>3</sup>  
Est. 100-year Storage Elevation 103.55 m

**Summary of Release Rates and Storage Volumes**

| Control Area | 5-Year Release Rate<br>(L/s) | 5-Year Required Storage<br>(m <sup>3</sup> ) | 100-Year Release Rate<br>(L/s) | 100-Year Required Storage<br>(m <sup>3</sup> ) | 100-Year Available Storage<br>(m <sup>3</sup> ) |
|--------------|------------------------------|----------------------------------------------|--------------------------------|------------------------------------------------|-------------------------------------------------|
| U1           | 37.3                         | 0.0                                          | 79.7                           | 0.0                                            | 0.0                                             |
| U2           | 10.6                         | 0.0                                          | 22.7                           | 0.0                                            | 0.0                                             |
| U3           | 3.2                          | 0.0                                          | 6.1                            | 0.0                                            | 0.0                                             |
| A1           | 216.4                        | 331.2                                        | 182.1                          | 1134.0                                         | 1150.7                                          |
| <b>Total</b> | <b>267.5</b>                 | <b>331.2</b>                                 | <b>290.6</b>                   | <b>1134.0</b>                                  | <b>1150.7</b>                                   |

\* Note Attenuated Areas includes constant controlled flow from BLDG A-G

**PREVIOUSLY APPROVED (D07-12-17-0186)**

Stormwater - Proposed Development  
 City of Ottawa Sewer Design Guidelines, 2012



**Target Flow Rate**

Site Area 4.44 ha  
 C 0.74 Rational Method runoff coefficient

**Estimated Post Development Peak Flow from Unattenuated Areas**

Area ID U1

Total Area 0.679 ha  
 C 0.24 Rational Method runoff coefficient

| 2-year                  |              |                              |                               |                              |                                          |
|-------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|
| t <sub>c</sub><br>(min) | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) |
| 15.1                    | 61.5         | 27.6                         | 27.6                          | 0.0                          | 0.0                                      |

Area ID U2

Total Area 0.079 ha  
 C 0.59 Rational Method runoff coefficient

| 2-year                  |              |                              |                               |                              |                                          |
|-------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|
| t <sub>c</sub><br>(min) | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) |
| 15.1                    | 61.5         | 7.9                          | 7.9                           | 0.0                          | 0.0                                      |

Area ID U3

Total Area 0.015 ha  
 C 0.90 Rational Method runoff coefficient

| 2-year                  |              |                              |                               |                              |                                          |
|-------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|
| t <sub>c</sub><br>(min) | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) |
| 15.1                    | 61.5         | 2.4                          | 2.4                           | 0.0                          | 0.0                                      |

**PREVIOUSLY APPROVED (D07-12-17-0186)**

**Estimated Post Development Storage Requirement**

|                           |                                                      |
|---------------------------|------------------------------------------------------|
| <b>Building ID</b>        | <b>BLDG A</b>                                        |
| <b>Roof Area</b>          | 0.190 ha                                             |
| <b>Avail Storage Area</b> | 0.180                                                |
| <b>C</b>                  | 0.90 Rational Method runoff coefficient              |
| <b>t<sub>c</sub></b>      | 10 min, t <sub>c</sub> at outlet without restriction |

**Estimated Number of Roof Drains**

|                              |                                                                         |
|------------------------------|-------------------------------------------------------------------------|
| <b>Building Length</b>       | 86.6                                                                    |
| <b>Building Width</b>        | 22.3                                                                    |
| <b>Number of Drains</b>      | 9                                                                       |
| <b>m<sup>2</sup> / Drain</b> | 200.1 max 232.25m <sup>2</sup> /notch as recommended by Zurn for Ottawa |

| Roof Top Rating Curve per Zurn Model Z-105-5 |                   |                   |                    |                    |                   |                       |
|----------------------------------------------|-------------------|-------------------|--------------------|--------------------|-------------------|-----------------------|
| d                                            | A                 | V <sub>acc</sub>  | V <sub>avail</sub> | Q <sub>notch</sub> | Q <sub>roof</sub> | V <sub>drawdown</sub> |
| (m)                                          | (m <sup>2</sup> ) | (m <sup>3</sup> ) | (m <sup>3</sup> )  | (L/s)              | (L/s)             | (hr)                  |
| 0.000                                        | 0                 | 0.0               | 0.0                | 0.00               | 0.00              | 0.00                  |
| 0.025                                        | 112.6             | 0.9               | 0.9                | 0.38               | 3.42              | 0.08                  |
| 0.050                                        | 450.3             | 6.6               | 7.5                | 0.77               | 6.93              | 0.34                  |
| 0.075                                        | 1013.1            | 17.8              | 25.3               | 1.14               | 10.26             | 0.82                  |
| 0.100                                        | 1801.0            | 34.7              | 60.0               | 1.52               | 13.68             | 1.53                  |
| 0.125                                        | 1801.0            | 45.0              | 105.1              | 1.90               | 17.10             | 2.26                  |
| 0.150                                        | 1801.0            | 45.0              | 150.1              | 2.28               | 20.52             | 2.87                  |

\* Assumes one notch opening per drain, assumes maximum slope of 10cm

| 2-year         |         |                     |                      |                     |                     |
|----------------|---------|---------------------|----------------------|---------------------|---------------------|
| t <sub>c</sub> | i       | Q <sub>actual</sub> | Q <sub>release</sub> | Q <sub>stored</sub> | V <sub>stored</sub> |
| (min)          | (mm/hr) | (L/s)               | (L/s)                | (L/s)               | (m <sup>3</sup> )   |
| 5              | 103.6   | 49.1                | 9.0                  | 40.1                | 12.0                |
| 10             | 76.8    | 36.4                | 9.0                  | 27.4                | 16.4                |
| 15             | 61.8    | 29.3                | 9.0                  | 20.2                | 18.2                |
| 20             | 52.0    | 24.7                | 9.0                  | 15.6                | 18.8                |
| 25             | 45.2    | 21.4                | 9.0                  | 12.4                | 18.6                |
| 30             | 40.0    | 19.0                | 9.0                  | 9.9                 | 17.9                |
| 35             | 36.1    | 17.1                | 9.0                  | 8.1                 | 16.9                |
| 40             | 32.9    | 15.6                | 9.0                  | 6.5                 | 15.7                |
| 45             | 30.2    | 14.3                | 9.0                  | 5.3                 | 14.3                |
| 50             | 28.0    | 13.3                | 9.0                  | 4.3                 | 12.8                |
| 55             | 26.2    | 12.4                | 9.0                  | 3.4                 | 11.1                |
| 60             | 24.6    | 11.6                | 9.0                  | 2.6                 | 9.4                 |
| 65             | 23.2    | 11.0                | 9.0                  | 1.9                 | 7.6                 |
| 70             | 21.9    | 10.4                | 9.0                  | 1.4                 | 5.7                 |
| 75             | 20.8    | 9.9                 | 9.0                  | 0.8                 | 3.7                 |
| 80             | 19.8    | 9.4                 | 9.0                  | 0.4                 | 1.8                 |
| 85             | 18.9    | 9.0                 | 9.0                  | 0.0                 | 0.0                 |
| 90             | 18.1    | 8.6                 | 8.6                  | 0.0                 | 0.0                 |
| 95             | 17.4    | 8.3                 | 8.3                  | 0.0                 | 0.0                 |
| 100            | 16.7    | 7.9                 | 7.9                  | 0.0                 | 0.0                 |
| 105            | 16.1    | 7.6                 | 7.6                  | 0.0                 | 0.0                 |

|                                       |                           |
|---------------------------------------|---------------------------|
| <b>2-year Q<sub>roof</sub></b>        | <b>9.03 L/s</b>           |
| <b>2-year Max. Storage Required</b>   | <b>18.8 m<sup>3</sup></b> |
| <b>2-year Storage Depth</b>           | <b>0.066 m</b>            |
| <b>2-year Estimated Drawdown Time</b> | <b>0.64 hr</b>            |

**PREVIOUSLY APPROVED (D07-12-17-0186)**

**Building ID**      **BLDG B**  
**Roof Area**      0.140 ha  
**Avail Storage Area**      0.133  
**C**      0.90 Rational Method runoff coefficient  
**t<sub>c</sub>**      10 min, t<sub>c</sub> at outlet without restriction

**Estimated Number of Roof Drains**

**Building Length**      58.0  
**Building Width**      24.0  
**Number of Drains**      6  
**m<sup>2</sup> / Drain**      222.3 max 232.25m<sup>2</sup>/notch as recommended by Zurn for Ottawa

| Roof Top Rating Curve per Zurn Model Z-105-5 |                   |                   |                    |                    |                   |                       |
|----------------------------------------------|-------------------|-------------------|--------------------|--------------------|-------------------|-----------------------|
| d                                            | A                 | V <sub>acc</sub>  | V <sub>avail</sub> | Q <sub>notch</sub> | Q <sub>roof</sub> | V <sub>drawdown</sub> |
| (m)                                          | (m <sup>2</sup> ) | (m <sup>3</sup> ) | (m <sup>3</sup> )  | (L/s)              | (L/s)             | (hr)                  |
| 0.000                                        | 0                 | 0.0               | 0.0                | 0.00               | 0.00              | 0.00                  |
| 0.025                                        | 83.4              | 0.7               | 0.7                | 0.38               | 2.28              | 0.08                  |
| 0.050                                        | 333.5             | 4.9               | 5.6                | 0.77               | 4.62              | 0.38                  |
| 0.075                                        | 750.3             | 13.2              | 18.8               | 1.14               | 6.84              | 0.91                  |
| 0.100                                        | 1333.9            | 25.7              | 44.5               | 1.52               | 9.12              | 1.70                  |
| 0.125                                        | 1333.9            | 33.3              | 77.8               | 1.90               | 11.40             | 2.51                  |
| 0.150                                        | 1333.9            | 33.3              | 111.2              | 2.28               | 13.68             | 3.19                  |

\* Assumes one notch opening per drain, assumes maximum slope of 10cm

| 2-year                  |              |                              |                               |                              |                                          |
|-------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|
| t <sub>c</sub><br>(min) | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) |
| 5                       | 103.6        | 36.4                         | 6.1                           | 30.2                         | 9.1                                      |
| 10                      | 76.8         | 27.0                         | 6.1                           | 20.8                         | 12.5                                     |
| 15                      | 61.8         | 21.7                         | 6.1                           | 15.5                         | 14.0                                     |
| 20                      | 52.0         | 18.3                         | 6.1                           | 12.1                         | 14.6                                     |
| 25                      | 45.2         | 15.9                         | 6.1                           | 9.7                          | 14.6                                     |
| 30                      | 40.0         | 14.1                         | 6.1                           | 7.9                          | 14.3                                     |
| 35                      | 36.1         | 12.7                         | 6.1                           | 6.5                          | 13.7                                     |
| 40                      | 32.9         | 11.5                         | 6.1                           | 5.4                          | 13.0                                     |
| 45                      | 30.2         | 10.6                         | 6.1                           | 4.5                          | 12.1                                     |
| 50                      | 28.0         | 9.8                          | 6.1                           | 3.7                          | 11.1                                     |
| 55                      | 26.2         | 9.2                          | 6.1                           | 3.0                          | 10.1                                     |
| 60                      | 24.6         | 8.6                          | 6.1                           | 2.5                          | 8.9                                      |
| 65                      | 23.2         | 8.1                          | 6.1                           | 2.0                          | 7.8                                      |
| 70                      | 21.9         | 7.7                          | 6.1                           | 1.6                          | 6.5                                      |
| 75                      | 20.8         | 7.3                          | 6.1                           | 1.2                          | 5.3                                      |
| 80                      | 19.8         | 7.0                          | 6.1                           | 0.8                          | 4.0                                      |
| 85                      | 18.9         | 6.7                          | 6.1                           | 0.5                          | 2.6                                      |
| 90                      | 18.1         | 6.4                          | 6.1                           | 0.2                          | 1.3                                      |
| 95                      | 17.4         | 6.1                          | 6.1                           | 0.0                          | 0.0                                      |
| 100                     | 16.7         | 5.9                          | 5.9                           | 0.0                          | 0.0                                      |
| 105                     | 16.1         | 5.7                          | 5.7                           | 0.0                          | 0.0                                      |

2-year Q<sub>roof</sub>      6.14 L/s  
2-year Max. Storage Required      14.6 m<sup>3</sup>  
2-year Storage Depth      0.067 m  
2-year Estimated Drawdown Time      0.74 hr

**PREVIOUSLY APPROVED (D07-12-17-0186)**

Building ID      **BLDG BB**  
Roof Area        0.041 ha  
Avail Storage Area      0.039  
C                  0.90 Rational Method runoff coefficient  
t<sub>c</sub>                10 min, t<sub>c</sub> at outlet without restriction

**Estimated Number of Roof Drains**

Building Length      15.5  
Building Width        24.0  
Number of Drains      2  
m<sup>2</sup> / Drain            194.7 max 232.25m<sup>2</sup>/notch as recommended by Zurn for Ottawa

| Roof Top Rating Curve per Zurn Model Z-105-5 |                   |                   |                    |                    |                   |                       |
|----------------------------------------------|-------------------|-------------------|--------------------|--------------------|-------------------|-----------------------|
| d                                            | A                 | V <sub>acc</sub>  | V <sub>avail</sub> | Q <sub>notch</sub> | Q <sub>roof</sub> | V <sub>drawdown</sub> |
| (m)                                          | (m <sup>2</sup> ) | (m <sup>3</sup> ) | (m <sup>3</sup> )  | (L/s)              | (L/s)             | (hr)                  |
| 0.000                                        | 0                 | 0.0               | 0.0                | 0.00               | 0.00              | 0.00                  |
| 0.025                                        | 24.3              | 0.2               | 0.2                | 0.38               | 0.76              | 0.07                  |
| 0.050                                        | 97.3              | 1.4               | 1.6                | 0.77               | 1.54              | 0.33                  |
| 0.075                                        | 219.0             | 3.9               | 5.5                | 1.14               | 2.28              | 0.80                  |
| 0.100                                        | 389.3             | 7.5               | 13.0               | 1.52               | 3.04              | 1.49                  |
| 0.125                                        | 389.3             | 9.7               | 22.7               | 1.90               | 3.80              | 2.20                  |
| 0.150                                        | 389.3             | 9.7               | 32.4               | 2.28               | 4.56              | 2.79                  |

\* Assumes one notch opening per drain, assumes maximum slope of 10cm

| 2-year         |         |                     |                      |                     |                     |
|----------------|---------|---------------------|----------------------|---------------------|---------------------|
| t <sub>c</sub> | i       | Q <sub>actual</sub> | Q <sub>release</sub> | Q <sub>stored</sub> | V <sub>stored</sub> |
| (min)          | (mm/hr) | (L/s)               | (L/s)                | (L/s)               | (m <sup>3</sup> )   |
| 5              | 103.6   | 10.6                | 2.0                  | 8.6                 | 2.6                 |
| 10             | 76.8    | 7.9                 | 2.0                  | 5.9                 | 3.5                 |
| 15             | 61.8    | 6.3                 | 2.0                  | 4.3                 | 3.9                 |
| 20             | 52.0    | 5.3                 | 2.0                  | 3.3                 | 4.0                 |
| 25             | 45.2    | 4.6                 | 2.0                  | 2.6                 | 3.9                 |
| 30             | 40.0    | 4.1                 | 2.0                  | 2.1                 | 3.8                 |
| 35             | 36.1    | 3.7                 | 2.0                  | 1.7                 | 3.6                 |
| 40             | 32.9    | 3.4                 | 2.0                  | 1.4                 | 3.3                 |
| 45             | 30.2    | 3.1                 | 2.0                  | 1.1                 | 3.0                 |
| 50             | 28.0    | 2.9                 | 2.0                  | 0.9                 | 2.6                 |
| 55             | 26.2    | 2.7                 | 2.0                  | 0.7                 | 2.3                 |
| 60             | 24.6    | 2.5                 | 2.0                  | 0.5                 | 1.9                 |
| 65             | 23.2    | 2.4                 | 2.0                  | 0.4                 | 1.5                 |
| 70             | 21.9    | 2.2                 | 2.0                  | 0.2                 | 1.0                 |
| 75             | 20.8    | 2.1                 | 2.0                  | 0.1                 | 0.6                 |
| 80             | 19.8    | 2.0                 | 2.0                  | 0.0                 | 0.2                 |
| 85             | 18.9    | 1.9                 | 1.9                  | 0.0                 | 0.0                 |
| 90             | 18.1    | 1.9                 | 1.9                  | 0.0                 | 0.0                 |
| 95             | 17.4    | 1.8                 | 1.8                  | 0.0                 | 0.0                 |
| 100            | 16.7    | 1.7                 | 1.7                  | 0.0                 | 0.0                 |
| 105            | 16.1    | 1.7                 | 1.7                  | 0.0                 | 0.0                 |

2-year Q<sub>roof</sub>                    2.00 L/s  
2-year Max. Storage Required      4.0 m<sup>3</sup>  
2-year Storage Depth              0.065 m  
2-year Estimated Drawdown Time      0.62 hr

**PREVIOUSLY APPROVED (D07-12-17-0186)**

**Building ID**      **BLDG C**  
**Roof Area**      0.288 ha  
**Avail Storage Area**      0.274  
**C**      0.90 Rational Method runoff coefficient  
**t<sub>c</sub>**      10 min, t<sub>c</sub> at outlet without restriction

**Estimated Number of Roof Drains**

**Building Length**      64.2  
**Building Width**      43.8  
**Number of Drains**      12  
**m<sup>2</sup> / Drain**      228.4 max 232.25m<sup>2</sup>/notch as recommended by Zurn for Ottawa

| Roof Top Rating Curve per Zurn Model Z-105-5 |                   |                   |                    |                    |                   |                       |
|----------------------------------------------|-------------------|-------------------|--------------------|--------------------|-------------------|-----------------------|
| d                                            | A                 | V <sub>acc</sub>  | V <sub>avail</sub> | Q <sub>notch</sub> | Q <sub>roof</sub> | V <sub>drawdown</sub> |
| (m)                                          | (m <sup>2</sup> ) | (m <sup>3</sup> ) | (m <sup>3</sup> )  | (L/s)              | (L/s)             | (hr)                  |
| 0.000                                        | 0                 | 0.0               | 0.0                | 0.00               | 0.00              | 0.00                  |
| 0.025                                        | 171.3             | 1.4               | 1.4                | 0.38               | 4.56              | 0.09                  |
| 0.050                                        | 685.1             | 10.0              | 11.4               | 0.77               | 9.24              | 0.39                  |
| 0.075                                        | 1541.4            | 27.1              | 38.5               | 1.14               | 13.68             | 0.94                  |
| 0.100                                        | 2740.3            | 52.8              | 91.3               | 1.52               | 18.24             | 1.74                  |
| 0.125                                        | 2740.3            | 68.5              | 159.9              | 1.90               | 22.80             | 2.58                  |
| 0.150                                        | 2740.3            | 68.5              | 228.4              | 2.28               | 27.36             | 3.27                  |

\* Assumes one notch opening per drain, assumes maximum slope of 10cm

| 2-year         |         |                     |                      |                     |                     |
|----------------|---------|---------------------|----------------------|---------------------|---------------------|
| t <sub>c</sub> | i       | Q <sub>actual</sub> | Q <sub>release</sub> | Q <sub>stored</sub> | V <sub>stored</sub> |
| (min)          | (mm/hr) | (L/s)               | (L/s)                | (L/s)               | (m <sup>3</sup> )   |
| 5              | 103.6   | 74.7                | 12.3                 | 62.3                | 18.7                |
| 10             | 76.8    | 55.4                | 12.3                 | 43.0                | 25.8                |
| 15             | 61.8    | 44.5                | 12.3                 | 32.2                | 29.0                |
| 20             | 52.0    | 37.5                | 12.3                 | 25.2                | 30.2                |
| 25             | 45.2    | 32.6                | 12.3                 | 20.2                | 30.3                |
| 30             | 40.0    | 28.9                | 12.3                 | 16.5                | 29.8                |
| 35             | 36.1    | 26.0                | 12.3                 | 13.7                | 28.7                |
| 40             | 32.9    | 23.7                | 12.3                 | 11.4                | 27.3                |
| 45             | 30.2    | 21.8                | 12.3                 | 9.5                 | 25.6                |
| 50             | 28.0    | 20.2                | 12.3                 | 7.9                 | 23.6                |
| 55             | 26.2    | 18.9                | 12.3                 | 6.5                 | 21.6                |
| 60             | 24.6    | 17.7                | 12.3                 | 5.4                 | 19.3                |
| 65             | 23.2    | 16.7                | 12.3                 | 4.4                 | 17.0                |
| 70             | 21.9    | 15.8                | 12.3                 | 3.5                 | 14.5                |
| 75             | 20.8    | 15.0                | 12.3                 | 2.7                 | 12.0                |
| 80             | 19.8    | 14.3                | 12.3                 | 2.0                 | 9.4                 |
| 85             | 18.9    | 13.7                | 12.3                 | 1.3                 | 6.7                 |
| 90             | 18.1    | 13.1                | 12.3                 | 0.7                 | 4.0                 |
| 95             | 17.4    | 12.6                | 12.3                 | 0.2                 | 1.2                 |
| 100            | 16.7    | 12.1                | 12.1                 | 0.0                 | 0.0                 |
| 105            | 16.1    | 11.6                | 11.6                 | 0.0                 | 0.0                 |

2-year Q<sub>roof</sub>      **12.34 L/s**  
2-year Max. Storage Required      **30.3 m<sup>3</sup>**  
2-year Storage Depth      **0.067 m**  
2-year Estimated Drawdown Time      **0.77 hr**

**PREVIOUSLY APPROVED (D07-12-17-0186)**

Building ID      **BLDG D**  
Roof Area        0.101 ha  
Avail Storage Area      0.096  
C                  0.90 Rational Method runoff coefficient  
t<sub>c</sub>                10 min, t<sub>c</sub> at outlet without restriction

**Estimated Number of Roof Drains**

Building Length      20.2  
Building Width        53.1  
Number of Drains      5  
m<sup>2</sup> / Drain              192.7 max 232.25m<sup>2</sup>/notch as recommended by Zurn for Ottawa

| Roof Top Rating Curve per Zurn Model Z-105-5 |                   |                   |                    |                    |                   |                       |
|----------------------------------------------|-------------------|-------------------|--------------------|--------------------|-------------------|-----------------------|
| d                                            | A                 | V <sub>acc</sub>  | V <sub>avail</sub> | Q <sub>notch</sub> | Q <sub>roof</sub> | V <sub>drawdown</sub> |
| (m)                                          | (m <sup>2</sup> ) | (m <sup>3</sup> ) | (m <sup>3</sup> )  | (L/s)              | (L/s)             | (hr)                  |
| 0.000                                        | 0                 | 0.0               | 0.0                | 0.00               | 0.00              | 0.00                  |
| 0.025                                        | 60.2              | 0.5               | 0.5                | 0.38               | 1.90              | 0.07                  |
| 0.050                                        | 240.9             | 3.5               | 4.0                | 0.77               | 3.85              | 0.33                  |
| 0.075                                        | 542.0             | 9.5               | 13.6               | 1.14               | 5.70              | 0.79                  |
| 0.100                                        | 963.6             | 18.6              | 32.1               | 1.52               | 7.60              | 1.47                  |
| 0.125                                        | 963.6             | 24.1              | 56.2               | 1.90               | 9.50              | 2.17                  |
| 0.150                                        | 963.6             | 24.1              | 80.3               | 2.28               | 11.40             | 2.76                  |

\* Assumes one notch opening per drain, assumes maximum slope of 10cm

| 2-year         |         |                     |                      |                     |                     |
|----------------|---------|---------------------|----------------------|---------------------|---------------------|
| t <sub>c</sub> | i       | Q <sub>actual</sub> | Q <sub>release</sub> | Q <sub>stored</sub> | V <sub>stored</sub> |
| (min)          | (mm/hr) | (L/s)               | (L/s)                | (L/s)               | (m <sup>3</sup> )   |
| 5              | 103.6   | 26.3                | 5.0                  | 21.3                | 6.4                 |
| 10             | 76.8    | 19.5                | 5.0                  | 14.5                | 8.7                 |
| 15             | 61.8    | 15.7                | 5.0                  | 10.7                | 9.6                 |
| 20             | 52.0    | 13.2                | 5.0                  | 8.2                 | 9.9                 |
| 25             | 45.2    | 11.5                | 5.0                  | 6.5                 | 9.7                 |
| 30             | 40.0    | 10.2                | 5.0                  | 5.2                 | 9.3                 |
| 35             | 36.1    | 9.1                 | 5.0                  | 4.2                 | 8.7                 |
| 40             | 32.9    | 8.3                 | 5.0                  | 3.4                 | 8.0                 |
| 45             | 30.2    | 7.7                 | 5.0                  | 2.7                 | 7.3                 |
| 50             | 28.0    | 7.1                 | 5.0                  | 2.1                 | 6.4                 |
| 55             | 26.2    | 6.6                 | 5.0                  | 1.7                 | 5.5                 |
| 60             | 24.6    | 6.2                 | 5.0                  | 1.2                 | 4.5                 |
| 65             | 23.2    | 5.9                 | 5.0                  | 0.9                 | 3.5                 |
| 70             | 21.9    | 5.6                 | 5.0                  | 0.6                 | 2.4                 |
| 75             | 20.8    | 5.3                 | 5.0                  | 0.3                 | 1.3                 |
| 80             | 19.8    | 5.0                 | 5.0                  | 0.0                 | 0.2                 |
| 85             | 18.9    | 4.8                 | 4.8                  | 0.0                 | 0.0                 |
| 90             | 18.1    | 4.6                 | 4.6                  | 0.0                 | 0.0                 |
| 95             | 17.4    | 4.4                 | 4.4                  | 0.0                 | 0.0                 |
| 100            | 16.7    | 4.2                 | 4.2                  | 0.0                 | 0.0                 |
| 105            | 16.1    | 4.1                 | 4.1                  | 0.0                 | 0.0                 |

2-year Q<sub>roof</sub>                      **4.98 L/s**  
2-year Max. Storage Required                      **9.9 m<sup>3</sup>**  
2-year Storage Depth                                      **0.065 m**  
2-year Estimated Drawdown Time                      **0.61 hr**

**PREVIOUSLY APPROVED (D07-12-17-0186)**

**Building ID: UT. BLDG G**

|                           |                                                      |
|---------------------------|------------------------------------------------------|
| <b>Roof Area</b>          | 0.097 ha                                             |
| <b>Avail Storage Area</b> | 0.092                                                |
| <b>C</b>                  | 0.90 Rational Method runoff coefficient              |
| <b>t<sub>c</sub></b>      | 10 min, t <sub>c</sub> at outlet without restriction |

**Estimated Number of Roof Drains**

|                              |                                                                         |
|------------------------------|-------------------------------------------------------------------------|
| <b>Building Length</b>       | 20.2                                                                    |
| <b>Building Width</b>        | 53.1                                                                    |
| <b>Number of Drains</b>      | 5                                                                       |
| <b>m<sup>2</sup> / Drain</b> | 184.4 max 232.25m <sup>2</sup> /notch as recommended by Zurn for Ottawa |

| Roof Top Rating Curve per Zurn Model Z-105-5 |                   |                   |                    |                    |                   |                       |
|----------------------------------------------|-------------------|-------------------|--------------------|--------------------|-------------------|-----------------------|
| d                                            | A                 | V <sub>acc</sub>  | V <sub>avail</sub> | Q <sub>notch</sub> | Q <sub>roof</sub> | V <sub>drawdown</sub> |
| (m)                                          | (m <sup>2</sup> ) | (m <sup>3</sup> ) | (m <sup>3</sup> )  | (L/s)              | (L/s)             | (hr)                  |
| 0.000                                        | 0                 | 0.0               | 0.0                | 0.00               | 0.00              | 0.00                  |
| 0.025                                        | 57.6              | 0.5               | 0.5                | 0.38               | 1.90              | 0.07                  |
| 0.050                                        | 230.4             | 3.4               | 3.8                | 0.77               | 3.85              | 0.31                  |
| 0.075                                        | 518.5             | 9.1               | 13.0               | 1.14               | 5.70              | 0.76                  |
| 0.100                                        | 921.8             | 17.8              | 30.7               | 1.52               | 7.60              | 1.41                  |
| 0.125                                        | 921.8             | 23.0              | 53.8               | 1.90               | 9.50              | 2.08                  |
| 0.150                                        | 921.8             | 23.0              | 76.8               | 2.28               | 11.40             | 2.64                  |

\* Assumes one notch opening per drain, assumes maximum slope of 10cm

| 2-year         |         |                     |                      |                     |                     |
|----------------|---------|---------------------|----------------------|---------------------|---------------------|
| t <sub>c</sub> | i       | Q <sub>actual</sub> | Q <sub>release</sub> | Q <sub>stored</sub> | V <sub>stored</sub> |
| (min)          | (mm/hr) | (L/s)               | (L/s)                | (L/s)               | (m <sup>3</sup> )   |
| 5              | 103.6   | 25.1                | 4.9                  | 20.2                | 6.1                 |
| 10             | 76.8    | 18.6                | 4.9                  | 13.7                | 8.2                 |
| 15             | 61.8    | 15.0                | 4.9                  | 10.0                | 9.0                 |
| 20             | 52.0    | 12.6                | 4.9                  | 7.7                 | 9.2                 |
| 25             | 45.2    | 11.0                | 4.9                  | 6.0                 | 9.0                 |
| 30             | 40.0    | 9.7                 | 4.9                  | 4.8                 | 8.6                 |
| 35             | 36.1    | 8.7                 | 4.9                  | 3.8                 | 8.0                 |
| 40             | 32.9    | 8.0                 | 4.9                  | 3.0                 | 7.3                 |
| 45             | 30.2    | 7.3                 | 4.9                  | 2.4                 | 6.5                 |
| 50             | 28.0    | 6.8                 | 4.9                  | 1.9                 | 5.6                 |
| 55             | 26.2    | 6.3                 | 4.9                  | 1.4                 | 4.6                 |
| 60             | 24.6    | 6.0                 | 4.9                  | 1.0                 | 3.7                 |
| 65             | 23.2    | 5.6                 | 4.9                  | 0.7                 | 2.6                 |
| 70             | 21.9    | 5.3                 | 4.9                  | 0.4                 | 1.6                 |
| 75             | 20.8    | 5.0                 | 4.9                  | 0.1                 | 0.5                 |
| 80             | 19.8    | 4.8                 | 4.8                  | 0.0                 | 0.0                 |
| 85             | 18.9    | 4.6                 | 4.6                  | 0.0                 | 0.0                 |
| 90             | 18.1    | 4.4                 | 4.4                  | 0.0                 | 0.0                 |
| 95             | 17.4    | 4.2                 | 4.2                  | 0.0                 | 0.0                 |
| 100            | 16.7    | 4.1                 | 4.1                  | 0.0                 | 0.0                 |
| 105            | 16.1    | 3.9                 | 3.9                  | 0.0                 | 0.0                 |

|                                       |                          |
|---------------------------------------|--------------------------|
| <b>2-year Q<sub>roof</sub></b>        | <b>4.94 L/s</b>          |
| <b>2-year Max. Storage Required</b>   | <b>9.2 m<sup>3</sup></b> |
| <b>2-year Storage Depth</b>           | <b>0.065 m</b>           |
| <b>2-year Estimated Drawdown Time</b> | <b>0.57 hr</b>           |



**PREVIOUSLY APPROVED (D07-12-17-0186)**

**Estimated Post Development Peak Flow from Attenuated Areas**

**Area ID**

**A**

**Maintenance Structures**

| ID                                       | STM100 | STM101A | STM101B | STM102 | STM103 | STM104 | STM105 | STM106 | STM107 |
|------------------------------------------|--------|---------|---------|--------|--------|--------|--------|--------|--------|
| Structure dia (mm)                       | 1500   | 1500    | 1500    | 1200   | 1200   | 1800   | 1200   | 1200   | 1200   |
| T/L*                                     | 102.85 | 103.55  | 103.55  | 103.55 | 103.55 | 103.55 | 103.55 | 103.55 | 103.55 |
| INV                                      | 101.16 | 101.44  | 101.51  | 101.78 | 101.71 | 101.61 | 101.70 | 101.76 | 101.81 |
| Depth                                    | 1.69   | 2.11    | 2.04    | 1.77   | 1.84   | 1.94   | 1.85   | 1.79   | 1.94   |
| V <sub>structure</sub> (m <sup>3</sup> ) | 3.0    | 3.7     | 3.6     | 2.0    | 2.1    | 4.9    | 2.1    | 2.0    | 2.2    |

| ID                                       | CBMH108 | CBMH109 | CBMH110 | STM111 | STM112 | STM113 | STM113A | CBMH114 | CBMH37 |
|------------------------------------------|---------|---------|---------|--------|--------|--------|---------|---------|--------|
| Structure dia (mm)                       | 1200    | 1200    | 1200    | 1200   | 1200   | 1200   | 1200    | 1200    | 1200   |
| T/L*                                     | 103.30  | 103.30  | 103.30  | 103.54 | 103.50 | 103.55 | 103.55  | 103.55  | 103.55 |
| INV                                      | 101.88  | 101.82  | 101.78  | 101.86 | 101.98 | 101.89 | 101.79  | 102.22  | 102.33 |
| Depth                                    | 1.42    | 1.48    | 1.52    | 1.68   | 1.52   | 1.66   | 1.76    | 1.33    | 1.22   |
| V <sub>structure</sub> (m <sup>3</sup> ) | 1.6     | 1.7     | 1.7     | 1.9    | 1.7    | 1.9    | 2.0     | 1.5     | 1.4    |

| ID                                       | CICB1  | CICB2  | CB3    | CB4    | CB5    | CICB6  | CICB7  | CICB9  | CICB10 |
|------------------------------------------|--------|--------|--------|--------|--------|--------|--------|--------|--------|
| Structure dia (mm)                       | 600    | 600    | 600    | 600    | 600    | 600    | 600    | 600    | 600    |
| T/L*                                     | 103.53 | 103.53 | 103.45 | 103.25 | 103.47 | 103.44 | 103.44 | 103.55 | 103.55 |
| INV                                      | 102.03 | 102.03 | 101.95 | 102.01 | 101.97 | 101.94 | 101.94 | 102.21 | 102.21 |
| Depth                                    | 1.50   | 1.50   | 1.50   | 1.24   | 1.50   | 1.50   | 1.50   | 1.34   | 1.34   |
| V <sub>structure</sub> (m <sup>3</sup> ) | 0.4    | 0.5    | 0.5    | 0.5    | 0.5    | 0.5    | 0.5    | 0.5    | 0.5    |

| ID                                       | CICB11 | CICB12 | CB13   | CB14   | CB15   | CB16   | CB17   | CB18   | CB19   |
|------------------------------------------|--------|--------|--------|--------|--------|--------|--------|--------|--------|
| Structure dia (mm)                       | 600    | 600    | 600    | 600    | 600    | 600    | 600    | 600    | 600    |
| T/L*                                     | 103.50 | 103.50 | 103.40 | 103.40 | 103.25 | 103.40 | 103.25 | 103.40 | 103.25 |
| INV                                      | 102.05 | 102.05 | 102.08 | 102.12 | 102.19 | 102.16 | 102.23 | 102.21 | 102.28 |
| Depth                                    | 1.45   | 1.45   | 1.32   | 1.28   | 1.06   | 1.24   | 1.02   | 1.19   | 0.97   |
| V <sub>structure</sub> (m <sup>3</sup> ) | 0.5    | 0.5    | 0.5    | 0.5    | 0.5    | 0.5    | 0.5    | 0.5    | 0.4    |

| ID                                       | CB20   | CB21   | CB22   | CB23   | CB24   | CB25   | CB26   | CB27   | CB28   |
|------------------------------------------|--------|--------|--------|--------|--------|--------|--------|--------|--------|
| Structure dia (mm)                       | 600    | 600    | 600    | 600    | 600    | 600    | 600    | 600    | 600    |
| T/L*                                     | 103.25 | 103.40 | 103.40 | 103.05 | 103.55 | 103.30 | 103.30 | 103.30 | 103.30 |
| INV                                      | 102.00 | 102.17 | 102.20 | 102.24 | 102.19 | 102.06 | 102.03 | 102.06 | 101.91 |
| Depth                                    | 1.25   | 1.23   | 1.20   | 0.81   | 1.36   | 1.24   | 1.27   | 1.24   | 1.39   |
| V <sub>structure</sub> (m <sup>3</sup> ) | 0.5    | 0.5    | 0.5    | 0.4    | 0.5    | 0.5    | 0.5    | 0.5    | 0.5    |

| ID                                       | CB29   | CB30   | CICB31 | CICB32 | CICB33 | CICB34 | CICB35 | CICB36 |
|------------------------------------------|--------|--------|--------|--------|--------|--------|--------|--------|
| Structure dia (mm)                       | 600    | 600    | 600    | 600    | 600    | 600    | 600    | 600    |
| T/L*                                     | 103.30 | 103.30 | 103.40 | 103.40 | 103.55 | 103.55 | 103.55 | 103.55 |
| INV                                      | 101.98 | 102.16 | 101.90 | 101.90 | 102.45 | 102.45 | 102.65 | 102.65 |
| Depth                                    | 1.32   | 1.14   | 1.50   | 1.50   | 1.10   | 1.10   | 0.90   | 0.90   |
| V <sub>structure</sub> (m <sup>3</sup> ) | 0.5    | 0.5    | 0.5    | 0.5    | 0.4    | 0.4    | 0.3    | 0.3    |

**Sewers**

| ID                                   | 200mm | 250mm | 300mm | 375mm | 450mm | 525mm | 600mm | 675mm | 825mm |
|--------------------------------------|-------|-------|-------|-------|-------|-------|-------|-------|-------|
| Storage Pipe Dia (mm)                | 200   | 250   | 300   | 375   | 450   | 525   | 600   | 675   | 825   |
| L (m)                                | 163.8 | 219.9 | 117.9 | 109   | 141.5 | 46.2  | 88.8  | 27.9  | 0     |
| V <sub>sewer</sub> (m <sup>3</sup> ) | 5.1   | 10.8  | 8.3   | 12.0  | 22.5  | 10.0  | 25.1  | 10.0  | 0.0   |

\*Top of lid or max ponding elevation (103.55)

| ID                                   | 900mm | UG Storage |
|--------------------------------------|-------|------------|
| Storage Pipe Dia (mm)                | 900   | 0          |
| L (m)                                | 86.4  | 0          |
| V <sub>sewer</sub> (m <sup>3</sup> ) | 55.0  | 76.0       |

\*Top of lid or max ponding elevation (103.55)

|                                            |       |
|--------------------------------------------|-------|
| Total U/G Storage (m <sup>3</sup> )        | 76.0  |
| Total Structure Storage (m <sup>3</sup> )  | 217.0 |
| Total Subsurface Storage (m <sup>3</sup> ) | 293.0 |

**PREVIOUSLY APPROVED (D07-12-17-0186)**

**Stage Attenuated Areas Storage Summary**

| Stage         | Surface Storage |                   |                |         | Surface and Subsurface Storage |                     |                             |                               |            |              |                         |                           |
|---------------|-----------------|-------------------|----------------|---------|--------------------------------|---------------------|-----------------------------|-------------------------------|------------|--------------|-------------------------|---------------------------|
|               | Stage           | Ponding           | h <sub>o</sub> | delta d | V*                             | V <sub>acc</sub> ** | 2-yr Q <sub>release</sub> † | 100-yr Q <sub>release</sub> † | 2-yr Elev. | 100-yr Elev. | h <sub>o, eff</sub> 2Yr | h <sub>o, eff</sub> 100yr |
|               | (m)             | (m <sup>2</sup> ) | (m)            | (m)     | (m <sup>3</sup> )              | (m <sup>3</sup> )   | (L/s)                       | (L/s)                         | (m)        | (m)          | (m)                     | (m)                       |
| Orifice INV   | 101.44          | -                 | 0.00           |         |                                | 0.0                 | 0.0                         | 0.0                           | 101.91     | 102.52       | 0.00                    | 0.00                      |
| Cistern INV   | 101.99          | -                 | 0.55           | 0.55    | 146.5                          | 146.5               | 0.0                         | 0.0                           | 101.91     | 102.52       | 0.00                    | 0.00                      |
| Cistern OBV   | 102.63          | -                 | 1.19           | 0.64    | 146.5                          | 293.0               | 152.0                       | 0.0                           | 101.91     | 102.52       | 0.72                    | 0.00                      |
| T/L1          | 103.25          | 0.4               | 1.81           | 0.63    | 0.1                            | 293.1               | 208.0                       | 153.5                         | 101.91     | 102.52       | 1.34                    | 0.73                      |
| T/L2          | 103.30          | 150.3             | 1.86           | 0.05    | 2.6                            | 295.7               | 211.9                       | 158.7                         | 101.91     | 102.52       | 1.39                    | 0.78                      |
| T/L3          | 103.35          | 795.8             | 1.91           | 0.05    | 21.5                           | 317.3               | 215.6                       | 163.7                         | 101.91     | 102.52       | 1.44                    | 0.83                      |
| 0.15m Ponding | 103.40          | 2067.2            | 1.96           | 0.05    | 69.1                           | 386.4               | 219.4                       | 168.6                         | 101.91     | 102.52       | 1.49                    | 0.88                      |
| Max Ponding   | 103.55          | 8923.7            | 2.11           | 0.15    | 764.3                          | 1150.7              | 230.1                       | 182.4                         | 101.91     | 102.52       | 1.64                    | 1.03                      |

\* V=Incremental storage volume

\*\*V<sub>acc</sub>=Total surface and sub-surface

† Q<sub>release</sub> = Release rate calculated from orifice equation accounting for backwater using the 5-year and 100-year waterlevels respectively

$$Q = C_d \times A \times \sqrt{2 \times g \times h_o}$$

Where Q = Release rate (cms)

C<sub>d</sub> =Discharge Coefficient (0.61)

A= Area of the orifice(m<sup>2</sup>)

g =gravitational constant (9.81m/s<sup>2</sup>)

h<sub>o eff</sub> =Effective head above the orifice due to waterlevel at outlet

Orifice Location **STM101** Dia 291  
Total Area 2.810 ha  
C 0.81 Rational Method runoff coefficient

| t <sub>c</sub><br>(min) | 2-year       |                                           |                               |                              |                                                        |
|-------------------------|--------------|-------------------------------------------|-------------------------------|------------------------------|--------------------------------------------------------|
|                         | i<br>(mm/hr) | Q <sub>actual</sub> <sup>†</sup><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub> <sup>††</sup><br>(m <sup>3</sup> ) |
| 5                       | 103.6        | 698.0                                     | 139.4                         | 558.7                        | 167.6                                                  |
| 10                      | 76.8         | 527.8                                     | 139.4                         | 388.4                        | 233.1                                                  |
| 15                      | 61.8         | 432.2                                     | 139.4                         | 292.8                        | 263.5                                                  |
| 20                      | 52.0         | 370.3                                     | 139.4                         | 230.9                        | 277.1                                                  |
| 25                      | 45.2         | 326.6                                     | 139.4                         | 187.3                        | 280.9                                                  |
| 30                      | 40.0         | 294.1                                     | 139.4                         | 154.7                        | 278.4                                                  |
| 35                      | 36.1         | 268.7                                     | 139.4                         | 129.3                        | 271.6                                                  |
| 40                      | 32.9         | 248.4                                     | 139.4                         | 109.0                        | 261.7                                                  |
| 45                      | 30.2         | 231.7                                     | 139.4                         | 92.3                         | 249.3                                                  |
| 50                      | 28.0         | 217.7                                     | 139.4                         | 78.4                         | 235.1                                                  |
| 55                      | 26.2         | 205.8                                     | 139.4                         | 66.5                         | 219.3                                                  |
| 60                      | 24.6         | 195.6                                     | 139.4                         | 56.2                         | 202.4                                                  |
| 65                      | 23.2         | 186.6                                     | 139.4                         | 47.3                         | 184.3                                                  |
| 70                      | 21.9         | 178.8                                     | 139.4                         | 39.4                         | 165.4                                                  |
| 75                      | 20.8         | 171.8                                     | 139.4                         | 32.4                         | 145.8                                                  |
| 80                      | 19.8         | 165.5                                     | 139.4                         | 26.1                         | 125.5                                                  |
| 85                      | 18.9         | 159.9                                     | 139.4                         | 20.5                         | 104.6                                                  |
| 90                      | 18.1         | 154.8                                     | 139.4                         | 15.4                         | 83.3                                                   |
| 95                      | 17.4         | 150.2                                     | 139.4                         | 10.8                         | 61.4                                                   |
| 100                     | 16.7         | 145.9                                     | 139.4                         | 6.5                          | 39.2                                                   |
| 105                     | 16.1         | 142.0                                     | 139.4                         | 2.6                          | 16.6                                                   |

† Includes controlled flow from BLDG A-G

†† Does not Include maintenance structure or sewer storage

**2-year Q<sub>attenuated</sub> 139.38 L/s**  
**2-year Max. Storage Required 281 m<sup>3</sup>**  
**Est. 2-year Storage Elevation 102.57 m**

PREVIOUSLY APPROVED (D07-12-17-0186)

| Area ID | Up       | Down    | Area<br>(ha) | C<br>(°) | Indiv AxC | Acc AxC | T <sub>c</sub><br>(min) | I<br>(mm/hr) | Q <sub>total</sub><br>(L/s) | DIA<br>(mm) | Slope<br>(%) | Length<br>(m) | A <sub>equivalent</sub><br>(m²) | R<br>(m) | Velocity<br>(m/s) | Qcap<br>(L/s) | Time Flow<br>(min) | Q / Q full<br>(%) |
|---------|----------|---------|--------------|----------|-----------|---------|-------------------------|--------------|-----------------------------|-------------|--------------|---------------|---------------------------------|----------|-------------------|---------------|--------------------|-------------------|
|         |          |         |              |          |           |         |                         |              |                             |             |              |               |                                 |          |                   |               |                    |                   |
|         | BLDG A   | STM113  | 0.190        | 0.90     | 0.17      | 0.17    | 10.0                    | 104.2        | 1.5                         | 250         | 1.00         | 7.9           | 0.049                           | 0.063    | 1.21              | 59.5          | 0.1                | 0.03              |
|         |          |         |              |          |           |         | 10.1                    |              |                             |             |              |               |                                 |          |                   |               |                    |                   |
| A32     | CBMH37   | CBMH114 | 0.062        | 0.55     | 0.03      | 0.03    | 10.1                    | 103.6        | 9.8                         | 250         | 0.47         | 21.9          | 0.049                           | 0.063    | 0.83              | 40.8          | 0.4                | 0.24              |
| A31     | CBMH114  | STM113  | 0.046        | 0.85     | 0.04      | 0.07    | 10.5                    | 107.4        | 20.6                        | 250         | 0.44         | 22.7          | 0.049                           | 0.063    | 0.80              | 39.4          | 0.5                | 0.32              |
|         |          |         |              |          |           |         | 11.0                    |              |                             |             |              |               |                                 |          |                   |               |                    |                   |
|         | BLDG C   | STM113  | 0.288        | 0.90     | 0.26      | 0.26    | 10.0                    | 104.2        | 14.2                        | 300         | 1.00         | 2.6           | 0.071                           | 0.075    | 1.37              | 96.7          | 0.0                | 0.15              |
|         |          |         |              |          |           |         | 10.0                    |              |                             |             |              |               |                                 |          |                   |               |                    |                   |
| A30     | CICB3536 | STM113  | 0.056        | 0.75     | 0.04      | 0.04    | 10.0                    | 104.2        | 11.9                        | 200         | 1.00         | 6             | 0.031                           | 0.050    | 1.04              | 32.8          | 0.1                | 0.36              |
|         |          |         |              |          |           |         | 10.1                    |              |                             |             |              |               |                                 |          |                   |               |                    |                   |
|         | STM113   | STM113A |              |          | 0.00      | 0.26    | 11.0                    | 99.1         | 94.1                        | 450         | 0.25         | 37.2          | 0.159                           | 0.113    | 0.90              | 142.6         | 0.7                | 0.66              |
|         |          |         |              |          |           |         | 11.7                    |              |                             |             |              |               |                                 |          |                   |               |                    |                   |
| A29     | CICB3324 | STM113A | 0.042        | 0.85     | 0.04      | 0.04    | 10.0                    | 104.2        | 10.2                        | 200         | 1.00         | 5.9           | 0.031                           | 0.050    | 1.04              | 32.8          | 0.1                | 0.31              |
|         |          |         |              |          |           |         | 10.1                    |              |                             |             |              |               |                                 |          |                   |               |                    |                   |
| A28     | CICB3132 | STM113A | 0.091        | 0.83     | 0.08      | 0.08    | 10.0                    | 104.2        | 21.8                        | 200         | 1.00         | 5.9           | 0.031                           | 0.050    | 1.04              | 32.8          | 0.1                | 0.66              |
|         |          |         |              |          |           |         | 10.1                    |              |                             |             |              |               |                                 |          |                   |               |                    |                   |
|         | STM113A  | STM104  |              |          | 0.00      | 0.40    | 11.7                    | 95.9         | 121.1                       | 450         | 0.25         | 70            | 0.159                           | 0.113    | 0.90              | 142.6         | 1.3                | 0.85              |
|         |          |         |              |          |           |         | 13.0                    |              |                             |             |              |               |                                 |          |                   |               |                    |                   |
| A19     | CB25     | CBMH108 | 0.251        | 0.80     | 0.20      | 0.20    | 10.0                    | 104.2        | 59.5                        | 300         | 1.00         | 17.3          | 0.071                           | 0.075    | 1.37              | 96.7          | 0.2                | 0.60              |
| A20     | CBMH108  | STM107  | 0.111        | 0.81     | 0.09      | 0.29    | 10.2                    | 103.1        | 83.5                        | 450         | 0.26         | 14            | 0.159                           | 0.113    | 0.97              | 153.5         | 0.2                | 0.54              |
|         |          |         |              |          |           |         | 10.5                    |              |                             |             |              |               |                                 |          |                   |               |                    |                   |
| A18     | CB24     | STM107  | 0.020        | 0.24     | 0.00      | 0.00    | 10.0                    | 104.2        | 1.4                         | 200         | 1.00         | 31.7          | 0.031                           | 0.050    | 1.04              | 32.8          | 0.5                | 0.04              |
|         |          |         |              |          |           |         | 10.5                    |              |                             |             |              |               |                                 |          |                   |               |                    |                   |
|         | BLDG B   | STM107  | 0.140        | 0.90     | 0.13      | 0.13    | 10.0                    | 104.2        | 7.1                         | 250         | 1.00         | 3.7           | 0.049                           | 0.063    | 1.21              | 59.5          | 0.1                | 0.12              |
|         |          |         |              |          |           |         | 10.1                    |              |                             |             |              |               |                                 |          |                   |               |                    |                   |
|         | STM107   | STM106  |              |          | 0.00      | 0.30    | 10.5                    | 101.6        | 90.7                        | 450         | 0.25         | 20.3          | 0.159                           | 0.113    | 0.90              | 142.6         | 0.4                | 0.64              |
|         |          |         |              |          |           |         | 10.9                    |              |                             |             |              |               |                                 |          |                   |               |                    |                   |
| A22     | CB27     |         | 0.055        | 0.86     | 0.05      | 0.05    | 10.0                    | 104.2        | 13.6                        | 200         | 1.00         | 3.1           | 0.031                           | 0.050    | 1.04              | 32.8          | 0.0                | 0.42              |
| A21     | CB26     | CBMH109 | 0.073        | 0.87     | 0.06      | 0.11    | 10.0                    | 103.9        | 31.9                        | 250         | 1.00         | 19.9          | 0.049                           | 0.063    | 1.21              | 59.5          | 0.3                | 0.54              |
|         |          |         |              |          |           |         | 10.3                    |              |                             |             |              |               |                                 |          |                   |               |                    |                   |
| A24     | CB28     | CBMH109 | 0.028        | 0.84     | 0.02      | 0.02    | 10.0                    | 104.2        | 6.8                         | 200         | 1.00         | 3             | 0.031                           | 0.050    | 1.04              | 32.8          | 0.0                | 0.21              |
|         |          |         |              |          |           |         | 10.0                    |              |                             |             |              |               |                                 |          |                   |               |                    |                   |
| A24     | CBMH109  | STM106  | 0.028        | 0.84     | 0.02      | 0.16    | 10.3                    | 102.5        | 44.9                        | 375         | 0.26         | 11.4          | 0.110                           | 0.094    | 0.81              | 89.4          | 0.2                | 0.50              |
|         |          |         |              |          |           |         | 10.6                    |              |                             |             |              |               |                                 |          |                   |               |                    |                   |
|         | STM106   | STM105  |              |          | 0.00      | 0.45    | 10.9                    | 99.7         | 132.9                       | 525         | 0.26         | 19.2          | 0.216                           | 0.131    | 1.01              | 219.3         | 0.3                | 0.61              |
|         |          |         |              |          |           |         | 11.2                    |              |                             |             |              |               |                                 |          |                   |               |                    |                   |
| A25     | CB29     | CBMH110 | 0.166        | 0.80     | 0.13      | 0.13    | 10.0                    | 104.2        | 38.5                        | 250         | 1.00         | 17.3          | 0.049                           | 0.063    | 1.21              | 59.5          | 0.2                | 0.65              |
| A26     | CBMH110  | STM105  | 0.062        | 0.86     | 0.05      | 0.16    | 10.2                    | 103.0        | 51.0                        | 375         | 0.36         | 14            | 0.110                           | 0.094    | 0.95              | 105.2         | 0.2                | 0.48              |
|         |          |         |              |          |           |         | 10.5                    |              |                             |             |              |               |                                 |          |                   |               |                    |                   |
|         | BLDG BB  | STM105  | 0.041        | 0.90     | 0.04      | 0.04    | 10.0                    | 104.2        | 2.3                         | 250         | 1.00         | 3.7           | 0.049                           | 0.063    | 1.21              | 59.5          | 0.1                | 0.04              |
|         |          |         |              |          |           |         | 10.1                    |              |                             |             |              |               |                                 |          |                   |               |                    |                   |
| A27     | CB30     | STM105  | 0.025        | 0.70     | 0.02      | 0.02    | 10.0                    | 104.2        | 5.1                         | 200         | 1.00         | 12.3          | 0.031                           | 0.050    | 1.04              | 32.8          | 0.2                | 0.16              |
|         |          |         |              |          |           |         | 10.2                    |              |                             |             |              |               |                                 |          |                   |               |                    |                   |
|         | STM105   | STM104  |              |          | 0.00      | 0.65    | 11.2                    | 98.3         | 186.8                       | 525         | 0.22         | 27            | 0.216                           | 0.131    | 0.93              | 201.7         | 0.5                | 0.93              |
|         |          |         |              |          |           |         | 11.7                    |              |                             |             |              |               |                                 |          |                   |               |                    |                   |
| A17     | CB23     |         | 0.070        | 0.90     | 0.06      | 0.06    | 10.0                    | 104.2        | 18.3                        | 250         | 0.44         | 54.2          | 0.049                           | 0.063    | 0.80              | 39.4          | 1.1                | 0.46              |
|         |          |         |              |          |           |         | 11.1                    |              |                             |             |              |               |                                 |          |                   |               |                    |                   |
| A16     | CB22     | STM112  | 0.074        | 0.75     | 0.06      | 0.06    | 10.0                    | 104.2        | 16.1                        | 250         | 1.00         | 5.7           | 0.049                           | 0.063    | 1.21              | 59.5          | 0.1                | 0.27              |
|         |          |         |              |          |           |         | 10.1                    |              |                             |             |              |               |                                 |          |                   |               |                    |                   |
| A15     | CB21     | STM112  | 0.052        | 0.80     | 0.04      | 0.04    | 10.0                    | 104.2        | 12.0                        | 250         | 1.00         | 5.7           | 0.049                           | 0.063    | 1.21              | 59.5          | 0.1                | 0.20              |
|         |          |         |              |          |           |         | 10.1                    |              |                             |             |              |               |                                 |          |                   |               |                    |                   |
|         | STM112   | STM111  |              |          | 0.00      | 0.16    | 11.1                    | 98.6         | 43.9                        | 375         | 0.25         | 36.3          | 0.110                           | 0.094    | 0.79              | 87.7          | 0.8                | 0.50              |
|         |          |         |              |          |           |         | 11.9                    |              |                             |             |              |               |                                 |          |                   |               |                    |                   |

|     |                   |         |       |      |      |      |      |       |       |     |      |      |       |       |      |        |     |      |
|-----|-------------------|---------|-------|------|------|------|------|-------|-------|-----|------|------|-------|-------|------|--------|-----|------|
| A14 | CB20              | STM111  | 0.136 | 0.77 | 0.11 | 0.11 | 10.0 | 104.2 | 30.4  | 200 | 1.00 | 11.6 | 0.031 | 0.050 | 1.04 | 32.3   | 0.2 | 0.33 |
|     |                   |         |       |      |      |      | 10.2 |       |       |     |      |      |       |       |      |        |     |      |
| A13 | CB19              | STM111  | 0.125 | 0.84 | 0.10 | 0.10 | 10.0 | 104.2 | 30.3  | 200 | 1.00 | 19.4 | 0.031 | 0.050 | 1.04 | 32.3   | 0.3 | 0.92 |
|     |                   |         |       |      |      |      | 10.3 |       |       |     |      |      |       |       |      |        |     |      |
| A12 | CB18              | STM111  | 0.141 | 0.88 | 0.12 | 0.12 | 10.0 | 104.2 | 35.8  | 250 | 1.00 | 12.2 | 0.049 | 0.063 | 1.21 | 59.5   | 0.2 | 0.60 |
|     |                   |         |       |      |      |      | 10.2 |       |       |     |      |      |       |       |      |        |     |      |
| A11 | CB17              | STM111  | 0.071 | 0.85 | 0.06 | 0.06 | 10.0 | 104.2 | 17.3  | 200 | 1.00 | 19.4 | 0.031 | 0.050 | 1.04 | 32.3   | 0.3 | 0.53 |
|     |                   |         |       |      |      |      | 10.3 |       |       |     |      |      |       |       |      |        |     |      |
| A10 | CB16              | STM111  | 0.116 | 0.87 | 0.10 | 0.10 | 10.0 | 104.2 | 29.2  | 250 | 1.00 | 12.2 | 0.049 | 0.063 | 1.21 | 59.5   | 0.2 | 0.49 |
|     |                   |         |       |      |      |      | 10.2 |       |       |     |      |      |       |       |      |        |     |      |
| A9  | CB15              | STM111  | 0.121 | 0.86 | 0.10 | 0.10 | 10.0 | 104.2 | 30.2  | 200 | 1.00 | 19.3 | 0.031 | 0.050 | 1.04 | 32.3   | 0.3 | 0.92 |
|     |                   |         |       |      |      |      | 10.3 |       |       |     |      |      |       |       |      |        |     |      |
| A8  | CB14              | STM111  | 0.121 | 0.87 | 0.11 | 0.11 | 10.0 | 104.2 | 30.5  | 250 | 1.00 | 12.2 | 0.049 | 0.063 | 1.21 | 59.5   | 0.2 | 0.51 |
|     |                   |         |       |      |      |      | 10.2 |       |       |     |      |      |       |       |      |        |     |      |
| A7  | CB13              | STM111  | 0.058 | 0.81 | 0.05 | 0.05 | 10.0 | 104.2 | 13.7  | 250 | 1.00 | 12.3 | 0.049 | 0.063 | 1.21 | 59.5   | 0.2 | 0.23 |
|     |                   |         |       |      |      |      | 10.2 |       |       |     |      |      |       |       |      |        |     |      |
|     | STM111            | STM104  | 0.00  | 0.91 | 0.00 | 0.91 | 11.9 | 95.2  | 241.1 | 600 | 0.25 | 88.3 | 0.283 | 0.150 | 1.09 | 307.0  | 1.4 | 0.79 |
|     |                   |         |       |      |      |      | 13.2 |       |       |     |      |      |       |       |      |        |     |      |
| A6  | C1CB11/12         | STM104  | 0.039 | 0.81 | 0.03 | 0.03 | 10.0 | 104.2 | 9.1   | 200 | 1.00 | 5.3  | 0.031 | 0.050 | 1.04 | 32.3   | 0.1 | 0.28 |
|     |                   |         |       |      |      |      | 10.1 |       |       |     |      |      |       |       |      |        |     |      |
|     | STM104            | STM101B | 0.00  | 1.99 | 0.00 | 1.99 | 13.2 | 89.7  | 520.5 | 900 | 0.13 | 39.9 | 0.636 | 0.225 | 1.03 | 652.7  | 0.6 | 0.80 |
|     |                   |         |       |      |      |      | 13.9 |       |       |     |      |      |       |       |      |        |     |      |
| A5  | C1CB9/10          | STM102  | 0.072 | 0.73 | 0.05 | 0.05 | 10.0 | 104.2 | 15.2  | 200 | 1.00 | 6.2  | 0.031 | 0.050 | 1.04 | 32.3   | 0.1 | 0.46 |
|     |                   |         |       |      |      |      | 10.1 |       |       |     |      |      |       |       |      |        |     |      |
| A4  | C1CB6/7           | STM102  | 0.121 | 0.78 | 0.09 | 0.09 | 10.0 | 104.2 | 27.3  | 200 | 1.00 | 6.2  | 0.031 | 0.050 | 1.04 | 32.3   | 0.1 | 0.83 |
|     |                   |         |       |      |      |      | 10.1 |       |       |     |      |      |       |       |      |        |     |      |
|     | STM102            | STM101B | 0.00  | 0.15 | 0.00 | 0.15 | 10.1 | 103.7 | 42.3  | 300 | 0.35 | 71.2 | 0.071 | 0.075 | 0.81 | 57.2   | 1.5 | 0.74 |
|     |                   |         |       |      |      |      | 11.6 |       |       |     |      |      |       |       |      |        |     |      |
| A2  | CB3/5             | STM101B | 0.036 | 0.79 | 0.03 | 0.03 | 10.0 | 104.2 | 8.3   | 200 | 1.00 | 2.1  | 0.031 | 0.050 | 1.04 | 32.3   | 0.0 | 0.25 |
|     |                   |         |       |      |      |      | 10.0 |       |       |     |      |      |       |       |      |        |     |      |
|     | FUT. BLDG G       | STM103  | 0.087 | 0.90 |      |      | 10.0 | 104.2 | 5.8   | 250 | 1.00 | 34.6 | 0.049 | 0.063 | 1.21 | 59.5   | 0.5 | 0.10 |
|     |                   |         |       |      |      |      | 10.5 |       |       |     |      |      |       |       |      |        |     |      |
| A3  | CB4               | STM103  | 0.303 | 0.86 | 0.26 | 0.26 | 10.0 | 104.2 | 75.6  | 300 | 1.00 | 26.8 | 0.071 | 0.075 | 1.37 | 96.7   | 0.3 | 0.78 |
|     |                   |         |       |      |      |      | 10.3 |       |       |     |      |      |       |       |      |        |     |      |
|     | BLDG D            | STM103  | 0.101 | 0.90 |      |      | 10.0 | 104.2 | 5.8   | 250 | 1.00 | 3.5  | 0.049 | 0.063 | 1.21 | 59.5   | 0.0 | 0.10 |
|     |                   |         |       |      |      |      | 10.0 |       |       |     |      |      |       |       |      |        |     |      |
|     | STM103            | STM101B | 0.00  | 0.26 | 0.00 | 0.26 | 10.5 | 101.7 | 85.4  | 375 | 0.38 | 47.3 | 0.110 | 0.094 | 0.98 | 108.1  | 0.8 | 0.79 |
|     |                   |         |       |      |      |      | 11.3 |       |       |     |      |      |       |       |      |        |     |      |
| A1  | C1CB1/2           | STM101B | 0.040 | 0.86 | 0.03 | 0.03 | 10.0 | 104.2 | 7.7   | 200 | 1.00 | 5.9  | 0.031 | 0.050 | 1.04 | 32.3   | 0.1 | 0.24 |
|     |                   |         |       |      |      |      | 10.1 |       |       |     |      |      |       |       |      |        |     |      |
|     | STM101B           | STM101A | 0.00  |      | 0.00 | 2.45 | 13.9 | 87.3  | 631.3 | 900 | 0.15 | 46.5 | 0.636 | 0.225 | 1.10 | 701.1  | 0.7 | 0.90 |
|     | STM101A           | EF 10   | 0.00  | 2.45 | 0.00 | 2.45 | 14.6 | 84.9  | 614.7 | 900 | 0.40 | 2.8  | 0.636 | 0.225 | 1.80 | 1144.9 | 0.0 | 0.54 |
|     | EF 10             | STM100  | 0.00  | 2.45 | 0.00 | 2.45 | 14.6 | 84.8  | 614.2 | 900 | 0.15 | 27.3 | 0.636 | 0.225 | 1.03 | 652.7  | 0.4 | 0.94 |
|     | STM100            | OUTLET  | 0.00  |      | 0.00 | 2.45 | 15.0 | 83.6  | 605.9 | 675 | 1.00 | 2.3  | 0.358 | 0.169 | 2.35 | 840.5  | 0.0 | 0.72 |
|     |                   |         |       |      |      |      | 15.0 |       |       |     |      |      |       |       |      |        |     |      |
|     | Controlled Flow** |         |       |      |      |      |      |       |       |     |      |      |       |       |      |        |     |      |
|     | STM101B           | STM101A | 0.00  |      | 0.00 | 0.46 | 13.9 | 87.3  | 631.3 | 900 | 0.15 | 46.5 | 0.636 | 0.225 | 1.10 | 701.1  | 0.7 | 0.90 |
|     | STM101A           | EF 10   | 0.00  | 0.46 | 0.00 | 0.46 | 14.6 | 84.9  | 216.4 | 675 | 0.40 | 2.8  | 0.358 | 0.169 | 1.49 | 531.6  | 0.0 | 0.41 |
|     | EF 10             | STM100  | 0.00  | 0.46 | 0.00 | 0.46 | 14.6 | 84.8  | 216.4 | 675 | 0.13 | 22.8 | 0.358 | 0.169 | 0.85 | 303.1  | 0.4 | 0.71 |
|     | STM100            | OUTLET  | 0.00  |      | 0.00 | 0.46 | 15.1 | 83.3  | 216.4 | 675 | 1.00 | 2.3  | 0.358 | 0.169 | 2.35 | 840.5  | 0.0 | 0.26 |
|     |                   |         |       |      |      |      | 15.1 |       |       |     |      |      |       |       |      |        |     |      |

\*\* The controlled 100-year release rate is used downstream of the orifice

Note:

- 1) There is a Stormceptor located between STM 101A and STM 100.  
2) Flows from buildings are controlled based on the 5-year storm and included within Qtotal.

**PREVIOUSLY APPROVED (D07-12-17-0186)**

| AREA ID | 5-YEAR                      |                |            |           |         | 100-YEAR   |            |         |
|---------|-----------------------------|----------------|------------|-----------|---------|------------|------------|---------|
|         | TOTAL AREA(m <sup>2</sup> ) | TOTAL AREA(ha) | PERV(0.20) | IMP(0.90) | C-VALUE | PERV(0.25) | IMP(1.125) | C-VALUE |
| A1      | 402.53                      | 0.040          | 135.60     | 266.93    | 0.66    | 135.60     | 266.93     | 1.00    |
| A2      | 364.86                      | 0.036          | 58.03      | 306.82    | 0.79    | 58.03      | 306.82     | 1.00    |
| A3      | 3030.47                     | 0.303          | 165.75     | 2864.72   | 0.86    | 165.75     | 2864.72    | 1.00    |
| A4      | 1211.59                     | 0.121          | 210.77     | 1000.82   | 0.78    | 211.09     | 1000.50    | 1.00    |
| A5      | 722.59                      | 0.072          | 177.75     | 544.83    | 0.73    | 177.75     | 544.83     | 1.00    |
| A6      | 386.91                      | 0.039          | 48.59      | 338.32    | 0.81    | 48.59      | 338.32     | 1.00    |
| A7      | 582.93                      | 0.058          | 72.02      | 510.91    | 0.81    | 72.02      | 510.91     | 1.00    |
| A8      | 1206.34                     | 0.121          | 44.70      | 1161.64   | 0.87    | 44.70      | 1161.64    | 1.00    |
| A9      | 1211.51                     | 0.121          | 64.59      | 1146.92   | 0.86    | 64.59      | 1146.92    | 1.00    |
| A10     | 1159.65                     | 0.116          | 49.12      | 1110.53   | 0.87    | 49.12      | 1110.53    | 1.00    |
| A11     | 705.91                      | 0.071          | 54.88      | 651.03    | 0.85    | 54.88      | 651.03     | 1.00    |
| A12     | 1412.76                     | 0.141          | 48.18      | 1364.58   | 0.88    | 48.18      | 1364.58    | 1.00    |
| A13     | 1250.25                     | 0.125          | 113.18     | 1137.07   | 0.84    | 113.18     | 1137.07    | 1.00    |
| A14     | 1357.19                     | 0.136          | 243.64     | 1113.55   | 0.77    | 243.64     | 1113.55    | 1.00    |
| A15     | 520.38                      | 0.052          | 77.50      | 442.88    | 0.80    | 77.50      | 442.88     | 1.00    |
| A16     | 742.26                      | 0.074          | 159.76     | 582.51    | 0.75    | 159.76     | 582.51     | 1.00    |
| A17     | 702.69                      | 0.070          | 0.00       | 702.69    | 0.90    | 0.00       | 702.69     | 1.00    |
| A18     | 202.61                      | 0.020          | 190.84     | 11.77     | 0.24    | 190.84     | 11.77      | 1.00    |
| A19     | 2512.48                     | 0.251          | 343.54     | 2168.95   | 0.80    | 343.54     | 2168.95    | 1.00    |
| A20     | 1109.91                     | 0.111          | 150.03     | 959.88    | 0.81    | 150.03     | 959.88     | 1.00    |
| A21     | 727.30                      | 0.073          | 27.94      | 699.36    | 0.87    | 27.94      | 699.36     | 1.00    |
| A22     | 545.42                      | 0.055          | 27.94      | 517.48    | 0.86    | 27.94      | 517.48     | 1.00    |
| A23     | 367.58                      | 0.037          | 23.25      | 344.34    | 0.86    | 23.25      | 344.34     | 1.00    |
| A24     | 280.15                      | 0.028          | 23.25      | 256.91    | 0.84    | 23.25      | 256.91     | 1.00    |
| A25     | 1655.33                     | 0.166          | 226.44     | 1428.89   | 0.80    | 226.44     | 1428.89    | 1.00    |
| A26     | 523.77                      | 0.052          | 29.28      | 494.49    | 0.86    | 29.28      | 494.49     | 1.00    |
| A27     | 251.47                      | 0.025          | 70.75      | 180.72    | 0.70    | 70.75      | 180.72     | 1.00    |
| A28     | 907.23                      | 0.091          | 91.75      | 815.48    | 0.83    | 91.75      | 815.48     | 1.00    |
| A29     | 415.98                      | 0.042          | 30.45      | 385.52    | 0.85    | 30.45      | 385.52     | 1.00    |
| A30     | 549.74                      | 0.055          | 120.06     | 429.69    | 0.75    | 120.06     | 429.69     | 1.00    |
| A31     | 459.11                      | 0.046          | 33.81      | 425.29    | 0.85    | 33.81      | 425.29     | 1.00    |
| A32     | 620.12                      | 0.062          | 311.01     | 309.11    | 0.55    | 311.01     | 309.11     | 1.00    |

|         |         |       |      |         |      |      |         |      |
|---------|---------|-------|------|---------|------|------|---------|------|
| BLDG A  | 1895.82 | 0.190 | 0.00 | 1895.82 | 0.90 | 0.00 | 1895.82 | 1.00 |
| BLDG B  | 1404.15 | 0.140 | 0.00 | 1404.15 | 0.90 | 0.00 | 1404.15 | 1.00 |
| BLDG BB | 409.82  | 0.041 | 0.00 | 409.82  | 0.90 | 0.00 | 409.82  | 1.00 |
| BLDG C  | 2884.52 | 0.288 | 0.00 | 2884.52 | 0.90 | 0.00 | 2884.52 | 1.00 |
| BLDG D  | 1014.34 | 0.101 | 0.00 | 1014.34 | 0.90 | 0.00 | 1014.34 | 1.00 |
| BLDG G  | 970.30  | 0.097 | 0.00 | 970.30  | 0.90 | 0.00 | 970.30  | 1.00 |

|    |         |       |         |        |      |         |        |      |
|----|---------|-------|---------|--------|------|---------|--------|------|
| U1 | 6790.56 | 0.679 | 6427.82 | 362.74 | 0.24 | 6419.46 | 371.10 | 1.00 |
| U2 | 786.12  | 0.079 | 353.58  | 432.54 | 0.59 | 353.58  | 432.54 | 1.00 |
| U3 | 154.46  | 0.015 | 0.00    | 154.46 | 0.90 | 0.00    | 154.46 | 1.00 |

|             |          |       |         |          |      |         |          |      |
|-------------|----------|-------|---------|----------|------|---------|----------|------|
| AREA A      | 28099.02 | 2.810 | 3424.38 | 24674.65 | 0.81 | 3424.70 | 24674.33 | 1.00 |
| AREA A+BLDG | 36677.97 | 3.668 | 3424.38 | 33253.59 | 0.83 | 3424.70 | 33253.27 | 1.00 |

|       |          |       |          |          |      |          |          |      |
|-------|----------|-------|----------|----------|------|----------|----------|------|
| TOTAL | 44380.56 | 4.438 | 10205.78 | 34203.33 | 0.74 | 10197.74 | 34182.82 | 1.00 |
|-------|----------|-------|----------|----------|------|----------|----------|------|

**PONDING AREAS**

| Elevation | Area(m <sup>2</sup> ) |
|-----------|-----------------------|
| 103.30    | 150.33                |
| 103.35    | 795.76                |
| 103.40    | 2067.20               |
| 103.55    | 8923.66               |



---

***Site Servicing and Stormwater Management Brief  
For Iber Hazeldean Land Limited***

***5754 Hazeldean Road / 24 Iber Road / 5734 Hazeldean Road  
September 2019 – REV 1***

***Proposed Amended Appendix D – Stormwater Management***

---





Stormwater - Proposed Development  
City of Ottawa Sewer Design Guidelines, 2012



Target Flow Rate

| Site Area |                                                    | 5-year                  |              | 100-year                     |                              |
|-----------|----------------------------------------------------|-------------------------|--------------|------------------------------|------------------------------|
|           |                                                    | t <sub>c</sub><br>(min) | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>actual</sub><br>(L/s) |
| C         | 4.44 ha<br>0.74 Rational Method runoff coefficient | 21.4                    | 67.4         | 271.6                        | 115.0                        |

Estimated Post Development Peak Flow from Unattenuated Areas

Area ID U1  
Total Area 0.679 ha  
C 0.24 Rational Method runoff coefficient

| 5-year                  |              |                              |                               |                              |                                          | 100-year     |                              |                               |                              |                                          |
|-------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|
| t <sub>c</sub><br>(min) | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) |
| 15.1                    | 83.2         | 37.3                         | 37.3                          | 0.0                          | 0.0                                      | 142.4        | 79.7                         | 79.7                          | 0.0                          | 0.0                                      |

Area ID U2  
Total Area 0.079 ha  
C 0.59 Rational Method runoff coefficient

| 5-year                  |              |                              |                               |                              |                                          | 100-year     |                              |                               |                              |                                          |
|-------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|
| t <sub>c</sub><br>(min) | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) |
| 15.1                    | 83.2         | 10.6                         | 10.6                          | 0.0                          | 0.0                                      | 142.4        | 22.7                         | 22.7                          | 0.0                          | 0.0                                      |

Area ID U3  
Total Area 0.015 ha  
C 0.90 Rational Method runoff coefficient

| 5-year                  |              |                              |                               |                              |                                          | 100-year     |                              |                               |                              |                                          |
|-------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|
| t <sub>c</sub><br>(min) | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) |
| 15.1                    | 83.2         | 3.2                          | 3.2                           | 0.0                          | 0.0                                      | 142.4        | 6.1                          | 6.1                           | 0.0                          | 0.0                                      |

**Estimated Post Development Storage Requirement**

|                           |                                                                                                                                 |
|---------------------------|---------------------------------------------------------------------------------------------------------------------------------|
| <b>Building ID</b>        | <b>BLDG A</b>                                                                                                                   |
| <b>Roof Area</b>          | 0.190 ha                                                                                                                        |
| <b>Avail Storage Area</b> | 0.180                                                                                                                           |
| <b>C</b>                  | 0.90 Rational Method runoff coefficient <i>Note: Rational Method Coefficient "C" increased by 25% for 100-year calculations</i> |
| <b>t<sub>c</sub></b>      | 10 min, t <sub>c</sub> at outlet without restriction                                                                            |

**Estimated Number of Roof Drains**

|                              |                                                                         |
|------------------------------|-------------------------------------------------------------------------|
| <b>Building Length</b>       | 86.6                                                                    |
| <b>Building Width</b>        | 22.3                                                                    |
| <b>Number of Drains</b>      | 9                                                                       |
| <b>m<sup>2</sup> / Drain</b> | 200.1 max 232.25m <sup>2</sup> /notch as recommended by Zurn for Ottawa |

| <b>Roof Top Rating Curve per Zurn Model Z-105-5</b> |                        |                        |                          |                          |                         |                             |
|-----------------------------------------------------|------------------------|------------------------|--------------------------|--------------------------|-------------------------|-----------------------------|
| <b>d</b>                                            | <b>A</b>               | <b>V<sub>acc</sub></b> | <b>V<sub>avail</sub></b> | <b>Q<sub>notch</sub></b> | <b>Q<sub>roof</sub></b> | <b>V<sub>drawdown</sub></b> |
| <b>(m)</b>                                          | <b>(m<sup>2</sup>)</b> | <b>(m<sup>3</sup>)</b> | <b>(m<sup>3</sup>)</b>   | <b>(L/s)</b>             | <b>(L/s)</b>            | <b>(hr)</b>                 |
| 0.000                                               | 0                      | 0.0                    | 0.0                      | 0.00                     | 0.00                    | 0.00                        |
| 0.025                                               | 112.6                  | 0.9                    | 0.9                      | 0.38                     | 3.42                    | 0.08                        |
| 0.050                                               | 450.3                  | 6.6                    | 7.5                      | 0.77                     | 6.93                    | 0.34                        |
| 0.075                                               | 1013.1                 | 17.8                   | 25.3                     | 1.14                     | 10.26                   | 0.82                        |
| 0.100                                               | 1801.0                 | 34.7                   | 60.0                     | 1.52                     | 13.68                   | 1.53                        |
| 0.125                                               | 1801.0                 | 45.0                   | 105.1                    | 1.90                     | 17.10                   | 2.26                        |
| 0.150                                               | 1801.0                 | 45.0                   | 150.1                    | 2.28                     | 20.52                   | 2.87                        |

\* Assumes one notch opening per drain, assumes maximum slope of 10cm

| <b>t<sub>c</sub></b><br><b>(min)</b> | <b>5-year</b>              |                                           |                                            |                                           |                                                     | <b>100-year</b>            |                                           |                                            |                                           |                                                     |
|--------------------------------------|----------------------------|-------------------------------------------|--------------------------------------------|-------------------------------------------|-----------------------------------------------------|----------------------------|-------------------------------------------|--------------------------------------------|-------------------------------------------|-----------------------------------------------------|
|                                      | <b>i</b><br><b>(mm/hr)</b> | <b>Q<sub>actual</sub></b><br><b>(L/s)</b> | <b>Q<sub>release</sub></b><br><b>(L/s)</b> | <b>Q<sub>stored</sub></b><br><b>(L/s)</b> | <b>V<sub>stored</sub></b><br><b>(m<sup>3</sup>)</b> | <b>i</b><br><b>(mm/hr)</b> | <b>Q<sub>actual</sub></b><br><b>(L/s)</b> | <b>Q<sub>release</sub></b><br><b>(L/s)</b> | <b>Q<sub>stored</sub></b><br><b>(L/s)</b> | <b>V<sub>stored</sub></b><br><b>(m<sup>3</sup>)</b> |
| 10                                   | 104.2                      | 49.4                                      | 10.5                                       | 38.9                                      | 23.3                                                | 178.6                      | 94.0                                      | 13.8                                       | 80.2                                      | 48.1                                                |
| 15                                   | 83.6                       | 39.6                                      | 10.5                                       | 29.1                                      | 26.2                                                | 142.9                      | 75.3                                      | 13.8                                       | 61.4                                      | 55.3                                                |
| 20                                   | 70.3                       | 33.3                                      | 10.5                                       | 22.8                                      | 27.4                                                | 120.0                      | 63.2                                      | 13.8                                       | 49.3                                      | 59.2                                                |
| 25                                   | 60.9                       | 28.9                                      | 10.5                                       | 18.4                                      | 27.6                                                | 103.8                      | 54.7                                      | 13.8                                       | 40.8                                      | 61.3                                                |
| 30                                   | 53.9                       | 25.6                                      | 10.5                                       | 15.1                                      | 27.1                                                | 91.9                       | 48.4                                      | 13.8                                       | 34.5                                      | 62.2                                                |
| 35                                   | 48.5                       | 23.0                                      | 10.5                                       | 12.5                                      | 26.3                                                | 82.6                       | 43.5                                      | 13.8                                       | 29.6                                      | 62.2                                                |
| 40                                   | 44.2                       | 20.9                                      | 10.5                                       | 10.5                                      | 25.1                                                | 75.1                       | 39.6                                      | 13.8                                       | 25.7                                      | 61.7                                                |
| 45                                   | 40.6                       | 19.3                                      | 10.5                                       | 8.8                                       | 23.7                                                | 69.1                       | 36.4                                      | 13.8                                       | 22.5                                      | 60.8                                                |
| 50                                   | 37.7                       | 17.8                                      | 10.5                                       | 7.4                                       | 22.1                                                | 64.0                       | 33.7                                      | 13.8                                       | 19.8                                      | 59.5                                                |
| 55                                   | 35.1                       | 16.6                                      | 10.5                                       | 6.2                                       | 20.3                                                | 59.6                       | 31.4                                      | 13.8                                       | 17.6                                      | 57.9                                                |
| 60                                   | 32.9                       | 15.6                                      | 10.5                                       | 5.1                                       | 18.5                                                | 55.9                       | 29.4                                      | 13.8                                       | 15.6                                      | 56.1                                                |
| 65                                   | 31.0                       | 14.7                                      | 10.5                                       | 4.2                                       | 16.5                                                | 52.6                       | 27.7                                      | 13.8                                       | 13.9                                      | 54.1                                                |
| 70                                   | 29.4                       | 13.9                                      | 10.5                                       | 3.4                                       | 14.4                                                | 49.8                       | 26.2                                      | 13.8                                       | 12.4                                      | 52.0                                                |
| 75                                   | 27.9                       | 13.2                                      | 10.5                                       | 2.7                                       | 12.3                                                | 47.3                       | 24.9                                      | 13.8                                       | 11.0                                      | 49.7                                                |
| 80                                   | 26.6                       | 12.6                                      | 10.5                                       | 2.1                                       | 10.1                                                | 45.0                       | 23.7                                      | 13.8                                       | 9.8                                       | 47.3                                                |
| 85                                   | 25.4                       | 12.0                                      | 10.5                                       | 1.5                                       | 7.9                                                 | 43.0                       | 22.6                                      | 13.8                                       | 8.8                                       | 44.7                                                |
| 90                                   | 24.3                       | 11.5                                      | 10.5                                       | 1.0                                       | 5.6                                                 | 41.1                       | 21.6                                      | 13.8                                       | 7.8                                       | 42.1                                                |
| 95                                   | 23.3                       | 11.0                                      | 10.5                                       | 0.6                                       | 3.2                                                 | 39.4                       | 20.8                                      | 13.8                                       | 6.9                                       | 39.4                                                |
| 100                                  | 22.4                       | 10.6                                      | 10.5                                       | 0.1                                       | 0.8                                                 | 37.9                       | 20.0                                      | 13.8                                       | 6.1                                       | 36.7                                                |
| 105                                  | 21.6                       | 10.2                                      | 10.2                                       | 0.0                                       | 0.0                                                 | 36.5                       | 19.2                                      | 13.8                                       | 5.4                                       | 33.8                                                |
| 110                                  | 20.8                       | 9.9                                       | 9.9                                        | 0.0                                       | 0.0                                                 | 35.2                       | 18.5                                      | 13.8                                       | 4.7                                       | 31.0                                                |

|                                       |                           |                                         |                           |
|---------------------------------------|---------------------------|-----------------------------------------|---------------------------|
| <b>5-year Q<sub>roof</sub></b>        | <b>10.48 L/s</b>          | <b>100-year Q<sub>roof</sub></b>        | <b>13.85 L/s</b>          |
| <b>5-year Max. Storage Required</b>   | <b>27.6 m<sup>3</sup></b> | <b>100-year Max. Storage Required</b>   | <b>62.2 m<sup>3</sup></b> |
| <b>5-year Storage Depth</b>           | <b>0.077 m</b>            | <b>100-year Storage Depth</b>           | <b>0.101 m</b>            |
| <b>5-year Estimated Drawdown Time</b> | <b>0.87 hr</b>            | <b>100-year Estimated Drawdown Time</b> | <b>1.56 hr</b>            |

**Iber Hazeldean Land Limited**  
**5734-5754 Hazeldean Road/24 Iber Road**  
**Proposed Site Conditions**

**Building ID** BLDG B  
**Roof Area** 0.140 ha  
**Avail Storage Area** 0.133  
**C** 0.90 Rational Method runoff coefficient *Note: Rational Method Coefficient "C" increased by 25% for 100-year calculations*  
**t<sub>c</sub>** 10 min, t<sub>c</sub> at outlet without restriction

**Estimated Number of Roof Drains**

**Building Length** 58.0  
**Building Width** 24.0  
**Number of Drains** 6  
**m<sup>2</sup> / Drain** 222.3 max 232.25m<sup>2</sup>/notch as recommended by Zurn for Ottawa

| Roof Top Rating Curve per Zurn Model Z-105-5 |                   |                   |                    |                    |                   |                       |
|----------------------------------------------|-------------------|-------------------|--------------------|--------------------|-------------------|-----------------------|
| d                                            | A                 | V <sub>acc</sub>  | V <sub>avail</sub> | Q <sub>notch</sub> | Q <sub>roof</sub> | V <sub>drawdown</sub> |
| (m)                                          | (m <sup>2</sup> ) | (m <sup>3</sup> ) | (m <sup>3</sup> )  | (L/s)              | (L/s)             | (hr)                  |
| 0.000                                        | 0                 | 0.0               | 0.0                | 0.00               | 0.00              | 0.00                  |
| 0.025                                        | 83.4              | 0.7               | 0.7                | 0.38               | 2.28              | 0.08                  |
| 0.050                                        | 333.5             | 4.9               | 5.6                | 0.77               | 4.62              | 0.38                  |
| 0.075                                        | 750.3             | 13.2              | 18.8               | 1.14               | 6.84              | 0.91                  |
| 0.100                                        | 1333.9            | 25.7              | 44.5               | 1.52               | 9.12              | 1.70                  |
| 0.125                                        | 1333.9            | 33.3              | 77.8               | 1.90               | 11.40             | 2.51                  |
| 0.150                                        | 1333.9            | 33.3              | 111.2              | 2.28               | 13.68             | 3.19                  |

\* Assumes one notch opening per drain, assumes maximum slope of 10cm

| t <sub>c</sub><br>(min) | 5-year       |                              |                               |                              |                                          | 100-year     |                              |                               |                              |                                          |
|-------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|
|                         | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) |
| 10                      | 104.2        | 36.6                         | 7.1                           | 29.5                         | 17.7                                     | 178.6        | 69.6                         | 9.4                           | 60.3                         | 36.2                                     |
| 15                      | 83.6         | 29.3                         | 7.1                           | 22.3                         | 20.0                                     | 142.9        | 55.7                         | 9.4                           | 46.4                         | 41.7                                     |
| 20                      | 70.3         | 24.7                         | 7.1                           | 17.6                         | 21.1                                     | 120.0        | 46.8                         | 9.4                           | 37.4                         | 44.9                                     |
| 25                      | 60.9         | 21.4                         | 7.1                           | 14.3                         | 21.4                                     | 103.8        | 40.5                         | 9.4                           | 31.1                         | 46.7                                     |
| 30                      | 53.9         | 18.9                         | 7.1                           | 11.9                         | 21.3                                     | 91.9         | 35.8                         | 9.4                           | 26.5                         | 47.6                                     |
| 35                      | 48.5         | 17.0                         | 7.1                           | 10.0                         | 20.9                                     | 82.6         | 32.2                         | 9.4                           | 22.8                         | 48.0                                     |
| 40                      | 44.2         | 15.5                         | 7.1                           | 8.4                          | 20.2                                     | 75.1         | 29.3                         | 9.4                           | 19.9                         | 47.9                                     |
| 45                      | 40.6         | 14.3                         | 7.1                           | 7.2                          | 19.4                                     | 69.1         | 26.9                         | 9.4                           | 17.6                         | 47.4                                     |
| 50                      | 37.7         | 13.2                         | 7.1                           | 6.1                          | 18.4                                     | 64.0         | 24.9                         | 9.4                           | 15.6                         | 46.8                                     |
| 55                      | 35.1         | 12.3                         | 7.1                           | 5.3                          | 17.3                                     | 59.6         | 23.3                         | 9.4                           | 13.9                         | 45.9                                     |
| 60                      | 32.9         | 11.6                         | 7.1                           | 4.5                          | 16.1                                     | 55.9         | 21.8                         | 9.4                           | 12.4                         | 44.8                                     |
| 65                      | 31.0         | 10.9                         | 7.1                           | 3.8                          | 14.9                                     | 52.6         | 20.5                         | 9.4                           | 11.2                         | 43.6                                     |
| 70                      | 29.4         | 10.3                         | 7.1                           | 3.2                          | 13.6                                     | 49.8         | 19.4                         | 9.4                           | 10.1                         | 42.2                                     |
| 75                      | 27.9         | 9.8                          | 7.1                           | 2.7                          | 12.2                                     | 47.3         | 18.4                         | 9.4                           | 9.1                          | 40.8                                     |
| 80                      | 26.6         | 9.3                          | 7.1                           | 2.2                          | 10.8                                     | 45.0         | 17.5                         | 9.4                           | 8.2                          | 39.3                                     |
| 85                      | 25.4         | 8.9                          | 7.1                           | 1.8                          | 9.3                                      | 43.0         | 16.8                         | 9.4                           | 7.4                          | 37.7                                     |
| 90                      | 24.3         | 8.5                          | 7.1                           | 1.4                          | 7.8                                      | 41.1         | 16.0                         | 9.4                           | 6.7                          | 36.0                                     |
| 95                      | 23.3         | 8.2                          | 7.1                           | 1.1                          | 6.3                                      | 39.4         | 15.4                         | 9.4                           | 6.0                          | 34.3                                     |
| 100                     | 22.4         | 7.9                          | 7.1                           | 0.8                          | 4.7                                      | 37.9         | 14.8                         | 9.4                           | 5.4                          | 32.5                                     |
| 105                     | 21.6         | 7.6                          | 7.1                           | 0.5                          | 3.1                                      | 36.5         | 14.2                         | 9.4                           | 4.9                          | 30.7                                     |
| 110                     | 20.8         | 7.3                          | 7.1                           | 0.2                          | 1.5                                      | 35.2         | 13.7                         | 9.4                           | 4.4                          | 28.8                                     |

|                                       |                           |                                         |                           |
|---------------------------------------|---------------------------|-----------------------------------------|---------------------------|
| <b>5-year Q<sub>roof</sub></b>        | <b>7.08 L/s</b>           | <b>100-year Q<sub>roof</sub></b>        | <b>9.36 L/s</b>           |
| <b>5-year Max. Storage Required</b>   | <b>21.4 m<sup>3</sup></b> | <b>100-year Max. Storage Required</b>   | <b>48.0 m<sup>3</sup></b> |
| <b>5-year Storage Depth</b>           | <b>0.078 m</b>            | <b>100-year Storage Depth</b>           | <b>0.103 m</b>            |
| <b>5-year Estimated Drawdown Time</b> | <b>1.00 hr</b>            | <b>100-year Estimated Drawdown Time</b> | <b>1.78 hr</b>            |

**Iber Hazeldean Land Limited**  
**5734-5754 Hazeldean Road/24 Iber Road**  
**Proposed Site Conditions**

**Building ID** BLDG BB  
**Roof Area** 0.041 ha  
**Avail Storage Area** 0.039  
**C** 0.90 Rational Method runoff coefficient *Note: Rational Method Coefficient "C" increased by 25% for 100-year calculations*  
**t<sub>c</sub>** 10 min, t<sub>c</sub> at outlet without restriction

**Estimated Number of Roof Drains**

**Building Length** 15.5  
**Building Width** 24.0  
**Number of Drains** 2  
**m<sup>2</sup> / Drain** 194.7 max 232.25m<sup>2</sup>/notch as recommended by Zurn for Ottawa

| Roof Top Rating Curve per Zurn Model Z-105-5 |                   |                   |                    |                    |                   |                       |
|----------------------------------------------|-------------------|-------------------|--------------------|--------------------|-------------------|-----------------------|
| d                                            | A                 | V <sub>acc</sub>  | V <sub>avail</sub> | Q <sub>notch</sub> | Q <sub>roof</sub> | V <sub>drawdown</sub> |
| (m)                                          | (m <sup>2</sup> ) | (m <sup>3</sup> ) | (m <sup>3</sup> )  | (L/s)              | (L/s)             | (hr)                  |
| 0.000                                        | 0                 | 0.0               | 0.0                | 0.00               | 0.00              | 0.00                  |
| 0.025                                        | 24.3              | 0.2               | 0.2                | 0.38               | 0.76              | 0.07                  |
| 0.050                                        | 97.3              | 1.4               | 1.6                | 0.77               | 1.54              | 0.33                  |
| 0.075                                        | 219.0             | 3.9               | 5.5                | 1.14               | 2.28              | 0.80                  |
| 0.100                                        | 389.3             | 7.5               | 13.0               | 1.52               | 3.04              | 1.49                  |
| 0.125                                        | 389.3             | 9.7               | 22.7               | 1.90               | 3.80              | 2.20                  |
| 0.150                                        | 389.3             | 9.7               | 32.4               | 2.28               | 4.56              | 2.79                  |

\* Assumes one notch opening per drain, assumes maximum slope of 10cm

| t <sub>c</sub><br>(min) | 5-year       |                              |                               |                              |                                          | 100-year     |                              |                               |                              |                                          |
|-------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|
|                         | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) |
| 10                      | 104.2        | 10.7                         | 2.3                           | 8.4                          | 5.0                                      | 178.6        | 20.3                         | 3.1                           | 17.3                         | 10.4                                     |
| 15                      | 83.6         | 8.6                          | 2.3                           | 6.2                          | 5.6                                      | 142.9        | 16.3                         | 3.1                           | 13.2                         | 11.9                                     |
| 20                      | 70.3         | 7.2                          | 2.3                           | 4.9                          | 5.9                                      | 120.0        | 13.7                         | 3.1                           | 10.6                         | 12.7                                     |
| 25                      | 60.9         | 6.2                          | 2.3                           | 3.9                          | 5.9                                      | 103.8        | 11.8                         | 3.1                           | 8.8                          | 13.1                                     |
| 30                      | 53.9         | 5.5                          | 2.3                           | 3.2                          | 5.8                                      | 91.9         | 10.5                         | 3.1                           | 7.4                          | 13.3                                     |
| 35                      | 48.5         | 5.0                          | 2.3                           | 2.7                          | 5.6                                      | 82.6         | 9.4                          | 3.1                           | 6.3                          | 13.3                                     |
| 40                      | 44.2         | 4.5                          | 2.3                           | 2.2                          | 5.3                                      | 75.1         | 8.6                          | 3.1                           | 5.5                          | 13.2                                     |
| 45                      | 40.6         | 4.2                          | 2.3                           | 1.8                          | 5.0                                      | 69.1         | 7.9                          | 3.1                           | 4.8                          | 12.9                                     |
| 50                      | 37.7         | 3.9                          | 2.3                           | 1.5                          | 4.6                                      | 64.0         | 7.3                          | 3.1                           | 4.2                          | 12.6                                     |
| 55                      | 35.1         | 3.6                          | 2.3                           | 1.3                          | 4.2                                      | 59.6         | 6.8                          | 3.1                           | 3.7                          | 12.3                                     |
| 60                      | 32.9         | 3.4                          | 2.3                           | 1.1                          | 3.8                                      | 55.9         | 6.4                          | 3.1                           | 3.3                          | 11.9                                     |
| 65                      | 31.0         | 3.2                          | 2.3                           | 0.9                          | 3.4                                      | 52.6         | 6.0                          | 3.1                           | 2.9                          | 11.4                                     |
| 70                      | 29.4         | 3.0                          | 2.3                           | 0.7                          | 2.9                                      | 49.8         | 5.7                          | 3.1                           | 2.6                          | 10.9                                     |
| 75                      | 27.9         | 2.9                          | 2.3                           | 0.5                          | 2.4                                      | 47.3         | 5.4                          | 3.1                           | 2.3                          | 10.4                                     |
| 80                      | 26.6         | 2.7                          | 2.3                           | 0.4                          | 1.9                                      | 45.0         | 5.1                          | 3.1                           | 2.1                          | 9.9                                      |
| 85                      | 25.4         | 2.6                          | 2.3                           | 0.3                          | 1.4                                      | 43.0         | 4.9                          | 3.1                           | 1.8                          | 9.3                                      |
| 90                      | 24.3         | 2.5                          | 2.3                           | 0.2                          | 0.9                                      | 41.1         | 4.7                          | 3.1                           | 1.6                          | 8.7                                      |
| 95                      | 23.3         | 2.4                          | 2.3                           | 0.1                          | 0.4                                      | 39.4         | 4.5                          | 3.1                           | 1.4                          | 8.1                                      |
| 100                     | 22.4         | 2.3                          | 2.3                           | 0.0                          | 0.0                                      | 37.9         | 4.3                          | 3.1                           | 1.2                          | 7.5                                      |
| 105                     | 21.6         | 2.2                          | 2.2                           | 0.0                          | 0.0                                      | 36.5         | 4.2                          | 3.1                           | 1.1                          | 6.9                                      |
| 110                     | 20.8         | 2.1                          | 2.1                           | 0.0                          | 0.0                                      | 35.2         | 4.0                          | 3.1                           | 0.9                          | 6.2                                      |

|                                       |                          |                                         |                           |
|---------------------------------------|--------------------------|-----------------------------------------|---------------------------|
| <b>5-year Q<sub>roof</sub></b>        | <b>2.32 L/s</b>          | <b>100-year Q<sub>roof</sub></b>        | <b>3.07 L/s</b>           |
| <b>5-year Max. Storage Required</b>   | <b>5.9 m<sup>3</sup></b> | <b>100-year Max. Storage Required</b>   | <b>13.3 m<sup>3</sup></b> |
| <b>5-year Storage Depth</b>           | <b>0.076 m</b>           | <b>100-year Storage Depth</b>           | <b>0.101 m</b>            |
| <b>5-year Estimated Drawdown Time</b> | <b>0.84 hr</b>           | <b>100-year Estimated Drawdown Time</b> | <b>1.51 hr</b>            |

**Iber Hazeldean Land Limited**  
**5734-5754 Hazeldean Road/24 Iber Road**  
**Proposed Site Conditions**

**Building ID** BLDG C  
**Roof Area** 0.288 ha  
**Avail Storage Area** 0.274  
**C** 0.90 Rational Method runoff coefficient *Note: Rational Method Coefficient "C" increased by 25% for 100-year calculations*  
**t<sub>c</sub>** 10 min, t<sub>c</sub> at outlet without restriction

**Estimated Number of Roof Drains**

**Building Length** 64.2  
**Building Width** 43.8  
**Number of Drains** 12  
**m<sup>2</sup> / Drain** 228.4 max 232.25m<sup>2</sup>/notch as recommended by Zurn for Ottawa

| Roof Top Rating Curve per Zurn Model Z-105-5 |                   |                   |                    |                    |                   |                       |
|----------------------------------------------|-------------------|-------------------|--------------------|--------------------|-------------------|-----------------------|
| d                                            | A                 | V <sub>acc</sub>  | V <sub>avail</sub> | Q <sub>notch</sub> | Q <sub>roof</sub> | V <sub>drawdown</sub> |
| (m)                                          | (m <sup>2</sup> ) | (m <sup>3</sup> ) | (m <sup>3</sup> )  | (L/s)              | (L/s)             | (hr)                  |
| 0.000                                        | 0                 | 0.0               | 0.0                | 0.00               | 0.00              | 0.00                  |
| 0.025                                        | 171.3             | 1.4               | 1.4                | 0.38               | 4.56              | 0.09                  |
| 0.050                                        | 685.1             | 10.0              | 11.4               | 0.77               | 9.24              | 0.39                  |
| 0.075                                        | 1541.4            | 27.1              | 38.5               | 1.14               | 13.68             | 0.94                  |
| 0.100                                        | 2740.3            | 52.8              | 91.3               | 1.52               | 18.24             | 1.74                  |
| 0.125                                        | 2740.3            | 68.5              | 159.9              | 1.90               | 22.80             | 2.58                  |
| 0.150                                        | 2740.3            | 68.5              | 228.4              | 2.28               | 27.36             | 3.27                  |

\* Assumes one notch opening per drain, assumes maximum slope of 10cm

| t <sub>c</sub><br>(min) | 5-year       |                              |                               |                              |                                          | 100-year     |                              |                               |                              |                                          |
|-------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|
|                         | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) |
| 10                      | 104.2        | 75.1                         | 14.2                          | 60.9                         | 36.6                                     | 178.6        | 143.1                        | 18.8                          | 124.3                        | 74.6                                     |
| 15                      | 83.6         | 60.3                         | 14.2                          | 46.1                         | 41.4                                     | 142.9        | 114.5                        | 18.8                          | 95.7                         | 86.1                                     |
| 20                      | 70.3         | 50.7                         | 14.2                          | 36.5                         | 43.8                                     | 120.0        | 96.1                         | 18.8                          | 77.3                         | 92.8                                     |
| 25                      | 60.9         | 43.9                         | 14.2                          | 29.7                         | 44.6                                     | 103.8        | 83.2                         | 18.8                          | 64.4                         | 96.6                                     |
| 30                      | 53.9         | 38.9                         | 14.2                          | 24.7                         | 44.4                                     | 91.9         | 73.6                         | 18.8                          | 54.8                         | 98.7                                     |
| 35                      | 48.5         | 35.0                         | 14.2                          | 20.8                         | 43.7                                     | 82.6         | 66.2                         | 18.8                          | 47.4                         | 99.5                                     |
| 40                      | 44.2         | 31.9                         | 14.2                          | 17.7                         | 42.4                                     | 75.1         | 60.2                         | 18.8                          | 41.4                         | 99.4                                     |
| 45                      | 40.6         | 29.3                         | 14.2                          | 15.1                         | 40.8                                     | 69.1         | 55.3                         | 18.8                          | 36.5                         | 98.7                                     |
| 50                      | 37.7         | 27.2                         | 14.2                          | 13.0                         | 38.9                                     | 64.0         | 51.2                         | 18.8                          | 32.5                         | 97.4                                     |
| 55                      | 35.1         | 25.3                         | 14.2                          | 11.1                         | 36.7                                     | 59.6         | 47.8                         | 18.8                          | 29.0                         | 95.7                                     |
| 60                      | 32.9         | 23.8                         | 14.2                          | 9.6                          | 34.4                                     | 55.9         | 44.8                         | 18.8                          | 26.0                         | 93.6                                     |
| 65                      | 31.0         | 22.4                         | 14.2                          | 8.2                          | 31.9                                     | 52.6         | 42.2                         | 18.8                          | 23.4                         | 91.3                                     |
| 70                      | 29.4         | 21.2                         | 14.2                          | 7.0                          | 29.3                                     | 49.8         | 39.9                         | 18.8                          | 21.1                         | 88.7                                     |
| 75                      | 27.9         | 20.1                         | 14.2                          | 5.9                          | 26.6                                     | 47.3         | 37.9                         | 18.8                          | 19.1                         | 85.9                                     |
| 80                      | 26.6         | 19.2                         | 14.2                          | 5.0                          | 23.8                                     | 45.0         | 36.0                         | 18.8                          | 17.3                         | 82.9                                     |
| 85                      | 25.4         | 18.3                         | 14.2                          | 4.1                          | 20.9                                     | 43.0         | 34.4                         | 18.8                          | 15.6                         | 79.7                                     |
| 90                      | 24.3         | 17.5                         | 14.2                          | 3.3                          | 17.9                                     | 41.1         | 32.9                         | 18.8                          | 14.2                         | 76.4                                     |
| 95                      | 23.3         | 16.8                         | 14.2                          | 2.6                          | 14.8                                     | 39.4         | 31.6                         | 18.8                          | 12.8                         | 73.0                                     |
| 100                     | 22.4         | 16.2                         | 14.2                          | 2.0                          | 11.7                                     | 37.9         | 30.4                         | 18.8                          | 11.6                         | 69.5                                     |
| 105                     | 21.6         | 15.6                         | 14.2                          | 1.4                          | 8.6                                      | 36.5         | 29.2                         | 18.8                          | 10.5                         | 65.9                                     |
| 110                     | 20.8         | 15.0                         | 14.2                          | 0.8                          | 5.4                                      | 35.2         | 28.2                         | 18.8                          | 9.4                          | 62.2                                     |

|                                       |                           |                                         |                           |
|---------------------------------------|---------------------------|-----------------------------------------|---------------------------|
| <b>5-year Q<sub>roof</sub></b>        | <b>14.20 L/s</b>          | <b>100-year Q<sub>roof</sub></b>        | <b>18.78 L/s</b>          |
| <b>5-year Max. Storage Required</b>   | <b>44.6 m<sup>3</sup></b> | <b>100-year Max. Storage Required</b>   | <b>99.5 m<sup>3</sup></b> |
| <b>5-year Storage Depth</b>           | <b>0.078 m</b>            | <b>100-year Storage Depth</b>           | <b>0.103 m</b>            |
| <b>5-year Estimated Drawdown Time</b> | <b>1.03 hr</b>            | <b>100-year Estimated Drawdown Time</b> | <b>1.84 hr</b>            |

**Iber Hazeldean Land Limited**  
**5734-5754 Hazeldean Road/24 Iber Road**  
**Proposed Site Conditions**

**Building ID: UT. BLDG G**

|                           |                                                      |                                                                                         |
|---------------------------|------------------------------------------------------|-----------------------------------------------------------------------------------------|
| <b>Roof Area</b>          | 0.097 ha                                             |                                                                                         |
| <b>Avail Storage Area</b> | 0.092                                                |                                                                                         |
| <b>C</b>                  | 0.90 Rational Method runoff coefficient              | <i>Note: Rational Method Coefficient "C" increased by 25% for 100-year calculations</i> |
| <b>t<sub>c</sub></b>      | 10 min, t <sub>c</sub> at outlet without restriction |                                                                                         |

**Estimated Number of Roof Drains**

|                              |                                                                         |
|------------------------------|-------------------------------------------------------------------------|
| <b>Building Length</b>       | 20.2                                                                    |
| <b>Building Width</b>        | 53.1                                                                    |
| <b>Number of Drains</b>      | 5                                                                       |
| <b>m<sup>2</sup> / Drain</b> | 184.4 max 232.25m <sup>2</sup> /notch as recommended by Zurn for Ottawa |

| <b>Roof Top Rating Curve per Zurn Model Z-105-5</b> |                        |                        |                          |                          |                         |                             |
|-----------------------------------------------------|------------------------|------------------------|--------------------------|--------------------------|-------------------------|-----------------------------|
| <b>d</b>                                            | <b>A</b>               | <b>V<sub>acc</sub></b> | <b>V<sub>avail</sub></b> | <b>Q<sub>notch</sub></b> | <b>Q<sub>roof</sub></b> | <b>V<sub>drawdown</sub></b> |
| <b>(m)</b>                                          | <b>(m<sup>2</sup>)</b> | <b>(m<sup>3</sup>)</b> | <b>(m<sup>3</sup>)</b>   | <b>(L/s)</b>             | <b>(L/s)</b>            | <b>(hr)</b>                 |
| 0.000                                               | 0                      | 0.0                    | 0.0                      | 0.00                     | 0.00                    | 0.00                        |
| 0.025                                               | 57.6                   | 0.5                    | 0.5                      | 0.38                     | 1.90                    | 0.07                        |
| 0.050                                               | 230.4                  | 3.4                    | 3.8                      | 0.77                     | 3.85                    | 0.31                        |
| 0.075                                               | 518.5                  | 9.1                    | 13.0                     | 1.14                     | 5.70                    | 0.76                        |
| 0.100                                               | 921.8                  | 17.8                   | 30.7                     | 1.52                     | 7.60                    | 1.41                        |
| 0.125                                               | 921.8                  | 23.0                   | 53.8                     | 1.90                     | 9.50                    | 2.08                        |
| 0.150                                               | 921.8                  | 23.0                   | 76.8                     | 2.28                     | 11.40                   | 2.64                        |

\* Assumes one notch opening per drain, assumes maximum slope of 10cm

| <b>t<sub>c</sub></b><br><b>(min)</b> | <b>5-year</b>              |                                           |                                            |                                           |                                                     |  | <b>100-year</b>            |                                           |                                            |                                           |                                                     |  |
|--------------------------------------|----------------------------|-------------------------------------------|--------------------------------------------|-------------------------------------------|-----------------------------------------------------|--|----------------------------|-------------------------------------------|--------------------------------------------|-------------------------------------------|-----------------------------------------------------|--|
|                                      | <b>i</b><br><b>(mm/hr)</b> | <b>Q<sub>actual</sub></b><br><b>(L/s)</b> | <b>Q<sub>release</sub></b><br><b>(L/s)</b> | <b>Q<sub>stored</sub></b><br><b>(L/s)</b> | <b>V<sub>stored</sub></b><br><b>(m<sup>3</sup>)</b> |  | <b>i</b><br><b>(mm/hr)</b> | <b>Q<sub>actual</sub></b><br><b>(L/s)</b> | <b>Q<sub>release</sub></b><br><b>(L/s)</b> | <b>Q<sub>stored</sub></b><br><b>(L/s)</b> | <b>V<sub>stored</sub></b><br><b>(m<sup>3</sup>)</b> |  |
| 10                                   | 104.2                      | 25.3                                      | 5.8                                        | 19.5                                      | 11.7                                                |  | 178.6                      | 48.1                                      | 7.6                                        | 40.5                                      | 24.3                                                |  |
| 15                                   | 83.6                       | 20.3                                      | 5.8                                        | 14.5                                      | 13.1                                                |  | 142.9                      | 38.5                                      | 7.6                                        | 30.9                                      | 27.8                                                |  |
| 20                                   | 70.3                       | 17.0                                      | 5.8                                        | 11.3                                      | 13.5                                                |  | 120.0                      | 32.3                                      | 7.6                                        | 24.7                                      | 29.7                                                |  |
| 25                                   | 60.9                       | 14.8                                      | 5.8                                        | 9.0                                       | 13.5                                                |  | 103.8                      | 28.0                                      | 7.6                                        | 20.4                                      | 30.6                                                |  |
| 30                                   | 53.9                       | 13.1                                      | 5.8                                        | 7.3                                       | 13.2                                                |  | 91.9                       | 24.8                                      | 7.6                                        | 17.1                                      | 30.9                                                |  |
| 35                                   | 48.5                       | 11.8                                      | 5.8                                        | 6.0                                       | 12.6                                                |  | 82.6                       | 22.3                                      | 7.6                                        | 14.6                                      | 30.8                                                |  |
| 40                                   | 44.2                       | 10.7                                      | 5.8                                        | 5.0                                       | 11.9                                                |  | 75.1                       | 20.3                                      | 7.6                                        | 12.6                                      | 30.3                                                |  |
| 45                                   | 40.6                       | 9.9                                       | 5.8                                        | 4.1                                       | 11.1                                                |  | 69.1                       | 18.6                                      | 7.6                                        | 11.0                                      | 29.7                                                |  |
| 50                                   | 37.7                       | 9.1                                       | 5.8                                        | 3.4                                       | 10.1                                                |  | 64.0                       | 17.2                                      | 7.6                                        | 9.6                                       | 28.9                                                |  |
| 55                                   | 35.1                       | 8.5                                       | 5.8                                        | 2.8                                       | 9.1                                                 |  | 59.6                       | 16.1                                      | 7.6                                        | 8.5                                       | 27.9                                                |  |
| 60                                   | 32.9                       | 8.0                                       | 5.8                                        | 2.2                                       | 8.0                                                 |  | 55.9                       | 15.1                                      | 7.6                                        | 7.5                                       | 26.8                                                |  |
| 65                                   | 31.0                       | 7.5                                       | 5.8                                        | 1.8                                       | 6.9                                                 |  | 52.6                       | 14.2                                      | 7.6                                        | 6.6                                       | 25.7                                                |  |
| 70                                   | 29.4                       | 7.1                                       | 5.8                                        | 1.4                                       | 5.7                                                 |  | 49.8                       | 13.4                                      | 7.6                                        | 5.8                                       | 24.4                                                |  |
| 75                                   | 27.9                       | 6.8                                       | 5.8                                        | 1.0                                       | 4.5                                                 |  | 47.3                       | 12.7                                      | 7.6                                        | 5.1                                       | 23.1                                                |  |
| 80                                   | 26.6                       | 6.4                                       | 5.8                                        | 0.7                                       | 3.3                                                 |  | 45.0                       | 12.1                                      | 7.6                                        | 4.5                                       | 21.7                                                |  |
| 85                                   | 25.4                       | 6.2                                       | 5.8                                        | 0.4                                       | 2.0                                                 |  | 43.0                       | 11.6                                      | 7.6                                        | 4.0                                       | 20.2                                                |  |
| 90                                   | 24.3                       | 5.9                                       | 5.8                                        | 0.1                                       | 0.7                                                 |  | 41.1                       | 11.1                                      | 7.6                                        | 3.5                                       | 18.7                                                |  |
| 95                                   | 23.3                       | 5.7                                       | 5.7                                        | 0.0                                       | 0.0                                                 |  | 39.4                       | 10.6                                      | 7.6                                        | 3.0                                       | 17.2                                                |  |
| 100                                  | 22.4                       | 5.4                                       | 5.4                                        | 0.0                                       | 0.0                                                 |  | 37.9                       | 10.2                                      | 7.6                                        | 2.6                                       | 15.6                                                |  |
| 105                                  | 21.6                       | 5.2                                       | 5.2                                        | 0.0                                       | 0.0                                                 |  | 36.5                       | 9.8                                       | 7.6                                        | 2.2                                       | 14.0                                                |  |
| 110                                  | 20.8                       | 5.1                                       | 5.1                                        | 0.0                                       | 0.0                                                 |  | 35.2                       | 9.5                                       | 7.6                                        | 1.9                                       | 12.4                                                |  |

|                                       |                           |                                         |                           |
|---------------------------------------|---------------------------|-----------------------------------------|---------------------------|
| <b>5-year Q<sub>roof</sub></b>        | <b>5.76 L/s</b>           | <b>100-year Q<sub>roof</sub></b>        | <b>7.61 L/s</b>           |
| <b>5-year Max. Storage Required</b>   | <b>13.5 m<sup>3</sup></b> | <b>100-year Max. Storage Required</b>   | <b>30.9 m<sup>3</sup></b> |
| <b>5-year Storage Depth</b>           | <b>0.076 m</b>            | <b>100-year Storage Depth</b>           | <b>0.100 m</b>            |
| <b>5-year Estimated Drawdown Time</b> | <b>0.78 hr</b>            | <b>100-year Estimated Drawdown Time</b> | <b>1.41 hr</b>            |

**Estimated Post Development Peak Flow from Attenuated Areas**

Area ID                      A + BLDG D  
 Available Sub-surface Storage

Total U/G Storage Volume (m<sup>3</sup>)                      157.0

**Stage Attenuated Areas Storage Summary**

|               | Surface Storage |                              |                       |                | Surface and Subsurface Storage |                                          |                                 |                               |
|---------------|-----------------|------------------------------|-----------------------|----------------|--------------------------------|------------------------------------------|---------------------------------|-------------------------------|
|               | Stage<br>(m)    | Ponding<br>(m <sup>2</sup> ) | h <sub>o</sub><br>(m) | delta d<br>(m) | V*<br>(m <sup>3</sup> )        | V <sub>acc</sub> **<br>(m <sup>3</sup> ) | Q <sub>release</sub> †<br>(L/s) | V <sub>drawdown</sub><br>(hr) |
| Orifice INV   | 101.44          | -                            | 0.00                  |                |                                | 0.0                                      | 0.0                             | 0.00                          |
| Cistern INV   | 101.99          | -                            | 0.55                  | 0.55           | 78.5                           | 78.5                                     | 133.3                           | 0.16                          |
| Cistern OBV   | 102.63          | -                            | 1.19                  | 0.64           | 78.5                           | 157.0                                    | 195.6                           | 0.22                          |
| T/L1          | 103.25          | 0.4                          | 1.81                  | 0.63           | 0.1                            | 157.1                                    | 241.8                           | 0.18                          |
| T/L2          | 103.30          | 137.6                        | 1.86                  | 0.05           | 2.4                            | 159.5                                    | 245.1                           | 0.18                          |
| T/L3          | 103.35          | 745.2                        | 1.91                  | 0.05           | 20.0                           | 179.6                                    | 248.4                           | 0.20                          |
| 0.15m Ponding | 103.40          | 1953.5                       | 1.96                  | 0.05           | 65.1                           | 244.6                                    | 251.6                           | 0.27                          |
| Max Ponding   | 103.55          | 8389.9                       | 2.11                  | 0.15           | 719.6                          | 964.2                                    | 261.0                           | 1.03                          |

\* V=Incremental storage volume

\*\*V<sub>acc</sub>=Total surface and sub-surface

† Q<sub>release</sub> = Release rate calculated from orifice equation

$$Q = C_d \times A \times \sqrt{2 \times g \times h_o}$$

Where    Q = Release rate (cms)  
           C<sub>d</sub> =Discharge Coefficient (0.61)  
           A =Area of the orifice(m<sup>2</sup>)  
           g =gravitational constant (9.81m/s<sup>2</sup>)  
           h<sub>o eff</sub> =Effective head above the orifice due to waterlevel at outlet

Orifice Location                      STM101                      Dia                      291

Total Area                      2.91 ha

C                      0.82 Rational Method runoff coefficient                      Note: Rational Method Coefficient "C" increased by 25% for 100-year calculations

| t <sub>c</sub><br>(min) | 5-year       |                                |                               |                              |                                          |  | 100-year     |                                |                               |                              |                                          |  |
|-------------------------|--------------|--------------------------------|-------------------------------|------------------------------|------------------------------------------|--|--------------|--------------------------------|-------------------------------|------------------------------|------------------------------------------|--|
|                         | i<br>(mm/hr) | Q <sub>actual</sub> †<br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) |  | i<br>(mm/hr) | Q <sub>actual</sub> †<br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) |  |
| 5                       | 141.2        | 971.3                          | 252.4                         | 719.0                        | 215.7                                    |  | 242.7        | 2013.5                         | 261.0                         | 1752.5                       | 525.7                                    |  |
| 10                      | 104.2        | 727.3                          | 252.4                         | 474.9                        | 285.0                                    |  | 178.6        | 1495.3                         | 261.0                         | 1234.2                       | 740.5                                    |  |
| 15                      | 83.6         | 591.2                          | 252.4                         | 338.8                        | 304.9                                    |  | 142.9        | 1207.1                         | 261.0                         | 946.1                        | 851.5                                    |  |
| 20                      | 70.3         | 503.4                          | 252.4                         | 251.0                        | 301.2                                    |  | 120.0        | 1021.8                         | 261.0                         | 760.7                        | 912.9                                    |  |
| 25                      | 60.9         | 441.6                          | 252.4                         | 189.3                        | 283.9                                    |  | 103.8        | 891.7                          | 261.0                         | 630.6                        | 946.0                                    |  |
| 30                      | 53.9         | 395.7                          | 252.4                         | 143.3                        | 257.9                                    |  | 91.9         | 794.9                          | 261.0                         | 533.9                        | 960.9                                    |  |
| 35                      | 48.5         | 360.0                          | 252.4                         | 107.6                        | 225.9                                    |  | 82.6         | 719.8                          | 261.0                         | 458.8                        | 963.5                                    |  |
| 40                      | 44.2         | 331.4                          | 252.4                         | 79.0                         | 189.6                                    |  | 75.1         | 659.8                          | 261.0                         | 398.8                        | 957.0                                    |  |
| 45                      | 40.6         | 307.9                          | 252.4                         | 55.5                         | 150.0                                    |  | 69.1         | 610.5                          | 261.0                         | 349.5                        | 943.7                                    |  |
| 50                      | 37.7         | 288.3                          | 252.4                         | 35.9                         | 107.7                                    |  | 64.0         | 569.4                          | 261.0                         | 308.3                        | 925.0                                    |  |
| 55                      | 35.1         | 271.6                          | 252.4                         | 19.2                         | 63.4                                     |  | 59.6         | 534.4                          | 261.0                         | 273.4                        | 902.1                                    |  |
| 60                      | 32.9         | 257.2                          | 252.4                         | 4.8                          | 17.4                                     |  | 55.9         | 504.2                          | 261.0                         | 243.2                        | 875.6                                    |  |
| 65                      | 31.0         | 244.7                          | 244.7                         | 0.0                          | 0.0                                      |  | 52.6         | 478.0                          | 261.0                         | 217.0                        | 846.2                                    |  |
| 70                      | 29.4         | 233.6                          | 233.6                         | 0.0                          | 0.0                                      |  | 49.8         | 454.9                          | 261.0                         | 193.9                        | 814.4                                    |  |
| 75                      | 27.9         | 223.9                          | 223.9                         | 0.0                          | 0.0                                      |  | 47.3         | 434.5                          | 261.0                         | 173.4                        | 780.4                                    |  |
| 80                      | 26.6         | 215.1                          | 215.1                         | 0.0                          | 0.0                                      |  | 45.0         | 416.2                          | 261.0                         | 155.1                        | 744.6                                    |  |
| 85                      | 25.4         | 207.2                          | 207.2                         | 0.0                          | 0.0                                      |  | 43.0         | 399.7                          | 261.0                         | 138.7                        | 707.2                                    |  |
| 90                      | 24.3         | 200.1                          | 200.1                         | 0.0                          | 0.0                                      |  | 41.1         | 384.8                          | 261.0                         | 123.8                        | 668.4                                    |  |
| 95                      | 23.3         | 193.6                          | 193.6                         | 0.0                          | 0.0                                      |  | 39.4         | 371.3                          | 261.0                         | 110.2                        | 628.4                                    |  |
| 100                     | 22.4         | 187.7                          | 187.7                         | 0.0                          | 0.0                                      |  | 37.9         | 358.9                          | 261.0                         | 97.9                         | 587.2                                    |  |
| 105                     | 21.6         | 182.2                          | 182.2                         | 0.0                          | 0.0                                      |  | 36.5         | 347.5                          | 261.0                         | 86.5                         | 545.0                                    |  |

† Includes controlled flow from BLDG A-G

|                                |                      |                                  |                      |
|--------------------------------|----------------------|----------------------------------|----------------------|
| 5-year Q <sub>attenuated</sub> | 252.4 L/s            | 100-year Q <sub>attenuated</sub> | 261.0 L/s            |
| 5-year Max. Storage Required   | 304.9 m <sup>3</sup> | 100-year Max. Storage Required   | 963.5 m <sup>3</sup> |
| Est. 5-year Storage Elevation  | 103.41 m             | Est. 100-year Storage Elevation  | 103.55 m             |

**Summary of Release Rates and Storage Volumes**

| Control Area | 5-Year<br>Required<br>Storage<br>(m <sup>3</sup> ) | 100-Year<br>Required<br>Storage<br>(m <sup>3</sup> ) | 100-Year<br>Available<br>Storage*<br>(m <sup>3</sup> ) |
|--------------|----------------------------------------------------|------------------------------------------------------|--------------------------------------------------------|
| U1           | 0.0                                                | 0.0                                                  | 0.0                                                    |
| U2           | 0.0                                                | 0.0                                                  | 0.0                                                    |
| U3           | 0.0                                                | 0.0                                                  | 0.0                                                    |
| A1           | 304.9                                              | 963.5                                                | 964.2                                                  |
| <b>Total</b> | <b>304.9</b>                                       | <b>963.5</b>                                         | <b>964.2</b>                                           |

\*Note Available Storage Not Including Structure and Sewer Storage

Stormwater - Proposed Development  
City of Ottawa Sewer Design Guidelines, 2012



#### Target Flow Rate

| Site Area |                                                    | 5-year                  |              |                              | 100-year     |                              |
|-----------|----------------------------------------------------|-------------------------|--------------|------------------------------|--------------|------------------------------|
|           |                                                    | t <sub>c</sub><br>(min) | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) |
| C         | 4.44 ha<br>0.74 Rational Method runoff coefficient | 21.4                    | 67.4         | 271.6                        | 115.0        | 463.6                        |

#### Estimated Post Development Peak Flow from Unattenuated Areas

Area ID U1

Total Area 0.679 ha  
C 0.24 Rational Method runoff coefficient

| 5-year                  |              |                              |                               |                              |                                          | 100-year     |                              |                               |                              |                                          |
|-------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|
| t <sub>c</sub><br>(min) | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) |
| 15.1                    | 83.2         | 37.3                         | 37.3                          | 0.0                          | 0.0                                      | 142.4        | 79.7                         | 79.7                          | 0.0                          | 0.0                                      |

Area ID U2

Total Area 0.079 ha  
C 0.59 Rational Method runoff coefficient

| 5-year                  |              |                              |                               |                              |                                          | 100-year     |                              |                               |                              |                                          |
|-------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|
| t <sub>c</sub><br>(min) | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) |
| 15.1                    | 83.2         | 10.6                         | 10.6                          | 0.0                          | 0.0                                      | 142.4        | 22.7                         | 22.7                          | 0.0                          | 0.0                                      |

Area ID U3

Total Area 0.015 ha  
C 0.90 Rational Method runoff coefficient

| 5-year                  |              |                              |                               |                              |                                          | 100-year     |                              |                               |                              |                                          |
|-------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|
| t <sub>c</sub><br>(min) | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) |
| 15.1                    | 83.2         | 3.2                          | 3.2                           | 0.0                          | 0.0                                      | 142.4        | 6.1                          | 6.1                           | 0.0                          | 0.0                                      |



**Estimated Post Development Storage Requirement**

|                           |                                                                                                                                 |
|---------------------------|---------------------------------------------------------------------------------------------------------------------------------|
| <b>Building ID</b>        | <b>BLDG A</b>                                                                                                                   |
| <b>Roof Area</b>          | 0.190 ha                                                                                                                        |
| <b>Avail Storage Area</b> | 0.180                                                                                                                           |
| <b>C</b>                  | 0.90 Rational Method runoff coefficient <i>Note: Rational Method Coefficient "C" increased by 25% for 100-year calculations</i> |
| <b>t<sub>c</sub></b>      | 10 min, t <sub>c</sub> at outlet without restriction                                                                            |

**Estimated Number of Roof Drains**

|                              |                                                                         |
|------------------------------|-------------------------------------------------------------------------|
| <b>Building Length</b>       | 86.6                                                                    |
| <b>Building Width</b>        | 22.3                                                                    |
| <b>Number of Drains</b>      | 9                                                                       |
| <b>m<sup>2</sup> / Drain</b> | 200.1 max 232.25m <sup>2</sup> /notch as recommended by Zurn for Ottawa |

| <b>Roof Top Rating Curve per Zurn Model Z-105-5</b> |                        |                        |                          |                          |                         |                             |
|-----------------------------------------------------|------------------------|------------------------|--------------------------|--------------------------|-------------------------|-----------------------------|
| <b>d</b>                                            | <b>A</b>               | <b>V<sub>acc</sub></b> | <b>V<sub>avail</sub></b> | <b>Q<sub>notch</sub></b> | <b>Q<sub>roof</sub></b> | <b>V<sub>drawdown</sub></b> |
| <b>(m)</b>                                          | <b>(m<sup>2</sup>)</b> | <b>(m<sup>3</sup>)</b> | <b>(m<sup>3</sup>)</b>   | <b>(L/s)</b>             | <b>(L/s)</b>            | <b>(hr)</b>                 |
| 0.000                                               | 0                      | 0.0                    | 0.0                      | 0.00                     | 0.00                    | 0.00                        |
| 0.025                                               | 112.6                  | 0.9                    | 0.9                      | 0.38                     | 3.42                    | 0.08                        |
| 0.050                                               | 450.3                  | 6.6                    | 7.5                      | 0.77                     | 6.93                    | 0.34                        |
| 0.075                                               | 1013.1                 | 17.8                   | 25.3                     | 1.14                     | 10.26                   | 0.82                        |
| 0.100                                               | 1801.0                 | 34.7                   | 60.0                     | 1.52                     | 13.68                   | 1.53                        |
| 0.125                                               | 1801.0                 | 45.0                   | 105.1                    | 1.90                     | 17.10                   | 2.26                        |
| 0.150                                               | 1801.0                 | 45.0                   | 150.1                    | 2.28                     | 20.52                   | 2.87                        |

\* Assumes one notch opening per drain, assumes maximum slope of 10cm

| <b>t<sub>c</sub></b><br><b>(min)</b> | <b>5-year</b>              |                                           |                                            |                                           |                                                     | <b>100-year</b>            |                                           |                                            |                                           |                                                     |
|--------------------------------------|----------------------------|-------------------------------------------|--------------------------------------------|-------------------------------------------|-----------------------------------------------------|----------------------------|-------------------------------------------|--------------------------------------------|-------------------------------------------|-----------------------------------------------------|
|                                      | <b>i</b><br><b>(mm/hr)</b> | <b>Q<sub>actual</sub></b><br><b>(L/s)</b> | <b>Q<sub>release</sub></b><br><b>(L/s)</b> | <b>Q<sub>stored</sub></b><br><b>(L/s)</b> | <b>V<sub>stored</sub></b><br><b>(m<sup>3</sup>)</b> | <b>i</b><br><b>(mm/hr)</b> | <b>Q<sub>actual</sub></b><br><b>(L/s)</b> | <b>Q<sub>release</sub></b><br><b>(L/s)</b> | <b>Q<sub>stored</sub></b><br><b>(L/s)</b> | <b>V<sub>stored</sub></b><br><b>(m<sup>3</sup>)</b> |
| 10                                   | 104.2                      | 49.4                                      | 10.5                                       | 38.9                                      | 23.3                                                | 178.6                      | 94.0                                      | 13.8                                       | 80.2                                      | 48.1                                                |
| 15                                   | 83.6                       | 39.6                                      | 10.5                                       | 29.1                                      | 26.2                                                | 142.9                      | 75.3                                      | 13.8                                       | 61.4                                      | 55.3                                                |
| 20                                   | 70.3                       | 33.3                                      | 10.5                                       | 22.8                                      | 27.4                                                | 120.0                      | 63.2                                      | 13.8                                       | 49.3                                      | 59.2                                                |
| 25                                   | 60.9                       | 28.9                                      | 10.5                                       | 18.4                                      | 27.6                                                | 103.8                      | 54.7                                      | 13.8                                       | 40.8                                      | 61.3                                                |
| 30                                   | 53.9                       | 25.6                                      | 10.5                                       | 15.1                                      | 27.1                                                | 91.9                       | 48.4                                      | 13.8                                       | 34.5                                      | 62.2                                                |
| 35                                   | 48.5                       | 23.0                                      | 10.5                                       | 12.5                                      | 26.3                                                | 82.6                       | 43.5                                      | 13.8                                       | 29.6                                      | 62.2                                                |
| 40                                   | 44.2                       | 20.9                                      | 10.5                                       | 10.5                                      | 25.1                                                | 75.1                       | 39.6                                      | 13.8                                       | 25.7                                      | 61.7                                                |
| 45                                   | 40.6                       | 19.3                                      | 10.5                                       | 8.8                                       | 23.7                                                | 69.1                       | 36.4                                      | 13.8                                       | 22.5                                      | 60.8                                                |
| 50                                   | 37.7                       | 17.8                                      | 10.5                                       | 7.4                                       | 22.1                                                | 64.0                       | 33.7                                      | 13.8                                       | 19.8                                      | 59.5                                                |
| 55                                   | 35.1                       | 16.6                                      | 10.5                                       | 6.2                                       | 20.3                                                | 59.6                       | 31.4                                      | 13.8                                       | 17.6                                      | 57.9                                                |
| 60                                   | 32.9                       | 15.6                                      | 10.5                                       | 5.1                                       | 18.5                                                | 55.9                       | 29.4                                      | 13.8                                       | 15.6                                      | 56.1                                                |
| 65                                   | 31.0                       | 14.7                                      | 10.5                                       | 4.2                                       | 16.5                                                | 52.6                       | 27.7                                      | 13.8                                       | 13.9                                      | 54.1                                                |
| 70                                   | 29.4                       | 13.9                                      | 10.5                                       | 3.4                                       | 14.4                                                | 49.8                       | 26.2                                      | 13.8                                       | 12.4                                      | 52.0                                                |
| 75                                   | 27.9                       | 13.2                                      | 10.5                                       | 2.7                                       | 12.3                                                | 47.3                       | 24.9                                      | 13.8                                       | 11.0                                      | 49.7                                                |
| 80                                   | 26.6                       | 12.6                                      | 10.5                                       | 2.1                                       | 10.1                                                | 45.0                       | 23.7                                      | 13.8                                       | 9.8                                       | 47.3                                                |
| 85                                   | 25.4                       | 12.0                                      | 10.5                                       | 1.5                                       | 7.9                                                 | 43.0                       | 22.6                                      | 13.8                                       | 8.8                                       | 44.7                                                |
| 90                                   | 24.3                       | 11.5                                      | 10.5                                       | 1.0                                       | 5.6                                                 | 41.1                       | 21.6                                      | 13.8                                       | 7.8                                       | 42.1                                                |
| 95                                   | 23.3                       | 11.0                                      | 10.5                                       | 0.6                                       | 3.2                                                 | 39.4                       | 20.8                                      | 13.8                                       | 6.9                                       | 39.4                                                |
| 100                                  | 22.4                       | 10.6                                      | 10.5                                       | 0.1                                       | 0.8                                                 | 37.9                       | 20.0                                      | 13.8                                       | 6.1                                       | 36.7                                                |
| 105                                  | 21.6                       | 10.2                                      | 10.2                                       | 0.0                                       | 0.0                                                 | 36.5                       | 19.2                                      | 13.8                                       | 5.4                                       | 33.8                                                |
| 110                                  | 20.8                       | 9.9                                       | 9.9                                        | 0.0                                       | 0.0                                                 | 35.2                       | 18.5                                      | 13.8                                       | 4.7                                       | 31.0                                                |

|                                       |                           |                                         |                           |
|---------------------------------------|---------------------------|-----------------------------------------|---------------------------|
| <b>5-year Q<sub>roof</sub></b>        | <b>10.48 L/s</b>          | <b>100-year Q<sub>roof</sub></b>        | <b>13.85 L/s</b>          |
| <b>5-year Max. Storage Required</b>   | <b>27.6 m<sup>3</sup></b> | <b>100-year Max. Storage Required</b>   | <b>62.2 m<sup>3</sup></b> |
| <b>5-year Storage Depth</b>           | <b>0.077 m</b>            | <b>100-year Storage Depth</b>           | <b>0.101 m</b>            |
| <b>5-year Estimated Drawdown Time</b> | <b>0.87 hr</b>            | <b>100-year Estimated Drawdown Time</b> | <b>1.56 hr</b>            |

**Iber Hazeldean Land Limited**  
**5734-5754 Hazeldean Road/24 Iber Road**  
**Proposed Site Conditions with Back Water**

**Building ID**            **BLDG B**  
**Roof Area**            0.140 ha  
**Avail Storage Area**    0.133  
**C**                        0.90 Rational Method runoff coefficient    *Note: Rational Method Coefficient "C" increased by 25% for 100-year calculations*  
**t<sub>c</sub>**                        10 min, t<sub>c</sub> at outlet without restriction

**Estimated Number of Roof Drains**

**Building Length**            58.0  
**Building Width**            24.0  
**Number of Drains**            6  
**m<sup>2</sup> / Drain**                222.3 max 232.25m<sup>2</sup>/notch as recommended by Zurn for Ottawa

| Roof Top Rating Curve per Zurn Model Z-105-5 |                   |                   |                    |                    |                   |                       |
|----------------------------------------------|-------------------|-------------------|--------------------|--------------------|-------------------|-----------------------|
| d                                            | A                 | V <sub>acc</sub>  | V <sub>avail</sub> | Q <sub>notch</sub> | Q <sub>roof</sub> | V <sub>drawdown</sub> |
| (m)                                          | (m <sup>2</sup> ) | (m <sup>3</sup> ) | (m <sup>3</sup> )  | (L/s)              | (L/s)             | (hr)                  |
| 0.000                                        | 0                 | 0.0               | 0.0                | 0.00               | 0.00              | 0.00                  |
| 0.025                                        | 83.4              | 0.7               | 0.7                | 0.38               | 2.28              | 0.08                  |
| 0.050                                        | 333.5             | 4.9               | 5.6                | 0.77               | 4.62              | 0.38                  |
| 0.075                                        | 750.3             | 13.2              | 18.8               | 1.14               | 6.84              | 0.91                  |
| 0.100                                        | 1333.9            | 25.7              | 44.5               | 1.52               | 9.12              | 1.70                  |
| 0.125                                        | 1333.9            | 33.3              | 77.8               | 1.90               | 11.40             | 2.51                  |
| 0.150                                        | 1333.9            | 33.3              | 111.2              | 2.28               | 13.68             | 3.19                  |

\* Assumes one notch opening per drain, assumes maximum slope of 10cm

| t <sub>c</sub><br>(min) | 5-year       |                              |                               |                              |                                          | 100-year     |                              |                               |                              |                                          |
|-------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|
|                         | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) |
| 10                      | 104.2        | 36.6                         | 7.1                           | 29.5                         | 17.7                                     | 178.6        | 69.6                         | 9.4                           | 60.3                         | 36.2                                     |
| 15                      | 83.6         | 29.3                         | 7.1                           | 22.3                         | 20.0                                     | 142.9        | 55.7                         | 9.4                           | 46.4                         | 41.7                                     |
| 20                      | 70.3         | 24.7                         | 7.1                           | 17.6                         | 21.1                                     | 120.0        | 46.8                         | 9.4                           | 37.4                         | 44.9                                     |
| 25                      | 60.9         | 21.4                         | 7.1                           | 14.3                         | 21.4                                     | 103.8        | 40.5                         | 9.4                           | 31.1                         | 46.7                                     |
| 30                      | 53.9         | 18.9                         | 7.1                           | 11.9                         | 21.3                                     | 91.9         | 35.8                         | 9.4                           | 26.5                         | 47.6                                     |
| 35                      | 48.5         | 17.0                         | 7.1                           | 10.0                         | 20.9                                     | 82.6         | 32.2                         | 9.4                           | 22.8                         | 48.0                                     |
| 40                      | 44.2         | 15.5                         | 7.1                           | 8.4                          | 20.2                                     | 75.1         | 29.3                         | 9.4                           | 19.9                         | 47.9                                     |
| 45                      | 40.6         | 14.3                         | 7.1                           | 7.2                          | 19.4                                     | 69.1         | 26.9                         | 9.4                           | 17.6                         | 47.4                                     |
| 50                      | 37.7         | 13.2                         | 7.1                           | 6.1                          | 18.4                                     | 64.0         | 24.9                         | 9.4                           | 15.6                         | 46.8                                     |
| 55                      | 35.1         | 12.3                         | 7.1                           | 5.3                          | 17.3                                     | 59.6         | 23.3                         | 9.4                           | 13.9                         | 45.9                                     |
| 60                      | 32.9         | 11.6                         | 7.1                           | 4.5                          | 16.1                                     | 55.9         | 21.8                         | 9.4                           | 12.4                         | 44.8                                     |
| 65                      | 31.0         | 10.9                         | 7.1                           | 3.8                          | 14.9                                     | 52.6         | 20.5                         | 9.4                           | 11.2                         | 43.6                                     |
| 70                      | 29.4         | 10.3                         | 7.1                           | 3.2                          | 13.6                                     | 49.8         | 19.4                         | 9.4                           | 10.1                         | 42.2                                     |
| 75                      | 27.9         | 9.8                          | 7.1                           | 2.7                          | 12.2                                     | 47.3         | 18.4                         | 9.4                           | 9.1                          | 40.8                                     |
| 80                      | 26.6         | 9.3                          | 7.1                           | 2.2                          | 10.8                                     | 45.0         | 17.5                         | 9.4                           | 8.2                          | 39.3                                     |
| 85                      | 25.4         | 8.9                          | 7.1                           | 1.8                          | 9.3                                      | 43.0         | 16.8                         | 9.4                           | 7.4                          | 37.7                                     |
| 90                      | 24.3         | 8.5                          | 7.1                           | 1.4                          | 7.8                                      | 41.1         | 16.0                         | 9.4                           | 6.7                          | 36.0                                     |
| 95                      | 23.3         | 8.2                          | 7.1                           | 1.1                          | 6.3                                      | 39.4         | 15.4                         | 9.4                           | 6.0                          | 34.3                                     |
| 100                     | 22.4         | 7.9                          | 7.1                           | 0.8                          | 4.7                                      | 37.9         | 14.8                         | 9.4                           | 5.4                          | 32.5                                     |
| 105                     | 21.6         | 7.6                          | 7.1                           | 0.5                          | 3.1                                      | 36.5         | 14.2                         | 9.4                           | 4.9                          | 30.7                                     |
| 110                     | 20.8         | 7.3                          | 7.1                           | 0.2                          | 1.5                                      | 35.2         | 13.7                         | 9.4                           | 4.4                          | 28.8                                     |

**5-year Q<sub>roof</sub>**                    7.08 L/s  
**5-year Max. Storage Required**    21.4 m<sup>3</sup>  
**5-year Storage Depth**            0.078 m  
**5-year Estimated Drawdown Time**    1.00 hr

**100-year Q<sub>roof</sub>**                    9.36 L/s  
**100-year Max. Storage Required**    48.0 m<sup>3</sup>  
**100-year Storage Depth**            0.103 m  
**100-year Estimated Drawdown Time**    1.78 hr

**Iber Hazeldean Land Limited**  
**5734-5754 Hazeldean Road/24 Iber Road**  
**Proposed Site Conditions with Back Water**

**Building ID**      **BLDG BB**  
**Roof Area**      0.041 ha  
**Avail Storage Area**      0.039  
**C**      0.90 Rational Method runoff coefficient      *Note: Rational Method Coefficient "C" increased by 25% for 100-year calculations*  
**t<sub>c</sub>**      10 min, t<sub>c</sub> at outlet without restriction

**Estimated Number of Roof Drains**

**Building Length**      15.5  
**Building Width**      24.0  
**Number of Drains**      2  
**m<sup>2</sup> / Drain**      194.7 max 232.25m<sup>2</sup>/notch as recommended by Zurn for Ottawa

| Roof Top Rating Curve per Zurn Model Z-105-5 |                   |                   |                    |                    |                   |                       |
|----------------------------------------------|-------------------|-------------------|--------------------|--------------------|-------------------|-----------------------|
| d                                            | A                 | V <sub>acc</sub>  | V <sub>avail</sub> | Q <sub>notch</sub> | Q <sub>roof</sub> | V <sub>drawdown</sub> |
| (m)                                          | (m <sup>2</sup> ) | (m <sup>3</sup> ) | (m <sup>3</sup> )  | (L/s)              | (L/s)             | (hr)                  |
| 0.000                                        | 0                 | 0.0               | 0.0                | 0.00               | 0.00              | 0.00                  |
| 0.025                                        | 24.3              | 0.2               | 0.2                | 0.38               | 0.76              | 0.07                  |
| 0.050                                        | 97.3              | 1.4               | 1.6                | 0.77               | 1.54              | 0.33                  |
| 0.075                                        | 219.0             | 3.9               | 5.5                | 1.14               | 2.28              | 0.80                  |
| 0.100                                        | 389.3             | 7.5               | 13.0               | 1.52               | 3.04              | 1.49                  |
| 0.125                                        | 389.3             | 9.7               | 22.7               | 1.90               | 3.80              | 2.20                  |
| 0.150                                        | 389.3             | 9.7               | 32.4               | 2.28               | 4.56              | 2.79                  |

\* Assumes one notch opening per drain, assumes maximum slope of 10cm

| t <sub>c</sub><br>(min) | 5-year       |                              |                               |                              |                                          | 100-year     |                              |                               |                              |                                          |
|-------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|
|                         | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) |
| 10                      | 104.2        | 10.7                         | 2.3                           | 8.4                          | 5.0                                      | 178.6        | 20.3                         | 3.1                           | 17.3                         | 10.4                                     |
| 15                      | 83.6         | 8.6                          | 2.3                           | 6.2                          | 5.6                                      | 142.9        | 16.3                         | 3.1                           | 13.2                         | 11.9                                     |
| 20                      | 70.3         | 7.2                          | 2.3                           | 4.9                          | 5.9                                      | 120.0        | 13.7                         | 3.1                           | 10.6                         | 12.7                                     |
| 25                      | 60.9         | 6.2                          | 2.3                           | 3.9                          | 5.9                                      | 103.8        | 11.8                         | 3.1                           | 8.8                          | 13.1                                     |
| 30                      | 53.9         | 5.5                          | 2.3                           | 3.2                          | 5.8                                      | 91.9         | 10.5                         | 3.1                           | 7.4                          | 13.3                                     |
| 35                      | 48.5         | 5.0                          | 2.3                           | 2.7                          | 5.6                                      | 82.6         | 9.4                          | 3.1                           | 6.3                          | 13.3                                     |
| 40                      | 44.2         | 4.5                          | 2.3                           | 2.2                          | 5.3                                      | 75.1         | 8.6                          | 3.1                           | 5.5                          | 13.2                                     |
| 45                      | 40.6         | 4.2                          | 2.3                           | 1.8                          | 5.0                                      | 69.1         | 7.9                          | 3.1                           | 4.8                          | 12.9                                     |
| 50                      | 37.7         | 3.9                          | 2.3                           | 1.5                          | 4.6                                      | 64.0         | 7.3                          | 3.1                           | 4.2                          | 12.6                                     |
| 55                      | 35.1         | 3.6                          | 2.3                           | 1.3                          | 4.2                                      | 59.6         | 6.8                          | 3.1                           | 3.7                          | 12.3                                     |
| 60                      | 32.9         | 3.4                          | 2.3                           | 1.1                          | 3.8                                      | 55.9         | 6.4                          | 3.1                           | 3.3                          | 11.9                                     |
| 65                      | 31.0         | 3.2                          | 2.3                           | 0.9                          | 3.4                                      | 52.6         | 6.0                          | 3.1                           | 2.9                          | 11.4                                     |
| 70                      | 29.4         | 3.0                          | 2.3                           | 0.7                          | 2.9                                      | 49.8         | 5.7                          | 3.1                           | 2.6                          | 10.9                                     |
| 75                      | 27.9         | 2.9                          | 2.3                           | 0.5                          | 2.4                                      | 47.3         | 5.4                          | 3.1                           | 2.3                          | 10.4                                     |
| 80                      | 26.6         | 2.7                          | 2.3                           | 0.4                          | 1.9                                      | 45.0         | 5.1                          | 3.1                           | 2.1                          | 9.9                                      |
| 85                      | 25.4         | 2.6                          | 2.3                           | 0.3                          | 1.4                                      | 43.0         | 4.9                          | 3.1                           | 1.8                          | 9.3                                      |
| 90                      | 24.3         | 2.5                          | 2.3                           | 0.2                          | 0.9                                      | 41.1         | 4.7                          | 3.1                           | 1.6                          | 8.7                                      |
| 95                      | 23.3         | 2.4                          | 2.3                           | 0.1                          | 0.4                                      | 39.4         | 4.5                          | 3.1                           | 1.4                          | 8.1                                      |
| 100                     | 22.4         | 2.3                          | 2.3                           | 0.0                          | 0.0                                      | 37.9         | 4.3                          | 3.1                           | 1.2                          | 7.5                                      |
| 105                     | 21.6         | 2.2                          | 2.2                           | 0.0                          | 0.0                                      | 36.5         | 4.2                          | 3.1                           | 1.1                          | 6.9                                      |
| 110                     | 20.8         | 2.1                          | 2.1                           | 0.0                          | 0.0                                      | 35.2         | 4.0                          | 3.1                           | 0.9                          | 6.2                                      |

**5-year Q<sub>roof</sub>**      2.32 L/s  
**5-year Max. Storage Required**      5.9 m<sup>3</sup>  
**5-year Storage Depth**      0.076 m  
**5-year Estimated Drawdown Time**      0.84 hr

**100-year Q<sub>roof</sub>**      3.07 L/s  
**100-year Max. Storage Required**      13.3 m<sup>3</sup>  
**100-year Storage Depth**      0.101 m  
**100-year Estimated Drawdown Time**      1.51 hr

**Iber Hazeldean Land Limited**  
**5734-5754 Hazeldean Road/24 Iber Road**  
**Proposed Site Conditions with Back Water**

|                           |                                                                                                                                 |
|---------------------------|---------------------------------------------------------------------------------------------------------------------------------|
| <b>Building ID</b>        | <b>BLDG C</b>                                                                                                                   |
| <b>Roof Area</b>          | 0.288 ha                                                                                                                        |
| <b>Avail Storage Area</b> | 0.274                                                                                                                           |
| <b>C</b>                  | 0.90 Rational Method runoff coefficient <i>Note: Rational Method Coefficient "C" increased by 25% for 100-year calculations</i> |
| <b>t<sub>c</sub></b>      | 10 min, t <sub>c</sub> at outlet without restriction                                                                            |

**Estimated Number of Roof Drains**

|                              |                                                                         |
|------------------------------|-------------------------------------------------------------------------|
| <b>Building Length</b>       | 64.2                                                                    |
| <b>Building Width</b>        | 43.8                                                                    |
| <b>Number of Drains</b>      | 12                                                                      |
| <b>m<sup>2</sup> / Drain</b> | 228.4 max 232.25m <sup>2</sup> /notch as recommended by Zurn for Ottawa |

| <b>Roof Top Rating Curve per Zurn Model Z-105-5</b> |                        |                        |                          |                          |                         |                             |
|-----------------------------------------------------|------------------------|------------------------|--------------------------|--------------------------|-------------------------|-----------------------------|
| <b>d</b>                                            | <b>A</b>               | <b>V<sub>acc</sub></b> | <b>V<sub>avail</sub></b> | <b>Q<sub>notch</sub></b> | <b>Q<sub>roof</sub></b> | <b>V<sub>drawdown</sub></b> |
| <b>(m)</b>                                          | <b>(m<sup>2</sup>)</b> | <b>(m<sup>3</sup>)</b> | <b>(m<sup>3</sup>)</b>   | <b>(L/s)</b>             | <b>(L/s)</b>            | <b>(hr)</b>                 |
| 0.000                                               | 0                      | 0.0                    | 0.0                      | 0.00                     | 0.00                    | 0.00                        |
| 0.025                                               | 171.3                  | 1.4                    | 1.4                      | 0.38                     | 4.56                    | 0.09                        |
| 0.050                                               | 685.1                  | 10.0                   | 11.4                     | 0.77                     | 9.24                    | 0.39                        |
| 0.075                                               | 1541.4                 | 27.1                   | 38.5                     | 1.14                     | 13.68                   | 0.94                        |
| 0.100                                               | 2740.3                 | 52.8                   | 91.3                     | 1.52                     | 18.24                   | 1.74                        |
| 0.125                                               | 2740.3                 | 68.5                   | 159.9                    | 1.90                     | 22.80                   | 2.58                        |
| 0.150                                               | 2740.3                 | 68.5                   | 228.4                    | 2.28                     | 27.36                   | 3.27                        |

\* Assumes one notch opening per drain, assumes maximum slope of 10cm

| <b>t<sub>c</sub></b><br><b>(min)</b> | <b>5-year</b>              |                                           |                                            |                                           |                                                     | <b>100-year</b>            |                                           |                                            |                                           |                                                     |
|--------------------------------------|----------------------------|-------------------------------------------|--------------------------------------------|-------------------------------------------|-----------------------------------------------------|----------------------------|-------------------------------------------|--------------------------------------------|-------------------------------------------|-----------------------------------------------------|
|                                      | <b>i</b><br><b>(mm/hr)</b> | <b>Q<sub>actual</sub></b><br><b>(L/s)</b> | <b>Q<sub>release</sub></b><br><b>(L/s)</b> | <b>Q<sub>stored</sub></b><br><b>(L/s)</b> | <b>V<sub>stored</sub></b><br><b>(m<sup>3</sup>)</b> | <b>i</b><br><b>(mm/hr)</b> | <b>Q<sub>actual</sub></b><br><b>(L/s)</b> | <b>Q<sub>release</sub></b><br><b>(L/s)</b> | <b>Q<sub>stored</sub></b><br><b>(L/s)</b> | <b>V<sub>stored</sub></b><br><b>(m<sup>3</sup>)</b> |
| 10                                   | 104.2                      | 75.1                                      | 14.2                                       | 60.9                                      | 36.6                                                | 178.6                      | 143.1                                     | 18.8                                       | 124.3                                     | 74.6                                                |
| 15                                   | 83.6                       | 60.3                                      | 14.2                                       | 46.1                                      | 41.4                                                | 142.9                      | 114.5                                     | 18.8                                       | 95.7                                      | 86.1                                                |
| 20                                   | 70.3                       | 50.7                                      | 14.2                                       | 36.5                                      | 43.8                                                | 120.0                      | 96.1                                      | 18.8                                       | 77.3                                      | 92.8                                                |
| 25                                   | 60.9                       | 43.9                                      | 14.2                                       | 29.7                                      | 44.6                                                | 103.8                      | 83.2                                      | 18.8                                       | 64.4                                      | 96.6                                                |
| 30                                   | 53.9                       | 38.9                                      | 14.2                                       | 24.7                                      | 44.4                                                | 91.9                       | 73.6                                      | 18.8                                       | 54.8                                      | 98.7                                                |
| 35                                   | 48.5                       | 35.0                                      | 14.2                                       | 20.8                                      | 43.7                                                | 82.6                       | 66.2                                      | 18.8                                       | 47.4                                      | 99.5                                                |
| 40                                   | 44.2                       | 31.9                                      | 14.2                                       | 17.7                                      | 42.4                                                | 75.1                       | 60.2                                      | 18.8                                       | 41.4                                      | 99.4                                                |
| 45                                   | 40.6                       | 29.3                                      | 14.2                                       | 15.1                                      | 40.8                                                | 69.1                       | 55.3                                      | 18.8                                       | 36.5                                      | 98.7                                                |
| 50                                   | 37.7                       | 27.2                                      | 14.2                                       | 13.0                                      | 38.9                                                | 64.0                       | 51.2                                      | 18.8                                       | 32.5                                      | 97.4                                                |
| 55                                   | 35.1                       | 25.3                                      | 14.2                                       | 11.1                                      | 36.7                                                | 59.6                       | 47.8                                      | 18.8                                       | 29.0                                      | 95.7                                                |
| 60                                   | 32.9                       | 23.8                                      | 14.2                                       | 9.6                                       | 34.4                                                | 55.9                       | 44.8                                      | 18.8                                       | 26.0                                      | 93.6                                                |
| 65                                   | 31.0                       | 22.4                                      | 14.2                                       | 8.2                                       | 31.9                                                | 52.6                       | 42.2                                      | 18.8                                       | 23.4                                      | 91.3                                                |
| 70                                   | 29.4                       | 21.2                                      | 14.2                                       | 7.0                                       | 29.3                                                | 49.8                       | 39.9                                      | 18.8                                       | 21.1                                      | 88.7                                                |
| 75                                   | 27.9                       | 20.1                                      | 14.2                                       | 5.9                                       | 26.6                                                | 47.3                       | 37.9                                      | 18.8                                       | 19.1                                      | 85.9                                                |
| 80                                   | 26.6                       | 19.2                                      | 14.2                                       | 5.0                                       | 23.8                                                | 45.0                       | 36.0                                      | 18.8                                       | 17.3                                      | 82.9                                                |
| 85                                   | 25.4                       | 18.3                                      | 14.2                                       | 4.1                                       | 20.9                                                | 43.0                       | 34.4                                      | 18.8                                       | 15.6                                      | 79.7                                                |
| 90                                   | 24.3                       | 17.5                                      | 14.2                                       | 3.3                                       | 17.9                                                | 41.1                       | 32.9                                      | 18.8                                       | 14.2                                      | 76.4                                                |
| 95                                   | 23.3                       | 16.8                                      | 14.2                                       | 2.6                                       | 14.8                                                | 39.4                       | 31.6                                      | 18.8                                       | 12.8                                      | 73.0                                                |
| 100                                  | 22.4                       | 16.2                                      | 14.2                                       | 2.0                                       | 11.7                                                | 37.9                       | 30.4                                      | 18.8                                       | 11.6                                      | 69.5                                                |
| 105                                  | 21.6                       | 15.6                                      | 14.2                                       | 1.4                                       | 8.6                                                 | 36.5                       | 29.2                                      | 18.8                                       | 10.5                                      | 65.9                                                |
| 110                                  | 20.8                       | 15.0                                      | 14.2                                       | 0.8                                       | 5.4                                                 | 35.2                       | 28.2                                      | 18.8                                       | 9.4                                       | 62.2                                                |

|                                       |                           |                                         |                           |
|---------------------------------------|---------------------------|-----------------------------------------|---------------------------|
| <b>5-year Q<sub>roof</sub></b>        | <b>14.20 L/s</b>          | <b>100-year Q<sub>roof</sub></b>        | <b>18.78 L/s</b>          |
| <b>5-year Max. Storage Required</b>   | <b>44.6 m<sup>3</sup></b> | <b>100-year Max. Storage Required</b>   | <b>99.5 m<sup>3</sup></b> |
| <b>5-year Storage Depth</b>           | <b>0.078 m</b>            | <b>100-year Storage Depth</b>           | <b>0.103 m</b>            |
| <b>5-year Estimated Drawdown Time</b> | <b>1.03 hr</b>            | <b>100-year Estimated Drawdown Time</b> | <b>1.84 hr</b>            |

**Iber Hazeldean Land Limited**  
**5734-5754 Hazeldean Road/24 Iber Road**  
**Proposed Site Conditions with Back Water**

**Building ID** FUT. BLDG G  
**Roof Area** 0.097 ha  
**Avail Storage Area** 0.092  
**C** 0.90 Rational Method runoff coefficient *Note: Rational Method Coefficient "C" increased by 25% for 100-year calculations*  
**t<sub>c</sub>** 10 min, t<sub>c</sub> at outlet without restriction

**Estimated Number of Roof Drains**

**Building Length** 20.2  
**Building Width** 53.1  
**Number of Drains** 5  
**m<sup>2</sup> / Drain** 184.4 max 232.25m<sup>2</sup>/notch as recommended by Zurn for Ottawa

| Roof Top Rating Curve per Zurn Model Z-105-5 |                   |                   |                    |                    |                   |                       |
|----------------------------------------------|-------------------|-------------------|--------------------|--------------------|-------------------|-----------------------|
| d                                            | A                 | V <sub>acc</sub>  | V <sub>avail</sub> | Q <sub>notch</sub> | Q <sub>roof</sub> | V <sub>drawdown</sub> |
| (m)                                          | (m <sup>2</sup> ) | (m <sup>3</sup> ) | (m <sup>3</sup> )  | (L/s)              | (L/s)             | (hr)                  |
| 0.000                                        | 0                 | 0.0               | 0.0                | 0.00               | 0.00              | 0.00                  |
| 0.025                                        | 57.6              | 0.5               | 0.5                | 0.38               | 1.90              | 0.07                  |
| 0.050                                        | 230.4             | 3.4               | 3.8                | 0.77               | 3.85              | 0.31                  |
| 0.075                                        | 518.5             | 9.1               | 13.0               | 1.14               | 5.70              | 0.76                  |
| 0.100                                        | 921.8             | 17.8              | 30.7               | 1.52               | 7.60              | 1.41                  |
| 0.125                                        | 921.8             | 23.0              | 53.8               | 1.90               | 9.50              | 2.08                  |
| 0.150                                        | 921.8             | 23.0              | 76.8               | 2.28               | 11.40             | 2.64                  |

\* Assumes one notch opening per drain, assumes maximum slope of 10cm

| t <sub>c</sub><br>(min) | 5-year       |                              |                               |                              |                                          | 100-year     |                              |                               |                              |                                          |
|-------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|
|                         | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) |
| 10                      | 104.2        | 25.3                         | 5.8                           | 19.5                         | 11.7                                     | 178.6        | 48.1                         | 7.6                           | 40.5                         | 24.3                                     |
| 15                      | 83.6         | 20.3                         | 5.8                           | 14.5                         | 13.1                                     | 142.9        | 38.5                         | 7.6                           | 30.9                         | 27.8                                     |
| 20                      | 70.3         | 17.0                         | 5.8                           | 11.3                         | 13.5                                     | 120.0        | 32.3                         | 7.6                           | 24.7                         | 29.7                                     |
| 25                      | 60.9         | 14.8                         | 5.8                           | 9.0                          | 13.5                                     | 103.8        | 28.0                         | 7.6                           | 20.4                         | 30.6                                     |
| 30                      | 53.9         | 13.1                         | 5.8                           | 7.3                          | 13.2                                     | 91.9         | 24.8                         | 7.6                           | 17.1                         | 30.9                                     |
| 35                      | 48.5         | 11.8                         | 5.8                           | 6.0                          | 12.6                                     | 82.6         | 22.3                         | 7.6                           | 14.6                         | 30.8                                     |
| 40                      | 44.2         | 10.7                         | 5.8                           | 5.0                          | 11.9                                     | 75.1         | 20.3                         | 7.6                           | 12.6                         | 30.3                                     |
| 45                      | 40.6         | 9.9                          | 5.8                           | 4.1                          | 11.1                                     | 69.1         | 18.6                         | 7.6                           | 11.0                         | 29.7                                     |
| 50                      | 37.7         | 9.1                          | 5.8                           | 3.4                          | 10.1                                     | 64.0         | 17.2                         | 7.6                           | 9.6                          | 28.9                                     |
| 55                      | 35.1         | 8.5                          | 5.8                           | 2.8                          | 9.1                                      | 59.6         | 16.1                         | 7.6                           | 8.5                          | 27.9                                     |
| 60                      | 32.9         | 8.0                          | 5.8                           | 2.2                          | 8.0                                      | 55.9         | 15.1                         | 7.6                           | 7.5                          | 26.8                                     |
| 65                      | 31.0         | 7.5                          | 5.8                           | 1.8                          | 6.9                                      | 52.6         | 14.2                         | 7.6                           | 6.6                          | 25.7                                     |
| 70                      | 29.4         | 7.1                          | 5.8                           | 1.4                          | 5.7                                      | 49.8         | 13.4                         | 7.6                           | 5.8                          | 24.4                                     |
| 75                      | 27.9         | 6.8                          | 5.8                           | 1.0                          | 4.5                                      | 47.3         | 12.7                         | 7.6                           | 5.1                          | 23.1                                     |
| 80                      | 26.6         | 6.4                          | 5.8                           | 0.7                          | 3.3                                      | 45.0         | 12.1                         | 7.6                           | 4.5                          | 21.7                                     |
| 85                      | 25.4         | 6.2                          | 5.8                           | 0.4                          | 2.0                                      | 43.0         | 11.6                         | 7.6                           | 4.0                          | 20.2                                     |
| 90                      | 24.3         | 5.9                          | 5.8                           | 0.1                          | 0.7                                      | 41.1         | 11.1                         | 7.6                           | 3.5                          | 18.7                                     |
| 95                      | 23.3         | 5.7                          | 5.7                           | 0.0                          | 0.0                                      | 39.4         | 10.6                         | 7.6                           | 3.0                          | 17.2                                     |
| 100                     | 22.4         | 5.4                          | 5.4                           | 0.0                          | 0.0                                      | 37.9         | 10.2                         | 7.6                           | 2.6                          | 15.6                                     |
| 105                     | 21.6         | 5.2                          | 5.2                           | 0.0                          | 0.0                                      | 36.5         | 9.8                          | 7.6                           | 2.2                          | 14.0                                     |
| 110                     | 20.8         | 5.1                          | 5.1                           | 0.0                          | 0.0                                      | 35.2         | 9.5                          | 7.6                           | 1.9                          | 12.4                                     |

|                                       |                           |                                         |                           |
|---------------------------------------|---------------------------|-----------------------------------------|---------------------------|
| <b>5-year Q<sub>roof</sub></b>        | <b>5.76 L/s</b>           | <b>100-year Q<sub>roof</sub></b>        | <b>7.61 L/s</b>           |
| <b>5-year Max. Storage Required</b>   | <b>13.5 m<sup>3</sup></b> | <b>100-year Max. Storage Required</b>   | <b>30.9 m<sup>3</sup></b> |
| <b>5-year Storage Depth</b>           | <b>0.076 m</b>            | <b>100-year Storage Depth</b>           | <b>0.100 m</b>            |
| <b>5-year Estimated Drawdown Time</b> | <b>0.78 hr</b>            | <b>100-year Estimated Drawdown Time</b> | <b>1.41 hr</b>            |

## Estimated Post Development Peak Flow from Attenuated Areas

Area ID A+ BLDG D

Total Subsurface Storage (m<sup>3</sup>) 374.9

## Stage Attenuated Areas Storage Summary

| Stage         | Surface Storage   |                |         |                   | Surface and Subsurface Storage |                             |                               |            |              |                        |                          |
|---------------|-------------------|----------------|---------|-------------------|--------------------------------|-----------------------------|-------------------------------|------------|--------------|------------------------|--------------------------|
|               | Ponding           | h <sub>o</sub> | delta d | V*                | V <sub>acc</sub> **            | 5-yr Q <sub>release</sub> † | 100-yr Q <sub>release</sub> † | 5-yr Elev. | 100-yr Elev. | h <sub>o eff</sub> 5yr | h <sub>o eff</sub> 100yr |
| (m)           | (m <sup>2</sup> ) | (m)            | (m)     | (m <sup>3</sup> ) | (m <sup>3</sup> )              | (L/s)                       | (L/s)                         | (m)        | (m)          | (m)                    | (m)                      |
| Orifice INV   | 101.44            | -              | 0.00    |                   | 0.0                            | 0.0                         | 0.0                           | 101.91     | 102.52       | 0.00                   | 0.00                     |
| Cistern INV   | 101.99            | -              | 0.55    | 187.5             | 187.5                          | 0.0                         | 0.0                           | 101.91     | 102.52       | 0.00                   | 0.00                     |
| Cistern OBV   | 102.63            | -              | 1.19    | 187.5             | 374.9                          | 152.0                       | 0.0                           | 101.91     | 102.52       | 0.72                   | 0.00                     |
| T/L1          | 103.25            | 0.4            | 1.81    | 0.63              | 0.1                            | 375.0                       | 208.0                         | 101.91     | 102.52       | 1.34                   | 0.73                     |
| T/L2          | 103.30            | 137.6          | 1.86    | 0.05              | 2.4                            | 377.4                       | 211.9                         | 101.91     | 102.52       | 1.39                   | 0.78                     |
| T/L3          | 103.35            | 745.2          | 1.91    | 0.05              | 20.0                           | 397.5                       | 215.6                         | 101.91     | 102.52       | 1.44                   | 0.83                     |
| 0.15m Ponding | 103.40            | 1953.5         | 1.96    | 0.05              | 65.1                           | 462.6                       | 219.4                         | 101.91     | 102.52       | 1.49                   | 0.88                     |
| Max Ponding   | 103.55            | 8389.9         | 2.11    | 0.15              | 719.6                          | 1182.2                      | 230.1                         | 101.91     | 102.52       | 1.64                   | 1.03                     |

\* V=Incremental storage volume

Note: 5 and 100 year water elevations provided by JFSA

\*\*V<sub>acc</sub>=Total surface and sub-surface† Q<sub>release</sub> = Release rate calculated from orifice equation accounting for backwater using the 5-year and 100-year waterlevels respectively

$$Q = C_d \times A \times \sqrt{2 \times g \times h_o}$$

Where Q = Release rate (cms)  
C<sub>d</sub> = Discharge Coefficient (0.61)  
A = Area of the orifice (m<sup>2</sup>)  
g = gravitational constant (9.81 m/s<sup>2</sup>)  
h<sub>o eff</sub> = Effective head above the orifice due to waterlevel at outlet

Orifice Location STM101 Dia 291

Total Area 2.908 ha

C

0.82 Rational Method runoff coefficient

Note: Rational Method Coefficient "C" increased by 25% for 100-year calculations

| t <sub>c</sub><br>(min) | 5-year       |                                |                               |                              |                                          | 100-year     |                                |                               |                              |                                          |
|-------------------------|--------------|--------------------------------|-------------------------------|------------------------------|------------------------------------------|--------------|--------------------------------|-------------------------------|------------------------------|------------------------------------------|
|                         | i<br>(mm/hr) | Q <sub>actual</sub> ‡<br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) | i<br>(mm/hr) | Q <sub>actual</sub> ‡<br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) |
| 5                       | 141.2        | 971.3                          | 191.7                         | 779.7                        | 233.9                                    | 242.7        | 2013.5                         | 182.0                         | 1831.5                       | 549.4                                    |
| 10                      | 104.2        | 727.3                          | 191.7                         | 535.7                        | 321.4                                    | 178.6        | 1495.3                         | 182.0                         | 1313.3                       | 788.0                                    |
| 15                      | 83.6         | 591.2                          | 191.7                         | 399.5                        | 359.6                                    | 142.9        | 1207.1                         | 182.0                         | 1025.1                       | 922.6                                    |
| 20                      | 70.3         | 503.4                          | 191.7                         | 311.7                        | 374.1                                    | 120.0        | 1021.8                         | 182.0                         | 839.8                        | 1007.7                                   |
| 25                      | 60.9         | 441.6                          | 191.7                         | 250.0                        | 375.0                                    | 103.8        | 891.7                          | 182.0                         | 709.7                        | 1064.5                                   |
| 30                      | 53.9         | 395.7                          | 191.7                         | 204.0                        | 367.2                                    | 91.9         | 794.9                          | 182.0                         | 612.9                        | 1103.2                                   |
| 35                      | 48.5         | 360.0                          | 191.7                         | 168.3                        | 353.5                                    | 82.6         | 719.8                          | 182.0                         | 537.8                        | 1129.4                                   |
| 40                      | 44.2         | 331.4                          | 191.7                         | 139.7                        | 335.3                                    | 75.1         | 659.8                          | 182.0                         | 477.8                        | 1146.6                                   |
| 45                      | 40.6         | 307.9                          | 191.7                         | 116.3                        | 313.9                                    | 69.1         | 610.5                          | 182.0                         | 428.5                        | 1157.0                                   |
| 50                      | 37.7         | 288.3                          | 191.7                         | 96.6                         | 289.9                                    | 64.0         | 569.4                          | 182.0                         | 387.4                        | 1162.1                                   |
| 55                      | 35.1         | 271.6                          | 191.7                         | 79.9                         | 263.8                                    | 59.6         | 534.4                          | 182.0                         | 352.4                        | 1162.8                                   |
| 60                      | 32.9         | 257.2                          | 191.7                         | 65.6                         | 236.0                                    | 55.9         | 504.2                          | 182.0                         | 322.2                        | 1160.1                                   |
| 65                      | 31.0         | 244.7                          | 191.7                         | 53.0                         | 206.8                                    | 52.6         | 478.0                          | 182.0                         | 296.0                        | 1154.4                                   |
| 70                      | 29.4         | 233.6                          | 191.7                         | 42.0                         | 176.3                                    | 49.8         | 454.9                          | 182.0                         | 272.9                        | 1146.3                                   |
| 75                      | 27.9         | 223.9                          | 191.7                         | 32.2                         | 144.9                                    | 47.3         | 434.5                          | 182.0                         | 252.4                        | 1136.0                                   |
| 80                      | 26.6         | 215.1                          | 191.7                         | 23.4                         | 112.5                                    | 45.0         | 416.2                          | 182.0                         | 234.1                        | 1123.9                                   |
| 85                      | 25.4         | 207.2                          | 191.7                         | 15.6                         | 79.4                                     | 43.0         | 399.7                          | 182.0                         | 217.7                        | 1110.2                                   |
| 90                      | 24.3         | 200.1                          | 191.7                         | 8.4                          | 45.6                                     | 41.1         | 384.8                          | 182.0                         | 202.8                        | 1095.1                                   |
| 95                      | 23.3         | 193.6                          | 191.7                         | 2.0                          | 11.2                                     | 39.4         | 371.3                          | 182.0                         | 189.3                        | 1078.8                                   |
| 100                     | 22.4         | 187.7                          | 187.7                         | 0.0                          | 0.0                                      | 37.9         | 358.9                          | 182.0                         | 176.9                        | 1061.3                                   |
| 105                     | 21.6         | 182.2                          | 182.2                         | 0.0                          | 0.0                                      | 36.5         | 347.5                          | 182.0                         | 165.5                        | 1042.8                                   |

‡ Includes controlled flow from BLDG A-G

5-year Q<sub>attenuated</sub> 191.65 L/s  
5-year Max. Storage Required 375.0 m<sup>3</sup>  
Est. 5-year Storage Elevation 103.07 m

100-year Q<sub>attenuated</sub> 182.01 L/s  
100-year Max. Storage Required 1162.8 m<sup>3</sup>  
Est. 100-year Storage Elevation 103.55 m

## Summary of Release Rates and Storage Volumes

| Control Area | 5-Year Release Rate<br>(L/s) | 5-Year Required Storage<br>(m <sup>3</sup> ) | 100-Year Release Rate<br>(L/s) | 100-Year Required Storage<br>(m <sup>3</sup> ) | 100-Year Available Storage<br>(m <sup>3</sup> ) |
|--------------|------------------------------|----------------------------------------------|--------------------------------|------------------------------------------------|-------------------------------------------------|
| U1           | 37.3                         | 0.0                                          | 79.7                           | 0.0                                            | 0.0                                             |
| U2           | 10.6                         | 0.0                                          | 22.7                           | 0.0                                            | 0.0                                             |
| U3           | 3.2                          | 0.0                                          | 6.1                            | 0.0                                            | 0.0                                             |
| A1           | 191.7                        | 375.0                                        | 182.0                          | 1162.8                                         | 1182.2                                          |
| Total        | 242.8                        | 375.0                                        | 290.5                          | 1162.8                                         | 1182.2                                          |

\* Note Attenuated Areas includes constant controlled flow from BLDG A-G

Stormwater - Proposed Development  
 City of Ottawa Sewer Design Guidelines, 2012



#### Target Flow Rate

Site Area 4.44 ha  
 C 0.74 Rational Method runoff coefficient

#### Estimated Post Development Peak Flow from Unattenuated Areas

Area ID U1

Total Area 0.679 ha  
 C 0.24 Rational Method runoff coefficient

| 2-year                  |              |                              |                               |                              |                                          |
|-------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|
| t <sub>c</sub><br>(min) | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) |
| 15.1                    | 61.5         | 27.6                         | 27.6                          | 0.0                          | 0.0                                      |

Area ID U2

Total Area 0.079 ha  
 C 0.59 Rational Method runoff coefficient

| 2-year                  |              |                              |                               |                              |                                          |
|-------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|
| t <sub>c</sub><br>(min) | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) |
| 15.1                    | 61.5         | 7.9                          | 7.9                           | 0.0                          | 0.0                                      |

Area ID U3

Total Area 0.015 ha  
 C 0.90 Rational Method runoff coefficient

| 2-year                  |              |                              |                               |                              |                                          |
|-------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|
| t <sub>c</sub><br>(min) | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) |
| 15.1                    | 61.5         | 2.4                          | 2.4                           | 0.0                          | 0.0                                      |

**Estimated Post Development Storage Requirement**

|                           |                                                      |
|---------------------------|------------------------------------------------------|
| <b>Building ID</b>        | <b>BLDG A</b>                                        |
| <b>Roof Area</b>          | 0.190 ha                                             |
| <b>Avail Storage Area</b> | 0.180                                                |
| <b>C</b>                  | 0.90 Rational Method runoff coefficient              |
| <b>t<sub>c</sub></b>      | 10 min, t <sub>c</sub> at outlet without restriction |

**Estimated Number of Roof Drains**

|                              |                                                                         |
|------------------------------|-------------------------------------------------------------------------|
| <b>Building Length</b>       | 86.6                                                                    |
| <b>Building Width</b>        | 22.3                                                                    |
| <b>Number of Drains</b>      | 9                                                                       |
| <b>m<sup>2</sup> / Drain</b> | 200.1 max 232.25m <sup>2</sup> /notch as recommended by Zurn for Ottawa |

| <b>Roof Top Rating Curve per Zurn Model Z-105-5</b> |                        |                        |                          |                          |                         |                             |
|-----------------------------------------------------|------------------------|------------------------|--------------------------|--------------------------|-------------------------|-----------------------------|
| <b>d</b>                                            | <b>A</b>               | <b>V<sub>acc</sub></b> | <b>V<sub>avail</sub></b> | <b>Q<sub>notch</sub></b> | <b>Q<sub>roof</sub></b> | <b>V<sub>drawdown</sub></b> |
| <b>(m)</b>                                          | <b>(m<sup>2</sup>)</b> | <b>(m<sup>3</sup>)</b> | <b>(m<sup>3</sup>)</b>   | <b>(L/s)</b>             | <b>(L/s)</b>            | <b>(hr)</b>                 |
| 0.000                                               | 0                      | 0.0                    | 0.0                      | 0.00                     | 0.00                    | 0.00                        |
| 0.025                                               | 112.6                  | 0.9                    | 0.9                      | 0.38                     | 3.42                    | 0.08                        |
| 0.050                                               | 450.3                  | 6.6                    | 7.5                      | 0.77                     | 6.93                    | 0.34                        |
| 0.075                                               | 1013.1                 | 17.8                   | 25.3                     | 1.14                     | 10.26                   | 0.82                        |
| 0.100                                               | 1801.0                 | 34.7                   | 60.0                     | 1.52                     | 13.68                   | 1.53                        |
| 0.125                                               | 1801.0                 | 45.0                   | 105.1                    | 1.90                     | 17.10                   | 2.26                        |
| 0.150                                               | 1801.0                 | 45.0                   | 150.1                    | 2.28                     | 20.52                   | 2.87                        |

\* Assumes one notch opening per drain, assumes maximum slope of 10cm

| <b>2-year</b>        |                |                           |                            |                           |                           |
|----------------------|----------------|---------------------------|----------------------------|---------------------------|---------------------------|
| <b>t<sub>c</sub></b> | <b>i</b>       | <b>Q<sub>actual</sub></b> | <b>Q<sub>release</sub></b> | <b>Q<sub>stored</sub></b> | <b>V<sub>stored</sub></b> |
| <b>(min)</b>         | <b>(mm/hr)</b> | <b>(L/s)</b>              | <b>(L/s)</b>               | <b>(L/s)</b>              | <b>(m<sup>3</sup>)</b>    |
| 5                    | 103.6          | 49.1                      | 9.0                        | 40.1                      | 12.0                      |
| 10                   | 76.8           | 36.4                      | 9.0                        | 27.4                      | 16.4                      |
| 15                   | 61.8           | 29.3                      | 9.0                        | 20.2                      | 18.2                      |
| 20                   | 52.0           | 24.7                      | 9.0                        | 15.6                      | 18.8                      |
| 25                   | 45.2           | 21.4                      | 9.0                        | 12.4                      | 18.6                      |
| 30                   | 40.0           | 19.0                      | 9.0                        | 9.9                       | 17.9                      |
| 35                   | 36.1           | 17.1                      | 9.0                        | 8.1                       | 16.9                      |
| 40                   | 32.9           | 15.6                      | 9.0                        | 6.5                       | 15.7                      |
| 45                   | 30.2           | 14.3                      | 9.0                        | 5.3                       | 14.3                      |
| 50                   | 28.0           | 13.3                      | 9.0                        | 4.3                       | 12.8                      |
| 55                   | 26.2           | 12.4                      | 9.0                        | 3.4                       | 11.1                      |
| 60                   | 24.6           | 11.6                      | 9.0                        | 2.6                       | 9.4                       |
| 65                   | 23.2           | 11.0                      | 9.0                        | 1.9                       | 7.6                       |
| 70                   | 21.9           | 10.4                      | 9.0                        | 1.4                       | 5.7                       |
| 75                   | 20.8           | 9.9                       | 9.0                        | 0.8                       | 3.7                       |
| 80                   | 19.8           | 9.4                       | 9.0                        | 0.4                       | 1.8                       |
| 85                   | 18.9           | 9.0                       | 9.0                        | 0.0                       | 0.0                       |
| 90                   | 18.1           | 8.6                       | 8.6                        | 0.0                       | 0.0                       |
| 95                   | 17.4           | 8.3                       | 8.3                        | 0.0                       | 0.0                       |
| 100                  | 16.7           | 7.9                       | 7.9                        | 0.0                       | 0.0                       |
| 105                  | 16.1           | 7.6                       | 7.6                        | 0.0                       | 0.0                       |

|                                       |                           |
|---------------------------------------|---------------------------|
| <b>2-year Q<sub>roof</sub></b>        | <b>9.03 L/s</b>           |
| <b>2-year Max. Storage Required</b>   | <b>18.8 m<sup>3</sup></b> |
| <b>2-year Storage Depth</b>           | <b>0.066 m</b>            |
| <b>2-year Estimated Drawdown Time</b> | <b>0.64 hr</b>            |



**Building ID**      **BLDG B**  
**Roof Area**      0.140 ha  
**Avail Storage Area**      0.133  
**C**      0.90 Rational Method runoff coefficient  
**t<sub>c</sub>**      10 min, t<sub>c</sub> at outlet without restriction

**Estimated Number of Roof Drains**

**Building Length**      58.0  
**Building Width**      24.0  
**Number of Drains**      6  
**m<sup>2</sup> / Drain**      222.3 max 232.25m<sup>2</sup>/notch as recommended by Zurn for Ottawa

| Roof Top Rating Curve per Zurn Model Z-105-5 |                   |                   |                    |                    |                   |                       |
|----------------------------------------------|-------------------|-------------------|--------------------|--------------------|-------------------|-----------------------|
| d                                            | A                 | V <sub>acc</sub>  | V <sub>avail</sub> | Q <sub>notch</sub> | Q <sub>roof</sub> | V <sub>drawdown</sub> |
| (m)                                          | (m <sup>2</sup> ) | (m <sup>3</sup> ) | (m <sup>3</sup> )  | (L/s)              | (L/s)             | (hr)                  |
| 0.000                                        | 0                 | 0.0               | 0.0                | 0.00               | 0.00              | 0.00                  |
| 0.025                                        | 83.4              | 0.7               | 0.7                | 0.38               | 2.28              | 0.08                  |
| 0.050                                        | 333.5             | 4.9               | 5.6                | 0.77               | 4.62              | 0.38                  |
| 0.075                                        | 750.3             | 13.2              | 18.8               | 1.14               | 6.84              | 0.91                  |
| 0.100                                        | 1333.9            | 25.7              | 44.5               | 1.52               | 9.12              | 1.70                  |
| 0.125                                        | 1333.9            | 33.3              | 77.8               | 1.90               | 11.40             | 2.51                  |
| 0.150                                        | 1333.9            | 33.3              | 111.2              | 2.28               | 13.68             | 3.19                  |

\* Assumes one notch opening per drain, assumes maximum slope of 10cm

| 2-year         |         |                     |                      |                     |                     |
|----------------|---------|---------------------|----------------------|---------------------|---------------------|
| t <sub>c</sub> | i       | Q <sub>actual</sub> | Q <sub>release</sub> | Q <sub>stored</sub> | V <sub>stored</sub> |
| (min)          | (mm/hr) | (L/s)               | (L/s)                | (L/s)               | (m <sup>3</sup> )   |
| 5              | 103.6   | 36.4                | 6.1                  | 30.2                | 9.1                 |
| 10             | 76.8    | 27.0                | 6.1                  | 20.8                | 12.5                |
| 15             | 61.8    | 21.7                | 6.1                  | 15.5                | 14.0                |
| 20             | 52.0    | 18.3                | 6.1                  | 12.1                | 14.6                |
| 25             | 45.2    | 15.9                | 6.1                  | 9.7                 | 14.6                |
| 30             | 40.0    | 14.1                | 6.1                  | 7.9                 | 14.3                |
| 35             | 36.1    | 12.7                | 6.1                  | 6.5                 | 13.7                |
| 40             | 32.9    | 11.5                | 6.1                  | 5.4                 | 13.0                |
| 45             | 30.2    | 10.6                | 6.1                  | 4.5                 | 12.1                |
| 50             | 28.0    | 9.8                 | 6.1                  | 3.7                 | 11.1                |
| 55             | 26.2    | 9.2                 | 6.1                  | 3.0                 | 10.1                |
| 60             | 24.6    | 8.6                 | 6.1                  | 2.5                 | 8.9                 |
| 65             | 23.2    | 8.1                 | 6.1                  | 2.0                 | 7.8                 |
| 70             | 21.9    | 7.7                 | 6.1                  | 1.6                 | 6.5                 |
| 75             | 20.8    | 7.3                 | 6.1                  | 1.2                 | 5.3                 |
| 80             | 19.8    | 7.0                 | 6.1                  | 0.8                 | 4.0                 |
| 85             | 18.9    | 6.7                 | 6.1                  | 0.5                 | 2.6                 |
| 90             | 18.1    | 6.4                 | 6.1                  | 0.2                 | 1.3                 |
| 95             | 17.4    | 6.1                 | 6.1                  | 0.0                 | 0.0                 |
| 100            | 16.7    | 5.9                 | 5.9                  | 0.0                 | 0.0                 |
| 105            | 16.1    | 5.7                 | 5.7                  | 0.0                 | 0.0                 |

2-year Q<sub>roof</sub>      6.14 L/s  
2-year Max. Storage Required      14.6 m<sup>3</sup>  
2-year Storage Depth      0.067 m  
2-year Estimated Drawdown Time      0.74 hr

**Building ID**      **BLDG BB**  
**Roof Area**        0.041 ha  
**Avail Storage Area**    0.039  
**C**                    0.90 Rational Method runoff coefficient  
**t<sub>c</sub>**                    10 min, t<sub>c</sub> at outlet without restriction

**Estimated Number of Roof Drains**

**Building Length**      15.5  
**Building Width**        24.0  
**Number of Drains**      2  
**m<sup>2</sup> / Drain**            194.7 max 232.25m<sup>2</sup>/notch as recommended by Zurn for Ottawa

| Roof Top Rating Curve per Zurn Model Z-105-5 |                   |                   |                    |                    |                   |                       |
|----------------------------------------------|-------------------|-------------------|--------------------|--------------------|-------------------|-----------------------|
| d                                            | A                 | V <sub>acc</sub>  | V <sub>avail</sub> | Q <sub>notch</sub> | Q <sub>roof</sub> | V <sub>drawdown</sub> |
| (m)                                          | (m <sup>2</sup> ) | (m <sup>3</sup> ) | (m <sup>3</sup> )  | (L/s)              | (L/s)             | (hr)                  |
| 0.000                                        | 0                 | 0.0               | 0.0                | 0.00               | 0.00              | 0.00                  |
| 0.025                                        | 24.3              | 0.2               | 0.2                | 0.38               | 0.76              | 0.07                  |
| 0.050                                        | 97.3              | 1.4               | 1.6                | 0.77               | 1.54              | 0.33                  |
| 0.075                                        | 219.0             | 3.9               | 5.5                | 1.14               | 2.28              | 0.80                  |
| 0.100                                        | 389.3             | 7.5               | 13.0               | 1.52               | 3.04              | 1.49                  |
| 0.125                                        | 389.3             | 9.7               | 22.7               | 1.90               | 3.80              | 2.20                  |
| 0.150                                        | 389.3             | 9.7               | 32.4               | 2.28               | 4.56              | 2.79                  |

\* Assumes one notch opening per drain, assumes maximum slope of 10cm

| 2-year                  |              |                              |                               |                              |                                          |
|-------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|
| t <sub>c</sub><br>(min) | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) |
| 5                       | 103.6        | 10.6                         | 2.0                           | 8.6                          | 2.6                                      |
| 10                      | 76.8         | 7.9                          | 2.0                           | 5.9                          | 3.5                                      |
| 15                      | 61.8         | 6.3                          | 2.0                           | 4.3                          | 3.9                                      |
| 20                      | 52.0         | 5.3                          | 2.0                           | 3.3                          | 4.0                                      |
| 25                      | 45.2         | 4.6                          | 2.0                           | 2.6                          | 3.9                                      |
| 30                      | 40.0         | 4.1                          | 2.0                           | 2.1                          | 3.8                                      |
| 35                      | 36.1         | 3.7                          | 2.0                           | 1.7                          | 3.6                                      |
| 40                      | 32.9         | 3.4                          | 2.0                           | 1.4                          | 3.3                                      |
| 45                      | 30.2         | 3.1                          | 2.0                           | 1.1                          | 3.0                                      |
| 50                      | 28.0         | 2.9                          | 2.0                           | 0.9                          | 2.6                                      |
| 55                      | 26.2         | 2.7                          | 2.0                           | 0.7                          | 2.3                                      |
| 60                      | 24.6         | 2.5                          | 2.0                           | 0.5                          | 1.9                                      |
| 65                      | 23.2         | 2.4                          | 2.0                           | 0.4                          | 1.5                                      |
| 70                      | 21.9         | 2.2                          | 2.0                           | 0.2                          | 1.0                                      |
| 75                      | 20.8         | 2.1                          | 2.0                           | 0.1                          | 0.6                                      |
| 80                      | 19.8         | 2.0                          | 2.0                           | 0.0                          | 0.2                                      |
| 85                      | 18.9         | 1.9                          | 1.9                           | 0.0                          | 0.0                                      |
| 90                      | 18.1         | 1.9                          | 1.9                           | 0.0                          | 0.0                                      |
| 95                      | 17.4         | 1.8                          | 1.8                           | 0.0                          | 0.0                                      |
| 100                     | 16.7         | 1.7                          | 1.7                           | 0.0                          | 0.0                                      |
| 105                     | 16.1         | 1.7                          | 1.7                           | 0.0                          | 0.0                                      |

2-year Q<sub>roof</sub>                    2.00 L/s  
2-year Max. Storage Required            4.0 m<sup>3</sup>  
2-year Storage Depth                    0.065 m  
2-year Estimated Drawdown Time            0.62 hr

**Building ID**      **BLDG C**  
**Roof Area**      0.288 ha  
**Avail Storage Area**      0.274  
**C**      0.90 Rational Method runoff coefficient  
**t<sub>c</sub>**      10 min, t<sub>c</sub> at outlet without restriction

**Estimated Number of Roof Drains**

**Building Length**      64.2  
**Building Width**      43.8  
**Number of Drains**      12  
**m<sup>2</sup> / Drain**      228.4 max 232.25m<sup>2</sup>/notch as recommended by Zurn for Ottawa

| Roof Top Rating Curve per Zurn Model Z-105-5 |                   |                   |                    |                    |                   |                       |
|----------------------------------------------|-------------------|-------------------|--------------------|--------------------|-------------------|-----------------------|
| d                                            | A                 | V <sub>acc</sub>  | V <sub>avail</sub> | Q <sub>notch</sub> | Q <sub>roof</sub> | V <sub>drawdown</sub> |
| (m)                                          | (m <sup>2</sup> ) | (m <sup>3</sup> ) | (m <sup>3</sup> )  | (L/s)              | (L/s)             | (hr)                  |
| 0.000                                        | 0                 | 0.0               | 0.0                | 0.00               | 0.00              | 0.00                  |
| 0.025                                        | 171.3             | 1.4               | 1.4                | 0.38               | 4.56              | 0.09                  |
| 0.050                                        | 685.1             | 10.0              | 11.4               | 0.77               | 9.24              | 0.39                  |
| 0.075                                        | 1541.4            | 27.1              | 38.5               | 1.14               | 13.68             | 0.94                  |
| 0.100                                        | 2740.3            | 52.8              | 91.3               | 1.52               | 18.24             | 1.74                  |
| 0.125                                        | 2740.3            | 68.5              | 159.9              | 1.90               | 22.80             | 2.58                  |
| 0.150                                        | 2740.3            | 68.5              | 228.4              | 2.28               | 27.36             | 3.27                  |

\* Assumes one notch opening per drain, assumes maximum slope of 10cm

| 2-year                  |              |                              |                               |                              |                                          |
|-------------------------|--------------|------------------------------|-------------------------------|------------------------------|------------------------------------------|
| t <sub>c</sub><br>(min) | i<br>(mm/hr) | Q <sub>actual</sub><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub><br>(m <sup>3</sup> ) |
| 5                       | 103.6        | 74.7                         | 12.3                          | 62.3                         | 18.7                                     |
| 10                      | 76.8         | 55.4                         | 12.3                          | 43.0                         | 25.8                                     |
| 15                      | 61.8         | 44.5                         | 12.3                          | 32.2                         | 29.0                                     |
| 20                      | 52.0         | 37.5                         | 12.3                          | 25.2                         | 30.2                                     |
| 25                      | 45.2         | 32.6                         | 12.3                          | 20.2                         | 30.3                                     |
| 30                      | 40.0         | 28.9                         | 12.3                          | 16.5                         | 29.8                                     |
| 35                      | 36.1         | 26.0                         | 12.3                          | 13.7                         | 28.7                                     |
| 40                      | 32.9         | 23.7                         | 12.3                          | 11.4                         | 27.3                                     |
| 45                      | 30.2         | 21.8                         | 12.3                          | 9.5                          | 25.6                                     |
| 50                      | 28.0         | 20.2                         | 12.3                          | 7.9                          | 23.6                                     |
| 55                      | 26.2         | 18.9                         | 12.3                          | 6.5                          | 21.6                                     |
| 60                      | 24.6         | 17.7                         | 12.3                          | 5.4                          | 19.3                                     |
| 65                      | 23.2         | 16.7                         | 12.3                          | 4.4                          | 17.0                                     |
| 70                      | 21.9         | 15.8                         | 12.3                          | 3.5                          | 14.5                                     |
| 75                      | 20.8         | 15.0                         | 12.3                          | 2.7                          | 12.0                                     |
| 80                      | 19.8         | 14.3                         | 12.3                          | 2.0                          | 9.4                                      |
| 85                      | 18.9         | 13.7                         | 12.3                          | 1.3                          | 6.7                                      |
| 90                      | 18.1         | 13.1                         | 12.3                          | 0.7                          | 4.0                                      |
| 95                      | 17.4         | 12.6                         | 12.3                          | 0.2                          | 1.2                                      |
| 100                     | 16.7         | 12.1                         | 12.1                          | 0.0                          | 0.0                                      |
| 105                     | 16.1         | 11.6                         | 11.6                          | 0.0                          | 0.0                                      |

2-year Q<sub>roof</sub>      12.34 L/s  
2-year Max. Storage Required      30.3 m<sup>3</sup>  
2-year Storage Depth      0.067 m  
2-year Estimated Drawdown Time      0.77 hr

**Building ID: UT. BLDG G**

|                           |                                                      |
|---------------------------|------------------------------------------------------|
| <b>Roof Area</b>          | 0.097 ha                                             |
| <b>Avail Storage Area</b> | 0.092                                                |
| <b>C</b>                  | 0.90 Rational Method runoff coefficient              |
| <b>t<sub>c</sub></b>      | 10 min, t <sub>c</sub> at outlet without restriction |

**Estimated Number of Roof Drains**

|                              |                                                                         |
|------------------------------|-------------------------------------------------------------------------|
| <b>Building Length</b>       | 20.2                                                                    |
| <b>Building Width</b>        | 53.1                                                                    |
| <b>Number of Drains</b>      | 5                                                                       |
| <b>m<sup>2</sup> / Drain</b> | 184.4 max 232.25m <sup>2</sup> /notch as recommended by Zurn for Ottawa |

| <b>Roof Top Rating Curve per Zurn Model Z-105-5</b> |                        |                        |                          |                          |                         |                             |
|-----------------------------------------------------|------------------------|------------------------|--------------------------|--------------------------|-------------------------|-----------------------------|
| <b>d</b>                                            | <b>A</b>               | <b>V<sub>acc</sub></b> | <b>V<sub>avail</sub></b> | <b>Q<sub>notch</sub></b> | <b>Q<sub>roof</sub></b> | <b>V<sub>drawdown</sub></b> |
| <b>(m)</b>                                          | <b>(m<sup>2</sup>)</b> | <b>(m<sup>3</sup>)</b> | <b>(m<sup>3</sup>)</b>   | <b>(L/s)</b>             | <b>(L/s)</b>            | <b>(hr)</b>                 |
| 0.000                                               | 0                      | 0.0                    | 0.0                      | 0.00                     | 0.00                    | 0.00                        |
| 0.025                                               | 57.6                   | 0.5                    | 0.5                      | 0.38                     | 1.90                    | 0.07                        |
| 0.050                                               | 230.4                  | 3.4                    | 3.8                      | 0.77                     | 3.85                    | 0.31                        |
| 0.075                                               | 518.5                  | 9.1                    | 13.0                     | 1.14                     | 5.70                    | 0.76                        |
| 0.100                                               | 921.8                  | 17.8                   | 30.7                     | 1.52                     | 7.60                    | 1.41                        |
| 0.125                                               | 921.8                  | 23.0                   | 53.8                     | 1.90                     | 9.50                    | 2.08                        |
| 0.150                                               | 921.8                  | 23.0                   | 76.8                     | 2.28                     | 11.40                   | 2.64                        |

\* Assumes one notch opening per drain, assumes maximum slope of 10cm

| <b>2-year</b>        |                |                           |                            |                           |                           |
|----------------------|----------------|---------------------------|----------------------------|---------------------------|---------------------------|
| <b>t<sub>c</sub></b> | <b>i</b>       | <b>Q<sub>actual</sub></b> | <b>Q<sub>release</sub></b> | <b>Q<sub>stored</sub></b> | <b>V<sub>stored</sub></b> |
| <b>(min)</b>         | <b>(mm/hr)</b> | <b>(L/s)</b>              | <b>(L/s)</b>               | <b>(L/s)</b>              | <b>(m<sup>3</sup>)</b>    |
| 5                    | 103.6          | 25.1                      | 4.9                        | 20.2                      | 6.1                       |
| 10                   | 76.8           | 18.6                      | 4.9                        | 13.7                      | 8.2                       |
| 15                   | 61.8           | 15.0                      | 4.9                        | 10.0                      | 9.0                       |
| 20                   | 52.0           | 12.6                      | 4.9                        | 7.7                       | 9.2                       |
| 25                   | 45.2           | 11.0                      | 4.9                        | 6.0                       | 9.0                       |
| 30                   | 40.0           | 9.7                       | 4.9                        | 4.8                       | 8.6                       |
| 35                   | 36.1           | 8.7                       | 4.9                        | 3.8                       | 8.0                       |
| 40                   | 32.9           | 8.0                       | 4.9                        | 3.0                       | 7.3                       |
| 45                   | 30.2           | 7.3                       | 4.9                        | 2.4                       | 6.5                       |
| 50                   | 28.0           | 6.8                       | 4.9                        | 1.9                       | 5.6                       |
| 55                   | 26.2           | 6.3                       | 4.9                        | 1.4                       | 4.6                       |
| 60                   | 24.6           | 6.0                       | 4.9                        | 1.0                       | 3.7                       |
| 65                   | 23.2           | 5.6                       | 4.9                        | 0.7                       | 2.6                       |
| 70                   | 21.9           | 5.3                       | 4.9                        | 0.4                       | 1.6                       |
| 75                   | 20.8           | 5.0                       | 4.9                        | 0.1                       | 0.5                       |
| 80                   | 19.8           | 4.8                       | 4.8                        | 0.0                       | 0.0                       |
| 85                   | 18.9           | 4.6                       | 4.6                        | 0.0                       | 0.0                       |
| 90                   | 18.1           | 4.4                       | 4.4                        | 0.0                       | 0.0                       |
| 95                   | 17.4           | 4.2                       | 4.2                        | 0.0                       | 0.0                       |
| 100                  | 16.7           | 4.1                       | 4.1                        | 0.0                       | 0.0                       |
| 105                  | 16.1           | 3.9                       | 3.9                        | 0.0                       | 0.0                       |

|                                       |                          |
|---------------------------------------|--------------------------|
| <b>2-year Q<sub>roof</sub></b>        | <b>4.94 L/s</b>          |
| <b>2-year Max. Storage Required</b>   | <b>9.2 m<sup>3</sup></b> |
| <b>2-year Storage Depth</b>           | <b>0.065 m</b>           |
| <b>2-year Estimated Drawdown Time</b> | <b>0.57 hr</b>           |

**Iber Hazeldean Land Limited**  
**5734-5754 Hazeldean Road/24 Iber Road**  
**Proposed Site Conditions - 2 Year Storm Event**

**Estimated Post Development Peak Flow from Attenuated Areas****Area ID A+BLDG D**

## Maintenance Structures

| ID                                       | STM100 | STM101A | STM101B | STM102 | STM103 | STM104 | STM105 | STM106 | STM107 |
|------------------------------------------|--------|---------|---------|--------|--------|--------|--------|--------|--------|
| Structure dia (mm)                       | 1500   | 1500    | 1500    | 1200   | 1200   | 1800   | 1200   | 1200   | 1200   |
| T/L*                                     | 102.85 | 103.55  | 103.55  | 103.55 | 103.55 | 103.55 | 103.55 | 103.55 | 103.55 |
| INV                                      | 101.16 | 101.44  | 101.51  | 101.78 | 101.71 | 101.61 | 101.70 | 101.76 | 101.81 |
| Depth                                    | 1.69   | 2.11    | 2.04    | 1.77   | 1.84   | 1.94   | 1.85   | 1.79   | 1.94   |
| V <sub>structure</sub> (m <sup>3</sup> ) | 3.0    | 3.7     | 3.6     | 2.0    | 2.1    | 4.9    | 2.1    | 2.0    | 2.2    |

| ID                                       | CBMH108 | CBMH109 | CBMH110 | STM111 | STM112 | STM113 | STM113A | CBMH114 | CBMH37 |
|------------------------------------------|---------|---------|---------|--------|--------|--------|---------|---------|--------|
| Structure dia (mm)                       | 1200    | 1200    | 1200    | 1200   | 1200   | 1200   | 1200    | 1200    | 1200   |
| T/L*                                     | 103.30  | 103.30  | 103.30  | 103.54 | 103.50 | 103.55 | 103.55  | 103.55  | 103.55 |
| INV                                      | 101.88  | 101.82  | 101.78  | 101.86 | 101.98 | 101.89 | 101.79  | 102.22  | 102.33 |
| Depth                                    | 1.42    | 1.48    | 1.52    | 1.68   | 1.52   | 1.66   | 1.76    | 1.33    | 1.22   |
| V <sub>structure</sub> (m <sup>3</sup> ) | 1.6     | 1.7     | 1.7     | 1.9    | 1.7    | 1.9    | 2.0     | 1.5     | 1.4    |

| ID                                       | CICB1  | CICB2  | CB3    | CBMH4  | CB5    | CICB6  | CICB7  | CICB9  | CICB10 |
|------------------------------------------|--------|--------|--------|--------|--------|--------|--------|--------|--------|
| Structure dia (mm)                       | 600    | 600    | 600    | 1200   | 600    | 600    | 600    | 600    | 600    |
| T/L*                                     | 103.53 | 103.53 | 103.45 | 103.25 | 103.47 | 103.44 | 103.44 | 103.55 | 103.55 |
| INV                                      | 102.03 | 102.03 | 101.95 | 102.01 | 101.97 | 101.94 | 101.94 | 102.21 | 102.21 |
| Depth                                    | 1.50   | 1.50   | 1.50   | 1.24   | 1.50   | 1.50   | 1.50   | 1.34   | 1.34   |
| V <sub>structure</sub> (m <sup>3</sup> ) | 0.4    | 0.5    | 0.5    | 1.4    | 0.5    | 0.5    | 0.5    | 0.5    | 0.5    |

| ID                                       | CICB11 | CICB12 | CB13   | CB14   | CB15   | CB16   | CB17   | CB18   | CB19   |
|------------------------------------------|--------|--------|--------|--------|--------|--------|--------|--------|--------|
| Structure dia (mm)                       | 600    | 600    | 600    | 600    | 600    | 600    | 600    | 600    | 600    |
| T/L*                                     | 103.50 | 103.50 | 103.40 | 103.40 | 103.25 | 103.40 | 103.25 | 103.40 | 103.25 |
| INV                                      | 102.05 | 102.05 | 102.08 | 102.12 | 102.19 | 102.16 | 102.23 | 102.21 | 102.28 |
| Depth                                    | 1.45   | 1.45   | 1.32   | 1.28   | 1.06   | 1.24   | 1.02   | 1.19   | 0.97   |
| V <sub>structure</sub> (m <sup>3</sup> ) | 0.5    | 0.5    | 0.5    | 0.5    | 0.5    | 0.5    | 0.5    | 0.5    | 0.4    |

| ID                                       | CB20   | CB21   | CB22   | CB23   | CB24   | CB25   | CB26   | CB27   | CB28   |
|------------------------------------------|--------|--------|--------|--------|--------|--------|--------|--------|--------|
| Structure dia (mm)                       | 600    | 600    | 600    | 600    | 600    | 600    | 600    | 600    | 600    |
| T/L*                                     | 103.25 | 103.40 | 103.40 | 103.05 | 103.55 | 103.30 | 103.30 | 103.30 | 103.30 |
| INV                                      | 102.00 | 102.17 | 102.20 | 102.24 | 102.19 | 102.06 | 102.03 | 102.06 | 101.91 |
| Depth                                    | 1.25   | 1.23   | 1.20   | 0.81   | 1.36   | 1.24   | 1.27   | 1.24   | 1.39   |
| V <sub>structure</sub> (m <sup>3</sup> ) | 0.5    | 0.5    | 0.5    | 0.4    | 0.5    | 0.5    | 0.5    | 0.5    | 0.5    |

| ID                                       | CB29   | CB30   | CICB31 | CICB32 | CICB33 | CICB34 | CICB35 | CICB36 |
|------------------------------------------|--------|--------|--------|--------|--------|--------|--------|--------|
| Structure dia (mm)                       | 600    | 600    | 600    | 600    | 600    | 600    | 600    | 600    |
| T/L*                                     | 103.30 | 103.30 | 103.40 | 103.40 | 103.55 | 103.55 | 103.55 | 103.55 |
| INV                                      | 101.98 | 102.16 | 101.90 | 101.90 | 102.45 | 102.45 | 102.65 | 102.65 |
| Depth                                    | 1.32   | 1.14   | 1.50   | 1.50   | 1.10   | 1.10   | 0.90   | 0.90   |
| V <sub>structure</sub> (m <sup>3</sup> ) | 0.5    | 0.5    | 0.5    | 0.5    | 0.4    | 0.4    | 0.3    | 0.3    |

## Sewers

| ID                                   | 200mm | 250mm | 300mm | 375mm | 450mm | 525mm | 600mm | 675mm | 825mm |
|--------------------------------------|-------|-------|-------|-------|-------|-------|-------|-------|-------|
| Storage Pipe Dia (mm)                | 200   | 250   | 300   | 375   | 450   | 525   | 600   | 675   | 825   |
| L (m)                                | 163.8 | 219.9 | 118   | 109   | 141.5 | 46.2  | 88.8  | 27.9  | 0     |
| V <sub>sewer</sub> (m <sup>3</sup> ) | 5.1   | 10.8  | 8.3   | 12.0  | 22.5  | 10.0  | 25.1  | 10.0  | 0.0   |

\*Top of lid or max ponding elevation (103.55)

| ID                                   | 900mm | UG Storage |
|--------------------------------------|-------|------------|
| Storage Pipe Dia (mm)                | 900   | 0          |
| L (m)                                | 86.4  | 0          |
| V <sub>sewer</sub> (m <sup>3</sup> ) | 55.0  | 157.0      |

\*Top of lid or max ponding elevation (103.55)

|                                            |       |
|--------------------------------------------|-------|
| Total U/G Storage (m <sup>3</sup> )        | 157.0 |
| Total Structure Storage (m <sup>3</sup> )  | 217.9 |
| Total Subsurface Storage (m <sup>3</sup> ) | 374.9 |

**Iber Hazeldean Land Limited**  
**5734-5754 Hazeldean Road/24 Iber Road**  
**Proposed Site Conditions - 2 Year Storm Event**

**Stage Attenuated Areas Storage Summary**

| Stage         | Surface Storage   |        |         |                   | Surface and Subsurface Storage |                              |                                |            |              |                   |                     |
|---------------|-------------------|--------|---------|-------------------|--------------------------------|------------------------------|--------------------------------|------------|--------------|-------------------|---------------------|
|               | Ponding           | $h_o$  | delta d | $V^*$             | $V_{acc}^{**}$                 | 2-yr $Q_{release}^{\dagger}$ | 100-yr $Q_{release}^{\dagger}$ | 2-yr Elev. | 100-yr Elev. | $h_{o, eff, 2Yr}$ | $h_{o, eff, 100yr}$ |
| (m)           | (m <sup>2</sup> ) | (m)    | (m)     | (m <sup>3</sup> ) | (m <sup>3</sup> )              | (L/s)                        | (L/s)                          | (m)        | (m)          | (m)               | (m)                 |
| Orifice INV   | 101.44            | -      | 0.00    |                   | 0.0                            | 0.0                          | 0.0                            | 101.91     | 102.52       | 0.00              | 0.00                |
| Cistern INV   | 101.99            | -      | 0.55    | 187.5             | 187.5                          | 0.0                          | 0.0                            | 101.91     | 102.52       | 0.00              | 0.00                |
| Cistern OBV   | 102.63            | -      | 1.19    | 187.5             | 374.9                          | 152.0                        | 0.0                            | 101.91     | 102.52       | 0.72              | 0.00                |
| T/L1          | 103.25            | 0.4    | 1.81    | 0.1               | 375.0                          | 208.0                        | 153.5                          | 101.91     | 102.52       | 1.34              | 0.73                |
| T/L2          | 103.30            | 137.6  | 1.86    | 2.4               | 377.4                          | 211.9                        | 158.7                          | 101.91     | 102.52       | 1.39              | 0.78                |
| T/L3          | 103.35            | 745.2  | 1.91    | 20.0              | 397.5                          | 215.6                        | 163.7                          | 101.91     | 102.52       | 1.44              | 0.83                |
| 0.15m Ponding | 103.40            | 1953.5 | 1.96    | 65.1              | 462.6                          | 219.4                        | 168.6                          | 101.91     | 102.52       | 1.49              | 0.88                |
| Max Ponding   | 103.55            | 8389.9 | 2.11    | 719.6             | 1182.2                         | 230.1                        | 182.4                          | 101.91     | 102.52       | 1.64              | 1.03                |

\* V=Incremental storage volume

\*\*V<sub>acc</sub>=Total surface and sub-surface† Q<sub>release</sub> = Release rate calculated from orifice equation accounting for backwater using the 5-year and 100-year waterlevels respectively

$$Q = C_d \times A \times \sqrt{2 \times g \times h_o}$$

Where Q = Release rate (cms)

C<sub>d</sub> = Discharge Coefficient (0.61)A = Area of the orifice(m<sup>2</sup>)g = gravitational constant (9.81m/s<sup>2</sup>)h<sub>o, eff</sub> = Effective head above the orifice due to waterlevel at outlet

Orifice Location **STM101** Dia 291  
 Total Area 2.908 ha  
 C 0.82 Rational Method runoff coefficient

| t <sub>c</sub><br>(min) | 2-year       |                                           |                               |                              |                                                        |
|-------------------------|--------------|-------------------------------------------|-------------------------------|------------------------------|--------------------------------------------------------|
|                         | i<br>(mm/hr) | Q <sub>actual</sub> <sup>†</sup><br>(L/s) | Q <sub>release</sub><br>(L/s) | Q <sub>stored</sub><br>(L/s) | V <sub>stored</sub> <sup>††</sup><br>(m <sup>3</sup> ) |
| 5                       | 103.6        | 717.8                                     | 115.4                         | 602.4                        | 180.7                                                  |
| 10                      | 76.8         | 541.2                                     | 115.4                         | 425.8                        | 255.5                                                  |
| 15                      | 61.8         | 442.0                                     | 115.4                         | 326.6                        | 293.9                                                  |
| 20                      | 52.0         | 377.8                                     | 115.4                         | 262.3                        | 314.8                                                  |
| 25                      | 45.2         | 332.5                                     | 115.4                         | 217.0                        | 325.6                                                  |
| 30                      | 40.0         | 298.7                                     | 115.4                         | 183.2                        | 329.8                                                  |
| 35                      | 36.1         | 272.4                                     | 115.4                         | 157.0                        | 329.6                                                  |
| 40                      | 32.9         | 251.3                                     | 115.4                         | 135.9                        | 326.1                                                  |
| 45                      | 30.2         | 234.0                                     | 115.4                         | 118.6                        | 320.1                                                  |
| 50                      | 28.0         | 219.5                                     | 115.4                         | 104.1                        | 312.2                                                  |
| 55                      | 26.2         | 207.1                                     | 115.4                         | 91.7                         | 302.6                                                  |
| 60                      | 24.6         | 196.5                                     | 115.4                         | 81.1                         | 291.8                                                  |
| 65                      | 23.2         | 187.2                                     | 115.4                         | 71.8                         | 280.0                                                  |
| 70                      | 21.9         | 179.0                                     | 115.4                         | 63.6                         | 267.2                                                  |
| 75                      | 20.8         | 171.8                                     | 115.4                         | 56.4                         | 253.6                                                  |
| 80                      | 19.8         | 165.3                                     | 115.4                         | 49.9                         | 239.4                                                  |
| 85                      | 18.9         | 159.4                                     | 115.4                         | 44.0                         | 224.6                                                  |
| 90                      | 18.1         | 154.2                                     | 115.4                         | 38.7                         | 209.2                                                  |
| 95                      | 17.4         | 149.3                                     | 115.4                         | 33.9                         | 193.4                                                  |
| 100                     | 16.7         | 144.9                                     | 115.4                         | 29.5                         | 177.2                                                  |
| 105                     | 16.1         | 140.9                                     | 115.4                         | 25.5                         | 160.6                                                  |

† Includes controlled flow from BLDG A-G

†† Does not Include maintenance structure or sewer storage

**2-year Q<sub>attenuated</sub> 115.41 L/s**  
**2-year Max. Storage Required 330 m<sup>3</sup>**  
**Est. 2-year Storage Elevation 102.47 m**

**Iber Hazeldean Land Limited**  
**5734-5754 Hazeldean Road/24 Iber Road**  
**Storm Sewer Calculation Sheet**

| Area ID | Up       | Down    | Area<br>(ha) | C<br>(-) | Indiv AXC | Acc AXC | T <sub>c</sub><br>(min) | I<br>(mm/hr) | Q <sub>TOTAL</sub><br>(L/s) | DIA<br>(mm) | Slope<br>(%) | Length<br>(m) | Sewer Data                     |          |                   | Qcap<br>(L/s) | Time Flow<br>(min) | Q / Q full<br>(-) |
|---------|----------|---------|--------------|----------|-----------|---------|-------------------------|--------------|-----------------------------|-------------|--------------|---------------|--------------------------------|----------|-------------------|---------------|--------------------|-------------------|
|         |          |         |              |          |           |         |                         |              |                             |             |              |               | A <sub>hydraulic</sub><br>(m²) | R<br>(m) | Velocity<br>(m/s) |               |                    |                   |
|         | BLDG A   | STM1113 | 0.190        | 0.90     | 0.17      | 0.17    | 10.0<br>10.1            | 104.2        | 1.5                         | 250         | 1.00         | 7.9           | 0.049                          | 0.063    | 1.21              | 59.5          | 0.1                | 0.03              |
| A32     | CBMH37   | CBMH114 | 0.062        | 0.55     | 0.03      | 0.03    | 10.1                    | 103.5        | 9.8                         | 250         | 0.47         | 21.9          | 0.049                          | 0.063    | 0.83              | 40.8          | 0.4                | 0.24              |
| A31     | CBMH114  | STM1113 | 0.046        | 0.85     | 0.04      | 0.07    | 10.5<br>11.0            | 101.4        | 20.8                        | 250         | 0.44         | 22.7          | 0.049                          | 0.063    | 0.80              | 39.4          | 0.5                | 0.52              |
|         | BLDG C   | STM1113 | 0.288        | 0.90     | 0.26      | 0.26    | 10.0<br>10.0            | 104.2        | 14.2                        | 300         | 1.00         | 2.6           | 0.071                          | 0.075    | 1.37              | 96.7          | 0.0                | 0.15              |
| A30     | CKCB3536 | STM1113 | 0.055        | 0.75     | 0.04      | 0.04    | 10.0<br>10.1            | 104.2        | 11.9                        | 200         | 1.00         | 6             | 0.031                          | 0.050    | 1.04              | 32.8          | 0.1                | 0.36              |
|         | STM113   | STM113A |              |          | 0.00      | 0.28    | 11.0<br>11.7            | 99.1         | 94.1                        | 450         | 0.25         | 37.2          | 0.159                          | 0.113    | 0.90              | 142.6         | 0.7                | 0.86              |
| A29     | CKCB3334 | STM113A | 0.042        | 0.85     | 0.04      | 0.04    | 10.0<br>10.1            | 104.2        | 10.2                        | 200         | 1.00         | 5.9           | 0.031                          | 0.050    | 1.04              | 32.8          | 0.1                | 0.31              |
| A28     | CKCB3132 | STM113A | 0.091        | 0.83     | 0.08      | 0.08    | 10.0<br>10.1            | 104.2        | 21.8                        | 200         | 1.00         | 5.9           | 0.031                          | 0.050    | 1.04              | 32.8          | 0.1                | 0.68              |
|         | STM113A  | STM1104 |              |          | 0.00      | 0.40    | 11.7<br>13.0            | 95.9         | 121.1                       | 450         | 0.25         | 70            | 0.159                          | 0.113    | 0.90              | 142.6         | 1.3                | 0.85              |
| A19     | CB25     | CBMH108 | 0.251        | 0.80     | 0.20      | 0.20    | 10.0                    | 104.2        | 58.5                        | 300         | 1.00         | 17.3          | 0.071                          | 0.075    | 1.37              | 96.7          | 0.2                | 0.80              |
| A20     | CBMH108  | STM1107 | 0.111        | 0.81     | 0.09      | 0.29    | 10.2<br>10.5            | 103.1        | 83.5                        | 450         | 0.29         | 14            | 0.159                          | 0.113    | 0.97              | 153.5         | 0.2                | 0.54              |
| A18     | CB24     | STM1107 | 0.020        | 0.24     | 0.00      | 0.00    | 10.0<br>10.5            | 104.2        | 1.4                         | 200         | 1.00         | 31.7          | 0.031                          | 0.050    | 1.04              | 32.8          | 0.5                | 0.04              |
|         | BLDG B   | STM1107 | 0.140        | 0.90     | 0.13      | 0.13    | 10.0<br>10.1            | 104.2        | 7.1                         | 250         | 1.00         | 3.7           | 0.049                          | 0.063    | 1.21              | 59.5          | 0.1                | 0.12              |
|         | STM107   | STM1106 |              |          | 0.00      | 0.30    | 10.5<br>10.9            | 101.6        | 90.7                        | 450         | 0.25         | 20.3          | 0.159                          | 0.113    | 0.90              | 142.6         | 0.4                | 0.64              |
| A22     | CB27     | CB26    | 0.055        | 0.86     | 0.05      | 0.05    | 10.0                    | 104.2        | 13.6                        | 200         | 1.00         | 3.1           | 0.031                          | 0.050    | 1.04              | 32.8          | 0.0                | 0.42              |
| A21     | CB26     | CBMH109 | 0.073        | 0.87     | 0.06      | 0.11    | 10.0<br>10.3            | 103.9        | 31.9                        | 250         | 1.00         | 19.9          | 0.049                          | 0.063    | 1.21              | 59.5          | 0.3                | 0.54              |
| A24     | CB28     | CBMH109 | 0.028        | 0.84     | 0.02      | 0.02    | 10.0<br>10.0            | 104.2        | 6.8                         | 200         | 1.00         | 3             | 0.031                          | 0.050    | 1.04              | 32.8          | 0.0                | 0.21              |
| A24     | CBMH109  | STM1105 | 0.028        | 0.84     | 0.02      | 0.16    | 10.3<br>10.8            | 102.5        | 44.9                        | 375         | 0.26         | 11.4          | 0.110                          | 0.094    | 0.81              | 89.4          | 0.2                | 0.50              |
|         | STM106   | STM1105 |              |          | 0.00      | 0.46    | 10.9<br>11.2            | 99.7         | 132.9                       | 525         | 0.26         | 19.2          | 0.216                          | 0.131    | 1.01              | 219.3         | 0.3                | 0.61              |
| A25     | CB29     | CBMH110 | 0.166        | 0.80     | 0.13      | 0.13    | 10.0                    | 104.2        | 38.5                        | 250         | 1.00         | 17.3          | 0.049                          | 0.063    | 1.21              | 59.5          | 0.2                | 0.85              |
| A26     | CBMH110  | STM1105 | 0.052        | 0.86     | 0.05      | 0.18    | 10.2<br>10.5            | 103.0        | 51.0                        | 375         | 0.36         | 14            | 0.110                          | 0.094    | 0.95              | 105.2         | 0.2                | 0.48              |
|         | BLDG BB  | STM1105 | 0.041        | 0.90     | 0.04      | 0.04    | 10.0<br>10.1            | 104.2        | 2.3                         | 250         | 1.00         | 3.7           | 0.049                          | 0.063    | 1.21              | 59.5          | 0.1                | 0.04              |
| A27     | CB30     | STM1105 | 0.025        | 0.70     | 0.02      | 0.02    | 10.0<br>10.2            | 104.2        | 5.1                         | 200         | 1.00         | 12.3          | 0.031                          | 0.050    | 1.04              | 32.8          | 0.2                | 0.16              |
|         | STM105   | STM1104 |              |          | 0.00      | 0.65    | 11.2<br>11.7            | 98.3         | 186.8                       | 525         | 0.22         | 27            | 0.216                          | 0.131    | 0.93              | 201.7         | 0.5                | 0.83              |
| A17     | CB23     | STM112  | 0.070        | 0.90     | 0.06      | 0.06    | 10.0<br>11.1            | 104.2        | 18.3                        | 250         | 0.44         | 54.2          | 0.049                          | 0.063    | 0.80              | 39.4          | 1.1                | 0.46              |
| A16     | CB22     | STM112  | 0.074        | 0.75     | 0.06      | 0.06    | 10.0<br>10.1            | 104.2        | 16.1                        | 250         | 1.00         | 5.7           | 0.049                          | 0.063    | 1.21              | 59.5          | 0.1                | 0.27              |
| A15     | CB21     | STM112  | 0.052        | 0.80     | 0.04      | 0.04    | 10.0<br>10.1            | 104.2        | 12.0                        | 250         | 1.00         | 5.7           | 0.049                          | 0.063    | 1.21              | 59.5          | 0.1                | 0.20              |
|         | STM112   | STM111  |              |          | 0.00      | 0.16    | 11.1<br>11.9            | 98.6         | 43.9                        | 375         | 0.25         | 36.3          | 0.110                          | 0.094    | 0.79              | 87.7          | 0.8                | 0.50              |

**Iber Hazeldean Land Limited**  
**5734-5754 Hazeldean Road/24 Iber Road**  
**Storm Sewer Calculation Sheet**

|                   |             |         |       |       |       |       |      |       |       |     |      |      |       |       |      |        |     |       |
|-------------------|-------------|---------|-------|-------|-------|-------|------|-------|-------|-----|------|------|-------|-------|------|--------|-----|-------|
| A14               | CB20        | STM111  | 0.136 | 0.771 | 0.111 | 0.111 | 10.0 | 104.2 | 30.4  | 200 | 1.00 | 11.6 | 0.031 | 0.050 | 1.04 | 32.8   | 0.2 | 0.85  |
|                   |             |         |       |       |       |       | 10.2 |       |       |     |      |      |       |       |      |        |     |       |
| A13               | CB19        | STM111  | 0.125 | 0.84  | 0.10  | 0.10  | 10.0 | 104.2 | 30.3  | 200 | 1.00 | 19.4 | 0.031 | 0.050 | 1.04 | 32.8   | 0.3 | 0.92  |
|                   |             |         |       |       |       |       | 10.3 |       |       |     |      |      |       |       |      |        |     |       |
| A12               | CB18        | STM111  | 0.141 | 0.88  | 0.12  | 0.12  | 10.0 | 104.2 | 35.8  | 250 | 1.00 | 12.2 | 0.049 | 0.063 | 1.21 | 59.5   | 0.2 | 0.60  |
|                   |             |         |       |       |       |       | 10.2 |       |       |     |      |      |       |       |      |        |     |       |
| A11               | CB17        | STM111  | 0.071 | 0.85  | 0.06  | 0.06  | 10.0 | 104.2 | 17.5  | 200 | 1.00 | 19.4 | 0.031 | 0.050 | 1.04 | 32.8   | 0.3 | 0.53  |
|                   |             |         |       |       |       |       | 10.3 |       |       |     |      |      |       |       |      |        |     |       |
| A10               | CB16        | STM111  | 0.116 | 0.87  | 0.10  | 0.10  | 10.0 | 104.2 | 29.2  | 250 | 1.00 | 12.2 | 0.049 | 0.063 | 1.21 | 59.5   | 0.2 | 0.49  |
|                   |             |         |       |       |       |       | 10.2 |       |       |     |      |      |       |       |      |        |     |       |
| A9                | CB15        | STM111  | 0.128 | 0.86  | 0.11  | 0.11  | 10.0 | 104.2 | 31.8  | 200 | 1.00 | 19.3 | 0.031 | 0.050 | 1.04 | 32.8   | 0.3 | 0.97  |
|                   |             |         |       |       |       |       | 10.3 |       |       |     |      |      |       |       |      |        |     |       |
| A8                | CB14        | STM111  | 0.121 | 0.87  | 0.11  | 0.11  | 10.0 | 104.2 | 30.5  | 250 | 1.00 | 12.2 | 0.049 | 0.063 | 1.21 | 59.5   | 0.2 | 0.51  |
|                   |             |         |       |       |       |       | 10.2 |       |       |     |      |      |       |       |      |        |     |       |
| A7                | CB13        | STM111  | 0.058 | 0.81  | 0.05  | 0.05  | 10.0 | 104.2 | 13.7  | 250 | 1.00 | 12.3 | 0.049 | 0.063 | 1.21 | 59.5   | 0.2 | 0.23  |
|                   |             |         |       |       |       |       | 10.2 |       |       |     |      |      |       |       |      |        |     |       |
|                   | STM111      | STM104  |       |       | 0.00  | 0.92  | 11.9 | 95.2  | 242.6 | 600 | 0.25 | 88.8 | 0.283 | 0.150 | 1.08 | 307.0  | 1.4 | 0.79  |
|                   |             |         |       |       |       |       | 13.2 |       |       |     |      |      |       |       |      |        |     |       |
| A6                | C1CB11/72   | STM104  | 0.039 | 0.81  | 0.03  | 0.03  | 10.0 | 104.2 | 9.1   | 200 | 1.00 | 5.8  | 0.031 | 0.050 | 1.04 | 32.8   | 0.1 | 0.28  |
|                   |             |         |       |       |       |       | 10.1 |       |       |     |      |      |       |       |      |        |     |       |
|                   | STM104      | STM101B |       |       | 0.00  | 1.99  | 13.2 | 89.7  | 521.9 | 900 | 0.13 | 39.9 | 0.536 | 0.225 | 1.03 | 652.7  | 0.6 | 0.80  |
|                   |             |         |       |       |       |       | 13.9 |       |       |     |      |      |       |       |      |        |     |       |
| A5                | C1CB9/10    | STM102  | 0.072 | 0.73  | 0.05  | 0.05  | 10.0 | 104.2 | 15.2  | 200 | 1.00 | 6.2  | 0.031 | 0.050 | 1.04 | 32.8   | 0.1 | 0.48  |
|                   |             |         |       |       |       |       | 10.1 |       |       |     |      |      |       |       |      |        |     |       |
| A4                | C1CB6/7     | STM102  | 0.121 | 0.78  | 0.09  | 0.09  | 10.0 | 104.2 | 27.3  | 200 | 1.00 | 6.2  | 0.031 | 0.050 | 1.04 | 32.8   | 0.1 | 0.83  |
|                   |             |         |       |       |       |       | 10.1 |       |       |     |      |      |       |       |      |        |     |       |
|                   | STM102      | STM101B |       |       | 0.00  | 0.15  | 10.1 | 103.7 | 42.3  | 300 | 0.35 | 71.2 | 0.071 | 0.075 | 0.81 | 57.2   | 1.5 | 0.74  |
|                   |             |         |       |       |       |       | 11.6 |       |       |     |      |      |       |       |      |        |     |       |
| A2                | CB3/5       | STM101B | 0.036 | 0.79  | 0.03  | 0.03  | 10.0 | 104.2 | 8.3   | 200 | 1.00 | 2.1  | 0.031 | 0.050 | 1.04 | 32.8   | 0.0 | 0.25  |
|                   |             |         |       |       |       |       | 10.0 |       |       |     |      |      |       |       |      |        |     |       |
|                   | FUT. BLDG G | STM103  | 0.097 | 0.90  |       |       | 10.0 | 104.2 | 5.8   | 250 | 1.00 | 34.6 | 0.049 | 0.063 | 1.21 | 59.5   | 0.5 | 0.10  |
|                   |             |         |       |       |       |       | 10.5 |       |       |     |      |      |       |       |      |        |     |       |
| A3                | CBM/4       | STM103  | 0.248 | 0.87  | 0.22  | 0.22  | 10.0 | 104.2 | 62.6  | 300 | 0.50 | 26.9 | 0.071 | 0.075 | 0.97 | 68.4   | 0.5 | 0.92  |
|                   |             |         |       |       |       |       | 10.5 |       |       |     |      |      |       |       |      |        |     |       |
|                   | BLDG D      | STM103  | 0.066 | 0.90  |       |       | 10.0 | 104.2 | #REF! | 250 | 1.00 | 3.5  | 0.049 | 0.063 | 1.21 | 59.5   | 0.0 | #REF! |
|                   |             |         |       |       |       |       | 10.0 |       |       |     |      |      |       |       |      |        |     |       |
|                   | STM103      | STM101B |       |       | 0.00  | 0.22  | 10.5 | 101.7 | #REF! | 375 | 0.38 | 47.3 | 0.110 | 0.094 | 0.98 | 108.1  | 0.8 | #REF! |
|                   |             |         |       |       |       |       | 11.3 |       |       |     |      |      |       |       |      |        |     |       |
| A1                | C1CB12      | STM101B | 0.121 | 0.76  | 0.09  | 0.09  | 10.0 | 104.2 | 28.7  | 200 | 1.00 | 5.9  | 0.031 | 0.050 | 1.04 | 32.8   | 0.1 | 0.81  |
|                   |             |         |       |       |       |       | 10.1 |       |       |     |      |      |       |       |      |        |     |       |
|                   | STM101B     | STM101A |       |       | 0.00  | 2.48  | 13.9 | 87.3  | #REF! | 900 | 0.15 | 46.5 | 0.836 | 0.225 | 1.10 | 701.1  | 0.7 | #REF! |
|                   | STM101A     | EF 10   | 0.00  | 2.48  | 0.00  | 2.48  | 14.6 | 84.9  | #REF! | 900 | 0.40 | 2.8  | 0.836 | 0.225 | 1.80 | 1144.9 | 0.0 | #REF! |
|                   | EF 10       | STM100  | 0.00  | 2.48  | 0.00  | 2.48  | 14.6 | 84.8  | #REF! | 900 | 0.13 | 22.8 | 0.836 | 0.225 | 1.03 | 652.7  | 0.4 | #REF! |
|                   | STM100      | OUTLET  | 0.00  | 2.48  | 0.00  | 2.48  | 15.0 | 83.6  | #REF! | 675 | 1.00 | 2.3  | 0.358 | 0.169 | 2.35 | 840.6  | 0.0 | #REF! |
|                   |             |         |       |       |       |       | 15.0 |       |       |     |      |      |       |       |      |        |     |       |
| Controlled Flow** |             |         |       |       |       |       |      |       |       |     |      |      |       |       |      |        |     |       |
|                   | STM101B     | STM101A |       |       | 0.00  | 0.48  | 13.9 | 87.3  | #REF! | 900 | 0.15 | 46.5 | 0.836 | 0.225 | 1.10 | 701.1  | 0.7 | #REF! |
|                   | STM101A     | EF 10   | 0.00  | 0.48  | 0.00  | 0.48  | 14.6 | 84.9  | 191.7 | 675 | 0.40 | 2.8  | 0.358 | 0.169 | 1.49 | 531.6  | 0.0 | 0.36  |
|                   | EF 10       | STM100  | 0.00  | 0.48  | 0.00  | 0.48  | 14.6 | 84.8  | 191.7 | 675 | 0.13 | 22.8 | 0.358 | 0.169 | 0.83 | 303.1  | 0.4 | 0.85  |
|                   | STM100      | OUTLET  | 0.00  | 0.48  | 0.00  | 0.48  | 15.1 | 83.3  | 191.7 | 675 | 1.00 | 2.3  | 0.358 | 0.169 | 2.35 | 840.6  | 0.0 | 0.23  |
|                   |             |         |       |       |       |       | 15.1 |       |       |     |      |      |       |       |      |        |     |       |

\*\* The controlled 100-year release rate is used downstream of the orifice

**Note:**

1) There is a Stormceptor located between STM 101A and STM 100.

2) Flows from buildings are controlled based on the 5-year storm and included within Qtotal.



**Iber Hazeldean Land Limited**  
**Storm Sewer Calculation Sheet**  
**5734-5754 Hazeldean Road/24 Iber Road**

| AREA ID | 5-YEAR                      |                |            |           |         | 100-YEAR   |            |         |
|---------|-----------------------------|----------------|------------|-----------|---------|------------|------------|---------|
|         | TOTAL AREA(m <sup>2</sup> ) | TOTAL AREA(ha) | PERV(0.20) | IMP(0.90) | C-VALUE | PERV(0.25) | IMP(1.125) | C-VALUE |
| A1      | 1206.31                     | 0.121          | 234.16     | 972.15    | 0.76    | 135.60     | 1070.71    | 1.00    |
| A2      | 364.86                      | 0.036          | 58.03      | 306.82    | 0.79    | 58.03      | 306.82     | 1.00    |
| A3      | 2480.31                     | 0.248          | 97.38      | 2382.93   | 0.87    | 165.75     | 2314.56    | 1.00    |
| A4      | 1211.59                     | 0.121          | 210.77     | 1000.82   | 0.78    | 211.09     | 1000.50    | 1.00    |
| A5      | 722.59                      | 0.072          | 177.75     | 544.83    | 0.73    | 177.75     | 544.83     | 1.00    |
| A6      | 386.91                      | 0.039          | 48.59      | 338.32    | 0.81    | 48.59      | 338.32     | 1.00    |
| A7      | 582.93                      | 0.058          | 72.02      | 510.91    | 0.81    | 72.02      | 510.91     | 1.00    |
| A8      | 1206.34                     | 0.121          | 44.70      | 1161.64   | 0.87    | 44.70      | 1161.64    | 1.00    |
| A9      | 1281.89                     | 0.128          | 80.67      | 1201.22   | 0.86    | 64.59      | 1217.29    | 1.00    |
| A10     | 1159.65                     | 0.116          | 49.12      | 1110.53   | 0.87    | 49.12      | 1110.53    | 1.00    |
| A11     | 705.91                      | 0.071          | 46.10      | 659.81    | 0.85    | 54.88      | 651.03     | 1.00    |
| A12     | 1412.76                     | 0.141          | 48.18      | 1364.58   | 0.88    | 48.18      | 1364.58    | 1.00    |
| A13     | 1250.25                     | 0.125          | 113.18     | 1137.07   | 0.84    | 113.18     | 1137.07    | 1.00    |
| A14     | 1357.19                     | 0.136          | 243.64     | 1113.55   | 0.77    | 243.64     | 1113.55    | 1.00    |
| A15     | 520.38                      | 0.052          | 77.50      | 442.88    | 0.80    | 77.50      | 442.88     | 1.00    |
| A16     | 742.26                      | 0.074          | 159.76     | 582.51    | 0.75    | 159.76     | 582.51     | 1.00    |
| A17     | 702.69                      | 0.070          | 0.00       | 702.69    | 0.90    | 0.00       | 702.69     | 1.00    |
| A18     | 202.61                      | 0.020          | 190.84     | 11.77     | 0.24    | 190.84     | 11.77      | 1.00    |
| A19     | 2512.48                     | 0.251          | 343.54     | 2168.95   | 0.80    | 343.54     | 2168.95    | 1.00    |
| A20     | 1109.91                     | 0.111          | 150.03     | 959.88    | 0.81    | 150.03     | 959.88     | 1.00    |
| A21     | 727.30                      | 0.073          | 27.94      | 699.36    | 0.87    | 27.94      | 699.36     | 1.00    |
| A22     | 545.42                      | 0.055          | 27.94      | 517.48    | 0.86    | 27.94      | 517.48     | 1.00    |
| A23     | 367.58                      | 0.037          | 23.25      | 344.34    | 0.86    | 23.25      | 344.34     | 1.00    |
| A24     | 280.15                      | 0.028          | 23.25      | 256.91    | 0.84    | 23.25      | 256.91     | 1.00    |
| A25     | 1655.33                     | 0.166          | 226.44     | 1428.89   | 0.80    | 226.44     | 1428.89    | 1.00    |
| A26     | 523.77                      | 0.052          | 29.28      | 494.49    | 0.86    | 29.28      | 494.49     | 1.00    |
| A27     | 251.47                      | 0.025          | 70.75      | 180.72    | 0.70    | 70.75      | 180.72     | 1.00    |
| A28     | 907.23                      | 0.091          | 91.75      | 815.48    | 0.83    | 91.75      | 815.48     | 1.00    |
| A29     | 415.98                      | 0.042          | 30.45      | 385.52    | 0.85    | 30.45      | 385.52     | 1.00    |
| A30     | 549.74                      | 0.055          | 120.06     | 429.69    | 0.75    | 120.06     | 429.69     | 1.00    |
| A31     | 459.11                      | 0.046          | 33.81      | 425.29    | 0.85    | 33.81      | 425.29     | 1.00    |
| A32     | 620.12                      | 0.062          | 311.01     | 309.11    | 0.55    | 311.01     | 309.11     | 1.00    |

|         |         |       |      |         |      |      |         |      |
|---------|---------|-------|------|---------|------|------|---------|------|
| BLDG A  | 1895.82 | 0.190 | 0.00 | 1895.82 | 0.90 | 0.00 | 1895.82 | 1.00 |
| BLDG B  | 1404.15 | 0.140 | 0.00 | 1404.15 | 0.90 | 0.00 | 1404.15 | 1.00 |
| BLDG BB | 409.82  | 0.041 | 0.00 | 409.82  | 0.90 | 0.00 | 409.82  | 1.00 |
| BLDG C  | 2884.52 | 0.288 | 0.00 | 2884.52 | 0.90 | 0.00 | 2884.52 | 1.00 |
| BLDG D  | 661.80  | 0.066 | 0.00 | 661.80  | 0.90 | 0.00 | 661.80  | 1.00 |
| BLDG G  | 970.30  | 0.097 | 0.00 | 970.30  | 0.90 | 0.00 | 970.30  | 1.00 |

|    |         |       |         |        |      |         |        |      |
|----|---------|-------|---------|--------|------|---------|--------|------|
| U1 | 6790.56 | 0.679 | 6427.82 | 362.74 | 0.24 | 6419.46 | 371.10 | 1.00 |
| U2 | 786.12  | 0.079 | 353.58  | 432.54 | 0.59 | 353.58  | 432.54 | 1.00 |
| U3 | 154.46  | 0.015 | 0.00    | 154.46 | 0.90 | 0.00    | 154.46 | 1.00 |

|                 |          |       |         |          |      |         |          |      |
|-----------------|----------|-------|---------|----------|------|---------|----------|------|
| AREA A          | 28423.02 | 2.842 | 3461.86 | 24961.16 | 0.81 | 3424.70 | 24998.32 | 1.00 |
| AREA A + BLDG D | 29084.82 | 2.908 | 3461.86 | 25622.96 | 0.82 | 3424.70 | 25660.12 | 1.00 |
| AREA A+BLDG     | 36649.42 | 3.665 | 3461.86 | 33187.56 | 0.83 | 3424.70 | 33224.72 | 1.00 |

|       |          |       |          |          |      |          |          |      |
|-------|----------|-------|----------|----------|------|----------|----------|------|
| TOTAL | 44380.56 | 4.438 | 10243.26 | 34137.30 | 0.74 | 10197.74 | 34182.82 | 1.00 |
|-------|----------|-------|----------|----------|------|----------|----------|------|

**PONDING AREAS**

| Elevation | Area(m <sup>2</sup> ) |
|-----------|-----------------------|
| 103.30    | 137.59                |
| 103.35    | 745.15                |
| 103.40    | 1953.54               |
| 103.55    | 8389.86               |



Parameters

Units: Metric

Storage Volume: 81 Cu m

Chamber Selection: M-6

Header Row Position: Left

Fill Over Embedment Stone: 300 mm

Controlled By: width 9 m

Embedment Stone mm:

Over: 150 Under: 12 Porosity: 0.4

Min 150mm over and under

Double Stacked


Double Stacked?: No

Stone Between: 304.80

Note: After making an input change you must hit calculate to update the Field Diagram and Project Results.

\* The image generation will not save if using MicroSoft Edge


Project Results



|                                    |                                              |
|------------------------------------|----------------------------------------------|
| 1                                  | Total Cover Over Chambers: 451 mm            |
| 2                                  | Height Of Chamber: 445 mm                    |
| 3                                  | Embedment Stone Under Chambers: 13 mm        |
| 4                                  | Volume of Embedment Stone Required: 95 Cu. m |
| 5                                  | Volume of Fill Material Required: 69 Cu. m   |
| Total Storage Provided: 82 Cu. m   |                                              |
| Type Of Chambers: M-6              |                                              |
| # Of Chambers Required: 274        |                                              |
| # Of End Caps Required: 18         |                                              |
| Required Bed Size: 230 Sq. m       |                                              |
| Volume of Excavation: 209 Cu. m    |                                              |
| * Area of Filter Fabric: 273 Sq. m |                                              |
| # of Chambers Long: 33             |                                              |
| # of rows: 8                       |                                              |
| Actual Trench Length: 26.93 m      |                                              |
| Actual Trench Width: 8.51 m        |                                              |

\* Filter Fabric quantity for Fabric on Top and Sides of System Only, does not include overlap







| M-6 CHAMBER SPECS                                      |                                                    |
|--------------------------------------------------------|----------------------------------------------------|
| NOMINAL DIMENSIONS<br>(LAYOUT LENGTH X WIDTH X HEIGHT) | 29.58" X 33.61" X 17.5"<br>(751mm X 854mm X 445mm) |
| BARE CHAMBER STORAGE                                   | 5.6 CUBIC FEET<br>(0.159 CUBIC METERS)             |
| *MIN INSTALLED STORAGE                                 | 11.36 CUBIC FEET<br>(0.322 CUBIC METERS)           |
| CHAMBER WEIGHT                                         | 14 lbs<br>(6.35 kg)                                |
| STORAGE PER LINEAR FOOT<br>WITHOUT STONE               | 2.27 CUBIC FEET<br>(0.064 CUBIC METERS)            |
| STORAGE PER LINEAR FOOT<br>WITH STONE                  | 4.61 CUBIC FEET<br>(0.131 CUBIC METERS)            |

\*ASSUMING A MIN OF 6" (152mm) STONE ABOVE AND BELOW AND 6" (152mm) BETWEEN ROWS WITH 40% STONE POROSITY (DOES NOT INCLUDE 12" (305mm) PERIMETER STONE VOLUME)

NOTE: M-6 CHAMBER DETAILS TESTED AND RATED FOR H-30 LOAD CONDITIONS WITH 18" (457mm) OF COVER AND NO PAVEMENT.




ø8" (200mm)  
MAX O.D. FOR  
SIDE CONNECTION



3.60" (91mm)  
2x4 SPACER SLOT TO HELP  
KEEP CHAMBER ROWS STRAIGHT

ø12" (300mm)  
MAX O.D. FOR  
TOP CONNECTION



CONCEPTUAL PLAN DISCLAIMER  
THIS GENERIC DETAIL DOES NOT ENCOMPASS THE SIZING, FIT, AND APPLICABILITY OF THE TRITON CHAMBER SYSTEM FOR THIS SPECIFIC PROJECT. IT IS THE ULTIMATE RESPONSIBILITY OF THE DESIGN ENGINEER TO ASSURE THAT THE STORMWATER SYSTEM DESIGN IS IN FULL COMPLIANCE WITH ALL APPLICABLE LAWS AND REGULATIONS. TRITON PRODUCTS MUST BE DESIGNED AND INSTALLED IN ACCORDANCE WITH TRITON'S MINIMUM REQUIREMENTS. TRITON STORMWATER SOLUTIONS DOES NOT APPROVE PLANS, SIZING, OR SYSTEM DESIGNS. THE DESIGN ENGINEER IS RESPONSIBLE FOR ALL DESIGN DECISIONS.




7600 EAST GRAND RIVER, STE. 195  
BRIGHTON, MI 48114  
PHONE: (810) 222-7652 • FAX: (810) 222-1769  
WWW.TRITONSWS.COM

## M-6 CHAMBER DETAIL


TRITON - STANDARD DETAILS

REVISED:  
02-26-16 JWM



| M-6 END CAP SPECS                                                                                                                                             |                                                    |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------|
| NOMINAL DIMENSIONS<br>(LAYOUT LENGTH X WIDTH X HEIGHT)                                                                                                        | 7.18" X 30.60" X 17.03"<br>(183mm X 777mm X 432mm) |
| BARE END CAP STORAGE                                                                                                                                          | 0.533 CUBIC FEET<br>(0.015 CUBIC METERS)           |
| *MIN INSTALLED STORAGE                                                                                                                                        | 2.26 CUBIC FEET<br>(0.064 CUBIC METERS)            |
| *ASSUMING A MIN OF 6" (152mm) STONE ABOVE AND BELOW AND 6" (152mm) BETWEEN ROWS WITH 40% STONE POROSITY (DOES NOT INCLUDE 12" (305mm) PERIMETER STONE VOLUME) |                                                    |

ø14" (350mm) MAX O.D.  
 FOR END CONNECTION  
 ALL PIPE CONNECTIONS  
 MUST BE INSTALLED ALONG  
 CHAMBER CAP CENTERLINE.



THE END CAP FITS UP INSIDE THE LAST CONNECTING RIBS OF THE M-6 CHAMBER

**CONCEPTUAL PLAN DISCLAIMER**  
 THIS GENERIC DETAIL DOES NOT ENCOMPASS THE SIZING, FIT, AND APPLICABILITY OF THE TRITON CHAMBER SYSTEM FOR THIS SPECIFIC PROJECT. IT IS THE ULTIMATE RESPONSIBILITY OF THE DESIGN ENGINEER TO ASSURE THAT THE STORMWATER SYSTEM DESIGN IS IN FULL COMPLIANCE WITH ALL APPLICABLE LAWS AND REGULATIONS. TRITON PRODUCTS MUST BE DESIGNED AND INSTALLED IN ACCORDANCE WITH TRITON'S MINIMUM REQUIREMENTS. TRITON STORMWATER SOLUTIONS DOES NOT APPROVE PLANS, SIZING, OR SYSTEM DESIGNS. THE DESIGN ENGINEER IS RESPONSIBLE FOR ALL DESIGN DECISIONS.

7600 EAST GRAND RIVER, STE. 195  
 BRIGHTON, MI 48114  
 PHONE: (810) 222-7652 • FAX: (810) 222-1769  
 WWW.TRITONSWS.COM

# M-6 CHAMBER END CAP DETAIL

TRITON - STANDARD DETAILS

REVISED:  
 02-26-16 JWM

# TRITON M-6 PRODUCT SPECIFICATIONS

1.0 General

1.1 Triton chambers are designed to control stormwater runoff. As a subsurface retention or detention system, Triton chambers retain and allow effective infiltration of water into the soil. As a subsurface detention system, Triton chambers detain and allow for the metered flow of water to an outfall.

2.0 Chamber Parameters

2.1 The chamber shall be injection compression molded of a structural grade 1010 green soy resin composite to be inherently resistant to environmental stress cracking (ESCR), creep, and to maintain proper stiffness through temperature ranges of -40 degrees Fahrenheit to 180 degrees Fahrenheit (-40 degrees Celsius to 82.2 degrees Celsius).

2.2 The material property for the chamber and end cap must meet or exceed the following:

Tensile Strength- Ultimate: 21,755 PSI (150 Mpa)

Tensile Strength-Yield: 17,404 PSI (120 Mpa)

Tensile Modulus: 1,750-2,240 KSI (12,066 Mpa - 15,444 Mpa)

Flex Modulus: 1,600 KSI (11,032 Mpa)

Flex Yield Strength: 33,100 PSI (228 Mpa)

Compressive Strength: 30,457 PSI (210 Mpa)

Shear Strength: 11,500 PSI (79 Mpa)

2.3 The nominal chamber dimensions of the Triton M-6 shall be 17.5 inches tall (445 millimeters), 33.61 inches wide (854 millimeters) and 31.5 inches long (800 millimeters). Lay-up length is 29.58 inches (751 millimeters).

2.4 The chamber shall have an elliptical curved section profile.

2.5 The chamber shall be open-bottomed.

2.6 The chamber shall incorporate an overlapping corrugation joint system to allow chamber rows to be constructed.

2.7 The nominal storage volume of a Triton M-6 chamber shall be 11.36 cubic feet (0.322 cubic meters) per chamber when installed per Triton's typical details. This equates to 1.40 cubic feet (0.040 cubic meters) of storage per square foot of bed. This does not include perimeter stone.

2.8 The chamber shall have both of its ends open to allow for unimpeded hydraulic flows and visual inspections down a row's entire length.

2.9 The chamber shall have five corrugations to achieve strengths defined above.

2.10 The chamber shall have five circular and elliptical, indented and raised, surfaces on the top to the chamber for a maximum of 12 inch (300 millimeter) diameter optional top feed inlets, inspection ports and/or clean-out access ports.

2.11 The chamber side shall be capable of accepting pipe O.D. up to 8 inches (200 millimeters).

2.12 The chamber shall be analyzed, designed and field tested using AASHTO LRFD bridge design specifications 1. Design live load shall meet or exceed the AASHTO HS30 or a rear axle load of 48,000 pounds (21,772.4 kg). Design shall consider earth and live loads without pavement as appropriate for the minimum 18 inches (457 millimeters) of total cover to a maximum total cover of 50 feet (15.24 meters).

2.13 The chamber shall be manufactured in an ISO/TS16949:2002 and ISO 14001:2004 certified facility

2.14 The service life of the product is over 60 years under a constant sustained load of 10,000 PSI (68.95 Mpa) which is equal to the H-20 loading condition. Under typical loading conditions the Chamber and End Cap has a useful life span of 120 years from date of when manufactured.

3.0 End Cap Parameters

3.1 The end cap shall be Injection Compression molded of 1010 green soy resin to be inherently resistant to environmental stress cracking (ESCR), creep and to maintain proper stiffness through temperature ranges of -40 degrees Fahrenheit to 180 degrees Fahrenheit (-40 degrees Celsius to 82.2 degrees Celsius).

3.2 The end cap shall be designed to fit inside the last corrugation of a chamber, which allows the capping of each end of the chamber row.

3.3 The end cap shall have 7 different diameter connection guides across the front face of the bull nosed surface. The maximum diameter that the end cap can accept is 14 inches (350 millimeters) PS46, ASTM F679 PVC pipe.

3.4 The end cap shall have excess structural adequacies to allow cutting an office of any size at any invert elevation.

3.5 The primary face of an end cap shall have five corrugations and be angled outward to resist horizontal loads generated near the edges of beds.

3.6 The end cap shall be manufactured in an ISO/TS16949:2002 and ISO 14001:2004 certified facility.

3.7 The service life of the product to be over 60 years under a sustained load of 10,000 PSI (68.95 Mpa) which is equal to the H-20 loading condition.

3.8 The nominal storage volume of a Triton M-6 end cap shall be 2.26 cubic feet (0.064 cubic meters) per end cap when installed per triton's typical details. This equates to 1.15 cubic feet (0.032 cubic meters) of storage per square foot of bed.

4.0 Installation

4.1 Installation shall be in accordance with the latest Triton Installation manual that can be downloaded from the Triton website: [www.tritonsws.com/support/downloads](http://www.tritonsws.com/support/downloads)

CONCEPTUAL PLAN DISCLAIMER

THIS GENERIC DETAIL DOES NOT ENCOMPASS THE SIZING, FIT, AND APPLICABILITY OF THE TRITON CHAMBER SYSTEM FOR THIS SPECIFIC PROJECT. IT IS THE ULTIMATE RESPONSIBILITY OF THE DESIGN ENGINEER TO ASSURE THAT THE STORMWATER SYSTEM DESIGN IS IN FULL COMPLIANCE WITH ALL APPLICABLE LAWS AND REGULATIONS. TRITON PRODUCTS MUST BE DESIGNED AND INSTALLED IN ACCORDANCE WITH TRITON'S MINIMUM REQUIREMENTS. TRITON STORMWATER SOLUTIONS DOES NOT APPROVE PLANS, SIZING, OR SYSTEM DESIGNS. THE DESIGN ENGINEER IS RESPONSIBLE FOR ALL DESIGN DECISIONS.

7600 EAST GRAND RIVER, STE.195

BRIGHTON, MI 48114

PHONE: (810) 222-7652 • FAX: (810) 222-1769

[WWW.TRITONSWWS.COM](http://WWW.TRITONSWWS.COM)

## M-6 PRODUCT SPECIFICATIONS

### TRITON - STANDARD DETAILS

REVISED:

03-02-16 JWM





---

---

***DRAWINGS / FIGURES***

---

---















[illegible]


|                                                                                         | REQUIRED                                                                 | PROVIDED                     |
|-----------------------------------------------------------------------------------------|--------------------------------------------------------------------------|------------------------------|
|                                                                                         | <b>II</b>                                                                | <b>II</b>                    |
| PERMITTED USE (AMONG OTHERS)                                                            | DRIVE-THROUGH FACILITY;<br>ANY VEHICLE SHOP; ANY SERVICE, E.G., CARWASH. | ALL PERMITTED USES           |
| MIN. LOT AREA                                                                           | 1000 SQ.M.                                                               | 44,935 SQ.M.                 |
| MIN. LOT WIDTH                                                                          | NO MIN.                                                                  | MULTIPLE WIDTHS EXCEEDING 1m |
| MIN. FRONT & CORNER YARD SETBACK                                                        | 3m                                                                       | 3m                           |
| MIN. REAR YARD SETBACK                                                                  | 3m                                                                       | 10m                          |
| MIN. INTERIOR SETBACK                                                                   | 3m                                                                       | 3m                           |
| MIN. OR 30% OF LOT WIDTH N/A                                                            | N/A                                                                      | N/A                          |
| MIN. DRIVEWAY WIDTH<br>LINE MUST BE OCCUPIED BY BUILDING WALLS WHEN LOT IS 40M OR WIDER | N/A                                                                      | N/A                          |
| MAX. BUILDING HEIGHT                                                                    | 22m                                                                      | 6.3m                         |
| MAX F.S.I.                                                                              | 2                                                                        | 1.635/271HS = 0.015          |
| MIN. WIDTH LANDSCAPE AREAS                                                              | 3m WHEN ABUTTING STREET; OTHERWISE 6.1m.                                 |                              |
| ACCESS DRIVE & PARKING AISLE (MIN. WIDTH)                                               | 6.1m                                                                     | 6.1m                         |
| PARKING SPACE - MIN. WIDTH X MIN. LENGTH                                                | 5.2m X 2.6m                                                              | 5.2m X 2.6m                  |
| MIN. BARRIER FREE PARKING                                                               | 2 SPACES                                                                 | 2 BARRIER FREE PARKING SPOTS |
| BICYCLE PARKING                                                                         | 1/250 SQ.M. = 44                                                         | 64 BIKE PARKING SPOTS        |

**Hobin Architecture  
Incorporated**  
65 Parlin Street  
Ottawa, Ontario  
Canada K1S 3K7  
T: 613 248-1200  
F: 613 245-2005  
E: mail@hobinarc.com  
**hobinarc.com**

PROJECT/LOCATION:  
HUNTINGTON PROPERTIES

DRAWING TITLE:  
**SITE PLAN**

|           |            |        |
|-----------|------------|--------|
| DRAWN BY: | DATE:      | SCALE: |
| SL        | 12/07/2017 | 1:500  |

[illegible]

It is the responsibility of the appropriate contractor to check and verify all dimensions on site and report all errors and/or omissions to the architect.

All contractors must comply with all pertinent codes and by-laws.

Do not scale drawings.

This drawing may not be used for construction until signed.

Copyright reserved.

[illegible]







[illegible]

It is the responsibility of the appropriate contractor to check and verify all dimensions on site and report all errors and/or omissions to the architect.

All contractors must comply with all pertinent codes and by-laws.

Do not scale drawings.

This drawing may not be used for construction until signed.

Copyright reserved.




**Hobin Architecture  
Incorporated**  
23 Pimlico Street  
Ottawa, Ontario  
Canada K1S 3K7  
T: 613-235-2000  
F: 613-235-2005  
E: mail@hobinarc.com  
**hobinarc.com**

PROJECT/LOCATION:  
HUNTINGTON PROPERTIES  
5754 HAZELDEAN RD.

DRAWING TITLE:  
IL ZONE  
SITE PLAN

|           |            |        |
|-----------|------------|--------|
| DRAWN BY: | DATE:      | SCALE: |
| SL        | 08/29/2019 | 1:250  |



| PERMITTED USE (AMONG OTHERS)                                                          | REQUIRED                                | IL                            | PROVIDED |
|---------------------------------------------------------------------------------------|-----------------------------------------|-------------------------------|----------|
| DRIVE-THROUGH FACILITY, AMBULANCE SHOP, AND VEHICLE EGT.                              |                                         | IL                            |          |
| ALL PERMITTED USES                                                                    |                                         |                               |          |
| MIN. LOT AREA                                                                         | 1,000 SQ.M.                             | 44,395 SQ.M.                  |          |
| MIN. LOT WIDTH                                                                        | NO MIN.                                 | MULTIPLE WIDTHS EXCEEDING 1m. |          |
| MIN. FRONT & CORNER YARD SETBACK                                                      | 3m                                      | 3m                            |          |
| MIN. REAR YARD SETBACK                                                                | 3m                                      | 10m                           |          |
| MIN. INTERIOR SETBACK                                                                 | 3m                                      | 3m                            |          |
| MIN. SIDE SETBACK LOT WIDTH N/A                                                       |                                         | N/A                           |          |
| MIN. 5M SETBACK LOT WIDTH N/A                                                         |                                         |                               |          |
| NO FRONT OR REAR LOT LINE MUST BE OCCUPIED BY BUILDING WALLS WHEN LOT IS 40M OR WIDER |                                         |                               |          |
| MAX. BUILDING HEIGHT                                                                  | 22m                                     | 6.3m                          |          |
| MAX F.S.I.                                                                            | 2                                       | 1.635/21THS = 0.0715          |          |
| MIN. WIDTH LANDSCAPE AREAS                                                            | 3m WHEN ABUTTING STREET; OTHERWISE 6.7m |                               |          |
| ACCESS DRIVE & PARKING AISLE (MIN. WIDTH)                                             | 6.7m                                    | 6.7m                          |          |
| PARKING SPACE - MIN. WIDTH X MIN. LENGTH                                              | 5.2m X 2.6m                             | 5.2m X 2.6m                   |          |
| MIN. BARRIER FREE PARKING                                                             | 2 SPACES                                | 2 BARRIER FREE PARKING SPOTS  |          |
| BIKE/PARKING                                                                          | 1/250 SQ.M. = 44                        | 64 BIKE PARKING SPOTS         |          |



