



Manotick Tree

MOVERS INC.

Serving Ottawa Since 1991

1966 Carsonby Road West,
North Gower ON K0A 2T0

Phone: (613) 489-1116

Fax: (613) 489-1117

Email: info@manoticktree.com

www.manoticktree.com

• Pruning & Removal • Stump Grinding • Tree Sales • Tree Relocation
(FULLY INSURED)

Tree Conservation Report

CONTACT INFORMATION

Name: Colliers Project Leaders	Phone: 343-997-1134
Site Address: Algonquin College 1385 Woodroffe Ave, Ottawa ON	Email Address: gretta.gitare@colliersprojectleaders.com

TREE INFORMATION

Tree Species:

- A. Crabapple
- B. Crabapple
- C. Crabapple
- D. Lilac
- E. Lilac
- F. Maple
- G. Lilac
- H. Lilac
- I. Lilac
- J. Lilac
- K. Lilac
- L. Lilac
- M. Lilac
- N. Lilac
- O. White Spruce
- P. Austrian Pine
- Q. Austrian Pine
- R. White Spruce
- S. Austrian Pine
- T. White Spruce
- U. Austrian Pine
- V. White Spruce
- W. Austrian Pine
- X. Austrian Pine
- Y. White Spruce
- Z. White Spruce
- AA. White Spruce
- BB. White Spruce
- CC. White Spruce
- DD. White Spruce
- EE. White Spruce

FF. Lilac
GG. Lilac
HH. Lilac
YY. White Spruce

Tree Diameter (in centimeters, at 1.2 meters from the ground):

A. 28cm
B. 38cm
C. 38cm
D. 7cm
E. 7cm
F. 11cm
G. 11cm
H. 11cm
I. 11cm
J. 11cm
K. 11cm
L. 13cm
M. 11cm
N. 13cm
O. 40cm
P. 15cm
Q. 20cm
R. 30cm
S. 20cm
T. 35cm
U. 25cm
V. 25cm
W. 25cm
X. 20cm
Y. 30cm
Z. 25cm
AA. 30cm
BB. 35cm
CC. 35cm
DD. 30cm
EE. 40cm
FF. 8cm
GG. 11cm
HH. 11cm
YY. 32cm

Tree Location on Property (description):

A-C – Along parking at the front of Building A
D-E – Along parking lot at Building E
F-G – South side of building S
H-N & FF – Parking Lot 9 east in islands
GG-HH – North of parking lot 9 in island
O-EE & YY – Parking Lot 9 West - North side along north access road

Health:

A-C – Fair health/ poor structure - Remove
D-E Fair health/ poor structure – Remove
F-G – Dead and poor health – Poor structure - Remove
H-N & FF – Fair to Poor health – Fair to poor structure – Remove
GG-HH – Fair health – fair structure - Remove
O-EE & YY – Fair health, fair structure - Remove

Impact of Development:

All of these trees are being removed for various property improvement projects. Remaining trees not listed are to be transplanted into more suitable areas. Trees must be moved before construction begins.

Protection Measures:

Erect a fence at the remaining critical root zone (CRZ) of trees, do not place any material or equipment within the CRZ of the tree, do not attach any signs, notices or posters to any tree, do not raise or lower the existing grade within the CRZ without approval, Tunnel or bore when digging within the CRZ of a tree, ensure that exhaust fumes from all equipment are NOT directed towards any tree's canopy.

Post Construction Measures:

Aerate and fertilize the retained trees if impacted by construction.
Suggest prune the retained trees for future health and longevity.

ARBORIST INFORMATION

Arborist Name: Fred Stevens	ISA Number: ON-0320A
Phone Number: 613-229-6653	<i>x Fred Stevens</i>