david schaeffer engineering ltd

120 Iber Road, Suite 103
Ottawa, Ontario K2S 1E9
Tel. (613) 836-0856
Fax (613) 836-7183
www.DSEL.ca

FUNCTIONAL SERVICING AND STORMWATER MANAGEMENT REPORT

FOR

MATTAMY HOMES
WATERIDGE VILLAGE – BLOCK 15
245 SQUADRON CRESCENT

CITY OF OTTAWA
FILE #: D07-12-19-0020

PROJECT NO.: 17-946

DECEMBER 2019 – REV. 6
© DSEL

FUNCTIONAL SERVICING AND STORMWATER MANAGEMENT REPORT
FOR
MATTAMY HOMES
WATERIDGE VILLAGE – BLOCK 15
245 squadron crescent

DECEMBER 2019 – REV. 6

CITY OF OTTAWA

PROJECT NO.: 17-946

TABLE OF CONTENTS

1.0 INTRODUCTION 1
1.1 Existing Conditions 2
1.2 Required Permits / Approvals 4
1.3 Pre-consultation 4
2.0 GUIDELINES, PREVIOUS STUDIES, AND REPORTS 5
2.1 Existing Studies, Guidelines, and Reports 5
3.0 WATER SUPPLY SERVICING 8
3.1 Existing Water Supply Services 8
3.2 Water Supply Servicing Design 8
3.3 Watermain Modelling 11
3.4 Water Supply Conclusion 12
4.0 WASTEWATER SERVICING 13
4.1 Existing Wastewater Services 13
4.2 Wastewater Design 13
4.3 Wastewater Servicing Conclusions 15
5.0 STORMWATER MANAGEMENT 16
5.1 Existing Stormwater Services 16
5.2 Post-development Stormwater Management Target 16
5.3 Model Summary 16

© DSEL

5.4 Proposed Stormwater Management System 17
5.5 Hydraulic Grade Line (HGL) Analysis & Overland Flow Depth 19
5.6 Low Impact Development (LID) Practices 21
5.7 Stormwater Servicing Conclusions 22

6.0 GEOTECHNICAL CONSIDERATIONS 23

7.0 EROSION AND SEDIMENT CONTROL 25

8.0 CONCLUSION AND RECOMMENDATIONS 26

FIGURES

Figure 1 Site Location

TABLES

Table 1 Summary of Water Demand per *Design Brief Phase 1B*
Table 2 Water Supply Design Criteria
Table 3 Proposed Water Demand and Boundary Conditions Proposed Conditions
Table 4 Estimated Fire Flow Demand
Table 5 Model Simulation Output Summary
Table 6 Wastewater Flow per Design Brief Phase 1B – Total Site Area
Table 7 Wastewater Design Criteria
Table 8 Summary of Total Estimated Peak Wastewater Flow
Table 9 HGL 100-Year and 100-Year + 20% Storms vs Underside of Footing
Table 10 Overland Flow 100-Year and 100-Year + 20% Storms vs Surrounding House Grade

APPENDICES

Appendix A Pre-consultation Notes
Geotechnical Memos
R-Plan
Appendix B Water Supply
Appendix C Wastewater Collection
Appendix D Stormwater Management
Drawings / Figures Site Plan
Plan 4m-1581
General Plan of Services, Drawing No. 100D, Project No. 38298, prepared by IBI Group, dated June 15, 2018.

© DSEL

General Plan of Services, Drawing No. 100E, Project No. 38298, prepared by IBI Group, dated April 16, 2018.
Squadron Crescent Moses Tennisco Street (STA. 0+400 to STA. 0+700), Drawing No. 135, Project No. 38298, prepared by IBI Group, dated June 15, 2018.
Grading Plan, Drawing No. 210, Project No. 38298, prepared by IBI Group, dated February 2, 2018.
Grading Plan, Drawing No. 211, Project No. 38298, prepared by IBI Group, dated February 2, 2018.
Grading Plan, Drawing No. 212, Project No. 38298, prepared by IBI Group, dated February 2, 2018.
Grading Plan, Drawing No. 213, Project No. 38298, prepared by IBI Group, dated November 13, 2017.
Grading Plan, Drawing No. 214, Project No. 38298, prepared by IBI Group, dated August 2, 2017.
Grading Plan, Drawing No. 215, Project No. 38298, prepared by IBI Group, dated December 5, 2017.
Ponding Plan, Drawing No. 751, Project No. 38298, prepared by IBI Group, dated June 16, 2018.

© DSEL

FUNCTIONAL SERVICING AND STORMWATER MANAGEMENT REPORT FOR MATTAMY HOMES WATERIDGE VILLAGE – BLOCK 15

245 squadron crescent

DECEMBER 2019 – REV. 6

CITY OF OTTAWA

PROJECT NO.: 17-946

1.0 INTRODUCTION

David Schaeffer Engineering Limited (DSEL) has been retained by Mattamy Homes to prepare a Functional Servicing and Stormwater Management report to amend the previously approved Site Plan Control Application (SPC), dated March 2018, for Block 15 of Wateridge Village at 245 Squadron Crescent. Subject lands are within the former CFB Rockcliffe lands, which are currently under re-development by the Canada Lands Company.

The subject property is located within the City of Ottawa urban boundary, in the Rideau-Rockcliffe Ward. The proposed development lies within the Wateridge Village at Rockcliffe subdivision Phase 1B, as illustrated in ***Figure 1***, below. The subject property is encompassed by Hemlock Road, Mikinak Road and Moses Tennisco Street, all of which are currently under construction. Comprised of a single parcel, the subject property measures approximately ***1.96 ha*** and is zoned Residential Fourth Density Zone (R4Y[2311]). A copy of the registered 4M-Plan is included in ***Drawings/ Figures***.

© DSEL




Image taken from Design Brief Wateridge Village at Rockcliffe Phase 1B, prepared by IBI Group, dated: June 16, 2017.

Figure 1: Site Location

The proposed development by Mattamy Homes involves the construction of 124 Stacked Townhomes (Blocks 1-7 per the Site Plan included in ***Drawings/Figures***) and 68 Back-to-Back Townhomes (Blocks 8-14 per the Site Plan included in ***Drawings/Figures***). The Back-to-Back Townhomes are proposed to be slab-on-grade units and the Stacked Townhomes are proposed to have basements. Of the Back-to-Back Townhomes, 34 units are proposed to be freehold units and to have laneway access directly to Squadron Crescent. These 34 units as shown in the Site Plan will require Part Lot Control. The previously approved ***FSR-Block15,*** prepared by DSEL and dated March 2018, contemplated 124 rear lane townhomes, whereas, the amendment proposes an additional 68 townhouse style units for a proposed total of 192 townhomes.

The objective of this report is to provide sufficient detail with respect to the availability of site services to support the amended application for Site Plan Control.

1.1 Existing Conditions

The construction of the surrounding road network and underground services was completed in 2018, while the existing lands encompassing the subject property remain vacant. Historically, the lands were part of the Canadian Forces Base Rockcliffe (CFB

© DSEL

Rockcliffe). The development of the lands, previously part of CFB Rockcliffe, were divided into phases. Phase 1 of the development, designed by IBI Group is completed and Phase 2 is currently under construction.

A ***Geotechnical Investigation*** was completed by Paterson Group Inc. updated in June, 2019. Per the ***Geotechnical Investigation***, the subject site consists of a layer of existing fill from the previous land use, underlain by stiff to very stiff brown silty clay. Practical refusal was encountered between 9.1 m and 24.1 m, below existing grade. Further summary is discussed in ***Section 6.0***.

Supplemental information from Paterson Group Inc. was also received regarding the anticipated infiltration rates. An infiltration rate of 140 mm/day was estimated for Block 15. Collaborating correspondence is found in ***Appendix A***.

The Canada Lands Company will be delivering the site to a pre-grade condition, in accordance with Mattamy Homes requirements.

Existing infrastructure, outlined below, was garnered from design drawings, not As-Built drawings. The design drawings are as per the most recent ***Wateridge Village at Rockcliffe, Phase 1B,*** drawing set, prepared by IBI Group, included in ***Drawings/ Figures***:

Squadron Crescent

- 200 mm diameter PVC watermain;
- 525-2400 mm diameter storm sewer;
- 250-300 mm diameter sanitary sewer; and

Mikinak Road

- 300 mm diameter watermain;
- 825-900 mm diameter storm sewer; and
- 250 mm diameter sanitary sewer.

The servicing received from IBI Group September 15, 2017 was updated by IBI Group to provide stubs to the proposed property and to confirm storm and sanitary capacity within the external system at these new connection points. The approved drawings, prepared by IBI Group detailing the services within Squadron Crescent and Mikinak Road, are included in the appendix ***Drawings/Figures***.

The existing services per ***Design Brief Phase 1B*** are considered “in service” as per correspondence with IBI Group included in ***Appendix A***.

© DSEL

1.2 Required Permits / Approvals

The proposed development is subject to the site plan control approval process. The City of Ottawa must approve the engineering design drawings and reports prior to the issuance of site plan control. Lots fronting Squadron Crescent require Part Lot Control.

An ECA Approval will be required through the Ministry of the Environment, Conservation and Parks (MECP) through the Direct Submission process as the development does not fall under the exemptions set out in O.Reg 525/98.

As per consultation with the RVCA, additional stormwater quality control is not required for the subject site as the water quality objectives are being achieved through the Eastern SWM Facility. Supporting correspondence is included in ***Appendix A***.

The City of Ottawa reviews watermains on behalf of the MECP. The MECP "Form 1" is submitted to the City of Ottawa for approval of watermains.

1.3 Pre-consultation

Pre-consultation correspondence, along with the servicing guidelines checklist, is located in ***Appendix A***.

© DSEL

2.0 GUIDELINES, PREVIOUS STUDIES, AND REPORTS

2.1 Existing Studies, Guidelines, and Reports

The following studies were utilized in the preparation of this report:

- **Ottawa Sewer Design Guidelines**,
  City of Ottawa, *SDG002*, October 2012.
  (City Standards)

  - **Technical Bulletin ISTB-2018-01**
    City of Ottawa, March 21, 2018.
    (*ISTB-2018-01*)

  - **Technical Bulletin ISTB-2018-04**
    City of Ottawa, June 27, 2018.
    (*ISTB-2018-04*)

- **Ottawa Design Guidelines – Water Distribution**
  City of Ottawa, July 2010.
  (Water Supply Guidelines)

  - **Technical Bulletin ISD-2010-2**
    City of Ottawa, December 15, 2010.
    (*ISD-2010-2*)

  - **Technical Bulletin ISDTB-2014-02**
    City of Ottawa, May 27, 2014.
    (*ISDTB-2014-02*)

  - **Technical Bulletin ISDTB-2018-02**
    City of Ottawa, March 21, 2018.
    (*ISDTB-2018-02*)

- **Design Guidelines for Sewage Works,**
  Ministry of the Environment, 2008.
  (MOE* Design Guidelines*)

- **Stormwater Planning and Design Manual,**
  Ministry of the Environment, March 2003.
  (SWMP Design Manual)

- **Ontario Building Code Compendium**
  Ministry of Municipal Affairs and Housing Building Development Branch, January 1, 2010, Update.
  (OBC)

© DSEL

- **Low Impact Development Stormwater Management Planning and Design Guide**
  Credit Valley Conservation & Toronto and Region Conservation, 2010.
  (LID Guide)

- **Former CFB Rockcliffe Master Servicing Study**
  IBI Group, August 2015.
  (MSS)

- **Low Impact Development (LID) Demonstration Project**
  Aquafor Beech Ltd., August 2015.
  (LID Demonstration Project)

- **Design Brief Wateridge Village at Rockcliffe Phase 1A**
  IBI Group., April 2016.
  (Design Brief Phase 1A)

- **Design Brief Wateridge Village at Rockcliffe Phase 1B**
  IBI Group., June 2017.
  (Design Brief Phase 1B)

- **Functional Servicing and Stormwater Management Report – Wateridge Village Block 15**
  DSEL, March 2018.
  (FSR-Block15)

- **Geotechnical Investigation Proposed Residential Development Block 15, 22 and 24 – Revision 3**
  Paterson, December 4, 2019.
  (Geotechnical Investigation)

- **Geotechnical Response to City of Ottawa Review Comments – Wateridge Residential Development – Phase 1B**
  Paterson, July 11, 2018.
  (PG4064-MEMO.07)

- **Infiltration Rates – Proposed Residential Development – Block 15 – Wateridge Village – Ottawa**
  Paterson, January 21, 2019.
  (PG4064-MEMO.09)

- **Grading Plan Review – Wateridge Residential Development – Phase 1B – Block 15**
  Paterson, November 6, 2019.
  (PG4064-MEMO.10)

© DSEL

- **Geotechnical Response to City Review Comments – Wateridge Residential Development**
  Paterson, September 27, 2019.
  (PG4064-MEMO.11)

- **Geotechnical Recommendations – Review of Servicing – Installation Impact on Adjacent Building Foundations – Wateridge Residential Development**
  Paterson, December 19, 2019.
  (PG4064-MEMO.12)

- **Geotechnical Recommendations – Review of Servicing – Installation Impact on Adjacent Building Foundations – Wateridge Residential Development**
  Paterson, November 6, 2019.
  (PG4064-MEMO.14)

- **Landscaping Plan Review – Block 15 – Wateridge Residential Development**
  Paterson, December 18, 2019.
  (PG4064-MEMO.15)

© DSEL

3.0 WATER SUPPLY SERVICING

3.1 Existing Water Supply Services

The subject property lies within the City of Ottawa MONT pressure zone, as shown by the Pressure Zone map in ***Appendix B***. A local 200 mm diameter watermain exists within the Squadron Crescent right-of-way to service the subject site.

The water servicing for the subject site was accounted for in the design of the water distribution system outlined in the ***Design Brief Phase 1B***. Water demand for the subject property is summarized below:

Table 1
Summary of Water Demand per *Design Brief Phase 1B*

Design Parameter	Total Demand (L/min)
Average Day	185.9
Peak Hour	709.8
Max Day + Fire Flow	13,000 + 322.7

3.2 Water Supply Servicing Design

It is proposed to provide two connections plus individual connections to the 200 mm watermain within Squadron Crescent. The site is serviced by surrounding fire hydrants on Squadron Crescent, Mikinak Road, and internal hydrants proposed on-site.

Individual units cannot be serviced horizontally through an adjacent unit, unless that service is accessible, see ***OBC*** section 7.1.5.4 (4) for detail. The proposed units could not be developed to accommodate the requirements of ***OBC*** section 7.1.5.4 (4) therefore, individual services are proposed for the back-to-back townhomes. Refer to ***SSP-1,*** accompanying this report***,*** for servicing layout. Due to the limiting distance from the property line to the townhomes, it is proposed to provide a sanitary sewer and watermain along the north property line with a separation of 1.0 m between both. The water and sanitary sewers are designed in accordance with *Procedures to Govern Separation of Sewers and Watermains (Procedure F-6-1)* prepared by the Ontario Ministry of the Environment, Parks and Conservation.

Table 2, summarizes the ***Water Supply Guidelines*** employed in the preparation of the water demand estimate for the proposed development.

© DSEL

Table 2
Water Supply Design Criteria

Design Parameter	Value
Townhouse	2.7 P/unit
Residential Average Daily Demand	280 L/d/P
Residential Maximum Daily Demand	2.5 x avg. day *
Residential Maximum Hourly	5.5 x max. day *
Minimum Watermain Size	150 mm diameter
Minimum Depth of Cover	2.4 m from top of watermain to finished grade
During normal operating conditions desired operating pressure is within	350 kPa and 480 kPa
During normal operating conditions pressure must not drop below	275 kPa
During normal operating conditions pressure must not exceed	552 kPa
During fire flow operating pressure must not drop below	140 kPa

Daily average based on Appendix 4-A from **Water Supply Guidelines*
*** Residential Max. Daily and Max. Hourly peaking factors per MOE Guidelines for Drinking-Water Systems Table 3-3 for 0 to 500 persons.*
-Table updated to reflect ISD-2010-2

Table 3, summarizes the anticipated water supply demand and boundary conditions for the subject site, received from the City of Ottawa.

Table 3
Proposed Water Demand and Boundary Conditions
Proposed Conditions

Design Parameter	Anticipated Demand[1] (L/min)	Boundary Condition[2] Connection 1 (m H_2O / kPa)		Boundary Condition[2] Connection 2 (m H_2O / kPa)	
Average Daily Demand	100.9	57.4	563.1	56.1	550.6
Peak Hour	555.0	57.7	566.0	56.4	553.6
Max Day + Fire Flow	19,000 + 252.3	32.7	320.8	32.4	318.1

1) Water demand calculation per ***Water Supply Guidelines***. See ***Appendix B*** for detailed calculations.
2) Boundary supplied by the City of Ottawa for the demands indicated in the correspondence. The assumed ground elevation for Connection 1 to Squadron Crescent, close to Mikanik Road is 89.26 m, and for Connection 2 to Squadron Crescent is 90.06 m. See ***Appendix B.***

The City provided both the anticipated minimum and maximum water pressures, as well as, the estimated water pressure during fire flow, as indicated by the correspondence in ***Appendix A***. The required fire flow (RFF) was estimated in accordance with City of Ottawa Technical Bulletin ***ISTB-2018-02***. Parameters used in calculating the RFF were received from Q4 Architects Incorporated, included in ***Appendix A*** and summarized below:

- Type of construction – Wood Frame Construction;
- Occupancy type – Limited Combustible; and

© DSEL

- Sprinkler Protection – The sprinkler system that will be used for the stacked townhomes does not qualify for a reduction per ***ISTB-2018-02*** *so is considered non-sprinklered* and non-sprinklered for back-to-back townhomes.

The maximum estimated fire flow is ***19,000 L/min*** at Blocks 2 and 3; see ***Appendix B*** for detailed calculations.

Table 4, summarizes the fire flow requirement calculated for each block, per the above assumptions and the available fire flow per ***Table 18.5.4.3*** of the ***ISTB-2018-02***. See ***Appendix B*** for Hydrant Coverage Figures for the Blocks with the lowest available fire flow (Blocks 5, 6 and 7).

Table 4
Estimated Fire Flow Demand

Block, Street and Townhome Type	Estimated Fire Demand (L/min)	Fire Hydrants within 75m	Fire Hydrants within 150m	Available Fire Flow per Table 18.5.4.3 of ISTB-2018-02 (L/min)
Block 1 (Stacked) – Takamose Private	18,000	2	4	26,496
Block 2 (Stacked) – Takamose Private	19,000	4	2	30,282
Block 3 (Stacked) – Takamose Private	19,000	3	4	32,174
Block 4 (Stacked) – Takamose Private	18,000	3	3	28,398
Block 5 (Stacked) – Makwa Private	16,000	2	2	18,926
Block 6 (Stacked) – Kiniw Private	16,000	2	2	18,926
Block 7 (Stacked) – Kiniw Private	16,000	2	2	18,926
Block 8 (Back-to-Back) – Kiniw Private	12,000	3	2	24,604
Block 9 (Back-to-Back) – Kiniw Private	13,000	4	1	26,497
Block 10 (Back-to-Back) – Kiniw Private	11,000	3	2	24,604
Block 11 (Back-to-Back) – Makwa Private	10,000	2	3	22,711
Block 12 (Back-to-Back) – Makwa Private	10,000	1	4	20,818
Block 13 (Back-to-Back) – Makwa Private	12,000	2	3	22,711
Block 14 (Back-to-Back) – Makwa Private	12,000	1	5	24,603

© DSEL

The property has eight (8) adjacent hydrants used to calculate the available fire flow, as well as, two (2) proposed hydrants within the site:

- Four (4) hydrants are located along the south side of Mikinak Road, one east of the property, one west of the property and two north of the property;
- Four (4) hydrants are located on Squadron Crescent, one west of the property, one east of the property and two south of the property; and
- Two (2) proposed hydrants within the development; one is located at the south-west corner of Takamose Private and Kiniw Private and the other at the north west corner of Makawa Private and the Private Lane.

3.3 Watermain Modelling

EPANet was utilized to determine the availability of pressures throughout the system during average day, max day plus fire flow, and peak hour demands. This static model determines pressures based on the available head obtained from the boundary conditions provided by the City of Ottawa.

The model utilizes the Hazen-Williams equation to determine pressure drop, while the pipe properties have been selected in accordance with ***Water Supply Guidelines***. The model was prepared to assess the available pressure at the finished first floor of each building, as well as the pressures the watermain provides to fire hydrants during fire flow conditions.

A summary of the resulting pressures at the critical nodes resulting in the lowest pressures are summarized in ***Table 5,*** below. A summary of all resulting pressures for each simulation is included in ***Appendix B***.

Table 5
Model Simulation Output Summary

Location	Average Day (kPa)	Max Day + Fire Flow (kPa)	Peak Hour (kPa)
Node 8	549.4	234.2	540.6
Node 9	544.0	233.7	535.1
Node 13	540.6	237.2	531.7
Node 14(Hydrant)	550.2	232.2	541.5
Node 20 (Hydrant)	544.2	237.8	535.4
Node 18	565.8	314.7	562.9

In order to demonstrate the fire flow scenario, the maximum flow of ***5,700 L/min*** was divided between the two proposed hydrants as per the maximum hydrant capacity specified in ***Table 18.5.4.3*** of ***ISTB-2018-02***. The minimum pressures shown in ***Table 5***, above, during the maximum daily flow plus fire flow scenario are above the minimum

© DSEL

required pressure described in ***Table 2***. Based on the boundary conditions received from the City of Ottawa, included in ***Appendix A***, there is sufficient pressure within the existing hydrants to supply the remaining ***9,500 L/min*** required fire flow at the existing hydrants.

As shown in ***Table 5***, above, the pressure at some locations during Average Day and Peak Hour exceed the maximum allowable pressure described in ***Table 2***, therefore pressure reducing valves are required.

Water will flow in all areas of the system and no 'dead' zones were found. ***Appendix B*** contains output reports and model schematics for each scenario. EPANet was used to run an age analysis on the pipes and nodes, and it was determined that no part of the watermain network exceed a total travel time of 5 days during the average day scenario, thus complying with the ***Water Design Guidelines***. Figures and outputs of the age analysis are included in ***Appendix B***.

Backflow preventers are required to be installed on all water services.

3.4 Water Supply Conclusion

It is proposed to service the development through two separate connections to the 200 mm diameter watermain within Squadron Crescent; one along the west and one along the south.

The anticipated water demand was submitted to the City of Ottawa for establishing boundary conditions.

The maximum fire flow for the development is ***19,000 L/min***, the flow was analyzed through 2 hydrants using EPANET. The resulting pressure exceeded the minimum per the ***Water Supply Guidelines***. Pressures during the average day and peak hour scenario are higher than allowable pressure in ***Table 2***; thus, pressure reducing valves are recommended.

A total travel time of 5 days, as per the ***Water Supply Guidelines***, was not exceeded at any part of the watermain network based on the EPANet analysis completed for the average day scenario.

The proposed water supply design conforms to all relevant City Guidelines and Policies.

© DSEL

4.0 WASTEWATER SERVICING

4.1 Existing Wastewater Services

The sanitary flow from the subject property was considered in the wastewater design for the Wateridge Subdivision. The overall flow from Block 15 was contemplated to discharge to the existing 300 mm sanitary sewer within Squadron Crescent, which outlets to the 375 mm diameter sewer within Mikinak Road. The total wastewater flow from the ***Design Brief Phase 1B*** is summarized in ***Table 6,*** below.

Table 6
Wastewater Flow per Design Brief Phase 1B – Total Site Area

Design Parameter	Total Flow (L/s)
Estimated Average Dry Weather Flow	1.97
Estimated Peak Dry Weather Flow	7.85
Estimated Peak Wet Weather Flow	8.40

The total flow summarized in ***Table 6***, above, is from the drainage areas from Block 15. Please refer to ***Appendix C*** for reduced copies of the IBI sanitary design calculations and drainage area map. These values were calculated based on the ***Sewer Design Guidelines*** prior to the issuing of ***ISTB-2018-01***.

The existing 300 mm diameter sanitary sewer within Squadron Crescent discharges to the existing 375 mm sanitary sewer within Mikinak Road. The collected sanitary flow from the abovementioned sanitary sewers is ultimately directed to the existing 2400 mm diameter Codd's Road Shaft sewer.

It is contemplated in ***Design Brief Phase 1B*** for Block 15 to have 3 drainage areas. A 0.79 ha area of Block 15 was contemplated to discharge between MH 215A and 216A; a 0.67 ha area to MH 216A and MH217A; and 1.46 ha between MH 220A and MH221A. The sanitary drainage area and associated calculation sheets extracted form ***Design Brief Phase 1B*** are included in ***Appendix C***.

4.2 Wastewater Design

It is proposed that the development will connect to the 300 mm diameter sewer within the Squadron Crescent right-of-way, as contemplated in the ***Design Brief Phase 1B***. Individual services laterals are proposed to service the back to back townhomes directly from the 250 mm and 300 mm diameter sanitary sewer within Squadron Crescent. ***Table 7***, below, summarizes the ***City Standards*** employed in the design of the proposed wastewater sewer system.

© DSEL

Table 7
Wastewater Design Criteria

Design Parameter	Value
Townhouse	2.7 P/unit
Average Daily Demand	280 L/d/per
Peaking Factor	Harmon's Peaking Factor. Max 3.8, Min 2.0 Harmon's Corrector Factor 0.8
Infiltration and Inflow Allowance	0.05 L/s/ha (Dry Weather) 0.28 L/s/ha (Wet Weather) 0.33 L/s/ha (Total)
Sanitary sewers are to be sized employing the Manning's Equation	$Q = \frac{1}{n} AR^{2/3} S^{1/2}$
Minimum Sewer Size	200 mm diameter
Minimum Manning's 'n'	0.013
Minimum Depth of Cover	2.5 m from crown of sewer to grade
Minimum Full Flowing Velocity	0.6 m/s
Maximum Full Flowing Velocity	3.0 m/s
Extracted from Sections 4 and 6 of the City of Ottawa Sewer Design Guidelines, October 2012 and *ISTB-2018-01*	

Table 8, below, demonstrates the anticipated peak flow from the proposed development compared to the estimated sanitary flow proposed in ***FSR-Block 15***. See ***Appendix C*** for associated calculations.

Table 8
Summary of Total Estimated Peak Wastewater Flow

Design Parameter	Total Flow per *FSR-Block15* (L/s)	Total Flow (L/s)
Estimated Average Dry Weather Flow	1.37	1.78
Estimated Peak Dry Weather Flow	5.48	6.22
Estimated Peak Wet Weather Flow	6.03	7.52

The estimated total sanitary flow discharged to the existing sanitary sewers within Squadron Crescent, based on the site plan provided in ***Drawings/Figures,*** anticipates a peak wet weather flow of ***7.52 L/s***.

The development proposes for an internal sanitary sewer network to collect sanitary flow from the stacked townhomes (Blocks 1 to 7) as well as from the back-to-back townhomes the front both Makwa Private and Kiniw Private. The back-to-back townhomes fronting Squadron Crescent are proposed to have sanitary services connecting directly to the existing sanitary sewers within Squadron Crescent. The proposed sanitary drainage areas are shown on drawing ***SAN-1***.

The internal sewer network is proposed to outlet to the existing sewer within Squadron Crescent between MH 222A and MH 169A, with the back-to-back townhomes facing Squadron Crescent proposed to be freehold units with individual connections to the existing sanitary sewers within Squadron Crescent. This differs from the sanitary drainage

© DSEL

areas and outlets proposed in ***Design Brief Phase 1B***, which only proposed 3 sanitary drainage areas with different outlets as summarized in ***Section 4.1***.

Since the proposed sanitary drainage plan differs from that proposed in ***Design Brief Phase 1B,*** two sanitary design sheets were completed; one for the internal sewer network and another to recreate the sanitary design sheet for ***Design Brief Phase 1B*** using the updated ***Sewer Design Guidelines*** based on ***ISTB-2018-01*** and was updated to represent the proposed site plan and sanitary drainage plan. Based on the updated design sheet, there is sufficient capacity within the existing sewers within Squadron Crescent to support the proposed sanitary design. The supporting design sheets are included in ***Appendix C***.

The proposed peak sanitary flow discharging to the existing sewers within Mikinak Road is ***37.71 L/s***. This is a ***16.8 L/s*** decrease from the Peak flow per ***Design Brief Phase 1B*** of ***54.54 L/s***; therefore, there is sufficient capacity within the downstream sewers to accommodate the proposed sanitary flow.

4.3 Wastewater Servicing Conclusions

The sanitary flow from the subject property has been considered in the wastewater design for the Wateridge Subdivision, as outlined in the ***Design Brief Phase 1B***.

The proposed development results in an overall decrease in wastewater flow than what was contemplated in the ***Design Brief Phase 1B***; therefore, no negative impact is anticipated to the existing downstream sanitary network.

The existing sewer within Squadron Crescent contain sufficient capacity to convey both the direct services from the back-to-back townhomes, as well as, the sanitary flow from the internal sanitary sewer network.

The proposed wastewater design conforms to all relevant ***City Standards***.

© DSEL

5.0 STORMWATER MANAGEMENT

5.1 Existing Stormwater Services

Minor and major flow from the subject site were accounted for in the Wateridge Subdivision. The subject site was contemplated in the ***Design Brief Phase 1B*** to be conveyed to the Eastern SWM Facility and ultimately to the Ottawa River, through bulk storm sewers within Mikinak Road and Codd's Road. Major flow was proposed to be directed to a dry pond to the south of Mikinak Road for quantity control and will eventually discharge through the minor system to the Eastern SWM Facility.

The ***Design Brief Phase 1B*** contemplated minor and major system drainage from Block 15 to be directed to Squadron Crescent. Refer to ***Appendix D*** for reduced copy of the storm design sheet and drainage area figures, prepared by IBI, for the Wateridge Subdivision.

Flows that influence the watershed in which the subject property is located are further reviewed by the principal authority. The subject property is located within the Ottawa River watershed, and is therefore subject to review by the Rideau Valley Conservation Authority (RVCA). Correspondence with the RVCA regarding water quality requirements is located in ***Appendix A.***

5.2 Post-development Stormwater Management Target

Stormwater management requirements for the proposed development were reviewed with the City of Ottawa and CLC, where the proposed development is required to:

- Follow quantity and quality controls outlined in the ***Design Brief Phase 1B;*** and
- Incorporate Low Impact Development measures in accordance with the ***Design Brief Phase 1B*** and ***LID Demonstration Project.***

5.3 Model Summary

The hydrology and hydraulics of the proposed stormwater management system were analyzed in EPASWMM using the Dynamic Wave Routing Model.

The following assumptions were made in the preparation for the EPASWMM model:

Hydrology

- Initial abstraction parameters per City of Ottawa standards;
- Horton's infiltration for soil loss, per City guidelines;
- Calculated % impervious area;
- Estimated average catchment slope for each catchment; and

© DSEL

- Sub-catchment width measured as perpendicular area to catch basins for longest distance of travel.

Hydraulics

- All PVC and concrete sewers have been assigned a Mannings n = 0.013
- Overland spill is modeled as a representative cross section (irregular for road), from high point to low point;
- Catch Basin capacity has been analyzed through a separate calculation found in ***Appendix D***;
- Orifices are all side mounted or bottom draw, circular and rectangular and have a 0.61 discharge coefficient;
- Entrance losses determined from Appendix 6-B of the ***City Standards,*** Exit loses losses equal to 1.0 per *Water Resources Engineering (rev 2) prepared by David A. Chin (2006)***;**
- An analysis of various storm distributions was completed to determine the critical storm event based on the proposed conditions. It was determined that during the 100-year storm event, the Chicago 6 Hour storm distribution resulted in the highest flow and storage requirements. This distribution is to be used in all future analysis of the system; and
- HGL at outlet per ***Wateridge Village at Rockcliffe Phase 1B, drawing 135, prepared by IBI (Project # 38298),*** equal to 86.38 m.

A summary of the hydrological parameters used for each sub catchment has been included in ***Appendix D***.

5.4 Proposed Stormwater Management System

It is proposed that the stormwater from the development will be directed to the 2400 mm storm sewer within Squadron Crescent.

As discussed in ***Section 5.1***, the quantity controls for Block 15 will be provided by the dry pond south of the subject site and through the Eastern SWM Facility as outlined in the ***Design Brief Phase 1B***.

The subject site was also accounted for in the design of the permanent pool of the Eastern SWM Facility which provides 80% TSS removal for the subdivision.

As per consultation with the RVCA, no additional stormwater quality controls are required as the water quality objective is being achieved through the Eastern SWM Facility. Correspondence with the RVCA is included in ***Appendix A***.

A storm design sheet was prepared to support the capacity of the internal storm sewers, refer to ***Appendix D*** for the calculation sheet and ***SWM-1,*** accompanying this report, for

© DSEL

the drainage area figure. Each catch basin has been equipped with an inlet control device (ICD) to ensure only the 5-year flow will enter the proposed minor system equal to a maximum ***308.1 L/s*** in the 100-year storm event. The overall Runoff Coefficient from the site is equal to what was allocated in the ***Design Brief Phase 1B*** and therefore, no additional quantity or quality controls are required.

The internal sewer network is proposed to outlet to the existing sewer within Squadron Crescent between MH 222 and MH 169. The storm drainage areas that are not collected in the internal storm sewer system are proposed to be directed to the Squadron Crescent ROW and collected through existing catch basins and conveyed through the existing storm sewer within Squadron Crescent.

Runoff Coefficients (RC) were calculated for each drainage area. A coefficient of 0.2 was used for permeable areas; 0.9 was used for impermeable areas; and 0.6 was used for locations with interlocking as per the proposed Site Plan. These calculations resulted in RCs lower than 0.8, which was anticipated for the development in ***Design Brief Phase 1B.*** For internal drainage areas, a conservative RC of 0.8 was used, while the calculated RCs were used for the drainage areas directing flow directly to Squadron Crescent. Since the RC calculated for the development is lower than that which was anticipated in ***Design Brief Phase 1B***, there is sufficient capacity downstream to accommodate the proposed design. Runoff Coefficient calculations are included in ***Appendix D.***

The stormwater design sheet from ***Design Brief Phase 1B*** for Squadron Crescent and Mikinak Road between Squadron Crescent was recreated using updated ***Sewer Design Guidelines*** and to include the proposed stormwater drainage plan for Block 15. As per the updated stormsewer design sheet, the existing sewers have sufficient capacity accommodate the proposed storm plan. Although there is sufficient capacity within the existing sewers, it should be noted that the sewers within Squadron Crescent, between MH 221 and MH 222; and MH 222 and MH 165 are at ***96.3%*** capacity and ***99.8%*** capacity respectively. Despite the sewers being near capacity the proposed peak flow discharging from Squadron Crescent to the existing sewer within Mikinak Road of ***8157 L/s*** is ***21 L/s*** less than the proposed peak flow per ***Design Brief Phase 1B*** of ***8178 L/s*** resulting in an overall decrease in the flow directed to the storm sewers within Squadron than was proposed in ***Design Brief Phase 1B***. Supporting calculations are included in ***Appendix D.***

The development also proposes for a 0.16 ha section to the north of the property to direct runoff to the existing catch basins and sanitary sewers within Mikinak Road as shown in the drainage areas in drawing ***SWM-1***. This deviates from ***Design Brief Phase 1B,*** which did not contemplate any flow from Block 15 being directed to storm sewers within Mikinak Road, upstream of MH165. Based on calculations completed based on the ***Design Brief Phase 1B*** storm design sheets, there is ***772 L/s*** of residual capacity within the sewer within Mikinak Road to convey the proposed tributary area from within Block 15.

© DSEL

As per correspondence with IBI Group, dated August 16, 2017, included in ***Appendix A***, there is ***396 L/s*** of capacity in the downstream sewers. As the proposed development does not exceed this flow, there is sufficient capacity within the downstream sewers and Eastern SWM facility to accommodate the proposed flow.

5.5 Hydraulic Grade Line (HGL) Analysis & Overland Flow Depth

A detail EPASWMM model was prepared for the internal minor and major system to determine the conveyance of the minor system and review major system their relation to the critical underside of footing (USF) and surrounding house grade (SHG). A model schematic has been included in ***Appendix D*** for reference.

Tables 9, below, summarizes the HGL in the 100-year and the 100-year + 20% storm events within the site and the USF elevation.

Table 9
HGL 100-Year and 100-Year + 20% Storms vs Underside of Footing

Node ID (per EPASWMM)	Critical Block ID	Critical USF (m)	100-Year HGL (m)	Freeboard to Critical USF (m)	100-Year + 20% HGL (m)	Freeboard to Critical USF (m)	Minimum USF (2) (m)
MH108	Block 1	87.80	86.69	1.11	86.70	1.10	86.99
MH108-MH107 (1)	Block 2	88.25	87.13	1.12	87.14	1.11	87.43
MH108-MH107 (1)	Block 3	88.60	87.53	1.07	87.54	1.06	87.83
MH107	Block 4	88.75	87.91	0.84	87.91	0.84	88.21
MH101	Block 5	88.00	87.22	0.78	87.26	0.74	87.52
MH101	Block 6	88.75	87.22	1.53	87.26	1.49	87.52
MH102	Block 7	88.60	87.21	1.39	87.25	1.35	87.51
MH107	Block 8	89.48	87.91	1.57	87.91	1.57	88.21
MH103	Block 9	89.30	88.06	1.24	87.70	1.60	88.36
MH103	Block 10	89.09	88.06	1.03	87.70	1.39	88.36
MH103	Block 11	88.87	88.06	0.81	87.70	1.17	88.36
MH104	Block 12	88.80	87.21	1.59	87.25	1.55	87.51
MH105	Block 13	88.44	87.04	1.40	87.08	1.36	87.34
MH106	Block 14	87.96	86.93	1.03	86.96	1.00	87.23

1) 100-Year HGL interpolated between manholes
2) Minimum USF equal to 0.30m above HGL

As per ***Table 9***, above, there is a minimum 0.30 m freeboard between the 100-year HGL and the USF which does not extend to the footing during the 100-year + 20% events.

A freeboard of 0.30 m between the 100-year hydraulic grade line and the underside of footing is targeted throughout. All of the proposed underside of footing elevations are

© DSEL

0.30 m (or greater) above the 100-year hydraulic grade line. The 100 year + 20% stress test also provides 0.30 m clearance; which confirms that it does not reach the footing of the building.

Since the back-to-back townhomes fronting Squadron Crescent do not have foundation drain connections to the existing storm sewer, an HGL analysis was not completed for the sewers within Squadron Crescent.

The depth of flow may extend adjacent to the right-of-way provided that the water level must not touch any part of the building envelope and must remain below the lowest building opening during the stress test event (100 year + 20%). There must be at least 15 cm of vertical clearance between the spill elevation on the street and the ground elevation at the nearest building envelope. The summary of the overland flow is summarized in ***Table 10,*** below.

Table 10
Overland Flow 100-Year and 100-Year + 20% Storms vs Surrounding House Grade

Node ID (per EPASWMM)	Critical Block ID	Critical SHG (m)	Overland Flow Elev. 100-Year (m)	Freeboard to Critical SHG (m)	Overland Flow Elev. 100-Year + 20% HGL (m)	Freeboard to Critical SHG (m)
OVRLND102	Block 8	91.25	90.94	0.31	90.95	0.30
CB103A	Block 9	90.81	90.53	0.28	90.54	0.27
CB103B	Block 7	90.35	90.06	0.29	90.07	0.28
OVRLN101	Block 13	90.39	90.24	0.15	90.24	0.15
CB104A	Block 5	90.06	89.88	0.18	89.93	0.13
OVERLAND106	Block 14	89.99	89.8	0.19	89.92	0.07
CB107A	Block 4	90.73	90.58	0.15	90.58	0.15
CB107B	Block 3	90.50	90.19	0.31	90.2	0.30
CB107C	Block 2	89.88	89.72	0.16	89.73	0.15
CB108A	Block 1	89.79	89.32	0.47	89.35	0.44

A separate review was completed for the on-site blocks that front Squadron Crescent. Refer to ***Table 11*** below for summary of the freeboard from the major system flow on Squadron in relation to the on-site blocks.

© DSEL

Table 11
Overland Flow Spill Elev. and 100-Year + 20% Storms vs Surrounding House Grade

Critical Block ID	Critical SHG (m)	Spill Elevation (m)	Freeboard to Spill Elevation (m)	100-Year + 20% Depth (m)	Spill Elev + 100-Year + 20% Depth (m)	Freeboard to Critical SHG (m)
Block 1 (1)	89.7	89.18	0.52	0	89.18	0.52
Block 2 (2)	90.21	89.87	0.34	0.11	89.98	0.23
Block 3 (2)	90.56	90.22	0.34	0.11	90.33	0.23
Block 4 (1)	90.94	90.77	0.17	0.05	90.82	0.12
Block 8 (1)	91.03	90.77	0.26	0.05	90.82	0.21
Block 9 (1)	90.99	90.77	0.22	0.05	90.82	0.17
Block 10 (1)	90.84	90.47	0.37	0.08	90.55	0.29
Block 10 (1)	90.60	90.17	0.43	0.08	90.25	0.35
Block 11 (1)	90.38	90.17	0.21	0.08	90.25	0.13
Block 12 (1)	90.42	89.87	0.55	0.09	89.96	0.46
Block 13 (1)	90.19	89.87	0.32	0.09	89.96	0.23
Block 14 (1)	89.53	89.18	0.35	0.00	89.18	0.35

1) 100-Year + 20% Depth from Table 5-7 Design Brief Wateridge Village at Rockcliffe Phase 1B prepared by IBI Group June 2017
2) Spill Elevation Equal to road grade on Mikinak Road, 100-Year + 20% Depth from Table 5-5 Design Brief Wateridge Village at Rockcliffe Phase 1A prepared by IBI Group April 2016

As shown in the table above, there is sufficient freeboard from the Surrounding House Grade compared with the existing major flow elevations on Squadron Crescent. No low points exist on Mikinak Road fronting the subject property, therefore,

5.6 Low Impact Development (LID) Practices

LID measures are proposed in accordance with the ***Design Brief Phase 1B*** and ***LID Demonstration Project***. It is proposed that flow from rooftops, sidewalks, landscaped areas and access lanes be directed to bioretention cells located throughout the property. Refer to drawing ***SSP-1*** for bioretention cell locations. The granular base below the overflow elevation has been sized in accordance with the ***LID Design Guide*** and based on infiltration rates, to ensure a maximum drawdown time of 48 hours. Based on correspondence with Paterson Group, included in ***Appendix A***, an infiltration rate of ***140 mm/day*** was estimated for the soil in Block 15.

The bioretention cells are designed with a 75 mm layer of mulch/riverstone; underlain by 600 mm deep layer of filter media (3 parts sand, 2 parts topsoil, 1 part organic soil components and additives); a 100 mm layer of pea gravel; and a 525 mm layer of clear stone equipped with a perforated pipe. When the perforated pipe and clearstone is saturated an overflow is provided which directs flow to the minor system.

© DSEL

Details of the bioretention cells are shown on drawing ***DS-2***, accompanying this report.

All LID measures are designed to infiltrate or detain an equivalent of the 4 mm event over the site area and each LID measure must treat the minimum of the 15 mm event. A total infiltration requirement of 4 mm or ***78.4 m³*** and a total treatment volume of the 15 mm event, or ***181.7 m³*** is required per the ***LID Demonstration Project***. The bioretention cells provide ***146.9 m³*** of volume being retained within the perforated pipe and clear stone below the overflow to the minor system. The filter media, clear stone, perforated pipe and ponding volume results in a treatment volume of ***299.8 m³,*** exceeding the 15 mm volume described above.

Stormwater from the ROW is proposed to access the proposed LID features through proposed curb cuts at the barrier curbs along each LID feature. The curb cuts were sized in order to capture the 15 mm storm event. Supporting calculations are included in ***Appendix D***.

5.7 Stormwater Servicing Conclusions

Minor and major system flow from Block 15 were accounted for in the Wateridge subdivision design. Quantity and quality controls are provided through a dry stormwater pond to the south and the Eastern SWM Facility to the north.

There is sufficient capacity within the existing storm sewers within Squadron Crescent to convey the proposed stormwater drainage plan.

LID practices in the form bioretention cells are proposed for treatment, storage and infiltration of roof, landscaped and road runoff from the site, in accordance with the ***LID Demonstration Project.***

The proposed stormwater design conforms to all relevant ***City Standards*** and Policies.

© DSEL

6.0 GEOTECHNICAL CONSIDERATIONS

A ***Geotechnical Investigation*** entitled ***Proposed Residential Development Block 15, 22 and 24*** was prepared by Paterson Group, dated December 4, 2019, detailing geotechnical recommendations for the Wateridge at Rockcliffe development Blocks 15, 22 and 24 inclusively.

Grade raise restrictions as outlined in the above-mentioned geotechnical report (1.0 m permissible) are exceeded in the proposed development. As per the geotechnical memo ***PG4064-MEMO.10***, prepared by Paterson Group, dated November 6, 2019, the proposed grading plan is supported and lightweight fill is not required. Geotechnical memo ***PG4064-MEMO.10*** is included in ***Appendix A***.

The review of LID features and infiltration rates of the subsoils below the proposed infiltration systems was determined for Block 15. The theoretical infiltration rates of the subsoils are included in the geotechnical memo ***PG4064-MEMO.09***, prepared by Paterson Group, dated January 21, 2019. Geotechnical memo ***PG4064-MEMO.09*** is included in ***Appendix A*** for reference.

As the development proposes service connections from the back-to-back townhomes, directly to the services within Squadron Crescent, the existing road is to be reinstated to the extents shown on DSEL drawing, ***GP-1,*** accompanying this report, as per the pavement design outlined in the ***Geotechnical Investigation***. The reinstated pavement structure, where it abuts the existing pavement that is not being replaced, is to be installed as per the structure outlined in geotechnical memo ***PG4064-MEMO.11***, prepared by Paterson Group, dated September 27, 2019, which can be found in ***Appendix A***.

It is anticipated that bedrock removal will be required for the development of this site. Note that bedrock removal is to be completed in accordance with the ***Geotechnical Investigation.***

As per the ***Geotechnical Investigation***, the groundwater table is anticipated to be a minimum of 1 m below the proposed underside of footing elevations. Geotechnical comments regarding the groundwater table with regards to the proposed development are included in ***PG4064-MEMO.11***.

The development proposes watermain, water meter boxes and sanitary sewers that have a horizontal separation distance less than 2.5 m from the edge of proposed building. A review of the servicing installation impact of these sewers and structures to the adjacent footings and recommendations for foundation support is completed as summarized in geotechnical memo ***PG4064-MEMO.12***, prepared by Paterson Group, dated December 19, 2019 and ***PG4064-MEMO.14***, prepared by Paterson Group, dated November 6, 2019. It is recommended that a lightweight concrete infilled trench be installed under the footings for units which have servicing infrastructure within 2.5 m of the building footprint, including Blocks 1-4 and Block 14. It is also recommended that the sanitary and

© DSEL

watermain that cross beneath stairways be provided with a sleeve where it is to be encased in concrete as per geotechnical memo ***PG4064-MEMO.07***, prepared by Paterson Group, dated July 11, 2018. Geotechnical recommendations for the footings and sleeves are shown both on ***GP-1*** and ***DS-3***. Geotechnical memos ***PG4064-MEMO.12, PG4064-MEMO.14***, and ***PG4064-MEMO.07*** are included in ***Appendix A*** for reference.

Proposed landscaping constraints and recommendations are presented in the landscaping plan review memo ***PG4064-MEMO.15***, prepared by Paterson Group, dated December 18, 2019, included in ***Appendix A*** for reference.

© DSEL

7.0 EROSION AND SEDIMENT CONTROL

Soil erosion occurs naturally and is a function of soil type, climate and topography. During construction the extent of erosion losses is exaggerated due to the removal of vegetation and the top layer of soil becoming agitated.

Prior to topsoil stripping, earthworks or underground construction, erosion and sediment controls will be implemented and will be maintained throughout construction.

Silt fence will be installed around the perimeter of the site and will be cleaned and maintained throughout construction. Silt fence will remain in place until the working areas have been stabilized and re-vegetated.

Catch basins will have SILTSACKs or an approved equivalent installed under the grate during construction to protect from silt entering the storm sewer system.

A mud mat will be installed at the construction access in order to prevent mud tracking onto adjacent roads.

Erosion and sediment controls must be in place during construction. The following recommendations to the contractor will be included in contract documents:

- Limit extent of exposed soils at any given time;
- Re-vegetate exposed areas as soon as possible;
- Minimize the area to be cleared and grubbed;
- Protect exposed slopes with plastic or synthetic mulches;
- Install silt fence to prevent sediment from entering existing ditches;
- No refueling or cleaning of equipment near existing watercourses;
- Provide sediment traps and basins during dewatering;
- Install filter cloth between catch basins and frames;
- Plan construction at proper time to avoid flooding; and
- Establish material stockpiles away from watercourses, so that barriers and filters may be installed.

The contractor will, at every rainfall, complete inspections and guarantee proper performance. The inspection is to include:

- Verification that water is not flowing under silt barriers; and
- Clean and change filter cloth at catch basins.

© DSEL

8.0 CONCLUSION AND RECOMMENDATIONS

David Schaeffer Engineering Ltd. (DSEL) has been retained by Mattamy Homes, to amend the previously approved Site Plan Control Application (SPC), dated March 2018, for Block 15 of Wateridge Village at 245 Squadron Crescent, which is currently under re-development. The preceding report outlines the following:

- Based on boundary conditions from the City of Ottawa, sufficient pressure exists to support average day flow, maximum daily flow and peak hourly flow requirements of the proposed development. Pressure reducing valves are required;
- Based on estimated fire flow per ***Table 18.5.4.3*** of ***ISTB-2018-02***, a combination of internal and existing hydrants have the capacity to supply the required fire flow for the development and based on boundary conditions and the EPANet model, the hydrants have sufficient pressure to provide the maximum required fire flow;
- The proposed development is anticipated to have a peak wet weather flow of ***7.52 L/s***, a reduction in flow compared to the ***Design Brief Phase 1B***;
- The quantity and quality controls are provided for the site through a dry pond to the south of the site and the Eastern SWM Facility outlined in the ***Design Brief Phase 1B,*** thus no on-site quantity and quality control measures are required; and
- LID practices in the form of bioretention cells are proposed to treat, storage and infiltrate roof, landscaped and road runoff from the site, in accordance with the ***LID Demonstration Project.***

Prepared by,
David Schaeffer Engineering Ltd.



Per: Jennifer Ailey, P.Eng

Prepared by,
David Schaeffer Engineering Ltd.

Per: Genavieve Greenberg

© DSEL
z:\projects\17-946-wateridge_block 15\b_design\b3_reports\b3-2_servicing (dsel)\2019-12_subm6\fsr_2019-12-19_946_block15_ajt.docx

APPENDIX A

Pre-Consultation Notes

Geotechnical Memos

R-Plan

DEVELOPMENT SERVICING STUDY CHECKLIST

17-948 08/08/2017

4.1 General Content		
☐	Executive Summary (for larger reports only).	N/A
☒	Date and revision number of the report.	Report Cover Sheet
☒	Location map and plan showing municipal address, boundary, and layout of proposed development.	Drawings/Figures
☒	Plan showing the site and location of all existing services.	Figure 1
☒	Development statistics, land use, density, adherence to zoning and official plan, and reference to applicable subwatershed and watershed plans that provide context to applicable subwatershed and watershed plans that provide context to which individual developments must adhere.	Section 1.0
☒	Summary of Pre-consultation Meetings with City and other approval agencies.	Section 1.3
☒	Reference and confirm conformance to higher level studies and reports (Master Servicing Studies, Environmental Assessments, Community Design Plans), or in the case where it is not in conformance, the proponent must provide justification and develop a defendable design criteria.	Section 2.1
☒	Statement of objectives and servicing criteria.	Section 1.0
☒	Identification of existing and proposed infrastructure available in the immediate area.	Sections 3.1, 4.1, 5.1
☐	Identification of Environmentally Significant Areas, watercourses and Municipal Drains potentially impacted by the proposed development (Reference can be made to the Natural Heritage Studies, if available).	N/A
☒	Concept level master grading plan to confirm existing and proposed grades in the development. This is required to confirm the feasibility of proposed stormwater management and drainage, soil removal and fill constraints, and potential impacts to neighbouring properties. This is also required to confirm that the proposed grading will not impede existing major system flow paths.	N/A
☐	Identification of potential impacts of proposed piped services on private services (such as wells and septic fields on adjacent lands) and mitigation required to address potential impacts.	N/A
☐	Proposed phasing of the development, if applicable.	N/A
☒	Reference to geotechnical studies and recommendations concerning servicing.	Section 1.4
☒	All preliminary and formal site plan submissions should have the following information: -Metric scale -North arrow (including construction North) -Key plan -Name and contact information of applicant and property owner -Property limits including bearings and dimensions -Existing and proposed structures and parking areas -Easements, road widening and rights-of-way -Adjacent street names	N/A

4.2 Development Servicing Report: Water		
☐	Confirm consistency with Master Servicing Study, if available	N/A
☒	Availability of public infrastructure to service proposed development	Section 1.1
☒	Identification of system constraints	Section 3.1
☒	Identify boundary conditions	Section 3.1, 3.2
☒	Confirmation of adequate domestic supply and pressure	Section 3.3

*Extracted from the City of Ottawa-Servicing Study Guidelines for Development Applications

☒	Confirmation of adequate fire flow protection and confirmation that fire flow is calculated as per the Fire Underwriter's Survey. Output should show available fire flow at locations throughout the development.	Section 3.2
☐	Provide a check of high pressures. If pressure is found to be high, an assessment is required to confirm the application of pressure reducing valves.	N/A
☐	Definition of phasing constraints. Hydraulic modeling is required to confirm servicing for all defined phases of the project including the ultimate design	N/A
☐	Address reliability requirements such as appropriate location of shut-off valves	N/A
☐	Check on the necessity of a pressure zone boundary modification	N/A
☒	Reference to water supply analysis to show that major infrastructure is capable of delivering sufficient water for the proposed land use. This includes data that shows that the expected demands under average day, peak hour and fire flow conditions provide water within the required pressure range	Section 3.2, 3.3
☐	Description of the proposed water distribution network, including locations of proposed connections to the existing system, provisions for necessary looping, and appurtenances (valves, pressure reducing valves, valve chambers, and fire hydrants) including special metering provisions.	N/A
☐	Description of off-site required feedermains, booster pumping stations, and other water infrastructure that will be ultimately required to service proposed development, including financing, interim facilities, and timing of implementation.	N/A
☒	Confirmation that water demands are calculated based on the City of Ottawa Design Guidelines.	Section 3.2
☐	Provision of a model schematic showing the boundary conditions locations, streets, parcels, and building locations for reference.	N/A

4.3 Development Servicing Report: Wastewater

☒	Summary of proposed design criteria (Note: Wet-weather flow criteria should not deviate from the City of Ottawa Sewer Design Guidelines. Monitored flow data from relatively new infrastructure cannot be used to justify capacity requirements for proposed infrastructure).	Section 4.2
☐	Confirm consistency with Master Servicing Study and/or justifications for deviations.	N/A
☐	Consideration of local conditions that may contribute to extraneous flows that are higher than the recommended flows in the guidelines. This includes groundwater and soil conditions, and age and condition of sewers.	N/A
☒	Description of existing sanitary sewer available for discharge of wastewater from proposed development.	Section 4.1
☒	Verify available capacity in downstream sanitary sewer and/or identification of upgrades necessary to service the proposed development. (Reference can be made to previously completed Master Servicing Study if applicable)	Section 4.2
☒	Calculations related to dry-weather and wet-weather flow rates from the development in standard MOE sanitary sewer design table (Appendix 'C') format.	Section 4.2, Appendix C
☒	Description of proposed sewer network including sewers, pumping stations, and forcemains.	Section 4.2
☐	Discussion of previously identified environmental constraints and impact on servicing (environmental constraints are related to limitations imposed on the development in order to preserve the physical condition of watercourses, vegetation, soil cover, as well as protecting against water quantity and quality).	N/A

*Extracted from the City of Ottawa-Servicing Study Guidelines for Development Applications

☐	Pumping stations: impacts of proposed development on existing pumping stations or requirements for new pumping station to service development.	N/A
☐	Forcemain capacity in terms of operational redundancy, surge pressure and maximum flow velocity.	N/A
☐	Identification and implementation of the emergency overflow from sanitary pumping stations in relation to the hydraulic grade line to protect against basement flooding.	N/A
☐	Special considerations such as contamination, corrosive environment etc.	N/A

4.4 Development Servicing Report: Stormwater Checklist

☒	Description of drainage outlets and downstream constraints including legality of outlets (i.e. municipal drain, right-of-way, watercourse, or private property)	Section 5.1
☒	Analysis of available capacity in existing public infrastructure.	Section 5.1, Appendix D
☒	A drawing showing the subject lands, its surroundings, the receiving watercourse, existing drainage patterns, and proposed drainage pattern.	Drawings/Figures
☒	Water quantity control objective (e.g. controlling post-development peak flows to pre-development level for storm events ranging from the 2 or 5 year event (dependent on the receiving sewer design) to 100 year return period); if other objectives are being applied, a rationale must be included with reference to hydrologic analyses of the potentially affected subwatersheds, taking into account long-term cumulative effects.	Section 5.2
☒	Water Quality control objective (basic, normal or enhanced level of protection based on the sensitivities of the receiving watercourse) and storage requirements.	Section 5.2
☒	Description of the stormwater management concept with facility locations and descriptions with references and supporting information	Section 5.3
☐	Set-back from private sewage disposal systems.	N/A
☐	Watercourse and hazard lands setbacks.	N/A
☒	Record of pre-consultation with the Ontario Ministry of Environment and the Conservation Authority that has jurisdiction on the affected watershed.	Appendix A
☐	Confirm consistency with sub-watershed and Master Servicing Study, if applicable study exists.	N/A
☒	Storage requirements (complete with calculations) and conveyance capacity for minor events (1:5 year return period) and major events (1:100 year return period).	Section 5.3
☐	Identification of watercourses within the proposed development and how watercourses will be protected, or, if necessary, altered by the proposed development with applicable approvals.	N/A
☒	Calculate pre and post development peak flow rates including a description of existing site conditions and proposed impervious areas and drainage catchments in comparison to existing conditions.	Section 5.1, 5.3
☐	Any proposed diversion of drainage catchment areas from one outlet to another.	N/A
☐	Proposed minor and major systems including locations and sizes of stormwater trunk sewers, and stormwater management facilities.	N/A
☐	If quantity control is not proposed, demonstration that downstream system has adequate capacity for the post-development flows up to and including the 100-year return period storm event.	N/A
☐	Identification of potential impacts to receiving watercourses	N/A
☐	Identification of municipal drains and related approval requirements.	N/A

*Extracted from the City of Ottawa-Servicing Study Guidelines for Development Applications

☒	Descriptions of how the conveyance and storage capacity will be achieved for the development.	Section 5.3
☐	100 year flood levels and major flow routing to protect proposed development from flooding for establishing minimum building elevations (MBE) and overall grading.	N/A
☐	Inclusion of hydraulic analysis including hydraulic grade line elevations.	N/A
☒	Description of approach to erosion and sediment control during construction for the protection of receiving watercourse or drainage corridors.	N/A
☐	Identification of floodplains – proponent to obtain relevant floodplain information from the appropriate Conservation Authority. The proponent may be required to delineate floodplain elevations to the satisfaction of the Conservation Authority if such information is not available or if information does not match current conditions.	N/A
☐	Identification of fill constraints related to floodplain and geotechnical investigation.	N/A

4.5 Approval and Permit Requirements: Checklist

☒	Conservation Authority as the designated approval agency for modification of floodplain, potential impact on fish habitat, proposed works in or adjacent to a watercourse, cut/fill permits and Approval under Lakes and Rivers Improvement Act. The Conservation Authority is not the approval authority for the Lakes and Rivers Improvement ct. Where there are Conservation Authority regulations in place, approval under the Lakes and Rivers Improvement Act is not required, except in cases of dams as defined in the Act.	Section 1.2
☐	Application for Certificate of Approval (CofA) under the Ontario Water Resources Act.	N/A
☐	Changes to Municipal Drains.	N/A
☐	Other permits (National Capital Commission, Parks Canada, Public Works and Government Services Canada, Ministry of Transportation etc.)	N/A

4.6 Conclusion Checklist

☒	Clearly stated conclusions and recommendations	Section 7.0
☐	Comments received from review agencies including the City of Ottawa and information on how the comments were addressed. Final sign-off from the responsible reviewing agency.	
☐	All draft and final reports shall be signed and stamped by a professional Engineer registered in Ontario	

*Extracted from the City of Ottawa-Servicing Study Guidelines for Development Applications

Genavieve Greenberg

From: Fraser, Mark <Mark.Fraser@ottawa.ca>
Sent: Wednesday, October 2, 2019 4:37 PM
To: Genavieve Greenberg
Cc: Adam Fobert
Subject: RE: Wateridge Block 15 - Boundary Conditions Request
Attachments: Wateridge Village (rockcliffe) Block 15 Oct 2019.pdf

Hi Genavieve,

Please find below boundary conditions, HGL, for hydraulic analysis at 245 Squadron Cres. (Wateridge Village-Block 15) assumed to be connected to the 203mm on Squadron (see attached for connection locations):

Block 15-Wateridge Village Subdivision
Type of Development: Residential
Site Address: 245 Squadron Cres.
Average Day Demand: 1.68 L/s
Maximum Daily Demand: 4.20 L/s
Maximum Hourly Demand: 9.25 L/s
Fire Flow: 19,000 L/min.

Domestic demands for Blocks 19, 22 and 24 were also included in the model.

Existing Conditions based on current pump operations:

CONNECTION 1 (200mm dia. - Squadron Cres.)
MAX HGL = 147.0m, *the maximum pressure is estimated to be more than 80 psi. A pressure check at completion of construction is recommended to determine if pressure control is required*.
MIN HGL = 146.7m
MXDY+Fire (317 L/s) = 122.0m

CONNECTION 2 (200mm dia. - Squadron Cres.)
MAX HGL = 147.0m, *the maximum pressure is estimated to be more than 80 psi. A pressure check at completion of construction is recommended to determine if pressure control is required*.
MIN HGL = 146.7m
MXDY+Fire (317 L/s) = 123.0m

Please note the following:

- *Boundary conditions provided above are for existing conditions. Upgrades to the Montreal and Brittany pump stations are currently being planned to support the CFB Rockcliffe development. The City plans to control the discharge HGL to 143.0m. Furthermore, the current plan is to use a different pumping strategy that will try to maintain a constant HGL of 143.0m even during peak hour and/or fire flow conditions.*

These are for current conditions and are based on computer model simulation.

Disclaimer: The boundary condition information is based on current operation of the city water distribution system. The computer model simulation is based on the best information available at the time. The operation of the water distribution system can change on a regular basis, resulting in a variation in boundary conditions. The physical properties of watermains deteriorate over time, as such must be assumed in the absence of actual field test data. The variation in physical watermain properties can therefore alter the results of the computer model simulation.

Regards,

Mark Fraser
Project Manager, Planning Services
Development Review Central Branch
City of Ottawa | Ville d'Ottawa
Planning, Infrastructure and Economic Development Department
110 Laurier Avenue West. 4th Floor, Ottawa ON, K1P 1J1
Tel:613.580.2424 ext. 27791
Fax: 613-580-2576
Mail: Code 01-14
Email: Mark.Fraser@ottawa.ca

*Please consider your environmental responsibility before printing this e-mail

This message, including any document or file attached, is intended only for the addressee and may contain privileged and /or confidential information. Any person is strictly prohibited from reading, using, disclosing or copying this message. If you received this message in error, please notify the sender and delete the message. Thank you.

From: Fraser, Mark
Sent: September 30, 2019 4:16 PM
To: Genavieve Greenberg <GGreenberg@dsel.ca>
Cc: Adam Fobert <AFobert@dsel.ca>
Subject: RE: Wateridge Block 15 - Boundary Conditions Request

Hi Genavieve,

Please accept this email as confirmation that updated boundary conditions have been requested from the Water Resources Assets Unit. Please note that it can take approximately 5 business days.

Regards,

Mark Fraser
Project Manager, Planning Services
Development Review Central Branch
City of Ottawa | Ville d'Ottawa
Planning, Infrastructure and Economic Development Department
110 Laurier Avenue West. 4th Floor, Ottawa ON, K1P 1J1
Tel:613.580.2424 ext. 27791
Fax: 613-580-2576
Mail: Code 01-14
Email: Mark.Fraser@ottawa.ca

*Please consider your environmental responsibility before printing this e-mail

This message, including any document or file attached, is intended only for the addressee and may contain privileged and /or confidential information. Any person is strictly prohibited from reading, using, disclosing or copying this message. If you received this message in error, please notify the sender and delete the message. Thank you.

From: Genavieve Greenberg <GGreenberg@dsel.ca>
Sent: September 30, 2019 11:26 AM
To: Fraser, Mark <Mark.Fraser@ottawa.ca>
Cc: Adam Fobert <AFobert@dsel.ca>
Subject: FW: Wateridge Block 15 - Boundary Conditions Request

CAUTION: This email originated from an External Sender. Please do not click links or open attachments unless you recognize the source.

ATTENTION : Ce courriel provient d'un expéditeur externe. Ne cliquez sur aucun lien et n'ouvrez pas de pièce jointe, excepté si vous connaissez l'expéditeur.

Good morning Mark,

We are exploring some alternative servicing options for the site and I was wondering if it would be possible to get boundary conditions for the connection 2 on the figure below.



None of the site demands have changed as listed below:

- The proposed development is residential and would consist of 124 stacked townhomes and 68 back-to-back townhomes.
- We are proposing to two connections to the 200 mm diameter watermain within Squadron Crescent.
- The maximum fire flow demand for the proposed development is 19,000 L/min

	L/min	L/s
Avg. Daily	100.9	1.68
Max Day	252.3	4.20
Peak Hour	555.0	9.25

The emails below outline the demands at the surrounding blocks of the development.

Please let me know if you need any additional information form me. Do you know how soon we might be able to get this information?

Thank you,

Genavieve Greenberg
Project Coordinator/ Junior Designer

DSEL
david schaeffer engineering ltd.

120 Iber Road, Unit 103
Stittsville, ON K2S 1E9

phone: (613) 836-0856 ext. 569
email: ggreenberg@DSEL.ca

This email, including any attachments, is for the sole use of the intended recipient(s) and may contain private, confidential, and privileged information. Any unauthorized review, use, disclosure, or distribution is prohibited. If you are not the intended recipient, or if this information has been inappropriately forwarded to you, please contact the sender by reply email and destroy all copies of the original.

From: Genavieve Melatti <GMelatti@dsel.ca>
Sent: Wednesday, January 30, 2019 1:46 PM
To: Buchanan, Richard <Richard.Buchanan@ottawa.ca>
Subject: RE: Wateridge Block 15 - Boundary Conditions Request

Hey Richard,

I have attached a figure showing the location of the different blocks as well as their connection points. The demand for each Block is included below.

Block 19:

Design Parameter	Anticipated Demand[1] (L/min)
Average Daily Demand	128.5
Peak Hour	697.1
Max Day + Fire Flow	15,000 + 317.8

Block 22:

Design Parameter	Anticipated Demand[1] (L/min)
Average Daily Demand	33.5
Peak Hour	248.2
Max Day + Fire Flow	11,000 + 164.4

Block 24:

Design Parameter	Anticipated Demand[1] (L/min)
Average Daily Demand	82.2
Peak Hour	369.7
Max Day + Fire Flow	12,000 + 246.5

Please let me know if there is any more information that you would be needing. Do you know how soon it would be possible it would be to get the boundary conditions back?

Thank you,

Genavieve Melatti
Project Coordinator/ Junior Designer

DSEL
david schaeffer engineering ltd.

120 Iber Road, Unit 103
Stittsville, ON K2S 1E9

phone: (613) 836-0856 ext. 569
email: gmelatti@DSEL.ca

This email, including any attachments, is for the sole use of the intended recipient(s) and may contain private, confidential, and privileged information. Any unauthorized review, use, disclosure, or distribution is prohibited. If you are not the intended recipient, or if this information has been inappropriately forwarded to you, please contact the sender by reply email and destroy all copies of the original.

From: Genavieve Melatti <GMelatti@dsel.ca>
Sent: Wednesday, January 23, 2019 9:58 AM
To: Buchanan, Richard <Richard.Buchanan@ottawa.ca>
Cc: Steve Merrick <SMerrick@dsel.ca>
Subject: Wateridge Block 15 - Boundary Conditions Request


Good morning Richard,

Would we be able to request boundary conditions for Wateridge Block 15:

1. Location of Service / Street Number: Block 15 - the property is bound by Mikinak Road to the north and Squadron Crescent to the west, south and east

2. Type of development and the fire flow required for the proposed development:

- The proposed development is residential and would consist of 124 stacked townhomes and 68 back-to-back townhomes.
- We are proposing to two connections to the 200 mm diameter watermain within Squadron Crescent.
- The maximum fire flow demand for the proposed development is 19,000 L/min at Blocks 2 and 3. The calculations and parameters used in these calculations are in the attached FUS calculation sheet.
- We are looking for the boundary conditions at the proposed connection point shown below in blue. We were hoping that these point were available in the City model, however, if not, would it be possible to have the boundary conditions for the points labeled as option 2 in purple on the sketch where both ends of Squadron Crescent meet Mikinak Road.



3.

	L/min	L/s
Avg. Daily	100.9	1.68
Max Day	252.3	4.20
Peak Hour	555.0	9.25

If you have any questions please feel free to contact me.

Thank you,

Genavieve Melatti
Project Coordinator/ Junior Designer

DSEL
david schaeffer engineering ltd.

120 Iber Road, Unit 103
Stittsville, ON K2S 1E9

phone: (613) 836-0856 ext. 569
email: gmelatti@DSEL.ca


This email, including any attachments, is for the sole use of the intended recipient(s) and may contain private, confidential, and privileged information. Any unauthorized review, use, disclosure, or distribution is prohibited. If you are not the intended recipient, or if this information has been inappropriately forwarded to you, please contact the sender by reply email and destroy all copies of the original.

'

This e-mail originates from the City of Ottawa e-mail system. Any distribution, use or copying of this e-mail or the information it contains by other than the intended recipient(s) is unauthorized. Thank you.

Le présent courriel a été expédié par le système de courriels de la Ville d'Ottawa. Toute distribution, utilisation ou reproduction du courriel ou des renseignements qui s'y trouvent par une personne autre que son destinataire prévu est interdite. Je vous remercie de votre collaboration.

'


Boundary Condition for Wateridge Village (CFB Rockcliffe)
Block 15
Connection 1
Connection 2
Legend
w_Pipe
Ownership
Private
Public
N
City of Ottawa

Genavieve Melatti

From: Sabrina Castellanos <scastellanos@q4architects.com>
Sent: Tuesday, January 22, 2019 11:02 AM
To: Genavieve Melatti
Cc: Steve Merrick; Conor Sutherland; Jillian Normand; Daniel Sousa
Subject: RE: Wateridge Block 15 FUS Information

Hi Genavieve,

Please see my answers in red below

Regards,

Sabrina Castellanos
Project Manager, B.Arch

Q4 Architects Inc.
2171 Avenue Road, Suite 302, Toronto, Ontario M5M 4B4
T: 416-322-6334 x256 F: 416-322-7294
www.q4architects.com

This e-mail (including any attachments) is the property of Q4 Architects Inc. and is intended for the person(s) it is addressed to only. Unauthorized reproduction, distribution, disclosure, or use is strictly prohibited and will be prosecuted to the fullest extent of the law. If you have received this message in error, please notify Q4 Architects Inc. immediately by telephone, fax, or e-mail, and permanently delete the message and attachments. Thank you. Please consider the environment before printing this email.

From: Genavieve Melatti <GMelatti@dsel.ca>
Sent: January 17, 2019 10:08 AM
To: Sabrina Castellanos <scastellanos@q4architects.com>
Cc: Steve Merrick <SMerrick@dsel.ca>
Subject: RE: Wateridge Block 15 FUS Information

Hey Sabrina,

As mentioned below we are looking for the following information:

- Confirmation that these blocks will not have a sprinkler system installed? They are not sprinkler – Part 9 of the OBC
- The ISO class for the for each Block style. All the blocks will be Wood frame construction – Class 1

I have included the ISO Guide in which sections 1, 2 and 3 on pages 3 to 10 provides definitions to clarify as well as the section from the City's technical bulletin. Note that ISO refers only to fire-resistive for fire ratings not less than 1-hour.

A. *Determine the type of construction.*

- Coefficient *C* in the FUS method is equivalent to coefficient *F* in the ISO method:

Correspondence between FUS and ISO construction coefficients

FUS type of construction	ISO class of construction	Coefficient *C*
Fire-resistive construction	Class 6 (fire resistive)	0.6
	Class 5 (modified fire resistive)	0.6
Non-combustible construction	Class 4 (masonry non-combustible)	0.8
	Class 3 (non-combustible)	0.8
Ordinary construction	Class 2 (joisted masonry)	1.0
Wood frame construction	Class 1 (frame)	1.5

However, the FUS definition of fire-resistive construction is more restrictive than those of ISO construction classes 5 and 6 (modified fire resistive and fire resistive). FUS requires structural members and floors in buildings of fire-resistive construction to have a fire-resistance rating of 3 hours or longer.

- With the exception of fire-resistive construction that is defined differently by FUS and ISO, practitioners can refer to the definitions of the ISO construction classes (and the supporting definitions of the types of materials and assemblies that make up the ISO construction classes) found in the current ISO guide [4] (see Annex i) to help select coefficient *C*.
- To identify the most appropriate type of construction for buildings of mixed construction, the rules included in the current ISO guide [4] can be followed (see Annex i). For a building to be assigned a given classification, the rules require ⅔ (67%) or more of the total wall area and ⅔ (67%) or more of the total floor and roof area of the building to be constructed according to the given construction class or a higher class.
- New residential developments (less than 4 storeys) are predominantly of wood frame construction ($C = 1.5$) or ordinary construction ($C = 1.0$) if exterior walls are of brick or masonry. Residential buildings with exterior walls of brick or masonry veneer and those with less than ⅔ (67%) of their exterior walls made of brick or masonry are considered wood frame construction ($C = 1.5$).

If you need any more information please let me know.

Thank you,

Genavieve Melatti
Project Coordinator/ Junior Designer

DSEL
david schaeffer engineering ltd.

120 Iber Road, Unit 103
Stittsville, ON K2S 1E9

phone: (613) 836-0856 ext. 569
email: gmelatti@DSEL.ca

This email, including any attachments, is for the sole use of the intended recipient(s) and may contain private, confidential, and privileged information. Any unauthorized review, use, disclosure, or distribution is prohibited. If you are not the intended recipient, or if this information has been inappropriately forwarded to you, please contact the sender by reply email and destroy all copies of the original.

From: Conor Sutherland <Conor.Sutherland@mattamycorp.com>
Sent: Thursday, January 17, 2019 10:04 AM

To: Genavieve Melatti <GMelatti@dsel.ca>
Cc: Steve Merrick <SMerrick@dsel.ca>; Jillian Normand <Jillian.Normand@mattamycorp.com>; Sabrina Castellanos <scastellanos@q4architects.com>
Subject: RE: Wateridge Block 15 FUS Information

Hi Genavieve,

Please find Sabrina's contact information below. She is also cc'd in this email.

scastellanos@q4architects.com

Sabrina if you could please work with DSEL to assist them in the design of Block 15 it would be greatly appreciated!

Thank you,
Conor

Conor Sutherland, B.Eng.
Land Development Coordinator
T (613) 831-3548 (direct). **F** (613) 831-9060
Conor.Sutherland@mattamycorp.com
Ottawa Office: 50 Hines Road, Suite 100, Ottawa, ON Canada K2K 2M5

Notice: This email is intended for use of the party to whom it is addressed and may contain confidential information. If you have received this email in error, please inform me and delete it. Thank you.

From: Genavieve Melatti <GMelatti@dsel.ca>
Sent: Thursday, January 17, 2019 9:55 AM
To: Conor Sutherland <Conor.Sutherland@mattamycorp.com>
Cc: Steve Merrick <SMerrick@dsel.ca>
Subject: Wateridge Block 15 FUS Information

Good morning Conor,

I was wondering if you could let me know who from Q4 I should contact for some information we will need for FUS calculations.

We will be needing the following information:

- We assume that as these are townhomes there will not be sprinkler systems installed. I would need this to please be confirmed.
- We will need the the ISO class for each Block style.

If you are able to let me know who I should contact with regards to this that would be great.

Thank you,

Genavieve Melatti
Project Coordinator/ Junior Designer

DSEL
david schaeffer engineering ltd.

120 Iber Road, Unit 103

Stittsville, ON K2S 1E9

phone: (613) 836-0856 ext. 569
email: gmelatti@DSEL.ca

This email, including any attachments, is for the sole use of the intended recipient(s) and may contain private, confidential, and privileged information. Any unauthorized review, use, disclosure, or distribution is prohibited. If you are not the intended recipient, or if this information has been inappropriately forwarded to you, please contact the sender by reply email and destroy all copies of the original.

Genavieve Greenberg

From: Matt Brown <MBrown@q4architects.com>
Sent: Friday, November 1, 2019 10:53 AM
To: Genavieve Greenberg
Subject: RE: Block 15

Yes they are wood frame

Mathew Brown
Associate, Sr. Project Manager, Tech

Q4 Architects Inc.
2171 Avenue Road, Suite 302, Toronto, Ontario M5M 4B4
T: 416-322-6334 x240 F: 416-322-7294
www.q4architects.com

From: Genavieve Greenberg <GGreenberg@dsel.ca>
Sent: November 1, 2019 10:48 AM
To: Matt Brown <MBrown@q4architects.com>; Bill Yip <byip@q4architects.com>; Daniel Sousa <dsousa@q4architects.com>; Neil Corbilla <NCorbilla@q4architects.com>; Pino Lavecchia <Pino.Lavecchia@mattamycorp.com>
Subject: RE: Block 15

Hi Matt,

Thank you for getting back to me, would you consider all buildings to be Class 1 Wood Construction per the ISO guide and the City's technical bulletin?

A. *Determine the type of construction.*

- Coefficient *C* in the FUS method is equivalent to coefficient *F* in the ISO method:

Correspondence between FUS and ISO construction coefficients

FUS type of construction	ISO class of construction	Coefficient *C*
Fire-resistive construction	Class 6 (fire resistive)	0.6
	Class 5 (modified fire resistive)	0.6
Non-combustible construction	Class 4 (masonry non-combustible)	0.8
	Class 3 (non-combustible)	0.8
Ordinary construction	Class 2 (joisted masonry)	1.0
Wood frame construction	Class 1 (frame)	1.5

However, the FUS definition of fire-resistive construction is more restrictive than those of ISO construction classes 5 and 6 (modified fire resistive and fire resistive). FUS requires structural members and floors in buildings of fire-resistive construction to have a fire-resistance rating of 3 hours or longer.

- With the exception of fire-resistive construction that is defined differently by FUS and ISO, practitioners can refer to the definitions of the ISO construction classes (and the supporting definitions of the types of materials and assemblies that make up the ISO construction classes) found in the current ISO guide [4] (see Annex i) to help select coefficient *C*.
- To identify the most appropriate type of construction for buildings of mixed construction, the rules included in the current ISO guide [4] can be followed (see Annex i). For a building to be assigned a given classification, the rules require ⅔ (67%) or more of the total wall area and ⅔ (67%) or more of the total floor and roof area of the building to be constructed according to the given construction class or a higher class.
- New residential developments (less than 4 storeys) are predominantly of wood frame construction ($C = 1.5$) or ordinary construction ($C = 1.0$) if exterior walls are of brick or masonry. Residential buildings with exterior walls of brick or masonry veneer and those with less than ⅔ (67%) of their exterior walls made of brick or masonry are considered wood frame construction ($C = 1.5$).

Thank you,

Genavieve Greenberg
Project Coordinator/ Junior Designer

DSEL
david schaeffer engineering ltd.

120 Iber Road, Unit 103
Stittsville, ON K2S 1E9

phone: (613) 836-0856 ext. 569
email: ggreenberg@DSEL.ca

This email, including any attachments, is for the sole use of the intended recipient(s) and may contain private, confidential, and privileged information. Any unauthorized review, use, disclosure, or distribution is prohibited. If you are not the intended recipient, or if this information has been inappropriately forwarded to you, please contact the sender by reply email and destroy all copies of the original.

From: Matt Brown <MBrown@q4architects.com>
Sent: Friday, November 1, 2019 10:39 AM
To: Bill Yip <byip@q4architects.com>; Daniel Sousa <dsousa@q4architects.com>; Neil Corbilla <NCorbilla@q4architects.com>; Pino Lavecchia <Pino.Lavecchia@mattamycorp.com>

Cc: Genavieve Greenberg <GGreenberg@dsel.ca>
Subject: RE: Block 15

Hi Genavieve

We are building all of the units out of wood, block 1-7 are 75% brick on the end walls blocks 8-14 are 90% siding on the end walls

We do not believe any of the buildings are sprinklered

Mathew Brown
Associate, Sr. Project Manager, Tech

Q4 Architects Inc.
2171 Avenue Road, Suite 302, Toronto, Ontario M5M 4B4
T: 416-322-6334 x240 F: 416-322-7294
www.q4architects.com

From: Bill Yip <byip@q4architects.com>
Sent: November 1, 2019 9:51 AM
To: Matt Brown <MBrown@q4architects.com>; Daniel Sousa <dsousa@q4architects.com>; Neil Corbilla <NCorbilla@q4architects.com>
Subject: FW: Block 15

For your attention.

Bill Yip
Coordinator

Q4 Architects Inc.
2171 Avenue Road, Suite 302, Toronto, Ontario M5M 4B4
Direct: 416-347-5504 T: 416-322-6334 x260 F: 416-322-7294
www.q4architects.com

This e-mail (including any attachments) is the property of Q4 Architects Inc. and is intended for the person(s) it is addressed to only. Unauthorized reproduction, distribution, disclosure, or use is strictly prohibited and will be prosecuted to the fullest extent of the law. If you have received this message in error, please notify Q4 Architects Inc. immediately by telephone, fax, or e-mail, and permanently delete the message and attachments. Thank you. Please consider the environment before printing this email.

From: Genavieve Greenberg <GGreenberg@dsel.ca>
Sent: November 1, 2019 9:48 AM
To: Bill Yip <byip@q4architects.com>
Cc: Steve Merrick <SMerrick@dsel.ca>
Subject: Block 15

Hi Bill,

I was wondering if you would be able to confirm a couple of things for this Block in order for us to verify our FUS calculations. I know there was some back and forth between the buildings being sprinklered. Are either of the block types to be sprinklered? Would you also be able to confirm the ISO class for the blocks, we currently have them as wood frame construction Class 1, would you be able to confirm that this is still the case?

I have attached the ISO Guide for reference, sections 1, 2 and 3 on pages 3 to 10 provide definitions and below is the section from the City's technical bulletin to clarify. Note that ISO refers only to fire-resistive for fire ratings not less than 1-hour.

A. *Determine the type of construction.*

- Coefficient *C* in the FUS method is equivalent to coefficient *F* in the ISO method:

Correspondence between FUS and ISO construction coefficients

FUS type of construction	ISO class of construction	Coefficient *C*
Fire-resistive construction	Class 6 (fire resistive)	0.6
	Class 5 (modified fire resistive)	0.6
Non-combustible construction	Class 4 (masonry non-combustible)	0.8
	Class 3 (non-combustible)	0.8
Ordinary construction	Class 2 (joisted masonry)	1.0
Wood frame construction	Class 1 (frame)	1.5

However, the FUS definition of fire-resistive construction is more restrictive than those of ISO construction classes 5 and 6 (modified fire resistive and fire resistive). FUS requires structural members and floors in buildings of fire-resistive construction to have a fire-resistance rating of 3 hours or longer.

- With the exception of fire-resistive construction that is defined differently by FUS and ISO, practitioners can refer to the definitions of the ISO construction classes (and the supporting definitions of the types of materials and assemblies that make up the ISO construction classes) found in the current ISO guide [4] (see Annex i) to help select coefficient *C*.
- To identify the most appropriate type of construction for buildings of mixed construction, the rules included in the current ISO guide [4] can be followed (see Annex i). For a building to be assigned a given classification, the rules require ⅔ (67%) or more of the total wall area and ⅔ (67%) or more of the total floor and roof area of the building to be constructed according to the given construction class or a higher class.
- New residential developments (less than 4 storeys) are predominantly of wood frame construction ($C = 1.5$) or ordinary construction ($C = 1.0$) if exterior walls are of brick or masonry. Residential buildings with exterior walls of brick or masonry veneer and those with less than ⅔ (67%) of their exterior walls made of brick or masonry are considered wood frame construction ($C = 1.5$).

Please let me know if you have any questions.

Genavieve Greenberg
Project Coordinator/ Junior Designer

DSEL
david schaeffer engineering ltd.

120 Iber Road, Unit 103
Stittsville, ON K2S 1E9

phone: (613) 836-0856 ext. 569
email: ggreenberg@DSEL.ca

This email, including any attachments, is for the sole use of the intended recipient(s) and may contain private, confidential, and privileged information. Any unauthorized review, use, disclosure, or distribution is prohibited. If you are not the intended recipient, or if this information has been inappropriately forwarded to you, please contact the sender by reply email and destroy all copies of the original.

Conservation Partners
Partenaires en conservation

Mississippi Valley Conservation Authority

Rideau Valley Conservation Authority

South Nation Conservation de la Nation Sud

File: 19-OTT-SPC-0086

March 11th, 2019

City of Ottawa
Planning, Infrastructure and Economic Development Department
110 Laurier Avenue West, 4th Floor
Ottawa, ON K1P 1J1

Attention: Kimberley Baldwin

Subject: Mattamy (Rockcliffe) Inc.
Site Plan Control Application D07-12-19-0020
245 Squadron Crescent, City of Ottawa

Dear Ms. Baldwin:

The Conservation Partners Planning and Development Review Team has completed a review of the above noted application to revise a previous submission, including increasing the number of units and altering the layout of the proposed development. The revision provides 192 residential units through a mix of stacked and townhouse developments.

We have undertaken our review within the context of Sections 1.6.6 Sewage, Water and Stormwater, 2.1 Natural Heritage, 2.2 Water and 3.1 Natural Hazards of the Provincial Policy Statement, 2014 issued under Section 3 of the *Planning Act*, and from the perspective of the Conservation Authority regulations. The following comments are offered for your consideration.

Natural Heritage/Natural Hazards

We have not identified any natural hazards or natural heritage features on this property which would preclude the approval of this application.

3889 Rideau Valley Drive, P.O. Box 599
Manotick, Ontario, K4M 1A5

Tel: 613-692-3571
Fax: 613-692-0831

Stormwater Management

We note that stormwater from this site is being directed to an existing 2400 mm storm sewer within Michael Stoqua Street which ultimately outlets to the Eastern SWM Facility as outlined in the Design Brief Phase 1B prepared by DSEL. Please note that the RVCA has not completed a technical review of the stormwater management plan. We will rely on the City to ensure that the stormwater management plan is consistent with the overall Master Servicing Study and the Design Brief Phase 1B.

Conclusion

In conclusion, the RVCA has no objection to this Site Plan Control application. The Conservation Authority kindly requests a copy of decision related to this file. For any questions regarding the information contained in this letter, please feel free to contact me.

Respectfully,

Jamie Batchelor, MCIP, RPP
Planner, Planning and Watershed Science
Rideau Valley Conservation Authority
613-692-3571 ext. 1191
Jamie.batchelor@rvca.ca

Cc: Jillian Normand: Mattamy (Rockcliffe) Inc.

Genavieve Greenberg

From: Jillian Normand <Jillian.Normand@mattamycorp.com>
Sent: Friday, December 6, 2019 12:20 PM
To: Genavieve Greenberg; Jennifer Ailey; Steve Merrick
Cc: Conor Sutherland; Matt Brown; Jessica McLellan; Pino Lavecchia
Subject: FW: Wateridge Block 15 - Stacks + sprinklers

Hi Genavieve,

Please see below regarding the FUS calculations.

Thanks,
Jillian

mattamyHOMES

Jillian Normand, MCIP, RPP
Senior Land Development Manager
T (613) 831-5144 (direct). C (613) 415-7786. F (613) 831-9060
Jillian.Normand@mattamycorp.com
Ottawa Office: 50 Hines Road, Suite 100, Ottawa, ON Canada K2K 2M5

Notice: This email is intended for use of the party to whom it is addressed and may contain confidential information. If you have received this email in error, please inform me and delete it. Thank you.

From: Andrew MacDonald <andrewm@jp2g.com>
Sent: December 6, 2019 11:43 AM
To: Daniel Potechin <Daniel.Potechin@mattamycorp.com>
Cc: Jillian Normand <Jillian.Normand@mattamycorp.com>; Mark MacIsaac <MarkM@jp2g.com>
Subject: RE: Wateridge Block 15 - Stacks + sprinklers

Hi Daniel,

The sprinkler systems do not qualify for the FUS water reduction for sprinkler systems as they are partial sprinkler systems without fire department hose connections or fire alarm supervision.

Regards,

Andrew MacDonald, P.Eng.
Mechanical Engineer
Jp2g Consultants Inc.

Email: andrewm@jp2g.com | Web: www.jp2g.com
T: 613.828.7800 x 218 | C: 613.282.0306 | F: 613.828.2600
1150 Morrison Drive, Suite 410, Ottawa, Ontario, K2H 8S9

Jp2g Consultants Inc.
ENGINEERS · PLANNERS · PROJECT MANAGERS

CONFIDENTIAL AND PRIVILEGED INFORMATION NOTICE:
This e-mail, and any attachments, may contain information that is confidential, subject to copyright, or exempt from disclosure.
Any unauthorized review, disclosure, retransmission, dissemination or other use of or reliance on this information may be unlawful and is strictly prohibited.
Keep it Clean - Go Green

From: Daniel Potechin <Daniel.Potechin@mattamycorp.com>
Sent: Friday, December 6, 2019 11:32 AM
To: Andrew MacDonald <andrewm@jp2g.com>
Cc: Jillian Normand <Jillian.Normand@mattamycorp.com>; Mark MacIsaac <MarkM@jp2g.com>
Subject: Fwd: Wateridge Block 15 - Stacks + sprinklers

Hi Andrew,

Per my voicemail, please see the attached bulletin and the note below from our civil engineer.

They are looking for the classification of sprinkler system as it relates to the attached bulletin from the City of Ottawa to finalize their calculations with respect to any reductions that may apply to the FUS.

Ultimately they will need a letter to confirm and include with their submission but need that classification in short order. If you can give me a ring and/or reply to this email it would be greatly appreciated.

Regards,

Daniel Potechin

Project Director, Wateridge Village

T (613)831-3506 (direct). F(613)831-9060.daniel.potechin@mattamycorp.com

Ottawa Office: 50 Hines Road, Suite 100, Ottawa, ON K2K 2M5

Notice: This email is intended for use of the party to whom it is addressed and may contain confidential information. If you have received this email in error, please inform me and delete it. Thank you.

From: Jillian Normand <Jillian.Normand@mattamycorp.com>
Sent: Friday, December 6, 2019, 11:25 a.m.
To: Daniel Potechin
Subject: FW: Wateridge Block 15 - Stacks + sprinklers

FYI re sprinkler classifications

Jillian Normand, MCIP, RPP
Senior Land Development Manager
T (613) 831-5144 (direct). C (613) 415-7786. F (613) 831-9060
Jillian.Normand@mattamycorp.com
Ottawa Office: 50 Hines Road, Suite 100, Ottawa, ON Canada K2K 2M5

Notice: This email is intended for use of the party to whom it is addressed and may contain confidential information. If you have received this email in error, please inform me and delete it. Thank you.

From: Genavieve Greenberg <GGreenberg@dsel.ca>
Sent: December 6, 2019 10:54 AM
To: Jillian Normand <Jillian.Normand@mattamycorp.com>; Matt Brown <MBrown@q4architects.com>; Pino Lavecchia <Pino.Lavecchia@mattamycorp.com>; Jessica McLellan <Jessica.Mclellan@mattamycorp.com>
Cc: Steve Merrick <SMerrick@dsel.ca>; Jennifer Ailey <JAiley@dsel.ca>
Subject: RE: Wateridge Block 15 - Stacks + sprinklers

Hi Jillian,

We have run the model using the sprinkler demand mentioned below, what we are needing is to confirm the classification of the sprinkler system per the City of Ottawa ISTB attached. When sprinklers are used, there are reductions that apply to the FUS calculation, we are trying to confirm that this reduction does apply and if so to what extent. There are 4 possible options: sprinklered, sprinklered with standard supply, supervised sprinklers and if the system doesn't fall under any of these classifications then it is considered non sprinklered.

We assumed the sprinklered option, but we need confirmation on the classification of the sprinkler system per ISDT-2018-02 section F on page 8 and section F on pages 20 and 21 describe the qualifications for these different levels.

Please let me know if you have any questions regarding these classifications.

Genavieve Greenberg
Project Coordinator/ Junior Designer

DSEL
david schaeffer engineering ltd.

120 Iber Road, Unit 103
Stittsville, ON K2S 1E9

phone: (613) 836-0856 ext. 569
email: ggreenberg@DSEL.ca

This email, including any attachments, is for the sole use of the intended recipient(s) and may contain private, confidential, and privileged information. Any unauthorized review, use, disclosure, or distribution is prohibited. If you are not the intended recipient, or if this information has been inappropriately forwarded to you, please contact the sender by reply email and destroy all copies of the original.

From: Jillian Normand <Jillian.Normand@mattamycorp.com>
Sent: Friday, December 6, 2019 10:37 AM
To: Genavieve Greenberg <GGreenberg@dsel.ca>; Matt Brown <MBrown@q4architects.com>; Pino Lavecchia <Pino.Lavecchia@mattamycorp.com>; Jessica McLellan <Jessica.Mclellan@mattamycorp.com>
Cc: Steve Merrick <SMerrick@dsel.ca>; Jennifer Ailey <JAiley@dsel.ca>
Subject: RE: Wateridge Block 15 - Stacks + sprinklers

Hi Genavieve,

We spoke to the mechanical engineer who provided that the flow rate required for the most conservative unit required 60gpm on the 1.5 services when modeling the sprinklers in stacks at Wateridge.

Do you require a formal letter stating this?

Thanks,
Jillian

Genavieve Greenberg

From: Jamie Batchelor <jamie.batchelor@rvca.ca>
Sent: Wednesday, September 4, 2019 9:35 AM
To: Genavieve Greenberg
Subject: RE: Wateridge Block 15 - RVCA Approval

Good Morning Genavieve,

I can confirm that no additional water quality controls are required as the water quality objective is being achieved through the overall SWM Pond.

Jamie Batchelor, MCIP, RPP
Planner, ext. 1191
Jamie.batchelor@rvca.ca


Rideau Valley Conservation Authority
3889 Rideau Valley Drive
PO Box 599, Manotick ON K4M 1A5
T 613-692-3571 | 1-800-267-3504 F 613-692-0831 | www.rvca.ca

This message may contain information that is privileged or confidential and is intended to be for the use of the individual(s) or entity n
may contain confidential or personal information which may be subject to the provisions of the Municipal *Freedom of Information &* F
you are not the intended recipient of this e-mail, any use, review, revision, retransmission, distribution, dissemination, copying, printing
taking of any action in reliance upon this e-mail, is strictly prohibited. If you have received this e-mail in error, please contact the send
and any copy of the e-mail and any printout thereof, immediately. Your cooperation is appreciated.

From: Genavieve Greenberg <GGreenberg@dsel.ca>
Sent: Tuesday, August 20, 2019 2:32 PM
To: Jamie Batchelor <jamie.batchelor@rvca.ca>
Subject: Wateridge Block 15 - RVCA Approval

Hey Jamie,

I wanted to touch base with you regarding the Wateridge-Block 15 Development at 245 Squadron Crescent.



The subject property is located within the Ottawa River watershed. The site was contemplated in the ***Design Brief Wateridge Village at Rockcliffe Phase 1B,*** prepared by IBI Group., dated June 2017 (***Design Brief Phase 1B***). The drainage plan per the report is attached to this email and shows the subject lands with a Runoff coefficient of 0.8 with flow directed to the Eastern SWM Facility and quantity control provided by the dry pond south of the property ultimately directed to the Eastern SWM facility..

The development proposes 124 stacked townhomes and 68 back-to-back townhomes on 1.96ha of land. The development will direct flow as contemplated to the Eastern SWM Facility with major flow directed to the dry pond south of the property and ultimately to Eastern SWM facility. The development proposed to have a runoff coefficient no greater than 0.8 as contemplated in ***Design Brief Phase 1B.***

The subject site was also accounted for int the design of the permanent pool of the Eastern SWM Facility which provides 80% TSS removal for the subdivision.

If you could please confirm if any additional quality controls are required for the development.

Please feel free to contact me should you have any questions or would like to discuss.

Thank you,

Genavieve Greenberg
Project Coordinator/ Junior Designer

DSEL
david schaeffer engineering ltd.

120 Iber Road, Unit 103
Stittsville, ON K2S 1E9

phone: (613) 836-0856 ext. 569
email: gmelatti@DSEL.ca

This email, including any attachments, is for the sole use of the intended recipient(s) and may contain private, confidential, and privileged information. Any unauthorized review, use, disclosure, or distribution is prohibited. If you are not the intended recipient, or if this information has been inappropriately forwarded to you, please contact the sender by reply email and destroy all copies of the original.

patersongroup **memorandum**

consulting engineers

re:	**Geotechnical Response to City of Ottawa Review Comments** **Wateridge Residential Development - Phase 1B** **335 St. Laurent Boulevard - Ottawa**
to:	Mattamy Homes - **Ms. Jillian Normand** - Jillian.Normand@mattamycorp.com
cc:	DSEL - **Mr. Steve Merrick** - SMerrick@dsel.ca
date:	July 11, 2018
file:	PG4064-MEMO.07

Further to your request, Paterson Group (Paterson) prepared a response to the City of Ottawa review comment for the fourth site plan submission prepared for the aforementioned development.

Site Servicing Comment - Watermain Sleeves

Comment: *Provide structural/geotechnical design of watermain sleeving.*

Paterson Response

Paterson reviewed the following site servicing plan prepared by DSEL:

- ❑ Site Servicing Plan - Wateridge Block 22 - Project No. 17-948 - Drawing No. SSP-1 - Sheet 3 of 6 - Revision 7 dated June 20, 2018.

As part of a previous review, Paterson provided details regarding lean mix concrete backfill where the excavation for services would undermine front porch footings within Block 22. Based on the details provided, the 100 mm diameter watermain is required to be encased in concrete below the front porch footings. The following provides recommendations regarding the sleeve to encase the watermain.

- ❑ A high grade PVC pipe, such as PVC-SDR26 can be provided for the sleeve around the watermain within the concrete backfill below the front porch footings.
- ❑ The diameter of the sleeve should be slightly larger than the outside diameter of the watermain. Since the proposed watermain pipe is 100 mm in diameter, the PVC-SDR26 sleeve can be 150 mm in diameter to accommodate the sidewall thickness of the watermain pipe.
- ❑ It is recommended that the voids between the PVC sleeve and the watermain pipe be filled with sand prior to backfilling. It is also recommended that both ends of each sleeve be plugged with concrete to reduce water infiltration which may wash the sand away and to hold the pipes in place within the sleeves.

We trust that this information satisfies your requirements.

Paterson Group Inc.



Colin Belcourt, P.Eng.

David J. Gilbert, P.Eng.

patersongroup **memorandum**

consulting engineers

re:	**Infiltration Rates** **Proposed Residential Development** - **Block 15** **Wateridge Village - Ottawa**
cc:	David Shaeffer Engineering Ltd. - **Mr. Steve Merrick** - smerrick@dsel.ca
date:	January 21, 2019
file:	PG4064-MEMO.09

Further to your request, Paterson Group (Paterson) carried out a review of available information obtained from a geotechnical program at a location adjacent to Block 15 of the proposed Wateridge Development.

Background

The purpose of this review was to provide a range of theoretical infiltration rates to be encountered within the subsoils below the proposed infiltration system at the aforementioned site.

The subsurface profile encountered at the test hole locations in Block 15 of the proposed development generally consisted of an overlaying fill extending to a maximum depth of 1.8 m below existing grade, underlain by a very stiff to stiff brown silty clay, which in turn is onderlain by a stiff to firm grey silty clay.

Geotechnical Commentary

The field saturated hydraulic conductivity (K_{fs}) values were slected using Engineering Technologies Canada (ETC) Ltd and based on a clay. Reference tables provided in the most recent ETC Pasl Permeameter User Guide. The infiltration rates were determined using Appendix C of the Low Impact Development Stormwater Managment Planning and Design Guide (CVC 2011). It should be noted that a safety correction factor of 3.5 was used when calculating the infiltration rate to account for any variations in the soil.

Based on the theoretical calculations, the infiltration rate of the subsoils below the proposed infiltration system for Block 15 will be approximately **140 to 200 mm/d**.

Please note that the values in this memorandum report are strictly theoretical and based on values obtained in similar materials during previous investigations in the surrounding area. It should also be noted that it was assumed the infiltration system will be installed within the silty clay layer of the subsurface.

We trust that this information is satisfactory for your immediate requirements.

Paterson Group Inc.





January 21, 2019



Nick Giamberardino, E.I.T. . David J. Gilbert, P.Eng.

patersongroup **memorandum**

consulting engineers

re:	**Grading Plan Review** **Wateridge Residential Development - Phase 1B - Block 15** 335 St. Laurent Boulevard - Ottawa
to:	Mattamy Homes - **Ms. Jillian Normand** - Jillian.Normand@mattamycorp.com
cc:	DSEL - **Mr. Steve Merrick** - SMerrick@dsel.ca
date:	November 6, 2019
file:	PG4064-MEMO.10 Revision 1

Further to your request and authorization, Paterson Group (Paterson) prepared the current memorandum to provide a review of the grading plan for Block 15 of the aforementioned residential development. The following memorandum should be read in conjunction with Paterson Report PG4064-2 - Blocks 15, 22 and 24 Revision 2 dated June 25, 2019.

Grading Plan Review

Paterson reviewed the following grading plan prepared by DSEL regarding the aforementioned development:

- ❑ Grading Plan - Block 15 - Job No. 17-946, Drawing No. GP-1, Sheet 2 of 13, Revision 4 dated November 11, 2019.

Based on our review of the above noted grading plan, the proposed grade raises within Block 15 of the aforementioned development are acceptable from a geotechnical perspective. Minor exceedances of the grade raise restriction were noted at select areas. However, Paterson has further reviewed the grades with respect to the soil conditions and proposed foundations. Based on further review, the proposed grades are acceptable from a geotechnical perspective and lightweight fill will not be required for the proposed buildings within Block 15 of the proposed development

Table 1 attached to this memo presents our summary of design details for the current phase.

We trust that this information satisfies your immediate requirements.

Best Regards,

Paterson Group Inc.



Colin Belcourt, P.Eng.

David J. Gilbert, P.Eng.

Table 1 - Summary of Grading Design Details - Wateridge Village - Block 15

Legal Lot/ Block Number	Civic Address	Underside of Footing Elevation (Proposed) (m)	Original GS Front (m)	Proposed GS Front (m)	Approx. Proposed Frost Cover Depth (m)	Minimum Bearing Capacity - Serviceability Limit States (kPa)	Seismic Site Class	Permissible Grade Raise (m)	Above Permissible Grade Raise Front (m)	LWF required in Garage and Front Porch (m)	LWF Required (m)
Block 1 - Unit 1A/1B	501/503 Takamose Private	87.80	89.21	89.70	1.90	150.00	D	1.00	n/a	n/a	n/a
Block 1 - Unit 2A/2B	505/507 Takamose Private	87.80	89.25	89.70	1.90	150.00	D	1.00	n/a	n/a	n/a
Block 1 - Unit 3A/3B	511/509 Takamose Private	87.80	89.50	89.86	2.06	150.00	D	1.00	n/a	n/a	n/a
Block 1 - Unit 4A/4B	513/515 Takamose Private	87.80	89.25	89.94	2.14	150.00	D	1.00	n/a	n/a	n/a
Block 1 - Unit 5A/5B	519/517 Takamose Private	87.80	89.00	89.98	2.18	150.00	D	1.00	n/a	n/a	n/a
Block 1 - Unit 6A/6B	778/776 Mikinak Road	87.80	89.99	90.20	2.40	150.00	D	1.00	n/a	n/a	n/a
Block 1 - Unit 7A/7B	772/774 Mikinak Road	87.80	91.00	90.07	2.27	150.00	D	1.00	n/a	n/a	n/a
Block 1 - Unit 8A/8B	770/768 Mikinak Road	87.80	89.90	90.03	2.23	150.00	D	1.00	n/a	n/a	n/a
Block 1 - Unit 9A/9B	764/766 Mikinak Road	87.80	89.86	89.95	2.15	150.00	D	1.00	n/a	n/a	n/a
Block 1 - Unit 10A/10B	762/760 Mikinak Road	87.80	89.36	89.91	2.11	150.00	D	1.00	n/a	n/a	n/a
Block 2 - Unit 1A/1B	To Be Provided	88.25	89.25	90.15	1.90	150.00	D	1.00	n/a	n/a	n/a
Block 2 - Unit 2A/2B	To Be Provided	88.25	89.25	90.18	1.93	150.00	D	1.00	n/a	n/a	n/a
Block 2 - Unit 3A/3B	To Be Provided	88.25	89.25	90.24	1.99	150.00	D	1.00	n/a	n/a	n/a
Block 2 - Unit 4A/4B	To Be Provided	88.25	89.50	90.30	2.05	150.00	D	1.00	n/a	n/a	n/a
Block 2 - Unit 5A/5B	To Be Provided	88.25	89.50	90.45	2.20	150.00	D	1.00	n/a	n/a	n/a
Block 2 - Unit 6A/6B	To Be Provided	88.25	89.50	90.50	2.25	150.00	D	1.00	0.00	n/a	n/a
Block 2 - Unit 7A/7B	To Be Provided	88.25	90.50	90.45	2.20	150.00	D	1.00	n/a	n/a	n/a
Block 2 - Unit 8A/8B	To Be Provided	88.25	89.35	90.38	2.13	150.00	D	1.00	0.03	n/a	n/a
Block 2 - Unit 9A/9B	To Be Provided	88.25	89.30	90.33	2.08	150.00	D	1.00	0.03	n/a	n/a
Block 2 - Unit 10A/10B	To Be Provided	88.25	89.25	90.26	2.01	150.00	D	1.00	0.01	n/a	n/a
Block 3 - Unit 1A/1B	To Be Provided	88.60	89.75	90.50	1.90	150.00	D	1.00	n/a	n/a	n/a
Block 3 - Unit 2A/2B	To Be Provided	88.60	89.80	90.53	1.93	150.00	D	1.00	n/a	n/a	n/a
Block 3 - Unit 3A/3B	To Be Provided	88.60	89.85	90.55	1.95	150.00	D	1.00	n/a	n/a	n/a
Block 3 - Unit 4A/4B	To Be Provided	88.60	89.90	90.58	1.98	150.00	D	1.00	n/a	n/a	n/a
Block 3 - Unit 5A/5B	To Be Provided	88.60	90.00	90.63	2.03	150.00	D	1.00	n/a	n/a	n/a
Block 3 - Unit 6A/6B	To Be Provided	88.60	90.25	90.83	2.23	150.00	D	1.00	n/a	n/a	n/a
Block 3 - Unit 7A/7B	To Be Provided	88.60	90.00	90.77	2.17	150.00	D	1.00	n/a	n/a	n/a
Block 3 - Unit 8A/8B	To Be Provided	88.60	90.00	90.70	2.10	150.00	D	1.00	n/a	n/a	n/a
Block 3 - Unit 9A/9B	To Be Provided	88.60	90.00	90.66	2.06	150.00	D	1.00	n/a	n/a	n/a
Block 3 - Unit 10A/10B	To Be Provided	88.60	90.00	90.59	1.99	150.00	D	1.00	n/a	n/a	n/a
Block 4 - Unit 1A/1B	To Be Provided	88.75	90.00	90.75	2.00	150.00	D	1.00	n/a	n/a	n/a
Block 4 - Unit 2A/2B	To Be Provided	88.75	90.00	90.84	2.09	150.00	D	1.00	n/a	n/a	n/a
Block 4 - Unit 3A/3B	To Be Provided	88.75	90.25	90.90	2.15	150.00	D	1.00	n/a	n/a	n/a
Block 4 - Unit 4A/4B	To Be Provided	88.75	90.00	90.98	2.23	150.00	D	1.00	n/a	n/a	n/a
Block 4 - Unit 5A/5B	To Be Provided	88.75	90.00	90.98	2.23	150.00	D	1.00	n/a	n/a	n/a
Block 4 - Unit 6A/6B	To Be Provided	88.75	90.00	91.10	2.35	150.00	D	1.00	0.10	n/a	n/a
Block 4 - Unit 7A/7B	To Be Provided	88.75	90.00	91.01	2.26	150.00	D	1.00	0.01	n/a	n/a
Block 4 - Unit 8A/8B	To Be Provided	88.75	90.00	91.01	2.26	150.00	D	1.00	0.01	n/a	n/a
Block 4 - Unit 9A/9B	To Be Provided	88.75	90.25	90.93	2.18	150.00	D	1.00	n/a	n/a	n/a
Block 4 - Unit 10A/10B	To Be Provided	88.75	90.00	90.93	2.18	150.00	D	1.00	n/a	n/a	n/a
Block 5 - Unit 1A/1B	601/603 Makwa Private	88.00	89.25	89.95	1.95	150.00	D	1.00	n/a	n/a	n/a
Block 5 - Unit 2A/2B	605/607 Makwa Private	88.00	89.25	89.96	1.96	150.00	D	1.00	n/a	n/a	n/a
Block 5 - Unit 3A/3B	611/609 Makwa Private	88.00	89.50	89.98	1.98	150.00	D	1.00	n/a	n/a	n/a
Block 5 - Unit 4A/4B	615/613 Makwa Private	88.00	89.50	90.01	2.01	150.00	D	1.00	n/a	n/a	n/a
Block 5 - Unit 5A/5B	617/619 Makwa Private	88.00	89.50	90.25	2.25	150.00	D	1.00	n/a	n/a	n/a
Block 5 - Unit 6A/6B	621/623 Makwa Private	88.00	89.25	90.29	2.29	150.00	D	1.00	0.04	n/a	n/a
Block 5 - Unit 7A/7B	627/625 Makwa Private	88.00	89.25	90.32	2.32	150.00	D	1.00	0.07	n/a	n/a
Block 5 - Unit 8A/8B	631/629 Makwa Private	88.00	89.25	90.40	2.40	150.00	D	1.00	0.15	n/a	n/a

Table 1 - Summary of Grading Design Details - Wateridge Village - Block 15

Legal Lot/ Block Number	Civic Address	Underside of Footing Elevation (Proposed) (m)	Original GS Front (m)	Proposed GS Front (m)	Approx. Proposed Frost Cover Depth (m)	Minimum Bearing Capacity - Serviceability Limit States (kPa)	Seismic Site Class	Permissible Grade Raise (m)	Above Permissible Grade Raise Front (m)	LWF required in Garage and Front Porch (m)	LWF Required (m)
Block 6 - Unit 1A/1B	To Be Provided	88.75	89.75	90.75	2.00	150.00	D	1.00	0.00	n/a	n/a
Block 6 - Unit 2A/2B	To Be Provided	88.75	89.50	90.65	1.90	150.00	D	1.00	0.15	n/a	n/a
Block 6 - Unit 3A/3B	To Be Provided	88.75	89.50	90.64	1.89	150.00	D	1.00	0.14	n/a	n/a
Block 6 - Unit 4A/4B	To Be Provided	88.75	89.50	90.62	1.87	150.00	D	1.00	0.12	n/a	n/a
Block 6 - Unit 5A/5B	To Be Provided	88.75	89.75	90.88	2.13	150.00	D	1.00	0.13	n/a	n/a
Block 6 - Unit 6A/6B	To Be Provided	88.75	89.75	90.91	2.16	150.00	D	1.00	0.16	n/a	n/a
Block 6 - Unit 7A/7B	To Be Provided	88.75	89.75	90.95	2.20	150.00	D	1.00	0.20	n/a	n/a
Block 6 - Unit 8A/8B	To Be Provided	88.75	89.75	90.99	2.24	150.00	D	1.00	0.24	n/a	n/a
Block 7 - Unit 1A/1B	To Be Provided	88.60	89.75	90.60	2.00	150.00	D	1.00	n/a	n/a	n/a
Block 7 - Unit 2A/2B	To Be Provided	88.60	89.75	90.50	1.90	150.00	D	1.00	n/a	n/a	n/a
Block 7 - Unit 3A/3B	To Be Provided	88.60	89.75	90.40	1.80	150.00	D	1.00	n/a	n/a	n/a
Block 7 - Unit 4A/4B	To Be Provided	88.60	89.75	90.78	2.18	150.00	D	1.00	0.03	n/a	n/a
Block 7 - Unit 5A/5B	To Be Provided	88.60	90.00	90.73	2.13	150.00	D	1.00	n/a	n/a	n/a
Block 7 - Unit 6A/6B	To Be Provided	88.60	89.75	90.82	2.22	150.00	D	1.00	0.07	n/a	n/a
Block 8 - Unit 1	801 Kiniw Private	89.48	90.00	91.25	1.77	150.00	D	1.00	0.25	n/a	n/a
Block 8 - Unit 2	803 Kiniw Private	89.48	90.00	91.25	1.77	150.00	D	1.00	0.25	n/a	n/a
Block 8 - Unit 3	805 Kiniw Private	89.48	90.00	91.25	1.77	150.00	D	1.00	0.25	n/a	n/a
Block 8 - Unit 4	807 Kiniw Private	89.48	90.00	91.18	1.70	150.00	D	1.00	0.18	n/a	n/a
Block 8 - Unit 5	809 Kiniw Private	89.48	90.00	91.18	1.70	150.00	D	1.00	0.18	n/a	n/a
Block 8 - Unit 6	317 Squadron Crescent	89.48	89.80	91.14	1.66	150.00	D	1.00	0.34	n/a	n/a
Block 8 - Unit 7	319 Squadron Crescent	89.48	89.80	91.14	1.66	150.00	D	1.00	0.34	n/a	n/a
Block 8 - Unit 8	321 Squadron Crescent	89.48	89.87	91.14	1.66	150.00	D	1.00	0.27	n/a	n/a
Block 8 - Unit 9	323 Squadron Crescent	89.48	89.87	91.14	1.66	150.00	D	1.00	0.27	n/a	n/a
Block 8 - Unit 10	325 Squadron Crescent	89.48	89.87	91.03	1.55	150.00	D	1.00	0.16	n/a	n/a
Block 9 - Unit 1	To Be Provided	89.30	89.75	91.00	1.70	150.00	D	1.00	0.25	n/a	n/a
Block 9 - Unit 2	To Be Provided	89.30	89.75	91.00	1.70	150.00	D	1.00	0.25	n/a	n/a
Block 9 - Unit 3	To Be Provided	89.30	89.75	90.98	1.68	150.00	D	1.00	0.23	n/a	n/a
Block 9 - Unit 4	To Be Provided	89.30	89.75	90.98	1.68	150.00	D	1.00	0.23	n/a	n/a
Block 9 - Unit 5	To Be Provided	89.30	89.75	90.98	1.68	150.00	D	1.00	0.23	n/a	n/a
Block 9 - Unit 6	To Be Provided	89.30	89.75	91.05	1.75	150.00	D	1.00	0.30	n/a	n/a
Block 9 - Unit 7	To Be Provided	89.30	89.75	91.15	1.85	150.00	D	1.00	0.40	n/a	n/a
Block 9 - Unit 8	To Be Provided	89.30	89.75	91.15	1.85	150.00	D	1.00	0.40	n/a	n/a
Block 9 - Unit 9	To Be Provided	89.30	89.75	91.28	1.98	150.00	D	1.00	0.53	n/a	n/a
Block 9 - Unit 10	To Be Provided	89.30	89.75	91.28	1.98	150.00	D	1.00	0.53	n/a	n/a
Block 10 - Unit 1	To Be Provided	89.09	89.75	91.03	1.94	150.00	D	1.00	0.28	n/a	n/a
Block 10 - Unit 2	To Be Provided	89.09	89.75	91.03	1.94	150.00	D	1.00	0.28	n/a	n/a
Block 10 - Unit 3	To Be Provided	89.09	89.75	90.97	1.88	150.00	D	1.00	0.22	n/a	n/a
Block 10 - Unit 4	To Be Provided	89.09	89.50	90.97	1.88	150.00	D	1.00	0.47	n/a	n/a
Block 10 - Unit 5	To Be Provided	89.09	89.50	90.85	1.76	150.00	D	1.00	0.35	n/a	n/a
Block 10 - Unit 6	To Be Provided	89.09	89.50	90.88	1.79	150.00	D	1.00	0.38	n/a	n/a
Block 10 - Unit 7	To Be Provided	89.09	89.50	90.87	1.78	150.00	D	1.00	0.37	n/a	n/a
Block 10 - Unit 8	To Be Provided	89.09	89.75	90.87	1.78	150.00	D	1.00	0.12	n/a	n/a
Block 10 - Unit 9	To Be Provided	89.09	89.75	90.84	1.75	150.00	D	1.00	0.09	n/a	n/a
Block 10 - Unit 10	To Be Provided	89.09	89.75	90.84	1.75	150.00	D	1.00	0.09	n/a	n/a
Block 11 - Unit 1	To Be Provided	88.87	89.50	90.78	1.91	150.00	D	1.00	0.28	n/a	n/a
Block 11 - Unit 2	To Be Provided	88.87	89.50	90.67	1.80	150.00	D	1.00	0.17	n/a	n/a
Block 11 - Unit 3	To Be Provided	88.87	89.50	90.54	1.67	150.00	D	1.00	0.04	n/a	n/a
Block 11 - Unit 4	To Be Provided	88.87	89.50	90.54	1.67	150.00	D	1.00	0.04	n/a	n/a

Table 1 - Summary of Grading Design Details - Wateridge Village - Block 15

Legal Lot/ Block Number	Civic Address	Underside of Footing Elevation (Proposed) (m)	Original GS Front (m)	Proposed GS Front (m)	Approx. Proposed Frost Cover Depth (m)	Minimum Bearing Capacity - Serviceability Limit States (kPa)	Seismic Site Class	Permissible Grade Raise (m)	Above Permissible Grade Raise Front (m)	LWF required in Garage and Front Porch (m)	LWF Required (m)
Block 11 - Unit 5	To Be Provided	88.87	89.50	90.81	1.94	150.00	D	1.00	0.31	n/a	n/a
Block 11 - Unit 6	To Be Provided	88.87	89.50	90.81	1.94	150.00	D	1.00	0.31	n/a	n/a
Block 11 - Unit 7	To Be Provided	88.87	89.50	90.68	1.81	150.00	D	1.00	0.18	n/a	n/a
Block 11 - Unit 8	To Be Provided	88.87	89.50	90.68	1.81	150.00	D	1.00	0.18	n/a	n/a
Block 12 - Unit 1	To Be Provided	88.80	89.25	90.52	1.72	150.00	D	1.00	0.27	n/a	n/a
Block 12 - Unit 2	To Be Provided	88.80	89.25	90.52	1.72	150.00	D	1.00	0.27	n/a	n/a
Block 12 - Unit 3	To Be Provided	88.80	89.25	90.54	1.74	150.00	D	1.00	0.29	n/a	n/a
Block 12 - Unit 4	To Be Provided	88.80	89.25	90.54	1.74	150.00	D	1.00	0.29	n/a	n/a
Block 12 - Unit 5	To Be Provided	88.80	89.50	90.53	1.73	150.00	D	1.00	0.03	n/a	n/a
Block 12 - Unit 6	To Be Provided	88.80	89.50	90.53	1.73	150.00	D	1.00	0.03	n/a	n/a
Block 12 - Unit 7	To Be Provided	88.80	89.50	90.51	1.71	150.00	D	1.00	0.01	n/a	n/a
Block 12 - Unit 8	To Be Provided	88.80	89.50	90.51	1.71	150.00	D	1.00	0.01	n/a	n/a
Block 13 - Unit 1	251 Squadron Crescent	88.44	89.25	90.30	1.86	150.00	D	1.00	0.05	n/a	n/a
Block 13 - Unit 2	253 Squadron Crescent	88.44	89.25	90.33	1.89	150.00	D	1.00	0.08	n/a	n/a
Block 13 - Unit 3	255 Squadron Crescent	88.44	89.25	90.34	1.90	150.00	D	1.00	0.09	n/a	n/a
Block 13 - Unit 4	257 Squadron Crescent	88.44	89.25	90.34	1.90	150.00	D	1.00	0.09	n/a	n/a
Block 13 - Unit 5	259 Squadron Crescent	88.44	89.25	90.55	2.11	150.00	D	1.00	0.30	n/a	n/a
Block 13 - Unit 6	638 Makwa Private	88.44	89.50	90.38	1.94	150.00	D	1.00	n/a	n/a	n/a
Block 13 - Unit 7	636 Makwa Private	88.44	89.50	90.37	1.93	150.00	D	1.00	n/a	n/a	n/a
Block 13 - Unit 8	634 Makwa Private	88.44	89.50	90.37	1.93	150.00	D	1.00	n/a	n/a	n/a
Block 13 - Unit 9	632 Makwa Private	88.44	89.50	90.23	1.79	150.00	D	1.00	n/a	n/a	n/a
Block 13 - Unit 10	630 Makwa Private	88.44	89.50	90.23	1.79	150.00	D	1.00	n/a	n/a	n/a
Block 14 - Unit 1	225 Squadron Crescent	87.96	89.00	89.98	2.02	150.00	D	1.00	n/a	n/a	n/a
Block 14 - Unit 2	227 Squadron Crescent	87.96	89.00	89.98	2.02	150.00	D	1.00	n/a	n/a	n/a
Block 14 - Unit 3	229 Squadron Crescent	87.96	89.00	89.98	2.02	150.00	D	1.00	n/a	n/a	n/a
Block 14 - Unit 4	231 Squadron Crescent	87.96	89.00	89.98	2.02	150.00	D	1.00	n/a	n/a	n/a
Block 14 - Unit 5	233 Squadron Crescent	87.96	89.00	90.12	2.16	150.00	D	1.00	0.12	n/a	n/a
Block 14 - Unit 6	235 Squadron Crescent	87.96	89.00	90.12	2.16	150.00	D	1.00	0.12	n/a	n/a
Block 14 - Unit 7	610 Makwa Private	87.96	89.25	90.04	2.08	150.00	D	1.00	n/a	n/a	n/a
Block 14 - Unit 8	608 Makwa Private	87.96	89.25	90.04	2.08	150.00	D	1.00	n/a	n/a	n/a
Block 14 - Unit 9	606 Makwa Private	87.96	89.25	89.91	1.95	150.00	D	1.00	n/a	n/a	n/a
Block 14 - Unit 10	604 Makwa Private	87.96	89.25	89.91	1.95	150.00	D	1.00	n/a	n/a	n/a
Block 14 - Unit 11	602 Makwa Private	87.96	89.25	89.92	1.96	150.00	D	1.00	n/a	n/a	n/a
Block 14 - Unit 12	600 Makwa Private	87.96	89.25	89.92	1.96	150.00	D	1.00	n/a	n/a	n/a

DSEL Grading Plans Reviewed: Grading Plan - Wateridge - Block 15 - Project 17-946 - Drawing No. GP-1 - Sheet No. 2 of 13 - Revision 4 dated November 11, 2019.

Note: Bearing Capacities noted in the table are the lowest anticipated bearing resistance values. Bedrock and glacial till have higher values, if encountered at footing level.

Note: Reference to block/lot numbers is made in the sense of standing at the street, looking towards the houses, then going from left to right.

patersongroup **memorandum**

consulting engineers

re:	**Geotechnical Response to City Review Comments** **Wateridge Residential Development** **335 St. Laurent Boulevard - Ottawa**
to:	Mattamy Homes - **Ms. Jillian Normand** - Jillian.Normand@mattamycorp.com
cc:	DSEL - **Mr. Steve Merrick** - SMerrick@dsel.ca
date:	September 27, 2019
file:	PG4064-MEMO.11

Further to your request, Paterson Group (Paterson) prepared a response to the most recent City of Ottawa review comments in a letter dated August 8, 2019, prepared for the aforementioned development. This memo should be read in conjunction with Paterson Group Report PG4064-2 Revision 2 - Blocks 15, 22 and 24 - June 25-2019.

Geotechnical Comment 1

Comment: *Paterson Group is required to submit a letter to the City of Ottawa signing off on the Grading Plan prepared by DSEL to verify that there are no exceedances from the permissible grade raise, the grading is acceptable from a geotechnical perspective and the proposal is in conformance with the recommendations and statements of the latest Geotechnical Investigation.*

Response: Reference should be made to PG4064-MEMO.08R - Grading Plan Review - April 12, 2019 for Paterson's review of the grading plan for Block 24 and reference should be made to PG4064-MEMO.10 - Grading Plan Review - Block 15 - July 29, 2019 for Paterson's review of the grading plan for Block 15. If site grading has changed since our review of the grading plan, a further assessment should be completed by Paterson.

Geotechnical Comment 2

Comment: *The proposed grading exceeds the permissible grade raise of 1.0 m for the subject site. Please conduct a geotechnical review of the grading information prepared by DSEL and provide lightweight fill requirements for the aforementioned development if this is the selected option being considered by Mattamy Homes to accommodate the grade raise. A summary table of relevant grading information for each housing block shall be provided. Lightweight fill placement details and limits are required to be identified on the Grading Plan prepared by DSEL.*

Response: Reference should be made to PG4064-MEMO.10 - Grading Plan Review - Block 15 - July 29, 2019 for Paterson's review of the grading plan for Block 15. As noted in the grading plan review memo, minor exceedances of the 1 m grade raise were noted. However, Paterson completed further review and the 1 m grade raise is considered very conservative for the soils at the subject site. Therefore, lightweight fill is **not** required based on the current grading for the subject site. If site grading has changed since our review of the grading plan, a further assessment should be completed by Paterson.

Geotechnical Comment 3

Comment: *Clay soils are present within the subject development that are highly sensitive to water depletion by trees of high water demand during periods of dry weather that can cause the clay to shrink resulting in settlement of any adjacent structure(s). Trees proposed within 4.5 m of foundations will be subject to the tree planting conditions established in the Tree Planting in Sensitive Marine Clay Soils 2017 Guidelines. Please establish the Plasticity Index of the clay soil and satisfy the procedures and conditions identified in the Tree Planting in Sensitive Marine Clay Soils2017 Guidelines.*

Response: Reference should be made to PG4064-MEMO.06R - Landscape Plan Review - April 11, 2018 for Paterson's review of the soil plasticity at the subject site. The following is noted in the memo:

"Atterberg testing was completed at seven (7) borehole locations across the overall site, all with plasticity index results of less than 40% (see Atterberg testing results attached). This satisfies the first condition for reducing the tree foundation setback to **4.5 m** in the City of Ottawa guideline "Tree Planting in Sensitive Marine Clay Soils - 2017 Guidelines."

Geotechnical Comment 4

Comment: *It is expected that bedrock removal will be required. Any blasting activities shall conform to City of Ottawa standard S.P. Np. F-1201. A pre-blasting survey is required to be completed prior to any blasting operations and written notification to all owners and tenants of buildings within 150 m shall be given a minimum of 15 days prior to any blasting commencing.*

Response: Reference can be made to Section 5.2 of the above noted geotechnical report for recommendations regarding bedrock removal. If blasting is required, a pre-blasting survey could be completed by Paterson for the relevant neighbouring structures upon request.

Geotechnical Comment 5

Comment: *Please provide Squadron Crescent road reinstatement recommendations.*

Response: Reference can be made to Table 4 within Section 5.7 of the above noted geotechnical report. Squadron Crescent would be considered a local roadway within the development and the pavement structure presented in Table 4 would be applicable for this roadway. The following additional recommendations are provided.

The pavement structure, where it abuts the existing pavement not being replaced, should be placed as follows:

- ❑ A 300 mm wide section of the existing asphalt roadway should be sawcut from the existing pavement edge to provide a sound surface to abut the proposed pavement structure.
- ❑ It is recommended to mill a 300 mm wide and 40 mm deep section of the existing asphalt, and construct an extension of the subbase and base to the widened section, and then place a new asphalt surface.
- ❑ The proposed pavement structure subbase materials should be tapered no greater than 3H:1V to meet the existing subbase materials.
- ❑ The new pavement granular base and subbase should be placed in maximum 300 mm thick lifts and compacted to a minimum of 98% of the material's SPMDD.
- ❑ If soft spots develop in the subgrade during compaction or due to construction traffic, the affected areas should be excavated and replaced with OPSS Granular B Type II material compacted in maximum 300 mm loose lifts.
- ❑ Clean existing granular road subbase materials can be reused upon assessment by the geotechnical consultant at the time of excavation (construction) as to its suitability.

Geotechnical Comment 6

Comment: *Please document what the elevation of the groundwater table is in relation to the proposed USF elevations and foundation drains.*

Response: Based on the results of the geotechnical investigation and the proposed underside of footing elevations, the long-term groundwater level is anticipated to be a minimum of 1 m below the underside of footing and foundation drains. The long-term groundwater elevation is anticipated to be below the elevation of 87 m with respect to the underside of footing elevations which are proposed at 88 m or higher. It should be further noted that a groundwater lowering of 0.5 m is expected due to the proposed development. Therefore, the proposed underside of footing elevations are acceptable from a geotechnical perspective regarding the long term groundwater level.

Geotechnical Comment 7

Comment: *Please review the proposed LID measures and provide recommendations from a geotechnical perspective.*

Response: Reference should be made to PG4064-MEMO.09 - Infiltration Rates - January 21-2019 for recommendations regarding the infiltration rates of the native soils.

Additional recommendations include the following:

- ❑ The fill between the clear stone media and the building footprint should consist of an impermeable silty clay to act as a clay seal. A minimum 3 m offset should be provided between the clear stone trench and the foundation walls of the proposed buildings (where livable space is located on the opposite side).
- ❑ A 150 mm thick scarification can be provided at the interface between the clear stone and the native soil.
- ❑ A non-woven geotextile liner, such as Terrafix 360R or equivalent, should fully surround the clear stone to prevent migration of fines into the clear stone.

Site Servicing Plan Comment 15

Comment: *The proposed private watermain and sanitary sewer along the north property line with a separation less than a horizontal separation distance of 2.5 m (edge of pipe to edge of pipe) is not supported. The reduced separation distance may be supported by Procedure F-6-1 however there appears to have been no consideration for future maintenance challenges as the sewer and watermain are located below the proposed underside of footings with minimal setback from the foundations. Repairing this private infrastructure without adversely impacting the structures and encroaching into the ROW will be difficult and unavoidable. Any maintenance costs will be significantly increased. Please investigate alternatives as any future repair costs will be the responsibility of the condominium corporation. Consideration shall be given to the future maintenance/repair challenges and associated costs with the servicing strategy and stormwater management solution proposals. Please demonstrate how this infrastructure would be serviced in the future for the City to review and provide recommendations from the geotechnical engineer. If these Blocks are to form part of the future condominium corporation the units shall be serviced internal to the development. Individual service connections under the current scenario to the public infrastructure within Mikinak Road would not be supported.*

Response: Reference should be made to PG4064-MEMO.12 - Lateral Support of Footings - September 26-2019 for information regarding the above noted comment. This memo should be read in conjunction with DSEL's drawings. This memo only addresses geotechnical aspects of footing/service lateral support. Impacts to ROW and additional costs to be addressed by Mattamy/DSEL.

We trust that this information satisfies your requirements.

Paterson Group Inc.



Colin Belcourt, P.Eng.

David J. Gilbert, P.Eng.

patersongroup **memorandum**

consulting engineers

re: **Geotechnical Recommendations - Review of Servicing Installation Impact on Adjacent Building Foundations**
Block 15 - Wateridge Residential Development
335 St. Laurent Boulevard - Ottawa

to: Mattamy Homes - **Ms. Jillian Normand** - Jillian.Normand@mattamycorp.com

cc: DSEL - **Mr. Steve Merrick** - SMerrick@dsel.ca

date: December 19, 2019

file: PG4064-MEMO.12 Revision 4

Paterson Group (Paterson) has prepared the current memorandum report to provide geotechnical recommendations for the foundation support program for the building footings directly adjacent to the proposed services at the aforementioned site.

Background Information

Paterson reviewed the following plans and sketches provided by David Schaeffer Engineering Limited (DSEL) for servicing at the aforementioned residential development:

- ❏ Site Servicing Plan - Wateridge - Block 15 - Project No. 17-946 - Drawing No. SSP-1 - Sheet 3 of 14 - Revision 7 dated December 19, 2019.
- ❏ Details and Notes - Project No. 17-946 - Drawing No. DS-2 - Sheet 13 of 14 - Revision 7 dated December 19, 2019.
- ❏ Grading Plan - Wateridge - Block 15 - Drawing GP-1 - Sheet 2 of 14, Revision 7 dated December 19, 2019.
- ❏ Cross Section - Wateridge - Block 15 - Project No. 17-946 - Drawing No. DS-3 - Sheet 14 of 14, Revision 7 dated December 19, 2019.

Based on the cross section details provided by DSEL, cross sections A-A, E-E and F-F have service pipes and structures located within the lateral support zone of the adjacent building foundation:

- ❏ A-A: The underside of the bedding for the watermain pipe will be located at approximately 86.57 m and the underside of footing is located at an elevation of 88.63 m. Therefore, the vertical separation is approximately 2.06 m with a lateral separation of approximately 2.2 m which does not include the additional trench excavation.

Cross section A-A and F-F has been updated since Paterson's initial review to include a fire line meter chamber. Based on the updated cross section provided by DSEL, the chamber is located in close proximity to the building footing and is therefore within the lateral support zone. The underside of the chamber appears to be located at an elevation of approximately 85.80 m. However, the chamber is only located within a limited section of the adjacent foundation.

- ❑ E-E: The underside of the bedding for the sanitary sewer pipe will be located at approximately 87.11 m and the underside of footing is located at an elevation of 88.64 m. Therefore, the vertical separation is approximately 1.53 m with a lateral separation of approximately 2.14 m which does not include the additional trench excavation. However, the stair footings are anticipated to be founded directly over the watermain pipe.

Based on the proposed service and structure locations with respect to the adjacent building foundations, the following backfilling program is recommended to ensure that adequate lateral support is provided to the adjacent buildings.

Recommendations

Section A-A

To avoid undermining the footings adjacent to the watermain pipe, the watermain should be raised a minimum of 0.6 m, such that the top of the watermain pipe is located at an elevation of 87.52 m. This would put the underside of the bedding at an approximate elevation of 87.17 m. Based on the lateral separation, the watermain would not longer be within the lateral support zone of the footing if placed at this elevation and additional concrete below the footing would not be required. The watermain can be provided with insulation as per City of Ottawa Standards.

Sections A-A and F-F

To ensure that lateral support is not disturbed for the building footings adjacent to the fire line meter chamber, the space between the chamber and the excavation sidewall below the building foundation should be backfilled with concrete. It is recommended that the chamber be installed and the area backfilled with concrete shortly after the area is excavated. The excavation sidewall should be clean of loose material at the time of concrete placement to prevent voids.

Section E-E

The above noted cross section indicates that a concrete infilled trench has been provided to an elevation of 87.26 m to match the elevation of the sanitary sewer as per previous discussions between Paterson and DSEL Based on our review, the cross section provided is as per Paterson's recommendations and acceptable from a geotechnical perspective for protecting the lateral support zone of the building footings.

However, reference should be made to Paterson's previous memo, PG4064-MEMO.07 - Response to City of Ottawa Review Comments - July 11-2018. As per the previous recommendations in this memo, the watermain is to be encased in concrete where the watermain runs below the porch stair footings. A sleeve is to be provided for the watermain where it is encased in concrete as per the previous recommendations. Based on these recommendations, the concrete infilled trench shown below the footing should be expanded to the following dimensions:

- ❑ The concrete infilled trench should extend from the invert of the sanitary sewer up to the underside of the porch footings. Based on the detail provided, the stair footings appear to be similar in elevation to the building footings.
- ❑ The concrete infilled trench should be a minimum of 300 mm beyond the edge of the footing in the direction parallel to the watermain.
- ❑ The concrete infilled trench should extend past the sleeved watermain away from the building. Depending on the extent of the stair footings with respect to the sanitary sewer pipe, the concrete infilled trench may need to extend past the sanitary sewer pipe if there is insufficient space to install the sanitary sewer adjacent to the concrete infill which extends to the sanitary invert. This could be determined on a case by case basis. A larger sleeve similar to the sleeve detail provided for the watermain could be provided for the sanitary sewer pipe if it is required to be encased in concrete.

With regards to the proposed window well located on this side of the house, the exterior edge of the window well is located approximately directly over the watermain pipe. Therefore, if future excavation down to the watermain pipe is required, the window wells would could be partially impacted and may require minor reinstatement after excavation. It is expected that reinstating the window wells as required would be easier and more cost effective than attempting to protect them from future excavation which may or may not be required.

If excavation down to the sanitary sewer is required, no damage to the window well would be anticipated as a trench box would sufficiently retain the soil beneath a light feature such as a window well.

Additional Recommendations

- ❏ Step 1 - Upon completion of the service placement, a workable, brown silty clay backfill placed under dry conditions and approved by the geotechnical consultant at the time of placement is considered acceptable for reuse. The silty clay backfill should be placed in maximum 300 mm loose lifts and compacted using a sheepsfoot roller making several passes to achieve a minimum 95% of its SPMDD. Where required, the service pipe should be adequately encased in concrete as described above.
- ❏ Step 2 - At the time of house construction, concrete should be placed below footing level within the areas described above. The concrete in-filled trench should extend to the above noted elevations of the adjacent sections of pipe or chamber. The concrete supporting the footings should extend horizontally at least 300 mm beyond the outside of the footing face. The trench should be in-filled with lean mix concrete to the underside of footing level.
- ❏ The recommended sub-excavated trench should extend below the footings which are directly adjacent to the service trenches and adjacent building foundation walls. The trench should extend at least 1.5 m horizontally below the foundation walls running perpendicular to the service pipes and be stepped with maximum 600 mm high steps back up to design underside of footing.
- ❏ Paterson personnel should complete inspections at the time of construction.

We trust that this information is satisfactory to meet your immediate requirements.

Paterson Group Inc.

Colin Belcourt, P.Eng.



David J. Gilbert, P.Eng.

Paterson Group

Head Office and Laboratory
154 Colonnade Road South
Ottawa - Ontario - K2E 7J5
Tel: (613) 226-7381 Fax: (613) 226-6344

Northern Office and Laboratory
63 Gibson Street
North Bay - Ontario - P1B 8Z4
Tel: (705) 472-5331 Fax: (705) 472-2334

St. Lawrence Office
993 Princess Street
Kingston - Ontario - K7L 1H3
Tel: (613) 542-7381

patersongroup **memorandum**

consulting engineers

re:	**Geotechnical Response to City Review Comments** **Wateridge Residential Development** **335 St. Laurent Boulevard - Ottawa**
to:	Mattamy Homes - **Ms. Jillian Normand** - Jillian.Normand@mattamycorp.com
date:	November 6, 2019
file:	PG4064-MEMO.13

Further to your request, Paterson Group (Paterson) prepared a response to the most recent City of Ottawa review comments in a letter dated October 28, 2019 prepared for the aforementioned development. This memo should be read in conjunction with Paterson Group Report PG4064-2 Revision 2 - Blocks 15, 22 and 24 - June 25-2019.

Geotechnical Comment 1

Comment: *Please confirm that the service pipes (100 mm dia. watermain and 200 mm dia. sanitary sewer) proposed between Block 1 and Block 2 (drawing no. PP-6 prepared by DSEL) are not within the lateral support zone of the proposed building footings. Please confirm that any future excavation of these services will not undermine the lateral support zone of the footings thus no requirement to provide a lightweight concrete in-filled trench to match the underside of the sanitary sewer. Details shall be documented on drawing PP-6 prepared by DSEL.*

Response: Reference should be made to PG4064-MEMO.14 - Lateral Support of Footings - November 6-2019 for recommendations regarding the lateral support of the Block 1 and Block 2 footings adjacent to the proposed service pipes.

Geotechnical Comment 2

Comment: *The reinforcement of foundation walls needs to be confirmed to satisfy the Tree Planting in Sensitive Marine Clay Soils-2017 Guidelines. Due to the presence of sensitive marine clay soils and reduced tree setbacks some foundation walls within the development will require a min. of two 15-M bars in the upper and lower sections of the foundation walls. Please document which Blocks require reinforcement. This needs to be documented in the geotechnical report to satisfy the condition. A condition will be included in the SPA to collect securities for the reinforcement of foundation walls and a letter provided to confirm the foundation walls have been reinforced per the Tree Planting in Sensitive Marine Clay Soils 2017 Guidelines.*

Response: Reference should be made to PG4064-MEMO.15 - Landscape Plan Review - Block 15 - November 6, 2019. This memo also includes Paterson's review of the soil plasticity at the subject site.

Geotechnical Comment 3

Comment: *The Landscaping Plan Review memorandum PG4064-MEMO.06R dated April 11, 2018 makes reference to an older revision of the landscaping plans prepared by NAK and is said to be read in conjunction with the Geotechnical Report dated August 8, 2017. The latest revision of the geotechnical report submitted in support of the development control application is dated June 25, 2019. Please provide an updated memorandum.*

Response: Reference should be made to PG4064-MEMO.15 - Landscape Plan Review - Block 15 - November 6, 2019 for a review of the current landscaping plans and referencing the current geotechnical report.

Landscaping Plan Comment 1

Comment: *Clay soils are present within the subject development. Trees are being proposed within 4.5 m of building foundations. Reduced tree to foundation setbacks are subject to the tree planting conditions established in the Tree Planting in Sensitive Marine Clay Soils-2017. The six conditions per the Tree Planting in Sensitive Marine Clay Soils-2017 Guidelines are to be met to allow any trees within 4.5 m of a building foundation. Paterson Group has indicated that the plasticity index of the soil does not exceed 40% satisfying the first condition to reduce the tree to foundation setback to 4.5 m however the other conditions have not been discussed.*

Response: Reference should be made to PG4064-MEMO.15 - Landscape Plan Review - Block 15 - November 6, 2019 which discusses the remaining conditions. However, it should be noted that Paterson is not responsible for all conditions, as indicated in the memo.

Landscaping Plan Comment 6

Comment: *Please include the following in a table format to satisfy the condition per the Tree Planting in Sensitive Marine Clay Soils-2017 Guidelines. The USF is required to be 2.1 m below the finished grade (footing level satisfied within 10 m of the tree).*

- ❏ *The foundation depth (as measured between the underside of footing and the lowest finished grade) identified for every Block with low/medium clay soils*
- ❏ *USF elevation proposed*
- ❏ *Lowest finished grade elevation proposed*
- ❏ *Foundation depth (difference between USF and lowest finished grade).*

Response: Reference should be made to PG4064-MEMO.15 - Landscape Plan Review - Block 15 - November 6, 2019 which provides a table with the above noted elevations and commentary regarding the underside of footing elevations with respect to tree planting.

We trust that this information satisfies your requirements.

Paterson Group Inc.







Colin Belcourt, P.Eng.

David J. Gilbert, P.Eng.

patersongroup **memorandum**

consulting engineers

re: **Geotechnical Recommendations - Review of Servicing Installation Impact on Adjacent Building Foundations**
Wateridge Residential Development
335 St. Laurent Boulevard - Ottawa

to: Mattamy Homes - **Ms. Jillian Normand** - Jillian.Normand@mattamycorp.com

cc: DSEL - **Mr. Steve Merrick** - SMerrick@dsel.ca

date: November 6, 2019

file: PG4064-MEMO.14

Paterson Group (Paterson) has prepared the current memorandum report to provide geotechnical recommendations for the foundation support program for the building footings directly adjacent to the proposed services at the aforementioned site.

Background Information

Paterson reviewed the following drawing provided by David Schaeffer Engineering Limited (DSEL) for servicing at the aforementioned residential development:

- ❏ Servicing Between Blk 1 and Blk 2 - Plan and Profile - Project No. 17-946 - Drawing No. PP-6 - Sheet 9 of 14 - Revision 4 dated November 1, 2019.

Based on our review of the above noted drawing, the following information is provided:

- ❏ Block 1: The underside of the bedding for the watermain and sanitary pipes will be located at approximately 87.25 and 86.15 m, respectively. The underside of footing for Block 1 is located at an elevation of 87.80 m. Therefore, the vertical separations are approximately 0.55 m and 1.65 m between the underside of footing and underside of bedding for the watermain and sanitary pipes, respectively. Taking into account the extents of the outside of the footing and the trench excavations, a horizontal separation from the footing of 1.9 m and 3 m has been taken for the watermain and sanitary pipes, respectively.
- ❏ Block 2: The underside of the bedding for the watermain and sanitary pipes will be located at approximately 87.25 and 86.15 m, respectively. The underside of footing for Block 2 is located at an elevation of 88.25 m. Therefore, the vertical separations are approximately 1 m and 2.1 m between the underside of footing and underside of bedding for the watermain and sanitary pipes, respectively. Taking into account the extents of the outside of the footing and the trench excavations, a horizontal separation from the footing of 3.2 m and 2.2 m has been taken for the watermain and sanitary pipes, respectively.
- ❏ To provide adequate lateral support to the footings, a lateral support zone of 1.5H:1V extending down and away from the outside edge of the footing should remain undisturbed by either excavation to install the services or to replace in the future.

Based on the proposed service depths and locations with respect to the proposed footings, the excavation for the service trenches will cause undermining of the footings for Block 2. To avoid undermining of the footings, the following is recommended:

Recommendations

Block 1

Based on our review, the installation of the proposed services will not have an impact on the lateral support zone of the footings for Block 1. Therefore, a concrete infilled trench below the footings for Block 1 is not required.

Block 2

Based on our review of the above noted dimensions provided for Block 2, the excavation of the sanitary sewer pipe will undermine the lateral support zone of the proposed footings. As a result, the following is recommended for the footings of Block 2 adjacent to the service pipes:

- ❑ Step 1 - Upon completion of the service placement, a workable, brown silty clay backfill placed under dry conditions and approved by the geotechnical consultant at the time of placement is considered acceptable for reuse. The silty clay backfill should be placed in maximum 300 mm loose lifts and compacted using a sheepsfoot roller making several passes to achieve a minimum 95% of its SPMDD.
- ❑ Step 2 - At the time of house construction, a lightweight concrete in-filled trench should be sub-excavated below footing level down a minimum elevation of 87.00 m. The near vertical, zero entry trench should extend horizontally at least 300 mm beyond the footing face. The trench should be in-filled with a lightweight concrete, such as a structural lightweight aggregate concrete or polystyrene lightweight fill, to underside of footing level.
- ❑ The recommended sub-excavated trench should extend below the footings which are directly adjacent to the service trenches and extend along the adjacent building foundation walls. The trench should extend at least 1.5 m horizontally below the foundation walls running perpendicular to the service pipes and be stepped with maximum 600 mm high steps back up to design underside of footing.
- ❑ Paterson personnel should complete inspections at the time of construction.

We trust that this information is satisfactory to meet your immediate requirements.

Paterson Group Inc.







Colin Belcourt, P.Eng.

David J. Gilbert, P.Eng.

patersongroup **memorandum**

consulting engineers

re:	**Landscaping Plan Review - Block 15** **Wateridge Residential Development - Phase 1B - Block 15** 335 St. Laurent Boulevard - Ottawa
to:	Mattamy Homes - **Ms. Jillian Normand** - Jillian.Normand@mattamycorp.com
cc:	NAK Design Strategies - **Mr. Christian Matteau** - cmatteau@nak-design.com
date:	December 18, 2019
file:	PG4064-MEMO.15 Revision 3

Further to your request and authorization, Paterson Group (Paterson) prepared the current memorandum to provide a review of the landscaping drawings for Block 15 of the aforementioned residential development. It should be noted that Block 15 is located both on City of Ottawa publicly owned roads and on a private road. The following memorandum should be read in conjunction with Paterson Report PG4064-2 Revision 3 - Blocks 15, 22 and 24 dated December 4, 2019. It should be noted that this memo supersedes any landscaping plan review memos issued before this date.

Landscaping Plan Review

Paterson reviewed the following landscaping plan prepared by Nak Design Strategies and grading plan prepared by DSEL regarding the aforementioned development:

- ❏ Block 15 Site Plan - Job No. Mattamy - Wateridge, File No. D07-12-19-0020, Drawing No. A1, Revision dated November 21, 2019.
- ❏ Landscape Plan - Blocks 15 - Job No. 17-047, Sheet No. L-02, Revision 8 dated December 3, 2019.
- ❏ Grading Plan - Wateridge Block 15 - 245 Squadron Crescent - Project No. 17-946, Drawing No. GP-1, Sheet 2 of 14, Revision 5 dated November 11, 2019.
- ❏ Streetscape Plan (proposed) prepared by Lashley and Associates.

Lots Adjacent to publicly owned roads

Based on the landscaping plans provided, the proposed tree planting is in compliance with the recommendations provided by Paterson and is considered acceptable from a geotechnical perspective, provided the items noted below are addressed. Atterberg testing was completed at seven (7) borehole locations across the overall site, all with plasticity index results of less than 40% (see Atterberg testing results attached). This satisfies the first condition for reducing the tree foundation setback to **4.5 m** in the City of Ottawa guideline “Tree Planting in Sensitive Marine Clay Soils - 2017 Guidelines.”

The following conditions are also required to be met based on the tree planting guidelines:

- ❏ The proposed trees should have a minimum setback of 4.5 m from the proposed foundation walls. Based on our review of the landscaping plan, a 4.5 m setback has been provided for all street trees. It was noted that the 4.5 m setback intersected with some front steps along Mikinak Road.
- ❏ The underside of footing is required to be 2.1 m below finished grade at the locations of the trees. Reference should be made to Table 1 below and following comments regarding the underside of footing elevations.
- ❏ Adequate soil volumes are required to be provided for the proposed trees - 25 cubic meters for small trees and 30 cubic meters for medium trees. This should be confirmed by the landscape architect.
- ❏ Tree species are required to be small to medium size, confirmed by the landscape architect. Reference should be made to the section below for comments regarding the tree species and appropriate setbacks from building foundation walls.
- ❏ The foundation walls are required to have a minimum of two 15-M bars in the upper and lower sections of the foundation walls. This should be indicated on the drawings for the relevant blocks foundation wall. Reference should be made to the additional comments below.
- ❏ Grading surrounding the tree should be designed to promote draining towards the tree root zone. This should be confirmed by the landscape architect and civil engineer.

Table 1 below provides a summary of the landscaping and grading information for the relevant Blocks:

Table 1 - Landscaping Plan and Grading Details					
Block	**Underside of Footing Elevation**	**Lowest Prop. Finished Grade**	**Foundation Depth (m)**	**Underside of Engineered Pad (If Required)**	**Tree to Foundation (m)**
1	87.86	89.70	1.84	87.6	5.5
2	88.06	90.15	2.09	88.05	5.5
3	88.35	90.50	2.15	n/a	5.6
4	88.57	90.68	2.11	n/a	5.6
5	*88.00*	*89.89*	*1.89*	*n/a*	*4.8*
6	*88.75*	*90.62*	*1.87*	*n/a*	*5.2*
7	*88.60*	*90.40*	*1.8*	*n/a*	*4.5*
8	89.48	91.03	1.55	88.93	5.6
9	89.30	90.81	1.51	88.71	5.6
10	89.09	90.85	1.76	88.75	7.0
11	88.87	90.52	1.65	88.42	5.0
12	88.80	90.31	1.51	88.21	5.5
13	88.44	90.13	1.69	88.03	5.0
14	87.96	89.91	1.95	87.81	5.2
❑ Italicized blocks are located on privately owned roads					

Based on our review, the following outstanding issues need to be completed for the proposed development to qualify for the reduced tree planting setback:

Item A: Underside of Footing Elevation

Based on our review, a 2.1 m depth to underside of footing has not been provided for the blocks which have trees less than 7.5 m from the foundation wall. To provide the equivalent of a 2.1 m foundation depth, the following is recommended:

To compensate for the reduced foundation depth, an engineered fill pad (OPSS Granular A or Granular B Type II) can be placed below the footing to the elevation of 2.1 m below proposed finished grade surrounding the building. The engineered fill pad will effectively increase the depth between the finished grade and the underlying silty clay deposit to the required 2.1 m which achieves the same goal as lowering the footing from a tree planting perspective. Reference can be made to Figure 1 attached for additional information.

These recommendations are required for Blocks 1, 2, 8, 9, 10, 11, 12 and 13.

Item B: Tree Species

As discussed with the landscape architect, it should be confirmed that the tree species placed within 7.5 m of the foundation wall consist of small and medium size trees with a mature tree height less than or equal to 14 m. It is understood that the tree heights listed on the plan are the mature heights of these trees in natural conditions and not in city conditions.

Item C: Additional Reinforcing Requirements

As required by the guidelines, the foundation walls should be provided with a minimum of two 15-M bars in the upper and lower sections of the foundation walls. This should be indicated on the relevant drawings and reviewed by Paterson at the time of construction. This requirement applies to **all residential blocks** within Block 15 of Phase 1B.

It is understood that some trees may be provided by others. If these trees meet the requirements to provide the additional reinforcing steel for the remaining blocks, this should be completed as required.

Provided these remaining conditions have been met, the landscaping drawings noted above are in compliance with the City of Ottawa tree planting guidelines.

Item D: Trees within 4.5 m of Front Stairs

Based on our review of the above noted drawings, the footing depths were found to be at a minimum of 1.8 m below proposed finished grade or lower. Based on the newest tree planting guidelines, the footings need to be placed at a minimum depth of 2.1 m below finished grade. It is understood that a number of the stair case structures have 2 or 3 of risers extending horizontally beyond the foundation walls towards Mikinak Road, which includes **Blocks 1-4**. In order to avoid lowering the footings and/or have differential settlement due to part of the riser being within the 4.5 m tree setback, it is recommended that where the front porch footings/risers are located within the 4.5 m setback, a granular backfill be introduced. Where the 2.1 m soil cover is not satisfied, the native material within the footprint of the front porch footings should be sub-excavated to a maximum 300 below the usf level and replaced with a granular pad consisting of OPSS Granular A or Granular B Type II placed in 300 mm loose lifts and compacted to 98% of the material's SPMDD. The granular pad should only be extended horizontally a minimum of 600 mm beyond the face of the foundation wall (towards the interior side of the front porch). It is important to note that a minimum 3H:1V frost taper will be required to transition from the granular pad to the native soil. Please refer to Figure 1 attached.

In addition, the backfill against the front facing porch foundation should also be backfilled with the above noted granular material. The horizontal extent of the foundation wall backfill should be dependent on the extent of the risers above, a minimum of 300 mm wide layer should be provided beyond the lowest riser.


Lots adjacent to privately owned roads

It is noted that Blocks 5, 6 and 7 of this proposed development is to be serviced by a private road. It should also be noted that the City of Ottawa guidelines are not applicable to this subject block due to the block being serviced by a private road. Upon review of the aforementioned drawings, all proposed tree setbacks are considered acceptable from a geotechnical perspective and damage due to the proposed tree planting will not occur.

We trust that this information satisfies your immediate requirements.


Best Regards,

Paterson Group Inc.



Stephanie A. Boisvenue, P.Eng.

Faisal I. Abou-Seido, P.Eng.



ONTARIO MOT PLASTICITY CHART PHASE 1B ATTERBERG GRAPHS V1.1.GPJ DST_MIN.GDT 10-24-16

DST consulting engineers


PLASTICITY CHART

DST Ref. No.: **IN-SO-026755**

Client: **Canada Lands Company**

Project: **Site Servicing Phase 1B**

Figure 1 - Trees Along Mikinak Road Intersecting with Front Porch Structures



Note:

- Where front porch footings have a minimum depth below finished grade of 2.1 m, the granular pad below the footings will not be required.
- The placement of the engineered fill should be reviewed and approved in the field by Paterson personnel.

Steve Merrick

From: Winston Yang <Winston.Yang@ibigroup.com>
Sent: Wednesday, August 16, 2017 11:50 AM
To: Adam Fobert; Jean Lachance
Cc: Jillian Normand; Jim Moffatt
Subject: RE: 918 Mattamy - Wateridge: IBI Servicing Review

Hi Adam and Jean,

I have reviewed the impact as per DSEL design for Block 15, 22 and 24.

Upon review of the proposed grading plans for Blocks 15, 22, and 24, we found the leave grades provided by DSEL to be reasonable.
We do not have a conceptual plan for Block 19 yet. The leave grades for that block seem low for a typical basement development. However they might be fine if underground parking is planned.

For the Servicing side, the storm and sanitary outlets location for each block were changed compared to the MSS and Design Brief.
Then we have implemented the changes DSEL made into our sewer design and have examined the capacity for each downstream sewers.
The result shows that the downstream sewers for storm and sanitary have the capacity to convey the flow for all new outlets for blocks, 15, 22 and 24.

In order to minimize the impact and cost, we are going to shift some manholes to accommodate the new outlets base on DSEL design.
For Block 22, MH210 and MH210A can be shifted to the south to replace the STM101 and SAN1 along Michael Stoqua Street.
For Block 24, MH213 and MH213A can be shifted to the south to replace the STM101 and SAN1 along Moses Tenisco Street. At the same time, MH212 and MH212A will be shifted to the south in order to reduce the length of the sewers.
For Block 15, there is no choice, the manhole STM101 and SAN1 are required for Squadron Crescent.
Since the typical 1200mm Dia. Manholes have been already ordered by the contractor.
We will contact the contractor to find out any further impacts will be caused by shifting the manholes.

For the storm section below. DSEL met the IBI criteria for the proposed lots.
In regards to Block 19, the drainage areas should be corresponded to IBI Lot141, Lot 167 in Phase 1A and Lot208B, Lot209 in Phase 1B.
And the IBI 100 year capture rate is 475l/s (283l/s+63l/s+46l/s+83l/s). Please considered in your design later on.

Should you have any questions please do not hesitate to contact either Jim or me.

Yours truly,

Winston Yang P.Eng.

email Winston.Yang@ibigroup.com web www.ibigroup.com

IBI GROUP
Suite 400, 333 Preston Street
Ottawa ON K1S 5N4 Canada
tel +1 613 225 1311 fax +1 613 225 9868

IBI Defining the cities of tomorrow

NOTE: This email message/attachments may contain privileged and confidential information. If received in error, please notify the sender and delete this e-mail message.

NOTE: Ce courriel peut contenir de l'information privilégiée et confidentielle. Si vous avez recu ce message par erreur, veuillez le mentionner immédiatement à l'expéditeur et effacer ce courriel.

From: Adam Fobert [mailto:AFobert@dsel.ca]
Sent: Tuesday, August 15, 2017 5:27 PM
To: Winston Yang <Winston.Yang@ibigroup.com>; Jim Moffatt <jmoffatt@IBIGroup.com>
Cc: Jean Lachance <JLachance@clc.ca>; Jillian Normand <Jillian.Normand@mattamycorp.com>
Subject: 918 Mattamy - Wateridge: IBI Servicing Review

Hello Jim and Winston,

How is your review of our site servicing is coming along? I have reviewed your Design Brief's for Phase 1A and 1B and have compared the analysis contained within to our proposed design.

I offer the following considerations based on my review:

General:
DSEL proposed one storm and one sanitary connection to each block. The City indicated that this was their expectation during our pre-consultation as it is their standard practice for multi-block parcels.

Block 15: The servicing brief shows three connections to Squadron Crescent. DSEL are proposing one connection downstream of the contemplated connections.

Block 22: The surrounding grades slope from east to west. The servicing brief shows a drainage divide mid-block, where half the site drains to Moses Tenisco and the other to Michael Stoqua . Moses Tenisco is 1.14m higher than Michael Stoqua at the proposed road connection points. As such, to avoid fighting grades DSEL proposed storm and sanitary connections to Michael Stoqua only.

Block 24: Moses Tenisco slopes from north to south 1.1m from Hemlock to Mikinak. The servicing brief shows a drainage divide mid-block with connections to Moses Tenisco and Mikinak. DSEL proposed a storm and sanitary outlet at the southern road connection on Moses Tenisco based on Mattamy's proposed site. This avoids fighting grades internally.

Wastewater:
Block 15:

IBI Servicing Brief = 487.3p
Mattamy Proposal = 335p

Proposed connections are downstream of IBI contemplated connections. Population is less than included in servicing brief. Therefore, we do not expect servicing issues with Block 15.

Block 22:

IBI Servicing Brief ~ 105p (note that I am interpolating since half of Block 22 is included in northern half of Block 24.)

Mattamy Proposal = 52p

IBI servicing brief assumed 52.5p tributary to Moses Tenisco. Therefore, we do not expect capacity issues.

Block 24:

IBI Servicing Brief ~284.4p (note that I am interpolating based on the population shown on phase 1A southern half of block 24).

Mattamy Proposal = 364p

DSEL reviewed the available capacity in the receiving sewers and did not see any capacity issues.

Note: Mattamy's proposed servicing eliminates the need for 63.8m of sanitary sewer on Moses Tennisco from MH213A to MH212A. Savings to CLC.

Stormwater:

I have reviewed Appendix E of the servicing briefs to compare our calculations to the assumptions used in the model.

Review of the Summary of DDSWMM Parameters

Block 15:

IBI Servicing brief: No storage assumed. 5 and 100 year capture 396L/s

Mattamy's proposal: 275m3 of storage provided. DSEL's estimated 5-year peak 357.4L/s

Block 19:

IBI Servicing brief: No storage assumed. 194 + 57 (note that Lot 209 and 208B are missing from chart).

Mattamy's proposal: TBD.

Block 22:

IBI Servicing brief: No storage assumed. 5 and 100 year (46 + 46) 92L/s

Mattamy's proposal: 46.5m3 of storage provided. DSEL's estimated 5-year peak 87L/s.

Block 24:

IBI Servicing brief: No Storage. 5 and 100 year capture (162 +162) 324L/s.

Mattamy's proposal: 27.3m3 of storage provided. DSEL's estimated 5-year peak 325.7L/s.

Let me know if you have any comments or questions. Thank you for your time.

Adam Fobert, P.Eng.
Manager of Site Plan Design

DSEL
david schaeffer engineering ltd.

120 Iber Road, Unit 103
Stittsville, ON K2S 1E9

office: (613) 836-0856
direct: (613) 836-0626
cell: (613) 222-9493
email: afobert@DSEL.ca

This email, including any attachments, is for the sole use of the intended recipient(s) and may contain private, confidential, and privileged information. Any unauthorized review, use, disclosure, or distribution is prohibited. If you are not the intended recipient or if this information has been inappropriately forwarded to you, please contact the sender by reply email and destroy all copies of the original.

Genavieve Greenberg

From: Jim Moffatt <jmoffatt@IBIGroup.com>
Sent: Tuesday, October 1, 2019 11:26 AM
To: Genavieve Greenberg; Ed Ireland; Karlinda Hinds
Cc: Jillian Normand; Adam Fobert
Subject: RE: Wateridge at Rockcliffe Phase 1B Servicing Confirmation (Block 15)

All sewers and watermains in Wateridge Village Phase 1B, including those on Squadron Crescent and downstream, are in service. If you require any further confirmation of Phase 1B services or have other questions about this Phase, just call me.

From: Genavieve Greenberg [mailto:GGreenberg@dsel.ca]
Sent: Friday, September 27, 2019 11:00 AM
To: Jim Moffatt <jmoffatt@IBIGroup.com>; Ed Ireland <ed.ireland@IBIGroup.com>; Karlinda Hinds <Karlinda.Hinds@ibigroup.com>
Cc: Jillian Normand <Jillian.Normand@mattamycorp.com>; Adam Fobert <AFobert@dsel.ca>
Subject: RE: Wateridge at Rockcliffe Phase 1B Servicing Confirmation (Block 15)

Good morning Jim,

We are working on the servicing plan for this block currently.

We have been asked by the City just to obtain confirmation that the services within Squadron Crescent and the rest of Phase 1B are in fact “in service”. Would it be possible to have that confirmed?

Thank you,

Genavieve Greenberg
Project Coordinator/ Junior Designer

DSEL
david schaeffer engineering ltd.

120 Iber Road, Unit 103
Stittsville, ON K2S 1E9

phone: (613) 836-0856 ext. 569
email: ggreenberg@DSEL.ca

This email, including any attachments, is for the sole use of the intended recipient(s) and may contain private, confidential, and privileged information. Any unauthorized review, use, disclosure, or distribution is prohibited. If you are not the intended recipient, or if this information has been inappropriately forwarded to you, please contact the sender by reply email and destroy all copies of the original.

From: Jim Moffatt <jmoffatt@IBIGroup.com>
Sent: Friday, September 27, 2019 10:17 AM
To: Ed Ireland <ed.ireland@IBIGroup.com>; Karlinda Hinds <Karlinda.Hinds@ibigroup.com>
Cc: Genavieve Greenberg <GGreenberg@dsel.ca>
Subject: RE: Wateridge at Rockcliffe Phase 1B Servicing Confirmation (Block 15)

Do we have a plan from Dsel showing the servicing requirements for Block 15. We provided sewer outlets near the north west portion of the site.

From: Ed Ireland
Sent: Friday, September 27, 2019 10:06 AM
To: Jim Moffatt <jmoffatt@IBIGroup.com>; Karlinda Hinds <Karlinda.Hinds@ibigroup.com>
Cc: GGreenberg@dsel.ca
Subject: FW: Wateridge at Rockcliffe Phase 1B Servicing Confirmation (Block 15)

Jim and Karlinda,

Can you email Genavieve the Wateridge files she needs and the construction group must have some correspondence with the City regarding service installation.

Ed

From: Genavieve Greenberg [mailto:GGreenberg@dsel.ca]
Sent: Friday, September 27, 2019 10:00 AM
To: Ed Ireland <ed.ireland@IBIGroup.com>
Subject: Wateridge at Rockcliffe Phase 1B Servicing Confirmation (Block 15)

Good morning Ed,

We have been requested by the City to obtain correspondence to confirm that the surrounding services for the proposed development are in service. Would you be able to provide confirmation that all of Wateridge Village at Rockcliffe Phase 1B are in service. Would you be able to confirm this for us?

I was also wondering if you might be able to send the most recent drawings for Phase 1B and if possible CAD for the Ponding Plan, Drawing No. 751.

I will give you a call this morning to discuss these items. If you have any questions at all please feel free to reach out to me.

Thank you,

Genavieve Greenberg
Project Coordinator/ Junior Designer

DSEL
david schaeffer engineering ltd.

120 Iber Road, Unit 103
Stittsville, ON K2S 1E9

phone: (613) 836-0856 ext. 569
email: ggreenberg@DSEL.ca

This email, including any attachments, is for the sole use of the intended recipient(s) and may contain private, confidential, and privileged information. Any unauthorized review, use, disclosure, or distribution is prohibited. If you are not the intended recipient, or if this information has been inappropriately forwarded to you, please contact the sender by reply email and destroy all copies of the original.

Genavieve Greenberg

From: Genavieve Greenberg
Sent: Friday, November 29, 2019 3:56 PM
To: Genavieve Greenberg
Subject: FW: Wateridge at Rockcliffe Phase 1B Servicing Confirmation (Block 15)

From: Shagha Attar [mailto:shagha.attar@ibigroup.com]
Sent: Wednesday, November 13, 2019 4:08 PM
To: Steve Merrick <SMerrick@dsel.ca>
Cc: Jim Moffatt <jmoffatt@IBIGroup.com>
Subject: RE: Wateridge at Rockcliffe Phase 1B Servicing Confirmation (Block 15)

Hi Steve,

As summarized in Table 5-6, and 5-7 of the IBI report "Design Brief Wateridge Village at Rockcliffe Phase 1B, June 2017", the maximum ponding depth including the cascading depth for area S218 was 0.25m and 0.26m for the 100 year and 100 year + 20% increase, respectively.
Due to the current CB relocation, the depth of ponding has been increased by 5 cm. However, it is still below the maximum allowable ponding depth and it allows for dynamic conveyance during the storm events.

Regards,

Shagha Attar P.ENG.

Water Resources Engineer

IBI GROUP
Suite 400, 333 Preston Street
Ottawa ON K1S 5N4 Canada
tel +1 613 225 1311 ext 64063 fax +1 613 225 9868

NOTE: This email message/attachments may contain privileged and confidential information. If received in error, please notify the sender and delete this e-mail message.
NOTE: Ce courriel peut contenir de l'information privilégiée et confidentielle. Si vous avez recu ce message par erreur, veuillez le mentionner immédiatement à l'expéditeur et effacer ce courriel.

From: Shagha Attar
Sent: Wednesday, November 13, 2019 1:31 PM
To: SMerrick@dsel.ca
Subject: RE: Wateridge at Rockcliffe Phase 1B Servicing Confirmation (Block 15)

Hi Steve,


Sorry for the late reply. I was away for couple of weeks.
Can you inform with the increase of 5cm in the depth of ponding, what is the current ponding volume?

Thanks!

Shagha Attar P.ENG.

Water Resources Engineer

IBI GROUP
Suite 400, 333 Preston Street
Ottawa ON K1S 5N4 Canada
tel +1 613 225 1311 ext 64063 fax +1 613 225 9868





NOTE: This email message/attachments may contain privileged and confidential information. If received in error, please notify the sender and delete this e-mail message.
NOTE: Ce courriel peut contenir de l'information privilégiée et confidentielle. Si vous avez recu ce message par erreur, veuillez le mentionner immédiatement à l'expéditeur et effacer ce courriel.

From: Steve Merrick [mailto:SMerrick@dsel.ca]
Sent: Tuesday, November 12, 2019 9:42 AM
To: Jim Moffatt <jmoffatt@IBIGroup.com>
Subject: RE: Wateridge at Rockcliffe Phase 1B Servicing Confirmation (Block 15)

Thank you Jim, can I get something back from IBI today to send to the City?

Thanks!

Steve Merrick, P.Eng.
Project Manager / Intermediate Designer

DSEL
david schaeffer engineering ltd.

120 Iber Road, Unit 103
Stittsville, ON K2S 1E9

phone: (613) 836-0856 ext. 561
cell: (613) 222-7816
email: smerrick@DSEL.ca

This email, including any attachments, is for the sole use of the intended recipient(s) and may contain private, confidential, and privileged information. Any unauthorized review, use, disclosure, or distribution is prohibited. If you are not the intended recipient, or if this information has been inappropriately forwarded to you, please contact the sender by reply email and destroy all copies of the original.

From: Jim Moffatt [mailto:jmoffatt@IBIGroup.com]
Sent: Tuesday, November 5, 2019 1:58 PM
To: Steve Merrick <SMerrick@dsel.ca>
Subject: RE: Wateridge at Rockcliffe Phase 1B Servicing Confirmation (Block 15)

I have passed this along to our SWM designer. She is out returning to office on Monday next.

From: Steve Merrick [mailto:SMerrick@dsel.ca]
Sent: Tuesday, November 5, 2019 11:01 AM
To: Jim Moffatt <jmoffatt@IBIGroup.com>; Marian Milne <mmilne@IBIGroup.com>
Cc: Genavieve Greenberg <GGreenberg@dsel.ca>
Subject: RE: Wateridge at Rockcliffe Phase 1B Servicing Confirmation (Block 15)

Hi Jim,

We received our final round of comments from the City on our application for Block 15. We are proposing to relocate 3 CB within Squadron to avoid driveways/site entrances. We will need something from IBI to confirm that this will not have a negative impact on the SWM.

The CB relocated at the north-west corner of the site is not located at a low point, therefore, no re-grading is required. The CB's located at the south-east have been relocated and some re-grading is required. The depth of ponding at the CB's has now increased by 5cm. We will need IBI to review this change and get back to us on their acceptance. I have attached our servicing and grading plans and bubbled the CB locations discussed above.

We are trying to get our submission back into the City as soon as possible and will require email correspondence from IBI to do so. Can you provide a respond today or tomorrow on this?

Thanks,


Steve Merrick, P.Eng.
Project Manager / Intermediate Designer

DSEL
david schaeffer engineering ltd.

120 Iber Road, Unit 103
Stittsville, ON K2S 1E9


phone: (613) 836-0856 ext. 561
cell: (613) 222-7816
email: smerrick@DSEL.ca

This email, including any attachments, is for the sole use of the intended recipient(s) and may contain private, confidential, and privileged information. Any unauthorized review, use, disclosure, or distribution is prohibited. If you are not the intended recipient, or if this information has been inappropriately forwarded to you, please contact the sender by reply email and destroy all copies of the original.


MIKINAK ROAD
SQUADRON CRESCENT
TAKAMOSE PRIVATE
MAKWA PRIVATE
PRIVATE LANE
KINIW PRIVATE
CROISSANT SQUADRON CRESCENT
BLOCK 1
BLOCK 2
BLOCK 3
BLOCK 4
BLOCK 5
BLOCK 6
BLOCK 7
BLOCK 8 SOG
BLOCK 9 SOG
BLOCK 10 SOG
BLOCK 11 SOG
BLOCK 12 SOG
BLOCK 13 SOG
BLOCK 14 SOG
BLOCK 121
PART 100
PART 101
PART 102
PART 103
PART 104
PART 105
PART 106
PART 107
PART 108
PART 109
PART 110
PART 111
PART 112
PART 113
PART 114
PART 115
PART 116
PART 117
PART 118
PART 119
PART 120
PART 121
PART 122
PART 123
PART 124
PART 125
PART 126
PART 127
PART 128
PART 129
PART 130
PART 131
PART 132
PART 133
PART 134
PART 135
PART 136
PART 137
PART 138
PART 139
PART 140
PART 141
PART 142
PART 143
PART 144
PART 145
PART 146
PART 147
PART 148
PART 149
PART 150
PART 151
PART 152
PART 153
PART 154
PART 155
PART 156
PART 157
PART 158
PART 159
PART 160
PART 161
PART 162
PART 163
PART 164
PART 165
PART 166
PART 167
PART 168
PART 169
PART 170
PART 171
PART 172
PART 173
PART 174
PART 175
PART 176
PART 177
PART 178
PART 179
PART 180
PART 181
PART 182
PART 183
PART 184
PART 185
PART 186
PART 187
PART 188
PART 189
PART 190
PART 191
PART 192
PART 193
PART 194
PART 195
PART 196
PART 197
PART 198
PART 199
PART 200
PART 201
PART 202
PART 203
PART 204
PART 205
PART 206
PART 207
PART 208
PART 209
PART 210
PART 211
PART 212
PART 213
PART 214
PART 215
PART 216
PART 217
PART 218
PART 219
PART 220
PART 221
PART 222
PART 223
PART 224
PART 225
PART 226
PART 227
PART 228
PART 229
PART 230
PART 231
PART 232
PART 233
PART 234
PART 235
PART 236
PART 237
PART 238
PART 239
PART 240
PART 241
PART 242
PART 243
PART 244
PART 245
PART 246
PART 247
PART 248
PART 249
PART 250
PART 251
PART 252
PART 253
PART 254
PART 255
PART 256
PART 257
PART 258
PART 259
PART 260
PART 261
PART 262
PART 263
PART 264
PART 265
PART 266
PART 267
PART 268
PART 269
PART 270
PART 271
PART 272
PART 273
PART 274
PART 275
PART 276
PART 277
PART 278
PART 279
PART 280
PART 281
PART 282
PART 283
PART 284
PART 285
PART 286
PART 287
PART 288
PART 289
PART 290
PART 291
PART 292
PART 293
PART 294
PART 295
PART 296
PART 297
PART 298
PART 299
PART 300
PART 301
PART 302
PART 303
PART 304
PART 305
PART 306
PART 307
PART 308
PART 309
PART 310
PART 311
PART 312
PART 313
PART 314
PART 315
PART 316
PART 317
PART 318
PART 319
PART 320
PART 321
PART 322
PART 323
PART 324
PART 325
PART 326
PART 327
PART 328
PART 329
PART 330
PART 331
PART 332
PART 333
PART 334
PART 335
PART 336
PART 337
PART 338
PART 339
PART 340
PART 341
PART 342
PART 343
PART 344
PART 345
PART 346
PART 347
PART 348
PART 349
PART 350
PART 351
PART 352
PART 353
PART 354
PART 355
PART 356
PART 357
PART 358
PART 359
PART 360
PART 361
PART 362
PART 363
PART 364
PART 365
PART 366
PART 367
PART 368
PART 369
PART 370
PART 371
PART 372
PART 373
PART 374
PART 375
PART 376
PART 377
PART 378
PART 379
PART 380
PART 381
PART 382
PART 383
PART 384
PART 385
PART 386
PART 387
PART 388
PART 389
PART 390
PART 391
PART 392
PART 393
PART 394
PART 395
PART 396
PART 397
PART 398
PART 399
PART 400
PART 401
PART 402
PART 403
PART 404
PART 405
PART 406
PART 407
PART 408
PART 409
PART 410
PART 411
PART 412
PART 413
PART 414
PART 415
PART 416
PART 417
PART 418
PART 419
PART 420
PART 421
PART 422
PART 423
PART 424
PART 425
PART 426
PART 427
PART 428
PART 429
PART 430
PART 431
PART 432
PART 433
PART 434
PART 435
PART 436
PART 437
PART 438
PART 439
PART 440
PART 441
PART 442
PART 443
PART 444
PART 445
PART 446
PART 447
PART 448
PART 449
PART 450
PART 451
PART 452
PART 453
PART 454
PART 455
PART 456
PART 457
PART 458
PART 459
PART 460
PART 461
PART 462
PART 463
PART 464
PART 465
PART 466
PART 467
PART 468
PART 469
PART 470
PART 471
PART 472
PART 473
PART 474
PART 475
PART 476
PART 477
PART 478
PART 479
PART 480
PART 481
PART 482
PART 483
PART 484
PART 485
PART 486
PART 487
PART 488
PART 489
PART 490
PART 491
PART 492
PART 493
PART 494
PART 495
PART 496
PART 497
PART 498
PART 499
PART 500
PART 501
PART 502
PART 503
PART 504
PART 505
PART 506
PART 507
PART 508
PART 509
PART 510
PART 511
PART 512
PART 513
PART 514
PART 515
PART 516
PART 517
PART 518
PART 519
PART 520
PART 521
PART 522
PART 523
PART 524
PART 525
PART 526
PART 527
PART 528
PART 529
PART 530
PART 531
PART 532
PART 533
PART 534
PART 535
PART 536
PART 537
PART 538
PART 539
PART 540
PART 541
PART 542
PART 543
PART 544
PART 545
PART 546
PART 547
PART 548
PART 549
PART 550
PART 551
PART 552
PART 553
PART 554
PART 555
PART 556
PART 557
PART 558
PART 559
PART 560
PART 561
PART 562
PART 563
PART 564
PART 565
PART 566
PART 567
PART 568
PART 569
PART 570
PART 571
PART 572
PART 573
PART 574
PART 575
PART 576
PART 577
PART 578
PART 579
PART 580
PART 581
PART 582
PART 583
PART 584
PART 585
PART 586
PART 587
PART 588
PART 589
PART 590
PART 591
PART 592
PART 593
PART 594
PART 595
PART 596
PART 597
PART 598
PART 599
PART 600
PART 601
PART 602
PART 603
PART 604
PART 605
PART 606
PART 607
PART 608
PART 609
PART 610
PART 611
PART 612
PART 613
PART 614
PART 615
PART 616
PART 617
PART 618
PART 619
PART 620
PART 621
PART 622
PART 623
PART 624
PART 625
PART 626
PART 627
PART 628
PART 629
PART 630
PART 631
PART 632
PART 633
PART 634
PART 635
PART 636
PART 637
PART 638
PART 639
PART 640
PART 641
PART 642
PART 643
PART 644
PART 645
PART 646
PART 647
PART 648
PART 649
PART 650
PART 651
PART 652
PART 653
PART 654
PART 655
PART 656
PART 657
PART 658
PART 659
PART 660
PART 661
PART 662
PART 663
PART 664
PART 665
PART 666
PART 667
PART 668
PART 669
PART 670
PART 671
PART 672
PART 673
PART 674
PART 675
PART 676
PART 677
PART 678
PART 679
PART 680
PART 681
PART 682
PART 683
PART 684
PART 685
PART 686
PART 687
PART 688
PART 689
PART 690
PART 691
PART 692
PART 693
PART 694
PART 695
PART 696
PART 697
PART 698
PART 699
PART 700
PART 701
PART 702
PART 703
PART 704
PART 705
PART 706
PART 707
PART 708
PART 709
PART 710
PART 711
PART 712
PART 713
PART 714
PART 715
PART 716
PART 717
PART 718
PART 719
PART 720
PART 721
PART 722
PART 723
PART 724
PART 725
PART 726
PART 727
PART 728
PART 729
PART 730
PART 731
PART 732
PART 733
PART 734
PART 735
PART 736
PART 737
PART 738
PART 739
PART 740
PART 741
PART 742
PART 743
PART 744
PART 745
PART 746
PART 747
PART 748
PART 749
PART 750
PART 751
PART 752
PART 753
PART 754
PART 755
PART 756
PART 757
PART 758
PART 759
PART 760
PART 761
PART 762
PART 763
PART 764
PART 765
PART 766
PART 767
PART 768
PART 769
PART 770
PART 771
PART 772
PART 773
PART 774
PART 775
PART 776
PART 777
PART 778
PART 779
PART 780
PART 781
PART 782
PART 783
PART 784
PART 785
PART 786
PART 787
PART 788
PART 789
PART 790
PART 791
PART 792
PART 793
PART 794
PART 795
PART 796
PART 797
PART 798
PART 799
PART 800
PART 801
PART 802
PART 803
PART 804
PART 805
PART 806
PART 807
PART 808
PART 809
PART 810
PART 811
PART 812
PART 813
PART 814
PART 815
PART 816
PART 817
PART 818
PART 819
PART 820
PART 821
PART 822
PART 823
PART 824
PART 825
PART 826
PART 827
PART 828
PART 829
PART 830
PART 831
PART 832
PART 833
PART 834
PART 835
PART 836
PART 837
PART 838
PART 839
PART 840
PART 841
PART 842
PART 843
PART 844
PART 845
PART 846
PART 847
PART 848
PART 849
PART 850
PART 851
PART 852
PART 853
PART 854
PART 855
PART 856
PART 857
PART 858
PART 859
PART 860
PART 861
PART 862
PART 863
PART 864
PART 865
PART 866
PART 867
PART 868
PART 869
PART 870
PART 871
PART 872
PART 873
PART 874
PART 875
PART 876
PART 877
PART 878
PART 879
PART 880
PART 881
PART 882
PART 883
PART 884
PART 885
PART 886
PART 887
PART 888
PART 889
PART 890
PART 891
PART 892
PART 893
PART 894
PART 895
PART 896
PART 897
PART 898
PART 899
PART 900
PART 901
PART 902
PART 903
PART 904
PART 905
PART 906
PART 907
PART 908
PART 909
PART 910
PART 911
PART 912
PART 913
PART 914
PART 915
PART 916
PART 917
PART 918
PART 919
PART 920
PART 921
PART 922
PART 923
PART 924
PART 925
PART 926
PART 927
PART 928
PART 929
PART 930
PART 931
PART 932
PART 933
PART 934
PART 935
PART 936
PART 937
PART 938
PART 939
PART 940
PART 941
PART 942
PART 943
PART 944
PART 945
PART 946
PART 947
PART 948
PART 949
PART 950
PART 951
PART 952
PART 953
PART 954
PART 955
PART 956
PART 957
PART 958
PART 959
PART 960
PART 961
PART 962
PART 963
PART 964
PART 965
PART 966
PART 967
PART 968
PART 969
PART 970
PART 971
PART 972
PART 973
PART 974
PART 975
PART 976
PART 977
PART 978
PART 979
PART 980
PART 981
PART 982
PART 983
PART 984
PART 985
PART 986
PART 987
PART 988
PART 989
PART 990
PART 991
PART 992
PART 993
PART 994
PART 995
PART 996
PART 997
PART 998
PART 999
PART 1000
PART 1001
PART 1002
PART 1003
PART 1004
PART 1005
PART 1006
PART 1007
PART 1008
PART 1009
PART 1010
PART 1011
PART 1012
PART 1013
PART 1014
PART 1015
PART 1016
PART 1017
PART 1018
PART 1019
PART 1020
PART 1021
PART 1022
PART 1023
PART 1024
PART 1025
PART 1026
PART 1027
PART 1028
PART 1029
PART 1030
PART 1031
PART 1032
PART 1033
PART 1034
PART 1035
PART 1036
PART 1037
PART 1038
PART 1039
PART 1040
PART 1041
PART 1042
PART 1043
PART 1044
PART 1045
PART 1046
PART 1047
PART 1048
PART 1049
PART 1050
PART 1051
PART 1052
PART 1053
PART 1054
PART 1055
PART 1056
PART 1057
PART 1058
PART 1059
PART 1060
PART 1061
PART 1062
PART 1063
PART 1064
PART 1065
PART 1066
PART 1067
PART 1068
PART 1069
PART 1070
PART 1071
PART 1072
PART 1073
PART 1074
PART 1075
PART 1076
PART 1077
PART 1078
PART 1079
PART 1080
PART 1081
PART 1082
PART 1083
PART 1084
PART 1085
PART 1086
PART 1087
PART 1088
PART 1089
PART 1090
PART 1091
PART 1092
PART 1093
PART 1094
PART 1095
PART 1096
PART 1097
PART 1098
PART 1099
PART 1100
PART 1101
PART 1102
PART 1103
PART 1104
PART 1105
PART 1106
PART 1107
PART 1108
PART 1109
PART 1110
PART 1111
PART 1112
PART 1113
PART 1114
PART 1115
PART 1116
PART 1117
PART 1118
PART 1119
PART 1120
PART 1121
PART 1122
PART 1123
PART 1124
PART 1125
PART 1126
PART 1127
PART 1128
PART 1129
PART 1130
PART 1131
PART 1132
PART 1133
PART 1134
PART 1135
PART 1136
PART 1137
PART 1138
PART 1139
PART 1140
PART 1141
PART 1142
PART 1143
PART 1144
PART 1145
PART 1146
PART 1147
PART 1148
PART 1149
PART 1150
PART 1151
PART 1152
PART 1153
PART 1154
PART 1155
PART 1156
PART 1157
PART 1158
PART 1159
PART 1160
PART 1161
PART 1162
PART 1163
PART 1164
PART 1165
PART 1166
PART 1167
PART 1168
PART 1169
PART 1170
PART 1171
PART 1172
PART 1173
PART 1174
PART 1175
PART 1176
PART 1177
PART 1178
PART 1179
PART 1180
PART 1181
PART 1182
PART 1183
PART 1184
PART 1185
PART 1186
PART 1187
PART 1188
PART 1189
PART 1190
PART 1191
PART 1192
PART 1193
PART 1194
PART 1195
PART 1196
PART 1197
PART 1198
PART 1199
PART 1200
PART 1201
PART 1202
PART 1203
PART 1204
PART 1205
PART 1206
PART 1207
PART 1208
PART 1209
PART 1210
PART 1211
PART 1212
PART 1213
PART 1214
PART 1215
PART 1216
PART 1217
PART 1218
PART 1219
PART 1220
PART 1221
PART 1222
PART 1223
PART 1224
PART 1225
PART 1226
PART 1227
PART 1228
PART 1229
PART 1230
PART 1231
PART 1232
PART 1233
PART 1234
PART 1235
PART 1236
PART 1237
PART 1238
PART 1239
PART 1240
PART 1241
PART 1242
PART 1243
PART 1244
PART 1245
PART 1246
PART 1247
PART 1248
PART 1249
PART 1250
PART 1251
PART 1252
PART 1253
PART 1254
PART 1255
PART 1256
PART 1257
PART 1258
PART 1259
PART 1260
PART 1261
PART 1262
PART 1263
PART 1264
PART 1265
PART 1266
PART 1267
PART 1268
PART 1269
PART 1270
PART 1271
PART 1272
PART 1273
PART 1274
PART 1275
PART 1276
PART 1277
PART 1278
PART 1279
PART 1280
PART 1281
PART 1282
PART 1283
PART 1284
PART 1285
PART 1286
PART 1287
PART 1288
PART 1289
PART 1290
PART 1291
PART 1292
PART 1293
PART 1294
PART 1295
PART 1296
PART 1297
PART 1298
PART 1299
PART 1300
PART 1301
PART 1302
PART 1303
PART 1304
PART 1305
PART 1306
PART 1307
PART 1308
PART 1309
PART 1310
PART 1311
PART 1312
PART 1313
PART 1314
PART 1315
PART 1316
PART 1317
PART 1318
PART 1319
PART 1320
PART 1321
PART 1322
PART 1323
PART 1324
PART 1325
PART 1326
PART 1327
PART 1328
PART 1329
PART 1330
PART 1331
PART 1332
PART 1333
PART 1334
PART 1335
PART 1336
PART 1337
PART 1338
PART 1339
PART 1340
PART 1341
PART 1342
PART 1343
PART 1344
PART 1345
PART 1346
PART 1347
PART 1348
PART 1349
PART 1350
PART 1351
PART 1352
PART 1353
PART 1354
PART 1355
PART 1356
PART 1357
PART 1358
PART 1359
PART 1360
PART 1361
PART 1362
PART 1363
PART 1364
PART 1365
PART 1366
PART 1367
PART 1368
PART 1369
PART 1370
PART 1371
PART 1372
PART 1373
PART 1374
PART 1375
PART 1376
PART 1377
PART 1378
PART 1379
PART 1380
PART 1381
PART 1382
PART 1383
PART 1384
PART 1385
PART 1386
PART 1387
PART 1388
PART 1389
PART 1390
PART 1391
PART 1392
PART 1393
PART 1394
PART 1395
PART 1396
PART 1397
PART 1398
PART 1399
PART 1400
PART 1401
PART 1402
PART 1403
PART 1404
PART 1405
PART 1406
PART 1407
PART 1408
PART 1409
PART 1410
PART 1411
PART 1412
PART 1413
PART 1414
PART 1415
PART 1416
PART 1417
PART 1418
PART 1419
PART 1420
PART 1421
PART 1422
PART 1423
PART 1424
PART 1425
PART 1426
PART 1427
PART 1428
PART 1429
PART 1430
PART 1431
PART 1432
PART 1433
PART 1434
PART 1435
PART 1436
PART 1437
PART 1438
PART 1439
PART 1440
PART 1441
PART 1442
PART 1443
PART 1444
PART 1445
PART 1446
PART 1447
PART 1448
PART 1449
PART 1450
PART 1451
PART 1452
PART 1453
PART 1454
PART 1455
PART 1456
PART 1457
PART 1458
PART 1459
PART 1460
PART 1461
PART 1462
PART 1463
PART 1464
PART 1465
PART 1466
PART 1467
PART 1468
PART 1469
PART 1470
PART 1471
PART 1472
PART 1473
PART 1474
PART 1475
PART 1476
PART 1477
PART 1478
PART 1479
PART 1480
PART 1481
PART 1482
PART 1483
PART 1484
PART 1485
PART 1486
PART 1487
PART 1488
PART 1489
PART 1490
PART 1491
PART 1492
PART 1493
PART 1494
PART 1495
PART 1496
PART 1497
PART 1498
PART 1499
PART 1500
PART 1501
PART 1502
PART 1503
PART 1504
PART 1505
PART 1506
PART 1507
PART 1508
PART 1509
PART 1510
PART 1511
PART 1512
PART 1513
PART 1514
PART 1515
PART 1516
PART 1517
PART 1518
PART 1519
PART 1520
PART 1521
PART 1522
PART 1523
PART 1524
PART 1525
PART 1526
PART 1527
PART 1528
PART 1529
PART 1530
PART 1531
PART 1532
PART 1533
PART 1534
PART 1535
PART 1536
PART 1537
PART 1538
PART 1539
PART 1540
PART 1541
PART 1542
PART 1543
PART 1544
PART 1545
PART 1546
PART 1547
PART 1548
PART 1549
PART 1550
PART 1551
PART 1552
PART 1553
PART 1554
PART 1555
PART 1556
PART 1557
PART 1558
PART 1559
PART 1560
PART 1561
PART 1562
PART 1563
PART 1564
PART 1565
PART 1566
PART 1567
PART 1568
PART 1569
PART 1570
PART 1571
PART 1572
PART 1573
PART 1574
PART 1575
PART 1576
PART 1577
PART 1578
PART 1579
PART 1580
PART 1581
PART 1582
PART 1583
PART 1584
PART 1585
PART 1586
PART 1587
PART 1588
PART 1589
PART 1590
PART 1591
PART 1592
PART 1593
PART 1594
PART 1595
PART 1596
PART 1597
PART 1598
PART 1599
PART 1600
PART 1601
PART 1602
PART 1603
PART 1604
PART 1605
PART 1606
PART 1607
PART 1608
PART 1609
PART 1610
PART 1611
PART 1612
PART 1613
PART 1614
PART 1615
PART 1616
PART 1617
PART 1618
PART 1619
PART 1620
PART 1621
PART 1622
PART 1623
PART 1624
PART 1625
PART 1626
PART 1627
PART 1628
PART 1629
PART 1630
PART 1631
PART 1632
PART 1633
PART 1634
PART 1635
PART 1636
PART 1637
PART 1638
PART 1639
PART 1640
PART 1641
PART 1642
PART 1643
PART 1644
PART 1645
PART 1646
PART 1647
PART 1648
PART 1649
PART 1650
PART 1651
PART 1652
PART 1653
PART 1654
PART 1655
PART 1656
PART 1657
PART 1658
PART 1659
PART 1660
PART 1661
PART 1662
PART 1663
PART 1664
PART 1665
PART 1666
PART 1667
PART 1668
PART 1669
PART 1670
PART 1671
PART 1672
PART 1673
PART 1674
PART 1675
PART 1676
PART 1677
PART 1678
PART 1679
PART 1680
PART 1681
PART 1682
PART 1683
PART 1684
PART 1685
PART 1686
PART 1687
PART 1688
PART 1689
PART 1690
PART 1691
PART 1692
PART 1693
PART 1694
PART 1695
PART 1696
PART 1697
PART 1698
PART 1699
PART 1700
PART 1701
PART 1702
PART 1703
PART 1704
PART 1705
PART 1706
PART 1707
PART 1708
PART 1709
PART 1710
PART 1711
PART 1712
PART 1713
PART 1714
PART 1715
PART 1716
PART 1717
PART 1718
PART 1719
PART 1720
PART 1721
PART 1722
PART 1723
PART 1724
PART 1725
PART 1726
PART 1727
PART 1728
PART 1729
PART 1730
PART 1731
PART 1732
PART 1733
PART 1734
PART 1735
PART 1736
PART 1737
PART 1738
PART 1739
PART 1740
PART 1741
PART 1742
PART 1743
PART 1744
PART 1745
PART 1746
PART 1747
PART 1748
PART 1749
PART 1750
PART 1751
PART 1752
PART 1753
PART 1754
PART 1755
PART 1756
PART 1757
PART 1758
PART 1759
PART 1760
PART 1761
PART 1762
PART 1763
PART 1764
PART 1765
PART 1766
PART 1767
PART 1768
PART 1769
PART 1770
PART 1771
PART 1772
PART 1773
PART 1774
PART 1775
PART 1776
PART 1777
PART 1778
PART 1779
PART 1780
PART 1781
PART 1782
PART 1783
PART 1784
PART 1785
PART 1786
PART 1787
PART 1788
PART 1789
PART 1790
PART 1791
PART 1792
PART 1793
PART 1794
PART 1795
PART 1796
PART 1797
PART 1798
PART 1799
PART 1800
PART 1801
PART 1802
PART 1803
PART 1804
PART 1805
PART 1806
PART 1807
PART 1808
PART 1809
PART 1810
PART 1811
PART 1812
PART 1813
PART 1814
PART 1815
PART 1816
PART 1817
PART 1818
PART 1819
PART 1820
PART 1821
PART 1822
PART 1823
PART 1824
PART 1825
PART 1826
PART 1827
PART 1828
PART 1829
PART 1830
PART 1831
PART 1832
PART 1833
PART 1834
PART 1835
PART 1836
PART 1837
PART 1838
PART 1839
PART 1840
PART 1841
PART 1842
PART 1843
PART 1844
PART 1845
PART 1846
PART 1847
PART 1848
PART 1849
PART 1850
PART 1851
PART 1852
PART 1853
PART 1854
PART 1855
PART 1856
PART 1857
PART 1858
PART 1859
PART 1860
PART 1861
PART 1862
PART 1863
PART 1864
PART 1865
PART 1866
PART 1867
PART 1868
PART 1869
PART 1870
PART 1871
PART 1872
PART 1873
PART 1874
PART 1875
PART 1876
PART 1877
PART 1878
PART 1879
PART 1880
PART 1881
PART 1882
PART 1883
PART 1884
PART 1885
PART 1886
PART 1887
PART 1888
PART 1889
PART 1890
PART 1891
PART 1892
PART 1893
PART 1894
PART 1895
PART 1896
PART 1897
PART 1898
PART 1899
PART 1900
PART 1901
PART 1902
PART 1903
PART 1904
PART 1905
PART 1906
PART 1907
PART 1908
PART 1909
PART 1910
PART 1911
PART 1912
PART 1913
PART 1914
PART 1915
PART 1916
PART 1917
PART 1918
PART 1919
PART 1920
PART 1921
PART 1922
PART 1923
PART 1924
PART 1925
PART 1926
PART 1927
PART 1928
PART 1929
PART 1930
PART 1931
PART 1932
PART 1933
PART 1934
PART 1935
PART 1936
PART 1937
PART 1938
PART 1939
PART 1940
PART 1941
PART 1942
PART 1943
PART 1944
PART 1945
PART 1946
PART 1947
PART 1948
PART 1949
PART 1950
PART 1951
PART 1952
PART 1953
PART 1954
PART 1955
PART 1956
PART 1957
PART 1958
PART 1959
PART 1960
PART 1961
PART 1962
PART 1963
PART 1964
PART 1965
PART 1966
PART 1967
PART 1968
PART 1969
PART 1970
PART 1971
PART 1972
PART 1973
PART 1974
PART 1975
PART 1976
PART 1977
PART 1978
PART 1979
PART 1980
PART 1981
PART 1982
PART 1983
PART 1984
PART 1985
PART 1986
PART 1987
PART 1988
PART 1989
PART 1990
PART 1991
PART 1992
PART 1993
PART 1994
PART 1995
PART 1996
PART 1997
PART 1998
PART 1999
PART 2000
PART 2001
PART 2002
PART 2003
PART 2004
PART 2005
PART 2006
PART 2007
PART 2008
PART 2009
PART 2010
PART 2011
PART 2012
PART 2013
PART 2014
PART 2015
PART 2016
PART 2017
PART 2018
PART 2019
PART 2020
PART 2021
PART 2022
PART 2023
PART 2024
PART 2025
PART 2026
PART 2027
PART 2028
PART 2029
PART 2030
PART 2031
PART 2032
PART 2033
PART 2034
PART 2035
PART 2036
PART 2037
PART 2038
PART 2039
PART 2040
PART 2041
PART 2042
PART 2043
PART 2044
PART 2045
PART 2046
PART 2047
PART 2048
PART 2049
PART 2050
PART 2051
PART 2052
PART 2053
PART 2054
PART 2055
PART 2056
PART 2057
PART 2058
PART 2059
PART 2060
PART 2061
PART 2062
PART 2063
PART 2064
PART 2065
PART 2066
PART 2067
PART 2068
PART 2069
PART 2070
PART 2071
PART 2072
PART 2073
PART 2074
PART 2075
PART 2076
PART 2077
PART 2078
PART 2079
PART 2080
PART 2081
PART 2082
PART 2083
PART 2084
PART 2085
PART 2086
PART 2087
PART 2088
PART 2089
PART 2090
PART 2091
PART 2092
PART 2093
PART 2094
PART 2095
PART 2096
PART 2097
PART 2098
PART 2099
PART 2100
PART 2101
PART 2102
PART 2103
PART 2104
PART 2105
PART 2106
PART 2107
PART 2108
PART 2109
PART 2110
PART 2111
PART 2112
PART 2113
PART 2114
PART 2115
PART 2116
PART 2117
PART 2118
PART 2119
PART 2120
PART 2121
PART 2122
PART 2123
PART 2124
PART 2125
PART 2126
PART 2127
PART 2128
PART 2129
PART 2130
PART 2131
PART 2132
PART 2133
PART 2134
PART 2135
PART 2136
PART 2137
PART 2138
PART 2139
PART 2140
PART 2141
PART 2142
PART 2143
PART 2144
PART 2145
PART 2146
PART 2147
PART 2148
PART 2149
PART 2150
PART 2151
PART 2152
PART 2153
PART 2154
PART 2155
PART 2156
PART 2157
PART 2158
PART 2159
PART 2160
PART 2161
PART 2162
PART 2163
PART 2164
PART 2165
PART 2166
PART 2167
PART 2168
PART 2169
PART 2170
PART 2171
PART 2172
PART 2173
PART 2174
PART 2175
PART 2176
PART 2177
PART 2178
PART 2179
PART 2180
PART 2181
PART 2182
PART 2183
PART 2184
PART 2185
PART 2186
PART 2187
PART 2188
PART 2189
PART 2190
PART 2191
PART 2192
PART 2193
PART 2194
PART 2195
PART 2196
PART 2197
PART 2198
PART 2199
PART 2200
PART 2201
PART 2202
PART 2203
PART 2204
PART 2205
PART 2206
PART 2207
PART 2208
PART 2209
PART 2210
PART 2211
PART 2212
PART 2213
PART 2214
PART 2215
PART 2216
PART 2217
PART 2218
PART 2219
PART 2220
PART 2221
PART 2222
PART 2223
PART 2224
PART 2225
PART 2226
PART 2227
PART 2228
PART 2229
PART 2230
PART 2231
PART 2232
PART 2233
PART 2234
PART 2235
PART 2236
PART 2237
PART 2238
PART 2239
PART 2240
PART 2241
PART 2242
PART 2243
PART 2244
PART 2245
PART 2246
PART 2247
PART 2248
PART 2249
PART 2250
PART 2251
PART 2252
PART 2253
PART 2254
PART 2255
PART 2256
PART 2257
PART 2258
PART 2259
PART 2260
PART 2261
PART 2262
PART 2263
PART 2264
PART 2265
PART 2266
PART 2267
PART 2268
PART 2269
PART 2270
PART 2271
PART 2272
PART 2273
PART 2274
PART 2275
PART 2276
PART 2277
PART 2278
PART 2279
PART 2280
PART 2281
PART 2282
PART 2283
PART 2284
PART 2285
PART 2286
PART 2287
PART 2288
PART 2289
PART 2290
PART 2291
PART 2292
PART 2293
PART 2294
PART 2295
PART 2296
PART 2297
PART 2298
PART 2299
PART 2300
PART 2301
PART 2302
PART 2303
PART 2304
PART 2305
PART 2306
PART 2307
PART 2308
PART 2309
PART 2310
PART 2311
PART 2312
PART 2313
PART 2314
PART 2315
PART 2316
PART 2317
PART 2318
PART 2319
PART 2320
PART 2321
PART 2322
PART 2323
PART 2324
PART 2325
PART 2326
PART 2327
PART 2328
PART 2329
PART 2330
PART 2331
PART 2332
PART 2333
PART 2334
PART 2335
PART 2336
PART 2337
PART 2338
PART 2339
PART 2340
PART 2341
PART 2342
PART 2343
PART 2344
PART 2345
PART 2346
PART 2347
PART 2348
PART 2349
PART 2350
PART 2351
PART 2352
PART 2353
PART 2354
PART 2355
PART 2356
PART 2357
PART 2358
PART 2359
PART 2360
PART 2361
PART 2362
PART 2363
PART 2364
PART 2365
PART 2366
PART 2367
PART 2368
PART 2369
PART 2370
PART 2371
PART 2372
PART 2373
PART 2374
PART 2375
PART 2376
PART 2377
PART 2378
PART 2379
PART 2380
PART 2381
PART 2382
PART 2383
PART 2384
PART 2385
PART 2386
PART 2387
PART 2388
PART 2389
PART 2390
PART 2391
PART 2392
PART 2393
PART 2394
PART 2395
PART 2396
PART 2397
PART 2398
PART 2399
PART 2400
PART 2401
PART 2402
PART 2403
PART 2404
PART 2405
PART 2406
PART 2407
PART 2408
PART 2409
PART 2410
PART 2411
PART 2412
PART 2413
PART 2414
PART 2415
PART 2416
PART 2417
PART 2418
PART 2419
PART 2420
PART 2421
PART 2422
PART 2423
PART 2424
PART 2425
PART 2426
PART 2427
PART 2428
PART 2429
PART 2430
PART 2431
PART 2432
PART 2433
PART 2434
PART 2435
PART 2436
PART 2437
PART 2438
PART 2439
PART 2440
PART 2441
PART 2442
PART 2443
PART 2444
PART 2445
PART 2446
PART 2447
PART 2448
PART 2449
PART 2450
PART 2451
PART 2452
PART 2453
PART 2454
PART 2455
PART 2456
PART 2457
PART 2458
PART 2459
PART 2460
PART 2461
PART 2462
PART 2463
PART 2464
PART 2465
PART 2466
PART 2467
PART 2468
PART 2469
PART 2470
PART 2471
PART 2472
PART 2473
PART 2474
PART 2475
PART 2476
PART 2477
PART 2478
PART 2479
PART 2480
PART 2481
PART 2482
PART 2483
PART 2484
PART 2485
PART 2486
PART 2487
PART 2488
PART 2489
PART 2490
PART 2491
PART 2492
PART 2493
PART 2494
PART 2495
PART 2496
PART 2497
PART 2498
PART 2499
PART 2500
PART 2501
PART 2502
PART 2503
PART 2504
PART 2505
PART 2506
PART 2507
PART 2508
PART 2509
PART 2510
PART 2511
PART 2512
PART 2513
PART 2514
PART 2515
PART 2516
PART 2517
PART 2518
PART 2519
PART 2520
PART 2521
PART 2522
PART 2523
PART 2524
PART 2525
PART 2526
PART 2527
PART 2528
PART 2529
PART 2530
PART 2531
PART 2532
PART 2533
PART 2534
PART 2535
PART 2536
PART 2537
PART 2538
PART 2539
PART 2540
PART 2541
PART 2542
PART 2543
PART 2544
PART 2545
PART 2546
PART 2547
PART 2548
PART 2549
PART 2550
PART 2551
PART 2552
PART 2553
PART 2554
PART 2555
PART 2556
PART 2557
PART 2558
PART 2559
PART 2560
PART 2561
PART 2562
PART 2563
PART 2564
PART 2565
PART 2566
PART 2567
PART 2568
PART 2569
PART 2570
PART 2571
PART 2572
PART 2573
PART 2574
PART 2575
PART 2576
PART 2577
PART 2578
PART 2579
PART 2580
PART 2581
PART 2582
PART 2583
PART 2584
PART 2585
PART 2586
PART 2587
PART 2588
PART 2589
PART 2590
PART 2591
PART 2592
PART 2593
PART 2594
PART 2595
PART 2596
PART 2597
PART 2598
PART 2599
PART 2600
PART 2601
PART 2602
PART 2603
PART 2604
PART 2605
PART 2606
PART 2607
PART 2608
PART 2609
PART 2610
PART 2611
PART 2612
PART 2613
PART 2614
PART 2615
PART 2616
PART 2617
PART 2618
PART 2619
PART 2620
PART 2621
PART 2622
PART 2623
PART 2624
PART 2625
PART 2626
PART 2627
PART 2628
PART 2629
PART 2630
PART 2631
PART 2632
PART 2633
PART 2634
PART 2635
PART 2636
PART 2637
PART 2638
PART 2639
PART 2640
PART 2641
PART 2642
PART 2643
PART 2644
PART 2645
PART 2646
PART 2647
PART 2648
PART 2649
PART 2650
PART 2651
PART 2652
PART 2653
PART 2654
PART 2655
PART 2656
PART 2657
PART 2658
PART 2659
PART 2660
PART 2661
PART 2662
PART 2663
PART 2664
PART 2665
PART 2666
PART 2667
PART 2668
PART 2669
PART 2670
PART 2671
PART 2672
PART 2673
PART 2674
PART 2675
PART 2676
PART 2677
PART 2678
PART 2679
PART 2680
PART 2681
PART 2682
PART 2683
PART 2684
PART 2685
PART 2686
PART 2687
PART 2688
PART 2689
PART 2690
PART 2691
PART 2692
PART 2693
PART 2694
PART 2695
PART 2696
PART 2697
PART 2698
PART 2699
PART 2700
PART 2701
PART 2702
PART 2703
PART 2704
PART 2705
PART 2706
PART 2707
PART 2708
PART 2709
PART 2710
PART 2711
PART 2712
PART 2713
PART 2714
PART 2715
PART 2716
PART 2717
PART 2718
PART 2719
PART 2720
PART 2721
PART 2722
PART 2723
PART 2724
PART 2725
PART 2726
PART 2727
PART 2728
PART 2729
PART 2730
PART 2731
PART 2732
PART 2733
PART 2734
PART 2735
PART 2736
PART 2737
PART 2738
PART 2739
PART 2740
PART 2741
PART 2742
PART 2743
PART 2744
PART 2745
PART 2746
PART 2747
PART 2748
PART 2749
PART 2750
PART 2751
PART 2752
PART 2753
PART 2754
PART 2755
PART 2756
PART 2757
PART 2758
PART 2759
PART 2760
PART 2761
PART 2762
PART 2763
PART 2764
PART 2765
PART 2766
PART 2767
PART 2768
PART 2769
PART 2770
PART 2771
PART 2772
PART 2773
PART 2774
PART 2775
PART 2776
PART 2777
PART 2778
PART 2779
PART 2780
PART 2781
PART 2782
PART 2783
PART 2784
PART 2785
PART 2786
PART 2787
PART 2788
PART 2789
PART 2790
PART 2791
PART 2792
PART 2793
PART 2794
PART 2795
PART 2796
PART 2797
PART 2798
PART 2799
PART 2800
PART 2801
PART 2802
PART 2803
PART 2804
PART 2805
PART 2806
PART 2807
PART 2808
PART 2809
PART 2810
PART 2811
PART 2812
PART 2813
PART 2814
PART 2815
PART 2816
PART 2817
PART 2818
PART 2819
PART 2820
PART 2821
PART 2822
PART 2823
PART 2824
PART 2825
PART 2826
PART 2827
PART 2828
PART 2829
PART 2830
PART 2831
PART 2832
PART 2833
PART 2834
PART 2835
PART 2836
PART 2837
PART 2838
PART 2839
PART 2840
PART 2841
PART 2842
PART 2843
PART 2844
PART 2845
PART 2846
PART 2847
PART 2848
PART 2849
PART 2850
PART 2851
PART 2852
PART 2853
PART 2854
PART 2855
PART 2856
PART 2857
PART 2858
PART 2859
PART 2860
PART 2861
PART 2862
PART 2863
PART 2864
PART 2865
PART


APPENDIX B

Water Supply


FOREST RIDGE P.S
Ogilvie Rd.
Backup P.S.
ORLEANS RES.
MONTREAL ROAD P.S.
BRITTANY DRIVE P.S.
REET P.S.
MONT
1E
HEMLOCK RD
MONTREAL RD
SUSSEX DR
RAMP
RIDEAU ST
VANIER PKWY
OGILVIE RD
BLAIR RD
ST. JOSEPH BLVD
305mm
406mm
610mm
914mm
1220mm
508mm
P S
B P S

APPENDIX B

- **Figure 4.4 Proposed Pipe alignment and Diameters**
- **Watermain Demand Calculation Sheet**
- **Boundary Conditions**
- **Hydraulic Modeling Results**



J:\32562-RockcliffeRedev\5.0 Drawings\59civil\current\Report Figures\MSS 2015\Section 4\Fig...4.4 Proposed Pipe alignment and Diameters-REV.dwg Layout Name: FIGURE4.4

Stantec

IBI

Project Title	Drawing Title	Sheet No.
FORMER CFB ROCKCLIFFE MASTER SERVICING STUDY	PROPOSED PIPE ALIGNMENT AND DIAMETERS	FIGURE 4.4

IBI GROUP
333 PRESTON STREET
OTTAWA, ON
K1S 5N4

WATERMAIN DEMAND CALCULATION SHEET

PROJECT : FORMER CFB ROCKCLIFFE - PHASE 1B
LOCATION : CITY OF OTTAWA

FILE: 38298.5.7
DATE PRINTED: 29-Jun-16
DESIGN: LE
PAGE: 1 OF 2

NODE	RESIDENTIAL UNITS SF	RESIDENTIAL UNITS SD	RESIDENTIAL UNITS TH	RESIDENTIAL POP'N	NON-RESIDENTIAL INDTRL (ha.)	NON-RESIDENTIAL COMM. (ha.)	NON-RESIDENTIAL INST. (ha.)	AVERAGE DAILY DEMAND (l/s) Res.	AVERAGE DAILY DEMAND (l/s) Non-res.	AVERAGE DAILY DEMAND (l/s) Total	MAXIMUM DAILY DEMAND (l/s) Res.	MAXIMUM DAILY DEMAND (l/s) Non-res.	MAXIMUM DAILY DEMAND (l/s) Total	MAXIMUM HOURLY DEMAND (l/s) Res.	MAXIMUM HOURLY DEMAND (l/s) Non-res.	MAXIMUM HOURLY DEMAND (l/s) Total	FIRE DEMAND (l/min)
PHASE 1B																	
J50				76.0				0.31	0.00	0.31	0.77	0.00	0.77	1.69	0.00	1.69	13,000
J52				146.5				0.59	0.00	0.59	1.48	0.00	1.48	3.26	0.00	3.26	13,000
J54				199.5				0.81	0.00	0.81	2.02	0.00	2.02	4.44	0.00	4.44	13,000
J56							2.49	0.00	1.44	1.44	0.00	2.16	2.16	0.00	3.89	3.89	13,000
J58				319.0				1.29	0.00	1.29	3.23	0.00	3.23	7.11	0.00	7.11	13,000
J60				212.3				0.86	0.00	0.86	2.15	0.00	2.15	4.73	0.00	4.73	13,000
J62				129.0				0.52	0.00	0.52	1.31	0.00	1.31	2.87	0.00	2.87	13,000
J64				367.0				1.49	0.00	1.49	3.72	0.00	3.72	8.18	0.00	8.18	13,000
J66				241.5				0.98	0.00	0.98	2.45	0.00	2.45	5.38	0.00	5.38	13,000
J68				153.5				0.62	0.00	0.62	1.55	0.00	1.55	3.42	0.00	3.42	13,000
J70				160.5				0.65	0.00	0.65	1.63	0.00	1.63	3.58	0.00	3.58	13,000
J72				358.5				1.45	0.00	1.45	3.63	0.00	3.63	7.99	0.00	7.99	13,000
J74						0.90		0.00	0.52	0.52	0.00	0.78	0.78	0.00	1.41	1.41	13,000
J76						0.65		0.00	0.38	0.38	0.00	0.56	0.56	0.00	1.02	1.02	13,000
J78				304.5				1.23	0.00	1.23	3.08	0.00	3.08	6.78	0.00	6.78	13,000
J80				105.0				0.43	0.00	0.43	1.06	0.00	1.06	2.34	0.00	2.34	13,000
J82				260.0				1.05	0.00	1.05	2.63	0.00	2.63	5.79	0.00	5.79	13,000
J84						0.88		0.00	0.51	0.51	0.00	0.76	0.76	0.00	1.38	1.38	13,000
J86						0.45	2.62	0.00	1.78	1.78	0.00	2.66	2.66	0.00	4.80	4.80	13,000
J88						0.95		0.00	0.55	0.55	0.00	0.82	0.82	0.00	1.48	1.48	13,000
TOTALS	**0**	**0**	**0**	**3033**	**0.00**	**3.83**	**5.11**	**12.28**	**5.18**	**17.46**	**30.71**	**7.74**	**38.45**	**67.56**	**13.98**	**81.54**	

ASSUMPTIONS

RESIDENTIAL DENSITIES
- Single Family (SF) 3.4 p / p / u
- Semi Detached (SD) 2.7 p / p / u
- Townhouse (TH) 2.7 p / p / u

AVG. DAILY DEMAND
- Residential 350 l / cap / day
- Institutional 50,000 l / ha / day

MAX. DAILY DEMAND
- Residential 875 l / cap / day
- Institutional 75,000 l / ha / day

MAX. HOURLY DEMAND
- Residential 1,925 l / cap / day
- Institutional 135,000 l / ha / day

FIRE FLOW
- SF, SD & TH 10,000 l / min
- ICI 13,000 l / min

IBI GROUP
333 PRESTON STREET
OTTAWA, ON
K1S 5N4

WATERMAIN DEMAND CALCULATION SHEET

PROJECT : FORMER CFB ROCKCLIFFE - PHASE 1B
LOCATION : CITY OF OTTAWA

FILE: 38298.5.7
DATE PRINTED: 29-Jun-16
DESIGN: LE

NODE	RESIDENTIAL UNITS SF	SD	TH	POP'N	NON-RESIDENTIAL INDTRL (ha.)	COMM. (ha.)	INST. (ha.)	AVERAGE DAILY DEMAND (l/s) Res.	Non-res.	Total	MAXIMUM DAILY DEMAND (l/s) Res.	Non-res.	Total	MAXIMUM HOURLY DEMAND (l/s) Res.	Non-res.	Total	FIRE DEMAND (l/min)
PHASE 1A																	
J01			18	48.6				0.20	0.00	0.20	0.49	0.00	0.49	1.08	0.00	1.08	10,000
J02			11	29.7				0.12	0.00	0.12	0.30	0.00	0.30	0.66	0.00	0.66	10,000
J04		4	9	35.1				0.14	0.00	0.14	0.36	0.00	0.36	0.78	0.00	0.78	10,000
J06		4	3	18.9				0.08	0.00	0.08	0.19	0.00	0.19	0.42	0.00	0.42	10,000
J10	4	6	5	43.3				0.18	0.00	0.18	0.44	0.00	0.44	0.96	0.00	0.96	10,000
J12	8			27.2				0.11	0.00	0.11	0.28	0.00	0.28	0.61	0.00	0.61	10,000
J14	10	2		39.4				0.16	0.00	0.16	0.40	0.00	0.40	0.88	0.00	0.88	10,000
J16	16	4		65.2				0.26	0.00	0.26	0.66	0.00	0.66	1.45	0.00	1.45	10,000
J18	9	2		36.0				0.15	0.00	0.15	0.36	0.00	0.36	0.80	0.00	0.80	10,000
J20	5	6		33.2				0.13	0.00	0.13	0.34	0.00	0.34	0.74	0.00	0.74	10,000
J22	11	6		53.6				0.22	0.00	0.22	0.54	0.00	0.54	1.19	0.00	1.19	10,000
J24	8	4	10	65.0				0.26	0.00	0.26	0.66	0.00	0.66	1.45	0.00	1.45	10,000
J26	4	12	3	54.1				0.22	0.00	0.22	0.55	0.00	0.55	1.21	0.00	1.21	10,000
J28	4	10	9	64.9				0.26	0.00	0.26	0.66	0.00	0.66	1.45	0.00	1.45	10,000
J30	6			20.4				0.08	0.00	0.08	0.21	0.00	0.21	0.45	0.00	0.45	10,000
J32				210.8				0.85	0.00	0.85	2.13	0.00	2.13	4.70	0.00	4.70	13,000
R02	26			88.4				0.36	0.00	0.36	0.90	0.00	0.90	1.97	0.00	1.97	10,000
J34							2.50	0.00	1.45	1.45	0.00	2.17	2.17	0.00	3.91	3.91	13,000
TOTA_S	**111**	**60**	**68**	**934**	**0.00**	**0.00**	**2.50**	3.78	1.45	5.23	**9.47**	**2.17**	**11.64**	**20.80**	**3.91**	**24.71**	

ASSUMPTIONS

RESIDENTIAL DENSITIES
- Single Family (SF) — 3.4 p / p / u
- Semi Detached (SD) — 2.7 p / p / u
- Townhouse (TH) — 2.7 p / p / u

AVG. DAILY DEMAND
- Residential — 350 l / cap / day
- Institutional — 50,000 l / ha / day

MAX. DAILY DEMAND
- Residential — 875 l / cap / day
- Institutional — 75,000 l / ha / day

MAX. HOURLY DEMAND
- Residential — 1.925 l / cap / day
- Institutional — 135,000 l / ha / day

FIRE FLOW
- SF, SD & TH — 10,000 l / min
- ICI — 13,000 l / min

Lance Erion

From: Mottalib, Abdul [Abdul.Mottalib@ottawa.ca]
Sent: Wednesday, June 03, 2015 2:00 PM
To: Lance Erion
Cc: Mottalib, Abdul
Subject: FW: Former CFB Rockcliffe - Request for Watermain Boundary Conditions - Phase 1

Please see below:

Thanks,

Abdul Mottalib, P. Eng.

Sent: June 03, 2015 11:29 AM
To: Mottalib, Abdul
Subject: RE: Former CFB Rockcliffe - Request for Watermain Boundary Conditions - Phase 1

Abdul,

Please note the following:


- Boundary conditions provided below are provided for existing conditions. The MSS for CFB Rockcliffe should be carefully reviewed by the designer to assess future conditions (changes to MTL PZ discharge pressures affecting boundary conditions).
- Upgrades to the MTL PZ pump stations are currently being planned to support the CFB Rockcliffe development. These upgrades must be implemented before subdivision construction to ensure adequate reliability of supply. The Class EA and functional design for the station upgrades are currently being updated. Schedule for design and construction will need to be reviewed by my staff with Construction Services if there is a need to confirm timing.

Codd's Road:
MAX HGL = 147.1m
PKHR = 147.0m
MXDY+Fire (13,000 Lpm) = 139.5m
MXDY+Fire (10,000 Lpm) = 140.0m

Burma Road:
MAX HGL = 147.1m
PKHR = 147.1m
MXDY+Fire (13,000 Lpm) = 140.2m
MXDY+Fire (10,000 Lpm) = 140.4m


Disclaimer: The boundary condition information is based on current operation of the city water distribution system. The computer model simulation is based on the best information available at the time. The operation of the water distribution system can change on a regular basis, resulting in a variation in boundary conditions. The physical properties of watermains deteriorate over time, as such must be assumed in the absence of actual field test data. The variation in physical watermain properties can therefore alter the results of the computer model simulation. Fire Flow analysis is a reflection of available flow in the watermain; there may be additional restrictions that occur between the watermain and the hydrant that the model cannot take into account.

Phase 1B - Node ID's




Date: Wednesday, June 29, 2016

Phase 1B - Pipe Sizes




Date: Wednesday, June 29, 2016

Phase 1B - Pipe ID's




Date: Wednesday, June 29, 2016

Phase 1B - Basic Day (Max HGL) Pressures (kPa) Existing HGL 147.1m




Date: Wednesday, June 29, 2016

Phase 1B - Basic Day (Max HGL) Pressures (kPa) Future HGL 143.0m




Date: Wednesday, June 29, 2016

Phase 1B - Peak Hour Pressures (kPa) Existing HGL 147.0 - 147.1m




Date: Wednesday, June 29, 2016

Phase 1B - Peak Hour Pressures (kPa) Future HGL 142.0m



Date: Wednesday, June 29, 2016

Phase 1B - Max Day Fireflows (l/s) HGL 139.5 - 140.2m



Date: Wednesday, June 29, 2016

Phase 1A - Basic Day (Max HGL) HGL 147.1m - Junction Report

	ID	Demand (L/s)	Elevation (m)	Head (m)	Pressure (kPa)
1	J01	0.20	88.50	147.08	574.06
2	J02	0.12	88.10	147.08	577.94
3	J04	0.14	87.00	147.08	588.71
4	J06	0.08	85.35	147.08	604.87
5	J10	0.18	85.60	147.08	602.41
6	J12	0.11	85.50	147.08	603.39
7	J14	0.16	88.10	147.08	577.91
8	J16	0.26	88.50	147.08	573.99
9	J18	0.15	89.00	147.08	569.09
10	J20	0.13	86.60	147.08	592.61
11	J22	0.22	87.45	147.08	584.28
12	J24	0.26	88.30	147.08	575.95
13	J26	0.22	86.10	147.08	597.52
14	J28	0.26	87.50	147.08	583.80
15	J30	0.08	88.90	147.08	570.07
16	J32	0.85	88.10	147.08	577.93
17	J34	1.45	88.30	147.08	575.97
18	J36	0.00	85.65	147.08	601.93
19	J50	0.31	88.40	147.08	574.98
20	J52	0.59	88.90	147.08	570.08
21	J54	0.81	89.40	147.08	565.18
22	J56	1.44	91.00	147.08	549.51
23	J58	1.29	90.60	147.07	553.41
24	J60	0.86	90.00	147.07	559.29
25	J62	0.52	89.85	147.08	560.78
26	J64	1.49	89.10	147.08	568.12
27	J66	0.98	89.40	147.08	565.18
28	J68	0.62	90.50	147.08	554.40
29	J70	0.65	92.50	147.08	534.81
30	J72	1.45	94.05	147.08	519.62
31	J74	0.52	94.80	147.08	512.30
32	J76	0.38	94.00	147.08	520.14
33	J78	1.23	89.90	147.08	560.28
34	J80	0.43	89.25	147.08	566.65
35	J82	1.05	88.75	147.08	571.55
36	J84	0.51	92.60	147.08	533.87
37	J86	1.78	92.60	147.08	533.89
38	J88	0.55	92.20	147.09	537.86
39	R01	0.00	103.00	147.10	432.13
40	R02	0.36	105.00	147.09	412.46
41	R03	0.00	104.00	147.10	422.33

Phase 1B - Peak Hour Existing HGL 147.0 - 147.1m

	ID	Demand (L/s)	Elevation (m)	Head (m)	Pressure (kPa)
1	J01	1.08	88.50	146.70	570.35
2	J02	0.66	88.10	146.64	573.64
3	J04	0.78	87.00	146.62	584.24
4	J06	0.42	85.35	146.62	600.37
5	J10	0.96	85.60	146.58	597.56
6	J12	0.61	85.50	146.58	598.51
7	J14	0.88	88.10	146.57	573.01
8	J16	1.45	88.50	146.57	569.09
9	J18	0.80	89.00	146.58	564.20
10	J20	0.74	86.60	146.58	587.71
11	J22	1.19	87.45	146.58	579.38
12	J24	1.45	88.30	146.58	571.09
13	J26	1.21	86.10	146.60	592.81
14	J28	1.45	87.50	146.60	579.08
15	J30	0.45	88.90	146.58	565.18
16	J32	4.70	88.10	146.62	573.46
17	J34	3.91	88.30	146.62	571.46
18	J36	0.00	85.65	146.62	597.43
19	J50	1.69	88.40	146.62	570.48
20	J52	3.26	88.90	146.61	565.53
21	J54	4.44	89.40	146.61	560.63
22	J56	3.89	91.00	146.64	545.25
23	J58	7.11	90.60	146.58	548.55
24	J60	4.73	90.00	146.58	554.47
25	J62	2.87	89.85	146.62	556.31
26	J64	8.18	89.10	146.61	563.52
27	J66	5.38	89.40	146.61	560.58
28	J68	3.42	90.50	146.61	549.83
29	J70	3.58	92.50	146.62	530.36
30	J72	7.99	94.05	146.64	515.38
31	J74	1.41	94.80	146.71	508.71
32	J76	1.02	94.00	146.72	516.66
33	J78	6.78	89.90	146.60	555.63
34	J80	2.34	89.25	146.61	562.05
35	J82	5.79	88.75	146.60	566.92
36	J84	1.38	92.60	146.74	530.53
37	J86	4.80	92.60	146.79	531.02
38	J88	1.48	92.20	146.87	535.77
39	R01	0.00	103.00	146.97	430.85
40	R02	1.97	105.00	146.86	410.16
41	R03	0.00	104.00	147.07	422.01

Phase 1B - Peak Hour Future HGL 142.0m - Junction Report

	ID	Demand (L/s)	Elevation (m)	Head (m)	Pressure (kPa)
1	J01	1.08	88.50	141.67	521.02
2	J02	0.66	88.10	141.60	524.24
3	J04	0.78	87.00	141.58	534.83
4	J06	0.42	85.35	141.57	550.95
5	J10	0.96	85.60	141.54	548.15
6	J12	0.61	85.50	141.54	549.10
7	J14	0.88	88.10	141.53	523.59
8	J16	1.45	88.50	141.53	519.67
9	J18	0.80	89.00	141.53	514.79
10	J20	0.74	86.60	141.53	538.30
11	J22	1.19	87.45	141.53	529.97
12	J24	1.45	88.30	141.54	521.68
13	J26	1.21	86.10	141.55	543.39
14	J28	1.45	87.50	141.55	529.67
15	J30	0.45	88.90	141.53	515.76
16	J32	4.70	88.10	141.58	524.04
17	J34	3.91	88.30	141.57	522.04
18	J36	0.00	85.65	141.57	548.01
19	J50	1.69	88.40	141.57	521.02
20	J52	3.26	88.90	141.56	516.05
21	J54	4.44	89.40	141.56	511.15
22	J56	3.89	91.00	141.59	495.71
23	J58	7.11	90.60	141.53	499.05
24	J60	4.73	90.00	141.53	504.97
25	J62	2.87	89.85	141.58	506.89
26	J64	8.18	89.10	141.56	514.05
27	J66	5.38	89.40	141.56	511.11
28	J68	3.42	90.50	141.56	500.35
29	J70	3.58	92.50	141.57	480.85
30	J72	7.99	94.05	141.59	465.84
31	J74	1.41	94.80	141.65	459.09
32	J76	1.02	94.00	141.66	467.03
33	J78	6.78	89.90	141.55	506.15
34	J80	2.34	89.25	141.56	512.58
35	J82	5.79	88.75	141.56	517.46
36	J84	1.38	92.60	141.67	480.88
37	J86	4.80	92.60	141.72	481.33
38	J88	1.48	92.20	141.80	485.99
39	R01	0.00	103.00	141.96	381.81
40	R02	1.97	105.00	141.84	361.01
41	R03	0.00	104.00	141.97	372.06

Basic Day Future HGL 142.0m - Junction Report

	ID	Demand (L/s)	Elevation (m)	Head (m)	Pressure (kPa)
1	J01	0.20	88.50	142.98	533.88
2	J02	0.12	88.10	142.98	537.76
3	J04	0.14	87.00	142.98	548.53
4	J06	0.08	85.35	142.98	564.70
5	J10	0.18	85.60	142.98	562.23
6	J12	0.11	85.50	142.98	563.21
7	J14	0.16	88.10	142.98	537.73
8	J16	0.26	88.50	142.98	533.81
9	J18	0.15	89.00	142.98	528.91
10	J20	0.13	86.60	142.98	552.43
11	J22	0.22	87.45	142.98	544.10
12	J24	0.26	88.30	142.98	535.77
13	J26	0.22	86.10	142.98	557.34
14	J28	0.26	87.50	142.98	543.62
15	J30	0.08	88.90	142.98	529.89
16	J32	0.85	88.10	142.98	537.75
17	J34	1.45	88.30	142.98	535.79
18	J36	0.00	85.65	142.98	561.76
19	J50	0.31	88.40	142.98	534.81
20	J52	0.59	88.90	142.98	529.90
21	J54	0.81	89.40	142.98	525.00
22	J56	1.44	91.00	142.98	509.33
23	J58	1.29	90.60	142.97	513.23
24	J60	0.86	90.00	142.97	519.11
25	J62	0.52	89.85	142.98	520.60
26	J64	1.49	89.10	142.98	527.94
27	J66	0.98	89.40	142.98	525.00
28	J68	0.62	90.50	142.98	514.22
29	J70	0.65	92.50	142.98	494.63
30	J72	1.45	94.05	142.98	479.45
31	J74	0.52	94.80	142.98	472.12
32	J76	0.38	94.00	142.98	479.97
33	J78	1.23	89.90	142.98	520.10
34	J80	0.43	89.25	142.98	526.47
35	J82	1.05	88.75	142.98	531.37
36	J84	0.51	92.60	142.98	493.69
37	J86	1.78	92.60	142.98	493.72
38	J88	0.55	92.20	142.99	497.68
39	R01	0.00	103.00	143.00	391.95
40	R02	0.36	105.00	142.99	372.29
41	R03	0.00	104.00	143.00	382.15

Phase 1B - Max Day + Fire HGL 139.5 - 140.2m - Fireflow Design Report

	ID	Total Demand (L/s)	Critical Node 1 ID	Critical Node 1 Pressure (kPa)	Critical Node 1 Head (m)	Adjusted Fire-Flow (L/s)	Available Flow @Hydrant (L/s)	Critical Node 2 ID	Critical Node 2 Pressure (kPa)	Critcal Node 2 Head (m)	Adjusted Available Flow (L/s)	Design Flow (L/s)
1	J01	167.16	R02	331.32	122.31	1,121.92	1,021.46	J01	139.97	102.78	1,021.48	1,021.48
2	J02	166.97	R02	331.94	121.97	1,198.01	976.69	J62	129.72	101.34	960.99	960.99
3	J04	167.03	R02	331.97	120.88	1,201.90	700.87	J18	129.19	100.18	689.35	689.35
4	J06	166.86	R02	331.98	119.23	1,203.78	660.69	J06	139.97	99.63	660.69	660.69
5	J10	167.11	R02	331.97	119.48	1,202.62	302.21	J10	139.96	99.88	302.21	302.21
6	J12	166.95	R02	331.97	119.38	1,202.42	260.38	J12	139.96	99.78	260.38	260.38
7	J14	167.07	R02	331.97	121.98	1,202.50	256.53	J14	139.96	102.38	256.53	256.53
8	J16	167.33	J16	321.74	121.33	246.17	246.17	J16	139.96	102.78	246.17	246.17
9	J18	167.03	R02	331.97	122.88	1,202.42	257.94	J18	139.96	103.28	257.94	257.94
10	J20	167.01	J20	317.31	118.98	236.20	236.20	J20	139.96	100.88	236.20	236.20
11	J22	167.21	J22	208.86	108.76	187.09	187.09	J22	139.96	101.73	187.09	187.09
12	J24	167.33	R02	331.97	122.18	1,202.69	298.92	J24	139.96	102.58	298.92	298.92
13	J26	167.22	R02	331.97	119.98	1,202.95	389.43	J26	139.96	100.38	389.43	389.43
14	J28	167.33	R02	331.97	121.38	1,202.60	384.11	J28	139.96	101.78	384.11	384.11
15	J30	166.88	J30	310.88	120.63	239.06	239.06	J30	139.96	103.18	239.06	239.06
16	J32	218.80	R02	328.76	121.65	1,230.08	895.98	J62	122.82	100.63	872.30	872.30
17	J34	218.84	R02	328.59	121.83	1,215.80	642.28	J34	139.97	102.58	642.29	642.29
18	J36	216.67	R02	328.53	119.18	1,208.48	630.89	J36	139.97	99.93	630.90	630.90
19	J50	217.44	R02	329.56	122.03	1,306.50	825.07	J50	139.97	102.68	825.07	825.07
20	J52	218.15	R02	330.35	122.61	1,395.62	807.70	J52	139.97	103.18	807.70	807.70
21	J54	218.69	R02	331.05	123.18	1,484.86	790.43	J54	139.97	103.68	790.44	790.44
22	J56	218.83	R02	331.90	124.87	1,607.21	734.61	J56	139.97	105.28	734.61	734.61
23	J58	219.90	J58	320.28	123.28	332.38	332.38	J58	139.96	104.88	332.39	332.38
24	J60	218.82	J60	305.43	121.17	312.36	312.37	J60	139.96	104.28	312.37	312.36
25	J62	217.98	R02	328.76	123.40	1,229.26	773.19	J62	139.97	104.13	773.20	773.20
26	J64	220.39	R02	329.62	122.74	1,315.85	804.42	J64	139.97	103.38	804.43	804.43
27	J66	219.12	R02	330.35	123.11	1,397.22	794.11	J66	139.97	103.68	794.12	794.12
28	J68	218.22	R02	331.00	124.28	1,479.87	767.72	J68	139.97	104.78	767.73	767.73
29	J70	218.30	R02	331.59	126.34	1,563.02	702.65	J70	139.97	106.78	702.65	702.65
30	J72	220.30	R02	332.08	127.94	1,632.26	691.52	J72	139.97	108.33	691.53	691.53
31	J74	217.45	R02	332.67	128.75	1,753.48	804.04	J74	139.97	109.08	804.04	804.04
32	J76	217.23	R02	332.82	127.96	1,794.90	864.82	J74	137.21	108.00	860.44	860.44
33	J78	219.75	R02	330.85	123.66	1,467.48	492.19	J78	139.96	104.18	492.19	492.19
34	J80	217.73	R02	330.27	122.95	1,388.98	491.89	J80	139.96	103.53	491.90	491.90
35	J82	219.30	R02	329.53	122.38	1,306.06	502.89	J82	139.96	103.03	502.89	502.89
36	J84	217.43	R02	333.09	126.59	1,865.81	977.08	J74	126.62	105.52	953.70	953.70
37	J86	219.33	R02	333.73	126.66	2,029.46	1,034.26	J86	139.97	106.88	1,034.28	1,034.28
38	J88	217.49	R02	334.75	126.36	2,359.29	1,166.02	J88	139.98	106.48	1,166.05	1,166.05
39	R02	167.57	R02	329.43	138.62	951.03	951.01	R02	139.97	119.28	951.03	951.03

Peak Hour Existing HGL 147.0 - 147.2m - Pipe Report

	ID	From Node	To Node	Length (m)	Diameter (mm)	Roughness	Flow (L/s)	Velocity (m/s)	Headloss (m)	HL/1000 (m/km)
1	101	J68	J78	74.96	204.00	110.00	3.26	0.10	0.01	0.10
2	103	J78	J54	82.08	204.00	110.00	-3.52	0.11	0.01	0.12
3	105	J66	J80	77.33	204.00	110.00	-0.19	0.01	0.0000	0.000
4	107	J80	J52	82.87	204.00	110.00	-2.53	0.08	0.01	0.06
5	109	J64	J82	72.60	204.00	110.00	1.71	0.05	0.00	0.03
6	11	R01	R02	205.21	393.00	120.00	49.27	0.41	0.11	0.54
7	111	J82	J50	82.87	204.00	110.00	-4.08	0.12	0.01	0.15
8	113	J54	J58	118.98	204.00	110.00	5.56	0.17	0.03	0.27
9	115	J58	J60	175.07	204.00	110.00	-1.55	0.05	0.00	0.03
10	117	J60	J56	171.69	204.00	110.00	-6.28	0.19	0.06	0.34
11	119	J84	J86	88.16	393.00	120.00	-50.70	0.42	0.05	0.57
12	13	J01	R02	306.73	393.00	120.00	-47.30	0.39	0.15	0.50
13	15	R03	J88	270.72	393.00	120.00	56.98	0.47	0.19	0.71
14	17	J84	J56	186.99	297.00	120.00	23.20	0.33	0.10	0.52
15	19	J02	J04	118.60	297.00	120.00	12.00	0.17	0.02	0.15
16	21	J04	J06	119.01	297.00	120.00	5.34	0.08	0.00	0.03
17	27	J10	J12	81.37	204.00	110.00	1.86	0.06	0.00	0.04
18	29	J12	J30	131.14	204.00	110.00	1.25	0.04	0.00	0.02
19	31	J30	J14	79.50	204.00	110.00	0.80	0.02	0.000	0.01
20	33	J14	J16	105.90	204.00	110.00	0.16	0.01	0.0000	0.000
21	35	J16	J18	88.67	204.00	110.00	-1.29	0.04	0.00	0.02
22	37	J24	J18	69.60	204.00	110.00	2.09	0.06	0.00	0.04
23	39	J24	J28	81.38	204.00	110.00	-4.58	0.14	0.02	0.19
24	41	J28	J04	86.06	204.00	110.00	-5.88	0.18	0.03	0.30
25	43	J14	J20	75.25	155.00	100.00	-0.25	0.01	0.000	0.00
26	45	J20	J10	83.78	155.00	100.00	-1.14	0.06	0.01	0.07
27	47	J20	J22	118.40	155.00	100.00	0.15	0.01	0.000	0.00
28	49	J22	J24	81.94	155.00	100.00	-1.04	0.06	0.00	0.06
29	51	J10	J26	100.14	204.00	110.00	-3.95	0.12	0.01	0.14
30	53	J26	J28	119.49	155.00	100.00	0.14	0.01	0.000	0.00
31	55	J26	J06	87.10	204.00	110.00	-5.31	0.16	0.02	0.25
32	57	J02	J32	157.46	393.00	120.00	21.51	0.18	0.02	0.12
33	59	J32	J34	175.10	297.00	120.00	4.30	0.06	0.00	0.02
34	61	J34	J36	132.79	297.00	120.00	0.39	0.01	0.0000	0.000
35	63	J36	J06	165.55	297.00	120.00	0.39	0.01	0.0000	0.000
36	65	R03	BC02	48.86	393.00	120.00	-56.98	0.47	0.03	0.71
37	67	R01	BC01	60.49	393.00	120.00	-49.27	0.41	0.03	0.54
38	69	J01	J02	133.74	393.00	120.00	46.22	0.38	0.06	0.48
39	73	J86	J88	125.70	393.00	120.00	-55.50	0.46	0.08	0.67
40	75	J50	J02	145.16	297.00	120.00	-12.05	0.17	0.02	0.16
41	77	J52	J50	112.09	297.00	120.00	-6.28	0.09	0.01	0.05
42	79	J54	J52	89.74	297.00	120.00	-0.49	0.01	0.0000	0.000
43	81	J56	J54	170.28	297.00	120.00	13.03	0.19	0.03	0.18
44	83	J32	J64	143.50	297.00	120.00	9.64	0.14	0.01	0.10
45	85	J64	J66	112.06	297.00	120.00	-0.25	0.00	0.00000	0.0000
46	87	J66	J68	89.98	297.00	120.00	-5.44	0.08	0.00	0.04
47	89	J68	J70	85.23	297.00	120.00	-12.12	0.17	0.01	0.16
48	91	J70	J72	85.23	297.00	120.00	-15.70	0.23	0.02	0.25
49	93	J72	J74	126.16	297.00	120.00	-23.69	0.34	0.07	0.54
50	95	J32	J62	77.50	393.00	120.00	2.87	0.02	0.000	0.00
51	97	J74	J76	75.91	393.00	120.00	-25.10	0.21	0.01	0.15
52	99	J76	J84	90.33	393.00	120.00	-26.12	0.22	0.02	0.17

APPENDIX C

- **Figure 5.1 – Recommended Wastewater Plan (MSS)**
- **Figure 3.1 – Recommended Wastewater Plan**
- **Sanitary Sewer Design Sheets**
- **Drawing 38298-501A, Sanitary Drainage Area Plan**

Water Demand Design Flows per Unit Count
City of Ottawa - Water Distribution Guidelines, July 2010

Domestic Demand

Type of Housing	Per / Unit	Units	Pop
Single Family	3.4	-	0
Semi-detached	2.7	-	0
Townhouse	2.7	192	519
Apartment			0
Bachelor	1.4		0
1 Bedroom	1.4		0
2 Bedroom	2.1		0
3 Bedroom	3.1	-	0
Average	1.8	-	0

	Pop	Avg. Daily		Max Day		Peak Hour	
		m^3/d	L/min	m^3/d	L/min	m^3/d	L/min
Total Domestic Demand	519	145.3	100.9	363.3	252.3	799.3	555.0

Institutional / Commercial / Industrial Demand

Property Type	Unit Rate	Units	Avg. Daily		Max Day		Peak Hour	
			m^3/d	L/min	m^3/d	L/min	m^3/d	L/min
Commercial floor space	2.5 $L/m^2/d$	-	0.00	0.0	0.0	0.0	0.0	0.0
Office	75 $L/9.3m^2/d$	-	0.00	0.0	0.0	0.0	0.0	0.0
Restaurant*	125 L/seat/d	-	0.00	0.0	0.0	0.0	0.0	0.0
Industrial - Light	35,000 L/gross ha/d	-	0.00	0.0	0.0	0.0	0.0	0.0
Industrial - Heavy	55,000 L/gross ha/d	-	0.00	0.0	0.0	0.0	0.0	0.0
Total I/CI Demand			0.0	0.0	0.0	0.0	0.0	0.0
Total Demand			**145.3**	**100.9**	**363.3**	**252.3**	**799.3**	**555.0**

Fire Flow Estimation per Fire Underwriters Survey

Water Supply For Public Fire Protection - 1999

Fire Flow Required

BLOCK 1

1. Base Requirement

$$F = 220C\sqrt{A}$$ L/min *Where **F** is the fire flow, **C** is the Type of construction and **A** is the Total floor area*

Type of Construction: Wood Frame

C	1.5		*Type of Construction Coefficient per FUS Part II, Section 1*
A	2033.4	m^2	*Total floor area based on FUS Part II section 1*

Fire Flow	14880.8	L/min	
	15000.0	**L/min**	*rounded to the nearest 1,000 L/min*

Adjustments

2. Reduction for Occupancy Type

Limited Combustible	-15%	
Fire Flow	**12750.0**	**L/min**

3. Reduction for Sprinkler Protection

Non-Sprinklered	0%	
Reduction	**0**	**L/min**

4. Increase for Separation Distance

	Cons. of Exposed Wall	S.D	Lw	Ha	LH	EC	
N	Wood Frame	30.1m-45m	32	3	96	5%	
S	Wood Frame	20.1m-30m	32	3	96	10%	
E	Wood Frame	3.1m-10m	16	3	48	18%	
W	Wood Frame	30.1m-45m	16	3	48	5%	
		% Increase				**38%**	*value not to exceed 75%*

Increase	**4845.0**	**L/min**

Lw = Length of the Exposed Wall
Ha = number of storeys of the adjacent structure. Max 5 stories
LH = Length-height factor of exposed wall. Value rounded up.
EC = Exposure Charge

Total Fire Flow

Fire Flow	17595.0	L/min	*fire flow not to exceed 45,000 L/min nor be less than 2,000 L/min per FUS Section*
	18000.0	**L/min**	*rounded to the nearest 1,000 L/min*

Notes:
-Type of construction, Occupancy Type and Sprinkler Protection information provided by Q4 Architects Incorporated, dated January 22nd, 2019.
-Calculations based on Fire Underwriters Survey - Part II

Fire Flow Estimation per Fire Underwriters Survey

Water Supply For Public Fire Protection - 1999

Fire Flow Required

BLOCK 2

1. Base Requirement

$$F = 220C\sqrt{A}$$ L/min *Where **F** is the fire flow, **C** is the Type of construction and **A** is the Total floor area*

Type of Construction: Wood Frame

C	1.5		*Type of Construction Coefficient per FUS Part II, Section 1*
A	2022.3	m^2	*Total floor area based on FUS Part II section 1*

Fire Flow	14840.2	L/min	
	15000.0	**L/min**	*rounded to the nearest 1,000 L/min*

Adjustments

2. Reduction for Occupancy Type

Limited Combustible	-15%	
Fire Flow	**12750.0**	**L/min**

3. Reduction for Sprinkler Protection

Non-Sprinklered	0%	
Reduction	**0**	**L/min**

4. Increase for Separation Distance

	Cons. of Exposed Wall	S.D	Lw	Ha	LH	EC
N	Wood Frame	30.1m-45m	32	3	96	5%
S	Wood Frame	20.1m-30m	32	3	96	10%
E	Wood Frame	3.1m-10m	16	3	48	18%
W	Wood Frame	3.1m-10m	16	3	48	18%
		% Increase				**51%** *value not to exceed 75%*

Increase	**6502.5**	**L/min**

Lw = Length of the Exposed Wall
Ha = number of storeys of the adjacent structure. Max 5 stories
LH = Length-height factor of exposed wall. Value rounded up.
EC = Exposure Charge

Total Fire Flow

Fire Flow	19252.5	L/min	*fire flow not to exceed 45,000 L/min nor be less than 2,000 L/min per FUS Section*
	19000.0	**L/min**	*rounded to the nearest 1,000 L/min*

Notes:
-Type of construction, Occupancy Type and Sprinkler Protection information provided by Q4 Architects Incorporated, dated January 22nd, 2019.
-Calculations based on Fire Underwriters Survey - Part II

Fire Flow Estimation per Fire Underwriters Survey

Water Supply For Public Fire Protection - 1999

Fire Flow Required

BLOCK 3

1. Base Requirement

$$F = 220C\sqrt{A}$$ L/min *Where **F** is the fire flow, **C** is the Type of construction and **A** is the Total floor area*

Type of Construction: Wood Frame

C	1.5		*Type of Construction Coefficient per FUS Part II, Section 1*
A	2022.3	m^2	*Total floor area based on FUS Part II section 1*

Fire Flow	14840.2	L/min	
	15000.0	**L/min**	*rounded to the nearest 1,000 L/min*

Adjustments

2. Reduction for Occupancy Type

Limited Combustible	-15%	
Fire Flow	**12750.0**	**L/min**

3. Reduction for Sprinkler Protection

Non-Sprinklered	0%	
Reduction	**0**	**L/min**

4. Increase for Separation Distance

	Cons. of Exposed Wall	S.D	Lw	Ha	LH	EC
N	Wood Frame	30.1m-45m	32	3	96	5%
S	Wood Frame	20.1m-30m	32	3	96	10%
E	Wood Frame	3.1m-10m	16	3	48	18%
W	Wood Frame	3.1m-10m	16	3	48	18%
		% Increase				**51%** *value not to exceed 75%*

Increase	**6502.5**	**L/min**

Lw = Length of the Exposed Wall
Ha = number of storeys of the adjacent structure. Max 5 stories
LH = Length-height factor of exposed wall. Value rounded up.
EC = Exposure Charge

Total Fire Flow

Fire Flow	19252.5	L/min	*fire flow not to exceed 45,000 L/min nor be less than 2,000 L/min per FUS Section*
	19000.0	**L/min**	*rounded to the nearest 1,000 L/min*

Notes:
-Type of construction, Occupancy Type and Sprinkler Protection information provided by Q4 Architects Incorporated, dated January 22nd, 2019.
-Calculations based on Fire Underwriters Survey - Part II

Fire Flow Estimation per Fire Underwriters Survey

Water Supply For Public Fire Protection - 1999

Fire Flow Required

BLOCK 4

1. Base Requirement

$$F = 220C\sqrt{A}$$ L/min *Where **F** is the fire flow, **C** is the Type of construction and **A** is the Total floor area*

Type of Construction: Wood Frame

C	1.5		*Type of Construction Coefficient per FUS Part II, Section 1*
A	2033.4	m^2	*Total floor area based on FUS Part II section 1*

Fire Flow	14880.8	L/min	
	15000.0	**L/min**	*rounded to the nearest 1,000 L/min*

Adjustments

2. Reduction for Occupancy Type

Limited Combustible	-15%	
Fire Flow	**12750.0**	**L/min**

3. Reduction for Sprinkler Protection

Non-Sprinklered	0%	
Reduction	**0**	**L/min**

4. Increase for Separation Distance

	Cons. of Exposed Wall	S.D	Lw	Ha	LH	EC
N	Wood Frame	30.1m-45m	32	3	96	5%
S	Wood Frame	20.1m-30m	32	3	96	10%
E	Wood Frame	30.1m-45m	16	3	48	5%
W	Wood Frame	3.1m-10m	16	3	48	18%
		% Increase				**38%** *value not to exceed 75%*

Increase	**4845.0**	**L/min**

Lw = Length of the Exposed Wall
Ha = number of storeys of the adjacent structure. Max 5 stories
LH = Length-height factor of exposed wall. Value rounded up.
EC = Exposure Charge

Total Fire Flow

Fire Flow	17595.0	L/min	*fire flow not to exceed 45,000 L/min nor be less than 2,000 L/min per FUS Section*
	18000.0	**L/min**	*rounded to the nearest 1,000 L/min*

Notes:
-Type of construction, Occupancy Type and Sprinkler Protection information provided by Q4 Architects Incorporated, dated January 22nd, 2019.
-Calculations based on Fire Underwriters Survey - Part II

Fire Flow Estimation per Fire Underwriters Survey

Water Supply For Public Fire Protection - 1999

Fire Flow Required

BLOCK 5

1. Base Requirement

$$F = 220C\sqrt{A}$$ L/min *Where **F** is the fire flow, **C** is the Type of construction and **A** is the Total floor area*

Type of Construction: Wood Frame

C	1.5		*Type of Construction Coefficient per FUS Part II, Section 1*
A	1622.7	m^2	*Total floor area based on FUS Part II section 1*

Fire Flow	13293.4	L/min	
	13000.0	**L/min**	*rounded to the nearest 1,000 L/min*

Adjustments

2. Reduction for Occupancy Type

Limited Combustible	-15%	
Fire Flow	**11050.0**	**L/min**

3. Reduction for Sprinkler Protection

Non-Sprinklered	0%	
Reduction	**0**	**L/min**

4. Increase for Separation Distance

	Cons. of Exposed Wall	S.D	Lw	Ha	LH	EC	
N	Wood Frame	20.1m-30m	18	3	54	8%	
S	Wood Frame	10.1m-20m	18	3	54	13%	
E	Wood Frame	20.1m-30m	26	3	78	9%	
W	Wood Frame	10.1m-20m	26	3	78	14%	
		% Increase				**44%**	*value not to exceed 75%*

Increase	**4862.0**	**L/min**

Lw = Length of the Exposed Wall
Ha = number of storeys of the adjacent structure. Max 5 stories
LH = Length-height factor of exposed wall. Value rounded up.
EC = Exposure Charge

Total Fire Flow

Fire Flow	15912.0	L/min	*fire flow not to exceed 45,000 L/min nor be less than 2,000 L/min per FUS Section*
	16000.0	**L/min**	*rounded to the nearest 1,000 L/min*

Notes:
-Type of construction, Occupancy Type and Sprinkler Protection information provided by Q4 Architects Incorporated, dated January 22nd, 2019.
-Calculations based on Fire Underwriters Survey - Part II

Fire Flow Estimation per Fire Underwriters Survey

Water Supply For Public Fire Protection - 1999

Fire Flow Required

BLOCK 6

1. Base Requirement

$$F = 220C\sqrt{A}$$ L/min *Where **F** is the fire flow, **C** is the Type of construction and **A** is the Total floor area*

Type of Construction: Wood Frame

C	1.5		*Type of Construction Coefficient per FUS Part II, Section 1*
A	1622.7	m^2	*Total floor area based on FUS Part II section 1*

Fire Flow	13293.4	L/min	
	13000.0	**L/min**	*rounded to the nearest 1,000 L/min*

Adjustments

2. Reduction for Occupancy Type

Limited Combustible	-15%	
Fire Flow	**11050.0**	**L/min**

3. Reduction for Sprinkler Protection

Non-Sprinklered	0%	
Reduction	**0**	**L/min**

4. Increase for Separation Distance

	Cons. of Exposed Wall	S.D	Lw	Ha	LH	EC	
N	Wood Frame	20.1m-30m	18	3	54	8%	
S	Wood Frame	3.1m-10m	18	3	54	18%	
E	Wood Frame	20.1m-30m	26	3	78	9%	
W	Wood Frame	10.1m-20m	26	3	78	14%	
		% Increase				**49%**	*value not to exceed 75%*

Increase	**5414.5**	**L/min**

Lw = Length of the Exposed Wall
Ha = number of storeys of the adjacent structure. Max 5 stories
LH = Length-height factor of exposed wall. Value rounded up.
EC = Exposure Charge

Total Fire Flow

Fire Flow	16464.5	L/min	*fire flow not to exceed 45,000 L/min nor be less than 2,000 L/min per FUS Section*
	16000.0	**L/min**	*rounded to the nearest 1,000 L/min*

Notes:
-Type of construction, Occupancy Type and Sprinkler Protection information provided by Q4 Architects Incorporated, dated January 22nd, 2019.
-Calculations based on Fire Underwriters Survey - Part II

Fire Flow Estimation per Fire Underwriters Survey

Water Supply For Public Fire Protection - 1999

Fire Flow Required

BLOCK 7

1. Base Requirement

$$F = 220C\sqrt{A}$$ L/min *Where **F** is the fire flow, **C** is the Type of construction and **A** is the Total floor area*

Type of Construction: Wood Frame

C	1.5		*Type of Construction Coefficient per FUS Part II, Section 1*
A	1222.9	m^2	*Total floor area based on FUS Part II section 1*

Fire Flow	11540.1	L/min	
	12000.0	**L/min**	*rounded to the nearest 1,000 L/min*

Adjustments

2. Reduction for Occupancy Type

Limited Combustible	-15%	
Fire Flow	**10200.0**	**L/min**

3. Reduction for Sprinkler Protection

Non-Sprinklered	0%	
Reduction	**0**	**L/min**

4. Increase for Separation Distance

	Cons. of Exposed Wall	S.D	Lw	Ha	LH	EC	
N	Wood Frame	3.1m-10m	18	3	54	18%	
S	Wood Frame	10.1m-20m	18	3	54	13%	
E	Wood Frame	10.1m-20m	26	3	78	14%	
W	Wood Frame	20.1m-30m	26	3	78	9%	
		% Increase				**54%**	*value not to exceed 75%*

Increase	**5508.0**	**L/min**

Lw = Length of the Exposed Wall
Ha = number of storeys of the adjacent structure. Max 5 stories
LH = Length-height factor of exposed wall. Value rounded up.
EC = Exposure Charge

Total Fire Flow

Fire Flow	15708.0	L/min	*fire flow not to exceed 45,000 L/min nor be less than 2,000 L/min per FUS Section*
	16000.0	**L/min**	*rounded to the nearest 1,000 L/min*

Notes:
-Type of construction, Occupancy Type and Sprinkler Protection information provided by Q4 Architects Incorporated, dated January 22nd, 2019.
-Calculations based on Fire Underwriters Survey - Part II

Fire Flow Estimation per Fire Underwriters Survey

Water Supply For Public Fire Protection - 1999

Fire Flow Required

BLOCK 8

1. Base Requirement

$$F = 220C\sqrt{A}$$ L/min *Where **F** is the fire flow, **C** is the Type of construction and **A** is the Total floor area*

Type of Construction: Wood Frame

C	1.5		*Type of Construction Coefficient per FUS Part II, Section 1*
A	745.3	m^2	*Total floor area based on FUS Part II section 1*

Fire Flow	9008.9	L/min	
	9000.0	**L/min**	*rounded to the nearest 1,000 L/min*

Adjustments

2. Reduction for Occupancy Type

Limited Combustible	-15%	
Fire Flow	**7650.0**	**L/min**

3. Reduction for Sprinkler Protection

Non-Sprinklered	0%	
Reduction	**0**	**L/min**

4. Increase for Separation Distance

	Cons. of Exposed Wall	S.D	Lw	Ha	LH	EC	
N	Wood Frame	20.1m-30m	24	3	72	9%	
S	Wood Frame	3.1m-10m	24	3	72	19%	
E	Wood Frame	10.1m-20m	33	3	99	15%	
W	Wood Frame	10.1m-20m	33	3	99	15%	
		% Increase				**58%**	*value not to exceed 75%*

Increase	**4437.0**	**L/min**

Lw = Length of the Exposed Wall
Ha = number of storeys of the adjacent structure. Max 5 stories
LH = Length-height factor of exposed wall. Value rounded up.
EC = Exposure Charge

Total Fire Flow

Fire Flow	12087.0	L/min	*fire flow not to exceed 45,000 L/min nor be less than 2,000 L/min per FUS Section*
	12000.0	**L/min**	*rounded to the nearest 1,000 L/min*

Notes:
-Type of construction, Occupancy Type and Sprinkler Protection information provided by Q4 Architects Incorporated, dated January 22nd, 2019.
-Calculations based on Fire Underwriters Survey - Part II

Fire Flow Estimation per Fire Underwriters Survey

Water Supply For Public Fire Protection - 1999

Fire Flow Required

BLOCK 9

1. Base Requirement

$$F = 220C\sqrt{A}$$ L/min *Where **F** is the fire flow, **C** is the Type of construction and **A** is the Total floor area*

Type of Construction: Wood Frame

C	1.5		*Type of Construction Coefficient per FUS Part II, Section 1*
A	758.4	m^2	*Total floor area based on FUS Part II section 1*

Fire Flow	9087.7	L/min	
	9000.0	**L/min**	*rounded to the nearest 1,000 L/min*

Adjustments

2. Reduction for Occupancy Type

Limited Combustible	-15%	
Fire Flow	**7650.0**	**L/min**

3. Reduction for Sprinkler Protection

Non-Sprinklered	0%	
Reduction	**0**	**L/min**

4. Increase for Separation Distance

	Cons. of Exposed Wall	S.D	Lw	Ha	LH	EC	
N	Wood Frame	3.1m-10m	24	3	72	19%	
S	Wood Frame	3.1m-10m	24	3	72	19%	
E	Wood Frame	10.1m-20m	33	3	99	15%	
W	Wood Frame	10.1m-20m	33	3	99	15%	
		% Increase				**68%**	*value not to exceed 75%*

Increase	**5202.0**	**L/min**	

Lw = Length of the Exposed Wall
Ha = number of storeys of the adjacent structure. Max 5 stories
LH = Length-height factor of exposed wall. Value rounded up.
EC = Exposure Charge

Total Fire Flow

Fire Flow	12852.0	L/min	*fire flow not to exceed 45,000 L/min nor be less than 2,000 L/min per FUS Section*
	13000.0	**L/min**	*rounded to the nearest 1,000 L/min*

Notes:
-Type of construction, Occupancy Type and Sprinkler Protection information provided by Q4 Architects Incorporated, dated January 22nd, 2019.
-Calculations based on Fire Underwriters Survey - Part II

Fire Flow Estimation per Fire Underwriters Survey

Water Supply For Public Fire Protection - 1999

Fire Flow Required

BLOCK 10

1. Base Requirement

$$F = 220C\sqrt{A}$$ L/min *Where **F** is the fire flow, **C** is the Type of construction and **A** is the Total floor area*

Type of Construction: Wood Frame

C	1.5		*Type of Construction Coefficient per FUS Part II, Section 1*
A	744.5	m^2	*Total floor area based on FUS Part II section 1*

Fire Flow	9004.3	L/min	
	9000.0	**L/min**	*rounded to the nearest 1,000 L/min*

Adjustments

2. Reduction for Occupancy Type

Limited Combustible	-15%	
Fire Flow	**7650.0**	**L/min**

3. Reduction for Sprinkler Protection

Non-Sprinklered	0%	
Reduction	**0**	**L/min**

4. Increase for Separation Distance

	Cons. of Exposed Wall	S.D	Lw	Ha	LH	EC
N	Wood Frame	3.1m-10m	24	3	72	19%
S	Wood Frame	>45m	24	3	72	0%
E	Wood Frame	10.1m-20m	33	3	99	15%
W	Wood Frame	10.1m-20m	33	3	99	15%
		% Increase				**49%** *value not to exceed 75%*

Increase	**3748.5**	**L/min**

Lw = Length of the Exposed Wall
Ha = number of storeys of the adjacent structure. Max 5 stories
LH = Length-height factor of exposed wall. Value rounded up.
EC = Exposure Charge

Total Fire Flow

Fire Flow	11398.5	L/min	*fire flow not to exceed 45,000 L/min nor be less than 2,000 L/min per FUS Section*
	11000.0	**L/min**	*rounded to the nearest 1,000 L/min*

Notes:
-Type of construction, Occupancy Type and Sprinkler Protection information provided by Q4 Architects Incorporated, dated January 22nd, 2019.
-Calculations based on Fire Underwriters Survey - Part II

Fire Flow Estimation per Fire Underwriters Survey

Water Supply For Public Fire Protection - 1999

Fire Flow Required

BLOCK 11

1. Base Requirement

$$F = 220C\sqrt{A}$$ L/min *Where **F** is the fire flow, **C** is the Type of construction and **A** is the Total floor area*

Type of Construction: Wood Frame

C	1.5		*Type of Construction Coefficient per FUS Part II, Section 1*
A	617.8	m^2	*Total floor area based on FUS Part II section 1*

Fire Flow	8202.4	L/min	
	8000.0	**L/min**	*rounded to the nearest 1,000 L/min*

Adjustments

2. Reduction for Occupancy Type

Limited Combustible	-15%	
Fire Flow	**6800.0**	**L/min**

3. Reduction for Sprinkler Protection

Non-Sprinklered	0%	
Reduction	**0**	**L/min**

4. Increase for Separation Distance

	Cons. of Exposed Wall	S.D	Lw	Ha	LH	EC	
N	Wood Frame	10.1m-20m	26	3	78	14%	
S	Wood Frame	>45m	26	3	78	0%	
E	Wood Frame	10.1m-20m	24	3	72	14%	
W	Wood Frame	3.1m-10m	24	3	72	19%	
		% Increase				**47%**	*value not to exceed 75%*

Increase	**3196.0**	**L/min**

Lw = Length of the Exposed Wall
Ha = number of storeys of the adjacent structure. Max 5 stories
LH = Length-height factor of exposed wall. Value rounded up.
EC = Exposure Charge

Total Fire Flow

Fire Flow	9996.0	L/min	*fire flow not to exceed 45,000 L/min nor be less than 2,000 L/min per FUS Section*
	10000.0	**L/min**	*rounded to the nearest 1,000 L/min*

Notes:
-Type of construction, Occupancy Type and Sprinkler Protection information provided by Q4 Architects Incorporated, dated January 22nd, 2019.
-Calculations based on Fire Underwriters Survey - Part II

Fire Flow Estimation per Fire Underwriters Survey

Water Supply For Public Fire Protection - 1999

Fire Flow Required

BLOCK 12

1. Base Requirement

$$F = 220C\sqrt{A}$$ L/min *Where **F** is the fire flow, **C** is the Type of construction and **A** is the Total floor area*

Type of Construction: Wood Frame

C	1.5		*Type of Construction Coefficient per FUS Part II, Section 1*
A	617.8	m^2	*Total floor area based on FUS Part II section 1*

Fire Flow	8202.4	L/min	
	8000.0	**L/min**	*rounded to the nearest 1,000 L/min*

Adjustments

2. Reduction for Occupancy Type

Limited Combustible	-15%	
Fire Flow	**6800.0**	**L/min**

3. Reduction for Sprinkler Protection

Non-Sprinklered	0%	
Reduction	**0**	**L/min**

4. Increase for Separation Distance

	Cons. of Exposed Wall	S.D	Lw	Ha	LH	EC	
N	Wood Frame	10.1m-20m	26	3	78	14%	
S	Wood Frame	>45m	26	3	78	0%	
E	Wood Frame	3.1m-10m	24	3	72	19%	
W	Wood Frame	3.1m-10m	24	3	72	19%	
		% Increase				**52%**	*value not to exceed 75%*

Increase	**3536.0**	**L/min**

Lw = Length of the Exposed Wall
Ha = number of storeys of the adjacent structure. Max 5 stories
LH = Length-height factor of exposed wall. Value rounded up.
EC = Exposure Charge

Total Fire Flow

Fire Flow	10336.0	L/min	*fire flow not to exceed 45,000 L/min nor be less than 2,000 L/min per FUS Section*
	10000.0	**L/min**	*rounded to the nearest 1,000 L/min*

Notes:
-Type of construction, Occupancy Type and Sprinkler Protection information provided by Q4 Architects Incorporated, dated January 22nd, 2019.
-Calculations based on Fire Underwriters Survey - Part II

Fire Flow Estimation per Fire Underwriters Survey

Water Supply For Public Fire Protection - 1999

Fire Flow Required

BLOCK 13

1. Base Requirement

$$F = 220C\sqrt{A}$$ L/min *Where **F** is the fire flow, **C** is the Type of construction and **A** is the Total floor area*

Type of Construction: Wood Frame

C	1.5		*Type of Construction Coefficient per FUS Part II, Section 1*
A	745.3	m^2	*Total floor area based on FUS Part II section 1*

Fire Flow	9008.9	L/min
	9000.0	**L/min** *rounded to the nearest 1,000 L/min*

Adjustments

2. Reduction for Occupancy Type

Limited Combustible	-15%
Fire Flow	**7650.0 L/min**

3. Reduction for Sprinkler Protection

Non-Sprinklered	0%
Reduction	**0 L/min**

4. Increase for Separation Distance

	Cons. of Exposed Wall	S.D	Lw	Ha	LH	EC
N	Wood Frame	10.1m-20m	33	3	99	15%
S	Wood Frame	>45m	33	3	99	0%
E	Wood Frame	3.1m-10m	24	3	72	19%
W	Wood Frame	3.1m-10m	24	3	72	19%
		% Increase				**53%** *value not to exceed 75%*

Increase	**4054.5 L/min**

Lw = Length of the Exposed Wall
Ha = number of storeys of the adjacent structure. Max 5 stories
LH = Length-height factor of exposed wall. Value rounded up.
EC = Exposure Charge

Total Fire Flow

Fire Flow	11704.5	L/min *fire flow not to exceed 45,000 L/min nor be less than 2,000 L/min per FUS Section*
	12000.0	**L/min** *rounded to the nearest 1,000 L/min*

Notes:
-Type of construction, Occupancy Type and Sprinkler Protection information provided by Q4 Architects Incorporated, dated January 22nd, 2019.
-Calculations based on Fire Underwriters Survey - Part II

Fire Flow Estimation per Fire Underwriters Survey

Water Supply For Public Fire Protection - 1999

Fire Flow Required

BLOCK 14

1. Base Requirement

$$F = 220C\sqrt{A}$$ L/min *Where **F** is the fire flow, **C** is the Type of construction and **A** is the Total floor area*

Type of Construction: Wood Frame

C	1.5		*Type of Construction Coefficient per FUS Part II, Section 1*
A	904.5	m^2	*Total floor area based on FUS Part II section 1*

Fire Flow	9924.7	L/min	
	10000.0	**L/min**	*rounded to the nearest 1,000 L/min*

Adjustments

2. Reduction for Occupancy Type

Limited Combustible	-15%	
Fire Flow	**8500.0**	**L/min**

3. Reduction for Sprinkler Protection

Non-Sprinklered	0%	
Reduction	**0**	**L/min**

4. Increase for Separation Distance

	Cons. of Exposed Wall	S.D	Lw	Ha	LH	EC
N	Wood Frame	20.1m-30m	24	3	72	9%
S	Wood Frame	3.1m-10m	24	3	72	19%
E	Wood Frame	10.1m-20m	39	3	117	15%
W	Wood Frame	>45m	39	3	117	0%
		% Increase				**43%** *value not to exceed 75%*

Increase	**3655.0**	**L/min**

Lw = Length of the Exposed Wall
Ha = number of storeys of the adjacent structure. Max 5 stories
LH = Length-height factor of exposed wall. Value rounded up.
EC = Exposure Charge

Total Fire Flow

Fire Flow	12155.0	L/min	*fire flow not to exceed 45,000 L/min nor be less than 2,000 L/min per FUS Section*
	12000.0	**L/min**	*rounded to the nearest 1,000 L/min*

Notes:
-Type of construction, Occupancy Type and Sprinkler Protection information provided by Q4 Architects Incorporated, dated January 22nd, 2019.
-Calculations based on Fire Underwriters Survey - Part II

```
******************************************************************
*                          E P A N E T                           *
*                  Hydraulic and Water Quality                   *
*                  Analysis for Pipe Networks                    *
*                        Version 2.0                             *
******************************************************************
```

Input File: 2019-11-29_946_Block15_ggg.net

DSEL EPANet - Wateridge Block 15

Link - Node Table:

Link ID	Start Node	End Node	Length m	Diameter mm	
3	9	8	49.3	200	
5	3	6	9.3	200	
6	6	12	46.3	200	
8	12	22	24.4	100	
9	14	11	30.0	200	
11	3	11	43.8	200	
4	19	3	24.6	200	
10	12	15	29.7	200	
12	2	9	78.9	200	
14	21	17	27.17	50	
2	2	4	22.3	200	
7	13	16	33.02	100	
13	10	6	36.4	100	
15	7	10	32.7	100	
16	20	2	8.7	200	
17	8	14	16.9	200	
21	18	WSquadron	7	200	
1	1	5	12.43	200	
18	16	10	73.85	100	
22	16	15	36.39	100	
23	15	20	2.13	200	
24	21	9	1.76	200	
25	22	8	45.6	100	
20	19	18	#N/A	200	Valve
19	5	4	#N/A	200	Valve

Node Results:

Node ID	Demand LPM	Head m	Pressure m	Quality hours
3	4.80	146.13	56.61	0.15
6	4.80	146.13	56.48	0.22

8	4.80	146.13	56.00	1.38
9	4.80	146.13	55.45	2.37
11	4.80	146.13	56.29	0.69
12	4.80	146.13	56.05	0.72

Node Results: (continued)

Node ID	Demand LPM	Head m	Pressure m	Quality hours	
2	4.80	146.13	55.41	2.86	
4	4.80	146.13	55.28	3.25	
7	4.80	146.13	56.39	1.51	
10	4.80	146.13	55.97	0.62	
13	4.80	146.13	55.11	3.39	
14	4.80	146.13	56.09	1.11	
15	4.80	146.13	55.49	1.11	
17	4.80	146.13	55.96	2.65	
18	4.80	147.00	57.68	0.03	
19	4.80	146.13	56.73	0.03	
5	4.80	146.00	54.99	3.25	
16	4.80	146.13	55.32	2.49	
20	4.80	146.13	55.47	1.15	
21	4.80	146.13	55.44	2.47	
22	4.80	146.13	56.01	2.87	
WSquadron	-121.56	147.00	0.00	0.00	Reservoir
1	20.66	146.00	0.00	0.00	Reservoir

Link Results:


Link ID	Flow LPM	Velocity m/s	Unit Headloss m/km	Status
3	26.06	0.01	0.00	Open
5	64.94	0.03	0.02	Open
6	48.12	0.03	0.01	Open
8	3.07	0.01	0.00	Open
9	37.40	0.02	0.01	Open
11	42.21	0.02	0.01	Open
4	111.95	0.06	0.04	Open
10	40.24	0.02	0.01	Open
12	11.64	0.01	0.00	Open
14	4.80	0.04	0.12	Open
2	30.27	0.02	0.00	Open
7	4.80	0.01	0.00	Open
13	12.02	0.03	0.02	Open
15	4.80	0.01	0.00	Open
16	23.43	0.01	0.00	Open

17	32.60	0.02	0.00	Open
21	121.56	0.06	0.05	Open
1	20.66	0.01	0.00	Open
18	2.41	0.01	0.00	Open
22	7.20	0.02	0.01	Open
23	28.23	0.01	0.00	Open
24	9.61	0.01	0.01	Open
25	1.73	0.00	0.00	Open
20	116.76	0.06	0.86	Open Valve

Link Results: (continued)

Link ID	Flow LPM	VelocityUnit m/s	Headloss m/km	Status
19	25.46	0.01	0.13	Open Valve

Average Day Scenario - Block 15



```
******************************************************************
*                          E P A N E T                           *
*                  Hydraulic and Water Quality                   *
*                  Analysis for Pipe Networks                    *
*                        Version 2.0                             *
******************************************************************
```

Input File: 2019-11-29_946_Block15_ggg.net

DSEL EPANet - Wateridge Block 15

Link - Node Table:

Link ID	Start Node	End Node	Length m	Diameter mm	
3	9	8	49.3	200	
5	3	6	9.3	200	
6	6	12	46.3	200	
8	12	22	24.4	100	
9	14	11	30.0	200	
11	3	11	43.8	200	
4	19	3	24.6	200	
10	12	15	29.7	200	
12	2	9	78.9	200	
14	21	17	27.17	50	
2	2	4	22.3	200	
7	13	16	33.02	100	
13	10	6	36.4	100	
15	7	10	32.7	100	
16	20	2	8.7	200	
17	8	14	16.9	200	
21	18	WSquadron	7	200	
1	1	5	12.43	200	
18	16	10	73.85	100	
22	16	15	36.39	100	
23	15	20	2.13	200	
24	21	9	1.76	200	
25	22	8	45.6	100	
20	19	18	#N/A	200	Valve
19	5	4	#N/A	200	Valve

Node Results:

Node ID	Demand LPM	Head m	Pressure m	Quality hours
3	26.43	145.24	55.72	0.06
6	26.43	145.24	55.59	0.08

8	26.43	145.24	55.11	0.54
9	26.43	145.23	54.55	1.15
11	26.43	145.24	55.40	0.25
12	26.43	145.24	55.16	0.31

Node Results: (continued)

Node ID	Demand LPM	Head m	Pressure m	Quality hours	
2	26.43	145.24	54.52	0.14	
4	26.43	145.24	54.39	0.04	
7	26.43	145.22	55.48	0.33	
10	26.43	145.22	55.06	0.17	
13	26.43	145.22	54.20	0.93	
14	26.43	145.24	55.20	0.41	
15	26.43	145.24	54.60	0.52	
17	26.43	145.15	54.98	1.20	
18	26.43	146.70	57.38	0.02	
19	26.43	145.25	55.85	0.02	
5	26.43	146.00	54.99	0.04	
16	26.43	145.22	54.41	0.77	
20	26.43	145.24	54.58	0.25	
21	26.43	145.23	54.54	1.17	
22	26.43	145.23	55.11	0.73	
WSquadron	-387.92	146.70	0.00	0.00	Reservoir
1	-167.11	146.00	0.00	0.00	Reservoir

Link Results:


Link ID	Flow LPM	Velocity m/s	Unit Headloss m/km	Status
3	32.81	0.02	0.00	Open
5	187.86	0.10	0.15	Open
6	105.43	0.06	0.04	Open
8	17.76	0.04	0.06	Open
9	94.34	0.05	0.04	Open
11	120.77	0.06	0.06	Open
4	335.06	0.18	0.34	Open
10	61.24	0.03	0.01	Open
12	46.48	0.02	0.01	Open
14	26.43	0.22	2.96	Open
2	114.25	0.06	0.06	Open
7	26.43	0.06	0.10	Open
13	56.00	0.12	0.42	Open
15	26.43	0.06	0.11	Open
16	41.34	0.02	0.01	Open

17	67.91	0.04	0.02	Open
21	387.92	0.21	0.46	Open
1	167.11	0.09	0.14	Open
18	3.14	0.01	0.00	Open
22	49.72	0.11	0.37	Open
23	14.91	0.01	0.00	Open
24	52.86	0.03	0.03	Open
25	8.67	0.02	0.01	Open
20	361.49	0.19	1.45	Open Valve

Link Results: (continued)

Link ID	Flow LPM	Velocity m/s	Unit Headloss m/km	Status
19	140.68	0.07	0.76	Open Valve

Peak Hour Scenario - Block 15



```
******************************************************************
*                          E P A N E T                           *
*                  Hydraulic and Water Quality                   *
*                  Analysis for Pipe Networks                    *
*                        Version 2.0                             *
******************************************************************
```

Input File: 2019-11-29_946_Block15_ggg.net

DSEL EPANet - Wateridge Block 15

Link - Node Table:

Link ID	Start Node	End Node	Length m	Diameter mm	
3	9	8	49.3	200	
5	3	6	9.3	200	
6	6	12	46.3	200	
8	12	22	24.4	100	
9	14	11	30.0	200	
11	3	11	43.8	200	
4	19	3	24.6	200	
10	12	15	29.7	200	
12	2	9	78.9	200	
14	21	17	27.17	50	
2	2	4	22.3	200	
7	13	16	33.02	100	
13	10	6	36.4	100	
15	7	10	32.7	100	
16	20	2	8.7	200	
17	8	14	16.9	200	
21	18	WSquadron	7	200	
1	1	5	12.43	200	
18	16	10	73.85	100	
22	16	15	36.39	100	
23	15	20	2.13	200	
24	21	9	1.76	200	
25	22	8	45.6	100	
20	19	18	#N/A	200	Valve
19	5	4	#N/A	200	Valve

Node Results:

Node ID	Demand LPM	Head m	Pressure m	Quality hours
3	12.01	116.21	26.69	0.03
6	12.01	115.97	26.32	0.05

8	12.01	114.00	23.87	0.08
9	12.01	114.50	23.82	0.05
11	12.01	114.78	24.94	0.05
12	12.01	115.29	25.21	0.07

Node Results: (continued)

Node ID	Demand LPM	Head m	Pressure m	Quality hours	
2	12.01	115.22	24.50	0.03	
4	12.01	117.07	26.22	0.02	
7	12.01	115.67	25.93	0.42	
10	12.01	115.67	25.51	0.07	
13	12.01	115.20	24.18	0.47	
14	5712.01	113.80	23.76	0.08	
15	12.01	114.98	24.34	0.09	
17	12.01	114.48	24.31	0.17	
18	12.01	121.40	32.08	0.02	
19	12.01	118.25	28.85	0.02	
5	12.01	121.64	30.63	0.02	
16	12.01	115.20	24.39	0.11	
20	5712.01	114.90	24.24	0.07	
21	12.01	114.50	23.81	0.09	
22	12.01	114.77	24.65	0.08	
WSquadron	-6323.29	122.00	0.00	0.00	Reservoir
1	-5329.00	123.00	0.00	0.00	Reservoir

Link Results:


Link ID	Flow LPM	Velocity m/s	Unit Headloss m/km	Status
3	1891.35	1.00	10.14	Open
5	2844.97	1.51	25.83	Open
6	2560.47	1.36	14.66	Open
8	414.43	0.88	21.42	Open
9	3430.26	1.82	32.53	Open
11	3442.28	1.83	32.64	Open
4	6299.26	3.34	82.93	Open
10	2134.03	1.13	10.62	Open
12	1927.39	1.02	9.19	Open
14	12.01	0.10	0.68	Open
2	5304.97	2.81	82.81	Open
7	12.01	0.03	0.02	Open
13	272.49	0.58	8.12	Open
15	12.01	0.03	0.02	Open
16	3365.57	1.79	36.56	Open

17	2281.75	1.21	11.41	Open
21	6323.29	3.35	85.93	Open
1	5329.00	2.83	109.62	Open
18	248.46	0.53	6.40	Open
22	224.43	0.48	6.22	Open
23	2346.45	1.24	33.32	Open
24	24.03	0.01	0.01	Open
25	402.42	0.85	16.90	Open
20	6311.28	3.35	3.15	Open Valve


Link Results: (continued)

Link ID	Flow LPM	VelocityUnit m/s	Headloss m/km	Status
19	5316.99	2.82	4.57	Open Valve

Max. Day + Fire Flow Scenario - Block 15



Water Age


Age
6.00
12.00
24.00
48.00
hours
Age
6.00
12.00
24.00
48.00
hours
AVG DAY 147.0m
PEAK HOUR 146.7m
MAX DAY PLUS FF 122.0m
AVG DAY 147.0m (RUN AT 146.0)
PEAK HOUR 146.7m (Run @ 146.0)
MAX DAY PLUS FF 123.0m
MIKINAK ROAD
SQUADRON CRESCENT
SQUADRON CRESCENT
SQUADRON CRESCENT
WSquadron
TAKAMOSE PRIVATE
MAKWA PRIVATE
PRIVATE LANE
KINIW PRIVATE
MAKWA PRIVATE
BLOCK 1
BLOCK 2
BLOCK 2
BLOCK 4
BLOCK 5
BLOCK 6
BLOCK 7
BLOCK 8
BLOCK 9
BLOCK 10
BLOCK 11
BLOCK 12
BLOCK 13
BLOCK 14
1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
19
20
21
22

DSEL EPANet - Wateridge Block 15


Network Table - Nodes

Node ID	Demand LPM	Head m	Pressure m	Age hours
Junc 3	4.80	146.13	56.61	0.15
Junc 6	4.80	146.13	56.48	0.22
Junc 8	4.80	146.13	56.00	1.38
Junc 9	4.80	146.13	55.45	2.37
Junc 11	4.80	146.13	56.29	0.69
Junc 12	4.80	146.13	56.05	0.72
Junc 2	4.80	146.13	55.41	2.86
Junc 4	4.80	146.13	55.28	3.25
Junc 7	4.80	146.13	56.39	1.51
Junc 10	4.80	146.13	55.97	0.62
Junc 13	4.80	146.13	55.11	3.39
Junc 14	4.80	146.13	56.09	1.11
Junc 15	4.80	146.13	55.49	1.11
Junc 17	4.80	146.13	55.96	2.65
Junc 18	4.80	147.00	57.68	0.03
Junc 19	4.80	146.13	56.73	0.03
Junc 5	4.80	146.00	54.99	3.25
Junc 16	4.80	146.13	55.32	2.49
Junc 20	4.80	146.13	55.47	1.15
Junc 21	4.80	146.13	55.44	2.47
Junc 22	4.80	146.13	56.01	2.87
Resvr WSquadron	-121.56	147.00	0.00	0.00
Resvr 1	20.66	146.00	0.00	0.00

DSEL EPANet - Wateridge Block 15

Network Table - Links

Link ID	Flow LPM	Velocity m/s	Unit Headloss m/km	Age hours
Pipe 3	26.06	0.01	0.00	1.87
Pipe 5	64.94	0.03	0.02	0.17
Pipe 6	48.12	0.03	0.01	0.46
Pipe 8	3.07	0.01	0.00	1.24
Pipe 9	37.40	0.02	0.01	0.89
Pipe 11	42.21	0.02	0.01	0.41
Pipe 4	111.95	0.06	0.04	0.08
Pipe 10	40.24	0.02	0.01	0.91
Pipe 12	11.64	0.01	0.00	4.14
Pipe 14	4.80	0.04	0.12	2.55
Pipe 2	30.27	0.02	0.00	3.05
Pipe 7	4.80	0.01	0.00	2.93
Pipe 13	12.02	0.03	0.02	0.41
Pipe 15	4.80	0.01	0.00	1.05
Pipe 16	23.43	0.01	0.00	1.24
Pipe 17	32.60	0.02	0.00	1.24
Pipe 21	121.56	0.06	0.05	0.01
Pipe 1	20.66	0.01	0.00	3.40
Pipe 18	2.41	0.01	0.00	2.62
Pipe 22	7.20	0.02	0.01	1.43
Pipe 23	28.23	0.01	0.00	1.12
Pipe 24	9.61	0.01	0.01	2.41
Pipe 25	1.73	0.00	0.00	3.10
Valve 20	116.76	0.06	0.86	0.03
Valve 19	25.46	0.01	0.13	3.25



DSEL
david schaeffer engineering ltd
SMART SUBDIVISIONS™
120 Iber Road Unit 103
Stittsville, Ontario, K2S 1E9
Tel. (613) 836-0856
Fax. (613) 836-7183
www.DSEL.ca

HYDRANT COVERAGE FIGURE - BLOCK 5

Distance from Hydrant to Building
- **<76 m**
- **>76 m and < 152 m**

PROJ NO.:	17-946
DRAWN BY:	G.G.G.
DATE:	2019-08-21
SCALE:	1:900
FIGURE NO.:	FIG-1

z:\projects\17-946-wateridge_block 15\b_design\b2_drawings\b2-2_main (dsel)\2019-08_subm4\2019-08-21_946_spa_ggg.dwg

MIKINAK ROAD

3.6m MULTI USE PATH

TAKAMOSE PRIVATE

MAKWA PRIVATE

PRIVATE LANE

KINIW PRIVATE

SQUADRON CRESCENT

BLOCK 1

BLOCK 2

BLOCK 3

BLOCK 4

BLOCK 5

BLOCK 6

BLOCK 7

BLOCK 8

BLOCK 9

BLOCK 10

BLOCK 11

BLOCK 12

BLOCK 13

BLOCK 14

1

2

3

4

5

6

7

8

9

10

WATER SERVICE TO BE BLANKED AT MAIN BY CITY FORCES. EXCAVATION, BACKFILLING AND REINSTATEMENT BY CONTRACTOR

TEE CONNECTION TO EXISTING 200mmø WATERMAIN BY CITY FORCES. EXCAVATION AND REINSTATEMENT BY SITE SERVICING CONTRACTOR.

RELOCATE EXISTING HYDRANT

RELOCATE EXISTING HYDRANT

TEE CONNECTION TO EXISTING 200mmø WATERMAIN BY CITY FORCES. EXCAVATION AND REINSTATEMENT BY SITE SERVICING CONTRACTOR.

BOUNDARY CHAMBER PER CITY OF OTTAWA STD. 1903

WATER SERVICE TO BE BLANKED AT MAIN BY CITY FORCES. EXCAVATION, BACKFILLING AND REINSTATEMENT BY CONTRACTOR

HYDRO VAULT

DSEL
david schaeffer engineering ltd
SMART SUBDIVISIONS™

120 Iber Road Unit 103
Stittsville, Ontario, K2S 1E9
Tel. (613) 836-0856
Fax. (613) 836-7183
www.DSEL.ca

HYDRANT COVERAGE FIGURE - BLOCK 7

Distance from Hydrant to Building
- **<76 m**
- **>76 m and < 152 m**

PROJ NO.:	17-946
DRAWN BY:	G.G.G.
DATE:	2019-08-21
SCALE:	1:900
FIGURE NO.:	FIG-2

z:\projects\17-946-wateridge_block 15\b_design\b2_drawings\b2-2_main (dsel)\2019-08_subm4\2019-08-21_946_spa_ggg.dwg

MIKINAK ROAD

3.6m MULTI USE PATH

SQUADRON CRESCENT

TAKAMOSE PRIVATE

PRIVATE LANE

KINIW PRIVATE

MAKWA PRIVATE

BLOCK 1

BLOCK 2

BLOCK 3

BLOCK 4

BLOCK 5

BLOCK 6

BLOCK 7

BLOCK 8

BLOCK 9

BLOCK 10

BLOCK 11

BLOCK 12

BLOCK 13

BLOCK 14

1

2

3

4

5

6

7

8

9

10

WATER SERVICE TO BE BLANKED AT MAIN BY CITY FORCES. EXCAVATION, BACKFILLING AND REINSTATEMENT BY CONTRACTOR

TEE CONNECTION TO EXISTING 200mmø WATERMAIN BY CITY FORCES. EXCAVATION AND REINSTATEMENT BY SITE SERVICING CONTRACTOR.

RELOCATE EXISTING HYDRANT

TEE CONNECTION TO EXISTING 200mmø WATERMAIN BY CITY FORCES. EXCAVATION AND REINSTATEMENT BY SITE SERVICING CONTRACTOR.

DSEL
david schaeffer engineering ltd.
SMART SUBDIVISIONS™

120 Iber Road Unit 103
Stittsville, Ontario, K2S 1E9
Tel. (613) 836-0856
Fax. (613) 836-7183
www.DSEL.ca

HYDRANT COVERAGE FIGURE - BLOCK 6

Distance from Hydrant to Building
- **<76 m**
- **>76 m and < 152 m**

PROJ NO.:	17-946
DRAWN BY:	G.G.G.
DATE:	2019-08-21
SCALE:	1:900
FIGURE NO.:	FIG-2

z:\projects\17-946-wateridge_block 15\b_design\b2_drawings\b2-2_main (dsel)\2019-08_subm4\2019-08-21_946_spa_ggg.dwg

APPENDIX C

Wastewater Collection

IBI GROUP
400-333 Preston Street
Ottawa, Ontario K1S 5N4 Canada
tel 613 225 1311 fax 613 225 9868
ibigroup.com

SANITARY SEWER DESIGN SHEET

Former CFB Rockcliffe
City of Ottawa
Canada Lands Company

LOCATION				RESIDENTIAL										ICI AREAS							INFILTRATION ALLOWANCE			FIXED FLOW	TOTAL FLOW	PROPOSED SEWER DESIGN						
				AREA	UNIT TYPES				AREA	POPULATION		PEAK	PEAK	AREA (Ha)						PEAK	AREA (Ha)		FLOW			CAPACITY	LENGTH	DIA	SLOPE	VELOCITY	AVAILABLE CAPACITY	
														INSTITUTIONAL		COMMERCIAL		INDUSTRIAL		FLOW									(full)		
STREET	AREA ID	FROM MH	TO MH	Phase 1B (Ha)	SF	SD	TH	APT	EXTERNAL (Ha)	IND	CUM	FACTOR	FLOW (L/s)	IND	CUM	IND	CUM	IND	CUM	(L/s)	IND	CUM	(L/s)	(L/s)	(L/s)	(L/s)	(m)	(mm)	(%)	(m/s)	L/s	(%)
Phase 1B																																
Hemlock Road	201A	MH201A	MH202A	0.31						0.0	0.0	4.00	0.00		0.00		0.00		0.00	0.00	0.31	0.31	0.09	0.00	0.09	50.02	87.06	250	0.65	0.987	49.93	99.83%
Future Street No. 6	EX202A	BULK202AN	MH202A						2.08	358.5	358.5	4.00	5.81		0.00		0.00		0.00	0.00	2.08	2.08	0.58	0.00	6.39	31.02	21.00	250	0.25	0.612	24.63	79.40%
Hemlock Road	202A	MH202A	MH203A	0.21						0.0	358.5	4.00	5.81		0.00		0.00		0.00	0.00	0.21	2.60	0.73	0.00	6.54	75.98	86.00	250	1.50	1.500	69.44	91.40%
Future Street No. 5	EX203A	BULK203AN	MH203A						1.40	160.5	160.5	4.00	2.60		0.00		0.00		0.00	0.00	1.40	1.40	0.39	0.00	2.99	83.23	21.00	250	1.80	1.643	80.24	96.40%
Hemlock Road	203A, EXPARK2	MH203A	MH204A	0.20					0.44	0.0	0.0	4.00	0.00		0.00		0.00		0.00	0.00	0.64	0.64	0.18	0.00	0.18	82.07	86.00	250	1.75	1.620	81.89	99.78%
rue Moses Tennisco Street	EX204A	BULK204AN	MH204A						1.39	153.5	153.5	4.00	2.49		0.00		0.00		0.00	0.00	1.39	1.39	0.39	0.00	2.88	83.23	21.00	250	1.80	1.643	80.36	96.54%
Hemlock Road	204A	MH204A	MH205A	0.21						0.0	153.5	4.00	2.49		0.00		0.00		0.00	0.00	0.21	1.60	0.45	0.00	2.94	67.96	90.00	250	1.20	1.341	65.02	95.68%
rue Michael Stoqua Street	EX205A	BULK205AN	MH205A						1.38	241.5	241.5	4.00	3.91		0.00		0.00		0.00	0.00	1.38	1.38	0.39	0.00	4.30	67.96	21.00	250	1.20	1.341	63.66	93.67%
Hemlock Road	205A	MH205A	MH206A	0.25						0.0	395.0	4.00	6.40		0.00		0.00		0.00	0.00	0.25	3.23	0.90	0.00	7.30	31.02	112.00	250	0.25	0.612	23.71	76.45%
rue Bareille-Snow Street	EX206A-B	BULK206AN	MH206A						9.61	1755.0	1755.0	3.63	25.80		0.00		0.00		0.00	0.00	9.61	9.61	2.69	0.00	28.49	87.74	21.00	250	2.00	1.731	59.24	67.52%
Hemlock Road	206A	MH206A	MH207A	0.20						0.0	2150.0	3.56	31.02		0.00		0.00		0.00	0.00	0.20	13.04	3.65	0.00	34.67	55.26	89.33	300	0.30	0.757	20.59	37.26%
Block 20	PARK1	MH207AN	MH207A	0.32						0.0	0.0	4.00	0.00		0.00		0.00		0.00	0.00	0.32	0.32	0.09	0.00	0.09	39.24	14.00	250	0.40	0.774	39.15	99.77%
Hemlock Road	PARK1, 207A	MH207A	*BULK176AE*	0.12						0.0	2150.0	3.56	31.02		0.00		0.00		0.00	0.00	0.12	13.48	3.77	0.00	34.79	65.38	33.16	300	0.42	0.896	30.59	46.79%
Phase 1A																																
Hemlock Road		*BULK176AE*	*MH176A*							0.0	2150.0	3.56	31.02		0.00		0.00		0.00	0.00	0.00	13.48	3.77	0.00	34.79	65.38	*21.97*	*300*	*0.42*	0.896	30.59	46.79%
Phase 1B																																
chemin Wanaki Road	200A, COM1	MH200A	MH214A	0.25						0.0	0.0	4.00	0.00		0.00	0.90	0.90		0.00	0.78	1.15	1.15	0.32	0.00	1.10	73.41	98.28	250	1.40	1.449	72.30	98.50%
chemin Wanaki Road	214A, COM2	MH214A	*BULK153AN*	0.16						0.0	0.0	4.00	0.00		0.00	0.65	1.55		0.00	1.35	0.81	1.96	0.55	0.00	1.89	51.91	44.22	250	0.70	1.024	50.01	96.35%
Phase 1B																																
chemin Wanaki Road	143B	BULK143AE	MH143A	0.31						104.0	104.0	4.00	1.69		0.00		0.00		0.00	0.00	0.31	0.31	0.09	0.00	1.77	43.87	21.50	250	0.50	0.866	42.10	95.96%
chemin Wanaki Road	143A	MH143A	MH144A	0.27						0.0	104.0	4.00	1.69		0.00		0.00		0.00	0.00	0.27	0.58	0.16	0.00	1.85	87.74	47.73	250	2.00	1.731	85.89	97.89%
chemin Wanaki Road	144A, 144B	MH144A	MH145A	0.72						0.0	104.0	4.00	1.69		0.00		0.00		0.00	0.00	0.72	1.30	0.36	0.00	2.05	87.74	40.57	250	2.00	1.731	85.69	97.66%
chemin Wanaki Road	145A, 145B, 145C	MH145A	MH146A	2.77						835.6	939.6	3.82	14.53		0.00		0.00		0.00	0.00	2.77	4.07	1.14	0.00	15.67	107.45	53.01	250	3.00	2.121	91.79	85.42%
chemin Wanaki Road	146A	MH146A	MH147A	0.14						0.0	939.6	3.82	14.53		0.00		0.00		0.00	0.00	0.14	4.21	1.18	0.00	15.71	43.54	37.48	250	1.00	1.224	27.83	63.92%
chemin Wanaki Road	PARK2	BLK147AE	MH147A	0.55						0.0	0.0	4.00	0.00		0.00		0.00		0.00	0.00	0.55	0.55	0.15	0.00	0.15	39.24	17.66	250	0.40	0.774	39.08	99.61%
chemin Wanaki Road	147C	BLK147AW	MH147A	0.10						33.6	33.6	4.00	0.54		0.00		0.00		0.00	0.00	0.10	0.10	0.03	0.00	0.57	43.87	17.33	250	0.50	0.866	43.30	98.70%
chemin Wanaki Road	147A	MH147A	MH170A	0.03						0.0	973.2	3.81	15.01		0.00		0.00		0.00	0.00	0.03	4.89	1.37	0.00	16.38	31.02	10.23	250	0.25	0.612	14.64	47.19%
chemin Wanaki Road	147B	MH107A	MH147C	0.16						0.0	973.2	3.81	15.01		0.00		0.00		0.00	0.00	0.16	5.05	1.41	0.00	16.42	31.02	39.00	250	0.25	0.612	14.59	47.05%
chemin Wanaki Road		MH147C	*BLK148AW*							0.0	973.2	3.81	15.01		0.00		0.00		0.00	0.00	0.00	5.05	1.41	0.00	16.42	31.02	11.77	250	0.25	0.612	14.59	47.05%
Phase 1B																																
Block 9	154A	*MH158A*	MH217A	0.19						0.0	973.2	3.81	15.01		2.62		3.83		0.00	5.60	0.19	12.94	3.62	0.00	24.23	53.37	171.95	250	0.74	1.053	29.13	54.59%
croissant Squadron Crescent	215Aa-b	MH215A	MH216A	0.79	3	4				117.8	117.8	4.00	1.91		0.00		0.00		0.00	0.00	0.79	0.79	0.22	0.00	2.13	50.02	80.00	250	0.65	0.987	47.89	95.74%
croissant Squadron Crescent	216Aa-b	MH216A	MH217A	0.67	2	6				94.5	212.3	4.00	3.44		0.00		0.00		0.00	0.00	0.67	1.46	0.41	0.00	3.85	50.02	71.19	250	0.65	0.987	46.17	92.30%
croissant Squadron Crescent	217A	MH217A	MH218A	0.02						0.0	1185.5	3.75	18.01		2.62		3.83		0.00	5.60	0.02	14.42	4.04	0.00	27.65	36.70	10.52	250	0.35	0.724	9.05	24.66%
croissant Squadron Crescent	218A	MH218A	MH218B	0.02						0.0	1185.5	3.75	18.01		2.62		3.83		0.00	5.60	0.02	14.44	4.04	0.00	27.66	36.70	12.49	250	0.35	0.724	9.05	24.65%
	THORN1	*EX SANMH*	MH218B						5.55	1574.0	1574.0	3.66	23.36		0.00		0.00		0.00	0.00	5.55	5.55	1.55	0.00	24.92	74.13	46.02	300	0.54	1.016	49.21	66.39%
croissant Squadron Crescent	218B	MH218B	MH219A	0.07						0.0	2759.5	3.47	38.82		2.62		3.83		0.00	5.60	0.07	20.06	5.62	0.00	50.04	59.68	37.08	300	0.35	0.818	9.64	16.16%
croissant Squadron Crescent	219A	MH219A	MH220A	0.15						0.0	2759.5	3.47	38.82		2.62		3.83		0.00	5.60	0.15	20.21	5.66	0.00	50.08	59.68	72.49	300	0.35	0.818	9.60	16.09%
croissant Squadron Crescent	220A, 220B	MH220A	MH221A	1.46						319.0	3078.5	3.43	42.81		2.62		3.83		0.00	5.60	1.46	21.67	6.07	0.00	54.48	59.68	43.77	300	0.35	0.818	5.21	8.72%
croissant Squadron Crescent	221A	MH221A	MH222A	0.02						0.0	3078.5	3.43	42.81		2.62		3.83		0.00	5.60	0.02	21.69	6.07	0.00	54.48	59.68	8.66	300	0.35	0.818	5.20	8.71%
croissant Squadron Crescent	222A	MH222A	*MH169A*	0.22						0.0	3078.5	3.43	42.81		2.62		3.83		0.00	5.60	0.22	21.91	6.13	0.00	54.54	59.68	89.42	300	0.35	0.818	5.14	8.61%

Design Parameters:

Residential			ICI Areas			
						Peak Factor
SF	3.4	p/p/u	INST	50,000	L/Ha/day	1.5
TH/SD	2.7	p/p/u	COM	50,000	L/Ha/day	1.5
APT	1.8	p/p/u	IND	35,000	L/Ha/day	MOE Chart
Other	60	p/p/Ha		17000	L/Ha/day	

Notes:
1. Mannings coefficient (n) = 0.013
2. Demand (per capita): 350 L/day 300 L/day
3. Infiltration allowance: 0.28 L/s/Ha
4. Residential Peaking Factor:
Harmon Formula = 1+(14/(4+P^0.5))
where P = population in thousands

Designed: WY

Checked: JIM

Dwg. Reference: 38298-501

No.	Revision	Date
1.	City submission No. 1	7/8/2016
2.	City submission No. 2	11/4/2016
3.	City submission No. 3	1/25/2017

File Reference:	Date:	Sheet No:
38298.5.7.1	7/8/2016	1 of 2

IBI GROUP
400-333 Preston Street
Ottawa, Ontario K1S 5N4 Canada
tel 613 225 1311 fax 613 225 9868
ibigroup.com

SANITARY SEWER DESIGN SHEET

Former CFB Rockcliffe
City of Ottawa
Canada Lands Company

LOCATION				RESIDENTIAL										ICI AREAS							INFILTRATION ALLOWANCE			FIXED FLOW	TOTAL FLOW	PROPOSED SEWER DESIGN						
				AREA	UNIT TYPES				AREA	POPULATION		PEAK	PEAK	AREA (Ha)						PEAK	AREA (Ha)		FLOW			CAPACITY	LENGTH	DIA	SLOPE	VELOCITY	AVAILABLE CAPACITY	
STREET	AREA ID	FROM MH	TO MH	Phase 1B (Ha)	SF	SD	TH	APT	EXTERNAL (Ha)	IND	CUM	FACTOR	FLOW (L/s)	INSTITUTIONAL IND	INSTITUTIONAL CUM	COMMERCIAL IND	COMMERCIAL CUM	INDUSTRIAL IND	INDUSTRIAL CUM	FLOW (L/s)	IND	CUM	(L/s)	(L/s)	(L/s)	(L/s)	(m)	(mm)	(%)	(full) (m/s)	L/s	(%)
Phase 1A																																
croissant Squadron Crescent		*MH169A*	*MH165A*							0.0	3078.5	3.43	42.81		2.62		3.83		0.00	5.60	0.00	21.91	6.13	0.00	54.54	63.80	*27.00*	*300*	*0.40*	0.874	9.26	14.51%
Phase 1B																																
rue Moses Tennisco Street	212A	MH212A	MH213A	1.20						252.0	252.0	4.00	4.08		0.00		0.00		0.00	0.00	1.20	1.20	0.34	0.00	4.42	50.02	63.80	250	0.65	0.987	45.60	91.16%
rue Moses Tennisco Street	213A	MH213A	*BULK165AN*	0.35						52.5	304.5	4.00	4.93		0.00		0.00		0.00	0.00	0.35	1.55	0.43	0.00	5.37	39.24	50.79	250	0.40	0.774	33.87	86.32%
Phase 1A																																
rue Moses Tennisco Street		*BULK165AN*	*MH165A*							0.0	304.5	4.00	4.93		0.00		0.00		0.00	0.00	0.00	1.55	0.43	0.00	5.37	39.24	*22.50*	*250*	*0.40*	0.774	33.87	86.32%
Phase 1B																																
rue Michael Stoqua Street	210A	MH210A	MH211A	0.40						52.5	52.5	4.00	0.85		0.00		0.00		0.00	0.00	0.40	0.40	0.11	0.00	0.96	50.02	64.80	250	0.65	0.987	49.05	98.08%
rue Michael Stoqua Street	211A	MH211A	MH166B	0.35						52.5	105.0	4.00	1.70		0.00		0.00		0.00	0.00	0.35	0.75	0.21	0.00	1.91	50.02	52.19	250	0.65	0.987	48.11	96.18%
Phase 1A																																
rue Michael Stoqua Street		MH166B	*MH166A*							0.0	105.0	4.00	1.70		0.00		0.00		0.00	0.00	0.00	0.75	0.21	0.00	1.91	39.24	*21.10*	*250*	*0.40*	0.774	37.33	95.13%
Phase 1B																																
rue Bareille-Snow Street	208A	MH208A	MH209A	1.01						207.4	207.4	4.00	3.36		0.00		0.00		0.00	0.00	1.01	1.01	0.28	0.00	3.64	50.02	64.85	250	0.65	0.987	46.37	92.72%
rue Bareille-Snow Street	209A	MH209A	MH167B	0.35						52.6	260.0	4.00	4.21		0.00		0.00		0.00	0.00	0.35	1.36	0.38	0.00	4.59	50.02	52.87	250	0.65	0.987	45.42	90.82%
Phase 1A																																
rue Bareille-Snow Street		MH167B	*MH167A*							0.0	260.0	4.00	4.21		0.00		0.00		0.00	0.00	0.00	1.36	0.38	0.00	4.59	63.80	*20.43*	*300*	*0.40*	0.874	59.21	92.80%
Phase 1B																																
Codd's Road	230A	BLK231AN	MH231A						0.87	85.7	85.7	4.00	1.39		0.00		0.00		0.00	0.00	0.87	0.87	0.24	0.00	1.63	75.98	3.00	250	1.50	1.500	74.35	97.85%
Codd's Road	231A, EXPARK1	MH231A	*BULK176AN*						0.76	43.3	129.0	4.00	2.09		0.00		0.00		0.00	0.00	0.76	1.63	0.46	0.00	2.55	87.74	50.22	250	2.00	1.731	85.19	97.10%
Phase 1A																																
Codd's Road		*BULK176AN*	*MH176A*							0.0	129.0	4.00	2.09		0.00		0.00		0.00	0.00	0.00	1.63	0.46	0.00	2.55	55.49	*23.23*	*250*	*0.80*	1.095	52.94	95.41%

Design Parameters:

Residential			ICI Areas			
						Peak Factor
SF	3.4	p/p/u				
TH/SD	2.7	p/p/u	INST	50,000	L/Ha/day	1.5
APT	1.8	p/p/u	COM	50,000	L/Ha/day	1.5
Other	60	p/p/Ha	IND	35,000	L/Ha/day	MOE Chart
				17000	L/Ha/day	

Notes:

1. Mannings coefficient (n) = 0.013
2. Demand (per capita): 350 L/day 300 L/day
3. Infiltration allowance: 0.28 L/s/Ha
4. Residential Peaking Factor:
   Harmon Formula = 1+(14/(4+P^0.5))
   where P = population in thousands

Designed: WY

Checked: JIM

Dwg. Reference: 38298-501

No.	Revision	Date
1.	City submission No. 1	7/8/2016
2.	City submission No. 2	11/4/2016
3.	City submission No. 3	1/25/2017

File Reference:	Date:	Sheet No:
38298.5.7.1	7/8/2016	2 of 2

REVIEWED BY
DEVELOPMENT REVIEW SERVICES BRANCH

Signed _____


Date _____ 2017

Plan Number _____

LEGEND :

S168 2.01|0.80 — AREA NUMBER / RUNOFF COEFFICIENT / AREA IN HECTARES

POTENTIAL DRAINAGE DIRECTION



No.	REVISIONS	By	Date
14			
13			
12			
11			
10			
9			
8			
7			
6	REVISED PER MOECC COMMENTS	J.I.M.	2017:06:07
5	ISSUED FOR TENDER	J.I.M.	2017:03:23
4	SUBMISSION FOR MOECC APPROVAL	J.I.M.	2017:02:16
3	SUBMISSION No.3 FOR CITY REVIEW	J.I.M.	2017:01:25
2	SUBMISSION No.2 FOR CITY REVIEW	J.I.M.	2016:11:04
1	SUBMISSION No.1 FOR CITY REVIEW	J.I.M.	2016:07:08

CANADA LANDS COMPANY
SOCIÉTÉ IMMOBILIÈRE DU CANADA

30 Metcalfe Street Suite 601
Ottawa, On K1P 5L4
613 998 7777

IBI GROUP
400 – 333 Preston Street
Ottawa ON K1S 5N4 Canada
tel 613 225 1311 fax 613 225 9868
ibigroup.com

Project Title

WATERIDGE VILLAGE AT ROCKCLIFFE

PHASE 1B

PROFESSIONAL ENGINEER — J. I. MOFFATT — 17/06/07 — PROVINCE OF ONTARIO

Drawing Title

SANITARY DRAINAGE AREA PLAN

Scale: 1 : 2000

Design	Date
J.I.M.	MAY 2016
Drawn	Checked
M.M.	J.I.M.
Project No.	Drawing No.
38298	501A

D07-16-15-0003

#17063

L:\38298-CP\Acad\Civil\3 Drawings\Sanitary Drainage Area Plan\38298 SANITARY DRAINAGE AREA PLAN.dwg Layout: None SANITARY DRAINAGE AREA PLAN Plot Style: ibi STANDARD.ctb Plot Scale: 1:1.0 Plotted: Apr 4,2017 9:23 AM Last Saved By: monica.lust Saved: Apr 4,2017 9:23 AM

LEGEND

256A (aw00200) — NODE IDENTIFICATION (CITY SEWER NODE)

200mmØ — PROPOSED SANITARY SEWER SIZE AND DIRECTION

300mmØ FORCEMAIN — EXISTING FORCEMAIN AND SIZE

200mmØ CO — EXISTING SITE SEWER SIZE AND DIRECTION

RCAF SANITARY PUMP STATION

TO OTTAWA RIVER 900mmØ CO OVERFLOW

INLET SEWER FROM AVIATION MUSEUM

300mmØ FORCEMAIN

(rc00900)

300mmØ CO

RCAF PULL-BACK SEWER

300mmØ CO

NRC SHAFT

675mmØ CO

675mmØ CO OUTFALL

EXISTING AIR BASE PULLBACK SEWER 300mmØ @ 0.69% CAPACITY ±84.l/s

(aw00100)

ALVIN HEIGHTS PULL-BACK SEWER (300mmØ CO)

AIR BASE SEWER (750mmØ CO)

(aw00200)

300mmØ CO

750mmØ CO

FUTURE MUSEUM

CODD'S ROAD SHAFT

CONNECT TO EXISTING CODD'S ROAD SHAFT INVERT 76.85m

OTTAWA INTERCEPTOR OUTFALL (2400mmØ CO)

INTERCEPT EXISTING SANITARY INVERT ±86.40m

EXISTING THORNCLIFFE VILLAGE SANITARY SEWER

CAP SEWER AND CONSTRUCT TEMPORARY OVER FLOW TO SWM FACILITY

PEACH TREE LANE SHAFT

EXISTING MONTFORT HOSPITAL SANITARY SEWER

N


Scale 0 100 200

Project Title
DESIGN BRIEF
WATERIDGE VILLAGE
AT ROCKCKIFFE
PHASE 1A

Drawing Title
RECOMMENDED
WASTEWATER PLAN

Sheet No.
FIGURE 3.1

J:\36298-CFBRockcliffe\5.9 Drawings\5eCivil\Current\DESIGN BRIEF FIGURES\Figure 3.1 Recommended Wastewater Plan.dwg Layout Name: FIGURE 3.1 Plot Style: AIA STANDARD COLOR-HALF.CTB Plot Scale: 1:0.969 Plotted At: 1/27/2016 12:26 PM Last Saved By: mmilne Last Saved At: Jan. 26, 16



Sheet No.

FIGURE 5.1

Drawing Title

RECOMMENDED WASTEWATER PLAN

Project Title

FORMER CFB ROCKCLIFFE MASTER SERVICING STUDY

Scale

IBI

Wateridge Block 15
Wastewater Flow per MSS

Wastewater Design Flows per Unit Count
City of Ottawa Sewer Design Guidelines, 2012

Site Area 1.960 **ha**

Extraneous Flow Allowances

Infiltration / Inflow	**0.55**	**L/s**

Domestic Contributions

Unit Type	**Unit Rate**	**Units**	**Pop**
Single Family	3.4		0
Semi-detached and duplex	2.7		0
Townhouse	2.7		487
Apartment			
Bachelor	1.4		0
1 Bedroom	1.4		0
2 Bedroom	2.1		0
3 Bedroom	3.1		0
Average	1.8		

Total Pop	**487**	
Average Domestic Flow	**1.97**	**L/s**
Peaking Factor	**3.98**	
Peak Domestic Flow	**7.85**	**L/s**

Institutional / Commercial / Industrial Contributions

Property Type	**Unit Rate**		**No. of Units**	**Avg Wastewater (L/s)**
Commercial floor space*	5	$L/m^2/d$		0.00
Hospitals	900	L/bed/d		0.00
School	70	L/student/d		0.00
Industrial - Light**	35,000	L/gross ha/d		0.00
Industrial - Heavy**	55,000	L/gross ha/d		0.00

Average I/C/I Flow	**0.00**
Peak Institutional / Commercial Flow	0.00
Peak Industrial Flow**	0.00
Peak I/C/I Flow	**0.00**

** assuming a 12 hour commercial operation*

*** peak industrial flow per City of Ottawa Sewer Design Guidelines Appendix 4B*

Total Estimated Average Dry Weather Flow Rate	**1.97**	**L/s**
Total Estimated Peak Dry Weather Flow Rate	**7.85**	**L/s**
Total Estimated Peak Wet Weather Flow Rate	**8.40**	**L/s**

DSEL©

Wateridge Block 15
Proposed Site Conditions

Wastewater Design Flows per Unit Count
City of Ottawa Sewer Design Guidelines, 2012

Site Area 1.960 **ha**

Extraneous Flow Allowances

Infiltration / Inflow (Dry)	**0.10 L/s**
Infiltration / Inflow (Wet)	**0.55 L/s**
Infiltration / Inflow (Total)	**0.65 L/s**

Extraneous Flow Allowances

Infiltration / Inflow **0.65 L/s**

Domestic Contributions

Unit Type	Unit Rate	Units	Pop
Single Family	3.4		0
Semi-detached and duplex	2.7		0
Townhouse	2.7	192	519
			0
Apartment			
Bachelor	1.4		0
1 Bedroom	1.4		0
2 Bedroom	2.1		0
3 Bedroom	3.1		0
Average	1.8		0

Total Pop **519**

Average Domestic Flow **1.68 L/s**

Peaking Factor **3.37**

Peak Domestic Flow **5.67 L/s**

Institutional / Commercial / Industrial Contributions

Property Type	Unit Rate	No. of Units	Avg Wastewater (L/s)
Dining room	125 L/seat/d		0.00
Commercial floor space	28,000.0 L/ha/d		0.00
Water Closets**	150 L/hr		0.00
Laundry Facility	1,200 L/unit/d		0.00

Average I/C/I Flow **0.00**

Peak Institutional / Commercial Flow 0.00
Peak I/C/I Flow **0.00**

Total Estimated Average Dry Weather Flow Rate	**1.78 L/s**
Total Estimated Peak Dry Weather Flow Rate	**6.22 L/s**
Total Estimated Peak Wet Weather Flow Rate	**7.52 L/s**

** Water closets demand of 150 L/hour from Appendix 4-A of the Sewer design guidelines, assuming a 12 hour operation

DSEL©

Mattamy Homes
Wateridge Block 15
Proposed Development - Internal Sanitary Flow

Wastewater Design Flows per Unit Count
City of Ottawa Sewer Design Guidelines, 2012

Site Area* 1.560 **ha**

Extraneous Flow Allowances

Infiltration / Inflow (Dry)	**0.08 L/s**
Infiltration / Inflow (Wet)	**0.44 L/s**
Infiltration / Inflow (Total)	**0.51 L/s**

Extraneous Flow Allowances

Infiltration / Inflow	**0.51 L/s**

Domestic Contributions*

Unit Type	Unit Rate	Units	Pop
Single Family	3.4		0
Semi-detached and duplex	2.7		0
Townhouse	2.7	158	427
			0
Apartment			
Bachelor	1.4		0
1 Bedroom	1.4		0
2 Bedroom	2.1		0
3 Bedroom	3.1		0
Average	1.8		0

Total Pop	**427**
Average Domestic Flow	**1.38 L/s**
Peaking Factor	**3.41**
Peak Domestic Flow	**4.71 L/s**

Institutional / Commercial / Industrial Contributions

Property Type	Unit Rate	No. of Units	Avg Wastewater (L/s)
Dining room	125 L/seat/d		0.00
Commercial floor space	28,000.0 L/ha/d		0.00
Water Closets**	150 L/hr		0.00
Laundry Facility	1,200 L/unit/d		0.00

Average I/C/I Flow	**0.00**
Peak Institutional / Commercial Flow	0.00
Peak I/C/I Flow	**0.00**

Total Estimated Average Dry Weather Flow Rate	**1.46 L/s**
Total Estimated Peak Dry Weather Flow Rate	**5.15 L/s**
Total Estimated Peak Wet Weather Flow Rate	**6.18 L/s**

*Consists only of areas and units tributary to the proposed internal sewer network and does not include areas for units discharging to the existing sewer within Squadron Crescent.

** Water closets demand of 150 L/hour from Appendix 4-A of the Sewer design guidelines, assuming a 12 hour operation

DSEL©

SANITARY SEWER CALCULATION SHEET

Manning's n=0.013

LOCATION			RESIDENTIAL AREA AND POPULATION							COMM		INSTIT		PARK		C+I+I	INFILTRATION				PIPE						
STREET	FROM M.H.	TO M.H.	AREA (ha)	UNITS	POP.	CUMULATIVE AREA (ha)	CUMULATIVE POP.	PEAK FACT.	PEAK FLOW (l/s)	AREA (ha)	ACCU. AREA (ha)	AREA (ha)	ACCU. AREA (ha)	AREA (ha)	ACCU. AREA (ha)	PEAK FLOW (l/s)	TOTAL AREA (ha)	ACCU. AREA (ha)	INFILT. FLOW (l/s)	TOTAL FLOW (l/s)	DIST (m)	DIA (mm)	SLOPE (%)	CAP. (FULL) (l/s)	RATIO Q act/Q cap	VEL. (FULL) (m/s)	VEL. (ACT.) (m/s)
Makwa Private																											
Contribution From Kiniw Private, Pipe 101A - 102A						0.04	11				0.00		0.00		0.00		0.04	0.04									
	102A	105A	0.14		19	0.18	30	3.5	0.34		0.00		0.00		0.00	0.00	0.14	0.18	0.05	0.39	53.40	200	0.40	20.74	0.02	0.66	0.26
Contribution From Private Lane, Pipe 104A - 105A						0.20	60				0.00		0.00		0.00		0.20	0.20									
	105A	106A	0.10		14	0.48	104	3.4	1.14		0.00		0.00		0.00	0.00	0.10	0.48	0.14	1.28	37.10	200	0.40	20.74	0.06	0.66	0.36
	106A	107A	0.05		6	0.53	110	3.4	1.21		0.00		0.00		0.00	0.00	0.05	0.53	0.15	1.36	7.15	200	0.34	19.12	0.07	0.61	0.35
	107A	115A	0.12		36	0.65	146	3.4	1.59		0.00		0.00		0.00	0.00	0.12	0.65	0.19	1.77	40.80	200	0.40	20.74	0.09	0.66	0.40
To Takamose Private, Pipe 115A - 116A						0.65	146				0.00		0.00		0.00			0.65									
Mikinak Road (Rear Yard Service)																											
	111A	113A	0.14		81	0.14	81	3.4	0.90		0.00		0.00		0.00	0.00	0.14	0.14	0.04	0.94	105.85	200	0.80	29.34	0.03	0.93	0.42
To Servicing Between Block 1 and 2, Pipe 113A - 114A						0.14	81				0.00		0.00		0.00			0.14									
	112A	113A	0.05		27	0.05	27	3.5	0.31		0.00		0.00		0.00	0.00	0.05	0.05	0.01	0.32	33.40	200	0.65	26.44	0.01	0.84	0.28
To Servicing Between Block 1 and 2, Pipe 113A - 114A						0.05	27				0.00		0.00		0.00			0.05									
Servicing Between Block 1 and 2																											
Contribution From Mikinak Road (Rear Yard Service), Pipe 111A - 113A						0.14	81				0.00		0.00		0.00		0.14	0.14									
Contribution From Mikinak Road (Rear Yard Service), Pipe 112A - 113A						0.05	27				0.00		0.00		0.00		0.05	0.19									
	113A	114A				0.19	108	3.4	1.19		0.00		0.00		0.00	0.00	0.00	0.19	0.05	1.24	34.45	200	1.35	38.11	0.03	1.21	0.55
To Takamose Private, Pipe 114A - 115A						0.19	108				0.00		0.00		0.00			0.19									
Private Lane																											
	103A	104A	0.20		60	0.20	60	3.4	0.67		0.00		0.00		0.00	0.00	0.20	0.20	0.06	0.73	44.02	200	0.65	26.44	0.03	0.84	0.36
	104A	105A	0.00		0	0.20	60	3.4	0.67		0.00		0.00		0.00	0.00	0.00	0.20	0.06	0.73	6.50	200	0.40	20.74	0.03	0.66	0.30
To Makwa Private, Pipe 110A - 114A						0.20	60				0.00		0.00		0.00			0.20									
Kiniw Private																											
	101A	102A	0.04		11	0.04	11	3.5	0.13		0.00		0.00		0.00	0.00	0.04	0.04	0.01	0.14	29.70	200	0.65	26.44	0.01	0.84	0.22
To Makwa Private, Pipe 102A - 103A						0.04	11				0.00		0.00		0.00			0.04									
	102A	110A	0.27		68	0.27	68	3.4	0.76		0.00		0.00		0.00	0.00	0.27	0.27	0.08	0.83	78.80	200	0.65	26.44	0.03	0.84	0.38
To Takamose Private, Pipe 108A - 110A						0.27	68				0.00		0.00		0.00			0.27									
Takamose Private																											
	109A	110A	0.08		22	0.08	22	3.5	0.25		0.00		0.00		0.00	0.00	0.08	0.08	0.02	0.27	29.81	200	0.65	26.44	0.01	0.84	0.27
Contribution From Kiniw Private, Pipe 102A - 108A						0.27	68				0.00		0.00		0.00		0.27	0.35									
	110A	114A	0.27		60	0.62	150	3.4	1.63		0.00		0.00		0.00	0.00	0.27	0.62	0.18	1.81	80.47	200	1.54	40.70	0.04	1.30	0.64
Contribution From Servicing Between Block 1 and 2, Pipe 113A - 114A						0.19	108				0.00		0.00		0.00		0.19	0.81									
	114A	115A	0.03		6	0.84	264	3.3	2.81		0.00		0.00		0.00	0.00	0.03	0.84	0.24	3.05	8.03	200	0.33	18.84	0.16	0.60	0.44
Contribution From Makwa Private, Pipe 107A - 115A						0.65	146				0.00		0.00		0.00		0.65	1.49									
	115A	116A	0.08		22	1.57	432	3.2	4.49		0.00		0.00		0.00	0.00	0.08	1.57	0.45	4.94	30.06	200	0.35	19.40	0.25	0.62	0.51
	116A	117A				1.57	432	3.2	4.49		0.00		0.00		0.00	0.00	0.00	1.57	0.45	4.94	11.08	200	2.35	50.28	0.10	1.60	1.01

DESIGN PARAMETERS

Park Flow =	9300	L/ha/da	0.10764	l/s/Ha			
Average Daily Flow =	280	l/p/day			Industrial Peak Factor = as per MOE Graph		
Comm/Inst Flow =	28000	L/ha/da	0.3241	l/s/Ha	Extraneous Flow =	0.286	L/s/ha
Industrial Flow =	35000	L/ha/da	0.40509	l/s/Ha	Minimum Velocity =	0.600	m/s
Max Res. Peak Factor =	4.00				Manning's n = (Conc)	0.013 (Pvc)	0.013
Commercial/Inst./Park Peak Factor =	1.00				Townhouse coeff=	2.7	
Institutional =	0.32	l/s/Ha			Single house coeff=	3.4	

Designe G.G.G.

Checkec S.L.M

Dwg. Reference: Sanitary Drainage Plan, Dwgs. No.

PROJECT Mattamy Homes Wateridge Village Block 15

LOCATIO Wateridge Village Block 15

City of Ottawa

File Ref: 17-946

Date: **November 29 2019**

Sheet No. 1 of 1

LICENSED PROFESSIONAL ENGINEER S. L. MERRICK 100186523 2019-12-06 PROVINCE OF ONTARIO

JOB #17-946

2019-12-10_946_SAN_ggg.xlsx

EXTERNAL SANITARY SEWER CALCULATION SHEET

Manning's n=0.013

LOCATION				RESIDENTIAL AREA AND POPULATION							COMM		INSTIT		PARK		C+I+I	INFILTRATION				PIPE						
STREET		FROM M.H.	TO M.H.	AREA (ha)	UNITS	POP.	CUMULATIVE AREA (ha)	CUMULATIVE POP.	PEAK FACT.	PEAK FLOW (l/s)	AREA (ha)	ACCU. AREA (ha)	AREA (ha)	ACCU. AREA (ha)	AREA (ha)	ACCU. AREA (ha)	PEAK FLOW (l/s)	TOTAL AREA (ha)	ACCU. AREA (ha)	INFILT. FLOW (l/s)	TOTAL FLOW (l/s)	DIST (m)	DIA (mm)	SLOPE (%)	CAP. (FULL) (l/s)	RATIO Q act/Q cap	VEL. (FULL) (m/s)	VEL. (ACT.) (m/s)
Squadron Crescent																												
From Block 15 to pipe between MH215A and MH216A				0.06	6	16	0.06	16	3.7	0.19		0.00		0.00		0.00	0.00	0.06	0.06	0.02	0.21							
	215Aa	215A	216A	0.45		21	0.51	37	3.7	0.44		0.00		0.00		0.00	0.00	0.45	0.51	0.15	0.59	80.0	250	0.65	47.94	0.01	0.98	0.33
From Block 15 to pipe between MH216A and MH217A				0.90	8	22	0.90	59	3.6	0.69		0.00		0.00		0.00	0.00	0.90	1.41	0.40	1.10							
	216Aa	216A	217A	0.42		23	1.83	82	3.6	0.96		0.00		0.00		0.00	0.00	0.42	1.83	0.52	1.48	71.2	250	0.65	47.94	0.03	0.98	0.44
Block 9	154A			0.19		973	2.02	1055	3.2	11.03	2.620	2.62	3.830	3.83		0.00	2.09	6.64	12.94	3.70	16.83							
	217A	217A	218A	0.02		0	2.04	1055	3.2	11.03		2.62		3.83		0.00	2.09	0.02	12.96	3.71	16.83	10.5	250	0.35	35.18	0.48	0.72	0.71
From Block 15 to pipe between MH218A and MH218B				0.02	1	3	2.06	1058	3.2	11.06		2.62		3.83		0.00	2.09	0.02	12.98	3.71	16.86							
	218A	218A	218B	0.02		0	4.12	1058	3.2	11.06		2.62		3.83		0.00	2.09	0.02	13.00	3.72	16.87	12.5	250	0.35	35.18	0.48	0.72	0.71
THORN1							5.55	1574				0.00		0.00		0.00		5.55	5.55									
From Block 15 to pipe between MH218B and MH219A				0.02	1	3	9.69	2634	3.0	25.54		2.62		3.83		0.00	2.09	0.02	18.57	5.31	32.94							
	218B	218B	219A	0.07		0	9.76	2634	3.0	25.54		2.62		3.83		0.00	2.09	0.07	18.64	5.33	32.96	37.1	300	0.35	57.21	0.58	0.81	0.84
From Block 15 to pipe between MH219A and MH220A				0.10	10	27	9.86	2661	3.0	25.78		2.62		3.83		0.00	2.09	0.10	18.74	5.36	33.23							
	219A	219A	220A	0.15		0	10.01	2661	3.0	25.78		2.62		3.83		0.00	2.09	0.15	18.89	5.40	33.27	72.5	300	0.35	57.21	0.58	0.81	0.84
	220B			0.00		0	10.01	2661	3.0	25.78		2.62		3.83		0.00	2.09	0.00	18.89	5.40	33.27							
From Block 15 to pipe between MH220A and MH221A				0.05	3	8	10.06	2669	3.0	25.85		2.62		3.83		0.00	2.09	0.05	18.94	5.42	33.35							
	220A	220A	221A	0.09		0	10.15	2669	3.0	25.85		2.62		3.83		0.00	2.09	0.09	19.03	5.44	33.38	43.8	300	0.35	57.21	0.58	0.81	0.84
	221A	221A	222A	0.02		0	10.17	2669	3.0	25.85		2.62		3.83		0.00	2.09	0.02	19.05	5.45	33.39	8.7	300	0.35	57.21	0.58	0.81	0.84
From Block 15 to pipe between MH222A and MH117A				0.08	3	8	10.25	2677	3.0	25.92		2.62		3.83		0.00	2.09	0.08	19.13	5.47	33.48							
	222A	222A	117A	0.22		0	10.47	2677	3.0	25.92		2.62		3.83		0.00	2.09	0.22	19.35	5.53	33.54	65.9	300	0.35	57.21	0.59	0.81	0.84
Contribution From Block 15, Pipe 116A - 117A							1.57	432.00				0.00		0.00		0.00		1.57	20.92									
	221A	117A	169A	0.02		0	12.06	3109	2.9	29.66		2.62		3.83		0.00	2.09	0.02	20.94	5.99	37.74	22.8	300	0.35	57.21	0.66	0.81	0.86

DESIGN PARAMETERS

Park Flow =	9300	L/ha/da	0.10764	l/s/Ha	Industrial Peak Factor = as per MOE Graph		
Average Daily Flow =	280	l/p/day					
Comm/Inst Flow =	28000	L/ha/da	0.3241	l/s/Ha	Extraneous Flow =	0.286	L/s/ha
Industrial Flow =	35000	L/ha/da	0.40509	l/s/Ha	Minimum Velocity =	0.600	m/s
Max Res. Peak Factor =	4.00				Manning's n = (Conc)	0.013 (Pvc)	0.013
Commercial/Inst./Park Peak Factor =	1.00				Townhouse coeff=	2.7	
Institutional =	0.32	l/s/Ha			Single house coeff=	3.4	

Designer G.G.G.

Checked J.A.

Dwg. Reference:
Sanitary Drainage Plan, Dwgs. No.

PROJECT Mattamy Homes Wateridge Village Block 15

LOCATIO Wateridge Village Block 15

City of Ottawa

File Ref: 17-946

Date: 04 Oct 2019

Sheet No 1
of 1

LICENSED PROFESSIONAL ENGINEER
S. MERRICK
100136523
2019-12-04
PROVINCE OF ONTARIO

APPENDIX D

Stormwater Management

IBI GROUP
400-333 Preston Street
Ottawa, Ontario K1S 5N4 Canada
tel 613 225 1311 fax 613 225 9868
ibigroup.com

STORM SEWER DESIGN SHEET

Former CFB Rockcliffe
City of Ottawa
Name of Client/Developer

LOCATION				AREA (Ha)										RATIONAL DESIGN FLOW												SEWER DATA								
STREET	AREA ID	FROM	TO	C= 0.20	C= 0.30	C= 0.45	C= 0.50	C= 0.56	C= 0.60	C= 0.65	C= 0.70	C= 0.73	C= 0.80	IND 2.78AC	CUM 2.78AC	INLET (min)	TIME IN PIPE	TOTAL (min)	i (5) (mm/hr)	i (10) (mm/hr)	i (100) (mm/hr)	5yr PEAK FLOW (L/s)	10yr PEAK FLOW (L/s)	100yr PEAK FLOW (L/s)	FIXED FLOW (L/s)	DESIGN FLOW (L/s)	CAPACITY (L/s)	LENGTH (m)	PIPE SIZE (mm) DIA	W	H	SLOPE (%)	VELOCITY (m/s)	AVAIL CAP (5yr) (L/s)	(%)
Phase 1B																																		
Hemlock Road	S201A-B, EX201	MH201	MH202								0.31		0.56	1.85	1.85	10.00	1.17	11.17	104.19	122.14	178.56	192.62				192.62	210.32	90.18	450			0.50	1.281	17.70	8.41%
Future Street No. 6	EX202A	BULK202N	MH202										0.90	2.00	2.00	12.23	0.27	12.50	93.72	109.82	160.45	187.60				187.60	286.47	16.00	600			0.20	0.982	98.87	34.51%
Hemlock Road	S202A, EX202B-C	MH202	MH203								0.10		0.55	1.42	5.27	12.50	0.53	13.03	92.61	108.50	158.52	487.86				487.86	784.52	86.00	600			1.50	2.688	296.66	37.81%
Future Street No. 5	S203B, EX203	BULK203N	203								0.09		0.73	1.80	1.80	10.88	0.12	11.00	99.76	116.92	170.90	179.44				179.44	351.93	16.00	450			1.40	2.144	172.49	49.01%
Hemlock Road	S203A, EXP203	MH203	MH204		0.44						0.16			0.68	7.75	13.03	0.49	13.53	90.49	106.01	154.87	700.89				700.89	847.38	86.00	600			1.75	2.903	146.49	17.29%
rue Moses Tennisco Street	S204B, EX204A	BULK204N	MH204								0.08		0.72	1.76	1.76	10.89	0.11	11.00	99.72	116.87	170.81	175.20				175.20	399.05	16.00	450			1.80	2.431	223.85	56.10%
Hemlock Road	S204A, EX204B	MH204	MH205								0.14		0.47	1.32	10.82	13.53	0.54	14.07	88.63	103.82	151.66	958.99				958.99	1,272.26	90.00	750			1.20	2.790	313.27	24.62%
rue Michael Stoqua Street	S205A, EX205A	BULK205N	MH205								0.08		0.81	1.96	1.96	11.15	0.15	11.30	98.49	115.42	168.69	192.75				192.75	297.43	16.01	450			1.00	1.812	104.68	35.20%
Hemlock Road	S205B-C, EX205B	MH205	MH206								0.17		0.63	1.73	14.51	14.07	1.20	15.26	86.70	101.55	148.32	1,257.92				1,257.92	1,818.95	112.01	1200			0.20	1.558	561.03	30.84%
Temp Ditch	FUTURE PHASE	DI 10	BULK206N		7.68									6.41	6.41	59.66	0.16	59.82	33.08	38.61	56.13	211.89				211.89	297.43	17.03	450			1.00	1.812	85.54	28.76%
rue Bareille-Snow Street	S206A, EX206A	BULK206N	MH206								0.06		1.02	2.39	2.39	10.85	0.15	11.00	99.91	117.09	171.14	238.30				238.30	448.66	17.50	525			1.00	2.008	210.35	46.89%
Hemlock Road	S206B, EX206B	MH206	MH207								0.03		0.46	1.08	17.98	15.26	0.78	16.04	82.71	96.86	141.44	1,486.80				1,486.80	2,227.75	89.33	1200			0.30	1.908	740.96	33.26%
Block 20	P207	CBMH207N	MH207		0.32									0.27	0.27	10.00	0.27	10.27	104.19	122.14	178.56	27.81				27.81	63.80	14.00	300			0.40	0.874	36.00	56.42%
Hemlock Road	S207	MH207	*BULK176E*								0.22			0.43	18.67	16.04	0.37	16.42	80.33	94.05	137.32	1,499.75				1,499.75	2,156.55	32.62	1350			0.15	1.460	656.80	30.46%
Phase 1A																																		
Ex. Hemlock Road	S176C	*BULK176E*	*MH176*								0.02			0.04	18.71	16.42	0.27	16.69	79.24	92.78	135.45	1,482.57				1,482.57	2,156.55	*24.06*	*1350*			*0.15*	1.460	673.98	31.25%
Phase 1B																																		
Codd's Road	S230, LOT230A-B	230	231								0.16		0.70	1.87	1.87	10.00	0.63	10.63	104.19	122.14	178.56	194.65				194.65	364.28	84.30	450			1.50	2.219	169.63	46.57%
Codd's Road	S231, LOT231	231	*BULK176N*								0.12		0.30	0.90	2.77	10.63	0.36	11.00	100.96	118.34	172.97	279.55				279.55	549.49	53.76	525			1.50	2.459	269.94	49.12%
Phase 1A																																		
Ex. Codd's Road	---	*BULK176N*	*MH176*											0.00	2.95	11.77	0.29	12.06	95.69	112.12	163.84	281.96				281.96	339.63	*18.21*	*525*			*1.50*	0.919	57.67	16.98%
Phase 1B																																		
chemin Wanaki Road	S200, LOT200	MH200	MH214								0.20		0.91	2.41	2.41	10.00	0.78	10.78	104.19	122.14	178.56	251.42				251.42	351.93	99.75	450			1.40	2.144	100.51	28.56%
chemin Wanaki Road	S214, LOT214	MH214	*BULK152N*								0.19		0.84	2.24	4.65	10.78	0.42	11.20	100.27	117.52	171.77	466.34				466.34	535.93	46.51	600			0.70	1.836	69.59	12.99%
Phase 1B																																		
chemin Wanaki Road	EX143	BULK143E	MH143										0.33	0.73	0.73	10.00	0.29	10.29	104.19	122.14	178.56	76.47				76.47	129.34	20.00	375			0.50	1.134	52.87	40.88%
chemin Wanaki Road		MH143	MH144											0.00	0.73	10.29	0.37	10.66	102.67	120.34	175.92	75.35				75.35	258.68	50.50	375			2.00	2.269	183.33	70.87%
chemin Wanaki Road	S144, EX144	MH144	MH145		0.55						0.18			0.81	1.54	10.66	0.30	10.97	100.81	118.15	172.70	155.54				155.54	258.68	41.15	375			2.00	2.269	103.14	39.87%
chemin Wanaki Road	S145, EX145	MH145	MH146								0.15		2.74	6.39	7.93	10.97	0.28	11.24	99.35	116.44	170.18	787.69				787.69	1,324.21	48.01	750			1.30	2.904	536.53	40.52%
chemin Wanaki Road		MH146	MH147											0.00	7.93	11.24	0.25	11.49	98.06	114.92	167.95	777.46				777.46	2,296.77	38.53	1050			0.65	2.570	1519.32	66.15%
chemin Wanaki Road	S147C	BULK147E	MH147		0.40									0.33	0.33	10.00	0.28	10.28	104.19	122.14	178.56	34.76				34.76	71.33	16.51	300			0.50	0.978	36.58	51.27%
chemin Wanaki Road	EX147	BULK 147W	MH147	0.16										0.09	0.09	12.00	0.32	12.32	94.70	110.96	162.13	8.42				8.42	71.33	18.72	300			0.50	0.978	62.91	88.19%
chemin Wanaki Road		MH147	MH170											0.00	8.35	12.32	0.09	12.41	93.35	109.38	159.81	779.62				779.62	2,296.77	13.96	1050			0.65	2.570	1517.16	66.06%
chemin Wanaki Road	S147A	MH170	BOX CULVERT								0.14			0.27	8.62	12.41	0.10	12.51	92.98	108.94	159.17	801.83				801.83	2,296.77	15.00	1050			0.65	2.570	1494.94	65.09%
Phase 1B																																		
rue Moses Tennisco Street	S212, LOT212A-B	MH212	MH213								0.15		1.03	2.58	2.58	10.00	0.66	10.66	104.19	122.14	178.56	269.09				269.09	361.72	63.80	525			0.65	1.619	92.63	25.61%
rue Moses Tennisco Street	S213, LOT213	MH213	*BULK165N*								0.21		0.23	0.92	3.50	10.66	0.82	11.47	100.85	118.20	172.77	353.25				353.25	519.40	55.71	750			0.20	1.139	166.15	31.99%
Temp Ditch	BLOCK 24	DI 1	MH165N		1.60									1.33	1.33	26.41	0.25	26.66	58.73	68.69	100.13	78.37				78.37	129.34	17.03	375			0.50	1.134	50.96	39.40%
Phase 1A																																		
Ex. Street No. 3	---	*BULK165N*	*MH165*											0.00	3.50	11.47	0.24	11.71	97.01	113.68	166.14	339.81				339.81	519.40	*16.10*	*750*			*0.20*	1.139	179.59	34.58%

Definitions:
Q = 2.78CiA, where:
Q = Peak Flow in Litres per Second (L/s)
A = Area in Hectares (Ha)
i = Rainfall intensity in millimeters per hour (mm/hr)
[i = 998.071 / (TC+6.053)^0.814] 5 YEAR
[i = 1174.184 / (TC+6.014)^0.816] 10 YEAR
[i = 1735.688 / (TC+6.014)^0.820] 100 YEAR

Notes:
1. Mannings coefficient (n) = 0.013

Designed: WY
Checked: JIM
Dwg. Reference: 38298-500

No.	Revision	Date
1.	City submission No. 1	7/8/2016
2.	City submission No. 2	11/4/2016
3.	City submission No. 3	1/25/2017

File Reference: 38298.5.7.1
Date: 7/8/2016
Sheet No: 1 of 2

IBI GROUP
400-333 Preston Street
Ottawa, Ontario K1S 5N4 Canada
tel 613 225 1311 fax 613 225 9868
ibigroup.com

STORM SEWER DESIGN SHEET

Former CFB Rockcliffe
City of Ottawa
Name of Client/Developer

LOCATION				AREA (Ha)										RATIONAL DESIGN FLOW												SEWER DATA									
STREET	AREA ID	FROM	TO	C= 0.20	C= 0.25	C= 0.40	C= 0.50	C= 0.56	C= 0.60	C= 0.65	C= 0.70	C= 0.73	C= 0.80	IND 2.78AC	CUM 2.78AC	INLET (min)	TIME IN PIPE	TOTAL (min)	i (5) (mm/hr)	i (10) (mm/hr)	i (100) (mm/hr)	5yr PEAK FLOW (L/s)	10yr PEAK FLOW (L/s)	100yr PEAK FLOW (L/s)	FIXED FLOW (L/s)	DESIGN FLOW (L/s)	CAPACITY (L/s)	LENGTH (m)	PIPE SIZE (mm) DIA	W	H	SLOPE (%)	VELOCITY (m/s)	AVAIL CAP (5yr) (L/s)	(%)
Phase 1B																																			
Block 9	---	*MH157*	MH217											0.00	12.28	13.26	0.93	14.19	89.63	105.00	153.38	1,100.86				1,100.86	2,337.95	168.50	975			1.00	3.034	1237.09	52.91%
croissant Squadron Crescent	S215, R215	MH215	MH216					0.14				0.38		0.99	0.99	10.00	0.94	10.94	104.19	122.14	178.56	103.06				103.06	317.25	79.94	525			0.50	1.420	214.19	67.51%
croissant Squadron Crescent	S216, R216A-B	MH216	MH217					0.20				0.28		0.88	1.87	10.94	0.86	11.80	99.48	116.60	170.41	185.91				185.91	429.70	75.99	600			0.45	1.472	243.79	56.74%
croissant Squadron Crescent	---	MH217	MH218											0.00	14.15	14.19	0.10	14.29	86.28	101.05	147.59	1,220.93				1,220.93	1,911.03	12.94	1050			0.45	2.138	690.10	36.11%
croissant Squadron Crescent	S218	MH218	MH219								0.17			0.33	14.48	14.29	0.51	14.80	85.93	100.64	146.99	1,244.42				1,244.42	1,424.40	49.00	1050			0.25	1.594	179.98	12.64%
croissant Squadron Crescent	---	MH219	MH220											0.00	14.48	14.80	0.90	15.70	84.21	98.62	144.02	1,219.47				1,219.47	1,575.26	73.09	1200			0.15	1.349	355.79	22.59%
croissant Squadron Crescent	S220, LOT220	MH220	MH221								0.18		1.96	4.71	19.19	15.70	0.54	16.24	81.35	95.26	139.09	1,561.24				1,561.24	1,575.26	43.47	1200			0.15	1.349	14.02	0.89%
														FIXED OUTLET FLOW FROM SWM FACILITY = 6660 L/s																					
croissant Squadron Crescent	---	MH221	MH222											0.00	19.19	16.24	0.11	16.35	79.75	93.38	136.33	1,530.55			6,660.00	8,190.55	8,565.43	11.97	2400			0.11	1.834	374.88	4.38%
croissant Squadron Crescent	S222A-B	MH222	*BULK165S*								0.26			0.51	19.70	16.35	0.86	17.21	79.44	93.01	135.79	1,564.69			6,660.00	8,224.69	8,565.43	94.49	2400			0.11	1.834	340.74	3.98%
Phase 1A																																			
croissant Squadron Crescent	---	*BULK165S*	*MH165*											0.00	19.70	17.21	0.23	17.43	77.04	90.19	131.66	1,517.52			6,660.00	8,177.52	8,565.43	*24.90*	*2400*			*0.11*	1.834	387.92	4.53%
Temp Ditch	BLOCK 15	DI 4	MH165S		1.96									1.63	1.63	50.88	0.17	51.05	37.18	43.41	63.14	60.73				60.73	182.91	16.50	375			1.00	1.604	122.18	66.80%
Phase 1B																																			
rue Michael Stoqua Street	S210, LOT210	MH210	MH211								0.20		0.23	0.90	0.90	10.00	0.83	10.83	104.19	122.14	178.56	93.85				93.85	147.47	64.80	375			0.65	1.293	53.62	36.36%
Temp Ditch	BLOCK 22	DI 12	MH211N		0.46									0.38	0.38	19.39	0.33	19.72	71.62	83.82	122.31	27.44				27.44	43.87	17.38	250			0.50	0.866	16.43	37.45%
Temp Ditch	BLOCK 23	DI 13	MH166N		0.46									0.38	0.38	22.34	0.34	22.68	65.50	76.63	111.77	25.06				25.06	43.87	17.50	250			0.50	0.866	18.81	42.88%
rue Michael Stoqua Street	S211, LOT211	MH211	*BULK166N*								0.17		0.23	0.84	1.74	10.83	1.09	11.93	99.98	117.18	171.27	174.27				174.27	248.09	55.70	600			0.15	0.850	73.82	29.75%
Phase 1A																																			
rue Michael Stoqua Street	---	*BULK166N*	*MH166*											0.00	1.74	11.93	0.32	12.24	95.01	111.33	162.67	165.61				165.61	248.09	*16.10*	*600*			*0.15*	0.850	82.48	33.25%
Phase 1B																																			
rue Bareille-Snow Street	S208, LOT208A-B	MH208	MH209								0.19		0.81	2.17	2.17	10.00	0.76	10.76	104.19	122.14	178.56	226.22				226.22	317.25	64.85	525			0.50	1.420	91.03	28.69%
rue Bareille-Snow Street	S209, LOT209	MH209	*BULK167N*								0.20		0.20	0.83	3.01	10.76	1.01	11.77	100.34	117.60	171.89	301.53				301.53	339.63	55.70	675			0.15	0.919	38.10	11.22%
Temp Ditch	BLOCK 21	DI 11	MH167N		1.22									1.02	1.02	35.74	0.21	35.95	47.82	55.88	81.38	48.58				48.58	100.88	17.52	300			1.00	1.383	52.30	51.84%
Phase 1A																																			
rue Bareille-Snow Street	---	*BULK167N*	*MH167*											0.00	3.01	11.77	0.29	12.06	95.69	112.12	163.84	287.55				287.55	339.63	*16.10*	*675*			*0.15*	0.919	52.08	15.34%

Definitions:
Q = 2.78CiA, where:
Q = Peak Flow in Litres per Second (L/s)
A = Area in Hectares (Ha)
i = Rainfall intensity in millimeters per hour (mm/hr)
[i = 998.071 / (TC+6.053)^0.814] 5 YEAR
[i = 1174.184 / (TC+6.014)^0.816] 10 YEAR
[i = 1735.688 / (TC+6.014)^0.820] 100 YEAR

Notes:
1. Mannings coefficient (n) = 0.013

Designed: WY
Checked: JIM
Dwg. Reference: 38298-500

No.	Revision	Date
1.	City submission No. 1	7/8/2016
2.	City submission No. 2	11/4/2016
3.	City submission No. 3	1/25/2017

File Reference: 38298.5.7.1
Date: 7/8/2016
Sheet No: 1 of 2

REVIEWED BY
DEVELOPMENT REVIEW SERVICES BRANCH

Signed _____


Date _____ 2017

Plan Number _____

LEGEND :

S168 2.01|0.80 — AREA NUMBER / RUNOFF COEFFICIENT / AREA IN HECTARES

POTENTIAL DRAINAGE DIRECTION



No.	REVISIONS	By	Date
14			
13			
12			
11			
10			
9			
8			
7			
6	REVISED PER MOECC COMMENTS	J.I.M.	2017:06:07
5	ISSUED FOR TENDER	J.I.M.	2017:03:23
4	SUBMISSION FOR MOECC APPROVAL	J.I.M.	2017:02:16
3	SUBMISSION No.3 FOR CITY REVIEW	J.I.M.	2017:01:25
2	SUBMISSION No.2 FOR CITY REVIEW	J.I.M.	2016:11:04
1	SUBMISSION No.1 FOR CITY REVIEW	J.I.M.	2016:07:08

CANADA LANDS COMPANY
SOCIÉTÉ IMMOBILIÈRE DU CANADA
30 Metcalfe Street Suite 601
Ottawa, On K1P 5L4
613 998 7777

IBI GROUP
400 – 333 Preston Street
Ottawa ON K1S 5N4 Canada
tel 613 225 1311 fax 613 225 9868
ibigroup.com

Project Title

WATERIDGE VILLAGE AT ROCKCLIFFE

PHASE 1B

J. I. MOFFATT
17/06/07
PROVINCE OF ONTARIO

Drawing Title

STORM DRAINAGE AREA PLAN


Scale: 1 : 2000

Design	Date
J.I.M.	MAY 2016
Drawn: M.M.	Checked: J.I.M.
Project No.: 38298	Drawing No.: 500A

D07-16-15-0003

#17063

L:\38298-CP\Discipline\4.0 Drawings\Data\Xrefs\ IN-IBI\500A_STORM DRAINAGE AREA PLAN.dwg Layout Name= STORM DRAINAGE AREA PLAN Plot Style: AIA STANDARD - HALF CTB Plot Scale= 1:1.0 X Plotted At: 6/14/2017 8:19 AM Last Saved By: jmoffatt Last Saved At: Mar. 17,17


LEGEND
108 NODE IDENTIFICATION
2700mmØ PROPOSED STORM SEWER SIZE AND DIRECTION
1050Ø STM EXISTING SITE STORM SEWER SIZE AND DIRECTION
N
EASTERN STORM FACILITY
POTENTIAL WATERFALL
FUTURE MUSEUM
TEMPORARY SWALE OUTLET PIPE
TEMPORARY DRAINAGE SWALE
INTERCEPT EXISTING STORM INVERT ±87.00m
CAP SEWER AND CONSTRUCT TEMPORARY DRAINAGE PIPE TO SWM FACILITY
1050Ø STM
2700mmØ
1800mmØ
1650mmØ
1500mmØ
1350mmØ
1200mmØ
1050mmØ
900mmØ
825mmØ
750mmØ
675mmØ
600mmØ
525mmØ
450mmØ
375mmØ
MH100
MH101
MH102
MH103
MH104
MH105
MH106
MH107
MH108
MH109
MH110
MH111
MH112
MH113
MH114
MH115
MH116
MH117
MH118
MH119
MH120
MH121
MH122
MH123
MH124
MH125
MH126
MH127
MH128
MH129
MH130
MH131
MH132
MH133
MH134
MH135
MH136
MH137
MH138
MH139
MH140
MH141
MH142
MH143
MH144
MH145
MH146
MH147
MH148
MH149
MH150
MH151
MH152
MH153
MH154
MH155
MH156
MH157
MH158
MH159
MH160
MH161
MH162
MH163
MH164
MH165
MH166
MH167
MH168
MH169
MH170
MH171
MH172
MH173
MH174
MH175
MH176
MH177
MH178
MH179
MH180
MH181
MH182
MH183
MH184
MH185
MH186
MH187
MH188
MH189
MH190
MH191
MH192
MH193
MH194
MH195
MH196
MH197
MH198
MH199
MH200
MH201
MH202
MH203
MH204
MH205
MH206
MH207
MH208
MH209
MH210
MH211
MH212
MH213
MH214
MH215
MH216
MH217
MH218
MH219
MH220
MH221
MH222
MH223
MH224
MH225
MH226
MH227
MH228
MH229
MH230
MH231
MH232
MH233
MH234
MH235
MH236
MH237
MH238
MH239
MH240
MH241
MH242
MH243
MH244
MH245
MH246
MH247
MH248
MH249
MH250
MH251
MH252
MH253
MH254
MH255
MH256
MH257
MH258
MH259
MH260
MH261
MH262
MH263
MH264
MH265
MH266
MH267
MH268
MH269
MH270
MH271
MH272
MH273
MH274
MH275
MH276
MH277
MH278
MH279
MH280
MH281
MH282
MH283
MH284
MH285
MH286
MH287
MH288
MH289
MH290
MH291
MH292
MH293
MH294
MH295
MH296
MH297
MH298
MH299
MH300
MH301
MH302
MH303
MH304
MH305
MH306
MH307
MH308
MH309
MH310
MH311
MH312
MH313
MH314
MH315
MH316
MH317
MH318
MH319
MH320
MH321
MH322
MH323
MH324
MH325
MH326
MH327
MH328
MH329
MH330
MH331
MH332
MH333
MH334
MH335
MH336
MH337
MH338
MH339
MH340
MH341
MH342
MH343
MH344
MH345
MH346
MH347
MH348
MH349
MH350
MH351
MH352
MH353
MH354
MH355
MH356
MH357
MH358
MH359
MH360
MH361
MH362
MH363
MH364
MH365
MH366
MH367
MH368
MH369
MH370
MH371
MH372
MH373
MH374
MH375
MH376
MH377
MH378
MH379
MH380
MH381
MH382
MH383
MH384
MH385
MH386
MH387
MH388
MH389
MH390
MH391
MH392
MH393
MH394
MH395
MH396
MH397
MH398
MH399
MH400
MH401
MH402
MH403
MH404
MH405
MH406
MH407
MH408
MH409
MH410
MH411
MH412
MH413
MH414
MH415
MH416
MH417
MH418
MH419
MH420
MH421
MH422
MH423
MH424
MH425
MH426
MH427
MH428
MH429
MH430
MH431
MH432
MH433
MH434
MH435
MH436
MH437
MH438
MH439
MH440
MH441
MH442
MH443
MH444
MH445
MH446
MH447
MH448
MH449
MH450
MH451
MH452
MH453
MH454
MH455
MH456
MH457
MH458
MH459
MH460
MH461
MH462
MH463
MH464
MH465
MH466
MH467
MH468
MH469
MH470
MH471
MH472
MH473
MH474
MH475
MH476
MH477
MH478
MH479
MH480
MH481
MH482
MH483
MH484
MH485
MH486
MH487
MH488
MH489
MH490
MH491
MH492
MH493
MH494
MH495
MH496
MH497
MH498
MH499
MH500
MH501
MH502
MH503
MH504
MH505
MH506
MH507
MH508
MH509
MH510
MH511
MH512
MH513
MH514
MH515
MH516
MH517
MH518
MH519
MH520
MH521
MH522
MH523
MH524
MH525
MH526
MH527
MH528
MH529
MH530
MH531
MH532
MH533
MH534
MH535
MH536
MH537
MH538
MH539
MH540
MH541
MH542
MH543
MH544
MH545
MH546
MH547
MH548
MH549
MH550
MH551
MH552
MH553
MH554
MH555
MH556
MH557
MH558
MH559
MH560
MH561
MH562
MH563
MH564
MH565
MH566
MH567
MH568
MH569
MH570
MH571
MH572
MH573
MH574
MH575
MH576
MH577
MH578
MH579
MH580
MH581
MH582
MH583
MH584
MH585
MH586
MH587
MH588
MH589
MH590
MH591
MH592
MH593
MH594
MH595
MH596
MH597
MH598
MH599
MH600
MH601
MH602
MH603
MH604
MH605
MH606
MH607
MH608
MH609
MH610
MH611
MH612
MH613
MH614
MH615
MH616
MH617
MH618
MH619
MH620
MH621
MH622
MH623
MH624
MH625
MH626
MH627
MH628
MH629
MH630
MH631
MH632
MH633
MH634
MH635
MH636
MH637
MH638
MH639
MH640
MH641
MH642
MH643
MH644
MH645
MH646
MH647
MH648
MH649
MH650
MH651
MH652
MH653
MH654
MH655
MH656
MH657
MH658
MH659
MH660
MH661
MH662
MH663
MH664
MH665
MH666
MH667
MH668
MH669
MH670
MH671
MH672
MH673
MH674
MH675
MH676
MH677
MH678
MH679
MH680
MH681
MH682
MH683
MH684
MH685
MH686
MH687
MH688
MH689
MH690
MH691
MH692
MH693
MH694
MH695
MH696
MH697
MH698
MH699
MH700
MH701
MH702
MH703
MH704
MH705
MH706
MH707
MH708
MH709
MH710
MH711
MH712
MH713
MH714
MH715
MH716
MH717
MH718
MH719
MH720
MH721
MH722
MH723
MH724
MH725
MH726
MH727
MH728
MH729
MH730
MH731
MH732
MH733
MH734
MH735
MH736
MH737
MH738
MH739
MH740
MH741
MH742
MH743
MH744
MH745
MH746
MH747
MH748
MH749
MH750
MH751
MH752
MH753
MH754
MH755
MH756
MH757
MH758
MH759
MH760
MH761
MH762
MH763
MH764
MH765
MH766
MH767
MH768
MH769
MH770
MH771
MH772
MH773
MH774
MH775
MH776
MH777
MH778
MH779
MH780
MH781
MH782
MH783
MH784
MH785
MH786
MH787
MH788
MH789
MH790
MH791
MH792
MH793
MH794
MH795
MH796
MH797
MH798
MH799
MH800
MH801
MH802
MH803
MH804
MH805
MH806
MH807
MH808
MH809
MH810
MH811
MH812
MH813
MH814
MH815
MH816
MH817
MH818
MH819
MH820
MH821
MH822
MH823
MH824
MH825
MH826
MH827
MH828
MH829
MH830
MH831
MH832
MH833
MH834
MH835
MH836
MH837
MH838
MH839
MH840
MH841
MH842
MH843
MH844
MH845
MH846
MH847
MH848
MH849
MH850
MH851
MH852
MH853
MH854
MH855
MH856
MH857
MH858
MH859
MH860
MH861
MH862
MH863
MH864
MH865
MH866
MH867
MH868
MH869
MH870
MH871
MH872
MH873
MH874
MH875
MH876
MH877
MH878
MH879
MH880
MH881
MH882
MH883
MH884
MH885
MH886
MH887
MH888
MH889
MH890
MH891
MH892
MH893
MH894
MH895
MH896
MH897
MH898
MH899
MH900
MH901
MH902
MH903
MH904
MH905
MH906
MH907
MH908
MH909
MH910
MH911
MH912
MH913
MH914
MH915
MH916
MH917
MH918
MH919
MH920
MH921
MH922
MH923
MH924
MH925
MH926
MH927
MH928
MH929
MH930
MH931
MH932
MH933
MH934
MH935
MH936
MH937
MH938
MH939
MH940
MH941
MH942
MH943
MH944
MH945
MH946
MH947
MH948
MH949
MH950
MH951
MH952
MH953
MH954
MH955
MH956
MH957
MH958
MH959
MH960
MH961
MH962
MH963
MH964
MH965
MH966
MH967
MH968
MH969
MH970
MH971
MH972
MH973
MH974
MH975
MH976
MH977
MH978
MH979
MH980
MH981
MH982
MH983
MH984
MH985
MH986
MH987
MH988
MH989
MH990
MH991
MH992
MH993
MH994
MH995
MH996
MH997
MH998
MH999
MH1000
MH1001
MH1002
MH1003
MH1004
MH1005
MH1006
MH1007
MH1008
MH1009
MH1010
MH1011
MH1012
MH1013
MH1014
MH1015
MH1016
MH1017
MH1018
MH1019
MH1020
MH1021
MH1022
MH1023
MH1024
MH1025
MH1026
MH1027
MH1028
MH1029
MH1030
MH1031
MH1032
MH1033
MH1034
MH1035
MH1036
MH1037
MH1038
MH1039
MH1040
MH1041
MH1042
MH1043
MH1044
MH1045
MH1046
MH1047
MH1048
MH1049
MH1050
MH1051
MH1052
MH1053
MH1054
MH1055
MH1056
MH1057
MH1058
MH1059
MH1060
MH1061
MH1062
MH1063
MH1064
MH1065
MH1066
MH1067
MH1068
MH1069
MH1070
MH1071
MH1072
MH1073
MH1074
MH1075
MH1076
MH1077
MH1078
MH1079
MH1080
MH1081
MH1082
MH1083
MH1084
MH1085
MH1086
MH1087
MH1088
MH1089
MH1090
MH1091
MH1092
MH1093
MH1094
MH1095
MH1096
MH1097
MH1098
MH1099
MH1100
MH1101
MH1102
MH1103
MH1104
MH1105
MH1106
MH1107
MH1108
MH1109
MH1110
MH1111
MH1112
MH1113
MH1114
MH1115
MH1116
MH1117
MH1118
MH1119
MH1120
MH1121
MH1122
MH1123
MH1124
MH1125
MH1126
MH1127
MH1128
MH1129
MH1130
MH1131
MH1132
MH1133
MH1134
MH1135
MH1136
MH1137
MH1138
MH1139
MH1140
MH1141
MH1142
MH1143
MH1144
MH1145
MH1146
MH1147
MH1148
MH1149
MH1150
MH1151
MH1152
MH1153
MH1154
MH1155
MH1156
MH1157
MH1158
MH1159
MH1160
MH1161
MH1162
MH1163
MH1164
MH1165
MH1166
MH1167
MH1168
MH1169
MH1170
MH1171
MH1172
MH1173
MH1174
MH1175
MH1176
MH1177
MH1178
MH1179
MH1180
MH1181
MH1182
MH1183
MH1184
MH1185
MH1186
MH1187
MH1188
MH1189
MH1190
MH1191
MH1192
MH1193
MH1194
MH1195
MH1196
MH1197
MH1198
MH1199
MH1200
MH1201
MH1202
MH1203
MH1204
MH1205
MH1206
MH1207
MH1208
MH1209
MH1210
MH1211
MH1212
MH1213
MH1214
MH1215
MH1216
MH1217
MH1218
MH1219
MH1220
MH1221
MH1222
MH1223
MH1224
MH1225
MH1226
MH1227
MH1228
MH1229
MH1230
MH1231
MH1232
MH1233
MH1234
MH1235
MH1236
MH1237
MH1238
MH1239
MH1240
MH1241
MH1242
MH1243
MH1244
MH1245
MH1246
MH1247
MH1248
MH1249
MH1250
MH1251
MH1252
MH1253
MH1254
MH1255
MH1256
MH1257
MH1258
MH1259
MH1260
MH1261
MH1262
MH1263
MH1264
MH1265
MH1266
MH1267
MH1268
MH1269
MH1270
MH1271
MH1272
MH1273
MH1274
MH1275
MH1276
MH1277
MH1278
MH1279
MH1280
MH1281
MH1282
MH1283
MH1284
MH1285
MH1286
MH1287
MH1288
MH1289
MH1290
MH1291
MH1292
MH1293
MH1294
MH1295
MH1296
MH1297
MH1298
MH1299
MH1300
MH1301
MH1302
MH1303
MH1304
MH1305
MH1306
MH1307
MH1308
MH1309
MH1310
MH1311
MH1312
MH1313
MH1314
MH1315
MH1316
MH1317
MH1318
MH1319
MH1320
MH1321
MH1322
MH1323
MH1324
MH1325
MH1326
MH1327
MH1328
MH1329
MH1330
MH1331
MH1332
MH1333
MH1334
MH1335
MH1336
MH1337
MH1338
MH1339
MH1340
MH1341
MH1342
MH1343
MH1344
MH1345
MH1346
MH1347
MH1348
MH1349
MH1350
MH1351
MH1352
MH1353
MH1354
MH1355
MH1356
MH1357
MH1358
MH1359
MH1360
MH1361
MH1362
MH1363
MH1364
MH1365
MH1366
MH1367
MH1368
MH1369
MH1370
MH1371
MH1372
MH1373
MH1374
MH1375
MH1376
MH1377
MH1378
MH1379
MH1380
MH1381
MH1382
MH1383
MH1384
MH1385
MH1386
MH1387
MH1388
MH1389
MH1390
MH1391
MH1392
MH1393
MH1394
MH1395
MH1396
MH1397
MH1398
MH1399
MH1400
MH1401
MH1402
MH1403
MH1404
MH1405
MH1406
MH1407
MH1408
MH1409
MH1410
MH1411
MH1412
MH1413
MH1414
MH1415
MH1416
MH1417
MH1418
MH1419
MH1420
MH1421
MH1422
MH1423
MH1424
MH1425
MH1426
MH1427
MH1428
MH1429
MH1430
MH1431
MH1432
MH1433
MH1434
MH1435
MH1436
MH1437
MH1438
MH1439
MH1440
MH1441
MH1442
MH1443
MH1444
MH1445
MH1446
MH1447
MH1448
MH1449
MH1450
MH1451
MH1452
MH1453
MH1454
MH1455
MH1456
MH1457
MH1458
MH1459
MH1460
MH1461
MH1462
MH1463
MH1464
MH1465
MH1466
MH1467
MH1468
MH1469
MH1470
MH1471
MH1472
MH1473
MH1474
MH1475
MH1476
MH1477
MH1478
MH1479
MH1480
MH1481
MH1482
MH1483
MH1484
MH1485
MH1486
MH1487
MH1488
MH1489
MH1490
MH1491
MH1492
MH1493
MH1494
MH1495
MH1496
MH1497
MH1498
MH1499
MH1500
MH1501
MH1502
MH1503
MH1504
MH1505
MH1506
MH1507
MH1508
MH1509
MH1510
MH1511
MH1512
MH1513
MH1514
MH1515
MH1516
MH1517
MH1518
MH1519
MH1520
MH1521
MH1522
MH1523
MH1524
MH1525
MH1526
MH1527
MH1528
MH1529
MH1530
MH1531
MH1532
MH1533
MH1534
MH1535
MH1536
MH1537
MH1538
MH1539
MH1540
MH1541
MH1542
MH1543
MH1544
MH1545
MH1546
MH1547
MH1548
MH1549
MH1550
MH1551
MH1552
MH1553
MH1554
MH1555
MH1556
MH1557
MH1558
MH1559
MH1560
MH1561
MH1562
MH1563
MH1564
MH1565
MH1566
MH1567
MH1568
MH1569
MH1570
MH1571
MH1572
MH1573
MH1574
MH1575
MH1576
MH1577
MH1578
MH1579
MH1580
MH1581
MH1582
MH1583
MH1584
MH1585
MH1586
MH1587
MH1588
MH1589
MH1590
MH1591
MH1592
MH1593
MH1594
MH1595
MH1596
MH1597
MH1598
MH1599
MH1600
MH1601
MH1602
MH1603
MH1604
MH1605
MH1606
MH1607
MH1608
MH1609
MH1610
MH1611
MH1612
MH1613
MH1614
MH1615
MH1616
MH1617
MH1618
MH1619
MH1620
MH1621
MH1622
MH1623
MH1624
MH1625
MH1626
MH1627
MH1628
MH1629
MH1630
MH1631
MH1632
MH1633
MH1634
MH1635
MH1636
MH1637
MH1638
MH1639
MH1640
MH1641
MH1642
MH1643
MH1644
MH1645
MH1646
MH1647
MH1648
MH1649
MH1650
MH1651
MH1652
MH1653
MH1654
MH1655
MH1656
MH1657
MH1658
MH1659
MH1660
MH1661
MH1662
MH1663
MH1664
MH1665
MH1666
MH1667
MH1668
MH1669
MH1670
MH1671
MH1672
MH1673
MH1674
MH1675
MH1676
MH1677
MH1678
MH1679
MH1680
MH1681
MH1682
MH1683
MH1684
MH1685
MH1686
MH1687
MH1688
MH1689
MH1690
MH1691
MH1692
MH1693
MH1694
MH1695
MH1696
MH1697
MH1698
MH1699
MH1700
MH1701
MH1702
MH1703
MH1704
MH1705
MH1706
MH1707
MH1708
MH1709
MH1710
MH1711
MH1712
MH1713
MH1714
MH1715
MH1716
MH1717
MH1718
MH1719
MH1720
MH1721
MH1722
MH1723
MH1724
MH1725
MH1726
MH1727
MH1728
MH1729
MH1730
MH1731
MH1732
MH1733
MH1734
MH1735
MH1736
MH1737
MH1738
MH1739
MH1740
MH1741
MH1742
MH1743
MH1744
MH1745
MH1746
MH1747
MH1748
MH1749
MH1750
MH1751
MH1752
MH1753
MH1754
MH1755
MH1756
MH1757
MH1758
MH1759
MH1760
MH1761
MH1762
MH1763
MH1764
MH1765
MH1766
MH1767
MH1768
MH1769
MH1770
MH1771
MH1772
MH1773
MH1774
MH1775
MH1776
MH1777
MH1778
MH1779
MH1780
MH1781
MH1782
MH1783
MH1784
MH1785
MH1786
MH1787
MH1788
MH1789
MH1790
MH1791
MH1792
MH1793
MH1794
MH1795
MH1796
MH1797
MH1798
MH1799
MH1800
MH1801
MH1802
MH1803
MH1804
MH1805
MH1806
MH1807
MH1808
MH1809
MH1810
MH1811
MH1812
MH1813
MH1814
MH1815
MH1816
MH1817
MH1818
MH1819
MH1820
MH1821
MH1822
MH1823
MH1824
MH1825
MH1826
MH1827
MH1828
MH1829
MH1830
MH1831
MH1832
MH1833
MH1834
MH1835
MH1836
MH1837
MH1838
MH1839
MH1840
MH1841
MH1842
MH1843
MH1844
MH1845
MH1846
MH1847
MH1848
MH1849
MH1850
MH1851
MH1852
MH1853
MH1854
MH1855
MH1856
MH1857
MH1858
MH1859
MH1860
MH1861
MH1862
MH1863
MH1864
MH1865
MH1866
MH1867
MH1868
MH1869
MH1870
MH1871
MH1872
MH1873
MH1874
MH1875
MH1876
MH1877
MH1878
MH1879
MH1880
MH1881
MH1882
MH1883
MH1884
MH1885
MH1886
MH1887
MH1888
MH1889
MH1890
MH1891
MH1892
MH1893
MH1894
MH1895
MH1896
MH1897
MH1898
MH1899
MH1900
MH1901
MH1902
MH1903
MH1904
MH1905
MH1906
MH1907
MH1908
MH1909
MH1910
MH1911
MH1912
MH1913
MH1914
MH1915
MH1916
MH1917
MH1918
MH1919
MH1920
MH1921
MH1922
MH1923
MH1924
MH1925
MH1926
MH1927
MH1928
MH1929
MH1930
MH1931
MH1932
MH1933
MH1934
MH1935
MH1936
MH1937
MH1938
MH1939
MH1940
MH1941
MH1942
MH1943
MH1944
MH1945
MH1946
MH1947
MH1948
MH1949
MH1950
MH1951
MH1952
MH1953
MH1954
MH1955
MH1956
MH1957
MH1958
MH1959
MH1960
MH1961
MH1962
MH1963
MH1964
MH1965
MH1966
MH1967
MH1968
MH1969
MH1970
MH1971
MH1972
MH1973
MH1974
MH1975
MH1976
MH1977
MH1978
MH1979
MH1980
MH1981
MH1982
MH1983
MH1984
MH1985
MH1986
MH1987
MH1988
MH1989
MH1990
MH1991
MH1992
MH1993
MH1994
MH1995
MH1996
MH1997
MH1998
MH1999
MH2000
MH2001
MH2002
MH2003
MH2004
MH2005
MH2006
MH2007
MH2008
MH2009
MH2010
MH2011
MH2012
MH2013
MH2014
MH2015
MH2016
MH2017
MH2018
MH2019
MH2020
MH2021
MH2022
MH2023
MH2024
MH2025
MH2026
MH2027
MH2028
MH2029
MH2030
MH2031
MH2032
MH2033
MH2034
MH2035
MH2036
MH2037
MH2038
MH2039
MH2040
MH2041
MH2042
MH2043
MH2044
MH2045
MH2046
MH2047
MH2048
MH2049
MH2050
MH2051
MH2052
MH2053
MH2054
MH2055
MH2056
MH2057
MH2058
MH2059
MH2060
MH2061
MH2062
MH2063
MH2064
MH2065
MH2066
MH2067
MH2068
MH2069
MH2070
MH2071
MH2072
MH2073
MH2074
MH2075
MH2076
MH2077
MH2078
MH2079
MH2080
MH2081
MH2082
MH2083
MH2084
MH2085
MH2086
MH2087
MH2088
MH2089
MH2090
MH2091
MH2092
MH2093
MH2094
MH2095
MH2096
MH2097
MH2098
MH2099
MH2100
MH2101
MH2102
MH2103
MH2104
MH2105
MH2106
MH2107
MH2108
MH2109
MH2110
MH2111
MH2112
MH2113
MH2114
MH2115
MH2116
MH2117
MH2118
MH2119
MH2120
MH2121
MH2122
MH2123
MH2124
MH2125
MH2126
MH2127
MH2128
MH2129
MH2130
MH2131
MH2132
MH2133
MH2134
MH2135
MH2136
MH2137
MH2138
MH2139
MH2140
MH2141
MH2142
MH2143
MH2144
MH2145
MH2146
MH2147
MH2148
MH2149
MH2150
MH2151
MH2152
MH2153
MH2154
MH2155
MH2156
MH2157
MH2158
MH2159
MH2160
MH2161
MH2162
MH2163
MH2164
MH2165
MH2166
MH2167
MH2168
MH2169
MH2170
MH2171
MH2172
MH2173
MH2174
MH2175
MH2176
MH2177
MH2178
MH2179
MH2180
MH2181
MH2182
MH2183
MH2184
MH2185
MH2186
MH2187
MH2188
MH2189
MH2190
MH2191
MH2192
MH2193
MH2194
MH2195
MH2196
MH2197
MH2198
MH2199
MH2200
MH2201
MH2202
MH2203
MH2204
MH2205
MH2206
MH2207
MH2208
MH2209
MH2210
MH2211
MH2212
MH2213
MH2214
MH2215
MH2216
MH2217
MH2218
MH2219
MH2220
MH2221
MH2222
MH2223
MH2224
MH2225
MH2226
MH2227
MH2228
MH2229
MH2230
MH2231
MH2232
MH2233
MH2234
MH2235
MH2236
MH2237
MH2238
MH2239
MH2240
MH2241
MH2242
MH2243
MH2244
MH2245
MH2246
MH2247
MH2248
MH2249
MH2250
MH2251
MH2252
MH2253
MH2254
MH2255
MH2256
MH2257
MH2258
MH2259
MH2260
MH2261
MH2262
MH2263
MH2264
MH2265
MH2266
MH2267
MH2268
MH2269
MH2270
MH2271
MH2272
MH2273
MH2274
MH2275
MH2276
MH2277
MH2278
MH2279
MH2280
MH2281
MH2282
MH2283
MH2284
MH2285
MH2286
MH2287
MH2288
MH2289
MH2290
MH2291
MH2292
MH2293
MH2294
MH2295
MH2296
MH2297
MH2298
MH2299
MH2300
MH2301
MH2302
MH2303
MH2304
MH2305
MH2306
MH2307
MH2308
MH2309
MH2310
MH2311
MH2312
MH2313
MH2314
MH2315
MH2316
MH2317
MH2318
MH2319
MH2320
MH2321
MH2322
MH2323
MH2324
MH2325
MH2326
MH2327
MH2328
MH2329
MH2330
MH2331
MH2332
MH2333
MH2334
MH2335
MH2336
MH2337
MH2338
MH2339
MH2340
MH2341
MH2342
MH2343
MH2344
MH2345
MH2346
MH2347
MH2348
MH2349
MH2350
MH2351
MH2352
MH2353
MH2354
MH2355
MH2356
MH2357
MH2358
MH2359
MH2360
MH2361
MH2362
MH2363
MH2364
MH2365
MH2366
MH2367
MH2368
MH2369
MH2370
MH2371
MH2372
MH2373
MH2374
MH2375
MH2376
MH2377
MH2378
MH2379
MH2380
MH2381
MH2382
MH2383
MH2384
MH2385
MH2386
MH2387
MH2388
MH2389
MH2390
MH2391
MH2392
MH2393
MH2394
MH2395
MH2396
MH2397
MH2398
MH2399
MH2400
MH2401
MH2402
MH2403
MH2404
MH2405
MH2406
MH2407
MH2408
MH2409
MH2410
MH2411
MH2412
MH2413
MH2414
MH2415
MH2416
MH2417
MH2418
MH2419
MH2420
MH2421
MH2422
MH2423
MH2424
MH2425
MH2426
MH2427
MH2428
MH2429
MH2430
MH2431
MH2432
MH2433
MH2434
MH2435
MH2436
MH2437
MH2438
MH2439
MH2440
MH2441
MH2442
MH2443
MH2444
MH2445
MH2446
MH2447
MH2448
MH2449
MH2450
MH2451
MH2452
MH2453
MH2454
MH2455
MH2456
MH2457
MH2458
MH2459
MH2460
MH2461
MH2462
MH2463
MH2464
MH2465
MH2466
MH2467
MH2468
MH2469
MH2470
MH2471
MH2472
MH2473
MH2474
MH2475
MH2476
MH2477
MH2478
MH2479
MH2480
MH2481
MH2482
MH2483
MH2484
MH2485
MH2486
MH2487
MH2488
MH2489
MH2490
MH2491
MH2492
MH2493
MH2494
MH2495
MH2496
MH2497
MH2498
MH2499
MH2500
MH2501
MH2502
MH2503
MH2504
MH2505
MH2506
MH2507
MH2508
MH2509
MH2510
MH2511
MH2512
MH2513
MH2514
MH2515
MH2516
MH2517
MH2518
MH2519
MH2520
MH2521
MH2522
MH2523
MH2524
MH2525
MH2526
MH2527
MH2528
MH2529
MH2530
MH2531
MH2532
MH2533
MH2534
MH2535
MH2536
MH2537
MH2538
MH2539
MH2540
MH2541
MH2542
MH2543
MH2544
MH2545
MH2546
MH2547
MH2548
MH2549
MH2550
MH2551
MH2552
MH2553
MH2554
MH2555
MH2556
MH2557
MH2558
MH2559
MH2560
MH2561
MH2562
MH2563
MH2564
MH2565
MH2566
MH2567
MH2568
MH2569
MH2570
MH2571
MH2572
MH2573
MH2574
MH2575
MH2576
MH2577
MH2578
MH2579
MH2580
MH2581
MH2582
MH2583
MH2584
MH2585
MH2586
MH2587
MH2588
MH2589
MH2590
MH2591
MH2592
MH2593
MH2594
MH2595
MH2596
MH2597
MH2598
MH2599
MH2600
MH2601
MH2602
MH2603
MH2604
MH2605
MH2606
MH2607
MH2608
MH2609
MH2610
MH2611
MH2612
MH2613
MH2614
MH2615
MH2616
MH2617
MH2618
MH2619
MH2620
MH2621
MH2622
MH2623
MH2624
MH2625
MH2626
MH2627
MH2628
MH2629
MH2630
MH2631
MH2632
MH2633
MH2634
MH2635
MH2636
MH2637
MH2638
MH2639
MH2640
MH2641
MH2642
MH2643
MH2644
MH2645
MH2646
MH2647
MH2648
MH2649
MH2650
MH2651
MH2652
MH2653
MH2654
MH2655
MH2656
MH2657
MH2658
MH2659
MH2660
MH2661
MH2662
MH2663
MH2664
MH2665
MH2666
MH2667
MH2668
MH2669
MH2670
MH2671
MH2672
MH2673
MH2674
MH2675
MH2676
MH2677
MH2678
MH2679
MH2680
MH2681
MH2682
MH2683
MH2684
MH2685
MH2686
MH2687
MH2688
MH2689
MH2690
MH2691
MH2692
MH2693
MH2694
MH2695
MH2696
MH2697
MH2698
MH2699
MH2700
MH2701
MH2702
MH2703
MH2704
MH2705
MH2706
MH2707
MH2708
MH2709
MH2710
MH2711
MH2712
MH2713
MH2714
MH2715
MH2716
MH2717
MH2718
MH2719
MH2720
MH2721
MH2722
MH2723
MH2724
MH2725
MH2726
MH2727
MH2728
MH2729
MH2730
MH2731
MH2732
MH2733
MH2734
MH2735
MH2736
MH2737
MH2738
MH2739
MH2740
MH2741
MH2742
MH2743
MH2744
MH2745
MH2746
MH2747
MH2748
MH2749
MH2750
MH2751
MH2752
MH2753
MH2754
MH2755
MH2756
MH2757
MH2758
MH2759
MH2760
MH2761
MH2762
MH2763
MH2764
MH2765
MH2766
MH2767
MH2768
MH2769
MH2770
MH2771
MH2772
MH2773
MH2774
MH2775
MH2776
MH2777
MH2778
MH2779
MH2780
MH2781
MH2782
MH2783
MH2784
MH2785
MH2786
MH2787
MH2788
MH2789
MH2790
MH2791
MH2792
MH2793
MH2794
MH2795
MH2796
MH2797
MH2798
MH2799
MH2800
MH2801
MH2802
MH2803
MH2804
MH2805
MH2806
MH2807
MH2808
MH2809
MH2810
MH2811
MH2812
MH2813
MH2814
MH2815
MH2816
MH2817
MH2818
MH2819
MH2820
MH2821
MH2822
MH2823
MH2824
MH2825
MH2826
MH2827
MH2828
MH2829
MH2830
MH2831
MH2832
MH2833
MH2834
MH2835
MH2836
MH2837
MH2838
MH2839
MH2840
MH2841
MH2842
MH2843
MH2844
MH2845
MH2846
MH2847
MH2848
MH2849
MH2850
MH2851
MH2852
MH2853
MH2854
MH2855
MH2856
MH2857
MH2858
MH2859
MH2860
MH2861
MH2862
MH2863
MH2864
MH2865
MH2866
MH2867
MH2868
MH2869
MH2870
MH2871
MH2872
MH2873
MH2874
MH2875
MH2876
MH2877
MH2878
MH2879
MH2880
MH2881
MH2882
MH2883
MH2884
MH2885
MH2886
MH2887
MH2888
MH2889
MH2890
MH2891
MH2892
MH2893
MH2894
MH2895
MH2896
MH2897
MH2898
MH2899
MH2900
MH2901
MH2902
MH2903
MH2904
MH2905
MH2906
MH2907
MH2908
MH2909
MH2910
MH2911
MH2912
MH2913
MH2914
MH2915
MH2916
MH2917
MH2918
MH2919
MH2920
MH2921
MH2922
MH2923
MH2924
MH2925
MH2926
MH2927
MH2928
MH2929
MH2930
MH2931
MH2932
MH2933
MH2934
MH2935
MH2936
MH2937
MH2938
MH2939
MH2940
MH2941
MH2942
MH2943
MH2944
MH2945
MH2946
MH2947
MH2948
MH2949
MH2950
MH2951
MH2952
MH2953
MH2954
MH2955
MH2956
MH2957
MH2958
MH2959
MH2960
MH2961
MH2962
MH2963
MH2964
MH2965
MH2966
MH2967
MH2968
MH2969
MH2970
MH2971
MH2972
MH2973
MH2974
MH2975
MH2976
MH2977
MH2978
MH2979
MH2980
MH2981
MH2982
MH2983
MH2984
MH2985
MH2986
MH2987
MH2988
MH2989
MH2990
MH2991
MH2992
MH2993
MH2994
MH2995
MH2996
MH2997
MH2998
MH2999
MH3000
MH3001
MH3002
MH3003
MH3004
MH3005
MH3006
MH3007
MH3008
MH3009
MH3010
MH3011
MH3012
MH3013
MH3014
MH3015
MH3016
MH3017
MH3018
MH3019
MH3020
MH3021
MH3022
MH3023
MH3024
MH3025
MH3026
MH3027
MH3028
MH3029
MH3030
MH3031
MH3032
MH3033
MH3034
MH3035
MH3036
MH3037
MH3038
MH3039
MH3040
MH3041
MH3042
MH3043
MH3044
MH3045
MH3046
MH3047
MH3048
MH3049
MH3050
MH3051
MH3052
MH3053
MH3054
MH3055
MH3056
MH3057
MH3058
MH3059
MH3060
MH3061
MH3062
MH3063
MH3064
MH3065
MH3066
MH3067
MH3068
MH3069
MH3070
MH3071
MH3072
MH3073
MH3074
MH3075
MH3076
MH3077
MH3078
MH3079
MH3080
MH3081
MH3082
MH3083
MH3084
MH3085
MH3086
MH3087
MH3088
MH3089
MH3090
MH3091
MH3092
MH3093
MH3094
MH3095
MH3096
MH3097
MH3098
MH3099
MH3100
MH3101
MH3102
MH3103
MH3104
MH3105
MH3106
MH3107
MH3108
MH3109
MH3110
MH3111
MH3112
MH3113
MH3114
MH3115
MH3116
MH3117
MH3118
MH3119
MH3120
MH3121
MH3122
MH3123
MH3124
MH3125
MH3126
MH3127
MH3128
MH3129
MH3130
MH3131
MH3132
MH3133
MH3134
MH3135
MH3136
MH3137
MH3138
MH3139
MH3140
MH3141
MH3142
MH3143
MH3144
MH3145
MH3146
MH3147
MH3148
MH3149
MH3150
MH3151
MH3152
MH3153
MH3154
MH3155
MH3156
MH3157
MH3158
MH3159
MH3160
MH3161
MH3162
MH3163
MH3164
MH3165
MH3166
MH3167
MH3168
MH3169
MH3170
MH3171
MH3172
MH3173
MH3174
MH3175
MH3176
MH3177
MH3178
MH3179
MH3180
MH3181
MH3182
MH3183
MH3184
MH3185
MH3186
MH3187
MH3188
MH3189
MH3190
MH3191
MH3192
MH3193
MH3194
MH3195
MH3196
MH3197
MH3198
MH3199
MH3200
MH3201
MH3202
MH3203
MH3204
MH3205
MH3206
MH3207
MH3208
MH3209
MH3210
MH3211
MH3212
MH3213
MH3214
MH3215
MH3216
MH3217
MH3218
MH3219
MH3220
MH3221
MH3222
MH3223
MH3224
MH3225
MH3226
MH3227
MH3228
MH3229
MH3230
MH3231
MH3232
MH3233
MH3234
MH3235
MH3236
MH3237
MH3238
MH3239
MH3240
MH3241
MH3242
MH3243
MH3244
MH3245
MH3246
MH3247
MH3248
MH3249
MH3250
MH3251
MH3252
MH3253
MH3254
MH3255
MH3256
MH3257
MH3258
MH3259
MH3260
MH3261
MH3262
MH3263
MH3264
MH3265
MH3266
MH3267
MH3268
MH3269
MH3270
MH3271
MH3272
MH3273
MH3274
MH3275
MH3276
MH3277
MH3278
MH3279
MH3280
MH3281
MH3282
MH3283
MH3284
MH3285
MH3286
MH3287
MH3288
MH3289
MH3290
MH3291
MH3292
MH3293
MH3294
MH3295
MH3296
MH3297
MH3298
MH3299
MH3300
MH3301
MH3302
MH3303
MH3304
MH3305
MH3306
MH3307
MH3308
MH3309
MH3310
MH3311
MH3312
MH3313
MH3314
MH3315
MH3316
MH3317
MH3318
MH3319
MH3320
MH3321
MH3322
MH3323
MH3324
MH3325
MH3326
MH3327
MH3328
MH3329
MH3330
MH3331
MH3332
MH3333
MH3334
MH3335
MH3336
MH3337
MH3338
MH3339
MH3340
MH3341
MH3342
MH3343
MH3344
MH3345
MH3346
MH3347
MH3348
MH3349
MH3350
MH3351
MH3352
MH3353
MH3354
MH3355
MH3356
MH3357
MH3358
MH3359
MH3360
MH3361
MH3362
MH3363
MH3364
MH3365
MH3366
MH3367
MH3368
MH3369
MH3370
MH3371
MH3372
MH3373
MH3374
MH3375
MH3376
MH3377
MH3378
MH3379
MH3380
MH3381
MH3382
MH3383
MH3384
MH3385
MH3386
MH3387
MH3388
MH3389
MH3390
MH3391
MH3392
MH3393
MH3394
MH3395
MH3396
MH3397

XP-SWMM NODE ID	MH NO.	GROUND ELEVATION (M)	USF (M)	100 YEAR 3 HOUR CHICAGO†		100 YEAR 24 HOUR SCS (103.2MM)‡		JULY 1, 1979¥		100 YEAR 3 HOUR CHICAGO INCREASED BY 20%£	
				HGL (M)	FREE BOARD (M)*	HGL (M)	FREE BOARD (M)*	HGL (M)	FREE BOARD (M)*	HGL (M)	FREE BOARD (M)*
S176	176	88.03	85.63	83.73	1.90	83.62	2.01	83.69	1.94	83.82	1.81
S178	178	89.00	86.60	83.37	3.23	83.28	3.32	83.35	3.25	83.46	3.14
S180	180	N/A	N/A	81.85	N/A	81.60	N/A	81.81	N/A	82.23	N/A
S190	190	N/A	N/A	81.54	N/A	81.33	N/A	81.51	N/A	81.91	N/A
S191	191	N/A	N/A	81.33	N/A	81.14	N/A	81.31	N/A	81.66	N/A
S192	192	N/A	N/A	81.11	N/A	80.95	N/A	81.09	N/A	81.39	N/A
S193	193	N/A	N/A	80.96	N/A	80.80	N/A	80.95	N/A	81.22	N/A

Notes:

* The free board is the USF minus the HGL (USF – HGL).
† HGL results for the 100 year 3 hour Chicago storm event were taken from the results of the XPSWMM model entitled "38298-ph1B-100ch.xp/out" and presented on the CD in **Appendix E**.
‡ HGL results for the 100 year 24 hour SCS Type II storm event were taken from the results of the XPSWMM model entitled "38298- ph1B-100SCS.xp/out" and presented on the CD in **Appendix E**.
¥ HGL results for the July 1, 1979 historical storm were taken from the results of the XPSWMM model entitled "38298- ph1B-JUL79.xp/out" and presented on the CD in **Appendix E**.
£ HGL results for the 100 year 3 hour Chicago storm event increased by 20% were taken from the results of the XPSWMM model entitled "38298- ph1B-120CH.xp/out" and presented on the CD in **Appendix E**.

The results indicate that the minimum 0.3 m clearance between the USF and HGL is maintained across the proposed Phase 1B site during the 100 year 3 hour Chicago design storm event. The results of the sensitivity analysis show that the minimum 0.3 m clearance is maintained across the site and there would be no flooding to properties during the 100 year Chicago storm with a 20% increase in intensity or the July 1, 1979 historical storm.

5.5.2 Performance of the Park Dry Pond

The hydraulic functioning of the park dry pond has been confirmed in XPSWMM. The hydraulic evaluation was completed for the following storm events:

- 100 year 3 hour Chicago storm event with a 10 minute time step
- 100 year 24 hour SCS Type II storm event with a 12 minute time step
- July 1 1979, August 4 1988 and August 8 1996 historical storms with a 5 minute time step
- and 100 year 3 hour Chicago storm event with a 20% increase in intensity, 10 minute time step

The dry pond is designed to provide water quantity control for approximately 41 ha of the ultimate Rockcliffe development as discussed in **Section 5.3.2**. Outflow from the facility will be ultimately conveyed to the Eastern SWM Facility for treatment, via storm sewers, prior to being released to the Ottawa River.

The results are provided in **Table 5-10** and detailed discussion on each component of the proposed dry pond is provided in **Section 5.6**.

STORM SEWER CALCULATION SHEET (RATIONAL METHOD)

Local Roads Return Frequency = 2 years
Collector Roads Return Frequency = 5 years
Manning 0.013 Arterial Roads Return Frequency = 10 years

	LOCATION		AREA (Ha) 2 YEAR				5 YEAR				10 YEAR				100 YEAR				FLOW						SEWER DATA								
			AREA	R	Indiv.	Accum.	AREA	R	Indiv.	Accum.	AREA	R	Indiv.	Accum.	AREA	R	Indiv.	Accum.	Time of	Intensity	Intensity	Intensity	Intensity	Peak Flow	DIA. (mm)	DIA. (mm)	TYPE	SLOPE	LENGTH	CAPACITY	VELOCITY	TIME OF	RATIO
Location	From Node	To Node	(Ha)		2.78 AC	2.78 AC	(Ha)		2.78 AC	2.78 AC	(Ha)		2.78 AC	2.78 AC	(Ha)		2.78 AC	2.78 AC	Conc. (min)	2 Year (mm/h)	5 Year (mm/h)	10 Year (mm/h)	100 Year (mm/h)	Q (l/s)	(actual)	(nominal)		(%)	(m)	(l/s)	(m/s)	LOW (min	Q/Q full
Private Lane																																	
	101	102			0.00	0.00			0.00	0.00			0.00	0.00			0.00	0.00	10.00	76.81	104.19	122.14	178.56	0	300	300	PVC	0.50	43.4	68.3778	0.9673	0.7477	0.000
	102	104			0.00	0.00			0.00	0.00			0.00	0.00			0.00	0.00	10.75	74.05	100.40	117.68	172.00	0	300	300	PVC	0.50	5.4	68.3778	0.9673	0.0930	0.000
Makwa Private, Pipe 104 - 105						0.00				0.00				0.00				0.00	10.84														
Makwa Private																																	
	103	104			0.00	0.00	0.34	0.80	0.76	0.76			0.00	0.00			0.00	0.00	10.00	76.81	104.19	122.14	178.56	79	300	300	PVC	0.91	43.3	92.3480	1.3065	0.5524	0.853
Private Lane, Pipe 102 - 104						0.00				0.00				0.00				0.00	10.84														
	104	105			0.00	0.00	0.42	0.80	0.93	1.69			0.00	0.00			0.00	0.00	10.84	73.72	99.95	117.15	171.22	169	450	450	CONC	0.47	35.0	195.4589	1.2290	0.4747	0.864
	105	106			0.00	0.00			0.00	1.69			0.00	0.00			0.00	0.00	11.32	72.10	97.72	114.52	167.37	165	450	450	CONC	0.39	6.5	178.0487	1.1195	0.0968	0.928
	106	108			0.00	0.00			0.00	1.69			0.00	0.00			0.00	0.00	11.41	71.78	97.28	114.00	166.60	164	450	450	CONC	0.49	41.6	199.5743	1.2548	0.5519	0.824
Takamose Private, Pipe 108 - 109						0.00				1.69				0.00				0.00	11.96														
Takemose Private																																	
					0.00	0.00	0.12	0.80	0.27	0.27			0.00	0.00			0.00	0.00															
	107	108			0.00	0.00	0.22	0.80	0.49	0.76			0.00	0.00			0.00	0.00	10.00	76.81	104.19	122.14	178.56	79	300	300	PVC	1.19	112.1	105.4881	1.4924	1.2519	0.747
Contribution From Makwa Private, Pipe 106 - 108						0.00				1.69				0.00				0.00	11.96														
	108	109			0.00	0.00	0.24	0.80	0.53	2.98			0.00	0.00			0.00	0.00	11.96	70.01	94.85	111.14	162.40	283	600	600	CONC	0.87	30.4	571.3892	2.0209	0.2505	0.495
	109	EX. STM Sewer			0.00	0.00			0.00	2.98			0.00	0.00			0.00	0.00	12.21	69.23	93.79	109.89	160.57	280	600	600	CONC	1.16	13.8	661.1454	2.3383	0.0984	0.423
						0.00				2.98				0.00				0.00	12.31														



Definitions:
Q = 2.78 AIR, where
Q = Peak Flow in Litres per second (L/s)
A = Areas in hectares (ha)
I = Rainfall Intensity (mm/h)
R = Runoff Coefficient

Notes:
1) Ottawa Rainfall-Intensity Curve
2) Min. Velocity = 0.80 m/s

Designed: G.G.G.	PROJECT:		
Checked: S.L.M.	LOCATION: City of Ottawa		
Dwg. Reference: SS	File Ref:	Date: November 29 2019	Sheet No. SHEET 1 OF 1

SQUADRON CRESCENT EXISTING SEWERS STORM SEWER CALCULATION SHEET (RATIONAL METHOD)

Local Roads Return Frequency = 2 years
Collector Roads Return Frequency = 5 years
Manning 0.013 Arterial Roads Return Frequency = 10 years

	LOCATION		AREA (Ha)														FLOW							SEWER DATA								
			2 YEAR				5 YEAR				10 YEAR				100 YEAR				Time of	Intensity	Intensity	Intensity	Intensity	Peak Flow	Fixed Flow	DIA. (mm)	DIA. (mm)	TYPE	SLOPE	LENGTH	CAPACITY	VELOCITY	TIME OF	RATIO
			AREA	R	Indiv.	Accum.	AREA	R	Indiv.	Accum.	AREA	R	Indiv.	Accum.	AREA	R	Indiv.	Accum.	Conc.	2 Year	5 Year	10 Year	100 Year										
Location	From Node	To Node	(Ha)		2.78 AC	2.78 AC	(Ha)		2.78 AC	2.78 AC	(Ha)		2.78 AC	2.78 AC	(Ha)		2.78 AC	2.78 AC	(min)	(mm/h)	(mm/h)	(mm/h)	(mm/h)	Q (l/s)		(actual)	(nominal)		(%)	(m)	(l/s)	(m/s)	LOW (min	Q/Q full
Squadron Crescent																																	
From Block 15 to pipe between MH215 and MH216					0.00	0.00	0.07	0.75	0.15				0.00	0.00			0.00	0.00	10.00	76.81	104.19	122.14	178.56	0									
R215					0.00	0.00	0.14	0.56	0.22				0.00	0.00			0.00	0.00	10.00	76.81	104.19	122.14	178.56	0									
S215	215	216			0.00	0.00	0.38	0.73	0.77	1.14			0.00	0.00			0.00	0.00	10.00	76.81	104.19	122.14	178.56	118		525	525	PVC	0.50	79.9	304.0999	1.4048	0.9484	0.389
From Block 15 to pipe between MH216 and MH217					0.00	0.00	0.08	0.79	0.18				0.00	0.00																			
R216A					0.00	0.00	0.14	0.56	0.22				0.00	0.00			0.00	0.00	10.00	76.81	104.19	122.14	178.56	0									
R216B					0.00	0.00	0.06	0.56	0.09				0.00	0.00			0.00	0.00	10.00	76.81	104.19	122.14	178.56	0									
S216	216	217			0.00	0.00	0.28	0.73	0.57	2.19			0.00	0.00			0.00	0.00	10.95	73.35	99.44	116.54	170.33	218		600	600	PVC	0.45	76.0	411.8915	1.4568	0.8694	0.529
						0.00				12.28				0.00				0.00	14.11														
	217	218			0.00	0.00			0.00	14.47			0.00	0.00			0.00	0.00	14.11	63.95	86.55	101.37	148.06	1252		1050	1050	PVC	0.45	12.9	1831.8262	2.1155	0.1019	0.000
From Block 15 to pipe between MH218 and MH219					0.00	0.00	0.12	0.72	0.24				0.00	0.00																			
S218	218	219			0.00	0.00	0.17	0.70	0.33	15.04			0.00	0.00			0.00	0.00	14.21	63.69	86.19	100.95	147.44	1296		1050	1050	PVC	0.25	49.0	1365.3626	1.5768	0.5179	0.950
	219	220			0.00	0.00	0.00	0.00	0.00	15.04			0.00	0.00			0.00	0.00	14.73	62.41	84.44	98.89	144.42	1270		1200	1200	PVC	0.15	73.1	1509.9717	1.3351	0.9124	0.841
From Block 15 to pipe between MH220 and MH221					0.00	0.00	0.10	0.77	0.21				0.00	0.00																			
S220	220	221			0.00	0.00	0.18	0.70	0.35	15.61			0.00	0.00			0.00	0.00	15.64	60.29	81.54	95.48	139.41	1272		1200	1200	PVC	0.15	43.5	1509.9717	1.3351	0.5427	0.843
Fixed Flow from Burma SWM Facility																								6660									
	221	222			0.00	0.00	0.00	0.00	0.00	15.61			0.00	0.00			0.00	0.00	16.18	59.11	79.91	93.57	136.61	7907		2400	2400	PVC	0.11	12.0	8210.4354	1.8149	0.1099	0.963
S222A					0.00	0.00	0.12	0.70	0.23				0.00	0.00																			
From Block 15 to pipe between MH222 and MH165					0.00	0.00	0.08	0.74	0.16				0.00	0.00																			
S222B	222	Block 15 Connection			0.00	0.00	0.14	0.70	0.27	16.28			0.00	0.00			0.00	0.00	16.29	58.87	79.59	93.19	136.06	7956		2400	2400	PVC	0.11	79.6	8210.4354	1.8149	0.7310	0.969
Flow from Internal Block 15 Sewers						0.00				2.98				0.00				0.00	12.31														
	Block 15	165			0.00	0.00			0.00	19.26			0.00	0.00			0.00	0.00	17.03	57.37	77.54	90.77	132.51	8153		2400	2400	PVC	0.11	49.1	8210.4354	1.8149	0.4509	0.993
Mikinak Road																																	
From upstream pipe per IBI Phase 1A						0.00				12.74								0.00	13.20														
From Block 15 to pipe between MH165B and MH165					0.00	0.00	0.18	0.80	0.40	0.40			0.00	0.00																			
S164B	164	165B			0.00	0.00	0.22	0.73	0.45	13.59			0.00	0.00			0.00	0.00	13.20	66.37	89.86	105.27	153.78	1221		900	900	PVC	0.86	65.3	1678.8135	2.6389	0.4127	0.727
S164A	165B	165			0.00	0.00	0.18	0.73	0.37	13.95			0.00	0.00			0.00	0.00	13.61	65.25	88.32	103.46	151.13	1232		1050	1050	PVC	0.52	35.5	1969.1539	2.2741	0.2601	0.626

Definitions:
Q = 2.78 AIR, where
Q = Peak Flow in Litres per second (L/s)
A = Areas in hectares (ha)
I = Rainfall Intensity (mm/h)
R = Runoff Coefficient

Notes:
1) Ottawa Rainfall-Intensity Curve
2) Min. Velocity = 0.80 m/s

Designed:	G.G.G.	PROJECT:	**Wateridge - Block 15**
Checked:	S.L.M.	LOCATION:	**City of Ottawa**
Dwg. Reference:	SS	File Ref:	Date: November 29 2019 / Sheet No. SHEET 1 OF 1



INLET CONTROL DEVICE (ICD) DATA (Circular Orifice Plate)

STREET NAME	CB ID	OUTLET PIPE			INVERT DEPTH		TOP OF GRATE	INVERT		ICD DIA. (mm)	RELEASE RATE AT MAX. ALLOWABLE PONDING (L/S)	GRATING COVER	CB Type
		DIA. (mm)	TYPE	LENGTH (m)	INLET INV. DEPTH (m)	OUTLET INV. DEPTH (m)		INLET	OUTLET				
PRIVE KINIW PRIVATE	CB 103A	200	PVC	6.4	-	1.49	90.39	-	88.9	100	30.1	S19 PERFORATED	Single OPSD 400.010
PRIVE MAKWA PRIVATE	CB 103B	200	PVC	3.5	1.02	0.62	89.98	88.96	89.36	150	58.8	S19 PERFORATED	Single OPSD 400.010
PRIVE MAKWA PRIVATE	CB 104A	200	PVC	4.4	1.95	1.55	89.67	87.72	88.12	-	-	S19 PERFORATED	Single OPSD 400.010
PRIVE MAKWA PRIVATE	CB 104B	200	PVC	5.8	1.5	1.8	89.57	88.07	87.77	150	68.9	S19 PERFORATED	Single OPSD 400.010
PRIVE MAKWA PRIVATE	CB 105B	200	PVC	11.4	-	1.6	89.83	-	88.23	100	23.5	S19 PERFORATED	Single OPSD 400.010
PRIVE TAKAMOSE PRIVATE	CB 107A	200	PVC	6.2	0.67	1.51	90.4	89.73	88.89	100	27.2	S19 PERFORATED	Single OPSD 400.010
PRIVE TAKAMOSE PRIVATE	CB 107B	200	PVC	6.2	0.68	1.49	90.03	89.35	88.54	100	26.9	S19 PERFORATED	Single OPSD 400.010
PRIVE TAKAMOSE PRIVATE	CB 107C	200	PVC	6.2	0.52	1.37	89.51	88.99	88.14	100	26.3	S19 PERFORATED	Single OPSD 400.010
PRIVE TAKAMOSE PRIVATE	CB 108A	200	PVC	6.2	0.53	1.35	89.33	88.8	87.98	150	54.3	S19 PERFORATED	Twin OPSD 400.010
PRIVE TAKAMOSE PRIVATE	CB 108B	200	PVC	6.8	-	1.17	89.29	-	88.12	-	-	S19 PERFORATED	Single OPSD 400.010

STORAGE SUMMARY
BLOCK 15
STORAGE VOLUME AVAILABLE BELOW OVERFLOW (CLEARSTONE AND SUBDRAIN)

Total Site			
Rainfall (mm)	**Drainage Area (sq.m)**	**Volume Required (cu.m)**	**Total Provided (cu.m)**
4	19588	78.352	102.83

Area ID	**Drainage Area (sq.m)**	**Volume Req. (cu.m) (4mm Storm)**	**Clear Stone Area (525mm Depth) (sq.m)***	**Volume in Clear Stone (cu.m)****	**Subdrain Length (m)**	**Subdrain Size (mm)**	**Subdrain Volume (cu.m)**	**Total Volume (cu.m)**
103B-1 & 103B-2	2900	11.6	80	16.8	10	200	0.31	17.11
104A-1 & 104A-2	3800	15.2	96	20.16	13.4	200	0.42	20.58
105B-1	400	1.6	145	30.45	0	200	0.00	30.45
107A-1	1000	4.0	45	9.45	31.6	200	0.99	10.44
107B-1	1200	4.8	45	9.45	31.6	200	0.99	10.44
107C-1	1200	4.8	45	9.45	31.6	200	0.99	10.44
108A-1	2400	9.6	16	3.36	0	200	0.00	3.36
Total	**12900**	**51.6**	**472.0**	**99.1**	**118.2**		**3.7**	**102.83**

* Refer to Drawing DS-2 for Bioretention Cross Section
** Volume calculation assumes 40% Void Ratio for Clear Stone

STORAGE SUMMARY
BLOCK 15
TOTAL LID TREATMENT VOLUME

Area ID	Drainage Area (sq.m)	Volume Req. (cu.m) (15mm Storm)	Area of Filter Media & Mulch (675mm Depth) (sq.m)*	Volume in Filter Media & Mulch (cu.m)**	Volume Below Overflow (Clear Stone and Subdrain)	Total Volume (cu.m)
103B-1 & 103B-2	2900	43.5	80	18.90	17.11	36.01
104A-1 & 104A-2	3800	57.0	96	22.68	20.58	43.26
105B-1	400	6.0	145	34.26	30.45	64.71
107A-1	1000	15.0	45	10.63	10.44	21.07
107B-1	1200	18.0	45	10.63	10.44	21.07
107C-1	1200	18.0	45	10.63	10.44	21.07
108A-1	2400	36.0	16	3.78	3.36	7.14
Total	**12900**	**193.5**	**472.0**	**111.5**	**102.8**	**214.34**

* Refer to Drawing DS-2 for Bioretention Cross Section
** Volume calculation assumes 35% Void Ratio for the Filter Media

Curb Cut Capacity Analysis

1) Weir Equation used at Low Point			2) Curb Opening Calc along Slope		
Q = Cw (L-0.1nh)h^1.5			L = 0.817 x Q^0.42 x SL^0.3 ([1 / (n x SX)]^0.6		
Weir Coefficient (Cw)			Curb Opening (L)		m
Side Contractions (n)			Gutter Flow (Q)		cms
Head (h)		m	Longitudinal Slope (SL)		m/m
Req. Length (L)		m	Mannings N (n)		
			Road Cross Slope (SX)		m/m

103B-1			**103B-2**		
DC103B-1			**DC103B-2**		
Area	0.22	Ha	Area	0.12	Ha
RC	0.8		RC	0.8	
15mm Flow (EPASWMM)	16.5	L/s	15mm Flow (EPASWMM)	5.7	L/s
Curb Cut Analysis - Low Point			**Curb Cut Analysis - Along Slope**		
Q = Cw (L-0.1nh)h^1.5			L = 0.817 x Q^0.42 x SL^0.3 ([1 / (n x SX)]^0.6		
Weir Coefficient (Cw)	1.58		Longitudinal Slope (SL)	0.01	m/m
Side Contractions (n)	0		Mannings N (n)	0.013	
Head (h)	0.1	m	Road Cross Slope (SX)	0.03	m/m
Req. Length (L)	0.33024	m	Req. Length (L)	2.6005	m
Actual Length	0.5	m	Actual Length (L)	2.6	m

104A-1			**104A-2**		
DC104A-1			**DC104A-2**		
Area	0.19	Ha	Area	0.19	Ha
RC	0.8		RC	0.8	
15mm Flow (EPASWMM)	14.6	L/s	15mm Flow (EPASWMM)	16.2	L/s
Curb Cut Analysis - Low Point			**Curb Cut Analysis - Along Slope**		
Q = Cw (L-0.1nh)h^1.5			L = 0.817 x Q^0.42 x SL^0.3 ([1 / (n x SX)]^0.6		
Weir Coefficient (Cw)	1.58		Longitudinal Slope (SL)	0.005	m/m
Side Contractions (n)	0		Mannings N (n)	0.013	
Head (h)	0.1	m	Road Cross Slope (SX)	0.03	m/m
Req. Length (L)	0.29221	m	Req. Length (L)	3.2754	m
Actual Length	0.5	m	Actual Length (L)	3.3	m

107A-1
DC107A-1

Area	0.1	Ha
RC	0.8	
15mm Flow (EPASWMM)	8.7	L/s

Curb Cut Analysis - Along Slope

L = 0.817 x Q^0.42 x SL^0.3 ([1 / (n x SX)]^0.6		
Longitudinal Slope (SL)	0.01	m/m
Mannings N (n)	0.013	
Road Cross Slope (SX)	0.03	m/m
Req. Length (L)	3.10586	m
Actual Length (L)	3.3	m

107B-1
DC107B-1

Area	0.12	Ha
RC	0.8	
15mm Flow (EPASWMM)	10.4	L/s

Curb Cut Analysis - Along Slope

L = 0.817 x Q^0.42 x SL^0.3 ([1 / (n x SX)]^0.6		
Longitudinal Slope (SL)	0.02	m/m
Mannings N (n)	0.013	
Road Cross Slope (SX)	0.03	m/m
Req. Length (L)	4.1214	m
Actual Length (L)	4.2	m

107C-1
DC107C-1

Area	0.12	Ha
RC	0.8	
15mm Flow (EPASWMM)	10.5	L/s

Curb Cut Analysis - Along Slope

L = 0.817 x Q^0.42 x SL^0.3 ([1 / (n x SX)]^0.6		
Longitudinal Slope (SL)	0.005	m/m
Mannings N (n)	0.013	
Road Cross Slope (SX)	0.03	m/m
Req. Length (L)	2.73007	m
Actual Length (L)	3	m

108A-1
DC108A-1

Area	0.24	Ha
RC	0.8	
15mm Flow (EPASWMM)	19.4	L/s

Curb Cut Analysis - Along Slope

L = 0.817 x Q^0.42 x SL^0.3 ([1 / (n x SX)]^0.6		
Longitudinal Slope (SL)	0.005	m/m
Mannings N (n)	0.013	
Road Cross Slope (SX)	0.03	m/m
Req. Length (L)	3.5331	m
Actual Length (L)	3.6	m

CB ID	Ponding Depth (m)	Total Maximum Inflow for 5-Year Storm Event (L/s)*	CB Grate Capacity (L/s)**	CB Size Type
CB 107A	0.12	29.65	92	Single OPSD 400.010
CB 107 B	0.1	36.28	60	Single OPSD 400.010
CB 108A	0.1	66.07	90	Twin OPSD 400.010
CB 107C	0.13	35.8	97	Single OPSD 400.010
CB 105B	0.07	11.21	25	Single OPSD 400.010
CB 104A	0.22	106.47	170	Single OPSD 400.010
CB 103B	0.22	59.86	170	Single OPSD 400.010
CB 103A	0.12	70.63	92	Single OPSD 400.010

*5-Year Storm Inflow taken from SWM Model using 5-year storm event

**Inlet Capacity calculated using Table 4.16 of the MTO Drainage Management Manual, 1997

Area ID	Outlet	Area	C	% Imp	Length	Width	Slope
103B-1	CB103B	0.22	0.8	0.86	50	44	0.5
103A-1	CB103A	0.05	0.8	0.86	25	20	0.5
103B-2	CB103B	0.07	0.8	0.86	18	39	0.5
104A-1	CB104A	0.19	0.8	0.86	41	46	0.5
104A-2	CB104A	0.19	0.8	0.86	56	34	0.5
105B-1	CB105B	0.04	0.8	0.86	17	24	1.5
108A-1	CB108A	0.24	0.8	0.86	14	171	2
107C-1	CB107C	0.12	0.8	0.86	35	34	2
107B-1	CB107B	0.12	0.8	0.86	35	34	1
107A-1	CB107A	0.1	0.8	0.86	35	29	0.7

MH108-MH109	Imp.	Perv.	Interlocking	Total
Area	0.204	0.031	0.006	0.241
C	0.9	0.2	0.6	0.80

MH107-MH108	Imp.	Perv.	Interlocking	Total
Area	0.083	0.020	0.001	0.104
C	0.9	0.2	0.6	0.76

MH107-MH108	Imp.	Perv.	Interlocking	Total
Area	0.202	0.035	0.003	0.240
C	0.9	0.2	0.6	0.79

MH101-MH102	Imp.	Perv.	Interlocking	Total
Area	0.339	0.080	0.007	0.426
C	0.9	0.2	0.6	0.76

MH103-MH104	Imp.	Perv.	Interlocking	Total
Area	0.288	0.043	0.008	0.339
C	0.9	0.2	0.6	0.80

EX.MH216-EX.MH217	Imp.	Perv.	Interlocking	Total
Area	0.057	0.005	0.017	0.080
C	0.9	0.2	0.6	0.79


EX.MH218-EX.MH219	Imp.	Perv.	Interlocking	Total
Area	0.084	0.027	0.010	0.121
C	0.9	0.2	0.6	0.72

EX.MH220-EX.MH221	Imp.	Perv.	Interlocking	Total
Area	0.072	0.011	0.017	0.100
C	0.9	0.2	0.6	0.77


EX.MH222-EX.MH165	Imp.	Perv.	Interlocking	Total
Area	0.048	0.011	0.011	0.071
C	0.9	0.2	0.6	0.74

Mikinak	Imp.	Perv.	Interlocking	Total
Area	0.125	0.033	0.008	0.165
C	0.9	0.2	0.6	0.75

EX.MH215-EX.MH216	Imp.	Perv.	Interlocking	Total
Area	0.044	0.009	0.012	0.065
C	0.9	0.2	0.6	0.75


107A-1
0.11
86%
107B-1
0.13
86%
107A-1
0.11
86%
CB107C
CB107B
CB107A
100mm ICD
100mm ICD
100mm ICD
CB108C
MAJOR-OUTLET
MINOR-OUTLET
MH109
MH108
MH107
CB104A-1
0.19
86%
OVRLN101
MH101
104A-2
0.22
86%
OVRLND106
108A-1
0.24
86%
CB104A
150mm ICD
MH105
MH106
MH105
MH105
100mm ICD
CB105B
105B-1
0.04
86%
OVRLND102
103B-1
0.22
86%
CB103B
150mm ICD
MH107
100mm ICD
CB103A
103B-2
0.07
86%
103A-1
0.05
86%

LEGEND


102
0.259
71%
CATCHMENT ID
PERCENT IMPERVIOUS
AREA IN HECTARES
MINOR SYSTEM
MAJOR SYSTEM
CATCHMENT CONNECTION
147mm ICD
CONTROL AREA
ORIFICE SIZE
INLET CONTROL DEVICE (ICD)
NODE
STM13

```
EPA STORM WATER MANAGEMENT MODEL - VERSION 5.1 (Build 5.1.012)
--------------------------------------------------------------

WARNING 02: maximum depth increased for Node CB107A
WARNING 02: maximum depth increased for Node CB107B
WARNING 02: maximum depth increased for Node CB108A
WARNING 02: maximum depth increased for Node CB107C
WARNING 02: maximum depth increased for Node CB105B
WARNING 02: maximum depth increased for Node CB104B
WARNING 02: maximum depth increased for Node CB103B
WARNING 02: maximum depth increased for Node CB103A

***********************************************************
NOTE: The summary statistics displayed in this report are
based on results found at every computational time step,
not just on results from each reporting time step.
***********************************************************

****************
Analysis Options
****************
Flow Units ............... LPS
Process Models:
  Rainfall/Runoff ........ YES
  RDII ................... NO
  Snowmelt ............... NO
  Groundwater ............ NO
  Flow Routing ........... YES
  Ponding Allowed ........ YES
  Water Quality .......... NO
Infiltration Method ...... HORTON
Flow Routing Method ...... DYNWAVE
Starting Date ............ 01/01/2000 00:01:00
Ending Date .............. 01/02/2000 00:00:00
Antecedent Dry Days ...... 0.0
Report Time Step ......... 00:01:00
Wet Time Step ............ 00:01:00
Dry Time Step ............ 00:01:00
Routing Time Step ........ 2.00 sec
Variable Time Step ....... YES
Maximum Trials ........... 8
Number of Threads ........ 1
Head Tolerance ........... 0.001500 m


*************************        Volume         Depth
Runoff Quantity Continuity     hectare-m            mm
*************************     ---------       -------
Initial LID Storage ......         0.002         1.351
```

Total Precipitation	0.115	82.291
Evaporation Loss	0.000	0.000
Infiltration Loss	0.009	6.506
Surface Runoff	0.106	75.852
Final Storage	0.002	1.351
Continuity Error (%)	-0.080	

Flow Routing Continuity	Volume hectare-m	Volume 10^6 ltr
Dry Weather Inflow	0.000	0.000
Wet Weather Inflow	0.106	1.062
Groundwater Inflow	0.000	0.000
RDII Inflow	0.000	0.000
External Inflow	0.000	0.000
External Outflow	0.106	1.061
Flooding Loss	0.000	0.000
Evaporation Loss	0.000	0.000
Exfiltration Loss	0.000	0.000
Initial Stored Volume	0.001	0.013
Final Stored Volume	0.002	0.016
Continuity Error (%)	-0.153	

Highest Continuity Errors

Node CB103B (-3.63%)
Node CB104B (1.68%)

Time-Step Critical Elements

Link 7 (1.59%)

Highest Flow Instability Indexes

All links are stable.

Routing Time Step Summary

Minimum Time Step	:	0.06 sec
Average Time Step	:	1.99 sec
Maximum Time Step	:	2.00 sec

```
  Percent in Steady State     :     0.00
  Average Iterations per Step :     2.00
  Percent Not Converging      :     0.03


  **************************
  Subcatchment Runoff Summary
  **************************


-------------------------------------------------------------------------------
-------------------
                           Total      Total      Total      Total      Total
Total     Peak  Runoff
                          Precip      Runon       Evap      Infil     Runoff
Runoff   Runoff   Coeff
  Subcatchment                mm         mm         mm         mm         mm
10^6 ltr      LPS

-------------------------------------------------------------------------------
-------------------
  103B-1                  82.29       0.00       0.00       6.57      75.77
0.17   105.01   0.921
  103A-1                  82.29       0.00       0.00       6.48      75.88
0.04    24.38   0.922
  103B-2                  82.29       0.00       0.00       6.43      75.96
0.05    34.32   0.923
  CB104A-1                82.29       0.00       0.00       6.54      75.81
0.14    91.45   0.921
  104A-2                  82.29       0.00       0.00       6.59      75.74
0.17   104.33   0.920
  105B-1                  82.29       0.00       0.00       6.42      75.98
0.03    19.62   0.923
  108A-1                  82.29       0.00       0.00       6.44      75.95
0.18   117.64   0.923
  107C-1                  82.29       0.00       0.00       6.45      75.93
0.10    63.64   0.923
  107B-1                  82.29       0.00       0.00       6.48      75.88
0.10    63.39   0.922
  107A-1                  82.29       0.00       0.00       6.50      75.86
0.08    53.45   0.922


  ******************
  Node Depth Summary
  ******************

  ---------------------------------------------------------------------------
                              Average  Maximum  Maximum  Time of Max    Reported
                                Depth    Depth      HGL   Occurrence   Max Depth
```

Node	Type	Meters	Meters	Meters	days	hr:min	Meters
MH109	JUNCTION	1.38	1.48	86.48	0	01:59	1.48
MH108	JUNCTION	0.42	0.73	86.69	0	01:59	0.73
MH106	JUNCTION	0.07	0.61	86.93	0	01:59	0.61
MH105	JUNCTION	0.04	0.66	87.04	0	01:59	0.65
MH104	JUNCTION	0.03	0.63	87.21	0	01:59	0.62
MH102	JUNCTION	0.01	0.41	87.21	0	01:59	0.41
STM101	JUNCTION	0.00	0.17	87.22	0	01:59	0.17
MH107	JUNCTION	0.02	0.20	87.91	0	01:52	0.20
MH103	JUNCTION	0.02	0.95	88.06	0	01:54	0.54
CB107A	JUNCTION	0.04	1.69	90.58	0	01:59	1.69
CB107B	JUNCTION	0.05	1.65	90.19	0	01:59	1.65
CB108A	JUNCTION	0.05	1.34	89.32	0	01:59	1.34
CB107C	JUNCTION	0.05	1.58	89.72	0	01:59	1.58
CB105B	JUNCTION	0.01	0.90	89.13	0	01:59	0.90
CB104B	JUNCTION	0.10	2.11	89.88	0	02:03	2.11
CB103B	JUNCTION	0.03	1.58	90.06	0	01:59	1.58
CB103A	JUNCTION	0.07	1.81	90.53	0	01:59	1.81
OVRLN101	JUNCTION	0.01	0.09	90.24	0	01:59	0.09
OVRLND102	JUNCTION	0.01	0.09	90.94	0	01:59	0.09
OVERLAND106	JUNCTION	0.01	0.09	89.80	0	01:59	0.09
MINOR-OUTLET	OUTFALL	1.43	1.43	86.38	0	00:00	1.43
OVERLANDFLOWOUT	OUTFALL	0.00	0.00	94.61	0	00:00	0.00
MAJOR-OUTLET	OUTFALL	0.00	0.10	89.22	0	01:59	0.10

****
Node Inflow Summary
****

Node	Type	Maximum Lateral Inflow LPS	Maximum Total Inflow LPS	Time of Max Occurrence days hr:min	Lateral Inflow Volume 10^6 ltr	Total Inflow Volume 10^6 ltr	Flow Balance Error Percent
MH109	JUNCTION	0.00	308.14	0 01:59	0	0.997	-0.000
MH108	JUNCTION	0.00	308.12	0 01:59	0	0.997	-0.062
MH106	JUNCTION	0.00	174.10	0 01:59	0		

```
0.582      -0.005
  MH105                JUNCTION      0.00   174.07     0  01:59           0
0.582      -0.007
  MH104                JUNCTION      0.00   159.10     0  02:01           0
0.554      -0.106
  MH102                JUNCTION      0.00    10.69     0  01:55           0
0.00447      -0.087
  STM101               JUNCTION      0.00     8.37     0  01:56           0
0.00115       0.000
  MH107                JUNCTION      0.00    80.25     0  01:59           0
0.244       0.000
  MH103                JUNCTION      0.00    88.57     0  01:59           0
0.23       0.000
  CB107A               JUNCTION     53.45    53.45     0  01:59      0.0834
0.0834      -0.432
  CB107B               JUNCTION     63.39    89.52     0  01:59      0.0987
0.11       0.182
  CB108A               JUNCTION      0.00   214.84     0  01:59           0
0.235      -0.612
  CB107C               JUNCTION     63.64   125.49     0  01:59      0.0987
0.124      -0.121
  CB105B               JUNCTION     19.62    19.62     0  01:59      0.0304
0.0304       0.003
  CB104B               JUNCTION    104.33   267.44     0  01:59       0.167
0.344       1.710
  CB103B               JUNCTION     34.32   132.84     0  01:59      0.0532
0.115      -3.506
  CB103A               JUNCTION     24.38   128.90     0  01:59      0.0379
0.205       0.182
  OVRLN101             JUNCTION     91.45    91.45     0  01:59       0.144
0.144      -1.259
  OVRLND102            JUNCTION    105.01   105.01     0  01:59       0.167
0.167       0.066
  OVERLAND106          JUNCTION    117.64   117.71     0  01:59       0.182
0.199       0.635
  MINOR-OUTLET         OUTFALL       0.00   308.16     0  01:59           0
0.998       0.000
  OVERLANDFLOWOUT      OUTFALL       0.00     0.00     0  00:00           0
 0       0.000 ltr
  MAJOR-OUTLET         OUTFALL       0.00   147.90     0  01:59           0
0.0653       0.000


  **********************
  Node Surcharge Summary
  **********************

  Surcharging occurs when water rises above the top of the highest conduit.
  -------------------------------------------------------------------------
                                                  Max. Height   Min. Depth
```

Node	Type	Hours Surcharged	Above Crown Meters	Below Rim Meters
MH109	JUNCTION	0.20	0.015	2.935
MH108	JUNCTION	0.14	0.027	2.949
MH106	JUNCTION	0.24	0.130	3.019
MH105	JUNCTION	0.25	0.177	2.739
MH104	JUNCTION	0.20	0.138	2.776
MH102	JUNCTION	0.14	0.081	2.836
MH103	JUNCTION	0.19	0.647	2.326

****
Node Flooding Summary
****

No nodes were flooded.

****
Outfall Loading Summary
****

Outfall Node	Flow Freq Pcnt	Avg Flow LPS	Max Flow LPS	Total Volume 10^6 ltr
MINOR-OUTLET	68.14	18.69	308.16	0.998
OVERLANDFLOWOUT	0.00	0.00	0.00	0.000
MAJOR-OUTLET	1.91	43.08	147.90	0.065
System	23.35	61.76	456.06	1.063

****
Link Flow Summary
****

Link	Type	Maximum |Flow| LPS	Time of Max Occurrence days hr:min	Maximum |Veloc| m/sec	Max/ Full Flow	Max/ Full Depth
3	CONDUIT	308.16	0 01:59	1.09	0.83	1.00
4	CONDUIT	308.14	0 01:59	1.09	0.86	1.00
5	CONDUIT	80.46	0 01:53	1.55	0.76	0.83
6	CONDUIT	174.10	0 01:59	1.09	0.86	1.00
7	CONDUIT	174.10	0 01:59	1.09	0.86	1.00
8	CONDUIT	159.27	0 02:01	1.02	0.79	1.00

9	CONDUIT	10.69	0	01:55	0.31	0.16	1.00
10	CONDUIT	8.37	0	01:56	0.20	0.12	0.78
11	CONDUIT	88.56	0	01:59	1.37	0.98	1.00
17	CHANNEL	90.38	0	01:59	0.60	0.03	0.57
18	CHANNEL	104.55	0	01:59	0.79	0.03	0.26
19	CHANNEL	72.91	0	01:59	0.28	0.02	0.54
20	CHANNEL	31.50	0	02:03	0.47	0.01	0.19
21	CONDUIT	0.00	0	00:00	0.00	0.00	0.15
22	CHANNEL	117.55	0	01:59	0.85	0.03	0.43
23	CHANNEL	98.58	0	01:59	1.50	0.01	0.21
24	CHANNEL	26.14	0	01:59	0.16	0.01	0.31
25	CHANNEL	61.89	0	01:59	0.21	0.01	0.40
26	CHANNEL	97.36	0	01:59	0.31	0.02	0.41
27	CHANNEL	147.90	0	01:59	0.85	0.04	0.30
1	ORIFICE	68.21	0	02:03			1.00
2	ORIFICE	27.16	0	01:59			1.00
12	ORIFICE	26.87	0	01:59			1.00
13	ORIFICE	26.22	0	01:59			1.00
14	ORIFICE	53.78	0	01:59			1.00
15	ORIFICE	19.55	0	01:59			1.00
16	ORIFICE	58.56	0	01:59			1.00
28	ORIFICE	30.01	0	01:59			1.00

****
Flow Classification Summary
****

Conduit	Adjusted /Actual Length	Fraction of Time in Flow Class: Dry	Up Dry	Down Dry	Sub Crit	Sup Crit	Up Crit	Down Crit	Norm Ltd	Inlet Ctrl
3	1.00	0.00	0.00	0.00	1.00	0.00	0.00	0.00	0.00	0.00
4	1.00	0.00	0.00	0.00	1.00	0.00	0.00	0.00	0.00	0.00
5	1.00	0.00	0.00	0.00	0.75	0.01	0.00	0.24	0.76	0.00
6	1.00	0.00	0.00	0.00	1.00	0.00	0.00	0.00	0.08	0.00
7	1.00	0.00	0.00	0.00	0.78	0.00	0.00	0.22	0.74	0.00

8	1.00	0.00	0.00	0.00	0.05	0.00	0.00	0.95	0.00
0.00									
9	1.00	0.00	0.00	0.00	0.04	0.00	0.00	0.96	0.00
0.00									
10	1.00	0.00	0.00	0.00	0.03	0.00	0.00	0.97	0.01
0.00									
11	1.00	0.00	0.00	0.00	0.02	0.00	0.00	0.98	0.00
0.00									
17	1.00	0.00	0.00	0.00	0.04	0.00	0.00	0.96	0.03
0.00									
18	1.00	0.00	0.00	0.00	0.00	0.02	0.00	0.98	0.01
0.00									
19	1.00	0.96	0.03	0.00	0.01	0.00	0.00	0.00	0.92
0.00									
20	1.00	0.00	0.98	0.00	0.02	0.00	0.00	0.00	0.92
0.00									
21	1.00	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00
0.00									
22	1.00	0.00	0.00	0.00	0.02	0.00	0.00	0.98	0.02
0.00									
23	1.00	0.98	0.00	0.00	0.00	0.01	0.00	0.01	0.01
0.00									
24	1.00	0.98	0.01	0.00	0.01	0.00	0.00	0.00	0.92
0.00									
25	1.00	0.98	0.01	0.00	0.01	0.00	0.00	0.00	0.92
0.00									
26	1.00	0.98	0.01	0.00	0.02	0.00	0.00	0.00	0.92
0.00									
27	1.00	0.98	0.00	0.00	0.01	0.01	0.00	0.00	0.01
0.00									

****
Conduit Surcharge Summary
****

Conduit	Hours Full: Both Ends	Hours Full: Upstream	Hours Full: Dnstream	Hours Above Full Normal Flow	Hours Capacity Limited
3	23.98	23.98	23.98	0.01	0.37
4	0.20	0.34	0.20	0.01	0.20
5	0.01	0.01	0.14	0.01	0.01
6	0.27	0.27	0.34	0.01	0.17
7	0.24	0.28	0.24	0.01	0.24
8	0.22	0.22	0.25	0.01	0.08
9	0.18	0.18	0.20	0.01	0.01
10	0.01	0.01	0.14	0.01	0.01
11	0.19	0.19	0.22	0.01	0.18

```
Analysis begun on:  Fri Oct 04 14:51:55 2019
Analysis ended on:  Fri Oct 04 14:51:57 2019
Total elapsed time: 00:00:02
```

```
EPA STORM WATER MANAGEMENT MODEL - VERSION 5.1 (Build 5.1.012)
--------------------------------------------------------------

WARNING 02: maximum depth increased for Node CB107A
WARNING 02: maximum depth increased for Node CB107B
WARNING 02: maximum depth increased for Node CB108A
WARNING 02: maximum depth increased for Node CB107C
WARNING 02: maximum depth increased for Node CB105B
WARNING 02: maximum depth increased for Node CB104B
WARNING 02: maximum depth increased for Node CB103B
WARNING 02: maximum depth increased for Node CB103A

***********************************************************
NOTE: The summary statistics displayed in this report are
based on results found at every computational time step,
not just on results from each reporting time step.
***********************************************************

****************
Analysis Options
****************
Flow Units ............... LPS
Process Models:
  Rainfall/Runoff ........ YES
  RDII ................... NO
  Snowmelt ............... NO
  Groundwater ............ NO
  Flow Routing ........... YES
  Ponding Allowed ........ YES
  Water Quality .......... NO
Infiltration Method ...... HORTON
Flow Routing Method ...... DYNWAVE
Starting Date ............ 01/01/2000 00:01:00
Ending Date .............. 01/02/2000 00:00:00
Antecedent Dry Days ...... 0.0
Report Time Step ......... 00:01:00
Wet Time Step ............ 00:01:00
Dry Time Step ............ 00:01:00
Routing Time Step ........ 2.00 sec
Variable Time Step ....... YES
Maximum Trials ........... 8
Number of Threads ........ 1
Head Tolerance ........... 0.001500 m


*************************        Volume         Depth
Runoff Quantity Continuity     hectare-m            mm
*************************     ---------       -------
Initial LID Storage ......         0.002         1.351
```

Total Precipitation	0.138	98.754
Evaporation Loss	0.000	0.000
Infiltration Loss	0.010	7.137
Surface Runoff	0.128	91.697
Final Storage	0.002	1.351
Continuity Error (%)	-0.081	

Flow Routing Continuity	Volume hectare-m	Volume 10^6 ltr
Dry Weather Inflow	0.000	0.000
Wet Weather Inflow	0.128	1.284
Groundwater Inflow	0.000	0.000
RDII Inflow	0.000	0.000
External Inflow	0.000	0.000
External Outflow	0.128	1.283
Flooding Loss	0.000	0.000
Evaporation Loss	0.000	0.000
Exfiltration Loss	0.000	0.000
Initial Stored Volume	0.001	0.013
Final Stored Volume	0.002	0.016
Continuity Error (%)	-0.110	

****
Highest Continuity Errors
****
Node CB103B (-3.21%)
Node CB104B (1.65%)

****
Time-Step Critical Elements
****
Link 7 (1.61%)

****
Highest Flow Instability Indexes
****
All links are stable.

****
Routing Time Step Summary
****
Minimum Time Step : 0.50 sec
Average Time Step : 1.99 sec
Maximum Time Step : 2.00 sec

```
  Percent in Steady State     :     0.00
  Average Iterations per Step :     2.00
  Percent Not Converging      :     0.02


  **************************
  Subcatchment Runoff Summary
  **************************


-------------------------------------------------------------------------------
-------------------
                           Total      Total      Total      Total      Total
Total     Peak  Runoff
                          Precip      Runon       Evap      Infil     Runoff
Runoff   Runoff   Coeff
  Subcatchment                mm         mm         mm         mm         mm
10^6 ltr      LPS

-------------------------------------------------------------------------------
-------------------
  103B-1                   98.75       0.00       0.00       7.20      91.62
0.20   127.37   0.928
  103A-1                   98.75       0.00       0.00       7.11      91.73
0.05    29.40   0.929
  103B-2                   98.75       0.00       0.00       7.07      91.80
0.06    41.29   0.930
  CB104A-1                 98.75       0.00       0.00       7.17      91.65
0.17   110.70   0.928
  104A-2                   98.75       0.00       0.00       7.22      91.59
0.20   126.72   0.927
  105B-1                   98.75       0.00       0.00       7.06      91.82
0.04    23.60   0.930
  108A-1                   98.75       0.00       0.00       7.07      91.79
0.22   141.56   0.929
  107C-1                   98.75       0.00       0.00       7.09      91.77
0.12    76.62   0.929
  107B-1                   98.75       0.00       0.00       7.11      91.73
0.12    76.44   0.929
  107A-1                   98.75       0.00       0.00       7.13      91.70
0.10    64.53   0.929


  ******************
  Node Depth Summary
  ******************

  ------------------------------------------------------------------------
                              Average  Maximum  Maximum  Time of Max    Reported
                                Depth    Depth      HGL   Occurrence   Max Depth
```

Node	Type	Meters	Meters	Meters	days	hr:min	Meters
MH109	JUNCTION	1.38	1.48	86.48	0	01:59	1.48
MH108	JUNCTION	0.42	0.74	86.70	0	01:59	0.74
MH106	JUNCTION	0.08	0.64	86.96	0	01:59	0.64
MH105	JUNCTION	0.04	0.69	87.08	0	01:59	0.69
MH104	JUNCTION	0.03	0.66	87.25	0	01:59	0.66
MH102	JUNCTION	0.01	0.45	87.25	0	01:59	0.45
STM101	JUNCTION	0.00	0.21	87.26	0	01:59	0.21
MH107	JUNCTION	0.02	0.20	87.91	0	01:52	0.20
MH103	JUNCTION	0.02	0.58	87.70	0	01:59	0.58
CB107A	JUNCTION	0.04	1.69	90.58	0	01:59	1.69
CB107B	JUNCTION	0.05	1.66	90.20	0	01:59	1.66
CB108A	JUNCTION	0.05	1.37	89.35	0	02:00	1.37
CB107C	JUNCTION	0.05	1.59	89.73	0	01:59	1.59
CB105B	JUNCTION	0.02	1.27	89.50	0	01:59	1.27
CB104B	JUNCTION	0.11	2.16	89.93	0	02:01	2.16
CB103B	JUNCTION	0.03	1.59	90.07	0	01:59	1.59
CB103A	JUNCTION	0.08	1.82	90.54	0	01:59	1.82
OVRLN101	JUNCTION	0.01	0.09	90.24	0	01:59	0.09
OVRLND102	JUNCTION	0.01	0.10	90.95	0	01:59	0.10
OVERLAND106	JUNCTION	0.01	0.11	89.82	0	02:00	0.11
MINOR-OUTLET	OUTFALL	1.43	1.43	86.38	0	00:00	1.43
OVERLANDFLOWOUT	OUTFALL	0.00	0.00	94.61	0	00:00	0.00
MAJOR-OUTLET	OUTFALL	0.00	0.13	89.25	0	02:00	0.13

****
Node Inflow Summary
****

Node	Type	Maximum Lateral Inflow LPS	Maximum Total Inflow LPS	Time of Max Occurrence days hr:min	Lateral Inflow Volume 10^6 ltr	Total Inflow Volume 10^6 ltr	Flow Balance Error Percent
MH109	JUNCTION	0.00	314.65	0 01:59	0	1.13	-0.001
MH108	JUNCTION	0.00	314.63	0 01:59	0	1.13	-0.053
MH106	JUNCTION	0.00	179.95	0 01:59	0		

```
0.658      -0.006
  MH105                JUNCTION      0.00   179.94     0  01:59           0
0.657      -0.000
  MH104                JUNCTION      0.00   160.58     0  02:01           0
0.624      -0.113
  MH102                JUNCTION      0.00    16.57     0  01:54           0
0.00501      -0.080
  STM101               JUNCTION      0.00    10.99     0  01:55           0
0.00141       0.000
  MH107                JUNCTION      0.00    80.46     0  01:59           0
0.278       0.000
  MH103                JUNCTION      0.00    88.86     0  01:59           0
0.263       0.000
  CB107A               JUNCTION     64.53    64.53     0  01:59       0.101
0.101      -0.430
  CB107B               JUNCTION     76.44   113.65     0  01:59       0.119
0.138       0.172
  CB108A               JUNCTION      0.00   325.94     0  01:59           0
0.347      -0.436
  CB107C               JUNCTION     76.62   162.89     0  01:59       0.119
0.16      -0.239
  CB105B               JUNCTION     23.60    23.60     0  01:59      0.0367
0.0367       0.002
  CB104B               JUNCTION    126.72   343.59     0  01:59       0.202
0.431       1.679
  CB103B               JUNCTION     41.29   167.20     0  01:59      0.0643
0.149      -3.111
  CB103A               JUNCTION     29.40   156.34     0  01:59      0.0459
0.247       0.164
  OVRLN101             JUNCTION    110.70   110.70     0  01:59       0.174
0.174      -1.227
  OVRLND102            JUNCTION    127.37   127.37     0  01:59       0.202
0.202       0.056
  OVERLAND106          JUNCTION    141.56   206.53     0  01:59        0.22
0.286       0.511
  MINOR-OUTLET         OUTFALL       0.00   314.67     0  01:59           0
1.13       0.000
  OVERLANDFLOWOUT      OUTFALL       0.00     0.00     0  00:00           0
 0       0.000 ltr
  MAJOR-OUTLET         OUTFALL       0.00   256.84     0  02:00           0
0.153       0.000


  **********************
  Node Surcharge Summary
  **********************

  Surcharging occurs when water rises above the top of the highest conduit.
  -------------------------------------------------------------------------
                                                  Max. Height   Min. Depth
```

Node	Type	Hours Surcharged	Above Crown Meters	Below Rim Meters
MH109	JUNCTION	0.26	0.019	2.931
MH108	JUNCTION	0.19	0.040	2.936
MH106	JUNCTION	0.29	0.160	2.989
MH105	JUNCTION	0.31	0.214	2.702
MH104	JUNCTION	0.25	0.178	2.736
MH102	JUNCTION	0.21	0.121	2.796
MH103	JUNCTION	0.23	0.281	2.692

****
Node Flooding Summary
****

No nodes were flooded.

****
Outfall Loading Summary
****

Outfall Node	Flow Freq Pcnt	Avg Flow LPS	Max Flow LPS	Total Volume 10^6 ltr
MINOR-OUTLET	67.78	20.87	314.67	1.132
OVERLANDFLOWOUT	0.00	0.00	0.00	0.000
MAJOR-OUTLET	2.17	86.43	256.84	0.153
System	23.31	107.31	570.69	1.285

****
Link Flow Summary
****

Link	Type	Maximum |Flow| LPS	Time of Max Occurrence days	hr:min	Maximum |Veloc| m/sec	Max/ Full Flow	Max/ Full Depth
3	CONDUIT	314.67	0	01:59	1.11	0.85	1.00
4	CONDUIT	314.65	0	01:59	1.11	0.88	1.00
5	CONDUIT	80.75	0	01:52	1.54	0.76	0.83
6	CONDUIT	179.95	0	01:59	1.13	0.89	1.00
7	CONDUIT	179.95	0	01:59	1.13	0.89	1.00
8	CONDUIT	160.74	0	02:01	1.02	0.80	1.00

9	CONDUIT	16.57	0	01:54	0.30	0.24	1.00
10	CONDUIT	10.99	0	01:55	0.24	0.16	0.84
11	CONDUIT	88.85	0	01:59	1.37	0.98	1.00
17	CHANNEL	109.73	0	01:59	0.61	0.03	0.64
18	CHANNEL	126.97	0	01:59	0.84	0.03	0.28
19	CHANNEL	107.31	0	01:59	0.34	0.03	0.63
20	CHANNEL	144.31	0	02:01	0.83	0.04	0.30
21	CONDUIT	0.00	0	00:00	0.00	0.00	0.18
22	CHANNEL	202.94	0	02:01	0.87	0.05	0.49
23	CHANNEL	125.97	0	01:59	1.53	0.01	0.23
24	CHANNEL	37.21	0	01:59	0.19	0.01	0.33
25	CHANNEL	86.29	0	01:59	0.25	0.02	0.42
26	CHANNEL	135.80	0	01:59	0.36	0.03	0.46
27	CHANNEL	256.84	0	02:00	0.98	0.07	0.37
1	ORIFICE	68.92	0	02:01			1.00
2	ORIFICE	27.21	0	01:59			1.00
12	ORIFICE	26.94	0	01:59			1.00
13	ORIFICE	26.31	0	01:59			1.00
14	ORIFICE	54.28	0	02:00			1.00
15	ORIFICE	23.47	0	01:59			1.00
16	ORIFICE	58.80	0	01:59			1.00
28	ORIFICE	30.06	0	01:59			1.00

****
Flow Classification Summary
****

Conduit	Adjusted /Actual Length	Fraction of Time in Flow Class: Dry	Up Dry	Down Dry	Sub Crit	Sup Crit	Up Crit	Down Crit	Norm Ltd	Inlet Ctrl
3	1.00	0.00	0.00	0.00	1.00	0.00	0.00	0.00	0.00	0.00
4	1.00	0.00	0.00	0.00	1.00	0.00	0.00	0.00	0.00	0.00
5	1.00	0.00	0.00	0.00	0.75	0.01	0.00	0.23	0.76	0.00
6	1.00	0.00	0.00	0.00	1.00	0.00	0.00	0.00	0.10	0.00
7	1.00	0.00	0.00	0.00	0.78	0.00	0.00	0.22	0.74	0.00

8	1.00	0.00	0.00	0.00	0.06	0.00	0.00	0.94	0.00
0.00									
9	1.00	0.00	0.00	0.00	0.05	0.00	0.00	0.95	0.00
0.00									
10	1.00	0.00	0.00	0.00	0.03	0.00	0.00	0.97	0.02
0.00									
11	1.00	0.00	0.00	0.00	0.02	0.00	0.00	0.98	0.00
0.00									
17	1.00	0.00	0.00	0.00	0.04	0.00	0.00	0.96	0.04
0.00									
18	1.00	0.00	0.00	0.00	0.00	0.02	0.00	0.98	0.01
0.00									
19	1.00	0.96	0.03	0.00	0.01	0.00	0.00	0.00	0.92
0.00									
20	1.00	0.00	0.98	0.00	0.02	0.00	0.00	0.00	0.92
0.00									
21	1.00	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00
0.00									
22	1.00	0.00	0.00	0.00	0.02	0.00	0.00	0.98	0.02
0.00									
23	1.00	0.98	0.00	0.00	0.00	0.01	0.00	0.01	0.01
0.00									
24	1.00	0.98	0.01	0.00	0.01	0.00	0.00	0.00	0.92
0.00									
25	1.00	0.98	0.01	0.00	0.02	0.00	0.00	0.00	0.92
0.00									
26	1.00	0.97	0.01	0.00	0.02	0.00	0.00	0.00	0.92
0.00									
27	1.00	0.98	0.00	0.00	0.00	0.02	0.00	0.00	0.01
0.00									

****
Conduit Surcharge Summary
****

Conduit	Hours Full: Both Ends	Hours Full: Upstream	Hours Full: Dnstream	Hours Above Full Normal Flow	Hours Capacity Limited
3	23.98	23.98	23.98	0.01	0.41
4	0.26	0.39	0.26	0.01	0.26
5	0.01	0.01	0.19	0.01	0.01
6	0.32	0.32	0.39	0.01	0.22
7	0.29	0.33	0.29	0.01	0.29
8	0.27	0.27	0.31	0.01	0.11
9	0.23	0.23	0.25	0.01	0.01
10	0.01	0.01	0.21	0.01	0.01
11	0.23	0.23	0.27	0.01	0.22

17	0.01	0.01	0.09	0.01	0.01
19	0.01	0.01	0.09	0.01	0.01

Analysis begun on: Fri Oct 04 15:13:28 2019
Analysis ended on: Fri Oct 04 15:13:30 2019
Total elapsed time: 00:00:02

```
[TITLE]
;;Project Title/Notes

[OPTIONS]
;;Option             Value
FLOW_UNITS           LPS
INFILTRATION         HORTON
FLOW_ROUTING         DYNWAVE
LINK_OFFSETS         ELEVATION
MIN_SLOPE            0
ALLOW_PONDING        YES
SKIP_STEADY_STATE    NO

START_DATE           01/01/2000
START_TIME           00:01:00
REPORT_START_DATE    01/01/2000
REPORT_START_TIME    00:01:00
END_DATE             01/02/2000
END_TIME             00:00:00
SWEEP_START          01/01
SWEEP_END            12/31
DRY_DAYS             0
REPORT_STEP          00:01:00
WET_STEP             00:01:00
DRY_STEP             00:01:00
ROUTING_STEP         0:00:02

INERTIAL_DAMPING     PARTIAL
NORMAL_FLOW_LIMITED  BOTH
FORCE_MAIN_EQUATION  H-W
VARIABLE_STEP        0.75
LENGTHENING_STEP     0
MIN_SURFAREA         1.14
MAX_TRIALS           8
HEAD_TOLERANCE       0.0015
SYS_FLOW_TOL         5
LAT_FLOW_TOL         5
MINIMUM_STEP         0.5
THREADS              1

[FILES]
;;Interfacing Files
SAVE HOTSTART "post.hsf"
USE HOTSTART "post.hsf"

[EVAPORATION]
;;Data Source    Parameters
;;-------------- ----------------
CONSTANT         0.0
DRY_ONLY         NO
```

```
[RAINGAGES]
;;Name           Format    Interval SCF      Source
;;-------------- --------- ------ ------ ----------
1                INTENSITY 0:10     1.0      TIMESERIES CH6H100

[SUBCATCHMENTS]
;;Name           Rain Gage        Outlet           Area     %Imperv  Width    %Slope
  CurbLen  SnowPack
;;-------------- ---------------- ---------------- -------- -------- --------
-------- -------- ----------------
103B-1           1                OVRLND102        0.22     86       44       0.5
  0
103A-1           1                CB103A           0.05     86       20       0.5
  0
103B-2           1                CB103B           0.07     86       39       1
  0
CB104A-1         1                OVRLN101         0.19     86       46       0.5
  0
104A-2           1                CB104B           0.22     86       39       0.5
  0
105B-1           1                CB105B           0.04     86       24       1.5
  0
108A-1           1                OVERLAND106      0.24     86       171      0.5
  0
107C-1           1                CB107C           0.13     86       37       2
  0
107B-1           1                CB107B           0.13     86       37       1
  0
107A-1           1                CB107A           0.11     86       31       0.7
  0

[SUBAREAS]
;;Subcatchment   N-Imperv   N-Perv     S-Imperv   S-Perv     PctZero    RouteTo
PctRouted
;;-------------- ---------- ---------- ---------- ---------- ---------- ----------
----------
103B-1           0.013      0.25       1.57       4.67       0          OUTLET
103A-1           0.013      0.25       1.57       4.67       0          OUTLET
103B-2           0.013      0.25       1.57       4.67       0          OUTLET
CB104A-1         0.013      0.25       1.57       4.67       0          OUTLET
104A-2           0.013      0.25       1.57       4.67       0          OUTLET
105B-1           0.013      0.25       1.57       4.67       0          OUTLET
108A-1           0.013      0.25       1.57       4.67       0          OUTLET
107C-1           0.013      0.25       1.57       4.67       0          OUTLET
107B-1           0.013      0.25       1.57       4.67       0          OUTLET
107A-1           0.013      0.25       1.57       4.67       0          OUTLET

[INFILTRATION]
;;Subcatchment   MaxRate    MinRate    Decay      DryTime    MaxInfil
```

```
;;-------------- ---------- ---------- ---------- ---------- ----------
103B-1           76.2       13.2       4.14       7          0
103A-1           76.2       13.2       4.14       7          0
103B-2           76.2       13.2       4.14       7          0
CB104A-1         76.2       13.2       4.14       7          0
104A-2           76.2       13.2       4.14       7          0
105B-1           76.2       13.2       4.14       7          0
108A-1           76.2       13.2       4.14       7          0
107C-1           76.2       13.2       4.14       7          0
107B-1           76.2       13.2       4.14       7          0
107A-1           76.2       13.2       4.14       7          0

[JUNCTIONS]
;;Name           Elevation  MaxDepth   InitDepth  SurDepth   Aponded
;;-------------- ---------- ---------- ---------- ---------- ----------
MH109            85         4.41       0          0          0
MH108            85.963     3.677      0          0          0
MH106            86.321     3.629      0          0          0
MH105            86.384     3.396      0          0          0
MH104            86.589     3.401      0          0          0
MH102            86.803     3.247      0          0          0
STM101           87.050     3.2        0          0          0
MH107            87.709     3.221      0          0          0
MH103            87.117     3.273      0          0          0
CB107A           88.89      1.63       0          0          0
CB107B           88.54      1.59       0          0          0
CB108A           87.98      1.45       0          0          0
CB107C           88.14      1.50       0          0          0
CB105B           88.23      1.67       0          0          0
CB104B           87.77      2.02       0          0          0
CB103B           88.48      1.72       0          0          0
CB103A           88.72      1.62       0          0          0
OVRLN101         90.15      0.34       0          0          0
OVRLND102        90.85      0.34       0          0          0
OVERLAND106      89.71      0.34       0          0          0

[OUTFALLS]
;;Name           Elevation  Type       Stage Data       Gated    Route To
;;-------------- ---------- ---------- ---------------- -------- ----------------
MINOR-OUTLET     84.95      FIXED      86.38            NO
OVERLANDFLOWOUT  94.61      FREE                        NO
MAJOR-OUTLET     89.12      FREE                        NO

[CONDUITS]
;;Name           From Node        To Node          Length     Roughness  InOffset
OutOffset  InitFlow   MaxFlow
;;-------------- ---------------- ---------------- ---------- ---------- ----------
---------- ---------- ----------
3                MINOR-OUTLET     MH109            13.8       0.013      *
*          0          0
```

```
4               MH109           MH108           30.35      0.013      85.860
*          0          0
5               MH108           MH107           112.10     0.013      86.364
*          0          0
6               MH108           MH106           41.55      0.013      86.113
*          0          0
7               MH106           MH105           6.5        0.013      86.351
*          0          0
8               MH105           MH104           35         0.013      86.414
*          0          0
9               MH104           MH102           5.4        0.013      86.776
*          0          0
10              MH102           STM101          43.4       0.013      86.833
*          0          0
11              MH104           MH103           43.1       0.013      86.739
*          0          0
17              OVRLN101        CB104B          91         0.013      *
89.57      0          0
18              OVRLND102       CB103A          56.46      0.013      *
90.44      0          0
19              CB103B          CB104B          60         0.013      89.98
89.57      0          0
20              CB104B          OVERLAND106     14         0.013      89.83
*          0          0
21              CB105B          OVERLAND106     10         0.013      89.90
*          0          0
22              OVERLAND106     CB108A          62         0.013      *
89.12      0          0
23              CB103A          CB103B          10         0.013      90.47
89.98      0          0
24              CB107A          CB107B          37         0.013      90.53
90.03      0          0
25              CB107B          CB107C          37         0.013      90.13
89.51      0          0
26              CB107C          CB108A          37         0.013      89.64
89.12      0          0
27              CB108A          MAJOR-OUTLET    15         0.013      89.22
89.12      0          0

[ORIFICES]
;;Name           From Node       To Node         Type         Offset     Qcoeff
 Gated    CloseTime
;;-------------- ---------------- ---------------- ------------ ----------
---------- -------- ----------
1               CB104B          MH104           SIDE         *          0.61
 NO       0
2               CB107A          MH107           SIDE         *          0.61
 NO       0
12              CB107B          MH107           SIDE         *          0.61
 NO       0
```

```
13               CB107C           MH107            SIDE         *          0.61
 NO       0
14               CB108A           MH108            SIDE         *          0.61
 NO       0
15               CB105B           MH105            SIDE         *          0.61
 NO       0
16               CB103B           MH103            SIDE         *          0.61
 NO       0
28               CB103A           MH103            SIDE         *          0.65
 NO       0

[XSECTIONS]
;;Link            Shape        Geom1            Geom2      Geom3      Geom4
Barrels    Culvert
;;--------------- ------------ ---------------- ---------- ---------- ----------
---------- ----------
3                CIRCULAR     0.60             0          0          0          1

4                CIRCULAR     0.60             0          0          0          1

5                CIRCULAR     0.30             0          0          0          1

6                CIRCULAR     0.45             0          0          0          1

7                CIRCULAR     0.45             0          0          0          1

8                CIRCULAR     0.45             0          0          0          1

9                CIRCULAR     0.3              0          0          0          1

10               CIRCULAR     0.3              0          0          0          1

11               CIRCULAR     0.3              0          0          0          1

17               IRREGULAR    OVERLAND         0          0          0          1

18               IRREGULAR    OVERLAND         0          0          0          1

19               IRREGULAR    OVERLAND         0          0          0          1

20               IRREGULAR    OVERLAND         0          0          0          1

21               RECT_OPEN    0.3              1          0          0          1

22               IRREGULAR    OVERLAND         0          0          0          1

23               IRREGULAR    OVERLAND         0          0          0          1

24               IRREGULAR    OVERLAND         0          0          0          1
```

```
25               IRREGULAR    OVERLAND         0          0          0          1

26               IRREGULAR    OVERLAND         0          0          0          1

27               IRREGULAR    OVERLAND         0          0          0          1

1                CIRCULAR     0.15             0          0          0
2                CIRCULAR     0.1              0          0          0
12               CIRCULAR     0.1              0          0          0
13               CIRCULAR     0.10             0          0          0
14               CIRCULAR     0.15             0          0          0
15               CIRCULAR     0.1              0          0          0
16               CIRCULAR     0.15             0          0          0
28               CIRCULAR     0.10             0          0          0

[TRANSECTS]
;;Transect Data in HEC-2 format
;
NC 0.013    0.013    0.013
X1 OVERLAND          4        0.0      0.0      0.0      0.0      0.0      0.0
0.0
GR 100      0        99.85    0.1      99.661   6.3      99.81    6.31

[LOSSES]
;;Link           Kentry     Kexit      Kavg       Flap Gate  Seepage
;;-------------- ---------- ---------- ---------- ---------- ----------
3                0          1          0          NO         0
4                1.3        1          0          NO         0
5                0          1          0          NO         0
6                0.4        1          0          NO         0
7                0.40       1          0          NO         0
8                0.4        1          0          NO         0
9                0.4        1          0          NO         0
10               0          1          0          NO         0
11               0          1          0          NO         0

[CURVES]
;;Name           Type       X-Value    Y-Value
;;-------------- ---------- ---------- ----------
CB103b-Capture   Storage    0          0
CB103b-Capture              0.15       409
CB103b-Capture              0.20       409
;
CB103B-UG-Storage Storage    0          0
CB103B-UG-Storage            0.07       37.7
CB103B-UG-Storage            1.21       37.7
CB103B-UG-Storage            1.2101     0
CB103B-UG-Storage            2.41       0
;
CB103a-Capture   Storage    0          0
```

```
CB103a-Capture              0.15       448
CB103a-Capture              0.20       448
;
CB103a-UG-Storage Storage    0          0
CB103a-UG-Storage            0.07       31
CB103a-UG-Storage            1.21       31
CB103a-UG-Storage            1.2101     0
CB103a-UG-Storage            2.41       0
;
CB102-Capture    Storage    0          0
CB102-Capture               0.12       74
CB102-Capture               0.17       74
;
CB102-UG-Storage Storage    0          0
CB102-UG-Storage            0.07       25
CB102-UG-Storage            1.21       25
CB102-UG-Storage            1.2101     0
CB102-UG-Storage            2.17       0

[TIMESERIES]
;;Name           Date       Time       Value
;;-------------- ---------- ---------- ----------
CH6H100          FILE "P:\General Administrative\5 - DSEL Templates\Site
Plan\EPASWMM Template\rainfall\CH6H100.dat"
;
CH6H100x         FILE "P:\General Administrative\5 - DSEL Templates\Site
Plan\EPASWMM Template\rainfall\CH6H100x.dat"
;
CH6H002          FILE "P:\General Administrative\5 - DSEL Templates\Site
Plan\EPASWMM Template\rainfall\CH6H002.dat"
;
CH6H005          FILE "P:\General Administrative\5 - DSEL Templates\Site
Plan\EPASWMM Template\rainfall\CH6H005.dat"
;
25mm             FILE "P:\General Administrative\5 - DSEL Templates\Site
Plan\EPASWMM Template\rainfall\CH4H25mm.dat"
;
10mm             FILE "Z:\Projects\17-946-Wateridge_Block
15\B_Design\B1_Analysis\B1-4_SWM\Rainfall\CH4H10mm.dat"
;
15mm             FILE "Z:\Projects\17-946-Wateridge_Block
15\B_Design\B1_Analysis\B1-4_SWM\Rainfall\CH4H15mm.dat"

[REPORT]
;;Reporting Options
INPUT      NO
CONTROLS   NO
SUBCATCHMENTS ALL
NODES ALL
LINKS ALL
```

[TAGS]

[MAP]
DIMENSIONS -2500.000 0.000 12500.000 10000.000
Units   None

[COORDINATES]
;;Node   X-Coord   Y-Coord
;;-------------- ------------------ ------------------
MH109   1368.677   7082.291
MH108   2894.675   7082.291
MH106   2909.986   4994.890
MH105   3088.614   4719.291
MH104   4701.374   4035.399
MH102   4910.625   4224.235
STM101   4895.314   6413.710
MH107   8534.231   7087.395
MH103   6788.776   3300.471
CB107A   6936.782   7414.030
CB107B   5130.083   7408.926
CB108A   1674.898   7414.030
CB107C   3328.487   7408.926
CB105B   2440.448   4632.529
CB104B   3374.420   4928.542
CB103B   5946.670   3749.594
CB103A   7023.545   3570.965
OVRLN101   5033.113   6250.393
OVRLND102   7243.002   6418.814
OVERLAND106   2797.705   5142.896
MINOR-OUTLET   684.785   7087.395
OVERLANDFLOWOUT 6459.333   6978.922
MAJOR-OUTLET   674.578   7250.712

[VERTICES]
;;Link   X-Coord   Y-Coord
;;-------------- ------------------ ------------------
17   5303.607   4729.499
17   4726.893   3866.978
18   7595.156   4744.810
19   4599.301   3800.631
20   3165.169   4994.890
21   2736.461   4918.334
21   2792.601   5117.378
22   2761.979   6903.662
23   6717.324   3397.441
24   6094.676   7470.170
25   4058.312   7546.725
26   2210.783   7556.932
27   1480.958   7255.816


```
[Polygons]
;;Subcatchment   X-Coord            Y-Coord
;;-------------- ------------------ ------------------
103B-1           7508.393           4421.577
103B-1           7217.484           4814.560
103B-1           6941.886           4401.163
103A-1           7227.691           3438.270
103A-1           7850.339           3438.270
103A-1           7513.497           3821.045
103A-1           7191.966           3443.374
103B-2           5788.456           2938.110
103B-2           6523.385           2861.555
103B-2           6186.543           3315.782
103B-2           5798.664           2984.043
CB104A-1         6104.884           5209.244
CB104A-1         6084.469           5255.177
CB104A-1         5762.938           5760.440
CB104A-1         5477.132           5224.555
104A-2           2955.919           4117.058
104A-2           3849.061           4045.607
104A-2           3461.182           4479.419
104A-2           2935.504           4091.540
105B-1           1649.379           4076.229
105B-1           2353.686           4096.643
105B-1           1981.118           4438.589
105B-1           1618.757           4009.881
108A-1           3721.470           5949.276
108A-1           3466.286           6423.917
108A-1           3078.407           5939.069
107C-1           4221.629           7699.835
107C-1           3833.750           8235.721
107C-1           3297.865           7684.524
107B-1           6232.476           7791.701
107B-1           5834.389           8337.794
107B-1           5364.852           7786.598
107A-1           8166.767           7755.975
107A-1           7687.022           8363.312
107A-1           7202.173           7786.598

[SYMBOLS]
;;Gage           X-Coord            Y-Coord
;;-------------- ------------------ ------------------
1                -682.998           7689.628


[BACKDROP]
FILE       "Z:\Projects\17-946-Wateridge_Block
15\B_Design\B1_Analysis\B1-4_SWM\2019-09-26_946_spa_ggg-SWM-2.bmp"
DIMENSIONS -2500.000 0.000 12500.000 10000.000
```

```
[PROFILES]
;;Name           Links
;;-------------- ----------
"                " 14
```

Design Chart 4.19: Inlet Capacity at Road Sag



DRAWINGS / FIGURES



SITE STATISTICS AND DEVELOPMENT DATA


SITE AREA	19,588.25m² (1.96 ha)
PAVED AREA	5,426.98m² (28%)
LANDSCAPED AREA	5,829.33m² (30%)
TOTAL BUILDING COVERAGE	8,331.94m² (42%)
TOTAL GROSS FLOOR AREA	22,746.76m²
STACKED TOWNS TYPE A UPPER MODEL (34@114m²)	3,876m²
STACKED TOWNS TYPE B LOWER MODEL (34@85m²)	2,890m²
STACKED TOWNS TYPE C UPPER MODEL (24@116.93m²)	2,806.32m²
STACKED TOWNS TYPE D LOWER MODEL (24@87.26m²)	2,094.24m²
STACKED TOWNS TYPE E UPPER MODEL (4@117.20m²)	468.80m²
STACKED TOWNS TYPE F LOWER MODEL (4@89.97m²)	359.88m²
B2B TOWNHOUSE TYPE A MODEL (20@126.72m²)	2,525.20m²
B2B TOWNHOUSE TYPE B MODEL (6@139.82m²)	838.92m²
B2B TOWNHOUSE TYPE C MODEL (14@159.24m²)	2,229.36m²
B2B TOWNHOUSE TYPE D MODEL (2@172.06m²)	344.12m²
B2B TOWNHOUSE TYPE F MODEL (26@165.92m²)	4,313.92m²
HYDRO VAULT (1)	116m²
DENSITY (UPH)	98 UPH
ZONE CATEGORY	R4Y[2456]

DWELLING BLOCK	DWELLING TYPE	GROUND FLOOR AREA (m2)	UNITS
BLOCK 1	STACKED TOWNS	502.57	20
BLOCK 2	STACKED TOWNS	500.72	20
BLOCK 3	STACKED TOWNS	500.72	20
BLOCK 4	STACKED TOWNS	502.57	20
BLOCK 5	STACKED TOWNS	401.53	16
BLOCK 6	STACKED TOWNS	399.93	16
BLOCK 7	STACKED TOWNS	301.14	12
BLOCK 8	BACK TO BACK TOWNHOUSES	571.00	10
BLOCK 9	BACK TO BACK TOWNHOUSES	591.81	10
BLOCK 10	BACK TO BACK TOWNHOUSES	575.07	10
BLOCK 11	BACK TO BACK TOWNHOUSES	480.28	8
BLOCK 12	BACK TO BACK TOWNHOUSES	469.87	8
BLOCK 13	BACK TO BACK TOWNHOUSES	571.00	10
BLOCK 14	BACK TO BACK TOWNHOUSES	689.68	12
	TOTAL	7,057.89	192

SECTION	ZONE PROVISION - PLANNED UNIT DEVELOPMENT	REQUIRED	PROPOSED
162A (Table)	MIN. LOT WIDTH (m)	N/A	N/A
162A (Table)	MIN. LOT AREA (m²)	1,400m²	19,588m²
162A (Table)	MAX. BUILDING HEIGHT (m)	11.0m	10.0m
162A (Table)	MIN. FRONT YARD SETBACK (m)	3.0m	3.05m
162A (Table)	MIN. CORNER SIDE YARD SETBACK (m)	3.0m	3.05m
57 (2)	MIN. CORNER SIDE YARD SIGHT TRIANGLE SETBACK (m)	0.5m	2.07m
162A (Table)	MIN. REAR YARD SETBACK (m)	3.0m	3.05m
162A (Table)	MIN. INTERIOR YARD SETBACK (m)	3.0m	N/A
101 (Table)	RESIDENT PARKING - B2B TOWNS (68)	51 (68@0.75/unit)	68
	- STACKED TOWNS (124) 5.2m x 2.6m 5.2m x 2.4m	62 (124@0.5/unit)	124 (124@1/unit): 99 (Regular stalls) 25 (Small car stalls)*
2018-124	VISITOR PARKING - B2B TOWNS	0	0
	- STACKED TOWNS	0	5
111A (Table)	MIN. BICYCLE PARKING (STACKED TOWNS)	62 (124@0.5/unit)	62
131 (Table)	MIN. WIDTH OF PRIVATE WAY (m)	6.0m	6.0m
2018-124	MIN. SETBACK OF ANY WALL OF A RESIDENTIAL BUILDING TO A PRIVATE WAY (m)	0.2m	1.3m
2018-124	MIN. SETBACK OF GARAGE DOOR TO PRIVATE WAY (m)	1.0m	5.2m
131 (Table)	MIN. SEPARATION DISTANCE BETWEEN BUILDINGS WITHIN A PLANNED UNIT DEVELOPMENT (m)	1.2m	3.0m
137 (Table)(7)	MIN. STACKED TOTAL AMENITY AREA (6m² per unit)	744m²	1,989m²
	MIN. B2B TOTAL AMENITY AREA	N/A	N/A
137 (Table)(7)	MIN. OF 50% AS COMMUNAL, AT LEAST 1 AGGREGATED AREA MIN. 54m²	372m²	373m²

• Section 106 (3a)- Up to 40% of the required parking spaces may be reduced in size to 2.4m x 4.6m for small cars only. Proposed 25 spaces for small car parking.

SECTION	ADDITIONAL PROVISIONS	REQUIRED	PROPOSED
65	PERMITTED PROJECTIONS INTO YARDS:		
65 (6)	COVERED OR UNCOVERED BALCONY, PORCH, DECK (m)	2.0m (Max)	1.75m
		>1.0m to lot line	1.25m
65 (5)	FIRE ESCAPES, OPEN STAIRWAYS, WINDOW WELLS (m)	>0.6m to lot line	1.71m
106 (1)(a)	MIN. PERPENDICULAR PARKING SPACE SIZE (m)	2.6m x 5.2m	2.6m x 5.2m
106 (1)(b)	MIN. PARALLEL PARKING SPACE SIZE (m)	2.6m x 6.7m	2.6m x 6.7m
106 (3)(a)	MIN. REDUCED PARKING SPACE SIZE (m)	2.4m x 4.6m	2.4m x 5.2m
107 (2)	MIN. DRIVEWAY WIDTH TO GARAGE (m)	2.6m	3.2m
109 (3)(b)	MAX. WALKWAY WIDTH PERMITTED IN YARD (m)	1.8m	1.8m
110 (Table)	MIN. LANDSCAPED AREA SURROUNDING PARKING LOT-ABUTTING A STREET (m)	3.0m	3.0m
111B (Table)	MIN. BICYCLE PARKING SPACE DIMENSIONS (m)	Width: 0.6m Length: 1.8m	0.6m 1.8m
111 (9)	MIN. BICYCLE PARKING SPACE ACCESS WIDTH AISLE (m)	1.5m	1.5m
2018-124	MAX. PROJECTION HEIGHT (m)	3.2m	0.96m
91	UTILITY INSTALLATION MIN. CORNER SIDE YARD SETBACK (m)	0.5m	1.95m



SCALE 1:400 (0 4 8 12 16 20 24)

LEGEND

- BACK TO BACK TOWNHOUSE
- STACKED TOWNHOUSE
- PATHWAY (PAVERS)
- WALKWAY TO ENTRY (PAVERS)
- CROSSWALK (PAVERS)
- RAISED CROSSWALK
- DRIVEWAY (PAVERS)
- DRIVEWAY (ASPHALT)
- CURB (0.2m)
- MOUNTABLE CURB
- DEPRESSED CURB
- PORCH
- PROJECTION (STAIRS)
- WINDOW WELL
- TWO FRAMED WINDOW WELL
- BALCONY
- S.S SNOW STORAGE AREA
- L/A LANDSCAPED AREA
- BLOCK BOUNDARY
- HYDRO METERS
- GAS METERS
- GARAGE
- R RISERS
- REDUCED WIDTH PARKING STALLS
- CONCRETE SIDEWALK
- ENTRANCE
- # UNIT NUMBER
- BENCH
- R.W.L RAIN WATER LEADER
- HYD FIRE HYDRANT
- CMB CANADA POST MAIL BOX
- LIGHT DUTY PAVING
- R12 STOP SIGN
- BIKE RACKS
- BIKE SHELTER
- V VISITOR PARKING
- EV ELECTRIC VEHICLE PARKING
- TREE GRATE
- ENTRY FEATURE
- ART FEATURE
- TACTILE WALKING SURFACE INDICATOR
- LIGHTING (R=0.5m)
- POLE MOUNT LIGHT
- BOLLARD LIGHT
- WASTE STORAGE 1.2m HEIGHT
- STREET TREES

19/12/19	Insert new street tree locations	SP
21/11/19	New building templates and shift buildings 4.5m away from tree	SP
05/11/19	Insert bike shelters	SP
04/10/19	Issued for Site Plan Third Submission	SP
26/09/19	General Revisions- fire hydrant and light poles	SP
16/09/19	General Revisions- 2' paver apron along driveways	SP
10/09/19	Insert landscape plan and meter locations	SP
09/09/19	General Revisions- reduced size parking stalls	SP
03/09/19	General Revisions- Update window wells and statistic chart	SP
06/08/19	General Revisions- Update labels BVHE to BVHF	SP
09/07/19	Landscaped area summary	SP
26/06/19	Issued for Site Plan Second Submission	CR
19/06/19	General Revisions- Update with new landscape plan	SP
04/06/19	General Revisions- Update site statistic chart	SP
27/05/19	General Revisions- Update Block 9 & 6 and hydro vault	SP
10/05/19	General Revisions- Update Block 10	SP
16/04/19	General Revisions- Add light duty paving b/w stacked TH	SP
04/04/19	General Revisions- New street names	SP
31/01/19	Issue for Site Plan Amendment Application	SP
DATE (D.M.Y)	REVISION	BY

GENERAL NOTES

1. DO NOT SCALE DRAWINGS FOR PRINT.
2. THIS DRAWING IS THE EXCLUSIVE PROPERTY OF KORSIAK URBAN PLANNING AND MATTAMY HOMES. COPYRIGHT RESERVED.
3. SITE PLAN PREPARED IN ACCORDANCE WITH PLAN 4M-1581AND PLAN 4R-30196, PREPARED BY ANNS O'SULLIVAN, VOLLEBEKK LTD.
4. TOWNHOUSE DWELLING UNITS ARE DESIGNED TO ACCOMMODATE CURBSIDE GARBAGE PICK-UP.
5. STACKED TOWNS ARE DESIGNED TO ACCOMMODATE BIN-PICKUP (MOLOK).
6. WALKWAYS AND CURBS TO BE TIED INTO PUBLIC ROW WHERE APPLICABLE.
7. REFERENCES CITY OF OTTAWA T.W.S.I. DETAIL SC7.3
8. TO BE RAISED 8cm PER CITY OF OTTAWA TYPICAL RAISED CROSSWALK STANDARD DRAWING R15.

PROJECT TEAM

SITE PLAN DESIGN: KORSIAK Urban Planning
LANDSCAPE ARCHITECTURE: NAK design strategies
MECHANICAL/ ELECTRICAL: LRJ
PLANNING: Stantec
TRANSPORTATION: NOVATECH Engineers, Planners & Landscape Architects
ARCHITECTURE: Q4A
NOISE: VALCOUSTICS Canada Ltd. consulting acoustical engineers
ENVIRONMENTAL: KILGOUR & Associates
CIVIL ENGINEER: DSEL david schaeffer engineering ltd
GEOTECHNICAL & STRUCTURAL: paterson group consulting engineers

mattamyHOMES

WATERIDGE VILLAGE: PHASE 1B
245 SQUADRON CRES.
BLOCK 15
PART OF LOT 22
CONCESSION 1 (OTTAWA FRONT)
GEOGRAPHIC TOWNSHIP OF GLOUCESTER
REGISTERED PLAN 4M-1559
CITY OF OTTAWA

TITLE: BLOCK 15 SITE PLAN

DATE: December 19, 2019	DRAWN BY: SP CHECKED BY: CR		DRAWING NO. A1
FILE NO.: D07-12-19-0020			
JOB NO.: Mattamy - Wateridge			

D07-12-19-0020

DWG #17978

X:\Korsiak & Company\MATTAMY\Ottawa\Wateridge\Site Plan\Dec 19\Block 15 site plan 2019 Dec 19.dwg

CURVE SCHEDULE

NUM.	LOCATION	RADIUS	ARC	CHORD	BEARING
C1	chemin Hemlock Road	60.00	22.56	22.42	N 79°13'50" E
C2	croissant Squadron Crescent	22.00	25.36	23.98	N 33°01'50" W

Lots 1, 2, 3, 4 and 5, Blocks 6, 7 and 8, part of Block 9, Blocks 10, 11, 12, 13, 14 and 15, part of Block 16, Blocks 17 to 28, both inclusive, Block 31, chemin Cobb's Road, chemin Hemlock Road, rue Bareille-Snow Street, rue Michael Stoqua Street, rue Moses Tennisco Street, croissant Squadron Crescent and part of chemin Wanaki Road are subject to easement Inst. OC1771382.

Part of Block 20 and part of chemin Hemlock Road are subject to easement Inst. OC1756037.

Lots 1, 2, 3, 4 and 5, Blocks 6, 7 and 8, part of Blocks 9, 10, and 11, Blocks 12, 13 and 14, part of Blocks 15 and 16, Block 17, part of Blocks 18, 19, 20, and 21, Block 22, part of Blocks 23, 24, 25 and 26, Blocks 27 and 28, part of chemin Cobb's Road, part of chemin Hemlock Road, part of rue Bareille-Snow Street, part of rue Michael Stoqua Street, part of rue Moses Tennisco Street, part of croissant Squadron Crescent and part of chemin Wanaki Road are subject to easement Inst. OC1755039.

Part of Block 10 is subject to easement Inst. OC1772805.

Part of Blocks 9 and 16 are subject to easement Inst. OC1772902.

Block 31 and Part of Blocks 10, 11, 15, 17, 18, 19, 21, 23, 24, 25, 26, 27 and part of chemin Cobb's Road, part of chemin Hemlock Road, part of rue Bareille-Snow Street, part of rue Michael Stoqua Street, part of rue Moses Tennisco Street, part of croissant Squadron Crescent and part of chemin Wanaki Road are subject to easement Inst. OC1874459.

APPROVED UNDER SECTION 51 OF THE PLANNING ACT BY THE CITY OF OTTAWA.

THIS 16th DAY OF March, 2017

STEPHEN WILLIS, GENERAL MANAGER PLANNING, INFRASTRUCTURE AND ECONOMIC DEVELOPMENT DEPARTMENT CITY OF OTTAWA

PLAN 4M- 1581

I CERTIFY THAT THIS PLAN IS REGISTERED IN THE LAND REGISTRY OFFICE FOR THE LAND TITLES DIVISION OF OTTAWA-CARLETON NO. 4 AT 15:55 O'CLOCK ON THE 17 DAY OF March 2017 AND ENTERED IN THE PARCEL REGISTER FOR PROPERTY IDENTIFIERS 04273-0561, 04273-0562, 04273-0563, 04273-0564, 04273-0565, 04273-0566, 04273-0567, 04273-0568, 04273-0569, 04273-0570, 04273-0580, 04273-0581, 04273-0586 and 04273-0587 AND THE REQUIRED CONSENTS ARE REGISTERED AS PLAN DOCUMENT NO. OC1874890

Representative for LAND REGISTRAR

This plan comprises all of the land identified by PIN's 04273-0561, 04273-0562, 04273-0563, 04273-0564, 04273-0565, 04273-0566, 04273-0567, 04273-0568, 04273-0569, 04273-0570, 04273-0580, 04273-0586 and 04273-0587 and part of the land identified by PIN 04273-0581.

PLAN OF SUBDIVISION OF

PART OF LOTS 21, 22 And 23
CONCESSION 1 (OTTAWA FRONT)
Geographic Township of Gloucester
And
BLOCKS 118, 119, 120, 121, 122, 123, 124, 125, 126 And 127
REGISTERED PLAN 4M-1559
CITY OF OTTAWA

Surveyed by Annis , O'Sullivan , Vollebekk Ltd.

Scale 1 : 1250

50 37.5 25 12.5 0 25 50 Metres

Metric
DISTANCES AND COORDINATES SHOWN ON THIS PLAN ARE IN METRES AND CAN BE CONVERTED TO FEET BY DIVIDING BY 0.3048.

SURVEYOR'S CERTIFICATE

I CERTIFY THAT :

1. This survey and plan are correct and in accordance with the Surveys Act, the Surveyors Act and the Land Titles Act and the regulations made under them.
2. The survey was completed on the 22nd day of February, 2017.

Feb 22, 2017 — Date

E. H. Herweyer — Ontario Land Surveyor

OWNER'S CERTIFICATE

THIS IS TO CERTIFY THAT :

1. Lots 1, 2, 3, 4, 5, Blocks 6 to 26, both inclusive, Blocks 29, 30, the Streets, namely, rue Bareille-Snow Street, rue Michael Stoqua Street, rue Moses Tennisco Street, croissant Squadron Crescent, chemin Cobb's Road, chemin Hemlock Road, avenue Provender Avenue and chemin Wanaki Road, the Street Widenings, namely, Blocks 33 and 34 and the Reserves, namely, Blocks 27, 28, 31 and 32 have been laid out in accordance with our instructions.
2. The Streets and Street Widenings are dedicated as public highways.

Dated the 16th day of March, 2017

Rodger Martin, Vice President, Real Estate Ontario & Atlantic
Canada Lands Company CLC Limited
I have the authority to bind the corporation.

Dated the 16th day of March, 2017

Jean Lachance, Senior Director Real Estate (Ottawa)
Canada Lands Company CLC Limited
I have the authority to bind the corporation.

NOTES AND LEGEND

—○—	denotes	Survey Monument Planted.
—■—	denotes	Survey Monument Found
SSB	-	Standard Iron Bar.
SSIB	-	Short Standard Iron Bar.
CC	-	Cut Cross.
IB	-	Iron Bar.
IBØ	-	Round Iron Bar.
IB	-	Iron Bar.
•	-	Survey Monument (0.3 long)
(WIT)	-	Witness
NT	-	Nontangential
CLF	-	Chain Link Fence
BF	-	Board Fence
R/W	-	Right-of-Way
(AOG)	-	Annis, O'Sullivan, Vollebekk Ltd.
(P1)	-	Registered Plan 4M-1559
(P2)	-	Plan 4R-26142
(P3)	-	Plan 4R-29484
(P4)	-	Plan 4R-29367
(P5)	-	Plan 4R-30067

Distances shown on curved limits are Arc distances unless otherwise noted.

Distances shown on this plan are ground distances and can be converted to grid distances by multiplying by the combined scale factor of 0.999947.

Bearings are grid, derived from the southerly limit of chemin Mikinak Road, shown to be N90°00'00" W on Registered Plan 4M-1559, and are referred to the Central Meridian of MTM Zone 9 (76°30' West Longitude) NAD-83 (original).

Coordinates are derived from Can-Net 2016 Real Time Network GPS observations referenced to Specified Control Points 01919680105 and 01983434761, MTM Zone 9 (76°30' West Longitude) NAD-83 (original).

Coordinate values are to urban accuracy in accordance with O. Reg. 216/10.

. 01919834761	Northing	5036178.12	Easting 372436.11
. 01919680146	Northing	5035456.42	Easting 372208.81
. Point A	Northing	5034986.54	Easting 373170.44
. Point B	Northing	5034986.54	Easting 372556.54

Caution: Coordinates cannot, in themselves, be used to re-establish corners or boundaries shown on this plan.

ELEVATION NOTES

1. Elevations are geodetic, referred to City of Ottawa Vertical Bench Mark No. 398 (01919680138), having an elevation of 98.06 metres.

DETAIL "A": SCALE 1:500

DETAIL "B": SCALE 1:500

DETAIL "C": SCALE 1:300

DETAIL "D": SCALE 1:200

ANNIS, O'SULLIVAN, VOLLEBEKK LTD.
14 Concourse Gate, Suite 500
Nepean, Ont. K2E 7S6
Phone: (613) 727-0850 / Fax: (613) 727-1079
Email: Nepean@ravenet.com
Ontario Land Surveyors

Job No. 14702-34 CLC Pt Lts 21-23 CI OF GL Pts IB SUB F

MIKINAK ROAD
DEDICATED BY REGISTEED PLAN 4M-1559
PIN 04273-0579(LT)

CROISSANT SQUADRON CRESCENT
DEDICATED BY REGISTEED PLAN 4M-1581
PIN 04273-0631(LT)

CROISSANT SQUADRON CRESCENT
DEDICATED BY REGISTEED PLAN 4M-1581
PIN 04273-0631(LT)

NORTHWEST CORNER OF BLOCK 15 REGISTERED PLAN 4M-1581

BLOCK 121 (0.30 RESERVE)
SUBJECT TO EASEMENTS AS IN INST. Nos. OC1771382 AND OC1874459

PART 104 PART 11 | PART 103 PART 12 | PART 102 PART 13 | PART 100 PART 14 | PART 101 PART 15

PART 16 PART 89 | PART 90 | PART 18 PART 97 | PART 98 | PART 21 PART 99

PART 87 | PART 88 | PART 1 PART 96 | PART 86 4R-XXXXX

PART 17 PART 82 | PART 84 PART 2 | PART 83 | PART 81 PART 3 | PART 80

PART 1 | PART 7 | PART 39 | PART 44
PART 2 | PART 8 | PART 40 | PART 45
PART 3 | PART 9 | PART 41 | PART 46
PART 4 | PART 10 | PART 42 | PART 47
PART 5 | PART 11 | PART 43 | PART 48
PART 6 | PART 12 | PART 49 | PART 54
PART 71 | PART 72 | PART 50 | PART 55
PART 69 PART 7 | PART 51 | PART 56
PART 52 | PART 57
PART 53 | PART 58
PART 59 | PART 64
PART 60 | PART 65
PART 61 | PART 66
PART 62 | PART 67
PART 63 | PART 68

PART 91 PART 4 | PART 92 | PART 19 | PART 95 | PART 79 | PART 22 | PART 85 | PART 8 | PART 78

BLOCK 15

PART 73 PART 5 | PART 74 | PART 93 | PART 94 | PART 76 | PART 23

PART 70 | PART 18 | PART 19 | PART 20 | PART 21 | PART 22 | PART 27 | PART 28 | PART 29 | PART 30 | PART 35 | PART 36 | PART 37 | PART 38 | PART 10 | PART 75 | PART 77 | PART 34 | PART 33 | PART 32 | PART 31 | PART 26 | PART 25 | PART 24 | PART 23 | PART 17 | PART 16 | PART 15 | PART 14 | PART 13

PART 29 | PART 74

SEE DETAIL 'A'
SEE DETAIL 'B'

REGISTERED PLAN 4M-1581

SUBJECT TO EASEMENTS AS IN OC1877247, OC1877276 AND OC1771382

PART 72 | PART 6

PART 11 | PART 82 PART 17 | PART 91 PART 4 | PART 19 | PART 92 | PART 12 | PART 72 | PART 73 PART 5 | PART 93 | PART 71 PART 6 | PART 74 PART 29 | PART 70 | PART 18

DETAIL 'B' (N.T.S)

PART 6 | PART 69 PART 7 | PART 71 | PART 29 | PART 70

DETAIL 'A' (N.T.S)

SCHEDULE				
PARTS	BLOCK	PLAN	PIN	REMARKS
1				
2				
3				
4				
5				
6				
7				
8				
9				
10				
11				
12				
13				
14				
15				
16				
17				
18				
19				
20				
21				
22				
23				
24				
25				
26				
27				
28				
29				
30				
31				
32				
33				
34				
35				
36				
37				
38				
39				
40				
41				
42				
43				
44				
45				
46				
47				
48				
49	15	4M-1581	04273-0606 (LT)	NONE
50				
51				
52				
53				
54				
55				
56				
57				
58				
59				
60				
61				
62				
63				
64				
65				
66				
67				
68				
69				
70				
71				
72				
73				
74				
75				
76				
77				
78				
79				
80				
81				
82				
83				
84				
85				
86				
87				
88				
89				
90				
91				
92				
93				
94				
95				
96				
97				
98				
99				
100				
101				
102				
103				
104				

PARTS 1 TO 104, INCLUSIVE, ARE SUBJECT TO EASEMENTS AS IN OC1877247, OC1877276 AND OC1771382.

PARTS 100 TO 104, INCLUSIVE, ARE SUBJECT TO EASEMENT AS IN INST. No. OC1874459

I REQUIRE THIS PLAN TO BE DEPOSITED UNDER THE LAND TITLES ACT.

DATE _____

GEORGE ZERVOS
ONTARIO LAND SURVEYOR

PLAN 4R-

RECEIVED AND DEPOSITED

DATE _____

REPRESENTATIVE FOR THE LAND REGISTRAR FOR THE LAND TITLES DIVISION OF OTTAWA-CARLETON (No 4)

PLAN OF SURVEY OF
BLOCK 15
REGISTERED PLAN 4M-1581
CITY OF OTTAWA

SCALE 1 : 250

5 0 5 10 15 metres

J.D. BARNES LIMITED

METRIC DISTANCES AND/OR COORDINATES SHOWN ON THIS PLAN ARE IN METRES AND CAN BE CONVERTED TO FEET BY DIVIDING BY 0.3048.

NOTES

BEARINGS ARE MTM GRID, DERIVED FROM OBSERVED REFERENCE POINTS A AND B, BY REAL TIME NETWORK (RTN) OBSERVATIONS, MTM ZONE 9, NAD83 (ORIGINAL) (2010.0).

DISTANCES ARE GROUND AND CAN BE CONVERTED TO GRID BY MULTIPLYING BY THE COMBINED SCALE FACTOR OF 0.999947.

INTEGRATION DATA

OBSERVED REFERENCE POINTS (ORPs): MTM ZONE 9, NAD83 (ORIGINAL) (2010.0).

COORDINATES TO URBAN ACCURACY PER SECTION 14 (2) OF O.REG 216/10.

POINT ID	EASTING	NORTHING
ORP (A)	372 888.63	5 034 986.44
ORP (B)	373 029.39	5 034 986.44

COORDINATES CANNOT, IN THEMSELVES, BE USED TO RE-ESTABLISH CORNERS OR BOUNDARIES SHOWN ON THIS PLAN.

LEGEND

■	DENOTES	SURVEY MONUMENT FOUND
□	DENOTES	SURVEY MONUMENT SET
SIB	DENOTES	STANDARD IRON BAR
SSIB	DENOTES	SHORT STANDARD IRON BAR
IB	DENOTES	IRON BAR
PB	DENOTES	PLASTIC BAR
WIT	DENOTES	WITNESS
MEAS	DENOTES	MEASURED
JDB	DENOTES	J.D. BARNES LIMITED
N.T.S	DENOTES	NOT TO SCALE

ALL SET SSIB AND PB MONUMENTS WERE USED DUE TO LACK OF OVERBURDEN AND/OR PROXIMITY OF UNDERGROUND UTILITIES IN ACCORDANCE WITH SECTION 11 (4) OF O.REG. 525/91.

SURVEYOR'S CERTIFICATE

I CERTIFY THAT:

1. THIS SURVEY AND PLAN ARE CORRECT AND IN ACCORDANCE WITH THE SURVEYS ACT, THE SURVEYORS ACT AND THE LAND TITLES ACT AND THE REGULATIONS MADE UNDER THEM.
2. THE SURVEY WAS COMPLETED ON 201 .

DATE

PRELIMINARY
GEORGE ZERVOS
ONTARIO LAND SURVEYOR

J.D.BARNES LIMITED
SURVEYING MAPPING GIS
LAND INFORMATION SPECIALISTS
2430 DON REID DRIVE, SUITE 204, OTTAWA, ON K1H 1E1
T: (613) 731-7244 F: (613) 731-8955 www.jdbarnes.com


DRAWN BY:	CHECKED BY:	REFERENCE NO.:
NS	XX	18-10-037-00Ppatl r-plan

FILE: G:\18-10-037\01- Block 15\Drawing\POTL\037-0Ppatl r-plan.dwg

2021-12-15 10:20:29

#17978





LEGEND

- PROPERTY LINE
- PROPOSED STORM MANHOLE
- PROPOSED SANITARY MANHOLE
- PROPOSED CATCH BASIN
- PROPOSED AREA DRAIN (PER CITY STD. S30 & S31)
- PROPOSED AREA DRAIN WITH SOLID GRATE(NYLOPLAST 2818AG___X OR APPROVED EQUIVALENT)
- PROPOSED VALVE BOX
- PROPOSED FIRE HYDRANT
- PROPOSED SIAMESE CONNECTION
- PROPOSED WATERMAIN
- PROPOSED STORM SEWER
- PROPOSED SANITARY SEWER
- PROPOSED PERFORATED SUBDRAIN
- PROPOSED DITCH CENTER
- EXISTING WATERMAIN
- EXISTING SANITARY SEWER
- EXISTING STORM SEWER
- EXISTING GAS MAIN
- PROPOSED GAS MAIN
- PROPOSED ENTRY FEATURE
- PROPOSED ART FEATURE
- RA–1 PROPOSED STOP SIGN
- PEDESTRIAN CROSSWALK
- TWSI (TACTILE WALKING SURFACE INDICATOR)
- CMB PROPOSED COMMUNITY MAILBOX
- HGBCSL PROPOSED UTILITY TRENCH (H–HYDRO, G–GAS, B–BELL, C–CABLE, SL–STREET LIGHT)
- PROPOSED SWITCHGEAR
- PROPOSED TRANSFORMER
- G PROPOSED GAS METER
- M PROPOSED METER CENTER
- PROPOSED HYDRO MANHOLE
- PROPOSED LIGHTING PULPIT
- PROPOSED HYDRO
- PROPOSED STREETLIGHT POLE
- PROPOSED LIGHTING DUCTS
- PROPOSED LANDSCAPED SWALE RIVERSTONE
- PROPOSED SOD
- PROPOSED TREE
- EXISTING TREE
- PROPOSED ROGERS PEDESTAL AND 1.5mX2m EASEMENT
- GRADE LEVEL BELL BOX PROPOSED AND 1x3m EASEMENT

NOTE: THIS COMPOSITE UTILITY PLAN WAS PREPARED FOR COORDINATION PURPOSES ONLY. UTILITY DESIGN PREPARED BY OTHERS.

NOT FOR CONSTRUCTION

SITE SERVICING AND STORMWATER MANAGEMENT STUDY
SERVICING AND STORMWATER MANAGEMENT RECOMMENDATIONS PROVIDED BY DSEL
PROJ. NO. 17–946
DATED FEBRUARY 2019

SITE PLAN INFORMATION
SITE PLAN PROVIDED BY KORSIAK URBAN PLANNING
DATED OCTOBER 04, 2019

HYDRO AND SITE LIGHTING SERVICES
DESIGN PREPARED BY LRL ENGINEERING
PROJ. NO. 170548
DATED OCTOBER 04, 2019

BENCH MARK
ELEVATIONS ARE GEODETIC, REFERRED TO CITY OF OTTAWA VERTICAL BENCHMARK NO. 396
ELEV= 95.06 METERS

NATURAL GAS SERVICING
DESIGN PREPARED BY
PROJ. NO.
DATED REV

ROGERS SERVICES
DESIGN PREPARED BY:
PROJ. NO.
DATED REV

BELL SERVICES
DESIGN PREPARED BY:
PROJ. NO.
DATED REV

LANDSCAPE PLAN
DESIGN PREPARED BY: NAK DESIGN STRATEGIES
PROJ. NO. 17–047 Sub 02
DATE RECEIVED OCTOBER 05, 2019

DRAFT

No.	BY	YY.MM.DD	DESCRIPTION
1	S.L.M.	2019.08.02	ISSUED FOR CIRCULATION #1

PROJECT No. 17-946

REVIEWED BY

COMPOSITE UTILITY PLAN
WATERIDGE - BLOCK 15

© DSEL

MATTAMY HOMES
50 Hines Road, Suite 100
Ottawa, Ontario, K2K 2M5
Tel. (613) 831-5144

DSEL
david schaeffer engineering ltd
SMART SUBDIVISIONS™
120 Iber Road Unit 103
Stittsville, Ontario, K2S 1E9
Tel. (613) 836-0856
Fax. (613) 836-7183
www.DSEL.ca

DRAWN BY:	B.N.C.	CHECKED BY:	S.L.M.	DRAWING NO.	SHEET NO.
DESIGNED BY:	B.N.C.	CHECKED BY:	S.L.M.	CUP-1	1 of 1
SCALE:	1:400	DATE:	FEBRUARY 2019		

D07-12-17-0111


z:\projects\17–946–wateridge_block 15\c_utilities\c2_cup\2019–10–07_946_cup_gas.dwg

REVIEWED BY
DEVELOPMENT REVIEW SERVICES BRANCH

Signed _____

Date _____ 2017

Plan Number _____



No.	REVISIONS	By	Date
14			
13			
12	AS BUILT	J.I.M.	2018:06:15
11	REVISED DITCH INLET LOCATION FOR BLOCKS 15, 18, 22 AND 24	J.I.M.	2018:02:02
10	REVISED CB222C & CB222D LOCATION	J.I.M.	2017:11:13
9	REVISED PER MATTAMY DESIGN FOR BLOCKS 22, 24 AND 15	J.I.M.	2017:09:15
8	ISSUED FOR CONSTRUCTION	J.I.M.	2017:08:02
7	REVISED PER CITY COMMENTS	J.I.M.	2017:06:16
6	REVISED PER MOECC COMMENTS	J.I.M.	2017:06:07
5	ISSUED FOR TENDER	J.I.M.	2017:03:23
4	SUBMISSION FOR MOECC APPROVAL	J.I.M.	2017:02:16
3	SUBMISSION No.3 FOR CITY REVIEW	J.I.M.	2017:01:25
2	SUBMISSION No.2 FOR CITY REVIEW	J.I.M.	2016:11:04
1	SUBMISSION No.1 FOR CITY REVIEW	J.I.M.	2016:07:08

CANADA LANDS COMPANY
SOCIÉTÉ IMMOBILIÈRE DU CANADA
30 Metcalfe Street Suite 601
Ottawa, On K1P 5L4
613 998 7777

IBI GROUP
400 – 333 Preston Street
Ottawa ON K1S 5N4 Canada
tel 613 225 1311 fax 613 225 9868
ibigroup.com

Project Title

WATERIDGE VILLAGE AT ROCKCLIFFE

PHASE 1B

PROFESSIONAL ENGINEER
J. I. MOFFATT
18/06/15
PROVINCE OF ONTARIO

N

Drawing Title

GENERAL PLAN OF SERVICES

Scale: 1 : 750

Design	Date
J.I.M.	MAY 2016
Drawn	**Checked**
M.M.	J.I.M.
Project No.	**Drawing No.**
38298	100D

D07-16-15-0003

#17063

J:\38298-CP\Drawings\Civil\Layouts PH1B\1000_GENERAL PLAN.dwg Layout Name: GENERAL PLAN Plot Style: AIA STANDARD-HALF.CTB Plot Scale: 1:50:1 Plotted At: 6/18/2018 11:56 AM Last Saved By: mmiha Last Saved At: Feb. 2, 16

REVIEWED BY
DEVELOPMENT REVIEW SERVICES BRANCH

Signed _____

Date _____ 2017

Plan Number _____



No.	REVISIONS	By	Date
14			
13			
12			
11	REVISED WATER SERVICE ELEVATION TO BLOCK 29	J.I.M.	2018:04:16
10	ADDED WATER SERVICE TO BLOCK 29	J.I.M.	2018:04:13
9	REVISED WANAKI ROAD WATERMAIN NRC, STA 1+210 TO 1+213	J.I.M.	2018:02:15
8	ISSUED FOR CONSTRUCTION	J.I.M.	2017:08:02
7	REVISED PER CITY COMMENTS	J.I.M.	2017:06:16
6	REVISED PER MOECC COMMENTS	J.I.M.	2017:06:07
5	ISSUED FOR TENDER	J.I.M.	2017:03:23
4	SUBMISSION FOR MOECC APPROVAL	J.I.M.	2017:02:16
3	SUBMISSION No.3 FOR CITY REVIEW	J.I.M.	2017:01:25
2	SUBMISSION No.2 FOR CITY REVIEW	J.I.M.	2016:11:04
1	SUBMISSION No.1 FOR CITY REVIEW	J.I.M.	2016:07:08

CANADA LANDS COMPANY
SOCIÉTÉ IMMOBILIÈRE DU CANADA

30 Metcalfe Street Suite 601
Ottawa, On K1P 5L4
613 998 7777

IBI GROUP
400 – 333 Preston Street
Ottawa ON K1S 5N4 Canada
tel 613 225 1311 fax 613 225 9868
ibigroup.com

Project Title

WATERIDGE VILLAGE AT ROCKCLIFFE

PHASE 1B

LICENSED PROFESSIONAL ENGINEER
J. I. MOFFATT
18/04/16
PROVINCE OF ONTARIO

N

Drawing Title

GENERAL PLAN OF SERVICES


Scale: 1 : 750


Design	Date
J.I.M.	MAY 2016
Drawn: M.M.	Checked: J.I.M.
Project No.: 38298	Drawing No.: 100E


D07-16-15-0003

#17063

\\38298-CPB\acad\wks\5.0 Drawings\Civil\Vistaplots Pln\101\100_GENERAL PLAN.dwg Layout Name: GENERAL PLAN Plot Style: AA_STANDARD-HALF.ctb Plot Scale: 1.00 | Printed At: 4/18/2018 12:24 PM Last Saved By: MatiasKhong Last Saved At: Apr. 15, 18


REFER TO 700 SERIES DRAWINGS FOR DETAILS OF THE STORMWATER MANAGEMENT FACILITY
CONT'D ON DWG 38298-134
CB220B T/G 89.70 RIM=35.0
MH220A
MH220
200ø WATERMAIN
CB220A T/G 89.70 RIM=35.0
MH221
MH221A
MH222
MH222A
CROISSANT SQUADRON CRESCENT
0+480 MATCH LINE


MATCH LINE 0+480
CROISSANT SQUADRON CRESCENT
RUE MOSES TENNISCO STREET
CONT'D ON DWG 38298-136
MH223A
CB222B
CB222A
CB222C
CB222D
MH212
MH212A
MH213
CB213A
CB213B
CB212A
CB212B
MH213A
BLOCK 17
BLOCK 4
MANHOLES AND SERVICES BY OTHERS
CITY FORCES
CAP AND CONNECT TO EXISTING WATERMAIN
220m TEMPORARY DITCH @ 0.50%
105m TEMPORARY DITCH @ 0.50%


PROPOSED ROAD CENTRELINE ELEVATION
EXISTING GROUND
PAVEMENT STRUCTURE
2.4m (TYP)
STM SAFETY PLATFORM @ 87.85
SAN SAFETY PLATFORM @ 87.75
SAN SAFETY PLATFORM @ 87.25
STM SAFETY PLATFORM @ 87.20
200ø WATERMAIN PVC DR18 CL-150
REMOVE CAP AND CONNECT TO EXISTING 200ø WATERMAIN
REMOVE BULKHEAD AND CONNECT TO EXISTING 2400ø STM. PIPE
REMOVE BULKHEAD AND CONNECT TO EXISTING 250ø SAN. PIPE
REMOVE BULKHEAD AND CONNECT TO EXISTING 750ø STM. PIPE
REMOVE 300ø KNOCKOUT AND CONNECT TO EXISTING MANHOLE
CLAY DYKE
FILL AS PER GEOTECHNICAL RECOMMENDATIONS
BH16-19 REFUSAL 82.61
BH16-20 REFUSAL 82.67
BH16-14 REFUSAL 82.86
BH16-11 REFUSAL 83.83

| | | |

GRADING & DRAINAGE
APPROVED


Signed _____

Date _____ 2017

NOTES:

FOR GRADING LEGEND, DETAILS AND CROSS SECTIONS REFER TO DRAWINGS 38298-015 & 38298-016.

THE PROPOSED PARK BLOCK GRADING IS TEMPORARY AND ENSURES THE PROPERTY WILL HAVE POSITIVE DRAINAGE UNTIL THE FINAL PARK GRADING DESIGN IS IMPLEMENTED.



No.	REVISIONS	By	Date
14			
13			
12			
11			
10			
9	REVISED GRADING FOR BLOCKS 15, 18, 22 AND 24	J.I.M.	2018:02:02
8	ISSUED FOR CONSTRUCTION	J.I.M.	2017:08:02
7	REVISED PER CITY COMMENTS	J.I.M.	2017:06:16
6	REVISED PER MOECC COMMENTS	J.I.M.	2017:06:07
5	ISSUED FOR TENDER	J.I.M.	2017:03:23
4	SUBMISSION FOR MOECC APPROVAL	J.I.M.	2017:02:16
3	SUBMISSION No.3 FOR CITY REVIEW	J.I.M.	2017:01:25
2	SUBMISSION No.2 FOR CITY REVIEW	J.I.M.	2016:11:04
1	SUBMISSION No.1 FOR CITY REVIEW	J.I.M.	2016:07:08

CANADA LANDS COMPANY
SOCIÉTÉ IMMOBILIÈRE DU CANADA
30 Metcalfe Street Suite 601
Ottawa, On K1P 5L4
613 998 7777

IBI GROUP
400 – 333 Preston Street
Ottawa ON K1S 5N4 Canada
tel 613 225 1311 fax 613 225 9868
ibigroup.com

Project Title

WATERIDGE VILLAGE AT ROCKCLIFFE

PHASE 1B

PROFESSIONAL ENGINEER
J. I. MOFFATT
18/02/02
PROVINCE OF ONTARIO

N

Drawing Title


GRADING PLAN

Scale: 1 : 500

Design	Date
J.I.M.	MAY 2016
Drawn: M.M.	Checked: J.I.M.
Project No.: 38298	Drawing No.: 210

D07-16-15-0003

#17063



GRADING & DRAINAGE APPROVED

Signed _____

Date _____ 2017

NOTES:

1. FOR GRADING LEGEND, DETAILS AND CROSS SECTIONS REFER TO DRAWINGS 38298-015 & 38298-016

2. THE PROPOSED PARK BLOCK GRADING IS TEMPORARY AND ENSURES THE PROPERTY WILL HAVE POSITIVE DRAINAGE UNTIL THE FINAL PARK GRADING DESIGN IS IMPLEMENTED.

3. TEMPORARY DRAINAGE DITCHES ON FUTURE EMPLOYMENT BLOCKS ARE TO BE REMOVED WHEN THOSE BLOCKS ARE DEVELOPED.



No.	REVISIONS	By	Date
14			
13			
12			
11			
10			
9	REVISED GRADING FOR BLOCKS 15, 16, 22 AND 24	J.I.M.	2018:02:02
8	ISSUED FOR CONSTRUCTION	J.I.M.	2017:08:02
7	REVISED PER CITY COMMENTS	J.I.M.	2017:06:16
6	REVISED PER MOECC COMMENTS	J.I.M.	2017:06:07
5	ISSUED FOR TENDER	J.I.M.	2017:03:23
4	SUBMISSION FOR MOECC APPROVAL	J.I.M.	2017:02:16
3	SUBMISSION No.3 FOR CITY REVIEW	J.I.M.	2017:01:25
2	SUBMISSION No.2 FOR CITY REVIEW	J.I.M.	2016:11:04
1	SUBMISSION No.1 FOR CITY REVIEW	J.I.M.	2016:07:08

CANADA LANDS COMPANY
SOCIÉTÉ IMMOBILIÈRE DU CANADA
30 Metcalfe Street Suite 601
Ottawa, On K1P 5L4
613 998 7777

IBI GROUP
400 – 333 Preston Street
Ottawa ON K1S 5N4 Canada
tel 613 225 1311 fax 613 225 9868
ibigroup.com

Project Title

WATERIDGE VILLAGE AT ROCKCLIFFE

PHASE 1B

LICENSED PROFESSIONAL ENGINEER
J. I. MOFFATT
18/02/02
PROVINCE OF ONTARIO

N

Drawing Title

GRADING PLAN

Scale: 1 : 500

Design	Date
J.I.M.	MAY 2016
Drawn: M.M.	Checked: J.I.M.
Project No.: 38298	Drawing No.: 211

D07-16-15-0003

#17063

C:\38298-GP\Revit\Plots\Drawings\Signed Plots\211 GRADING PLAN.dwg Layout Name: GRADING PLAN Plot Style: AIA STANDARD-FULL.ctb Plot Scale: 1:25.4 Plotted At: 7/20/2018 12:13 PM Last Saved By: mmiha Last Saved At: Feb.

CONT'D ON DWG 38298-210

CONT'D ON DWG 38298-211

CROISSANT SQUADRON CRESCENT

BLOCK 15

BLOCK 16

BLOCK 13

BLOCK 14

BLOCK 10

BLOCK 6

BLOCK 7

BLOCK 8

BLOCK 9

BLOCK 12

BLOCK 11

220m TEMPORARY DITCH @ 0.50%

220m TEMPORARY DITCH @ 0.40%

REMOVE TEMPORARY DRAINAGE DITCH

PERMANENT W/L 88.10m
100 YEAR W/L 89.48m

N

GRADING & DRAINAGE APPROVED

Signed _____

Date _____ 2016

NOTES:

FOR GRADING LEGEND, DETAILS AND CROSS SECTIONS REFER TO DRAWINGS 38298-015 & 38298-016.

THE PROPOSED PARK BLOCK GRADING IS TEMPORARY AND ENSURES THE PROPERTY WILL HAVE POSITIVE DRAINAGE UNTIL THE FINAL PARK GRADING DESIGN IS IMPLEMENTED.



No.	REVISIONS	By	Date
14			
13			
12			
11			
10			
9	REVISED GRADING FOR BLOCKS 15, 16, 22 AND 24	J.I.M.	2018:02:02
8	ISSUED FOR CONSTRUCTION	J.I.M.	2017:08:02
7	REVISED PER CITY COMMENTS	J.I.M.	2017:06:16
6	REVISED PER MOECC COMMENTS	J.I.M.	2017:06:07
5	ISSUED FOR TENDER	J.I.M.	2017:03:23
4	SUBMISSION FOR MOECC APPROVAL	J.I.M.	2017:02:16
3	SUBMISSION No.3 FOR CITY REVIEW	J.I.M.	2017:01:25
2	SUBMISSION No.2 FOR CITY REVIEW	J.I.M.	2016:11:04
1	SUBMISSION No.1 FOR CITY REVIEW	J.I.M.	2016:07:08

CANADA LANDS COMPANY
SOCIÉTÉ IMMOBILIÈRE DU CANADA

30 Metcalfe Street Suite 601
Ottawa, On K1P 5L4
613 998 7777

IBI GROUP
400 – 333 Preston Street
Ottawa ON K1S 5N4 Canada
tel 613 225 1311 fax 613 225 9868
ibigroup.com

Project Title

WATERIDGE VILLAGE AT ROCKCLIFFE
PHASE 1B

LICENSED PROFESSIONAL ENGINEER
J. I. MOFFATT
18/02/02
PROVINCE OF ONTARIO

Drawing Title

GRADING PLAN

Scale

1 : 500

Design	Date
J.I.M.	MAY 2016
Drawn	Checked
M.M.	J.I.M.
Project No.	Drawing No.
38298	212

D07-16-15-0003

#17063

X:\38298-GTBRockcliffe\3.0 Drawings\3\Civil\Layouts PHB\212 GRADING PLAN.dwg Layout: None GRADING PLAN Plot Style: AIA STANDARD-FULL.CTB Plot Scale: 1:25.4 Printed At: 7/25/2018 12:17 PM Last Saved By: mmiha Last Saved At: Feb

GRADE RAISE LIMIT = 1.5m
GRADE RAISE LIMIT = 1.25m

CHEMIN MIKINAK ROAD

3.6m MULTI USE PATH

PARK

BLOCK 18

BLOCK 17

BLOCK 113

BLOCK 114

BLOCK 112

BLOCK 101

BLOCK 109

CHEMIN CODDS ROAD

RUE MOSES TENNISCO STREET

INSTALL SNOW FENCE AROUND PERIMETER OF PARK BLOCK 18/20 1.0m INSIDE P.L.

2.0m ASPHALT WALK

CONTD ON DWG 38298-212

GRADING & DRAINAGE APPROVED

Signed _____

Date _____ 2017

NOTES:

FOR GRADING LEGEND, DETAILS AND CROSS SECTIONS REFER TO DRAWINGS 38298-015 & 38298-016.

THE PROPOSED PARK BLOCK GRADING IS TEMPORARY AND ENSURES THE PROPERTY WILL HAVE POSITIVE DRAINAGE UNTIL THE FINAL PARK GRADING DESIGN IS IMPLEMENTED.



No.	REVISIONS	By	Date
14			
13			
12			
11			
10			
9	REVISED CB222C & CB222D LOCATION	J.I.M.	2017:11:13
8	ISSUED FOR CONSTRUCTION	J.I.M.	2017:08:02
7	REVISED PER CITY COMMENTS	J.I.M.	2017:06:16
6	REVISED PER MOECC COMMENTS	J.I.M.	2017:06:07
5	ISSUED FOR TENDER	J.I.M.	2017:03:23
4	SUBMISSION FOR MOECC APPROVAL	J.I.M.	2017:02:16
3	SUBMISSION No.3 FOR CITY REVIEW	J.I.M.	2017:01:25
2	SUBMISSION No.2 FOR CITY REVIEW	J.I.M.	2016:11:04
1	SUBMISSION No.1 FOR CITY REVIEW	J.I.M.	2016:07:08

CANADA LANDS COMPANY
SOCIÉTÉ IMMOBILIÈRE DU CANADA
30 Metcalfe Street Suite 601
Ottawa, On K1P 5L4
613 998 7777

IBI
IBI GROUP
400 – 333 Preston Street
Ottawa ON K1S 5N4 Canada
tel 613 225 1311 fax 613 225 9868
ibigroup.com

Project Title

WATERIDGE VILLAGE AT ROCKCLIFFE

PHASE 1B

LICENSED PROFESSIONAL ENGINEER
J. I. MOFFATT
17/11/13
PROVINCE OF ONTARIO

N

Drawing Title

GRADING PLAN


Scale
1 : 500


Design	Date
J.I.M.	MAY 2016
Drawn	Checked
M.M.	J.I.M.
Project No.	Drawing No.
38298	213

D07-16-15-0003

#17063

X:\38298-CEB\Cadd\Plans\Sheets\Layouts\GRADING PLAN.dwg, Layout Name: GRADING PLAN Plot Style: AIA STANDARD.ctb, Plot Scale: 1:25.4 Printed At: 7/20/2018 4:30 PM Last Saved By: emorse Last Saved At: Nov. 13, 17





TYPICAL DITCH SECTION
N.T.S.

GRADING & DRAINAGE APPROVED

Signed _____

Date _____ 2017

NOTES:

FOR GRADING LEGEND, DETAILS AND CROSS SECTIONS REFER TO DRAWINGS 38298-015 & 38298-016.

THE PROPOSED PARK BLOCK GRADING IS TEMPORARY AND ENSURES THE PROPERTY WILL HAVE POSITIVE DRAINAGE UNTIL THE FINAL PARK GRADING DESIGN IS IMPLEMENTED.



No.	REVISIONS	By	Date
14			
13			
12			
11			
10			
9			
8	ISSUED FOR CONSTRUCTION	J.I.M.	2017:08:02
7	REVISED PER CITY COMMENTS	J.I.M.	2017:06:16
6	REVISED PER MOECC COMMENTS	J.I.M.	2017:06:07
5	ISSUED FOR TENDER	J.I.M.	2017:03:23
4	SUBMISSION FOR MOECC APPROVAL	J.I.M.	2017:02:16
3	SUBMISSION No.3 FOR CITY REVIEW	J.I.M.	2017:01:25
2	SUBMISSION No.2 FOR CITY REVIEW	J.I.M.	2016:11:04
1	SUBMISSION No.1 FOR CITY REVIEW	J.I.M.	2016:07:08

CANADA LANDS COMPANY
SOCIÉTÉ IMMOBILIÈRE DU CANADA
30 Metcalfe Street Suite 601
Ottawa, On K1P 5L4
613 998 7777

IBI GROUP
400 – 333 Preston Street
Ottawa ON K1S 5N4 Canada
tel 613 225 1311 fax 613 225 9868
ibigroup.com

Project Title

WATERIDGE VILLAGE AT ROCKCLIFFE

PHASE 1B

LICENSED PROFESSIONAL ENGINEER
J. I. MOFFATT
17/08/02
PROVINCE OF ONTARIO

Drawing Title

GRADING PLAN


Scale: 1 : 500

Design	Date
J.I.M.	MAY 2016
Drawn: M.M.	Checked: J.I.M.
Project No. 38298	Drawing No. 214

D07-16-15-0003

#17063

J:\38298-ckrocuvilla\3.0 drawings\Civil\Layouts prints\214 GRADING PLAN.dwg Layout Name: GRADING PLAN Plot Style: AIA STANDARD_FULL.CTB Plot Scale: 1:25.4 Plotted At: 8/2/2017 8:59 AM Last Saved By: mmiex Last Saved At: Mar. 22,





TYPICAL SECTION FOR BACKYARD RE-GRADE
N.T.S.

GRADING & DRAINAGE APPROVED

Signed _____

Date _____ 2017

LEGEND:

- PROPOSED CHAIN LINK FENCE
- 91.96 PROPOSED GRADE
- 91.96 EXISTING GRADE
- EXISTING PICKUP ELEVATION
- x x x x REMOVE EXISTING
- PROPOSED AREA TO BE FILLED AND RE-GRADED
- LIMIT OF CONTRUCTION



No.	REVISIONS	By	Date
14			
13			
12			
11			
10			
9			
8			
7			
6			
5	REVISED GRADING AS PER REVISED BURMA POND DESIGN	J.I.M.	2017:12:05
4	ISSUED FOR CONSTRUCTION	J.I.M.	2017:08:02
3	REVISED PER CITY COMMENTS	J.I.M.	2017:06:16
2	REVISED PER MOECC COMMENTS	J.I.M.	2017:06:07
1	ISSUED FOR TENDER	J.I.M.	2017:03:23

CANADA LANDS COMPANY
SOCIÉTÉ IMMOBILIÈRE DU CANADA
30 Metcalfe Street Suite 601
Ottawa, On K1P 5L4
613 998 7777

IBI GROUP
400 – 333 Preston Street
Ottawa ON K1S 5N4 Canada
tel 613 225 1311 fax 613 225 9868
ibigroup.com

Project Title

WATERIDGE VILLAGE AT ROCKCLIFFE

PHASE 1B

LICENSED PROFESSIONAL ENGINEER
J. I. MOFFATT
17/12/05
PROVINCE OF ONTARIO

N

Drawing Title

GRADING PLAN

Scale: 1 : 250

Design	Date
J.I.M.	MAY 2016
Drawn: M.M.	Checked: J.I.M.
Project No.: 38298	Drawing No.: 215

D07-16-15-0003

#17063

J:\38298-CP\Docs\Mkrs\3.0 Drawings\Grdng\Layouts Pre\B\215 GRADING PLAN.dwg Layout: Name: GRADING PLAN Print Style: AIA STANDARD-FULL.CTB Print Scale: 1:1 Plotted At: 12/5/2017 3:24 PM Last Saved By: ewinton.iqmp Last Saved At: Dec. 5, 17

PONDING AREA TABLE

PONDING AREA ID	MAXIMUM PONDING ELEVATION (m)	TOP OF GRATE ELEVATION (m)	MAXIMUM PONDING DEPTH (m)	MAXIMUM PONDING VOLUME (m^3)	MAXIMUM PONDING AREA (m^2)
PA149	92.05	91.94	0.11	9.76	221.26
PA150	92.30	92.20	0.10	2.45	71.02
	92.30	92.20	0.10	2.54	72.71
PA165	88.71	88.60	0.11	5.65	109.20
PA167A	88.17	88.05	0.12	5.23	123.49
PA167B	87.99	87.85	0.14	5.22	98.76
	88.00	87.90	0.10	2.00	43.27
PA201B	93.85	93.64	0.21	15.63	206.06
	93.85	93.68	0.17	5.61	94.06
PA208	88.62	88.39	0.23	33.02	433.66
PA209	88.25	88.12	0.13	3.80	100.23
PA210	89.11	88.88	0.23	39.50	518.67
PA211	88.75	88.62	0.13	4.74	107.37
PA213	89.17	89.07	0.10	1.45	45.93
	89.20	89.07	0.13	3.15	72.69
PA215	90.77	90.52	0.25	67.41	819.67
PA216	90.47	90.32	0.15	10.54	211.20
PA218	90.17	89.99	0.18	16.42	272.58
PA220	89.87	89.70	0.17	17.62	299.78
PA222	89.13	88.94	0.19	12.95	201.47

REVIEWED BY
DEVELOPMENT REVIEW SERVICES BRANCH

Signed _____

Date _____ 2016

Plan Number _____

LEGEND:

- PHASE 1B DRAINAGE AREA
- PHASE 1A DRAINAGE AREA
- EXTERNAL DRAINAGE AREA
- PA116 — POND ID
- MAJOR FLOW
- TOTAL FLOW
- MAJOR FLOW TO PARK DRY POND
- MAJOR FLOW TO BURMA SWMF
- EMERGENCY OVERLAND FLOW
- MH136 — MANHOLE ID

No.	REVISIONS	By	Date
14			
13			
12			
11			
10			
9			
8			
7			
6	REVISED PER CITY COMMENTS	J.I.M.	2017:06:16
5	REVISED PER MOECC COMMENTS	J.I.M.	2017:06:07
4	SUBMISSION FOR MOECC APPROVAL	J.I.M.	2017:02:16
3	SUBMISSION No.3 FOR CITY REVIEW	J.I.M.	2017:01:25
2	SUBMISSION No.2 FOR CITY REVIEW	J.I.M.	2016:11:04
1	SUBMISSION No.1 FOR CITY REVIEW	P.S.	2016:07:11

CANADA LANDS COMPANY
SOCIÉTÉ IMMOBILIÈRE DU CANADA
30 Metcalfe Street Suite 601
Ottawa, On K1P 5L4
613 998 7777

IBI GROUP
400 – 333 Preston Street
Ottawa ON K1S 5N4 Canada
tel 613 225 1311 fax 613 225 9868
ibigroup.com

Project Title

WATERIDGE VILLAGE AT ROCKCLIFFE

PHASE 1B

J. I. MOFFATT
17/06/16
PROVINCE OF ONTARIO

N

Drawing Title

PONDING PLAN

Scale: 1:2000

Design	Scale
P.S.	JULY 2016
Drawn: S.V.	Checked: P.S.
Project No.: 38298	Drawing No.: 751

D07-16-15-0003

#17063

J:\38298-CIBBrouwhis\5.0 Drawings\Odot\CIVIL Ph1B\38298 -Save= CIVIL_Ph--1B--751.dwg Layout Name= 751 Plot Style= ---- Plot Scale= 1:8.704 Plotted At: 6/16/2017 8:33 AM Last Saved By: mmilne Last Saved At: Jun 16, 17