PANORAMA WELLNESS CENTRE 3280 PALLADIUM DRIVE KANATA, ON SITE SERVICING STUDY

For:

Govan Brown & Associates

31-200 Thurston Drive

Ottawa, Ontario

By:

H.S.P. Consultants Inc.

5715 Warner Drive

Long Sault, ON K0C 1P0

HSP Project No.:

10113

Date:

100211486

March 10th, 2020

Prepared by:

Troy Gove, P.Eng Civil Engineer Reviewed by:

K. MacDonald, P. Eng. Department Manager

INDEX

1.0 Intr	oduction	l	. 5
1.1	Scope	9	. 5
1.2	Site		. 5
1.3	Previo	ous Studies	. 5
1.4	Accor	mpanying Reports	. 5
2.0		ervicing	
3.0		Vater Servicing	
4.0	Site Sto	rm Water Management	.7
4.1	Desig	n Intent	7
4.2	Desig	n Parameters	. 7
4	2.1 I	Pre-Development Flow	. 7
4.:		Catch basin Sub-Areas	
4.		Catch Basin CB100 (Storm Line 1)	
4.		Catch Basin CB108 (Storm Line 2)	
4.:		Catch Basin Man Hole CBMH101 (Storm Line 3)	
4.		Catch Basin CB103 (Storm Line 4)	
		Catch Basin CB102(Storm Line 5)	
4.		Catch Basin CB105 (Storm Line 6)	
4.		Catch Basin CB104 (Storm Line 7)	
		Roof Drains (Storm Line 8)1	
		Catch Basin CB106 (Storm Line 9)1	
	2.2.10	Catch Basin CB107 (Storm Line 10)	
4	2.2.11	Catch Basin CB109 (Storm Line 11)	
	2.2.12	Catch Basin CB110 (Storm Line 12)	
	2.2.13	Man Hole MH300 (Storm Line 13)1	
	2.2.14	Catch Basin Man Hole CBMH400 (Storm Line 14)	
	2.2.15	Man Hole MH100 (Storm Line 15)1	
		Storage Requirements1	
• • •		Storm Water Quality1	
	-	Other flows1	
4.	3 Erc	osion and Sediment Control1	2

LIST OF APPENDICES

APPENDIX A – Drawings SP1 to SP4

APPENDIX B - FUS Demand Calculations

APPENDIX C - ICI Sanitary Sewer Design Table

APPENDIX D - Storm Water Calculations

APPENDIX E - Stormceptor Design Report

1.0 Introduction

1.1 Scope

HSP was retained Govan Brown & Associates to design necessary plans, specifications and documents pertaining to the site servicing for the proposed development located at 3280 Palladium Drive, Kanata, Ontario. This study forms part of the Site Plan Application for the above-mentioned development. The scope identified herein is based off of expected occupancy of the first floor. When the second floor occupancy is determined, it should be noted that the site servicing study be re-assessed base on the new tenant loading.

1.2 Site

The site is described as Block 2 of Registered Plan 4M-1627, Geographic Township of Huntley, City of Ottawa, on the north side of Upper Canada Street as shown on the topographic survey prepared by Stantec Inc. The subject lot has an area of 0.4856 hectares.

1.3 Previous Studies

The design of the site servicing of this development has been completed in accordance with the following reports:

- Kanata West Master Serving Study, June 2006
- Amendment to Kanata West Business Park Stormwater Management Report and Pond 6 East Design Brief, Revision 2, July 2016

1.4 Accompanying Reports

This design brief is to be accompanied by the following supplemental reports:

 Storm Water Management Report Completed by: HSP Consultants Inc

Date: March 2020

Geotechnical Report

Completed by: Paterson Group

Date: January 2019

2.0 Water Servicing

The current zoning for the development is Industrial, however the proposed use translates more into a Commercial/Institutional space and as such Table 3-2 of the MOE Drinking Water Design Guidelines may be used. As per Clause 3.4.3 of the MOE Guidelines, an allowance of $28m^3/(ha^*d)$ will be used if no records are available. As such, the development will be designed for $28m^3/(ha^*d)$ of drinking water. Given the area of our site, the flow rate for domestic water is 40L/s. The flow rate required for the full sprinkler system may be found in Appendix B. This calculation indicates a required flow rate of 83L/s. Therefore, the total required flow for the development is 123L/s.

There are proposed three AA hydrants within 75m of 3280 Palladium drive. As per Technical Bulletin ISTB-2018-02, these hydrants produce 5,700L/min, providing a total of 17,100 L/min, which is above the 7,380 L/min requirement for the development.

The proposed watermain on Upper Canada Drive is a 200mmø PVC CL150DR located on the north side of the street. The required service size for the development is a 150mmø service. The service will be installed with a W3 Chamber, as per city standards.

3.0 Wastewater Servicing

As shown on Drawing SP1, Revision A in Appendix A, theproposed sanitary sewer runs parallel to Upper Canada Street. The proposed sanitary sewer main begins at Sanitary Manhole 160A and flows easterly along Upper Canada at 0.7%. The PVC SDR35 sanitary sewer has a diameter of 250mm.

The proposed site has an area of 0.4856 hectares. In accordance with the City of Ottawa's Sewer Design Guidelines, the proposed flow has been calculated in accordance to Appendix 4A. Given the proposed use of a Medical Office, the sanitary design flow is calculated as follows:

Table 3.1: Sanitary Design Flow Calculations

No. of Doctors:3275 Litres/Day/PersonNo. of Office Staff:975 Litres/Day/PersonNo. of Patients:10025 Litres/Day/Person

Total Flow: 4000 Litres/Day
Total Flow: 2.78 Litres/Second

Based on ICI Sewer Design Tables (Appendix C), the design parameter for the subdivision is 35,000 Litres/Hectare/Day for Industrial zoning. Given the site area, this translates to a maximum flow of 8237 Litres/hectare/day.

As such, the development falls well within the designed flow for the subdivision.

4.0 Site Storm Water Management

HSP created drawings SP1 to SP4 (Appendix A) to design the storm water management system for the proposed site. These drawings also depict the general features of the site, parking, structures and landscaping.

The private right-of-way south of the property will have new mains installed prior to the completion of this project. Upper Canada Street is proposed to have a new 675mmø concrete storm sewer installed at a slope of 0.7%. This proposed sewer will be the discharge point for the development.

The design of the storm water management system is completed in accordance with the Ontario Ministry of Environment "Storm Water Management Planning and Design Manual", City of Ottawa, and Conservation Authority requirements.

4.1 Design Intent

At the time of the design, a topographic survey was completed. The lot corner elevations are to remain at existing elevations. The main principle of the site storm sewer management is to contain all storm water on the site and limit its flow leaving the site to a "pre-development" state prior to entering the storm sewer mains and providing storage for any excess water.

4.2 Design Parameters

The following is a list of the design parameters used in determining the storm water flows for the site and corresponding sewer pipe sizes. The design calculations are provided in Appendix D.

4.2.1 Pre-Development Flow

- Proposed site has an area of 0.4856 hectares;
- "Pre-Development" runoff limit was established by HSP from predevelopment conditions of the site.
- Rainfall Intensity as per IDF Table for "Carleton Place, Ontario";
- Time of Concentration of 5 minutes:
- 2 & 100-year design storms.

A predevelopment flow limit of 30.4 L/s (2 year) & 67.5 L/s (100 year) are imposed for the proposed development. These are the flow rates used to limit the future runoff flowrate and to determine storage requirements.

4.2.2 Catch basin Sub-Areas

The catch basins are used to collect the storm water from its associated area. The amount of impervious area is determined for each area. Catch basin subareas can be seen on Drawing SP3 in Appendix A. All impervious surfaces (roofs, roadways, etc.) are associated with a run-off coefficient of 0.90. All pervious surfaces (e.g. grass) are associated with a run-off coefficient of 0.20 for the design storm events. With this information, and in accordance with the Modified Rational Method, a hydrograph is prepared for the detention areas. This hydrograph provides the storage requirement for the area under consideration. As per City of Ottawa requirements, to calculate the required above ground storage, the outlet flow rate has been halved. Given the overall anticipated design flows for the site, the total generated post development flow is 113.5 L/s (2 year) & 252.1 L/s (100 year), which are both greater than the predevelopment flows. As such, quantity control measures are required.

4.2.2.1 Catch Basin CB100 (Storm Line 1)

Catch Basin CB100 is located at the north east side of the property. This catch basin drains a total of $366m^2$, with $65m^2$ of that total constituting pervious area. The total flow rate for this area, according to the Modified Rational Method, is 8.9 L/s (2-Year) and 19.7 L/s (100-Year). This Catch basin will flow into CBMH101 unrestricted with a 13m 200mmø PVC SDR35 storm sewer sloped at 1.0%.

4.2.2.2 Catch Basin CB108 (Storm Line 2)

Catch Basin CB108 is located at the north of the property. This catch basin drains a total of 131m², with 116m² of that total constituting pervious area. The total flow rate for this area, according to the Modified Rational Method, is 1.1 L/s (2-Year) and 2.5 L/s (100-Year). This Catch basin will flow into CBMH101 unrestricted with a 14m 150mmø PVC SDR35 storm sewer sloped at 1.0%.

4.2.2.3 Catch Basin Man Hole CBMH101 (Storm Line 3)

Catch Basin Man-Hole CBMH100 is located at the north east side of the property. This catch basin drains a total of 846m², with 213m² of that total constituting pervious area. The total flow rate for this area, according to the Modified Rational Method, is 19.1 L/s (2-Year) and 42.5 L/s (100-Year). This Catch basin will flow into the CB102 unrestricted with a 200mmø PVC SDR35 storm sewer sloped at 1.0%.

4.2.2.4 Catch Basin CB103 (Storm Line 4)

Catch Basin CB103 is located at the east of the property. This catch basin drains a total of 330m², with 32m² of that total constituting pervious area. The total flow rate for this area, according to the Modified Rational Method, is 8.6 L/s (2-Year) and 19.1 L/s (100-Year). This Catch basin will flow into CB102 unrestricted with a 13m 200mmø PVC SDR35 storm sewer sloped at 1.0%.

4.2.2.5 Catch Basin CB102(Storm Line 5)

Catch Basin CB102 is located at the middle of the property. This catch basin drains a total of 1,494m², with 245m² of that total constituting pervious area. The total flow rate for this area, according to the Modified Rational Method, is 36.7 L/s (2-Year) and 81.5 L/s (100-Year). This Catch basin will flow into CB102 unrestricted with a 17m 300mmø PVC SDR35 storm sewer sloped at 1.0%.

4.2.2.6 Catch Basin CB105 (Storm Line 6)

Catch Basin CB105 is located at the east of the property. This catch basin drains a total of 330m², with 32m² of that total constituting pervious area. The total flow rate for this area, according to the Modified Rational Method, is 8.6 L/s (2-Year) and 19.1 L/s (100-Year). This Catch basin will flow into CB104 unrestricted with a 13m 200mmø PVC SDR35 storm sewer sloped at 1.0%.

4.2.2.7 Catch Basin CB104 (Storm Line 7)

Catch Basin CB104 is located in the middle of the property. This catch basin drains a total of 2262m², with 405m² of that total constituting pervious area. The total flow rate for this area, according to the Modified Rational Method, is 54.8 L/s (2-Year) and 121.7L/s (100-Year). This Catch basin will flow into CB106 unrestricted with a 17m 300mmø PVC SDR35 storm sewer sloped at 1.0%.

4.2.2.8 Roof Drains (Storm Line 8)

Refer to mechanical drawings for roof drain system. Below grade, the roof drains will be drained by a 300mmø PVC SDR35 storm sewer sloped at 1.0%. The total flow rate for this area, according to the Modified Rational Method, is 30.6 L/s (2-Year) and 68L/s (100-Year).

4.2.2.9 Catch Basin CB106 (Storm Line 9)

Catch Basin CB106 is located in the middle of the property. This catch basin drains a total of 3658m², with 405m² of that total constituting pervious area. The total flow rate for this area, according to the Modified Rational Method, is 94.1 L/s (2-Year) and 209L/s (100-Year). This Catch basin will flow into CB107 unrestricted with a 13m 400mmø PVC SDR35 storm sewer sloped at 1.5%.

4.2.2.10 Catch Basin CB107 (Storm Line 10)

Catch Basin CB107 is located in the middle of the property. This catch basin drains a total of 3991m², with 438m² of that total constituting pervious area. The total flow rate for this area, according to the Modified Rational Method, is 102.7 L/s (2-Year) and 228.2L/s (100-Year). This Catch basin will flow into MH100 unrestricted with a 9m 400mmø PVC SDR35 storm sewer sloped at 2.0%.

4.2.2.11 Catch Basin CB109 (Storm Line 11)

Catch Basin CB109 is located in the west of the property. This catch basin drains a total of 419m², with 109m² of that total constituting pervious area. The total flow rate for this area, according to the Modified Rational Method, is 9.4 L/s (2-Year) and 20.9L/s (100-Year). This Catch basin will flow into CB110 unrestricted with a 28m 200mmø PVC SDR35 storm sewer sloped at 1.0%.

4.2.2.12 Catch Basin CB110 (Storm Line 12)

Catch Basin CB110 is located in the west of the property. This catch basin drains a total of 713m², with 342m² of that total constituting pervious area. The total flow rate for this area, according to the Modified Rational Method, is 12.6 L/s (2-Year) and 27.9L/s (100-Year). This Catch basin will flow into MH300 unrestricted with a 13m 200mmø PVC SDR35 storm sewer sloped at 1.0%.

4.2.2.13 Man Hole MH300 (Storm Line 13)

Man Hole MH300 is located in the south-west of the property. This catch basin drains a total of 713m², with 342m² of that total constituting pervious area. The total flow rate for this area, according to the Modified Rational Method, is 12.6 L/s (2-Year) and 27.9L/s (100-Year). This Catch basin will flow into MH300 unrestricted with a 13m 200mmø PVC SDR35 storm sewer sloped at 1.0%.

4.2.2.14 Catch Basin Man Hole CBMH400 (Storm Line 14)

Catch Basin Man Hole CBMH400 is located in the south of the property. This catch basin drains a total of 884m², with 458m² of that total constituting pervious area. The total flow rate for this area, according to the Modified Rational Method, is 14.9 L/s (2-Year) and 33.0L/s (100-Year). This Catch basin will flow into MH100 unrestricted with a 13m 200mmø PVC SDR35 storm sewer sloped at 1.0%.

4.2.2.15 Man Hole MH100 (Storm Line 15)

Man Hole MH100 is located in the south of the property. This manhole forms the discharge point for all controlled flow on the property and is the only structure with a restricted flow. This catch basin drains a total of $4766m^2$, with $992m^2$ of that total constituting pervious area. The total unrestricted flow rate for this area, according to the Modified Rational Method, is 112.4 L/s (2-Year) and 249.8L/s (100-Year). The flow will be restricted with a Hydrovex 250 VHV-2, designed for 65L/s and 1.5m of head. The restricted flow rates will be 29L/s (2-Year) and 65.2 L/s (100-Year).

4.2.3 Storage Requirements

The City of Ottawa requires a 50% flow reduction to design for storage while using the Modified Rational Method. As such the storage calculations found in Appendix D have a reduced flow rate, and thus increasing the storage requirement. The underground storage system has been designed by Cultec. The design calculations and drawings for this system will be provided once available. The system has been designed to store the 100-year storm event, for a total of 76m³.

4.2.4 Storm Water Quality

To provide a minimum of 80% removal of total suspended solids (TSS) for the site, a device needs to be installed. Given the relative flows for the site, a Stormcepter® unit has been selected. MH100 will discharge to an inline device, namely STC750 (MH200) will be installed to treat the site. The units are to be installed and maintained as per the manufacturer's recommendations. The Stormceptor design report may be found in Appendix E.

4.2.5 Other flows

There is an uncontrolled flow on the south side of the property, of 1.04L/s (2-year) and 2.32L/s (100 year). These uncontrolled flows were subtracted from the predevelopment flow rates to establish the allowed release rate from the controlled areas.


4.3 Erosion and Sediment Control

During construction, erosion and sediment control measures must be implemented to limit the sediment transfer to existing streams and storm systems. This project will implement the following control measures:

- Installation of light-duty silt fence along the south, east and north ends of the property.
- Installation of a "Mud-Mat" at the site access point at Upper Canada Street.
- Installation of a straw bale flow check dam at the low point of the existing site.
- Installation of geotextile cover for the catch basin and manholes on Upper Canada Street.

The Erosion and Sediment Control Plan may be viewed on Drawing SP3 in Appendix A.

APPENDIX A Drawings SP1 to SP4



- 1. CONTRACTOR TO VERIFY ALL DIMENSIONS AND SITE CONDITIONS AND BRING ANY DISCREPANCY TO THE
- 2. CONTRACTOR TO ABIDE BY ALL APPLICABLE LEGISLATION, CITY OF OTTAWA SPECIFICATIONS, MOE
- REGULATIONS, AND BEST TRADE PRACTICES.
- THE LOCATION OF UTILITIES, WHERE SHOWN, IS APPROXIMATE ONLY, AND THE EXACT LOCATION MUST BE DETERMINED BY CONTACTING THE PROPER AUTHORITIES CONCERNED. THE CONTRACTOR MUST PROVE THE LOCATION OF UTILITIES AND SHALL BE RESPONSIBLE FOR THEIR ADEQUATE PROTECTION FROM DAMAGE DURING CONSTRUCTION.
- 4. CONTRACTOR TO INSTALL ALL OBC REQUIRED, BARRIER-FREE COMPONENTS ASSOCIATED WITH BARRIER-FREE PARKING AND EXTERIOR WALKS.
- 5. CONTRACTOR TO INSTALL A TACTILE ATTENTION INDICATOR AT BASE OF EXTERIOR WALK RAMP AS PER OBC 3.8.3.2.(h) AND 3.8.3.18.

1. ALL BEDDING MATERIALS TO CONFORM TO OPS STANDARDS AND SPECIFICATIONS.

- 2. GRANULAR A BEDDING MATERIAL TO BE IN ACCORDANCE WITH OPSS 1010, 314, 501 AND INSTALLED TO OPSD 708.030, 802.010M (GRAN. 'A' ONLY), AND 802.030M (CLASS B, GRAN. 'A' BEDDING AND COVER).
- 3. ALL BEDDING TO BE COMPACTED TO 95% STANDARD PROCTOR DENSITY AND TESTED BY AN
- INDEPENDENT COMPANY. HSP ENGINEER TO RECEIVE COPIES OF ALL TESTING REPORTS. 4. BACKFILL MAY CONSIST OF EXCAVATED SILT AND SAND AND/OR GLACIAL TILL AND TO BE COMPACTED TO 95% STANDARD PROCTOR DENSITY IN 300mm LIFTS.

- 1. STORM PIPING MATERIAL TO BE PVC SDR35 (GREEN ONLY).
- 2. SANITARY PIPING MATERIAL TO BE PVC DR29 (WHITE ONLY). 3. WATER SERVICE TO BE HDPE AS APPROVED BY THE CITY /W CURB BOX AND W3 VALVE CHAMBER.
- 4. GRANULAR 'A' BEDDING MATERIAL TO BE INSTALLED AS PER ABOVE.
- 5. CONNECTION AT EXISTING STORM SEWER SHALL BE THROUGH MANUFACTURED TEE.
- 6. DEPTH OF BURY OF WATER SERVICE TO BE MINIMUM 2.3m

MAINTENANCE HOLES AND CATCHBASINS:

- 1. MAINTENANCE HOLES TO BE 1200mm Ø AND AS PER OPSD 701.010 AND 701.030.
- 2. CATCHBASINS TO BE 600x600 AND AS PER OPSD 705.010, C/W SUMP. 3. CATCHBASIN GRATING TO BE AS PER OPSD 401.081 "FISH TYPE".
- 4. MAINTENANCE HOLE LID FOR ALL CATCH BASIN MANHOLES TO BE AS PER OPSD 401.081.
- 5. ADJUSTMENT UNITS AS PER OPSD 704.010.
- 6. ALL MAINTENANCE HOLES TO BE EQUIPPED WITH STEPS AS PER OPSD 405.010.

SPACING REQUIREMENTS:

1. AT ALL SEWER CROSSINGS, THE WATERMAIN SHALL BE LOCATED ABOVE THE SEWER. IF NOT FEASIBLE, THEN THE WATERMAIN SHALL GO BELOW WITH A MINIMUM SEPARATION OF 0.5m, AS PER MOE

STORM WATER QUANTITY NOTES:

1. MH100 TO BE FITTED WITH A HYDROVEX 250 VHV-2, DESIGNED FOR 65L/s AND 1.5m OF HEAD.

- CONTRACTOR TO INSTALL SPECIFIED TREATMENT SYSTEM OR PRE-APPROVED ALTERNATIVE TO MEET
- THE TOTAL SUSPENDED SOLID (TSS) REMOVAL OF AT LEAST 80%.
- 2. MH200 IS TO BE A STORMCEPTOR INLINE MODEL STC750.
- 3. THE UNIT IS TO BE MAINTAINED BY THE OWNER OF THE PROPERTY IN ACCORDANCE WITH THE MANUFACTURERS RECOMMENDATIONS FOR PROCEDURE AND FREQUENCY.

GRADING REQUIREMENTS:

1. EMBANKMENTS MUST NOT EXCEED 3:1 IN SLOPE.

- PAVEMENT & CURBS:

 1. ALL SITE CURBING TO BE INSTALLED AS PER OPSD 600.110. CONCRETE IS TO BE 32 MPa WITH 7% AIR, AS PER CITY STANDARD.
- 2. SITE ASPHALT PAVEMENT IS TO BE CONSTRUCTED WITH MINIMUM 400mm GRANULAR B TYPE II, 150mm
- GRANULAR 'A', 50mm SUPERPAVE SP19.0 AND 40mm SUPERPAVE SP12.5 IN ALL ACCESS LANES. SITE ASPHALT PAVEMENT IS TO BE CONSTRUCTED WITH MINIMUM 300mm GRANULAR B TYPE II, 150mm GRANULAR 'A' AND 50mm SUPERPAVE SP12.5 IN ALL CAR PARKING AREAS.
- 4. GRANULARS TO BE COMPACTED TO 100% STANDARD PROCTOR DENSITY AND ASPHALT TO BE COMPACTED TO 96% MARSHALL DENSITY. COMPACTION OF GRANULAR 'A' TO BE TESTED BY AN
- INDEPENDENT COMPANY WITH COPIES OF ALL REPORTS SENT TO THE HSP ENGINEER. CONCRETE SIDEWALKS ARE TO BE CONSTRUCTED AS PER OPSD 310.010 AND 310.050 WITH 250mm GRANULAR A AND 32 MPa CONCRETE WITH 5±1% AIR.

CULTEC STORM WATER STORAGE SYSTEM:

1. ALL SITE STORM WATER TO BE STORED UNDERGROUND USING CULTEC STORAGE SYSTEM.

LEGEND	ASA.	
STORM MAINTENANCE HOLE	727	ELEVATION
CATCHBASIN		STORM
SAN. MAINTENANCE HOLE		WATER
		SANITARY
HYDRANT	GAS	GAS
PRIMARY DOORWAY		UNDERGROUND POWER
HP22	-	O/H HYDRO
UTILITY POLE	(4) March 1 E 2000 2 E 2000 3 E 2000 2 E 2000 3 E 2000 3 E 2000	LOT BOUNDARY

REVISION

1 A 03/10/20 ISSUED FOR SITE PLAN APPLICATION TMG KJM REASON FOR ISSUE

ISSUE



T: 613-932-3289 F: 613-937-0125 www.hsp.ca Kristopher D. Benes, OAA, MRAIC, LEED AP

HSP Inc.

5715 Warner Drive

Long Sault, ON


Canada K0C 1P0

architects inc. architecture | interiors | concepts 2305 HILLARY AVE. | OTTAWA | ON | K1H 7J2


613.883.5090 | Info@openplan.ca

THIS DRAWING, SPECIFICATIONS AND RELATED DOCUMENTS ARE THE PROPERTY OF HSP INC. AND MUST B RETURNED UPON REQUEST. UNAUTHORIZED USE OF THIS DRAWING, DISCLOSURE OF TECHNICAL INFORMATIO ONTAINED THEREIN, OR REPRODUCTION EITHER IN WHOLE OR IN PART FOR USE BY ALL THIRD PARTIES, IS ORBIDDEN UNLESS WITH PRIOR WRITTEN PERMISSION OF ALL HSP INC. ALL SUCH AUTHORIZED

RAWING SHOULD NOT BE SCALED. DIMENSIONS SHOWN MUST NOT BE USED FOR CONSTRUCTION UNTIL RIFIED IN THE FIELD. ALL DISCREPANCIES MUST BE REPORTED TO THE OFFICE BEFORE COMMENCING WORLD




FEBRUARY 2020



GOVAN BROWN & ASSOCIATES LTD. 31-2000 THURSTON DRIVE OTTAWA, ON K1G 4K7

PANORAMA WELLNESS CENTRE 3280 PALLADIUM DRIVE, OTTAWA SITE SERVICING PLAN

B. SAMIS T.GOVE K. MACDONALD T.GOVE



REVISION

1 A 03/10/20 ISSUED FOR SITE PLAN APPLICATION TMG KJM

ISSUE



5715 Warner Drive Long Sault, ON Canada K0C 1P0 T: 613-932-3289 F: 613-937-0125 www.hsp.ca

Kristopher D. Benes, OAA, MRAIC, LEED AP


open plan architects inc. architecture | Interiors | concepts


2305 HILLARY AVE. | OTTAWA | ON | K1H 7J2 613.883.5090 | Info@openplan.ca

his drawing, specifications and related documents are the property of HSP Inc. and Must E RETURNED UPON REQUEST. UNAUTHORIZED USE OF THIS DRAWING, DISCLOSURE OF TECHNICAL INFORMATION ontained therein, or reproduction either in whole or in part for use by all third parties, i

DRAWING SHOULD NOT BE SCALED. DIMENSIONS SHOWN MUST NOT BE USED FOR CONSTRUCTION UNTIL ERIFIED IN THE FIELD. ALL DISCREPANCIES MUST BE REPORTED TO THE OFFICE BEFORE COMMENCING WORK

FORBIDDEN UNLESS WITH PRIOR WRITTEN PERMISSION OF ALL HSP INC. ALL SUCH AUTHORIZED






SHEET 2 of 4 REVISION:


GOVAN BROWN & ASSOCIATES LTD. 31-2000 THURSTON DRIVE OTTAWA, ON K1G 4K7

PANORAMA WELLNESS CENTRE 3280 PALLADIUM DRIVE, OTTAWA SITE GRADING PLAN

T.GO\	/E	B. SAMIS
DRAWN BY: T.GO\	/E	APPROVED BY: K. MACDONALD
SCALE: 1:200)	DRAWING No.
DATE:	DPO IDOT NA	1 .7 - /

FEBRUARY 2020





APPENDIX B FUS Demand Calculations

Determine Building to be Assessed

Panorama Wellness Centre 3280 Palladium Dr., Ottawa, ON. Fire Flow Demand Calculation

1) Initial Estimate of Required Fire Flow

F=220*C*SQRT (A)

F = the required fire flow in litres per minute

 $\mbox{\ensuremath{\text{C}}}$ = coefficient related to the type of construction

- = 1.5 for wood frame construction (structure essentially all combustible)
- = 1.0 for ordinary construction (brick or other masonry walls, combustible floor and interior)
- = 0.8 for non-combustible construction (unprotected metal structural components, masonry or metal walls)
- = 0.6 for fire resistive construction (fully protected frame, floor, roof)

A = the total floor area in square metres (incl all storeys but not basements at least 50% below grade)

Fire flow shall not exceed 30,000 L/min unless it is a one storey building which must not exceed 25,000 L/min or be less than 2,000 L/min

Calculations for fire flow F:

A = 1974

C = 0.8

F = 8000 L/min = 133 L/s Rounded to Nearest 1,000 L/min.

- 2) Charge to required fire flow based on contents of building (Occupancy)
 - -25 % = reduction due to non-combustible contents
 - -15 % = reduction due to limited combustible contents
 - 0 % = no charge due to combustible contents
 - 15 % = surcharge due to free burning contents
 - 25 % = surcharge due to rapid burning contents

OSR = -15% Contents are considered limited combustible

Decrease in Fire Flow = -1200

F = 6800 L/min = 113 L/s

- 3) Charge to Required Fire Flow Based on Presence of Automatic Sprinkler Protection
 - 0 % = no reduction due to absence of automatic sprinkler system
 - $-25\,\%$ = reduction proper system supervision including water flow and control valve alarm service
 - -50 % = reduction with system supervision including water flow and control valve alarm service

AS = -50% Sprinler System installed with supervision

Decrease in Fire Flow = -3400

4) Charge to Required Fire Flow Based on Proximity to Other Building

 $\label{thm:charge} The charge for any one side generally should not exceed the following limits for the separations shown$

Separation (m)		Charge I			
0 to	3	25% to	20%	Wall	Distance
3 to	10	20% to	15%	Left	>30m
10 to	20	15% to	10%	Right	6m
20 to	30	10% to	5%	Front	>30m
30 to	45	5% to	0%	Back	37.7m

Calculation of Fire Flow Increase due to Proximity to Other Buildings

PB = PL+PR+PF+PRR

Where,

PL = proximity charge for left side of building = 5.0%
PR = proximity charge for right side of building = 17.1%
PF = proximity charge for front of building = 5.0%
PRR = proximity charge for rear of building = 2.6%

PB = 29.7%

Increase in Fire Flow = 2020

F = 5000 = 83 L/s Rounded to nearest 1000 L/min

^{*}Note that firewalls were not considered in the calculation above (Conservative estimate)

^{*}Note that seperation distrance were taken to building property line on sides notadjacent to road as it is currently an undevelopped area

APPENDIX C
ICI Sanitary Sewer Design Table



K1S 5N4

PROJECT: KANATA WEST BUSINESS PARK LOCATION: 333 HUNTMAR DRIVE CLIENT: TAGGART

	LOCATION						RESI	DENTIAL					ICI A	REAS				INFILT	RATION ALLOV	WANCE	FIXED	TOTAL				PROPOSED S	EWER DESIGN			
	LOCATION				UNI	TYPES	- 1	REA POPULATI	ON PEAK PEAK				AREA (Ha)				PEAK	AREA	A (Ha)	FLOW	FLOW	FLOW	CAPACITY	LENGTH	DIA	SLOPE	VELOCITY	VELOCITY	AVA	ILABLE
CTREET	AREAIR	FROM	TO		CD.	T	D.T.)	FACTOR FLOW	PRESTIGE I	BUISNESS PK	COMN	MERCIAL		INDUSTRIAL		FLOW	1110	CLINA	(1.4-)	(1.7-)	(1.1.)	(1, 1-)	()		(0/)	(full)	(actual)	CAP	PACITY
STREET	AREA ID	MH	МН	SF	SD	TH A	PT	Ha) IND C	UM (L/s)	IND	CUM	IND	CUM	IND	CUM	PF	(L/s)	IND	сим	(L/s)	(L/s)	(L/s)	(L/s)	(m)	(mm)	(%)	(m/s)	(m/s)	L/s	(%)
KANATA WEST BUSINES	S PARK																													
											.																			
Upper Canada Street	Blocks 30, 31, 33, 53	MH154A	MH153A								1.00			2.78	2.78	5.40	6.08	3.00	3.00	0.99	0.00	7.07	43.87	110.00	250	0.50	0.866	0.607	36.80	83.88
	Blocks 34, 35	MH153A	MH152A			1				1.86	1.86				2.78	5.40	6.99	2.08	5.08	1.68	0.00	8.66	39.24	114.86	250	0.40	0.774	0.601	30.57	77.92
	Blocks 39	MH152A	MH151A			1				4.52	6.38				2.78	5.40	9.18	4.55	9.63	3.18	0.00	12.36	36.70	10.84	250	0.35	0.724	0.611	24.34	66.32
		MH151A MH150A	MH150A MH101A	-	_					-	6.38 6.38			1	2.78 2.78	5.40	9.18 9.18	0.20	9.83 9.94	3.24	0.00	12.43 12.46	36.70 36.70	102.56 63.86	250	0.35	0.724	0.653 0.653	24.28 24.24	66.14 66.04
		IVIH15UA	IVIHIUIA	-	_					-	0.38			1	2.78	5.40	9.18	0.11	9.94	3.28	0.00	12.40	30.70	03.80	250	0.35	0.724	0.053	24.24	00.04
Campeau Drive	Blocks 3, 38	MH99A	MH100A			+				5.84	5.84			1			2.84	6.34	6.34	2.09	0.00	4.93	50.02	112.75	250	0.65	0.987	0.607	45.09	90.14
cumpeuu Drive	Blocks 4, 37	MH100A	MH101A			+				1.58	7.42			1			3.61	1.83	8.17	2.70	0.00	6.30	51.91	101.44	250	0.70	1.024	0.630	45.60	87.86
	DIOCKS 4, 37	MITTOOA	WITTOIA	1	+	+ +				1.30	7.42						3.01	1.03	0.17	2.70	0.00	0.30	31.31	101.44	230	0.70	1.024	0.030	43.00	87.80
Nipissing Court	Blocks 1, 7	MH123A	MH122A			+ +				1	1		1	1.93	1.93	6.25	4.89	2.29	2.29	0.76	0.00	5.64	50.02	65.18	250	0.65	0.987	0.607	44.38	88.72
TIPIOSING COURT	Blocks 2	MH122A	MH121A							0.79	0.79			2.55	1.93	6.25	5.27	0.99	3.28	1.08	0.00	6.35	50.02	100.00	250	0.65	0.987	0.607	43.66	87.30
	Block 5	MH121A	MH101A							0.78	1.57				1.93	6.25	5.65	1.02	4.30	1.42	0.00	7.07	85.51	97.00	250	1.90	1.688	1.007	78.45	91.73
Campeau Drive	Block 36	MH101A	MH103A							0.33	15.70				4.71	4.75	16.69	0.56	22.97	7.58	0.00	24.27	43.87	93.00	250	0.50	0.866	0.866	19.59	44.66
	Block 32, 54	MH103A	MH104A							1.00	16.70				4.71	4.75	17.18	1.31	24.28	8.01	0.00	25.19	43.87	120.00	250	0.50	0.866	0.866	18.67	42.57
Campeau Drive	Block 29	MH104A	MH105A							0.69	17.39				4.71	4.75	17.52	0.83	25.11	8.29	0.00	25.80	43.87	53.11	250	0.50	0.866	0.900	18.07	41.18
KWRC	Blocks 6, 8, 9, 10		MH 105A									11.78	11.78				5.73	11.78	11.78	3.89	0.00	9.61	39.24	12.01	250	0.40	0.774	0.601	29.62	75.50
											4= 00		44.00							40.00										
Campeau Drive	D11 - 2 4	MH105A	MH106A							0.75	17.39		11.78		4.71	4.75	23.24	0.28	37.17	12.27	0.00	35.51	59.68	87.77	300	0.35	0.818	0.851	24.17	40.50
	Block 24	MH106A	MH107A	-						0.75	18.14		11.78		4.71	4.75	23.61	1.10	38.27	12.63	0.00	36.24	59.68	90.92	300	0.35	0.818	0.851	23.45	39.28
Upper Canada Street	Blocks 27, 28	MH154A	MH156A	1		+ +				+	 			1.90	1.90	6.00	4.62	2.11	2.11	0.70	0.00	5.31	50.02	107.00	250	0.65	0.987	0.607	44.70	89.37
Opper Canada Street	Block 25	MH156A	MH131A			+ +				0.60	0.60			1.90	1.90	6.00	4.91	0.79	2.90	0.96	0.00	5.87	50.02	101.71	250	0.65	0.987	0.607	44.15	88.27
	DIOCK 25	WIIIISOA	WIIIII	1	+	+ +				0.00	0.00				1.50	0.00	4.51	0.75	2.50	0.50	0.00	3.07	30.02	101.71	230	0.03	0.507	0.007	44.13	00.27
Palladium Drive	Blocks 17, 26	MH130A	MH131A							1	0.00			1.91	1.91	6.00	4.64	2.38	2.38	0.79	0.00	5.43	50.02	106.00	250	0.65	0.987	0.607	44.59	89.15
Palladium Drive		MH131A	MH132A								0.60				3.81	5.25	8.39	0.23	5.51	1.82	0.00	10.21	43.87	67.35	250	0.50	0.866	0.672	33.66	76.72
	Block 23	MH132A	MH133A							1.01	1.61				3.81	5.25	8.89	1.27	6.78	2.24	0.00	11.12	43.87	71.26	250	0.50	0.866	0.672	32.75	74.64
		MH133A	MH107A								1.61				3.81	5.25	8.89	0.17	6.95	2.29	0.00	11.18	107.45	42.79	250	3.00	2.121	1.304	96.28	89.60
Campeau Drive	Block 49	MH107A	MH108A								19.75	0.42	12.20		8.52	4.40	30.72	0.97	46.19	15.24	0.00	45.96	59.68	120.00	300	0.35	0.818	0.900	13.72	22.99
	<u> </u>	MH108A	EX604A								19.75		12.20	<u> </u>	8.52	4.40	30.72	0.49	46.68	15.40	0.00	46.12	59.68	120.00	300	0.35	0.818	0.900	13.56	22.72
	Block 22	MH 604A	MH 603A			1				2.63	22.38		12.20		8.52	4.40	32.00	3.03	49.71	16.40	0.00	48.40	62.51	102.12	300	0.38	0.857	0.942	14.11	22.58
Upper Canada Street	Blocks 18, 19, 20, 21	MH160A	MH161A	_	_					2.22	0.00			2.25	2.25	5.75	5.24	2.48	2.48	0.82	0.00	6.06	58.86	83.00	250	0.90	1.162	0.714	52.80	
	Block 14- 16	MH161A	MH162A		_		_			2.23	2.23				2.25	5.75	6.32	2.45	4.93	1.63	0.00	7.95	50.02	112.00	250	0.65		0.692	42.07	84.10
		MH162A	MH140A								2.23				2.25	5.75	6.32	0.22	5.15	1.70	0.00	8.02	63.57	110.98	250	1.05	1.255	0.772	55.55	87.38
Upper Canada Street	Blocks 40, 41	MH167A	MH166A	+		++				+	0.00		-	1.45	1.45	6.25	3.67	1.66	1.66	0.55	0.00	4.22	51.91	72.00	250	0.70	1.024	0.611	47.69	91.87
opper Canada Street	Block 42	MH166A	MH165A	 	+	+ +			 	+	0.00			0.74	2.19	5.70	5.06	0.94	2.60	0.86	0.00	5.91	50.02	100.00	250	0.70	0.987	0.607	44.10	88.17
	Blocks 12, 13	MH165A	MH140A	 	+	+ +			- - - 	+	0.00			1.49	3.68	5.30	7.90	1.68	4.28	1.41	0.00	9.31	39.24	99.02	250	0.65	0.987	0.601	29.92	76.26
	DIOCK3 12, 13	MILLOOM	IIII140A	 	+	+ +		- - 	+ +	+	0.00		<u> </u>	1.73	3.00	3.30	7.30	1.00	7.20	1.71	0.00	7.31	33.24	33.02	-30	0.40	0.774	0.001	23.32	, 0.20
Journeyman Street		MH140A	MH141A	1	-					1	2.23		t	1	5.93	5.00	13.10	0.30	9.73	3.21	0.00	16.31	31.02	120.00	250	0.25	0.612	0.612	14.71	47.43
		MH141A	MH (84)		1	1 1				1	2.23				5.93	5.00	13.10	0.22	9.95	3.28	0.00	16.38	31.02	40.30	250	0.25	0.612	0.612	14.64	47.20
	•	Stuh	MH 603A	1		1 1		- 		1	2.23				5.93	5.00	13.10	0.00	9.95	3.28	0.00	16.38	31.63	32.98	250	0.26	0.624	0.624	15.26	48.22
		SLUD																		1										1
		SLUD																												
Campeau Drive	Block 11	MH 603A	MH 602A							2.40	27.01		12.20		14.45	3.80	41.30	2.83	62.49	20.62	0.00	61.93	103.47	105.24	375	0.32	0.908	0.944	41.54	40.15
Campeau Drive	Block 11 Tanger Outlet Centres	5:05	MH 602A MH 601A							2.40	27.01 27.01	16.40	12.20 28.60		14.45 14.45	3.80 3.80	41.30 49.28	2.83 16.84	62.49 79.33	20.62 26.18	0.00	61.93 75.46	103.47 109.75	105.24 107.73	375 375	0.32 0.36	0.908 0.963	0.944 1.032	41.54 34.29	40.15 31.25 29.53

Campeau Drive	Block XX	MH XXX	MH XXX	Light Grev = Constructed Sewer

Design Parameters:			Notes:		Designed: LME	No.	Revision	Date
			1. Manning's coefficient (n) = 0	.013		1.	City submission No. 1	11/25/2014
Residential	ICI Areas		2. Demand (per capita): 280 L/	day 300 L/day		2.	City submission No. 2	4/8/2015
SF 3.4 p/p/u		Peak Factor (PF)	3. Infiltration allowance: 0.33 L	/s/Ha 0.4 L/s/Ha	Checked:	3.	City submission No. 3	6/18/2015
TH/SD 2.7 p/p/u	P.B.P. 28,000 L/Ha/da	1.5	4. Residential Peaking Factor:			4. City submission No. 4 10/15/2015		10/15/2015
APT 1.8 p/p/u	COM 28,000 L/Ha/da	/ 1.5	Harmon Formula = 1+(14/(4+P^	0.5)) K=0.8		5.	Revised for Phase 2 Registration	4/19/2018
Other 60 p/p/Ha	IND 35,000 L/Ha/da	MOE Chart	where P = population in thousar	nds	Dwg. Reference: 14289-501	6. Revised for Phase 3 Registration		9/14/2018
						7. Revised per City Comments (Phase 3)		12/14/2018
						File Reference:	Date:	Sheet No:
						14289.5.7.1	4/19/2018	1 of 1

APPENDIX D Storm Water Calculations

Panorama Wellness Centre Storm Water Calculations - Pre-development Pre-development status was undeveloped lot

Controlled Flow

1. Determine Average Runoff Coefficient "C" for Controlled Flow

Item	Area (m²)	Runoff Coefficient
Building	0	0.90
Paved	0	0.90
Grass	4856	0.20
•	4,856.00	
C _{avg} =	0.20	

2. Determine Rainfall Intensity (i) - 2 year storm, (ii) - 100 year storm. 2 yr Intensity 100 yr Intensity

	Z yr michionly	100 yr intensity
Duration	(mm/hr)	(mm/hr)
5	112.50	249.90
10	69.30	154.00
15	52.20	116.00
20	45.00	101.00
25	37.00	86.00
30	32.10	71.40
60	19.80	44.00
120	12.20	27.10
360	5.70	12.60
720	3.50	7.70
1440	2.10	4.80

3. Determine pre-development time of concentration

Given the existing elevations, the maximum drainage length is 75m Over this length, the average slope is 0.022 m/m Using the Airport equation with an area of 4856m2 Tc = 6 minutes

Use 5 min. for design

4. Determine Flow Rates - Rational Method for Controlled Flow Q = 2.78CiA

				2 YEAR			100 YEAR			
			Q (per unit				Q (per unit			
Item	Area (ha)	C_{avg}	'i' (mm)	area)	Q (m ³ /s)	Q (L/s)	'i' (mm)	area)	Q (m ³ /s)	Q (L/s)
Lot	0.4856	0.20	112.50	0.063	0.0304	30.37	249.90	0.139	0.0675	67.47

 2 YEAR
 100 YEAR

 Controlled Flow:
 0.0304
 0.0675

Post Development

Storm Water Calculations - 2 yr & 100 yr

Controlled Flow

1. Determine Average Runoff Coefficient "C".

Item	Area (m²)	С	Product
Building	1088	0.90	979.20
Paved Areas	2686	0.90	2417.40
Grass	992	0.20	198.40
	4766.00		3595.00
c -	0.75		

2. Determine Rainfall Intensity (i). 2 yr Intensity 100 yr Intensity

	Z yr intensity	100 yr intensity
Duration	(mm/hr)	(mm/hr)
5	112.50	249.90
10	69.30	154.00
15	52.20	116.00
20	45.00	101.00
25	37.00	86.00
30	32.10	71.40

Unit Rate of Runoff Q = 2.78Ci

Q= 235.90773

3. Determine Flow Rates for Controlled Flow

Q = 2.78CiA

$$5 \text{ yr Q} = 112.43 \text{ L/s}$$

= 0.1124 m³/s

				2 YE	AR			100	YEAR	ĺ
				Q (per unit	:			Q (per		
Item	Area (ha)	C_{avg}	'i' (mm)	area)	Q (m³/s)	Q (L/s)	'i' (mm)	unit area)	Q (m³/s)	Q (L/s)
Developed Lot	0.4766	0.75	112.50	0.236	0.1124	112.43	249.90	0.524	0.2498	249.75
-	0.4766		·							·

4. Determine Flow Rates for Uncontrolled Flow

ltem	Area (m²)	'C' 5 Yr	Product 5 Yr
Building	0	0.90	0
Paved	22	0.90	20
Grass	68	0.20	14
•	90.00		33
$C_{avg} =$	0.37		

Q = 2.78CiA

			2 YEAR							
				Q (per unit				Q (per		
Item	Area (ha)	C_{avg}	'i' (mm)	area)	Q (m³/s)	Q (L/s)	'i' (mm)	unit area)	Q (m³/s)	Q (L/s)
Lot	0.009	0.37	112.50	0.116	0.0010	1.04	249.90	0.258	0.0023	2.32

2 YEAR 100 YEAR **Controlled Flow:** 0.1124 0.2498 **Uncontrolled Flow:** 0.0010 0.0023 Total Flow under the design storm: 0.1135 0.2521

2 YEAR 100 YEAR Therefore, total flow Pre Development: 0.0304 0.0675 **Total Flow Post Development:** 0.1135 0.2521 **Uncontrolled Flow Post Development** 0.0023 0.0010 Allowed Controlled Flow (Pre - Post Uncontrolled) 0.0293 0.0652

Developed Parcel Only 2 yr Storm Water Calculations

Storm	Sewer Des	ign			AR	EA	F	LOW TIM	IE Unit Rate	DE	SIGN FLOWS	Allowed	Pipe	:	SEWER D Capacity			Pipe	STORAC Avail.	GE Avail.
				I enath of	Increment	Cumul.	To Upper		of Runoff		Cumul. Flow	Flow	Diam.	Slone	Full	Velocity	Percent	Area		Volume
Line	From	То	Sub-Area	Sewer (m)	(ha)	Total (ha)		(min)	(m³/ha*s)	Flow (m ³ /s)	(m³/s)	(m³/s)	(mm)	m/m	(m³/s)	Full (m/s)		(m²)	(m ²)	(m ³)
1	CB100	CBMH101	Paved/Bldg	, ,	0.0301	•	5		0.281	0.0085	,		,		•	1	, ,			
			Landscape	13	0.0065	0.0366	5		0.063	0.0004	0.0089	0.0089	200	0.01	0.0328	1.044	27.11	0.031	0.02	0.30
2	CB108	CBMH101	Paved/Bldg		0.0015		5		0.281	0.0004										
2	CD100	CDIVITIO	Landscape	14	0.0015	0.0131	5		0.261	0.0004	0.0011	0.0011	150	0.01	0.0152	0.862	7.22	0.018	0.02	0.23
			Zanaccapo		0.0110	0.0101			0.000	0.0001	0.0011	0.0011	100	0.01	0.0.02	0.002		0.0.0	0.02	0.20
3	CBMH101	CB102	Paved/Bldg		0.0633		5		0.281	0.0178										
			Landscape	16	0.0213	0.0846	5		0.063	0.0013	0.0191	0.0191	300	0.01	0.0968	1.369	19.78	0.071	0.06	0.91
4	CB103	CB102	Paved/Bldg		0.0298		5		0.281	0.0084										
7	ODTOS	OB 102	Landscape	13	0.0230	0.0330	5		0.063	0.0004	0.0086	0.0086	200	0.01	0.0328	1.044	26.16	0.031	0.02	0.30
			•																	
5	CB102	CB104	Paved/Bldg		0.1249		5		0.281	0.0352										
			Landscape	17	0.0245	0.1494	5		0.063	0.0015	0.0367	0.0367	300	0.01	0.0968	1.369	37.90	0.071	0.04	0.75
6	CB105	CB104	Paved/Bldg		0.0298		5		0.281	0.0084										
_			Landscape	13	0.0032	0.0330	5		0.063	0.0002	0.0086	0.0086	200	0.01	0.0328	1.044	26.16	0.031	0.02	0.30
7	CB104	CB106	Paved/Bldg	17	0.1857	0.2262	5 5		0.281	0.0523	0.0540	0.0548	250	0.04	0.4.400	4 547	07.50	0.000	0.00	4.00
			Landscape	17	0.0405	0.2262	5		0.063	0.0025	0.0548	0.0546	350	0.01	0.1460	1.517	37.53	0.096	0.06	1.02
8	BLDG	CB106	Paved/Bldg		0.1088		5		0.281	0.0306										
			Landscape	12	0.0000	0.1088	5		0.063	0.0000	0.0306	0.0306	300	0.01	0.0968	1.369	31.64	0.071	0.05	0.58
0	CB106	CB107	Paved/Bldg		0.3253		_		0.004	0.0916										
9	CB100	CB107	Landscape	13	0.3253	0.3658	5 5		0.281 0.063	0.0916	0.0941	0.0907	400	0.01	0.2085	1.658	43.51	0.126	0.07	0.92
			Zanasaps		0.0.100	0.0000			0.000	0.0020	0.0011	0.0001	100	0.01	0.2000	11000	10.01	020	0.01	0.02
10	CB107	MH100	Paved/Bldg		0.3553		5		0.281	0.1000										
			Landscape	9	0.0438	0.3991	5		0.063	0.0027	0.1027	0.1027	400	0.02	0.2948	2.345	34.85	0.126	0.08	0.74
11	CB109	CB110	Paved/Bldg	28	0.0310		5		0.281	0.0087										
	02100	02.10	Landscape	20	0.0109	0.0419	5		0.063	0.0007	0.0094	0.0094	200	0.01	0.0328	1.044	28.65	0.031	0.02	0.00
12	CB110	MH300	Paved/Bldg	40	0.0371	0.0740	5		0.281	0.0104	0.0400	0.0400	000	0.04	0.0000	4.044	20.00	0.004	0.00	0.05
			Landscape	13	0.0342	0.0713	5		0.063	0.0021	0.0126	0.0126	200	0.01	0.0328	1.044	38.32	0.031	0.02	0.25
13	MH300	MH400	Paved/Bldg		0.0371		5		0.281	0.0104										
			Landscape	10	0.0342	0.0713	5		0.063	0.0021	0.0126	0.0126	200	0.01	0.0328	1.044	38.32	0.031	0.02	0.19
4.4	MH 400	MH400	Dovod/Dlds		0.0400				0.004	0.0400										
14	MH400	MH100	Paved/Bldg Landscape	40	0.0426 0.0449	0.0875	5 5		0.281 0.063	0.0120 0.0028	0.0148	0.0148	250	0.01	0.0595	1.212	24.86	0.049	0.04	1.48
			Zanasoapo	10	0.0440	0.0070			0.000	0.0020	0.0140	0.0140	200	0.01	0.0000	1.212	2 1.00	0.040	0.04	1.10
15	MH100	MH200	Paved/Bldg		0.3774		5		0.281	0.1062										
			Landscape	3	0.0992	0.4766	5		0.063	0.0062	0.1124	0.0290	300	0.005	0.0684	0.968	42.37	0.071	0.04	0.12
							1													

Developed Parcel Only 100yr Storm Water Calculations

Storm	ı Sewer Desi	gn			AR	EA	F	LOW TIN	ME Unit Rate	DE	SIGN FLOWS	Allowed	Pipe	;	SEWER D	ESIGN		Pipe	STORA Avail.	GE Avail.
				Length of	Increment	Cumul.	To Upper		of Runoff		Cumul. Flow	Flow	Diam.	Slope	Full	Velocity	Percent	Area	Area	Volume
Line	From	То	Sub-Area	Sewer (m)	(ha)	Total (ha)	End (min)	(min)		Flow (m ³ /s)	(m³/s)	(m³/s)	(mm)	m/m	(m³/s)	Full (m/s)	Full (%)	(m²)	(m²)	(m³)
1	CB100	CB101	Paved/Bldg		0.0301		5		0.625	0.0188										
			Landscape	13	0.0065	0.0366	5		0.139	0.0009	0.0197	0.0197	200	0.01	0.0328	1.044	60.07	0.031	0.01	0.16
0	OD400	OD404	Davis d/DIda		0.0045		_		0.005	0.0000										
2	CB108	CB101	Paved/Bldg Landscape	14	0.0015 0.0116	0.0131	5 5		0.625 0.139	0.0009 0.0016	0.0025	0.0025	150	0.01	0.0152	0.862	16.72	0.018	0.01	0.21
			Lanuscape	14	0.0110	0.0131	3		0.139	0.0010	0.0025	0.0025	150	0.01	0.0132	0.002	10.72	0.018	0.01	0.21
3	CBMH101	CB102	Paved/Bldg		0.0633		5		0.625	0.0396										
			Landscape	16	0.0213	0.0846	5		0.139	0.0030	0.0425	0.0425	300	0.01	0.0968	1.369	43.94	0.071	0.04	0.63
			•																	
4	CB103	CB102	Paved/Bldg		0.0298		5		0.625	0.0186										
			Landscape	13	0.0032	0.0330	5		0.139	0.0004	0.0191	0.0191	200	0.01	0.0328	1.044	58.11	0.031	0.01	0.17
_	05400	05.40.4					_													
5	CB102	CB104	Paved/Bldg	47	0.1249	0.4.404	5		0.625	0.0781	0.0045	0.0045	200	0.04	0.0000	4.000	04.40	0.074	0.04	0.40
			Landscape	17	0.0245	0.1494	5		0.139	0.0034	0.0815	0.0815	300	0.01	0.0968	1.369	84.19	0.071	0.01	0.19
6	CB105	CB104	Paved/Bldg		0.0298		5		0.625	0.0186										
· ·	02100	OBTOT	Landscape	13	0.0032	0.0330	5		0.139	0.0004	0.0191	0.0191	200	0.01	0.0328	1.044	58.11	0.031	0.01	0.17
7	CB104	CB106	Paved/Bldg		0.1857		5		0.625	0.1161										
			Landscape	17	0.0405	0.2262	5		0.139	0.0056	0.1217	0.1217	350	0.01	0.1460	1.517	83.37	0.096	0.02	0.27
							_													
8	BLDG	CB106	Paved/Bldg	40	0.1088	0.4000	5		0.625	0.0680	0.0000	0.0000	200	0.04	0.0000	4.000	70.00	0.074	0.00	0.05
			Landscape	12	0.0000	0.1088	5		0.139	0.0000	0.0680	0.0680	300	0.01	0.0968	1.369	70.28	0.071	0.02	0.25
9	CB106	CB107	Paved/Bldg		0.3253		5		0.625	0.2034										
J	OBTOO	OBTO	Landscape	13	0.0405	0.3658	5		0.139	0.0056	0.2090	0.2090	400	0.015	0.2553	2.030	81.87	0.126	0.02	0.30
											0.200									
10	CB107	MH100	Paved/Bldg		0.3553		5		0.625	0.2222										
			Landscape	9	0.0438	0.3991	5		0.139	0.0061	0.2282	0.2282	400	0.02	0.2948	2.345	77.42	0.126	0.03	0.26
	05400	05446					_													
11	CB109	CB110	Paved/Bldg	28	0.0310	0.0440	5		0.625	0.0194	0.0000	0.0000	200	0.04	0.0000	4.044	CO CE	0.004	0.04	0.00
			Landscape		0.0109	0.0419	5		0.139	0.0015	0.0209	0.0209	200	0.01	0.0328	1.044	63.65	0.031	0.01	0.00
12	CB110	MH300	Paved/Bldg		0.0371		5		0.625	0.0232										
	02110	WII 1000	Landscape	13	0.0342	0.0713	5		0.139	0.0048	0.0279	0.0279	200	0.01	0.0328	1.044	85.13	0.031	0.00	0.06
13	MH300	CBMH400	Paved/Bldg		0.0371		5		0.625	0.0232										
			Landscape	10	0.0342	0.0713	5		0.139	0.0048	0.0279	0.0279	200	0.01	0.0328	1.044	85.13	0.031	0.00	0.05
	00141115				0.0		_													
14	CBMH400	MH100	Paved/Bldg	40	0.0426	0.0004	5		0.625	0.0266	0.0000	0.0000	050	0.04	0.0505	4.040	EE 44	0.040	0.00	0.00
			Landscape	40	0.0458	0.0884	5		0.139	0.0064	0.0330	0.0330	250	0.01	0.0595	1.212	55.44	0.049	0.02	0.88
15	MH100	MH200	Paved/Bldg		0.3774		5		0.625	0.2360										
10	WILLIAM	1411 1200	Landscape	3	0.0992	0.4766	5		0.023	0.2300	0.2498	0.0652	300	0.01	0.0968	1.369	67.36	0.071	0.02	0.07
				_																
				•	-		-			-			-					-		

Hydrograph MH100 - 2 yr Storm

VARIABLES

AREA

0.4766 ha

Item	Area (m²)	'C'	Product
Paved/Bldg	0	0.90	0.00
Building	3774	0.90	3396.60
Grass	992	0.20	198.40
Total =	4766		3595.00
C _{avg} =	0.75		

*allowable release rate reduced by 50%

Step 2

Duration	Intensity
5	112.50
10	69.30
15	52.20
20	45.00
25	37.00
30	32.10
35	34.00
40	27.00

Allowable Release Rate =

Time of Concentration =

Step 3


Olep 3										
Time	Q (5)	Q (10)	Q (15)	Q (20)	Q (25)	Q (30)	Q (35)	Q (40)	Q _{all (M3/S)}	
0	0	0	0	0	0	0	0	0	0.0145	
5	0.1124	0.0693	0.0522	0.0450	0.0370	0.0321	0.0340	0.0270	0.0145	
10	0	0.0693	0.0522	0.0450	0.0370	0.0321	0.0340	0.0270	0.0145	
15		0	0.0522	0.0450	0.0370	0.0321	0.0340	0.0270	0.0145	
20			0	0.0450	0.0370	0.0321	0.0340	0.0270	0.0145	
25				0	0.0370	0.0321	0.0340	0.0270	0.0145	
30					0	0.0321	0.0340	0.0270	0.0145	
35						0	0.0340	0.0270	0.0145	
40							0	0.0270	0.0145	
45								0	0.0145	

*L/s

min

14.50

5



Step 4

		Sim. Triangle	Area under	
	Area OF trapeziod	Time Value	allowed	Storage
Duration	(m ³)	(min) X	flow (m ³)	(m³)
5	33.73	0.645	8.139	25.59
10	41.56	1.047	12.139	29.42
15	46.95	1.390	16.191	30.76
20	53.97	1.612	20.348	33.62
25	55.47	1.961	24.394	31.07
30	57.75	2.260	28.484	29.26
35	57.75	2.260	32.834	24.91
40	57.75	2.260	37.184	20.56
REQUIRED				33.62

Therefore, below ground storage of 34m³ is required for the Cultec System.

Hydrograph MH100 - 100 yr Storm

VARIABLES

0.4766 ha

AREA

Item	Area (m²)	'C'	Product
Pavement	0.00	0.90	0.00
Building	3774	0.90	3396.60
Grass	992	0.20	198.40
		=	
Total =	4766		3595.00
$C_{avg} =$	0.75		

Allowable Release Rate = Time of Concentration = 32.60 *L/s min


*allowable release rate reduced by 50%

Step 2

Duration	Intensity
5	249.90
10	154.00
15	116.00
20	101.00
25	86.00
30	71.40
35	54.00
40	32.00

Step 3

oteb o									
Time	Q (5)	Q (10)	Q (15)	Q (20)	Q (25)	Q (30)	Q (35)	Q (40)	Q _{all (M3/S)}
0	0	0	0	0	0	0	0	0	0.0326
5	0.2498	0.1539	0.1159	0.1009	0.0859	0.0714	0.0540	0.0320	0.0326
10	0	0.1539	0.1159	0.1009	0.0859	0.0714	0.0540	0.0320	0.0326
15		0	0.1159	0.1009	0.0859	0.0714	0.0540	0.0320	0.0326
20			0	0.1009	0.0859	0.0714	0.0540	0.0320	0.0326
25				0	0.0859	0.0714	0.0540	0.0320	0.0326
30					0	0.0714	0.0540	0.0320	0.0326
35						0	0.0540	0.0320	0.0326
40							0	0.0320	0.0326
45								0	0.0326



Step 4

	Area OF trapeziod	Sim. Triangle Time Value	Area under allowed	Storage
Duration	(m ³)	(min) X	flow (m ³)	(m ³)
5	74.93	0.653	18.283	56.64
10	92.35	1.059	27.268	65.08
15	104.34	1.406	36.370	67.97
20	121.13	1.615	45.741	75.39
25	128.92	1.896	54.971	73.95
30	85.63	1.615	45.741	39.89
35	80.95	1.896	54.971	25.98
REQUIRED				75.39

Therefore, below ground storage of 76m³ is required for the Cultec System.

APPENDIX E Stormceptor Design Report





Detailed Stormceptor Sizing Report – Panorama Wellness Centre

Project Information & Location				
Project Name	Project Name Panorama Wellness Centre Project Num		10113	
City	Ottawa	State/ Province	Ontario	
Country	Canada	Date 3/6/2020		
Designer Information		EOR Information (optional)		
Name	Troy Gove	Name		
Company	Company HSP Consultants Inc. Company			
Phone #	Phone # 613-932-3289 Phone #			
Email	tgove@hsp.ca	Email		

Stormwater Treatment Recommendation

The recommended Stormceptor Model(s) which achieve or exceed the user defined water quality objective for each site within the project are listed in the below Sizing Summary table.

Site Name	Site Name Panorama Wellness Centre	
Recommended Stormceptor Model	septor Model STC 750	
Target TSS Removal (%)	80.0	
TSS Removal (%) Provided	82	
PSD	Fine Distribution	
Rainfall Station	OTTAWA MACDONALD-CARTIER INT'L A	

The recommended Stormceptor model achieves the water quality objectives based on the selected inputs, historical rainfall records and selected particle size distribution.

Stormceptor Sizing Summary			
Stormceptor Model	% TSS Removal Provided		
STC 300	73		
STC 750	82		
STC 1000	83		
STC 1500	84		
STC 2000	86		
STC 3000	88		
STC 4000	90		
STC 5000	91		
STC 6000	92		
STC 9000	94		
STC 10000	94		
STC 14000	96		
StormceptorMAX	Custom		





Stormceptor

The Stormceptor oil and sediment separator is sized to treat stormwater runoff by removing pollutants through gravity separation and flotation. Stormceptor's patented design generates positive TSS removal for each rainfall event, including large storms. Significant levels of pollutants such as heavy metals, free oils and nutrients are prevented from entering natural water resources and the re-suspension of previously captured sediment (scour) does not occur. Stormceptor provides a high level of TSS removal for small frequent storm events that represent the majority of annual rainfall volume and pollutant load. Positive treatment continues for large infrequent events, however, such events have little impact on the average annual TSS removal as they represent a small percentage of the total runoff volume and pollutant load.

Design Methodology

Stormceptor is sized using PCSWMM for Stormceptor, a continuous simulation model based on US EPA SWMM. The program calculates hydrology using local historical rainfall data and specified site parameters. With US EPA SWMM's precision, every Stormceptor unit is designed to achieve a defined water quality objective. The TSS removal data presented follows US EPA guidelines to reduce the average annual TSS load. The Stormceptor's unit process for TSS removal is settling. The settling model calculates TSS removal by analyzing:

- Site parameters
- · Continuous historical rainfall data, including duration, distribution, peaks & inter-event dry periods
- Particle size distribution, and associated settling velocities (Stokes Law, corrected for drag)
- TSS load
- · Detention time of the system

Hydrology Analysis

PCSWMM for Stormceptor calculates annual hydrology with the US EPA SWMM and local continuous historical rainfall data. Performance calculations of Stormceptor are based on the average annual removal of TSS for the selected site parameters. The Stormceptor is engineered to capture sediment particles by treating the required average annual runoff volume, ensuring positive removal efficiency is maintained during each rainfall event, and preventing negative removal efficiency (scour). Smaller recurring storms account for the majority of rainfall events and average annual runoff volume, as observed in the historical rainfall data analyses presented in this section.

Rainfall Station				
State/Province	Ontario	Total Number of Rainfall Events	4093	
Rainfall Station Name	OTTAWA MACDONALD- CARTIER INT'L A	Total Rainfall (mm)	20978.1	
Station ID #	6000	Average Annual Rainfall (mm)	567.0	
Coordinates	45°19'N, 75°40'W	Total Evaporation (mm)	1504.6	
Elevation (ft)	370	Total Infiltration (mm)	4392.6	
Years of Rainfall Data	37	Total Rainfall that is Runoff (mm)	15080.9	

Notes

- Stormceptor performance estimates are based on simulations using PCSWMM for Stormceptor, which uses the EPA Rainfall and Runoff modules.
- Design estimates listed are only representative of specific project requirements based on total suspended solids (TSS) removal
 defined by the selected PSD, and based on stable site conditions only, after construction is completed.
- For submerged applications or sites specific to spill control, please contact your local Stormceptor representative for further design assistance.





Discharge (cms)

Drainage Area			
Total Area (ha)	0.476		
Imperviousness %	79.00		
Water Quality Objective			
TSS Removal (%) 80.0			
Runoff Volume Capture (%)			
Oil Spill Capture Volume (L)			
Peak Conveyed Flow Rate (L/s)			
Water Quality Flow Rate (L/s)			

0.000	0.000			
Up Stream	Flow Diversi	on		
Max. Flow to Stormce	otor (cms)			
Design Details				
Stormceptor Inlet Inve	rt Elev (m)	101.00		
Stormceptor Outlet Inve	100.95			
Stormceptor Rim E	104.00			
Normal Water Level Ele	evation (m)			
Pipe Diameter (r	nm)	300		
Pipe Materia	PVC - plastic			
Multiple Inlets (No			
Grate Inlet (Y/I	N)	No		

Up Stream Storage

Storage (ha-m)

Particle Size Distribution (PSD)

Removing the smallest fraction of particulates from runoff ensures the majority of pollutants, such as metals, hydrocarbons and nutrients are captured. The table below identifies the Particle Size Distribution (PSD) that was selected to define TSS removal for the Stormceptor design.

Fine Distribution			
Particle Diameter (microns)	Distribution %	Specific Gravity	
20.0	20.0	1.30	
60.0	20.0	1.80	
150.0	20.0	2.20	
400.0	20.0	2.65	
2000.0	20.0	2.65	






Site Name		Panorama Wellness Centre		
Site Details				
Drainage Area		Infiltration Parameters		
Total Area (ha)	0.476	Horton's equation is used to estimate infiltration		
Imperviousness %	79.00	Max. Infiltration Rate (mm/hr) 61.98		
Surface Characteristics	6	Min. Infiltration Rate (mm/hr) 10.16		
Width (m)	138.00	Decay Rate (1/sec) 0.00055		
Slope %	2	Regeneration Rate (1/sec) 0.01		
Impervious Depression Storage (mm)	0.508	Evaporation		
Pervious Depression Storage (mm)	5.08	Daily Evaporation Rate (mm/day) 2.54		
Impervious Manning's n 0.015		Dry Weather Flow		
Pervious Manning's n	0.25	Dry Weather Flow (lps) 0		
Maintenance Frequency	У	Winter Months		
Maintenance Frequency (months) > 12		Winter Infiltration 0		
	TSS Loading	g Parameters		
TSS Loading Function				
Buildup/Wash-off Parame	eters	TSS Availability Parameters		
Target Event Mean Conc. (EMC) mg/L		Availability Constant A		
Exponential Buildup Power		Availability Factor B		
Exponential Washoff Exponent		Availability Exponent C		
		Min. Particle Size Affected by Availability (micron)		





Cumulative Runoff Volume by Runoff Rate					
Runoff Rate (L/s)	Runoff Volume (m³)	Volume Over (m³)	Cumulative Runoff Volume (%)		
1	28428	43838	39.3		
4	55727	16542	77.1		
9	65308	6961	90.4		
16	69250	3020	95.8		
25	71008	1262	98.3		
36	71818	452	99.4		
49	72153	117	99.8		
64	72249	21	100.0		
81	72270	0	100.0		
100	72270	0	100.0		








Rainfall Event Analysis				
Rainfall Depth (mm)	No. of Events	Percentage of Total Events (%)	Total Volume (mm)	Percentage of Annual Volume (%)
6.35	3113	76.1	5230	24.9
12.70	501	12.2	4497	21.4
19.05	225	5.5	3469	16.5
25.40	105	2.6	2317	11.0
31.75	62	1.5	1765	8.4
38.10	35	0.9	1206	5.8
44.45	28	0.7	1163	5.5
50.80	12	0.3	557	2.7
57.15	7	0.2	378	1.8
63.50	1	0.0	63	0.3
69.85	1	0.0	64	0.3
76.20	1	0.0	76	0.4
82.55	0	0.0	0	0.0
88.90	1	0.0	84	0.4
95.25	0	0.0	0	0.0
101.60	0	0.0	0	0.0
107.95	0	0.0	0	0.0
114.30	1	0.0	109	0.5
120.65	0	0.0	0	0.0
127.00	0	0.0	0	0.0







For Stormceptor Specifications and Drawings Please Visit: http://www.imbriumsystems.com/technical-specifications