

Transportation Impact Assessment – Step 4: Analysis

1995 Carling Avenue



Document Control Page

| | |
|--------------------------|--|
| CLIENT: | Claridge Homes |
| PROJECT NAME: | 1995 Carling Avenue |
| REPORT TITLE: | Transportation Impact Assessment |
| IBI REFERENCE: | 124829 |
| VERSION: | Final |
| DIGITAL MASTER: | J:\124829_1995Carling\6.0_Technical\6.23_Traffic\03_Tech-Reports\TTR_1995Carling_MASTER_2020-03-09.docx |
| ORIGINATOR: | Eric M°Laren |
| REVIEWER: | David Hook |
| AUTHORIZATION: | Justin Date |
| CIRCULATION LIST: | Mike Giampa - City of Ottawa Transportation Project Manager |
| HISTORY: | TIA Step 1-3 Submitted for City Review – March 17, 2020 TIA Step 4 Issued to Client for Submission to City – April 13, 2020 |

TIA Plan Reports - Certification

On 14 June 2017, the Council of the City of Ottawa adopted new Transportation Impact Assessment (TIA) Guidelines. In adopting the guidelines, Council established a requirement for those preparing and delivering transportation impact assessments and reports to sign a letter of certification.

Individuals submitting TIA reports will be responsible for all aspects of development-related transportation assessment and reporting, and undertaking such work, in accordance and compliance with the City of Ottawa's Official Plan, the Transportation Master Plan and the Transportation Impact Assessment (2017) Guidelines.

By submitting the attached TIA report (and any associate documents) and signing this document, the individual acknowledges that s/he meets the four criteria listed below:

CERTIFICATION

1. I have reviewed and have a sound understanding of the objectives, needs and requirements of the City of Ottawa's Official Plan, Transportation Master Plan and the Transportation Impact Assessment (2017) Guidelines;
2. I have a sound knowledge of industry standard practice with respect to the preparation of transportation impact assessment reports, including multi modal level of service review;
3. I have substantial experience (more than 5 years) in undertaking and delivering transportation impact studies (analysis, reporting and geometric design) with strong background knowledge in transportation planning, engineering or traffic operations; and
4. I am either a licensed¹ or registered¹ professional in good standing, whose field of expertise [check appropriate field(s)] is either transportation engineering or transportation planning .

¹ License or registration body that oversees the profession is required to have a code of conduct and ethics guidelines that will ensure appropriate conduct and representation for transportation planning and/or transportation engineering works.

Dated at Ottawa this 13th day of April 2020.
(City)

Name: David Hook, P.Eng.

Professional Title: Project Engineer



Signature of Individual certifier that she/he meets the above four criteria

| |
|--|
| Office Contact Information (Please Print) |
| Address: 400-333 Preston Street |
| City / Postal Code: K1S 5N4 |
| Telephone / Extension: 613-225-1311 ext. 64029 |
| E-Mail Address: dhook@ibigroup.com |

Stamp




Table of Contents

| | |
|---|-------------|
| Executive Summary | ES-1 |
| 1 Introduction | 1 |
| 2 TIA Screening | 2 |
| 3 Project Scoping | 2 |
| 3.1 Description of Proposed Development | 2 |
| 3.1.1 Site Location | 2 |
| 3.1.2 Land Use Details..... | 2 |
| 3.1.3 Development Phasing & Date of Occupancy..... | 2 |
| 3.2 Existing Conditions | 5 |
| 3.2.1 Existing Road Network..... | 5 |
| 3.2.2 Existing Bicycle and Pedestrian Facilities..... | 10 |
| 3.2.3 Existing Transit Facilities and Service | 10 |
| 3.2.4 Collision History | 10 |
| 3.3 Planned Conditions..... | 11 |
| 3.3.1 Transportation Network..... | 11 |
| 3.3.2 Future Adjacent Developments..... | 14 |
| 3.3.3 Network Concept Screenline | 14 |
| 3.4 Study Area | 16 |
| 3.5 Time Periods..... | 16 |
| 3.6 Analysis Years | 16 |
| 3.7 Exemptions Review | 16 |
| 4 Forecasting | 18 |
| 4.1 Development Generated Traffic..... | 18 |
| 4.1.1 Trip Generation Methodology | 18 |
| 4.1.2 Trip Generation Results | 18 |
| 4.1.3 Trip Distribution and Assignment..... | 21 |
| 4.2 Background Network Traffic | 23 |

Table of Contents

| | | |
|----------|---|-----------|
| 4.2.1 | Changes to the Background Transportation Network..... | 23 |
| 4.2.2 | General Background Growth Rates | 23 |
| 4.2.3 | Other Area Development | 23 |
| 4.3 | Demand Rationalization..... | 24 |
| 4.3.1 | Description of Capacity Issues..... | 24 |
| 4.3.2 | Adjustment to Development-Generated Demands | 24 |
| 4.3.3 | Adjustment to Background Network Demands | 24 |
| 4.4 | Traffic Volume Summary | 24 |
| 4.4.1 | Future Background Traffic Volumes | 24 |
| 4.4.2 | Future Total Traffic Volumes..... | 24 |
| 5 | Analysis | 29 |
| 5.1 | Development Design..... | 29 |
| 5.1.1 | Design for Sustainable Modes | 29 |
| 5.1.2 | Circulation and Access | 29 |
| 5.1.3 | New Street Networks | 29 |
| 5.2 | Parking..... | 29 |
| 5.2.1 | Parking Supply | 29 |
| 5.2.2 | Spillover Parking | 29 |
| 5.3 | Boundary Streets | 30 |
| 5.3.1 | Mobility | 30 |
| 5.3.2 | Road Safety | 30 |
| 5.4 | Access Intersections | 31 |
| 5.4.1 | Location and Design of Access..... | 31 |
| 5.4.2 | Access Intersection Control | 32 |
| 5.4.3 | Access Intersection Design (MMLOS)..... | 32 |
| 5.5 | Transportation Demand Management (TDM)..... | 32 |
| 5.5.1 | Context for TDM..... | 32 |
| 5.5.2 | Need and Opportunity | 33 |
| 5.5.3 | TDM Program..... | 33 |

Table of Contents

| | | |
|----------|--|-----------|
| 5.6 | Neighbourhood Traffic Management | 33 |
| 5.6.1 | Adjacent Neighbourhoods..... | 33 |
| 5.7 | Transit | 33 |
| 5.7.1 | Route Capacity..... | 33 |
| 5.7.1 | Transit Priority Measures | 34 |
| 5.8 | Review of Network Concept | 34 |
| 5.9 | Intersection Design | 34 |
| 5.9.1 | Intersection Control | 34 |
| 5.9.2 | Intersection Analysis Criteria (Automobile)..... | 34 |
| 5.9.3 | Intersection Capacity Analysis | 36 |
| 5.9.4 | Intersection Design (MMLOS)..... | 42 |
| 5.10 | Geometric Review..... | 44 |
| 5.10.1 | Sight Distance and Corner Clearances..... | 44 |
| 5.10.2 | Auxiliary Lane Analysis | 44 |
| 5.11 | Summary of Recommended Modifications | 46 |
| 6 | Conclusion | 48 |

List of Tables

| | |
|--|----|
| Table 1 - Land Use Statistics | 2 |
| Table 2 - Existing Roadways | 5 |
| Table 3 - Reported Collisions within Vicinity of Proposed Development..... | 10 |
| Table 4 - Exemptions Review | 17 |
| Table 5 - Base Vehicular Trip Generation..... | 18 |
| Table 6 - Person-Trip Generation | 19 |
| Table 7 - Proposed Mode Share Targets..... | 20 |
| Table 8 – Peak Hour Person-Trips by Mode..... | 21 |
| Table 9 - Future Adjacent Developments | 23 |
| Table 10 - Segment MMLOS Results | 30 |

Table of Contents

| | |
|---|----|
| Table 11 – 2024 Development Generated Transit Demand | 33 |
| Table 12 - LOS Criteria for Signalized Intersections..... | 35 |
| Table 13 - LOS Criteria for Unsignalized Intersections..... | 36 |
| Table 14 - Intersection Capacity Analysis: Existing (2020) Traffic | 37 |
| Table 15 - Intersection Capacity Analysis: Future (2024) Background Traffic | 38 |
| Table 16 - Intersection Capacity Analysis: Future (2029) Background Traffic | 39 |
| Table 17 - Intersection Capacity Analysis: Future (2024) Total Traffic..... | 40 |
| Table 18 - Intersection Capacity Analysis: Future (2024) Total Traffic..... | 41 |
| Table 19 - Intersection MMLoS | 42 |
| Table 20 - Auxiliary Left-Turn Storage Analysis at Signalized Intersections | 45 |
| Table 21 – Auxiliary Right-Turn Lane Storage Analysis at Signalized Intersections | 46 |

List of Figures

| | |
|---|----|
| Figure 1 - Future 'Affordable RTTP Network Projects'..... | 12 |
| Figure 2 - Carling Avenue Transit Priority Corridor - Iroquois Road to Bromley Road | 12 |
| Figure 3 - Carling Avenue Transit Priority Corridor - Bromley Road to Maitland Avenue / Sherbourne Road..... | 13 |
| Figure 4 – Future Cycling Facilities within Context Area | 14 |
| Figure 5 - Screenlines | 15 |
| Figure 6 - Ottawa West TAZ | 19 |

List of Exhibits

| | |
|--|----|
| Exhibit 1 - Site Location | 3 |
| Exhibit 2 - Proposed Development | 4 |
| Exhibit 3 - Lane Configurations and Intersection Control | 8 |
| Exhibit 4 - Existing (2020) Traffic | 9 |
| Exhibit 5 - Site Generated AM & PM Peak Hour Traffic Volumes | 22 |
| Exhibit 6 - Future (2024) Background Traffic..... | 25 |

Table of Contents

| | |
|--|----|
| Exhibit 7 - Future (2029) Background Traffic | 26 |
| Exhibit 8 - Future (2024) Total Traffic | 27 |
| Exhibit 9 - Future (2029) Total Traffic | 28 |

List of Appendices

- Appendix A – City Circulation Comments
- Appendix B – Screening Form
- Appendix C – Turning Movement Counts
- Appendix D – OC Transpo Routes
- Appendix E – Collision Data
- Appendix F – Trip Generation Data
- Appendix G – TDM Checklists
- Appendix H – MMLOS Analysis
- Appendix I – Intersection Control Warrants
- Appendix J – Intersection Capacity Analyses

Executive Summary

IBI Group (IBI) was retained by Claridge Homes to undertake a Transportation Impact Assessment (TIA) in support of a combined Zoning By-law Amendment and Site Plan Control application for a proposed high-rise residential development to be located at 1995 Carling Avenue in Ottawa. The proposed development consists a 27-storey building with a total of 210 dwelling units. The development will be constructed in a single phase and is projected to be fully occupied by 2024. Access to the site will be provided via a full-movement site access driveway on Bromley Road.

The site will provide 174 vehicle parking spaces and 155 bicycle parking spaces within a six-level underground parking garage and exceeds the minimum number of parking spaces required by the Zoning By-law.

It is anticipated that prior to 2024, the outside lanes on Carling Avenue will be converted to dedicated bus lanes between Lincoln Fields Station and the Trillium Line Carling Station, reducing the number of general traffic lanes in both directions to two. In recognition of the potential impact this may have on regional traffic patterns, a -0.5% linear reduction in background traffic volumes has been considered in the development of background traffic volumes.

Two future adjacent developments were identified in the vicinity of the proposed development and considered in the development of background traffic volumes as well: 485 Ancaster Avenue, a two-tower mixed-use development near the corner of Carling Avenue & Woodroffe Avenue, and the future Carlingwood Canadian Tire which will replace the former Sears Carlingwood.

With the implementation of transit lanes on Carling Avenue it is anticipated that transit use will increase by 25% with a corresponding decrease in automobile driver and passenger mode shares. With consideration of these expected changes in mode shares, it is projected that the site will generate approximately 55 to 60 two-way vehicle-trips and 30 to 40 two-way transit-trips during the weekday morning and afternoon peak hours.

Intersection capacity analysis has revealed that the intersection of Carling Avenue & Hare Avenue will exceed its theoretical capacity by 2024 under background traffic conditions due to the planned reduction in general traffic lanes to accommodate the dedicated transit lanes. Analysis has shown that prohibiting U-turns at this intersection would allow the intersection to operate at a Level of Service of 'E' through to the horizon year of this study. Most of the U-turn demand is expected to migrate to the intersection of Carling Avenue & Iroquois Road as a result of this prohibition. It is therefore recommended that the City consider providing a westbound protected-permitted left-turn phase to improve safety at the intersection by reducing conflicts between eastbound through traffic and the increased volume of westbound U-turn traffic. The intersection of Carling Avenue & Maitland Avenue / Sherbourne Road was also shown to be approaching its theoretical capacity under Future (2024) Background Traffic conditions, however, due to space constraints no modifications to this intersection was recommended. This intersection as well as all other study area intersections were shown to operate at or below their theoretical capacity through to the study horizon year.

Based on the auxiliary lane analysis, the northbound and southbound auxiliary left-turn lanes at the intersection of Carling Avenue & Maitland Avenue / Sherbourne Road are deficient by 5m and 40m, respectively. The northbound left-turn lane deficiency is considered negligible and therefore not necessary. In the southbound direction there are practical limitations due to the intersection of Sherbourne Road & Bromley Road and as such it is not recommended that the southbound left-turn lane be extended either.

A multi-modal analysis of each study area intersection identified existing deficiencies in the road network and potential remediation measures have been suggested in which the City could consider to meet the prescribed LOS targets. These remediation measures would improve mobility and comfort for all transportation modes but are not required to accommodate the proposed development.

A review of collision recorded indicated that there was a high frequency of angle and turning movement collisions at the intersection of Carling Avenue & Iroquois Road. It is therefore recommended that the City further investigate collisions at this intersection and implement mitigation measures. It should be noted that site-generated traffic is not anticipated to significantly contribute to movements with observed safety issues.

All intersections within the study area are shown to operate under their theoretical capacities beyond the 2024 horizon year of the study and no modifications to auxiliary lanes were recommended. A post-development monitoring plan is therefore not a requirement of this study. Further, the analysis conducted indicates that no off-site intersection improvements are necessary as a direct consequence of the proposed development in order to accommodate the projected site-generated travel demands. The study therefore does not require an RMA for off-site roadworks.

Based on the findings of this study, it is the overall opinion of IBI Group that the proposed development will integrate well with and can be safely accommodated by the adjacent transportation network.

1 Introduction

IBI Group (IBI) was retained by Claridge Homes to undertake a Transportation Impact Assessment (TIA) in support of a combined Zoning By-law Amendment and Site Plan Control application for a proposed high-rise residential development to be located at 1995 Carling Avenue in Ottawa.

In accordance with the City of Ottawa's Transportation Impact Assessment Guidelines, published in June 2017, the following report is divided into four major components:

- **Screening** – Prior to the commencement of a TIA, an initial assessment of the proposed development is undertaken to establish the need for a comprehensive review of the site based on three triggers: Trip Generation, Location and Safety.
- **Scoping** – This component of the TIA report describes both the existing and planned conditions in the vicinity of the development and defines study parameters such as the study area, analysis periods and analysis years of the development. It also provides an opportunity to identify any scope exemptions that would eliminate elements of scope described in the TIA Guidelines that are not relevant to the development proposal, based on consultation with City staff.
- **Forecasting** – The Forecasting component of the TIA is intended to review both the development-generated travel demand and the background network travel demand, and provides an opportunity to rationalize this demand to ensure projections are within the capacity constraints of the transportation network.
- **Analysis** – This component documents the results of any analyses undertaken to ensure that the transportation related features of the proposed development are in conformance with prescribed technical standards and that its impacts on the transportation network are both sustainable and effectively managed. It also identifies a development strategy to ensure that what is being proposed is aligned with the City of Ottawa's city-building objectives, targets and policies.

Throughout the development of a TIA report, each of the four study components above are submitted in draft form to the City of Ottawa and undergo a review by a designated Transportation Project Manager. Any comments received are addressed to the satisfaction of the City's Transportation Project Manager before proceeding with subsequent components of the study. All technical comments and responses throughout this process are included in **Appendix A**.

2 TIA Screening

An initial screening was completed to confirm the need for a Transportation Impact Assessment by reviewing the following three triggers:

- **Trip Generation:** Based on the proposed number of apartment dwelling units, the minimum development size threshold has been exceeded and therefore the Trip Generation trigger is satisfied.
- **Location:** The proposed development is located within a Design Priority Area (DPA) and, as such, the Location trigger is satisfied.
- **Safety:** Boundary street conditions were reviewed to determine if there is an elevated potential for safety concerns adjacent the site. Based on this review, the Safety Trigger is not satisfied.

As the proposed development meets the Trip Generation and Location triggers, the need to undertake a Transportation Impact Assessment is confirmed.

A copy of the Screening Form is provided in **Appendix B**.

3 Project Scoping

3.1 Description of Proposed Development

3.1.1 Site Location

The proposed development is located within the Carlingwood community and is approximately 0.14 hectares in size. It is bound by Carling Avenue to the south, Bromley Road to the east, the Bromley Square residential tower to the west, and low-density residential to the north.

The site location and its surrounding context is illustrated in **Exhibit 1**.

3.1.2 Land Use Details

The subject site is currently occupied by two residential dwellings and is zoned AM10 – Arterial Mainstreet, based on GeoOttawa.

The proposed development includes a single 27-storey tower with six levels of underground parking. **Table 1** summarizes the proposed land uses included in this development.

Table 1 - Land Use Statistics

| LAND USE | SIZE |
|------------|--------------------|
| Apartments | 210 dwelling units |


The site will provide 174 vehicle parking spaces and 155 bicycle parking spaces within the six-level underground parking facility. Access to the site will be provided via a two-way private approach on Bromley Road.

The configuration of the proposed development is illustrated in **Exhibit 2**.

3.1.3 Development Phasing & Date of Occupancy

The proposed development is anticipated to be constructed and fully occupied by the end of 2024.





1995 Carling Avenue
Transportation Impact Assessment

Exhibit 2:
Proposed Development

PROJECT No. 124829
DATE: April 2020
SCALE: 0m 5m 10m



3.2 Existing Conditions

3.2.1 Existing Road Network

3.2.1.1 Roadways

The proposed development is bound by Carling Avenue to the south and Bromley Road to the east. **Table 2** below summarizes the details of the boundary roadways as well as other streets within the context area of the proposed development.

Table 2 - Existing Roadways

| NAME | CLASS | JURISDICTION | ORIENTATION AND EXTENTS | CROSS-SECTION | RIGHT-OF-WAY | SPEED LIMIT |
|-----------------|-----------------|----------------|---|------------------------|--------------|-------------|
| Carling Avenue | Arterial | City of Ottawa | East-West, from March Road to Bronson Avenue | Urban Six-Lane Divided | 44.5m | 60 km/h |
| Maitland Avenue | Arterial | City of Ottawa | North-South, from Carling Avenue to Clyde Avenue | Urban Four-Lane | 26.0m | 50 km/h |
| Sherbourne Road | Major Collector | City of Ottawa | North-South, from Byron Avenue to Carling Avenue | Urban Two-Lane | 30.5m | 50 km/h |
| Iroquois Road | Local | City of Ottawa | North-South, from Prince Charles Road to Strathmore Boulevard | Urban Two-Lane | 20.0m | 40 km/h |
| Bromley Road | Local | City of Ottawa | East-West, from Carling Avenue to east of Sherbourne Road | Urban Two-Lane | 20.0m | 50 km/h |
| Hare Avenue | Local | City of Ottawa | North-South, from Carling Avenue to Killarney Drive | Urban Two-Lane | 21.5m | 50 km/h |

3.2.1.2 Nearby Driveways

On Bromley Road, there are currently two driveways near the proposed development: the loading access driveway for the adjacent Bromley Square apartment building and the McKellar Park Suites driveway. Approximately 60m north of Carling Avenue, permanent bollards are in place across Bromley Road to restrict cut-through traffic in the adjacent residential community.

On Carling Avenue, within 200m of the proposed development are the two main accesses for the Bromley Square apartment building and the accesses for the neighbouring Carling Terrace condominium building. Each of these driveways provide one-way right-in or right-out access to the adjacent developments.

3.2.1.3 Intersections

The following intersections have the greatest potential to be impacted by the proposed development:



- **Carling Avenue & Iroquois Road** is a four-legged signalized intersection with right-turn channels provided on the eastbound and westbound approaches and left-turn lanes on all approaches except for the northbound approach. This intersection is located approximately 415 metres west of the site.



- **Carling Avenue & Hare Avenue** is a three-legged two-way stop-controlled intersection with free-flow on Carling Avenue. A median break permits left-turns at this intersection and a westbound left-turn lane has been provided on Carling Avenue. This intersection is located approximately 215 metres west of the site.



- **Carling Avenue & Bromley Road** is a three-legged two-way stop-controlled intersection with free-flow on Carling Avenue. Turning movements are restricted to right-in/right-out due to the presence of a median on Carling Avenue.



- **Carling Avenue & Maitland Avenue / Sherbourne Road** is a four-legged signalized intersection with single auxiliary left-turn lanes on the eastbound, northbound and southbound approaches and a double left-turn auxiliary lane on the westbound approach. This intersection is located approximately 450 metres east of the site.

The intersection control and lane configurations for all intersections described above are shown in **Exhibit 3**.

3.2.1.4 Traffic Management Measures

The following traffic management measures have been implemented within the context area of the proposed development:

- Bollards have been installed across Bromley Road approximately 60m north of Carling Avenue to restrict neighbourhood cut-through traffic.
- Pavement markings indicating to vehicles to slow down have been provided on Hare Avenue.
- On-road speed limit pavement markings have been provided on Iroquois Road south of Carling Avenue.

3.2.1.5 Existing Traffic Volumes

As the proposed development will consist of residential land uses, the weekday peak hour traffic conditions will be most affected by any associated increase in traffic. Weekday morning and afternoon peak hour turning movement counts were therefore obtained from the City of Ottawa at the following intersections:

- Carling Avenue & Iroquois Road (City of Ottawa, May 2017)
- Carling Avenue & Maitland Avenue / Sherbourne Road (City of Ottawa, March 2017)

It should be noted that a major retailer within the vicinity of the proposed development (Sears Carlingwood) closed for business in early 2018. Traffic associated with this retailer remains accounted for in the volumes analyzed in this study. As will be discussed in subsequent sections of this study, this retail space will be replaced with another major anchor tenant to the Carlingwood Shopping Centre (Canadian Tire) and is expected to be open for business in 2021.

Supplemental sidestreet traffic counts were conducted by IBI Group at the following two intersections:

- Carling Avenue & Hare Avenue (IBI Group, March 2020)
- Carling Avenue & Bromley Road (IBI Group, March 2020)

Peak hour traffic volumes representative of existing conditions are shown in **Exhibit 4**. Weekday morning and afternoon peak hour turning movement counts have been provided in **Appendix C**.



Sherbourne Road


Maitland Avenue

Bromley Road

Carling Avenue

Hare Avenue

Iroquois Road



Legend

- Stop Sign
- Traffic Signal
- Lane Configurations
- Storage Lengths
- (C) Channelized Right-Turn

PROJECT No. 124829
 DATE: April 2020
 SCALE: N.T.S.

Exhibit 3:
 Lane Configuration
 and Intersection Control

1995 Carling Avenue
 Transportation Impact Assessment






Exhibit 4:
Existing (2020)
Traffic

PROJECT No. 124829
DATE: April 2020
SCALE: N.T.S.

3.2.2 Existing Bicycle and Pedestrian Facilities

Pedestrian facilities within the context area are provided in the form of sidewalks on both sides of most roadways. The exceptions are Bromley Road, Hare Avenue and Iroquois Road south of Carling Avenue which presently do not have any pedestrian facilities.

The only cycling facilities provided within the context area are bicycle lanes on both sides of Sherbourne Road. All other roadways require cyclists to share the road with motorists.

3.2.3 Existing Transit Facilities and Service

The following transit route, operated by OC Transpo, exists within the vicinity of the site:

- **Route #85** provides regular, all-day service between Bayshore Station and Terrasses de la Chaudière in Gatineau, operating on 15-minute headways during peak periods. On weekends, service is reduced to between 15- and 30-minute headways.

The nearest westbound bus stop serving Route #85 is located at the front entrance to Bromley Square, approximately 55m west of the proposed development. The nearest accessible eastbound bus stop is at the intersection of Carling Avenue & Iroquois, located at a walking distance of approximately 440m west of the proposed development. An existing eastbound bus stop is provided on Carling Avenue across from Bromley Square (Carling Avenue / Melwood Avenue) however there are no safe pedestrian crossings on Carling Avenue in the vicinity of this bus stop.

Within the study area, transit priority measures are limited to a queue jump lane after the right-turn lane on the westbound approach of the Carling Avenue & Iroquois Road intersection.

The transit map for Route #85 is provided in **Appendix D**.

3.2.4 Collision History

A review of historical collision data has been undertaken for the boundary streets with the vicinity of the proposed development. The TIA Guidelines require a safety review if at least six collisions for any one movement or of a discernible pattern, have occurred over a five-year period. **Table 3** summarizes all reported collisions between January 1, 2014 and December 31, 2018.

Table 3 - Reported Collisions within Vicinity of Proposed Development

| LOCATION | # OF REPORTED COLLISIONS |
|--|--------------------------|
| INTERSECTIONS | |
| Carling Avenue & Iroquois Road | 33 |
| Carling Avenue & Hare Avenue | 6 |
| Carling Avenue & Bromley Road | 2 |
| Carling Avenue & Maitland Avenue / Sherbourne Road | 63 |
| SEGMENTS | |
| Carling Avenue – Iroquois Road to Hare Avenue | 1 |
| Carling Avenue – Hare Avenue to Bromley Road | 6 |
| Carling Avenue – Bromley Road to Maitland Avenue / Sherbourne Road | 9 |

Based on a preliminary review of the collision history noted above, intersection and road segments with at least six collisions over the five-year period may require further review.

Detailed collision records are provided in **Appendix E**.

Another method of evaluating the relative magnitude of collision frequency at one intersection compared to another is to quantify the average historical number of collisions against the daily volume of traffic entering the intersection. This is commonly expressed in terms of average collisions per year per Million Vehicles Entering (MVE) and a rate of greater than 1.0 is considered significant. Average annual daily traffic (AADT) volumes are provided with all City-provided traffic counts. The intersection of Carling Avenue & Iroquois and Carling Avenue & Maitland Avenue / Sherbourne Road are therefore calculated as having average collision frequencies of 0.70 collisions per MVE and 0.79 collisions per MVE, respectively.

3.3 Planned Conditions

3.3.1 Transportation Network

3.3.1.1 Future Road Network Projects

The 2013 Transportation Master Plan (TMP) outlines future road network modifications required in the 2031 'Affordable Network'. A review of the TMP Affordable Plan indicates that there are no planned changes to the arterial road network within the broader area surrounding the proposed development.


3.3.1.2 Future Transit Facilities and Services

The 2013 TMP outlines the future rapid transit and transit priority (RTTP) network. The following project was noted in the 'Affordable RTTP Network' that may have a significant impact on future travel demand in the vicinity of the proposed development:

- **Carling Avenue Transit Priority Corridor (Continuous Lanes):** Based on the TMP, continuous bus lanes are planned between Lincoln Fields Station and the Trillium Line Carling Station. Isolated transit priority measures (e.g. queue jump lanes, transit priority signals, etc.) will be provided on Carling Avenue beyond those stations. A Planning and Functional Design Study was initiated in February 2017 for this project. The current plans indicate that within the context area of the proposed development, the outside lanes on Carling Avenue will be converted to dedicated bus lanes and cyclists will be permitted to use these lanes as well. According to City of Ottawa staff, these transit priority measures are expected to be implemented prior to 2024.


Figure 1 illustrates the transit infrastructure projects in the vicinity of the proposed development that are part of the TMP's 2031 Affordable Network. **Figure 2** and **Figure 3** illustrate the currently proposed transit priority measures within the context area of the proposed development.

Figure 1 - Future 'Affordable RTPP Network Projects'




Source: 2013 Transportation Master Plan – Map 5 '2031 Affordable Network'

Figure 2 - Carling Avenue Transit Priority Corridor - Iroquois Road to Bromley Road



Source: <https://ottawa.ca/en/city-hall/public-engagement/projects/carling-avenue-transit-priority-measures>

Figure 3 - Carling Avenue Transit Priority Corridor - Bromley Road to Maitland Avenue / Sherbourne Road




Source: <https://ottawa.ca/en/city-hall/public-engagement/projects/carling-avenue-transit-priority-measures>

3.3.1.3 Future Cycling and Pedestrian Facilities

The 2013 Ottawa Cycling Plan (OCP) designates Carling Avenue and Maitland as ‘Spine Routes’, which form part of a system linking the commercial, employment, institutional, residential and educational nodes throughout the city. As shown on **Figure 4**, Sherbourne Road and Iroquois Road are designated as ‘Local Routes’, providing connections between ‘Spine Routes’ and ‘Major Pathways’.

The OCP does not indicate any specific improvements on any of the context area roadways, however, the current plans for the Carling Avenue Transit Priority Corridor indicate that cyclists will be permitted to use the dedicated bus lanes on Carling Avenue.

Figure 4 – Future Cycling Facilities within Context Area



Source: GeoOttawa

The 2013 Ottawa Pedestrian Plan (OPP) indicates that within the context area the only planned improvement to pedestrian facilities is the implementation of a sidewalk on the west side of Sherbourne Road (Phase 2: 2020-2025).

3.3.2 Future Adjacent Developments

The City of Ottawa Transportation Impact Assessment (TIA) Guidelines specify that all significant developments proposed within the surrounding area which are likely to occur within the study's horizon year must be identified and taken into consideration in the development of future background traffic projections.

There are currently only two significant development applications in the vicinity of the proposed development:

- **485 Ancaster Avenue** is a proposed residential development consisting of one 4-storey building and one 22-storey building with ground floor commercial space.
- **Carlingwood Canadian Tire** is a proposed major retail store which will replace the former Sears store at the Carlingwood Shopping Centre and is expected to be open by 2021. It shall be noted that Sears closed in January 2018 and was demolished in March 2019.

There are currently no other significant development applications within the context area that are either in the development application approval process, have already been approved and in pre-construction or are currently under construction.

3.3.3 Network Concept Screenline


A screenline is an artificial boundary between areas of major traffic generation that captures all significant points of entry from one area to another to compare crossing demand with the available roadway capacity. Screenlines are typically located along geographical barriers such as rivers, rail lines or within the greenbelt. To capture existing flow and model future demand, count stations are established by the City of Ottawa at each crossing point along the screenline.

The nearest strategic planning screenlines adjacent to the development have been identified:

- **SL24 – Western Parkway** – This is the nearest north/south screenline that would capture trips from the proposed development heading towards Ottawa’s west end, and it roughly follows the Transitway alignment from Lincoln Fields Station to Baseline Station. The screenline has four crossing points: Richmond Road, Carling Avenue, Highway 417 and Iris Street.
- **SL27, SL28 and SL28 – O-Train South, Centre and North** – These are the nearest north/south screenlines that would capture trips from the proposed development heading towards downtown Ottawa, and they roughly follow the Trillium Line alignment from the Ottawa River to Heron Road. These screenlines have nine crossing points: Sir John A. Macdonald Parkway, Scott Street, Somerset Street, Gladstone Avenue, Highway 417, Beech Street, Carling Avenue, Prince of Wales Drive and Colonel By Drive.
- **SL2** – This is the nearest east/west screenline that would capture trips from the proposed development crossing over to Gatineau and captures all traffic crossing the Ottawa River via the Champlain Bridge.

SL2, SL 24, SL27, SL28 and SL29 are shown in **Figure 5**, as determined from the City of Ottawa’s *Road Network Development Report (2013)*, a supporting document to the 2013 Transportation Master Plan (TMP). A review of the above-noted screenlines may be required in the Analysis component of this study.

Figure 5 - Screenlines



Source: TRANS Screenline System (2010)

3.4 Study Area

With consideration of the information presented thus far, the following intersections have been identified as being most impacted by the proposed development and will be assessed for vehicular capacity as part of this study:

- Carling Avenue & Iroquois Road
- Carling Avenue & Hare Avenue
- Carling Avenue & Bromley Road
- Carling Avenue & Maitland Avenue / Sherbourne Road

Multi-Modal Level of Service (MMLOS) will be conducted for all intersections listed above with the exception of the stop-controlled intersections as no methodology currently exists for evaluating MMLOS at unsignalized intersections. The need to provide alternative means of traffic control (i.e. signals) at the stop-controlled intersections will be reviewed in the Analysis component of this study to determine whether signals are warranted or required operationally within the horizon year of this study.

Additional MMLOS analysis will be conducted for the relevant boundary street segments, which in this case is limited to the segments of Carling Avenue and Bromley Road adjacent to the proposed development.

3.5 Time Periods

Based on the proposed residential land use, traffic generated during the weekday morning and afternoon peak hour is expected to result in the most significant impact to traffic operations on the adjacent road network in terms of combined development-generated and background traffic. These two time periods will therefore be considered for operational analysis in this study.

3.6 Analysis Years

Based on the anticipated build-out year of the proposed development, the following two analysis years will be considered in this TIA:

- Year 2024 – Full Build-Out of the Proposed Development
- Year 2029 – 5 Years Beyond Full Build-out / Occupancy

3.7 Exemptions Review

The TIA Guidelines provide exemption considerations for elements of the Design Review and Network Impact components. **Table 4** summarizes the TIA modules that are not applicable to this study.

Table 4 - Exemptions Review

| TIA MODULE | ELEMENT | EXEMPTION CONSIDERATIONS | REQUIRED |
|--------------------------------------|-------------------------------|--|----------|
| DESIGN REVIEW COMPONENT | | | |
| 4.1 Development Design | 4.1.2 Circulation and Access | <ul style="list-style-type: none"> Only required for site plans | ✓ |
| | 4.1.3 New Street Networks | <ul style="list-style-type: none"> Only required for plans of subdivision | ✗ |
| 4.2 Parking | 4.2.1 Parking Supply | <ul style="list-style-type: none"> Only required for site plans | ✓ |
| | 4.2.2 Spillover Parking | <ul style="list-style-type: none"> Only required for site plans where parking supply is 15% below unconstrained demand | ✗ |
| NETWORK IMPACT COMPONENT | | | |
| 4.5 Transportation Demand Management | All Elements | <ul style="list-style-type: none"> Not required for site plans expected to have fewer than 60 employees and/or students on location at any given time | ✓ |
| 4.6 Neighbourhood Traffic Management | 4.6.1 Adjacent Neighbourhoods | <ul style="list-style-type: none"> Only required when the development relies on local or collector streets for access and total volumes exceed ATM capacity thresholds | ✓ |
| 4.8 Network Concept | n/a | <ul style="list-style-type: none"> Only required when proposed development generates more than 200 person-trips during the peak hour in excess of the equivalent volume permitted by established zoning | ✗ |

4 Forecasting

4.1 Development Generated Traffic

4.1.1 Trip Generation Methodology

Peak hour site-generated traffic volumes were developed using the 2009 TRANS Trip Generation Residential Trip Rates Study Report. The TRANS trip generation rates are based on a blended rate derived from 17 trip generation studies undertaken in 2008, the ITE Trip Generation Manual and the 2005 TRANS Origin-Destination (O-D) Travel Survey. Separate trip generation rates exist for each of the four general geographic areas in Ottawa: Core, Urban (Inside the Greenbelt), Suburban (Outside the Greenbelt) and Rural. These trip generation rates reflect existing travel behavior by dwelling type and geographic area. The TIA Guidelines recommend that the TRANS trip generation rates be converted to person-trips based on the vehicular mode share proportions detailed in the TRANS Trip Generation study. Person-trips were then subdivided based on representative mode share percentages applicable to the study area to determine the number of vehicle, transit, pedestrian, cycling and other trip types.

4.1.2 Trip Generation Results

4.1.2.1 Vehicle Trip Generation

Weekday peak hour vehicular traffic volumes associated with the subject development were determined using the trip generation rates published in the TRANS Trip Generation study.

The base vehicular trip generation for the proposed development has been summarized in **Table 5**.

Table 5 - Base Vehicular Trip Generation

| LAND USE | SIZE | PERIOD | GENERATED TRIPS (VPH) | | |
|---------------------|-----------|--------|-----------------------|-----|-------|
| | | | IN | OUT | TOTAL |
| High-Rise Apartment | 210 units | AM | 12 | 39 | 51 |
| | | PM | 35 | 22 | 57 |

Note: vph = Vehicles Per Hour

Source: TRANS Trip Generation Residential Trip Rates, August 2009

4.1.2.2 Person Trip Generation

The person-trip to vehicle-trip conversion factors for TRANS trip generation rates vary depending on the peak hour, geographic location and land use considered. The base vehicular trip generation values from the previous section were divided by the vehicle mode shares to determine the number of person-trips generated.

The resulting number of person-trips have been summarized in **Table 6**.

Table 6 - Person-Trip Generation


| LAND USE | AUTO MODE SHARE | PERIOD | PERSON TRIPS (PPH) | | |
|---------------------|-----------------|--------|--------------------|-----|-------|
| | | | IN | OUT | TOTAL |
| High-Rise Apartment | 37% | AM | 33 | 105 | 138 |
| | 40% | PM | 88 | 55 | 143 |

Notes: pph = persons per hour

4.1.2.3 Mode Share Proportions

The 2011 TRANS Origin-Destination (O-D) Survey provides approximations of the existing modal share within the Ottawa West Traffic Assessment Zone (TAZ). The extents of the Ottawa West TAZ are illustrated in **Figure 6**. Relevant extracts from the 2011 O-D Survey are provided in **Appendix F**.

Figure 6 - Ottawa West TAZ



Source: 2011 TRANS O-D Survey

The proposed weekday morning and afternoon mode share targets were developed by calculating the weighted average ‘AM From’ and ‘AM Within’, and ‘PM To’ and ‘PM Within’ mode shares of the Ottawa West TAZ from the 2011 O-D Survey, respectively. The dedicated bus lanes along Carling Avenue are expected to be implemented prior to 2024 and as such adjustments have been made to account for the anticipated increase in transit demand. The Transportation Master Plan (TMP) indicates that by 2031 the goal is for 28% and 21% of trips from and to the inner suburbs to be transit-trips during the weekday morning and afternoon peak hours, respectively. This corresponds to a 17% to 31% increase in transit mode share. As such, the transit mode share targets for the proposed development have been increased by a factor of 25% (i.e. transit mode share target = 1.25 * existing transit mode share) to account for the expected increase in transit ridership. This increase in transit mode share is expected to result in a corresponding decrease in auto driver and auto passenger mode shares. It has been conservatively assumed that other non-auto mode shares (i.e. walking, cycling and other) will remain the same through to the horizon year of this study.

The existing mode shares and the mode share targets for the proposed development are outlined in **Table 7**.

Table 7 - Proposed Mode Share Targets

| TRAVEL MODE | EXISTING MODE SHARES ¹ | | | | | | MODE SHARE TARGETS | |
|----------------|-----------------------------------|-------|-----------|---------|-------|-----------|--------------------|-----|
| | AM FROM | AM TO | AM WITHIN | PM FROM | PM TO | PM WITHIN | AM | PM |
| Auto Driver | 46% | 51% | 33% | 55% | 53% | 32% | 38% | 41% |
| Auto Passenger | 11% | 15% | 15% | 16% | 14% | 10% | 11% | 11% |
| Transit | 31% | 23% | 4% | 21% | 24% | 4% | 28% | 20% |
| Cycling | 6% | 3% | 6% | 3% | 6% | 7% | 6% | 6% |
| Walking | 4% | 3% | 33% | 3% | 3% | 45% | 13% | 20% |
| Other | 2% | 5% | 8% | 2% | 1% | 2% | 4% | 1% |

Notes:

¹ 2011 TRANS O-D Survey for the Ottawa West Traffic Assessment Zone

4.1.2.4 Trip Reduction Factors

Deduction of Existing Development Trips

Not Applicable: The residences on the proposed development lands are currently vacant and thus do not generate any traffic.

Pass-by Traffic

Not Applicable: The proposed development is residential and will not generate pass-by traffic.

Synergy/ Internalization

Not Applicable: The proposed development will include only residential land uses, therefore internalization reduction factors are not applicable.

4.1.2.5 Trip Generation by Mode

The mode share targets presented above were applied to the number of development-generated person-trips to establish the number of trips per travel mode, as summarized in **Table 8**.

Table 8 – Peak Hour Person-Trips by Mode

| MODE | AM Peak Hour | | | PM Peak Hour | | |
|----------------|--------------|------------|------------|--------------|-----------|------------|
| | IN | OUT | TOTAL | IN | OUT | TOTAL |
| Auto Driver | 13 | 40 | 53 | 36 | 23 | 59 |
| Auto Passenger | 4 | 12 | 16 | 10 | 6 | 16 |
| Transit | 9 | 29 | 38 | 18 | 11 | 29 |
| Cycling | 2 | 6 | 8 | 5 | 3 | 8 |
| Walking | 4 | 14 | 18 | 18 | 11 | 29 |
| Other | 1 | 4 | 5 | 1 | 1 | 2 |
| Total | 33 | 105 | 138 | 88 | 55 | 143 |

Based on the above, the proposed development is expected to generate up to 59 two-way vehicular trips and 38 two-way transit trips during the weekday peak hours.

4.1.3 Trip Distribution and Assignment

Consistent with the Ottawa West TAZ origin-destination distribution, site-generated vehicle trips are distributed in accordance with the following distribution. Assignment to specific routes was based on engineering judgement and an analysis of Google Maps travel times during peak hour conditions.

- 65% to/from the East
 - 45% via Sir John A. MacDonald Parkway
 - 45% via Highway 417
 - 10% via Carling Avenue
- 15% to/from the West
 - 65% via Carling Avenue
 - 35% via Highway 417
- 20% to/from the South
 - 100% to the South via Woodroffe Avenue
 - 100% from the South via Maitland Avenue

Utilizing the estimated number of new auto trips and applying the above distribution, future site-generated traffic volumes are illustrated for each of the study area intersections in **Exhibit 5**.



Sherbourne Road


Maitland Avenue

Bromley Road

Carling Avenue

Hare Avenue

Iroquois Road



LEGEND

Permitted Movements
 xxx (xxx)
 xxx (xxx)
 xxx (xxx)

Exhibit 5:
Site-Generated
AM & PM Peak Hour
Traffic Volumes

PROJECT No. 124829
DATE: April 2020
SCALE: N.T.S.

1995 Carling Avenue
Transportation Impact Assessment

4.2 Background Network Traffic

4.2.1 Changes to the Background Transportation Network

To properly assess future traffic conditions, planned modifications to the transportation network that may impact travel patterns or demand within the study area have been considered. The Scoping section of this report summarized the anticipated changes to the study area transportation network based on the Transportation Master Plan (TMP) and determined that within the study area, the outside lanes on Carling Avenue will be converted to dedicated bus lanes prior to the 2024 analysis year. It is unknown, however, what impact the dedicated bus lanes will have on regional traffic patterns. As such, it has been conservatively assumed that there will be no impact background traffic volumes as a result of the reduction in general traffic capacity from three to two lanes per direction.

The OCP and OPP were also reviewed for cycling and pedestrian network projects. With the exception of the dedicated bus lanes which cyclists will be permitted to use as well, there are currently no planned changes to the pedestrian or cyclist networks. It is assumed that this will have a negligible impact on background traffic volumes.

4.2.2 General Background Growth Rates

The background growth rate is intended to represent any regional growth from outside the study area that will travel along the adjacent road network. Based on the supporting traffic studies of the future adjacent developments previously discussed, traffic volumes within the study area are expected to decrease linearly by approximately 0.5% to 1.0% per year. It is therefore assumed that there will be no growth in traffic within the horizon year of this study. Traffic generated by known future adjacent developments has been accounted for separately in this analysis.

4.2.3 Other Area Development

Future adjacent developments in the vicinity of the proposed development have been identified previously in the Scoping section of this report. **Table 9** summarizes the land use details and expected build-out year of these future adjacent developments.

Table 9 - Future Adjacent Developments

| DEVELOPMENT | LAND USE | EXPECTED BUILD-OUT YEAR |
|---------------------------|--|-------------------------|
| 485 Ancaster Avenue | <ul style="list-style-type: none"> • 290 High-Rise Condominium Units • 1,073m² Commercial Space | 2022 |
| Carlingwood Canadian Tire | <ul style="list-style-type: none"> • 14,949m² Home Improvement Store | 2021 |

The proposed development at 485 Ancaster Avenue is located approximately 900 metres west of the site and has been considered in the estimation of future background volumes. Any traffic associated with this development within the context area of this study has only a minimal impact.

As previously mentioned, the traffic data used in this study was collected prior to the closing of Sears Carlingwood. As such, the net increase in traffic volumes associated with the proposed Canadian Tire has been considered in the development of future background volumes.

4.3 Demand Rationalization

The purpose of this section is to rationalize future travel demands within the study area to account for potential capacity limitations in the transportation network and its ability to effectively accommodate the additional demand generated by a new development.

4.3.1 Description of Capacity Issues

A Public Open House (POH) was held for the Carling Avenue Transit Priority Measures project in February 2017. Display boards from this POH noted that the intersection of Carling Avenue & Maitland Avenue / Sherbourne Road may operate at capacity (i.e. Level of Service 'E') once the transit priority measures have been implemented as a result of a reduction in the number of general traffic lanes in each direction. There are no other documented records of existing or future capacity issues at any of the other study area intersections.

4.3.2 Adjustment to Development-Generated Demands

The development of the proposed mode share targets considered both the existing local mode shares and the expected increase in transit demand as a result of the planned transit priority measures. As such, no further adjustments to development-generated demand is necessary.

4.3.3 Adjustment to Background Network Demands

As discussed previously, although the implementation of dedicated bus lanes on Carling Avenue will result in a reduction in vehicular capacity on Carling Avenue its impact on regional traffic patterns is unknown. Based on information presented in studies associated with nearby adjacent developments, there is evidence to support negative growth in traffic within the study area. In recognition of planned transit priority measures, an annual background growth rate of -0.5% can be expected and has therefore been considered in the future background traffic projections for this study.

4.4 Traffic Volume Summary

4.4.1 Future Background Traffic Volumes

Future background traffic volumes have been established through the application of growth rates to through movements on Carling Avenue and all movements at the intersection of Carling Avenue & Maitland Avenue / Sherbourne Road, and by superimposing these adjusted traffic volumes with future adjacent development traffic volumes.

Exhibit 6 and **Exhibit 7** present the future background traffic volumes anticipated for the 2024 and 2029 analysis years, respectively.

4.4.2 Future Total Traffic Volumes

Future total traffic volumes have been established by combining the site-generated traffic volumes with the future background traffic volumes.

Exhibit 8 and **Exhibit 9** present the future total traffic volumes anticipated for the 2024 and 2029 analysis years, respectively.



Sherbourne Road


Maitland Avenue

Bromley Road

Carling Avenue

Hare Avenue

Iroquois Road



LEGEND

Permitted Movements
 Weekday AM (PM) Peak
 Hour Vehicular Volume

PROJECT No. 124829
 DATE: April 2020
 SCALE: N.T.S.

Exhibit 6:
 Future (2024)
 Background Traffic



Sherbourne Road


Maitland Avenue

Bromley Road

Carling Avenue

Hare Avenue

Iroquois Road



LEGEND

Permitted Movements
 Weekday AM (PM) Peak
 Hour Vehicular Volume

PROJECT No. 124829
 DATE: April 2020
 SCALE: N.T.S.

Exhibit 7:
 Future (2029)
 Background Traffic

1995 Carling Avenue
 Transportation Impact Assessment





Sherbourne Road


Maitland Avenue

Bromley Road

Carling Avenue

Hare Avenue

Iroquois Road



LEGEND

| | |
|--|-----------------------|
| | Permitted Movements |
| | Weekday AM (PM) Peak |
| | Hour Vehicular Volume |
| | xxx (xxx) |
| | xxx (xxx) |
| | xxx (xxx) |

PROJECT No. 124829
 DATE: April 2020
 SCALE: N.T.S.

Exhibit 8:
 Future (2024)
 Total Traffic

1995 Carling Avenue
 Transportation Impact Assessment



Sherbourne Road


Maitland Avenue

Bromley Road

Carling Avenue

Hare Avenue

Iroquois Road



LEGEND

Permitted Movements
 Weekday AM (PM) Peak
 Hour Vehicular Volume
 xxx (xxx)
 xxx (xxx)
 xxx (xxx)

PROJECT No. 124829
 DATE: April 2020
 SCALE: N.T.S.

Exhibit 9:
 Future (2029)
 Total Traffic

1995 Carling Avenue
 Transportation Impact Assessment

5 Analysis

5.1 Development Design

5.1.1 Design for Sustainable Modes

For consistency with the City of Ottawa’s Urban Design Guidelines and transportation policies, new developments shall provide safe and efficient access for all users, while creating an environment that encourages walking, cycling and transit use.

The proposed development is located adjacent to Carling Avenue which will have dedicated bus lanes in both directions prior to the 2024 buildout year, thereby improving the convenience and reliability of transit service along this corridor. Currently, the nearest westbound and eastbound bus stops are 55m and 440m west of the proposed development, respectively. As such, the proposed development is only 40m short of meeting OC Transpo’s service design guidelines of providing peak period service within a five minute (400m) walk of residences.

The TDM-Supportive Development Design and Infrastructure Checklist was completed and is provided in **Appendix G**. This checklist identifies specific measures that are being considered in association with the proposed development to offset the vehicular impact on the adjacent road network.

5.1.2 Circulation and Access

All site-generated traffic will access the proposed development via a two-way private approach on Bromley Road. Within the underground parking facility, all drive aisles will be a minimum of 6.0m wide.

All pick-up and drop-offs activities, loading and waste collection will occur on Bromley Road. The pedestrian access has been oriented to facilitate this on Bromley Road and to discourage these activities from occurring on Carling Avenue within the dedicated bus lane. In order to accommodate these activities, it is recommended that on-street parking be permitted on Bromley Road adjacent to the proposed development.

5.1.3 New Street Networks

Not Applicable: The New Street Networks element is exempt from this TIA, as defined in the study scope. This element is not required for development applications involving site plans.

5.2 Parking

5.2.1 Parking Supply

Six levels of underground parking will be provided with a total of 168 vehicle parking spaces and 155 bicycle parking spaces.

Based on the number of residential units proposed and the provisions for Area X of the Zoning By-law, a minimum of 89 vehicle parking spaces, 20 visitor parking spaces and 105 bicycle parking spaces must be provided by the proposed development. The proposed parking supply therefore exceeds the Zoning Bylaw requirements.

5.2.2 Spillover Parking

The minimum parking supply requirement has been met, therefore, no further review of parking will be necessary for the purposes of this study.

5.3 Boundary Streets

There are two existing boundary streets adjacent to the proposed development: Carling Avenue and Bromley Road. As there are plans to make Carling Avenue a ‘Complete Street’ through the implementation of transit lanes, Multi-Modal Level of Service (MMLOS) analysis has been conducted for Bromley Road only.

5.3.1 Mobility

Segment-based Multi-Modal Level of Service (MMLOS) results for Bromley Road along the proposed development frontage are provided in **Table 10** below.

Details of the Multi-Modal Level of Service (MMLOS) analysis are provided in **Appendix H**.

Table 10 - Segment MMLOS Results

| LOCATION | LEVEL OF SERVICE BY MODE | | | |
|-----------------|--------------------------|-------------------------|-------------------------|---------------------------|
| | PEDESTRIAN (PLOS) | BICYCLE (BLOS) | TRANSIT (TLOS) | TRUCK (TkLOS) |
| SEGMENTS | | | | |
| Bromley Road | F (Target: C) | B (Target: D) | D (Target: D) | B (Target: N/A) |

The results of the Segment MMLOS indicate that Bromley Road is not currently meeting its PLOS target. The City may wish to consider providing a sidewalk along one side of Bromley Road in order to increase pedestrian comfort and safety along this roadway segment.

5.3.2 Road Safety

A summary of all reported collisions within the study period over the past five years was presented in the Scoping section of this TIA. The City requires a safety review if at least six collisions for any one movement or of a discernible pattern have occurred over a five-year period. Preliminary analysis identified some intersections and road segments of potential concern, therefore further review was conducted, as summarized below:

Carling Avenue & Iroquois Road

In the past five years there have been a total of 33 collisions at this intersection, one of which involved a pedestrian. Based on the traffic volumes observed, this intersection experiences an average collision rate of 0.70 collisions per Million Vehicle Entering (MVE). A collision rate of less than 1.0 collisions per MVE is generally considered to be within the ‘expected’ or ‘normal’ operating range for a given location. Over the past five years, there have been 13 angle collisions, five rear-end collisions, three sideswipe collisions, 11 turning movement collisions and one pedestrian collision. Of the 13 angle collisions that occurred, seven involved eastbound through vehicles and northbound through vehicles, and four involved westbound through vehicles and southbound through or left-turning vehicles. The majority of the turning movement collisions involved eastbound vehicles completing left-turns or U-turns and westbound through vehicles. Most of the angle and turning movement collisions occurred during the daytime under clear environmental conditions (i.e. no rain or snow) and dry pavement conditions. Based on the above information, it is possible that excessive westbound speeds and red-light running may be contributing factors to these collision trends and should be investigated by the City for consideration of appropriate mitigation measures.

Carling Avenue & Hare Avenue

In the past five years there have been a total of six collisions at this intersection including two angle, two sideswipe and two turning movement collisions. No significant reoccurring collision patterns have therefore been observed.

Carling Avenue & Maitland Avenue / Sherbourne Road

In the past five years there have been a total of 63 collisions at this intersection. This translates to 0.79 collisions per MVE which is within the normal operating range. Of the 63 collisions that occurred in the past five years, there was one head-on collision, four angle collisions, 31 rear-end collisions, 21 sideswipe collisions, five turning movement collisions and one single motor vehicle (SMV) collision. Of the rear-end and sideswipe collisions, 12 involved northbound vehicles, four involved southbound vehicles, 11 involved eastbound vehicles and 25 involved westbound vehicles. The majority of these collisions occurred during the daytime under clear environmental conditions (i.e. no rain or snow) and dry pavement conditions. Based on the collision records, most of these collisions appeared to involve two vehicles going straight through (not turning right or left) with the exception of a few westbound left-turn collisions. The majority of these collisions occurred in the peak direction of traffic and, based on a preliminary review of field conditions, there is no apparent cause.

Carling Avenue – Hare Avenue to Bromley Road

There have been a total six collisions along this roadway segment in the past five years. Four of these collisions were rear-end collisions and two were SMV collisions. As such, no significant reoccurring collision patterns have been observed on this segment of Carling Avenue.

Carling Avenue –Bromley Road to Maitland Avenue / Sherbourne Road

Nine collisions have been observed along this segment of Carling Avenue in the past five years: one angle collisions (likely driveway related), five rear-end collisions (three eastbound and two westbound) and three sideswipe collisions (two eastbound and one westbound). As there have not been any significant reoccurring collisions patterns, further analysis is not warranted.

5.4 Access Intersections

5.4.1 Location and Design of Access

The proposed development will provide a new two-way private approach on Bromley Road. The existing private approach will be removed. The proposed site access is in conformance with the City of Ottawa Private Approach By-law 2003-447, with particular confirmation of the following items:

- **Width:** A private approach shall have a minimum width of 2.4m and a maximum width of 9.0m. The City of Ottawa Zoning By-law, however, indicates that for parking garage a two-way private approach shall have a minimum width of 6.0m.
 - The private approach will be 6.0m wide, which is appropriate for an access to a structured parking facility. ✓
- **Quantity and Spacing of Private Approaches:** For sites with frontage between 35 and 45 metres, two (2) two-way private approaches or two (2) one-way private approaches are permitted. Any two private approaches must be separated by at least 9.0m and can be reduced to 2.0m in the case of two one-way driveways. On lots that abut more than one roadway, these provisions apply to each frontage separately.
 - The frontage on Bromley Road is approximately 45m, therefore the single two-way private approach is compliant with the by-law. ✓

- Distance from Property Line: Private approaches must be at least 3.0m from the abutting property line, however this requirement can be reduced to 0.3m provided that the access is a safe distance from the access serving the adjacent property, sight lines are adequate and that it does not create a traffic hazard.
 - The private approach is approximately 6.2m from the property line. ✓
- Distance from Nearest Intersecting Street Line: For apartment buildings with 100 to 199 parking spaces located on a parcel adjacent to or within 46m of an arterial or major collector, all private approaches must be a minimum of 30m from the nearest intersecting street line.
 - The private approach is approximately 34.7m from the nearest intersecting street line. ✓
- Distance from Any Other Private Approach: For apartment buildings with 100 to 199 parking spaces located on a parcel adjacent to or within 46m of an arterial or major collector, all two-way private approaches must be a minimum of 30m from the any other private approach.
 - The private approach is approximately 10.3m from the loading access for Bromley Square. ✗
 - It is not expected that the proximity of the two accesses will have any impact to Carling Avenue, therefore, a relaxation of the bylaw is recommended in this situation.
- Grade of Private Approach: The grade of a private approach serving a parking area of more than 50 spaces must not exceed 2% within the private property for a distance of 9m from the highway/curb line.
 - The grade of the private approaches will be less than 2% within 9m of the curb line. ✓

5.4.2 Access Intersection Control

It is anticipated that the site access driveway will be unsignalized.

5.4.3 Access Intersection Design (MMLOS)

Not Applicable – The site access driveway will be unsignalized, therefore MMLOS analysis is not required.

5.5 Transportation Demand Management (TDM)

The City of Ottawa is committed to implementing Transportation Demand Management (TDM) measures on a City-wide basis in an effort to reduce automobile dependence, particularly during the weekday peak travel periods. TDM initiatives are aimed at encouraging individuals to use non-auto modes of travel during the peak periods.

5.5.1 Context for TDM

As discussed previously, the proposed development is located immediately adjacent to Carling Avenue which will be upgraded with continuous bus lanes between Lincoln Fields Station and the Trillium Line Carling Station and is also located within the Carling Avenue Arterial Mainstreet Design Priority Area (DPA).

The mode share targets used to estimate future development traffic were based on the TRANS Origin-Destination (O-D) Survey for the Ottawa West Traffic Assessment Zone (TAZ) and were adjusted to account for the impact of the planned Carling Avenue transit priority measures.

5.5.2 Need and Opportunity

A failure to meet the non-auto mode share targets would result in increased traffic at the study area intersections, potentially resulting in reduced Levels of Service (LOS). However, it is expected that there is a low probability that the mode share targets will not be achieved given the proximity of the site to a future transit priority corridor and its relative proximity to amenities such as the Carlingwood Shopping Centre.

5.5.3 TDM Program

The proposed development conforms to the City’s TDM principles by providing convenient and direct connections to adjacent pedestrian and transit facilities and is within a 500m walking distance from the Carlingwood Shopping Centre.

The City of Ottawa’s TDM Measures Checklist was completed for the proposed development and provided in **Appendix G**. This checklist indicates measures that are being contemplated as part of this development. A more detailed TDM program will be further developed at the site plan application stage.

5.6 Neighbourhood Traffic Management

5.6.1 Adjacent Neighbourhoods

As the development is dependent on Bromley Road for access, a review of Neighbourhood Traffic Management thresholds is required as part of the TIA process.

The TIA Guidelines specify a liveability threshold of 120 vehicles per hour for local roads. Bromley Road is projected to operate with two-way total traffic volumes of up to 71 and 87 vehicles per hour during the weekday morning and afternoon peak hours, respectively. As both weekday peak hours are expected to operate within the liveability threshold at the horizon year of the study, a Neighbourhood Traffic Management (NTM) plan is not necessary for this development.

5.7 Transit

5.7.1 Route Capacity

The estimated Future (2024) Total transit passenger demand within the study area was provided in Section 4.1.2.5. The results have been summarized in **Table 11**.

Table 11 – 2024 Development Generated Transit Demand

| PERIOD | PEAK PERIOD DEMAND | |
|--------|--------------------|-----|
| | IN | OUT |
| AM | 9 | 29 |
| PM | 18 | 11 |

As shown above, site-generated two-way transit ridership volumes of roughly 38 and 29 passengers are expected during the weekday morning and afternoon peak hours, respectively. It is expected that these transit trips will be easily accommodated by the future bus priority corridor along Carling Avenue.

5.7.1 Transit Priority Measures

It is expected that the transit priority measures that will be implemented as part of the Carling Avenue transit priority corridor will be sufficient to accommodate the proposed development.

5.8 Review of Network Concept

Not Applicable: The Network Concept element is exempt from this TIA, as defined in the study scope. This element is not required for development applications that generate less than 200 person-trips.

5.9 Intersection Design

The following sections summarize the methodology and results of the multi-modal intersection capacity analysis conducted within the study area.

5.9.1 Intersection Control

The following section evaluates the need to conduct traffic signal warrant analyses and roundabout analyses at any applicable study area intersections. The results of the intersection control warrants discussed below are provided in **Appendix I**.

5.9.1.1 Traffic Signal Warrants

Traffic signal warrant analysis has been completed for the intersection of Carling Avenue & Hare Avenue which the intersection capacity analysis indicates is expected to approach or exceed its theoretical capacity under Future (2024 & 2029) Background and Total Traffic conditions. The results of the traffic signal warrant analysis indicate that traffic signals are not warranted at this intersection.

5.9.1.2 Roundabout Analysis

The City's Roundabout Implementation Policy indicates that intersections that satisfy any of the following criteria should be screened utilizing the Roundabout Initial Feasibility Screening Tool:

- At any new City intersection
- Where traffic signals are warranted
- At intersections where capacity or safety problems are being experienced

The intersections of Carling Avenue & Maitland Avenue / Sherbourne Road and Carling Avenue & Hare Avenue were therefore screened as both are expected to approach or exceed their theoretical capacity under Future (2024 & 2029) Background and Total Traffic conditions. Based on the results of the roundabout screening analysis, it is not recommended that a roundabout be considered at either intersection.

5.9.2 Intersection Analysis Criteria (Automobile)

The following section outlines the City of Ottawa's methodology for determining motor vehicle Level-of-Service (LOS) at signalized and unsignalized intersections.

5.9.2.1 Signalized Intersections

In qualitative terms, the Level-of-Service (LOS) defines operational conditions within a traffic stream and their perception by motorists. A LOS definition generally describes these conditions in terms of such factors as delay, speed and travel time, freedom to manoeuvre, traffic interruptions,

safety, comfort and convenience. LOS can also be related to the ratio of the volume to capacity (v/c) which is simply the relationship of the traffic volume (either measured or forecast) to the capability of the intersection or road section to accommodate a given traffic volume. This capability varies depending on the factors described above. LOS are given letter designations from 'A' to 'F'. LOS 'A' represents the best operating conditions and LOS 'E' represents the level at which the intersection or an approach to the intersection is carrying the maximum traffic volume that can, practicably, be accommodated. LOS 'F' indicates that the intersection is operating beyond its theoretical capacity.

The City of Ottawa has developed criteria as part of the Transportation Impact Assessment Guidelines, which directly relate the volume to capacity (v/c) ratio of a signalized intersection to a LOS designation. These criteria are presented in **Table 12** as follows:

Table 12 - LOS Criteria for Signalized Intersections

| LOS | VOLUME TO CAPACITY RATIO (v/c) |
|-----|--------------------------------|
| A | 0 to 0.60 |
| B | 0.61 to 0.70 |
| C | 0.71 to 0.80 |
| D | 0.81 to 0.90 |
| E | 0.91 to 1.00 |
| F | > 1.00 |

The intersection capacity analysis technique provides an indication of the LOS for each movement at the intersection under consideration and for the intersection as a whole. The overall v/c ratio for an intersection is defined as the sum of equivalent volumes for all critical movements at the intersection divided by the sum of capacities for all critical movements.

The Level of Service calculation is based on locally-specific parameters as described in the TIA Guidelines and incorporates existing signal timing plans obtained from the City of Ottawa. The analysis existing conditions utilized a Peak Hour Factor (PHF) of 0.90, while future conditions considers optimized signal timing plans and use of a Peak Hour Factor (PHF) of 1.0 to recognize peak spreading beyond a 15-minute period in congested conditions.

5.9.2.2 Unsignalized Intersections

The capacity of an unsignalized intersection can also be expressed in terms of the LOS it provides. For an unsignalized intersection, the Level of Service is defined in terms of the average movement delays at the intersection. This is defined as the total elapsed time from when a vehicle stops at the end of the queue until the vehicle departs from the stop line; this includes the time required for a vehicle to travel from the last-in-queue position to the first-in-queue position. The average delay for any particular minor movement at the un-signalized intersection is a function of the capacity of the approach and the degree of saturation.

The Highway Capacity Manual 2010 (HCM), prepared by the Transportation Research Board, includes the following Levels of Service criteria for un-signalized intersections, related to average movement delays at the intersection, as indicated in **Table 13**.

Table 13 - LOS Criteria for Unsignalized Intersections

| LOS | DELAY (seconds) |
|-----|-----------------|
| A | <10 |
| B | >10 and <15 |
| C | >15 and <25 |
| D | >25 and <35 |
| E | >35 and <50 |
| F | >50 |

The unsignalized intersection capacity analysis technique included in the HCM and used in the current study provides an indication of the Level of Service for each movement of the intersection under consideration. By this technique, the performance of the unsignalized intersection can be compared under varying traffic scenarios, using the Level of Service concept in a qualitative sense. One unsignalized intersection can be compared with another unsignalized intersection using this concept. Level of Service 'E' represents the capacity of the movement under consideration and generally, in large urban areas, Level of Service 'D' is considered to represent an acceptable operating condition. Level of Service 'E' is considered an acceptable operating condition for planning purposes for intersections located within Ottawa's Urban Core (the downtown and its vicinity). Level of Service 'F' indicates that the movement is operating beyond its design capacity.

5.9.3 Intersection Capacity Analysis

Following the established intersection capacity analysis criteria described above, the existing and future conditions are analyzed during the weekday peak hour traffic volumes derived in this study.

The following section presents the results of the intersection capacity analysis. All tables summarize study area intersection LOS results during the weekday morning and afternoon peak hour periods.

The Synchro output files have been provided in **Appendix J**.

5.9.3.1 Existing (2020) Traffic

An intersection capacity analysis has been undertaken using the Existing (2020) Traffic volumes presented in **Exhibit 4. Table 14** summarizes the results of the intersection capacity analysis.

Table 14 - Intersection Capacity Analysis: Existing (2020) Traffic

| INTERSECTION | TRAFFIC CONTROL | AM PEAK HOUR | | PM PEAK HOUR | |
|--|-----------------|-------------------------------|--------------------------------------|-------------------------------|--------------------------------------|
| | | OVERALL LOS (V/C OR DELAY) | CRITICAL MOVEMENTS (V/C OR DELAY) | OVERALL LOS (V/C OR DELAY) | CRITICAL MOVEMENTS (V/C OR DELAY) |
| Carling Avenue & Iroquois Road | Signalized | A (0.52) | EBTR (0.52) | B (0.65) | WBT (0.65) |
| Carling Avenue & Hare Avenue | Unsignalized | E (42.1s) | NBRL (42.1s) | D (25.7s) | NBRL (25.7s) |
| Carling Avenue & Bromley Road | Unsignalized | B (10.9s) | SBR (10.9s) | C (21.3s) | SBR (21.3s) |
| Carling Avenue & Maitland Avenue/ Sherbourne Road | Signalized | D (0.90) | SBL (1.33) | E (0.95) | NBL (0.98) |

Based on the results of the analysis, the intersections of Carling Avenue & Hare Avenue and Carling Avenue & Maitland Avenue / Sherbourne Road are presently approaching their theoretical capacity (i.e. LOS 'E') under Existing (2020) Traffic conditions during the weekday morning and afternoon peak hour, respectively. During the weekday morning peak hour, several movements at the Carling Avenue & Maitland Avenue / Sherbourne Road intersection are operating in excess of their theoretical capacity; however, the intersection as a whole is operating at an acceptable Level of Service (i.e. LOS 'D' or better).

5.9.3.2 Future (2024) Background Traffic

An intersection capacity analysis has been undertaken using the Future (2024) Background Traffic volumes presented in **Exhibit 6**, yielding the following results:

Table 15 - Intersection Capacity Analysis: Future (2024) Background Traffic

| INTERSECTION | TRAFFIC CONTROL | AM PEAK HOUR | | PM PEAK HOUR | |
|--|---------------------------|-------------------------------|--------------------------------------|-------------------------------|--------------------------------------|
| | | OVERALL LOS (V/C OR DELAY) | CRITICAL MOVEMENTS (V/C OR DELAY) | OVERALL LOS (V/C OR DELAY) | CRITICAL MOVEMENTS (V/C OR DELAY) |
| Carling Avenue & Iroquois Road | Signalized | B (0.62) | EBT (0.62) | A (0.59) | WBT (0.59) |
| | Signalized ^{1,2} | B (0.63) | EBT (0.68) | A (0.57) | WBT (0.57) |
| Carling Avenue & Hare Avenue | Unsignalized | F (52.1s) | NBRL (52.1s) | E (36.8s) | NBRL (36.8s) |
| | Unsignalized ¹ | E (43.6s) | NBRL (43.6s) | D (33.8s) | NBRL (33.8s) |
| Carling Avenue & Bromley Road | Unsignalized | A (9.8s) | SBR (9.8s) | C (17.0s) | SBR (17.0s) |
| Carling Avenue & Maitland Avenue/ Sherbourne Road | Signalized ³ | E (0.91) | NBTR (0.93) | C (0.74) | WBL (0.88) |

Notes:

¹ – U-turns prohibited at Carling Avenue & Hare Avenue and rerouted to Carling Avenue & Iroquois Road.

² – Protected-permitted westbound left-turn phase added.

³ – Optimized signal timing plan.

Under Future (2024) Background Traffic conditions, the intersection of Carling Avenue & Maitland Avenue / Sherbourne is expected to approach its theoretical capacity in the morning peak hour. In the afternoon peak hour, the intersection as a whole is operating at an acceptable Level of Service (i.e. LOS 'D' or better). Given the space constraints at the intersection, no physical intersection modifications (e.g. additional lanes) are recommended. Potential signal timing plan modifications were considered; however, none were identified that would improve traffic operations at the intersection during the morning peak hour.

With the planned conversion of two general traffic lanes to dedicated bus lanes the traffic capacity on Carling Avenue is expected to decrease resulting in less gaps for northbound traffic at the intersection of Carling Avenue & Hare Avenue which ultimately results in increased delays. The increased delays are expected to cause the northbound approach to exceed its theoretical capacity in the morning peak hour and to approach its theoretical capacity in the afternoon peak hour. Analysis has shown that prohibiting U-turn movements at this intersection will permit the intersection to operate at or below its theoretical capacity during both peak hours with minimal impacts to the intersection of Carling Avenue & Iroquois Road. It is recommended that a westbound left-turn protected-permitted phase be added at the intersection of Carling Avenue & Iroquois Road to reduce conflicts between the increased westbound U-turn traffic and eastbound through traffic.

5.9.3.3 Future (2029) Background Traffic

An intersection capacity analysis has been undertaken using the Future (2029) Background Traffic volumes presented in **Exhibit 7**, yielding the following results:

Table 16 - Intersection Capacity Analysis: Future (2029) Background Traffic

| INTERSECTION | TRAFFIC CONTROL | AM PEAK HOUR | | PM PEAK HOUR | |
|--|---------------------------|-------------------------------|--------------------------------------|-------------------------------|--------------------------------------|
| | | OVERALL LOS (V/C OR DELAY) | CRITICAL MOVEMENTS (V/C OR DELAY) | OVERALL LOS (V/C OR DELAY) | CRITICAL MOVEMENTS (V/C OR DELAY) |
| Carling Avenue & Iroquois Road | Signalized ^{1,2} | B (0.61) | EBT (0.66) | A (0.56) | WBT (0.56) |
| Carling Avenue & Hare Avenue | Unsignalized ¹ | E (40.5s) | NBRL (40.5s) | D (32.0s) | NBRL (32.0s) |
| Carling Avenue & Bromley Road | Unsignalized | A (9.7s) | SBR (9.7s) | C (16.7s) | SBR (16.7s) |
| Carling Avenue & Maitland Avenue/ Sherbourne Road | Signalized ³ | D (0.89) | NBTR (0.91) | B (0.68) | NBL (0.84) |

Notes:

¹ – U-turns prohibited at Carling Avenue & Hare Avenue and rerouted to Carling Avenue & Iroquois Road.

² – Protected-permitted westbound left-turn phase added.

³ – Optimized signal timing plan.

Under Future (2029) Background Traffic conditions, only the Carling Avenue & Hare Avenue intersection is expected to continue operating at its theoretical capacity during the morning peak hour. During the morning peak hour, traffic operations at the Carling Avenue & Maitland Avenue / Sherbourne Road intersection is expected to operate at an overall LOS of 'D'. Overall, traffic operations are expected to improve slightly at all intersections as a result of continuing decreases in background traffic demand.

5.9.3.4 Future (2024) Total Traffic

An intersection capacity analysis has been undertaken using the Future (2024) Total Traffic volumes presented in **Exhibit 8**, yielding the following results:

Table 17 - Intersection Capacity Analysis: Future (2024) Total Traffic

| INTERSECTION | TRAFFIC CONTROL | AM PEAK HOUR | | PM PEAK HOUR | |
|--|---------------------------|-------------------------------|--------------------------------------|-------------------------------|--------------------------------------|
| | | OVERALL LOS (V/C OR DELAY) | CRITICAL MOVEMENTS (V/C OR DELAY) | OVERALL LOS (V/C OR DELAY) | CRITICAL MOVEMENTS (V/C OR DELAY) |
| Carling Avenue & Iroquois Road | Signalized ^{1,2} | B (0.66) | EBT (0.70) | A (0.58) | WBT (0.58) |
| Carling Avenue & Hare Avenue | Unsignalized ¹ | E (45.7s) | NBRL (45.7s) | D (34.9s) | NBRL (34.9s) |
| Carling Avenue & Bromley Road | Unsignalized | A (10.1s) | SBR (10.1s) | C (18.0s) | SBR (18.0s) |
| Carling Avenue & Maitland Avenue/ Sherbourne Road | Signalized ³ | E (0.91) | NBTR (0.93) | C (0.73) | NBL (0.89) |

Notes:

¹ – U-turns prohibited at Carling Avenue & Hare Avenue and rerouted to Carling Avenue & Iroquois Road.

² – Protected-permitted westbound left-turn phase added.

³ – Optimized signal timing plan.

Based on the above results, the addition of site-generated traffic is expected to have a minor impact at all study area intersections. Overall, however, traffic operations will not be significantly affected, and all intersection movements will continue operating at or below their theoretical capacity.

5.9.3.5 Future (2029) Total Traffic

An intersection capacity analysis has been undertaken using the Future (2029) Total Traffic volumes presented in **Exhibit 9**, yielding the following results:

Table 18 - Intersection Capacity Analysis: Future (2024) Total Traffic

| INTERSECTION | TRAFFIC CONTROL | AM PEAK HOUR | | PM PEAK HOUR | |
|--|---------------------------|-------------------------------|--------------------------------------|-------------------------------|--------------------------------------|
| | | OVERALL LOS (V/C OR DELAY) | CRITICAL MOVEMENTS (V/C OR DELAY) | OVERALL LOS (V/C OR DELAY) | CRITICAL MOVEMENTS (V/C OR DELAY) |
| Carling Avenue & Iroquois Road | Signalized ^{1,2} | B (0.63) | EBT (0.68) | A (0.56) | WBT (0.56) |
| Carling Avenue & Hare Avenue | Unsignalized ¹ | E (42.4s) | NBRL (42.4s) | D (33.1s) | NBRL (33.1s) |
| Carling Avenue & Bromley Road | Unsignalized | A (10.0s) | SBR (10.0s) | C (17.6s) | SBR (17.6s) |
| Carling Avenue & Maitland Avenue/ Sherbourne Road | Signalized ³ | D (0.89) | NBTR (0.91) | C (0.71) | NBL (0.86) |

Notes:

¹ – U-turns prohibited at Carling Avenue & Hare Avenue and rerouted to Carling Avenue & Iroquois Road.

² – Protected-permitted westbound left-turn phase added.

³ – Optimized signal timing plan.

As observed under Future (2024) Total Traffic conditions, under Future (2029) Total Traffic conditions all study area intersections are expected to continue operating at or below their theoretical capacity and no intersection movements are expected to exceed their theoretical capacity. Minor improvements in traffic operations are expected relative to Future (2024) Total Traffic conditions as a result of anticipated declines in background traffic volumes.

5.9.4 Intersection Design (MMLOS)

5.9.4.1 Intersection MMLOS Methodology

Analysis criteria for each of the four non-auto modes are briefly described as follows:

Intersection Pedestrian Level of Service (PLOS)

The PLOS at intersections is based on several factors including the number of traffic lanes that pedestrians must cross, corner radii, and whether the crossing allows for permissive or protective right or left turns, among others. The City of Ottawa target for PLOS along an Arterial Mainstreet is 'C'.

Intersection Bicycle Level of Service (BLOS)

The BLOS at intersections is dependent on several factors: the number of lanes that the cyclist is required to cross to make a left-turn; the presence of a dedicated right-turn lane on the approach; and the operating speed of each approach. The City target for BLOS along an Arterial Mainstreet spine route is 'C'.

Intersection Transit Level of Service (TLOS)

Intersection TLOS is based on the average signal delay experienced by transit vehicles at each intersection. The City Target TLOS along an Arterial Mainstreet with a Transit Priority Corridor (Continuous Lanes) is 'C'.

Intersection Truck Level of Service (TkLOS)

The Truck LOS (TkLOS) is based on the right-turn radii, as well as the number of receiving lanes for vehicles making a right-turn from the traffic lane being analyzed. The City of Ottawa target for TkLOS along an Arterial Mainstreet is 'D' for truck routes or 'E' for non-truck routes.

5.9.4.2 Intersection MMLOS Results

An analysis of the future conditions for each mode has been conducted based on the methodology prescribed in the City of Ottawa Multi-Modal Level of Service (MMLOS) Guidelines. The Level of Service (LOS) for each mode has been calculated for each intersection where signals exist or are anticipated.

The intersection MMLOS results have been summarized in **Table 19**. Detailed intersection MMLOS analysis results are provided **Appendix H**.

Table 19 - Intersection MMLOS

| LOCATION | LEVEL OF SERVICE BY MODE | | | |
|--|--------------------------|-------------------------|-------------------------|-------------------------|
| | PEDESTRIAN (PLOS) | BICYCLE (BLOS) | TRANSIT (TLOS) | TRUCK (TkLOS) |
| INTERSECTIONS | | | | |
| Carling Avenue & Iroquois Road | F (Target: C) | F (Target: C) | F (Target: C) | E (Target: D) |
| Carling Avenue & Maitland Avenue / Sherbourne Road | F (Target: C) | F (Target: C) | F (Target: C) | F (Target: D) |

5.9.4.3 Summary of Potential Improvements

Based on the MMLOS results outlined in **Table 19**, the following measures have been identified that could improve conditions for each travel mode:

Pedestrians

- The analysis indicates that all study area intersections are presently operating below the City's PLOS target of 'C'. Achieving a PLOS of 'C' would require reducing the width of Carling Avenue as well as reducing the traffic signal cycle lengths. With consideration of the volume of traffic demand on Carling Avenue, such modifications would have a significant negative impact to vehicle LOS. As a result of the number of travel lanes necessary to accommodate the traffic demand and transit priority lanes, it is not possible to achieve the targeted PLOS at these intersections but may be improved through supplemental design features such as enhanced crosswalk markings or advanced pedestrian signal phases.

Cyclists

- Based on the analysis, none of the study area intersections meet their respective BLOS targets. This is primarily due to the high operating speeds along most study area roadways (i.e. 60 km/h or greater) and the number of lanes that cyclists must cross to make a left-turn. Cyclists will be permitted to use the planned bus lanes on Carling Avenue and therefore they will be much less exposed to general traffic. At intersections, however, left-turning cyclists would still be required to cross many lanes of traffic in order to complete left-turn movements. Furthermore, at the intersection of Carling Avenue & Maitland Avenue / Sherbourne Road, the dedicated bus lanes will transition to right-turn lanes in advance of the intersection and cyclists will be required to mix with general traffic. To achieve BLOS targets, significant intersection modifications such as the addition of bike pocket lanes at the intersection approaches complete with two-stage left turn boxes or a redesign to 'protected intersection' standards would be required. As both Carling and Maitland are each designated as Spine cycling routes, the City should consider infrastructure improvements within the study area to address these existing gaps in the active transportation network.

Transit

- The results of the analysis indicate that neither signalized intersection is meeting its TLOS target. However, if the northbound and southbound approaches of the Carling Avenue & Iroquois Road intersection are ignored the intersection would meet its TLOS target as the eastbound and westbound approaches will have queue jump lanes in the future. At the intersection of Carling Avenue & Maitland Avenue / Sherbourne Road, the dedicated bus lanes end in advance of the intersection and, as such, transit will be delayed by general traffic resulting in a poor TLOS. Given that the intersection is expected to approach its theoretical capacity under both Future (2024 & 2029) Background and Total Traffic conditions, it should be cautioned that any reduction in vehicular capacity at the intersection to accommodate transit priority lanes through the intersection may result in significant traffic congestion. It should be noted that the TLOS deficiency is primarily a result of background traffic demand and site-generated traffic demand has a negligible impact.

Truck

- Both signalized intersections within the study area do not meet the TLOS target. However, at the intersection of Carling Avenue & Iroquois Road, it is only the eastbound right-turn movement that is failing to meet the TLOS target. As Iroquois Road is not a trucking route it is expected that this deficiency is acceptable. Similarly, at the intersection of Carling

Avenue & Maitland Avenue / Sherbourne Road, it is the westbound right-turn movement that is failing to meet the TLOS target. Sherbourne Road is also not a trucking route therefore it is expected that this deficiency is also acceptable. If both of these movements are ignored then both signalized intersections meet the TLOS target.

The recommended measures listed above are intended only as suggestions to the City on how the MMLOS within the study area could be improved and do not identify measures to be implemented as a direct consequence of this development. The MMLOS analysis identifies existing deficiencies in the study area and are not expected to be exacerbated by the proposed development.

5.10 Geometric Review

The following section reviews all geometric requirements for the study area intersections.

5.10.1 Sight Distance and Corner Clearances

The proposed site access is located along a straight segment of Bromley Road with clear sightlines in both directions. From the southbound approach of the Carling Avenue & Bromley Road intersection there is at least 130m of visibility to approaching westbound vehicles in the curb lane which is in excess of the minimum stopping sight distance for a design speed on Carling Avenue of 70km/h. With consideration that the curb lane will be converted to a bus lane, the volume and speed of traffic will be significantly reduced in this lane, thereby facilitating right turns from Bromley Road.

The Transportation Association of Canada (TAC) Geometric Design Guide for Canadian Roads indicates that a minimum corner clearance of 15m should be maintained between a private approach on a local road and any intersecting roadway. The proposed site access will be located approximately 33.3m from Carling Avenue and therefore meets this requirement.

5.10.2 Auxiliary Lane Analysis

Auxiliary turning lane requirements for all intersections within the study area are described as follows:

5.10.2.1 Unsignalized Auxiliary Left-Turn Lane Requirements

Based on the intersection capacity analysis, the westbound left-turn lane at the intersection of Carling Avenue & Hare Avenue is expected to experience negligible queues and therefore the existing storage provided will be sufficient. It shall be noted that this result is contingent on the implementation of westbound U-turn restrictions at this location.

5.10.2.2 Signalized Auxiliary Left-Turn Requirements

A review of auxiliary left-turn lane storage requirements was completed at all signalized intersections within the study area under Future (2029) Total Traffic conditions. The review compared the projected 95th percentile queue lengths from Synchro operational results, and the standard queue length calculation based on the following equation:

$$\text{Storage Length} = \frac{NL}{C} \times 1.5$$

Where:

N = number of vehicles per hour

L = Length occupied by a vehicle in the queue = 7 m

C = number of traffic signal cycles per hour

The results of the auxiliary left-turn lane analysis are summarized below in **Table 20**.

Table 20 - Auxiliary Left-Turn Storage Analysis at Signalized Intersections

| INTERSECTION | APPROACH | 95TH %ILE QUEUE LENGTH / CALCULATED QUEUE (M) | | EXISTING STORAGE LENGTH (M) | STORAGE DEFICIENCY (M) |
|--|----------|--|-------------------|-----------------------------------|------------------------------|
| | | AM PEAK HR | PM PEAK HR | | |
| Carling Avenue & Iroquois Road | SB | 32.8 / 28.4 | 46.8 / 44.4 | 50 | - |
| | EB | 3.2 / 7.6 | 6.6 / 16.3 | 25 | - |
| | WB | 5.9 / 17.4 | 8.2 / 21.6 | 20 | - |
| Carling Avenue & Maitland Avenue / Sherbourne Road | NB | #57.6 / 23.0 | 80.7 / 16.5 | 75 | 5 |
| | SB | #41.3 / 48.7 | 17.5 / 86.3 | 45 | 40 |
| | EB | 22.7 / 15.7 | #57.0 / 30.0 | 55 | - |
| | WB | #65.8 / 57.8 | #121.2 / 139.3 | 115 (D) | - |

Notes: 'D' stands for double left-turn lane.

Based on the results of the left-turn analysis presented above, the northbound and southbound auxiliary left-turn lanes at the intersection of Carling Avenue & Maitland Avenue / Sherbourne Road are 5m and 40m deficient, respectively.

While modifications to pavement markings can address the 5m storage deficiency, it can be considered negligible and therefore not necessary. With regard to the southbound left-turn lane on Sherbourne Road, there are practical limitations to extending the turn lane as it would extend beyond the intersection with Bromley Road. Given the above, modifications to storage capacity to address these are not feasible and therefore not recommended.

5.10.2.3 Unsignalized Auxiliary Right-Turn Lane Requirements

All unsignalized intersections in the study area are expected to have auxiliary right-turn lanes in the future as part of the planned implementation of dedicated bus lanes along Carling Avenue. Based on the projected 95th percentile queue lengths under Future (2029) Total Traffic conditions, the proposed auxiliary right-turn lane lengths will be sufficient to accommodate the projected traffic demand.

5.10.2.4 Signalized Auxiliary Right-Turn Lane Requirements

For signalized intersections, Section 9.14 of TAC suggests that auxiliary right-turn lanes shall be considered when more than 10% of vehicles on an approach are turning right and when the peak hour demand exceeds 60 vehicles. The purpose of this guideline is to mitigate operational impacts to through-traffic, particularly on high-speed arterial roadways, and may not be applicable in all circumstances.

The results of the auxiliary right-turn lane analysis are summarized below in **Table 21** below:

Table 21 – Auxiliary Right-Turn Lane Storage Analysis at Signalized Intersections

| INTERSECTION | APPROACH | NUMBER OF RIGHT-TURNS / % RIGHT-TURNS | | 95TH %ILE QUEUE (M) AM / PM | EXISTING / PROPOSED STORAGE LENGTH (M) | STORAGE DEFICIENCY (M) |
|--|----------|---------------------------------------|--------------|--------------------------------|--|------------------------|
| | | AM PEAK HOUR | PM PEAK HOUR | | | |
| Carling Avenue & Iroquois Road | NB | 30 / 53% | 10 / 23% | - | - | - |
| | SB | 27 / 25% | 60 / 30% | - | - | - |
| | EB | 5 / 0% | 4 / 1% | 0.0 / 0.0 | 40 | - |
| | WB | 60 / 12% | 107 / 7% | 2.5 / 9.2 | 85 | - |
| Carling Avenue & Maitland Avenue / Sherbourne Road | NB | 396 / 63% | 208 / 31% | - | - | - ¹ |
| | SB | 16 / 4% | 44 / 15% | - | - | - |
| | EB | 265 / 15% | 174 / 21% | 21.0 / 17.8 | 130 | - |
| | WB | 16 / 3% | 53 / 3% | - | - | - |

Notes:

¹ – Meets the right-turn criteria, however, there is insufficient right-of-way available to accommodate a right-turn lane.

Based on the results presented above, the northbound approach at the Carling Avenue & Maitland Avenue / Sherbourne Road intersection meets the criteria for a right-turn lane however there is insufficient right-of-way to accommodate one at this location. All existing and future proposed right-turn lanes are expected to be sufficiently long to accommodate the projected Future (2029) Total Traffic demand.

5.11 Summary of Recommended Modifications

Based on the intersection capacity, Multi-Modal Level of Service and auxiliary lane analyses results presented above, no off-site improvements to the adjacent road network are required as a direct consequence of the proposed development in order to accommodate multi-modal transportation demands generated by the site. Under Future (2024) Background Traffic conditions, it was observed that the northbound approach at the Carling Avenue & Hare Avenue intersection experienced significant delays once the outer lanes on Carling Avenue were converted to dedicated bus lanes. Prohibiting U-turns at this location was found to allow this intersection to operate at LOS 'E' through to the horizon year of this study. It is expected that prohibiting U-turns at the Carling Avenue & Hare Avenue intersection would result in most of this demand to transfer to the Carling Avenue & Iroquois Road intersection. There is sufficient capacity at this intersection to accommodate this additional demand, however, it is recommended that the City consider implementing a protected-permitted westbound left-turn phase at this location. This would provide a protected phase that would make completing U-turn movements much safer as it would reduce conflicts with through traffic. Prohibiting U-turns at Carling Avenue & Hare Avenue would also improve safety at that intersection by also reducing conflicts with through traffic on Carling Avenue.

The MMLOS results identified existing deficiencies with respect to user comfort as well as potential mitigation measures that could be considered for implementation by the City but are not required to safely accommodate the proposed development.

As indicated in Section 5.3.2, it is suggested that the City further investigate collision patterns at the intersection of Carling Avenue & Iroquois Road to address the high frequency of angle and turning-movement collisions observed at the intersection and implement mitigation measures. Considering the collision patterns observed, it is not expected that site-generated traffic will significantly contribute to movements with observed safety issues.

6 Conclusion

The proposed residential development at 1995 Carling Avenue is expected to generate up to 53 and 59 two-way vehicular trips during the weekday morning and afternoon peak hours, respectively. It is expected that with the introduction of dedicated bus lanes on Carling Avenue that local transit mode shares may increase by 25% over existing levels, resulting in a reduction in local automobile use. It is also expected that this would have an impact to regional traffic patterns, however, the magnitude of this impact is unknown at the moment. Traffic volumes on Carling Avenue have been shown to decline slightly year over year and this trend is expected to continue with the introduction of higher quality transit service within the study area.

A review of historical collision records identified a high frequency of angle and turning-movement collisions at the intersection of Carling Avenue & Iroquois Road. Based on the reoccurring collision patterns observed, it was recommended that the City further investigate collision patterns at this intersection and implement mitigation measures. With consideration of the expected distribution of site-generated traffic, it is not anticipated that the proposed development will significantly contribute to movements with observed safety issues.

A multi-modal analysis of each study area intersection identified deficiencies in the existing road network and potential remediation measures have been suggested in which the City could consider in order to meet the prescribed targets. These remediation measures would improve mobility and comfort for all transportation modes but are not required to safely accommodate the proposed development.

It was found that the intersections of Carling Avenue & Hare Avenue and Carling Avenue & Maitland Avenue / Sherbourne Road would approach or exceed their theoretical capacities under Future (2024) Background Traffic conditions. Due to space constraints, no intersection modifications were recommended for the Carling Avenue & Maitland Avenue / Sherbourne Road intersection. At the Carling Avenue & Hare Avenue intersection, however, it is recommended that the City prohibit U-turn movements to address the capacity issue. The analyses indicate that with this prohibition, this intersection would not exceed its theoretical capacity within the horizon year of this study. A prohibition of U-turns at this location would result in demand shifting to the intersection of Carling Avenue & Iroquois Road, therefore, it is recommended that the City implement a protected-permitted phase for the westbound left-turn movement to improve safety at the intersection by reducing conflicts between vehicles completing a U-turn movement and through traffic on Carling Avenue.

As no physical modifications are required as a result of site-generated demand, an RMA will not be required. Further, as all required road network modifications are a result of background demand, a post-development monitoring plan will not be required either.

Based on the findings of this study, it is the overall opinion of IBI Group that the proposed development will integrate well with and can be safely accommodated by the adjacent transportation network.

Appendix A – City Circulation Comments

Step 1, 2 & 3 Submission (Screening, Scoping & Forecasting) – Circulation Comments & Response

Report Submitted: March 17, 2020

Comments Received: April 1, 2020


Transportation Project Manager: Mike Giampa

1. Revise the existing mode share. Since this is a residential development, a blend of from/within district should be used for the AM Peak and to/within district in the PM Peak.
 - IBI Response: Existing mode shares have been updated.
2. Provide future mode share targets to account for the Carling transit improvements.
 - IBI Response: Future transit mode share has been increased by a factor of 25% to account for increases in future transit ridership as a result of the Carling Avenue transit improvements.
3. Transit lanes are planned to be in place prior to the development's 2024 buildout year.
 - IBI Response: Report has been updated to reflect this new information.
4. Correct Table 8. The auto driver trips are incorrect.
 - IBI Response: Table 8 has been corrected.
5. Revisit the need for demand rationalization as a result of the reduction of the number of general traffic lanes. Provide figures depicting the total traffic operating in study area intersections.
 - IBI Response: The demand rationalization has been revised to reflect the reduction in general traffic lanes and the traffic volume exhibits have been updated.
6. Consider a background traffic reduction for a 2024/2029 horizon years given recent trends and the implementation of transit lanes on Carling Avenue from Lincoln Fields to Bronson.
 - IBI Response: Based on traffic growth rates identified in supporting TIAs for adjacent developments, a -0.5% linear growth rate has been applied to background traffic volumes.
7. Left turn storage analysis is required at the intersections to make sure there is enough storage capacity where development traffic is expected to complete turning movements and/or U-turn movements.
 - IBI Response: Acknowledged, left-turn storage analysis will be conducted in Step 4 Analysis.

Appendix B – Screening Form


City of Ottawa 2017 TIA Guidelines Screening Form

1. Description of Proposed Development

| | |
|------------------------------------|--|
| Municipal Address | 1995 Carling Avenue |
| Description of Location | <p>The site is situated north of Carling Avenue and west of Bromley Road, between McKellar Park Suites and Bromley Square.</p>  |
| Land Use Classification | High-Rise Residential |
| Development Size (units) | 210 Residential Units |
| Development Size (m ²) | |
| Number of Accesses and Locations | One two-way access on Bromley Road. |
| Phase of Development | Single Phase |
| Buildout Year | 2024 |


If available, please attach a sketch of the development or site plan to this form.

Proposed Development:



2. Trip Generation Trigger



Considering the Development's Land Use type and Size (as filled out in the previous section), please refer to the Trip Generation Trigger checks below.

| Land Use Type | Minimum Development Size |
|-------------------------------------|--|
| Single-family homes | 40 units |
| Townhomes or apartments | 90 units  |
| Office | 3,500 m ² |
| Industrial | 5,000 m ² |
| Fast-food restaurant or coffee shop | 100 m ² |
| Destination retail | 1,000 m ² |
| Gas station or convenience market | 75 m ² |

* If the development has a land use type other than what is presented in the table above, estimates of person-trip generation may be made based on average trip generation characteristics represented in the current edition of the Institute of Transportation Engineers (ITE) Trip Generation Manual.

➤ **Based on the results above, the Trip Generation Trigger is satisfied.**

3. Location Triggers

| | Yes | No |
|--|---|---|
| Does the development propose a new driveway to a boundary street that is designated as part of the City's Transit Priority, Rapid Transit or Spine Bicycle Networks? | |  |
| Is the development in a Design Priority Area (DPA) or Transit-oriented Development (TOD) zone?* |  | |

*DPA and TOD are identified in the City of Ottawa Official Plan (DPA in Section 2.5.1 and Schedules A and B; TOD in Annex 6). See Chapter 4 for a list of City of Ottawa Planning and Engineering documents that support the completion of TIA).

➤ **Based on the results above, the Location Trigger is satisfied.**

4. Safety Triggers

| | Yes | No |
|---|-----|-------------------------------------|
| Are posted speed limits on a boundary street are 80 km/hr or greater? | | <input checked="" type="checkbox"/> |
| Are there any horizontal/vertical curvatures on a boundary street that limits sight lines at a proposed driveway? | | <input checked="" type="checkbox"/> |
| Is the proposed driveway within the area of influence of an adjacent traffic signal or roundabout (i.e. within 300 m of intersection in rural conditions, or within 150 m of intersection in urban/ suburban conditions)? | | <input checked="" type="checkbox"/> |
| Is the proposed driveway within auxiliary lanes of an intersection? | | <input checked="" type="checkbox"/> |
| Does the proposed driveway make use of an existing median break that serves an existing site? | | <input checked="" type="checkbox"/> |
| Is there is a documented history of traffic operations or safety concerns on the boundary streets within 500 m of the development? | | <input checked="" type="checkbox"/> |
| Does the development include a drive-thru facility? | | <input checked="" type="checkbox"/> |

➤ **Based on the results above, the Safety Trigger is NOT satisfied.**

5. Summary

| | Yes | No |
|---|-------------------------------------|-------------------------------------|
| Does the development satisfy the Trip Generation Trigger? | <input checked="" type="checkbox"/> | |
| Does the development satisfy the Location Trigger? | <input checked="" type="checkbox"/> | |
| Does the development satisfy the Safety Trigger? | | <input checked="" type="checkbox"/> |

CONCLUSION: The Trip Generation and Location Triggers are satisfied, therefore a TIA is required.

Appendix C – Turning Movement Counts

Turning Movement Count - Peak Hour Diagram


CARLING AVE @ IROQUOIS RD

Survey Date: Wednesday, May 10, 2017

Start Time: 07:00

WO No: 37025

Device: Miovision



Turning Movement Count - Peak Hour Diagram


CARLING AVE @ IROQUOIS RD

Survey Date: Wednesday, May 10, 2017

Start Time: 07:00

WO No: 37025

Device: Miovision



Comments

Survey Date: Wednesday March 11 2020
 Weather: Dry



NB (South Leg) Street Name: Hare Avenue
 SB (North Leg) Street Name: _____

EB (West Leg) Street Name: Carling Avenue
 WB (East Leg) Street Name: Carling Avenue

Start Time (AM Peak): 8:00
 End Time (AM Peak): 11:00

The AM Peak Hour is from 8:00 AM to 9:00 AM **AADT Factor:** 1.0

Turning Movement Count - 15 Minute Vehicle Summary Report (AM Peak)

| Time Period | Hare Avenue Northbound | | | | | Southbound | | | | | N/S STREET TOTAL | Carling Avenue Eastbound | | | | | Carling Avenue Westbound | | | | | E/W STREET TOTAL | Grand TOTAL | 1 Hour Traffic Volumes (All Scenarios) |
|---------------------|------------------------|----|----|---------|----------|------------|----|----|---------|----------|------------------|--------------------------|----|----|---------|----------|--------------------------|----|----|---------|----------|------------------|-------------|--|
| | LT | ST | RT | U-Turns | NB TOTAL | LT | ST | RT | U-Turns | SB TOTAL | | LT | ST | RT | U-Turns | EB TOTAL | LT | ST | RT | U-Turns | WB TOTAL | | | |
| 8:00 8:15 | 4 | | 3 | | 7 | | | | | 0 | 7 | | | 4 | 0 | 4 | 5 | | | 3 | 8 | 12 | 19 | |
| 8:15 8:30 | 1 | | 5 | | 6 | | | | | 0 | 6 | | | 1 | 0 | 1 | 1 | | | 6 | 7 | 8 | 14 | |
| 8:30 8:45 | 1 | | 1 | | 2 | | | | | 0 | 2 | | | 0 | 0 | 0 | 3 | | | 3 | 6 | 6 | 8 | |
| 8:45 9:00 | 1 | | 5 | | 6 | | | | | 0 | 6 | | | 1 | 1 | 2 | 4 | | | 3 | 7 | 9 | 15 | |
| 9:00 9:15 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | 0 | 0 | |
| 9:15 9:30 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | 0 | 0 | |
| 9:30 9:45 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | 0 | 0 | |
| 9:45 10:00 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | 0 | 0 | |
| 10:00 10:15 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | 0 | 0 | |
| 10:15 10:30 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | 0 | 0 | |
| 10:30 10:45 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | 0 | 0 | |
| 10:45 11:00 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | 0 | 0 | |
| TOTAL: | 7 | 0 | 14 | 0 | 21 | 0 | 0 | 0 | 0 | 0 | 21 | 0 | 0 | 6 | 1 | 7 | 13 | 0 | 0 | 15 | 28 | 35 | 56 | |
| TOTAL PK HR: | 7 | 0 | 14 | 0 | 21 | 0 | 0 | 0 | 0 | 0 | 21 | 0 | 0 | 6 | 1 | 7 | 13 | 0 | 0 | 15 | 28 | 35 | 56 | |

Start Time (MD Peak): 11:30
 End Time (MD Peak): 13:30

The Mid-day Peak Hour is from 11:30 AM to 12:30 PM

Turning Movement Count - 15 Minute Vehicle Summary Report (Mid-Day Peak)

| Time Period | Hare Avenue Northbound | | | | | Southbound | | | | | N/S STREET TOTAL | Carling Avenue Eastbound | | | | | Carling Avenue Westbound | | | | | E/W STREET TOTAL | Grand TOTAL | 1 Hour Traffic Volumes (All Scenarios) |
|---------------------|------------------------|----|----|---------|----------|------------|----|----|---------|----------|------------------|--------------------------|----|----|---------|----------|--------------------------|----|----|---------|----------|------------------|-------------|--|
| | LT | ST | RT | U-Turns | NB TOTAL | LT | ST | RT | U-Turns | SB TOTAL | | LT | ST | RT | U-Turns | EB TOTAL | LT | ST | RT | U-Turns | WB TOTAL | | | |
| 11:30 11:45 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | 0 | 0 | |
| 11:45 12:00 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | 0 | 0 | |
| 12:00 12:15 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | 0 | 0 | |
| 12:15 12:30 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | 0 | 0 | |
| 12:30 12:45 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | 0 | 0 | |
| 12:45 13:00 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | 0 | 0 | |
| 13:00 13:15 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | 0 | 0 | |
| 13:15 13:30 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | 0 | 0 | |
| TOTAL: | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| TOTAL PK HR: | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |

Start Time (PM Peak): 16:30
 End Time (PM Peak): 19:30

The PM Peak Hour is from 4:30 PM to 5:30 PM

Turning Movement Count - 15 Minute Vehicle Summary Report (PM Peak)

| Time Period | Hare Avenue Northbound | | | | | Southbound | | | | | N/S STR TOTAL | Carling Avenue Eastbound | | | | | Carling Avenue Westbound | | | | | E/W STR TOTAL | Grand TOTAL | 1 Hour Traffic Volumes (All Scenarios) |
|---------------------|------------------------|----|----|---------|----------|------------|----|----|---------|----------|---------------|--------------------------|----|----|---------|----------|--------------------------|----|----|---------|----------|---------------|-------------|--|
| | LT | ST | RT | U-Turns | NB TOTAL | LT | ST | RT | U-Turns | SB TOTAL | | LT | ST | RT | U-Turns | EB TOTAL | LT | ST | RT | U-Turns | WB TOTAL | | | |
| 16:30 16:45 | 3 | | 2 | | 5 | | | | | 0 | 5 | | | 2 | 0 | 2 | 9 | | | 8 | 17 | 19 | 24 | |
| 16:45 17:00 | 1 | | 3 | | 4 | | | | | 0 | 4 | | | 3 | 1 | 4 | 13 | | | 3 | 16 | 20 | 24 | |
| 17:00 17:15 | 5 | | 4 | | 9 | | | | | 0 | 9 | | | 1 | 0 | 1 | 12 | | | 6 | 18 | 19 | 28 | |
| 17:15 17:30 | 1 | | 2 | | 3 | | | | | 0 | 3 | | | 2 | 0 | 2 | 9 | | | 3 | 12 | 14 | 17 | |
| 17:30 17:45 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | 0 | 0 | |
| 17:45 18:00 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | 0 | 0 | |
| 18:00 18:15 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | 0 | 0 | |
| 18:15 18:30 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | 0 | 0 | |
| 18:30 18:45 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | 0 | 0 | |
| 18:45 19:00 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | 0 | 0 | |
| 19:00 19:15 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | 0 | 0 | |
| 19:15 19:30 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | 0 | 0 | |
| TOTAL: | 10 | 0 | 11 | 0 | 21 | 0 | 0 | 0 | 0 | 0 | 21 | 0 | 0 | 8 | 1 | 9 | 43 | 0 | 0 | 20 | 63 | 72 | 93 | |
| TOTAL PK HR: | 10 | 0 | 11 | 0 | 21 | 0 | 0 | 0 | 0 | 0 | 21 | 0 | 0 | 8 | 1 | 9 | 43 | 0 | 0 | 20 | 63 | 72 | 93 | |

Survey Date: Wednesday March 11 2020
 Weather: Dry



NB (South Leg) Street Name: Hare Avenue
 SB (North Leg) Street Name: _____

EB (West Leg) Street Name: Carling Avenue
 WB (East Leg) Street Name: Carling Avenue

Start Time (AM Peak): 8:00
 End Time (AM Peak): 11:00

| Turning Movement Count - 15 Minute Pedestrian Volume Report (AM Peak) | | | | | | | |
|---|-------------------------------------|-------------------------------------|------------------|---------------------------------------|---------------------------------------|------------------|-------------|
| Time Period | Hare Avenue | | N/S STREET TOTAL | Carling Avenue | | E/W STREET TOTAL | Grand TOTAL |
| | NB Approach (East or West Crossing) | SB Approach (East or West Crossing) | | EB Approach (North or South Crossing) | WB Approach (North or South Crossing) | | |
| 8:00 8:15 | 0 | | 0 | 2 | 0 | 2 | 2 |
| 8:15 8:30 | 0 | | 0 | 0 | 0 | 0 | 0 |
| 8:30 8:45 | 2 | | 2 | 0 | 0 | 0 | 2 |
| 8:45 9:00 | 0 | | 0 | 0 | 0 | 0 | 0 |
| 9:00 9:15 | | | 0 | | | 0 | 0 |
| 9:15 9:30 | | | 0 | | | 0 | 0 |
| 9:30 9:45 | | | 0 | | | 0 | 0 |
| 9:45 10:00 | | | 0 | | | 0 | 0 |
| 10:00 10:15 | | | 0 | | | 0 | 0 |
| 10:15 10:30 | | | 0 | | | 0 | 0 |
| 10:30 10:45 | | | 0 | | | 0 | 0 |
| 10:45 11:00 | | | 0 | | | 0 | 0 |
| TOTAL: | 2 | 0 | 2 | 2 | 0 | 2 | 4 |
| TOTAL PK HR: | 2 | 0 | 2 | 2 | 0 | 2 | 4 |

Start Time (MD Peak): 11:30
 End Time (MD Peak): 13:30

| Turning Movement Count - 15 Minute Pedestrian Volume Report (Mid-Day Peak) | | | | | | | |
|--|-------------------------------------|-------------------------------------|------------------|---------------------------------------|---------------------------------------|------------------|-------------|
| Time Period | Hare Avenue | | N/S STREET TOTAL | Carling Avenue | | E/W STREET TOTAL | Grand TOTAL |
| | NB Approach (East or West Crossing) | SB Approach (East or West Crossing) | | EB Approach (North or South Crossing) | WB Approach (North or South Crossing) | | |
| 11:30 11:45 | | | 0 | | | 0 | 0 |
| 11:45 12:00 | | | 0 | | | 0 | 0 |
| 12:00 12:15 | | | 0 | | | 0 | 0 |
| 12:15 12:30 | | | 0 | | | 0 | 0 |
| 12:30 12:45 | | | 0 | | | 0 | 0 |
| 12:45 13:00 | | | 0 | | | 0 | 0 |
| 13:00 13:15 | | | 0 | | | 0 | 0 |
| 13:15 13:30 | | | 0 | | | 0 | 0 |
| TOTAL: | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| TOTAL PK HR: | 0 | 0 | 0 | 0 | 0 | 0 | 0 |

Start Time (PM Peak): 16:30
 End Time (PM Peak): 19:30

| Turning Movement Count - 15 Minute Pedestrian Volume Report (PM Peak) | | | | | | | |
|---|-------------------------------------|-------------------------------------|------------------|---------------------------------------|---------------------------------------|------------------|-------------|
| Time Period | Hare Avenue | | N/S STREET TOTAL | Carling Avenue | | E/W STREET TOTAL | Grand TOTAL |
| | NB Approach (East or West Crossing) | SB Approach (East or West Crossing) | | EB Approach (North or South Crossing) | WB Approach (North or South Crossing) | | |
| 16:30 16:45 | 1 | | 1 | 0 | 0 | 0 | 1 |
| 16:45 17:00 | 4 | | 4 | 0 | 0 | 0 | 4 |
| 17:00 17:15 | 5 | | 5 | 1 | 0 | 1 | 6 |
| 17:15 17:30 | 2 | | 2 | 1 | 0 | 1 | 3 |
| 17:30 17:45 | | | 0 | | | 0 | 0 |
| 17:45 18:00 | | | 0 | | | 0 | 0 |
| 18:00 18:15 | | | 0 | | | 0 | 0 |
| 18:15 18:30 | | | 0 | | | 0 | 0 |
| 18:30 18:45 | | | 0 | | | 0 | 0 |
| 18:45 19:00 | | | 0 | | | 0 | 0 |
| 19:00 19:15 | | | 0 | | | 0 | 0 |
| 19:15 19:30 | | | 0 | | | 0 | 0 |
| TOTAL: | 12 | 0 | 12 | 2 | 0 | 2 | 14 |
| TOTAL PK HR: | 12 | 0 | 12 | 2 | 0 | 2 | 14 |

Survey Date: Wednesday March 11 2020
 Weather: Dry

NB (South Leg) Street Name: Hare Avenue
 SB (North Leg) Street Name: _____

EB (West Leg) Street Name: Carling Avenue
 WB (East Leg) Street Name: Carling Avenue



Start Time (AM Peak): 8:00
 End Time (AM Peak): 11:00

| Turning Movement Count - 15 Minute Heavy Vehicle Report (AM Peak) | | | | | | | | | | | | | | | | | | | | | | | |
|---|------------------------|----|----|---------|----------|------------|----|----|---------|----------|------------------|--------------------------|----|----|---------|----------|--------------------------|----|----|---------|----------|------------------|-------------|
| Time Period | Hare Avenue Northbound | | | | | Southbound | | | | | N/S STREET TOTAL | Carling Avenue Eastbound | | | | | Carling Avenue Westbound | | | | | E/W STREET TOTAL | Grand TOTAL |
| | LT | ST | RT | U-Turns | NB TOTAL | LT | ST | RT | U-Turns | SB TOTAL | | LT | ST | RT | U-Turns | EB TOTAL | LT | ST | RT | U-Turns | WB TOTAL | | |
| 8:00 8:15 | 0 | | 1 | | 1 | | | | | 0 | 1 | | | 0 | 0 | 0 | | | 0 | 0 | 0 | | |
| 8:15 8:30 | 0 | | 0 | | 0 | | | | | 0 | 0 | | | 0 | 0 | 0 | | | 0 | 0 | 0 | | |
| 8:30 8:45 | 0 | | 0 | | 0 | | | | | 0 | 0 | | | 0 | 0 | 0 | | | 0 | 0 | 0 | | |
| 8:45 9:00 | 0 | | 0 | | 0 | | | | | 0 | 0 | | 1 | 0 | 1 | 0 | | | 0 | 0 | 1 | | |
| 9:00 9:15 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | | |
| 9:15 9:30 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | | |
| 9:30 9:45 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | | |
| 9:45 10:00 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | | |
| 10:00 10:15 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | | |
| 10:15 10:30 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | | |
| 10:30 10:45 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | | |
| 10:45 11:00 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | | |
| TOTAL: | 0 | 0 | 1 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | | |
| TOTAL PK HR: | 0 | 0 | 1 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | | |

Start Time (MD Peak): 11:30
 End Time (MD Peak): 13:30

| Turning Movement Count - 15 Minute Heavy Vehicle Report (Mid-Day Peak) | | | | | | | | | | | | | | | | | | | | | | | |
|--|------------------------|----|----|---------|----------|------------|----|----|---------|----------|------------------|--------------------------|----|----|---------|----------|--------------------------|----|----|---------|----------|------------------|-------------|
| Time Period | Hare Avenue Northbound | | | | | Southbound | | | | | N/S STREET TOTAL | Carling Avenue Eastbound | | | | | Carling Avenue Westbound | | | | | E/W STREET TOTAL | Grand TOTAL |
| | LT | ST | RT | U-Turns | NB TOTAL | LT | ST | RT | U-Turns | SB TOTAL | | LT | ST | RT | U-Turns | EB TOTAL | LT | ST | RT | U-Turns | WB TOTAL | | |
| 11:30 11:45 | | | | | 0 | | | | | 0 | 0 | | | 0 | | | | | | 0 | 0 | | |
| 11:45 12:00 | | | | | 0 | | | | | 0 | 0 | | | 0 | | | | | | 0 | 0 | | |
| 12:00 12:15 | | | | | 0 | | | | | 0 | 0 | | | 0 | | | | | | 0 | 0 | | |
| 12:15 12:30 | | | | | 0 | | | | | 0 | 0 | | | 0 | | | | | | 0 | 0 | | |
| 12:30 12:45 | | | | | 0 | | | | | 0 | 0 | | | 0 | | | | | | 0 | 0 | | |
| 12:45 13:00 | | | | | 0 | | | | | 0 | 0 | | | 0 | | | | | | 0 | 0 | | |
| 13:00 13:15 | | | | | 0 | | | | | 0 | 0 | | | 0 | | | | | | 0 | 0 | | |
| 13:15 13:30 | | | | | 0 | | | | | 0 | 0 | | | 0 | | | | | | 0 | 0 | | |
| TOTAL: | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | |
| TOTAL PK HR: | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | |

Start Time (PM Peak): 16:30
 End Time (PM Peak): 19:30

| Turning Movement Count - 15 Minute Heavy Vehicle Report (PM Peak) | | | | | | | | | | | | | | | | | | | | | | | |
|---|------------------------|----|----|---------|----------|------------|----|----|---------|----------|------------------|--------------------------|----|----|---------|----------|--------------------------|----|----|---------|----------|------------------|-------------|
| Time Period | Hare Avenue Northbound | | | | | Southbound | | | | | N/S STREET TOTAL | Carling Avenue Eastbound | | | | | Carling Avenue Westbound | | | | | E/W STREET TOTAL | Grand TOTAL |
| | LT | ST | RT | U-Turns | NB TOTAL | LT | ST | RT | U-Turns | SB TOTAL | | LT | ST | RT | U-Turns | EB TOTAL | LT | ST | RT | U-Turns | WB TOTAL | | |
| 16:30 16:45 | 0 | | 0 | | 0 | | | | | 0 | 0 | | | 0 | 0 | 0 | | | 1 | 1 | 1 | | |
| 16:45 17:00 | 0 | | 0 | | 0 | | | | | 0 | 0 | | 1 | 1 | 1 | 0 | | | 0 | 0 | 1 | | |
| 17:00 17:15 | 0 | | 0 | | 0 | | | | | 0 | 0 | | 0 | 0 | 0 | 0 | | | 0 | 0 | 0 | | |
| 17:15 17:30 | 0 | | 0 | | 0 | | | | | 0 | 0 | | 0 | 0 | 0 | 0 | | | 0 | 0 | 0 | | |
| 17:30 17:45 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | | |
| 17:45 18:00 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | | |
| 18:00 18:15 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | | |
| 18:15 18:30 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | | |
| 18:30 18:45 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | | |
| 18:45 19:00 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | | |
| 19:00 19:15 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | | |
| 19:15 19:30 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | | |
| TOTAL: | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 1 | 0 | 0 | 0 | 1 | 1 | 2 | | |
| TOTAL PK HR: | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 1 | 0 | 0 | 0 | 1 | 1 | 2 | | |

Survey Date: Wednesday March 11 2020
 Weather: Dry



NB (South Leg) Street Name: _____
 SB (North Leg) Street Name: Bromley Road

EB (West Leg) Street Name: _____
 WB (East Leg) Street Name: Carling Avenue

Start Time (AM Peak): 8:00
 End Time (AM Peak): 11:00

The AM Peak Hour is from 8:00 AM to 9:00 AM **AADT Factor:** 1.0

| Turning Movement Count - 15 Minute Vehicle Summary Report (AM Peak) | | | | | | | | | | | | | | | | | | | | | | | | |
|---|------------|----|----|---------|----------|-------------------------|----|----|---------|----------|------------------|--------------------------|----|----|---------|----------|--------------------------|----|----|---------|----------|------------------|-------------|--|
| Time Period | Northbound | | | | | Bromley Road Southbound | | | | | N/S STREET TOTAL | Carling Avenue Eastbound | | | | | Carling Avenue Westbound | | | | | E/W STREET TOTAL | Grand TOTAL | 1 Hour Traffic Volumes (All Scenarios) |
| | LT | ST | RT | U-Turns | NB TOTAL | LT | ST | RT | U-Turns | SB TOTAL | | LT | ST | RT | U-Turns | EB TOTAL | LT | ST | RT | U-Turns | WB TOTAL | | | |
| 8:00 8:15 | | | | | 0 | | | 2 | | 2 | 2 | | | | 0 | | | 2 | | 2 | 2 | 4 | | |
| 8:15 8:30 | | | | | 0 | | | 5 | | 5 | 5 | | | | 0 | | | 2 | | 2 | 2 | 7 | | |
| 8:30 8:45 | | | | | 0 | | | 3 | | 3 | 3 | | | | 0 | | | 1 | | 1 | 1 | 4 | | |
| 8:45 9:00 | | | | | 0 | | | 3 | | 3 | 3 | | | | 0 | | | 0 | | 0 | 0 | 3 | | |
| 9:00 9:15 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | 0 | | |
| 9:15 9:30 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | 0 | | |
| 9:30 9:45 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | 0 | | |
| 9:45 10:00 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | 0 | | |
| 10:00 10:15 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | 0 | | |
| 10:15 10:30 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | 0 | | |
| 10:30 10:45 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | 0 | | |
| 10:45 11:00 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | 0 | | |
| TOTAL: | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 13 | 0 | 13 | 13 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 5 | 0 | 5 | 5 | 18 | |
| TOTAL PK HR: | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 13 | 0 | 13 | 13 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 5 | 0 | 5 | 5 | 18 | |

Start Time (MD Peak): 11:30
 End Time (MD Peak): 13:30

The Mid-day Peak Hour is from 11:30 AM to 12:30 PM

| Turning Movement Count - 15 Minute Vehicle Summary Report (Mid-Day Peak) | | | | | | | | | | | | | | | | | | | | | | | | |
|--|------------|----|----|---------|----------|-------------------------|----|----|---------|----------|------------------|--------------------------|----|----|---------|----------|--------------------------|----|----|---------|----------|------------------|-------------|--|
| Time Period | Northbound | | | | | Bromley Road Southbound | | | | | N/S STREET TOTAL | Carling Avenue Eastbound | | | | | Carling Avenue Westbound | | | | | E/W STREET TOTAL | Grand TOTAL | 1 Hour Traffic Volumes (All Scenarios) |
| | LT | ST | RT | U-Turns | NB TOTAL | LT | ST | RT | U-Turns | SB TOTAL | | LT | ST | RT | U-Turns | EB TOTAL | LT | ST | RT | U-Turns | WB TOTAL | | | |
| 11:30 11:45 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | 0 | | |
| 11:45 12:00 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | 0 | | |
| 12:00 12:15 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | 0 | | |
| 12:15 12:30 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | 0 | | |
| 12:30 12:45 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | 0 | | |
| 12:45 13:00 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | 0 | | |
| 13:00 13:15 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | 0 | | |
| 13:15 13:30 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | 0 | | |
| TOTAL: | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | 0 |
| TOTAL PK HR: | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | 0 |

Start Time (PM Peak): 16:30
 End Time (PM Peak): 19:30

The PM Peak Hour is from 4:30 PM to 5:30 PM

| Turning Movement Count - 15 Minute Vehicle Summary Report (PM Peak) | | | | | | | | | | | | | | | | | | | | | | | | |
|---|------------|----|----|---------|----------|-------------------------|----|----|---------|----------|---------------|--------------------------|----|----|---------|----------|--------------------------|----|----|---------|----------|---------------|-------------|--|
| Time Period | Northbound | | | | | Bromley Road Southbound | | | | | N/S STR TOTAL | Carling Avenue Eastbound | | | | | Carling Avenue Westbound | | | | | E/W STR TOTAL | Grand TOTAL | 1 Hour Traffic Volumes (All Scenarios) |
| | LT | ST | RT | U-Turns | NB TOTAL | LT | ST | RT | U-Turns | SB TOTAL | | LT | ST | RT | U-Turns | EB TOTAL | LT | ST | RT | U-Turns | WB TOTAL | | | |
| 16:30 16:45 | | | | | 0 | | | 5 | | 5 | 5 | | | | 0 | | | 9 | | 9 | 9 | 14 | | |
| 16:45 17:00 | | | | | 0 | | | 3 | | 3 | 3 | | | | 0 | | | 4 | | 4 | 4 | 7 | | |
| 17:00 17:15 | | | | | 0 | | | 2 | | 2 | 2 | | | | 0 | | | 1 | | 1 | 1 | 3 | | |
| 17:15 17:30 | | | | | 0 | | | 1 | | 1 | 1 | | | | 0 | | | 2 | | 2 | 2 | 3 | | |
| 17:30 17:45 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | 0 | | |
| 17:45 18:00 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | 0 | | |
| 18:00 18:15 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | 0 | | |
| 18:15 18:30 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | 0 | | |
| 18:30 18:45 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | 0 | | |
| 18:45 19:00 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | 0 | | |
| 19:00 19:15 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | 0 | | |
| 19:15 19:30 | | | | | 0 | | | | | 0 | 0 | | | | 0 | | | | | 0 | 0 | 0 | | |
| TOTAL: | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 11 | 0 | 11 | 11 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 16 | 0 | 16 | 16 | 27 | |
| TOTAL PK HR: | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 11 | 0 | 11 | 11 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 16 | 0 | 16 | 16 | 27 | |

Survey Date: Wednesday March 11 2020
 Weather: Dry



NB (South Leg) Street Name: _____
 SB (North Leg) Street Name: Bromley Road

EB (West Leg) Street Name: _____
 WB (East Leg) Street Name: Carling Avenue

Start Time (AM Peak): 8:00
 End Time (AM Peak): 11:00

| Turning Movement Count - 15 Minute Pedestrian Volume Report (AM Peak) | | | | | | | |
|---|-------------------------------------|-------------------------------------|------------------|---------------------------------------|---------------------------------------|------------------|-------------|
| Time Period | Bromley Road | | N/S STREET TOTAL | Carling Avenue | | E/W STREET TOTAL | Grand TOTAL |
| | NB Approach (East or West Crossing) | SB Approach (East or West Crossing) | | EB Approach (North or South Crossing) | WB Approach (North or South Crossing) | | |
| 8:00 8:15 | | 2 | 2 | 0 | 0 | 0 | 2 |
| 8:15 8:30 | | 3 | 3 | 0 | 0 | 0 | 3 |
| 8:30 8:45 | | 2 | 2 | 0 | 0 | 0 | 2 |
| 8:45 9:00 | | 1 | 1 | 0 | 0 | 0 | 1 |
| 9:00 9:15 | | | 0 | | | 0 | 0 |
| 9:15 9:30 | | | 0 | | | 0 | 0 |
| 9:30 9:45 | | | 0 | | | 0 | 0 |
| 9:45 10:00 | | | 0 | | | 0 | 0 |
| 10:00 10:15 | | | 0 | | | 0 | 0 |
| 10:15 10:30 | | | 0 | | | 0 | 0 |
| 10:30 10:45 | | | 0 | | | 0 | 0 |
| 10:45 11:00 | | | 0 | | | 0 | 0 |
| TOTAL: | 0 | 8 | 8 | 0 | 0 | 0 | 8 |
| TOTAL PK HR: | 0 | 8 | 8 | 0 | 0 | 0 | 8 |

Start Time (MD Peak): 11:30
 End Time (MD Peak): 13:30

| Turning Movement Count - 15 Minute Pedestrian Volume Report (Mid-Day Peak) | | | | | | | |
|--|-------------------------------------|-------------------------------------|------------------|---------------------------------------|---------------------------------------|------------------|-------------|
| Time Period | Bromley Road | | N/S STREET TOTAL | Carling Avenue | | E/W STREET TOTAL | Grand TOTAL |
| | NB Approach (East or West Crossing) | SB Approach (East or West Crossing) | | EB Approach (North or South Crossing) | WB Approach (North or South Crossing) | | |
| 11:30 11:45 | | | 0 | | | 0 | 0 |
| 11:45 12:00 | | | 0 | | | 0 | 0 |
| 12:00 12:15 | | | 0 | | | 0 | 0 |
| 12:15 12:30 | | | 0 | | | 0 | 0 |
| 12:30 12:45 | | | 0 | | | 0 | 0 |
| 12:45 13:00 | | | 0 | | | 0 | 0 |
| 13:00 13:15 | | | 0 | | | 0 | 0 |
| 13:15 13:30 | | | 0 | | | 0 | 0 |
| TOTAL: | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| TOTAL PK HR: | 0 | 0 | 0 | 0 | 0 | 0 | 0 |

Start Time (PM Peak): 16:30
 End Time (PM Peak): 19:30

| Turning Movement Count - 15 Minute Pedestrian Volume Report (PM Peak) | | | | | | | |
|---|-------------------------------------|-------------------------------------|------------------|---------------------------------------|---------------------------------------|------------------|-------------|
| Time Period | Bromley Road | | N/S STREET TOTAL | Carling Avenue | | E/W STREET TOTAL | Grand TOTAL |
| | NB Approach (East or West Crossing) | SB Approach (East or West Crossing) | | EB Approach (North or South Crossing) | WB Approach (North or South Crossing) | | |
| 16:30 16:45 | | 2 | 2 | 0 | 0 | 0 | 2 |
| 16:45 17:00 | | 8 | 8 | 0 | 0 | 0 | 8 |
| 17:00 17:15 | | 6 | 6 | 0 | 0 | 0 | 6 |
| 17:15 17:30 | | 5 | 5 | 0 | 0 | 0 | 5 |
| 17:30 17:45 | | | 0 | | | 0 | 0 |
| 17:45 18:00 | | | 0 | | | 0 | 0 |
| 18:00 18:15 | | | 0 | | | 0 | 0 |
| 18:15 18:30 | | | 0 | | | 0 | 0 |
| 18:30 18:45 | | | 0 | | | 0 | 0 |
| 18:45 19:00 | | | 0 | | | 0 | 0 |
| 19:00 19:15 | | | 0 | | | 0 | 0 |
| 19:15 19:30 | | | 0 | | | 0 | 0 |
| TOTAL: | 0 | 21 | 21 | 0 | 0 | 0 | 21 |
| TOTAL PK HR: | 0 | 21 | 21 | 0 | 0 | 0 | 21 |

Turning Movement Count - Peak Hour Diagram


CARLING AVE @ MAITLAND AVE/SHERBOURNE RD

Survey Date: Thursday, March 30, 2017

Start Time: 07:00

WO No: 36828

Device: Miovision



Turning Movement Count - Peak Hour Diagram


CARLING AVE @ MAITLAND AVE/SHERBOURNE RD

Survey Date: Thursday, March 30, 2017

Start Time: 07:00

WO No: 36828

Device: Miovision



Appendix D – OC Transpo Routes



85

GATINEAU BAYSHORE

Fréquent

7 days a week / 7 jours par semaine

All day service

Service toute la journée

GATINEAU



BAYSHORE

- Station
- Timepoint / Heures de passage

2019.07



Future route after O-Train Line 1 is open
Trajet du circuit après l'ouverture de la Ligne 1 de l'O-Train

Lost and Found / Objets perdus..... **613-563-4011**
Security / Sécurité **613-741-2478**



INFO 613-741-4390
octranspo.com

Appendix E – Collision Data



City Operations - Transportation Services

Collision Details Report - Public Version

From: January 1, 2014 **To:** December 31, 2018

Location: BROMLEY RD @ CARLING AVE

Traffic Control: Stop sign

Total Collisions: 2

| Date/Day/Time | Environment | Impact Type | Classification | Surface Cond'n | Veh. Dir | Vehicle Manoeuvre | Vehicle type | First Event | No. Ped |
|------------------------|-------------|-------------|----------------|----------------|----------|-------------------|---------------------------|---------------------|---------|
| 2014-Feb-11, Tue,15:40 | Clear | Sideswipe | P.D. only | Wet | West | Changing lanes | Passenger van | Other motor vehicle | |
| | | | | | West | Going ahead | Automobile, station wagon | Other motor vehicle | |
| 2016-May-27, Fri,14:59 | Clear | Sideswipe | P.D. only | Dry | South | Turning right | Automobile, station wagon | Other motor vehicle | |
| | | | | | South | Turning right | Automobile, station wagon | Other motor vehicle | |

Location: CARLING AVE @ HARE AVE

Traffic Control: Stop sign

Total Collisions: 3

| Date/Day/Time | Environment | Impact Type | Classification | Surface Cond'n | Veh. Dir | Vehicle Manoeuvre | Vehicle type | First Event | No. Ped |
|------------------------|-------------|------------------|------------------|----------------|----------|-------------------|---------------------------|---------------------|---------|
| 2014-Jan-25, Sat,13:27 | Clear | Angle | P.D. only | Wet | North | Turning left | Pick-up truck | Other motor vehicle | |
| | | | | | East | Going ahead | Automobile, station wagon | Other motor vehicle | |
| 2015-Jun-05, Fri,13:27 | Clear | Sideswipe | P.D. only | Dry | East | Changing lanes | Pick-up truck | Other motor vehicle | |
| | | | | | East | Going ahead | Passenger van | Other motor vehicle | |
| 2016-May-21, Sat,18:21 | Clear | Turning movement | Non-fatal injury | Dry | West | Making "U" turn | Automobile, station wagon | Other motor vehicle | |

East Going ahead Automobile, station wagon Other motor vehicle

Location: CARLING AVE @ IROQUOIS RD

Traffic Control: Traffic signal

Total Collisions: 33

| Date/Day/Time | Environment | Impact Type | Classification | Surface Cond'n | Veh. Dir | Vehicle Manoeuvre | Vehicle type | First Event | No. Ped |
|------------------------|-------------|------------------|------------------|----------------|----------|-------------------|---------------------------|---------------------|---------|
| 2014-Mar-26, Wed,21:15 | Clear | Rear end | P.D. only | Dry | West | Going ahead | Automobile, station wagon | Other motor vehicle | |
| | | | | | West | Going ahead | Automobile, station wagon | Other motor vehicle | |
| 2014-Apr-15, Tue,12:30 | Snow | Angle | Non-fatal injury | Wet | West | Going ahead | Pick-up truck | Other motor vehicle | |
| | | | | | South | Turning left | Automobile, station wagon | Other motor vehicle | |
| 2014-Sep-08, Mon,08:50 | Clear | Angle | P.D. only | Dry | West | Going ahead | Automobile, station wagon | Other motor vehicle | |
| | | | | | North | Going ahead | Pick-up truck | Other motor vehicle | |
| 2015-Sep-08, Tue,14:35 | Clear | Angle | Non-fatal injury | Dry | West | Going ahead | Automobile, station wagon | Other motor vehicle | |
| | | | | | South | Turning left | Automobile, station wagon | Other motor vehicle | |
| 2016-May-05, Thu,17:15 | Clear | Turning movement | Non-fatal injury | Dry | West | Going ahead | Automobile, station wagon | Other motor vehicle | 2 |
| | | | | | East | Turning left | Automobile, station wagon | Other motor vehicle | |
| 2016-Jun-21, Tue,16:00 | Clear | Angle | P.D. only | Dry | South | Turning right | Automobile, station wagon | Other motor vehicle | |
| | | | | | East | Going ahead | Pick-up truck | Other motor vehicle | |

| | | | | | | | | |
|------------------------|-------|------------------|------------------|-------|-------|----------------|---------------------------|---------------------|
| 2016-Oct-31, Mon,10:13 | Clear | Angle | Non-fatal injury | Dry | West | Going ahead | Automobile, station wagon | Other motor vehicle |
| | | | | | South | Going ahead | Automobile, station wagon | Other motor vehicle |
| 2016-Nov-16, Wed,16:11 | Clear | Turning movement | P.D. only | Dry | West | Going ahead | Automobile, station wagon | Other motor vehicle |
| | | | | | East | Turning left | Automobile, station wagon | Other motor vehicle |
| 2016-Dec-04, Sun,13:50 | Clear | Turning movement | P.D. only | Dry | East | Turning left | Automobile, station wagon | Other motor vehicle |
| | | | | | West | Going ahead | Automobile, station wagon | Other motor vehicle |
| 2016-Dec-14, Wed,10:40 | Clear | Rear end | P.D. only | Dry | South | Unknown | Automobile, station wagon | Other motor vehicle |
| | | | | | South | Unknown | Truck - closed | Other motor vehicle |
| 2017-Feb-10, Fri,07:44 | Clear | Turning movement | P.D. only | Dry | West | Turning left | Pick-up truck | Other motor vehicle |
| | | | | | East | Going ahead | Automobile, station wagon | Other motor vehicle |
| 2017-Feb-12, Sun,12:19 | Snow | Angle | P.D. only | Slush | West | Going ahead | Automobile, station wagon | Other motor vehicle |
| | | | | | South | Going ahead | Automobile, station wagon | Other motor vehicle |
| 2017-May-02, Tue,08:31 | Clear | Sideswipe | P.D. only | Dry | West | Changing lanes | Truck - dump | Other motor vehicle |
| | | | | | West | Going ahead | Automobile, station wagon | Other motor vehicle |

| | | | | | | | | | |
|------------------------|-------|------------------|------------------|-----|-------|---------------------|---------------------------|---------------------|---|
| 2017-May-15, Mon,20:15 | Clear | Angle | P.D. only | Dry | East | Going ahead | Automobile, station wagon | Other motor vehicle | |
| | | | | | North | Going ahead | Automobile, station wagon | Other motor vehicle | |
| 2017-Jun-03, Sat,17:14 | Clear | Angle | Non-fatal injury | Dry | East | Going ahead | Automobile, station wagon | Other motor vehicle | |
| | | | | | North | Going ahead | Automobile, station wagon | Other motor vehicle | |
| 2017-Jun-06, Tue,15:05 | Rain | Sideswipe | P.D. only | Wet | East | Changing lanes | Passenger van | Other motor vehicle | |
| | | | | | East | Going ahead | Automobile, station wagon | Other motor vehicle | |
| 2017-Jun-11, Sun,11:40 | Clear | Angle | Non-fatal injury | Dry | East | Slowing or stopping | Automobile, station wagon | Other motor vehicle | |
| | | | | | North | Going ahead | Automobile, station wagon | Other motor vehicle | |
| 2017-Aug-16, Wed,16:56 | Clear | Turning movement | P.D. only | Dry | East | Turning left | Automobile, station wagon | Other motor vehicle | |
| | | | | | West | Going ahead | Automobile, station wagon | Other motor vehicle | |
| 2017-Oct-18, Wed,18:42 | Clear | SMV other | Non-fatal injury | Dry | East | Turning right | Automobile, station wagon | Pedestrian | 2 |
| 2017-Oct-20, Fri,16:15 | Clear | Rear end | P.D. only | Dry | East | Going ahead | Automobile, station wagon | Other motor vehicle | |
| | | | | | East | Slowing or stopping | Automobile, station wagon | Other motor vehicle | |
| 2017-Nov-29, Wed,14:55 | Clear | Angle | P.D. only | Dry | East | Going ahead | Pick-up truck | Other motor vehicle | |

| | | | | | | | | |
|------------------------|-------|------------------|-----------|----------------|-------|---------------------|------------------------------|------------------------|
| | | | | | North | Going ahead | Automobile, station wagon | Other motor vehicle |
| 2017-Dec-02, Sat,21:11 | Clear | Angle | P.D. only | Dry | East | Going ahead | Automobile, station wagon | Other motor vehicle |
| | | | | | North | Going ahead | Automobile, station wagon | Other motor vehicle |
| 2018-Jan-02, Tue,09:32 | Snow | Rear end | P.D. only | Loose snow | East | Slowing or stopping | Passenger van | Skidding/sliding |
| | | | | | East | Stopped | Automobile, station wagon | Other motor vehicle |
| 2018-Jan-08, Mon,14:30 | Snow | Turning movement | P.D. only | Packed snow | East | Making "U" turn | Automobile, station wagon | Other motor vehicle |
| | | | | | West | Going ahead | Pick-up truck | Other motor vehicle |
| 2018-Jan-25, Thu,15:23 | Clear | Turning movement | P.D. only | Dry | East | Making "U" turn | Automobile, station wagon | Other motor vehicle |
| | | | | | West | Going ahead | Automobile, station wagon | Other motor vehicle |
| 2018-Feb-09, Fri,11:04 | Clear | Angle | P.D. only | Wet | East | Going ahead | Automobile, station wagon | Other motor vehicle |
| | | | | | North | Going ahead | Automobile, station wagon | Other motor vehicle |
| 2018-Apr-03, Tue,09:02 | Clear | Sideswipe | P.D. only | Dry | East | Changing lanes | Automobile, station wagon | Other motor vehicle |
| | | | | | East | Going ahead | Automobile, station wagon | Other motor vehicle |
| 2018-Apr-08, Sun,17:26 | Clear | Angle | P.D. only | Dry | East | Going ahead | Automobile, station wagon | Other motor vehicle |

| | | | | | | | | |
|-------------------------|---------------|------------------|------------------|-------|-------|---------------------|---------------------------|---------------------|
| | | | | | North | Going ahead | Pick-up truck | Other motor vehicle |
| 2018-Jun-26, Tue, 13:38 | Clear | Rear end | Non-fatal injury | Dry | East | Slowing or stopping | Pick-up truck | Other motor vehicle |
| | | | | | East | Slowing or stopping | Automobile, station wagon | Other motor vehicle |
| | | | | | East | Stopped | Automobile, station wagon | Other motor vehicle |
| 2018-Sep-06, Thu, 16:30 | Clear | Turning movement | Non-fatal injury | Dry | East | Turning left | Municipal transit bus | Other motor vehicle |
| | | | | | West | Going ahead | Automobile, station wagon | Other motor vehicle |
| 2018-Sep-18, Tue, 11:56 | Clear | Turning movement | P.D. only | Dry | East | Turning left | Unknown | Other motor vehicle |
| | | | | | West | Going ahead | Automobile, station wagon | Other motor vehicle |
| 2018-Oct-10, Wed, 17:02 | Clear | Turning movement | P.D. only | Dry | East | Turning left | Automobile, station wagon | Other motor vehicle |
| | | | | | West | Going ahead | Pick-up truck | Other motor vehicle |
| 2018-Dec-14, Fri, 16:30 | Freezing Rain | Turning movement | P.D. only | Slush | East | Turning left | Pick-up truck | Other motor vehicle |
| | | | | | West | Going ahead | Automobile, station wagon | Other motor vehicle |

Location: CARLING AVE @ MAITLAND AVE/SHERBOURNE RD

Traffic Control: Traffic signal

Total Collisions: 63

| Date/Day/Time | Environment | Impact Type | Classification | Surface Cond'n | Veh. Dir | Vehicle Manoeuver | Vehicle type | First Event | No. Ped |
|-------------------------|-------------|-------------|----------------|----------------|----------|---------------------|---------------------------|---------------------|---------|
| 2014-Jan-07, Tue, 15:47 | Clear | Rear end | P.D. only | Dry | North | Slowing or stopping | Automobile, station wagon | Other motor vehicle | |

| | | | | | | | | |
|-------------------------|-------|------------------|-----------|------------|-------|---------------------|---------------------------|---------------------|
| | | | | | North | Stopped | Automobile, station wagon | Other motor vehicle |
| | | | | | North | Stopped | Automobile, station wagon | Other motor vehicle |
| 2014-Jan-25, Sat, 18:00 | Snow | Rear end | P.D. only | Loose snow | North | Slowing or stopping | Automobile, station wagon | Skidding/sliding |
| | | | | | North | Stopped | Automobile, station wagon | Other motor vehicle |
| 2014-Feb-14, Fri, 10:30 | Snow | Approaching | P.D. only | Loose snow | East | Slowing or stopping | Automobile, station wagon | Other motor vehicle |
| | | | | | West | Stopped | Automobile, station wagon | Other motor vehicle |
| 2014-Mar-01, Sat, 12:55 | Clear | Rear end | P.D. only | Wet | West | Going ahead | Pick-up truck | Other motor vehicle |
| | | | | | West | Stopped | Automobile, station wagon | Other motor vehicle |
| 2014-Mar-06, Thu, 17:22 | Clear | Sideswipe | P.D. only | Dry | North | Changing lanes | Passenger van | Other motor vehicle |
| | | | | | North | Going ahead | Automobile, station wagon | Other motor vehicle |
| 2014-Apr-29, Tue, 13:30 | Clear | Rear end | P.D. only | Dry | North | Slowing or stopping | Pick-up truck | Other motor vehicle |
| | | | | | North | Stopped | Automobile, station wagon | Other motor vehicle |
| | | | | | North | Stopped | Automobile, station wagon | Other motor vehicle |
| 2014-May-20, Tue, 17:16 | Clear | Turning movement | P.D. only | Dry | East | Turning left | Automobile, station wagon | Other motor vehicle |
| | | | | | West | Going ahead | Pick-up truck | Other motor vehicle |

| | | | | | | | | |
|------------------------|-------|----------|-----------|-----|-------|-------------|---------------------------|---------------------|
| 2014-Jul-16, Wed,10:05 | Clear | Rear end | P.D. only | Dry | South | Going ahead | Automobile, station wagon | Other motor vehicle |
| | | | | | South | Stopped | Pick-up truck | Other motor vehicle |

| | | | | | | | | |
|------------------------|------|-------|------------------|-----|-------|-------------|---------------------------|---------------------|
| 2014-Aug-12, Tue,21:28 | Rain | Angle | Non-fatal injury | Wet | North | Going ahead | Pick-up truck | Other motor vehicle |
| | | | | | West | Going ahead | Automobile, station wagon | Other motor vehicle |

| | | | | | | | | |
|------------------------|-------|-----------|-----------|-----|-------|----------------|---------------------------|---------------------|
| 2014-Sep-14, Sun,10:37 | Clear | Sideswipe | P.D. only | Dry | North | Changing lanes | Unknown | Other motor vehicle |
| | | | | | North | Going ahead | Automobile, station wagon | Other motor vehicle |

| | | | | | | | | |
|------------------------|-------|-----------|----------------|-----|------|---------|---------------------------|---------------------|
| 2014-Sep-23, Tue,12:15 | Clear | Sideswipe | Non-reportable | Dry | East | Unknown | Pick-up truck | Other motor vehicle |
| | | | | | East | Unknown | Automobile, station wagon | Other motor vehicle |

| | | | | | | | | |
|------------------------|-------|-----------|-----------|-----|------|--------------|-------------------|---------------------|
| 2014-Nov-12, Wed,12:03 | Clear | Sideswipe | P.D. only | Dry | West | Turning left | Truck and trailer | Other motor vehicle |
| | | | | | West | Turning left | Pick-up truck | Other motor vehicle |

| | | | | | | | | |
|------------------------|-------|----------|-----------|-----|------|--------------|---------------------------|---------------------|
| 2015-Jan-25, Sun,16:40 | Clear | Rear end | P.D. only | Dry | West | Turning left | Automobile, station wagon | Other motor vehicle |
| | | | | | West | Turning left | Automobile, station wagon | Other motor vehicle |

| | | | | | | | | |
|------------------------|-------|----------|-----------|-------|------|---------------------|---------------------------|---------------------|
| 2015-Jan-26, Mon,15:33 | Clear | Rear end | P.D. only | Slush | West | Slowing or stopping | Automobile, station wagon | Other motor vehicle |
| | | | | | West | Stopped | Automobile, station wagon | Other motor vehicle |

| | | | | | | | | |
|------------------------|-------|----------|-----------|-----|-------|---------------------|---------------------------|---------------------|
| 2015-Feb-13, Fri,19:03 | Clear | Rear end | P.D. only | Dry | North | Slowing or stopping | Automobile, station wagon | Other motor vehicle |
| | | | | | North | Stopped | Pick-up truck | Other motor vehicle |

| | | | | | | | | |
|------------------------|------|----------|-----------|-----|------|-------------|---------------------------|---------------------|
| 2015-May-11, Mon,13:40 | Rain | Rear end | P.D. only | Wet | West | Going ahead | Pick-up truck | Other motor vehicle |
| | | | | | West | Stopped | Automobile, station wagon | Other motor vehicle |

| | | | | | | | | |
|------------------------|-------|------------------|-----------|-----|-------|--------------|---------------------------|---------------------|
| 2015-Jul-04, Sat,16:11 | Clear | Turning movement | P.D. only | Dry | North | Turning left | Automobile, station wagon | Other motor vehicle |
| | | | | | South | Going ahead | Passenger van | Other motor vehicle |

| | | | | | | | | |
|------------------------|-------|----------|-----------|-----|------|-------------|---------------|---------------------|
| 2015-Sep-18, Fri,16:00 | Clear | Rear end | P.D. only | Dry | West | Going ahead | Pick-up truck | Other motor vehicle |
| | | | | | West | Stopped | Passenger van | Other motor vehicle |

| | | | | | | | | |
|------------------------|-------|----------|-----------|-----|------|-------------|---------------------------|---------------------|
| 2015-Sep-21, Mon,18:32 | Clear | Rear end | P.D. only | Dry | West | Going ahead | Pick-up truck | Other motor vehicle |
| | | | | | West | Stopped | Automobile, station wagon | Other motor vehicle |
| | | | | | West | Stopped | Pick-up truck | Other motor vehicle |

| | | | | | | | | |
|------------------------|-------|-----------|-----------|-----|------|----------------|---------------------------|---------------------|
| 2015-Sep-27, Sun,13:53 | Clear | Sideswipe | P.D. only | Dry | West | Changing lanes | Automobile, station wagon | Other motor vehicle |
| | | | | | West | Going ahead | Automobile, station wagon | Other motor vehicle |

| | | | | | | | | |
|------------------------|-------|----------|-----------|-----|------|-------------|---------------------------|---------------------|
| 2015-Sep-30, Wed,16:19 | Clear | Rear end | P.D. only | Dry | West | Going ahead | Automobile, station wagon | Other motor vehicle |
| | | | | | West | Stopped | Pick-up truck | Other motor vehicle |

| | | | | | | | | |
|------------------------|-------|-----------|------------------|-----|-------|---------------------|---------------------------|---------------------|
| 2015-Oct-21, Wed,00:23 | Clear | Angle | P.D. only | Dry | West | Making "U" turn | Automobile, station wagon | Other motor vehicle |
| | | | | | North | Turning right | Pick-up truck | Other motor vehicle |
| 2015-Oct-31, Sat,11:57 | Clear | Rear end | P.D. only | Dry | West | Changing lanes | Automobile, station wagon | Other motor vehicle |
| | | | | | West | Stopped | Automobile, station wagon | Other motor vehicle |
| 2015-Nov-11, Wed,16:57 | Clear | Sideswipe | P.D. only | Dry | South | Changing lanes | Automobile, station wagon | Other motor vehicle |
| | | | | | South | Going ahead | Automobile, station wagon | Other motor vehicle |
| 2015-Nov-20, Fri,18:34 | Clear | Rear end | Non-fatal injury | Dry | North | Going ahead | Pick-up truck | Other motor vehicle |
| | | | | | North | Slowing or stopping | Pick-up truck | Other motor vehicle |
| 2016-Jan-20, Wed,15:37 | Clear | Sideswipe | P.D. only | Dry | West | Changing lanes | Automobile, station wagon | Other motor vehicle |
| | | | | | West | Going ahead | Pick-up truck | Other motor vehicle |
| 2016-Feb-14, Sun,16:45 | Clear | Rear end | P.D. only | Dry | West | Changing lanes | Automobile, station wagon | Other motor vehicle |
| | | | | | West | Going ahead | Automobile, station wagon | Other motor vehicle |
| 2016-Mar-07, Mon,15:26 | Clear | Rear end | P.D. only | Dry | West | Going ahead | Pick-up truck | Other motor vehicle |
| | | | | | West | Stopped | Passenger van | Other motor vehicle |

| | | | | | | | | |
|------------------------|-------|-----------|------------------|------------|-------|---------------------|---------------------------|---------------------|
| 2016-Jun-30, Thu,11:35 | Clear | Rear end | Non-fatal injury | Dry | North | Going ahead | Pick-up truck | Other motor vehicle |
| | | | | | North | Stopped | Automobile, station wagon | Other motor vehicle |
| 2016-Sep-08, Thu,12:19 | Clear | Rear end | P.D. only | Dry | North | Slowing or stopping | Pick-up truck | Other motor vehicle |
| | | | | | North | Stopped | Automobile, station wagon | Other motor vehicle |
| 2016-Sep-20, Tue,11:59 | Clear | Sideswipe | P.D. only | Dry | West | Changing lanes | Automobile, station wagon | Other motor vehicle |
| | | | | | West | Going ahead | Passenger van | Other motor vehicle |
| 2016-Oct-21, Fri,11:43 | Rain | Sideswipe | P.D. only | Wet | West | Turning left | Truck and trailer | Other motor vehicle |
| | | | | | West | Going ahead | Automobile, station wagon | Other motor vehicle |
| 2016-Nov-07, Mon,09:02 | Clear | Sideswipe | P.D. only | Dry | West | Turning left | Construction equipment | Other motor vehicle |
| | | | | | West | Stopped | Automobile, station wagon | Other motor vehicle |
| | | | | | West | Stopped | Pick-up truck | Other motor vehicle |
| 2016-Nov-11, Fri,15:43 | Clear | Rear end | P.D. only | Dry | North | Turning left | Passenger van | Other motor vehicle |
| | | | | | North | Turning left | Passenger van | Other motor vehicle |
| 2017-Feb-05, Sun,13:46 | Snow | Rear end | P.D. only | Loose snow | West | Slowing or stopping | Automobile, station wagon | Other motor vehicle |
| | | | | | West | Stopped | Pick-up truck | Other motor vehicle |

| | | | | | | | | |
|------------------------|-------|-----------|-----------|-----|-------|---------------------|---------------------------|---------------------|
| 2017-Feb-10, Fri,06:45 | Clear | Rear end | P.D. only | Ice | East | Slowing or stopping | Automobile, station wagon | Other motor vehicle |
| | | | | | East | Going ahead | Automobile, station wagon | Other motor vehicle |
| 2017-Feb-23, Thu,15:53 | Clear | Sideswipe | P.D. only | Dry | North | Turning right | Pick-up truck | Other motor vehicle |
| | | | | | North | Turning right | Pick-up truck | Other motor vehicle |
| 2017-Aug-29, Tue,16:45 | Clear | Rear end | P.D. only | Dry | West | Turning left | Automobile, station wagon | Other motor vehicle |
| | | | | | West | Turning left | Automobile, station wagon | Other motor vehicle |
| 2017-Aug-31, Thu,12:54 | Clear | Sideswipe | P.D. only | Dry | South | Changing lanes | Automobile, station wagon | Other motor vehicle |
| | | | | | South | Going ahead | Automobile, station wagon | Other motor vehicle |
| 2017-Sep-07, Thu,17:00 | Rain | Sideswipe | P.D. only | Wet | West | Changing lanes | Automobile, station wagon | Other motor vehicle |
| | | | | | West | Going ahead | Automobile, station wagon | Other motor vehicle |
| 2017-Oct-17, Tue,15:52 | Clear | Sideswipe | P.D. only | Dry | West | Changing lanes | Automobile, station wagon | Other motor vehicle |
| | | | | | West | Going ahead | Automobile, station wagon | Other motor vehicle |
| 2017-Oct-26, Thu,09:33 | Clear | Rear end | P.D. only | Dry | East | Going ahead | Automobile, station wagon | Other motor vehicle |
| | | | | | East | Stopped | Pick-up truck | Other motor vehicle |

| | | | | | | | | |
|------------------------|-------|-----------|-----------|-------------|-------|---------------------|---------------------------|---------------------|
| 2017-Nov-11, Sat,16:15 | Clear | Sideswipe | P.D. only | Dry | East | Changing lanes | Unknown | Other motor vehicle |
| | | | | | East | Stopped | Automobile, station wagon | Other motor vehicle |
| 2017-Nov-14, Tue,17:21 | Clear | Rear end | P.D. only | Dry | West | Going ahead | Pick-up truck | Other motor vehicle |
| | | | | | West | Stopped | Pick-up truck | Other motor vehicle |
| | | | | | West | Stopped | Automobile, station wagon | Other motor vehicle |
| 2017-Dec-12, Tue,15:01 | Snow | Rear end | P.D. only | Loose snow | East | Slowing or stopping | Automobile, station wagon | Other motor vehicle |
| | | | | | East | Unknown | Unknown | Other motor vehicle |
| 2017-Dec-13, Wed,09:37 | Clear | Angle | P.D. only | Slush | East | Turning left | Automobile, station wagon | Other motor vehicle |
| | | | | | North | Going ahead | Automobile, station wagon | Other motor vehicle |
| 2017-Dec-19, Tue,08:55 | Clear | Rear end | P.D. only | Dry | East | Unknown | Passenger van | Other motor vehicle |
| | | | | | East | Stopped | Automobile, station wagon | Other motor vehicle |
| 2018-Jan-14, Sun,11:46 | Clear | Sideswipe | P.D. only | Packed snow | West | Changing lanes | Automobile, station wagon | Other motor vehicle |
| | | | | | West | Going ahead | Automobile, station wagon | Other motor vehicle |
| 2018-Jan-16, Tue,09:05 | Snow | SMV other | P.D. only | Loose snow | West | Slowing or stopping | Automobile, station wagon | Fence/noice barrier |

| | | | | | | | | |
|------------------------|-------|------------------|------------------|-----|-------|---------------------|---------------------------|---------------------|
| 2018-Feb-09, Fri,10:45 | Clear | Turning movement | Non-fatal injury | Wet | North | Turning left | Automobile, station wagon | Other motor vehicle |
| | | | | | South | Going ahead | Automobile, station wagon | Other motor vehicle |
| 2018-Feb-13, Tue,07:55 | Clear | Sideswipe | P.D. only | Dry | East | Changing lanes | Automobile, station wagon | Other motor vehicle |
| | | | | | East | Going ahead | Automobile, station wagon | Other motor vehicle |
| 2018-Mar-04, Sun,08:23 | Clear | Turning movement | P.D. only | Dry | East | Turning right | Automobile, station wagon | Other motor vehicle |
| | | | | | West | Turning left | Automobile, station wagon | Other motor vehicle |
| 2018-Mar-06, Tue,14:30 | Clear | Sideswipe | P.D. only | Dry | East | Changing lanes | Automobile, station wagon | Other motor vehicle |
| | | | | | East | Going ahead | Automobile, station wagon | Other motor vehicle |
| 2018-Mar-28, Wed,16:34 | Clear | Rear end | P.D. only | Dry | North | Slowing or stopping | Automobile, station wagon | Other motor vehicle |
| | | | | | North | Stopped | Automobile, station wagon | Other motor vehicle |
| 2018-Jul-12, Thu,06:32 | Clear | Angle | Non-fatal injury | Dry | East | Going ahead | Automobile, station wagon | Other motor vehicle |
| | | | | | North | Turning right | Automobile, station wagon | Other motor vehicle |
| 2018-Sep-06, Thu,15:00 | Clear | Rear end | P.D. only | Dry | West | Slowing or stopping | Truck - dump | Other motor vehicle |
| | | | | | West | Stopped | Automobile, station wagon | Other motor vehicle |

| | | | | | | | | |
|------------------------|---------------------------------|------------------|-----------|-----|-------|---------------------|---------------------------|---------------------|
| 2018-Oct-11, Thu,19:01 | Fog, mist, smoke, Rear end dust | | P.D. only | Dry | West | Slowing or stopping | Automobile, station wagon | Other motor vehicle |
| | | | | | West | Stopped | Automobile, station wagon | Other motor vehicle |
| 2018-Oct-13, Sat,18:52 | Clear | Turning movement | P.D. only | Dry | East | Turning right | Unknown | Other motor vehicle |
| | | | | | West | Turning left | Automobile, station wagon | Other motor vehicle |
| 2018-Oct-20, Sat,18:00 | Clear | Sideswipe | P.D. only | Dry | South | Changing lanes | Automobile, station wagon | Other motor vehicle |
| | | | | | South | Going ahead | Automobile, station wagon | Other motor vehicle |
| 2018-Nov-13, Tue,18:45 | Clear | Sideswipe | P.D. only | Wet | East | Changing lanes | Automobile, station wagon | Other motor vehicle |
| | | | | | East | Going ahead | Automobile, station wagon | Other motor vehicle |
| 2018-Nov-15, Thu,12:10 | Clear | Rear end | P.D. only | Dry | East | Going ahead | Automobile, station wagon | Other motor vehicle |
| | | | | | East | Stopped | Automobile, station wagon | Other motor vehicle |
| 2018-Nov-30, Fri,13:00 | Clear | Rear end | P.D. only | Dry | East | Going ahead | Unknown | Other motor vehicle |
| | | | | | East | Slowing or stopping | Automobile, station wagon | Other motor vehicle |
| 2018-Dec-08, Sat,16:50 | Clear | Sideswipe | P.D. only | Dry | West | Changing lanes | Automobile, station wagon | Other motor vehicle |
| | | | | | West | Turning left | Automobile, station wagon | Other motor vehicle |

Location: CARLING AVE WB btwn BROMLEY RD & MCKELLAR AVE

Traffic Control: No control

Total Collisions: 2

| Date/Day/Time | Environment | Impact Type | Classification | Surface Cond'n | Veh. Dir | Vehicle Manoeuvre | Vehicle type | First Event | No. Ped |
|------------------------|-------------|-------------|----------------|----------------|----------|-------------------|---------------------------|---------------------|---------|
| 2014-Aug-15, Fri,16:16 | Clear | Sideswipe | P.D. only | Dry | West | Changing lanes | Automobile, station wagon | Other motor vehicle | |
| | | | | | West | Going ahead | Pick-up truck | Other motor vehicle | |
| 2015-Jul-28, Tue,16:07 | Clear | Rear end | P.D. only | Dry | West | Going ahead | Automobile, station wagon | Other motor vehicle | |
| | | | | | West | Stopped | Pick-up truck | Other motor vehicle | |

Location: CARLING AVE WB btwn HARE AVE & BROMLEY RD

Traffic Control: No control

Total Collisions: 5

| Date/Day/Time | Environment | Impact Type | Classification | Surface Cond'n | Veh. Dir | Vehicle Manoeuvre | Vehicle type | First Event | No. Ped |
|------------------------|-------------|-------------|------------------|----------------|----------|-------------------|---------------------------|---------------------|---------|
| 2014-Jan-28, Tue,16:25 | Clear | Rear end | Non-fatal injury | Wet | West | Going ahead | Automobile, station wagon | Other motor vehicle | |
| | | | | | West | Going ahead | Municipal transit bus | Other motor vehicle | |
| 2014-Jun-30, Mon,16:34 | Clear | Other | P.D. only | Dry | East | Reversing | Truck - closed | Other motor vehicle | |
| | | | | | West | Stopped | Automobile, station wagon | Other motor vehicle | |
| 2014-Dec-10, Wed,16:19 | Snow | Rear end | P.D. only | Slush | West | Changing lanes | Automobile, station wagon | Other motor vehicle | |
| | | | | | West | Going ahead | Automobile, station wagon | Other motor vehicle | |
| 2015-Mar-20, Fri,14:54 | Clear | Rear end | P.D. only | Dry | West | Going ahead | Automobile, station wagon | Other motor vehicle | |

| | | | | | | | | |
|------------------------|------|-----------|-----------|----------------|------|------------|------------------------------|------------------------|
| | | | | | West | Stopped | Automobile, station wagon | Other motor vehicle |
| 2017-Mar-15, Wed,08:37 | Snow | SMV other | P.D. only | Packed snow | West | Overtaking | Automobile, station wagon | Curb |

Location: CARLING AVE WB btwn MCKELLAR AVE & SHERBOURNE RD

Traffic Control: No control

Total Collisions: 1

| Date/Day/Time | Environment | Impact Type | Classification | Surface Cond'n | Veh. Dir | Vehicle Manoeuvre | Vehicle type | First Event | No. Ped |
|------------------------|-------------|-------------|------------------|-------------------|----------|-------------------|------------------------------|------------------------|---------|
| 2014-Oct-02, Thu,10:51 | Clear | Rear end | Non-fatal injury | Dry | West | Going ahead | Automobile, station wagon | Other motor vehicle | |
| | | | | | West | Turning right | Pick-up truck | Other motor vehicle | |
| | | | | | South | Turning right | Automobile, station wagon | Other motor vehicle | |



City Operations - Transportation Services

Collision Details Report - Public Version

From: January 1, 2014 **To:** December 31, 2018

Location: CARLING AVE @ HARE AVE

Traffic Control: Stop sign

Total Collisions: 3

| Date/Day/Time | Environment | Impact Type | Classification | Surface Cond'n | Veh. Dir | Vehicle Manoeuvre | Vehicle type | First Event | No. Ped |
|------------------------|-------------|------------------|------------------|----------------|----------|-------------------|---------------------------|---------------------|---------|
| 2016-May-21, Sat,18:21 | Clear | Turning movement | Non-fatal injury | Dry | West | Making "U" turn | Automobile, station wagon | Other motor vehicle | |
| | | | | | East | Going ahead | Automobile, station wagon | Other motor vehicle | |
| 2015-Jun-05, Fri,13:27 | Clear | Sideswipe | P.D. only | Dry | East | Changing lanes | Pick-up truck | Other motor vehicle | |
| | | | | | East | Going ahead | Passenger van | Other motor vehicle | |
| 2014-Jan-25, Sat,13:27 | Clear | Angle | P.D. only | Wet | North | Turning left | Pick-up truck | Other motor vehicle | |
| | | | | | East | Going ahead | Automobile, station wagon | Other motor vehicle | |

Location: CARLING AVE EB btwn HARE AVE & MELWOOD AVE

Traffic Control: No control

Total Collisions: 1

| Date/Day/Time | Environment | Impact Type | Classification | Surface Cond'n | Veh. Dir | Vehicle Manoeuvre | Vehicle type | First Event | No. Ped |
|------------------------|-------------|-------------|----------------|----------------|----------|-------------------|---------------------------|------------------|---------|
| 2015-Aug-15, Sat,07:39 | Clear | SMV other | P.D. only | Dry | East | Going ahead | Automobile, station wagon | Skidding/sliding | |

Location: CARLING AVE EB btwn IROQUOIS RD & KINGSMERE AVE

Traffic Control: No control

Total Collisions: 1

| Date/Day/Time | Environment | Impact Type | Classification | Surface Cond'n | Veh. Dir | Vehicle Manoeuvre | Vehicle type | First Event | No. Ped |
|---------------|-------------|-------------|----------------|----------------|----------|-------------------|--------------|-------------|---------|
|---------------|-------------|-------------|----------------|----------------|----------|-------------------|--------------|-------------|---------|

| | | | | | | | | |
|------------------------|-------|----------|-----------|-----|------|-------------|---------------------------|---------------------|
| 2017-Apr-24, Mon,09:01 | Clear | Rear end | P.D. only | Dry | East | Going ahead | Automobile, station wagon | Other motor vehicle |
| | | | | | East | Stopped | Automobile, station wagon | Other motor vehicle |
| | | | | | East | Stopped | Truck - closed | Other motor vehicle |

Location: CARLING AVE EB btwn MAPLECREST AVE & DUNLEVIE AVE

Traffic Control: No control

Total Collisions: 1

| Date/Day/Time | Environment | Impact Type | Classification | Surface Cond'n | Veh. Dir | Vehicle Manoeuvre | Vehicle type | First Event | No. Ped |
|------------------------|-------------|-------------|----------------|----------------|----------|-------------------|---------------------------|---------------------|---------|
| 2014-Oct-16, Thu,08:40 | Rain | Sideswipe | P.D. only | Wet | East | Changing lanes | Automobile, station wagon | Other motor vehicle | |
| | | | | | East | Going ahead | Automobile, station wagon | Other motor vehicle | |

Location: CARLING AVE EB btwn RIDDELL AVE N & MAITLAND AVE

Traffic Control: No control

Total Collisions: 5

| Date/Day/Time | Environment | Impact Type | Classification | Surface Cond'n | Veh. Dir | Vehicle Manoeuvre | Vehicle type | First Event | No. Ped |
|------------------------|-------------|-------------|----------------|----------------|----------|---------------------|---------------------------|---------------------|---------|
| 2018-Dec-19, Wed,10:11 | Clear | Rear end | P.D. only | Dry | East | Going ahead | Automobile, station wagon | Other motor vehicle | |
| | | | | | East | Going ahead | Automobile, station wagon | Other motor vehicle | |
| 2016-Jul-28, Thu,15:21 | Clear | Rear end | P.D. only | Dry | East | Going ahead | Pick-up truck | Other motor vehicle | |
| | | | | | East | Slowing or stopping | Pick-up truck | Other motor vehicle | |
| 2016-Jan-18, Mon,10:00 | Clear | Rear end | P.D. only | Loose snow | East | Slowing or stopping | Automobile, station wagon | Other motor vehicle | |
| | | | | | East | Stopped | Pick-up truck | Other motor vehicle | |

| | | | | | | | | |
|------------------------|-------|-----------|-----------|-----|------|----------------|------------------------------|------------------------|
| 2015-Aug-27, Thu,15:11 | Clear | Sideswipe | P.D. only | Dry | East | Changing lanes | Automobile, station wagon | Other motor vehicle |
| | | | | | East | Going ahead | Automobile, station wagon | Other motor vehicle |

| | | | | | | | | |
|------------------------|-------|-------|-----------|-----|-------|---------------|------------------------------|------------------------|
| 2015-Jun-15, Mon,16:53 | Clear | Angle | P.D. only | Dry | North | Turning right | Motorcycle | Other motor vehicle |
| | | | | | East | Stopped | Automobile, station wagon | Other motor vehicle |

Appendix F – Trip Generation Data

Table 3.12: Person Trip Generation Rates – (all households with residents not older than 55 years of age)

| Person Trip Generation Rates | | | | | | | | | | |
|---|------------------|------------|--------------------------------------|------------|-------------------------------------|------------|------------------|------------|------------------|------|
| All Households with persons 55 years of age or less AM and PM Peak Hours | | | | | | | | | | |
| Dwelling Unit Types \ Geographic Areas | Core Area | | Urban Area (Inside the greenbelt) | | Suburban (Outside the greenbelt) | | Rural | | All Areas | |
| | Person Trip Rate | % ∇ | Person Trip Rate | % ∇ | Person Trip Rate | % ∇ | Person Trip Rate | % ∇ | Person Trip Rate | |
| Single detached: | AM | 0.85 | - 7% | 0.99 | + 9% | 0.94 | + 3% | 0.78 | - 14% | 0.91 |
| | PM | 0.74 | - 3% | 0.75 | - 1% | 0.79 | + 4% | 0.71 | - 7% | |
| Semi-detached: | AM | 0.79 | - 10% | 0.97 | 10% | 0.89 | + 1% | 0.64 | - 27% | 0.88 |
| | PM | 0.74 | - 1% | 0.68 | - 9% | 0.82 | + 9% | 0.60 | - 20% | |
| Row Townhouse: | AM | 0.71 | - 3% | 0.78 | + 7% | 0.67 | - 8% | 0.74 | + 1% | 0.73 |
| | PM | 0.62 | - 3% | 0.60 | - 6% | 0.69 | + 8% | 0.56 | - 13% | |
| Apartment: | AM | 0.48 | - 4% | 0.51 | + 2% | 0.53 | + 6% | 0.36 | - 28% | 0.50 |
| | PM | 0.45 | 0% | 0.42 | - 7% | 0.52 | + 16% | 0.52 | + 16% | |
| All Types: | AM | 0.62 | - 23% | 0.82 | + 2% | 0.86 | + 8% | 0.76 | - 5% | 0.80 |
| | PM | 0.57 | - 16% | 0.63 | - 7% | 0.75 | + 10% | 0.69 | + 1% | |

Note: 5 % (+ or -) represents the percentage delta change in trip rate when compared against the average trip rate across all geographic areas

Table 3.13: Mode Shares - (all households with residents not older than 55 years of age)

| Reported Mode Shares | | | | | | | | | | | | | | | | |
|---|---------------|---------------|---------------|--------------------------------------|---------------|---------------|-------------------------------------|---------------|---------------|---------------|---------------|---------------|---------------|---------------|---------------|-----|
| All Households with persons 55 years of age or less AM and PM Peak Hours | | | | | | | | | | | | | | | | |
| Dwelling Unit Types \ Geographic Areas | Core Area | | | Urban Area (Inside the greenbelt) | | | Suburban (Outside the greenbelt) | | | Rural* | | | All Areas | | | |
| | Vehicle Trips | Transit Share | Non-Motorised | Vehicle Trips | Transit Share | Non-Motorised | Vehicle Trips | Transit Share | Non-Motorised | Vehicle Trips | Transit Share | Non-Motorised | Vehicle Trips | Transit Share | Non-Motorised | |
| Single - Detached: | AM | 35% | 20% | 33% | 51% | 26% | 11% | 55% | 25% | 9% | 60% | 27% | 4% | 54% | 25% | 10% |
| | PM | 45% | 11% | 32% | 58% | 19% | 13% | 64% | 19% | 6% | 73% | 13% | 2% | 63% | 17% | 8% |
| Semi-Detached: | AM | 38% | 30% | 26% | 44% | 35% | 10% | 52% | 24% | 12% | 64% | 27% | 5% | 49% | 28% | 12% |
| | PM | 36% | 20% | 34% | 51% | 27% | 13% | 62% | 17% | 7% | 77% | 12% | 1% | 58% | 20% | 10% |
| Row / Townhouse: | AM | 33% | 22% | 40% | 45% | 34% | 10% | 55% | 27% | 8% | 73% | 15% | 3% | 49% | 30% | 11% |
| | PM | 39% | 15% | 42% | 53% | 28% | 8% | 61% | 22% | 6% | 74% | 15% | 1% | 57% | 24% | 9% |
| Apartment: | AM | 27% | 27% | 43% | 37% | 41% | 14% | 44% | 34% | 13% | 76% | 8% | 16% | 36% | 35% | 23% |
| | PM | 23% | 29% | 42% | 40% | 37% | 14% | 44% | 33% | 9% | 48% | 4% | 17% | 35% | 33% | 23% |
| All Types: | AM | 32% | 24% | 38% | 47% | 31% | 11% | 54% | 26% | 9% | 61% | 26% | 4% | 51% | 27% | 11% |
| | PM | 34% | 21% | 38% | 53% | 24% | 12% | 62% | 20% | 6% | 73% | 13% | 2% | 59% | 20% | 10% |

Note: Percentages do not necessarily sum to 100% as the proportion of automobile passengers have not been tabulated. Vehicle trips reflect the percentage of vehicle drivers.
* - Rural area sample size is extremely low and mode shares are highly influenced by school types where public transportation levels are high during the AM versus the PM peaks.

Table 6.1: Vehicle Trip Generation Rates

| Vehicle Trip Generation Rates AM and PM Peak Hours | | | | | | |
|---|--|----|------------------------------|------|-----------|--------------|
| ITE Land Use Code | Data Source Dwelling Unit Type | | Vehicle Trip Generation Rate | | | |
| | | | 2008 Count Data | ITE | OD Survey | Blended Rate |
| 210 | Single-detached dwellings | AM | 0.66 | 0.75 | 0.56 | 0.66 |
| | | PM | 0.89 | 1.01 | 0.53 | 0.81 |
| 224 | Semi-detached dwellings, townhouses, rowhouses | AM | 0.40 | 0.70 | 0.46 | 0.52 |
| | | PM | 0.64 | 0.72 | 0.46 | 0.61 |
| 231 | Low-rise condominiums (1 or 2 floors) | AM | 0.53 | 0.67 | 0.21 | 0.47 |
| | | PM | 0.41 | 0.78 | 0.18 | 0.46 |
| 232 | High-rise condominiums (3+ floors) | AM | 0.53 | 0.34 | 0.21 | 0.36 |
| | | PM | 0.41 | 0.38 | 0.18 | 0.32 |
| 233 | Luxury condominiums | AM | 0.53 | 0.56 | 0.21 | 0.43 |
| | | PM | 0.41 | 0.55 | 0.18 | 0.38 |
| 221 | Low-rise apartments (2 floors) | AM | 0.19 | 0.46 | 0.21 | 0.29 |
| | | PM | 0.21 | 0.58 | 0.18 | 0.32 |
| 223 | Mid-rise apartments (3-10 floors) | AM | 0.19 | 0.30 | 0.21 | 0.23 |
| | | PM | 0.21 | 0.39 | 0.18 | 0.26 |
| 222 | High-rise apartments (10+ floors) | AM | 0.19 | 0.30 | 0.21 | 0.23 |
| | | PM | 0.21 | 0.35 | 0.18 | 0.25 |

Table 6.2: Recommended Vehicle Trip Directional Splits

| Comparison of Directional Splits (Inbound/Outbound) AM and PM Peak Hours | | | | | | | | |
|---|--|----|-----------------|----------|---------|----------|--------------|----------|
| ITE Land Use Code | Area Dwelling Unit Type Data Source | | 2008 Count Data | | ITE | | Blended Rate | |
| | | | Inbound | Outbound | Inbound | Outbound | Inbound | Outbound |
| 210 | Single-detached dwellings | AM | 33% | 67% | 25% | 75% | 29% | 71% |
| | | PM | 60% | 40% | 63% | 37% | 62% | 39% |
| 224 | Semi-detached dwellings, townhouses, rowhouses | AM | 40% | 60% | 33% | 67% | 37% | 64% |
| | | PM | 55% | 45% | 51% | 49% | 53% | 47% |
| 231 | Low-rise condominiums (1 or 2 floors) | AM | 36% | 64% | 25% | 75% | 31% | 70% |
| | | PM | 54% | 46% | 58% | 42% | 56% | 44% |
| 232 | High-rise condominiums (3+ floors) | AM | 36% | 64% | 19% | 81% | 28% | 73% |
| | | PM | 54% | 46% | 62% | 38% | 58% | 42% |
| 233 | Luxury condominiums | AM | 36% | 64% | 23% | 77% | 30% | 71% |
| | | PM | 54% | 46% | 63% | 37% | 59% | 42% |
| 221 | Low-rise apartments (2 floors) | AM | 22% | 78% | 21% | 79% | 22% | 79% |
| | | PM | 62% | 38% | 65% | 35% | 64% | 37% |
| 223 | Mid-rise apartments (3-10 floors) | AM | 22% | 78% | 25% | 75% | 24% | 77% |
| | | PM | 62% | 38% | 61% | 39% | 62% | 39% |
| 222 | High-rise apartments (10+ floors) | AM | 22% | 78% | 25% | 75% | 24% | 77% |
| | | PM | 62% | 38% | 61% | 39% | 62% | 39% |

Table 6.3: Recommended Vehicle Trip Generation Rates for Residential Land Uses with Transit Bonus

| Recommended Vehicle Trip Generation Rates with Transit Bonus AM and PM Peak Hours | | | | | | | | | |
|--|--|----|-------------------|-------------------------|---------------------------------|-------------------------|-------------------------------------|-------------------------|-----------|
| ITE Land Use Code | Geographic Area Dwelling Unit Type | | Vehicle Trip Rate | | | | | | |
| | | | Core | | Urban (Inside the Greenbelt) | | Suburban (Outside the Greenbelt) | | Rural |
| | | | Base Rate | < 600m to Rapid Transit | Base Rate | < 600m to Rapid Transit | Base Rate | < 600m to Rapid Transit | Base Rate |
| 210 | Single-detached dwellings | AM | 0.40 | 0.31 | 0.67 | 0.50 | 0.70 | 0.49 | 0.62 |
| | | PM | 0.60 | 0.33 | 0.76 | 0.57 | 0.90 | 0.63 | 0.92 |
| 224 | Semi-detached dwellings, townhouses, rowhouses | AM | 0.34 | 0.34 | 0.51 | 0.50 | 0.54 | 0.39 | 0.62 |
| | | PM | 0.39 | 0.38 | 0.51 | 0.51 | 0.71 | 0.51 | 0.67 |
| 231 | Low-rise condominiums (1 or 2 floors) | AM | 0.34 | 0.34 | 0.50 | 0.50 | 0.60 | 0.60 | 0.71 |
| | | PM | 0.29 | 0.29 | 0.49 | 0.49 | 0.66 | 0.66 | 0.72 |
| 232 | High-rise condominiums (3+ floors) | AM | 0.26 | 0.26 | 0.38 | 0.38 | 0.46 | 0.46 | 0.54 |
| | | PM | 0.20 | 0.20 | 0.34 | 0.34 | 0.46 | 0.46 | 0.50 |
| 233 | Luxury condominiums | AM | 0.31 | 0.31 | 0.45 | 0.45 | 0.55 | 0.55 | 0.65 |
| | | PM | 0.24 | 0.24 | 0.40 | 0.40 | 0.55 | 0.55 | 0.59 |
| 221 | Low-rise apartments (2 floors) | AM | 0.21 | 0.21 | 0.31 | 0.31 | 0.37 | 0.37 | 0.44 |
| | | PM | 0.20 | 0.20 | 0.34 | 0.34 | 0.46 | 0.46 | 0.50 |
| 223 | Mid-rise apartments (3-10 floors) | AM | 0.17 | 0.17 | 0.24 | 0.24 | 0.29 | 0.29 | 0.35 |
| | | PM | 0.16 | 0.16 | 0.28 | 0.28 | 0.37 | 0.37 | 0.41 |
| 222 | High-rise apartments (10+ floors) | AM | 0.17 | 0.17 | 0.24 | 0.24 | 0.29 | 0.29 | 0.35 |
| | | PM | 0.16 | 0.16 | 0.27 | 0.27 | 0.36 | 0.36 | 0.39 |

Note: The transit bonus was only applied to geographic areas and dwelling unit types where the reported transit mode shares were less than the transit mode share reported for residential development located within the 600m proximity to a rapid transit station. It is noted that condominium and apartment housing categories reported similar levels of transit mode shares independent of location to rapid transit stations.

6.5 Future Data Collection

While the rates presented in were prepared by blending the vehicle trip rates from ITE, the OD Survey and the 2008 local trip generation studies, it is important to stress the importance and need for ongoing local trip generation surveys to monitor changes in travel behaviour. The 2008 trip generation studies undertaken to support this study provide insight into local travel patterns and a well organized ongoing annual data collection program aimed at trip generation surveys of key land uses or requirement for data collection by local developers will continue to provide recent and accurate local trip generation rates. For example the high-rise apartment category of dwelling units reported the lowest peak hour vehicle trip rates.

Ottawa West

Demographic Characteristics

| | | | |
|---------------------|--------|-------------------------|--------|
| Population | 50,410 | Actively Travelled | 40,800 |
| Employed Population | 22,930 | Number of Vehicles | 23,590 |
| Households | 24,070 | Area (km ²) | 18.3 |

| Occupation Status (age 5+) | Male | Female | Total |
|----------------------------|---------------|---------------|---------------|
| Full Time Employed | 10,960 | 9,490 | 20,450 |
| Part Time Employed | 930 | 1,540 | 2,480 |
| Student | 4,680 | 4,690 | 9,370 |
| Retiree | 4,580 | 7,260 | 11,840 |
| Unemployed | 570 | 980 | 1,540 |
| Homemaker | 30 | 990 | 1,020 |
| Other | 670 | 600 | 1,270 |
| Total: | 22,410 | 25,560 | 47,970 |


| Traveller Characteristics | Male | Female | Total |
|---------------------------|-------|--------|-------|
| Transit Pass Holders | 4,120 | 5,780 | 9,900 |

| | | | |
|------------------|--------|--------|--------|
| Licensed Drivers | 17,020 | 17,720 | 34,740 |
|------------------|--------|--------|--------|

| | | | |
|---------------|-----|-----|-----|
| Telecommuters | 140 | 250 | 390 |
|---------------|-----|-----|-----|

| | | | |
|-------------------------|--------|--------|---------|
| Trips made by residents | 65,610 | 75,080 | 140,690 |
|-------------------------|--------|--------|---------|



| Selected Indicators | |
|---------------------------------|------|
| Daily Trips per Person (age 5+) | 2.93 |
| Vehicles per Person | 0.47 |
| Number of Persons per Household | 2.09 |
| Daily Trips per Household | 5.85 |
| Vehicles per Household | 0.98 |
| Workers per Household | 0.95 |
| Population Density (Pop/km2) | 2760 |



| Household Size | | |
|----------------|---------------|-------------|
| 1 person | 10,380 | 43% |
| 2 persons | 7,710 | 32% |
| 3 persons | 2,730 | 11% |
| 4 persons | 2,280 | 9% |
| 5+ persons | 970 | 4% |
| Total: | 24,070 | 100% |

| Households by Vehicle Availability | | |
|------------------------------------|---------------|-------------|
| 0 vehicles | 6,230 | 26% |
| 1 vehicle | 12,950 | 54% |
| 2 vehicles | 4,200 | 17% |
| 3 vehicles | 540 | 2% |
| 4+ vehicles | 140 | 1% |
| Total: | 24,070 | 100% |

| Households by Dwelling Type | | |
|-----------------------------|---------------|-------------|
| Single-detached | 8,320 | 35% |
| Semi-detached | 1,780 | 7% |
| Townhouse | 980 | 4% |
| Apartment/Condo | 13,000 | 54% |
| Total: | 24,070 | 100% |




* In 2005 data was only collected for household members aged 11+ therefore these results cannot be compared to the 2011 data.

Travel Patterns

Top Five Origins of Trips to Ottawa West

AM Peak Period



Summary of Trips to and from Ottawa West

| Districts | Destinations of Trips From | | Origins of Trips To | |
|----------------------------|----------------------------|---------|---------------------|---------|
| | District | % Total | District | % Total |
| Ottawa Centre | 4,270 | 16% | 340 | 1% |
| Ottawa Inner Area | 3,080 | 12% | 1,750 | 5% |
| Ottawa East | 310 | 1% | 460 | 1% |
| Beacon Hill | 150 | 1% | 610 | 2% |
| Alta Vista | 1,550 | 6% | 1,160 | 4% |
| Hunt Club | 360 | 1% | 580 | 2% |
| Merivale | 3,340 | 13% | 4,960 | 15% |
| Ottawa West | 8,280 | 32% | 8,280 | 25% |
| Bayshore / Cedarview | 1,940 | 7% | 4,870 | 15% |
| Orléans | 220 | 1% | 1,460 | 4% |
| Rural East | 40 | 0% | 60 | 0% |
| Rural Southeast | 50 | 0% | 190 | 1% |
| South Gloucester / Leitrim | 0 | 0% | 290 | 1% |
| South Nepean | 160 | 1% | 1,830 | 6% |
| Rural Southwest | 80 | 0% | 400 | 1% |
| Kanata / Stittsville | 840 | 3% | 2,020 | 6% |
| Rural West | 70 | 0% | 170 | 1% |
| Île de Hull | 730 | 3% | 170 | 1% |
| Hull Périphérie | 170 | 1% | 360 | 1% |
| Plateau | 40 | 0% | 760 | 2% |
| Aylmer | 60 | 0% | 770 | 2% |
| Rural Northwest | 20 | 0% | 310 | 1% |
| Pointe Gatineau | 30 | 0% | 450 | 1% |
| Gatineau Est | 70 | 0% | 310 | 1% |
| Rural Northeast | 60 | 0% | 170 | 1% |
| Buckingham / Masson-Angers | 70 | 0% | 140 | 0% |
| Ontario Sub-Total: | 24,740 | 95% | 29,430 | 90% |
| Québec Sub-Total: | 1,250 | 5% | 3,440 | 10% |
| Total: | 25,990 | 100% | 32,870 | 100% |

Trips by Trip Purpose

| 24 Hours | From District | | To District | | Within District | |
|---------------------------|---------------|------|-------------|------|-----------------|------|
| Work or related | 17,850 | 19% | 24,050 | 25% | 4,670 | 8% |
| School | 3,820 | 4% | 4,540 | 5% | 4,230 | 7% |
| Shopping | 9,960 | 10% | 10,800 | 11% | 10,260 | 18% |
| Leisure | 9,570 | 10% | 9,420 | 10% | 6,520 | 11% |
| Medical | 2,740 | 3% | 2,190 | 2% | 1,140 | 2% |
| Pick-up / drive passenger | 6,010 | 6% | 7,490 | 8% | 4,320 | 7% |
| Return Home | 40,560 | 43% | 32,380 | 34% | 23,230 | 40% |
| Other | 4,500 | 5% | 4,550 | 5% | 3,520 | 6% |
| Total: | 95,010 | 100% | 95,420 | 100% | 57,890 | 100% |

| AM Peak (06:30 - 08:59) | From District | | To District | | Within District | |
|---------------------------|---------------|------|-------------|------|-----------------|------|
| Work or related | 11,500 | 65% | 16,000 | 65% | 1,900 | 23% |
| School | 2,450 | 14% | 4,090 | 17% | 3,260 | 39% |
| Shopping | 120 | 1% | 250 | 1% | 270 | 3% |
| Leisure | 720 | 4% | 450 | 2% | 340 | 4% |
| Medical | 470 | 3% | 330 | 1% | 60 | 1% |
| Pick-up / drive passenger | 1,110 | 6% | 1,880 | 8% | 1,400 | 17% |
| Return Home | 790 | 4% | 530 | 2% | 560 | 7% |
| Other | 540 | 3% | 1,060 | 4% | 490 | 6% |
| Total: | 17,700 | 100% | 24,590 | 100% | 8,280 | 100% |

| PM Peak (15:30 - 17:59) | From District | | To District | | Within District | |
|---------------------------|---------------|------|-------------|------|-----------------|------|
| Work or related | 590 | 2% | 550 | 3% | 300 | 2% |
| School | 180 | 1% | 10 | 0% | 110 | 1% |
| Shopping | 2,510 | 10% | 2,680 | 12% | 1,940 | 14% |
| Leisure | 2,090 | 8% | 2,220 | 10% | 1,780 | 13% |
| Medical | 200 | 1% | 270 | 1% | 120 | 1% |
| Pick-up / drive passenger | 1,970 | 8% | 2,350 | 11% | 1,030 | 7% |
| Return Home | 17,330 | 68% | 12,540 | 58% | 8,090 | 57% |
| Other | 790 | 3% | 870 | 4% | 850 | 6% |
| Total: | 25,660 | 100% | 21,490 | 100% | 14,220 | 100% |

| Peak Period (%) | Total: | % of 24 Hours | Within District (%) |
|-----------------|---------|---------------|---------------------|
| 24 Hours | 248,320 | | 23% |
| AM Peak Period | 50,570 | 20% | 16% |
| PM Peak Period | 61,370 | 25% | 23% |

Trips by Primary Travel Mode

| 24 Hours | From District | | To District | | Within District | |
|----------------|---------------|------|-------------|------|-----------------|------|
| Auto Driver | 53,530 | 56% | 53,730 | 56% | 22,130 | 38% |
| Auto Passenger | 14,560 | 15% | 14,560 | 15% | 6,300 | 11% |
| Transit | 18,670 | 20% | 18,820 | 20% | 2,810 | 5% |
| Bicycle | 3,120 | 3% | 3,140 | 3% | 3,110 | 5% |
| Walk | 2,780 | 3% | 2,750 | 3% | 21,610 | 37% |
| Other | 2,340 | 2% | 2,430 | 3% | 1,910 | 3% |
| Total: | 95,000 | 100% | 95,430 | 100% | 57,870 | 100% |

| AM Peak (06:30 - 08:59) | From District | | To District | | Within District | |
|-------------------------|---------------|------|-------------|------|-----------------|------|
| Auto Driver | 8,230 | 46% | 12,650 | 51% | 2,740 | 33% |
| Auto Passenger | 1,910 | 11% | 3,800 | 15% | 1,220 | 15% |
| Transit | 5,490 | 31% | 5,550 | 23% | 370 | 4% |
| Bicycle | 1,050 | 6% | 710 | 3% | 500 | 6% |
| Walk | 650 | 4% | 770 | 3% | 2,770 | 33% |
| Other | 370 | 2% | 1,110 | 5% | 690 | 8% |
| Total: | 17,700 | 100% | 24,590 | 100% | 8,290 | 100% |

| PM Peak (15:30 - 17:59) | From District | | To District | | Within District | |
|-------------------------|---------------|------|-------------|------|-----------------|------|
| Auto Driver | 14,180 | 55% | 11,370 | 53% | 4,550 | 32% |
| Auto Passenger | 4,060 | 16% | 3,010 | 14% | 1,370 | 10% |
| Transit | 5,400 | 21% | 5,090 | 24% | 570 | 4% |
| Bicycle | 750 | 3% | 1,250 | 6% | 1,000 | 7% |
| Walk | 690 | 3% | 620 | 3% | 6,400 | 45% |
| Other | 570 | 2% | 160 | 1% | 320 | 2% |
| Total: | 25,650 | 100% | 21,500 | 100% | 14,210 | 100% |

| Avg Vehicle Occupancy | From District | | To District | | Within District | |
|-----------------------|---------------|--|-------------|--|-----------------|--|
| 24 Hours | 1.27 | | 1.27 | | 1.28 | |
| AM Peak Period | 1.23 | | 1.30 | | 1.45 | |
| PM Peak Period | 1.29 | | 1.26 | | 1.30 | |

| Transit Modal Split | From District | | To District | | Within District | |
|---------------------|---------------|--|-------------|--|-----------------|--|
| 24 Hours | 22% | | 22% | | 9% | |
| AM Peak Period | 35% | | 25% | | 9% | |
| PM Peak Period | 23% | | 26% | | 9% | |

Appendix G – TDM Checklists

TDM-Supportive Development Design and Infrastructure Checklist: *Residential Developments (multi-family or condominium)*

| Legend | |
|-----------------|--|
| REQUIRED | The Official Plan or Zoning By-law provides related guidance that must be followed |
| BASIC | The measure is generally feasible and effective, and in most cases would benefit the development and its users |
| BETTER | The measure could maximize support for users of sustainable modes, and optimize development performance |

| TDM-supportive design & infrastructure measures: <i>Residential developments</i> | | Check if completed & add descriptions, explanations or plan/drawing references |
|---|---|--|
| 1. WALKING & CYCLING: ROUTES | | |
| 1.1 Building location & access points | | |
| BASIC | 1.1.1 Locate building close to the street, and do not locate parking areas between the street and building entrances | <input checked="" type="checkbox"/> |
| BASIC | 1.1.2 Locate building entrances in order to minimize walking distances to sidewalks and transit stops/stations | <input checked="" type="checkbox"/> |
| BASIC | 1.1.3 Locate building doors and windows to ensure visibility of pedestrians from the building, for their security and comfort | <input checked="" type="checkbox"/> |
| 1.2 Facilities for walking & cycling | | |
| REQUIRED | 1.2.1 Provide convenient, direct access to stations or major stops along rapid transit routes within 600 metres; minimize walking distances from buildings to rapid transit; provide pedestrian-friendly, weather-protected (where possible) environment between rapid transit accesses and building entrances; ensure quality linkages from sidewalks through building entrances to integrated stops/stations (<i>see Official Plan policy 4.3.3</i>) | <input checked="" type="checkbox"/> Main entrance is on Carling Avenue thereby reducing walking distance to transit. |
| REQUIRED | 1.2.2 Provide safe, direct and attractive pedestrian access from public sidewalks to building entrances through such measures as: reducing distances between public sidewalks and major building entrances; providing walkways from public streets to major building entrances; within a site, providing walkways along the front of adjoining buildings, between adjacent buildings, and connecting areas where people may congregate, such as courtyards and transit stops; and providing weather protection through canopies, colonnades, and other design elements wherever possible (<i>see Official Plan policy 4.3.12</i>) | <input checked="" type="checkbox"/> Main entrance is on Carling Avenue and a walkway will be provided between the sidewalk and the building entrance. Entrances on Bromley Road will also have walkways. |

| TDM-supportive design & infrastructure measures: <i>Residential developments</i> | | Check if completed & add descriptions, explanations or plan/drawing references |
|---|---|--|
| REQUIRED | 1.2.3 Provide sidewalks of smooth, well-drained walking surfaces of contrasting materials or treatments to differentiate pedestrian areas from vehicle areas, and provide marked pedestrian crosswalks at intersection sidewalks (see <i>Official Plan policy 4.3.10</i>) | <input checked="" type="checkbox"/> Concrete sidewalks will be provided for pedestrians. |
| REQUIRED | 1.2.4 Make sidewalks and open space areas easily accessible through features such as gradual grade transition, depressed curbs at street corners and convenient access to extra-wide parking spaces and ramps (see <i>Official Plan policy 4.3.10</i>) | <input checked="" type="checkbox"/> Sidewalks will be constructed per building code and accessibility standards. |
| REQUIRED | 1.2.5 Include adequately spaced inter-block/street cycling and pedestrian connections to facilitate travel by active transportation. Provide links to the existing or planned network of public sidewalks, multi-use pathways and on-road cycle routes. Where public sidewalks and multi-use pathways intersect with roads, consider providing traffic control devices to give priority to cyclists and pedestrians (see <i>Official Plan policy 4.3.11</i>) | <input checked="" type="checkbox"/> Direct pedestrian access to Carling Avenue will be provided. |
| BASIC | 1.2.6 Provide safe, direct and attractive walking routes from building entrances to nearby transit stops | <input type="checkbox"/> |
| BASIC | 1.2.7 Ensure that walking routes to transit stops are secure, visible, lighted, shaded and wind-protected wherever possible | <input type="checkbox"/> |
| BASIC | 1.2.8 Design roads used for access or circulation by cyclists using a target operating speed of no more than 30 km/h, or provide a separated cycling facility | <input type="checkbox"/> |
| 1.3 Amenities for walking & cycling | | |
| BASIC | 1.3.1 Provide lighting, landscaping and benches along walking and cycling routes between building entrances and streets, sidewalks and trails | <input type="checkbox"/> |
| BASIC | 1.3.2 Provide wayfinding signage for site access (where required, e.g. when multiple buildings or entrances exist) and egress (where warranted, such as when directions to reach transit stops/stations, trails or other common destinations are not obvious) | <input type="checkbox"/> |

| TDM-supportive design & infrastructure measures: <i>Residential developments</i> | | Check if completed & add descriptions, explanations or plan/drawing references |
|---|--|---|
| 2. WALKING & CYCLING: END-OF-TRIP FACILITIES | | |
| 2.1 Bicycle parking | | |
| REQUIRED | 2.1.1 Provide bicycle parking in highly visible and lighted areas, sheltered from the weather wherever possible (see <i>Official Plan policy 4.3.6</i>) | <input checked="" type="checkbox"/> All bicycle parking will be located below-grade. |
| REQUIRED | 2.1.2 Provide the number of bicycle parking spaces specified for various land uses in different parts of Ottawa; provide convenient access to main entrances or well-used areas (see <i>Zoning By-law Section 111</i>) | <input checked="" type="checkbox"/> Sufficient bicycle parking spaces will be provided to meet by-law requirements. |
| REQUIRED | 2.1.3 Ensure that bicycle parking spaces and access aisles meet minimum dimensions; that no more than 50% of spaces are vertical spaces; and that parking racks are securely anchored (see <i>Zoning By-law Section 111</i>) | <input checked="" type="checkbox"/> |
| BASIC | 2.1.4 Provide bicycle parking spaces equivalent to the expected number of resident-owned bicycles, plus the expected peak number of visitor cyclists | <input type="checkbox"/> |
| 2.2 Secure bicycle parking | | |
| REQUIRED | 2.2.1 Where more than 50 bicycle parking spaces are provided for a single residential building, locate at least 25% of spaces within a building/structure, a secure area (e.g. supervised parking lot or enclosure) or bicycle lockers (see <i>Zoning By-law Section 111</i>) | <input checked="" type="checkbox"/> All bicycle parking spaces will be located in the below-grade parking facility. |
| BETTER | 2.2.2 Provide secure bicycle parking spaces equivalent to at least the number of units at condominiums or multi-family residential developments | <input type="checkbox"/> |
| 2.3 Bicycle repair station | | |
| BETTER | 2.3.1 Provide a permanent bike repair station, with commonly used tools and an air pump, adjacent to the main bicycle parking area (or secure bicycle parking area, if provided) | <input type="checkbox"/> |
| 3. TRANSIT | | |
| 3.1 Customer amenities | | |
| BASIC | 3.1.1 Provide shelters, lighting and benches at any on-site transit stops | <input type="checkbox"/> |
| BASIC | 3.1.2 Where the site abuts an off-site transit stop and insufficient space exists for a transit shelter in the public right-of-way, protect land for a shelter and/or install a shelter | <input type="checkbox"/> |
| BETTER | 3.1.3 Provide a secure and comfortable interior waiting area by integrating any on-site transit stops into the building | <input type="checkbox"/> |

| TDM-supportive design & infrastructure measures: <i>Residential developments</i> | | Check if completed & add descriptions, explanations or plan/drawing references |
|---|--|---|
| 4. RIDESHARING | | |
| 4.1 Pick-up & drop-off facilities | | |
| BASIC | 4.1.1 Provide a designated area for carpool drivers (plus taxis and ride-hailing services) to drop off or pick up passengers without using fire lanes or other no-stopping zones | <input checked="" type="checkbox"/> A direct pedestrian connection to Bromley has been provided to facilitate pick-up and drop-off activity on Bromley near the building entrance rather than on Carling. |
| 5. CARSHARING & BIKESHARING | | |
| 5.1 Carshare parking spaces | | |
| BETTER | 5.1.1 Provide up to three carshare parking spaces in an R3, R4 or R5 Zone for specified residential uses (see <i>Zoning By-law Section 94</i>) | <input type="checkbox"/> |
| 5.2 Bikeshare station location | | |
| BETTER | 5.2.1 Provide a designated bikeshare station area near a major building entrance, preferably lighted and sheltered with a direct walkway connection | <input type="checkbox"/> |
| 6. PARKING | | |
| 6.1 Number of parking spaces | | |
| REQUIRED | 6.1.1 Do not provide more parking than permitted by zoning, nor less than required by zoning, unless a variance is being applied for | <input checked="" type="checkbox"/> Parking by-law requirements have been met. |
| BASIC | 6.1.2 Provide parking for long-term and short-term users that is consistent with mode share targets, considering the potential for visitors to use off-site public parking | <input type="checkbox"/> |
| BASIC | 6.1.3 Where a site features more than one use, provide shared parking and reduce the cumulative number of parking spaces accordingly (see <i>Zoning By-law Section 104</i>) | <input type="checkbox"/> |
| BETTER | 6.1.4 Reduce the minimum number of parking spaces required by zoning by one space for each 13 square metres of gross floor area provided as shower rooms, change rooms, locker rooms and other facilities for cyclists in conjunction with bicycle parking (see <i>Zoning By-law Section 111</i>) | <input type="checkbox"/> |
| 6.2 Separate long-term & short-term parking areas | | |
| BETTER | 6.2.1 Provide separate areas for short-term and long-term parking (using signage or physical barriers) to permit access controls and simplify enforcement (i.e. to discourage residents from parking in visitor spaces, and vice versa) | <input type="checkbox"/> |

TDM Measures Checklist:
Residential Developments (multi-family, condominium or subdivision)

| Legend | |
|---------------|--|
| BASIC | The measure is generally feasible and effective, and in most cases would benefit the development and its users |
| BETTER | The measure could maximize support for users of sustainable modes, and optimize development performance |
| ★ | The measure is one of the most dependably effective tools to encourage the use of sustainable modes |

| TDM measures: <i>Residential developments</i> | | Check if proposed & add descriptions |
|---|---------|--|
| 1. TDM PROGRAM MANAGEMENT | | |
| 1.1 Program coordinator | | |
| BASIC | ★ 1.1.1 | Designate an internal coordinator, or contract with an external coordinator <input type="checkbox"/> |
| 1.2 Travel surveys | | |
| BETTER | 1.2.1 | Conduct periodic surveys to identify travel-related behaviours, attitudes, challenges and solutions, and to track progress <input type="checkbox"/> |
| 2. WALKING AND CYCLING | | |
| 2.1 Information on walking/cycling routes & destinations | | |
| BASIC | 2.1.1 | Display local area maps with walking/cycling access routes and key destinations at major entrances (<i>multi-family, condominium</i>) <input type="checkbox"/> |
| 2.2 Bicycle skills training | | |
| BETTER | 2.2.1 | Offer on-site cycling courses for residents, or subsidize off-site courses <input type="checkbox"/> |

| TDM measures: <i>Residential developments</i> | | Check if proposed & add descriptions |
|---|--|--------------------------------------|
| 3. TRANSIT | | |
| 3.1 Transit information | | |
| BASIC | 3.1.1 Display relevant transit schedules and route maps at entrances (<i>multi-family, condominium</i>) | <input type="checkbox"/> |
| BETTER | 3.1.2 Provide real-time arrival information display at entrances (<i>multi-family, condominium</i>) | <input type="checkbox"/> |
| 3.2 Transit fare incentives | | |
| BASIC ★ | 3.2.1 Offer PRESTO cards preloaded with one monthly transit pass on residence purchase/move-in, to encourage residents to use transit | <input type="checkbox"/> |
| BETTER | 3.2.2 Offer at least one year of free monthly transit passes on residence purchase/move-in | <input type="checkbox"/> |
| 3.3 Enhanced public transit service | | |
| BETTER ★ | 3.3.1 Contract with OC Transpo to provide early transit services until regular services are warranted by occupancy levels (<i>subdivision</i>) | <input type="checkbox"/> N/A |
| 3.4 Private transit service | | |
| BETTER | 3.4.1 Provide shuttle service for seniors homes or lifestyle communities (e.g. scheduled mall or supermarket runs) | <input type="checkbox"/> |
| 4. CARSHARING & BIKESHARING | | |
| 4.1 Bikeshare stations & memberships | | |
| BETTER | 4.1.1 Contract with provider to install on-site bikeshare station (<i>multi-family</i>) | <input type="checkbox"/> |
| BETTER | 4.1.2 Provide residents with bikeshare memberships, either free or subsidized (<i>multi-family</i>) | <input type="checkbox"/> |
| 4.2 Carshare vehicles & memberships | | |
| BETTER | 4.2.1 Contract with provider to install on-site carshare vehicles and promote their use by residents | <input type="checkbox"/> |
| BETTER | 4.2.2 Provide residents with carshare memberships, either free or subsidized | <input type="checkbox"/> |
| 5. PARKING | | |
| 5.1 Priced parking | | |
| BASIC ★ | 5.1.1 Unbundle parking cost from purchase price (<i>condominium</i>) | <input type="checkbox"/> N/A |
| BASIC ★ | 5.1.2 Unbundle parking cost from monthly rent (<i>multi-family</i>) | <input checked="" type="checkbox"/> |

| TDM measures: <i>Residential developments</i> | | Check if proposed & add descriptions |
|---|---|--------------------------------------|
| 6. TDM MARKETING & COMMUNICATIONS | | |
| 6.1 Multimodal travel information | | |
| BASIC ★ | 6.1.1 Provide a multimodal travel option information package to new residents | <input type="checkbox"/> |
| 6.2 Personalized trip planning | | |
| BETTER ★ | 6.2.1 Offer personalized trip planning to new residents | <input type="checkbox"/> |

Appendix H – MMLOS Analysis

Multi-Modal Level of Service
 1995 Carling Avenue - Transportation Impact Assessment
 Scenario: Existing and Future Conditions

April 6, 2020



| INTERSECTIONS | | Carling Avenue & Iroquois Road | | | | Carling Avenue & Maitland / Sherbourne | | | |
|---------------------------------|---|---|------------------------------|--|--|--|------------------------------|------------------------------|------------------------------|
| | | NORTH leg | SOUTH leg | EAST leg | WEST leg | NORTH leg | SOUTH leg | EAST leg | WEST leg |
| Pedestrian | Lanes (do NOT include lanes protected by bulb-outs) | 3 | 2 | 8 | 8 | 3 | 4 | 7 | 7 |
| | Median | No Median | No Median | Median (>2.4m) | Median (>2.4m) | No Median | No Median | Median (>2.4m) | Median (>2.4m) |
| | Island Refuge | | | | | | | | |
| | Conflicting Left Turns (from street to right) | Protected/permisive | Permissive | Permissive | Permissive | Protected | Protected | Permissive | Permissive |
| | Conflicting Right Turns (from street to left) | Permissive or yield control | Permissive or yield control | Permissive or yield control | Permissive or yield control | Permissive or yield control | Permissive or yield control | Permissive or yield control | Permissive or yield control |
| | RTOR? (from street to left) | RTOR allowed | RTOR allowed | RTOR allowed | RTOR allowed | RTOR allowed | RTOR allowed | RTOR allowed | RTOR allowed |
| | Ped Leading Interval? (on cross street) | No | No | No | No | No | No | No | No |
| | Corner Radius | > 10m to 15m | > 5m to 10m | Right turn channel with receiving lane | Right turn channel with receiving lane | > 5m to 10m | > 5m to 10m | > 5m to 10m | > 5m to 10m |
| | Right Turn Channel | No right turn channel | No right turn channel | Conventional right turn channel without receiving lane | Conventional right turn channel without receiving lane | No right turn channel | No right turn channel | No right turn channel | No right turn channel |
| | Crosswalk Type | Standard transverse markings | Standard transverse markings | Standard transverse markings | Standard transverse markings | Standard transverse markings | Zebra stripe hi-vis markings | Zebra stripe hi-vis markings | Zebra stripe hi-vis markings |
| | LOS (PETS) | 70 C | 86 B | 2 F | 2 F | 79 B | 65 C | 14 F | 14 F |
| | Cycle Length (sec) | 130 | 130 | 130 | 130 | 120 | 120 | 120 | 120 |
| | Pedestrian Walk Time (solid white symbol) (sec) | 10 | 10 | 27 | 27 | 7 | 7 | 20 | 20 |
| | LOS (Delay,seconds) | 56.9 E | 56.9 E | 44.4 E | 44.4 E | 54.3 E | 54.3 E | 44.5 E | 44.5 E |
| Overall Level of Service | F | | | | F | | | | |
| Cyclist | Type of Bikeway | Mixed Traffic | Mixed Traffic | Mixed Traffic | Mixed Traffic | Mixed Traffic | Mixed Traffic | Mixed Traffic | Mixed Traffic |
| | Turning Speed (based on corner radius & angle) | | | Fast | | | | | |
| | Right Turn Storage Length | | | > 50m | | | | | |
| | Dual Right Turn? | | | No | | | | | |
| | Shared Through-Right? | Yes | Yes | No | Yes | Yes | Yes | Yes | Yes |
| | Bike Box? | No | No | No | No | No | No | No | No |
| | Number of Lanes Crossed for Left Turns | 1 Lane Crossed | No Lanes Crossed | 2+ Lanes Crossed | 2+ Lanes Crossed | 1 Lane Crossed | 1 Lane Crossed | 2+ Lanes Crossed | 2+ Lanes Crossed |
| | Operating Speed on Approach | 50km/h | 50km/h | ≥ 60km/h | ≥ 60km/h | ≥ 60km/h | ≥ 60km/h | ≥ 60km/h | ≥ 60km/h |
| | Dual Left Turn Lanes? | No | No | No | No | No | No | Yes | No |
| | Level of Service | D | B | F | F | F | F | F | F |
| Level of Service | F | | | | F | | | | |
| Transit | Average Signal Delay | >40 sec | ≤40 sec | 0 | 0 | >40 sec | >40 sec | >40 sec | ≤40 sec |
| | Level of Service | F | E | A | A | F | F | F | E |
| Level of Service | F | | | | F | | | | |
| Truck | Turning Radius (Right Turn) | 10 to 15m | < 10m | > 15m | 10 to 15m | < 10m | < 10m | < 10m | < 10m |
| | Number of Receiving Lanes | 2+ | 2+ | 1 | 1 | 2+ | 2+ | 1 | 2+ |
| | Level of Service | B | D | C | E | D | D | F | D |
| Level of Service | E | | | | F | | | | |
| SEGMENTS | | Bromley Road - Adjacent to Proposed Development | | | | | | | |
| Pedestrian | Sidewalk Width | 1 2 3 | | | | | | | |
| | Boulevard Width | No Sidewalk | | | | | | | |
| | AADT | N/A | | | | | | | |
| | On-Street Parking | N/A | | | | | | | |
| | Operating Speed | 31 to 50 km/h | | | | | | | |
| | Level of Service | F | | | | | | | |
| Cyclist | Type of Bikeway | Mixed Traffic | | | | | | | |
| | Number of Travel Lanes (per direction) | 1 Travel Lane Per Direction | | | | | | | |
| | Raised Median? | | | | | | | | |
| | Bike Lane Width | | | | | | | | |
| | Operating Speed | 50 km/h | | | | | | | |
| | Bike Lane Blockages (Commercial Areas) | | | | | | | | |
| | Median Refuge | | | | | | | | |
| | Number of Travel Lanes on Sidestreet | | | | | | | | |
| Level of Service | B | | | | | | | | |
| Transit | Facility Type | Mixed Traffic | | | | | | | |
| | Friction | Limited parking/driveway friction | | | | | | | |
| Level of Service | D | | | | | | | | |
| Truck | Curb Lane Width | >3.7 | | | | | | | |
| | Number of Travel Lanes | 2 | | | | | | | |
| | Level of Service | B | | | | | | | |

Appendix I – Intersection Control Warrants



MINIMUM WARRANTS FOR INSTALLATION OF TRAFFIC SIGNALS USING PROJECTED VOLUMES*

Project: 1995 Carling Avenue - Transportation Impact Assessment

Date: 2020-04-13

Project # 124829

Location Carling Avenue
(Roadway)

at Hare Avenue
(Intersecting Roadway)

Municipality City of Ottawa

Projected Volume Future (2029) Total Traffic

Peak Hour Average Hourly Volume

| WARRANT | DESCRIPTION | MINIMUM REQUIREMENT FOR 2 LANE HIGHWAYS | | | | COMPLIANCE | | |
|---------------------------|---|---|-----------------|--------------------|--------------------------|------------|------|----------|
| | | FREE FLOW | RESTRICTED FLOW | ADJUSTED FREE FLOW | ADJUSTED RESTRICTED FLOW | SECTIONAL | | ENTIRE % |
| | | | | | | Number | % | |
| 1. VEHICULAR VOLUME | A. Vehicle volumes, all approaches (Average Hour) | 480 | 720 | 720 | 1080 | 1168 | 162% | 4% |
| | B. Vehicle volume along minor roads (Average Hour) | 120 | 170 | 270 | 383 | 11 | 4% | |
| 2. DELAY TO CROSS TRAFFIC | A. Vehicle volumes, along artery (Average Hour) | 480 | 720 | 720 | 1080 | 1157 | 161% | 5% |
| | B. Combined vehicle and pedestrian volume crossing artery from minor roads (Average Hour) | 50 | 75 | 75 | 113 | 4 | 5% | |

Projected Traffic Volumes:

| Approach Volume Input (vph) | | | |
|-----------------------------|-----------|----------|----------|
| Artery V1 | Artery V2 | Minor V3 | Minor V4 |
| 528 | 629 | 11 | 0 |

Average Hourly Volume (AHV) = PHV/2 or (amPHV + pmPHV)/4
PHV = Either AM or PM Peak Hour Volume

Notes and Adjustment Factors:

| Notes | Response | Adj. Factors |
|---|--|--------------|
| 1. Vehicle volume warrants (1A) and (2A) for intersections of roadways having two or more moving lanes in one direction should be 25% higher than the values given above. | <input type="checkbox"/> Yes | 1.25 |
| 2. Warrant values for free flow apply when the 85th percentile speed of artery traffic equals or exceeds 70 km/h or when the intersection lies within the built-up area of an isolated community having a population of less than 10,000. | <input type="checkbox"/> Yes | |
| 3. Warrant values for restricted flow apply to large urban communities when the 85th percentile speed of artery traffic does not exceed 70 km/h. | <input type="checkbox"/> No | |
| 4. The lowest sectional percentage governs the entire warrant. | | |
| 5. For "T" intersections the warrant values for the minor road should be increased by 50% (Warrant 1B only). | <input type="checkbox"/> Yes | 1.5 |
| 6. All flow values for Warrant 1 and Warrant 2 are to be increased by 20% for existing intersections and by 50% in the case of new intersections. | <input type="checkbox"/> Existing | 1.2 |
| 7. The crossing volumes are defined as: | | |
| (a) Left-turns from both minor road approaches. | <input type="checkbox"/> 4 <input type="checkbox"/> 0 | |
| (b) The heaviest through volume from the minor road. | <input type="checkbox"/> 0 | |
| © 50% of the heavier left turn movement from major road when both of the following are met: | <input type="checkbox"/> 26 | 0 |
| (i) the left-turn volume >120 vph | <input type="checkbox"/> No | |
| (ii) the left-turn volume plus the opposing volume >720 vph | <input type="checkbox"/> No | |
| (d) Pedestrians crossing the main road. | <input type="checkbox"/> 0 | |

CONCLUSION: The intersection does NOT meet the minimum warrants for traffic control signals.

* "Ontario Traffic Manual, Book 12", Ontario Ministry of Transportation.

City of Ottawa Roundabout Initial Feasibility Screening Tool

The intent of this screening tool is to provide a relatively quick assessment of the feasibility of a roundabout at a particular intersection in comparison to other appropriate forms of traffic control or road modifications including all-way stop control, traffic signals, auxiliary lanes, etc. The intended outcome of this tool is to provide enough information to assist staff in deciding whether or not to proceed with an Intersection Control Study to investigate the feasibility of a roundabout in more detail.

- 1 Project Name: 1995 Carling Avenue - Transportation Impact Assessment

- 2 Intersection: Carling Avenue & Hare Avenue

- 3 Location and Description of Intersection:
Lane Configuration, total or approach AADT, distance to nearby intersection(s), etc. Attach or sketch a diagram and include existing and/or horizon-year turning movements. If an existing intersection then indicate type of control
The intersection is currently configured as a stop-controlled intersection and is estimated to experience traffic volumes in the order of 24,000 vehicles per day. The eastbound and westbound approaches both have three through lanes, and the westbound approach has an auxiliary left-turn lane. The northbound approach has a single shared right/left lane.

- 4 What traditional modifications are proposed?
All-way stop control, traffic signals, auxiliary lanes, etc. Attach or sketch a diagram if necessary.
The prohibition of U-turn movements.

- 5 What size of roundabout is being considered?
Describe, and attach a Roundabout Traffic Flow Worksheet
Three-lane roundabout

- 6 Why is a roundabout being considered?
As an alternative to the existing stop-control

- 7 Are there contra-indications for If "Yes" is indicated for one or more of the contra-indications then a roundabout may be problematic at the subject intersection. That is not to say

| No. | Contra-Indication | Outcome |
|-----|--|---|
| 1 | Is there insufficient property at the intersection (i.e. less than 44 metres diameter if considering a single-lane roundabout, and less than 60 metres if considering a two-lane roundabout) or property constraints that would require demolition of adjacent structures? | Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> |
| 2 | Are there any instances where stopping sight distance (SSD) of a roundabout yield line may not be attainable (i.e. the intersection is on a crest vertical curve)? | Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> |
| 3 | Is there an existing uncontrolled approach with a grade in excess of 4 percent? | Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> |
| 4 | Is the intersection located within a coordinated signal system? | Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> |
| 5 | Is there a closely-spaced traffic signal or railway crossing that could not be controlled with a nearby roundabout? | Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> |
| 6 | Are significant differences in directional flows or any situations of sudden high demand expected? | Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> |
| 7 | Are there known visually-impaired pedestrians that cross this intersection? | Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> |

- 8 Are there suitability factors for a roundabout? If "Yes" is indicated for two or more of the suitability factors then a roundabout should be technically feasible at the subject intersection..

| No. | Suitability Factor | Outcome |
|-----|--|---|
| 1 | Does the intersection currently experience an average collision frequency of more than 1.5 injury crashes per year, or a collision rate in excess of 1 injury crash per 1 million vehicles entering (MVE)? | Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> |
| 2 | Has there been a fatal crash at the intersection in the last 10 years? | Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> |
| 3 | Are capacity problems currently being experienced, or expected in the future? | Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> |
| 4 | Are traffic signals warranted, or expected to be warranted in the future? | Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> |
| 5 | Does the intersection have more than 4 legs, or unusual geometry? | Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> |
| 6 | Will Planned modifications to the intersection require that nearby structures be widened (i.e. to accommodate left-turn lanes)? | Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> |
| 7 | Is the intersection located at a transition between rural and urban environments (i.e. an urban boundary) such that a roundabout could act as a means of speed transition? | Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> |

- 9 Conclusions/recommendation whether to proceed with an Intersection Control Study:

This intersection does not meet sufficient suitability factors to warrant a roundabout. Furthermore, there is insufficient property available for implementing even a two-lane roundabout and the intersection is located within a coordinated signal system. As such, it is not recommended that a roundabout be implemented at this intersection.

DRAFT

City of Ottawa Mini-Roundabout Screening Criteria

Mini roundabouts are best suited and most effective when they meet the following conditions;

| No. | Criteria | Outcome |
|-----|--|---|
| 1 | Located at minor collector road intersecting a minor collector road or a local residential road | Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> |
| 2 | ADT lesser than 15,000 (estimated ADT in case of new development area) | Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> |
| 3 | At least 10% of the total traffic has generated from minor road (estimated in case of new development area) | Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> |
| 4 | Operating speed <55km/hr or posted speed ≤ 50km/hr in a new development area | Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> |
| 5 | A right of way wide enough to accommodate a 13 m to 27 m Inscribed Circle Diameter roundabout and adjacent sidewalks | Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> |
| 6 | Situated on a non truck route or roads without heavy truck movements | Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> |
| 7 | Intersections with no more than four legs | Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> |

Conclusion

Given that this is a large arterial to local intersection a mini-roundabout is not appropriate for this location.

City of Ottawa Roundabout Initial Feasibility Screening Tool

The intent of this screening tool is to provide a relatively quick assessment of the feasibility of a roundabout at a particular intersection in comparison to other appropriate forms of traffic control or road modifications including all-way stop control, traffic signals, auxiliary lanes, etc. The intended outcome of this tool is to provide enough information to assist staff in deciding whether or not to proceed with an Intersection Control Study to investigate the feasibility of a roundabout in more detail.

- 1 Project Name: 1995 Carling Avenue - Transportation Impact Assessment

- 2 Intersection: Carling Avenue & Maitland Avenue / Sherbourne Road

- 3 Location and Description of Intersection:
Lane Configuration, total or approach AADT, distance to nearby intersection(s), etc. Attach or sketch a diagram and include existing and/or horizon-year turning movements. If an existing intersection then indicate type of control
The intersection is currently configured as a signalized intersection and experiences traffic volumes in the order of 44,000 vehicles per day. The eastbound and westbound approaches both have three through lanes and a single left-turn lane while the northbound and southbound approaches have a single through and left-turn lane each.

- 4 What traditional modifications are proposed?
All-way stop control, traffic signals, auxiliary lanes, etc. Attach or sketch a diagram if necessary.
Traffic signal phase changes.

- 5 What size of roundabout is being considered?
Describe, and attach a Roundabout Traffic Flow Worksheet
Three-lane roundabout

- 6 Why is a roundabout being considered?
As an alternative to traffic signals.

- 7 Are there contra-indications for If "Yes" is indicated for one or more of the contra-indications then a roundabout may be problematic at the subject intersection. That is not to say

| No. | Contra-Indication | Outcome |
|-----|--|---|
| 1 | Is there insufficient property at the intersection (i.e. less than 44 metres diameter if considering a single-lane roundabout, and less than 60 metres if considering a two-lane roundabout) or property constraints that would require demolition of adjacent structures? | Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> |
| 2 | Are there any instances where stopping sight distance (SSD) of a roundabout yield line may not be attainable (i.e. the intersection is on a crest vertical curve)? | Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> |
| 3 | Is there an existing uncontrolled approach with a grade in excess of 4 percent? | Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> |
| 4 | Is the intersection located within a coordinated signal system? | Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> |
| 5 | Is there a closely-spaced traffic signal or railway crossing that could not be controlled with a nearby roundabout? | Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> |
| 6 | Are significant differences in directional flows or any situations of sudden high demand expected? | Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> |
| 7 | Are there known visually-impaired pedestrians that cross this intersection? | Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> |

- 8 Are there suitability factors for a roundabout? If "Yes" is indicated for two or more of the suitability factors then a roundabout should be technically feasible at the subject intersection..

| No. | Suitability Factor | Outcome |
|-----|--|---|
| 1 | Does the intersection currently experience an average collision frequency of more than 1.5 injury crashes per year, or a collision rate in excess of 1 injury crash per 1 million vehicles entering (MVE)? | Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> |
| 2 | Has there been a fatal crash at the intersection in the last 10 years? | Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> |
| 3 | Are capacity problems currently being experienced, or expected in the future? | Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> |
| 4 | Are traffic signals warranted, or expected to be warranted in the future? | Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> |
| 5 | Does the intersection have more than 4 legs, or unusual geometry? | Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> |
| 6 | Will Planned modifications to the intersection require that nearby structures be widened (i.e. to accommodate left-turn lanes)? | Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> |
| 7 | Is the intersection located at a transition between rural and urban environments (i.e. an urban boundary) such that a roundabout could act as a means of speed transition? | Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> |

- 9 Conclusions/recommendation whether to proceed with an Intersection Control Study:

Although this location may meet a couple of the suitability factors, there is insufficient property available for implementing even a two-lane roundabout and the intersection is located within a coordinated signal system. As such, it is not recommended that a roundabout be implemented at this intersection.

DRAFT

City of Ottawa Mini-Roundabout Screening Criteria

Mini roundabouts are best suited and most effective when they meet the following conditions;

| No. | Criteria | Outcome |
|-----|--|---|
| 1 | Located at minor collector road intersecting a minor collector road or a local residential road | Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> |
| 2 | ADT lesser than 15,000 (estimated ADT in case of new development area) | Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> |
| 3 | At least 10% of the total traffic has generated from minor road (estimated in case of new development area) | Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> |
| 4 | Operating speed <55km/hr or posted speed ≤ 50km/hr in a new development area | Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> |
| 5 | A right of way wide enough to accommodate a 13 m to 27 m Inscribed Circle Diameter roundabout and adjacent sidewalks | Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> |
| 6 | Situated on a non truck route or roads without heavy truck movements | Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> |
| 7 | Intersections with no more than four legs | Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> |





















Conclusion

Given that this is a large arterial to arterial/major collector intersection a mini-roundabout is not appropriate for this location.

Appendix J – Intersection Capacity Analyses

1: Iroquois Road & Carling Avenue
1995 Carling Avenue


Existing (2020) Traffic
AM Peak Hour

| |  |  |  |  |  |  |  |  |  |  |  |  |
|---------------------------|---|---|---|---|---|---|---|---|---|---|---|---|
| Lane Group | EBL | EBT | EBR | WBU | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT |
| Lane Configurations |  |  | | |  |  |  | |  | |  |  |
| Traffic Volume (vph) | 19 | 1623 | 5 | 10 | 7 | 366 | 60 | 3 | 24 | 30 | 75 | 7 |
| Future Volume (vph) | 19 | 1623 | 5 | 10 | 7 | 366 | 60 | 3 | 24 | 30 | 75 | 7 |
| Ideal Flow (vphpl) | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 |
| Storage Length (m) | 25.0 | | 0.0 | | 20.0 | | 85.0 | 0.0 | | 0.0 | 50.0 | |
| Storage Lanes | 1 | | 0 | | 1 | | 1 | 0 | | 0 | 1 | |
| Taper Length (m) | 7.5 | | | | 7.5 | | | 7.5 | | | 7.5 | |
| Lane Util. Factor | 1.00 | 0.91 | 0.91 | 0.91 | 1.00 | 0.91 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Ped Bike Factor | 0.98 | 1.00 | | | 1.00 | | 0.94 | | 0.99 | | 0.99 | 0.98 |
| Fr _t | | | | | | | 0.850 | | 0.929 | | | 0.882 |
| Fl _t Protected | 0.950 | | | | 0.950 | | | | 0.998 | | 0.950 | |
| Satd. Flow (prot) | 1729 | 4871 | 0 | 0 | 1729 | 4687 | 1502 | 0 | 1636 | 0 | 1679 | 1492 |
| Fl _t Permitted | 0.462 | | | | 0.116 | | | | 0.991 | | 0.704 | |
| Satd. Flow (perm) | 822 | 4871 | 0 | 0 | 211 | 4687 | 1406 | 0 | 1624 | 0 | 1231 | 1492 |
| Right Turn on Red | | | Yes | | | | Yes | | | Yes | | |
| Satd. Flow (RTOR) | | 1 | | | | | 95 | | 16 | | | 30 |
| Link Speed (k/h) | | 60 | | | | 60 | | | 50 | | | 50 |
| Link Distance (m) | | 305.5 | | | | 198.3 | | | 297.2 | | | 304.9 |
| Travel Time (s) | | 18.3 | | | | 11.9 | | | 21.4 | | | 22.0 |
| Confl. Peds. (#/hr) | 15 | | 12 | | 12 | | 15 | 13 | | 12 | 12 | |
| Confl. Bikes (#/hr) | | | 1 | | | | 1 | | | 4 | | |
| Peak Hour Factor | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 |
| Heavy Vehicles (%) | 0% | 2% | 0% | 0% | 0% | 6% | 3% | 0% | 4% | 0% | 3% | 0% |
| Adj. Flow (vph) | 21 | 1803 | 6 | 11 | 8 | 407 | 67 | 3 | 27 | 33 | 83 | 8 |
| Shared Lane Traffic (%) | | | | | | | | | | | | |
| Lane Group Flow (vph) | 21 | 1809 | 0 | 0 | 19 | 407 | 67 | 0 | 63 | 0 | 83 | 38 |
| Turn Type | pm+pt | NA | | Perm | Perm | NA | Perm | Perm | NA | | Perm | NA |
| Protected Phases | 7 | 4 | | | | 8 | | | 2 | | | 6 |
| Permitted Phases | 4 | | | 8 | 8 | | 8 | 2 | | | 6 | |
| Detector Phase | 7 | 4 | | 8 | 8 | 8 | 8 | 2 | 2 | | 6 | 6 |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 5.0 | 5.0 | | 5.0 | 5.0 | 5.0 | 5.0 | 10.0 | 10.0 | | 10.0 | 10.0 |
| Minimum Split (s) | 12.0 | 28.3 | | 28.3 | 28.3 | 28.3 | 28.3 | 47.3 | 47.3 | | 47.3 | 47.3 |
| Total Split (s) | 14.0 | 83.0 | | 69.0 | 69.0 | 69.0 | 69.0 | 47.0 | 47.0 | | 47.0 | 47.0 |
| Total Split (%) | 10.8% | 63.8% | | 53.1% | 53.1% | 53.1% | 53.1% | 36.2% | 36.2% | | 36.2% | 36.2% |
| Maximum Green (s) | 7.0 | 76.7 | | 62.7 | 62.7 | 62.7 | 62.7 | 39.7 | 39.7 | | 39.7 | 39.7 |
| Yellow Time (s) | 3.7 | 3.7 | | 3.7 | 3.7 | 3.7 | 3.7 | 3.3 | 3.3 | | 3.3 | 3.3 |
| All-Red Time (s) | 3.3 | 2.6 | | 2.6 | 2.6 | 2.6 | 2.6 | 4.0 | 4.0 | | 4.0 | 4.0 |
| Lost Time Adjust (s) | -3.0 | -2.3 | | | -2.3 | -2.3 | -2.3 | | -3.3 | | -3.3 | -3.3 |
| Total Lost Time (s) | 4.0 | 4.0 | | | 4.0 | 4.0 | 4.0 | | 4.0 | | 4.0 | 4.0 |
| Lead/Lag | Lead | | | Lag | Lag | Lag | Lag | | | | | |
| Lead-Lag Optimize? | Yes | | | Yes | Yes | Yes | Yes | | | | | |
| Vehicle Extension (s) | 3.0 | 3.0 | | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | | 3.0 | 3.0 |
| Recall Mode | Max | C-Max | | C-Max | C-Max | C-Max | C-Max | None | None | | None | None |
| Walk Time (s) | | 10.0 | | 10.0 | 10.0 | 10.0 | 10.0 | 27.0 | 27.0 | | 27.0 | 27.0 |
| Flash Dont Walk (s) | | 12.0 | | 12.0 | 12.0 | 12.0 | 12.0 | 13.0 | 13.0 | | 13.0 | 13.0 |
| Pedestrian Calls (#/hr) | | 12 | | 15 | 15 | 15 | 15 | 12 | 12 | | 13 | 13 |
| Act Effct Green (s) | 95.8 | 95.8 | | 65.0 | 65.0 | 65.0 | 65.0 | | 26.2 | | 26.2 | 26.2 |
| Actuated g/C Ratio | 0.74 | 0.74 | | | 0.50 | 0.50 | 0.50 | | 0.20 | | 0.20 | 0.20 |

| Lane Group | SBR |
|-------------------------|------|
| Lane Configurations | |
| Traffic Volume (vph) | 27 |
| Future Volume (vph) | 27 |
| Ideal Flow (vphpl) | 1800 |
| Storage Length (m) | 0.0 |
| Storage Lanes | 0 |
| Taper Length (m) | |
| Lane Util. Factor | 1.00 |
| Ped Bike Factor | |
| Frt | |
| Flt Protected | |
| Satd. Flow (prot) | 0 |
| Flt Permitted | |
| Satd. Flow (perm) | 0 |
| Right Turn on Red | Yes |
| Satd. Flow (RTOR) | |
| Link Speed (k/h) | |
| Link Distance (m) | |
| Travel Time (s) | |
| Confl. Peds. (#/hr) | 13 |
| Confl. Bikes (#/hr) | |
| Peak Hour Factor | 0.90 |
| Heavy Vehicles (%) | 7% |
| Adj. Flow (vph) | 30 |
| Shared Lane Traffic (%) | |
| Lane Group Flow (vph) | 0 |
| Turn Type | |
| Protected Phases | |
| Permitted Phases | |
| Detector Phase | |
| Switch Phase | |
| Minimum Initial (s) | |
| Minimum Split (s) | |
| Total Split (s) | |
| Total Split (%) | |
| Maximum Green (s) | |
| Yellow Time (s) | |
| All-Red Time (s) | |
| Lost Time Adjust (s) | |
| Total Lost Time (s) | |
| Lead/Lag | |
| Lead-Lag Optimize? | |
| Vehicle Extension (s) | |
| Recall Mode | |
| Walk Time (s) | |
| Flash Dont Walk (s) | |
| Pedestrian Calls (#/hr) | |
| Act Effct Green (s) | |
| Actuated g/C Ratio | |

1: Iroquois Road & Carling Avenue
1995 Carling Avenue

Existing (2020) Traffic
AM Peak Hour




| Lane Group | EBL | EBT | EBR | WBU | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT |
|------------------------|------|-------|-----|-----|------|-------|------|-----|-------|-----|------|-------|
| v/c Ratio | 0.03 | 0.50 | | | 0.18 | 0.17 | 0.09 | | 0.19 | | 0.33 | 0.12 |
| Control Delay | 8.3 | 9.9 | | | 23.4 | 18.0 | 1.6 | | 29.5 | | 44.2 | 14.4 |
| Queue Delay | 0.0 | 0.0 | | | 0.0 | 0.0 | 0.0 | | 0.0 | | 0.0 | 0.0 |
| Total Delay | 8.3 | 9.9 | | | 23.4 | 18.0 | 1.6 | | 29.5 | | 44.2 | 14.4 |
| LOS | A | A | | | C | B | A | | C | | D | B |
| Approach Delay | | 9.8 | | | | 16.0 | | | 29.5 | | | 34.8 |
| Approach LOS | | A | | | | B | | | C | | | C |
| Queue Length 50th (m) | 0.9 | 42.5 | | | 2.6 | 20.3 | 0.0 | | 10.9 | | 20.1 | 1.8 |
| Queue Length 95th (m) | 5.4 | 113.9 | | | 8.4 | 26.9 | 3.7 | | 18.8 | | 28.4 | 9.2 |
| Internal Link Dist (m) | | 281.5 | | | | 174.3 | | | 273.2 | | | 280.9 |
| Turn Bay Length (m) | 25.0 | | | | 20.0 | | 85.0 | | | | 50.0 | |
| Base Capacity (vph) | 792 | 3589 | | | 105 | 2343 | 750 | | 547 | | 407 | 513 |
| Starvation Cap Reductn | 0 | 0 | | | 0 | 0 | 0 | | 0 | | 0 | 0 |
| Spillback Cap Reductn | 0 | 0 | | | 0 | 0 | 0 | | 0 | | 0 | 0 |
| Storage Cap Reductn | 0 | 0 | | | 0 | 0 | 0 | | 0 | | 0 | 0 |
| Reduced v/c Ratio | 0.03 | 0.50 | | | 0.18 | 0.17 | 0.09 | | 0.12 | | 0.20 | 0.07 |

Intersection Summary

| | |
|-----------------------------------|---|
| Area Type: | Other |
| Cycle Length: | 130 |
| Actuated Cycle Length: | 130 |
| Offset: | 6 (5%), Referenced to phase 4:EBTL and 8:WBTL, Start of Green |
| Natural Cycle: | 90 |
| Control Type: | Actuated-Coordinated |
| Maximum v/c Ratio: | 0.50 |
| Intersection Signal Delay: | 12.7 |
| Intersection Capacity Utilization | 58.8% |
| Analysis Period (min) | 15 |
| Intersection LOS: | B |
| ICU Level of Service | B |

Splits and Phases: 1: Iroquois Road & Carling Avenue





| | |
|------------------------|-----|
| Lane Group | SBR |
| v/c Ratio | |
| Control Delay | |
| Queue Delay | |
| Total Delay | |
| LOS | |
| Approach Delay | |
| Approach LOS | |
| Queue Length 50th (m) | |
| Queue Length 95th (m) | |
| Internal Link Dist (m) | |
| Turn Bay Length (m) | |
| Base Capacity (vph) | |
| Starvation Cap Reductn | |
| Spillback Cap Reductn | |
| Storage Cap Reductn | |
| Reduced v/c Ratio | |
| Intersection Summary | |

2: Hare Avenue & Carling Avenue
 1995 Carling Avenue

Existing (2020) Traffic
 AM Peak Hour

| Intersection | | | | | | | | |
|--------------------------|------|------|------|------|------|------|------|------|
| Int Delay, s/veh | 0.8 | | | | | | | |
| Movement | EBU | EBT | EBR | WBU | WBL | WBT | NBL | NBR |
| Lane Configurations | ↑↑↑ | | | | ↓ | ↑↑↑ | ↑ | |
| Traffic Vol, veh/h | 1 | 1730 | 7 | 15 | 13 | 435 | 7 | 15 |
| Future Vol, veh/h | 1 | 1730 | 7 | 15 | 13 | 435 | 7 | 15 |
| Conflicting Peds, #/hr | 0 | 0 | 2 | 0 | 2 | 0 | 2 | 0 |
| Sign Control | Free | Free | Free | Free | Free | Free | Stop | Stop |
| RT Channelized | - | - | None | - | - | None | - | None |
| Storage Length | - | - | - | - | 250 | - | 0 | - |
| Veh in Median Storage, # | - | 0 | - | - | - | 0 | 0 | - |
| Grade, % | - | 0 | - | - | - | 0 | 0 | - |
| Peak Hour Factor | 90 | 90 | 90 | 90 | 90 | 90 | 90 | 90 |
| Heavy Vehicles, % | 0 | 0 | 14 | 0 | 0 | 0 | 0 | 7 |
| Mvmt Flow | 1 | 1922 | 8 | 17 | 14 | 483 | 8 | 17 |

| Major/Minor | Major1 | | Major2 | | Minor1 | | | |
|----------------------|--------|---|--------|------|--------|---|------|------|
| Conflicting Flow All | 353 | 0 | 0 | 1409 | 1932 | 0 | 2187 | 967 |
| Stage 1 | - | - | - | - | - | - | 1930 | - |
| Stage 2 | - | - | - | - | - | - | 257 | - |
| Critical Hdwy | 5.6 | - | - | 5.6 | 5.3 | - | 5.7 | 7.24 |
| Critical Hdwy Stg 1 | - | - | - | - | - | - | 6.6 | - |
| Critical Hdwy Stg 2 | - | - | - | - | - | - | 6 | - |
| Follow-up Hdwy | 2.3 | - | - | 2.3 | 3.1 | - | 3.8 | 3.97 |
| Pot Cap-1 Maneuver | 1010 | - | - | 265 | 139 | - | 76 | 211 |
| Stage 1 | - | - | - | - | - | - | 64 | - |
| Stage 2 | - | - | - | - | - | - | 705 | - |
| Platoon blocked, % | - | - | - | - | - | - | - | - |
| Mov Cap-1 Maneuver | 1010 | - | - | 181 | 181 | - | 63 | 211 |
| Mov Cap-2 Maneuver | - | - | - | - | - | - | 63 | - |
| Stage 1 | - | - | - | - | - | - | 64 | - |
| Stage 2 | - | - | - | - | - | - | 583 | - |

| Approach | EB | WB | NB |
|----------------------|----|-----|------|
| HCM Control Delay, s | 0 | 1.7 | 42.1 |
| HCM LOS | | | E |

| Minor Lane/Major Mvmt | NBLn1 | EBT | EBR | WBL | WBT |
|-----------------------|-------|-----|-----|-------|-----|
| Capacity (veh/h) | 121 | - | - | 181 | - |
| HCM Lane V/C Ratio | 0.202 | - | - | 0.172 | - |
| HCM Control Delay (s) | 42.1 | - | - | 28.9 | - |
| HCM Lane LOS | E | - | - | D | - |
| HCM 95th %tile Q(veh) | 0.7 | - | - | 0.6 | - |

3: Carling Avenue & Bromley Road
1995 Carling Avenue

Existing (2020) Traffic
AM Peak Hour

| Intersection | | | | | | |
|--------------------------|------|------|------|------|------|------|
| Int Delay, s/veh | 0.1 | | | | | |
| Movement | EBL | EBT | WBT | WBR | SBL | SBR |
| Lane Configurations | | ↑↑↑ | ↑↑↑ | | | ↑ |
| Traffic Vol, veh/h | 0 | 1760 | 450 | 5 | 0 | 13 |
| Future Vol, veh/h | 0 | 1760 | 450 | 5 | 0 | 13 |
| Conflicting Peds, #/hr | 8 | 0 | 0 | 8 | 0 | 0 |
| Sign Control | Free | Free | Free | Free | Stop | Stop |
| RT Channelized | - | None | - | None | - | None |
| Storage Length | - | - | - | - | - | 0 |
| Veh in Median Storage, # | - | 0 | 0 | - | 0 | - |
| Grade, % | - | 0 | 0 | - | 0 | - |
| Peak Hour Factor | 90 | 90 | 90 | 90 | 90 | 90 |
| Heavy Vehicles, % | 0 | 0 | 0 | 0 | 0 | 0 |
| Mvmt Flow | 0 | 1956 | 500 | 6 | 0 | 14 |


| Major/Minor | Major1 | Major2 | Minor2 | | |
|----------------------|--------|--------|--------|---|-------|
| Conflicting Flow All | - | 0 | - | 0 | - 261 |
| Stage 1 | - | - | - | - | - |
| Stage 2 | - | - | - | - | - |
| Critical Hdwy | - | - | - | - | - 7.1 |
| Critical Hdwy Stg 1 | - | - | - | - | - |
| Critical Hdwy Stg 2 | - | - | - | - | - |
| Follow-up Hdwy | - | - | - | - | - 3.9 |
| Pot Cap-1 Maneuver | 0 | - | - | - | 0 633 |
| Stage 1 | 0 | - | - | - | 0 - |
| Stage 2 | 0 | - | - | - | 0 - |
| Platoon blocked, % | - | - | - | - | - |
| Mov Cap-1 Maneuver | - | - | - | - | - 628 |
| Mov Cap-2 Maneuver | - | - | - | - | - |
| Stage 1 | - | - | - | - | - |
| Stage 2 | - | - | - | - | - |

| Approach | EB | WB | SB |
|----------------------|----|----|------|
| HCM Control Delay, s | 0 | 0 | 10.9 |
| HCM LOS | | | B |

| Minor Lane/Major Mvmt | EBT | WBT | WBR | SBLn1 |
|-----------------------|-----|-----|-----|-------|
| Capacity (veh/h) | - | - | - | 628 |
| HCM Lane V/C Ratio | - | - | - | 0.023 |
| HCM Control Delay (s) | - | - | - | 10.9 |
| HCM Lane LOS | - | - | - | B |
| HCM 95th %tile Q(veh) | - | - | - | 0.1 |

4: Maitland Avenue/Sherbourne Road & Carling Avenue
1995 Carling Avenue

Existing (2020) Traffic
AM Peak Hour



| Lane Group | EBU | EBL | EBT | EBR | WBU | WBL | WBT | WBR | NBL | NBT | NBR | SBL |
|-------------------------|-------|-------|-------|------|-------|-------|-------|------|-------|-------|------|-------|
| Lane Configurations | | ↔ | ↑↑↑ | | | ↔ | ↑↑ | | ↔ | ↑ | | ↔ |
| Traffic Volume (vph) | 17 | 29 | 1456 | 259 | 6 | 308 | 294 | 17 | 129 | 101 | 415 | 69 |
| Future Volume (vph) | 17 | 29 | 1456 | 259 | 6 | 308 | 294 | 17 | 129 | 101 | 415 | 69 |
| Ideal Flow (vphpl) | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 |
| Storage Length (m) | | 55.0 | | 0.0 | | 115.0 | | 0.0 | 75.0 | | 0.0 | 45.0 |
| Storage Lanes | | 1 | | 0 | | 2 | | 0 | 1 | | 0 | 1 |
| Taper Length (m) | | 7.5 | | | | 7.5 | | | 7.5 | | | 7.5 |
| Lane Util. Factor | 0.91 | 1.00 | 0.91 | 0.91 | 0.95 | 0.97 | 0.95 | 0.95 | 1.00 | 1.00 | 1.00 | 1.00 |
| Ped Bike Factor | | 0.95 | 0.99 | | | 1.00 | 0.99 | | | 0.97 | | |
| Frt | | | 0.977 | | | | 0.992 | | | 0.879 | | |
| Flt Protected | | 0.950 | | | | 0.950 | | | 0.950 | | | 0.950 |
| Satd. Flow (prot) | 0 | 1656 | 4735 | 0 | 0 | 3228 | 3228 | 0 | 1679 | 1506 | 0 | 1679 |
| Flt Permitted | | 0.950 | | | | 0.950 | | | 0.266 | | | 0.111 |
| Satd. Flow (perm) | 0 | 1571 | 4735 | 0 | 0 | 3216 | 3228 | 0 | 470 | 1506 | 0 | 196 |
| Right Turn on Red | | | | Yes | | | | Yes | | | Yes | |
| Satd. Flow (RTOR) | | | 40 | | | | 7 | | | 141 | | |
| Link Speed (k/h) | | | 60 | | | | 60 | | | 50 | | |
| Link Distance (m) | | | 447.3 | | | | 309.6 | | | 300.2 | | |
| Travel Time (s) | | | 26.8 | | | | 18.6 | | | 21.6 | | |
| Confl. Peds. (#/hr) | | 25 | | 16 | | 16 | | 25 | 13 | | 15 | 15 |
| Confl. Bikes (#/hr) | | | | | | | | 1 | | | 2 | |
| Peak Hour Factor | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 |
| Heavy Vehicles (%) | 0% | 7% | 2% | 1% | 0% | 4% | 6% | 0% | 3% | 5% | 2% | 3% |
| Adj. Flow (vph) | 19 | 32 | 1618 | 288 | 7 | 342 | 327 | 19 | 143 | 112 | 461 | 77 |
| Shared Lane Traffic (%) | | | | | | | | | | | | |
| Lane Group Flow (vph) | 0 | 51 | 1906 | 0 | 0 | 349 | 346 | 0 | 143 | 573 | 0 | 77 |
| Turn Type | Prot | Prot | NA | | Prot | Prot | NA | | Perm | NA | | Perm |
| Protected Phases | 7 | 7 | 4 | | 3 | 3 | 8 | | | 2 | | |
| Permitted Phases | | | | | | | | | 2 | | | 6 |
| Detector Phase | 7 | 7 | 4 | | 3 | 3 | 8 | | 2 | 2 | | 6 |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 5.0 | 5.0 | 5.0 | | 5.0 | 5.0 | 5.0 | | 10.0 | 10.0 | | 10.0 |
| Minimum Split (s) | 10.9 | 10.9 | 23.9 | | 10.9 | 10.9 | 23.9 | | 24.8 | 24.8 | | 24.8 |
| Total Split (s) | 19.0 | 19.0 | 61.0 | | 19.0 | 19.0 | 61.0 | | 40.0 | 40.0 | | 40.0 |
| Total Split (%) | 15.8% | 15.8% | 50.8% | | 15.8% | 15.8% | 50.8% | | 33.3% | 33.3% | | 33.3% |
| Maximum Green (s) | 13.1 | 13.1 | 55.1 | | 13.1 | 13.1 | 55.1 | | 33.2 | 33.2 | | 33.2 |
| Yellow Time (s) | 3.7 | 3.7 | 3.7 | | 3.7 | 3.7 | 3.7 | | 3.3 | 3.3 | | 3.3 |
| All-Red Time (s) | 2.2 | 2.2 | 2.2 | | 2.2 | 2.2 | 2.2 | | 3.5 | 3.5 | | 3.5 |
| Lost Time Adjust (s) | | -1.9 | -1.9 | | | -1.9 | -1.9 | | -2.8 | -2.8 | | -2.8 |
| Total Lost Time (s) | | 4.0 | 4.0 | | | 4.0 | 4.0 | | 4.0 | 4.0 | | 4.0 |
| Lead/Lag | Lead | Lead | Lag | | Lead | Lead | Lag | | | | | |
| Lead-Lag Optimize? | Yes | Yes | Yes | | Yes | Yes | Yes | | | | | |
| Vehicle Extension (s) | 3.0 | 3.0 | 3.0 | | 3.0 | 3.0 | 3.0 | | 3.0 | 3.0 | | 3.0 |
| Recall Mode | None | None | C-Max | | None | None | C-Max | | None | None | | None |
| Walk Time (s) | | | 7.0 | | | | 7.0 | | 7.0 | 7.0 | | 7.0 |
| Flash Dont Walk (s) | | | 11.0 | | | | 11.0 | | 11.0 | 11.0 | | 11.0 |
| Pedestrian Calls (#/hr) | | | 16 | | | | 25 | | 15 | 15 | | 13 |
| Act Effct Green (s) | | 11.0 | 57.0 | | | 15.0 | 63.3 | | 36.0 | 36.0 | | 36.0 |
| Actuated g/C Ratio | | 0.09 | 0.48 | | | 0.12 | 0.53 | | 0.30 | 0.30 | | 0.30 |

4: Maitland Avenue/Sherbourne Road & Carling Avenue
1995 Carling Avenue


Existing (2020) Traffic
AM Peak Hour



| Lane Group | SBT | SBR |
|-------------------------|-------|------|
| Lane Configurations | ↔ | |
| Traffic Volume (vph) | 322 | 16 |
| Future Volume (vph) | 322 | 16 |
| Ideal Flow (vphpl) | 1800 | 1800 |
| Storage Length (m) | | 0.0 |
| Storage Lanes | | 0 |
| Taper Length (m) | | |
| Lane Util. Factor | 1.00 | 1.00 |
| Ped Bike Factor | 1.00 | |
| Frt | 0.993 | |
| Flt Protected | | |
| Satd. Flow (prot) | 1765 | 0 |
| Flt Permitted | | |
| Satd. Flow (perm) | 1765 | 0 |
| Right Turn on Red | | Yes |
| Satd. Flow (RTOR) | 2 | |
| Link Speed (k/h) | 50 | |
| Link Distance (m) | 301.0 | |
| Travel Time (s) | 21.7 | |
| Confl. Peds. (#/hr) | | 13 |
| Confl. Bikes (#/hr) | | |
| Peak Hour Factor | 0.90 | 0.90 |
| Heavy Vehicles (%) | 2% | 6% |
| Adj. Flow (vph) | 358 | 18 |
| Shared Lane Traffic (%) | | |
| Lane Group Flow (vph) | 376 | 0 |
| Turn Type | NA | |
| Protected Phases | 6 | |
| Permitted Phases | | |
| Detector Phase | 6 | |
| Switch Phase | | |
| Minimum Initial (s) | 10.0 | |
| Minimum Split (s) | 24.8 | |
| Total Split (s) | 40.0 | |
| Total Split (%) | 33.3% | |
| Maximum Green (s) | 33.2 | |
| Yellow Time (s) | 3.3 | |
| All-Red Time (s) | 3.5 | |
| Lost Time Adjust (s) | -2.8 | |
| Total Lost Time (s) | 4.0 | |
| Lead/Lag | | |
| Lead-Lag Optimize? | | |
| Vehicle Extension (s) | 3.0 | |
| Recall Mode | None | |
| Walk Time (s) | 7.0 | |
| Flash Dont Walk (s) | 11.0 | |
| Pedestrian Calls (#/hr) | 13 | |
| Act Effct Green (s) | 36.0 | |
| Actuated g/C Ratio | 0.30 | |

4: Maitland Avenue/Sherbourne Road & Carling Avenue
1995 Carling Avenue

Existing (2020) Traffic
AM Peak Hour




| Lane Group | EBU | EBL | EBT | EBR | WBU | WBL | WBT | WBR | NBL | NBT | NBR | SBL |
|------------------------|-----|------|-------|-----|-----|-------|-------|-----|-------|--------|-----|-------|
| v/c Ratio | | 0.34 | 0.84 | | | 0.87 | 0.20 | | 1.01 | 1.04 | | 1.33 |
| Control Delay | | 56.3 | 31.2 | | | 73.2 | 16.1 | | 122.8 | 81.2 | | 264.7 |
| Queue Delay | | 0.0 | 0.0 | | | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 |
| Total Delay | | 56.3 | 31.2 | | | 73.2 | 16.1 | | 122.8 | 81.2 | | 264.7 |
| LOS | | E | C | | | E | B | | F | F | | F |
| Approach Delay | | | 31.8 | | | | 44.8 | | | 89.5 | | |
| Approach LOS | | | C | | | | D | | | F | | |
| Queue Length 50th (m) | | 11.4 | 137.3 | | | 42.1 | 22.3 | | ~34.6 | ~121.1 | | ~23.3 |
| Queue Length 95th (m) | | 23.3 | 158.6 | | | #66.4 | 33.4 | | #76.2 | #189.4 | | #54.2 |
| Internal Link Dist (m) | | | 423.3 | | | | 285.6 | | | 276.2 | | |
| Turn Bay Length (m) | | 55.0 | | | | 115.0 | | | 75.0 | | | 45.0 |
| Base Capacity (vph) | | 207 | 2270 | | | 403 | 1706 | | 141 | 550 | | 58 |
| Starvation Cap Reductn | | 0 | 0 | | | 0 | 0 | | 0 | 0 | | 0 |
| Spillback Cap Reductn | | 0 | 0 | | | 0 | 0 | | 0 | 0 | | 0 |
| Storage Cap Reductn | | 0 | 0 | | | 0 | 0 | | 0 | 0 | | 0 |
| Reduced v/c Ratio | | 0.25 | 0.84 | | | 0.87 | 0.20 | | 1.01 | 1.04 | | 1.33 |

Intersection Summary

Area Type: Other
 Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 40 (33%), Referenced to phase 4:EBT and 8:WBT, Start of Green
 Natural Cycle: 80
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 1.33
 Intersection Signal Delay: 51.0 Intersection LOS: D
 Intersection Capacity Utilization 101.0% ICU Level of Service G
 Analysis Period (min) 15
 ~ Volume exceeds capacity, queue is theoretically infinite.
 Queue shown is maximum after two cycles.
 # 95th percentile volume exceeds capacity, queue may be longer.
 Queue shown is maximum after two cycles.

Splits and Phases: 4: Maitland Avenue/Sherbourne Road & Carling Avenue



4: Maitland Avenue/Sherbourne Road & Carling Avenue
 1995 Carling Avenue


Existing (2020) Traffic
 AM Peak Hour



| Lane Group | SBT | SBR |
|------------------------|-------|-----|
| v/c Ratio | 0.71 | |
| Control Delay | 45.7 | |
| Queue Delay | 0.0 | |
| Total Delay | 45.7 | |
| LOS | D | |
| Approach Delay | 82.9 | |
| Approach LOS | F | |
| Queue Length 50th (m) | 78.3 | |
| Queue Length 95th (m) | 113.1 | |
| Internal Link Dist (m) | 277.0 | |
| Turn Bay Length (m) | | |
| Base Capacity (vph) | 530 | |
| Starvation Cap Reductn | 0 | |
| Spillback Cap Reductn | 0 | |
| Storage Cap Reductn | 0 | |
| Reduced v/c Ratio | 0.71 | |
| Intersection Summary | | |

1: Iroquois Road & Carling Avenue
1995 Carling Avenue

Existing (2020) Traffic
PM Peak Hour



| Lane Group | EBU | EBL | EBT | EBR | WBU | WBL | WBT | WBR | NBL | NBT | NBR | SBL |
|-------------------------|-------|-------|-------|------|-------|-------|-------|-------|-------|-------|------|-------|
| Lane Configurations | | | | | | | | | | | | |
| Traffic Volume (vph) | 1 | 41 | 656 | 4 | 6 | 17 | 1425 | 107 | 13 | 20 | 10 | 117 |
| Future Volume (vph) | 1 | 41 | 656 | 4 | 6 | 17 | 1425 | 107 | 13 | 20 | 10 | 117 |
| Ideal Flow (vphpl) | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 |
| Storage Length (m) | | 25.0 | | 0.0 | | 20.0 | | 85.0 | 0.0 | | 0.0 | 50.0 |
| Storage Lanes | | 1 | | 0 | | 1 | | 1 | 0 | | 0 | 1 |
| Taper Length (m) | | 7.5 | | | | 7.5 | | | 7.5 | | | 7.5 |
| Lane Util. Factor | 0.91 | 1.00 | 0.91 | 0.91 | 0.91 | 1.00 | 0.91 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Ped Bike Factor | | | 1.00 | | | 0.98 | | 0.90 | | 0.99 | | 0.98 |
| Frt | | | 0.999 | | | | | 0.850 | | 0.968 | | |
| Flt Protected | | 0.950 | | | | 0.950 | | | | 0.985 | | 0.950 |
| Satd. Flow (prot) | 0 | 1729 | 4865 | 0 | 0 | 1656 | 4919 | 1547 | 0 | 1724 | 0 | 1712 |
| Flt Permitted | | 0.086 | | | | 0.362 | | | | 0.918 | | 0.753 |
| Satd. Flow (perm) | 0 | 157 | 4865 | 0 | 0 | 618 | 4919 | 1391 | 0 | 1595 | 0 | 1336 |
| Right Turn on Red | | | | Yes | | | | Yes | | | Yes | |
| Satd. Flow (RTOR) | | | 1 | | | | | 119 | | 11 | | |
| Link Speed (k/h) | | | 60 | | | | 60 | | | 50 | | |
| Link Distance (m) | | | 305.5 | | | | 198.3 | | | 297.2 | | |
| Travel Time (s) | | | 18.3 | | | | 11.9 | | | 21.4 | | |
| Confl. Peds. (#/hr) | | 28 | | 19 | | 19 | | 28 | 28 | | 17 | 17 |
| Confl. Bikes (#/hr) | | | | 6 | | | | | | | | |
| Peak Hour Factor | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 |
| Heavy Vehicles (%) | 0% | 0% | 2% | 0% | 0% | 6% | 1% | 0% | 0% | 0% | 0% | 1% |
| Adj. Flow (vph) | 1 | 46 | 729 | 4 | 7 | 19 | 1583 | 119 | 14 | 22 | 11 | 130 |
| Shared Lane Traffic (%) | | | | | | | | | | | | |
| Lane Group Flow (vph) | 0 | 47 | 733 | 0 | 0 | 26 | 1583 | 119 | 0 | 47 | 0 | 130 |
| Turn Type | pm+pt | pm+pt | NA | | Perm | Perm | NA | Perm | Perm | NA | | Perm |
| Protected Phases | 7 | 7 | 4 | | | | 8 | | | 2 | | |
| Permitted Phases | 4 | 4 | | | 8 | 8 | | 8 | 2 | | | 6 |
| Detector Phase | 7 | 7 | 4 | | 8 | 8 | 8 | 8 | 2 | 2 | | 6 |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 5.0 | 5.0 | 5.0 | | 5.0 | 5.0 | 5.0 | 5.0 | 10.0 | 10.0 | | 10.0 |
| Minimum Split (s) | 12.0 | 12.0 | 28.3 | | 28.3 | 28.3 | 28.3 | 28.3 | 47.3 | 47.3 | | 47.3 |
| Total Split (s) | 12.0 | 12.0 | 83.0 | | 71.0 | 71.0 | 71.0 | 71.0 | 47.0 | 47.0 | | 47.0 |
| Total Split (%) | 9.2% | 9.2% | 63.8% | | 54.6% | 54.6% | 54.6% | 54.6% | 36.2% | 36.2% | | 36.2% |
| Maximum Green (s) | 5.0 | 5.0 | 76.7 | | 64.7 | 64.7 | 64.7 | 64.7 | 39.7 | 39.7 | | 39.7 |
| Yellow Time (s) | 3.7 | 3.7 | 3.7 | | 3.7 | 3.7 | 3.7 | 3.7 | 3.3 | 3.3 | | 3.3 |
| All-Red Time (s) | 3.3 | 3.3 | 2.6 | | 2.6 | 2.6 | 2.6 | 2.6 | 4.0 | 4.0 | | 4.0 |
| Lost Time Adjust (s) | | -3.0 | -2.3 | | | -2.3 | -2.3 | -2.3 | | -3.3 | | -3.3 |
| Total Lost Time (s) | | 4.0 | 4.0 | | | 4.0 | 4.0 | 4.0 | | 4.0 | | 4.0 |
| Lead/Lag | Lead | Lead | | | Lag | Lag | Lag | Lag | | | | |
| Lead-Lag Optimize? | Yes | Yes | | | Yes | Yes | Yes | Yes | | | | |
| Vehicle Extension (s) | 3.0 | 3.0 | 3.0 | | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | | 3.0 |
| Recall Mode | Max | Max | C-Max | | C-Max | C-Max | C-Max | C-Max | None | None | | None |
| Walk Time (s) | | | 10.0 | | 10.0 | 10.0 | 10.0 | 10.0 | 27.0 | 27.0 | | 27.0 |
| Flash Dont Walk (s) | | | 12.0 | | 12.0 | 12.0 | 12.0 | 12.0 | 13.0 | 13.0 | | 13.0 |
| Pedestrian Calls (#/hr) | | | 19 | | 28 | 28 | 28 | 28 | 17 | 17 | | 28 |
| Act Effct Green (s) | | 89.8 | 89.8 | | | 67.0 | 67.0 | 67.0 | | 32.2 | | 32.2 |
| Actuated g/C Ratio | | 0.69 | 0.69 | | | 0.52 | 0.52 | 0.52 | | 0.25 | | 0.25 |

1: Iroquois Road & Carling Avenue
1995 Carling Avenue


Existing (2020) Traffic
PM Peak Hour



| Lane Group | SBT | SBR |
|-------------------------|-------|------|
| Lane Configurations | ↔ | |
| Traffic Volume (vph) | 23 | 60 |
| Future Volume (vph) | 23 | 60 |
| Ideal Flow (vphpl) | 1800 | 1800 |
| Storage Length (m) | | 0.0 |
| Storage Lanes | | 0 |
| Taper Length (m) | | |
| Lane Util. Factor | 1.00 | 1.00 |
| Ped Bike Factor | 0.97 | |
| Frt | 0.892 | |
| Flt Protected | | |
| Satd. Flow (prot) | 1554 | 0 |
| Flt Permitted | | |
| Satd. Flow (perm) | 1554 | 0 |
| Right Turn on Red | | Yes |
| Satd. Flow (RTOR) | 24 | |
| Link Speed (k/h) | 50 | |
| Link Distance (m) | 304.9 | |
| Travel Time (s) | 22.0 | |
| Confl. Peds. (#/hr) | | 28 |
| Confl. Bikes (#/hr) | | 2 |
| Peak Hour Factor | 0.90 | 0.90 |
| Heavy Vehicles (%) | 0% | 2% |
| Adj. Flow (vph) | 26 | 67 |
| Shared Lane Traffic (%) | | |
| Lane Group Flow (vph) | 93 | 0 |
| Turn Type | NA | |
| Protected Phases | 6 | |
| Permitted Phases | | |
| Detector Phase | 6 | |
| Switch Phase | | |
| Minimum Initial (s) | 10.0 | |
| Minimum Split (s) | 47.3 | |
| Total Split (s) | 47.0 | |
| Total Split (%) | 36.2% | |
| Maximum Green (s) | 39.7 | |
| Yellow Time (s) | 3.3 | |
| All-Red Time (s) | 4.0 | |
| Lost Time Adjust (s) | -3.3 | |
| Total Lost Time (s) | 4.0 | |
| Lead/Lag | | |
| Lead-Lag Optimize? | | |
| Vehicle Extension (s) | 3.0 | |
| Recall Mode | None | |
| Walk Time (s) | 27.0 | |
| Flash Dont Walk (s) | 13.0 | |
| Pedestrian Calls (#/hr) | 28 | |
| Act Effct Green (s) | 32.2 | |
| Actuated g/C Ratio | 0.25 | |

1: Iroquois Road & Carling Avenue
1995 Carling Avenue

Existing (2020) Traffic
PM Peak Hour




| Lane Group | EBU | EBL | EBT | EBR | WBU | WBL | WBT | WBR | NBL | NBT | NBR | SBL |
|------------------------|-----|------|-------|-----|-----|------|-------|------|-----|-------|-----|------|
| v/c Ratio | | 0.14 | 0.22 | | | 0.08 | 0.62 | 0.15 | | 0.12 | | 0.39 |
| Control Delay | | 10.4 | 9.1 | | | 16.9 | 23.9 | 3.2 | | 26.4 | | 41.4 |
| Queue Delay | | 0.0 | 0.0 | | | 0.0 | 0.0 | 0.0 | | 0.0 | | 0.0 |
| Total Delay | | 10.4 | 9.1 | | | 16.9 | 23.9 | 3.2 | | 26.4 | | 41.4 |
| LOS | | B | A | | | B | C | A | | C | | D |
| Approach Delay | | | 9.2 | | | | 22.4 | | | 26.4 | | |
| Approach LOS | | | A | | | | C | | | C | | |
| Queue Length 50th (m) | | 4.6 | 30.0 | | | 3.3 | 102.8 | 0.0 | | 6.3 | | 24.6 |
| Queue Length 95th (m) | | 9.6 | 36.8 | | | 8.5 | 118.0 | 9.3 | | 15.2 | | 41.6 |
| Internal Link Dist (m) | | | 281.5 | | | | 174.3 | | | 273.2 | | |
| Turn Bay Length (m) | | 25.0 | | | | 20.0 | | 85.0 | | | | 50.0 |
| Base Capacity (vph) | | 335 | 3359 | | | 318 | 2535 | 774 | | 534 | | 441 |
| Starvation Cap Reductn | | 0 | 0 | | | 0 | 0 | 0 | | 0 | | 0 |
| Spillback Cap Reductn | | 0 | 0 | | | 0 | 0 | 0 | | 0 | | 0 |
| Storage Cap Reductn | | 0 | 0 | | | 0 | 0 | 0 | | 0 | | 0 |
| Reduced v/c Ratio | | 0.14 | 0.22 | | | 0.08 | 0.62 | 0.15 | | 0.09 | | 0.29 |

Intersection Summary

| | |
|------------------------------------|---|
| Area Type: | Other |
| Cycle Length: | 130 |
| Actuated Cycle Length: | 130 |
| Offset: | 95 (73%), Referenced to phase 4:EBTL and 8:WBTL, Start of Green |
| Natural Cycle: | 90 |
| Control Type: | Actuated-Coordinated |
| Maximum v/c Ratio: | 0.62 |
| Intersection Signal Delay: | 19.7 |
| Intersection LOS: | B |
| Intersection Capacity Utilization: | 68.8% |
| ICU Level of Service: | C |
| Analysis Period (min): | 15 |

Splits and Phases: 1: Iroquois Road & Carling Avenue



1: Iroquois Road & Carling Avenue
 1995 Carling Avenue

Existing (2020) Traffic
 PM Peak Hour



| Lane Group | SBT | SBR |
|-----------------------------|-------|-----|
| v/c Ratio | 0.23 | |
| Control Delay | 26.4 | |
| Queue Delay | 0.0 | |
| Total Delay | 26.4 | |
| LOS | C | |
| Approach Delay | 35.1 | |
| Approach LOS | D | |
| Queue Length 50th (m) | 12.4 | |
| Queue Length 95th (m) | 25.2 | |
| Internal Link Dist (m) | 280.9 | |
| Turn Bay Length (m) | | |
| Base Capacity (vph) | 530 | |
| Starvation Cap Reductn | 0 | |
| Spillback Cap Reductn | 0 | |
| Storage Cap Reductn | 0 | |
| Reduced v/c Ratio | 0.18 | |
| Intersection Summary | | |

2: Hare Avenue & Carling Avenue
1995 Carling Avenue

Existing (2020) Traffic
PM Peak Hour

| Intersection | | | | | | | | |
|--------------------------|------|------|------|------|------|------|------|------|
| Int Delay, s/veh | 0.6 | | | | | | | |
| Movement | EBU | EBT | EBR | WBU | WBL | WBT | NBL | NBR |
| Lane Configurations | ↑↑↑ | | | | ↑ | ↑↑↑ | ↑ | |
| Traffic Vol, veh/h | 1 | 780 | 8 | 26 | 37 | 1544 | 10 | 11 |
| Future Vol, veh/h | 1 | 780 | 8 | 26 | 37 | 1544 | 10 | 11 |
| Conflicting Peds, #/hr | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Sign Control | Free | Free | Free | Free | Free | Free | Stop | Stop |
| RT Channelized | - | - | None | - | - | None | - | None |
| Storage Length | - | - | - | - | 250 | - | 0 | - |
| Veh in Median Storage, # | - | 0 | - | - | - | 0 | 0 | - |
| Grade, % | - | 0 | - | - | - | 0 | 0 | - |
| Peak Hour Factor | 90 | 90 | 90 | 90 | 90 | 90 | 90 | 90 |
| Heavy Vehicles, % | 0 | 0 | 0 | 4 | 0 | 0 | 0 | 0 |
| Mvmt Flow | 1 | 867 | 9 | 29 | 41 | 1716 | 11 | 12 |

| Major/Minor | Major1 | | Major2 | | Minor1 | | | |
|----------------------|--------|---|--------|------|--------|---|------|-----|
| Conflicting Flow All | 1252 | 0 | 0 | 639 | 876 | 0 | 1700 | 438 |
| Stage 1 | - | - | - | - | - | - | 874 | - |
| Stage 2 | - | - | - | - | - | - | 826 | - |
| Critical Hdwy | 5.6 | - | - | 5.68 | 5.3 | - | 5.7 | 7.1 |
| Critical Hdwy Stg 1 | - | - | - | - | - | - | 6.6 | - |
| Critical Hdwy Stg 2 | - | - | - | - | - | - | 6 | - |
| Follow-up Hdwy | 2.3 | - | - | 2.34 | 3.1 | - | 3.8 | 3.9 |
| Pot Cap-1 Maneuver | 324 | - | - | 686 | 455 | - | 138 | 489 |
| Stage 1 | - | - | - | - | - | - | 292 | - |
| Stage 2 | - | - | - | - | - | - | 358 | - |
| Platoon blocked, % | - | - | - | - | - | - | - | - |
| Mov Cap-1 Maneuver | 324 | - | - | 525 | 525 | - | 119 | 489 |
| Mov Cap-2 Maneuver | - | - | - | - | - | - | 119 | - |
| Stage 1 | - | - | - | - | - | - | 290 | - |
| Stage 2 | - | - | - | - | - | - | 310 | - |

| Approach | EB | WB | NB |
|----------------------|----|-----|------|
| HCM Control Delay, s | 0 | 0.5 | 25.7 |
| HCM LOS | | | D |

| Minor Lane/Major Mvmt | NBLn1 | EBT | EBR | WBL | WBT |
|-----------------------|-------|-----|-----|-------|-----|
| Capacity (veh/h) | 197 | - | - | 525 | - |
| HCM Lane V/C Ratio | 0.118 | - | - | 0.133 | - |
| HCM Control Delay (s) | 25.7 | - | - | 12.9 | - |
| HCM Lane LOS | D | - | - | B | - |
| HCM 95th %tile Q(veh) | 0.4 | - | - | 0.5 | - |

3: Carling Avenue & Bromley Road
 1995 Carling Avenue

Existing (2020) Traffic
 PM Peak Hour

| Intersection | | | | | | |
|--------------------------|------|------|------|------|------|------|
| Int Delay, s/veh | 0.1 | | | | | |
| Movement | EBL | EBT | WBT | WBR | SBL | SBR |
| Lane Configurations | | ↑↑↑ | ↑↑↑ | | | ↑ |
| Traffic Vol, veh/h | 0 | 817 | 1595 | 16 | 0 | 12 |
| Future Vol, veh/h | 0 | 817 | 1595 | 16 | 0 | 12 |
| Conflicting Peds, #/hr | 0 | 0 | 0 | 0 | 0 | 0 |
| Sign Control | Free | Free | Free | Free | Stop | Stop |
| RT Channelized | - | None | - | None | - | None |
| Storage Length | - | - | - | - | - | 0 |
| Veh in Median Storage, # | - | 0 | 0 | - | 0 | - |
| Grade, % | - | 0 | 0 | - | 0 | - |
| Peak Hour Factor | 90 | 90 | 90 | 90 | 90 | 90 |
| Heavy Vehicles, % | 0 | 0 | 0 | 0 | 0 | 8 |
| Mvmt Flow | 0 | 908 | 1772 | 18 | 0 | 13 |


| Major/Minor | Major1 | Major2 | Minor2 | | |
|----------------------|--------|--------|--------|---|------|
| Conflicting Flow All | - | 0 | - | 0 | 895 |
| Stage 1 | - | - | - | - | - |
| Stage 2 | - | - | - | - | - |
| Critical Hdwy | - | - | - | - | 7.26 |
| Critical Hdwy Stg 1 | - | - | - | - | - |
| Critical Hdwy Stg 2 | - | - | - | - | - |
| Follow-up Hdwy | - | - | - | - | 3.98 |
| Pot Cap-1 Maneuver | 0 | - | - | - | 234 |
| Stage 1 | 0 | - | - | - | - |
| Stage 2 | 0 | - | - | - | - |
| Platoon blocked, % | - | - | - | - | - |
| Mov Cap-1 Maneuver | - | - | - | - | 234 |
| Mov Cap-2 Maneuver | - | - | - | - | - |
| Stage 1 | - | - | - | - | - |
| Stage 2 | - | - | - | - | - |

| Approach | EB | WB | SB |
|----------------------|----|----|------|
| HCM Control Delay, s | 0 | 0 | 21.3 |
| HCM LOS | | | C |

| Minor Lane/Major Mvmt | EBT | WBT | WBR | SBLn1 |
|-----------------------|-----|-----|-----|-------|
| Capacity (veh/h) | - | - | - | 234 |
| HCM Lane V/C Ratio | - | - | - | 0.057 |
| HCM Control Delay (s) | - | - | - | 21.3 |
| HCM Lane LOS | - | - | - | C |
| HCM 95th %tile Q(veh) | - | - | - | 0.2 |

4: Maitland Avenue/Sherbourne Road & Carling Avenue
1995 Carling Avenue

Existing (2020) Traffic
PM Peak Hour



| Lane Group | EBU | EBL | EBT | EBR | WBU | WBL | WBT | WBR | NBL | NBT | NBR | SBL |
|---------------------------|-------|-------|-------|------|-------|-------|-------|------|-------|-------|------|-------|
| Lane Configurations | | ↔ | ↑↑↑ | | | ↔ | ↑↑ | | ↔ | ↑ | | ↔ |
| Traffic Volume (vph) | 23 | 62 | 565 | 167 | 9 | 749 | 1335 | 55 | 209 | 218 | 218 | 49 |
| Future Volume (vph) | 23 | 62 | 565 | 167 | 9 | 749 | 1335 | 55 | 209 | 218 | 218 | 49 |
| Ideal Flow (vphpl) | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 |
| Storage Length (m) | | 55.0 | | 0.0 | | 115.0 | | 0.0 | 75.0 | | 0.0 | 45.0 |
| Storage Lanes | | 1 | | 0 | | 1 | | 0 | 1 | | 0 | 1 |
| Taper Length (m) | | 7.5 | | | | 7.5 | | | 7.5 | | | 7.5 |
| Lane Util. Factor | 0.91 | 1.00 | 0.91 | 0.91 | 0.95 | 0.97 | 0.95 | 0.95 | 1.00 | 1.00 | 1.00 | 1.00 |
| Ped Bike Factor | | 0.99 | 0.99 | | | 0.97 | 0.99 | | 0.98 | 0.98 | | |
| Fr _t | | | 0.966 | | | | 0.994 | | | 0.925 | | |
| Fl _t Protected | | 0.950 | | | | 0.950 | | | 0.950 | | | 0.950 |
| Satd. Flow (prot) | 0 | 1729 | 4650 | 0 | 0 | 3321 | 3381 | 0 | 1729 | 1624 | 0 | 1729 |
| Fl _t Permitted | | 0.950 | | | | 0.950 | | | 0.423 | | | 0.157 |
| Satd. Flow (perm) | 0 | 1705 | 4650 | 0 | 0 | 3232 | 3381 | 0 | 755 | 1624 | 0 | 286 |
| Right Turn on Red | | | | Yes | | | | Yes | | | Yes | |
| Satd. Flow (RTOR) | | | 61 | | | | 5 | | | 44 | | |
| Link Speed (k/h) | | | 60 | | | | 60 | | | 50 | | |
| Link Distance (m) | | | 447.3 | | | | 309.6 | | | 300.2 | | |
| Travel Time (s) | | | 26.8 | | | | 18.6 | | | 21.6 | | |
| Confl. Peds. (#/hr) | | 36 | | 25 | | 25 | | 36 | 20 | | 15 | 15 |
| Confl. Bikes (#/hr) | | | | | | | | 2 | | | | |
| Peak Hour Factor | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 |
| Heavy Vehicles (%) | 0% | 0% | 2% | 1% | 0% | 1% | 1% | 4% | 0% | 0% | 3% | 0% |
| Adj. Flow (vph) | 26 | 69 | 628 | 186 | 10 | 832 | 1483 | 61 | 232 | 242 | 242 | 54 |
| Shared Lane Traffic (%) | | | | | | | | | | | | |
| Lane Group Flow (vph) | 0 | 95 | 814 | 0 | 0 | 842 | 1544 | 0 | 232 | 484 | 0 | 54 |
| Turn Type | Prot | Prot | NA | | Prot | Prot | NA | | Perm | NA | | Perm |
| Protected Phases | 7 | 7 | 4 | | 3 | 3 | 8 | | | 2 | | |
| Permitted Phases | | | | | | | | | 2 | | | 6 |
| Detector Phase | 7 | 7 | 4 | | 3 | 3 | 8 | | 2 | 2 | | 6 |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 5.0 | 5.0 | 5.0 | | 5.0 | 5.0 | 5.0 | | 10.0 | 10.0 | | 10.0 |
| Minimum Split (s) | 10.9 | 10.9 | 23.9 | | 10.9 | 10.9 | 23.9 | | 24.8 | 24.8 | | 24.8 |
| Total Split (s) | 15.0 | 15.0 | 36.0 | | 41.0 | 41.0 | 62.0 | | 43.0 | 43.0 | | 43.0 |
| Total Split (%) | 12.5% | 12.5% | 30.0% | | 34.2% | 34.2% | 51.7% | | 35.8% | 35.8% | | 35.8% |
| Maximum Green (s) | 9.1 | 9.1 | 30.1 | | 35.1 | 35.1 | 56.1 | | 36.2 | 36.2 | | 36.2 |
| Yellow Time (s) | 3.7 | 3.7 | 3.7 | | 3.7 | 3.7 | 3.7 | | 3.3 | 3.3 | | 3.3 |
| All-Red Time (s) | 2.2 | 2.2 | 2.2 | | 2.2 | 2.2 | 2.2 | | 3.5 | 3.5 | | 3.5 |
| Lost Time Adjust (s) | | -1.9 | -1.9 | | | -1.9 | -1.9 | | -2.8 | -2.8 | | -2.8 |
| Total Lost Time (s) | | 4.0 | 4.0 | | | 4.0 | 4.0 | | 4.0 | 4.0 | | 4.0 |
| Lead/Lag | Lead | Lead | Lag | | Lead | Lead | Lag | | | | | |
| Lead-Lag Optimize? | Yes | Yes | Yes | | Yes | Yes | Yes | | | | | |
| Vehicle Extension (s) | 3.0 | 3.0 | 3.0 | | 3.0 | 3.0 | 3.0 | | 3.0 | 3.0 | | 3.0 |
| Recall Mode | None | None | C-Max | | None | None | C-Max | | None | None | | None |
| Walk Time (s) | | | 7.0 | | | | 7.0 | | 7.0 | 7.0 | | 7.0 |
| Flash Dont Walk (s) | | | 11.0 | | | | 11.0 | | 11.0 | 11.0 | | 11.0 |
| Pedestrian Calls (#/hr) | | | 25 | | | | 36 | | 15 | 15 | | 20 |
| Act Effct Green (s) | | 10.7 | 34.3 | | | 35.3 | 59.0 | | 38.4 | 38.4 | | 38.4 |
| Actuated g/C Ratio | | 0.09 | 0.29 | | | 0.29 | 0.49 | | 0.32 | 0.32 | | 0.32 |

4: Maitland Avenue/Sherbourne Road & Carling Avenue
 1995 Carling Avenue


Existing (2020) Traffic
 PM Peak Hour



| Lane Group | SBT | SBR |
|-------------------------|-------|------|
| Lane Configurations | ↔ | |
| Traffic Volume (vph) | 205 | 44 |
| Future Volume (vph) | 205 | 44 |
| Ideal Flow (vphpl) | 1800 | 1800 |
| Storage Length (m) | | 0.0 |
| Storage Lanes | | 0 |
| Taper Length (m) | | |
| Lane Util. Factor | 1.00 | 1.00 |
| Ped Bike Factor | 0.99 | |
| Frt | 0.973 | |
| Flt Protected | | |
| Satd. Flow (prot) | 1749 | 0 |
| Flt Permitted | | |
| Satd. Flow (perm) | 1749 | 0 |
| Right Turn on Red | | Yes |
| Satd. Flow (RTOR) | 10 | |
| Link Speed (k/h) | 50 | |
| Link Distance (m) | 301.0 | |
| Travel Time (s) | 21.7 | |
| Confl. Peds. (#/hr) | | 20 |
| Confl. Bikes (#/hr) | | |
| Peak Hour Factor | 0.90 | 0.90 |
| Heavy Vehicles (%) | 0% | 2% |
| Adj. Flow (vph) | 228 | 49 |
| Shared Lane Traffic (%) | | |
| Lane Group Flow (vph) | 277 | 0 |
| Turn Type | NA | |
| Protected Phases | 6 | |
| Permitted Phases | | |
| Detector Phase | 6 | |
| Switch Phase | | |
| Minimum Initial (s) | 10.0 | |
| Minimum Split (s) | 24.8 | |
| Total Split (s) | 43.0 | |
| Total Split (%) | 35.8% | |
| Maximum Green (s) | 36.2 | |
| Yellow Time (s) | 3.3 | |
| All-Red Time (s) | 3.5 | |
| Lost Time Adjust (s) | -2.8 | |
| Total Lost Time (s) | 4.0 | |
| Lead/Lag | | |
| Lead-Lag Optimize? | | |
| Vehicle Extension (s) | 3.0 | |
| Recall Mode | None | |
| Walk Time (s) | 7.0 | |
| Flash Dont Walk (s) | 11.0 | |
| Pedestrian Calls (#/hr) | 20 | |
| Act Effct Green (s) | 38.4 | |
| Actuated g/C Ratio | 0.32 | |

4: Maitland Avenue/Sherbourne Road & Carling Avenue
1995 Carling Avenue

Existing (2020) Traffic
PM Peak Hour




| Lane Group | EBU | EBL | EBT | EBR | WBU | WBL | WBT | WBR | NBL | NBT | NBR | SBL |
|------------------------|-----|--------|-------|-----|-----|-------|--------|-----|--------|--------|-----|-------|
| v/c Ratio | | 0.62 | 0.59 | | | 0.86 | 0.93 | | 0.96 | 0.88 | | 0.59 |
| Control Delay | | 70.8 | 36.9 | | | 50.0 | 39.8 | | 90.2 | 53.9 | | 63.5 |
| Queue Delay | | 0.0 | 0.0 | | | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 |
| Total Delay | | 70.8 | 36.9 | | | 50.0 | 39.8 | | 90.2 | 53.9 | | 63.5 |
| LOS | | E | D | | | D | D | | F | D | | E |
| Approach Delay | | | 40.4 | | | | 43.4 | | | 65.7 | | |
| Approach LOS | | | D | | | | D | | | E | | |
| Queue Length 50th (m) | | 21.9 | 58.0 | | | 94.5 | 176.2 | | 53.1 | 98.5 | | 10.6 |
| Queue Length 95th (m) | | m#41.7 | m72.1 | | | 118.8 | #229.4 | | #102.6 | #157.2 | | #30.2 |
| Internal Link Dist (m) | | | 423.3 | | | | 285.6 | | | 276.2 | | |
| Turn Bay Length (m) | | 55.0 | | | | 115.0 | | | 75.0 | | | 45.0 |
| Base Capacity (vph) | | 158 | 1371 | | | 1023 | 1663 | | 245 | 557 | | 92 |
| Starvation Cap Reductn | | 0 | 0 | | | 0 | 0 | | 0 | 0 | | 0 |
| Spillback Cap Reductn | | 0 | 0 | | | 0 | 0 | | 0 | 0 | | 0 |
| Storage Cap Reductn | | 0 | 0 | | | 0 | 0 | | 0 | 0 | | 0 |
| Reduced v/c Ratio | | 0.60 | 0.59 | | | 0.82 | 0.93 | | 0.95 | 0.87 | | 0.59 |

Intersection Summary

Area Type: Other
 Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 103 (86%), Referenced to phase 4:EBT and 8:WBT, Start of Green
 Natural Cycle: 90
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.96
 Intersection Signal Delay: 46.2 Intersection LOS: D
 Intersection Capacity Utilization 94.5% ICU Level of Service F
 Analysis Period (min) 15
 # 95th percentile volume exceeds capacity, queue may be longer.
 Queue shown is maximum after two cycles.
 m Volume for 95th percentile queue is metered by upstream signal.

Splits and Phases: 4: Maitland Avenue/Sherbourne Road & Carling Avenue



4: Maitland Avenue/Sherbourne Road & Carling Avenue
 1995 Carling Avenue






















Existing (2020) Traffic
 PM Peak Hour



| Lane Group | SBT | SBR |
|------------------------|-------|-----|
| v/c Ratio | 0.49 | |
| Control Delay | 35.0 | |
| Queue Delay | 0.0 | |
| Total Delay | 35.0 | |
| LOS | C | |
| Approach Delay | 39.6 | |
| Approach LOS | D | |
| Queue Length 50th (m) | 50.1 | |
| Queue Length 95th (m) | 75.7 | |
| Internal Link Dist (m) | 277.0 | |
| Turn Bay Length (m) | | |
| Base Capacity (vph) | 575 | |
| Starvation Cap Reductn | 0 | |
| Spillback Cap Reductn | 0 | |
| Storage Cap Reductn | 0 | |
| Reduced v/c Ratio | 0.48 | |
| Intersection Summary | | |

1: Iroquois Road & Carling Avenue
1995 Carling Avenue


Future (2024) Background Traffic
AM Peak Hour

| |  |  |  |  |  |  |  |  |  |  |  |  |
|-------------------------|---|---|---|---|---|---|--|---|---|---|---|---|
| Lane Group | EBL | EBT | EBR | WBU | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT |
| Lane Configurations |  |  |  | |  |  |  | |  | |  |  |
| Traffic Volume (vph) | 19 | 1630 | 5 | 10 | 7 | 375 | 60 | 3 | 24 | 30 | 75 | 7 |
| Future Volume (vph) | 19 | 1630 | 5 | 10 | 7 | 375 | 60 | 3 | 24 | 30 | 75 | 7 |
| Ideal Flow (vphpl) | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 |
| Storage Length (m) | 25.0 | | 40.0 | | 20.0 | | 85.0 | 0.0 | | 0.0 | 50.0 | |
| Storage Lanes | 1 | | 1 | | 1 | | 1 | 0 | | 0 | 1 | |
| Taper Length (m) | 7.5 | | | | 7.5 | | | 7.5 | | | 7.5 | |
| Lane Util. Factor | 1.00 | 0.95 | 1.00 | 0.91 | 1.00 | 0.91 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Ped Bike Factor | 0.98 | | 0.94 | | | | 0.94 | | 0.99 | | 0.99 | 0.98 |
| Frt | | | 0.850 | | | | 0.850 | | 0.929 | | | 0.881 |
| Flt Protected | 0.950 | | | | 0.950 | | | | 0.997 | | 0.950 | |
| Satd. Flow (prot) | 1729 | 3390 | 1547 | 0 | 1729 | 4687 | 1502 | 0 | 1635 | 0 | 1679 | 1490 |
| Flt Permitted | 0.479 | | | | 0.152 | | | | 0.990 | | 0.717 | |
| Satd. Flow (perm) | 852 | 3390 | 1461 | 0 | 277 | 4687 | 1406 | 0 | 1623 | 0 | 1254 | 1490 |
| Right Turn on Red | | | Yes | | | | Yes | | | Yes | | |
| Satd. Flow (RTOR) | | | 36 | | | | 95 | | 25 | | | 27 |
| Link Speed (k/h) | | 60 | | | | 60 | | | 50 | | | 50 |
| Link Distance (m) | | 305.5 | | | | 136.9 | | | 297.2 | | | 304.9 |
| Travel Time (s) | | 18.3 | | | | 8.2 | | | 21.4 | | | 22.0 |
| Confl. Peds. (#/hr) | 15 | | 12 | | 12 | | 15 | 13 | | 12 | 12 | |
| Confl. Bikes (#/hr) | | | 1 | | | | 1 | | | 4 | | |
| Peak Hour Factor | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Heavy Vehicles (%) | 0% | 2% | 0% | 0% | 0% | 6% | 3% | 0% | 4% | 0% | 3% | 0% |
| Adj. Flow (vph) | 19 | 1630 | 5 | 10 | 7 | 375 | 60 | 3 | 24 | 30 | 75 | 7 |
| Shared Lane Traffic (%) | | | | | | | | | | | | |
| Lane Group Flow (vph) | 19 | 1630 | 5 | 0 | 17 | 375 | 60 | 0 | 57 | 0 | 75 | 34 |
| Turn Type | pm+pt | NA | Perm | Perm | Perm | NA | Perm | Perm | NA | | Perm | NA |
| Protected Phases | 7 | 4 | | | | 8 | | | 2 | | | 6 |
| Permitted Phases | 4 | | 4 | 8 | 8 | | 8 | 2 | | | 6 | |
| Detector Phase | 7 | 4 | 4 | 8 | 8 | 8 | 8 | 2 | 2 | | 6 | 6 |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 10.0 | 10.0 | | 10.0 | 10.0 |
| Minimum Split (s) | 12.0 | 28.3 | 28.3 | 28.3 | 28.3 | 28.3 | 28.3 | 47.3 | 47.3 | | 47.3 | 47.3 |
| Total Split (s) | 14.0 | 83.0 | 83.0 | 69.0 | 69.0 | 69.0 | 69.0 | 47.0 | 47.0 | | 47.0 | 47.0 |
| Total Split (%) | 10.8% | 63.8% | 63.8% | 53.1% | 53.1% | 53.1% | 53.1% | 36.2% | 36.2% | | 36.2% | 36.2% |
| Maximum Green (s) | 7.0 | 76.7 | 76.7 | 62.7 | 62.7 | 62.7 | 62.7 | 39.7 | 39.7 | | 39.7 | 39.7 |
| Yellow Time (s) | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.3 | 3.3 | | 3.3 | 3.3 |
| All-Red Time (s) | 3.3 | 2.6 | 2.6 | 2.6 | 2.6 | 2.6 | 2.6 | 4.0 | 4.0 | | 4.0 | 4.0 |
| Lost Time Adjust (s) | -3.0 | -2.3 | -2.3 | | -2.3 | -2.3 | -2.3 | | -3.3 | | -3.3 | -3.3 |
| Total Lost Time (s) | 4.0 | 4.0 | 4.0 | | 4.0 | 4.0 | 4.0 | | 4.0 | | 4.0 | 4.0 |
| Lead/Lag | Lead | | | Lag | Lag | Lag | Lag | | | | | |
| Lead-Lag Optimize? | Yes | | | Yes | Yes | Yes | Yes | | | | | |
| Vehicle Extension (s) | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | | 3.0 | 3.0 |
| Recall Mode | Max | C-Max | C-Max | C-Max | C-Max | C-Max | C-Max | None | None | | None | None |
| Walk Time (s) | | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 27.0 | 27.0 | | 27.0 | 27.0 |
| Flash Dont Walk (s) | | 12.0 | 12.0 | 12.0 | 12.0 | 12.0 | 12.0 | 13.0 | 13.0 | | 13.0 | 13.0 |
| Pedestrian Calls (#/hr) | | 12 | 12 | 15 | 15 | 15 | 15 | 12 | 12 | | 13 | 13 |
| Act Effct Green (s) | 99.6 | 100.4 | 100.4 | | 65.0 | 65.0 | 65.0 | | 25.9 | | 25.9 | 25.9 |
| Actuated g/C Ratio | 0.77 | 0.77 | 0.77 | | 0.50 | 0.50 | 0.50 | | 0.20 | | 0.20 | 0.20 |

| Lane Group | SBR |
|-------------------------|------|
| Lane Configurations | |
| Traffic Volume (vph) | 27 |
| Future Volume (vph) | 27 |
| Ideal Flow (vphpl) | 1800 |
| Storage Length (m) | 0.0 |
| Storage Lanes | 0 |
| Taper Length (m) | |
| Lane Util. Factor | 1.00 |
| Ped Bike Factor | |
| Frt | |
| Flt Protected | |
| Satd. Flow (prot) | 0 |
| Flt Permitted | |
| Satd. Flow (perm) | 0 |
| Right Turn on Red | Yes |
| Satd. Flow (RTOR) | |
| Link Speed (k/h) | |
| Link Distance (m) | |
| Travel Time (s) | |
| Confl. Peds. (#/hr) | 13 |
| Confl. Bikes (#/hr) | |
| Peak Hour Factor | 1.00 |
| Heavy Vehicles (%) | 7% |
| Adj. Flow (vph) | 27 |
| Shared Lane Traffic (%) | |
| Lane Group Flow (vph) | 0 |
| Turn Type | |
| Protected Phases | |
| Permitted Phases | |
| Detector Phase | |
| Switch Phase | |
| Minimum Initial (s) | |
| Minimum Split (s) | |
| Total Split (s) | |
| Total Split (%) | |
| Maximum Green (s) | |
| Yellow Time (s) | |
| All-Red Time (s) | |
| Lost Time Adjust (s) | |
| Total Lost Time (s) | |
| Lead/Lag | |
| Lead-Lag Optimize? | |
| Vehicle Extension (s) | |
| Recall Mode | |
| Walk Time (s) | |
| Flash Dont Walk (s) | |
| Pedestrian Calls (#/hr) | |
| Act Effct Green (s) | |
| Actuated g/C Ratio | |

1: Iroquois Road & Carling Avenue
1995 Carling Avenue

Future (2024) Background Traffic
AM Peak Hour




| Lane Group | EBL | EBT | EBR | WBU | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT |
|------------------------|------|-------|------|-----|------|-------|------|-----|-------|-----|------|-------|
| v/c Ratio | 0.02 | 0.62 | 0.00 | | 0.12 | 0.16 | 0.08 | | 0.17 | | 0.30 | 0.11 |
| Control Delay | 8.3 | 12.3 | 0.0 | | 20.3 | 17.9 | 1.1 | | 23.3 | | 43.3 | 14.5 |
| Queue Delay | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 | | 0.0 | | 0.0 | 0.0 |
| Total Delay | 8.3 | 12.3 | 0.0 | | 20.3 | 17.9 | 1.1 | | 23.3 | | 43.3 | 14.5 |
| LOS | A | B | A | | C | B | A | | C | | D | B |
| Approach Delay | | 12.2 | | | | 15.8 | | | 23.3 | | | 34.3 |
| Approach LOS | | B | | | | B | | | C | | | C |
| Queue Length 50th (m) | 0.7 | 63.6 | 0.0 | | 2.3 | 18.6 | 0.0 | | 7.4 | | 18.2 | 1.6 |
| Queue Length 95th (m) | 5.0 | 187.8 | 0.0 | | 7.2 | 24.9 | 2.4 | | 15.4 | | 25.9 | 8.7 |
| Internal Link Dist (m) | | 281.5 | | | | 112.9 | | | 273.2 | | | 280.9 |
| Turn Bay Length (m) | 25.0 | | 40.0 | | 20.0 | | 85.0 | | | | 50.0 | |
| Base Capacity (vph) | 859 | 2618 | 1136 | | 138 | 2343 | 750 | | 553 | | 414 | 510 |
| Starvation Cap Reductn | 0 | 0 | 0 | | 0 | 0 | 0 | | 0 | | 0 | 0 |
| Spillback Cap Reductn | 0 | 0 | 0 | | 0 | 0 | 0 | | 0 | | 0 | 0 |
| Storage Cap Reductn | 0 | 0 | 0 | | 0 | 0 | 0 | | 0 | | 0 | 0 |
| Reduced v/c Ratio | 0.02 | 0.62 | 0.00 | | 0.12 | 0.16 | 0.08 | | 0.10 | | 0.18 | 0.07 |

Intersection Summary

| | |
|------------------------------------|---|
| Area Type: | Other |
| Cycle Length: | 130 |
| Actuated Cycle Length: | 130 |
| Offset: | 6 (5%), Referenced to phase 4:EBTL and 8:WBTL, Start of Green |
| Natural Cycle: | 100 |
| Control Type: | Actuated-Coordinated |
| Maximum v/c Ratio: | 0.62 |
| Intersection Signal Delay: | 14.3 |
| Intersection LOS: | B |
| Intersection Capacity Utilization: | 73.1% |
| ICU Level of Service: | D |
| Analysis Period (min): | 15 |

Splits and Phases: 1: Iroquois Road & Carling Avenue

























| | |
|------------------------|-----|
| Lane Group | SBR |
| v/c Ratio | |
| Control Delay | |
| Queue Delay | |
| Total Delay | |
| LOS | |
| Approach Delay | |
| Approach LOS | |
| Queue Length 50th (m) | |
| Queue Length 95th (m) | |
| Internal Link Dist (m) | |
| Turn Bay Length (m) | |
| Base Capacity (vph) | |
| Starvation Cap Reductn | |
| Spillback Cap Reductn | |
| Storage Cap Reductn | |
| Reduced v/c Ratio | |
| Intersection Summary | |

1: Iroquois Road & Carling Avenue
1995 Carling Avenue

Future (2024) Background Traffic (No U-Turn at Hare)

AM Peak Hour

| |  |  |  |  |  |  |  |  |  |  |  |  |
|-------------------------|---|---|---|---|---|---|--|---|---|---|---|---|
| Lane Group | EBU | EBL | EBT | EBR | WBU | WBL | WBT | WBR | NBL | NBT | NBR | SBL |
| Lane Configurations | |  |  |  | |  |  |  | |  | |  |
| Traffic Volume (vph) | 1 | 19 | 1629 | 5 | 25 | 7 | 374 | 60 | 3 | 24 | 30 | 75 |
| Future Volume (vph) | 1 | 19 | 1629 | 5 | 25 | 7 | 374 | 60 | 3 | 24 | 30 | 75 |
| Ideal Flow (vphpl) | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 |
| Storage Length (m) | | 25.0 | | 40.0 | | 20.0 | | 85.0 | 0.0 | | 0.0 | 50.0 |
| Storage Lanes | | 1 | | 1 | | 1 | | 1 | 0 | | 0 | 1 |
| Taper Length (m) | | 7.5 | | | | 7.5 | | | 7.5 | | | 7.5 |
| Lane Util. Factor | 0.95 | 1.00 | 0.95 | 1.00 | 0.91 | 1.00 | 0.91 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Ped Bike Factor | | 0.97 | | 0.94 | | | | 0.94 | | 0.99 | | 0.99 |
| Frt | | | | 0.850 | | | | 0.850 | | 0.929 | | |
| Flt Protected | | 0.950 | | | | 0.950 | | | | 0.997 | | 0.950 |
| Satd. Flow (prot) | 0 | 1729 | 3390 | 1547 | 0 | 1729 | 4687 | 1502 | 0 | 1635 | 0 | 1679 |
| Flt Permitted | | 0.479 | | | | 0.125 | | | | 0.990 | | 0.717 |
| Satd. Flow (perm) | 0 | 850 | 3390 | 1461 | 0 | 228 | 4687 | 1406 | 0 | 1623 | 0 | 1254 |
| Right Turn on Red | | | | Yes | | | | Yes | | | Yes | |
| Satd. Flow (RTOR) | | | | 95 | | | | 95 | | 30 | | |
| Link Speed (k/h) | | | 60 | | | | 60 | | | 50 | | |
| Link Distance (m) | | | 305.5 | | | | 136.9 | | | 297.2 | | |
| Travel Time (s) | | | 18.3 | | | | 8.2 | | | 21.4 | | |
| Confl. Peds. (#/hr) | | 15 | | 12 | | 12 | | 15 | 13 | | 12 | 12 |
| Confl. Bikes (#/hr) | | | | 1 | | | | 1 | | | 4 | |
| Peak Hour Factor | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Heavy Vehicles (%) | 0% | 0% | 2% | 0% | 0% | 0% | 6% | 3% | 0% | 4% | 0% | 3% |
| Adj. Flow (vph) | 1 | 19 | 1629 | 5 | 25 | 7 | 374 | 60 | 3 | 24 | 30 | 75 |
| Shared Lane Traffic (%) | | | | | | | | | | | | |
| Lane Group Flow (vph) | 0 | 20 | 1629 | 5 | 0 | 32 | 374 | 60 | 0 | 57 | 0 | 75 |
| Turn Type | pm+pt | pm+pt | NA | Perm | pm+pt | pm+pt | NA | Perm | Perm | NA | | Perm |
| Protected Phases | 7 | 7 | 4 | | 3 | 3 | 8 | | | 2 | | |
| Permitted Phases | 4 | 4 | | 4 | 8 | 8 | | 8 | 2 | | | 6 |
| Detector Phase | 7 | 7 | 4 | 4 | 3 | 3 | 8 | 8 | 2 | 2 | | 6 |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 10.0 | 10.0 | | 10.0 |
| Minimum Split (s) | 12.0 | 12.0 | 28.3 | 28.3 | 12.0 | 12.0 | 28.3 | 28.3 | 47.3 | 47.3 | | 47.3 |
| Total Split (s) | 14.0 | 14.0 | 69.0 | 69.0 | 14.0 | 14.0 | 69.0 | 69.0 | 47.0 | 47.0 | | 47.0 |
| Total Split (%) | 10.8% | 10.8% | 53.1% | 53.1% | 10.8% | 10.8% | 53.1% | 53.1% | 36.2% | 36.2% | | 36.2% |
| Maximum Green (s) | 7.0 | 7.0 | 62.7 | 62.7 | 7.0 | 7.0 | 62.7 | 62.7 | 39.7 | 39.7 | | 39.7 |
| Yellow Time (s) | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.3 | 3.3 | | 3.3 |
| All-Red Time (s) | 3.3 | 3.3 | 2.6 | 2.6 | 3.3 | 3.3 | 2.6 | 2.6 | 4.0 | 4.0 | | 4.0 |
| Lost Time Adjust (s) | | -3.0 | -2.3 | -2.3 | | | -3.0 | -2.3 | -2.3 | | -3.3 | -3.3 |
| Total Lost Time (s) | | 4.0 | 4.0 | 4.0 | | | 4.0 | 4.0 | 4.0 | | 4.0 | 4.0 |
| Lead/Lag | Lead | Lead | Lag | Lag | Lead | Lead | Lag | Lag | | | | |
| Lead-Lag Optimize? | Yes | Yes | Yes | Yes | Yes | Yes | Yes | Yes | | | | |
| Vehicle Extension (s) | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | | 3.0 |
| Recall Mode | Max | Max | C-Max | C-Max | None | None | C-Max | C-Max | None | None | | None |
| Walk Time (s) | | | 10.0 | 10.0 | | | 10.0 | 10.0 | 27.0 | 27.0 | | 27.0 |
| Flash Dont Walk (s) | | | 12.0 | 12.0 | | | 12.0 | 12.0 | 13.0 | 13.0 | | 13.0 |
| Pedestrian Calls (#/hr) | | | 12 | 12 | | | 15 | 15 | 12 | 12 | | 13 |
| Act Effct Green (s) | | 98.0 | 92.2 | 92.2 | | | 74.2 | 65.0 | 65.0 | 25.9 | | 25.9 |
| Actuated g/C Ratio | | 0.75 | 0.71 | 0.71 | | | 0.57 | 0.50 | 0.50 | 0.20 | | 0.20 |

1: Iroquois Road & Carling Avenue
1995 Carling Avenue

Future (2024) Background Traffic (No U-Turn at Hare)


AM Peak Hour



| Lane Group | SBT | SBR |
|-------------------------|-------|------|
| Lane Configurations | ↔ | |
| Traffic Volume (vph) | 7 | 27 |
| Future Volume (vph) | 7 | 27 |
| Ideal Flow (vphpl) | 1800 | 1800 |
| Storage Length (m) | | 0.0 |
| Storage Lanes | | 0 |
| Taper Length (m) | | |
| Lane Util. Factor | 1.00 | 1.00 |
| Ped Bike Factor | 0.98 | |
| Frt | 0.881 | |
| Flt Protected | | |
| Satd. Flow (prot) | 1490 | 0 |
| Flt Permitted | | |
| Satd. Flow (perm) | 1490 | 0 |
| Right Turn on Red | | Yes |
| Satd. Flow (RTOR) | 27 | |
| Link Speed (k/h) | 50 | |
| Link Distance (m) | 304.9 | |
| Travel Time (s) | 22.0 | |
| Confl. Peds. (#/hr) | | 13 |
| Confl. Bikes (#/hr) | | |
| Peak Hour Factor | 1.00 | 1.00 |
| Heavy Vehicles (%) | 0% | 7% |
| Adj. Flow (vph) | 7 | 27 |
| Shared Lane Traffic (%) | | |
| Lane Group Flow (vph) | 34 | 0 |
| Turn Type | NA | |
| Protected Phases | 6 | |
| Permitted Phases | | |
| Detector Phase | 6 | |
| Switch Phase | | |
| Minimum Initial (s) | 10.0 | |
| Minimum Split (s) | 47.3 | |
| Total Split (s) | 47.0 | |
| Total Split (%) | 36.2% | |
| Maximum Green (s) | 39.7 | |
| Yellow Time (s) | 3.3 | |
| All-Red Time (s) | 4.0 | |
| Lost Time Adjust (s) | -3.3 | |
| Total Lost Time (s) | 4.0 | |
| Lead/Lag | | |
| Lead-Lag Optimize? | | |
| Vehicle Extension (s) | 3.0 | |
| Recall Mode | None | |
| Walk Time (s) | 27.0 | |
| Flash Dont Walk (s) | 13.0 | |
| Pedestrian Calls (#/hr) | 13 | |
| Act Effct Green (s) | 25.9 | |
| Actuated g/C Ratio | 0.20 | |

1: Iroquois Road & Carling Avenue
1995 Carling Avenue

Future (2024) Background Traffic (No U-Turn at Hare)
AM Peak Hour




| Lane Group | EBU | EBL | EBT | EBR | WBU | WBL | WBT | WBR | NBL | NBT | NBR | SBL |
|------------------------|-----|------|--------|------|-----|------|-------|------|-----|-------|-----|------|
| v/c Ratio | | 0.02 | 0.68 | 0.00 | | 0.14 | 0.16 | 0.08 | | 0.16 | | 0.30 |
| Control Delay | | 8.3 | 19.6 | 0.0 | | 10.6 | 17.9 | 1.1 | | 20.4 | | 43.3 |
| Queue Delay | | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 | | 0.0 | | 0.0 |
| Total Delay | | 8.3 | 19.6 | 0.0 | | 10.6 | 17.9 | 1.1 | | 20.4 | | 43.3 |
| LOS | | A | B | A | | B | B | A | | C | | D |
| Approach Delay | | | 19.4 | | | | 15.2 | | | 20.4 | | |
| Approach LOS | | | B | | | | B | | | C | | |
| Queue Length 50th (m) | | 0.8 | 108.5 | 0.0 | | 1.8 | 18.5 | 0.0 | | 6.2 | | 18.2 |
| Queue Length 95th (m) | | 5.2 | #261.2 | 0.0 | | 7.2 | 24.7 | 2.4 | | 14.4 | | 25.9 |
| Internal Link Dist (m) | | | 281.5 | | | | 112.9 | | | 273.2 | | |
| Turn Bay Length (m) | | 25.0 | | 40.0 | | 20.0 | | 85.0 | | | | 50.0 |
| Base Capacity (vph) | | 847 | 2405 | 1064 | | 247 | 2343 | 750 | | 556 | | 414 |
| Starvation Cap Reductn | | 0 | 0 | 0 | | 0 | 0 | 0 | | 0 | | 0 |
| Spillback Cap Reductn | | 0 | 0 | 0 | | 0 | 0 | 0 | | 0 | | 0 |
| Storage Cap Reductn | | 0 | 0 | 0 | | 0 | 0 | 0 | | 0 | | 0 |
| Reduced v/c Ratio | | 0.02 | 0.68 | 0.00 | | 0.13 | 0.16 | 0.08 | | 0.10 | | 0.18 |

Intersection Summary

Area Type: Other
 Cycle Length: 130
 Actuated Cycle Length: 130
 Offset: 6 (5%), Referenced to phase 4:EBTL and 8:WBTL, Start of Green
 Natural Cycle: 120
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.68
 Intersection Signal Delay: 19.3 Intersection LOS: B
 Intersection Capacity Utilization 73.1% ICU Level of Service D
 Analysis Period (min) 15
 # 95th percentile volume exceeds capacity, queue may be longer.
 Queue shown is maximum after two cycles.

Splits and Phases: 1: Iroquois Road & Carling Avenue





| Lane Group | SBT | SBR |
|-----------------------------|-------|-----|
| v/c Ratio | 0.11 | |
| Control Delay | 14.5 | |
| Queue Delay | 0.0 | |
| Total Delay | 14.5 | |
| LOS | B | |
| Approach Delay | 34.3 | |
| Approach LOS | C | |
| Queue Length 50th (m) | 1.6 | |
| Queue Length 95th (m) | 8.7 | |
| Internal Link Dist (m) | 280.9 | |
| Turn Bay Length (m) | | |
| Base Capacity (vph) | 510 | |
| Starvation Cap Reductn | 0 | |
| Spillback Cap Reductn | 0 | |
| Storage Cap Reductn | 0 | |
| Reduced v/c Ratio | 0.07 | |
| Intersection Summary | | |

2: Hare Avenue & Carling Avenue
1995 Carling Avenue

Future (2024) Background Traffic
AM Peak Hour

| Intersection | | | | | | | | |
|--------------------------|------|------|------|------|------|------|------|------|
| Int Delay, s/veh | 0.9 | | | | | | | |
| Movement | EBU | EBT | EBR | WBU | WBL | WBT | NBL | NBR |
| Lane Configurations | | ↑↑ | ↑ | | ↓ | ↑↑ | ↓ | |
| Traffic Vol, veh/h | 1 | 1735 | 7 | 15 | 13 | 443 | 7 | 15 |
| Future Vol, veh/h | 1 | 1735 | 7 | 15 | 13 | 443 | 7 | 15 |
| Conflicting Peds, #/hr | 0 | 0 | 2 | 0 | 2 | 0 | 2 | 0 |
| Sign Control | Free | Free | Free | Free | Free | Free | Stop | Stop |
| RT Channelized | - | - | None | - | - | None | - | None |
| Storage Length | - | - | 350 | - | 250 | - | 0 | - |
| Veh in Median Storage, # | - | 0 | - | - | - | 0 | 0 | - |
| Grade, % | - | 0 | - | - | - | 0 | 0 | - |
| Peak Hour Factor | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| Heavy Vehicles, % | 0 | 0 | 14 | 0 | 0 | 0 | 0 | 7 |
| Mvmt Flow | 1 | 1735 | 7 | 15 | 13 | 443 | 7 | 15 |

| Major/Minor | Major1 | | Major2 | | Minor1 | | | |
|----------------------|--------|---|--------|------|--------|---|------|------|
| Conflicting Flow All | 443 | 0 | 0 | 1735 | 1744 | 0 | 2019 | 870 |
| Stage 1 | - | - | - | - | - | - | 1739 | - |
| Stage 2 | - | - | - | - | - | - | 280 | - |
| Critical Hdwy | 6.4 | - | - | 6.4 | 4.1 | - | 6.8 | 7.04 |
| Critical Hdwy Stg 1 | - | - | - | - | - | - | 5.8 | - |
| Critical Hdwy Stg 2 | - | - | - | - | - | - | 5.8 | - |
| Follow-up Hdwy | 2.5 | - | - | 2.5 | 2.2 | - | 3.5 | 3.37 |
| Pot Cap-1 Maneuver | 761 | - | - | 113 | 365 | - | 52 | 285 |
| Stage 1 | - | - | - | - | - | - | 129 | - |
| Stage 2 | - | - | - | - | - | - | 748 | - |
| Platoon blocked, % | | - | - | | | | | |
| Mov Cap-1 Maneuver | 761 | - | - | 159 | 159 | - | 41 | 284 |
| Mov Cap-2 Maneuver | - | - | - | - | - | - | 41 | - |
| Stage 1 | - | - | - | - | - | - | 123 | - |
| Stage 2 | - | - | - | - | - | - | 615 | - |

| Approach | EB | WB | NB |
|----------------------|----|-----|------|
| HCM Control Delay, s | 0 | 1.9 | 52.1 |
| HCM LOS | | | F |

| Minor Lane/Major Mvmt | NBLn1 | EBT | EBR | WBL | WBT |
|-----------------------|-------|-----|-----|-------|-----|
| Capacity (veh/h) | 98 | - | - | 159 | - |
| HCM Lane V/C Ratio | 0.224 | - | - | 0.176 | - |
| HCM Control Delay (s) | 52.1 | - | - | 32.4 | - |
| HCM Lane LOS | F | - | - | D | - |
| HCM 95th %tile Q(veh) | 0.8 | - | - | 0.6 | - |

2: Hare Avenue & Carling Avenue
1995 Carling Avenue

Future (2024) Background Traffic (No U-Turn at Hare)

AM Peak Hour

| Intersection | | | | | | |
|--------------------------|------|------|------|------|------|------|
| Int Delay, s/veh | 0.5 | | | | | |
| Movement | EBT | EBR | WBL | WBT | NBL | NBR |
| Lane Configurations | ↑↑ | ↑ | ↓ | ↑↑ | ↑↓ | |
| Traffic Vol, veh/h | 1750 | 7 | 13 | 458 | 7 | 15 |
| Future Vol, veh/h | 1750 | 7 | 13 | 458 | 7 | 15 |
| Conflicting Peds, #/hr | 0 | 2 | 2 | 0 | 2 | 0 |
| Sign Control | Free | Free | Free | Free | Stop | Stop |
| RT Channelized | - | None | - | None | - | None |
| Storage Length | - | 350 | 250 | - | 0 | - |
| Veh in Median Storage, # | 0 | - | - | 0 | 0 | - |
| Grade, % | 0 | - | - | 0 | 0 | - |
| Peak Hour Factor | 100 | 100 | 100 | 100 | 100 | 100 |
| Heavy Vehicles, % | 0 | 14 | 0 | 0 | 0 | 7 |
| Mvmt Flow | 1750 | 7 | 13 | 458 | 7 | 15 |

| Major/Minor | Major1 | | Major2 | | Minor1 | |
|----------------------|--------|---|--------|---|--------|------|
| Conflicting Flow All | 0 | 0 | 1759 | 0 | 2009 | 877 |
| Stage 1 | - | - | - | - | 1752 | - |
| Stage 2 | - | - | - | - | 257 | - |
| Critical Hdwy | - | - | 4.1 | - | 6.8 | 7.04 |
| Critical Hdwy Stg 1 | - | - | - | - | 5.8 | - |
| Critical Hdwy Stg 2 | - | - | - | - | 5.8 | - |
| Follow-up Hdwy | - | - | 2.2 | - | 3.5 | 3.37 |
| Pot Cap-1 Maneuver | - | - | 360 | - | 53 | 282 |
| Stage 1 | - | - | - | - | 127 | - |
| Stage 2 | - | - | - | - | 768 | - |
| Platoon blocked, % | - | - | - | - | - | - |
| Mov Cap-1 Maneuver | - | - | 359 | - | 51 | 281 |
| Mov Cap-2 Maneuver | - | - | - | - | 51 | - |
| Stage 1 | - | - | - | - | 127 | - |
| Stage 2 | - | - | - | - | 739 | - |

| Approach | EB | WB | NB |
|----------------------|----|-----|------|
| HCM Control Delay, s | 0 | 0.4 | 43.6 |
| HCM LOS | | | E |

| Minor Lane/Major Mvmt | NBLn1 | EBT | EBR | WBL | WBT |
|-----------------------|-------|-----|-----|-------|-----|
| Capacity (veh/h) | 115 | - | - | 359 | - |
| HCM Lane V/C Ratio | 0.191 | - | - | 0.036 | - |
| HCM Control Delay (s) | 43.6 | - | - | 15.4 | - |
| HCM Lane LOS | E | - | - | C | - |
| HCM 95th %tile Q(veh) | 0.7 | - | - | 0.1 | - |

3: Carling Avenue & Bromley Road
1995 Carling Avenue

Future (2024) Background Traffic
AM Peak Hour

| Intersection | | | | | | |
|--------------------------|------|------|------|------|------|------|
| Int Delay, s/veh | 0.1 | | | | | |
| Movement | EBL | EBT | WBT | WBR | SBL | SBR |
| Lane Configurations | | ↑↑ | ↑↑ | ↑ | | ↑ |
| Traffic Vol, veh/h | 0 | 1764 | 457 | 5 | 0 | 13 |
| Future Vol, veh/h | 0 | 1764 | 457 | 5 | 0 | 13 |
| Conflicting Peds, #/hr | 8 | 0 | 0 | 8 | 0 | 0 |
| Sign Control | Free | Free | Free | Free | Stop | Stop |
| RT Channelized | - | None | - | None | - | None |
| Storage Length | - | - | - | 300 | - | 0 |
| Veh in Median Storage, # | - | 0 | 0 | - | 0 | - |
| Grade, % | - | 0 | 0 | - | 0 | - |
| Peak Hour Factor | 100 | 100 | 100 | 100 | 100 | 100 |
| Heavy Vehicles, % | 0 | 0 | 0 | 0 | 0 | 0 |
| Mvmt Flow | 0 | 1764 | 457 | 5 | 0 | 13 |





















| Major/Minor | Major1 | Major2 | Minor2 | | |
|----------------------|--------|--------|--------|---|-------|
| Conflicting Flow All | - | 0 | - | 0 | 237 |
| Stage 1 | - | - | - | - | - |
| Stage 2 | - | - | - | - | - |
| Critical Hdwy | - | - | - | - | 6.9 |
| Critical Hdwy Stg 1 | - | - | - | - | - |
| Critical Hdwy Stg 2 | - | - | - | - | - |
| Follow-up Hdwy | - | - | - | - | 3.3 |
| Pot Cap-1 Maneuver | 0 | - | - | - | 0 771 |
| Stage 1 | 0 | - | - | - | 0 - |
| Stage 2 | 0 | - | - | - | 0 - |
| Platoon blocked, % | - | - | - | - | - |
| Mov Cap-1 Maneuver | - | - | - | - | 765 |
| Mov Cap-2 Maneuver | - | - | - | - | - |
| Stage 1 | - | - | - | - | - |
| Stage 2 | - | - | - | - | - |

| Approach | EB | WB | SB |
|----------------------|----|----|-----|
| HCM Control Delay, s | 0 | 0 | 9.8 |
| HCM LOS | | | A |

| Minor Lane/Major Mvmt | EBT | WBT | WBR | SBLn1 |
|-----------------------|-----|-----|-----|-------|
| Capacity (veh/h) | - | - | - | 765 |
| HCM Lane V/C Ratio | - | - | - | 0.017 |
| HCM Control Delay (s) | - | - | - | 9.8 |
| HCM Lane LOS | - | - | - | A |
| HCM 95th %tile Q(veh) | - | - | - | 0.1 |

4: Maitland Avenue/Sherbourne Road & Carling Avenue
1995 Carling Avenue

Future (2024) Background Traffic
AM Peak Hour

| |  |  |  |  |  |  |  |  |  |  |  |  |
|-------------------------|---|---|---|---|---|---|--|---|---|---|---|---|
| Lane Group | EBU | EBL | EBT | EBR | WBU | WBL | WBT | WBR | NBL | NBT | NBR | SBL |
| Lane Configurations | |  |  |  | |  |  | |  |  | |  |
| Traffic Volume (vph) | 16 | 29 | 1459 | 260 | 6 | 302 | 298 | 16 | 131 | 99 | 406 | 68 |
| Future Volume (vph) | 16 | 29 | 1459 | 260 | 6 | 302 | 298 | 16 | 131 | 99 | 406 | 68 |
| Ideal Flow (vphpl) | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 |
| Storage Length (m) | | 55.0 | | 130.0 | | 115.0 | | 0.0 | 75.0 | | 0.0 | 45.0 |
| Storage Lanes | | 1 | | 1 | | 2 | | 0 | 1 | | 0 | 1 |
| Taper Length (m) | | 7.5 | | | | 7.5 | | | 7.5 | | | 7.5 |
| Lane Util. Factor | 0.95 | 1.00 | 0.95 | 1.00 | 0.95 | 0.97 | 0.95 | 0.95 | 1.00 | 1.00 | 1.00 | 1.00 |
| Ped Bike Factor | | 0.95 | | 0.96 | | 0.99 | 0.99 | | 0.99 | 0.97 | | |
| Frt | | | | 0.850 | | | 0.992 | | | 0.879 | | |
| Flt Protected | | 0.950 | | | | 0.950 | | | 0.950 | | | 0.950 |
| Satd. Flow (prot) | 0 | 1654 | 3390 | 1532 | 0 | 3228 | 3229 | 0 | 1679 | 1506 | 0 | 1679 |
| Flt Permitted | | 0.950 | | | | 0.950 | | | 0.351 | | | 0.134 |
| Satd. Flow (perm) | 0 | 1565 | 3390 | 1465 | 0 | 3205 | 3229 | 0 | 614 | 1506 | 0 | 237 |
| Right Turn on Red | | | | Yes | | | | Yes | | | Yes | |
| Satd. Flow (RTOR) | | | | 242 | | | 6 | | | 90 | | |
| Link Speed (k/h) | | | 60 | | | | 60 | | | 50 | | |
| Link Distance (m) | | | 447.3 | | | | 309.6 | | | 300.2 | | |
| Travel Time (s) | | | 26.8 | | | | 18.6 | | | 21.6 | | |
| Confl. Peds. (#/hr) | | 25 | | 16 | | 16 | | 25 | 13 | | 15 | 15 |
| Confl. Bikes (#/hr) | | | | | | | | 1 | | | 2 | |
| Peak Hour Factor | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Heavy Vehicles (%) | 0% | 7% | 2% | 1% | 0% | 4% | 6% | 0% | 3% | 5% | 2% | 3% |
| Adj. Flow (vph) | 16 | 29 | 1459 | 260 | 6 | 302 | 298 | 16 | 131 | 99 | 406 | 68 |
| Shared Lane Traffic (%) | | | | | | | | | | | | |
| Lane Group Flow (vph) | 0 | 45 | 1459 | 260 | 0 | 308 | 314 | 0 | 131 | 505 | 0 | 68 |
| Turn Type | Prot | Prot | NA | Perm | Prot | Prot | NA | | Perm | NA | | Perm |
| Protected Phases | 7 | 7 | 4 | | 3 | 3 | 8 | | | 2 | | |
| Permitted Phases | | | | 4 | | | | | 2 | | | 6 |
| Detector Phase | 7 | 7 | 4 | 4 | 3 | 3 | 8 | | 2 | 2 | | 6 |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | | 10.0 | 10.0 | | 10.0 |
| Minimum Split (s) | 10.9 | 10.9 | 23.9 | 23.9 | 10.9 | 10.9 | 23.9 | | 24.8 | 24.8 | | 24.8 |
| Total Split (s) | 13.2 | 13.2 | 59.0 | 59.0 | 17.0 | 17.0 | 62.8 | | 44.0 | 44.0 | | 44.0 |
| Total Split (%) | 11.0% | 11.0% | 49.2% | 49.2% | 14.2% | 14.2% | 52.3% | | 36.7% | 36.7% | | 36.7% |
| Maximum Green (s) | 7.3 | 7.3 | 53.1 | 53.1 | 11.1 | 11.1 | 56.9 | | 37.2 | 37.2 | | 37.2 |
| Yellow Time (s) | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | | 3.3 | 3.3 | | 3.3 |
| All-Red Time (s) | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | | 3.5 | 3.5 | | 3.5 |
| Lost Time Adjust (s) | | -1.9 | -1.9 | -1.9 | | -1.9 | -1.9 | | -2.8 | -2.8 | | -2.8 |
| Total Lost Time (s) | | 4.0 | 4.0 | 4.0 | | 4.0 | 4.0 | | 4.0 | 4.0 | | 4.0 |
| Lead/Lag | Lead | Lead | Lag | Lag | Lead | Lead | Lag | | | | | |
| Lead-Lag Optimize? | Yes | Yes | Yes | Yes | Yes | Yes | Yes | | | | | |
| Vehicle Extension (s) | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | | 3.0 | 3.0 | | 3.0 |
| Recall Mode | None | None | C-Max | C-Max | None | None | C-Max | | None | None | | None |
| Walk Time (s) | | | 7.0 | 7.0 | | | 7.0 | | 7.0 | 7.0 | | 7.0 |
| Flash Dont Walk (s) | | | 11.0 | 11.0 | | | 11.0 | | 11.0 | 11.0 | | 11.0 |
| Pedestrian Calls (#/hr) | | | 16 | 16 | | | 25 | | 15 | 15 | | 13 |
| Act Effct Green (s) | | 8.8 | 56.0 | 56.0 | | 13.4 | 62.9 | | 38.6 | 38.6 | | 38.6 |
| Actuated g/C Ratio | | 0.07 | 0.47 | 0.47 | | 0.11 | 0.52 | | 0.32 | 0.32 | | 0.32 |

4: Maitland Avenue/Sherbourne Road & Carling Avenue
1995 Carling Avenue


Future (2024) Background Traffic
AM Peak Hour



| Lane Group | SBT | SBR |
|-------------------------|-------|------|
| Lane Configurations | ↔ | |
| Traffic Volume (vph) | 316 | 16 |
| Future Volume (vph) | 316 | 16 |
| Ideal Flow (vphpl) | 1800 | 1800 |
| Storage Length (m) | | 0.0 |
| Storage Lanes | | 0 |
| Taper Length (m) | | |
| Lane Util. Factor | 1.00 | 1.00 |
| Ped Bike Factor | 1.00 | |
| Frt | 0.993 | |
| Flt Protected | | |
| Satd. Flow (prot) | 1765 | 0 |
| Flt Permitted | | |
| Satd. Flow (perm) | 1765 | 0 |
| Right Turn on Red | | Yes |
| Satd. Flow (RTOR) | 2 | |
| Link Speed (k/h) | 50 | |
| Link Distance (m) | 301.0 | |
| Travel Time (s) | 21.7 | |
| Confl. Peds. (#/hr) | | 13 |
| Confl. Bikes (#/hr) | | |
| Peak Hour Factor | 1.00 | 1.00 |
| Heavy Vehicles (%) | 2% | 6% |
| Adj. Flow (vph) | 316 | 16 |
| Shared Lane Traffic (%) | | |
| Lane Group Flow (vph) | 332 | 0 |
| Turn Type | NA | |
| Protected Phases | 6 | |
| Permitted Phases | | |
| Detector Phase | 6 | |
| Switch Phase | | |
| Minimum Initial (s) | 10.0 | |
| Minimum Split (s) | 24.8 | |
| Total Split (s) | 44.0 | |
| Total Split (%) | 36.7% | |
| Maximum Green (s) | 37.2 | |
| Yellow Time (s) | 3.3 | |
| All-Red Time (s) | 3.5 | |
| Lost Time Adjust (s) | -2.8 | |
| Total Lost Time (s) | 4.0 | |
| Lead/Lag | | |
| Lead-Lag Optimize? | | |
| Vehicle Extension (s) | 3.0 | |
| Recall Mode | None | |
| Walk Time (s) | 7.0 | |
| Flash Dont Walk (s) | 11.0 | |
| Pedestrian Calls (#/hr) | 13 | |
| Act Effct Green (s) | 38.6 | |
| Actuated g/C Ratio | 0.32 | |

4: Maitland Avenue/Sherbourne Road & Carling Avenue
1995 Carling Avenue

Future (2024) Background Traffic
AM Peak Hour




| Lane Group | EBU | EBL | EBT | EBR | WBU | WBL | WBT | WBR | NBL | NBT | NBR | SBL |
|------------------------|-----|------|--------|-------|-----|-------|-------|-----|-------|--------|-----|-------|
| v/c Ratio | | 0.37 | 0.92 | 0.32 | | 0.85 | 0.19 | | 0.66 | 0.93 | | 0.89 |
| Control Delay | | 61.8 | 41.2 | 4.2 | | 74.7 | 16.2 | | 52.8 | 56.6 | | 118.7 |
| Queue Delay | | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 |
| Total Delay | | 61.8 | 41.2 | 4.2 | | 74.7 | 16.2 | | 52.8 | 56.6 | | 118.7 |
| LOS | | E | D | A | | E | B | | D | E | | F |
| Approach Delay | | | 36.3 | | | | 45.2 | | | 55.8 | | |
| Approach LOS | | | D | | | | D | | | E | | |
| Queue Length 50th (m) | | 10.2 | 168.0 | 2.3 | | 37.4 | 20.8 | | 26.0 | 95.9 | | 14.9 |
| Queue Length 95th (m) | | 22.3 | #218.2 | 16.7 | | #61.6 | 29.6 | | #53.3 | #159.4 | | #43.4 |
| Internal Link Dist (m) | | | 423.3 | | | | 285.6 | | | 276.2 | | |
| Turn Bay Length (m) | | 55.0 | | 130.0 | | 115.0 | | | 75.0 | | | 45.0 |
| Base Capacity (vph) | | 126 | 1581 | 812 | | 361 | 1694 | | 204 | 562 | | 79 |
| Starvation Cap Reductn | | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | | 0 |
| Spillback Cap Reductn | | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | | 0 |
| Storage Cap Reductn | | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | | 0 |
| Reduced v/c Ratio | | 0.36 | 0.92 | 0.32 | | 0.85 | 0.19 | | 0.64 | 0.90 | | 0.86 |

Intersection Summary

Area Type: Other
 Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 40 (33%), Referenced to phase 4:EBT and 8:WBT, Start of Green
 Natural Cycle: 80
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.93
 Intersection Signal Delay: 43.4
 Intersection LOS: D
 Intersection Capacity Utilization 106.6%
 ICU Level of Service G
 Analysis Period (min) 15
 # 95th percentile volume exceeds capacity, queue may be longer.
 Queue shown is maximum after two cycles.

Splits and Phases: 4: Maitland Avenue/Sherbourne Road & Carling Avenue






| Lane Group | SBT | SBR |
|------------------------|-------|-----|
| v/c Ratio | 0.58 | |
| Control Delay | 38.3 | |
| Queue Delay | 0.0 | |
| Total Delay | 38.3 | |
| LOS | D | |
| Approach Delay | 51.9 | |
| Approach LOS | D | |
| Queue Length 50th (m) | 63.5 | |
| Queue Length 95th (m) | 92.8 | |
| Internal Link Dist (m) | 277.0 | |
| Turn Bay Length (m) | | |
| Base Capacity (vph) | 589 | |
| Starvation Cap Reductn | 0 | |
| Spillback Cap Reductn | 0 | |
| Storage Cap Reductn | 0 | |
| Reduced v/c Ratio | 0.56 | |
| Intersection Summary | | |

1: Iroquois Road & Carling Avenue
1995 Carling Avenue

Future (2024) Background Traffic
PM Peak Hour



| Lane Group | EBU | EBL | EBT | EBR | WBU | WBL | WBT | WBR | NBL | NBT | NBR | SBL |
|-------------------------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|------|-------|
| Lane Configurations | | | | | | | | | | | | |
| Traffic Volume (vph) | 1 | 41 | 689 | 4 | 6 | 17 | 1449 | 107 | 13 | 20 | 10 | 117 |
| Future Volume (vph) | 1 | 41 | 689 | 4 | 6 | 17 | 1449 | 107 | 13 | 20 | 10 | 117 |
| Ideal Flow (vphpl) | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 |
| Storage Length (m) | | 25.0 | | 40.0 | | 20.0 | | 85.0 | 0.0 | | 0.0 | 50.0 |
| Storage Lanes | | 1 | | 1 | | 1 | | 1 | 0 | | 0 | 1 |
| Taper Length (m) | | 7.5 | | | | 7.5 | | | 7.5 | | | 7.5 |
| Lane Util. Factor | 0.95 | 1.00 | 0.95 | 1.00 | 0.91 | 1.00 | 0.91 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Ped Bike Factor | | | | 0.92 | | 0.98 | | 0.90 | | 0.99 | | 0.98 |
| Frt | | | | 0.850 | | | | 0.850 | | 0.969 | | |
| Flt Protected | | 0.950 | | | | 0.950 | | | | 0.985 | | 0.950 |
| Satd. Flow (prot) | 0 | 1729 | 3390 | 1547 | 0 | 1656 | 4919 | 1547 | 0 | 1726 | 0 | 1712 |
| Flt Permitted | | 0.108 | | | | 0.390 | | | | 0.921 | | 0.761 |
| Satd. Flow (perm) | 0 | 197 | 3390 | 1426 | 0 | 665 | 4919 | 1391 | 0 | 1602 | 0 | 1350 |
| Right Turn on Red | | | | Yes | | | | Yes | | | Yes | |
| Satd. Flow (RTOR) | | | | 36 | | | | 107 | | 10 | | |
| Link Speed (k/h) | | | 60 | | | | 60 | | | 50 | | |
| Link Distance (m) | | | 305.5 | | | | 137.5 | | | 297.2 | | |
| Travel Time (s) | | | 18.3 | | | | 8.3 | | | 21.4 | | |
| Confl. Peds. (#/hr) | | 28 | | 19 | | 19 | | 28 | 28 | | 17 | 17 |
| Confl. Bikes (#/hr) | | | | 6 | | | | | | | | |
| Peak Hour Factor | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Heavy Vehicles (%) | 0% | 0% | 2% | 0% | 0% | 6% | 1% | 0% | 0% | 0% | 0% | 1% |
| Adj. Flow (vph) | 1 | 41 | 689 | 4 | 6 | 17 | 1449 | 107 | 13 | 20 | 10 | 117 |
| Shared Lane Traffic (%) | | | | | | | | | | | | |
| Lane Group Flow (vph) | 0 | 42 | 689 | 4 | 0 | 23 | 1449 | 107 | 0 | 43 | 0 | 117 |
| Turn Type | pm+pt | pm+pt | NA | Perm | Perm | Perm | NA | Perm | Perm | NA | | Perm |
| Protected Phases | 7 | 7 | 4 | | | | 8 | | | 2 | | |
| Permitted Phases | 4 | 4 | | 4 | 8 | 8 | | 8 | 2 | | | 6 |
| Detector Phase | 7 | 7 | 4 | 4 | 8 | 8 | 8 | 8 | 2 | 2 | | 6 |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 10.0 | 10.0 | | 10.0 |
| Minimum Split (s) | 12.0 | 12.0 | 28.3 | 28.3 | 28.3 | 28.3 | 28.3 | 28.3 | 47.3 | 47.3 | | 47.3 |
| Total Split (s) | 12.0 | 12.0 | 83.0 | 83.0 | 71.0 | 71.0 | 71.0 | 71.0 | 47.0 | 47.0 | | 47.0 |
| Total Split (%) | 9.2% | 9.2% | 63.8% | 63.8% | 54.6% | 54.6% | 54.6% | 54.6% | 36.2% | 36.2% | | 36.2% |
| Maximum Green (s) | 5.0 | 5.0 | 76.7 | 76.7 | 64.7 | 64.7 | 64.7 | 64.7 | 39.7 | 39.7 | | 39.7 |
| Yellow Time (s) | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.3 | 3.3 | | 3.3 |
| All-Red Time (s) | 3.3 | 3.3 | 2.6 | 2.6 | 2.6 | 2.6 | 2.6 | 2.6 | 4.0 | 4.0 | | 4.0 |
| Lost Time Adjust (s) | | -3.0 | -2.3 | -2.3 | | -2.3 | -2.3 | -2.3 | | -3.3 | | -3.3 |
| Total Lost Time (s) | | 4.0 | 4.0 | 4.0 | | 4.0 | 4.0 | 4.0 | | 4.0 | | 4.0 |
| Lead/Lag | Lead | Lead | | | Lag | Lag | Lag | Lag | | | | |
| Lead-Lag Optimize? | Yes | Yes | | | Yes | Yes | Yes | Yes | | | | |
| Vehicle Extension (s) | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | | 3.0 |
| Recall Mode | Max | Max | C-Max | C-Max | C-Max | C-Max | C-Max | C-Max | None | None | | None |
| Walk Time (s) | | | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 27.0 | 27.0 | | 27.0 |
| Flash Dont Walk (s) | | | 12.0 | 12.0 | 12.0 | 12.0 | 12.0 | 12.0 | 13.0 | 13.0 | | 13.0 |
| Pedestrian Calls (#/hr) | | | 19 | 19 | 28 | 28 | 28 | 28 | 17 | 17 | | 28 |
| Act Effct Green (s) | | 90.1 | 90.1 | 90.1 | | 67.0 | 67.0 | 67.0 | | 31.9 | | 31.9 |
| Actuated g/C Ratio | | 0.69 | 0.69 | 0.69 | | 0.52 | 0.52 | 0.52 | | 0.25 | | 0.25 |

1: Iroquois Road & Carling Avenue
 1995 Carling Avenue


Future (2024) Background Traffic
 PM Peak Hour



| Lane Group | SBT | SBR |
|-------------------------|-------|------|
| Lane Configurations | ↔ | |
| Traffic Volume (vph) | 23 | 60 |
| Future Volume (vph) | 23 | 60 |
| Ideal Flow (vphpl) | 1800 | 1800 |
| Storage Length (m) | | 0.0 |
| Storage Lanes | | 0 |
| Taper Length (m) | | |
| Lane Util. Factor | 1.00 | 1.00 |
| Ped Bike Factor | 0.97 | |
| Frt | 0.892 | |
| Flt Protected | | |
| Satd. Flow (prot) | 1554 | 0 |
| Flt Permitted | | |
| Satd. Flow (perm) | 1554 | 0 |
| Right Turn on Red | | Yes |
| Satd. Flow (RTOR) | 30 | |
| Link Speed (k/h) | 50 | |
| Link Distance (m) | 304.9 | |
| Travel Time (s) | 22.0 | |
| Confl. Peds. (#/hr) | | 28 |
| Confl. Bikes (#/hr) | | 2 |
| Peak Hour Factor | 1.00 | 1.00 |
| Heavy Vehicles (%) | 0% | 2% |
| Adj. Flow (vph) | 23 | 60 |
| Shared Lane Traffic (%) | | |
| Lane Group Flow (vph) | 83 | 0 |
| Turn Type | NA | |
| Protected Phases | 6 | |
| Permitted Phases | | |
| Detector Phase | 6 | |
| Switch Phase | | |
| Minimum Initial (s) | 10.0 | |
| Minimum Split (s) | 47.3 | |
| Total Split (s) | 47.0 | |
| Total Split (%) | 36.2% | |
| Maximum Green (s) | 39.7 | |
| Yellow Time (s) | 3.3 | |
| All-Red Time (s) | 4.0 | |
| Lost Time Adjust (s) | -3.3 | |
| Total Lost Time (s) | 4.0 | |
| Lead/Lag | | |
| Lead-Lag Optimize? | | |
| Vehicle Extension (s) | 3.0 | |
| Recall Mode | None | |
| Walk Time (s) | 27.0 | |
| Flash Dont Walk (s) | 13.0 | |
| Pedestrian Calls (#/hr) | 28 | |
| Act Effct Green (s) | 31.9 | |
| Actuated g/C Ratio | 0.25 | |

1: Iroquois Road & Carling Avenue
1995 Carling Avenue

Future (2024) Background Traffic
PM Peak Hour




| Lane Group | EBU | EBL | EBT | EBR | WBU | WBL | WBT | WBR | NBL | NBT | NBR | SBL |
|------------------------|-----|------|-------|------|-----|------|-------|------|-----|-------|-----|------|
| v/c Ratio | | 0.12 | 0.29 | 0.00 | | 0.07 | 0.57 | 0.14 | | 0.11 | | 0.35 |
| Control Delay | | 10.1 | 9.9 | 0.0 | | 16.6 | 22.8 | 3.3 | | 26.5 | | 40.4 |
| Queue Delay | | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 | | 0.0 | | 0.0 |
| Total Delay | | 10.1 | 9.9 | 0.0 | | 16.6 | 22.8 | 3.3 | | 26.5 | | 40.4 |
| LOS | | B | A | A | | B | C | A | | C | | D |
| Approach Delay | | | 9.8 | | | | 21.4 | | | 26.5 | | |
| Approach LOS | | | A | | | | C | | | C | | |
| Queue Length 50th (m) | | 4.1 | 43.3 | 0.0 | | 2.9 | 90.5 | 0.0 | | 5.8 | | 21.9 |
| Queue Length 95th (m) | | 8.8 | 54.4 | 0.0 | | 7.8 | 104.5 | 8.9 | | 14.4 | | 37.8 |
| Internal Link Dist (m) | | | 281.5 | | | | 113.5 | | | 273.2 | | |
| Turn Bay Length (m) | | 25.0 | | 40.0 | | 20.0 | | 85.0 | | | | 50.0 |
| Base Capacity (vph) | | 361 | 2350 | 999 | | 342 | 2535 | 768 | | 536 | | 446 |
| Starvation Cap Reductn | | 0 | 0 | 0 | | 0 | 0 | 0 | | 0 | | 0 |
| Spillback Cap Reductn | | 0 | 0 | 0 | | 0 | 0 | 0 | | 0 | | 0 |
| Storage Cap Reductn | | 0 | 0 | 0 | | 0 | 0 | 0 | | 0 | | 0 |
| Reduced v/c Ratio | | 0.12 | 0.29 | 0.00 | | 0.07 | 0.57 | 0.14 | | 0.08 | | 0.26 |

Intersection Summary

| | |
|------------------------------------|---|
| Area Type: | Other |
| Cycle Length: | 130 |
| Actuated Cycle Length: | 130 |
| Offset: | 95 (73%), Referenced to phase 4:EBTL and 8:WBTL, Start of Green |
| Natural Cycle: | 90 |
| Control Type: | Actuated-Coordinated |
| Maximum v/c Ratio: | 0.57 |
| Intersection Signal Delay: | 19.0 |
| Intersection LOS: | B |
| Intersection Capacity Utilization: | 69.0% |
| ICU Level of Service: | C |
| Analysis Period (min): | 15 |

Splits and Phases: 1: Iroquois Road & Carling Avenue
























| Lane Group | SBT | SBR |
|-----------------------------|-------|-----|
| v/c Ratio | 0.21 | |
| Control Delay | 22.8 | |
| Queue Delay | 0.0 | |
| Total Delay | 22.8 | |
| LOS | C | |
| Approach Delay | 33.1 | |
| Approach LOS | C | |
| Queue Length 50th (m) | 9.4 | |
| Queue Length 95th (m) | 21.5 | |
| Internal Link Dist (m) | 280.9 | |
| Turn Bay Length (m) | | |
| Base Capacity (vph) | 534 | |
| Starvation Cap Reductn | 0 | |
| Spillback Cap Reductn | 0 | |
| Storage Cap Reductn | 0 | |
| Reduced v/c Ratio | 0.16 | |
| Intersection Summary | | |

1: Iroquois Road & Carling Avenue
1995 Carling Avenue

Future (2024) Background Traffic (No U-Turn at Hare)

PM Peak Hour

| |  |  |  |  |  |  |  |  |  |  |  |  |
|-------------------------|---|---|---|---|---|---|--|---|---|---|---|---|
| Lane Group | EBU | EBL | EBT | EBR | WBU | WBL | WBT | WBR | NBL | NBT | NBR | SBL |
| Lane Configurations | |  |  |  | | |  |  | |  | |  |
| Traffic Volume (vph) | 2 | 41 | 688 | 4 | 32 | 17 | 1448 | 107 | 13 | 20 | 10 | 117 |
| Future Volume (vph) | 2 | 41 | 688 | 4 | 32 | 17 | 1448 | 107 | 13 | 20 | 10 | 117 |
| Ideal Flow (vphpl) | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 |
| Storage Length (m) | | 25.0 | | 40.0 | | 20.0 | | 85.0 | 0.0 | | 0.0 | 50.0 |
| Storage Lanes | | 1 | | 1 | | 1 | | 1 | 0 | | 0 | 1 |
| Taper Length (m) | | 7.5 | | | | 7.5 | | | 7.5 | | | 7.5 |
| Lane Util. Factor | 0.95 | 1.00 | 0.95 | 1.00 | 0.91 | 1.00 | 0.91 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Ped Bike Factor | | | | 0.92 | | 0.98 | | 0.90 | | 0.99 | | 0.98 |
| Frt | | | | 0.850 | | | | 0.850 | | 0.969 | | |
| Flt Protected | | 0.950 | | | | 0.950 | | | | 0.985 | | 0.950 |
| Satd. Flow (prot) | 0 | 1729 | 3390 | 1547 | 0 | 1694 | 4919 | 1547 | 0 | 1726 | 0 | 1712 |
| Flt Permitted | | 0.108 | | | | 0.390 | | | | 0.921 | | 0.761 |
| Satd. Flow (perm) | 0 | 197 | 3390 | 1425 | 0 | 684 | 4919 | 1391 | 0 | 1602 | 0 | 1350 |
| Right Turn on Red | | | | Yes | | | | Yes | | | Yes | |
| Satd. Flow (RTOR) | | | | 95 | | | | 107 | | 10 | | |
| Link Speed (k/h) | | | 60 | | | | 60 | | | 50 | | |
| Link Distance (m) | | | 305.5 | | | | 137.5 | | | 297.2 | | |
| Travel Time (s) | | | 18.3 | | | | 8.3 | | | 21.4 | | |
| Confl. Peds. (#/hr) | | 28 | | 19 | | 19 | | 28 | 28 | | 17 | 17 |
| Confl. Bikes (#/hr) | | | | 6 | | | | | | | | |
| Peak Hour Factor | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Heavy Vehicles (%) | 0% | 0% | 2% | 0% | 0% | 6% | 1% | 0% | 0% | 0% | 0% | 1% |
| Adj. Flow (vph) | 2 | 41 | 688 | 4 | 32 | 17 | 1448 | 107 | 13 | 20 | 10 | 117 |
| Shared Lane Traffic (%) | | | | | | | | | | | | |
| Lane Group Flow (vph) | 0 | 43 | 688 | 4 | 0 | 49 | 1448 | 107 | 0 | 43 | 0 | 117 |
| Turn Type | pm+pt | pm+pt | NA | Perm | pm+pt | pm+pt | NA | Perm | Perm | NA | | Perm |
| Protected Phases | 7 | 7 | 4 | | 3 | 3 | 8 | | | 2 | | |
| Permitted Phases | 4 | 4 | | 4 | 8 | 8 | | 8 | 2 | | | 6 |
| Detector Phase | 7 | 7 | 4 | 4 | 3 | 3 | 8 | 8 | 2 | 2 | | 6 |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 10.0 | 10.0 | | 10.0 |
| Minimum Split (s) | 12.0 | 12.0 | 28.3 | 28.3 | 12.0 | 12.0 | 28.3 | 28.3 | 47.3 | 47.3 | | 47.3 |
| Total Split (s) | 12.0 | 12.0 | 71.0 | 71.0 | 12.0 | 12.0 | 71.0 | 71.0 | 47.0 | 47.0 | | 47.0 |
| Total Split (%) | 9.2% | 9.2% | 54.6% | 54.6% | 9.2% | 9.2% | 54.6% | 54.6% | 36.2% | 36.2% | | 36.2% |
| Maximum Green (s) | 5.0 | 5.0 | 64.7 | 64.7 | 5.0 | 5.0 | 64.7 | 64.7 | 39.7 | 39.7 | | 39.7 |
| Yellow Time (s) | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.3 | 3.3 | | 3.3 |
| All-Red Time (s) | 3.3 | 3.3 | 2.6 | 2.6 | 3.3 | 3.3 | 2.6 | 2.6 | 4.0 | 4.0 | | 4.0 |
| Lost Time Adjust (s) | | -3.0 | -2.3 | -2.3 | | | -3.0 | -2.3 | -2.3 | | -3.3 | -3.3 |
| Total Lost Time (s) | | 4.0 | 4.0 | 4.0 | | | 4.0 | 4.0 | 4.0 | | 4.0 | 4.0 |
| Lead/Lag | Lead | Lead | Lag | Lag | Lead | Lead | Lag | Lag | | | | |
| Lead-Lag Optimize? | Yes | Yes | Yes | Yes | Yes | Yes | Yes | Yes | | | | |
| Vehicle Extension (s) | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | | 3.0 |
| Recall Mode | Max | Max | C-Max | C-Max | None | None | C-Max | C-Max | None | None | | None |
| Walk Time (s) | | | 10.0 | 10.0 | | | 10.0 | 10.0 | 27.0 | 27.0 | | 27.0 |
| Flash Dont Walk (s) | | | 12.0 | 12.0 | | | 12.0 | 12.0 | 13.0 | 13.0 | | 13.0 |
| Pedestrian Calls (#/hr) | | | 19 | 19 | | | 28 | 28 | 17 | 17 | | 28 |
| Act Effct Green (s) | | 87.7 | 80.3 | 80.3 | | | 75.3 | 67.0 | 67.0 | 31.9 | | 31.9 |
| Actuated g/C Ratio | | 0.67 | 0.62 | 0.62 | | | 0.58 | 0.52 | 0.52 | 0.25 | | 0.25 |

1: Iroquois Road & Carling Avenue
1995 Carling Avenue

Future (2024) Background Traffic (No U-Turn at Hare)

PM Peak Hour




| Lane Group | SBT | SBR |
|-------------------------|-------|------|
| Lane Configurations | | |
| Traffic Volume (vph) | 23 | 60 |
| Future Volume (vph) | 23 | 60 |
| Ideal Flow (vphpl) | 1800 | 1800 |
| Storage Length (m) | | 0.0 |
| Storage Lanes | | 0 |
| Taper Length (m) | | |
| Lane Util. Factor | 1.00 | 1.00 |
| Ped Bike Factor | 0.97 | |
| Frt | 0.892 | |
| Flt Protected | | |
| Satd. Flow (prot) | 1554 | 0 |
| Flt Permitted | | |
| Satd. Flow (perm) | 1554 | 0 |
| Right Turn on Red | | Yes |
| Satd. Flow (RTOR) | 30 | |
| Link Speed (k/h) | 50 | |
| Link Distance (m) | 304.9 | |
| Travel Time (s) | 22.0 | |
| Confl. Peds. (#/hr) | | 28 |
| Confl. Bikes (#/hr) | | 2 |
| Peak Hour Factor | 1.00 | 1.00 |
| Heavy Vehicles (%) | 0% | 2% |
| Adj. Flow (vph) | 23 | 60 |
| Shared Lane Traffic (%) | | |
| Lane Group Flow (vph) | 83 | 0 |
| Turn Type | NA | |
| Protected Phases | 6 | |
| Permitted Phases | | |
| Detector Phase | 6 | |
| Switch Phase | | |
| Minimum Initial (s) | 10.0 | |
| Minimum Split (s) | 47.3 | |
| Total Split (s) | 47.0 | |
| Total Split (%) | 36.2% | |
| Maximum Green (s) | 39.7 | |
| Yellow Time (s) | 3.3 | |
| All-Red Time (s) | 4.0 | |
| Lost Time Adjust (s) | -3.3 | |
| Total Lost Time (s) | 4.0 | |
| Lead/Lag | | |
| Lead-Lag Optimize? | | |
| Vehicle Extension (s) | 3.0 | |
| Recall Mode | None | |
| Walk Time (s) | 27.0 | |
| Flash Dont Walk (s) | 13.0 | |
| Pedestrian Calls (#/hr) | 28 | |
| Act Effct Green (s) | 31.9 | |
| Actuated g/C Ratio | 0.25 | |

1: Iroquois Road & Carling Avenue
1995 Carling Avenue

Future (2024) Background Traffic (No U-Turn at Hare)

PM Peak Hour




| Lane Group | EBU | EBL | EBT | EBR | WBU | WBL | WBT | WBR | NBL | NBT | NBR | SBL |
|------------------------|-----|------|-------|------|-----|------|-------|------|-----|-------|-----|------|
| v/c Ratio | | 0.12 | 0.33 | 0.00 | | 0.11 | 0.57 | 0.14 | | 0.11 | | 0.35 |
| Control Delay | | 10.3 | 15.3 | 0.0 | | 10.4 | 22.8 | 3.3 | | 26.5 | | 40.4 |
| Queue Delay | | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 | | 0.0 | | 0.0 |
| Total Delay | | 10.3 | 15.3 | 0.0 | | 10.4 | 22.8 | 3.3 | | 26.5 | | 40.4 |
| LOS | | B | B | A | | B | C | A | | C | | D |
| Approach Delay | | | 14.9 | | | | 21.1 | | | 26.5 | | |
| Approach LOS | | | B | | | | C | | | C | | |
| Queue Length 50th (m) | | 4.2 | 54.6 | 0.0 | | 4.8 | 90.4 | 0.0 | | 5.8 | | 21.9 |
| Queue Length 95th (m) | | 9.0 | 69.0 | 0.0 | | 10.0 | 104.5 | 8.9 | | 14.4 | | 37.8 |
| Internal Link Dist (m) | | | 281.5 | | | | 113.5 | | | 273.2 | | |
| Turn Bay Length (m) | | 25.0 | | 40.0 | | 20.0 | | 85.0 | | | | 50.0 |
| Base Capacity (vph) | | 358 | 2095 | 917 | | 460 | 2535 | 768 | | 536 | | 446 |
| Starvation Cap Reductn | | 0 | 0 | 0 | | 0 | 0 | 0 | | 0 | | 0 |
| Spillback Cap Reductn | | 0 | 0 | 0 | | 0 | 0 | 0 | | 0 | | 0 |
| Storage Cap Reductn | | 0 | 0 | 0 | | 0 | 0 | 0 | | 0 | | 0 |
| Reduced v/c Ratio | | 0.12 | 0.33 | 0.00 | | 0.11 | 0.57 | 0.14 | | 0.08 | | 0.26 |

Intersection Summary

| | |
|------------------------------------|---|
| Area Type: | Other |
| Cycle Length: | 130 |
| Actuated Cycle Length: | 130 |
| Offset: | 95 (73%), Referenced to phase 4:EBTL and 8:WBTL, Start of Green |
| Natural Cycle: | 90 |
| Control Type: | Actuated-Coordinated |
| Maximum v/c Ratio: | 0.57 |
| Intersection Signal Delay: | 20.3 |
| Intersection LOS: | C |
| Intersection Capacity Utilization: | 69.2% |
| ICU Level of Service: | C |
| Analysis Period (min): | 15 |

Splits and Phases: 1: Iroquois Road & Carling Avenue





| Lane Group | SBT | SBR |
|-----------------------------|-------|-----|
| v/c Ratio | 0.21 | |
| Control Delay | 22.8 | |
| Queue Delay | 0.0 | |
| Total Delay | 22.8 | |
| LOS | C | |
| Approach Delay | 33.1 | |
| Approach LOS | C | |
| Queue Length 50th (m) | 9.4 | |
| Queue Length 95th (m) | 21.5 | |
| Internal Link Dist (m) | 280.9 | |
| Turn Bay Length (m) | | |
| Base Capacity (vph) | 534 | |
| Starvation Cap Reductn | 0 | |
| Spillback Cap Reductn | 0 | |
| Storage Cap Reductn | 0 | |
| Reduced v/c Ratio | 0.16 | |
| Intersection Summary | | |

2: Hare Avenue & Carling Avenue
1995 Carling Avenue

Future (2024) Background Traffic
PM Peak Hour

| Intersection | | | | | | | | |
|--------------------------|------|------|------|------|------|------|------|------|
| Int Delay, s/veh | 0.6 | | | | | | | |
| Movement | EBU | EBT | EBR | WBU | WBL | WBT | NBL | NBR |
| Lane Configurations | | ↑↑ | ↑ | | ↓ | ↑↑ | ↓ | |
| Traffic Vol, veh/h | 1 | 810 | 8 | 26 | 37 | 1565 | 10 | 11 |
| Future Vol, veh/h | 1 | 810 | 8 | 26 | 37 | 1565 | 10 | 11 |
| Conflicting Peds, #/hr | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Sign Control | Free | Free | Free | Free | Free | Free | Stop | Stop |
| RT Channelized | - | - | None | - | - | None | - | None |
| Storage Length | - | - | 350 | - | 250 | - | 0 | - |
| Veh in Median Storage, # | - | 0 | - | - | - | 0 | 0 | - |
| Grade, % | - | 0 | - | - | - | 0 | 0 | - |
| Peak Hour Factor | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| Heavy Vehicles, % | 0 | 0 | 0 | 4 | 0 | 0 | 0 | 0 |
| Mvmt Flow | 1 | 810 | 8 | 26 | 37 | 1565 | 10 | 11 |

| Major/Minor | Major1 | | Major2 | | Minor1 | | | |
|----------------------|--------|---|--------|------|--------|---|------|-----|
| Conflicting Flow All | 1565 | 0 | 0 | 810 | 818 | 0 | 1721 | 405 |
| Stage 1 | - | - | - | - | - | - | 812 | - |
| Stage 2 | - | - | - | - | - | - | 909 | - |
| Critical Hdwy | 6.4 | - | - | 6.48 | 4.1 | - | 6.8 | 6.9 |
| Critical Hdwy Stg 1 | - | - | - | - | - | - | 5.8 | - |
| Critical Hdwy Stg 2 | - | - | - | - | - | - | 5.8 | - |
| Follow-up Hdwy | 2.5 | - | - | 2.54 | 2.2 | - | 3.5 | 3.3 |
| Pot Cap-1 Maneuver | 146 | - | - | 433 | 819 | - | 82 | 601 |
| Stage 1 | - | - | - | - | - | - | 402 | - |
| Stage 2 | - | - | - | - | - | - | 358 | - |
| Platoon blocked, % | - | - | - | - | - | - | - | - |
| Mov Cap-1 Maneuver | 146 | - | - | 592 | 592 | - | 72 | 601 |
| Mov Cap-2 Maneuver | - | - | - | - | - | - | 72 | - |
| Stage 1 | - | - | - | - | - | - | 397 | - |
| Stage 2 | - | - | - | - | - | - | 320 | - |

| Approach | EB | WB | NB |
|----------------------|----|-----|------|
| HCM Control Delay, s | 0 | 0.5 | 36.8 |
| HCM LOS | | | E |

| Minor Lane/Major Mvmt | NBLn1 | EBT | EBR | WBL | WBT |
|-----------------------|-------|-----|-----|-------|-----|
| Capacity (veh/h) | 134 | - | - | 592 | - |
| HCM Lane V/C Ratio | 0.157 | - | - | 0.106 | - |
| HCM Control Delay (s) | 36.8 | - | - | 11.8 | - |
| HCM Lane LOS | E | - | - | B | - |
| HCM 95th %tile Q(veh) | 0.5 | - | - | 0.4 | - |

2: Hare Avenue & Carling Avenue
1995 Carling Avenue

Future (2024) Background Traffic (No U-Turn at Hare)

PM Peak Hour

| Intersection | | | | | | |
|--------------------------|------|------|------|------|------|------|
| Int Delay, s/veh | 0.4 | | | | | |
| Movement | EBT | EBR | WBL | WBT | NBL | NBR |
| Lane Configurations | ↑↑ | ↑ | ↓ | ↑↑ | ↓ | ↓ |
| Traffic Vol, veh/h | 836 | 8 | 37 | 1591 | 10 | 11 |
| Future Vol, veh/h | 836 | 8 | 37 | 1591 | 10 | 11 |
| Conflicting Peds, #/hr | 0 | 0 | 0 | 0 | 0 | 0 |
| Sign Control | Free | Free | Free | Free | Stop | Stop |
| RT Channelized | - | None | - | None | - | None |
| Storage Length | - | 350 | 250 | - | 0 | - |
| Veh in Median Storage, # | 0 | - | - | 0 | 0 | - |
| Grade, % | 0 | - | - | 0 | 0 | - |
| Peak Hour Factor | 100 | 100 | 100 | 100 | 100 | 100 |
| Heavy Vehicles, % | 0 | 0 | 0 | 0 | 0 | 0 |
| Mvmt Flow | 836 | 8 | 37 | 1591 | 10 | 11 |

| Major/Minor | Major1 | | Major2 | | Minor1 | |
|----------------------|--------|---|--------|---|--------|-----|
| Conflicting Flow All | 0 | 0 | 844 | 0 | 1706 | 418 |
| Stage 1 | - | - | - | - | 836 | - |
| Stage 2 | - | - | - | - | 870 | - |
| Critical Hdwy | - | - | 4.1 | - | 6.8 | 6.9 |
| Critical Hdwy Stg 1 | - | - | - | - | 5.8 | - |
| Critical Hdwy Stg 2 | - | - | - | - | 5.8 | - |
| Follow-up Hdwy | - | - | 2.2 | - | 3.5 | 3.3 |
| Pot Cap-1 Maneuver | - | - | 801 | - | 84 | 589 |
| Stage 1 | - | - | - | - | 391 | - |
| Stage 2 | - | - | - | - | 375 | - |
| Platoon blocked, % | - | - | - | - | - | - |
| Mov Cap-1 Maneuver | - | - | 801 | - | 80 | 589 |
| Mov Cap-2 Maneuver | - | - | - | - | 80 | - |
| Stage 1 | - | - | - | - | 391 | - |
| Stage 2 | - | - | - | - | 358 | - |

| Approach | EB | WB | NB |
|----------------------|----|-----|------|
| HCM Control Delay, s | 0 | 0.2 | 33.8 |
| HCM LOS | | | D |

| Minor Lane/Major Mvmt | NBLn1 | EBT | EBR | WBL | WBT |
|-----------------------|-------|-----|-----|-------|-----|
| Capacity (veh/h) | 146 | - | - | 801 | - |
| HCM Lane V/C Ratio | 0.144 | - | - | 0.046 | - |
| HCM Control Delay (s) | 33.8 | - | - | 9.7 | - |
| HCM Lane LOS | D | - | - | A | - |
| HCM 95th %tile Q(veh) | 0.5 | - | - | 0.1 | - |

3: Carling Avenue & Bromley Road
 1995 Carling Avenue

Future (2024) Background Traffic
 PM Peak Hour

| Intersection | | | | | | |
|--------------------------|------|------|------|------|------|------|
| Int Delay, s/veh | 0.1 | | | | | |
| Movement | EBL | EBT | WBT | WBR | SBL | SBR |
| Lane Configurations | | ↑↑ | ↑↑ | ↑ | | ↑ |
| Traffic Vol, veh/h | 0 | 847 | 1615 | 16 | 0 | 12 |
| Future Vol, veh/h | 0 | 847 | 1615 | 16 | 0 | 12 |
| Conflicting Peds, #/hr | 0 | 0 | 0 | 0 | 0 | 0 |
| Sign Control | Free | Free | Free | Free | Stop | Stop |
| RT Channelized | - | None | - | None | - | None |
| Storage Length | - | - | - | 300 | - | 0 |
| Veh in Median Storage, # | - | 0 | 0 | - | 0 | - |
| Grade, % | - | 0 | 0 | - | 0 | - |
| Peak Hour Factor | 100 | 100 | 100 | 100 | 100 | 100 |
| Heavy Vehicles, % | 0 | 0 | 0 | 0 | 0 | 8 |
| Mvmt Flow | 0 | 847 | 1615 | 16 | 0 | 12 |

| Major/Minor | Major1 | Major2 | Minor2 | | |
|----------------------|--------|--------|--------|---|------|
| Conflicting Flow All | - | 0 | - | 0 | 808 |
| Stage 1 | - | - | - | - | - |
| Stage 2 | - | - | - | - | - |
| Critical Hdwy | - | - | - | - | 7.06 |
| Critical Hdwy Stg 1 | - | - | - | - | - |
| Critical Hdwy Stg 2 | - | - | - | - | - |
| Follow-up Hdwy | - | - | - | - | 3.38 |
| Pot Cap-1 Maneuver | 0 | - | - | - | 312 |
| Stage 1 | 0 | - | - | - | - |
| Stage 2 | 0 | - | - | - | - |
| Platoon blocked, % | - | - | - | - | - |
| Mov Cap-1 Maneuver | - | - | - | - | 312 |
| Mov Cap-2 Maneuver | - | - | - | - | - |
| Stage 1 | - | - | - | - | - |
| Stage 2 | - | - | - | - | - |

| Approach | EB | WB | SB |
|----------------------|----|----|----|
| HCM Control Delay, s | 0 | 0 | 17 |
| HCM LOS | | | C |

| Minor Lane/Major Mvmt | EBT | WBT | WBR | SBLn1 |
|-----------------------|-----|-----|-----|-------|
| Capacity (veh/h) | - | - | - | 312 |
| HCM Lane V/C Ratio | - | - | - | 0.038 |
| HCM Control Delay (s) | - | - | - | 17 |
| HCM Lane LOS | - | - | - | C |
| HCM 95th %tile Q(veh) | - | - | - | 0.1 |

4: Maitland Avenue/Sherbourne Road & Carling Avenue
1995 Carling Avenue

Future (2024) Background Traffic
PM Peak Hour



| Lane Group | EBU | EBL | EBT | EBR | WBU | WBL | WBT | WBR | NBL | NBT | NBR | SBL |
|-------------------------|------|-------|-------|-------|-------|-------|-------|------|-------|-------|------|-------|
| Lane Configurations | | | | | | | | | | | | |
| Traffic Volume (vph) | 22 | 62 | 592 | 171 | 9 | 734 | 1343 | 54 | 221 | 213 | 213 | 48 |
| Future Volume (vph) | 22 | 62 | 592 | 171 | 9 | 734 | 1343 | 54 | 221 | 213 | 213 | 48 |
| Ideal Flow (vphpl) | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 |
| Storage Length (m) | | 55.0 | | 130.0 | | 115.0 | | 0.0 | 75.0 | | 0.0 | 45.0 |
| Storage Lanes | | 1 | | 1 | | 1 | | 0 | 1 | | 0 | 1 |
| Taper Length (m) | | 7.5 | | | | 7.5 | | | 7.5 | | | 7.5 |
| Lane Util. Factor | 0.95 | 1.00 | 0.95 | 1.00 | 0.95 | 0.97 | 0.95 | 0.95 | 1.00 | 1.00 | 1.00 | 1.00 |
| Ped Bike Factor | | 0.98 | | 0.94 | | 0.96 | 0.99 | | 0.98 | 0.98 | | |
| Frt | | | | 0.850 | | | 0.994 | | | 0.925 | | |
| Flt Protected | | 0.950 | | | | 0.950 | | | 0.950 | | | 0.950 |
| Satd. Flow (prot) | 0 | 1729 | 3390 | 1532 | 0 | 3321 | 3381 | 0 | 1729 | 1624 | 0 | 1729 |
| Flt Permitted | | 0.950 | | | | 0.950 | | | 0.462 | | | 0.223 |
| Satd. Flow (perm) | 0 | 1699 | 3390 | 1438 | 0 | 3200 | 3381 | 0 | 822 | 1624 | 0 | 406 |
| Right Turn on Red | | | | Yes | | | | Yes | | | Yes | |
| Satd. Flow (RTOR) | | | | 171 | | | 4 | | | 49 | | |
| Link Speed (k/h) | | | 60 | | | | 60 | | | 50 | | |
| Link Distance (m) | | | 447.3 | | | | 309.6 | | | 300.2 | | |
| Travel Time (s) | | | 26.8 | | | | 18.6 | | | 21.6 | | |
| Confl. Peds. (#/hr) | | 36 | | 25 | | 25 | | 36 | 20 | | 15 | 15 |
| Confl. Bikes (#/hr) | | | | | | | | 2 | | | | |
| Peak Hour Factor | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Heavy Vehicles (%) | 0% | 0% | 2% | 1% | 0% | 1% | 1% | 4% | 0% | 0% | 3% | 0% |
| Adj. Flow (vph) | 22 | 62 | 592 | 171 | 9 | 734 | 1343 | 54 | 221 | 213 | 213 | 48 |
| Shared Lane Traffic (%) | | | | | | | | | | | | |
| Lane Group Flow (vph) | 0 | 84 | 592 | 171 | 0 | 743 | 1397 | 0 | 221 | 426 | 0 | 48 |
| Turn Type | Prot | Prot | NA | Perm | Prot | Prot | NA | | Perm | NA | | Perm |
| Protected Phases | 7 | 7 | 4 | | 3 | 3 | 8 | | | 2 | | |
| Permitted Phases | | | | 4 | | | | | 2 | | | 6 |
| Detector Phase | 7 | 7 | 4 | 4 | 3 | 3 | 8 | | 2 | 2 | | 6 |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | | 10.0 | 10.0 | | 10.0 |
| Minimum Split (s) | 10.9 | 10.9 | 23.9 | 23.9 | 10.9 | 10.9 | 23.9 | | 24.8 | 24.8 | | 24.8 |
| Total Split (s) | 11.0 | 11.0 | 33.0 | 33.0 | 37.0 | 37.0 | 59.0 | | 50.0 | 50.0 | | 50.0 |
| Total Split (%) | 9.2% | 9.2% | 27.5% | 27.5% | 30.8% | 30.8% | 49.2% | | 41.7% | 41.7% | | 41.7% |
| Maximum Green (s) | 5.1 | 5.1 | 27.1 | 27.1 | 31.1 | 31.1 | 53.1 | | 43.2 | 43.2 | | 43.2 |
| Yellow Time (s) | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | | 3.3 | 3.3 | | 3.3 |
| All-Red Time (s) | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | | 3.5 | 3.5 | | 3.5 |
| Lost Time Adjust (s) | | -1.9 | -1.9 | -1.9 | | -1.9 | -1.9 | | -2.8 | -2.8 | | -2.8 |
| Total Lost Time (s) | | 4.0 | 4.0 | 4.0 | | 4.0 | 4.0 | | 4.0 | 4.0 | | 4.0 |
| Lead/Lag | Lead | Lead | Lag | Lag | Lead | Lead | Lag | | | | | |
| Lead-Lag Optimize? | Yes | Yes | Yes | Yes | Yes | Yes | Yes | | | | | |
| Vehicle Extension (s) | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | | 3.0 | 3.0 | | 3.0 |
| Recall Mode | None | None | C-Max | C-Max | None | None | C-Max | | None | None | | None |
| Walk Time (s) | | | 7.0 | 7.0 | | | 7.0 | | 7.0 | 7.0 | | 7.0 |
| Flash Dont Walk (s) | | | 11.0 | 11.0 | | | 11.0 | | 11.0 | 11.0 | | 11.0 |
| Pedestrian Calls (#/hr) | | | 25 | 25 | | | 36 | | 15 | 15 | | 20 |
| Act Effct Green (s) | | 10.4 | 38.1 | 38.1 | | 32.1 | 59.7 | | 37.9 | 37.9 | | 37.9 |
| Actuated g/C Ratio | | 0.09 | 0.32 | 0.32 | | 0.27 | 0.50 | | 0.32 | 0.32 | | 0.32 |

4: Maitland Avenue/Sherbourne Road & Carling Avenue
 1995 Carling Avenue


Future (2024) Background Traffic
 PM Peak Hour



| Lane Group | SBT | SBR |
|-------------------------|-------|------|
| Lane Configurations | ↔ | |
| Traffic Volume (vph) | 201 | 45 |
| Future Volume (vph) | 201 | 45 |
| Ideal Flow (vphpl) | 1800 | 1800 |
| Storage Length (m) | | 0.0 |
| Storage Lanes | | 0 |
| Taper Length (m) | | |
| Lane Util. Factor | 1.00 | 1.00 |
| Ped Bike Factor | 0.99 | |
| Frt | 0.973 | |
| Flt Protected | | |
| Satd. Flow (prot) | 1748 | 0 |
| Flt Permitted | | |
| Satd. Flow (perm) | 1748 | 0 |
| Right Turn on Red | | Yes |
| Satd. Flow (RTOR) | 11 | |
| Link Speed (k/h) | 50 | |
| Link Distance (m) | 301.0 | |
| Travel Time (s) | 21.7 | |
| Confl. Peds. (#/hr) | | 20 |
| Confl. Bikes (#/hr) | | |
| Peak Hour Factor | 1.00 | 1.00 |
| Heavy Vehicles (%) | 0% | 2% |
| Adj. Flow (vph) | 201 | 45 |
| Shared Lane Traffic (%) | | |
| Lane Group Flow (vph) | 246 | 0 |
| Turn Type | NA | |
| Protected Phases | 6 | |
| Permitted Phases | | |
| Detector Phase | 6 | |
| Switch Phase | | |
| Minimum Initial (s) | 10.0 | |
| Minimum Split (s) | 24.8 | |
| Total Split (s) | 50.0 | |
| Total Split (%) | 41.7% | |
| Maximum Green (s) | 43.2 | |
| Yellow Time (s) | 3.3 | |
| All-Red Time (s) | 3.5 | |
| Lost Time Adjust (s) | -2.8 | |
| Total Lost Time (s) | 4.0 | |
| Lead/Lag | | |
| Lead-Lag Optimize? | | |
| Vehicle Extension (s) | 3.0 | |
| Recall Mode | None | |
| Walk Time (s) | 7.0 | |
| Flash Dont Walk (s) | 11.0 | |
| Pedestrian Calls (#/hr) | 20 | |
| Act Effct Green (s) | 37.9 | |
| Actuated g/C Ratio | 0.32 | |

4: Maitland Avenue/Sherbourne Road & Carling Avenue
1995 Carling Avenue

Future (2024) Background Traffic
PM Peak Hour




| Lane Group | EBU | EBL | EBT | EBR | WBU | WBL | WBT | WBR | NBL | NBT | NBR | SBL |
|------------------------|-----|--------|-------|-------|-----|-------|--------|-----|-------|-------|-----|------|
| v/c Ratio | | 0.56 | 0.55 | 0.30 | | 0.84 | 0.83 | | 0.85 | 0.78 | | 0.38 |
| Control Delay | | 68.2 | 38.8 | 7.1 | | 50.9 | 32.4 | | 66.1 | 42.6 | | 38.4 |
| Queue Delay | | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 |
| Total Delay | | 68.2 | 38.8 | 7.1 | | 50.9 | 32.4 | | 66.1 | 42.6 | | 38.4 |
| LOS | | E | D | A | | D | C | | E | D | | D |
| Approach Delay | | | 35.3 | | | | 38.8 | | | 50.6 | | |
| Approach LOS | | | D | | | | D | | | D | | |
| Queue Length 50th (m) | | 18.6 | 64.0 | 0.6 | | 82.9 | 155.6 | | 47.7 | 79.8 | | 8.6 |
| Queue Length 95th (m) | | m#48.5 | m88.2 | m16.9 | | 107.1 | #192.0 | | #77.2 | 108.3 | | 18.8 |
| Internal Link Dist (m) | | | 423.3 | | | | 285.6 | | | 276.2 | | |
| Turn Bay Length (m) | | 55.0 | | 130.0 | | 115.0 | | | 75.0 | | | 45.0 |
| Base Capacity (vph) | | 150 | 1075 | 573 | | 930 | 1683 | | 315 | 652 | | 155 |
| Starvation Cap Reductn | | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | | 0 |
| Spillback Cap Reductn | | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | | 0 |
| Storage Cap Reductn | | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | | 0 |
| Reduced v/c Ratio | | 0.56 | 0.55 | 0.30 | | 0.80 | 0.83 | | 0.70 | 0.65 | | 0.31 |

Intersection Summary

Area Type: Other
 Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 103 (86%), Referenced to phase 4:EBT and 8:WBT, Start of Green
 Natural Cycle: 80
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.85
 Intersection Signal Delay: 39.6 Intersection LOS: D
 Intersection Capacity Utilization 94.0% ICU Level of Service F
 Analysis Period (min) 15
 # 95th percentile volume exceeds capacity, queue may be longer.
 Queue shown is maximum after two cycles.
 m Volume for 95th percentile queue is metered by upstream signal.

Splits and Phases: 4: Maitland Avenue/Sherbourne Road & Carling Avenue






| Lane Group | SBT | SBR |
|------------------------|-------|-----|
| v/c Ratio | 0.44 | |
| Control Delay | 32.4 | |
| Queue Delay | 0.0 | |
| Total Delay | 32.4 | |
| LOS | C | |
| Approach Delay | 33.4 | |
| Approach LOS | C | |
| Queue Length 50th (m) | 43.0 | |
| Queue Length 95th (m) | 60.3 | |
| Internal Link Dist (m) | 277.0 | |
| Turn Bay Length (m) | | |
| Base Capacity (vph) | 676 | |
| Starvation Cap Reductn | 0 | |
| Spillback Cap Reductn | 0 | |
| Storage Cap Reductn | 0 | |
| Reduced v/c Ratio | 0.36 | |
| Intersection Summary | | |

1: Iroquois Road & Carling Avenue
1995 Carling Avenue

Future (2029) Background Traffic
AM Peak Hour



| Lane Group | EBU | EBL | EBT | EBR | WBU | WBL | WBT | WBR | NBL | NBT | NBR | SBL |
|-------------------------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|------|-------|
| Lane Configurations | | | | | | | | | | | | |
| Traffic Volume (vph) | 1 | 19 | 1588 | 5 | 25 | 7 | 365 | 60 | 3 | 24 | 30 | 75 |
| Future Volume (vph) | 1 | 19 | 1588 | 5 | 25 | 7 | 365 | 60 | 3 | 24 | 30 | 75 |
| Ideal Flow (vphpl) | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 |
| Storage Length (m) | | 25.0 | | 40.0 | | 20.0 | | 85.0 | 0.0 | | 0.0 | 50.0 |
| Storage Lanes | | 1 | | 1 | | 1 | | 1 | 0 | | 0 | 1 |
| Taper Length (m) | | 7.5 | | | | 7.5 | | | 7.5 | | | 7.5 |
| Lane Util. Factor | 0.95 | 1.00 | 0.95 | 1.00 | 0.91 | 1.00 | 0.91 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Ped Bike Factor | | 0.97 | | 0.94 | | | | 0.94 | | 0.99 | | 0.99 |
| Frt | | | | 0.850 | | | | 0.850 | | 0.929 | | |
| Flt Protected | | 0.950 | | | | 0.950 | | | | 0.997 | | 0.950 |
| Satd. Flow (prot) | 0 | 1729 | 3390 | 1547 | 0 | 1729 | 4687 | 1502 | 0 | 1635 | 0 | 1679 |
| Flt Permitted | | 0.485 | | | | 0.135 | | | | 0.990 | | 0.717 |
| Satd. Flow (perm) | 0 | 860 | 3390 | 1461 | 0 | 246 | 4687 | 1406 | 0 | 1623 | 0 | 1254 |
| Right Turn on Red | | | | Yes | | | | Yes | | | Yes | |
| Satd. Flow (RTOR) | | | | 95 | | | | 95 | | | 30 | |
| Link Speed (k/h) | | | 60 | | | | 60 | | | 50 | | |
| Link Distance (m) | | | 305.5 | | | | 136.9 | | | 297.2 | | |
| Travel Time (s) | | | 18.3 | | | | 8.2 | | | 21.4 | | |
| Confl. Peds. (#/hr) | | 15 | | 12 | | 12 | | 15 | 13 | | 12 | 12 |
| Confl. Bikes (#/hr) | | | | 1 | | | | 1 | | | 4 | |
| Peak Hour Factor | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Heavy Vehicles (%) | 0% | 0% | 2% | 0% | 0% | 0% | 6% | 3% | 0% | 4% | 0% | 3% |
| Adj. Flow (vph) | 1 | 19 | 1588 | 5 | 25 | 7 | 365 | 60 | 3 | 24 | 30 | 75 |
| Shared Lane Traffic (%) | | | | | | | | | | | | |
| Lane Group Flow (vph) | 0 | 20 | 1588 | 5 | 0 | 32 | 365 | 60 | 0 | 57 | 0 | 75 |
| Turn Type | pm+pt | pm+pt | NA | Perm | pm+pt | pm+pt | NA | Perm | Perm | NA | | Perm |
| Protected Phases | 7 | 7 | 4 | | 3 | 3 | 8 | | | 2 | | |
| Permitted Phases | 4 | 4 | | 4 | 8 | 8 | | 8 | 2 | | | 6 |
| Detector Phase | 7 | 7 | 4 | 4 | 3 | 3 | 8 | 8 | 2 | 2 | | 6 |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 10.0 | 10.0 | | 10.0 |
| Minimum Split (s) | 12.0 | 12.0 | 28.3 | 28.3 | 12.0 | 12.0 | 28.3 | 28.3 | 47.3 | 47.3 | | 47.3 |
| Total Split (s) | 14.0 | 14.0 | 69.0 | 69.0 | 14.0 | 14.0 | 69.0 | 69.0 | 47.0 | 47.0 | | 47.0 |
| Total Split (%) | 10.8% | 10.8% | 53.1% | 53.1% | 10.8% | 10.8% | 53.1% | 53.1% | 36.2% | 36.2% | | 36.2% |
| Maximum Green (s) | 7.0 | 7.0 | 62.7 | 62.7 | 7.0 | 7.0 | 62.7 | 62.7 | 39.7 | 39.7 | | 39.7 |
| Yellow Time (s) | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.3 | 3.3 | | 3.3 |
| All-Red Time (s) | 3.3 | 3.3 | 2.6 | 2.6 | 3.3 | 3.3 | 2.6 | 2.6 | 4.0 | 4.0 | | 4.0 |
| Lost Time Adjust (s) | | -3.0 | -2.3 | -2.3 | | | -3.0 | -2.3 | -2.3 | | -3.3 | -3.3 |
| Total Lost Time (s) | | 4.0 | 4.0 | 4.0 | | | 4.0 | 4.0 | 4.0 | | 4.0 | 4.0 |
| Lead/Lag | Lead | Lead | Lag | Lag | Lead | Lead | Lag | Lag | | | | |
| Lead-Lag Optimize? | Yes | Yes | Yes | Yes | Yes | Yes | Yes | Yes | | | | |
| Vehicle Extension (s) | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | | 3.0 |
| Recall Mode | Max | Max | C-Max | C-Max | None | None | C-Max | C-Max | None | None | | None |
| Walk Time (s) | | | 10.0 | 10.0 | | | 10.0 | 10.0 | 27.0 | 27.0 | | 27.0 |
| Flash Dont Walk (s) | | | 12.0 | 12.0 | | | 12.0 | 12.0 | 13.0 | 13.0 | | 13.0 |
| Pedestrian Calls (#/hr) | | | 12 | 12 | | | 15 | 15 | 12 | 12 | | 13 |
| Act Effct Green (s) | | 98.0 | 92.2 | 92.2 | | 74.2 | 65.0 | 65.0 | | 25.9 | | 25.9 |
| Actuated g/C Ratio | | 0.75 | 0.71 | 0.71 | | 0.57 | 0.50 | 0.50 | | 0.20 | | 0.20 |

1: Iroquois Road & Carling Avenue
 1995 Carling Avenue


Future (2029) Background Traffic
 AM Peak Hour



| Lane Group | SBT | SBR |
|-------------------------|-------|------|
| Lane Configurations | ↩ | |
| Traffic Volume (vph) | 7 | 27 |
| Future Volume (vph) | 7 | 27 |
| Ideal Flow (vphpl) | 1800 | 1800 |
| Storage Length (m) | | 0.0 |
| Storage Lanes | | 0 |
| Taper Length (m) | | |
| Lane Util. Factor | 1.00 | 1.00 |
| Ped Bike Factor | 0.98 | |
| Frt | 0.881 | |
| Flt Protected | | |
| Satd. Flow (prot) | 1490 | 0 |
| Flt Permitted | | |
| Satd. Flow (perm) | 1490 | 0 |
| Right Turn on Red | | Yes |
| Satd. Flow (RTOR) | 27 | |
| Link Speed (k/h) | 50 | |
| Link Distance (m) | 304.9 | |
| Travel Time (s) | 22.0 | |
| Confl. Peds. (#/hr) | | 13 |
| Confl. Bikes (#/hr) | | |
| Peak Hour Factor | 1.00 | 1.00 |
| Heavy Vehicles (%) | 0% | 7% |
| Adj. Flow (vph) | 7 | 27 |
| Shared Lane Traffic (%) | | |
| Lane Group Flow (vph) | 34 | 0 |
| Turn Type | NA | |
| Protected Phases | 6 | |
| Permitted Phases | | |
| Detector Phase | 6 | |
| Switch Phase | | |
| Minimum Initial (s) | 10.0 | |
| Minimum Split (s) | 47.3 | |
| Total Split (s) | 47.0 | |
| Total Split (%) | 36.2% | |
| Maximum Green (s) | 39.7 | |
| Yellow Time (s) | 3.3 | |
| All-Red Time (s) | 4.0 | |
| Lost Time Adjust (s) | -3.3 | |
| Total Lost Time (s) | 4.0 | |
| Lead/Lag | | |
| Lead-Lag Optimize? | | |
| Vehicle Extension (s) | 3.0 | |
| Recall Mode | None | |
| Walk Time (s) | 27.0 | |
| Flash Dont Walk (s) | 13.0 | |
| Pedestrian Calls (#/hr) | 13 | |
| Act Effct Green (s) | 25.9 | |
| Actuated g/C Ratio | 0.20 | |

1: Iroquois Road & Carling Avenue
1995 Carling Avenue

Future (2029) Background Traffic
AM Peak Hour




| Lane Group | EBU | EBL | EBT | EBR | WBU | WBL | WBT | WBR | NBL | NBT | NBR | SBL |
|------------------------|-----|------|--------|------|-----|------|-------|------|-----|-------|-----|------|
| v/c Ratio | | 0.02 | 0.66 | 0.00 | | 0.13 | 0.16 | 0.08 | | 0.16 | | 0.30 |
| Control Delay | | 8.3 | 19.1 | 0.0 | | 10.5 | 17.8 | 1.1 | | 20.4 | | 43.3 |
| Queue Delay | | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 | | 0.0 | | 0.0 |
| Total Delay | | 8.3 | 19.1 | 0.0 | | 10.5 | 17.8 | 1.1 | | 20.4 | | 43.3 |
| LOS | | A | B | A | | B | B | A | | C | | D |
| Approach Delay | | | 18.9 | | | | 15.1 | | | 20.4 | | |
| Approach LOS | | | B | | | | B | | | C | | |
| Queue Length 50th (m) | | 0.8 | 103.3 | 0.0 | | 1.8 | 18.0 | 0.0 | | 6.2 | | 18.2 |
| Queue Length 95th (m) | | 5.2 | #250.0 | 0.0 | | 7.2 | 24.2 | 2.4 | | 14.4 | | 25.9 |
| Internal Link Dist (m) | | | 281.5 | | | | 112.9 | | | 273.2 | | |
| Turn Bay Length (m) | | 25.0 | | 40.0 | | 20.0 | | 85.0 | | | | 50.0 |
| Base Capacity (vph) | | 852 | 2405 | 1064 | | 256 | 2343 | 750 | | 556 | | 414 |
| Starvation Cap Reductn | | 0 | 0 | 0 | | 0 | 0 | 0 | | 0 | | 0 |
| Spillback Cap Reductn | | 0 | 0 | 0 | | 0 | 0 | 0 | | 0 | | 0 |
| Storage Cap Reductn | | 0 | 0 | 0 | | 0 | 0 | 0 | | 0 | | 0 |
| Reduced v/c Ratio | | 0.02 | 0.66 | 0.00 | | 0.13 | 0.16 | 0.08 | | 0.10 | | 0.18 |

Intersection Summary

Area Type: Other
 Cycle Length: 130
 Actuated Cycle Length: 130
 Offset: 6 (5%), Referenced to phase 4:EBTL and 8:WBTL, Start of Green
 Natural Cycle: 120
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.66
 Intersection Signal Delay: 18.9 Intersection LOS: B
 Intersection Capacity Utilization 71.9% ICU Level of Service C
 Analysis Period (min) 15
 # 95th percentile volume exceeds capacity, queue may be longer.
 Queue shown is maximum after two cycles.

Splits and Phases: 1: Iroquois Road & Carling Avenue





| Lane Group | SBT | SBR |
|-----------------------------|-------|-----|
| v/c Ratio | 0.11 | |
| Control Delay | 14.5 | |
| Queue Delay | 0.0 | |
| Total Delay | 14.5 | |
| LOS | B | |
| Approach Delay | 34.3 | |
| Approach LOS | C | |
| Queue Length 50th (m) | 1.6 | |
| Queue Length 95th (m) | 8.7 | |
| Internal Link Dist (m) | 280.9 | |
| Turn Bay Length (m) | | |
| Base Capacity (vph) | 510 | |
| Starvation Cap Reductn | 0 | |
| Spillback Cap Reductn | 0 | |
| Storage Cap Reductn | 0 | |
| Reduced v/c Ratio | 0.07 | |
| Intersection Summary | | |

2: Hare Avenue & Carling Avenue
1995 Carling Avenue

Future (2029) Background Traffic
AM Peak Hour

| Intersection | | | | | | |
|--------------------------|------|------|------|------|------|------|
| Int Delay, s/veh | 0.5 | | | | | |
| Movement | EBT | EBR | WBL | WBT | NBL | NBR |
| Lane Configurations | ↑↑ | ↑ | ↓ | ↑↑ | ↑ | ↓ |
| Traffic Vol, veh/h | 1706 | 7 | 13 | 447 | 7 | 15 |
| Future Vol, veh/h | 1706 | 7 | 13 | 447 | 7 | 15 |
| Conflicting Peds, #/hr | 0 | 2 | 2 | 0 | 2 | 0 |
| Sign Control | Free | Free | Free | Free | Stop | Stop |
| RT Channelized | - | None | - | None | - | None |
| Storage Length | - | 350 | 250 | - | 0 | - |
| Veh in Median Storage, # | 0 | - | - | 0 | 0 | - |
| Grade, % | 0 | - | - | 0 | 0 | - |
| Peak Hour Factor | 100 | 100 | 100 | 100 | 100 | 100 |
| Heavy Vehicles, % | 0 | 14 | 0 | 0 | 0 | 7 |
| Mvmt Flow | 1706 | 7 | 13 | 447 | 7 | 15 |

| Major/Minor | Major1 | | Major2 | | Minor1 | |
|----------------------|--------|---|--------|---|--------|------|
| Conflicting Flow All | 0 | 0 | 1715 | 0 | 1960 | 855 |
| Stage 1 | - | - | - | - | 1708 | - |
| Stage 2 | - | - | - | - | 252 | - |
| Critical Hdwy | - | - | 4.1 | - | 6.8 | 7.04 |
| Critical Hdwy Stg 1 | - | - | - | - | 5.8 | - |
| Critical Hdwy Stg 2 | - | - | - | - | 5.8 | - |
| Follow-up Hdwy | - | - | 2.2 | - | 3.5 | 3.37 |
| Pot Cap-1 Maneuver | - | - | 375 | - | 57 | 292 |
| Stage 1 | - | - | - | - | 135 | - |
| Stage 2 | - | - | - | - | 773 | - |
| Platoon blocked, % | - | - | - | - | - | - |
| Mov Cap-1 Maneuver | - | - | 374 | - | 55 | 291 |
| Mov Cap-2 Maneuver | - | - | - | - | 55 | - |
| Stage 1 | - | - | - | - | 135 | - |
| Stage 2 | - | - | - | - | 744 | - |

| Approach | EB | WB | NB |
|----------------------|----|-----|------|
| HCM Control Delay, s | 0 | 0.4 | 40.5 |
| HCM LOS | | | E |

| Minor Lane/Major Mvmt | NBLn1 | EBT | EBR | WBL | WBT |
|-----------------------|-------|-----|-----|-------|-----|
| Capacity (veh/h) | 123 | - | - | 374 | - |
| HCM Lane V/C Ratio | 0.179 | - | - | 0.035 | - |
| HCM Control Delay (s) | 40.5 | - | - | 15 | - |
| HCM Lane LOS | E | - | - | B | - |
| HCM 95th %tile Q(veh) | 0.6 | - | - | 0.1 | - |

3: Carling Avenue & Bromley Road
 1995 Carling Avenue

Future (2029) Background Traffic
 AM Peak Hour

| Intersection | | | | | | |
|--------------------------|------|------|------|------|------|------|
| Int Delay, s/veh | 0.1 | | | | | |
| Movement | EBL | EBT | WBT | WBR | SBL | SBR |
| Lane Configurations | | ↑↑ | ↑↑ | ↑ | | ↑ |
| Traffic Vol, veh/h | 0 | 1720 | 446 | 5 | 0 | 13 |
| Future Vol, veh/h | 0 | 1720 | 446 | 5 | 0 | 13 |
| Conflicting Peds, #/hr | 8 | 0 | 0 | 8 | 0 | 0 |
| Sign Control | Free | Free | Free | Free | Stop | Stop |
| RT Channelized | - | None | - | None | - | None |
| Storage Length | - | - | - | 300 | - | 0 |
| Veh in Median Storage, # | - | 0 | 0 | - | 0 | - |
| Grade, % | - | 0 | 0 | - | 0 | - |
| Peak Hour Factor | 100 | 100 | 100 | 100 | 100 | 100 |
| Heavy Vehicles, % | 0 | 0 | 0 | 0 | 0 | 0 |
| Mvmt Flow | 0 | 1720 | 446 | 5 | 0 | 13 |


| Major/Minor | Major1 | Major2 | Minor2 | | |
|----------------------|--------|--------|--------|---|-----|
| Conflicting Flow All | - | 0 | - | 0 | 231 |
| Stage 1 | - | - | - | - | - |
| Stage 2 | - | - | - | - | - |
| Critical Hdwy | - | - | - | - | 6.9 |
| Critical Hdwy Stg 1 | - | - | - | - | - |
| Critical Hdwy Stg 2 | - | - | - | - | - |
| Follow-up Hdwy | - | - | - | - | 3.3 |
| Pot Cap-1 Maneuver | 0 | - | - | - | 777 |
| Stage 1 | 0 | - | - | - | 0 |
| Stage 2 | 0 | - | - | - | 0 |
| Platoon blocked, % | - | - | - | - | - |
| Mov Cap-1 Maneuver | - | - | - | - | 771 |
| Mov Cap-2 Maneuver | - | - | - | - | - |
| Stage 1 | - | - | - | - | - |
| Stage 2 | - | - | - | - | - |

| Approach | EB | WB | SB |
|----------------------|----|----|-----|
| HCM Control Delay, s | 0 | 0 | 9.7 |
| HCM LOS | | | A |

| Minor Lane/Major Mvmt | EBT | WBT | WBR | SBLn1 |
|-----------------------|-----|-----|-----|-------|
| Capacity (veh/h) | - | - | - | 771 |
| HCM Lane V/C Ratio | - | - | - | 0.017 |
| HCM Control Delay (s) | - | - | - | 9.7 |
| HCM Lane LOS | - | - | - | A |
| HCM 95th %tile Q(veh) | - | - | - | 0.1 |

4: Maitland Avenue/Sherbourne Road & Carling Avenue
1995 Carling Avenue

Future (2029) Background Traffic
AM Peak Hour



| Lane Group | EBU | EBL | EBT | EBR | WBU | WBL | WBT | WBR | NBL | NBT | NBR | SBL |
|-------------------------|-------|-------|-------|-------|-------|-------|-------|------|-------|-------|------|-------|
| Lane Configurations | | | | | | | | | | | | |
| Traffic Volume (vph) | 16 | 28 | 1423 | 253 | 6 | 294 | 291 | 16 | 128 | 97 | 396 | 66 |
| Future Volume (vph) | 16 | 28 | 1423 | 253 | 6 | 294 | 291 | 16 | 128 | 97 | 396 | 66 |
| Ideal Flow (vphpl) | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 |
| Storage Length (m) | | 55.0 | | 130.0 | | 115.0 | | 0.0 | 75.0 | | 0.0 | 45.0 |
| Storage Lanes | | 1 | | 1 | | 2 | | 0 | 1 | | 0 | 1 |
| Taper Length (m) | | 7.5 | | | | 7.5 | | | 7.5 | | | 7.5 |
| Lane Util. Factor | 0.95 | 1.00 | 0.95 | 1.00 | 0.95 | 0.97 | 0.95 | 0.95 | 1.00 | 1.00 | 1.00 | 1.00 |
| Ped Bike Factor | | 0.95 | | 0.96 | | 0.99 | 0.99 | | 0.99 | 0.97 | | |
| Frt | | | | 0.850 | | | 0.992 | | | 0.880 | | |
| Flt Protected | | 0.950 | | | | 0.950 | | | 0.950 | | | 0.950 |
| Satd. Flow (prot) | 0 | 1655 | 3390 | 1532 | 0 | 3228 | 3228 | 0 | 1679 | 1508 | 0 | 1679 |
| Flt Permitted | | 0.950 | | | | 0.950 | | | 0.357 | | | 0.142 |
| Satd. Flow (perm) | 0 | 1565 | 3390 | 1465 | 0 | 3204 | 3228 | 0 | 624 | 1508 | 0 | 251 |
| Right Turn on Red | | | | Yes | | | | Yes | | | Yes | |
| Satd. Flow (RTOR) | | | | 250 | | | 6 | | | 91 | | |
| Link Speed (k/h) | | | 60 | | | | 60 | | | 50 | | |
| Link Distance (m) | | | 447.3 | | | | 309.6 | | | 300.2 | | |
| Travel Time (s) | | | 26.8 | | | | 18.6 | | | 21.6 | | |
| Confl. Peds. (#/hr) | | 25 | | 16 | | 16 | | 25 | 13 | | 15 | 15 |
| Confl. Bikes (#/hr) | | | | | | | | 1 | | | 2 | |
| Peak Hour Factor | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Heavy Vehicles (%) | 0% | 7% | 2% | 1% | 0% | 4% | 6% | 0% | 3% | 5% | 2% | 3% |
| Adj. Flow (vph) | 16 | 28 | 1423 | 253 | 6 | 294 | 291 | 16 | 128 | 97 | 396 | 66 |
| Shared Lane Traffic (%) | | | | | | | | | | | | |
| Lane Group Flow (vph) | 0 | 44 | 1423 | 253 | 0 | 300 | 307 | 0 | 128 | 493 | 0 | 66 |
| Turn Type | Prot | Prot | NA | Perm | Prot | Prot | NA | | Perm | NA | | Perm |
| Protected Phases | 7 | 7 | 4 | | 3 | 3 | 8 | | | 2 | | |
| Permitted Phases | | | | 4 | | | | | 2 | | | 6 |
| Detector Phase | 7 | 7 | 4 | 4 | 3 | 3 | 8 | | 2 | 2 | | 6 |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | | 10.0 | 10.0 | | 10.0 |
| Minimum Split (s) | 10.9 | 10.9 | 23.9 | 23.9 | 10.9 | 10.9 | 23.9 | | 24.8 | 24.8 | | 24.8 |
| Total Split (s) | 13.2 | 13.2 | 59.0 | 59.0 | 17.0 | 17.0 | 62.8 | | 44.0 | 44.0 | | 44.0 |
| Total Split (%) | 11.0% | 11.0% | 49.2% | 49.2% | 14.2% | 14.2% | 52.3% | | 36.7% | 36.7% | | 36.7% |
| Maximum Green (s) | 7.3 | 7.3 | 53.1 | 53.1 | 11.1 | 11.1 | 56.9 | | 37.2 | 37.2 | | 37.2 |
| Yellow Time (s) | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | | 3.3 | 3.3 | | 3.3 |
| All-Red Time (s) | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | | 3.5 | 3.5 | | 3.5 |
| Lost Time Adjust (s) | | -1.9 | -1.9 | -1.9 | | -1.9 | -1.9 | | -2.8 | -2.8 | | -2.8 |
| Total Lost Time (s) | | 4.0 | 4.0 | 4.0 | | 4.0 | 4.0 | | 4.0 | 4.0 | | 4.0 |
| Lead/Lag | Lead | Lead | Lag | Lag | Lead | Lead | Lag | | | | | |
| Lead-Lag Optimize? | Yes | Yes | Yes | Yes | Yes | Yes | Yes | | | | | |
| Vehicle Extension (s) | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | | 3.0 | 3.0 | | 3.0 |
| Recall Mode | None | None | C-Max | C-Max | None | None | C-Max | | None | None | | None |
| Walk Time (s) | | | 7.0 | 7.0 | | | 7.0 | | 7.0 | 7.0 | | 7.0 |
| Flash Dont Walk (s) | | | 11.0 | 11.0 | | | 11.0 | | 11.0 | 11.0 | | 11.0 |
| Pedestrian Calls (#/hr) | | | 16 | 16 | | | 25 | | 15 | 15 | | 13 |
| Act Effct Green (s) | | 8.8 | 56.4 | 56.4 | | 13.5 | 63.4 | | 38.1 | 38.1 | | 38.1 |
| Actuated g/C Ratio | | 0.07 | 0.47 | 0.47 | | 0.11 | 0.53 | | 0.32 | 0.32 | | 0.32 |

4: Maitland Avenue/Sherbourne Road & Carling Avenue
1995 Carling Avenue

Future (2029) Background Traffic
AM Peak Hour



| Lane Group | SBT | SBR |
|-------------------------|-------|------|
| Lane Configurations | ↔ | |
| Traffic Volume (vph) | 308 | 16 |
| Future Volume (vph) | 308 | 16 |
| Ideal Flow (vphpl) | 1800 | 1800 |
| Storage Length (m) | | 0.0 |
| Storage Lanes | | 0 |
| Taper Length (m) | | |
| Lane Util. Factor | 1.00 | 1.00 |
| Ped Bike Factor | 1.00 | |
| Frt | 0.993 | |
| Flt Protected | | |
| Satd. Flow (prot) | 1765 | 0 |
| Flt Permitted | | |
| Satd. Flow (perm) | 1765 | 0 |
| Right Turn on Red | | Yes |
| Satd. Flow (RTOR) | 2 | |
| Link Speed (k/h) | 50 | |
| Link Distance (m) | 301.0 | |
| Travel Time (s) | 21.7 | |
| Confl. Peds. (#/hr) | | 13 |
| Confl. Bikes (#/hr) | | |
| Peak Hour Factor | 1.00 | 1.00 |
| Heavy Vehicles (%) | 2% | 6% |
| Adj. Flow (vph) | 308 | 16 |
| Shared Lane Traffic (%) | | |
| Lane Group Flow (vph) | 324 | 0 |
| Turn Type | NA | |
| Protected Phases | 6 | |
| Permitted Phases | | |
| Detector Phase | 6 | |
| Switch Phase | | |
| Minimum Initial (s) | 10.0 | |
| Minimum Split (s) | 24.8 | |
| Total Split (s) | 44.0 | |
| Total Split (%) | 36.7% | |
| Maximum Green (s) | 37.2 | |
| Yellow Time (s) | 3.3 | |
| All-Red Time (s) | 3.5 | |
| Lost Time Adjust (s) | -2.8 | |
| Total Lost Time (s) | 4.0 | |
| Lead/Lag | | |
| Lead-Lag Optimize? | | |
| Vehicle Extension (s) | 3.0 | |
| Recall Mode | None | |
| Walk Time (s) | 7.0 | |
| Flash Dont Walk (s) | 11.0 | |
| Pedestrian Calls (#/hr) | 13 | |
| Act Effct Green (s) | 38.1 | |
| Actuated g/C Ratio | 0.32 | |

4: Maitland Avenue/Sherbourne Road & Carling Avenue
1995 Carling Avenue

Future (2029) Background Traffic
AM Peak Hour




| Lane Group | EBU | EBL | EBT | EBR | WBU | WBL | WBT | WBR | NBL | NBT | NBR | SBL |
|------------------------|-----|------|--------|-------|-----|-------|-------|-----|------|--------|-----|-------|
| v/c Ratio | | 0.36 | 0.89 | 0.31 | | 0.83 | 0.18 | | 0.65 | 0.91 | | 0.84 |
| Control Delay | | 61.6 | 38.0 | 3.5 | | 71.9 | 16.0 | | 51.3 | 54.3 | | 103.0 |
| Queue Delay | | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 |
| Total Delay | | 61.6 | 38.0 | 3.5 | | 71.9 | 16.0 | | 51.3 | 54.3 | | 103.0 |
| LOS | | E | D | A | | E | B | | D | D | | F |
| Approach Delay | | | 33.6 | | | | 43.7 | | | 53.7 | | |
| Approach LOS | | | C | | | | D | | | D | | |
| Queue Length 50th (m) | | 10.0 | 160.8 | 0.4 | | 36.3 | 20.3 | | 25.2 | 91.6 | | 14.0 |
| Queue Length 95th (m) | | 22.1 | #208.9 | 14.2 | | #59.3 | 29.0 | | 48.4 | #152.9 | | #40.8 |
| Internal Link Dist (m) | | | 423.3 | | | | 285.6 | | | 276.2 | | |
| Turn Bay Length (m) | | 55.0 | | 130.0 | | 115.0 | | | 75.0 | | | 45.0 |
| Base Capacity (vph) | | 126 | 1593 | 820 | | 362 | 1707 | | 208 | 563 | | 83 |
| Starvation Cap Reductn | | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | | 0 |
| Spillback Cap Reductn | | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | | 0 |
| Storage Cap Reductn | | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | | 0 |
| Reduced v/c Ratio | | 0.35 | 0.89 | 0.31 | | 0.83 | 0.18 | | 0.62 | 0.88 | | 0.80 |

Intersection Summary

Area Type: Other
 Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 40 (33%), Referenced to phase 4:EBT and 8:WBT, Start of Green
 Natural Cycle: 75
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.91
 Intersection Signal Delay: 41.0
 Intersection LOS: D
 Intersection Capacity Utilization 104.6%
 ICU Level of Service G
 Analysis Period (min) 15
 # 95th percentile volume exceeds capacity, queue may be longer.
 Queue shown is maximum after two cycles.

Splits and Phases: 4: Maitland Avenue/Sherbourne Road & Carling Avenue

























| Lane Group | SBT | SBR |
|------------------------|-------|-----|
| v/c Ratio | 0.58 | |
| Control Delay | 38.3 | |
| Queue Delay | 0.0 | |
| Total Delay | 38.3 | |
| LOS | D | |
| Approach Delay | 49.2 | |
| Approach LOS | D | |
| Queue Length 50th (m) | 61.6 | |
| Queue Length 95th (m) | 90.3 | |
| Internal Link Dist (m) | 277.0 | |
| Turn Bay Length (m) | | |
| Base Capacity (vph) | 589 | |
| Starvation Cap Reductn | 0 | |
| Spillback Cap Reductn | 0 | |
| Storage Cap Reductn | 0 | |
| Reduced v/c Ratio | 0.55 | |
| Intersection Summary | | |

1: Iroquois Road & Carling Avenue
1995 Carling Avenue

Future (2029) Background Traffic
PM Peak Hour

| |  |  |  |  |  |  |  |  |  |  |  |  |
|-------------------------|---|---|---|---|---|---|--|---|---|---|---|---|
| Lane Group | EBU | EBL | EBT | EBR | WBU | WBL | WBT | WBR | NBL | NBT | NBR | SBL |
| Lane Configurations | |  |  |  | |  |  |  | |  | |  |
| Traffic Volume (vph) | 2 | 41 | 671 | 4 | 32 | 17 | 1412 | 107 | 13 | 20 | 10 | 117 |
| Future Volume (vph) | 2 | 41 | 671 | 4 | 32 | 17 | 1412 | 107 | 13 | 20 | 10 | 117 |
| Ideal Flow (vphpl) | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 |
| Storage Length (m) | | 25.0 | | 40.0 | | 20.0 | | 85.0 | 0.0 | | 0.0 | 50.0 |
| Storage Lanes | | 1 | | 1 | | 1 | | 1 | 0 | | 0 | 1 |
| Taper Length (m) | | 7.5 | | | | 7.5 | | | 7.5 | | | 7.5 |
| Lane Util. Factor | 0.95 | 1.00 | 0.95 | 1.00 | 0.91 | 1.00 | 0.91 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Ped Bike Factor | | 0.99 | | 0.92 | | 0.98 | | 0.90 | | 0.99 | | 0.98 |
| Frt | | | | 0.850 | | | | 0.850 | | 0.969 | | |
| Flt Protected | | 0.950 | | | | 0.950 | | | | 0.985 | | 0.950 |
| Satd. Flow (prot) | 0 | 1729 | 3390 | 1547 | 0 | 1694 | 4919 | 1547 | 0 | 1726 | 0 | 1712 |
| Flt Permitted | | 0.115 | | | | 0.397 | | | | 0.921 | | 0.761 |
| Satd. Flow (perm) | 0 | 208 | 3390 | 1425 | 0 | 696 | 4919 | 1391 | 0 | 1602 | 0 | 1350 |
| Right Turn on Red | | | | Yes | | | | Yes | | | Yes | |
| Satd. Flow (RTOR) | | | | 95 | | | | 107 | | 10 | | |
| Link Speed (k/h) | | | 60 | | | | 60 | | | 50 | | |
| Link Distance (m) | | | 305.5 | | | | 137.5 | | | 297.2 | | |
| Travel Time (s) | | | 18.3 | | | | 8.3 | | | 21.4 | | |
| Confl. Peds. (#/hr) | | 28 | | 19 | | 19 | | 28 | 28 | | 17 | 17 |
| Confl. Bikes (#/hr) | | | | 6 | | | | | | | | |
| Peak Hour Factor | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Heavy Vehicles (%) | 0% | 0% | 2% | 0% | 0% | 6% | 1% | 0% | 0% | 0% | 0% | 1% |
| Adj. Flow (vph) | 2 | 41 | 671 | 4 | 32 | 17 | 1412 | 107 | 13 | 20 | 10 | 117 |
| Shared Lane Traffic (%) | | | | | | | | | | | | |
| Lane Group Flow (vph) | 0 | 43 | 671 | 4 | 0 | 49 | 1412 | 107 | 0 | 43 | 0 | 117 |
| Turn Type | pm+pt | pm+pt | NA | Perm | pm+pt | pm+pt | NA | Perm | Perm | NA | | Perm |
| Protected Phases | 7 | 7 | 4 | | 3 | 3 | 8 | | | 2 | | |
| Permitted Phases | 4 | 4 | | 4 | 8 | 8 | | 8 | 2 | | | 6 |
| Detector Phase | 7 | 7 | 4 | 4 | 3 | 3 | 8 | 8 | 2 | 2 | | 6 |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 10.0 | 10.0 | | 10.0 |
| Minimum Split (s) | 12.0 | 12.0 | 28.3 | 28.3 | 12.0 | 12.0 | 28.3 | 28.3 | 47.3 | 47.3 | | 47.3 |
| Total Split (s) | 12.0 | 12.0 | 71.0 | 71.0 | 12.0 | 12.0 | 71.0 | 71.0 | 47.0 | 47.0 | | 47.0 |
| Total Split (%) | 9.2% | 9.2% | 54.6% | 54.6% | 9.2% | 9.2% | 54.6% | 54.6% | 36.2% | 36.2% | | 36.2% |
| Maximum Green (s) | 5.0 | 5.0 | 64.7 | 64.7 | 5.0 | 5.0 | 64.7 | 64.7 | 39.7 | 39.7 | | 39.7 |
| Yellow Time (s) | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.3 | 3.3 | | 3.3 |
| All-Red Time (s) | 3.3 | 3.3 | 2.6 | 2.6 | 3.3 | 3.3 | 2.6 | 2.6 | 4.0 | 4.0 | | 4.0 |
| Lost Time Adjust (s) | | -3.0 | -2.3 | -2.3 | | | -3.0 | -2.3 | -2.3 | | -3.3 | -3.3 |
| Total Lost Time (s) | | 4.0 | 4.0 | 4.0 | | | 4.0 | 4.0 | 4.0 | | 4.0 | 4.0 |
| Lead/Lag | Lead | Lead | Lag | Lag | Lead | Lead | Lag | Lag | | | | |
| Lead-Lag Optimize? | Yes | Yes | Yes | Yes | Yes | Yes | Yes | Yes | | | | |
| Vehicle Extension (s) | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | | 3.0 |
| Recall Mode | Max | Max | C-Max | C-Max | None | None | C-Max | C-Max | None | None | | None |
| Walk Time (s) | | | 10.0 | 10.0 | | | 10.0 | 10.0 | 27.0 | 27.0 | | 27.0 |
| Flash Dont Walk (s) | | | 12.0 | 12.0 | | | 12.0 | 12.0 | 13.0 | 13.0 | | 13.0 |
| Pedestrian Calls (#/hr) | | | 19 | 19 | | | 28 | 28 | 17 | 17 | | 28 |
| Act Effct Green (s) | | 87.7 | 80.3 | 80.3 | | | 75.3 | 67.0 | 67.0 | 31.9 | | 31.9 |
| Actuated g/C Ratio | | 0.67 | 0.62 | 0.62 | | | 0.58 | 0.52 | 0.52 | 0.25 | | 0.25 |

1: Iroquois Road & Carling Avenue
 1995 Carling Avenue


Future (2029) Background Traffic
 PM Peak Hour



| Lane Group | SBT | SBR |
|-------------------------|-------|------|
| Lane Configurations | ↔ | |
| Traffic Volume (vph) | 23 | 60 |
| Future Volume (vph) | 23 | 60 |
| Ideal Flow (vphpl) | 1800 | 1800 |
| Storage Length (m) | | 0.0 |
| Storage Lanes | | 0 |
| Taper Length (m) | | |
| Lane Util. Factor | 1.00 | 1.00 |
| Ped Bike Factor | 0.97 | |
| Frt | 0.892 | |
| Flt Protected | | |
| Satd. Flow (prot) | 1554 | 0 |
| Flt Permitted | | |
| Satd. Flow (perm) | 1554 | 0 |
| Right Turn on Red | | Yes |
| Satd. Flow (RTOR) | 32 | |
| Link Speed (k/h) | 50 | |
| Link Distance (m) | 304.9 | |
| Travel Time (s) | 22.0 | |
| Confl. Peds. (#/hr) | | 28 |
| Confl. Bikes (#/hr) | | 2 |
| Peak Hour Factor | 1.00 | 1.00 |
| Heavy Vehicles (%) | 0% | 2% |
| Adj. Flow (vph) | 23 | 60 |
| Shared Lane Traffic (%) | | |
| Lane Group Flow (vph) | 83 | 0 |
| Turn Type | NA | |
| Protected Phases | 6 | |
| Permitted Phases | | |
| Detector Phase | 6 | |
| Switch Phase | | |
| Minimum Initial (s) | 10.0 | |
| Minimum Split (s) | 47.3 | |
| Total Split (s) | 47.0 | |
| Total Split (%) | 36.2% | |
| Maximum Green (s) | 39.7 | |
| Yellow Time (s) | 3.3 | |
| All-Red Time (s) | 4.0 | |
| Lost Time Adjust (s) | -3.3 | |
| Total Lost Time (s) | 4.0 | |
| Lead/Lag | | |
| Lead-Lag Optimize? | | |
| Vehicle Extension (s) | 3.0 | |
| Recall Mode | None | |
| Walk Time (s) | 27.0 | |
| Flash Dont Walk (s) | 13.0 | |
| Pedestrian Calls (#/hr) | 28 | |
| Act Effct Green (s) | 31.9 | |
| Actuated g/C Ratio | 0.25 | |

1: Iroquois Road & Carling Avenue
1995 Carling Avenue

Future (2029) Background Traffic
PM Peak Hour




| Lane Group | EBU | EBL | EBT | EBR | WBU | WBL | WBT | WBR | NBL | NBT | NBR | SBL |
|------------------------|-----|------|-------|------|-----|------|-------|------|-----|-------|-----|------|
| v/c Ratio | | 0.12 | 0.32 | 0.00 | | 0.11 | 0.56 | 0.14 | | 0.11 | | 0.35 |
| Control Delay | | 10.2 | 15.2 | 0.0 | | 10.4 | 22.5 | 3.3 | | 26.5 | | 40.4 |
| Queue Delay | | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 | | 0.0 | | 0.0 |
| Total Delay | | 10.2 | 15.2 | 0.0 | | 10.4 | 22.5 | 3.3 | | 26.5 | | 40.4 |
| LOS | | B | B | A | | B | C | A | | C | | D |
| Approach Delay | | | 14.8 | | | | 20.8 | | | 26.5 | | |
| Approach LOS | | | B | | | | C | | | C | | |
| Queue Length 50th (m) | | 4.2 | 53.0 | 0.0 | | 4.8 | 87.2 | 0.0 | | 5.8 | | 21.9 |
| Queue Length 95th (m) | | 9.0 | 67.0 | 0.0 | | 10.0 | 100.9 | 8.9 | | 14.4 | | 37.8 |
| Internal Link Dist (m) | | | 281.5 | | | | 113.5 | | | 273.2 | | |
| Turn Bay Length (m) | | 25.0 | | 40.0 | | 20.0 | | 85.0 | | | | 50.0 |
| Base Capacity (vph) | | 364 | 2095 | 917 | | 466 | 2535 | 768 | | 536 | | 446 |
| Starvation Cap Reductn | | 0 | 0 | 0 | | 0 | 0 | 0 | | 0 | | 0 |
| Spillback Cap Reductn | | 0 | 0 | 0 | | 0 | 0 | 0 | | 0 | | 0 |
| Storage Cap Reductn | | 0 | 0 | 0 | | 0 | 0 | 0 | | 0 | | 0 |
| Reduced v/c Ratio | | 0.12 | 0.32 | 0.00 | | 0.11 | 0.56 | 0.14 | | 0.08 | | 0.26 |

Intersection Summary

| | |
|-----------------------------------|---|
| Area Type: | Other |
| Cycle Length: | 130 |
| Actuated Cycle Length: | 130 |
| Offset: | 95 (73%), Referenced to phase 4:EBTL and 8:WBTL, Start of Green |
| Natural Cycle: | 90 |
| Control Type: | Actuated-Coordinated |
| Maximum v/c Ratio: | 0.56 |
| Intersection Signal Delay: | 20.1 |
| Intersection LOS: | C |
| Intersection Capacity Utilization | 68.5% |
| ICU Level of Service | C |
| Analysis Period (min) | 15 |

Splits and Phases: 1: Iroquois Road & Carling Avenue





| Lane Group | SBT | SBR |
|-----------------------------|-------|-----|
| v/c Ratio | 0.20 | |
| Control Delay | 22.0 | |
| Queue Delay | 0.0 | |
| Total Delay | 22.0 | |
| LOS | C | |
| Approach Delay | 32.8 | |
| Approach LOS | C | |
| Queue Length 50th (m) | 9.0 | |
| Queue Length 95th (m) | 21.1 | |
| Internal Link Dist (m) | 280.9 | |
| Turn Bay Length (m) | | |
| Base Capacity (vph) | 535 | |
| Starvation Cap Reductn | 0 | |
| Spillback Cap Reductn | 0 | |
| Storage Cap Reductn | 0 | |
| Reduced v/c Ratio | 0.16 | |
| Intersection Summary | | |

2: Hare Avenue & Carling Avenue
 1995 Carling Avenue

Future (2029) Background Traffic
 PM Peak Hour

| Intersection | | | | | | |
|--------------------------|------|------|------|------|------|------|
| Int Delay, s/veh | 0.4 | | | | | |
| Movement | EBT | EBR | WBL | WBT | NBL | NBR |
| Lane Configurations | ↑↑ | ↑ | ↓ | ↑↑ | ↓ | ↓ |
| Traffic Vol, veh/h | 817 | 8 | 37 | 1553 | 10 | 11 |
| Future Vol, veh/h | 817 | 8 | 37 | 1553 | 10 | 11 |
| Conflicting Peds, #/hr | 0 | 0 | 0 | 0 | 0 | 0 |
| Sign Control | Free | Free | Free | Free | Stop | Stop |
| RT Channelized | - | None | - | None | - | None |
| Storage Length | - | 350 | 250 | - | 0 | - |
| Veh in Median Storage, # | 0 | - | - | 0 | 0 | - |
| Grade, % | 0 | - | - | 0 | 0 | - |
| Peak Hour Factor | 100 | 100 | 100 | 100 | 100 | 100 |
| Heavy Vehicles, % | 0 | 0 | 0 | 0 | 0 | 0 |
| Mvmt Flow | 817 | 8 | 37 | 1553 | 10 | 11 |

| Major/Minor | Major1 | | Major2 | | Minor1 | |
|----------------------|--------|---|--------|---|--------|-----|
| Conflicting Flow All | 0 | 0 | 825 | 0 | 1668 | 409 |
| Stage 1 | - | - | - | - | 817 | - |
| Stage 2 | - | - | - | - | 851 | - |
| Critical Hdwy | - | - | 4.1 | - | 6.8 | 6.9 |
| Critical Hdwy Stg 1 | - | - | - | - | 5.8 | - |
| Critical Hdwy Stg 2 | - | - | - | - | 5.8 | - |
| Follow-up Hdwy | - | - | 2.2 | - | 3.5 | 3.3 |
| Pot Cap-1 Maneuver | - | - | 814 | - | 89 | 597 |
| Stage 1 | - | - | - | - | 400 | - |
| Stage 2 | - | - | - | - | 384 | - |
| Platoon blocked, % | - | - | - | - | - | - |
| Mov Cap-1 Maneuver | - | - | 814 | - | 85 | 597 |
| Mov Cap-2 Maneuver | - | - | - | - | 85 | - |
| Stage 1 | - | - | - | - | 400 | - |
| Stage 2 | - | - | - | - | 367 | - |

| Approach | EB | WB | NB |
|----------------------|----|-----|----|
| HCM Control Delay, s | 0 | 0.2 | 32 |
| HCM LOS | | | D |

| Minor Lane/Major Mvmt | NBLn1 | EBT | EBR | WBL | WBT |
|-----------------------|-------|-----|-----|-------|-----|
| Capacity (veh/h) | 154 | - | - | 814 | - |
| HCM Lane V/C Ratio | 0.136 | - | - | 0.045 | - |
| HCM Control Delay (s) | 32 | - | - | 9.6 | - |
| HCM Lane LOS | D | - | - | A | - |
| HCM 95th %tile Q(veh) | 0.5 | - | - | 0.1 | - |

3: Carling Avenue & Bromley Road
 1995 Carling Avenue

Future (2029) Background Traffic
 PM Peak Hour

| Intersection | | | | | | |
|--------------------------|------|------|------|------|------|------|
| Int Delay, s/veh | 0.1 | | | | | |
| Movement | EBL | EBT | WBT | WBR | SBL | SBR |
| Lane Configurations | | ↑↑ | ↑↑ | ↑ | | ↑ |
| Traffic Vol, veh/h | 0 | 826 | 1576 | 16 | 0 | 12 |
| Future Vol, veh/h | 0 | 826 | 1576 | 16 | 0 | 12 |
| Conflicting Peds, #/hr | 0 | 0 | 0 | 0 | 0 | 0 |
| Sign Control | Free | Free | Free | Free | Stop | Stop |
| RT Channelized | - | None | - | None | - | None |
| Storage Length | - | - | - | 300 | - | 0 |
| Veh in Median Storage, # | - | 0 | 0 | - | 0 | - |
| Grade, % | - | 0 | 0 | - | 0 | - |
| Peak Hour Factor | 100 | 100 | 100 | 100 | 100 | 100 |
| Heavy Vehicles, % | 0 | 0 | 0 | 0 | 0 | 8 |
| Mvmt Flow | 0 | 826 | 1576 | 16 | 0 | 12 |


| Major/Minor | Major1 | Major2 | Minor2 | | |
|----------------------|--------|--------|--------|---|------|
| Conflicting Flow All | - | 0 | - | 0 | 788 |
| Stage 1 | - | - | - | - | - |
| Stage 2 | - | - | - | - | - |
| Critical Hdwy | - | - | - | - | 7.06 |
| Critical Hdwy Stg 1 | - | - | - | - | - |
| Critical Hdwy Stg 2 | - | - | - | - | - |
| Follow-up Hdwy | - | - | - | - | 3.38 |
| Pot Cap-1 Maneuver | 0 | - | - | - | 321 |
| Stage 1 | 0 | - | - | - | - |
| Stage 2 | 0 | - | - | - | - |
| Platoon blocked, % | - | - | - | - | - |
| Mov Cap-1 Maneuver | - | - | - | - | 321 |
| Mov Cap-2 Maneuver | - | - | - | - | - |
| Stage 1 | - | - | - | - | - |
| Stage 2 | - | - | - | - | - |

| Approach | EB | WB | SB |
|----------------------|----|----|------|
| HCM Control Delay, s | 0 | 0 | 16.7 |
| HCM LOS | | | C |

| Minor Lane/Major Mvmt | EBT | WBT | WBR | SBLn1 |
|-----------------------|-----|-----|-----|-------|
| Capacity (veh/h) | - | - | - | 321 |
| HCM Lane V/C Ratio | - | - | - | 0.037 |
| HCM Control Delay (s) | - | - | - | 16.7 |
| HCM Lane LOS | - | - | - | C |
| HCM 95th %tile Q(veh) | - | - | - | 0.1 |

4: Maitland Avenue/Sherbourne Road & Carling Avenue
1995 Carling Avenue

Future (2029) Background Traffic
PM Peak Hour



| Lane Group | EBU | EBL | EBT | EBR | WBU | WBL | WBT | WBR | NBL | NBT | NBR | SBL |
|-------------------------|------|-------|-------|-------|-------|-------|-------|------|-------|-------|------|-------|
| Lane Configurations | | | | | | | | | | | | |
| Traffic Volume (vph) | 22 | 60 | 578 | 167 | 8 | 715 | 1309 | 53 | 216 | 208 | 208 | 47 |
| Future Volume (vph) | 22 | 60 | 578 | 167 | 8 | 715 | 1309 | 53 | 216 | 208 | 208 | 47 |
| Ideal Flow (vphpl) | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 |
| Storage Length (m) | | 55.0 | | 130.0 | | 115.0 | | 0.0 | 75.0 | | 0.0 | 45.0 |
| Storage Lanes | | 1 | | 1 | | 1 | | 0 | 1 | | 0 | 1 |
| Taper Length (m) | | 7.5 | | | | 7.5 | | | 7.5 | | | 7.5 |
| Lane Util. Factor | 0.95 | 1.00 | 0.95 | 1.00 | 0.95 | 0.97 | 0.95 | 0.95 | 1.00 | 1.00 | 1.00 | 1.00 |
| Ped Bike Factor | | 0.98 | | 0.94 | | 0.96 | 0.99 | | 0.98 | 0.98 | | |
| Frt | | | | 0.850 | | | 0.994 | | | 0.925 | | |
| Flt Protected | | 0.950 | | | | 0.950 | | | 0.950 | | | 0.950 |
| Satd. Flow (prot) | 0 | 1729 | 3390 | 1532 | 0 | 3321 | 3381 | 0 | 1729 | 1624 | 0 | 1729 |
| Flt Permitted | | 0.950 | | | | 0.950 | | | 0.466 | | | 0.226 |
| Satd. Flow (perm) | 0 | 1698 | 3390 | 1438 | 0 | 3197 | 3381 | 0 | 829 | 1624 | 0 | 411 |
| Right Turn on Red | | | | Yes | | | | Yes | | | Yes | |
| Satd. Flow (RTOR) | | | | 167 | | | 4 | | | 49 | | |
| Link Speed (k/h) | | | 60 | | | | 60 | | | 50 | | |
| Link Distance (m) | | | 447.3 | | | | 309.6 | | | 300.2 | | |
| Travel Time (s) | | | 26.8 | | | | 18.6 | | | 21.6 | | |
| Confl. Peds. (#/hr) | | 36 | | 25 | | 25 | | 36 | 20 | | 15 | 15 |
| Confl. Bikes (#/hr) | | | | | | | | 2 | | | | |
| Peak Hour Factor | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Heavy Vehicles (%) | 0% | 0% | 2% | 1% | 0% | 1% | 1% | 4% | 0% | 0% | 3% | 0% |
| Adj. Flow (vph) | 22 | 60 | 578 | 167 | 8 | 715 | 1309 | 53 | 216 | 208 | 208 | 47 |
| Shared Lane Traffic (%) | | | | | | | | | | | | |
| Lane Group Flow (vph) | 0 | 82 | 578 | 167 | 0 | 723 | 1362 | 0 | 216 | 416 | 0 | 47 |
| Turn Type | Prot | Prot | NA | Perm | Prot | Prot | NA | | Perm | NA | | Perm |
| Protected Phases | 7 | 7 | 4 | | 3 | 3 | 8 | | | 2 | | |
| Permitted Phases | | | | 4 | | | | | 2 | | | 6 |
| Detector Phase | 7 | 7 | 4 | 4 | 3 | 3 | 8 | | 2 | 2 | | 6 |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | | 10.0 | 10.0 | | 10.0 |
| Minimum Split (s) | 10.9 | 10.9 | 23.9 | 23.9 | 10.9 | 10.9 | 23.9 | | 24.8 | 24.8 | | 24.8 |
| Total Split (s) | 11.0 | 11.0 | 33.0 | 33.0 | 37.0 | 37.0 | 59.0 | | 50.0 | 50.0 | | 50.0 |
| Total Split (%) | 9.2% | 9.2% | 27.5% | 27.5% | 30.8% | 30.8% | 49.2% | | 41.7% | 41.7% | | 41.7% |
| Maximum Green (s) | 5.1 | 5.1 | 27.1 | 27.1 | 31.1 | 31.1 | 53.1 | | 43.2 | 43.2 | | 43.2 |
| Yellow Time (s) | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | | 3.3 | 3.3 | | 3.3 |
| All-Red Time (s) | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | | 3.5 | 3.5 | | 3.5 |
| Lost Time Adjust (s) | | -1.9 | -1.9 | -1.9 | | -1.9 | -1.9 | | -2.8 | -2.8 | | -2.8 |
| Total Lost Time (s) | | 4.0 | 4.0 | 4.0 | | 4.0 | 4.0 | | 4.0 | 4.0 | | 4.0 |
| Lead/Lag | Lead | Lead | Lag | Lag | Lead | Lead | Lag | | | | | |
| Lead-Lag Optimize? | Yes | Yes | Yes | Yes | Yes | Yes | Yes | | | | | |
| Vehicle Extension (s) | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | | 3.0 | 3.0 | | 3.0 |
| Recall Mode | None | None | C-Max | C-Max | None | None | C-Max | | None | None | | None |
| Walk Time (s) | | | 7.0 | 7.0 | | | 7.0 | | 7.0 | 7.0 | | 7.0 |
| Flash Dont Walk (s) | | | 11.0 | 11.0 | | | 11.0 | | 11.0 | 11.0 | | 11.0 |
| Pedestrian Calls (#/hr) | | | 25 | 25 | | | 36 | | 15 | 15 | | 20 |
| Act Effct Green (s) | | 10.6 | 39.3 | 39.3 | | 31.6 | 60.3 | | 37.1 | 37.1 | | 37.1 |
| Actuated g/C Ratio | | 0.09 | 0.33 | 0.33 | | 0.26 | 0.50 | | 0.31 | 0.31 | | 0.31 |

4: Maitland Avenue/Sherbourne Road & Carling Avenue
 1995 Carling Avenue


Future (2029) Background Traffic
 PM Peak Hour



| Lane Group | SBT | SBR |
|-------------------------|-------|------|
| Lane Configurations | ↔ | |
| Traffic Volume (vph) | 196 | 44 |
| Future Volume (vph) | 196 | 44 |
| Ideal Flow (vphpl) | 1800 | 1800 |
| Storage Length (m) | | 0.0 |
| Storage Lanes | | 0 |
| Taper Length (m) | | |
| Lane Util. Factor | 1.00 | 1.00 |
| Ped Bike Factor | 0.99 | |
| Frt | 0.972 | |
| Flt Protected | | |
| Satd. Flow (prot) | 1746 | 0 |
| Flt Permitted | | |
| Satd. Flow (perm) | 1746 | 0 |
| Right Turn on Red | | Yes |
| Satd. Flow (RTOR) | 11 | |
| Link Speed (k/h) | 50 | |
| Link Distance (m) | 301.0 | |
| Travel Time (s) | 21.7 | |
| Confl. Peds. (#/hr) | | 20 |
| Confl. Bikes (#/hr) | | |
| Peak Hour Factor | 1.00 | 1.00 |
| Heavy Vehicles (%) | 0% | 2% |
| Adj. Flow (vph) | 196 | 44 |
| Shared Lane Traffic (%) | | |
| Lane Group Flow (vph) | 240 | 0 |
| Turn Type | NA | |
| Protected Phases | 6 | |
| Permitted Phases | | |
| Detector Phase | 6 | |
| Switch Phase | | |
| Minimum Initial (s) | 10.0 | |
| Minimum Split (s) | 24.8 | |
| Total Split (s) | 50.0 | |
| Total Split (%) | 41.7% | |
| Maximum Green (s) | 43.2 | |
| Yellow Time (s) | 3.3 | |
| All-Red Time (s) | 3.5 | |
| Lost Time Adjust (s) | -2.8 | |
| Total Lost Time (s) | 4.0 | |
| Lead/Lag | | |
| Lead-Lag Optimize? | | |
| Vehicle Extension (s) | 3.0 | |
| Recall Mode | None | |
| Walk Time (s) | 7.0 | |
| Flash Dont Walk (s) | 11.0 | |
| Pedestrian Calls (#/hr) | 20 | |
| Act Effct Green (s) | 37.1 | |
| Actuated g/C Ratio | 0.31 | |

4: Maitland Avenue/Sherbourne Road & Carling Avenue
1995 Carling Avenue

Future (2029) Background Traffic
PM Peak Hour




| Lane Group | EBU | EBL | EBT | EBR | WBU | WBL | WBT | WBR | NBL | NBT | NBR | SBL |
|------------------------|-----|-------|-------|-------|-----|-------|-------|-----|------|-------|-----|------|
| v/c Ratio | | 0.54 | 0.52 | 0.29 | | 0.83 | 0.80 | | 0.84 | 0.78 | | 0.37 |
| Control Delay | | 66.6 | 37.2 | 6.9 | | 50.3 | 30.6 | | 65.6 | 42.8 | | 38.6 |
| Queue Delay | | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 |
| Total Delay | | 66.6 | 37.2 | 6.9 | | 50.3 | 30.6 | | 65.6 | 42.8 | | 38.6 |
| LOS | | E | D | A | | D | C | | E | D | | D |
| Approach Delay | | | 34.0 | | | | 37.4 | | | 50.6 | | |
| Approach LOS | | | C | | | | D | | | D | | |
| Queue Length 50th (m) | | 18.2 | 59.2 | 0.0 | | 81.6 | 146.1 | | 47.1 | 78.8 | | 8.6 |
| Queue Length 95th (m) | | #47.8 | 85.7 | 16.8 | | 103.8 | 181.8 | | 72.2 | 104.7 | | 18.5 |
| Internal Link Dist (m) | | | 423.3 | | | | 285.6 | | | 276.2 | | |
| Turn Bay Length (m) | | 55.0 | | 130.0 | | 115.0 | | | 75.0 | | | 45.0 |
| Base Capacity (vph) | | 152 | 1110 | 583 | | 928 | 1701 | | 317 | 652 | | 157 |
| Starvation Cap Reductn | | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | | 0 |
| Spillback Cap Reductn | | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | | 0 |
| Storage Cap Reductn | | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | | 0 |
| Reduced v/c Ratio | | 0.54 | 0.52 | 0.29 | | 0.78 | 0.80 | | 0.68 | 0.64 | | 0.30 |

Intersection Summary

Area Type: Other
 Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 103 (86%), Referenced to phase 4:EBT and 8:WBT, Start of Green
 Natural Cycle: 80
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.84
 Intersection Signal Delay: 38.6
 Intersection LOS: D
 Intersection Capacity Utilization 92.3%
 ICU Level of Service F
 Analysis Period (min) 15
 # 95th percentile volume exceeds capacity, queue may be longer.
 Queue shown is maximum after two cycles.

Splits and Phases: 4: Maitland Avenue/Sherbourne Road & Carling Avenue






| Lane Group | SBT | SBR |
|-----------------------------|-------|-----|
| v/c Ratio | 0.44 | |
| Control Delay | 32.8 | |
| Queue Delay | 0.0 | |
| Total Delay | 32.8 | |
| LOS | C | |
| Approach Delay | 33.8 | |
| Approach LOS | C | |
| Queue Length 50th (m) | 42.7 | |
| Queue Length 95th (m) | 59.0 | |
| Internal Link Dist (m) | 277.0 | |
| Turn Bay Length (m) | | |
| Base Capacity (vph) | 676 | |
| Starvation Cap Reductn | 0 | |
| Spillback Cap Reductn | 0 | |
| Storage Cap Reductn | 0 | |
| Reduced v/c Ratio | 0.36 | |
| Intersection Summary | | |

1: Iroquois Road & Carling Avenue
1995 Carling Avenue

Future (2024) Total Traffic
AM Peak Hour



| Lane Group | EBU | EBL | EBT | EBR | WBU | WBL | WBT | WBR | NBL | NBT | NBR | SBL |
|-------------------------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|------|-------|
| Lane Configurations | | ↔ | ↕↕ | ↗ | | ↔ | ↕↕↕ | ↗ | | ↕↕ | | ↗ |
| Traffic Volume (vph) | 1 | 19 | 1630 | 5 | 39 | 7 | 400 | 60 | 3 | 24 | 30 | 75 |
| Future Volume (vph) | 1 | 19 | 1630 | 5 | 39 | 7 | 400 | 60 | 3 | 24 | 30 | 75 |
| Ideal Flow (vphpl) | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 |
| Storage Length (m) | | 25.0 | | 40.0 | | 20.0 | | 85.0 | 0.0 | | 0.0 | 50.0 |
| Storage Lanes | | 1 | | 1 | | 1 | | 1 | 0 | | 0 | 1 |
| Taper Length (m) | | 7.5 | | | | 7.5 | | | 7.5 | | | 7.5 |
| Lane Util. Factor | 0.95 | 1.00 | 0.95 | 1.00 | 0.91 | 1.00 | 0.91 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Ped Bike Factor | | 0.98 | | 0.94 | | | | 0.94 | | 0.99 | | 0.99 |
| Frt | | | | 0.850 | | | | 0.850 | | 0.929 | | |
| Flt Protected | | 0.950 | | | | 0.950 | | | | 0.997 | | 0.950 |
| Satd. Flow (prot) | 0 | 1729 | 3390 | 1547 | 0 | 1729 | 4687 | 1502 | 0 | 1635 | 0 | 1679 |
| Flt Permitted | | 0.464 | | | | 0.119 | | | | 0.990 | | 0.717 |
| Satd. Flow (perm) | 0 | 824 | 3390 | 1461 | 0 | 217 | 4687 | 1406 | 0 | 1623 | 0 | 1254 |
| Right Turn on Red | | | | Yes | | | | Yes | | | Yes | |
| Satd. Flow (RTOR) | | | | 95 | | | | 95 | | | 30 | |
| Link Speed (k/h) | | | 60 | | | | 60 | | | 50 | | |
| Link Distance (m) | | | 305.5 | | | | 136.9 | | | 297.2 | | |
| Travel Time (s) | | | 18.3 | | | | 8.2 | | | 21.4 | | |
| Confl. Peds. (#/hr) | | 15 | | 12 | | 12 | | 15 | 13 | | 12 | 12 |
| Confl. Bikes (#/hr) | | | | 1 | | | | 1 | | | 4 | |
| Peak Hour Factor | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Heavy Vehicles (%) | 0% | 0% | 2% | 0% | 0% | 0% | 6% | 3% | 0% | 4% | 0% | 3% |
| Adj. Flow (vph) | 1 | 19 | 1630 | 5 | 39 | 7 | 400 | 60 | 3 | 24 | 30 | 75 |
| Shared Lane Traffic (%) | | | | | | | | | | | | |
| Lane Group Flow (vph) | 0 | 20 | 1630 | 5 | 0 | 46 | 400 | 60 | 0 | 57 | 0 | 75 |
| Turn Type | pm+pt | pm+pt | NA | Perm | pm+pt | pm+pt | NA | Perm | Perm | NA | | Perm |
| Protected Phases | 7 | 7 | 4 | | 3 | 3 | 8 | | | 2 | | |
| Permitted Phases | 4 | 4 | | 4 | 8 | 8 | | 8 | 2 | | | 6 |
| Detector Phase | 7 | 7 | 4 | 4 | 3 | 3 | 8 | 8 | 2 | 2 | | 6 |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 10.0 | 10.0 | | 10.0 |
| Minimum Split (s) | 12.0 | 12.0 | 28.3 | 28.3 | 12.0 | 12.0 | 28.3 | 28.3 | 47.3 | 47.3 | | 47.3 |
| Total Split (s) | 14.0 | 14.0 | 69.0 | 69.0 | 14.0 | 14.0 | 69.0 | 69.0 | 47.0 | 47.0 | | 47.0 |
| Total Split (%) | 10.8% | 10.8% | 53.1% | 53.1% | 10.8% | 10.8% | 53.1% | 53.1% | 36.2% | 36.2% | | 36.2% |
| Maximum Green (s) | 7.0 | 7.0 | 62.7 | 62.7 | 7.0 | 7.0 | 62.7 | 62.7 | 39.7 | 39.7 | | 39.7 |
| Yellow Time (s) | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.3 | 3.3 | | 3.3 |
| All-Red Time (s) | 3.3 | 3.3 | 2.6 | 2.6 | 3.3 | 3.3 | 2.6 | 2.6 | 4.0 | 4.0 | | 4.0 |
| Lost Time Adjust (s) | | -3.0 | -2.3 | -2.3 | | | -3.0 | -2.3 | -2.3 | | -3.3 | -3.3 |
| Total Lost Time (s) | | 4.0 | 4.0 | 4.0 | | | 4.0 | 4.0 | 4.0 | | 4.0 | 4.0 |
| Lead/Lag | Lead | Lead | Lag | Lag | Lead | Lead | Lag | Lag | | | | |
| Lead-Lag Optimize? | Yes | Yes | Yes | Yes | Yes | Yes | Yes | Yes | | | | |
| Vehicle Extension (s) | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | | 3.0 |
| Recall Mode | Max | Max | C-Max | C-Max | None | None | C-Max | C-Max | None | None | | None |
| Walk Time (s) | | | 10.0 | 10.0 | | | 10.0 | 10.0 | 27.0 | 27.0 | | 27.0 |
| Flash Dont Walk (s) | | | 12.0 | 12.0 | | | 12.0 | 12.0 | 13.0 | 13.0 | | 13.0 |
| Pedestrian Calls (#/hr) | | | 12 | 12 | | | 15 | 15 | 12 | 12 | | 13 |
| Act Effct Green (s) | | 98.0 | 89.6 | 89.6 | | 74.3 | 65.0 | 65.0 | | 25.9 | | 25.9 |
| Actuated g/C Ratio | | 0.75 | 0.69 | 0.69 | | 0.57 | 0.50 | 0.50 | | 0.20 | | 0.20 |

1: Iroquois Road & Carling Avenue
 1995 Carling Avenue


Future (2024) Total Traffic
 AM Peak Hour



| Lane Group | SBT | SBR |
|-------------------------|-------|------|
| Lane Configurations | ↔ | |
| Traffic Volume (vph) | 7 | 27 |
| Future Volume (vph) | 7 | 27 |
| Ideal Flow (vphpl) | 1800 | 1800 |
| Storage Length (m) | | 0.0 |
| Storage Lanes | | 0 |
| Taper Length (m) | | |
| Lane Util. Factor | 1.00 | 1.00 |
| Ped Bike Factor | 0.98 | |
| Frt | 0.881 | |
| Flt Protected | | |
| Satd. Flow (prot) | 1490 | 0 |
| Flt Permitted | | |
| Satd. Flow (perm) | 1490 | 0 |
| Right Turn on Red | | Yes |
| Satd. Flow (RTOR) | 27 | |
| Link Speed (k/h) | 50 | |
| Link Distance (m) | 304.9 | |
| Travel Time (s) | 22.0 | |
| Confl. Peds. (#/hr) | | 13 |
| Confl. Bikes (#/hr) | | |
| Peak Hour Factor | 1.00 | 1.00 |
| Heavy Vehicles (%) | 0% | 7% |
| Adj. Flow (vph) | 7 | 27 |
| Shared Lane Traffic (%) | | |
| Lane Group Flow (vph) | 34 | 0 |
| Turn Type | NA | |
| Protected Phases | 6 | |
| Permitted Phases | | |
| Detector Phase | 6 | |
| Switch Phase | | |
| Minimum Initial (s) | 10.0 | |
| Minimum Split (s) | 47.3 | |
| Total Split (s) | 47.0 | |
| Total Split (%) | 36.2% | |
| Maximum Green (s) | 39.7 | |
| Yellow Time (s) | 3.3 | |
| All-Red Time (s) | 4.0 | |
| Lost Time Adjust (s) | -3.3 | |
| Total Lost Time (s) | 4.0 | |
| Lead/Lag | | |
| Lead-Lag Optimize? | | |
| Vehicle Extension (s) | 3.0 | |
| Recall Mode | None | |
| Walk Time (s) | 27.0 | |
| Flash Dont Walk (s) | 13.0 | |
| Pedestrian Calls (#/hr) | 13 | |
| Act Effct Green (s) | 25.9 | |
| Actuated g/C Ratio | 0.20 | |

1: Iroquois Road & Carling Avenue
1995 Carling Avenue

Future (2024) Total Traffic
AM Peak Hour




| Lane Group | EBU | EBL | EBT | EBR | WBU | WBL | WBT | WBR | NBL | NBT | NBR | SBL |
|------------------------|-----|------|--------|------|-----|------|-------|------|-----|-------|-----|------|
| v/c Ratio | | 0.02 | 0.70 | 0.00 | | 0.20 | 0.17 | 0.08 | | 0.16 | | 0.30 |
| Control Delay | | 8.3 | 20.8 | 0.0 | | 11.4 | 18.0 | 1.1 | | 20.4 | | 43.3 |
| Queue Delay | | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 | | 0.0 | | 0.0 |
| Total Delay | | 8.3 | 20.8 | 0.0 | | 11.4 | 18.0 | 1.1 | | 20.4 | | 43.3 |
| LOS | | A | C | A | | B | B | A | | C | | D |
| Approach Delay | | | 20.5 | | | | 15.4 | | | 20.4 | | |
| Approach LOS | | | C | | | | B | | | C | | |
| Queue Length 50th (m) | | 0.8 | 109.3 | 0.0 | | 2.6 | 19.9 | 0.0 | | 6.2 | | 18.2 |
| Queue Length 95th (m) | | 5.2 | #261.4 | 0.0 | | 9.6 | 26.4 | 2.4 | | 14.4 | | 25.9 |
| Internal Link Dist (m) | | | 281.5 | | | | 112.9 | | | 273.2 | | |
| Turn Bay Length (m) | | 25.0 | | 40.0 | | 20.0 | | 85.0 | | | | 50.0 |
| Base Capacity (vph) | | 834 | 2337 | 1037 | | 241 | 2343 | 750 | | 556 | | 414 |
| Starvation Cap Reductn | | 0 | 0 | 0 | | 0 | 0 | 0 | | 0 | | 0 |
| Spillback Cap Reductn | | 0 | 0 | 0 | | 0 | 0 | 0 | | 0 | | 0 |
| Storage Cap Reductn | | 0 | 0 | 0 | | 0 | 0 | 0 | | 0 | | 0 |
| Reduced v/c Ratio | | 0.02 | 0.70 | 0.00 | | 0.19 | 0.17 | 0.08 | | 0.10 | | 0.18 |

Intersection Summary

Area Type: Other
 Cycle Length: 130
 Actuated Cycle Length: 130
 Offset: 6 (5%), Referenced to phase 4:EBTL and 8:WBTL, Start of Green
 Natural Cycle: 120
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.70
 Intersection Signal Delay: 20.1 Intersection LOS: C
 Intersection Capacity Utilization 73.1% ICU Level of Service D
 Analysis Period (min) 15
 # 95th percentile volume exceeds capacity, queue may be longer.
 Queue shown is maximum after two cycles.

Splits and Phases: 1: Iroquois Road & Carling Avenue



1: Iroquois Road & Carling Avenue
 1995 Carling Avenue

Future (2024) Total Traffic
 AM Peak Hour



| Lane Group | SBT | SBR |
|------------------------|-------|-----|
| v/c Ratio | 0.11 | |
| Control Delay | 14.5 | |
| Queue Delay | 0.0 | |
| Total Delay | 14.5 | |
| LOS | B | |
| Approach Delay | 34.3 | |
| Approach LOS | C | |
| Queue Length 50th (m) | 1.6 | |
| Queue Length 95th (m) | 8.7 | |
| Internal Link Dist (m) | 280.9 | |
| Turn Bay Length (m) | | |
| Base Capacity (vph) | 510 | |
| Starvation Cap Reductn | 0 | |
| Spillback Cap Reductn | 0 | |
| Storage Cap Reductn | 0 | |
| Reduced v/c Ratio | 0.07 | |
| Intersection Summary | | |

2: Hare Avenue & Carling Avenue
 1995 Carling Avenue

Future (2024) Total Traffic
 AM Peak Hour

| Intersection | | | | | | |
|--------------------------|------|------|------|------|------|------|
| Int Delay, s/veh | 0.5 | | | | | |
| Movement | EBT | EBR | WBL | WBT | NBL | NBR |
| Lane Configurations | ↑↑ | ↑ | ↓ | ↑↑ | ↑↓ | |
| Traffic Vol, veh/h | 1765 | 7 | 13 | 498 | 7 | 15 |
| Future Vol, veh/h | 1765 | 7 | 13 | 498 | 7 | 15 |
| Conflicting Peds, #/hr | 0 | 2 | 2 | 0 | 2 | 0 |
| Sign Control | Free | Free | Free | Free | Stop | Stop |
| RT Channelized | - | None | - | None | - | None |
| Storage Length | - | 350 | 250 | - | 0 | - |
| Veh in Median Storage, # | 0 | - | - | 0 | 0 | - |
| Grade, % | 0 | - | - | 0 | 0 | - |
| Peak Hour Factor | 100 | 100 | 100 | 100 | 100 | 100 |
| Heavy Vehicles, % | 0 | 14 | 0 | 0 | 0 | 7 |
| Mvmt Flow | 1765 | 7 | 13 | 498 | 7 | 15 |

| Major/Minor | Major1 | | Major2 | | Minor1 | |
|----------------------|--------|---|--------|---|--------|------|
| Conflicting Flow All | 0 | 0 | 1774 | 0 | 2044 | 885 |
| Stage 1 | - | - | - | - | 1767 | - |
| Stage 2 | - | - | - | - | 277 | - |
| Critical Hdwy | - | - | 4.1 | - | 6.8 | 7.04 |
| Critical Hdwy Stg 1 | - | - | - | - | 5.8 | - |
| Critical Hdwy Stg 2 | - | - | - | - | 5.8 | - |
| Follow-up Hdwy | - | - | 2.2 | - | 3.5 | 3.37 |
| Pot Cap-1 Maneuver | - | - | 355 | - | 50 | 278 |
| Stage 1 | - | - | - | - | 125 | - |
| Stage 2 | - | - | - | - | 751 | - |
| Platoon blocked, % | - | - | - | - | - | - |
| Mov Cap-1 Maneuver | - | - | 354 | - | 48 | 277 |
| Mov Cap-2 Maneuver | - | - | - | - | 48 | - |
| Stage 1 | - | - | - | - | 125 | - |
| Stage 2 | - | - | - | - | 722 | - |

| Approach | EB | WB | NB |
|----------------------|----|-----|------|
| HCM Control Delay, s | 0 | 0.4 | 45.7 |
| HCM LOS | | | E |

| Minor Lane/Major Mvmt | NBLn1 | EBT | EBR | WBL | WBT |
|-----------------------|-------|-----|-----|-------|-----|
| Capacity (veh/h) | 110 | - | - | 354 | - |
| HCM Lane V/C Ratio | 0.2 | - | - | 0.037 | - |
| HCM Control Delay (s) | 45.7 | - | - | 15.6 | - |
| HCM Lane LOS | E | - | - | C | - |
| HCM 95th %tile Q(veh) | 0.7 | - | - | 0.1 | - |

3: Carling Avenue & Bromley Road
 1995 Carling Avenue

Future (2024) Total Traffic
 AM Peak Hour

| Intersection | | | | | | |
|--------------------------|------|------|------|------|------|------|
| Int Delay, s/veh | 0.2 | | | | | |
| Movement | EBL | EBT | WBT | WBR | SBL | SBR |
| Lane Configurations | | ↑↑ | ↑↑ | ↑ | | ↑ |
| Traffic Vol, veh/h | 0 | 1779 | 457 | 18 | 0 | 53 |
| Future Vol, veh/h | 0 | 1779 | 457 | 18 | 0 | 53 |
| Conflicting Peds, #/hr | 8 | 0 | 0 | 8 | 0 | 0 |
| Sign Control | Free | Free | Free | Free | Stop | Stop |
| RT Channelized | - | None | - | None | - | None |
| Storage Length | - | - | - | 300 | - | 0 |
| Veh in Median Storage, # | - | 0 | 0 | - | 0 | - |
| Grade, % | - | 0 | 0 | - | 0 | - |
| Peak Hour Factor | 100 | 100 | 100 | 100 | 100 | 100 |
| Heavy Vehicles, % | 0 | 0 | 0 | 0 | 0 | 0 |
| Mvmt Flow | 0 | 1779 | 457 | 18 | 0 | 53 |


| Major/Minor | Major1 | Major2 | Minor2 | | |
|----------------------|--------|--------|--------|---|-----|
| Conflicting Flow All | - | 0 | - | 0 | 237 |
| Stage 1 | - | - | - | - | - |
| Stage 2 | - | - | - | - | - |
| Critical Hdwy | - | - | - | - | 6.9 |
| Critical Hdwy Stg 1 | - | - | - | - | - |
| Critical Hdwy Stg 2 | - | - | - | - | - |
| Follow-up Hdwy | - | - | - | - | 3.3 |
| Pot Cap-1 Maneuver | 0 | - | - | - | 771 |
| Stage 1 | 0 | - | - | - | 0 |
| Stage 2 | 0 | - | - | - | 0 |
| Platoon blocked, % | - | - | - | - | - |
| Mov Cap-1 Maneuver | - | - | - | - | 765 |
| Mov Cap-2 Maneuver | - | - | - | - | - |
| Stage 1 | - | - | - | - | - |
| Stage 2 | - | - | - | - | - |

| Approach | EB | WB | SB |
|----------------------|----|----|------|
| HCM Control Delay, s | 0 | 0 | 10.1 |
| HCM LOS | | | B |

| Minor Lane/Major Mvmt | EBT | WBT | WBR | SBLn1 |
|-----------------------|-----|-----|-----|-------|
| Capacity (veh/h) | - | - | - | 765 |
| HCM Lane V/C Ratio | - | - | - | 0.069 |
| HCM Control Delay (s) | - | - | - | 10.1 |
| HCM Lane LOS | - | - | - | B |
| HCM 95th %tile Q(veh) | - | - | - | 0.2 |

4: Maitland Avenue/Sherbourne Road & Carling Avenue
1995 Carling Avenue

Future (2024) Total Traffic
AM Peak Hour



| Lane Group | EBU | EBL | EBT | EBR | WBU | WBL | WBT | WBR | NBL | NBT | NBR | SBL |
|-------------------------|-------|-------|-------|-------|-------|-------|-------|------|-------|-------|------|-------|
| Lane Configurations | | ↔ | ↕ | ↗ | | ↖ | ↕ | | ↗ | ↖ | | ↗ |
| Traffic Volume (vph) | 17 | 29 | 1461 | 272 | 6 | 302 | 299 | 16 | 142 | 99 | 406 | 68 |
| Future Volume (vph) | 17 | 29 | 1461 | 272 | 6 | 302 | 299 | 16 | 142 | 99 | 406 | 68 |
| Ideal Flow (vphpl) | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 |
| Storage Length (m) | | 55.0 | | 130.0 | | 115.0 | | 0.0 | 75.0 | | 0.0 | 45.0 |
| Storage Lanes | | 1 | | 1 | | 2 | | 0 | 1 | | 0 | 1 |
| Taper Length (m) | | 7.5 | | | | 7.5 | | | 7.5 | | | 7.5 |
| Lane Util. Factor | 0.95 | 1.00 | 0.95 | 1.00 | 0.95 | 0.97 | 0.95 | 0.95 | 1.00 | 1.00 | 1.00 | 1.00 |
| Ped Bike Factor | | 0.95 | | 0.96 | | 0.99 | 0.99 | | 0.99 | 0.97 | | |
| Frt | | | | 0.850 | | | 0.992 | | | 0.879 | | |
| Flt Protected | | 0.950 | | | | 0.950 | | | 0.950 | | | 0.950 |
| Satd. Flow (prot) | 0 | 1656 | 3390 | 1532 | 0 | 3228 | 3229 | 0 | 1679 | 1506 | 0 | 1679 |
| Flt Permitted | | 0.950 | | | | 0.950 | | | 0.351 | | | 0.134 |
| Satd. Flow (perm) | 0 | 1567 | 3390 | 1465 | 0 | 3205 | 3229 | 0 | 614 | 1506 | 0 | 237 |
| Right Turn on Red | | | | Yes | | | | Yes | | | Yes | |
| Satd. Flow (RTOR) | | | | 242 | | | 6 | | | 90 | | |
| Link Speed (k/h) | | | 60 | | | | 60 | | | 50 | | |
| Link Distance (m) | | | 447.3 | | | | 309.6 | | | 300.2 | | |
| Travel Time (s) | | | 26.8 | | | | 18.6 | | | 21.6 | | |
| Confl. Peds. (#/hr) | | 25 | | 16 | | 16 | | 25 | 13 | | 15 | 15 |
| Confl. Bikes (#/hr) | | | | | | | | 1 | | | 2 | |
| Peak Hour Factor | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Heavy Vehicles (%) | 0% | 7% | 2% | 1% | 0% | 4% | 6% | 0% | 3% | 5% | 2% | 3% |
| Adj. Flow (vph) | 17 | 29 | 1461 | 272 | 6 | 302 | 299 | 16 | 142 | 99 | 406 | 68 |
| Shared Lane Traffic (%) | | | | | | | | | | | | |
| Lane Group Flow (vph) | 0 | 46 | 1461 | 272 | 0 | 308 | 315 | 0 | 142 | 505 | 0 | 68 |
| Turn Type | Prot | Prot | NA | Perm | Prot | Prot | NA | | Perm | NA | | Perm |
| Protected Phases | 7 | 7 | 4 | | 3 | 3 | 8 | | | 2 | | |
| Permitted Phases | | | | 4 | | | | | 2 | | | 6 |
| Detector Phase | 7 | 7 | 4 | 4 | 3 | 3 | 8 | | 2 | 2 | | 6 |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | | 10.0 | 10.0 | | 10.0 |
| Minimum Split (s) | 10.9 | 10.9 | 23.9 | 23.9 | 10.9 | 10.9 | 23.9 | | 24.8 | 24.8 | | 24.8 |
| Total Split (s) | 13.2 | 13.2 | 59.0 | 59.0 | 17.0 | 17.0 | 62.8 | | 44.0 | 44.0 | | 44.0 |
| Total Split (%) | 11.0% | 11.0% | 49.2% | 49.2% | 14.2% | 14.2% | 52.3% | | 36.7% | 36.7% | | 36.7% |
| Maximum Green (s) | 7.3 | 7.3 | 53.1 | 53.1 | 11.1 | 11.1 | 56.9 | | 37.2 | 37.2 | | 37.2 |
| Yellow Time (s) | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | | 3.3 | 3.3 | | 3.3 |
| All-Red Time (s) | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | | 3.5 | 3.5 | | 3.5 |
| Lost Time Adjust (s) | | -1.9 | -1.9 | -1.9 | | -1.9 | -1.9 | | -2.8 | -2.8 | | -2.8 |
| Total Lost Time (s) | | 4.0 | 4.0 | 4.0 | | 4.0 | 4.0 | | 4.0 | 4.0 | | 4.0 |
| Lead/Lag | Lead | Lead | Lag | Lag | Lead | Lead | Lag | | | | | |
| Lead-Lag Optimize? | Yes | Yes | Yes | Yes | Yes | Yes | Yes | | | | | |
| Vehicle Extension (s) | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | | 3.0 | 3.0 | | 3.0 |
| Recall Mode | None | None | C-Max | C-Max | None | None | C-Max | | None | None | | None |
| Walk Time (s) | | | 7.0 | 7.0 | | | 7.0 | | 7.0 | 7.0 | | 7.0 |
| Flash Dont Walk (s) | | | 11.0 | 11.0 | | | 11.0 | | 11.0 | 11.0 | | 11.0 |
| Pedestrian Calls (#/hr) | | | 16 | 16 | | | 25 | | 15 | 15 | | 13 |
| Act Effct Green (s) | | 8.8 | 56.0 | 56.0 | | 13.4 | 62.9 | | 38.6 | 38.6 | | 38.6 |
| Actuated g/C Ratio | | 0.07 | 0.47 | 0.47 | | 0.11 | 0.52 | | 0.32 | 0.32 | | 0.32 |

4: Maitland Avenue/Sherbourne Road & Carling Avenue
 1995 Carling Avenue

Future (2024) Total Traffic
 AM Peak Hour



| Lane Group | SBT | SBR |
|-------------------------|-------|------|
| Lane Configurations | ↔ | |
| Traffic Volume (vph) | 316 | 16 |
| Future Volume (vph) | 316 | 16 |
| Ideal Flow (vphpl) | 1800 | 1800 |
| Storage Length (m) | | 0.0 |
| Storage Lanes | | 0 |
| Taper Length (m) | | |
| Lane Util. Factor | 1.00 | 1.00 |
| Ped Bike Factor | 1.00 | |
| Frt | 0.993 | |
| Flt Protected | | |
| Satd. Flow (prot) | 1765 | 0 |
| Flt Permitted | | |
| Satd. Flow (perm) | 1765 | 0 |
| Right Turn on Red | | Yes |
| Satd. Flow (RTOR) | 2 | |
| Link Speed (k/h) | 50 | |
| Link Distance (m) | 301.0 | |
| Travel Time (s) | 21.7 | |
| Confl. Peds. (#/hr) | | 13 |
| Confl. Bikes (#/hr) | | |
| Peak Hour Factor | 1.00 | 1.00 |
| Heavy Vehicles (%) | 2% | 6% |
| Adj. Flow (vph) | 316 | 16 |
| Shared Lane Traffic (%) | | |
| Lane Group Flow (vph) | 332 | 0 |
| Turn Type | NA | |
| Protected Phases | 6 | |
| Permitted Phases | | |
| Detector Phase | 6 | |
| Switch Phase | | |
| Minimum Initial (s) | 10.0 | |
| Minimum Split (s) | 24.8 | |
| Total Split (s) | 44.0 | |
| Total Split (%) | 36.7% | |
| Maximum Green (s) | 37.2 | |
| Yellow Time (s) | 3.3 | |
| All-Red Time (s) | 3.5 | |
| Lost Time Adjust (s) | -2.8 | |
| Total Lost Time (s) | 4.0 | |
| Lead/Lag | | |
| Lead-Lag Optimize? | | |
| Vehicle Extension (s) | 3.0 | |
| Recall Mode | None | |
| Walk Time (s) | 7.0 | |
| Flash Dont Walk (s) | 11.0 | |
| Pedestrian Calls (#/hr) | 13 | |
| Act Effct Green (s) | 38.6 | |
| Actuated g/C Ratio | 0.32 | |

4: Maitland Avenue/Sherbourne Road & Carling Avenue
1995 Carling Avenue


Future (2024) Total Traffic
AM Peak Hour

| Lane Group | EBU | EBL | EBT | EBR | WBU | WBL | WBT | WBR | NBL | NBT | NBR | SBL |
|------------------------|-----|------|--------|-------|-----|-------|-------|-----|-------|--------|-----|-------|
| v/c Ratio | | 0.38 | 0.92 | 0.33 | | 0.85 | 0.19 | | 0.72 | 0.93 | | 0.89 |
| Control Delay | | 62.2 | 41.4 | 4.7 | | 74.7 | 16.2 | | 57.7 | 56.6 | | 118.7 |
| Queue Delay | | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 |
| Total Delay | | 62.2 | 41.4 | 4.7 | | 74.7 | 16.2 | | 57.7 | 56.6 | | 118.7 |
| LOS | | E | D | A | | E | B | | E | E | | F |
| Approach Delay | | | 36.3 | | | | 45.1 | | | 56.9 | | |
| Approach LOS | | | D | | | | D | | | E | | |
| Queue Length 50th (m) | | 10.5 | 168.4 | 3.8 | | 37.4 | 20.9 | | 28.9 | 95.9 | | 14.9 |
| Queue Length 95th (m) | | 22.6 | #218.7 | 18.8 | | #61.6 | 29.7 | | #59.6 | #159.4 | | #43.4 |
| Internal Link Dist (m) | | | 423.3 | | | | 285.6 | | | 276.2 | | |
| Turn Bay Length (m) | | 55.0 | | 130.0 | | 115.0 | | | 75.0 | | | 45.0 |
| Base Capacity (vph) | | 126 | 1581 | 812 | | 361 | 1694 | | 204 | 562 | | 79 |
| Starvation Cap Reductn | | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | | 0 |
| Spillback Cap Reductn | | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | | 0 |
| Storage Cap Reductn | | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | | 0 |
| Reduced v/c Ratio | | 0.37 | 0.92 | 0.33 | | 0.85 | 0.19 | | 0.70 | 0.90 | | 0.86 |

Intersection Summary

Area Type: Other
 Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 40 (33%), Referenced to phase 4:EBT and 8:WBT, Start of Green
 Natural Cycle: 80
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.93
 Intersection Signal Delay: 43.6 Intersection LOS: D
 Intersection Capacity Utilization 106.7% ICU Level of Service G
 Analysis Period (min) 15
 # 95th percentile volume exceeds capacity, queue may be longer.
 Queue shown is maximum after two cycles.

Splits and Phases: 4: Maitland Avenue/Sherbourne Road & Carling Avenue



4: Maitland Avenue/Sherbourne Road & Carling Avenue
 1995 Carling Avenue


Future (2024) Total Traffic
 AM Peak Hour



| Lane Group | SBT | SBR |
|------------------------|-------|-----|
| v/c Ratio | 0.58 | |
| Control Delay | 38.3 | |
| Queue Delay | 0.0 | |
| Total Delay | 38.3 | |
| LOS | D | |
| Approach Delay | 51.9 | |
| Approach LOS | D | |
| Queue Length 50th (m) | 63.5 | |
| Queue Length 95th (m) | 92.8 | |
| Internal Link Dist (m) | 277.0 | |
| Turn Bay Length (m) | | |
| Base Capacity (vph) | 589 | |
| Starvation Cap Reductn | 0 | |
| Spillback Cap Reductn | 0 | |
| Storage Cap Reductn | 0 | |
| Reduced v/c Ratio | 0.56 | |
| Intersection Summary | | |

1: Iroquois Road & Carling Avenue
1995 Carling Avenue


Future (2024) Total Traffic
PM Peak Hour



| Lane Group | EBU | EBL | EBT | EBR | WBU | WBL | WBT | WBR | NBL | NBT | NBR | SBL |
|-------------------------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|------|-------|
| Lane Configurations | | ↔ | ↕ | ↗ | | ↔ | ↕ | ↗ | | ↕ | | ↗ |
| Traffic Volume (vph) | 2 | 41 | 692 | 4 | 40 | 17 | 1463 | 107 | 13 | 20 | 10 | 117 |
| Future Volume (vph) | 2 | 41 | 692 | 4 | 40 | 17 | 1463 | 107 | 13 | 20 | 10 | 117 |
| Ideal Flow (vphpl) | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 |
| Storage Length (m) | | 25.0 | | 40.0 | | 20.0 | | 85.0 | 0.0 | | 0.0 | 50.0 |
| Storage Lanes | | 1 | | 1 | | 1 | | 1 | 0 | | 0 | 1 |
| Taper Length (m) | | 7.5 | | | | 7.5 | | | 7.5 | | | 7.5 |
| Lane Util. Factor | 0.95 | 1.00 | 0.95 | 1.00 | 0.91 | 1.00 | 0.91 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Ped Bike Factor | | | | 0.92 | | 0.98 | | 0.90 | | 0.99 | | 0.98 |
| Frt | | | | 0.850 | | | | 0.850 | | 0.969 | | |
| Flt Protected | | 0.950 | | | | 0.950 | | | | 0.985 | | 0.950 |
| Satd. Flow (prot) | 0 | 1729 | 3390 | 1547 | 0 | 1699 | 4919 | 1547 | 0 | 1726 | 0 | 1712 |
| Flt Permitted | | 0.106 | | | | 0.389 | | | | 0.921 | | 0.761 |
| Satd. Flow (perm) | 0 | 193 | 3390 | 1425 | 0 | 685 | 4919 | 1391 | 0 | 1602 | 0 | 1350 |
| Right Turn on Red | | | | Yes | | | | Yes | | | Yes | |
| Satd. Flow (RTOR) | | | | 95 | | | | 107 | | 10 | | |
| Link Speed (k/h) | | | 60 | | | | 60 | | | 50 | | |
| Link Distance (m) | | | 305.5 | | | | 137.5 | | | 297.2 | | |
| Travel Time (s) | | | 18.3 | | | | 8.3 | | | 21.4 | | |
| Confl. Peds. (#/hr) | | 28 | | 19 | | 19 | | 28 | 28 | | 17 | 17 |
| Confl. Bikes (#/hr) | | | | 6 | | | | | | | | |
| Peak Hour Factor | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Heavy Vehicles (%) | 0% | 0% | 2% | 0% | 0% | 6% | 1% | 0% | 0% | 0% | 0% | 1% |
| Adj. Flow (vph) | 2 | 41 | 692 | 4 | 40 | 17 | 1463 | 107 | 13 | 20 | 10 | 117 |
| Shared Lane Traffic (%) | | | | | | | | | | | | |
| Lane Group Flow (vph) | 0 | 43 | 692 | 4 | 0 | 57 | 1463 | 107 | 0 | 43 | 0 | 117 |
| Turn Type | pm+pt | pm+pt | NA | Perm | pm+pt | pm+pt | NA | Perm | Perm | NA | | Perm |
| Protected Phases | 7 | 7 | 4 | | 3 | 3 | 8 | | | 2 | | |
| Permitted Phases | 4 | 4 | | 4 | 8 | 8 | | 8 | 2 | | | 6 |
| Detector Phase | 7 | 7 | 4 | 4 | 3 | 3 | 8 | 8 | 2 | 2 | | 6 |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 10.0 | 10.0 | | 10.0 |
| Minimum Split (s) | 12.0 | 12.0 | 28.3 | 28.3 | 12.0 | 12.0 | 28.3 | 28.3 | 47.3 | 47.3 | | 47.3 |
| Total Split (s) | 12.0 | 12.0 | 71.0 | 71.0 | 12.0 | 12.0 | 71.0 | 71.0 | 47.0 | 47.0 | | 47.0 |
| Total Split (%) | 9.2% | 9.2% | 54.6% | 54.6% | 9.2% | 9.2% | 54.6% | 54.6% | 36.2% | 36.2% | | 36.2% |
| Maximum Green (s) | 5.0 | 5.0 | 64.7 | 64.7 | 5.0 | 5.0 | 64.7 | 64.7 | 39.7 | 39.7 | | 39.7 |
| Yellow Time (s) | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.3 | 3.3 | | 3.3 |
| All-Red Time (s) | 3.3 | 3.3 | 2.6 | 2.6 | 3.3 | 3.3 | 2.6 | 2.6 | 4.0 | 4.0 | | 4.0 |
| Lost Time Adjust (s) | | -3.0 | -2.3 | -2.3 | | -3.0 | -2.3 | -2.3 | | -3.3 | | -3.3 |
| Total Lost Time (s) | | 4.0 | 4.0 | 4.0 | | 4.0 | 4.0 | 4.0 | | 4.0 | | 4.0 |
| Lead/Lag | Lead | Lead | Lag | Lag | Lead | Lead | Lag | Lag | | | | |
| Lead-Lag Optimize? | Yes | Yes | Yes | Yes | Yes | Yes | Yes | Yes | | | | |
| Vehicle Extension (s) | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | | 3.0 |
| Recall Mode | Max | Max | C-Max | C-Max | None | None | C-Max | C-Max | None | None | | None |
| Walk Time (s) | | | 10.0 | 10.0 | | | 10.0 | 10.0 | 27.0 | 27.0 | | 27.0 |
| Flash Dont Walk (s) | | | 12.0 | 12.0 | | | 12.0 | 12.0 | 13.0 | 13.0 | | 13.0 |
| Pedestrian Calls (#/hr) | | | 19 | 19 | | | 28 | 28 | 17 | 17 | | 28 |
| Act Effct Green (s) | | 87.7 | 80.3 | 80.3 | | 75.3 | 67.0 | 67.0 | | 31.9 | | 31.9 |
| Actuated g/C Ratio | | 0.67 | 0.62 | 0.62 | | 0.58 | 0.52 | 0.52 | | 0.25 | | 0.25 |

1: Iroquois Road & Carling Avenue
 1995 Carling Avenue


Future (2024) Total Traffic
 PM Peak Hour



| Lane Group | SBT | SBR |
|-------------------------|-------|------|
| Lane Configurations | ↔ | |
| Traffic Volume (vph) | 23 | 60 |
| Future Volume (vph) | 23 | 60 |
| Ideal Flow (vphpl) | 1800 | 1800 |
| Storage Length (m) | | 0.0 |
| Storage Lanes | | 0 |
| Taper Length (m) | | |
| Lane Util. Factor | 1.00 | 1.00 |
| Ped Bike Factor | 0.97 | |
| Frt | 0.892 | |
| Flt Protected | | |
| Satd. Flow (prot) | 1554 | 0 |
| Flt Permitted | | |
| Satd. Flow (perm) | 1554 | 0 |
| Right Turn on Red | | Yes |
| Satd. Flow (RTOR) | 29 | |
| Link Speed (k/h) | 50 | |
| Link Distance (m) | 304.9 | |
| Travel Time (s) | 22.0 | |
| Confl. Peds. (#/hr) | | 28 |
| Confl. Bikes (#/hr) | | 2 |
| Peak Hour Factor | 1.00 | 1.00 |
| Heavy Vehicles (%) | 0% | 2% |
| Adj. Flow (vph) | 23 | 60 |
| Shared Lane Traffic (%) | | |
| Lane Group Flow (vph) | 83 | 0 |
| Turn Type | NA | |
| Protected Phases | 6 | |
| Permitted Phases | | |
| Detector Phase | 6 | |
| Switch Phase | | |
| Minimum Initial (s) | 10.0 | |
| Minimum Split (s) | 47.3 | |
| Total Split (s) | 47.0 | |
| Total Split (%) | 36.2% | |
| Maximum Green (s) | 39.7 | |
| Yellow Time (s) | 3.3 | |
| All-Red Time (s) | 4.0 | |
| Lost Time Adjust (s) | -3.3 | |
| Total Lost Time (s) | 4.0 | |
| Lead/Lag | | |
| Lead-Lag Optimize? | | |
| Vehicle Extension (s) | 3.0 | |
| Recall Mode | None | |
| Walk Time (s) | 27.0 | |
| Flash Dont Walk (s) | 13.0 | |
| Pedestrian Calls (#/hr) | 28 | |
| Act Effct Green (s) | 31.9 | |
| Actuated g/C Ratio | 0.25 | |

1: Iroquois Road & Carling Avenue
1995 Carling Avenue

Future (2024) Total Traffic
PM Peak Hour




| Lane Group | EBU | EBL | EBT | EBR | WBU | WBL | WBT | WBR | NBL | NBT | NBR | SBL |
|------------------------|-----|------|-------|------|-----|------|-------|------|-----|-------|-----|------|
| v/c Ratio | | 0.12 | 0.33 | 0.00 | | 0.12 | 0.58 | 0.14 | | 0.11 | | 0.35 |
| Control Delay | | 10.3 | 15.3 | 0.0 | | 10.5 | 22.9 | 3.3 | | 26.5 | | 40.4 |
| Queue Delay | | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 | | 0.0 | | 0.0 |
| Total Delay | | 10.3 | 15.3 | 0.0 | | 10.5 | 22.9 | 3.3 | | 26.5 | | 40.4 |
| LOS | | B | B | A | | B | C | A | | C | | D |
| Approach Delay | | | 14.9 | | | | 21.2 | | | 26.5 | | |
| Approach LOS | | | B | | | | C | | | C | | |
| Queue Length 50th (m) | | 4.2 | 55.1 | 0.0 | | 5.6 | 91.7 | 0.0 | | 5.8 | | 21.9 |
| Queue Length 95th (m) | | 9.0 | 69.4 | 0.0 | | 11.2 | 105.9 | 8.9 | | 14.4 | | 37.8 |
| Internal Link Dist (m) | | | 281.5 | | | | 113.5 | | | 273.2 | | |
| Turn Bay Length (m) | | 25.0 | | 40.0 | | 20.0 | | 85.0 | | | | 50.0 |
| Base Capacity (vph) | | 355 | 2094 | 916 | | 461 | 2535 | 768 | | 536 | | 446 |
| Starvation Cap Reductn | | 0 | 0 | 0 | | 0 | 0 | 0 | | 0 | | 0 |
| Spillback Cap Reductn | | 0 | 0 | 0 | | 0 | 0 | 0 | | 0 | | 0 |
| Storage Cap Reductn | | 0 | 0 | 0 | | 0 | 0 | 0 | | 0 | | 0 |
| Reduced v/c Ratio | | 0.12 | 0.33 | 0.00 | | 0.12 | 0.58 | 0.14 | | 0.08 | | 0.26 |

Intersection Summary

| | |
|-----------------------------------|---|
| Area Type: | Other |
| Cycle Length: | 130 |
| Actuated Cycle Length: | 130 |
| Offset: | 95 (73%), Referenced to phase 4:EBTL and 8:WBTL, Start of Green |
| Natural Cycle: | 90 |
| Control Type: | Actuated-Coordinated |
| Maximum v/c Ratio: | 0.58 |
| Intersection Signal Delay: | 20.4 |
| Intersection LOS: | C |
| Intersection Capacity Utilization | 69.5% |
| ICU Level of Service | C |
| Analysis Period (min) | 15 |

Splits and Phases: 1: Iroquois Road & Carling Avenue



1: Iroquois Road & Carling Avenue
 1995 Carling Avenue

Future (2024) Total Traffic
 PM Peak Hour



| Lane Group | SBT | SBR |
|------------------------|-------|-----|
| v/c Ratio | 0.21 | |
| Control Delay | 23.1 | |
| Queue Delay | 0.0 | |
| Total Delay | 23.1 | |
| LOS | C | |
| Approach Delay | 33.2 | |
| Approach LOS | C | |
| Queue Length 50th (m) | 9.6 | |
| Queue Length 95th (m) | 21.7 | |
| Internal Link Dist (m) | 280.9 | |
| Turn Bay Length (m) | | |
| Base Capacity (vph) | 533 | |
| Starvation Cap Reductn | 0 | |
| Spillback Cap Reductn | 0 | |
| Storage Cap Reductn | 0 | |
| Reduced v/c Ratio | 0.16 | |
| Intersection Summary | | |

2: Hare Avenue & Carling Avenue
 1995 Carling Avenue

Future (2024) Total Traffic
 PM Peak Hour

| Intersection | | | | | | |
|--------------------------|------|------|------|------|------|------|
| Int Delay, s/veh | 0.4 | | | | | |
| Movement | EBT | EBR | WBL | WBT | NBL | NBR |
| Lane Configurations | ↑↑ | ↑ | ↓ | ↑↑ | ↑ | |
| Traffic Vol, veh/h | 848 | 8 | 37 | 1614 | 10 | 11 |
| Future Vol, veh/h | 848 | 8 | 37 | 1614 | 10 | 11 |
| Conflicting Peds, #/hr | 0 | 0 | 0 | 0 | 0 | 0 |
| Sign Control | Free | Free | Free | Free | Stop | Stop |
| RT Channelized | - | None | - | None | - | None |
| Storage Length | - | 350 | 250 | - | 0 | - |
| Veh in Median Storage, # | 0 | - | - | 0 | 0 | - |
| Grade, % | 0 | - | - | 0 | 0 | - |
| Peak Hour Factor | 100 | 100 | 100 | 100 | 100 | 100 |
| Heavy Vehicles, % | 0 | 0 | 0 | 0 | 0 | 0 |
| Mvmt Flow | 848 | 8 | 37 | 1614 | 10 | 11 |

| Major/Minor | Major1 | | Major2 | | Minor1 | |
|----------------------|--------|---|--------|---|--------|-----|
| Conflicting Flow All | 0 | 0 | 856 | 0 | 1729 | 424 |
| Stage 1 | - | - | - | - | 848 | - |
| Stage 2 | - | - | - | - | 881 | - |
| Critical Hdwy | - | - | 4.1 | - | 6.8 | 6.9 |
| Critical Hdwy Stg 1 | - | - | - | - | 5.8 | - |
| Critical Hdwy Stg 2 | - | - | - | - | 5.8 | - |
| Follow-up Hdwy | - | - | 2.2 | - | 3.5 | 3.3 |
| Pot Cap-1 Maneuver | - | - | 793 | - | 81 | 584 |
| Stage 1 | - | - | - | - | 385 | - |
| Stage 2 | - | - | - | - | 370 | - |
| Platoon blocked, % | - | - | - | - | - | - |
| Mov Cap-1 Maneuver | - | - | 793 | - | 77 | 584 |
| Mov Cap-2 Maneuver | - | - | - | - | 77 | - |
| Stage 1 | - | - | - | - | 385 | - |
| Stage 2 | - | - | - | - | 353 | - |

| Approach | EB | WB | NB |
|----------------------|----|-----|------|
| HCM Control Delay, s | 0 | 0.2 | 34.9 |
| HCM LOS | | | D |

| Minor Lane/Major Mvmt | NBLn1 | EBT | EBR | WBL | WBT |
|-----------------------|-------|-----|-----|-------|-----|
| Capacity (veh/h) | 141 | - | - | 793 | - |
| HCM Lane V/C Ratio | 0.149 | - | - | 0.047 | - |
| HCM Control Delay (s) | 34.9 | - | - | 9.8 | - |
| HCM Lane LOS | D | - | - | A | - |
| HCM 95th %tile Q(veh) | 0.5 | - | - | 0.1 | - |

3: Carling Avenue & Bromley Road
 1995 Carling Avenue

Future (2024) Total Traffic
 PM Peak Hour

| Intersection | | | | | | |
|--------------------------|------|------|------|------|------|------|
| Int Delay, s/veh | 0.2 | | | | | |
| Movement | EBL | EBT | WBT | WBR | SBL | SBR |
| Lane Configurations | | ↑↑ | ↑↑ | ↑ | | ↑ |
| Traffic Vol, veh/h | 0 | 859 | 1615 | 52 | 0 | 35 |
| Future Vol, veh/h | 0 | 859 | 1615 | 52 | 0 | 35 |
| Conflicting Peds, #/hr | 0 | 0 | 0 | 0 | 0 | 0 |
| Sign Control | Free | Free | Free | Free | Stop | Stop |
| RT Channelized | - | None | - | None | - | None |
| Storage Length | - | - | - | 300 | - | 0 |
| Veh in Median Storage, # | - | 0 | 0 | - | 0 | - |
| Grade, % | - | 0 | 0 | - | 0 | - |
| Peak Hour Factor | 100 | 100 | 100 | 100 | 100 | 100 |
| Heavy Vehicles, % | 0 | 0 | 0 | 0 | 0 | 8 |
| Mvmt Flow | 0 | 859 | 1615 | 52 | 0 | 35 |





















| Major/Minor | Major1 | Major2 | Minor2 | | |
|----------------------|--------|--------|--------|---|--------|
| Conflicting Flow All | - | 0 | - | 0 | - 808 |
| Stage 1 | - | - | - | - | - |
| Stage 2 | - | - | - | - | - |
| Critical Hdwy | - | - | - | - | - 7.06 |
| Critical Hdwy Stg 1 | - | - | - | - | - |
| Critical Hdwy Stg 2 | - | - | - | - | - |
| Follow-up Hdwy | - | - | - | - | - 3.38 |
| Pot Cap-1 Maneuver | 0 | - | - | - | 0 312 |
| Stage 1 | 0 | - | - | - | 0 - |
| Stage 2 | 0 | - | - | - | 0 - |
| Platoon blocked, % | - | - | - | - | - |
| Mov Cap-1 Maneuver | - | - | - | - | - 312 |
| Mov Cap-2 Maneuver | - | - | - | - | - |
| Stage 1 | - | - | - | - | - |
| Stage 2 | - | - | - | - | - |

| Approach | EB | WB | SB |
|----------------------|----|----|----|
| HCM Control Delay, s | 0 | 0 | 18 |
| HCM LOS | | | C |

| Minor Lane/Major Mvmt | EBT | WBT | WBR | SBLn1 |
|-----------------------|-----|-----|-----|-------|
| Capacity (veh/h) | - | - | - | 312 |
| HCM Lane V/C Ratio | - | - | - | 0.112 |
| HCM Control Delay (s) | - | - | - | 18 |
| HCM Lane LOS | - | - | - | C |
| HCM 95th %tile Q(veh) | - | - | - | 0.4 |

4: Maitland Avenue/Sherbourne Road & Carling Avenue
1995 Carling Avenue

Future (2024) Total Traffic
PM Peak Hour

| |  |  |  |  |  |  |  |  |  |  |  |  |
|-------------------------|---|---|---|---|---|---|--|---|---|---|---|---|
| Lane Group | EBU | EBL | EBT | EBR | WBU | WBL | WBT | WBR | NBL | NBT | NBR | SBL |
| Lane Configurations | |  |  |  | |  |  | |  |  | |  |
| Traffic Volume (vph) | 26 | 62 | 593 | 178 | 9 | 734 | 1345 | 54 | 251 | 213 | 213 | 48 |
| Future Volume (vph) | 26 | 62 | 593 | 178 | 9 | 734 | 1345 | 54 | 251 | 213 | 213 | 48 |
| Ideal Flow (vphpl) | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 |
| Storage Length (m) | | 55.0 | | 130.0 | | 115.0 | | 0.0 | 75.0 | | 0.0 | 45.0 |
| Storage Lanes | | 1 | | 1 | | 1 | | 0 | 1 | | 0 | 1 |
| Taper Length (m) | | 7.5 | | | | 7.5 | | | 7.5 | | | 7.5 |
| Lane Util. Factor | 0.95 | 1.00 | 0.95 | 1.00 | 0.95 | 0.97 | 0.95 | 0.95 | 1.00 | 1.00 | 1.00 | 1.00 |
| Ped Bike Factor | | 0.98 | | 0.94 | | 0.96 | 0.99 | | 0.98 | 0.98 | | |
| Frt | | | | 0.850 | | | 0.994 | | | 0.925 | | |
| Flt Protected | | 0.950 | | | | 0.950 | | | 0.950 | | | 0.950 |
| Satd. Flow (prot) | 0 | 1729 | 3390 | 1532 | 0 | 3321 | 3381 | 0 | 1729 | 1624 | 0 | 1729 |
| Flt Permitted | | 0.950 | | | | 0.950 | | | 0.476 | | | 0.249 |
| Satd. Flow (perm) | 0 | 1699 | 3390 | 1438 | 0 | 3200 | 3381 | 0 | 847 | 1624 | 0 | 453 |
| Right Turn on Red | | | | Yes | | | | Yes | | | Yes | |
| Satd. Flow (RTOR) | | | | 178 | | | 4 | | | 49 | | |
| Link Speed (k/h) | | | 60 | | | | 60 | | | 50 | | |
| Link Distance (m) | | | 447.3 | | | | 309.6 | | | 300.2 | | |
| Travel Time (s) | | | 26.8 | | | | 18.6 | | | 21.6 | | |
| Confl. Peds. (#/hr) | | 36 | | 25 | | 25 | | 36 | 20 | | 15 | 15 |
| Confl. Bikes (#/hr) | | | | | | | | 2 | | | | |
| Peak Hour Factor | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Heavy Vehicles (%) | 0% | 0% | 2% | 1% | 0% | 1% | 1% | 4% | 0% | 0% | 3% | 0% |
| Adj. Flow (vph) | 26 | 62 | 593 | 178 | 9 | 734 | 1345 | 54 | 251 | 213 | 213 | 48 |
| Shared Lane Traffic (%) | | | | | | | | | | | | |
| Lane Group Flow (vph) | 0 | 88 | 593 | 178 | 0 | 743 | 1399 | 0 | 251 | 426 | 0 | 48 |
| Turn Type | Prot | Prot | NA | Perm | Prot | Prot | NA | | Perm | NA | | Perm |
| Protected Phases | 7 | 7 | 4 | | 3 | 3 | 8 | | | 2 | | |
| Permitted Phases | | | | 4 | | | | | 2 | | | 6 |
| Detector Phase | 7 | 7 | 4 | 4 | 3 | 3 | 8 | | 2 | 2 | | 6 |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | | 10.0 | 10.0 | | 10.0 |
| Minimum Split (s) | 10.9 | 10.9 | 23.9 | 23.9 | 10.9 | 10.9 | 23.9 | | 24.8 | 24.8 | | 24.8 |
| Total Split (s) | 12.0 | 12.0 | 33.0 | 33.0 | 36.0 | 36.0 | 57.0 | | 51.0 | 51.0 | | 51.0 |
| Total Split (%) | 10.0% | 10.0% | 27.5% | 27.5% | 30.0% | 30.0% | 47.5% | | 42.5% | 42.5% | | 42.5% |
| Maximum Green (s) | 6.1 | 6.1 | 27.1 | 27.1 | 30.1 | 30.1 | 51.1 | | 44.2 | 44.2 | | 44.2 |
| Yellow Time (s) | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | | 3.3 | 3.3 | | 3.3 |
| All-Red Time (s) | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | | 3.5 | 3.5 | | 3.5 |
| Lost Time Adjust (s) | | -1.9 | -1.9 | -1.9 | | -1.9 | -1.9 | | -2.8 | -2.8 | | -2.8 |
| Total Lost Time (s) | | 4.0 | 4.0 | 4.0 | | 4.0 | 4.0 | | 4.0 | 4.0 | | 4.0 |
| Lead/Lag | Lead | Lead | Lag | Lag | Lead | Lead | Lag | | | | | |
| Lead-Lag Optimize? | Yes | Yes | Yes | Yes | Yes | Yes | Yes | | | | | |
| Vehicle Extension (s) | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | | 3.0 | 3.0 | | 3.0 |
| Recall Mode | None | None | C-Max | C-Max | None | None | C-Max | | None | None | | None |
| Walk Time (s) | | | 7.0 | 7.0 | | | 7.0 | | 7.0 | 7.0 | | 7.0 |
| Flash Dont Walk (s) | | | 11.0 | 11.0 | | | 11.0 | | 11.0 | 11.0 | | 11.0 |
| Pedestrian Calls (#/hr) | | | 25 | 25 | | | 36 | | 15 | 15 | | 20 |
| Act Effct Green (s) | | 10.0 | 36.3 | 36.3 | | 31.4 | 57.8 | | 40.2 | 40.2 | | 40.2 |
| Actuated g/C Ratio | | 0.08 | 0.30 | 0.30 | | 0.26 | 0.48 | | 0.34 | 0.34 | | 0.34 |

4: Maitland Avenue/Sherbourne Road & Carling Avenue
 1995 Carling Avenue


Future (2024) Total Traffic
 PM Peak Hour



| Lane Group | SBT | SBR |
|-------------------------|-------|------|
| Lane Configurations | ↗ | |
| Traffic Volume (vph) | 201 | 45 |
| Future Volume (vph) | 201 | 45 |
| Ideal Flow (vphpl) | 1800 | 1800 |
| Storage Length (m) | | 0.0 |
| Storage Lanes | | 0 |
| Taper Length (m) | | |
| Lane Util. Factor | 1.00 | 1.00 |
| Ped Bike Factor | 0.99 | |
| Frt | 0.973 | |
| Flt Protected | | |
| Satd. Flow (prot) | 1748 | 0 |
| Flt Permitted | | |
| Satd. Flow (perm) | 1748 | 0 |
| Right Turn on Red | | Yes |
| Satd. Flow (RTOR) | 11 | |
| Link Speed (k/h) | 50 | |
| Link Distance (m) | 301.0 | |
| Travel Time (s) | 21.7 | |
| Confl. Peds. (#/hr) | | 20 |
| Confl. Bikes (#/hr) | | |
| Peak Hour Factor | 1.00 | 1.00 |
| Heavy Vehicles (%) | 0% | 2% |
| Adj. Flow (vph) | 201 | 45 |
| Shared Lane Traffic (%) | | |
| Lane Group Flow (vph) | 246 | 0 |
| Turn Type | NA | |
| Protected Phases | 6 | |
| Permitted Phases | | |
| Detector Phase | 6 | |
| Switch Phase | | |
| Minimum Initial (s) | 10.0 | |
| Minimum Split (s) | 24.8 | |
| Total Split (s) | 51.0 | |
| Total Split (%) | 42.5% | |
| Maximum Green (s) | 44.2 | |
| Yellow Time (s) | 3.3 | |
| All-Red Time (s) | 3.5 | |
| Lost Time Adjust (s) | -2.8 | |
| Total Lost Time (s) | 4.0 | |
| Lead/Lag | | |
| Lead-Lag Optimize? | | |
| Vehicle Extension (s) | 3.0 | |
| Recall Mode | None | |
| Walk Time (s) | 7.0 | |
| Flash Dont Walk (s) | 11.0 | |
| Pedestrian Calls (#/hr) | 20 | |
| Act Effct Green (s) | 40.2 | |
| Actuated g/C Ratio | 0.34 | |

4: Maitland Avenue/Sherbourne Road & Carling Avenue
1995 Carling Avenue

Future (2024) Total Traffic
PM Peak Hour




| Lane Group | EBU | EBL | EBT | EBR | WBU | WBL | WBT | WBR | NBL | NBT | NBR | SBL |
|------------------------|-----|-------|-------|-------|-----|--------|--------|-----|-------|-------|-----|------|
| v/c Ratio | | 0.61 | 0.58 | 0.32 | | 0.85 | 0.86 | | 0.89 | 0.74 | | 0.32 |
| Control Delay | | 72.3 | 40.1 | 6.9 | | 52.7 | 35.3 | | 68.0 | 38.4 | | 33.2 |
| Queue Delay | | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 |
| Total Delay | | 72.3 | 40.1 | 6.9 | | 52.7 | 35.3 | | 68.0 | 38.4 | | 33.2 |
| LOS | | E | D | A | | D | D | | E | D | | C |
| Approach Delay | | | 36.5 | | | | 41.4 | | | 49.4 | | |
| Approach LOS | | | D | | | | D | | | D | | |
| Queue Length 50th (m) | | 20.0 | 66.7 | 0.0 | | 82.8 | 161.3 | | 53.4 | 75.7 | | 8.1 |
| Queue Length 95th (m) | | #48.2 | 88.1 | 17.3 | | #109.3 | #210.0 | | #92.7 | 106.6 | | 17.9 |
| Internal Link Dist (m) | | | 423.3 | | | | 285.6 | | | 276.2 | | |
| Turn Bay Length (m) | | 55.0 | | 130.0 | | 115.0 | | | 75.0 | | | 45.0 |
| Base Capacity (vph) | | 144 | 1026 | 559 | | 899 | 1630 | | 331 | 665 | | 177 |
| Starvation Cap Reductn | | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | | 0 |
| Spillback Cap Reductn | | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | | 0 |
| Storage Cap Reductn | | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | | 0 |
| Reduced v/c Ratio | | 0.61 | 0.58 | 0.32 | | 0.83 | 0.86 | | 0.76 | 0.64 | | 0.27 |

Intersection Summary

Area Type: Other
 Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 103 (86%), Referenced to phase 4:EBT and 8:WBT, Start of Green
 Natural Cycle: 90
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.89
 Intersection Signal Delay: 40.9
 Intersection LOS: D
 Intersection Capacity Utilization 94.3%
 ICU Level of Service F
 Analysis Period (min) 15
 # 95th percentile volume exceeds capacity, queue may be longer.
 Queue shown is maximum after two cycles.

Splits and Phases: 4: Maitland Avenue/Sherbourne Road & Carling Avenue



4: Maitland Avenue/Sherbourne Road & Carling Avenue
 1995 Carling Avenue


Future (2024) Total Traffic
 PM Peak Hour



| Lane Group | SBT | SBR |
|------------------------|-------|-----|
| v/c Ratio | 0.41 | |
| Control Delay | 30.3 | |
| Queue Delay | 0.0 | |
| Total Delay | 30.3 | |
| LOS | C | |
| Approach Delay | 30.8 | |
| Approach LOS | C | |
| Queue Length 50th (m) | 40.8 | |
| Queue Length 95th (m) | 59.3 | |
| Internal Link Dist (m) | 277.0 | |
| Turn Bay Length (m) | | |
| Base Capacity (vph) | 691 | |
| Starvation Cap Reductn | 0 | |
| Spillback Cap Reductn | 0 | |
| Storage Cap Reductn | 0 | |
| Reduced v/c Ratio | 0.36 | |
| Intersection Summary | | |

1: Iroquois Road & Carling Avenue
1995 Carling Avenue

Future (2029) Total Traffic
AM Peak Hour



| Lane Group | EBU | EBL | EBT | EBR | WBU | WBL | WBT | WBR | NBL | NBT | NBR | SBL |
|-------------------------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|------|-------|
| Lane Configurations | | | | | | | | | | | | |
| Traffic Volume (vph) | 1 | 19 | 1589 | 5 | 39 | 7 | 391 | 60 | 3 | 24 | 30 | 75 |
| Future Volume (vph) | 1 | 19 | 1589 | 5 | 39 | 7 | 391 | 60 | 3 | 24 | 30 | 75 |
| Ideal Flow (vphpl) | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 |
| Storage Length (m) | | 25.0 | | 40.0 | | | 20.0 | | 85.0 | 0.0 | 0.0 | 50.0 |
| Storage Lanes | | 1 | | 1 | | | 1 | | 1 | 0 | 0 | 1 |
| Taper Length (m) | | 7.5 | | | | | 7.5 | | 7.5 | | | 7.5 |
| Lane Util. Factor | 0.95 | 1.00 | 0.95 | 1.00 | 0.91 | 1.00 | 0.91 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Ped Bike Factor | | 0.98 | | 0.94 | | | | 0.94 | | 0.99 | | 0.99 |
| Frt | | | | 0.850 | | | | 0.850 | | 0.929 | | |
| Flt Protected | | 0.950 | | | | | 0.950 | | | 0.997 | | 0.950 |
| Satd. Flow (prot) | 0 | 1729 | 3390 | 1547 | 0 | 1729 | 4687 | 1502 | 0 | 1635 | 0 | 1679 |
| Flt Permitted | | 0.469 | | | | | 0.129 | | | 0.990 | | 0.717 |
| Satd. Flow (perm) | 0 | 832 | 3390 | 1461 | 0 | 235 | 4687 | 1406 | 0 | 1623 | 0 | 1254 |
| Right Turn on Red | | | | Yes | | | | Yes | | | Yes | |
| Satd. Flow (RTOR) | | | | 95 | | | | 95 | | 30 | | |
| Link Speed (k/h) | | | 60 | | | | 60 | | | 50 | | |
| Link Distance (m) | | | 305.5 | | | | 136.9 | | | 297.2 | | |
| Travel Time (s) | | | 18.3 | | | | 8.2 | | | 21.4 | | |
| Confl. Peds. (#/hr) | | 15 | | 12 | | | 12 | | 15 | 13 | | 12 |
| Confl. Bikes (#/hr) | | | | 1 | | | | | 1 | | | 4 |
| Peak Hour Factor | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Heavy Vehicles (%) | 0% | 0% | 2% | 0% | 0% | 0% | 6% | 3% | 0% | 4% | 0% | 3% |
| Adj. Flow (vph) | 1 | 19 | 1589 | 5 | 39 | 7 | 391 | 60 | 3 | 24 | 30 | 75 |
| Shared Lane Traffic (%) | | | | | | | | | | | | |
| Lane Group Flow (vph) | 0 | 20 | 1589 | 5 | 0 | 46 | 391 | 60 | 0 | 57 | 0 | 75 |
| Turn Type | pm+pt | pm+pt | NA | Perm | pm+pt | pm+pt | NA | Perm | Perm | NA | | Perm |
| Protected Phases | 7 | 7 | 4 | | 3 | 3 | 8 | | | 2 | | |
| Permitted Phases | 4 | 4 | | 4 | 8 | 8 | | 8 | 2 | | | 6 |
| Detector Phase | 7 | 7 | 4 | 4 | 3 | 3 | 8 | 8 | 2 | 2 | | 6 |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 10.0 | 10.0 | | 10.0 |
| Minimum Split (s) | 12.0 | 12.0 | 28.3 | 28.3 | 12.0 | 12.0 | 28.3 | 28.3 | 47.3 | 47.3 | | 47.3 |
| Total Split (s) | 14.0 | 14.0 | 69.0 | 69.0 | 14.0 | 14.0 | 69.0 | 69.0 | 47.0 | 47.0 | | 47.0 |
| Total Split (%) | 10.8% | 10.8% | 53.1% | 53.1% | 10.8% | 10.8% | 53.1% | 53.1% | 36.2% | 36.2% | | 36.2% |
| Maximum Green (s) | 7.0 | 7.0 | 62.7 | 62.7 | 7.0 | 7.0 | 62.7 | 62.7 | 39.7 | 39.7 | | 39.7 |
| Yellow Time (s) | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.3 | 3.3 | | 3.3 |
| All-Red Time (s) | 3.3 | 3.3 | 2.6 | 2.6 | 3.3 | 3.3 | 2.6 | 2.6 | 4.0 | 4.0 | | 4.0 |
| Lost Time Adjust (s) | | -3.0 | -2.3 | -2.3 | | | -3.0 | -2.3 | -2.3 | | -3.3 | -3.3 |
| Total Lost Time (s) | | 4.0 | 4.0 | 4.0 | | | 4.0 | 4.0 | 4.0 | | 4.0 | 4.0 |
| Lead/Lag | Lead | Lead | Lag | Lag | Lead | Lead | Lag | Lag | | | | |
| Lead-Lag Optimize? | Yes | Yes | Yes | Yes | Yes | Yes | Yes | Yes | | | | |
| Vehicle Extension (s) | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | | 3.0 |
| Recall Mode | Max | Max | C-Max | C-Max | None | None | C-Max | C-Max | None | None | | None |
| Walk Time (s) | | | 10.0 | 10.0 | | | 10.0 | 10.0 | 27.0 | 27.0 | | 27.0 |
| Flash Dont Walk (s) | | | 12.0 | 12.0 | | | 12.0 | 12.0 | 13.0 | 13.0 | | 13.0 |
| Pedestrian Calls (#/hr) | | | 12 | 12 | | | 15 | 15 | 12 | 12 | | 13 |
| Act Effct Green (s) | | 98.0 | 89.6 | 89.6 | | | 74.3 | 65.0 | 65.0 | 25.9 | | 25.9 |
| Actuated g/C Ratio | | 0.75 | 0.69 | 0.69 | | | 0.57 | 0.50 | 0.50 | 0.20 | | 0.20 |

1: Iroquois Road & Carling Avenue
 1995 Carling Avenue


Future (2029) Total Traffic
 AM Peak Hour



| Lane Group | SBT | SBR |
|-------------------------|-------|------|
| Lane Configurations | ↔ | |
| Traffic Volume (vph) | 7 | 27 |
| Future Volume (vph) | 7 | 27 |
| Ideal Flow (vphpl) | 1800 | 1800 |
| Storage Length (m) | | 0.0 |
| Storage Lanes | | 0 |
| Taper Length (m) | | |
| Lane Util. Factor | 1.00 | 1.00 |
| Ped Bike Factor | 0.98 | |
| Frt | 0.881 | |
| Flt Protected | | |
| Satd. Flow (prot) | 1490 | 0 |
| Flt Permitted | | |
| Satd. Flow (perm) | 1490 | 0 |
| Right Turn on Red | | Yes |
| Satd. Flow (RTOR) | 27 | |
| Link Speed (k/h) | 50 | |
| Link Distance (m) | 304.9 | |
| Travel Time (s) | 22.0 | |
| Confl. Peds. (#/hr) | | 13 |
| Confl. Bikes (#/hr) | | |
| Peak Hour Factor | 1.00 | 1.00 |
| Heavy Vehicles (%) | 0% | 7% |
| Adj. Flow (vph) | 7 | 27 |
| Shared Lane Traffic (%) | | |
| Lane Group Flow (vph) | 34 | 0 |
| Turn Type | NA | |
| Protected Phases | 6 | |
| Permitted Phases | | |
| Detector Phase | 6 | |
| Switch Phase | | |
| Minimum Initial (s) | 10.0 | |
| Minimum Split (s) | 47.3 | |
| Total Split (s) | 47.0 | |
| Total Split (%) | 36.2% | |
| Maximum Green (s) | 39.7 | |
| Yellow Time (s) | 3.3 | |
| All-Red Time (s) | 4.0 | |
| Lost Time Adjust (s) | -3.3 | |
| Total Lost Time (s) | 4.0 | |
| Lead/Lag | | |
| Lead-Lag Optimize? | | |
| Vehicle Extension (s) | 3.0 | |
| Recall Mode | None | |
| Walk Time (s) | 27.0 | |
| Flash Dont Walk (s) | 13.0 | |
| Pedestrian Calls (#/hr) | 13 | |
| Act Effct Green (s) | 25.9 | |
| Actuated g/C Ratio | 0.20 | |

1: Iroquois Road & Carling Avenue
1995 Carling Avenue

Future (2029) Total Traffic
AM Peak Hour




| Lane Group | EBU | EBL | EBT | EBR | WBU | WBL | WBT | WBR | NBL | NBT | NBR | SBL |
|------------------------|-----|------|--------|------|-----|------|-------|------|-----|-------|-----|------|
| v/c Ratio | | 0.02 | 0.68 | 0.00 | | 0.19 | 0.17 | 0.08 | | 0.16 | | 0.30 |
| Control Delay | | 8.3 | 20.3 | 0.0 | | 11.2 | 18.0 | 1.1 | | 20.4 | | 43.3 |
| Queue Delay | | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 | | 0.0 | | 0.0 |
| Total Delay | | 8.3 | 20.3 | 0.0 | | 11.2 | 18.0 | 1.1 | | 20.4 | | 43.3 |
| LOS | | A | C | A | | B | B | A | | C | | D |
| Approach Delay | | | 20.1 | | | | 15.3 | | | 20.4 | | |
| Approach LOS | | | C | | | | B | | | C | | |
| Queue Length 50th (m) | | 0.8 | 104.2 | 0.0 | | 2.6 | 19.4 | 0.0 | | 6.2 | | 18.2 |
| Queue Length 95th (m) | | 5.2 | #250.2 | 0.0 | | 9.6 | 25.8 | 2.4 | | 14.4 | | 25.9 |
| Internal Link Dist (m) | | | 281.5 | | | | 112.9 | | | 273.2 | | |
| Turn Bay Length (m) | | 25.0 | | 40.0 | | 20.0 | | 85.0 | | | | 50.0 |
| Base Capacity (vph) | | 838 | 2337 | 1037 | | 250 | 2343 | 750 | | 556 | | 414 |
| Starvation Cap Reductn | | 0 | 0 | 0 | | 0 | 0 | 0 | | 0 | | 0 |
| Spillback Cap Reductn | | 0 | 0 | 0 | | 0 | 0 | 0 | | 0 | | 0 |
| Storage Cap Reductn | | 0 | 0 | 0 | | 0 | 0 | 0 | | 0 | | 0 |
| Reduced v/c Ratio | | 0.02 | 0.68 | 0.00 | | 0.18 | 0.17 | 0.08 | | 0.10 | | 0.18 |

Intersection Summary

Area Type: Other
 Cycle Length: 130
 Actuated Cycle Length: 130
 Offset: 6 (5%), Referenced to phase 4:EBTL and 8:WBTL, Start of Green
 Natural Cycle: 120
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.68
 Intersection Signal Delay: 19.7 Intersection LOS: B
 Intersection Capacity Utilization 71.9% ICU Level of Service C
 Analysis Period (min) 15
 # 95th percentile volume exceeds capacity, queue may be longer.
 Queue shown is maximum after two cycles.

Splits and Phases: 1: Iroquois Road & Carling Avenue



1: Iroquois Road & Carling Avenue
 1995 Carling Avenue

Future (2029) Total Traffic
 AM Peak Hour



| Lane Group | SBT | SBR |
|------------------------|-------|-----|
| v/c Ratio | 0.11 | |
| Control Delay | 14.5 | |
| Queue Delay | 0.0 | |
| Total Delay | 14.5 | |
| LOS | B | |
| Approach Delay | 34.3 | |
| Approach LOS | C | |
| Queue Length 50th (m) | 1.6 | |
| Queue Length 95th (m) | 8.7 | |
| Internal Link Dist (m) | 280.9 | |
| Turn Bay Length (m) | | |
| Base Capacity (vph) | 510 | |
| Starvation Cap Reductn | 0 | |
| Spillback Cap Reductn | 0 | |
| Storage Cap Reductn | 0 | |
| Reduced v/c Ratio | 0.07 | |
| Intersection Summary | | |

2: Hare Avenue & Carling Avenue
 1995 Carling Avenue

Future (2029) Total Traffic
 AM Peak Hour

| Intersection | | | | | | |
|--------------------------|------|------|------|------|------|------|
| Int Delay, s/veh | 0.5 | | | | | |
| Movement | EBT | EBR | WBL | WBT | NBL | NBR |
| Lane Configurations | ↑↑ | ↑ | ↓ | ↑↑ | ↓ | ↓ |
| Traffic Vol, veh/h | 1721 | 7 | 13 | 487 | 7 | 15 |
| Future Vol, veh/h | 1721 | 7 | 13 | 487 | 7 | 15 |
| Conflicting Peds, #/hr | 0 | 2 | 2 | 0 | 2 | 0 |
| Sign Control | Free | Free | Free | Free | Stop | Stop |
| RT Channelized | - | None | - | None | - | None |
| Storage Length | - | 350 | 250 | - | 0 | - |
| Veh in Median Storage, # | 0 | - | - | 0 | 0 | - |
| Grade, % | 0 | - | - | 0 | 0 | - |
| Peak Hour Factor | 100 | 100 | 100 | 100 | 100 | 100 |
| Heavy Vehicles, % | 0 | 14 | 0 | 0 | 0 | 7 |
| Mvmt Flow | 1721 | 7 | 13 | 487 | 7 | 15 |

| Major/Minor | Major1 | | Major2 | | Minor1 | |
|----------------------|--------|---|--------|---|--------|------|
| Conflicting Flow All | 0 | 0 | 1730 | 0 | 1995 | 863 |
| Stage 1 | - | - | - | - | 1723 | - |
| Stage 2 | - | - | - | - | 272 | - |
| Critical Hdwy | - | - | 4.1 | - | 6.8 | 7.04 |
| Critical Hdwy Stg 1 | - | - | - | - | 5.8 | - |
| Critical Hdwy Stg 2 | - | - | - | - | 5.8 | - |
| Follow-up Hdwy | - | - | 2.2 | - | 3.5 | 3.37 |
| Pot Cap-1 Maneuver | - | - | 370 | - | 54 | 288 |
| Stage 1 | - | - | - | - | 132 | - |
| Stage 2 | - | - | - | - | 755 | - |
| Platoon blocked, % | - | - | - | - | - | - |
| Mov Cap-1 Maneuver | - | - | 369 | - | 52 | 287 |
| Mov Cap-2 Maneuver | - | - | - | - | 52 | - |
| Stage 1 | - | - | - | - | 132 | - |
| Stage 2 | - | - | - | - | 727 | - |

| Approach | EB | WB | NB |
|----------------------|----|-----|------|
| HCM Control Delay, s | 0 | 0.4 | 42.4 |
| HCM LOS | | | E |

| Minor Lane/Major Mvmt | NBLn1 | EBT | EBR | WBL | WBT |
|-----------------------|-------|-----|-----|-------|-----|
| Capacity (veh/h) | 118 | - | - | 369 | - |
| HCM Lane V/C Ratio | 0.186 | - | - | 0.035 | - |
| HCM Control Delay (s) | 42.4 | - | - | 15.1 | - |
| HCM Lane LOS | E | - | - | C | - |
| HCM 95th %tile Q(veh) | 0.7 | - | - | 0.1 | - |

3: Carling Avenue & Bromley Road
1995 Carling Avenue

Future (2029) Total Traffic
AM Peak Hour

| Intersection | | | | | | |
|--------------------------|------|------|------|------|------|------|
| Int Delay, s/veh | 0.2 | | | | | |
| Movement | EBL | EBT | WBT | WBR | SBL | SBR |
| Lane Configurations | | ↑↑ | ↑↑ | ↑ | | ↑ |
| Traffic Vol, veh/h | 0 | 1735 | 446 | 18 | 0 | 53 |
| Future Vol, veh/h | 0 | 1735 | 446 | 18 | 0 | 53 |
| Conflicting Peds, #/hr | 8 | 0 | 0 | 8 | 0 | 0 |
| Sign Control | Free | Free | Free | Free | Stop | Stop |
| RT Channelized | - | None | - | None | - | None |
| Storage Length | - | - | - | 300 | - | 0 |
| Veh in Median Storage, # | - | 0 | 0 | - | 0 | - |
| Grade, % | - | 0 | 0 | - | 0 | - |
| Peak Hour Factor | 100 | 100 | 100 | 100 | 100 | 100 |
| Heavy Vehicles, % | 0 | 0 | 0 | 0 | 0 | 0 |
| Mvmt Flow | 0 | 1735 | 446 | 18 | 0 | 53 |





















| Major/Minor | Major1 | Major2 | Minor2 | | |
|----------------------|--------|--------|--------|---|-----|
| Conflicting Flow All | - | 0 | - | 0 | 231 |
| Stage 1 | - | - | - | - | - |
| Stage 2 | - | - | - | - | - |
| Critical Hdwy | - | - | - | - | 6.9 |
| Critical Hdwy Stg 1 | - | - | - | - | - |
| Critical Hdwy Stg 2 | - | - | - | - | - |
| Follow-up Hdwy | - | - | - | - | 3.3 |
| Pot Cap-1 Maneuver | 0 | - | - | - | 777 |
| Stage 1 | 0 | - | - | - | 0 |
| Stage 2 | 0 | - | - | - | 0 |
| Platoon blocked, % | - | - | - | - | - |
| Mov Cap-1 Maneuver | - | - | - | - | 771 |
| Mov Cap-2 Maneuver | - | - | - | - | - |
| Stage 1 | - | - | - | - | - |
| Stage 2 | - | - | - | - | - |

| Approach | EB | WB | SB |
|----------------------|----|----|----|
| HCM Control Delay, s | 0 | 0 | 10 |
| HCM LOS | | | B |

| Minor Lane/Major Mvmt | EBT | WBT | WBR | SBLn1 |
|-----------------------|-----|-----|-----|-------|
| Capacity (veh/h) | - | - | - | 771 |
| HCM Lane V/C Ratio | - | - | - | 0.069 |
| HCM Control Delay (s) | - | - | - | 10 |
| HCM Lane LOS | - | - | - | B |
| HCM 95th %tile Q(veh) | - | - | - | 0.2 |

4: Maitland Avenue/Sherbourne Road & Carling Avenue
1995 Carling Avenue

Future (2029) Total Traffic
AM Peak Hour

| |  |  |  |  |  |  |  |  |  |  |  |  |
|-------------------------|---|---|---|---|---|---|--|---|---|---|---|---|
| Lane Group | EBU | EBL | EBT | EBR | WBU | WBL | WBT | WBR | NBL | NBT | NBR | SBL |
| Lane Configurations | |  |  |  | |  |  | |  |  | |  |
| Traffic Volume (vph) | 17 | 28 | 1425 | 265 | 6 | 294 | 292 | 16 | 139 | 97 | 396 | 66 |
| Future Volume (vph) | 17 | 28 | 1425 | 265 | 6 | 294 | 292 | 16 | 139 | 97 | 396 | 66 |
| Ideal Flow (vphpl) | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 |
| Storage Length (m) | | 55.0 | | 130.0 | | 115.0 | | 0.0 | 75.0 | | 0.0 | 45.0 |
| Storage Lanes | | 1 | | 1 | | 2 | | 0 | 1 | | 0 | 1 |
| Taper Length (m) | | 7.5 | | | | 7.5 | | | 7.5 | | | 7.5 |
| Lane Util. Factor | 0.95 | 1.00 | 0.95 | 1.00 | 0.95 | 0.97 | 0.95 | 0.95 | 1.00 | 1.00 | 1.00 | 1.00 |
| Ped Bike Factor | | 0.95 | | 0.96 | | 0.99 | 0.99 | | 0.99 | 0.97 | | |
| Frt | | | | 0.850 | | | 0.992 | | | 0.880 | | |
| Flt Protected | | 0.950 | | | | 0.950 | | | 0.950 | | | 0.950 |
| Satd. Flow (prot) | 0 | 1657 | 3390 | 1532 | 0 | 3228 | 3228 | 0 | 1679 | 1508 | 0 | 1679 |
| Flt Permitted | | 0.950 | | | | 0.950 | | | 0.357 | | | 0.142 |
| Satd. Flow (perm) | 0 | 1567 | 3390 | 1465 | 0 | 3204 | 3228 | 0 | 624 | 1508 | 0 | 251 |
| Right Turn on Red | | | | Yes | | | | Yes | | | Yes | |
| Satd. Flow (RTOR) | | | | 250 | | | 6 | | | 91 | | |
| Link Speed (k/h) | | | 60 | | | | 60 | | | 50 | | |
| Link Distance (m) | | | 447.3 | | | | 309.6 | | | 300.2 | | |
| Travel Time (s) | | | 26.8 | | | | 18.6 | | | 21.6 | | |
| Confl. Peds. (#/hr) | | 25 | | 16 | | 16 | | 25 | 13 | | 15 | 15 |
| Confl. Bikes (#/hr) | | | | | | | | 1 | | | 2 | |
| Peak Hour Factor | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Heavy Vehicles (%) | 0% | 7% | 2% | 1% | 0% | 4% | 6% | 0% | 3% | 5% | 2% | 3% |
| Adj. Flow (vph) | 17 | 28 | 1425 | 265 | 6 | 294 | 292 | 16 | 139 | 97 | 396 | 66 |
| Shared Lane Traffic (%) | | | | | | | | | | | | |
| Lane Group Flow (vph) | 0 | 45 | 1425 | 265 | 0 | 300 | 308 | 0 | 139 | 493 | 0 | 66 |
| Turn Type | Prot | Prot | NA | Perm | Prot | Prot | NA | | Perm | NA | | Perm |
| Protected Phases | 7 | 7 | 4 | | 3 | 3 | 8 | | | 2 | | |
| Permitted Phases | | | | 4 | | | | | 2 | | | 6 |
| Detector Phase | 7 | 7 | 4 | 4 | 3 | 3 | 8 | | 2 | 2 | | 6 |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | | 10.0 | 10.0 | | 10.0 |
| Minimum Split (s) | 10.9 | 10.9 | 23.9 | 23.9 | 10.9 | 10.9 | 23.9 | | 24.8 | 24.8 | | 24.8 |
| Total Split (s) | 13.2 | 13.2 | 59.0 | 59.0 | 17.0 | 17.0 | 62.8 | | 44.0 | 44.0 | | 44.0 |
| Total Split (%) | 11.0% | 11.0% | 49.2% | 49.2% | 14.2% | 14.2% | 52.3% | | 36.7% | 36.7% | | 36.7% |
| Maximum Green (s) | 7.3 | 7.3 | 53.1 | 53.1 | 11.1 | 11.1 | 56.9 | | 37.2 | 37.2 | | 37.2 |
| Yellow Time (s) | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | | 3.3 | 3.3 | | 3.3 |
| All-Red Time (s) | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | | 3.5 | 3.5 | | 3.5 |
| Lost Time Adjust (s) | | -1.9 | -1.9 | -1.9 | | -1.9 | -1.9 | | -2.8 | -2.8 | | -2.8 |
| Total Lost Time (s) | | 4.0 | 4.0 | 4.0 | | 4.0 | 4.0 | | 4.0 | 4.0 | | 4.0 |
| Lead/Lag | Lead | Lead | Lag | Lag | Lead | Lead | Lag | | | | | |
| Lead-Lag Optimize? | Yes | Yes | Yes | Yes | Yes | Yes | Yes | | | | | |
| Vehicle Extension (s) | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | | 3.0 | 3.0 | | 3.0 |
| Recall Mode | None | None | C-Max | C-Max | None | None | C-Max | | None | None | | None |
| Walk Time (s) | | | 7.0 | 7.0 | | | 7.0 | | 7.0 | 7.0 | | 7.0 |
| Flash Dont Walk (s) | | | 11.0 | 11.0 | | | 11.0 | | 11.0 | 11.0 | | 11.0 |
| Pedestrian Calls (#/hr) | | | 16 | 16 | | | 25 | | 15 | 15 | | 13 |
| Act Effct Green (s) | | 8.8 | 56.4 | 56.4 | | 13.5 | 63.3 | | 38.1 | 38.1 | | 38.1 |
| Actuated g/C Ratio | | 0.07 | 0.47 | 0.47 | | 0.11 | 0.53 | | 0.32 | 0.32 | | 0.32 |

4: Maitland Avenue/Sherbourne Road & Carling Avenue
 1995 Carling Avenue


Future (2029) Total Traffic
 AM Peak Hour



| Lane Group | SBT | SBR |
|-------------------------|-------|------|
| Lane Configurations | ↔ | |
| Traffic Volume (vph) | 308 | 16 |
| Future Volume (vph) | 308 | 16 |
| Ideal Flow (vphpl) | 1800 | 1800 |
| Storage Length (m) | | 0.0 |
| Storage Lanes | | 0 |
| Taper Length (m) | | |
| Lane Util. Factor | 1.00 | 1.00 |
| Ped Bike Factor | 1.00 | |
| Frt | 0.993 | |
| Flt Protected | | |
| Satd. Flow (prot) | 1765 | 0 |
| Flt Permitted | | |
| Satd. Flow (perm) | 1765 | 0 |
| Right Turn on Red | | Yes |
| Satd. Flow (RTOR) | 2 | |
| Link Speed (k/h) | 50 | |
| Link Distance (m) | 301.0 | |
| Travel Time (s) | 21.7 | |
| Confl. Peds. (#/hr) | | 13 |
| Confl. Bikes (#/hr) | | |
| Peak Hour Factor | 1.00 | 1.00 |
| Heavy Vehicles (%) | 2% | 6% |
| Adj. Flow (vph) | 308 | 16 |
| Shared Lane Traffic (%) | | |
| Lane Group Flow (vph) | 324 | 0 |
| Turn Type | NA | |
| Protected Phases | 6 | |
| Permitted Phases | | |
| Detector Phase | 6 | |
| Switch Phase | | |
| Minimum Initial (s) | 10.0 | |
| Minimum Split (s) | 24.8 | |
| Total Split (s) | 44.0 | |
| Total Split (%) | 36.7% | |
| Maximum Green (s) | 37.2 | |
| Yellow Time (s) | 3.3 | |
| All-Red Time (s) | 3.5 | |
| Lost Time Adjust (s) | -2.8 | |
| Total Lost Time (s) | 4.0 | |
| Lead/Lag | | |
| Lead-Lag Optimize? | | |
| Vehicle Extension (s) | 3.0 | |
| Recall Mode | None | |
| Walk Time (s) | 7.0 | |
| Flash Dont Walk (s) | 11.0 | |
| Pedestrian Calls (#/hr) | 13 | |
| Act Effct Green (s) | 38.1 | |
| Actuated g/C Ratio | 0.32 | |

4: Maitland Avenue/Sherbourne Road & Carling Avenue
1995 Carling Avenue

Future (2029) Total Traffic
AM Peak Hour




| Lane Group | EBU | EBL | EBT | EBR | WBU | WBL | WBT | WBR | NBL | NBT | NBR | SBL |
|------------------------|-----|------|--------|-------|-----|-------|-------|-----|-------|--------|-----|-------|
| v/c Ratio | | 0.37 | 0.89 | 0.32 | | 0.83 | 0.18 | | 0.70 | 0.91 | | 0.84 |
| Control Delay | | 61.7 | 38.2 | 4.0 | | 71.9 | 16.1 | | 55.8 | 54.3 | | 103.0 |
| Queue Delay | | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 |
| Total Delay | | 61.7 | 38.2 | 4.0 | | 71.9 | 16.1 | | 55.8 | 54.3 | | 103.0 |
| LOS | | E | D | A | | E | B | | E | D | | F |
| Approach Delay | | | 33.6 | | | | 43.6 | | | 54.6 | | |
| Approach LOS | | | C | | | | D | | | D | | |
| Queue Length 50th (m) | | 10.2 | 161.2 | 1.9 | | 36.3 | 20.4 | | 28.0 | 91.6 | | 14.0 |
| Queue Length 95th (m) | | 22.3 | #209.4 | 16.4 | | #59.3 | 29.0 | | #57.3 | #152.9 | | #40.8 |
| Internal Link Dist (m) | | | 423.3 | | | | 285.6 | | | 276.2 | | |
| Turn Bay Length (m) | | 55.0 | | 130.0 | | 115.0 | | | 75.0 | | | 45.0 |
| Base Capacity (vph) | | 127 | 1593 | 820 | | 362 | 1706 | | 208 | 563 | | 83 |
| Starvation Cap Reductn | | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | | 0 |
| Spillback Cap Reductn | | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | | 0 |
| Storage Cap Reductn | | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | | 0 |
| Reduced v/c Ratio | | 0.35 | 0.89 | 0.32 | | 0.83 | 0.18 | | 0.67 | 0.88 | | 0.80 |

Intersection Summary

Area Type: Other
 Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 40 (33%), Referenced to phase 4:EBT and 8:WBT, Start of Green
 Natural Cycle: 75
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.91
 Intersection Signal Delay: 41.1
 Intersection LOS: D
 Intersection Capacity Utilization 104.6%
 ICU Level of Service G
 Analysis Period (min) 15
 # 95th percentile volume exceeds capacity, queue may be longer.
 Queue shown is maximum after two cycles.

Splits and Phases: 4: Maitland Avenue/Sherbourne Road & Carling Avenue



4: Maitland Avenue/Sherbourne Road & Carling Avenue
 1995 Carling Avenue


Future (2029) Total Traffic
 AM Peak Hour



| Lane Group | SBT | SBR |
|------------------------|-------|-----|
| v/c Ratio | 0.58 | |
| Control Delay | 38.3 | |
| Queue Delay | 0.0 | |
| Total Delay | 38.3 | |
| LOS | D | |
| Approach Delay | 49.2 | |
| Approach LOS | D | |
| Queue Length 50th (m) | 61.6 | |
| Queue Length 95th (m) | 90.3 | |
| Internal Link Dist (m) | 277.0 | |
| Turn Bay Length (m) | | |
| Base Capacity (vph) | 589 | |
| Starvation Cap Reductn | 0 | |
| Spillback Cap Reductn | 0 | |
| Storage Cap Reductn | 0 | |
| Reduced v/c Ratio | 0.55 | |
| Intersection Summary | | |

1: Iroquois Road & Carling Avenue
1995 Carling Avenue

Future (2029) Total Traffic
PM Peak Hour



| Lane Group | EBU | EBL | EBT | EBR | WBU | WBL | WBT | WBR | NBL | NBT | NBR | SBL |
|-------------------------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|------|-------|
| Lane Configurations | | | | | | | | | | | | |
| Traffic Volume (vph) | 2 | 41 | 675 | 4 | 40 | 17 | 1427 | 107 | 13 | 20 | 10 | 117 |
| Future Volume (vph) | 2 | 41 | 675 | 4 | 40 | 17 | 1427 | 107 | 13 | 20 | 10 | 117 |
| Ideal Flow (vphpl) | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 |
| Storage Length (m) | | 25.0 | | 40.0 | | 20.0 | | 85.0 | 0.0 | | 0.0 | 50.0 |
| Storage Lanes | | 1 | | 1 | | 1 | | 1 | 0 | | 0 | 1 |
| Taper Length (m) | | 7.5 | | | | 7.5 | | | 7.5 | | | 7.5 |
| Lane Util. Factor | 0.95 | 1.00 | 0.95 | 1.00 | 0.91 | 1.00 | 0.91 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Ped Bike Factor | | 0.99 | | 0.92 | | 0.98 | | 0.90 | | 0.99 | | 0.98 |
| Frt | | | | 0.850 | | | | 0.850 | | 0.969 | | |
| Flt Protected | | 0.950 | | | | 0.950 | | | | 0.985 | | 0.950 |
| Satd. Flow (prot) | 0 | 1729 | 3390 | 1547 | 0 | 1699 | 4919 | 1547 | 0 | 1726 | 0 | 1712 |
| Flt Permitted | | 0.112 | | | | 0.395 | | | | 0.921 | | 0.761 |
| Satd. Flow (perm) | 0 | 203 | 3390 | 1425 | 0 | 695 | 4919 | 1391 | 0 | 1602 | 0 | 1350 |
| Right Turn on Red | | | | Yes | | | | Yes | | | Yes | |
| Satd. Flow (RTOR) | | | | 95 | | | | 107 | | 10 | | |
| Link Speed (k/h) | | | 60 | | | | 60 | | | 50 | | |
| Link Distance (m) | | | 305.5 | | | | 137.5 | | | 297.2 | | |
| Travel Time (s) | | | 18.3 | | | | 8.3 | | | 21.4 | | |
| Confl. Peds. (#/hr) | | 28 | | 19 | | 19 | | 28 | 28 | | 17 | 17 |
| Confl. Bikes (#/hr) | | | | 6 | | | | | | | | |
| Peak Hour Factor | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Heavy Vehicles (%) | 0% | 0% | 2% | 0% | 0% | 6% | 1% | 0% | 0% | 0% | 0% | 1% |
| Adj. Flow (vph) | 2 | 41 | 675 | 4 | 40 | 17 | 1427 | 107 | 13 | 20 | 10 | 117 |
| Shared Lane Traffic (%) | | | | | | | | | | | | |
| Lane Group Flow (vph) | 0 | 43 | 675 | 4 | 0 | 57 | 1427 | 107 | 0 | 43 | 0 | 117 |
| Turn Type | pm+pt | pm+pt | NA | Perm | pm+pt | pm+pt | NA | Perm | Perm | NA | | Perm |
| Protected Phases | 7 | 7 | 4 | | 3 | 3 | 8 | | | 2 | | |
| Permitted Phases | 4 | 4 | | 4 | 8 | 8 | | 8 | 2 | | | 6 |
| Detector Phase | 7 | 7 | 4 | 4 | 3 | 3 | 8 | 8 | 2 | 2 | | 6 |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 10.0 | 10.0 | | 10.0 |
| Minimum Split (s) | 12.0 | 12.0 | 28.3 | 28.3 | 12.0 | 12.0 | 28.3 | 28.3 | 47.3 | 47.3 | | 47.3 |
| Total Split (s) | 12.0 | 12.0 | 71.0 | 71.0 | 12.0 | 12.0 | 71.0 | 71.0 | 47.0 | 47.0 | | 47.0 |
| Total Split (%) | 9.2% | 9.2% | 54.6% | 54.6% | 9.2% | 9.2% | 54.6% | 54.6% | 36.2% | 36.2% | | 36.2% |
| Maximum Green (s) | 5.0 | 5.0 | 64.7 | 64.7 | 5.0 | 5.0 | 64.7 | 64.7 | 39.7 | 39.7 | | 39.7 |
| Yellow Time (s) | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.3 | 3.3 | | 3.3 |
| All-Red Time (s) | 3.3 | 3.3 | 2.6 | 2.6 | 3.3 | 3.3 | 2.6 | 2.6 | 4.0 | 4.0 | | 4.0 |
| Lost Time Adjust (s) | | -3.0 | -2.3 | -2.3 | | | -3.0 | -2.3 | -2.3 | | -3.3 | -3.3 |
| Total Lost Time (s) | | 4.0 | 4.0 | 4.0 | | | 4.0 | 4.0 | 4.0 | | 4.0 | 4.0 |
| Lead/Lag | Lead | Lead | Lag | Lag | Lead | Lead | Lag | Lag | | | | |
| Lead-Lag Optimize? | Yes | Yes | Yes | Yes | Yes | Yes | Yes | Yes | | | | |
| Vehicle Extension (s) | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | | 3.0 |
| Recall Mode | Max | Max | C-Max | C-Max | None | None | C-Max | C-Max | None | None | | None |
| Walk Time (s) | | | 10.0 | 10.0 | | | 10.0 | 10.0 | 27.0 | 27.0 | | 27.0 |
| Flash Dont Walk (s) | | | 12.0 | 12.0 | | | 12.0 | 12.0 | 13.0 | 13.0 | | 13.0 |
| Pedestrian Calls (#/hr) | | | 19 | 19 | | | 28 | 28 | 17 | 17 | | 28 |
| Act Effct Green (s) | | 87.7 | 80.3 | 80.3 | | 75.3 | 67.0 | 67.0 | | 31.9 | | 31.9 |
| Actuated g/C Ratio | | 0.67 | 0.62 | 0.62 | | 0.58 | 0.52 | 0.52 | | 0.25 | | 0.25 |

1: Iroquois Road & Carling Avenue
 1995 Carling Avenue


Future (2029) Total Traffic
 PM Peak Hour



| Lane Group | SBT | SBR |
|-------------------------|-------|------|
| Lane Configurations | ↔ | |
| Traffic Volume (vph) | 23 | 60 |
| Future Volume (vph) | 23 | 60 |
| Ideal Flow (vphpl) | 1800 | 1800 |
| Storage Length (m) | | 0.0 |
| Storage Lanes | | 0 |
| Taper Length (m) | | |
| Lane Util. Factor | 1.00 | 1.00 |
| Ped Bike Factor | 0.97 | |
| Frt | 0.892 | |
| Flt Protected | | |
| Satd. Flow (prot) | 1554 | 0 |
| Flt Permitted | | |
| Satd. Flow (perm) | 1554 | 0 |
| Right Turn on Red | | Yes |
| Satd. Flow (RTOR) | 31 | |
| Link Speed (k/h) | 50 | |
| Link Distance (m) | 304.9 | |
| Travel Time (s) | 22.0 | |
| Confl. Peds. (#/hr) | | 28 |
| Confl. Bikes (#/hr) | | 2 |
| Peak Hour Factor | 1.00 | 1.00 |
| Heavy Vehicles (%) | 0% | 2% |
| Adj. Flow (vph) | 23 | 60 |
| Shared Lane Traffic (%) | | |
| Lane Group Flow (vph) | 83 | 0 |
| Turn Type | NA | |
| Protected Phases | 6 | |
| Permitted Phases | | |
| Detector Phase | 6 | |
| Switch Phase | | |
| Minimum Initial (s) | 10.0 | |
| Minimum Split (s) | 47.3 | |
| Total Split (s) | 47.0 | |
| Total Split (%) | 36.2% | |
| Maximum Green (s) | 39.7 | |
| Yellow Time (s) | 3.3 | |
| All-Red Time (s) | 4.0 | |
| Lost Time Adjust (s) | -3.3 | |
| Total Lost Time (s) | 4.0 | |
| Lead/Lag | | |
| Lead-Lag Optimize? | | |
| Vehicle Extension (s) | 3.0 | |
| Recall Mode | None | |
| Walk Time (s) | 27.0 | |
| Flash Dont Walk (s) | 13.0 | |
| Pedestrian Calls (#/hr) | 28 | |
| Act Effct Green (s) | 31.9 | |
| Actuated g/C Ratio | 0.25 | |

1: Iroquois Road & Carling Avenue
1995 Carling Avenue

Future (2029) Total Traffic
PM Peak Hour




| Lane Group | EBU | EBL | EBT | EBR | WBU | WBL | WBT | WBR | NBL | NBT | NBR | SBL |
|------------------------|-----|------|-------|------|-----|------|-------|------|-----|-------|-----|------|
| v/c Ratio | | 0.12 | 0.32 | 0.00 | | 0.12 | 0.56 | 0.14 | | 0.11 | | 0.35 |
| Control Delay | | 10.3 | 15.2 | 0.0 | | 10.4 | 22.6 | 3.3 | | 26.5 | | 40.4 |
| Queue Delay | | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 | | 0.0 | | 0.0 |
| Total Delay | | 10.3 | 15.2 | 0.0 | | 10.4 | 22.6 | 3.3 | | 26.5 | | 40.4 |
| LOS | | B | B | A | | B | C | A | | C | | D |
| Approach Delay | | | 14.8 | | | | 20.9 | | | 26.5 | | |
| Approach LOS | | | B | | | | C | | | C | | |
| Queue Length 50th (m) | | 4.2 | 53.3 | 0.0 | | 5.6 | 88.6 | 0.0 | | 5.8 | | 21.9 |
| Queue Length 95th (m) | | 9.0 | 67.3 | 0.0 | | 11.2 | 102.5 | 8.9 | | 14.4 | | 37.8 |
| Internal Link Dist (m) | | | 281.5 | | | | 113.5 | | | 273.2 | | |
| Turn Bay Length (m) | | 25.0 | | 40.0 | | 20.0 | | 85.0 | | | | 50.0 |
| Base Capacity (vph) | | 361 | 2094 | 916 | | 466 | 2535 | 768 | | 536 | | 446 |
| Starvation Cap Reductn | | 0 | 0 | 0 | | 0 | 0 | 0 | | 0 | | 0 |
| Spillback Cap Reductn | | 0 | 0 | 0 | | 0 | 0 | 0 | | 0 | | 0 |
| Storage Cap Reductn | | 0 | 0 | 0 | | 0 | 0 | 0 | | 0 | | 0 |
| Reduced v/c Ratio | | 0.12 | 0.32 | 0.00 | | 0.12 | 0.56 | 0.14 | | 0.08 | | 0.26 |

Intersection Summary

| | |
|------------------------------------|---|
| Area Type: | Other |
| Cycle Length: | 130 |
| Actuated Cycle Length: | 130 |
| Offset: | 95 (73%), Referenced to phase 4:EBTL and 8:WBTL, Start of Green |
| Natural Cycle: | 90 |
| Control Type: | Actuated-Coordinated |
| Maximum v/c Ratio: | 0.56 |
| Intersection Signal Delay: | 20.2 |
| Intersection LOS: | C |
| Intersection Capacity Utilization: | 68.8% |
| ICU Level of Service: | C |
| Analysis Period (min): | 15 |

Splits and Phases: 1: Iroquois Road & Carling Avenue



1: Iroquois Road & Carling Avenue
 1995 Carling Avenue

Future (2029) Total Traffic
 PM Peak Hour



| Lane Group | SBT | SBR |
|------------------------|-------|-----|
| v/c Ratio | 0.21 | |
| Control Delay | 22.4 | |
| Queue Delay | 0.0 | |
| Total Delay | 22.4 | |
| LOS | C | |
| Approach Delay | 32.9 | |
| Approach LOS | C | |
| Queue Length 50th (m) | 9.2 | |
| Queue Length 95th (m) | 21.3 | |
| Internal Link Dist (m) | 280.9 | |
| Turn Bay Length (m) | | |
| Base Capacity (vph) | 534 | |
| Starvation Cap Reductn | 0 | |
| Spillback Cap Reductn | 0 | |
| Storage Cap Reductn | 0 | |
| Reduced v/c Ratio | 0.16 | |
| Intersection Summary | | |

2: Hare Avenue & Carling Avenue
 1995 Carling Avenue

Future (2029) Total Traffic
 PM Peak Hour

| Intersection | | | | | | |
|--------------------------|------|------|------|------|------|------|
| Int Delay, s/veh | 0.4 | | | | | |
| Movement | EBT | EBR | WBL | WBT | NBL | NBR |
| Lane Configurations | ↑↑ | ↑ | ↓ | ↑↑ | ↑ | |
| Traffic Vol, veh/h | 829 | 8 | 37 | 1576 | 10 | 11 |
| Future Vol, veh/h | 829 | 8 | 37 | 1576 | 10 | 11 |
| Conflicting Peds, #/hr | 0 | 0 | 0 | 0 | 0 | 0 |
| Sign Control | Free | Free | Free | Free | Stop | Stop |
| RT Channelized | - | None | - | None | - | None |
| Storage Length | - | 350 | 250 | - | 0 | - |
| Veh in Median Storage, # | 0 | - | - | 0 | 0 | - |
| Grade, % | 0 | - | - | 0 | 0 | - |
| Peak Hour Factor | 100 | 100 | 100 | 100 | 100 | 100 |
| Heavy Vehicles, % | 0 | 0 | 0 | 0 | 0 | 0 |
| Mvmt Flow | 829 | 8 | 37 | 1576 | 10 | 11 |

| Major/Minor | Major1 | | Major2 | | Minor1 | |
|----------------------|--------|---|--------|---|--------|-----|
| Conflicting Flow All | 0 | 0 | 837 | 0 | 1691 | 415 |
| Stage 1 | - | - | - | - | 829 | - |
| Stage 2 | - | - | - | - | 862 | - |
| Critical Hdwy | - | - | 4.1 | - | 6.8 | 6.9 |
| Critical Hdwy Stg 1 | - | - | - | - | 5.8 | - |
| Critical Hdwy Stg 2 | - | - | - | - | 5.8 | - |
| Follow-up Hdwy | - | - | 2.2 | - | 3.5 | 3.3 |
| Pot Cap-1 Maneuver | - | - | 806 | - | 86 | 592 |
| Stage 1 | - | - | - | - | 394 | - |
| Stage 2 | - | - | - | - | 379 | - |
| Platoon blocked, % | - | - | - | - | - | - |
| Mov Cap-1 Maneuver | - | - | 806 | - | 82 | 592 |
| Mov Cap-2 Maneuver | - | - | - | - | 82 | - |
| Stage 1 | - | - | - | - | 394 | - |
| Stage 2 | - | - | - | - | 362 | - |

| Approach | EB | WB | NB |
|----------------------|----|-----|------|
| HCM Control Delay, s | 0 | 0.2 | 33.1 |
| HCM LOS | | | D |

| Minor Lane/Major Mvmt | NBLn1 | EBT | EBR | WBL | WBT |
|-----------------------|-------|-----|-----|-------|-----|
| Capacity (veh/h) | 149 | - | - | 806 | - |
| HCM Lane V/C Ratio | 0.141 | - | - | 0.046 | - |
| HCM Control Delay (s) | 33.1 | - | - | 9.7 | - |
| HCM Lane LOS | D | - | - | A | - |
| HCM 95th %tile Q(veh) | 0.5 | - | - | 0.1 | - |

3: Carling Avenue & Bromley Road
 1995 Carling Avenue

Future (2029) Total Traffic
 PM Peak Hour

| Intersection | | | | | | |
|--------------------------|------|------|------|------|------|------|
| Int Delay, s/veh | 0.2 | | | | | |
| Movement | EBL | EBT | WBT | WBR | SBL | SBR |
| Lane Configurations | | ↑↑ | ↑↑ | ↑ | | ↑ |
| Traffic Vol, veh/h | 0 | 838 | 1576 | 52 | 0 | 35 |
| Future Vol, veh/h | 0 | 838 | 1576 | 52 | 0 | 35 |
| Conflicting Peds, #/hr | 0 | 0 | 0 | 0 | 0 | 0 |
| Sign Control | Free | Free | Free | Free | Stop | Stop |
| RT Channelized | - | None | - | None | - | None |
| Storage Length | - | - | - | 300 | - | 0 |
| Veh in Median Storage, # | - | 0 | 0 | - | 0 | - |
| Grade, % | - | 0 | 0 | - | 0 | - |
| Peak Hour Factor | 100 | 100 | 100 | 100 | 100 | 100 |
| Heavy Vehicles, % | 0 | 0 | 0 | 0 | 0 | 8 |
| Mvmt Flow | 0 | 838 | 1576 | 52 | 0 | 35 |





















| Major/Minor | Major1 | Major2 | Minor2 | | |
|----------------------|--------|--------|--------|---|--------|
| Conflicting Flow All | - | 0 | - | 0 | - 788 |
| Stage 1 | - | - | - | - | - |
| Stage 2 | - | - | - | - | - |
| Critical Hdwy | - | - | - | - | - 7.06 |
| Critical Hdwy Stg 1 | - | - | - | - | - |
| Critical Hdwy Stg 2 | - | - | - | - | - |
| Follow-up Hdwy | - | - | - | - | - 3.38 |
| Pot Cap-1 Maneuver | 0 | - | - | - | 0 321 |
| Stage 1 | 0 | - | - | - | 0 - |
| Stage 2 | 0 | - | - | - | 0 - |
| Platoon blocked, % | - | - | - | - | - |
| Mov Cap-1 Maneuver | - | - | - | - | - 321 |
| Mov Cap-2 Maneuver | - | - | - | - | - |
| Stage 1 | - | - | - | - | - |
| Stage 2 | - | - | - | - | - |

| Approach | EB | WB | SB |
|----------------------|----|----|------|
| HCM Control Delay, s | 0 | 0 | 17.6 |
| HCM LOS | | | C |

| Minor Lane/Major Mvmt | EBT | WBT | WBR | SBLn1 |
|-----------------------|-----|-----|-----|-------|
| Capacity (veh/h) | - | - | - | 321 |
| HCM Lane V/C Ratio | - | - | - | 0.109 |
| HCM Control Delay (s) | - | - | - | 17.6 |
| HCM Lane LOS | - | - | - | C |
| HCM 95th %tile Q(veh) | - | - | - | 0.4 |

4: Maitland Avenue/Sherbourne Road & Carling Avenue
1995 Carling Avenue

Future (2029) Total Traffic
PM Peak Hour

| |  |  |  |  |  |  |  |  |  |  |  |  |
|-------------------------|---|---|---|---|---|---|--|---|---|---|---|---|
| Lane Group | EBU | EBL | EBT | EBR | WBU | WBL | WBT | WBR | NBL | NBT | NBR | SBL |
| Lane Configurations | |  |  |  | |  |  | |  |  | |  |
| Traffic Volume (vph) | 26 | 60 | 579 | 174 | 8 | 715 | 1311 | 53 | 246 | 208 | 208 | 47 |
| Future Volume (vph) | 26 | 60 | 579 | 174 | 8 | 715 | 1311 | 53 | 246 | 208 | 208 | 47 |
| Ideal Flow (vphpl) | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 | 1800 |
| Storage Length (m) | | 55.0 | | 130.0 | | 115.0 | | 0.0 | 75.0 | | 0.0 | 45.0 |
| Storage Lanes | | 1 | | 1 | | 1 | | 0 | 1 | | 0 | 1 |
| Taper Length (m) | | 7.5 | | | | 7.5 | | | 7.5 | | | 7.5 |
| Lane Util. Factor | 0.95 | 1.00 | 0.95 | 1.00 | 0.95 | 0.97 | 0.95 | 0.95 | 1.00 | 1.00 | 1.00 | 1.00 |
| Ped Bike Factor | | 0.98 | | 0.94 | | 0.96 | 0.99 | | 0.98 | 0.98 | | 0.99 |
| Frt | | | | 0.850 | | | 0.994 | | | 0.925 | | |
| Flt Protected | | 0.950 | | | | 0.950 | | | 0.950 | | | 0.950 |
| Satd. Flow (prot) | 0 | 1729 | 3390 | 1532 | 0 | 3321 | 3381 | 0 | 1729 | 1624 | 0 | 1729 |
| Flt Permitted | | 0.950 | | | | 0.950 | | | 0.482 | | | 0.258 |
| Satd. Flow (perm) | 0 | 1698 | 3390 | 1438 | 0 | 3198 | 3381 | 0 | 857 | 1624 | 0 | 465 |
| Right Turn on Red | | | | Yes | | | | Yes | | | Yes | |
| Satd. Flow (RTOR) | | | | 174 | | | 4 | | | 51 | | |
| Link Speed (k/h) | | | 60 | | | | 60 | | | 50 | | |
| Link Distance (m) | | | 447.3 | | | | 309.6 | | | 300.2 | | |
| Travel Time (s) | | | 26.8 | | | | 18.6 | | | 21.6 | | |
| Confl. Peds. (#/hr) | | 36 | | 25 | | 25 | | 36 | 20 | | 15 | 15 |
| Confl. Bikes (#/hr) | | | | | | | | 2 | | | | |
| Peak Hour Factor | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Heavy Vehicles (%) | 0% | 0% | 2% | 1% | 0% | 1% | 1% | 4% | 0% | 0% | 3% | 0% |
| Adj. Flow (vph) | 26 | 60 | 579 | 174 | 8 | 715 | 1311 | 53 | 246 | 208 | 208 | 47 |
| Shared Lane Traffic (%) | | | | | | | | | | | | |
| Lane Group Flow (vph) | 0 | 86 | 579 | 174 | 0 | 723 | 1364 | 0 | 246 | 416 | 0 | 47 |
| Turn Type | Prot | Prot | NA | Perm | Prot | Prot | NA | | Perm | NA | | Perm |
| Protected Phases | 7 | 7 | 4 | | 3 | 3 | 8 | | | 2 | | |
| Permitted Phases | | | | 4 | | | | | 2 | | | 6 |
| Detector Phase | 7 | 7 | 4 | 4 | 3 | 3 | 8 | | 2 | 2 | | 6 |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | | 10.0 | 10.0 | | 10.0 |
| Minimum Split (s) | 10.9 | 10.9 | 23.9 | 23.9 | 10.9 | 10.9 | 23.9 | | 24.8 | 24.8 | | 24.8 |
| Total Split (s) | 11.0 | 11.0 | 32.0 | 32.0 | 34.0 | 34.0 | 55.0 | | 54.0 | 54.0 | | 54.0 |
| Total Split (%) | 9.2% | 9.2% | 26.7% | 26.7% | 28.3% | 28.3% | 45.8% | | 45.0% | 45.0% | | 45.0% |
| Maximum Green (s) | 5.1 | 5.1 | 26.1 | 26.1 | 28.1 | 28.1 | 49.1 | | 47.2 | 47.2 | | 47.2 |
| Yellow Time (s) | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | | 3.3 | 3.3 | | 3.3 |
| All-Red Time (s) | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | | 3.5 | 3.5 | | 3.5 |
| Lost Time Adjust (s) | | -1.9 | -1.9 | -1.9 | | -1.9 | -1.9 | | -2.8 | -2.8 | | -2.8 |
| Total Lost Time (s) | | 4.0 | 4.0 | 4.0 | | 4.0 | 4.0 | | 4.0 | 4.0 | | 4.0 |
| Lead/Lag | Lead | Lead | Lag | Lag | Lead | Lead | Lag | | | | | |
| Lead-Lag Optimize? | Yes | Yes | Yes | Yes | Yes | Yes | Yes | | | | | |
| Vehicle Extension (s) | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | | 3.0 | 3.0 | | 3.0 |
| Recall Mode | None | None | C-Max | C-Max | None | None | C-Max | | None | None | | None |
| Walk Time (s) | | | 7.0 | 7.0 | | | 7.0 | | 7.0 | 7.0 | | 7.0 |
| Flash Dont Walk (s) | | | 11.0 | 11.0 | | | 11.0 | | 11.0 | 11.0 | | 11.0 |
| Pedestrian Calls (#/hr) | | | 25 | 25 | | | 36 | | 15 | 15 | | 20 |
| Act Effct Green (s) | | 11.1 | 37.2 | 37.2 | | 30.9 | 57.0 | | 39.9 | 39.9 | | 39.9 |
| Actuated g/C Ratio | | 0.09 | 0.31 | 0.31 | | 0.26 | 0.48 | | 0.33 | 0.33 | | 0.33 |

4: Maitland Avenue/Sherbourne Road & Carling Avenue
 1995 Carling Avenue


Future (2029) Total Traffic
 PM Peak Hour



| Lane Group | SBT | SBR |
|-------------------------|-------|------|
| Lane Configurations | ↔ | |
| Traffic Volume (vph) | 196 | 44 |
| Future Volume (vph) | 196 | 44 |
| Ideal Flow (vphpl) | 1800 | 1800 |
| Storage Length (m) | | 0.0 |
| Storage Lanes | | 0 |
| Taper Length (m) | | |
| Lane Util. Factor | 1.00 | 1.00 |
| Ped Bike Factor | 0.99 | |
| Frt | 0.972 | |
| Flt Protected | | |
| Satd. Flow (prot) | 1746 | 0 |
| Flt Permitted | | |
| Satd. Flow (perm) | 1746 | 0 |
| Right Turn on Red | | Yes |
| Satd. Flow (RTOR) | 12 | |
| Link Speed (k/h) | 50 | |
| Link Distance (m) | 301.0 | |
| Travel Time (s) | 21.7 | |
| Confl. Peds. (#/hr) | | 20 |
| Confl. Bikes (#/hr) | | |
| Peak Hour Factor | 1.00 | 1.00 |
| Heavy Vehicles (%) | 0% | 2% |
| Adj. Flow (vph) | 196 | 44 |
| Shared Lane Traffic (%) | | |
| Lane Group Flow (vph) | 240 | 0 |
| Turn Type | NA | |
| Protected Phases | 6 | |
| Permitted Phases | | |
| Detector Phase | 6 | |
| Switch Phase | | |
| Minimum Initial (s) | 10.0 | |
| Minimum Split (s) | 24.8 | |
| Total Split (s) | 54.0 | |
| Total Split (%) | 45.0% | |
| Maximum Green (s) | 47.2 | |
| Yellow Time (s) | 3.3 | |
| All-Red Time (s) | 3.5 | |
| Lost Time Adjust (s) | -2.8 | |
| Total Lost Time (s) | 4.0 | |
| Lead/Lag | | |
| Lead-Lag Optimize? | | |
| Vehicle Extension (s) | 3.0 | |
| Recall Mode | None | |
| Walk Time (s) | 7.0 | |
| Flash Dont Walk (s) | 11.0 | |
| Pedestrian Calls (#/hr) | 20 | |
| Act Effct Green (s) | 39.9 | |
| Actuated g/C Ratio | 0.33 | |

4: Maitland Avenue/Sherbourne Road & Carling Avenue
1995 Carling Avenue

Future (2029) Total Traffic
PM Peak Hour




| Lane Group | EBU | EBL | EBT | EBR | WBU | WBL | WBT | WBR | NBL | NBT | NBR | SBL |
|------------------------|-----|-------|-------|-------|-----|--------|--------|-----|------|-------|-----|------|
| v/c Ratio | | 0.54 | 0.55 | 0.31 | | 0.85 | 0.85 | | 0.86 | 0.72 | | 0.31 |
| Control Delay | | 65.9 | 39.2 | 7.1 | | 52.7 | 35.4 | | 64.0 | 37.2 | | 32.1 |
| Queue Delay | | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 |
| Total Delay | | 65.9 | 39.2 | 7.1 | | 52.7 | 35.4 | | 64.0 | 37.2 | | 32.1 |
| LOS | | E | D | A | | D | D | | E | D | | C |
| Approach Delay | | | 35.3 | | | | 41.4 | | | 47.2 | | |
| Approach LOS | | | D | | | | D | | | D | | |
| Queue Length 50th (m) | | 19.0 | 62.7 | 0.0 | | 81.1 | 157.5 | | 52.7 | 74.2 | | 8.0 |
| Queue Length 95th (m) | | #50.3 | 86.7 | 17.4 | | #114.6 | #208.3 | | 79.2 | 98.0 | | 16.8 |
| Internal Link Dist (m) | | | 423.3 | | | | 285.6 | | | 276.2 | | |
| Turn Bay Length (m) | | 55.0 | | 130.0 | | 115.0 | | | 75.0 | | | 45.0 |
| Base Capacity (vph) | | 159 | 1051 | 565 | | 870 | 1607 | | 357 | 706 | | 193 |
| Starvation Cap Reductn | | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | | 0 |
| Spillback Cap Reductn | | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | | 0 |
| Storage Cap Reductn | | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | | 0 |
| Reduced v/c Ratio | | 0.54 | 0.55 | 0.31 | | 0.83 | 0.85 | | 0.69 | 0.59 | | 0.24 |

Intersection Summary

Area Type: Other
 Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 103 (86%), Referenced to phase 4:EBT and 8:WBT, Start of Green
 Natural Cycle: 80
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.86
 Intersection Signal Delay: 40.2
 Intersection LOS: D
 Intersection Capacity Utilization 92.6%
 ICU Level of Service F
 Analysis Period (min) 15
 # 95th percentile volume exceeds capacity, queue may be longer.
 Queue shown is maximum after two cycles.

Splits and Phases: 4: Maitland Avenue/Sherbourne Road & Carling Avenue



4: Maitland Avenue/Sherbourne Road & Carling Avenue
 1995 Carling Avenue

Future (2029) Total Traffic
 PM Peak Hour



| Lane Group | SBT | SBR |
|------------------------|-------|-----|
| v/c Ratio | 0.41 | |
| Control Delay | 29.8 | |
| Queue Delay | 0.0 | |
| Total Delay | 29.8 | |
| LOS | C | |
| Approach Delay | 30.2 | |
| Approach LOS | C | |
| Queue Length 50th (m) | 40.3 | |
| Queue Length 95th (m) | 55.3 | |
| Internal Link Dist (m) | 277.0 | |
| Turn Bay Length (m) | | |
| Base Capacity (vph) | 734 | |
| Starvation Cap Reductn | 0 | |
| Spillback Cap Reductn | 0 | |
| Storage Cap Reductn | 0 | |
| Reduced v/c Ratio | 0.33 | |
| Intersection Summary | | |