





SOUTH NEPEAN TOWN CENTRE BLOCK 4

3288 GREENBANK ROAD






LIST OF DRAWINGS:

L-01 - LANDSCAPE PLAN L-02 - LANDSCAPE PLAN

01 - DETAILS

D-02 - ROW & SOIL VOLUME








NILOCK Pattern A www.unilock.com 1-800-UNILOCK Notes: AutoCAD® hatch pattern files can be downloaded fror www.unilock.com for use in architectural drawings. 100% Standard Some patterns may not necessarily reflect the percentages of stone sizes within a particular bundle percentages of stone sizes within a particular bundle configuration. In some cases you may have extras in one or more of the sizes. This must be accounted for in your planning and design.

MULTI-USE PATHWAY PAVERS - OPTILOC



GRANITE FUSION





TYPICAL WALKWAY PAVERS - ARTLINE

- ACER RUBRUM AND CELTIS OCCIDENTALIS TO BE SPRING DUG SPECIMENS AND PLANTED IN THE SPRING ONLY. 2. THE LOCATION OF THE TREES SHOWN ON THIS PLAN IS APPROXIMATE AND SHALL NOT BE SCALED FROM THIS DRAWING.
- THIS PLAN MUST BE READ IN CONJUNCTION WITH THE APPROVED CUP AND CITY CROSS SECTIONS.
- 3. CONTRACTOR SHALL ENSURE THAT ALL UTILITY LOCATIONS ARE OBTAINED PRIOR TO ANY EXCAVATION FOR LANDSCAPING.
- 4. LOCATION OF ALL PLANT MATERIALS TO BE STAKED BY THE CONTRACTOR AND VERIFIED IN THE FIELD BY LANDSCAPE ARCHITECT & CITY OF OTTAWA PRIOR TO THE EXCAVATION OF PITS.
- 5. ALL PLANT MATERIAL SHALL BE NURSERY GROWN STOCK UNLESS OTHERWISE NOTED.
- 6. TREES TO HAVE A MINIMUM 1800 CLEAR STEM ABOVE GRADE.
- 7. PLACE SOD ON A MINIMUM 150mm TOPSOIL.
- 8. CONTRACTOR TO MAKE GOOD ALL EXISTING AREAS DAMAGED BY HIS WORK TO THE SATISFACTION OF THE CITY OF
- 9. THE CITY WILL BE NOTIFIED IF ANY TREES CANNOT BE LOCATED OR PLANTED DUE TO CONFLICTS WITH UTILITIES OR DRIVEWAYS. THE REQUIRED TREES NOT PLANTED ARE SUBJECT TO TREE BANKING. THE FINAL NUMBER OF TREES TO BE BANKED WILL BE PROVIDED TO THE CITY FOLLOWING ALL PLANTINGS (REFERS TO ROW TREES ONLY).
- 10. ALL PLANT MATERIAL SHALL BE WARRANTIED FOR TWO YEARS FROM THE DATE OF PERFORMANCE ACCEPTANCE AS DETERMINED BY THE CITY OF OTTAWA.
- 11. PERIODIC REVIEWS OF PLANTING SHALL BE CARRIED OUT BY THE LANDSCAPE ARCHITECT.
- 12. PLANTINGS TO BE STAKED FOR APPROVAL PRIOR TO CONSTRUCTION
- 13. CITY GRASS CUTTING RESPONSIBILITIES FOR SODDED AREAS SHALL BEGIN FOLLOWING PERFORMANCE ACCEPTANCE INSPECTION BY THE LANDSCAPE ARCHITECT AND THE CITY. ACCEPTANCE WILL BE PROVIDED ONLY IF: - SOD IS PROPERLY ESTABLISHED.
 - TURF IS FREE OF DEAD SPOTS AND WEEDS. - SODDED AREAS HAVE BEEN CUT WITHIN 24 HOURS PRIOR TO ACCEPTANCE INSPECTION.
 - MINIMUM OF 3 WEEKS HAVE ELAPSED FOLLOWING LAYING OF SOD. - A MINIMUM OF TWO CUTS HAVE TAKEN PLACE.
- SODDED AREAS HAVE BEEN TOP-DRESSED, SEEDED AND AERATED *NOTE REFERS ONLY TO ROW SODDING
- 14. STREET TREE PLANTING GUIDELINE NOTE: APPROVED CROSS SECTIONS SHALL TAKE PRECEDENCE
 - 4.5m STREET LIGHT 2.5m - STREET LIGHT (SMALL TREE <7m MATURE HT.)
 - 3.0m HYDRO TRANSFORMER 1.5m - PATH, DRIVEWAY, FENCE, SOUND WALL
 - 4.5m CONIFERS MINIMUM SETBACK FROM CURB
 - 2.5m FIRE HYDRANTS 1.5m - WATER SERVICE / CURB STOP
 - 1.0m BELL / CABLE PEDESTALS

TREE PLANTING IN MARINE CLAY SOILS

- 1. THIS LANDSCAPE PLAN CONFORMS WITH THE TREE-TO-FOUNDATION SETBACK, SOIL VOLUME, AND SURFACE-GRADING REQUIREMENTS OUTLINED IN THE CITY OF OTTAWA'S GUIDELINES FOR TREE PLANTING IN SENSITIVE MARINE CLAY SOILS (2017), BASED ON THE FINDINGS OUTLINED IN THE PROJECT GEOTECHNICAL REPORT.
- 2. ADDITIONAL REQUIREMENTS OUTLINED IN THE CITY OF OTTAWA'S <u>GUIDELINES FOR TREE PLANTING IN SENSITIVE MARINE CLAY SOILS</u> (2017), INCLUDING USF DEPTH, FOUNDATION WALL REINFORCEMENT, AND SUBDIVISION GRADING, SHOULD BE CONFIRMED BY THE PROJECT ENGINEER(S).
- 3. THE CONTRACTOR SHOULD REPORT ANY DISCREPANCIES TO THE CONTRACT ADMINISTRATOR BEFORE PLANTING TREES.
- 4. <u>CITY OF OTTAWA: GUIDELINES FOR TREE PLANTING IN SENSITIVE MARINE CLAY SOILS (2017):</u> THE FOLLOWING GUIDELINES ARE PRIMARILY FOCUSED ON SMALL AND MEDIUM SIZE STREET TREES. HOWEVER, LARGE TREES (MATURE HEIGHT OVER 14M) CAN STILL BE PLANTED IN AREAS OF SMC SOILS PROVIDED A TREE TO FOUNDATION SETBACK EQUAL TO THE FULL MATURE HEIGHT OF THE TREE CAN BE PROVIDED (E.G. IN A PARK OR OTHER GREEN SPACE). FOR STREET TREES IN THE ROAD RIGHT-OF-WAY WHERE SMC SOILS HAVE BEEN IDENTIFIED, THE TREE TO FOUNDATION SETBACKS MAY BE REDUCED TO 4.5M FOR SMALL (MATURE TREE HEIGHT UP TO 7.5M) AND MEDIUM SIZE TREES (MATURE TREE HEIGHT 7.5M-14M) PROVIDED ALL OF THE FOLLOWING SIX CONDITIONS ARE MET:
- 1. THE MODIFIED PLASTICITY INDEX OF THE SOIL BETWEEN THE UNDERSIDE OF FOOTING (USF) AND A DEPTH OF 3.5M GENERALLY DOES NOT EXCEED 40%. THIS CORRESPONDS TO SOILS WITH LOW/MEDIUM POTENTIAL FOR SOIL VOLUME CHANGE. CLAY SOILS THAT EXCEED THE 40% PLASTICITY INDEX ARE CONSIDERED TO HAVE HIGH POTENTIAL FOR SOIL VOLUME CHANGE. FOR THESE WORST-CASE SOILS, THE SETBACKS AND TREE PLANTING RESTRICTIONS REMAIN UNCHANGED FROM THE 2005 CLAY SOILS POLICY (TREE SETBACK MUST EQUAL THE MATURE HEIGHT OF THE TREE - I.E. 7.5M SETBACK FOR SMALL TREES).
- 2. THE USF IS 2.1M OR GREATER BELOW THE LOWEST FINISHED GRADE. NOTE: THIS FOOTING LEVEL MUST BE SATISFIED FOR FOOTINGS WITHIN 10M OF THE TREE, AS MEASURED FROM THE CENTRE OF THE TREE TRUNK, AND VERIFIED BY MEANS OF THE GRADING PLAN AS INDICATED IN THE PROCEDURAL CHANGES BELOW.
- 3. A SMALL SIZE TREE MUST BE PROVIDED WITH A MINIMUM OF 25M3 OF AVAILABLE SOIL VOLUME, AS DETERMINED BY A LANDSCAPE ARCHITECT. A MEDIUM SIZE TREE MUST BE PROVIDED WITH A MINIMUM OF 30M3 OF AVAILABLE SOIL VOLUME, AS DETERMINED BY A LANDSCAPE ARCHITECT. THE DEVELOPER WILL ENSURE THE SOIL IS GENERALLY UNCOMPACTED WHEN BACKFILLING IN STREET TREE
- NOTE: THE SOIL VOLUME CALCULATION MUST BE BASED ON A DEPTH OF 1.5M BELOW FINISHED GRADE (E.G. 5M LENGTH X 4M WIDTH AT SURFACE X 1.5M DEPTH = 30M3). IT MAY INCLUDE LANDS IN THE RIGHT-OF-WAY AND ON PRIVATE PROPERTY, BUT MUST SUBTRACT THE VOLUME OF SHALLOW UTILITY TRENCHES (I.E. VOLUME OF SHALLOW UTILITY TRENCHES CANNOT COUNT TOWARDS

CAL/HT. ROOT

B&B

1 GAL. PT

B&B

0.4 1

- 4. THE TREE SPECIES MUST BE SMALL TO MEDIUM SIZE, AS CONFIRMED BY A LANDSCAPE ARCHITECT IN THE LANDSCAPE PLAN. 5. THE FOUNDATION WALLS ARE TO BE REINFORCED AT LEAST NOMINALLY (MINIMUM OF TWO UPPER AND TWO LOWER 15M BARS IN
- THE FOUNDATION WALL) TO PROVIDE DUCTILITY AS DESCRIBED IN THE GEOTECHNICAL REPORT. 6. GRADING SURROUNDING THE TREE MUST PROMOTE DRAINING TO THE TREE ROOT ZONE (IN SUCH A MANNER AS NOT TO BE

COMMON NAME

DETRIMENTAL TO THE TREE), AS NOTED ON THE SUBDIVISION GRADING PLAN.

PLANT LIST A - ROW STREET TREES KEY QTY. BOTANICAL NAME

PLANT LIST C - AMENITY AREA PLANTING

CORNUS SERICEA 'KELSEYI'

SCHIZACHYRIUM SCOPARIUM

HYDRANGEA PANICULATA 'GRANDIFLORA'

BOTANICAL NAME

AMELANCHIER LAEVIS

				(mm)		_	
		UOUS STREET TREES (6-8m)					
AC	2	AMELANCHIER CANADENSIS	SERVICEBERRY	70	B&B		
MEDI	UM DECI	DUOUS TREES (10-15m)					
CO	7	CELTIS OCCIDENTALIS	HACKBERRY	70	B&B		
PC	9	PYRUS CALLERYANA	ORNAMENTAL PEAR	70	B&B		
SR	5	SYRINGA RETICULATA	JAPANESE LILAC	70	B&B		
TM	5	TILIA MONGOLICA	MONGOLIAN LINDEN	70	B&B		
PLA	'NT LIS	T B - BLOCK 4 PLANTING					
KEY	QTY.	BOTANICAL NAME	COMMON NAME	CAL/HT.	ROOT	SPREAD((m) HEIGHT(m
				(mm)			
MEDI	UM DECI	DUOUS TREES (10-15m)		, ,			
SR	1	SYRINGA RETICULATA	JAPANESE LILAC	70	B&B		
TM	3	TILIA MONGOLICA	MONGOLIAN LINDEN	70	B&B		
		UOUS TREES					
AR	2	ACER RUBRUM	RED MAPLE	70	B&B		
TREE	form sh	IRUBS					
Al	25	AMELANCHIER LAEVIS	ALLEGHENY SERVICEBERRY	40	B&B	6	6
Ea	14	EUONYMUS ALATUS	BURNING BUSH	125cm	TOPGRAF	T 6	10
Hg	23	HYDRANGEA PANICULATA 'GRANDIFLORA'	PEE GEE HYDRANGEA	40	B&B	5	8
DECII	DUOUS SI	HRUBS					
Cf	88	CORNUS SERICEA 'FARROW'	ARCTIC FIRE DOGWOOD		3 GAL.		
Ef	64	EUONYMUS ALATUS 'FIREBALL'	FIREBALL BURNING BUSH		3 GAL.		
Fo	56	FORSYTHIA OVATA 'NORTHERN GOLD'	NORTHERN GOLD FORSYTHIA		3 GAL.		
Sm	56	SYRINGA MEYERI 'PALIBIN'	DWARF KOREAN LILAC		3 GAL.		
CON	IFEROUS :	SHRUBS					
Ja	60	JUNIPERUS SABINA	Sabina Juniper		3 GAL.		
Js	32	JUNIPERUS SCOPULORUM 'SKYROCKET'	SKYROCKET JUNIPER	200cm	WB.		
GRAS	SSES						
ca	399	CALAMAGROSTIS ACUTIFLORA 'LIGHTNING STRIKE"	VARIEGATED FEATHER REED GRASS		1 GAL.		
mg	225	MISCANTHUS SINENSIS 'HURON BLUSH'	HURON BLUSH MAIDEN GRASS		1 GAL.		

COMMON NAME

LITTLE BLUESTEM

CITY FILE NUMBER D07-16-19-0015


ALLEGHENY SERVICEBERRY

KELSEY RED OSIER DOGWOOD


PEE GEE HYDRANGEA

	SITE INFORMATION
SITE PLAN	PROVIDED BY KORSIAK URBAN PLANNING DATED MARCH 19, 2020
COMPOSITE UTILITY PLAN	CUP PROVIDED BY STANTEC/PROJ. NO. 160401085/DATED APRIL 2020
GEOTECHNICAL STUDY	GEOTECHNICAL INVESTIGATION REPORT PROPOSED RESIDENTIAL DEVELOPMENT 3288 GREENBANK ROAD BY PATERSON GROUP.REPORT NO.PG2743-2 DATED MARCH 6, 2019

Contractor shall check all dimensions on the work and report any discrepancy to the Landscape Architect before proceeding. All drawings and specifications are the property of the Landscape Architect and must be returned at the completion of the work. This drawing is not to be used for construction until signed by the Landscape Architect.



	PROPERTY LINE
	LIMIT OF WORK
FENCING	
	GARBAGE ENCLOSURE GATE
	2.0M HIGH OPAQUE SCREEN
PLANTING	
	LARGE DECIDUOUS TREE (>14m)
2	MEDIUM DECIDUOUS TREE (<14m)
$\left(\bigcirc_{3}\right)$	ORNAMENTAL / SMALL TREE (<7m)
() ₄	SHRUB (TREE FORM)
	DECIDUOUS SHRUB
8	CONIFEROUS SHRUB
⊙	ORNAMENTAL GRASSES
	SODDING
SURFACING	
	CONCRETE SIDEWALK
	ASPHALT PAVING
	CONCRETE PAVING
	UNIT PAVING - WALKWAYS
	UNIT PAVING - MULTI-USE PATHWAY - DRIVEWAY BAND
SITE FURNISHINGS	S
	BIKE RACK
	BENCH
	PLANTER
DETAIL KEY	
	— DETAIL NO.
DI ANTINIO KEV	— SHEET NO.
PLANTING KEY	DEE (DECIE) AVA CLIDITO CDECIEC
('' '' '	REE SPECIES XX SHRUB SPECIES UANTITY 4 QUANTITY
	








design strategies 1285 WELLINGTON STREET WEST, OTTAWA, ON K1Y 3A8 CANADA T 613.237.2345 F 613.237.6423 NAKDESIGNSTRATEGIES.COM


BLOCK 4 SOUTH NEPEAN TOWN CENTRE

LANDSCAPE PLAN

Date Apr 2020 Scale 1:250 Drawn TM Checked DE, JH Job No. 19-282

#19282





AMENITY AREA

ACER RUBRUM AND CELTIS OCCIDENTALIS TO BE SPRING DUG SPECIMENS AND PLANTED IN THE SPRING ONLY.

- 2. THE LOCATION OF THE TREES SHOWN ON THIS PLAN IS APPROXIMATE AND SHALL NOT BE SCALED FROM THIS DRAWING. THIS PLAN MUST BE READ IN CONJUNCTION WITH THE APPROVED CUP AND CITY CROSS SECTIONS.
- 3. CONTRACTOR SHALL ENSURE THAT ALL UTILITY LOCATIONS ARE OBTAINED PRIOR TO ANY EXCAVATION FOR
- 4. LOCATION OF ALL PLANT MATERIALS TO BE STAKED BY THE CONTRACTOR AND VERIFIED IN THE FIELD BY LANDSCAPE
- ARCHITECT & CITY OF OTTAWA PRIOR TO THE EXCAVATION OF PITS.
- 5. ALL PLANT MATERIAL SHALL BE NURSERY GROWN STOCK UNLESS OTHERWISE NOTED.
- 6. TREES TO HAVE A MINIMUM 1800 CLEAR STEM ABOVE GRADE.
- 7. PLACE SOD ON A MINIMUM 150mm TOPSOIL.
- 8. CONTRACTOR TO MAKE GOOD ALL EXISTING AREAS DAMAGED BY HIS WORK TO THE SATISFACTION OF THE CITY OF
- 9. THE CITY WILL BE NOTIFIED IF ANY TREES CANNOT BE LOCATED OR PLANTED DUE TO CONFLICTS WITH UTILITIES OR DRIVEWAYS. THE REQUIRED TREES NOT PLANTED ARE SUBJECT TO TREE BANKING. THE FINAL NUMBER OF TREES TO BE BANKED WILL BE PROVIDED TO THE CITY FOLLOWING ALL PLANTINGS (REFERS TO ROW TREES ONLY).
- 10. ALL PLANT MATERIAL SHALL BE WARRANTIED FOR TWO YEARS FROM THE DATE OF PERFORMANCE ACCEPTANCE AS DETERMINED BY THE CITY OF OTTAWA.
- 11. PERIODIC REVIEWS OF PLANTING SHALL BE CARRIED OUT BY THE LANDSCAPE ARCHITECT.
- 12. PLANTINGS TO BE STAKED FOR APPROVAL PRIOR TO CONSTRUCTION
- 13. CITY GRASS CUTTING RESPONSIBILITIES FOR SODDED AREAS SHALL BEGIN FOLLOWING PERFORMANCE ACCEPTANCE INSPECTION BY THE LANDSCAPE ARCHITECT AND THE CITY. ACCEPTANCE WILL BE PROVIDED ONLY IF: - SOD IS PROPERLY ESTABLISHED.
- TURF IS FREE OF DEAD SPOTS AND WEEDS. - SODDED AREAS HAVE BEEN CUT WITHIN 24 HOURS PRIOR TO ACCEPTANCE INSPECTION.
- MINIMUM OF 3 WEEKS HAVE ELAPSED FOLLOWING LAYING OF SOD. - A MINIMUM OF TWO CUTS HAVE TAKEN PLACE.
- SODDED AREAS HAVE BEEN TOP-DRESSED, SEEDED AND AERATED *NOTE REFERS ONLY TO ROW SODDING
- 14. STREET TREE PLANTING GUIDELINE NOTE: APPROVED CROSS SECTIONS SHALL TAKE PRECEDENCE
 - 4.5m STREET LIGHT 2.5m - STREET LIGHT (SMALL TREE <7m MATURE HT.)
 - 3.0m HYDRO TRANSFORMER 1.5m - PATH, DRIVEWAY, FENCE, SOUND WALL
 - 4.5m CONIFERS MINIMUM SETBACK FROM CURB
 - 2.5m FIRE HYDRANTS 1.5m - WATER SERVICE / CURB STOP
 - 1.0m BELL / CABLE PEDESTALS
- TREE PLANTING IN MARINE CLAY SOILS
- 1. THIS LANDSCAPE PLAN CONFORMS WITH THE TREE-TO-FOUNDATION SETBACK, SOIL VOLUME, AND SURFACE-GRADING REQUIREMENTS OUTLINED IN THE CITY OF OTTAWA'S GUIDELINES FOR TREE PLANTING IN SENSITIVE MARINE CLAY SOILS (2017), BASED ON THE FINDINGS OUTLINED IN THE PROJECT GEOTECHNICAL REPORT.
- 2. ADDITIONAL REQUIREMENTS OUTLINED IN THE CITY OF OTTAWA'S GUIDELINES FOR TREE PLANTING IN SENSITIVE MARINE CLAY SOILS (2017), INCLUDING USF DEPTH, FOUNDATION WALL REINFORCEMENT, AND SUBDIVISION GRADING, SHOULD BE CONFIRMED BY THE PROJECT ENGINEER(S).
- 3. THE CONTRACTOR SHOULD REPORT ANY DISCREPANCIES TO THE CONTRACT ADMINISTRATOR BEFORE PLANTING TREES.
- 4. CITY OF OTTAWA: GUIDELINES FOR TREE PLANTING IN SENSITIVE MARINE CLAY SOILS (2017): THE FOLLOWING GUIDELINES ARE PRIMARILY FOCUSED ON SMALL AND MEDIUM SIZE STREET TREES. HOWEVER, LARGE TREES (MATURE HEIGHT OVER 14M) CAN STILL BE PLANTED IN AREAS OF SMC SOILS PROVIDED A TREE TO FOUNDATION SETBACK EQUAL TO THE FULL MATURE HEIGHT OF THE TREE CAN BE PROVIDED (E.G. IN A PARK OR OTHER GREEN SPACE). FOR STREET TREES IN THE ROAD RIGHT-OF-WAY WHERE SMC SOILS HAVE BEEN IDENTIFIED, THE TREE TO FOUNDATION SETBACKS MAY BE REDUCED TO 4.5M FOR SMALL (MATURE TREE HEIGHT UP TO 7.5M) AND MEDIUM SIZE TREES (MATURE TREE HEIGHT 7.5M-14M) PROVIDED ALL OF THE FOLLOWING SIX CONDITIONS ARE MET:
- . THE MODIFIED PLASTICITY INDEX OF THE SOIL BETWEEN THE UNDERSIDE OF FOOTING (USF) AND A DEPTH OF 3.5M GENERALLY DOES NOT EXCEED 40%. THIS CORRESPONDS TO SOILS WITH LOW/MEDIUM POTENTIAL FOR SOIL VOLUME CHANGE. CLAY SOILS THAT EXCEED THE 40% PLASTICITY INDEX ARE CONSIDERED TO HAVE HIGH POTENTIAL FOR SOIL VOLUME CHANGE. FOR THESE WORST-CASE SOILS, THE SETBACKS AND TREE PLANTING RESTRICTIONS REMAIN UNCHANGED FROM THE 2005 CLAY SOILS POLICY (TREE SETBACK MUST EQUAL THE MATURE HEIGHT OF THE TREE - I.E. 7.5M SETBACK FOR SMALL TREES).
- 2. THE USF IS 2.1M OR GREATER BELOW THE LOWEST FINISHED GRADE. NOTE: THIS FOOTING LEVEL MUST BE SATISFIED FOR FOOTINGS WITHIN 10M OF THE TREE, AS MEASURED FROM THE CENTRE OF THE TREE TRUNK, AND VERIFIED BY MEANS OF THE GRADING PLAN AS INDICATED IN THE PROCEDURAL CHANGES BELOW.
- 3. A SMALL SIZE TREE MUST BE PROVIDED WITH A MINIMUM OF 25M3 OF AVAILABLE SOIL VOLUME, AS DETERMINED BY A LANDSCAPE ARCHITECT. A MEDIUM SIZE TREE MUST BE PROVIDED WITH A MINIMUM OF 30M3 OF AVAILABLE SOIL VOLUME, AS DETERMINED BY A LANDSCAPE ARCHITECT. THE DEVELOPER WILL ENSURE THE SOIL IS GENERALLY UNCOMPACTED WHEN BACKFILLING IN STREET TREE PLANTING LOCATIONS. NOTE: THE SOIL VOLUME CALCULATION MUST BE BASED ON A DEPTH OF 1.5M BELOW FINISHED GRADE (E.G. 5M LENGTH X
- 4M WIDTH AT SURFACE X 1.5M DEPTH = 30M3). IT MAY INCLUDE LANDS IN THE RIGHT-OF-WAY AND ON PRIVATE PROPERTY, BUT MUST SUBTRACT THE VOLUME OF SHALLOW UTILITY TRENCHES (I.E. VOLUME OF SHALLOW UTILITY TRENCHES CANNOT COUNT TOWARDS MINIMUM SOIL VOLUME).
- 4. THE TREE SPECIES MUST BE SMALL TO MEDIUM SIZE, AS CONFIRMED BY A LANDSCAPE ARCHITECT IN THE LANDSCAPE PLAN. 5. THE FOUNDATION WALLS ARE TO BE REINFORCED AT LEAST NOMINALLY (MINIMUM OF TWO UPPER AND TWO LOWER 15M BARS IN THE FOUNDATION WALL) TO PROVIDE DUCTILITY AS DESCRIBED IN THE GEOTECHNICAL REPORT. 6. GRADING SURROUNDING THE TREE MUST PROMOTE DRAINING TO THE TREE ROOT ZONE (IN SUCH A MANNER AS NOT TO BE DETRIMENTAL TO THE TREE), AS NOTED ON THE SUBDIVISION GRADING PLAN.


KEY	QTY.	BOTANICAL NAME	COMMON NAME	CAL/HT.	ROOT	
				(mm)		_
SMAL	L DECIDU	JOUS STREET TREES (6-8m)				
AC	2	AMELANCHIER CANADENSIS	SERVICEBERRY	70	B&B	
MEDI	UM DECII	DUOUS TREES (10-15m)				
CO	7	CELTIS OCCIDENTALIS	HACKBERRY	70	B&B	
PC	9	PYRUS CALLERYANA	ORNAMENTAL PEAR	70	B&B	
SR	5	SYRINGA RETICULATA	JAPANESE LILAC	70	B&B	
TM	5	TILIA MONGOLICA	MONGOLIAN LINDEN	70	B&B	
	NIT LICT					
PLA	1/1 FI2	TB-BLOCK 4 PLANTING				
KEY	QTY.	BOTANICAL NAME	COMMON NAME	CAL/HT.	ROOT	SPREAD(m) HEIGHT(m)
				(mm)		
	UM DECII	DUOUS TREES (10-15m)				
MEDI		SYRINGA RETICULATA	JAPANESE LILAC	70	B&B	
<u>medi</u> Sr	I	STRINGA RELICULATA	37 (1 7 (1 1202 212) (3			


KEY	QTY.	BOTANICAL NAME	COMMON NAME	CAL/HT.	ROOT	SPREAD(m) H
				(mm)			
MEDI	UM DECI	DUOUS TREES (10-15m)					
SR	1	SYRINGA RETICULATA	JAPANESE LILAC	70	B&B		
TM	3	TILIA MONGOLICA	MONGOLIAN LINDEN	70	B&B		
LARG	E DECID	UOUS TREES					
AR	2	ACER RUBRUM	RED MAPLE	70	B&B		
TREE I	form sh	IRUBS					
Al	25	AMELANCHIER LAEVIS	ALLEGHENY SERVICEBERRY	40	B&B	6	6
Ea	14	EUONYMUS ALATUS	BURNING BUSH	125cm	TOPGRAF1	6	10
Hg	23	HYDRANGEA PANICULATA 'GRANDIFLORA'	PEE GEE HYDRANGEA	40	B&B	5	8
DECIE	DUOUS SI	HRUBS					
Cf	88	CORNUS SERICEA 'FARROW'	ARCTIC FIRE DOGWOOD		3 GAL.		
Ef	64	EUONYMUS ALATUS 'FIREBALL'	FIREBALL BURNING BUSH		3 GAL.		
Fo	56	FORSYTHIA OVATA 'NORTHERN GOLD'	NORTHERN GOLD FORSYTHIA		3 GAL.		
Sm	56	SYRINGA MEYERI 'PALIBIN'	DWARF KOREAN LILAC		3 GAL.		
CONI	IFEROUS :	SHRUBS					
Ja	60	JUNIPERUS SABINA	SABINA JUNIPER		3 GAL.		
Js	32	JUNIPERUS SCOPULORUM 'SKYROCKET'	SKYROCKET JUNIPER	200cm	WB.		

GRAS:	SES							
ca	399	CALAMAGROSTIS ACUTIFLORA 'LIGHTNING STRIKE'	VARIEGATED FEATHER REED GRASS		1 GAL.			
mg	225	MISCANTHUS SINENSIS 'HURON BLUSH'	HURON BLUSH MAIDEN GRASS		1 GAL.			
PLAI	nt list	C - AMENITY AREA PLANTING						
KEY	QTY.	BOTANICAL NAME	COMMON NAME	CAL	ROOT	SPREAD(m)	HEIGHT(m)	
				(mm)				
TREE F	ORM SHE	RUBS						
Al	7	AMELANCHIER LAEVIS	ALLEGHENY SERVICEBERRY	40	B&B	6	6	
Hg	7	HYDRANGEA PANICULATA 'GRANDIFLORA'	PEE GEE HYDRANGEA	40	B&B	5	8	•
DECID	OUS SHR	UBS_						
Cs	12	CORNUS SERICEA 'KELSEYI'	KELSEY RED OSIER DOGWOOD		3 GAL.	0.6	0.6	
GRAS:	<u>SES</u>							•
SZ	20	SCHIZACHYRIUM SCOPARIUM	LITTLE BLUESTEM	1 GAL.	PT	0.4	1	

CITY FILE NUMBER D07-16-19-0015

Contractor shall check all dimensions on the work and report any discrepancy to the Landscape Architect before proceeding. All drawings and specifications are the property of the Landscape Architect and must be returned at the completion of the work. This drawing is not to be used for construction until signed by the Landscape Architect.





-				
-				
1	Issued for First Submission	Apr.21/20		
 No.	Description	Date		
Revision				

1 DETAIL NO.


PLANTING KEY

— SHEET NO.

TREE SPECIES XX SHRUB SPECIES

QUANTITY

4
QUANTITY





1285 WELLINGTON STREET WEST, OTTAWA, ON K1Y 3A8 CANADA T 613.237.2345 F 613.237.6423 NAKDESIGNSTRATEGIES.COM


BLOCK 4 SOUTH NEPEAN TOWN CENTRE


LANDSCAPE PLAN


SITE INFORMATION					
SITE PLAN	PROVIDED BY KORSIAK URBAN PLANNING DATED MARCH 19, 2020				
COMPOSITE UTILITY PLAN	CUP PROVIDED BY STANTEC/PROJ. NO. 160401085/DATED APRIL 2020				
GEOTECHNICAL STUDY	GEOTECHNICAL INVESTIGATION REPORT PROPOSED RESIDENTIAL DEVELOPMENT 3288 GREENBANK ROAD BY PATERSON GROUP.REPORT NO.PG2743-2 DATED MARCH 6, 2019				


			7
e	Apr 2020	Sheet	
ıle	1:250		10
wn	TM	L-02	1 7
ecked	DE, JH		7
No.	19-282		2

#19282










TYPICAL 18.0m ROW





Contractor shall check all dimensions on the work and report any discrepancy to the Landscape Architect before proceeding. All

drawings and specifications are the property of the Landscape Architect and must be returned at the completion of the work. This drawing is not to be used for construction until signed by the



TYPICAL 16.5m ROW N.T.S.





JOCKVALE ROAD SOIL VOLUME





JOCKVALE ROAD



1 Issued for First Submission

No. Description

Revision

	ROW & SO	IL VOLUME
Date	Apr 2020	Sheet
Scale	NTS	D 00

D-02 Drawn TM Checked DE, JH Job No. 19-282

#19282

Date