

5. CONSTRUCTION:
- 5.1 PRIOR TO COMMENCING WORK:
- A. OBTAIN AND PAY FOR ALL NECESSARY PERMITS AND APPROVALS FROM THE AUTHORITIES.
- B. SIZE, DEPTH AND LOCATION OF EXISTING SERVICES, UTILITIES AND STRUCTURES AS SHOWN ON DRAWINGS AND FIELD SURVEY SHALL BE ALL EXISTING SERVICES, UTILITIES AND STRUCTURES. NOT NECESSARILY SHOWN ON THE DRAWINGS. COMPLETENESS AND ACCURACY ARE NOT GUARANTEED. NOTIFY ALL APPLICABLE OWNERS, UTILITY COMPANIES AND AUTHORITIES PRIOR TO ANY REMOVAL OF PROPOSED WORK AND LOCATE AND CLEARLY IDENTIFY ALL EXISTING SERVICES, UTILITIES AND STRUCTURES ON AND ADJACENT TO THE SITE. UNDERGROUND LOCATES INCLUDING ONTARIO ONE CALL: 1-800-400-2250) SHALL BE CONDUCTED PRIOR TO THE START OF ANY EXCAVATION. CONTRAST LOCATIONS OF ALL EXISTING SERVICES AND UTILITIES BY CAREFUL TEST EXCAVATIONS AND REPORT ANY DIFFERENCES TO THE ENGINEER.


- VOLUME OF WATER. THE UNDOILED MATERIAL SHALL BE ACCORDING TO OPSS 1103.
- 6.1.1 SHAPE BONE TO SMOOTH CONTOUR AND COMPACT TO NOT LESS THAN 100% CORRECTED MAXIMUM DRY DENSITY BEFORE BEGINNING PAVING OPERATIONS.
- 6.1.2 ASPHALTIC CONCRETE ONLY WHEN BASE OR PREVIOUS COURSE IS DRY AND AIR TEMPERATURE IS ABOVE 5 DEGC.
- 6.1.3 ROLL UNTIL ROLLER MARKS ARE ELIMINATED AND COMPACTED TO NOT LESS THAN 95% OF THE THEORETICAL MAXIMUM DRY DENSITY IN AREAS INACCESSIBLE TO A ROLLER. REVEAL DEGS ADJACENT TO GRANULAR SURFACES.
- 6.1.4 FINISH SURFACE SMOOTH, TRUE TO GRADE.
- 6.1.5 KEEP VEHICULAR TRAFFIC AND OTHER LOADS OFF NEWLY PAVED AREAS UNTIL 24 HOURS AFTER PAVING.
- 6.1.6 DIRT UNWENT AND WASTE MATERIAL TO A FACILITY APPROVED FOR ACCEPTING SUCH MATERIALS.

- | | | | | | | |
|------|-------|-------------------------------|---|----------|----------|--|
| | | | MANHOLE | | | INSTALL 10 |
| MH+7 | 93.38 | SOLENO
AQUA-CORRIL
AS-2 | OIL & GRIT
SEPARATOR (OGS)
HDPE MANHOLE | 90.77(E) | 90.77(W) | |
| CB-8 | 92.60 | 600 x 600mm | PRE-CAST
CONCRETE
CATCH-BASIN | - | 90.35 | TO GPSD
CITY
FRA
CITY
INSTALL 11 |
| | | OGS ENO | OIL & GRIT | | | |

- SECTION 'A-A'

-

-

- | | | |
|---|-------------|-------------|
| Seal | Drawn | D.B.G. |
|  | Hor. Scale | |
| | Vert. Scale | |
| | Date | APR 22-2010 |
| | Job No. | 19022 |
| | Drawing No. | |