


PROFILE VIEW (WALL 1)

SCALE 1:100




Block count:

Corner Unit (interfaced).....	2	Dual face unit.....	3
6-44 top block.....	15	Corner end unit.....	17
3-44 top block.....	3	6-28 top block.....	7
6-44 block.....	42	3-28 block.....	2
3-44 block.....	31	6-28 block.....	9
24-44 block.....	15	90° Column Unit.....	38
24-86 block.....	9		
24-62 block.....	13		

PROFILE VIEW (WALL 2)

SCALE 1:100



NOTES:


- THE CONTRACTOR IS SOLELY RESPONSIBLE FOR UTILITY CLEARANCE AND CONSTRUCTION SITE SAFETY. MCON PRODUCTS INC. AND PATERSON GROUP SHALL NOT BE RESPONSIBLE FOR MEANS OR METHODS OF CONSTRUCTION OR FOR SAFETY OF WORKERS OR OF THE PUBLIC.
- THIS DESIGN IS BASED ON THE FOLLOWING SOIL PROPERTIES:

PROPERTY	RETAINED FILL	FOUNDATION MEDIUM
FRICITION ANGLE - PHI	33	33
UNIT WEIGHT	21 KN/m ³	19 KN/m ³
COHESION - C	0	5 kPa
SOIL TYPE	GRANULAR B TYPE II & NATIVE FILL	STIFF SILTY CLAY
- MATERIAL PROPERTIES ARE BASED ON SITE EVALUATION BY THE PATERSON GROUP. SEISMIC LOADING WAS EVALUATED ACCORDING TO THE ONTARIO BUILDING CODE 2012 WITH A PEAK GROUND ACCELERATION VALUE OF 0.32. NO SURCHARGE LOAD IS APPLICABLE FOR THIS WALL.
- THE WALL BASE DESIGN ASSUMES A BEARING RESISTANCE AT SLS OF 150 kPa. THE SITE GEOTECHNICAL ENGINEER SHOULD OBSERVE THE BEARING CONDITIONS AND ADJUST THE THICKNESS OF THE GRANULAR BASE OR RECOMMEND CONCRETE BEDDING TO ACCOMMODATE THE SITE CONDITIONS, IF NECESSARY.
- THE DESIGN IS FOR STABILITY OF THE PRECAST MODULAR RETAINING WALL SYSTEM ONLY. SITE STABILITY (GLOBAL STABILITY) IS THE RESPONSIBILITY OF THE SITE GEOTECHNICAL ENGINEER. WALL GEOMETRY AND GRADE ELEVATIONS ABOVE AND BELOW THE WALL SHOULD CONFORM WITH THE GRADING PLAN PROVIDED HERE IN IF ACTUAL SITE GRADES VARY SIGNIFICANTLY FROM THOSE SHOWN ON THE GRADING PLAN REV. A.
- THE RETAINING WALL DESIGN WAS BASED ON OUR UNDERSTANDING AND REVIEW OF THE PROPOSED SOLDER PILE AND LAGGING SHORING SYSTEM TO BE PLACED BEHIND THE RETAINING WALL ADJACENT TO THE PROPOSED BUILDING. THE SHORING SYSTEM (PERMANENT) SHOULD BE DESIGNED TO HANDLE THE LOAD APPLIED BY THE PROPOSED PARKING AREA. OTHERWISE, THE RETAINING WALL WILL REQUIRE LIGHT WEIGHT FILL TO BE PLACED WITHIN THE BACKFILL TO REDUCE THE SURCHARGE LOAD ON THE RETAINING WALL AND ENSURE ITS STABILITY.
- HORIZONTAL LAYOUT DIMENSIONS ARE MEASURED ALONG THE FACE OF THE WALL, CORRESPONDING TO A HORIZONTAL REFERENCE ESTABLISHED BY PATERSON GROUP BASED ON DRAWINGS BY STANTEC, PROJECT NO. 100124, 100124 INDUSTRIAL AVENUE, 244 FOUNTAIN PLACE, GRANVILLE, ONTARIO.
- PRECAST UNITS SHALL BE STONE STRONG RETAINING WALL UNITS MANUFACTURED UNDER LICENSE FROM STONE STRONG SYSTEMS. UNITS SHALL HAVE A MOLDED GRANITE FACE. THE BLOCKS MAY BE STAINED IN PLACE TO ACHIEVE THE DESIRED COLOR.
- THE WALL BASE SHALL CONSIST OF A MINIMUM OF 300 TO 1000mm OF OPSS GRANULAR A OR GRANULAR B TYPE II BASE. THE BASE SHALL BE COMPACTED AS TO PROVIDE A LEVEL AND HARD SURFACE ON WHICH TO PLACE THE FIRST COURSE OF UNITS. GRANULAR BASE MATERIAL SHALL BE COMPACTED TO A MINIMUM 98% OF STANDARD PROCTOR MAXIMUM DENSITY (SPMDD) WHERE THE WALL HEIGHT IS 3.7m. A REINFORCED GRANULAR PAD WRAPPED IN GEOTRAX (TERRAFIX TBX 3500 OR EQUIV.) WITH A 100mm OVERLAP WILL BE REQUIRED. THE BASE SHALL BE SMOOTHED TO ENSURE CONTACT OF THE RETAINING WALL UNIT WITH THE SURFACE OF GRANULAR BASE. THE BASE MAY BE DRESSED WITH FINER AGGREGATE TO AID LEVELING. ENSURE GRADATION OF DRESSING MATERIAL IS 3 TIMES THE MAXIMUM PARTICLE SIZE USED. THE CONTRACTOR MAY SUBSTITUTE CONCRETE WITH A MINIMUM 28-DAY COMPRESSIVE STRENGTH OF 20 MPa AND AIR ENTRAINMENT FOR THE GRANULAR BASE MATERIAL.
- INSTALL 100mm DIAMETER PERFORATED PIPE DRAIN UNDER LOWER COURSE OF WALL OR ALTERNATIVELY BEHIND HEEL OF WALL PROVIDE CLEAR STONE SURROUNDING THE DRAIN TO PROTECT PIPE FROM CLOGGING AND DAMAGE. PROVIDE OUTLETS THROUGH WALL BASE LAYER AT 15m INTERVALS. NO FURTHER AIR THAN 15m CENTRES.
- WALL IS DESIGNED FOR A MINIMUM OF 200mm TOE EMBEDMENT WITH A MINIMUM HORIZONTAL LEDGE OF 300mm BEYOND THE FACE OF THE BASE BLOCKS WHERE GRANULAR BEDDING WILL NOT BE SUFFICIENT. THE USE OF CONCRETE BEDDING MAY BE REQUIRED. EXTRA PRECAUTIONS MUST BE TAKEN TO PROVIDE TOE EMBEDMENT IN AREAS WHERE BASE OF WALL STEPS.
- THE RETAINING WALL IS A BATTERED WALL. ALIGNMENT OF THE BOTTOM WALL COURSE SHOULD BE PLANNED TO CONSIDER THAT A NOMINAL 100mm AUTOMATIC SETBACK WILL OCCUR WITH EACH 0.9m IN HEIGHT. AS SUCH, THE LOWEST WALL BASE WITHIN A CONTIGUOUS SECTION SHOULD BE WITHIN WALL CORRIDOR, INCLUDING REQUIREMENT FOR BASE EXTENT IN FRONT OF WALL. SIMILARLY, THE FACE OF THE HIGHEST WALL (TW LEVEL) WITHIN THE SECTION SHOULD ALSO BE AT LEAST WITHIN 0.5m WITHIN THE WALL CORRIDOR (OR AS REQUIRED BY OWNER).
- UNIT FILL SHALL BE A CLEAN, COARSE GRANULAR MATERIAL. UNIT FILL SHALL BE 19mm Ø CLEAR STONE MEETING THE SATISFACTION OF THE GEOTECHNICAL ENGINEER. UNIT FILL SHALL FILL CAVITIES WITHIN AND BETWEEN THE UNITS AND MAY EXTEND BEHIND THE FACING UNITS FOR THE CONTRACTOR'S CONVENIENCE.
- BACKFILL MATERIAL SHALL BE APPROVED BY THE SITE GEOTECHNICAL ENGINEER PRIOR TO USE AND SHOULD CONSIST OF OPSS GRANULAR B TYPE II BUFFER OF 1000mm AS SHOWN WITH ALL FILL WITHIN A 1M TV ZONE UP AND BACK FROM THE HEEL SHOULD ALSO BE COMPACTED. BACKFILL SHALL BE PLACED IN MAXIMUM 300mm LOOSE LIFTS AND COMPACTED TO A MINIMUM OF 95% OF THE MATERIAL'S SPMDD. MOISTURE CONTENT SHOULD BE CONTROLLED AND MAINTAINED WITHIN -3 TO +4 PERCENT OF OPTIMUM.
- ENSURE EACH COURSE IS COMPLETELY FILLED AND BACKFILL IS PLACED TO THE SAME LEVEL PRIOR TO PROCEEDING TO THE NEXT COURSE. ENSURE ADJACENT UNITS ARE IN CONTACT SO THAT UNIT FILL MAY NOT ESCAPE THROUGH THE JOINT BETWEEN UNITS. GAPS GREATER THAN 6mm BETWEEN UNITS (AT THE FACE) SHALL NOT BE ALLOWED. AT THE INTERSECTIONS WITH STRUCTURES, CUT UNITS TO OBTAIN A NEAT FIT. FULL BLOCK UNITS FORWARD TO ENGAGE THE ALIGNMENT LOOPS ON THE UNIT BELOW BEFORE INFILLING IN ALL CASES.
- MAINTAIN TEMPORARY GRADES TO DIVERT SURFACE WATER AWAY FROM THE RETAINING WALL EXCAVATION. SLOPE FINAL BACKFILL TO PROVIDE POSITIVE DRAINAGE AND TO ELIMINATE PONDING, WHERE APPLICABLE. THE UPPER COURSE FOR THE RETAINING WALL CONSISTS OF DUAL FACE (DF) BLOCKS WHICH ALLOW FOR THE GRADE BEHIND THE TOP OF THE WALL TO VARY, WHILE PRESENTING A FINISHED REAR WALL FACE.
- IF WINTER CONSTRUCTION IS CONSIDERED, HEAT MUST BE MAINTAINED WHEN THE BASE IS EXPOSED. THE WALL BASE SHALL BE COVERED WITH INSULATION TARP TO MAINTAIN HEAT AND PROTECT THE BASE FROM POTENTIAL FROST HEAVE. ONCE THE BASE IS BACKFILLED, THE TOP OF WALL MUST BE COVERED WITH INSULATION TARPS OVER EACH UNIT UNTIL CONSTRUCTION IS COMPLETED.
- THE GEOTECHNICAL CONSULTANT SHOULD BE NOTIFIED AT THE BEGINNING OF THE WALL CONSTRUCTION TO COMPLETE PERIODIC INSPECTIONS AND PROVIDE GEOTECHNICAL RECOMMENDATIONS AS THE WALL CONSTRUCTION PROGRESSES.
- DURING THE CONSTRUCTION OF THE RETAINING WALL, THE CONTRACTOR MUST ENSURE THAT A SAFE SLOPE IS PROVIDED BEHIND THE RETAINING WALL. PATERSON GROUP SHOULD COMPLETE PERIODIC INSPECTIONS TO ENSURE A PROPER SLOPE IS PROVIDED AS PER THE SITE GEOTECHNICAL RECOMMENDATIONS.
- ANY INADEQUATE PERFORMING SUBGRADE SHOULD BE FULLY EXCAVATED AND REPLACED WITH OPSS GRANULAR B TYPE II COMPACTED TO 98% OF THE MATERIALS SPMDD.
- ANY CUTTING OF BLOCKS TO SUIT SITE CONDITIONS OR WALL DESIGN WILL BE THE RESPONSIBILITY OF THE CONTRACTOR. REMOVAL/CUTTING OF LIFTING LOOPS ON THE FINAL ROW OF BLOCKS WILL BE THE RESPONSIBILITY OF THE CONTRACTOR.

ISSUED FOR REVIEW


CROSS SECTION B-B

SCALE 1:40




CROSS SECTION A-A

SCALE 1:30




GRADING PLAN

SCALE 1:125




CROSS SECTION C-C


SCALE 1:30



90° CORNER DETAILS



90° TIEBACK



paterson group
consulting engineers

154 Colonnade Road South
Ottawa, Ontario K2E 7J5
Tel: (613) 226-7381 Fax: (613) 226-6344

NO.	REVISIONS	DATE	INITIAL
2	REVISED AS PER NEW GRADING AND LAYOUT	12/08/2021	FA
1	REVISED WALL BASED ON GEOTECHNICAL REPORT INFORMATION	21/11/2019	FA

T.C UNITED GROUP
PROPOSED MULTI-STOREY RESIDENTIAL BUILDING
244 FOUNTAIN PLACE
OTTAWA, ONTARIO

Stamp: GEOTECHNICAL / STRUCTURAL PERSPECTIVE
12/08/2021
D. J. GILBERT
160118190
PROVINCE OF ONTARIO

Stamp: GEOTECHNICAL PERSPECTIVE
21/11/2019
E. I. ABU-SUDO
00156744
PROVINCE OF ONTARIO

Title: **STONE STRONG RETAINING WALL DESIGN**

Scale:	AS SHOWN	Report No.:	PG3780
Drawn by:	RCG	Drawing No.:	
Checked by:	FA		
Approved by:	FA		PG3780-3
Date:	08/2021	Revision No.:	2