

## **Findlay Creek #2 Elementary Public School with Daycare**

**820 Miikana Road, Ottawa, Ontario  
SW22240**

**Prepared For**

**Vladimir Popovic  
Partner  
N45 Architecture Inc.  
71 Bank Street, 7th Floor  
Ottawa, ON K1P 5N2  
Tel: 613-224-0095 x224  
[vladimirp@n45.ca](mailto:vladimirp@n45.ca)**

## **NOISE IMPACT STUDY**

**Prepared By**

---

**Surajudeen Adewusi, Ph.D., P.Eng.  
Senior Engineer  
Thornton Tomasetti  
116 Albert Street, Suite 300  
Ottawa, Ontario, K1P 5G3  
Tel: 613 216 1247  
[SAdewusi@ThorntonTomasetti.com](mailto:SAdewusi@ThorntonTomasetti.com)  
[www.ThorntonTomasetti.com](http://www.ThorntonTomasetti.com)**

**Reviewed By**

**Robert Fuller, P.Eng.  
Project Engineer**

**June 15, 2022**

**Table of Contents**

**1.0 Introduction ..... 1**

**2.0 Site..... 1**

**3.0 Noise Sources..... 1**

**4.0 Noise Assessment Criteria..... 2**

4.1 Surface Transportation Noise Assessment Criteria .....2

4.2 Stationary Source Noise Assessment Criteria ..... 3

**5.0 Impact of the Environment on the Project – Surface Transportation Noise..... 3**

5.1 Points of Reception ..... 3

5.2 Road Traffic Noise Parameters.....4

5.3 Estimated Sound Levels at PORs ..... 5

5.4 Discussion of Sound Level at OLAs ..... 6

**6.0 Surrounding Stationary Noise Source..... 7**

**7.0 Impact of the Project on Surrounding Area ..... 7**

7.1 Stationary Noise Sources.....7

7.2 Receptor Locations..... 8

7.3 Stationary Source Noise Level Prediction.....8

**8.0 Concluding Comments ..... 8**

**9.0 References ..... 10**

**Appendix A – Results of STAMSON 5.04 Calculations..... 15**

**Appendix B– Results of STAMSON 5.04 Calculations with Increased Right of Way (ROW) for Miikana Road ..... 22**

**Appendix C1– Results of STAMSON 5.04 Calculations with Outdoor Classroom relocated to 55 m from Kelly Farm Drive ..... 25**

**Appendix C2– Results of STAMSON 5.04 Calculations with 1.5 m Barrier located 20 meters from Outdoor Classroom along Kelly Farm Drive. .... 27**

**Appendix D – Sound Power Level Data for AAON RTUs ..... 29**

**Appendix E – CadnaA Input and Output Information ..... 30**

**List of Tables**

Table 1: Sound Level Limits for Noise-Sensitive Areas – Road Noise .....2

Table 2: ENCG Building Component Requirements (Road Noise – Daytime Only).....2

Table 3: ENCG Ventilation and Warning Clause Requirements (Road noise - Daytime Only).....3

Table 4: ENCG Exclusion Limit Values for Class 1 Areas (New Noise-Sensitive Land Uses in Proximity to Existing Stationary Sources).....3

Table 5: Points of Reception and Outdoor Living Areas .....4

Table 6: ENCG Traffic and Road Parameters for STAMSON Modelling .....4

Table 7: Calculated Sound Levels at PORs .....5

Table 8: Mechanical Noise Sources Associated With School.....8

Table 9: Predicted Stationary Noise Source Levels at the Receptors .....8

**List of Figures**

Figure 1: Site Plan with Point of Reception .....11  
Figure 2: Aerial view of the site and surroundings .....12  
Figure 3: Location of PORs for HVAC stationary noise sources. ....13  
Figure 4: Contour lines for HVAC noise sources on the surroundings.....14

## 1.0 Introduction

At the request of N45 Architecture Inc. (the Client), Thornton Tomasetti (TT) is pleased to present this Noise Impact Study (NIS) for the proposed two-storey Findlay Creek Elementary Public School with Daycare (the Project) to be located at 820 Miikana Road, Ottawa, Ontario. The objective of this study is to assess noise impacts from nearby surface transportation sources, as well as noise impacts from the Project onto nearby noise-sensitive points of reception (residences) to determine if the proposed Project meets the requirements stipulated in the City of Ottawa Environmental Noise Control Guidelines (ENCG) [1].

## 2.0 Site

TT staff visited the site on May 30, 2022. A draft Site Plan of the Project and an aerial photo of the Project surrounding areas are provided in Figure 1 and Figure 2, respectively. Figure 1 shows the Point of Reception (POR) locations. The site area and roads are approximately at the same level as shown in the topography drawing and observed during the site visit. The Project will be in a residential area with split zone site – Minor Institutional Zone (I1) and Residential Fourth Density Zone (R4Z).

The Project is bordered on the north and west by Miikana Road and Kelly Farm Drive respectively. The Project is bordered on the east and south by one- and two-storey residential buildings and a public Park (Salamander Park). The surrounding neighborhood consists of residential land uses.

## 3.0 Noise Sources

The only significant sources of noise impacting the Project are from the adjacent roads: Miikana Road and Kelly Farm Drive.

During the site visit on May 30, 2022, the surrounding areas were observed for any substantial existing stationary noise sources. The only source of noise heard was from tractors working on the internal roads construction for the residential buildings along Kelly Farm Drive opposite to the Project site. This is temporary noise source and will not be considered.

According to the City of Ottawa ENCG, human activities at Public Parks are not considered as stationary noise sources, hence noise from human activities at the Salamander Public Park located at the Project East is not an issue.

The proposed school has Kindergarten Play Area, Outdoor Classroom Area and Sport Field. The activities at these locations will not be considered as sources of noise but the Outdoor Classroom and Kindergarten Play Area will be considered as outdoor points of reception due to the transportation noise sources.

The HVAC system for the Project is a source of stationary noise to the surrounding residential buildings. The impact of the HVAC system on the surrounding area will be assessed. A quiet HVAC systems may be recommended to ensure the noise radiated to the surrounding area is small.

#### 4.0 Noise Assessment Criteria

The City of Ottawa requirements for environmental noise impact assessments are outlined in the ENCG [1], which in turn reference the Environmental Noise Guideline, NPC-300 [2], prepared by the Ontario Ministry of the Environment, Conservation and Parks (MECP). The Project will be located in a Class 1 area, which is defined as “an area with an acoustical environment typical of a major population center, where the background sound level is dominated by the activities of people, usually road traffic, often referred to as “urban hum.”.

The sections below describe the applicable noise assessment criteria for surface transportation noise sources and stationary noise sources.

##### 4.1 Surface Transportation Noise Assessment Criteria

Sound level limits outlined in ENCG for road traffic noise impacting on noise-sensitive areas applicable to the Project are summarized in Table 1. Sound level limits are given in A-weighted, equivalent sound levels ( $L_{eq}$ , dBA). Furthermore, based on the plane-of-window calculations for indoor spaces, upgraded building components, ventilation systems and warning clauses may be required. The ENCG building component and ventilation requirements for road noise applicable to the Project are shown in Tables 2 and 3, respectively. These requirements are based on calculated sound levels at Outdoor Living Areas (OLAs) and the plane-of-window of bedrooms and living/dining rooms.

Table 1: Sound Level Limits for Noise-Sensitive Areas – Road Noise

| Type of Space   | Time Period                | Maximum $L_{eq}$ (dBA) |
|---|----------------------------|------------------------|
| Outdoor Living Area   | Daytime (07:00 to 23:00)   | 55                     |
| Living/dining, den areas of residences, hospitals, schools, etc. (indoor) | Daytime (07:00 to 23:00)   | 45                     |
|   | Nighttime (23:00 to 07:00) | 45                     |
| Sleeping quarters of residences (indoor)                                  | Daytime (07:00 to 23:00)   | 45                     |
|   | Nighttime (23:00 to 07:00) | 40                     |

Table 2: ENCG Building Component Requirements (Road Noise – Daytime Only)

| Assessment Location | Sound Level (time as noted)                        | Building Component Requirements  |
|---------------------|--|--|
| Plane of Window     | Daytime $L_{EQ-16HR}$ Less than or equal to 65 dBA | Building compliant with the Ontario Building Code  |
|                     | Daytime $L_{EQ-16HR}$ Greater than 65 dBA          | Building components (walls, windows, etc.) must be designed to achieve indoor sound level criteria |

Table 3: ENCG Ventilation and Warning Clause Requirements (Road noise - Daytime Only)

| Assessment Location | Sound Level (time as noted)   | Ventilation Requirement  | Warning Clause Requirement |
|---------------------|---|--|----------------------------|
| Plane of Window     | Daytime $L_{EQ-16HR}$ Less than or equal to 55 dBA                        | None required  | Not required               |
|                     | Daytime $L_{EQ-16HR}$ Greater than 55 dBA to less than or equal to 65 dBA | Forced air heating with provision for central air conditioning | Required Type C            |
|                     | Daytime $L_{EQ-16HR}$ Greater than 65 dBA                                 | Central air conditioning is required                           | Required Type D            |

**4.2 Stationary Source Noise Assessment Criteria**

Stationary sources of noise include all sources of sound and vibration that exist or operate on nearby premises, excluding construction noise sources. The noise level criterion for noise from stationary sources in a given time period is the higher value between (1) the time period exclusion limit value prescribed by the MECP, and (2) the corresponding minimum hourly background/ambient sound level ( $L_{eq,1hr}$ ) due to traffic during the time period. Exclusion limit values outlined in the ENCG for new noise-sensitive land uses in proximity to existing stationary noise sources have been summarized in Table 4 for Class 1 areas.

Table 4: ENCG Exclusion Limit Values for Class 1 Areas (New Noise-Sensitive Land Uses in Proximity to Existing Stationary Sources)

| Type of Point of Reception          | Time Period (Description)   | Exclusion Limit - $L_{eq,1hr}$ (dBA) |
|-------------------------------------|-----------------------------|--------------------------------------|
| Outdoor Living Area (OLA)           | 07:00 to 23:00 (Daytime)    | 50                                   |
| Plane of Window (Living Quarters)   | 07:00 to 23:00 (Daytime)    | 50                                   |
| Plane of Window (Sleeping Quarters) | 23:00 to 07:00 (Night-time) | 45                                   |

The exclusion limits outlined in Table 4 apply to both neighboring “off-site” stationary noise sources which may impact the Project, as well as “on-site” stationary noise sources associated with the Project which may impact neighboring noise sensitive land uses (in this case, the neighboring residences).

**5.0 Impact of the Environment on the Project – Surface Transportation Noise**

**5.1 Points of Reception**

The surface transportation corridors impacting on the Project are Miikana Road and Kelly Farm Drive and both are located within 100 m of the Project.

Other local transportation routes in the area such as Salamander Way are shielded from the Project by residential buildings; and Quest Private is both far away from the critical POR and expected to have a very low volume of traffic. Therefore, they are not considered since their impact on the critical PORs will not be substantial.

Information about the exact locations of windows and doors was not available during this study. PORs were chosen to represent worst-case scenarios at the Plane of Window (PoW) of occupied spaces and Outdoor Living Areas (OLA). Only one PoW POR was considered, which represents the worst-case location

due to exposure to both road segments. Similarly, two PORs was considered for the OLAs (playground and outdoor classroom), at locations consistent with the ENCG’s definition of ‘Outdoor Amenity Area’ (OAA). Table 5 summarizes the descriptions of the location of the PORs, and their locations are shown in Figure 1.

Table 5: Points of Reception and Outdoor Living Areas

| Point of Reception (POR) | Level  | POR Height (m) | Location   | Building Facade | Notes/Comments   |
|--------------------------|--------|----------------|--|-----------------|--|
| POR 1                    | 2nd    | 4.5            | Corner of building, 19.6 m and 16.5 m from the center of Miikana Road and Kelly Farm Drive, respectively | Northwest       | Sound levels at the second floor plane-of-window (PoW) of classroom and library. |
| OLA1                     | Ground | 1.5            | Kindergarten playground behind the building, 75.8 m from the center of Kelly Farm Drive.                 | Facing South    | OLA  |
| OLA2                     | Ground | 1.5            | Outdoor classroom behind the building, 41.5 m from the center of Kelly Farm Drive.                       | Facing South    | OLA  |

**5.2 Road Traffic Noise Parameters**

The surface transportation corridors impacting on the Project are Miikana Road and Kelly Farm Drive, which are already constructed and in use. Miikana Road connects to Bank Road, which is an Arterial Road according to City of Ottawa Road Classification [3, 4], hence Miikana Road is considered as a 2-lane Major Collector road and Kelly Farm Drive is considered as 2-lane Collector road.

The “ultimate” road and traffic data information, including the Annual Average Daily Traffic (AADT), for Miikana Road and Kelly Farm Drive was obtained from the ENCG based on their roadway classifications and are summarized in Table 6. These parameters are used to predict the traffic noise levels following the prediction method outlined in the Ontario Road Noise Analysis Method for Environment and Transportation (ORNAMENT) [5], developed by the MECP. Software developed by the MECP to perform ORNAMENT calculations, STAMSON Version 5.04, was used to predict the noise levels. The output report files from STAMSON software are attached as Appendix A.

Table 6: ENCG Traffic and Road Parameters for STAMSON Modelling

| Road       | Implied Roadway Class           | Speed Limit [km/h] | Ultimate AADT [Vehicles/day] | Day/Night Split [%] | Medium Trucks [%] | Heavy Trucks [%] |
|------------|---------------------------------|--------------------|------------------------------|---------------------|-------------------|------------------|
| Miikana    | 2-Lane Major Collector (2-UMCU) | 50                 | 12,000                       | 92/8                | 7                 | 5                |
| Kelly Farm | 2-Lane Urban Collector (2-UCU)  | 50                 | 8,000                        | 92/8                | 7                 | 5                |

5.3 Estimated Sound Levels at PORs

STAMSON 5.04 software for noise studies in Ontario involving transportation corridors developed by the MECP for the assessment of road and rail noise was used for the analysis. Details of the STAMSON calculations are provided in 0 and summarized in Table 7. The sound level predictions were modelled with sound-absorptive ground surfaces, except for roadways, which were modelled as sound reflective.

Table 7: Calculated Sound Levels at PORs

| POR  | Daytime<br>L <sub>eq</sub> (dBA) | Nighttime<br>L <sub>eq</sub> (dBA) | Building Component<br>OR Noise Barrier Requirement   | Ventilation<br>Requirement | Warning<br>Clause<br>Requirement |
|------|----------------------------------|------------------------------------|--|----------------------------|----------------------------------|
| POR1 | 66                               | 58                                 | Building components (walls, windows, etc.) must be designed to achieve indoor sound level criteria | Central air conditioning   | Type D                           |
| OLA1 | 51                               | 43                                 | N/A  | N/A                        | N/A                              |
| OLA2 | 57                               | 49                                 | Noise Barrier or relocation of OLA2 to another area.   | N/A                        | N/A                              |

5.3.1 Discussion of Sound Level at POR1

Table 7 shows that the calculated daytime surface transportation noise level measured at the Plane of Window (POR1) exceeds the ENCG sound level limits (greater than 65 dBA) presented in Table 2. It should be noted that POR1 at PoW is the worst-case scenario. Furthermore, the exact location of windows and doors are not available at the time of this study, and the vehicle traffic observed during the site visit on May 30, 2022 was very low. The L<sub>EQ</sub> contributed by Miikana Road and Kelly Farm Drive are 64 dBA and 61 dBA, respectively. The distance between the noise source and reception is an important factor that affects sound level, hence an increase in the setback between the proposed school and Miikana Road from 7.5 m to 11 m will reduce the overall daytime L<sub>EQ</sub> value at POR1 to 65 dBA, as shown in Appendix B.

If desired, the re-orientation of the school with 11 m setback from Miikana Road will reduce the sound level from 66 dBA to the acceptable level of 65 dBA at POR1 to comply with ENCG requirements without needing to design building components beyond the specifications of the Ontario Building Code.

5.3.2 Indoor Noise Control Measures

The results presented in Table 7 indicate that the calculated surface transportation noise level measured at the Plane of Window (POR1) is greater than 65 dBA due to exposure to both Miikana Road and Kelly Farm Drive during the daytime. As stated in Tables 2 and 3, City of Ottawa ENCG requires that if the sound level at PoW (POR1) for Daytime L<sub>EQ-16HR</sub> is greater than 65 dBA, Building components (walls, windows, etc.) must be designed to achieve indoor sound level criteria with Type D warning clause. Therefore, the following noise control measures to mitigate the effect of surface transportation noise are required.



### 5.3.2.1 Ventilation Requirements

Central air conditioning must be provided to all occupied spaces inside the proposed school.

### 5.3.2.2 Building Component Requirements

The building envelope components (exterior walls and windows) all facades must be designed to meet indoor sound level of 45 dBA. The National Research Council of Canada (NRC) publications titled “Controlling Sound Transmission into Buildings” [6] provides a step-by-step procedure for calculating appropriate STC ratings for windows and other building envelope components to provide a required noise reduction.

For an assumed window to floor area ratio of 50 %, Acoustic Insulation Factor (AIF) calculation method revealed that fixed windows with 3mm & 3mm double glazing glass and inter-pane spacing of 16 mm, and solid walls constructed in accordance with OBC will provide STC of 31 and 35 respectively and reduce the noise level in the classrooms to acceptable value.

Note that these example constructions are provided for reference only, and the performance of building elements, including window assemblies should be confirmed by the supplier or installer.

### 5.3.2.3 Warning Clause Requirements

A per the ENCG, warning clause Type ‘D’ must be included in agreements of offers of purchase and sale, as well as any lease/rental agreements associated with the school. Sample wording from the ENCG have been adapted below for the Project.

#### **WARNING CLAUSE TYPE “D”**

“This school has been supplied with a central air conditioning system which will allow windows and exterior doors to remain closed, thereby ensuring that the indoor sound levels are within the sound level limits of the Municipality and the Ministry of the Environment.”

## 5.4 Discussion of Sound Level at OLAs

Table 7 presents the daytime calculated surface transportation noise level measured at the Outdoor Living Areas (OLAs) as 51 dBA for the Kindergarten Play Area (OLA1) and 57 dBA at the Outdoor Classroom (OLA2) locations. While the sound level at OLA1 is within the recommended limit (55 dBA), that at OLA2 is more than the limit.

If desired, STAMSON calculations showed that by shifting the Outdoor Classroom from the current 41.5 m to 55 m from the Kelly Farm Drive will reduce the noise level at OLA2 to 55 dBA required by the City of Ottawa, please see Appendix C1 for the STAMSON results.

Alternatively, STAMSON calculations show that a barrier of 1.5 m at 20 m from the outdoor classroom will reduce the daytime noise level to 53 dBA, which is below the limit. See Appendix C2.

#### 5.4.1 Outdoor Noise Control Measures

The location of the Outdoor Classroom may be shifted to 55 m from the middle of Kelly Farm Drive to achieve the require noise limit.

Alternatively, for the proposed site layout without re-orientation of the outdoor classroom, a 1.5 meters tall roadside barrier along Kelly Farm Drive placed at 20 meters from the Outdoor Classroom area will be required to reduce the noise level to acceptable value required by the City of Ottawa.

### 6.0 Surrounding Stationary Noise Source

There were no significant stationary noise sources in the vicinity of the Project at the time of site visit on May 30, 2022. Two tractors were working on the construction of internal roads on the other side of the Kelly Farm Drive on the day of the site visit. This is a temporary event hence is not considered as a source of noise for the Project.

### 7.0 Impact of the Project on Surrounding Area

Mechanical equipment, particularly the rooftop air handling units (RTU) for the Heating Ventilation and Airconditioning (HVAC) systems for the Project, which are expected to be operated 24 hours a day, seven days a week, is considered as a noise source to the surrounding residential buildings. Figure 3 shows the locations of the point of reception for buildings closest to the proposed project and the locations of the rooftop air handling units (RTUs). Three PORs (POR A, POR B, POR C) are consdiered.

#### 7.1 Stationary Noise Sources

As presented in section 5.3.2, noise control measures are required for the present proposed layout of the project. The windows and doors have to remain closed and air conditioning systems have to be provided for air heating and cooling purposes. The required cooling load of the Heating Ventilation and Airconditioning (HVAC) system was estimated based on the footprint area of the project, which was found to be less than the value for a similar project, the Fernbank Public School at 480 Cope Drive. Therefore, the HVAC systems for the Fernbank Public School, a two-storey public school with daycare, are assumed for the analysis to consider the worst-case scenario for the Project. Detailed information about specific mechanical equipment for the Project is not available at the time of this study.

Twelve rooftop air handling units (RTU), which are expected to run 24 hours a day, seven days a week are considered. The RTUs have been sized for the Project such that they may operate at 75% speed during worst-case predictable conditions. Other small rooftop exhaust fans for bathrooms, etc. are considered insignificant noise sources in the context of this study. The 12 RTU units are listed in Table 8, for which radiated noise levels were obtained from the manufacturer (see Appendix D). All of the RTU noise sources are considered to be running for 45 minutes during the day and night, which is 75 % capacity for the evaluation of the  $L_{EQ-1HR}$  calculation of the radiated noise to the surroundings to compare with the 45 dBA limit.

Table 8: Mechanical Noise Sources Associated With School

| Source No. | Location | Description (make / model) | Sound Power Level Data Used (see Appendix B) | Overall Sound Power Level [dBA] |
|------------|----------|----------------------------|--|---------------------------------|
| RTU-1      | Rooftop  | 20 Ton RTU (AAON / RN-020) | "RN 13-20 Ton (75%)"                         | 84                              |
| RTU-2      | Rooftop  | 5 Ton RTU (AAON / RQ-005)  | "RQ 4-6 RN 6 & 7 Ton (75%)"                  | 74                              |
| RTU-3, 4   | Rooftop  | 11 Ton RTU (AAON / RN-011) | "RN 9 & 11 Ton (75%)"                        | 77                              |
| RTU-5      | Rooftop  | 6 Ton RTU (AAON / RQ-006)  | "RQ 4-6 RN 6 & 7 Ton (75%)"                  | 74                              |
| RTU-6      | Rooftop  | 10 Ton RTU (AAON / RN-010) | "RN 8 & 10 Ton (75%)"                        | 81                              |
| RTU-7      | Rooftop  | 7 Ton RTU (AAON / RN-007)  | "RQ 4-6 RN 6 & 7 Ton (75%)"                  | 74                              |
| RTU-8      | Rooftop  | 18 Ton RTU (AAON / RN-018) | "RN 13-20 Ton (75%)"                         | 84                              |
| RTU-9      | Rooftop  | 16 Ton RTU (AAON / RN-016) | "RN 13-20 Ton (75%)"                         | 84                              |
| RTU-10     | Rooftop  | 11 Ton RTU (AAON / RN-011) | "RN 9 & 11 Ton (75%)"                        | 77                              |
| RTU-11     | Rooftop  | 9 Ton RTU (AAON / RN-009)  | "RN 9 & 11 Ton (75%)"                        | 77                              |
| RTU-12     | Rooftop  | 7 Ton RTU (AAON / RN-007)  | "RQ 4-6 RN 6 & 7 Ton (75%)"                  | 74                              |

### 7.2 Receptor Locations

Three critical plane-of-window receptor locations are chosen for nearest residential buildings to the west, north and east labelled as POR A, POR B and POR C. These critical noise receptors represent the locations that are most exposed to the nearest stationary noise sources, at a height of 4.5 m. These receptor locations are shown in Figure 3. Protection of these receptors is expected to result in protection of all other potential off-site plane-of-window and outdoor living area receptors.

### 7.3 Stationary Source Noise Level Prediction

Sound levels at the PORs due to the stationary sources associated with the school were calculated using CadnaA software, version 2019, in accordance with the methods described in ISO 9613-2, and the results are summarized in Table 9 below. Calculated noise level contours are also presented in Figure 4 and CadnaA input and output information is presented as Appendix E . The predicted stationary sound levels do not exceed the ENCG limit at the PORs hence no noise mitigation is required.

Table 9: Predicted Stationary Noise Source Levels at the Receptors

| Receptor | Time Period              | Predicted Stationary Sound Levels $L_{EQ-1hr}$ (dBA) | Stationary Source Sound Level Limit $L_{EQ-1hr}$ (dBA) | Compliance? |
|----------|--------------------------|--|--|-------------|
| POR A    | Night-time (0700 – 1900) | 38   | 45   | Yes         |
| POR B    | Night-time (0700 – 1900) | 38   | 45   | Yes         |
| POR C    | Night-time (0700 – 1900) | 34   | 45   | Yes         |

## 8.0 Concluding Comments

With the implementation of the proposed mitigation measures outlined in Sections 5.3.2 and 5.4.1, the noise impact of the nearby transportation noise sources on the Project is expected to meet the requirements of the ENCG. These noise control measures include:

- Provision of a central air conditioning system which will allow windows and exterior doors to remain closed;
- Design of the building components (walls, windows, etc.) to achieve indoor sound level criteria and/or re-orientation of the building.
- Installation of a noise barrier around the outdoor classroom and/or re-location of the outdoor classroom.

The proposed Project at 820 Miikana Road, Ottawa should therefore be approved from a noise perspective.

Please do not hesitate to contact us if there are any questions.

Yours Truly,

Thornton Tomasetti



Surajudeen Adewusi, Ph.D., P.Eng.  
Senior Engineer

Reviewed by:


Robert Fuller, P.Eng.  
Project Engineer

DISCLAIMER - Achieving the required noise control requirements relies on correct incorporation of noise control recommendations into Architectural and Mechanical drawings and specifications, as well as correct installation during construction. On Request, TT will conduct drawing reviews and onsite reviews of noise control measures and provide observations as appropriate; however, notwithstanding the foregoing, it is expressly understood and agreed that TT shall not have control or charge of, and shall not be responsible for the acts or omissions, including but not limited to means, methods, techniques, sequences and procedures, of the Design Professionals and/or Contractors performing design and/or construction on the Project. Accordingly, TT shall not be held responsible for the failure of any party to properly incorporate the noise control measures stated in this report.

----- End -----

## 9.0 References

1. City of Ottawa Environmental Noise Control Guidelines (ENCG), approved by Ottawa City Council in January 2016.
2. Ministry of the Environment, Conservation and Parks (MOECP) Publication NPC-300: Stationary and Transportation Sources - Approval and Planning, published in October 2013.
3. <https://ottawa.ca/en/planning-development-and-construction/community-design/design-and-planning-guidelines/completed-guidelines/village-collector-and-rural-arterialcollector-road-design>
4. <https://ottawa.ca/en/planning-development-and-construction/official-plan-and-master-plans/official-plan/volume-1-official-plan/section-7-annexes/annex-1-road-classification-and-rights-way>
5. Ontario Road Noise Analysis Method for Environment and Transportation (ORNAMENT), Technical document published by the MOECC in October 1989.
6. Quirt, J David, "[Controlling Sound Transmission into Buildings](#)", NRC Publication 01-09-1985



**ZONING INFORMATION**

SITE: ALL ZONING DEFINITIONS AND REQUIREMENTS AS PER CITY OF OTTAWA ZONING BY-LAW 2006-203

| ZONING MECHANISM                             | REQUIRED   | PROVIDED   |
|--|--|--|
| DEFINITION                                   | R1A MINOR INSTITUTIONAL ZONE   | SCHOOL, DAY CARE   |
| MIN. LOT WIDTH                               | 18.0 m   | 19.6 m   |
| MIN. LOT AREA                                | 402 m <sup>2</sup>   | 28,388 m <sup>2</sup> (3.7 Acres)  |
| MIN. FRONT YARD SETBACK                      | 7.5 m  | 7.5 m  |
| MIN. REAR YARD SETBACK                       | 7.5 m  | 86 m   |
| MIN. INTERIOR SIDE YARD SETBACK              | 7.5 m  | 10 m   |
| MIN. CORNER SIDE YARD SETBACK                | 4.5 m  | 3 m  |
| MAX. BUILDING HEIGHT                         | 16.0 m   | 8.5 m  |
| MAX. FLOOR SPACE INDEX                       | 1.0  | 3.76   |
| MIN. WIDTH OF LANDSCAPED AREA                | ABUTTING A STREET + 3 m  | > 3 m  |
| PARKING LANDSCAPE BUFFER                     | FOR A PARKING LOT CONTAINING:<br>1- 10 SPACES<br>ABUTTING A STREET + 2 m<br>NOT ABUTTING A STREET + 1.5 m  | ABUTTING A STREET + 3 m<br>NOT ABUTTING A STREET + 1.5 m                             |
| PRIVATE APPROACH PROVISIONS                  | 15.0 m AS PER OTTAWA BY-LAW 2004-47 FROM 2004. FOR A PARKING LOT CONTAINING 200 SPACES   | 30.0 m   |
| STANDARD PARKING SPACE                       | 2.8 m WIDTH x 5.2 m LENGTH   | 2.8 m WIDTH x 5.2 m LENGTH   |
| PARALLEL PARKING SPACE                       | 2.6 m WIDTH x 6.7 m LENGTH   | 2.6 m WIDTH x 6.7 m LENGTH   |
| ACCESSIBLE PARKING SPACE                     | 3.6 m WIDTH x 5.2 m LENGTH   | 3.6 m WIDTH x 5.2 m LENGTH   |
| PARKING REQUIREMENTS                         | ELEMENTARY SCHOOL: 13 PARKING SPACES<br>DAYCARE: 15 x 11 SPACES<br>16 PICTURE PORTABLES + 17 SPACES<br>DAYCARE: 230 m <sup>2</sup> x 1 SPACILE<br>TOTAL REQ'D = 72 PARKING SPACES        | 102 PARKING SPACES   |
| BARRIER FREE ACCESSIBLE                      | AS PER OTTAWA TRAFFIC PARKING BY-LAW 2003-533, PART 10, ITEM 10.11.10. FOR A PARKING AREA WITH 4-10 SPACES<br>BARRIER FREE ACCESSIBLE SPACE IS REQ'D                                     | 4 ACCESSIBLE PARKING SPACES  |
| LOADING SPACES                               | 1 per 200 m <sup>2</sup> - 4389 m <sup>2</sup> of G.F.A.   | 4.441 m <sup>2</sup> G.F.A. = 1 SPACE  |
| BICYCLE PARKING RATE                         | 1 per 100 m <sup>2</sup> of G.F.A.<br>1.441 m <sup>2</sup> REQ'D FOR BICYCLE SPACES  | 16 BICYCLE SPACES  |
| MAX. NUMBER OF PRIVATE APPROACHES ALLOWED    | AS PER OTTAWA USE OF PRIVATE APPROACHES BY-LAW 2004-44, ITEM 23.04(1) ONE PRIVATE APPROACH AND TWO ONE-WAY APPROACH OR TWO TWO-WAY APPROACHES ARE PERMITTED.                             | 1 TWO-WAY APPROACH<br>1 ONE-WAY APPROACH<br>1 ONE-WAY APPROACH<br>1 ONE-WAY APPROACH |
| MIN. DISTANCE BETWEEN THE PRIVATE APPROACHES | AS PER OTTAWA USE OF PRIVATE APPROACHES BY-LAW 2004-44, ITEM 23.04(2) 18 M CLEARANCE BETWEEN PRIVATE APPROACHES AND THE APPROACHES REQUIRED FOR THE DISTANCE BETWEEN PRIVATE APPROACHES. |  |



APPROVED  REFUSED

DATE \_\_\_\_\_

XXX XXX, P. Eng., Manager Development Review,  
Suburban Services

|     |                              |           |
|-----|------------------------------|-----------|
| 3   |                              |           |
| 2   |                              |           |
| 1   | ISSUED FOR SITE PLAN CONTROL | XX MAY 22 |
| NO. | revision                     | date      |

**N45 ARCHITECTURE INC.**  
71 Bank Street, 7th floor - Ottawa, Ontario, K1P 5N2  
tel. 613.224.0095 fax 613.224.9811

project #

**FINDLAY CREEK #2 PUBLIC SCHOOL**

820 MIIKANA ROAD  
OTTAWA, ON

project north

seal

drawing title

**SITE PLAN**

scale AS NOTED  
date MAY 2022

drawn by JCK  
checked by VP

project number **A-001**

CONTRACTOR TO VERIFY ALL DIMENSIONS AND NOTIFY THE ARCHITECT OF ANY DISCREPANCIES BEFORE WORK COMMENCES. DO NOT SCALE DRAWINGS.

revision

Figure 1: Site Plan with Point of Reception




Figure 2: Aerial view of the site and surroundings




Figure 3: Location of PORs for HVAC stationary noise sources.





Figure 4: Contour lines for HVAC noise sources on the surroundings.

Appendix A – Results of STAMSON 5.04 Calculations

STAMSON 5.0                    NORMAL REPORT                    Date: 01-06-2022 15:35:24  
 MINISTRY OF ENVIRONMENT AND ENERGY / NOISE ASSESSMENT

Filename: por1.te                    Time Period: Day/Night 16/8 hours  
 Description: POR1 Findlay Creek Elementary School #2

Road data, segment # 1: Miikana (day/night)

-----  
 Car traffic volume : 9715/845    veh/TimePeriod  
 Medium truck volume : 773/67    veh/TimePeriod  
 Heavy truck volume : 552/48    veh/TimePeriod  
 Posted speed limit : 50 km/h  
 Road gradient : 0 %  
 Road pavement : 1 (Typical asphalt or concrete)

Data for Segment # 1: Miikana (day/night)

-----  
 Angle1    Angle2                    : -90.00 deg    90.00 deg  
 Wood depth : 0                    (No woods.)  
 No of house rows : 0 / 0  
 Surface : 1                    (Absorptive ground surface)  
 Receiver source distance : 19.60 / 19.60 m  
 Receiver height : 4.50 / 4.50 m  
 Topography : 1                    (Flat/gentle slope; no barrier)  
 Reference angle : 0.00

Road data, segment # 2: Kelly Farm (day/night)

-----  
 Car traffic volume : 6477/563    veh/TimePeriod  
 Medium truck volume : 515/45    veh/TimePeriod  
 Heavy truck volume : 368/32    veh/TimePeriod  
 Posted speed limit : 50 km/h  
 Road gradient : 0 %  
 Road pavement : 1 (Typical asphalt or concrete)

Data for Segment # 2: Kelly Farm (day/night)

-----  
 Angle1    Angle2                    : 0.00 deg    90.00 deg  
 Wood depth : 0                    (No woods.)  
 No of house rows : 0 / 0  
 Surface : 1                    (Absorptive ground surface)  
 Receiver source distance : 16.50 / 16.50 m  
 Receiver height : 4.50 / 4.50 m  
 Topography : 1                    (Flat/gentle slope; no barrier)  
 Reference angle : 0.00

Results segment # 1: Miikana (day)

Source height = 1.50 m

ROAD (0.00 + 64.38 + 0.00) = 64.38 dBA

| Angle1 | Angle2 | Alpha | RefLeq | P.Adj | D.Adj | F.Adj | W.Adj | H.Adj | B.Adj | SubLeq |
|--------|--------|-------|--------|-------|-------|-------|-------|-------|-------|--------|
| -90    | 90     | 0.57  | 67.51  | 0.00  | -1.82 | -1.30 | 0.00  | 0.00  | 0.00  | 64.38  |

Segment Leq : 64.38 dBA

Results segment # 2: Kelly Farm (day)

Source height = 1.50 m

ROAD (0.00 + 60.79 + 0.00) = 60.79 dBA

| Angle1 | Angle2 | Alpha | RefLeq | P.Adj | D.Adj | F.Adj | W.Adj | H.Adj | B.Adj | SubLeq |
|--------|--------|-------|--------|-------|-------|-------|-------|-------|-------|--------|
| 0      | 90     | 0.57  | 65.75  | 0.00  | -0.65 | -4.31 | 0.00  | 0.00  | 0.00  | 60.79  |

Segment Leq : 60.79 dBA

Total Leq All Segments: 65.96 dBA

Results segment # 1: Miikana (night)

Source height = 1.50 m

ROAD (0.00 + 56.79 + 0.00) = 56.79 dBA

| Angle1 | Angle2 | Alpha | RefLeq | P.Adj | D.Adj | F.Adj | W.Adj | H.Adj | B.Adj | SubLeq |
|--------|--------|-------|--------|-------|-------|-------|-------|-------|-------|--------|
| -90    | 90     | 0.57  | 59.91  | 0.00  | -1.82 | -1.30 | 0.00  | 0.00  | 0.00  | 56.79  |

Segment Leq : 56.79 dBA

Results segment # 2: Kelly Farm (night)

Source height = 1.50 m

ROAD (0.00 + 53.19 + 0.00) = 53.19 dBA

| Angle1 | Angle2 | Alpha | RefLeq | P.Adj | D.Adj | F.Adj | W.Adj | H.Adj | B.Adj | SubLeq |
|--------|--------|-------|--------|-------|-------|-------|-------|-------|-------|--------|
|        |        |       |        |       |       |       |       |       |       |        |

---

|   |    |      |       |      |       |       |      |      |      |       |
|---|----|------|-------|------|-------|-------|------|------|------|-------|
| 0 | 90 | 0.57 | 58.15 | 0.00 | -0.65 | -4.31 | 0.00 | 0.00 | 0.00 | 53.19 |
|---|----|------|-------|------|-------|-------|------|------|------|-------|

---

Segment Leq : 53.19 dBA

Total Leq All Segments: 58.36 dBA

TOTAL Leq FROM ALL SOURCES (DAY): 65.96  
(NIGHT): 58.36

STAMSON 5.0                    NORMAL REPORT                    Date: 01-06-2022 16:57:16  
 MINISTRY OF ENVIRONMENT AND ENERGY / NOISE ASSESSMENT

Filename: OLA1.te                    Time Period: Day/Night 16/8 hours  
 Description: OLA1 Findlay Creek Elementary School #2

Road data, segment # 1: Kelly Farm (day/night)

-----  
 Car traffic volume : 6477/563    veh/TimePeriod  
 Medium truck volume : 515/45    veh/TimePeriod  
 Heavy truck volume : 368/32    veh/TimePeriod  
 Posted speed limit : 50 km/h  
 Road gradient : 0 %  
 Road pavement : 1 (Typical asphalt or concrete)

Data for Segment # 1: Kelly Farm (day/night)

-----  
 Angle1 Angle2 : -25.00 deg 90.00 deg  
 Wood depth : 0 (No woods.)  
 No of house rows : 0 / 0  
 Surface : 1 (Absorptive ground surface)  
 Receiver source distance : 75.80 / 75.80 m  
 Receiver height : 1.50 / 1.50 m  
 Topography : 1 (Flat/gentle slope; no barrier)  
 Reference angle : 0.00

Results segment # 1: Kelly Farm (day)

-----  
 Source height = 1.50 m

ROAD (0.00 + 51.00 + 0.00) = 51.00 dBA

| Angle1 | Angle2 | Alpha | RefLeq | P.Adj | D.Adj  | F.Adj | W.Adj | H.Adj | B.Adj | SubLeq |
|--------|--------|-------|--------|-------|--------|-------|-------|-------|-------|--------|
| -25    | 90     | 0.66  | 65.75  | 0.00  | -11.68 | -3.07 | 0.00  | 0.00  | 0.00  | 51.00  |

-----  
 Segment Leq : 51.00 dBA

Total Leq All Segments: 51.00 dBA

Results segment # 1: Kelly Farm (night)

-----  
 Source height = 1.50 m

ROAD (0.00 + 43.41 + 0.00) = 43.41 dBA

| Angle1 | Angle2 | Alpha | RefLeq | P.Adj | D.Adj | F.Adj | W.Adj | H.Adj | B.Adj | SubLeq |
|--------|--------|-------|--------|-------|-------|-------|-------|-------|-------|--------|
|        |        |       |        |       |       |       |       |       |       |        |

-25      90      0.66    58.16      0.00   -11.68    -3.07      0.00      0.00      0.00    43.41

---

Segment Leq : 43.41 dBA

Total Leq All Segments: 43.41 dBA

TOTAL Leq FROM ALL SOURCES (DAY): 51.00  
(NIGHT): 43.41

STAMSON 5.0                    NORMAL REPORT                    Date: 01-06-2022 17:02:39  
 MINISTRY OF ENVIRONMENT AND ENERGY / NOISE ASSESSMENT

Filename: OLA2.te                    Time Period: Day/Night 16/8 hours  
 Description: OLA2 Findlay Creek Elementary School #2

Road data, segment # 1: Kelly Farm (day/night)

-----  
 Car traffic volume : 6477/563    veh/TimePeriod  
 Medium truck volume : 515/45    veh/TimePeriod  
 Heavy truck volume : 368/32    veh/TimePeriod  
 Posted speed limit : 50 km/h  
 Road gradient : 0 %  
 Road pavement : 1 (Typical asphalt or concrete)

Data for Segment # 1: Kelly Farm (day/night)

-----  
 Angle1 Angle2 : -90.00 deg 90.00 deg  
 Wood depth : 0 (No woods.)  
 No of house rows : 0 / 0  
 Surface : 1 (Absorptive ground surface)  
 Receiver source distance : 41.50 / 41.50 m  
 Receiver height : 1.50 / 1.50 m  
 Topography : 1 (Flat/gentle slope; no barrier)  
 Reference angle : 0.00

Results segment # 1: Kelly Farm (day)

-----  
 Source height = 1.50 m

ROAD (0.00 + 56.96 + 0.00) = 56.96 dBA

| Angle1 | Angle2 | Alpha | RefLeq | P.Adj | D.Adj | F.Adj | W.Adj | H.Adj | B.Adj | SubLeq |
|--------|--------|-------|--------|-------|-------|-------|-------|-------|-------|--------|
| -90    | 90     | 0.66  | 65.75  | 0.00  | -7.34 | -1.46 | 0.00  | 0.00  | 0.00  | 56.96  |

-----  
 Segment Leq : 56.96 dBA

Total Leq All Segments: 56.96 dBA

Results segment # 1: Kelly Farm (night)

-----  
 Source height = 1.50 m

ROAD (0.00 + 49.36 + 0.00) = 49.36 dBA

| Angle1 | Angle2 | Alpha | RefLeq | P.Adj | D.Adj | F.Adj | W.Adj | H.Adj | B.Adj | SubLeq |
|--------|--------|-------|--------|-------|-------|-------|-------|-------|-------|--------|
| -90    | 90     | 0.66  | 65.75  | 0.00  | -7.34 | -1.46 | 0.00  | 0.00  | 0.00  | 56.96  |

-90      90    0.66   58.16    0.00   -7.34   -1.46    0.00    0.00    0.00    49.36

---

Segment Leq : 49.36 dBA

Total Leq All Segments: 49.36 dBA

TOTAL Leq FROM ALL SOURCES (DAY): 56.96  
(NIGHT): 49.36



**Appendix B– Results of STAMSON 5.04 Calculations with Increased Right of Way (ROW) for Miikana Road**

STAMSON 5.0                    NORMAL REPORT                    Date: 02-06-2022 15:37:05  
 MINISTRY OF ENVIRONMENT AND ENERGY / NOISE ASSESSMENT

Filename: por1.te                    Time Period: Day/Night 16/8 hours  
 Description: POR1 with increased ROW for Miikana Road

Road data, segment # 1: Miikana (day/night)

-----  
 Car traffic volume : 9715/845    veh/TimePeriod  
 Medium truck volume : 773/67    veh/TimePeriod  
 Heavy truck volume : 552/48    veh/TimePeriod  
 Posted speed limit : 50 km/h  
 Road gradient : 0 %  
 Road pavement : 1 (Typical asphalt or concrete)

Data for Segment # 1: Miikana (day/night)

-----  
 Angle1    Angle2                    : -90.00 deg    90.00 deg  
 Wood depth                    : 0            (No woods.)  
 No of house rows               : 0 / 0  
 Surface                         : 1            (Absorptive ground surface)  
 Receiver source distance : 23.00 / 23.00 m  
 Receiver height               : 4.50 / 4.50 m  
 Topography                    : 1            (Flat/gentle slope; no barrier)  
 Reference angle               : 0.00

Road data, segment # 2: Kelly Farm (day/night)

-----  
 Car traffic volume : 6477/563    veh/TimePeriod  
 Medium truck volume : 515/45    veh/TimePeriod  
 Heavy truck volume : 368/32    veh/TimePeriod  
 Posted speed limit : 50 km/h  
 Road gradient : 0 %  
 Road pavement : 1 (Typical asphalt or concrete)

Data for Segment # 2: Kelly Farm (day/night)

-----  
 Angle1    Angle2                    : 0.00 deg    90.00 deg  
 Wood depth                    : 0            (No woods.)  
 No of house rows               : 0 / 0  
 Surface                         : 1            (Absorptive ground surface)  
 Receiver source distance : 16.50 / 16.50 m  
 Receiver height               : 4.50 / 4.50 m  
 Topography                    : 1            (Flat/gentle slope; no barrier)  
 Reference angle               : 0.00

Results segment # 1: Miikana (day)

Source height = 1.50 m

ROAD (0.00 + 63.29 + 0.00) = 63.29 dBA

| Angle1 | Angle2 | Alpha | RefLeq | P.Adj | D.Adj | F.Adj | W.Adj | H.Adj | B.Adj | SubLeq |
|--------|--------|-------|--------|-------|-------|-------|-------|-------|-------|--------|
| -90    | 90     | 0.57  | 67.51  | 0.00  | -2.91 | -1.30 | 0.00  | 0.00  | 0.00  | 63.29  |

Segment Leq : 63.29 dBA

Results segment # 2: Kelly Farm (day)

Source height = 1.50 m

ROAD (0.00 + 60.79 + 0.00) = 60.79 dBA

| Angle1 | Angle2 | Alpha | RefLeq | P.Adj | D.Adj | F.Adj | W.Adj | H.Adj | B.Adj | SubLeq |
|--------|--------|-------|--------|-------|-------|-------|-------|-------|-------|--------|
| 0      | 90     | 0.57  | 65.75  | 0.00  | -0.65 | -4.31 | 0.00  | 0.00  | 0.00  | 60.79  |

Segment Leq : 60.79 dBA

Total Leq All Segments: 65.23 dBA

Results segment # 1: Miikana (night)

Source height = 1.50 m

ROAD (0.00 + 55.69 + 0.00) = 55.69 dBA

| Angle1 | Angle2 | Alpha | RefLeq | P.Adj | D.Adj | F.Adj | W.Adj | H.Adj | B.Adj | SubLeq |
|--------|--------|-------|--------|-------|-------|-------|-------|-------|-------|--------|
| -90    | 90     | 0.57  | 59.91  | 0.00  | -2.91 | -1.30 | 0.00  | 0.00  | 0.00  | 55.69  |

Segment Leq : 55.69 dBA

Results segment # 2: Kelly Farm (night)

Source height = 1.50 m

ROAD (0.00 + 53.19 + 0.00) = 53.19 dBA

| Angle1 | Angle2 | Alpha | RefLeq | P.Adj | D.Adj | F.Adj | W.Adj | H.Adj | B.Adj | SubLeq |
|--------|--------|-------|--------|-------|-------|-------|-------|-------|-------|--------|
| -90    | 90     | 0.57  | 57.19  | 0.00  | -2.91 | -1.30 | 0.00  | 0.00  | 0.00  | 53.19  |

---

|   |    |      |       |      |       |       |      |      |      |       |
|---|----|------|-------|------|-------|-------|------|------|------|-------|
| 0 | 90 | 0.57 | 58.15 | 0.00 | -0.65 | -4.31 | 0.00 | 0.00 | 0.00 | 53.19 |
|---|----|------|-------|------|-------|-------|------|------|------|-------|

---

Segment Leq : 53.19 dBA

Total Leq All Segments: 57.63 dBA

TOTAL Leq FROM ALL SOURCES (DAY): 65.23  
(NIGHT): 57.63

**Appendix C1– Results of STAMSON 5.04 Calculations with Outdoor Classroom relocated to 55 m from Kelly Farm Drive**

STAMSON 5.0                  NORMAL REPORT                  Date: 03-06-2022 17:03:01  
 MINISTRY OF ENVIRONMENT AND ENERGY / NOISE ASSESSMENT

Filename: ola1.te                                  Time Period: Day/Night 16/8 hours  
 Description: Findlay Creek School-OLA2 moved to 55m 4rm Kelly

Road data, segment # 1: Kelly Farm (day/night)

```
-----
Car traffic volume  : 6477/563   veh/TimePeriod
Medium truck volume :  515/45    veh/TimePeriod
Heavy truck volume  :  368/32    veh/TimePeriod
Posted speed limit  :    50 km/h
Road gradient       :      0 %
Road pavement      :      1 (Typical asphalt or concrete)
```

Data for Segment # 1: Kelly Farm (day/night)

```
-----
Angle1  Angle2      : -90.00 deg  90.00 deg
Wood depth          :      0        (No woods.)
No of house rows    :      0 / 0
Surface             :      1        (Absorptive ground surface)
Receiver source distance : 55.00 / 55.00 m
Receiver height     :  1.50 / 1.50 m
Topography          :      1        (Flat/gentle slope; no barrier)
Reference angle     :      0.00
```

Results segment # 1: Kelly Farm (day)

Source height = 1.50 m

ROAD (0.00 + 54.93 + 0.00) = 54.93 dBA

| Angle1 | Angle2 | Alpha | RefLeq | P.Adj | D.Adj | F.Adj | W.Adj | H.Adj | B.Adj | SubLeq |
|--------|--------|-------|--------|-------|-------|-------|-------|-------|-------|--------|
| -90    | 90     | 0.66  | 65.75  | 0.00  | -9.37 | -1.46 | 0.00  | 0.00  | 0.00  | 54.93  |

Segment Leq : 54.93 dBA

Total Leq All Segments: 54.93 dBA

Results segment # 1: Kelly Farm (night)

Source height = 1.50 m

ROAD (0.00 + 47.33 + 0.00) = 47.33 dBA

| Angle1 | Angle2 | Alpha | RefLeq | P.Adj | D.Adj | F.Adj | W.Adj | H.Adj | B.Adj | SubLeq |
|--------|--------|-------|--------|-------|-------|-------|-------|-------|-------|--------|
| -90    | 90     | 0.66  | 58.16  | 0.00  | -9.37 | -1.46 | 0.00  | 0.00  | 0.00  | 47.33  |

Segment Leq : 47.33 dBA

Total Leq All Segments: 47.33 dBA

TOTAL Leq FROM ALL SOURCES (DAY): 54.93  
(NIGHT): 47.33

**Appendix C2– Results of STAMSON 5.04 Calculations with 1.5 m Barrier located 20 meters from Outdoor Classroom along Kelly Farm Drive.**

STAMSON 5.0                      NORMAL REPORT                      Date: 13-06-2022 16:08:49  
 MINISTRY OF ENVIRONMENT AND ENERGY / NOISE ASSESSMENT

Filename: ola2bar.te                      Time Period: Day/Night 16/8 hours  
 Description: Barrier between Kelly Farm and Outdoor Classroom

Road data, segment # 1: Kelly Farm (day/night)

```
-----
Car traffic volume   : 6477/563   veh/TimePeriod
Medium truck volume : 515/45    veh/TimePeriod
Heavy truck volume  : 368/32    veh/TimePeriod
Posted speed limit  : 50 km/h
Road gradient       : 0 %
Road pavement      : 1 (Typical asphalt or concrete)
```

Data for Segment # 1: Kelly Farm (day/night)

```
-----
Angle1  Angle2      : -90.00 deg  90.00 deg
Wood depth      : 0          (No woods.)
No of house rows : 0 / 0
Surface         : 1          (Absorptive ground surface)
Receiver source distance : 41.50 / 41.50 m
Receiver height  : 1.50 / 1.50 m
Topography      : 2          (Flat/gentle slope; with barrier)
Barrier angle1   : -90.00 deg  Angle2 : 90.00 deg
Barrier height   : 1.50 m
Barrier receiver distance : 20.00 / 20.00 m
Source elevation : 0.00 m
Receiver elevation : 0.00 m
Barrier elevation : 0.00 m
Reference angle  : 0.00
```

Results segment # 1: Kelly Farm (day)

-----

Source height = 1.50 m

Barrier height for grazing incidence

-----

| Source Height (m) | Receiver Height (m) | Barrier Height (m) | Elevation of Barrier Top (m) |
|-------------------|---------------------|--------------------|------------------------------|
| 1.50              | 1.50                | 1.50               | 1.50                         |

ROAD (0.00 + 52.51 + 0.00) = 52.51 dBA

| Angle1 | Angle2 | Alpha | RefLeq | P.Adj | D.Adj | F.Adj | W.Adj | H.Adj | B.Adj | SubLeq |
|--------|--------|-------|--------|-------|-------|-------|-------|-------|-------|--------|
| -90    | 90     | 0.57  | 65.75  | 0.00  | -6.94 | -1.30 | 0.00  | 0.00  | -5.00 | 52.51  |

Segment Leq : 52.51 dBA

Total Leq All Segments: 52.51 dBA

Results segment # 1: Kelly Farm (night)

Source height = 1.50 m

Barrier height for grazing incidence

| Source Height (m) | Receiver Height (m) | Barrier Height (m) | Elevation of Barrier Top (m) |
|-------------------|---------------------|--------------------|------------------------------|
| 1.50              | 1.50                | 1.50               | 1.50                         |

ROAD (0.00 + 44.92 + 0.00) = 44.92 dBA

| Angle1 | Angle2 | Alpha | RefLeq | P.Adj | D.Adj | F.Adj | W.Adj | H.Adj | B.Adj | SubLeq |
|--------|--------|-------|--------|-------|-------|-------|-------|-------|-------|--------|
| -90    | 90     | 0.57  | 58.16  | 0.00  | -6.94 | -1.30 | 0.00  | 0.00  | -5.00 | 44.92  |

Segment Leq : 44.92 dBA

Total Leq All Segments: 44.92 dBA

TOTAL Leq FROM ALL SOURCES (DAY): 52.51  
(NIGHT): 44.92

Appendix D – Sound Power Level Data for AAON RTUs

| Speed % | RTU Model           | Inlet  | Outlet | Total | Fans | Dia | RPM  | Sound Power Level |     |     |     |      |      |      |      |     |
|---------|---------------------|--------|--------|-------|------|-----|------|-------------------|-----|-----|-----|------|------|------|------|-----|
|         |                     |        |        |       |      |     |      | 63                | 125 | 250 | 500 | 1000 | 2000 | 4000 | 8000 | LWA |
| 100%    | RQ 2 & 3 Ton        | Inlet  |        |       | 1    | 30  | 850  | 79                | 74  | 72  | 70  | 66   | 62   | 59   | 59   | 72  |
|         |                     | Outlet |        |       |      |     |      | 81                | 77  | 71  | 71  | 67   | 62   | 59   | 58   | 73  |
|         |                     | Total  |        |       |      |     |      | 83                | 79  | 74  | 73  | 69   | 65   | 62   | 61   | 75  |
| 75%     | RQ 2 & 3 Ton        | Inlet  |        |       | 1    | 30  | 638  | 73                | 68  | 66  | 63  | 59   | 56   | 53   | 52   | 65  |
|         |                     | Outlet |        |       |      |     |      | 75                | 71  | 64  | 65  | 60   | 56   | 53   | 52   | 66  |
|         |                     | Total  |        |       |      |     |      | 77                | 73  | 68  | 67  | 63   | 59   | 56   | 55   | 69  |
| 50%     | RQ 2 & 3 Ton        | Inlet  |        |       | 1    | 30  | 425  | 84                | 59  | 57  | 54  | 51   | 47   | 44   | 44   | 57  |
|         |                     | Outlet |        |       |      |     |      | 66                | 62  | 56  | 56  | 52   | 47   | 44   | 43   | 57  |
|         |                     | Total  |        |       |      |     |      | 68                | 64  | 59  | 58  | 54   | 50   | 47   | 46   | 60  |
| 25%     | RQ 2 & 3 Ton        | Inlet  |        |       | 1    | 30  | 213  | 49                | 44  | 42  | 39  | 36   | 32   | 29   | 29   | 42  |
|         |                     | Outlet |        |       |      |     |      | 51                | 47  | 40  | 41  | 37   | 32   | 29   | 28   | 42  |
|         |                     | Total  |        |       |      |     |      | 53                | 49  | 44  | 43  | 39   | 35   | 32   | 31   | 45  |
| 100%    | RQ 4-6 RN 6 & 7 Ton | Inlet  |        |       | 1    | 30  | 1085 | 85                | 79  | 77  | 75  | 71   | 68   | 65   | 64   | 77  |
|         |                     | Outlet |        |       |      |     |      | 86                | 83  | 76  | 76  | 72   | 68   | 65   | 63   | 78  |
|         |                     | Total  |        |       |      |     |      | 89                | 84  | 80  | 79  | 75   | 71   | 68   | 67   | 80  |
| 75%     | RQ 4-6 RN 6 & 7 Ton | Inlet  |        |       | 1    | 30  | 814  | 78                | 73  | 71  | 69  | 65   | 61   | 58   | 58   | 71  |
|         |                     | Outlet |        |       |      |     |      | 80                | 77  | 70  | 70  | 66   | 61   | 58   | 57   | 72  |
|         |                     | Total  |        |       |      |     |      | 82                | 78  | 73  | 72  | 68   | 64   | 61   | 61   | 74  |
| 50%     | RQ 4-6 RN 6 & 7 Ton | Inlet  |        |       | 1    | 30  | 543  | 70                | 64  | 62  | 60  | 56   | 53   | 50   | 49   | 63  |
|         |                     | Outlet |        |       |      |     |      | 71                | 68  | 61  | 61  | 57   | 53   | 50   | 48   | 63  |
|         |                     | Total  |        |       |      |     |      | 74                | 69  | 65  | 64  | 59   | 56   | 53   | 52   | 65  |
| 25%     | RQ 4-6 RN 6 & 7 Ton | Inlet  |        |       | 1    | 30  | 271  | 54                | 49  | 47  | 45  | 41   | 37   | 35   | 34   | 47  |
|         |                     | Outlet |        |       |      |     |      | 56                | 53  | 46  | 46  | 42   | 38   | 35   | 33   | 48  |
|         |                     | Total  |        |       |      |     |      | 59                | 54  | 50  | 48  | 44   | 41   | 38   | 37   | 50  |
| 100%    | RN 8 & 10 Ton       | Inlet  |        |       | 1    | 30  | 1085 | 92                | 86  | 85  | 82  | 78   | 75   | 72   | 71   | 84  |
|         |                     | Outlet |        |       |      |     |      | 94                | 90  | 83  | 83  | 79   | 75   | 72   | 71   | 85  |
|         |                     | Total  |        |       |      |     |      | 96                | 91  | 87  | 86  | 82   | 78   | 75   | 74   | 88  |
| 75%     | RN 8 & 10 Ton       | Inlet  |        |       | 1    | 30  | 814  | 86                | 80  | 78  | 76  | 72   | 68   | 66   | 65   | 78  |
|         |                     | Outlet |        |       |      |     |      | 87                | 84  | 77  | 77  | 73   | 69   | 66   | 64   | 79  |
|         |                     | Total  |        |       |      |     |      | 90                | 85  | 81  | 80  | 75   | 72   | 69   | 68   | 81  |
| 50%     | RN 8 & 10 Ton       | Inlet  |        |       | 1    | 30  | 543  | 77                | 71  | 69  | 67  | 63   | 60   | 57   | 56   | 69  |
|         |                     | Outlet |        |       |      |     |      | 79                | 75  | 68  | 68  | 64   | 60   | 57   | 56   | 70  |
|         |                     | Total  |        |       |      |     |      | 81                | 76  | 72  | 71  | 67   | 63   | 60   | 59   | 73  |
| 25%     | RN 8 & 10 Ton       | Inlet  |        |       | 1    | 30  | 271  | 62                | 56  | 54  | 52  | 48   | 45   | 42   | 41   | 54  |
|         |                     | Outlet |        |       |      |     |      | 64                | 60  | 53  | 53  | 49   | 45   | 42   | 41   | 55  |
|         |                     | Total  |        |       |      |     |      | 66                | 61  | 57  | 56  | 52   | 48   | 45   | 44   | 58  |
| 100%    | RN 9 & 11 Ton       | Inlet  |        |       | 2    | 30  | 1085 | 88                | 82  | 80  | 78  | 74   | 71   | 68   | 67   | 80  |
|         |                     | Outlet |        |       |      |     |      | 89                | 86  | 79  | 79  | 75   | 71   | 68   | 66   | 81  |
|         |                     | Total  |        |       |      |     |      | 92                | 87  | 83  | 82  | 78   | 74   | 71   | 70   | 83  |
| 75%     | RN 9 & 11 Ton       | Inlet  |        |       | 2    | 30  | 814  | 81                | 76  | 74  | 72  | 68   | 64   | 61   | 61   | 74  |
|         |                     | Outlet |        |       |      |     |      | 83                | 80  | 73  | 73  | 69   | 64   | 61   | 60   | 75  |
|         |                     | Total  |        |       |      |     |      | 85                | 81  | 76  | 75  | 71   | 67   | 64   | 64   | 77  |
| 50%     | RN 9 & 11 Ton       | Inlet  |        |       | 2    | 30  | 407  | 66                | 61  | 59  | 57  | 53   | 49   | 46   | 46   | 59  |
|         |                     | Outlet |        |       |      |     |      | 68                | 64  | 58  | 58  | 54   | 49   | 46   | 45   | 60  |
|         |                     | Total  |        |       |      |     |      | 70                | 66  | 61  | 60  | 56   | 52   | 49   | 48   | 62  |
| 25%     | RN 9 & 11 Ton       | Inlet  |        |       | 2    | 30  | 271  | 57                | 52  | 50  | 48  | 44   | 40   | 38   | 37   | 50  |
|         |                     | Outlet |        |       |      |     |      | 59                | 56  | 49  | 49  | 45   | 41   | 38   | 36   | 51  |
|         |                     | Total  |        |       |      |     |      | 62                | 57  | 53  | 51  | 47   | 44   | 41   | 40   | 53  |
| 100%    | RN 13-20 Ton        | Inlet  |        |       | 2    | 30  | 1085 | 95                | 89  | 88  | 85  | 81   | 78   | 75   | 74   | 87  |
|         |                     | Outlet |        |       |      |     |      | 97                | 93  | 86  | 86  | 82   | 78   | 75   | 74   | 88  |
|         |                     | Total  |        |       |      |     |      | 99                | 94  | 90  | 89  | 85   | 81   | 78   | 77   | 91  |
| 75%     | RN 13-20 Ton        | Inlet  |        |       | 2    | 30  | 814  | 89                | 83  | 81  | 79  | 75   | 71   | 69   | 68   | 81  |
|         |                     | Outlet |        |       |      |     |      | 90                | 87  | 80  | 80  | 76   | 72   | 69   | 67   | 82  |
|         |                     | Total  |        |       |      |     |      | 93                | 88  | 84  | 83  | 78   | 75   | 72   | 71   | 84  |
| 50%     | RN 13-20 Ton        | Inlet  |        |       | 2    | 30  | 543  | 80                | 74  | 72  | 70  | 66   | 63   | 60   | 59   | 72  |
|         |                     | Outlet |        |       |      |     |      | 82                | 78  | 71  | 71  | 67   | 63   | 60   | 59   | 73  |
|         |                     | Total  |        |       |      |     |      | 84                | 79  | 75  | 74  | 70   | 66   | 63   | 62   | 76  |
| 25%     | RN 13-20 Ton        | Inlet  |        |       | 2    | 30  | 271  | 65                | 59  | 57  | 55  | 51   | 48   | 45   | 44   | 57  |
|         |                     | Outlet |        |       |      |     |      | 67                | 63  | 56  | 56  | 52   | 48   | 45   | 44   | 58  |
|         |                     | Total  |        |       |      |     |      | 69                | 64  | 60  | 59  | 55   | 51   | 48   | 47   | 61  |
| 100%    | RN 25 & 30 Ton      | Inlet  |        |       | 3    | 30  | 1085 | 97                | 91  | 89  | 87  | 83   | 80   | 77   | 76   | 89  |
|         |                     | Outlet |        |       |      |     |      | 98                | 95  | 88  | 88  | 84   | 80   | 77   | 75   | 90  |
|         |                     | Total  |        |       |      |     |      | 101               | 96  | 92  | 91  | 86   | 83   | 80   | 79   | 92  |
| 75%     | RN 25 & 30 Ton      | Inlet  |        |       | 3    | 30  | 814  | 90                | 85  | 83  | 81  | 77   | 73   | 70   | 70   | 83  |
|         |                     | Outlet |        |       |      |     |      | 92                | 88  | 82  | 82  | 78   | 73   | 70   | 69   | 83  |
|         |                     | Total  |        |       |      |     |      | 94                | 90  | 85  | 84  | 80   | 76   | 73   | 72   | 86  |
| 50%     | RN 25 & 30 Ton      | Inlet  |        |       | 3    | 30  | 543  | 81                | 76  | 74  | 72  | 68   | 64   | 62   | 61   | 74  |
|         |                     | Outlet |        |       |      |     |      | 83                | 80  | 73  | 73  | 69   | 65   | 62   | 60   | 75  |
|         |                     | Total  |        |       |      |     |      | 86                | 81  | 77  | 75  | 71   | 67   | 65   | 64   | 77  |
| 25%     | RN 25 & 30 Ton      | Inlet  |        |       | 3    | 30  | 271  | 66                | 61  | 59  | 57  | 53   | 49   | 47   | 46   | 59  |
|         |                     | Outlet |        |       |      |     |      | 68                | 65  | 58  | 58  | 54   | 49   | 47   | 45   | 60  |
|         |                     | Total  |        |       |      |     |      | 70                | 66  | 62  | 60  | 56   | 52   | 50   | 49   | 62  |



**Appendix E – CadnaA Input and Output Information**

**Report (Siteplan\_HVAC\_EffectJune7b.cna)**

**Calculation Configuration**

| Configuration                                  |                                |
|--|--------------------------------|
| Parameter                                      | Value                          |
| General  |                                |
| Country  | (user defined)                 |
| Max. Error (dB)                                | 0.00                           |
| Max. Search Radius (#(Unit,LEN))               | 2000.00                        |
| Min. Dist Src to Rcvr                          | 0.00                           |
| Partition                                      |                                |
| Raster Factor                                  | 0.50                           |
| Max. Length of Section (#(Unit,LEN))           | 1000.00                        |
| Min. Length of Section (#(Unit,LEN))           | 1.00                           |
| Min. Length of Section (%)                     | 0.00                           |
| Proj. Line Sources                             | On                             |
| Proj. Area Sources                             | On                             |
| Ref. Time                                      |                                |
| Reference Time Day (min)                       | 960.00                         |
| Reference Time Night (min)                     | 480.00                         |
| Daytime Penalty (dB)                           | 0.00                           |
| Recr. Time Penalty (dB)                        | 0.00                           |
| Night-time Penalty (dB)                        | 0.00                           |
| DTM  |                                |
| Standard Height (m)                            | 0.00                           |
| Model of Terrain                               | Triangulation                  |
| Reflection                                     |                                |
| max. Order of Reflection                       | 2                              |
| Search Radius Src                              | 100.00                         |
| Search Radius Rcvr                             | 100.00                         |
| Max. Distance Source - Rcvr                    | 1000.00 1000.00                |
| Min. Distance Rcvr - Reflector                 | 1.00 1.00                      |
| Min. Distance Source - Reflector               | 0.10                           |
| Industrial (ISO 9613)                          |                                |
| Lateral Diffraction                            | some Obj                       |
| Obst. within Area Src do not shield            | On                             |
| Screening                                      | Excl. Ground Att. over Barrier |
|  | Dz with limit (20/25)          |
| Barrier Coefficients C1,2,3                    | 3.0 20.0 0.0                   |
| Temperature (#(Unit,TEMP))                     | 10                             |
| rel. Humidity (%)                              | 70                             |
| Ground Absorption G                            | 1.00                           |
| Wind Speed for Dir. (#(Unit,SPEED))            | 3.0                            |
| Roads (RLS-90)                                 |                                |
| Strictly acc. to RLS-90                        |                                |
| Railways (Schall 03 (1990))                    |                                |
| Strictly acc. to Schall 03 / Schall-Transrapid |                                |
| Aircraft (???)                                 |                                |
| Strictly acc. to AzB                           |                                |

**Result Table**

| Receiver |       | Land Use | Limiting Value |       |         | rel. Axis |        |       | Lr w/o Noise Control |       | dL req. |       | Lr w/ Noise Control |       | Exceeding |       | passive NC |
|----------|-------|----------|----------------|-------|---------|-----------|--------|-------|----------------------|-------|---------|-------|---------------------|-------|-----------|-------|------------|
| Name     | ID    |          | Day            | Night | Station | Distance  | Height | Day   | Night                | Day   | Night   | Day   | Night               | Day   | Night     |       |            |
|          |       |          | dB(A)          | dB(A) | m       | m         | m      | dB(A) | dB(A)                | dB(A) | dB(A)   | dB(A) | dB(A)               | dB(A) | dB(A)     | dB(A) |            |
| POR A    | POR_A |          | 45             | 45    |         |           |        | 37.6  | 37.6                 | -     | -       | 0.0   | 0.0                 | -     | -         | -     |            |
| POR B    | POR_B |          | 45             | 45    |         |           |        | 38.2  | 38.2                 | -     | -       | 0.0   | 0.0                 | -     | -         | -     |            |
| POR C    | POR_C |          | 45             | 45    |         |           |        | 34.1  | 34.1                 | -     | -       | 0.0   | 0.0                 | -     | -         | -     |            |

**Group Day and Night**

| Name | Expression | Partial Sum Level |             |             |
|------|------------|-------------------|-------------|-------------|
|      |            | POR A             | POR B       | POR C       |
|      |            | Day   Night       | Day   Night | Day   Night |
|      |            |                   |             |             |

Partial Day/Night

| Source |       | Partial Level |       |       |       |       |       |
|--------|-------|---------------|-------|-------|-------|-------|-------|
| Name   | M. ID | POR A         |       | POR B |       | POR C |       |
|        |       | Day           | Night | Day   | Night | Day   | Night |
| RTU-1  |       | 26.0          | 26.0  | 19.5  | 19.5  | 12.1  | 12.1  |
| RTU-1  |       | 35.7          | 35.7  | 28.4  | 28.4  | 22.0  | 22.0  |
| RTU-3  |       | 25.3          | 25.3  | 23.2  | 23.2  | 16.0  | 16.0  |
| RTU-4  |       | 22.6          | 22.6  | 26.2  | 26.2  | 17.4  | 17.4  |
| RTU-5  |       | 19.0          | 19.0  | 21.7  | 21.7  | 14.5  | 14.5  |
| RTU-6  |       | 24.1          | 24.1  | 31.3  | 31.3  | 23.1  | 23.1  |
| RTU-7  |       | 16.5          | 16.5  | 22.1  | 22.1  | 16.0  | 16.0  |
| RTU-8  |       | 25.1          | 25.1  | 33.2  | 33.2  | 28.4  | 28.4  |
| RTU-12 |       | 13.6          | 13.6  | 21.0  | 21.0  | 21.4  | 21.4  |
| RTU-11 |       | 15.9          | 15.9  | 22.4  | 22.4  | 25.1  | 25.1  |
| RTU-9  |       | 24.6          | 24.6  | 29.9  | 29.9  | 28.2  | 28.2  |
| RTU-10 |       | 16.7          | 16.7  | 22.3  | 22.3  | 22.6  | 22.6  |

## Sound Sources

### Point Sources

| Name   | M. ID | Result. PWL |         |       | Lw / Li |       | Correction |       |         | Sound Reduction |      | Attenuation | Operating Time |       |         | K0   | Freq.  | Direct. | Height | Coordinates |            |      |
|--------|-------|-------------|---------|-------|---------|-------|------------|-------|---------|-----------------|------|-------------|----------------|-------|---------|------|--------|---------|--------|-------------|------------|------|
|        |       | Day         | Evening | Night | Type    | Value | norm.      | Day   | Evening | Night           | R    |             | Area           | Day   | Special |      |        |         |        | Night       | (min)      | (Hz) |
|        |       | (dBA)       | (dBA)   | (dBA) |         | dB(A) | dB(A)      | dB(A) | dB(A)   |                 | (m²) |             | (min)          | (min) | (min)   | (dB) | (Hz)   |         | (m)    | (m)         | (m)        |      |
| RTU-1  |       | 74.0        | 74.0    | 74.0  | Lw      | 74    |            | 0.0   | 0.0     | 0.0             |      | 45.00       | 45.00          | 45.00 | 0.0     | 500  | (none) | 0.50    | g      | 453304.01   | 5017651.55 | 6.50 |
| RTU-1  |       | 84.0        | 84.0    | 84.0  | Lw      | 84    |            | 0.0   | 0.0     | 0.0             |      | 45.00       | 45.00          | 45.00 | 0.0     | 500  | (none) | 0.50    | g      | 453307.56   | 5017640.89 | 6.50 |
| RTU-3  |       | 77.0        | 77.0    | 77.0  | Lw      | 77    |            | 0.0   | 0.0     | 0.0             |      | 45.00       | 45.00          | 45.00 | 0.0     | 500  | (none) | 0.50    | g      | 453322.05   | 5017651.96 | 6.50 |
| RTU-4  |       | 77.0        | 77.0    | 77.0  | Lw      | 77    |            | 0.0   | 0.0     | 0.0             |      | 45.00       | 45.00          | 45.00 | 0.0     | 500  | (none) | 0.50    | g      | 453336.74   | 5017668.33 | 6.50 |
| RTU-5  |       | 74.0        | 74.0    | 74.0  | Lw      | 74    |            | 0.0   | 0.0     | 0.0             |      | 45.00       | 45.00          | 45.00 | 0.0     | 500  | (none) | 0.50    | g      | 453343.03   | 5017659.93 | 6.50 |
| RTU-6  |       | 81.0        | 81.0    | 81.0  | Lw      | 81    |            | 0.0   | 0.0     | 0.0             |      | 45.00       | 45.00          | 45.00 | 0.0     | 500  | (none) | 0.50    | g      | 453357.30   | 5017677.98 | 6.50 |
| RTU-7  |       | 74.0        | 74.0    | 74.0  | Lw      | 74    |            | 0.0   | 0.0     | 0.0             |      | 45.00       | 45.00          | 45.00 | 0.0     | 500  | (none) | 6.00    | r      | 453363.18   | 5017669.17 | 6.00 |
| RTU-8  |       | 84.0        | 84.0    | 84.0  | Lw      | 84    |            | 0.0   | 0.0     | 0.0             |      | 45.00       | 45.00          | 45.00 | 0.0     | 500  | (none) | 0.50    | g      | 453379.55   | 5017689.73 | 6.50 |
| RTU-12 |       | 74.0        | 74.0    | 74.0  | Lw      | 74    |            | 0.0   | 0.0     | 0.0             |      | 45.00       | 45.00          | 45.00 | 0.0     | 500  | (none) | 0.50    | g      | 453400.11   | 5017701.90 | 6.50 |
| RTU-11 |       | 77.0        | 77.0    | 77.0  | Lw      | 77    |            | 0.0   | 0.0     | 0.0             |      | 45.00       | 45.00          | 45.00 | 0.0     | 500  | (none) | 0.50    | g      | 453410.60   | 5017693.09 | 6.50 |
| RTU-9  |       | 84.0        | 84.0    | 84.0  | Lw      | 84    |            | 0.0   | 0.0     | 0.0             |      | 45.00       | 45.00          | 45.00 | 0.0     | 500  | (none) | 0.50    | g      | 453390.88   | 5017669.59 | 6.50 |
| RTU-10 |       | 77.0        | 77.0    | 77.0  | Lw      | 77    |            | 0.0   | 0.0     | 0.0             |      | 45.00       | 45.00          | 45.00 | 0.0     | 500  | (none) | 0.50    | g      | 453401.79   | 5017675.88 | 6.50 |

### Line Sources

| Name | M. ID | Result. PWL |         |       | Result. PWL' |         |       | Lw / Li |       | Correction |       |         | Sound Reduction |      | Attenuation | Operating Time |       |         | K0   | Freq. | Direct. | Moving Pt. Src |       |       |        |      |
|------|-------|-------------|---------|-------|--------------|---------|-------|---------|-------|------------|-------|---------|-----------------|------|-------------|----------------|-------|---------|------|-------|---------|----------------|-------|-------|--------|------|
|      |       | Day         | Evening | Night | Day          | Evening | Night | Type    | Value | norm.      | Day   | Evening | Night           | R    |             | Area           | Day   | Special |      |       |         | Night          | (min) | (min) | (min)  | (dB) |
|      |       | (dBA)       | (dBA)   | (dBA) | (dBA)        | (dBA)   | (dBA) |         | dB(A) | dB(A)      | dB(A) | dB(A)   |                 | (m²) |             | (min)          | (min) | (min)   | (dB) | (Hz)  |         | (m)            | (m)   | (m)   | (km/h) |      |

### Geometry Line Sources

| Name | Height |     | Coordinates |     |     |        |
|------|--------|-----|-------------|-----|-----|--------|
|      | Begin  | End | x           | y   | z   | Ground |
|      | (m)    | (m) | (m)         | (m) | (m) | (m)    |

### Area Sources

| Name | M. ID | Result. PWL |         |       | Result. PWL" |         |       | Lw / Li |       | Correction |       |         | Sound Reduction |      | Attenuation | Operating Time  |  |   | K0   | Freq.   | Direct. | Moving Pt. Src |       |       |        |      |
|------|-------|-------------|---------|-------|--------------|---------|-------|---------|-------|------------|-------|---------|-----------------|------|-------------|---|--|---|--|---|---------|----------------|-------|-------|--------|------|
|      |       | Day         | Evening | Night | Day          | Evening | Night | Type    | Value | norm.      | Day   | Evening | Night           | R    |             | Area  | Day  | Special   |  |   |         | Night          | (min) | (min) | (min)  | (dB) |
|      |       | (dBA)       | (dBA)   | (dBA) | (dBA)        | (dBA)   | (dBA) |         | dB(A) | dB(A)      | dB(A) | dB(A)   |                 | (m²) |             | (min) <td>(min) <td>(min) <td>(dB) <td>(Hz) <td></td> <td>(m)</td> <td>(m)</td> <td>(m)</td> <td>(km/h)</td> <td></td> </td></td></td></td> | (min) <td>(min) <td>(dB) <td>(Hz) <td></td> <td>(m)</td> <td>(m)</td> <td>(m)</td> <td>(km/h)</td> <td></td> </td></td></td> | (min) <td>(dB) <td>(Hz) <td></td> <td>(m)</td> <td>(m)</td> <td>(m)</td> <td>(km/h)</td> <td></td> </td></td> | (dB) <td>(Hz) <td></td> <td>(m)</td> <td>(m)</td> <td>(m)</td> <td>(km/h)</td> <td></td> </td> | (Hz) <td></td> <td>(m)</td> <td>(m)</td> <td>(m)</td> <td>(km/h)</td> <td></td> |         | (m)            | (m)   | (m)   | (km/h) |      |

### Geometry Area Sources

| Name | Height |     | Coordinates |     |     |        |
|------|--------|-----|-------------|-----|-----|--------|
|      | Begin  | End | x           | y   | z   | Ground |
|      | (m)    | (m) | (m)         | (m) | (m) | (m)    |

### Vertical Area Sources

| Name | M. ID | Result. PWL |         |       | Result. PWL" |         |       | Lw / Li |       | Correction |       |         | Sound Reduction |      | Attenuation | Operating Time   |   |  | K0                            | Freq.          | Direct. |
|------|-------|-------------|---------|-------|--------------|---------|-------|---------|-------|------------|-------|---------|-----------------|------|-------------|--|---|--|-------------------------------|----------------|---------|
|      |       | Day         | Evening | Night | Day          | Evening | Night | Type    | Value | norm.      | Day   | Evening | Night           | R    |             | Area   | Day   | Special                                      |                               |                |         |
|      |       | (dBA)       | (dBA)   | (dBA) | (dBA)        | (dBA)   | (dBA) |         | dB(A) | dB(A)      | dB(A) | dB(A)   |                 | (m²) |             | (min) <td>(min) <td>(min) <td>(dB) <td>(Hz) <td></td> </td></td></td></td> | (min) <td>(min) <td>(dB) <td>(Hz) <td></td> </td></td></td> | (min) <td>(dB) <td>(Hz) <td></td> </td></td> | (dB) <td>(Hz) <td></td> </td> | (Hz) <td></td> |         |

### Geometry Vertical Area Sources

| Name | Height |     | Coordinates |     |     |        |
|------|--------|-----|-------------|-----|-----|--------|
|      | Begin  | End | x           | y   | z   | Ground |
|      | (m)    | (m) | (m)         | (m) | (m) | (m)    |

### Road

| Name | M. ID | Lme   |         |       | Count Data |            | exact Count Data |         |       |     | Speed Limit |       | SCS    | Surface |      | Gradient | Mult. Reflection |        |       |     |
|------|-------|-------|---------|-------|------------|------------|------------------|---------|-------|-----|-------------|-------|--------|---------|------|----------|------------------|--------|-------|-----|
|      |       | Day   | Evening | Night | DTV        | Str.class. | M                |         | p (%) |     | Auto        | Truck | Dist.  | Dstro   | Type | (%)      | Drefl            | Hbuild | Dist. |     |
|      |       | (dBA) | (dBA)   | (dBA) |            |            | Day              | Evening | Night | Day | Evening     | Night | (km/h) | (km/h)  | (dB) |          | (%)              | (dB)   | (m)   | (m) |

Geometry Road

| Name | Height |     | Coordinates |     |     |        | Dist | LSlope |
|------|--------|-----|-------------|-----|-----|--------|------|--------|
|      | Begin  | End | x           | y   | z   | Ground | (m)  | (%)    |
|      | (m)    | (m) | (m)         | (m) | (m) | (m)    |      |        |

Receptors

| Name  | M. | ID    | Level Lr |       | Limit. Value |       | Land Use |      | Height | Coordinates |      |     |           |            |      |
|-------|----|-------|----------|-------|--------------|-------|----------|------|--------|-------------|------|-----|-----------|------------|------|
|       |    |       | Day      | Night | Day          | Night | Type     | Auto | Noise  | Type        | X    | Y   | Z         |            |      |
|       |    |       | (dBA)    | (dBA) | (dBA)        | (dBA) |          |      |        |             | (m)  | (m) | (m)       | (m)        |      |
| POR A |    | POR_A | 37.6     | 37.6  | 45.0         | 45.0  |          |      |        |             | 4.50 | r   | 453271.13 | 5017639.11 | 4.50 |
| POR B |    | POR_B | 38.2     | 38.2  | 45.0         | 45.0  |          |      |        |             | 4.50 | r   | 453339.91 | 5017717.26 | 4.50 |
| POR C |    | POR_C | 34.1     | 34.1  | 45.0         | 45.0  |          |      |        |             | 4.50 | r   | 453453.30 | 5017727.38 | 4.50 |

Obstacles

Barriers

| Name | M. | ID | Absorption |       | Z-Ext. | Cantilever |       | Height |     |
|------|----|----|------------|-------|--------|------------|-------|--------|-----|
|      |    |    | left       | right |        | horz.      | vert. | Begin  | End |
|      |    |    |            |       | (m)    | (m)        | (m)   | (m)    | (m) |

Geometry Barriers

| Name | M. | ID | Absorption |       | Z-Ext. | Cantilever |       | Height |     | Coordinates |     |     |        |     |
|------|----|----|------------|-------|--------|------------|-------|--------|-----|-------------|-----|-----|--------|-----|
|      |    |    | left       | right |        | horz.      | vert. | Begin  | End | x           | y   | z   | Ground |     |
|      |    |    |            |       | (m)    | (m)        | (m)   | (m)    | (m) | (m)         | (m) | (m) | (m)    | (m) |

Building

| Name   | M. | ID | RB | Residents | Absorption | Height |
|--------|----|----|----|-----------|------------|--------|
|        |    |    |    |           |            | Begin  |
|        |    |    |    |           |            | (m)    |
| School |    |    |    | 0         |            | 6.00   |

Geometry Building

| Name   | M. | ID | RB | Residents | Absorption | Height | Coordinates |           |            |        |      |
|--------|----|----|----|-----------|------------|--------|-------------|-----------|------------|--------|------|
|        |    |    |    |           |            | Begin  | x           | y         | z          | Ground |      |
|        |    |    |    |           |            | (m)    | (m)         | (m)       | (m)        | (m)    |      |
| School |    |    |    | 0         |            | 6.00   | r           | 453293.48 | 5017651.97 | 6.00   | 0.00 |
|        |    |    |    |           |            |        |             | 453324.28 | 5017668.90 | 6.00   | 0.00 |
|        |    |    |    |           |            |        |             | 453323.62 | 5017669.82 | 6.00   | 0.00 |
|        |    |    |    |           |            |        |             | 453335.12 | 5017676.30 | 6.00   | 0.00 |
|        |    |    |    |           |            |        |             | 453336.18 | 5017675.37 | 6.00   | 0.00 |
|        |    |    |    |           |            |        |             | 453403.20 | 5017713.97 | 6.00   | 0.00 |
|        |    |    |    |           |            |        |             | 453406.77 | 5017707.10 | 6.00   | 0.00 |
|        |    |    |    |           |            |        |             | 453412.45 | 5017710.14 | 6.00   | 0.00 |
|        |    |    |    |           |            |        |             | 453422.76 | 5017691.37 | 6.00   | 0.00 |
|        |    |    |    |           |            |        |             | 453415.36 | 5017687.53 | 6.00   | 0.00 |
|        |    |    |    |           |            |        |             | 453417.21 | 5017683.44 | 6.00   | 0.00 |
|        |    |    |    |           |            |        |             | 453409.15 | 5017679.21 | 6.00   | 0.00 |
|        |    |    |    |           |            |        |             | 453413.38 | 5017671.14 | 6.00   | 0.00 |
|        |    |    |    |           |            |        |             | 453391.04 | 5017658.58 | 6.00   | 0.00 |
|        |    |    |    |           |            |        |             | 453382.58 | 5017672.73 | 6.00   | 0.00 |
|        |    |    |    |           |            |        |             | 453306.04 | 5017629.90 | 6.00   | 0.00 |
|        |    |    |    |           |            |        |             | 453293.21 | 5017652.50 | 6.00   | 0.00 |

3D Reflector

| Name | M. | ID | Type | Attenuation | B | m   | Height |
|------|----|----|------|-------------|---|-----|--------|
|      |    |    |      | dB/100m     | % | 1/m | (m)    |

Geometry Absorption

| Name | M. | ID | Type | Attenuation | B | m   | Height | Coordinates |     |     |        |
|------|----|----|------|-------------|---|-----|--------|-------------|-----|-----|--------|
|      |    |    |      | dB/100m     | % | 1/m | (m)    | x           | y   | z   | Ground |
|      |    |    |      |             |   |     |        | (m)         | (m) | (m) | (m)    |

Ground Absorption

| Name | M. | ID | G   |
|------|----|----|-----|
|      |    |    | 0.0 |
|      |    |    | 0.0 |

Geometry Absorption

