




Stantec Consulting Ltd. 400 - 1331 Clyde Avenue Ottawa ON Tel. 613.722.4420 www.stantec.com

Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that



PROPOSED WATERMAIN PROPOSED VALVE AND VALVE BOX PROPOSED VALVE CHAMBER PROPOSED REDUCER PROPOSED FIRE HYDRANT PROPOSED SANITARY SEWER PROPOSED STORM SEWER PROPOSED CATCHBASIN MANHOLE PROPOSED CATCH BASIN ALL CATCH BASINS TO BE CONNECTED TO INTERNAL PLUMBING AND DRAIN TO EXTERIOR STORM WATER MANAGEMENT TANKS. PROPOSED DITCH INLET CATCHBASIN PROPOSED SUBDRAIN CATCHBASIN EXISTING WATERMAIN EXISTING VALVE AND VALVE BOX EXISTING VALVE CHAMBER EXISTING REDUCER EXISTING FIRE HYDRANT EXISTING SANITARY SEWER EXISTING STORM SEWER EXISTING CATCHBASIN MANHOLE EXISTING CATCHBASIN EXISTING SUBDRAIN CATCHBASIN EXISTING SWALE PROPOSED DEPRESSED CURB LOCATIONS PROPOSED MOUNTABLE/BARRIER CURB LOCATION THERMAL INSULATION ON STORM SEWER WHERE COVER IS LESS THAN 1.5m. THERMAL INSULATION ON WATERMAIN WHERE COVER IS LESS THAN 2.4m AS PER W22.

M RM

· ____ · · · · ___ · · · · ___

NOTES:

UNDERGROUND PARKING RAMP TRENCH DRAINS TO BE CONVEYED THROUGH BUILDING AND OUTLET INTO EXTERNAL UNDERGROUND STORM WATER MANAGEMENT STORAGE TANKS.

WATER METER

REMOTE WATER METER

- ALL SURFACE CATCH BASINS INSTALLED ON TOP OF UNDERGROUND PARKING STRUCTURE TO BE CONVEYED THROUGH BUILDING AND OUTLET INTO EXTERNAL UNDERGROUND STORM WATER MANAGEMENT STORAGE TANKS.
- PROPOSED FIRE HYDRANT TO BE SERVICED THROUGH BUILDINGS INTERNAL PLUMBING.
- ALL CATCHBASINS AND FIRE HYDRANTS INSTALLED ON TOP OF PARKING GARAGE STRUCTURE ARE TO BE INSTALLED BY OTHERS.
- INTERNAL GARAGE DRAINS TO BE CONNECTED TO THE SANITARY SEWER.
- AT THE COMPLETION OF CONSTRUCTION A WATER SYSTEM PRESSURE CHECK IS REQUIRED TO BE COMPLETED TO DETERMINE IF PRESSURE CONTROL DEVICES ARE REQUIRED.

5	REVISED AS PER CITY COMMENTS		SLW	DT	22.07.14
4	REVISED AS PER CITY COMMENTS		SLW	DT	22.03.29
3	REVISED AS PER CITY COMMENTS		SLM	TR	21.09.02
2	ISSUED FOR GEOTECH REVIEW		SLM	DT	21.08.03
1	ISSUED TO CITY FOR SPA		SLW	DT	20.05.22
Revision		Ву	Appd.	YY.MM.DD	
File Name: 160401511-DB		SLW	DT	MJS	19.09.05
		Dwn.	Chkd.	Dsgn.	YY.MM.DD

Permit-Seal

Client/Project

NAUTICAL LANDS GROUP 2962 Carp Road

WELLINGS OF STITTSVILLE PH 2 20 CEDAROW COURT OTTAWA, ON

Title

SITE SERVICING PLAN

