

AtHamlin

ALLISON HAMLIN
MANAGER (A), DEVELOPMENT REVIEW WEST
PLANNING, REAL ESTATE & ECONOMIC DEVELOPMENT
DEPARTMENT, CITY OF OTTAWA

APPROVED
By Allison Hamlin at 3:56 pm, Jul 15, 2022

Statistics

Description	Symbol	Max	Min	Avg/Min	Avg
Drives	+	473.2 lux	5.1 lux	17.5:1	89.4 lux
Front-Walkways	+	297.5 lux	0.1 lux	558.0:1	55.8 lux
Parking Lot	+	145.2 lux	8.0 lux	5.3:1	42.2 lux
Parking Sidewalk	+	149.2 lux	2.8 lux	14.7:1	41.2 lux
Property Line - Front	+	5.0 lux	0.0 lux	N/A	0.4 lux
Property Line - Back	+	3.0 lux	0.0 lux	N/A	0.1 lux

Symbol	Label	Image	Quantity	Manufacturer	Catalog Number	Description	Number Lumens	Light Loss Factor	Wattage	Foot	
A			4	SONNY GARDO	P26-40L-800-NW-G2-4-HS	Puriform Gen2 - Area Medium (225), 80 LEDs, 4000K CCT, TYPE 4-HS OPTIC, 1000mm internal spacing	3	21332	0.85	574.6704	
B			1	SONNY CANADA LTD	P15-P-405-740-BLC	Puriform Area Small 15' Square, 48 LEDs, 4000K CCT, TYPE BLC OPTIC	1	7782	0.85	69	
C			6	Utopia Lighting	W0624 LED PL 700U 4FT 40K	W0624 LED WITH PL PERFORMANCE PACKAGE, 4000K, T0CKL, FORWARD THROW OPTIC	1	12650	0.85	76.21	
C1			1	Utopia Lighting	W0624 LED PL 700U 4FT 40K	W0624 LED WITH PL PERFORMANCE PACKAGE, 4000K, T0CKL, FORWARD THROW OPTIC	1	12650	0.85	76.21	
D			11	PHILIPS LIGHTING - LIGHTSTORE	240CJ20915W06K210	EssiLite	1	1442	0.7	20	
C2			2	Utopia Lighting	W0624 LED PL 700U 4FT 40K	W0624 LED WITH PL PERFORMANCE PACKAGE, 4000K, T0CKL, FORWARD THROW OPTIC	1	22560	0.85	193.51	
C3			1	Utopia Lighting	W0624 LED PL 700U 4FT 40K	W0624 LED WITH PL PERFORMANCE PACKAGE, 4000K, T0CKL, TYPE 2 OPTIC	1	12125	1	76.21	

