



No.	Botanical Name	Common Name	DBH (m)	CRZ (m)	Condition	Remarks	Recomm.
1	Ulmus sp.	Elm	0.15	1.50	F	Leaves mostly fallen	Remove
2	Pinus nigra	Black Pine	0.30	3.00	G		Remove
3	Pinus nigra	Black Pine	0.30	3.00	G		Remove
4	Acer platanoides	Norway Maple	0.30	3.00	G	Black spot	Remove
5	Picea abies	Norway Spruce	0.35	3.50	G		Remove
6	Picea abies	Norway Spruce	0.30	3.00	G		Remove
7	Picea abies	Norway Spruce	0.30	3.00	G		Remove
8	Acer platanoides	Norway Maple	0.25	2.50	F	Prominent burl, black spot	Remove
9	Acer platanoides	Norway Maple	0.35	3.50	G	Black spot	Remove
10	Thuja occidentalis	Eastern White Cedar	0.1 0.15	1.1 1.5	G	Clump, 15m ht	Remove
11	Pinus nigra	Black Pine	0.20	2.00	G		Remove
12	Pinus nigra	Black Pine	0.20	2.00	G		Remove
13	Pinus nigra	Black Pine	0.20	2.00	G		Remove
14	Acer platanoides	Norway Maple	0.45	4.50	G	Black spot	Remove
15	Picea abies	Norway Spruce	0.20	2.00	G		Remove
16	Picea abies	Norway Spruce	0.20	2.00	G		Remove
17	Picea abies	Norway Spruce	0.30	3.00	G		Remove
18	Betula Sp.	Birch	0.45	4.50	G		Remove
19	Pinus nigra	Black Pine	0.20	2.00	G		Remove
20	Pinus nigra	Black Pine	0.25	2.50	G		Remove
21	Pinus nigra	Black Pine	0.25	2.50	G		Remove
22	Picea abies	Norway Spruce	0.25	2.50	G		Remove
23	Picea abies	Norway Spruce	0.20	2.00	G		Remove
24	Picea abies	Norway Spruce	0.20	2.00	G		Remove
25	Picea abies	Norway Spruce	0.20	2.00	G		Remove
26	Picea abies	Norway Spruce	0.20	2.00	G		Remove
27	Acer ginnala	Amur Maple	0.15	1.50	F	Leaning, health unclear - no leaves	PROTECT
28	Acer ginnala	Amur Maple	0.20	2.00	F	Low crotch, health unclear - no leaves	PROTECT
29	Acer negundo	Manitoba Maple	0.20	2.00	F	Not easily desecrable from street	PROTECT
30	Acer negundo	Manitoba Maple	0.20	2.00	F	Not easily desecrable from street	Remove

PLANTING NOTES

- This drawing shall be read in conjunction with all relevant Architectural, Engineering, and related drawings and documents.
- Refer to Engineering Drawings for Grading. Provide drainage as indicated in grading plan. Round all tops and toes of slopes, smoothly. Compact all areas to 95% Standard Proctor Density unless otherwise noted.
- Refer to Architectural Drawings for site layout.
- Refer to Engineering Drawings for site servicing.
- Contractor must contact utility companies for locates prior to excavation or planting.
- It is essential to use the plans and details in conjunction with the specifications and notes.
- Existing trees to be retained shall be protected according to the contract detail and specifications.
- Plant material shall be No. 1 Grade and shall comply with Canadian Standards for Nursery Stock (latest edition) published by the Canadian Nursery Landscape Association.
- Use plant material with strong fibrous root system free of disease, defects or injuries, and structurally sound. Use trees with straight trunks, well and characteristically branched for species. Obtain approval from consultant of plant material at source prior to digging. All trees and shrubs shall be container grown, potted, W/B or B/B, as indicated on Plant List. Bare root planting will only be acceptable for certain species and as approved by the Landscape Architect.
- Plant material substitutions shall not be permitted without the written approval from the consultant, with **48 hours notice**, prior to shipping plant material.
- Plant locations are schematic / approximate only. Contractor shall stake out locations on site for approval by the Landscape Architect prior to installation. The illustrated number of plants shown in the Planting Plan supersedes the estimated number in the Plant List. Contractor to report any discrepancies to the Landscape Architect prior to installation. Contractor will assume full responsibility if the Landscape Architect is not notified.

KEY	QTY	BOTANICAL NAME	COMMON NAME	SIZE	COND.	SPACING
Coniferous Trees						
PBB	8	<i>Picea pungens</i> 'Baby Blue'	Baby Blue Colorado Spruce	175cm Ht	WB	As Shown
PNC	3	<i>Pinus nigra</i> 'Compacta'	Compact Austrian Pine	80cm Tg	WB	As Shown
Deciduous Trees						
CGZ	3	<i>Crataegus crus-galli</i> 'Cruzam'	Crusader Hawthorn	50mm Cal	WB	As Shown
COC	5	<i>Celtis occidentalis</i> 'ChicagoLana'	ChicagoLana Hackberry	50mm Cal	WB	As Shown
SRI	1	<i>Syringa reticulata</i> 'Ivory Silk'	Ivory Silk Japanese Tree Lilac	50mm Cal	WB	As Shown
Deciduous Shrubs						
Hif	18	<i>Hydrangea paniculata</i> 'SMHPLDF'	Little Quick Fire Hydrangea	60cm 2g	PT	As Shown
Ra	18	<i>Rhus aromatica</i>	Fragrant Sumac	60cm 3g	PT	As Shown

PRODUCT NOTES

- Bike Racks to be MBR 300-4-S (4 Rings - Surface Mount) with Galvanized Finish, By Maglin. Install Per Manufacturer's Specifications.

TREE PROTECTION NOTES

The following protection measures must be implemented for retained trees, both on site and on adjacent sites, prior to any tree removal or site works and maintained for the duration of construction on site:

- Under the guidance of a Landscape Architect or Certified Arborist, erect a fence at the critical root zone (CRZ) of trees where the CRZ is established as being 10 centimetres from the trunk of a tree for every centimetre of trunk diameter at breast height. The CRZ is calculated as DBH x 10cm. Refer to the Tree Protection Fence Detail. See plan for fence location.
- When trees to be removed overlap with the CRZ of trees to be preserved: cut roots at the edge of the CRZ and grind down stumps after tree removals, do not pull out stumps. Ensure there is no root pulling or disturbance of the ground within the CRZ.
- If roots must be cut, roots 20mm or larger should be cut at right angles with clean, sharp horticultural tools without tearing, crushing, or pulling. Refer to City of Ottawa Specification S.P. F-8011 Tree Protection, Excavation of Root Zone.
- Hand work only where required within the CRZ, absolutely no machinery permitted.
- Do not place any material or equipment within the CRZ of any tree.
- Do not attach any signs, notices or posters to any tree.
- Do not disturb, raise or lower the existing grade within the CRZ without approval.
- Only tunnel or bore when digging within the CRZ of a tree.
- Do not damage the root system, trunk, or branches of any tree.
- Ensure that exhaust fumes from all equipment are directed away from any tree canopy.

REVISIONS

No.	REVISION	DATE	BY
9	REVISED REAR WORK YARD	AUG 17/22	RGJ

SCALE

1:500

FOR REVIEW ONLY

DESIGN	ME/LR/GJ
CHECKED	RGJ
DRAWN	MEL
CHECKED	RGJ
APPROVED	RGJ

LOCATION

CITY OF OTTAWA
2555 SHEFFIELD ROAD

DRAWING NAME

LANDSCAPE PLAN AND TREE CONSERVATION REPORT

PROJECT No: 119007
REV # 9
DRAWING No: 119007-L

C:\temp\p\p\19007-L.dwg, 11, Aug 17, 2022, 4:23pm, mbaat

D07-12-19-0124