

PROJECT INFORMATION	
ZONING BY-LAW 2008-250	TM (Z72) S444
SITE AREA	2,610.7 sq. m. 28,102 sq. ft.
TM - ZONING REQUIREMENT	9 STOREYS & 31 m.
BUILDING HEIGHT	9 STOREYS & 31 m.
AMENITY AREA - 6m <sup>2</sup> PER UNIT (141 UNITS)	846 sq. m.
FRONT YARD SETBACK	1.4 m.
FRONT YARD SETBACK - ABOVE 15m HL. OR 4th STOREY	+ 2.0 m.
INTERIOR YARD SETBACK - ABUTTING R ZONE	6.0 m.
CORNER YARD SETBACK	3.0 m.
CORNER YARD SETBACK - ABOVE 15m HL.	+ 2.0 m.
REAR YARD SETBACK	7.5 m.
PARKING - PER UNIT (AFTER 12)	0.5
VISITOR PARKING - PER UNIT (AFTER 12)	0.1
BICYCLE PARKING - RESIDENTIAL - PER UNIT	0.5
BICYCLE PARKING - COMMERCIAL	1 PER 250m <sup>2</sup> GFA

PROJECT STATISTICS	
GRADE (GEODETIC ELEVATION)	67.30 m. aasl
BUILDING HEIGHT	31.0 m.
AMENITY LEVEL - BUILDING HEIGHT	5.0 m.
FRONT YARD SETBACK - LOWER	1.5 m.
FRONT YARD SETBACK - ABOVE 15m HL. OR 4th STOREY	3.5 m.
INTERIOR YARD SETBACK - ABUTTING TM	0.0 m.
INTERIOR YARD SETBACK - ABUTTING R3	6.0 m.
CORNER YARD SETBACK - LOWER	3.0 m.
CORNER YARD SETBACK - ABOVE 15m HL. OR 4th STOREY	5.0 m.
REAR YARD SETBACK - LOWER	7.5 m.
REAR YARD SETBACK - UPPER	16.6 m.
STANDARD PARKING SPACE	2.6m X 5.2m
SMALL CAR PARKING SPACE	2.4m X 4.6m
DRIVEWAY & AISLE	6.7m
BICYCLE AISLE	1.1m

GROSS BUILDING FLOOR AREA	
(OTTAWA ZONING DEFINITION)	000 sq. m.
LUG PARKING LEVELS	000 sq. m.
GROUND FLOOR	769.0 sq. m. 8,277 sq. ft.
MEZZANINE	371.9 sq. m. 4,003 sq. ft.
2nd - 4th FLOOR	3 x 1,301.4 sq. m. 3 x 14,008 sq. ft. 42,024 sq. ft.
5th to 7th FLOOR	3 x 992.5 sq. m. 3 x 10,683 sq. ft. 32,049 sq. ft.
8th FLOOR	610.0 sq. m. 6,647 sq. ft.
9th FLOOR	621.9 sq. m. 6,847 sq. ft.
AMENITY / MECHANICAL FLOOR	0.0 sq. m. 0.0 sq. ft.
TOTAL AREA ABOVE GRADE	9,666.3 sq. m. 104,047 sq. ft.

UNIT STATISTICS	
1 BEDROOM UNIT	21
1 BEDROOM + UNIT	20
2 BEDROOM UNIT	25
2 BEDROOM + UNIT	18
3 BEDROOM UNIT	4
3 BEDROOM + UNIT	4
TOTAL	141
COMMERCIAL RETAIL UNIT	484.4 sq. m. 5,214 sq. ft.

REQUIRED	
RESIDENCE	-0.5 PER UNIT AFTER 12 UNITS 65
VISITOR	-0.1 PER UNIT AFTER 12 UNITS 13
COMMERCIAL	- UNDER 500m <sup>2</sup> NON REQUIRED 0
TOTAL	78
MAXIMUM PARKING AS PER TABLE 103 = 1.75 PER UNIT	247

PROVIDED	
RESIDENCE	-0.58 PER UNIT (141 UNITS) 136
VISITOR	-0.1 PER UNIT (141 UNITS) 13
COMMERCIAL	- UNDER 500m <sup>2</sup> NON REQUIRED 0
TOTAL	149
STANDARD PARKING SPACE	2.6m X 5.2m
SMALL CAR PARKING SPACE	2.4m X 4.6m

BICYCLE PARKING	
REQUIRED	-0.5 PER UNIT (141 UNITS) 71
COMMERCIAL RETAIL	-1.0 PER 250m <sup>2</sup> OF G.F.A. 2
TOTAL	73

AMENITY SPACE	
AT GRADE EXTERIOR COMMUNAL	200.0 sq. m.
AT GRADE EXTERIOR PRIVATE YARDS	200.0 sq. m.
2nd FLOOR - PRIVATE EXTERIOR	25.0 sq. m.
5th FLOOR - PRIVATE EXTERIOR	290.0 sq. m.
8th FLOOR - COMMUNAL EXTERIOR	135.0 sq. m.
AMENITY LEVEL - COMMUNAL EXTERIOR	405.0 sq. m.
AMENITY LEVEL - COMMUNAL EXTERIOR	290.0 sq. m.
TOTAL	1,545.0 sq. m.
TOTAL COMMUNAL	1,030.0 sq. m.
REQUIRED - 6.0M <sup>2</sup> PER UNIT (141) =	846 sq. m.
REQUIRED COMMUNAL @ 95% =	423 sq. m.

LOT COVERAGE	
PAVED SURFACE	439.2 sq. m. 16.8%
BUILDING FOOTPRINT	1,402.3 sq. m. 53.7%
LANDSCAPE OPEN SPACE	769.2 sq. m. 29.5%
TOTAL	2,610.7 sq. m. 100.0%

REFUGE REQUIREMENT (141 UNITS)	
GARBAGE	-0.11 PER UNIT 16 YARDS
RECYCLING GMP	-0.019 PER UNIT 3 YARDS
RECYCLING FIBER	-0.038 PER UNIT 5 YARDS
COMPOST	-240L PER 50 UNITS 3

IT IS THE RESPONSIBILITY OF THE APPROPRIATE CONTRACTOR TO CHECK AND VERIFY ALL DIMENSIONS ON SITE AND TO REPORT ALL ERRORS AND/OR OMISSIONS TO THE ARCHITECT.

ALL CONTRACTORS MUST COMPLY WITH ALL PERTINENT CODES AND BY-LAWS.

THIS DRAWING MAY NOT BE USED FOR CONSTRUCTION UNTIL SIGNED BY THE ARCHITECT.

DO NOT SCALE DRAWINGS.

COPYRIGHT RESERVED.

**NOTATION SYMBOLS:**

① INDICATES DRAWING NOTES, LISTED ON EACH SHEET.

Ⓜ INDICATES ASSEMBLY TYPE; REFER TO TYPICAL ASSEMBLIES SCHEDULE.

Ⓜ INDICATES WINDOW TYPE; REFER TO WINDOW ELEVATIONS AND DETAILS ON A100 SERIES.

Ⓜ INDICATES DOOR TYPE; REFER TO DOOR SCHEDULE AND DETAILS ON A100 SERIES.

①②③④⑤⑥⑦⑧⑨⑩⑪⑫⑬⑭⑮⑯⑰⑱⑲⑳㉑㉒㉓㉔㉕㉖㉗㉘㉙㉚㉛㉜㉝㉞㉟


①②③④⑤⑥⑦⑧⑨⑩⑪⑫⑬⑭⑮⑯⑰⑱⑲⑳㉑㉒㉓㉔㉕㉖㉗㉘㉙㉚㉛㉜㉝㉞㉟

①②③④⑤⑥⑦⑧⑨⑩⑪⑫⑬⑭⑮⑯⑰⑱⑲⑳㉑㉒㉓㉔㉕㉖㉗㉘㉙㉚㉛㉜㉝㉞㉟

①②③④⑤⑥⑦⑧⑨⑩⑪⑫⑬⑭⑮⑯⑰⑱⑲⑳㉑㉒㉓㉔㉕㉖㉗㉘㉙㉚㉛㉜㉝㉞㉟

**1 SITE PLAN**  
SCALE 1:150

APPROVED  
By Andrew McCreight at 1:19 pm, Mar 02, 2023



**ANDREW MCCREIGHT**  
MANAGER (A), DEVELOPMENT REVIEW CENTRAL  
PLANNING, REAL ESTATE & ECONOMIC DEVELOPMENT  
DEPARTMENT, CITY OF OTTAWA

DRAWING NOTES	
①	PROPERTY LINE
②	BUILDING SETBACKS AT GRADE - SEE SCHEDULE S444
③	CORNER SITE TRIANGLE, TO BE CONFIRMED
④	HARD SURFACE PAVING, SEE LANDSCAPE PLAN
⑤	CONTINUOUS DEPRESSED SIDEWALK THROUGH DRIVE
⑥	CONCRETE SIDEWALK TO BE REPLACED WITH NEW BARRIER CURB / SIDEWALK
⑦	SOFT LANDSCAPING, SEE LANDSCAPE PLAN
⑧	6.0m WIDE GARAGE ENTRY RAMP WITH TRENCH DRAIN
⑨	OUTLINE OF BELOW GRADE PARKING GARAGE
⑩	OUTLINE OF UPPER FLOORS
⑪	OUTLINE OF AMENITY / MECHANICAL LEVEL
⑫	OUTLINE OF PRIVATE TERRACE ABOVE
⑬	RETAINING WALL WITH GUARD RAIL AS REQUIRED
⑭	PRIVATE WALKWAY TO GROUND FLOOR UNIT
⑮	EXISTING TREE TO REMAIN, PROTECT AS REQUIRED
⑯	EXISTING FIRE HYDRANT
⑰	VENTILATION GRILL (INTAKE / EXHAUST)
⑱	SIAMASE CONNECTION
⑲	ENTRANCE DRIVEWAY WITH BARRIER CURB
⑳	EXISTING TREE TO BE REMOVED
㉑	EXISTING BUILDING TO BE REMOVED
㉒	EXISTING CITY SIDEWALK
㉓	PRIVACY SCREEN
㉔	PROPOSED SERVICES
㉕	GAS EQUIPMENT LOCATION
㉖	EXISTING STREET LIGHT / TRAFFIC POLE
㉗	SEAT WALL, SEE LANDSCAPE FOR DETAILS
㉘	BICYCLE PARKING SPACE WITH RACK
㉙	REPLACE EXISTING CITY PAVERS AS SHOWN ON LANDSCAPE PLAN
㉚	CITY OWNED BOLLARD BICYCLE RACKS

SITE PLAN SYMBOLS	
	EXISTING CITY BOULEVARD PAVERS
	NEW BOULEVARD PAVERS ON PRIVATE PROPERTY
	CONCRETE / ASPHALT DRIVEWAY SURFACE
	CONCRETE SIDEWALK / WALK
	UNIT PAVERS AT PRIVATE TERRACE
	SOFT LANDSCAPING
	PROPERTY LINE
	BUILDING SETBACK LINE
	1.2m HT. METAL PICKET FENCE
	BIKE RACK
	ENTRANCE / EXIT DOOR
	FIRE HYDRANT
	VEHICULAR DIRECTION
	EXISTING TREES
	SIAMASE CONNECTION
	SITE LIGHTING

①	SHORT TERM REFUGE CONTAINER STAGING AREA
②	150mm WIDE BARRIER CURB, DEPRESSED AT ENTRY
③	RE-INSTATE EXISTING BOARD FENCE
④	150mm WIDE BARRIER CURB AT EDGE OF DRIVING SURFACE
⑤	REMOVED EXISTING HYDRO TRANSFORMER
⑥	CATCH BASIN / MANHOLE SEE CIVIL FOR DETAILS
⑦	GROUND FLOOR PRIVATE TERRACES WITH PRIVACY SCREEN
⑧	PROPOSED TREES, SEE LANDSCAPE FOR DETAILS
⑨	EXISTING CITY PAVERS TO REMAIN

SURVEYOR	
<b>Annis O'Sullivan Vollebek Ltd.</b> 14 Concourse Gate, Suite 500, Nepean, Ontario K2E 7S6 Tel: (613) 727-0850 Fax: (613) 727-1079 E-Mail: AndyS@aovltd.com	<b>PROPERTY OWNER</b> <b>Starwood Group Inc.</b> 188 Eglinton Avenue East Suite 800 Toronto, Ontario, M4P 2X7 Tel: (416) 482-8222 Fax: (416) 482-8224

GEOTECHNICAL ENGINEER	
<b>Paterson Group</b> 154 Colonnade Road South Ottawa, Ontario, K2E 7J5 Tel: (613) 226-7381 Fax: (613) 226-6344 Email: carlosd@patersongroup.ca	<b>URBAN PLANNER</b> <b>FoTenn Consultants Inc.</b> 396 Cooper Street, Suite 300, Ottawa, ON Canada, K2P 2H7 Tel.: (613) 730-5709 Fax: (613) 730-1136 E-Mail: mcelligott@fotenn.com

WIND / NOISE ENGINEER	
<b>Gradient Wind Engineering</b> 127 Walgreen Road, Ottawa, ON, Canada K0A 1L0 Tel: (613) 836-0934 Cell: (613) 226-5273 Email: joshua.foster@gradientwind.com	<b>CIVIL ENGINEER</b> <b>CIMA Engineering Ltd.</b> 110-240 Catherine Street, Ottawa, ON K2P 2G8 Tel: (613) 860-2462 Fax: (613) 860-1870 Email: Tim.Kennedy@cima.ca

LEGAL DESCRIPTION	
<b>PART 1</b> Plan of LOTS 7, 9, 11 AND 13 PART OF LOTS 3 AND 4 REGISTERED PLAN 114 CITY OF OTTAWA Surveyed by Annis, O'Sullivan, Vollebek Ltd.	<b>LANDSCAPE ARCHITECT</b> <b>Gino J. Aiello Landscape Architect</b> 110 Didsbury Road Unit 9, Ottawa, Ontario K2E 0C2 Tel: (613) 852-1343 Cell: (613) Email: gino@glala.com

ARCHITECT	
<b>Roderick Lahey Architects</b> 56 Beech Street, Ottawa, Ontario K1S 3J6 1.613.724.9932 f.613.724.1209 www.rodericklahey.ca	<b>TRANSPORTATION ENGINEER</b> <b>CIMA Engineering Ltd.</b> 110-240 Catherine Street, Ottawa, ON K2P 2G8 Tel: (613) 860-2462 Fax: (613) 860-1870 Email: Tim.Kennedy@cima.ca