

Functional Servicing and Stormwater Management Report



Project: 50 The Driveway, Ottawa
Client: 276405 Ontario Inc.

PREPARED BY:



Dimitra Frykali, P.Eng., M.A.Sc.
Project Designer

REVIEWED BY:



Sarra Karavasili, P.E., M.A.Sc.
Assistant Project Manager

AUTHORIZED FOR ISSUE BY:

LITHOS GROUP INC.



Nick Moutzouris, P.Eng., M.A.Sc.
Principal

Issues and Revisions Registry

Identification	Date	Description of issued and/or revision
FSR/SWM Report	January 16 th , 2023	Issued for Site Plan Application
FSR/SWM Report	March 27 th , 2023	Issued for Site Plan Application

Statement of Conditions

This Report / Study (the “Work”) has been prepared at the request of, and for the exclusive use of, the Owner / Client, the City of Ottawa and its affiliates (the “Intended User”). No one other than the Intended User has the right to use and rely on the Work without first obtaining the written authorization of Lithos Group Inc. and its Owner. Lithos Group Inc. expressly excludes liability to any party except the intended User for any use of, and/or reliance upon, the work.

Neither possession of the Work, nor a copy of it, carries the right of publication. All copyright in the Work is reserved to Lithos Group Inc. The Work shall not be disclosed, produced or reproduced, quoted from, or referred to, in whole or in part, or published in any manner, without the express written consent of Lithos Group Inc. and the Owner.

Executive Summary

Lithos Group Inc. (Lithos) was retained by 276405 Ontario Inc. (the “Owner”) to prepare a Functional Servicing and Stormwater Management Report in support of a Site Plan Application, for a proposed residential-use development located in the area referred to as the “Golden Triangle”, at 50 The Driveway (K2P 1E2), in the City of Ottawa (the “City”). The following summarizes our conclusions:

Storm Drainage

The post-development 100-year storm flow has been designed to match the five (5)-year pre-development storm flow. In order to achieve the target flows and meet the City’s Regulations, quantity controls will be utilized and 98.00 m³ of storage tank will be required as well as 54.10 m³ will be utilized in underground chambers. The stormwater management (SWM) system will be designed to provide enhanced level (Level 1) protection as specified by the Ministry of the Environment, Conservation and Parks (MECP). Water quality control can be provided for a minimum total suspended solids (TSS) removal of 80%.

Sanitary Sewers

The proposed development will connect to the existing 300mm combined sewer on Queen Elizabeth Driveway ROW, through a 200mm diameter sanitary sewer lateral connection, which increases to a 250mm diameter with a minimum grade of 2.00%, downstream of the sanitary control manhole at the property line. The additional net discharge flow from the proposed development, is anticipated at approximately 1.80 L/s. According to the information provided by the City, the existing infrastructure has the capacity to support the additional sanitary flow, from the proposed development.

Water Supply

Water supply for the site will be from the existing 150mm diameter watermain on the Lewis Street. It is anticipated that a total design flow of 118.15 L/s will be required to support the proposed development. Based on the boundary conditions received from the City, it is revealed that the existing water infrastructure can support the proposed development.

Site Grading

The proposed grades will improve the existing drainage conditions to meet the City’s/Regional requirements. Grades will be maintained along the property line wherever feasible. Existing drainage patterns on adjacent properties will not be altered and stormwater runoff from the subject development will not affect the adjacent properties.

Table of Contents

1.0	Introduction	4
2.0	Site Description	4
3.0	Site Proposal	4
4.0	Terms of Reference and Methodology	5
4.1.	Terms of Reference	5
4.2.	Methodology: Stormwater Drainage and Management.....	5
4.3.	Methodology: Sanitary Discharge	5
4.4.	Methodology: Water Usage	6
5.0	Stormwater Management and Drainage	7
5.1.	Existing Conditions	7
5.2.	Proposed Conditions	8
5.2.1.1	Quantity Controls.....	9
5.2.1.2	Underground Storage Tank.....	9
5.2.1.3	Underground Infiltration Chambers	10
5.2.1.4	Major Overland Flow Route and Emergency Overland Flow Route	10
5.2.1.5	Quality Controls	10
5.2.1.5	Proposed Storm Connection	10
6.0	Combined Drainage System	11
6.1.	Existing Combined Drainage System	11
6.2.	Existing Flows	11
6.3.	Proposed Flows	11
6.4.	Proposed Sanitary Connections	11
6.5.	Conclusions	11
7.0	Water Supply System	12
7.1.	Existing System.....	12
7.2.	Proposed Water Supply Requirements.....	12
7.3.	Watermain Analysis Results.....	13
7.4.	Proposed Watermain Connection	14
8.0	Erosion and Sediment Control	14
9.0	Site Grading	15
9.1.	Existing Grades	15
9.2.	Proposed Grades	15

10.0 Conclusions and Recommendations..... 15

LIST OF FIGURES

Figure 1 - Location Plan.
Figure 2 -Aerial Plan.

LIST OF TABLES

Table 4-1 – Sanitary Design Criteria 6
Table 4-2 – Water Usage..... 7
Table 5-1 – Target Input Parameters 7
Table 5-2 – Target Peak Flows 8
Table 5-3 – Post-development Input Parameters..... 8
Table 5-4 – Post-development Quantity Control as Per City Requirements 9
Table 5-5– Site TSS Removal 10
Table 7-1 – Fire Flow Input Parameters..... 12
Table 7-2 – Water Demand..... 12
Table 7-3– Boundary Conditions Provided by the City 13
Table 7-4- Watermain Analysis Results – Domestic Flow 13
Table 7-5 – Fire Hydrants adjacent to the property 14

Appendices

- Appendix A – Site Photographs
- Appendix B – Background Information
- Appendix C – Storm Analysis
- Appendix D – Sanitary Data Analysis
- Appendix E – Water Data Analysis

1.0 Introduction

Lithos Group Inc. (Lithos) was retained by Main and Main (the “Owner”) to prepare a Functional Servicing and Stormwater Management Report in support of a Site Plan Application for a proposed residential-use development located at 50 The Driveway in the City of Ottawa (the “City”).

The purpose of this report is to provide site-specific information for the City’s review with respect to infrastructure required to support the proposed development. More specifically, the report will present details on sanitary discharge, water supply and of the storm drainage pattern.

The following documents were available for our review:

- Plan and Profiles of:
 - Waverley Street, drawing No. 3331 Sheet 11 of 20, dated January, 2003;
 - Lewis Street from Robert Street to N.C.C Driveway, drawing No. 911-P, dated June, 1978;
 - Gilmour Street, drawing No. 012 Sheet 12 of 35, dated March 2018.
- Sewer and Water Maps of the existing combined sewer network upstream and downstream of the subject site (for reference purposes only);
- Site Plan & Statistics prepared by Hobin Architecture Inc., dated January 05, 2023;
- Topographical Survey prepared by Annis, O’Sullivan, Vollebakk Ltd., dated July 01, 2021; and,
- Geotechnical Investigation prepared by Paterson Group dated July 16, 2021.

2.0 Site Description

The existing site is approximately 0.296 hectares and is currently comprised of an existing building, an elevated tower and outdoor parking area. The site is located within the urban limits of the City of Ottawa (K1L 6N1), in the area referred to as the “Golden Triangle”. Refer to **Figures 1** and **2** following this report and site photographs in **Appendix A**.

3.0 Site Proposal

The proposed development will be a 9-storey residential-use building and it will be serviced by two (2) underground parking levels. The proposed development will be comprised of 77 residential units. The total development will include approximately 8,886.92 m² of Gross Floor Area (GFA). Please refer to **Appendix B** for site plan and building statistics.

4.0 Terms of Reference and Methodology

4.1. Terms of Reference

The following references and technical guidelines were consulted in the present study:

- City of Ottawa Servicing Study Guidelines, online edition,
- City of Ottawa Sewer Design Guidelines, (2012),
- City of Ottawa Design Guidelines – Water Distribution, (2010),
- Technical Bulletin ISTB-2018-2;
- Ministry of Environment, Conservation and Parks (MECP) Guidelines for the Design of Water Systems (2008)
- MECP Guidelines for the Design of Sanitary Sewage Systems (2008)
- MECP Stormwater Planning and Design Manual (2003)
- Fire Underwriters Survey (FUS) (2020)
- Ontario Building Code (2010)

4.2. Methodology: Stormwater Drainage and Management

This report provides a detailed Stormwater Management (SWM) review of the pre-development and post-development conditions and comments on opportunities to reduce peak flows, as per the City of Ottawa guidelines.

The stormwater management criteria for this development are based on the City of Ottawa Sewer Design Guidelines, as well as the Ministry of Environment, Conservation and Parks (MECP) 2003 Stormwater Management Planning and Design Manual (SWMPD). The following design criteria will be reviewed:

- Post-development peak flow for the 100-year storm event from the site should be controlled to the 5-year target flow. A 20-minute time of concentration and a 10 min inlet time derived from City of Ottawa IDF curves, were considered for connection to a dedicated storm sewer. Please refer to the detailed calculations found in [Appendix B](#), for further details;
- For connection to a dedicated storm sewer, when the imperviousness of the existing property is greater than 50%, the maximum value of the runoff coefficient, “c”, used in calculating the pre-development peak runoff rate is limited to 0.40;
- A safe overland flow will be provided for all major flows in excess of the 100-year storm event.

4.3. Methodology: Sanitary Discharge

The sanitary sewage discharge from the site will be determined using sanitary sewer design sheets that incorporate the land use and building statistics as supplied by the design team. The calculated values provide peak sanitary flow discharge that considers infiltration.

The estimated sanitary discharge flows from the proposed site will be calculated based on the criteria shown **Table 4-1** below. (Sections 4 and 6 of the City of Ottawa Sewer Design Guidelines).

Table 4-1 – Sanitary Design Criteria

Design Parameter	Value
Residential Units (1-Bedroom)	1.4 people/unit
Residential Units (2-Bedroom)	2.1 people/unit
Residential Units (3-Bedroom)	3.1 people/unit
Average Daily Residential Flow	280 L/person/day
Residential Peak Factor	$PF = 1 + (14/(4+(P/1000)^{1/2}))$
Commercial Floor Space	50000 L/ha/day
Commercial Peaking Factor	1.5 if commercial contribution >20%, otherwise 1.0
Infiltration and Inflow Allowance	0.28 L/s/ha
Sanitary sewers are to be sized employing the Manning's Equation	$Q = \frac{1}{n} AR^{2/3} S^{1/2}$
Minimum Manning's 'n'	0.013
Minimum Depth of Cover	1.5 m from crown of sewer to grade
Minimum Full Flowing Velocity	0.6 m/s
Maximum Full Flowing Velocity	3.0 m/s

4.4. Methodology: Water Usage

The fire flow requirements were estimated using the method prescribed by the Fire Underwriters Survey (FUS) 2020. This method is based on the floor area of the building to be protected, the type and combustibility of the structural frame and the separation distances with adjoining building units.

Section 4.3.22 of the City Design guidelines for water distribution provides guidance for determining the method for estimating Fire Demand. As indicated, the requirements for levels of fire protection on private property are covered in the Ontario Building Code. Section 7.2.11 of the OBC addresses the installation of water service pipes and fire service mains. Part 3 of the OBC outlines the requirement for Fire Protection, Occupant Safety, and Accessibility; and subsection A-3.2.5.7 provides the provisions for firefighting.

Based on trained personnel responding to the emergency and water supply being delivered through a municipal main, the required minimum provision for water supply flow rates shall not be less than 2,700L/min or greater than 9,000L/min (OBC Section A.3.2.5.7, Table 2). The City of Ottawa was contacted in June 2021 to obtain boundary conditions based on an estimated water demand.

The domestic water usage was calculated based on the City of Ottawa Guidelines – Water Distribution outlined in **Table 4-2** that follows.

Table 4-2 – Water Usage

Design Parameter	Value
Average Residential Day Demand	350 L/person/day
Maximum Residential Day Demand	2.5 x Average Day Demand
Maximum Residential Hour Demand	2.2 x Max Day Demand
Average Commercial Day Demand	2.5 L/m ² /d
Maximum Commercial Day Demand	1.5 x Average Day Demand
Maximum Commercial Hour Demand	1.8 x Max Day Demand
Minimum Depth of Cover	2.4 m from top of watermain to finished grade
During Peak Hour Demand desired operating pressure is within	350kPa and 480kPa
Minimum pressure during normal operating conditions (average day to maximum hour demand)	275kPa
During normal operating conditions, pressure must not exceed	552kPa
Minimum pressure during fire flow plus maximum day demand	140kPa

5.0 Stormwater Management and Drainage

5.1. Existing Conditions

The existing site is currently comprised of an existing building, an elevated tower and outdoor parking space.

According to available records there is an on-site catchbasin (CB) in the parking area near the east end of the parking area. This catchbasin appears to be connected to the 1800 mm diameter combined sewer on Lewis Street.

Moreover, the existing site is primarily covered by impermeable surfaces; thus, there is no significant infiltration onsite. Although the existing run-off composite coefficient is estimated at 0.90, the City of Ottawa Guidelines require the target flow calculations to be based on a run-off coefficient of 0.4. **Table 5-1** shows the pre-development input parameters, as illustrated on the drainage area plan in **Figure DAP-1** in **Appendix C**.

Table 5-1 – Target Input Parameters

Catchment	Drainage Area (ha)	Actual "C"	Design "C"	Tc (min.)
A1- Pre	0.296	0.90	0.40	20
External Area	0.071	0.49	0.40	20

Peak flows calculated for the existing conditions are shown in **Table 5-2** below. Detailed calculations are in **Appendix C**.

Table 5-2 – Target Peak Flows

Catchment	Peak Flow Rational Method (L/s)	
	5-year	100-year
A1 Pre	23.1	39.5
External Area	5.5	9.5

As shown on **Table 5-2** above, post-development flows towards the City’s infrastructure will need to be controlled to the target flow of 23.1 L/s.

5.2. Proposed Conditions

In order to meet the City’s Stormwater Management criteria, the development flow rate is to be controlled to the five (5)-year target flow, as established in **Section 5.1**. The site will consist of the following three (3) internal and one (1) external drainage areas:

1. A1 Post – Storm runoff from the Rooftops/Terraces/Walkways will be controlled in the underground storage tank, located into P1 level;
2. A2 Post – Uncontrolled storm runoff conveyed towards the adjacent right of ways;
3. A3 Post – Area towards the catch basin will be controlled in infiltration chambers;
4. Ext.1 – Storm Runoff from External Area that will be controlled in infiltration chambers.

The post-development drainage areas and runoff coefficients are indicated in **Figure DAP-2**, located in **Appendix C** and summarized in **Table 5-3** below.

Table 5-3 – Post-development Input Parameters

Drainage Area	Drainage Area (ha)	Drainage Area Atot (ha)	“C”	Tc (min.)
A1 Post (rooftops/terrace/walkways controlled in tank)	0.226	0.251	1.00*	10
A2 Post (Uncontrolled Area – towards Lewis Street)	0.025		0.54*	10
A3 Post (Area towards the catch basin controlled in chambers)	0.045	0.116	0.62*	10
External Area- (Area towards the catch basin controlled in chambers)	0.071		0.61*	10

* “C” value for the 100 year storm event is increased by 25%, with a maximum of 1.00, as per City's Sewer Design Guidelines.

The external drainage area and A3 Post will be captured by catch basin #1 (CB1) which is to retain any storm runoff from its tributary area into an underground infiltration gallery and avoid discharging it into the municipal infrastructure for events up to 100 years.

5.2.1.1 Quantity Controls

Using the City’s intensity-duration-frequency (IDF) data, modified rational method calculations were undertaken to determine the maximum storage required during each storm event. Results for the 5, and 100-year storm events are provided in **Table 5-4**. The detailed post-development quantity control calculations are provided in **Appendix C**.

Table 5-4 – Post-development Quantity Control as Per City Requirements

Storm Event	Target Controlled Release Rate (L/s)	Uncontrolled Flow (L/s)	Required Storage Tank Volume (m ³)	Total Controlled Release Rate of the Tank (L/s)	Total Site Release Rate (L/s)
5-year	23.1	3.5	45.0	10.9	14.4
100-year		6.7	98.0	16.6	22.7

As shown in **Table 5-4**, in order to control post-development flows to the 5-year pre-development conditions, a target flow of 23.1 L/s is to be satisfied. The required on-site storage is accommodated by the use of one (1) underground storage tank, located at P1 level. **Table 5-4**, illustrates the minimum required storage to be retained, which is 89.0 m³, for the 100-year storm event.

The stormwater flow released from the rooftops and the terraces (**Drainage Area A1 Post**) will be gravity driven into the underground storage tank, at P1 Level. Please refer to engineering drawing **Site Servicing Plan (“SS-01”**, submitted separately) for details.

5.2.1.2 Underground Storage Tank

An underground storage tank is proposed to meet the quantity control requirements, set forth by the City’s WWFMG Guidelines. Controlled stormwater flows from the rooftops and terraces (**Drainage Area A1 Post**) will be gravity driven into the proposed underground main storage tank located at P1 level.

The proposed underground storage tank will have an active storage depth of 1.40 m above the inlet of the outlet pipe, accounting for a quantity control maximum storage of 98.0 m³, during the hundred year storm event. Stormwater from the underground storage tank will outlet through a **80mm diameter orifice plate** with a maximum release rate of 16.0 L/s and it will be gravity driven to the existing 300mm diameter combined sewer along Queen Elizabeth Driveway ROW.

The proposed storage tank will have a total footprint area of 70.0 m². Refer to **Figure 3**, included in **Appendix C**, for the minimum tank design requirements. Additional details of the tank design will also be provided by the mechanical engineer.

In summary, a maximum control stormwater release rate from the main storage tank of 16.0 L/s, along with the uncontrolled release rate of 6.7 L/s (**Drainage Area A2 Post**), results to a post-development total release rate of 22.7 L/s, for the 100-year event.

Consequently, the proposed SWM plan retains enough runoff volume, to reduce the post-development peak flows for each storm event to the extent possible and approach the required target flow.

Underground Infiltration Chambers

Stormwater from the site and external will ultimately be driven into the underground storage chambers before being infiltrated.

The underground chambers will be located at the north east corner of the property (refer to Site Servicing Plan **SS-01**, submitted separately). The underground chambers will have a minimum storage depth of 1.29 m and an active storage component of 57.45 m³ to meet the 100 year storage requirement. In order to meet the required volume of 54.10 m³, it is proposed to use 136 blocks of Greenstorm-ST-B Chambers. Please refer to **Appendix B** for more details.

The bottom of the storage facility will be at 63.80 masl and there will be 1.00 m clearance from the existing 'high' groundwater level to the bottom of the chambers, as required by MOE. In addition, the proposed chambers will have more than 5.0 m at horizontal distance from the proposed buildings' footings according to the OBC requirements.

5.2.1.3 Major Overland Flow Route and Emergency Overland Flow Route

Under existing conditions, overland flow from Queen Elizabeth Driveway enters the site and exits through the adjacent properties to the east, reaching Waverley Street. Under post-development conditions, the drainage pattern is being maintained without causing any flooding to the proposed development. All accesses to the building are above the flood limit and the maximum ponding achieved during flooding is estimated at 20 cm as per the proposed grading and the correspondence email, found in **Appendix B**.

5.2.1.4 Quality Controls

For MECP Enhanced Level protection, the removal of 80% total suspended solids (TSS) is required. Stormwater discharged from the proposed development's rooftop area is considered "clean" and will be driven into the underground storage tank. The detailed quality control calculations can be found in **Appendix C**. A summary of the site quality control is included in below.

Table 5-5– Site TSS Removal

Drainage Area	Drainage Area (ha)	% Area of Controlled Site	Effective TSS Removal	Additional Quality Control Required
A1, A3, EXT.1	0.342	100%	80%	Inherent
Total	0.342	100%		

5.2.1.5 Proposed Storm Connection

The proposed development will connect to the existing 300 mm diameter combined sewer along Queen Elizabeth Driveway ROW, via a 150mm diameter storm sewer service connection, with a minimum grade of 2.00% (or equivalent pipe design). The engineering drawing SS-01 (submitted separately), indicates the stormwater service connection.

6.0 Combined Drainage System

6.1. Existing Combined Drainage System

The existing site is currently comprised of an existing building, an elevated tower and outdoor parking space. According to available records, there are two (2) combined sewers abutting the subject property. More specifically:

- A 300mm diameter combined sewer located within the Queen Elizabeth Driveway ROW. This combined sewer outlets to the 1800 mm diameter combined sewer noted below.
- A 1800mm diameter trunk combined sewer located within Lewis Street ROW (flowing north). This combined sewer eventually discharges into the Somerset trunk sewer, which in turn outlets into the Rideau River Collector (RRC).

6.2. Existing Flows

The sanitary flow generated by the proposed development at 50 The Driveway was compared to the existing flow in order to quantify the net increase in the combined sewer network abutting the subject site.

Using the design criteria outlined in [Section 4.3](#) and existing site information, the sanitary discharge flow from the existing property towards Lewis Street is estimated at 0.17 L/s.

6.3. Proposed Flows

According to the proposed development statistics, as well as the design criteria outlined in [Section 4.3](#), the new building will discharge 1.97 L/s (1.89 L/s of sanitary flow and 0.083 L/s of infiltration) into the City's Infrastructure.

The additional flow will be considered within the sanitary discharge rate; therefore, there is an increase in sanitary flow of approximately 1.80 L/s. For detailed calculations, refer to the sanitary sewer design sheet in [Appendix D](#).

6.4. Proposed Sanitary Connections

The proposed development will connect to the existing 300mm diameter combined sewer on Queen Elizabeth Driveway ROW through a 200 mm diameter sanitary sewer connection, which increases to a 250mm with a minimum grade of 2.00% downstream of the sanitary control manhole at the property line. According to the coordination that took place with the City of Ottawa, a lateral connection with bends is acceptable, in order to avoid a connection into the NCC property. Please refer to correspondence email included in [Appendix B](#) as well as to engineering drawing "SS-01" (submitted separately) for details.

6.5. Conclusions

After taking into consideration all the above, we provided the required calculations to the City, in order to review how the additional flow from the proposed development will affect the municipal networks downstream. According to the information provided, the combined sewer infrastructure along Queen Elizabeth Driveway ROW has adequate capacity to accommodate the additional flows from the proposed development and, thus, they can support it. Refer to [Appendix B](#) for email correspondence with the City. For detailed calculations refer to the sanitary sewer design sheet in [Appendix D](#).

7.0 Water Supply System

7.1. Existing System

The subject property lies within the City of Ottawa 1W pressure zone. The existing watermain system consists of a 150 mm diameter watermain on the Lewis Street.

7.2. Proposed Water Supply Requirements

The estimated water consumption was calculated based on the occupancy rates shown on **Table 4-2**, according to the City’s watermain design criteria.

It is anticipated that an average domestic water consumption of approximately 0.59 L/s (50,976 L/day), a maximum daily consumption of 1.48 L/s (127,872 L/day) and a peak hourly demand of 3.25 L/s (11,700L/hr) will be required.

The fire flow requirements we estimated using the method prescribed by the Fire Underwriters Survey (FUS) be undertaken to assess the minimum requirement for fire suppression. The fire flow calculations is normally conducted for the largest storey, by area, and for the two immediately adjacent storeys.

As a result, to the above-mentioned method, we have selected the total area of Level 2 and the immediately adjoining storeys, which are Levels 1 and 3.

Table 7-1 illustrates the input parameters used for the FUS calculations. According to our calculations, a minimum fire suppression flow of approximately 116.67 L/s (1,849 USGPM) will be required. Detailed calculations can be found in **Appendix E**.

Table 7-1 – Fire Flow Input Parameters

Parameter	Frame used for Building	Combustibility of Contents	Presence of Sprinklers	Separation Distance			
				North	East	South	West
Value according to FUS options	Non-Combustible Construction	Limited Combustible Construction	Yes	30.1m to 45m	10.1m to 20m	10.1m to 20m	>45m
Surcharge/reduction from base flow	0.8	15%	30%	5%	11%	11%	0%

In summary, the required design flow is the sum of ‘the minimum fire suppression flow’ and ‘maximum daily demand’ ($116.67 + 1.48 = 118.15$ L/s, 1,873 USGPM).

Table 7-2 summarizes the anticipated water demand on the City of Ottawa Guidelines – Water Distribution.

Table 7-2 – Water Demand

Design Parameter	Anticipated Demand (L/min)
Average Day Demand	$0.59 * 60 = 35.4$
Max Day + Fire Flow	$(116.67 + 1.48) * 60 = 7,089$
Max Hour Demand	$3.25 * 60 = 195.0$

7.3. Watermain Analysis Results

Upon completion of the detailed calculations in order to determine the anticipated domestic water consumption and the required minimum fire flow for the proposed development, the calculation results were provided to the City of Ottawa. As a result, the above noted values were used to generate the municipal watermain network boundary conditions.

Table 7-3 below summarizes the boundary conditions provided by the City of Ottawa for the existing municipal watermain network along Lewis and Queen Elizabeth Driveway.

Table 7-3– Boundary Conditions Provided by the City

Municipal Watermain Boundary Condition	152mm on Lewis Street	305 mm on Queen Elizabeth Driveway
Minimum HGL	106.4	106.4
Maximum HGL	115.4	115.3
Max Day + Fire Flow (250 L/s) (m)	104.6	105.3

Table 7-4 below summarizes the calculated water demands for the proposed development under the various operating conditions and compares the anticipated operating pressures at the watermains to the normal operating pressures outlined in the City of Ottawa Design Guidelines. Furthermore, the pressure losses from the building’s water service to the Siamese connection have been calculated, in order to define the available flow at this point.

Table 7-4- Watermain Analysis Results – Domestic Flow

Watermain Connection	Design Parameter	Anticipated Demand (L/s)	Approximate Design Operating Pressures (psi) / Relative Head (m)	Normal Municipal Operating Pressures (psi)
Lewis Street	Average Demand	0.59	87 psi (66.3m)	50-70 psi
	Peak Hour Demand	3.25	54.0 psi (37.7m)	40-70 psi
	Max Day + Fire Flow	118.15	52.0 psi (36.6m)	20 psi (min)

According to **Table 7-4** and the information provided by the City of Ottawa, the water pressure for the average demand and the peak hour demand, result in values that achieve the criteria of the City's Guidelines, as indicated in **Table 7-4**.

Furthermore, capacity assessment of the adjacent fire hydrants was also investigated. Following our review, there are two (2) public fire hydrants, within 150m radius away from our site. More specifically, the distance of the subject fire hydrants (characterized as blue-colored, class “AA”) is less than 75m from the subject site, following an unobstructed path in the Right of Way to the building. According to Table 18.5.4.3 in the Bulletin ISTB-2018-02, there is a total rated capacity of 11,356 L/min, which translates into 189.27 L/s. Considering the fact that this flow is greater than the proposed development’s fire flow demand of 116.67L/s, the above noted fire hydrants will have sufficient capacity to support the subject future development. Please refer to **Table 7-5** for further details.

Table 7-5 – Fire Hydrants adjacent to the property

ID	Class	Distance (m)	Flow (L/min)
368031H056	Class AA	36.30 < 75	5678.00
368031H224	Class AA	63.50 < 75	5678.00

7.4. Proposed Watermain Connection

The proposed development will be serviced by two (2) 150 mm diameter waterlines separated by an isolation valve. The proposed water laterals will connect to the 150mm diameter existing watermain on Lewis Street. Refer to engineering drawings “SS-01” (submitted separately) for details.

8.0 Erosion and Sediment Control

Soil erosion occurs naturally and is a function of soil type, climate topography. The extent of erosion losses is exaggerated during construction where vegetation has been removed and the top layer of soil becomes agitated.

Prior to topsoil stripping, earthworks or underground construction, erosion and sediment controls will be implemented and will be maintained throughout construction.

Silt fence will be installed around the perimeter of the site and will be cleaned and maintained throughout construction.

Catch basins will have filter fabric installed under the grate during construction to protect from silt entering the storm sewer system.

A mud mat will be installed at the construction access in order to prevent mud tracking onto adjacent roads.

Erosion and sediment controls must be in place during construction. The following recommendations to the contractor will be included in contract documents.

- Limit extend of exposed soils at any given time.
- Re-vegetate exposed areas as soon as possible.
- Minimize the area to be cleared and grubbed.
- Protect exposed slopes with plastic or synthetic mulches.
- Install silt fence to prevent sediment from entering existing ditches.
- No refueling or cleaning of equipment near existing watercourses.
- Provide sediment traps and basins during dewatering.
- Install filter cloth between catch basins and frames.
- Plan construction at proper time to avoid flooding.

Establish material stockpiles away from watercourses, so that barriers and filters may be installed.

The contractor will, at every rainfall, complete inspections and guarantee proper performance. The inspection is to include:

- Verification that water is not following under silt barriers.
- Clean and change filter cloth at catch basins.

9.0 Site Grading

9.1. Existing Grades

The existing site is approximately 0.296 hectares and is currently comprised of an existing building, an elevated tower and by an adjacent outdoor parking area. The site drains into the existing stormwater system inside the property and the drainage pattern is being maintained as previously existed.

9.2. Proposed Grades

The proposed grades will improve the existing drainage conditions to meet the City's/Regional requirements. Grades will be maintained along the property line wherever feasible. Existing drainage patterns on adjacent properties will not be altered and stormwater runoff from the subject development will not affect the adjacent properties.

10.0 Conclusions and Recommendations

Based on our investigation, we conclude the following:

Storm Drainage


The post-development 100-year storm flow has been designed to match the five (5)-year pre-development storm flow. In order to achieve the target flows and meet the City's Regulations, quantity controls will be utilized and 98.00 m³ of storage tank will be required as well as 54.10 m³ will be utilized in underground chambers. The stormwater management (SWM) system will be designed to provide enhanced level (Level 1) protection as specified by the Ministry of the Environment, Conservation and Parks (MECP). Water quality control can be provided for a minimum total suspended solids (TSS) removal of 80%.

Sanitary Sewers

The proposed development will connect to the existing 300mm combined sewer on Queen Elizabeth Driveway ROW, through a 200mm diameter sanitary sewer lateral connection, which increases to a 250mm diameter with a minimum grade of 2.00%, downstream of the sanitary control manhole at the property line. The additional net discharge flow from the proposed development, is anticipated at approximately 1.80 L/s. According to the information provided by the City, the existing infrastructure has the capacity to support the additional sanitary flow, from the proposed development.

Water Supply

Water supply for the site will be from the existing 150mm diameter watermain on the Lewis Street. It is anticipated that a total design flow of 118.15 L/s will be required to support the proposed development. Based on the boundary conditions received from the City, it is revealed that the existing water infrastructure can support the proposed development.



LOCATION PLAN
RESIDENTIAL USE DEVELOPMENT
50 THE DRIVEWAY
OTTAWA, ONTARIO

DATE:	MARCH 2023	PROJECT No:	UD22-093
SCALE:	N.T.S.	FIGURE No:	FIG 1

150 Bermondsey Road, Toronto, Ontario M4A 1Y1



AERIAL PLAN
RESIDENTIAL USE DEVELOPMENT
50 THE DRIVEWAY
OTTAWA, ONTARIO

DATE:	MARCH 2023	PROJECT No:	UD22-093
SCALE:	N.T.S.	FIGURE No:	FIG 2

150 Bermondsey Road, Toronto, Ontario M4A 1Y1

Appendix A

Site Photographs




North-West Corner of property along Driveway Road



South-West Corner of property along Driveway Road

Appendix B

Background Information



"ALLOWANCE FOR ROAD"
REGISTERED PLAN 3365

PIN 0425 - MURS
PHE 5 PLAN 49 - (MURS)

JOB NUMBER
TOP OF SPALL
Dec-03-11

TOPOGRAPHICAL SKETCH OF
50 THE DRIVEWAY
CITY OF OTTAWA
Prepared by Anns, O'Sullivan, Vollebek Ltd.
TOPOGRAPHICAL INFORMATION ASSESSMENT YEAR JANUARY 2021

Scale 1:150

Metric:
DISTANCES SHOWN ON THIS PLAN ARE IN METRES AND
CAN BE CONVERTED TO FEET BY DIVIDING BY 3.048

Caution:
This is NOT a plan of survey and should not be used
except for the purpose indicated in the title block.

SITE AREA = 2068 m²
BUILDING FOOTPRINT AREA = 806 m²

July 7, 2021


Notas & Legend

Symbol	Description	Feature
○	Spot Elevation	Spot Elevation
○	Water Table	Water Table
○	Maintenance Hole (Storm Sewer)	Maintenance Hole (Storm Sewer)
○	Maintenance Hole (Sanitary)	Maintenance Hole (Sanitary)
○	Maintenance Hole (Underfloor)	Maintenance Hole (Underfloor)
○	Overhead Wires	Overhead Wires
○	Utility Pole	Utility Pole
○	Corner	Corner
○	Center Mark	Center Mark
○	Top of Gate	Top of Gate
○	Gas Meter	Gas Meter
○	Red Trenching Wire	Red Trenching Wire
○	Soilmark	Soilmark
○	Bound Line	Bound Line
○	Concrete Retaining Wall	Concrete Retaining Wall
○	Wooden Retaining Wall	Wooden Retaining Wall
○	Brick Retaining Wall	Brick Retaining Wall
○	Diaphragm	Diaphragm
○	Location of Elevation	Location of Elevation
○	Top of Wall / Core Elevation	Top of Wall / Core Elevation
○	Centerline	Centerline
○	Property Line	Property Line
○	Flag Pole	Flag Pole
○	Underground Gas	Underground Gas
○	Gas Meter (as shown by symbol)	Gas Meter (as shown by symbol)

ELEVATION NOTES
1. Elevations shown are generic, and are referred to the CGCS2011 datum unless
indicated otherwise. All elevations are in meters unless otherwise stated.
2. It is the responsibility of the user to verify the information for use in the field. The
user of this plan is responsible for the accuracy of the information and the user
agrees with the information shown on this drawing.

UTILITY NOTES
1. This drawing cannot be accepted as an engineering drawing until all the utility lines
are in place and the user is responsible for the accuracy of the information and the user
agrees with the information shown on this drawing.
2. Utility lines shown are generic.
3. A field location of underground utilities by the user is required. The user is
responsible for the accuracy of the information and the user agrees with the information
shown on this drawing.

THE DRIVEWAY



9 STOREY BUILDING:
 TOTAL GROSS AREA: 123,495 sq.ft.
 TOTAL NET RES AREA: 100,488 sq.ft.
 TOTAL UNITS : 77
 PARKING STALLS : 97
 BIKE STALLS : 77
 STORAGE LOCKERS : 77
 FFE : 68.9

A1.00 SITE PLAN
 A1.00 1 : 150

PROJECT TEAM

- ARCHITECT**
 HOBIN ARCHITECTURE
 Barry Hobin
 bhobin@hobinarc.com
- David Anderson
 danderson@hobinarc.com
 413.238.7200 x122
- OWNERSHIP**
 CANADIAN NURSES ASSOCIATION
- PLANNING**
 J.L.RICHARDS
 Jim F. Chaddler
 fchaddler@richards.ca
- Eric Fohan
 efohan@richards.ca
- CIVIL**
 UTHOS GROUP
 Sara Karavasi
 sara@uthosgroup.ca
- LANDSCAPE ARCHITECT**
 CSW
 Lisa MacDonald
 macdonald@csw.ca
- Sarah Mcintosh
 mcintosh@csw.ca
- TRANSPORTATION**
 PARSONS
 Mark Baker
 Mark.Baker@parsons.com
- Matthew Manife
 Matthew.Manife@parsons.com
- ENVIRONMENTAL**
 GRADIENT WIND
 Joshua Foster
 joshua.foster@gradientwind.com

5	230105	RE-ISSUED FOR SPC
4	220429	ISSUED FOR SPC
3	220119	RE-ISSUED FOR REZONING
2	211208	RE-ISSUED FOR REZONING
1	210716	ISSUED FOR REZONING
no.	date	revision

It is the responsibility of the appropriate contractor to check and verify all dimensions on site and report all errors and/or omissions to the architect.

All contractors must comply with all pertinent codes and by-laws.

Do not scale drawings.

This drawing may not be used for construction until signed.

Copyright reserved.

BUILDING AREA SUMMARY

BUILDING AREA:	17,986	SQ.FT.
NUMBER OF STOREYS ABOVE GRADE:	9	STOREYS
TOTAL GROSS AREA:	123,495	SQ.FT.
TOTAL NET/LEASEABLE AREA:	100,488	SQ.FT.
TOTAL GFA (AS PER CITY DEF.):	95,668	SQ.FT.
UNIT SUMMARY		
TOTAL UNITS:	77	
	QTY.	RATIO %
SMALL SUITES (≤ 1,400 SQ.FT.)		
15 1 BED	7	9%
8 1 BED + DEN	8	10%
MEDIUM SUITES (1,400 - 1,800 SQ.FT.)		
34 2 BED	13	17%
12 2 BEDROOM + DEN	13	17%
LARGE SUITES (≥ 1,800 SQ.FT.)		
28 2 BEDROOM + DEN	16	21%
12 3 BEDROOM + DEN	12	16%
AVERAGE UNIT SIZE:	1,305	SQ.FT.


ZONING NOTES:

CURRENT ZONING:	R4UC(478)
LOT AREA :	2,958 m ²
LOT WIDTH(Lewis st.) :	44.19 m
LOT DEPTH. :	75.2 m
DEVELOPMENT STATS	
LOT OF AREA 'A'	MIN 1150 m ²
% OF LANDSCAPED AREA	30%
TOTAL UNITS	77
SETBACK ALONG FRONT YARD (LEWIS ST.)	3 m
SETBACK ALONG SIDE YARD (FACING CANAL)	1.2 m
SETBACK ALONG SIDE YARD (FACING TOWNS)	7.5 m
SETBACK ALONG REAR YARD	7.5 m
MAXIMUM HEIGHT	14.5 m
NUMBER OF STOREYS	9
BUILDING GFA	11,473 m ²
ZONING GFA (as per city zoning def.)	8,886 m ²

PARKING REQUIREMENTS

1. VEHICLE PARKING	REQUIRED PARKING	PROVIDED PARKING
RESIDENTIAL PARKING 77 UNITS (- 12UNITS) (X 0.5)	0.5 / UNIT 33 SPACES	1.0 / UNIT 77 SPACES
VISITOR PARKING 88 UNITS (- 12UNITS) (X 0.1)	0.1 / UNITS 7 SPACES	0.26 / UNITS 20 SPACES
TOTAL PARKING	40 SPACES	97 SPACES
PARKING DISTRIBUTION		
LEVEL P2		46 SPACES
LEVEL P1		51 SPACES
TOTAL		97 SPACES
2. BICYCLE PARKING		
REQUIRED BICYCLE PARKING SPACES RESIDENTIAL (NEW)	0.5 SPACE/UNIT - 39 SPACES REQUIRED FOR 77 UNITS	
PROVIDED BICYCLE PARKING SPACES		77 TOTAL BIKE STALLS (UNDERGROUND)
3. AMENITY REQUIREMENTS		
REQUIRED AMENITY SPACE 6 m ² REQUIRED PER UNIT 77 UNITS X 6 SQ.M. = 462 SQ.M. TOTAL AMENITY REQUIRED REQUIRED AMENITY SPACE TO BE COMMON - 231 SQ.M. PROVIDED COMMON AMENITY SPACE - 290 SQ.M.		
PROVIDED AMENITY SPACE BREAKDOWN: -GROUND FLOOR COMMON AMENITY - 290 m ² (240m ² INTERIOR + 50m ² EXTERIOR) -PRIVATE BALCONY & TERRACE AMENITY - 2,541 m ² TOTAL AMENITY SPACE PROVIDED 2,831 m ²		

LOCATION PLAN



LEGEND

PROPOSED FIRE ROUTE	EDGE OF SIDEWALK	P.T.D. PARKING TICKET DISPENSER
PROPOSED BUILDING	PROPERTY LINE	P.D.S. EXISTING PAY & DISPLAY
BUILDING TO BE DEMOLISHED	SETBACK	B.S. EXISTING TRANSIT STOP
H.M.H. EXISTING TRAFFIC MAN HOLE	PROPOSED DEPRESSED CURB DETAIL TO CITY OF OTTAWA STANDARD SC-7	C.B. EXISTING CATCH BASIN
T.M.H. EXISTING TRAFFIC MAN HOLE	EXTENT OF PRIVATELY OWNED PUBLIC SPACE	P.C.B. PROPOSED CATCH BASIN
M.H. EXISTING MAN HOLE	CURB TO BE REBUILT	AS SIGNAGE FOR ACCESSIBLE PARKING SPACE
T.S.P. EXISTING TRAFFIC LIGHT	ROLL CURB	FRS SIGNAGE FOR FIRE ROUTE ACCESS
E.H. EXISTING FIRE HYDRANT	EXISTING UTILITY POLE	EXISTING SIGN
C.C.C. CURB DETAIL TO CITY OF OTTAWA STANDARDS	F.D.C. FIRE DEPARTMENT CONNECTION	EXISTING BOLLARD
B.P. BIKE PARKING SPACE		EXISTING LIGHT POLE
		NEW LIGHT POLE
		PROPOSED WALL MOUNTED LIGHT
		SL. EXISTING STREET LIGHTING BOX
		T.B. EXISTING TRAFFIC SIGNAL BOX

NOTE:
 ALL EXISTING SITE INFORMATION AS PER SITE SURVEY PLAN DATED JUNE 30TH, 2021 AND PREPARED BY ANNIS, O'SULLIVAN, VOLLEBECK LTD.

Hobin Architecture Incorporated
 68 Pamela Street
 Ottawa, Ontario
 Canada K1S 8K7
 T: 613-238-7200
 F: 613-238-2005
 E: info@hobinarc.com
 hobinarc.com

PROJECT LOCATION:
50 THE DRIVEWAY

DRAWING TITLE:
SITE PLAN

DRAWN BY: DA DATE: 2023-01-25 SCALE: 1:150

PROJECT: 2051



DRAWING NO.: **A1-00**

REVISION NO.



WAVERLEY STREET

QUEEN ELIZABETH DRIVEWAY



Stations	Top of Watermain	Existing Surface	Sewer Type & Diameter	Sewer Inverts Existing & Proposed
830.00	66.94	66.94	375mm COMB	64.00
830.50	66.94	66.94	375mm COMB	64.00
831.00	66.94	66.94	375mm COMB	64.00
831.50	66.94	66.94	375mm COMB	64.00
832.00	66.94	66.94	375mm COMB	64.00
832.50	66.94	66.94	375mm COMB	64.00
833.00	66.94	66.94	375mm COMB	64.00
833.50	66.94	66.94	375mm COMB	64.00
834.00	66.94	66.94	375mm COMB	64.00
834.50	66.94	66.94	375mm COMB	64.00
835.00	66.94	66.94	375mm COMB	64.00
835.50	66.94	66.94	375mm COMB	64.00
836.00	66.94	66.94	375mm COMB	64.00
836.50	66.94	66.94	375mm COMB	64.00
837.00	66.94	66.94	375mm COMB	64.00
837.50	66.94	66.94	375mm COMB	64.00
838.00	66.94	66.94	375mm COMB	64.00
838.50	66.94	66.94	375mm COMB	64.00
839.00	66.94	66.94	375mm COMB	64.00
839.50	66.94	66.94	375mm COMB	64.00
840.00	66.94	66.94	375mm COMB	64.00
840.50	66.94	66.94	375mm COMB	64.00
841.00	66.94	66.94	375mm COMB	64.00
841.50	66.94	66.94	375mm COMB	64.00
842.00	66.94	66.94	375mm COMB	64.00
842.50	66.94	66.94	375mm COMB	64.00
843.00	66.94	66.94	375mm COMB	64.00
843.50	66.94	66.94	375mm COMB	64.00
844.00	66.94	66.94	375mm COMB	64.00
844.50	66.94	66.94	375mm COMB	64.00
845.00	66.94	66.94	375mm COMB	64.00
845.50	66.94	66.94	375mm COMB	64.00
846.00	66.94	66.94	375mm COMB	64.00
846.50	66.94	66.94	375mm COMB	64.00
847.00	66.94	66.94	375mm COMB	64.00
847.50	66.94	66.94	375mm COMB	64.00
848.00	66.94	66.94	375mm COMB	64.00
848.50	66.94	66.94	375mm COMB	64.00
849.00	66.94	66.94	375mm COMB	64.00
849.50	66.94	66.94	375mm COMB	64.00
850.00	66.94	66.94	375mm COMB	64.00

Revisions:

No.	Date	Description	Drawn By	Approved By

Design:

Drawn By	Date	Checked By	Date
ZAFAR I. RANA			
J. FRANCE, J. DUFFY			
S. SAUVE, A. SCAFFER			

Construction Services Manager:

Wayne Bennett P.Eng.

Final Measurements:

Construction Type	Inspector
SEWER, WATER, ROAD	A. SCAFFER
Work Commenced	Project Manager
AUGUST 2001	Z. RANA, J. BRADLEY, N. STOLT
Work Completed	Field Book #
OCT 2002	
Contractor	Date
ORAVEX INC	JUN 2003
Drawn By	Checked By
A. SCAFFER	Z. SAUVE, JUN 2003

- Tender Notes:
1. Soil information shown is not guaranteed and contractors are advised to collect additional soil information as deemed necessary.
 2. Soil information taken from: FOMDEX, Ref. # 00-504-4
 3. This plan supercedes in whole or in part plan # F5a
 4. While illustrations and utilities shown are taken from the best available information, they cannot be guaranteed.
 5. The actual rock line was recorded during construction of the existing.
 6. Boreholes taken prior to construction.
 7. See typical cross sections for road structure material depths.
 8. All Water information and locations cannot be guaranteed. Please contact the Region of Ottawa-Carleton, Environmental Section.
 9. Ministry of Environment Approval # Sewer Water

Legal Survey Notes:

Boundary information shown hereon has been compiled and calculated from Terrestrial data and not based on an actual survey. Distances shown to survey monuments are for reference purposes only, survey monuments may not define property boundaries.

© Copyright Toronto Land Information Services Inc. 1997-97. All rights reserved. This is not an admission of publication.

THIS IS NOT A PLAN OF SURVEY

This plan was compiled from data and documents recorded in the Land Registry System and has been prepared for property marking purposes only.

© Copyright the Registrar, Region of Ottawa-Carleton, 1970-97. All rights reserved. This notice is not an admission of publication.

© Copyright Toronto Land Information Services Inc. 1997-97. All rights reserved. This is not an admission of publication.

Ottawa
Transportation, Utilities and Public Works
Infrastructure Services Branch
110 LAURIER AVENUE WEST, OTTAWA, ONTARIO, K1P 1J1

Rosemarie Leclair
Director/Manager


Richard Hewitt, P.Eng.
Branch Director

WAVERLEY STREET
STA. 830.00 TO QUEEN ELIZABETH DRIVEWAY

Contract No.	Survey Book	Scale (See notes)	Plan No.
OIC3331	3331	HR: 1:250 VERT: 1:50	3331

Sheet 11 of 20

LEWIS STREET



**Regional Municipality
of
Ottawa-Carleton
Works Department**

F.E. AYERS
Works Commissioner

W.L. KEAY
Director Pollution Control

Engineer in Charge of
Design & Construction

L.L. Larson
Date

6-6-78



Project officer
Kenneth Slack Date 5/6/78

Drawn by:
S. BARRETT Date APRIL 1978

Approved by: _____ Date _____

Notes


THIS PLAN DRAWN FROM THE FOLLOWING
SURVEY BOOK 570, SURVEYOR H. PICKARD
CENTRAL REGISTRY E-13 SHEET 20, E-14 SHEET 25



Revisions
1 30/10/78 AS BUILT FROM BOOK 570
& FIELD PRINT. S.P.B., T.J.S. *[Signature]*

Scales
HORIZON 0 10 20 30 40 FEET
VERTICAL 0 3 6 9 12 FEET

Project Title
**6" W.M. IN
LEWIS STREET
FROM ROBERT ST.
TO
N.C.C. DRIVEWAY**

Drawing No. **911-P** Sheet _____





GILMOUR STREET TRUNK SEWER ROAD, SEWER AND WATERMAIN CONSTRUCTION

GILMOUR STREET PLAN AND PROFILE STA. 3+590 TO STA. 3+720

Contract No. **ISD15-5013** Dwg. No. **012**
 Sheet 12 of 35

Asset No. _____
 Asset Group _____

Des. PDR Chk'd PDR
 Dwn. MF, MB PDR
 Utility Circ. No. Index No. _____
 Const. Inspector _____

Scale: HORIZONTAL 1:250
 0m 2.5 5 10
 VERTICAL 1:50

J.R. J.L. Richards
 ENGINEERS ARCHITECTS PLANNERS
 www.jrichards.ca

General Manager: **W. NEWELL P. ENG.**
 Infrastructure Services Department
 Project Manager: **T. BLASIOLI P. ENG.**

NOTE: The location of utilities is approximate only, the exact location should be determined by consulting the municipal authorities and utility companies concerned. The contractor shall prove the location of utilities and shall be responsible for adequate protection from damage.

No.	Description	By	Date (dd/mm/yy)
1	ISSUED FOR UTILITY CIRCULATION	PDR	22/06/15
2	ISSUED FOR 66% PRELIMINARY DESIGN	PDR	17/07/15
3	ISSUED FOR PRELIMINARY DESIGN CIRCULATION	PDR	07/08/15
4	ISSUED FOR MOE APPROVAL	PDR	14/08/15
5	ISSUED FOR 33% DETAILED DESIGN SUBMISSION	CB	15/09/15
6	ISSUED FOR 66% DETAILED DESIGN SUBMISSION	CB	14/10/15
7	ISSUED FOR TENDER	CB	03/12/15
8	ISSUED FOR ADDENDUM NO. 2	PDR	11/01/16
9	ISSUED FOR CONSTRUCTION	CB	01/02/16
10	ISSUED FOR SCM NO. 8	CB	16/03/16
11	'AS BUILT' INFORMATION ADDED	CB	30/03/18

'AS BUILT' NOTE:
 "ALL NUMERICAL VALUES THAT ARE NOT STROKED OUT AND REPLACED IN ITALICS ON 'AS BUILT' DRAWINGS ARE CONSIDERED TO BE DESIGN VALUES ONLY AND NOT MEASURED IN THE FIELD"

This drawing comprises the original design drawing updated to reflect information supplied by others as to the final 'AS CONSTRUCTED' conditions. The information supplied by others has not been verified and, as such, this drawing is not warranted by J.L. Richards and Associates Limited for completeness or accuracy.
 Date of Issue: MARCH 30, 2018

NO.	STRUCTURE TYPE / SIZE
TLM 111	OPSD 701.013 - 2400mm Ø C/W SAFETY LANDING (OPSD 404.020)
TLM 112	5.0 m - CAST IN PLACE BAFFLE DROP CHAMBER

1. MAINTENANCE HOLES TO BE BENCHED PER OPSD 701.021
2. MAINTENANCE HOLE COVERS TO S24 UNLESS SHOWN OTHERWISE


NO.	STRUCTURE TYPE / SIZE
COM 214	OPSD 701.010 - 1200mm Ø
COM 215	OPSD 701.011 - 1500mm Ø
COM 220	OPSD 701.010 - 1200mm Ø
AV01	OPSD 701.031 - 1524mm x 1829mm C/W 300mm SUMP AND GALVANIZED STEEL HONEYCOMB GRATING PER OPSD 403.010 (TYPE B)

1. MAINTENANCE HOLES TO BE BENCHED PER OPSD 701.021
2. MAINTENANCE HOLE COVERS TO S24.1 UNLESS SHOWN OTHERWISE

NO.	STATION	OFFSET	COVER	STRUCTURE	T/GRATE	LENGTH	INVERT	ICD
CB 25	3+602.50	4.0 R	S23	OPSD 705.010	68,927	7.4	67,527	V-O
CB 26	3+623.50	4.0 R	S23	OPSD 705.010	68,844	7.2	67,444	C-O
CB 27	3+623.50	4.0 L	S23	OPSD 705.010	68,917	0.8	67,517	C-O

1. OFFSET MEASURED FROM ROAD ALIGNMENT CONTROL TO CENTER OF CATCH BASIN.
2. GRATE ELEVATIONS ARE GIVEN AT EDGE OF PAVEMENT.
3. ALL CATCH BASIN LEADS TO BE 200mmØ PVC DR-35 UNLESS SHOWN OTHERWISE FOR STANDARD CONCRETE CATCH BASINS (OPSD 705.010).
4. ALL CATCH BASINS TO INCLUDE 600mm SUMP.
5. LENGTH MEASURED FROM CENTERLINE OF STRUCTURE TO CENTERLINE OF SEWER.
6. INLET CONTROL DEVICE (ICD)
 V = VORTEX TYPE ICD
 C = FRAME TYPE ICD WITH CIRCULAR ORIFICE
 O = ODOUR CONTROL INLET
 REFER TO CONTRACT SPECIFICATIONS FOR ICD DETAILS
7. ALL CATCH BASINS ARE TO BE CONNECTED TO THE LOCAL COMBINED SEWER.

STATION	COMBINED INVERT	TLM COMBINED INVERT	TOP OF WATERMAIN	PROFILE CONTROL
3+590	65.237	66.447	66.458	69.001
3+591.62	65.500	66.447	66.447	69.001
3+600	65.500	66.447	66.447	69.001
3+609.00	66.000	66.447	66.447	69.001
3+610	66.000	66.447	66.447	69.001
3+620.5	66.000	66.447	66.447	69.001
3+623.50	66.000	66.447	66.447	69.001
3+630	66.000	66.447	66.447	69.001
3+640	66.000	66.447	66.447	69.001
3+650	66.000	66.447	66.447	69.001
+652.7	66.000	66.447	66.447	69.001
3+656.65	66.000	66.447	66.447	69.001
3+657.92	66.000	66.447	66.447	69.001
3+660	66.000	66.447	66.447	69.001
3+663.70	66.000	66.447	66.447	69.001
+667.8	66.000	66.447	66.447	69.001
3+670	66.000	66.447	66.447	69.001
3+680	66.000	66.447	66.447	69.001
3+690	66.000	66.447	66.447	69.001
3+700	66.000	66.447	66.447	69.001
3+703.61	66.000	66.447	66.447	69.001
3+710	66.000	66.447	66.447	69.001
3+720	66.000	66.447	66.447	69.001



REVISIONS / RÉVISIONS	DATE	BY
REDRAWN FROM VOIDED UTILITY PLAN E-13-20	JUNE 2009	MH
INCREASE GAS PRESSURE (REF: 2009) GASLINE ADDED ON SALISBURY ST.	MAR. 2010	KJ
ALISTREAM - ALLIUM (DEC 2001) CONDUIT ADDED TO LEWIS STREET	AUG 2011	DC
HYDRO/EL/ENR/ENG/PLANNING/CITY SEWER WATER TRAFFIC, IS COMPILED/DIGITIZED FROM UTILITY/CITY DATA	FEB 2015	DC
ALLIUM - LEWIS STREET (DEC 2001) CONDUIT ADDED TO LEWIS STREET	JUN 2021	JH

LEGEND	
Water Valve, Valve Chamber, Fire Hydrant	⊙ ⊕ ⊖
Sewer Manhole, Catch Basin Manhole	⊙ ⊕ ⊖
Catch Basin / Drainage, Wing Wall, Head Wall	⊙ ⊕ ⊖
Pole, Pole w/ Light, Decorative, Lawn Light	⊙ ⊕ ⊖
Power Supply, Panel, Pedestal, Transformer, Tower, Regulator	⊙ ⊕ ⊖
Amp, Hand Hole, Vault, Gas Valve	⊙ ⊕ ⊖
OC Transpo: Bus Shelter-No Power, Energized, Isolated	⊙ ⊕ ⊖
Streetscape: Planter Box, Grate Square, Eng. Soil	⊙ ⊕ ⊖
Traffic Connect Box / Disconnect Box, SL Disconnect	⊙ ⊕ ⊖
R.L. Hand Hole, R.L. Camera	⊙ ⊕ ⊖
Scada: Hand Hole, Monitoring Panel	⊙ ⊕ ⊖
Reducer	⊙ ⊕ ⊖
Pipe, Duct, Conduit, Lateral	⊙ ⊕ ⊖
Culvert	⊙ ⊕ ⊖
Abandoned	⊙ ⊕ ⊖
Capped	⊙ ⊕ ⊖
Buried Cable	⊙ ⊕ ⊖
Property Line	⊙ ⊕ ⊖
Install Year	(2015)

TELECOM GLOSSARY			
A.....Allstream	P.....Primus		
AT.....Atis	P2P.....Canadian P2P Fibre		
B.....Bell	R.....Rogers		
BH.....Beech Hill	S.....Sprint		
F.....Fibre Noir	SL.....Street Lighting		
G.....Gloabal	T.....Traffic		
GT.....Group Telecom	TO.....Telcom Ottawa		
H.....Hydro Ottawa	TU.....Telus		
HI.....Hydro One	V.....Videotron		
L / L3.....Level 3	Z.....Zayo		


GLOSSARY - OTHER			
DD.....Dept. of Defence	PED.....Pedestal (owner unknown)		
MH.....Manhole (owner unknown)	PW.....Public Works		
OOC.....OC Transpo	UP.....Utility Pole (owner unknown)		
SCD.....Scada			

CAUTION/ATTENTION
 Although utility locations are established using the best available information, they cannot be guaranteed.
 Property lines were compiled from plans and documents recorded in the Land Registry System and are for indexing purposes only.
 Bien que l'emplacement des services publics soient établis en utilisant la meilleure information disponible, ils ne peuvent pas être garantis.
 Des lignes de propriété ont été compilées en utilisant des plans et des documents enregistrés dans le système de cadastre et sont pour l'indexation seulement.

Ottawa
 Right of Way, Heritage, and Urban Design Services /
 Gestion des emprises, du patrimoine, et du design urbain
 Planning, Infrastructure and Economic Development Department /
 Direction générale de la planification, de l'infrastructure et du développement économique
 100 Concession Street, 6th Floor East / 6ème Étage Est, Ottawa, ON K2G 6J8

OTTAWA UTILITY COORDINATING COMMITTEE
 CENTRAL REGISTRY
 COMITÉ DE COORDINATION DES SERVICES PUBLICS D'OTTAWA
 ENREGISTREMENT CENTRAL

UTILITY COORDINATING COMMITTEE
 UCC
 Ottawa
 CCSP
 COMITÉ DE COORDINATION DES SERVICES PUBLICS



REVISIONS / RÉVISIONS	DATE	BY
REDRAWN FROM VOIDED UTILITY PLANS E-14-16, 20, 29	JUNE 2009	KJ
HYDROBELLEFROGERS, CITY SEWER, WATER, TRAFFIC, SL COMPILED/DIGITIZED FROM UTILITY/CITY DATA	MAY 2010	KJ
HYDRO 1 - 15KV HIGH VOLTAGE/20KV HYDRO1 - HV OIL FILLED LINE ON CATHERINE	DEC 2016	KJ

LEGEND	
Water Valve, Valve Chamber, Fire Hydrant	
Sewer Manhole, Catch Basin Manhole	
Catch Basin / Drainage, Wing Wall, Head Wall	
Pole, Pole w/ light, Decorative, Lawn Light	
Power Supply, Panel, Pedestal, Transformer, Tower, Regulator	
Amp, Hand Hole, Vault, Gas Valve	
OC Transpo: Bus Shelter-No Power, Energized, Isolated	
Streetscape: Planter Box, Grate Square, Eng. Soil	
Traffic: Connect Box / Disconnect Box, SL, Disconnect	
R.L. Hand Hole, R.L. Camera	
Scada: Hand Hole, Monitoring Panel	
Reducer	
Pipe, Duct, Conduit, Lateral	
Culvert	
Abandoned	
Capped	
Buried Cable	
Property Line	
Install Year	(2015)

TELECOM GLOSSARY	
A.....Allstream	P.....Primus
AT.....Atia	P2P.....Canadian P2P Fibre
B.....Bell	R.....Rogers
BH.....Borch Hill	S.....Sprint
F.....Fibre Noir	SL.....Street Lighting
G.....Gloability	T.....Traffic
GT.....Group Telecom	TO.....Telecom Ottawa
H.....Hydro Ottawa	TU.....Telus
HI.....Hydro One	V.....Videotron
L / L3.....Level3	Z.....Zayo

GLOSSARY - OTHER	
DD.....Dept. of Defence	PED.....Pedestal (owner unknown)
MH.....Manhole (owner unknown)	PW.....Public Works
OIOC.....OC Transpo	UP.....Utility Pole (owner unknown)
SCD.....Scada	

CAUTION/ATTENTION
 Although utility locations are established using the best available information, they cannot be guaranteed. Property lines were compiled from plans and documents recorded in the Land Registry System and are for indexing purposes only.
 Bien que l'emplacement des services publics soient établis en utilisant la meilleure information disponible, ils ne peuvent pas être garantis. Des lignes de propriété ont été compilées en utilisant des plans et des documents enregistrés dans le système de cadastre et sont pour l'indexation seulement.



OTTAWA UTILITY COORDINATING COMMITTEE
 CENTRAL REGISTRY
 COMITÉ DE COORDINATION DES SERVICES PUBLICS D'OTTAWA
 ENREGISTREMENT CENTRAL



PRODUCED BY: GIS & DATA MANAGEMENT BRANCH
 INFORMATION CENTRE UNIT
 SCALE: 1:250
 SHEET NUMBER
E-14-21

E-13-20

E-14-22

This image shows a page of handwritten musical notation on ten staves. The notation is dense and includes various symbols, including notes, rests, and beams. There are several annotations and markings scattered throughout the page:

- Staff 1:** The word "RUBATO" is written in the left margin.
- Staff 2:** The word "CORNER" is written in the middle margin.
- Staff 3:** The word "CORNER" is written in the middle margin.
- Staff 4:** The word "CORNER" is written in the middle margin.
- Staff 5:** The word "CORNER" is written in the middle margin.
- Staff 6:** The word "CORNER" is written in the middle margin.
- Staff 7:** The word "CORNER" is written in the middle margin.
- Staff 8:** The word "CORNER" is written in the middle margin.
- Staff 9:** The word "CORNER" is written in the middle margin.
- Staff 10:** The word "CORNER" is written in the middle margin.

The handwriting is in black ink on white paper. The notation is somewhat messy and appears to be a working draft or a composer's sketch. The word "CORNER" is repeated multiple times, possibly indicating a specific musical technique or a section of the piece. The word "RUBATO" is also present, suggesting a change in tempo or a more expressive playing style.

Geotechnical
Engineering

Environmental
Engineering

Hydrogeology

Geological
Engineering

Materials Testing

Building Science

Noise and Vibration
Studies

Paterson Group Inc.

Consulting Engineers
154 Colonnade Road South
Ottawa (Nepean), Ontario
Canada K2E 7S8

Tel: (613) 226-7381
Fax: (613) 226-6344
www.patersongroup.ca

Geotechnical Investigation
Proposed Multi-Storey Building
50 The Driveway
Ottawa, Ontario

Prepared For

Main and Main

July 16, 2021

Report: PG5880-1

Table of Contents

	PAGE
1.0 Introduction	1
2.0 Proposed Development.....	1
3.0 Method of Investigation	2
3.1 Field Investigation	2
3.2 Field Survey	4
3.3 Laboratory Testing	4
3.4 Analytical Testing	4
4.0 Observations	5
4.1 Surface Conditions.....	5
4.2 Subsurface Profile.....	5
4.3 Groundwater	6
5.0 Discussion	8
5.1 Geotechnical Assessment.....	8
5.2 Site Grading and Preparation.....	8
5.3 Foundation Design	9
5.4 Design for Earthquakes.....	10
5.5 Basement Slab.....	12
5.6 Basement Wall.....	12
5.7 Pavement Design.....	14
6.0 Design and Construction Precautions.....	16
6.1 Foundation Drainage and Backfill	16
6.2 Protection of Footings Against Frost Action	18
6.3 Excavation Side Slopes and Temporary Shoring.....	18
6.4 Pipe Bedding and Backfill	20
6.5 Groundwater Control.....	21
6.6 Winter Construction.....	22
6.7 Corrosion Potential and Sulphate.....	23
7.0 Recommendations	24
8.0 Statement of Limitations.....	25

Appendices

- Appendix 1** Soil Profile and Test Data Sheets
 Symbols and Terms
 Analytical Test Results
- Appendix 2** Figure 1 - Key Plan
 Figures 2 & 3 – Seismic Shear Wave Velocity Profiles
 Drawing PG5880-1 - Test Hole Location Plan

1.0 Introduction

Paterson Group (Paterson) was commissioned by Main and Main to conduct a geotechnical investigation for the proposed development to be located at 50 The Driveway in the City of Ottawa (refer to Figure 1 - Key Plan in Appendix 2 of this report).

The objectives of the geotechnical investigation were to:

- Determine the subsoil and groundwater conditions at this site by means of boreholes.
- Provide geotechnical recommendations pertaining to the design of the proposed development including construction considerations which may affect the design.

The following report has been prepared specifically and solely for the aforementioned project which is described herein. It contains our findings and includes geotechnical recommendations pertaining to the design and construction of the subject development as they are understood at the time of writing this report.

Investigating the presence or potential presence of contamination on the subject property was not part of the scope of work of the present investigation. Therefore, the present report does not address environmental issues.

2.0 Proposed Development

Based on the available drawings, it is understood that the proposed development will consist of a multi-storey mixed-use structure with two levels of underground parking which will occupy the majority of the subject site. It is also understood that portions of the east and south existing building facades will be retained and integrated as part of the proposed building. However, the structure is expected to be demolished as part of the proposed development.

The proposed building will generally be surrounded by walkways and landscaped areas. It is also expected that the proposed building will be municipally serviced.

3.0 Method of Investigation

3.1 Field Investigation

Field Program

The field program for the current geotechnical investigation was carried out during the period of June 30 through July 5, 2021. At that time three (3) boreholes and two (2) test pits were advanced to maximum depth of 20.5 m and 4.7 m below the existing ground surface, respectively. The test hole locations were distributed in a manner to provide general coverage of the subject site and taking into consideration the location of underground utilities and site features. The test hole locations are shown on Drawing PG5880-1 - Test Hole Location Plan included in Appendix 2.

The boreholes were drilled using a low-clearance drill rig operated by a two-person crew. The test pits were excavated using a rubber-tired back-hoe. All fieldwork was conducted under the full-time supervision of Paterson personnel under the direction of a senior engineer. The drilling procedure consisted of advancing each test hole to the required depths at the selected locations and sampling the overburden.

Sampling and In Situ Testing

The soil samples were recovered from the auger flights and using a 50 mm diameter split-spoon sampler. Grab samples were collected from the test pit sidewalls and by hand-auger recovery at selected intervals. The samples were classified on site, placed in sealed plastic bags, and transported to our laboratory. The depths at which the auger, split spoon and grab samples were recovered from the boreholes are shown as SS, AU and G, respectively, on the Soil Profile and Test Data sheets in Appendix 1.

The Standard Penetration Test (SPT) was conducted in conjunction with the recovery of the split-spoon samples. The SPT results are recorded as “N” values on the Soil Profile and Test Data sheets. The “N” value is the number of blows required to drive the split-spoon sampler 300 mm into the soil after a 150 mm initial penetration using a 63.5 kg hammer falling from a height of 760 mm.

Undrained shear strength testing, using a vane apparatus, was carried out at regular intervals of depth in cohesive soils.

The overburden thickness was evaluated by a dynamic cone penetration test (DCPT) completed at BH 1-21 and BH 5-21. The DCPT consists of driving a steel drill rod, equipped with a 50 mm diameter cone at the tip, using a 63.5 kg hammer falling from a height of 760 mm. The number of blows required to drive the cone into the soil is recorded for each 300 mm increment.

The subsurface conditions observed in the boreholes were recorded in detail in the field. The soil profiles are logged on the Soil Profile and Test Data sheets in Appendix 1 of this report.

Groundwater

Monitoring wells were installed at boreholes BH 1-21, BH 4-21, and BH 5-21. Boreholes BH 2-21, BH 3-21 and BH 5-21 were fitted with flexible standpipe piezometers to allow for groundwater level monitoring. Groundwater level observations are discussed in Section 4.3 and are presented in the Soil Profile and Test Data sheets in Appendix 1.

Monitoring Well Installation

Typical monitoring well construction details are described below:

- 3.0 m of slotted 51 mm PVC screen at the base of the boreholes.
- 51 mm diameter PVC riser pipe from the top of the screen to the ground surface.
- No. 3 silica sand backfill within annular space around screen.
- 300 mm thick bentonite hole plug directly above PVC slotted screen.
- Clean backfill from top of bentonite plug to the ground surface.

Refer to the Soil Profile and Test Data sheets in Appendix 1 for specific well construction details.

Sample Storage

All samples will be stored in the laboratory for a period of one (1) month after issuance of this report. They will then be discarded unless we are otherwise directed.

3.2 Field Survey

The test hole locations were selected by Paterson to provide general coverage of the proposed development, taking into consideration the existing site features and underground utilities. The test hole locations and ground surface elevation at each test hole location were surveyed by Paterson personnel using a handheld GPS and referenced to a geodetic datum. The location of the boreholes and ground surface elevation at each test hole location are presented on Drawing PG5880-1 - Test Hole Location Plan in Appendix 2.

3.3 Laboratory Testing

Soil samples were recovered from the subject site and visually examined in our laboratory to review the results of the field logging. Soil samples will be stored for a period of one month after this report is completed, unless otherwise directed.

3.4 Analytical Testing

One (1) soil sample was submitted for analytical testing to assess the corrosion potential for exposed ferrous metals and the potential of sulphate attacks against subsurface concrete structures. The sample was submitted to determine the concentration of sulphate and chloride, the resistivity, and the pH of the samples. The results are presented in Appendix 1 and are discussed further in Section 6.7.

4.0 Observations

4.1 Surface Conditions

Existing Conditions

The subject site is currently occupied by a three-storey institutional building with associated landscaped areas, parking areas and access lanes. The ground surface is relatively flat throughout the parking area. The ground surface around the eastern portion of the site slopes downwards gradually from north to south and between geodetic elevations of 68.5 to 66.0 m.

The site is bordered to the east by a paved pedestrian pathway and further by Queen Elizabeth Driveway, to the south by the Embassy of Germany and residential dwellings, to the west by townhouses and to the north by Lewis Street and further by a high-rise apartment building and the associated above-ground parking structure.

Historical Conditions

It should be noted Neville's Creek historically transected the southern portion of the subject site, which is understood to have been infilled in the late 19th century. The existing surface conditions have been completely altered since that time and are not considered representative of its previous footprint due to notable in-filling of the creek.

4.2 Subsurface Profile

Overburden

Generally, the subsurface profile encountered at the test hole locations consisted of an asphalt pavement structure or topsoil underlain by a variable layer of fill. The fill was observed to generally consist of brown and/or grey silty clay or sand with varying amounts of gravel, cobbles, concrete, wood debris and organics. The fill was observed to extend to depths ranging between of 0.7 m to 6.7 m below the existing ground surface.

The fill layers were observed to be underlain by a deposit of silty clay. This deposit was generally observed to consist of a very stiff to stiff, brown silty clay crust underlain by a layer of stiff grey silty clay. It should be noted the crust layer was not encountered in the areas where the fill layer was encountered above the grey silty clay at BH 2-21 and BH 5 -21.

Practical refusal to DCPT was encountered at an approximate depth of 20.5 m and 22.1 m at the location of boreholes BH 1-21 and BH 5-21, respectively.

Reference should be made to the Soil Profile and Test Data sheets in Appendix 1 for the details of the soil profile encountered at each test hole location.

Bedrock

Based on available geological mapping, the bedrock in the subject area consists of Paleozoic Shale of the Carlsbad formation, with an overburden drift thickness of 15 to 25 m depth.

Existing Building Foundation

Two test pits were advanced against portions of the existing building that are anticipated to be incorporated as part of the proposed development. The foundation wall was generally observed to consist of damp-proofed concrete and backfilled against by fill containing variable amounts of clay, silt, sand, gravel and inorganic debris. The top of the footing was encountered at an elevation of 63.3 and 62.2 m at TP 1-21 and TP 2-21, respectively. The underside of footing was encountered at an elevation of 63.0 m at TP 1-21 along with a clay drainage pipe.

The underside of footing was not encountered at TP 2-21 due to a combination of groundwater ingress and loose foundation backfill sidewalls unable to remain open. The top of the footing was inferred at an elevation of 62.2 m based on auger-probes carried out prior to in-filling the test pit at that time.

Based on our review of structural drawings prepared for The Canadian Nurses Association and dated October 1986, the southwestern and southeastern building addition is understood to be founded on piles anticipated to have been driven to refusal.

4.3 Groundwater

Groundwater levels were measured on July 6, 2021 within the installed monitoring wells and piezometers. Also, groundwater infiltration levels were recorded within the open holes during the excavation of the test pits. The measured groundwater levels and observed depth of infiltration are presented in Table 1 below:

Table 1 – Summary of Groundwater Levels					
Test Hole Number	Groundwater Measuring Medium	Ground Surface Elevation (m)	Measured Groundwater Level / Groundwater Infiltration for Test Pits		Dated Recorded
			Depth (m)	Elevation (m)	
BH 1-21	Monitoring Well	68.36	Dry	Dry	July 6, 2021
BH 2-21	Piezometer	68.21	10.56	57.65	July 6, 2021
BH 3-21	Piezometer	68.69	4.13	64.56	July 6, 2021
BH 4-21	Monitoring Well	66.10	4.03	62.57	July 6, 2021
BH 5-21	Monitoring Well	66.18	3.82	62.36	July 6, 2021
BH 5-21	Piezometer	66.18	9.72	56.46	July 6, 2021
TP 1-21	Sidewall Infiltration	65.98	Dry	Dry	June 30, 2021
TP 2-21	Sidewall Infiltration	66.18	3.0	63.18	June 30, 2021
Note: The ground surface elevation at each borehole location was surveyed using a handheld GPS using a geodetic datum.					

It should be noted that long-term groundwater levels can also be estimated based on the observed colour and consistency of the recovered soil samples. Based on these observations, the long-term groundwater table can be expected at approximate depths of 3.5 to 4.5 m below ground surface. The recorded groundwater levels are noted on the applicable Soil Profile and Test Data sheet presented in Appendix 1.

However, it should be noted that groundwater levels are subject to seasonal fluctuations. Therefore, the groundwater levels could vary at the time of construction.

From: Sidhu, Jasmin <jasmin.sidhu@stantec.com>
Sent: December 22, 2022 3:00 PM
To: Tousignant, Eric <Eric.Tousignant@ottawa.ca>
Cc: D'Aoust, Stephane <stephane.daoust@stantec.com>; Gillott, Fiona <Fiona.Gillott@ottawa.ca>
Subject: RE: 50 Driveway


CAUTION: This email originated from an External Sender. Please do not click links or open attachments unless you recognize the source.

ATTENTION : Ce courriel provient d'un expéditeur externe. Ne cliquez sur aucun lien et n'ouvrez pas de pièce jointe, excepté si vous connaissez l'expéditeur.

Good afternoon Eric,

Given the pseudo-2D nature of the model (i.e., where runoff is generated using standard storm subcatchments and directed to CBs at ground surface, from where uncaptured flow is then routed onto the 2D surface), 2D surface model results only reflect overland spill which ICM reports in terms of depth, direction, and velocity per mesh element.

However, below is a screenshot of the existing conditions model for the area of interest. This figure shows the general direction of flow and ponding in the area near 50 the Driveway under the 1:100-yr design event, based on ground elevations from the City's 1m DEM. The anticipated flow paths along Lewis St, the Driveway, and the parking lot of 50 the Driveway are also shown on the figure (blue arrows). Based on the DEM, overland flow from Gilmour St would flow southeast along the Driveway and southwest along Lewis St to Robert St. There is ~0.4m between the bottom of curb/edge of roadway to the high (spill) point in the parking lot area for the property in question.



Kind regards,

Jasmin Sidhu P.Eng.
Water Resources Engineer
**Vacation Alert: Please note that I will be off work from December 22 to January 9, inclusive.*

From: Tousignant, Eric <Eric.Tousignant@ottawa.ca>
Sent: Monday, December 19, 2022 14:57
To: Sidhu, Jasmin <jasmin.sidhu@stantec.com>
Cc: D'Aoust, Stephane <stephane.daoust@stantec.com>; Gillott, Fiona <fiona.gillott@ottawa.ca>
Subject: RE: 50 Driveway

Thanks Jasmin, much appreciated.

Eric

From: Sidhu, Jasmin <jasmin.sidhu@stantec.com>
Sent: December 19, 2022 2:53 PM
To: Tousignant, Eric <Eric.Tousignant@ottawa.ca>
Cc: D'Aoust, Stephane <stephane.daoust@stantec.com>; Gillott, Fiona <Fiona.Gillott@ottawa.ca>
Subject: RE: 50 Driveway

CAUTION: This email originated from an External Sender. Please do not click links or open attachments unless you recognize the source.

ATTENTION : Ce courriel provient d'un expéditeur externe. Ne cliquez sur aucun lien et n'ouvrez pas de pièce jointe, excepté si vous connaissez l'expéditeur.

Hi Eric,

Of course. This does fall within the O'Connor model extents. We'll take a look at the modelled major system flow through this site and let you know what we find.

Kind regards,

Jasmin Sidhu P.Eng.
Water Resources Engineer
**Vacation Alert: Please note that I will be off work from December 22 to January 9, inclusive.*

sarrak@lithosgroup.ca

From: Bakhit, Reza <reza.bakhit@ottawa.ca>
Sent: December 13, 2022 4:58 PM
To: sarrak@lithosgroup.ca
Cc: Fawzi, Mohammed
Subject: RE: 50 The Driveway, OT - capacity of the combined sewer

Hi Sarra,

I can confirm the proposed wastewater flow of 1.97l/s is acceptable.

Thanks,

Reza Bakhit, P.Eng, C.E.T

Project Manager

Planning, Real Estate and Economic Development Department / Direction générale de la planification, des biens immobiliers et du développement économique

Development Review - Central Branch

City of Ottawa | Ville d'Ottawa

110 Laurier Avenue West Ottawa, ON | 110, avenue. Laurier Ouest. Ottawa (Ontario) K1P 1J1

613.580.2424 ext./poste 19346, reza.bakhit@ottawa.ca

Please note: Given the current pandemic, I will be working from home until further notice; reaching me by email is the easiest. I will be checking my voicemail, just not as frequently as I normally would be.

From: Bakhit, Reza
Sent: Tuesday, December 13, 2022 9:13 AM
To: 'sarrak@lithosgroup.ca' <sarrak@lithosgroup.ca>
Subject: RE: 50 The Driveway, OT - capacity of the combined sewer

Hi Sarra,

I will provide you with clarification on the capacity.

Thanks,

Reza Bakhit, P.Eng, C.E.T

Project Manager

Planning, Real Estate and Economic Development Department / Direction générale de la planification, des biens immobiliers et du développement économique

Development Review - Central Branch

City of Ottawa | Ville d'Ottawa

110 Laurier Avenue West Ottawa, ON | 110, avenue. Laurier Ouest. Ottawa (Ontario) K1P 1J1

613.580.2424 ext./poste 19346, reza.bakhit@ottawa.ca

Please note: Given the current pandemic, I will be working from home until further notice; reaching me by email is the easiest. I will be checking my voicemail, just not as frequently as I normally would be.

From: sarrak@lithosgroup.ca <sarrak@lithosgroup.ca>
Sent: December 12, 2022 10:54 AM
To: Mottalib, Abdul <Abdul.Mottalib@ottawa.ca>
Subject: 50 The Driveway, OT - capacity of the combined sewer

CAUTION: This email originated from an External Sender. Please do not click links or open attachments unless you recognize the source.

ATTENTION : Ce courriel provient d'un expéditeur externe. Ne cliquez sur aucun lien et n'ouvrez pas de pièce jointe, excepté si vous connaissez l'expéditeur.

I hope my email finds you well.

We are the civil engineers working on the second SPA submission for the property at 50 The Driveway, in the City of Ottawa.

Could you kindly confirm that there is enough capacity in the combined sewer network abutting our site, taking into consideration that the calculated wastewater flow for the subject property is 1.97 L/s (net flow 1.80 L/s)?

Thank you for your assistance.

Sincerely,

Sarra Karavasili, P.E., M.A.Sc.

Assistant Project Manager



Lithos Group Inc.

150 Bermondsey Rd, Unit #200

Toronto, Ontario M4A 1Y1

D: (647) 366-9610 x1

Main Office: (416) 750-7769

Sarrak@LithosGroup.ca

www.LithosGroup.ca

CONFIDENTIALITY NOTE

This email may contain confidential information and any rights to privilege have not been waived.
If you have received this transmission in error, please notify us by telephone or e-mail. Thank you.



Χωρίς ιούς www.avast.com

This e-mail originates from the City of Ottawa e-mail system. Any distribution, use or copying of this e-mail or the information it contains by other than the intended recipient(s) is unauthorized. Thank you.

From: Tousignant, Eric <Eric.Tousignant@ottawa.ca>
Sent: Tuesday, November 29, 2022 11:48 AM
To: Fel Petti
Cc: Neff, Pete; Fawzi, Mohammed
Subject: RE: 50 Driveway

Hi Fel

I had a chat internally here and a lateral connection with bends would be acceptable due to the exceptional situation here. However, it will still need to be discussed with Operations first. This would be one pipe out of the Monitoring MH since this is in the ultimate combined sewer area. We would need some kind of deviation report.

We can chat further if you wish.

Eric



This e-mail originates from the City of Ottawa e-mail system. Any distribution, use or copying of this e-mail or the information it contains by other than the intended recipient(s) is unauthorized. Thank you.

Le présent courriel a été expédié par le système de courriels de la Ville d'Ottawa. Toute distribution, utilisation ou reproduction du courriel ou des renseignements qui s'y trouvent par une personne autre que son destinataire prévu est interdite. Je vous remercie de votre collaboration.

Dimitra Frysalis

From: David Anderson <danderson@hobinarc.com>
Sent: Wednesday, March 8, 2023 11:23 AM
To: sarrak@lithosgroup.ca
Cc: dimitraf@lithosgroup.ca
Subject: RE: 50 The Driveway - 2nd SPA Submission

Hi Sarra,

This is great, thank you! We've gone through the section and can confirm the project will be compliant. For our reference, here is a summary of our correspondences over the past few days:

- We can confirm that vertical openings and vertical communications will be properly protected as per the building code.
- Foundation will be a raft slab, as per the soils report. Top of slab is at 60.155m and underside of slab at 59.155m.
- Building classification is non-combustible. Full table below is included on the Site Plan:

BUILDING CLASSIFICATION		PART 3	PART 9
NUMBER OF STREETS/ ACCESS ROUTES	FACES 1 STREET. ACCESS ROUTE IS PROVIDED WITHIN 15 METERS OF THE PRINCIPAL ENTRANCE	3.2.2.10 & 3.2.5.5	
BLDG CLASSIFICATION	SECTION 3.2.2.42 GROUP C, ANY HEIGHT, ANY AREA, SPRINKLERED	3.2.2.42	9.10.4
SPRINKLER SYSTEM PROPOSED	<input checked="" type="checkbox"/> ENTIRE BLDG <input type="checkbox"/> IN LIEU OF ROOF RATING <input type="checkbox"/> PARKING & GROUND & <input type="checkbox"/> NOT REQUIRED <input type="checkbox"/> MECHANICAL PENTHOUSE	3.2.2.20-83 3.2.1.5 3.2.2.17	9.10.8
STANDPIPE REQUIRED	<input checked="" type="checkbox"/> YES <input type="checkbox"/> NO	3.2.9	
FIRE ALARM REQ'D	<input checked="" type="checkbox"/> YES <input type="checkbox"/> NO	3.2.4	9.10.17.2
WATER SERVICE/ SUPPLY IS ADEQUATE	<input checked="" type="checkbox"/> YES <input type="checkbox"/> NO		
HIGH BUILDING	<input checked="" type="checkbox"/> YES <input type="checkbox"/> NO	3.2.6	
CONSTRUCTION TYPE	PERMITTED CONSTR. ACTUAL CONSTR. <input type="checkbox"/> COMBUSTIBLE <input type="checkbox"/> COMBUSTIBLE <input checked="" type="checkbox"/> NON-COMBUSTIBLE <input checked="" type="checkbox"/> NON-COMBUSTIBLE <input type="checkbox"/> BOTH <input type="checkbox"/> BOTH	3.2.2.20-83	9.10.6

Let me know if you need any further information.

Cheers,

From: sarrak@lithosgroup.ca <sarrak@lithosgroup.ca>
Sent: Tuesday, March 7, 2023 2:00 PM
To: David Anderson <danderson@hobinarc.com>
Cc: dimitraf@lithosgroup.ca
Subject: RE: 50 The Driveway - 2nd SPA Submission

Hello David,

To be honest, I am not too sure if there is a specific definition.

You may find more details in Section 3.5 'Vertical Transportation' in Division B of NBC. Hope this helps.

From: [Elaine Guenette](mailto:Elaine.Guenette)
To: sarrak@lithosgroup.ca
Cc: dimitraf@lithosgroup.ca
Subject: RE: 50 The Driveway, OT- addressing comments
Date: Thursday, December 15, 2022 9:11:03 AM

Hi Sarra,

The proposed building at 50 The Driveway will be fully sprinklered.

Regards,

Smith + Andersen

Elaine Guenette B.A.Sc., P.Eng., LEED AP
Principal
d 613 691 1853 m 343 961 2244

From: sarrak@lithosgroup.ca <sarrak@lithosgroup.ca>
Sent: December 15, 2022 8:30 AM
To: Elaine Guenette <elaine.guenette@smithandandersen.com>
Cc: dimitraf@lithosgroup.ca
Subject: 50 The Driveway, OT- addressing comments

CAUTION: This message originated from outside Smith + Andersen

Hello Elaine,

I hope my email finds you well.

We are the civil engineers working on the 2nd SPA submission for the subject project.

Following our review of the 1st round of comments dated August 31, 2022, we would require your assistance on the comment below:

3.10: "Provide an email correspondence from the mechanical engineer confirming that the proposed building will be sprinklered. Please include this correspondence as an appendix in the report."

Could you kindly confirm that the proposed building will be sprinklered, just so we address the above noted comment?

Thank you,

Sarra Karavasili, P.E., M.A.Sc.
Assistant Project Manager
[Lithos Group Inc.](#)

Guy Forget

From: Jamie Batchelor <jamie.batchelor@rvca.ca>
Sent: Monday, July 12, 2021 9:26 AM
To: Guy Forget
Cc: Eric Lalande
Subject: RE: 50 Driveway

[CAUTION] This email originated from outside JLR. Do not click links or open attachments unless you recognize the sender and know the content is safe. If in doubt, please forward suspicious emails to Helpdesk.

Good Morning Guy,

Based on the proposed plans (rooftops and landscaped areas) and the fact that the stormwater from this site would ultimately be directed to combined storm sewers, no additional on-site water quality control would be required save and except best management practices. We would encourage you to explore opportunities to incorporate LID measures into the stormwater management plan.

Jamie Batchelor, MCIP, RPP
Planner, ext. 1191
jamie.batchelor@rvca.ca



3889 Rideau Valley Drive
PO Box 599, Manotick ON K4M 1A5
T 613-692-3571 | 1-800-267-3504 F 613-692-0831 | www.rvca.ca

This message may contain information that is privileged or confidential and is intended to be for the use of the individual(s) or entity n; may contain confidential or personal information which may be subject to the provisions of the Municipal *Freedom of Information & F* you are not the intended recipient of this e-mail, any use, review, revision, retransmission, distribution, dissemination, copying, printing taking of any action in reliance upon this e-mail, is strictly prohibited. If you have received this e-mail in error, please contact the send and any copy of the e-mail and any printout thereof, immediately. Your cooperation is appreciated.

From: Guy Forget <gforget@jlrichards.ca>
Sent: Thursday, July 8, 2021 4:06 PM
To: Jamie Batchelor <jamie.batchelor@rvca.ca>
Cc: Eric Lalande <eric.lalande@rvca.ca>
Subject: FW: 50 Driveway

Hi Jamie,

I just sent this email to Eric for an opinion on water quality (see attached and below).

We are submitting mid next week, and was hoping to have an opinion before then. Given that Eric is back next week, can I ask you or somebody else at the RVCA to provide an opinion?

Let me know

Guy

Guy Forget, P.Eng., LEED AP
Senior Water Resources Engineer

J.L. Richards & Associates Limited
700 - 1565 Carling Avenue, Ottawa, ON K1Z 8R1
Direct: 343-804-5363



**J.L. Richards
& Associates Limited**
ENGINEERS • ARCHITECTS • PLANNERS



Platinum
member

*J.L. Richards & Associates Limited is proactively doing our part to protect the wellbeing of our staff and communities while improving our communication technology. **We are pleased to announce that we have implemented direct phone lines for all of our staff, allowing you to connect with us regardless of whether we are working remotely or in the office.** We are dedicated to delivering quality services to you through value and commitment, as always. Please reach out to us if you have any questions about your project.*

From: Guy Forget
Sent: Thursday, July 8, 2021 4:01 PM
To: 'Eric Lalonde' <eric.lalonde@rvca.ca>
Cc: Lucie Dalrymple <ldalrymple@jlrichards.ca>; 'Emily Roukhkian' <emily@mainandmain.ca>
Subject: 50 Driveway

Hi Eric,

Hope you are doing well.

We have been retained to prepare an Assessment of Adequacy of Public Services Report (Servicing Brief) for 50 Driveway, in the City of Ottawa.

As shown on the attached Location Plan, the Site (0.28 ha) is bounded by Queen Elizabeth Way and Lewis Street and is part of the combined sewer system that ultimately drains to ROPEC.

There is a large combined (1800 mm diameter) on Lewis Street and a smaller 305 mm diameter on QED. Based on our review of the existing condition, runoff from the site currently drains to both combined sewers.

Under the post-development condition (see attached), a significant portion of the site will be the 9-storey roof which accounts for 60% of the overall parcel (1700 m² of 2800 m²).

The areas outside of the of the building envelope are either grassed or interlock. The area labelled in cyan as 127 m² is the one that is almost all hard surface and will sheet flow to the 1800 mm combined sewer as there are no opportunities to pick it up with a sewer. The other areas I have labelled are a combination of grass and interlock. Please note that there is no above ground parking. As such, there will be a reduction in TSS given that the large existing parking surface will be removed.

Could you provide an opinion whether the project can proceed without any additional quality measures given the reduction in TSS combined to the fact that the Site is part of the combined system which ultimately drains to ROPEC. Note that we are submitting our Report mid next week, so we would be grateful if you could provide RVCA's opinion before then.

Thank you
Guy



FRÄNKISCHE / EN / Products / Rigofill® ST block/half block

[BACK TO OVERVIEW](#)

Rigofill® ST block/half block



CONTENTS

[Components](#)

[Downloads](#)

 [Contact search](#)

FRÄNKISCHE



polypropylene (PP).

The Rigofill ST full block consists of two half elements to be installed on site and has a void ratio of > 96 %. The Rigofill ST half block consists of only one half element, which must be assembled with a roof slab on site. The cross-shaped inspection tunnel in the storage/infiltration unit has been designed for the use of automotive dollies. This allows for full inspection of the effective drainage surface and the entire system volume with all statically relevant bearing-type fixtures. In combination with QuadroControl ST, Rigofill ST storage/infiltration systems have been designed for professional final acceptance inspection and repeated inspection. Installation under trafficked areas (HGV 60) and at great depths is possible.

cial geotextile lining, QuadroControl ST inspection shafts and additional accessories.


NB! Follow the Rigofill ST installation manual! **Rigofill ST block**

- W x D x H = 800 x 800 x 660 mm
- Gross volume: 422 l
- Storage volume: 406 l

Rigofill ST half block


- W x D x H = 800 x 800 x 350 mm
- Gross volume: 224 l
- Storage volume: 212 l

FRÄNKISCHE




Accessories

Side wall lattice
Rigofill® ST




Accessories

Side wall lattice
Rigofill® ST half
block



Accessories

Block connector
Rigofill® ST



Accessories

Adapter Rigofill®
ST



Accessories

Side wall lattice
Rigofill® ST short



Accessories

Side wall lattice
Rigofill® ST half
block short



Accessories

The supporting
grid

Downloads

FRÄNKISCHE



Data Sheet Rigofill ST
Datasheet



From: [David Anderson](mailto:David.Anderson@lithosgroup.ca)
 To: sarrak@lithosgroup.ca
 Cc: dimitraf@lithosgroup.ca
 Subject: RE: 50 The Driveway - 2nd SPA Submission
 Date: Wednesday, March 8, 2023 11:23:09 AM
 Attachments:

Hi Sarra,

This is great, thank you! We've gone through the section and can confirm the project will be compliant. For our reference, here is a summary of our correspondences over the past few days:

- We can confirm that vertical openings and vertical communications will be properly protected as per the building code.
- Foundation will be a raft slab, as per the soils report. Top of slab is at 60.155m and underside of slab at 59.155m.
- Building classification is non-combustible. Full table below is included on the Site Plan:

BUILDING CLASSIFICATION		PART 3	PART 9
NUMBER OF STREETS/ ACCESS ROUTES	FACES 1 STREET. ACCESS ROUTE IS PROVIDED WITHIN 15 METERS OF THE PRINCIPAL ENTRANCE	3.2.2.10 & 3.2.5.5	
BLDG CLASSIFICATION	SECTION 3.2.2.42 GROUP C, ANY HEIGHT, ANY AREA, SPRINKLERED	3.2.2.42	9.10.4
SPRINKLER SYSTEM PROPOSED	<input checked="" type="checkbox"/> ENTIRE BLDG <input type="checkbox"/> IN LIEU OF ROOF RATING <input type="checkbox"/> PARKING & GROUND & MECHANICAL PENTHOUSE <input type="checkbox"/> NOT REQUIRED	3.2.2.20-83 3.2.1.5 3.2.2.17	9.10.8
STANDPIPE REQUIRED	<input checked="" type="checkbox"/> YES <input type="checkbox"/> NO	3.2.9	
FIRE ALARM REQ'D	<input checked="" type="checkbox"/> YES <input type="checkbox"/> NO	3.2.4	9.10.17.2
WATER SERVICE/ SUPPLY IS ADEQUATE	<input checked="" type="checkbox"/> YES <input type="checkbox"/> NO		
HIGH BUILDING	<input checked="" type="checkbox"/> YES <input type="checkbox"/> NO	3.2.6	
CONSTRUCTION TYPE	PERMITTED CONSTR. ACTUAL CONSTR. <input type="checkbox"/> COMBUSTIBLE <input type="checkbox"/> COMBUSTIBLE <input checked="" type="checkbox"/> NON-COMBUSTIBLE <input checked="" type="checkbox"/> NON-COMBUSTIBLE <input type="checkbox"/> BOTH <input type="checkbox"/> BOTH	3.2.2.20-83	9.10.6

Let me know if you need any further information.

Cheers,

From: sarrak@lithosgroup.ca <sarrak@lithosgroup.ca>
Sent: Tuesday, March 7, 2023 2:00 PM
To: David Anderson <danderson@hobinarc.com>
Cc: dimitraf@lithosgroup.ca
Subject: RE: 50 The Driveway - 2nd SPA Submission

Hello David,

To be honest, I am not too sure if there is a specific definition.

Giandotti (1934):

$$T_c = [4*(A^{0.5}) + 1.5 * L] / [0.8* (H_{mn} - H_{min})]$$

Where:

A = watershed area (Km²)

L = length of the main channel (Km)

H_{mn} = Mean basin elevation

H_{min} = Outlet elevation

And : A = 134.23 m²

L = 40.00 m

H_{max} = 68.80 m

H_{mn} = 67.38 m

H_{min} = 65.95 m

$$T_c = [4*(0.000134^{0.5}) + 1.5 * 0.04] / [0.8* (67.38 - 65.95)]$$


T_c = 0.08 hr = 5 min

Inlet time = 15 min

Time of concentration = 15 + 5 = 20 min

Appendix C

Storm Analysis



RUN-OFF COEFFICIENTS				
DRAINAGE AREA	LAND USE	AREA (ha)	ACTUAL COEFFICIENT	DESIGN COEFFICIENT
A1 PRE	HARDSCAPE	0.296	0.90	0.40
External 1	LANDSCAPE	0.071	0.61	0.40



LEGEND

- STORM DRAINAGE AREA NUMBER
- DRAINAGE AREA (ha)
- COMPOSITE RUNOFF COEFFICIENT
- PRE-DEVELOPMENT STORM DRAINAGE AREA
- PROPERTY LINE
- EMERGENCY OVERLAND FLOW ROUTE

PRE-DEVELOPMENT DRAINAGE AREA PLAN
RESIDENTIAL USE DEVELOPMENT
50 THE DRIVEWAY
OTTAWA, ONTARIO

DATE: MARCH 2023 PROJECT No: UD22-093
SCALE: N.T.S. FIGURE No: DAP1



**Rational Method
Pre-Development Flow Calculation**

Prepared By: Dimitra Frysali, P.E., M.A.Sc.
Reviewed by: Nick Moutzouris, P.Eng., M.A.Sc.

**50 The Driveway File No.
UD22-093 City of Ottawa
Date: March 2023**

Area Number	Area (ha)	Actual Coefficient	Design Coefficient
A1 Pre	0.296	0.90	0.40
External Area 1	0.071	0.49	0.40
A1 Pre + External Area 1	0.367	0.77	0.40


Rational Method Calculation

Event 5-year IDF Data Set City of Ottawa a = 998.071 b= 6.053 c= 0.81

Area Number	A (ha)	C	AC	Tc (min.)	I (mm/h)	Q (m ³ /s)	Q (L/s)
A1 Pre	0.296	0.40	0.12	20	70.25	0.023	23.1
External Area 1	0.071	0.400	0.028	20	70.25	0.006	5.5

Event 100-year IDF Data Set City of Ottawa a = 1735.688 b= 6.014 c= 0.82

Area Number	A (ha)	C	AC	Tc (min.)	I (mm/h)	Q (m ³ /s)	Q (L/s)
A1 Pre	0.296	0.40	0.12	20	119.95	0.039	39.5
External Area 1	0.071	0.400	0.028	20	119.95	0.009	9.5



DRAINAGE AREA	AREA (ha)	TOTAL AREA (ha)
A1 POST	0.226	0.367
A2 POST	0.025	
A3 POST	0.045	
EXT. 1	0.071	

RUN-OFF COEFFICIENTS						
DRAINAGE AREA	LEGEND	LAND USE	AREA (ha)	INITIAL COEFFICIENT	ACTUAL COEFFICIENT	DESIGN COEFFICIENT
A1 POST (Rooftops / Terraces / Walkways - Controlled in tank)	[Diagonal Hatching]	LANDSCAPE	0.012	0.25	0.86	1.00
		HARDSCAPE	0.213	0.90		
A2 POST (Uncontrolled area - towards Lewis Street)	[Diagonal Hatching]	LANDSCAPE	0.016	0.25	0.48	0.54
		HARDSCAPE	0.009	0.90		
A3 POST (Area towards the catch basin - controlled in chambers)	[Hexagonal Pattern]	LANDSCAPE	0.028	0.25	0.50	0.62
		HARDSCAPE	0.017	0.90		
EXT. 1 (External Area towards the catch basin - controlled in chambers)	[Downward Arrows]	LANDSCAPE	0.045	0.25	0.49	0.61
		HARDSCAPE	0.026	0.90		



150 Bermondsey Road, Toronto, Ontario M4A 1Y1

LEGEND

- STORM DRAINAGE AREA NUMBER
- DRAINAGE AREA (ha)
- COMPOSITE RUNOFF COEFFICIENT
- POST-DEVELOPMENT STORM DRAINAGE AREA
- PROPERTY LINE
- EMERGENCY OVERLAND FLOW ROUTE

POST-DEVELOPMENT DRAINAGE AREA PLAN

RESIDENTIAL USE DEVELOPMENT
50 THE DRIVEWAY
OTTAWA, ONTARIO

DATE: MARCH 2023

PROJECT No: UD22-093

SCALE: N.T.S.

FIGURE No: DAP2



Modified Rational Method - 5 Year Storm

Site Flow and Storage Summary

50 The Driveway, Ottawa

File No. UD22-093

City of Ottawa

Date: March 2023

File No: UD22-093

Prepared by: Dimitra Frysalis P.E., M.A.Sc

Reviewed by: Nick Moutzouris, P.Eng., M.A.Sc.

Drainage Area A1 Post		Drainage Area A2 Post				Total Site											
Rooftops / Terraces/ Walkways -Controlled in tank		Uncontrolled area - towards Lewis Street				Total Site= A1 + A2											
Area (A1) = 0.226 ha "C" = 0.86 AC1= 0.195 Tc = 10.0 min Time Increment = 5.0 min Release Rate = 56.42 L/s		Area (A2) = 0.025 ha "C" = 0.48 AC2= 0.01 Tc = 10.0 min Time Increment = 5.0 min Max. Release Rate = 3.5 L/s				Design Controlled Release Rate (80mm orifice plate)= 10.9 L/s Max. Storage Tank Size = 45 m ³ Storage Tank footprint Area = 70.0 m ² Controlled Release Rate Achieved = 10.9 L/s Uncontrolled Release Rate = 3.5 L/s Total Site Release Rate = 14.4 L/s 5-year pre-development Site Release Rate (Allowable Release Rate) = 23.1 L/s											
5-Year Design Storm		Tributary Area (A1)		ha		C		Tributary Area (A2)		ha		C					
a=	998.07	Landsc.Area	0.013	0.25	Landsc.Area	0.016	0.25	Landsc.Area	0.016	0.025	0.48						
b=	6.053	Hardsc. Area	0.213	0.90	Hardsc. Area	0.009	0.90	Hardsc. Area	0.009	0.025	0.48						
c=	0.814	Total	0.226	0.86	Total	0.025	0.48	Total	0.025	0.48							
I =	a / (TC + b)c																
(1)	(2)	(3)		(4)		(5)		(6)		(7)		(8)		(9)		(10)	
Time	Rainfall	Storm		Runoff		Storm		Runoff		Total Storm	Released	Storage		Storage			
(min)	(mm/hr)	Runoff (A1 post)		Volume (A1 post)		Runoff (A2 Post)		Volume (A2 Post)		Runoff Volume	Volume	Volume		Depth of Tank			
		(m ³ /s)		(m ³)		(m ³ /s)		(m ³)		(m ³)	(m ³)	(m ³)		(m)			
10.0	104.2	0.056	33.85	0.004	2.10	33.85	3.26	30.59	0.44								
15.0	83.6	0.045	40.72	0.003	2.53	40.72	4.89	35.83	0.51								
20.0	70.3	0.038	45.65	0.002	2.83	45.65	6.52	39.13	0.56								
25.0	60.9	0.033	49.47	0.002	3.07	49.47	8.15	41.32	0.59								
30.0	53.9	0.029	52.57	0.002	3.26	52.57	9.78	42.79	0.61								
35.0	48.5	0.026	55.17	0.002	3.42	55.17	11.41	43.77	0.63								
40.0	44.2	0.024	57.43	0.001	3.56	57.43	13.04	44.39	0.63								
45.0	40.6	0.022	59.40	0.001	3.69	59.40	14.67	44.74	0.64								
50.0	37.7	0.020	61.17	0.001	3.80	61.17	16.30	44.87	0.64								
55.0	35.1	0.019	62.77	0.001	3.90	62.77	17.93	44.84	0.64								
60.0	32.9	0.018	64.22	0.001	3.99	64.22	19.56	44.67	0.64								
65.0	31.0	0.017	65.56	0.001	4.07	65.56	21.19	44.38	0.63								
70.0	29.4	0.016	66.80	0.001	4.15	66.80	22.82	43.99	0.63								
75.0	27.9	0.015	67.96	0.001	4.22	67.96	24.45	43.51	0.62								
80.0	26.6	0.014	69.04	0.001	4.29	69.04	26.08	42.97	0.61								
85.0	25.4	0.014	70.06	0.001	4.35	70.06	27.71	42.36	0.61								
90.0	24.3	0.013	71.03	0.001	4.41	71.03	29.34	41.69	0.60								
95.0	23.3	0.013	71.94	0.001	4.46	71.94	30.97	40.97	0.59								
100.0	22.4	0.012	72.80	0.001	4.52	72.80	32.60	40.21	0.57								
105.0	21.6	0.012	73.63	0.001	4.57	73.63	34.23	39.41	0.56								
110.0	20.8	0.011	74.42	0.001	4.62	74.42	35.86	38.57	0.55								
115.0	20.1	0.011	75.18	0.001	4.67	75.18	37.49	37.69	0.54								
120.0	19.5	0.011	75.90	0.001	4.71	75.90	39.11	36.79	0.53								
125.0	18.9	0.010	76.60	0.001	4.75	76.60	40.74	35.86	0.51								
130.0	18.3	0.010	77.27	0.001	4.80	77.27	42.37	34.90	0.50								
135.0	17.8	0.010	77.92	0.001	4.84	77.92	44.00	33.92	0.48								
140.0	17.3	0.009	78.55	0.001	4.88	78.55	45.63	32.92	0.47								
145.0	16.8	0.009	79.16	0.001	4.91	79.16	47.26	31.89	0.46								
150.0	16.4	0.009	79.74	0.001	4.95	79.74	48.89	30.85	0.44								
155.0	15.9	0.009	80.31	0.001	4.98	80.31	50.52	29.79	0.43								
160.0	15.6	0.008	80.87	0.001	5.02	80.87	52.15	28.71	0.41								
165.0	15.2	0.008	81.40	0.001	5.05	81.40	53.78	27.62	0.39								
170.0	14.8	0.008	81.93	0.000	5.08	81.93	55.41	26.51	0.38								
175.0	14.5	0.008	82.44	0.000	5.12	82.44	57.04	25.39	0.36								
180.0	14.2	0.008	82.93	0.000	5.15	82.93	58.67	24.26	0.35								
185.0	13.9	0.008	83.42	0.000	5.18	83.42	60.30	23.11	0.33								
190.0	13.6	0.007	83.89	0.000	5.21	83.89	61.93	21.96	0.31								
195.0	13.3	0.007	84.35	0.000	5.24	84.35	63.56	20.79	0.30								
200.0	13.0	0.007	84.80	0.000	5.26	84.80	65.19	19.61	0.28								
205.0	12.8	0.007	85.24	0.000	5.29	85.24	66.82	18.42	0.26								
210.0	12.6	0.007	85.67	0.000	5.32	85.67	68.45	17.22	0.25								
215.0	12.3	0.007	86.09	0.000	5.34	86.09	70.08	16.01	0.23								
220.0	12.1	0.007	86.50	0.000	5.37	86.50	71.71	14.79	0.21								
225.0	11.9	0.006	86.91	0.000	5.39	86.91	73.34	13.57	0.19								
230.0	11.7	0.006	87.30	0.000	5.42	87.30	74.97	12.33	0.18								
235.0	11.5	0.006	87.69	0.000	5.44	87.69	76.60	11.09	0.16								
240.0	11.3	0.006	88.07	0.000	5.47	88.07	78.23	9.84	0.14								



Modified Rational Method - 100 Year

50 The Driveway, Ottawa

Storm Site Flow and Storage Summary

File No. UD22-093

City of Ottawa

Date: March 2023

File No: UD22-093

Prepared by: Dimitra Frysalis P.E., M.A.Sc

Reviewed by: Nick Moutzouris, P.Eng., M.A.Sc.

Drainage Area A1 Post				Drainage Area A2 Post			Total Site					
Rooftops / Terraces/ Walkways - Controlled in tank				Uncontrolled area - towards Lewis Street			Total Site= A1 + A2					
* C value for the 100 year storm event is increased by 25%, with a maximum of 1.0 per City's Sewer Design Guidelines												
Area (A1) = 0.226 ha "C" = 1.00 AC1= 0.226 Tc = 10.0 min Time Increment = 5.0 min Release Rate = 112.10 L/s				Area (A2) = 0.025 ha "C" = 0.54 AC2= 0.01 Tc = 10.0 min Time Increment = 5.0 min Max. Release Rate = 6.7 L/s			Design Controlled Release Rate (80mm orifice plate)= 16.0 L/s Max. Storage Tank Size = 98 m ³ Storage Tank footprint Area = 70.0 m ² Controlled Release Rate Achieved = 16.0 L/s Uncontrolled Release Rate = 6.7 L/s Total Site Release Rate = 22.7 L/s 5-year pre-development Site Release Rate (Allowable Release Rate) = 23.1 L/s					
100-Year Design Storm		Tributary Area (A1)	ha	C	Tributary Area (A2)	ha	C					
a=	1735.69	Landsc.Area	0.013	0.25	Landsc.Area	0.018	0.25					
b=	6.014	Hardsc. Area	0.213	0.90	Hardsc. Area	0.007	0.90					
c=	0.820	Total	0.226	0.86	Total	0.025	0.43					
l = a / (TC + b)c												
(1)	(2)	(3)		(4)	(5)		(6)	(7)		(8)	(9)	(10)
Time	Rainfall Intensity	Storm Runoff (A1 post)	Runoff Volume (A1 post)	Storm Runoff (A2 Post)	Runoff Volume (A2 Post)	Total Storm Runoff Volume	Released Volume	Storage Volume	Storage	Depth of Tank		
(min)	(mm/hr)	(m ³ /s)	(m ³)	(m ³ /s)	(m ³)	(m ³)	(m ³)	(m ³)	(m ³)	(m)		
10.0	178.6	0.112	67.26	0.007	4.02	67.26	4.80	62.46	0.89			
15.0	142.9	0.090	80.74	0.005	4.82	80.74	7.20	73.54	1.05			
20.0	120.0	0.075	90.36	0.004	5.40	90.36	9.60	80.76	1.15			
25.0	103.8	0.065	97.79	0.004	5.84	97.79	12.00	85.79	1.23			
30.0	91.9	0.058	103.81	0.003	6.20	103.81	14.40	89.41	1.28			
35.0	82.6	0.052	108.87	0.003	6.50	108.87	16.80	92.07	1.32			
40.0	75.1	0.047	113.22	0.003	6.76	113.22	19.20	94.02	1.34			
45.0	69.1	0.043	117.04	0.003	6.99	117.04	21.60	95.44	1.36			
50.0	64.0	0.040	120.45	0.002	7.19	120.45	24.00	96.45	1.38			
55.0	59.6	0.037	123.52	0.002	7.38	123.52	26.40	97.12	1.39			
60.0	55.9	0.035	126.32	0.002	7.55	126.32	28.80	97.52	1.39			
65.0	52.6	0.033	128.90	0.002	7.70	128.90	31.20	97.70	1.40			
70.0	49.8	0.031	131.28	0.002	7.84	131.28	33.60	97.68	1.40			
75.0	47.3	0.030	133.50	0.002	7.97	133.50	36.00	97.50	1.39			
80.0	45.0	0.028	135.57	0.002	8.10	135.57	38.40	97.17	1.39			
85.0	43.0	0.027	137.52	0.002	8.21	137.52	40.80	96.72	1.38			
90.0	41.1	0.026	139.37	0.002	8.32	139.37	43.20	96.17	1.37			
95.0	39.4	0.025	141.11	0.001	8.43	141.11	45.60	95.51	1.36			
100.0	37.9	0.024	142.77	0.001	8.53	142.77	48.00	94.77	1.35			
105.0	36.5	0.023	144.35	0.001	8.62	144.35	50.40	93.95	1.34			
110.0	35.2	0.022	145.86	0.001	8.71	145.86	52.80	93.06	1.33			
115.0	34.0	0.021	147.30	0.001	8.80	147.30	55.20	92.10	1.32			
120.0	32.9	0.021	148.69	0.001	8.88	148.69	57.60	91.09	1.30			
125.0	31.9	0.020	150.02	0.001	8.96	150.02	60.00	90.02	1.29			
130.0	30.9	0.019	151.30	0.001	9.04	151.30	62.40	88.90	1.27			
135.0	30.0	0.019	152.53	0.001	9.11	152.53	64.80	87.73	1.25			
140.0	29.2	0.018	153.73	0.001	9.18	153.73	67.20	86.53	1.24			
145.0	28.4	0.018	154.88	0.001	9.25	154.88	69.60	85.28	1.22			
150.0	27.6	0.017	156.00	0.001	9.32	156.00	72.00	84.00	1.20			
155.0	26.9	0.017	157.08	0.001	9.38	157.08	74.40	82.68	1.18			
160.0	26.2	0.016	158.14	0.001	9.45	158.14	76.80	81.34	1.16			
165.0	25.6	0.016	159.16	0.001	9.51	159.16	79.20	79.96	1.14			
170.0	25.0	0.016	160.15	0.001	9.57	160.15	81.60	78.55	1.12			
175.0	24.4	0.015	161.12	0.001	9.62	161.12	84.00	77.12	1.10			
180.0	23.9	0.015	162.06	0.001	9.68	162.06	86.40	75.66	1.08			
185.0	23.4	0.015	162.98	0.001	9.74	162.98	88.80	74.18	1.06			
190.0	22.9	0.014	163.87	0.001	9.79	163.87	91.20	72.67	1.04			
195.0	22.4	0.014	164.75	0.001	9.84	164.75	93.60	71.15	1.02			
200.0	22.0	0.014	165.60	0.001	9.89	165.60	96.00	69.60	0.99			
205.0	21.6	0.014	166.44	0.001	9.94	166.44	98.40	68.04	0.97			
210.0	21.1	0.013	167.25	0.001	9.99	167.25	100.80	66.45	0.95			
215.0	20.8	0.013	168.05	0.001	10.04	168.05	103.20	64.85	0.93			
220.0	20.4	0.013	168.83	0.001	10.09	168.83	105.60	63.23	0.90			
225.0	20.0	0.013	169.60	0.001	10.13	169.60	108.00	61.60	0.88			
230.0	19.7	0.012	170.35	0.001	10.18	170.35	110.40	59.95	0.86			
235.0	19.3	0.012	171.09	0.001	10.22	171.09	112.80	58.29	0.83			
240.0	19.0	0.012	171.81	0.001	10.26	171.81	115.20	56.61	0.81			



Orifice Design

50 The Driveway, Ottawa

File No. UD22-093

Date: January 2023

Prepared by: Dimitra Frysali, P.E., M.A.Sc.

Reviewed by: Nick Moutzouris, P.Eng., M.A.Sc.

Orifice Equation for 80mm Plate

$$Q = C \times A \times \sqrt{2 \times g \times h}$$

100 yr event

d= 80 mm
C= 0.61
A= 0.005 m²
g= 9.81 m/s²
h= 1.40 m
Q= 16.0 L/s

5 yr event

d= 80 mm
C= 0.61
A= 0.005 m²
g= 9.81 m/s²
h= 0.64 m
Q= 10.9 L/s



Modified Rational Method - 5 Year Storm - Chambers

50 The Driveway, Ottawa
File No. UD22-093

Site Flow and Storage Summary

50 The Driveway, Ottawa

City of Ottawa
Date: March 2023

File No: UD22-093
Prepared by: Dimitra Frysali P.E., M.A.Sc
Reviewed by: Nick Moutzouris, P.Eng., M.A.Sc.

5-Year Design Storm		Tributary Area (A1)	ha	C	Tributary Area (A3)	ha	C	Total Storm		Storage	Storage Depth of Chambers
(1)	(2)	(3)		(4)	(5)		(6)	(7)		(8)	(9)
Time	Rainfall Intensity	Storm Runoff (A1 post)	Runoff Volume (A1 post)	Storm Runoff (A3 Post)	Runoff Volume (A3 Post)	Total Storm Runoff	Total Storm Volume	Storage Volume			
(min)	(mm/hr)	(m ³ /s)	(m ³)	(m ³ /s)	(m ³)	(m ³)	(m ³)	(m ³)			
10.0	104.2	0.006	3.87	0.010	6.02	9.89	9.89	9.89	0.24		
15.0	83.6	0.005	4.66	0.008	7.24	11.90	11.90	11.90	0.28		
20.0	70.3	0.004	5.22	0.007	8.11	13.34	13.34	13.34	0.32		
25.0	60.9	0.004	5.66	0.006	8.79	14.45	14.45	14.45	0.34		
30.0	53.9	0.003	6.01	0.005	9.34	15.36	15.36	15.36	0.37		
35.0	48.5	0.003	6.31	0.005	9.81	16.12	16.12	16.12	0.38		
40.0	44.2	0.003	6.57	0.004	10.21	16.78	16.78	16.78	0.40		
45.0	40.6	0.003	6.80	0.004	10.56	17.35	17.35	17.35	0.41		
50.0	37.7	0.002	7.00	0.004	10.87	17.87	17.87	17.87	0.43		
55.0	35.1	0.002	7.18	0.003	11.16	18.34	18.34	18.34	0.44		
60.0	32.9	0.002	7.35	0.003	11.41	18.76	18.76	18.76	0.45		
65.0	31.0	0.002	7.50	0.003	11.65	19.15	19.15	19.15	0.46		
70.0	29.4	0.002	7.64	0.003	11.87	19.52	19.52	19.52	0.47		
75.0	27.9	0.002	7.77	0.003	12.08	19.85	19.85	19.85	0.47		
80.0	26.6	0.002	7.90	0.003	12.27	20.17	20.17	20.17	0.48		
85.0	25.4	0.002	8.01	0.002	12.45	20.47	20.47	20.47	0.49		
90.0	24.3	0.002	8.12	0.002	12.62	20.75	20.75	20.75	0.50		
95.0	23.3	0.001	8.23	0.002	12.79	21.01	21.01	21.01	0.50		
100.0	22.4	0.001	8.33	0.002	12.94	21.27	21.27	21.27	0.51		
105.0	21.6	0.001	8.42	0.002	13.09	21.51	21.51	21.51	0.51		
110.0	20.8	0.001	8.51	0.002	13.23	21.74	21.74	21.74	0.52		
115.0	20.1	0.001	8.60	0.002	13.36	21.96	21.96	21.96	0.52		
120.0	19.5	0.001	8.68	0.002	13.49	22.17	22.17	22.17	0.53		
125.0	18.9	0.001	8.76	0.002	13.62	22.38	22.38	22.38	0.53		
130.0	18.3	0.001	8.84	0.002	13.73	22.57	22.57	22.57	0.54		
135.0	17.8	0.001	8.91	0.002	13.85	22.76	22.76	22.76	0.54		
140.0	17.3	0.001	8.99	0.002	13.96	22.95	22.95	22.95	0.55		
145.0	16.8	0.001	9.05	0.002	14.07	23.12	23.12	23.12	0.55		
150.0	16.4	0.001	9.12	0.002	14.17	23.30	23.30	23.30	0.56		
155.0	15.9	0.001	9.19	0.002	14.27	23.46	23.46	23.46	0.56		
160.0	15.6	0.001	9.25	0.001	14.37	23.62	23.62	23.62	0.56		
165.0	15.2	0.001	9.31	0.001	14.47	23.78	23.78	23.78	0.57		
170.0	14.8	0.001	9.37	0.001	14.56	23.93	23.93	23.93	0.57		
175.0	14.5	0.001	9.43	0.001	14.65	24.08	24.08	24.08	0.57		
180.0	14.2	0.001	9.49	0.001	14.74	24.23	24.23	24.23	0.58		
185.0	13.9	0.001	9.54	0.001	14.83	24.37	24.37	24.37	0.58		
190.0	13.6	0.001	9.60	0.001	14.91	24.51	24.51	24.51	0.58		
195.0	13.3	0.001	9.65	0.001	14.99	24.64	24.64	24.64	0.59		
200.0	13.0	0.001	9.70	0.001	15.07	24.77	24.77	24.77	0.59		
205.0	12.8	0.001	9.75	0.001	15.15	24.90	24.90	24.90	0.59		
210.0	12.6	0.001	9.80	0.001	15.23	25.03	25.03	25.03	0.60		
215.0	12.3	0.001	9.85	0.001	15.30	25.15	25.15	25.15	0.60		
220.0	12.1	0.001	9.89	0.001	15.37	25.27	25.27	25.27	0.60		
225.0	11.9	0.001	9.94	0.001	15.45	25.39	25.39	25.39	0.61		
230.0	11.7	0.001	9.99	0.001	15.52	25.50	25.50	25.50	0.61		
235.0	11.5	0.001	10.03	0.001	15.59	25.62	25.62	25.62	0.61		
240.0	11.3	0.001	10.07	0.001	15.65	25.73	25.73	25.73	0.61		



Modified Rational Method - 100 Year Storm - Chambers

50 The Driveway, Ottawa

File No. UD22-093

City of Ottawa

Date: March 2023

Site Flow and Storage Summary

50 The Driveway, Ottawa

File No: UD22-093

Prepared by: Dimitra Frysali P.E., M.A.Sc

Reviewed by: Nick Moutzouris, P.Eng., M.A.Sc.

100-Year Design Storm		Tributary Area (A1)	ha	C	Tributary Area (A3)	ha	C	Total Storm		Storage	Storage Depth of Chambers
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)	(10)	(11)	(12)
Time	Rainfall Intensity	Storm Runoff (A1 post)	Runoff Volume (A1 post)	Storm Runoff (A3 Post)	Runoff Volume (A3 Post)	Runoff	Volume	Runoff	Volume	Volume	Storage Depth of Chambers
(min)	(mm/hr)	(m ³ /s)	(m ³)	(m ³ /s)	(m ³)	(m ³)	(m ³)	(m ³)	(m ³)	(m ³)	(m)
10.0	178.6	0.014	8.30	0.021	12.89	21.19	21.19	21.19	21.19	0.51	
15.0	142.9	0.011	9.96	0.017	15.47	25.43	25.43	25.43	25.43	0.61	
20.0	120.0	0.009	11.15	0.014	17.32	28.46	28.46	28.46	28.46	0.68	
25.0	103.8	0.008	12.06	0.012	18.74	30.80	30.80	30.80	30.80	0.74	
30.0	91.9	0.007	12.80	0.011	19.90	32.70	32.70	32.70	32.70	0.78	
35.0	82.6	0.006	13.43	0.010	20.86	34.29	34.29	34.29	34.29	0.82	
40.0	75.1	0.006	13.96	0.009	21.70	35.66	35.66	35.66	35.66	0.85	
45.0	69.1	0.005	14.44	0.008	22.43	36.87	36.87	36.87	36.87	0.88	
50.0	64.0	0.005	14.86	0.008	23.08	37.94	37.94	37.94	37.94	0.91	
55.0	59.6	0.005	15.24	0.007	23.67	38.91	38.91	38.91	38.91	0.93	
60.0	55.9	0.004	15.58	0.007	24.21	39.79	39.79	39.79	39.79	0.95	
65.0	52.6	0.004	15.90	0.006	24.70	40.60	40.60	40.60	40.60	0.97	
70.0	49.8	0.004	16.19	0.006	25.16	41.35	41.35	41.35	41.35	0.99	
75.0	47.3	0.004	16.47	0.006	25.58	42.05	42.05	42.05	42.05	1.00	
80.0	45.0	0.003	16.72	0.005	25.98	42.70	42.70	42.70	42.70	1.02	
85.0	43.0	0.003	16.96	0.005	26.36	43.32	43.32	43.32	43.32	1.03	
90.0	41.1	0.003	17.19	0.005	26.71	43.90	43.90	43.90	43.90	1.05	
95.0	39.4	0.003	17.40	0.005	27.04	44.45	44.45	44.45	44.45	1.06	
100.0	37.9	0.003	17.61	0.005	27.36	44.97	44.97	44.97	44.97	1.07	
105.0	36.5	0.003	17.80	0.004	27.66	45.47	45.47	45.47	45.47	1.09	
110.0	35.2	0.003	17.99	0.004	27.95	45.94	45.94	45.94	45.94	1.10	
115.0	34.0	0.003	18.17	0.004	28.23	46.40	46.40	46.40	46.40	1.11	
120.0	32.9	0.003	18.34	0.004	28.50	46.83	46.83	46.83	46.83	1.12	
125.0	31.9	0.002	18.50	0.004	28.75	47.25	47.25	47.25	47.25	1.13	
130.0	30.9	0.002	18.66	0.004	29.00	47.66	47.66	47.66	47.66	1.14	
135.0	30.0	0.002	18.81	0.004	29.23	48.05	48.05	48.05	48.05	1.15	
140.0	29.2	0.002	18.96	0.004	29.46	48.42	48.42	48.42	48.42	1.16	
145.0	28.4	0.002	19.10	0.003	29.68	48.79	48.79	48.79	48.79	1.16	
150.0	27.6	0.002	19.24	0.003	29.90	49.14	49.14	49.14	49.14	1.17	
155.0	26.9	0.002	19.37	0.003	30.10	49.48	49.48	49.48	49.48	1.18	
160.0	26.2	0.002	19.50	0.003	30.31	49.81	49.81	49.81	49.81	1.19	
165.0	25.6	0.002	19.63	0.003	30.50	50.13	50.13	50.13	50.13	1.20	
170.0	25.0	0.002	19.75	0.003	30.69	50.45	50.45	50.45	50.45	1.20	
175.0	24.4	0.002	19.87	0.003	30.88	50.75	50.75	50.75	50.75	1.21	
180.0	23.9	0.002	19.99	0.003	31.06	51.05	51.05	51.05	51.05	1.22	
185.0	23.4	0.002	20.10	0.003	31.23	51.34	51.34	51.34	51.34	1.23	
190.0	22.9	0.002	20.21	0.003	31.41	51.62	51.62	51.62	51.62	1.23	
195.0	22.4	0.002	20.32	0.003	31.57	51.89	51.89	51.89	51.89	1.24	
200.0	22.0	0.002	20.43	0.003	31.74	52.16	52.16	52.16	52.16	1.25	
205.0	21.6	0.002	20.53	0.003	31.90	52.43	52.43	52.43	52.43	1.25	
210.0	21.1	0.002	20.63	0.003	32.05	52.68	52.68	52.68	52.68	1.26	
215.0	20.8	0.002	20.73	0.002	32.21	52.93	52.93	52.93	52.93	1.26	
220.0	20.4	0.002	20.82	0.002	32.36	53.18	53.18	53.18	53.18	1.27	
225.0	20.0	0.002	20.92	0.002	32.50	53.42	53.42	53.42	53.42	1.28	
230.0	19.7	0.002	21.01	0.002	32.65	53.66	53.66	53.66	53.66	1.28	
235.0	19.3	0.001	21.10	0.002	32.79	53.89	53.89	53.89	53.89	1.29	
240.0	19.0	0.001	21.19	0.002	32.93	54.12	54.12	54.12	54.12	1.29	





Water Quality Calculations

50 The Driveway, Ottawa
File No. UD22-093
Date: March 2023

Surface	Method	Effective TSS Removal	Area (ha)	% Area of Controlled Site	Overall TSS Removal
A1, A3, EXT.1	Inherent	80%	0.342	100%	80%
Total			0.342	100%	80%

Note: Uncontrolled water does not account in the above calculations



QUANTITY CONTROL
 Volume required for 100-year event = 98.00 m³
 Tank Area = 70.0 m²

NOTE: TANK DESIGN TO BE VERIFIED BY BUILDING MECHANICAL CONSULTANT



TANK DESIGN
 RESIDENTIAL USE DEVELOPMENT
 50 THE DRIVEWAY
 OTTAWA, ONTARIO

150 Bermondsey Road, Toronto, Ontario M4A 1Y1

DATE: MARCH 2023
 SCALE: N.T.S.

PROJECT No: UD22-093
 FIGURE No: FIG 3

Appendix D

Sanitary Data Analysis



COMBINED SEWER DESIGN SHEET
50 The Driveway
CITY OF OTTAWA

LOCATION	SECTION (ha.)	RESIDENTIAL											COMMERCIAL			INFILTRATION		SEWER DESIGN						
		SINGLE FAMILY DWELLING @ 3.4 ppu	SEMI-DETACHED / TOWNHOUSE (ROW) @ 2.7 ppu	DUPLEX @ 2.3 ppu	BACHELOR @ 1.4 ppu	1 BED @ 1.4 ppu	2 BED @ 2.1 ppu	3 BED @ 3.1 ppu	AVERAGE APT. @ 1.8 ppu	TOTAL RESIDENTIAL POPULATION	AVERAGE RES. FLOW @ 280 L/c/d (L/s)	HARMON PEAKING FACTOR	RES. PEAK FLOW (L/s)	INSTITUTIONAL AREA (ha.)	AVERAGE INSTITUTIONAL FLOW @ 50000/L/ha/d (L/s)	INSTITUTIONAL PEAK FLOW (L/s)	TOTAL ACCUM. AREA (ha.)	INFILT. @ 0.28 L/s/ha. (L/s)	TOTAL DESIGN FLOW (L/s)	PIPE LENGTH (m)	PIPE DIA. (mm)	SLOPE (%)	FULL FLOW CAPACITY n = 0.013 (L/sec)	% of DESIGN CAPACITY (%)
column number	(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)	(10)	(11)	(12)	(13)	(14)	(15)	(16)	(17)	(18)	(19)	(20)	(21)	(22)	(23)	(24)
Existing Condition																								
Institutional (towards QED ROW)	0.296	0	0	0	0	0	0	0	0	0.00	0.00	4.00	0.00	0.10	0.06	0.08	0.296	0.083	0.17	-	-	-	-	-
Proposed Condition																								
Residential-use development (towards QED ROW)	0.296	0	0	0	0	23	54	0	0	146	0.47	4.00	1.89	0.00	0.00	0.00	0.296	0.083	1.97		200	2.0%	46.38	4.25%
Average Residential Flow Rate - 280 Litres / capita / day											Infiltration Allowance (Dry Weather) - 0.05 Litres / s / gross ha													
Average Daily Flow Commercial - 50,000 Litres / gross ha / day											Infiltration Allowance (Wet Weather) - 0.28 Litres / s / gross ha													
Average Daily Flow Institutional - 50,000 Litres / gross ha / day											Infiltration Allowance (Total I/I) - 0.33 Litres / s / gross ha													
Average Daily Flow Industrial - 35,000 Litres / gross ha / day											Peaking Factor = $1 + [14 / (4 + P^{0.5})]$, P=Population in thousands													
Site Area: 0.296 Ha											Total Net Flow towards QED ROW= 1.80													



Prepared By: Dimitra Frysalis, P. E., M.A.Sc.
 Reviewed by: Nick Moutzouris, P.Eng., M.A.Sc.
 Date: March 2023

Project: 50 The Driveway
 Project: UD22-093
 City of Ottawa

Appendix E

Water Data Analysis



WATER DEMAND

50 The Driveway, Ottawa

File No: UD22-093

Date: March 2023

Prepared by: Dimitra Frysali, P.E., M.A.Sc.

Reviewed By: Nick Moutzouris, P.Eng., M.A.Sc.

Fire Flow Calculation

1 $F = 220 C (A)^{1/2}$

Where F= Fire flow in Lpm

C= construction type coefficient

= 0.8 for non combustible

A = total floor area in sq.m. excluding basements

	Area Applied
Level 2= 1592.17 m ²	100%
Level 1= 1588.64 m ²	25%
Level 3= 1350.35 m ²	25%
= 2,326.9 sq.m.	
F = 8,489.91 L/min	$F(No.1) = 200C \sqrt{A}$
F = 8,000 L/min	$F(No.1)$ Round to nearest 1000 l/min

Note: The levels indicated, reference the floors with the largest areas (refer to architectural design)

2 Occupancy Reduction

15% reduction for limited-combustible occupancy

F = 6800 L/min $F(No.2) = F(No.1) \times \text{occupancy reduction/charge}(\%)$

3 Sprinkler Reduction

30% Reduction for NFPA Sprinkler System

F = 4760 l/min $F(No.3) = F(No.2) \times \text{sprinkler reduction}(\%)$

4 Separation Charge

0% West >45m

5% North 30.1m to 45m

11% South 10.1m to 20m

11% East 10.1m to 20m

27% Total Separation Charge

F = 1,836.00 L/min $F(No.4) = F(No.2) \times \text{separation charge}(\%)$

F = 6,596.00 L/min $F(tot) = F(No.3) + F(No.4)$

F = 7,000 L/min $F(tot)$ Round to nearest 1000 l/min

116.67 L/s

F = 1849 US GPM

Domestic Flow Calculations

Population=	146 Persons	From Sanitary Calculations
Commercial Area (Retail) =	0.0 m ²	From Site Statistics
Average Day Demand (Residential) =	350.0 L/person/day	
Average Day Demand (Commercial) =	2.5 L/m ² /day (OBC)	1 US Gallon=3.785 L
Average Residential Water Demand=	0.59 L/s	
	9 US GPM	1L/s=15.852 US GPM
Average Commercial Water Demand=	0.00 L/s	
	0.00 US GPM	

Max. Daily Residential Demand Peaking Factor= 2.5

Max. Daily Commercial Demand Peaking Factor = 1.5

Max. Daily Demand = 1.48 L/s = 23 US GPM

or

Max. Hourly Residential Demand Peaking Factor = 2.2

Max. Hourly Commercial Demand Peaking Factor = 1.8

Max. Hourly Demand = 3.25 L/s = 52 US GPM


Max Daily Demand = 1.48 L/s

Fire Flow = 116.67 L/s

Required 'Design' Flow = 118.15 L/s
1873 US GPM

Note: Required 'Design' Flow is the maximum of either:

- 1) Fire Flow + Maximum Daily Demand
- 2) Maximum Hourly Demand



SEPARATION DISTANCES
RESIDENTIAL USE DEVELOPMENT
50 THE DRIVEWAY
OTTAWA, ONTARIO

DATE:	MARCH 2023	PROJECT No:	UD22-093
SCALE:	N.T.S.	FIGURE No:	FIG 4



DISTANCE FROM FIRE HYDRANT
RESIDENTIAL USE DEVELOPMENT
50 THE DRIVEWAY
OTTAWA, ONTARIO

DATE:	MARCH 2023	PROJECT No:	UD22-093
SCALE:	N.T.S.	FIGURE No:	FIG 5

From: sarrak <sarrak@lithosgroup.ca>
Sent: Tuesday, March 14, 2023 3:30 PM
To: dimitraf
Subject: Fwd: 50 The Driveway - Water Servicing
Attachments: 50 The Driveway March 2023.pdf; Tech bulletin ISTB-2018-02.pdf

Begin forwarded message:

From: Fawzi, Mohammed <mohammed.fawzi@ottawa.ca>
Date: 14 Mar 2023 at 9:09 μ.μ.
To: sarrak@lithosgroup.ca <sarrak@lithosgroup.ca>
Cc: Fel Petti <fel@mainandmain.ca>
Subject: RE: 50 The Driveway - Water Servicing

Hi Sarra,

The following are boundary conditions, HGL, for hydraulic analysis at 50 The Driveway (zone 1W) assumed to be connected to the 152 mm on Lewis Street (see attached PDF for location).

Minimum HGL: 106.4 m

Maximum HGL: 115.4 m

Max Day + Fire Flow (116.67 L/s:) 104.6 m

These are for current conditions and are based on computer model simulation.

Disclaimer: The boundary condition information is based on current operation of the city water distribution system. The computer model simulation is based on the best information available at the time. The operation of the water distribution system can change on a regular basis, resulting in a variation in boundary conditions. The physical properties of watermains deteriorate over time, as such must be assumed in the absence of actual field test data. The variation in physical watermain properties can therefore alter the results of the computer model simulation.

If you also refer to Tech Bulletin ISTB-2018-02 Appendix I (attached), please also complete the Hydrant Capacity requirement. It is simply calculating the available flow from all hydrants within a 150m radius of the subject site and calculating the available flow from the hydrants with respect to their classes and distance, all specified in the bulletin attached.

Boundary Conditions for 50 The Driveway

