

# **Site Servicing & Stormwater Management Report**

**Commercial Development**

**3845 Cambrian Road**

**Ottawa, Ontario**

# Table of Contents

1.0 INTRODUCTION .....	2
2.0 PURPOSE.....	2
3.0 EXISTING CONDITIONS .....	3
4.0 PROPOSED DEVELOPMENT.....	3
5.0 STORMWATER MANAGEMENT PLAN .....	3
5.1 Pre-Development Conditions .....	4
5.2 Post-Development Conditions.....	4
5.2.1 100-year Site Storage Requirements .....	5
6.0 STORM SEWERS AND SWM SYSTEM .....	5
6.1 Storm Sewers.....	5
6.2 SWM System.....	6
7.0 SANITARY SEWER .....	6
8.0 WATER SERVICING.....	6
9.0 EROSION AND SEDIMENT CONTROL DURING CONSTRUCTION .....	7
10.0 CONCLUSIONS .....	7

## List of Tables

Table 1 - ICD Schedule .....	5
Table 2 - Building Water Demands and Fire Flow .....	6

## List of Figures

Figure 1 – Site Context.....	2
------------------------------	---

## List of Appendices

- Appendix A: Stormwater Management Calculations
- Appendix B: Storm and Sanitary Sewer Computation Forms
- Appendix C: Sanitary Load and Fire Flow
- Appendix D: Stormwater Storage Chambers Specifications
- Appendix E: City Correspondence
- Appendix F: WaterCad Model Results

## Drawings

- Drawing C101 | Erosion/Sediment Control & Removals Plan
- Drawing C102 | Site Servicing Plan
- Drawing C103 | Grading Plan
- Drawing C104 | Detail Page 1
- Drawing C105 | Detail Page 2
- Drawing C106 | Post Development Drainage Plan

## 1.0 INTRODUCTION

Parsons Inc. was retained by Loblaw Properties Limited to provide engineering services for a new commercial development located at 3845 Cambrian Road in Ottawa, Ontario.

The site encompasses a total area of approximately 1.50 ha and is bordered by Cambrian Road to the north, future residential development to the south (currently vacant), future school to the west (currently vacant) and the future re-aligned Greenbank Road to the east as shown on the following figure.

The proposed development includes the addition of a retail store and another commercial rental unit on the same lot. Servicing of the buildings will be provided by the new on-site storm sewers, sanitary services, and new water services from Cambrian Road. New fire hydrants will be added on-site to provide exterior fire protection.

Figure 1 – Site Context



## 2.0 PURPOSE

This report summarizes the proposed site servicing, grading and drainage design, documents the proposed method of attenuating stormwater runoff from the subject site, and deals with erosion and sediment control measures to be undertaken during construction.

Stormwater management items addressed include the following:

- establishing the allowable post-development release rate from the site;
- calculating the post-development runoff from the site;
- determining the required on-site stormwater storage volume and storage areas.

### 3.0 EXISTING CONDITIONS

The subject site is currently vacant. The proposed commercial development is part of the Half Moon Bay West Subdivision. As mentioned earlier, on the east site of the proposed development, will be the future re-aligned Greenbank Road. Currently, there is no access to the subject site from Greenbank Road. Cambrian Road is currently the only access to the subject site. Cambrian Road will be widened as part of the new Greenbank Road project. Addition of sidewalks and bike lanes is also proposed as part of this future project. A new 1500mm storm sewer, 500mm sanitary sewer and 400mm watermain have been installed in 2019 along Cambrian Road and will be used to provide services to the proposed commercial development. A 750mm storm service, 200mm sanitary service and a 200mm water service have also been installed in 2019 up to the property line to service this future development from Cambrian Road. Refer to **Drawing C102** for more details.

According to the geotechnical investigation report for this development, by Toronto Inspection Limited dated November 17, 2018, soil condition on this site consists of a mixture of organic and silty material fill extending to a depth between 1.5m to 3.7m with an underlayer of very soft silty clay/clayey silt up to 21.0m deep. Also, the average on-site groundwater table is estimated at an elevation of 92.20m. Existing site surface elevation varies between 92.42m and 96.67m. There is also an existing large pile of dirt directly adjacent to the western property line with a maximum elevation of 99.35m

### 4.0 PROPOSED DEVELOPMENT

As shown on the Architectural Site Plan, the proposed development will consist of a new 3205 m<sup>2</sup> retail store (Building A) and a commercial rental unit of 483 m<sup>2</sup> (Building B). The finished floor elevation of Building A and B are set at 94.05m and 94.12m respectively. Each building is considerably higher than the estimated groundwater table elevation. The proposal will also include parking spaces, concrete sidewalks, concrete curbs, a new entrance from Cambrian Road and an entrance from the future Greenbank Road.

The site grading will match the existing conditions along the south and west side of the subject site with maximum 3H:1V slopes. Grading along Cambrian Road and future Greenbank Road will be coordinated with the future project to plan a smooth transition in the future, however at this time the grading will tie-in to existing conditions. The limit of grading outside of the site is shown on **Drawing C103**.

### 5.0 STORMWATER MANAGEMENT PLAN

**Drawing C106**, appended to this report, depict the boundaries of the post-development drainage areas, and should be read in conjunction with this report.

The design approach for the stormwater management is to ensure that the post-development peak flows do not exceed the allowable release rate to mitigate the risk of flooding and against erosion. The City of Ottawa indicated that the allowable release rate for this site was determined in the *Design Brief for the Half Moon Bay West Phase 1, prepared by DSEL, dated September 5, 2018*. Correspondence with the City can be found in **Appendix E**. The storm sewers installed as part of this new subdivision project are sized to allow a flow of **347.6 L/s** for the proposed commercial development. Parameters used to calculate the allowable release rate are from the DSEL report.

- Runoff Coefficient (C) = 0.80
- Drainage Area (A) = 1.50 ha
- Time of Concentration (Tc) = 10min

The Rational Method formula has been used to calculate stormwater runoff and rainfall data is based on the IDF curve equations from the *Ottawa Sewer Design Guidelines, Second Edition, October 2012*.

$$Q = 2.78 CIA, \text{ where:}$$

Q = Flow rate (L/s)  
C = Runoff coefficient  
I = Rainfall intensity (mm/hr)  
A = Area (ha)



Rainfall intensity:  $I_5 = 998.071 / (T_c + 6.053)^{0.814}$

Using the Rational Method formula and the above parameters, the allowable post-development release rate for this site is **347.6 L/s**.

## 5.1 Pre-Development Conditions

As mentioned earlier, the subject site is currently vacant. Based on the topographical survey received, the site grading is relatively similar through the site and is lower along the north, south and east property lines. On the west side of the site, a major pile of dirt with a height up to 5.0m is present. A drainage ditch used to flow through this site, however this ditch was abandoned as part of the construction of new infrastructure along Cambrian Rd and future Greenbank Rd. Services for this property were installed in 2019. A Storm maintenance hole (MHST) with a 750mm pipe was installed near the property line along Cambrian Rd to collect part of the runoff from this site.

## 5.2 Post-Development Conditions

The following is a description of each drainage area through the site, refer to **Drawing C106** attached to this report.

- Areas WS-01 and WS-02 consist of the controlled roof areas;
- Areas WS-03 to WS-05 are located behind and to the west of Building A;
- Areas WS-06 to WS-09 consist of the main parking lot area;
- Area WS-10 is the site entrance from Cambrian Road;
- Areas WS-11 and WS-12 are the parking lot and refuse disposal area located between Building B and the site entrance from Cambrian Road;
- Area WS-13 is the proposed swale on the corner the Cambrian and future Greenbank intersection, located behind the future Greenbank sidewalk;
- Areas WS-14 to WS-16 consist of areas located outside of the site to the west that will drain temporarily towards the site due to the presence of the large dirt pile. It is assumed that this major dirt pile will be removed as part the development of the neighbouring property.

Since this project will be constructed before the new re-aligned Greenbank Rd, the grading of the site must match existing surface elevations at the property line while also considering the future Greenbank Rd project proposed sidewalk and road profile. Due to the important variation in grades between existing conditions and future conditions along Cambrian Rd and Greenbank Rd, grading along all property lines will match existing condition with a maximum slope of 3H:1V. This means that a small portion of this site will drain uncontrolled towards the public right of way. The uncontrolled area of this site is estimated at 0.059 ha and generates a flow of 4.9 L/s and 10.5 L/s for the 5-year and 100-year storm event respectively.

All other areas on-site will be captured through a new on-site storm sewer system.

For the purpose of calculating the average runoff coefficients for the post-development areas, the following guidelines were used:

- Landscaped surfaces (grass, trees, shrubs, etc.) C = 0.20
- Impervious surfaces (asphalt, concrete, pavers, rooftops, etc.) C = 0.90
- The runoff coefficient for 100-year event is increased by 25% based on the Ottawa Sewer Design Guidelines.

**Appendix A** "Stormwater Management Calculations" provides a summary of the post-development areas and average runoff coefficients.

An inlet control device (ICD) is required to control the flows from the site to the allowable release rate of **347.6 L/s** for the 100-year post development storm event. The equivalent storage to attenuate the 100-year post-development flow has been calculated to be **129.9 m<sup>3</sup>** in addition to the rooftop storage provided on each building. The required storage will be provided by the storm pipes, the structures and by new proposed underground storage chambers. The calculations are shown in **Appendix A**.

Storage requirements to attenuate the 100-year post-development flow rate are given below:

### 5.2.1 100-year Site Storage Requirements

The 100-year post-development flow will be captured within the subsurface storage system. Below grade storage will be provided by storm structures, pipes, and mainly underground storm chambers. All roof areas will also be controlled to provide additional storage. The design will utilize **129.9 m<sup>3</sup>** of storage in the underground storage system. The proposed system is the StormTech SC-740 or equivalent, see **Appendix D** for specifications. The bottom of the proposed chambers is set above the estimated groundwater table elevation (92.20m). Perforated subdrains will be placed on the perimeter of the storm chambers, directly above the elevation 92.20m to collect infiltration from the chambers and redirect it to the storm outlet.

As the uncontrolled area of the site generates a flow of 10.5 L/s for the 100-year storm event, the allowable discharge at the proposed ICD located in MHST-37 is limited at **337.1 L/s**. The design head was calculated as the delta in height between the centre of the orifice and the hydraulic grade line (HGL) for the 100-year event within the underground storage chambers which is equivalent to the 100-year storage elevation. The orifice outlet flow has been calculated based on the MTO Drainage Management Manuel, Part 3, Chapter 8, p.127:

- $Q_{\text{orifice}} \text{ (m}^3\text{/s)} = C_d A (2gH)^{0.5}$

where:

$C_d$  = coefficient of discharge (0.62)

$A$  = Area of orifice opening in m<sup>2</sup>

$g$  = acceleration due to gravity (9.81 m/s<sup>2</sup>)

$H$  = difference in height between 2y HGL and centre of the orifice in metres

See **Appendix A** for detailed pipe outlet calculations and **Drawing C104** for ICD detail.

The **Table 1** lists all the requirements for the manufacturer to design the appropriate ICD.

Table 1 - ICD Schedule

ICD ID	Location	Outlet Diameter (mm)	Flow 5y/100y (L/s)	Head 5y/100y (m)	Equivalent Diameter (mm)	Model
1	MHST-37	750	287.0/337.1	2.03/2.80	305	FRAME & PLATE

## 6.0 STORM SEWERS AND SWM SYSTEM

### 6.1 Storm Sewers

Calculations showing the storm sewer capacities are appended to this report under **Appendix B** "Storm Sewer Computation Forms". The storm sewer design spreadsheet is based on the Rational Method and Manning formula and was used to calculate the design flow and required pipe sizes. Capacity required for proposed storm sewers is based on the 5-year rainfall intensity obtained from the Ottawa Sewer Design Guidelines, where  $T_c$  is the time of concentration:

- $I_5 \text{ (mm/hr)} = 998.071 / (T_c + 6.053)^{0.814}$

**Drawing C106** shows the proposed drainage areas. Details including pipe lengths, sizes, materials, inverts elevations and structure types are shown on **Drawing C102**.

## 6.2 SWM System

As mentioned above, the SWM system includes an ICD in MHST-37 that will control the flow to a maximum of **337.1 L/s**. The total allowable discharge from the site is **347.6 L/s** including uncontrolled areas. Any additional flow will be store on-site using underground storage chambers and the piping system. The site stormwater runoff ultimately discharges to the Jock River. There is no on-site stormwater quality treatment required as the runoff from the site is conveyed to the Clarke Pond before discharging in the Jock River. The Clarke Pond was designed and constructed to provide a minimum of 80% TSS removal for all stormwater generated from the Half Moon Bay West Subdivision.

## 7.0 SANITARY SEWER

The new commercial buildings within the proposed development will be served with a new on-site sanitary system. Each building will have its own sanitary service. The on-site sanitary system will be connected to the existing sanitary service previously installed for this future development located at the property line along Cambrian Road. The peak sanitary flow for the proposed commercial development is calculated to be **0.67 L/s**, including infiltration. The sanitary load calculations can be found in **Appendix C**. The additional flow from the commercial development to the municipal sanitary sewer was accounted for in the Half Moon Bay Subdivision design. Thus, the capacity of the downstream sanitary sewer is considered adequate. The Sanitary Sewer Computation Sheet is included in **Appendix B**. Details concerning the existing and proposed pipe lengths and locations are shown on the site servicing plan.

## 8.0 WATER SERVICING

Water servicing and fire protection for the proposed commercial development will be provided by a new on-site 200mm watermain connected to the existing 400mm watermain on Cambrian Road. Two new fire hydrants will be installed on-site to provide exterior fire protection. Details regarding the new and existing watermain service connection pipe size and location are shown on **Drawing C102**. Both proposed buildings are expected to have interior sprinklers systems, thus the water services for these building will be a 200mm diameter.

The water demands for the proposed development are listed in **Table 2**. The fire flow was calculated using the Fire Underwriters Survey (FUS, 2020) method. Calculation details can be found in **Appendix C**.

Table 2 - Building Water Demands and Fire Flow

	Average Daily Demand (L/s)	Max Daily Demand (L/s)	Peak Hourly Demand (L/s)	Fire Flow Demand (L/s)	Max Daily + Fire Flow Demand (L/s)
Building A	0.10	0.16	0.28	83.0	83.16
Building B	0.02	0.02	0.04	33.0	33.02

Boundary conditions were obtained from the City on April 21, 2023, and are presented in **Appendix E**. Based on the information received, a water model was created using WaterCad to confirm that the proposed watermain and fire hydrants were able to provide domestic and fire flow demands while maintaining adequate pressure in the system. The water model shows that the proposed system has the required capacity to provide domestic and fire protection demands. However, for the average day demand, the pressure in the system is over 550 kPa (80 psi) meaning that each building water connection will require water pressure reducing valve installed directly downstream of the water meter inside the building. Water model results are shown in **Appendix F**.

Also, to avoid water quality issues due to the watermain dead end at the connection to Building A, the second fire hydrant was placed at the back of Building A, near the connection to the building, so that any accumulation of debris or sediments can be flushed from the water line.

## 9.0 EROSION AND SEDIMENT CONTROL DURING CONSTRUCTION

To mitigate the impacts due to erosion and sedimentation during construction, erosion and sediment control measures shall be installed and maintained throughout the duration of construction.

Measures shall only be removed once the construction activities are complete, and the site has stabilized.

The measures will include but are not limited to:

- Siltsack® shall be installed between the frame and cover of existing and new catchbasins and maintenance holes, to minimize sediments entering the storm drainage system.
- All grassed areas must be completed prior to the removal of the Siltsack® in catch basins and maintenance holes.
- Light Duty Silt Fence Barriers placed around the perimeter of the site where necessary, installed and maintained according to OPSS 577 and OPSD 219.110.
- Construction mud mat at site entrance along Cambrian Rd to minimize the amount of mud carried out of the site.

Refer to **Drawing C101** notes for more details.

## 10.0 CONCLUSIONS

The 100-year storm event peak flow will be controlled to an allowable discharge of **347.6 L/s**. Stormwater storage is provided up to and including the 100-year storm in underground chambers and on building rooftops prior to discharging to the municipal storm sewer system. On-site stormwater quality treatment is not required as this site is part of the area serviced by the Clarke Pond.

The water servicing of the building addition will be provided by a new on-site 200mm watermain with two new fire hydrants. The maximum fire flow of the two proposed building was estimated at **83.0 L/s**. A water model was used to confirm that adequate pressure in the system could be maintained during a fire flow demand. However, pressure in the City system during average day demands is too high and will trigger the addition of pressure reducing valves inside the buildings.

The sanitary servicing of the site will be provided by an on-site sanitary sewer connected to the existing 500mm sanitary along Cambrian Rd. The peak sanitary flow for the proposed development, including infiltration, is calculated to be **0.67 L/s**.

Grading and drainage measures will ensure proper drainage of the site, while erosion and sediment control measures will minimize downstream impacts due to construction activities.

We look forward to receiving approval of this report and the appended plans from the City of Ottawa in order to proceed with construction of the site.

Prepared by:

Reviewed by:



Benoit Villeneuve, P.Eng., ing.

A handwritten signature in black ink, appearing to read "Mathew Theiner".

Mathew Theiner, P.Eng., ing.

**Appendix A:  
Stormwater Management Calculations**



**TABLE I - ALLOWABLE RUNOFF CALCULATIONS BASED ON EXISTING CONDITIONS**

Area Description	Area (ha)	Time of Conc, Tc (min)	Minor Storm			
			Storm = 5 yr	I <sub>5</sub> (mm/hr)	C <sub>AVG</sub>	Q <sub>ALLOW</sub> (L/s)
EWS-01	1.50	10	Storm = 5 yr	104.19	0.80	<b>347.6</b>
<b>TOTAL</b>	<b>1.50</b>					<b>347.6</b>

Allowable Capture Rate is based the Design Brief for the Half Moon Bay West Phase 1, prepared by DSEL, Project #16-888, dated September 5, 2018

5-year Storm                      C<sub>ASPH/ROOF/CONC</sub> = 0.90                      C<sub>GRASS</sub> = 0.20  
 100-year Storm                      C<sub>ASPH/ROOF/CONC</sub> = 1.00                      C<sub>GRASS</sub> = 0.25

**TABLE II - POST-DEVELOPMENT AVERAGE RUNOFF COEFFICIENTS**

Watershed Area No.	Impervious Areas (m <sup>2</sup> )	A * C <sub>ASPH</sub>	Pervious Areas (m <sup>2</sup> )	A * C <sub>GRASS</sub>	Sum AC	Total Area (m <sup>2</sup> )	C <sub>AVG</sub> (5yr)	C <sub>AVG</sub> (100yr)
WS-01*	3200.00	2880	0.00	0	2880	3200	0.90	1.00
WS-02*	490.00	441	0.00	0	441	490	0.90	1.00
WS-03	326.00	293	0.00	0	293	326	0.90	1.00
WS-04	440.00	396	239.00	48	444	679	0.65	0.82
WS-05	1714.00	1543	368.00	74	1616	2082	0.78	0.97
WS-06	1614.00	1453	183.00	37	1489	1797	0.83	1.00
WS-07	1489.00	1340	0.00	0	1340	1489	0.90	1.00
WS-08	1280.00	1152	155.00	31	1183	1435	0.82	1.00
WS-09	1354.00	1219	192.00	38	1257	1546	0.81	1.00
WS-10	220.00	198	307.00	61	259	527	0.49	0.62
WS-11	520.00	468	23.00	5	473	543	0.87	1.00
WS-12	125.00	113	0.00	0	113	125	0.90	1.00
WS-13	0.00	0	100.00	20	20	100	0.20	0.25
WS-14**	0.00	0	498.00	100	100	498	0.20	0.25
WS-15**	0.00	0	486.00	97	97	486	0.20	0.25
WS-16**	0.00	0	275.00	55	55	275	0.20	0.25
WS-Unc***	75.00	68	510.00	102	170	585	0.29	0.36
<b>Total</b>	<b>12847</b>		<b>2065</b>		<b>11908</b>	<b>16183</b>		

\* Roof top storage Areas  
 \*\*External flow from neighbouring property  
 \*\*\*Uncontrolled Areas

**TABLE III - TOTAL RUNOFF COEFFICIENT FOR CONTROLLED AREAS (EXCLUDING ROOF TOP AREAS)**

$C_{AVG(5yr)} = \frac{\text{Sum AC}}{\text{Total Area}} = \frac{8\ 739}{11\ 908} = 0.73$	$C_{AVG(100yr)} = 0.92$
--	-------------------------

**TABLE IV - SUMMARY OF POST-DEVELOPMENT RUNOFF**

Area No	Area (ha)	Storm = 5 yr				Storm = 100 yr			
		I <sub>5</sub> (mm/hr)	C <sub>AVG(5yr)</sub>	Q <sub>GEN</sub> (L/s)	Q <sub>CONT</sub> (L/s)	I <sub>100</sub> (mm/hr)	C <sub>AVG(100yr)</sub>	Q <sub>GEN</sub> (L/s)	Q <sub>CONT</sub> (L/s)
WS-01*	0.320	104.19	0.90	83.4	287.0	178.56	1.00	158.8	337.1
WS-02*	0.049	104.19	0.90	12.8		178.56	1.00	24.3	
WS-03	0.033	104.19	0.90	8.5		178.56	1.00	16.2	
WS-04	0.068	104.19	0.65	12.9		178.56	0.82	27.5	
WS-05	0.208	104.19	0.78	46.8		178.56	0.97	100.3	
WS-06	0.180	104.19	0.83	43.1		178.56	1.00	89.2	
WS-07	0.149	104.19	0.90	38.8		178.56	1.00	73.9	
WS-08	0.144	104.19	0.82	34.3		178.56	1.00	71.2	
WS-09	0.155	104.19	0.81	36.4		178.56	1.00	76.7	
WS-10	0.053	104.19	0.49	7.5		178.56	0.62	16.1	
WS-11	0.054	104.19	0.87	13.7		178.56	1.00	27.0	
WS-12	0.013	104.19	0.90	3.3		178.56	1.00	6.2	
WS-13	0.010	104.19	0.20	0.6		178.56	0.25	1.2	
WS-14**	0.050	104.19	0.20	2.9		178.56	0.25	6.2	
WS-15**	0.049	104.19	0.20	2.8		178.56	0.25	6.0	
WS-16**	0.028	104.19	0.20	1.6		178.56	0.25	3.4	
WS-Unc***	0.059	104.19	0.29	4.9	4.9	178.56	0.36	10.5	
<b>Total</b>	<b>1.618</b>			<b>354.2</b>	<b>291.9</b>		<b>714.9</b>	<b>347.6</b>	

\* Roof top storage Areas  
 $I_5 = 998.071 / (Tc+6.053)^{0.814}$   
 $I_{100} = 1735.688 / (Tc+6.014)^{0.820}$   
 Time of concentration (min), Tc = 10 mins

**Table V - Storage Volumes (5-Year and 100-Year Storm Events)**

**Site Storage Requirement**

$C_{AVG} = 0.73$  (5-year)  
 $C_{AVG} = 0.92$  (100-year)  
 Time Interval = 5 (mins)  
 Drainage Area = 1.163 (hectares)

Duration (min)	Release Rate = <u>287.0</u> (L/sec) Return Period = <u>5</u> (years) IDF Parameters, A = <u>998.071</u> , B = <u>0.814</u> $I = A/(T_c+6.199)^B$						Release Rate = <u>337.1</u> (L/sec) Return Period = <u>100</u> (years) IDF Parameters, A = <u>1735.688</u> , B = <u>0.820</u> $I = A/(T_c+6.014)^B$					
	Rainfall Intensity, I (mm/hr)	Peak Flow (L/sec)	Peak Flow from Roof (L/sec)	Release Rate (L/sec)	Storage Rate (L/sec)	Storage (m <sup>3</sup> )	Rainfall Intensity, I (mm/hr)	Peak Flow (L/sec)	Peak Flow from Roof (L/sec)	Release Rate (L/sec)	Storage Rate (L/sec)	Storage (m <sup>3</sup> )
0	-	-	-	-	-	-	-	-	-	-	-	-
5	141.2	335.1	18.2	287.0	66.3	19.9	242.7	720.0	23.8	337.1	406.8	122.0
10	104.2	247.3	18.2	287.0	-21.5	-12.9	178.6	529.7	23.8	337.1	216.5	129.9
15	83.6	198.3	18.2	287.0	-70.5	-63.4	142.9	423.9	23.8	337.1	110.7	99.6
20	70.3	166.7	18.2	287.0	-102.0	-122.5	120.0	355.9	23.8	337.1	42.6	51.1
25	60.9	144.5	18.2	287.0	-124.2	-186.4	103.8	308.1	23.8	337.1	-5.2	-7.8
30	53.9	128.0	18.2	287.0	-140.8	-253.4	91.9	272.5	23.8	337.1	-40.7	-73.3
35	48.5	115.1	18.2	287.0	-153.6	-322.6	82.6	245.0	23.8	337.1	-68.3	-143.4
40	44.2	104.9	18.2	287.0	-163.9	-393.4	75.1	222.9	23.8	337.1	-90.3	-216.8
45	40.6	96.4	18.2	287.0	-172.3	-465.3	69.1	204.8	23.8	337.1	-108.4	-292.7
50	37.7	89.4	18.2	287.0	-179.4	-538.2	64.0	189.7	23.8	337.1	-123.5	-370.6
55	35.1	83.4	18.2	287.0	-185.4	-611.9	59.6	176.9	23.8	337.1	-136.4	-450.0
60	32.9	78.2	18.2	287.0	-190.6	-686.1	55.9	165.8	23.8	337.1	-147.4	-530.8
65	31.0	73.7	18.2	287.0	-195.1	-760.9	52.6	156.2	23.8	337.1	-157.1	-612.6
70	29.4	69.7	18.2	287.0	-199.1	-836.1	49.8	147.7	23.8	337.1	-165.5	-695.3
75	27.9	66.2	18.2	287.0	-202.6	-911.6	47.3	140.2	23.8	337.1	-173.1	-778.8
80	26.6	63.0	18.2	287.0	-205.7	-987.5	45.0	133.5	23.8	337.1	-179.8	-862.9
85	25.4	60.2	18.2	287.0	-208.6	-1063.7	43.0	127.4	23.8	337.1	-185.8	-947.7
90	24.3	57.6	18.2	287.0	-211.1	-1140.1	41.1	122.0	23.8	337.1	-191.3	-1033.0
95	23.3	55.3	18.2	287.0	-213.5	-1216.7	39.4	117.0	23.8	337.1	-196.3	-1118.7
100	22.4	53.2	18.2	287.0	-215.6	-1293.6	37.9	112.4	23.8	337.1	-200.8	-1204.8
105	21.6	51.2	18.2	287.0	-217.5	-1370.6	36.5	108.3	23.8	337.1	-205.0	-1291.4
110	20.8	49.4	18.2	287.0	-219.4	-1447.7	35.2	104.4	23.8	337.1	-208.8	-1378.2
115	20.1	47.8	18.2	287.0	-221.0	-1525.0	34.0	100.9	23.8	337.1	-212.4	-1465.4
120	19.5	46.2	18.2	287.0	-222.6	-1602.5	32.9	97.6	23.8	337.1	-215.7	-1552.8
Max =						<b>19.9</b>						<b>129.9</b>

**Notes**

- 1) Peak flow is equal to the product of 2.78 x C x I x A
- 2) Rainfall Intensity,  $I_5 = A/(T_c+6.053)^B$  &  $I_{100} = A/(T_c+6.014)^B$
- 3) Release Rate = LESSER of Min (Release Rate, Peak Flow) - Minus 100 Year Flow Of Uncontrolled Areas OR Pipe Outlet Capacity
- 4) Storage Rate = Peak Flow - Release Rate
- 5) Storage = Duration x Storage Rate
- 6) Maximum Storage = Max Storage Over Duration

**Table VI - Storage Volumes (5-Year and 100-Year Storm Events)**

**Storage Requirement for Roof Area Building A**

$C_{AVG} = 0.90$  (5-year)  
 $C_{AVG} = 1.00$  (100-year)  
 Time Interval = 5 (mins)  
 Drainage Area = 0.032 (hectares) per drain  
Zurn Z105 Control-Flo Single Notch  
Number of Drains = 10  
Total Release Rate 5 year = 15.25 L/s  
Total Release Rate 100 year = 19.96 L/s

Duration (min)	5-Year Storm Event					100-Year Storm Event				
	Rainfall Intensity, I (mm/hr)	Peak Flow (L/sec)	Release Rate (L/sec)	Storage Rate (L/sec)	Storage (m <sup>3</sup> )	Rainfall Intensity, I (mm/hr)	Peak Flow (L/sec)	Release Rate (L/sec)	Storage Rate (L/sec)	Storage (m <sup>3</sup> )
0	-	-	-	-	-	-	-	-	-	-
5	141.2	11.3	1.5	9.8	2.9	242.7	21.6	2.0	19.6	5.9
10	104.2	8.3	1.5	6.8	4.1	178.6	15.9	2.0	13.9	8.3
15	83.6	6.7	1.5	5.2	4.6	142.9	12.7	2.0	10.7	9.6
20	70.3	5.6	1.5	4.1	4.9	120.0	10.7	2.0	8.7	10.4
25	60.9	4.9	1.5	3.4	5.0	103.8	9.2	2.0	7.2	10.9
30	53.9	4.3	1.5	2.8	5.0	91.9	8.2	2.0	6.2	11.1
35	48.5	3.9	1.5	2.4	5.0	82.6	7.3	2.0	5.4	11.2
40	44.2	3.5	1.5	2.0	4.8	75.1	6.7	2.0	4.7	11.3
45	40.6	3.3	1.5	1.7	4.7	69.1	6.1	2.0	4.1	11.2
50	37.7	3.0	1.5	1.5	4.5	64.0	5.7	2.0	3.7	11.1
55	35.1	2.8	1.5	1.3	4.2	59.6	5.3	2.0	3.3	10.9
60	32.9	2.6	1.5	1.1	4.0	55.9	5.0	2.0	3.0	10.7
65	31.0	2.5	1.5	1.0	3.7	52.6	4.7	2.0	2.7	10.5
70	29.4	2.4	1.5	0.8	3.5	49.8	4.4	2.0	2.4	10.2
75	27.9	2.2	1.5	0.7	3.2	47.3	4.2	2.0	2.2	9.9
80	26.6	2.1	1.5	0.6	2.9	45.0	4.0	2.0	2.0	9.6
85	25.4	2.0	1.5	0.5	2.6	43.0	3.8	2.0	1.8	9.3
90	24.3	1.9	1.5	0.4	2.3	41.1	3.7	2.0	1.7	9.0
95	23.3	1.9	1.5	0.3	1.9	39.4	3.5	2.0	1.5	8.6
100	22.4	1.8	1.5	0.3	1.6	37.9	3.4	2.0	1.4	8.3
105	21.6	1.7	1.5	0.2	1.3	36.5	3.2	2.0	1.3	7.9
110	20.8	1.7	1.5	0.1	0.9	35.2	3.1	2.0	1.1	7.5
115	20.1	1.6	1.5	0.1	0.6	34.0	3.0	2.0	1.0	7.1
120	19.5	1.6	1.5	0.0	0.2	32.9	2.9	2.0	0.9	6.7

Max Storage (m<sup>3</sup>) per drain= **5.0** **11.3**

Average Ponding Depth (mm) **15.7** **35.2**

Maximum Ponding Depth (mm) **102.0** **133.4**

- Notes**
- 1 ) Peak flow is equal to the product of 2.78 x C x I x A
  - 2) Rainfall Intensity,  $I_5 = A/(T_c+6.053)^B$  &  $I_{100} = A/(T_c+6.014)^B$
  - 3) Release Rate = LESSER of Min (Release Rate, Peak Flow) - Minus 100 Year Flow Of Uncontrolled Areas OR Pipe Outlet Capacity
  - 4 ) Storage Rate = Peak Flow - Release Rate
  - 5) Storage = Duration x Storage Rate
  - 6) Maximum Storage = Max Storage Over Duration

**Table VII - Storage Volumes (5-Year and 100-Year Storm Events)**

**Storage Requirement for Roof Area Building B**

$C_{AVG} = 0.90$  (5-year)  
 $C_{AVG} = 1.00$  (100-year)  
 Time Interval = 5 (mins)  
 Drainage Area = 0.025 (hectares) per drain  
 245 (sqm) per drain

Zurn Z105 Control-Flo Single Notch  
 Number of Drains =   
 Total Release Rate 5 year = 2.93 L/s  
 Total Release Rate 100 year = 3.86 L/s

Release Rate = <u>1.47</u> (L/sec) per drain Return Period = <u>5</u> (years) IDF Parameters, A = <u>998.071</u> , B = <u>0.814</u> $I = A/(T_c+6.053)^B$	Release Rate = <u>1.93</u> (L/sec) per drain Return Period = <u>100</u> (years) IDF Parameters, A = <u>1735.688</u> , B = <u>0.820</u> $I = A/(T_c+6.014)^B$
--	---

Duration (min)	Rainfall Intensity, I (mm/hr)	Peak Flow (L/sec)	Release Rate (L/sec)	Storage Rate (L/sec)	Storage (m <sup>3</sup> )	Rainfall Intensity, I (mm/hr)	Peak Flow (L/sec)	Release Rate (L/sec)	Storage Rate (L/sec)	Storage (m <sup>3</sup> )
0	-	-	-	-	-	-	-	-	-	-
5	141.2	8.7	1.5	7.2	2.2	242.7	16.5	1.9	14.6	4.4
10	104.2	6.4	1.5	4.9	3.0	178.6	12.2	1.9	10.2	6.1
15	83.6	5.1	1.5	3.7	3.3	142.9	9.7	1.9	7.8	7.0
20	70.3	4.3	1.5	2.8	3.4	120.0	8.2	1.9	6.2	7.5
25	60.9	3.7	1.5	2.3	3.4	103.8	7.1	1.9	5.1	7.7
30	53.9	3.3	1.5	1.8	3.3	91.9	6.3	1.9	4.3	7.8
35	48.5	3.0	1.5	1.5	3.2	82.6	5.6	1.9	3.7	7.8
40	44.2	2.7	1.5	1.2	3.0	75.1	5.1	1.9	3.2	7.7
45	40.6	2.5	1.5	1.0	2.8	69.1	4.7	1.9	2.8	7.5
50	37.7	2.3	1.5	0.8	2.5	64.0	4.4	1.9	2.4	7.3
55	35.1	2.2	1.5	0.7	2.3	59.6	4.1	1.9	2.1	7.0
60	32.9	2.0	1.5	0.6	2.0	55.9	3.8	1.9	1.9	6.8
65	31.0	1.9	1.5	0.4	1.7	52.6	3.6	1.9	1.7	6.5
70	29.4	1.8	1.5	0.3	1.4	49.8	3.4	1.9	1.5	6.1
75	27.9	1.7	1.5	0.2	1.1	47.3	3.2	1.9	1.3	5.8
80	26.6	1.6	1.5	0.2	0.8	45.0	3.1	1.9	1.1	5.4
85	25.4	1.6	1.5	0.1	0.5	43.0	2.9	1.9	1.0	5.1
90	24.3	1.5	1.5	0.0	0.1	41.1	2.8	1.9	0.9	4.7
95	23.3	1.4	1.4	0.0	0.0	39.4	2.7	1.9	0.8	4.3
100	22.4	1.4	1.4	0.0	0.0	37.9	2.6	1.9	0.7	3.9
105	21.6	1.3	1.3	0.0	0.0	36.5	2.5	1.9	0.6	3.5
110	20.8	1.3	1.3	0.0	0.0	35.2	2.4	1.9	0.5	3.1
115	20.1	1.2	1.2	0.0	0.0	34.0	2.3	1.9	0.4	2.7
120	19.5	1.2	1.2	0.0	0.0	32.9	2.2	1.9	0.3	2.2

Max Storage (m<sup>3</sup>) per drain= **3.4** **7.8**

Average Ponding Depth (mm) **13.9** **31.8**

Maximum Ponding Depth (mm) **97.9** **129.0**

**Notes**

- 1 ) Peak flow is equal to the product of 2.78 x C x I x A
- 2) Rainfall Intensity,  $I_5 = A/(T_c+6.053)^B$  &  $I_{100} = A/(T_c+6.014)^B$
- 3) Release Rate = LESSER of Min (Release Rate, Peak Flow) - Minus 100 Year Flow Of Uncontrolled Areas OR Pipe Outlet Capacity
- 4 ) Storage Rate = Peak Flow - Release Rate
- 5) Storage = Duration x Storage Rate
- 6) Maximum Storage = Max Storage Over Duration

### ICD Design Table - VIII

$Q = 0.62 \times A \times [2gh]^{0.5}$  where:

$g = 9.81$

Location	Pipe Outlet Diameter (mm)	Pipe Outlet Invert (m)	HGL (m)		Outlet flow (L/s)		Trial orifice size (mm)	Orifice size (mm)	Orifice Area (sqm)	Head (m)	
			100-year event	5-year event	100-year event	5-year event				100-year event	5-year event
MHST-37	750	90.16	93.11	92.34	337.1	287.0	<b>305</b>	305.67	0.07338	2.80	2.03



**Appendix B:  
Storm and Sanitary Sewer Computation Forms**

## STORM SEWER COMPUTATION FORM

**Rational Method**  
 $Q = 2.78 \cdot A \cdot I \cdot R$   
 Q = Flow (L/sec)  
 A = Area (ha)  
 I = Rainfall Intensity (mm/hr)  
 R = Ave. Runoff Coefficient

**City of Ottawa IDF Curve - 5-y**  
 $I_p = 998.071 / (T_c + 6.053)^{0.814}$   
 Minimum Time of Conc.  $T_c = 10 \text{ min}$

Manning's  $n = 0.013$

Drainage Area	From	To	Area (ha)	Runoff Parameters					Roof Flow Q (L/sec)	Peak Flow Q (L/sec)	Pipe Dia.			Slope (%)	Length (m)	Capacity		Velocity		Time of Flow (min)	Q(d) / Q(f)	REMARKS
				Runoff Coeff. R	Indiv. 2.78AR	Accum. 2.78AR	Time of Conc. (min)	Rainfall Intensity (mm/hr)			nom. (mm)	actual (mm)	full (L/sec)			full (m/sec)	actual (m/sec)					
																		Time of Conc. (min)	Rainfall Intensity (mm/hr)			
WS-04	CB-19	CBMH-21	0.068	0.65	0.12	0.12	10.00	104.19		12.85	250	254	1.00	26.0	62.04	1.22	0.81	0.35	0.21			
WS-03	TD-CB-15	MHST-22	0.033	0.90	0.08	0.08	10.00	104.19		8.50	250	254	1.00	30.0	62.04	1.22		0.41	0.14			
		MHST-23				0.08	10.41	102.08		8.33	250	254	0.45	31.3	41.62	0.82		0.64	0.20			
WS-05 & WS-14	CBMH-21	MHST-23	0.258	0.67	0.48	0.60	10.35	102.38		61.47	300	305	1.00	19.0	100.88	1.38		0.23	0.61			
		MHST-23																				
		MHST-24				0.68	11.05	98.96	15.3	82.73	450	457	0.25	63.0	148.72	0.91		1.16	0.56			
WS-07	CBMH-27	CBMH-26	0.149	0.90	0.37	0.37	10.00	104.19		38.82	250	254	1.00	35.3	62.04	1.22		0.48	0.63			
		MHST-25				0.228	0.69	0.44	0.81	10.48	101.72		82.76	300	305	1.50	9.5	123.55	1.69		0.09	0.67
WS-06 & WS-15	CBMH-26	MHST-25	0.228	0.69	0.44																	
		MHST-30						1.50	12.54	92.45	15.3	153.51	525	533	0.20	37.8	200.65	0.90		0.70	0.77	
WS-09	CBMH-28	CBMH-29	0.155	0.81	0.35	0.35	10.00	104.19		36.41	250	254	1.00	35.3	62.04	1.22		0.48	0.59			
		MHST-30				0.171	0.72	0.34	0.69	10.48	101.72		70.56	300	305	1.00	16.2	100.88	1.38		0.20	0.70
WS-08 & WS-16	CBMH-29	MHST-30	0.171	0.72	0.34																	
		MHST-31						2.19	13.24	89.71	15.3	211.64	600	610	0.20	15.0	286.47	0.98		0.25	0.74	
WS-13	RYCB-34	MHST-33	0.010	0.20	0.01	0.01	10.00	104.19		0.58	250	254	1.00	14.0	62.04	1.22		0.19	0.01			
WS-12	CB-35	MHST-33	0.013	0.90	0.03	0.03	10.00	104.19		3.26	250	254	1.00	15.5	62.04	1.22		0.21	0.05			
		MHST-31						0.04	10.21	103.10		3.80	250	254	0.50	56.5	43.87	0.87		1.09	0.09	
		MHST-31						2.23	13.49	88.78	15.3	212.86	600	610	0.20	30.3	286.47	0.98		0.51	0.74	
WS-10	CBMH-20	MHST-32	0.053	0.49	0.07	2.30	14.00	86.93	15.3	215.03	600	610	0.20	11.0	286.47	0.98		0.19	0.75			
		MHST-32																				
WS-11	SC-INLET	MHST-32	0.054	0.87	0.13	0.13	10.00	104.19		13.69	300	305	2.00	2.6	142.67	1.96		0.02	0.10			
		MHST-37						2.43	14.19	86.27	15.3	224.84	600	610	0.20	13.8	286.47	0.98		0.23	0.78	
		EX. MHST				2.43	14.42	85.48	18.2	225.86	750	762	0.50	16.2	821.24	1.80		0.15	0.28			

Note:

**Design:** B. Villeneuve  
**Check:** M. Theiner  
**Date:** 2023-04-17

**Project:** 3845 Cambrian Rd  
 Commercial Development  
**Client:** Loblaw Properties Ltd.

## STORM SEWER COMPUTATION FORM

**Rational Method**  
 $Q = 2.78 \cdot A \cdot I \cdot R$   
 Q = Flow (L/sec)  
 A = Area (ha)  
 I = Rainfall Intensity (mm/h)  
 R = Ave. Runoff Coefficient

**City of Ottawa IDF Curve - 100-y**  
 $I_{100} = 1735.688 / (T_c + 6.014)^{0.820}$   
 Minimum Time of Conc.  $T_c = 10 \text{ min}$

Manning's  $n = 0.013$

Drainage Area	From	To	Area (ha)	Runoff Parameters					Roof Flow Q (L/sec)	Peak Flow Q (L/sec)	Pipe Dia.		Slope (%)	Length (m)	Capacity		Velocity		Time of Flow (min)	Q(d) / Q(f)	REMARKS
				Runoff Coeff. R	Indiv. 2.78AR	Accum. 2.78AR	Time of Conc. (min)	Rainfall Intensity (mm/hr)			nom. (mm)	actual (mm)			full (L/sec)	full (m/sec)	actual (m/sec)				
WS-04	CB-19	CBMH-21	0.068	0.82	0.15	0.15	10.00	178.56	27.54	250	254	1.00	26.0	62.04	1.22	1.00	0.35	0.44			
WS-03	TD-CB-15	MHST-22	0.033	1.00	0.09	0.09	10.00	178.56	16.18	250	254	1.00	30.0	62.04	1.22		0.41	0.26			
		MHST-23				0.09	10.41	174.90	15.85	250	254	0.45	31.3	41.62	0.82		0.64	0.38			
WS-05 & WS-14	CBMH-21	MHST-23	0.258	0.83	0.60	0.75	10.35	175.42	131.65	300	305	1.00	19.0	100.88	1.38		0.23	1.30			
		MHST-23				0.84	11.05	169.50	20.0	162.52	450	457	0.25	63.0	148.72	0.91		1.16	1.09		
		MHST-24				0.84	12.21	160.60	20.0	155.04	450	457	0.25	17.9	148.72	0.91		0.33	1.04		
WS-07	CBMH-27	CBMH-26	0.149	1.00	0.41	0.41	10.00	178.56	73.91	250	254	1.00	35.3	62.04	1.22		0.48	1.19			
WS-06 & WS-15	CBMH-26	MHST-25	0.228	0.84	0.53	0.95	10.48	174.29	165.10	300	305	1.50	9.5	123.55	1.69		0.09	1.34			
		MHST-25						1.79	12.54	158.25	20.0	302.98	525	533	0.20	37.8	200.65	0.90		0.70	1.51
WS-09	CBMH-28	CBMH-29	0.155	1.00	0.43	0.43	10.00	178.56	76.74	250	254	1.00	35.3	62.04	1.22		0.48	1.24			
WS-08 & WS-16	CBMH-29	MHST-30	0.171	0.88	0.42	0.85	10.48	174.29	147.77	300	305	1.00	16.2	100.88	1.38		0.20	1.46			
		MHST-30						2.64	13.24	153.52	20.0	424.67	600	610	0.20	15.0	286.47	0.98		0.25	1.48
WS-13	RYCB-34	MHST-33	0.010	0.25	0.01	0.01	10.00	178.56	1.24	250	254	1.00	14.0	62.04	1.22		0.19	0.02			
WS-12	CB-35	MHST-33	0.013	1.00	0.03	0.03	10.00	178.56	6.20	250	254	1.00	15.5	62.04	1.22		0.21	0.10			
		MHST-33						0.04	10.21	176.66	7.37	250	254	0.50	56.5	43.87	0.87		1.09	0.17	
		MHST-31						2.68	13.49	151.90	20.0	426.75	600	610	0.20	30.3	286.47	0.98		0.51	1.49
WS-10	CBMH-20	MHST-32	0.053	0.62	0.09	2.77	14.00	148.72	20.0	431.63	600	610	0.20	11.0	286.47	0.98		0.19	1.51		
WS-11	SC-INLET	MHST-32	0.054	1.00	0.15	0.15	10.00	178.56	26.95	300	305	2.00	2.6	142.67	1.96		0.02	0.19			
	MSHT-32	MHST-37				2.92	14.19	147.58	20.0	450.73	600	610	0.20	13.8	286.47	0.98		0.23	1.57		
		MHST-37 <i>EX. MHST</i>				2.92	14.42	146.21	23.8	450.61	750	762	0.50	16.2	821.24	1.80		0.15	0.55		

Note:

**Design:** B. Villeneuve  
**Check:** M. Theiner  
**Date:** 2023-04-17

**Project:** 3845 Cambrian Rd  
 Commercial Development  
**Client:** Loblaw Properties Ltd.

# SANITARY SEWER DESIGN SHEET

Drainage Area	From	To	Peak Flow Q (L/sec)	Sewer Data										REMARKS
				Type of Pipe	Pipe Dia.		Slope (%)	Length (m)	Capacity full (L/sec)	Velocity		Time of Flow (min)	Q(d) / Q(f)	
					nom. (mm)	actual (mm)				full (m/sec)	actual (m/sec)			
	Retail A	MHSA-3	0.65	PVC	200	203.2	3.2	19.9	60.7	1.87	0.77	0.43	0.01	Including Infiltration
	MHSA-3	MHSA-2	0.67	PVC	200	203.2	1.6	92.5	43.3	1.33	0.59	2.63	0.02	
	MHSA-2	MHSA-1	0.67	PVC	200	203.2	1.6	11.7	43.7	1.35	0.59	0.33	0.02	
	MHSA-1	EX MH-S	0.67	PVC	200	203.2	2.7	15.0	56.2	1.73	0.71	0.35	0.01	

Manning's n = 0.013

<b>Design:</b>	B. Villeneuve	<b>Project Name:</b>	3845 Cambrian Road
<b>Check:</b>	M. Theiner	<b>Parsons Project #:</b>	478575
<b>Date:</b>	April, 2023	<b>Client:</b>	Loblaw Properties Ltd.
		<b>Client Project #:</b>	

**Appendix C:  
Sanitary Load and Fire Flow**



# SANITARY DESIGN FLOWS

Area	COMMERCIAL/RETAIL			TOTAL	INFILTRATION			Total
	Retail Area (m <sup>2</sup> )	Peak Factor	Peak Flow (L/s)	Peak Flow	Site Area	Infiltration Allowance (L/s/ha)	Infiltr. Flow (L/s)	Total Peak Flow
				(L/s)	(ha)			(L/s)
<b>Subject Site</b>					1.50	0.33	0.50	0.50
<b>Retail A</b>	3 204	1.5	0.16	0.16				0.16
<b>Retail B</b>	483	1.5	0.02	0.02				0.02
							<b>Total</b>	<b>0.67</b>

## Average Daily Demands

(Based on City of Ottawa Sewer Design Guidelines 2012 and MOE Water Design Guidelines)

Average Residential Daily Flow =	280 L/p/d
Institutional Flow =	28 000 L/ha/d
Commercial Flow =	28 000 L/ha/d
Light Industrial Flow =	35 000 L/ha/d
Heavy Industrial Flow =	55 000 L/ha/d
Hotel Daily Flow =	225 L/bed/d
Office/Warehouse Daily Flow =	75 L/empl/d
Shopping Centres =	2 500 L/(1000m <sup>2</sup> /d)

## Population Densities

Average suburban residential dev.	60 p/ha
Single family	3.4 p./unit
Semi-detached	2.7 p./unit
Duplex	2.3 p./unit
Townhouse	2.7 p./unit
Appartment average	1.8 p./unit
Bachelor	1.4 p./unit
1 Bedroom	1.4 p./unit
2 Bedrooms	2.1 p./unit
3 Bedrooms	3.1 p./unit
Hotel room, 18 m <sup>2</sup>	1 p./unit
Restaurant, 1 m <sup>2</sup>	1 p./unit
Office	1 p/25m <sup>2</sup>
Warehouse	1 p/90m <sup>2</sup>
Automotive Service Centre, per bay	1 p/bay (plus management)

## Peak Factors

Commercial =	1.5 if commercial contribution > 20%, otherwise
Institutional =	1.5 if institutional contribution > 20%, otherwise
Industrial =	per Appendix 4-B.0 Graph
Residential :	Harmon Equation
	$1 + (14/(4+(Capita/1000) ^ 0.5))*8$
	min =
	max =

Infiltration allowance (dry weather)	0.05 L/s/ha
Infiltration allowance (wet weather)	0.28 L/s/ha

l/l (total) 0.33 L/s/ha

<b>Design:</b>	BV	<b>Project:</b>	Commercial Development Loblaw Properties Ltd.
<b>Check :</b>	MT	<b>Location:</b>	3845 Cambrian Road Ottawa, Ontario
<b>Dwg reference:</b>		<b>Project # :</b>	478575
		<b>Date:</b>	April, 2023
		<b>Sheet:</b>	1 of 1

## 3845 Cambrian Road Commercial Development - Estimated Water Demands

Area	Units	Population	Gross Floor Area (m <sup>2</sup> )	Average Daily Demand (ADD) (L/s)	Maximum Daily Demand (MDD) (L/s)	Peak Hourly Demand (PHD) (L/s)	Fire Flow (FF) (L/s)	MDD + FF (L/s)
<b>Proposed Retail A</b>								
Commercial Unit			3204	0.10	0.16	0.28	83	83.16
<b>Proposed Retail B</b>								
Commercial Unit			483	0.02	0.02	0.04	33	33.02

### Average Daily Demand

Based on Ottawa Design Guidelines - Water Distribution, 2010 and MOE Design Guidelines for Drinking-Water Systems, 2008

Average Residential Daily Flow =	350 L/p/d
Institutional Flow =	28 000 L/gross ha/d
Commercial Flow =	28 000 L/gross ha/d
Light Industrial Flow =	35 000 L/gross ha/d
Heavy Industrial Flow =	55 000 L/gross ha/d
Hotel Daily Flow =	225 L/bed/d
Office/Warehouse Daily Flow =	75 L/person/d
Office/Warehouse Daily Flow =	8.06 L/m <sup>2</sup> /day
Restaurant (Ordinary not 24 Hours) =	125 L/seat/d
Restaurant (24 Hours) =	200 L/seat/d
Shopping Centres =	2 500 L/(1000m <sup>2</sup> /d)
Amenity Area =	5 L/m <sup>2</sup> /d

### **Maximum Daily Demand**

Residential = 2.5 x Average Daily Demand
4.9 x Average Daily Demand **
Industrial = 1.5 x Average Daily Demand
Commercial = 1.5 x Average Daily Demand
Institutional = 1.5 x Average Daily Demand

### **Peak Hourly Demand**

Residential = 2.2 x Maximum Daily Demand
7.4 x Maximum Daily Demand **
Industrial = 1.8 x Maximum Daily Demand
Commercial = 1.8 x Maximum Daily Demand
Institutional = 1.8 x Maximum Daily Demand

3845 Cambrian Road Commercial Development

Building	Type of Construction	Total Floor Area (m <sup>2</sup> )	Fire Flow (min. 2,000) (L/min)	Adjusted (nearest 1,000) (L/min)	Occupancy Factor	Reduction / Increase due to Occupancy	Fire Flow with Occupancy (min. 2,000) (L/min)	Sprinklers Factor	Reduction due to Sprinklers (L/min)	Exposure Factor	Increase due to Exposure (L/min)	Fire Flow (L/min)	Roof Contribution (L/min)	Required Fire Demand	
														Adjusted to the nearest 1000 (min. 2,000, max. 45,000) (L/min)	Minimum 33 (L/s)
	C	A	F		O			S		E			R	F	
Retail A	0.8	3 204	9 962	10 000	0%	0	10 000	50%	5 000	0%	0	5 000	0	5 000	83
Retail B	0.8	483	3 868	4 000	0%	0	4 000	50%	2 000	0%	0	2 000	0	2 000	33

References

Water Supply for Public Fire Protection, 2020 by Fire Underwriters Survey (FUS) and Ottawa Design Guidelines - Water Distribution, July 2010 and subsequent Technical Bulletins

C Type of Construction

Wood Frame (Type V)	1.5
Mass Timber (Type IV-A) - Encapsulated Mass Timber	0.8
Mass Timber (Type IV-B) - Rated Mass Timber	0.9
Mass Timber (Type IV-C) - Ordinary Mass Timber	1.0
Mass Timber (Type IV-D) - Unrated Mass Timber	1.5
Ordinary Construction (Type III also known as joisted masonry)	1.0
Non-Combustible Construction (Type II - minimum 1 hour fire resistance rating)	0.8
Fire resistive Construction (Type I - minimum 2 hour fire resistance rating)	0.6

S Sprinklers

	Complete Coverage	Partial Coverage
Automatic Sprinklers NFPA Standards	30%	30% * x%
Standard Water Supply	10%	10% * x%
Full Supervision	10%	10% * x%

(x%: percentage of total protected floor area)

Additional Reductions for Community Level Automatic Sprinkler Protection of Area

Buildings located within communities or subdivisions that are completely sprinkler protected may apply up to a maximum additional 25% reduction in required fire flows beyond the normal maximum of 50% reduction for sprinkler protection of an individual building.

Adjustment of Sprinkler Reductions for Community Level Oversight of Sprinkler Maintenance, Testing, and Water Supply Requirements

The reduction in required fire flow for sprinkler protection may be reduced or eliminated if:  
 - The community does not have a Fire Prevention Program that provides a system of ensuring that the fire sprinkler systems are inspected, tested, and maintained in accordance with NFPA 25  
 - The community does not maintain the pressure and flow rate requirements for fire sprinkler installations, or otherwise allows the flow rates and pressure levels that were available during sprinkler system design to significantly degrade, increasing the probability of inadequate water supply for effective sprinkler operation.

A Total Effective Floor Area (m<sup>2</sup>)

Buildings Classified with a Construction Coefficient from 1.0 to 1.5  
 100% of all Floor Areas

Buildings Classified with a Construction Coefficient below 1.0

Vertical Openings Unprotected  
 Two (2) Largest Adjoining Floor Areas  
 Additional Floors (up to eight (8)) at 50%

Vertical Openings Properly Protected  
 Single Largest Floor  
 Additional Two (2) Adjoining Floors at 25%

High One Storey Building

When a building has a large single storey space exceeding 3m in height, the number of storeys to be used in determining the total effective area depends upon the use being made of the building.

Subdividing Buildings (Vertical Firewalls)

Minimum two (2) hour fire resistance rating and meets National Building Code requirements.

- Up to 10% can be applied if there is severe risk of fire on the exposed side of the firewall due to hazard conditions.  
 - An exposure charge of up to 10% can be applied if there are unprotected openings in the firewall

Basement

Basement floor excluded when it is at least 50% below grade.

Open Parking Garages

Use the area of the largest floor.

O Occupancy

Non-Combustible	-25%
Limited Combustible	-15%
Combustible	0%
Free Burning	15%
Rapid Burning	25%

- Table 3 provides recommended Occupancy and Contents Adjustment Factors for Example Major Occupancies from the National Building Code of Canada.

- Adjustment factors should be adjusted accordingly to the specific fire loading and situation that exists in the subject building.

- Values can be interpolated from the examples given considering fire loading and expected combustibility of contents if the subject building is not listed.

- Values can be modified by up to 10% (+/-) depending on the extent to which the fire loading is unusual for the building.

- Buildings with multiple major occupancies should use the most restrictive factor or interpolate based on the percentage of each occupancy and its associated fire loading.

Table 3 Values for Subject Building

Group:	E
Division:	
Description of Occupancy:	Shops/Stores
Occupancy and Contents:	Combustible
Adjustment Factor:	0%

R Roof

Shake Roof	2,000 to 4,000 L/min	additional should be added to the fire flow
Wood Shingle	2,000 to 4,000 L/min	additional should be added to the fire flow

F Fire Flow (L/Min)

220 \* C \* (A^0.5)

E Exposure

The maximum exposure adjustment that can be applied to a building is 75% when summing the percentages of all sides of the building

Separation Distance (m)	Maximum Exposure Adjustment	N	E	S	W
0 to 3	25%				
3.1 to 10	20%				
10.1 to 20	15%				
20.1 to 30	10%				
Greater than 30	0%				

Table 6: Exposure Adjustment Charges for Subject Building Considering Construction Type of Exposed Building Face

Distance to the Exposure (m)	Length-Height Factor of Exposing Building Face	Type V	Type III-IV <sup>2</sup>	Type III-IV <sup>3</sup>	Type I-II <sup>2</sup>	Type I-II <sup>3</sup>
0 to 3	0-20	20%	15%	5%	10%	0%
	21-40	21%	16%	6%	11%	1%
	41-60	22%	17%	7%	12%	2%
	61-80	23%	18%	8%	13%	3%
	81-100	24%	19%	9%	14%	4%
	Over 100	25%	20%	10%	15%	5%
3.1 to 10	0-20	15%	10%	3%	6%	0%
	21-40	16%	11%	4%	7%	0%
	41-60	17%	12%	5%	8%	1%
	61-80	18%	13%	6%	9%	2%
	81-100	19%	14%	7%	10%	3%
	Over 100	20%	15%	8%	11%	4%
10.1 to 20	0-20	10%	5%	0%	3%	0%
	21-40	11%	6%	1%	4%	0%
	41-60	12%	7%	2%	5%	0%
	61-80	13%	8%	3%	6%	1%
	81-100	14%	9%	4%	7%	2%
	Over 100	15%	10%	5%	8%	3%
20.1 to 30	0-20	0%	0%	0%	0%	0%
	21-40	2%	1%	0%	0%	0%
	41-60	4%	2%	0%	1%	0%
	61-80	6%	3%	1%	2%	0%
	81-100	8%	4%	2%	3%	0%
	Over 100	10%	5%	3%	4%	0%
Over 30m	All Sizes	0%	0%	0%	0%	0%

<sup>2</sup> with unprotected openings

<sup>3</sup> without unprotected openings

Automatic Sprinkler Protection in Exposed Buildings

- If the exposed building is fully protected with an automatic sprinkler system (see note Recognition of Automatic Sprinkler), the exposure adjustment charge determined from Table 6 may be reduced by up to 50% of the value determined.

Automatic Sprinkler Protection in both Subject and Exposed Buildings

- If both the subject building and the exposed building are fully protected with automatic sprinkler systems (see note Recognition of Automatic Sprinkler), no exposure adjustment charge should be applied.

Exposure Protection of Area Between Subject and Exposed Buildings

- If the exposed building is fully protected with an automatic sprinkler system (see note Recognition of Automatic Sprinkler), and the area between the buildings is protected with an exterior automatic sprinkler system, no exposure adjustment charge should be applied.

Reduction of Exposure Charge for Type V Buildings

- If the exposed building face of a Type V building has an exterior cladding assembly with a minimum 1 hour fire resistive rating, then the exposure charge may be treated as a Type III/IV building for the purposes of looking up the appropriate exposure charge in Table 6.

**Appendix D:  
Stormwater Storage Chambers Specifications**

PROJECT INFORMATION	
ENGINEERED PRODUCT MANAGER	
ADS SALES REP	
PROJECT NO.	



# 3845 CAMBRIAN RD OTTAWA, ON, CANADA

## SC-740 STORMTECH CHAMBER SPECIFICATIONS

- CHAMBERS SHALL BE STORMTECH SC-740.
- CHAMBERS SHALL BE ARCH-SHAPED AND SHALL BE MANUFACTURED FROM VIRGIN, IMPACT-MODIFIED POLYPROPYLENE COPOLYMERS.
- CHAMBERS SHALL BE CERTIFIED TO CSA B184, "POLYMERIC SUB-SURFACE STORMWATER MANAGEMENT STRUCTURES", AND MEET THE REQUIREMENTS OF ASTM F2418, "STANDARD SPECIFICATION FOR POLYPROPYLENE (PP) CORRUGATED WALL STORMWATER COLLECTION CHAMBERS".
- CHAMBER ROWS SHALL PROVIDE CONTINUOUS, UNOBSTRUCTED INTERNAL SPACE WITH NO INTERNAL SUPPORTS THAT WOULD IMPEDE FLOW OR LIMIT ACCESS FOR INSPECTION.
- THE STRUCTURAL DESIGN OF THE CHAMBERS, THE STRUCTURAL BACKFILL, AND THE INSTALLATION REQUIREMENTS SHALL ENSURE THAT THE LOAD FACTORS SPECIFIED IN THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS, SECTION 12.12, ARE MET FOR: 1) LONG-DURATION DEAD LOADS AND 2) SHORT-DURATION LIVE LOADS, BASED ON THE CSA S6 CL-625 TRUCK AND THE AASHTO DESIGN TRUCK WITH CONSIDERATION FOR IMPACT AND MULTIPLE VEHICLE PRESENCES.
- CHAMBERS SHALL BE DESIGNED, TESTED AND ALLOWABLE LOAD CONFIGURATIONS DETERMINED IN ACCORDANCE WITH ASTM F2787, "STANDARD PRACTICE FOR STRUCTURAL DESIGN OF THERMOPLASTIC CORRUGATED WALL STORMWATER COLLECTION CHAMBERS". LOAD CONFIGURATIONS SHALL INCLUDE: 1) INSTANTANEOUS (<1 MIN) AASHTO DESIGN TRUCK LIVE LOAD ON MINIMUM COVER 2) MAXIMUM PERMANENT (75-YR) COVER LOAD AND 3) ALLOWABLE COVER WITH PARKED (1-WEEK) AASHTO DESIGN TRUCK.
- REQUIREMENTS FOR HANDLING AND INSTALLATION:
  - TO MAINTAIN THE WIDTH OF CHAMBERS DURING SHIPPING AND HANDLING, CHAMBERS SHALL HAVE INTEGRAL, INTERLOCKING STACKING LUGS.
  - TO ENSURE A SECURE JOINT DURING INSTALLATION AND BACKFILL, THE HEIGHT OF THE CHAMBER JOINT SHALL NOT BE LESS THAN 50 mm (2").
  - TO ENSURE THE INTEGRITY OF THE ARCH SHAPE DURING INSTALLATION, a) THE ARCH STIFFNESS CONSTANT AS DEFINED IN SECTION 6.2.8 OF ASTM F2418 SHALL BE GREATER THAN OR EQUAL TO 550 LBS/FT/%. AND b) TO RESIST CHAMBER DEFORMATION DURING INSTALLATION AT ELEVATED TEMPERATURES (ABOVE 23° C / 73° F), CHAMBERS SHALL BE PRODUCED FROM REFLECTIVE GOLD OR YELLOW COLORS.
- ONLY CHAMBERS THAT ARE APPROVED BY THE SITE DESIGN ENGINEER WILL BE ALLOWED. UPON REQUEST BY THE SITE DESIGN ENGINEER OR OWNER, THE CHAMBER MANUFACTURER SHALL SUBMIT A STRUCTURAL EVALUATION FOR APPROVAL BEFORE DELIVERING CHAMBERS TO THE PROJECT SITE AS FOLLOWS:
  - THE STRUCTURAL EVALUATION SHALL BE SEALED BY A REGISTERED PROFESSIONAL ENGINEER.
  - THE STRUCTURAL EVALUATION SHALL DEMONSTRATE THAT THE SAFETY FACTORS ARE GREATER THAN OR EQUAL TO 1.95 FOR DEAD LOAD AND 1.75 FOR LIVE LOAD, THE MINIMUM REQUIRED BY ASTM F2787 AND BY SECTIONS 3 AND 12.12 OF THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS FOR THERMOPLASTIC PIPE.
  - THE TEST DERIVED CREEP MODULUS AS SPECIFIED IN ASTM F2418 SHALL BE USED FOR PERMANENT DEAD LOAD DESIGN EXCEPT THAT IT SHALL BE THE 75-YEAR MODULUS USED FOR DESIGN.
- CHAMBERS AND END CAPS SHALL BE PRODUCED AT AN ISO 9001 CERTIFIED MANUFACTURING FACILITY.

## IMPORTANT - NOTES FOR THE BIDDING AND INSTALLATION OF THE SC-740 SYSTEM

- STORMTECH SC-740 CHAMBERS SHALL NOT BE INSTALLED UNTIL THE MANUFACTURER'S REPRESENTATIVE HAS COMPLETED A PRE-CONSTRUCTION MEETING WITH THE INSTALLERS.
- STORMTECH SC-740 CHAMBERS SHALL BE INSTALLED IN ACCORDANCE WITH THE "STORMTECH SC-310/SC-740/DC-780 CONSTRUCTION GUIDE".
- CHAMBERS ARE NOT TO BE BACKFILLED WITH A DOZER OR AN EXCAVATOR SITUATED OVER THE CHAMBERS. STORMTECH RECOMMENDS 3 BACKFILL METHODS:
  - STONESHOOTER LOCATED OFF THE CHAMBER BED.
  - BACKFILL AS ROWS ARE BUILT USING AN EXCAVATOR ON THE FOUNDATION STONE OR SUBGRADE.
  - BACKFILL FROM OUTSIDE THE EXCAVATION USING A LONG BOOM HOE OR EXCAVATOR.
- THE FOUNDATION STONE SHALL BE LEVELED AND COMPACTED PRIOR TO PLACING CHAMBERS.
- JOINTS BETWEEN CHAMBERS SHALL BE PROPERLY SEATED PRIOR TO PLACING STONE.
- MAINTAIN MINIMUM - 150 mm (6") SPACING BETWEEN THE CHAMBER ROWS.
- EMBEDMENT STONE SURROUNDING CHAMBERS MUST BE A CLEAN, CRUSHED, ANGULAR STONE 20-50 mm (3/4-2").
- THE CONTRACTOR MUST REPORT ANY DISCREPANCIES WITH CHAMBER FOUNDATION MATERIALS BEARING CAPACITIES TO THE SITE DESIGN ENGINEER.
- ADS RECOMMENDS THE USE OF "FLEXSTORM CATCH IT" INSERTS DURING CONSTRUCTION FOR ALL INLETS TO PROTECT THE SUBSURFACE STORMWATER MANAGEMENT SYSTEM FROM CONSTRUCTION SITE RUNOFF.

## NOTES FOR CONSTRUCTION EQUIPMENT

- STORMTECH SC-740 CHAMBERS SHALL BE INSTALLED IN ACCORDANCE WITH THE "STORMTECH SC-310/SC-740/DC-780 CONSTRUCTION GUIDE".
- THE USE OF CONSTRUCTION EQUIPMENT OVER SC-740 CHAMBERS IS LIMITED:
  - NO EQUIPMENT IS ALLOWED ON BARE CHAMBERS.
  - NO RUBBER TIRED LOADERS, DUMP TRUCKS, OR EXCAVATORS ARE ALLOWED UNTIL PROPER FILL DEPTHS ARE REACHED IN ACCORDANCE WITH THE "STORMTECH SC-310/SC-740/DC-780 CONSTRUCTION GUIDE".
  - WEIGHT LIMITS FOR CONSTRUCTION EQUIPMENT CAN BE FOUND IN THE "STORMTECH SC-310/SC-740/DC-780 CONSTRUCTION GUIDE".
- FULL 900 mm (36") OF STABILIZED COVER MATERIALS OVER THE CHAMBERS IS REQUIRED FOR DUMP TRUCK TRAVEL OR DUMPING.


**USE OF A DOZER TO PUSH EMBEDMENT STONE BETWEEN THE ROWS OF CHAMBERS MAY CAUSE DAMAGE TO THE CHAMBERS AND IS NOT AN ACCEPTABLE BACKFILL METHOD. ANY CHAMBERS DAMAGED BY THE "DUMP AND PUSH" METHOD ARE NOT COVERED UNDER THE STORMTECH STANDARD WARRANTY.**

CONTACT STORMTECH AT 1-888-892-2694 WITH ANY QUESTIONS ON INSTALLATION REQUIREMENTS OR WEIGHT LIMITS FOR CONSTRUCTION EQUIPMENT.



PROPOSED LAYOUT		PROPOSED ELEVATIONS	
55	STORMTECH SC-740 CHAMBERS	MAXIMUM ALLOWABLE GRADE (TOP OF PAVEMENT/UNPAVED):	95.553
16	STORMTECH SC-740 END CAPS	MINIMUM ALLOWABLE GRADE (UNPAVED WITH TRAFFIC):	93.724
152	STONE ABOVE (mm)	MINIMUM ALLOWABLE GRADE (UNPAVED NO TRAFFIC):	93.571
152	STONE BELOW (mm)	MINIMUM ALLOWABLE GRADE (TOP OF RIGID CONCRETE PAVEMENT):	93.571
40	STONE VOID	MINIMUM ALLOWABLE GRADE (BASE OF FLEXIBLE PAVEMENT):	93.571
130.0	INSTALLED SYSTEM VOLUME (m <sup>3</sup> ) (PERIMETER STONE INCLUDED) (COVER STONE INCLUDED) (BASE STONE INCLUDED)	TOP OF STONE:	93.267
		TOP OF SC-740 CHAMBER:	93.114
		300 mm x 300 mm TOP MANIFOLD INVERT:	92.670
		600 mm ISOLATOR ROW PLUS INVERT:	92.355
204.0	SYSTEM AREA (m <sup>2</sup> )	600 mm ISOLATOR ROW PLUS INVERT:	92.355
60.4	SYSTEM PERIMETER (m)	BOTTOM OF SC-740 CHAMBER:	92.352
		BOTTOM OF STONE:	92.200

				*INVERT ABOVE BASE OF CHAMBER	
PART TYPE	ITEM ON LAYOUT	DESCRIPTION	INVERT*	MAX FLOW	
PREFABRICATED EZ END CAP	A	600 mm BOTTOM PREFABRICATED EZ END CAP, PART#: SC740ECEZ / TYP OF ALL 600 mm BOTTOM CONNECTIONS AND ISOLATOR PLUS ROWS	3 mm		
FLAMP	B	INSTALL FLAMP ON 600 mm ACCESS PIPE / PART#: SC74024RAMP (TYP 3 PLACES)			
MANIFOLD	C	300 mm x 300 mm TOP MANIFOLD, ADS N-12	318 mm		
CONCRETE STRUCTURE	D	(DESIGN BY ENGINEER / PROVIDED BY OTHERS)		161 L/s IN	
CONCRETE STRUCTURE	E	(DESIGN BY ENGINEER / PROVIDED BY OTHERS)		79 L/s IN	



- ISOLATOR ROW PLUS  
(SEE DETAIL/TYP 2 PLACES)
- PLACE MINIMUM 3.810 m OF ADSPLUS125 WOVEN GEOTEXTILE OVER BEDDING STONE AND UNDERNEATH CHAMBER FEET FOR SCOUR PROTECTION AT ALL CHAMBER INLET ROWS
- BED LIMITS

**NOTES**

- MANIFOLD SIZE TO BE DETERMINED BY SITE DESIGN ENGINEER. SEE TECH NOTE #6.32 FOR MANIFOLD SIZING GUIDANCE.
- DUE TO THE ADAPTATION OF THIS CHAMBER SYSTEM TO SPECIFIC SITE AND DESIGN CONSTRAINTS, IT MAY BE NECESSARY TO CUT AND COUPLE ADDITIONAL PIPE TO STANDARD MANIFOLD COMPONENTS IN THE FIELD.
- THE SITE DESIGN ENGINEER MUST REVIEW ELEVATIONS AND IF NECESSARY ADJUST GRADING TO ENSURE THE CHAMBER COVER REQUIREMENTS ARE MET.
- THIS CHAMBER SYSTEM WAS DESIGNED WITHOUT SITE-SPECIFIC INFORMATION ON SOIL CONDITIONS OR BEARING CAPACITY. THE SITE DESIGN ENGINEER IS RESPONSIBLE FOR DETERMINING THE SUITABILITY OF THE SOIL AND PROVIDING THE BEARING CAPACITY OF THE INSITU SOILS. THE BASE STONE DEPTH MAY BE INCREASED OR DECREASED ONCE THIS INFORMATION IS PROVIDED.
- **NOT FOR CONSTRUCTION:** THIS LAYOUT IS FOR DIMENSIONAL PURPOSES ONLY TO PROVE CONCEPT & THE REQUIRED STORAGE VOLUME CAN BE ACHIEVED ON SITE.

**StormTech®**  
Chamber System

888-892-2694 | WWW.STORMTECH.COM

4640 TRUEMAN BLVD  
HILLIARD, OH 43026  
1-800-733-7473

**SCALE = 1 : 100**

3845 CAMBRIAN RD  
OTTAWA, ON, CANADA

DATE: \_\_\_\_\_  
DRAWN: BU

PROJECT #: \_\_\_\_\_  
CHECKED: N/A

DATE	DRW	CHK	DESCRIPTION

SHEET  
**2 OF 5**


THIS DRAWING HAS BEEN PREPARED BASED ON INFORMATION PROVIDED TO ADS UNDER THE DIRECTION OF THE SITE DESIGN ENGINEER OR OTHER PROJECT REPRESENTATIVE. THE SITE DESIGN ENGINEER SHALL REVIEW THIS DRAWING PRIOR TO CONSTRUCTION. IT IS THE ULTIMATE RESPONSIBILITY OF THE SITE DESIGN ENGINEER TO ENSURE THAT THE PRODUCT(S) DEPICTED AND ALL ASSOCIATED DETAILS MEET ALL APPLICABLE LAWS, REGULATIONS, AND PROJECT REQUIREMENTS.

## ACCEPTABLE FILL MATERIALS: STORMTECH SC-740 CHAMBER SYSTEMS

MATERIAL LOCATION		DESCRIPTION	AASHTO MATERIAL CLASSIFICATIONS	COMPACTION / DENSITY REQUIREMENT
D	<b>FINAL FILL:</b> FILL MATERIAL FOR LAYER 'D' STARTS FROM THE TOP OF THE 'C' LAYER TO THE BOTTOM OF FLEXIBLE PAVEMENT OR UNPAVED FINISHED GRADE ABOVE. NOTE THAT PAVEMENT SUBBASE MAY BE PART OF THE 'D' LAYER.	ANY SOIL/ROCK MATERIALS, NATIVE SOILS, OR PER ENGINEER'S PLANS. CHECK PLANS FOR PAVEMENT SUBGRADE REQUIREMENTS.	N/A	PREPARE PER SITE DESIGN ENGINEER'S PLANS. PAVED INSTALLATIONS MAY HAVE STRINGENT MATERIAL AND PREPARATION REQUIREMENTS.
C	<b>INITIAL FILL:</b> FILL MATERIAL FOR LAYER 'C' STARTS FROM THE TOP OF THE EMBEDMENT STONE ('B' LAYER) TO 18" (450 mm) ABOVE THE TOP OF THE CHAMBER. NOTE THAT PAVEMENT SUBBASE MAY BE A PART OF THE 'C' LAYER.	GRANULAR WELL-GRADED SOIL/AGGREGATE MIXTURES, <35% FINES OR PROCESSED AGGREGATE.  MOST PAVEMENT SUBBASE MATERIALS CAN BE USED IN LIEU OF THIS LAYER.	AASHTO M145 <sup>1</sup> A-1, A-2-4, A-3  OR  AASHTO M43 <sup>1</sup> 3, 357, 4, 467, 5, 56, 57, 6, 67, 68, 7, 78, 8, 89, 9, 10	BEGIN COMPACTIONS AFTER 12" (300 mm) OF MATERIAL OVER THE CHAMBERS IS REACHED. COMPACT ADDITIONAL LAYERS IN 6" (150 mm) MAX LIFTS TO A MIN. 95% PROCTOR DENSITY FOR WELL GRADED MATERIAL AND 95% RELATIVE DENSITY FOR PROCESSED AGGREGATE MATERIALS. ROLLER GROSS VEHICLE WEIGHT NOT TO EXCEED 12,000 lbs (53 kN). DYNAMIC FORCE NOT TO EXCEED 20,000 lbs (89 kN).
B	<b>EMBEDMENT STONE:</b> FILL SURROUNDING THE CHAMBERS FROM THE FOUNDATION STONE ('A' LAYER) TO THE 'C' LAYER ABOVE.	CLEAN, CRUSHED, ANGULAR STONE	AASHTO M43 <sup>1</sup> 3, 357, 4, 467, 5, 56, 57	NO COMPACTION REQUIRED.
A	<b>FOUNDATION STONE:</b> FILL BELOW CHAMBERS FROM THE SUBGRADE UP TO THE FOOT (BOTTOM) OF THE CHAMBER.	CLEAN, CRUSHED, ANGULAR STONE	AASHTO M43 <sup>1</sup> 3, 357, 4, 467, 5, 56, 57	PLATE COMPACT OR ROLL TO ACHIEVE A FLAT SURFACE. <sup>2,3</sup>

**PLEASE NOTE:**

- THE LISTED AASHTO DESIGNATIONS ARE FOR GRADATIONS ONLY. THE STONE MUST ALSO BE CLEAN, CRUSHED, ANGULAR. FOR EXAMPLE, A SPECIFICATION FOR #4 STONE WOULD STATE: "CLEAN, CRUSHED, ANGULAR NO. 4 (AASHTO M43) STONE".
- STORMTECH COMPACTION REQUIREMENTS ARE MET FOR 'A' LOCATION MATERIALS WHEN PLACED AND COMPACTED IN 6" (150 mm) (MAX) LIFTS USING TWO FULL COVERAGES WITH A VIBRATORY COMPACTOR.
- WHERE INFILTRATION SURFACES MAY BE COMPROMISED BY COMPACTION, FOR STANDARD DESIGN LOAD CONDITIONS, A FLAT SURFACE MAY BE ACHIEVED BY RAKING OR DRAGGING WITHOUT COMPACTION EQUIPMENT. FOR SPECIAL LOAD DESIGNS, CONTACT STORMTECH FOR COMPACTION REQUIREMENTS.
- ONCE LAYER 'C' IS PLACED, ANY SOIL/MATERIAL CAN BE PLACED IN LAYER 'D' UP TO THE FINISHED GRADE. MOST PAVEMENT SUBBASE SOILS CAN BE USED TO REPLACE THE MATERIAL REQUIREMENTS OF LAYER 'C' OR 'D' AT THE SITE DESIGN ENGINEER'S DISCRETION.



**NOTES:**

- CHAMBERS SHALL MEET THE REQUIREMENTS OF ASTM F2418, "STANDARD SPECIFICATION FOR POLYPROPYLENE (PP) CORRUGATED WALL STORMWATER COLLECTION CHAMBERS".
- SC-740 CHAMBERS SHALL BE DESIGNED IN ACCORDANCE WITH ASTM F2787 "STANDARD PRACTICE FOR STRUCTURAL DESIGN OF THERMOPLASTIC CORRUGATED WALL STORMWATER COLLECTION CHAMBERS".
- THE SITE DESIGN ENGINEER IS RESPONSIBLE FOR ASSESSING THE BEARING RESISTANCE (ALLOWABLE BEARING CAPACITY) OF THE SUBGRADE SOILS AND THE DEPTH OF FOUNDATION STONE WITH CONSIDERATION FOR THE RANGE OF EXPECTED SOIL MOISTURE CONDITIONS.
- PERIMETER STONE MUST BE EXTENDED HORIZONTALLY TO THE EXCAVATION WALL FOR BOTH VERTICAL AND SLOPED EXCAVATION WALLS.
- REQUIREMENTS FOR HANDLING AND INSTALLATION:
  - TO MAINTAIN THE WIDTH OF CHAMBERS DURING SHIPPING AND HANDLING, CHAMBERS SHALL HAVE INTEGRAL, INTERLOCKING STACKING LUGS.
  - TO ENSURE A SECURE JOINT DURING INSTALLATION AND BACKFILL, THE HEIGHT OF THE CHAMBER JOINT SHALL NOT BE LESS THAN 2".
  - TO ENSURE THE INTEGRITY OF THE ARCH SHAPE DURING INSTALLATION, a) THE ARCH STIFFNESS CONSTANT SHALL BE GREATER THAN OR EQUAL TO 550 LBS/FT/%. THE ASC IS DEFINED IN SECTION 6.2.8 OF ASTM F2418. AND b) TO RESIST CHAMBER DEFORMATION DURING INSTALLATION AT ELEVATED TEMPERATURES (ABOVE 73° F / 23° C), CHAMBERS SHALL BE PRODUCED FROM REFLECTIVE GOLD OR YELLOW COLORS.

3845 CAMBRIAN RD  
 OTTAWA, ON, CANADA  
 DATE: \_\_\_\_\_  
 DRAWN: BU  
 PROJECT #: \_\_\_\_\_  
 CHECKED: N/A


DATE	DRW	CHK	DESCRIPTION

**StormTech®**  
 Chamber System  
 888-892-2694 | WWW.STORMTECH.COM

4640 TRUEMAN BLVD  
 HILLIARD, OH 43026  
 1-800-733-7473



THIS DRAWING HAS BEEN PREPARED BASED ON INFORMATION PROVIDED TO ADS UNDER THE DIRECTION OF THE SITE DESIGN ENGINEER OR OTHER PROJECT REPRESENTATIVE. THE SITE DESIGN ENGINEER SHALL REVIEW THIS DRAWING PRIOR TO CONSTRUCTION. IT IS THE ULTIMATE RESPONSIBILITY OF THE SITE DESIGN ENGINEER TO ENSURE THAT THE PRODUCT(S) DEPICTED AND ALL ASSOCIATED DETAILS MEET ALL APPLICABLE LAWS, REGULATIONS, AND PROJECT REQUIREMENTS.



**SC-740 ISOLATOR ROW PLUS DETAIL**  
NTS

**INSPECTION & MAINTENANCE**

- STEP 1) INSPECT ISOLATOR ROW PLUS FOR SEDIMENT
- A. INSPECTION PORTS (IF PRESENT)
    - A.1. REMOVE/OPEN LID ON NYLOPLAST INLINE DRAIN
    - A.2. REMOVE AND CLEAN FLEXSTORM FILTER IF INSTALLED
    - A.3. USING A FLASHLIGHT AND STADIA ROD, MEASURE DEPTH OF SEDIMENT AND RECORD ON MAINTENANCE LOG
    - A.4. LOWER A CAMERA INTO ISOLATOR ROW PLUS FOR VISUAL INSPECTION OF SEDIMENT LEVELS (OPTIONAL)
    - A.5. IF SEDIMENT IS AT, OR ABOVE, 3" (80 mm) PROCEED TO STEP 2. IF NOT, PROCEED TO STEP 3.
  - B. ALL ISOLATOR PLUS ROWS
    - B.1. REMOVE COVER FROM STRUCTURE AT UPSTREAM END OF ISOLATOR ROW PLUS
    - B.2. USING A FLASHLIGHT, INSPECT DOWN THE ISOLATOR ROW PLUS THROUGH OUTLET PIPE
      - i) MIRRORS ON POLES OR CAMERAS MAY BE USED TO AVOID A CONFINED SPACE ENTRY
      - ii) FOLLOW OSHA REGULATIONS FOR CONFINED SPACE ENTRY IF ENTERING MANHOLE
    - B.3. IF SEDIMENT IS AT, OR ABOVE, 3" (80 mm) PROCEED TO STEP 2. IF NOT, PROCEED TO STEP 3.
- STEP 2) CLEAN OUT ISOLATOR ROW PLUS USING THE JETVAC PROCESS
- A. A FIXED CULVERT CLEANING NOZZLE WITH REAR FACING SPREAD OF 45" (1.1 m) OR MORE IS PREFERRED
  - B. APPLY MULTIPLE PASSES OF JETVAC UNTIL BACKFLUSH WATER IS CLEAN
  - C. VACUUM STRUCTURE SUMP AS REQUIRED
- STEP 3) REPLACE ALL COVERS, GRATES, FILTERS, AND LIDS; RECORD OBSERVATIONS AND ACTIONS.
- STEP 4) INSPECT AND CLEAN BASINS AND MANHOLES UPSTREAM OF THE STORMTECH SYSTEM.


**NOTES**

1. INSPECT EVERY 6 MONTHS DURING THE FIRST YEAR OF OPERATION. ADJUST THE INSPECTION INTERVAL BASED ON PREVIOUS OBSERVATIONS OF SEDIMENT ACCUMULATION AND HIGH WATER ELEVATIONS.
2. CONDUCT JETTING AND VACTORING ANNUALLY OR WHEN INSPECTION SHOWS THAT MAINTENANCE IS NECESSARY.

	<b>StormTech®</b> Chamber System 888-892-2694   WWW.STORMTECH.COM	4640 TRUEMAN BLVD HILLIARD, OH 43026 1-800-733-7473	<b>3845 CAMBRIAN RD</b> OTTAWA, ON, CANADA DATE: _____ DRAWN: BU PROJECT #: _____ CHECKED: N/A
THIS DRAWING HAS BEEN PREPARED BASED ON INFORMATION PROVIDED TO ADS UNDER THE DIRECTION OF THE SITE DESIGN ENGINEER OR OTHER PROJECT REPRESENTATIVE. THE SITE DESIGN ENGINEER SHALL REVIEW THIS DRAWING PRIOR TO CONSTRUCTION. IT IS THE ULTIMATE RESPONSIBILITY OF THE SITE DESIGN ENGINEER TO ENSURE THAT THE PRODUCT(S) DEPICTED AND ALL ASSOCIATED DETAILS MEET ALL APPLICABLE LAWS, REGULATIONS, AND PROJECT REQUIREMENTS.			
SHEET <b>4 OF 5</b>			

# SC-740 TECHNICAL SPECIFICATION

NTS




### NOMINAL CHAMBER SPECIFICATIONS

SIZE (W X H X INSTALLED LENGTH)	51.0" X 30.0" X 85.4"	(1295 mm X 762 mm X 2169 mm)
CHAMBER STORAGE	45.9 CUBIC FEET	(1.30 m <sup>3</sup> )
MINIMUM INSTALLED STORAGE*	74.9 CUBIC FEET	(2.12 m <sup>3</sup> )
WEIGHT	75.0 lbs.	(33.6 kg)

\*ASSUMES 6" (152 mm) STONE ABOVE, BELOW, AND BETWEEN CHAMBERS

PRE-FAB STUB AT BOTTOM OF END CAP WITH FLAMP END WITH "BR"  
 PRE-FAB STUBS AT BOTTOM OF END CAP FOR PART NUMBERS ENDING WITH "B"  
 PRE-FAB STUBS AT TOP OF END CAP FOR PART NUMBERS ENDING WITH "T"  
 PRE-CORED END CAPS END WITH "PC"



PART #	STUB	A	B	C
SC740EPE06T / SC740EPE06TPC	6" (150 mm)	10.9" (277 mm)	18.5" (470 mm)	---
SC740EPE06B / SC740EPE06BPC	---	---	---	0.5" (13 mm)
SC740EPE08T / SC740EPE08TPC	8" (200 mm)	12.2" (310 mm)	16.5" (419 mm)	---
SC740EPE08B / SC740EPE08BPC	---	---	---	0.6" (15 mm)
SC740EPE10T / SC740EPE10TPC	10" (250 mm)	13.4" (340 mm)	14.5" (368 mm)	---
SC740EPE10B / SC740EPE10BPC	---	---	---	0.7" (18 mm)
SC740EPE12T / SC740EPE12TPC	12" (300 mm)	14.7" (373 mm)	12.5" (318 mm)	---
SC740EPE12B / SC740EPE12BPC	---	---	---	1.2" (30 mm)
SC740EPE15T / SC740EPE15TPC	15" (375 mm)	18.4" (467 mm)	9.0" (229 mm)	---
SC740EPE15B / SC740EPE15BPC	---	---	---	1.3" (33 mm)
SC740EPE18T / SC740EPE18TPC	18" (450 mm)	19.7" (500 mm)	5.0" (127 mm)	---
SC740EPE18B / SC740EPE18BPC	---	---	---	1.6" (41 mm)
SC740ECEZ*	24" (600 mm)	18.5" (470 mm)	---	0.1" (3 mm)

ALL STUBS, EXCEPT FOR THE SC740ECEZ ARE PLACED AT BOTTOM OF END CAP SUCH THAT THE OUTSIDE DIAMETER OF THE STUB IS FLUSH WITH THE BOTTOM OF THE END CAP. FOR ADDITIONAL INFORMATION CONTACT STORMTECH AT 1-888-892-2694.

\* FOR THE SC740ECEZ THE 24" (600 mm) STUB LIES BELOW THE BOTTOM OF THE END CAP APPROXIMATELY 1.75" (44 mm). BACKFILL MATERIAL SHOULD BE REMOVED FROM BELOW THE N-12 STUB SO THAT THE FITTING SITS LEVEL.

NOTE: ALL DIMENSIONS ARE NOMINAL

3845 CAMBRIAN RD  
 OTTAWA, ON, CANADA

DATE: PROJECT #:  
 DRAWN: BU CHECKED: N/A

DESCRIPTION

DATE DRW CHK


StormTech®  
 Chamber System  
 888-892-2694 | WWW.STORMTECH.COM

4640 TRUEMAN BLVD  
 HILLIARD, OH 43026  
 1-800-733-7473



THIS DRAWING HAS BEEN PREPARED BASED ON INFORMATION PROVIDED TO ADS UNDER THE DIRECTION OF THE SITE DESIGN ENGINEER OR OTHER PROJECT REPRESENTATIVE. THE SITE DESIGN ENGINEER SHALL REVIEW THIS DRAWING PRIOR TO CONSTRUCTION. IT IS THE ULTIMATE RESPONSIBILITY OF THE SITE DESIGN ENGINEER TO ENSURE THAT THE PRODUCT(S) DEPICTED AND ALL ASSOCIATED DETAILS MEET ALL APPLICABLE LAWS, REGULATIONS, AND PROJECT REQUIREMENTS.





T/G - 93.80  
INV. - 90.28  
INV. - 90.25

T/G - 93.55  
INV. - 88.84  
INV. - 88.78

STM 30.3m  
300mm Ø @ 0.30%

SC-C8-35  
T/G - 93.55

0.05%

STM

**Appendix E:  
City Correspondence**

## Boundary Conditions 3845 Cambrian Rd

### Provided Information

Scenario	Demand	
	L/min	L/s
Average Daily Demand	7	0.12
Maximum Daily Demand	11	0.18
Peak Hour	19	0.32
Fire Flow Demand #1	4,980	83.00

### Location



### Results

#### Existing Conditions (Pressure Zone 3SW)

##### Connection 1 – Cambrian Rd.

Demand Scenario	Head (m)	Pressure <sup>1</sup> (psi)
Maximum HGL	156.5	89.9
Peak Hour	142.6	70.1
Max Day plus Fire Flow	138.2	63.9

<sup>1</sup> Ground Elevation = 93.3 m

## Future Conditions (Pressure Zone SUC)

### Connection 1 – Cambrian Rd.

Demand Scenario	Head (m)	Pressure <sup>1</sup> (psi)
Maximum HGL	146.8	76.0
Peak Hour	142.8	70.4
Max Day plus Fire Flow	144.2	72.4

<sup>1</sup> Ground Elevation = 93.3 m

### Notes

1. As per the Ontario Building Code in areas that may be occupied, the static pressure at any fixture shall not exceed 552 kPa (80 psi.) Pressure control measures to be considered are as follows, in order of preference:
  - a. If possible, systems to be designed to residual pressures of 345 to 552 kPa (50 to 80 psi) in all occupied areas outside of the public right-of-way without special pressure control equipment.
  - b. Pressure reducing valves to be installed immediately downstream of the isolation valve in the home/ building, located downstream of the meter so it is owner maintained.

### **Disclaimer**

*The boundary condition information is based on current operation of the city water distribution system. The computer model simulation is based on the best information available at the time. The operation of the water distribution system can change on a regular basis, resulting in a variation in boundary conditions. The physical properties of watermains deteriorate over time, as such must be assumed in the absence of actual field test data. The variation in physical watermain properties can therefore alter the results of the computer model simulation. Fire Flow analysis is a reflection of available flow in the watermain; there may be additional restrictions that occur between the watermain and the hydrant that the model cannot take into account.*




# Villeneuve, Benoit [NN-CA]

**From:** Bramah, Bruce <bruce.bramah@ottawa.ca>  
**Sent:** 20 mars 2023 15:00  
**To:** Villeneuve, Benoit [NN-CA]  
**Cc:** Theiner, Mathew [NN-CA]; Harrold, Eric  
**Subject:** [EXTERNAL] RE: 3845 & 3850 Cambrian Rd Commercial Developments - Stormwater Management

Good afternoon Benoit,

Both properties shall comply with the servicing criteria from the final detailed design: Design Brief for the Half Moon Bay West Phase 1, Prepared by DSEL, Project #16-888, dated Sept 5, 2018. The design brief notes a predevelopment C=0.8, Tc=10min. The resulting pre development flows are 348 L/s and 315 L/s for 3845 Cambrian and 3850 Cambrian respectively.



If you have any further questions, please feel free to call me or we can set up a meeting to discuss.

Thank you,

--  
**Bruce Bramah, EIT**  
Project Manager

Planning, Real Estate and Economic Development Department / Direction générale de la planification, des biens immobiliers et du développement économique  
Development Review - South Branch


**From:** Benoit.Villeneuve@parsons.com <Benoit.Villeneuve@parsons.com>  
**Sent:** March 10, 2023 1:24 PM  
**To:** Bramah, Bruce <bruce.bramah@ottawa.ca>; Charie, Kelsey <kelsey.charie@ottawa.ca>; Harrold, Eric <eric.harrold@ottawa.ca>  
**Cc:** Theiner, Mathew <mathew.theiner@parsons.com>; Moore, Sean <Sean.Moore@ottawa.ca>; O'Callaghan, Katie <katie.ocallaghan@ottawa.ca>  
**Subject:** 3845 & 3850 Cambrian Rd Commercial Developments - Stormwater Management

**CAUTION: This email originated from an External Sender. Please do not click links or open attachments unless you recognize the source.**

**ATTENTION : Ce courriel provient d'un expéditeur externe. Ne cliquez sur aucun lien et n'ouvrez pas de pièce jointe, excepté si vous connaissez l'expéditeur.**

Hi,

Parsons is currently providing municipal engineering services for both commercial development located at 3845 Cambrian Rd and 3850 Cambrian Rd. These two sites are across from each other on Cambrian Rd and are serviced by the same storm sewer previously installed in 2019 for the future re-aligned Greenbank Rd. (see image below)



According to pre-consultation meeting notes for both projects (see attached), the allowable release rate for each site is determined using two different methods.

For 3850 Cambrian Rd the allowable release rate is calculated using the following parameters:

- Allowable runoff coefficient = lesser of existing pre-development to a maximum of 0.5 (in our case C=0.2 as this is a vacant land)
- Time of concentration = pre-development, maximum 10 min
- Allowable flowrate using  $T_c=10\text{min}$ ,  $C=0.2$  and an area of 1.4 ha,  $Q_{\text{allowable}} = 81.1 \text{ L/s}$

For 3845 Cambrian Rd the allowable release rate is calculated using the following parameters:

- Allowable runoff coefficient = 0.8
- Time of concentration = 10 min
- Site area = 1.5 ha
- Allowable flowrate = 348 L/s

Furthermore, as these two properties are part of the Half Moon Bay West Subdivision, these two sites were taken into account in the design of the new storm sewer along future Greenbank Rd and the new Clarke Pond. Based on the *Functional Servicing and Stormwater Management Report for the Half Moon Bay West Subdivision, dated March 8, 2019 by Mattamy Homes and DSEL*, the storm sewer was designed using runoff coefficient of 0.8 for both properties and a time of concentration of 29.62 min and 31.23 min for 3845 Cambrian and 3850 Cambrian respectively. Appendix D of this report showing the storm drainage plan and storm design sheets is attached for your reference.

Using the time of concentration mentioned above and runoff coefficient of 0.8, the allowable release rate for 3845 Cambrian is 181.5 L/s and 163.4 L/s for 3850 Cambrian.

We would like you to discuss and let us know which method of calculations should be used for both of these commercial developments. We could also arrange a meeting in the middle of next week to discuss.

If you have any questions please let us know.

Thank you,

**Benoit Villeneuve, EIT**

Junior Designer

100-1223 Michael St North, Ottawa, ON K1J 7T2

[benoit.villeneuve@parsons.com](mailto:benoit.villeneuve@parsons.com)

P : +1 613.691.1596

[Parsons \[can01.safelinks.protection.outlook.com\]](#) / [LinkedIn \[can01.safelinks.protection.outlook.com\]](#) / [Twitter \[can01.safelinks.protection.outlook.com\]](#)

[\[can01.safelinks.protection.outlook.com\]](#) / [Facebook \[can01.safelinks.protection.outlook.com\]](#) / [Instagram \[can01.safelinks.protection.outlook.com\]](#)

[\[can01.safelinks.protection.outlook.com\]](#)




'NOTICE: This email message and all attachments transmitted with it may contain privileged and confidential information, and information that is protected by, and proprietary to, Parsons Corporation, and is intended solely for the use of the addressee for the specific purpose set forth in this communication. If the reader of this message is not the intended recipient, you are hereby notified that any reading, dissemination, distribution, copying, or other use of this message or its attachments is strictly prohibited, and you should delete this message and all copies and backups thereof. The recipient may not further distribute or use any of the information contained herein without the express written authorization of the sender. If you have received this message in error, or if you have any questions regarding the use of the proprietary information contained therein, please contact the sender of this message immediately, and the sender will provide you with further instructions.'

This e-mail originates from the City of Ottawa e-mail system. Any distribution, use or copying of this e-mail or the information it contains by other than the intended recipient(s) is unauthorized. Thank you.

Le présent courriel a été expédié par le système de courriels de la Ville d'Ottawa. Toute distribution, utilisation ou reproduction du courriel ou des renseignements qui s'y trouvent par une personne autre que son destinataire prévu est interdite. Je vous remercie de votre collaboration.

**Appendix F:  
WaterCad Model Results**

# Scenario: Base



## Scenario: Base

PIPE TABLE

	Length (Scaled) (m)	Start Node ▲	Stop Node	Diameter (mm)	Material	Hazen-Williams C	Flow (L/s)	Velocity (m/s)
32: P-1	3	CONNECTION AT CAMBRIAN	J-1	200.0	PVC	110.0	0.12	0.00
76: P-2	11	J-1	J-2	200.0	PVC	110.0	0.12	0.00
38: P-3	3	J-2	BLDG B	200.0	PVC	110.0	0.12	0.00
40: P-4	33	BLDG B	H-1	200.0	PVC	110.0	0.10	0.00
63: P-7	10	J-4	J-5	200.0	PVC	110.0	0.10	0.00
65: P-8	12	J-5	J-6	200.0	PVC	110.0	0.10	0.00
67: P-9	54	J-6	J-7	200.0	PVC	110.0	0.10	0.00
69: P-10	20	J-7	J-8	200.0	PVC	110.0	0.10	0.00
71: P-11	29	J-8	H-2	200.0	PVC	110.0	0.10	0.00
75: P-13	7	J-9	BLDG A	200.0	PVC	110.0	0.10	0.00
44: P-5	53	H-1	J-3	200.0	PVC	110.0	0.10	0.00
61: P-6	15	J-3	J-4	200.0	PVC	110.0	0.10	0.00
73: P-12	25	H-2	J-9	200.0	PVC	110.0	0.10	0.00

JUNCTION TABLE

	Label ▲	Elevation (m)	Demand (L/s)	Hydraulic Grade (m)	Pressure (kPa)
74: BLDG A	BLDG A	94.05	0.10	156.50	611
37: BLDG B	BLDG B	94.12	0.02	156.50	611
31: J-1	J-1	93.80	0.00	156.50	614
35: J-2	J-2	93.95	0.00	156.50	612
78: J-3	J-3	93.70	0.00	156.50	615
60: J-4	J-4	93.70	0.00	156.50	615
62: J-5	J-5	93.80	0.00	156.50	614
64: J-6	J-6	93.90	0.00	156.50	613
66: J-7	J-7	93.45	0.00	156.50	617
68: J-8	J-8	93.25	0.00	156.50	619
72: J-9	J-9	93.90	0.00	156.50	613

RESERVOIR TABLE

	Label	Elevation (m)	Flow (Out net) (L/s)	Hydraulic Grade (m)
30: CONNECTI	CONNECTION AT CAMBRIAN	156.50	0.12	156.50





## Scenario: Peak Hour

**PIPE TABLE**

	Length (Scaled) (m)	Start Node ▲	Stop Node	Diameter (mm)	Material	Hazen-Williams C	Flow (L/s)	Velocity (m/s)
32: P-1	3	CONNECTION AT CAMBRIAN	J-1	200.0	PVC	110.0	0.32	0.01
76: P-2	11	J-1	J-2	200.0	PVC	110.0	0.32	0.01
38: P-3	3	J-2	BLDG B	200.0	PVC	110.0	0.32	0.01
40: P-4	33	BLDG B	H-1	200.0	PVC	110.0	0.28	0.01
63: P-7	10	J-4	J-5	200.0	PVC	110.0	0.28	0.01
65: P-8	12	J-5	J-6	200.0	PVC	110.0	0.28	0.01
67: P-9	54	J-6	J-7	200.0	PVC	110.0	0.28	0.01
69: P-10	20	J-7	J-8	200.0	PVC	110.0	0.28	0.01
71: P-11	29	J-8	H-2	200.0	PVC	110.0	0.28	0.01
75: P-13	7	J-9	BLDG A	200.0	PVC	110.0	0.28	0.01
44: P-5	53	H-1	J-3	200.0	PVC	110.0	0.28	0.01
61: P-6	15	J-3	J-4	200.0	PVC	110.0	0.28	0.01
73: P-12	25	H-2	J-9	200.0	PVC	110.0	0.28	0.01


**JUNCTION TABLE**

	Label ▲	Elevation (m)	Demand (L/s)	Hydraulic Grade (m)	Pressure (kPa)
74: BLDG A	BLDG A	94.05	0.28	142.60	475
37: BLDG B	BLDG B	94.12	0.04	142.60	474
31: J-1	J-1	93.80	0.00	142.60	478
35: J-2	J-2	93.95	0.00	142.60	476
78: J-3	J-3	93.70	0.00	142.60	479
60: J-4	J-4	93.70	0.00	142.60	479
62: J-5	J-5	93.80	0.00	142.60	478
64: J-6	J-6	93.90	0.00	142.60	477
66: J-7	J-7	93.45	0.00	142.60	481
68: J-8	J-8	93.25	0.00	142.60	483
72: J-9	J-9	93.90	0.00	142.60	477

**RESERVOIR TABLE**

	Label	Elevation (m)	Flow (Out net) (L/s)	Hydraulic Grade (m)
30: CONNECTI	CONNECTION AT CAMBRIAN	142.60	0.32	142.60

# Scenario: Max Day + FF



## Scenario: Max Day + FF

### PIPE TABLE

	Length (Scaled) (m)	Start Node	Stop Node	Diameter (mm)	Material	Hazen-Williams C	Flow (L/s)	Velocity (m/s)
32: P-1	3	CONNECTION AT CAMBRIAN	J-1	200.0	PVC	110.0	83.18	2.65
76: P-2	11	J-1	J-2	200.0	PVC	110.0	83.18	2.65
38: P-3	3	J-2	BLDG B	200.0	PVC	110.0	83.18	2.65
40: P-4	33	BLDG B	H-1	200.0	PVC	110.0	83.16	2.65
63: P-7	10	J-4	J-5	200.0	PVC	110.0	83.16	2.65
65: P-8	12	J-5	J-6	200.0	PVC	110.0	83.16	2.65
67: P-9	54	J-6	J-7	200.0	PVC	110.0	83.16	2.65
69: P-10	20	J-7	J-8	200.0	PVC	110.0	83.16	2.65
71: P-11	29	J-8	H-2	200.0	PVC	110.0	83.16	2.65
75: P-13	7	J-9	BLDG A	200.0	PVC	110.0	0.16	0.01
44: P-5	53	H-1	J-3	200.0	PVC	110.0	83.16	2.65
61: P-6	15	J-3	J-4	200.0	PVC	110.0	83.16	2.65
73: P-12	25	H-2	J-9	200.0	PVC	110.0	0.16	0.01

### JUNCTION TABLE

	Label	Elevation (m)	Demand (L/s)	Hydraulic Grade (m)	Pressure (kPa)
74: BLDG A	BLDG A	94.05	0.16	127.26	325
37: BLDG B	BLDG B	94.12	0.02	137.40	424
31: J-1	J-1	93.80	0.00	138.06	433
35: J-2	J-2	93.95	0.00	137.56	427
78: J-3	J-3	93.70	0.00	133.52	390
60: J-4	J-4	93.70	0.00	132.85	383
62: J-5	J-5	93.80	0.00	132.41	378
64: J-6	J-6	93.90	0.00	131.88	372
66: J-7	J-7	93.45	0.00	129.46	352
68: J-8	J-8	93.25	0.00	128.58	346
72: J-9	J-9	93.90	0.00	127.26	327



### RESERVOIR TABLE

	Label	Elevation (m)	Flow (Out net) (L/s)	Hydraulic Grade (m)
30: CONNECTI	CONNECTION AT CAMBRIAN	138.20	83.18	138.20

### HYDRANT TABLE

	Label	Length (Hydrant Lateral) (m)	Elevation (m)	Demand (L/s)	Hydraulic Grade (m)	Pressure (kPa)
77: H-1	H-1	6	93.85	0.00	135.90	412
79: H-2	H-2	6	93.60	83.00	126.09	318

## DRAWINGS



**EROSION AND SEDIMENT CONTROL MEASURES**

- CONTRACTOR IS RESPONSIBLE FOR ALL INSTALLATION, MONITORING, REPAIR AND REMOVAL OF ALL EROSION AND SEDIMENT CONTROL FEATURES. THE CONTRACTOR SHALL IMPLEMENT BEST MANAGEMENT PRACTICES TO PROVIDE PROTECTION OF THE AREA DRAINAGE SYSTEM AND THE RECEIVING WATER BODY FROM CONSTRUCTION ACTIVITIES. THE CONTRACTOR ACKNOWLEDGES THAT FAILURE TO IMPLEMENT APPROPRIATE EROSION AND SEDIMENT CONTROL MEASURES MAY BE SUBJECT TO PENALTIES IMPOSED BY ANY APPLICABLE REGULATORY AGENCY.
- SEDIMENT AND EROSION CONTROL PLAN OBJECTIVES:
  - PREVENT SOIL EROSION, THIS CAN RESULT FROM STREAMING RAIN WATER OR WIND EROSION DURING CONSTRUCTION.
  - PREVENT SEDIMENT DEPOSITS IN THE SEWER PIPES AND NEARBY COLLECTING STREAMS (AS APPLICABLE).
  - PREVENT AIR POLLUTION FROM PARTICULATE MATTER AND DUST.

**1. PRIOR TO START OF CONSTRUCTION**

- PRIOR TO THE REMOVAL OF ANY VEGETATIVE COVER, MOVING OF SOIL, AND CONSTRUCTION:
  - INSTALL SILT FENCE (AS PER OPSD 219.110) ALONG DISTICHES IMMEDIATELY DOWNSTREAM FROM AREAS TO BE DISTURBED (SEE PLAN FOR LOCATION).
  - INSTALL FILTER CLOTH ON DOWNSTREAM SIDE OF SILT FENCE.
  - INSTALL BLACK FILTERS IN ALL CONCRETE CATCH BASINS STRUCTURES.
  - INSPECT MEASURES IMMEDIATELY.
  - THE CONTRACTOR MUST SET UP THE MEASURES INDICATED ON THE PLAN, INSPECT THEM FREQUENTLY AND CLEAN AND REPAIR OR REPLACE THE DISTURBED STRUCTURES AT THE END OF THE CONSTRUCTION PERIOD, THE CONTRACTOR IS RESPONSIBLE FOR REMOVAL OF THE TEMPORARY STRUCTURES AND RECONSTRUCTION OF THE AFFECTED AREAS.

**2. DURING CONSTRUCTION**

- SEDIMENT AND EROSION CONTROL MEASURES TO BE CONSTRUCTED AS PER OPSD 805.
- WHEN SEDIMENT AND EROSION CONTROL MEASURES MUST BE REMOVED TO COMPLETE A PORTION OF THE WORK, THE SAME MEASURES MUST BE REINSTATED UPON THE WORK'S COMPLETION.
- WORK TO BE DONE IN THE VICINITY OF MAJOR WATERWAYS TO BE CARRIED OUT FROM JULY AND SEPTEMBER ONLY.
- MINIMIZE THE EXTENT OF DISTURBED AREAS AND THE DURATION OF EXPOSURE.
- PROTECT DISTURBED AREAS FROM RUNOFF.
- PROVIDE TEMPORARY COVER SUCH AS SEEDING OR MULCHING IF DISTURBED AREA WILL NOT BE REHABILITATED SHORTLY.
- INSPECT STRAW BALE FLOW CHECK DAMS, SILT FENCES, SILT SACKS, AND CATCH BASIN SUMPS REGULARLY AND AFTER EVERY MAJOR STORM EVENT. CLEAN AND REPAIR WHEN NECESSARY.
- PLAN TO BE REVIEWED AND REVISED AS REQUIRED DURING CONSTRUCTION.
- EROSION CONTROL FENCING TO BE ALSO INSTALLED AROUND THE BASE OF ALL STOCKPILES.
- DO NOT LOCATE TOPSOIL PILES AND EXCAVATION MATERIAL CLOSER THAN 25m FROM ANY PAVED SURFACE OR ONE WHICH IS TO BE PAVED BEFORE THE PILE IS REMOVED. ALL TOPSOIL PILES ARE TO BE SEEDED IF THEY ARE TO REMAIN ON SITE LONG ENOUGH FOR SEEDS TO GROW LONGER THAN 30 DAYS. WHEN STOCKPILE SOIL ON SITE IN PILES THE CONTRACTOR MUST COVER EACH PILE WITH TAPPS, STRAW OR A GEOTEXTILE FABRIC TO AVOID FIRE HAZARD. TRANSPORT WIND AND/OR STREAMING RAIN WATER.
- CONTROL WIND-BLOWN DUST OFF SITE TO ACCEPTABLE LEVELS BY SEEDING TOPSOIL PILES AND OTHER AREAS TEMPORARILY PROVIDE WATERING AS REQUIRED. FOR BEST CONTROL, CONTRACTOR TO APPLY CALCIUM CHLORIDE (TYPE I - OPSD 201 AND CANCO88-15-1) AND WATER WITH EQUIPMENT APPROVED BY THE OWNER'S REPRESENTATIVE AT RATE IN ACCORDANCE TO OPSD 508 WHEN DIRECTED BY OWNER'S REPRESENTATIVE.
- ALL EROSION CONTROL STRUCTURE TO REMAIN IN PLACE UNTIL ALL DISTURBED GROUND SURFACES HAVE BEEN STABILIZED EITHER BY PAVING OR RESTORATION OF VEGETATIVE COVER. SEDIMENT CAPTURE SILT SACKS MUST BE MAINTAINED AND CANNOT BE REMOVED UNTIL ALL LANDSCAPING AREAS ARE COMPLETED.
- NO ALTERNATE METHODS OF EROSION PROTECTION SHALL BE PERMITTED UNLESS APPROVED BY THIS CONSULTING ENGINEER AND THE TOWN DEPARTMENT OF PUBLIC WORKS.
- CONTRACTOR RESPONSIBLE FOR MUNICIPAL, ROADWAY AND SIDEWALK TO BE CLEARED OF ALL SEDIMENT FROM VEHICULAR TRACKING ETC. AT THE END OF EACH WORK DAY.
- DURING WET CONDITIONS, TIRES OF ALL VEHICLES/EQUIPMENT LEAVING THE SITE ARE TO BE SCRAPED.
- ANY MATERIAL TRACKED ONTO THE ROAD SHALL BE REMOVED IMMEDIATELY BY HAND OR RUBBER LOADER.
- TAKE ALL NECESSARY STEPS TO PREVENT BUILDING MATERIAL, CONSTRUCTION DEBRIS OR WASTE BEING SPILLED OR TRACKED ONTO ADJUTING PROPERTIES OR PUBLIC STREETS DURING CONSTRUCTION AND PROCEED IMMEDIATELY TO CLEAN UP ANY AREAS SO AFFECTED.
- PROVIDE GRAVEL ENTRANCES WHEREVER EQUIPMENT LEAVES THE SITE TO PROVIDE MUD TRACKING ONTO PAVED SURFACES. GRAVEL BED SHALL BE A MINIMUM OF 50m LONG, 4m WIDE, AND 1.5m DEEP, AND SHALL CONSIST OF COURSE MATERIAL. MAINTAIN GRAVEL ENTRANCE IN CLEAN CONDITION.

**3. AFTER CONSTRUCTION**

- PROVIDE PERMANENT COVER CONSISTING OF TOPSOIL AND SEED TO DISTURBED AREAS.
- ALL SEDIMENT AND EROSION CONTROL MEASURES TO BE REMOVED BY THE CONTRACTOR FOLLOWING THE COMPLETION OF WORK AND AFTER DISTURBED AREAS HAVE BEEN REHABILITATED AND STABILIZED. THIS INCLUDES REMOVE STRAW BALE FLOW CHECK DAMS, SILT FENCES AND FILTER CLOTHS ON CATCH BASINS AND MANHOLE COVERS.
- INSPECT AND CLEAN CATCH BASIN SUMPS AND STORM SEWERS.

**NOTES, REMOVALS AND DEMOLITION**

- PRE-REMOVAL THE CONTRACTOR MUST VISIT THE PREMISES IN ORDER TO BE FULLY AWARE OF EXISTING CONDITIONS ON SITE, INCLUDING ALL ELEMENTS TO BE REMOVED AND DEMOLISHED. NO CLAIM WILL BE ACCEPTED FOR A DEFICIENT EVALUATION OF THE WORK TO BE COMPLETED.
- THE CONTRACTOR IS RESPONSIBLE FOR LOCKING AND THE REQUEST FOR INTERRUPTION OF PUBLIC UTILITY SERVICES, SUCH AS GAS, TELEPHONE, POWER, CABLE, SEWERS, WATERMAIN, ETC. BEFORE PROCEEDING WITH WORK. COORDINATE WITH ALL APPLICABLE UTILITY COMPANIES.
- FREE MOMENTS TO BE TAGGED AND BAGGED AND/OR PROTECTED AS INDICATED ON DRAWING.
- CURS ASPHALT, SIDEWALK, AND GRANULAR BASE TO BE EXCAVATED WITHIN LIMITS OF DEMOLITION REMOVAL. THE CONTRACTOR MUST CARRY OUT NECESSARY SAW CUTS.
- SEWER/WATERMAIN PIPES TO BE ABANDONED MUST BE CUT, FILL WITH UNDRINKABLE CONCRETE CONFORMING TO OPSD 1505 AND CAPPED.
- REMOVE AND DISPOSE SEWERS AS INDICATED. PLUG ANY SERVICE LATERALS TO BE ABANDONED.
- THE CONTRACTOR MUST ENTIRELY REMOVE THE DEMOLITION WRECKAGE FROM THE CONSTRUCTION SITE OFFSITE IN ACCORDANCE WITH THE REQUIREMENTS OF THE MINISTRY OF ENVIRONMENT AND CLIMATE CHANGE (MEECC).
- THE CONTRACTOR MUST DISCARD AND RECYCLE DEMOLITION WRECKAGE MATERIALS IN COLLABORATION WITH A REGIONAL RECYCLING COMPANY.
- ALL OTHER DEMOLITION MATERIALS MUST BE DISPOSED OFF-SITE AT AUTHORIZED LICENSED LANDFILLS AND IN CONFORMITY WITH THE APPLICABLE LAWS AND REGULATIONS. THE CONTRACTOR MUST BE ABE TO PROVIDE, UPON REQUEST, COPIES OF THE DISPOSAL TICKETS TO THE OWNER'S REPRESENTATIVE.
- SURFACES AND WORKS LOCATED OUTSIDE OF THE CONSTRUCTION WORK LIMIT MUST BE REINSTATED AS THEY WERE BEFORE BEGINNING OF WORK. CONTRACTOR IS RESPONSIBLE TO MAKE GOOD ON ANY DAMAGES TO EXISTING CURBS AND ASPHALT NOT SCHEDULED FOR REMOVAL.
- ALL MATERIALS, PRODUCTS AND OTHERS COMING FROM THE DEMOLITION BELONG TO THE CONTRACTOR. MUST COMPLETE ALL REMOVALS AS SHOWN ON THE DRAWINGS AND AS REQUIRED TO MAKE THE WORK COMPLETE.
- THE CONTRACTOR MUST PROTECT AND MAINTAIN ANY EXISTING WORKS WHICH MUST REMAIN IN PLACE. IF THEY ARE DAMAGED, THE CONTRACTOR MUST IMMEDIATELY MAKE THE REPAIRS AND NECESSARY REPAIRS TO THE SATISFACTION OF THE OWNER'S REPRESENTATIVE AND WITHOUT ADDITIONAL EXPENSE TO THE OWNER.
- THE CONTRACTOR MUST NOT PERFORM ANY TREE CUTTING DURING THE CORE REGULATORY BIRD NESTING PERIOD, WHICH APRIL 15 TO AUGUST 15.

**TURNER FLEISCHER**

Turner Fleischer Architects Inc.  
 67 Leslie Road  
 Toronto, ON M2S 1T5  
 416 425 2322  
 turner@turnerfleischer.com

This drawing, as an instrument of service, is provided by the copyright owner of this drawing, Turner Fleischer Architects Inc., to the client for the use and purposes specified in the contract. It is not to be used for any other purpose without the written consent of Turner Fleischer Architects Inc. The client agrees to indemnify and hold Turner Fleischer Architects Inc. harmless from and against all claims, damages, losses and expenses, including reasonable attorneys' fees, that may be asserted against or incurred by Turner Fleischer Architects Inc. or its employees, agents or consultants in connection with the use of this drawing for any purpose other than that for which it was prepared. This instrument of service shall remain the property of Turner Fleischer Architects Inc. and shall not be reproduced, stored in a retrieval system, or transmitted in any form or by any means, electronic, mechanical, photocopying, recording, or by any information storage and retrieval system, without the prior written consent of Turner Fleischer Architects Inc.

**PARSONS**

1500 MIDLAND STREET, SUITE 900, OTHAWA, ONTARIO K1P 1T3  
 TEL: 613-476-4100 FAX: 613-739-7100

**TOPOGRAPHIC INFORMATION & BENCHMARK**  
 SURVEY COMPLETED BY ANNEB, ORSHANIAN, VOLLEBERG, LTD. ON MARCH 28, 2023. ELEVATIONS SHOWN ARE GIC02516 AND ARE REFERRED TO THE GIC02516 GEOIDETIC DATUM. DERIVED FROM CONTROL MONUMENT NO. 019880071 HAVING AN ELEVATION OF 98.74M.

NO.	DESCRIPTION	DATE	BY



**Loblaw Companies Limited**

**3845 CAMBRIAN RD**  
 BARRHAVEN, ONTARIO

**EROSION/SEDIMENT CONTROL & REMOVALS PLAN**

PROJECT NO: 419876  
 DATE: 2023-02-27  
 DRAWN BY: EV  
 CHECKED BY: MIT  
 TITLES: As Indicated

2023-05-01  
 PROJECT OF ONTARIO



		WATERMAIN TABLE				
STATION	SURFACE ELEVATION	W/M DEPTH	TOP OF W/M ELEV.	INV. OF W/M ELEV.	INV. OF W/M ELEV.	NOTES
0+000	93.66	3.35m	90.31	90.11	90.11	CONNECTION TO EXISTING VALVE
0+002	93.80	3.49m	90.31	90.11	90.11	45° HORIZONTAL BEND
0+003	93.88	3.57m	90.31	90.11	90.11	45° HORIZONTAL BEND
0+005	93.88	2.48m	91.40	91.20	91.20	2 x 45° VERTICAL BENDS
0+007	93.80	2.40m	91.40	91.20	91.20	CR-01 REFER TO CROSSING TABLE
0+011	93.80	2.40m	91.40	91.20	91.20	45° HORIZONTAL BEND
0+014	93.93	2.40m	91.40	91.20	91.20	45° HORIZONTAL BEND
0+015	93.80	2.40m	91.40	91.20	91.20	CR-03 REFER TO CROSSING TABLE
0+017	93.78	2.40m	91.38	91.18	91.18	200x200 TEE, 200mm WATER SERVICE CONNECTION
0+044	93.79	2.40m	91.39	91.19	91.19	CR-05 REFER TO CROSSING TABLE
0+051	93.70	2.40m	91.30	91.10	91.10	200x150 TEE FOR FIRE HYDRANT LATERAL
0+066	93.70	2.40m	91.30	91.10	91.10	CR-08 REFER TO CROSSING TABLE
0+096	93.63	2.40m	91.23	91.03	91.03	CR-11 REFER TO CROSSING TABLE
0+104	93.63	2.40m	91.23	91.03	91.03	45° HORIZONTAL BEND
0+108	93.61	2.40m	91.21	91.01	91.01	CR-12 REFER TO CROSSING TABLE
0+119	93.74	2.40m	91.34	91.14	91.14	45° HORIZONTAL BEND
0+129	93.75	2.40m	91.35	91.15	91.15	45° HORIZONTAL BEND
0+137	93.90	2.40m	91.50	91.30	91.30	CR-13 REFER TO CROSSING TABLE
0+141	93.90	2.40m	91.50	91.30	91.30	45° HORIZONTAL BEND
0+195	93.44	2.40m	91.04	91.84	91.84	45° HORIZONTAL BEND
0+215	93.23	2.40m	90.83	90.63	90.63	45° HORIZONTAL BEND
0+240	93.40	2.40m	91.00	90.80	90.80	CR-14 REFER TO CROSSING TABLE
0+244	93.40	2.40m	91.00	90.80	90.80	200x150 TEE FOR FIRE HYDRANT LATERAL
0+269	93.81	2.40m	91.41	91.21	91.21	45° HORIZONTAL BEND
0+271	93.96	2.40m	91.58	91.38	91.38	45° HORIZONTAL BEND
0+277	94.00	2.40m	91.60	91.40	91.40	SERVICE CONNECTION, CAPPED 1.5m FROM BLDG

ICD SCHEDULE						
ICD ID	LOCATION	ORIFICE INVERT (m)	FLOW 5y/100y (L/s)	HEAD 5y/100y (m)	EQUIVALENT DIAMETER (mm)	MODEL*
1	MHST-37	90.16	287.9337.1	2.032.80	305	SEE D2 ON DWG C104

\*ICD SHOP DRAWINGS SHALL BE SUBMITTED TO PARSONS BEFORE COMMENCING ANY WORK

**NOTES: UNDERGROUND STORMWATER STORAGE**

- UNDERGROUND STORMWATER STORAGE SYSTEM CHAMBER TYPE OR EQUIVALENT STORAGE REQUIREMENT: 150 cu m
- CHAMBER TYPE: STORMTAC SC-740 OR EQUIVALENT
- BOTTOM GRANULAR PAD ELEVATION & PERFORATED SUBURBAN INVERT: 0.20m
- BOTTOM OF CHAMBER ELEVATION: 0.25
- TOP OF CHAMBER ELEVATION: 93.7m
- TOP OF SYSTEM TO BE A MINIMUM OF 450mm BELOW PARKING LOT PAVEMENT

CROSSING TABLE							
CROSSING No.	PIPE ELEV. AT CROSSING	PIPE ELEV. AT CROSSING	CLEARANCE	CROSSING No.	PIPE ELEV. AT CROSSING	PIPE ELEV. AT CROSSING	CLEARANCE
CR-01	STM, TOP 90.85	WM, INV. 91.20	0.25m	CR-08	STM, TOP 91.40	STM, INV. 91.80	0.50m
CR-02	SAN, TOP 88.91	STM, INV. 90.09	1.58m	CR-09	SAN, TOP 90.03	STM, INV. 91.77	1.77m
CR-03	STM, TOP 90.93	WM, INV. 91.20	0.27m	CR-10	SAN, TOP 90.49	STM, INV. 91.75	1.26m
CR-04	SAN, TOP 89.17	WM, INV. 90.24	1.07m	CR-11	WM, TOP 91.23	WM, INV. 91.80	0.57m
CR-05	WM, TOP 91.30	STM, INV. 91.92	0.53m	CR-12	WM, TOP 90.75	WM, INV. 91.01	0.26m
CR-06	SAN, TOP 89.65	STM, INV. 91.69	2.24m	CR-13	STM, TOP 91.08	WM, INV. 91.30	0.22m
CR-07	SAN, TOP 89.76	PHAT, INV. 91.15	1.39m	CR-14	WM, TOP 91.00	STM, INV. 91.97	0.97m

**NOTES: SEWER**

- CONTRACTOR TO CONFIRM ELEVATION OF EXISTING STORM AND SANITARY SEWERS AT PROPOSED CONNECTION POINTS AND REPORT ANY DISCREPANCIES TO THE ENGINEER BEFORE COMMENCING ANY WORK.
- ALL WORK SHALL BE PERFORMED AS APPLICABLE IN ACCORDANCE WITH OPS 407, 407-01 & 407-02.
- ALL STORM AND SANITARY SEWERS INSTALLED BELOW THE GROUNDWATER TABLE ELEVATION (SEE 200mm BLDG. WATER TIGHTNESS AND INSULATION TESTS SHALL BE CARRIED OUT ACCORDING TO OPS 407-01 & 407-02).
- CLAY SEALS PER CROSSING CITY OF OTTAWA STD DETAIL 58 AND EXTENDED AT LEAST 1.5m ABOVE THE GROUNDWATER TABLE ELEVATION.
- PIPE MATERIAL TO BE PVC 80/90 AND CONFORMANCE REQUIREMENTS AS INDICATED OTHERWISE. PVC SEWERS TO BE INSTALLED PER OPS 802/90 (2) UNLESS INDICATED OTHERWISE. UNLESS INDICATED OTHERWISE, ALL SEWERS SHALL BE COVERED WITH 1.5 METERS OF COVER SUBJECT TO INSULATION PER CITY OF OTTAWA STD DETAIL 535.
- ALL SEWERS WITH LESS THAN 1.5 METERS OF COVER SHALL BE COVERED WITH CRUSHER-RUN LIMESTONE BEDDING COMPACTED TO 95% SPMCD.
- PIPE SADDLE MATERIAL TO BE INSTALLED PER OPS 407-01 & 407-02. UNLESS INDICATED OTHERWISE, MAINTENANCE HOLES TO BE 1000mm AS PER OPS 701.010. UNLESS INDICATED OTHERWISE, MAINTENANCE HOLES AND CATCH BASIN MAINTENANCE HOLES TO BE 1000mm AS PER OPS 705.010. UNLESS INDICATED OTHERWISE, CATCH BASINS TO BE INSTALLED PER OPS 402. EXCAVATING, BACKFILLING, AND COMPACTING REQUIRED FOR MAINTENANCE HOLES, CATCH-BASIN MAINTENANCE HOLES, AND CATCH BASINS TO BE COMPLETED AS PER OPS 402. THEY ARE TO BE BACKFILLED WITH OPS GRANULAR & COMPACTED TO 95% SPMCD. JOINTS BETWEEN SECTIONS TO BE WRAPPED WITH NON-WOVEN GEOTEXTILE.
- FOR SANITARY STRUCTURES: CAST IRON MAINTENANCE HOLE COVERS AS PER OPS 402 TYPE 'A'.
- FOR STORM STRUCTURES: CAST IRON CATCH-BASIN MAINTENANCE HOLE COVERS AS PER OPS 402 TYPE 'Y' AND CAST IRON CATCH-BASIN COVER AS PER OPS 402.020.
- SANITARY MAINTENANCE HOLES REQUIRE BENCHING AS PER OPS 701.021.
- THE CONTRACTOR IS RESPONSIBLE FOR MAKING OR ARRANGING ALL CONNECTIONS TO THE EXISTING SEWERS AS PER MUNICIPAL REQUIREMENTS. PRIOR TO CONNECTION, THE CONTRACTOR MUST PROVIDE TO THE CONSULTANT / ENGINEER AND THE CITY FOR APPROVAL, ALL TEST RESULTS PERFORMED ON THE INTERNAL SERVICES.
- ADVISE THE CITY PUBLIC WORKS AT LEAST 24 HOURS IN ADVANCE BEFORE ANY CONNECTION TO THE CITY SERVICES. CO-ORDINATE WITH CITY AS REQUIRED.
- TERMINATE AND PLUG ALL SERVICE CONNECTIONS AT 1.5m FROM EDGE OF THE BUILDING.
- ALL SEWERS TO BE C.C.T.V. INSPECTED BY THE CONTRACTOR AS PER OPS 404. TWO COPIES OF THE INSPECTION REPORT MUST BE PROVIDED TO THE CONSULTANT AND THE C.C.T.V. INSPECTION IN PDF FORMAT ONLY.

**NOTES: WATERMAIN**

- ALL WATERMAIN TO BE INSTALLED AT MINIMUM COVER OF 2.4m BENEATH FINISHED GRADE. WHERE THE MINIMUM COVER OF 2.4m IS NOT REACHED, THERMAL INSULATION IS REQUIRED AS PER CITY OF OTTAWA DETAIL W22.
- WATERMAIN PIPE MATERIALS TO BE CLASS PVC DR-18. CR APPROVED EQUIVALENT, UNLESS INDICATED OTHERWISE.
- WATERMAIN TO BE COVERED WITH 1.5 METERS OF COVER PER OPS 402.020. WATERMAIN BEDDING AND COVER MATERIAL TO BE OPS 1010 GRANULAR A' CRUSHER-RUN LIMESTONE COMPACTED TO 95% SPMCD.
- A CONTINUOUS 1/2 GAUGE COPPER TRACER WIRE MUST BE INSTALLED OVER ALL WATERMANS. TRACER WIRE SHALL BE TIED TO ALL FIRE HYDRANTS.
- INSTALLATION OF A WATERMAIN PIPE CROSSING A SEWER PIPE SHALL BE AS PER CITY OF OTTAWA DETAIL W2 AND W22.
- IF WATERMAIN PIPE MUST BE DEFLECTED TO MEET ALIGNMENT, ENSURE THAT THE AMOUNT OF DEFLECTION USED IS LESS THAN HALF THAT RECOMMENDED BY THE MANUFACTURER.
- CATHODIC PROTECTION REQUIRED FOR ALL IRON FITTINGS AS PER OPS 1109.011. BRUSH OFF AND RESTRAINING AS PER OPS 1103.010 AND OPS 1103.020.
- HYDRANT INSTALLATION AS PER OPS 1105.010 AND OPS 441. HYDRANT TO COMPLY WITH ANWA C50.
- HYDRANTS MUST HAVE THREE EXITS (TWO 63.5mm AND ONE 100.0mm STORZ) OF STAINLESS STEEL WITHOUT DRAIN. FIRE HYDRANTS MUST BE INSTALLED SUCH THAT THE STORZ EXIT POINTS TOWARDS THE BUILDING IT WILL SERVICE. THE CONTRACTOR MUST ENSURE THAT THE BREAKAWAY ANGLE IS LOCATED ABOVE THE FINISHED GROUND (APPROXIMATELY 150mm).
- FIRE FLOW TESTS FOLLOWED BY COLORADO COUING OF HYDRANTS AS PER NFPA 291 SHALL BE CARRIED OUT PRIOR TO SUBSTANTIAL COMPLETION OF THE WORK.
- WATERMAIN AND HYDRANT CONTROL VALVES IN THE 900 - 300mm RANGE WILL BE RESILIENT SEATING GATE VALVES (AWSS) WITH MECHANICAL JOINT CONNECTIONS. VALVES WILL OPERATE COUNTERCLOCKWISE TO OPEN WITH A NON-SHOCKING STEEL VALVE WILL COMPLY WITH THE STANDARD ANWA 010mm OPERATING NUT. VALVES TO BE INSTALLED AS PER OPS 441.
- FIRE FITTINGS, BENDS, TEES, CROSSERS, REDUCERS, ETC) WILL BE MECHANICAL JOINT (ANWA C-11) WITH CEMENT MORTAR LINING (ANWA C-14).
- COULERS MUST BE COMPRESSIVE TYPE (MINIMUM PRESSURE RATING OF 105 MPa). COULERS MUST BE MUELLER 11-12049.
- VALVE BOXES MUST BE COMPLETELY METALLIC) 3/8" PILE SLIDING TYPE WITH GUIDE PLATES.
- ALL WATERMANS MUST BE THOROUGHLY FLUSHED AND CLEANED TO REMOVE ALL DIRT AND DEBRIS PRIOR TO THE DISINFECTION PROCESS.
- ALL WATERMANS SHALL BE TESTED FOR LEAKS AND BACTERIOLOGICALLY TESTED AS PER PROVINCIAL AND MUNICIPAL REGULATIONS. IF THE CONTRACTOR'S RESPONSIBILITY TO ENSURE THAT ALL WATERMAIN PIPES ARE FLUSHED WITH THE CHLORINE LEVEL IN THE WATER IS SIMILAR TO THE LEVEL OF CHLORINE IN THE MUNICIPAL WATERMAIN NETWORK IN THE AREA.
- BACTERIOLOGICAL TESTING MUST CONSIST OF TWO SAMPLINGS TWENTY FOUR HOURS APART. IF BACTERIOLOGICAL SAMPLES ARE SATISFACTORY, THE WATERMAIN MAY BE PLACED INTO USE.
- ALL WATERMAIN VALVES TO BE OPERATED BY THE CITY OF OTTAWA ONLY.

**TURNER FLEISCHER**  
 Turner Fleischer Architects Inc.  
 67 Lash Road  
 Toronto, ON M5S 1A5  
 416 429 2222  
 turner@turnerfleischer.com

**PARSONS**  
 1500 MIDLAND STREET, SUITE 100, OTTAWA, ONTARIO K1T 1T3  
 TEL: 613 976 4766 FAX: 613 976 7010

**TOPOGRAPHIC INFORMATION & BENCHMARK**  
 SURVEY COMPLETED BY ANNE, CRABHORN, VOLLEBERG, LTD. ON MARCH 26, 2023. ELEVATIONS SHOWN ARE GEODETIC AND ARE REFERRED TO THE GROUND GEODETIC DATUM, DERIVED FROM CONTROL MONUMENT NO. 01968001 HAVING AN ELEVATION OF 99.742m.


**Loblaw Companies Limited**

3845 CAMBRIAN RD  
 BARRHAVEN, ONTARIO

**PROJECT INFORMATION**

PROJECT NO.	419876
PROJECT TITLE	3845 CAMBRIAN RD
DATE	2023-02-27
BY	MM
CHECKED BY	MM
DATE	2023-06-01
SCALE	As Indicated





**LEGEND**

- EXISTING PROPERTY LINE
- EXISTING DITCH/SWALE CENTERLINE
- TERRACE (3:1 MAX)
- EXISTING GRADE
- ▨ PROPOSED GRADE
- ▧ PROPOSED TOP OF WALL GRADE
- ▩ PROPOSED BOTTOM OF WALL GRADE
- ▧ PROPOSED FINISHED FLOOR ELEVATION
- ▧ PROPOSED TOP OF CURB ELEVATION
- ▧ PROPOSED CENTRELNE OF DITCH/SWALE GRADE
- ▧ PROPOSED SLOPE DIRECTION AND PERCENTAGE
- PROPOSED STORM MAINTENANCE HOLE
- PROPOSED SANITARY MAINTENANCE HOLE
- PROPOSED CATCH BASIN
- ▧ PROPOSED REAR YARD CATCH BASIN AS PER CITY STD DWG S-1
- ▧ PROPOSED LIGHT DUTY PAVEMENT
- ▧ PROPOSED HEAVY DUTY PAVEMENT
- ▧ PROPOSED TEMPORARY HEAVY DUTY PAVEMENT
- ▧ PROPOSED CONCRETE SIDEWALK
- ▧ PROPOSED CONCRETE STRUCTURAL SLAB PER STRUCTURAL
- ▧ PROPOSED CONCRETE CURB
- ▧ PROPOSED DEPRESSED CONCRETE CURB WITH TWSI PER CITY STD DWG S-7.3
- ▧ PROPOSED LIGHT STANDARD
- ▧ APPROXIMATE LIMIT OF GRADING ON NEIGHBOURING PROPERTY

**PAVEMENT STRUCTURES**

MATERIAL	LIGHT DUTY	HEAVY DUTY	COMPACTION
SURFACE LAYER : HLS	85 mm	40 mm	≥ 96%
BASE LAYER : HLB	--	60 mm	≥ 96%
GRANULAR BASE : OPSS MUNI 1010 GRANULAR A	150 mm	150 mm	100%*
GRANULAR SUB-BASE : OPSS MUNI 1010 GRANULAR B	300 mm	450 mm	100%*

\*MINIMUM PAVEMENT COMPACTION BASED ON MARSHALL DENSITY TEST "OF THE STANDARD PROCTOR MAXIMUM DRY DENSITY"  
 SOURCE: GEOTECHNICAL INVESTIGATION, WEST OF CAMBRIAN ROAD AND GREENBANK ROAD, BARRHAVEN, ONTARIO, BY TORONTO INSPECTION LTD, DATED NOVEMBER 13, 2018

**NOTES - GENERAL**

- THE CONTRACTOR MUST CONFORM TO ALL LAWS, CODES, ORDINANCES, AND REGULATIONS ADOPTED BY FEDERAL, PROVINCIAL OR MUNICIPAL GOVERNMENT COUNCILS AND GOVERNMENT AGENCIES, APPLYING TO WORK TO BE CARRIED OUT. WHEREVER STANDARDS, LAWS AND/OR REGULATIONS ARE MENTIONED THEY REFER TO THEIR CURRENT VERSIONS UNLESS OTHERWISE SPECIFIED.
- ALL MATERIALS AND CONSTRUCTION METHODS SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE ONTARIO PROVINCIAL STANDARD SPECIFICATIONS AND DRAWINGS (OPSS AND OPSD). THE ONTARIO MINISTRY OF ENVIRONMENT AND CLIMATE CHANGE, THE ONTARIO MINISTRY OF NATURAL RESOURCES, APPLICABLE CONSTRUCTION AUTHORITIES, THE MUNICIPAL STANDARD SPECIFICATIONS AND DRAWINGS, AND ALL OTHER GOVERNING AUTHORITIES AS THEY APPLY UNLESS OTHERWISE INDICATED.
- ALL MATERIALS SUPPLIED AND PLACED FOR PARKING LOT AND ACCESS ROAD CONSTRUCTION SHALL BE TO OPSS STANDARDS AND SPECIFICATIONS UNLESS OTHERWISE NOTED. CONSTRUCTION TO OPSS 208.1 AND 3.14 MATERIALS TYPES 1001, 1002 & 1010.
- THE LOCATION OF EXISTING UNDERGROUND SERVICES AND PUBLIC UTILITIES AS SHOWN ON THE PLANS ARE APPROXIMATE. THE CONTRACTOR MUST DETERMINE THE EXACT LOCATION, SIZE, MATERIAL AND DEPTH OF EXISTING UTILITIES (ON-SITE AND OFF-SITE) PRIOR TO ANY EXCAVATION WORK. DAMAGE TO ANY EXISTING SERVICES AND/OR EXISTING UTILITIES THROUGH CONSTRUCTION, WHETHER OR NOT SHOWN ON THE DRAWINGS MUST BE REPAIRED BY THE CONTRACTOR AT HIS OWN EXPENSE.
- THE CONTRACTOR SHALL DETERMINE THE EXACT INVERT (GEODETIC ELEVATION), DIAMETER AND CONNECTIONS OF ALL EXISTING UTILITIES AT THE PROPOSED CONNECTIONS. THEY SHALL ALSO CARRY OUT, IF NECESSARY, EXPLORATORY DIGS IN ORDER TO DETERMINE THE EXACT LOCATION AND INVERTS OF EXISTING DUCK BANKS. THIS INFORMATION SHALL IMMEDIATELY BE PROVIDED TO THE CONSULTANT PRIOR TO START UNDERTAKING ANY EXCAVATION WORK AND A 48 HOUR PERIOD MUST BE ALLOCATED TO THE CONSULTANT FOR DESIGN REVIEW.
- AT PROPOSED UTILITY CONNECTION POINTS AND CROSSINGS (I.E. STORM SEWER, SANITARY SEWER, WATER, ETC.) THE CONTRACTOR SHALL DETERMINE THE PROPOSED LOCATION AND DEPTH OF EXISTING UTILITIES AND REPORT ANY DISCREPANCIES TO THE ENGINEER BEFORE COMMENCING WORK.
- CONTRACTOR IS RESPONSIBLE FOR ALL LAYOUT FOR CONSTRUCTION PURPOSES.
- THE CONTRACTOR IS RESPONSIBLE FOR THE COORDINATION OF ALL WORK AND ACTIVITIES WITH OTHER TRADES AND CONTRACTORS.
- THE CONTRACTOR IS THE PERSON IN CHARGE OF SAFETY ON THE BUILDING SITE. THE CONTRACTOR IS RESPONSIBLE FOR PROVIDING ADEQUATE PROTECTION OF THE WORKERS, OTHER PERSONNEL AND THE GENERAL PUBLIC. PROTECTION OF MATERIALS, AS WELL AS MAINTAINING IN GOOD CONDITION THE COMPLETED WORKS AND WORKS TO BE COMPLETED, THE CONTRACTOR MUST PROVIDE AT ALL TIMES:
  - a. A SUFFICIENT NUMBER OF FENCES, BARRIERS, POSTERS, GUARDS AND OTHERS TO INFRINGE LAWS.
  - b. NECESSARY CONVENIENCES FOR THE COMPLETION OF WORK SUCH AS HEATING, LIGHTING, VENTILATION ETC.
- CONTRACTOR IS RESPONSIBLE TO OBTAIN THE VARIOUS PERMITS/APPROVALS REQUIRED TO COMPLETE ALL THE WORKS AND ACTIVITIES AND BEAR COST OF THE SAME, SUCH AS BUT NOT LIMITED TO, ROAD CUT PERMITS, SEWER PERMITS, WATER PERMIT ETC. AND THEIR ASSOCIATED COSTS.
- ALL ELEVATIONS ARE GEODETIC AND UTILITY METRE UNITS.
- JOB BENCH MARK - CONFIRM WITH PARSONS PRIOR TO UTILIZATION. THE CONTRACTOR MUST MAINTAIN BENCHMARKS AND LANDMARK REFERENCES AS IS OTHERWISE THESE REFERENCES WILL BE REPOSITIONED BY A CERTIFIED LAND SURVEYOR AT THE CONTRACTOR'S EXPENSE.
- ALL GROUND SURFACES SHALL BE EVENLY GRADED WITHOUT POONDING AREAS AND LOW POINTS EXCEPT WHERE APPROVED SWALE OR CATCH BASIN UTILITIES ARE PROVIDED.
- IF GROUNDWATER IS ENCOUNTERED DURING CONSTRUCTION, DEWATERING OF EXCAVATIONS COULD BE REQUIRED. IT IS ASSUMED THAT GROUNDWATER MAY BE CONTROLLED BY SUMP AND PUMPING METHODS. THE CONTRACTOR SHALL OBTAIN A PERMIT TO TAKE WATER IF SITE CONDITIONS REQUIRE TAKING MORE THAN A TOTAL OF 49,000 LITRE.
- STRIP AND REMOVE ALL TOPSOIL FROM IMPROVED AREAS. SITE PREPARATION INCLUDES CLEARING, GRUBBING, STRIPPING OF TOPSOIL, DECONTAMINATION, REMOVAL OF UNSUITABLE MATERIALS, CUT, FILL AND ROUGH GRADING OF ALL AREAS TO RECEIVE FINISHED SURFACES.
- ADJUSTING PROPERTY GRADE TO BE MATCHED.
- ALL EDGES OF DISTURBED PAVEMENT SHALL BE SAW CUT TO FORM A NEAT AND STRAIGHT LINE PRIOR TO PLACING NEW PAVEMENT. PAVEMENT REINSTATEMENT SHALL BE WITH STEP JOINTS OF 300mm WIDTH MINIMUM.
- CURBS TO BE BARRIER, CONSTRUCTED AS PER OPSS 600.110, EXCEPT WHERE INDICATED OTHERWISE. ELEVATION AT TOP OF CONCRETE CURB NOT TO EXCEED 150mm ABOVE THE ASPHALT UNLESS OTHERWISE INDICATED ON THE DRAWINGS.
- DEPRESSED CURBS TO BE KEYSHAPED, CONSTRUCTED TO PER OPSS 600.100.
- LIGHT DUTY AND HEAVY DUTY ASPHALT PAVEMENTS TO BE CONSTRUCTED AS PER TABLE ON DRAWING 010.
- TRANSITION BETWEEN EXISTING AND PROPOSED PAVEMENT SHALL BE CONSTRUCTED PER DETAIL ON DRAWING 010.
- RESTORE PAVEMENT STRUCTURE AND SURFACES ON EXISTING ROADS TO A CONDITION AT LEAST EQUAL TO ORIGINAL AND TO THE SATISFACTION OF THE MUNICIPAL AUTHORITIES.
- CLEANLINESS ON THE SITE INCLUDES THE CONTRACTOR SHALL CLEAN ROADWAYS AT HIS OWN COST AS DIRECTED BY THE OWNER'S REPRESENTATIVE. MATERIALS AND EQUIPMENT MUST BE LAD OUT IN AN ORGANIZED AND SAFE MANNER, AND ALL MATERIAL, EQUIPMENT AND TEMPORARY STRUCTURES WHICH ARE NO LONGER NECESSARY FOR THE EXECUTION OF THE CONTRACT MUST BE REMOVED FROM THE SITE.
- CONTRACTOR TO ENSURE SATURATION MEASURES ARE IMPLEMENTED TO REDUCE THE RISK OF GROUND CONTAMINATION FROM PETROLEUM PRODUCTS.
- THE CONTRACTOR MUST ENSURE THE FOLLOWING MEASURES ARE IMPLEMENTED REGARDING THE HANDLING OF CONCRETE:
  - a. CONCRETE SHOULD EITHER BE MOVED AWAY FROM THE SITE OR SHOULD BE PREPARED ON SAVED SURFACES IF ONLY SMALL QUANTITIES ARE REQUIRED (I.E. MINOR REPAIRS).
  - b. EXCESS CONCRETE MUST BE DISPOSED OFF-SITE AT A LOCATION THAT MEETS ALL REGULATORY REQUIREMENTS.
  - c. THE WASHING OF CONCRETE TRUCKS AND OTHER EQUIPMENT USED FOR MIXING CONCRETE SHOULD NOT BE CARRIED OUT WITHIN 30 METERS OF A WATERCOURSE OR WETLAND AND SHOULD TAKE PLACE OUTSIDE OF THE WORK SITE.
  - d. ALL CONCRETE TRUCKS SHOULD COLLECT THEIR WASH WATER AND RECYCLE IT BACK INTO THEIR TRUCKS FOR DISPOSAL OFF-SITE AT A LOCATION MEETING ALL REGULATORY REQUIREMENTS.
- THE CONTRACTOR SHALL ENSURE THAT ALL EXCAVATED SURPLUS MATERIALS THAT WILL BE REQUIRED TO BE DISPOSED OFF-SITE BE STOCKPILED TEMPORARILY FOR SAMPLING PRIOR BEING LOADED OFF-SITE.
- MINOR DISTURBANCES TO EXISTING VEGETATION DURING THE EXECUTION OF ALL WORKS.
- TRENCHING, BACKFILLING AND COMPACTING MUST CONFORM TO OPSS 401.
- DEWATERING OF PIPELINE, UTILITY AND ASSOCIATED STRUCTURE EXCAVATIONS TO BE COMPLETED ALL PER OPSS 801.
- THE CONTRACTOR MUST CONTROL SURFACE RUNOFF FROM PRECIPITATION DURING CONSTRUCTION.
- FOR ALL GEOTECHNICAL WORK, CONTRACTOR TO REFER TO "GEOTECHNICAL INVESTIGATION WEST OF CAMBRIAN ROAD AND GREENBANK ROAD, BARRHAVEN, ONTARIO BY TORONTO INSPECTION LTD, DATED NOVEMBER 13, 2018"
- REMOVE FROM SITE ALL EXCESS EXCAVATED MATERIAL UNLESS OTHERWISE DIRECTED BY THE ENGINEER. EXCAVATE AND REMOVE ALL ORGANIC MATERIAL AND DEBRIS LOCATED WITHIN THE PROPOSED BUILDING, PARKING AND ROADWAY LOCATIONS.
- THE CONTRACTOR IS RESPONSIBLE FOR ALL EXCAVATION BACKFILL AND REINSTATEMENT OFF ALL AREAS DISTURBED DURING CONSTRUCTION TO EXISTING CONDITIONS OR BETTER, INCLUDING WEDDING TO THE SATISFACTION OF THE CONSULTANT AND MUNICIPAL AUTHORITIES. ASPHALT REINSTATEMENT MUST BE IN ACCORDANCE WITH OPSS 310. LANDSCAPE REINSTATEMENT WITH 150mm OF TOPSOIL AND 300mm OF SUBSOIL IN ACCORDANCE WITH OPSS 802 AND OPSS 803.
- DURING THE CONSTRUCTION PERIOD, THE CONTRACTOR IS RESPONSIBLE FOR INSTALLING AND MAINTAINING TEMPORARY TRAFFIC SIGNAGE, INCLUDING TRAFFIC SIGNS, TRAFFIC BARRIERS AND TEMPORARY TRAFFIC LIGHTS AND FLAGMANS, AS REQUIRED BY THE OWNER, THE CONSULTANT, THE MUNICIPALITY, THE MTO, AND OTHER GOVERNING AUTHORITIES.
- CONSTRUCT SIDEWALK EXPANSION JOINTS & CONTROL JOINTS AS PER OPSS 310.020.
- CONSTRUCT CONCRETE SIDEWALK AS PER OPSS 310.020 AND OPSS 351. TACTILE WALKING SURFACE INDICATORS PER OPSS 351.
- DISPOSE OF CONTAMINATED MATERIALS AT APPROPRIATE OFF-SITE FACILITY THAT MEETS ALL REGULATORY REQUIREMENTS.
- BE PREPARED TO INTERCEPT, CLEAN UP, AND DISPOSE OF SPILLS OR RELEASES THAT MAY OCCUR WHETHER ON LAND OR WATER. BARRIER MATERIALS AND EQUIPMENT REQUIRED FOR CLEANUP OF SPILLS OR RELEASES READILY ACCESSIBLE ON SITE.
- PROMPTLY REPAIR SPILLS AND RELEASES POTENTIALLY CAUSING DAMAGE TO ENVIRONMENT TO AUTHORITY HAVING JURISDICTION OR INTEREST IN SPILL OR RELEASE INCLUDING CONSERVATION AUTHORITY, WATER SUPPLY AUTHORITIES, DRAINAGE AUTHORITY, ROAD AUTHORITY AND FIRE DEPARTMENT.
- DECONTAMINATE EQUIPMENT AFTER WORKING IN POTENTIALLY CONTAMINATED WORK AREAS AND PRIOR TO SUBSEQUENT WORK OR TRAVEL ON CLEAN AREAS. DO NOT DISCHARGE DECONTAMINATED WATER OR SURFACE WATER RUNOFF, OR GROUNDWATER WHICH MAY HAVE COME IN CONTACT WITH POTENTIALLY CONTAMINATED MATERIAL, OFF SITE OR ON WORK SITE.
- CONTRACTOR IS TO SUBMIT A TRAFFIC MANAGEMENT PLAN FOR APPROVAL ONE (1) WEEK PRIOR TO ANY WORK WITHIN THE ROW LIMITS TO MEET THE REQUIREMENTS OF MTO BOOK 7. THE CONTRACTOR WILL BE REQUIRED TO IMPLEMENT ALL REQUIREMENTS OF THE MTO BOOK 7.
- CITY PUBLIC WORKS DEPARTMENT TO BE CONTACTED MINIMUM 7 DAYS PRIOR TO PLANNED DATE FOR CONNECTION TO EXISTING STORM SEWER, SANITARY SEWERS, AND WATERMAIN. CONNECTION TO EXISTING TO TAKE PLACE IN THE PRESENCE OF APPROPRIATE CITY OF OTTAWA STAFF.

**TURNER FLEISCHER**  
 Turner Fleischer Architects Inc.  
 67 Leslie Road  
 Toronto, ON M2H 1P5  
 T 416 429 2222  
 turner@turnerfleischer.com

**PARSONS**  
 150 KING STREET SUITE 1000 TORONTO ONTARIO M5X 1C7  
 T 416 593 4100 Fax: 416 593 7100

**TOPOGRAPHIC INFORMATION & BENCHMARK**  
 SURVEY COMPLETED BY ANNE, ORSHANIAN WILKINS, LTD ON MARCH 28, 2023. ELEVATIONS SHOWN ARE GEODETIC AND ARE REFERRED TO THE GDS08 GEODETIC DATUM. DERIVED FROM CONTROL MONUMENT NO. 01968001 HAVING AN ELEVATION OF 94.742m.


**Loblaw Companies Limited**

PROJECT: 3845 CAMBRIAN RD  
 BARRHAVEN, ONTARIO


GRADING PLAN

PROJECT NO: 419876  
 PROJECT DATE: 2023-02-27  
 DRAWN BY: BV  
 CHECKED BY: MIT  
 DATE: 2023-06-01  
 AS INDICATED


DATE: 2023-06-01  
 SCALE: 1:1




SILT SACK DETAIL  
**PARSONS** D1







FRAME & PLATE ICD  
**PARSONS** D2




**PARSONS** D3




TYPICAL SUBDRAIN DETAIL  
**PARSONS** D4




**PARSONS** OPSD 791.021




**PARSONS** OPSD 791.021




**Oltava** OPSD 105B.020




**Oltava** OPSD 105B.020




**Oltava** OPSD 705.010




**Oltava** OPSD 705.010




**Oltava** OPSD 705.010




**Oltava** OPSD 791.021




**Oltava** OPSD 791.021




**Oltava** OPSD 791.021




**Oltava** OPSD 791.021




**Oltava** OPSD 105B.020




**Oltava** OPSD 705.010




**Oltava** OPSD 705.010




**Oltava** OPSD 791.021




**Oltava** OPSD 708.030




**Oltava** OPSD 708.030




**Oltava** OPSD 708.030



**Oltava** OPSD 708.030



**Oltava** OPSD 708.030









**Oltava** OPSD 219.110



This drawing, as an instrument of service, is provided to you in the property of Turner Fleischer Architects Inc. It is to be used only for the project and site identified on this drawing. It is not to be used for any other project or site without the written consent of Turner Fleischer Architects Inc. The user assumes full responsibility for the accuracy of the information provided herein. Turner Fleischer Architects Inc. does not warrant the accuracy of the information provided herein. Turner Fleischer Architects Inc. shall not be held liable for any damages or losses resulting from the use of this drawing, whether or not such damages or losses were foreseeable at the time of the drawing. Turner Fleischer Architects Inc. shall not be held liable for any damages or losses resulting from the use of this drawing, whether or not such damages or losses were foreseeable at the time of the drawing.




1333 MICHAEL STREET SUITE 500 OTTAWA, ONTARIO K1P 1T3  
 Tel: 613-738-4100 Fax: 613-739-7100



**THRUST BLOCK DIMENSION TABLES FOR PVC AND DI PIPE 400mm AND UNDER**

PIPE SIZE (mm)	THRUST BLOCK LENGTH (mm)	THRUST BLOCK WIDTH (mm)	THRUST BLOCK HEIGHT (mm)
100	1000	1000	1000
150	1500	1500	1500
200	2000	2000	2000
250	2500	2500	2500
300	3000	3000	3000
350	3500	3500	3500
400	4000	4000	4000



**TABLES OF RESTRAINED LENGTHS FOR PVC AND DI PIPE 400mm AND UNDER**

PIPE SIZE (mm)	RESTRAINED LENGTH (mm)	RESTRAINED LENGTH (mm)	RESTRAINED LENGTH (mm)	RESTRAINED LENGTH (mm)	RESTRAINED LENGTH (mm)
100	1000	1000	1000	1000	1000
150	1500	1500	1500	1500	1500
200	2000	2000	2000	2000	2000
250	2500	2500	2500	2500	2500
300	3000	3000	3000	3000	3000
350	3500	3500	3500	3500	3500
400	4000	4000	4000	4000	4000



PROJECT NO.	4198216
PROJECT DATE	2023-02-27
DRAWN BY	EV
CHECKED BY	MT
TITLE	As Indicated

**Loblaw Companies Limited**

**PROJECT**  
 3845 CAMBRIAN RD  
 BARRHAVEN, ONTARIO

**DETAIL PAGE 2**

PROJECT NO.	4198216
PROJECT DATE	2023-02-27
DRAWN BY	EV
CHECKED BY	MT
TITLE	As Indicated



This drawing, as an instrument of service, is provided to you in the property of Turner Fleischer Architects Inc. The copyright for this work and all other intellectual property contained herein remains with us and shall only be used by Turner Fleischer Architects Inc. Any violation, use or reproduction of this drawing, plan, specification, schedule, contract or any other document without the written consent of Turner Fleischer Architects Inc. is prohibited. This drawing is not to be used for any other project without the written consent of Turner Fleischer Architects Inc. The user shall be responsible for the accuracy of the information contained herein and shall be responsible for any errors or omissions. Turner Fleischer Architects Inc. shall not be liable for any damages, including consequential damages, arising from the use of this drawing, plan, specification, schedule, contract or any other document. For any questions or drawings involving this drawing, please contact Turner Fleischer Architects Inc. at 1 416 425 2222.



1333 MICHAEL STREET, SUITE 500, OTTAWA, ONTARIO K1P 1T3  
 Tel: 613 738-4765 Fax: 613 738-7705

PROJECT NO.	4198216
PROJECT DATE	2023-02-27
DRAWN BY	EV
CHECKED BY	MT
TICKS	As indicated

**Loblaw Companies Limited**

**3845 CAMBRIAN RD**  
 BARRHAVEN, ONTARIO

**POST-DEVELOPMENT DRAINAGE AREAS**

PROJECT NO.	4198216
PROJECT DATE	2023-02-27
DRAWN BY	EV
CHECKED BY	MT
TICKS	As indicated

