

# TECHNICAL MEMORANDUM

---

**DATE:** MARCH 24, 2023  
**TO:** VLADIMIR POPOVIC  
**FROM:** CARA RUDDLE, P.ENG.  
**RE:** VINCENT MASSEY PUBLIC SCHOOL BUS LOOP  
745 SMYTH ROAD  
STORMWATER MANAGEMENT BRIEF

---

Novatech has been retained to prepare a Stormwater Management Brief for a proposed bus loop to be constructed on the south side of Vincent Massey Public School located at 745 Smyth Road in Ottawa. **Figure 1** is a Key Plan showing the site location. The purpose of this brief is to provide the stormwater management concept for the proposed bus loop.

The existing property is currently developed and includes the Vincent Massey Public School building, a parking lot, football field, outdoor basketball court, grassed areas with some trees. The property is approximately 3.84 hectares in size and is bound to the north by several residential properties, to the south by Smyth Road, to the east by Haig Drive and to the west by Edgcombe Street. The topography of the proposed work area generally slopes from west to east. **Figure 2** Existing Conditions Plan shows the existing site conditions and topography.


It is proposed to construct a bus loop along the front of the school that will include an ingress and an egress to Smyth Road. The existing parking lot access from Smyth Road will be closed and the parking lot will be accessed using the existing entrance from Edgcombe Street. **Figure 3** shows the proposed Bus Loop Plan. Only modifications relating to staff parking and school bus access are proposed, there will not be any modifications or expansions to the school building. Therefore, stormwater management will be provided for the re-constructed area only.

## STORMWATER MANAGEMENT

Stormwater currently sheet drains from the front of the building towards roadside catchbasins along Smyth Road. The following stormwater management criteria was provided by the City of Ottawa at the Pre-Consultation meeting with City staff:

- The 2-yr storm or 5-yr storm event using IDF information derived from the Meteorological Services of Canada rainfall data, taken from the MacDonald Cartier Airport, collect 1966 to 1997.

M:\2022\122204\CAD\Civil\Figures\Servicing\122204-KP.dwg, Fig 1, Mar 20, 2023 - 8:13am, madeotl



**SITE**



Engineers, Planners & Landscape Architects  
 Suite 200, 240 Michael Cowpland Drive  
 Ottawa, Ontario, Canada K2M 1P6

Telephone (613) 254-9643  
 Facsimile (613) 254-5867  
 Website www.novatech-eng.com



VINCENT MASSEY PUBLIC SCHOOL  
 745 SMYTH ROAD

**KEY PLAN**

SCALE		N.T.S	
DATE	JOB	FIGURE	
FEB 2023	122204	FIG 1	

M:\2022\122204\CAD\Civil\Figures\Servicing\122204-Ex con.dwg, Ex Con, Mar 20, 2023 - 8:30am, madeo1



**NOVATECH**  
 Engineers, Planners & Landscape Architects  
 Suite 200, 240 Michael Cowpland Drive  
 Ottawa, Ontario, Canada K2M 1P6  
 Telephone (613) 254-9643  
 Facsimile (613) 254-5867  
 Website www.novatech-eng.com


VINCENT MASSEY PUBLIC SCHOOL  
 745 SMYTH ROAD

**EXISTING CONDITIONS  
 PLAN**

SCALE 1 : 500

DATE	JOB	FIGURE
DEC 2022	122204	FIG 2

M:\2022\122204\CAD\Civil\Figures\Servicing\122204-Pro con.dwg, Pro Con, Mar 20, 2023 - 8:36am, madeoit



No. 745  
The Vincent Massey Public School  
2 Storey  
Brick sided Building  
FFE = 76.20



**NOVATECH**  
Engineers, Planners & Landscape Architects  
Suite 200, 240 Michael Cowpland Drive  
Ottawa, Ontario, Canada K2M 1P6  
Telephone (613) 254-9643  
Facsimile (613) 254-5867  
Website www.novatech-eng.com

VINCENT MASSEY PUBLIC SCHOOL  
745 SMYTH ROAD

**PROPOSED BUS LOOP  
PLAN**

SCALE 1 : 500

DATE DEC 2022 JOB 122204 FIGURE FIG 3

- For separated sewer system built pre-1970 the design of the storm sewer is based on a 2-year storm
- The pre-development runoff coefficient or a maximum equivalent 'C' of 0.5, whichever is less (subsection 8.3.7.3).
- A calculated time of concentration (Cannot be less than 10 minutes).
- Flows to the storm sewer in excess of the 2-year storm release rate, up to and including the 100-year storm event, must be detained on site.
- For a combined sewer system, the maximum C=0.4 or the pre-development C value, whichever is less. In the absence of other information, the allowable release rate shall be based on a 2-year storm event.

Existing drainage patterns will be maintained under post-development conditions. All runoff from the proposed bus loop will be collected in a swale and outlet to the existing storm sewer system along Smyth Road per existing conditions. Only the bus loop portion of the development is considered in the stormwater management design. There are minimal changes proposed to the existing parking lot and existing drainage patterns will be maintained. Refer to the attached pre-development and post-development drainage area plans (**Figure 4** and **Figure 5**) for details.


Quantity control of stormwater is provided, and stormwater will be stored on the surface within the grassed swale and below the surface within a proposed subdrain and granular surround below the grassed swale located in the centre of the bus loop. The release of stormwater will be controlled by an orifice control prior to releasing to the City storm sewer system. In storm events greater than the 100-year storm, stormwater will continue to drain to the grassed swale and flow through a depressed curb cut at the entrance of the bus loop and into the Smyth Road right-of-way. The table below summarizes the flow, storage required, and storage provided for the proposed development.

#### Stormwater Management Summary

Area ID	Area (ha)	Weighted Cw	Outlet Location	100 Year Storm Event		
				Flow (L/s)	Required Vol (cu.m)	Max. Vol. Provided (cu.m.)
A1	0.317	0.61	Smyth Rd	16.7	58.78	60.35
<b>Total Flow</b>				<b>16.7</b>		
<b>Allowable Flow</b>				<b>16.7</b>		





Refer to the appendix for stormwater calculations and drainage area plans. Refer to the Grading and Servicing Plan (dwg 122204-GS) for details.

M:\2022\122204\CAD\Civil\Figures\Servicing\122204-Pro con.dwg, PRE, Mar 20, 2023 - 8:36am, maddoiti



No. 745  
The Vincent Massey Public School  
2 Storey  
Brick sided Building  
FFE = 76.20

**LEGEND**


-  PROPERTY LINE
-  EXISTING STORM SEWER
-  PRE DEVELOPMENT DRAINAGE AREA
-  DRAINAGE AREA ha  
DRAINAGE AREA IDENTIFIER  
RUNOFF COEFFICIENT



**NOVATECH**  
Engineers, Planners & Landscape Architects  
Suite 200, 240 Michael Cowpland Drive  
Ottawa, Ontario, Canada K2M 1P6  
Telephone (613) 254-9643  
Facsimile (613) 254-5867  
Website www.novatech-eng.com


VINCENT MASSEY PUBLIC SCHOOL  
745 SMYTH ROAD

**PRE DEVELOPMENT  
DRAINAGE AREA PLAN**

SCALE 1 : 500 



DATE DEC 2022 JOB 122204 FIGURE FIG 4

M:\2022\122204\CAD\Civil\Figures\Servicing\122204-Pro con.dwg, POST, Mar 24, 2023 - 3:57pm, macedoi



No. 745  
The Vincent Massey Public School  
2 Storey  
Brick sided Building  
FFE = 76.20

**LEGEND**

-  PROPERTY LINE
-  EXISTING STORM SEWER
-  PRE DEVELOPMENT DRAINAGE AREA

0.183  
PRE  
0.5

- DRAINAGE AREA ha
- DRAINAGE AREA IDENTIFIER
- RUNOFF COEFFICIENT




**NOVATECH**  
Engineers, Planners & Landscape Architects  
Suite 200, 240 Michael Cowpland Drive  
Ottawa, Ontario, Canada K2M 1P6

Telephone (613) 254-9643  
Facsimile (613) 254-5867  
Website www.novatech-eng.com

VINCENT MASSEY PUBLIC SCHOOL  
745 SMYTH ROAD

**POST DEVELOPMENT  
DRAINAGE AREA PLAN**

SCALE 1 : 500 

DATE DEC 2022 JOB 122204 FIGURE FIG 5

## **Best Management Practices**

The proposed development will use the following stormwater best management practices (BMPs) to mitigate the reduction in groundwater infiltration/recharge resulting from development:

- Surface drainage will sheet drain through the grassed swale and outlet directly to the proposed CB1 and into the ex. CB along Smyth Road where possible,
- Construction of swales at minimal slopes where possible.

By implementing stormwater management BMPs as part of the storm drainage design, the impacts of development on the hydrologic cycle can be reduced.

## **EROSION AND SEDIMENT CONTROL**

Temporary erosion and sediment control measures will be implemented during construction in accordance with the Best Management Practices for Erosion and Sediment Control. This includes the following temporary measures:

- Silt fences will be placed as per OPSS 577 and OPSD 219.110 along the surrounding construction limits;
- Filter bags will be placed under the grates of nearby existing catchbasins and will remain in place until vegetation has been established and construction is completed.
- Street sweeping, and cleaning will be performed, as required, to suppress dust and to provide safe and clean roadways adjacent to the construction site.

The erosion and sediment control measures are to be installed to the satisfaction of the engineer, and the City of Ottawa prior to construction and will remain in place during construction until vegetation is established. The erosion and sediment control measure will also be subject to regular inspection to ensure measures are operational.



## Conclusions


The conclusions of this brief are as follows:

- Quantity control of stormwater will be provided through surface storage in a grassed swale with the release rate controlled prior to release to the existing storm sewer system along Smyth Road.
- An overland flow route will be provided to Smyth Road.
- Erosion and sediment control measures will be implemented during construction.

This brief is respectfully submitted for review and approval. Please contact the undersigned should you have questions or require additional information.

## NOVATECH

Prepared by:



Micheal Adeoti  
Project Engineer  
Land Development Engineering

Reviewed by:



Cara Ruddle, P.Eng.  
Senior Project Manager  
Land Development Engineering



## Appendix

**Time to Peak Calculations - Existing Conditions**

TABLE 1A: Time of Concentration (Uplands Overland Flow Method)

Area ID	Overland Flow						Channel Flow			Overall	
	Length (m)	Elevation U/S (m)	Elevation D/S (m)	Slope (%)	Velocity (Uplands) (m/s)	Travel Time (min)	Length (m)	Velocity * (m/s)	Travel Time (min)	Time of Concentration (min)	Time to Peak (min)
PRE	103.9	76.13	75.37	0.7%	0.3	6	N/A	N/A	N/A	6	4




Figure A.5.2: Upland Method for Estimating Time of Concentration (SCS National Engineering Handbook, 1971)

**TABLE 2A: Pre-Development Runoff Coefficient "C" - PRE**

Area	Surface	Ha	"C"	C <sub>avg</sub>	*C <sub>100</sub>	Runoff Coefficient Equation
Total	Hard	0.023	0.90	0.25	0.31	C = (A <sub>hard</sub> x 0.9 + A <sub>soft</sub> x 0.2)/A <sub>Tot</sub> * Runoff
0.311	Soft	0.288	0.20			

**TABLE 2B: Pre-Development Flows**

Outlet Options	Area (ha)	C <sub>avg</sub>	Tc (min)	Q <sub>2 Year</sub> (L/s)	Q <sub>5 Year</sub> (L/s)	Q <sub>100 Year</sub> (L/s)
Smyth Road	0.311	0.25	10	16.7	22.7	47.2

Time of Concentration Tc= 10 min  
 Intensity (2 Year Event) I<sub>2</sub>= 76.81 mm/hr  
 Intensity (5 Year Event) I<sub>5</sub>= 104.19 mm/hr  
 Intensity (100 Year Event) I<sub>100</sub>= 178.56 mm/hr

Equations:  
 Flow Equation  
 Q = 2.78 x C x I x A  
 Where:  
 C is the runoff coefficient  
 I is the rainfall intensity, City of Ottawa IDF  
 A is the total drainage area

100 year Intensity = 1735.688 / (Time in min + 6.014)<sup>0.820</sup>  
 5 year Intensity = 998.071 / (Time in min + 6.053)<sup>0.814</sup>  
 2 year Intensity = 732.951 / (Time in min + 6.199)<sup>0.810</sup>

**TABLE 3A: Post-Development Runoff Coefficient "C" - A-4**

Area	Surface	Ha	5 Year Event		100 Year Event	
			"C"	C <sub>avg</sub>	"C" + 25%	*C <sub>avg</sub>
Total	Hard	0.152	0.90	0.54	1.00	0.61
0.317	Roof	0.000	1.00		1.00	
	Soft	0.165	0.20		0.25	

**TABLE 3B: 2 YEAR EVENT QUANTITY STORAGE REQUIREMENT - A-4**

0.317 =Area (ha)  
 0.54 = C

Return Period	Time (min)	Intensity (mm/hr)	Flow Q (L/s)	Allowable Runoff (L/s)	Net Flow to be Stored (L/s)	Storage Req'd (m <sup>3</sup> )
2 YEAR	5	103.57	48.89	10.8	38.09	11.43
	10	76.81	36.26	10.8	25.46	15.27
	<b>15</b>	<b>61.77</b>	<b>29.16</b>	<b>10.8</b>	<b>18.36</b>	<b>16.52</b>
	20	52.03	24.56	10.8	13.76	16.51
	25	45.17	21.32	10.8	10.52	15.78

**TABLE 3C: 5 YEAR EVENT QUANTITY STORAGE REQUIREMENT - A-4**

0.317 =Area (ha)  
 0.54 = C

Return Period	Time (min)	Intensity (mm/hr)	Flow Q (L/s)	Allowable Runoff (L/s)	Net Flow to be Stored (L/s)	Storage Req'd (m <sup>3</sup> )
5 YEAR	10	104.19	49.18	13.3	35.88	21.53
	15	83.56	39.44	13.3	26.14	23.53
	<b>20</b>	<b>70.25</b>	<b>33.16</b>	<b>13.3</b>	<b>19.86</b>	<b>23.83</b>
	25	60.90	28.75	13.3	15.45	23.17
	30	53.93	25.46	13.3	12.16	21.88

**TABLE 3D: 100 YEAR EVENT QUANTITY STORAGE REQUIREMENT - A-4**

0.317 =Area (ha)  
 0.61 = C

Return Period	Time (min)	Intensity (mm/hr)	Flow Q (L/s)	Allowable Runoff (L/s)	Net Flow to be Stored (L/s)	Storage Req'd (m <sup>3</sup> )
100 YEAR	20	119.95	64.44	16.7	47.74	57.29
	25	103.85	55.79	16.7	39.09	58.64
	<b>30</b>	<b>91.87</b>	<b>49.35</b>	<b>16.7</b>	<b>32.65</b>	<b>58.78</b>
	35	82.58	44.36	16.7	27.66	58.09
	40	75.15	40.37	16.7	23.67	56.81

Equations:

Flow Equation

$$Q = 2.78 \times C \times I \times A$$

Where:

C is the runoff coefficient

I is the rainfall intensity, City of Ottawa IDF

A is the total drainage area

Runoff Coefficient Equation

$$C_5 = (A_{\text{hard}} \times 0.9 + A_{\text{soft}} \times 0.2) / A_{\text{Tot}}$$

$$C_{100} = (A_{\text{hard}} \times 1.0 + A_{\text{soft}} \times 0.25) / A_{\text{Tot}}$$

TABLE 3E: Structure information

Structures	Size Dia.(mm)	Area (m <sup>2</sup> )	T/G	Inv IN	Inv OUT
CB 1	600	0.37	75.00	74.10	74.04

TABLE 3F: Pipe / Stone Trench Information

Structures	Width (m)	Depth (m)	Length (m)	Void Ratio	Inv UP	Inv DOWN
Stone Trench	1.5	0.9	50.0	40%	74.20	74.10

TABLE 3G: Storage Provided - A-4

Storage Table				Total Storage		
Elevation (m)	System Depth (m)	CB 1 Volume (m <sup>3</sup> )	Trench Volume (m <sup>3</sup> )	Underground Volume (m <sup>3</sup> )*	Ponding Volume (m <sup>3</sup> )	Total Volume (m <sup>3</sup> )
74.040	0.00	0.00	0.00	0.00	0.00	<b>0.00</b>
74.100	0.06	0.02	0.00	0.02	0.00	<b>0.02</b>
75.000	0.96	0.36	27.00	27.36	0.00	<b>27.36</b>
75.050	-	-	-	27.36	1.07	<b>28.43</b>
75.100	-	-	-	27.36	4.51	<b>31.87</b>
75.150	-	-	-	27.36	9.83	<b>37.19</b>
75.200	-	-	-	27.36	16.24	<b>43.60</b>
75.250	-	-	-	27.36	23.89	<b>51.25</b>
75.300	-	-	-	27.36	32.99	<b>60.35</b>

TABLE 3H: Orifice Sizing information - A-4

Control Device							
Round Plate Orifice				85 mm			
Design Event	Flow (L/S)	Head (m)	Elev (m)	Outlet dia. (mm)	Volume (m <sup>3</sup> )	Area (m <sup>2</sup> )	Dia. (mm)
1:2 Year	10.8	0.47	74.64	250	16.52	0.0057	85.0
1:5 Year	13.3	0.72	74.89	250	23.83	0.0057	85.0
1:100 Year	16.7	1.13	75.29	250	58.78	0.0057	85.0

Orifice Control Sizing

$$Q = 0.62 \times A \times (2gh)^{0.5}$$

Q is the release rate in m<sup>3</sup>/s

A is the orifice area in m<sup>2</sup>


g is the acceleration due to gravity, 9.81 m/s<sup>2</sup>

h is the head of water above the orifice centre in m

d is the diameter of the orifice in m

\*\*The design Head is calculated based on the centre of the outlet pipe

Stage Storage Curve Area A-4



**Table 4: Post-Development Stormwater Mangement Summary**

Area ID	Area (ha)	1:5 Year Weighted Cw	Outlet Location	2 Year Storm Event			5 Year Storm Event			100 Year Storm Event		
				Release (L/s)	Req'd Vol (cu.m)	Max. Vol. Provided (cu.m.)	Release (L/s)	Req'd Vol (cu.m)	Max. Vol. Provided (cu.m.)	Release (L/s)	Req'd Vol (cu.m)	Max. Vol. Provided (cu.m.)
A1	0.317	0.54	Smyth Rd	10.8	16.52	27.36	13.3	23.83	60.65	16.7	58.78	60.65
<b>Total</b>				<b>10.8</b>			<b>13.3</b>			<b>16.7</b>		
<b>Allowable</b>				<b>16.7</b>			<b>16.7</b>			<b>16.7</b>		