



AECOM Canada Ltd.
250 York Street
Suite 410, Citi Plaza
London, ON N6A 6K2
Canada

T: 519.673.0510
F: 519.673.5975
aecom.com

Project name:
AMZL DYT3 Ottawa

Project ref:
60634622

From:
Jack Yu Guo, and Taesang Ahn

Date:
March 24, 2023

To:
Joseph Abela, Arch. Tech
Project Manager

Fady ElMohandes, Ph.D., P.Eng., PMP
Structural Department Manager

CC:
Douglas McLachlin, P.Eng

Technical Memorandum (Rev.3)

Subject: 60634622 Supplementary Geotechnical Investigation at DYT3 Ottawa, Ontario

The DYT3 site (the site) is located at 2625 Sheffield Road in Ottawa, Ontario. A supplementary geotechnical field investigation program was carried out at the site between March 14 and March 15, 2022, under the full-time supervision of AECOM staff. A total of four (4) boreholes, two (2) sampled boreholes and two (2) Dynamic Core Penetration Tests (DCPTs), were advanced near the existing structure, and the borehole locations and logs are provided in **Appendix A**. The laboratory test results are provided in **Appendix B**.

Subsurface Conditions at the Borehole Locations

A granular fill layer was encountered in Boreholes BH-S1/MW and BH-S2/MW beneath the asphalt. The thickness of granular fill ranged from 76 to 180 mm. This granular fill extended to 66.92 to 66.72 metres above sea level (mASL).

A layer of sand fill underlain by a layer of granular fill was encountered in Boreholes BH-S1/MW and BH-S2/MW. The thickness of sand fill ranged from 1.2 to 1.3 m. The sand fill was encountered at the elevations ranged from 66.2 to 66.72 mASL and extended to 65.5 mASL. Standard Penetration Testing (SPT) N blow counts ranged from 10 to over 50 blows per 0.3 m of penetration, indicating a compact to very dense soil.

The native silty clay to clayey silt underlain by the layers of fill was encountered in Boreholes BH-S1/MW and BH-S2/MW. The silty clay was encountered at elevation 62.5 mASL and extended to 58.0 to 56.3 mASL. Standard Penetration Testing (SPT) N values ranged from Weight Hammer (WH) to 10 blows per 0.3 m of penetration, indicating a very soft to stiff cohesive soil. The sand seams were present within the clay layer at about 62.3mASL. According to the field vane tests at 7mbgs, the undisturbed and remolded shear strength was 34.1 kPa and 8.5kP, respectively. The sensitivity ratio was about 4. This clay was medium to very sensitive and significant settlement would be expected under loading conditions. The natural water content for the very soft clay (w=about 53.5%) was higher than the liquid limit (LL=40%), indicating a highly flocculent quick clay, i.e., the clay would liquefy when it is remolded.

The native silty clay till was underlain by a layer of native silty clay in Borehole BH-S1/MW. The silty clay till was encountered at the elevation of 58.0 mASL and it extended to 56.0 mASL. Standard Penetration Testing (SPT) N values were over 50 blows per 0.3 m of penetration, indicating a hard cohesive soil.

Bedrock was encountered in Borehole BH-S2/MW below the native silty clay materials and also in DCPT-1 and DCPT-2. The bedrock surface was encountered at elevations ranging from 57.3 to 56.3 mASL. Bedrock coring was carried out in BH-S2/MW. The bedrock is comprised of Carlsbad formation shale, which is highly weathered and in dark grey in colour with horizontal bedding. The vertical and inclined open joints were infilled with clay as were observed in the core samples. The top 2m of the shale bedrock was highly weathered with an RQD of 0% and a fracture index of about 10.

The groundwater level was observed at a depth of 4.27 mbgs at the time of drilling in the open hole. Monitoring wells were installed in Boreholes BH-S1/MW and BH-S2/MW to allow for long-term groundwater monitoring at these two locations.

Foundation Options and Recommendations

According to the historical foundation design of the building, shallow foundations have been used to support the old building. Therefore, it is feasible to use the spread footings and strip footings as the foundation design option.

Foundations Options

Typically, shallow foundations are not suitable for heavily to moderately loaded structures based on the compressible soils encountered at the site. Loading of the sensitive clay would cause significant post-construction settlement. Since the existing building is supported by shallow foundations, the soil under the existing building footprint has been consolidated. But additional loading due to an increase in building structural load will still generate some settlement. It is recommended to increase the design settlement criteria to 50mm in the Ottawa region where substantial soft soils are existing. The bearing capacities are evaluated with the detailed foundation location plan.

Based on the above considerations, the recommended option from a geotechnical/foundations perspective is to support the proposed building on spread and strip footings with a foundation depth of 1.5mbgs. The lightweight backfill is required to replace the existing and regular backfill above the footing to minimize the long-term consolidation settlement for the footings with a foundation depth of 2.7mbgs.. Otherwise, deep foundations shall be used with pile caps at 2.7mbgs.

Foundation Design Capacities

Shallow foundations

The bearing capacity at the ultimate limit state (ULS) is estimated based on the two-layer method proposed by Meyerhof and Hanna (1978) and Meyerhof (1974). The bearing capacity at the service limit state (SLS) is estimated via numerical software Settle 3 by Rocscience inc. The footings should be placed at a minimum of 1.5 m below the ground surface.

The soil layers considered in the analysis were divided into five(5) sublayers, as seen in **Table 1**. The consolidation test results are shown in **Appendix B**. The settlement analysis via Settle 3D is shown in **Appendix C**.

Table 1 Soil layers for bearing capacity analysis

| Soil Layer | Thickness (m) | Compactness /Consistency | Unit Weight (kN/m ³) | S _u (kPa) | Φ (°) | E (MPa) | Consolidation Settlement Parameter | | | | | |
|--------------------------------|---------------|--------------------------|----------------------------------|----------------------|-------|---------|------------------------------------|----------------|-----|----------------------|----------------|-------------------------------------|
| | | | | | | | C _c | C _r | OCR | P _c (kPa) | e ₀ | C _v (cm ² /s) |
| Fill | 1.5 | Dense to very dense | 21 | - | 35 | 52.5 | - | - | - | - | - | - |
| Top silty clay with sand | 1.5 | Stiff to firm | 20 | - | - | 40.0 | - | - | - | - | - | - |
| Silty Clay | 3 | Very soft | 20 | 35* | - | - | 0.339 | 0.033 | 1 | - | 1.4 | 7.45E-4 |
| Silty Clay Bottom | 1 | Firm to Stiff | 20 | - | - | - | 0.339 | 0.033 | - | 110 | 0.55 | 7.45E-4 |
| Silty Clay/Clayey Silt Till | 2 | Very stiff to hard | 20 | - | - | 40.0 | - | - | - | - | - | - |
| Engineered Fill | - | 100% SPMDD | 21 | - | 36 | 62.5 | - | - | - | - | - | - |
| *Weighted average value | | | | | | | | | | | | |

Based on the subsurface soil conditions described in Table 1, the bearing capacity in terms of the ULS and SLS estimated for the different sizes of spread footing is shown in Table 2. It should be noted that the footing is generally ULS controlled because

the founding soil layer is stiff to firm silty clay underlain by very soft silty clay. The ULS could be increased by subexcavating the clay and replaced with compacted engineered fill such as OPSS Granular A. At least 0.3 m thick Granular A pad compacted at SPMDD of 100% will improve the geotechnical resistance at ULS. Geogrid (e.g., Terrafix TBX2000) between native clayey soil and granular pad will provide a better load distribution resulting in the improvement of the bearing capacity as well. It should be noted that a smaller capacity (either ULS or SLS) should be used for the foundation design.

Table 2 ULS and SLS for Shallow Foundation Option

| Footing size | Factored Geotechnical Resistance at ULS (kPa) | Factored Geotechnical Resistance at ULS with 0.3 m of Granular A Pad (kPa) | Geotechnical Reaction at SLS* (kPa) |
|--------------------------------|---|--|-------------------------------------|
| Strip footing 1.5m wide | 110 | 115 | 90 |
| 2m x 2m | 130 | 140 | 200 |
| 3m x 3m | 120 | 130 | 150 |
| 4m x 4m | 110 | 120 | 100 |
| 4m x 4m** | 120 | 130 | 100** |
| 5m x 5m | 110 | 120 | 100 (General) /140 (only interior) |
| 6m x 6m** | 120 | 130 | 80** |

Note: * The SLS is calculated based on the settlement of 50mm at 15-year design life.
 ** - 2.7 m embedded depth and backfill with lightweight fill. Otherwise 1.5 m embedded depth for footing and backfill with Graular B.

Driven Steel H-Piles

Steel H-piles (HP 310 x 110) can be used to support the structure. The piles will be installed through the native silty clay to clayey silt and are expected to drive into weathered bedrock. The termination elevation is anticipated at 56mASL. The pile cap elevation should be below the frost line of 1.5m below the ground surface. The in-situ load test with Pile Driving Analyzer (PDA) is needed to determine the actual capacity of the H-Pile. The factored geotechnical resistances for H-piles are shown in Table 3.

Table 3 ULS and SLS for Driven H-Pile (HP 310x110)

| Pile Foundation Stratum | Estimated Tip Elevation | Approx. Design Length | Factored Geotechnical Axial Resistance at ULS (kN/Pile) | Geotechnical Axial Resistance at SLS (kN/Pile) |
|----------------------------|-------------------------|-----------------------|---|--|
| Bedrock (fractured) | 52mASL | 12 m | 600* | >ULS capacity |

Note: * The ULS capacity should be determined via field pile load test

Drilled Concrete Caissons

To provide sufficient geotechnical resistance, the caissons should be socketed at least 2.5m into the bedrock. Temporary steel liners should be advanced to address the shallow groundwater levels and prevent caving within the wet granular soils. The following table summarizes the recommended factored geotechnical resistance at ULS and the geotechnical reaction at SLS for the caisson diameters and bearing elevation for limit states design.

Table 4 ULS and SLS for Caissons

| Pile Foundation Stratum | Estimated Tip Elevation (mASL) | Approx. Design Length (m) | Socket Length (m) | Factored Geotechnical Axial Resistance at ULS (kN/Pile) | | Geotechnical Axial Resistance at SLS (kN/Pile) | |
|-------------------------|--------------------------------|---------------------------|-------------------|---|-----------|--|-----------|
| | | | | 0.9m dia. | 1.2m dia. | 0.9m dia. | 1.2m dia. |
| Bedrock | 53.83 | 13.17 | 2.5 | 1100 kN | 1500 kN | >ULS Capacity | |

Resistance of Piles to Lateral Loads

The resistance to lateral loading is derived from the soil in front of the piles for vertical piles. That resistance may be estimated using Subgrade Reaction Theory (with deformations less than 5% of pile diameter), in which the coefficient of horizontal subgrade reactions K_S is based on the following equations:

In cohesionless soil:

$$K_S = n_h(z/d)$$

Where:

K_S = coefficient of horizontal subgrade reaction (MPa/m)

n_h = constant of horizontal subgrade reaction (MPa/m)

d = pile diameter (m)

z = depth below ground surface (m)

In cohesive soil:

$$K_S = 67C_u/d$$

Where:

K_S = coefficient of horizontal subgrade reaction (MPa/m)

C_u = undrained shear strength of the soil (MPa)

d = pile diameter (m)

According to the vane test results, the undrained shear strength of the native silty clay is 34.1 kPa and 8.5kPa for undisturbed and remold strength, respectively, at this site. For the lateral resistance calculation, it is recommended that 5 kPa within the native silty clay should be used, considering the disturbance and sensitivity of the clay soil.

Lateral loading could be resisted fully or partially by use of battered piles. The piles could be installed at a better of up to 4 vertical to 1 horizontal.

Group action for lateral loading should be considered where the pile spacing in the direction of the loading is less than eight pile diameters. Group action can be evaluated by reducing the coefficient of lateral subgrade reaction in the direction of loading by a reduction fact R, as indicated in Table 5. Subgrade reaction reduction factors for other pile spacing values may be interpolated for pile spacing in between those listed in this table.

Table 5 – Lateral Load Capacity Reduction Factor for Pile Group

| Pile Spacing in Direction of Loading D = Pile Diameter/Width | Subgrade Reaction Reduction Factor R |
|--|--------------------------------------|
| 8d | 1 |
| 6d | 0.7 |
| 4d | 0.4 |
| 3d | 0.25 |

Negative Skin Friction (Downdrag Loads) on Piles

The negative skin friction within the native clay soil that are subject to settlement should be considered with the final civil/structural design. The amount of negative skin friction as well as depth to the neutral plane should be refined during the detailed design stage and based on the actual fill height, design pile length for each specific area.

Lightweight Fill

For the footings at the depth of 2.7mbgs, the Geospec® lightweight fill EPS 22 block or equivalent shall be used as backfill materials to reduce the overall stress on the underlain compressible clay layer. The minimum replacement shall be 2.1m EPS22 lightweight fill and 0.4m granular fill/pavement structure on top of EPS 22 block. The lightweight fill shall be placed above the founding elevation and extend 0.5×B (foundation width) in all directions from the footing edge.

Subgrade modulus

The vertical modulus of subgrade reaction ($K_{0.3}$) on the engineered fill of 30 MPa/m to 50 MPa/m (for square plate 30 x 30 cm or 30 cm wide strip resting on pre-compressed layers) may be used for the design. It should be noted that reduction of $K_{0.3}$ due to shape and size of foundations (i.e., K_s) should be considered.

Table 6 Subgrade Reaction Modulus

| Size of slab | Ks | | |
|----------------|--------------------------|--------------------------|-------------------------|
| | Min. $K_{0.3}= 30$ Mpa/m | Max. $K_{0.3}= 50$ Mpa/m | Mean $K_{0.3}=40$ MPa/m |
| 2m x 2m | 10.0 | 16.5 | 13.2 |
| 3m x 3m | 9.1 | 15.1 | 12.1 |
| 4m x 4m | 8.7 | 13.4 | 11.6 |
| 5m x 5m | 8.4 | 14.0 | 11.2 |

Seismic Site Classification

Table 7 summarizes the site classification based on the soil properties in the top 20 m of the subsurface. Considering the undrained shear strength and SPT values of the very soft to stiff silty clay to clayey silt encountered, a seismic site classification of the building and proposed canopy area is **Site Class E**.

Table 7 Site Classification for Seismic Site Response (CFEM 2006)

| Site Class | Ground Profile Name | Shear Wave Velocity \bar{V}_s (m/s) | Standard Penetration Resistance \bar{N}_{60} | Soil Undrained Shear Strength s_u (kPa) |
|------------|-------------------------------|--|--|---|
| A | Hard Rock | $\bar{V}_s > 1500$ | Not Applicable | Not Applicable |
| B | Rock | $760 < \bar{V}_s \leq 1500$ | Not Applicable | Not Applicable |
| C | Very Dense Soil and Soft Rock | $360 < \bar{V}_s \leq 760$ | $\bar{N}_{60} > 50$ | $s_u > 100$ |
| D | Stiff Soil | $180 < \bar{V}_s \leq 360$ | $15 \leq \bar{N}_{60} \leq 50$ | $50 < s_u \leq 100$ |
| E | Soft Soil | $\bar{V}_s \leq 180$ | $\bar{N}_{60} < 15$ | $s_u < 50$ |
| | | Any profile with more than 3m of soil with the following characteristics: <ul style="list-style-type: none"> • Plasticity Index $PI > 20$; • Moisture Content $w \geq 40\%$; and • Undrained Shear Strength $s_u < 25$ kPa | | |
| F | Other Soil | Site Specific Evaluation Required | | |

Spectral accelerations and PGA values given in Table 8 should be adjusted using Tables 4.2 to 4.9 in CHBDC S6-14. The design PGA and $S_a(T)$, should be selected based on project-specific requirements as described in the minimum performance level in CHBDC S6-14. Seismic earth pressures acting on the structure may be estimated using Mononobe-Okabe or Wood methods depending on the rigidity or tolerable movement of the structures.

Table 8 Spectral Acceleration S_a (T) and PGA (CHBDC S6-14)

| 2%/50 years (0.000404 per annum) probability | | | | |
|--|--------------|--------------|--------------|----------------|
| Sa(0.2) | Sa(0.5) | Sa(1.0) | Sa(2.0) | PGA |
| 0.465 | 0.248 | 0.122 | 0.058 | 0.297 g |
| 5%/50 years (0.001 per annum) | | | | |

| | | | | |
|---------------------------------------|---------|---------|---------|---------|
| Sa(0.2) | Sa(0.5) | Sa(1.0) | Sa(2.0) | PGA |
| 0.269 | 0.144 | 0.072 | 0.033 | 0.172 g |
| 10%/50 years (0.001 per annum) | | | | |
| Sa(0.2) | Sa(0.5) | Sa(1.0) | Sa(2.0) | PGA |
| 0.169 | 0.091 | 0.045 | 0.021 | 0.107 g |
| 40%/50 years (0.001 per annum) | | | | |
| Sa(0.2) | Sa(0.5) | Sa(1.0) | Sa(2.0) | PGA |
| 0.057 | 0.032 | 0.015 | 0.006 | 0.034 g |

Liquefaction Consideration

To delineate liquefaction susceptibility, this memo has adopted the empirical criteria recommended in the Canadian Foundation Engineering Manual:

- $w/w_L \geq 0.85$ and $I_P \leq 12$: Susceptible to liquefaction or cyclic mobility;
- $w/w_L \geq 0.80$ and $10 \leq I_P \leq 12$: Moderately susceptible to liquefaction;
- $w/w_L < 0.85$ and $I_P \geq 12$: No liquefaction or cyclic mobility.

Where w is the in-situ soil water content, w_L is the liquid limit of the soil and I_P is the plasticity index of the soil.

The clay present on site is susceptible to liquefaction as the natural water content is higher than its liquid limit.

Minimum Insulation Calculation

A design methodology for insulated foundations has been presented by Robinsky and Bespflug (1973). Summaries of their design charts for heated and unheated structures are shown in Figure 1 and Figure 2, respectively (CFEM, 2006).




Figure 1 Design curves for minimum insulation requirements for heated structures (adapted from Robinsky and Bespflug, 1973)




Figure 2 Design curves for minimum insulation requirements for unheated structures (adapted from Robinsky and Bessflug, 1973)

Design freezing Index of Ottawa is around 1100°C Day. As the footings will be founded on granular materials and all the backfill materials are granular materials, the sandy soil conditions are adopted while using the figures. When the building temperature of 18°C is to be maintained, Insulation should be placed with minimum soil covers of 300 mm and extend at least 1.22 m from the edge of the building. For the heated structures, the minimum installation thickness is about 20 mm according to **Figure 1**. As the perimeter of the building should be considered as unheated structures, the minimum insulation thickness is about 60 mm according to **Figure 2**.

Closure

We trust that this meets your expectations. If you have any questions or need clarification, please do not hesitate to contact the undersigned.

AECOM Canada Ltd.

Yu Guo, Ph.D., P.Eng.
 Senior Geotechnical Engineer

Taesang Ahn, Ph.D., P.Eng.
 Senior Geotechnical Engineer

Encl.

Appendix A Borehole Location and Borehole Logs



LEGEND

- Geotechnical Borehole - 20 m Depth
- DCPT - 20 m Depth
- Geotechnical Borehole - AECOM, 2020 Investigation

NOTES:

This drawing has been prepared for the use of AECOM's client and may not be used, reproduced or relied upon by third parties, except as agreed by AECOM and its client, as required by law or for use by governmental reviewing agencies. AECOM accepts no responsibility, and denies any party that modifies this drawing without AECOM's express written consent.

REFERENCE DRAWINGS

| NO. | DATE | DESCRIPTION |
|-----|------|-------------|
| | | |

REVISIONS

| REV. | DATE | DESCRIPTION | BY | CHK |
|------|------------|-------------|----|-----|
| 0 | 2022.03.03 | BH Plan | JH | TA |

| | |
|---|--|
| CLIENT NAME: AMAZON LOGISTICS | PROJECT LOCATION: 2625 Sheffield Rd, Ottawa ON |
| PROJECT NUMBER: 60634622 | |

PROPOSED BOREHOLE LOCATION PLAN

| | | |
|--------------|----------------|---------------|
| DRAWN BY: JH | SCALE: 1:1500 | DRAWING No. 1 |
| CHECKED: TA | DATE: MAR 2022 | REVISION 0 |

TERMINOLOGY USED IN BOREHOLE LOGS

Topsoil: Mixture of soil and humus capable of supporting good vegetative growth.

Peat: A mass of organic matter usually fibrous in texture in various stages of decomposition, generally dark brown to black in colour and of spongy consistency.

Fill: The term fill has been used to describe materials which have been placed by non-natural processes. Fills can often be heterogeneous in nature and those relying on this report should expect them to contain deleterious materials. Such materials can include wood, bricks, slag, porcelain, organics, and obstructions such as scrap metal, storage tanks, and abandoned concrete/steel structures.

Due to the uncertainty of the placement method of the material, the boring samples obtained for this report are not expected to represent other materials at any horizontal or vertical distance from where the sample was obtained.

Fill material may be contaminated by toxic/hazardous waste that renders it unacceptable for deposition in any but designated land fill site. Unless specifically stated, the fill on this site has not been tested for contaminants that can be considered toxic or hazardous. Testing to determine the toxicity of fill materials can be conducted, if requested.

Till: The term till on the borehole logs indicates that the material originates from a geological process associated with glaciation. Till must be considered heterogeneous in composition and containing pockets and/or seams of material such as sand, gravel, silt or clay. Till often contains cobbles (60 to 200 mm) and boulders (over 200 mm). Contractors may therefore encounter cobbles and boulders during excavation, even if they are not indicated by the logs. It should be appreciated that normal sampling equipment cannot differentiate the size or type of any obstruction. Due to the horizontal and vertical variability of till, the sample description may be applicable to a very limited zone. Caution is essential when dealing with sensitive excavations or dewatering programs in till materials.

Terminology describing soil structure

Desiccated: having visible signs of weathering by oxidization of clay minerals, shrinkage cracks, etc.

Stratified: alternating layers of varying material or color with the layers greater than 6 mm thick.

Laminated: alternating layers of varying material or color with the layers less than 6 mm thick.

Fissured: material breaks along plane of fracture.

Varved: composed of regular alternating layers of silt and clay.

Slickensided: fracture planes appear polished or glossy, sometimes striated.

Blocky: cohesive soil that can be broken down into small angular lumps which resist further breakdown.

Lensed: inclusion of small pockets of different soil, such as small lenses of sand scattered through a mass of clay; not thickness.

Seam: a thin, confined layer of soil having different particle size, texture, or color from materials above and below.

Homogeneous: same color and appearance throughout.


Well Graded: having wide range in grain sized and substantial amounts of all predominantly on grain size.

Uniformly Graded: predominantly on grain size.

Residual: completed weathered sedimentary rock mixed with native soils.

All soil sample descriptions included in this report generally follow the Canadian Foundations Engineering Manual and the Unified Soil Classification System. These systems follow the standard proposed by the International Society for Soil Mechanics and Foundation Engineering. Laboratory grain size analyses provided by AECOM follow the same system. Note that, with exception of those samples where a grain size distribution analysis has been completed, all samples have been classified by visual inspection. Visual inspection classification is not sufficient to provide exact grain sizing.

ISSMFE / USCS SOIL CLASSIFICATION



The standard terminology to describe cohesive soils includes consistency, which is based on undrained shear strength as measured by in-situ vane tests, penetrometer tests, unconfined compression tests or similar field and laboratory analysis. Standard Penetration Test 'N' values can also be used to provide an approximate indication of the consistency and shear strength of fine grained, cohesive soils.

The standard terminology to describe cohesionless soils includes the compactness condition as determined by the Standard Penetration Test 'N' value.

| Cohesionless Soils | | Cohesive Soils | | | Composition | |
|-----------------------|-------------------------------|----------------|--------------------------------|-------------------------------|-------------|--------------------------|
| Compactness Condition | SPT N-Index (blows per 0.3 m) | Consistency | Undrained Shear Strength (kPa) | SPT N-Index (blows per 0.3 m) | Term | Criteria |
| Very loose | 0 – 4 | Very soft | < 12 | < 2 | Trace | 1% - 10% |
| Loose | 4 – 10 | Soft | 12 - 25 | 2 – 4 | Some | 10% - 20% |
| Compact | 10 – 30 | Firm | 25 – 50 | 4 – 8 | Adjective | 20% - 35% |
| Dense | 30 – 50 | Stiff | 50 – 100 | 8 – 15 | And | > 35% |
| Very Dense | > 50 | Very Stiff | 100 - 200 | 15 – 30 | Noun | > 35% & largest fraction |
| | | Hard | > 200 | > 30 | | |

Standard Penetration Test (SPT):

The number of blows required to drive a 50 mm (2 in.) open split spoon sampler from a depth of 150 mm (6 in.) to 450 mm (18 in.) in undisturbed soil. Each blow is driven by a 63.6 kg (140 lb.) hammer free falling a distance of 0.76 m (30 in.).

| Sample & Soil Abbreviations | | Contaminant Abbreviations | | Strata/Graphic Plot | | | | | |
|-----------------------------|-------------------------------|---|---|---------------------|-------------|--|---------------|--|------------------|
| CORE | Rock core sample | BNAE | base/neutral/acid extractables | | Fill | | Asphalt | | Cobbles |
| AS | Auger sample | BTEX | benzene, toluene, ethylbenzene, xylenes | | Topsoil | | Concrete | | Sandy Silt Till |
| FV | Field vane | OCP | organochlorine pesticides | | Clay | | Silty Clay | | Silty Clay Till |
| PP | Pocket penetrometer | MI | metals & inorganics | | Silt | | Clayey Silt | | Clayey Silt Till |
| SG | Specific Gravity | PAH | polycyclic aromatic hydrocarbons | | Sand | | Silty Sand | | Silty Gravel |
| GS | Grab sample | PCB | polychlorinated biphenyls | | Gravel | | Sand & Gravel | | Clayey Gravel |
| SS | Split spoon sample | PHC | CCME petroleum hydrocarbons (fractions 1 – 4) | | Clayey Sand | | Shale | | Limestone |
| DCPT | Dynamic cone penetration test | VOC | volatile organic compounds (includes BTEX) | | | | | | |
| GR | Gravel | Plasticity Description Liquid Limit (w_l) | | | | | | | |
| SA | Sand | Low | w _l < 30 | | | | | | |
| SI | Silt | Medium | 30 < w _l < 50 | | | | | | |
| CL | Clay | High | 50 < w _l | | | | | | |

Explanatory Sheet To Rock Core Log

| Column No. | Description | |
|-------------------|--|--|
| 1. | Elevation and Depth of Geotechnical Boundary in Borehole | |
| 2. | Drilling Method Used | |
| 3. | General Description of Geotechnical Unit: Quantitative description including rock type (s), percentage of rock types, frequency and sizes of interbeds, colour, texture, weathering, strength and general joint spacing | |
| | Hardness | |
| | H1 | Extremely Hard Cannot be scratched with a pocket knife or sharp pick. Can only be chipped with repeated heavy hammer blows |
| | H2 | Very Hard Cannot be scratched with a pocket knife or sharp pick. Breaks with repeated heavy hammer blows |
| | H3 | Hard Can be scratched with a pocket knife or sharp pick with difficulty (heavy pressure) Breaks with heavy hammer blows |
| | H4 | Moderately Hard Can be scratched with a pocket knife or sharp pick with light or moderate pressure. Breaks with moderate hammer blows |
| | H5 | Moderately Soft Can be grooved 1.6 mm (1/16 in) with a pocket knife or sharp pick |
| | H6 | Soft Can be grooved or gouged easily with a pocket knife or sharp pick with slight pressure, can be scratch with a finger nail. Breaks with light or moderate manual pressure |
| | H7 | Very Soft Can readily be indented, grooved or gouged with a finger nail, or Carved with pocket knife. Breaks with light manual pressure |
| | Strength (from ISRM) Approx UCS | |
| | Svh | Very High Strength >200 MPa |
| | Sh | High Strength 50 to 200 MPa |
| | Sm | Medium Strength 15 to 50 MPa |
| | Sl | Low Strength 4 to 15 MPa |
| | Svl | Very Low Strength 1 to 4 MPa |
| 4 | Geological Symbol for Rock or Soil Material | |
| 5. | Elevation of Geotechnical Boundary | |
| 6. | Run Number: Drill run number | |
| 7. | Penetration Rate: meters per min | |
| 8. | Colour & Return Percentage: | |
| 9. | Core Recovery: Core recovery is the total length of core pieces, irrespective of their individual lengths, obtained in a core run and expressed as a percentage of the length of that core run. | |
| 10. | Rock Quality Designation (RQD): The total length of those pieces of sound core which are 10 cm (4 inches) or greater in length in a core run expressed as a percentage of the total length of that core run. Sound pieces of rock are those pieces separated by natural breaks and not machine breaks or subsequent artificial breaks. | |
| | 0 - 25 percent | Very Poor Quality |
| | 25 - 40 percent | Poor Quality |
| | 40 - 75 percent | Fair Quality |
| | 75 - 90 percent | Good Quality |
| | 90 - 100 percent | Very Good Quality |
| 11. | Fracturing: | |
| | Fu | Unfractured No Fractures |
| | Fvs | Very Slightly Fractured Core length greater than 0.9 m (3 ft) |
| | Fsl | Slightly Fractured Core length from 0.3 to 0.9 m (1 to 3 ft) |
| | Fm | Moderately Fractured Core length from 0.1 to 0.3 m (4 in. to 1 ft) |
| | Fi | Intensely Fractured Core lengths from 0.25 to 0.1 m (1 in. to 4 in.) |
| | Fvi | Very Intensely Fractured Mostly chips and fragments |
| 12. | Dip of discontinuity measured from the axis of rock core. | |

13.

Discontinuity Description

Fracture Width (FW)

| | | |
|------|-----------------|---|
| FWt | Tight | No visible separation |
| FWs | Slightly Open | FW < 0.8 mm (1/32 in.) |
| FWm | Moderately Open | 0.8 mm (1/32 in.) ≤ FW < 3.2 mm (1/8 in.) |
| FWo | Open | 3.2 mm (1/8 in.) ≤ FW < 9.7 mm (3/8 in.) |
| FWmw | Moderately Wide | 9.7 mm (3/8 in.) ≤ FW < 25.4 mm (1 in.) |
| FWw | Wide | FW ≥ 25.4 mm (1 in.) |

Fracture Filling or Coating Thickness (FF)

| | | |
|------|------------------|---|
| FFc | Clean | No film coating |
| FFvt | Very Thin | FF < 0.8 mm (1/32 in.) |
| FFm | Moderately Thin | 0.8 mm (1/32 in.) ≤ FF < 3.2 mm (1/8 in.) |
| FFt | Thin | 3.2 mm (1/8 in.) ≤ FF < 9.7 mm (3/8 in.) |
| FFmt | Moderately Thick | 9.7 mm (3/8 in.) ≤ FF < 25.4 mm (1 in.) |
| FFw | Thick | FF ≥ 25.4 mm (1 in.) |

Roughness

| | | |
|-----|------------------|--|
| Rst | Stepped | Near normal steps and ridges occur on the fracture surface |
| Rr | Rough | Large angular asperities can be seen |
| Rm | Moderately Rough | Asperities are cleanly visible and fracture surface feels abrasive |
| Rs | Slightly Rough | Small asperities on the fracture surface are visible and can be felt |
| Rsm | Smooth | No asperities, smooth to the touch |

Bedding Spacing (Sb)

| | | |
|-----|---------------------|-------------------------------------|
| Bm | Massive | ≤ Sb > 3 m (10 ft) |
| Bvt | Very Thickly Bedded | 0.9 m (3 ft) ≤ Sb ≤ 3 m (10 ft) |
| Bt | Thickly Bedded | 0.3 m (1 ft) ≤ Sb ≤ 0.9 m (3 ft) |
| Bm | Moderately Bedded | 0.1 m (4 in.) ≤ Sb ≤ 0.3 m (1 ft) |
| Bt | Thinly Bedded | 25 mm (1 in.) ≤ Sb ≤ 0.1 m (4 in.) |
| Bvt | Very Thinly Bedded | 6 mm (1/4 in.) ≤ Sb ≤ 25 mm (1 in.) |
| Bl | Laminated | Sb ≤ 6 mm (1/4 in.) |

Orientation

| | | |
|----|----------|------------|
| Of | Flat | = 0 - 20° |
| Od | Dipping | = 20 - 50° |
| Ov | Vertical | = 50 - 90° |

Surface Shape

| | |
|--------|--------------------|
| Planar | Flat surface |
| Wavy | Undulating surface |

Fracture Type:

| | |
|---|-------------------|
| B | Bedding |
| J | Fault |
| C | Joint |
| F | Foliation |
| S | Shear Plane |
| M | Mechanical Breaks |

14.

Hydraulic Conductivity (cm/sec)

15.

Point Load Index:

| | |
|------------------|--------|
| Extremely Strong | > 10 |
| Very Strong | 4 - 10 |
| Strong | 2 - 4 |
| Medium Strong | 1 - 2 |

PROJECT: DYT3 - Ottawa
 LOCATION: 2625 Sheffield Rd
 COORDINATES: N 5028171.5; E 452674.6
 DATUM: Geodetic
 AECOM PROJECT #: 60634622
 CLIENT: Amazon Logistics

RECORD OF BOREHOLE: BH-S1/MW

SHEET 1 OF 2

START DATE: Mar 14, 2022
 END DATE: Mar 15, 2022
 BORING METHOD: 200 mm O.D. Hollow Stem Auger
 CONTRACTOR: Canadian Environmental Drilling
 PENETRATION TEST HAMMER, 64kg; DROP, 760mm
 SAMPLER HAMMER, 64kg; DROP, 760mm

| DEPTH SCALE (METRES) | BORING METHOD | SOIL PROFILE | | SAMPLES | | | Dynamic Cone Penetration Testing (blows/0.3m) | | | | SHEAR STRENGTH Cu, kPa | | | | ADDITIONAL LAB. TESTING & GRAIN SIZE DISTRIBUTION (%) | WELL INSTALLATION AND WATER LEVELS | | |
|----------------------|---|---|-------------|-----------------|--------|---------|---|----|----|----|------------------------|----|----|----|---|------------------------------------|----|------|
| | | DESCRIPTION | STRATA PLOT | ELEV. DEPTH (m) | NUMBER | TYPE | N VALUE | 20 | 40 | 60 | 80 | 20 | 40 | 60 | | | 80 | |
| 0 | Power Auger Drilling 200 mm O.D. Hollow Stem Auger | PAVEMENT | | 67.00 | | | | | | | | | | | | | | |
| | | ASPHALT: 100 mm thick | | 0.00 | | | | | | | | | | | | | | |
| | | FILL: sand and gravel, 76 mm thick, some rock pieces, brown, moist, very dense | | 0.10 | 1 | SS | 50/150mm | | | | | | | | | | | |
| | | FILL: sand, occasional cobbles, trace gravel, brown, moist, very dense | | 0.20 | | | | | | | | | | | | | | |
| 1 | | | | | 2 | SS | 50/150mm | | | | | | | | | 18 | 57 | (25) |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| 2 | | SILTY CLAY: trace gravel, some sand, brown to grey, moist to wet, stiff to firm | 65.50 | 3 | SS | 8 | | | | | | | | | | | | |
| | | firm | 1.50 | 4 | SS | 5 | | | | | | | | 2 | 39 | 59 | | |
| 3 | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| 4 | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| 5 | | Sand Seam | | 1 | TW | | | | | | | | | | | | | |
| | | | | 1 | TW | | | | | | | | | | | | | |
| 6 | | | | 6 | SS | 5 | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| 7 | | | | 7 | SS | 5 | | | | | | | | 7 | 46 | 33 14 | | |
| | | | | | | | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| 9 | | SILTY CLAY TILL: trace gravel, some sand, grey, wet, hard | 58.00 | 8 | SS | 50/76mm | | | | | | | | | | | | |
| | | | 9.00 | | | | | | | | | | | | | | | |
| 10 | | | | | | | | | | | | | | | | | | |

(LOG TO BE READ IN CONJUNCTION WITH REPORT)

DEPTH SCALE

1 : 50



LOGGED: BK

CHECKED: TA

AECOM_BH_001_60634622 - DYT3 OTTAWA 2022_04_12.GPJ GAL-MISS.GDT 22-10-11

PROJECT: DYT3 - Ottawa
 LOCATION: 2625 Sheffield Rd
 COORDINATES: N 5028171.5; E 452674.6
 DATUM: Geodetic
 AECOM PROJECT #: 60634622
 CLIENT: Amazon Logistics

RECORD OF BOREHOLE: BH-S1/MW

SHEET 2 OF 2

START DATE: Mar 14, 2022
 END DATE: Mar 15, 2022
 BORING METHOD: 200 mm O.D. Hollow Stem Auger
 CONTRACTOR: Canadian Environmental Drilling
 PENETRATION TEST HAMMER, 64kg; DROP, 760mm
 SAMPLER HAMMER, 64kg; DROP, 760mm

| DEPTH SCALE (METRES) | BORING METHOD | SOIL PROFILE | | SAMPLES | | | Dynamic Cone Penetration Testing (blows/0.3m) | | | | SHEAR STRENGTH Cu, kPa | | | | ADDITIONAL LAB. TESTING & GRAIN SIZE DISTRIBUTION (%) | WELL INSTALLATION AND WATER LEVELS | |
|----------------------|----------------------|--|-------------|-----------------|--------|------|---|----|----|----|------------------------|----|----|----|---|------------------------------------|----|
| | | DESCRIPTION | STRATA PLOT | ELEV. DEPTH (m) | NUMBER | TYPE | N VALUE | 20 | 40 | 60 | 80 | 20 | 40 | 60 | | | 80 |
| | | CONTINUED FROM PREVIOUS PAGE | | | | | | | | | | | | | | GR SA SI CL | |
| 10 | Power Auger Drilling | SILTY CLAY TILL: trace gravel, some sand, grey, wet, hard | | | | | | | | | | | | | | | |
| 11 | | | | 56.03 | 9 | SS | 50/76mm | | | | | | | | | | |
| 11 | | AUGER REFUSAL END OF BOREHOLE Notes: 1. This log is to be read with the subject report and project number as presented above. 2. Interpretation assistance by AECOM is required for projects excluding the above mentioned project. 3. No abnormal odour or staining was observed unless otherwise indicated. 4. The groundwater was observed at the depth of 4.27 mbgs in the open hole. 5. The monitoring well was installed upon the completion of drilling. | | 10.97 | | | | | | | | | | | | | |
| 12 | | | | | | | | | | | | | | | | | |
| 13 | | | | | | | | | | | | | | | | | |
| 14 | | | | | | | | | | | | | | | | | |
| 15 | | | | | | | | | | | | | | | | | |
| 16 | | | | | | | | | | | | | | | | | |
| 17 | | | | | | | | | | | | | | | | | |
| 18 | | | | | | | | | | | | | | | | | |
| 19 | | | | | | | | | | | | | | | | | |
| 20 | | | | | | | | | | | | | | | | | |

(LOG TO BE READ IN CONJUNCTION WITH REPORT)

DEPTH SCALE

1 : 50



LOGGED: BK

CHECKED: TA

AECOM_BH_001_60634622 - DYT3 OITAWA 2022_04_12.GPJ GAL-MISS.GDT 22-10-11

PROJECT: DYT3 - Ottawa
 LOCATION: 2625 Sheffield Rd
 COORDINATES: N 5027916.8; E 452712.8
 DATUM: Geodetic
 AECOM PROJECT #: 60634622
 CLIENT: Amazon Logistics

RECORD OF BOREHOLE: BH-S2/MW

SHEET 1 OF 3

START DATE: Mar 15, 2022
 END DATE: Mar 15, 2022
 BORING METHOD: 200 mm O.D. Hollow Stem Auger
 CONTRACTOR: Canadian Environmental Drilling
 PENETRATION TEST HAMMER, 64kg; DROP, 760mm
 SAMPLER HAMMER, 64kg; DROP, 760mm

| DEPTH SCALE (METRES) | BORING METHOD | SOIL PROFILE | | SAMPLES | | | Dynamic Cone Penetration Testing (blows/0.3m) | | | | SHEAR STRENGTH Cu, kPa | | | | ADDITIONAL LAB. TESTING & GRAIN SIZE DISTRIBUTION (%) | WELL INSTALLATION AND WATER LEVELS | | |
|----------------------|---|--|-------------|-----------------|--------|------|---|-----------------|--|--|------------------------|-------------|--|--|---|------------------------------------|--|--|
| | | DESCRIPTION | STRATA PLOT | ELEV. DEPTH (m) | NUMBER | TYPE | N VALUE | 20 40 60 80 | | | | 20 40 60 80 | | | | | | |
| | | | | | | | | 100 200 300 400 | | | | 10 20 30 40 | | | | | | |
| 0 | Power Auger Drilling 200 mm O.D. Hollow Stem Auger | PAVEMENT | | 67.00 | | | | | | | | | | | | | | |
| | | ASPHALT: 100 mm thick | | 0.00 | | | | | | | | | | | | | | |
| | | FILL: sand and gravel, 180 mm thick, some rock pieces, brown, moist, compact | | 0.10 | 1 | SS | 11 | | | | | | | | | | | |
| | | FILL: sand, trace gravel, brown, moist, compact | | 0.28 | | | | | | | | | | | | | | |
| 1 | | | | | 2 | SS | 10 | | | | | | | | | | | |
| | | | | | 65.50 | | | | | | | | | | | | | |
| | | SILTY CLAY: trace gravel, some sand, brown to grey, moist to wet, very soft to stiff | | 1.50 | 3 | SS | 5 | | | | | | | | | | | |
| 2 | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| 3 | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| 4 | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| 5 | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| 6 | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| 7 | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| 9 | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| 10 | | | | | | | | | | | | | | | | | | |

CONTINUED NEXT PAGE

(LOG TO BE READ IN CONJUNCTION WITH REPORT)

DEPTH SCALE

1 : 50



LOGGED: BK

CHECKED: TA

AECOM_BH_001_60634622 - DYT3 OTTAWA 2022_04_12.GPJ GAL-MISS.GDT 22-10-11

2022.03.15

PROJECT: DYT3 - Ottawa
 LOCATION: 2625 Sheffield Rd
 COORDINATES: N 5027916.8; E 452712.8
 DATUM: Geodetic
 AECOM PROJECT #: 60634622
 CLIENT: Amazon Logistics

RECORD OF BOREHOLE: BH-S2/MW

SHEET 2 OF 3

START DATE: Mar 15, 2022
 END DATE: Mar 15, 2022
 BORING METHOD: 200 mm O.D. Hollow Stem Auger
 CONTRACTOR: Canadian Environmental Drilling
 PENETRATION TEST HAMMER, 64kg; DROP, 760mm
 SAMPLER HAMMER, 64kg; DROP, 760mm

| DEPTH SCALE (METRES) | BORING METHOD | SOIL PROFILE | | SAMPLES | | | Dynamic Cone Penetration Testing (blows/0.3m) | | | | SHEAR STRENGTH Cu, kPa | | | | ADDITIONAL LAB. TESTING & GRAIN SIZE DISTRIBUTION (%) | WELL INSTALLATION AND WATER LEVELS | |
|-------------------------|---------------|--|-------------|-----------------|--------|------|---|-----------------|--|--|------------------------|-------------|--|--|---|------------------------------------|--|
| | | DESCRIPTION | STRATA PLOT | ELEV. DEPTH (m) | NUMBER | TYPE | N VALUE | 20 40 60 80 | | | | 20 40 60 80 | | | | | |
| | | | | | | | | 100 200 300 400 | | | | 10 20 30 40 | | | | | |
| 10 | | CONTINUED FROM PREVIOUS PAGE | | | | | | | | | | | | | GR SA SI CL | | |
| | | SILTY CLAY: trace gravel, some sand, brown to grey, moist to wet, very soft to stiff | | | | | | | | | | | | | | | |
| | | SHALE BEDROCK: Refer to RECORD OF DRILLHOLE: BH-S2/MW Highly weathered, grey, horizontal bedding, vertical and inclined open joints, clay infilling RUN 1 10.67-10.98 TCR=100%, SCR=42%, RQD=0%, FI=9 RUN 2 10.98-12.50 TCR=93%, SCR=27%, RQD=0%, FI=10 RUN 3 12.50-12.80 TCR=100%, SCR=13%, RQD=0%, FI=9 | | 56.33 10.67 | | | | | | | | | | | | | |
| 11 | Coring | | | | | | | | | | | | | | | | |
| 12 | Coring | | | | | | | | | | | | | | | | |
| 13 | | END OF BOREHOLE Notes: 1. This log is to be read with the subject report and project number as presented above. 2. Interpretation assistance by AECOM is required for projects excluding the above mentioned project. 3. No abnormal odour or staining was observed unless otherwise indicated. 4. The groundwater was observed at the depth of 4.27 mbgs in the open hole. 5. The monitoring well was installed upon the completion of drilling. | | 54.20 12.80 | | | | | | | | | | | | | |
| 14 | | | | | | | | | | | | | | | | | |
| 15 | | | | | | | | | | | | | | | | | |
| 16 | | | | | | | | | | | | | | | | | |
| 17 | | | | | | | | | | | | | | | | | |
| 18 | | | | | | | | | | | | | | | | | |
| 19 | | | | | | | | | | | | | | | | | |
| 20 | | | | | | | | | | | | | | | | | |

(LOG TO BE READ IN CONJUNCTION WITH REPORT)

DEPTH SCALE

1 : 50



LOGGED: BK

CHECKED: TA

AECOM_BH_001_60634622 - DYT3 OTTAWA 2022_04_12.GPJ GAL-MISS.GDT 22-10-11

PROJECT: DYT3 - Ottawa
 LOCATION: 2625 Sheffield Rd
 COORDINATES: N 5027916.8; E 452712.8
 DATUM: Geodetic
 AECOM PROJECT #: 60634622
 CLIENT: Amazon Logistics

RECORD OF DRILLHOLE: BH-S2/MW

SHEET 3 OF 3

START DATE: Mar 15, 2022
 END DATE: Mar 15, 2022
 DRILLING METHOD:

CONTRACTOR: Canadian Environmental Drilling INCLINATION: -90° AZIMUTH: ---

| DEPTH SCALE METRES | DRILLING RECORD | DESCRIPTION | SYMBOLIC LOG | ELEV. DEPTH (m) | RUN No. | PENETRATION RATE (mm/min) | FLUSH | COLOUR | % RETURN | FR/FX-FRACTURE | F-FAULT | SM-SMOOTH | FL-FLEXURED | BC-BROKEN CORE | WELL INSTALLATION AND WATER LEVELS |
|--------------------|-----------------|--|----------------------|------------------------------|--|---------------------------|------------------|--------|----------------------------------|----------------|----------------|------------|-------------|----------------|------------------------------------|
| | | | | | | | | | | CL-CLEAVAGE | J-JOINT | R-ROUGH | UE-UNEVEN | MB-MECH. BREAK | |
| | | | | | | | | | | SH-SHEAR | P-POLISHED | ST-STEPPED | W-WAVY | B-BEDDING | |
| | | | | | | | | | | VN-VEIN | S-SLICKENSIDED | PL-PLANAR | C-CURVED | | |
| RECOVERY | | R.Q.D. % | FRACT. INDEX PER 0.3 | DISCONTINUITY DATA | | HYDRAULIC CONDUCTIVITY | | | DIAMETRAL POINT LOAD INDEX (MPa) | | | | | | |
| TOTAL CORE % | SOLID CORE % | % | DIP w.r.t. CORE AXIS | TYPE AND SURFACE DESCRIPTION | 10 ⁻⁶ K _v cm ² /sec | 10 ⁻⁴ | 10 ⁻² | | | | | | | | |
| 11 | | ASPHALT | | 56.33 | | | | | | | | | | | |
| | | Highly weathered, grey, horizontal bedding, open joints, clay infilling SHALE | | 10.67 | 1 | | | | | | | | | | 36.2 |
| | | 45° inclined joints and vertical joints | | 56.02 | | | | | | | | | | | |
| | | | | 10.98 | | | | | | | | | | | 10.3 |
| 12 | | | | | 2 | | | | | | | | | | |
| | | | | 54.50 | | | | | | | | | | | |
| | | | | 12.50 | | | | | | | | | | | |
| | | | | 54.20 | | | | | | | | | | | |
| 13 | | END OF BOREHOLE | | 12.80 | 3 | | | | | | | | | | |
| | | Notes: 1. This log is to be read with the subject report and project number as presented above. 2. Interpretation assistance by AECOM is required for projects excluding the above mentioned project. 3. No abnormal odour or staining was observed unless otherwise indicated. 4. The groundwater was observed at the depth of 4.27 mbgs in the open hole. 5. The monitoring well was installed upon the completion of drilling. | | | | | | | | | | | | | |
| 14 | | | | | | | | | | | | | | | |
| 15 | | | | | | | | | | | | | | | |
| 16 | | | | | | | | | | | | | | | |
| 17 | | | | | | | | | | | | | | | |
| 18 | | | | | | | | | | | | | | | |
| 19 | | | | | | | | | | | | | | | |
| 20 | | | | | | | | | | | | | | | |

AECOM_RCK_001_60634622 - DYT3 OTTAWA 2022_04_12.GPJ GAL-MISS.GDT 22-10-11

DEPTH SCALE

1 : 50



LOGGED: BK

CHECKED: TA

PROJECT: DYT3 - Ottawa
 LOCATION: 2625 Sheffield Rd
 COORDINATES: N 5028091.4; E 452590.1
 DATUM: Geodetic
 AECOM PROJECT #: 60634622
 CLIENT: Amazon Logistics

RECORD OF BOREHOLE: DCPT-1

SHEET 1 OF 1

START DATE: Mar 14, 2022
 END DATE: Mar 14, 2022
 BORING METHOD: 50.8 mm diameter CPT
 CONTRACTOR: Canadian Environmental Drilling
 PENETRATION TEST HAMMER, 64kg; DROP, 760mm
 SAMPLER HAMMER, 64kg; DROP, 760mm

| DEPTH SCALE (METRES) | BORING METHOD | SOIL PROFILE | | SAMPLES | | | Dynamic Cone Penetration Testing (blows/0.3m) | | SHEAR STRENGTH Cu, kPa | | ADDITIONAL LAB. TESTING & GRAIN SIZE DISTRIBUTION (%) | WELL INSTALLATION AND WATER LEVELS | |
|----------------------|--|---|-------------|-----------------|--------|------|---|----|------------------------|----|---|------------------------------------|----|
| | | DESCRIPTION | STRATA PLOT | ELEV. DEPTH (m) | NUMBER | TYPE | N VALUE | 20 | 40 | 60 | | | 80 |
| 0 | Dynamic Cone Penetration Testing 50.8 mm diameter CPT | PAVEMENT | | 67.00 | | | | | | | GR SA SI CL | | |
| | | ASPHALT: 50 mm thick | | | | | | | | | | | |
| 1 | | | | | | | | | | | | | |
| 2 | | | | | | | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | | | | | | | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | | | | | | | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | | END OF BOREHOLE | | 9.75 | | | | | | | | | |
| 11 | | Notes: 1. This log is to be read with the subject report and project number as presented above. 2. Interpretation assistance by AECOM is required for projects excluding the above mentioned project. 3. No abnormal odour or staining was observed unless otherwise indicated. 4. The groundwater was observed at the depth of 4.27 mbgs in the open hole. | | | | | | | | | | | |
| 12 | | | | | | | | | | | | | |
| 13 | | | | | | | | | | | | | |
| 14 | | | | | | | | | | | | | |
| 15 | | | | | | | | | | | | | |

▽
2022.03.14

AECOM_BH_001_60634622 - DYT3 OTTAWA 2022_04_12.GPJ GAL-MISS.GDT 22-10-11

(LOG TO BE READ IN CONJUNCTION WITH REPORT)

DEPTH SCALE

1 : 75



LOGGED: BK

CHECKED: TA

PROJECT: DYT3 - Ottawa
 LOCATION: 2625 Sheffield Rd
 COORDINATES: N 5028025.2; E 452766.4
 DATUM: Geodetic
 AECOM PROJECT #: 60634622
 CLIENT: Amazon Logistics

RECORD OF BOREHOLE: DCPT-2

SHEET 1 OF 1

START DATE: Mar 14, 2022
 END DATE: Mar 14, 2022
 BORING METHOD: 50.8 mm diameter CPT
 CONTRACTOR: Canadian Environmental Drilling

PENETRATION TEST HAMMER, 64kg; DROP, 760mm
 SAMPLER HAMMER, 64kg; DROP, 760mm

| DEPTH SCALE (METRES) | BORING METHOD | SOIL PROFILE | | SAMPLES | | | Dynamic Cone Penetration Testing (blows/0.3m) | | SHEAR STRENGTH Cu, kPa | | ADDITIONAL LAB. TESTING & GRAIN SIZE DISTRIBUTION (%) | WELL INSTALLATION AND WATER LEVELS | |
|----------------------|--|---|-------------|-----------------|--------|------|---|----|------------------------|----|---|------------------------------------|----|
| | | DESCRIPTION | STRATA PLOT | ELEV. DEPTH (m) | NUMBER | TYPE | N VALUE | 20 | 40 | 60 | | | 80 |
| 0 | | PAVEMENT | | 67.50 | | | | | | | | | |
| | | ASPHALT: 40 mm thick | | | | | | | | | | | |
| 1 | Dynamic Cone Penetration Testing 50.8 mm diameter CPT | | | | | | | | | | | | |
| 2 | | | | | | | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | | | | | | | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | | | | | | | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | | | | | | | | | | | | | |
| 11 | | END OF BOREHOLE | | 10.67 | | | | | | | | | |
| 12 | | Notes: 1. This log is to be read with the subject report and project number as presented above. 2. Interpretation assistance by AECOM is required for projects excluding the above mentioned project. 3. No abnormal odour or staining was observed unless otherwise indicated. 4. The groundwater was observed at the depth of 4.57 mbgs in the open hole. | | | | | | | | | | | |
| 13 | | | | | | | | | | | | | |
| 14 | | | | | | | | | | | | | |
| 15 | | | | | | | | | | | | | |

2022.03.14

AECOM_BH_001_60634622 - DYT3 OITAWA 2022_04_12.GPJ GAL-MISS.GDT 22-10-11

(LOG TO BE READ IN CONJUNCTION WITH REPORT)

DEPTH SCALE

1 : 75



LOGGED: BK

CHECKED: TA


Appendix B Laboratory Results

MOISTURE CONTENT DETERMINATION

| CLIENT | | | | AECOM | | | DATE | | March 28, 2022 | |
|----------------|-----------|--------------|--------|---|--|--|---|--|---|-------|
| PROJECT NUMBER | | | | 60634622 | | | TESTED BY | | SAM/DHARMIK | |
| PROJECT NAME | | | | DYT3 | | | REVIEWED BY | | Ramana M | |
| LOCATION | | | | 2625 Sheffield Rd, Ottawa, ON | | | | | | |
| Borehole Name | Sample Id | Depth (feet) | Can Id | Observations | | | Formula | | | |
| | | | | Weight of Empty Can (g) W ₁ | Weight of Wet Soil + Can (g) W ₂ | Weight of Dry Soil + Can (g) W ₃ | Weight of Water (g) W _w = (W ₂ -W ₃) | Weight of Dry soil (g) W _s = (W ₃ -W ₁) | Moisture Content (%) w = (W _w /W _s)*100 | |
| S1MW | SS1 | | 114 | 13.40 | 71.64 | 66.49 | 5.15 | 53.09 | 9.70 | |
| | SS2 | | 174 | 13.66 | 83.21 | 78.18 | 5.03 | 64.52 | 7.80 | |
| | SS3 | | 87 | 13.68 | 64.32 | 52.02 | 12.30 | 38.34 | 32.08 | |
| | SS4 | | 148 | 13.47 | 58.60 | 46.23 | 12.37 | 32.76 | 37.76 | |
| | SS6 | | 111 | 13.58 | 83.02 | 64.70 | 18.32 | 51.12 | 35.84 | |
| | SS7 | | 105 | 13.85 | 95.34 | 87.63 | 7.71 | 73.78 | 10.45 | |
| | SS8 | | 63 | 13.49 | 81.09 | 74.80 | 6.29 | 61.31 | 10.26 | |
| | SS9 | | 132 | 13.72 | 69.74 | 62.13 | 7.61 | 48.41 | 15.72 | |
| | S2MW | SS1 | | 82 | 13.47 | 72.24 | 70.18 | 2.06 | 56.71 | 3.63 |
| SS2 | | | 161 | 13.48 | 86.74 | 75.35 | 11.39 | 61.87 | 18.41 | |
| SS3 | | | 173 | 13.45 | 82.40 | 69.36 | 13.04 | 55.91 | 23.32 | |
| SS4 | | | 165 | 13.71 | 64.42 | 47.84 | 16.58 | 34.13 | 48.58 | |
| SS5 | | | 134 | 13.69 | 74.97 | 53.78 | 21.19 | 40.09 | 52.86 | |
| SS6 | | | 181 | 13.60 | 91.34 | 62.39 | 28.95 | 48.79 | 59.34 | |
| SS8 | | | 144 | 13.66 | 102.50 | 84.24 | 18.26 | 70.58 | 25.87 | |
| S1MW | | TW1-1(TOP) | 78' | 56 | 13.56 | 39.96 | 32.26 | 7.70 | 18.70 | 41.18 |
| | TW1-2 | 78' | 106 | 13.51 | 75.01 | 70.41 | 4.60 | 56.90 | 8.08 | |
| S2MW | TW2(TOP) | | 116 | 13.74 | 111.35 | 95.93 | 15.42 | 82.19 | 18.76 | |
| | SS9 | | 168 | 13.62 | 94.40 | 86.68 | 7.72 | 73.06 | 10.57 | |

Total Samples 19


| AECOM CANADA LTD. | | AECOM | | | | | |
|--|-------------------------|----------------|----------|--------------|----------|---------------|------------|
| DETERMINATION OF LIQUID LIMIT | | | | | | | |
| Client | AECOM | Project Number | 60634662 | | Date | April 3, 2022 | |
| Project Name | Sheffield Rd | | | Tested By | Ian P | | |
| Location | Ottawa | | | Reviewed By | Ramana M | | |
| Borehole Number | S1/MW | Sample Id | SS7 | Depth (feet) | 20-22 | Lab Number | 202204003S |
| Description | Formula | Trial 1 | Trial 2 | Trial 3 | Trial 4 | Trial 5 | Trial 6 |
| Container Number | | 134 | 175 | 146 | 149 | 136 | |
| Weight of Empty Container (g) W_1 | | 13.69 | 13.68 | 13.77 | 13.64 | 13.83 | |
| Weight of Container + Wet Soil (g) W_2 | | 19.70 | 21.64 | 21.68 | 20.73 | 22.64 | |
| Weight of Container + Dry Soil(g) W_3 | | 17.81 | 19.21 | 19.21 | 18.60 | 20.04 | |
| Weight of Water (g) W_w | $W_w = W_2 - W_3$ | 1.89 | 2.43 | 2.47 | 2.13 | 2.60 | |
| Weight of Dry Soil (g) W_s | $W_s = W_3 - W_1$ | 4.12 | 5.53 | 5.44 | 4.96 | 6.21 | |
| Water Content (%) | $w = (W_w / W_s) * 100$ | 45.87 | 43.94 | 45.40 | 42.94 | 41.87 | |
| Number of Blows | | 10 | 21 | 14 | 34 | 50 | |
| Liquid Limit (%) From Graph | | 43.7 | | | | | |



| AECOM CANADA LTD. AECOM | | | | | | | |
|--|-------------------------|----------------|----------|--------------|----------|---------------|------------|
| DETERMINATION OF PLASTIC LIMIT | | | | | | | |
| Client | AECOM | Project Number | 60634662 | | Date | April 3, 2022 | |
| Project Name | Sheffield Rd | | | Tested By | Ian P | | |
| Location | Ottawa | | | Reviewed By | Ramana M | | |
| Borehole Number | S1/MW | Sample Id | SS7 | Depth (feet) | 20-22 | Lab Number | 202204003S |
| Description | Formula | Trial 1 | Trial 2 | Trial 3 | Trial 4 | Trial 5 | Trial 6 |
| Container Number | | 156 | 132 | 64 | | | |
| Weight of Empty Container (g) W_1 | | 13.41 | 13.70 | 13.48 | | | |
| Weight of Container + Wet Soil (g) W_2 | | 14.34 | 14.98 | 14.63 | | | |
| Weight of Container + Dry Soil (g) W_3 | | 14.14 | 14.70 | 14.38 | | | |
| Weight of Water (g) W_w | $W_w = W_2 - W_3$ | 0.20 | 0.28 | 0.25 | | | |
| Weight of Dry Soil (g) W_s | $W_s = W_3 - W_1$ | 0.73 | 1.00 | 0.90 | | | |
| Plastic Limit (%) | $w = (W_w / W_s) * 100$ | 27.40 | 28.00 | 27.78 | | | |
| Average Plastic Limit (%) w_p | | 27.73 | | | | | |

| Result Summary | |
|----------------------|---------|
| Liquid Limit (%) | 44 |
| Plastic Limit (%) | 28 |
| Plasticity Index (%) | 16 |
| Sample status | Plastic |


| AECOM CANADA LTD. | | AECOM | | | | | |
|--|-------------------------|----------------|----------|--------------|-------------|---------------|------------|
| DETERMINATION OF LIQUID LIMIT | | | | | | | |
| Client | AECOM | Project Number | 60634662 | | Date | April 3, 2022 | |
| Project Name | Sheffield Rd | | | | Tested By | | |
| Location | Ottawa | | | | Reviewed By | Ramana M | |
| Borehole Number | S2/MW | Sample Id | SS5 | Depth (feet) | 10-12 | Lab Number | 202204005S |
| Description | Formula | Trial 1 | Trial 2 | Trial 3 | Trial 4 | Trial 5 | Trial 6 |
| Container Number | | 283 | 229 | 33 | 223 | | |
| Weight of Empty Container (g) W_1 | | 12.40 | 12.40 | 12.00 | 12.50 | | |
| Weight of Container + Wet Soil (g) W_2 | | 20.40 | 22.00 | 22.50 | 22.90 | | |
| Weight of Container + Dry Soil(g) W_3 | | 18.10 | 19.30 | 19.51 | 19.92 | | |
| Weight of Water (g) W_w | $W_w = W_2 - W_3$ | 2.30 | 2.70 | 2.99 | 2.98 | | |
| Weight of Dry Soil (g) W_s | $W_s = W_3 - W_1$ | 5.70 | 6.90 | 7.51 | 7.42 | | |
| Water Content (%) | $w = (W_w / W_s) * 100$ | 40.35 | 39.13 | 39.81 | 40.16 | | |
| Number of Blows | | 13 | 35 | 26 | 21 | | |
| Liquid Limit (%) From Graph | | 39.7 | | | | | |



| AECOM CANADA LTD. AECOM | | | | | | | |
|--|-------------------------|----------------|----------|--------------|---------------|------------|------------|
| DETERMINATION OF PLASTIC LIMIT | | | | | | | |
| Client | AECOM | Project Number | 60634662 | Date | April 3, 2022 | | |
| Project Name | Sheffield Rd | | | Tested By | 0 | | |
| Location | Ottawa | | | Reviewed By | Ramana M | | |
| Borehole Number | SZ/MW | Sample Id | SS5 | Depth (feet) | 10-12 | Lab Number | 202204005S |
| Description | Formula | Trial 1 | Trial 2 | Trial 3 | Trial 4 | Trial 5 | Trial 6 |
| Container Number | | 196 | 255 | 22 | | | |
| Weight of Empty Container (g) W_1 | | 12.4 | 12.50 | 12.00 | | | |
| Weight of Container + Wet Soil (g) W_2 | | 19.6 | 19.30 | 20.30 | | | |
| Weight of Container + Dry Soil(g) W_3 | | 18.3 | 18.00 | 19.00 | | | |
| Weight of Water (g) W_w | $W_w = W_2 - W_3$ | 1.30 | 1.30 | 1.30 | | | |
| Weight of Dry Soil (g) W_s | $W_s = W_3 - W_1$ | 5.90 | 5.50 | 7.00 | | | |
| Plastic Limit (%) | $w = (W_w / W_s) * 100$ | 22.03 | 23.64 | 18.57 | | | |
| Average Plastic Limit (%) w_p | | 21.41 | | | | | |

| Result Summary | |
|----------------------|---------|
| Liquid Limit (%) | 40 |
| Plastic Limit (%) | 21 |
| Plasticity Index (%) | 19 |
| Sample status | Plastic |

| AECOM CANADA LTD. | | AECOM | | | | | |
|--|-------------------------|----------------|----------|--------------|-------------|---------------|---------|
| DETERMINATION OF LIQUID LIMIT | | | | | | | |
| Client | AECOM | Project Number | 60634662 | | Date | April 3, 2022 | |
| Project Name | Sheffield Rd | | | | Tested By | | |
| Location | Ottawa | | | | Reviewed By | Ramana M | |
| Borehole Number | S2/MW | Sample Id | TW1/SS1 | Depth (feet) | Lab Number | 202204006S | |
| Description | Formula | Trial 1 | Trial 2 | Trial 3 | Trial 4 | Trial 5 | Trial 6 |
| Container Number | | 284 | 278 | 40 | 251 | | |
| Weight of Empty Container (g) W_1 | | 12.41 | 12.40 | 12.00 | 12.40 | | |
| Weight of Container + Wet Soil (g) W_2 | | 22.80 | 23.10 | 23.90 | 23.80 | | |
| Weight of Container + Dry Soil(g) W_3 | | 20.60 | 20.70 | 20.90 | 20.66 | | |
| Weight of Water (g) W_w | $W_w = W_2 - W_3$ | 2.20 | 2.40 | 3.00 | 3.14 | | |
| Weight of Dry Soil (g) W_s | $W_s = W_3 - W_1$ | 8.19 | 8.30 | 8.90 | 8.26 | | |
| Water Content (%) | $w = (W_w / W_s) * 100$ | 26.86 | 28.92 | 33.71 | 38.01 | | |
| Number of Blows | | 35 | 25 | 17 | 13 | | |
| Liquid Limit (%) From Graph | | 29.9 | | | | | |



| AECOM CANADA LTD. AECOM | | | | | | | |
|--|-------------------------|----------------|----------|--------------|---------------|------------|------------|
| DETERMINATION OF PLASTIC LIMIT | | | | | | | |
| Client | AECOM | Project Number | 60634662 | Date | April 3, 2022 | | |
| Project Name | Sheffield Rd | | | Tested By | 0 | | |
| Location | Ottawa | | | Reviewed By | Ramana M | | |
| Borehole Number | SZ/MW | Sample Id | TW1/SS1 | Depth (feet) | 0 | Lab Number | 202204006S |
| Description | Formula | Trial 1 | Trial 2 | Trial 3 | Trial 4 | Trial 5 | Trial 6 |
| Container Number | | 214 | 18 | 293 | | | |
| Weight of Empty Container (g) W_1 | | 12.4 | 11.90 | 12.40 | | | |
| Weight of Container + Wet Soil (g) W_2 | | 20.4 | 18.90 | 20.00 | | | |
| Weight of Container + Dry Soil(g) W_3 | | 19.12 | 17.78 | 18.79 | | | |
| Weight of Water (g) W_w | $W_w = W_2 - W_3$ | 1.28 | 1.12 | 1.21 | | | |
| Weight of Dry Soil (g) W_s | $W_s = W_3 - W_1$ | 6.72 | 5.88 | 6.39 | | | |
| Plastic Limit (%) | $w = (W_w / W_s) * 100$ | 19.05 | 19.05 | 18.94 | | | |
| Average Plastic Limit (%) w_p | | 19.01 | | | | | |

| Result Summary | |
|----------------------|---------|
| Liquid Limit (%) | 30 |
| Plastic Limit (%) | 19 |
| Plasticity Index (%) | 11 |
| Sample status | Plastic |

AECOM CANADA LTD.



| | | | | | |
|---------------------|------------------------------|-------------|-------|--------------|---------------|
| Client | AECOM | Borehole No | S1/MW | Lab No | 2022040015 |
| Project Number | 60634622 | Sample ID | SS2 | Date | April 1, 2022 |
| Project Name | Sheffield Rd | | | Depth (Feet) | 2.5-5 |
| Location | Ottawa | | | Tested by | SAM |
| Soil Classification | Silty Sand, some gravel (SM) | | | Reviewed by | Ramona M |

| | | | | | |
|-------------------------|-------|------------------------|------|----------------------|------|
| Total Sample Mass (A) g | 134.8 | % Coarse Aggregate (D) | 17.7 | % Fine Aggregate (E) | 82.3 |
|-------------------------|-------|------------------------|------|----------------------|------|

| COARSE AGGREGATE | | | | | |
|------------------|------------------------------|----------------------------------|------------------------------------|-----------|--------------------------|
| Sieve (mm) | Individual Mass Retained (g) | Cumulative Mass Retained (g) [X] | Coarse Aggregate Portion Only | | % Passing (Total Sample) |
| | | | % Retained | % Passing | |
| 106 | | | | 100.0 | 100.0 |
| 75.0 | | | | 100.0 | 100.0 |
| 63.0 | | | | 100.0 | 100.0 |
| 53.0 | | | | 100.0 | 100.0 |
| 37.5 | | | | 100.0 | 100.0 |
| 26.5 | | | | 100.0 | 100.0 |
| 22.4 | | | | 100.0 | 100.0 |
| 19.0 | | | | 100.0 | 100.0 |
| 16.0 | | | | 100.0 | 100.0 |
| 13.2 | 3.8 | 3.8 | 15.7 | 84.3 | 97.2 |
| 9.5 | 8.7 | 12.4 | 52.0 | 48.0 | 90.8 |
| 6.7 | 7.1 | 19.5 | 81.6 | 18.4 | 85.5 |
| 4.75 | 4.4 | 23.9 | 100.0 | | 82.3 |
| Pan | 109.9 | Pan + [B] | Mass Passing 4.75 mm (g) [C = A-B] | | 110.9 |

| FINE AGGREGATE | | | |
|------------------------------------|-------|---|-------|
| Sample Mass before washing (g) [F] | 109.9 | Mass passing 75 µm sieve by washing (g) | 32.77 |
| Sample Mass after washing (g) | 77.13 | Mass passing 75 µm sieve by sieving (g) | 0.65 |

| Sieve (mm) | Cumulative Mass Retained (g) [Y] | Fine Aggregate Portion Only | | % Passing (Total Sample) |
|------------|----------------------------------|------------------------------------|-----------|--------------------------|
| | | % Retained | % Passing | |
| 4.75 | | | 100.0 | 82.27 |
| 2.36 | 13.7 | 12.5 | 87.5 | 72.01 |
| 1.18 | 33.33 | 30.3 | 69.7 | 57.32 |
| 0.600 | 50.56 | 46.0 | 54.0 | 44.42 |
| 0.425 | 57.17 | 52.0 | 48.0 | 39.47 |
| 0.300 | 63.19 | 57.5 | 42.5 | 34.97 |
| 0.150 | 71.02 | 64.6 | 35.4 | 29.11 |
| 0.075 | 76.48 | 69.6 | 30.4 | 25.02 |
| Pan | 0.65 | Total Mass passing 75 µm sieve (g) | 33.42 | |

Calculations:

$D = (B/A) * 100$
 $E = (C/A) * 100$

Coarse Aggregate Portion:
 % Retained = $(X/B) * 100$
 % Passing = $((B-X)/B) * 100$

Fine Aggregate Portion:
 % Retained = $(Y/F) * 100$
 % Passing = $((F-Y)/F) * 100$

Total Mass Calculations


% Retained on Coarse Aggregate Sieves = $(X/A) * 100$

% Retained on Fine Aggregate Sieves = $(Y/F) * E + \% \text{ Ret. } 4.75$

% Passing Coarse Aggregate Sieves = $((A-X)/A) * 100$

% Passing on Fine Aggregate Sieves = $((F-Y)/F) * E$

UNIFIED SOIL CLASSIFICATION SYSTEM



GRAIN SIZE DISTRIBUTION CURVE (SIEVE AND HYDROMETER ANALYSIS)

| | | | | | | | | | | | | | | | |
|--|-------------------------|---------|------------------------------|----------|--------------|----------------------|---------------|----------------------|------------------|----------------------|------------|----------------|-----|----------------|-----|
| AECOM CANADA LTD. 83 Galaxy Blvd, Unit 6 Toronto, Ontario | Client | | AECOM | | Date | | April 1, 2022 | | Project Number | | 60634622 | | | | |
| | Borehole No / Sample Id | | S1/MW SS2 | | Depth (feet) | | 2.5-5 | | Lab No | | 202204001S | | | | |
| | Project Name | | Sheffield Rd | | | | | | Project Location | | Ottawa | | | | |
| | Soil Classification | | Silty Sand, some gravel (SM) | | | | | | Figure No: | | | | | | |
| Gravel(%) | 18 | Sand(%) | 57 | Fines(%) | 25 | D ₆₀ (mm) | 1.395 | D ₃₀ (mm) | 0.173 | D ₁₀ (mm) | N/A | C _u | N/A | C _c | N/A |

| | | | | | |
|---------------------|-------------------------------|-------------|-------|--------------|---------------|
| Client | AECOM | Borehole No | S2/MW | Lab No | 2022040045 |
| Project Number | 60634622 | Sample ID | SS2 | Date | April 1, 2022 |
| Project Name | Sheffield Rd | | | Depth (Feet) | 2.5-5 |
| Location | Ottawa | | | Tested by | SAM |
| Soil Classification | Silty Sand, trace gravel (SM) | | | Reviewed by | |

| | | | | | |
|-------------------------|-------|------------------------|------|----------------------|------|
| Total Sample Mass (A) g | 475.5 | % Coarse Aggregate (D) | 10.9 | % Fine Aggregate (E) | 89.1 |
|-------------------------|-------|------------------------|------|----------------------|------|

| COARSE AGGREGATE | | | | | |
|------------------|------------------------------|----------------------------------|------------------------------------|-----------|--------------------------|
| Sieve (mm) | Individual Mass Retained (g) | Cumulative Mass Retained (g) [X] | Coarse Aggregate Portion Only | | % Passing (Total Sample) |
| | | | % Retained | % Passing | |
| 106 | | | | 100.0 | 100.0 |
| 75.0 | | | | 100.0 | 100.0 |
| 63.0 | | | | 100.0 | 100.0 |
| 53.0 | | | | 100.0 | 100.0 |
| 37.5 | | | | 100.0 | 100.0 |
| 26.5 | | | | 100.0 | 100.0 |
| 22.4 | | | | 100.0 | 100.0 |
| 19.0 | | | | 100.0 | 100.0 |
| 16.0 | 5.9 | 5.9 | 11.3 | 88.7 | 98.8 |
| 13.2 | 9.1 | 14.9 | 28.8 | 71.2 | 96.9 |
| 9.5 | 12.4 | 27.4 | 52.9 | 47.1 | 94.2 |
| 6.7 | 10.0 | 37.4 | 72.1 | 27.9 | 92.1 |
| 4.75 | 14.4 | 51.8 | 100.0 | | 89.1 |
| Pan | 423.1 | Pan + [B] | Mass Passing 4.75 mm (g) [C = A-B] | | 423.72 |

| FINE AGGREGATE | | | |
|------------------------------------|-------|---|-----|
| Sample Mass before washing (g) [F] | 210.5 | Mass passing 75 µm sieve by washing (g) | 53 |
| Sample Mass after washing (g) | 157.5 | Mass passing 75 µm sieve by sieving (g) | 8.8 |

| Sieve (mm) | Cumulative Mass Retained (g) [Y] | Fine Aggregate Portion Only | | % Passing (Total Sample) |
|------------|----------------------------------|------------------------------------|-----------|--------------------------|
| | | % Retained | % Passing | |
| 4.75 | | | 100.0 | 89.11 |
| 2.36 | 8.09 | 3.8 | 96.2 | 85.69 |
| 1.18 | 16.08 | 7.6 | 92.4 | 82.30 |
| 0.600 | 23.7 | 11.3 | 88.7 | 79.08 |
| 0.425 | 30.03 | 14.3 | 85.7 | 76.40 |
| 0.300 | 42.42 | 20.2 | 79.8 | 71.15 |
| 0.150 | 105.36 | 50.1 | 49.9 | 44.51 |
| 0.075 | 148.7 | 70.6 | 29.4 | 26.16 |
| Pan | 8.8 | Total Mass passing 75 µm sieve (g) | 61.8 | |

Calculations:

$D = (B/A) * 100$
 $E = (C/A) * 100$

Coarse Aggregate Portion:
 % Retained = $(X/B) * 100$
 % Passing = $((B-X)/B) * 100$

Fine Aggregate Portion:
 % Retained = $(Y/F) * 100$
 % Passing = $((F-Y)/F) * 100$

Total Mass Calculations


% Retained on Coarse Aggregate Sieves = $(X/A) * 100$

% Retained on Fine Aggregate Sieves = $(Y/F) * E + \% \text{ Ret. } 4.75$

% Passing Coarse Aggregate Sieves = $((A-X)/A) * 100$

% Passing on Fine Aggregate Sieves = $((F-Y)/F) * E$

UNIFIED SOIL CLASSIFICATION SYSTEM



GRAIN SIZE DISTRIBUTION CURVE (SIEVE AND HYDROMETER ANALYSIS)

| | | | | | | | | | | | | | | | |
|--|--------------------------------|-------------------------------|----|---------------------|---------------|----------------------------|-----------------------|----------------------------|--------|----------------------------|-----|----------------------|-----|----------------------|-----|
| AECOM CANADA LTD. 83 Galaxy Blvd, Unit 6 Toronto, Ontario | Client | AECOM | | Date | April 1, 2022 | | Project Number | 60634622 | | | | | | | |
| | Borehole No / Sample Id | S2/MW SS2 | | Depth (feet) | 2.5-5 | | Lab No | 202204004S | | | | | | | |
| | Project Name | Sheffield Rd | | | | | | Project Location | Ottawa | | | | | | |
| | Soil Classification | Silty Sand, trace gravel (SM) | | | | | | Figure No: | | | | | | | |
| Gravel (%) | 11 | Sand (%) | 63 | Fines (%) | 26 | D₆₀ (mm) | 0.237 | D₃₀ (mm) | 0.091 | D₁₀ (mm) | N/A | C_u | N/A | C_c | N/A |

Hydrometer Analysis

| | |
|----------------|------------|
| Lab No | 202204002S |
| Project Name | DYT3 |
| Project Number | 60634622 |
| Location | OTTAWA |

| | | | |
|---------------------|----------------------------|-------------|----------------|
| Borehole No | S1/MW | Tested by | IP/SAM/DHARMIK |
| Sample Id | SS4 | Reviewed by | Ramana M |
| Depth (feet) | | Date | |
| Soil Classification | Lean Clay, trace sand (CL) | | |

| Soil Hydrometer Used | |
|----------------------|--------|
| 151 H SN# | 993585 |
| | 115105 |

| Soil Information | |
|--|---------|
| Liquid Limit (LL) | |
| Plasticity Index (PI) | |
| Specific Gravity of Soil (Gs) | 2.70 |
| Specific Gravity of Water (Gw) | 1 |
| Sg Correction Factor (α) | 0.989 |
| Total Mass of sample | 197.8 g |
| Soil Particles Greater Than This Are Excluded From Graph | 9.50 mm |

| Hydrometer Details | |
|--|-------------------------|
| Volume of Bulb (V _b) | 61.1 cm ³ |
| Length of Bulb (L _b) | 14.44 cm |
| Length from '1.0' reading to top of Bulb (L _s) | 10.17 cm |
| Scale Dimension (hs) | 0.27 cm/Div |
| Cross-sectional Area of Cylinder (A) | 28.3535 cm ² |
| Meniscus Correction (Hm) | 0.0005 Divisions |

| Calculation of Dry Soil Mass | |
|---|---------|
| Oven Dried Mass (W _o) | 30.48 g |
| Air Dried Mass (W _a) | 30.55 g |
| Hygroscopic Corr Factor (F) | 0.998 |
| Air Dried Mass in Analysis (M _a) | 50 g |
| Oven Dried Mass in Analysis (M _o) | 49.9 g |
| % Passing 2.0 mm Sieve (P ₁₀) | 99.8 |
| Sample Represented (W) | 50.0 g |

| Sieve Analysis of Retained on 2.0 mm Sieve (M2) | | | |
|---|-------------------------------|------------------|-----------|
| Sieve Size (mm) | Cummulative Mass Retained (g) | Mass Passing (g) | % Passing |
| 75.0 | | | |
| 63.0 | | | |
| 53.0 | | | |
| 37.5 | | | |
| 26.5 | | | |
| 19.0 | | | |
| 13.2 | | | |
| 9.5 | | | |
| 4.75 | 0.0 | 197.8 | 100.0 |
| 2.0 | 0.4 | 197.4 | 99.8 |

| Sieve Analysis of Hydrometer Material (M7) | | | |
|--|-------------------------------|------------------|-----------|
| Sieve Size (mm) | Cummulative Mass Retained (g) | Mass Passing (g) | % Passing |
| 2.00 | 0.0 | 49.9 | 99.8 |
| 0.850 | 0.1 | 49.8 | 99.7 |
| 0.425 | 0.2 | 49.7 | 99.4 |
| 0.25 | 0.4 | 49.5 | 99.1 |
| 0.106 | 0.7 | 49.2 | 98.4 |
| 0.075 | 0.8 | 49.0 | 98.1 |
| Pass 0.075 | 0.0 | | |

Percent In Suspension (P) as per Section 14.3 of ASTM D 422

$$P = [(100000/W) * (Gs/(Gs - Gw))] * (R - Gw) \text{ in percent (for Soil Hydrometer 151 H)}$$

Where R = Corrected Hydrometer Reading = Hs - Hc

Hs = Actual Hydrometer Reading
Hc = Composite Correction to be determined as per Section 7 of ASTM D 422

Diameter of Soil Particles (D) as per Section 15 of ASTM D 422

$$D = \text{SQRT of } \{[(30 \cdot \eta) / (980 \cdot (Gs - Gw))] \cdot (L/T)\} \text{ in mm}$$

Where η = Viscosity of suspending Medium (Water) in poises
L = Effective Depth = L1 + 0.5 * [L₂ - V_b / A] in cm
L1 = distance from the top of the bulb to Recorded Hydrometer Reading in cm
T = Time in minutes


| Date | Time | Elapsed Time (minutes) | Hs in Divisions | Hc in Divisions | Temp Tc in C | R=Hs-Hc | P in % | L in cm | η in Poise | K | D in mm |
|----------|-------------|------------------------|-----------------|-----------------|--------------|---------|--------|---------|------------|------------|---------|
| 1-Jan-00 | 10:34:00 AM | 1.0 | 1.0335 | 0.0030 | 26.1 | 1.0305 | 96.9 | 7.36 | 8.75559 | 0.0125568 | 0.0341 |
| | 10:35:00 AM | 2.0 | 1.0330 | 0.0030 | 26.1 | 1.0300 | 95.3 | 7.49 | 8.75559 | 0.0125568 | 0.0243 |
| | 10:38:00 AM | 5.0 | 1.0320 | 0.0030 | 26.1 | 1.0290 | 92.2 | 7.76 | 8.75559 | 0.0125568 | 0.0156 |
| | 10:48:00 AM | 15.0 | 1.0310 | 0.0030 | 26.0 | 1.0280 | 89.0 | 8.03 | 8.77493 | 0.01257066 | 0.0092 |
| | 11:03:00 AM | 30.0 | 1.0300 | 0.0030 | 25.9 | 1.0270 | 85.8 | 8.30 | 8.79435 | 0.01258456 | 0.0066 |
| | 11:33:00 AM | 60.0 | 1.0280 | 0.0030 | 25.8 | 1.0250 | 79.4 | 8.84 | 8.81384 | 0.0125985 | 0.0048 |
| 2-Jan-00 | 2:43:00 PM | 250.0 | 1.0235 | 0.0030 | 25.4 | 1.0205 | 65.1 | 10.06 | 8.89259 | 0.01265465 | 0.0025 |
| | 10:33:00 AM | 1440.0 | 1.0185 | 0.0030 | 20.8 | 1.0155 | 49.3 | 11.41 | 9.89606 | 0.01334957 | 0.0012 |

| L1 cm | Viscosity | |
|-------|-----------|--------------|
| | C | K (η/(Gs-1)) |
| 1.21 | -0.522902 | 5.1503494 |
| 1.35 | -0.522902 | 5.1503494 |
| 1.62 | -0.522902 | 5.1503494 |
| 1.89 | -0.520695 | 5.1617255 |
| 2.16 | -0.518485 | 5.1731466 |
| 2.70 | -0.516271 | 5.1846127 |
| 3.91 | -0.507377 | 5.2309329 |
| 5.27 | -0.400459 | 5.821213 |

| | |
|-----------------------------|-------|
| Mass Retained on Sieve # 10 | 40.5 |
| Mass Passed Sieve # 10 | 157.3 |
| Jar Number | |

| Hygroscopic Data | Can Id | 53 |
|------------------|---------------------------|-------|
| | Empty Can Weight (g) | 13.43 |
| | Can+ Air Dried Soil (g) | 43.98 |
| | Can + Oven Dried Soil (g) | 43.91 |

UNIFIED SOIL CLASSIFICATION SYSTEM



GRAIN SIZE DISTRIBUTION CURVE (SIEVE AND HYDROMETER ANALYSIS)

| | | | | | | | | | | | | |
|--|---------------------|----------------------------|--------------|------------------|----------------|----------|------------|-------|----|-----|----|-----|
| AECOM CANADA LTD. 83 Galaxy Blvd, Unit 6 Toronto, Ontario | Client | AECOM | Date | January 0, 1900 | Project Number | 60634622 | Gravel (%) | 0 | | | | |
| | Sample ID | S1/MW SS4 | Depth (feet) | 0 | Project Name | DTT3 | Sand (%) | 2 | | | | |
| | Lab Sample No: | 202204002S | | Project Location | | OTTAWA | Silt (%) | 39 | | | | |
| | Soil Classification | Lean Clay, trace sand (CL) | | | | | Clay (%) | 59 | | | | |
| | Figure No. | | D10 | N/A | D30 | N/A | D60 | 0.002 | Cu | N/A | Cc | N/A |

Hydrometer Analysis

| | |
|----------------|------------|
| Lab No | 202204003S |
| Project Name | DYT3 |
| Project Number | 60634622 |
| Location | OTTAWA |

| | | | |
|---------------------|--|-------------|----------------|
| Borehole No | S1/MW | Tested by | IP/SAM/DHARMIK |
| Sample Id | SS7 | Reviewed by | Ramana M |
| Depth (feet) | | Date | 12-Apr-22 |
| Soil Classification | Silty Sand, some clay, trace gravel (SM) | | |

| Soil Hydrometer Used | |
|----------------------|--------|
| 151 H SN# | 993585 |
| | 115105 |

| Soil Information | |
|--|---------|
| Liquid Limit (LL) | |
| Plasticity Index (PI) | |
| Specific Gravity of Soil (Gs) | 2.70 |
| Specific Gravity of Water (Gw) | 1 |
| Sg Correction Factor (α) | 0.989 |
| Total Mass of sample | 511.9 g |
| Soil Particles Greater Than This Are Excluded From Graph | 9.50 mm |

| Hydrometer Details | |
|--|-------------------------|
| Volume of Bulb (V _b) | 63.1 cm ³ |
| Length of Bulb (L _b) | 14.15 cm |
| Length from '1.0' reading to top of Bulb (L _s) | 10.5 cm |
| Scale Dimension (hs) | 0.27 cm/Div |
| Cross-sectional Area of Cylinder (A) | 28.1351 cm ² |
| Meniscus Correction (Hm) | 0.0005 Divisions |

| Calculation of Dry Soil Mass | |
|---|---------|
| Oven Dried Mass (W _o) | 28.88 g |
| Air Dried Mass (W _a) | 29.07 g |
| Hygroscopic Corr Factor (F) | 0.993 |
| Air Dried Mass in Analysis (M _a) | 50 g |
| Oven Dried Mass in Analysis (M _o) | 49.7 g |
| % Passing 2.0 mm Sieve (P ₁₀) | 84.6 |
| Sample Represented (W) | 58.7 g |

| Sieve Analysis of Retained on 2.0 mm Sieve (M2) | | | |
|---|-------------------------------|------------------|-----------|
| Sieve Size (mm) | Cummulative Mass Retained (g) | Mass Passing (g) | % Passing |
| 75.0 | | | |
| 63.0 | | | |
| 53.0 | | | |
| 37.5 | | | |
| 26.5 | | | |
| 19.0 | | | |
| 13.2 | | | |
| 9.5 | | | |
| 4.75 | 36.8 | 475.2 | 92.8 |
| 2.0 | 79.0 | 432.9 | 84.6 |

| Sieve Analysis of Hydrometer Material (M7) | | | |
|--|-------------------------------|------------------|-----------|
| Sieve Size (mm) | Cummulative Mass Retained (g) | Mass Passing (g) | % Passing |
| 2.00 | 0.0 | 49.7 | 84.6 |
| 0.850 | 5.3 | 44.4 | 75.5 |
| 0.425 | 9.7 | 40.0 | 68.1 |
| 0.25 | 13.4 | 36.3 | 61.8 |
| 0.106 | 19.6 | 30.1 | 51.3 |
| 0.075 | 22.0 | 27.7 | 47.1 |
| Pass 0.075 | 1.2 | | |

Percent In Suspension (P) as per Section 14.3 of ASTM D 422

$$P = [(100000/W) * (Gs/(Gs - Gw))] * (R - Gw) \text{ in percent (for Soil Hydrometer 151 H)}$$

Where R = Corrected Hydrometer Reading = Hs - Hc

Hs = Actual Hydrometer Reading
Hc = Composite Correction to be determined as per Section 7 of ASTM D 422

Diameter of Soil Particles (D) as per Section 15 of ASTM D 422

$$D = \text{SQRT of } \{[(30 \cdot \eta) / (980 \cdot (Gs - Gw))] \cdot (L/T)\} \text{ in mm}$$

Where η = Viscosity of suspending Medium (Water) in poises
L = Effective Depth = L1 + 0.5 * [L₂ - V_b / A] in cm
L1 = distance from the top of the bulb to Recorded Hydrometer Reading in cm
T = Time in minutes


| Date | Time | Elapsed Time (minutes) | Hs in Divisions | Hc in Divisions | Temp Tc in C | R=Hs-Hc | P in % | L in cm | η in Poise | K | D in mm |
|-----------|-------------|------------------------|-----------------|-----------------|--------------|---------|--------|---------|------------|------------|---------|
| 13-Apr-22 | 10:44:00 AM | 1.0 | 1.0175 | 0.0030 | 25.7 | 1.0145 | 39.2 | 11.49 | 8.83341 | 0.01261248 | 0.0427 |
| | 10:45:00 AM | 2.0 | 1.0160 | 0.0030 | 25.7 | 1.0130 | 35.1 | 11.89 | 8.83341 | 0.01261248 | 0.0308 |
| | 10:48:00 AM | 5.0 | 1.0145 | 0.0030 | 25.7 | 1.0115 | 31.1 | 12.30 | 8.83341 | 0.01261248 | 0.0198 |
| | 10:58:00 AM | 15.0 | 1.0130 | 0.0030 | 25.6 | 1.0100 | 27.0 | 12.70 | 8.85306 | 0.0126265 | 0.0116 |
| | 11:13:00 AM | 30.0 | 1.0120 | 0.0030 | 25.7 | 1.0090 | 24.3 | 12.97 | 8.83341 | 0.01261248 | 0.0083 |
| | 11:43:00 AM | 60.0 | 1.0110 | 0.0030 | 25.6 | 1.0080 | 21.6 | 13.24 | 8.85306 | 0.0126265 | 0.0059 |
| | 2:53:00 PM | 250.0 | 1.0085 | 0.0030 | 25.8 | 1.0055 | 14.9 | 13.92 | 8.81384 | 0.0125985 | 0.0030 |
| 14-Apr-22 | 10:43:00 AM | 1440.0 | 1.0080 | 0.0030 | 20.7 | 1.0050 | 13.5 | 14.05 | 9.92007 | 0.01336576 | 0.0013 |

| L1 cm | Viscosity | | K (η/(Gs-1)) |
|-------|-----------|--|--------------|
| | C | | |
| 5.53 | -0.514053 | | 5.1961241 |
| 5.94 | -0.514053 | | 5.1961241 |
| 6.35 | -0.514053 | | 5.1961241 |
| 6.75 | -0.511832 | | 5.2076811 |
| 7.02 | -0.514053 | | 5.1961241 |
| 7.29 | -0.511832 | | 5.2076811 |
| 7.97 | -0.516271 | | 5.1846127 |
| 8.10 | -0.398036 | | 5.8353345 |

| | |
|-----------------------------|-------|
| Mass Retained on Sieve # 10 | 185.3 |
| Mass Passed Sieve # 10 | 326.6 |
| Jar Number | |

| Hygroscopic Data | Can Id | 55 |
|------------------|---------------------------|-------|
| | Empty Can Weight (g) | 13.33 |
| | Can+ Air Dried Soil (g) | 42.40 |
| | Can + Oven Dried Soil (g) | 42.21 |

UNIFIED SOIL CLASSIFICATION SYSTEM



GRAIN SIZE DISTRIBUTION CURVE (SIEVE AND HYDROMETER ANALYSIS)

| | | | | | | | | | | | | |
|--|---------------------|--|--------------|----------------|------------------|----------|------------|-------|----|-----|----|-----|
| AECOM CANADA LTD. 83 Galaxy Blvd, Unit 6 Toronto, Ontario | Client | AECOM | Date | April 12, 2022 | Project Number | 60634622 | Gravel (%) | 7 | | | | |
| | Sample ID | S1/MW SS7 | Depth (feet) | 0 | Project Name | DY3 | Sand (%) | 46 | | | | |
| | Lab Sample No: | 202204003S | | | Project Location | OTTAWA | Silt (%) | 33 | | | | |
| | Soil Classification | Silty Sand, some clay, trace gravel (SM) | | | | | Clay (%) | 14 | | | | |
| | Figure No. | | D10 | N/A | D30 | 0.018 | D60 | 0.226 | Cu | N/A | Cc | N/A |

Hydrometer Analysis

| | |
|----------------|------------|
| Lab No | 202204005S |
| Project Name | DYT3 |
| Project Number | 60634622 |
| Location | OTTAWA |

| | | | |
|---------------------|--|-------------|----------------|
| Borehole No | S2MW | Tested by | IP/SAM/DHARMIK |
| Sample Id | SS5 | Reviewed by | Ramana M |
| Depth (feet) | 10-12 | Date | 01-Apr-22 |
| Soil Classification | Lean Clay, trace sand, trace gravel (CL) | | |

| Soil Hydrometer Used | |
|----------------------|--------|
| 151 H SN# | 993585 |
| | 115105 |

| Soil Information | |
|--|---------|
| Liquid Limit (LL) | |
| Plasticity Index (PI) | |
| Specific Gravity of Soil (Gs) | 2.70 |
| Specific Gravity of Water (Gw) | 1 |
| Sg Correction Factor (α) | 0.989 |
| Total Mass of sample | 297.4 g |
| Soil Particles Greater Than This Are Excluded From Graph | 9.50 mm |

| Hydrometer Details | |
|--|-------------------------|
| Volume of Bulb (V _b) | 61.1 cm ³ |
| Length of Bulb (L _b) | 14.44 cm |
| Length from '1.0' reading to top of Bulb (L _s) | 10.17 cm |
| Scale Dimension (hs) | 0.27 cm/Div |
| Cross-sectional Area of Cylinder (A) | 28.3535 cm ² |
| Meniscus Correction (Hm) | 0.0005 Divisions |

| Calculation of Dry Soil Mass | |
|---|---------|
| Oven Dried Mass (W _o) | 22.18 g |
| Air Dried Mass (W _a) | 22.5 g |
| Hygroscopic Corr Factor (F) | 0.986 |
| Air Dried Mass in Analysis (M _a) | 50 g |
| Oven Dried Mass in Analysis (M _o) | 49.3 g |
| % Passing 2.0 mm Sieve (P ₁₀) | 98.4 |
| Sample Represented (W) | 50.1 g |

| Sieve Analysis of Retained on 2.0 mm Sieve (M2) | | | |
|---|-------------------------------|------------------|-----------|
| Sieve Size (mm) | Cummulative Mass Retained (g) | Mass Passing (g) | % Passing |
| 75.0 | | | |
| 63.0 | | | |
| 53.0 | | | |
| 37.5 | | | |
| 26.5 | | | |
| 19.0 | | | |
| 13.2 | | | |
| 9.5 | | | |
| 4.75 | 2.1 | 295.4 | 99.3 |
| 2.0 | 4.8 | 292.6 | 98.4 |

| Sieve Analysis of Hydrometer Material (M7) | | | |
|--|-------------------------------|------------------|-----------|
| Sieve Size (mm) | Cummulative Mass Retained (g) | Mass Passing (g) | % Passing |
| 2.00 | 0.0 | 49.3 | 98.4 |
| 0.850 | 0.4 | 48.9 | 97.6 |
| 0.425 | 0.7 | 48.6 | 97.0 |
| 0.25 | 1.2 | 48.1 | 96.1 |
| 0.106 | 2.4 | 46.9 | 93.6 |
| 0.075 | 4.2 | 45.1 | 90.0 |
| Pass 0.075 | 1.4 | | |

Percent In Suspension (P) as per Section 14.3 of ASTM D 422

$$P = [(100000/W) * (Gs/(Gs - Gw))] * (R - Gw) \text{ in percent (for Soil Hydrometer 151 H)}$$

Where R = Corrected Hydrometer Reading = Hs - Hc

Hs = Actual Hydrometer Reading
Hc = Composite Correction to be determined as per Section 7 of ASTM D 422

Diameter of Soil Particles (D) as per Section 15 of ASTM D 422

$$D = \text{SQRT of } \{[(30 * \eta) / (980 * (Gs - Gw))] * (L/T)\} \text{ in mm}$$

Where η = Viscosity of suspending Medium (Water) in poises
L = Effective Depth = L1 + 0.5 * [L₂ - V_b / A] in cm
L1 = distance from the top of the bulb to Recorded Hydrometer Reading in cm
T = Time in minutes

| Date | Time | Elapsed Time (minutes) | Hs in Divisions | Hc in Divisions | Temp Tc in C | R=Hs-Hc | P in % | L in cm | η in Poise | K | D in mm |
|----------|-------------|------------------------|-----------------|-----------------|--------------|---------|--------|---------|------------|------------|---------|
| 2-Apr-22 | 10:55:00 AM | 1.0 | 1.0290 | 0.0030 | 26.1 | 1.0260 | 82.4 | 8.57 | 8.75559 | 0.0125568 | 0.0368 |
| | 10:56:00 AM | 2.0 | 1.0280 | 0.0030 | 26.1 | 1.0250 | 79.3 | 8.84 | 8.75559 | 0.0125568 | 0.0264 |
| | 10:59:00 AM | 5.0 | 1.0265 | 0.0030 | 26.1 | 1.0235 | 74.5 | 9.25 | 8.75559 | 0.0125568 | 0.0171 |
| | 11:09:00 AM | 15.0 | 1.0250 | 0.0030 | 26.0 | 1.0220 | 69.8 | 9.65 | 8.77493 | 0.01257066 | 0.0101 |
| | 11:24:00 AM | 30.0 | 1.0240 | 0.0030 | 25.9 | 1.0210 | 66.6 | 9.92 | 8.79435 | 0.01258456 | 0.0072 |
| | 11:54:00 AM | 60.0 | 1.0230 | 0.0030 | 25.8 | 1.0200 | 63.4 | 10.19 | 8.81384 | 0.0125985 | 0.0052 |
| 3-Apr-22 | 3:04:00 PM | 250.0 | 1.0190 | 0.0030 | 25.7 | 1.0160 | 50.7 | 11.27 | 8.83341 | 0.01261248 | 0.0027 |
| | 10:54:00 AM | 1440.0 | 1.0160 | 0.0030 | 20.6 | 1.0130 | 41.2 | 12.08 | 9.94418 | 0.01338199 | 0.0012 |

| L1 cm | Viscosity | | K (η/(Gs-1)) |
|-------|-----------|--|--------------|
| | C | | |
| 2.43 | -0.522902 | | 5.1503494 |
| 2.70 | -0.522902 | | 5.1503494 |
| 3.11 | -0.522902 | | 5.1503494 |
| 3.51 | -0.520695 | | 5.1617255 |
| 3.78 | -0.518485 | | 5.1731466 |
| 4.05 | -0.516271 | | 5.1846127 |
| 5.13 | -0.514053 | | 5.1961241 |
| 5.94 | -0.395608 | | 5.8495155 |

| | |
|-----------------------------|-------|
| Mass Retained on Sieve # 10 | 76.3 |
| Mass Passed Sieve # 10 | 221.1 |
| Jar Number | |

| Hygroscopic Data | Can Id | 146 |
|------------------|---------------------------|-------|
| | Empty Can Weight (g) | 13.80 |
| | Can+ Air Dried Soil (g) | 36.30 |
| | Can + Oven Dried Soil (g) | 35.98 |

Hydrometer Analysis

| | |
|----------------|------------|
| Lab No | 202204006S |
| Project Name | DYT3 |
| Project Number | 60634622 |
| Location | OTTAWA |

| | | | |
|---------------------|----------------------------|-------------|----------------|
| Borehole No | S2MW | Tested by | IP/SAM/DHARMIK |
| Sample Id | TW1 SS1 | Reviewed by | Ramana M |
| Depth (feet) | | Date | 01-Apr-22 |
| Soil Classification | Lean Clay, trace sand (CL) | | |

| Soil Hydrometer Used | |
|----------------------|--------|
| 151 H SN# | 993585 |
| | 115105 |

| Soil Information | |
|--|---------|
| Liquid Limit (LL) | |
| Plasticity Index (PI) | |
| Specific Gravity of Soil (Gs) | 2.70 |
| Specific Gravity of Water (Gw) | 1 |
| Sg Correction Factor (α) | 0.989 |
| Total Mass of sample | 297.2 g |
| Soil Particles Greater Than This Are Excluded From Graph | 9.50 mm |

| Hydrometer Details | |
|--|-------------------------|
| Volume of Bulb (V _b) | 61.1 cm ³ |
| Length of Bulb (L _b) | 14.44 cm |
| Length from '1.0' reading to top of Bulb (L _s) | 10.17 cm |
| Scale Dimension (hs) | 0.27 cm/Div |
| Cross-sectional Area of Cylinder (A) | 28.3535 cm ² |
| Meniscus Correction (Hm) | 0.0005 Divisions |

| Calculation of Dry Soil Mass | |
|---|---------|
| Oven Dried Mass (W _o) | 18.58 g |
| Air Dried Mass (W _a) | 18.7 g |
| Hygroscopic Corr Factor (F) | 0.994 |
| Air Dried Mass in Analysis (M _a) | 50 g |
| Oven Dried Mass in Analysis (M _o) | 49.7 g |
| % Passing 2.0 mm Sieve (P ₁₀) | 100.0 |
| Sample Represented (W) | 49.7 g |

| Sieve Analysis of Retained on 2.0 mm Sieve (M2) | | | |
|---|-------------------------------|------------------|-----------|
| Sieve Size (mm) | Cummulative Mass Retained (g) | Mass Passing (g) | % Passing |
| 75.0 | | | |
| 63.0 | | | |
| 53.0 | | | |
| 37.5 | | | |
| 26.5 | | | |
| 19.0 | | | |
| 13.2 | | | |
| 9.5 | | | |
| 4.75 | 0.0 | 297.2 | 100.0 |
| 2.0 | 0.0 | 297.2 | 100.0 |

| Sieve Analysis of Hydrometer Material (M7) | | | |
|--|-------------------------------|------------------|-----------|
| Sieve Size (mm) | Cummulative Mass Retained (g) | Mass Passing (g) | % Passing |
| 2.00 | 0.0 | 49.7 | 100.0 |
| 0.850 | 0.1 | 49.6 | 99.9 |
| 0.425 | 0.1 | 49.6 | 99.8 |
| 0.25 | 0.1 | 49.5 | 99.7 |
| 0.106 | 0.2 | 49.5 | 99.6 |
| 0.075 | 0.3 | 49.4 | 99.5 |
| Pass 0.075 | 0.0 | | |

Percent In Suspension (P) as per Section 14.3 of ASTM D 422

$P = [(100000/W) * (Gs/(Gs - Gw))] * (R - Gw)$ in percent (for Soil Hydrometer 151 H)

Where R = Corrected Hydrometer Reading = Hs - Hc

Hs = Actual Hydrometer Reading
Hc = Composite Correction to be determined as per Section 7 of ASTM D 422

Diameter of Soil Particles (D) as per Section 15 of ASTM D 422

$D = \text{SQRT of } \{[(30 \cdot \eta) / (980 \cdot (Gs - Gw))] \cdot (L/T)\}$ in mm

Where η = Viscosity of suspending Medium (Water) in poises
L = Effective Depth = $L_1 + 0.5 \cdot [L_2 - V_b / A]$ in cm
L₁ = distance from the top of the bulb to Recorded Hydrometer Reading in cm
T = Time in minutes


| Date | Time | Elapsed Time (minutes) | Hs in Divisions | Hc in Divisions | Temp Tc in C | R=Hs-Hc | P in % | L in cm | η in Poise | K | D in mm |
|----------|-------------|------------------------|-----------------|-----------------|--------------|---------|--------|---------|------------|------------|---------|
| 2-Apr-22 | 11:30:00 AM | 1.0 | 1.0330 | 0.0030 | 21.9 | 1.0300 | 95.9 | 7.49 | 9.63853 | 0.01317473 | 0.0361 |
| | 11:31:00 AM | 2.0 | 1.0325 | 0.0030 | 21.9 | 1.0295 | 94.3 | 7.63 | 9.63853 | 0.01317473 | 0.0257 |
| | 11:34:00 AM | 5.0 | 1.0320 | 0.0030 | 21.9 | 1.0290 | 92.7 | 7.76 | 9.63853 | 0.01317473 | 0.0164 |
| | 11:44:00 AM | 15.0 | 1.0305 | 0.0030 | 21.9 | 1.0275 | 87.9 | 8.17 | 9.63853 | 0.01317473 | 0.0097 |
| | 11:59:00 AM | 30.0 | 1.0290 | 0.0030 | 21.8 | 1.0260 | 83.1 | 8.57 | 9.66145 | 0.01319039 | 0.0071 |
| | 12:29:00 PM | 60.0 | 1.0250 | 0.0030 | 21.8 | 1.0220 | 70.3 | 9.65 | 9.66145 | 0.01319039 | 0.0053 |
| | 3:39:00 PM | 250.0 | 1.0190 | 0.0030 | 21.7 | 1.0160 | 51.2 | 11.27 | 9.68448 | 0.01320609 | 0.0028 |
| 3-Apr-22 | 11:29:00 AM | 1440.0 | 1.0140 | 0.0030 | 20.1 | 1.0110 | 35.2 | 12.62 | 10.06625 | 0.01346388 | 0.0013 |

| L1 cm | Viscosity | |
|-------|-----------|--------------|
| | C | K (η/(Gs-1)) |
| 1.35 | -0.426827 | 5.6697227 |
| 1.49 | -0.426827 | 5.6697227 |
| 1.62 | -0.426827 | 5.6697227 |
| 2.03 | -0.426827 | 5.6697227 |
| 2.43 | -0.424451 | 5.6832087 |
| 3.51 | -0.424451 | 5.6832087 |
| 5.13 | -0.422071 | 5.696751 |
| 6.48 | -0.383407 | 5.9213247 |

| | |
|-----------------------------|-------|
| Mass Retained on Sieve # 10 | 0 |
| Mass Passed Sieve # 10 | 297.2 |
| Jar Number | |

| Hygroscopic Data | Can Id | 100 |
|------------------|---------------------------|-------|
| | Empty Can Weight (g) | 13.60 |
| | Can+ Air Dried Soil (g) | 32.30 |
| | Can + Oven Dried Soil (g) | 32.18 |

UNIFIED SOIL CLASSIFICATION SYSTEM



GRAIN SIZE DISTRIBUTION CURVE (SIEVE AND HYDROMETER ANALYSIS)

| | | | | | | | | | | | | | |
|--|---------------------|--|----------------------------|-----|--------------|---------------|------------------|----------------|----------|----------|------------|-----|--|
| <p>AECOM CANADA LTD. 83 Galaxy Blvd, Unit 6 Toronto, Ontario</p> | Client | | AECOM | | Date | April 1, 2022 | | Project Number | 60634622 | | Gravel (%) | 0 | |
| | Sample ID | | S2MW TW1 SS1 | | Depth (feet) | 0 | | Project Name | DYT3 | | Sand (%) | 1 | |
| | Lab Sample No: | | 202204006S | | | | Project Location | OTTAWA | | Silt (%) | 56 | | |
| | Soil Classification | | Lean Clay, trace sand (CL) | | | | | | | | Clay (%) | 43 | |
| | Figure No. | | D10 | N/A | | D30 | N/A | | D60 | 0.004 | Cu | N/A | |
| | | | | | | | | | | Cc | N/A | | |

| DETERMINATION OF UNIT WEIGHT - ASTM D7263 | | | | | | | | | | |
|---|--|------------------|-------------|-------------------------------|----------|----------|------------|----------|----------|--|
| Project Number | 60634622 | | Date Tested | 29-Mar-22 | | | Tested by | | | |
| Project Name | DYT3 | | Location | 2625 Sheffield Rd, Ottawa, ON | | | Checked by | Ramana M | | |
| Water Content | | | | | | | | | | |
| Test Info | Lab Number | 202204007S | | | | | | | | |
| | Borehole Name | S1-MW | | | | | | | | |
| | Sample ID | TW1 | | | | | | | | |
| | Depth | 78'(Bottom 20cm) | | | | | | | | |
| | Trial | A | B | A | B | A | B | A | B | |
| | Tare ID | 190 | 192 | | | | | | | |
| Mass in Grams | Tare Wt | 13.50 | 13.60 | | | | | | | |
| | Tare + Wet Soil | 51.40 | 45.60 | | | | | | | |
| | Tare + Dry Soil | 43.90 | 39.19 | | | | | | | |
| | Water | M _w | 7.50 | 6.41 | | | | | | |
| | Dry Soil | M _d | 30.40 | 25.59 | | | | | | |
| | Water Content % | w | 24.67 | 25.05 | | | | | | |
| Average % | | 24.86 | | | | | | | | |
| Weight- Volume Relations | | | | | | | | | | |
| Temp of water (C) | | 20 | 20 | | | | | | | |
| Density of Water | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | |
| Mass in Grams | Wet Soil | M _t | 147.32 | 169.82 | | | | | | |
| | Soil + Wax in Air | | 162.27 | 179.80 | | | | | | |
| | Wax | | 14.95 | 9.98 | | | | | | |
| | Wet Soil + Wax in water | | 73.79 | 85.63 | | | | | | |
| | Dry Soil ^A | M _d | 118.17 | 135.80 | | | | | | |
| Specific Gravity of Soil (assumed) | | G _s | 2.72 | 2.72 | | | | | | |
| Volume in CC | Wet Soil + Wax ^B | | 88.48 | 94.17 | | | | | | |
| | Wax | | 16.46 | 10.99 | | | | | | |
| | Wet Soil | V | 72.02 | 83.18 | | | | | | |
| | Dry Soil = M _d / G _s | V _s | 43.52 | 50.02 | | | | | | |
| KN/cum | Wet Unit Weight = (M _t /V)x9.81 | | 20.07 | 20.03 | | | | | | |
| | Average Wet Unit Weight | γ _m | 20.05 | | | | | | | |
| | Dry Unit Weight = (M _d /V)x9.81 | | 16.10 | 16.02 | | | | | | |
| | Average Dry Unit Weight | γ _d | 16.06 | | | | | | | |
| Void Ratio = (V-V _s)/V _s | | e | 0.65 | 0.66 | | | | | | |
| Porosity % = [(V-V _s)/V]x100 | | n | 39.56 | 39.87 | | | | | | |
| Degree of Saturation = [V _w /(V-V _s)] x100 | | S | 100.00 | 100.00 | | | | | | |

DETERMINATION OF SPECIFIC GRAVITY OF SOIL SOLIDS

| | | | | | | | | |
|--|-------------------------------|----------------|----------|--------------|-------------|----------|------------|--|
| Client | AECOM | Project Number | 60634622 | | Date | 4-Apr-22 | | |
| Project Name | DYT3 | | | | Done By | Ian P | | |
| Location | Ottawa | | | | Reviewed By | Ramana M | | |
| Borehole Number | S2/MW TW1 | Sample Id | SS7 | Depth (feet) | | Lab# | 202204006S | |
| Description | Formula | Trial 1 | Trial 2 | Trial 3 | Trial 4 | Trial 5 | Trial 6 | |
| Weight of Empty Density Bottle (g) W_1 | | 89.32 | 87.44 | 89.18 | | | | |
| Weight of Density Bottle + Dry Soil (g) W_2 | | 109.43 | 109.54 | 109.92 | | | | |
| Weight of Dry Soil W_s (g) | $W_0 = W_2 - W_1$ | 20.11 | 22.1 | 20.74 | | | | |
| Weight of Density Bottle + Water (g) W_4 | | 338.35 | 337.11 | 338.42 | | | | |
| Weight of Density Bottle + Soil + Water (g) W_3 | | 351.24 | 351.28 | 351.72 | | | | |
| Weight of Water Displaced (g) W_4 | $W_5 = \{(W_0 + W_4) - W_3\}$ | 7.22 | 7.93 | 7.44 | | | | |
| Specific Gravity of Soil Solids | $G_s = (W_0) / (W_5)$ | 2.785 | 2.787 | 2.788 | | | | |
| Average Specific Gravity at room temperature (G_T) | | 2.787 | | | | | | |

| Description | Formula | Data |
|---|---|----------|
| Room Temperature $T^{\circ}C$ | | 21.5 |
| Standard Temperature for Reporting Specific Gravity | | 20 |
| Relative Density of Water at Room Temperature γ_T | | 0.997913 |
| Relative Density of Water at Standard Temperature γ_{20} | | 0.998234 |
| Corrected Specific Gravity (G_{20}) | $G_{20} = G_T * (\gamma_T / \gamma_{20})$ | 2.786 |

k 0.999677931

One-Dimension Consolidation Test as per ASTM D2435-11

| | | | | | |
|------------------|--------------------------------------|--------|-----------------|-----------|--------------------|
| Lab Number | 2022040065 | | Date of Testing | 30-Mar-22 | |
| Project Num | 60634622 | Client | AECOM | Tested by | Ian / Dharmik/ Sam |
| Project Name | DYT3 Ottawa | | Reviewed by | Ramana M | |
| Project Location | 2625 Sheffield Road, Ottawa, Ontario | | | | |
| Sample Id | BHS2/MW TW 1 (SS7) | | Depth (feet) | 20-22 | |



| Grain Size Analysis Results | | | | | |
|-----------------------------|--------|--------|---------------|--------------------------------|----------------------------------|
| Gravel % | Sand % | Silt % | Clay % | Soil Type | |
| 0 | 1 | 56 | 43 | Lean Clay | |
| Atterberg's Limits | | | Other Results | | |
| LL % | PL % | PI % | SG | *** γ kN/m ³ | *** γ_d kN/m ³ |
| 30 | 19 | 11 | 2.787 | 1.947 | 1.486 |


Note: ** Assumed Values *** Before Testing

CONSOLIDATION TEST SUMMARY

| Initial Height of Specimen H_0 (mm) | | 1.91 | | Height of Solids H_s (cm) | | 0.896 | |
|---------------------------------------|---|-------------------------------|---------------------------------------|-----------------------------|-------------------------------|----------------|--|
| Load Increment | Axial Stress σ_a (lb/ft ²) | Axial Stress σ_a (kPa) | Corrected Deformation ΔH (cm) | Specimen Height H (cm) | Axial Strain ϵ_a (%) | Void Ratio e | |
| 1 | Seating Load | | 0.0000 | 1.9100 | 0 | 1.13 | |
| 2 | 125 | 11.97 | 0.2870 | 1.6230 | 15.0272251 | 0.81 | |
| 3 | 250 | 23.94 | 0.2997 | 1.6103 | 15.6921466 | 0.80 | |
| 4 | 500 | 47.88 | 0.3200 | 1.5900 | 16.7560209 | 0.78 | |
| 5 | 1000 | 95.76 | 0.3556 | 1.5544 | 18.617801 | 0.74 | |
| 6 | 2000 | 191.52 | 0.4216 | 1.4884 | 22.0753927 | 0.66 | |
| 7 | 4000 | 383.04 | 0.5334 | 1.3766 | 27.9267016 | 0.54 | |
| 8 | 8000 | 766.08 | 0.6096 | 1.3004 | 31.9162304 | 0.45 | |
| 9 | 16000 | 1532.16 | 0.6731 | 1.2369 | 35.2408377 | 0.38 | |
| 10 | 32000 | 3064.32 | 0.7341 | 1.1759 | 38.4324607 | 0.31 | |
| 11 | 8000 | 766.08 | -0.7163 | 1.1937 | -37.5015707 | 0.33 | |
| 12 | 2000 | 191.52 | -0.6960 | 1.2140 | -36.4376963 | 0.36 | |
| 13 | 500 | 47.88 | -0.6706 | 1.2394 | -35.1078534 | 0.38 | |
| 14 | 125 | 11.97 | -0.6528 | 1.2572 | -34.1769634 | 0.40 | |


Determination of Pre-Consolidation Pressure from e-log σ Curve


| Void Ratio e | Axial Stress σ_a (kPa) | Log of Axial Stress σ_a (kPa) |
|----------------|-------------------------------|--------------------------------------|
| 1.13 | 0 | #NUM! |
| 0.81 | 11.97 | 1.078094 |
| 0.80 | 23.94 | 1.379124 |
| 0.78 | 47.88 | 1.680154 |
| 0.74 | 95.76 | 1.981184 |
| 0.66 | 191.52 | 2.282214 |
| 0.54 | 383.04 | 2.583244 |
| 0.45 | 766.08 | 2.884274 |
| 0.38 | 1532.16 | 3.185304 |
| 0.31 | 3064.32 | 3.486334 |
| 0.33 | 766.08 | 2.884274 |
| 0.36 | 191.52 | 2.282214 |
| 0.38 | 47.88 | 1.680154 |
| 0.40 | 11.97 | 1.078094 |




| | |
|--------------------------------------|-------------------------------------|
| Coefficient of Compressibility C_c | Preconsolidation Pressure p_0 kPa |
| 0.3109 | 100 |

Appendix C Settlement Analysis



| | | | | | |
|---|----------------------|--|-------------------------|-------------------------------|-------------------------|
|  | Project | | | AMZL-DYT3 Settlement Analysis | |
| | Analysis Description | | | Total Settlement at 15 Years | |
| | Drawn By | | Jack Yu Guo | Company | AECOM Canada Ltd. |
| | Date | | 2022-04-12, 12:13:31 PM | File Name | Settlement_detailed.s3z |



| | | | |
|--|---|---|--|
| AECOM <small>SETTLE3 5.016</small> | Project AMZL-DYT3 Settlement Analysis | | |
| | Analysis Description Total Settlement at 15 Years (Lightweight Fill) | | |
| | Drawn By Jack Yu Guo | Company AECOM Canada Ltd. | |
| | Date 2022-11-22 | File Name Settlement_detailed_update_SLS.s3z | |