



SITE PLAN - PARKING GARAGE PHASE 1A

AP0601 Scale: 1: 250








SITE STATISTICS

Site Description:



PIN 04258-0401 (LT) Part of Lot 15, Concession Junction Gore Geographic

Registered Plan 5R-10411 City of Ottawa

Township of Gloucester Part 4 & 5

Parcel 12[370] F(1.5)

4 CHEO - 1DOOR4CARE REFERENCE IMAGE AP0601 Scale: 1:1	3 CHEO PARKING GARAGE CONCEPTUAL RENDERING AP0601 Scale: 1:1	2 KEY SITE PLAN AP0601 Scale: 1: 2500 APPROVED By Lily Yu at 4:30 pm, Oct 26, 2023
Principles 1:1	FRE ROUTE PASE PELESTRAL CONTROL SOFT MANY CONTRO	APPROVED By Lily Xu at 4:30 pm, Oct 26, 2023 LILY XU, MCIP, RPP MANAGER, DEVELOPMENT REVIEW SOUTH PLANNING, INFRASTRUCTURE & ECONOMIC DEVELOPMENT DEPARTMENT, CITY OF OTTAWA
PEGES ITAMI CHISONIO	SCANDE PRODUCE FROM REPER TO WAY-WING DIAWANGEST RING ROAD RING ROAD RING ROAD RING ROAD RING ROAD RING ROAD	PAILTINGS PAIL ALL ALL ALL ALL ALL ALL ALL ALL ALL A

0 asiana d	Parcel 12[3/0				
Assigned Address Zoning By-Law		401 Smyth Road, Ottawa ON. Ottawa Zoning By-law 2008-250		-0	
Zoning By-Law		Ottawa Zonin	g By-law 2008-23	50	
Zoning Category		I2-Major Institutional Zone	Wide range of uses including but not limited community health and resource centre, daycare, hospital, parking garage, residential care facility an school		
Proposed Use	Seven storey Parking Garage				
Definition: Parking Garage		Parking garage means a building used for the parking of four or more motor vehicles, but excludes a parking garage accessory to a detached, linked-detached, semidetached, or duplex dwelling. (garage de stationnement)			
Areas	Proposed Required				
Minimum Lot Width (m)		140 (Lot E)	No Min	No Minimum	
Minimum Lot Area (m2)		11000	No Min	imum	
Building Area (m2)		4807	-		
Parking		Proposed	Requir	ed	
Parking Garage Total		1050	-		
Accessible Parking (Min) Type A		12		11	
туре A Туре В		40	11	11	
Type C (CHEO Requirement)		42	-	-	
Motorcycle		6 -			
Bicycle Parking (Min)		To be Required /Provided by 1Door4Care Through Own Site Plan Application			
oading Spaces (Min)		To be Required /Provided by 1Door4Care Through Own Site Plan Application			
Electric Vehicle Charging Spots		20	20 -		
Site Coverage		Proposed	Requir	Required	
ot Coverage (Max)		44%	No Res	No Restriction	
% Landscape area (Min)		-	-	-	
Landscaped Buffer to Street (Min)		0%		3	
% Outdoor Storage % Utility Service Yard		0%		0%	
Floor Space Index		1.5 (Site Spec		1070	
Setbacks		Proposed Requir		ed	
Front Yard (m)		7.5 7.5			
Rear Yard (m)		Greater than 7.5 7.5			
Interior Side Yard (m)		N/A 7.5			
Exterior Side Yard (m)		7.5 7.5			
Height		Proposed	•	Required	
Max Principal Bldg. (m)		25.6m	R2 or R Other 0	Within 12m. of an R1, R2 or R3 zone - 15m Other Cases - No Maximum	
Parking Dim's		Proposed	-	Required	
Standard (m)		2.6m x 5.2m	-	2.6m x 5.2m	
Type A		3.4m x 5.2m		3.4m x 5.2m	
Туре В		2.4m x 5.2m	2.4m x	2.4m x 5.2m	
Туре С		2.4m x 5.2m		2.4m x 5.2m	
Motorcycle		1.3m x 3.0m		1.3m x 3.0m	
Loading Space Dim's		3.5m x 9.0m 0.6m x 1.8m		3.5m x 9.0m	
Bicycle Space Conservation Authority		υ.υιιι x 1.δM	X Mo.u	0.6m x 1.8m	
Rideau River Conservation Authority			Not a P	egulated Zone	
Notes			, Not a N	20 a. a. c. a. 2011C	
7.5m Front Yard Setback from CHEO pr 46m Front Yard Setback from OHSC Pro					
BUILDING AREA		Proposed (GFA	1	Total	
Existing (GFA) CHEO Main Facility	61,750	1Door4Care) Total		
Max Keeping Wing	4,000				
Ottawa Children's Treatment Centre	3,320				
Roger Nielson House	1,464				
Ronald McDonald House	1,210				
Subtotal	71,744		21,586	93,330	
Parking					
City of Ottawa Parking Requirments (Part 4, Sections 100-114) Provide 1.4 Parking Spaces per		Required	Provided Parking Garage 1050 1Door4Care 71		
100m2 of GFA			Existing Parking		
(Total GFA/100 SQm)*1.4 Parking Spac	es	1307		2150	
Accessible Parking					
Accessibility Design Standards (ADS) -	Required	Provided		Totals	
11+1% of total = 11+13 = 24		Parking Garage			
Type A	12	12	14	26	

Type C Spots are a CHEO Requirmnet for Parents & Caregivers with Children & Youth with As indicated City of Ottawa File No. D07-12-22-0170 City of Ottawa Plan No. 18912

401 Smyth Road, Ottawa ON

SITE PLAN

6 2023-10-13 ISSUED FOR SPC RESUBMISSION

5 2023-09-29 ISSUED FOR 50% CD SUBMISSION 4 2023-08-31 ISSUED FOR 100% DD SUBMISSION 3 2023-08-16 ISSUED FOR PERMIT - FOUNDATIONS

2 2023-08-16 ISSUED FOR SPC SUBMISSION

revisions

1 2023-07-31 ISSUED FOR 50% DD SUBMISSION 0 2023-04-20 ISSUED FOR TECHNICAL SUBMISSION

JASON CHANG
LICENCE
8092

1Door4Care: CHEO Integrated
Treatment Centre: Parking Garage

All drawing and specifications are the property of the architect. The contractor shall

verify all dimensions and information on site and report any discrepancy to architect before proceeding.

AP0601

2023-10-13

1Door4Care

Infrastructure Ontario

EllisDon

WALTERFEDY

INFRASTRUCTURE Healthcare

drawing number:

Property Boundary by: Annis, O'Sullivan, Vollebekk LTD. 14 Concourse Gate, Suite 500 Nepean, Ont. K2E 7S6

disabilities and are NOT REQUIRED per Ottawa Accessible Design Standards (ADS)

Total Parking spaces provided excluding CHEO requirmnent of Type C spots