3850 Cambrian Road Transportation Impact Assessment

Step 1 Screening Report
Step 2 Scoping Report
Step 3 Forecasting Report
Step 4 Strategy Report (Rev #1)

Prepared for:

Choice Properties Limited Partnership 700-22 St Clair Ave E Toronto ON, M4T 2S5

Prepared by:



6 Plaza Court Ottawa, ON K2H 7W1

October 2023

PN: 2022-066

Table of Contents

L		Screer	ning	1					
2			ng and Planned Conditions						
	2.1		posed Development						
	2.2	•	ring Conditions						
	2.2		Area Road Network						
	2.2	2.2	Existing Intersections						
	2.2	2.3	Existing Driveways						
	2.2	2.4	Cycling and Pedestrian Facilities						
	2.2	2.5	Existing Transit						
	2.2	2.6	Existing Area Traffic Management Measures						
	2.2	2.7	Existing Peak Hour Travel Demand						
	2.2	2.8	Collision Analysis						
	2.3	Plan	ned Conditions						
	2.3	3.1	Changes to the Area Transportation Network	9					
	2.3	3.2	Other Study Area Developments						
3		Study	Area and Time Periods						
	3.1	•	y Area						
	3.2	Time	Periods	11					
	3.3	Hori	zon Years	11					
1		Exemp	otion Review	11					
5		Develo	opment-Generated Travel Demand	12					
	5.1	Mod	le Shares	12					
	5.2	Trip	Generation	12					
	5.3	Trip	Distribution	14					
	5.4	Trip	Assignment	14					
ŝ		Backg	round Network Travel Demands	16					
	6.1	Tran	sportation Network Plans	16					
	6.2	Back	ground Growth	16					
	6.3	Othe	er Developments	17					
7		Dema	nd Rationalization	18					
	7.1	2024	4 Future Background Operations	. 18					
	7.2	2029	9 Future Background Operations	. 19					
	7.3	2024	4 Future Total Operations	. 21					
	7.4	2029	9 Future Total Operations	22					
	7.5	Mod	lal Share Sensitivity and Demand Rationalization Conclusions	. 24					
	7.5	5.1	Network Rationalization	. 24					
	7.5	5.2	Development Rationalization	. 24					
3		Develo	opment Design	. 24					
	8.1	Desi	gn for Sustainable Modes	. 24					
	8.2	Circu	ulation and Access	. 24					
9			g						
	9.1	Parking Supply							



10	Boundary Street Design	26
11	Access Intersections Design	26
11.1	Location and Design of Access	26
11.2	Intersection Control	27
11.3	Access Intersection Design	27
11	3.1 Future Access Intersection Operations	27
11	.3.2 Access Intersection MMLOS	
11	3.3 Recommended Design Elements	27
12	Transportation Demand Management	
12.1		
12.2	Need and Opportunity	27
12.3	TDM Program	27
13	Transit	27
13.1	Route Capacity	27
13.2	Transit Priority	28
14	Network Intersection Design	28
14.1	Network Intersection Control	28
14.2	Network Intersection Design	28
14	I.2.1 2024 & 2029 Future Total Network Intersection Operations	28
14	1.2.2 Network Intersection MMLOS	28
14	1.2.3 Recommended Design Elements	28
15	Summary of Improvements Indicated and Modifications Options	29
16	Conclusion	32
	of Figures	
•	1: Area Context Plan	
_	2: Concept Plan	
•	3: Study Area Pedestrian Facilities	
•	4: Study Area Cycling Facilities	
•	5: Existing Pedestrian Volumes	
_	6: Existing Cyclist Volumes	
_	7: Existing Study Area Transit Service	
	8: Existing Study Area Transit Stops - Within 400 metres	
_	9: Existing Traffic Counts	
_	10: Representation of Study Area Collision Records	
	11: New Site Generation Auto Volumes	
-	12: Pass-by Volumes	
_	13: New Site Generation, Pass-by, ana Diverted Trip – Beyond 2031 (informational only)	
-	14: 2024 Total Background Development Volumes	
-	15: 2029 Total Background Development Volumes	
_	16: 2024 Future Background Volumes	
-	17: 2029 Future Background Volumes	
rigure :	18: 2024 Future Total Volumes	21



Figure 19: 2029 Future Total Volumes	23
Table of Tables	
Table 1: Intersection Count Date	7
Table 2: Existing Intersection Operations	7
Table 3: Study Area Collision Summary, 2016-2020	8
Table 4: Summary of Collision Locations, 2016-2020	8
Table 5: Exemption Review	11
Table 6: TRANS Trip Generation Manual Recommended Mode Shares – South Nepean	12
Table 7: Trip Generation Person Trip Rates by Peak Hour	12
Table 8: Total Person Trip Generation by Peak Hour	13
Table 9: Trip Generation by Mode	13
Table 10: Local Barrhaven South Distribution	14
Table 11: Trip Assignment	14
Table 12: 2024 Future Background Intersection Operations	19
Table 13: 2029 Future Background Intersection Operations	20
Table 14: 2024 Future Total Intersection Operations	21
Table 15: 2029 Future Total Intersection Operations	23
Table 16: Boundary Street MMLOS Analysis	26
Table 17: Trip Generation by Transit Mode	27
Table 18: Study Area Intersection MMLOS Analysis	28

List of Appendices

Appendix A – TIA Screening Form and Certification Form

Appendix B – Turning Movement Count Data

Appendix C – Synchro Intersection Worksheets – Existing Conditions

Appendix D - Collision Data

Appendix E – Greenbank Road and South West Transitway Extension Preliminary Design

Appendix F – Background Development Volumes

Appendix G – Synchro Intersection Worksheets – 2024 Future Background Conditions

Appendix H – Signal Warrant Calculation Sheet

Appendix I – Synchro Intersection Worksheets – 2029 Future Background Conditions

Appendix J – Synchro Intersection Worksheets – 2024 Future Total Conditions

Appendix K – Synchro Intersection Worksheets – 2029 Future Total Conditions

Appendix L – Turning Templates

Appendix M – TDM Checklist

Appendix N – MMLOS Worksheets



1 Screening

This study has been prepared according to the City of Ottawa's 2017 Transportation Impact Assessment (TIA) Guidelines, prior to the June 2023 updates. Accordingly, a Step 1 Screening Form has been prepared and is included as Appendix A, along with the Certification Form for the TIA Study PM. As shown in the Screening Form, a TIA is required including the Design Review component and the Network Impact Component. This study has been prepared to support a site plan application.

2 Existing and Planned Conditions

2.1 Proposed Development

The existing site, located at 3850 Cambrian Road, is zoned as General Mixed Use Zone (GM[1628]). The proposed development consists of a gross floor area of 17,000 sq.ft pharmacy and gross leasable area of 18,781 sq.ft retail buildings. A total of 121 surface vehicle parking spaces and 18 surface bicycle parking spaces are proposed. The concept plan includes one new full-movement access on Cambrian Road in the interim condition. In the ultimate condition, two right-in/right-out accesses are proposed on Re-Aligned Greenbank Road corridor, and the access on Cambrian Road will be right-in/right-out. The ultimate condition is beyond the study horizon year and are not included in this report. The anticipated full build-out and occupancy horizon is 2024 with construction occurring in a single phase. The site is located within the Barrhaven South Community Design Plan area and Barrhaven South Community Core design priority area. Figure 1 illustrates the study area context. Figure 2 illustrates the proposed concept plan.





Figure 1: Area Context Plan

Source: http://maps.ottawa.ca/geoOttawa/ Accessed: July 28, 2022



Figure 2: Concept Plan



2.2 Existing Conditions

2.2.1 Area Road Network

Cambrian Road: Cambrian Road is a City of Ottawa arterial road. West of Seeley's Bay Street, it is two-lane rural cross-section with gravel shoulders present on both sides of the road East of Seeley's Bay Street, it is two-lane urban cross-section with sidewalks on both sides of the road. The posted speed limit is 50 km/h within the study area, and the City-protected right-of-way is 37.5 metres.

River Mist Road: River Mist Road is a City of Ottawa collector road with a two-lane urban cross-section. Sidewalks are presented on both sides of the road. The unposted speed limit is assumed to be 50 km/hr, and the measured right-of-way is approximately 24.0 metres.

Apolune Street: Apolune Street is a City of Ottawa collector road with a two-lane urban cross-section including on-street parking and sidewalks on both sides of the road. The unposted speed limit is assumed to be 50 km/h and the measured right-of-way is 24.0 metres.

2.2.2 Existing Intersections

The key existing intersections within one kilometre of the site have been summarized below:

Cambrian Road at River Mist Road The intersection of Cambrian Road at River Mist Road is an all-way

stop-controlled intersection. Each approach consists of a shared all-

movement lane. No turn restrictions were noted.

Cambrian Road at Apolune Street The intersection of Cambrian Road at Apolune Street is a T

intersection with stop-control on Apolune Street. The southbound approach consists of a shared left-turn/right-turn lane. The eastbound approach consists of an auxiliary left-turn lane and a through lane, and the westbound approach consists of a shared

through/right-turn lane. No turn restrictions are noted.

2.2.3 Existing Driveways

Construction accesses are located within 200 metres of the future site access intersections. As these are temporary or minor in nature and are not expected to provide access to significant traffic generators, they are not anticipated to have an impact on this TIA.


2.2.4 Cycling and Pedestrian Facilities

Figure 3 illustrates the pedestrian facilities in the study area and Figure 4 illustrates the cycling facilities.


Sidewalks are provided on both sides of Cambrian Road east of Seeley's Bay Street, River Mist Road, and Apolune Street. An approximate 760-metre sidewalk is provided on the north side of Cambrian Road west of Seeley's Bay Street. Paved shoulders are provided on both sides along Cambrian Road between Borrisokane Road and Cambrian Road at Apolune Street/Elevation Road.

In the ultimate cycling network, the Re-Aligned Greenbank Road will be a spine cycling route, and Cambrian Road, Apolune Street, and River Mist Road are local routes. South of Cambrian Road, Apolune Street will continue as Elevation Road, is a local route, and is anticipated to include multi-use pathways. The Transportation Master Plan Part 1 identifies Re-Aligned Greenbank Road for designation as a cross-town bikeway.





Source: http://maps.ottawa.ca/geoOttawa/ Accessed: July 28, 2022



Source: http://maps.ottawa.ca/geoOttawa/ Accessed: July 28, 2022

Pedestrian and cyclist volumes included in study area intersection counts, presented in Section 2.2.7, have been compiled and are illustrated in Figure 5 and Figure 6, respectively.



Cambrian


Cambrian

Cambrian

Sign of the state of the st

Figure 5: Existing Pedestrian Volumes





2.2.5 Existing Transit

Figure 7 illustrates the transit system map in the study area and Figure 8 illustrates nearby transit stops. All transit information is from June 7, 2022 and is included for general information purposes and context to the surrounding area.

Within the study area, route #75 travels along Cambrian Road and River Mist Road. The frequency of these routes within proximity of the proposed site based on June 7, 2022 service levels are:

 Route # 75 – 10-minute service in the peak period/direction and 15-minute service all-day, 30-minute service after 8 PM





Source: http://www.octranspo.com/ Accessed: June 7, 2022

Not in use
400 metres

white Add and the second of the sec

Figure 8: Existing Study Area Transit Stops - Within 400 metres

Source: http://www.octranspo.com/ Accessed: June 7, 2022

2.2.6 Existing Area Traffic Management Measures

There are no existing area traffic management measures within the study area.

2.2.7 Existing Peak Hour Travel Demand

Existing turning movement count at Cambrian Road at River Mist Road was acquired from the City of Ottawa, and existing turning movement count at Cambrian Road at Grand Canal Street was acquired from the Traffic Specialist. The turning movements at the Cambrian Road at Apolune Street intersection were derived from the first phases of the Half Moon Bay West CTS (Stantec, 2016). Table 1 summarizes the intersection count dates.



Table 1: Intersection Count Date

Intersection	Count Date	Source		
Cambrian Road at River Mist Road	Wednesday, October 23, 2019	City of Ottawa		
Cambrian Road at River Wist Road	Saturday, October 15, 2022	The Traffic Specialist		
Cambrian Dand at Analysis Street	-	Half Moon Bay West CTS (Stantec, 2016)		
Cambrian Road at Apolune Street	Saturday, October 15, 2022	The Traffic Specialist		

Figure 9 illustrates the existing traffic counts and Table 2 summarizes the existing intersection operations. Synchro 11 has been used to model the unsignalized intersections and HCM 2010 methodology was used for unsignalized intersection operation. Detailed turning movement count data is included in Appendix B and the Synchro worksheets are provided in Appendix C.

Figure 9: Existing Traffic Counts




Table 2: Existing Intersection Operations

			AM Pea	ak Hour			PM Pea	ak Hour			SAT Pe	ak Hour	
Intersection	Lane	LOS	V/C	Delay (s)	Q (95 th)	LOS	V/C	Delay (s)	Q (95 th)	LOS	V/C	Delay (s)	Q (95 th)
Cambrian	EB	С	0.71	23.1	43.5	С	0.76	25.0	53.3	В	0.49	13.0	20.3
Road at	WB	С	0.68	21.9	38.3	D	0.82	30.3	66.0	С	0.66	17.4	37.5
River Mist	NB	С	0.56	17.5	25.5	В	0.38	13.6	13.5	В	0.23	10.6	6.8
Road	SB	В	0.23	12.5	6.8	В	0.13	11.4	3.0	В	0.12	10.1	3.0
Unsignalized	Overall	С	-	20.3	-	С	-	24.7	-	В	-	14.5	-
Cambrian	EBL	Α	0.01	8.3	0.0	Α	0.03	8.4	0.8	Α	0.03	8.0	0.8
Road at	EBT	-	-	-	-	-	-	-	-	-	-	-	-
Apolune	WBT/R	-	-	-	-	-	-	-	-	-	-	-	-
Street	SBL/R	С	0.25	15.9	6.8	С	0.21	19.0	6.0	В	0.19	13.1	5.3
Unsignalized	Overall	Α	-	2.2	-	Α	-	1.6	-	Α	-	2.5	-

Notes: Saturation flow rate of 1800 veh/h/lane

Peak Hour Factor = 0.90 V/C = volume-to-capacity ratio Queue is measured in metres Delay = average vehicle delay in seconds

m = metered queue

= volume for the 95th %ile cycle exceeds capacity

During peak hours in the existing conditions, the study area intersections operate well. No capacity issues are noted.



2.2.8 Collision Analysis

Collision data have been acquired from the City of Ottawa open data website (data.ottawa.ca) for five years prior to the commencement of this TIA for the surrounding study area road network. Table 3 summarizes the collision types and conditions in the study area, Figure 10 illustrates the intersections and segments analyzed, and Table 4 summarizes the total collisions for each of these locations. Collision data are included in Appendix D.

Table 3: Study Area Collision Summary, 2016-2020 Number % **Total Collisions** 2 100% **Fatality** 0 0% Classification Non-Fatal Injury 1 50% **Property Damage Only** 1 50% 50% Angle 1 **Initial Impact Type SMV Other** 1 50% Dry 1 50% **Road Surface Condition Loose Snow** 1 50% **Pedestrian Involved** 0 0%

0 **Cyclists Involved** 0%

Figure 10: Representation of Study Area Collision Records



Table 4: Summary of Collision Locations, 2016-2020

	Number	%
Intersections / Segments	2	100%
Apolune St @ Cambrian Rd	1	50%
Cambrian Rd btwn Borrisokane Rd & Grand Canal St	1	50%

Within the study area, there are a total of two collisions during the 2016-2020 time period, with one involving property damage only and the remaining one having non-fatal injuries. No further collision review is required as part of this study.



2.3 Planned Conditions

2.3.1 Changes to the Area Transportation Network

The subject development is within the Barrhaven South Community Design Plan (CDP) Area. As such, it is subject to the planning polices outlined in the CDP. The CDP provides target population and employment densities in the four Sub-Planning Areas along with the plans for infrastructure to support the community growth. As part of this plan, the right-of-way along the following roads has been protected to accommodate an expansion to a four-lane arterial:

- Re-Aligned Greenbank Road rapid transit corridor north and south of Cambrian Road with a protected right-of-way of 41.5 metres
- Cambrian Road between Borrisokane Road and Longfields Road with a protected right-of-way of 37.5 metres

Realigned Greenbank Road will be located on the east side of the proposed development. The Re-Aligned Greenbank Road includes the design of a new 4-lane arterial roadway with 2-lane segregated median Bus Rapid Transit and facilities for pedestrians and cyclists between Marketplace Avenue/Chapman Mills Drive in the north and Barnsdale Road in the south. The preliminary design is included in Appendix E. The Re-Aligned Greenbank Road construction has not been scheduled and is assumed beyond 2031. Therefore, the Re-Aligned Greenbank Road is assumed to be after the study horizons and will not be modeled within the subject analyses.

Within the study horizons, a temporary road will be constructed on the south leg of the Cambrian Road at future Re-Aligned Greenbank Road intersection to serve as interim access for the future grocery site on the southeast quadrant of the intersection.

The westbound and southbound auxiliary left-turn lanes at the intersection of Cambrian Road at Apolune Street/Elevation Road have recently been painted. It is expected that an auxiliary left-turn lane will be on the northbound movement and the intersection is expected to be signalized within future horizons and will be included in the future horizons.

2.3.2 Other Study Area Developments

Mattamy's Half Moon Bay West Phase 3

The proposed subdivision is situated within the Mattamy Development of Half Moon Bay West, this phase of which is anticipated to be built-out during 2025. The development will include 38 detached single-family homes, 190 townhomes, and a 0.43-hectare commercial block. (CGH Transportation, 2021)

3555 Borrisokane Road

The proposed development includes a site plan application consisting of a car wash. It is anticipated to be built by 2023. This development forms a portion of the commercial block assessed within the Half Moon Bay West Phase 3 area. (D. J. Halpenny & Associates Ltd, 2022)

Glenview Homes (3387 Borrisokane Road)

The proposed development includes a plan of subdivision application consisting of 179 single family homes and 109 townhomes. It is anticipated to be built by 2023. (Stantec 2017)

OCSB Elementary School (135 Halyard Lane)

The proposed development application includes a site plan to have a single-storey elementary school with approximately 800 students and a 2,970 sq. ft of childcare centre. It is anticipated to be built by 2023. (Dillon Consulting, 2022)



Mattamy's Half Moon Bay West Phase 4

The proposed site is situated within the Mattamy Development of Half Moon Bay West, this phase of which is anticipated to be built-out during 2026. This phase of the development will include 59 detached single-family homes.

Minto's Kennedy (3432 Greenbank Road)

The proposed development includes a plan of subdivision application consisting of 523 units, including 103 single family homes, 274 executive townhomes, and 146 avenue townhomes, and is anticipated to be built by 2024. (CGH Transportation, 2022)

Loblaws Companies Ltd. (3845 Cambrian Road)

The proposed development includes a site plan application consisting of a 34,496 sq. ft. of grocery store and a 5,050 sq. ft. of retail store totaling 39,546 sq. ft. It is anticipated to be built by 2025. The file has been initiated and no TIA is available at this time.

Metro Ontario Inc. (3831 Cambrian Road)

The proposed development includes a site plan application consisting of a 4,024 sq. m supermarket, an attached 929 square metre retail store, an 830 square metre retail building, and a 1,060 sq. m mixed-use building. It is anticipated to be built by 2023. (CGH Transportation, 2021)

Meadow's Phase 7-8 (3640 Greenbank Road)

The proposed development, which was named Phase 5 in the TIA, includes a plan of subdivision application. The concept plan considers a total of 221 townhouses and 125 single family units. The full build-out and occupancy of Phase 7 is now assumed to be 2023 and Phase 8 by 2025. (IBI, 2018)

Mattamy's Half Moon Bay South Phase 5 (3718 Greenbank Road)

The proposed development application includes a plan of subdivision application consisting of 67 single detached home units and 97 townhouse units. This development is under construction and is assumed to be completed by the end of 2022. (CGH Transportation, 2019)

Mattamy's Half Moon Bay South Phase 7/8 (3718 Greenbank Road)

The proposed development, located on the west of the Re-Aligned Greenbank Road corridor and includes a mixture of 228 stacked townhouse units, and is anticipated to be built by 2024. (CGH Transportation, 2022)

Caivan's Ridge Phases 1-2 (3809 Borrisokane Road)

This development will include 279 townhouse units and 311 detached home units. This development is expected to be built-out during 2025. (CGH Transportation, 2019)

Caivan's The Ridge Phase 3-4 (3713 Borrisokane Road)

This development will include 589 townhouse units, 61 detached housing units. This development is expected to be built-out during 2024. (CGH Transportation, 2021)

Caivan's Conservancy East Stage (3285, 3288, 3305 Borrisokane Road)

This development will include 600 single family homes and 600 townhouses and 100 mid-rise dwelling units. This development is expected to be built-out during 2029. (CGH Transportation, 2021).

Minto's Quinn's Pointe Stages 4 (3882 Barnsdale Road and 3960 Greenbank Road)

The proposed development application includes a plan of subdivision application consists of 536 single-family dwelling units, 493 townhomes, 100 apartment units, and two elementary schools. Phases 2 and 3 have been completed, and Phase 4 is expected to be completed by 2025. (Stantec, 2018)



AIBC Manufacturing Site (3713 Borrisokane Road)

The site includes approximately 3,250 square metres of general office space and 9,385 sq. m of industrial buildings. This development began operations in 2022, and the office component will be completed by 2023. (CGH Transportation, 2020)

3 Study Area and Time Periods

3.1 Study Area

The study area will include the intersections of:

- Cambrian Road at:
 - o River Mist Road
 - Apolune Street
 - Site Access #1 (Future)

Future volumes at the ultimate access locations will be shown for the Re-Aligned Greenbank Road accesses and as they are outside the study horizons, will not be assessed from an operational perspective. This is informational only and are to be coordinated by the City through the Re-Aligned Greenbank design team.

The boundary road will be Cambrian Road and the preliminary design drawings will be used to assess the future Re-Aligned Greenbank Road. No screenlines are present within proximity to the site.

3.2 Time Periods

The weekday AM, PM and Saturday peak hours will be examined.

3.3 Horizon Years

The anticipated build-out year is 2024. As a result, the full build-out plus five years horizon year is 2029.

4 Exemption Review

Table 5 summarizes the exemptions for this TIA.

Table 5: Exemption Review

Module	Element	Explanation	Exempt/Required							
Design Review Component										
4.1 Development	4.1.2 Circulation and Access	Only required for site plans	Required							
Design	4.1.3 New Street Networks	Only required for plans of subdivision	Exempt							
	4.2.1 Parking Supply	Only required for site plans	Required							
4.2 Parking	4.2.2 Spillover Parking	Only required for site plans where parking supply is 15% below unconstrained demand	Exempt							
Network Impact Comp	onent									
4.5 Transportation Demand Management	All Elements	Not required for site plans expected to have fewer than 60 employees and/or students on location at any given time	Required							
4.6 Neighbourhood Traffic Management	4.6.1 Adjacent Neighbourhoods	Only required when the development relies on local or collector streets for access and	Exempt							



Module	Element	Explanation	Exempt/Required
		total volumes exceed ATM capacity thresholds	
4.8 Network Concept		Only required when proposed development generates more than 200 person-trips during the peak hour in excess of equivalent volume permitted by established zoning	Exempt

Development-Generated Travel Demand

5.1 Mode Shares

Examining the mode shares recommended in the TRANS Trip Generation Manual (2020) for the subject district, derived from the most recent National Capital Region Origin-Destination survey (OD Survey), the existing average district mode shares by land use for South Nepean have been summarized in Table 6. The PM peak hour mode shares were used for the Saturday peak hour. Given the daytime peak for Saturday and sidewalks connecting to adjacent residential developments, the closest residents to may tend use non-auto trips to the grocery store during the Saturday peak hour. A 2% of auto driver mode has been shifted to each of the cycling and walking modes for the Saturday peak hour.

Commercial Generator Travel Mode AM PM SAT 74% **Auto Driver** 61% 57% **Auto Passenger** 14% 27% 27% **Transit** 1% 1% 1% Cycling 0% 0% 2% Walking 11% 11% 12% 100% Total 100% 100%

Table 6: TRANS Trip Generation Manual Recommended Mode Shares – South Nepean

5.2 Trip Generation

This TIA has been prepared using the vehicle trip rates and derived person trip rates for commercial component from the ITE Trip Generation Manual 11th Edition using the City-prescribed conversion factor of 1.28. Table 7 summarizes the person trip rates for the non-residential land uses by peak hour.

Land Use Peak Vehicle Trip Person Trip Land Use Code Hour Rate Rates Pharmacy/Drugstore AM 2.94 3.76 880 without Drive-PM 8.51 10.89 (ITE) **Through Window** SAT 10.68 13.67 AM 2.36 3.02 822 Retail (<40k) PM 6.59 8.44 (ITE) SAT 6.57 8.41

Table 7: Trip Generation Person Trip Rates by Peak Hour

Using the above person trip rates, the total person trip generation has been estimated. Table 8 summarizes the total person trip generation for the non-residential land uses.



Table 8: Total Person Trip Generation by Peak Hour

Land Use	CEA/CLA	AN	Л Peak H	our	Р	M Peak H	lour	SAT Peak Hour			
Land Ose	GFA/GLA	In	Out	Total	In	Out	Total	In	Out	Total	
Pharmacy/Drugstore without Drive- Through Window	17,000 sq.ft	42	21	63	91	94	185	113	116	229	
Retail (<40k)	18,781 sq.ft	34	23	57	80	80	160	81	77	158	

It is noted that Internal capture rates from the ITE Trip Generation Handbook 3rd Edition only include development's retail component for mixed-use developments. Therefore, the internal capture rates for Retail (<40k) to/from Supermarket were assumed to be 5% for the AM peak hour and 15% for the PM peak hour.

Pass-by reductions of 53% and 40%, have been applied to AM and PM peak hours for the land use of Pharmacy/Drugstore without Drive-Through Window and retail (<40k), respectively, and pass-by reductions of 31% and 45% have been assumed for Saturday peak hour for the land use of Pharmacy/Drugstore without Drive-Through Window and retail (<40k).

Using the above mode share targets for the internal capture and pass-by rates, and the person trip rates, the person trips by mode have been projected. Table 9 summarizes the residential trip generation and the non-residential trip generation by mode and peak hour.

Table 9: Trip Generation by Mode

	l l	AM Pea	ak Hou	r	F	PM Pea	ak Hou	r	9	AT Pea	ak Hou	r	
Trav	el Mode	Mode Share	In	Out	Total	Mode Share	In	Out	Total	Mode Share	In	Out	Total
e gh	Auto Driver	74%	9	4	13	61%	8	7	15	57%	14	14	28
Pharmacy/Drugstore without Drive-Through Window	Auto Passenger	14%	6	3	9	27%	25	25	50	27%	31	32	63
acy/Dru; t Drive-T Window	Transit	1%	0	0	0	1%	1	1	2	1%	1	1	2
Cy Vin	Cycling	0%	0	0	0	0%	0	0	0	2%	2	2	4
ag # >	Walking	11%	5	2	7	11%	10	10	20	12%	14	14	28
har tho	Pass-by	53%	-22	-12	-34	53%	-48	-50	-98	45%	-51	-53	-104
₫ .≥	Total	100%	20	9	29	100%	44	43	87	100%	62	63	125
	Auto Driver	74%	10	7	17	61%	12	12	24	57%	17	16	33
	Auto Passenger	14%	5	3	8	27%	20	20	40	27%	20	19	39
⊗	Transit	1%	0	1	1	1%	1	1	2	1%	1	1	2
Retail (<40k)	Cycling	0%	0	0	0	0%	0	0	0	2%	1	1	2
i <u>e</u>	Walking	11%	4	2	6	11%	8	8	16	12%	9	8	17
Ret	Pass-by	40%	-14	-9	-23	40%	-32	-32	-64	31%	-25	-24	-49
	Internal Capture	5%	-1	-1	-2	15%	-7	-7	-14	15%	-8	-8	-16
	Total	100%	20	13	33	100%	41	41	82	100%	48	45	93
	Auto Driver	74%	19	11	30	61%	20	19	39	57%	31	30	61
_	Auto Passenger	14%	11	6	17	27%	45	45	90	27%	51	51	102
Total	Transit	1%	0	1	1	1%	2	2	4	1%	2	2	4
-	Cycling	0%	0	0	0	0%	0	0	0	2%	3	3	6
	Walking	11%	9	4	13	11%	18	18	36	12%	23	22	45
	Total	100%	39	22	61	100%	85	84	170	100%	110	108	218



As shown above, a total of 30 AM, 39 PM, and 61 Saturday new peak hour two-way vehicle trips are projected as a result of the proposed development.

5.3 Trip Distribution

Typically, the City's TRANS O-D distribution would be used to approximate the distribution of development traffic for employment and residential developments. As the proposed site is located here to serve the local community, it was felt that a site-specific distribution would be required to factor in the adjacent residential developments. As such, the local Barrhaven South distribution is summarized in Table 10.

Table 10: Local Barrhaven South Distribution

To/From	% of Trips
North	10%
South	30%
East	50%
West	10%
Total	100%

5.4 Trip Assignment

Using the distribution outlined above, turning movement splits, and access to major transportation infrastructure, the trips generated by the site have been assigned to the study area road network. Re-Aligned Greenbank Road will extend south of Cambrian Road to Barnsdale Road beyond 2031 and not within the horizons of this study.

To assist in the City's future planning, an assignment has been developed for this condition and has been supplied for informational purposes only. Any assessment of Re-Aligned Greenbank Road is a regional issue and unrelated to the planned right-in/right-out access arrangement.

Table 11 summarizes the proportional assignment to the study area roadways in the interim and ultimate conditions. Figure 11 and Figure 12 illustrate the new site generated volumes and pass-by volumes within the study horizons.

As noted above, Figure 13 illustrates the new site generated volumes once Re-Aligned Greenbank Road extends to the south, which will be beyond 2031. Since the ultimate condition is beyond the study horizon year, it will not be analysed in this TIA.

Table 11: Trip Assignment

To/From	Study Horizons	Beyond 2031 (informational only)
10/FIOIII	Via	Via
North	8% River Mist (N) 2% Apolune (N)	5% River Mist (N) 5% Re-Aligned Greenbank (N)
South	25% Elevation (S) 5% River Mist (S)	20% Re-Aligned Greenbank (S) 5% River Mist (S) 5% Elevation (S)
East	30% Cambrian (E) 20% River Mist (S)	30% Cambrian Rd (E) 20% River Mist (S)
West	3% Cambrian (W) 7% Apolune (N)	3% Cambrian (W) 7% Apolune (N)
Total	100%	100%




Site Access #1 ı 4(7)[11] 7(12)[19] ↑ 0(0)[0] ← 6(6)[9] 1(2)[3] 0(1)[1] 12(13)[20] 12(13)[20] 0(0)[0] 4 | 4 **₽** 0(0)[0] 4 | 4 3(5)[8] 0(0)[0] Cambrian 7(12)[19] 0(0)[0] Cambrian $\begin{array}{ccc}
1(2)[2] & \xrightarrow{1} \\
3(6)[9] & \xrightarrow{3(5)[8]} & \xrightarrow{1}
\end{array}$ 0(0)[0] ┑╽┍ 1 1 1 ^{7(7)[11]} → Temporary Driveway

00
00 -1(1)[1] 0(0)[0] $\overrightarrow{\neg}$ 0(0)[0] [8](5)5 00 00 River Mist

Figure 11: New Site Generation Auto Volumes










Figure 13: New Site Generation, Pass-by, and Diverted Trip – Beyond 2031 (informational only)

6 Background Network Travel Demands

6.1 Transportation Network Plans

The transportation network plans were discussed in Section 2.3. The signalized intersection of Cambrian Road at Apolune Street/Elevation Road, including the planned auxiliary lanes will be analyzed at all future horizons. Within the study horizons, a temporary road will be constructed on the south leg of the Cambrian Road at future Re-Aligned Greenbank Road intersection to serve as interim access for the future grocery site on the southeast quadrant of the intersection.

The Re-Aligned Greenbank Road was noted to be planned for implementation after the study horizons.

6.2 Background Growth

All background developments within Barrhaven South have been included in this TIA. All growth is assumed to be captured within the background development; therefore, no annual growth rate will be applied. Regional growth would be present on the north-south arterial network outside the study area intersections, such as Borrisokane Road, Greenbank Road and Longfields Drive.



6.3 Other Developments

The background developments explicitly considered in the background conditions (Section 6.2) include:

- Mattamy Half Moon Bay West Phases 3, 4
- 3555 Borrisokane Road
- Glenview Homes (3387 Borrisokane Road)
- OCSB Elementary School (135 Halyard Lane)
- Minto's Kennedy (3432 Greenbank Road) (2024 new site generated auto volumes)
- Loblaws (3845 Cambrian Road)
- Metro Ontario Inc. (3831 Cambrian Road)
- Meadow's Phase 7-8 (3640 Greenbank Road)
- Mattamy's Half Moon Bay South Phase 5 (3718 Greenbank Road)
- Mattamy's Half Moon Bay South Phase 7/8 (3718 Greenbank Road)
- Caivan's Ridge Phases 1-2 (3809 Borrisokane Road)
- Caivan's The Ridge Phase 3-4 (3713 Borrisokane Road)
- AIBC Manufacturing Site (3713 Borrisokane Road)
- Minto's Quinn's Pointe Stages 4 (3882 Barnsdale Road and 3960 Greenbank Road)
- Caivan's Conservancy East Stage (3285, 3288, 3305 Borrisokane Road)

Figure 14 and Figure 15 illustrate the 2024 and 2029 total background development volumes. The background development volumes within the study area have been provided in Appendix F.




Figure 14: 2024 Total Background Development Volumes






Figure 15: 2029 Total Background Development Volumes

7 Demand Rationalization

7.1 2024 Future Background Operations

The signalized intersection of Cambrian Road at Apolune Street/Elevation Road includes auxiliary left-turn lanes on all approaches. Figure 16 illustrates the 2024 background volumes and Table 12 summarizes the 2024 background intersection operations. Synchro 11 has been used to model the unsignalized intersections and HCM 2010 methodology was used for unsignalized intersection operation. The synchro worksheets for the 2024 future background horizon are provided in Appendix G.

Signal warrant analysis was performed for the intersection of Cambrian Road at River Mist Road and continues to not meet signal warrant. As the City does not have a planned improvement at this location, it is assumed to remain as an all-way stop-controlled intersection. Signal warrant calculation sheets are provided in Appendix H.




Figure 16: 2024 Future Background Volumes



Table 12: 2024 Future Background Intersection Operations

			AM Pe	ak Hour			PM Pe	ak Hour			SAT Pe	ak Hour	
Intersection	Lane	LOS	V/C	Delay (s)	Q (95 th)	LOS	V/C	Delay (s)	Q (95 th)	LOS	V/C	Delay (s)	Q (95 th)
Cambrian	EB	F	1.02	76.4	114.8	F	0.99	59.1	106.5	С	0.66	18.6	36.0
Road at	WB	Ε	0.89	44.1	71.3	F	1.01	66.8	115.5	D	0.80	26.8	60.0
River Mist	NB	D	0.70	26.5	39.0	С	0.47	16.7	18.0	В	0.31	12.4	9.8
Road	SB	С	0.32	15.6	9.8	В	0.18	13.0	4.5	В	0.15	11.2	3.8
Unsignalized	Overall	E	-	49.3	-	F	-	53.3	-	С	-	20.8	-
	EBL	Α	0.02	8.3	2.7	Α	0.06	5.2	5.4	Α	0.06	5.0	6.0
	EBT/R	Α	0.37	9.1	43.6	Α	0.49	7.7	86.5	Α	0.32	5.4	44.7
Cambrian	WBL	Α	0.05	8.2	6.1	Α	0.11	5.6	8.7	Α	0.14	5.6	10.4
Road at	WBT/R	Α	0.58	13.0	83.9	Α	0.45	7.4	70.6	Α	0.31	5.7	41.6
Apolune	NBL	В	0.63	32.9	35.0	В	0.70	67.0	48.8	В	0.70	67.4	46.7
Street	NBT/R	Α	0.08	0.2	0.0	Α	0.07	0.2	0.0	Α	0.25	13.0	11.7
Signalized	SBL	Α	0.54	30.0	27.1	Α	0.52	56.8	33.9	Α	0.46	55.0	28.7
	SBT/R	Α	0.05	0.2	0.0	Α	0.03	0.1	0.0	Α	0.19	14.4	10.4
	Overall	Α	0.59	15.6	-	Α	0.52	15.4	-	Α	0.38	16.0	-
Cambrian	EB	-	-	-	-	-	-	-	-	-	-	-	-
Road at	WB	Α	0.01	8.3	0.0	Α	0.01	8.6	0.0	Α	0.01	7.4	0.0
Temporary	NB	С	0.07	17.0	1.5	С	0.18	21.6	4.5	Α	0.06	9.6	1.5
Driveway <i>Unsignalized</i>	Overall	Α	_	0.4	_	Α	_	0.9	_	Α	_	2.3	_

Notes:

Saturation flow rate of 1800 veh/h/lane

Peak Hour Factor = 1.00 V/C = volume-to-capacity ratio Queue is measured in metres Delay = average vehicle delay in seconds

m = metered queue

= volume for the 95th %ile cycle exceeds capacity

The intersections of Cambrian Road at River Mist Road on the eastbound during AM and PM peak hours and westbound movement during the PM peak hour may experience high delays and extended queues due to the background development. The capacity issues are due to the background developments and are considered the responsibility of the City to address through DC funding.

7.2 2029 Future Background Operations

Figure 17 illustrates the 2029 background volumes and Table 13 summarizes the 2029 background intersection operations. Synchro 11 has been used to model the unsignalized intersections and HCM 2010 methodology was used for unsignalized intersection operation. The synchro worksheets for the 2029 future background horizon are provided in Appendix I.

Signal warrant analysis was performed for the intersection of Cambrian Road at River Mist Road and continues to not meet signal warrant. As the City does not have a planned improvement at this location, it is assumed to remain as an all-way stop-controlled intersection. Signal warrant calculation sheets are provided in Appendix H.



51(76)[82] 95(135)[117] 391(487)[469] 51(128)[74] 464(428)[286] 613(654)[205] 9(6)[7] 57(114)[128] 616(679)[533] 547(674)[477] 524(633)[154] _1 14(42)[46] 24(36)[21] 22(57)[66] - 109(106)[82] - 50(15)[10] - 194(130)[103] 256(460)[263] 129(255)[232] 507(494)[410] 270(193)[181] 117(88)[109] 6(9)[10] 15(38)[44] 93(162)[108] ¬ Temporary Driveway

Figure 17: 2029 Future Background Volumes

Table 13: 2029 Future Background Intersection Operations

			AM Pe	ak Hour			PM Pe	ak Hour			SAT Pe	ak Hour	
Intersection	Lane	LOS	V/C	Delay (s)	Q (95 th)	LOS	V/C	Delay (s)	Q (95 th)	LOS	V/C	Delay (s)	Q (95 th)
Cambrian	EB	F	1.28	164.9	193.5	F	1.23	126.5	177.0	Е	0.90	38.7	78.0
Road at	WB	F	1.09	77.3	102.8	F	1.25	133.4	182.3	F	1.03	74.3	129.0
River Mist	NB	D	0.82	34.1	48.0	С	0.56	19.1	21.0	В	0.40	15.0	13.5
Road	SB	С	0.36	17.6	10.5	В	0.20	14.2	5.3	В	0.18	12.7	4.5
Unsignalized	Overall	F	-	96.9	-	F	-	108.4	-	E	-	49.4	-
	EBL	Α	0.04	9.5	3.6	Α	0.09	7.5	8.2	Α	0.08	7.2	8.5
	EBT/R	Α	0.45	11.1	50.3	Α	0.60	11.9	133.0	Α	0.42	8.1	70.3
Cambrian	WBL	Α	0.12	9.9	9.8	Α	0.29	10.2	22.8	Α	0.30	9.9	24.9
Road at	WBT/R	В	0.67	17.2	#107.4	Α	0.52	10.8	98.9	Α	0.38	8.3	59.6
Apolune	NBL	С	0.77	38.0	52.0	С	0.78	65.9	63.7	С	0.76	65.5	60.4
Street	NBT/R	Α	0.14	0.4	0.0	Α	0.14	0.5	0.0	Α	0.32	9.5	13.9
Signalized	SBL	Α	0.59	29.6	34.3	Α	0.60	54.9	43.5	Α	0.55	53.6	37.4
	SBT/R	Α	0.07	0.2	0.0	Α	0.04	0.1	0.0	Α	0.18	11.5	10.2
	Overall	В	0.70	18.6	-	Α	0.64	19.1	-	Α	0.48	18.4	-
Cambrian	EB	-	-	-	-	-	-	-	-	-	-	-	-
Road at	WB	Α	0.01	8.6	0.0	Α	0.01	9.0	0.0	Α	0.01	7.7	0.0
Temporary	NB	С	0.08	20.3	2.3	D	0.25	29.7	6.8	В	0.09	11.2	2.3
Driveway Unsignalized	Overall	Α	-	0.4	-	A	-	1.0	-	Α	-	1.4	-

Notes:

Saturation flow rate of 1800 veh/h/lane

Peak Hour Factor = 1.00

V/C = volume-to-capacity ratio

Queue is measured in metres

Delay = average vehicle delay in seconds

m = metered queue

= volume for the 95th %ile cycle exceeds capacity

Capacity issues will remain at the intersection of Cambrian Road at River Mist Road, and on the westbound movement at the Cambrian Road at River Mist Road intersection may start to experience high delays and extended queues during the AM and Saturday peak hours due to the background developments. The capacity issues are due to the background developments and are considered the responsibility of the City to address through DC funding.



The westbound shared through/right-turn movement at the intersection of Cambrian Road at Apolune Street during the AM peak may be subject to extended queues at this horizon due to the background developments.

7.3 2024 Future Total Operations

Figure 18 illustrates the 2024 future total volumes and Table 14 summarizes the 2024 future total intersection operations. Synchro 11 has been used to model the unsignalized intersections and HCM 2010 methodology was used for unsignalized intersection operation. The synchro worksheets for the 2024 future total horizon are provided in Appendix J.

Signal warrant analysis was performed for the intersection of Cambrian Road at River Mist Road and continues to not meet signal warrant. As the City does not have a planned improvement at this location, it is assumed to remain as an all-way stop-controlled intersection. Signal warrant calculation sheets are provided in Appendix H.




Figure 18: 2024 Future Total Volumes



		AM Peak Hour					PM Pe	ak Hour		SAT Peak Hour				
Intersection	Lane	LOS	V/C	Delay (s)	Q (95 th)	LOS	V/C	Delay (s)	Q (95 th)	LOS	V/C	Delay (s)	Q (95 th)	
Cambrian	EB	F	1.05	85.5	123.0	F	1.01	60.5	108.0	С	0.70	21.1	43.5	
Road at	WB	Ε	0.92	48.5	75.8	F	1.03	74.1	124.5	D	0.83	31.4	69.0	
River Mist	NB	D	0.73	28.1	41.3	С	0.48	16.9	18.0	В	0.33	13.0	10.5	
Road	SB	С	0.33	16.0	10.5	В	0.18	13.1	4.5	В	0.16	11.5	4.5	
Unsignalized	Overall	F	-	54.5	-	F	-	56.7	-	С	-	23.8	-	
	EBL	Α	0.02	8.3	2.7	Α	0.06	5.2	5.4	Α	0.06	5.0	6.0	
	EBT/R	Α	0.37	9.1	43.9	Α	0.49	7.7	86.8	Α	0.33	5.4	44.7	
Cambrian	WBL	Α	0.06	8.2	6.6	Α	0.12	5.7	9.3	Α	0.15	5.7	11.5	
Road at	WBT/R	Α	0.58	13.1	84.1	Α	0.45	7.4	71.3	Α	0.32	5.7	42.3	
Apolune	NBL	В	0.63	32.9	35.0	В	0.70	67.0	48.8	В	0.70	67.4	46.7	
Street	NBT/R	Α	0.09	0.2	0.0	Α	0.08	0.3	0.0	Α	0.28	12.7	12.3	
Signalized	SBL	Α	0.55	30.4	27.6	Α	0.54	57.6	34.4	Α	0.48	56.1	29.9	
	SBT/R	Α	0.05	0.2	0.0	Α	0.03	0.1	0.0	Α	0.19	14.4	10.4	
	Overall	Α	0.59	15.6	-	Α	0.52	15.4	-	Α	0.38	16.0	-	



	Lane	AM Peak Hour					PM Pe	ak Hour		SAT Peak Hour			
Intersection		LOS	V/C	Delay (s)	Q (95 th)	LOS	V/C	Delay (s)	Q (95 th)	LOS	V/C	Delay (s)	Q (95 th)
Cambrian	EB	-	-	-	-	-	-	-	-	-	-	-	-
Road at	WB	Α	0.01	8.3	0.0	Α	0.01	8.7	0.0	Α	0.01	7.5	0.0
Temporary	NB	С	0.07	17.4	1.5	С	0.18	22.2	5.3	Α	0.07	9.8	1.5
Driveway Unsignalized	Overall	Α	-	0.4	-	Α	-	0.9	-	Α	-	2.0	-
Cambrian	EB	Α	0.02	8.6	0.0	Α	0.04	8.8	0.8	Α	0.04	8.4	0.8
Road at Site	WB	-	-	-	-	-	-	-	-	-	-	-	-
Access #1	SB	С	0.11	15.8	3.0	С	0.31	21.4	9.8	С	0.26	16.9	7.5
Unsignalized	Overall	Α	-	0.7	-	Α	-	1.9	-	Α	-	2.3	-

Saturation flow rate of 1800 veh/h/lane

Notes: Peak Hour Factor = 1.00

V/C = volume-to-capacity ratio Queue is measured in metres Delay = average vehicle delay in seconds

m = metered queue

= volume for the 95th %ile cycle exceeds capacity

The study area intersections will operate similar to the 2024 future background condition. No additional capacity issues are noted.

The site is anticipated to generate less than a 2.3% increase in traffic during the weekday peak hours and less than a 4.5% increase during the Saturday peak at Cambrian Road at the River Mist Road intersection. These volume increases are not considered significant impacts on the intersections and remain the responsibility of the City to address through DC funding.

7.4 2029 Future Total Operations

Figure 19 illustrates the 2029 total volumes and Table 15 summarizes the 2029 total intersection operations. Synchro 11 has been used to model the unsignalized intersections and HCM 2010 methodology was used for unsignalized intersection operation. The synchro worksheets for the 2029 future total horizon are provided in Appendix K.

Signal warrant analysis was performed for the intersection of Cambrian Road at River Mist Road and continues to not meet signal warrant. As the City does not have a planned improvement at this location, it is assumed to remain as an all-way stop-controlled intersection. Signal warrant calculation sheets are provided in Appendix H.



Figure 19: 2029 Future Total Volumes

Table 15: 2029 Future Total Intersection Operations

			AM P	eak Hou	r		PM Pe	ak Hour		SAT Peak Hour				
Intersection	Lane	LOS	V/C	Delay (s)	Q (95 th)	LOS	V/C	Delay (s)	Q (95 th)	LOS	V/C	Delay (s)	Q (95 th)	
Cambrian	EB	F	1.30	166.5	193.5	F	1.28	140.0	189.0	Е	0.94	45.0	87.0	
Road at	WB	F	1.11	83.5	108.0	F	1.28	142.7	189.8	F	1.06	85.3	140.3	
River Mist	NB	Е	0.84	35.6	50.3	С	0.58	19.8	22.5	С	0.42	15.6	14.3	
Road	SB	С	0.37	17.9	11.3	В	0.21	14.4	5.3	В	0.19	12.9	5.3	
Unsignalized	Overall	F	-	99.7	-	F	-	117.6	-	F	-	56.4	-	
	EBL	Α	0.04	9.5	3.6	Α	0.09	7.5	8.2	Α	0.08	7.2	8.5	
	EBT/R	Α	0.46	11.2	50.6	Α	0.60	11.9	133.3	Α	0.42	8.1	70.4	
Cambrian	WBL	Α	0.12	9.9	10.3	Α	0.31	10.4	23.9	Α	0.32	10.3	26.9	
Road at	WBT/R	В	0.67	17.3	#107.6	Α	0.53	10.9	99.8	Α	0.38	8.3	60.2	
Apolune	NBL	С	0.77	38.0	52.0	С	0.78	65.9	63.7	С	0.76	65.5	60.4	
Street	NBT/R	Α	0.15	0.4	0.0	Α	0.15	0.5	0.0	Α	0.34	9.3	14.2	
Signalized	SBL	Α	0.60	30.1	34.9	В	0.61	55.7	44.4	Α	0.59	55.9	39.0	
	NBT/R	Α	0.07	0.2	0.0	Α	0.04	0.1	0.0	Α	0.18	11.5	10.2	
	Overall	В	0.70	18.6	-	В	0.64	19.2	-	Α	0.48	18.6	-	
Cambrian	EB	-	-	-	-	-	-	-	-	-	-	-	-	
Road at	WB	Α	0.01	8.6	0.0	Α	0.01	9.1	0.0	Α	0.01	7.7	0.0	
Temporary	NB	С	0.08	20.8	2.3	D	0.25	30.8	7.5	В	0.09	11.6	2.3	
Driveway	Overall	Α	_	0.4	_	Α	_	1.1	_	Α	_	1.3	_	
Unsignalized	Overall		_	0.4	-	A	_	1.1	-	A		1.5	_	
Cambrian	EB	Α	0.02	8.8	0.8	Α	0.04	9.2	0.8	Α	0.05	8.7	0.8	
Road at Site	WB	-	-	-	-	-	-	-	-	-	-	-	-	
Access #1	SB	С	0.13	18.0	3.0	D	0.40	28.7	13.5	С	0.33	21.6	10.5	
Unsignalized	Overall	Α	-	0.7	-	Α	-	2.2	-	Α	-	2.4	-	

Saturation flow rate of 1800 veh/h/lane

Notes: Peak Hour Factor = 1.00 V/C = volume-to-capacity ratio Queue is measured in metres

Delay = average vehicle delay in seconds

m = metered queue

= volume for the 95th %ile cycle exceeds capacity



The Cambrian Road at River Mist Road intersection will operate similar to the 2029 future background condition. No additional capacity issues are noted. Compared to the 2024 future total condition, operational changes and increased queuing are similar to the changes between 2024 and 2029 future background conditions.

As outlined in the 2024 future total conditions, the site-generated volumes will have minimal impact the intersection of Cambrian Road at River Mist Road. The capacity issues are due to the background developments and are considered the responsibility of the City to address through DC funding.

7.5 Modal Share Sensitivity and Demand Rationalization Conclusions

7.5.1 Network Rationalization

The background conditions identify capacity constraints related to the intersection control at the Cambrian Road at River Mist Road intersection. Specifically, these are related to the eastbound movement during the AM and PM peak hours and westbound movement during the PM peak hour by 2024, and for the westbound movement during the AM and Saturday peak hours by 2029. These operational constraints are expected and have been reported previously in area TIAs that have assessed these intersections. The proposed site has minimal impact on the Cambrian Road volumes.

In the short term, motorist behavior may start to change to take alternative routes through the community to avoid these constraints. This has already been occurring with area diversions to Half Moon Bay at Greenbank Road where the City has addressed these diversions with a new mini-roundabout intersection.

Ultimately, the signalization of the intersection would be a local improvement for operations at this intersection, and more regional solution is the Re-Aligned Greenbank Road implementation south beyond Cambrian Road. The segment south of Cambrian Road would allow motorists to access the north-south arterial road network from east-west collections (e.g. Dundonald) rather than needing to use Cambrian Road for that connectivity.

Beyond the infrastructure noted, the subject site is a step towards mitigating the current vehicle trips headed to retail and grocery options north of the Jock River. It may not have a notable reduction on Cambrian Road at this time, but it likely has regional benefits that balance out the existence of the local constraints.

7.5.2 Development Rationalization

The proposed trip generation rates and modal shares are consistent with the surrounding area context and do not unduly impact the surrounding road network. No site specific demand rationalization is considered necessary as part of this TIA.

8 Development Design

8.1 Design for Sustainable Modes

The proposed development is a retail development with surface parking for both automobiles and bicycles. A total of 121 vehicle parking spaces and 18 bike parking spaces will be provided for the pharmacy and retails.

Future pedestrian and cycling facilities along Cambrian Road and future Greenbank Road are planned to be provided beyond the study horizon.

The infrastructure TDM checklist is provided in Appendix M.

8.2 Circulation and Access

Within the study horizon, Access #1 will accommodate vehicles accessing the site, and access will be all-movement access. The two-way access onto Cambrian Road is 9.0 metres wide, and the throat length is 13.0 metres, although



it is functionally longer with a total of 21.0 metres measured from the back of sidewalk to the first conflict point on-site. The internal drive aisles are 6.7 metres. The loading areas are provided at the back of Building A/B and between Buildings C and D. The delivery trucks and garbage collection vehicle turning templates were reviewed to confirm movements will be permitted on site, and the turning templates are provided in Appendix L.

Beyond 2031, Access #1 will become right-in/right-out with the new median as part of the Re-Aligned Greenbank Road and Cambrian Road signalized intersection when constructed by the City. Similarly, the right-in/right-out Accesses #2 and #3 will be opened with the Re-Aligned Greenbank Road construction. Access #2 width will be 7.6 metes and have an expected throat length of 14.5 metres, serving automobile movements, and Access #3 width will be 9.0 metres and have an expected throat length of 72.0 metres, serving as truck access for Building A/B. Actual throat lengths will be dependent on the City design for Cambrian Road and Re-Aligned Greenbank Road.

Access #1 is approximately 90 metres from the future Re-Aligned Greenbank Road and Cambrian Road intersection, which meets the minimum corner clearance of 70 metres from TAC (2017). On the south side of Cambrian Road, the 3845 Cambrian Road development has an access proposed approximately 30 metres to the east of Access #1. TAC notes that the relative location should be examined but provides no direct guidance on the desirable offset except in conditions with inter-development interaction is expected to be significant. The drive-way volumes are not considered to be significant and low inter-development interaction is expected. As further examination, the left-turn movements were modeled with Auto-Turn to show possible conflicts and are provided in Appendix L. General automobile and larger truck (garbage truck) movements will have no overlap in travel sweeps and can be completed without concern should they proceed at the same time. Truck/trailer (WB-20) vehicles would overlap should they proceed to make opposing left-turn movements at the same time. This situation is considered to be an exceedingly rare occurrence and would not be a typical design consideration at access locations. Overall, this condition can be permitted during the interim condition prior to Cambrian Road becoming a divided road as part of the Re-Aligned Greenbank Road construction, where no interaction between the access would be permitted.

Beyond 2031, Access #2 would be located within 55 metres of the future Re-Aligned Greenbank Road and Cambrian Road intersection, which is 15 metres shorter than a typical 70 metre clearance requirement, and within the left-tun storage length plus bay taper for the southbound movement. The right-in/right-out restrictions on the future access conditions necessitate accesses be provided on both Cambrian Road and Re-Aligned Greenbank Road. While the Cambrian Road frontage and future signalization at Re-Aligned Greenbank limit the ability to separate the loading access from the shopper entrance, Re-Aligned Greenbank Road would allow these movements to be separated. Overall, the proposed Access #2 location has been located as far away from the future signalized intersection as possible, given lot size, site design and tenant requirements, and is a typical condition that is experienced throughout the City of Ottawa.

The current design activities for Re-Aligned Greenbank Road will need their design to consider and be supportive of the surrounding land-use, either approved, in application, or planned through the Barrhaven South Community Design Plan and Barrhaven South Community Core Concept Plan and Design Framework.

Access #3 is located beyond the corner clearance requirement of left-tun storage length plus bay taper.

9 Parking

9.1 Parking Supply

The site provides a total of 121 vehicle surface parking spaces and 18 bicycle parking spaces. The minimum parking provision is 3.6 vehicle parking spaces per 100 m² of gross floor area and 1 bicycle per 250 m² of gross floor area,



which is 120 vehicle parking spaces and eight bicycle parking spaces, and the minimum vehicle and bicycle parking requirements are satisfied.

Based on the City of Ottawa Traffic and Parking (By-law No. 2017-301), the total number of accessible spaces required is two spaces. The site provides a total of four accessible parking spaces, and it meets the requirements.

10 Boundary Street Design

Table 16 summarizes the MMLOS analysis for the boundary streets of Cambrian Road. The boundary street analysis is based on the land use of the "General Urban Area" and the policy area of "Within 300 metres of a school". The MMLOS worksheets have been provided in Appendix N.

Table 16: Boundary Street MMLOS Analysis

Sagment	Pedestrian LOS		Bicycle LOS		Trans	it LOS	Truck LOS	
Segment	PLOS	Target	BLOS	Target	TLOS	Target	TrLOS	Target
Cambrian Road (Existing)	F	Α	F	В	N/A	N/A	N/A	N/A
Cambrian Road (Future)	С	Α	Α	В	N/A	N/A	N/A	N/A
Re-Aligned Greenbank Road (Future)	D	Α	Α	Α	Α	Α	Α	D

Cambrian Road does not meet the pedestrian MMLOS targets, and the operating speed would need to be lower than 30 km/h. Cambrian Road does not meet the bicycle MMLOS targets in the existing condition but will be met in the future condition.

No mitigation for the boundary street design of Cambrian Road is required as part of this application and require higher level City adjustments to the road operations, such as speed limits.

Future Re-Aligned Greenbank Road will not meet the pedestrian MMLOS target and needs at least 2 metre-wide of sidewalk and boulevard. The City's design team will need to rationalize the various elements and targets for the roadway.

11 Access Intersections Design

11.1 Location and Design of Access

The site is proposed to have a full-movement access (Access #1) within the study horizon years. Once the Re-Aligned Greenbank Road is built (Beyond 2031), right-in/right-out Access #2 and Access #3 will be provided along Re-Aligned Greenbank Road. The access along Cambrian Road is proposed to be 9.0 metres wide, while the future Access #2 is proposed to be 7.6 metres wide, and Access #3 is proposed to be 9.0 metres wide. All accesses widths meet the private approach by law.

The TAC Geometric Design Guidelines throat length requirements for a shopping if this size on an arterial road is 15.0 metres, as measured from the end of the corner radii. Access #1 will have a throat length of 13.0 metres once the future signalized intersection is constructed. This length is less than 15.0 metres primarily due to the larger radii required to support larger truck movements, and the actual space from the back of sidewalk to the first conflict point would be approximately 21.0 metres. This is similar to the future conditions at Access #2 where the length from the radii is 14.5 metres while the actual space is 20.6 metres. Access #3 does meet the 15.0 metre requirements.

Overall, no concerns are noted with the proposed configurations and are considered to meet the intentions of TAC in function and future operations.



11.2 Intersection Control

Based upon the projected volumes, the site access will have stop-control on the minor approach.

11.3 Access Intersection Design

11.3.1 Future Access Intersection Operations

The operations are noted in Section 7.4 and both 2024 and 2029 future total access intersections operate well with all movements and the overall intersection operating at LOS A.

11.3.2 Access Intersection MMLOS

Based upon the projected volumes, the site access will have stop-control on the minor approach.

11.3.3 Recommended Design Elements

No changes to the site access are proposed.

12 Transportation Demand Management

12.1 Context for TDM

The mode shares used within the TIA represent the unmodified district shares for the Barrhaven South. A shift from auto modes to transit modes, in both the subject and surrounding developments, may be anticipated once the BRT network is extended along the Re-Aligned Greenbank Road Corridor, but any such shifts are expected to occur outside of the analysis horizons of this report. Overall, the modal shares are likely to be achieved and supporting TDM measures should be provided.

The subject site is within the Barrhaven South Community Core design priority area.

12.2 Need and Opportunity

The subject site has been assumed to rely predominantly on auto travel and those assumptions have been carried through the analysis.

12.3 TDM Program

The "suite of post occupancy TDM measures" has been summarized in the TDM checklists for the non-residential land uses. The checklist is provided in Appendix M. The key TDM measures recommended include:

Provide a multimodal travel option package to new/relocating employees

In addition to these measures, providing more than the minimum bicycle parking required, will help in achieving the mode shares for the proposed development and is recommended.

13 Transit

13.1 Route Capacity

In Section 5.1 the trip generation by mode was estimated, including an estimate of the number of transit trips that will be generated by the proposed development. Table 17 summarizes the transit trip generation.

Table 17: Trip Generation by Transit Mode

Travel	Mode	AN	/I Peak Ho	our	PN	Л Peak Ho	ur	SAT Peak Hour			
Mode	Share	In	In Out		In Out Tota			In Out		Total	
Transit	1%	0	1	1	2	2	4	2	2	4	



The proposed development is anticipated to generate an additional 1 AM, 4 PM, and 4 Saturday peak hour two-way transit trips. Overall, the existing transit service is expected to be accommodate these increased riders and be predominantly localized trips within Barrhaven South.

13.2 Transit Priority

Examining the study area intersection delays, negligible impacts are noted on the transit movements and no decrease in transit LOS at the study area intersections are noted as a result of forecasted site-generated traffic. It is expected that the local transit service may be reconfigured or improved by the City once the Re-Aligned Greenbank Road and Cambrian Road widening are completed, and it is outside of the study horizons.

14 Network Intersection Design

14.1 Network Intersection Control

No change to the existing signalized control is recommended for the network intersections.

14.2 Network Intersection Design

14.2.1 2024 & 2029 Future Total Network Intersection Operations

The operations are noted in Section 7.4 and no changes on the intersections within the study area are required.

14.2.2 Network Intersection MMLOS

Table 18 summarizes the MMLOS analysis for the intersection of Cambrian Road at Apolune Street/Elevation Road. The existing intersection is not signalized and therefore only the future conditions will be analyzed. The future intersection geometry is assumed to be the same as the functional design completed by Stantec without cycling infrastructure along the Cambrian Road within the study horizon years. The intersection analysis is based on the land use of "General Urban Area" and the policy area of "Within 300 metres of a school". The MMLOS worksheets have been provided in Appendix N.

Pedestrian LOS Bicycle LOS Transit LOS Truck LOS Auto LOS Intersection **PLOS Target BLOS** Target **TLOS** Target TrLOS Target **ALOS Target Cambrian Rd at** E N/A N/A N/A D Apolune St / Α Ε В N/A В **Elevation Rd**

Table 18: Study Area Intersection MMLOS Analysis

The MMLOS targets will not meet for the pedestrian and bicycle LOS in the future condition within the study horizon years at the intersection of Cambrian Road at Apolune Street/Elevation Road. The pedestrian level of service would require crossing distances of a maximum of two lane-widths per crossing and protected left-turn on each approach to meet a LOS A. The left-turn configurations would need to be two-stage or include turn boxes on each approach to meet the bicycle LOS target. The City will be responsible for exploring options to address the area PLOS and BLOS deficiencies for this intersection.

The MMLOS review for the Re-Aligned Greenbank Road is considered a responsibility of the City and their current design exercise. As they are currently working through this design, any review within this study would be premature.

14.2.3 Recommended Design Elements

No study area intersection design elements are proposed as part of this study.



15 Summary of Improvements Indicated and Modifications Options

The following summarizes the analysis and results presented in this TIA report:

Proposed Site and Screening

- The proposed site includes a gross floor area of 17,000 sq.ft pharmacy and gross leasable area of 18,781 sq.ft retail buildings
- A total of 121 surface vehicle parking spaces and 18 surface bicycle parking spaces are proposed
- The concept plan includes one new full-movement access on Cambrian Road in the interim condition
- In the ultimate condition, two right-in/right-out accesses are proposed on Re-Aligned Greenbank Road corridor, and the access on Cambrian Road will be right-in/right-out
- The ultimate condition is beyond the study horizon year, and would not be included in this report
- The development is proposed to be completed as a single phase by 2024
- The trip generation and location triggers were met for the TIA Screening

Existing Conditions

- Cambrian Road is an arterial road, and River Mist Road and Apolune Street are collector roads in the study
- Sidewalks are provided on both sides of Cambrian Road east of Seeley's Bay Street, River Mist Road, and Apolune Street
- Paved shoulders are provided on both sides along Cambrian Road between Borrisokane Road and Cambrian Road at Apolune Street/Elevation Road
- Re-Aligned Greenbank Road will be a spine cycling route, and Cambrian Road, Apolune Street, and River
 Mist Road are local route
- The Transportation Master Plan Part 1 identifies Re-Aligned Greenbank Road for designation as a cross-town bikeway
- Within the study area, there are a total of two collisions during the 2016-2020 time period, and no further collision review is required as part of this study
- During peak hours in the existing conditions, the study area intersections operate well

Development Generated Travel Demand

- The proposed development is forecasted produce 61 AM, 170 PM, and 218 Saturday new peak hour people trips
- Of the forecasted people trips, a total of 30 AM, 39 PM, and 61 Saturday new peak hour two-way vehicle trips are projected as a result of the proposed development
- Of the forecasted trips, 10 % are anticipated to travel both the north and west, 30 % to the south, and 50 % to the east
- The proposed trip generation rates and modal shares are consistent with the surrounding area context and do not unduly impact the surrounding road network

Background Conditions

- The signalized intersection of Cambrian Road at Apolune Street/Elevation Road, including the planned auxiliary lanes will be analyzed at all future horizons
- All growth is assumed to be captured within the background development; therefore, no annual growth rate will be applied



- Within the study horizons, a temporary road will be constructed on the south leg of the Cambrian Road
 at future Re-Aligned Greenbank Road intersection to serve as interim access for the future grocery site on
 the southeast quadrant of the intersection
- The background conditions identify capacity constraints related to the intersection control at the Cambrian Road at River Mist Road intersection
- The capacity issues are due to the background developments and are considered the responsibility of the City to address through DC funding
- In the short term, motorist behavior may start to change to take alternative routes through the community to avoid these constraints
- Ultimately, the signalization of the intersections would be a local improvement for operations at these intersections, and more regional solution is the Re-Aligned Greenbank Road implementation south beyond Cambrian Road

Development Design

- The proposed development is a retail development with surface parking for both automobiles and bicycles
- Future pedestrian and cycling facilities along Cambrian Road and future Greenbank Road are planned to be provided beyond the study horizon
- Two loading zones are provided within the development
- The delivery trucks and garbage collection vehicle turning templates were reviewed to confirm movements will be permitted on site
- Access #1 is approximately 90 metres from the future Re-Aligned Greenbank Road and Cambrian Road intersection, which meets the minimum corner clearance of 70 metres from TAC (2017)
- Access #2 would be located within 55 metres of the future Re-Aligned Greenbank Road and Cambrian Road intersection, which is 15 metres shorter than a typical 70 metre clearance requirement, and within the left-tun storage length plus bay taper for the southbound movement
- The proposed Access #2 location has been located as far away from the future signalized intersection as possible, given lot size, site design and tenant requirements, and is a typical condition that is experienced throughout the City of Ottawa
- Access #3 is located beyond the corner clearance requirement of left-tun storage length plus bay taper
- On the south side of Cambrian Road, the 3845 Cambrian Road development has an access proposed approximately 30 metres to the east of Access #1, and general automobile and larger truck (garbage truck) movements will have no overlap in travel sweeps

Parking

- The site provides a total of 121 vehicle surface parking spaces and 18 bicycle parking spaces
- The minimum vehicle and bicycle parking requirements are satisfied
- The minimum accessible parking requirement is satisfied

Boundary Street Design

- Cambrian Road does not meet the pedestrian MMLOS targets and needs less than 30 km/h operating speed
- Cambrian Road does not meet the bicycle MMLOS targets in the existing condition but will be met in the future condition



- No mitigation for the boundary street design of Cambrian Road is required as part of this application and require higher level City adjustments to the road operations, such as speed limits
- Future Re-Aligned Greenbank Road will not meet the pedestrian MMLOS target and needs at least 2 metre-wide of sidewalk and boulevard, and should be rationalized through the City's design team

Access Intersections Design

- The site accesses are proposed to be 9.0-metres-wide and operate with minor approach stop-controlled
- Once the Re-Aligned Greenbank Road is constructed by the City, the Access #2 and Access # 3 can be
 opened and both accesses will operate as right-in/right-out
- Access #2 will be for automobile movements and access #3 will predominantly be the truck access for Building A/B
- The throat length requirement of 15.0 metres, per TAC, will not be strictly met at Access #1 and Access #2
- The curb radii required at the accesses overlap with the throat length area, where a total distance from the back of sidewalk is approximately 21.0 metres for Access #1 and 20.6 metres for Access #2
- Given the available distance between the roadway sidewalk and the first conflict point internal to the site
 are greater than 15.0 metres, are considered to meet the intentions of TAC in function and future
 operations
- No concerns are noted with the proposed configurations and are considered to meet the intentions of TAC in function and future operations
- The 2024 and 2029 future total access intersections operate well with all movements and the overall intersection operating at LOS A
- No additional design elements are proposed

TDM

- Supportive TDM measures to be included within the proposed development should include:
 - o Provide a multimodal travel option package to new/relocating employees
- Providing more than the minimum bicycle parking required will help in achieving the mode shares for the proposed development and is recommended

Transit

- The proposed development is anticipated to generate an additional 1 AM, 4 PM and 4 Saturday peak hour two-way transit trips
- The existing transit service is expected to be accommodate these increased riders and be predominantly localized trips within Barrhaven South
- Negligible impacts are noted on the transit movements and no decrease in transit LOS at the study area intersections are noted as a result of forecasted site-generated traffic
- It is expected that the local transit service may be reconfigured or improved by the City once the Re-Aligned Greenbank Road and Cambrian Road widening are completed, and it is outside of the study horizons

Network Intersection Design

- The capacity issues are due to the background developments and are considered the responsibility of the
 City to address through DC funding
- No changes on the intersections within the study area are required
- No change to the existing signalized control is recommended for the network intersections



- The MMLOS targets will not be met the pedestrian and bicycle LOS at the intersections of Cambrian Road at Apolune Street/Elevation Road in the future conditions within the study horizon years
- Cambrian Road at Apolune Street/Elevation Road would require crossing distances of a maximum of two lane-widths per crossing and protected left-turn on each approach to meet the PLOS at this intersection
- Cambrian Road at Apolune Street/Elevation Road would require improved left-turn configurations on each approach to meet the BLOS at this intersection
- The City will be responsible for exploring options to address the area PLOS and BLOS deficiencies for Cambrian Road at Apolune Street/Elevation Road
- The MMLOS review for the Re-Aligned Greenbank Road is considered a responsibility of the City and their current design exercise. As they are currently working through this design, any review within this study would be premature

16 Conclusion

It is recommended that, from a transportation perspective, the proposed development applications proceed.

Prepared By:

Reviewed By:

JulhiChan

Yu-Chu Chen, EIT Transportation Engineering-Intern A. J. HARTE 100149314
October 11, 2023

Andrew Harte, P.Eng. Senior Transportation Engineer



Appendix A

TIA Screening Form and PM Certification Form





City of Ottawa 2017 TIA Guidelines Step 1 - Screening Form Date: 06-Jul-22
Project Number: 2022-066
Project Reference: 3850 Cambrian

1.1 Description of Proposed Development	
Municipal Address	3850 Cambrian Road
Description of Location	Ward 3. 1.28 ha of rectangular parcel
Land Use Classification	General Mixed-Use Zone (GM[1628])
Development Size	Retail blocks totaling 36,748 sq ft
A 0000000	An access onto Cambrian Road, future access to Re-
Accesses	Aligned Greenbank Road
Phase of Development	Single
Buildout Year	2025
TIA Requirement	Full TIA Required

1.2 Trip Generation Trigger	
Land Use Type	Destination retail
Development Size	3,414 G.F.A.
Trip Generation Trigger	Yes

1.3 Location Triggers		
Does the development propose a new driveway to a boundary street that is		
designated as part of the City's Transit Priority, Rapid Transit or Spine	Yes	
Bicycle Networks?		Future access
Is the development in a Design Priority Area (DPA) or Transit-oriented	Yes	Barrhaven South Community
Development (TOD) zone?	res	Core Design Priority Area
Location Trigger	Yes	

1.4. Safety Triggers		
Are posted speed limits on a boundary street 80 km/hr or greater?	No	
Are there any horizontal/vertical curvatures on a boundary street limits sight lines at a proposed driveway?	No	
Is the proposed driveway within the area of influence of an adjacent traffic signal or roundabout (i.e. within 300 m of intersection in rural conditions, or within 150 m of intersection in urban/ suburban conditions)?	No	Future Re-Aligned Greenbank Road and Cambrian Road will be within 150m
Is the proposed driveway within auxiliary lanes of an intersection?	No	Future Re-Aligned Greenbank Road and Cambrian Road will have medians.
Does the proposed driveway make use of an existing median break that serves an existing site?	No	
Is there is a documented history of traffic operations or safety concerns on the boundary streets within 500 m of the development?	No	
Does the development include a drive-thru facility?	No	
Safety Trigger	No	



TIA Plan Reports

On 14 June 2017, the Council of the City of Ottawa adopted new Transportation Impact Assessment (TIA) Guidelines. In adopting the guidelines, Council established a requirement for those preparing and delivering transportation impact assessments and reports to sign a letter of certification.

Individuals submitting TIA reports will be responsible for all aspects of development-related transportation assessment and reporting, and undertaking such work, in accordance and compliance with the City of Ottawa's Official Plan, the Transportation Master Plan and the Transportation Impact Assessment (2017) Guidelines.

By submitting the attached TIA report (and any associated documents) and signing this document, the individual acknowledges that s/he meets the four criteria listed below.

CERTIFICATION

- 1. I have reviewed and have a sound understanding of the objectives, needs and requirements of the City of Ottawa's Official Plan, Transportation Master Plan and the Transportation Impact Assessment (2017) Guidelines;
- 2. I have a sound knowledge of industry standard practice with respect to the preparation of transportation impact assessment reports, including multi modal level of service review;
- 3. I have substantial experience (more than 5 years) in undertaking and delivering transportation impact studies (analysis, reporting and geometric design) with strong background knowledge in transportation planning, engineering or traffic operations; and
- 4. I am either a licensed¹ or registered² professional in good standing, whose field of expertise [check $\sqrt{\text{appropriate field(s)}}$] is either transportation engineering $\sqrt{\text{or}}$ or transportation planning \square .
- License of registration body that oversees the profession is required to have a code of conduct and ethics guidelines that will ensure appropriate conduct and representation for transportation planning and/or transportation engineering works.

Dated at Ottawa (City)	this 20 day of September	, 2018
Name:	Andrew Harte (Please Print)	
Professional Title:	Professional Engineer	
Signature	of Individual certifier that s/he meets the above four criteria	-

Office Contact Information (Please Print)
Address: 6 Plaza Court
City / Postal Code: Ottawa / K2H 7W1
Telephone / Extension: (613) 697-3797
E-Mail Address: Andrew.Harte@CGHTransportation.com



Appendix B

Turning Movement Counts






Turning Movement Count - Study Results

CAMBRIAN RD @ RIVER MIST RD

 Survey Date:
 Wednesday, October 23, 2019
 WO No:
 38918

 Start Time:
 07:00
 Device:
 Miovision

Full Study Diagram





Transportation Services - Traffic Services


Turning Movement Count - Study Results

CAMBRIAN RD @ RIVER MIST RD

 Survey Date:
 Wednesday, October 23, 2019
 WO No:
 38918

 Start Time:
 07:00
 Device:
 Miovision

Full Study Peak Hour Diagram



July 14, 2020 Page 1 of 8 July 14, 2020 Page 2 of 8




Turning Movement Count - Peak Hour Diagram

CAMBRIAN RD @ RIVER MIST RD

 Survey Date:
 Wednesday, October 23, 2019
 WO No:
 38918

 Start Time:
 07:00
 Device:
 Miovision



Comments




Transportation Services - Traffic Services

Turning Movement Count - Peak Hour Diagram

CAMBRIAN RD @ RIVER MIST RD

 Survey Date:
 Wednesday, October 23, 2019
 WO No:
 38918

 Start Time:
 07:00
 Device:
 Miovision



Comments




Turning Movement Count - Peak Hour Diagram

CAMBRIAN RD @ RIVER MIST RD

 Survey Date:
 Wednesday, October 23, 2019
 WO No:
 38918

 Start Time:
 07:00
 Device:
 Miovision



Comments



Transportation Services - Traffic Services

Turning Movement Count - Study Results

CAMBRIAN RD @ RIVER MIST RD

 Survey Date:
 Wednesday, October 23, 2019
 WO No:
 38918

 Start Time:
 07:00
 Device:
 Miovision

Full Study Summary (8 HR Standard)

Survey Date: Wednesday, October 23, 201

Total Observed U-Turns

Northbound: 1 Southbound: 0 .99

Eastbound: () Westbound:

								Eastbour	nd: ()		West	tbound:	0						
			RIVE	R MIS	T RD							CA	MBRIA	N RD					
_	No	rthbou	ınd		So	uthbou	ınd			E	astbou	ınd		٧	Vestbo	und			
Period	LT	ST	RT	NB TOT	LT	ST	RT	SB TOT	STR TOT	LT	ST	RT	EB TOT	LT	ST	RT	WB TOT	STR TOT	Grand Total
07:00 08:00	112	19	133	264	42	6	25	73	337	12	198	38	248	35	227	35	297	545	882
08:00 09:00	113	47	100	260	54	19	25	98	358	13	226	45	284	56	246	36	338	622	980
09:00 10:00	82	9	107	198	22	10	16	48	246	9	149	28	186	46	173	21	240	426	672
11:30 12:30	40	5	71	116	16	7	11	34	150	12	160	25	197	47	157	17	221	418	568
12:30 13:30	24	6	55	85	11	1	14	26	111	8	150	34	192	41	140	26	207	399	510
15:00 16:00	57	17	80	154	50	15	20	85	239	17	229	65	311	85	167	38	290	601	840
16:00 17:00	61	13	87	161	32	15	15	62	223	20	371	76	467	121	254	54	429	896	1119
17:00 18:00	69	14	101	184	34	15	20	69	253	24	355	102	481	127	248	63	438	919	1172
Sub Total	558	130	734	1422	261	88	146	495	1917	115	1838	413	2366	558	1612	290	2460	4826	6743
U Turns				1				0	1				0				0	0	1
Total	558	130	734	1423	261	88	146	495	1918	115	1838	413	2366	558	1612	290	2460	4826	6744
EQ 12Hr	776	181	1020	1978	363	122	203	688	2666	160	2555	574	3289	776	2241	403	3419	6708	9374
Note: These	values a	re calcı	lated b	y multipl	ying the	totals b	y the a	ppropriate	e expans	ion fac	tor.			1.39					
AVG 12Hr	658	153	865	1678	308	104	172	584	2399	136	2167	487	2790	658	1901	342	2900	6037	8437
Note: These	volumes	are cal	culated	by multi	plying th	ne Equiv	alent 1	2 hr. tota	ls by the	AADT	factor.			0.9					
AVG 24Hr	862	201	1134	2198	403	136	225	765	2963	178	2839	638	3654	862	2490	448	3799	7453	10416
Note: These	volumes	are cal	culated	by multi	plying th	ne Avera	age Dai	ly 12 hr. 1	totals by	12 to 2	4 expan	sion fac	ctor.	1.31					

Note: U-Turns provided for approach totals. Refer to 'U-Turn' Report for specific breakdown.

2020-Jul-14 Page 3 of 3 July 14, 2020 Page 3 of 8



Turning Movement Count - Study Results

CAMBRIAN RD @ RIVER MIST RD

 Survey Date:
 Wednesday, October 23, 2019
 WO No:
 38918

 Start Time:
 07:00
 Device:
 Miovision

Full Study 15 Minute Increments

			RIVE	R MIS	T RD							CAN	IBRIA	N RD					
	No	orthboi	und		Sc	uthbou	ınd			Е	astbour	nd		W	estbour	nd			
Time Period	LT	ST	RT	N TOT	LT	ST	RT	S TOT	STR TOT	LT	ST	RT	E TOT	LT	ST	RT	W TOT	STR TOT	Grand Total
07:00 07:15	24	4	33	61	10	0	4	14	1	3	50	7	60	9	57	2	68	1	203
07:15 07:30	22	5	37	64	10	2	7	19	3	2	53	9	64	11	46	8	65	3	212
07:30 07:45	28	5	30	63	13	2	7	22	2	4	43	11	58	7	61	12	80	2	223
07:45 08:00	38	5	33	76	9	2	7	18	2	3	52	11	66	8	63	13	84	2	244
08:00 08:15	32	12	28	72	9	1	10	20	5	5	57	12	74	12	65	14	91	5	257
08:15 08:30	33	28	22	83	26	6	6	38	5	4	56	10	70	10	58	15	83	5	274
08:30 08:45	18	5	21	44	14	7	3	24	4	2	63	16	81	19	61	3	83	4	232
08:45 09:00	30	2	29	61	5	5	6	16	1	2	50	7	59	15	62	4	81	1	217
09:00 09:15	32	7	52	91	9	5	4	18	4	1	49	12	62	13	66	5	84	4	255
09:15 09:30	18	0	18	36	9	2	3	14	0	5	38	3	46	13	38	5	56	0	152
09:30 09:45	14	1	26	41	2	1	3	6	1	1	37	3	41	13	34	7	54	1	142
09:45 10:00	18	1	11	30	2	2	6	10	1	2	25	10	37	7	35	4	46	1	123
11:30 11:45	16	0	21	37	2	3	5	10	3	2	38	10	50	13	46	2	61	3	158
11:45 12:00	7	1	8	16	5	1	5	11	1	2	39	4	45	10	41	5	56	1	128
12:00 12:15	9	3	20	32	7	2	1	10	1	2	47	5	54	12	41	4	57	1	153
12:15 12:30	8	1	22	31	2	1	0	3	5	6	36	6	48	12	29	6	47	5	129
12:30 12:45	10	2	16	29	2	0	5	7	1	2	41	6	49	8	38	7	53	1	138
12:45 13:00	7	0	7	14	6	1	4	11	1	1	40	12	53	12	36	2	50	1	128
13:00 13:15	2	3	17	22	2	0	4	6	3	3	33	8	44	10	30	6	46	3	118
13:15 13:30	5	1	15	21	1	0	1	2	2	2	36	8	46	11	36	11	58	2	127
15:00 15:15	10	2	11	23	21	3	4	28	7	4	61	11	76	18	37	10	65	7	192
15:15 15:30	7	5	14	26	12	4	10	26	2	3	52	16	71	25	40	9	74	2	197
15:30 15:45	12	2	23	37	8	7	2	17	4	6	67	18	91	16	45	7	68	4	213
15:45 16:00	28	8	32	68	9	1	4	14	3	4	49	20	73	26	45	12	83	3	238
16:00 16:15	18	3	24	45	11	4	3	18	2	7	91	17	115	30	63	14	107	2	285
16:15 16:30	8	3	18	29	8	5	5	18	5	3	75	21	99	27	63	12	102	5	248
16:30 16:45	16	3	23	42	7	5	5	17	0	5	119	18	142	29	65	14	108	0	309
16:45 17:00	19	4	22	45	6	1	2	9	3	5	86	20	111	35	63	14	112	3	277
17:00 17:15	13	5	40	58	8	4	5	17	2	6	83	31	120	24	67	14	105	2	300
17:15 17:30	21	3	18	42	8	2	3	13	2	4	85	25	114	35	65	22	122	2	291
17:30 17:45	12	3	21	36	10	5	9	24	3	5	105	23	133	36	58	16	110	3	303
17:45 18:00	23	3	22	48	8	4	3	15	2	9	82	23	114	32	58	11	101	2	278
Total:	558	130	734	1423	261	88	146	495	81	115	1838	413	2366	558	1612	290	2460	81	6,744

Note: U-Turns are included in Totals.



Transportation Services - Traffic Services

Turning Movement Count - Study Results

CAMBRIAN RD @ RIVER MIST RD

 Survey Date:
 Wednesday, October 23, 2019
 WO No:
 38918

 Start Time:
 07:00
 Device:
 Miovision

Full Study Cyclist Volume

		RIVER MIST RE	,	•	CAMBRIAN R	D	
Time Period	Northbound	Southbound	Street Total	Eastbound	Westbound	Street Total	Grand Total
07:00 07:15	0	0	0	0	1	1	1
07:15 07:30	0	0	0	0	0	0	0
07:30 07:45	1	0	1	1	0	1	2
07:45 08:00	0	0	0	0	0	0	0
08:00 08:15	0	1	1	0	0	0	1
08:15 08:30	1	0	1	0	0	0	1
08:30 08:45	0	0	0	0	0	0	0
08:45 09:00	0	0	0	1	0	1	1
09:00 09:15	0	0	0	0	0	0	0
09:15 09:30	0	0	0	0	1	1	1
09:30 09:45	1	0	1	0	0	0	1
09:45 10:00	0	0	0	0	0	0	0
11:30 11:45	0	0	0	0	0	0	0
1:45 12:00	0	0	0	0	0	0	0
2:00 12:15	0	0	0	0	0	0	0
2:15 12:30	0	0	0	0	0	0	0
2:30 12:45	0	0	0	0	0	0	0
2:45 13:00	0	0	0	0	0	0	0
13:00 13:15	0	0	0	0	0	0	0
3:15 13:30	0	0	0	0	0	0	0
15:00 15:15	0	2	2	0	0	0	2
5:15 15:30	1	0	1	0	0	0	1
5:30 15:45	0	0	0	0	0	0	0
5:45 16:00	2	0	2	0	0	0	2
6:00 16:15	0	1	1	0	0	0	1
16:15 16:30	0	0	0	0	0	0	0
6:30 16:45	0	0	0	0	0	0	0
6:45 17:00	0	0	0	0	0	0	0
7:00 17:15	0	0	0	0	0	0	0
7:15 17:30	0	0	0	0	0	0	0
17:30 17:45	0	0	0	0	0	0	0
17:45 18:00	0	0	0	0	0	0	0
Total	6	4	10	2	2	4	1/1

July 14, 2020 Page 4 of 8 July 14, 2020 Page 5 of 8



Turning Movement Count - Study Results

CAMBRIAN RD @ RIVER MIST RD

 Survey Date:
 Wednesday, October 23, 2019
 WO No:
 38918

 Start Time:
 07:00
 Device:
 Miovision

Full Study Pedestrian Volume RIVER MIST RD CAMBRIAN RD

Time Period	NB Approach (E or W Crossing)	SB Approach (E or W Crossing)	Total	EB Approach (N or S Crossing)	WB Approach (N or S Crossing)	Total	Grand Total
07:00 07:15	1	2	3	1	4	5	8
07:15 07:30	0	3	3	7	1	8	11
07:30 07:45	0	5	5	1	4	5	10
07:45 08:00	0	6	6	0	0	0	6
08:00 08:15	1	19	20	3	11	14	34
08:15 08:30	0	8	8	0	13	13	21
08:30 08:45	4	6	10	7	7	14	24
08:45 09:00	4	8	12	2	8	10	22
09:00 09:15	0	0	0	0	1	1	1
09:15 09:30	0	1	1	0	3	3	4
09:30 09:45	0	1	1	0	2	2	3
09:45 10:00	1	1	2	0	3	3	5
11:30 11:45	2	2	4	23	4	27	31
11:45 12:00	0	2	2	0	0	0	2
12:00 12:15	2	5	7	2	4	6	13
12:15 12:30	0	4	4	2	3	5	9
12:30 12:45	1	1	2	0	1	1	3
12:45 13:00	2	2	4	1	3	4	8
13:00 13:15	0	4	4	4	3	7	11
13:15 13:30	0	1	1	0	0	0	1
15:00 15:15	3	9	12	6	30	36	48
15:15 15:30	0	3	3	8	5	13	16
15:30 15:45	2	8	10	0	8	8	18
15:45 16:00	1	12	13	8	3	11	24
16:00 16:15	3	6	9	3	6	9	18
16:15 16:30	2	7	9	1	4	5	14
16:30 16:45	1	2	3	4	0	4	7
16:45 17:00	1	9	10	4	4	8	18
17:00 17:15	1	2	3	1	6	7	10
17:15 17:30	0	0	0	0	6	6	6
17:30 17:45	1	6	7	3	10	13	20
17:45 18:00	0	2	2	1	7	8	10
Total	33	147	180	92	164	256	436



Transportation Services - Traffic Services

Turning Movement Count - Study Results

CAMBRIAN RD @ RIVER MIST RD

 Survey Date:
 Wednesday, October 23, 2019
 WO No:
 38918

 Start Time:
 07:00
 Device:
 Miovision

						F	ull S	tud	у Не	avy	Vel	nicle	es						
			RIVE	R MIS	T RD							CAM	IBRIA	N RD					
	Total Tota																		
Time Period	LT	ST	RT		LT	ST	RT			LT	ST	RT		LT	ST	RT			Grand Total
07:00 07:15	0	0	1	1	0	0	0	0	1	1	2	1	4	3	4	0	7	11	12
07:15 07:30	0	0	3	3	0	0	0	0	3	0	7	2	9	2	4	1	7	16	19
07:30 07:45	1	0	1	2	0	0	0	0	2	0	3	0	3	1	4	1	6	9	11
07:45 08:00	2	0	0	2	0	0	0	0	2	1	7	2	10	2	5	0	7	17	19
08:00 08:15	0	3	1	4	0	0	1	1	5	0	3	1	4	2	4	1	7	11	16
08:15 08:30	1	2	0	3	2	0	0	2	5	0	5	0	5	1	4	1	6	11	16
08:30 08:45	0	0	3	3	0	1	0	1	4	0	7	0	7	3	8	0	11	18	22
08:45 09:00	1	0	0	1	0	0	0	0	1	1	4	2	7	1	8	0	9	16	17
09:00 09:15	3	0	1	4	0	0	0	0	4	0	0	1	1	1	8	0	9	10	14
09:15 09:30	0	0	0	0	0	0	0	0	0	0	3	0	3	1	1	0	2	5	5
09:30 09:45	0	0	1	1	0	0	0	0	1	0	5	0	5	2	2	1	5	10	11
09:45 10:00	0	0	1	1	0	0	0	0	1	0	4	0	4	2	2	0	4	8	9
11:30 11:45	0	0	2	2	1	0	0	1	3	0	6	1	7	2	1	0	3	10	13
11:45 12:00	0	0	1	1	0	0	0	0	1	0	0	0	0	2	1	0	3	3	4
12:00 12:15	0	0	1	1	0	0	0	0	1	1	3	1	5	1	1	0	2	7	8
12:15 12:30	0	1	3	4	0	1	0	1	5	0	1	0	1	1	2	0	3	4	9
12:30 12:45	0	0	1	1	0	0	0	0	1	0	4	0	4	1	1	1	3	7	8
12:45 13:00	0	0	0	0	0	0	1	1	1	1	4	1	6	1	2	1	4	10	11
13:00 13:15	0	0	2	2	0	0	1	1	3	0	4	1	5	1	0	0	1	6	9
13:15 13:30	1	0	1	2	0	0	0	0	2	1	5	0	6	1	4	0	5	11	13
15:00 15:15	1	0	1	2	5	0	0	5	7	1	4	2	7	1	1	0	2	9	16
15:15 15:30	0	0	1	1	0	0	1	1	2	0	2	1	3	1	2	0	3	6	8
15:30 15:45	1	0	3	4	0	0	0	0	4	0	2	1	3	1	5	0	6	9	13
15:45 16:00	1	0	1	2	0	0	1	1	3	0	7	0	7	1	3	0	4	11	14
16:00 16:15	1	0	1	2	0	0	0	0	2	0	6	0	6	1	3	1	5	11	13
16:15 16:30	2	0	2	4	0	1	0	1	5	0	1	0	1	0	6	0	6	7	12
16:30 16:45	0	0	0	0	0	0	0	0	0	0	1	0	1	1	2	0	3	4	4
16:45 17:00	0	0	3	3	0	0	0	0	3	0	2	1	3	0	0	0	0	3	6
17:00 17:15	0	0	2	2	0	0	0	0	2	0	2	0	2	1	1	0	2	4	6
17:15 17:30	0	0	2	2	0	0	0	0	2	0	3	0	3	0	0	0	0	3	5
17:30 17:45	1	0	2	3	0	0	0	0	3	0	2	0	2	1	1	0	2	4	7
17:45 18:00	0	0	2	2	0	0	0	0	2	0	2	0	2	0	1	0	1	3	5
Total: None	16	6	43	65	8	3	5	16	81	7	111	18	136	39	91	8	138	274	355

July 14, 2020 Page 6 of 8 July 14, 2020 Page 7 of 8



17:45

Total

18:00

0

Transportation Services - Traffic Services

Turning Movement Count - Study Results

CAMBRIAN RD @ RIVER MIST RD

 Survey Date:
 Wednesday, October 23, 2019
 WO No:
 38918

 Start Time:
 07:00
 Device:
 Miovision

Full Study 15 Minute U-Turn Total RIVER MIST RD CAMBRIAN RD

Northbound Southbound Eastbound Westbound Time Period Total U-Turn Total U-Turn Total U-Turn Total **U-Turn Total** 07:00 07:15 07:15 07:30 0 0 0 0 07:30 07:45 0 0 0 0 07:45 08:00 0 0 0 0 08:00 08:15 0 08:15 08:30 0 0 08:30 08:45 0 0 0 08:45 09:00 0 0 0 09:00 09:15 0 0 0 09:15 09:30 0 0 0 0 09:30 09:45 0 0 0 0 09:45 10:00 0 0 0 0 11:30 11:45 0 0 0 0 11:45 12:00 0 0 0 12:00 12:15 0 0 0 12:15 12:30 0 0 0 0 12:30 12:45 0 0 0 12:45 13:00 0 0 0 0 13:00 13:15 0 0 0 0 13:15 13:30 0 0 0 0 15:00 15:15 0 0 0 0 15:15 15:30 0 0 0 15:30 15:45 0 0 0 0 15:45 16:00 0 0 0 0 0 16:00 16:15 0 0 0 16:15 16:30 0 0 0 0 16:30 16:45 0 0 0 0 16:45 17:00 0 0 0 0 17:00 17:15 0 0 0 0 17:15 17:30 0 0 0 0 0 17:30 17:45 0 0 0 0 0


July 14, 2020 Page 8 of 8

0

0

0

0







Mattamy Homes

Half Moon Bay West

Figure 9: Net New Site Traffic Volumes



Turning Movement Count Summary Report



Including OFF Peak, PM Peak and PHF
All Vehicles Except Bicycles

Cambr	ian	Roa	nd 8	k Ri	iver	Mis	t Ro	oad										Ва	arrh	ave	en V	Vest,	ON
Survey Da	te:	Satur	day,	Octo	ber 15	5, 202	22					Start Time:				1100			AAD	T Fa		1.1	
Weather: A	M:	Mainly	/ Suni	ny 15	° C	Survey Duration: 5 Hrs.						Survey Hours: 1100				- 160	0						
Weather PN	۸:	Overd	ast 12	2º C			Surveyor(s):								J. Mousseau								
	n Ro	d.	(Caml	oriai	n Ro	d.		River Mist Rd.				d.	F	River	Mis	t R	d.					
1		Eas	stbou	nd		Westbound						Northbound				Southbound							
Time Period	LT	ST	RT	UT	E/B Tot	LT	ST	RT	UT	W/B Tot	Street Total	LT	ST	RT	UT	N/B Tot	LT	ST	RT	UT	S/B Tot	Street Total	Grand Total
1100-1200	3	233	21	0	257	63	232	39	0	334	591	45	5	85	0	135	32	9	9	0	50	185	776
1200-1300	6	262	39	0	307	69	280	72	0	421	728	40	10	79	0	129	32	13	16	0	61	190	918
1300-1400	16	243	27	0	286	61	253	33	0	347	633	52	8	90	0	150	42	8	14	0	64	214	847
1400-1500	7	264	49	0	320	75	261	40	0	376	696	32	6	68	0	106	26	4	11	0	41	147	843
1500-1600	14	237	40	0	291	77	272	48	0	397	688	48	10	72	0	130	24	4	14	0	42	172	860
Totals	46	1239	176	0	1461	345	1298	232	0	1875	3336	217	39	394	0	650	156	38	64	0	258	908	4244

Expansion factors are applied exclusively to standard <u>weekday</u> 8-hour turning movement counts conducted during the hours of 0700h - 1000h, 1130h - 1330h and 1500h - 1800h

OFF Peak H	our Fa	actor	→	0.	.98									Highe	st F	lourly	Vehic	le Vol	ume l	Betw	een 1	100h &	1500h
OFF Peak Hr	LT	ST	RT	UT	Total	LT	ST	RT	UT	Total	Str. Tot.	LT	ST	RT	UT	Total	LT	ST	RT	UT	Total	Str. Tot.	Gr. Tot.
1200-1300	6	262	39	0	307	69	280	72	0	421	728	40	10	79	0	129	32	13	16	0	61	190	918
PM Peak Ho	ur Fa	- 4 - -		_																			
I III I CUIT IIC	uiia	ctor 4	<u> </u>	0.	.92									Highe	st F	lourly	Vehic	e Vol	ume l	Betw	een 1	500h &	1900h
PM Peak Hr	LT	ST	RT	UT		LT	ST	RT	UT	Total	Str. Tot.	LT	ST	Highe RT	st I	_	Vehic LT	le Vol	ume I RT	Betw UT	_	500h & Str. Tot.	_

Comments:

OC Transpo buses comprise 50.98% of the heavy vehicle traffic.


Notes:

- 1. Includes all vehicle types except bicycles and electric scooters.
- 2. When expansion and AADT factors are applied, the results will differ slightly due to rounding.

TRUSTED TRAFFIC DATA

Turning Movement Count Summary, OFF and PM Peak Hour Flow Diagrams

All Vehicles Except Bicycles



Printed on: 10/17/2022 Prepared by: thetrafficspecialist@gmail.com

Printed on: 10/17/2022

Summary: All Vehicles


Prepared by: thetrafficspecialist@gmail.com

Flow Diagrams: OFF PM Peak



Turning Movement Count Heavy Vehicle Summary (FHWA Class 4-13) Flow Diagram






Comments:

OC Transpo buses comprise 50.98% of the heavy vehicle traffic.



Turning Movement Count All Buses Summary (FHWA Class 4 ONLY) Flow Diagram





Comments:

OC Transpo buses comprise 50.98% of the heavy vehicle traffic.

Printed on: 10/17/2022 Prepared by: thetrafficspecialist@gmail.com Summary: Heavy Vehicles Printed on: 10/17/2022 Prepared by: thetrafficspecialist@gmail.com Summary: Buses Only




Turning Movement Count Bicycle Summary Flow Diagram






Turning Movement Count Pedestrian Crossings Summary and Flow Diagram





Comments:

OC Transpo buses comprise 50.98% of the heavy vehicle traffic.



Time Period	West Side Crossing	East Side Crossing	Street	South Side Crossing	North Side Crossing	Street	Grand
Time Period	Cambrian Rd.	Cambrian Rd.	Total	River Mist Rd.	River Mist Rd.	Total	Total
1100-1200	7	23	30	3	30	33	63
1200-1300	6	17	23	8	18	26	49
1300-1400	5	8	13	4	8	12	25
1400-1500	1	6	7	1	3	4	11
1500-1600	1	16	17	3	13	16	33
Totals	20	70	90	19	72	91	181

Comments:

OC Transpo buses comprise 50.98% of the heavy vehicle traffic.

Printed on: 10/17/2022 Prepared by: thetrafficspecialist@gmail.com Summary: Pedestrian Crossings



Turning Movement Count Summary Report



Including OFF Peak, PM Peak and PHF All Vehicles Except Bicycles

Apolun	e S	tree	t/E	leva	atio	n R	oad	& (Can	nbri	an R	oac						Ва	ırrh	ave	en V	lest,	ON
Survey Da	te:	Satur	day,	Octo	ber 15	5, 202	2					Star	t Time	e:		1100			AAD	T Fa	ctor:		1.1
Weather: A	M:	Mostly	/ Suni	ny 15	° C		Surve	y Dura	ation:	5	Hrs.	Surv	ey Ho	ours:		1100	- 160	0					
Weather PN	۸:	Overc	ast 12	2º C								Surv	eyor(s):		M. Br	azeaı	J					
	(Cambrian Rd. Cambrian Rd.											Eleva	atior	ı Ro	l.		Apo	lune	e St			
1		Eas	stbou	nd			We	stbou	ınd				No	rthbou	ınd			Sou	thbou	und		1	
Time Period	LT	ST	RT	UT	E/B Tot	LT	ST	RT	UT	W/B Tot	Street Total	LT	ST	RT	UT	N/B Tot	LT	ST	RT	UT	S/B Tot	Street Total	Grand Total
1100-1200	25	159	4	0	188	15	241	39	0	295	483	4	2	13	0	19	26	4	47	0	77	96	57
1200-1300	25	201	3	0	229	14	260	47	0	321	550	10	2	17	0	29	33	0	43	0	76	105	65
1300-1400	32	203	8	0	243	21	242	44	1	308	551	6	3	16	0	25	35	4	34	0	73	98	64
1400-1500	35	215	5	0	255	15	222	45	0	282	537	9	1	20	0	30	50	2	42	0	94	124	66
1500-1600	31	247	4	0	282	9	218	53	0	280	562	3	2	10	0	15	40	3	37	0	80	95	65
Totals	148	1025	24	0	1197	74	1183	228	1	1486	2683	32	10	76	0	118	184	13	203	0	400	518	320

Expansion factors are applied exclusively to standard weekday 8-hour turning movement counts conducted during the hours of 0700h - 1000h, 1130h - 1330h and 1500h - 1800h

OFF Peak H	lour F	actor	→	0.	95									Highe	st H	lourly	Vehicl	e Volu	ıme E	Betw	een 1	100h &	1500h
OFF Peak Hr	LT	ST	RT	UT	Total	LT	ST	RT	UT	Total	Str. Tot.	LT	ST	RT	UT	Total	LT	ST	RT	UT	Total	Str. Tot.	Gr. Tot.
1345-1445	38	206	6	0	250	15	236	49	0	300	550	12	1	21	0	34	47	2	45	0	94	128	678
				_		_		_	_														
PM Peak Ho	our Fa			0.	89									Highe	st H	lourly	Vehicl	e Volu	ıme E	Betw	een 1	500h &	1900h
	our Fa		RT	0 .	89 Total	LT	ST	RT	UT	Total	Str. Tot.	LT	ST	Highe RT	st H	lourly Total	Vehicle LT	e Vol u	ıme E	Betw UT	_	500h &	_

Comments:

New housing construction is underway in this area.


Notes:

Printed on: 10/17/2022

- 1. Includes all vehicle types except bicycles and electric scooters.
- 2. When expansion and AADT factors are applied, the results will differ slightly due to rounding.

Turning Movement Count Summary, OFF and PM Peak Hour

Flow Diagrams



Prepared by: thetrafficspecialist@gmail.com

Printed on: 10/17/2022

Summary: All Vehicles


Prepared by: thetrafficspecialist@gmail.com

Flow Diagrams: OFF PM Peak



Turning Movement Count Heavy Vehicle Summary (FHWA Class 4-13) Flow Diagram






Comments:

New housing construction is underway in this area.



Turning Movement Count Bicycle Summary Flow Diagram





Comments:


Printed on: 10/17/2022

New housing construction is underway in this area



Turning Movement Count Pedestrian Crossings Summary and Flow Diagram





Time Period	West Side Crossing	East Side Crossing	Street	South Side Crossing	North Side Crossing	Street	Grand
Time Period	Cambrian Rd.	Cambrian Rd.	Total	Elevation Rd.	Apolune St.	Total	Total
1100-1200	3	2	5	2	0	2	7
1200-1300	0	5	5	0	0	0	5
1300-1400	0	0	0	1	0	1	1
1400-1500	0	0	0	0	0	0	0
1500-1600	0	0	0	1	0	1	1
Totals	3	7	10	4	0	4	14

Comments:

New housing construction is underway in this area.

Printed on: 10/17/2022 Prepared by: thetrafficspecialist@gmail.com Summary: Pedestrian Crossings

Appendix C

Synchro Intersection Worksheets – Existing Conditions



Intersection												
Intersection Delay, s/veh	20.3											
Intersection LOS	С											
	_											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		44			4			4			4	
Traffic Vol, veh/h	14	308	49	49	247	45	121	50	104	58	16	26
Future Vol, veh/h	14	308	49	49	247	45	121	50	104	58	16	26
Peak Hour Factor	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90
Heavy Vehicles, %	7	10	6	16	9	4	2	10	4	3	6	4
Mvmt Flow	16	342	54	54	274	50	134	56	116	64	18	29
Number of Lanes	0	1	0	0	1	0	0	1	0	0	1	0
Approach	EB			WB			NB			SB		
Opposing Approach	WB			EB			SB			NB		
Opposing Lanes	1			1			1			1		
Conflicting Approach Left	SB			NB			EB			WB		
Conflicting Lanes Left	1			1			1			1		
Conflicting Approach Right	NB			SB			WB			EB		
Conflicting Lanes Right	1			1			1			1		
HCM Control Delay	23.1			21.9			17.5			12.5		
HCM LOS	C C			C C			17.5			В		
I IOW LOO	U			U			U			D		
Lana		NDI =1	EDI -1	WDI a1	CDI =1							
Lane		NBLn1	EBLn1	WBLn1	SBLn1							
Vol Left, %		44%	4%	14%	58%							
Vol Thru, %		18%	83%	72%	16%							
Vol Right, %		38%	13%	13%	26%							
Sign Control		Stop	Stop	Stop	Stop							
Traffic Vol by Lane		275	371	341	100							
LT Vol		121	14	49	58							
Through Vol		50	308	247	16							
RT Vol		104	49	45	26							
Lane Flow Rate		306	412	379	111							
Geometry Grp		1	1	1	1							
Degree of Util (X)		0.555	0.71	0.676	0.224							
Departure Headway (Hd)		6.538	6.201	6.421	7.26							
Convergence, Y/N		Yes	Yes	Yes	Yes							
Сар		550	581	561	491							
Service Time		4.603	4.263	4.485	5.349							
HCM Lane V/C Ratio		0.556	0.709	0.676	0.226							
HCM Control Delay		17.5	23.1	21.9	12.5							
		С	С	С	В							
HCM Lane LOS		2.4	F 0	E 1	0.0							

Intersection						
Int Delay, s/veh	2.2					
Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations	ሻ	•	ß		Y	
Traffic Vol, veh/h	9	225	397	14	64	32
Future Vol, veh/h	9	225	397	14	64	32
Conflicting Peds, #/hr	5	0	0	5	2	2
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	75	-	-	-	0	-
Veh in Median Storage	е,#-	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	90	90	90	90	90	90
Heavy Vehicles, %	2	21	6	2	2	2
Mvmt Flow	10	250	441	16	71	36
Major/Minor	Major4		Majora		Minor	
	Major1		Major2		Minor2	450
Conflicting Flow All	462	0	-	0	726 454	456
Stage 1	-	-	-	-		
Stage 2	-	-	-	-	272	-
Critical Hdwy	4.12	-	-	-	6.42	6.22
Critical Hdwy Stg 1	-	-	-	-	5.42	-
Critical Hdwy Stg 2	-	-	-	-	5.42	
Follow-up Hdwy	2.218	-	-	-	0.0.0	
Pot Cap-1 Maneuver	1099	-	-	-	391	604
Stage 1	-	-	-	-	640	-
Stage 2	-	-	-	-	774	-
Platoon blocked, %		-	-	-		
Mov Cap-1 Maneuver	1094	-	-	-	384	600
Mov Cap-2 Maneuver	-	-	-	-	384	-
Stage 1	-	-	-	-	631	-
Stage 2	-	-		-	770	-
A b	ED		ME		00	
Approach	EB		WB		SB	
HCM Control Delay, s	0.3		0		15.9	
HCM LOS					С	
Minor Lane/Major Mvn	nt	EBL	EBT	WBT	WBR	SBLn1
Capacity (veh/h)		1094	-	-	- VVDIC	436
HCM Lane V/C Ratio		0.009				0.245
HCM Control Delay (s)	١	8.3				15.9
HCM Lane LOS		0.5 A				15.9 C
I IOIVI LAITE LUS		А	-	-	-	U

3.4

5.8 5.1

HCM 95th-tile Q

0 - - - 0.9

HCM 95th %tile Q(veh)

Intersection												
Intersection Delay, s/veh	24.7											
Intersection LOS	С											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		4			4			4			44	
Traffic Vol, veh/h	20	325	94	123	285	64	69	15	103	29	12	15
Future Vol, veh/h	20	325	94	123	285	64	69	15	103	29	12	15
Peak Hour Factor	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90
Heavy Vehicles, %	2	2	2	2	2	2	2	2	7	2	2	2
Mvmt Flow	22	361	104	137	317	71	77	17	114	32	13	17
Number of Lanes	0	1	0	0	1	0	0	1	0	0	1	0
Approach	EB			WB			NB			SB		
Opposing Approach	WB			EB			SB			NB		
Opposing Lanes	1			1			1			1		
Conflicting Approach Left	SB			NB			EB			WB		
Conflicting Lanes Left	1			1			1			1		
Conflicting Approach Right	NB			SB			WB			EB		
Conflicting Lanes Right	1			1			1			1		
HCM Control Delay	25			30.3			13.6			11.4		
HCM LOS	С			D			В			В		
ane		NBLn1	EBLn1	WBLn1	SBLn1							
/ol Left, %		37%	5%	26%	52%							
ol Thru, %		8%	74%	60%	21%							
ol Right, %		55%	21%	14%	27%							
Sign Control		Stop	Stop	Stop	Stop							
Fraffic Vol by Lane		187	439	472	56							
.T Vol		69	20	123	29							
Through Vol		15	325	285	12							
RT Vol		103	94	64	15							
ane Flow Rate		208	488	524	62							
Geometry Grp		1	1	1	1							
Degree of Util (X)		0.38	0.768	0.829	0.126							
Departure Headway (Hd)		6.577	5.666	5.69	7.305							
Convergence, Y/N		Yes	Yes	Yes	Yes							
Cap		546	639	640	488							
Service Time		4.631	3.683	3.708	5.38							
		0.381	0.764	0.819	0.127							
ICM Lane V/C Ratio		13.6	25	30.3	11.4							

Intersection						
Int Delay, s/veh	1.6					
Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations	7	•	Þ		Y	
Traffic Vol, veh/h	32	394	373	48	43	18
Future Vol, veh/h	32	394	373	48	43	18
Conflicting Peds, #/hr	6	0	0	6	3	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	75	-	-	-	0	-
Veh in Median Storage	.# -	0	0		0	-
Grade, %	-	0	0		0	-
Peak Hour Factor	90	90	90	90	90	90
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	36	438	414	53	48	20
	00	100		00	.0	
	Major1		Major2		Minor2	
Conflicting Flow All	473	0	-	0	960	447
Stage 1	-	-	-	-	447	-
Stage 2	-	-	-	-	513	-
Critical Hdwy	4.12	-	-	-	6.42	6.22
Critical Hdwy Stg 1	-	-	-	-	5.42	-
Critical Hdwy Stg 2	-	-	-	-	5.42	-
Follow-up Hdwy	2.218	-	-	-	3.518	3.318
Pot Cap-1 Maneuver	1089	-	-	-	285	612
Stage 1	-	-			644	-
Stage 2		-	_		601	-
Platoon blocked, %			- 1		001	
Mov Cap-1 Maneuver	1083			-	272	609
				- 1	272	009
Mov Cap-2 Maneuver	-	_	-	-		-
Stage 1	-	-	-	-	619	-
Stage 2	-	-	-	-	597	-
Approach	EB		WB		SB	
HCM Control Delay, s	0.6		0		19	
HCM LOS	0.0		0		C	
1101111 200					U	
Minor Lane/Major Mvm	nt	EBL	EBT	WBT	WBR	SBLn1
Capacity (veh/h)		1083	-	-	-	325
HCM Lane V/C Ratio		0.033	-	-	-	0.209
HCM Control Delay (s)		8.4	-	-	-	19
HCM Lane LOS		Α			-	C
HCM 95th %tile Q(veh))	0.1	-	-	-	0.8

1.8

7.1 8.8

HCM Lane LOS HCM 95th-tile Q

Intersection						
Int Delay, s/veh	2.5					
int Delay, s/ven	2.5					
Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations	Ĭ	•	Þ		W	
Traffic Vol, veh/h	38	206	236	49	47	45
Future Vol, veh/h	38	206	236	49	47	45
Conflicting Peds, #/hr	6	0	0	6	3	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	75	-	-	-	0	-
Veh in Median Storage	e,# -	0	0	-	0	-
Grade, %	-,	0	0		0	
Peak Hour Factor	90	90	90	90	90	90
Heavy Vehicles, %	2	2	2	2	2	2
Mymt Flow	42	229	262	54	52	50
	-12	LLU	202	01	UZ.	00
	Major1	1	/lajor2		Minor2	
Conflicting Flow All	322	0	-	0	611	295
Stage 1	-	-	-	-	295	-
Stage 2	-	-	-	-	316	-
Critical Hdwy	4.12	-	-	-	6.42	6.22
Critical Hdwy Stg 1	-	-	-	-	5.42	-
Critical Hdwy Stg 2	-	-	-	-	5.42	-
Follow-up Hdwy	2.218	-	-	-	3.518	3.318
Pot Cap-1 Maneuver	1238	-	-	-	457	744
Stage 1	-		-		755	-
Stage 2	_	_			739	
Platoon blocked. %					. 00	
Mov Cap-1 Maneuver	1231			-	436	740
Mov Cap-1 Maneuver	1201	-	-		436	140
Stage 1					725	
					735	
Stage 2		-	-		135	
Approach	EB		WB		SB	
HCM Control Delay, s	1.3		0		13.1	
HCM LOS					В	
Minor Lane/Major Mvr	nt	EBL	EBT	WBT	WBR:	
Capacity (veh/h)		1231	-	-	-	546
HCM Lane V/C Ratio		0.034	-	-	-	0.187
HCM Control Delay (s)	8	-	-	-	13.1
HCM Lane LOS		Α	-	-	-	В

10.6

0.9

13 17.4

2.7

10.1

5 0.4

HCM Control Delay

HCM Lane LOS HCM 95th-tile Q

0.1 - - - 0.7

HCM 95th %tile Q(veh)

Appendix D

Collision Data




Accident Date	Accident Year	Accident Time	Location	Environment Condition	Light	Traffic Control	Traffic Control Condition	Classification Of Accident	Initial Impact Type	Road Surface Condition	# Vehicles	# Motorcycles	# Bicycles	# Pedestrians
2019-10-10	2019	15:43	APOLUNE ST @ CAMBRIAN RD (0018897)	01 - Clear	01 - Daylight	02 - Stop sign	01 - Functioning	03 - P.D. only	02 - Angle	01 - Dry	2	0	0	0
2016-01-30	2016	4:40	CAMBRIAN RD btwn BORRISOKANE RD & GRAND CANAL ST (7N36UU)	03 - Snow	07 - Dark	10 - No control	0	02 - Non-fatal injury	07 - SMV other	03 - Loose snow	1	0	0	0

Appendix E

Greenbank Road and South West Transitway Extension Preliminary Design





Appendix F

Background Development Volumes







Figure 8: New Site Generation Auto Volumes 000 Cambrian Road 0(0) 0(0) 99(174) 7 ← 28(50) Site 50(43) ----Future Site Access #2









81(48) 0(0) Cambrian Road Site Access #1 (Truck Entrance) 92(54) Site Access #2 0(0) 92(54) 3(12) 0(0) 10(6) 1

Figure 8: New 2027 Site Traffic Auto Volumes












CIGIH



QUINN'S POINTE 2 TRANSPORTATION IMPACT ASSESSMENT

Forecasting October 30, 2018

Figure 10 and Figure 11 summarize the trip assignment to the study area road network during the weekday AM and PM peak hours, respectively.

Figure 10 Trip Assignment – 2022 Interim – Weekday AM Peak Hour





Figure 11 Trip Assignment - 2022 Interim - Weekday PM Peak Hour







 $olw:\active \ 163601203 \ planning \ report\ strategy \ update \ submission \ rpt. quinns_pointe_2_40_strategy_report_10-30-2018. docx$

19

3831 Cambrian Road Transportation Impact Assessment






Street 7


Figure 9: Site Generated Trips




Transportation Impact Assessment Proposed Elementary School and Childcare in Barrhaven March 2022– 21-2355













Page 14

March 5, 2019 Rosanna Baggs, C.E.T. Page 3 of 4

Reference: Mattamy Half Moon Bay West Community Transportation Study Update

Table 2 - Auto Trip Generation - Original Draft Plan (October 2017)

Land Use Code	Units		AM Peak Hou	r		PM Peak Hour	1
Land Use Code	Uillis	Inbound	Outbound	Rate	Inbound	Outbound	Rate
Step 1: ITE Trip Generation Rate	es						
210 - Single Detached Houses	518	25%	75%	0.72	63%	37%	0.89
230 - Residential Condo / Townhouse	427	17%	83%	0.39	67%	33%	0.46
220 - Apartments	92	20%	80%	0.53	65%	35%	0.74
Step 2: Auto Trips Generated							
210 - Single Detached Houses	518	93	280	373	290	171	461
230 - Residential Condo / Townhouse	427	28	139	167	131	65	196
220 - Apartments	92	10	39	49	44	24	68
Total Development		131	458	589	465	260	725

As can be seen in **Table 2**, the original draft plan was projected to generate 589 and 725 auto trips (two-way) during the AM and PM peak hours, respectively.

Table 3 - Auto Trip Generation - Revised Draft Plan (February 2019)


Land Use Code	Units	AM Peak Hour			PM Peak Hour		
		Inbound	Outbound	Rate	Inbound	Outbound	Rate
Step 1: ITE Trip Generation Rat	es						
210 - Single Detached Houses	446	25%	75%	0.72	63%	37%	0.89
230 - Residential Condo / Townhouse	455	17%	83%	0.39	67%	33%	0.46
220 - Apartments	72	20%	80%	0.53	65%	35%	0.74
Step 2: Auto Trips Generated							
210 - Single Detached Houses	446	80	241	321	250	147	397
230 - Residential Condo / Townhouse	455	30	147	177	140	69	209
220 - Apartments	72	8	30	38	34	19	53
Total Development		118	418	536	424	235	659

As can be seen in **Table 3**, the revised draft plan is expected to generate 536 and 659 auto trips (two-way) during the AM and PM peak hours, respectively.


CONCLUSION

A comparison of the original and revised plan shows that the proposed subdivision's collector road network and intersections with the existing boundary road network remain unchanged.

Design with community in mind



3809 Borrisokane Road Transportation Impact Assessment





3845 Cambrian Road Transportation Impact Assessment

Figure 11: New Site Generation Auto Volumes





Figure 12: Pass-by Volumes





Appendix G

Synchro Intersection Worksheets – 2024 Future Background Conditions



49.3

23

23 424

23 424

0

WB

SB

NB

76.4

EBT EBR

1.00

10

53%

32%

Stop

330

50 424

104

330

0.693 1.037

Yes

5.769 5.056

26.5 76.4

5.2 15.3

7.769 7.056

0.704 1.021

4%

80%

16%

Stop

529

23

82

529

Yes

518

82

82

1.00

6

82

Intersection Delay, s/veh

Intersection LOS

Movement

Lane Configurations Traffic Vol, veh/h

Future Vol, veh/h

Peak Hour Factor

Heavy Vehicles, %

Number of Lanes

Opposing Lanes Conflicting Approach Left

Conflicting Lanes Left Conflicting Approach Right

Conflicting Lanes Right HCM Control Delay

Mvmt Flow

Approach
Opposing Approach

HCM LOS

Vol Left, %

Vol Thru, %

Vol Right, % Sign Control

Through Vol

Lane Flow Rate

Geometry Grp Degree of Util (X)

Service Time

Departure Headway (Hd)

Convergence, Y/N

HCM Lane V/C Ratio

HCM Control Delay

HCM Lane LOS HCM 95th-tile Q

LT Vol

RT Vol

Cap

Traffic Vol by Lane

WDI	MOT	MDD	NDI	NDT	NDD	ODI	OPT	000
WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
49	♣ 335	51	176	↔ 50	104	71	↔ 16	46
49	335	51	176	50	104	71	16	46
1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
16	9	4	2	10	4	3	6	4
49	335	51	176	50	104	71	16	46
0	1	0	0	1	0	0	1	0
WB			NB			SB		
EB			SB			NB		
1			1			1		
NB			EB			WB		
1			1			1		
SB 1			WB 1			EB 1		
44.1			26.5			15.6		
44.1			20.5 D			C		
_						0		
WBLn1	SBLn1							
11%	53%							
77%	12%							
12%	35%							
Stop	Stop							
435	133							
49	71							
335	16							
51 435	46 133							
435	133							
0.879	0.312							
7.485	8.735							
Yes	Yes							
487	414							
5.485	6.735							
0.893	0.321							
44.1	15.6							
9.5	C 1.3							
5.5	1.3							

4.2	WBT 441 441 1485 1485 18 520 NA 6 10.0 23.7 39.6 56.6% 4.2 1.5	79 79 0 0	189 189 1658 0.736 1284 189 Perm 4 4 10.0 30.4 30.4 43.4%	NBT 0 0 1483 1483 568 66 NA 4 10.0 30.4 30.4	66 66 0 0	SBL 140 1492 0.714 1121 140 Perm 8 8 10.0	SBT 0 0 1483 1483 335 32 NA 8	32
31 31 1658 0.549 958 31 Perm 6 6 10.0 23.7 39.6 56.6%	441 441 1485 1485 18 520 NA 6 6 10.0 23.7 39.6 56.6% 4.2	79 0	189 189 1658 0.736 1284 189 Perm 4 4 10.0 30.4 30.4 43.4%	0 0 1483 1483 568 66 NA 4 10.0 30.4 30.4	66 0	140 1492 0.714 1121 140 Perm 8 8	0 0 1483 1483 335 32 NA 8	32 32 0 0
31 1658 0.549 958 31 Perm 6 6 10.0 23.7 39.6 56.6%	441 1485 18 520 NA 6 6 10.0 23.7 39.6 56.6% 4.2	79 0	189 1658 0.736 1284 189 Perm 4 4 10.0 30.4 30.4 43.4%	0 1483 1483 568 66 NA 4 10.0 30.4 30.4	66 0	140 1492 0.714 1121 140 Perm 8 8	0 1483 1483 335 32 NA 8	32
1658 0.549 958 31 Perm 6 6 6 10.0 23.7 39.6 56.6%	1485 1485 18 520 NA 6 6 10.0 23.7 39.6 56.6% 4.2	0	1658 0.736 1284 189 Perm 4 4 10.0 30.4 30.4 43.4%	1483 568 66 NA 4 10.0 30.4 30.4	0	1492 0.714 1121 140 Perm 8 8	1483 1483 335 32 NA 8	0
0.549 958 31 Perm 6 6 6 10.0 23.7 39.6 56.6%	1485 18 520 NA 6 6 10.0 23.7 39.6 56.6% 4.2	0	0.736 1284 189 Perm 4 4 10.0 30.4 30.4 43.4%	1483 568 66 NA 4 10.0 30.4 30.4	0	0.714 1121 140 Perm 8 8	1483 335 32 NA 8	0
958 31 Perm 6 6 10.0 23.7 39.6 56.6% 4.2	18 520 NA 6 6 10.0 23.7 39.6 56.6% 4.2		1284 189 Perm 4 4 10.0 30.4 30.4 43.4%	568 66 NA 4 4 10.0 30.4 30.4	_	1121 140 Perm 8 8	335 32 NA 8	
31 Perm 6 6 6 10.0 23.7 39.6 56.6%	18 520 NA 6 6 10.0 23.7 39.6 56.6% 4.2		189 Perm 4 4 10.0 30.4 30.4 43.4%	568 66 NA 4 4 10.0 30.4 30.4	_	140 Perm 8 8	335 32 NA 8	
Perm 6 6 7 10.0 23.7 39.6 66.6% 4.2	520 NA 6 6 10.0 23.7 39.6 56.6% 4.2	0	Perm 4 4 10.0 30.4 30.4 43.4%	66 NA 4 4 10.0 30.4 30.4	0	Perm 8 8 8	32 NA 8	0
Perm 6 6 7 10.0 23.7 39.6 66.6% 4.2	NA 6 6 10.0 23.7 39.6 56.6% 4.2	0	Perm 4 4 10.0 30.4 30.4 43.4%	NA 4 4 10.0 30.4 30.4	0	Perm 8 8 8	NA 8	0
6 6 10.0 23.7 39.6 56.6%	6 10.0 23.7 39.6 56.6% 4.2		4 4 10.0 30.4 30.4 43.4%	4 4 10.0 30.4 30.4		8 8	8	
10.0 23.7 39.6 56.6%	10.0 23.7 39.6 56.6% 4.2		10.0 30.4 30.4 43.4%	4 10.0 30.4 30.4		10.0	8	
10.0 23.7 39.6 56.6%	10.0 23.7 39.6 56.6% 4.2		10.0 30.4 30.4 43.4%	10.0 30.4 30.4		10.0		
10.0 23.7 39.6 56.6%	10.0 23.7 39.6 56.6% 4.2		10.0 30.4 30.4 43.4%	10.0 30.4 30.4		10.0		
23.7 39.6 56.6% 4.2	23.7 39.6 56.6% 4.2		30.4 30.4 43.4%	30.4 30.4			10.0	
23.7 39.6 56.6% 4.2	23.7 39.6 56.6% 4.2		30.4 30.4 43.4%	30.4 30.4			10.0	
39.6 56.6% 4.2	39.6 56.6% 4.2		30.4 43.4%	30.4		20.4		
56.6% 4.2	56.6% 4.2		43.4%			30.4	30.4	
4.2	4.2			10 101		30.4	30.4	
				43.4%		43.4%	43.4%	
	1.5		3.3	3.3		3.3	3.3	
1.5			2.6	2.6		2.6	2.6	
0.0	0.0		0.0	0.0		0.0	0.0	
5.7	5.7		5.9	5.9		5.9	5.9	
C-Min	C-Min		None	None		None	None	
42.1	42.1		16.3	16.3		16.3	16.3	
0.60	0.60		0.23	0.23		0.23	0.23	
0.05	0.58		0.63	0.08		0.54	0.05	
8.2	13.0		32.9	0.2		30.0	0.2	
0.0	0.0		0.0	0.0		0.0	0.0	
8.2	13.0		32.9	0.2		30.0	0.2	
Α	В		С	Α		С	Α	
	12.8			24.5			24.5	
	В			С			С	
1.4	34.3		22.6	0.0		16.4	0.0	
6.1	83.9		35.0	0.0		27.1	0.0	
	254.3			97.9			184.1	
37.5			30.0			30.0		
	901		449	888		392	736	
576	0		0	0		0	0	
	0		0	0		0	0	
576	0		0	0		0	0	
576 0	0.58		0.42	0.07		0.36	0.04	
	0	0 0 0 0 0 0	0 0 0 0 0 0 0 0 0.05 0.58	0 0 0 0 0 0 0 0 0 0 0 0 0.05 0.58 0.42	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0.05 0.58 0.42 0.07	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0.05 0.58 0.42 0.07 0.36	0 0.05 0.58 0.42 0.07 0.36 0.04

Natural Cycle: 60

Control Type: Actuated-Coordinated

Lanes, Volumes, Timings

2: Elevation/Apolune & Cambrian

2024 Future Background AM Peak Hour

Maximum v/c Ratio: 0.63	
Intersection Signal Delay: 15.6	Intersection LOS: B
Intersection Capacity Utilization 56.9%	ICU Level of Service B
Analysis Period (min) 15	

 Splits and Phases:
 2: Elevation/Apolune & Cambrian

 → Ø2 (R)
 30.4 s

 → Ø6 (R)
 Ø8

HCM 2010 TWSC 5: Temporary Driveway & Cambrian 2024 Future Background AM Peak Hour

Interception						
Intersection	0.4					
Int Delay, s/veh	U.4					
Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations	ĥ			ર્ન	W	
Traffic Vol, veh/h	430	22	9	536	15	6
Future Vol, veh/h	430	22	9	536	15	6
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage,	# 0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	100	100	100	100	100	100
Heavy Vehicles, %	2	2	2	2	2	2
Mymt Flow	430	22	9	536	15	6
14 1 041 14					W 4	
	ajor1		Major2		Minor1	
Conflicting Flow All	0	0	452	0	995	441
Stage 1	-	-	-	-	441	-
Stage 2	-	-	-	-	554	-
Critical Hdwy	-	-	4.12	-	6.42	6.22
Critical Hdwy Stg 1	-	-	-	-	5.42	-
Critical Hdwy Stg 2	-	-	-	-	5.42	-
Follow-up Hdwy	-	-		-	3.518	
Pot Cap-1 Maneuver	-	-	1109	-	271	616
Stage 1	-	-	-	-	648	-
Stage 2	-	-	-	-	575	-
Platoon blocked, %	-	-		-		
Mov Cap-1 Maneuver	-	-	1109	-	268	616
Mov Cap-2 Maneuver	-	-	-	-	268	-
Stage 1	-	-	-	-	648	-
Stage 2	-	-	-	-	568	-
3.0						
			MD		ND	
Approach	EB		WB		NB	
HCM Control Delay, s	0		0.1		17	
HCM LOS					С	
Minor Lane/Major Mvmt	- 1	NBLn1	EBT	EBR	WBL	WBT
Capacity (veh/h)		320	-	- LDIK	1109	-
HCM Lane V/C Ratio		0.066			0.008	
HCM Control Delay (s)		17			8.3	0
HCM Lane LOS		C			0.5 A	A
HOMOSIL OUT		0.0	-	-	A	А

	•	-	*	•	—	•	1	†	1	-	↓	1
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBF
Lane Configurations	*	1>		*	1>		*	1 >		*	1>	
Traffic Volume (vph)	32	445	177	56	411	103	136	0	41	88	0	1
Future Volume (vph)	32	445	177	56	411	103	136	0	41	88	0	1
Satd. Flow (prot)	1658	1670	0	1658	1511	0	1658	1483	0	1492	1483	
Flt Permitted	0.442		-	0.382		_	0.746		_	0.730		
Satd. Flow (perm)	766	1670	0	667	1511	0	1302	1483	0	1139	1483	
Satd. Flow (RTOR)		33			21			443			464	
Lane Group Flow (vph)	32	622	0	56	514	0	136	41	0	88	18	
Turn Type	Perm	NA	-	Perm	NA	_	Perm	NA	_	Perm	NA	
Protected Phases		2			6			4			8	
Permitted Phases	2	=		6	_		4	•		8	_	
Detector Phase	2	2		6	6		4	4		8	8	
Switch Phase	=	=			-						-	
Minimum Initial (s)	10.0	10.0		10.0	10.0		10.0	10.0		10.0	10.0	
Minimum Split (s)	23.7	23.7		23.7	23.7		30.4	30.4		30.4	30.4	
Total Split (s)	82.0	82.0		82.0	82.0		38.0	38.0		38.0	38.0	
Total Split (%)	68.3%	68.3%		68.3%	68.3%		31.7%	31.7%		31.7%	31.7%	
Yellow Time (s)	4.2	4.2		4.2	4.2		3.3	3.3		3.3	3.3	
All-Red Time (s)	1.5	1.5		1.5	1.5		2.6	2.6		2.6	2.6	
Lost Time Adjust (s)	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0	
Total Lost Time (s)	5.7	5.7		5.7	5.7		5.9	5.9		5.9	5.9	
Lead/Lag	• • • • • • • • • • • • • • • • • • • •	• • • • • • • • • • • • • • • • • • • •			• • • • • • • • • • • • • • • • • • • •							
Lead-Lag Optimize?												
Recall Mode	C-Min	C-Min		C-Min	C-Min		None	None		None	None	
Act Effct Green (s)	90.6	90.6		90.6	90.6		17.8	17.8		17.8	17.8	
Actuated g/C Ratio	0.76	0.76		0.76	0.76		0.15	0.15		0.15	0.15	
v/c Ratio	0.06	0.49		0.11	0.45		0.70	0.07		0.52	0.03	
Control Delay	5.2	7.7		5.6	7.4		67.0	0.2		56.8	0.1	
Queue Delay	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0	
Total Delay	5.2	7.7		5.6	7.4		67.0	0.2		56.8	0.1	
LOS	A	Α		A	Α		Е	A		Е	Α	
Approach Delay	,,	7.5		- / /	7.2		_	51.5			47.2	
Approach LOS		A			A			D			D	
Queue Length 50th (m)	1.7	46.0		3.0	36.6		30.8	0.0		19.4	0.0	
Queue Length 95th (m)	5.4	86.5		8.7	70.6		48.8	0.0		33.9	0.0	
Internal Link Dist (m)	0	122.9		0.1	259.5		10.0	171.4		00.0	184.1	
Turn Bay Length (m)	37.5	122.0		37.5	200.0		30.0			30.0		
Base Capacity (vph)	578	1268		503	1145		348	721		304	736	
Starvation Cap Reductn	0	0		0	0		0	0		0	0	
Spillback Cap Reductn	0	0		0	0		0	0		0	0	
Storage Cap Reductn	0	0		0	0		0	0		0	0	
Reduced v/c Ratio	0.06	0.49		0.11	0.45		0.39	0.06		0.29	0.02	
Intersection Summary												
Cycle Length: 120												
Actuated Cycle Length: 120												
Officet: 0 (00/) Deferenced	4 l O											

Offset: 0 (0%), Referenced to phase 2:EBTL and 6:WBTL, Start of Green

Natural Cycle: 60

Control Type: Actuated-Coordinated

2024 Future Background PM Peak Hour

Maximum v/c Ratio: 0.70	
Intersection Signal Delay: 15.4	Intersection LOS: B
Intersection Capacity Utilization 73.4%	ICU Level of Service D
Analysis Period (min) 15	

Splits and Phases: 2: Elevation/Apolune & Cambrian



HCM 2010 TWSC 5: Temporary Driveway & Cambrian 2024 Future Background PM Peak Hour

Intersection						
Int Delay, s/veh	0.9					
iiii Delay, S/VeII	0.9					
Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations	₽			ની	N/	
Traffic Vol, veh/h	517	57	6	532	38	9
Future Vol, veh/h	517	57	6	532	38	9
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage		-	-	0	0	-
Grade, %	0			0	0	
Peak Hour Factor	100	100	100	100	100	100
Heavy Vehicles, %	2	2	2	2	2	2
Mymt Flow	517	57	6	532	38	9
IVIVIIIL FIOW	317	5/	р	532	38	9
Major/Minor	Major1		Major2		Minor1	
Conflicting Flow All	0	0	574	0	1090	546
Stage 1	-	-	-	-	546	-
Stage 2					544	
Critical Hdwy		_	4.12	-	6.42	6.22
Critical Hdwy Stg 1	- 1		4.12	- 1	5.42	0.22
Critical Hdwy Stg 1					5.42	
Follow-up Hdwy			2.218		3.518	
		-	999		238	538
Pot Cap-1 Maneuver	-	-	999	-		
Stage 1	-	-	-	-	580	-
Stage 2	-	-	-	-	582	-
Platoon blocked, %	-	-		-		
Mov Cap-1 Maneuver	-	-	999	-	236	538
Mov Cap-2 Maneuver	-	-	-	-	236	-
Stage 1	-	-	-	-	580	-
Stage 2	-	-	-	-	577	-
5						
			MD		ND	
Approach	EB		WB		NB	
HCM Control Delay, s	0		0.1		21.6	
HCM LOS					С	
Minor Lane/Major Mvn	nt I	NBLn1	EBT	EBR	WBL	WBT
	it l	264			999	
Capacity (veh/h)			-	-		-
HCM Lane V/C Ratio		0.178	-	-	0.006	-
HCM Control Delay (s)		21.6	-	-	8.6	0
HCM Lane LOS		С	-	-	Α	Α

Geometry Grp Degree of Util (X)

Cap Service Time

Departure Headway (Hd)

Convergence, Y/N

HCM Lane V/C Ratio

HCM Control Delay

HCM 95th-tile Q

Intersection												
Intersection Delay, s/veh	20.8											
Intersection LOS	С											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		4			4			4			4	
Traffic Vol, veh/h	18	330	82	69	378	82	80	10	79	40	13	27
Future Vol, veh/h	18	330	82	69	378	82	80	10	79	40	13	27
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Heavy Vehicles, %	2	2	2	7	2	2	2	2	4	2	8	2
Mvmt Flow	18	330	82	69	378	82	80	10	79	40	13	27
Number of Lanes	0	1	0	0	1	0	0	1	0	0	1	0
Approach	EB			WB			NB			SB		
Opposing Approach	WB			EB			SB			NB		
Opposing Lanes	1			1			1			1		
Conflicting Approach Left	SB			NB			EB			WB		
Conflicting Lanes Left	1			1			1			1		
Conflicting Approach Right	NB			SB			WB			EB		
Conflicting Lanes Right	1			1			1			1		
HCM Control Delay	18.4			26.8			12.4			11.2		
HCM LOS	С			D			В			В		
Lane		NBLn1	EBLn1	WBLn1	SBLn1							
Vol Left, %		47%	4%	13%	50%							
Vol Thru, %		6%	77%	71%	16%							
Vol Right, %		47%	19%	16%	34%							
Sign Control		Stop	Stop	Stop	Stop							
Traffic Vol by Lane		169	430	529	80							
LT Vol		80	18	69	40							
Through Vol		10	330	378	13							
RT Vol		79	82	82	27							
Lane Flow Rate		169	430	529	80							

0.306 0.653 0.799 0.154

6.527 5.465 5.439 6.909

Yes Yes

3.526 4.917

0.8 0.153

26.8 11.2

8 0.5

Yes

Yes

12.4 18.4

1.3 4.8

4.533 3.558

0.305 0.657

	•	\rightarrow	*	•	←	*	1	†	1	1	↓	4
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	*	1 >		ች	î,		ች	ĵ.		ች	î,	
Traffic Volume (vph)	38	248	160	70	270	88	128	1	61	72	2	45
Future Volume (vph)	38	248	160	70	270	88	128	1	61	72	2	45
Satd. Flow (prot)	1566	1642	0	1271	1498	0	1658	1333	0	1436	1402	C
Flt Permitted	0.538			0.507			0.726			0.717		
Satd. Flow (perm)	878	1642	0	679	1498	0	1267	1333	0	1076	1402	0
Satd. Flow (RTOR)		48			24			61			45	
Lane Group Flow (vph)	38	408	0	70	358	0	128	62	0	72	47	0
Turn Type	Perm	NA	-	Perm	NA	_	Perm	NA	_	Perm	NA	
Protected Phases		2			6			4			8	
Permitted Phases	2			6	-		4	•		8	_	
Detector Phase	2	2		6	6		4	4		8	8	
Switch Phase	=	=		-	-					-	-	
Minimum Initial (s)	10.0	10.0		10.0	10.0		10.0	10.0		10.0	10.0	
Minimum Split (s)	23.7	23.7		23.7	23.7		30.4	30.4		30.4	30.4	
Total Split (s)	77.0	77.0		77.0	77.0		43.0	43.0		43.0	43.0	
Total Split (%)	64.2%	64.2%		64.2%	64.2%		35.8%	35.8%		35.8%	35.8%	
Yellow Time (s)	4.2	4.2		4.2	4.2		3.3	3.3		3.3	3.3	
All-Red Time (s)	1.5	1.5		1.5	1.5		2.6	2.6		2.6	2.6	
Lost Time Adjust (s)	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0	
Total Lost Time (s)	5.7	5.7		5.7	5.7		5.9	5.9		5.9	5.9	
Lead/Lag	0.1	0.7		0.7	0.1		0.0	0.0		0.0	0.0	
Lead-Lag Optimize?												
Recall Mode	C-Min	C-Min		C-Min	C-Min		None	None		None	None	
Act Effct Green (s)	91.0	91.0		91.0	91.0		17.4	17.4		17.4	17.4	
Actuated g/C Ratio	0.76	0.76		0.76	0.76		0.14	0.14		0.14	0.14	
v/c Ratio	0.76	0.70		0.70	0.70		0.70	0.14		0.14	0.14	
Control Delay	5.0	5.4		5.6	5.7		67.4	13.0		55.0	14.4	
Queue Delay	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0	
Total Delay	5.0	5.4		5.6	5.7		67.4	13.0		55.0	14.4	
LOS	J.0	J.4 A		J.0 A	J.7		07.4 E	13.0 B		55.0 D	В	
Approach Delay		5.4			5.7			49.7		U	38.9	
Approach LOS		3.4 A			3.7 A			49.7 D			30.9 D	
Queue Length 50th (m)	2.0	22.6		3.8	21.0		29.0	0.2		15.7	0.4	
Queue Length 95th (m)	6.0	44.7		10.4	41.6		46.7	11.7		28.7	10.4	
Internal Link Dist (m)	0.0	122.9		10.4	257.7		40.7	171.4		20.1	184.1	
Turn Bay Length (m)	37.5	122.9		37.5	251.1		30.0	171.4		30.0	104.1	
Base Capacity (vph)	665	1256		514	1141		391	454		332	464	
Starvation Cap Reductn	000	1256		0	0		391	454		0	464	
Spillback Cap Reductn	0	0		0	0		0	0		0	0	
Storage Cap Reductn	0	0		0	0		0	0		0	0	
Reduced v/c Ratio		0.32		0.14	0.31		0.33			0.22	0.10	
Reduced V/C Ratio	0.06	0.32		0.14	0.31		0.33	0.14		0.22	0.10	
Intersection Summary												
Cycle Length: 120												

Actuated Cycle Length: 120

Offset: 0 (0%), Referenced to phase 2:EBTL and 6:WBTL, Start of Green

Natural Cycle: 60

Control Type: Actuated-Coordinated

Lanes, Volumes, Timings

2: Elevation/Apolune & Cambrian

2024 Future Background SAT Peak Hour

Maximum v/c Ratio: 0.70	
Intersection Signal Delay: 16.0	Intersection LOS: B
Intersection Capacity Utilization 61.0%	ICU Level of Service B
Analysis Period (min) 15	

Splits and Phases: 2: Elevation/Apolune & Cambrian

opino and i nacco. 2. Elevation, polario a cambilari	
→ø2 (R)	↑ Ø4
77 s	43 s
▼ Ø6 (R)	↓ ø8
77 s	43 s

HCM 2010 TWSC 5: Temporary Driveway & Cambrian 2024 Future Background SAT Peak Hour

Intersection						
Int Delay, s/veh	2.3					
Movement	EBT	EBR	WBL	WBT	NBL	NBR
		EDK	WBL			INDIX
Lane Configurations	1	66	7	લી 83	¥	10
Traffic Vol, veh/h	40		7		44	
Future Vol, veh/h	40	66	7	83	44	10
Conflicting Peds, #/hr	_ 0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage,		-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	100	100	100	100	100	100
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	40	66	7	83	44	10
Main (Minne	-1	_	4-:0		Minand	
	ajor1		Major2		Minor1	
Conflicting Flow All	0	0	106	0	170	73
Stage 1	-	-	-	-	73	-
Stage 2	-	-	-	-	97	-
Critical Hdwy	-	-	4.12	-	6.42	6.22
Critical Hdwy Stg 1	-	-	-	-	5.42	-
Critical Hdwy Stg 2	-	-	-	-	5.42	-
Follow-up Hdwy	-	-	2.218	-	0.0.0	
Pot Cap-1 Maneuver	-	-	1485	-	820	989
Stage 1	-	-	-	-	950	-
Stage 2	-		-	-	927	-
Platoon blocked, %	-					
Mov Cap-1 Maneuver	-	-	1485	-	816	989
Mov Cap-1 Maneuver	-		1700		816	-
Stage 1			-		950	
Stage 2					922	
Staye 2	-	-	-	-	322	-
Approach	EB		WB		NB	
HCM Control Delay, s	0		0.6		9.6	
HCM LOS					A	
Minor Lane/Major Mvmt	1	NBLn1	EBT	EBR	WBL	WBT
Capacity (veh/h)		843	-	-	1485	-
HCM Lane V/C Ratio		0.064	-	-	0.005	-
HCM Control Delay (s)		9.6	-	-	7.4	0
HCM Lane LOS		Α	-	-	Α	A
HCM 95th %tile Q(veh)		0.2	-	-	0	-
0001 7000 Q(1011)		0.2			0	

Appendix H

Signal Warrant Calculation Sheet



Justification #7

		Minimum F	Requirement	Minimum R	Requirement		Compliance		
Justification	Description	1 Lane	Highway	2 or Mo	re Lanes	Sect	ional	Entire %	Signal
		Free Flow	Restr. Flow	Free Flow	Restr. Flow	Numerical	%	Ellule 76	
1. Minimum Vehicular	A. Vehicle volume, all approaches (average hour)	480	720	600	900	726	101%	101%	No
Volume	B. Vehicle volume, along minor streets (average hour)	120	170	120	170	192	113%	101%	NO
2. Delay to Cross	A. Vehicle volumes, major street (average hour)	480	720	600	900	534	74%		
Traffic	B. Combined vehicle and pedestrian volume crossing artery from minor streets (average hour)	50	75	50	75	115	153%	74%	No

- Streets (average nour)

 Notes

 1. Refer to OTM Book 12, pg 92, Mar 2012
 2. Lowest section percatage governs justification
 3. Average hourly volumes estimated from peak hour volumes, AHV = PM/2 or (AM + PM) / 4, including amplifcation factors
 4. T-intersection factor corrected, applies only to 18

Cambrian Road @ River Mist Road FB 2029

Justification #7

		Minimum R	equirement	Minimum R	Requirement		Compliance		
Justification	Description	1 Lane I	Highway	2 or Mo	re Lanes	Secti	ional	Entire %	Signal
		Free Flow	Restr. Flow	Free Flow	Restr. Flow	Numerical	%	Entire %	
1. Minimum Vehicular	A. Vehicle volume, all approaches (average hour)	480	720	600	900	830	115%	115%	No
Volume	B. Vehicle volume, along minor streets (average hour)	120	170	120	170	204	120%	115%	NO
2. Delay to Cross	A. Vehicle volumes, major street (average hour)	480	720	600	900	626	87%		
Traffic	B. Combined vehicle and pedestrian volume crossing artery from minor streets (average hour)	50	75	50	75	125	166%	87%	No

- Notes
 1. Refer to OTM Book 12, pg 92, Mar 2012
 2. Lowest section percentage governs justification
 3. Average hourly volumes estimated from peak hour volumes, AHV = PM/2 or (AM + PM) / 4, including amplifcation factors
 4. -Intersection factor corrected, applies only to 18

Cambrian Road @ River Mist Road FT 2024

Justification #7

		Minimum F	Requirement	Minimum R	equirement		Compliance		
Justification	Description	1 Lane	Highway	2 or Mo	re Lanes	Sect	ional	Entire %	Signal
		Free Flow	Restr. Flow	Free Flow	Restr. Flow	Numerical	%	Ellule 76	
1. Minimum Vehicular	A. Vehicle volume, all approaches (average hour)	480	720	600	900	737	102%	102%	No
	B. Vehicle volume, along minor streets (average hour)	120	170	120	170	195	115%	102%	NO
	A. Vehicle volumes, major street (average hour)	480	720	600	900	542	75%		
Traffic	B. Combined vehicle and pedestrian volume crossing artery from minor streets (average hour)	50	75	50	75	117	156%	75%	No

- Streets (average nour)

 Notes

 1. Refer to OTM Book 12, pg 92, Mar 2012
 2. Lowest section percatage governs justification
 3. Average hourly volumes estimated from peak hour volumes, AHV = PM/2 or (AM + PM) / 4, including amplifcation factors
 4. T-intersection factor corrected, applies only to 18

Cambrian Road @ River Mist Road FT 2029

Justification #7

		Minimum R	equirement	Minimum R	Requirement		Compliance			
Justification	Description	1 Lane I	Highway	2 or Mo	re Lanes	Secti	ional	Entire %	Signal	
		Free Flow	Restr. Flow	Free Flow	Restr. Flow			Entire %	i	
1. Minimum Vehicular	A. Vehicle volume, all approaches (average hour)	480	720	600	900	841	117%	117%	No	
Volume	B. Vehicle volume, along minor streets (average hour)	120	170	120	170	208	122%	11/70	INO	
2. Delay to Cross	A. Vehicle volumes, major street (average hour)	480	720	600	900	634	88%			
Traffic	B. Combined vehicle and pedestrian volume crossing artery from minor streets (average hour)	50	75	50	75	127	169%	88%	No	

- Notes
 1. Refer to OTM Book 12, pg 92, Mar 2012
 2. Lowest section percentage governs justification
 3. Average hourly volumes estimated from peak hour volumes, AHV = PM/2 or (AM + PM) / 4, including amplifcation factors
 4. -Intersection factor corrected, applies only to 18

Appendix I

Synchro Intersection Worksheets – 2029 Future Background Conditions



Intersection							
Intersection Delay, s/veh	96.9						
Intersection LOS	F						

Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		44			4			4			4	
Traffic Vol, veh/h	24	507	93	51	391	51	194	50	109	71	16	47
Future Vol, veh/h	24	507	93	51	391	51	194	50	109	71	16	47
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Heavy Vehicles, %	7	10	6	16	9	4	2	10	4	3	6	4
Mvmt Flow	24	507	93	51	391	51	194	50	109	71	16	47
Number of Lanes	0	1	0	0	1	0	0	1	0	0	1	0
Approach	EB			WB			NB			SB		
Opposing Approach	WB			EB			SB			NB		
Opposing Lanes	1			1			1			1		
Conflicting Approach Left	SB			NB			EB			WB		
Conflicting Lanes Left	1			1			1			1		
Conflicting Approach Right	NB			SB			WB			EB		
Conflicting Lanes Right	1			1			1			1		
HCM Control Delay	164.9			77.3			34.1			17.6		
HCM LOS	F			F			D			С		

Lane	NBLn1	EBLn1	WBLn1	SBLn1
Vol Left, %	55%	4%	10%	53%
Vol Thru, %	14%	81%	79%	12%
Vol Right, %	31%	15%	10%	35%
Sign Control	Stop	Stop	Stop	Stop
Traffic Vol by Lane	353	624	493	134
LT Vol	194	24	51	71
Through Vol	50	507	391	16
RT Vol	109	93	51	47
Lane Flow Rate	353	624	493	134
Geometry Grp	1	1	1	1
Degree of Util (X)	0.764	1.281	1.022	0.331
Departure Headway (Hd)	8.49	7.497	8.1	9.814
Convergence, Y/N	Yes	Yes	Yes	Yes
Cap	431	487	454	368
Service Time	6.49	5.497	6.1	7.814
HCM Lane V/C Ratio	0.819	1.281	1.086	0.364
HCM Control Delay	34.1	164.9	77.3	17.6
HCM Lane LOS	D	F	F	С
HCM 95th-tile Q	6.4	25.8	13.7	1.4

	•	-	\rightarrow	•	-	*	1	†	1	-	↓	1
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	*	f)		ሻ	- ↑		ሻ	- ↑		ሻ	1→	
Traffic Volume (vph)	14	256	129	57	464	95	270	0	117	174	0	42
Future Volume (vph)	14	256	129	57	464	95	270	0	117	174	0	42
Satd. Flow (prot)	1658	1475	0	1658	1483	0	1658	1483	0	1492	1483	0
Flt Permitted	0.360			0.497			0.730			0.682		
Satd. Flow (perm)	628	1475	0	867	1483	0	1274	1483	0	1071	1483	0
Satd. Flow (RTOR)		50			20			554			315	
Lane Group Flow (vph)	14	385	0	57	559	0	270	117	0	174	42	0
Turn Type	Perm	NA		Perm	NA		Perm	NA		Perm	NA	
Protected Phases		2			6			4			8	
Permitted Phases	2			6			4			8		
Detector Phase	2	2		6	6		4	4		8	8	
Switch Phase												
Minimum Initial (s)	10.0	10.0		10.0	10.0		10.0	10.0		10.0	10.0	
Minimum Split (s)	23.7	23.7		23.7	23.7		30.4	30.4		30.4	30.4	
Total Split (s)	39.6	39.6		39.6	39.6		30.4	30.4		30.4	30.4	
Total Split (%)	56.6%	56.6%		56.6%	56.6%		43.4%	43.4%		43.4%	43.4%	
Yellow Time (s)	4.2	4.2		4.2	4.2		3.3	3.3		3.3	3.3	
All-Red Time (s)	1.5	1.5		1.5	1.5		2.6	2.6		2.6	2.6	
Lost Time Adjust (s)	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0	
Total Lost Time (s)	5.7	5.7		5.7	5.7		5.9	5.9		5.9	5.9	
Lead/Lag												
Lead-Lag Optimize?												
Recall Mode	C-Min	C-Min		C-Min	C-Min		None	None		None	None	
Act Effct Green (s)	39.2	39.2		39.2	39.2		19.2	19.2		19.2	19.2	
Actuated g/C Ratio	0.56	0.56		0.56	0.56		0.27	0.27		0.27	0.27	
v/c Ratio	0.04	0.45		0.12	0.67		0.77	0.14		0.59	0.07	
Control Delay	9.5	11.1		9.9	17.2		38.0	0.4		29.6	0.2	
Queue Delay	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0	
Total Delay	9.5	11.1		9.9	17.2		38.0	0.4		29.6	0.2	
LOS	Α	В		Α	В		D	Α		С	Α	
Approach Delay		11.1			16.6			26.6			23.9	
Approach LOS		В			В			С			С	
Queue Length 50th (m)	0.8	23.7		3.3	46.4		31.9	0.0		19.3	0.0	
Queue Length 95th (m)	3.6	50.3		9.8	#107.4		52.0	0.0		34.3	0.0	
Internal Link Dist (m)		192.0			268.9			97.9			184.1	
Turn Bay Length (m)	37.5			37.5			30.0			30.0		
Base Capacity (vph)	351	847		485	838		445	879		374	723	
Starvation Cap Reductn	0	0		0	0		0	0		0	0	
Spillback Cap Reductn	0	0		0	0		0	0		0	0	
Storage Cap Reductn	0	0		0	0		0	0		0	0	
Reduced v/c Ratio	0.04	0.45		0.12	0.67		0.61	0.13		0.47	0.06	
Intersection Summary												
Cycle Length: 70												
4 1 1 10 1 1 11 70												

Actuated Cycle Length: 70
Offset: 0 (0%), Referenced to phase 2:EBTL and 6:WBTL, Start of Green
Natural Cycle: 65

Control Type: Actuated-Coordinated

Lanes, Volumes, Timings 2: Elevation/Apolune & Cambrian

2029 Future Background AM Peak Hour

Maximum v/c Ratio: 0.77	
Intersection Signal Delay: 18.6	Intersection LOS: B
Intersection Capacity Utilization 77.1%	ICU Level of Service D
Analysis Period (min) 15	
# 95th percentile volume exceeds capacity, queue may be long	ger.
Queue shown is maximum after two cycles.	

Splits and Phases: 2: Elevation/Apolune & Cambrian

Ø2 (R)	↑ 04
39.6 s	30.4s
▼ Ø6 (R)	Ø8
39.6 s	30.4 s

HCM 2010 TWSC 5: Temporary Driveway & Cambrian 2029 Future Background AM Peak Hour

Intersection						
Int Delay, s/veh	0.4					
**		EDD	MD	MOT	ND	NDD
Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations	^}	00	^	4	Y	^
Traffic Vol, veh/h	524	22	9	613	15	6
Future Vol, veh/h	524	22	9	613	15	6
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-		- 0	None
Storage Length	- 4 0	-	-	-	-	-
Veh in Median Storage		-	-	0	0	-
Grade, %	0	400	400	0	0	400
Peak Hour Factor	100	100	100	100	100	100
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	524	22	9	613	15	6
Major/Minor	Major1	- 1	Major2		Minor1	
Conflicting Flow All	0	0	546	0	1166	535
Stage 1	-	-	-	-	535	-
Stage 2	-	-	-	-	631	-
Critical Hdwy	-	-	4.12	-	6.42	6.22
Critical Hdwy Stg 1	-	-	-	-	5.42	-
Critical Hdwy Stg 2	-	-	-	-	5.42	-
Follow-up Hdwy	-	-	2.218	-	3.518	3.318
Pot Cap-1 Maneuver	-	-	1023	-	214	545
Stage 1	-	-	-	-	587	-
Stage 2	-	-	-	-	530	-
Platoon blocked, %	-	-		-		
Mov Cap-1 Maneuver	-	-	1023	-	211	545
Mov Cap-2 Maneuver	-	-	-	-	211	-
Stage 1	-	-	-	-	587	-
Stage 2	-	-	-	-	523	-
·						
Approach	EB		WB		NB	
	0		0.1		20.3	
HCM Control Delay, s HCM LOS	U		0.1		20.3 C	
HOW LOS					C	
Minor Lane/Major Mvm	nt I	NBLn1	EBT	EBR	WBL	WBT
Capacity (veh/h)		256	-	-	1023	-
HCM Lane V/C Ratio		0.082	-	-	0.009	-
HCM Control Delay (s)		20.3	-	-	8.6	0
HCM Lane LOS		С	-	-	Α	Α
HOMOSH WITH OF I		0.0			^	

Intersection	
Intersection Delay, s/veh	108.4
Intersection LOS	F

Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		4			4			44			4	
Traffic Vol, veh/h	36	494	162	128	487	76	130	15	106	38	12	29
Future Vol, veh/h	36	494	162	128	487	76	130	15	106	38	12	29
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Heavy Vehicles, %	2	2	2	2	2	2	2	2	7	2	2	2
Mvmt Flow	36	494	162	128	487	76	130	15	106	38	12	29
Number of Lanes	0	1	0	0	1	0	0	1	0	0	1	0
Approach	EB			WB			NB			SB		
Opposing Approach	WB			EB			SB			NB		
Opposing Lanes	1			1			1			1		
Conflicting Approach Left	SB			NB			EB			WB		
Conflicting Lanes Left	1			1			1			1		
Conflicting Approach Right	NB			SB			WB			EB		
Conflicting Lanes Right	1			1			1			1		
HCM Control Delay	126.5			133.4			19.1			14.2		
HCM LOS	F			F			С			В		

Lane	NBLn1	EBLn1	WBLn1	SBLn1
Vol Left, %	52%	5%	19%	48%
Vol Thru, %	6%	71%	70%	15%
Vol Right, %	42%	23%	11%	37%
Sign Control	Stop	Stop	Stop	Stop
Traffic Vol by Lane	251	692	691	79
LT Vol	130	36	128	38
Through Vol	15	494	487	12
RT Vol	106	162	76	29
Lane Flow Rate	251	692	691	79
Geometry Grp	1	1	1	1
Degree of Util (X)	0.507	1.193	1.21	0.181
Departure Headway (Hd)	8.084	6.564	6.647	9.173
Convergence, Y/N	Yes	Yes	Yes	Yes
Cap	449	561	553	393
Service Time	6.084	4.564	4.647	7.173
HCM Lane V/C Ratio	0.559	1.234	1.25	0.201
HCM Control Delay	19.1	126.5	133.4	14.2
HCM Lane LOS	С	F	F	В
HCM 95th-tile Q	2.8	23.6	24.3	0.7

	*	→	\rightarrow	•	←	•	4	†	1	-	ļ	1
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	*	ĵ.		ሻ	ĵ.		ሻ	ĵ.		ሻ	1→	
Traffic Volume (vph)	42	460	255	114	428	135	193	0	88	126	0	27
Future Volume (vph)	42	460	255	114	428	135	193	0	88	126	0	27
Satd. Flow (prot)	1658	1653	0	1658	1500	0	1658	1483	0	1492	1483	0
Flt Permitted	0.399			0.314			0.740			0.700		
Satd. Flow (perm)	692	1653	0	548	1500	0	1291	1483	0	1092	1483	0
Satd. Flow (RTOR)		46			26			430			447	
Lane Group Flow (vph)	42	715	0	114	563	0	193	88	0	126	27	0
Turn Type	Perm	NA		Perm	NA		Perm	NA		Perm	NA	
Protected Phases		2			6			4			8	
Permitted Phases	2			6			4			8		
Detector Phase	2	2		6	6		4	4		8	8	
Switch Phase												
Minimum Initial (s)	10.0	10.0		10.0	10.0		10.0	10.0		10.0	10.0	
Minimum Split (s)	23.7	23.7		23.7	23.7		30.4	30.4		30.4	30.4	
Total Split (s)	82.0	82.0		82.0	82.0		38.0	38.0		38.0	38.0	
Total Split (%)	68.3%	68.3%		68.3%	68.3%		31.7%	31.7%		31.7%	31.7%	
Yellow Time (s)	4.2	4.2		4.2	4.2		3.3	3.3		3.3	3.3	
All-Red Time (s)	1.5	1.5		1.5	1.5		2.6	2.6		2.6	2.6	
Lost Time Adjust (s)	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0	
Total Lost Time (s)	5.7	5.7		5.7	5.7		5.9	5.9		5.9	5.9	
Lead/Lag												
Lead-Lag Optimize?												
Recall Mode	C-Min	C-Min		C-Min	C-Min		None	None		None	None	
Act Effct Green (s)	85.3	85.3		85.3	85.3		23.1	23.1		23.1	23.1	
Actuated g/C Ratio	0.71	0.71		0.71	0.71		0.19	0.19		0.19	0.19	
v/c Ratio	0.09	0.60		0.29	0.52		0.78	0.14		0.60	0.04	
Control Delay	7.5	11.9		10.2	10.8		65.9	0.5		54.9	0.1	
Queue Delay	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0	
Total Delay	7.5	11.9		10.2	10.8		65.9	0.5		54.9	0.1	
LOS	Α	В		В	В		Е	Α		D	Α	
Approach Delay		11.6			10.7			45.4			45.3	
Approach LOS		В			В			D			D	
Queue Length 50th (m)	2.7	70.8		8.8	51.8		43.5	0.0		27.3	0.0	
Queue Length 95th (m)	8.2	133.0		22.8	98.9		63.7	0.0		43.5	0.0	
Internal Link Dist (m)		122.9			257.3			171.4			184.1	
Turn Bay Length (m)	37.5			37.5			30.0			30.0		
Base Capacity (vph)	491	1187		389	1073		345	711		292	724	
Starvation Cap Reductn	0	0		0	0		0	0		0	0	
Spillback Cap Reductn	0	0		0	0		0	0		0	0	
Storage Cap Reductn	0	0		0	0		0	0		0	0	
Reduced v/c Ratio	0.09	0.60		0.29	0.52		0.56	0.12		0.43	0.04	
Intersection Summary												
Cycle Length: 120												
Actuated Cycle Length: 120	1											

Actuated Cycle Length: 120
Offset: 0 (0%), Referenced to phase 2:EBTL and 6:WBTL, Start of Green Natural Cycle: 70

Control Type: Actuated-Coordinated

Lanes, Volumes, Timings 2: Elevation/Apolune & Cambrian

2029 Future Background PM Peak Hour

Maximum v/c Ratio: 0.78	
Intersection Signal Delay: 19.1	Intersection LOS: B
Intersection Capacity Utilization 82.7%	ICU Level of Service E
Analysis Period (min) 15	

Splits and Phases: 2: Elevation/Apolune & Cambrian



HCM 2010 TWSC 5: Temporary Driveway & Cambrian 2029 Future Background PM Peak Hour

Intersection						
Int Delay, s/veh	1					
	EDT	EDD	WDI	WBT	NDI	NDD
Movement	EBT	EBR	WBL		NBL	NBR
Lane Configurations	^}		0	4	* /*	0
Traffic Vol, veh/h	633	57	6	654	38	9
Future Vol, veh/h	633	57	6	654	38	9
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage		-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	100	100	100	100	100	100
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	633	57	6	654	38	9
Major/Minor	Major1		Major?		Minor1	
			Major2			000
Conflicting Flow All	0	0	690	0	1328	662
Stage 1	-	-	-	-	662	-
Stage 2	-	-	-	-	666	-
Critical Hdwy	-	-	4.12	-	6.42	6.22
Critical Hdwy Stg 1	-	-	-	-	5.42	-
Critical Hdwy Stg 2	-	-	-	-	5.42	-
Follow-up Hdwy	-	-	2.218	-	0.0.0	
Pot Cap-1 Maneuver	-	-	905	-	171	462
Stage 1	-	-	-	-	513	-
Stage 2	-	-	-	-	511	-
Platoon blocked, %	-	-		-		
Mov Cap-1 Maneuver	-		905	-	169	462
Mov Cap-2 Maneuver			-		169	-
Stage 1			_		513	
Stage 2					506	-
Olaye 2					300	
Approach	EB		WB		NB	
HCM Control Delay, s	0		0.1		29.7	
HCM LOS					D	
Mineral and Main M		UDL4	EDT	EDD	MD	MIDT
Minor Lane/Major Mvm	it l	NBLn1	EBT	EBR	WBL	WBT
Capacity (veh/h)		192	-	-	905	-
HCM Lane V/C Ratio		0.245	-	-		-
HCM Control Delay (s)		29.7	-	-	9	0
HCM Lane LOS		D	-	-	Α	Α

Intersection												
Intersection Delay, s/veh	49.4											
Intersection LOS	Е											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		44			4			43-			43-	
Traffic Vol, veh/h	21	410	108	74	469	82	103	10	82	40	13	30
Future Vol, veh/h	21	410	108	74	469	82	103	10	82	40	13	30
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Heavy Vehicles, %	2	2	2	7	2	2	2	2	4	2	8	2
Mvmt Flow	21	410	108	74	469	82	103	10	82	40	13	30
Number of Lanes	0	1	0	0	1	0	0	1	0	0	1	0
Approach	EB			WB			NB			SB		
Opposing Approach	WB			EB			SB			NB		
Opposing Lanes	1			1			1			1		
Conflicting Approach Left	SB			NB			EB			WB		
Conflicting Lanes Left	1			1			1			1		
Conflicting Approach Right	NB			SB			WB			EB		
Conflicting Lanes Right	1			1			1			1		
HCM Control Delay	38.7			74.3			15			12.7		
HCM LOS	Е			F			В			В		
Lane		NBLn1	EBLn1	WBLn1	SBLn1							
Vol Left, %		53%	4%	12%	48%							
Vol Thru, %												
		5%	76%	75%	16%							
Vol Right, %		42%	20%	75% 13%								
· · · · · · · · · · · · · · · · · · ·					16% 36% Stop							
Vol Right, %		42%	20%	13%	16% 36%							
Vol Right, % Sign Control Traffic Vol by Lane LT Vol		42% Stop 195 103	20% Stop 539 21	13% Stop 625 74	16% 36% Stop 83 40							
Vol Right, % Sign Control Traffic Vol by Lane		42% Stop 195 103 10	20% Stop 539	13% Stop 625	16% 36% Stop 83 40							
Vol Right, % Sign Control Traffic Vol by Lane LT Vol Through Vol RT Vol		42% Stop 195 103	20% Stop 539 21 410 108	13% Stop 625 74 469 82	16% 36% Stop 83 40							
Vol Right, % Sign Control Traffic Vol by Lane LT Vol Through Vol		42% Stop 195 103 10 82 195	20% Stop 539 21 410 108 539	13% Stop 625 74 469 82 625	16% 36% Stop 83 40 13 30 83							
Vol Right, % Sign Control Traffic Vol by Lane LT Vol Through Vol RT Vol Lane Flow Rate Geometry Grp		42% Stop 195 103 10 82 195	20% Stop 539 21 410 108 539	13% Stop 625 74 469 82 625	16% 36% Stop 83 40 13 30 83							
Vol Right, % Sign Control Traffic Vol by Lane LT Vol Through Vol RT Vol Lane Flow Rate Geometry Grp Degree of Util (X)		42% Stop 195 103 10 82 195 1 0.388	20% Stop 539 21 410 108 539 1 0.884	13% Stop 625 74 469 82 625 1	16% 36% Stop 83 40 13 30 83 1							
Vol Right, % Sign Control Traffic Vol by Lane LT Vol Through Vol RT Vol Lane Flow Rate Geometry Grp Degree of Util (X) Departure Headway (Hd)		42% Stop 195 103 10 82 195 1 0.388 7.384	20% Stop 539 21 410 108 539 1 0.884 6.08	13% Stop 625 74 469 82 625 1 1.048 6.038	16% 36% Stop 83 40 13 30 83 1 0.177 7.952							
Vol Right, % Sign Control Traffic Vol by Lane LT Vol Through Vol RT Vol Lane Flow Rate Geometry Grp Degree of Util (X) Departure Headway (Hd) Convergence, Y/N		42% Stop 195 103 10 82 195 1 0.388 7.384 Yes	20% Stop 539 21 410 108 539 1 0.884 6.08 Yes	13% Stop 625 74 469 82 625 1 1.048 6.038 Yes	16% 36% Stop 83 40 13 30 83 1 0.177 7.952 Yes							
Vol Right, % Sign Control Traffic Vol by Lane LT Vol Through Vol RT Vol Lane Flow Rate Geometry Grp Degree of Util (X) Departure Headway (Hd) Convergence, Y/N Cap		42% Stop 195 103 10 82 195 1 0.388 7.384 Yes 491	20% Stop 539 21 410 108 539 1 0.884 6.08 Yes 598	13% Stop 625 74 469 82 625 1 1.048 6.038 Yes 606	16% 36% Stop 83 40 13 30 83 1 0.177 7.952 Yes 454							
Vol Right, % Sign Control Traffic Vol by Lane LT Vol Through Vol RT Vol Lane Flow Rate Geometry Grp Degree of Util (X) Departure Headway (Hd) Convergence, Y/N Cap Service Time		42% Stop 195 103 10 82 195 1 0.388 7.384 Yes 491 5.384	20% Stop 539 21 410 108 539 1 0.884 6.08 Yes 598 4.08	13% Stop 625 74 469 82 625 1 1.048 6.038 Yes 606 4.038	16% 36% Stop 83 40 13 30 83 1 0.177 7.952 Yes 454 5.952							
Vol Right, % Sign Control Traffic Vol by Lane LT Vol Through Vol RT Vol Lane Flow Rate Geometry Grp Degree of Util (X) Departure Headway (Hd) Convergence, Y/N Cap Service Time HCM Lane V/C Ratio		42% Stop 195 103 10 82 195 1 0.388 7.384 Yes 491	20% Stop 539 21 410 108 539 1 0.884 6.08 Yes 598 4.08	13% Stop 625 74 469 82 625 1 1.048 6.038 Yes 606 4.038 1.031	16% 36% Stop 83 40 13 30 83 1 0.177 7.952 Yes 454 5.952 0.183							
Vol Right, % Sign Control Traffic Vol by Lane LT Vol Through Vol RT Vol Lane Flow Rate Geometry Grp Degree of Util (X) Departure Headway (Hd) Convergence, Y/N Cap Service Time HCM Lane V/C Ratio HCM Control Delay		42% Stop 195 103 10 82 195 1 0.388 7.384 Yes 491 5.384 0.397 15	20% Stop 539 21 410 108 539 1 0.884 6.08 Yes 598 4.08 0.901 38.7	13% Stop 625 74 469 82 625 1 1.048 6.038 Yes 606 4.038 1.031 74.3	16% 36% Stop 83 40 13 30 83 1 0.177 7.952 Yes 454 5.952 0.183 12.7							
Vol Right, % Sign Control Traffic Vol by Lane LT Vol Through Vol RT Vol Lane Flow Rate Geometry Grp Degree of Util (X) Departure Headway (Hd) Convergence, Y/N Cap Service Time HCM Lane V/C Ratio		42% Stop 195 103 10 82 195 1 0.388 7.384 Yes 491 5.384 0.397	20% Stop 539 21 410 108 539 1 0.884 6.08 Yes 598 4.08	13% Stop 625 74 469 82 625 1 1.048 6.038 Yes 606 4.038 1.031	16% 36% Stop 83 40 13 30 83 1 0.177 7.952 Yes 454 5.952 0.183							

	*	-	*	•	←	*	4	†	1	-	Į.	1
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBF
Lane Configurations	*	1 >		ሻ	f >		ች	f.		ች	1>	
Traffic Volume (vph)	46	263	232	128	286	117	181	1	109	105	2	5
Future Volume (vph)	46	263	232	128	286	117	181	1	109	105	2	5
Satd. Flow (prot)	1566	1623	0	1271	1484	0	1658	1330	0	1436	1401	
Flt Permitted	0.500			0.442			0.722			0.673		
Satd. Flow (perm)	817	1623	0	592	1484	0	1260	1330	0	1011	1401	
Satd. Flow (RTOR)		65			30			109			52	
Lane Group Flow (vph)	46	495	0	128	403	0	181	110	0	105	54	
Turn Type	Perm	NA		Perm	NA		Perm	NA		Perm	NA	
Protected Phases		2			6			4			8	
Permitted Phases	2			6			4			8		
Detector Phase	2	2		6	6		4	4		8	8	
Switch Phase												
Minimum Initial (s)	10.0	10.0		10.0	10.0		10.0	10.0		10.0	10.0	
Minimum Split (s)	23.7	23.7		23.7	23.7		30.4	30.4		30.4	30.4	
Total Split (s)	77.0	77.0		77.0	77.0		43.0	43.0		43.0	43.0	
Total Split (%)	64.2%	64.2%		64.2%	64.2%		35.8%	35.8%		35.8%	35.8%	
Yellow Time (s)	4.2	4.2		4.2	4.2		3.3	3.3		3.3	3.3	
All-Red Time (s)	1.5	1.5		1.5	1.5		2.6	2.6		2.6	2.6	
Lost Time Adjust (s)	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0	
Total Lost Time (s)	5.7	5.7		5.7	5.7		5.9	5.9		5.9	5.9	
Lead/Lag												
Lead-Lag Optimize?												
Recall Mode	C-Min	C-Min		C-Min	C-Min		None	None		None	None	
Act Effct Green (s)	85.8	85.8		85.8	85.8		22.6	22.6		22.6	22.6	
Actuated g/C Ratio	0.72	0.72		0.72	0.72		0.19	0.19		0.19	0.19	
v/c Ratio	0.08	0.42		0.30	0.38		0.76	0.32		0.55	0.18	
Control Delay	7.2	8.1		9.9	8.3		65.5	9.5		53.6	11.5	
Queue Delay	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0	
Total Delay	7.2	8.1		9.9	8.3		65.5	9.5		53.6	11.5	
LOS	Α	Α		Α	Α		Е	Α		D	В	
Approach Delay		8.0			8.7			44.3			39.3	
Approach LOS		Α			Α			D			D	
Queue Length 50th (m)	2.9	35.8		9.8	30.1		40.8	0.2		22.6	0.4	
Queue Length 95th (m)	8.5	70.3		24.9	59.6		60.4	13.9		37.4	10.2	
Internal Link Dist (m)		122.9			257.3			171.4			184.1	
Turn Bay Length (m)	37.5			37.5			30.0			30.0		
Base Capacity (vph)	583	1178		423	1069		389	486		312	469	
Starvation Cap Reductn	0	0		0	0		0	0		0	0	
Spillback Cap Reductn	0	0		0	0		0	0		0	0	
Storage Cap Reductn	0	0		0	0		0	0		0	0	
Reduced v/c Ratio	0.08	0.42		0.30	0.38		0.47	0.23		0.34	0.12	
Intersection Summary												
Cycle Length: 120												
Actuated Cycle Length: 120 Offset: 0 (0%), Referenced		CDTI and	C-WDTI	Ctart of	Croon							

Offset: 0 (0%), Referenced to phase 2:EBTL and 6:WBTL, Start of Green Natural Cycle: 60

Scenario 1 3850 Cambrian Road 11:59 pm 10/19/2022 2029 Future Background

Control Type: Actuated-Coordinated

2029 Future Background SAT Peak Hour

Maximum v/c Ratio: 0.76	
Intersection Signal Delay: 18.4	Intersection LOS: B
Intersection Capacity Utilization 69.6%	ICU Level of Service C
Analysis Period (min) 15	

Splits and Phases: 2: Elevation/Apolune & Cambrian

→ Ø2 (R)	₫ 04
77 s	43 s
₩ Ø6 (R)	₩ Ø8
77 s	43 s

HCM 2010 TWSC 5: Temporary Driveway & Cambrian 2029 Future Background SAT Peak Hour

Intersection	_					
Int Delay, s/veh	1.4					
Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations	₽			ની	Υ	
Traffic Vol, veh/h	154	66	7	205	44	10
Future Vol, veh/h	154	66	7	205	44	10
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage	, # 0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	100	100	100	100	100	100
Heavy Vehicles, %	2	2	2	2	2	2
Mymt Flow	154	66	7	205	44	10
Matagh Cara	Antona.		M-:0		Minand	
	Major1		Major2		Minor1	40=
Conflicting Flow All	0	0	220	0	406	187
Stage 1	-	-	-	-	187	-
Stage 2	-	-	-	-	219	-
Critical Hdwy	-	-	4.12	-	6.42	6.22
Critical Hdwy Stg 1	-	-	-	-	5.42	-
Critical Hdwy Stg 2	-	-	-	-	5.42	-
Follow-up Hdwy	-	-			3.518	
Pot Cap-1 Maneuver	-	-	1349	-	601	855
Stage 1	-	-	-	-	845	-
Stage 2	-	-	-	-	817	-
Platoon blocked, %	-	-		-		
Mov Cap-1 Maneuver	-	-	1349	-	597	855
Mov Cap-2 Maneuver	-	-	-	-	597	-
Stage 1	-	-	-	-	845	-
Stage 2		-	-	-	812	-
3						
A	EB		MD		ND	
Approach			WB		NB	
HCM Control Delay, s	0		0.3		11.2	
HCM LOS					В	
Minor Lane/Major Mvm	t I	NBLn1	EBT	EBR	WBL	WBT
Capacity (veh/h)		632	-		1349	-
HCM Lane V/C Ratio		0.085				
HCM Control Delay (s)		11.2			7.7	0
HCM Lane LOS		В			Α.	A
HCM 95th %tile Q(veh)		0.3			0	
HOW SOUL WILLE CO (VEIL)		0.3	-	-	U	-

Appendix J

Synchro Intersection Worksheets – 2024 Future Total Conditions



Intersection												
Intersection Delay, s/veh	54.5											
Intersection LOS	F											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBI
Lane Configurations		4			4			4			4	
Traffic Vol, veh/h	24	427	85	49	341	51	181	50	104	71	16	4
Future Vol, veh/h	24	427	85	49	341	51	181	50	104	71	16	4
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.0
Heavy Vehicles, %	7	10	6	16	9	4	2	10	4	3	6	
Mvmt Flow	24	427	85	49	341	51	181	50	104	71	16	4
Number of Lanes	0	1	0	0	1	0	0	1	0	0	1	(
Approach	EB			WB			NB			SB		
Opposing Approach	WB			EB			SB			NB		
Opposing Lanes	1			1			1			1		
Conflicting Approach Left	SB			NB			EB			WB		
Conflicting Lanes Left	1			1			1			1		
Conflicting Approach Right	NB			SB			WB			EB		
Conflicting Lanes Right	1			1			1			1		
HCM Control Delay	85.5			48.5			28.1			16		
HCM LOS	F			Е			D			С		
Lane		NBLn1	EBLn1	WBLn1	SBLn1							
Vol Left, %		54%	4%	11%	53%							
Vol Thru, %		15%	80%	77%	12%							
Vol Right, %		31%	16%	12%	36%							
Sign Control		Stop	Stop	Stop								
Traffic Vol by Lane					Stop							
		335	536	441	Stop 135							
LT Vol		335 181										
			536	441	135							
LT Vol		181	536 24	441 49	135 71							
LT Vol Through Vol		181 50	536 24 427	441 49 341	135 71 16							
LT Vol Through Vol RT Vol Lane Flow Rate		181 50 104	536 24 427 85	441 49 341 51	135 71 16 48							
LT Vol Through Vol RT Vol Lane Flow Rate Geometry Grp		181 50 104 335	536 24 427 85 536	441 49 341 51 441	135 71 16 48 135							
LT Vol Through Vol RT Vol Lane Flow Rate Geometry Grp Degree of Util (X)		181 50 104 335	536 24 427 85 536 1	441 49 341 51 441	135 71 16 48 135							
LT Vol Through Vol RT Vol Lane Flow Rate Geometry Grp		181 50 104 335 1 0.712	536 24 427 85 536 1	441 49 341 51 441 1 0.903	135 71 16 48 135 1 0.321							
LT Vol Through Vol RT Vol Lane Flow Rate Geometry Grp Degree of Util (X) Departure Headway (Hd) Convergence, Y/N		181 50 104 335 1 0.712 7.888	536 24 427 85 536 1 1.066 7.158	441 49 341 51 441 1 0.903 7.601	135 71 16 48 135 1 0.321 8.895							
LT Vol Through Vol RT Vol Lane Flow Rate Geometry Grp Degree of Util (X) Departure Headway (Hd)		181 50 104 335 1 0.712 7.888 Yes	536 24 427 85 536 1 1.066 7.158 Yes	441 49 341 51 441 1 0.903 7.601 Yes	135 71 16 48 135 1 0.321 8.895 Yes							
LT Vol Through Vol RT Vol Lane Flow Rate Geometry Grp Degree of Util (X) Departure Headway (Hd) Convergence, Y/N Cap		181 50 104 335 1 0.712 7.888 Yes 462	536 24 427 85 536 1 1.066 7.158 Yes 509	441 49 341 51 441 1 0.903 7.601 Yes 481	135 71 16 48 135 1 0.321 8.895 Yes 406							
LT Vol Through Vol RT Vol Lane Flow Rate Geometry Grp Degree of Util (X) Departure Headway (Hd) Convergence, Y/N Cap Service Time HCM Lane V/C Ratio		181 50 104 335 1 0.712 7.888 Yes 462 5.888 0.725	536 24 427 85 536 1 1.066 7.158 Yes 509 5.158 1.053	441 49 341 51 441 1 0.903 7.601 Yes 481 5.601 0.917	135 71 16 48 135 1 0.321 8.895 Yes 406 6.895 0.333							
LT Vol Through Vol RT Vol Lane Flow Rate Geometry Grp Degree of Util (X) Departure Headway (Hd) Convergence, Y/N Cap Service Time		181 50 104 335 1 0.712 7.888 Yes 462 5.888	536 24 427 85 536 1 1.066 7.158 Yes 509 5.158	441 49 341 51 441 1 0.903 7.601 Yes 481 5.601	135 71 16 48 135 1 0.321 8.895 Yes 406 6.895							

	•	-	\rightarrow	•	←	*	4	†	1	-	ļ	4
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	*	1>		7	₽		ሻ	f)		ች	1>	
Traffic Volume (vph)	9	247	90	34	441	80	189	0	71	142	0	32
Future Volume (vph)	9	247	90	34	441	80	189	0	71	142	0	32
Satd, Flow (prot)	1658	1474	0	1658	1485	0	1658	1483	0	1492	1483	0
Flt Permitted	0.408			0.548			0.736			0.711		
Satd. Flow (perm)	712	1474	0	956	1485	0	1284	1483	0	1117	1483	0
Satd. Flow (RTOR)		36			18			567			335	
Lane Group Flow (vph)	9	337	0	34	521	0	189	71	0	142	32	0
Turn Type	Perm	NA		Perm	NA		Perm	NA		Perm	NA	
Protected Phases		2			6			4			8	
Permitted Phases	2			6			4			8		
Detector Phase	2	2		6	6		4	4		8	8	
Switch Phase												
Minimum Initial (s)	10.0	10.0		10.0	10.0		10.0	10.0		10.0	10.0	
Minimum Split (s)	23.7	23.7		23.7	23.7		30.4	30.4		30.4	30.4	
Total Split (s)	39.6	39.6		39.6	39.6		30.4	30.4		30.4	30.4	
Total Split (%)	56.6%	56.6%		56.6%	56.6%		43.4%	43.4%		43.4%	43.4%	
Yellow Time (s)	4.2	4.2		4.2	4.2		3.3	3.3		3.3	3.3	
All-Red Time (s)	1.5	1.5		1.5	1.5		2.6	2.6		2.6	2.6	
Lost Time Adjust (s)	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0	
Total Lost Time (s)	5.7	5.7		5.7	5.7		5.9	5.9		5.9	5.9	
Lead/Lag	0.1	0.7		0.1	0.1		0.0	0.0		0.0	0.0	
Lead-Lag Optimize?												
Recall Mode	C-Min	C-Min		C-Min	C-Min		None	None		None	None	
Act Effct Green (s)	42.1	42.1		42.1	42.1		16.3	16.3		16.3	16.3	
Actuated g/C Ratio	0.60	0.60		0.60	0.60		0.23	0.23		0.23	0.23	
v/c Ratio	0.02	0.37		0.06	0.58		0.63	0.09		0.55	0.05	
Control Delay	8.3	9.1		8.2	13.1		32.9	0.03		30.4	0.03	
Queue Delay	0.0	0.0		0.0	0.0		0.0	0.2		0.0	0.2	
Total Delay	8.3	9.1		8.2	13.1		32.9	0.0		30.4	0.0	
LOS	0.5 A	9.1 A		Ο.2	В		32.9 C	0.2 A		30.4 C	Α.2	
Approach Delay	A	9.1		А	12.8		U	24.0		C	24.9	
Approach LOS		9.1 A			12.0 B			24.0 C			24.9 C	
Queue Length 50th (m)	0.4	17.0		1.6	34.3		22.6	0.0		16.6	0.0	
	2.7	43.9		6.6	84.1		35.0	0.0		27.6	0.0	
Queue Length 95th (m) Internal Link Dist (m)	2.1	192.0		0.0	170.7		35.0	97.9		21.0	184.1	
	37.5	192.0		37.5	170.7		30.0	97.9		30.0	104.1	
Turn Bay Length (m)		004			004			007			700	
Base Capacity (vph)	428 0	901		575	901		449	887 0		390	736	
Starvation Cap Reductn	-	0		0	-		0	0		0	0	
Spillback Cap Reductn	0	0		0	0		0	0		0	0	
Storage Cap Reductn		-		-	-		-	-				
Reduced v/c Ratio	0.02	0.37		0.06	0.58		0.42	0.08		0.36	0.04	
Intersection Summary			_	_	_	_					_	
Cycle Length: 70												
Actuated Cycle Length: 70												
Offset: 0 (0%), Referenced	to phase 2	EBTL and	6:WBTL	. Start of	Green							
Natural Cycle: 60	- P	2.23110		,								
Control Type: Actuated-Coo	ordinated											
7												

2024 Future Total AM Peak Hour

Maximum v/c Ratio: 0.63	
Intersection Signal Delay: 15.6	Intersection LOS: B
Intersection Capacity Utilization 57.2%	ICU Level of Service B
Analysis Period (min) 15	

Splits and Phases: 2: Elevation/Apolune & Cambrian

opiilo anu rhases.	2. Elevation/Apolune & Cambrian	
→ ø2 (R)		↑ ø4
39.6 s		30.4s
Ø6 (R)		₩ Ø8
39.6 s		30.4 s

HCM 2010 TWSC 5: Temporary Driveway & Cambrian 2024 Future Total AM Peak Hour

Intersection						
Int Delay, s/veh	0.4					
Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations	1>	LDI	TTDL	4	W	HUIT
Traffic Vol., veh/h	437	22	9	548	15	6
Future Vol. veh/h	437	22	9	548	15	6
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage	, # 0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	100	100	100	100	100	100
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	437	22	9	548	15	6
Major/Minor N	Major1		Major2		Minor1	
Conflicting Flow All	0	0	459	0	1014	448
Stage 1	-	-	-	-	448	-
Stage 2					566	
Critical Hdwy	-	-	4.12		6.42	6.22
Critical Hdwy Stg 1	-	-	-	-	5.42	-
Critical Hdwy Stg 2	-	-	-	-	5.42	-
Follow-up Hdwy	-	-	2.218	-	3.518	3.318
Pot Cap-1 Maneuver	-	-	1102	-	264	611
Stage 1	-	-	-	-	644	-
Stage 2	-	-	-	-	568	-
Platoon blocked, %	-	-		-		
Mov Cap-1 Maneuver	-	-	1102	-	261	611
Mov Cap-2 Maneuver	-	-	-	-	261	-
Stage 1	-	-	-	-	644	-
Stage 2	-	-	-	-	561	-
Approach	EB		WB		NB	
HCM Control Delay, s	0		0.1		17.4	
HCM LOS	0		0.1		17.4 C	
					J	
					1110	14/50
Minor Lane/Major Mvm	t I	NBLn1	EBT	EBR	WBL	WBT
Capacity (veh/h)		312	-	-	1102	-
HCM Lane V/C Ratio		0.067	-	-		-
HCM Control Delay (s)		17.4	-	-	8.3	0
HCM Lane LOS		С	-	-	A	Α

0.2 - - 0 -

Scenario 1 3850 Cambrian Road 11:59 pm 10/19/2022 2024 Future Total

Intersection						
Int Delay, s/veh	0.7					
Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations		4	ĵ.		W	
Traffic Vol, veh/h	16	443	531	32	16	24
Future Vol. veh/h	16	443	531	32	16	24
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-		-	None
Storage Length		-		-	0	-
Veh in Median Storage	.# -	0	0	_	0	_
Grade, %	-	0	0		0	
Peak Hour Factor	100	100	100	100	100	100
Heavy Vehicles, %	2	2	2	2	2	2
Mymt Flow	16	443	531	32	16	24
			-			
Malaghtinas	Madaud		4-:0		M:0	
	Major1		Major2		Minor2	
Conflicting Flow All	563	0	-	0	1022	547
Stage 1	-	-	-	-	547	-
Stage 2	-	-	-	-	475	-
Critical Hdwy	4.12	-	-	-	6.42	6.22
Critical Hdwy Stg 1	-	-	-	-	5.42	-
Critical Hdwy Stg 2	-	-	-	-	5.42	-
Follow-up Hdwy	2.218	-	-	-	3.518	
Pot Cap-1 Maneuver	1008	-	-	-	261	537
Stage 1	-	-	-	-	580	-
Stage 2	-	-	-	-	626	-
Platoon blocked, %		-	-	-		
Mov Cap-1 Maneuver	1008	-	-	-	256	537
Mov Cap-2 Maneuver	-	-	-	-	256	-
Stage 1	-	-	-	-	568	-
Stage 2	-	-	-	-	626	-
Approach	EB		WB		SB	
HCM Control Delay, s	0.3		0		15.8	
HCM LOS	0.5		U		13.0 C	
I IOW LOG					U	
Minor Lane/Major Mvm	nt	EBL	EBT	WBT	WBR	SBLn1
Capacity (veh/h)		1008	-	-	-	373
HCM Lane V/C Ratio		0.016	-	-	-	0.107
HCM Control Delay (s)		8.6	0	-	-	15.8
HCM Lane LOS		Α	Α	-	-	С
LICALOCAL OVAILA OVACAL		٥				0.4

Intersection												
Intersection Delay, s/veh	56.7											
Intersection LOS	F											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SB
Lane Configurations		43-			4			4			4	
Traffic Vol, veh/h	36	416	142	123	399	76	113	15	103	38	12	2
Future Vol, veh/h	36	416	142	123	399	76	113	15	103	38	12	2
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.0
Heavy Vehicles, %	2	2	2	2	2	2	2	2	7	2	2	
Mvmt Flow	36	416	142	123	399	76	113	15	103	38	12	2
Number of Lanes	0	1	0	0	1	0	0	1	0	0	1	
Approach	EB			WB			NB			SB		
Opposing Approach	WB			EB			SB			NB		
Opposing Lanes	1			1			1			1		
Conflicting Approach Left	SB			NB			EB			WB		
Conflicting Lanes Left	1			1			1			1		
Conflicting Approach Right	NB			SB			WB			EB		
Conflicting Lanes Right	1			1			1			1		
HCM Control Delay	60.5			74.1			16.9			13.1		
HCM LOS	F			F			С			В		
Lane		NBLn1	EBLn1	WBLn1	SBLn1							
Vol Left, %		49%	6%	21%	48%							
Vol Thru, %		6%	70%	67%	15%							
Vol Right, %		45%	24%	13%	37%							
Sign Control		Stop	Stop	Stop	Stop							
Traffic Vol by Lane		231	594	598	79							
LT Vol		113	36	123	38							
Through Vol		15	416	399	12							
RT Vol		103	142	76	29							
Lane Flow Rate		231	594	598	79							
Geometry Grp		1	1	1	1							
Degree of Util (X)		0.465	0.993	1.043	0.178							
Departure Headway (Hd)		7.518	6.248	6.279	8.343							
Convergence, Y/N		Yes	Yes	Yes	Yes							
Cap		483	588	580	433							
Service Time		5.518	4.248	4.286	6.343							
HCM Lane V/C Ratio		0.478	1.01	1.031	0.182							
HCM Control Delay		16.9	60.5	74.1	13.1							
HCM Lane LOS		С	F	F	В							
HCM 95th-tile Q		2.4	14.4	16.6	0.6							

0 - - - 0.4

2024 Future Total PM Peak Hour

	•	-	*	1	-	*	1	†	1	1	↓	4
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	ሻ	î,		ሻ	ĵ,		7	ĵ.		ሻ	- 1>	
Traffic Volume (vph)	32	446	177	61	412	105	136	0	46	90	0	18
Future Volume (vph)	32	446	177	61	412	105	136	0	46	90	0	18
Satd. Flow (prot)	1658	1670	0	1658	1511	0	1658	1483	0	1492	1483	0
Flt Permitted	0.441			0.382			0.746			0.727		
Satd. Flow (perm)	765	1670	0	667	1511	0	1302	1483	0	1134	1483	0
Satd. Flow (RTOR)		33			21			442			463	
Lane Group Flow (vph)	32	623	0	61	517	0	136	46	0	90	18	0
Turn Type	Perm	NA		Perm	NA		Perm	NA		Perm	NA	
Protected Phases		2			6			4			8	
Permitted Phases	2			6			4			8		
Detector Phase	2	2		6	6		4	4		8	8	
Switch Phase												
Minimum Initial (s)	10.0	10.0		10.0	10.0		10.0	10.0		10.0	10.0	
Minimum Split (s)	23.7	23.7		23.7	23.7		30.4	30.4		30.4	30.4	
Total Split (s)	82.0	82.0		82.0	82.0		38.0	38.0		38.0	38.0	
Total Split (%)	68.3%	68.3%		68.3%	68.3%		31.7%	31.7%		31.7%	31.7%	
Yellow Time (s)	4.2	4.2		4.2	4.2		3.3	3.3		3.3	3.3	
All-Red Time (s)	1.5	1.5		1.5	1.5		2.6	2.6		2.6	2.6	
Lost Time Adjust (s)	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0	
Total Lost Time (s)	5.7	5.7		5.7	5.7		5.9	5.9		5.9	5.9	
Lead/Lag												
Lead-Lag Optimize?												
Recall Mode	C-Min	C-Min		C-Min	C-Min		None	None		None	None	
Act Effct Green (s)	90.6	90.6		90.6	90.6		17.8	17.8		17.8	17.8	
Actuated g/C Ratio	0.76	0.76		0.76	0.76		0.15	0.15		0.15	0.15	
v/c Ratio	0.06	0.49		0.12	0.45		0.70	0.08		0.54	0.03	
Control Delay	5.2	7.7		5.7	7.4		67.0	0.3		57.6	0.1	
Queue Delay	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0	
Total Delay	5.2	7.7		5.7	7.4		67.0	0.3		57.6	0.1	
LOS	Α	Α		Α	Α		Е	Α		Е	Α	
Approach Delay		7.5			7.3			50.1			48.0	
Approach LOS		Α			Α			D			D	
Queue Length 50th (m)	1.7	46.2		3.3	37.1		30.8	0.0		19.8	0.0	
Queue Length 95th (m)	5.4	86.8		9.3	71.3		48.8	0.0		34.4	0.0	
Internal Link Dist (m)		122.9			169.1			171.4			184.1	
Turn Bay Length (m)	37.5			37.5			30.0			30.0		
Base Capacity (vph)	577	1268		503	1145		348	720		303	735	
Starvation Cap Reductn	0	0		0	0		0	0		0	0	
Spillback Cap Reductn	0	0		0	0		0	0		0	0	
Storage Cap Reductn	0	0		0	0		0	0		0	0	
Reduced v/c Ratio	0.06	0.49		0.12	0.45		0.39	0.06		0.30	0.02	
Intersection Summary												
Cycle Length: 120												

Cycle Length: 120
Actuated Cycle Length: 120
Offset: 0 (0%), Referenced to phase 2:EBTL and 6:WBTL, Start of Green

Natural Cycle: 60

Control Type: Actuated-Coordinated

Scenario 1 3850 Cambrian Road 11:59 pm 10/19/2022 2024 Future Total

Synchro 11 Report

Page 3

Lanes, Volumes, Timings 2: Elevation/Apolune & Cambrian 2024 Future Total PM Peak Hour

Maximum v/c Ratio: 0.70 Intersection Signal Delay: 15.4 Intersection LOS: B Intersection Capacity Utilization 73.5% ICU Level of Service D Analysis Period (min) 15 Splits and Phases: 2: Elevation/Apolune & Cambrian **↑**04 -**4**ø2 (R) ₩ Ø6 (R)

Intersection						
Int Delay, s/veh	0.9					
Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations	1>	LDIX	WUL	4	W	NUN
Traffic Vol, veh/h	529	57	6	545	38	9
Future Vol. veh/h	529	57	6	545	38	9
Conflicting Peds, #/hr	0	0	0	040	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	- Otop	None
Storage Length		-		-	0	-
Veh in Median Storage				0	0	
Grade, %	0			0	0	
Peak Hour Factor	100	100	100	100	100	100
Heavy Vehicles, %	2	2	2	2	2	2
Mymt Flow	529	57	6	545	38	9
WWW. TIOW	020	01	0	040	30	J
	Major1		Major2		Minor1	
Conflicting Flow All	0	0	586	0		558
Stage 1	-	-	-	-	558	-
Stage 2	-	-	-	-	557	-
Critical Hdwy	-	-	4.12	-	6.42	6.22
Critical Hdwy Stg 1	-	-	-	-	5.42	-
Critical Hdwy Stg 2	-	-	-	-	5.42	-
Follow-up Hdwy	-	-	2.218		3.518	
Pot Cap-1 Maneuver	-	-	989	-	230	529
Stage 1	-	-	-	-	573	-
Stage 2	-	-	-	-	574	-
Platoon blocked, %	-	-		-		
Mov Cap-1 Maneuver	-	-	989	-	228	529
Mov Cap-2 Maneuver	-	-	-	-	228	-
Stage 1	-	-	-	-	573	-
Stage 2	-	-	-	-	569	-
Approach	EB		WB		NB	
	0		0.1		22.2	
HCM Control Delay, s HCM LOS	U		0.1		22.2 C	
HOW LOS					U	
Minor Lane/Major Mvm	it 1	NBLn1	EBT	EBR	WBL	WBT
Capacity (veh/h)		256	-	-	989	-
HCM Lane V/C Ratio		0.184	-	-	0.006	-
HCM Control Delay (s)		22.2	-	-	8.7	0
HCM Lane LOS		С	-	-	Α	Α

Intersection						
Int Delay, s/veh	1.9					
Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations	LDL	4	₩ DI	ושוו	₩.	אושט
Traffic Vol, veh/h	36	545	520	65	'Y' 41	59
Future Vol, veh/h	36	545	520	65	41	59
	0	040	0	00	0	0
Conflicting Peds, #/hr						_
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage		0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	100	100	100	100	100	100
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	36	545	520	65	41	59
MaineMines	Malaut	_	4-10	_	M:	
	Major1		Major2		Minor2	
Conflicting Flow All	585	0	-	0	1170	553
Stage 1	-	-	-	-	553	-
Stage 2	-	-	-	-	617	-
Critical Hdwy	4.12	-	-	-	6.42	6.22
Critical Hdwy Stg 1	-	-	-	-	5.42	-
Critical Hdwy Stg 2	-	-	-	-	5.42	-
Follow-up Hdwy	2.218	-	-			3.318
Pot Cap-1 Maneuver	990	-	-	-	213	533
Stage 1	-	-	-		576	-
Stage 2	-		_		538	
Platoon blocked, %			-		000	
Mov Cap-1 Maneuver	990				202	533
Mov Cap-1 Maneuver	990	-			202	555
Stage 1	-	-	-	-	546	-
Stage 2	-	-	-	-	538	-
Approach	EB		WB		SB	
HCM Control Delay, s	0.5		0		21.4	
HCM LOS	0.0				C	
					0	
Minor Lane/Major Mvm	nt	EBL	EBT	WBT	WBR	SBLn1
Capacity (veh/h)		990	-	-	-	319
HCM Lane V/C Ratio		0.036	-	-	-	0.313
HCM Control Delay (s))	8.8	0	-	-	21.4
HCM Lane LOS		A	A			C
HCM 95th %tile Q(veh)	0.1	-		-	1.3

HCM 95th %tile Q(veh) 0.7 - - 0 -

Intersection												
Intersection Delay, s/veh	23.8											
Intersection LOS	С											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		4			4			4			4	
Traffic Vol, veh/h	20	339	90	69	387	82	88	10	79	40	13	29
Future Vol. veh/h	20	339	90	69	387	82	88	10	79	40	13	29
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Heavy Vehicles, %	2	2	2	7	2	2	2	2	4	2	8	2
Mymt Flow	20	339	90	69	387	82	88	10	79	40	13	29
Number of Lanes	0	1	0	0	1	0	0	1	0	0	1	0
Approach	EB			WB			NB			SB		
Opposing Approach	WB			EB			SB			NB		
Opposing Lanes	1			1			1			1		
Conflicting Approach Left	SB			NB			EB			WB		
Conflicting Lanes Left	1			1			1			1		
Conflicting Approach Right	NB			SB			WB			EB		
Conflicting Lanes Right	1			1			1			1		
HCM Control Delay	21.1			31.4			13			11.5		
HCM LOS	С			D			В			В		
HCM LOS	С			D			В			В		
	С	NBLn1	EBLn1	D WBLn1	SBLn1		В			В		
Lane	С	NBLn1 50%	EBLn1 4%		SBLn1 49%		В			В		
Lane Vol Left, %	С			WBLn1			В			В		
Lane Vol Left, % Vol Thru, %	C	50%	4%	WBLn1 13%	49%		В			В		
Lane Vol Left, % Vol Thru, % Vol Right, %	C	50% 6%	4% 76%	WBLn1 13% 72%	49% 16%		В			В		
Lane Vol Left, % Vol Thru, % Vol Right, % Sign Control	С	50% 6% 45%	4% 76% 20%	WBLn1 13% 72% 15%	49% 16% 35%		В			В		
HCM LOS Lane Vol Left, % Vol Thru, % Vol Right, % Sign Control Traffic Vol by Lane LT Vol	С	50% 6% 45% Stop	4% 76% 20% Stop 449 20	WBLn1 13% 72% 15% Stop	49% 16% 35% Stop		В			В		
Lane Vol Left, % Vol Thru, % Vol Right, % Sign Control Traffic Vol by Lane LT Vol	С	50% 6% 45% Stop 177 88 10	4% 76% 20% Stop 449 20 339	WBLn1 13% 72% 15% Stop 538 69 387	49% 16% 35% Stop 82 40 13		В			В		
Lane Vol Left, % Vol Thru, % Vol Right, % Sign Control Traffic Vol by Lane LT Vol Through Vol	C	50% 6% 45% Stop 177 88	4% 76% 20% Stop 449 20	WBLn1 13% 72% 15% Stop 538 69	49% 16% 35% Stop 82 40		В			В		
Lane Vol Left, % Vol Tru, % Vol Right, % Sign Control Traffic Vol by Lane LT Vol TrTrough Vol RT Vol	C	50% 6% 45% Stop 177 88 10	4% 76% 20% Stop 449 20 339 90 449	WBLn1 13% 72% 15% Stop 538 69 387 82 538	49% 16% 35% Stop 82 40 13		В			В		
Lane Vol Left, % Vol Thru, % Vol Right, % Sign Control Traffic Vol by Lane LT Vol Through Vol RT Vol Lane Flow Rate Geometry Grp	C	50% 6% 45% Stop 177 88 10 79 177	4% 76% 20% Stop 449 20 339 90 449	WBLn1 13% 72% 15% Stop 538 69 387 82 538 1	49% 16% 35% Stop 82 40 13 29 82		В			В		
Lane Vol Left, % Vol Thru, % Vol Right, % Sign Control Traffic Vol by Lane LT Vol Through Vol RT Vol Lane Flow Rate	C	50% 6% 45% Stop 177 88 10 79 177 1	4% 76% 20% Stop 449 20 339 90 449 1	WBLn1 13% 72% 15% Stop 538 69 387 82 538 1 0.842	49% 16% 35% Stop 82 40 13 29 82 1		В			В		
Lane Vol Left, % Vol Tript, % Vol Right, % Sign Control Traffic Vol by Lane LT Vol Through Vol RT Vol Lane Flow Rate Geometry Grp Degree of Util (X) Departure Headway (Hd)	C	50% 6% 45% Stop 177 88 10 79 177	4% 76% 20% Stop 449 20 339 90 449	WBLn1 13% 72% 15% Stop 538 69 387 82 538 1	49% 16% 35% Stop 82 40 13 29 82		В			В		
Lane Vol Left, % Vol Tript, % Vol Right, % Sign Control Traffic Vol by Lane LT Vol Through Vol RT Vol Lane Flow Rate Geometry Grp Degree of Util (X) Departure Headway (Hd)	C	50% 6% 45% Stop 177 88 10 79 177 1	4% 76% 20% Stop 449 20 339 90 449 1	WBLn1 13% 72% 15% Stop 538 69 387 82 538 1 0.842	49% 16% 35% Stop 82 40 13 29 82 1		В			В		
Lane Vol Left, % Vol Thru, % Vol Right, % Sign Control Traffic Vol by Lane LT Vol Through Vol RT Vol Lane Flow Rate Geometry Grp Degree of Util (X) Convergence, Y/N Cap	C	50% 6% 45% Stop 177 88 10 79 177 1 0.328 6.664 Yes 538	4% 76% 20% Stop 449 20 339 90 449 1 0.705 5.649 Yes 642	WBLn1 13% 72% 15% Stop 538 69 387 82 538 1 0.842 5.634	49% 16% 35% Stop 82 40 13 29 82 1 0.161 7.054		В			В		
Lane Vol Left, % Vol Thru, % Vol Right, % Sign Control Traffic Vol by Lane LT Vol Through Vol RT Vol Lane Flow Rate Geometry Grp Degree of Util (X) Convergence, Y/N Cap	C	50% 6% 45% Stop 177 88 10 79 177 1 0.328 6.664 Yes 538 4.719	4% 76% 20% Stop 449 20 339 90 449 1 0.705 5.649 Yes	WBLn1 13% 72% 15% Stop 538 69 387 82 538 1 0.842 5.634 Yes	49% 16% 35% Stop 82 40 13 29 82 1 0.161 7.054 Yes		В			В		
Lane Vol Left, % Vol Tinu, % Vol Right, % Sign Control Traffic Vol by Lane LT Vol Through Vol RT Vol Lane Flow Rate Geometry Grp Degree of Util (X) Departure Headway (Hd) Convergence, Y/N Cap Service Time	C	50% 6% 45% Stop 177 88 10 79 177 1 0.328 6.664 Yes 538	4% 76% 20% Stop 449 20 339 90 449 1 0.705 5.649 Yes 642	WBLn1 13% 72% Stop 538 69 387 82 538 1 0.842 5.634 Yes 646	49% 16% 35% Stop 82 40 13 29 82 1 0.161 7.054 Yes 507		В			В		
Lane Vol Left, % Vol Tirnu, % Vol Right, % Sign Control Traffic Vol by Lane LT Vol Through Vol RT Vol Lane Flow Rate Geometry Grp Degree of Util (X) Departure Headway (Hd) Convergence, Y/N Cap Service Time HCM Lane V/C Ratio	C	50% 6% 45% Stop 177 88 10 79 177 1 0.328 6.664 Yes 538 4.719	4% 76% 20% Stop 449 20 339 90 449 1 0.705 5.649 Yes 642 3.667	WBLn1 13% 72% 15% Stop 538 69 387 82 538 1 0.842 5.634 Yes 646 3.649	49% 16% 35% Stop 82 40 13 29 82 1 0.161 7.054 Yes 507 5.12		В			В		
Lane Vol Left, % Vol Thru, % Vol Right, % Sign Control Traffic Vol by Lane LT Vol Through Vol RT Vol Lane Flow Rate Geometry Grp Degree of Util (X)	C	50% 6% 45% Stop 177 88 10 79 177 1 0.328 6.664 Yes 538 4.719 0.329	4% 76% 20% Stop 449 20 339 90 449 1 0.705 5.649 Yes 642 3.667 0.699	WBLn1 13% 72% 15% Stop 538 69 387 82 538 1 0.842 5.634 Yes 646 3.649 0.833	49% 16% 35% Stop 82 40 13 29 82 1 0.161 7.054 Yes 507 5.12 0.162		В			В		

	→	\rightarrow	*	1	+	•	1	1	1	-	Į.	1
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBF
Lane Configurations	*	- 1>		ሻ	f)		ሻ	ĵ.		ሻ	f)	
Traffic Volume (vph)	38	249	160	78	271	91	128	1	69	75	2	4
Future Volume (vph)	38	249	160	78	271	91	128	1	69	75	2	45
Satd. Flow (prot)	1566	1642	0	1271	1496	0	1658	1332	0	1436	1402	(
Flt Permitted	0.536			0.506			0.726			0.711		
Satd. Flow (perm)	875	1642	0	677	1496	0	1267	1332	0	1067	1402	(
Satd. Flow (RTOR)		48			25			69			45	
Lane Group Flow (vph)	38	409	0	78	362	0	128	70	0	75	47	(
Turn Type	Perm	NA		Perm	NA		Perm	NA		Perm	NA	
Protected Phases		2			6			4			8	
Permitted Phases	2			6	_		4	•		8	_	
Detector Phase	2	2		6	6		4	4		8	8	
Switch Phase	=	=		-	-					-	-	
Minimum Initial (s)	10.0	10.0		10.0	10.0		10.0	10.0		10.0	10.0	
Minimum Split (s)	23.7	23.7		23.7	23.7		30.4	30.4		30.4	30.4	
Total Split (s)	77.0	77.0		77.0	77.0		43.0	43.0		43.0	43.0	
Total Split (%)	64.2%	64.2%		64.2%	64.2%		35.8%	35.8%		35.8%	35.8%	
Yellow Time (s)	4.2	4.2		4.2	4.2		3.3	3.3		3.3	3.3	
All-Red Time (s)	1.5	1.5		1.5	1.5		2.6	2.6		2.6	2.6	
Lost Time Adjust (s)	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0	
Total Lost Time (s)	5.7	5.7		5.7	5.7		5.9	5.9		5.9	5.9	
Lead/Lag	5.1	5.7		5.1	5.1		5.5	3.3		5.5	5.5	
Lead-Lag Optimize?												
Recall Mode	C-Min	C-Min		C-Min	C-Min		None	None		None	None	
Act Effct Green (s)	91.0	91.0		91.0	91.0		17.4	17.4		17.4	17.4	
					0.76							
Actuated g/C Ratio	0.76	0.76		0.76	0.76		0.14	0.14		0.14	0.14	
				0.15						56.1		
Control Delay	5.0	5.4		5.7	5.7		67.4	12.7			14.4	
Queue Delay	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0	
Total Delay	5.0	5.4		5.7	5.7		67.4	12.7		56.1	14.4	
LOS	Α	Α		Α	A		Е	В		Е	В	
Approach Delay		5.4			5.7			48.1			40.1	
Approach LOS		Α			Α			D			D	
Queue Length 50th (m)	2.0	22.7		4.3	21.3		29.0	0.2		16.5	0.4	
Queue Length 95th (m)	6.0	44.7		11.5	42.3		46.7	12.3		29.9	10.4	
Internal Link Dist (m)		122.9			166.9			171.4			184.1	
Turn Bay Length (m)	37.5			37.5			30.0			30.0		
Base Capacity (vph)	663	1256		513	1140		391	459		329	464	
Starvation Cap Reductn	0	0		0	0		0	0		0	0	
Spillback Cap Reductn	0	0		0	0		0	0		0	0	
Storage Cap Reductn	0	0		0	0		0	0		0	0	
Reduced v/c Ratio	0.06	0.33		0.15	0.32		0.33	0.15		0.23	0.10	
Intersection Summary												
Cycle Length: 120												
Actuated Cycle Length: 120)											

Offset: 0 (0%), Referenced to phase 2:EBTL and 6:WBTL, Start of Green

Natural Cycle: 60

Control Type: Actuated-Coordinated

Lanes, Volumes, Timings

2: Elevation/Apolune & Cambrian

2024 Future Future SAT Peak Hour

Maximum v/c Ratio: 0.70	
Intersection Signal Delay: 16.0	Intersection LOS: B
Intersection Capacity Utilization 61.0%	ICU Level of Service B
Analysis Period (min) 15	

Splits and Phases: 2: Elevation/Apolune & Cambrian

→ø2 (R)	↑ Ø4
77 s	43 s
▼ Ø6 (R)	₩ Ø8
77 s	43 s

HCM 2010 TWSC 5: Temporary Driveway & Cambrian 2024 Future Future SAT Peak Hour

Intersection						
Int Delay, s/veh	2					
Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations	1 >			લી	W	
Traffic Vol, veh/h	59	66	7	103	44	10
Future Vol, veh/h	59	66	7	103	44	10
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-		-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage	e, # 0	-	-	0	0	-
Grade, %	0			0	0	
Peak Hour Factor	100	100	100	100	100	100
Heavy Vehicles, %	2	2	2	2	2	2
Mymt Flow	59	66	7	103	44	10
Maine/Mines	Materia		M-:0		Minand	
	Major1		Major2		Minor1	
Conflicting Flow All	0	0	125	0	209	92
Stage 1	-	-	-	-	92	-
Stage 2	-	-	-	-	117	-
Critical Hdwy	-	-	4.12	-	6.42	6.22
Critical Hdwy Stg 1	-	-	-	-	5.42	-
Critical Hdwy Stg 2	-	-	-	-	5.42	-
Follow-up Hdwy	-	-	2.218	-	3.518	
Pot Cap-1 Maneuver	-	-	1462	-	779	965
Stage 1	-	-	-	-	932	-
Stage 2	-	-	-	-	908	-
Platoon blocked, %	-	-		-		
Mov Cap-1 Maneuver	-	-	1462	-	775	965
Mov Cap-2 Maneuver	-	-	-	-	775	-
Stage 1	-	-	-	-	932	-
Stage 2	-	-	-	-	903	-
Approach	EB		WB		NB	
	0		0.5		9.8	
HCM Control Delay, s HCM LOS	U		0.5		9.8 A	
HOM FOS					А	
Minor Lane/Major Mvm	nt	NBLn1	EBT	EBR	WBL	WBT
Capacity (veh/h)		804	-	-	1462	-
HCM Lane V/C Ratio		0.067	-	-	0.005	-
HCM Control Delay (s)	1	9.8	-	-	7.5	0

Minor Lane/Maior Mymt	NBLn1	EBT	EBR	WBL	WBT
Capacity (veh/h)	804	-	-	1462	-
HCM Lane V/C Ratio	0.067	-	-	0.005	-
HCM Control Delay (s)	9.8	-	-	7.5	0
HCM Lane LOS	Α	-	-	Α	Α
HCM 95th %tile Q(veh)	0.2	-	-	0	-

Intersection						
Int Delay, s/veh	2.3					
Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations	LDL	4	₩ <u>₽</u>	אטול	SDL W	אומט
	48	344	389	60		51
Traffic Vol, veh/h	48		389		56 56	51 51
Future Vol, veh/h		344		60		
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-		-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage	,# -	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	100	100	100	100	100	100
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	48	344	389	60	56	51
	Major1		Major2		Minor2	
Conflicting Flow All	449	0	-	0	859	419
Stage 1	-	-	-	-	419	-
Stage 2	-	-	-	-	440	-
Critical Hdwy	4.12	-	-	-	6.42	6.22
Critical Hdwy Stg 1	-	-	-	-	5.42	-
Critical Hdwy Stg 2	-	-	-	-	5.42	-
Follow-up Hdwy	2.218	-	-	-	3.518	3.318
Pot Cap-1 Maneuver	1111	-		-	327	634
Stage 1		-		-	664	-
Stage 2	-		-		649	-
Platoon blocked. %					0.0	
Mov Cap-1 Maneuver	1111				310	634
Mov Cap-1 Maneuver					310	004
Stage 1					629	
					649	
Stage 2	-	-	-	-	049	-
Approach	EB		WB		SB	
HCM Control Delay, s	1		0		16.9	
HCM LOS					C	
Minor Lane/Major Mvm	t	EBL	EBT	WBT	WBR	SBLn1
Capacity (veh/h)		1111	-	-	-	410
HCM Lane V/C Ratio		0.043	-	-	-	0.261
HCM Control Delay (s)		8.4	0	-	-	16.9
HCM Lane LOS		Α	Α	-	-	С
		0.1	-		_	1
HCM 95th %tile Q(veh))	U.I	-	-	-	1

Appendix K

Synchro Intersection Worksheets – 2029 Future Total Conditions



	<i>•</i>	\rightarrow	•	1	-	•	1	†	1	-	ļ	4
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	*	ĵ.		ች	1>		ሻ	f >		ሻ	1>	
Traffic Volume (vph)	14	257	129	60	464	96	270	0	122	176	0	42
Future Volume (vph)	14	257	129	60	464	96	270	0	122	176	0	42
Satd. Flow (prot)	1658	1475	0	1658	1482	0	1658	1483	0	1492	1483	0
Flt Permitted	0.359			0.496			0.730			0.679		
Satd. Flow (perm)	626	1475	0	866	1482	0	1274	1483	0	1066	1483	0
Satd. Flow (RTOR)		50			21			552			314	
Lane Group Flow (vph)	14	386	0	60	560	0	270	122	0	176	42	0
Turn Type	Perm	NA		Perm	NA		Perm	NA		Perm	NA	
Protected Phases		2			6			4			8	
Permitted Phases	2			6			4			8		
Detector Phase	2	2		6	6		4	4		8	8	
Switch Phase												
Minimum Initial (s)	10.0	10.0		10.0	10.0		10.0	10.0		10.0	10.0	
Minimum Split (s)	23.7	23.7		23.7	23.7		30.4	30.4		30.4	30.4	
Total Split (s)	39.6	39.6		39.6	39.6		30.4	30.4		30.4	30.4	
Total Split (%)	56.6%	56.6%		56.6%	56.6%		43.4%	43.4%		43.4%	43.4%	
Yellow Time (s)	4.2	4.2		4.2	4.2		3.3	3.3		3.3	3.3	
All-Red Time (s)	1.5	1.5		1.5	1.5		2.6	2.6		2.6	2.6	
Lost Time Adjust (s)	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0	
Total Lost Time (s)	5.7	5.7		5.7	5.7		5.9	5.9		5.9	5.9	
Lead/Lag												
Lead-Lag Optimize?												
Recall Mode	C-Min	C-Min		C-Min	C-Min		None	None		None	None	
Act Effct Green (s)	39.2	39.2		39.2	39.2		19.2	19.2		19.2	19.2	
Actuated g/C Ratio	0.56	0.56		0.56	0.56		0.27	0.27		0.27	0.27	
v/c Ratio	0.04	0.46		0.12	0.67		0.77	0.15		0.60	0.07	
Control Delay	9.5	11.2		9.9	17.3		38.0	0.4		30.1	0.2	
Queue Delay	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0	
Total Delay	9.5	11.2		9.9	17.3		38.0	0.4		30.1	0.2	
LOS	Α	В		Α	В		D	Α		С	Α	
Approach Delay		11.1			16.6			26.3			24.3	
Approach LOS		В			В			С			С	
Queue Length 50th (m)	0.8	23.8		3.5	46.4		31.9	0.0		19.6	0.0	
Queue Length 95th (m)	3.6	50.6		10.3	#107.6		52.0	0.0		34.9	0.0	
Internal Link Dist (m)		192.0			170.7			97.9			184.1	
Turn Bay Length (m)	37.5			37.5			30.0			30.0		
Base Capacity (vph)	350	847		484	838		445	877		373	723	
Starvation Cap Reductn	0	0		0	0		0	0		0	0	
Spillback Cap Reductn	0	0		0	0		0	0		0	0	
Storage Cap Reductn	0	0		0	0		0	0		0	0	
Reduced v/c Ratio	0.04	0.46		0.12	0.67		0.61	0.14		0.47	0.06	
Intersection Summary												
Cycle Length: 70												
Actuated Cycle Length: 70												

Actuated Cycle Length: 70

Offset: 0 (0%), Referenced to phase 2:EBTL and 6:WBTL, Start of Green

Natural Cycle: 65

Control Type: Actuated-Coordinated

2029 Future Total AM Peak Hour

Maximum v/c Ratio: 0.77	
Intersection Signal Delay: 18.6	Intersection LOS: B
Intersection Capacity Utilization 83.7%	ICU Level of Service E
Analysis Period (min) 15	
# 95th percentile volume exceeds capacity, queue may be long	ger.
Queue shown is maximum after two cycles.	

Splits and Phases: 2: Elevation/Apolune & Cambrian

Ø2 (R) 39.6 s	↑ ø4
39.6 s	30.4 s
▼ Ø6 (R)	₩ 08
20.6 c	20.4 c

HCM 2010 TWSC 5: Temporary Driveway & Cambrian 2029 Future Total AM Peak Hour

Intersection						
Int Delay, s/veh	0.4					
**						
Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations	٦			ની	Υ	
Traffic Vol, veh/h	531	22	9	625	15	6
Future Vol, veh/h	531	22	9	625	15	6
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage,		-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	100	100	100	100	100	100
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	531	22	9	625	15	6
Majas/Minas A	laiau1		Majara		Minaul	
	lajor1		Major2		Minor1	F.4C
Conflicting Flow All	0	0	553	0	1185	542
Stage 1	-	-	-	-	542	-
Stage 2	-	-	-	-	643	-
Critical Hdwy	-	-	4.12	-	6.42	6.22
Critical Hdwy Stg 1	-	-	-	-	5.42	-
Critical Hdwy Stg 2	-	-	-	-	5.42	-
Follow-up Hdwy	-	-	2.218	-	3.518	
Pot Cap-1 Maneuver	-	-	1017	-	209	540
Stage 1	-	-	-	-	583	-
Stage 2	-	-	-	-	523	-
Platoon blocked, %	-	-		-		
Mov Cap-1 Maneuver	-	-	1017	-	206	540
Mov Cap-2 Maneuver	-	-	-	-	206	-
Stage 1	-	-	-	-	583	-
Stage 2	-				516	
otago 2					0.0	
			14/10			
Approach	EB		WB		NB	
HCM Control Delay, s	0		0.1		20.7	
HCM LOS					С	
Minor Lane/Major Mvmt		NBLn1	EBT	EBR	WBL	WBT
Capacity (veh/h)		250	EDI	EDR -	1017	WDI
HCM Lane V/C Ratio		0.084	- 1		0.009	- 1
		20.7			8.6	0
HCM Control Delay (s)		20.7 C			0.0 A	A
HCM Lane LOS		C	-	-	A	А

0.3 - - 0 -

Intersection						
Int Delay, s/veh	0.7					
Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations		4	î,		**	
Traffic Vol. veh/h	16	538	595	32	16	24
Future Vol. veh/h	16	538	595	32	16	24
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length		-		-	0	-
Veh in Median Storage,		0	0	-	0	-
Grade. %	-	0	0		0	-
Peak Hour Factor	100	100	100	100	100	100
Heavy Vehicles, %	2	2	2	2	2	2
Mymt Flow	16	538	595	32	16	24
WINITE I IOW	10	330	333	JZ	10	24
	/lajor1	Λ	Major2		Minor2	
Conflicting Flow All	627	0	-	0	1181	611
Stage 1	-	-	-	-	611	-
Stage 2	-	-	-	-	570	-
Critical Hdwy	4.12	-	-	-	6.42	6.22
Critical Hdwy Stg 1	-	-	-	-	5.42	-
Critical Hdwy Stg 2	-	-	-	-	5.42	-
Follow-up Hdwy	2.218	-		-	3.518	3.318
Pot Cap-1 Maneuver	955	-	-	-	210	494
Stage 1	-	-		-	542	-
Stage 2	-	-		-	566	-
Platoon blocked. %		-		-	000	
Mov Cap-1 Maneuver	955	_		_	205	494
Mov Cap-2 Maneuver	-				205	-
Stage 1		-		-	529	_
Stage 2					566	
Stage 2					300	
Approach	EB		WB		SB	
HCM Control Delay, s	0.3		0		18	
HCM LOS					С	
Minor Lane/Major Mvmt	+	EBL	EBT	WBT	WBR	SRI n1
Capacity (veh/h)		955	-	-	WDIX	316
HCM Lane V/C Ratio		0.017				0.127
		8.8	0	-	-	18
HCM Control Doloy (a)					-	10
HCM Control Delay (s)			-			0
HCM Control Delay (s) HCM Lane LOS HCM 95th %tile Q(veh)		0.0 A 0.1	A	-	-	C 0.4

Intersection	447.0											
Intersection Delay, s/veh Intersection LOS	117.6 F											
intersection LOS	Г											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		44			4			43-			44	
Traffic Vol, veh/h	38	501	167	128	494	76	135	15	106	38	12	31
Future Vol, veh/h	38	501	167	128	494	76	135	15	106	38	12	31
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Heavy Vehicles, %	2	2	2	2	2	2	2	2	7	2	2	2
Mvmt Flow	38	501	167	128	494	76	135	15	106	38	12	31
Number of Lanes	0	1	0	0	1	0	0	1	0	0	1	0
Approach	EB			WB			NB			SB		
Opposing Approach	WB			EB			SB			NB		
Opposing Lanes	1			1			1			1		
Conflicting Approach Left	SB			NB			EB			WB		
Conflicting Lanes Left	1			1			1			1		
Conflicting Approach Right	NB			SB			WB			EB		
Conflicting Lanes Right	1			1			1			1		
HCM Control Delay	140			142.7			19.8			14.4		
HCM LOS	F			F			С			В		
		NDI 4	EDI 4	WDL 4	ODI 4							
Lane		NBLn1	EBLn1	WBLn1	SBLn1							
Vol Left, %		53%	5%	18%	47%							
Vol Thru, %		6%	71%	71%	15%							
Vol Right, %		41%	24%	11%	38%							
Sign Control		Stop	Stop	Stop	Stop							
Traffic Vol by Lane		256	706	698	81							
LT Vol		135 15	38 501	128 494	38 12							
Through Vol				494 76	31							
RT Vol		106	167	698								
Lane Flow Rate		256 1	706 1	1	81 1							
Geometry Grp Degree of Util (X)		0.523	1.227	1.233	0.186							
Degree of Office) Departure Headway (Hd)		8.188	6.646	6.744	9.324							
Convergence, Y/N		o. 100 Yes	Yes	Yes	9.324 Yes							
Convergence, 1/N		443	551	544	387							
		443			7.324							
		C 100	4 C 4 C									
Service Time		6.188	4.646	4.744								
Service Time HCM Lane V/C Ratio		0.578	1.281	1.283	0.209							
Service Time HCM Lane V/C Ratio HCM Control Delay		0.578	1.281	1.283 142.7	0.209							
Service Time HCM Lane V/C Ratio		0.578	1.281	1.283	0.209							

2029 Future Total PM Peak Hour

	•	-	*	•	—	•	1	†	1	-	Į.	4
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	ሻ	- ↑		ሻ	ĵ,		7	1>		ሻ	1→	
Traffic Volume (vph)	42	461	255	119	429	137	193	0	93	128	0	27
Future Volume (vph)	42	461	255	119	429	137	193	0	93	128	0	27
Satd. Flow (prot)	1658	1653	0	1658	1500	0	1658	1483	0	1492	1483	0
Flt Permitted	0.398			0.314			0.740			0.697		
Satd. Flow (perm)	691	1653	0	548	1500	0	1291	1483	0	1088	1483	0
Satd. Flow (RTOR)		46			26			428			447	
Lane Group Flow (vph)	42	716	0	119	566	0	193	93	0	128	27	0
Turn Type	Perm	NA		Perm	NA		Perm	NA		Perm	NA	
Protected Phases		2			6			4			8	
Permitted Phases	2			6			4			8		
Detector Phase	2	2		6	6		4	4		8	8	
Switch Phase												
Minimum Initial (s)	10.0	10.0		10.0	10.0		10.0	10.0		10.0	10.0	
Minimum Split (s)	23.7	23.7		23.7	23.7		30.4	30.4		30.4	30.4	
Total Split (s)	82.0	82.0		82.0	82.0		38.0	38.0		38.0	38.0	
Total Split (%)	68.3%	68.3%		68.3%	68.3%		31.7%	31.7%		31.7%	31.7%	
Yellow Time (s)	4.2	4.2		4.2	4.2		3.3	3.3		3.3	3.3	
All-Red Time (s)	1.5	1.5		1.5	1.5		2.6	2.6		2.6	2.6	
Lost Time Adjust (s)	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0	
Total Lost Time (s)	5.7	5.7		5.7	5.7		5.9	5.9		5.9	5.9	
Lead/Lag												
Lead-Lag Optimize?												
Recall Mode	C-Min	C-Min		C-Min	C-Min		None	None		None	None	
Act Effct Green (s)	85.3	85.3		85.3	85.3		23.1	23.1		23.1	23.1	
Actuated g/C Ratio	0.71	0.71		0.71	0.71		0.19	0.19		0.19	0.19	
v/c Ratio	0.09	0.60		0.31	0.53		0.78	0.15		0.61	0.04	
Control Delay	7.5	11.9		10.4	10.9		65.9	0.5		55.7	0.1	
Queue Delay	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0	
Total Delay	7.5	11.9		10.4	10.9		65.9	0.5		55.7	0.1	
LOS	Α	В		В	В		Е	Α		Е	Α	
Approach Delay		11.7			10.8			44.6			46.0	
Approach LOS		В			В			D			D	
Queue Length 50th (m)	2.7	70.9		9.3	52.3		43.5	0.0		27.8	0.0	
Queue Length 95th (m)	8.2	133.3		23.9	99.8		63.7	0.0		44.4	0.0	
Internal Link Dist (m)		122.9			169.1			171.4			184.1	
Turn Bay Length (m)	37.5			37.5			30.0			30.0		
Base Capacity (vph)	491	1187	_	389	1073		345	710		291	724	
Starvation Cap Reductn	0	0		0	0		0	0		0	0	
Spillback Cap Reductn	0	0	_	0	0		0	0		0	0	
Storage Cap Reductn	0	0		0	0		0	0		0	0	
Reduced v/c Ratio	0.09	0.60		0.31	0.53		0.56	0.13		0.44	0.04	
Intersection Summary												
Occale I amouth 400												

Cycle Length: 120

Actuated Cycle Length: 120
Offset: 0 (0%), Referenced to phase 2:EBTL and 6:WBTL, Start of Green

Natural Cycle: 70

Control Type: Actuated-Coordinated

Scenario 1 3850 Cambrian Road 11:59 pm 10/19/2022 2029 Future Total

Synchro 11 Report Page 3 Lanes, Volumes, Timings 2: Elevation/Apolune & Cambrian

₩ Ø6 (R)

2029 Future Total PM Peak Hour

Maximum v/c Ratio: 0.78 Intersection Signal Delay: 19.2 Intersection LOS: B Intersection Capacity Utilization 82.7% ICU Level of Service E Analysis Period (min) 15 Splits and Phases: 2: Elevation/Apolune & Cambrian **↑**04

Scenario 1 3850 Cambrian Road 11:59 pm 10/19/2022 2029 Future Total

Synchro 11 Report Page 4

late as a still a						
Intersection						
Int Delay, s/veh	2.2					
Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations		4	ĵ.		W	
Traffic Vol, veh/h	36	645	627	65	41	59
Future Vol. veh/h	36	645	627	65	41	59
Conflicting Peds, #/hr	0	045	027	00	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-		-	None	-	
Storage Length	-	-	-	-	0	-
Veh in Median Storage		0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	100	100	100	100	100	100
Heavy Vehicles, %	2	2	2	2	2	2
Mymt Flow	36	645	627	65	41	59
		_				
	Major1		Major2		Minor2	
Conflicting Flow All	692	0	-	0	1377	660
Stage 1	-	-	-	-	660	-
Stage 2	-	-	-	-	717	-
Critical Hdwy	4.12	-	-	-	6.42	6.22
Critical Hdwy Stg 1	-	-	-	-	5.42	-
Critical Hdwy Stg 2	_	-			5.42	_
Follow-up Hdwy	2.218				3.518	3 318
Pot Cap-1 Maneuver	903	-			160	463
	903				514	403
Stage 1		-	-	-		
Stage 2	-	-	-	-	484	-
Platoon blocked, %	005	-	-	-		105
Mov Cap-1 Maneuver	903	-	-	-	150	463
Mov Cap-2 Maneuver	-	-	-	-	150	-
Stage 1	-	-	-	-	482	-
Stage 2	-	-	-	-	484	-
·						
Anneach	ED		MD		CD	
Approach	EB		WB		SB	
HCM Control Delay, s	0.5		0		28.7	
HCM LOS					D	
Minor Lane/Major Mvm	nt .	EBL	EBT	WBT	WRP	SBLn1
	IL		EDI	WDI	WDR	
Capacity (veh/h)		903	-	-	-	250
HCM Lane V/C Ratio		0.04		-	-	0.4
HCM Control Delay (s)		9.2	0	-	-	28.7
HCM Lane LOS		Α	Α	-	-	D

0.1 - - - 1.8

Intersection												
Intersection Delay, s/veh	56.4											
Intersection LOS	F											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		43-			4			44			44	
Traffic Vol, veh/h	23	420	117	74	479	82	112	10	82	40	13	32
Future Vol, veh/h	23	420	117	74	479	82	112	10	82	40	13	32
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Heavy Vehicles, %	2	2	2	7	2	2	2	2	4	2	8	2
Mvmt Flow	23	420	117	74	479	82	112	10	82	40	13	32
Number of Lanes	0	1	0	0	1	0	0	1	0	0	1	0
Approach	EB			WB			NB			SB		
Opposing Approach	WB			EB			SB			NB		
Opposing Lanes	1			1			1			1		
Conflicting Approach Left	SB			NB			EB			WB		
Conflicting Lanes Left	1			1			1			1		
Conflicting Approach Right	NB			SB			WB			EB		
Conflicting Lanes Right	1			1			1			1		
HCM Control Delay	45			85.3			15.6			12.9		
HCM LOS	Е			F			С			В		
Lane		NBLn1	EBLn1	WBLn1	SBLn1							
Vol Left, %		55%	4%	12%	47%							
Vol Thru, %		5%	.,.	75%								
					15%							
VOI RIGHT %			75% 21%		15% 38%							
Vol Right, % Sign Control		40%	21%	13%	38%							
Sign Control		40% Stop	21% Stop	13% Stop	38% Stop							
Sign Control Traffic Vol by Lane		40% Stop 204	21% Stop 560	13% Stop 635	38% Stop 85							
Sign Control Traffic Vol by Lane LT Vol		40% Stop	21% Stop	13% Stop	38% Stop							
Sign Control		40% Stop 204 112	21% Stop 560 23	13% Stop 635 74	38% Stop 85 40							
Sign Control Traffic Vol by Lane LT Vol Through Vol RT Vol		40% Stop 204 112 10 82	21% Stop 560 23 420 117	13% Stop 635 74 479 82	38% Stop 85 40 13							
Sign Control Traffic Vol by Lane LT Vol Through Vol RT Vol Lane Flow Rate		40% Stop 204 112 10	21% Stop 560 23 420	13% Stop 635 74 479	38% Stop 85 40 13							
Sign Control Traffic Vol by Lane LT Vol Through Vol RT Vol Lane Flow Rate Geometry Grp		40% Stop 204 112 10 82 204	21% Stop 560 23 420 117 560	13% Stop 635 74 479 82 635	38% Stop 85 40 13 32 85							
Sign Control Traffic Vol by Lane LT Vol Through Vol RT Vol Lane Flow Rate Geometry Grp Degree of Util (X)		40% Stop 204 112 10 82 204 1	21% Stop 560 23 420 117 560	13% Stop 635 74 479 82 635 1	38% Stop 85 40 13 32 85							
Sign Control Traffic Vol by Lane LT Vol Through Vol RT Vol Lane Flow Rate		40% Stop 204 112 10 82 204 1 0.406	21% Stop 560 23 420 117 560 1	13% Stop 635 74 479 82 635 1	38% Stop 85 40 13 32 85 1 0.185							
Sign Control Traffic Vol by Lane LT Vol Through Vol RT Vol Lane Flow Rate Geometry Grp Degree of Util (X) Departure Headway (Hd)		40% Stop 204 112 10 82 204 1 0.406 7.53	21% Stop 560 23 420 117 560 1 0.921 6.179	13% Stop 635 74 479 82 635 1 1.082 6.136	38% Stop 85 40 13 32 85 1 0.185 8.116							
Sign Control Traffic Vol by Lane LT Vol Through Vol RT Vol Lane Flow Rate Geometry Grp Degree of Util (X) Departure Headway (Hd) Convergence, Y/N Cap		40% Stop 204 112 10 82 204 1 0.406 7.53 Yes	21% Stop 560 23 420 117 560 1 0.921 6.179 Yes	13% Stop 635 74 479 82 635 1 1.082 6.136 Yes	38% Stop 85 40 13 32 85 1 0.185 8.116 Yes							
Sign Control Traffic Vol by Lane LT Vol Through Vol RT Vol Lane Flow Rate Geometry Grp Degree of Util (X) Departure Headway (Hd) Convergence, Y/N Cap Service Time		40% Stop 204 112 10 82 204 1 0.406 7.53 Yes 481	21% Stop 560 23 420 117 560 1 0.921 6.179 Yes 594	13% Stop 635 74 479 82 635 1 1.082 6.136 Yes 597	38% Stop 85 40 13 32 85 1 0.185 8.116 Yes 445							
Sign Control Traffic Vol by Lane LT Vol Through Vol RT Vol Lane Flow Rate Geometry Grp Degree of Util (X) Departure Headway (Hd) Convergence, Y/N Cap Service Time HCM Lane V/C Ratio		40% Stop 204 112 10 82 204 1 0.406 7.53 Yes 481 5.53	21% Stop 560 23 420 117 560 1 0.921 6.179 Yes 594 4.179	13% Stop 635 74 479 82 635 1 1.082 6.136 Yes 597 4.144	38% Stop 85 40 13 32 85 1 0.185 8.116 Yes 445 6.116							
Sign Control Traffic Vol by Lane LT Vol Through Vol RT Vol Lane Flow Rate Geometry Grp Degree of Util (X) Departure Headway (Hd) Convergence, Y/N		40% Stop 204 112 10 82 204 1 0.406 7.53 Yes 481 5.53 0.424	21% Stop 560 23 420 117 560 1 0.921 6.179 Yes 594 4.179 0.943	13% Stop 635 74 479 82 635 1 1.082 6.136 Yes 597 4.144 1.064	38% Stop 85 40 13 32 85 1 0.185 8.116 Yes 445 6.116 0.191							

	•	-	*	•	-	*	1	†	1	-	ļ	1
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	*	1 >		ች	f)		ች	f >		ች	1 >	
Traffic Volume (vph)	46	264	232	136	287	120	181	1	117	108	2	52
Future Volume (vph)	46	264	232	136	287	120	181	1	117	108	2	52
Satd. Flow (prot)	1566	1623	0	1271	1484	0	1658	1330	0	1436	1401	0
Flt Permitted	0.497			0.441			0.722			0.653		
Satd. Flow (perm)	812	1623	0	590	1484	0	1260	1330	0	981	1401	0
Satd. Flow (RTOR)		65			31			117			52	
Lane Group Flow (vph)	46	496	0	136	407	0	181	118	0	108	54	0
Turn Type	Perm	NA		Perm	NA		Perm	NA		Perm	NA	
Protected Phases		2			6			4			8	
Permitted Phases	2			6			4			8		
Detector Phase	2	2		6	6		4	4		8	8	
Switch Phase												
Minimum Initial (s)	10.0	10.0		10.0	10.0		10.0	10.0		10.0	10.0	
Minimum Split (s)	23.7	23.7		23.7	23.7		30.4	30.4		30.4	30.4	
Total Split (s)	77.0	77.0		77.0	77.0		43.0	43.0		43.0	43.0	
Total Split (%)	64.2%	64.2%		64.2%	64.2%		35.8%	35.8%		35.8%	35.8%	
Yellow Time (s)	4.2	4.2		4.2	4.2		3.3	3.3		3.3	3.3	
All-Red Time (s)	1.5	1.5		1.5	1.5		2.6	2.6		2.6	2.6	
Lost Time Adjust (s)	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0	
Total Lost Time (s)	5.7	5.7		5.7	5.7		5.9	5.9		5.9	5.9	
Lead/Lag												
Lead-Lag Optimize?												
Recall Mode	C-Min	C-Min		C-Min	C-Min		None	None		None	None	
Act Effct Green (s)	85.8	85.8		85.8	85.8		22.6	22.6		22.6	22.6	
Actuated g/C Ratio	0.72	0.72		0.72	0.72		0.19	0.19		0.19	0.19	
v/c Ratio	0.08	0.42		0.32	0.38		0.76	0.34		0.59	0.18	
Control Delay	7.2	8.1		10.3	8.3		65.5	9.3		55.9	11.5	
Queue Delay	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0	
Total Delay	7.2	8.1		10.3	8.3		65.5	9.3		55.9	11.5	
LOS	Α	Α		В	Α		Е	Α		Е	В	
Approach Delay		8.0			8.8			43.3			41.1	
Approach LOS		Α			Α			D			D	
Queue Length 50th (m)	2.9	36.0		10.6	30.5		40.8	0.2		23.4	0.4	
Queue Length 95th (m)	8.5	70.4		26.9	60.2		60.4	14.2		39.0	10.2	
Internal Link Dist (m)		122.9			166.9			171.4			184.1	
Turn Bay Length (m)	37.5			37.5			30.0			30.0		
Base Capacity (vph)	580	1178		421	1069		389	492		303	469	
Starvation Cap Reductn	0	0		0	0		0	0		0	0	
Spillback Cap Reductn	0	0		0	0		0	0		0	0	
Storage Cap Reductn	0	0		0	0		0	0		0	0	
Reduced v/c Ratio	0.08	0.42		0.32	0.38		0.47	0.24		0.36	0.12	
Intersection Summary												
Cycle Length: 120												
Actuated Cycle Length: 120												

Actuated Cycle Length: 120
Offset: 0 (0%), Referenced to phase 2:EBTL and 6:WBTL, Start of Green
Natural Cycle: 60

Control Type: Actuated-Coordinated

2029 Future Future SAT Peak Hour

Maximum v/c Ratio: 0.76	
Intersection Signal Delay: 18.6	Intersection LOS: B
Intersection Capacity Utilization 69.6%	ICU Level of Service C
Analysis Period (min) 15	

Splits and Phases: 2: Elevation/Apolune & Cambrian

opino ana mases. Z. Lievano	I/Apolitic & Garibilan
- ≠ø2 (R)	₹ Ø4
77 s	43 s
Ø6 (R)	₩ Ø8
77 s	43 s

HCM 2010 TWSC 2029 Future Future 5: Cambrian SAT Peak Hour


Intersection						
Int Delay, s/veh	1.3					
Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations	ĵ.			4	W	
Traffic Vol, veh/h	175	66	7	226	44	10
Future Vol, veh/h	175	66	7	226	44	10
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage	e,# 0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	100	100	100	100	100	100
Heavy Vehicles, %	2	2	2	2	2	2
Mymt Flow	175	66	7	226	44	10
Major/Minor	Major4		Majora		Minor4	
	Major1		Major2		Minor1	000
Conflicting Flow All	0	0	241	0	448	208
Stage 1	-	-	-	-	208	-
Stage 2	-	-	- 440	-	240	- 0.00
Critical Hdwy	-	-	4.12	-	6.42	6.22
Critical Hdwy Stg 1	-	-	-	-	5.42	-
Critical Hdwy Stg 2	-	-	-	-	5.42	-
Follow-up Hdwy	-	-	2.218	-	0.0.0	
Pot Cap-1 Maneuver	-	-	1326	-	568	832
Stage 1	-	-	-	-	827	-
Stage 2	-	-	-	-	800	-
Platoon blocked, %	-	-		-		
Mov Cap-1 Maneuver	-	-	1326	-	565	832
Mov Cap-2 Maneuver	-	-	-	-	565	-
Stage 1	-	-	-	-	827	-
Stage 2	-	-	-	-	795	-
Approach	EB		WB		NB	
	0		0.2		11.6	
HCM Control Delay, s HCM LOS	U		0.2		11.6 B	
HCIVI LUS					В	
Minor Lane/Major Mvn	nt l	NBLn1	EBT	EBR	WBL	WBT
Capacity (veh/h)		601	-	-	1326	-
HCM Lane V/C Ratio		0.09		-	0.005	-
HCM Control Delay (s))	11.6	-	-	7.7	0
HCM Lane LOS		В		-	Α	A
HOMOSII WILL OV. I						


Intersection						
Int Delay, s/veh	2.4					
Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations	EDL	<u>- EDI</u>	WB1	WDR	SBL	ODR
	40			60		E4
Traffic Vol, veh/h	48 48	440 440	493 493	60 60	56 56	51 51
Future Vol, veh/h						51
Conflicting Peds, #/hr	0	0	0	0	0	
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage		0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	100	100	100	100	100	100
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	48	440	493	60	56	51
Major/Minor I	Major1	, n	Major2		Minor2	
Conflicting Flow All	553	0	-	0	1059	523
	553	-	- 1	-	523	523
Stage 1					523	- 1
Stage 2	4.12	-	-	-	6.42	6.22
Critical Hdwy			-	-	5.42	6.22
Critical Hdwy Stg 1	-	-	-	-		-
Critical Hdwy Stg 2	- 0.040	-	-	-	5.42	2.240
Follow-up Hdwy	2.218	-	-	-	3.518	
Pot Cap-1 Maneuver	1017	-	-	-	249	554
Stage 1	-	-	-	-	595	-
Stage 2	-	-	-	-	587	-
Platoon blocked, %	101-	-	-	-		
Mov Cap-1 Maneuver	1017	-	-	-	234	554
Mov Cap-2 Maneuver	-	-	-	-	234	-
Stage 1	-	-	-	-	558	-
Stage 2	-	-	-	-	587	-
Approach	EB		WB		SB	
HCM Control Delay, s	0.9		0		21.6	
HCM LOS	0.9		U		21.0 C	
HOW LOS					U	
Minor Lane/Major Mvm	nt	EBL	EBT	WBT	WBR	SBLn1
Capacity (veh/h)		1017	-	-	-	323
HCM Lane V/C Ratio		0.047	-	-	-	0.331
HCM Control Delay (s)		8.7	0	-	-	
HCM Lane LOS		Α	Α		-	С
HCM 95th %tile Q(veh)	1	0.1	-			1.4


Appendix L


Turning Templates











Appendix M

TDM Checklist



TDM Measures Checklist:

Non-Residential Developments (office, institutional, retail or industrial)

	Legend
BASIC	The measure is generally feasible and effective, and in most cases would benefit the development and its users
BETTER	The measure could maximize support for users of sustainable modes, and optimize development performance
*	The measure is one of the most dependably effective tools to encourage the use of sustainable modes

	TDM	measures: Non-residential developments	Check if proposed & add descriptions
	1.	TDM PROGRAM MANAGEMENT	
	1.1	Program coordinator	
BASIC *	1.1.1	Designate an internal coordinator, or contract with an external coordinator	
	1.2	Travel surveys	
BETTER	1.2.1	Conduct periodic surveys to identify travel-related behaviours, attitudes, challenges and solutions, and to track progress	
	2.	WALKING AND CYCLING	
	2.1	Information on walking/cycling routes & destinations	
BASIC	2.1.1	Display local area maps with walking/cycling access routes and key destinations at major entrances	
	2.2	Bicycle skills training	
		Commuter travel	
BETTER *	2.2.1	Offer on-site cycling courses for commuters, or subsidize off-site courses	
	2.3	Valet bike parking	
		Visitor travel	
BETTER	2.3.1	Offer secure valet bike parking during public events when demand exceeds fixed supply (e.g. for festivals, concerts, games)	

	TDM	measures: Non-residential developments	Check if proposed & add descriptions
	3.	TRANSIT	
	3.1	Transit information	
BASIC	3.1.1	Display relevant transit schedules and route maps at entrances	
BASIC	3.1.2	Provide online links to OC Transpo and STO information	
BETTER	3.1.3	Provide real-time arrival information display at entrances	
	3.2	Transit fare incentives	
		Commuter travel	
BETTER	3.2.1	Offer preloaded PRESTO cards to encourage commuters to use transit	
BETTER 1	3.2.2	Subsidize or reimburse monthly transit pass purchases by employees	
		Visitor travel	
BETTER	3.2.3	Arrange inclusion of same-day transit fare in price of tickets (e.g. for festivals, concerts, games)	
	3.3	Enhanced public transit service	
		Commuter travel	
BETTER	3.3.1	Contract with OC Transpo to provide enhanced transit services (e.g. for shift changes, weekends)	
		Visitor travel	
BETTER	3.3.2	Contract with OC Transpo to provide enhanced transit services (e.g. for festivals, concerts, games)	
	3.4	Private transit service	
		Commuter travel	
BETTER	3.4.1	Provide shuttle service when OC Transpo cannot offer sufficient quality or capacity to serve demand (e.g. for shift changes, weekends)	
		Visitor travel	
BETTER	3.4.2	Provide shuttle service when OC Transpo cannot offer sufficient quality or capacity to serve demand (e.g. for festivals, concerts, games)	

8

★ 6.1.1 Charge for long-term parking (daily, weekly, monthly)

6.1.2 Unbundle parking cost from lease rates at multi-tenant

Visitor travel

6.1.3 Charge for short-term parking (hourly)

	TDM	measures: Non-residential developments	Check if proposed & add descriptions
	7.	TDM MARKETING & COMMUNICATIONS	
	7.1	Multimodal travel information	
		Commuter travel	
BASIC *	7.1.1	Provide a multimodal travel option information package to new/relocating employees and students	\square
	_	Visitor travel	
BETTER ★	7.1.2	Include multimodal travel option information in invitations or advertising that attract visitors or customers (e.g. for festivals, concerts, games)	
	7.2	Personalized trip planning	
		Commuter travel	
BETTER ★	7.2.1	Offer personalized trip planning to new/relocating employees	
	7.3	Promotions	
		Commuter travel	
BETTER	7.3.1	Deliver promotions and incentives to maintain awareness, build understanding, and encourage trial of sustainable modes	
	8.	OTHER INCENTIVES & AMENITIES	
	8.1	Emergency ride home	
		Commuter travel	
BETTER ★	8.1.1	Provide emergency ride home service to non-driving commuters	
	8.2	Alternative work arrangements	
		Commuter travel	
BASIC ★	8.2.1	Encourage flexible work hours	
BETTER	8.2.2	Encourage compressed workweeks	
BETTER 🛨	8.2.3	Encourage telework	
	8.3	Local business travel options	
		Commuter travel	
BASIC *	8.3.1	Provide local business travel options that minimize the need for employees to bring a personal car to work	
	8.4	Commuter incentives	
		Commuter travel	
BETTER	8.4.1	Offer employees a taxable, mode-neutral commuting allowance	
	8.5	On-site amenities	
		Commuter travel	
BETTER	8.5.1	Provide on-site amenities/services to minimize mid-day or mid-commute errands	

10 11

TDM-Supportive Development Design and Infrastructure Checklist: *Non-Residential Developments (office, institutional, retail or industrial)*

Legend		
REQUIRED	The Official Plan or Zoning By-law provides related guidance that must be followed	
BASIC	The measure is generally feasible and effective, and in most cases would benefit the development and its users	
BETTER	The measure could maximize support for users of sustainable modes, and optimize development performance	

	TDM-s	supportive design & infrastructure measures: Non-residential developments	Check if completed & add descriptions, explanations or plan/drawing references
	1.	WALKING & CYCLING: ROUTES	
	1.1	Building location & access points	
BASIC	1.1.1	Locate building close to the street, and do not locate parking areas between the street and building entrances	
BASIC	1.1.2	Locate building entrances in order to minimize walking distances to sidewalks and transit stops/stations	Ø
BASIC	1.1.3	Locate building doors and windows to ensure visibility of pedestrians from the building, for their security and comfort	abla
	1.2	Facilities for walking & cycling	
REQUIRED	1.2.1	Provide convenient, direct access to stations or major stops along rapid transit routes within 600 metres; minimize walking distances from buildings to rapid transit; provide pedestrian-friendly, weather-protected (where possible) environment between rapid transit accesses and building entrances; ensure quality linkages from sidewalks through building entrances to integrated stops/stations (see Official Plan policy 4.3.3)	
REQUIRED	1.2.2	Provide safe, direct and attractive pedestrian access from public sidewalks to building entrances through such measures as: reducing distances between public sidewalks and major building entrances; providing walkways from public streets to major building entrances; within a site, providing walkways along the front of adjoining buildings, between adjacent buildings, and connecting areas where people may congregate, such as courtyards and transit stops; and providing weather protection through canopies, colonnades, and other design elements wherever possible (see Official Plan policy 4.3.12)	

	TDM-s	supportive design & infrastructure measures: Non-residential developments	Check if completed & add descriptions, explanations or plan/drawing references
REQUIRED	1.2.3	Provide sidewalks of smooth, well-drained walking surfaces of contrasting materials or treatments to differentiate pedestrian areas from vehicle areas, and provide marked pedestrian crosswalks at intersection sidewalks (see Official Plan policy 4.3.10)	
REQUIRED	1.2.4	Make sidewalks and open space areas easily accessible through features such as gradual grade transition, depressed curbs at street corners and convenient access to extra-wide parking spaces and ramps (see Official Plan policy 4.3.10)	
REQUIRED	1.2.5	Include adequately spaced inter-block/street cycling and pedestrian connections to facilitate travel by active transportation. Provide links to the existing or planned network of public sidewalks, multi-use pathways and onroad cycle routes. Where public sidewalks and multi-use pathways intersect with roads, consider providing traffic control devices to give priority to cyclists and pedestrians (see Official Plan policy 4.3.11)	
BASIC	1.2.6	Provide safe, direct and attractive walking routes from building entrances to nearby transit stops	
BASIC	1.2.7	Ensure that walking routes to transit stops are secure, visible, lighted, shaded and wind-protected wherever possible	
BASIC	1.2.8	Design roads used for access or circulation by cyclists using a target operating speed of no more than 30 km/h, or provide a separated cycling facility	
	1.3	Amenities for walking & cycling	
BASIC	1.3.1	Provide lighting, landscaping and benches along walking and cycling routes between building entrances and streets, sidewalks and trails	
BASIC	1.3.2	Provide wayfinding signage for site access (where required, e.g. when multiple buildings or entrances exist) and egress (where warranted, such as when directions to reach transit stops/stations, trails or other common destinations are not obvious)	

5 6

			Check if completed &
	TDM-s	upportive design & infrastructure measures: Non-residential developments	add descriptions, explanations or plan/drawing references
	2.	WALKING & CYCLING: END-OF-TRIP FACILI	TIES
	2.1	Bicycle parking	
REQUIRED	2.1.1	Provide bicycle parking in highly visible and lighted areas, sheltered from the weather wherever possible (see Official Plan policy 4.3.6)	
REQUIRED	2.1.2	Provide the number of bicycle parking spaces specified for various land uses in different parts of Ottawa; provide convenient access to main entrances or well-used areas (see Zoning By-law Section 111)	☑
REQUIRED	2.1.3	Ensure that bicycle parking spaces and access aisles meet minimum dimensions; that no more than 50% of spaces are vertical spaces; and that parking racks are securely anchored (see Zoning By-law Section 111)	☑
BASIC	2.1.4	Provide bicycle parking spaces equivalent to the expected number of commuter cyclists (assuming the cycling mode share target is met), plus the expected peak number of customer/visitor cyclists	
BETTER	2.1.5	Provide bicycle parking spaces equivalent to the expected number of commuter and customer/visitor cyclists, plus an additional buffer (e.g. 25 percent extra) to encourage other cyclists and ensure adequate capacity in peak cycling season	
	2.2	Secure bicycle parking	
REQUIRED	2.2.1	Where more than 50 bicycle parking spaces are provided for a single office building, locate at least 25% of spaces within a building/structure, a secure area (e.g. supervised parking lot or enclosure) or bicycle lockers (see Zoning By-law Section 111)	
BETTER	2.2.2	Provide secure bicycle parking spaces equivalent to the expected number of commuter cyclists (assuming the cycling mode share target is met)	
	2.3	Shower & change facilities	
BASIC	2.3.1	Provide shower and change facilities for the use of active commuters	
BETTER	2.3.2	In addition to shower and change facilities, provide dedicated lockers, grooming stations, drying racks and laundry facilities for the use of active commuters	
	2.4	Bicycle repair station	
BETTER	2.4.1	Provide a permanent bike repair station, with commonly used tools and an air pump, adjacent to the main bicycle parking area (or secure bicycle parking area, if provided)	

TDM-supportive design & infrastructure measures: Non-residential developments			Check if completed & add descriptions, explanations or plan/drawing references	
	3.	TRANSIT		
	3.1	Customer amenities		
BASIC	3.1.1	Provide shelters, lighting and benches at any on-site transit stops		
BASIC	3.1.2	Where the site abuts an off-site transit stop and insufficient space exists for a transit shelter in the public right-of-way, protect land for a shelter and/or install a shelter		
BETTER	3.1.3	Provide a secure and comfortable interior waiting area by integrating any on-site transit stops into the building		
	4.	RIDESHARING		
	4.1	Pick-up & drop-off facilities		
BASIC	4.1.1	Provide a designated area for carpool drivers (plus taxis and ride-hailing services) to drop off or pick up passengers without using fire lanes or other no-stopping zones		
	4.2	Carpool parking		
BASIC	4.2.1	Provide signed parking spaces for carpools in a priority location close to a major building entrance, sufficient in number to accommodate the mode share target for carpools		
BETTER	4.2.2	At large developments, provide spaces for carpools in a separate, access-controlled parking area to simplify enforcement		
	5.	CARSHARING & BIKESHARING		
	5.1	Carshare parking spaces		
BETTER	5.1.1	Provide carshare parking spaces in permitted non- residential zones, occupying either required or provided parking spaces (see Zoning By-law Section 94)		
	5.2	Bikeshare station location		
BETTER	5.2.1	Provide a designated bikeshare station area near a major building entrance, preferably lighted and sheltered with a direct walkway connection		

	TDM-s	supportive design & infrastructure measures: Non-residential developments	Check if completed & add descriptions, explanations or plan/drawing references
	6.	PARKING	
	6.1	Number of parking spaces	
REQUIRED	6.1.1	Do not provide more parking than permitted by zoning, nor less than required by zoning, unless a variance is being applied for	Image: section of the content of the
BASIC	6.1.2	Provide parking for long-term and short-term users that is consistent with mode share targets, considering the potential for visitors to use off-site public parking	
BASIC	6.1.3	Where a site features more than one use, provide shared parking and reduce the cumulative number of parking spaces accordingly (see Zoning By-law Section 104)	
BETTER	6.1.4	Reduce the minimum number of parking spaces required by zoning by one space for each 13 square metres of gross floor area provided as shower rooms, change rooms, locker rooms and other facilities for cyclists in conjunction with bicycle parking (see Zoning By-law Section 111)	
	6.2	Separate long-term & short-term parking areas	
BETTER	6.2.1	Separate short-term and long-term parking areas using signage or physical barriers, to permit access controls and simplify enforcement (i.e. to discourage employees from parking in visitor spaces, and vice versa)	
	7.	OTHER	
	7.1	On-site amenities to minimize off-site trips	
BETTER	7.1.1	Provide on-site amenities to minimize mid-day or mid-commute errands	

Appendix N

MMLOS Worksheets



Multi-Modal Level of Service - Intersections Form

Consultant Scenario Comments

GH Transportation Inc	Project
uture	Date

2022-066	
8/21/2023	

	NTERSECTIONS	Cambrian Rd at ApoluneSt / Elevation Rd					
	Crossing Side	NORTH	SOUTH	EAST	WEST		
	Lanes	4	4	5	5		
	Median	No Median - 2.4 m	No Median - 2.4 m	No Median - 2.4 m	No Median - 2.4 m		
	Conflicting Left Turns	Permissive	Permissive	Permissive	Permissive		
	Conflicting Right Turns	Permissive or yield control	Permissive or yield control	Permissive or yield control	Permissive or yield control		
	Right Turns on Red (RToR) ?	RTOR allowed	RTOR allowed	RTOR allowed	RTOR allowed		
	Ped Signal Leading Interval?	No	No	No	No		
ian	Right Turn Channel	No Channel	No Channel	No Channel	No Channel		
str	Corner Radius	10-15m	10-15m	10-15m	10-15m		
Pedestrian	Crosswalk Type	Std transverse Std transverse markings markings		Std transverse markings	Std transverse markings		
_	PETSI Score	53	53	37	37		
	Ped. Exposure to Traffic LoS	D	D	E	E		
	Cycle Length						
	Effective Walk Time						
	Average Pedestrian Delay						
	Pedestrian Delay LoS	-	<u> </u>	<u> </u>	-		
	Level of Service	D	D	<u> </u>	E		
		E					
	Approach From	NORTH	SOUTH	EAST	WEST		
	Bicycle Lane Arrangement on Approach	Mixed Traffic	Mixed Traffic	Mixed Traffic	Mixed Traffic		
	Right Turn Lane Configuration						
	Right Turning Speed						
<u>o</u>	Cyclist relative to RT motorists	#N/A	#N/A	#N/A	#N/A		
ycl	Separated or Mixed Traffic	Mixed Traffic	Mixed Traffic	Mixed Traffic	Mixed Traffic		
Bicycle	Left Turn Approach	No lane crossed	No lane crossed	No lane crossed	No lane crossed		
	Operating Speed	> 40 to ≤ 50 km/h	> 40 to ≤ 50 km/h	> 50 to < 60 km/h	> 50 to < 60 km/h		
	Left Turning Cyclist	В	В	С	С		
		В	В	С	С		
	Level of Service	С					
	Average Signal Delay						
ısit							
Transit	Level of Service						
				•			
Truck	Effective Corner Radius						
	Number of Receiving Lanes on Departure from Intersection						
	1	-	-	<u> </u>	-		
	Level of Service						
	Volume to Capacity Ratio	0.61 - 0.70					
Auto							
✓	Level of Service	В					

Multi-Modal Level of Service - Segments Form

Consultant	CGH Transportation Inc	Project	2022-066
Scenario	Existing/Future	Date	8/21/2023
Comments		1	
		1	

SEGMENTS			Cambrian Rd Existing	Cambrian Rd Future	Re-Aligned Greenbank Rd Future	Section 4
Pedestrian	Sidewalk Width Boulevard Width	F	no sidewalk n/a	≥ 2 m > 2 m	1.8 m > 2 m	
	Avg Daily Curb Lane Traffic Volume		> 3000	> 3000	> 3000	
	Operating Speed On-Street Parking		> 50 to 60 km/h no	> 50 to 60 km/h no	> 50 to 60 km/h no	
est	Exposure to Traffic PLoS		F	С	D	-
eq	Effective Sidewalk Width					
	Pedestrian Volume Crowding PLoS		Α	Α	Α	
	Level of Service		F	C	D	-
	Level of Service			C	D	-
Bicycle	Type of Cycling Facility	D	Mixed Traffic	Physically Separated	Physically Separated	
	Number of Travel Lanes		≤ 2 (no centreline)			
	Operating Speed		≥ 50 to 60 km/h			
	# of Lanes & Operating Speed LoS		D	-	-	-
	Bike Lane (+ Parking Lane) Width					
<u>5</u>	Bike Lane Width LoS		-	-	-	-
蓝	Bike Lane Blockages					
	Blockage LoS Median Refuge Width (no median = < 1.8 m)		< 1.8 m refuge	-	-	-
	No. of Lanes at Unsignalized Crossing		≤ 3 lanes			
	Sidestreet Operating Speed		≤ 40 km/h			
	Unsignalized Crossing - Lowest LoS		Α	A		-
	Level of Service		D	Α	Α	-
Transit	Facility Type	Α			Segregated ROW	
	Friction or Ratio Transit:Posted Speed					
	Level of Service		-	-	Α	-
Truck	Truck Lane Width	Α			≤ 3.5 m	
	Travel Lanes per Direction				> 1	
	Level of Service		-	-	Α	-