NOVATECH

Engineers, Planners & Landscape Architects

Engineering
- Land/Site Development
- Municipal Infrastructure
- Environmental/ Water Resources
- Traffic/ Transportation
- Recreational

Planning
- Land/Site Development
- Planning Application Management
- Municipal Planning
- Urban Design
- Expert Witness (LPAT)
- Wireless Industry

Landscape Architecture
- Streetscapes & Public Amenities
- Open Space, Parks & Recreation
- Community & Residential
- Commercial & Institutional
- Environmental Restoration

39 Years

Mattino Developments Inc.
Block 21, Mattino Way

Servicing Design Brief

SERVICING DESIGN BRIEF
MATTINO DEVELOPMENTS INC.
BLOCK 21, MATTINO WAY

Prepared By:

NOVATECH
Suite 200, 240 Michael Cowpland Drive
Ottawa, Ontario
K2M 1P6

November 1, 2019
Revised: March 4, 2020
Revised: July 2, 2020
Revised: November 17, 2020
Revised: August 5, 2022
Revised: October 5, 2022
Revised: December 21, 2022

Novatech File: 112021-10
Ref: R-2019-189

NOVATECH
Engineers, Planners & Landscape Architects

December 21, 2022

City of Ottawa
Infrastructure Services and Community Sustainability
110 Laurier Avenue West, 4th Floor
Ottawa, ON K1P 1J1

Attention: **Mr. Kelby Lodoen Unseth, Planner II**

Dear Mr. Lodoen Unseth:

Reference: **Mattino Developments Inc.**
Block 21, Mattino Way
Servicing Design Brief
Our File No.: 112021-10

Enclosed for your review and approval is the revised Servicing Design Brief for the proposed Block 21 development.

If you have any questions or comments, please do not hesitate to contact us.

Sincerely,

NOVATECH

Lucas Wilson, P.Eng.
Project Manager

Suite 200, 240 Michael Cowpland Drive, Ottawa ON K2M 1P6 Tel: 613.254.9643 Fax: 613.254.5867 www.novatech-eng.com

TABLE OF CONTENTS

LIST OF TABLES

LIST OF FIGURES

APPENDICES

1.0 INTRODUCTION

The subject site is located within the Longfields community and is municipally known as 591 Via Mattino Way. The site is approximately 1.04 hectares and is bounded by a Transitway and Rail Corridor to the north and west, existing residential to the east, and the existing Longfields Central subdivision to the south. A key plan of the area is presented below in **Figure 1-1**.

Figure 1-1: Key Plan

The site is currently vacant. The proposed development will consist of 88 units in five three-storey apartment buildings (three 16-unit, two 20-unit apartments). The proposed site plan is shown in **Figure 2**.

This Servicing Design Brief provides information on the considerations and approach by which Novatech has analyzed the existing site information for the subject site, and details how the development lands will be serviced while meeting the City requirements and all other relevant regulations.

This report should be read in conjunction with the following:

- Geotechnical Investigation, 'Proposed Residential Development, Mountshannon Drive, Ottawa, Ontario' prepared by Paterson dated January 31, 2013.
- Geotechnical Review – Block 21 Existing Soils Information Memorandum, prepared by Paterson dated November 12, 2019 (PG2306-MEMO.08).
- Geotechnical Review – Block 21 Existing Information Memorandum, prepared by Paterson dated November 23, 2020 (PG2306-MEMO.09).



Figure 1-2: Site Plan

2.0 ROADWAYS

2.1 Existing Conditions

Currently there is access to the site through Via Mattino Way (Local Road).

2.2 Proposed Conditions

The development will be accessed from two entrances along Via Mattino Way.

All roads within the development are 6.7m private roads with at-grade parking.

2.3 Roadway Design

Paterson has prepared a Geotechnical Investigation report for the development (January 2013) that provides recommendations for roadway structure, servicing and foundations. The site consists of private roads and at-grade parking; the recommended roadway structure is as follows:

Table 2-1: Roadway Structure

Roadway Material Description	Pavement Structure Layer Thickness (mm)
	Private Road
Asphalt Wear Course: Superpave 12.5 (Class B)	40
Asphalt Binder Course: Superpave 19.0 (Class B)	50
Base: Granular A	150
Sub-Base: Granular B – Type II	400
Total	**640**

3.0 GRADING

3.1 Existing Conditions

The site has a high point along the centre (north to south) and slopes approximately 1.0% easterly and westerly.

A Geotechnical investigation was carried out by Paterson which included 10 test pits within the Longfields Central subdivision (4 within the subject site). Test pits were dug at depths ranging from 6.10m to 6.70m below existing grade with no bedrock encountered. Each test pit was dry upon completion; therefore, groundwater levels were estimated based on moisture levels and colour of the recovered soil samples and expected to be between 2m to 3m below existing ground.

3.2 Proposed Conditions

The design grades will tie into existing elevations along the Transitway to the west, Parkland to the north and east and the adjacent residential lands to the south. For detailed grading refer to drawing 112021-10-GR.

The proposed grading will fall within these ranges:

- Landscaped Area: Minimum 1% - Maximum 7%
- Roadway and Parking: Minimum 1.0%
- Maximum Terracing Grade of 3H:1V

4.0 EROSION AND SEDIMENT CONTROL

The following erosion and sediment control measures will be implemented during construction in accordance with the “Guidelines on Erosion and Sediment Control for Urban Construction Sites” (Government of Ontario, May 1987).

- A qualified inspector should conduct regular visits to ensure the contractor is working in accord with the drawings and that mitigation measures are implemented as specified;
- Filter socks are to be placed under all new and existing catchbasins and storm manhole covers;
- Mud mats are to be placed at the construction entrances;
- Silt fences around the area under construction to be placed per OPSS 577 and OPSD 219.110;
- Application of topsoil and sod to disturbed areas; and,
- After complete build-out, all sewers are to be inspected and cleaned and all sediment and construction fencing is to be removed.

The proposed erosion and sediment control measures will be implemented prior to construction and will remain in place during construction until vegetation is established. There will be regular inspection and maintenance of the sediment control measures. It is important that precautions be taken during construction to prevent sediment from entering the proposed stormwater management systems. The erosion and sediment control plan is provided in **Appendix C**.

5.0 SANITARY SEWERS

5.1 Existing Conditions

An existing 200mm diameter sanitary stub is located at the eastern access to the site (MH119). There is also an existing 400mm diameter trunk sewer located north of the site.

5.2 Proposed Conditions

The peak design flow parameters in **Table 5-1** have been used in the sewer capacity analysis.

Unit and population densities and all other design parameters are specified in the City of Ottawa Sewer Design Guidelines (October 2012) and Technical bulletin ISTB-2018-01.

Sanitary flow from Block 21 is proposed to connect into the existing 200mm diameter sanitary stub that was provided during the construction of Longfields Central. The sanitary sewer layout is shown on 112021-10-GP (**Appendix C**), and the design sheet is attached in **Appendix A**. The site (approx. 1.04ha) will outlet at MH 119 (east entrance) with a peak design flow of 2.5 L/s. The wastewater flow is routed through the Longfields Central Subdivsion, directing flow to the East Barrhaven Trunk (EBHT) sanitary sewer. The EBHT drains into the West Rideau Collector Sewer (WRCS) on Merivale Road and eventually makes its way to the Robert O. Pickard Environmental Centre to be treated before being released to the Ottawa River.

Table 5-1: Sanitary Sewer Design Parameters

Parameter	Design Parameter
Apartment (2 bedroom) Unit Population	2.1 people/unit
Apartment Unit Density	88 Units (per Site Plan)
Residential Flow Rate, Average Daily	280 L/cap/day
Residential Peaking Factor	Harmon Equation (min=2.0, max=4.0)
Total Infiltration Rate	0.33 L/s/ha
Minimum Pipe Size	200 mm
Minimum Velocity	0.6 m/s
Maximum Velocity	3.0 m/s

5.3 Offsite Requirements

For the design of Longfields Central, a peak design flow of 4.0 L/s was calculated from MH 119 to MH 117, accounting for future flows from Block 21 (Longfields Central sanitary design sheet excerpt included in **Appendix A**). With the detailed design of Block 21 being complete, the peak design flow calculated from MH 119 to MH 117 is now 3.2 L/s. Since the proposed flows are lower than previously accounted for in the Longfields Central Site Servicing and Stormwater Management Study, there will be sufficient capacity offsite to service the proposed development.



Figure 5-1: Sanitary Sewer Network

6.0 WATER

6.1 Existing Conditions

The proposed development is located inside the 2W Pressure Zone. Reconfiguration of the existing pressure zone from 2W to 3C is anticipated in 2020. Existing 200mm diameter stubs are located at both entrances to the site off Via Mattino Way. An existing 200mm diameter watermain run along Boulder Way north of the site.

6.2 Proposed Conditions

Block 21 will be connected to the existing watermain network by way of two separate feed points. The two connections are proposed to the existing 200mm diameter stubs located at the entrances off Via Mattino Way.

The development will be serviced by 200mm diameter watermains and will provide sufficient capacity to maintain appropriate pressures and fire flows throughout the development. **Figure 4** provides a high-level schematic of the proposed water distribution system.

The watermain boundary conditions below were obtained from the City of Ottawa and have been included in **Appendix A**:

Boundary Condition #1 – Located at Mountshannon Drive Existing 200mm x 400mm diameter watermain connection (Shown in **Appendix A**)

	Existing Zone 2W	Future Zone 3C
Demand Scenario	**Head (m)**	**Head (m)**
Maximum HGL	133.0	147.8
Peak Hour	126.0	146.3
Max Day + FF of 200 L/s	124.3	145.9
Max Day + FF of 250 L/s	123.2	145.4

Boundary Condition #2 – Located at Campanale Avenue (Shown in **Appendix A**)

	Existing Zone 2W	Future Zone 3C
Demand Scenario	**Head (m)**	**Head (m)**
Maximum HGL	133.0	147.8
Peak Hour	125.9	146.6
Max Day + FF of 200 L/s	119.4	141.6
Max Day + FF of 250 L/s	115.8	138.9

Construction of the first building within Block 21 is anticipated to be completed within 2021, later than what is anticipated for the reconfiguration to the future Zone 3C pressure zone. As such, the future Zone 3C boundary conditions will be used in the modelling for Block 21.

City of Ottawa watermain design Parameters are outlined in **Table 6-1**.

Figure 6-1: Watermain Layout

Table 6-1: Watermain Design Criteria

Design Parameter	Design Criteria
Apartment (2 bedroom) Unit Population	2.1 people/unit
Density	88 units
Residential Demand	280 L/c/d
Maximum Day Demand	2.5 x Average Day
Peak Hour Demand	2.2 x Maximum Day
Fire Demand	200 L/s (Building 5) 217 L/s (Building 2 and 3) 233 L/s (Building 1) 250 L/s (Building 4)
Maximum Pressure	690 kPa (100psi) unoccupied areas
Maximum Pressure	552 kPa (80psi) occupied areas outside of ROW
Minimum Pressure	275 kPa (40 psi) except during fire flow
Minimum Pressure	140 kPa (20 psi) fire flow conditions

Table 6-2: Water Flow Summary

Unit Type	Units	Population	Average Day Demand (L/s)	Maximum Day Demand (L/s)	Peak Hour Demand (L/s)
Apartments	88	185	0.599	1.497	3.294
Total	**88**	**185**	**0.599**	**1.497**	**3.294**

Based on the fire underwriters survey, the fire flows were calculated as 200 L/s (Building 5), 217 L/s (Building 2 and 3), 233 L/s (Building 1) and 250 L/s (Building 4). Hydrant spacing and locations per City of Ottawa guidelines are illustrated on the Fire Hydrant Coverage Plan in **Appendix A**. Fire flow calculations are provided in **Appendix A**.

The proposed watermain was modeled using EPANET 2 (See 112021-10-GP for detailed watermain layout).

A summary of the model results are shown below in **Table 6-3**, **Table 6-4** and **Table 6-5**. Full model results are included in **Appendix A**.

Table 6-3: Summary of Hydraulic Model Results - Maximum Day + Fire Flow

Operating Condition	Minimum Pressure
Building #1 (233 L/s)	277.43 kPa (HYD2)
Building #2 (217 L/s)	300.48 kPa (HYD2)
Building #3 (217 L/s)	285.96 kPa (HYD2)
Building #4 (250 L/s)	222.79 kPa (HYD2)
Building #5 (200 L/s)	316.18 kPa (HYD2)

Table 6-4: Summary of Hydraulic Model Results - Peak Hour Demand

Operating Condition	Maximum Pressure	Minimum Pressure
3.294 L/s through system	523.76 kPa (HYD1)	519.73 kPa (T1)

The hydraulic modeling summarized above highlights the maximum and minimum system pressures during Peak Hour/Maximum Pressure Check conditions, and the minimum system pressures during the Maximum Day + Fire conditions. Since the Maximum Day + Fire Flow pressures are above the minimum 140 kPa and the Peak Hour Pressures onsite fall within the normal operating pressure range (345 kPa to 552 kPa) we conclude the proposed water design will adequately service the development

Table 6-5: Summary of Hydraulic Model Results – Maximum Pressure Check

Operating Condition	Maximum Pressure	Minimum Pressure
0.599 L/s through system	559.07 kPa (HYD3)	532.29 kPa (CAP1)

Average day pressures at HYD3 are slightly above 552 kPa at 559.07 kPa. Since the average day pressures are modelled within the watermain and not the service to the units, lower pressures will be encountered at the upper levels. Pressures at the first floor were modelled at Building 1, nearest HYD3. The average day pressures within the units are below 552 kPa. We conclude that pressure reducing valves are not necessary to reduce the modelled pressure below 552 kPa within the watermain as the modelled average day pressures within the services to the units are within the required range.

7.0 STORMWATER MANAGEMENT

7.1 Stormwater Management Criteria

The following stormwater management criteria for the proposed development was prepared in accordance with the City of Ottawa Sewer Design Guidelines (October 2012) and the Longfields Central Site Servicing and Stormwater Management Study (Novatech, 2014). This report was prepared in accordance with the Longfields Davidson Heights Serviceability Study Update Report (1998).

- Provide a dual drainage system (i.e. minor and major system flows);
- Maximize the use of surface storage available on site;
- Control the runoff to MH122 to the allowable release rates Specified in **Section 7.1.1** using on-site storage;
- Ensure that no surface ponding will occur on the paved surfaces (i.e., private drive aisles or parking lots) during the 2-year storm event;
- Ensure that ponding is confined within the parking areas at a maximum depth of 0.35 m for both static ponding and dynamic flow; and,
- Provide guidelines to ensure that site preparation and construction is in accordance with the current Best Management Practices for Erosion and Sediment Control.

For the approval of the Longfields Central Subdivision, the following assumptions were made for the future development of Block 21 (see **Appendix B** for Longfields Central report excerpts):

- Restricted minor system flow of 37.5 L/s/ha;
- On-Site storage of 270 m^3 (270 m^3/ha);
    - 100 m^3 of surface storage;
    - 170 m^3 of underground storage (superpipe and/or storage chambers).

7.1.1 Allowable Release Rate

The allowable release rate for Block 21 (1.04 ha) was established based on the restricted minor system flow of 37.5 L/s/ha (37.6 L/s) for all storms up-to and including the 100-year storm event.

7.2 Existing Conditions

Existing 525mm and 675mm diameter storm sewers run along Via Mattino Way adjacent to the proposed development. Stubs were provided at both entrances to the site (MH122 and MH124), a 250mm diameter storm sewer at the west entrance (MH124) and a 525mm diameter storm sewer at the east entrance (MH122). An existing 1350mm diameter trunk storm sewer runs along the adjacent parkland to the north.

7.3 Proposed Conditions

Runoff from Block 21 will be routed to the existing storm sewer system in Via Mattino Way through the existing 525mm diameter stub located at the private entrance to the east (MH122). The storm system within Longfields Central is directed to the 1350mm diameter trunk storm sewer within Mountshannon Drive and ultimately outlets to the Longfields Davidson Heights Stormwater Management Facility located southwest of the Leikin Drive and Bill Leathem Drive intersection. This existing facility provides water quality control prior to discharging to the Rideau

River via Barrhaven Creek. As such, on-site stormwater quality controls are not required. **Figure 5** outlines the proposed storm sewer system layout, and how it will connect to the existing network along Via Mattino Way.



Figure 7-1: Storm Sewer Network

7.3.1 Quality Control

As previously discussed, the Lonfields Davidson Heights SWM Facility provides the Quality Control for the site. The proposed site has a drainage area of approximately 1.04 ha and a runoff coefficient of 0.71. The site was previously referred to as areas 2A & 2B in the Longfields Central Design, which had a drainage area of 1.00 ha and runoff coefficient of 0.80 ha (refer to excerpt provided in **Appendix B**). When comparing the area x runoff coefficient values the proposed site has the same area, but a lower runoff coefficient than what was previously allocated, as shown below:

Parameter	*Longfields Central Design*	*Current Design*
Drainage Area	1.00 ha	1.00 ha
Runoff Coefficient	0.80	0.71
Area x Runoff Coefficient	0.80	0.71

7.3.2 Minor System Design

Storm Sewers

The storm sewers comprising the minor system have been designed based on the criteria outlined in the Ottawa Sewer Design Guidelines using the principals of dual drainage. The design criteria used in sizing the storm sewers are summarized in **Table 6.1**.

The proposed storm sewers have been designed using the rational method to convey peak flows associated with a 2-year rainfall event. The storm sewer design sheets are provided in **Appendix A**. The corresponding Storm Drainage Area Plan (Drawing 112021-10-STM) is provided in **Appendix C**.

Table 7-1: Storm Sewer Design Parameters

Parameter	Design Criteria
Private Roads	2 Year Return Period
Storm Sewer Design	Rational Method
IDF Rainfall Data	Ottawa Sewer Design Guidelines
Initial Time of Concentration (T_c)	10 min
Minimum Velocity	0.8 m/s
Maximum Velocity	3.0 m/s
Minimum Diameter	250 mm

Underground Storage

The allowable release rate is quite restrictive, as such underground storage will be required to attenuate runoff from the site. Underground storage will be provided using a series of 600mm diameter storm sewers and 1200mm diameter structures providing approximately 67 m^3 of storage. Refer to the proposed General Plan of Services (112021-10-GP) for storage pipe layout.

7.3.3 Major System Design

The site has been designed to convey runoff from storms that exceed the minor system capacity to Via Mattino Way. The roadway and parking areas have been graded to ensure that the 100-year peak overland flows are confined within the parking area at a maximum flow depth of 300mm.

The site has been graded to provide an emergency overland flow route that spills along the roadway and outlets to Via Mattino Way at the eastern entrance to the site.

Surface Storage

The stage-storage curves for each inlet were calculated based on the proposed Grading Plan (drawing 112021-10-GR). The total surface storage shown in the stage-storage curves at each inlet is provided in **Appendix B**. Approximately 278 m^3 of total surface storage is available within the low-points of the parking areas and amenity space.

The total storage provided underground and on the surface is as follows:

Structure ID	Underground Storage (m^3)		Surface Storage (m^3)		Total Storage (m^3)	
	Required (100-YR)	Provided	Required (100-YR)	Provided	Required (100-YR)	Provided
CBMH1*	13	13	8	22	21	35
CBMH5	8	8	25	22	33	30
TOTAL	**21**	**21**	**33**	**44**	**54**	**65**
CBMH2*	-	-	14	15	14	15
TOTAL	**-**	**-**	**14**	**15**	**14**	**15**
MH7*	17	17	-	-	17	17
CBMH4	10	10	17	26	27	36
CBMH7	-	-	36	35	36	36
CB1	-	-	39	39	39	39
TOTAL	**27**	**27**	**92**	**100**	**119**	**128**
CBMH3*	11	11	41	39	52	50
CBMH8	-	-	20	36	20	36
TOTAL	**11**	**11**	**61**	**75**	**67**	**86**
CBMH6*	8	8	38	44	46	52
TOTAL	**8**	**8**	**38**	**44**	**46**	**52**
TOTAL OVERALL	**67**	**67**	**239**	**278**	**300**	**346**

*Structure with ICD.

7.4 Hydrologic & Hydraulic Modeling

The *City of Ottawa Sewer Design Guidelines* (October 2012) require hydrologic modeling for all dual drainage systems. The performance of the proposed storm drainage system for Block 21 was evaluated using the *PCSWMM* hydrologic/hydraulic modeling software.

Design Storms

The hydrologic analysis was completed using the following synthetic design storms and historical storms. The IDF parameters used to generate the design storms were taken from the Sewer Design Guidelines (October 2012).

3-Hour Chicago Storms:

25mm 3-hr Chicago storm
2-year 3-hr Chicago storm
5-year 3-hr Chicago storm
100-year 3-hr Chicago storm
100-year (+20%) 3-hr Chicago storm

12-Hour SCS Storms:

2-year 12-hr SCS storm
5-year 12-hr Chicago storm
100-year 12-hr Chicago storm
100-year (+20%) 12-hour SCS storm

The 3-hour Chicago distribution generates the highest peak flows for both the minor and major systems and was determined to be the critical storm distribution for the design of the storm drainage system.

The proposed drainage system has also been stress tested using a 3-hour Chicago design storm that has a 20% higher intensity and total volume compared to the 100-year event.

Model Development

The PCSWMM model accounts for both minor and major system flows *(dual drainage),* including the routing of flows through the storm sewer network *(minor system),* and overland along the road network *(major system).* The results of the analysis were used to:

- Ensure no ponding in the paved areas following a 2-year event;
- Calculate the storm sewer hydraulic grade line for the 100-year storm event;
- Evaluate overland flow depths and ponding volumes in the paved areas during the 100-year event; and
- Determine the total major and minor system runoff from the site to Via Mattino Way.

The model is capable of accounting for both static and dynamic storage within the private roadways and parking areas, including the overland flow across all high points and capture/bypass curves for inlets on continuous grade. The 100-year flow depths computed by the model represent the total (static + dynamic) ponding depths at low points for areas in road sags.

Storm Drainage Area Plan & Subcatchment Parameters

The Block 21 development has been divided into subcatchments based on the drainage areas tributary to each inlet of the proposed storm sewer system. The catchment areas are shown on the Storm Drainage Area Plan provided as drawing **112021-10-STM** in **Appendix C**.

The hydrologic parameters for each subcatchment were developed based on the Site Plan (**Figure 2**) and the Storm Drainage Area Plan specified above. Subcatchment parameters are outlined in **Table 7-2**.

Table 7-2: Subcatchment Model Parameters

Area ID	Catchment Area (ha)	Runoff Coefficient (C)	Percent Impervious (%)	Zero Imperv. (%)	Flow Length (m)	Equivalent Width (m)	Average Slope (%)
1	0.08	0.79	84%	25%	25	32	1%
2	0.14	0.75	79%	30%	25	52	1%
3	0.09	0.74	77%	40%	20	45	1%
4	0.12	0.76	80%	45%	20	60	1%
5	0.08	0.74	77%	30%	20	40	1%
6	0.11	0.72	74%	25%	20	55	1%
7	0.15	0.71	73%	40%	20	75	1%
8	0.13	0.69	70%	30%	20	65	1%
9	0.05	0.34	20%	25%	15	47	1%
10	0.04	0.70	71%	10%	15	27	1%
TOTAL	**1.00 ha**	**0.71**	**73%**	**-**	**-**	**-**	**-**

Infiltration

Infiltration losses for all catchment areas were modeled using Horton's infiltration equation, which defines the infiltration capacity of the soil over the duration of a precipitation event using a decay function that ranges from an initial maximum infiltration rate to a minimum rate as the storm progresses. The default values for the Sewer Design Guidelines were used for all catchments.

Horton's Equation:
$f(t) = f_c + (f_o - f_c)e^{-k(t)}$

Initial infiltration rate: f_o = 76.2 mm/hr
Final infiltration rate: f_c = 13.2 mm/hr
Decay Coefficient: k = 4.14/hr

Depression Storage

The default values for depression storage in the Sewer Design Guidelines were used for all catchments. Rooftops were assumed to provide no depression storage (Zero Imperv. Parameter).

- Depression Storage (pervious areas): 4.67 mm
- Depression Storage (impervious areas): 1.57 mm

Equivalent Width

Equivalent Width' refers to the width of the sub-catchment flow path. This parameter is calculated as described in the Sewer Design Guidelines, Section 5.4.5.6. The flow paths used to calculate the equivalent widths are shown on the PCSWMM schematics provided in **Appendix B**.

Impervious Values

Impervious values for each subcatchment area were calculated based on the proposed Site Plan (**Figure 2**) and correspond to the Runoff Coefficients using the following equation:

$$\%imp = \frac{C - 0.2}{0.7}$$

7.5 Results of Hydrologic / Hydraulic Analysis

The model was used to evaluate the performance of the proposed storm drainage system for Block 21.

7.5.1 Minor System

Inflows to the storm sewer were modeled based on the characteristics of each inlet. All the catchbasins in the parking areas are located at low points. Inflows to the storm sewer are based on the ICD specified for the inlet and the maximum depth of ponding. ICDs have been sized to limit the outlet peak flows to the allowable release rate. Details are outlined as follows in **Table 6.4**. ICDs information is indicated on the General Plan of Services (drawing 112021-10-GP).

Table 7-3: Inlet Control Devices & Design Flows

Structure ID	ICD Size & Inlet Rate						
	ICD Type	T/G (m)	Orifice Invert (m)	100-year Head on Orifice (m)	2-year Orifice Peak Flow* (L/s)	5-year Orifice Peak Flow* (L/s)	100-year Orifice Peak Flow* (L/s)
CBMH1	Tempest LMF (Vortex 78)	92.95	90.70	2.38	5.8	7.5	8.1
CBMH2	Tempest LMF (Vortex 70)	92.95	91.19	2.02	3.9	5.4	6.0
CBMH3	Tempest LFM (Vortex 86)	92.60	90.48	2.37	8.9	9.8	9.8
CBMH6	Tempest LMF (Vortex 72)	92.95	90.70	2.53	6.3	6.9	7.1
MH7	Tempest LMF (Vortex 69)	93.21	90.74	2.46	5.3	6.2	6.4

**PCSWMM model results for a 3-hour Chicago storm distribution.*

7.5.2 Major System

The major system network was evaluated using the PCSWMM model to ensure that the ponding depths conform to City standards. A summary of ponding depths at each inlet for the 2-year, 5-year, 100-year and 100-year (+20%) events are provided in **Appendix B**. The maximum static and dynamic ponding depths are less than 0.35m during all events, thereby meeting the major system criteria. In addition, there is no cascading flow over the highpoint during the 100-year storm event.

Table 7-4: Overland Flow Results (100-year, 3-hour Chicago storm event)

Structure	T/G	Max. Static Ponding		100-yr Event			
		Elev.	Spill Depth	Elev.	Depth	Cascading	Cascade Depth
	(m)	(m)	(m)	(m)	(m)	Flow?	(m)
CB1	92.95	93.20	0.25	93.20	0.25	N	0.00
CBMH1	92.95	93.17	0.22	93.08	0.13	N	0.00
CBMH2	92.95	93.22	0.27	93.20	0.25	N	0.00
CBMH3	92.60	92.85	0.25	92.85	0.25	N	0.00
CBMH4	92.95	93.25	0.30	93.20	0.25	N	0.00
CBMH5	92.85	93.07	0.22	93.08	0.23	Y	0.01
CBMH6	92.95	93.25	0.30	93.23	0.28	N	0.00
CBMH7	92.95	93.20	0.25	93.20	0.25	N	0.00
CBMH8	92.60	92.92	0.32	92.85	0.25	N	0.00

An expanded table of the ponding depths at low points in the roadway (including the stress-test event) is provided in **Appendix B**. Based on these results, the proposed storm drainage system will not experience any adverse flooding even with a 20% increase to the 100-year event.

7.5.3 Hydraulic Grade Line

The results of the analysis were used to determine if there would be any surcharging from the storm sewer system during the 100-year storm event. **Appendix B** provides a summary of the 100-year HGL elevation at each storm manhole within the proposed development, as well as a summary of the HGL elevations for a 20% increase (rainfall intensity and total precipitation) in the 100-year design event. The results of the HGL analysis and the stress testing indicates that the storm sewer does not surcharge during the 100-year event and 100-year+20% storm event

The results of the HGL analysis were used to ensure that a minimum freeboard of 0.30m is provided between the 100-year HGL and the designed underside of footing elevations. The 100-year HGL elevations at each storm manhole with respect to the lowest adjacent underside of footing elevation are provided in **Table 7-5**.

Table 7-5: 100-year HGL Elevations

Manhole ID	MH Invert Elevation (m)	T/G Elevation (m)	HGL Elevation (100yr) (m)	Design USF (m)	Clearance (100yr) (m)
HGL - Block 21					
MH01	90.01	92.75	90.68	91.51	0.83
MH03	90.19	93.40	90.69	91.51	0.82
MH05	90.32	93.23	90.69	91.53	0.84
MH07	90.74	93.21	90.79	91.70	0.91
MH09	90.52	93.23	90.70	91.74	1.04
EX MH122*	89.77	92.85	90.68	91.03	0.35

**Downstream 'fixed' outfall condition set at 100-year HGL within EX MH122 (90.68m). Initial depths based on fixed outfall elevation of 90.68m.*

An expanded table showing the results of the stress test (100-year +20% event) and the HGL elevations is provided in **Appendix B**. The stress test indicates that the HGL elevations will be below the USF elevations for this event.

7.5.4 Peak Flows

The overall release rates from the ICDs were added to determine the overall release rate from the site. The results of this analysis indicate that the allowable release rates will be met for each storm event. Refer to **Table 7-6** for the modelled peak flows for each storm event.

The results of the PCSWMM analysis indicate that outflows from the proposed development will not exceed the allowable release rate for all storm events.

Table 7-6: Summary of Peak Flows

Design Event	Allowable Release Rate (L/s)	Controlled Minor System Release Rate (L/s)	Major System Release Rate (L/s)
2-year	37.6	29.4	0
5-year		35.6	0
100-year		**37.4**	0
100-year (+20%)	-	37.6	102.9

**PCSWMM Model results for a 3-hr Chicago storm distribution; normal outfall condition.*

8.0 TEMPORARY FLOW CONTROLS DURING CONSTRUCTION

As specified in the City of Ottawa Sewer Design Guidelines (October, 2012), temporary flow controls are required during construction. This is to prevent the possibility of new incomplete sewer infrastructure from causing excessive flows within the existing / operational downstream sewer system.

8.1 Temporary Sanitary Flow Controls During Construction

During construction the incomplete sanitary sewer system will require a temporary flow control within the most downstream maintenance hole from the site (SAN MH-8). As the total sanitary flows from the proposed development are estimated to be 2.5 L/s a Tempest LMF ICD (Vortex – 45) will be required.

The design head for the Tempest LMF ICD (Vortex – 45) is 2.0m, as per the Ottawa Sewer Design Guidelines, as the depth in SAN MH-8 is 3.8m. Supporting correspondence and documentation for the Tempest LMF ICD is provided in **Appendix B**.

9.0 CONCLUSIONS AND RECOMMENDATIONS

The report conclusions are as follows:

1) The proposed storm system will control post-development flow to the allowable release rate of 37.5 L/s/ha. All runoff volume from the 100-year storm event is stored on site using underground and above ground storage. Underground storage will be provided using a series of 600mm diameter storm sewers and 1200mm diameter structures. The Longfields Davidson Heights Stormwater Management Facility provides water quality control.

2) The proposed sanitary sewer conforms to City design criteria and provides a gravity outlet for the development site. There is sufficient capacity in the downstream sanitary sewers to accommodate the flows outletting to the existing Mattino Way sanitary sewers.

3) Connection to the existing watermains in Mattino Way will provide municipal water service to the development.

4) There is adequate fire protection to the proposed development, in accordance with the Fire Underwriter's Survey.

5) The proposed infrastructure (sanitary, storm and water) complies with City of Ottawa design standards.

10.0 CLOSURE

This report is respectfully submitted for review and approval. Please contact the undersigned should you have questions or require additional information.

Sincerely,

NOVATECH

Prepared By:

Lucas Wilson, P.Eng.
Project Manager

Reviewed By:

Mark Bissett, P.Eng.
Senior Project Manager

APPENDIX A: Design Sheets

Storm Sewer Design Sheet (Rational Method)
Sanitary Sewer Design Sheets
Excerpt from Longfields Central Site Servicing Report (Sanitary Design Sheet)
Watermain Boundary Conditions
Watermain Boundary Conditions Verification Correspondence
Watermain Modelling
Fire Flow Calculations
Figure 1: Fire Hydrant Coverage Plan

Block 21, Mattino Way: Storm Sewer Design Sheet (Rational Method)

LOCATION			AREA								FLOW									PROPOSED SEWER							
Location	From Node	To Node	Hard Surface	Soft Surface	Towns Front Yard	Towns Front Yard	Towns Rear Yard	Towns Rear Yard	Total Area	Weighted Runoff Coefficient	Indivi 2.78 AR	Accum 2.78 AR	Time of Concentration	Rain Intensity (mm/hr)			Peak Flow	Total Peak Flow (Q)	Pipe	Size	Grade	Length	Capacity	Full Flow Velocity	Time of Flow	Q/Qfull
														2yr	5yr	10yr			Type							
			0.90	0.20	Area	c	Area	c	(ha)								(L/s)	(L/s)		(mm)	(%)	(m)	(l/s)	(m/s)	(min.)	(%)
Block 21																										
2, 3, 6	CBMH4	7	0.26	0.08					0.34	0.74	0.70	0.70	10.00	76.81			53.4	**53.4**	CONC	600	0.20	50.4	286.5	0.98	0.86	18.6%
									0.00		0.00	0.00	10.00				0.0									
									0.00		0.00	0.00	10.00													
2, 3, 6	7	3							0.00		0.00	0.70	10.86	73.67			51.2	**51.2**	PVC	300	1.00	39.7	100.9	1.38	0.48	50.8%
									0.00		0.00	0.00	10.86				0.0									
									0.00		0.00	0.00	10.86													
1, 4, 9, 10	9	5	0.20	0.09					0.29	0.68	0.55	0.55	10.00	76.81			42.3	**42.3**	PVC	375	0.25	50.3	91.5	0.80	1.05	46.2%
									0.00		0.00	0.00	10.00				0.0									
									0.00		0.00	0.00	10.00													
7	5	3	0.11	0.04					0.15	0.71	0.30	0.85	11.05	73.01			61.9	**61.9**	CONC	450	0.25	28.7	148.7	0.91	0.53	41.6%
									0.00		0.00	0.00	11.05				0.0									
									0.00		0.00	0.00	11.05													
	3	1							0.00		0.00	1.54	11.57	71.25			109.9	**109.9**	CONC	450	0.25	43.4	148.7	0.91	0.80	73.9%
									0.00		0.00	0.00	11.57				0.0									
									0.00		0.00	0.00	11.57													
5, 8	1	EX122	0.15	0.06					0.21	0.71	0.41	1.96	12.37	68.76			134.5	**134.5**	CONC	525	0.25	37.2	224.3	1.00	0.62	59.9%
									0.00		0.00	0.00	12.37				0.0									
									0.00		0.00	0.00	12.37													
Longfields Central																										
17, 27	EX126	EX124							0.00		0.00	0.00	10.00				0.0	**47.3**	PVC	300	0.40	45.0	63.8	0.87	0.86	74.2%
					0.22	0.62	0.05	0.54	0.27	0.61	0.45	0.45	10.00		104.19		47.3									
									0.00		0.00	0.00	10.00				0.0									
4, 5, 6	EX124	EX122							0.00		0.00	0.00	10.86				0.0	**132.0**	CONC	525	0.25	92.3	224.3	1.00	1.53	58.8%
					0.36	0.66	0.12	0.62	0.48	0.65	0.87	1.32	10.86		99.9		132.0									
									0.00		0.00	0.00	10.86				0.0									
	EX122	EX120							0.00		0.00	1.96	12.99	66.96			130.9	**250.8**	CONC	675	0.30	18.6	480.3	1.30	0.24	52.2%
									0.00		0.00	1.32	12.99		90.67		119.8									
									0.00		0.00	0.00	12.99				0.0									

Q = 2.78 AIR

WHERE : Q = PEAK FLOW IN LITRES PER SECOND (L/s)
A = AREA IN HECTARES (ha)
I = RAINFALL INTENSITY IN MILLIMETERS PER HOUR (mm/hr)
R = WEIGHTED RUNOFF COEFFICIENT

Q = (1/n) A R^(2/3)So^(1/2)

WHERE : Q = CAPACITY (L/s)
n = MANNING COEFFICIENT OF ROUGHNESS (0.013)
A = FLOW AREA (m^2)

Project: Block 21 (112021-10)
Designed: LRW
Checked: MAB
Date: June 16, 2022

NOVATECH
Engineers, Planners & Landscape Architects

Block 21, Mattino Way - Sanitary Sewer Design Sheet

AREA			RESIDENTIAL								INFILTRATION				PIPE							
			Towns		Apartments																	
ID	From	To	Units	Pop.	Units	Pop.	Pop.	Accum. Pop.	Peak Factor	Peak Flow (l/s)	Total Area (ha)	Accum. Area (ha)	Infilt. Flow (l/s)	**Total Flow (l/s)**	Size (mm)	Slope (%)	Length (m)	Capacity (l/s)	Full Flow Vel. (m/s)	Actual Vel. (m/s)	Q/Q_{full} (%)	d/D
Block 21																						
	6	**4**	0	0.0	88	184.8	184.8	184.8	3.5	2.1	0.86	0.86	0.3	2.4	200	0.65	73.0	27.6	0.85	0.43	8.7%	0.216
	4	**2**	0	0.0	0	0.0	0.0	184.8	3.5	2.1	0.02	0.88	0.3	2.4	200	0.65	43.4	27.6	0.85	0.43	8.7%	0.077
	2	**EX119**	0	0.0	0	0.0	0.0	184.8	3.5	2.1	0.15	1.03	0.3	2.5	200	0.65	40.8	27.6	0.85	0.43	8.9%	0.077
Via Mattino Way																						
	EX121	**EX119**	24	64.8	0	0.0	64.8	64.8	3.6	0.8	0.70	0.70	0.2	1.0	200	1.00	84.1	34.2	1.06	0.40	2.9%	0.108
	EX119	**EX117**	4	10.8	0	0.0	10.8	260.4	3.5	2.9	0.10	0.80	0.3	3.2	200	0.35	18.2	20.2	0.62	0.38	15.8%	0.297

Design Parameters:

Avg Flow/Person =	280	l/day			
Comm./Inst. Flow =	35000	l/ha/day			
Infiltration =	0.33	l/s/ha			
Pipe Friction n =	0.013				
Residential Peaking Factor = Harmon Equation (max 4, min 2)					

Population Density:

	ppl/unit	units/net ha
Apartment (2 Bedroom)	2.10	90
Singles	3.40	
Towns	2.70	60

Project: Block 21 (112021-10)

Designed: LRW

Checked: MAB

Date: June 16, 2020

NOVATECH
Engineers, Planners & Landscape Architects

Longfields Central
SANITARY SEWER DESIGN SHEET

AREA			RESIDENTIAL							ICI		INFILTRATION			Total Flow (l/s)	PIPE							
AREA ID	From	To	Towns	Stacked Towns	Java	Pop.	Accum. Pop.	Peak Factor	Peak Flow (l/s)	C/I Area (Ha)	Peak Flow (l/s)	Total Area (ha)	Accum. Area (ha)	Infilt. Flow (l/s)		Size (mm)	Slope (%)	Length (m)	Capacity (l/s)	Full Flow Vel. (m/s)	Q/Q_{full} (%)	d/D_{full}	v/V_{full} (%)
645 Longfields Drive																							
C1	C32	109	16			43.2	43.2	4.00	0.70			0.52	0.52	0.15	0.85	200	2.60	65.2	55.17	1.70	1.5%	0.08	33.0%
A20	111	109	4			10.8	10.8	4.00	0.18			0.20	0.20	0.06	0.23	200	2.00	24.9	48.39	1.49	0.5%	0.00	0.0%
A1	109	107	10			27.0	81.0	4.00	1.31			0.29	1.01	0.28	1.60	200	0.50	55.8	24.19	0.75	6.6%	0.16	54.0%
A2	107	105	10			27.0	108.0	4.00	1.75			0.27	1.28	0.36	2.11	200	0.55	35.4	25.38	0.78	8.3%	0.19	60.0%
A3	105	103	6			16.2	124.2	4.00	2.01			0.17	1.45	0.41	2.42	200	1.75	41.8	45.26	1.40	5.3%	0.16	54.0%
A5	121	119	25			67.5	67.5	4.00	1.09			0.70	0.70	0.20	1.29	200	1.00	84.1	34.22	1.06	3.8%	0.12	45.0%
A6,A7	119	117	2		80	149.4	216.9	4.00	3.51			1.10	1.80	0.50	4.02	200	0.35	18.2	20.24	0.62	19.9%	0.30	78.0%
A11,A21	117	115	1			2.7	219.6	4.00	3.56	0.20	0.17	0.28	2.08	0.58	4.31	200	0.35	28.5	20.24	0.62	21.3%	0.30	78.0%
A12	115	113	3			8.1	227.7	4.00	3.69			0.09	2.17	0.61	4.30	200	0.35	18.8	20.24	0.62	21.2%	0.30	78.0%
A4	113	103	21			56.7	284.4	4.00	4.61			0.57	2.74	0.77	5.38	200	0.35	75.5	20.24	0.62	26.6%	0.34	83.0%
A13,A14	103	101	11	10		56.7	465.3	3.99	7.52			0.52	4.71	1.32	8.84	200	0.35	67.9	20.24	0.62	43.7%	0.44	96.0%
	101	MS3				0.0	465.3	3.99	7.52			0.00	4.71	1.32	8.84	200	0.35	13.8	20.24	0.62	43.7%	0.44	96.0%
Existing in Mountshannon Drive																							
A15	MS1	MS3		16		43.2	43.2	4.00	0.70			0.38	0.38	0.11	0.81	250	0.30	75.8	33.98	0.67	2.4%	0.08	33.0%
Connection to EBHT																							
A19	MS3	K2				0.0	508.5	3.97	8.18			0.08	5.17	1.45	9.63	300	0.32	15.5	57.07	0.78	16.9%	0.27	73.0%

Design Parameters:

Avg Flow/Person =	350	l/day
Infiltration =	0.28	l/s/ha
Residential Peaking Factor = Harmon Equation (max 4, min 2)		
Pipe Friction n =	0.013	
Comm./Inst. Flow =	50000	l/ha/day
Peaking Factor Comm./Inst. =	1.5	

Population Density:

Towns	2.7	ppl/unit
Stacked Towns	2.7	ppl/unit
Java	1.8	ppl/unit

LICENSED PROFESSIONAL ENGINEER
M. A. BISSETT
2014-05-16
PROVINCE OF ONTARIO

NOVATECH ENGINEERING CONSULTANTS LTD.

Project: 112021
Designed: LRW
Checked: MAB
Date: May 16, 2014

Boundary Conditions for Longfields Block 21

Information Provided:
Date provided: Oct 2019

Scenario	Demand	
	L/min	L/s
Average Daily Demand	36	0.6
Maximum Daily Demand	90	1.5
Peak Hour	198	3.3
Fire Flow Demand #1	12000	200
Fire Flow Demand #2	15000	250

Location:

Results

Connection 1 - Boulder Way

Demand Scenario	Existing Zone 2W		Future Zone 3C	
	Head (m)	Pressure[1] (psi)	Head (m)	Pressure[1] (psi)
Maximum HGL	133.0	57.8	147.8	78.8
Peak Hour	125.9	47.9	146.2	76.6
Max Day plus Fire #1	117.4	35.7	138.6	65.9
Max Day plus Fire #2	112.7	29.1	134.5	60.0

[1] Ground Elevation = 92.3 m

Connection 2 - Mountshannon

Demand Scenario	Existing Zone 2W		Future Zone 3C	
	Head (m)	Pressure[1] (psi)	Head (m)	Pressure[1] (psi)
Maximum HGL	133.0	58.2	147.8	79.3
Peak Hour	126.0	48.2	146.3	77.1
Max Day plus Fire #1	124.3	45.9	145.9	76.6
Max Day plus Fire #2	123.2	44.3	145.4	75.9

[1] Ground Elevation = 92 m

Connection 3 - Campanale

Demand Scenario	Existing Zone 2W		Future Zone 3C	
	Head (m)	Pressure[1] (psi)	Head (m)	Pressure[1] (psi)
Maximum HGL	133.0	56.0	147.8	77.0
Peak Hour	125.9	46.0	146.6	75.4
Max Day plus Fire #1	119.4	36.7	141.6	68.2
Max Day plus Fire #2	115.8	31.6	138.9	64.4

[1] Ground Elevation = 93.6 m

Notes:

1) Confirm pressure reducing valves are not required once the pressure zone is reconfigured in 2020.
2) A 203 mm watermain was inserted in the model as shown on page 1.
3) Use the HGLs provided above to interpolate results for fires ranging from 200 l/s to 250 l/s, respectively.

Disclaimer

The boundary condition information is based on current operation of the city water distribution system. The computer model simulation is based on the best information available at the time. The operation of the water distribution system can change on a regular basis, resulting in a variation in boundary conditions. The physical properties of watermains deteriorate over time, as such must be assumed in the

absence of actual field test data. The variation in physical watermain properties can therefore alter the results of the computer model simulation. Fire Flow analysis is a reflection of available flow in the watermain; there may be additional restrictions that occur between the watermain and the hydrant that the model cannot take into account.

Block 21 Water Demand						
	Area (ha)	Units	Population	Average Day Demand (L/s)	Maximum Day Demand (L/s)	Peak Hour Demand (L/s)
Apartments	N/A	88	185	0.599	1.497	3.294
Total	**0.00**	**88**	**185**	**0.599**	**1.497**	**3.294**

Water Demand Parameters

Apartments (2 Bedroom)	2.1	ppl/unit
Residential Demand	280	L/c/day
Residential Max Day	2.5	x Avg Day
Residential Peak Hour	2.2	x Max Day
Residential Fire Flow	200, 217, 233, 250	L/s

Block 21 - Watermain Demand

Node	Apartments	Total Population	Average Day Residential Demand (L/s)	Maximum Day Residential Demand (L/s)	Peak Hour Residential Demand (L/s)	Fire Flow (L/s)
HYD1		0	0.000	0.000	0.000	233
HYD2	20	42	0.136	0.340	0.749	250
HYD3		0	0.000	0.000	0.000	250
NODE1	68	143	0.463	1.157	2.545	N/A
Total	**88**	**185**	**0.599**	**1.497**	**3.294**	

Water Demand Parameters

Singles	3.4	ppl/unit	Residential Max Day	2.5	x Avg Day
Apartments	2.1	ppl/unit	Residential Peak Hour	2.2	x Max Day
Residential Demand	280	L/c/day	Residential Fire Flow	200 - 250	L/s

Block 21 - Watermain Analysis

Network Table - Nodes - (Peak Hour)

Node ID	Elevation m	Demand LPS	Head m	Pressure m	Pressure kPa	Pressure psi
Junc HYD1	92.91	0	146.3	53.39	523.76	75.96
Junc HYD2	93.27	0.75	146.3	53.03	520.22	75.45
Junc HYD3	93.04	0	146.3	53.26	522.48	75.78
Junc T1	93.32	0	146.3	52.98	519.73	75.38
Junc NODE1	93.27	2.55	146.3	53.03	520.22	75.45
Resvr RES1	146.3	-0.37	146.3	0	0.00	0.00
Resvr RES2	146.6	-18.23	146.6	0	0.00	0.00

Network Table - Links - (Peak Hour)

Link ID	Length m	Diameter mm	Roughness	Flow LPS	Velocity m/s	Headloss m/km	Friction Factor
Pipe P1	40	204	110	3.07	0.09	0.09	0.041
Pipe P2	31	204	110	3.07	0.09	0.09	0.041
Pipe P3	39	204	110	0.75	0.02	0.01	0.051
Pipe P4	50	204	110	2.32	0.07	0.05	0.043
Pipe P5	51	204	110	-0.23	0.01	0.00	0.061
Pipe P6	72	204	110	-0.23	0.01	0.00	0.066

Block 21 - Watermain Analysis

Network Table - Nodes - (Max Pressure Check - Future Zone C3)

Node ID	Elevation m	Demand LPS	Head m	Pressure m	Pressure kPa	Pressure psi
Junc HYD1	92.91	0	147.8	54.89	538.47	78.10
Junc HYD2	93.27	0.14	147.8	54.53	534.94	77.59
Junc HYD3	93.04	0	147.8	54.76	559.07	81.09
Junc CAP1	93.54	0.11	147.8	54.26	532.29	77.20
Junc T1	93.32	0	147.8	54.48	534.45	77.52
Junc NODE1	93.27	0.35	147.8	54.53	534.94	77.59
Resvr RES1	147.8	-0.96	147.8	0	0.00	0.00
Resvr RES2	147.8	-0.87	147.8	0	0.00	0.00

Network Table - Links - (Max Pressure Check - Future Zone 3C)

Link ID	Length m	Diameter mm	Roughness	Flow LPS	Velocity m/s	Headloss m/km	Friction Factor
Pipe P1	40	204	110	-0.34	0.01	0.00	0.061
Pipe P2	31	204	110	-0.34	0.01	0.00	0.055
Pipe P3	39	204	110	-0.14	0.00	0.00	0.055
Pipe P4	50	204	110	-0.10	0.01	0.00	0.075
Pipe P5	51	204	110	0.26	0.01	0.00	0.058
Pipe P6	72	204	110	-0.26	0.01	0.00	0.058

Block 21 - Watermain Analysis

Network Table - Nodes - (Fire Flow Summary)

Fire Flow		Minimum Pressure		
Node	Flow (L/s)	Pressure (kPa)	Pressure (PSI)	Node
BLDG #1	233	277.43	40.24	HYD2
BLDG #2	217	300.48	43.58	HYD2
BLDG #3	217	285.96	41.48	HYD2
BLDG #4	250	222.79	32.31	HYD2
BLDG #5	200	316.18	45.86	HYD2

Block 21 - Watermain Analysis

Network Table - Nodes (Max Day + FF 'Bldg 1')

Node ID	Elevation m	Demand LPS	Head m	Pressure m	Pressure kPa	Pressure psi
Junc HYD1	92.91	95	122.06	29.15	285.96	41.48
Junc HYD2	93.27	43.34	121.55	28.28	277.43	40.24
Junc HYD3	93.04	95	122.33	29.29	287.33	41.67
Junc T1	93.32	0	122.03	28.71	281.65	40.85
Junc NODE1	93.27	1.16	122.04	28.77	282.23	40.93
Resvr RES1	145.6	-143.62	145.6	0	0.00	0.00
Resvr RES2	139.8	-94.4	139.8	0	0.00	0.00

Network Table - Links (Max Day + FF 'Bldg 1')

Link ID	Length m	Diameter mm	Roughness	Flow LPS	Velocity m/s	Headloss m/km	Friction Factor
Pipe P1	40	204	110	133.29	4.08	97.57	0.023
Pipe P2	31	204	110	38.29	1.17	9.69	0.028
Pipe P3	39	204	110	43.34	1.33	12.18	0.028
Pipe P4	50	204	110	5.05	0.15	0.23	0.038
Pipe P5	51	204	110	6.20	0.19	0.33	0.037
Pipe P6	72	204	110	-101.20	3.10	58.59	0.024

Block 21 - Watermain Analysis

Network Table - Nodes (Max Day + FF 'Bldg 2')

Node ID	Elevation m	Demand LPS	Head m	Pressure m	Pressure kPa	Pressure psi
Junc HYD1	92.91	95	124.82	31.91	313.04	45.40
Junc HYD2	93.27	61.34	123.9	30.63	300.48	43.58
Junc HYD3	93.04	61	125.5	32.46	318.43	46.18
Junc T1	93.32	0	124.81	31.49	308.92	44.80
Junc NODE1	93.27	1.16	124.81	31.54	309.41	44.88
Resvr RES1	145.7	-133.6	145.7	0	0.00	0.00
Resvr RES2	140.7	-88.42	140.7	0	0.00	0.00

Network Table - Links (Max Day + FF 'Bldg 2')

Link ID	Length m	Diameter mm	Roughness	Flow LPS	Velocity m/s	Headloss m/km	Friction Factor
Pipe P1	40	204	110	120.89	3.70	81.42	0.024
Pipe P2	31	204	110	59.89	1.83	22.17	0.026
Pipe P3	39	204	110	61.34	1.88	23.18	0.026
Pipe P4	50	204	110	1.45	0.04	0.02	0.046
Pipe P5	51	204	110	2.61	0.08	0.07	0.042
Pipe P6	72	204	110	-97.61	2.99	54.79	0.025

Block 21 - Watermain Analysis

Network Table - Nodes (Max Day + FF 'Bldg 3')

Node ID	Elevation m	Demand LPS	Head m	Pressure m	Pressure kPa	Pressure psi
Junc HYD1	92.91	61	125.16	32.25	316.37	45.89
Junc HYD2	93.27	95.34	122.42	29.15	285.96	41.48
Junc HYD3	93.04	61	125.26	32.22	316.08	45.84
Junc T1	93.32	0	124.47	31.15	305.58	44.32
Junc NODE1	93.27	1.16	124.8	31.53	309.31	44.86
Resvr RES1	145.7	-133.58	145.7	0	0.00	0.00
Resvr RES2	140.7	-88.45	140.7	0	0.00	0.00

Network Table - Links (Max Day + FF 'Bldg 3')

Link ID	Length m	Diameter mm	Roughness	Flow LPS	Velocity m/s	Headloss m/km	Friction Factor
Pipe P1	40	204	110	125.26	3.83	86.96	0.024
Pipe P2	31	204	110	64.26	1.97	25.26	0.026
Pipe P3	39	204	110	95.34	2.92	52.45	0.025
Pipe P4	50	204	110	31.08	0.95	6.58	0.029
Pipe P5	51	204	110	32.24	0.99	7.04	0.029
Pipe P6	72	204	110	-93.24	2.85	50.33	0.025

Block 21 - Watermain Analysis

Network Table - Nodes (Max Day + FF 'Bldg 4')

Node ID	Elevation m	Demand LPS	Head m	Pressure m	Pressure kPa	Pressure psi
Junc HYD1	92.91	60	119.21	26.3	258.00	37.42
Junc HYD2	93.27	95.34	115.98	22.71	222.79	32.31
Junc HYD3	93.04	95	118.61	25.57	250.84	36.38
Junc T1	93.32	0	118.04	24.72	242.50	35.17
Junc NODE1	93.27	1.16	118.6	25.33	248.49	36.04
Resvr RES1	145.4	-153.49	145.4	0	0.00	0.00
Resvr RES2	138.9	-101.53	138.9	0	0.00	0.00

Network Table - Links (Max Day + FF 'Bldg 4')

Link ID	Length m	Diameter mm	Roughness	Flow LPS	Velocity m/s	Headloss m/km	Friction Factor
Pipe P1	40	204	110	148.84	4.55	119.68	0.023
Pipe P2	31	204	110	53.84	1.65	18.20	0.027
Pipe P3	39	204	110	95.34	2.92	52.45	0.025
Pipe P4	50	204	110	41.50	1.27	11.24	0.028
Pipe P5	51	204	110	42.66	1.31	11.83	0.028
Pipe P6	72	204	110	-102.66	3.14	60.15	0.024

Block 21 - Watermain Analysis

Network Table - Nodes (Max Day + FF 'Bldg 5')

Node ID	Elevation m	Demand LPS	Head m	Pressure m	Pressure kPa	Pressure psi
Junc HYD1	92.91	53	128.23	35.32	346.49	50.25
Junc HYD2	93.27	94.34	125.5	32.23	316.18	45.86
Junc HYD3	93.04	53	128.27	35.23	345.61	50.13
Junc T1	93.32	0	127.52	34.2	335.50	48.66
Junc NODE1	93.27	1.16	127.86	34.59	339.33	49.22
Resvr RES1	145.9	-123.3	145.9	0	0.00	0.00
Resvr RES2	141.6	-81.73	141.6	0	0.00	0.00

Network Table - Links (Max Day + FF 'Bldg 5')

Link ID	Length m	Diameter mm	Roughness	Flow LPS	Velocity m/s	Headloss m/km	Friction Factor
Pipe P1	40	204	110	115.81	3.54	75.20	0.024
Pipe P2	31	204	110	62.81	1.92	24.22	0.026
Pipe P3	39	204	110	94.34	2.89	51.44	0.025
Pipe P4	50	204	110	31.53	0.96	6.76	0.029
Pipe P5	51	204	110	32.69	1.00	7.22	0.029
Pipe P6	72	204	110	-85.69	2.62	43.05	0.025

Block 21 - Watermain Analysis

Network Table - Nodes (Max Day + FF '20 psi')

Node ID	Elevation m	Demand LPS	Head m	Pressure m	Pressure kPa	Pressure psi
Junc H1	92.91	97	111.32	18.41	180.60	26.19
Junc H2	93.27	97.34	108.62	15.35	150.58	21.84
Junc H3	93.04	97	111.67	18.63	182.76	26.51
Junc T1	93.32	0	110.76	17.44	171.09	24.81
Junc NODE1	93.27	1.16	111.02	17.75	174.13	25.26
Resvr RES1	145.4	-171.72	145.4	0	0.00	0.00
Resvr RES2	138.9	-124.31	138.9	0	0.00	0.00

Network Table - Links (Max Day + FF '20 psi')

Link ID	Length m	Diameter mm	Roughness	Flow LPS	Velocity m/s	Headloss m/km	Friction Factor
Pipe P1	40	204	110	166.67	5.10	147.58	0.023
Pipe P2	31	204	110	69.67	2.13	29.34	0.026
Pipe P3	39	204	110	97.34	2.98	54.51	0.025
Pipe P4	50	204	110	27.67	0.85	5.31	0.030
Pipe P5	51	204	110	28.83	0.88	5.72	0.029
Pipe P6	72	204	110	-125.83	3.85	87.69	0.024

FUS - Fire Flow Calculations

As per 2020 Fire Underwriter's Survey Guidelines

NOVATECH
Engineers, Planners & Landscape Architects

Novatech Project #: 112021-10
Project Name: Block 21
Date: 12/14/2022
Input By: Lucas Wilson
Reviewed By: Mark Bissett

Legend

Building Description: Bldg 1, 16 Unit Apartment
Type V - Wood frame

Step			Input		Value Used	Total Fire Flow (L/min)
Base Fire Flow						
1	**Construction Material**			**Multiplier**		
	Coefficient related to type of construction **C**	Type V - Wood frame	Yes	1.5	1.5	
		Type IV - Mass Timber		Varies		
		Type III - Ordinary construction		1		
		Type II - Non-combustible construction		0.8		
		Type I - Fire resistive construction (2 hrs)		0.6		
2	**Floor Area**					
	A	Building Footprint (m^2)	460			
		Number of Floors/Storeys	3			
		Area of structure considered (m^2)			**1,380**	
	F	**Base fire flow without reductions**				**12,000**
		F = 220 **C** (**A**)$^{0.5}$				
Reductions or Surcharges						
3	**Occupancy hazard reduction or surcharge**		**FUS Table 3**	**Reduction/Surcharge**		
	(1)	Non-combustible	Yes	-25%	-25%	**9,000**
		Limited combustible		-15%		
		Combustible		0%		
		Free burning		15%		
		Rapid burning		25%		
4	**Sprinkler Reduction**		**FUS Table 4**	**Reduction**		
	(2)	Adequately Designed System (NFPA 13)		-30%		**0**
		Standard Water Supply		-10%		
		Fully Supervised System		-10%		
				Cumulative Sub-Total	**0%**	
		Area of Sprinklered Coverage (m^2)	0	0%		
				Cumulative Total	**0%**	
5	**Exposure Surcharge**		**FUS Table 5**		**Surcharge**	
	(3)	North Side	3.1 - 10 m		20%	**4,500**
		East Side	20.1 - 30 m		10%	
		South Side	3.1 - 10 m		20%	
		West Side	>30m		0%	
				Cumulative Total	**50%**	
Results						
6	**(1) + (2) + (3)**	**Total Required Fire Flow, rounded to nearest 1000L/min**			**L/min**	**14,000**
		(2,000 L/min < Fire Flow < 45,000 L/min)		or	L/s	**233**
				or	USGPM	3,699

FUS - Fire Flow Calculations

As per 2020 Fire Underwriter's Survey Guidelines

NOVATECH
Engineers, Planners & Landscape Architects

Novatech Project #: 112021-10
Project Name: Block 21
Date: 12/14/2022
Input By: Lucas Wilson
Reviewed By: Mark Bissett

Legend

Building Description: Bldg 2, 16 Unit Apartment
Type V - Wood frame

Step			Input		Value Used	Total Fire Flow (L/min)
Base Fire Flow						
1	**Construction Material**			**Multiplier**		
	Coefficient related to type of construction **C**	Type V - Wood frame	Yes	1.5	1.5	
		Type IV - Mass Timber		Varies		
		Type III - Ordinary construction		1		
		Type II - Non-combustible construction		0.8		
		Type I - Fire resistive construction (2 hrs)		0.6		
2	**Floor Area**					
	A	Building Footprint (m^2)	460			
		Number of Floors/Storeys	3			
		Area of structure considered (m^2)			**1,380**	
	F	**Base fire flow without reductions**				**12,000**
		F = 220 **C** (**A**)$^{0.5}$				
Reductions or Surcharges						
3	**Occupancy hazard reduction or surcharge**		**FUS Table 3**	**Reduction/Surcharge**		
	(1)	Non-combustible	Yes	-25%	-25%	**9,000**
		Limited combustible		-15%		
		Combustible		0%		
		Free burning		15%		
		Rapid burning		25%		
4	**Sprinkler Reduction**		**FUS Table 4**	**Reduction**		
	(2)	Adequately Designed System (NFPA 13)		-30%		**0**
		Standard Water Supply		-10%		
		Fully Supervised System		-10%		
				Cumulative Sub-Total	**0%**	
		Area of Sprinklered Coverage (m^2)	0	0%		
				Cumulative Total	**0%**	
5	**Exposure Surcharge**		**FUS Table 5**		**Surcharge**	
	(3)	North Side	3.1 - 10 m		20%	**4,050**
		East Side	>30m		0%	
		South Side	10.1 - 20 m		15%	
		West Side	20.1 - 30 m		10%	
				Cumulative Total	**45%**	
Results						
6	**(1) + (2) + (3)**	**Total Required Fire Flow, rounded to nearest 1000L/min**			**L/min**	**13,000**
		(2,000 L/min < Fire Flow < 45,000 L/min)		or	L/s	**217**
				or	USGPM	3,435

FUS - Fire Flow Calculations

As per 2020 Fire Underwriter's Survey Guidelines

NOVATECH
Engineers, Planners & Landscape Architects

Novatech Project #: 112021-10
Project Name: Block 21
Date: 12/14/2022
Input By: Lucas Wilson
Reviewed By: Mark Bissett

Legend

Building Description: Bldg 3, 16 Unit Apartment
Type V - Wood frame

Step			Input		Value Used	Total Fire Flow (L/min)
Base Fire Flow						
1	**Construction Material**			**Multiplier**		
	Coefficient related to type of construction **C**	Type V - Wood frame	Yes	1.5	1.5	
		Type IV - Mass Timber		Varies		
		Type III - Ordinary construction		1		
		Type II - Non-combustible construction		0.8		
		Type I - Fire resistive construction (2 hrs)		0.6		
2	**Floor Area**					
	A	Building Footprint (m^2)	460			
		Number of Floors/Storeys	3			
		Area of structure considered (m^2)			**1,380**	
	F	**Base fire flow without reductions**				**12,000**
		F = 220 **C** (**A**)$^{0.5}$				
Reductions or Surcharges						
3	**Occupancy hazard reduction or surcharge**		**FUS Table 3**	**Reduction/Surcharge**		
	(1)	Non-combustible	Yes	-25%	-25%	**9,000**
		Limited combustible		-15%		
		Combustible		0%		
		Free burning		15%		
		Rapid burning		25%		
4	**Sprinkler Reduction**		**FUS Table 4**	**Reduction**		
	(2)	Adequately Designed System (NFPA 13)		-30%		**0**
		Standard Water Supply		-10%		
		Fully Supervised System		-10%		
				Cumulative Sub-Total	**0%**	
		Area of Sprinklered Coverage (m^2)	0	0%		
				Cumulative Total	**0%**	
5	**Exposure Surcharge**		**FUS Table 5**		**Surcharge**	
	(3)	North Side	20.1 - 30 m		10%	**3,600**
		East Side	>30m		0%	
		South Side	3.1 - 10 m		20%	
		West Side	20.1 - 30 m		10%	
				Cumulative Total	**40%**	
Results						
6	**(1) + (2) + (3)**	**Total Required Fire Flow, rounded to nearest 1000L/min**			**L/min**	**13,000**
		(2,000 L/min < Fire Flow < 45,000 L/min)		or	L/s	**217**
				or	USGPM	3,435

FUS - Fire Flow Calculations

As per 2020 Fire Underwriter's Survey Guidelines

NOVATECH
Engineers, Planners & Landscape Architects

Novatech Project #: 112021-10
Project Name: Block 21
Date: 12/14/2022
Input By: Lucas Wilson
Reviewed By: Mark Bissett

Legend

Building Description: Bldg 4, 20 Unit Apartment
Type V - Wood frame

Step			Input		Value Used	Total Fire Flow (L/min)
Base Fire Flow						
1	**Construction Material**			**Multiplier**		
	Coefficient related to type of construction **C**	Type V - Wood frame	Yes	1.5	1.5	
		Type IV - Mass Timber		Varies		
		Type III - Ordinary construction		1		
		Type II - Non-combustible construction		0.8		
		Type I - Fire resistive construction (2 hrs)		0.6		
2	**Floor Area**					
	A	Building Footprint (m^2)	570			
		Number of Floors/Storeys	3			
		Area of structure considered (m^2)			**1,710**	
	F	**Base fire flow without reductions**				**14,000**
		F = 220 **C** (**A**)$^{0.5}$				
Reductions or Surcharges						
3	**Occupancy hazard reduction or surcharge**		**FUS Table 3**	**Reduction/Surcharge**		
	(1)	Non-combustible	Yes	-25%	-25%	**10,500**
		Limited combustible		-15%		
		Combustible		0%		
		Free burning		15%		
		Rapid burning		25%		
4	**Sprinkler Reduction**		**FUS Table 4**	**Reduction**		
	(2)	Adequately Designed System (NFPA 13)		-30%		**0**
		Standard Water Supply		-10%		
		Fully Supervised System		-10%		
				Cumulative Sub-Total	**0%**	
		Area of Sprinklered Coverage (m^2)	0	0%		
				Cumulative Total	**0%**	
5	**Exposure Surcharge**		**FUS Table 5**		**Surcharge**	
	(3)	North Side	20.1 - 30 m		10%	**4,200**
		East Side	20.1 - 30 m		10%	
		South Side	3.1 - 10 m		20%	
		West Side	>30m		0%	
				Cumulative Total	**40%**	
Results						
6	**(1) + (2) + (3)**	**Total Required Fire Flow, rounded to nearest 1000L/min**			**L/min**	**15,000**
		(2,000 L/min < Fire Flow < 45,000 L/min)		or	L/s	**250**
				or	USGPM	3,963

FUS - Fire Flow Calculations

As per 2020 Fire Underwriter's Survey Guidelines

NOVATECH
Engineers, Planners & Landscape Architects

Novatech Project #: 112021-10
Project Name: Block 21
Date: 12/14/2022
Input By: Lucas Wilson
Reviewed By: Mark Bissett

Legend

Building Description: Bldg 5, 20 Unit Apartment
Type V - Wood frame

Step			Input		Value Used	Total Fire Flow (L/min)
Base Fire Flow						
1	**Construction Material**			**Multiplier**		
	Coefficient related to type of construction **C**	Type V - Wood frame	Yes	1.5	1.5	
		Type IV - Mass Timber		Varies		
		Type III - Ordinary construction		1		
		Type II - Non-combustible construction		0.8		
		Type I - Fire resistive construction (2 hrs)		0.6		
2	**Floor Area**					
	A	Building Footprint (m^2)	570			
		Number of Floors/Storeys	3			
		Area of structure considered (m^2)			**1,710**	
	F	**Base fire flow without reductions**				**14,000**
		F = 220 **C** (**A**)$^{0.5}$				
Reductions or Surcharges						
3	**Occupancy hazard reduction or surcharge**		**FUS Table 3**	**Reduction/Surcharge**		
	(1)	Non-combustible	Yes	-25%	-25%	**10,500**
		Limited combustible		-15%		
		Combustible		0%		
		Free burning		15%		
		Rapid burning		25%		
4	**Sprinkler Reduction**		**FUS Table 4**	**Reduction**		
	(2)	Adequately Designed System (NFPA 13)		-30%		**0**
		Standard Water Supply		-10%		
		Fully Supervised System		-10%		
				Cumulative Sub-Total	**0%**	
		Area of Sprinklered Coverage (m^2)	0	0%		
				Cumulative Total	**0%**	
5	**Exposure Surcharge**		**FUS Table 5**		**Surcharge**	
	(3)	North Side	>30m		0%	**1,050**
		East Side	>30m		0%	
		South Side	20.1 - 30 m		10%	
		West Side	>30m		0%	
				Cumulative Total	**10%**	
Results						
6	**(1) + (2) + (3)**	**Total Required Fire Flow, rounded to nearest 1000L/min**			**L/min**	**12,000**
		(2,000 L/min < Fire Flow < 45,000 L/min)		or	L/s	**200**
				or	USGPM	3,170



NOVATECH
Engineers, Planners & Landscape Architects
Suite 200, 240 Michael Cowpland Drive
Ottawa, Ontario, Canada K2M 1P6

Telephone (613) 254-9643
Facsimile (613) 254-5867
Website www.novatech-eng.com

CITY OF OTTAWA
LONGFIELDS CENTRAL - BLOCK 21

FIRE HYDRANT COVERAGE PLAN

SCALE 1 : 1000 (0, 10, 20, 30, 40)

DATE OCTOBER 2022 | JOB 112021-10 | FIGURE FIG-1

SHT8X11.DWG - 216mmx279mm

M:\2012\112021\Block 21\CAD\Design\Figures\Design Brief\Fig 1-HYD Coverage Plan.dwg, FIG1, Oct 04, 2022 - 3:15pm, lwilson

Lucas Wilson

From: Sharif, Golam <sharif.sharif@ottawa.ca>
Sent: Wednesday, December 21, 2022 8:51 AM
To: Lucas Wilson
Cc: Mark Bissett
Subject: RE: Block 21 - 605 Via Way: Watermain Boundary Condition Verification

Hi Lucas,

I have received the confirmation from our water modelling unit. There is no significant change on the BC, therefore use the 2019 BC. Please attached the correspondence in your report. Thanks.

Sharif

From: Lucas Wilson <l.wilson@novatech-eng.com>
Sent: December 19, 2022 3:21 PM
To: Sharif, Golam <sharif.sharif@ottawa.ca>
Cc: Mark Bissett <m.bissett@novatech-eng.com>
Subject: RE: Block 21 - 605 Via Way: Watermain Boundary Condition Verification

Just wanted to follow up with you regarding the boundary condition verification. Since the fire flows haven't changed, is a verification still required?

Thanks,
Lucas Wilson, P.Eng., Project Manager | Engineering
NOVATECH Engineers, Planners & Landscape Architects
240 Michael Cowpland Drive, Suite 200, Ottawa, ON K2M 1P6 | Tel: 613.254.9643 Ext: 282 | Fax: 613.254.5867

From: Lucas Wilson
Sent: Wednesday, December 14, 2022 2:06 PM
To: Sharif, Golam <sharif.sharif@ottawa.ca>
Cc: Mark Bissett <m.bissett@novatech-eng.com>
Subject: RE: Block 21 - 605 Via Way: Watermain Boundary Condition Verification

Sharif – Previously provided fire flow values have been confirmed using the 2020 FUS guidelines (no change to fire flows), revised spreadsheet referencing 2020 FUS is attached.

Let me know if you need anything else.

Thanks,

Lucas Wilson, P.Eng., Project Manager | Engineering
NOVATECH Engineers, Planners & Landscape Architects
240 Michael Cowpland Drive, Suite 200, Ottawa, ON K2M 1P6 | Tel: 613.254.9643 Ext: 282 | Fax: 613.254.5867

From: Sharif, Golam <sharif.sharif@ottawa.ca>
Sent: Wednesday, December 14, 2022 12:09 PM
To: Lucas Wilson <l.wilson@novatech-eng.com>
Cc: Mark Bissett <m.bissett@novatech-eng.com>
Subject: RE: Block 21 - 605 Via Way: Watermain Boundary Condition Verification

HI Lucas,

Could you please update your FUS calculation. I believe your design and units have not changed, however, the 1999 FUS guideline has been updated. Please update that and we can verify if we can still use those BC. Thanks.

Sharif

From: Lucas Wilson <l.wilson@novatech-eng.com>
Sent: December 13, 2022 3:26 PM
To: Sharif, Golam <sharif.sharif@ottawa.ca>
Cc: Mark Bissett <m.bissett@novatech-eng.com>
Subject: Block 21 - 605 Via Way: Watermain Boundary Condition Verification

It has been requested in the most recent City of Ottawa comments to request a new boundary condition verification as the boundary conditions attached are from 2019. I have also attached the water demand and fire flows provided in the most recent submission.

Water Demand:
Average Day Demand = 0.599 L/s
Max Day Demand = 1.497 L/s
Peak Hour Demand = 3.294 L/s

Residential fire flows:
Building 1 = 233 L/s
Building 2 = 217 L/s
Building 3 = 217 L/s
Building 4 = 250 L/s
Building 5 = 200 L/s

Please let me know if you need any additional information.

Thanks,
Lucas Wilson, P.Eng., Project Manager | Engineering
NOVATECH Engineers, Planners & Landscape Architects
240 Michael Cowpland Drive, Suite 200, Ottawa, ON K2M 1P6 | Tel: 613.254.9643 Ext: 282 | Fax: 613.254.5867

'

'
'

This e-mail originates from the City of Ottawa e-mail system. Any distribution, use or copying of this e-mail or the information it contains by other than the intended recipient(s) is unauthorized. Thank you.

Le présent courriel a été expédié par le système de courriels de la Ville d'Ottawa. Toute distribution, utilisation ou reproduction du courriel ou des renseignements qui s'y trouvent par une personne autre que son destinataire prévu est interdite. Je vous remercie de votre collaboration.

'

APPENDIX B

Excerpts from Longfields Central Site Servicing Report

Tempest LMF Correspondence & Documentation

PCSWMM Storage Node Curves

PCSWMM Model Results (Ponding)
PCSWMM Model Results (HGL)

PCSWMM Model Schematics
PCSWMM Model Results (100-year output data)

LEGEND

- DRAINAGE AREA (hectares) / AREA ID / RUN-OFF COEFFICIENT
- STATIC PONDING - MAX. EXTENT OF STATIC PONDING VOLUME
- DYNAMIC PONDING - MAX. EXTENT OF DYNAMIC PONDING VOLUME
- PROPOSED STORM MANHOLE & SEWER WITH DIRECTION OF FLOW
- EXISTING STORM MANHOLE & SEWER WITH DIRECTION OF FLOW
- PROPOSED ROAD CATCHBASIN
- EXISTING ROAD CATCHBASIN
- MAJOR SYSTEM FLOW ROUTE

CATCH BASIN TABLE

CB ID	T/G ELEV (m)	INVERT (m)	I.C.D.
1	92.19	S=90.59 E=90.57	HYDROVEX 75 VHV-1
2	92.20	N=90.67	-
3	92.43	N=91.03	HYDROVEX 75 VHV-1
4	92.44	W=90.94 W=90.92	HYDROVEX 75 VHV-1
5	92.44	E=91.04	-
6	92.55	SW=91.15	-
7	92.55	NE=91.06 NE=91.05	HYDROVEX 125 VHV-2
8	92.42	W=90.92 W=90.94	HYDROVEX 125 VHV-2
9	92.42	E=91.02	-
10	92.49	S=91.01 S=90.99	HYDROVEX 125 VHV-2
11	92.49	N=91.09	-
12	92.63	SW=91.14 S=91.13	HYDROVEX 75 VHV-1
13	92.63	NE=91.23	-
14	92.83	NW=91.43	-
15	92.80	SE=91.34 E=91.33	HYDROVEX 75 VHV-1
16	92.88	NW=91.48	-
17	92.83	SE=91.38 E=91.37	94mm

* ALL SETS OF CATCHBASINS ARE TO BE INTERCONNECTED WITH A SINGLE ICD, UNLESS STATED OTHERWISE

STM MANHOLE TABLE

MANHOLE ID	OBVERT
100	SE=89.07 SW=89.07 NW=89.07
102	NE=89.15 SW=89.15
104	NE=89.27 W=89.66
106	E=89.91 N=89.91 W=89.91
108	E=90.16 NW=90.16
110	SE=90.38 NW=90.38
112	SE=90.72 SW=90.72 NW=90.72
114	SE=91.03
116	S=90.18 NW=90.18
118	SE=90.25 W=90.28
120	E=90.39 W=90.39
122	E=90.44 NE=90.44 NW=90.44
124	SW=90.67 SE=90.67 NE=90.67
126	NE=90.85
KT208	S=89.51 NW=89.51
KT209	SE=89.15 N=89.15
KT539	S=89.32 N=89.32
MS2	W=90.26 N=90.34
MS4	S=90.23 N=89.42

NOTE:
THE POSITION OF ALL POLE LINES, CONDUITS, WATERMAINS, SEWERS AND OTHER UNDERGROUND AND OVERGROUND UTILITIES AND STRUCTURES IS NOT NECESSARILY SHOWN ON THE CONTRACT DRAWINGS, AND WHERE SHOWN, THE ACCURACY OF THE POSITION OF SUCH UTILITIES AND STRUCTURES IS NOT GUARANTEED. BEFORE STARTING WORK, DETERMINE THE EXACT LOCATION OF ALL SUCH UTILITIES AND STRUCTURES AND ASSUME ALL LIABILITY FOR DAMAGE TO THEM.

Mattino DEVELOPMENTS INC.
171 CLARIDGE DRIVE
OTTAWA, ON
K2J 5V8

No.	REVISION	DATE	BY
6.	REVISED PER CITY COMMENTS	JUL 25/14	MAB
5.	ISSUED WITH MOE APPLICATION	JUN 12/14	MAB
4.	REVISED PER CITY COMMENTS	MAY 16/14	MAB
3.	REVISED PER CITY COMMENTS	APR 03/14	MAB
2.	REVISED PLAN OF SUBDIVISION	FEB 14/14	MAB
1.	ISSUED FOR APPROVAL	JUN 07/13	KJM

SCALE 1:500

DESIGN LRW
CHECKED MAB
DRAWN DTD
CHECKED MAB
APPROVED JGR

FOR REVIEW ONLY

REGISTERED PROFESSIONAL ENGINEER J.G. RIDDELL PROVINCE OF ONTARIO
LICENSED PROFESSIONAL ENGINEER M.A. BISSETT 2014-07-25 PROVINCE OF ONTARIO

NOVATECH
Engineers, Planners & Landscape Architects
Suite 200, 240 Michael Cowpland Drive
Ottawa, Ontario, Canada K2M 1P6
Telephone (613) 254-9643
Facsimile (613) 254-5867
Website www.novatech-eng.com

CITY of OTTAWA
LONGFIELDS CENTRAL
591 LONGFIELDS DRIVE

STORM DRAINAGE AREA PLAN

PROJECT No. 112021
REV REV # 6
DRAWING No. 112021-STM

Longfields Central
Site Servicing and Stormwater Management Study

Prepared for:

171 Claridge Drive
Ottawa, ON
K2J 5V8

Prepared by:

NOVATECH ENGINEERING CONSULTANTS LTD.
Suite 200, 240 Michael Cowpland Drive
Kanata, Ontario
K2M 1P6

Issued: June 7, 2013
Revised: February 14, 2014
Revised: April 3, 2014
Revised: May 16, 2014
Revised: June 12, 2014
Revised: July 25, 2014

Ref: R-2014-073
Novatech File No. 112021

November 22, 2013

- Longfields Development (by Campanale)
    - Revised Rearyard Areas: 0.34 ha + 0.29ha = 0.63 ha @ C = 0.54
    - Right-Of-Way Areas: 0.28 ha+ 0.09 ha = 0.37 ha @ C = 0.69

It is therefore noted that the revised areas contributing from the Campanale Development total to 1.0 ha and may cause an increase in major system flow contributing to SWM Park 959.

5.4.5 Future Development Blocks

During detailed design of the Longfields Development, it was determined that the medium density residential area is unable to provide the 64 L/s/ha and 100 m^3/ha through surface storage within the roadway and rearyard areas as requested in the *Longfields Davidson Heights Serviceability Study Update Report (1998)*. To achieve the guidelines set out in the Longfields Davidson Heights Serviceability Study Update Report (1998) throughout the development, the following high unit residential blocks will be restricted to the design criteria provided below:

Block 1 (0.21 ha)

- Restricted minor system flow of 6.0 L/s (28.8 L/s/ha)
- On-Site storage of 20.8 m^3 (100 m^3/ha)

Block 2 (0.15 ha)

- Restricted minor system flow of 9.6 L/s (64 L/s/ha)
- On-Site storage of 25 m^3 (167 m^3/ha)

Block 21 (1.0 ha)

- Restricted minor system flow of 37.6 L/s (37.5 L/s/ha)
- On-Site storage of 270 m^3 (270 m^3/ha)
    - 100 m^3 of surface storage
    - 170 m^3 of underground storage using either:
        - Superpipe storage
        - Underground storage chambers

It has been determined that the storage suggested above for each future residential block is sufficient for each block and can be accommodated through both surface and subsurface storage. Conditions must be placed within the subdivision agreement and registered on title for the site plan for all future blocks for the on-site storage criteria and restrictive release rates provided above.

Conceptual calculations have been completed for Block 21 to ensure sufficient storage is available within the future block. Through conceptual grading, it was determined that 100 m^3 of surface storage can be provided within storage sags throughout the parking lot areas. The additional 170 m^3 of necessary storage will be provided beneath the parking lot areas throughout the block using underground storage chambers. The chambers will be installed to provide temporary subsurface storage of runoff from storms up to 1:100 year event. The chambers conceptually designed for this report are provided by Stormtech (or approved equivalent) and have been designed with the following system requirements:

TEMPEST Product Submittal Package R3

Date: June 15, 2022

Customer: Novatech

Contact: Lucas Wilson

Location: Ottawa

Project Name: Mattino Way

IPEX

Tempest LMF ICD Rd Shop Drawing







SECTION A-A

TOLERANCES:	IPEX TECHNOLOGIES INC.			
	PROJECTION	UNITS: in (mm)	TITLE: LMF ROUND CB ASSEMBLY	
	DRAWN BY: H. M-MARTIN	DATE: 2011-07-26	SIZE: B	SCALE(S): 1/8
	VERIFIED BY:	DATE: 2011-07-26	DRAWING NUMBER: SGH74_FA002R03	REV: 3

Tempest LMF ICD Flow Curve

Flow: 8.1 L/s
Head: 2.38 m
CBMH1



IPEX

Tempest LMF ICD Flow Curve

Flow: 6.0 L/s
Head: 2.02 m
CBMH2



IPEX

Tempest LMF ICD Flow Curve

Flow: 9.8 L/s
Head: 2.37 m
CBMH3



IPEX

Tempest LMF ICD Flow Curve

Flow: 7.1 L/s
Head: 2.53 m
CBMH6



IPEX

Tempest LMF ICD Flow Curve

Flow: 6.4 L/s
Head: 2.46 m
MH7



IPEX

Tempest LMF ICD Flow Curve

Flow: 2.5 L/s
Head: 2 m
SAN MH8



IPEX

Square CB Installation Notes:

1. Materials and tooling verification:
   - Tooling: impact drill, 3/8'' concrete bit, torque wrench for 9/16''nut, hand hammer, level, and marker.
   - Material: (4) concrete anchor 3/8x3-1/2, (4) washers, (4) nuts
2. Use the mounting wall plate to locate and mark the hole (4) pattern on the catch basin wall. You should use a level to ensure that the plate is at the horizontal.
3. Use an impact drill with a 3/8'' concrete bit to make the four holes at a minimum of 1-1/2'' depth up to 2-1/2''. Clean the concrete dust from the holes.
4. Install the anchors (4) in the holes by using a hammer. Put the nuts on the top of the anchors to protect the threads when you will hit the anchors with the hammer. Remove the nuts on the ends of the anchors
5. Install the wall mounting plate on the anchors and screw the nut in place with a maximum torque of 40 N.m (30 lbf-ft). There should be no gap between the wall mounting plate and the catch basin wall.
6. From ground above using a reach bar, lower the device by hooking the end of the reach bar to the handle of the LMF device. Align the triangular plate portion into the mounting wall plate. Push down the device to be sure it has centered in to the wall mounting plate and has created a seal.







IPEX

Round CB Installation Notes: (Refer to square install notes above for steps 1 , 3, & 4)

2. Use spigot catch basin wall plate to locate and mark the hole (4) pattern on the catch basin wall. You should use a level to ensure that the plate is at the horizontal.
5. Install the CB spigot wall plate on the anchors and screw the 4 nuts in place with a maximum torque of 40 N.m (30 lb-ft). There should be no gap between the CB spigot wall plate and the catch basin wall.
6. Apply solvent cement on the hub of the universal mounting plate and the spigot of the spigot CB wall plate. Slide the hub over the spigot. Make sure the universal mounting plate is at the horizontal and its hub is completely inserted onto the spigot. Normally, the corners of the universal mounting plate hub adapter should touch the catch basin wall.
7. From ground above using a reach bar, lower the ICD device by hooking the end of the reach bar to the handle of the ICD device. Align the triangular plate portion into the mounting wall plate. Push down the device to be sure it has centered into the mounting plate and has created a seal.






CAUTION/WARNING/DISCLAIM:

- Verify that the inlet(s) pipe(s) is not protruding into the catch basin. If it is, cut it back so that the inlet pipe is flush with the catch basin wall.
- Any required cement in the installation must be approved for PVC.
- The solvent cement should not be used below 0°C (32°F) or in a high humidity environment. Please refer to the IPEX solvent cement guide to confirm required curing times or attend the IPEX **Online Solvent Cement Training Course**.
- Call your IPEX representative for more information or if you have any questions about our products.

IPEX

IPEX TEMPEST Inlet Control Devices Technical Specification

General

Inlet control devices (ICD's) are designed to provide flow control at a specified rate for a given water head level and also provide odour and floatable control where specified. All ICD's will be IPEX Tempest or approved equal.

All devices shall be removable from a universal mounting plate. An operator from street level using only a T-bar with a hook will be able to retrieve the device while leaving the universal mounting plate secured to the catch basin wall face. The removal of the TEMPEST devices listed above must not require any unbolting or special manipulation or any special tools.

High Flow (HF) Sump devices will consist of a removable threaded cap which can be accessible from street level with out entry into the catchbasin (CB). The removal of the threaded cap shall not require any special tools other than the operator's hand.

ICD's must have no moving parts.

Materials

ICD's are to be manufactured from Polyvinyl Chloride (PVC) or Polyurethane material, designed to be durable enough to withstand multiple freeze-thaw cycles and exposure to harsh elements.

The inner ring seal will be manufactured using a Buna or Nitrile material with hardness between Duro 50 and Duro 70.

The wall seal is to be comprised of a 3/8" thick Neoprene Closed Cell Sponge gasket which is attached to the back of the wall plate.

All hardware will be made from 304 stainless steel.

Dimensioning

The Low Medium Flow (LMF), High Flow (HF) and the High Flow (HF) Sump shall allow for a minimum outlet pipe diameter of 200mm with a 600mm deep Catch Basin sump.

Installation

Contractor shall be responsible for securing, supporting and connecting the ICD's to the existing influent pipe and catchbasin/manhole structure as specified and designed by the Engineer.

Block 21 - Mattino Way (112021-10)
PCSWMM Storage Curves (surface storage)

NOVATECH
Engineers, Planners & Landscape Architects

CB1-Storage		
Depth (m)	Area (m^2)	Volume (m^3)
0.00	0.36	0.00
1.77	0.36	0.64
1.82	28.00	1.35
1.87	92.00	4.35
1.92	190.00	11.40
1.97	290.00	23.40
2.02	377.00	40.07
2.021	0.00	40.26
2.77	0.00	40.26

CBMH1-Storage		
Depth (m)	Area (m^2)	Volume (m^3)
0.00	1.17	0.00
2.25	1.17	2.63
2.30	17.00	3.09
2.35	68.00	5.21
2.40	142.00	10.46
2.45	222.00	19.56
2.47	254.00	24.32
2.48	0.00	25.59
3.25	0.00	25.59

CBMH2-Storage		
Depth (m)	Area (m^2)	Volume (m^3)
0.00	1.17	0.00
1.76	1.17	2.06
1.81	5.60	2.23
1.86	22.60	2.93
1.91	50.80	4.77
1.96	90.30	8.30
2.01	141.20	14.08
2.03	164.60	17.14
2.04	0.00	17.96
3.04	0.00	17.96

CBMH3-Storage		
Depth (m)	Area (m^2)	Volume (m^3)
0.00	1.17	0.00
2.12	1.17	2.48
2.17	19.00	2.98
2.22	76.20	5.36
2.27	171.00	11.54
2.32	301.50	23.36
2.37	421.10	41.42
2.371	0.00	41.63
3.12	0.00	41.63

CBMH4-Storage		
Depth (m)	Area (m^2)	Volume (m^3)
0.00	1.17	0.00
2.11	1.17	2.47
2.16	7.50	2.69
2.21	30.00	3.62
2.26	63.00	5.95
2.31	110.00	10.27
2.36	170.00	17.27
2.41	260.00	28.02
2.42	0.00	29.32
3.11	0.00	29.32

CBMH5-Storage		
Depth (m)	Area (m^2)	Volume (m^3)
0.00	1.17	0.00
2.11	1.17	2.47
2.16	17.10	2.93
2.21	69.00	5.08
2.26	147.10	10.48
2.31	230.00	19.91
2.33	261.00	24.82
2.33	0.00	24.95
3.11	0.00	24.95

CBMH6-Storage		
Depth (m)	Area (m^2)	Volume (m^3)
0.00	1.17	0.00
2.25	1.17	2.63
2.30	12.16	2.97
2.35	48.59	4.48
2.40	108.89	8.42
2.45	193.72	15.99
2.50	297.64	28.27
2.55	417.45	46.15
2.56	0.00	48.24
3.25	0.00	48.24

CBMH7-Storage		
Depth (m)	Area (m^2)	Volume (m^3)
0.00	1.17	0.00
2.06	1.17	2.41
2.11	17.00	2.86
2.16	68.00	4.99
2.21	148.30	10.40
2.26	260.00	20.60
2.31	400.00	37.10
2.32	0.00	39.10
3.06	0.00	39.10

CBMH8-Storage		
Depth (m)	Area (m^2)	Volume (m^3)
0.00	1.17	0.00
1.86	1.17	2.18
1.91	8.20	2.41
1.96	33.00	3.44
2.01	75.00	6.14
2.06	132.00	11.32
2.11	205.00	19.74
2.16	290.00	32.12
2.18	321.00	38.23
2.181	0.00	38.39
2.86	0.00	38.39

Block 21 - Mattino Way (112021-10)
PCSWMM Model Results (Ponding)

NOVATECH
Engineers, Planners & Landscape Architects

CB / CBMH ID	Invert Elev. (m)	Rim Elev. (m)	Spill Elev. (m)	Ponding Depth (m)	HGL Elev. (m)[1]				Ponding Depth (m)				Spill Depth (m)			
					2-yr	5-yr	100-yr	100-yr (+20%)	2-yr	5-yr	100-yr	100-yr (+20%)	2-yr	5-yr	100-yr	100-yr (+20%)
CB1	91.18	92.95	93.20	0.25	92.43	93.05	93.20	93.21	0.00	0.10	0.25	0.26	0.00	0.00	0.00	0.01
CBMH1	90.70	92.95	93.17	0.22	91.92	92.72	93.08	93.09	0.00	0.00	0.13	0.14	0.00	0.00	0.00	0.00
CBMH2	91.19	92.95	93.22	0.27	92.04	92.79	93.20	93.22	0.00	0.00	0.25	0.27	0.00	0.00	0.00	0.00
CBMH3	90.48	92.60	92.85	0.25	92.34	92.72	92.85	92.88	0.00	0.12	0.25	0.28	0.00	0.00	0.00	0.03
CBMH4	90.84	92.95	93.25	0.30	92.43	93.05	93.20	93.21	0.00	0.10	0.25	0.26	0.00	0.00	0.00	0.00
CBMH5	90.74	92.85	93.07	0.22	91.92	92.72	93.08	93.09	0.00	0.00	0.23	0.24	0.00	0.00	0.01	0.02
CBMH6	90.70	92.95	93.25	0.30	92.67	93.10	93.23	93.26	0.00	0.15	0.28	0.31	0.00	0.00	0.00	0.01
CBMH7	90.89	92.95	93.20	0.25	92.43	93.05	93.20	93.21	0.00	0.10	0.25	0.26	0.00	0.00	0.00	0.01
CBMH8	90.74	92.60	92.92	0.32	92.34	92.72	92.85	92.88	0.00	0.12	0.25	0.28	0.00	0.00	0.00	0.00

[1] *3-hour Chicago Storm.*

Block 21 - Mattino Way (112021-10)
Summary of Hydraulic Grade Line (HGL) Elevations

MH ID	Obvert Elevation (m)	T/G Elevation (m)	HGL Elevation[1] (m)	Surcharge (m)	Clearance from T/G (m)	HGL in Stress Test[1] (m)
MH1	90.53	92.75	90.68	0.15	2.07	90.69
MH3	90.64	93.40	90.69	0.05	2.71	90.69
MH5	90.77	93.23	90.69	0.00	2.54	90.69
MH7 (D/S ICD)	91.04	93.21	90.79	0.00	2.42	90.79
MH9	90.89	93.23	90.70	0.00	2.53	90.70

[1] *3-hour Chicago Storm; fixed outfall elevation of 90.68 m (100yr HGL in MH122).*

Block 21 - Mattino Way (112021-10)
PCSWMM Model Schematic

NOVATECH
Engineers, Planners & Landscape Architects

Overall Model Schematic

Date: 2022-06-16
M:\2012\112021\Block 21\DATA\Calculations\Sewer Calcs\SWM\PCSWMM\Model Schematic-Output\PCSWMM Model Schematic.docx

Block 21 - Mattino Way (112021-10)
PCSWMM Model Schematic

NOVATECH
Engineers, Planners & Landscape Architects

Subcatchment ID's



Date: 2022-06-16
M:\2012\112021\Block 21\DATA\Calculations\Sewer Calcs\SWM\PCSWMM\Model Schematic-Output\PCSWMM Model Schematic.docx

Block 21 - Mattino Way (112021-10)
PCSWMM Model Schematic

NOVATECH
Engineers, Planners & Landscape Architects

Node ID's



Date: 2022-06-16
M:\2012\112021\Block 21\DATA\Calculations\Sewer Calcs\SWM\PCSWMM\Model Schematic-Output\PCSWMM Model Schematic.docx

Block 21 – Mattino Way (112021-10)
PCSWMM Model Output
100yr 3-hour Chicago Storm

NOVATECH
Engineers, Planners & Landscape Architects

```
EPA STORM WATER MANAGEMENT MODEL - VERSION 5.1 (Build 5.1.013)
  ----------------------------------------------------------------

  Longfields Block 21 PCSWMM Model (112021-10)


  *************
  Element Count
  *************
  Number of rain gages ...... 1
  Number of subcatchments ... 10
  Number of nodes ........... 36
  Number of links ........... 43
  Number of pollutants ...... 0
  Number of land uses ....... 0


  ****************
  Raingage Summary
  ****************
                                                   Data       Recording
  Name                 Data Source                 Type       Interval
  ----------------------------------------------------------------------
  Raingage1            C3hr-100yr                  INTENSITY   10 min.


  *********************
  Subcatchment Summary
  *********************
  Name                       Area     Width   %Imperv    %Slope Rain Gage            Outlet
  ------------------------------------------------------------------------------------------
---
  01                         0.08     32.00     84.30    1.0000 Raingage1            CBMH5
  02                         0.14     56.00     78.60    1.0000 Raingage1            CBMH7
  03                         0.09     45.00     77.10    1.0000 Raingage1            CBMH4
  04                         0.12     60.00     80.00    1.0000 Raingage1            CBMH1
  05                         0.08     40.00     77.10    1.0000 Raingage1            CBMH8
  06                         0.11     55.00     74.30    1.0000 Raingage1            CB1
  07                         0.15     75.00     72.90    1.0000 Raingage1            CBMH6
  08                         0.13     65.00     70.00    1.0000 Raingage1            CBMH3
  09                         0.05     33.33     20.00    1.0000 Raingage1            CBMH2
  10                         0.04     26.67     71.40    1.0000 Raingage1            RYCB1


  ************
  Node Summary
  ************
                                         Invert      Max.    Ponded    External
  Name                 Type                Elev.     Depth      Area    Inflow
  ----------------------------------------------------------------------------
  HP-CBMH1             JUNCTION           93.17      1.00       0.0
  HP-CBMH2             JUNCTION           93.22      1.00       0.0
  HP-CBMH4             JUNCTION           93.25      1.00       0.0
  HP-CBMH5             JUNCTION           93.07      1.00       0.0
  HP-CBMH6             JUNCTION           93.25      1.00       0.0
  HP-CBMH7             JUNCTION           93.20      1.00       0.0
  HP-CBMH8             JUNCTION           92.92      1.00       0.0
  HP-RYCB1             JUNCTION           93.24      1.00       0.0
  HP-CB1               OUTFALL            93.20      1.00       0.0
  HP-CBMH3             OUTFALL            92.85      1.00       0.0
  HP-LCB1              OUTFALL             0.00     94.34       0.0
  MH122                OUTFALL            89.92      0.53       0.0
  CB1                  STORAGE            91.18      2.77       0.0
  CBMH01-Dummy         STORAGE            90.71      2.39       0.0
  CBMH1                STORAGE            90.70      3.25       0.0
  CBMH2                STORAGE            91.19      2.76       0.0
  CBMH2-ICD            STORAGE            91.19      1.76       0.0
  CBMH3                STORAGE            90.48      3.12       0.0
  CBMH3-ICD            STORAGE            90.48      2.14       0.0
  CBMH4                STORAGE            90.84      3.11       0.0
  CBMH5                STORAGE            90.74      3.11       0.0
  CBMH5-Dummy          STORAGE            90.78      2.32       0.0
  CBMH6                STORAGE            90.70      3.25       0.0
  CBMH6-Dummy1         STORAGE            90.72      3.28       0.0
  CBMH6-Dummy2         STORAGE            90.72      2.58       0.0
  CBMH7                STORAGE            90.89      3.06       0.0
  CBMH8                STORAGE            90.74      2.86       0.0
  Dummy-CB1            STORAGE            90.76      3.24       0.0
  LCB1                 STORAGE            91.45      2.73       0.0
  MH1                  STORAGE            90.01      2.74       0.0
  MH3                  STORAGE            90.19      3.21       0.0
  MH5                  STORAGE            90.32      2.91       0.0
  MH7                  STORAGE            90.74      2.47       0.0
  MH7-ICD              STORAGE            90.74      2.47       0.0
  MH9                  STORAGE            90.52      2.72       0.0
  RYCB1                STORAGE            91.37      2.80       0.0


  ************
  Link Summary
  ************
  Name                 From Node          To Node            Type           Length    %Slope Roughness
  ---------------------------------------------------------------------------------------------------
  C01                  CBMH2              HP-CBMH2           CONDUIT           2.0  -11.0672    0.0150
  C02                  CB1                HP-CB1             CONDUIT           2.0  -12.5988    0.0150
  C04                  CBMH4              HP-CBMH4           CONDUIT           2.0  -15.1717    0.0150
  C05                  HP-CBMH4           CBMH7              CONDUIT           2.0   15.1717    0.0150
  C06                  CBMH6              HP-CBMH6           CONDUIT           2.0  -15.1717    0.0150
  C07                  HP-CBMH6           CBMH1              CONDUIT           2.0   15.1717    0.0150
  C08                  CBMH7              HP-CBMH7           CONDUIT           2.0  -12.5988    0.0150
  C09                  HP-CBMH7           CBMH5              CONDUIT           2.0   17.7743    0.0150
  C11                  HP-CBMH2           CBMH5              CONDUIT           2.0   18.8249    0.0150
  C12                  CBMH1              HP-CBMH1           CONDUIT           2.0  -11.0672    0.0150
  C13                  HP-CBMH1           CBMH5              CONDUIT           2.0   16.2088    0.0150
  C14                  CBMH5              HP-CBMH5           CONDUIT           2.0  -11.0672    0.0150
  C15                  HP-CBMH5           CBMH8              CONDUIT           2.0   24.1771    0.0150
  C16                  CBMH8              HP-CBMH8           CONDUIT           2.0  -16.2088    0.0150
  C17                  HP-CBMH8           CBMH3              CONDUIT           2.0   16.2088    0.0150
  C18                  CBMH3              HP-CBMH3           CONDUIT           2.0  -12.5988    0.0150
  C19                  HP-RYCB1           CBMH2              CONDUIT           2.0   14.6549    0.0150
  C20                  RYCB1              HP-RYCB1           CONDUIT           2.0   -3.5021    0.0150
  CB1-MH7              CB1                Dummy-CB1          CONDUIT           2.4    0.8334    0.0130
  CBMH1-Storage        CBMH01-Dummy       CBMH1              CONDUIT          17.0    0.1765    0.0130
  CBMH2-MH9            CBMH2-ICD          MH9                CONDUIT          14.0    1.3573    0.0130
  CBMH3-ICD-MH1        CBMH3-ICD          MH1                CONDUIT          17.3    0.5202    0.0130
  CBMH4-MH7            CBMH4              Dummy-CB1          CONDUIT          41.7    0.1918    0.0130
  CBMH5-CBMH1          CBMH5              CBMH1              CONDUIT          20.2    0.1980    0.0130
  CBMH5-Storage        CBMH5-Dummy        CBMH5              CONDUIT          20.0    0.2000    0.0130
  CBMH6-Storage1       CBMH6-Dummy1       CBMH6              CONDUIT          10.2    0.1961    0.0130
  CBMH6-Storage2       CBMH6-Dummy2       CBMH6              CONDUIT          10.2    0.1961    0.0130
  CBMH7-CBMH4          CBMH7              CBMH4              CONDUIT          25.6    0.1953    0.0130
  cbmh8-cbmh3          CBMH8              CBMH3              CONDUIT          29.4    0.2041    0.0130
  Dummy-CB1-MH7        Dummy-CB1          MH7                CONDUIT           8.7    0.2299    0.0130
  LCB01-CBMH7          LCB1               CBMH7              CONDUIT          20.8    1.0097    0.0130
  LCB1-HP-LCB1         LCB1               HP-LCB1            CONDUIT           1.0  -16.2088    0.0350
  MH1-MH122            MH1                MH122              CONDUIT          37.8    0.2381    0.0130
  MH3-MH1              MH3                MH1                CONDUIT          43.4    0.2535    0.0130
  MH5-MH3              MH5                MH3                CONDUIT          28.7    0.2439    0.0130
  MH7-MH3              MH7-ICD            MH3                CONDUIT          39.7    1.0076    0.0130
  MH9-MH5              MH9                MH5                CONDUIT          50.3    0.2386    0.0130
  RYCB1-CBMH2          RYCB1              CBMH2              CONDUIT          18.5    0.9730    0.0130
  O-CBMH1              CBMH1              MH9                ORIFICE
  O-CBMH2              CBMH2              CBMH2-ICD          ORIFICE
  O-CBMH3              CBMH3              CBMH3-ICD          ORIFICE
  O-CBMH6              CBMH6              MH5                ORIFICE
  O-MH7                MH7                MH7-ICD            ORIFICE


  *********************
  Cross Section Summary
  *********************
                                                 Full       Full       Hyd.       Max.   No. of       Full
  Conduit              Shape                    Depth       Area       Rad.      Width  Barrels       Flow
  ---------------------------------------------------------------------------------------------------------
  C01                  RECT_OPEN                 1.00       3.00       0.75       3.00       1   54926.48
  C02                  RECT_OPEN                 1.00       3.00       0.75       3.00       1   58604.17
  C04                  RECT_OPEN                 1.00       3.00       0.75       3.00       1   64310.23
  C05                  RECT_OPEN                 1.00       3.00       0.75       3.00       1   64310.23
  C06                  RECT_OPEN                 1.00       3.00       0.75       3.00       1   64310.23
  C07                  RECT_OPEN                 1.00       3.00       0.75       3.00       1   64310.23
  C08                  RECT_OPEN                 1.00       3.00       0.75       3.00       1   58604.17
  C09                  RECT_OPEN                 1.00       3.00       0.75       3.00       1   69608.09
  C11                  RECT_OPEN                 1.00       3.00       0.75       3.00       1   71635.87
  C12                  RECT_OPEN                 1.00       3.00       0.75       3.00       1   54926.48
  C13                  RECT_OPEN                 1.00       3.00       0.75       3.00       1   66472.09
  C14                  RECT_OPEN                 1.00       3.00       0.75       3.00       1   54926.48
  C15                  RECT_OPEN                 1.00       3.00       0.75       3.00       1   81183.07
  C16                  RECT_OPEN                 1.00       3.00       0.75       3.00       1   66472.09
  C17                  RECT_OPEN                 1.00       3.00       0.75       3.00       1   66472.09
  C18                  RECT_OPEN                 1.00       3.00       0.75       3.00       1   58604.17
  C19                  RECT_OPEN                 1.00       3.00       0.75       3.00       1   63205.48
  C20                  RECT_OPEN                 1.00       3.00       0.75       3.00       1   30898.03
  CB1-MH7              CIRCULAR                  0.20       0.03       0.05       0.20       1      29.94
  CBMH1-Storage        CIRCULAR                  0.60       0.28       0.15       0.60       1     257.95
```

CBMH2-MH9	CIRCULAR	0.30	0.07	0.07	0.30	1	112.66
CBMH3-ICD-MH1	CIRCULAR	0.30	0.07	0.07	0.30	1	69.75
CBMH4-MH7	CIRCULAR	0.60	0.28	0.15	0.60	1	268.96
CBMH5-CBMH1	CIRCULAR	0.60	0.28	0.15	0.60	1	273.25
CBMH5-Storage	CIRCULAR	0.60	0.28	0.15	0.60	1	274.61
CBMH6-Storage1	CIRCULAR	0.60	0.28	0.15	0.60	1	271.91
CBMH6-Storage2	CIRCULAR	0.60	0.28	0.15	0.60	1	271.91
CBMH7-CBMH4	CIRCULAR	0.60	0.28	0.15	0.60	1	271.37
cbmh8-cbmh3	CIRCULAR	0.60	0.28	0.15	0.60	1	277.40
Dummy-CB1-MH7	CIRCULAR	0.60	0.28	0.15	0.60	1	294.41
LCB01-CBMH7	CIRCULAR	0.25	0.05	0.06	0.25	1	59.76
LCB1-HP-LCB1	RECT_OPEN	1.00	3.00	0.75	3.00	1	28488.04
MH1-MH122	CIRCULAR	0.53	0.22	0.13	0.53	1	209.86
MH3-MH1	CIRCULAR	0.45	0.16	0.11	0.45	1	143.54
MH5-MH3	CIRCULAR	0.45	0.16	0.11	0.45	1	140.81
MH7-MH3	CIRCULAR	0.30	0.07	0.07	0.30	1	97.07
MH9-MH5	CIRCULAR	0.38	0.11	0.09	0.38	1	85.64
RYCB1-CBMH2	CIRCULAR	0.30	0.07	0.07	0.30	1	95.39

****
NOTE: The summary statistics displayed in this report are
based on results found at every computational time step,
not just on results from each reporting time step.
****

****
Analysis Options
****
Flow Units ..... LPS
Process Models:
  Rainfall/Runoff ..... YES
  RDII ..... NO
  Snowmelt ..... NO
  Groundwater ..... NO
  Flow Routing ..... YES
  Ponding Allowed ..... YES
  Water Quality ..... NO
Infiltration Method ..... HORTON
Flow Routing Method ..... DYNWAVE
Surcharge Method ..... EXTRAN
Starting Date 10/10/2019 00:00:00
Ending Date 10/17/2019 00:00:00
Antecedent Dry Days 0.0
Report Time Step 00:05:00
Wet Time Step 00:05:00
Dry Time Step 01:00:00
Routing Time Step ..... 2.00 sec
Variable Time Step ..... YES
Maximum Trials 8
Number of Threads 4
Head Tolerance ..... 0.001500 m

****
Control Actions Taken
****

Runoff Quantity Continuity	Volume hectare-m	Depth mm
Total Precipitation	0.071	71.667
Evaporation Loss	0.000	0.000
Infiltration Loss	0.012	11.916
Surface Runoff	0.059	59.673
Final Storage	0.001	0.776
Continuity Error (%)	-0.974	

Flow Routing Continuity	Volume hectare-m	Volume 10^6 ltr
Dry Weather Inflow	0.000	0.000
Wet Weather Inflow	0.059	0.591
Groundwater Inflow	0.000	0.000
RDII Inflow	0.000	0.000
External Inflow	0.002	0.019
External Outflow	0.061	0.609
Flooding Loss	0.000	0.000
Evaporation Loss	0.000	0.000
Exfiltration Loss	0.000	0.000
Initial Stored Volume	0.003	0.027
Final Stored Volume	0.003	0.027
Continuity Error (%)	0.036	

****
Time-Step Critical Elements
****
None

****
Highest Flow Instability Indexes
****
Link O-CBMH2 (2)

****
Routing Time Step Summary
****
Minimum Time Step : 0.26 sec
Average Time Step : 2.00 sec
Maximum Time Step : 2.00 sec
Percent in Steady State : 0.00
Average Iterations per Step : 2.00
Percent Not Converging : 0.00

****
Subcatchment Runoff Summary
****

Subcatchment	Total Precip mm	Total Runon mm	Total Evap mm	Total Infil mm	Imperv Runoff mm	Perv Runoff mm	Total Runoff 10^6 ltr	Peak Runoff LPS	Runoff Coeff
01	71.67	0.00	0.00	6.95	59.73	4.67	64.40	38.40	0.899
02	71.67	0.00	0.00	9.51	55.74	6.23	61.97	65.69	0.865
03	71.67	0.00	0.00	10.16	54.74	6.73	61.47	42.32	0.858
04	71.67	0.00	0.00	8.85	56.87	5.94	62.80	57.04	0.876
05	71.67	0.00	0.00	10.16	54.62	6.73	61.35	37.62	0.856
06	71.67	0.00	0.00	11.42	52.57	7.50	60.07	51.12	0.838
07	71.67	0.00	0.00	12.05	51.74	7.88	59.62	69.27	0.832
08	71.67	0.00	0.00	13.36	49.57	8.66	58.23	59.18	0.813
09	71.67	0.00	0.00	36.26	14.11	21.92	36.04	15.98	0.503
10	71.67	0.00	0.00	12.67	50.29	8.45	58.74	18.61	0.820

****
Node Depth Summary
****

Node	Type	Average Depth Meters	Maximum Depth Meters	Maximum HGL Meters	Time of Max Occurrence days hr:min	Reported Max Depth Meters
HP-CBMH1	JUNCTION	0.00	0.00	93.17	0 00:00	0.00
HP-CBMH2	JUNCTION	0.00	0.00	93.22	0 00:00	0.00
HP-CBMH4	JUNCTION	0.00	0.00	93.25	0 00:00	0.00
HP-CBMH5	JUNCTION	0.00	0.01	93.08	0 01:21	0.00
HP-CBMH6	JUNCTION	0.00	0.00	93.25	0 00:00	0.00
HP-CBMH7	JUNCTION	0.00	0.00	93.20	0 00:00	0.00
HP-CBMH8	JUNCTION	0.00	0.00	92.92	0 00:00	0.00
HP-RYCB1	JUNCTION	0.00	0.00	93.24	0 00:00	0.00

HP-CB1	OUTFALL	0.00	0.00	93.20	0	00:00	0.00
HP-CBMH3	OUTFALL	0.00	0.00	92.85	0	00:00	0.00
HP-LCB1	OUTFALL	0.00	0.00	0.00	0	00:00	0.00
MH122	OUTFALL	0.76	0.76	90.68	0	00:00	0.76
CB1	STORAGE	0.09	2.02	93.20	0	02:13	2.02
CBMH01-Dummy	STORAGE	0.07	2.37	93.08	0	01:21	2.36
CBMH1	STORAGE	0.05	2.38	93.08	0	01:21	2.37
CBMH2	STORAGE	0.02	2.01	93.20	0	01:28	2.01
CBMH2-ICD	STORAGE	0.00	0.05	91.24	0	01:28	0.05
CBMH3	STORAGE	0.24	2.37	92.85	0	01:40	2.37
CBMH3-ICD	STORAGE	0.20	0.21	90.69	0	01:09	0.21
CBMH4	STORAGE	0.11	2.36	93.20	0	02:12	2.36
CBMH5	STORAGE	0.05	2.34	93.08	0	01:21	2.33
CBMH5-Dummy	STORAGE	0.05	2.30	93.08	0	01:20	2.29
CBMH6	STORAGE	0.05	2.53	93.23	0	01:34	2.53
CBMH6-Dummy1	STORAGE	0.05	2.51	93.23	0	01:34	2.51
CBMH6-Dummy2	STORAGE	0.05	2.51	93.23	0	01:34	2.51
CBMH7	STORAGE	0.10	2.31	93.20	0	02:13	2.31
CBMH8	STORAGE	0.04	2.11	92.85	0	01:38	2.11
Dummy-CB1	STORAGE	0.11	2.44	93.20	0	02:12	2.44
LCB1	STORAGE	0.07	1.75	93.20	0	02:11	1.75
MH1	STORAGE	0.67	0.67	90.68	0	01:32	0.67
MH3	STORAGE	0.49	0.50	90.69	0	01:32	0.50
MH5	STORAGE	0.36	0.37	90.69	0	01:32	0.37
MH7	STORAGE	0.12	2.46	93.20	0	02:12	2.46
MH7-ICD	STORAGE	0.00	0.05	90.79	0	02:13	0.05
MH9	STORAGE	0.16	0.18	90.70	0	01:08	0.18
RYCB1	STORAGE	0.02	1.83	93.20	0	01:28	1.83

****
Node Inflow Summary
****

Node	Type	Maximum Lateral Inflow LPS	Maximum Total Inflow LPS	Time of Max Occurrence days hr:min	Lateral Inflow Volume 10^6 ltr	Total Inflow Volume 10^6 ltr	Flow Balance Error Percent
HP-CBMH1	JUNCTION	0.00	0.00	0 00:00	0	0	0.000 ltr
HP-CBMH2	JUNCTION	0.00	0.00	0 00:00	0	0	0.000 ltr
HP-CBMH4	JUNCTION	0.00	0.00	0 00:00	0	0	0.000 ltr
HP-CBMH5	JUNCTION	0.00	18.12	0 01:21	0	0.00725	-0.001
HP-CBMH6	JUNCTION	0.00	0.00	0 00:00	0	0	0.000 ltr
HP-CBMH7	JUNCTION	0.00	0.00	0 00:00	0	0	0.000 ltr
HP-CBMH8	JUNCTION	0.00	0.00	0 00:00	0	0	0.000 ltr
HP-RYCB1	JUNCTION	0.00	0.00	0 00:00	0	0	0.000 ltr
HP-CB1	OUTFALL	0.00	0.00	0 00:00	0	0	0.000 ltr
HP-CBMH3	OUTFALL	0.00	0.00	0 00:00	0	0	0.000 ltr
HP-LCB1	OUTFALL	0.00	0.00	0 00:00	0	0	0.000 ltr
MH122	OUTFALL	0.00	37.41	0 01:35	0	0.628	0.000
CB1	STORAGE	51.12	61.83	0 01:10	0.0661	0.0714	0.017
CBMH01-Dummy	STORAGE	0.00	12.46	0 01:07	0	0.00673	0.366
CBMH1	STORAGE	57.04	58.78	0 01:09	0.0754	0.142	0.007
CBMH2	STORAGE	15.98	34.09	0 01:10	0.018	0.0417	-0.059
CBMH2-ICD	STORAGE	0.00	6.02	0 01:28	0	0.0417	0.108
CBMH3	STORAGE	59.18	70.65	0 01:10	0.0757	0.133	0.006
CBMH3-ICD	STORAGE	0.00	9.79	0 01:40	0	0.135	0.002
CBMH4	STORAGE	42.32	68.02	0 01:05	0.0553	0.142	-0.016
CBMH5	STORAGE	38.40	92.08	0 01:09	0.0515	0.075	0.025
CBMH5-Dummy	STORAGE	0.00	14.88	0 01:05	0	0.00817	0.059
CBMH6	STORAGE	69.27	69.41	0 01:10	0.0894	0.0975	0.035
CBMH6-Dummy1	STORAGE	0.00	11.43	0 01:05	0	0.00404	0.008
CBMH6-Dummy2	STORAGE	0.00	11.43	0 01:05	0	0.00404	0.008
CBMH7	STORAGE	65.69	67.63	0 01:10	0.0868	0.0911	-0.012
CBMH8	STORAGE	37.62	37.62	0 01:10	0.0491	0.057	-0.025
Dummy-CB1	STORAGE	0.00	59.38	0 01:06	0	0.214	0.019
LCB1	STORAGE	0.00	11.25	0 01:02	0	0.00431	0.048
MH1	STORAGE	0.00	37.41	0 01:35	0	0.629	0.000
MH3	STORAGE	0.00	27.62	0 01:33	0	0.489	-0.000
MH5	STORAGE	0.00	21.26	0 01:30	0	0.27	-0.001
MH7	STORAGE	0.00	18.55	0 01:06	0	0.208	0.002
MH7-ICD	STORAGE	0.00	6.37	0 02:12	0	0.208	0.000
MH9	STORAGE	0.00	14.15	0 01:24	0	0.168	-0.001
RYCB1	STORAGE	18.61	18.61	0 01:10	0.0235	0.0235	-0.033

****
Node Surcharge Summary
****

No nodes were surcharged.

****
Node Flooding Summary
****

No nodes were flooded.

****
Storage Volume Summary
****

Storage Unit	Average Volume 1000 m3	Avg Pcnt Full	Evap Pcnt Loss	Exfil Pcnt Loss	Maximum Volume 1000 m3	Max Pcnt Full	Time of Max Occurrence days hr:min	Maximum Outflow LPS
CB1	0.001	2	0	0	0.039	97	0 02:13	40.49
CBMH01-Dummy	0.000	3	0	0	0.000	99	0 01:21	2.62
CBMH1	0.000	0	0	0	0.008	30	0 01:21	61.22
CBMH2	0.000	0	0	0	0.014	77	0 01:28	6.02
CBMH2-ICD	0.000	0	0	0	0.000	3	0 01:28	6.02
CBMH3	0.001	2	0	0	0.041	99	0 01:40	14.07
CBMH3-ICD	0.000	9	0	0	0.000	10	0 01:09	9.79
CBMH4	0.000	1	0	0	0.017	57	0 02:12	27.62
CBMH5	0.000	1	0	0	0.025	100	0 01:20	18.29
CBMH5-Dummy	0.000	2	0	0	0.000	99	0 01:20	5.60
CBMH6	0.000	1	0	0	0.038	79	0 01:34	29.52
CBMH6-Dummy1	0.000	1	0	0	0.000	77	0 01:34	1.88
CBMH6-Dummy2	0.000	2	0	0	0.000	97	0 01:34	1.88
CBMH7	0.001	2	0	0	0.036	92	0 02:13	35.31
CBMH8	0.000	1	0	0	0.020	52	0 01:38	20.91
Dummy-CB1	0.000	4	0	0	0.002	75	0 02:12	18.55
LCB1	0.000	3	0	0	0.001	64	0 02:11	2.41
MH1	0.001	24	0	0	0.001	25	0 01:32	37.41
MH3	0.000	15	0	0	0.001	16	0 01:32	27.62
MH5	0.000	12	0	0	0.000	13	0 01:32	21.26
MH7	0.000	5	0	0	0.003	99	0 02:12	6.37
MH7-ICD	0.000	0	0	0	0.000	2	0 02:13	6.37
MH9	0.000	6	0	0	0.000	7	0 01:08	14.15
RYCB1	0.000	1	0	0	0.001	94	0 01:28	18.27

****
Outfall Loading Summary
****

Outfall Node	Flow Freq Pcnt	Avg Flow LPS	Max Flow LPS	Total Volume 10^6 ltr
HP-CB1	0.00	0.00	0.00	0.000
HP-CBMH3	0.00	0.00	0.00	0.000
HP-LCB1	0.00	0.00	0.00	0.000
MH122	83.62	1.28	37.41	0.628
System	20.90	1.28	37.41	0.628

****
Link Flow Summary
****

Link	Type	Maximum |Flow| LPS	Time of Max Occurrence days hr:min	Maximum |Veloc| m/sec	Max/ Full Flow	Max/ Full Depth
C01	CONDUIT	0.00	0 00:00	0.00	0.00	0.10
C02	CONDUIT	0.00	0 00:00	0.00	0.00	0.12
C04	CONDUIT	0.00	0 00:00	0.00	0.00	0.12
C05	CONDUIT	0.00	0 00:00	0.00	0.00	0.12
C06	CONDUIT	0.00	0 00:00	0.00	0.00	0.14
C07	CONDUIT	0.00	0 00:00	0.00	0.00	0.06
C08	CONDUIT	0.00	0 00:00	0.00	0.00	0.12
C09	CONDUIT	0.00	0 00:00	0.00	0.00	0.11
C11	CONDUIT	0.00	0 00:00	0.00	0.00	0.11
C12	CONDUIT	0.00	0 00:00	0.00	0.00	0.06
C13	CONDUIT	0.00	0 00:00	0.00	0.00	0.11

C14	CONDUIT	18.12	0	01:21	0.05	0.00	0.12
C15	CONDUIT	18.15	0	01:21	0.05	0.00	0.13
C16	CONDUIT	0.00	0	00:00	0.00	0.00	0.13
C17	CONDUIT	0.00	0	00:00	0.00	0.00	0.12
C18	CONDUIT	0.00	0	00:00	0.00	0.00	0.12
C19	CONDUIT	0.00	0	00:00	0.00	0.00	0.12
C20	CONDUIT	0.00	0	00:00	0.00	0.00	0.01
CB1-MH7	CONDUIT	40.49	0	01:06	1.29	1.35	1.00
CBMH1-Storage	CONDUIT	12.46	0	01:07	0.07	0.05	1.00
CBMH2-MH9	CONDUIT	6.02	0	01:28	0.83	0.05	0.16
CBMH3-ICD-MH1	CONDUIT	9.79	0	01:40	0.16	0.14	0.83
CBMH4-MH7	CONDUIT	27.62	0	01:07	0.19	0.10	1.00
CBMH5-CBMH1	CONDUIT	51.44	0	01:08	0.18	0.19	1.00
CBMH5-Storage	CONDUIT	14.88	0	01:05	0.05	0.05	1.00
CBMH6-Storage1	CONDUIT	11.43	0	01:05	0.04	0.04	1.00
CBMH6-Storage2	CONDUIT	11.43	0	01:05	0.04	0.04	1.00
CBMH7-CBMH4	CONDUIT	29.61	0	01:05	0.26	0.11	1.00
cbmh8-cbmh3	CONDUIT	20.91	0	01:22	0.18	0.08	1.00
Dummy-CB1-MH7	CONDUIT	18.55	0	01:06	0.19	0.06	1.00
LCB01-CBMH7	CONDUIT	11.25	0	01:02	0.29	0.19	1.00
LCB1-HP-LCB1	CONDUIT	0.00	0	00:00	0.00	0.00	0.01
MH1-MH122	CONDUIT	37.41	0	01:35	0.17	0.18	1.00
MH3-MH1	CONDUIT	27.62	0	01:33	0.17	0.19	1.00
MH5-MH3	CONDUIT	21.26	0	01:30	0.14	0.15	0.90
MH7-MH3	CONDUIT	6.37	0	02:13	0.15	0.07	0.59
MH9-MH5	CONDUIT	14.15	0	01:23	0.19	0.17	0.63
RYCB1-CBMH2	CONDUIT	18.27	0	01:10	0.26	0.19	1.00
O-CBMH1	ORIFICE	8.14	0	01:21			1.00
O-CBMH2	ORIFICE	6.02	0	01:28			1.00
O-CBMH3	ORIFICE	9.79	0	01:40			1.00
O-CBMH6	ORIFICE	7.11	0	01:34			1.00
O-MH7	ORIFICE	6.37	0	02:12			1.00

****
Flow Classification Summary
****

Conduit	Adjusted /Actual Length	Dry	Up Dry	Down Dry	Sub Crit	Sup Crit	Up Crit	Down Crit	Norm Ltd	Inlet Ctrl
		---------- Fraction of Time in Flow Class ----------								
C01	1.00	0.99	0.01	0.00	0.00	0.00	0.00	0.00	0.00	0.00
C02	1.00	0.96	0.04	0.00	0.00	0.00	0.00	0.00	0.00	0.00
C04	1.00	0.96	0.04	0.00	0.00	0.00	0.00	0.00	0.00	0.00
C05	1.00	0.96	0.04	0.00	0.00	0.00	0.00	0.00	0.00	0.00
C06	1.00	0.98	0.02	0.00	0.00	0.00	0.00	0.00	0.00	0.00
C07	1.00	0.99	0.01	0.00	0.00	0.00	0.00	0.00	0.00	0.00
C08	1.00	0.96	0.04	0.00	0.00	0.00	0.00	0.00	0.00	0.00
C09	1.00	0.98	0.02	0.00	0.00	0.00	0.00	0.00	0.00	0.00
C11	1.00	0.98	0.02	0.00	0.00	0.00	0.00	0.00	0.00	0.00
C12	1.00	0.99	0.01	0.00	0.00	0.00	0.00	0.00	0.00	0.00
C13	1.00	0.98	0.02	0.00	0.00	0.00	0.00	0.00	0.00	0.00
C14	1.00	0.98	0.01	0.00	0.00	0.00	0.00	0.00	0.99	0.00
C15	1.00	0.98	0.01	0.00	0.00	0.00	0.00	0.00	0.99	0.00
C16	1.00	0.98	0.02	0.00	0.00	0.00	0.00	0.00	0.00	0.00
C17	1.00	0.98	0.02	0.00	0.00	0.00	0.00	0.00	0.00	0.00
C18	1.00	0.98	0.02	0.00	0.00	0.00	0.00	0.00	0.00	0.00
C19	1.00	0.99	0.01	0.00	0.00	0.00	0.00	0.00	0.00	0.00
C20	1.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
CB1-MH7	1.00	0.00	0.00	0.00	0.06	0.00	0.00	0.94	0.00	0.00
CBMH1-Storage	1.00	0.76	0.20	0.00	0.04	0.00	0.00	0.00	0.96	0.00
CBMH2-MH9	1.00	0.00	0.00	0.00	0.00	0.00	0.00	1.00	0.00	0.00
CBMH3-ICD-MH1	1.00	0.00	0.00	0.00	1.00	0.00	0.00	0.00	0.00	0.00
CBMH4-MH7	1.00	0.00	0.00	0.00	1.00	0.00	0.00	0.00	0.92	0.00
CBMH5-CBMH1	1.00	0.00	0.00	0.00	1.00	0.00	0.00	0.00	0.03	0.00
CBMH5-Storage	1.00	0.00	0.96	0.00	0.04	0.00	0.00	0.00	0.96	0.00
CBMH6-Storage1	1.00	0.78	0.18	0.00	0.03	0.00	0.00	0.00	0.97	0.00
CBMH6-Storage2	1.00	0.78	0.18	0.00	0.03	0.00	0.00	0.00	0.97	0.00
CBMH7-CBMH4	1.00	0.00	0.00	0.00	1.00	0.00	0.00	0.00	0.02	0.00
cbmh8-cbmh3	1.00	0.00	0.00	0.00	0.25	0.00	0.00	0.75	0.01	0.00
Dummy-CB1-MH7	1.00	0.00	0.00	0.00	0.99	0.00	0.00	0.00	0.02	0.00
LCB01-CBMH7	1.00	0.01	0.00	0.00	0.06	0.00	0.00	0.94	0.94	0.00
LCB1-HP-LCB1	1.00	0.99	0.01	0.00	0.00	0.00	0.00	0.00	0.00	0.00
MH1-MH122	1.00	0.00	0.00	0.00	1.00	0.00	0.00	0.00	0.00	0.00
MH3-MH1	1.00	0.00	0.00	0.00	1.00	0.00	0.00	0.00	0.00	0.00
MH5-MH3	1.00	0.00	0.00	0.00	1.00	0.00	0.00	0.00	0.00	0.00
MH7-MH3	1.00	0.00	0.83	0.00	0.17	0.00	0.00	0.00	1.00	0.00
MH9-MH5	1.00	0.00	0.00	0.00	1.00	0.00	0.00	0.00	0.00	0.00
RYCB1-CBMH2	1.00	0.00	0.00	0.00	1.00	0.00	0.00	0.00	0.99	0.00

****
Conduit Surcharge Summary
****

Conduit	Hours Full: Both Ends	Hours Full: Upstream	Hours Full: Dnstream	Hours Above Full Normal Flow	Hours Capacity Limited
CB1-MH7	8.65	8.65	8.71	0.06	0.11
CBMH1-Storage	3.67	3.67	3.71	0.01	0.01
CBMH4-MH7	8.49	8.49	8.71	0.01	0.01
CBMH5-CBMH1	3.65	3.65	3.71	0.01	0.01
CBMH5-Storage	3.61	3.61	3.65	0.01	0.01
CBMH6-Storage1	3.30	3.30	3.31	0.01	0.01
CBMH6-Storage2	3.30	3.30	3.31	0.01	0.01
CBMH7-CBMH4	8.37	8.37	8.49	0.01	0.01
cbmh8-cbmh3	3.45	3.45	3.49	0.01	0.01
Dummy-CB1-MH7	8.71	8.71	8.78	0.01	0.01
LCB01-CBMH7	7.92	7.92	8.37	0.01	0.01
MH1-MH122	168.00	168.00	168.00	0.01	0.01
MH3-MH1	168.00	168.00	168.00	0.01	0.01
MH7-MH3	0.01	0.01	167.75	0.01	0.01
RYCB1-CBMH2	1.80	1.80	1.99	0.01	0.01

Analysis begun on: Wed Jun 15 15:32:05 2022
Analysis ended on: Wed Jun 15 15:32:10 2022
Total elapsed time: 00:00:05

APPENDIX C: Drawings

112021-10-GP
112021-10-GR
112021-10-STM
112021-10-ESC

WATERMAIN TABLE				
Station	F/G ELEVATION	TOP OF WATERMAIN	COVER	DESCRIPTION
1+000.00	93.13	90.73	2.40	CONNECT TO EXISTING
1+008.93	93.17	90.77	2.40	22.5° H. BEND
1+020.15	93.12	90.72	2.40	HYD3 CONNECTION
1+022.01	93.12	90.72	2.40	22.5° H. BEND
1+025.00	93.11	90.71	2.40	-
1+049.26	93.29	90.89	2.40	VB1
1+050.00	93.30	90.90	2.40	-
1+051.26	93.32	90.92	2.40	200 x 200 TEE
1+054.31	93.37	90.97	2.40	11.25° H. BEND
1+075.00	93.21	90.81	2.40	-
1+085.04	93.25	90.85	2.40	22.5° H. BEND
1+090.45	93.27	90.87	2.40	HYD2 CONNECTION
1+095.26	93.35	90.95	2.40	200 TO 150 REDUCER
1+100.00	93.22	90.82	2.40	-
1+100.07	93.22	90.82	2.40	22.5° H. BEND
1+102.02	93.23	90.83	2.40	SP5
1+116.61	93.51	91.11	2.40	45° H. BEND
1+117.70	93.57	91.17	2.40	CAP
2+000.00	93.32	90.92	2.40	200 x 200 TEE
2+002.00	93.31	90.91	2.40	VB2
2+007.85	93.28	90.88	2.40	45° V. BEND
2+008.59	93.28	90.30	1.66	45° V. BEND
2+009.44	93.27	90.30	1.65	45° V. BEND
2+010.18	93.27	90.87	2.40	45° V. BEND
2+025.00	93.59	91.19	2.40	-
2+025.27	93.59	91.19	2.40	SP1 CONNECTION
2+027.86	93.56	91.16	2.40	SP4 CONNECTION
2+042.53	93.32	90.92	2.40	45° H. BEND
2+048.26	93.41	91.01	2.40	45° H. BEND
2+050.00	93.26	90.86	2.40	-
2+050.31	93.25	90.85	2.40	45° V. BEND
2+050.74	93.25	91.07	2.18	45° V. BEND
2+051.71	93.25	91.07	2.18	45° V. BEND
2+052.14	93.25	90.85	2.40	45° V. BEND
2+072.84	93.34	90.94	2.40	SP2 CONNECTION
2+073.84	93.32	90.92	2.40	SP3 CONNECTION
2+075.00	93.30	90.90	2.40	-
2+096.23	92.93	90.53	2.40	45° H. BEND
2+099.23	92.91	90.51	2.40	45° H. BEND
2+100.00	92.89	90.49	2.40	-
2+101.23	92.88	90.48	2.40	HYD1 CONNECTION
2+125.00	92.77	90.37	2.40	-
2+150.00	92.82	90.42	2.40	-
2+152.68	92.80	90.40	2.40	CONNECT TO EXISTING

ICD TABLE					
STRUCTURE ID	T/G ELEVATION	INVERT	I.C.D.	HEAD (m)	RELEASE RATE (L/s)
7	93.23	NE=90.74 SE=90.74	Tempest LMF Vortex 69	2.46	6.4
CBMH1	92.95	NW=90.70 E=90.70 SW=90.70	Tempest LMF Vortex 78	2.38	8.1
CBMH2	92.95	N=91.19 SW=91.19	Tempest LMF Vortex 70	2.02	6.0
CBMH3	92.60	SW=90.48 NE=90.68	Tempest LMF Vortex 86	2.37	9.8
CBMH6	92.95	SE=90.70 SW=90.70 NE=90.70	Tempest LMF Vortex 72	2.53	7.1

SEWER CROSSING TABLE		
LOCATION	ELEVATIONS	CLEARANCE
C1	STM INV=91.37 WM OBV=90.87	0.50m
C2	STM INV=90.80 WM OBV=90.30	0.50m
C3	WM INV=91.30 STM OBV=91.00	0.30m
C4	WM INV=90.65 SAN OBV=89.97	0.68m
C5	STM INV=90.40 SAN OBV=89.45	0.95m
C6	STM INV=90.52 SAN OBV=90.32	0.20m
C7	STM INV=90.71 WM OBV=90.21	0.50m

CATCHBASIN/LCB TABLE			
CB ID	T/G ELEVATION	INVERT	I.C.D.
CB1	92.95	91.18	-
LCB1	93.18	91.45	-
LCB2	93.41	92.01	-
RYCB1	93.17	91.37 91.77	-

SANITARY MANHOLE TABLE				
MANHOLE ID	SIZE(mm)	T/G ELEV (m)	INVERT (m)	PIPE DIAMETER (mm)
2	1200Ø	92.76	NW=89.24 SW=89.18	NW=200 SW=200
4	1200Ø	93.23	NE=89.58 SE=89.52	NE=200 SE=200
6	1200Ø	93.19	N=90.08 SW=90.05	N=200 SW=200
8	1200Ø	92.81	NE=89.02 SW=89.01	NE=200 SW=200
119	1200Ø	92.87	E=88.90 NW=88.87 NE=88.96	E=200 NW=200 NE=200

STORM MANHOLE TABLE					
MANHOLE ID	SIZE(mm)	T/G ELEV (m)	INVERT (m)	PIPE DIAMETER (mm)	I.C.D.
1	1500Ø	92.75	NW=90.08 SW=90.01 NE=90.39	NW=450 SW=525 NE=300	-
3	1200Ø	93.42	NE=90.25 SE=90.19 NW=90.34	NE=450 SE=450 NW=300	-
5	1200Ø	93.24	NE=90.40 SW=90.32	NE=375 SW=450	-
7	1200Ø	93.23	NE=90.74 SE=90.74	NE=600 SE=300	Tempest LMF Vortex 69
9	1200Ø	93.23	SW=90.52 N=90.75 NE=91.00	SW=375 N=150 NE=300	-
122	1800Ø	92.85	E=89.77 NE=89.92 NW=89.92	E=675 NE=525 NW=525	Concentric Cylindrical Structure SI
CBMH1	1500Ø	92.95	NW=90.70 E=90.70 SW=90.70	NW=200 E=600 SW=600	Tempest LMF Vortex 78
CBMH2	1200Ø	92.95	N=91.19 SW=91.19	N=300 SW=300	Tempest LMF Vortex 70
CBMH3	1200Ø	92.60	SW=90.48 NE=90.68	SW=300 NE=600	Tempest LMF Vortex 86
CBMH4	1500Ø	92.95	SW=90.84 NE=90.84	SW=600 NE=600	-
CBMH5	1500Ø	92.85	W=90.74 SE=90.74	W=600 SE=600	-
CBMH6	1200Ø	92.95	SE=90.70 SW=90.70 NE=90.70	SE=200 SW=600 NE=600	Tempest LMF Vortex 72
CBMH7	1200Ø	92.95	SW=90.89 NW=91.24	SW=600 NW=250	-
CBMH8	1200Ø	92.60	SW=90.74	SW=600	-



LEGEND

- SANITARY MANHOLE, SEWER & DIRECTION OF FLOW
- STORM MANHOLE, SEWER & DIRECTION OF FLOW
- 300mmØ — WATERMAIN AND DIAMETER
- VALVE & VALVE BOX
- GATE VALVE CHAMBER PER W3
- 95 — ROAD CATCHBASIN
- SITE LEGAL BOUNDARY
- EXISTING PROPERTY & ROW LINES
- HYD T/F=100.00 — HYDRANT C/W VALVE & LEAD TF= TOP OF FLANGE ELEVATION
- THRUST BLOCK AND BEND
- W — WATER METER
- REMOTE WATER METER
- LCB30 — LANDSCAPE TYPE CATCHBASIN
- RYCB1 — REAR YARD CATCH BASIN
- CBMH1 — CATCH BASIN MANHOLE
- STORAGE CHAMBER SUBDRAIN
- x — x — TEMPORARY CONSTRUCTION FENCING

GENERAL NOTES:

1. DIMENSIONS AND LAYOUT INFORMATION SHALL BE CONFIRMED PRIOR TO COMMENCEMENT OF CONSTRUCTION.
2. THE ORIGINAL TOPOGRAPHY AND GROUND ELEVATIONS, SERVICING AND SURVEY INFORMATION SHOWN ON THIS PLAN ARE SUPPLIED FOR INFORMATION PURPOSES ONLY. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO VERIFY THE ACCURACY OF ALL INFORMATION OBTAINED FROM THIS PLAN.
3. CO-ORDINATE AND SCHEDULE ALL WORK WITH OTHER TRADES AND CONTRACTORS.
4. BEFORE COMMENCING CONSTRUCTION, PROVIDE PROOF OF COMPREHENSIVE ALL RISK AND OPERATIONAL LIABILITY INSURANCE INCLUDING BLASTING. INSURANCE POLICY TO NAME THE OWNER, ENGINEER AND THE CITY AS CO-INSURED.
5. CONNECT TO EXISTING SYSTEMS AS DETAILED, INCLUDING ALL RESTORATION WORK NECESSARY TO REINSTATE SURFACES TO EXISTING CONDITIONS OR BETTER.
6. DETERMINE THE EXACT LOCATION, SIZE, MATERIAL AND ELEVATION OF ALL EXISTING UTILITIES PRIOR TO COMMENCING CONSTRUCTION. PROTECT AND ASSUME RESPONSIBILITY FOR ALL EXISTING UTILITIES WHETHER OR NOT SHOWN ON THESE DRAWINGS.
7. OBTAIN AND PAY FOR ALL NECESSARY PERMITS AND APPROVALS BEFORE COMMENCING CONSTRUCTION.
8. RESTORE ALL TRENCHES AND SURFACE FEATURES TO EXISTING CONDITIONS OR BETTER AND TO THE SATISFACTION OF MUNICIPAL AUTHORITIES.
9. REMOVE FROM SITE ALL EXCESS EXCAVATED MATERIAL UNLESS OTHERWISE INSTRUCTED BY THE ENGINEER. EXCAVATE AND REMOVE FROM SITE ALL ORGANIC MATERIAL AND DEBRIS UNLESS OTHERWISE INSTRUCTED BY THE ENGINEER.
10. ALL ELEVATIONS ARE GEODETIC AND UTILIZE METRIC UNITS.
11. REFER TO GEOTECHNICAL INVESTIGATION PROJECT: PG2306-1 (JANUARY 31, 2013), PREPARED BY PATERSON GROUP FOR SUBSURFACE CONDITIONS AND CONSTRUCTION RECOMMENDATIONS.
12. PERFORATED PIPE SUB-DRAINS TO BE PROVIDED AT SUBGRADE LEVEL EXTENDING FROM THE ROADSIDE CATCHBASIN FOR A DISTANCE OF 3.0m, PARALLEL TO THE CURB IN TWO DIRECTIONS.

SEWER NOTES:

1. SPECIFICATIONS:

ITEM	SPEC. No.	REFERENCE
CATCHBASIN (600x600mm)	705.010	OPSD
STORM / SANITARY MANHOLE (1200Ø)	701.010	OPSD
ROADSIDE CB, FRAME & COVER	S2 & S19	CITY of OTTAWA
STORM / SANITARY MH FRAME & COVER	S24.1 / S24 & S25	CITY of OTTAWA
STORM SEWER	PVC DR 35 OR CONC.	(CLASS SPECIFIED ON PROFILE DRAWINGS)
SANITARY SEWER	PVC DR 35	
CATCHBASIN LEAD	PVC DR 35	

2. INSULATE ALL PIPES (SAN/STM) THAT HAVE LESS THAN 1.5m COVER WITH 50mmX1200mm HI-40 INSULATION. PROVIDE 150mm CLEARANCE BETWEEN PIPE AND INSULATION.
3. SERVICES ARE TO BE CONSTRUCTED TO 1.0m FROM BUILDING FACE AT MINIMUM SLOPE OF 1.0% (2.0% IS PREFERRED).
4. PIPE BEDDING, COVER AND BACKFILL ARE TO BE COMPACTED TO AT LEAST 95% OF THE STANDARD PROCTOR MAXIMUM DRY DENSITY. THE USE OF CLEAR CRUSHED STONE AS A BEDDING LAYER SHALL NOT BE PERMITTED.
5. SEWER SERVICE CONNECTIONS PER CITY OF OTTAWA DETAILS S11 AND S11.1.
6. BACKWATER VALVES ARE TO BE INSTALLED ON SERVICES AS PER CITY STANDARDS (S14, S14.1, S14.2).
7. THE SITE SERVICING CONTRACTOR SHALL PERFORM FIELD TESTS FOR QUALITY CONTROL OF ALL SANITARY SEWERS. LEAKAGE TESTING SHALL BE COMPLETED IN ACCORDANCE WITH OPSS 410.07.16 AND 407.07.24. DYE TESTING IS TO BE COMPLETED ON ALL SANITARY SERVICES TO CONFIRM PROPER CONNECTION TO THE SANITARY SEWER MAIN. THE FIELD TESTS SHALL BE PERFORMED IN THE PRESENCE OF THE ENGINEER.
8. STORM MANHOLES AND CBMHS SHALL HAVE 300mm SUMPS UNLESS OTHERWISE INDICATED.
9. CONTRACTOR TO TELEVISE (CCTV) ALL PROPOSED SEWERS, 200mmØ OR GREATER PRIOR TO CONNECTING THE PROPOSED SEWERS. UPON COMPLETION OF CONTRACT, THE CONTRACTOR IS RESPONSIBLE TO FLUSH AND CLEAN ALL SEWERS & APPURTENANCES.
10. ALL CATCH BASIN LEADS SHALL BE 200mmØ @ 1.0% (MIN.) UNLESS SHOWN OTHERWISE.
11. ALL CATCH BASINS SHALL HAVE 600mm SUMPS UNLESS INDICATED OTHERWISE.

WATERMAIN NOTES:

1. GENERAL:

ITEM	DETAIL No.	REFERENCE
WATERMAIN TRENCHING	W17	CITY OF OTTAWA
THERMAL INSULATION IN SHALLOW TRENCHES	W22 / W23	CITY OF OTTAWA
WATERMAIN CROSSING BELOW SEWER / OVER SEWER	W25 / W25.2	CITY OF OTTAWA
THRUST BLOCK	W25.3	CITY OF OTTAWA

2. THE WATERMAIN SHALL BE PVC DR 18 IN ACCORDANCE WITH MATERIAL SPECIFICATION MW-18.1, UNLESS OTHERWISE INDICATED, COMPLETE WITH TRACING WIRE AND CATHODIC PROTECTION.
3. SUPPLY AND CONSTRUCT ALL WATERMAINS AND APPURTENANCES IN ACCORDANCE WITH THE CITY OF OTTAWA STANDARDS AND SPECIFICATIONS. EXCAVATION, INSTALLATION, BACKFILL AND RESTORATION OF ALL WATERMAINS BY THE CONTRACTOR. CONNECTIONS AND SHUT-OFFS AT THE MAIN AND CHLORINATION OF THE WATER SYSTEM SHALL BE PERFORMED BY CITY OFFICIALS.
4. WATERMAIN SHALL BE MINIMUM 2.4m DEPTH BELOW GRADE UNLESS OTHERWISE INDICATED.
5. PROVIDE MINIMUM 0.30m CLEARANCE BETWEEN OUTSIDE OF PIPES AT ALL CROSSINGS.
6. HORIZONTAL CLEARANCE BETWEEN WATERMAIN AND SEWERS IS 2.5m (MIN.).
7. CONNECTION TO EXISTING WATERMAIN BY CITY FORCES, CIVIL CONTRACTOR TO EXCAVATE TRENCH, PLACE BEDDING, BACKFILL AND REINSTATE SURFACE TO EXISTING CONDITIONS OR BETTER.
8. FIRE HYDRANT INSTALLATION PER CITY DETAIL W19.
9. THERMAL INSULATION FOR WATERMAINS IN SHALLOW TRENCHES PER W22
10. THERMAL INSULATION OF WATERMAINS AT OPEN STRUCTURES PER W23
11. WATERMAIN CROSSING BELOW SEWER PER W25
12. WATERMAIN CROSSING OVER SEWER PER W25.2

NOTE:
THE POSITION OF ALL POLE LINES, CONDUITS, WATERMAINS, SEWERS AND OTHER UNDERGROUND AND OVERGROUND UTILITIES AND STRUCTURES IS NOT NECESSARILY SHOWN ON THE CONTRACT DRAWINGS, AND WHERE SHOWN, THE ACCURACY OF THE POSITION OF SUCH UTILITIES AND STRUCTURES IS NOT GUARANTEED. BEFORE STARTING WORK, DETERMINE THE EXACT LOCATION OF ALL SUCH UTILITIES AND STRUCTURES AND ASSUME ALL LIABILITY FOR DAMAGE TO THEM.

MATTINO DEVELOPMENTS INC
515 Via Mattino Way
Ottawa, Ontario K2J 6B7
Telephone: (613) 440-3767

No.	REVISION	DATE	BY
6.	REVISED PER CITY COMMENTS	DEC 21/22	MAB
5.	CITY SUBMISSION	OCT 5/22	MAB
4.	CITY SUBMISSION	AUG 5/22	MAB
3.	CITY SUBMISSION	JUL 2/20	MAB
2.	REVISED PER CITY COMMENTS	MAR 4/20	MAB
1.	ISSUED FOR APPROVAL	NOV 1/19	MAB

SCALE 1:300 (1:300 0 3 6 9 12)

DESIGN LRW
CHECKED MAB
DRAWN DTD
CHECKED MAB
APPROVED JGR

FOR REVIEW ONLY

L. R. WILSON 100160065 LICENSED PROFESSIONAL ENGINEER PROVINCE OF ONTARIO

M.A. BISSETT 2022.12.21 LICENSED PROFESSIONAL ENGINEER PROVINCE OF ONTARIO

NOVATECH
Engineers, Planners & Landscape Architects
Suite 200, 240 Michael Cowpland Drive
Ottawa, Ontario, Canada K2M 1P6
Telephone (613) 254-9643
Facsimile (613) 254-5867
Website www.novatech-eng.com

CITY OF OTTAWA
LONGFIELDS CENTRAL - BLOCK 21
605 VIA MATTINO WAY

GENERAL PLAN OF SERVICES

PROJECT No. 112021-10
REV REV # 6
DRAWING No. 112021-10-GP

D07-12-19-0190

#18092



PONDING							
PONDING ID	STRUCTURE	100 YEAR PONDING ELEVATION	100 YEAR PONDING DEPTH (m)	100 YEAR +20% PONDING ELEVATION	100 YEAR + 20% PONDING DEPTH (m)	MAX STATIC PONDING ELEVATION	MAX STATIC PONDING DEPTH (m)
P1	CB1	93.20	0.25	93.21	0.26	93.20	0.25
P2	CBMH4	93.20	0.25	93.21	0.26	93.25	0.30
P3	CBMH7	93.20	0.25	93.21	0.26	93.20	0.25
P4	CBMH5	93.08	0.23	93.09	0.24	93.07	0.22
P5	CBMH8	92.85	0.25	92.88	0.28	92.92	0.32
P6	CBMH3	92.85	0.25	92.88	0.28	92.85	0.25
P7	CBMH1	93.08	0.13	93.09	0.14	93.17	0.22
P8	CBMH6	93.23	0.28	93.26	0.31	93.25	0.30
P9	CBMH2	93.20	0.25	93.22	0.27	93.22	0.27



NORTH

KEY PLAN
N.T.S.

LEGEND

2.6%	PROPOSED SLOPE AND DIRECTION
72.55 / 72.45	PROPOSED ELEVATION / EXISTING ELEVATION
×103.41	PROPOSED ELEVATION
×103.41 EP	PROPOSED ELEVATION AT EDGE OF PAVEMENT
×103.41 HP	PROPOSED ELEVATION AT HIGH POINT
×103.41 TC	PROPOSED ELEVATION AT TOP OF CURB
FF=	FINISHED FLOOR ELEVATION
TF=	TOP OF FOUNDATION
USF=	UNDERSIDE OF FOOTING
	DRAINAGE SPLIT
	TERRACING AND BREAKLINE (MAX 3:1 TERRACE SLOPE)
HYD1 TF=102.84	PROPOSED HYDRANT AND TOP OF FLANGE ELEVATION
VB1	PROPOSED VALVE & VALVE BOX LOCATION
SP	PROPOSED SERVICE POST
101	PROPOSED SANITARY MANHOLE
100	PROPOSED STORM MANHOLE
95	PROPOSED CATCHBASIN
	MAJOR OVERLAND FLOW DIRECTION
	100 yr PONDING AREA
	100 yr + 20% PONDING AREA
	MAX. STATIC PONDING AREA
— x — x —	TEMPORARY CONSTRUCTION FENCING

GENERAL NOTES:

1. DIMENSIONS AND LAYOUT INFORMATION SHALL BE CONFIRMED PRIOR TO COMMENCEMENT OF CONSTRUCTION.

2. THE ORIGINAL TOPOGRAPHY AND GROUND ELEVATIONS, SERVICING AND SURVEY INFORMATION SHOWN ON THIS PLAN ARE SUPPLIED FOR INFORMATION PURPOSES ONLY. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO VERIFY THE ACCURACY OF ALL INFORMATION OBTAINED FROM THIS PLAN.

3. CO-ORDINATE AND SCHEDULE ALL WORK WITH OTHER TRADES AND CONTRACTORS.

4. BEFORE COMMENCING CONSTRUCTION, PROVIDE PROOF OF COMPREHENSIVE ALL RISK AND OPERATIONAL LIABILITY INSURANCE INCLUDING BLASTING. INSURANCE POLICY TO NAME THE OWNER, ENGINEER AND THE CITY AS CO-INSURED. AMOUNT OF INSURANCE TO BE SPECIFIED BY OWNER'S AGENT.

5. CONNECT TO EXISTING SYSTEMS AS DETAILED, INCLUDING ALL RESTORATION WORK NECESSARY TO REINSTATE SURFACES TO EXISTING CONDITIONS OR BETTER.

6. DETERMINE THE EXACT LOCATION, SIZE, MATERIAL AND ELEVATION OF ALL EXISTING UTILITIES PRIOR TO COMMENCING CONSTRUCTION. PROTECT AND ASSUME ALL RESPONSIBILITY FOR ALL EXISTING UTILITIES WHETHER OR NOT SHOWN ON THESE DRAWINGS.

7. OBTAIN AND PAY FOR ALL NECESSARY PERMITS AND APPROVALS BEFORE COMMENCING CONSTRUCTION.

8. RESTORE ALL TRENCHES AND SURFACE FEATURES TO EXISTING CONDITIONS OR BETTER AND TO THE SATISFACTION OF CITY OF OTTAWA AUTHORITIES.

- ASPHALT RESTORATION SHALL BE IN ACCORDANCE WITH CITY OF OTTAWA DETAIL R-10.
- THICKNESS OF GRANULAR MATERIAL AND ASPHALT LAYERS TO MATCH EXISTING.
- BOULEVARDS SHALL BE REINSTATED WITH 100mm OF TOPSOIL AND SOD.

9. REMOVE FROM SITE ALL EXCESS EXCAVATED MATERIAL UNLESS OTHERWISE INSTRUCTED BY ENGINEER.

10. ALL ELEVATIONS ARE GEODETIC AND UTILIZE METRIC UNITS.

- THE LEGAL BOUNDARY COMES FROM - REGISTERED PLAN 4M-1527
- SITE BENCH MARK - SPIKE AND WASHER IN ASPHALT ON MOUNT SHANNON DRIVE - N45016560.63 E364246.28 ELEV.=92.28m
- SITE BENCH MARK IS BASED ON VRS CAN-NET NETWORK - GEODETIC ELEVATIONS

12. CONCRETE SIDEWALK TO BE CONSTRUCTED AS PER CITY STANDARD.

13. REFER TO GEOTECHNICAL REPORT (PG2306-1, DATED JANUARY 31, 2013), PREPARED BY PATERSON GROUP FOR SUBSURFACE CONDITIONS AND CONSTRUCTION RECOMMENDATIONS.

14. PERFORATED PIPE SUB-DRAINS TO BE PROVIDED ALONG THE ROADWAY WITH INVERTS 300mm BELOW SUBGRADE PER CITY OF OTTAWA DETAIL R1.

GRADING AND PAVEMENT NOTES:

1. ALL TOPSOIL, ORGANIC OR DELETERIOUS MATERIAL MUST BE ENTIRELY REMOVED FROM BENEATH THE PROPOSED HARD SURFACE (ie. PAVEMENT, CURB, SIDEWALK, ETC.) AREAS AS DIRECTED BY THE SITE ENGINEER OR GEOTECHNICAL ENGINEER.
2. EXPOSED SUBGRADES IN PROPOSED PAVED AREAS SHOULD BE HEAVILY PROOF ROLLED WITH A LARGE (10 TON) VIBRATORY STEEL DRUM ROLLER UNDER DRY CONDITIONS AND INSPECTED BY THE GEOTECHNICAL ENGINEER PRIOR TO THE PLACEMENT OF GRANULARS.
3. ANY SOFT AREAS EVIDENT FROM THE PROOF ROLLING SHOULD BE SUB-EXCAVATED AND REPLACED WITH SUITABLE MATERIAL THAT IS FROST COMPATIBLE WITH THE EXISTING SOILS AS RECOMMENDED BY THE GEOTECHNICAL ENGINEER.
4. THE GRANULAR BASE SHOULD BE PLACED IN MAXIMUM 300mm LIFTS AND COMPACTED TO AT LEAST 98% OF THE STANDARD PROCTOR MAXIMUM DRY DENSITY VALUE. ANY ADDITIONAL GRANULAR FILL USED BELOW THE PROPOSED PAVEMENT SHOULD BE PLACED IN MAXIMUM 300mm LIFTS AND COMPACTED TO AT LEAST 95% OF THE STANDARD PROCTOR MAXIMUM DRY DENSITY VALUE.
5. ASPHALTIC CONCRETE TO BE COMPACTED TO AT LEAST 97% OF MARSHALL DENSITY.
6. ALL ROADWAYS TO HAVE 3% CROSSFALL INCLUDING SUBGRADE AND GRANULAR BASE.
7. ROADWAY SUBGRADE TO BE INSPECTED BY THE GEOTECHNICAL ENGINEER AT THE TIME OF CONSTRUCTION TO REVIEW IF A WOVEN GEOTEXTILE IS REQUIRED BELOW THE GRANULAR MATERIALS; AND TO CONFIRM THE DEPTH AND COMPACTION OF GRANULAR 'B'
8. PRIOR TO PLACEMENT OF TOPLIFT, THE CONTRACTOR SHALL ADJUST ALL STRUCTURES TO FINAL GRADE PER CITY OF OTTAWA STANDARDS.
9. MINIMUM OF 2% GRADE FOR ALL GRASS AREAS UNLESS OTHERWISE NOTED.
10. MAXIMUM TERRACING GRADE TO BE 3:1 UNLESS OTHERWISE NOTED.
11. ALL GRADES BY CURBS ARE EDGE OF PAVEMENT GRADES UNLESS OTHERWISE INDICATED.
12. CURBS SHALL BE BARRIER CURB AS SPECIFIED AND CONSTRUCTED PER CITY OF OTTAWA STANDARD (SC1.2).
13. REFER TO LANDSCAPE PLAN FOR PLANTING AND OTHER LANDSCAPE FEATURE DETAILS.
14. TOPOGRAPHY IS DERIVED FROM NCC 1:2000 MAPPING AND SUPPLEMENTED WITH FIELD SURVEY BY NOVATECH

PAVEMENT STRUCTURE:

40mm	ASPHALT SP-12.5
50mm	ASPHALT SP-19.0
150mm	GRAN "A"
400mm	GRAN "B" TYPE II
640mm	TOTAL DEPTH

NOTE:
THE POSITION OF ALL POLE LINES, CONDUITS, WATERMAINS, SEWERS AND OTHER UNDERGROUND AND OVERGROUND UTILITIES AND STRUCTURES IS NOT NECESSARILY SHOWN ON THE CONTRACT DRAWINGS, AND WHERE SHOWN, THE ACCURACY OF THE POSITION OF SUCH UTILITIES AND STRUCTURES IS NOT GUARANTEED. BEFORE STARTING WORK, DETERMINE THE EXACT LOCATION OF ALL SUCH UTILITIES AND STRUCTURES AND ASSUME ALL LIABILITY FOR DAMAGE TO THEM.

MATTINO DEVELOPMENTS INC
515 Via Mattino Way
Ottawa, Ontario K2J 6B7
Telephone: (613) 440-3767

No.	REVISION	DATE	BY
6.	REVISED PER CITY COMMENTS	DEC 21/22	MAB
5.	CITY SUBMISSION	OCT 5/22	MAB
4.	CITY SUBMISSION	AUG 5/22	MAB
3.	CITY SUBMISSION	JUL 2/20	MAB
2.	REVISED PER CITY COMMENTS	MAR 4/20	MAB
1.	ISSUED FOR APPROVAL	NOV 1/19	MAB

SCALE 1:300

1:300
0 3 6 9 12

DESIGN DTD
CHECKED MAB
DRAWN DTD
CHECKED MAB
APPROVED JGR

FOR REVIEW ONLY

LICENSED PROFESSIONAL ENGINEER L. R. WILSON 100160065 PROVINCE OF ONTARIO

LICENSED PROFESSIONAL ENGINEER M.A. BISSETT 2022.12.21 PROVINCE OF ONTARIO

NOVATECH
Engineers, Planners & Landscape Architects
Suite 200, 240 Michael Cowpland Drive
Ottawa, Ontario, Canada K2M 1P6
Telephone (613) 254-9643
Facsimile (613) 254-5867
Website www.novatech-eng.com

CITY OF OTTAWA
LONGFIELDS CENTRAL - BLOCK 21
605 VIA MATTINO WAY

GRADING PLAN

PROJECT No. 112021-10
REV REV # 6
DRAWING No. 112021-10-GR

D07-12-19-0190

#18092

M:\2012\112021\Block 21\CAD\Design\112021-10-GR.dwg, GR, Dec 13, 2022



PONDING

PONDING ID	STRUCTURE	100 YEAR PONDING ELEVATION	100 YEAR PONDING DEPTH (m)	100 YEAR +20% PONDING ELEVATION	100 YEAR + 20% PONDING DEPTH (m)	MAX STATIC PONDING ELEVATION	MAX STATIC PONDING DEPTH (m)
P1	CB1	93.20	0.25	93.21	0.26	93.20	0.25
P2	CBMH4	93.20	0.25	93.21	0.26	93.25	0.30
P3	CBMH7	93.20	0.25	93.21	0.26	93.20	0.25
P4	CBMH5	93.08	0.23	93.09	0.24	93.07	0.22
P5	CBMH8	92.85	0.25	92.88	0.28	92.92	0.32
P6	CBMH3	92.85	0.25	92.88	0.28	92.85	0.25
P7	CBMH1	93.08	0.13	93.09	0.14	93.17	0.22
P8	CBMH6	93.23	0.28	93.26	0.31	93.25	0.30
P9	CBMH2	93.20	0.25	93.22	0.27	93.22	0.27

NOTE:
THE POSITION OF ALL POLE LINES, CONDUITS, WATERMAINS, SEWERS AND OTHER UNDERGROUND AND OVERGROUND UTILITIES AND STRUCTURES IS NOT NECESSARILY SHOWN ON THE CONTRACT DRAWINGS, AND WHERE SHOWN, THE ACCURACY OF THE POSITION OF SUCH UTILITIES AND STRUCTURES IS NOT GUARANTEED. BEFORE STARTING WORK, DETERMINE THE EXACT LOCATION OF ALL SUCH UTILITIES AND STRUCTURES AND ASSUME ALL LIABILITY FOR DAMAGE TO THEM.

MATTINO DEVELOPMENTS INC
515 Via Mattino Way
Ottawa, Ontario K2J 6B7
Telephone: (613) 440-3767

No.	REVISION	DATE	BY
6.	REVISED PER CITY COMMENTS	DEC 21/22	MAB
5.	CITY SUBMISSION	OCT 5/22	MAB
4.	CITY SUBMISSION	AUG 5/22	MAB
3.	CITY SUBMISSION	JUL 2/20	MAB
2.	REVISED PER CITY COMMENTS	MAR 4/20	MAB
1.	ISSUED FOR APPROVAL	NOV 1/19	MAB

SCALE 1:300 (1:300, 0 3 6 9 12)

DESIGN LRW
CHECKED MAB
DRAWN DTD
CHECKED MAB
APPROVED JGR

FOR REVIEW ONLY

LICENSED PROFESSIONAL ENGINEER — L. R. WILSON — 100160065 — PROVINCE OF ONTARIO

LICENSED PROFESSIONAL ENGINEER — M.A. BISSETT — 2022.12.21 — PROVINCE OF ONTARIO

NOVATECH
Engineers, Planners & Landscape Architects
Suite 200, 240 Michael Cowpland Drive
Ottawa, Ontario, Canada K2M 1P6
Telephone (613) 254-9643
Facsimile (613) 254-5867
Website www.novatech-eng.com

CITY OF OTTAWA
LONGFIELDS CENTRAL - BLOCK 21
605 VIA MATTINO WAY

POST-DEVELOPMENT
STORM DRAINAGE AREA PLAN

PROJECT No. 112021-10
REV REV # 6
DRAWING No. 112021-10-STM

D07-12-19-0190

#18092

M:\2021\112021\Block 21\CAD\Design\112021-10-STM.dwg STM Oct 05, 2022 - 2:09pm lwilson



LEGEND

- SILT FENCE PER OPSD 219.110
- MUD MATS (50mm - 100mm GRANULAR B, TYPE II)
- EXISITING GROUND CONTOUR AND ELEVATION
- TEMPORARY CONSTRUCTION FENCING
- VB — VALVE & VALVE BOX
- ECB30 — LANDSCAPE TYPE CATCHBASIN
- RYCB9 — REAR YARD CATCH BASIN
- CBMH15 — CATCH BASIN MANHOLE
- 96 — CATCHBASIN

EROSION AND SEDIMENT CONTROL NOTES :

1. ALL EROSION AND SEDIMENT CONTROLS ARE TO BE INSTALLED AND MAINTAINED TO THE SATISFACTION OF THE ENGINEER, THE MUNICIPALITY AND THE CONSERVATION AUTHORITY. THEY ARE TO BE APPROPRIATE TO THE SITE CONDITIONS, PRIOR TO UNDERTAKING ANY SITE ALTERATIONS (FILLING, GRADING, REMOVAL OF VEGETATION, ETC.) AND DURING ALL PHASES OF SITE PREPARATION AND CONSTRUCTION. THESE PRACTICES ARE TO BE IMPLEMENTED IN ACCORDANCE WITH THE CURRENT BEST MANAGEMENT PRACTICES FOR EROSION AND SEDIMENT CONTROL AND SHOULD INCLUDE AS A MINIMUM THOSE MEASURES INDICATED ON THE PLAN.
2. TO PREVENT SURFACE EROSION FROM ENTERING THE DITCH OR STORM SYSTEM DURING CONSTRUCTION, FILTER SOCKS (TERRAFIX SILT SOXX OR APPROVED EQUIVALENT) WILL BE PLACED AROUND GRATES OF ALL PROPOSED AND EXISTING CATCHBASINS AND STRUCTURES. A LIGHT DUTY SILT FENCE BARRIER WILL ALSO BE INSTALLED IN SELECTED LOCATIONS SHOWN ON THIS PLAN. THESE CONTROL MEASURES WILL REMAIN IN PLACE UNTIL VEGETATION HAS BEEN ESTABLISHED AND CONSTRUCTION COMPLETE.
3. THE SEDIMENT CONTROL MEASURES SHALL ONLY BE REMOVED WHEN, IN THE OPINION OF THE ENGINEER, THE MEASURES ARE NO LONGER REQUIRED. NO CONTROL MEASURES MAY BE PERMANENTLY REMOVED WITHOUT PRIOR AUTHORIZATION FROM THE ENGINEER.
4. THE CONTRACTOR SHALL IMMEDIATELY REPORT TO THE ENGINEER ANY ACCIDENTAL DISCHARGES OF SEDIMENT MATERIAL INTO ANY DITCH OR STORM SEWER SYSTEM. APPROPRIATE RESPONSE MEASURES, INCLUDING ANY REPAIRS TO EXISTING CONTROL MEASURES OR THE IMPLEMENTATION OF ADDITIONAL CONTROL MEASURES, SHALL BE CARRIED OUT BY THE CONTRACTOR WITHOUT DELAY.
5. THE CONTRACTOR ACKNOWLEDGES THAT FAILURE TO IMPLEMENT EROSION AND SEDIMENT CONTROL MEASURES MAY BE SUBJECT TO PENALTIES IMPOSED BY ANY APPLICABLE REGULATORY AGENCY.
6. THE CONTRACTOR SHALL ENSURE PROPER DUST CONTROL IS PROVIDED WITH THE APPLICATION OF WATER (AND IF REQUIRED, CALCIUM CHLORIDE) DURING DRY PERIODS.
7. CONTRACTOR SHALL INSTALL MUD MATS AT THE CONSTRUCTION ENTRANCE.
8. ALL TOPSOIL AND ANY SOFT, WET OR DELETERIOUS MATERIAL SHALL BE REMOVED FROM IMPROVED AREAS UNLESS OTHERWISE DIRECTED BY ENGINEER.
9. THE EROSION AND SEDIMENT CONTROL PLAN SHOULD BE CONSIDERED A "LIVING DOCUMENT" WHICH MAY NEED TO BE REVISED AND EXPANDED AS THE PROJECT EVOLVES.
10. THE CONTRACTOR SHALL IMPLEMENT BEST MANAGEMENT PRACTICES, TO PROVIDE FOR PROTECTION OF THE AREA DRAINAGE SYSTEM AND RECEIVING WATERCOURSE, DURING CONSTRUCTION ACTIVITIES. THE CONTRACTOR ACKNOWLEDGES THAT FAILURE TO IMPLEMENT APPROPRIATE EROSION AND SEDIMENT CONTROL MEASURES MAY BE SUBJECT TO PENALTIES IMPOSED BY ANY APPLICABLE REGULATORY AGENCY.

NOTE:
THE POSITION OF ALL POLE LINES, CONDUITS, WATERMAINS, SEWERS AND OTHER UNDERGROUND AND OVERGROUND UTILITIES AND STRUCTURES IS NOT NECESSARILY SHOWN ON THE CONTRACT DRAWINGS, AND WHERE SHOWN, THE ACCURACY OF THE POSITION OF SUCH UTILITIES AND STRUCTURES IS NOT GUARANTEED. BEFORE STARTING WORK, DETERMINE THE EXACT LOCATION OF ALL SUCH UTILITIES AND STRUCTURES AND ASSUME ALL LIABILITY FOR DAMAGE TO THEM.

MATTINO DEVELOPMENTS INC
515 Via Mattino Way
Ottawa, Ontario K2J 6B7
Telephone: (613) 440-3767

No.	REVISION	DATE	BY
6.	REVISED PER CITY COMMENTS	DEC 21/22	MAB
5.	CITY SUBMISSION	OCT 5/22	MAB
4.	CITY SUBMISSION	AUG 5/22	MAB
3.	CITY SUBMISSION	JUL 2/20	MAB
2.	REVISED PER CITY COMMENTS	MAR 4/20	MAB
1.	ISSUED FOR APPROVAL	NOV 1/19	MAB

SCALE 1:300 (1:300, 0 3 6 9 12)

DESIGN LRW
CHECKED MAB
DRAWN DTD
CHECKED MAB
APPROVED JGR

FOR REVIEW ONLY

LICENSED PROFESSIONAL ENGINEER — L. R. WILSON — 100160065 — PROVINCE OF ONTARIO

LICENSED PROFESSIONAL ENGINEER — M.A. BISSETT — 2022.12.21 — PROVINCE OF ONTARIO

NOVATECH
Engineers, Planners & Landscape Architects
Suite 200, 240 Michael Cowpland Drive
Ottawa, Ontario, Canada K2M 1P6
Telephone (613) 254-9643
Facsimile (613) 254-5867
Website www.novatech-eng.com

CITY OF OTTAWA
LONGFIELDS CENTRAL - BLOCK 21
605 VIA MATTINO WAY

EROSION AND SEDIMENT CONTROL PLAN

PROJECT No. 112021-10
REV REV # 6
DRAWING No. 112021-10-ESC

D07-12-19-0190

#18092

M:\2021\112021\Block 21\CAD\Design\112021-10-ESC.dwg, GP, Oct 05, 2022 - 2:12pm, lwilson

APPENDIX D: Geotechnical Memorandums

Geotechnical Review – Block 21 Existing Soils Information (Nov. 12/19)
Geotechnical Review – Block 21 Existing Information (Nov. 23/20)

patersongroup **memorandum**

consulting engineers

re: **Geotechnical Review - Block 21 Existing Soils Information**
Proposed Residential Development
Block 21 - 591 Via Mattino Way - Ottawa

to: Mattino Homes - **Mr. Pino Mattino** - mattino.ca@gmail.com

date: November 12, 2019

file: PG2306-MEMO.08

The present memorandum has been prepared to provide a geotechnical review of the existing soils information located within the area of Block 21 within the aforementioned site. The present report should be read in conjunction with Paterson Report PG2306-1 dated January 13, 2013. Our response is summarized below:

Review of Existing Soils Information - Block 21

Paterson has reviewed the above noted geotechnical report with respect to the location of Block 21 within the development. Based on our review, the proposed development at Block 21 is partially within the area of study. A consistent subsurface profile was noted across the area of study and it is anticipated that a similar subsurface profile will be encountered within Block 21.

Therefore, the above noted geotechnical report is applicable for the proposed developments to be located within Block 21. A typical materials testing and inspection program for residential developments is required to be carried out during construction to confirm the geotechnical recommendations in the above noted geotechnical report, including the provided bearing capacities.

We trust that this information satisfies your immediate requirements.

Paterson Group Inc.

Colin Belcourt, P.Eng.

David J. Gilbert, P.Eng.

Paterson Group Inc.

Head Office and Laboratory
154 Colonnade Road South
Ottawa - Ontario - K2E 7J5
Tel: (613) 226-7381 Fax: (613) 226-6344

Northern Office and Laboratory
63 Gibson Street
North Bay - Ontario - P1B 8Z4
Tel: (705) 472-5331 Fax: (705) 472-2334

St. Lawrence Office
993 Princess Street
Kingston - Ontario - K7L 1H3
Tel: (613) 542-7381

patersongroup **memorandum**

consulting engineers

re: **Geotechnical Review - Block 21 Existing Information**
Proposed Residential Development
Block 21 - 591 Via Mattino Way - Ottawa

to: Mattino Homes - **Mr. Pino Mattino** - mattino.ca@gmail.com

date: November 23, 2020

file: PG2306-MEMO.09

Further to your request, Paterson Group (Paterson) prepared a response for the geotechnical review comments received from the City of Ottawa based on the memo issued on November 12, 2019 (PG2306-MEMO.06) for the proposed residential development of Block 21 within the aforementioned site.

Review of Existing Geotechnical Information - Block 21

Paterson reviewed the available geotechnical information for Block 21. The subject site has a consistent subsoil profile which is suitable for the proposed residential development. The available geotechnical information for Block 21 is in general conformance with City of Ottawa Geotechnical Investigation Guidelines. It's expected that during the construction phase, each foundation will be subjected to a geotechnical field inspection to confirm geotechnical conditions and design parameters.

Grading Plan Review

A grading plan prepared by Novatech Engineering (Drawing 112021-10-GR Revision 3 dated July 2, 2020 was reviewed and approved. Memo enclosed.

We trust that this information satisfies your requirements.

Best Regards,

Paterson Group Inc.

Carlos P. Da Silva, P.Eng., ing., QP_{ESA}

Paterson Group Inc.

Head Office and Laboratory
154 Colonnade Road South
Ottawa - Ontario - K2E 7J5
Tel: (613) 226-7381 Fax: (613) 226-6344

Northern Office and Laboratory
63 Gibson Street
North Bay - Ontario - P1B 8Z4
Tel: (705) 472-5331 Fax: (705) 472-2334

St. Lawrence Office
993 Princess Street
Kingston - Ontario - K7L 1H3
Tel: (613) 542-7381

patersongroup **memorandum**

consulting engineers

re: **Grading Plan Review - Block 21**
Proposed Residential Development
Block 21 - 591 Via Mattino Way - Ottawa

to: Mattino Homes - **Mr. Pino Mattino** - mattino.ca@gmail.com

date: November 23, 2020

file: PG2306-MEMO.10

Further to your request, Paterson Group (Paterson) reviewed the following grading plan for the proposed residential complex with one basement level parking at the aforementioned site.

Grading Plan Review

A grading plan prepared by Novatech Engineering (Drawing 112021-10-GR Revision 3 dated July 2, 2020 was reviewed for Block 21.

Paterson Review

Based on the stiff to very stiff nature of the upper silty clay deposit and the underlying firm clay, the final grading being proposed for the subject development is within the acceptable permissible grade raise of 1.2 m and considered satisfactory from a geotechnical perspective.

We trust that this information satisfies your requirements.

Best Regards,

Paterson Group Inc.

Carlos P. Da Silva, P.Eng., ing., QP_{ESA}

Paterson Group Inc.

Head Office and Laboratory
154 Colonnade Road South
Ottawa - Ontario - K2E 7J5
Tel: (613) 226-7381 Fax: (613) 226-6344

Northern Office and Laboratory
63 Gibson Street
North Bay - Ontario - P1B 8Z4
Tel: (705) 472-5331 Fax: (705) 472-2334

St. Lawrence Office
993 Princess Street
Kingston - Ontario - K7L 1H3
Tel: (613) 542-7381

ROADWAY PONDING							
PONDING ID	STRUCTURE	100 YEAR PONDING ELEVATION	100 YEAR PONDING DEPTH (m)	100 YEAR +20% PONDING ELEVATION	100 YEAR + 20% PONDING DEPTH (m)	MAX STATIC PONDING ELEVATION	MAX STATIC PONDING DEPTH (m)
P1	CB4	93.07	0.12	93.11	0.16	93.10	0.15
P2	CBMH4	93.07	0.12	93.14	0.19	93.25	0.30
P3	CB2	93.07	0.12	93.15	0.20	93.20	0.25
P4	CB3	93.08	0.18	93.08	0.18	93.07	0.17
P5	CB1	92.85	0.23	92.93	0.31	92.92	0.30
P6	CBMH3	92.83	0.21	92.86	0.24	92.85	0.23
P7	CBMH1	93.08	0.13	93.12	0.17	93.17	0.22
P8	CB5	93.21	0.26	93.25	0.30	93.25	0.30
P9	CBMH2	93.21	0.26	93.23	0.28	93.22	0.27

NORTH

KEY PLAN
N.T.S.

LEGEND

- PROPOSED SLOPE AND DIRECTION
- PROPOSED ELEVATION / EXISTING ELEVATION
- PROPOSED ELEVATION
- PROPOSED ELEVATION AT EDGE OF PAVEMENT
- PROPOSED ELEVATION AT HIGH POINT
- PROPOSED ELEVATION AT TOP OF CURB
- FF= FINISHED FLOOR ELEVATION
- TF= TOP OF FOUNDATION
- USF= UNDERSIDE OF FOOTING
- DRAINAGE SPLIT
- TERRACING AND BREAKLINE (MAX 3:1 TERRACE SLOPE)
- PROPOSED HYDRANT AND TOP OF FLANGE ELEVATION
- PROPOSED VALVE & VALVE BOX LOCATION
- PROPOSED SERVICE POST
- PROPOSED SANITARY MANHOLE
- PROPOSED STORM MANHOLE
- PROPOSED CATCHBASIN
- MAJOR OVERLAND FLOW DIRECTION
- 100 yr PONDING AREA
- 100 yr + 20% PONDING AREA
- MAX. STATIC PONDING AREA
- TEMPORARY CONSTRUCTION FENCING

GENERAL NOTES:

1. DIMENSIONS AND LAYOUT INFORMATION SHALL BE CONFIRMED PRIOR TO COMMENCEMENT OF CONSTRUCTION.
2. THE ORIGINAL TOPOGRAPHY AND GROUND ELEVATIONS, SERVICING AND SURVEY INFORMATION SHOWN ON THIS PLAN ARE SUPPLIED FOR INFORMATION PURPOSES ONLY. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO VERIFY THE ACCURACY OF ALL INFORMATION OBTAINED FROM THIS PLAN.
3. CO-ORDINATE AND SCHEDULE ALL WORK WITH OTHER TRADES AND CONTRACTORS.
4. BEFORE COMMENCING CONSTRUCTION, PROVIDE PROOF OF COMPREHENSIVE ALL RISK AND OPERATIONAL LIABILITY INSURANCE INCLUDING BLASTING. INSURANCE POLICY TO NAME THE OWNER, ENGINEER AND THE CITY AS CO-INSURED. AMOUNT OF INSURANCE TO BE SPECIFIED BY OWNER'S AGENT.
5. CONNECT TO EXISTING SYSTEMS AS DETAILED, INCLUDING ALL RESTORATION WORK NECESSARY TO REINSTATE SURFACES TO EXISTING CONDITIONS OR BETTER.
6. DETERMINE THE EXACT LOCATION, SIZE, MATERIAL AND ELEVATION OF ALL EXISTING UTILITIES PRIOR TO COMMENCING CONSTRUCTION. PROTECT AND ASSUME ALL RESPONSIBILITY FOR ALL EXISTING UTILITIES WHETHER OR NOT SHOWN ON THESE DRAWINGS.
7. OBTAIN AND PAY FOR ALL NECESSARY PERMITS AND APPROVALS BEFORE COMMENCING CONSTRUCTION.
8. RESTORE ALL TRENCHES AND SURFACE FEATURES TO EXISTING CONDITIONS OR BETTER AND TO THE SATISFACTION OF CITY OF OTTAWA AUTHORITIES.
   - ASPHALT RESTORATION SHALL BE IN ACCORDANCE WITH CITY OF OTTAWA DETAIL R-10,
   - THICKNESS OF GRANULAR MATERIAL AND ASPHALT LAYERS TO MATCH EXISTING.
   - BOULEVARDS SHALL BE REINSTATED WITH 100mm OF TOPSOIL AND SOD.
9. REMOVE FROM SITE ALL EXCESS EXCAVATED MATERIAL UNLESS OTHERWISE INSTRUCTED BY ENGINEER.
10. ALL ELEVATIONS ARE GEODETIC AND UTILIZE METRIC UNITS.
    - THE LEGAL BOUNDARY COMES FROM - REGISTERED PLAN 4M-1527
    - SITE BENCH MARK - SPIKE AND WASHER IN ASPHALT ON MOUNT SHANNON DRIVE - N45016560.63 E364246.28 ELEV.=92.28m
    - SITE BENCH MARK IS BASED ON VRS CAN-NET NETWORK - GEODETIC ELEVATIONS
12. CONCRETE SIDEWALK TO BE CONSTRUCTED AS PER CITY STANDARD.
13. REFER TO GEOTECHNICAL REPORT (PG2306-1, DATED JANUARY 31, 2013), PREPARED BY PATERSON GROUP FOR SUBSURFACE CONDITIONS AND CONSTRUCTION RECOMMENDATIONS.
14. PERFORATED PIPE SUB-DRAINS TO BE PROVIDED ALONG THE ROADWAY WITH INVERTS 300mm BELOW SUBGRADE PER CITY OF OTTAWA DETAIL R1.

GRADING AND PAVEMENT NOTES:

1. ALL TOPSOIL, ORGANIC OR DELETERIOUS MATERIAL MUST BE ENTIRELY REMOVED FROM BENEATH THE PROPOSED HARD SURFACE (ie. PAVEMENT, CURB, SIDEWALK, ETC.) AREAS AS DIRECTED BY THE SITE ENGINEER OR GEOTECHNICAL ENGINEER.
2. EXPOSED SUBGRADES IN PROPOSED PAVED AREAS SHOULD BE HEAVILY PROOF ROLLED WITH A LARGE (10 TON) VIBRATORY STEEL DRUM ROLLER UNDER DRY CONDITIONS AND INSPECTED BY THE GEOTECHNICAL ENGINEER PRIOR TO THE PLACEMENT OF GRANULARS.
3. ANY SOFT AREAS EVIDENT FROM THE PROOF ROLLING SHOULD BE SUB-EXCAVATED AND REPLACED WITH SUITABLE MATERIAL THAT IS FROST COMPATIBLE WITH THE EXISTING SOILS AS RECOMMENDED BY THE GEOTECHNICAL ENGINEER.
4. THE GRANULAR BASE SHOULD BE PLACED IN MAXIMUM 300mm LIFTS AND COMPACTED TO AT LEAST 98% OF THE STANDARD PROCTOR MAXIMUM DRY DENSITY VALUE. ANY ADDITIONAL GRANULAR FILL USED BELOW THE PROPOSED PAVEMENT SHOULD BE PLACED IN MAXIMUM 300mm LIFTS AND COMPACTED TO AT LEAST 95% OF THE STANDARD PROCTOR MAXIMUM DRY DENSITY VALUE.
5. ASPHALTIC CONCRETE TO BE COMPACTED TO AT LEAST 97% OF MARSHALL DENSITY.
6. ALL ROADWAYS TO HAVE 3% CROSSFALL INCLUDING SUBGRADE AND GRANULAR BASE.
7. ROADWAY SUBGRADE TO BE INSPECTED BY THE GEOTECHNICAL ENGINEER AT THE TIME OF CONSTRUCTION TO REVIEW IF A WOVEN GEOTEXTILE IS REQUIRED BELOW THE GRANULAR MATERIALS; AND TO CONFIRM THE DEPTH AND COMPACTION OF GRANULAR 'B'
8. PRIOR TO PLACEMENT OF TOPLIFT, THE CONTRACTOR SHALL ADJUST ALL STRUCTURES TO FINAL GRADE PER CITY OF OTTAWA STANDARDS.
9. MINIMUM OF 2% GRADE FOR ALL GRASS AREAS UNLESS OTHERWISE NOTED.
10. MAXIMUM TERRACING GRADE TO BE 3:1 UNLESS OTHERWISE NOTED.
11. ALL GRADES BY CURBS ARE EDGE OF PAVEMENT GRADES UNLESS OTHERWISE INDICATED.
12. CURBS SHALL BE BARRIER CURB AS SPECIFIED AND CONSTRUCTED PER CITY OF OTTAWA STANDARD (SC1.2).
13. REFER TO LANDSCAPE PLAN FOR PLANTING AND OTHER LANDSCAPE FEATURE DETAILS.
14. TOPOGRAPHY IS DERIVED FROM NCC 1:2000 MAPPING AND SUPPLEMENTED WITH FIELD SURVEY BY NOVATECH

PAVEMENT STRUCTURE:

40mm	ASPHALT SP-12.5
50mm	ASPHALT SP-19.0
150mm	GRAN "A"
400mm	GRAN "B" TYPE II
640mm	TOTAL DEPTH

NOTE:
THE POSITION OF ALL POLE LINES, CONDUITS, WATERMAINS, SEWERS AND OTHER UNDERGROUND AND OVERGROUND UTILITIES AND STRUCTURES IS NOT NECESSARILY SHOWN ON THE CONTRACT DRAWINGS, AND WHERE SHOWN, THE ACCURACY OF THE POSITION OF SUCH UTILITIES AND STRUCTURES IS NOT GUARANTEED. BEFORE STARTING WORK, DETERMINE THE EXACT LOCATION OF ALL SUCH UTILITIES AND STRUCTURES AND ASSUME ALL LIABILITY FOR DAMAGE TO THEM.

MATTINO DEVELOPMENTS INC
515 Via Mattino Way
Ottawa, Ontario K2J 6B7
Telephone: (613) 440-3767

No.	REVISION	DATE	BY
3.	CITY SUBMISSION	JUL 2/20	MAB
2.	REVISED PER CITY COMMENTS	MAR 4/20	MAB
1.	ISSUED FOR APPROVAL	NOV 1/19	MAB

SCALE 1:300 (1:300, 0 3 6 9 12)

DESIGN DTD
CHECKED MAB
DRAWN DTD
CHECKED MAB
APPROVED JGR

FOR REVIEW ONLY

LICENSED PROFESSIONAL ENGINEER — L. R. WILSON — 100160065 — 2020.07.02 — PROVINCE OF ONTARIO

LICENSED PROFESSIONAL ENGINEER — M.A. BISSETT — 2020.07.02 — PROVINCE OF ONTARIO

NOVATECH
Engineers, Planners & Landscape Architects
Suite 200, 240 Michael Cowpland Drive
Ottawa, Ontario, Canada K2M 1P6
Telephone (613) 254-9643
Facsimile (613) 254-5867
Website www.novatech-eng.com

CITY OF OTTAWA
LONGFIELDS CENTRAL - BLOCK 21
605 VIA MATTINO WAY

GRADING PLAN

PROJECT No. 112021-10
REV REV # 3
DRAWING No. 112021-10-GR

D07-12-19-0190

#18092

M:\2021\10\02\Block 21\CAD\Design\112021-10-GR.dwg, GR, Jul 02, 2020 - 12:37pm, dsolson