Proposed High-Rise Residential Development 1200 Maritime Way

Serviceability and Stormwater Management Report

Prepared for:

Claridge Homes

Prepared By:

NOVATECH Suite 200, 240 Michael Cowpland Drive Ottawa, Ontario K2M 1P6

> January 25, 2021 Amended November 3, 2021 Revised May 31, 2022 Revised October 11, 2022 Revised April 28, 2023

> > Novatech File: 120144 Ref No. R-2021-012



April 28, 2022

City of Ottawa Planning, Infrastructure and Economic Development Department Planning and Infrastructure Approvals Branch 110 Laurier Avenue West, 4th Floor Ottawa ON, K1P 1J1

Attention: Ms. Laurel McCreight, MCIP, RPP

Dear Laurel:

Reference: 1200 Maritime Way - Claridge Development (D07-12-21-0017) Serviceability and Stormwater Management Report

Enclosed is the Serviceability and Stormwater Management Report for the proposed 1200 Maritime Way development located along the Highway 417, Kanata Avenue and Maritime Way in the City of Ottawa. This report is submitted in support of the site plan application and outlines how the site will be serviced with public infrastructure.

Trusting this report is adequate for your purposes. Should you have any questions, or require additional information, please contact me.

Yours truly,

NOVATECH 27 Marcoul

Greg MacDonald, P. Eng. Director, Land Development and Public Sector Infrastructure

cc: Vincent, Denomme, Claridge Homes

TABLE OF CONTENTS

1.0	INTRODUCTION	1
2.0	EXISTING CONDITIONS	1
3.0	PROPOSED DEVELOPMENT	1
4.0	SITE CONSTRAINTS	2
5.0	SANITARY SEWER	3
6.0	STORM SEWER AND STORMWATER MANAGEMENT	4
6.1		4
6.2		5
6.3		5
6.4		6
6.5	Major Overland Flow Route	6
7.0	WATERMAIN	7
8.0	EROSION AND SEDIMENT CONTROL	8
9.0		

List of Figures

Figure 1:	Key Plan
Figure 2:	Existing Conditions Plan
Figure 3:	Site Plan

List of Tables

- Table 6.1:
 Stormwater Management Summary
- Table 7.1:Domestic Water Demand Summary
- Table 7.1:
 Water Boundary Conditions and Hydraulic Analysis Summary

List of Appendices

- Appendix A: Site Plan
- Appendix B: Sanitary Servicing Information
- Appendix C: Stormwater Management Calculations
- Appendix D: Water Servicing Information
- Appendix E: Servicing Study Guidelines Checklist
- Appendix F: Pre-consultation Meeting Minutes

List of Drawings

Notes and Details	120144-ND
General Plan of Services	120144-GP
Grading and Erosion Sediment Control Plan	120144-GR
Erosion and Sediment Control Plan	120144-ESC
Stormwater Management Plan	120144-SWM

1.0 INTRODUCTION

Novatech has been retained by Claridge Homes to prepare a Servicing and Stormwater Management Report for the proposed residential development located 1200 Maritime Way within the City of Ottawa. The site is located between Maritime Way and Highway 417 and is part of the Kanata Town Centre – Central Business District (KTC-CBD). The purpose of this report is to support the site plan application for the subject development. **Figure 1** Key Plan shows the site location.

2.0 EXISTING CONDITIONS

The subject site has an approximate area of 1.24 hectares and is currently undeveloped. The site is bound by Maritime Way and Townplace Suites to the north, Vacant Land to the East, Highway 417 to the south and Timberwalk Retirement Home to the West. The site is generally flat with a gradual slope from the south to the north. The site currently contains a number of fill piles ranging in 1-2m in height in the southern portion of the site from previous development activities within the Business District. It should be noted that the Northern portion of the site also once contained a stormwater management pond which has since been filled in. **Figure 2** depicts the existing site conditions.

The Subject site is part of the Kanata Town Centre, Central Business District which was designed by JL. Richards and design information is provided in the following reports:


- Kanata Town Centre, Central Business District, Stormwater Management Report, J.L. Richards, January 1999 (Referenced as JLR Report)
- Servicing Brief (Revised) Kanata Town Centre Central Business District Subdivision, Technical Memorandum, J.L. Richards, June 13, 2012
- Kanata Town Centre Central Business District Master Design Sheet Update Sanitary Peak Flows Block 4, Block 5 and Block west of Block 9 (Zone 122), J.L. Richards, August 18,2017 (Referenced as JLR Memo).


3.0 PROPOSED DEVELOPMENT

The proposed development will include two (2) apartment buildings interconnected by a central access and a joint underground parking structure. The proposed buildings will be referred to the East Tower and West Tower for the remainder of the report. It is proposed to develop the site in two (2) phases with Phase 1 including the West Tower, central entrance, and the parking structure outside the footprint of the East Tower, and Phase 2 including the East tower and the parking structure below.

The West Tower will be a total of thirty (30) storeys, complete with a seven (7) storey podium, and a total of 313 units. The East Tower will be a total of twenty-eight (28) storeys, complete with a seven (7) storey podium with a total of 302 units, and 400m² of commercial area. The overall development will provide 634 parking spaces. **Figure 3** shows the proposed development.

Access to the site will be provided from the proposed central entrance from Maritime Way.








Website

TECH	1200 MARITIME WAY CITY OF OTTAWA
andscape Architects el Cowpland Drive anada K2M 1P6	EXISTING CONDITIONS PLAN
(613) 254-9643 (613) 254-5867	1:750 1:750 30 30
v.novatech-eng.com	DATE MAY 2022 JOB FIGURE 2

GUT11V17 NIA/C = 270mmYA22mm



TECH	1200 MARIT		
Landscape Architects ael Cowpland Drive Canada K2M 1P6	PROPOSED) SITE PLAN	
(613) 254-9643 (613) 254-5867	scale 1:750	0 10	20 30
w.novatech-eng.com	APRIL 2023	^{јов} 120144	FIGURE 3

4.0 SITE CONSTRAINTS

A geotechnical investigation was completed by Paterson Group Inc. and a report prepared entitled 'Geotechnical Investigation, Proposed High-Rise Development', Report PG5281-1, dated July 16, 2020. The report included the following recommendations:

- Inferred bedrock surface was encountered at depths ranging from approximately 3.7 m at the west end of the site, descending to depths of approximately 16.2 m on the east end of the site.
- The long-term groundwater table can be expected at approximately 4 to 5 m below ground surface. It should also be noted that groundwater levels are subject to seasonal fluctuations. Therefore, the groundwater level could vary at the time of construction.
- Due to the presence of the silty clay deposit, a permissible grade raise restriction of 2 m is recommended for grading at the subject site. If higher than permissible grade raises are required, preloading with or without a surcharge, lightweight fill, and/or other measures should be investigated to reduce the risks of unacceptable long-term post construction total and differential settlements.
- The excavation side slopes above the groundwater level extending to a maximum depth of 3 m should be excavated at 1H:1V or shallower. The shallower slope is required for excavation below groundwater level. The subsurface soils are considered to be a Type 2 and 3 soil according to the Occupational Health and Safety Act and Regulations for Construction Projects.
- A temporary Ministry of Environment, Conservation and Parks (MECP) permit to take water (PTTW) may be required if more than 400,000 L/day of ground and/or surface water are to be pumped during the construction phase. At least 4 to 5 months should be allowed for completion of the application and issuance of the permit by the MECP.
- For typical ground or surface water volumes being pumped during the construction phase, typically between 50,000 to 400,000 L/day, it is required to register on the Environmental Activity and Sector Registry (EASR). A minimum of two to four weeks should be allotted for completion of the EASR registration and the Water Taking and Discharge Plan to be prepared by a Qualified Person as stipulated under O.Reg. 63/16. If a project qualifies for a PTTW based upon anticipated conditions, an EASR will not be allowed as a temporary dewatering measure while awaiting the MECP review of the PTTW application.

5.0 SANITARY SEWER

There is an existing 825mm diameter sanitary sewer within the Martime Way right-of-way along the frontage of the proposed development. It is proposed to service the East and West towers with individual 200mm services. The East Tower service will connect directly to the existing sewer within the Maritime Way right-of-way. The West tower will be serviced by connecting to the existing private service for the neighboring Timberwalk Retirement Home, which ultimately discharges to the Maritime Way sewer.

Sanitary flows for the proposed development were calculated using criteria from Section 4 of the City of Ottawa Sewer Design Guidelines as follows:

- Residential Average Flow = 280 L/capita/day
- 1 Bed apartment = 1.4 Person/unit
- 2 Bed apartment = 2.1 Person/unit
- Commercial flow = 125 L/seat/day
- Residential Peaking Factor = Harmon Equation (max peaking factor = 4.0)
- Commercial Peaking Factor = 1.0
- Peak Extraneous Flows (Infiltration) = 0.33L/s/ha

The peak sanitary flow including infiltration for the proposed development was calculated to be 11.83 L/s with 6.03 L/s for the West Tower, and 5.80L/s for the East Tower. Detailed sanitary flow calculations are provided in **Appendix B** for reference.

The existing 825 mm diameter sanitary trunk sewer on Maritime Way was designed by J.L. Richards in 1998 to accommodate the development of the KTC-CBD subdivision and upstream lands. At the time of the original design of the trunk sewer, the land parcels were designated for commercial use and the sanitary flows were estimated using 50,000 L/ha/day per Ministry guidelines. Subsequently, land uses for various blocks have changed to include residential use.

The original sanitary sewer design sheet for the 825mm diameter trunk sewer has been revised by J.L. Richards within the JLR Memo and is included in **Appendix C** for reference. The JLR Memo included a change in land use for Block 122 (Claridge lands at 1250 Maritime Way) as well as Blocks 4 and 5 east of Maritime Way and north of the stormwater management facility. J.L. Richards noted an increase in the theoretical design flows at the junction of Teron Road and Campeau Drive from 475.94 L/sec to 480.24 L/sec, with a potential capacity of 838.6 L/s.

The proposed site was designated as part of Block 9 in the above analysis and was assumed to be a commercial site with a flow of 50,000L/ha/day. With an area of 1.23ha which equates to an assumed peaked flow of 1.07L/s. Thus, the proposed development will result in an increase of 10.76L/s when compared to the previous design.

In addition to the proposed development, other developments have since been constructed that will impact the capacity of the downstream system. As such we preformed a review of the downstream system, utilizing the available reports and aerial mapping data under two (2) scenarios. The first scenario utilized the same design criteria as the original JLR design. The second scenario was preformed using the current City of Ottawa Guidelines listed above.

The first analysis using the original design guidelines indicates that several downstream pipes would be surcharging with a maximum of 109% of the available pipe capacity. Although the original design parameters were highly conservative which is why the City of Ottawa has since revised the standards.

Utilizing the current design guidelines indicates that all pipes in the downstream system will have capacity with the worst pipe having a flow of 93% of the pipe capacity. It should be noted that even the current design standards are conservative and are not representative of the real-world flow values.

As, such we do not anticipate any negative impacts due to the proposed development. Refer to **Appendix C** for detailed calculations.

6.0 STORM SEWER AND STORMWATER MANAGEMENT

There is an existing 1650mm diameter storm sewer within the Maritime Way right-of-way fronting the proposed development. There is also an existing 375mm diameter private storm sewer on the adjacent Timber walk Retirement home property to the west, which ultimately discharges to the 1650mm sewer in Maritime Way. It is proposed to service the subject development with connections to both the existing 1650mm Storm Sewer and the private 375mm sewer. In total there are four (4) proposed connections; one (1) connection to the private 375mm sewer and three (3) connections to the existing 1650mm sewer. The connection to the private sewer will be an uncontrolled 300mm diameter foundation drainage connection for the West Tower. The three (3) connections to the 1650mm sewer include: a 300mm diameter foundation drain connection for the East Tower, a controlled 375mm diameter rear yard drainage system, and a controlled 450mm diameter cistern outlet. Refer to the General Plan of Services (120144-GP) for details.

Through correspondence with the City of Ottawa it is understood that the existing hydraulic Grade line (HGL) within the storm sewer fronting the site varies in elevation from 94.30-94.40m. As such it is proposed to place the service connection inverts at or above the existing HGL at the proposed building connections to mitigate potential backflow issues. It is also proposed to provide a pump within the proposed Cistern maximize the available storage while avoiding potential tailwater issues. Refer to **Appendix C** for details.

6.1 Storm Water Management Criteria

Stormwater management (SWM) design criteria for the proposed development were established by the City of Ottawa Sewer Design Guidelines (October 2012), and the JLR Report. The SWM design criteria are as follows:

- Control post-development peak flows up-to and including the 100-year storm event to the allowable release rate. Provide on-site water quantity control for all flow in excess of the allowable release rate. The allowable release rate is to be determined by applying the following parameters to the site area:
 - A runoff coefficient of 0.8 (refer to Dwg 15712-STM in Appendix C)
 - A time of concentration of 20 minutes
 - A 5-year intensity using the City of Ottawa Intensity-Duration-Frequency (IDF) curves
- Minimize the impact on the downstream receiving watercourses by minimizing the potential erosion and volume of sediment entering the watercourses both on a temporary basis (during construction) and on a permanent basis.
- Provide guidelines to ensure that site preparation and construction is in accordance with the current Best Management Practices for Erosion and Sediment Control.

6.2 Existing Site Drainage

As mentioned previously the site is currently undeveloped and contains several fill piles ranging 1-2m in height in the southern portion of the site. The site generally drains towards Maritime Way, with a small amount of drainage directed towards the highway 416 corridor due to obstructions caused by the fill piles.

6.3 Quantity Control

The allowable release rate for the 1.24 ha site was calculated to be 193.4 L/s based on the SWM criteria provided within the JLR report.

Design Storms

The design storms are based on City of Ottawa design storms. Design storms were used for the 5 and 100-year return periods (i.e. storm events).

Model Parameters

Post-development catchments were modelled based on the proposed site plan and grading as shown on **Drawing 120144-SWM**, within **Appendix C**. All the sub-catchments over proposed underground parking areas are assumed to be 100% impervious. The building roofs were assumed to have no depression storage.

The site has been divided into six (6) drainage areas for the post development condition. The drainage areas are as follows:

Area A-01, R-01, R-02

• Flows from the proposed central access, West Tower Roof and East Tower Roof will be conveyed to the existing storm sewer in Maritime Way. These flows will be captured by area drains, and roof drains which will be conveyed to a proposed cistern under the main entrance within the P1 level of underground parking garage. Flows from the cistern to the existing sewer in Maritime Way will be pumped to the proposed service, where the flows will drain by gravity to the existing sewer system. The pump (to be designed by the mechanical consultant) is required to convey flow at 133 L/s. A "stand-by"pump will be provided for emergency and/or maintenance purposes. An emergency back-up power supply will also be provided. The storm service will be equipped with a backflow prevention device to protect the building from any potential sewer back-ups. Storage will be provided for storms up to and including the 100-year event within the cistern. Flows in excess of the 100-year event will overflow through a proposed 150mm overflow pipe, and a vented lid will be provided on the tank for emergencies which will convey flows directly to the Maritime Way right-of-way.

Area A-02:

• Flows from the proposed landscaped area on the southern portion of the property will be captured by a proposed storm system consisting of landscape drains, and catchbasin manholes which will convey flows to the existing Maritime Way sewer system. The proposed system will include a 152mm orifice and will store flows within the underground pipe system. Flows in excess of the 100-year event will overflow though the catch basin lids and be conveyed through the swale system to Maritime Way Right-of-way.

Area D-01:

• The drainage along the frontage of the property will flow uncontrolled to the Maritime Way Right of way

Area D-02:

• A small portion of the landscaped area at the rear of the East Tower will drain uncontrolled to the Highway 416 corridor.

Table **6.1 below** summarizes the flow, storage required, and storage provided for each of the site drainage areas.

Table 6.1 Stormwater Management Summary

				5	Year Storm	n Event	100 Y	ear Storm	n Event
Area ID	Area (ha)	1:5 Year Weighted Cw	Orifice Size & Type	Flow (L/s)	Req Vol (cu.m)	Max. Vol. Provided (cu.m.)	Flow (L/s)	Req Vol (cu.m)	Max. Vol. Provided (cu.m.)
D-01	0.029	0.57	N/A	4.8	N/A	N/A	9.2	N/A	N/A
D-02	0.008	0.20	N/A	0.50	N/A	N/A	1.0	N/A	N/A
A-02	0.290	0.38	152mm Plate	32.0	9.65	27.91	49.6	23.81	27.91
A-01, R-01, R-02	0.910	0.90	Pump	133.0	62.57	294.41	133.0	205.72	294.4
Post-Development Release Rate			170.3			192.8			
Allowable Release Rate			193.4			193.4			

Refer to **Appendix C** for Rational and Modified Method calculations, and **Drawing STM** Post Development Drainage Area Plan.

6.4 Water Quality Control

The proposed site is tributary to the downstream SWM facility which has been designed to provide quantity and quality control for the proposed development as detailed within the JLR Report. Refer to **Appendix C** for excerpts.

6.5 Major Overland Flow Route

A major overland flow route will be provided for storms greater than the 100-year storm event. Stormwater will be directed to the Maritime Way right-of-way. The major overland system is shown on the Grading Plan (drawing 120144-GR).

7.0 WATERMAIN

There is an existing 600mm watermain, and a 200mm local watermain within the Maritime Way right-of-way fronting the development. It is proposed to provide servicing to the proposed development by connecting to the existing 200mm local watermain. Each tower will have its own individual twined services separated by an isolation valve to provide redundancy resulting in a total of four (4) proposed watermain connections.

The proposed water services will be sized to provide both the required domestic water demand and fire flow. Shut-off valves will be located on the proposed services at the property line and a water meter and remote water meter will be provided for each tower. The proposed buildings are to be sprinklered and will be equipped with Siamese connections located near the front entrance of each building, within 45m of a fire hydrant. Refer to the General Plan of Services drawing (120144-GP) for servicing details.

Water demand calculations have been calculated using criteria from Section 4 of the City of Ottawa Water Distribution Guidelines and the Ontario Building Code. The required fire demand was calculated using the Fire Underwriters Survey (FUS) Guidelines. The water demand and fire flow calculations are provided in **Appendix D** for reference. A summary of the water demand and fire flows are provided in **Table 7.1**.

Building	Population	Commercial Area (m²)	Ave. Daily Demand (L/s)	Max. Daily Demand (L/s)	Peak Hour Demand (L/s)	Fire Flow (L/s)
West Tower	528	0	1.71	4.28	9.41	100
East Tower	504	400	1.78	4.30	9.37	117
Total Domestic Demands	1032	400	3.49	8.58	18.78	

Table 7.1: Domestic Water Demand Summary

Detailed calculations are included in **Appendix D.**

The above water demand information was submitted to the City for boundary conditions from the City's water model. These boundary conditions were used for analyzing the performance of the proposed and existing watermain systems for three theoretical conditions:

- 1) High Pressure check under Average Day conditions
- 2) Peak Hour demand
- 3) Maximum Day + Fire Flow demand.

Refer to **Table 7.2** for a summary of the proposed boundary conditions and hydraulic analysis.

Criteria	Head (m)	Pressure ¹ (psi)	Pressure Requirements (psi)	
Connection	n 1- West Tower (20	0mm dia. Maritime W	'ay)	
Max HGL	161.3	94.9	< 80psi	
Min HGL	156.1	87.5	> 40psi	
Max Day + Fire Flow	148.6	76.8	> 20psi	
Connectio	n 2- East Tower (20	0mm dia. Maritime W	ay)	
Max HGL	161.3	95.3	< 80psi	
Min HGL	156.1	87.9	> 40psi	
Max Day + Fire Flow	142.8	69.0	> 20psi	

¹Pressure based on service entry elevation of 94.58m for connection #1 and 94.25m for Connection #2

The hydraulic analysis indicates that the system can provide adequate pressures and flow to meet the domestic and fire flow requirements for the site. As the above pressure are above 80 psi pressure reducing valves will be required for the site. Refer to **Appendix D** for detailed water demand calculations, and City of Ottawa boundary conditions.

8.0 EROSION AND SEDIMENT CONTROL

Temporary erosion and sediment control measures will be implemented on-site during construction in accordance with the Best Management Practices for Erosion and Sediment Control. This includes the following temporary measures:

- Filter socks (catchbasin inserts) will be placed in existing and proposed catchbasins and catchbasin manholes, and will remain in place until vegetation has been established and construction is completed;
- Silt fencing will be placed along the surrounding construction limits;
- Mud mats will be installed at the site entrances;
- Strawbale or rock check dams will be installed in swales and ditches;
- The contractor will be required to perform regular street sweeping and cleaning as required, to suppress dust and to provide safe and clean roadways adjacent to the construction site;

Erosion and sediment control measures should be inspected daily and after every rain event to determine maintenance, repair or replacement requirements. Sediments or granulars that enter site sewers shall be removed immediately by the contractor. These measures will be implemented prior to the commencement of construction and maintained in good order until vegetation has been established. Refer to the Erosion and Sediment Control Plan (drawing 120144-ESC) for additional information.

9.0 CONCLUSIONS

<u>Watermain</u>

The analysis of the existing and proposed watermain network confirms the following:

- The four (4) proposed 200mm dia. watermain services which connect to the existing 200mm dia. watermain in Maritime Way will service the proposed development.
- There are adequate pressures in the existing watermain infrastructure to meet the required domestic demands for the development, and pressure reducing valves will be required.
- There is adequate flow to service the proposed fire protections system.

Sanitary Servicing

The analysis of the existing and proposed sanitary system confirms the following:

• It is anticipated that there is adequate capacity within the existing sanitary infrastructure to service the proposed development based on the information provided in the existing JLR Memo, and the available mapping data.

Stormwater Management

The following provides a summary of the storm sewer and stormwater management system:

- The proposed storm sewer system is to connect to the existing 1650mm diameter storm sewer in Maritime Way.
- Underground storage is be provided within the storm sewer system and underground Cistern.
- Inlet control devices and underground storage have been designed to ensure no static ponding is achieved in the 2-year event.
- Storm flows will be attenuated through the implementation of inlet control devices.
- Parking lots have been graded to ensure that static ponding depths do not exceed 0.30m.
- As per existing conditions a major overland flow route is provided to Maritime Way.
- Quality control of stormwater will be provided in the downstream SWM facility.

Erosion and Sediment control

• Erosion and sediment control measures (i.e. filter fabric, catchbasin inserts, silt fences, etc.) will be implemented prior to construction and are to remain in place until vegetation is established.

Please contact the undersigned should you have questions or require additional information.

NOVATECH

Prepared by:

medeas

Anthony Mestwarp, P.Eng Project Engineer | Land Development


Reviewed by:



Greg MacDonald, P.Eng. Director | Land Development and Public Sector Infrastructure

APPENDIX A

Site Plan



KEY PLAN

GROUND PARKING AREA :		Total =	+/- 1 968 m ² (West Tower) +/- 4 457 m ² = 34.8 % +/- 1 702 m ² = 13.3%	
SITE AREA : SITE COVERAGE :			+/- 12 808 m ² (To be confirmed by surveyo +/- 2 489 m ² (East Tower)	r)
Min Interior Side Yard Setback	no minimum		15.40 m / 15.13 m	
Min FSI	2		+/- 4.53	
Min Corner Side Yard Setback	no minimum		5.24 m	
Min Front Yard Setback	no mininum		7.50 m / 3.09 m	
Max Building Height	67m		+/- 93.5 m	
Min Lot Area	no minimum		+/- 12 808 m²	
Min Lot Width	no minimum		+/- 69.65 m	
PROVISION	REQUIRED		PROVIDED	

+/- 22 475 m²

+/- 19 845 m²

+/- 1 997 m² + /- 1 197 m²

302

28 FLOORS + MECH. / +/- 87.50m

+/- 1 507 m² +/- 1 122 m²

RENTAL - EAST TOWER

	-
PROVIDED BICYCLE STALLS :	
PARKING STALLS :	
DWELLING UNITS :	
NUMBER OF FLOORS AND BUILDING HEIGHT	
COMMUNAL AMENITY AREA :	
PRIVATE AMENITY AREA (G.F.A.) :	
RENTAL FLOORS G.F.A. (2nd to 28th floor) :	
GROUND FLOOR G.F.A. :	
BASEMENT G.F.A. :	
PROPOSED GROSS FLOOR AREA :	

NUMBER OF SUITES REQUIRED TO BE BARRIER-FREE 302 UNITS = **45 UNITS** HAVE TO BE BARRIER-FREE THEY WILL BE DISTRIBUTED BETWEEN THE 28 FLOORS

RENTAL - WEST TOWER

PROPOSED GROSS FLOOR AREA : BASEMENT G.F.A. : GROUND FLOOR G.F.A. : RENTAL FLOORS G.F.A. (2nd to 28th floor) : PRIVATE AMENITY AREA (G.F.A.) : COMMUNAL AMENITY AREA : NUMBER OF FLOORS AND BUILDING HEIGHT DWELLING UNITS : PARKING STALLS : PROVIDED BICYCLE STALLS :


+/- 25 617 m²
+/- 631 m²
+/- 437 m²
+/- 24 548 m²
+/- 1 232 m²
+ /- 1 054 m²
30 FLOORS + MECH. / +/- 93.50m
313
314 (299 INSIDE / 14 VIS. OUTSIDE + 1 VIS. INSIDE)
157 (150 INSIDE / 7 OUTSIDE)

303 (288 INSIDE / 4 VIS. OUTSIDE + 11 VIS. INSIDE) 151 (143 INSIDE / 8 OUTSIDE)

NUMBER OF SUITES REQUIRED TO BE BARRIER-FREE : 313 UNITS = 47 UNITS HAVE TO BE BARRIER-FREE THEY WILL BE DISTRIBUTED BETWEEN THE 30 FLOORS

- FOR EXISTING SITE CONDITIONS, SEE SURVEY PLAN BY ANNIS, O'SULLIVAN, VOLLEBEKK LTD., SUBMITTED SEPARATELY;
- FOR NEW GRADES AND SITE SERVICES, SEE CIVIL ENGINEERING PLAN BY
- NOVATECH ENGINEERING CONSULTANTS, SUBMITTED SEPARATELY; FOR PROPOSED VEGETATION AND LANDSCAPE INFORMATION, SEE LANDSCAPE PLAN BY
- JAMES B. LENNOX & ASSOCIATES, SUBMITTED SEPARATELY.











NOTES GÉNÉRALES General Notes 1 Ces documents d'architecture sont la propriété exclusive de NEUF architect(e)s et ne pourront être utilisés, reproduits ou copiés sans autorisation écrite préalable. / These architectural documents are the exclusive property of NEUF architect(e)s and cannot be used, copied or reproduced without written pre-authorisation 2 Les dimensions apparaissant aux documents devront être vérifiées par l'entrepreneur avant le début des travaux. / All dimensions which appear on the documents must be verify by the contractor before to start the work 3 Veuillez aviser l'architecte de toute dimension erreur et/ou
 divergences entre ces documents et ceux des autres professionnels. The architect must be notified of all errors, omissions and discrepancies between these documents and those of the others professionnals. Les dimensions sur ces documents doivent être lues et non
 mesurées. / The dimensions on these documents must be read and not measured. STRUCTURE Structural Goodeve Structural Inc. 18-77, Auriga Drive, Ottawa ON K2E 7Z7 T 613 226 4558 goodevestructural.ca ARCHITECTURE DE PAYSAGE Landscape Architect James B. Lennox & Associates 3332, Carling Avenue, Ottawa ON K2H 5A8 T 613 722 5168 jbla.ca CIVIL Civil Novatech Eng. Consultants Ltd. 240, Michael Cowpland Drive, Suite 200, Ottawa ON K2M 1P6 T 613 234 9643 novatech-eng.com ARCHITECTES Architect **NEUF architect(e)S** SENCRL 630, boul. René-Lévesque O. 32e étages, Montréal QC H3B 1S6 T 514 847 1117 NEUFarchitectes.com SCEAU / Seal NEUF ARCHITECT(E)S NEUF ARCHITECTES SENCRL CLIENT Client ARIDGE HOMES OUVRAGE Project **1200 MARITIME WAY** (KANATA RENTAL) EMPLACEMENT Location NO PROJET No. OTTAWA 12371.00 NO RÉVISION DATE (aa-mm-jj) A FOR COMMENTS 2020.05.28 B FOR COMMENTS 2020.06.05 FOR COMMENTS 2020.07.23 IN PROGRESS 2020.09.16 SITE PLAN COORDINATION 2020.12.08 SITE PLAN COORDINATION 2020.12.16 G SITE PLAN COORDINATION 2021.02.22 PER TRANSPORTATION COMMENTS 2021.05.18 PER CITY COMMENTS 2021.05.27 PER CITY COMMENTS 2021.11.11 K REVISED SITE PLAN 2022.03.28 L REVISED SITE PLAN - COORDINATION 2022.04.07 M PER CITY COMMENTS 2022.06.03 N FOR COMMENTS 2023.04.13 O FOR COMMENTS 2023.04.17 P SITE PLAN APPROVAL 2023.04.27 VÉRIFIÉ PAR Checked DESSINÉ PAR Drawn by ΡV LH ÉCHELLE Scale DATE (aa mm jj) 1 : 300 🛌 05/28/20 TITRE DU DESSIN Drawing Title 8 SITE PLAN AT **GROUND FLOOR LEVEL** \sim


> NO. DESSIN Dwg Number A203 #18348

RÉVISION Revision

0

APPENDIX B

Sanitary Sewer Servicing Information



scape Architects owpland Drive da K2M 1P6	SANITARY AREA PLAN		
(613) 254-9643 (613) 254-5867	scale 1:750 ⁽	0 10	20 30
vatech-eng.com	APRIL 2023	лов 120144	FIGURE

CITY OF OTTAWA

1200 MARITIME WAY

Novatech Project #: Project Name: 1200 Martime Way Date Prepared: 5/30/2022 Date Revised: 4/28/2023 Input By: Anthony Mestwarp Reviewed By: Greg Macdonald Drawing Reference: 120144-SAN

Legend: PROJECT SPECIFIC INFO USER DESIGN INPUT CUMULATIVE CELL CALCULATED DESIGN CELL OUTPUT

LOCATIO	N									DEMA	ND											DESIGN CAI	PACITY			
						RESIDENTIAL FI	.ow					COMMERCIAL FLOW				EXTRANEOUS F	FLOW				PROPOSE	D SEWER PIP	E SIZING / DE	ESIGN		
AREA	FROM MH	і то мн	1 Bed Apartment	2 Bed Apartment	POPULATIO N (in 1000's)	POPULATION		AVG POPULATION FLOW (L/s)	PEAKED DESIGN POP FLOW (L/s)	COMMERICAL AREA (m²)	CUMULATIVE COMMERICAL AREA (m ²)	DESIGN COMMERICAL FLOW (L/s)	COMMERICAL PEAK FACTOR	PEAKED COMMERCIAL FLOW	Total Area (ha.)	Accum. Area (ha.)	DESIGN EXTRAN. FLOW (L/s)	TOTAL DESIGN FLOW (L/s)	PIPE LENGTH (m)	PIPE SIZE (mm) AND MATERIAL	PIPE ID ACTUAL (m)	ROUGH. (n)	DESIGN GRADE (%)	CAPACITY (L/s)	FULL FLOW VELOCITY (m/s)	Qpeak Design / Qcap
			*									DISSANT FRANCOISE	,					•	•							
WEST	STUB	302	185	128	0.528	0.528	3.37	1.71	5.76	0.000	0.000	0.00	1.00	0.00	0.82	0.82	0.27	6.03	3.7	200 PVC	0.203	0.013	2.00	48.4	1.49	12.5%
			11								CRO	DISSANT FRANCOISE	(SANMH 205)						0	1	1					
EAST	STUB	301	186	116	0.504	0.504	3.38	1.63	5.52	400.000	400.000	0.14	1.00	0.14	0.42	0.42	0.14	5.80	3.6	200 PVC	0.203	0.013		34.2	1.06	17.0%
EAST	301	MAIN			0.000	0.504	3.38	1.63	5.52	-	400.000	0.14	1.00	0.14	0.00	0.42	0.14	5.80	15.4	200 PVC	0.203	0.013	1.00	34.2	1.06	17.0%
TOTAL			371	244	1.032	1.032				400.000	400.000				1.24				CAPACITY EQUAT							
Design Parameters: 1. Residential Flows -1 Bed Apartment -2 Bed Apartment 2. Commercial Flow -Office 3. q Avg capita flow 4. M = Harmon Formula (maximum 5. K = 6. Commercial Peak Factor -area < 20% of development -area < 20% of development 8. Extraneous Flows =	2 1: 2: of 4.0) 0 1 1	.4 Person/ Ur .1 Person/ Ur 25 L/seat ³ /day 30 L/per/day .8 .5 .0 33 L/sec/ha	iit	(Assume 1 sea	t/4m²)															2/3)So^(1/2) n = Manning c: A = Flow area i R = Wetter So So = Pipe Slop	oefficient of rou (m ²) imenter (m)	ghness (0.013	9)			



LOCAT	ION						RESIDEN	TIAL						COMMER	CIAL/INSTI	UTIONAL	PLUGGE	ED FLOW	R	+ C			PROP	OSED SEWE	R	
				NUMBER OF UNIT	rs			INDIV	IDUAL	СОМОІ	LATIVE								PEAK	PEAK						
STREET	FROM MH	то мн	Houses	Extended Care		Hotel/Ap	ot	POPUL.	AREA	POPUL.	AREA	PEAK FACTOR (M)	POPUL. FLOW L/S	ACTUAL AREA ha	CUMM AREA ha	COMM FLOW I/s	FLOW I/s	COMM FLOW I/s	EXTR. FLOW	DESIGN FLOW	LENGTH (m)	PIPE SIZE (mm)	SLOPE %	CAPACITY (L/s)	FULL FLOW VELOCITY (m/s)	RATIO (Q/Qfull)
			Singles Stacks Towns	No. Units Act Pop	No. Units	Act. Pop	Equ. Pop	People	ha	People	ha								l/s	L/S						
Robinson - 1996	Upstream	7A						2588	28.38	2588	28.38	3.496	36.65	20.370	20.370	17.68	162.69	162.69	14.02	231.04						
1250 Maritime Way	Blk 122	7A						377	0.89	377	0.89	4.000	6.11	0.005	0.005	0.004	0.83	0.83	0.25	7.19						
1200 Maritime Way	Blk 126	7A																	0.000	0.00						
Maritime Way	7A	507								2965	29.27	3.447	41.40		20.375	17.687		163.520	14.266	236.87	81.9	825	0.14	537.091	1.00	44%
Maritime Way	507	506			125	225	174	174	1.02	3139	30.29	3.426	43.56	4.910	25.285	21.949		163.520	15.92	244.95	119.3	825	0.12	497.249	0.93	49%
Cordillera Street	534	533			125	207	207	207	0.58	207	0.58	4.000	3.35	0.550	0.550	0.477			0.32	4.16	66.6	200	1.65	42.130	1.36	10%
Can. Shield Avenue	533	532								207	0.58	4.000	3.35		0.550	0.477			0.32	4.16	69.9	200	1.20	35.929	1.16	12%
Can. Shield Avenue	532	531							0.33	207	0.91	4.000	3.35		0.550	0.477			0.41	4.24	69.9	200	1.20	35.929	1.16	12%
Great Lakes Avenue	536	531			100	180	139	139	0.78	139	0.78	4.000	2.25	0.040	0.040	0.035	0.300	0.300	0.23	2.82	60.0	200	2.40	50.811	1.63	6%
Great Lakes Avenue	531	530								346	1.69	4.000	5.61		0.590	0.512		0.300	0.644	7.06	80.8	200	3.75	63.514	2.04	11%
Great Lakes Avenue	530	506A								346	1.69	4.000	5.61		0.590	0.512		0.300	0.644	7.06	85.2	200	1.40	38.808	1.25	18%
Great Lakes Avenue	506A	506							0.38	346	2.07	4.000	5.61		0.590	0.512		0.300	0.740	7.16	4.9	200	1.40	38.808	1.25	18%
Maritime Way	506	505			176	316.8	269	269	0.57	3754	32.93	3.358	51.06		25.875	22.461		163.820	16.818	254.16	111.0	825	0.12	497.249	0.94	51%
Maritime Way	505	504			146	262.8	230	230	0.56	3984	33.49	3.335	53.82	1.750	27.625	23.980		163.820	17.479	259.10	114.4	825	0.11	476.080	0.90	54%
Maritime Way	504	501							0.27	3984	33.76	3.335	53.82		27.625	23.980		163.820	17.556	259.18	29.9	825	0.11	476.080	0.90	54%
Can. Shield Avenue	542	541			176	316.8	269	269	0.74	269	0.74	4.000	4.36						0.212	4.57	71.3	200	2.20	48.648	1.56	9%
Can. Shield Avenue	541	540			154	272.2	232	232	0.51	501	1.25	3.974	8.06	1.360	1.360	1.181			0.731	9.98	77.7	200	0.90	31.115	1.00	32%
	Block 3	540		208 333			428	428	1.02	428	1.02	4.000	6.94						0.286	7.22	12.0	200	0.60	25.406	0.82	28%
Can. Shield Avenue	540	512							0.3	929	2.57	3.820	14.38		1.360	1.181			1.100	16.66	82.6	200	0.71	27.636	0.89	60%
-																										
Maritime Way Maritime Way (Blk 4)	514 513	513 512			144	271	271	271	1.12	271	1.12	4.000	4.39						0.314	4.70	51.2 51.9	200 200	2.14 2.28	47.980 49.525	1.54 1.59	<u>0%</u> 9%
• • •															4 200	4 404										
Maritime Way	512	511					58	58	0.73	1258	4.42	3.734	19.03		1.360	1.181			1.618	21.83	49.3	200	3.12	57.934	1.86	38%
	Block 5	511			154	301	301	301	0.92	301	0.92	4.000	4.88						0.258	5.13	12.2	200	2.00	46.384	1.49	11%
Maritime Way	511	510								1559	5.34	3.667	23.16		1.360	1.181			1.876	26.22	38.4	200	1.70	42.764	1.38	61%
Maritime Way	510	501								1559	5.34	3.667	23.16		1.360	1.181			1.876	26.22	11.3	200	2.28	49.525	1.59	53%
Trunk Easement	501	500				L				5543	39.1	3.203	71.93		28.985	25.161		163.820	19.425	280.33	129.0	825	0.10	453.925	0.86	62%
Trunk Easement	500	94								5543	39.1	3.203	71.93		28.985	25.161		163.820	19.425	280.33						
A	90	92	35					95	0.80	95	0.80	4.000	1.54						0.228	1.77	120.0	250	0.60	46.063	0.95	4%
	92	94	12					32	1.19	127	1.99	4.000	2.06						0.568	2.63	103.0	250	2.20	88.205	1.82	3%
	94	95								5670	41.09	3.194	73.36		28.985	25.161		163.820	19.992	282.33	17.5	825	0.12	497.249	0.94	57%
	95	89	10					27	0.52	5697	41.61	3.192	73.67		28.985	25.161		163.820	20.141	282.79	66.6	825	0.12	497.249	0.94	57%



LOCAT	ION						RESIDEN	ITIAL						COMMER	CIAL/INSTIT	TUTIONAL	PLUGGE	ED FLOW	R	+ C			PROP	OSED SEWE	R	
					NUMBER OF UNI	TS		INDI	/IDUAL	СОМО	LATIVE								PEAK EXTR.	PEAK DESIGN						
STREET	FROM MH	то мн	Hou	ses	Extended Care		Hotel/Apt	POPUL.	AREA	POPUL.	AREA	PEAK FACTOR (M)	POPUL. FLOW L/S	ACTUAL AREA ha	CUMM AREA ha	COMM FLOW I/s	FLOW I/s	COMM FLOW I/s	FLOW	FLOW	LENGTH (m)	PIPE SIZE (mm)	SLOPE %	CAPACITY (L/s)	FULL FLOW VELOCITY (m/s)	RATIO (Q/Qfull)
			Singles Sta	icks Towns	No. Units Act Pop	No. Units	Act. Pop Equ. Pop	People	ha	People	ha								l/s	L/S						
В	85	87	19					65	1.19	65	1.19	4.000	1.05						0.340	1.39	116.9	250	0.40	37.611	0.77	4%
	87	89		24				65	0.82	130	2.01	4.000	2.11						0.573	2.68	116.7	250	1.41	70.614	1.45	4%
	80	84		10				22	0.25	5950	42.07	2 101	75.40		29.095	25 161		162 820	20 702	295.26	70.0	925	0.12	407.240	0.04	570/
Α	89	64		12				32	0.35	5859	43.97	3.181	75.49		28.985	25.161		163.820	20.792	285.26	79.0	825	0.12	497.249	0.94	57%
С	80	82	19					65	1.08	65	1.08	4.000	1.05						0.308	1.36	120.0	250	0.40	37.611	0.77	4%
	82	84		25				67	0.83	132	1.91	4.000	2.14						0.544	2.68	118.5	250	1.20	65.143	1.34	4%
A	84	79		14				38	0.54	6029	46.42	3.169	77.39		28.985	25.161		163.820	21.490	287.86	79.0	825	0.12	497.249	0.94	58%
D	75 76	76 77		17 20				46 54	0.37	46 100	0.37	4.000	0.75						0.105	0.85	57.0 78.4	250 250	0.40	37.611 37.611	0.77	2%
	70	79		13				35	0.29	135	1.29	4.000	2.19						0.368	2.56	117.7	250	0.40	53.521	1.10	<u>5%</u> 5%
Park Easement	79 67	67 66		6				16	0.98	6164 6180	48.69 49.02	3.160	78.89 79.07		28.985 28.985	25.161 25.161		163.820 163.820	22.099 22.192	289.97 290.25	55.0 70.0	825 825	0.12	497.249 497.249	0.94	58%
	07	00		0				10	0.55	0100	49.02	3.159	79.07		20.900	23.101		103.020	22.192	290.23	70.0	025	0.12	437.249	0.94	58%
BELLROCK DRIVE	70	73	1	2 14				70	2.56	70	2.56	4.000	1.13						0.728	1.86	87.2	250	0.40	37.611	0.77	5%
EASEMENT	73 74	74		12				32	0.54	102	3.1	4.000	1.65						0.882	2.53	80.3	250	0.40	37.611	0.77	7%
CAMBRAY LANE	62	62 66		25				68	0.31	102 170	3.41 3.89	4.000 4.000	1.65 2.75						0.970	2.62 3.86	39.9 100.5	250 250	0.40	37.611 37.611	0.77	7% 10%
																										1070
BISHOPS MILLS WAY	66	65		9				24	0.53	6374	53.44	3.146	81.22		28.985	25.161		163.820	23.450	293.65	62.0	825	0.12	497.249	0.94	59%
SOUTH OF HWY 7	EX.	65						7792	191.6	7792	191.6	3.061	96.63				37.720	37.720	53.648	188.00	50.2	900	0.11	600.412	0.95	31%
BISHOPS MILLS WAY	65	64		2				5		14171	245.04	2.803	160.91		28.985	25.161		201.540	77.083	464.70	17.0	900	0.11	600.412	0.95	77%
EDENVALE DRIVE	59	60		8				22	0.50	22	0.50	4.000	0.36						0.141	0.50	77.0	200	1.40	38.808	1.25	1%
KETTLEBY STREET	60	61		22				59	0.62	81	1.12	4.000	1.31						0.315	1.63	103.6	250	0.40	37.611	0.77	4%
CAMBRAY LANE	58	61		5				14	0.41	14	0.41	4.000	0.23						0.115	0.34	74.5	200	0.70	27.441	0.88	1%
KETTLEBY STREET	61	64		25				68	0.42	163	1.95	4.000	2.64						0.549	3.19	105.0	250	0.90	56.416	1.16	6%
BISHOPS MILLS WAY	64	63		3				8		14342	246.99	2.798	162.55		28.985	25.161		201.540	77.632	466.88	13.0	900	0.11	600.412	0.95	78%
	63	57		10				27	0.68	14369	247.67	2.797	162.81		28.985	25.161		201.540	77.823	467.33	64.9	900	0.11	600.412	0.95	78%
TER. BUNGALOW Ph. 2	51	53		8				130	0.94	130	0.94	4.000	2.11						0.264	2.37	122.3	200	0.70	27.441	0.88	9%
	53 54	54 55	4	4				11	0.27	141 141	0.94	4.000 4.000	2.28 2.28						0.264	2.55	13.6 36.7	200 200	0.70	27.441 27.441	0.88	9%
BISHOPS MILLS WAY	54 55	55 56	11					37	0.27	141	1.21 2.02	4.000	2.28						0.340	2.63 3.45	107.1	200	0.70	37.611	0.88	<u>10%</u> 9%
	56	57	7	12				56	0.65	234	2.67	4.000	3.79						0.751	4.54	101.5	250	0.60	46.063	0.95	10%
PARK	57	34		1				3	0.37	14606	250.71	2.790	165.07		28.985	25.161		201.540	78.678	470.45	53.5	900	0.11	600.412	0.95	700/
	34	33		3				8	0.37	14608	250.71	2.790	165.15		28.985	25.161		201.540		470.43	50.3	900	0.11	600.412	0.95	78% 78%



LOCATI	ION							RESIDEN	TIAL						COMMER	RCIAL/INSTI	TUTIONAL	PLUGG	ED FLOW	R	+ C			PROP	OSED SEWE	R	
						ITS			INDIV	/IDUAL	СОМОГ	ATIVE	PEAK	POPUL.	ACTUAL	симм	сомм		сомм	PEAK EXTR.	PEAK DESIGN					FULL FLOW	
STREET	FROM MH	ТО МН		Houses	Extended Care		Hotel/A	pt	POPUL. People	AREA ha	POPUL. People	AREA ha	FACTOR (M)	FLOW L/S	AREA	AREA	FLOW I/s	FLOW I/s	FLOW I/s	FLOW	FLOW	LENGTH (m)	PIPE SIZE (mm)	SLOPE %	CAPACITY (L/s)	VELOCITY (m/s)	RATIO (Q/Qfull)
			Singles	Stacks Town	s No. Units Act Po	p No. Units	Act. Pop	Equ. Pop												l/s	L/S						
HAWSTONE	43	44		22					59	1.19	59	1.19	4.000	0.96						0.335	1.29	51.0	250	1.00	59.468	1.22	2%
	44	45		8					22	0.09	81	1.28	4.000	1.31						0.360	1.67	29.0	250	0.50	42.050	0.87	4%
	45	35	-							0.06	81	1.34	4.000	1.31						0.377	1.69	39.8	250	0.50	42.050	0.87	4%
BIRKENDALE DRIVE	35 36	36 37	7 13						24 44	1.18 0.79	105 149	2.52 3.31	4.000	1.70 2.41						0.709	2.41 3.35	93.2 77.1	250 250	0.37	36.173 36.173	0.74	7%
	37	33	2	3					15	0.75	143	3.31	4.000	2.66						0.931	3.59	17.9	250	0.40	37.611	0.77	9% 10%
BIRKENDALE DRIVE	33	32		10					27	0.56	14805	254.58	2.784	166.96		28.985	25.161		201.540	79.767	473.43	72.7	900	0.11	600.412	0.95	79%
TEESWATER STREET	30	31		16					43	0.66	43	0.66	4.000	0.70						0.186	0.88	75.1	250	0.40	37.611	0.77	2%
	31	32		19					51	0.41	94	1.07	4.000	1.52						0.301	1.82	77.9	250	0.40	37.611	0.77	5%
BIRKENDALE STREET	32	18		6					16	0.37	14915	256.02	2.781	168.01		28.985	25.161		201.540	80.172	474.88	44.4	900	0.11	600.412	0.95	79%
	18	16		4					11		14926	256.02	2.780	168.11		28.985	25.161		201.540	80.172	474.99	44.4	900	0.11	600.412	0.95	79%
COMMERCIAL PLAZA	19	17											4.000	0.00	0.520	0.520	0.451			0.146	0.60	26.5	150	0.90	14.448	0.83	4%
COLCHESTER SQUARE	17	16								0.10		0.10	4.000	0.00		0.520	0.451			0.174	0.63	33.2	250	0.40	37.611	0.77	2%
COLCHESTER SQUARE	16	15		10					27	0.56	14953	256.68	2.780	168.37		29.505	25.612		201.540	80.504	476.03	66.0	900	0.11	600.412	0.95	70%
	15	14A		2					5		14958	256.68	2.779	168.42		29.505	25.612		201.540	80.504	476.07	25.8	900	0.11	600.412	0.95	79% 79%
ELSINORE LANE	39	28		32					86	0.53	86	0.53	4.000	1.39						0.149	1.54	56.7	250	1.00	59.468	1.22	3%
	28 24	24 23		18 12					49 32	1.47 0.14	135 167	2.00 2.14	4.000	2.19						0.563	2.75 3.31	43.0 34.0	250 250	0.40	37.611 37.611	0.77	7%
ELSINORE LANE	24	306		8					22	0.14	189	2.14	4.000	3.06						0.602	3.73	48.8	250	0.40	39.446	0.81	<u>9%</u> 9%
ENDENVALE DRIVE	306	14-A								0.45	189	2.83	4.000	3.06						0.796	3.86	46.4	250	0.49	41.627	0.86	9%
COLCHESTER SQUARE	14-A	14									15147	259.51	2.774	170.21		29.505	25.612		201.540	81.300	478.66	14.7	900	0.11	600.412	0.95	
															0.500												80%
	Church	14													0.520	0.520	0.451			0.146	0.60	35.0	150	1.00	15.229	0.87	4%
COLCHESTER SQUARE	14	11		4					11	0.16	15158	259.67	2.774	170.31		30.025	26.063		201.540	81.491	479.41	72.6	900	0.11	600.412	0.95	80%
TERON	11	10									15158	259.67	2.774	170.31		30.025	26.063		201.540	81.491	479.41	29.6	900	0.11	600.412	0.95	80%
	10	EX.								0.25	15158	259.92	2.774	170.31		30.025	26.063	<u> </u>	201.540	81.562	479.48	72.3	900	0.11	600.412	0.95	80%
TERON	0.P.P.	EX.																0.780	0.780		0.78	100) FORCEMAI	N			
TERON	EX.	EX. 2									15158	259.92	2.774	170.31		30.025	26.063		202.320	81.562	480.26	9.400	680.000	0.960	839.974	2.34	57%
Notes:																											



LOCAT	ION									RESIDEN	FIAL						COMMER	RCIAL/INSTI	TUTIONAL	PLUGGE	D FLOW	R	+ C
					NU	MBER		s			INDIV	IDUAL	CUMUL	ATIVE								PEAK	PEAK
STREET	FROM MH	то мн		Houses	E	Extende	ed Care		Hotel/A		POPUL.	AREA	POPUL.	AREA	PEAK FACTOR (M)	POPUL. FLOW L/S	ACTUAL AREA ha	CUMM AREA ha	COMM FLOW I/s	FLOW I/s	COMM FLOW I/s	EXTR. FLOW	DESIGN FLOW
			Singles	Stacks		No. Units	Act Pop	No. Units	Act. Pop	Equ. Pop	People	ha	People	ha								l/s	L/S
1) As per Kanata Town Ce	entre Sanitar	y Trunk S	ewer Study	revised N	March 27, 1	996 by	Robinsor	n Consult	ants Inc.														
2) Park or open space are	ea.																						
Equivalent population b	ase on 208 i	ooms and	l 20 staff m	embers.																			
 As per Kanata Town Ce Park or open space are 	entre Sanitar ea. pase on 208 r	y Trunk S rooms and	Singles ewer Study	Stacks revised M nembers.	Towns	No. Units 996 by	Act Pop Robinsor	No. Units n Consult	Act. Pop ants Inc.	Equ. Pop	People							-					

4) Allowance for an ultimate flow of 188 l/s to provide flexibility in future development as per Kanata Town Centre Sanitary Trunk Study.

5) Additional flow associated with hotel amendities including swimming pool with bathrooms and laudry as per design calculations for Block 1 provided by WSP (October 2016).

6) Additional flow associated with overall amenities including beauty salon, staff, dining and laundry as per design calculations for 1250 Maritime Way (Timberwalk Retirement Home) provided by Novatech (July 31, 2017).

Design Parameters:

1) Q(p) = (PxqxM/86,400)			Un	its		
2) Q(d) = Q(p) + Q(e)			Sin	ngle	3.4	pers/unit
Definitions:			Τον	wn	2.7	pers/unit
P = Population			Hot	tel/ Apartmentt	1.8	pers/unit
q = Average per capita flow = 350 L/p	erson/day		Ret	tirement Home	1.6	pers/unit
M = Residential Peaking Factor (Harm	non Formu	a from section 4.4.1 of the City Sewer Design Guidelines):				
	M = 1+[1	4/(4+Pop/1000)^1/2]*1 - (Maximum of 4.0)	Co	mmercial Flow	50000	L/ha/day
			Co	mmercial Peak Factor	1.	5
Q(d) = Design Flow (L/sec)						
Q(p) = Population Flow (L/sec)						
Q(r) = Commercial Flow (L/sec)						
Q(e) = Extraneous Flow (L/sec)	0.28	l/s/ha				



				CONS	ULTAN	TSLTD.
+ C			PROPO	DSED SEWEI	र	
PEAK DESIGN FLOW	LENGTH (m)	PIPE SIZE (mm)	SLOPE %	CAPACITY (L/s)	FULL FLOW VELOCITY (m/s)	RATIO (Q/Qfull)
L/S						
			0 Maritin SEWER I	ne Way DESIGN SHE	ET	
Date		[]	Janu	ary 27, 2021		
Design	GMAC					
Job 120		wg. Referenc 120144- SAN		Checked	I and Stamped	d:

1200 Maritime Way SANITARY SEWER JOB# 120144	DESIGN SH	IEET OF	DOWNS	TREAM	SEWE	RS - OLD STAI	NDARD	S																			ENG		RING
LOCA	ATION								RESIDEN	TIAL						COMME	RCIAL/INSTI	ITUTIONAL	PLUGG	ED FLOW	R	+ C			PR	OPOSED	SEWER		
					I	NUMBER OF UNI	rs			INDIV	IDUAL	СОМО	LATIVE								PEAK EXTR.	PEAK DESIGN							
STREET	FROM MH	то мн	Singles	Houses	Towns	No. Act Pop	No.	Hotel/A	ot Equ. Pop	POPUL. People	AREA ha	POPUL. People	AREA ha	PEAK FACTOR (M)	POPUL. FLOW L/S	ACTUAL AREA ha	CUMM AREA ha	COMM FLOW I/s	FLOW I/s	COMM FLOW I/s	FLOW	FLOW	LENGTH (m)	PIPE SIZE (mm)	ACTUAL PIPE SIZE (mm)	SLOPE %	CAPACITY (L/s)	, FULL FLOW VELOCITY (m/s)	RATIO (Q/Qfull)
Robinson - 1996	Upstream	7A				Units	Units	Рор		2588	28.38	2588	28.38	3.496	36.65	20.370	20.370	17.68	162.69	162.69	13.65	230.67							
1250 Maritime Way	Blk 122	7A								377	0.89	377	0.89	4.000	6.11	0.005	0.005	0.004	0.83	0.83	0.25	7.19							
1200 Maritime Way	Blk 126	7A					633		1058	1058	1.28	1058	1.28	3.784	16.22	0.040	0.040	0.010			0.37	16.60							
Maritime Way Maritime Way	7A 507	507 506					125	225	174	174	1.02	4023 4197	30.55 31.57	3.331 3.315	54.29 56.35	3.680	20.415 24.095	17.721 20.916		163.520 163.520	14.27 15.59	249.80 256.38	81.9 119.3	825 825	838 838	0.14	560.313 518.749	1.02 0.94	45% 49%
Cordillera Street	534	533					125	207	207	207	0.58	207	0.58	4.000	3.35	0.550	0.550	0.477			0.32	4.15	66.6	200	203	1.65	43.952	1.37	9%
Can. Shield Avenue Can. Shield Avenue	533 532	532 531									0.33	207 207	0.58	4.000	3.35 3.35		0.550 0.550	0.477			0.32	4.15 4.24	69.9 69.9	200 200	203 203	1.20 1.20	37.482 37.482	1.17 1.17	11%
San. Shield Avenue	002	001									0.00	207	0.01	4.000	0.00		0.000	0.477			0.41	7.24	00.0	200	200	1.20	07.402	1.17	11%
Great Lakes Avenue	536	531					100	180	139	139	0.78	139	0.78	4.000	2.25	0.040	0.040	0.035	0.300	0.300	0.23	2.82	60.0	200	203	2.40	53.008	1.65	5%
Great Lakes Avenue	531	530										346	1.69	4.000	5.61		0.590	0.512		0.300	0.64	7.06	80.8	200	203	3.75	66.260	2.06	11%
Great Lakes Avenue Great Lakes Avenue	530 506A	506A 506									0.38	346 346	1.69 2.07	4.000	5.61 5.61		0.590 0.590	0.512		0.300	0.64	7.06 7.16	85.2 4.9	200 200	203 203	1.40 1.40	40.486 40.486	1.26 1.26	17% 18%
Great Lakes Avenue	500A	500									0.50	540	2.07	4.000	5.01		0.330	0.512		0.300	0.74	7.10	4.5	200	203	1.40	40.400	1.20	1070
Maritime Way	506	505					176	316.8	269	269	0.57	4812	34.21	3.260	63.55	4 750	24.685	21.428		163.820	16.49	265.29	111.0	825	838	0.12	518.749	0.95	51%
Maritime Way Maritime Way	505 504	504 501					146	262.8	230	230	0.56	5042 5042	34.77 35.04	3.242 3.242	66.21 66.21	1.750	26.435 26.435	22.947 22.947		163.820 163.820	17.14 17.21	270.11 270.19	114.4 29.9	825 825	838 838	0.11	496.665 496.665	0.91	54% 54%
							170																						
Can. Shield Avenue Can. Shield Avenue	542 541	541 540					176 154	316.8 272.2	269 232	269 232	0.74 0.51	269 501	0.74	4.000 3.974	4.36 8.06	1.360	1.360	1.181			0.21	4.57 9.98	71.3	200 200	203 203	2.20 0.90	50.751 32.461	1.58 1.01	9% 31%
		540							400	400	4.00	100	1.00	4 000								7.00	40.0				00.504		
	Block 3	540				208 333			428	428	1.02	428	1.02	4.000	6.94						0.29	7.22	12.0	200	203	0.60	26.504	0.83	27%
Can. Shield Avenue	540	512									0.3	929	2.57	3.820	14.38		1.360	1.181			1.10	16.66	82.6	200	203	0.71	28.831	0.90	58%
Maritime Way	514	513																					51.2	200	203	2.14	50.055	1.56	0%
Maritime Way (Blk 4)	513	512					144	271	271	271	1.12	271	1.12	4.000	4.39						0.31	4.70	51.9	200	203	2.28	51.666	1.61	9%
Maritime Way	512	511							58	58	0.73	1258	4.42	3.734	19.03		1.360	1.181			1.62	21.83	49.3	200	203	3.12	60.439	1.88	36%
	Block 5	511					154	301	301	301	0.92	301	0.92	4.000	4.88						0.26	5.13	12.2	200	203	2.00	48.390	1.51	11%
Maritime Way	511	510										1559	5.34	3.667	23.16		1.360	1.181			1.88	26.22	38.4	200	203	1.70	44.613	1.39	59%
Maritime Way	510	501										1559	5.34	3.667	23.16		1.360	1.181			1.88	26.22	11.3	200	203	2.28	51.666	1.61	51%
Trunk Easement	501	500										6601	40.38	3.131	83.73		27.795	24.128		163.820	19.09	290.76	129.0	825	838	0.10	473.551	0.87	61%
Trunk Easement	500	94										6601	40.38	3.131	83.73		27.795	24.128		163.820	19.09	290.76							0170
A	90	92			35			-		95	0.80	95	0.80	4.000	1.54						0.22	1.76	120.0	250	254	0.60	48.055	0.96	4%
	92	94			12					32	1.19	127	1.99	4.000	2.06						0.22	2.62	103.0	250	254	2.20	92.018	1.84	4% 3%
	94	95										6728	42.37	3.123	85.12		27.795	24.128		163.820	19.65	292.72	17.5	825	838	0.12	518.749	0.95	EC0/
	94	95 89		+	10					27	0.52	6755	42.37	3.123	85.12		27.795	24.128		163.820	19.65	292.72	66.6	825	838	0.12		0.95	56% 57%
	1																												

1200 Maritime Way SANITARY SEWER DI JOB# 120144	ESIGN SH	IEET OF	DOWNSTREAM	I SEWER	RS - OLD STANDARD	S																			
В	85	87	19			65	1.19	65	1.19	4.000	1.05						0.33	1.39	116.9	250	254	0.40	39.237	0.78	4%
	87	89		24		65	0.82	130	2.01	4.000	2.11						0.56	2.67	116.7	250	254	1.41	73.667	1.47	4%
A	89	84		12		32	0.35	6917	45.25	3.112	87.19		27.795	24.128		163.820	20.45	295.59	79.0	825	838	0.12	518.749	0.95	57%
С	00	00	10			05	4.00	05	1.00	4 000	4.05						0.20	4.00	100.0	250	054	0.40	20.007	0.70	
C	80 82	82 84	19	25		65	1.08 0.83	65 132	1.08 1.91	4.000 4.000	1.05 2.14						0.30	1.36 2.67	120.0 118.5	250 250	254 254	0.40	39.237 67.960	0.78	3% 4%
	02	04		25		07	0.00	132	1.31	4.000	2.14						0.55	2.07	110.5	230	2.04	1.20	07.300	1.50	4 70
А	84	79		14		38	0.54	7087	47.70	3.101	89.04		27.795	24.128		163.820	21.14	298.12	79.0	825	838	0.12	518.749	0.95	57%
D	75	76		17		46	0.37	46	0.37	4.000	0.75						0.10	0.85	57.0	250	254	0.40	39.237	0.78	2%
	76	77		20		54	0.29	100	0.66	4.000	1.62						0.18	1.81	78.4	250	254	0.40	39.237	0.78	5%
	77	79		13		35	0.63	135	1.29	4.000	2.19						0.36	2.55	117.7	250	254	0.81	55.835	1.11	5%
Dark Factoriant	70	67					0.00	7000	40.07	2 002	00.50		07 705	24.400		162.000	01 77	200.00	<i>EE</i> 0	005	000	0.40	E10 740	0.05	500/
Park Easement	79 67	67 66		6		16	0.98	7222 7238	49.97 50.30	3.093 3.093	90.50 90.68		27.795 27.795	24.128 24.128		163.820 163.820	21.77 21.87	300.22 300.49	55.0 70.0	825 825	838 838	0.12	518.749 518.749	0.95	58% 58%
		00		0		10	0.00	1200	50.50	0.000	50.00		21.135	27.120		100.020	21.07	000.49	70.0	020	000	0.12	010.749	0.30	38%
BELLROCK DRIVE	70	73	12	14		70	2.56	70	2.56	4.000	1.13						0.72	1.85	87.2	250	254	0.40	39.237	0.78	5%
	73	74		12		32	0.54	102	3.1	4.000	1.65			1			0.87	2.52	80.3	250	254	0.40	39.237	0.78	6%
EASEMENT	74	62					0.31	102	3.41	4.000	1.65						0.95	2.61	39.9	250	254	0.40	39.237	0.78	7%
CAMBRAY LANE	62	66		25		68	0.48	170	3.89	4.000	2.75						1.09	3.84	100.5	250	254	0.40	39.237	0.78	10%
BISHOPS MILLS WAY	66	65		9		24	0.53	7432	54.72	3.081	92.77		27.795	24.128		163.820	23.10	303.82	62.0	825	838	0.12	518.749	0.95	59%
SOUTH OF HWY 7	EX.	65				7792	191.6	7792	191.6	3.061	96.63				37.720	37.720	53.65	188.00	50.2	900	914	0.11	626.373	0.96	0.004
300TH OF HW17	EA.	05				1192	191.0	1192	191.0	3.001	90.03				31.120	31.120	55.05	100.00	50.2	900	914	0.11	020.373	0.90	30%
BISHOPS MILLS WAY	65	64		2		5		15229	246.32	2.772	170.98		27.795	24.128		201.540	76.75	473.40	17.0	900	914	0.11	626.373	0.96	76%
EDENVALE DRIVE	59	60		8		22	0.50	22	0.50	4.000	0.36						0.14	0.50	77.0	200	203	1.40	40.486	1.26	1%
KETTLEBY STREET	60	61		22		59	0.62	81	1.12	4.000	1.31						0.31	1.63	103.6	250	254	0.40	39.237	0.78	4%
CAMBRAY LANE	58	61		5		14	0.41	14	0.41	4.000	0.23						0.11	0.34	74.5	200	203	0.70	28.628	0.89	1%
KETTLEBY STREET	61	64		25		68	0.42	163	1.95	4.000	2.64						0.55	3.19	105.0	250	254	0.90	58.855	1.17	5%
NETTEEDT OTNEET	01	04		20		00	0.42	100	1.00	4.000	2.04						0.00	0.10	100.0	200	204	0.00	00.000	1.17	576
BISHOPS MILLS WAY	64	63		3		8		15400	248.27	2.767	172.60		27.795	24.128		201.540	77.30	475.57	13.0	900	914	0.11	626.373	0.96	76%
	63	57		10		27	0.68	15427	248.95	2.766	172.85		27.795	24.128		201.540	77.49	476.01	64.9	900	914	0.11	626.373	0.96	76%
TER. BUNGALOW Ph. 2	51	53	48			130	0.94	130	0.94	4.000	2.11						0.26	2.37	122.3	200	203	0.70	28.628	0.89	8%
	53	54	4			11		141	0.94	4.000	2.28						0.26	2.55	13.6	200	203	0.70	28.628	0.89	9%
	54	55					0.27	141	1.21	4.000	2.28						0.34	2.62	36.7	200	203	0.70	28.628	0.89	9%
BISHOPS MILLS WAY	55	56	11			37	0.81	178	2.02	4.000	2.88						0.57	3.45	107.1	250	254	0.40	39.237	0.78	9%
	56	57	7	12		56	0.65	234	2.67	4.000	3.79						0.75	4.54	101.5	250	254	0.60	48.055	0.96	9%
DADK	E7	24		4			0.97	15604	254.00	0.750	175.00	-	27 705	24.400		201 5 40	70.24	470.00	ED E	000	014	0.14	606 070	0.00	
PARK	57 34	34 33		1		3	0.37	15664 15672	251.99 251.99	2.759 2.759	175.09 175.16		27.795 27.795	24.128 24.128		201.540 201.540	78.34 78.34	479.09 479.17	53.5 50.3	900 900	914 914	0.11	626.373 626.373	0.96	76%
	- 04	55		5		0 		13072	201.99	2.108	173.10		21.195	24.120		201.040	10.04	413.11	50.5	300	514	0.11	020.373	0.30	76%
HAWSTONE	43	44	22			59	1.19	59	1.19	4.000	0.96						0.33	1.29	51.0	250	254	1.00	62.039	1.24	2%
-	44	45	8			22	0.09	81	1.28	4.000	1.31						0.36	1.67	29.0	250	254	0.50	43.868	0.87	4%
EDENVALE	45	35					0.06	81	1.34	4.000	1.31						0.38	1.69	39.8	250	254	0.50	43.868	0.87	4%
BIRKENDALE DRIVE	35	36	7			24	1.18	105	2.52	4.000	1.70						0.71	2.41	93.2	250	254	0.37	37.737	0.75	6%
	36	37	13			44	0.79	149	3.31	4.000	2.41						0.93	3.34	77.1	250	254	0.37	37.737	0.75	9%
	37	33	2	3		15		164	3.31	4.000	2.66			1			0.93	3.58	17.9	250	254	0.40	39.237	0.78	9%

1200 Maritime Way SANITARY SEWER DESIGN SHEET OF DOWNSTREAM SEWERS - OLD STANDARDS JOB# 120144

BIRKENDALE DRIVE 27.795 24.128 201.540 482.05 33 32 10 27 0.56 15863 255.86 2.754 176 96 79.42 72.7 TEESWATER STREET 30 31 16 43 0.66 43 0.66 4.000 0.70 0.18 0.88 75.1 31 32 19 51 0.41 94 1.07 4.000 1.52 0.30 1.82 77.9 **BIRKENDALE STREET** 177.99 483.48 32 18 6 16 0.37 15973 257.30 2.751 27.795 24.128 201.540 79.83 44 4 18 16 4 11 15984 257.30 2.750 178.09 27.795 24.128 201.540 79.83 483.59 44.4 COMMERCIAL PLAZA 19 17 4.000 0.00 0.520 0.520 0.451 0.15 0.60 26.5 COLCHESTER SQUARE 17 16 0.10 0.10 4.000 0.00 0.520 0.451 0.17 0.62 33.2 COLCHESTER SQUARE 16 15 10 27 0.56 16011 257.96 2.750 178.34 28.315 24.579 201.540 80.16 484.62 66.0 15 14A 2 16016 257.96 2.750 178.39 28.315 24.579 201.540 80.16 484.67 25.8 5 ELSINORE LANE 39 28 32 86 0.53 86 0.53 4.000 1.39 0.15 1.54 56.7 28 24 18 49 1.47 135 2.00 4.000 2.19 0.56 2.75 43.0 24 12 23 32 0.14 167 2.14 4.000 2.71 0.60 3.31 34.0 FLSINORE LANE 23 306 8 22 0.24 189 2.38 4.000 3.06 0.67 3.73 48.8 ENDENVALE DRIVE 306 14-A 0.45 189 2.83 4.000 3.06 0.79 3.85 46.4 COLCHESTER SQUARE 14-A 14 16205 260 79 2.744 180.16 28 315 24.579 201.540 80 95 487.23 14 7 0.520 Church 14 4.000 0.00 0.520 0.451 0 15 0.60 35.0 COLCHESTER SQUARE 14 4 0.16 487.97 11 11 16216 260.95 2.744 180.26 28.835 25.030 201.540 81.14 72.6 TERON 11 10 16216 260.95 2.744 180.26 28.835 25.030 201.540 81.14 487.97 29.6 10 16216 EX. 0.25 261.20 2.744 180.26 28.835 25.030 201.540 81.21 488.04 72.3 TERON 0.P.P. EX. 4.000 0.780 0.780 0.00 0.78 CAMPEAU / TERRON 11833 EX.2 4 14 7.5 14 7.5 4.000 0.23 19.20 19.200 16.667 0.000 24.37 94.7 0.000 7.48 TERON EX. EX. 2 16230 268.70 2.744 180.39 48.035 41.697 202.320 88.69 513.10 9.4 EX.2 6230 2.744 180.39 48.035 41.69 42.8 268 70 2.744 180.39 48.035 41.697 88 69 513 10 40.7 1183 16230 202 320 11837 11859 194 349 349 349 2.19 16579 270.89 2.734 183.65 50.225 43.598 202.320 89.91 519.48 89.9 TERRON (SE) 11841 11859 42 76 76 76 1.12 76 1.12 4.000 1.23 0.31 1.54 50.7 SALTER CRES. 11859 11839 16655 184.35 43.598 202.320 520.50 272.01 2.732 50.225 90.23 50.0 11839 11840 16655 272.01 2.732 184.35 50.225 43.598 202.320 90.23 520.50 40.3 11840 16938 186.98 523.63 70.5 11844 105 284 1.78 273.79 2.725 50.225 43.598 202.320 90.72 0.462.724 43.598 524.10 CHECK 11838 43.598 74 46 187.43 524.26 20755 11860 52 140 4.45 17127 278.91 2.720 188.73 50.225 43.598 202.320 92.16 526.81 14.0 11860 11861 8 22 0.32 17149 279.23 2.720 188.93 50.225 43.598 202.320 92.25 527.10 46.4 7 11861 11862 19 0.36 17168 279.59 2.719 189.11 50.225 43.598 202.320 92.35 527.37 57.7 6 527.79 11862 11863 3 26 0.60 17194 280.19 2.719 189.35 50.225 43.598 202.320 92.52 63.2 11863 6 11864 3 26 0.71 17221 280.90 2 718 189 59 50.225 43 598 202 320 92 72 528 23 73.4 BANTING CRES 11856 11864 54 122 403 6.2 6.2 4 000 6 53 0 850 0.850 0.738 1 97 9.25 94.1 403 11865 12091 6 11 0.39 17643 287.96 2.707 193.49 2.09 53.165 46.150 202.320 95.52 537.47 95.7 12091 910 18 5 75 1.76 17645 289.72 2.707 193.50 53.165 46.150 202.320 96.01 537.98 56.8

900	914	0.11	626.373	0.96	77%
250	254	0.40	39.237	0.78	2%
250	254	0.40	39.237	0.78	5%
900	0 914	0.11	626.373	0.96	77%
900	914	0.11	626.373	0.96	77%
		-			1170
150	152	0.90	15.073	0.84	4%
250	254	0.40	39.237	0.78	2%
900	914	0.11	626.373	0.96	77%
900	914	0.11	626.373	0.96	77%
250	254	1.00	62.039	1.24	2%
250	254	0.40	39.237	0.78	7%
250	254	0.40	39.237	0.78	8%
250	254	0.44	41.152	0.82	9%
250	254	0.49	43.427	0.87	9%
900	914	0.11	626.373	0.96	78%
150	152	1.00	15.888	0.88	4%
					70
900	914	0.11	626.373	0.96	78%
900	914	0.11	626.373	0.96	78%
900	914	0.11	626.373	0.96	78%
100 FORC	EMAIN	1			
250	254	1.84	84.153	1.68	29%
675	686	0.46	594.765	1.63	86%
675	686	0.77	769.506	2.11	67%
675	686	0.57	662.070	1.81	77%
675	686	0.39	547.645	1.50	95%
250	254	0.410	39.724	0.79	4%
675	686	4.86	1933.235	5.29	27%
675	686	0.40	554.621	1.52	94%
675	686	0.40	554.621	1.52	94%
					0470
675	686	0.33	503.760	1.38	104%
675	686	0.30	480.316	1.31	109%
675	686	0.36	526.160	1.44	100%
675	686	0.35	518.801	1.42	102%
675	686	0.66	712.424	1.95	74%
675	686	0.40	554.621	1.52	95%
675	686	0.40	554.621	1.52	95%
250	254	0.51	44.305	0.88	21%
675	686	0.40	554.621	1.52	96%
675	686	0.65	707.006	1.93	76%
675	686	0.72	744.102	2.04	72%

SANITARY SEWER DESIGN SHEET OF DOWNSTREAM SEWERS - OLD STANDARDS JOB# 120144

PENFIELD DR 911 910 1514 1359 118 212 9029 188 9029 188 2.999 109.68 11.23 11.230 9.748 55.78 175.21 64.8 TRUNK 910 26674 177.72 2.528 273.12 64.395 55.898 202.320 909 908 55.898 909 26674 477.72 64.395 202.320 151.79 683.13 2.528 273.12 908 907 26674 477.72 2.528 273.12 16.52 80.915 70.239 202.320 156.42 702.10 41.4

Notes:

 Notes:

 1) As per Kanata Town Centre Sanitary Trunk Sewer Study revised March 27, 1996 by Robinson Consultants Inc.

 2) Park or open space area.

 3) Equivalent population base on 208 rooms and 20 staff members.

 4) Allowance for an ultimate flow of 188 I/s to provide flexibility in future development as per Kanata Town Centre Sanitary Trunk Study.

 5) Additional flow associated with hotel amendities including swimming pool with bathrooms and laudry as per design calculations for Block 1 provided by WSP (October 2016).

 6) Additional flow associated with overall amenities including beauty salon, staff, dining and laundry as per design calculations for 1250 Maritime Way (Timberwalk Retirement Home) provided by Novatech (July 31, 2017).

 7) JLR Spreadsheet up-dated to include development flows from 1200 Maritime Way. Reference Appendix A of Serviceability Report for 1250 Maritime Way attached in Appendix of 1200 Maritime Way Serviceability Report (Novatech January 28, 2021).

Design Parameters:

1) Q(p) = (PxqxM/86,400)	Units					
2) $Q(d) = Q(p) + Q(e)$	Single	3.4	pers/unit		1200 Maritime	Way
Definitions:	Town	2.7	pers/unit		SANITARY SEWER DE	
P = Population	Hotel/ Apartmentt	1.8	pers/unit		SANITART SEWER DE	SIGN SHEET
q = Average per capita flow = 350 L/person/day	Retirement Home	1.6	pers/unit			
M = Residential Peaking Factor (Harmon Formula from section 4.4.1 of the City Sewer Design Guidelines):						
$M = 1 + [14/(4 + Pop/1000)^{-1}/2]^{*}1 - (Maximum of 4.0)$	Commercial Flow	50000	L/ha/day			
	Commercial Peak Factor		1.5	Date	March	25, 2022
Q(d) = Design Flow (L/sec)				Design GMAC		
Q(p) = Population Flow (L/sec)				Job No.	wg. Referenc	Checked and Stamped:
Q(r) = Commercial Flow (L/sec)				100111	120144-	
Q(e) = Extraneous Flow (L/sec) 0.28 I/s/ha				120144	SAN	

N	C	//	1	Г		C	H	
N 0					R T S		N	G D.

			140100 (1000 1000) 1000		
600	610	0.14	239.676	0.83	73%
			0.000		
600	610	1.02	646.934	2.24	106%
900	914	0.75	1635.562	2.52	42%
900	914	0.46	1280.900	1.97	55%

1200 Maritime Way SANITARY SEWER D JOB# 120144	DESIGN SH	IEET OF	DOWNS	STREAM SEWE	ERS -CU	IRRENT	STAND	DARDS																						
LOCAT	TION								RESIDEN	TIAL						co	MMERCIAL	/INSTITUTIO	NAL	PLUGGE	ED FLOW	R	+ C			PR	OPOSED	SEWER		
					NUMBER	R OF UNIT	rs			INDIV	IDUAL	CUMUL	ATIVE									PEAK	PEAK							
STREET	FROM MH	ТО МН		Houses	Extend	ded Care		Hotel/Ap	ot	POPUL.	AREA	POPUL.	AREA	PEAK FACTOR (M)	POPUL. FLOW L/S	ACTUAL AREA ha	CUMM AREA ha	COMM PEAK FACTOR	COMM FLOW I/s	FLOW I/s	COMM FLOW I/s	EXTR. FLOW	DESIGN FLOW	LENGTH (m)	PIPE SIZE (mm)	ACTUAL PIPE SIZE (mm)	SLOPE %	CAPACITY (L/s)	FULL FLOW VELOCITY (m/s)	RATIO (Q/Qfull)
			Singles	Stacks Towns	No. Units	Act Pop	No. Units	Act. Pop	Equ. Pop	People	ha	People	ha									l/s	L/S							
Robinson - 1996	Upstream	7A								2588	28.38	2588	28.38	2.797	23.46	20.370	20.370	1.500	9.90	162.69	162.69	16.09	212.14							
1250 Maritime Way	Blk 122	7A								377	0.89	377	0.89	3.227	3.94	0.005	0.005	1.000	0.002	0.83	0.83	0.30	5.07							
1200 Maritime Way	Blk 126	7 A								1032	1.24	1032	1.24	3.380	3.34	0.004	0.004	1.000	0.140			0.410	11.83							
Maritime Way	7A	507										3997	30.51	2.667	34.54		20.379	1.500	9.906		163.520	16.79	224.76	81.9	825	838	0.14	560.313	1.02	40%
Maritime Way	507	506					125	225	174	174	1.02	4171	31.53	2.654	35.87	3.680	24.059	1.500	11.695		163.520	18.34	229.43	119.3	825	838	0.12	518.749	0.94	44%
Cordillera Street	524	533					125	207	207	207	0.58	207	0.59	2 24 4	2.00	0.550	0.550	1 500	0.267			0.37	2.96	66.6	200	202	1.65	42.050	1.07	70/
Can. Shield Avenue	534 533	533					125	207	207	207	0.58	207	0.58	3.314 3.314	2.22 2.22	0.550	0.550	1.500 1.500	0.267			0.37	2.86 2.86	66.6 69.9	200	203 203	1.65 1.20	43.952 37.482	1.37 1.17	7% 8%
Can. Shield Avenue	532	531									0.33	207	0.91	3.314	2.22		0.550	1.500	0.267			0.48	2.00	69.9	200	203	1.20	37.482	1.17	8%
Great Lakes Avenue	536	531					100	180	139	139	0.78	139	0.78	3.361	1.51	0.040	0.040	1.000	0.013	0.300	0.300	0.27	2.10	60.0	200	203	2.40	53.008	1.65	4%
Great Lakes Avenue	531	530										346	1.69	3.241	3.63		0.590	1.500	0.287		0.300	0.75	4.97	80.8	200	203	3.75	66.260	2.06	8%
Great Lakes Avenue	530	506A										346	1.69	3.241	3.63		0.590	1.500	0.287		0.300	0.75	4.97	85.2	200	203	1.40	40.486	1.26	12%
Great Lakes Avenue	506A	506									0.38	346	2.07	3.241	3.63		0.590	1.500	0.287		0.300	0.88	5.10	4.9	200	203	1.40	40.486	1.26	13%
Maritime Way	506	505					176	316.8	269	269	0.57	4786	34.17	2.610	40.48		24.649	1.500	11.982		163.820	19.41	235.69	111.0	825	838	0.12	518.749	0.95	450/
Maritime Way	505	505					146	262.8	209	230	0.56	5016	34.17	2.595	40.48	1.750	24.049	1.500	12.833		163.820	20.17	235.09	111.0	825	838	0.12	496.665	0.95	45% 48%
Maritime Way	504	501									0.27	5016	35	2.595	42.18		26.399	1.500	12.833		163.820	20.26	239.10	29.9	825	838	0.11	496.665	0.91	48%
Can. Shield Avenue	542	541					176	316.8	269	269	0.74	269	0.74	3.279	2.86	4 0 0 0	1.000	4.500	0.000			0.24	3.10	71.3	200	203	2.20	50.751	1.58	6%
Can. Shield Avenue	541	540					154	272.2	232	232	0.51	501	1.25	3.179	5.16	1.360	1.360	1.500	0.661			0.86	6.68	77.7	200	203	0.90	32.461	1.01	21%
	Block 3	540			208	333			428	428	1.02	428	1.02	3.206	4.45			1.000	0.000			0.34	4.78	12.0	200	203	0.60	26.504	0.83	18%
Can. Shield Avenue	540	512									0.3	929	2.57	3.056	9.20		1.360	1.500	0.661			1.30	11.16	82.6	200	203	0.71	28.831	0.90	39%
Maritime Way	514	513																						51.2	200	203	2.14	50.055	1.56	0%
Maritime Way (Blk 4)	513	512					144	271	271	271	1.12	271	1.12	3.278	2.88			1.000	0.000			0.37	3.25	51.9	200	203	2.28	51.666	1.61	6%
Maritime Way	512	511							58	58	0.73	1258	4.42	2.987	12.18		1.360	1.500	0.661			1.91	14.75	49.3	200	203	3.12	60.439	1.88	24%
	Block 5	511					154	301	301	301	0.92	301	0.92	3.262	3.18			1.000	0.000			0.30	3.49	12.2	200	203	2.00	48.390	1.51	7%
Maritime Way	511	510			+							1559	5.34	2.934	14.82		1.360	1.500	0.661			2.21	17.70	38.4	200	203	1.70	44.613	1.39	40%
Maritime Way	510	501										1559	5.34	2.934	14.82		1.360	1.500	0.661			2.21	17.70	11.3	200	203	2.28	51.666	1.61	34%
Trunk Easement Trunk Easement	501 500	500 94										6575 6575	40.34 40.34	2.506 2.506	53.40 53.40		27.759 27.759	1.500 1.500	13.494 13.494		163.820 163.820		253.19 253.19	129.0	825	838	0.10	473.551	0.87	53%
A	90	92		35						95	0.80	95	0.80	3.400	1.05			1.000	0.000			0.26	1.31	120.0	250	254	0.60	48.055	0.96	20/
<u> </u>	90	92		12						32	1.19	127	1.99	3.400	1.03			1.000	0.000			0.66	2.04	103.0	250	254	2.20	92.018	1.84	<u>3%</u> 2%
																													_	_ /0
	94	95										6702	42.33	2.500	54.30		27.759	1.500	13.494		163.820		254.74	17.5	825	838	0.12	518.749	0.95	49%
	95	89		10						27	0.52	6729	42.85	2.499	54.48		27.759	1.500	13.494		163.820	23.30	255.10	66.6	825	838	0.12	518.749	0.95	49%

200 Maritime Way SANITARY SEWER DE OB# 120144	ESIGN SH	IEET OF	DOWNS	TREAM SEWERS -CU	RRENT ST	TANDARDS							 													
В	85	87	19				65	1.19	65	1.19	3.432	0.72		1.000	0.000			0.39	1.12	116.9	250	254	0.40	39.237	0.78	3%
	87	89		24			65	0.82	130	2.01	3.368	1.42		1.000	0.000			0.66	2.08	116.7	250	254	1.41	73.667	1.47	3%
A	89	84		12			32	0.35	6891	45.21	2.491	55.62	27.759	1.500	13.494		163.820	24.08	257.01	79.0	825	838	0.12	518.749	0.95	50%
С	80	82	19				65	1.08	65	1.08	3.432	0.72		1.000	0.000			0.36	1.08	120.0	250	254	0.40	39.237	0.78	3%
_	82	84		25			67	0.83	132	1.91	3.367	1.44		1.000	0.000			0.63	2.07	118.5	250	254	1.20	67.960	1.36	3%
A	84	79		14			38	0.54	7061	47.66	2.482	56.80	27.759	1.500	13.494		163.820	24.89	259.01	79.0	825	838	0.12	518.749	0.95	50%
_															0.000											
D	75	76		17			46	0.37	46	0.37	3.458	0.52		1.000	0.000			0.12	0.64	57.0	250	254	0.40	39.237	0.78	2%
	76	77		20			54	0.29	100	0.66	3.395	1.10		1.000	0.000			0.22	1.32	78.4	250	254	0.40	39.237	0.78	3%
	77	79		13			35	0.63	135	1.29	3.364	1.47		1.000	0.000			0.43	1.90	117.7	250	254	0.81	55.835	1.11	3%
Park Easement	79	67						0.98	7196	49.93	2.476	57.74	27.759	1.500	13.494		163.820	25.64	260.69	55.0	825	838	0.12	518.749	0.95	50%
	67	66		6			16	0.33	7212	50.26	2.475	57.85	27.759	1.500	13.494		163.820	25.75	260.91	70.0	825	838	0.12	518.749	0.95	50%
BELLROCK DRIVE	70	73		12 14			70	2.56	70	2.56	3.426	0.78		1.000	0.000			0.84	1.62	87.2	250	254	0.40	39.237	0.78	4%
	73	74		12			32	0.54	102	3.1	3.393	1.12		1.000	0.000			1.02	2.14	80.3	250	254	0.40	39.237	0.78	5%
EASEMENT	74	62			<u> </u>			0.31	102	3.41	3.393	1.12		1.000	0.000			1.13	2.25	39.9	250	254	0.40	39.237	0.78	6%
CAMBRAY LANE	62	66		25			68	0.48	170	3.89	3.338	1.84		1.000	0.000			1.28	3.12	100.5	250	254	0.40	39.237	0.78	8%
BISHOPS MILLS WAY	66	65		9			24	0.53	7406	54.68	2.466	59.19	27.759	1.500	13.494		163.820	27.20	263.71	62.0	825	838	0.12	518.749	0.95	51%
SOUTH OF HWY 7	EX.	65					7792	191.6	7792	191.6	2.449	61.85		1.000	0.000	37.720	37.720	63.23	162.79	50.2	900	914	0.11	626.373	0.96	26%
BISHOPS MILLS WAY	65	64		2			5		15203	246.28	2.218	109.27	27.759	1.000	8.996		201.540	90.43	410.24	17.0	900	914	0.11	626.373	0.96	050/
BISHOFS WILLS WAT	05	04		2			5		15205	240.20	2.210	109.27	21.159	1.000	0.990		201.340	90.43	410.24	17.0	900	914	0.11	020.373	0.90	65%
EDENVALE DRIVE	59	60		8			22	0.50	22	0.50	3.500	0.25		1.000	0.000			0.17	0.41	77.0	200	203	1.40	40.486	1.26	1%
KETTLEBY STREET	60	61		22			59	0.62	81	1.12	3.414	0.90		1.000	0.000			0.37	1.27	103.6	250	254	0.40	39.237	0.78	3%
CAMBRAY LANE	58	61		5			14	0.41	14	0.41	3.520	0.16		1.000	0.000			0.14	0.29	74.5	200	203	0.70	28.628	0.89	1%
KETTLEBY STREET	61	64		25			68	0.42	163	1.95	3.343	1.77		1.000	0.000			0.64	2.41	105.0	250	254	0.90	58.855	1.17	4%
BISHOPS MILLS WAY	64	<u></u>							45074	0.40.00	0.014	440.04	07 750	1 000	0.000		004 540	04.00	444.00	42.0	000	014	0.44	000 070	0.00	
BISHOPS MILLS WAY	64 63	63 57		3 10			8 27	0.68	15374 15401	248.23 248.91	2.214 2.213	110.31 110.47	27.759 27.759	1.000 1.000	8.996 8.996		201.540 201.540	91.08 91.30	411.92 412.31	13.0 64.9	900 900	914 914	0.11	626.373 626.373	0.96	66% 66%
ER. BUNGALOW Ph. 2	51	53		48			130	0.94	130	0.94	3.368	1.42		1.000	0.000			0.31	1.73	122.3	200	203	0.70	28.628	0.89	6%
	53 54	54		4			11	0.27	141	0.94	3.360	1.54		1.000	0.000			0.31	1.85 1.93	13.6	200	203	0.70		0.89	6%
BISHOPS MILLS WAY	55	55 56	11				37	0.27	141 178	1.21 2.02	3.360 3.333	1.54 1.92		1.000	0.000			0.40	2.59	36.7 107.1	200 250	203 254	0.70	28.628 39.237	0.89	7% 7%
	56	57	7	12			56	0.65	234	2.67	3.298	2.50		1.000	0.000			0.88	3.38	101.5	250	254	0.60	48.055	0.96	7%
DADIC	F7				<u> </u>			0.07	45000	054.05	0.000	144.00	 07 750	1.000	0.000		204 5 42	00.00	44 4 7 4	F0 F	000	044	0.44	600.070	0.00	-
PARK	57 34	34 33		1 3			3 8	0.37	15638 15646	251.95 251.95		111.90 111.95	27.759 27.759	1.000 1.000	8.996 8.996		201.540 201.540	92.30 92.30	414.74 414.79	53.5 50.3	900 900	914 914	0.11	626.373 626.373	0.96	66% 66%
HAWSTONE	43 44	44 45		22 8			59 22	1.19 0.09	59 81	1.19 1.28	3.440 3.414	0.66		1.000 1.000	0.000			0.39	1.05 1.32	51.0 29.0	250 250	254 254	1.00 0.50	62.039 43.868	1.24 0.87	2% 3%
EDENVALE	45	35						0.06	81	1.34	3.414	0.90		1.000	0.000			0.42	1.34	39.8	250	254	0.50	43.868	0.87	3%
BIRKENDALE DRIVE	35	36	7				24	1.18	105	2.52	3.390	1.15		1.000	0.000			0.83	1.99	93.2	250	254	0.37	37.737	0.75	5%
	36	37	13				44	0.79	149	3.31	3.354	1.62		1.000	0.000			1.09	2.71	77.1	250	254	0.37	37.737	0.75	7%
	37	33	2	3			15		164	3.31	3.343	1.78		1.000	0.000			1.09	2.87	17.9	250	254	0.40	39.237	0.78	7%
BIRKENDALE DRIVE	33	32		10			27	0.56	15837	255.82	2.204	113.10	27.759	1.000	8.996		201.540	93.58	417.21	72.7	900	914	0.11	626.373	0.96	67%
TEESWATER STREET	30	31		16			43	0.66	43	0.66	3.462	0.48		1.000	0.000			0.22	0.70	75.1	250	254	0.40	39.237	0.78	
					+						3.402	1.04		1.000	0.000			0.35	1.39							2%
	31	32		19	1		51	0.41	94	1.07	3.401	1.04			1 0.000	1	1 1	0.35	1.39	77.9	250	254	0.40	39.237	0.78	4%

200 Maritime Way SANITARY SEWER DES JOB# 120144	SIGN SH	EET OF	DOWNS	TREAM SEWE	RS -CUF	RRENT	STAND	ARDS																					
BIRKENDALE STREET	32	18		6						16	0.37	15947	257.26	2.201	113.76		27.759	1.000	8.996	201.540	94.06	418.35	44.4	900	914	0.11	626.373	0.96	67%
	18	16		4						11		15958	257.26	2.201	113.82		27.759	1.000	8.996	201.540	94.06	418.41	44.4	900	914	0.11	626.373	0.96	67%
COMMERCIAL PLAZA	19	17														0.520	0.520	1.500	0.253		0.17	0.42	26.5	150	152	0.90	15.073	0.84	
COLCHESTER SQUARE	17	16									0.10		0.10				0.520	1.500	0.253		0.20	0.46	33.2	250	254	0.40	39.237	0.78	3%
																													1%
COLCHESTER SQUARE	16	15		10						27	0.56	15985	257.92	2.200	113.98		28.279	1.000	9.164	201.540	94.45	419.13	66.0	900	914	0.11	626.373	0.96	67%
	15	14A		2						5		15990	257.92	2.200	114.01		28.279	1.000	9.164	201.540	94.45	419.16	25.8	900	914	0.11	626.373	0.96	67%
ELSINORE LANE	39	28		32						86	0.53	86	0.53	3.409	0.95			1.000	0.000		0.17	1.12	56.7	250	254	1.00	62.039	1.24	2%
	28	24		18						49	1.47	135	2.00	3.364	1.47			1.000	0.000		0.66	2.13	43.0	250	254	0.40	39.237	0.78	5%
	24	23		12						32	0.14	167	2.14	3.340	1.81			1.000	0.000		0.71	2.51	34.0	250	254	0.40	39.237	0.78	6%
ELSINORE LANE	23	306		8						22	0.24	189	2.38	3.326	2.04			1.000	0.000		0.79	2.82	48.8	250	254	0.44	41.152	0.82	7%
ENDENVALE DRIVE	306	14-A									0.45	189	2.83	3.326	2.04			1.000	0.000		0.93	2.97	46.4	250	254	0.49	43.427	0.87	7%
COLCHESTER SQUARE	14-A	14										16179	260.75	2.196	115.15		28.279	1.000	9.164	201.540	95.38	421.23	14.7	900	914	0.11	626.373	0.96	67%
	Church	14														0.520	0.520	1.500	0.253		0.17	0.42	35.0	150	152	1.00	15.888	0.88	3%
																													570
COLCHESTER SQUARE	14	11		4						11	0.16	16190	260.91	2.196	115.21		28.799	1.000	9.333	201.540	95.60	421.69	72.6	900	914	0.11	626.373	0.96	67%
TERON	11	10										16190	260.91	2.196	115.21		28.799	1.000	9.333	201.540	95.60	421.69	29.6	900	914	0.11	626.373	0.96	67%
	10	EX.									0.25	16190	261.16	2.196	115.21		28.799	1.000	9.333	201.540	95.69	421.77	72.3	900	914	0.11	626.373	0.96	67%
TERON	0.P.P.	EX.																1.500	0.000	0.780 0.780		0.78		100 FORC	EMAIN				
CAMPEAU / TERRON	11833	EX.2	4							14	7.5	14	7.5	3.520	0.16	19.20	19.200	1.500	9.333	0.000 0.000	8.81	18.30	94.7	250	254	1.84	84.153	1.68	22%
TERON	EX.	EX. 2										16204	268.66	2.196	115.30		47.999	1.000	15.555	202.320	104.50	437.67	9.4	675	686	0.46	594.765	1.63	74%
	EX.2	***										16204	268.66	2.196	115.30		47.999	1.000	15.555	202.320	104.50	437.67	42.8	675	686	0.77	769.506	2.11	57%
	***	11837										16204	268.66	2.196	115.30		47.999	1.000	15.555	202.320	104.50	437.67	40.7	675	686	0.57	662.070	1.81	66%
	11837	11859					194	349	349	349	2.19	16553	270.85	2.188	117.38		50.189	1.000	16.265	202.320	105.94	441.91	89.9	675	686	0.39	547.645	1.50	81%
TERRON (SE)	11841	11859					42	76	76	76	1.12	76	1.12	3.420	0.84			1.00	0.000		0.37	1.21	50.7	250	254	0.410	39.724	0.79	3%
	44050	44000										40000	074.07	0.407	447.00		50.400	1 000	40.005	000.000	400.04	440.70	50.0	075	606	4.00	4000.005	5.00	
SALTER CRES.	11859 11839	11839										16629	271.97 271.97	2.187 2.187	117.83		50.189 50.189	1.000	16.265	202.320 202.320	106.31	442.73	50.0 40.3	675 675	686	4.86 0.40	1933.235 554.621	5.29 1.52	23%
	11840	11840 11844		105						284	1.78	16629 16912	271.97	2.187	117.83 119.51		50.189	1.000	16.265 16.265	202.320	106.31 106.90	442.73 445.00	40.3 70.5	675	686 686	0.40	554.621	1.52	80%
	11640	11044		103						204	1.76	10912	213.13	2.101	119.51		50.189	1.000	10.205	202.320	100.90	445.00	70.5	075	080	0.40	554.021	1.52	80%
PENFIELD DR.	11844	11838		14						38	0.46	16950	274.21		119.74		50.189	1.000	16.265	202.320	107.05	445.38	48.7	675	686	0.33		1.38	88%
CHECK	11838	20755		4						11	0.21	16961	274.42	2.180	119.80		50.189	1.000	16.265	202.320		445.51	33.5	675	686	0.30	480.316	1.31	93%
	20755	11860		52						140	4.45	17101	278.87		120.63		50.189	1.000	16.265	202.320	108.59	447.81	14.0	675	686	0.36		1.44	85%
	11860	11861		8						22	0.32	17123	279.19	2.176	120.76		50.189	1.000	16.265	202.320	108.70	448.04	46.4	675	686	0.35	518.801	1.42	86%
	11861	11862		7						19	0.36	17142	279.55	2.176	120.87		50.189	1.000	16.265	202.320	108.81	448.27	57.7	675	686	0.66	712.424	1.95	63%
	11862 11863	11863 11864	3	6						26 26	0.60	17168 17195	280.15 280.86	2.175 2.175	121.03 121.19		50.189 50.189	1.000	16.265 16.265	202.320 202.320	109.01 109.25	448.63 449.02	63.2 73.4	675 675	686 686	0.40	554.621 554.621	1.52 1.52	81% 81%
	110																							0	a- :	0			
BANTING CRES PENFIELD DR	11856 11864	11864 11865	54	7			122			403 19	6.2 0.47	403 17617	6.2 287.53	3.216 2.166	4.20 123.68	0.850	0.850 51.039	1.000	0.275	202.320	2.33 111.73	6.80 454.27	94.1 91.7	250 675	254 686	0.51	44.305 554.621	0.88	15% 82%
	11865	12091		6						11	0.39	17617	287.92	2.166	123.68	2.09	53.129	1.000	17.218	202.320	112.55	455.76	95.7	675	686	0.65	707.006	1.93	64%
				ı I V							0.00		201.02	2.100	0.00	2.00	00.120		1	202.020				510		0.00			04 70
	12091	910	18	5						75	1.76	17619	289.68	2.166	123.69		53.129	1.000	17.218	202.320	113.13	456.35	56.8	675	686	0.72	744.102	2.04	61%

1200 Maritime Way SANITARY SEWER DESIGN SHEET OF DOWNSTREAM SEWERS -CURRENT STANDARDS JOB# 120144

PENFIELD DR	911	910	1514	1359	118	212	9029	188	9029	188	2.399	70.20	11.23	11.230	1.000	3.639		65.75	139.58	64.8	600	610	0.14	239.676	0.83	58%
																								0.000	1	
TRUNK	910	909							26648	477.68	2.022	174.66		64.359	1.000	20.857	202.320	178.87	576.71	56.4	600	610	1.02	646.934	2.24	89%
	909	908							26648	477.68	2.022	174.66		64.359	1.000	20.857	202.320	178.87	576.71	26.5	900	914	0.75	1635.562	2.52	35%
	908	907							26648	477.68	2.022	174.66	16.52	80.879	1.000	26.211	202.320	184.32	587.51	41.4	900	914	0.46	1280.900	1.97	46%
				 													-									

Notes:

Notes:
1) As per Kanata Town Centre Sanitary Trunk Sewer Study revised March 27, 1996 by Robinson Consultants Inc.
2) Park or open space area.
3) Equivalent population base on 208 rooms and 20 staff members.
4) Allowance for an ultimate flow of 188 l/s to provide flexibility in future development as per Kanata Town Centre Sanitary Trunk Study.
5) Additional flow associated with hotel amendities including swimming pool with bathrooms and laudry as per design calculations for Block 1 provided by WSP (October 2016).
6) Additional flow associated with overall amenities including beauty salon, staff, dining and laudry as per design calculations for 1250 Maritime Way (Timberwalk Retirement Home) provided by Novatech (July 31, 2017).
7) JLR Spreadsheet up-dated to include development flows from 1200 Maritime Way. Reference Appendix A of Serviceability Report for 1250 Maritime Way attached in Appendix of 1200 Maritime Way Serviceability Report (Novatech January 28, 2021).

Design Parameters:							
1) Q(p) = (PxqxM/86,400)	Units						
2) $Q(d) = Q(p) + Q(e)$	Single	3.4	pers/unit			1200 Maritime	Way
Definitions:	Town	2.7	pers/unit			SANITARY SEWER DE	
P = Population	Hotel/ Apartmentt	1.8	pers/unit			SANITART SEWER DE	SIGN SHEET
q = Average per capita flow = 280 L/person/day	Retirement Home	1.6	pers/unit				
M = Residential Peaking Factor (Harmon Formula from section 4.4.1 of the City Sewer Design Guidelines):							
M = 1+[14/(4+Pop/1000)^1/2]*0.8 - (Maximum of 4.0)	Commercial Flow	28000	L/ha/day				
	Commercial Peak Factor	1.5	if <20% of area	Date		March	25, 2022
Q(d) = Design Flow(L/sec)		1.0	if >20% of area	Design	GMAC		
Q(p) = Population Flow (L/sec)				Job	No.	wg. Referenc	Checked and Stamped:
Q(r) = Commercial Flow (L/sec)				100	144	120144-	
Q(e) = Extraneous Flow (L/sec) 0.33 //s/ha				120	1144	SAN	

	N	C		\mathbf{J}	1	I	Ξ	C	H	Ĩ
E	N	G	I.	N	E	Е	R	I.	N	G
C	ON	IS	U	I T	A	N	TS		I T	D

MEMORANDUM



J.L. Richards & Associates Limited 864 Lady Ellen Place Ottawa, ON Canada K1Z 5M2 Tel: 613 728 3571 Fax: 613 728 6012

Page 1 of 2

To: Greg MacDonald, P.Eng. Novatech Engineering Consultants Ltd.

Date:	August 18, 2017
Job No.:	15712-015.1
CC:	Lucie Dalrymple, P.Eng. J.L. Richards & Associates Ltd.

From: Karla Ferrey, P.Eng.

Re: Kanata Town Centre Central Business District Master Design Sheet Update - Sanitary Peak Flows Block 4, Block 5 and Block west of Block 9 (Zone 122)

We understand that the City is requesting an update to the Master Sanitary Sewer Design Sheet for the Kanata Town Centre Central Business District (KTC-CBD) from JL Richards such to incorporate the proposed peak flow revision from Block 4, Block 5, and the parcel west of Block 9 (previously Robinson'96 - Zone 122). Refer to attached JLR Sanitary Drainage Plan and Robinson Consultants Figure 7.1 for locations of Block 4, Block 5 and Zone 122.

We understand that the City will ultimately decide (as the owner of the existing sewers within the KTC-CBD and downstream system) whether the proposed peak flow increase is acceptable and that if accepted, it will not require a reduction of the allowable peak flows for the remaining future development in the KTC-CBD.

As requested, we have incorporated the proposed sanitary peak flow increase associated with your following developments:

a) Proposed Block 4 - Residential development

The proposed development will result in a theoretical increase in peak flow from 3.88 L/s to 4.71 L/s at MH 513 where the Block 4 development outlets to Maritime Way. This represents a theoretical peak flow increase of 0.83 L/s from the anticipated 2012 land use (i.e., hotel use, based on 270 L/pers/day).

b) Proposed Block 5 - Residential development

The proposed development will result in a theoretical increase in peak flow from 3.52 L/s to 5.13 L/s at MH 511 where the Block 5 development outlets to Maritime Way. This represents a theoretical peak flow increase of 1.61 L/s from the anticipated 2012 land use (i.e., hotel use, based on 270 L/pers/day).

c) <u>Proposed parcel west of Block 9 (previously identified in the 1996 Robinson KTC Sanitary Design as Zone</u> <u>122) – Retirement Home – Claridge Homes</u>

The proposed development will result in a theoretical increase in peak flow from 2.84 L/s to 7.19 L/s at MH 7A where Claridge Homes development outlets to Maritime Way. This represents a theoretical peak flow increase of 3.57 L/s from the anticipated 2012 land use (i.e., Commercial use based on 2787m2 office space and Infiltration based 1.5ha). Theoretical flows for Zone 122 were taken from Robinson Consultants Sanitary Trunk Information from Table 4.7 and Figure 7.1, see attached copies.

At the most downstream MH at the intersection of Teron Rd and Campeau Dr (MH Ex. 2) shown on the attached Sanitary Sewer Design Sheet for the Kanata Village Green subdivision (prepared in 1998 by JLR), the proposed 3 developments would result in a theoretical increase in peak flow from 475.94 L/s to 480.24 L/s which corresponds to a 4.3 L/s (0.9%) peak flow increase.

Based on the available theoretical residual capacities noted in the attached updated Master Sanitary Sewer Design Sheet, the existing sanitary sewer system from the intersection of Rock Mountain Gate and Maritime Way to the intersection of Campeau Dr and Teron Rd has the capacity to accommodate the additional theoretical peak flows of Block 4, Block 5 and Zone 122. Downstream of the Campeau Drive intersection, JLR does not have on record design sheets for the City's existing downstream sanitary sewer system.

August 18, 2017 JLR No.: 15712-015.1

Page 2 of 2

Should you have any questions or require anything further, please do not hesitate to call.

J.L. RICHARDS & ASSOCIATES LIMITED

Prepared by:

Karla Ferrey, P.Eng.



CITY OF OTTAWA

KANATA TOWN CENTRE CENTRAL BUSINESS DISTRICT URBANDALE CORPORATION JLR PROJECT NO.: 15712

Commercial Flow =	50000	L/ha/d
q residential=	350	l/cap/d
q hotel =	270	l/cap/d
q retirement homes =	450	l/cap/d
i =	0.28	l/s/ha
SING. HOUSING	3.4	pers/hse
MULT. HOUSING	2.7	pers/hse
Hotel/Appartments	1.8	pers/ro
Retirement Homes	1.6	pers/ro

Manning's Coefficient (n) =

-																				J.	Soemclent (n) =		2	2017 Updates	to Block 4,5	, West of 9 P	eak Flows]	
									ESIDENTIAL								RCIAL / INSTIT		PLUGG	ED FLOW		+C			SEWER	DATA		CAP	ACITY
STREET	M.H. #						NUMBER OF			1	r			PEAKING		Actual	CUMM.	COMM.		CUMM.	PEAK EXTR.				CAPAC.				
	FROM	то	SING.	Stack	s Towns No un	Ext. Care its Act. pop	No units	Hotel/Apar	t. Equ. pop.	POPUL. people	AREA ha	POPUL. people	AREA	FACTOR	FLOW I/s	AREA ha	AREA ha	FLOW I/s	FLOW I/s	FLOW I/s	FLOW I/s	FLOW I/s	DIA. mm	SLOPE %	l/s	VEL. m/s	LENGTH m	Residual (L/s)	% Full
	1 ICOM	10			No un	Act. pop	No units	Act. pop.	Equ. pop.	people	114	people	na		1/3	nu	na	13	13	1/3	13							(1/3)	
Robinson - 1996	Upstream	7A								(1) 2588	(1) 28.38	2588	28.38	3.50	36.65	(1) 20.37	20.37	17.68	(1) 162.69	162.69	14.01	231.04							
Claridge	Block 122 (per Robinson'96)	7A								377	0.89	377	0.89	4.00	6.11	0.005	0.005	0.004	(6) 0.83	0.83	0.25	7.19							
MARITIME WAY	7A	507										2965	29.27	3.45	41.40		20.38	17.69		163.52	14.26	236.87	825	0.14	529.34	0.99	81.90	292.47	45%
MARITIME WAT	507	506					125	225	174	174	1.02	3139	30.29	3.43	43.56	4.91	25.29	21.95		163.52	15.92	244.95	825	0.14	500.32	0.99	119.30	255.37	49%
CORDILLERA ST.	534	533	-				125	207	207	207	0.58	207	0.58	4.00	3.35	0.55	0.55	0.48			0.32	4.15	200	1.65	42.13	1.34	66.60	37.98	10%
CANADIAN SHIELD AV.	533	532										207	0.58	4.00	3.35		0.55	0.48			0.32	4.15	200	1.20	35.93	1.14	69.60	31.78	12%
CANADIAN SHIELD AV.	532	531	_								0.33	207	0.91	4.00	3.35		0.55	0.48			0.41	4.24	200	1.20	35.93	1.14	69.60	31.69	12%
GREAT LAKES AV.	536	531	-				100	180	139	139	0.78	139	0.78	4.00	2.25	0.04	0.04	0.03	(5) 0.30	0.30	0.23	2.81	200	2.40	50.81	1.62	60.00	48.00	6%
GREAT LAKES AV.	531	530										346	1.69	4.00	5.61		0.59	0.51		0.30	0.64	7.05	200	3.75	63.51	2.02	80.80	56.46	11%
GREAT LAKES AV. GREAT LAKES AV.	530 506A	506A 506	_								0.38	346 346	1.69 2.07	4.00	5.61 5.61		0.59	0.51 0.51		0.30	0.64	7.05 7.16	200 200	1.40 1.40	38.80 38.80	1.24 1.24	85.20 4.90	31.75 31.65	18% 18%
GREAT LAKES AV.	506A	506									0.36	340	2.07	4.00	5.61		0.59	0.51		0.30	0.74	7.10	200	1.40	30.00	1.24	4.90	31.05	10%
MARITIME WAY	506	505					176	316.8	269	269	0.57	3754	32.93	3.36	51.06		25.87	22.46		163.82	16.82	254.17	825	0.12	486.76	0.91	111.00	232.59	52%
MARITIME WAY	505	504			_ _		146	262.8	230	230	0.56	3984	33.49	3.33	53.82	1.75	27.62	23.98		163.82	17.47	259.09	825	0.11	484.63	0.91	114.40	225.55	53%
MARITIME WAY	504	501	+	+			+	+	+	+	0.27	3984	33.76	3.33	53.82		27.62	23.98	<u> </u>	163.82	17.55	259.16	825	0.11	476.06	0.89	29.90	216.89	54%
CANADIAN SHIELD AV.	542	541					176	316.8	269	269	0.74	269	0.74	4.00	4.36						0.21	4.57	200	2.20	48.64	1.55	71.30	44.08	9%
CANADIAN SHIELD AV.	541	540					154	277.2	232	232	0.51	501	1.25	3.97	8.06	1.36	1.36	1.18			0.73	9.98	200	0.90	31.13	0.99	77.70	21.15	32%
	Block 3	540	_		208	333	-	-	428	428	1.02	428	1.02	4.00	6.93						0.29	7.22	200	0.60	25.40	0.81	12.00	18.18	28%
	BIOCK 3	540			200	333			420	420	1.02	420	1.02	4.00	0.93						0.29	1.22	200	0.60	23.40	0.81	12.00	10.10	2076
CANADIAN SHIELD AV.	540	512	_								0.30	929	2.57	3.82	14.38		1.36	1.18			1.10	16.66	200	0.71	27.65	0.88	82.60	11.00	60%
MARITIME WAY	514	513												4.00									200	2.14	47.96	1.53	51.20	47.96	
MARITIME WAY (Block 4)	513	512					144	271	271	271	1.12	271	1.12	_	4.39						0.31	4.71	200	2.28	49.52	1.58	51.90	44.81	10%
MARITIME WAY	512	511	_						58	58	(2) 0.73	1258	4.42	3.73	19.02		1.36	1.18			1.62	21.82	200	3.12	57.95	1.84	49.30	36.12	38%
	012	•							50		(2) 0.70	1200	4.42	0.70	10.02		1.00	1.10			1.02	21.02	200	0.12	01.00	1.04	40.00	00.12	0070
	Block 5	511					154	301	301	301	0.92	301	0.92	4.00	4.88						0.26	5.13	200	2.00	46.38	1.48	12.20	41.25	11%
MARITIME WAY	511	510										1559	5.34	3.67	23.16		1.36	1.18			1.87	26.21	200	1.70	42.76	1.36	38.40	16.54	61%
MARITIME WAY	510	501										1559	5.34	3.67	23.16		1.36	1.18			1.87	26.21	200	2.28	49.52	1.58	11.30	23.30	53%
	501	500	_						-			55.40	00.00	0.00	74.00		00.00	05.40		100.00	40.40	000.00	005	0.40	400.00	0.07	100.00	400.57	040/
TRUNK EASEMENT TRUNK EASEMENT	500	500 94		-								5543 5543	39.09 39.09	3.20 3.20	71.92 71.92		28.98 28.98	25.16 25.16		163.82 163.82	19.42 19.42	280.32 280.32	825	0.10	462.89	0.87	129.00	182.57	61%
		0.										0010	00.00	0.20	11102		20.00	20.10		100.02	10.12	LOOIDE							
A	90	92			35					95	0.80	95	0.80	4.00	1.53						0.22	1.76	250	0.60	46.06	0.94	120.0	44.30	4%
	92	94			12		-	+	+	32	1.19	127	1.99	4.00	2.06						0.56	2.61	250	2.20	88.20	1.80	103.0	85.58	3%
	94	95		1								5670	41.08	3.19	73.36		28.98	25.16		163.82	19.98	282.31	825	0.12	497.22	0.93	17.5	214.91	57%
	95	89			10					27	0.52	5697	41.60	3.19	73.66		28.98	25.16		163.82	20.12	282.76	825	0.12	497.22	0.93	66.6	214.46	57%
<u> </u>		07	19					+		65	1.19	65	1.19	4.00	1.05						0.33	1.38	050	0.40	37.61	0.77	440.0	36.23	4%
В	85 87	87 89	19		24		1		-	65	0.82	129	2.01	4.00	2.10						0.56	2.66	250 250	0.40	70.70	1.44	116.9 116.7		4%
																							200				110.7		
А	89	84			12				+	32	0.35	5859	43.96	3.18	75.48		28.98	25.16		163.82	20.78	285.24	825	0.12	497.22	0.93	79.0	211.98	57%
С	80	82	19							65	1.08	65	1.08	4.00	1.05						0.30	1.35	250	0.40	37.61	0.77	120.0	36.26	4%
	82	84			25					68	0.83	132	1.91	4.00	2.14						0.53	2.68	250	1.20	65.18	1.33	118.5	62.51	4%
Α	84	79			14		-			38	0.54	6028	46.41	3.17	77.38		28.98	25.16		163.82	21.47	287.83	825	0.12	497.22	0.93	79.0	209.39	58%
							1	1	ļ	ļ								ļ	L	L									
D	75	76			17					46	0.37	46	0.37	4.00	0.74						0.10	0.85	250	0.40	37.61	0.77	57.0		2%
	76 77	77 79	+	-	20 13			+	+	54 35	0.29	100 135	0.66	4.00 4.00	1.62 2.19						0.18	1.80 2.55	250 250	0.40	37.61 53.66	0.77	78.4		5% 5%
		13									0.00				2.10						0.00	2.00	200	0.01	55.00		117.7	012	570
PARK EASEMENT	79	67									0.98	6163		-	78.89		28.98	25.16		163.82	22.11	289.97	825	0.12	497.22	0.93	55.0		58%
	67	66			6		1			16	0.33	6180	49.01	3.16	79.07		28.98	25.16		163.82	22.20	290.25	825	0.12	497.22	0.93	70.0	206.98	58%

R:\15000\15712-NAD83.LD\San & stm design\Rev 10 Aug 1, 2017 - Block 4,5,west of 9 peak Flow update\sanitary flow analysis.XLS

MASTER SANITARY SEWER DESIGN SHEET Designed: L.D.

2017 Update by: KF 2017 Check by: LD

Date: August 15, 2017

ers/hse

ers/hse

pers/room

pers/room 0.013



CITY OF OTTAWA

KANATA TOWN CENTRE CENTRAL BUSINESS DISTRICT URBANDALE CORPORATION JLR PROJECT NO.: 15712

Commercial Flow =	50000	L/ł
q residential=	350	l/ca
q hotel =	270	l/ca
q retirement homes =	450	l/ca
i =	0.28	l/s/
SING. HOUSING	3.4	pe
MULT. HOUSING	2.7	ре
Hotel/Appartments	1.8	F
Retirement Homes	1.6	F

Manning's Coefficient (n) = 0.013

																				manning 5	Coefficient (n) =	0.010	2	017 Update	s to Block 4,5	5, West of 9 F	Peak Flows	1	
betw betw <thw< th=""> betw betw be</thw<>									RESIDENTIAL							COMME	ERCIAL / INSTIT	UTIONAL	PLUGGE	ED FLOW	R	+C						CA	PACITY
Image: Problem integra Image: Problem integra Problem integro Problem integra <th< th=""><th>etdeet.</th><th>M.H. #</th><th></th><th></th><th></th><th></th><th></th><th>NUMBER OF U</th><th>INITS</th><th></th><th></th><th>CUM</th><th>IULATIVE</th><th>PEAKING</th><th>POPUL.</th><th>Actual</th><th>CUMM.</th><th>COMM.</th><th></th><th>CUMM.</th><th>PEAK EXTR.</th><th>PEAK DES.</th><th></th><th>1</th><th></th><th>1</th><th></th><th></th><th></th></th<>	etdeet.	M.H. #						NUMBER OF U	INITS			CUM	IULATIVE	PEAKING	POPUL.	Actual	CUMM.	COMM.		CUMM.	PEAK EXTR.	PEAK DES.		1		1			
Image Image <th< th=""><th>SIREEI</th><th></th><th></th><th>SING.</th><th>Stacks</th><th>Towns</th><th>Ext.</th><th>. Care</th><th>Hotel/Apart.</th><th>POPUL.</th><th>AREA</th><th>POPUL</th><th> AREA</th><th>FACTOR</th><th>FLOW</th><th>AREA</th><th>AREA</th><th>FLOW</th><th>FLOW</th><th>FLOW</th><th>FLOW</th><th>FLOW</th><th>DIA. mm</th><th>SLOPE %</th><th></th><th>VEL. m/s</th><th>LENGTH m</th><th>Residual</th><th>% Full</th></th<>	SIREEI			SING.	Stacks	Towns	Ext.	. Care	Hotel/Apart.	POPUL.	AREA	POPUL	AREA	FACTOR	FLOW	AREA	AREA	FLOW	FLOW	FLOW	FLOW	FLOW	DIA. mm	SLOPE %		VEL. m/s	LENGTH m	Residual	% Full
····································		FROM	то				No units	Act. pop No units	Act. pop. Equ. pop.	people	ha	people	ha		l/s	ha	ha	l/s	l/s	l/s	l/s	l/s						(L/s)	
····································				-	10					70	0.50	70	0.50	4.00							0.70	4.05			07.04	0.77		05.75	50/
Image Image <th< td=""><td>BELLROCK DRIVE</td><td></td><td>-</td><td>_</td><td>12</td><td></td><td></td><td></td><td></td><td></td><td></td><td>-</td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td>5% 7%</td></th<>	BELLROCK DRIVE		-	_	12							-																	5% 7%
Image Image <t< td=""><td>FACEMENT</td><td></td><td></td><td>-</td><td></td><td>12</td><td></td><td></td><td></td><td>32</td><td></td><td>-</td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td>7%</td></t<>	FACEMENT			-		12				32		-																	7%
Second Second Second Second </td <td></td> <td></td> <td></td> <td></td> <td></td> <td>25</td> <td></td> <td></td> <td></td> <td>68</td> <td></td> <td>-</td> <td></td> <td></td> <td>-</td> <td></td> <td>7%</td>						25				68		-			-														7%
Image: Property image:		02				20					0.10		0.00		2.70							0.00	230	0.77	02.10		100.5	10.00	
Important Important <t< td=""><td>BISHOPS MILLS WAY</td><td>66</td><td>65</td><td></td><td></td><td>9</td><td></td><td></td><td></td><td>24</td><td>0.53</td><td>6374</td><td>53.43</td><td>3.15</td><td>81.22</td><td></td><td>28.98</td><td>25.16</td><td></td><td>163.82</td><td>23.44</td><td>293.64</td><td>825</td><td>0.12</td><td>497.22</td><td>0.93</td><td>62.0</td><td>203.59</td><td>59%</td></t<>	BISHOPS MILLS WAY	66	65			9				24	0.53	6374	53.43	3.15	81.22		28.98	25.16		163.82	23.44	293.64	825	0.12	497.22	0.93	62.0	203.59	59%
Important Important <t< td=""><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></t<>																													
Image Image <th< td=""><td>SOUTH of HWY 417</td><td>EX.</td><td>65</td><td></td><td></td><td></td><td></td><td></td><td></td><td>(1) 7792</td><td>(1) 191.60</td><td>7792</td><td>191.60</td><td>3.06</td><td>96.63</td><td></td><td></td><td></td><td>(4) 37.72</td><td>37.72</td><td>53.65</td><td>188.00</td><td>900</td><td>0.11</td><td>600.38</td><td>0.94</td><td>50.2</td><td>412.38</td><td>31%</td></th<>	SOUTH of HWY 417	EX.	65							(1) 7792	(1) 191.60	7792	191.60	3.06	96.63				(4) 37.72	37.72	53.65	188.00	900	0.11	600.38	0.94	50.2	412.38	31%
Image Image <th< td=""><td></td><td></td><td></td><td>_</td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td>-</td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></th<>				_								-																	
And And <td>BISHOPS MILLS WAY</td> <td>65</td> <td>64</td> <td>_</td> <td></td> <td>2</td> <td></td> <td></td> <td></td> <td>5</td> <td></td> <td>14171</td> <td>245.03</td> <td>2.80</td> <td>160.92</td> <td></td> <td>28.98</td> <td>25.16</td> <td></td> <td>201.54</td> <td>77.08</td> <td>464.70</td> <td>900</td> <td>0.11</td> <td>600.38</td> <td>0.94</td> <td>17.0</td> <td>135.69</td> <td>77%</td>	BISHOPS MILLS WAY	65	64	_		2				5		14171	245.03	2.80	160.92		28.98	25.16		201.54	77.08	464.70	900	0.11	600.38	0.94	17.0	135.69	77%
And And <td></td> <td></td> <td></td> <td></td> <td></td> <td>0</td> <td></td> <td></td> <td></td> <td>22</td> <td>0.50</td> <td>22</td> <td>0.50</td> <td>4.00</td> <td>0.25</td> <td></td> <td></td> <td></td> <td></td> <td>1</td> <td>0.14</td> <td>0.40</td> <td></td> <td></td> <td>20.00</td> <td>4.04</td> <td></td> <td>20.24</td> <td>40/</td>						0				22	0.50	22	0.50	4.00	0.25					1	0.14	0.40			20.00	4.04		20.24	40/
Ome Des Des Des Des Des Des Des Des Des <				-	-							-								-									1% 4%
And model And model <t< td=""><td>KETTLEBY STREET</td><td>60</td><td>61</td><td>-</td><td></td><td>22</td><td></td><td></td><td></td><td>55</td><td>0.02</td><td>01</td><td>1.12</td><td>4.00</td><td>1.51</td><td></td><td></td><td></td><td></td><td></td><td>0.51</td><td>1.05</td><td>250</td><td>0.40</td><td>57.01</td><td>0.11</td><td>103.6</td><td>33.30</td><td>470</td></t<>	KETTLEBY STREET	60	61	-		22				55	0.02	01	1.12	4.00	1.51						0.51	1.05	250	0.40	57.01	0.11	103.6	33.30	470
And model And model <t< td=""><td>CAMBRAY LANE</td><td>58</td><td>61</td><td></td><td>1</td><td>5</td><td></td><td>+ +</td><td></td><td>14</td><td>0.41</td><td>14</td><td>0.41</td><td>4.00</td><td>0.22</td><td></td><td></td><td></td><td></td><td></td><td>0.11</td><td>0.33</td><td>200</td><td>0.70</td><td>27.44</td><td>0.87</td><td>74.5</td><td>27.10</td><td>1%</td></t<>	CAMBRAY LANE	58	61		1	5		+ +		14	0.41	14	0.41	4.00	0.22						0.11	0.33	200	0.70	27.44	0.87	74.5	27.10	1%
Partial Partial <t< td=""><td></td><td>-</td><td></td><td></td><td>1</td><td></td><td>1</td><td></td><td></td><td></td><td>1</td><td></td><td>1</td><td>1</td><td>1</td><td></td><td></td><td>1</td><td></td><td>t</td><td>1</td><td></td><td>H</td><td></td><td>1</td><td>1</td><td></td><td>1</td><td>1</td></t<>		-			1		1				1		1	1	1			1		t	1		H		1	1		1	1
no. no. <td>KETTLEBY STREET</td> <td>61</td> <td>64</td> <td></td> <td></td> <td>25</td> <td></td> <td></td> <td></td> <td>68</td> <td>0.42</td> <td>162</td> <td>1.95</td> <td>4.00</td> <td>2.63</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>0.55</td> <td>3.17</td> <td>250</td> <td>0.90</td> <td>56.41</td> <td>1.15</td> <td>105.0</td> <td>53.24</td> <td>6%</td>	KETTLEBY STREET	61	64			25				68	0.42	162	1.95	4.00	2.63						0.55	3.17	250	0.90	56.41	1.15	105.0	53.24	6%
no.																							Ц						
Image: Sector in the	BISHOPS MILLS WAY			_								-																	78%
Image: Second		63	57		<u> </u>	10		┥──┤		27	0.68	14369	247.66	2.80	162.80		28.98	25.16		201.54	77.82	467.32	900	0.11	600.38	0.94	64.9	133.06	78%
Image: Second				-	40					120	0.04	120	0.04	4.00	2.40						0.00	2.26			07.44	0.07		25.00	
Image Image <th< td=""><td>TER. BUNGALOW Ph.2</td><td></td><td></td><td>-</td><td></td><td></td><td></td><td></td><td></td><td></td><td>0.94</td><td>-</td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td>-</td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td>9% 9%</td></th<>	TER. BUNGALOW Ph.2			-							0.94	-								-									9% 9%
Image: Problem Image: Problem Image: Problem Image: Pr				-	4						0.27	-			-														9% 10%
Home	BISHOPS MILLS WAY			11						37		-																	9%
A A A B				7		12				56		-			-													-	10%
A A A B																													
Image: Problem Image: Problem Image: Problem Image: Pr	PARK	57	34			1				3	0.37	14605	250.70	2.79	165.06		28.98	25.16		201.54	78.67	470.43	900	0.11	600.38	0.94	53.5	129.95	78%
Image Image <th< td=""><td></td><td>34</td><td>33</td><td></td><td></td><td>3</td><td></td><td></td><td></td><td>8</td><td></td><td>14613</td><td>250.70</td><td>2.79</td><td>165.14</td><td></td><td>28.98</td><td>25.16</td><td></td><td>201.54</td><td>78.67</td><td>470.51</td><td>900</td><td>0.11</td><td>600.38</td><td>0.94</td><td>50.3</td><td>129.87</td><td>78%</td></th<>		34	33			3				8		14613	250.70	2.79	165.14		28.98	25.16		201.54	78.67	470.51	900	0.11	600.38	0.94	50.3	129.87	78%
Image: state Image: state<				_																									_ _ !
Image: bit in the state in thestate in the state in the state in the state in the stat	HAWKSTONE			-	-							-			-														2%
Here Here <th< td=""><td></td><td></td><td>-</td><td>_</td><td>8</td><td></td><td></td><td></td><td></td><td>22</td><td></td><td>-</td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td>4% 4%</td></th<>			-	_	8					22		-																	4% 4%
MAME MA MA MA MA MA<				7						24		_																	7%
1 1	BIRKENDALL DRIVE			13								-																	9%
And the and the and the and the analysis				2		3				15		-									0.93								10%
And the and the and the and the analysis																													
Mark 1 Mark 1<	BIRKENDALE DRIVE	33	32			10				27	0.56	14804	254.59	2.78	166.96		28.98	25.16		201.54	79.76	473.42	900	0.11	600.38	0.94	72.7	126.97	79%
Mark 1 Mark 1<				_								-																	!
Image: state	TEESWATER STREET		-									-															-		2%
18 16 16 1 4 1		31	32		-	19		+	<u>├</u>	51	0.41	95	1.07	4.00	1.53						0.30	1.83	250	0.40	37.61	0.77	77.9	35.78	5%
18 16 16 1 4 1		30	40	+		6		+ +		16	0.37	14915	256.03	2 78	168.01		28.98	25.16		201 54	80.16	474 87	000	0.11	600.38	0.94	A A A	125 51	79%
Normation	DIRRENDALE STREET			+	1		1	+ +			0.07	-												-					79%
COLCHESTER SQUARE 17 16 1		10	10		1	† ·		+ +			1												300	0.11					+
COLCHESTER SQUAR 17 16<	COMMERCIAL PLAZA	19	17											4.00		0.52	0.52	0.45			0.15	0.60	150	0.90	14.45	0.82	26.5	13.85	4%
And14A14A12211010010.030.042.081.281.28111100.010.		17	16								0.10		0.10	4.00			0.52	0.45			0.17	0.62		0.40	37.61	0.77	33.2	36.98	2%
15 14A 2 2 0 0 0 0 0 0.1 60.3 0.94 22.8 14.3 1 1 1 0 2 0 0 0 0 0.1 60.3 0.94 22.8 14.3 1 1 1 0 1 0 0 0 0.1 60.3 0.94 28.8 14.3 1 0 1 0 0 0 0 0 0.1 60.3 0.94 28.8 14.3 1 0 1 0 0 0 0 0 0 0 0 0 0.1 60.3 0.94 28.8 14.3 1 0 1 0 0 0 0 0 0 0 0 0 0 0.1 0											<u> </u>									L			μ	L		<u> </u>]
Image: bit in the state of the state o	COLCHESTER SQUARE			-	<u> </u>		ļ				0.56																		
Mark Mark <th< td=""><td></td><td>15</td><td>14 A</td><td></td><td><u> </u></td><td>2</td><td></td><td>+</td><td></td><td>5</td><td></td><td>14958</td><td>256.69</td><td>2.78</td><td>168.42</td><td></td><td>29.50</td><td>25.61</td><td></td><td>201.54</td><td>80.49</td><td>476.06</td><td>900</td><td>0.11</td><td>600.38</td><td>0.94</td><td>25.8</td><td>124.32</td><td>79%</td></th<>		15	14 A		<u> </u>	2		+		5		14958	256.69	2.78	168.42		29.50	25.61		201.54	80.49	476.06	900	0.11	600.38	0.94	25.8	124.32	79%
Mark Mark <th< td=""><td></td><td>00</td><td></td><td>-</td><td>22</td><td> </td><td></td><td>+</td><td></td><td>00</td><td>0.52</td><td>06</td><td>0.52</td><td>4.00</td><td>1.40</td><td></td><td></td><td></td><td></td><td> </td><td>0.15</td><td>1 55</td><td>070</td><td>4.00</td><td>50.46</td><td>1.01</td><td></td><td>57.01</td><td>20/</td></th<>		00		-	22			+		00	0.52	06	0.52	4.00	1.40						0.15	1 55	070	4.00	50.46	1.01		57.01	20/
24 23 12 <t< td=""><td>ELSINORE LANE</td><td></td><td></td><td>+</td><td></td><td></td><td></td><td>+ +</td><td></td><td></td><td></td><td>-</td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td><u> </u></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td>3% 7%</td></t<>	ELSINORE LANE			+				+ +				-								<u> </u>									3% 7%
LESINCE LARE 306 8 8 9				+			1	+ +												<u> </u>								-	
BUDENALE DRIVE 306 14A I	ELSINORE LANE			1				+ +				-								1									
And And Anticol And Anticol </td <td></td> <td></td> <td></td> <td></td> <td>1</td> <td></td> <td>1</td> <td></td> <td>t</td> <td></td> <td></td> <td></td> <td>-</td> <td></td> <td></td> <td></td> <td></td> <td></td>					1													1		t				-					
Image: Church Image: Church<	COLCHESTER SQUARE	14 A	14									15147	259.52	2.77	170.21		29.50	25.61		201.54	81.29	478.65	900	0.11	600.38	0.94	14.7	121.74	80%
Church 14 4.0 0.52 0.62 0.45 0.15 0.60 15.0 15.0 16.0 16.0 14.63 Image: Church					<u> </u>						<u> </u>		+							ļ			μ			<u> </u>			7
		Church	14	-	-	<u> </u>		<u> </u>	├ ───┤			-		4.00		0.52	0.52	0.45			0.15	0.60	150	1.00	15.23	0.86	35.0	14.63	4%
					I	l	I	1	I I		1	1		I	1	J I			J	L	1			I		1		I	

MASTER SANITARY SEWER DESIGN SHEET Designed: L.D.

2017 Update by: KF 2017 Check by: LD

Date: August 15, 2017

./ha/d /cap/d

. cap/d

cap/d

s/ha

ers/hse

oers/hse

pers/room

pers/room



CITY OF OTTAWA

KANATA TOWN CENTRE CENTRAL BUSINESS DISTRICT URBANDALE CORPORATION JLR PROJECT NO.: 15712

Commercial Flow = 50000 L/ha/d q residential= 350 q hotel = 270 q retirement homes = 450 i= 0.28 SING. HOUSING 3.4 pers/hse MULT. HOUSING 2.7 Hotel/Appartments 1.8 **Retirement Homes** 1.6

Manning's Coefficient (n) = 0.013

			-						RESIDENTIAL															2017 Updates		, West of 9 Pe	eak Flows		
									ESIDENTIAL					Lancour		Ļ	ERCIAL / INSTIT		PLUGG	ED FLOW		R+C			SEWER	DATA		CAP	PACITY
STREET	M.H. #	ŧ	CINC	Stacks Tow		t. Care	UMBER OF I	Hotel/Apar	+	POPUL.	AREA	_		-	FLOW	Actual AREA	CUMM. AREA	COMM. FLOW	FL OW	CUMM.		PEAK DES.	1	SLOPE %	CAPAC.	1000	1 510511		
	FROM	то	- Sing.	Stacks Town		Act. pop	No units		Equ. pop.		ha	people	1	FACTOR	I/s	ha	ha	I/s	FLOW	FLOW I/s	FLOW	FLOW	DIA. mm	SLOPE %	l/s	VEL. m/s	LENGTH m	Residual (L/s)	% Full
COLCHESTER SQUARE	14	11		4					1	11	0.16	15158	_	2.77	170.31		30.02	26.06		201.54	81.48	479.39	900	0.11	600.38	0.94	72.6		80%
TERON	11	10				1		1				15158	259.68	2.77	170.31		30.02	26.06		201.54	81.48	479.39	900	0.11	600.38	0.94	29.6		
	10	EX.									0.25	15158	259.93	2.77	170.31		30.02	26.06		201.54	81.55	479.46	900	0.11	600.38	0.94	72.3		
TERON	O.P.P.	EX.												4.00					0.78	0.78		0.78	100	Forcemain					
									_				L																
TERON	EX.	EX. 2	-									15158	259.93	2.77	170.31		30.02	26.06		202.32	81.55	480.24	680	0.96	838.61	2.31	9.4	358.37	57%
															-					+			/	+					
			-						1			1	1		1								I I –	1					
			(1)	As per Kanata	Town Centre S	anitary Trunk	Sewer Study.	revised Marc	h 27, 1996, by	Robinson Cons	ultants Inc.																		
			_			,	,,																₽					 	
			(2)	Park or open	snace area								-										₩						
				I alk of open	space area.																		/──		+	+			+
			(3)	Equivalent po	pulation base	e on 208 roor	ns and 20 st	aff members	S.																				-
			4																				Д						
			(4)	Allowance for Centre Sanita			s to provide f	lexibility in fu	uture develop	oment as per K	anata Town												#───		+				
			-	oontro ount	ing manifesta	<i></i>							1	1	+					+			/──			+		+	+
			(5)	Additional flo	w associated	with hotel arr	nmenities inc	luding swim	iming pool wit	th bathrooms a	and														1			<u> </u>	
				laundry as pe	er design calc	ulations for B	lock 1 provid	ded by WSP	October 20	16)														1					
			- (0)	Additional fla		with overall c		naludina has		aff, dining and								+	l				#					ļ	
			(6)							arr, dining and ement Home)					+								₩		+			<u> </u>	
			-	provided by N	-		200 10000000	s way (mine		sinent nome)													/}──	+	<u> </u>			<u> </u>	+
																							1					<u>† </u>	+
			_																	-			4						
			-																				₩	+	+			<u> </u>	+
				T	1	1	1			11	1	+		-	+								H		<u> </u>			+	+
			-	+ +				-		++		1	+	-					<u> · · · · · · · · · · · · · · · · · · ·</u>	1			H	+		+		<u>+</u>	



MASTER SANITARY SEWER DESIGN SHEET Designed: L.D.

2017 Update by: KF 2017 Check by: LD

Date: August 15, 2017


l/cap/d

l/cap/d

l/s/ha

pers/hse

pers/room pers/room






Table 4.7 - Revised as per RMOC Letter Dated March 27, 1996 KANATA TOWN CENTRE SANITARY TRUNK SEWER STUDY

Ultimate Development Flows Worksheet

Average Persons per Dwelling Unit

3.19

, s.

61.7

					Stn. Qp=	163 2 beds/r			q (res)= q (ret)= q (com)= q (hot)= Peaking fact 3.8		I/s x m2 I/s x m2 I/s x bed off & hot=	5000 5000 225 1.5	cu. m/ca l/1000m2 l/1000m2 l/bed x da	2 x day 2 x day	
					=		l/s/ha			persons/dw					
one	Area	Resident	ial Units	5	Retail		Office		Special Gen.		Peaking	Qp	Qi	Qtot	Cummu
		Low	Med	High	GLA (m2)	Emp.	Area (m2)	Emp.	Hotel Rooms	Emp.	Factor	(l/s)	(l/s)	(l/s)	Qtot (1/s
			0												
112	1.6		100		2230	47	5574	200							
111	2.2	1. A.S					Sec. Sec.							e e Pri	1
109	2.2		33				and the second		200	88					1 · · ·
115	0.8						1394	50	Sec. Same						
116	0.20													lise an	100.0
114	0.10														÷ .
118	1.7			50			9755	350							- 15g
120	1.1		87					1. A.	A Second		- markers		100.00		1.25
100	7.40		0 din 880.7 i	1000000000708.co	16908	386					4.00	1.47	2.07	3.54	166.6
101	1.30				4041	87					4.00	0.35	0.36	0.71	167.3
102	0.80				1579	34					4.00	0.14	0.22	0.36	167.7
104	1.50			168	10080	217					4.00	6.86	0.42	7.28	174.9
110	8.20		300	.00	10000	~					3.68	16.98	2.30	19.28	193.
103	13.30				74459	1603					3.68	6.46	3.72	10.19	203.9
105	2.10			90	8826	190					3.64	3.68	0.59	4.27	203.3
105	1.50	,		50	3298	71					3.64	0.29	0.42	0.71	208.7
117	0.04				3290	71					3.64	0.29	0.42	0.01	208.
	2.60		- 1	100	2230	47	34838	1250			3.60	6.42	0.01	7.15	
119				100	2230	4/	34030	1200	100	88		0.42			215.
107	9.10								100	88	3.60		2.55	3.33	218.
113	2.10			300	2230	47	16722	600			3.50	10.99	0.59	11.58	229.
121	0.10						19509	700			3.50	1.69	0.03	1.72	231.
122	1.50				_		27870	1000			3.50	2.42	0.42	2.84	233.
123	1.70		72	50			1394	50			3.45	5.48	0.48	5.95	239.3
124	0.60							-			3.45	0.00	0.17	0.17	239.
125	1.40										3.45	0.00	0.39	0.39	239.
126	2.80										3.45	0.00	0.78	0.78	240.6
127	1.80		80				4181	150			3.41	4.56	0.50	5.07	245.2
128	1.20		36				4181	150			3.39	2.24	0.34	2.58	247.6
129	1.70		70				6968	250			3.37	4.23	0.48	4.71	251.
130	1.10						11148	400			3.37	0.97	0.31	1.28	253.2
131	2.00										3.37	0.00	0.56	0.56	253.
132	0.60		40			-					3.35	2.06	0.17	2.23	255.
133	0.60										3.35	0.00	0.17	0.17	255.
134	0.70		Surger Street of the local division of the l				4181	150	-		3.35	0.36	0.20	0.56	256.
135	0.60		36								3.34	1.85	0.17	2.02	258.
136	1.00		18								3.33	0.92	0.28	1.20	259.
137	0.80	10	18								3.32	1.43	0.22	1.65	260.
138	1.50		93								3.29	4.71	0.42	5.13	265.
139	0.80	18	8								3.28	1.31	0.22	1.54	266.
156	1.10	"I	37								3.27	1.86	0.31	2.17	268.
140	0.90	8	27								3.26	1.75	0.25	2.01	270.
141	1.00	l vl	59								3.24	2.94	0.28	3.22	273.
142	0.50		59								3.24	0.00	0.14	0.14	273.
	0.50		24		1						3.24	1.69	0.14	1.86	275.
144			34								3.23	1.98	0.17	2.29	275.
143	1.10	10	30											4.88	281.
145	1.30		92								3.19	4.52	0.36	4.88	281.
146	1.00	16	19				1				3.18	1.71	0.28		285.
108	1.20		34								3.17	1.66	0.34	2.00	
148	1.00	8	18								3.17	1.27	0.28	1.55	286.
150	0.70		11								3.16	0.54	0.20	0.73	287.
151	0.30										3.16	0.00	0.08	0.08	287.
152	2.00		. 1								3.16	0.00	0.56	0.56	287.
	1.20	I	66								3.15	3.20	0.34	3.53	291.
154		I					3177	114			3.15	0.28	0.50	0.78	291.
	1.80														294.
154	1.80 1.30		49								3.13	2.36	0.36	2.73	
154 155			49	100							3.13	2.36 2.78	0.36	3.00	296.
154 155 147	1.30		49	100	1858	39								2.73 3.00 0.33	

Combined Down Stream Flow

425.64

J.L.RICHARDS & ASSOCIATES LIMITED, Consulting Engineers, Architects & Planners

q (res) = 350 q (com) = 50,000 q (inst) = 50,000

I = 0.280

l/cap/day l/ha/day l/ha/day

l/s/ha

1. 1. 1. 1. 1.

× × ×,


SANITARY SEWER DESIGN SHEET

KANATA TOWN CENTRE (RESIDENTIAL)

CITY OF KANATA

= Singles, Townhouses, Ter. Bungalows =	0.280 3.8	l/s/ha pers / unit	(low & medium	donaity				TOWN						Designed by:	L∗N.D.
Stacked Townhouses / Apartments =	2.2	pers / unit	、 (high density)	density)		U			AL) RPORATIO	N				Checked by.	M-F.S-
Stacked Townhouses / Apartments =	80	units / ha	(high density)												
STREET		.H. #	Singles &	UNITS Stacked	AREA	CUMMU POPUL.	AREA	Peaking Factor	POPUL. FLOW	INFIL. FLOW	PEAK FLOW	DIA	Slope	SEWER DATA CAPAC.	VEL.
	FROM	то	Townhouses	Townhouses	ha	peop.	ha	4.00	I/s	I/s	1/5	mm	%	I/s	m/s
A	90 92	92: 94	37 13		0.80	141 190	0.80	4.00	2.28	0.22	2.50 3.64	250 250	0.60 2.20	46.06 88.20	(
	94 95	95 89	10		66.80 0.52	4831 4869	68.79 69.31	3.26 3.26	63.77 64.21	19.26 19.41	270.61 271.20	825 825	0.12 0.12	497.22 497.22	(
В	85 87	87 89	19		1.19 0.82	72	1.19	4.00 4.00	1.17 2.77	0.33 0.56	1.50	250 250	0.40	37.61	(
A	89	84	26		0.35	171 5085	2.01 71.67	3.24	66.71	20.07	3.33 274.35	825	1.41	70.70	
c	80	82	20		1.08	76	1.08	4.00	1.23	0.30	1.53	250	0.12	497.22 37.61	
, , , , , , , , , , , , , , , , , , ,	82	84	28		0.83	182	1.91	4.00	2.96	0.53	3.49	250	1.20	65.18	
A	84	79	14		0.54	5321	74.12	3.22	69.40	20.75	277.74	825	0.12	497.22	
D	75 76	76 77	19 20		0.37 0.29	72 148	0.37 0.66	4.00 4.00	1.17 2.40	0.10 0.18	1.27 2.59	250 250	0.40	37.61 37.61	
	77	79	14		0.63	201	1.29	4.00	3.26	0.36	3.62	250	0.81	53.66	
PARK EASEMENT	79 67	67 66	6		0.98 0.33	5522 5545	76.39 76.72	3.20 3.20	71.69 71.95	21.39 21.48	280.66 281.01	825 825	0.12 0.12	497.22 497.22	
BELLROCK DRIVE	70	73	26		2.56	99	2.56	4.00	1.60	0.72	2.32	250	0.40	37.61	
EASEMENT	73 74	74 62	10		0.54 0.31	137 137	3.10 3.41	4.00 4.00	2.22 2.22	0.87 0.95	3.08 3.17	250 250	0.40 0.40	37.61 37.61	
	62	66	25		0.48	232	3.89	4.00	3.76	1.09	4.85	250	0.77	52.18	
BISHOPS MILLS WAY	66 EX	65	9		0.53	5811	81.14 191.60	3.18	74.95	22.72	285.25	825	0.12	497.22	
SOUTH of HWY 417 BISHOPS MILLS WAY	EX. 65	64	2		191.60	13610	272.74	3.06 2.82	96.63 155.52	53.65 76.37	188.16 457.35	900	0.11	600.38	
EDENVALE DRIVE	59	60	8		0.50	30	0.50	4.00	0.49	0.14	0.63	200	0.11	600.38	
KETTLEBY STREET	60	61	24	-	0.62	122	1.12	4.00	1.97	0.31	2.28	250	1.40 0.40	38.80 37.61	(
CAMBRAY LANE	58	61	8		0.41	30	0.41	4.00	0.49	0.11	0.61	200	0.70	27.44	
KETTLEBY STREET	61	64	25		0.42	247	1.95	4.00	4.00	0.55	4.55	250	0.90	56.41	
BISHOPS MILLS WAY	64 63	63 57	3 10		0.68	13869 13907	274.69 275.37	2.81 2.81	158.01 158.38	76.91 77.10	460.38 460.94	900 900	0.11	600.38 600.38	
TER. BUNGALOW Ph.2	51	53	48		0.94	182	0.94	4.00	2.96	0.26	3.22	200	0.70	27.44	
	53 54	54 55	4		0.27	198 198	0.94 1.21	4.00 4.00	3.20 3.20	0.26 0.34	3.47 3.54	200 200	0.70 0.70	27.44 27.44	
BISHOPS MILLS WAY	55 56	56 57	11 19		0.81 0.65	239 312	2.02 2.67	4.00 4.00	3.88 5.05	0.57 0.75	4.44 5.80	250 250	0.40 0.60	37. ⁶ 1 46.06	
PARK	57 34	34 33	1		0.37	14222	278.41	2.80 2.80	161.40	77.95 77.95	464.82	900	0.11	600.38	
HAWKSTONE	43	44	3 16		1.19	14234	278.41	4.00	161.51 0.99	0.33	464.93 1.32	900 250	0.11	600.38 59.46	
ENDENVALE	44 45	45	8		0.09	91	1.28	4.00	1.48	0.36	1.84	250 250 250	0.50	42.05	
BIRKENDALE DRIVE	35 36	36 37	7 13		1.18	118	2.54	4.00 4.00	1.91 2.71	0.71	2.62 3.64	250 250	0.37	36.18 36.09	
	37	33	2		0.00	175		4.00	2.83	0.93	3.76	250	0.40	37.61	
BIRKENDALE DRIVE	33	32	13		0.56	14458	282.30	2.79	163.66	79.04	468.16	900	0.11	600.38	
TEESWATER STREET	30 31	31 32	18 19		0.66 0.41	68 141	0.66 1.07	4.00 4.00	1.11 2.28	0.18 0.30	1.29 2.58	250 250	0.40 0.40	37.61 37.61	
BIRKENDALE STREET	32	18	4		0.37	14614	283.74	2.79	165.14	79.45	470.05	900	0.11	600.38	
COMMERCIAL PLAZA	18	16	6		0.50	14636	283.74	2.79	165.36	79.45	470.27	900	0.11	600.38	
COLCHESTER SQUARE	19 17	16			0.52 0.10	0	0.52 0 62	1.50 4.00	0.45 0.45	0.15 0.17	0.60 0.62	150 250	0.90 0.40	14.45 37.61	
COLCHESTER SQUARE	16 15	15 14 A	10 2		0.56	14674 14682	284 92 284 92	2.79 2.79	166.17 166.25	79.78 79.78		900	0.11	600.38 600.38	(
ELSINORE LANE	39	28	22		0.53	84	0.53	4.00	1.35	0.15	1.50	250	1.00	59.46	
	28 24	24 23	14 12		1.47 0.14	137	2.00	4.00	2.22 2.96	0.56 0.60	2.78	250 250	0.40	37.61	
ELSINORE LANE ENDENVALE DRIVE	23 306	306 14 A	8		0.24 0.45	213 213	2.38 2.83	4.00 4.00	3.45 3.45	0.67 0.79	4.11	250 250	0.44	39.41 41.68	
COLCHESTER SQUARE	14 A	14				14895	287.75	2.78	167.82	80.57	473.85	900	0.11	600.38	
	Church	14			0.52	0		1.50	0.45	0.15		150	1.00	15.23	
COLCHESTER SQUARE	14	11	4		0.16	14910		2.78	168.87	80.76		900	0.11	600.38	
TERON	11 10	10 EX.			0.25	14910 14910	288.43 288.68	2.78 2.78	168.87 168.87	80.76 80.83		900 900	0.11 0.11	600.38 600.38	
TERON	OPP.	EX.									0.78	100	Forcemain		
TERON	EX.	EX									475.94	680	0.96	838.61	:

'EL. n/s	LENGTH m
0.94	120.0
1 80	103.0
0.93 0.93	17.5 66.6
0.77 1.44	116.9 116.7
0.93	79.0
0.77 1.33	120.0 118.5
0.93	79.0
0.77	57.0
0.77 1.09	78.4 117.7
0.93 0.93	55.0 70.0
0.77	87.2
0.77 0.77 1.06	60.3 39.9 100.5
0.93	62.0
0.94	50.2
0.94	17.0
1.24 0.77	77.0 103.6
0.87	74.5
1.15	105.0
0.94 0.94	13.0 64.9
0.87	122.3
0.87 0.87	13.6 36.7
0.77 0.94	36.7 107.1 101.5
0.94 0.94	53.5 50.3
1.21 0.85	51.0 29.0
0.86	39.8
0.74 0.74 0.77	93.2 77.1 17.9
0.94	72.7
0.77 0.77	75.1 77.9
0.9 <i>4</i> 0.94	44.4
0.8.2	26.5
0.77 0.94	33.2 66.0
0.94	25.8
1.21	56.7 43.0
0.77	34.0 48.8
0.85	46.4
0.91	14.7
0.86	35.0
0.94 0.94 0.94	72.6 29.6 72.3
0.36	12.3
2.31	9.4



Karla Ferrey

From: Sent: To: Subject: Attachments: Lucie Dalrymple August 1, 2017 9:43 AM Karla Ferrey FW: Kanata Town Centre - Sanitary Flows 1088 San Drainage.pdf; 1136 San Drainage.pdf

...here it is

Lucie Dalrymple, P.Eng. Associate Senior Civil Engineer

J.L. Richards & Associates Limited 864 Lady Ellen Place, Ottawa, ON K1Z 5M2 Tel: 613-728-3571 Fax: 613-728-6012

J.L. Richards & Associates Limited ENGINEERS · ARCHITECTS · PLANNERS



From: Matthew Hrehoriak [mailto:m.hrehoriak@novatech-eng.com] Sent: July 31, 2017 10:16 AM To: Lucie Dalrymple Subject: RE: Kanata Town Centre - Sanitary Flows

Hi Lucie,

The sanitary info for the block 4 and 5 developments are as follows:

1088 Maritime Way (Block 4)

San service connection between SANMH 512-513 San Drainage Area = 1.121 ha No. Units = 144 Population = 271


1136 Maritime Way (Block 5)


San service connection between SANMH 510-511 San Drainage Area = 0.915 ha No. Units = 154 Population = 301

Regards,

Matthew Hrehoriak, B.Eng., EIT

NOVATECH Engineers, Planners & Landscape Architects 240 Michael Cowpland Drive, Suite 200, Ottawa, ON, K2M 1P6 | Tel: 613.254.9643 x 273 | Fax: 613.254.5867 The information contained in this email message is confidential and is for exclusive use of the addressee.





SHT11X17.DWG - 279mmX432mm

SANITARY SEWER DESIGN SHEET 1250 Maritime Way Timberwalk Retirement Home Developer: Claridge Homes

Date: 31-Jul-17

Designed: CMS Checked: GJM

Locatio	n				RE	SIDE	NTIAL				IN	STITU	TIONA	L	C	OMME							0	THER						INFILT	RATION				P	IPE		
			1 Be	droom	2 Be	droom	Тс	otal (R	esidenti	al)		Assist	ed Care		Con	venience	Store		Staff		Be	eauty Sal	lon	1	aundry			Dining			Infilt.	Total			\square		Full	
ID	From	То	Units	Pop.	Units	Рор	o. Pop				Jnits / Bed	Pop.	Peak Factor	Flow (L/s)			Flow (L/s)	Pop.	Peak Factor	Flow (L/s)	Stations	Peak Factor	Flow (L/s)	Machines	Peak Factor	Flow (L/s)	Seats	Peak Factor	Flow (L/s)	Total Area (ha)		Flow (L/s)	Size (mm)	Slope (%)	Length (m)	Capacity (I/s)	Flow Vel. (m/s)	Q/Q _{fu} (%)
Part A (current application)	BLD-1	MH101	92	129.0	8	17.0	0 146.	0	4.0	2.37	54	60.0	1.5	0.47	50	1.5	0.004	20	1.5	0.10	2	1.5	0.02	6	1.5	0.13	55	1.5	0.11	0.48	0.13	3.33	200	2.00	2.5	48.4	1.49	6.9%
Part A (current application)	MH101	TEE-1	0	0.0	0	0.0	146.	0	4.0	2.37	0	0.0	1.5	0.47	0	1.5	0.004	0	1.5	0.10	0	1.5	0.02	0	1.5	0.13	0	1.5	0.11	0.00	0.13	3.33	200	2.00	13.4	48.4	1.49	6.9%
		-																						•					-									
Part B (future application)	BLD-2	MH103	0	0.0	110	231.	.0 231.	0	4.0 ;	3.74	0	0.0	1.5	0.00	0	1.5	0.000	0	1.5	0.00	0	1.5	0.00	0	1.5	0.00	0	1.5	0.00	0.41	0.11	3.86	200	2.00	2.5	48.4	1.49	8.0%
Part B (future application)	MH103	TEE-2	0	0.0	0	0.0	231.	0	4.0 3	3.74	0	0.0	1.5	0.00	0	1.5	0.000	0	1.5	0.00	0	1.5	0.00	0	1.5	0.00	0	1.5	0.00	0.00	0.11	3.86	200	2.00	13.4	48.4	1.49	8.0%
	1			1		1													1	1			1	•	1	1		1	•		1		<u>.</u>					
TOTAL (Parts A + B)	-	-	92	129.0	118	248.	.0 377.	0	4.0	6.11	54	60.0	1.5	0.47	50	1.5	0.004	20	1.5	0.10	2	1.5	0.02	6	1.5	0.13	55	1.5	0.11	0.89	0.25	7.18	200	2.00	2.5	48.4	1.49	14.89
Design Parameters: Residential Institutional Commercial Staff Beauty Salon Laundy Dining Infiltration	45) 275 650 1200 115	0 L/cap/da 0 L/bed/da 5 L/m ² pe 5 L/cap/da 0 L/day pe 0 L/day pe 5 L/seat/d 3 L/s/ha	ay day ay er station er machir		Peakin Reside Instituti Commo Other	ntial onal		on Equ	uation (m	ax 4, mi	n 2)	1.40 2.10	Jnit: Assisted 1 Bedroo 2 Bedroo Studio	m																								
lotes: . The harmon peaking factor . Residential flows were used . Institutional flow used for as	for senior a	apartment	s (350 L/	cap/day.	Harmon	Peaking	Factor)	ed Oct	ober 12th	n, 2016																												

Institutional now used for assisted care units (450 L/bed/day, Peaking Factor = 1.5)
 Future building assumed to be a 10 storey building comprised of 110 2 bedroom units



END OF J.L RICHARDS MEMORANDUM

Matthew Linton

From: Sent: To: Cc: Subject: Mike Traub <mike.traub@claridgehomes.com> July-13-17 1:12 PM Matthew Linton Pascal Vendette; Conrad Stang Re: FW: 1250 Maritime Way - Sanitary

Hi Matt,

There will be two stations in the hair salon and about 55 seats in the main dining room.

Let me know if you have any further questions.

Thanks,

Mike

On Wed, Jul 12, 2017 at 4:40 PM, Matthew Linton <m.linton@novatech-eng.com> wrote:

Pascal/Mike,

Could we obtain some clarifications on the following below? This is for city comments as they are stating our assumed values seem low.

Thanks,

Matthew Linton, CAD Technologist

NOVATECH Engineers, Planners & Landscape Architects

240 Michael Cowpland Drive, Suite 200, Ottawa, ON, K2M 1P6 | Tel: 613.254.9643 Ext: 207 | Fax: 613.254.5867

The information contained in this email message is confidential and is for exclusive use of the addressee.

From: Conrad Stang Sent: July-12-17 3:55 PM

Matthew Linton

From: Sent: To: Subject: Pascal Vendette <pascal@neufarchitectes.com> May-01-17 1:39 PM Matthew Linton RE: Unit Counts - Timberwalk (Maritime Way)

2nd floor : 28 assisted care units 3rd floor : 26 assisted care units 4th to 7th floor : 25 units 6 suites 17 1br 2 br



PASCAL VENDETTE

Technologue senior en architecture Senior Architectural Technologist T 514 847 1117 #269 F 514 847 2287 C 514 833 6005 630, boul. René-Lévesque O. 32° étage, Montréal (QC) H3B 1S6 47 Clarence Street, suite 406, Ottawa (ON) K1N 9K1 **NEUF ARCHITECTES** SENCRL

Politiques de transmission et de confidentialité de NEUF architect(e)s NEUF architect(e)s transmission and confidentiality policy

De : Matthew Linton [mailto:m.linton@novatech-eng.com] Envoyé : 1 mai 2017 11:21 À : Pascal Vendette <pascal@neufarchitectes.com> Objet : Unit Counts - Timberwalk (Maritime Way)

Pascal,

Can you please send us over either the calculated dwelling units (I see you have the dwelling units on drawing A050 however we need to know 1 bedroom, 2 bedroom, etc.) or floor plans for each of the floors for the retirement home?

Thanks,

Matthew Linton, CAD Technologist

NOVATECH Engineers, Planners & Landscape Architects 240 Michael Cowpland Drive, Suite 200, Ottawa, ON, K2M 1P6 | Tel: 613.254.9643 Ext: 207 | Fax: 613.254.5867 The information contained in this email message is confidential and is for exclusive use of the addressee.

Matthew Linton

From:	Pascal Vendette <pascal@neufarchitectes.com></pascal@neufarchitectes.com>
Sent:	July-13-17 9:49 AM
To:	Matthew Linton
Cc:	mike.traub@claridgehomes.com; Conrad Stang
Subject:	RE: 1250 Maritime Way - Sanitary
Follow Up Flag:	Follow up
Flag Status:	Completed

Hi Matthew. Sorry for the dealy ... it's crazy here.

Here is my response to item #1.

There are commercial washers-dryers in the basement ...

- 2 gas heater tumble dryers 75 lbs
- 1 high-performance washer extractor 65 lbs
- 1 cabinet hardmount washer extractor 20 lbs

... and residential type washer-dryer (one of each) on floors 4 to 7

Mike can you please take care of items #2 & #3.

Best regards,



PASCAL VENDETTE

Technologue senior en architecture Senior Architectural Technologist T 514 847 1117 #269 F 514 847 2287 C 514 833 6005 630, boul. René-Lévesque O. 32° étage, Montréal (QC) H3B 1S6 47 Clarence Street, suite 406, Ottawa (ON) K1N 9K1 **NEUF ARCHITECTES** SENCRL

Politiques de transmission et de confidentialité de NEUF architect(e)s NEUF architect(e)s transmission and confidentiality policy

De : Matthew Linton [mailto:m.linton@novatech-eng.com]
Envoyé : 13 juillet 2017 09:38
À : Pascal Vendette <pascal@neufarchitectes.com>
Cc : mike.traub@claridgehomes.com; Conrad Stang <c.stang@novatech-eng.com>
Objet : RE: 1250 Maritime Way - Sanitary

Pascal,

Can we have some clarification on this?

SANITARY SEWER DESIGN SHEET 1250 Maritime Way Timberwalk Retirement Home Developer: Claridge Homes

Date: 30-Nov-17

Designed: CMS Revised: JDM Checked: GJM

			1 Poo	-							101110	JTIONA	L		MMEC	IAL						01	THER						INFILTR	ATION				Г	IPE	
			I Deu	lroom	2 Bec	Iroom	Tota	(Resider	itial)		Assist	ed Care		Conv	enience	Store		Staff		Be	auty Salo	n	L	aundry			Dining			Infilt.	Total					Full
ID	From	То	Units	Pop.	Units	Pop.	Pop.	Peak Factor	Flow (L/s)	Units / Bed	Pop.	Peak Factor	Flow (L/s)	Area (m2)		Flow (L/s)	Pop.	Peak Factor	Flow (L/s)	Stations	Peak Factor	Flow (L/s)	Machines	Peak Factor	Flow (L/s)	Seats	Peak Factor	Flow (L/s)	Total Area (ha)	Flow (L/s)	(L/s)	Size (mm)	Slope (%)	Length (m)	Capacity (I/s)	/ Flow Q// Vel. (9 (m/s)
art A (current application)	BLD1	MH4	92	129.0	8	17.0	146.0	4.0	2.37	54	60.0	1.5	0.47	100	1.5	0.009	20	1.5	0.10	2	1.5	0.02	6	1.5	0.13	55	1.5	0.11	0.48	0.13	3.33	200	2.66	9.6	55.8	1.72 6.
art A (current application)	MH4	MH2	0	0.0	0	0.0	146.0	4.0	2.37	0	0.0	1.5	0.47	0	1.5	0.009	0	1.5	0.10	0	1.5	0.02	0	1.5	0.13	0	1.5	0.11	0.00	0.13	3.33	200	2.70	27.8	56.2	1.73 5.
														•		-					, ,		•													
Part B (future application) FU	UT-BLD2	MH2	0	0.0	110	231.0	231.0	4.0	3.74	0	0.0	1.5	0.00	0	1.5	0.000	0	1.5	0.00	0	1.5	0.00	0	1.5	0.00	0	1.5	0.00	0.41	0.11	3.86	200	2.00	2.5	48.4	1.49 8.
										-																		-		-						
TOTAL (Parts A + B)	MH2	EX MH	92	129.0	118	248.0	377.0	4.0	6.11	54	60.0	1.5	0.47	100	1.5	0.009	20	1.5	0.10	2	1.5	0.02	6	1.5	0.13	55	1.5	0.11	0.89	0.25	7.19	200	1.50	13.8	41.9	1.29 17
sign Parameters: sidential litutional mmercial ff auty Salon undy ing ltration	450 5 275 650 1200	L/cap/da L/bed/da L/m ² per L/cap/da L/day pe L/day pe L/seat/da L/s/ha	y day y r station r machin		Peaking Resident Institution Commer Other	nal cial	Harmon 1.5 1.5 1.5	Equation (max 4, m		1.40 2.10	Unit: Assisted 1 Bedroo 2 Bedroo Studio	m																				PROFES	Ň	ENGINEER FO	

Restutential nows were used for senior apartments (350 D/cap/day, namon Peaking r.)
 Institutional flow used for assisted care units (450 L/bed/day, Peaking Factor = 1.5)
 Future building assumed to be a 10 storey building comprised of 110 2 bedroom units


M:\2016\116043\DATA\Calculations\Sewer Calcs\SAN\20171130-SAN.xlsx






APPENDIX C

Stormwater Management Calculations





3. TOTAL AREA: 1.24 ha

SCALE	DESIGN	FOR REVIEW ONLY		LOCATION
1:250			ΝΟΛΤΞΟΗ	CITY OF OTTAWA MARITIME WAY - KANATA RENTAL
1.200	GJM DRAWN CJF		Engineers, Planners & Landscape Architects Suite 200, 240 Michael Cowpland Drive	DRAWING NAME STORM WATER
1:250 4 6 8 10	CHECKED JAG		Ottawa, Ontario, Canada K2M 1P6 Telephone (613) 254-9643 Facsimile (613) 254-5867 Website www.novatech-eng.com	MANAGEMENT PLAN
	approved GJM			



120144 REV # 5 /ING No. 120144-SWM City Plan #18348



TABLE 1A: Allowable Runoff Coefficient "C"

Area	"C"	
Total	0.80	
1.238	0.00	

TABLE 1B: Allowable Flows

Outlet Options	Area (ha)	"C"	Tc (min)	Q _{5 Year} (L/s)	Q _{ALLOW} (L/s)
	1.238	0.80	20	193.4	193.4

Time of Concentration	Tc=	20	min
Intensity (2 Year Event)	I ₂ =	52.03	mm/hr
Intensity (5 Year Event)	I ₅ =	70.25	mm/hr
Intensity (100 Year Event)	I ₁₀₀ =	119.95	mm/hr

Equations: Flow Equation Q = 2.78 x C x I x A Where: C is the runoff coefficient I is the rainfall intensity, City of Ottawa IDF A is the total drainage area

100 year Intensity = 1735.688 / (Time in min + 6.014)^{0.820} 5 year Intensity = 998.071 / (Time in min + 6.053)^{0.814} 2 year Intensity = 732.951 / (Time in min + 6.199)^{0.810}



TABLE 2A: Post-Development Runoff Coefficient "C" - D1

Area	Surface	Ha	"C"	C _{avg}	*C ₁₀₀	Runoff Coefficient Equation
Total	Hard	0.015	0.90	0.57	0.65	$C = (A_{hard} \times 0.9 + A_{soft} \times 0.2)/$
0.029	Soft	0.013	0.20	0.57	0.05	* Runoff Coefficient increases
						25% up to a maximum value

TABLE 2B: Post-Development D1 Flows

Outlet Options	Area (ha)	Cavg	Tc (min)	Q _{2 Year} (L/s)	Q _{5 Year} (L/s)	Q _{100 Year} (L/s)
	0.029	0.57	10	3.5	4.8	9.2

Time of Concentration	Tc=	10	min
Intensity (2 Year Event)	I ₂ =	76.81	mm/hr
Intensity (5 Year Event)	I ₅ =	104.19	mm/hr
Intensity (100 Year Event)	I ₁₀₀ =	178.56	mm/hr

soft x 0.2)/A_{Tot} increases by 25% up to a maximum value of 1.00 for the 100-Year event

Equations: Flow Equation Q = 2.78 x C x I x A Where:

100 year Intensity = 1735.688 / (Time in min + 6.014)^{0.820} 5 year Intensity = 998.071 / (Time in min + 6.053)^{0.814} 2 year Intensity = 732.951 / (Time in min + 6.199)^{0.810}

C is the runoff coefficient I is the rainfall intensity, City of Ottawa IDF

A is the total drainage area



TABLE 3A: Post-Development Runoff Coefficient "C" - D2

Area	Surface	Ha	"C"	C _{avg}	*C ₁₀₀	Runoff Coefficient Equation
Total	Hard	0.000	0.90	0.20		$C = (A_{hard} \times 0.9 + A_{soft} \times 0.2)/A_{Tot}$
0.008	Soft	0.008	0.20	0.20	0.25	* Runoff Coefficient increases by
						2E0/ up to a maximum value of

nt increases by 25% up to a maximum value of 1.00 for the 100-Year event

TABLE 3B: Post-Development D2 Flows

Outlet Options	Area (ha)	C _{avg}	Tc (min)	Q _{2 Year} (L/s)	Q _{5 Year} (L/s)	Q _{100 Year} (L/s)
	0.008	0.20	10	0.3	0.5	1.0

Time of Concentration	Tc=	10	min
Intensity (2 Year Event)	$I_2 =$	76.81	mm/hr
Intensity (5 Year Event)	I ₅ =	104.19	mm/hr
Intensity (100 Year Event)	I ₁₀₀ =	178.56	mm/hr

Equations: Flow Equation Q = 2.78 x C x I x A Where:

C is the runoff coefficient

100 year Intensity = 1735.688 / (Time in min + 6.014)^{0.820} 5 year Intensity = 998.071 / (Time in min + 6.053)^{0.814} 2 year Intensity = 732.951 / (Time in min + 6.199)^{0.810}

I is the rainfall intensity, City of Ottawa IDF A is the total drainage area



TABLE 4A: Post-Development Runoff Coefficient "C" - A-02

	5 Year Event			100 Yea	ar Event	
Area	Surface	Ha	"C"	C_{avg}	"C" + 25%	*C _{avg}
Total	Hard	0.075	0.90		1.00	
0.290	Roof	0.000	0.90	0.38	1.00	0.44
0.290	Soft	0.215	0.20		0.25	

TABLE 4B: 5 YEAR EVENT QUANTITY STORAGE REQUIREMENT - A-02

0.290 =Area (ha) 0.38 = C

-	0.00	•					
I					Allowable	Net Flow	
I	Return	Time	Intensity	Flow	Runoff	to be Stored	Storage
	Period	(min)	(mm/hr)	Q (L/s)	(L/s)*	(L/s)	Req'd (m ³)
ſ		0	230.48	70.95	16.000	54.95	0.00
		5	141.18	43.46	16.000	27.46	8.24
	5 YEAR	10	104.19	32.08	16.000	16.08	9.65
		15	83.56	25.72	16.000	9.72	8.75
		20	70.25	21.63	16.000	5.63	6.75

TABLE 4C: 100 YEAR EVENT QUANTITY STORAGE REQUIREMENT - A-02

0.290 =Area (ha) 0.44 = C

0.44	-0					
				Allowable	Net Flow	01
Return	Time	Intensity	Flow	Runoff	to be Stored	Storage
Period	(min)	(mm/hr)	Q (L/s)	(L/s)*	(L/s)	Req'd (m ³)
	5	242.70	87.05	24.80	62.25	18.67
	10	178.56	64.04	24.80	39.24	23.55
100 YEAR	15	142.89	51.25	24.80	26.45	23.81
	20	119.95	43.02	24.80	18.22	21.87
	25	103.85	37.25	24.80	12.45	18.67

TABLE 4E: 100 YEAR EVENT QUANTITY STORAGE REQUIREMENT - A-02

0.290 =Area (ha) 0.44 = C

0.44	-0					
				Allowable	Net Flow	Charrente
Return	Time	Intensity	Flow	Runoff	to be Stored	Storage
Period	(min)	(mm/hr)	Q (L/s)	(L/s)*	(L/s)	Req'd (m ³)
	5	291.24	104.46	29.7	74.76	22.43
	10	214.27	76.85	29.7	47.15	28.29
100 YEAR + 20	15	171.47	61.50	29.7	31.80	28.62
	20	143.94	51.63	29.7	21.93	26.31
	25	124.62	44.69	29.7	14.99	22.49

Equations:

Flow Equation

Q = 2.78 x C x I x A

Where:

C is the runoff coefficient

I is the rainfall intensity, City of Ottawa IDF

A is the total drainage area

* Allowable run-off is 50% of the actual flow to estimate the required volume as per city of Ottawa Guidelines for underground storage

Runoff Coefficient Equation

 $C_{5} = (A_{hard} \times 0.9 + A_{soft} \times 0.2)/A_{Tot}$

 $C_{100} = (A_{hard} \times 1.0 + A_{soft} \times 0.25)/A_{Tot}$



TABLE 5D: Structure information

Structures	Size Dia.(mm)	Area (m ²)	T/G	Inv IN	Inv OUT
CBMH 105	1200	1.13	95.50	94.36	94.35
CBMH 103	1200	1.13	96.15	94.80	94.74
CBMH 102	1200	1.13	96.20	95.00	94.99
STMMH 101	1200	1.13	96.50	95.13	95.07

TABLE 5D: Landscape drain information

Structures	Size Dia.(mm)	Area (m ²)	T/G	Top of pipe	
LD 104	300	0.07	96.10	94.93	
LD 100	300	0.07	96.30	95.61	

TABLE 5E: Pipe information

Structures	Size Dia.(mm)	Length	Inv UP	Inv DOWN
LD 104 -CBMH 105	375	50.0	94.54	94.36
CBMH 103 - LD 104	375	54.4	94.74	94.55
CBMH 102 - CBMH 103	375	53.8	94.99	94.80
STMMH 101 - CBMH 102	375	20.0	95.07	95.00
LD 100 - STMMH 101	375	29.3	95.23	95.13

TABLE 5F: Storage Provided

	Storage Table										
Elevation (m)	System Depth (m)	CBMH 105 Volume (m ³)	CBMH 103 Volume (m ³)	CBMH 102 Volume (m ³)	STMMH 101 Volume (m ³)	LD 104 Volume (m ³)	LD 100 Volume (m ³)	Pipe Storage Volume (m ³)	Underground Volume (m ³)*	Ponding Volume (m ³)	Total Volume (m ³)
94.350	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
94.360	0.01	0.01	0.00	0.00	0.00	0.00	0.00	0.00	0.01	0.00	0.01
94.740	0.39	0.44	0.00	0.00	0.00	0.00	0.00	5.95	6.39	0.00	6.39
94.990	0.64	0.72	0.28	0.00	0.00	0.00	0.00	13.65	14.66	0.00	14.66
95.070	0.72	0.81	0.37	0.09	0.00	0.01	0.00	16.11	17.40	0.00	17.40
95.500	1.15	1.30	0.86	0.58	0.49	0.04		22.12	25.38	0.00	25.38
95.610	1.26	1.43	0.98	0.70	0.61	0.05	0.00	23.66	27.42	0.28	27.70
95.640	1.29	1.46	1.02	0.74	0.64	0.05	0.00		27.56	0.35	27.91
95.700 95.800	1.35 1.45	-	1.09 1.20	0.80 0.92	0.71 0.83	0.05 0.06	0.01 0.01	-	27.78 28.13	0.35 0.35	28.13 28.48
95.900	1.55	-	1.31	1.03	0.94	0.07	0.02	-	28.48	0.35	28.83

TABLE 2G: Orifice Sizing information - A-1 Control Device Round Plate Orifice 152 mm								Orifice Control Sizing Q = $0.62 \times A \times (2gh) \times 0.5$ Q is the release rate in m ³ /s
Design Event	Flow (L/S)	Head (m)	Elev (m)	Outlet dia. (mm)	Volume (m ³)	Area (m²)	Dia. (mm)	A is the orifice area in m ²
1:5 Year	32.0	0.41	94.84	375.00	9.65	0.0181	152.0	g is the acceleration due to gravity, 9.81 m/s ²
1:100 Year	49.6	0.99	95.42	375.00	23.81	0.0182	152.0	h is the head of water above the orifice centre in m
1:100 + 20 Year	59.4	1.41	95.84	375.00	28.62	0.0182	152.0	d is the diameter of the orifice in m

The design Head is calculated based on the centre of the orifice at the bottom of the pipe

Numbers in red are above the system spill elevation






TABLE 6A: Post-Development Runoff Coefficient "C" - A-01,R-01,R-02

	5 Year	Event	100 Yea	ar Event		
Area	Surface	Ha	"C"	C _{avg}	"C" + 25%	*C _{avg}
Total	Hard	0.443	0.90		1.00	
0.910	Roof	0.468	0.90	0.90	1.00	1.00
0.910	Soft	0.000	0.20		0.25	

TABLE 6B: 2 YEAR EVENT QUANTITY STORAGE REQUIREMENT - A-01,R-01,R-02

0.910 =Area (ha) = C

0.90	= C					
Return	Time	Intensity	Flow	Allowable	Net Flow to be	Storage
Period	(min)	(mm/hr)	Q (L/s)		Stored (L/s)	Req'd (m ³)
	-5	632.75	1441.00	133.0	1308.00	-392.40
	0	167.22	380.83	133.0	247.83	0.00
2 YEAR	5	103.57	235.87	133.0	102.87	30.86
	10	76.81	174.91	133.0	41.91	25.15
	15	61.77	140.67	133.0	7.67	6.90

TABLE 6C: 5 YEAR EVENT QUANTITY STORAGE REQUIREMENT - A-01,R-01,R-02

0.910 =Area (ha) 0.90

0.90	= C					
Return Period	Time (min)	Intensity (mm/hr)	Flow Q (L/s)	Allowable Runoff (L/s)	Net Flow to be Stored (L/s)	Storage Req'd (m ³)
	0	230.48	524.89	133.0	391.89	0.00
	5	141.18	321.52	133.0	188.52	56.55
5 YEAR	10	104.19	237.29	133.0	104.29	62.57
	15	83.56	190.29	133.0	57.29	51.56
	20	70.25	159.99	133.0	26.99	32.39

TABLE 6D: 100 YEAR EVENT QUANTITY STORAGE REQUIREMENT - A-01,R-01,R-02

=Area (ha) 0.910 1.00 = C

	-					
					Net Flow	
Return	Time	Intensity	Flow	Allowable	to be	Storage
Period	(min)	(mm/hr)	Q (L/s)	Runoff (L/s)	Stored (L/s)	Req'd (m ³)
	5	242.70	614.14	133.0	481.14	144.34
	10	178.56	451.83	133.0	318.83	191.30
100 YEAR	15	142.89	361.58	133.0	228.58	205.72
	20	119.95	303.52	133.0	170.52	204.63
	25	103.85	262.78	133.0	129.78	194.66

TABLE 6E: 100 YEAR EVENT QUANTITY STORAGE REQUIREMENT - A-01,R-01,R-02 0.910 =Area (ha)

1.00 = C

	-					
					Net Flow	
Return	Time	Intensity	Flow	Allowable	to be	Storage
Period	(min)	(mm/hr)	Q (L/s)	Runoff (L/s)	Stored (L/s)	Req'd (m ³)
	10	214.27	542.19	133.0	409.19	245.52
	15	171.47	433.90	133.0	300.90	270.81
100 YEAR + 20	20	143.94	364.23	133.0	231.23	277.47
	25	124.62	315.33	133.0	182.33	273.50
	30	110.24	278.96	133.0	145.96	262.72

Equations: Flow Equation Q = 2.78 x C x I x A Where: C is the runoff coefficient I is the rainfall intensity, City of Ottawa IDF A is the total drainage area

Runoff Coefficient Equation $C_{s} = (A_{hard} \times 0.9 + A_{soft} \times 0.2)/A_{Tot}$ C₁₀₀ = (A_{hard} x 1.0 + A_{soft} x 0.25)/A_{Tot}



I

Structures	Size Dia.(mm)	Area (m²)	T/G	Bottom of Tank
Tank	-	118.83	96.45	93.23

TABLE 6G: Storage Provided - A-01,R-01,R-02

Storag			
	System	Tank	1
Elevation	Depth	Volume	
(m)	(m)	(m ³)	
93.23	0.00	0.00	
93.330	0.10	11.88	
93.430	0.20	23.77	
93.530	0.30	35.65	
93.630	0.40	47.53	
93.730	0.50	59.41	
93.830	0.60	71.30	
93.930	0.70	83.18	
94.030	0.80	95.06	
94.130	0.90	106.95	
94.230	1.00	118.83	
94.330	1.10	130.71	
94.430	1.20	142.60	
94.530	1.30	154.48	
94.630	1.40	166.36	
94.730	1.50	178.24	
94.830	1.60	190.13	
94.930	1.70	202.01	
95.030	1.80	213.89	
95.130	1.90	225.78	
95.230	2.00	237.66	
95.330	2.10	249.54	
95.430	2.20	261.43	
95.530	2.30	273.31	
95.630	2.40	285.19	
95.700	2.47	293.51	Top of Tank
95.800	2.57	293.62	
95.900	2.67	293.74	
96.000	2.77	293.85	
96.100	2.87	293.96	
96.200	2.97	294.08	
96.300	3.07	294.19	
96.400	3.17	294.30	
96.500	3.27	294.41	Top of Grate

TABLE 6H: Orifice Sizing Information - A-01,R-01,R-02

control Device							
Pump							
	Volume			Outlet Dia.			
Flow	Required	Depth	Elevation	(mm)			
133.00	30.86	0.25	93.48	300			
133.00	62.57	0.53	93.76	300			
133.00	205.72	1.73	94.96	300			
133.00	277.47	2.33	95.57	300			
	133.00 133.00 133.00	Volume Flow Required 133.00 30.86 133.00 62.57 133.00 205.72	Volume Depth Flow Required Depth 133.00 30.86 0.25 133.00 62.57 0.53 133.00 205.72 1.73	Volume Elevation 133.00 30.86 0.25 93.48 133.00 62.57 0.53 93.76 133.00 205.72 1.73 94.96			






Table 15: Post-Development Stormwater Management Summary


			5 Year Storm Event					100 Year Storm Event					
Area ID	Area (ha)	1:5 Year Weighted Cw	1:100 Year Weighted Cw	Control Device	Outlet Location	Release (L/s)	Ponding Depth (m)		Max. Vol. Provided (cu.m.)	Release (L/s)	Ponding Depth (m)	Req'd Vol (cu.m)	Max. Vol. Provided (cu.m.)
D-01	0.029	0.57	0.65	N/A	Maritime Way	4.8	N/A	N/A	N/A	9.2	N/A	N/A	N/A
D-02	0.008	0.20	0.25	N/A	Highway 417	0.5	N/A	N/A	N/A	1.0	N/A	N/A	N/A
A-02	0.290	0.38	0.44	152	Maritime Way	32.0	0.414	9.65	27.91	49.6	0.989	23.81	27.91
A-01,R-01,R-02	0.910	0.90	1.00	Pump	Maritime Way	133.0	0.526	62.57	294.41	133.0	1.730	205.72	294.41
Post-Devlopment Fle	Post-Devlopment Flow		170.3	-	72.2	322.3	192.8	-	229.5	322.3			
Total Allowable Rele	Total Allowable Release Rate			193.4				193.4					

From: Kuruvilla, Santhosh <Santhosh.Kuruvilla@ottawa.ca>
Sent: Friday, May 20, 2022 9:42 AM
To: Anthony Mestwarp <a.mestwarp@novatech-eng.com>
Cc: Greg MacDonald <g.Macdonald@novatech-eng.com>
Subject: RE: D07-12-21-0017 - 1200 Maritime

Hi Anthony,

Following are the HGL data received from our water resources group for your use.

The 100 year HGL on Maritime from MHST13985- 13986 is: 94.40 to 94.30



Thanks, Santhosh

From: Anthony Mestwarp <a.mestwarp@novatech-eng.com>
Sent: May 16, 2022 2:58 PM
To: Kuruvilla, Santhosh <<u>Santhosh.Kuruvilla@ottawa.ca</u>>
Subject: D07-12-21-0017 - 1200 Maritime

I am reviewing the SWM requirements for the 1200 Maritime site and would like to confirm the HGL within the STM sewer fronting the site.

Based on the design drawings for Maritime way the HGL varies 94.30-94.15 across the site frontage (refer to the attached). City Manhole numbers : MHST13985- 13986. Can you please confirm that this is still the case?

Thanks,

ı.

ı.

Anthony Mestwarp, P.Eng., Project Engineer | Land Development Engineering
NOVATECH Engineers, Planners & Landscape Architects
240 Michael Cowpland Drive, Suite 200, Ottawa, ON, K2M 1P6 | Tel: 613.254.9643 Ext. 216 | Fax: 613.254.5867
The information contained in this email message is confidential and is for exclusive use of the addressee.

This e-mail originates from the City of Ottawa e-mail system. Any distribution, use or copying of this email or the information it contains by other than the intended recipient(s) is unauthorized. Thank you.

Le présent courriel a été expédié par le système de courriels de la Ville d'Ottawa. Toute distribution, utilisation ou reproduction du courriel ou des renseignements qui s'y trouvent par une personne autre que son destinataire prévu est interdite. Je vous remercie de votre collaboration.

2.0 STORMWATER MANAGEMENT - MINOR/MAJOR SYSTEM DESIGN

2.1 General

Traditionally, urban drainage systems were designed considering only the "minor system". A more recent trend however is to design the drainage system according to the dual drainage concept which considers both, the "minor" and the "major" systems. The "minor" drainage system is comprised mainly of street gutters, inlet catch basins, storm sewers and manholes. This system is designed to capture and convey runoff during frequent storm events with return periods up to 1:5 year. The major system is formed by swales/ditches, streets, open channels, stormwater management facilities and will accommodate runoff during storms exceeding 1:5 year up to 1:100 year.

Stormwater servicing for all lands included in the Central Business District of the Kanata Town Centre will be designed using the dual drainage concept, also know as the minor/major drainage system. Furthermore, the minor system on Urbandale's lands (and other lands such as the Penex Kanata Ltd. lands) will also be designed allowing the use of inlet control devices (ICD). With the use of ICD's, flows captured by catch basins can be limited to the conveyance capacity of the storm sewers and therefore minimizing the risk of unacceptable surcharges. With the use of ICD's in catch basin inlets, a higher level of protection (1:100 year) against flooding of basements having foundation drains connected to storm sewers is provided.

2.2 Minor System Design

Storm sewers for Urbandale's lands in the Central Business District of the Kanata Town Centre were sized using the Rational Method. An inlet time of 20 minutes and runoff coefficients ranging from 0.2 (parks) to 0.9 (high density commercial) as presented in Table 1.0 were used.

Land U:	se	Runoff Coefficient			
Park		0.20			
Residential: - - -	low medium high	0.40 0.45 0.50 and 0.60			
Commercial		0.80 and 0.90			

Table 1.0 - Urban Runoff Coefficients

Rainfall intensities required by the Rational Method were taken from the City of Kanata's Intensity-Duration-Curve (IDF). A time of concentration was calculated based on an inlet time of 20 minutes and the 5 year rainfall intensity was extracted using this information. The storm sewer layout (for Street 'A'), drainage area limits and respective runoff coefficients are presented on Drawings 15712-STM (attached in pocket). Plan and profiles for the future Street 'A' are presented on Drawings 15712-01, 15712-02 and 15712-03. The Rational Method storm sewer design sheet for Urbandale's lands (Street 'A') located in the Central Business District is provided in Appendix 'B'.

2.3 Major System Design

A properly designed, constructed and maintained minor/major drainage system is the keystone to good urban drainage. The purpose of the major system is to convey excess runoff generated from severe events which are not captured by the sewer system without causing any damages. With the combination of a properly designed major system and ICD's installed on the minor system, the risk of property damage due to surcharged storm sewer is essentially eliminated, provided that the storm sewer is properly operated and maintained.

Basements in Urbandale's lands in the Central Business District of the Kanata Town Centre will be protected against flooding resulting from a surcharged storm sewer system by setting basement floors 0.3 m above the 1:100 year hydraulic grade line. To achieve this, Scepter Type 'A' ICD's (with a capture of 20 L/s for a head = 1.22 m) will be used in street catch basins to limit the minor system's carrying capacity. Since the road grades for the internal roads have not been designed at this stage, the location of the proposed catch basins have not

I.

ł

been determined. During the detailed design of the internal road grades, the use of Scepter Type 'A' ICD's will be specified. The number of contributing catch basins will be limited to the carrying capacity of the minor system. Furthermore, all storm sewer manholes should be provided with solid covers to limit sources of water which were not accounted for during the design of the minor system.

Overall grading plans will be prepared for Urbandale's lands located in the Central Business District to ensure that the minor/major drainage concept is properly implemented. Overland flow corridors will be carefully selected for these lands. Once the detailed design of these lands is completed, detailed plan and profiles and grading plans will be included in the submission package for a Certificate of Approval by the MOE.

2.4 On-Site Controls

The 1993 Master Drainage Study discussed and recommended the use of the following onsite controls in addition to end of pipe control (stormwater management facility):

- 1. Rooftop storage on flat roofs and parking lot storage in the commercial area, where feasible, to detain post-development flows.
- 2. Use of catch basin equipped with ICD's to control the rate of inflow to the storm sewer system.
- 3. Direction of the building roof downspouts, where possible, to grassed areas to minimize the runoff from hard surfaces and increase the recharge of the groundwater table.
- 4. Provision of grassed swales along the rear of lots (in residential development) at minimum slope to retard runoff and provide opportunity for infiltration.
- 5. Use of perforated leads to connect rear yard catch basins to increase groundwater recharge, where soils conditions are favourable.

The above measures should be investigated and evaluated site-specifically during the detailed design of each subdivision. The investigation and evaluation should be incorporated in the individual Stormwater Site Management Plan.

11.0 SUMMARY

- This Stormwater Management Report has been prepared to address a number of draft plan conditions for Urbandale's Kanata Town Centre Lands - Central Business District.
- A detailed design for a Stormwater Management Facility, as recommended in the "Kanata Town Centre - Master Drainage Study for Watts Creek" (Cumming Cockburn Limited, May 1993), is presented.

Final approvals are required prior to construction.

Shows that the iii) minor system be designed to 5-year and 100-year can safely be conveyed on the roadway.

- Stormwater servicing for the tributary areas to the SWMF will be designed using the dual drainage concept. The storm sewer system (on Street 'A') has been sized to capture and convey a 1:5 year flow. The surface drainage, grading, and overland flow corridors will be designed to accommodate the flows in excess of 1:5 year up to 1:100 year.
- iv) Basements in future residential development will be protected against flooding during a 1:100 year event by installing Scepter Type 'A' ICD's in catch basins located within the streets and by setting the basement floor elevations 0.3 m above the 1:100 year HGL. As an additional precautionary measure, all lateral storm sewer services will be provided with a backwater valve.
- v) To maintain the integrity of the performance of the storm sewer, storm sewer manholes will be provided with solid manhole covers.
- vi) Building roof downspouts will be discharged onto grassed areas wherever possible, to reduce the volume and velocity of runoff as well as peak flows. This will also improve water quality slightly but, more importantly, will increase groundwater recharge.

Urbandale Corporation

SWMF provides vii) quality control for the entire upstream drainage area, therefore no site-specific quality control is required.

1


- A SWMF will be constructed in the southeast corner of the lands. This facility will incorporate a permanent pool storage of 5949 m³ (between elevations 88.90 m to 89.90 m), an extended detention storage of 2758 m³ (between elevations 89.90 m to 90.20 m) and a water quantity storage of 36491 m³ (between elevations 90.20 m to 93.25 m).
- viii) Landscaping will be incorporated into the pond design to provide a natural appearance and to improve overall performance.
- A monitoring and maintenance program is proposed to demonstrate and ensure longterm acceptable performance. The parameters to be analyzed include total suspended solids (>70% TSS removal), dissolved oxygen, total and dissolved phosphorous, nitrates, nitrites, TKN, ammonia, chlorides, sodium and pH.
- x) Appropriate erosion and sediment control measures during construction will be implemented to trap sediments on-site.


Prepared by:


Guy Forget, P.Eng.

Reviewed by:

Maria F. Schouten, P.Eng.









KANATA TOWN CENTRE CENTRAL BUSINESS DISTRICT URBANDALE CORPORATION JLR PROJECT NO.: 15712 Printed on 5/29/2007 at 7:45 AM

STORM SEWER DESIGN SHEET IDF CURVE 1: 5

> Designed by: C.B. Checked by: D.L.

	g's Coefficie NHOLE	1	0.013			DRA	NAGE	AREAS	-	_	_	1	1-5 YP P	EAK FLOW	GENERA	TION	ACTUAL			SEWER	DATA			11		liper	REAM						DOWN	STREAM			_
	MBER	-					1		1200	r	cumm	2.78AF	2.78AR	Time	Intens.	Peak Flow	Dia	Dia	Slope		V full	Length	Flow	Ex	Pr. Center		Obvert	Invert	Cover	Ex.	Pr. Center	Obvert	Forced	Obvert	Invert	Cover	Dstre
From	То	0.20	0.30	0.40	0.50	0.60	0.80	0.80	0.90	area (ha)	area (ha)	CUMM	min	mm/hr	L/s	(mm)	(mm)	%	(Vs)	(m/s)		Time (min)	Ground		Drop				Ground	Line	Drop	Drop				Ber
13	607	0.75	, e c	202	-	4.01		15.53	9.57	29.86	29.86	65.59	65.59	28.52	55.80	3659.80	1676.4	1650	0.19	4155.57	1.88	83.20	0.74	AU 73	96.32		92.656	91.006	3.66	1.1.4	95.47	41 N	-0.15	92.497	90.847	2.97	-
607	606	1.0	Ш. М	5. H.		1	5.60	0.23	-	5.83	35.69	12.97	78.55	29.26 30.21	54.85	4308.72	1828.8	1800	0.21	5495.32	2.09	119.10	0.95	- 26.76	95.47		92.647	90.847	2.82	100-1-0	94.80		0.33	92.397	90.597	2.40	15.0
635	634			_				-						20.00	70.25		304.8	300	2.90	171.80	2.35		0.36		103.38		97.681	97.381	5.70		102.56			96.187	95.887	6.37	13.0
634	633						0.17	0.29		0.46	0.46	1.02	1.02	20.36 20.97	69.46	71.06	304.8	300	1.60	127.61	1.75	64.00	0.61		102.56		96.187	95.887	6.37		101.67			95.163	94.863	6.51	90.0
633A	633							0.08		0.08	0.08	0.18	0.18	20.00	70.25	12.50	304.8	300	0.87	94.10	1.29	35.10	0.45		101.49		95.122	94.822	6.37				0.30	94.816	94.516	-94.82	-
633	632										0.46		1.20	20.97	68.18	81.88	381	375	1.00	182.91	1.60	64.70	0.67		101.67		95.163	94.788	6.51		101.29			94.516	94.141	6.77	13.0
632	631				-		1.16	0.31		1.47	1.93	3.27	4,47	21.65 22.27	66.83	298.76	533.4	525	1.00	448.66	2.01	74.80	0.62	-	101.29		94.516	93.991	6.77		97.55			93.768	93.243	3.78	80.0
636	631		_		-			0.25		0.25	0.25	0.56	0.56	20.00	70.25	39.06	304.8	300	2.23	150.65	2.06	93.30	0.75		102.26		95,849	95.549	6.41		97.55			93.768	93.468	3.78	_
631	630		_		-						2.18		5.03	22.27	65.64	329,91	533.4	525	3.85	880.33	3.94	81.10	0.34		100.65		96.921	96.396	3.73		97.55		0.03	93.798	93.273	3.75	-
630 606A	606A 606	0.36					_	0.41		0.77	0.77 0.77	1.11	6.14 6.14	22.61 23.25	65.00 63.85	398.97 391.91	533.4 533.4	525 525	1.35 1.35	521.29 521.29	2.33 2.33	88.90 4.90	0.64 0.04		97.55 94.64		93.768 92.538	93.243 92.013	3.78 2.10		94.64 94.80		0.03 0.41	92.568 92.472	92.043 91.947	2.07 2.33	18.0 81.0
														23.28																							_
606 605	605 604		1203		100		2.94	0.35 0.25		0.35	36.81 40.00	0.78	85.47 92.57	30.21 31.00 31.50	53.68 52.73	4587.99 4881.44	(1) 1828.8 (1) 1828.8	(1) 1800 (1) 1800	0.25	6049.60 5911.34	2.30	110.40 67.40	0.80	1	94.80 94.69	2N 2 Hat	92.065 91.765	90.590 90.290	2.74 2.93		94.69 94.50	0.06	0.02	91.784 91.601	90.309 90.126	2.91	90.0
642 641	641 640					-	1.10	0.13		0.13	0.13	0.29	0.29	20.00	70.25 69.08	20.31 210.47	381 457.2	375	1.85	248.79 266.03	2.18	71.30 77.70	0.54		100.26 98.94		97.259 95.940	96.884 95.490	3.00 3.00		98.94 98.33			95.940 95.318	95.565 94.868	3.00	
												-		21.34																							
640	612			_			1.02	0.14	_	1.16	2.53	2.58	5.63	21.34 22.11	67.43	379.43	609.6	600	0.66	520.98	1.79	82.30	0.77		98.33		95.318	94,718	3.01		97.86		-0.04	94.774	94,174	3.09	80.0
614 613	613 612					1.12		0.12 0.14		0.12	0.12	0.27	0.27	20.00	70.25 69.34	18,75 169,64	304.8 381	300	2.16	148.20 257.25	2.03	51.20 51.60	0.42		100.07		96.938 95.833	96.638 95.458	3.13 3.13		98.96 97.86			95.833 94.813	95.533 94.438	3.13	
015								0.14		1.20	1.00	2.10	2.40	20.80	00.04	100.04		0.0	1.50	LOTILO	2.20	51.00	0.00				33.000	30,400	5.15					01.010		0.00	
612 611	611 601	0.27				0.90	0.72	0.16		0.43	4.34	0.51	8.58	22.11 22.31	65.93 65.56	565.64 789.16	685.8 685.8	675 675	3.12	1548.97 1109.24	4.19	49.60	0.20		97.86 96.45		94.813 93.235	94.138 92.560	3.05 3.21		96.45 94.93	0.06	0.03	93.265 92.530	92.590 91.855	3.18 2.40	80.00
601	604	1.20	1.03		-	1.50		0.07	2	0.07	6.19	0.16	12.19	22.55 22.95	65.10	793.79	685.8	675	1.42	1044.99	2.83	67.50	0.40	server the	94.93	_ 1925) 	92.470	91.795	2.46	1 FOLM	94.50	0,00	-0.05	91.511	90.836	2.99	90.0
604	Chamber	[8.2]				42	- 19	343	-AL.	1121	46.19	Real S	104.76	31.50 31.62	52.16	5464.60	(1) 1828.8	(1) 1800	0.21	5495.32	2.09	14.40	0.11	- Kak	94.50	2477	91.556	90.081	2.94	C	94.00	1 N 12	· •0.01	91.526	90.051	2.47	
hamber	Pond		Q. 1	22-	111			411		antesta.	46.19	1.3.	104.76	31.62	52.03	5451.05	1524	2x1500	0.33	8472.67	2.32	11.50	0.08	M 191	94.50	SHUES.	91.539	90.039	2.96	14.18	94.00			91.501	90.001	2.50	
			_		-									31.70				alent size of a																			
																		eet calculation			isting p	pipe is a				_					A		~			-	
			_				-				-	-			-		norizontal	elliptical 1475	x 2310	HE III.											he	ESSI	DAL	-			-



Filename: V:\15712\Rev 4\storm\15712-STM_rev3.XLS

T E C H N I C A L M E M O R A N D U M



J.L. Richards & Associates Limited 864 Lady Ellen Place Ottawa, ON Canada K1Z 5M2 Tel: 613 728 3571 Fax: 613 728 6012

4

			PAGE 1 OF
TO:	Urbandale Corporation	DATE:	June 13, 2012
	c/o Mary Jarvis, MCIP, RPP Director of Planning	JOB NO.:	15712-10
FROM:	Jonathan Párraga, P.Eng.	CC:	J.L. Richards & Associates Limited
RE:	Servicing Brief (Revised) Kanata Town Centre Central Business District Subdivision		Attention: Lucie Dalrymple, P.Eng.

PURPOSE OF UNDERTAKING

This Servicing Brief was prepared, in support of Urbandale Corporation's re-zoning application for the Kanata Town Centre - Central Business District (KTC-CBD) Subdivision. The following confirms that water, sanitary and storm sewer services are readily available to accommodate this subdivision.

DESCRIPTION OF PROPERTY

The subject lands encompass an area of approximately 18.8 hectares within the KTC-CBD, in the City of Ottawa (former City of Kanata). The lands are bounded to the north by Campeau Drive, to the west by a partial of land fronting Castlefrank Drive, south by Hwy. 417 and to the east by the Hydro One corridor (refer to Figure 1 attached). This subdivision is comprised of residential and commercial developments. Civil infrastructure (i.e., local watermains, storm and sanitary sewers) within the ROWs are all existing and in service. The trunk storm sewer, sanitary sewer, and watermain along the south leg of Maritime Way were constructed by Urbandale Corporation in 1998 and the remaining local infrastructure in 2007-2008. The 900 mm dia. feedermain on Great Lakes Avenue was constructed for the City of Ottawa in 2008-2009.

STORM SEWER SERVICING

<u>Outlet</u>:

The KTC-CBD lands are tributary to the KTC-CBD Stormwater Management Facility (SWMF) located in the southeast corner of the subdivision (refer to Figure 1 for Pond location), which subsequently drains to Watts Creek. This SWMF was designed, and subsequently constructed, to accommodate the development of the KTC-CBD subdivision and provides quantity as well as quality control for the stormwater flows. Details of the SWMF can be found in the Stormwater Management Report, Kanata Town Centre, Central Business District, dated January 1999 and prepared by J.L. Richards & Associates Limited.

Minor/Major System:

The KTC-CBD storm drainage system has been designed using the dual drainage concept, consisting of a minor and a major system. The minor system conveys storm runoff generated during frequent storm events (i.e., 1:5 year or less) via a local storm sewer collection system outletting to the KTC-CBD

the	An Hall Contraction of the second sec
CAMPEAU DRIVE CASTLEFRANK ROAD HEIRING TOT TOT TOT TOT TOT TOT TOT TOT TOT TOT	KANATA TOWN CENTRE CENTRAL BUSINESS DISTRICT (KTC-CBD)
PROJECT: KTC-CBD URBANDALE CORPORATION	DRAWING:
L.Richards ENGINEERRARCHITECTSPLANNERS ENGINEERRARCHITECTSPLANNERS CORPORATION CITY OF OTTAWA J.L. Richards & Associates Limited & Associates Limited B4 Lady Ellen Place Ottawa, ON Canada K1Z 5M2 Tel: 613 728 3571 Tel: 613 728 3571	PLANDESIGN:DRAWN: T.S.DRAWING No.:DATE:OCT.2006FIG.1SCALE:N.T.S.JOB No.:15712

PAGE 2 OF 4

SWMF where, as noted, water quality and quantity treatment is provided. In accordance with the noted SWMF Design Report, the following runoff coefficients were used at detailed design of the local storm sewers

Residential - Low Density	C=0.40
Residential - Medium Density	C=0.45
Residential - High Density	C=0.50 and 0.60
Commercial Area	C=0.80 and 0.90
Parkland	C=0.20

An excerpt from the noted 1999 Stormwater Management Report, indicating assigned runoff coefficients 'C', allowable capture rates, and required on-site storage volumes for the specific land parcels is included in Attachment 1. The servicing design for each Block in the KTC-CBD shall adhere to these SWM design requirements.

The major system was established at the detailed design stage to convey excess runoff generated during severe events which would not be captured in the minor system. The excess runoff will be conveyed via overland routes to the KTC-CBD SWMF. The grading plans of the KTC-CBD lands have been developed with roadway sags. Local Blocks of land are expected to incorporate parking lot, cistern and roof top storage (or a combination thereof) at Site Plan Control, to ensure that the minor / major drainage concept, as specified in the Attachment 1 Table, is properly implemented.

A Hydraulic Grade Line (HGL) Analysis was carried out during detailed design to verify the anticipated amount of freeboard provided between the maximum storm sewer HGL elevations and the building underside of footing elevations. At detailed design of each Block, and as required at Site Plan Control, the on-site HGL clearance will require confirmation. The analysis was based on the estimated maximum water elevations of the KTC-CBD SWMF.

WATER SERVICING

The local network of water servicing for the KTC-CBD Subdivision was originally developed based on the existing 610 mm and 406 mm diameter watermains on Maritime Way. Water servicing specifics for the subdivision were addressed in detail in the Hydraulic Network Analysis (HNA) Report, which was prepared and submitted to the City in conjunction with the detailed servicing design of this project. The HNA Report for KTC-CBD demonstrated that the proposed (now existing) watermain sizing satisfied the water demand during the maximum hourly and fire flow conditions, as per the City of Ottawa Design Guidelines. Furthermore, the analysis included an assessment of pressures during low demand conditions (i.e., high pressure check) ensuring that the system pressures do not exceed the maximum pressure requirements set by the Ontario Building Code (OBC).

Since then a 900 mm diameter feedermain was constructed in 2008-2009 on Great Lakes Avenue, linking the existing 610 mm diameter feedermain on Maritime Way to the existing 900 mm diameter feedermain on Campeau Drive. At detailed design of each Block, and as required at Site Plan Control, the designer will have to obtain boundary conditions from the City of Ottawa and carry out an HNA for their respective Block.

PAGE 3 OF 4

SANITARY SEWER SERVICING

There is an existing 825 mm diameter trunk sanitary sewer along the south leg of Maritime Way and extends easterly along a service easement to Gray Crescent in Village Green. This sanitary trunk sewer was designed by JLR (1998) to accommodate the development of the KTC-CBD subdivision and upstream lands. Local sanitary sewers were subsequently designed by JLR (2007) and constructed. At the time of the original design of the trunk sewer the land parcels were designated for commercial use and the sanitary flows were estimated using 50,000 L/ha/d (MOE guidelines for sanitary flow for commercial zones). Subsequently, the land use was revised to include residential use, as well as commercial use. As such, in 2007, JLR revised the original sanitary flow estimate according to the projected land use to design the local sewers. Currently, Blocks 3, 6 and 8 have been sold and either developed or partially developed. As such, the estimated sanitary flows generated by the local Blocks have currently been updated to reflect exiting conditions and projected development of local Blocks. Table 1 provides a summary of the existing and anticipated land uses.

Block No.	Land Use Description	Number of Units/Rooms	Population	Daily Sewage Flow	Area
1	Hotel Suites	167	301	270 L/pp/d*	1.48
2	Commercial			50,000 L/pp/d	1.36
3	Retirement Home	208	333		1.02
4	Apartments	120	216	350 L/pp/d	1.37
5	Apartments	120	216	350 L/pp/d	1.02
6	Apartments with Community Centre			350 L/pp/d**	2.83
7	Commercial	N/A		50,000 L/pp/d	1.70
8	Hotel	125	225	270 L/pp/d*	1.02
9	Commercial	N/A	N/A	50,000 L/pp/d	4.96
10	Walkway Easement	N/A	N/A	N/A	0.28

 Table 1 - Kanata Town Centre Existing and Anticipated Land Uses

Note: * Additional flow of dining room and staff accounted for in design

** Additional flow from Community Centre pool 40 L/pp/d accounted for in design

The current peak flow estimate has been revised in accordance with the land uses presented in Table 1. A comparison of the original peak flow estimate (1998) and the current peak flow estimate is presented in Table 2. The revised peak flow estimate, based on the current land use projections and existing land uses, creates an increase of estimated flow of 4.05 L/s (274.66 L/s – 270.61 L/s) at the Trunk easement. This flow, however, with a reduction in the downstream peaking factor due to the increase in residential units in the CBD, normalizes close to the original (1998) estimated flow and actually estimates a small reduction of 0.15 L/s (475.94 L/s - 475.79L/s) at the end of the residential subdivision at the intersection of Campeau Drive and Teron Road. The original peak flow design estimate (1998) and the updated detailed design spreadsheet, as well as the sanitary drainage boundary plan, can be found in Attachment 2.

PAGE 4 OF 4

Location	Tributary Area	Up MH	Down MH	Original Assigned Flow Estimate (1998)	Current Flow Estimate (2012)
Trunk Easement	Upstream + KTC-CBD	500	94	270.61	274.66
Total Flow at end of Residential	Upstream + KTC-CBD + Residential to Teron Road	Ex.	Ex. 2	475.94	475.79

Table 2 - Kanata Town Centre Estimated Sanitary Peak Flow

SUMMARY

The existing trunk (1998) and local (2007-2008) infrastructure servicing the subject lands, which are referred to as KTC-CBD, have capacity to service the local Blocks, with regards to stormwater and wastewater; based on the SWM design parameters provided in Attachment 1 and wastewater based on the revised existing and proposed land uses as per Table 1 of this report.. Domestic water is available along the frontage of each Block with the understanding that a site specific HNA is to be carried out at Site Plan Control to demonstrate conformance with the City Guidelines

Revised by:

J.L. RICHARDS & ASSOCIATES LIMITED

Jonathan Párraga, P.Eng.

JP:jd Attach.




ATTACHMENT 1

Kanata Town Centre - Central Business District Stormwater Design Criteria - Tributary Areas to SWMF

Required on cito	Storado Violumo		up to 100 yr		up to 100 vr	160000			up to Too yi			up to 100 yr			up to 100 vr	lin to 10 vr	10 to 10 yr		up to 100 yl	up to JU yI		
On-Site	Storade	2007 2007	20	No	Yes	ND	ON	Yac			Vac	No.		NO	Yes	Limited	l imited	Yes	l imitad	No	ON ON	No
Allowable	Capture Rate	1.5 VDar	1.0 7.01	1:5 year	1:5 year	1:5 vear	1:5 vear	1:5 vear	1:10 vear	1.10 vear	1:10 vear	1.5 vear	10 Juni	1.5 year	1:5 year	1:5 year	1:5 vear	1.5 vear	1:5 vear	1.5 vear	1:100 vear	1:100 year
0	factor	0.80	100	0.0/	0.87	0.87	0.76	0.87	0.76	0.60	0.20	0.80	000	0.00	0.80	0.80	0.80	0.80	0.60	0.20	0.41	0.56
TIMP	(%)	85	OF	000	95	95	80	95	80	57		85	2 Z Z		85	85	85	85	57	1 4 1	30	52
Area (ha)		7.85	1 16	01.0	3.03	3.55	0.38	0.80	2.84	2.77	0.82	4.66	216	10	2.11	1.32	10.41	4.48	1.82	0.54	7.87	0.95
Description		AMC Site	Park & Ride			Iransıtway	Hotel Road	Hotel Site	Castlefrank Road	Adjacent Lands	Exist Pond **	Kanata North	Adi Lands (east)	Adil ande (couth coot)	AUJ LAIIUS (SOUIN-EASI)	Street "A"	Urbandale North	Urbandale South	Urbandale East	Urbandale East (park)	Queensway	SWMF
DRAINAGE	AREA No.	~	2	<u>ــــــــــــــــــــــــــــــــــــ</u>		4 1	ן רע	Q	 	0	o	10	~	1	7		14	15	16	17	18	19

Filename: V:\15712.LD\Design\Storm\SWM_Criteria\SW_Runoff_Criteria.xls

Sheet No. SWM Criteria



-415

42 KNUDSONI 5 D PP 思想的 0.54 70 16 1.82 0.57 11 2.30 VAD C. LEGEND: -- SUB-BASIN I.D. NO. - 1 - 3.75 - 12 AREA IN HECTARES CURVE NUMBER (CN) SUB-BASIN I.D. NO. - <u>2</u> - <u>6.1</u> - <u>0.8</u> AREA IN HECTARES -TOTAL IMPERVIOUSNESS -5. 1. -111 「高麗の KANATA TOWN CENTRE UUUT YHAUNAL UUUT YHAUNAL FUTURE CONDITIONS URBANDALE FIGURE 3

ATTACHMENT 2



KANATA TOWN CENTRE CENTRAL BUSINESS DISTRICT URBANDALE CORPORATION JLR PROJECT NO.: 15712

Commercial Flow =	50000	L/ha/d	SANITARY SEWER DESIGN SHEET
q residential=	350	l/cap/d	Designed: C.B.
q hotel =	270	l/cap/d	Revised by: J.L.P.
q retirement homes =	450	l/cap/d	Checked By: D.L.
i =	0.28	l/s/ha	
SING. HOUSING	3.4	pers/hse	
MULT. HOUSING	2.7	pers/hse	
Hotel/Appartments	1.8	pers/room	
Retirement Homes	1.6	pers/room	

Manning's Coefficient (n) = 0.013

Date: May 28, 2012

			I						RESIDENTIAL							COMM	ERCIAL / INSTIT		PLUGG	ED FLOW	R	+C	п		SEWER DA	ΔΤΔ	
	м.	H. #					NUMBER OF					CUMM	ULATIVE	PEAKING	POPUL.	00	CUMM.	COMM.	1 2000	CUMM.	PEAK EXTR.	PEAK DES.		<u> </u>	1	1	1
STREET			SING. Stacks	Towns	Ext	Care		Hotel/Apa	art.	POPUL.	AREA	POPUL.	-	FACTOR		AREA	AREA	FLOW	FLOW	FLOW	FLOW	FLOW	DIA.	SLOPE %	CAPAC.		LENGTH m
	FROM	TO			No units		No units	Act. pop.	Equ. pop.	people	ha	people	ha	moren	l/s	ha	ha	l/s	l/s	l/s	l/s	l/s	mm		° l/s	m/s	
MARITIME WAY	7A	507								(1) 2588	(1) 28.38	2588	28.38	3.50	36.65	(1) 23.16	23.16	20.10	(1) 162.69	162.69	14.43	233.88	825	0.14	529.34	0.99	81.90
MARITIME WAY	507	506			1		125	225	174	174	1.02	2762	29.40	3.30	38.85	4.91	28.07	24.37	(1) 102.03	162.69	16.09	242.00	825	0.14	500.32		119.30
	507	506					125	223	174	174	1.02	2702	29.40	3.47	30.03		20.07	24.37		102.09	10.09	242.00	020	0.12	500.32	0.94	119.30
CORDILLERA ST.	534	533												4.00		0.55	0.55						200		42.13	-	
CANADIAN SHIELD AV.	533	532												4.00			0.55						200		35.93	1.14	69.60
CANADIAN SHIELD AV.	532	531					167	301	234	234	1.48	234	1.48	4.00	3.79		0.55	0.48			0.57	4.84	200	1.20	35.93	1.14	69.60
GREAT LAKES AV.	536	531									0.24		0.24	4.00									200	2.40	50.81	1.62	60.00
GREAT LAKES AV.	531	530										234	1.72	4.00	3.79		0.55	0.48		1	0.64	4.90	200	3.75	63.51	2.02	80.80
GREAT LAKES AV.	530	506A										234	1.72	4.00	3.79		0.55	0.48			0.64	4.90	200		38.80	1.24	
GREAT LAKES AV.	506A	506									0.38	234	2.10	4.00	3.79		0.55	0.48			0.74	5.01	200	1.40	38.80		
MARITIME WAY	506	505		-			176	316.8	269	269	0.57	3265	32.07	3.41	45.11		28.62	24.84		162.69	16.99	249.64	825	0.12	486.76	0.91	111.00
MARITIME WAY	505	504			1		146	262.8	230	209	0.56	3495	32.63	3.39	47.93	1.75	30.37	24.04		162.69	17.64	254.62	825	0.12	484.63	0.91	114.40
MARITIME WAY	503	501						202.0	200	200	0.27	3495	32.90	3.39	47.93		30.37	26.36		162.69	17.72	254.70	825		476.06		29.90
CANADIAN SHIELD AV.	542	541					176	316.8	269	269	0.74	269	0.74	4.00	4.36						0.21	4.57	200		48.64	1.55	71.30
CANADIAN SHIELD AV.	541	540					154	277.2	232	232	0.51	501	1.25	3.97	8.06	1.36	1.36	1.18			0.73	9.98	200	0.90	31.13	0.99	77.70
	Block 3	540			208	333			428	428	1.02	428	1.02	4.00	6.93						0.29	7.22	200	0.60	25.40	0.81	12.00
																						10.00					
CANADIAN SHIELD AV.	540	512									0.30	929	2.57	3.82	14.38		1.36	1.18			1.10	16.66	200	0.71	27.65	0.88	82.60
MARITIME WAY	514	513												4.00									200	2.14	47.96	1.53	51.20
MARITIME WAY	513	513					120	216	216	216	1.37	216	1.37	4.00	3.50						0.38	3.88	200		49.52	1.58	51.90
	515	512					120	210	210	210	1.07	210	1.07	4.00	0.00						0.00	0.00	200	2.20	40.02	1.00	01.00
MARITIME WAY	512	511							58	58	(2) 0.73	1203	4.67	3.75	18.26		1.36	1.18			1.69	21.13	200	3.12	57.95	1.84	49.30
MARITIME WAY	511	510					120	216	216	216	1.02	1419	5.69	3.70	21.25		1.36	1.18			1.97	24.40	200	1.70	42.76	1.36	38.40
MARITIME WAY	510	501										1419	5.69	3.70	21.25		1.36	1.18			1.97	24.40	200	2.28	49.52	1.58	11.30
TRUNK EASEMENT	501	500										4914	38.59	3.25	64.73		31.73	27.54		162.69	19.69	274.66	825	0.10	462.89	0.87	129.00
TRUNK EASEMENT	500	94										4914	38.59	3.25	64.73		31.73	27.54		162.69	19.69	274.66	020	0.10	402.00	0.07	120.00
TROUG EASEMENT	500	54										4314	30.35	5.25	04.75		51.75	21.34		102.03	19.05	274.00			1	+	├ ───┦
Α	90	92		35						95	0.80	95	0.80	4.00	1.53					1	0.22	1.76	250	0.60	46.06	0.94	120.0
	92	94		12						32	1.19	127	1.99	4.00	2.06						0.56	2.61	250	2.20	88.20	1.80	103.0
	94	95										5041	40.58	3.24	66.20		31.73	27.54		162.69	20.25	276.67	825	0.12	497.22	0.93	17.5
	94 95	95 89		10						27	0.52	5068	40.58	3.24	66.51		31.73	27.54		162.69	20.23	270.07		0.12			17.5
					1						5.52	0000		0.2.1	00.01		00	21.04		102.00	20.00	2	020	0.12		0.00	00.0
В	85	87	19							65	1.19	65	1.19	4.00	1.05						0.33	1.38	250		37.61	0.77	116.9
	87	89		24						65	0.82	129	2.01	4.00	2.10						0.56	2.66	250	1.41	70.70	1.44	116.7
Α	89	84		12						32	0.35	5230	43.46	3.23	68.36		31.73	27.54		162.69	21.05	279.65	825	0.12	497.22	0.93	79.0
C	80	82	19	05	<u> </u>					65	1.08	65	1.08	4.00	1.05						0.30	1.35	250		37.61	0.77	120.0
	82	84		25	+					68	0.83	132	1.91	4.00	2.14					<u> </u>	0.53	2.68	250	1.20	65.18	1.33	118.5
A	84	79		14	1					38	0.54	5399	45.91	3.21	70.30		31.73	27.54		162.69	21.74	282.27	825	0.12	497.22	0.93	79.0
	1		1 1	1	1	1	1					1	1	1					1		1	1	11		1	1	



KANATA TOWN CENTRE CENTRAL BUSINESS DISTRICT URBANDALE CORPORATION JLR PROJECT NO.: 15712

Commercial Flow =	50000	L/ha/d	SANITARY SEWER DESIGN SHEET
q residential=	350	l/cap/d	Designed: C.B.
q hotel =	270	l/cap/d	Revised by: J.L.P.
q retirement homes =	450	l/cap/d	Checked By: D.L.
i =	0.28	l/s/ha	
SING. HOUSING	3.4	pers/hse	
MULT. HOUSING	2.7	pers/hse	
Hotel/Appartments	1.8	pers/room	
Retirement Homes	1.6	pers/room	

Manning's Coefficient (n) = 0.013

Date: May 28, 2012

			1							RESIDENTIAL							COMM	IERCIAL / INSTIT	UTIONAL	PLUGG	D FLOW	R	+C	Π		SEWER DA	ATA	
STREET	M.H	ł. #						NUMBER OF	UNITS				CUMM	ULATIVE	PEAKING	POPUL.		CUMM.	COMM.		CUMM.	PEAK EXTR.	PEAK DES.				T	
SIREEI			SING.	Stacks	Towns	Ext.	Care		Hotel/Apa	art.	POPUL.	AREA	POPUL.	AREA	FACTOR	FLOW	AREA	AREA	FLOW	FLOW	FLOW	FLOW	FLOW	DIA. mm	SLOPE 9	6 CAPAC.	. VEL. m/s	LENGTH m
	FROM	то				No units	Act. pop	No units	Act. pop.	Equ. pop.	people	ha	people	ha		l/s	ha	ha	l/s	l/s	l/s	l/s	l/s			1/5	11/5	
D	75	76			17						46	0.37	46	0.37	4.00	0.74						0.10	0.85	250	0.40	37.61	0.77	57.0
	76	77			20						54	0.29	100	0.66	4.00	1.62						0.18	1.80	250	0.40	37.61	0.77	78.4
	77	79			13						35	0.63	135	1.29	4.00	2.19						0.36	2.55	250	0.81	53.66	1.09	117.7
PARK EASEMENT	79	67										0.98	5534	48.18	3.20	71.83		31.73	27.54		162.69	22.37	284.44	825	0.12	497.22		55.0
	67	66			6						16	0.33	5551	48.51	3.20	72.01		31.73	27.54		162.69	22.47	284.71	825	0.12	497.22	0.93	70.0
																								11				
BELLROCK DRIVE	70	73		12	14						70	2.56	70	2.56	4.00	1.14						0.72	1.85	250	0.40	37.61	0.77	87.2
	73	74			12						32	0.54	103	3.10	4.00	1.66						0.87	2.53	250	0.40	37.61	0.77	60.3
EASEMENT	74	62										0.31	103	3.41	4.00	1.66						0.95	2.62	250	0.40	37.61	0.77	39.9
CAMBRAY LANE	62	66			25						68	0.48	170	3.89	4.00	2.76						1.09	3.85	250	0.77	52.18	1.06	100.5
																								11				
BISHOPS MILLS WAY	66	65			9						24	0.53	5745	52.93	3.19	74.21		31.73	27.54		162.69	23.70	288.14	825	0.12	497.22	0.93	62.0
			 										L		<u> </u>									μ	I	+	+	───
SOUTH of HWY 417	EX.	65									(1) 7792	(1) 191.60	7792	191.60	3.06	96.63				(4) 37.72	37.72	53.65	188.00	900	0.11	600.38	0.94	50.2
			<u> </u>			<u> </u>					_	<u> </u>		a					e					Н.		-	+	───
BISHOPS MILLS WAY	65	64			2						5		13542	244.53	2.82	154.86		31.73	27.54		200.41	77.35	460.17	900	0.11	600.38	0.94	17.0
																												L
EDENVALE DRIVE	59	60			8						22	0.50	22	0.50	4.00	0.35						0.14	0.49	200		38.80		77.0
KETTLEBY STREET	60	61			22						59	0.62	81	1.12	4.00	1.31						0.31	1.63	250	0.40	37.61	0.77	103.6
					-							0.44		0.44	4.00	0.00						0.44	0.00	11		07.44		<u> </u>
CAMBRAY LANE	58	61			5						14	0.41	14	0.41	4.00	0.22						0.11	0.33	200	0.70	27.44	0.87	74.5
					25						68	0.42	400	4.05	4.00	0.00						0.55	3.17	050	0.00	50.44	4.45	405.0
KETTLEBY STREET	61	64			25						66	0.42	162	1.95	4.00	2.63						0.55	3.17	250	0.90	56.41	1.15	105.0
BISHOPS MILLS WAY	64	63			3						8		13713	246.48	2.82	156.51		31.73	27.54		200.41	77.90	462.36	000	0.11	600.38	0.94	13.0
BISHOPS MILLS WAT	63	57			10						27	0.68	13713	240.46	2.82	156.77		31.73	27.54		200.41	78.09	462.81	900 900	0.11	600.38		64.9
	63	57			10						21	0.00	13740	247.10	2.02	150.77		31.73	27.04		200.41	76.09	402.01	900	0.11	000.38	0.94	64.9
TER. BUNGALOW Ph.2	51	53		48							130	0.94	130	0.94	4.00	2.10						0.26	2.36	200	0.70	27.44	0.87	122.3
TER. BUNGALOW FILZ	53	53		40							130	0.34	140	0.94	4.00	2.10						0.26	2.54	200	0.70	27.44	0.87	122.5
	54	55		-								0.27	140	1.21	4.00	2.28						0.34	2.61	200	0.70	27.44	0.87	36.7
BISHOPS MILLS WAY	55	56	11								37	0.21	178	2.02	4.00	2.88						0.57	3.45	250	0.40	37.61	0.77	107.1
Diorior o mileeo trat	56	57	7		12						56	0.65	234	2.67	4.00	3.79						0.75	4.54	250	0.60	46.06	0.94	101.5
	50	57										0.00	201	2.07	1.00	0.10						0.10		200	0.00	10.00	0.01	101.0
PARK	57	34			1						3	0.37	13976	250.20	2.81	159.04		31.73	27.54		200.41	78.94	465.94	900	0.11	600.38	0.94	53.5
	34	33	1		3	1					8	1	13984	250.20	2.81	159.12		31.73	27.54		200.41	78.94	466.01	900	0.11	600.38		50.3
			1									1	I		I						1			11		1	1 1	
HAWKSTONE	43	44	1	22							59	1.19	59	1.19	4.00	0.96					1	0.33	1.30	250	1.00	59.46	1.21	51.0
	44	45	1	8							22	0.09	81	1.28	4.00	1.31						0.36	1.67	250	0.50	42.05	0.86	29.0
ENDENVALE	45	35	1									0.08	81	1.36	4.00	1.31						0.38	1.69	250	0.50	42.05	0.86	39.8
BIRKENDALE DRIVE	35	36	7								24	1.18	105	2.54	4.00	1.70						0.71	2.41	250	0.37	36.18	0.74	93.2
	36	37	13								44	0.79	149	3.33	4.00	2.41						0.93	3.35	250	0.37	36.09	0.74	77.1
	37	33	2		3						15		164	3.33	4.00	2.66						0.93	3.59	250	0.40	37.61	0.77	17.9
BIRKENDALE DRIVE	33	32			10						27	0.56	14175	254.09	2.80	160.95		31.73	27.54		200.41	80.03	468.93	900	0.11	600.38	0.94	72.7
TEESWATER STREET	30	31			16						43	0.66	43	0.66	4.00	0.70						0.18	0.88	250	0.40	37.61	0.77	75.1
	31	32			19						51	0.41	95	1.07	4.00	1.53						0.30	1.83	250	0.40	37.61	0.77	77.9
BIRKENDALE STREET	32	18			6						16	0.37	14286	255.53	2.80	162.01		31.73	27.54		200.41	80.43	470.40	900	0.11	600.38	0.94	44.4




KANATA TOWN CENTRE CENTRAL BUSINESS DISTRICT URBANDALE CORPORATION JLR PROJECT NO.: 15712

Commercial Flow =	50000	L/ha/d	SANITARY SEWER DESIGN SHEET
q residential=	350	l/cap/d	Designed: C.B.
q hotel =	270	l/cap/d	Revised by: J.L.P.
q retirement homes =	450	l/cap/d	Checked By: D.L.
i =	0.28	l/s/ha	
SING. HOUSING	3.4	pers/hse	
MULT. HOUSING	2.7	pers/hse	
Hotel/Appartments	1.8	pers/room	
Retirement Homes	1.6	pers/room	
			Date: May 28, 2012

П

Manning's Coefficient (n) = 0.013

																		Manning's Coefficient (n) = 0.013									
								RE	ESIDENTIAL							COMME	RCIAL / INSTITU	UTIONAL	PLUGGE	ED FLOW	R	+C	П		SEWER DA	ТА	1
STREET	M	H. #					NUMBER O	FUNITS				CUMM	ULATIVE	PEAKING	POPUL.		CUMM.	COMM.		CUMM.	PEAK EXTR.	PEAK DES.	DIA		CAPAC.	VEL.	
UNLEI			SING. Stacks	Towns		. Care		Hotel/Apart		POPUL.	AREA			FACTOR	FLOW	AREA	AREA	FLOW	FLOW	FLOW	FLOW	FLOW	mm S	SLOPE %	I/s	m/s	LENGTH m
	FROM	TO			No units	Act. pop	No units	Act. pop.	Equ. pop.	people	ha	people	ha		l/s	ha	ha	l/s	l/s	l/s	l/s	l/s					
	18	16		4						11		14297	255.53	2.80	162.12		31.73	27.54		200.41	80.43	470.50	900	0.11	600.38	0.94	44.4
							_																				
COMMERCIAL PLAZA	19	17												4.00		0.52	0.52	0.45			0.15	0.60	150	0.90	14.45	0.82	26.5
COLCHESTER SQUARE	17	16		-							0.10	-	0.10	4.00			0.52	0.45			0.17	0.62	250	0.40	37.61	0.77	33.2
	40	45		10			-			07	0.50	44004	256.19	2.00	400.00		22.25	07.00		200.44	00.70	474.54	000	0.44	000.00	0.04	00.0
COLCHESTER SQUARE	16 15	15 14 A		10						27	0.56	14324 14329	256.19	2.80 2.80	162.38 162.43		32.25 32.25	27.99 27.99		200.41 200.41	80.76 80.76	471.54 471.59	900 900	0.11	600.38 600.38	0.94	66.0 25.8
	15	14 A		2						5		14329	200.19	2.00	102.43		32.23	21.99		200.41	80.76	471.59	900	0.11	000.36	0.94	20.8
ELSINORE LANE	39	28	32							86	0.53	86	0.53	4.00	1.40						0.15	1.55	250	1.00	59.46	1.21	56.7
	28	20	18	1	1	1	1	+ +		49	1.47	135	2.00	4.00	2.19	<u> </u>				<u> </u>	0.56	2.75	250	0.40	37.61	0.77	43.0
	24	24	12	1				+ +		32	0.14	167	2.14	4.00	2.71	1					0.60	3.31	250	0.40	37.61	0.77	43.0
ELSINORE LANE	23	306	8					1 1		22	0.24	189	2.38	4.00	3.06						0.67	3.73	250	0.44	39.41	0.80	48.8
ENDENVALE DRIVE	306	14 A									0.45	189	2.83	4.00	3.06						0.79	3.85	250	0.49	41.68	0.85	46.4
		1						1 1		1																	
COLCHESTER SQUARE	14 A	14										14518	259.02	2.79	164.23		32.25	27.99		200.41	81.56	474.19	900	0.11	600.38	0.94	14.7
	Church	14												4.00		0.52	0.52	0.45			0.15	0.60	150	1.00	15.23	0.86	35.0
COLCHESTER SQUARE	14	11	4							11	0.16	14529	259.18	2.79	164.34		32.77	28.45		200.41	81.75	474.94		0.11	600.38	0.94	72.6
TERON	11	10										14529	259.18	2.79	164.34		32.77	28.45		200.41	81.75	474.94	900	0.11	600.38	0.94	29.6
	10	EX.									0.25	14529	259.43	2.79	164.34		32.77	28.45		200.41	81.82	475.01	900	0.11	600.38	0.94	72.3
							_																				
TERON	0.P.P.	EX.					_	+				_		4.00					0.78	0.78		0.78	100 F	orcemain			
	-	-		-								11500	050.40	0.70	404.04		32.77	00.45		004.40	04.00	175 70			000.04	0.04	
TERON	EX.	EX. 2										14529	259.43	2.79	164.34		32.77	28.45		201.19	81.82	475.79	680	0.96	838.61	2.31	9.4
	+		+ +	-				+ +																			
							-																				
			(1)																								
			As per	Kanata To	own Centre S	anitary Trunk	Sewer Study,	, revised March 2	27, 1996, by Rol	binson Consulta	nts Inc.																
	1																										
			(2) Park o	r open sp	pace area.								1							İ							
																İ											
			(3) Equiva	lent pop	ulation base	on 208 roon	ns and 20 sta	aff members.																			
							to provide fl	lexibility in futur	e developmen	t as per Kanata	a Town																
	1		Centre	Sanitary	/ Trunk Stud	у.						L															
	_		4																	L							
			4										 							ļ			₩				
			4										<u> </u>			-											
				-	-		-	<u>т т</u>	-		-		<u> </u>	L													
							-				1		ļ														



ingineers, Architects & Planners

q (res) =

350

14 A

Church

11

10

O.P.P

EX.

14

14

EX.

EX.

EX.

4

COLCHESTER SQUARE

COLCHESTER SQUARE

TERON

TERON

TERON

I/cap/day

SAL	VIT.	ARY	SEV	VEI

Slope

0.60

2.20

0.12 0.12

0.40

1.41

0.12

0.40

1.20

0.12

0.40

0.40

0.81

0.12

0.12

0.40

0.40

0.40

0.77

0.12

0.11

0.11

1.40

0.40

0.70

0.90

0.11

0,11

0.70

0.70

0.70

0.40

0.60

0 1 1

0.11

1.00

0.50

0.50

0.37

0.37

0.40

0.11

0.40

0.40

0.11

0.11

0,90

0.40

0.11

0.11

1 00

0.40

0.40

0.44

0.49

0.11

1.00

0.11

0.11

0.11

Forcema

0.96

Designed by: L.N.D.

Checked by: M.F.S.

SEWER DATA

l/s

46.08

88.20

497.22

497.22

37.61

497.22

37.61

65.18

497.22

37.61

37.61

53.66

497.22

497.22

37.61

37.61

37.61

497.22

600.38

600.38

38.80

37.61

27.44

56.41

600 38

600.38

27.44

27.44

27.44

37.61

46.06

600 38

600.38

59.46

42.05

42.05

36 18

36.09

37.61

600.38

37.61

37.61

600 38

600.38

14.45

37.61

600.38

600.38

59 46 37.61

37.61

39.41

41.68

600.38

15.23

600,38

600.38

600.38

838.61

52.18

70.70

CAPAC.

50,000 q(com) =I/ha/day q (inst) = 50,000 I/ha/day KANATA TOWN CENTRE 1 = 0.280 l/s/ha Singles, Townhouses, Ter. Bungalows = 3.8 pers / unit (low & medium density) (RESIDENTIAL) URBANDALE CORPORATION Stacked Townhouses / Apartments = 2.2 pers / unit (high density) Stacked Townhouses / Apartments = 80 units / ha (high density) CUMMULATIVE No. of UNITS M.H. # POPUL PEAK Peaking INFIL AREA POPUL. AREA Factor STREET Singles & Stacked FLOW FLOW FLOW DIA. Townhouses ownhouses ha peop. ha I/s mm I/c I/s 2.50 Α 90 92 37 0.80 141 0.80 4.00 2.28 0.22 250 250 3.08 0.56 3.64 13 1.19 1.99 4.00 190 95 89 66.80 4831 68 79 3.26 63.77 19.26 19.41 270 61 825 825 94 64.21 95 10 0.52 69.31 3.26 271.20 4869 0.33 85 87 1.17 в 19 1.19 72 1,19 4.00 1.50 250 87 89 26 0.82 171 2.01 4.00 2.77 0.56 3.33 250 89 84 12 0.35 5085 71.67 3.24 66.71 20.07 274.35 825 A С 80 82 20 1.08 1.08 4.00 1.23 0.30 1.53 250 82 84 28 0.83 182 1.91 4.00 2.96 0.53 3.49 250 84 79 A 14 0.54 5321 74.12 3.22 69.40 20.75 277.74 825 D 75 76 19 0.37 0.37 4.00 1.17 0.10 1.27 250 72 77 0.18 2.59 76 77 20 14 0.29 148 0.66 4.00 2.40 250 79 0.63 201 1.29 4.00 3.26 0.36 3.62 250 PARK EASEMENT 79 67 0.98 76.39 71.69 21.39 280.66 5522 825 67 66 6 0.33 5545 76.72 3.20 71.95 21.48 281.01 825 0.72 BELLROCK DRIVE 70 73 73 26 10 2 56 99 2 56 4 00 1.60 2.32 250 0.54 137 2.22 0.87 3.08 250 3.10 4.00 EASEMENT 74 62 0.31 137 3.41 4.00 2.22 3.76 0.95 3.17 250 CAMBRAY LANE 62 66 25 0.48 232 3.89 4.00 1.09 4.85 250 66 65 0.53 5811 74.95 22.72 285.25 825 BISHOPS MILLS WAY 81.14 3.18 9 65 191.60 SOUTH of HWY 417 EX. 7792 191.60 3.06 96.63 53.65 188.16 900 155.52 457.35 BISHOPS MILLS WAY 65 64 2 13610 272.74 76.37 900 2.82 EDENVALE DRIVE 59 60 0.50 4.00 0.14 0.63 200 0.50 0.49 KETTLEBY STREET 61 24 0.62 122 1.12 4.00 1.97 0.31 2.28 250 60 CAMBRAY LANE 58 61 8 0.41 0.41 4.00 0.49 0.11 0.61 200 30 KETTLEBY STREET 61 64 25 0.42 247 1.95 4.00 4.00 0.55 4.55 250 BISHOPS MILLS WAY 64 63 57 13869 274.69 2.81 158.01 76.91 460,38 900 0.68 63 10 13907 275.37 2.81 158,38 77.10 460,94 900 0.94 0.26 TER. BUNGALOW Ph.2 53 48 182 0.94 4.00 2.96 3.22 200 53 3.20 0.26 3.47 200 54 198 0.94 4.00 0.27 3.54 54 55 198 1.21 4.00 3.20 0.34 200 BISHOPS MILLS WAY 55 56 57 0.81 239 312 2.02 4.00 3.88 0.57 4.44 250 11 5.05 0.75 56 19 0.65 2.67 4.00 5.80 250 0.37 57 278 41 77 95 464 82 PARK 34 14222 2 80 161 40 900 77.95 33 0.00 14234 278.41 161.51 464.93 900 2.80 3 HAWKSTONE 43 44 16 1.19 4.00 0.99 0.33 1.32 250 1.19 44 45 0.09 91 1.28 1.36 4.00 1.48 0.36 1.84 250 1.48 1.91 2.71 0.08 ENDENVALE 45 4.00 0.38 250 1.86 35 BIRKENDALE DRIVE 35 36 1.18 118 2 54 4.00 0.71 2.62 250 0.93 3.64 250 13 167 37 0.79 3.33 4.00 36 37 33 0.00 175 3.33 4.00 2.83 0.93 3.76 250 BIRKENDALE DRIVE 33 32 13 0.56 14458 282.30 2.79 163.66 79.04 468.16 900 TEESWATER STREET 30 31 0.66 0.66 1,11 0.18 1.29 18 4.00 250 31 32 19 0.41 141 1.07 4.00 2.28 0.30 2.58 250 BIRKENDALE STREET 32 0.37 79.45 470 05 18 16 4 14614 283 74 2 79 165 14 900 79.45 283.74 165.36 470.27 900 14636 2.79 COMMERCIAL PLAZA 17 19 0.52 0.52 1.50 0.45 0,15 0,60 150 COLCHESTER SQUARE 17 16 0.10 0.62 4.00 0.45 0.17 0.62 250 COLCHESTER SQUARE 0.56 14674 284.92 166.17 79.78 471.41 16 15 15 10 2.79 900 14 A 2 14682 284.92 2.79 166 25 79,78 471 48 900 0.15 ELSINORE LANE 39 28 22 0.53 0.53 4 00 1.35 1.50 250 28 24 14 1.47 137 2.00 4.00 2.22 0.56 2.78 250 23 12 0.14 0.24 182 2.14 4.00 2.96 0.60 0.67 3.55 250 ELSINORE LANE 2.38 4.00 3.45 4.11 250 23 306 8 213 ENDENVALE DRIVE 306 14 A 0.45 213 2.83 4.00 3.45 0.79 4.24 250

CITY OF KANATA

287.75

0.52

288.43

288.43

288.68

2.78

1.50

2.78

2.78

2.78

14895

14910

14910

14910

0.52

0.16

0.25

167.82

0.45

168,87

168.87

168 87

80.57

0.15

80.76

80,76

80,83

473.85

0.60

475.09

475.09

475.16

0.78

475.94

900

150

900

900


900

100

680

R DESIGN SHEET

VEL. m/s	LENGTH m
0.94 1.80	120.0 103.0
0.93	17.5
0.93	66.6
0.77 1.44	116.9 116.7
0.93	79.0
0.77 1.33	120.0 118.5
0.93	79.0
0.77	57.0
0.77	78.4
1.09	117.7
0.93	55.0 70.0
0.77	87.2
0.77	60.3
1.06	39.9 100.5
0.93	62.0
0.94	50.2
0.94	17.0
1.24 0.77	77.0 103.6
0.87	74.5
1.15	105.0
0.94	13.0
0.94	64.9
0.87	122.3
0.87 0.87	13.6 36.7
0.77	107.1
0.94	101.5
0.94 0.94	53.5 50.3
1.21	51.0
0.85	29.0
0.86 0.74	39.8 93.2
0.74	77.1
0.77	17.9
0.94	72.7
0.77	75.1 77.9
0.91	44.4
0.94	44.4
0.82	26.5
0.77	33.2
0.94 0.94	66.0 25.8
1.21	
0.77	56.7 43.0
0.77	34.0
0.80 0.85	48.8 46.4
0.91	14.7
0.86	35.0
0.94 0.94	72.6 29.6
0.94	72.3
2.31	9.4



APPENDIX D

Water Servicing Information

TYPE OF UNITS / FLOOR EAST TOWER							
TYPE OF UNIT	UNITS / FLOOR	UNITS / TOTAL					
GROUND FLOOR							
1BR	8	8					
2BR	2	2					
2nd FLOOR 10							
1BR	13	13					
2BR	6	6					
3rd FLOOR		19					
1BR	16	16					
2BR	5	5					
4th to 7th FLOOR		21					
1BR	16	64					
2BR	5	20					
8th FLOOR		84					
1BR	5	5					
2BR	3	3					
9th to 20th FLOOR		8					
1BR	4	48					
2BR	4	48					
21st to 28th FLOOF	२	96					
1BR	4	32					
2BR	4	32					
L	1	64					
TOTAL 302							

UNITS SCHEDULE EAST TOWER_NBR								
TYPE OF UNITS	NBR OF UNITS	%						
1BR	186	62%						
2BR	2BR 116 38%							
302								

TYPE OF UNIT	NBR OF UNIT	AREA / UNIT (ft²)	AREA / UNIT (m²)				
•			•				
GROUND FLC	OR						
1BR	1	965 ft ²	90 m²				
1BR	1	782 ft ²	73 m ²				
1BR	1	654 ft²	61 m ²				
1BR	1	811 ft ²	75 m ²				
1BR	1	542 ft ²	50 m ²				
1BR	1	780 ft ²	72 m ²				
1BR	1	794 ft ²	74 m²				
1BR	1	799 ft ²	74 m²				
2BR	1	962 ft ²	89 m²				
2BR	1	1 217 ft ²	113 m ²				

2nd FLOOR

21101120011			
1BR	1	542 ft ²	50 m²
1BR	1	778 ft²	72 m²
1BR	1	592 ft ²	55 m²
1BR	1	592 ft ²	55 m²
1BR	1	754 ft²	70 m²
1BR	1	845 ft²	78 m²
1BR	1	824 ft²	77 m²
1BR	1	812 ft²	75 m²
1BR	1	654 ft²	61 m²
1BR	1	784 ft²	73 m²
1BR	1	801 ft ²	74 m²
1BR	1	794 ft²	74 m²
1BR	1	768 ft ²	71 m²
2BR	1	959 ft²	89 m²
2BR	1	943 ft²	88 m²
2BR	1	1 046 ft²	97 m²
2BR	1	1 303 ft ²	121 m²
2BR	1	1 285 ft²	119 m ²
2BR	1	1 221 ft²	113 m²
	19		

3rd FLOOR

3rd FLOOR			
1BR	1	542 ft ²	50 m²
1BR	1	613 ft ²	57 m²
1BR	1	778 ft ²	72 m²
1BR	1	592 ft ²	55 m²
1BR	1	592 ft ²	55 m²
1BR	1	754 ft²	70 m²
1BR	1	845 ft ²	78 m²
1BR	1	824 ft ²	77 m²
1BR	1	757 ft²	70 m²
1BR	1	812 ft ²	75 m²
1BR	1	654 ft²	61 m²
1BR	1	784 ft ²	73 m²
1BR	1	801 ft ²	74 m²
1BR	1	794 ft ²	74 m²
1BR	1	768 ft ²	71 m²
1BR	1	885 ft²	82 m²
2BR	1	943 ft²	88 m²
2BR	1	1 206 ft ²	112 m²
2BR	1	1 239 ft ²	115 m²
2BR	1	996 ft²	93 m²
2BR	1	1 199 ft²	111 m²
	21		

TYPE OF UNIT	NBR OF UNIT	AREA / UNIT (ft²)	AREA / UNIT (m²)
4th to 7th FLO	OR		
1BR	4	542 ft ²	50 m ²
1BR	4	613 ft ²	57 m²
1BR	4	778 ft ²	72 m ²
1BR	4	592 ft ²	55 m ²
1BR	4	592 ft ²	55 m²
1BR	4	754 ft ²	70 m ²
1BR	4	845 ft ²	78 m ²
1BR	4	824 ft ²	77 m²
1BR	4	757 ft ²	70 m ²
1BR	4	812 ft ²	75 m ²
1BR	4	654 ft ²	61 m²
1BR	4	784 ft ²	73 m ²
1BR	4	801 ft ²	74 m²
1BR	4	794 ft ²	74 m²
1BR	4	768 ft ²	71 m²
1BR	4	885 ft ²	82 m²
2BR	4	943 ft²	88 m²
2BR	4	1 206 ft ²	112 m ²
2BR	4	1 239 ft ²	115 m ²
2BR	4	996 ft²	92 m²
2BR	4	1 198 ft ²	111 m ²

8th FLOOR

1BR	1	629 ft ²	58 m²
1BR	1	614 ft²	57 m²
1BR	1	609 ft ²	57 m²
1BR	1	592 ft ²	55 m²
1BR	1	593 ft ²	55 m²
2BR	1	835 ft²	78 m²
2BR	1	924 ft ²	86 m²
2BR	1	865 ft²	80 m²
	8		

9th to 20th FLOOR

1BR	12	614 ft²	57 m²
1BR	12	609 ft ²	57 m²
1BR	12	592 ft ²	55 m²
1BR	12	593 ft ²	55 m²
2BR	12	827 ft ²	77 m²
2BR	12	835 ft²	78 m²
2BR	12	924 ft²	86 m²
2BR	12	865 ft²	80 m²
	96		

21st to 28th FLOOR

2 IST TO 28TH FLOOR								
1BR	8	614 ft²	57 m²					
1BR	8	609 ft ²	57 m²					
1BR	8	592 ft²	55 m²					
1BR	8	593 ft²	55 m²					
2BR	8	827 ft²	77 m²					
2BR	8	835 ft²	78 m²					
2BR	8	924 ft²	86 m²					
2BR	8	865 ft²	80 m²					
	64							
	302							

FLOOR	NBR OF FLOORS	AREA / FLOOR (ft²)	AREA / FLOOR (m²)	AREA TOTAL (ft²)	AREA TOTAL (m²)
U-PARKING 3	1	7 776 ft ²	722 m ²	7 776 ft ²	722 m ²
U-PARKING 2	1	5 856 ft ²	544 m ²	5 856 ft ²	544 m²
U-PARKING 1	1	2 595 ft ²	241 m ²	2 595 ft ²	241 m²
GROUND FLOOR	1	12 079 ft ²	1 122 m ²	12 079 ft ²	1 122 m²
2nd FLOOR	1	15 566 ft ²	1 446 m ²	15 566 ft ²	1 446 m²
3rd FLOOR	1	16 523 ft ²	1 535 m ²	16 523 ft ²	1 535 m²
4th to 7th FLOOR	4	16 523 ft ²	1 535 m ²	66 094 ft ²	6 140 m ²
8th FLOOR	1	5 321 ft ²	494 m ²	5 321 ft ²	494 m ²
9th to 20th FLOOR	12	5 505 ft ²	511 m ²	66 062 ft ²	6 137 m²
21st to 28th FLOOR	8	5 505 ft ²	511 m ²	44 041 ft ²	4 092 m ²
TOTAL	•	93 251 ft ²	8 663 m ²	241 914 ft ²	22 475 m ²

	GROSS CON	STRUCTION ARE	A_EAST TOWER	Ł	
FLOOR	NBR OF FLOORS	AREA / FLOOR (ft²)	AREA / FLOOR (m²)	AREA TOTAL (ft ²)	AREA TOTAL (m²)
GROUND FLOOR	1	19 021 ft ²	1 767 m ²	19 021 ft ²	1 767 m²
2nd FLOOR	1	19 645 ft ²	1 825 m²	19 645 ft ²	1 825 m²
3rd FLOOR	1	20 241 ft ²	1 880 m ²	20 241 ft ²	1 880 m²
4th to 7th FLOOR	4	20 240 ft ²	1 880 m ²	80 960 ft ²	7 521 m²
8th FLOOR	1	7 375 ft ²	685 m ²	7 375 ft ²	685 m²
9th to 20th FLOOR	12	6 977 ft ²	648 m ²	83 726 ft ²	7 778 m ²
21st to 28th FLOOR	8	6 977 ft ²	648 m ²	55 817 ft ²	5 186 m²
MECHANICAL PENTHOUSE	1	2 139 ft ²	199 m ²	2 139 ft ²	199 m²
TOTAL		102 615 ft ²	9 533 m²	288 923 ft ²	26 842 m ²

	I	RENTABLE AREA	_EAST TOWER		
FLOOR	NBR OF FLOORS	AREA / FLOOR (ft ²)	AREA / FLOOR (m²)	AREA TOTAL (ft ²)	AREA TOTAL (m²)
GROUND FLOOR	1	8 305 ft ²	772 m ²	8 305 ft ²	772 m ²
2nd FLOOR	1	16 299 ft ²	1 514 m²	16 299 ft ²	1 514 m²
3rd FLOOR	1	17 379 ft ²	1 615 m ²	17 379 ft ²	1 615 m²
4th to 7th FLOOR	4	17 379 ft ²	1 615 m ²	69 515 ft ²	6 458 m²
8th FLOOR	1	5 661 ft ²	526 m ²	5 661 ft²	526 m ²
9th to 20th FLOOR	12	5 859 ft ²	544 m²	70 312 ft ²	6 532 m²
21st to 28th FLOOR	8	5 859 ft ²	544 m²	46 875 ft ²	4 355 m²
TOTAL	•	76 742 ft ²	7 130 m ²	234 347 ft ²	21 772 m ²

C	OMMERCIAL SPACE AREA_EAST TO	WER
	AREA (ft²)	AREA (m²)
COMMERCIAL	4 310 ft²	400 m ²

	GROSS CONSTRUC	TION AREA SU	IMMARY_EAST TOV	VER		
FLOOR	USAGE	NBR OF FLOORS	AREA / FLOOR (ft ²)	AREA / FLOOR (m²)	AREA TOTAL (ft²)	AREA TOTAL (m²)
GROUND FLOOR	CIRCULATION	1	760 ft ²	71 m ²	760 ft ²	71 m ²
GROUND FLOOR	COMMERCIAL	1	4 310 ft ²	400 m ²	4 310 ft ²	400 m ²
GROUND FLOOR	COMMON AREA	1	3 499 ft ²	325 m ²	3 499 ft ²	325 m ²
GROUND FLOOR	RESIDENTIAL	1	8 305 ft ²	772 m ²	8 305 ft ²	772 m ²
GROUND FLOOR	SERVICES	1	330 ft ²	31 m ²	330 ft ²	31 m ²
GROUND FLOOR	VERTICAL CIRCULATION	1	1 817 ft ²	169 m ²	1 817 ft ²	169 m ²
	VEITHORE OINCOLATION		19 021 ft ²	1 767 m ²	19 021 ft ²	1 767 m ²
2nd FLOOR	CIRCULATION	1	1 930 ft ²	179 m ²	1 930 ft ²	179 m ²
2nd FLOOR	RESIDENTIAL	1	16 299 ft ²	1 514 m ²	16 299 ft ²	1 514 m ²
2nd FLOOR	SERVICES	1	257 ft ²	24 m ²	257 ft ²	24 m ²
2nd FLOOR	VERTICAL CIRCULATION	1	1 160 ft ²	108 m ²	1 160 ft ²	108 m ²
		· · ·	19 645 ft ²	1 825 m ²	19 645 ft ²	1 825 m ²
3rd FLOOR	CIRCULATION	1	1 613 ft ²	150 m ²	1 613 ft ²	150 m ²
3rd FLOOR	RESIDENTIAL	1	17 379 ft ²	1 615 m ²	17 379 ft ²	1 615 m ²
3rd FLOOR	SERVICES	1	257 ft ²	24 m ²	257 ft ²	24 m ²
3rd FLOOR	VERTICAL CIRCULATION	1	991 ft ²	92 m ²	991 ft ²	92 m²
			20 241 ft ²	1 880 m ²	20 241 ft ²	1 880 m ²
4th to 7th FLOOR	CIRCULATION	4	1 613 ft ²	150 m ²	6 454 ft²	600 m ²
1th to 7th FLOOR	RESIDENTIAL	4	17 379 ft ²	1 615 m ²	69 515 ft ²	6 458 m²
4th to 7th FLOOR	SERVICES	4	257 ft ²	24 m ²	1 027 ft ²	95 m²
4th to 7th FLOOR	VERTICAL CIRCULATION	4	991 ft ²	92 m ²	3 965 ft ²	368 m²
			20 240 ft ²	1 880 m²	80 960 ft ²	7 521 m²
8th FLOOR	CIRCULATION	1	738 ft ²	69 m²	738 ft ²	69 m²
8th FLOOR	RESIDENTIAL	1	5 661 ft ²	526 m ²	5 661 ft ²	526 m²
8th FLOOR	SERVICES	1	82 ft ²	8 m ²	82 ft ²	8 m ²
8th FLOOR	VERTICAL CIRCULATION	1	893 ft ²	83 m ²	893 ft ²	83 m²
			7 375 ft ²	685 m²	7 375 ft ²	685 m²
Oth to 20th FLOOR	CIRCULATION	12	566 ft ²	53 m ²	6 791 ft²	631 m²
oth to 20th FLOOR	RESIDENTIAL	12	5 859 ft ²	544 m ²	70 312 ft ²	6 532 m ²
Oth to 20th FLOOR	SERVICES	12	56 ft ²	5 m ²	676 ft ²	63 m ²
9th to 20th FLOOR	VERTICAL CIRCULATION	12	495 ft ²	46 m ²	5 946 ft ²	552 m²
			6 977 ft ²	648 m ²	83 726 ft ²	7 778 m²
21st to 28th FLOOR	CIRCULATION	8	566 ft ²	53 m ²	4 527 ft ²	421 m ²
21st to 28th FLOOR	RESIDENTIAL	8	5 859 ft ²	544 m ²	46 875 ft ²	4 355 m ²
21st to 28th FLOOR	SERVICES	8	56 ft ²	5 m ²	451 ft ²	42 m ²
21st to 28th FLOOR	VERTICAL CIRCULATION	8	495 ft ²	46 m ²	3 964 ft ²	368 m²
			6 977 ft ²	648 m ²	55 817 ft ²	5 186 m²
MECHANICAL PENTHOUSE	TECHNICAL	1	2 139 ft ²	199 m ²	2 139 ft ²	199 m ²
			2 139 ft ²	199 m²	2 139 ft ²	199 m²
			102 615 ft ²	9 533 m²	288 923 ft ²	26 842 m ²

AMENITIES F	REQUIREMENT_E	AST TOWER
NBR OF UNITS	AMENITIES (6m² / UNIT)	MIN. 50% COMMUNAL
302	1 812 m ²	906 m ²

PROVIDED AME	NITIES_EAST TOWER
TYPE OF AMENITIES	AREA TOTAL (m²)
COMMUNAL AMENITIES	1 197 m²
PERSONAL AMENITIES	1 997 m²

PARKING RE	QUIREMENT_EAST TOWER
NBR OF	PARKING RATIO
UNITS	(1 / UNIT)
302	302

BIKE RACKS	REQUIREMENT_EAST TOWER
NBR OF	BIKE RACKS RATIO
UNITS	(0.5 / UNIT)
302	151

NOTES GÉNÉRALES General Notes

- Ces documents d'architecture sont la propriété exclusive de

 NEUF architect(e)s et ne pourront être utilisés, reproduits ou copiés sans autorisation écrite préalable. / These architectural documents are the exclusive property of NEUF architect(e)s and cannot be used, copied or reproduced without written pre-authorisation
 Les dimensions apparaissant aux documents devront être vérifiées
 par l'entrepreneur avant le début des travaux. / All dimensions which appear on the documents must be verify by the contractor before to start the work.

 Veuillez aviser l'architecte de toute dimension erreur et/ou

 divergences entre ces documents et ceux des autres professionnels. / The architect must be notified of all errors, omissions and discrepancies between these documents and those of the others professionnals.

 Les dimensions sur ces documents doivent être lues et non

 mesurées. / The dimensions on these documents must be read and not measured.


STRUCTURE Structural **Goodeve Structural Inc.** 18-77, Auriga Drive, Ottawa ON K2E 7Z7 T 613 226 4558 goodevestructural.ca

ARCHITECTURE DE PAYSAGE Landscape Architect James B. Lennox & Associates 3332, Carling Avenue, Ottawa ON K2H 5A8 T 613 722 5168 jbla.ca

CIVIL Civil Novatech Eng. Consultants Ltd. 240, Michael Cowpland Drive, Suite 200, Ottawa ON K2M 1P6 T 613 234 9643 novatech-eng.com

ARCHITECTES Architect **NEUF architect(e)S** SENCRL 630, boul. René-Lévesque O. 32e étages, Montréal QC H3B 1S6 T 514 847 1117 NEUFarchitectes.com

SCEAU / Seal



CLIENT Client



OUVRAGE Project **1200 MARITIME WAY** (KANATA RENTAL)

EMPLACEMENT Location

NO PROJET №. 12371.00

RÉVISION Revision

DATE (aa-mm-jj)

DESSINÉ PAR Drawn by	VÉRIFIÉ PAR Checked
DATE (aa.mm.jj)	ÉCHELLE Scale
NOV 2018	
TITRE DU DESSIN Drawing Title	
STATISTICS -	EAST
TOWER	



1BR	1	813 ft ²	76 m ²
1BR	1	674 ft ²	63 m ²
1BR	1	800 ft ²	74 m ²
1BR	1	704 ft ²	65 m ²
1BR	1	706 ft ²	66 m ²
1BR	1	793 ft ²	74 m ²
1BR	1	802 ft ²	75 m ²
1BR	1	795 ft ²	74 m ²
1BR	1	807 ft ²	75 m ²
1BR	1	634 ft ²	59 m ²
1BR	1	793 ft ²	74 m ²
1BR	1	795 ft ²	74 m ²
1BR	1	802 ft ²	74 m ²
1BR	1	795 ft ²	74 m ²
2BR	1	992 ft ²	92 m ²
2BR 2BR	1	1 243 ft ²	115 m ²
2BR 2BR	1	1 082 ft ²	101 m ²
2BR 2BR	1	1 170 ft ²	109 m ²
2BR 2BR	1	1 226 ft ²	109 m 114 m ²
2BR 2BR	1	1 050 ft ²	98 m ²
I		100011	30 11
	20	1000 11	90111
	20		
1BR		813 ft²	76 m ²
1BR 1BR	20 1 1	813 ft ² 674 ft ²	76 m² 63 m²
1BR	20 1 1 1	813 ft ² 674 ft ² 800 ft ²	76 m² 63 m² 74 m²
1BR 1BR 1BR 1BR	20 1 1	813 ft ² 674 ft ² 800 ft ² 704 ft ²	76 m ² 63 m ² 74 m ² 65 m ²
1BR 1BR 1BR	20 1 1 1 1 1 1	813 ft ² 674 ft ² 800 ft ² 704 ft ² 706 ft ²	76 m² 63 m² 74 m²
1BR1BR1BR1BR1BR1BR1BR	20 1 1 1 1 1 1 1 1	813 ft ² 674 ft ² 800 ft ² 704 ft ² 706 ft ² 793 ft ²	76 m ² 63 m ² 74 m ² 65 m ² 66 m ² 74 m ²
1BR 1BR 1BR 1BR 1BR 1BR 1BR 1BR 1BR 1BR 1BR	20 1 1 1 1 1 1	813 ft ² 674 ft ² 800 ft ² 704 ft ² 706 ft ² 793 ft ² 802 ft ²	76 m ² 63 m ² 74 m ² 65 m ² 66 m ² 74 m ² 75 m ²
1BR1BR1BR1BR1BR1BR1BR	20 1 1 1 1 1 1 1 1 1	813 ft ² 674 ft ² 800 ft ² 704 ft ² 706 ft ² 793 ft ² 802 ft ² 795 ft ²	76 m ² 63 m ² 74 m ² 65 m ² 66 m ² 74 m ²
1BR 1BR 1BR 1BR 1BR 1BR 1BR 1BR 1BR 1BR 1BR 1BR 1BR 1BR 1BR	20 1 1 1 1 1 1 1 1 1 1 1 1 1	813 ft ² 674 ft ² 800 ft ² 704 ft ² 706 ft ² 793 ft ² 802 ft ² 795 ft ² 807 ft ²	76 m ² 63 m ² 74 m ² 65 m ² 66 m ² 74 m ² 75 m ² 74 m ² 75 m ²
1BR 1BR 1BR 1BR 1BR 1BR 1BR 1BR 1BR 1BR 1BR 1BR 1BR 1BR 1BR 1BR 1BR 1BR 1BR 1BR	20 1 1 1 1 1 1 1 1 1 1 1 1 1	813 ft ² 674 ft ² 800 ft ² 704 ft ² 706 ft ² 793 ft ² 802 ft ² 795 ft ² 807 ft ² 634 ft ²	76 m ² 63 m ² 74 m ² 65 m ² 66 m ² 74 m ² 75 m ² 75 m ² 59 m ²
1BR 1BR	20 1 1 1 1 1 1 1 1 1 1 1 1 1	813 ft ² 674 ft ² 800 ft ² 704 ft ² 706 ft ² 793 ft ² 802 ft ² 795 ft ² 807 ft ² 634 ft ² 793 ft ²	76 m ² 63 m ² 74 m ² 65 m ² 66 m ² 74 m ² 75 m ² 75 m ² 59 m ² 74 m ²
1BR 1BR	20 1 1 1 1 1 1 1 1 1 1 1 1 1	813 ft ² 674 ft ² 800 ft ² 704 ft ² 706 ft ² 793 ft ² 802 ft ² 807 ft ² 634 ft ² 793 ft ² 795 ft ²	76 m ² 63 m ² 74 m ² 65 m ² 66 m ² 74 m ² 75 m ² 75 m ² 75 m ² 59 m ² 74 m ² 74 m ²
1BR 1BR	20 1 1 1 1 1 1 1 1 1 1 1 1 1	813 ft² 674 ft² 800 ft² 704 ft² 705 ft² 802 ft² 795 ft² 807 ft² 795 ft² 807 ft² 807 ft² 807 ft² 802 ft²	76 m ² 63 m ² 74 m ² 65 m ² 66 m ² 74 m ² 75 m ² 75 m ² 59 m ² 74 m ² 74 m ² 74 m ² 74 m ²
1BR 1BR	20 1 1 1 1 1 1 1 1 1 1 1 1 1	813 ft² 674 ft² 800 ft² 704 ft² 706 ft² 793 ft² 802 ft² 795 ft² 807 ft² 634 ft² 795 ft² 802 ft² 795 ft² 802 ft² 795 ft² 802 ft² 795 ft² 802 ft² 795 ft² 802 ft² 795 ft² 802 ft² 795 ft² 802 ft² 795 ft²	76 m² 63 m² 74 m² 65 m² 66 m² 74 m² 75 m² 75 m² 59 m² 74 m² 74 m² 74 m² 74 m² 74 m² 74 m² 74 m² 74 m² 74 m² 74 m² 74 m² 74 m² 74 m² 74 m² 74 m² 74 m²
1BR 2BR	20 1 1 1 1 1 1 1 1 1 1 1 1 1	813 ft² 674 ft² 800 ft² 704 ft² 705 ft² 802 ft² 795 ft² 807 ft² 634 ft² 795 ft² 802 ft² 793 ft² 93 ft² 807 ft² 93 ft² 795 ft² 802 ft² 795 ft² 802 ft² 795 ft² 802 ft² 795 ft² 802 ft² 795 ft² 802 ft² 795 ft² 802 ft² 802 ft² 795 ft² 802 ft² 795 ft² 802 ft² 795 ft² 992 ft²	76 m² 63 m² 74 m² 65 m² 66 m² 74 m² 75 m² 75 m² 59 m² 74 m² 92 m²
1BR 1BR 1BR 1BR 1BR 1BR 1BR 1BR 1BR 1BR 1BR 1BR 1BR 1BR 1BR 1BR 1BR 2BR 2BR	20 1 1 1 1 1 1 1 1 1 1 1 1 1	813 ft² 674 ft² 800 ft² 704 ft² 705 ft² 802 ft² 795 ft² 807 ft² 634 ft² 795 ft² 802 ft² 795 ft² 802 ft² 795 ft² 802 ft² 795 ft² 802 ft² 795 ft² 802 ft² 795 ft² 992 ft² 1 243 ft²	76 m² 63 m² 74 m² 65 m² 66 m² 74 m² 75 m² 75 m² 59 m² 74 m² 92 m² 115 m²
1BR 1BR 1BR 1BR 1BR 1BR 1BR 1BR 1BR 1BR 1BR 1BR 1BR 1BR 2BR 2BR 2BR	20 1 1 1 1 1 1 1 1 1 1 1 1 1	813 ft² 674 ft² 800 ft² 704 ft² 705 ft² 802 ft² 795 ft² 992 ft² 1 243 ft² 1 082 ft²	76 m² 63 m² 74 m² 65 m² 66 m² 74 m² 75 m² 74 m² 75 m² 59 m² 74 m² 74 m² 74 m² 74 m² 74 m² 74 m² 74 m² 74 m² 74 m² 74 m² 74 m² 74 m² 74 m² 74 m² 74 m² 74 m² 74 m² 74 m² 74 m² 101 m²
1BR 1BR 1BR 1BR 1BR 1BR 1BR 1BR 1BR 1BR 1BR 1BR 1BR 1BR 1BR 1BR 1BR 2BR 2BR	20 1 1 1 1 1 1 1 1 1 1 1 1 1	813 ft² 674 ft² 800 ft² 704 ft² 705 ft² 802 ft² 795 ft² 807 ft² 634 ft² 795 ft² 802 ft² 795 ft² 802 ft² 795 ft² 802 ft² 795 ft² 802 ft² 795 ft² 802 ft² 795 ft² 992 ft² 1 243 ft²	76 m² 63 m² 74 m² 65 m² 66 m² 74 m² 75 m² 75 m² 59 m² 74 m² 92 m² 115 m²

		2BR	1	1 083 π²	101 m ²	
		2BR	1	1 170 ft ²	109 m ²	
813 ft ²	76 m ²	9				
674 ft²	63 m ²					
800 ft ²	74 m²	9th to 20th FL	.OOR			
704 ft ²	65 m²	1BR	12	753 ft ²	70 m ²	
706 ft ²	66 m²	1BR	12	813 ft ²	76 m²	
793 ft ²	74 m²	1BR	12	796 ft ²	74 m²	
802 ft ²	75 m²	1BR	12	802 ft ²	74 m²	
795 ft ²	74 m²	1BR	12	639 ft ²	59 m ²	
807 ft ²	75 m ²	2BR	12	1 174 ft ²	109 m ²	
634 ft²	59 m²	2BR	12	1 083 ft ²	101 m ²	
793 ft ²	74 m²	2BR	12	1 170 ft ²	109 m ²	
795 ft ²	74 m²	2BR	12	1 117 ft ²	104 m ²	
802 ft ²	74 m²		108	·		
795 ft ²	74 m²					
992 ft²	92 m²	21st to 30th F	LOOR			
1 243 ft²	115 m ²	1BR	10	753 ft ²	70 m ²	
1 082 ft ²	101 m ²	1BR	10	802 ft ²	74 m²	
1 170 ft²	109 m ²	1BR	10	639 ft ²	59 m²	
1 226 ft²	114 m²	2BR	10	1 174 ft ²	109 m ²	
1 050 ft²	98 m²	2BR	10	1 024 ft ²	95 m²	
		2BR	10	1 233 ft ²	115 m ²	
		2BR	10	1 117 ft ²	104 m ²	
			70			

2BR	1	1 170 ft ²	109 m ²
	9		•
9th to 20th FL	OOR		
1BR	12	753 ft²	70 m ²
1BR	12	813 ft ²	76 m ²
1BR	12	796 ft ²	74 m²
1BR	12	802 ft ²	74 m ²
1BR	12	639 ft²	59 m²
2BR	12	1 174 ft²	109 m ²
2BR	12	1 083 ft ²	101 m ²
2BR	12	1 170 ft ²	109 m ²
2BR	12	1 117 ft ²	104 m ²
	108		
21st to 30th Fl	_OOR		
1BR	10	753 ft²	70 m ²
1BR	10	802 ft ²	74 m ²
1BR	10	639 ft ²	59 m ²

313

8th FLOOR			
1BR	1	753 ft²	70 m²
1BR	1	813 ft ²	76 m²
1BR	1	796 ft ²	74 m²
1BR	1	802 ft ²	74 m²
1BR	1	639 ft ²	59 m²
1BR	1	879 ft²	82 m²
2BR	1	1 174 ft²	109 m ²
2BR	1	1 083 ft ²	101 m ²
2BR	1	1 170 ft²	109 m ²
	9	•	

	1BR	4	674 ft²	63 m²
	1BR	4	800 ft ²	74 m²
	1BR	4	704 ft²	65 m²
	1BR	4	706 ft ²	66 m²
	1BR	4	793 ft ²	74 m²
	1BR	4	802 ft ²	75 m²
	1BR	4	795 ft²	74 m²
	1BR	4	807 ft ²	75 m²
	1BR	4	634 ft²	59 m²
	1BR	4	793 ft ²	74 m²
	1BR	4	795 ft ²	74 m²
	1BR	4	802 ft ²	74 m²
	1BR	4	795 ft²	74 m²
	2BR	4	992 ft²	92 m²
	2BR	4	1 243 ft²	115 m²
	2BR	4	1 082 ft²	101 m²
	2BR	4	1 170 ft²	109 m ²
	2BR	4	1 226 ft²	114 m²
	2BR	4	1 050 ft²	98 m²
•		80		

UNITS SCHEDULE / FLOOR_WEST TOWER
 TYPE OF
 NBR OF
 AREA /
 AREA /

 UNIT
 UNIT
 UNIT (ft²)
 UNIT (m²)
 4th to 7th FLOOR
 1BR
 4
 813 ft²
 76 m²

 1BR
 4
 674 ft²
 63 m²

UNITS SCI	IEDULE WEST TO	OWER_NBR
TYPE OF UNITS	NBR OF UNITS	%
1BR	185	59%
2BR	128	41%
	313	

UNITS SCHEDULE / FLOOR_WEST TOWER

TYPE OF NBR OF AREA / AREA / UNIT UNIT UNIT (ft²) UNIT (m²)

 1BR
 1
 849 ft²
 79 m²

 1BR
 1
 759 ft²
 71 m²

 1BR
 1
 760 ft²
 71 m²

 1BR
 1
 760 ft²
 71 m²

 1BR
 1
 673 ft²
 63 m²

 1BR
 1
 792 ft²
 74 m²

 2BR
 1
 1 100 ft²
 102 m²

 6
 6
 6
 6

GROUND FLOOR

TYPE OF UNITS / FLOOR WEST TOWER				
TYPE OF UNIT	UNITS / FLOOR	UNITS / TOTAL		
GROUND FLOOR				
1BR	5	5		
2BR	1	1		
2nd FLOOR		6		
1BR	14	14		
2BR	6	6		
		20		
3rd FLOOR				
1BR	14	14		
2BR	6	6		
4th to 7th FLOOR		20		
1BR	14	56		
2BR	6	24		
8th FLOOR		80		
1BR	6	6		
2BR	3	3		
9th to 20th FLOOR		9		
1BR	5	60		
2BR	4	48		
21st to 30th FLOOF	R	108		
1BR	3	30		
2BR	4	40		
		70		
TOTAL		313		

GROSS FLOOR AREA_WEST TOWER					
FLOOR	NBR OF FLOORS	AREA / FLOOR (ft ²)	AREA / FLOOR (m²)	AREA TOTAL (ft²)	AREA TOTAL (m²)
U-PARKING 2	1	3 914 ft ²	364 m²	3 914 ft ²	364 m²
U-PARKING 1	1	2 879 ft ²	267 m ²	2 879 ft ²	267 m ²
GROUND FLOOR	1	4 705 ft ²	437 m ²	4 705 ft ²	437 m ²
2nd FLOOR	1	17 031 ft ²	1 582 m ²	17 031 ft ²	1 582 m²
3rd FLOOR	1	16 558 ft ²	1 538 m ²	16 558 ft ²	1 538 m²
4th to 7th FLOOR	4	16 558 ft ²	1 538 m ²	66 230 ft ²	6 153 m²
8th FLOOR	1	7 610 ft ²	707 m ²	7 610 ft ²	707 m ²
9th to 20th FLOOR	12	7 824 ft ²	727 m ²	93 892 ft ²	8 723 m ²
21st to 30th FLOOR	10	6 292 ft²	585 m²	62 916 ft ²	5 845 m²
TOTAL	•	83 370 ft ²	7 745 m ²	275 735 ft ²	25 617 m ²

GROSS CONSTRUCTION AREA_WEST TOWER					
FLOOR	NBR OF FLOORS	AREA / FLOOR (ft²)	AREA / FLOOR (m²)	AREA TOTAL (ft ²)	AREA TOTAL (m²)
GROUND FLOOR	1	9 837 ft²	914 m²	9 837 ft²	914 m²
2nd FLOOR	1	19 892 ft ²	1 848 m²	19 892 ft ²	1 848 m²
3rd FLOOR	1	19 892 ft ²	1 848 m²	19 892 ft ²	1 848 m ²
4th to 7th FLOOR	4	19 892 ft ²	1 848 m²	79 569 ft ²	7 392 m ²
8th FLOOR	1	9 785 ft²	909 m²	9 785 ft²	909 m²
9th to 20th FLOOR	12	9 595 ft²	891 m ²	115 136 ft ²	10 697 m ²
21st to 30th FLOOR	10	8 002 ft ²	743 m ²	80 021 ft ²	7 434 m ²
MECHANICAL PENTHOUSE	1	2 139 ft ²	199 m²	2 139 ft ²	199 m ²
TOTAL		99 035 ft ²	9 201 m²	336 272 ft ²	31 241 m ²

RENTABLE AREA_WEST TOWER					
FLOOR	NBR OF FLOORS	AREA / FLOOR (ft ²)	AREA / FLOOR (m²)	AREA TOTAL (ft ²)	AREA TOTAL (m²)
GROUND FLOOR	1	4 933 ft ²	458 m ²	4 933 ft ²	458 m²
2nd FLOOR	1	17 476 ft ²	1 624 m²	17 476 ft²	1 624 m²
3rd FLOOR	1	17 476 ft ²	1 624 m²	17 476 ft²	1 624 m²
4th to 7th FLOOR	4	17 476 ft²	1 624 m²	69 903 ft ²	6 494 m²
8th FLOOR	1	8 107 ft ²	753 m ²	8 107 ft ²	753 m²
9th to 20th FLOOR	12	8 346 ft ²	775 m ²	100 149 ft ²	9 304 m²
21st to 30th FLOOR	10	6 741 ft²	626 m ²	67 412 ft ²	6 263 m²
TOTAL		80 554 ft ²	7 484 m²	285 455 ft ²	26 520 m ²

FL 0.0 D	USACE	NBR OF	AREA / FLOOR	AREA /	AREA TOTAL	AREA TOTA
FLOOR	USAGE	FLOORS	(ft²)	FLOOR (m ²)	(ft²)	(m²)
			4 000 52	400 3	4 000 (12	400 2
ROUND FLOOR	CIRCULATION	1	1 293 ft ²	120 m ²	1 293 ft ²	120 m ²
ROUND FLOOR	COMMON AREA	1	2 328 ft ²	216 m ²	2 328 ft ²	216 m ²
ROUND FLOOR	RESIDENTIAL	1	4 933 ft ²	458 m ²	4 933 ft ²	458 m ²
ROUND FLOOR	SERVICES	1	26 ft ²	2 m ²	26 ft ²	2 m ²
ROUND FLOOR	VERTICAL CIRCULATION	1	1 257 ft ²	117 m ²	1 257 ft ²	117 m ²
			9 837 ft ²	914 m²	9 837 ft²	914 m²
nd FLOOR	CIRCULATION	1	1 465 ft ²	136 m ²	1 465 ft ²	136 m²
nd FLOOR	RESIDENTIAL	1	17 476 ft ²	1 624 m ²	17 476 ft ²	1 624 m ²
nd FLOOR	SERVICES	1	60 ft ²	6 m ²	60 ft ²	6 m ²
nd FLOOR	VERTICAL CIRCULATION	1	892 ft ²	83 m ²	892 ft ²	83 m ²
		<u>.</u>	19 892 ft ²	1 848 m ²	19 892 ft ²	1 848 m²
d FLOOR	CIRCULATION	1	1 465 ft ²	136 m ²	1 465 ft ²	136 m ²
d FLOOR	RESIDENTIAL	1	17 476 ft ²	1 624 m ²	17 476 ft ²	1 624 m²
d FLOOR	SERVICES	1	60 ft ²	6 m²	60 ft ²	6 m²
d FLOOR	VERTICAL CIRCULATION	1	892 ft ²	83 m²	892 ft ²	83 m²
			19 892 ft ²	1 848 m²	19 892 ft ²	1 848 m²
h to 7th FLOOR	CIRCULATION	4	1 465 ft ²	136 m ²	5 860 ft²	544 m²
h to 7th FLOOR	RESIDENTIAL	4	17 476 ft ²	1 624 m ²	69 903 ft ²	6 494 m ²
h to 7th FLOOR	SERVICES	4	60 ft ²	6 m ²	240 ft ²	22 m ²
h to 7th FLOOR	VERTICAL CIRCULATION	4	892 ft ²	83 m ²	3 567 ft ²	331 m ²
			19 892 ft ²	1 848 m ²	79 569 ft ²	7 392 m²
h FLOOR	CIRCULATION	1	716 ft ²	67 m²	716 ft ²	67 m²
h FLOOR	RESIDENTIAL	1	8 107 ft ²	753 m ²	8 107 ft ²	753 m²
h FLOOR	SERVICES	1	204 ft ²	19 m²	204 ft ²	19 m²
h FLOOR	VERTICAL CIRCULATION	1	759 ft ²	70 m²	759 ft ²	70 m ²
			9 785 ft²	909 m²	9 785 ft²	909 m²
h to 20th FLOOR	CIRCULATION	12	619 ft ²	58 m²	7 428 ft ²	690 m²
h to 20th FLOOR	RESIDENTIAL	12	8 346 ft ²	775 m ²	100 149 ft ²	9 304 m ²
h to 20th FLOOR	SERVICES	12	62 ft ²	6 m ²	744 ft ²	69 m ²
h to 20th FLOOR	VERTICAL CIRCULATION	12	568 ft ²	53 m ²	6 816 ft ²	633 m ²
		12	9 595 ft ²	891 m ²	115 136 ft ²	10 697 m ²
Ist to 30th FLOOR	CIRCULATION	10	631 ft ²	59 m ²	6 309 ft ²	586 m ²
Ist to 30th FLOOR	RESIDENTIAL	10	6 741 ft ²	626 m ²	67 412 ft ²	6 263 m ²
Ist to 30th FLOOR	SERVICES	10	62 ft ²	6 m ²	620 ft ²	58 m ²
Ist to 30th FLOOR	VERTICAL CIRCULATION	10	568 ft ²	53 m ²	5 680 ft ²	528 m ²
			8 002 ft ²	743 m²	80 021 ft ²	7 434 m²
ECHANICAL PENTHOUSE	TECHNICAL	1	2 139 ft ²	199 m ²	2 139 ft ²	199 m²
		•	2 139 ft ²	199 m ²	2 139 ft ²	199 m ²
			99 035 ft ²	9 201 m ²	336 272 ft ²	31 241 m ²

AMENITIES REQUIREMENT_WEST TOWER				
	AMENITIES	MIN. 50%		
NBR OF UNITS	(6m² / UNIT)	COMMUNAL		
313	1 878 m²	939 m²		

PROVIDED AMENITIES_WEST TOWER				
TYPE OF AMENITIES	AREA TOTAL (m²)			
COMMUNAL AMENITIES	1 054 m²			
PERSONAL AMENITIES	1 232 m²			

PARKING REQUIREMENT_WEST TOWER		
NBR OF PARKING RATIO		
UNITS	(1 / UNIT)	
313	313	

BIKE RACKS REQUIREMENT_WEST TOWER			
NBR OF BIKE RACKS RATIO			
(0.5 / UNIT)			
157			

NOTES GÉNÉRALES General Notes

- 1 Ces documents d'architecture sont la propriété exclusive de NEUF architect(e)s et ne pourront être utilisés, reproduits ou copiés sans autorisation écrite préalable. / These architectural documents are the exclusive property of NEUF architect(e)s and cannot be used, copied or reproduced without written pre-authorisation
- 2 Les dimensions apparaissant aux documents devront être vérifiées par lentrepreneur avant le début des travaux. / All dimensions which appear on the documents must be verify by the contractor before to
- 3 Veuillez aviser l'architecte de toute dimension erreur et/ou
 divergences entre ces documents et ceux des autres professionnels. / The architect must be notified of all errors, omissions and discrepancies between these documents and those of the others professionnals
- professionnals.
 Les dimensions sur ces documents doivent être lues et non
 mesurées. / The dimensions on these documents must be read and not measured.


STRUCTURE Structural Goodeve Structural Inc. 18-77, Auriga Drive, Ottawa ON K2E 7Z7 T 613 226 4558 goodevestructural.ca

ARCHITECTURE DE PAYSAGE Landscape Architect James B. Lennox & Associates 3332, Carling Avenue, Ottawa ON K2H 5A8 T 613 722 5168 jbla.ca

CIVIL Civil Novatech Eng. Consultants Ltd. 240, Michael Cowpland Drive, Suite 200, Ottawa ON K2M 1P6 T 613 234 9643 novatech-eng.com

ARCHITECTES Architect **NEUF architect(e)S** SENCRL 630, boul. René-Lévesque O. 32e étages, Montréal QC H3B 1S6 T 514 847 1117 NEUFarchitectes.com

SCEAU / Seal



CLIENT Client



OUVRAGE Project **1200 MARITIME WAY** (KANATA RENTAL)

EMPLACEMENT Location OTTAWA

NO PROJET No. 12371.00

RÉVISION Revision

DATE (aa-mm-jj)

DESSINÉ PAR Drawn by Auteur DATE (aa.mm.jj) 02/15/23	vérifié par Checked Vérificateur échelle Scale
TITRE DU DESSIN Drawing Title STATISTICS - TOWER	WEST

NO. DESSIN Dwg Number A103





1200 MARITIME WAY HYDRAULIC ANALYSIS

Table 4								
			l.	able 1				
			Wate	r Demand				
	Unit Type				Tota	al Demand (L/s)		
Occuupancy	Retail Area (Seats)	1 Bed Apartment	2 Bed Apartment	Total Units	Total Population	Avg Day	Max. Daily	Peak Hour
			West Appa	rtment (Phase	e 1)			
Residential		185	128	313	528	1.71	4.28	9.41
Commercial						0.00	0.00	0.00
Total		185	128			1.71	4.28	9.41
			East Appa	rtment (Phase	e 2)			
Residential		186	116	302	504	1.63	4.08	8.98
Commercial	100					0.14	0.22	0.39
Total		186	116			1.78	4.30	9.37
	Total	Development			1032	3.49	8.58	18.79
Design Parame	eters:							
- 1 Bed Apartmen	t	1.4	persons/unit					
- 2 Bed Apartmen	t	2.1	persons/unit					
	ater Distribution G	<u>uidelines</u>						
- Average Domes	tic Flow			280	L/c/day	L/person/day	_	
- "Commerical Sp	ace A" Café			125	L/day/seat	(assume 1 seat	:/4m²)	
						Total:	399m2	
Residential Pea	king Factors City	of Ottawa Wa	ater Distrubuti	on Guidelines	<u>s:</u>			
Conditions	Peaking Factor		Units]				
Maximum Day	2.5	x avg day	L/c/day	1				
Peak Hour	2.2	x max day	L/c/day					
				-				

Commercial Peaking Factors City of Ottawa Water Distribution Guidelines

Conditions	Peaking Factor		Units
Maximum Day	1.5	x avg day	L/c/day
Peak Hour	1.8	x max day	L/c/day





SHT11X17.DWG - 279mmX432mm

FUS - Fire Flow Calculations

As per 2020 Fire Underwriter's Survey Guidelines

Novatech Project #: 120144 Project Name: 1200 Maritime Way - East Tower Date: 4/28/2023 Input By: Curtis Ferguson, E.I.T. Reviewed By: Anthony Mestwarp. P.Eng



Legend

Input by User

No Information or Input Required

Building Description: 28 Storey Building with 7 Storey Podium

Type I - Fire resistive construction (2 hrs)

Step			Choose		Value Used	Total Fire Flow (L/min)
		Base Fire Flo	w	•		· · ·
	Construction Ma	terial		Mult	iplier	
1	Coefficient related to type of construction C	Type V - Wood frame Type IV - Mass Timber Type III - Ordinary construction Type II - Non-combustible construction		1.5 Varies 1 0.8	0.6	
	-	Type I - Fire resistive construction (2 hrs)	Yes	0.6		
2	Floor Area A F Occupancy haza (1)	Podium Level Footprint (m ²) Total Floors/Storeys (Podium) Tower Footprint (m ²) Total Floors/Storeys (Tower) Protected Openings (1 hr) Area of structure considered (m ²) Base fire flow without reductions F = 220 C (A) ^{0.5} Reductions or Surce rd reduction or surcharge Non-combustible Limited combustible Combustible Free burning	2490 7 652 21 Yes harges	Reduction -25% -15% 0% 15%	3,735 /Surcharge -15%	8,000
	Sprinkler Reduct	Rapid burning tion (100% sprinkler coverage of building	used)	25% Redu	ction	
4	(2)	Adequately Designed System (NFPA 13) Standard Water Supply Fully Supervised System	Yes Yes Yes	-30% -10% -10% nulative Total	-30% -10% -10% - 50%	-3,400
	Exposure Surcha	arge (cumulative %, Maximum Exposure A	djustment Ch	arge Used)	Surcharge	
5	(3)	North Side East Side South Side West Side	20.1 - 30 m 3.1 - 10 m 10.1 - 20 m 20.1 - 30 m Cun	nulative Total	10% 20% 15% 10% 55%	3,740
	-	Results				
		Total Required Fire Flow, rounded to nea	rest 1000L/mi	n	L/min	7,000
6	(1) + (2) + (3)	(2,000 L/min < Fire Flow < 45,000 L/min)		or or	L/s USGPM	117 1,849
7	Storage Volume	Required Duration of Fire Flow (hours) Required Volume of Fire Flow (m ³)			Hours m ³	2 840

FUS - Fire Flow Calculations

As per 2020 Fire Underwriter's Survey Guidelines

Novatech Project #: 120144 Project Name: 1200 Maritime Way - West Tower Date: 4/28/2023 Input By: Curtis Ferguson, E.I.T. Reviewed By: Anthony Mestwarp. P.Eng



Legend

Input by User

No Information or Input Required

Building Description: 30 Storey Building with 7 Storey Podium

Type I - Fire resistive construction (2 hrs)

Step			Choose		Value Used	Total Fire Flow
		Base Fire Flo				(L/min)
			vv	M - 14	nlier	
	Construction Ma			Mult	plier	
	Coefficient	Type V - Wood frame		1.5		
1	related to type	Type IV - Mass Timber		Varies		
	of construction	Type III - Ordinary construction		1	0.6	
	С	Type II - Non-combustible construction		0.8		
		Type I - Fire resistive construction (2 hrs)	Yes	0.6		
	Floor Area		1000			
		Podium Level Footprint (m ²)	1969	-		
		Total Floors/Storeys (Podium)	7	-		
	Α	Tower Footprint (m ²)	892	-		
2		Total Floors/Storeys (Tower)	23	-		
		Protected Openings (1 hr)	Yes			
		Area of structure considered (m ²)			2,954	
	F	Base fire flow without reductions				7 000
	E C	$F = 220 C (A)^{0.5}$	-			7,000
	-	Reductions or Sur	charges			
	Occupancy haza	rd reduction or surcharge		Reduction	Surcharge	
		Non-combustible		-25%		
3	(1)	Limited combustible	Yes	-15%		
Ũ		Combustible		0%	-15%	5,950
		Free burning		15%		
		Rapid burning		25%		
	Sprinkler Reduct	tion (100% sprinkler coverage of building	j used)	Redu	ction	
		Adequately Designed System (NFPA 13)	Yes	-30%	-30%	
4		Standard Water Supply	Yes	-10%	-10%	
	(2)	Fully Supervised System	Yes	-10%	-10%	-2,975
			Cun	nulative Total	-50%	
	Exposure Surch	arge (cumulative %, Maximum Exposure /			Surcharge	
		North Side	20.1 - 30 m		10%	
-		East Side	10.1 - 20 m		15%	
5	(3)	South Side	30.1-45 m		5%	2,678
		West Side	10.1 - 20 m		15%	,
				nulative Total	45%	
	-	Results				
		Total Required Fire Flow, rounded to nea	arest 1000L/mi	n	L/min	6,000
6	(1) + (2) + (3)	(2,000 L/min < Fire Flow < 45,000 L/min)		or	L/s	
		(2,000 L/111111 < FILE FIOW < 45,000 L/MIN)		or	USGPM	1,585
		Required Duration of Fire Flow (hours)			Hours	2
7 Storage Volume						

: : 😫 🚼 🚳 🖹 🕅 🐣 🕸 🖂 geo©ttawa FR + Address, Street, or Place Q ● ● <u>↓</u> **● ♥ ♥** ○ ~ ⊖ 1 EXISTING CONNECTION OF THE 200mm WATERMAIN TO THE HYDRANT SERVICE + -> EAST TOWER: WEST TOWER: PROPOSED 200mm WATER SERVICE LOCATION. PROPOSED 200mm WATER SERVICE LOCATION. . TWIN-SERVICES SEPARATED BY A PROPOSED TWIN-SERVICES SEPARATED BY A PROPOSED ISOLATION VALVE. ISOLATION VALVE. AVG DAY: 1.87 AVG DAY: 1.70 MAX DAY: 4.54 MAX DAY: 4.26 PEAK HOUR: 9.89 PEAK HOUR: 9.38 FIRE FLOW: 117 FIRE FLOW: 100 APPROX, SITE ** BOUNDARY E---40m -8448908.500 5670923.885 Meters

From: Kuruvilla, Santhosh <Santhosh.Kuruvilla@ottawa.ca>
Sent: Wednesday, August 17, 2022 8:56 AM
To: Anthony Mestwarp <a.mestwarp@novatech-eng.com>
Cc: Greg MacDonald <g.Macdonald@novatech-eng.com>; Curtis Ferguson <c.ferguson@novatech-eng.com>
Subject: RE: 120144- Boundary Conditions Request - 1200 Maritime Way (D07-12-21-0017)

Hi Anthony,

Please find attached the updated boundary conditions for the subject application.

Thanks, Santhosh

From: Anthony Mestwarp <<u>a.mestwarp@novatech-eng.com</u>>
Sent: July 22, 2022 11:31 AM
To: Kuruvilla, Santhosh <<u>Santhosh.Kuruvilla@ottawa.ca</u>>
Cc: Greg MacDonald <<u>g.Macdonald@novatech-eng.com</u>>; Curtis Ferguson <<u>c.ferguson@novatech-eng.com</u>>
Subject: RE: 120144- Boundary Conditions Request - 1200 Maritime Way (D07-12-21-0017)

The client has decided to revise the water servicing for the 1200 Maritime Way site to have separate servicing for the east and west towers per the attached.

Can you please provide updated boundary conditions per the following.

West Tower:

Avg Day – 1.70 Max Day – 4.26 Peak Hour – 9.38 Fire Flow 100

East Tower:

Avg Day – 1.87 Max Day – 4.54 Peak Hour – 9.89 Fire Flow - 117

Thanks,

Anthony Mestwarp, P.Eng., Project Engineer | Land Development Engineering

NOVATECH Engineers, Planners & Landscape Architects

240 Michael Cowpland Drive, Suite 200, Ottawa, ON, K2M 1P6 | Tel: 613.254.9643 Ext. 216 | Fax: 613.254.5867 The information contained in this email message is confidential and is for exclusive use of the addressee.

From: Kuruvilla, Santhosh <<u>Santhosh.Kuruvilla@ottawa.ca</u>>
Sent: Wednesday, June 29, 2022 8:02 AM
To: Anthony Mestwarp <<u>a.mestwarp@novatech-eng.com</u>>
Cc: Greg MacDonald <<u>g.Macdonald@novatech-eng.com</u>>; Curtis Ferguson <<u>c.ferguson@novatech-eng.com</u>>
Subject: RE: 120144- Boundary Conditions Request - 1200 Maritime Way (D07-12-21-0017)

Hello Anthony,

Please find attached the water boundary conditions for the subject application for your use.

Thanks, Santhosh

From: Kuruvilla, Santhosh
Sent: June 07, 2022 11:25 AM
To: Anthony Mestwarp <<u>a.mestwarp@novatech-eng.com</u>>
Cc: Greg MacDonald <<u>g.Macdonald@novatech-eng.com</u>>; Curtis Ferguson <<u>c.ferguson@novatech-eng.com</u>>
Subject: RE: 120144- Boundary Conditions Request - 1200 Maritime Way

Thanks Anthony.

I will send you a meeting invite soon.

Santhosh

From: Anthony Mestwarp <<u>a.mestwarp@novatech-eng.com</u>>
Sent: June 07, 2022 10:00 AM
To: Kuruvilla, Santhosh <<u>Santhosh.Kuruvilla@ottawa.ca</u>>
Cc: Greg MacDonald <<u>g.Macdonald@novatech-eng.com</u>>; Curtis Ferguson <<u>c.ferguson@novatech-eng.com</u>>
Subject: RE: 120144- Boundary Conditions Request - 1200 Maritime Way

I am free after 2:00.

Regards,

Anthony Mestwarp, P.Eng., Project Engineer | Land Development Engineering

NOVATECH Engineers, Planners & Landscape Architects

240 Michael Cowpland Drive, Suite 200, Ottawa, ON, K2M 1P6 | Tel: 613.254.9643 Ext. 216 | Fax: 613.254.5867 The information contained in this email message is confidential and is for exclusive use of the addressee.

From: Kuruvilla, Santhosh <<u>Santhosh.Kuruvilla@ottawa.ca</u>>
Sent: Tuesday, June 7, 2022 8:14 AM
To: Anthony Mestwarp <<u>a.mestwarp@novatech-eng.com</u>>
Cc: Greg MacDonald <<u>g.Macdonald@novatech-eng.com</u>>; Curtis Ferguson <<u>c.ferguson@novatech-eng.com</u>>
Subject: RE: 120144- Boundary Conditions Request - 1200 Maritime Way

Hi Anthony,

Are you available this afternoon between 1:00-3:00 for about 10-15 mins? I would like to ask you a clarification question.

Please let me know and I will send you a Teams meeting invite.

Thanks, Santhosh

From: Anthony Mestwarp <a.mestwarp@novatech-eng.com
Sent: May 17, 2022 2:22 PM
To: Kuruvilla, Santhosh <<u>Santhosh.Kuruvilla@ottawa.ca</u>
Cc: Greg MacDonald <<u>g.Macdonald@novatech-eng.com</u>
; Curtis Ferguson <<u>c.ferguson@novatech-eng.com</u>
Subject: FW: 120144- Boundary Conditions Request - 1200 Maritime Way

As discussed please find the boundary condition request that was sent on April 28th for the 1200 Maritime Way project.

Please let me know if you require anything further.

Regards,

Anthony Mestwarp, P.Eng., Project Engineer | Land Development Engineering

NOVATECH Engineers, Planners & Landscape Architects

240 Michael Cowpland Drive, Suite 200, Ottawa, ON, K2M 1P6 | Tel: 613.254.9643 Ext. 216 | Fax: 613.254.5867 The information contained in this email message is confidential and is for exclusive use of the addressee.

From: Anthony Mestwarp
Sent: Thursday, April 28, 2022 3:44 PM
To: justin.armstrong@ottawa.ca
Cc: Santhosh.Kuruvilla@ottawa.ca; Greg MacDonald <g.Macdonald@novatech-eng.com
; Curtis Ferguson
<c.ferguson@novatech-eng.com
Subject: FW: 120144- Boundary Conditions Request - 1200 Maritime Way</pre>

Hi Justin,

I see that Santhosh is out of the office, I hope he is back soon. Can you please begin the process for the boundary condition request.

Thanks,

Anthony Mestwarp, P.Eng., Project Engineer | Land Development Engineering
NOVATECH Engineers, Planners & Landscape Architects
240 Michael Cowpland Drive, Suite 200, Ottawa, ON, K2M 1P6 | Tel: 613.254.9643 Ext. 216 | Fax: 613.254.5867
The information contained in this email message is confidential and is for exclusive use of the addressee.

From: Anthony Mestwarp
Sent: Thursday, April 28, 2022 2:29 PM
To: <u>Santhosh.Kuruvilla@ottawa.ca</u>
Cc: Curtis Ferguson <<u>c.ferguson@novatech-eng.com</u>>; Greg MacDonald <<u>g.Macdonald@novatech-eng.com</u>>; Subject: RE: 120144- Boundary Conditions Request - 1200 Maritime Way

Hi Santhosh,

Please find attached the supporting documents for the updated boundary conditions request for 1200 Maritime way.

The proposed site will have a total of 633 units (387 1-bed, & 246 2-bed), and 399m2 of commercial area.

Total demands and fire flows are summarized below;

- Average Daily Demand: 3.57 L/s
- Max Daily Demand: 8.79 L/s
- Peak Hour Demand: 19.25 L/s
- Fire Flow (FUS): 117 L/s

In response to the below the proposed development will have 2 water services connecting to the existing 200mm local watermain separated by an isolation valve. The local watermain was installed as part of the neighboring 1250 Maritime way site and covers the entire frontage of 1200 Maritime way, and is capable of providing redundancy for the site.

Please let us know if you have any questions.

Regards,

Anthony Mestwarp, P.Eng., Project Engineer | Land Development Engineering

NOVATECH Engineers, Planners & Landscape Architects

240 Michael Cowpland Drive, Suite 200, Ottawa, ON, K2M 1P6 | Tel: 613.254.9643 Ext. 216 | Fax: 613.254.5867 The information contained in this email message is confidential and is for exclusive use of the addressee.

From: Greg MacDonald <g.Macdonald@novatech-eng.com>
Sent: Wednesday, February 16, 2022 7:51 AM
To: Anthony Mestwarp <a.mestwarp@novatech-eng.com>
Subject: FW: 120144- Boundary Conditions Request - 1200 Maritime Way

See below

Greg MacDonald, P. Eng. Director, Land Development and Public Sector Infrastructure

NOVATECH Engineers, Planners & Landscape Architects

240 Michael Cowpland Drive, Suite 200, Ottawa, ON, K2M 1P6 | Tel: 613.254.9643 x279 | Cell: 613.890.9705 | Fax: 613.254.5867

The information contained in this email message is confidential and is for exclusive use of the addressee

From: Kuruvilla, Santhosh <<u>Santhosh.Kuruvilla@ottawa.ca</u>>
Sent: Wednesday, February 16, 2022 6:58 AM
To: Curtis Ferguson <<u>c.ferguson@novatech-eng.com</u>>
Cc: Greg MacDonald <<u>g.Macdonald@novatech-eng.com</u>>
Subject: RE: 120144- Boundary Conditions Request - 1200 Maritime Way

Hi Curtis,

I would like to provide you the following information I received from our Infrastructure Planning unit regarding water service connections for this development

"Hi Santosh,

I will wait to receive the updated request. So far, their request only shows a map with service connection from the 200mm watermain on Maritime. They need to establish how they are getting the redundancy. Are they extending the Maritime way watermain further east upto Great lakes Ave and proposing 2 connections separated by a valve? Or is the second connection from the 406mm watermain that I highlighted below?



In the next submission Novatech should provide clarity how the redundancy is met. The request should include a siteplan, proposed watermain extensions (if any), and connection locations."

Santhosh

This e-mail originates from the City of Ottawa e-mail system. Any distribution, use or copying of this email or the information it contains by other than the intended recipient(s) is unauthorized. Thank you.

Le présent courriel a été expédié par le système de courriels de la Ville d'Ottawa. Toute distribution, utilisation ou reproduction du courriel ou des renseignements qui s'y trouvent par une personne autre que son destinataire prévu est interdite. Je vous remercie de votre collaboration.'

Boundary Conditions 1200 Maritime Way

Provided Information

Connection 1 – West Tower	Demand		
Connection 1 – West Tower	L/min	L/s	
Average Daily Demand	102	1.70	
Maximum Daily Demand	256	4.26	
Peak Hour	563	9.38	
Fire Flow Demand #1	6,000	100.00	

Connection 2 – East Tower	Demand		
Connection 2 – East Tower	L/min	L/s	
Average Daily Demand	112	1.87	
Maximum Daily Demand	272	4.54	
Peak Hour	593	9.89	
Fire Flow Demand #1	7,000	116.67	

Location



<u>Results</u>

Connection 1 (West Tower) – Maritime Way.

Demand Scenario	Head (m)	Pressure ¹ (psi)
Maximum HGL	161.3	92.1
Peak Hour	156.1	84.8
Max Day plus Fire 1	148.6	74.1

Ground Elevation = 96.4 m

Connection 2 (East Tower) – Maritime Way.

Demand Scenario	Head (m)	Pressure ¹ (psi)
Maximum HGL	161.3	93.3
Peak Hour	156.1	86.0
Max Day plus Fire 1	142.8	67.1

Ground Elevation = 95.6 m

<u>Notes</u>

- 1. A second connection to the watermain, separated by an isolation valve, is required for each tower to decrease vulnerability of the water system in case of breaks.
- As per the Ontario Building Code in areas that may be occupied, the static pressure at any fixture shall not exceed 552 kPa (80 psi.) Pressure control measures to be considered are as follows, in order of preference:
 - a. If possible, systems to be designed to residual pressures of 345 to 552 kPa (50 to 80 psi) in all occupied areas outside of the public right-of-way without special pressure control equipment.
 - b. Pressure reducing valves to be installed immediately downstream of the isolation valve in the home/ building, located downstream of the meter so it is owner maintained.

Disclaimer

The boundary condition information is based on current operation of the city water distribution system. The computer model simulation is based on the best information available at the time. The operation of the water distribution system can change on a regular basis, resulting in a variation in boundary conditions. The physical properties of watermains deteriorate over time, as such must be assumed in the absence of actual field test data. The variation in physical watermain properties can therefore alter the results of the computer model simulation. Fire Flow analysis is a reflection of available flow in the watermain; there may be additional restrictions that occur between the watermain and the hydrant that the model cannot take into account.



CALCULATED WATER DEMNADS: West Tower Average Day (Maximum HGL)= 1.70 U/s Maximum Day = 4.26 U/s Peak Hour (Minimum HGL)= 9.38 U/s Max Day + Fire 104.26 U/s East Tower Average Day (Maximum HGL)= 1.87 U/s Maximum Day = 4.54 U/s Peak Hour (Minimum HGL)= 9.89 U/s Max Day + Fire 121.54 U/s Peak Hour (Minimum HGL)= 161.3 m Peak Hour (Minimum HGL)= 161.3 m Peak Hour (Minimum HGL)= 165.1 m Max Day + Fire = 148.6 m Connection # 2 East Tower Average Day (Maximum HGL)= Average Day (Maximum HGL)= 165.1 m Max Day + Fire = 142.8 m Watermain Analysis (West Tower). Max Day + Fire = Water Service Elevation = 94.58 m High Pressure Test = Max. HGL - Water Service Elevation x 1.42197 PSI/m < 80 PSI Low Pressure Test = Min. HGL - Water Service Elevation x 1.42197 PSI/m > 40 PSI Low Pressure Test = Min. HGL - Water Service Elevation x 1.42197 PSI/m > 40 PSI Low Pressure Test = Min. HGL - Water Service Elevation x 1.42197 PSI/m > 40 PSI Low Pressure = 87.5 PSI <th colspan="3"></th>			
Average Day (Maximum HGL)= 1.70 L/s Maximum Day = 4.26 L/s Peak Hour (Minimum HGL)= 9.38 L/s Max Day + Fire = 104.26 L/s East Tower Average Day (Maximum HGL)= 1.87 L/s Maximum Day = 4.54 L/s Peak Hour (Minimum HGL)= 9.89 L/s Max Day + Fire = 121.54 L/s Peak Hour (Minimum HGL)= 9.89 L/s Max Day + Fire = 121.54 L/s Connection # 1 West Tower Average Day (Maximum HGL)= Average Day (Maximum HGL)= 161.3 m Peak Hour (Minimum HGL)= 156.1 m Max Day + Fire = 142.8 m Vaterage Day (Maximum HGL)= 156.1 m Max Day + Fire = 142.8 m Vatermain Analysis (West Tower) Max Day + Fire = Water Service Elevation = 94.58 m High Pressure Test = Max. HGL - Water Service Elevation x 1.42197 PSI/m < 80 PSI High Pressure = 94.9 PSI Low Pressure Test = Min. HGL - Water Service Elevation x 1.42197 PSI/m > 40 PSI Low Pressure = 87.5 PSI Max Day + Fire Test = Max Day + Fire Flow - Water Service Elevation x 1.42197 PSI/m > 20 PSI		COLATED WATER DEMINADS:	
Average Day (Maximum HGL)= 1.70 L/s Maximum Day = 4.26 L/s Peak Hour (Minimum HGL)= 9.38 L/s Max Day + Fire = 104.26 L/s East Tower Average Day (Maximum HGL)= 1.87 L/s Maximum Day = 4.54 L/s Peak Hour (Minimum HGL)= 9.89 L/s Max Day + Fire = 121.54 L/s City of Ottawa Boundary Conditions: Bounday conditions based on connection to 203mm dia. Watermain in Maritime Way Connection # 1 West Tower Average Day (Maximum HGL)= 161.3 m Peak Hour (Minimum HGL)= 166.1 m Max Day + Fire = 142.8 m Connection # 2 East Tower Average Day (Maximum HGL)= Average Day (Maximum HGL)= 156.1 m Max Day + Fire = 142.8 m Watermain Analysis (West Tower) Max Day + Fire = Water Service Elevation = 94.58 m High Pressure Test = Max. HGL - Water Service Elevation x 1.42197 PSI/m < 80 PSI High Pressure = 94.9 PSI Low Pressure Test = Min. HGL - Water Service Elevation x 1.42197 PSI/m > 40 PSI Low Pressure = 87.5 PSI Max Day + Fire Test = Max Day + Fire Flow - Water Servi	West Tower		
Peak Hour (Minimum HGL) = 9.38 L/s Max Day + Fire = 104.26 L/s East Tower Average Day (Maximum HGL) = 1.87 L/s Maximum Day = 4.54 L/s Peak Hour (Minimum HGL) = 9.89 L/s Max Day + Fire = 121.54 L/s City of Ottawa Boundary Conditions: Bounday conditions based on connection to 203mm dia. Watermain in Maritime Way Connection # 1 West Tower Average Day (Maximum HGL) = 161.3 m Peak Hour (Minimum HGL) = 156.1 m Max Day + Fire = 148.6 m Connection # 2 East Tower Average Day (Maximum HGL) = 161.3 m Peak Hour (Minimum HGL) = 161.3 m Peak Hour (Minimum HGL) = 161.3 m Peak Hour (Minimum HGL) = 165.1 m Max Day + Fire = 142.8 m Watermain Analysis (West Tower) Water Service Elevation = 94.58 m High Pressure Test = Max. HGL - Water Service Elevation x 1.42197 PSI/m < 80 PSI High Pressure Test = Min. HGL - Water Service Elevation x 1.42197 PSI/m < 40 PSI Low Pressure Test = Min. HGL - Water Service Elevation x 1.42197 PSI/m > 40 PSI Low Pressure Test = Max. Day + Fire Fiow - Water Service Elevation x 1.42197 PSI/m > 20 PSI		1.70 L/s	
Max Day + Fire = 104.26 L/s East Tower Maximum Day = 4.54 L/s Maximum Day = 4.54 L/s Peak Hour (Minimum HGL) = 9.89 L/s Max Day + Fire = 121.54 L/s City of Ottawa Boundary Conditions: Bounday conditions based on connection to 203mm dia. Watermain in Maritime Way Connection # 1 West Tower Average Day (Maximum HGL) = 161.3 m Peak Hour (Minimum HGL) = 156.1 m Max Day + Fire = 148.6 m Connection # 2 East Tower Max Day + Fire = Average Day (Maximum HGL) = 166.1 m Max Day + Fire = 142.8 m Watermain Analysis (West Tower) Max Day + Fire = Water Service Elevation = 94.58 m High Pressure Test = Max. HGL - Water Service Elevation x 1.42197 PSI/m < 80 PSI High Pressure = 94.9 PSI Low Pressure Test = Min. HGL - Water Service Elevation x 1.42197 PSI/m > 40 PSI Low Pressure = 87.5 PSI Max Day + Fire Test = Max Day + Fire Flow - Water Service Elevation x 1.42197 PSI/m > 20 PSI		4.26 L/s	
East Tower Average Day (Maximum HGL)= 1.87 L/s Maximum Day = 4.54 L/s Peak Hour (Minimum HGL) = 9.89 L/s Max Day + Fire = 121.54 L/s City of Ottawa Boundary Conditions: Bounday conditions based on connection to 203mm dia. Watermain in Maritime Way Connection # 1 West Tower Average Day (Maximum HGL) = 161.3 m Peak Hour (Minimum HGL) = 166.1 m Max Day + Fire = 148.6 m Connection # 2 East Tower Average Day (Maximum HGL) = 161.3 m Peak Hour (Minimum HGL) = 161.3 m Peak Hour (Minimum HGL) = 166.1 m Max Day + Fire = 142.8 m Watermain Analysis (West Tower) Water Service Elevation = 94.58 m High Pressure Test = Max. HGL - Water Service Elevation x 1.42197 PSI/m < 80 PSI	Peak Hour (Minimum HGL) =	9.38 L/s	
Average Day (Maximum HGL)= 1.87 L/s Maximum Day = 4.54 L/s Peak Hour (Minimum HGL) = 9.89 L/s Max Day + Fire = 121.54 L/s City of Ottawa Boundary Conditions: Bounday conditions based on connection to 203mm dia. Watermain in Maritime Way Connection # 1 West Tower Average Day (Maximum HGL)= 161.3 m Peak Hour (Minimum HGL)= 156.1 m Max Day + Fire = 148.6 m Connection # 2 East Tower Image: Connection HGL)= Average Day (Maximum HGL)= 161.3 m Peak Hour (Minimum HGL)= 142.8 m Water Service Elevation = 94.58 m High Pressure Test = Max. HGL - Water Service Elevation x 1.42197 PSI/m < 80 PSI	Max Day + Fire =	104.26 L/s	
Maximum Day = 4.54 L/s Peak Hour (Minimum HGL) = 9.89 L/s Max Day + Fire = 121.54 L/s City of Ottawa Boundary Conditions: Bounday conditions based on connection to 203mm dia. Watermain in Maritime Way Connection # 1 West Tower Average Day (Maximum HGL) = 161.3 m Peak Hour (Minimum HGL) = 156.1 m Max Day + Fire = 148.6 m Connection # 2 East Tower Average Day (Maximum HGL) = 161.3 m Peak Hour (Minimum HGL) = 161.3 m Max Day + Fire = 142.8 m Watermain Analysis (West Tower) Max Day + Fire = Water Service Elevation = 94.58 m High Pressure Test = Max. HGL - Water Service Elevation x 1.42197 PSI/m < 80 PSI	East Tower		
Peak Hour (Minimum HGL) = 9.89 L/s Max Day + Fire = 121.54 L/s City of Ottawa Boundary Conditions: Bounday conditions based on connection to 203mm dia. Watermain in Maritime Way Connection # 1 West Tower Average Day (Maximum HGL) = 161.3 m Peak Hour (Minimum HGL) = 156.1 m Max Day + Fire = 148.6 m Connection # 2 East Tower Average Day (Maximum HGL) = 161.3 m Peak Hour (Minimum HGL) = 156.1 m Max Day + Fire = 142.8 m Watermain Analysis (West Tower) Water Service Elevation = 94.58 m High Pressure Test = Max. HGL - Water Service Elevation x 1.42197 PSI/m < 80 PSI High Pressure Test = Min. HGL - Water Service Elevation x 1.42197 PSI/m > 40 PSI Low Pressure Test = Min. HGL - Water Service Elevation x 1.42197 PSI/m > 40 PSI Low Pressure = 87.5 PSI Max Day + Fire Test = Max Day + Fire Flow - Water Service Elevation x 1.42197 PSI/m > 20 PSI	Average Day (Maximum HGL)=	1.87 L/s	
Max Day + Fire = 121.54 L/s City of Ottawa Boundary Conditions: Bounday conditions based on connection to 203mm dia. Watermain in Maritime Way Connection # 1 West Tower Average Day (Maximum HGL)= 161.3 m Peak Hour (Minimum HGL)= 156.1 m Max Day + Fire = 148.6 m Connection # 2 East Tower Max Day + Fire = Average Day (Maximum HGL)= 161.3 m Peak Hour (Minimum HGL)= 161.3 m Peak Hour (Minimum HGL)= 161.3 m Max Day + Fire = 142.8 m Watermain Analysis (West Tower) Max Day + Fire = Water Service Elevation = 94.58 m High Pressure Test = Max. HGL - Water Service Elevation x 1.42197 PSI/m < 80 PSI	-	4.54 L/s	
City of Ottawa Boundary Conditions: Bounday conditions based on connection to 203mm dia. Watermain in Maritime Way Connection # 1 West Tower Average Day (Maximum HGL)= 161.3 m Peak Hour (Minimum HGL) = 156.1 m Max Day + Fire = 148.6 m Connection # 2 East Tower Average Day (Maximum HGL)= 161.3 m Peak Hour (Minimum HGL)= 161.3 m Peak Hour (Minimum HGL)= 161.3 m Peak Hour (Minimum HGL)= 166.1 m Max Day + Fire = 142.8 m Watermain Analysis (West Tower) Water Service Elevation = Water Service Elevation = 94.58 m High Pressure Test = Max. HGL - Water Service Elevation x 1.42197 PSI/m < 80 PSI		9.89 L/s	
Bounday conditions based on connection to 203mm dia. Watermain in Maritime Way Connection # 1 West Tower Average Day (Maximum HGL)= 161.3 m Peak Hour (Minimum HGL)= 156.1 m Max Day + Fire = 148.6 m Connection # 2 East Tower Average Day (Maximum HGL)= 161.3 m Peak Hour (Minimum HGL)= 161.3 m Peak Hour (Minimum HGL)= 156.1 m Max Day + Fire = 142.8 m Watermain Analysis (West Tower) Water Service Elevation = 94.58 m High Pressure Test = Max. HGL - Water Service Elevation x 1.42197 PSI/m < 80 PSI	Max Day + Fire =	121.54 L/s	
Connection # 1 West Tower Average Day (Maximum HGL)= 161.3 m Peak Hour (Minimum HGL)= 156.1 m Max Day + Fire = 148.6 m Connection # 2 East Tower Average Day (Maximum HGL)= 161.3 m Peak Hour (Minimum HGL)= 161.3 m Peak Hour (Minimum HGL)= 166.1 m Max Day + Fire = 142.8 m Watermain Analysis (West Tower) Water Service Elevation = 94.58 m High Pressure Test = Max. HGL - Water Service Elevation x 1.42197 PSI/m < 80 PSI	City of Ottawa Boundary Conditions:	-	
Average Day (Maximum HGL)= 161.3 m Peak Hour (Minimum HGL)= 156.1 m Max Day + Fire = 148.6 m Connection # 2 East Tower Average Day (Maximum HGL)= Average Day (Maximum HGL)= 161.3 m Peak Hour (Minimum HGL)= 156.1 m Max Day + Fire = 142.8 m Watermain Analysis (West Tower) Water Service Elevation = 94.58 m High Pressure Test = Max. HGL - Water Service Elevation x 1.42197 PSI/m < 80 PSI	Bounday conditions based on connectio	on to 203mm dia. Watermain in Maritime Way	
Peak Hour (Minimum HGL) = 156.1 m Max Day + Fire = 148.6 m Connection # 2 East Tower Average Day (Maximum HGL) = 161.3 m Peak Hour (Minimum HGL) = 156.1 m Max Day + Fire = 142.8 m Water Max Day + Fire = 142.8 m Water Service Elevation = 94.58 m High Pressure Test = Max. HGL - Water Service Elevation x 1.42197 PSI/m < 80 PSI High Pressure Test = Max. HGL - Water Service Elevation x 1.42197 PSI/m < 80 PSI Low Pressure Test = Min. HGL - Water Service Elevation x 1.42197 PSI/m > 40 PSI Low Pressure Test = Max. Day + Fire Flow - Water Service Elevation x 1.42197 PSI/m > 20 PSI	Connection # 1 West Tower		
Max Day + Fire = 148.6 m Connection # 2 East Tower Average Day (Maximum HGL)= 161.3 m Peak Hour (Minimum HGL) = 156.1 m Max Day + Fire = 142.8 m Water Max Day + Fire = 142.8 m Water Service Elevation = 94.58 m High Pressure Test = Max. HGL - Water Service Elevation x 1.42197 PSI/m < 80 PSI High Pressure Test = Max. HGL - Water Service Elevation x 1.42197 PSI/m < 80 PSI Low Pressure Test = Min. HGL - Water Service Elevation x 1.42197 PSI/m > 40 PSI Low Pressure = 87.5 PSI Max Day + Fire Test = Max Day + Fire Flow - Water Service Elevation x 1.42197 PSI/m > 20 PSI	Average Day (Maximum HGL)=	161.3 m	
Connection # 2 East Tower Average Day (Maximum HGL)= 161.3 m Peak Hour (Minimum HGL) = 156.1 m Max Day + Fire = 142.8 m Watermain Analysis (West Tower) Water Service Elevation = 94.58 m High Pressure Test = Max. HGL - Water Service Elevation x 1.42197 PSI/m < 80 PSI	Peak Hour (Minimum HGL) =	156.1 m	
Average Day (Maximum HGL)= 161.3 m Peak Hour (Minimum HGL) = 156.1 m Max Day + Fire = 142.8 m Watermain Analysis (West Tower) Water Service Elevation = 94.58 m High Pressure Test = Max. HGL - Water Service Elevation x 1.42197 PSI/m < 80 PSI	Max Day + Fire =	148.6 m	
Average Day (Maximum HGL)= 161.3 m Peak Hour (Minimum HGL) = 156.1 m Max Day + Fire = 142.8 m Watermain Analysis (West Tower) Water Service Elevation = 94.58 m High Pressure Test = Max. HGL - Water Service Elevation x 1.42197 PSI/m < 80 PSI	Connection # 2 East Tower		
Peak Hour (Minimum HGL) = 156.1 m Max Day + Fire = 142.8 m Watermain Analysis (West Tower) Water Service Elevation = 94.58 m High Pressure Test = Max. HGL - Water Service Elevation x 1.42197 PSI/m < 80 PSI	Average Day (Maximum HGL)=	161.3 m	
Max Day + Fire = 142.8 m Watermain Analysis (West Tower) Water Service Elevation = 94.58 m High Pressure Test = Max. HGL - Water Service Elevation x 1.42197 PSI/m < 80 PSI		156.1 m	
Water Service Elevation = 94.58 m High Pressure Test = Max. HGL - Water Service Elevation x 1.42197 PSI/m < 80 PSI High Pressure = 94.9 PSI Low Pressure Test = Min. HGL - Water Service Elevation x 1.42197 PSI/m > 40 PSI Low Pressure = 87.5 PSI Max Day + Fire Test = Max Day + Fire Flow - Water Service Elevation x 1.42197 PSI/m > 20 PSI		142.8 m	
Water Service Elevation = 94.58 m High Pressure Test = Max. HGL - Water Service Elevation x 1.42197 PSI/m < 80 PSI	Matarmain Analysia (Maat Towar)		
High Pressure Test = Max. HGL - Water Service Elevation x 1.42197 PSI/m < 80 PSI High Pressure = 94.9 PSI Low Pressure Test = Min. HGL - Water Service Elevation x 1.42197 PSI/m > 40 PSI Low Pressure = 87.5 PSI Max Day + Fire Test = Max Day + Fire Flow - Water Service Elevation x 1.42197 PSI/m > 20 PSI	Watermain Analysis (West Tower)		
High Pressure =94.9PSILow Pressure Test = Min. HGL - Water Service Elevation x 1.42197 PSI/m > 40 PSILow Pressure =87.5PSIMax Day + Fire Test = Max Day + Fire Flow - Water Service Elevation x 1.42197 PSI/m > 20 PSI	Water Service Elevation =	94.58 m	
Low Pressure =87.5 PSIMax Day + Fire Test = Max Day + Fire Flow - Water Service Elevation x 1.42197 PSI/m > 20 PSI	-		

I



Watermain Analysis (East Tower)

Water Service Elevation =

94.25 m

High Pressure Test = Max. HGL - Water Service Elevation x 1.42197 PSI/m < 80 PSI</th>High Pressure =95.3 PSI

Low Pressure Test = Min. HGL - Water Service Elevation x 1.42197 PSI/m > 40 PSI Low Pressure = 87.9 PSI

Max Day + Fire Test = Max Day + Fire Flow - Water Service Elevation x 1.42197 PSI/m > 20 PSI Max Day + Fire (Connection #1) = 69.0 PSI

APPENDIX E

Servicing Study Guidelines Checklist



4.1 General Content	Addressed (Y/N/NA)	Comments		
Executive Summary (for larger reports only).	NA			
Date and revision number of the report.	Y			
Location map and plan showing municipal address, boundary, and layout of proposed development.	Y	Refer to figure 1		
Plan showing the site and location of all existing services.	Y	Refer to Grading and Servicing Plans		
Development statistics, land use, density, adherence to zoning and official plan, and reference to applicable subwatershed and watershed plans that provide context to which individual developments must adhere.	Y	Refer to Site Plan		
Summary of Pre-consultation Meetings with City and other approval agencies.	Y	Refer to Appendix F		
Reference and confirm conformance to higher level studies and reports (Master Servicing Studies, Environmental Assessments, Community Design Plans), or in the case where it is not in conformance, the proponent must provide justification and develop a defendable design criteria.	Y			
Statement of objectives and servicing criteria.	Y	Demont Castinger F. O. Casitano annon C. O. Starra Causar		
Identification of existing and proposed infrastructure available in the immediate area.	Y	Report Sections: 5.0 Sanitary sewer, 6.0 Storm Sewer and Stormwater Management, 7.0 Water Servicing		
Identification of Environmentally Significant Areas, watercourses and Municipal Drains potentially impacted by the proposed development (Reference can be made to the Natural Heritage Studies, if available).	NA			
Concept level master grading plan to confirm existing and proposed grades in the development. This is required to confirm the feasibility of proposed stormwater management and drainage, soil removal and fill constraints, and potential impacts to neighboring properties. This is also required to confirm that the proposed grading will not impede existing major system flow paths.	Y	Refer to Grading Plan and Stormwater Management Plan		



4.1 General Content	Addressed (Y/N/NA)	Comments
Identification of potential impacts of proposed piped services on private services (such as wells and septic fields on adjacent lands) and mitigation required to address potential impacts.	NA	
Proposed phasing of the development, if applicable.	Y	
Reference to geotechnical studies and recommendations concerning servicing.	Y	
All preliminary and formal site plan submissions should have the following information:		
Metric scale	Y	All Drawings
North arrow (including construction North)	Y	All Drawings
Key plan	Y	All Drawings
Name and contact information of applicant and property owner	Y	Drawings/Report
Property limits including bearings and dimensions	Y	Report
Existing and proposed structures and parking areas	Y	All Drawings
Easements, road widening and rights-of-way	Y	All Drawings
Adjacent street names	Y	All Drawings



4.2 Water	Addressed (Y/N/NA)	Comments
Confirm consistency with Master Servicing Study, if available.	NA	
Availability of public infrastructure to service proposed development.	Y	Report Sections: 5.0 Sanitary sewer, 6.0 Storm Sewer and Stormwater Management, 7.0 Water Servicing
Identification of system constraints.	NA	
Identify boundary conditions.	Y	
Confirmation of adequate domestic supply and pressure.	Y	
Confirmation of adequate fire flow protection and confirmation that fire flow is calculated as per the Fire Underwriter's Survey. Output should show available fire flow at locations throughout the development.	Y	
Provide a check of high pressures. If pressure is found to be high, an assessment is required to confirm the application of pressure reducing valves.	Y	
Definition of phasing constraints. Hydraulic modeling is required to confirm servicing for all defined phases of the project including the ultimate design.	NA	
Address reliability requirements such as appropriate location of shut-off valves.	Y	Refer to Grading and Servicing Plans
Check on the necessity of a pressure zone boundary modification.	NA	
Reference to water supply analysis to show that major infrastructure is capable of delivering sufficient water for the proposed land use. This includes data that shows that the expected demands under average day, peak hour and fire flow conditions provide water within the required pressure range.		
Description of the proposed water distribution network, including locations of proposed connections to the existing system, provisions for necessary looping, and appurtenances (valves, pressure reducing valves, valve chambers, and fire hydrants) including special metering provisions.	Y	Report Section 7.0 Water Servicing
Description of off-site required feedermains, booster pumping stations, and other water infrastructure that will be ultimately required to service proposed development, including financing, interim facilities, and timing of implementation.	NA	
Confirmation that water demands are calculated based on the City of Ottawa Design Guidelines. Provision of a model schematic showing the boundary	Y	Report Section 7.0 Water Servicing
conditions locations, streets, parcels, and building locations for reference.	NA	



4.3 Wastewater	Addressed (Y/N/NA)	Comments		
Summary of proposed design criteria (Note: Wet-weather flow criteria should not deviate from the City of Ottawa Sewer Design Guidelines. Monitored flow data from relatively new infrastructure cannot be used to justify capacity requirements for proposed infrastructure).	Y	Refer to report section 5.0 Sanitary sewer		
Confirm consistency with Master Servicing Study and/or justifications for deviations.	NA			
Consideration of local conditions that may contribute to extraneous flows that are higher than the recommended flows in the guidelines. This includes groundwater and soil conditions, and age and condition of sewers.	NA			
Description of existing sanitary sewer available for discharge of wastewater from proposed development.	Y	Refer to report section 5.0 Sanitary sewer		
Verify available capacity in downstream sanitary sewer and/or identification of upgrades necessary to service the proposed development. (Reference can be made to previously completed Master Servicing Study if applicable)	Y	Refer to Appendix B		
Calculations related to dry-weather and wet-weather flow rates from the development in standard MOE sanitary sewer design table (Appendix 'C') format.	NA			
Description of proposed sewer network including sewers, pumping stations, and forcemains.	Y	Refer to report section 5.0 Sanitary sewer		
Discussion of previously identified environmental constraints and impact on servicing (environmental constraints are related to limitations imposed on the development in order to preserve the physical condition of watercourses, vegetation, soil cover, as well as protecting against water quantity and quality).	NA			
Pumping stations: impacts of proposed development on existing pumping stations or requirements for new pumping station to service development.	NA			
Forcemain capacity in terms of operational redundancy, surge pressure and maximum flow velocity.	NA			
Identification and implementation of the emergency overflow from sanitary pumping stations in relation to the hydraulic grade line to protect against basement flooding.	NA			
Special considerations such as contamination, corrosive environment etc.	NA			



4.4 Stormwater	Addressed (Y/N/NA)	Comments		
Description of drainage outlets and downstream constraints including legality of outlet (i.e. municipal drain, right-of-way, watercourse, or private property).	Y	Refer to report section 6.0 Storm Sewer and Stormwater Management		
Analysis of the available capacity in existing public infrastructure.	NA	Stormwater release rates less than or equal to city allowabale release rate critera		
A drawing showing the subject lands, its surroundings, the receiving watercourse, existing drainage patterns and proposed drainage patterns.	Y	Refer to Stormwater Management Plan		
Water quantity control objective (e.g. controlling post- development peak flows to pre-development level for storm events ranging from the 2 or 5 year event (dependent on the receiving sewer design) to 100 year return period); if other objectives are being applied, a rationale must be included with reference to hydrologic analyses of the potentially affected subwatersheds, taking into account long-term cumulative effects.	Y	Refer to report section 6.0 Storm Sewer and Stormwater Management		
Water Quality control objective (basic, normal or enhanced level of protection based on the sensitivities of the receiving watercourse) and storage requirements.	Y	Refer to report section 6.0 Storm Sewer and Stormwater Management		
Description of stormwater management concept with facility locations and descriptions with references and supporting information.	Y	Refer to report section 6.0 Storm Sewer and Stormwater Management		
Set-back from private sewage disposal systems.	N/A			
Watercourse and hazard lands setbacks.	N/A			
Record of pre-consultation with the Ontario Ministry of Environment and the Conservation Authority that has jurisdiction on the affected watershed.	N/A			
Confirm consistency with sub-watershed and Master Servicing Study, if applicable study exists.	N/A			
Storage requirements (complete with calcs) and conveyance capacity for 5 yr and 100 yr events.	Y	Refer to Appendix C		
Identification of watercourse within the proposed development and how watercourses will be protected, or, if necessary, altered by the proposed development with applicable approvals.	NA			
Calculate pre and post development peak flow rates including a description of existing site conditions and proposed impervious areas and drainage catchments in comparison to existing conditions. Any proposed diversion of drainage catchment areas	Y	Refer to Appendix C		
from one outlet to another.	NA			
Proposed minor and major systems including locations and sizes of stormwater trunk sewers, and SWM facilities.	N/A			



		Keviseu. Octobel 20
If quantity control is not proposed, demonstration that		
downstream system has adequate capacity for the post-	NI (A	
development flows up to and including the 100-year	N/A	
return period storm event.		



		Revised: October
4.4 Stormwater	Addressed (Y/N/NA)	Comments
Identification of municipal drains and related approval requirements.	N/A	
Description of how the conveyance and storage capacity will be achieved for the development.	Y	Refer to report section 6.0 Storm Sewer and Stormwater Management
100 year flood levels and major flow routing to protect proposed development from flooding for establishing minimum building elevations (MBE) and overall grading.	N/A	
Inclusion of hydraulic analysis including HGL elevations.	N/A	
Description of approach to erosion and sediment control during construction for the protection of receiving watercourse or drainage corridors.	Y	Report Section 8.0 Erosion and Sediment Control
Identification of floodplains – proponent to obtain relevant floodplain information from the appropriate Conservation Authority. The proponent may be required to delineate floodplain elevations to the satisfaction of the Conservation Authority if such information is not available or if information does not match current conditions.	NA	
Identification of fill constrains related to floodplain and geotechnical investigation.	Y	Report section 4.0 Site Constraints



4.5 Approval and Permit Requirements	Addressed (Y/N/NA)	Comments
Conservation Authority as the designated approval agency for modification of floodplain, potential impact on fish habitat, proposed works in or adjacent to a watercourse, cut/fill permits and Approval under Lakes and Rivers Improvement Act. The Conservation Authority is not the approval authority for the Lakes and Rivers Improvement Act. Where there are Conservation Authority regulations in place, approval under the Lakes and Rivers Improvement Act is not required, except in cases of dams as defined in the Act.		
Application for Certificate of Approval (CofA) under the Ontario Water Resources Act.	NA	
Changes to Municipal Drains.	NA	
Other permits (National Capital Commission, Parks		
Canada, Public Works and Government Services Canada,	NA	
Ministry of Transportation etc.)		

4.6 Conclusion	Addressed (Y/N/NA)	Comments
Clearly stated conclusions and recommendations.	Y	Report Section 9.0 Conclusions
Comments received from review agencies including the City of Ottawa and information on how the comments were addressed. Final sign-off from the responsible reviewing agency.	NA	
All draft and final reports shall be signed and stamped by a professional Engineer registered in Ontario.	Y	

APPENDIX F

PRE-CONSULTATION MEETING MINUTES Please refer to the below regarding the Pre-Application meeting held on August 6, 2020 for the property at 1200 Maritime Way for a Site Plan Control Application and Zoning By-law Amendment for a residential development. I have also attached the required Plans & Study List for application submission. Despite the amount of hard copies identified in the list, they may not be required- please confirm with the Planner prior to submission.

Below are staff's preliminary comments based on the information available at the time of the pre-consultation meeting:

Planning / Urban Design

General:

- You are encouraged to contact the Ward Councillor, Councillor <u>Jenna Sudds</u>, regarding the proposal.
- Urban Design Review Panel review is required for the proposed increase in height and site plan control application.
 - A pre-consult with the UDRP is also recommended.
- Cash-in-Lieu of Parkland will be required if proof of payment cannot be provided.

Zoning By-law Amendment:

- Staff do not have a concern with the proposed increase in height provided it meets Official Plan and Secondary Planning requirements and policies.
- Please ensure that adequate tower separation and associated setbacks on-site and from abutting property lines is achieved in accordance with the high-rise design guidelines.
- A zoning schedule and or FSI should be considered as part of the Zoning By-law amendment to increase the height on the subject property.

Site Plan Control:

- Current proposal does not adequately address Maritime Way.
- Please ensure that adequate setbacks (11.5 metres for a tower) are provided from the eastern property line, and the length of a podium is not designed to directly face this property line.
- Please utilize a 6-storey podium in lieu of a 9 storey podium.
- Please consider that if the towers are the same height, they have the same floor plate (pairing) vs. the current proposal.
- If different floor plates are desired for the two towers, they should be different heights.
- Three towers are possible on-site, one at the desired 30 storeys and two at a lower height (ex. 15).
- Need to study massing as it relates to other properties, buildings, shadowing, wind etc.

- Proposal needs to work with grades along Kanata Avenue.
- Connections to the MUP to the south need to be considered.
- Ensure that adequate outdoor amenity space is provided.
- Group "back" of house and functional requirements.
- Reduce surface parking to the greatest extent possible.
- Provide grade related units.
- Please see attached illustration.
- A Design Brief is required.
 - A terms of reference is provided. All applicable elements of the Design Brief have been highlighted.
- Please review the Building Code to make sure the proposed development will meet the accessibility requirements.

Engineering

General:

- It is the sole responsibility of the consultant to investigate the location of existing underground utilities in the proposed servicing area and submit a request for locates. The location of existing utilities and services shall be documented on an Existing Conditions Plan.
- All underground and above ground building footprints and permanent walls need to be shown on the plans to confirm that any permanent structure does not encroach within the right-of-way.
- Any easements on the subject site shall be identified and respected by any development proposal and shall adhere to the conditions identified in the easement agreement. A **legal survey plan** shall be provided and all easements shall be shown on the engineering plans.
- Please provide an Existing Conditions/Removals Plan as part of the engineering drawing set. Any existing services are to be removed or abandoned in accordance with City standards.
- Please note that the proposed servicing design and site works shall be in accordance with the following documents:
 - Ottawa Sewer Design Guidelines (October 2012)
 - o Technical Bulletin PIEDTB-2016-01
 - Technical Bulletins ISTB-2018-01, ISTB-2018-02 and ISTB-2018-03.
 - Ottawa Design Guidelines Water Distribution (2010)
 - Geotechnical Investigation and Reporting Guidelines for Development Applications in the City of Ottawa (2007)
 - City of Ottawa Slope Stability Guidelines for Development Applications (revised 2012)
 - City of Ottawa Environmental Noise Control Guidelines (January 2016)
 - City of Ottawa Accessibility Design Standards (2012) (City recommends development be in accordance with these standards on private property)
 - Ottawa Standard Tender Documents (latest version)
 - Ontario Provincial Standards for Roads & Public Works (2013)

 Record drawings and utility plans are also available for purchase from the City (Contact the City's Information Centre by email at <u>InformationCentre@ottawa.ca</u> or by phone at (613) 580-424 x.44455).

Stormwater Management Criteria and Information:

- It appears the subject site is located within the KTC SWM Pond (Phase
 2) catchment (see attached). The consultant should review the attached report and confirm SWM criteria, flow allowance to the existing storm system, design assumptions, etc. Consult Operations staff to determine how the existing facility is currently performing (i.e. ability to achieve targets, condition of infrastructure within the SWM block, etc.
- Water Quality Control: Please consult with the local conservation authority regarding water quality criteria prior to submission of a Site Plan Control Proposal application to establish any water quality control restrictions, criteria and measures for the site. Correspondence and clearance shall be provided in the Appendix of the report.
- Please note that foundation drain is to be independently connected to sewermain unless being pumped with appropriate back up power, sufficient sized pump and back flow prevention.
- Please note that as per *Technical Bulletin PIEDTB-2016-01 section 8.3.11.1 (p.12 of 14)* **there shall be no surface ponding on private parking areas during the 2-year storm rainfall event**. Depending on the SWM strategy proposed underground or additional underground storage may be required to satisfy this requirement.
- Underground Storage: Please note that the Modified Rational Method for storage computation in the Sewer Design Guidelines was originally intended to be used for above ground storage (i.e. parking lot) where the change in head over the orifice varied from 1.5 m to 1.2 m (assuming a 1.2 m deep CB and a max ponding depth of 0.3 m). This change in head was small and hence the release rate fluctuated little, therefore there was no need to use an average release rate.
- When underground storage is used, the release rate fluctuates from a maximum peak flow based on maximum head down to a release rate of zero. This difference is large and has a significant impact on storage requirements. We therefore require that an average release rate equal to 50% of the peak allowable rate shall be applied to estimate the required volume. Alternatively, the consultant may choose to use a submersible pump in the design to ensure a constant release rate.
- In the event that there is a disagreement from the designer regarding the required storage, The City will require that the designer demonstrate their rationale utilizing dynamic modelling, that will then be reviewed by City modellers in the Water Resources Group.

- Note that the above will added to upcoming revised Sewer Design Guidelines to account for underground storage, which is now widely used.
- Provide sufficient details and information on any proposed underground storage system. A cross-section of any underground storage system is to be provided with sufficient details and information. In case of a pump failure or blockage an overflow should be provided. Backup power supply is required if using a pump.
- Please note that the minimum orifice dia. for a plug style ICD is 83mm and the minimum flow rate from a vortex ICD is 6 L/s in order to reduce the likelihood of plugging.
- Post-development site grading shall match existing property line grades in order to minimize disruption to the adjacent residential properties. A topographical plan of survey shall be provided as part of the submission and a note provided on the plans.
- Please provide a **Pre-Development Drainage Area Plan** to define the predevelopment drainage areas/patterns. **Existing drainage patterns shall be maintained and discussed as part of the proposed SWM solution**.
- If rooftop control and storage is proposed as part of the SWM solutions sufficient details (Cl. 8.3.8.4) shall be discussed and document in the report and on the plans. Roof drains are to be connected downstream of any incorporated ICDs within the SWM system and not to the foundation drain system.

Storm Sewer:

- Storm sewer monitoring maintenance holes are required to be installed at the property line (on the private side of the property) as per City of Ottawa Sewer-Use By-Law 2003-514 (14) *Monitoring Devices*.
- As-built drawings of the existing services within the vicinity of the site shall be obtained and reviewed in order to determine proper servicing and SWM plan for the subject site(s).
- Storm service connections are to have backwater valves.

Sanitary Sewer:

- An analysis and demonstration that there is sufficient/adequate residual capacity to accommodate any increase in wastewater flows in the receiving and downstream wastewater system is required to be provided. The City can provide flows for existing areas and direction on how to estimate future flows for vacant areas within the sewer shed.
- Please apply the wastewater design flow parameters *in Technical Bulletin PIEDTB-2018-01.*

- Sanitary sewer monitoring maintenance holes are required to be installed at the property line (on the private side of the property) as per City of Ottawa Sewer-Use By-Law 2003-514 (14) *Monitoring Devices*.
- Sanitary service connections are to have backwater valves.

Water:

- Water Supply Redundancy: Residential buildings with a basic day demand greater than 50m³/day (0.57 L/s) are required to be connected to a minimum of two water services separated by an isolation valve to avoid a vulnerable service area as per the *Ottawa Design Guidelines Water Distribution, WDG001, July 2010 Clause 4.3.1 Configuration.* The basic day demand for each site anticipated to exceed 50m³/day therefore 2 water services will be required. There shall be primary water service and a secondary connection.
- Please review Technical Bulletin ISTB-2018-0, maximum fire flow hydrant capacity is provided in Section 3 Table 1 of Appendix I. A hydrant coverage figure shall be provided and demonstrate there is adequate fire protection.
- Boundary conditions are required to confirm that the require fire flows can be achieved as well as availability of the domestic water pressure on the City street in front of the development. Use Table 3-3 of the MOE Design Guidelines for Drinking-Water System to determine Maximum Day and Maximum Hour peaking factors for 0 to 500 persons and use Table 4.2 of the Ottawa Design Guidelines, Water Distribution for 501 to 3,000 persons. Please provide the following information to the City of Ottawa via email to request water distribution network boundary conditions for the subject site. Please note that once this information has been provided to the City of Ottawa it takes approximately 5-10 business days to receive boundary conditions.
 - o Type of Development and Units

o Site Address

• A plan showing the proposed water service connection locations.

• Average Daily Demand (L/s)

- Maximum Daily Demand (L/s)
- $_{\odot}\textbf{Peak}$ Hour Demand (L/s)
- $_{\circ} \textbf{Fire Flow} (L/min)$
- [Fire flow demand requirements shall be based on Fire Underwriters Survey (FUS) Water Supply for Public Fire Protection

o **1999]**

- Exposure separation distances shall be defined on a figure to support the FUS calculation and required fore flow (RFF).
- Hydrant capacity shall be assessed to demonstrate the RFF can be achieved. Please identify which hydrants are being considered to meet the RFF on a fire hydrant coverage plan as part of the boundary conditions request.
- The subject site is located within the 1E Pressure Zone.

Snow Storage:

 Any portion of the subject property which is intended to be used for permanent or temporary snow storage shall be as shown on the approved site plan and grading plan. Snow storage shall not interfere with approved grading and drainage patters or servicing. Snow storage areas shall be setback from the property lines, foundations, fencing or landscaping a minimum of 1.5m. Snow storage areas shall not occupy driveways, aisles, required parking spaces or any portion of a road allowance. If snow is to be removed from the site please indicate this on the plan(s).

Permits and Approvals:

• The consultant shall determine if this project will be subject to an Environmental Compliance Approval (ECA) for Private Sewage Works. It shall be determined if the exemptions set out under Ontario Regulation 525/98: *Approval Exemptions* are satisfied. All regulatory approvals shall be documented and discussed in the report.

Geotechnical Investigation:

- A Geotechnical Study/Investigation shall be prepared in support of this development proposal.
- Reducing the groundwater level in this area can lead to potential damages to surrounding structures due to excessive differential settlements of the ground. The impact of groundwater lowering on adjacent properties needs to be discussed and investigated to ensure there will be no short term and long term damages associated with lowering the groundwater in this area.
- Geotechnical Study shall be consistent with the **Geotechnical Investigation and Reporting Guidelines for Development Applications**.
- https://documents.ottawa.ca/sites/default/files/documents/cap137602.pdf

Exterior Site Lighting:

• Any proposed light fixtures (both pole-mounted and wall mounted) must be part of the approved Site Plan. All external light fixtures must meet the criteria for Full Cut-off Classification as recognized by the Illuminating Engineering Society of North America (IESNA or IES), and must result in minimal light spillage onto adjacent properties (as a guideline, 0.5 fc is normally the maximum allowable spillage). In order to satisfy these criteria, the please provide the City with a **Site Lighting Plan, Photometric Plan and Certification (Statement) Letter** from an acceptable professional engineer stating that the design is compliant.

Please contact Infrastructure Project Manager <u>Ahmed Elsayed</u> for follow-up questions.

Transportation

- Follow Traffic Impact Assessment Guidelines
 - ∘ A TIA is required. Please proceed to submit Scoping report.
 - Start this process asap. The application will not be deemed complete until the submission of the draft step 1-4, including the functional draft RMA package (if applicable) and/or monitoring report (if applicable).
 - Request base mapping asap if RMA is required. Contact Engineering Services (<u>https://ottawa.ca/en/city-hall/planning-and-</u> development/engineering-services)
- TMP shows:
 - Future BRT along Hwy 417 (affordable network) and future LRT along Hwy 417 (ultimate network); and
 - Plans to widen Kanata Avenue from two to four lanes, between Highway 417 and Campeau Drive (Phase 2: 2020-2025).
- Drive aisle width should be 6.7m wide.
- Reduce number of conflict points as much as possible within internal roadways.
- Noise Impact Studies required for the following:
 - o Road
 - Stationary (if there will be any exposed mechanical equipment due to the proximity to neighbouring noise sensitive land uses)
 - On site plan:
 - Show all details of the roads abutting the site up to and including the opposite curb; include such items as pavement markings, accesses and/or sidewalks.
 - Show clear throat length dimension on site plan.
 - Turning movement diagrams required for all accesses showing the largest vehicle to access/egress the site.
 - Turning movement diagrams required for internal movements (loading areas, garbage).
 - Show all curb radii measurements; ensure that all curb radii are reduced as much as possible
 - Show lane/aisle widths.
 - Sidewalk is to be continuous across access as per City Specification 7.1.
 - Grey out any area that will not be impacted by this application.
- AODA legislation is in effect for all organizations, please ensure that the design conforms to these standards.

Please contact Transportation Project Manager, Josiane Gervais for follow-up questions.

<u>Other</u>

Please refer to the links to "<u>Guide to preparing studies and plans</u>" and <u>fees</u> for general information. Additional information is available related to <u>building</u> <u>permits</u>, <u>development charges</u>, and the <u>Accessibility Design Standards</u>. Be aware that other fees and permits may be required, outside of the development review process. You may obtain background drawings by contacting informationcentre@ottawa.ca.

These pre-consultation comments are valid for one year. If you submit a development application(s) after this time, you may be required to meet for another pre-consultation meeting and/or the submission requirements may change. You are as well encouraged to contact us for a follow-up meeting if the plan/concept will be further refined.

Please do not hesitate to contact me if you have any questions.

Regards, Laurel

Laurel McCreight MCIP, RPP Planner Development Review West Urbaniste Examen des demandes d'aménagement ouest

City of Ottawa | Ville d'Ottawa 613.580.2424 ext./poste 16587 ottawa.ca/planning / ottawa.ca/urbanisme DRAWINGS

GENERAL NOTES: 1. COORDINATE AND SCHEDULE ALL WORK WITH OTHER TRADES AND CONTRACTORS.	1. ALL EROSION AND SEDIMENT CONTROL OTTAWA AND THE CONSERVATION AUT UNDERTAKING ANY SITE ALTERATIONS (
2. DETERMINE THE EXACT LOCATION, SIZE, MATERIAL AND ELEVATION OF ALL EXISTING UTILITIES PRIOR TO COMMENCING CONSTRUCTION. PROTECT AND ASSUME RESPONSIBILITY FOR ALL EXISTING UTILITIES WHETHER OR NOT SHOWN ON THI DRAWING.	OF SITE PREPARATION AND CONSTRUCT
 OBTAIN ALL NECESSARY PERMITS AND APPROVALS FROM THE CITY OF OTTAWA BEFORE COMMENCING CONSTRUCTION. BEFORE COMMENCING CONSTRUCTION OBTAIN AND PROVIDE PROOF OF COMPREHENSIVE, ALL RISK AND OPERATIONAL 	SOCKS WILL BE PLACED UNDER GRATES
LIABILITY INSURANCE FOR \$5,000,000.00. INSURANCE POLICY TO NAME OWNERS, ENGINEERS AND ARCHITECTS AS CO-INSURED. 5. RESTORE ALL DISTURBED AREAS ON-SITE AND OFF-SITE, INCLUDING TRENCHES AND SURFACES ON PUBLIC ROAD	INSTALLED WITHIN THE OUTLET DITCHE HAS BEEN ESTABLISHED AND CONSTRUC 3. THE SEDIMENT CONTROL MEASURES S
ALLOWANCES TO EXISTING CONDITIONS OR BETTER TO THE SATISFACTION OF THE CITY OF OTTAWA AND ENGINEER. 6. REMOVE FROM SITE ALL EXCESS EXCAVATED MATERIAL, ORGANIC MATERIAL AND DEBRIS UNLESS OTHERWISE	MEASURES ARE NO LONGER REQUIRED. AUTHORIZATION FROM THE ENGINEER.
INSTRUCTED BY ENGINEER. EXCAVATE AND REMOVE FROM SITE ANY CONTAMINATED MATERIAL. ALL CONTAMINATED MATERIAL SHALL BE DISPOSED OF AT A LICENSED LANDFILL FACILITY.7. ALL ELEVATIONS ARE GEODETIC.	4. THE CONTRACTOR SHALL IMMEDIATEL' MATERIAL INTO ANY DITCH OR STORI REPAIRS TO EXISTING CONTROL MEASU BE CARRIED OUT BY THE CONTRACTOR
8. REFER TO GEOTECHNICAL REPORT (No. PG5281-1, DATED JUL 16TH, 2020), PREPARED BY PATERSON. FOR SUBSURFACE CONDITIONS, CONSTRUCTION RECOMMENDATIONS, AND GEOTECHNICAL INSPECTION REQUIREMENTS. THE	5. THE CONTRACTOR ACKNOWLEDGES TH MAY BE SUBJECT TO PENALTIES IMPOSE
GEOTECHNICAL CONSULTANT IS TO REVIEW ON-SITE CONDITIONS AFTER EXCAVATION PRIOR TO PLACEMENT OF THE GRANULAR MATERIAL. 9. REFER TO ARCHITECT'S AND LANDSCAPE ARCHITECT'S DRAWINGS FOR BUILDING AND HARDSURFACE AREAS AND	6. THE CONTRACTOR SHALL PROVIDE DUS AS REQUIRED.
DIMENSIONS. 10. REFER TO STORMWATER MANAGEMENT REPORT PREPARED BY NOVATECH ENGINEERING CONSULTANTS LTD (20230428).	
11. SAW CUT AND KEY GRIND ASPHALT AT ALL ROAD CUTS AND ASPHALT TIE IN POINTS AS PER CITY OF OTTAWA STANDARD (R10).	S
 PROVIDE LINE/PARKING PAINTING. CONTRACTOR TO PROVIDE THE CONSULTANT WITH A GENERAL PLAN OF SERVICES INDICATING ALL SERVICING AS-BUILT INFORMATION SHOWN ON THIS PLAN, AS-BUILT INFORMATION MUST INCLUDE: PIPE MATERIAL, SIZES, LENGTHS, SLOPES. 	
INVERT AND T/G ELEVATIONS, STRUCTURE LOCATIONS, VALVE AND HYDRANT LOCATIONS, T/WM ELEVATIONS AND ANY ALIGNMENT CHANGES, ETC.	
SEWER NOTES: 1. SPECIFICATIONS:	
ITEM SPEC. No. REFERENCE CATCHBASIN (600x600mm) 705.010 OPSD STORM / SANITARY MANHOLE (1200Ø) 701.010 OPSD CB, FRAME & COVER 400.020 OPSD	
STORM / SANITARY MH FRAME & COVER 401.010 OPSD SEWER TRENCH - BEDDING (GRANULAR A) S6, S7, W17 CITY OF OTTAWA / OPSD COVER (GRANULAR A OR GRANULAR B TYPE I,	
WITH MAXIMUM PARTICLE SIZE=25mm) STORM SEWER PVC DR 35 SANITARY SEWER PVC DR 35 CATCHBASIN LEAD PVC DR 35	50mmØ TO 1 CRUSHED
SEWER SERVICE CONNECTION - RIGID PIPES11CITY OF OTTAWASEWER SERVICE ABANDONMENTS11,4CITY OF OTTAWA	
2. INSULATE ALL PIPES (SAN/STM) THAT HAVE LESS THAN 1.5m COVER WITH 50mmX1200mm HI-40 INSULATION. PROVIDE 150n CLEARANCE BETWEEN PIPE AND INSULATION.	nm
 SERVICES ARE TO BE CONSTRUCTED TO 1.0m FROM FACE OF BUILDING AT A MINIMUM SLOPE OF 1.0%. PIPE BEDDING, COVER AND BACKFILL ARE TO BE COMPACTED TO AT LEAST 98% OF THE STANDARD PROCTOR MAXIMUM DRY DENSITY. THE USE OF CLEAR CRUSHED STONE AS A BEDDING LAYER SHALL NOT BE PERMITTED. 	
 FLEXIBLE CONNECTIONS ARE REQUIRED FOR CONNECTING PIPES TO MANHOLES (FOR EXAMPLE KOR-N-SEAL, PSX: POSITIVE SEAL AND DURASEAL). THE CONCRETE CRADLE FOR THE PIPE CAN BE ELIMINATED. 	
6. THE OWNER SHALL REQUIRE THAT THE SITE SERVICING CONTRACTOR PERFORM FIELD TESTS FOR QUALITY CONTROL OF ALL SANITARY SEWERS. LEAKAGE TESTING SHALL BE COMPLETED IN ACCORDANCE WITH OPSS 410.07.16, 410.07.16.04 AM 407.07.24. DYE TESTING IS TO BE COMPLETED ON ALL SANITARY SERVICES TO CONFIRM PROPER CONNECTION TO THE	
SANITARY SEWER MAIN. THE FIELD TESTS SHALL BE PERFORMED IN THE PRESENCE OF A CERTIFIED PROFESSIONAL ENGINEER WHO SHALL SUBMIT A CERTIFIED COPY OF THE TEST RESULTS.	
 STORM MANHOLES AND CBMHS ARE TO HAVE 300mm SUMPS UNLESS OTHERWISE INDICATED. CONTRACTOR TO TELEVISE (CCTV) ALL PROPOSED SEWERS, 200mmØ OR GREATER PRIOR TO BASE COURSE ASPHALT. UPON COMPLETION OF CONTRACT, THE CONTRACTOR IS RESPONSIBLE TO FLUSH AND CLEAN ALL SEWERS & 	
 APPURTENANCES. 9. FULL PORT BACKWATER VALUES ARE REQUIRED ON THE SANITARY SERVICES. INSTALLED AS PER THE MANUFACTURES RECOMMENDATIONS AND A BACKWATER VALVE IS REQUIRED ON THE STORM SERVICES / FOUNDATION DRAINS FOR EACH 	4
BUILDING; INSTALLED AS PER STD. DWGS14 10. REINSTATE ALL EXISTING PAVEMENT, CURB AND BOULEVARDS AS PER CITY OF OTTAWA R10.	
11. ALL EXISTING SANITARY AND STORM SERVICES ARE TO BE CAPPED AT THE PROPERTY LINE TO THE SATISFACTION OF TH CITY OF OTTAWA'S SEWER OPERATION.	E
12. MONITORING TEST PORTS FOR BUILDING SERVICES TO BE INSTALLED IN PARKING GARAGE.	
1. SPECIFICATIONS:	
ITEMSPEC. NO.REFERENCEWATERMAIN TRENCHINGW17CITY OF OTTAWATHERMAL INSULATION IN SHALLOW TRENCHESW22CITY OF OTTAWA	
VALVE BOX ASSEMBLYW24CITY OF OTTAWACONNECTION DETAIL FROM EXISTING TO NEW WMW25.1CITY OF OTTAWAWATERMAIN CROSSING BELOW SEWERW25CITY OF OTTAWAWATERMAIN CROSSING OVER SEWERW25.2CITY OF OTTAWA	
WATERMAIN CROSSING OVER SEWERW25.2CITY OF OTTAWATHERMAL INSULATED AT OPEN STRUCTUREW23CITY OF OTTAWAWATER SERVICE INSULATION AT SEWER CROSSINGW38CITY OF OTTAWA	
2. SUPPLY AND CONSTRUCT ALL WATERMAINS AND APPURTENANCES IN ACCORDANCE WITH THE CITY OF OTTAWA STANDARDS AND SPECIFICATIONS. EXCAVATION, INSTALLATION, BACKFILL AND RESTORATION OF ALL WATERMAINS BY THE CONTRACTOR. CONNECTIONS AND SHUT-OFFS AT THE MAIN AND CHLORINATION OF THE WATER SYSTEM SHALL BE PERFORMED BY CITY OFFICIALS.	
 WATERMAIN SHALL BE MINIMUM 2.4m DEPTH BELOW GRADE UNLESS OTHERWISE INDICATED. OTHERWISE THERMAL INSULATION IS REQUIRED AS PER STD. DWGW22. 	
4. PROVIDE MINIMUM 0.50m CLEARANCE BETWEEN OUTSIDE OF PIPES AT ALL CROSSINGS WHEN WATERMIAN IS BELOW AND MINIMUM 0.25m CLEARANCE WHEN WATERMAIN IS ABOVE.)
5. WATER SERVICE IS TO BE CONSTRUCTED TO WITHIN 1.0m OF FOUNDATION WALL AND CAPPED, UNLESS OTHERWISE INDICATED.	
6. ALL EXISTING WATER SERVICES TO BE BLANKED AT MAIN BY CITY FORCES. EXCAVATION AND REINSTATEMENT BY CONTRACTOTR	
GRADING NOTES:	SEWER & WATERMAIN I
 ALL TOPSOIL, ORGANIC OR DELETERIOUS MATERIAL MUST BE ENTIRELY REMOVED FROM BENEATH THE PROPOSED PAVED AREAS AS DIRECTED BY THE SITE ENGINEER OR GEOTECHNICAL ENGINEER. 	1. INSULATE ALL SEWER PIPES THAT THAN 2.0m COVER AND ALL WATE LESS THAN 2.4m OF COVER WITH POLYSTYRENE INSULATION AS PE
 EXPOSED SUBGRADES IN PROPOSED PAVED AREAS SHOULD BE PROOF ROLLED WITH A LARGE STEEL DRUM ROLLER AND INSPECTED BY THE GEOTECHNICAL ENGINEER PRIOR TO THE PLACEMENT OF GRANULARS. ANY SOFT AREAS EVIDENT FROM THE PROOF POLITING SHOULD BE SUB EXCAVATED AND REPLACED WITH 	POLYSTYRENE INSULATION AS PE 1109.030. 2. THE THICKNESS OF INSULATION S EQUIVALENT OF 25mm FOR EVER
 ANY SOFT AREAS EVIDENT FROM THE PROOF ROLLING SHOULD BE SUB-EXCAVATED AND REPLACED WITH SUITABLE MATERIAL THAT IS FROST COMPATIBLE WITH THE EXISTING SOILS AS RECOMMENDED BY THE GEOTECHNICAL ENGINEER. 	REDUCTION IN THE REQUIRED DE COVER WITH 50mm MINIMUM (SEE T = THICKNESS OF INSULATION (m
4. THE GRANULAR BASE SHOULD BE COMPACTED TO AT LEAST 99% OF THE STANDARD PROCTOR MAXIMUM DRY DENSITY VALUE. ANY ADDITIONAL GRANULAR FILL USED BELOW THE PROPOSED PAVEMENT SHOULD BE COMPACTED TO AT LEAST 95% OF THE STANDARD PROCTOR MAXIMUM DRY DENSITY VALUE.	W = WIDTH OF INSULATION (mm) $W = D + 300 (1000 min.)$ $D = O.D OF PIPE (mm)$
 MINIMUM OF 2% GRADE FOR ALL GRASS AREAS UNLESS OTHERWISE NOTED. MAXIMUM TERRACING GRADE TO BE 3:1 UNLESS OTHERWISE NOTED. 	
7. ALL GRADES BY CURBS ARE EDGE OF PAVEMENT GRADES UNLESS OTHERWISE INDICATED.	
 ALL CURBS SHALL BE BARRIER CURB (150mm) UNLESS OTHERWISE NOTED AND CONSTRUCTED AS PER CITY OF OTTAWA STANDARDS (SC1.1). REFER TO LANDSCAPE PLAN FOR PLANTING AND OTHER LANDSCAPE FEATURE DETAILS. 	
 REPER TO LANDSCAPE PLAN FOR PLANTING AND OTHER LANDSCAPE PEATORE DETAILS. 10. CONTRACTOR TO PROVIDE THE CONSULTANT WITH A GRADING PLAN INDICATING AS-BUILT ELEVATIONS OF ALL DESIGN GRADES SHOWN ON THIS PLAN. 	
PAVEMENT STRUCTURE:	
LIGHT DUTY 50mm HL3 150mm GRAN "A"	
300mm GRAN "B" TYPE II HEAVY DUTY	
40mm HL3 50mm HL8 150mm GRAN "A" 450mm GRAN "B" TYPE II	
ITION OF ALL POLE LINES, CONDUITS, AINS, SEWERS AND OTHER ROUND AND OVERGROUND UTILITIES AND	
JRES IS NOT NECESSARILY SHOWN ON TRACT DRAWINGS, AND WHERE SHOWN,	NOT
URACY OF THE POSITION OF SUCH 3 AND STRUCTURES IS NOT GUARANTEED.	CONSTR

LOCATION OF ALL SUCH UTILITIES AND

DAMAGE TO THEM.

STRUCTURES AND ASSUME ALL LIABILITY FOR

NOT FOR CONSTRUCTION

SEDIMENT CONTROL NOTES :


SEDIMENT CONTROLS SHALL BE INSTALLED TO THE SATISFACTION OF THE ENGINEER, CITY OF CONSERVATION AUTHORITY. THEY SHALL BE APPROPRIATE TO THE SITE CONDITIONS, PRIOR TO Y SITE ALTERATIONS (FILLING, GRADING, REMOVAL OF VEGETATION, ETC.) AND DURING ALL PHASES TION AND CONSTRUCTION. THESE PRACTICES SHALL BE IMPLEMENTED IN ACCORDANCE WITH THE IANAGEMENT PRACTICES FOR EROSION AND SEDIMENT CONTROL AND SHOULD INCLUDE AS A MEASURES INDICATED ON THE PLAN.

FACE EROSION FROM ENTERING THE DITCH OR STORM SYSTEM DURING CONSTRUCTION, FILTER ACED UNDER GRATES OF ALL PROPOSED AND EXISTING CATCHBASINS AND STRUCTURES. A LIGHT BARRIER WILL ALSO BE INSTALLED IN SELECTED LOCATIONS, AND STRAW BALE BARRIERS WILL BE I THE OUTLET DITCHES. THESE CONTROL MEASURES WILL REMAIN IN PLACE UNTIL VEGETATION ISHED AND CONSTRUCTION COMPLETE.

ONTROL MEASURES SHALL ONLY BE REMOVED WHEN, IN THE OPINION OF THE ENGINEER, THE IO LONGER REQUIRED. NO CONTROL MEASURES MAY BE PERMANENTLY REMOVED WITHOUT PRIOR


R SHALL IMMEDIATELY REPORT TO THE ENGINEER ANY ACCIDENTAL DISCHARGES OF SEDIMENT ANY DITCH OR STORM SEWER SYSTEM. APPROPRIATE RESPONSE MEASURES, INCLUDING ANY ING CONTROL MEASURES OR THE IMPLEMENTATION OF ADDITIONAL CONTROL MEASURES, SHALL BY THE CONTRACTOR WITHOUT DELAY.


R ACKNOWLEDGES THAT FAILURE TO IMPLEMENT EROSION AND SEDIMENT CONTROL MEASURES TO PENALTIES IMPOSED BY ANY APPLICABLE REGULATORY AGENCY. R SHALL PROVIDE DUST CONTROL WITH THE APPLICATION OF WATER AND/OR CALCIUM CHLORIDE



MUD MAT DETAIL NOT TO SCALE

WATERMAIN INSULATION NOTES:







					SCALE
7					AS SHO
	3.	ISSUED FOR SPA	APR 28/23	GJM	
IDGE A · E · S	2.	REVISED PER CITY COMMENTS	OCT 11/22	GJM	
V.G.2	1.	REVISED PER CITY COMMENTS	MAY 31/22	GJM	
	No.	REVISION	DATE	BY	



CLARIDGE HOMES CLARIDGE HOMES 505 PRESTON STREET, OTTAWA , ONTARIO K1S 4N7.










CISTERN SECTION N.T.S










LEGEND			PROPOSED TRENCH DRAIN
	PROPERTY LINE		PROPOSED BUILDING ENT
	PROPOSED CURB		DIRECTION OF FLOW
	PROPOSED DEPRESSED CURB		PROPOSED RETAINING WA
	PROPOSED TACTILE WALKING SURFACE INDICATOR (TWSI)	1	PIPE CROSSING
0	PROPOSED STORM MANHOLE	· ·	PROPOSED SWALE
\bigcirc	PROPOSED CATCHBASIN MANHOLE	ւն մե	PROPOSED TERRACING
	PROPOSED CATCHBASIN	$\bigcirc \rightarrow$	EXISTING UTILITY POLE C/V
0	PROPOSED LANDSCAPE DRAIN		EXISTING WATERMAIN C/W
	PROPOSED AREA DRAIN		EXISTING HYDRANT C/W V
мм	PROPOSED MUD MAT	SAN MH	EXISTING SANITARY MANH
	LIGHT DUTY SILT FENCE (OPSD 219.110)	ST <u>M MH</u>	EXISTING STORM MANHOLI
	PROPOSED FILTER BAGS AT CATCHBASINS,	CB 1 .	EXISTING CATCHBASIN
\bigcirc	CATCHBASIN MANHOLES AND TRENCHDRAINS	OHW	EXISTING OVERHEAD WIRE

CALE	DESIGN	FOR REVIEW ONLY			LOCATION	
:250	ARM/CJF	OROFESSION	PROFESSIONA	ΝΟΛΤΞΟΗ	CITY OF OTTAWA 1200 MARITIME WAY	
.200	ARM/JAG DRAWN CJF	A.R. MESTWARP	G.J. MacDONALD	Engineers, Planners & Landscape Architects Suite 200, 240 Michael Cowpland Drive Ottawa, Ontario, Canada K2M 1P6	DRAWING NAME EROSION AND SEDIMENT	
1:250	CHECKED	APRIL 28 /2023 BOUNCE OF ONTAHIO	April 28, 2023 April 28, 2023	Telephone (613) 254-9643 Facsimile (613) 254-5867 Website www.novatech-eng.com	CONTROL PLAN	
	approved	THE OF ON	CC OF	website www.hovatech-eng.com		



LOWER PIPE	HIGHER PIPE	CLEARANCE
200mmØ SAN OBV = 93.29	300mmØ STM INV = 94.07*	0.78m
600mmØ WM OBV = 93.90	450mmØ STM INV = 94.28*	0.38m
1650mmØ STM OBV = 92.68*	200mmØ SAN INV = 93.67	0.99m
600mmØ WM OBV = 93.45	200mmØ SAN INV = 93.71	0.26m
600mmØ WM OBV = 93.44	300mmØ STM INV = 93.71	0.27m
825mmØ SAN OBV = 91.79*	200mmØ WM INV = 92.80	1.01m
1650mmØ STM OBV = 92.67*	200mmØ WM INV = 92.92	0.25m
600mmØ WM OBV = 93.43	200mmØ WM INV = 93.69	0.26m
825mmØ SAN OBV = 91.79*	200mmØ WM INV = 92.78	0.99m
1650mmØ STM OBV = 92.67*	200mmØ WM INV = 92.92	0.25m
600mmØ WM OBV = 93.43	200mmØ WM INV = 93.68	0.25m
600mmØ WM OBV = 93.41	375mmØ STM INV = 94.24	0.83m
600mmØ WM OBV = 94.05	200mmØ WM INV = 94.30	0.25m
1650mmØ STM OBV = 92.82*	200mmØ WM INV = 93.48	0.66m
825mmØ SAN OBV = 91.84*	200mmØ WM INV = 93.53	1.69m
	200mmØ SAN OBV = 93.29 600mmØ WM OBV = 93.90 1650mmØ STM OBV = 92.68* 600mmØ WM OBV = 93.45 600mmØ WM OBV = 93.44 825mmØ SAN OBV = 91.79* 1650mmØ STM OBV = 92.67* 600mmØ WM OBV = 93.43 825mmØ SAN OBV = 91.79* 1650mmØ STM OBV = 92.67* 600mmØ WM OBV = 93.43 600mmØ WM OBV = 93.41 600mmØ WM OBV = 94.05	200mmØ SAN OBV = 93.29 300mmØ STM INV = 94.07* 600mmØ WM OBV = 93.90 450mmØ STM INV = 94.28* 1650mmØ STM OBV = 92.68* 200mmØ SAN INV = 93.67 600mmØ WM OBV = 93.45 200mmØ SAN INV = 93.71 600mmØ WM OBV = 93.44 300mmØ STM INV = 93.71 825mmØ SAN OBV = 91.79* 200mmØ WM INV = 92.80 1650mmØ STM OBV = 92.67* 200mmØ WM INV = 92.92 600mmØ WM OBV = 93.43 200mmØ WM INV = 93.69 825mmØ SAN OBV = 91.79* 200mmØ WM INV = 92.78 1650mmØ STM OBV = 92.67* 200mmØ WM INV = 92.92 600mmØ WM OBV = 93.43 200mmØ WM INV = 92.92 600mmØ WM OBV = 93.43 200mmØ WM INV = 92.92 600mmØ WM OBV = 93.41 375mmØ STM INV = 94.24 600mmØ WM OBV = 94.05 200mmØ WM INV = 93.48

<u>ND</u>	
	PROPERTY LINE
	PROPOSED CURB
	PROPOSED DEPRESSED CURB
	PROPOSED TACTILE WALKING SURFACE INDICATOR (TWSI)
	PROPOSED CAP
	PROPOSED SANITARY SEWER C/W MANHOL
	PROPOSED STORM SEWER C/W MANHOLE
	PROPOSED CATCHBASIN MANHOLE
	PROPOSED CATCHBASIN
	PROPOSED LANDSCAPE DRAIN
	PROPOSED AREA DRAIN
	PROPOSED INLET CONTROL DEVICE
	PROPOSED SIAMESE CONNECTION
	PROPOSED WATER MAIN
-	PROPOSED HYDRANT c/w LEAD & VALVE
	PROPOSED VALVE AND VALVE BOX
	PROPOSED WATER METER
	PROPOSED REMOTE WATER METER

	PROPOSED TR
▼	PROPOSED BL
	DIRECTION OF
	PROPOSED RE
1	PIPE CROSSIN
· ·	PROPOSED SW
սի սի	PROPOSED TE
	EXISTING UTIL
/// 	EXISTING WATE
	EXISTING HYD
	EXISTING SANI
∕⊖ —	EXISTING STOP
1.	EXISTING CATO

PROPOSED WATERMAIN (200mmØ DOMESTIC SERVICE TABL					
STATION SURFACE T/WM ELEVATION ELEVATION			COMMENTS		
1+000.0	95.31	*92.91	CONNECTION TO EXISTING 200mmØ WM		
1+002.5	95.38	92.98	CROSS ABOVE 825mmØ SAN (0.99m CLEARAI		
1+005.3	95.47	93.12	CROSS ABOVE 1650mmØ STM AS PER CITY OTTAWA STANDARD W25.2 (0.25m CLEARAN		
1+008.3	95.40	93.88	CROSS ABOVE 600mmØ WM AS PER CITY O OTTAWA STANDARD W25.2 (0.25m CLEARAN		
1+017.7	95.37	92.97	200mmØ VALVE AND VALVE BOX		
1+022.0	95.13	92.73	САР		

VERIFY AND REPORT ANY DISCREPANCIES TO PROJECT ENGINEER PRIOR TO CONSTRUCTION.

	PROPOSED WATERMAIN (200mmØ DOMESTIC SERVICE TABLE				
	STATION	SURFACE ELEVATION	T/WM ELEVATION	COMMENTS	
	2+000.0	95.33	92.93	CONNECTION TO EXISTING 200mmØ WM	
	2+002.5	95.40	93.00	CROSS ABOVE 825mmØ SAN (0.99m CLEARAN	
	2+005.4	95.47	93.12	CROSS ABOVE 1650mmØ STM AS PER CITY O OTTAWA STANDARD W25.2 (0.25m CLEARANC	
	2+008.3 95.41		93.89	CROSS ABOVE 600mmØ WM (0.26m CLEARANO	
	2+017.7	95.38	92.25	200mmØ VALVE AND VALVE BOX	
2+021.4 95.13 95.13 CAP					
	*TOP OF EXISTING WATERMAIN ASSUMED 2.4m BELOW EXISTING GROUND. CONTRACTOR TO				

VERIFY AND REPORT ANY DISCREPANCIES TO PROJECT ENGINEER PRIOR TO CONSTRUCTION.


PROPOS	PROPOSED WATERMAIN (200mmØ DOMESTIC SERVICE TABLE					
STATION	SURFACE T/WM ELEVATION ELEVATION		COMMENTS			
3+000.0	96.08	93.68	CONNECTION TO EXISTING 200mmØ WM			
3+003.6	96.11	93.71	CROSS ABOVE 825mmØ SAN (1.69m CLEARAN			
3+006.3	96.08	93.68	CROSS ABOVE 1650mmØ STM AS PER CITY (OTTAWA STANDARD W25.2 (0.66m CLEARANC			
3+009.0	96.02	94.50	CROSS ABOVE 600mmØ WM (0.25m CLEARAN			
3+018.2	96.45	94.05	11.25° HORIZONTAL BEND			
3+023.7	96.93	94.53	200mm VALVE AND VALVE BOX			
3+025.0	96.98	94.58	CAP			
*TOP OF EXISTING WATERMAIN ASSUMED 2.4m BELOW EXISTING GROUND. CONTRACTOR TO						

VERIFY AND REPORT ANY DISCREPANCIES TO PROJECT ENGINEER PRIOR TO CONSTRUCTION.


PROPOSED WATERMAIN (200mmØ DOMESTIC SERVICE TABLE)

STATION	SURFACE ELEVATION	T/WM ELEVATION	COMMENTS	
4+000.0	96.09	*93.69	CONNECTION TO EXISTING 200mmØ WM	
4+004.1	96.13	93.73	CROSS ABOVE 825mmØ SAN (1.69m CLEARAN	
4+006.7	96.08	93.68	CROSS ABOVE 1650mmØ STM AS PER CITY (OTTAWA STANDARD W25.2 (0.66m CLEARAN)	
4+009.3	96.02	94.50	CROSS ABOVE 600mmØ WM AS PER CITY O OTTAWA STANDARD W25.2 (0.25m CLEARANC	
4+012.7	96.17	93.77	11.25° HORIZONTAL BEND	
4+024.3	96.93	94.53	200mmØ VALVE AND VALVE BOX	
4+025.3	96.98	94.58	CAP	
TOP OF EXIS	TING WATERMA	AIN ASSUMED 2.4	m BELOW EXISTING GROUND. CONTRACTOR TO	

CONTROLS						
	LOCATION	MODEL NO. / ORFICE DIAMETER	5-YEAR FLOW (L/S)	5-YEAR HEAD (m)	100-YEAR FLOW (L/S)	10 HE
	CBMH 105	152mm PLATE	32.0	0.414	49.6	
	CISTERN	PUMP	133	0.53	133	



City Plan #18348



				REF	ER TO 120144-ND FOR ADDITIONAL NOT
CALE	DESIGN	FOR REVI	EW ONLY		LOCATION
:250		PROFESSIONA	PROFESSIONAL	ΝΟΛΤΞΟΗ	CITY OF OTTAWA 1200 MARITIME WAY
.230	ARM/JAG drawn CJF	A.R. MESTWARP	G.J. MacDONALD	Engineers, Planners & Landscape Architects Suite 200, 240 Michael Cowpland Drive	DRAWING NAME GRADING PLAN
1:250 6 8 10	CHECKED ARM/JAG	APRIL 28 /2023	April 28, 2023 April 28, 2023 April 28, 2023 April 28, 2023 April 28, 2023	Ottawa, Ontario, Canada K2M 1P6 Telephone (613) 254-9643 Facsimile (613) 254-5867 Website www.novatech-eng.com	
	GJM				