DO NOT SCALE DRAWINGS;

NOTES ARE APPLICABLE TO ALL DRAWINGS IN THE SET;

Fotenn Consultants Inc. IS NOT RESPONSIBLE FOR ACCURACY OF BASE INFORMATION;

REFER TO CIVIL ENGINEERING DRAWINGS FOR GRADING & SITE SERVICING INFORMATION;

THE CONTRACTOR IS RESPONSIBLE FOR CONFIRMING SITE CONDITIONS AND REPORTING ANY DISCREPANCIES TO THE LANDSCAPE ARCHITECT;

THE CONTRACTOR IS RESPONSIBLE FOR CONFIRMING EXACT LOCATIONS OF ALL UNDERGROUND SERVICES AND OBTAINING CLEARANCE FROM ALL APPLICABLE UTILITIES. PROPOSED WORKS FOUND TO BE IN CONFLICT WITH UNDERGROUND SERVICES MAY BE ADJUSTED AT THE DIRECTION OF THE LANDSCAPE ARCHITECT;

LANDSCAPE ELEMENTS SHOWN ARE SUBJECT TO THE FINAL LOCATION OF UNDERGROUND SERVICES AND

DO NOT INSTALL TREES ON PROPERTY / LOT LINES OR WITHIN DRAINAGE EASEMENTS;

PERFORM WORK IN ACCORDANCE WITH DETAILS AND SPECIFICATIONS;

ALL PLANT MATERIAL SHALL BE No. 1 NURSERY STOCK AND SHALL MEET OR EXCEED THE SPECIFICATION OF THE Canadian Standards for Nursery Stock, AS PUBLISHED BY THE Canadian Nursery Landscape Association;

SPECIES SUBSTITUTIONS ARE NOT PERMITTED WITHOUT PRIOR WRITTEN APPROVAL OF THE LANDSCAPE

ALL UN-PAVED SURFACES TO RECEIVE 150mm DEPTH TOPSOIL & SOD.

STANDARDS FOR TREE PLANTING:

NO PLANTING ON CORNERS OR ANYWHERE WHERE IT WOULD CREATE A SIGHT LINE CONCERN;

MAINTAIN A MINIMUM DISTANCE OF 2.5m FROM THE CURB FOR DECIDUOUS TREES AND 4.5m FOR CONIFEROUS TREES;

MAINTAIN A MINIMUM DISTANCE OF 1.5m FOR DECIDUOUS (4.5m FOR CONIFERS) FROM ANY SIDEWALK OR PRIVATE WALKWAY;

MAINTAIN A MINIMUM DISTANCE OF 1.2m FROM ALL DRIVEWAYS;

MAINTAIN A MINIMUM DISTANCE OF 2.5m FROM COMMUNITY MAILBOXES, LIGHT STANDARDS, FIRE HYDRANTS AND NO PLANTING IN FRONT OF HYDRANTS;

MAINTAIN A MINIMUM DISTANCE OF 3.0m FROM ALL HYDRO TRANSFORMERS; MAINTAIN A MINIMUM DISTANCE OF 1.0m FROM ALL UNDERGROUND SERVICES;

MAINTAIN A MINIMUM DISTANCE OF 1.0m FROM ALL BELL AND CABLE BOXES;

MAINTAIN A MINIMUM DISTANCE OF 10.0 FROM BUS SHELTERS

ALLISON HAMLIN

PLANNING, REAL ESTATE & ECONOMIC DEVELOPMENT **DEPARTMENT, CITY OF OTTAWA**


APPROVED


By Allison Hamlin at 5:16 pm, Feb 29, 2024


Client / Client MANAGER (A), DEVELOPMENT REVIEW WEST


key plan / plan repère

legend / légende









AND QUANTITIES)



0.45m HIGH RETAINING WALL


BIKE RACK

* * * 2×1m HIGH BLACK CHAIN LINK FENCE

of revised in response to Consultant changes of revised in response to City comments 2023/12/18 2023/08/24 04 re-issue for SPA 2023/07/24 03 re-issue for SPA 2023/03/31 02 re-issue for SPA 01 issue for SPA 2022/12/16

2022/11/15 00 issue for ZBLA

396 Cooper Street, Suite 300 Ottawa, ON, CANADA K2P 2H7




project / projet


3430 CARLING AVENUE


drawing / dessin

LANDSCAPE PLAN

designed / conçu BM / EM	drawn / dessiné BM / EM	reviewed / examiné
date Nov. 2022	project number / No. du projet	











— — — EXTENTS OF UNDERGROUND PARKING GARAGE

(REFER TO PLANTING SCHEDULE FOR SPECIES


(REFER TO PLANTING SCHEDULE FOR SPECIES


0.45m HIGH RETAINING WALL

	06	revised in response to Consultant changes	2024/01/12
	05	revised in response to City comments	2023/12/18
	04	re-issue for SPA	2023/08/24
	03	re-issue for SPA	2023/07/24
	02	re-issue for SPA	2023/03/31
	01	issue for SPA	2022/12/16
	00	issue for ZBLA	2022/11/15
			, , , , , ,




project number / No. du projet





PRECAST UNIT PAVERS

n.t.s.



DEPARTMENT, CITY OF OTTAWA

Client / Client

key plan / plan repère

PLANNING, REAL ESTATE & ECONOMIC DEVELOPMENT

APPROVED

ALLISON HAMLIN MANAGER (A), DEVELOPMENT REVIEW WEST

By Allison Hamlin at 5:16 pm, Feb 29, 2024

of revised in response to Consultant changes

2023/12/18

2023/08/24

2023/07/24

2023/03/31

2022/12/16

2022/11/15

os revised in response to City comments

04 re-issue for SPA

03 re-issue for SPA

02 re-issue for SPA

01 issue for SPA

00 issue for ZBLA

SURFACE MOUNTED BIKE RACK ON PAVERS W/ CIP CONC. MOUNT n.t.s.

ROOT PRUNING DETAIL

WIPED WITH ALCOHOL BEFORE EACH CUT.

NOTES:

APPROVED BY LANDSCAPE ARCHITECT) TO PREVENT DESSICATION;

PROPER ROOT PRUNING TECHNIQUE REQUIRED WHEN TREE ROOTS ENCOUNTERED DURING EXCAVATION.


AFTER ROOTS ARE CLEANLY CUT, THE AREA SHOULD BE BACKFILLED WITH SUITABLE MATERIAL (TO BE


AND / OR RESTORE THE BALANCE BETWEEN TOP GROWTH AND ROOTS. DO NOT PRUNE LEADERS.

EXCAVATIONS WITHIN DRIPLINE SHOULD BE BY DIRECTIONAL MICRO-TUNNELLING AND BORING. OUTSIDE THE

WHERE APPROPRIATE, THE TREES SHALL UNDERGO AN OVERALL PRUNING TO RESTORE TREE APPEARANCE

DRIPLINE, ROOTS SHOULD BE CUT CLEANLY (AS PER ABOVE DRAWING) WITH PRUNING SHEARS OR A SAW





DECIDUOUS TREE PLANTING

n.t.s.

TREE PROTECTION FENCING

n.t.s.

PRUNE AWAY APPROX. 20% AND/OR DAMAGED BRANCHES BAREROOT STOCK: SPREAD ROOTS EVENLY AND ENSURE EVEN SOIL COVERAGE AROUND ROOTS; POTTED STOCK: COMPLETELY REMOVE POT FROM ROOTBALL ^ **X X X X X X X X X X** X XXXXXXXXXXX MULCH LAYER TO 60mm DEPTH -CLEAR AWAY FROM STEM OF SHRUB MIN. 400mm PLANTING MEDIUM, BACKFILLED AND HAND-TAMPED IN LIFTS AS TO AVOID ROOTBALL DISTURBANCE SCARIFY BOTTOM OF BED/PIT UNDISTURBED SUBGRADE

TREE PROTECTION

LIMIT OF CLEARING

ROOT PRUNING TRENCH

AND GRADING

MAX.150mm

CUT ROOTS


CLEANLY AS PER

NOTES BELOW

FENCING

SHRUB PLANTING

n.t.s.



PERENNIAL PLANTING

Ottawa, ON, CANADA K2P 2H7 north / le nord stamp / le cachet project / projet

3430 CARLING AVENUE

drawing / dessin

LANDSCAPE PLAN

drawn / dessiné reviewed / examiné BM / EM BM / EM project number / No. du projet Nov. 2022

n.t.s.