



**LOCATION PLAN** 

- protection from damage during construction.
- Plant Material locations are **Schematic / Approximate** only. Contractor shall stake out locations on site prior to
- **Shrubs** shall be planted in a continuous prepared bed of 450mm depth planting soil mix covered over with a woven polypropylene weed control fabric (LANDSCAPE FABRIC-Green-Line by Thrace-LINQ) and 75mm depth
- Perennials and Ornamental Grasses shall be planted in a continuous prepared bed of 450mm depth planting soil mix covered over with 75mm depth composted pine mulch to finish grade as specified. (NO WEED
- quality conforming to the Canadian Nursery Sod Growers
- Reinstate all areas damaged or disturbed beyond the
- Plant Material substitutions shall not be permitted without
- prior to proceeding landscape work and any required

### **GENERAL NOTES**

This drawing shall be read in conjunction with all relevant Architectural, Engineering and related Drawings and

N.T.S.

- Refer to Engineering Drawings for Grading and
- Refer to Architectural Drawings for Site layout.
- Utility companies and shall be responsible for adequate
- Contractor shall guarantee all plant material for a period
- Sod areas to receive 125mm topsoil. Sod shall be No. 1
- written approval from the Consultant.
- Field Reviews.

- Contractor shall provide the location(s) of all
- edition), published by the Canadian Nursery Trades
- of one (1) full year from the date of Completion.

- limit of Work.

- Documents.
- Servicing.
- services/utilities by consulting Municipal Authorities and
- Plant material shall be No.1 Grade and shall comply with the Metric Guide Specifications For Nursery Stock (latest Association.
- composted pine mulch to finish grade, as specified.
- CONTROL FABRIC)
- Specification.
- Contractor shall advise Consultant a minimum of 48hrs.
- THIS PLAN HAS BEEN PREPARED FOR MUNICIPAL SITE PLAN APPROVAL ONLY AND MAY NOT BE **USED FOR ANY OTHER PURPOSE.**

## PLANT MATERIAL SCHEDULE

CODE	BOTANICAL NAME	COMMON NAME	QTY.	SIZE	REMARKS / (N) NATIVE
DECIDU	OUS TREES		•	•	
CO	CELTIS OCCIDENTALIS	COMMON HACKBERRY	3	50mm cal	B&B, single-stem / N
GT	GLEDITSIA TRIACANTHOS SKYLINE	SKYLINE HONEYLOCUST	3	50mm cal	B&B, single-stem
CONIFE	ROUS TREES		•		
PG	PICEA GLAUCA	WHITE SPRUCE	3	200 cm ht	B&B / <b>N</b>
SHRUBS	3	·			
PFG	POTENTILLA FRUTICOSA GOLDFINGER	GOLDFINGER CINQUEFOIL	34	50cm ht	potted, 100cm o/c
PO	PHYSOCARPUS OPULIFOLIUS	COMMON NINEBARK	30	50cm ht	potted, 100cm o/c / N
RB	ROSA BLANDA	SHRUB ROSE	40	50cm ht	potted, 100cm o/c / N
ORNAM	ENTAL GRASSES		•		
Cal	CALAMAGROSTIS canadensis	CANADA BLUEJOINT	32	15cm pot	plant 75cm o/c / N

## SCHEDULE OF EXISTING TREES

(Inventory conducted Oct. 1, 2021)

CODE	SPECIES	CONDITION	DBH <sup>1</sup> (cm)	OWNERSHIP	ACTION NOTES
1	Honeylocust	good	22	Private (Owner)	REMOVE / Development conflict;
2	Spruce	good	23	Private (Owner)	REMOVE / Development conflict;
3	Spruce	good	22	Private (Owner)	REMOVE / Development conflict;
4	Spruce	good	20	Private (Owner)	REMOVE / Development conflict;
5	Linden	good	16	Private (Owner)	REMOVE / Development conflict;
6	Linden	good	23	Private (Owner)	REMOVE / Development conflict;

No tree species at risk, as identified under the Province of Ontario Endangered Species Act (ESA), were found on subject property or within 25m of adjacent properties.

In conformance to the guidelines outlined in the City of Ottawa Protocol for Wildlife Protection During Construction, no <u>clearing of vegetation</u> shall occur between April 15 and August 15, unless a qualified biologist has determined that no bird nesting is occurring within 5 days prior to clearing. A pre-clearing survey for active stick nests and cavity nests shall also be conducted between April 1 and April 15 in order to identify and protect early nesting owls and raptors.

LEGEND / SYMBOL



EXISTING TREE TO BE REMOVED (Refer to Schedule of Existing Trees)

**EXISTING TREE** TO BE RETAINED

CRZ (Critical Root Zone)



PROPOSED DECIDUOUS TREE DETAIL 1/L2.01



PROPOSED CONIFEROUS TREE DETAIL 1/L2.01




PROPOSED SHRUBS, PERENNIALS, ORNAMENTAL GRASSES DETAIL 1/L2.01

PROPOSED BICYCLE PARKING SPACES PROVIDED: 20 PROPOSED BICYCLE RACK PROPOSED QTY.: 10



DETAIL 3/L2.01

DETAIL 2/L2.01





PROPOSED LIMIT OF CURRENT APPLICATION

OWNER: WOODVALE PENTECOSTAL CHURCH

205 Greenbank Rd., Ottawa, ON K2H 8K9 ARCHITECT: HOBIN ARCHITECTURE INC. 63 Pamilla St., Ottawa, ON K1S 3K7

**CIVIL ENGINEER:** D.B.GRAY ENGINEERING 700 Longpoint Circle, Ottawa, ON K1T 4E9

STRUCTURAL ENGINEER: 2611 Queensview Dr., Ottawa, ON K2B 8K2

MECHANICAL / ELECTRICAL: GOODKEY WEEDMARK 1688 Woodward Dr., Ottawa, ON K2C 3R8

LANDSCAPE ARCHITECT LEVSTEK CONSULTANTS INC. 5871 Hugh Cresc., Ottawa, ON K0A 2W0


LEGAL DESCRIPTION: Part 1, Plan of, Part of North Half of Lot 31 and Concession 2 (Rideau Front). Geographic Township of Nepean,

City of Ottawa.

# FOR APPROVAL ONLY

1						
	5.	MAR.28/24	PER CITY COMMENTS (3)			
	4.	FEB.29/24	PER CITY COMMENTS (2)			
	3.	NOV.28/23	PER CITY COMMENTS (1)			
	2.	AUG.31/23	ISSUE FOR SITE PLAN APPROVAL			
	1	OCT 19/21	ISSUE FOR REVIEW			

o. date



Contractor shall check and verify all dimensions on site and report all errors and/or omissions to the Consultant. Work to be done in accordance with all applicable codes and

Do not scale Drawing. This Drawing shall not be used for construction until signed by the Consultant.

Copyright reserved. This Drawing is the exclusive property of Levstek Consultants Inc. and shall not be used without consent

LEVSTEK CONSULTANT 5871 Hugh Crescent · Ottawa · Ontario · KOA 2WO 613 · 826 · 0518



**WOODVALE PENTECOSTAL CHURCH ADDITION** PHASE 2

205 GREENBANK ROAD

LANDSCAPE / TCR PLAN

Prawing No. L1.01 1199 1:400