



This document and all information herein is confidential and the intellectual property of Rossmann Architects. It is disclosed in confidence on terms that it will not be disclosed to any third party, used, sold, loaned, licensed, or reproduced in whole or in any part in any manner or form for manufacturing, tendering or for any other purpose without the written permission of Rossmann Architects. The copyright is retained by Rossmann Architects and Associates Inc.

NOTE-A :
ALL DRAWINGS ARE TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS AND SPECIFICATIONS, INCLUDING OTHER CONSULTANTS DRAWINGS AND SPECIFICATIONS. ANY DISCREPANCIES BETWEEN DRAWINGS WILL BE REPORTED TO THE PROJECT LEAD IMMEDIATELY FOR CLARIFICATION PRIOR TO COMMENCING ANY CONSTRUCTION.

NOTE-B :
ALL GENERAL SITE INFORMATION AND CONDITIONS HAVE BEEN COMPILED FROM EXISTING PLANS AND SURVEYS.

NOTE-C :
CONTRACTOR IS RESPONSIBLE TO CHECK AND VERIFY ALL DIMENSIONS ON SITE AND REPORT ALL ERRORS AND / OR OMISSIONS TO THE ARCHITECT.

NOTE-D :
REFER TO LANDSCAPE PLAN FOR ALL EXTERIOR LANDSCAPING.

NOTE-E :
DO NOT SCALE DRAWINGS.

NOTE-F :
ALL CONTRACTORS MUST COMPLY WITH ALL APPLICABLE CODES AND REGULATIONS.

SURVEY INFO
TOPOGRAPHIC SURVEY OF :
Stantec Geomatics Ltd.
PART OF LOT 14, CONCESSION 2
(OTTAWA FRONT) GEOGRAPHIC
TOWNSHIP OF GLOUCESTER,
CITY OF OTTAWA

PROJECT INFORMATION

SITE SUMMARY
ADDRESS: 98-100 BEARBROOK RD.
GLOUCESTER, OTTAWA

CURRENT ZONING: AM11
SITE AREA: 3914.04 m²
PROPOSED USE: RESIDENTIAL
BUILDING AREA: 1812.30 m²

ZONING SUMMARY

	REQUIRED	PROPOSED
LOT AREA	3914.04 m ²	3914.04 m ²
LOT WIDTH	0.00 m	78.91 m
MAX. BUILDING HEIGHT	30.00 m	30.00 m
MAX. PARAPET HEIGHT	0.00 m	0.90 m

SET BACKS

	REQUIRED	PROPOSED
- FRONT YARD	3.00 m (min.)	3.00 m
- CORNER SIDE YARD	5.00 m (max.)	0.00 m
- INTERIOR SIDE YARD	7.50 m (min.)	7.50 m
- INTERIOR SIDE YARD	All other case	0.00 m
- REAR YARD	10.00 m (min.)	12.73 m

MIN LANDSCAPED AREA

	REQUIRED	PROPOSED
MIN LANDSCAPED AREA	0.00 m ²	605.41 m ²

PARKING

	REQUIRED	PROPOSED
VEHICULAR:		
MID-RISE	1.2 / UNIT	175
VISITORS:	0.2 / UNIT	32
ACCESSIBLE (inc. in count):	3	3
BICYCLE:		
BICYCLE:	0.5 / UNIT	80
		86

WASTE MANAGEMENT CONTAINERS

	REQUIRED	PROVIDED
GARBAGE (160X0.11Y=18Y)	4Y ²	5X4Y ²
RECYCLING (160X0.38Y=6Y)	4Y ²	2K4Y ²
ORGANICS (240L per 50 UNITS=4)	240L	4

AMENITY AREA

	REQUIRED	PROPOSED
PRIVATE	480 m ²	1760.18 m ²
COMMUNAL	480 m ²	543 m ²

(CALC: 6 m² / UNIT - MIN 50% MUST BE COMMUNAL)

SUMMARY OF PROPOSED:

160 APARTMENTS:
Four bed 'Townhouses' x 2
Two bed 'Townhouses' x 7
Studio x 7;
1 Bed x 36;
1 Bed + Den x 74;
2 Bed x 31;
3 Bed x 3;


PARKING BAYS: 32 Exterior + 176 Interior = 208 Total
PARKING GARAGE: 3306.99m² x 2= 6613.98 m²

TOTAL BUILDING AREA: 14 463.88 m² (excl. garage)
PROPOSED COVERAGE: 51.00 % (1828.44 m²)

KEYNOTE DESCRIPTIONS

- GARAGE ENTRANCE
- PROPOSED ROOFTOP TERRACE (NINTH FLOOR)
- TRANSFORMER PAD
- ELEVATOR SHAFT
- STAIRCASE SHAFT
- TOWNHOUSE ENTRANCE
- CONCRETE CURB

PROJECT NO. / NO. DE PROJET : 21046
DATE : 2024-07-08
DRAWN BY / DESSINÉ PAR : M.ALLEN
REVIEWED BY / VÉRIFIÉ PAR : E.SOULIERE
SCALE / ÉCHELLE : 1 : 150
PROJECT PHASE / PHASE DU PROJET : 1
DWG NO. / NO. DESSIN : A003
REVISION NO. / NO. DE RÉVISION : 1.32



1 SITE PLAN
A003 1:150

John Seigny
JOHN SEIGNY C.E.T.
MANAGER (A), DEVELOPMENT REVIEW EAST
PLANNING, DEVELOPMENT & BUILDING SERVICES
DEPARTMENT, CITY OF OTTAWA

APPROVED
By seignyjo at 11:26 am, Dec 09, 2024

UNIT COUNT	2 Bedroom "TOWNHOUSE"	4 Bedroom "TOWNHOUSE"	STUDIO	1 BEDROOM	1 BED + DEN	2 BEDROOM	3 BEDROOM	TOTAL
GROUND FLOOR	7	2		1	4	2		16
2ND FLOOR	(7)	(2)	1	4	5	2		12
3RD FLOOR			1	5	11	4		21
4TH FLOOR			1	5	11	4		21
5TH FLOOR			1	5	11	4		21
6TH FLOOR			1	5	11	4		21
7TH FLOOR			1	5	11	4		21
8TH FLOOR			1	6	10	3		20
9TH FLOOR						4	3	7
TOTAL	7	2	7	36	74	31	3	160

SITE CONTEXT



LEGEND

- SURFACES**
- GRASS
 - POURED CONCRETE
 - CONCRETE PAVERS
 - ASPHALT PAVING
 - PROPOSED NEW BUILDING
 - PEDESTRIAN ROUTE
 - HEIGHT RESTRICTION ZONE PER AM11(11.1-iv)
- VEGETATION**
- TREE: EXISTING TO REMAIN
 - TREE: EXISTING TO BE REMOVED
 - TREE: NEW PROPOSED
 - SHRUB: NEW PROPOSED
- SYMBOLS**
- DIRECTIONAL ARROWS
 - BUILDING ACCESS
 - BUILDING EGRESS
 - SIAMESE CONNECTION
 - UTILITY POLE
 - FIRE HYDRANT
 - CATCH BASIN / MANHOLE
 - DEPRESSED CURB
 - LANDSCAPE LIGHT
 - LIGHT POLE
 - WALL MOUNTED LIGHT
 - EXISTING GRADE ELEVATION
 - PROPOSED GRADE ELEVATION
 - LOT CORNERS
 - BIKE PARKING
 - CAR PARKING
 - BF PARKING
 - BF PARKING (TYPE A)
 - BF PARKING (TYPE B)
- PARKING**
- BIKE PARKING: H: HORIZONTAL 0.6M x 1.8M, V: VERTICAL 0.5M x 1.5M, S: STACKED 0.37M x 1.8M
 - CAR PARKING: R: RESIDENTIAL, V: VISITOR
 - BF PARKING: R: RESIDENTIAL, V: VISITOR
 - BF PARKING (TYPE A): R: RESIDENTIAL, V: VISITOR
 - BF PARKING (TYPE B): R: RESIDENTIAL, V: VISITOR