



ADDITIONAL GEOTECHNICAL INVESTIGATION

**Wateridge Village - Phase 4, Block 6
Ottawa, Ontario**

REPORT

Revision 1

October 1, 2024

Terrapex Environmental Ltd.
90 Scarsdale Road
Toronto, Ontario, M3B 2R7
Telephone: (416) 245-0011
Email: toronto@terrapex.com
Website: www.terrapex.com

DISTRIBUTION: Rohit Communities

PROJECT # CO947.00

TABLE OF CONTENTS

1.	INTRODUCTION	1
2.	FIELD WORK AND LABORATORY WORK.....	1
2.1	FIELD WORK	1
2.2	GEOTECHNICAL LABORATORY TESTS	3
2.3	INFILTRATION TESTING.....	3
3.	SITE AND SUBSURFACE CONDITONS	3
3.1	SITE DESCRIPTION	4
3.2	SUBSURFACE SOIL CONDITIONS	4
3.3	BEDROCK CONDITIONS.....	5
3.4	GROUNDWATER CONDITIONS.....	5
4.	SOIL INFILTRATION, CORROSIVITY AND CBR TEST RESULTS	6
4.1	SOIL INFILTRATION TEST RESULTS	6
4.2	TEST RESULTS OF SOIL CORROSION POTENTIAL	6
4.3	CALIFORNIA BEARING RATIO TEST	7
5.	DISCUSSION AND RECOMMENDATIONS	7
5.1	SITE GRADING	7
5.2	FOUNDATION DESIGN	8
5.3	CONCRETE SLAB-ON-GRADE	9
5.4	EXCAVATION, BACKFILL AND GROUNDWATER CONTROL	9
5.5	LATERAL EARTH PRESSURE	10
5.6	EARTHQUAKE DESIGN PARAMETERS	11
5.7	PAVEMENT DESIGN	11
	5.7.1 On-Grade Construction.....	11
	5.7.2 Above Parking Garage Roof.....	13
6.	LIMITATIONS OF REPORT.....	13

APPENDICES

Appendix A	Borehole Location Plan
Appendix B	Borehole Log Sheets
Appendix C	Geotechnical Laboratory Test Results
Appendix D	Certificate of Chemical Analysis
Appendix E	Field Infiltration Test Results
Appendix F	California Bearing Ratio Test Results

1. INTRODUCTION

Terrapex Environmental Ltd. (Terrapex) has been retained by Rohit Communities to carry out an additional geotechnical investigation for the proposed development located at 1076 Hemlock Private, Wateridge Community Phase 4 (the Site), in the City of Ottawa, Ontario. Authorization to proceed with this study was given by Mr. John Hebert of Rohit Communities.

We understand that Rohit Communities is seeking approval to develop the land at Wateridge Village referred to as Phase 4 including Block 4 with mid-rise residential apartment dwelling and, Block 5 and Block 6 with low-rise residential apartment dwelling. According to the Site Plan provided to Terrapex by Client on January 19, 2024, the Site is scheduled for a mixed-use residential development which would include the following:

- Block 4 will contain mid-rise residential apartment dwelling (Building D, six storeys with one level of underground parking garage).
- Block 5 will contain low-rise residential apartment dwelling (Building A, four storeys with one level of underground parking garage).
- Block 6 will contain two low-rise residential apartment dwellings (Building B and Building C, four storeys with one level of underground parking garage).

Geotechnical investigations have been conducted at the Site previously and the most recent geotechnical investigation report prepared by Terrapex dated February 5, 2019, with a Title of ***Geotechnical Investigation Report, Proposed Mixed-Use Development, Phase 2A & 2B, Wateridge Village, Ottawa, Ontario*** was reviewed. The relevant soil and groundwater information from this previous investigation are presented in this report.

The purpose of this investigation was to characterize the underlying soil and groundwater conditions and to provide recommendations for the detailed design of the proposed development. This report will provide findings from the geotechnical investigation and engineering recommendations for the design and construction of the proposed development at Block 6. The work carried out for Block 4 and Block 5 are reported under separate covers.

This report presents the results of the investigation performed in accordance with the general terms of reference outlined above and is intended for the guidance of the owner and the design architects or engineers only. It is assumed that the design will be in accordance with the applicable building codes and standards.

2. FIELD WORK AND LABORATORY WORK

2.1 FIELD WORK

The fieldwork for this study was carried out on November 8 to 11 and November 19, 2023. It consisted of seven (7) boreholes advanced by a drilling contractor commissioned by Terrapex

utilizing track-mounted drilling equipment. The boreholes are designated as BH/MW6-1, BH6-2, BH/MW6-3, BH6-4 to BH6-5, BH/MW6-6 and BH6-7, advanced to depths ranging from 1.1 to 4.7 m below ground (mbg). Monitoring wells were installed in BH/MW6-1, BH/MW6-3 and BH/MW6-6 for long-term monitoring of the groundwater level. Data loggers were installed in the monitoring wells for real time monitoring of the groundwater level. The location of the boreholes and monitoring wells, together with the boreholes drilled in previous investigation (BH110 and TP205) are presented in Figure 1 of Appendix A.

Standard penetration tests were carried out in the course of advancing the boreholes through the overburden soils to take representative soil samples and to measure penetration index values (N-values) to characterize the condition of the various soil materials. The number of blows of the striking hammer required to drive the split spoon sampler through 300 mm depth increments was recorded and these are presented on the logs in Appendix B as penetration index values.

Bedrock was encountered at depths of 0.7 mbg to 3.0 mbg at all borehole and monitoring well locations, except for BH110. Bedrock was cored from 2.2 mbg to 4.6 mbg in BH/MW6-1, from 1.3 mbg to 4.6 mbg in BH/MW6-3, and from 2.3 mbg to 4.6 mbg in BH/MW6-1 for monitoring well installation.

One Test Pit (TP205) was excavated during the investigation carried out in 2018 to a depth of 1.6 mbg in Block 6. One (1) borehole (BH110) was drilled within Block 6 during the investigation carried out in 2018 to a depth of 1.3 mbg.

Groundwater level observations were made during and upon completion of the borehole drilling, where applicable, as well as in the installed monitoring wells.

The location and ground surface elevation at the locations of the boreholes and monitoring wells were established utilizing a TopCon HiPer V GNSS Receiver referenced to UTM Zone 18T (NAD83) and presented in the attached Borehole Location Plan in Appendix A of this report. The information of the drilled boreholes and installed monitoring wells is summarized in Table 1.

Table 1: Summary of Borehole Information

Borehole No.	Northing (m)	Easting (m)	Ground Elevation (m)	Depth of Borehole (m)	Depth of Monitoring Well (m)
BH/MW6-1	5033727.08	450070.46	82.82	4.7	4.7
BH6-2	5033694.44	450105.97	84.19	1.2	N/A
BH/MW6-3	5033677.45	450119.58	85.70	4.6	4.6
BH6-4	5033626.16	450118.00	87.36	3.0	N/A
BH6-5	5033612.15	450146.62	87.34	3.0	N/A
BH/MW6-6	5033580.10	450125.25	85.87	4.6	4.6
BH6-7	5033564.86	450163.18	86.75	1.8	N/A
BH110	5033554	450130	86.37	1.3	N/A
TP205	5033606	450123	85.81	1.6	N/A

The fieldwork for this project was carried out under the supervision of an experienced technician from this office who laid out the positions of the boreholes in the field; arranged locates of buried

services; effected the drilling, sampling and in situ testing; observed groundwater conditions; and prepared field borehole log sheets.

2.2 GEOTECHNICAL LABORATORY TESTS

The soil samples recovered from the split spoon sampler were properly sealed, labelled and brought to Terrapex's Toronto laboratory for detailed examination. Each soil sample was examined in the laboratory for visual and textural characteristics by the Project Engineer. Moisture content determinations were carried out on all recovered soil samples. The results are plotted on the borehole logs attached in Appendix B.

Five (5) grain size analyses and two (2) Atterberg Limits tests were performed on selected soil samples. The geotechnical laboratory results are provided in Appendix C of this report as well as presented on the respective borehole logs provided in Appendix B. One combined subgrade soil sample obtained from the location of Inf 6-1 was subjected to California Bearing Ratio (CBR) test and the results are presented in Appendix F of this Report.

In addition, two (2) soil samples, BH6-5-SS2 and BH/MW6-2-SS3 were submitted to AGAT Laboratories for determination of pH and sulphate content and their potential for sulphate attack on buried concrete. The results of the tests are enclosed in Appendix E and will be discussed in Section 4.2 of this report.

2.3 INFILTRATION TESTING

Soil infiltration rate testing was carried out in unsaturated soils at locations labeled as Inf6-1 through Inf6-4, as shown in Figure 2 of Appendix A. The field tests were carried out on November 16 and November 20 of 2023. Soils were pre-soaked and then a falling head test was conducted by adding a volume of water into a select soil horizon, and monitoring the rate that it was accepted into the soil. Depending upon the target depth, the water was introduced into the select soil horizon via the screened horizon of a drive-point piezometer, or by introducing a volume of water to the soil using a Pask Permeameter instrument. An electronic sounding tape was used to measure the steady-state flow rate of gravimetrically-fed water into the unsaturated soil horizon. The results of the infiltration test are presented in Appendix D of this report and will be discussed in Section 4.1 of this report.

3. SITE AND SUBSURFACE CONDITONS

Full details of the subsurface soil and groundwater conditions at the site are given on the Borehole Log Sheets attached in Appendix B of this report. The following paragraphs present a description of the site and a commentary on the engineering properties of the various soil materials contacted in the boreholes.

It should be noted that the boundaries of soil types indicated on the borehole logs are inferred from non-continuous soil sampling and observations made during drilling. These boundaries are intended to reflect transition zones for the purpose of geotechnical design, and therefore, should not be construed as exact planes of geological change.

3.1 SITE DESCRIPTION

The subject site is located at the former CFB Rockcliffe property in the City of Ottawa. The former CFB Rockcliffe property is approximately 310 acres; bounded by Aviation Parkway to the west, Sir George Etienne Cartier Parkway to the North, the National Research Council of Canada campus to the east, and existing residential communities and Montfort Hospital to the south. It is bounded by two bedrock escarpments at the south and north boundaries. The Rockcliffe Airport is also located in the vicinity of the site, just north of Sir George Etienne Cartier Parkway.

Our investigation was limited to Phase 4 and the work carried out for Block 6 was bounded by Kijigong Street from the south, future private driveway from the north, future private driveway from the west and future Oshedinaa Street from the east. The ground surface topography of the site is uneven. The ground surface elevations at the locations of the boreholes vary from 82.8 m to 87.3 m.

3.2 SUBSURFACE SOIL CONDITIONS

In general, the subsurface at the site consists of fill material overlying bedrock.

Fill: Fill material consisting of gravelly sand, sandy silt to silty clay was encountered at all borehole locations, extending to depths varying from 0.7 mbg to 3.0 mbg. The fill material is generally presented in a loose to very dense state (soft to hard for silty clay), with the recorded SPT “N” values varying from 2 to over 50 blows per 300 mm penetration. The moisture content of the fill material ranges between 3% and 38%.

Grain size analyses for five (5) selected soil samples and Atterberg Limits test of one (1) soil samples of the fill material was conducted and the results are presented in Appendix C of this report and summarized in Table 2:

Table 2: Grain size Analyses Results (Fill)

Borehole No.	Sample No.	Grain size Analyses Distribution (%)				Atterberg Limits Test (%)		
		Gravel	Sand	Silt	Clay	LL	PL	PI
BH/MW6-1	SS1A	9	21	27	43	N/A		
BH/MW6-1	SS1B	29	38	23	10	N/A		
BH6-4	SS1	6	8	25	61	58	30	28
BH6-5	SS2	7	7	25	61	N/A		
BH6-6	SS3	18	33	36	13	N/A		

3.3 BEDROCK CONDITIONS

Bedrock was encountered at depths of 0.7 mbg to 3.0 mbg at all borehole and monitoring well locations, except for BH110, corresponding to a geodetic elevation of 80.7 m to 85.1 m. At the location of BH/MW6-1, BH/MW6-3 and BH/MW6-6, the bedrock was proven by rock coring to a depth of 4.6 mbg. The bedrock was also proven by excavation/augering at the other borehole/test pit locations. The approximate depth and geodetic elevation of the bedrock surface at each borehole/test pit location is provided in Table 3.

Table 3: Summary of Bedrock Information

Borehole No.	Depth of Bedrock Surface (m)	Elevation of Bedrock Surface (m)	Note
BH/MW6-1	2.1	80.7	Cored
BH6-2	0.7	83.5	Augered
BH/MW6-3	1.3	84.3	Cored
BH6-4	3.0	84.4	Augered
BH6-5	2.8	84.5	Augered
BH/MW6-6	2.3	83.6	Cored
BH6-7	1.7	85.1	Augered
BH110	N/A	N/A	N/A
TP205	1.6	84.2	Excavated

The bedrock surface should not be considered accurate to better than ± 0.5 m and some variations in the bedrock surface elevation across the site should be expected.

Review of available geological mapping and previous geotechnical investigations indicates that the bedrock is of the Ottawa Formation, consisting of limestone with some shale bedding and some sandstone in the basal part. In BH/MW6-1, BH/MW6-3 and BH/MW6-6, the bedrock was cored from 2.1 m to 4.6 m, from 1.3 m to 4.6 m and from 2.3 m to 4.6 m, respectively. Total Core Recovery (TCR) achieved with the HQ double tube size core bit is 100% and the Rock Quality Designation (RQD) varied from 15% to 84%, which indicate very poor to good quality of bedrock. According to the previous investigations at the site, the rock is classified to be strong to very strong.

3.4 GROUNDWATER CONDITIONS

The groundwater table was measured in the installed monitoring wells on November 24, 2023. The groundwater table measured in the monitoring wells were at depths of 3.67 to 4.30 m, corresponding to elevations of 78.5 m to 82.2 m. The measured groundwater levels are provided in Table 4.

Table 4: Groundwater levels observed in Monitoring Wells

Borehole No.	Ground Elevation (m)	Depth of Well (m)	Date of Reading	Depth of Groundwater (mbg)	Groundwater Elevation (m)
BH/MW6-1	82.82	4.6	11/24/2023	4.3	78.52
BH/MW6-3	85.70	4.6	11/24/2023	--	--
BH/MW6-6	85.87	4.6	11/24/2023	3.67	82.2

More information of the groundwater will be provided after downloading the data from the data loggers.

It should be noted that the groundwater levels can vary and are subject to seasonal fluctuations in response to major weather events.

4. SOIL INFILTRATION, CORROSIVITY AND CBR TEST RESULTS

4.1 SOIL INFILTRATION TEST RESULTS

Field-saturated hydraulic conductivity, (Kfs) was calculated from the measurements using following equation (Elrick et. al., 1989):

$$K_{fs} = \frac{C_1 Q_1}{2\pi(H_1)^2 + \pi a^2 C_1 + 2\pi \left(\frac{H_1}{\alpha^*}\right)}$$

Where:

Kfs =Field saturated hydraulic conductivity (entrapped air present) (cm/sec)

C₁ = Shape factor

Q₁ = flow rate (cm³/s)

H₁ = Well height (cm)

a = Well radius (cm)

α* = alpha factor (0.15 cm⁻¹)

The field measurement data and analysis of the infiltration rate testing are provided in Appendix D. Based on the resulting Kfs (cm/s), the corresponding infiltration rates (mm/hr) were estimated using the covariable relationship presented in the Low Impact Development Stormwater Management Planning and Design Guide (TRCA and CVCA, 2010). A summary of the infiltration rate testing results is presented below in Table 5.

Table 5: Summary of Infiltration Tests

Location Tested	Measured Kfs (cm/s)	Measured Infiltration Rate (mm/hr)	factor of safety	Design Infiltration Rate(mm/hr)
INF6-1	8.00E-05	3.00E-04	62	2.5
INF6-2	2.00E-04	2.00E-05	36	2.5
INF-6-3	1.00E-05	4.00E-04	65	2.5

4.2 TEST RESULTS OF SOIL CORROSION POTENTIAL

Two (2) bulk soil samples collected during the investigation were submitted for corrosion potential tests. The test results are listed in Table 6 and a detail report is presented in in Appendix E of this report.

Table 6: Summary of Soil Corrosivity Tests

SAMPLE ID	PH	SULPHATE (µg/g)
BH6-5 SS2	7.88	38
BH/MW6-6 SS3	8.09	37

The pH of the tested sample indicates a moderate alkalinity. The concentration of water-soluble sulphate content of the tested samples is below the CSA Standard of 0.1% water- soluble sulphate (Table 3 of CSA A23.1/CSA A23.2, Additional Requirement for Concrete Subjected to Sulphate Attack). Special concrete mixes against sulphate attack are therefore not required for the sub-surface concrete. Kg/m³

4.3 CALIFORNIA BEARING RATIO TEST

One (1) composite sample from the top 1.5 m of the borehole (Inf6-1) was collected at the time of Infiltration test for CBR testing. Proctor test was also performed on the same sample. The results of the test are presented in Appendix C of this report. A summary of the test results is provided in Table 7.

Table 7: Summary of CBR Test

SAMPLE ID	PENETRATION (mm)	CORRECTED STRESS (MPa, after soaking)	BEARING RATIO (%)	MOISTURE AT PENETRATION POINT (%)	MAXIMUM DRY DENSITY (Kg/m3)
INF6-1	2.5	1.10	15.94	10.03	2091
	5.0	2.45	23.79		

5. DISCUSSION AND RECOMMENDATIONS

In this section, the subsurface conditions are interpreted as relevant to the design of the proposed two four-storey building with one level of underground parking garage.

The construction methods described in this report must not be considered as being specifications or recommendations to the prospective contractors, or as being the only suitable methods. Prospective contractors should evaluate all of the factual information, obtain additional subsurface information as they might deem necessary and should select their construction methods, sequencing and equipment based on their own experience in similar ground conditions. The readers of this report are also reminded that the conditions are known only at the borehole locations and in view of the generally wide spacing of the boreholes, conditions may vary significantly between boreholes.

5.1 SITE GRADING

Based on the proposed “Grading Plan”, Sheet Number C-200, prepared by Arcadis, dated September 25, 2024, and the architectural drawings prepared by NORR Architects & Engineers

Limited, dated September 25, 2024, provided to Terrapex by the Client, it is understood that the underground parking will cover the majority of the site, except for the south of Building C, and southwest corner of Building B. The finished grade in areas which are outside the footprint of the underground parking varies from 85.1 masl to 88.15 masl. According to the elevations surveyed at the borehole locations, the existing topographic elevation within the above area varies from 85.9 masl to 87.4 masl. As such, the proposed grade change is -0.8 m (cut) to 0.7 m (fill).

Prior to carrying out any area grading of the site, the existing fill material should be removed from both cut and fill areas. The exposed subgrade should be inspected by a qualified geotechnical engineer prior to any fill material placement. Fill material should be placed in maximum 300 mm thick lifts and compact to minimum 98% of the SPMDD of the material. If the fill material is used as an engineered fill then must be compacted to 100% of the SPMDD.

5.2 FOUNDATION DESIGN

According to the Site plan provided to Terrapex by Client (Preliminary Site Plan prepared by NORR/Rohit dated May 26, 2023), the proposed buildings on Block 6 will be developed into two low-rise residential apartment dwellings (Building B and Building C, four storeys with one level of underground parking garage). The finished floor elevation at the P1 parking for apartment building was not known to Terrapex at the time of preparing this report but can be assumed at ± 3 m below existing ground for apartment building. The foundation will be about 0.5 to 1.0 m below the finished floor.

The proposed four-storeys building with one level underground parking can be supported by spread and strip footings founded on bedrock minimum 1.0 m below the bedrock surface for a factored bearing resistance at Ultimate Limit States of 1 MPa (ULS).

Foundations designed to the specified bearing capacity stated above are expected to settle less than 25 mm total and 19 mm differential.

Where it is necessary to place footings on bedrock at different levels, the upper footing must be founded below an imaginary 1 horizontal to 1 vertical line (1H:1V in bedrock) drawn up from the base of the lower footing. The lower footing must be installed first to help minimize the risk of undermining the upper footing.

The bedrock may weather rapidly between wetting and drying cycles. In view of this, it is suggested that a lean concrete mat slab be placed immediately after the excavation is complete to keep the bedrock intact, unless the footings are cast immediately after excavating.

It should be noted that the recommended bearing resistances have been calculated by Terrapex from the borehole information for the design stage only. The investigation and comments are necessarily on-going as new information of the underground conditions becomes available. For example, more specific information is available with respect to conditions between boreholes when foundation construction is underway. The interpretation between boreholes and the recommendations of this report must therefore be checked through field inspections provided by Terrapex to validate the information for use during the construction stage.

All footings exposed to seasonal freezing conditions should be provided with at least 1.8 m of earth cover or equivalent thermal insulation against frost.

5.3 CONCRETE SLAB-ON-GRADE

Based on the borehole information, the basement floor slab for apartment building is expected to be in the bedrock. The floor slab can be cast as slab-on-grade provided a 200 mm layer of clear crushed stone (19 mm maximum size) is placed between the underside of the floor slab and the exposed bedrock surface. A perimeter and underfloor drainage system will be required around the exterior basement walls.

5.4 EXCAVATION, BACKFILL AND GROUNDWATER CONTROL

Based on the borehole findings, excavation for foundations, basements, sewer trenches and utilities will be carried out through fill material consisting of sandy silt to clayey silt and bedrock. No significant groundwater issue is anticipated for the excavation and installation of the foundations. It is expected that any seepage, which occurs during wet periods, can be removed by strategically placed sump pumps.

Excavation of the soil strata is not expected to pose any difficulty and can be carried out with heavy hydraulic excavators. Bedrock excavation is anticipated across the site. According to the rock core data from the previous investigations, the bedrock generally consists of strong to very strong limestone with interbedded shale of variable bed thicknesses and depth across the site.

Bedrock excavation is expected to be carried out using line drilling and blasting, hoe ramming or both. Provision should be made in the excavation contract to include the use of these techniques for excavation in bedrock. Any blasting should be carried out in accordance with City of Ottawa Special Provision S.P. No: F-1201 and under the supervision of a blasting specialist engineer. Vibration monitoring of the blasting operation should be carried out to ensure that the blasting meets the limiting vibration criteria at all times.

The contractor should submit a complete and detailed blasting design and monitoring proposal prepared by a blasting/vibrations specialist prior to commencing blasting. This would have to be reviewed and accepted in relation to the requirements of the blasting specifications. Vibration monitoring of the blasting should be carried out to ensure that the blasting meets the limiting vibration criteria at all times. A pre-blast condition survey should be carried out of surrounding structures and utilities located within 100 m of the excavation site. The condition survey should also include the National Research Council's Montreal Road Campus located east of the subject site.

All excavations must be carried out in accordance with Occupational Health and Safety Act (OHSA). With respect to OHSA, the near surface fill material is expected to conform to Type 3 soils. The bedrock is classified as Type 1 soil.

Temporary excavations for slopes in Type 3 soil should not exceed 1.0 horizontal to 1.0 vertical. Excavations in the bedrock may be cut with vertical side-walls. In the event very loose and/or soft soils are encountered at shallow depths or within zones of persistent seepage, it will be necessary to flatten the side slopes as necessary to achieve stable conditions.

For excavations through multiple soil types, the side slope geometry is governed by the soil with the highest number designation. Excavation side-slopes should not be unduly left exposed to inclement weather. Excavation slopes consisting of sandy soils will be prone to gullyng in periods of wet weather, unless the slopes are properly sheeted with tarpaulins.

Where workers must enter excavations extending deeper than 1.2 m below grade, the excavation side-walls must be suitably sloped and/or braced in accordance with the Occupational Health and Safety Act and Regulations for Construction Projects.

It should be noted that the on-site fill material may contain boulders, cobbles and remnants of former buildings in the form of buried concrete. Provisions must be made in the excavation and foundation installation contracts for the removal of possible boulders and concrete.

Based on the borehole information, the existing fill is considered unsuitable for re-use as backfill material as it contains organics and other debris. Excavated native soils free from organics can be used as general construction backfill, provided their moisture content is within 2 percent of their optimum moisture contents which will require significant aeration.

Imported granular fill, which can be compacted with hand-held equipment, should be used in confined areas.

Based on observations made during drilling of the boreholes and excavation of the test pits, close examination of the soil samples extracted from the boreholes, and groundwater measurements made in the monitoring wells, significant groundwater problems are not anticipated within the presumed excavation depths throughout the site. It is expected that any seepage from wet sand seams and perched water, which occurs during wet periods, can be removed by pumping from sumps.

5.5 LATERAL EARTH PRESSURE

The lateral earth pressures acting on basement walls may be calculated from the following expression.

$$P = K (\gamma h + q)$$

Where **P** = lateral pressure in kPa acting at a depth **h** (m) below ground surface

K = lateral earth pressure coefficient, $K = 0.40$ for vertical walls in overburden and horizontal backfill; $K = 0.25$ for vertical walls in bedrock.

γ = unit weight of backfill (kN/m^3), a value of 19.5 kN/m^3 may be used for fill and 26.0 kN/m^3 for bedrock

q = the complete surcharge loading (kPa)

This equation assumes that free-draining backfill and positive drainage is provided to ensure that there is no hydrostatic pressure acting in conjunction with the earth pressure.

5.6 EARTHQUAKE DESIGN PARAMETERS

The 2012 Ontario Building Code (OBC) stipulates the methodology for earthquake design analysis, as set out in Subsection 4.1.8.7. The determination of the type of analysis is predicated on the importance of the structure, the spectral response acceleration and the site classification.

The parameters for determination of the Site Classification for Seismic Site Response are set out in Table 4.1.8.4.A of the 2012 OBC. The classification is based on the determination of the average shear wave velocity in the top 30 metres of the site stratigraphy, where shear wave velocity (v_s) measurements have been taken. In the absence of such measurements, the classification is estimated on the basis of empirical analysis of undrained shear strength or penetration resistance. The applicable penetration resistance is that which has been corrected to a rod energy efficiency of 60% of the theoretical maximum or the (N_{60}) value.

Based on the current and previous borehole and test pit information, the subsurface stratigraphy generally comprises surficial topsoil and asphaltic concrete pavement, underlain by fill material, followed by various native soils consisting of silty sand to sand, sandy silt to silt, and clay and silt soils, underlain by limestone bedrock at shallow depths. Based on the above, the site designation for seismic analysis is estimated to be Class B according to Table 4.1.8.4.A from the quoted code.

The site specific 5% damped spectral acceleration coefficients, and the peak ground acceleration factors are provided in the 2012 Ontario Building.

5.7 PAVEMENT DESIGN

5.7.1 On-Grade Construction

Based on the existing topography of the site and the proposed grades, re-grading of the subgrade will be required. It is anticipated that the sub-grade material for the pavement will generally comprise of engineered fill.

The subgrade should be thoroughly proof-rolled and re-compacted to ensure uniformity in subgrade strength and support. Lift thicknesses should not exceed 200 mm in a loose state and the excavated site material should be compacted using heavy vibratory rollers.

The recommended pavement structures provided in Table 6 are based upon an estimate of the subgrade soil properties determined from visual examination and textural classification of the soil samples. The values may need to be adjusted based on the city of Ottawa Engineering Standard. Consequently, the recommended pavement structures should be considered for preliminary design purposes only. A functional design life of eight to ten years has been used to establish the pavement recommendations. This represents the number of years to the first rehabilitation, assuming regular maintenance is carried out. If required, a more refined pavement structure design can be performed based on specific traffic data and design life requirements and will

involve specific laboratory tests to determine frost susceptibility and strength characteristics of the subgrade soils, as well as specific data input from the client.

Table 8: Recommended Asphaltic Concrete Pavement Structure Design

Pavement Layer	Compaction Requirements	Light Duty Pavement	Heavy Duty Pavement
Surface Course	as per OPSS 310	40 mm Superpave 12.5 Level B Asphalt (PG58-34)	40 mm Superpave 12.5 Level D Asphalt (PG64-34)
Binder Course	as per OPSS 310	50 mm Superpave 19 mm Level B Asphalt (PG58-34)	100 mm Superpave 19 mm Level D Asphalt (PG64-34)
Granular Base	100% SPMDD	150 mm Granular 'A' (OPSS 1010) Pit Run or 19 mm Crusher Run Limestone	150 mm Granular 'A' (OPSS 1010) Pit Run or 19 mm Crusher Run Limestone
Granular Sub-Base	100% SPMDD	450 mm Granular 'B' Type II (OPSS 1010)	600 mm Granular 'B' Type II (OPSS 1010)

The subgrade must be compacted to at least 98% of SPMDD for at least the upper 600 mm and 95% below this level. The granular base and sub-base materials should be compacted to a minimum of 100% SPMDD.

The long-term performance of the proposed pavement structure is highly dependent upon the subgrade support conditions. Stringent construction control procedures should be maintained to ensure that uniform subgrade moisture and density conditions are achieved as much as practically possible when fill is placed and that the subgrade is not disturbed and weakened after it is exposed.

Control of surface water is a significant factor in achieving good pavement life. Grading adjacent to the pavement areas must be designed so that water is not allowed to pond adjacent to the outside edges of the pavement or curb. In addition, the need for adequate drainage cannot be over-emphasized. The subgrade must be free of depressions and sloped (preferably at a minimum gradient of three percent) to provide effective drainage toward subgrade drains. Continuous sub-drains are recommended to intercept excess subsurface moisture at the curb lines and catch basins. The invert of sub-drains should be maintained at least 0.3 m below subgrade level.

Additional comments on the construction of pavement areas are as follows:

- As part of the subgrade preparation, the proposed pavement areas should be stripped of vegetation, topsoil, unsuitable earth fill and other obvious objectionable material. The subgrade should be properly shaped and sloped as required, and then proof-rolled. Loose/soft or spongy subgrade areas should be sub-excavated and replaced with suitable approved material compacted to at least 98% of SPMDD.
- Where new fill is needed to increase the grade or replace disturbed portions of the subgrade, excavated inorganic soils or similar clean imported fill materials may be used, provided their moisture content is maintained within 2 % of the soil's optimum moisture content. All fill must be placed and compacted to not less than 98% of SPMDD.
- For fine-grained soils, as encountered at the site, the degree of compaction specification

alone cannot ensure distress free subgrade. Proof-rolling must be carried out and witnessed by Terrapex personnel for final recommendations of sub-base thicknesses.

- In the event that pavement construction takes place in the spring thaw, the late fall, or following periods of significant rainfall, it should be anticipated that an increase in thickness of the granular sub-base layer will be required to compensate for reduced subgrade strength.

5.7.2 Above Parking Garage Roof

The pavement above the parking garage roof slab may be comprised of a minimum of 75 mm thick layer of granular 'A' topped with asphaltic concrete having a minimum thickness of 80 mm (40 mm HL8 and 40 mm HL3). The asphaltic concrete materials should be rolled and compacted in accordance with OPSS 310 requirements.

The gradation and physical properties of HL-3 and HL-8 asphaltic concrete, and Granular 'A' shall conform to the OPSS standards.

The critical section of pavement will be at the transition between the pavement on grade and the pavement above the garage roof slab. In order to alleviate the detrimental effects of dynamic loading / settlement / pavement depression in the backfill to the rigid garage roof structure, it is recommended that an approach type slab be constructed at the entrance/exit points, by extending the granular sub-base to greater depths along the exterior garage wall.

The granular courses of the pavement should be placed in lifts not exceeding 150 mm thick and be compacted to a minimum of 100% SPMDD.

6. LIMITATIONS OF REPORT

The conclusion and recommendations in this report are based on information determined at the inspection locations. Soil and groundwater conditions between and beyond the test holes may differ from those encountered at the test hole locations, and conditions may become apparent during construction which could not be detected or anticipated at the time of the soil investigation. The design recommendations given in this report are applicable only to the project described in the text, and then only if constructed substantially in accordance with details of alignment and elevations stated in the report. Since all details of the design may not be known to us, in our analysis certain assumptions had to be made as set out in this report. The actual conditions may, however, vary from those assumed, in which case changes and modifications may be required to our recommendations.

This report was prepared for Rohit Communities by Terrapex Environmental Ltd. The material in it reflects Terrapex Environmental Ltd. judgement in light of the information available to it at the time of preparation. Any use which a Third Party makes of this report, or any reliance on decisions which the Third Party may make based on it, are the sole responsibility of such Third Parties.

We recommend, therefore, that Terrapex be retained during the final design stage to review the design drawings and to verify that they are consistent with Terrapex's recommendations, or the assumptions made in our analysis. We recommend also that Terrapex be retained during construction to confirm that the subsurface conditions throughout the site do not deviate materially from those encountered in the test holes. In cases when these recommendations are not followed, the company's responsibility is limited to accurately interpreting the conditions encountered at the test holes, only.


The comments given in this report on potential construction problems and possible methods are intended for the guidance of the design engineer, only. The number of inspection locations may not be sufficient to determine all the factors that may affect construction methods and costs. The contractors bidding on this project or undertaking the construction should, therefore, make their own interpretation of the factual information presented and draw their own conclusions as to how the subsurface conditions may affect their work.

Respectfully submitted,

TERRAPEX ENVIRONMENTAL



Thomas Yan., P.Eng.
Senior Geotechnical Engineer



Meysam Najari, PhD
Vice President, Geotechnical Services

APPENDIX A
Borehole Location Plan



- LEGEND**
- PROPOSED PLAN OF SUBDIVISION
 - ◆ BOREHOLE (TERRAPEX, 2023)
 - ◆ MONITORING WELL (TERRAPEX, 2023)
 - BOREHOLE (TERRAPEX, 2018)
 - ☒ TEST PIT (TERRAPEX, 2018)



DATA SOURCE: CITY OF OTTAWA
 MAP PROJECTION: NAD 1983 UTM ZONE 18N

CLIENT: **CLC**

SITE LOCATION: **WATERIDGE VILLAGE
 OTTAWA, ONTARIO**




TITLE: **GENERAL SITE LAYOUT**

DRAWN BY: JS	PROJECT NO.: CO947.00	CHECKED BY: TY
------------------------	---------------------------------	--------------------------


REVISION: 00	DATE: DECEMBER 2023	FIGURE: 1
------------------------	-------------------------------	---------------------

C:\Users\Jsereno\OneDrive - TerraPex Environmental Ltd\PROJECTS\Wateridge Village\MOI\GEO\TECHNICAL\CO947.00.FIG.2.GENERAL SITE LAYOUT.mxd

C:\Users\JSmrsl\OneDrive - TerraPex Environmental Ltd\PROJECTS\Ottawa\CO947\00\Wateridge Village\MOI\HSC\CO947\Fig. 3 INFILTRATION INVESTIGATION.mxd



- LEGEND**
- PROPOSED PLAN OF SUBDIVISION
 - ☒ INFILTRATION TESTING LOCATION
 - ◆ BOREHOLE (TERRAPEX, 2023)
 - ⊕ MONITORING WELL (TERRAPEX, 2023)
 - BEDROCK SURFACE CONTOURS



DATA SOURCE: CITY OF OTTAWA
 MAP PROJECTION: NAD 1983 UTM ZONE 18N

CLIENT:	CLC	
SITE LOCATION:	WATERIDGE VILLAGE OTTAWA, ONTARIO	
TITLE:	INFILTRATION INVESTIGATION	
DRAWN BY:	PROJECT NO.:	CHECKED BY:
JS	CO947.00	CB
REVISION:	DATE:	FIGURE:
00	NOVEMBER 2023	2

APPENDIX B
Borehole Log Sheets

CLIENT: Rohit Communities				PROJECT NO.: CO947.00				RECORD OF: BH/MW6-1								
ADDRESS: Wateridge Village / Hemlock Road Area								CITY/PROVINCE: Ottawa, ON		NORTHING (m): 5033727.08		EASTING (m): 450070.46		ELEV. (m) 82.82		
CONTRACTOR: George Downing Estate Drilling Ltd						METHOD:										
BOREHOLE DIAMETER (cm): 20			WELL DIAMETER (cm): 5			SCREEN SLOT #: 10		SAND TYPE: 2		SEALANT TYPE: Bentonite						
SAMPLE TYPE		AUGER		DRIVEN		CORING		DYNAMIC CONE		SHELBY		SPLIT SPOON				
GWL (m)	SOIL SYMBOL	SOIL DESCRIPTION		DEPTH (m)	ELEVATION (m)	SHEAR STRENGTH (kPa)		WATER CONTENT (%)		SAMPLE NO.	SAMPLE TYPE	RECOVERY (%)	SV/TOV (ppm or %LEL)	LABORATORY TESTING	WELL INSTALLATION	REMARKS
						N-VALUE (Blows/300mm)		PL W.C. LL								
		FILL stiff, grey, moist sandy silty clay, trace gravel & organics ----		0	82.5	12	20.7	16.8	20.7	1A	50					Bentonite
		Gr=8.7%, Sa=21.5%, Si=26.6%, Cl=43.2% ---- very dense, light brown, moist SILTY GRAVELLY SAND trace to some clay, rock pieces ----		0.5	82	53	10.7			1B	40					50 mm monitoring well was installed and the water level measured on November 24, 2023: 4.30 mbgs
		Gr=29.2%, Sa=37.5%, Si=23.5%, Cl=9.8% ---- Bedrock Cored to depth of 4.67 m.		1	81.5	50/125	11.5			2	100					
		TCR(1) = 100% RQD(1) = 15%		1.5	81					3						
		TCR(2) = 100% RQD(2) = 45%		2	80.5					R1						Sand
		END OF BOREHOLE		2.5	80					R2						Screen + Sand
		END OF BOREHOLE		3	79.5											END OF BOREHOLE: 4.67 mbgs ELEV.(m) = 78.1
		END OF BOREHOLE		3.5	79											
		END OF BOREHOLE		4	78.5											
		END OF BOREHOLE		4.5												



LOGGED BY: UB


DRILLING DATE: 10-11-2023


INPUT BY: RR

MONITORING DATE:

REVIEWED BY: TY

PAGE 1 OF 1

CLIENT: Rohit Communities				PROJECT NO.: CO947.00				RECORD OF: BH6-2												
ADDRESS: Wateridge Village / Hemlock Road Area																				
CITY/PROVINCE: Ottawa, ON				NORTHING (m): 5033694.44				EASTING (m): 450105.97		ELEV. (m) 84.19										
CONTRACTOR: George Downing Estate Drilling Ltd						METHOD:														
BOREHOLE DIAMETER (cm):			WELL DIAMETER (cm):			SCREEN SLOT #:		SAND TYPE:		SEALANT TYPE:										
SAMPLE TYPE		<input type="checkbox"/> AUGER		<input type="checkbox"/> DRIVEN		<input checked="" type="checkbox"/> CORING		<input type="checkbox"/> DYNAMIC CONE		<input type="checkbox"/> SHELBY		<input type="checkbox"/> SPLIT SPOON								
GWL (m)	SOIL SYMBOL	SOIL DESCRIPTION		DEPTH (m)	ELEVATION (m)	SHEAR STRENGTH (kPa)				WATER CONTENT (%)				SAMPLE NO.	SAMPLE TYPE	RECOVERY (%)	SV/TOV (ppm or %LEL)	LABORATORY TESTING	WELL INSTALLATION	REMARKS
						N-VALUE (Blows/300mm)				PL W.C. LL										
		FILL compact to dense, grey, moist sandy silty clay trace gravel, trace oxidation Bedrock Cored to depth of 1.15 m.		0	84	▲	30							1A	50					
				0.5	83.5			■	30							1B				
		END OF BOREHOLE		1										2						
																			END OF BOREHOLE: 1.15 mbgs ELEV.(m) = 83.0	
						LOGGED BY: UB				DRILLING DATE: 10-11-2023										
						INPUT BY: RR				MONITORING DATE:										
						REVIEWED BY: TY				PAGE 1 OF 1										

CLIENT: Rohit Communities				PROJECT NO.: CO947.00				RECORD OF: BH6-3						
ADDRESS: Wateridge Village / Hemlock Road Area														
CITY/PROVINCE: Ottawa, ON				NORTHING (m): 5033677.45				EASTING (m): 450119.58		ELEV. (m) 85.70				
CONTRACTOR: George Downing Estate Drilling Ltd						METHOD:								
BOREHOLE DIAMETER (cm):			WELL DIAMETER (cm):			SCREEN SLOT #:		SAND TYPE:		SEALANT TYPE:				
SAMPLE TYPE		<input type="checkbox"/> AUGER		<input type="checkbox"/> DRIVEN		<input checked="" type="checkbox"/> CORING		<input type="checkbox"/> DYNAMIC CONE		<input type="checkbox"/> SHELBY		<input type="checkbox"/> SPLIT SPOON		
GWL (m)	SOIL SYMBOL	SOIL DESCRIPTION		DEPTH (m)	SHEAR STRENGTH (kPa)				WATER CONTENT (%)				REMARKS	
					N-VALUE (Blows/300mm)				PL W.C. LL					
				ELEVATION (m)	20	40	60	80	20	40	60	80		
				0	85.5	22			24.8					
				0.5	85									
				1	84.5									
				1.5	84					R1				
				2	83.5									
				2.5	83					R2				
				3	82.5									
				3.5	82									
				4	81.5									
				4.5										
		END OF BOREHOLE											END OF BOREHOLE: 4.64 mbgs ELEV.(m) = 81.0	
									LOGGED BY: UB			DRILLING DATE: 09-11-2023		
									INPUT BY: RR			MONITORING DATE:		
									REVIEWED BY: TY			PAGE 1 OF 1		



LOGGED BY: UB


DRILLING DATE: 09-11-2023


INPUT BY: RR


MONITORING DATE:


REVIEWED BY: TY

PAGE 1 OF 1

CLIENT: Rohit Communities				PROJECT NO.: CO947.00				RECORD OF:								
ADDRESS: Wateridge Village / Hemlock Road Area								BH6-4								
CITY/PROVINCE: Ottawa, ON				NORTHING (m): 5033626.16				EASTING (m): 450118.00				ELEV. (m) 87.36				
CONTRACTOR: George Downing Estate Drilling Ltd						METHOD:										
BOREHOLE DIAMETER (cm):			WELL DIAMETER (cm):			SCREEN SLOT #:		SAND TYPE:			SEALANT TYPE:					
SAMPLE TYPE		AUGER		DRIVEN		CORING		DYNAMIC CONE		SHELBY		SPLIT SPOON				
GWL (m)	SOIL SYMBOL	SOIL DESCRIPTION		DEPTH (m)	ELEVATION (m)	SHEAR STRENGTH (kPa)		WATER CONTENT (%)		SAMPLE NO.	SAMPLE TYPE	RECOVERY (%)	SV/TOV (ppm or %LEL)	LABORATORY TESTING	WELL INSTALLATION	REMARKS
						N-VALUE (Blows/300mm)		PL W.C. LL								
		FILL soft to firm, grey, moist silty clay trace gravel, trace sand, trace organics Gr=6.0%, Sa=7.8%, Si=25.4%, Cl=60.8%. LL=58.3%, Pl=28.		0	87			29.4		1	42					
				0.5	86.5			32.1		2	33					
				1	86			34.9		3	50					
				1.5	85.5			38.1		4	50					
		END OF BOREHOLE		2	85											
				2.5												
																END OF BOREHOLE: 2.77 mbgs ELEV.(m) = 84.6
										LOGGED BY: UB			DRILLING DATE: 10-11-2023			
										INPUT BY: RR			MONITORING DATE:			
										REVIEWED BY: TY			PAGE 1 OF 1			

CLIENT: Rohit Communities				PROJECT NO.: CO947.00				RECORD OF:								
ADDRESS: Wateridge Village / Hemlock Road Area								BH6-5								
CITY/PROVINCE: Ottawa, ON			NORTHING (m): 5033612.15			EASTING (m): 450146.62			ELEV. (m) 87.34							
CONTRACTOR: George Downing Estate Drilling Ltd						METHOD:										
BOREHOLE DIAMETER (cm):		WELL DIAMETER (cm):		SCREEN SLOT #:		SAND TYPE:		SEALANT TYPE:								
SAMPLE TYPE	AUGER	DRIVEN	CORING	DYNAMIC CONE	SHELBY	SPLIT SPOON										
GWL (m)	SOIL SYMBOL	SOIL DESCRIPTION	DEPTH (m)	ELEVATION (m)	SHEAR STRENGTH (kPa)		WATER CONTENT (%)		SAMPLE NO.	SAMPLE TYPE	RECOVERY (%)	(new title)		LABORATORY TESTING	WELL INSTALLATION	REMARKS
					N-VALUE (Blows/300mm)		PL W.C. LL					SV/TOV (ppm or %LEL)				
		FILL soft, grey, moist silty clay trace gravel, trace sand, trace organics --- Gr=7.3%, Sa=7.5%, Si=24.6%, Cl=60.6% --- stiff	0 0.5 1 1.5 2 2.5 2.97	87 86.5 86 85.5 85 84.5	3 2 2 13			32.8 34.6 32.9 30.5		1 2 3 4	58 42 50 100					
		Bedrock Core to depth of 2.97 m. END OF BOREHOLE														END OF BOREHOLE: 2.97 mbgs ELEV.(m) = 84.5
								LOGGED BY: UB				DRILLING DATE: 10-11-2023				
								INPUT BY: RR				MONITORING DATE:				
								REVIEWED BY: TY				PAGE 1 OF 1				

CLIENT: Rohit Communities				PROJECT NO.: CO947.00				RECORD OF: BH/MW6-6							
ADDRESS: Wateridge Village / Hemlock Road Area															
CITY/PROVINCE: Ottawa, ON				NORTHING (m): 5033580.10		EASTING (m): 450125.25		ELEV. (m) 85.87							
CONTRACTOR: George Downing Estate Drilling Ltd				METHOD:											
BOREHOLE DIAMETER (cm): 20		WELL DIAMETER (cm): 5		SCREEN SLOT #: 10		SAND TYPE: 2		SEALANT TYPE: Bentonite							
SAMPLE TYPE	AUGER	DRIVEN	CORING	DYNAMIC CONE	SHELBY	SPLIT SPOON									
GWL (m)	SOIL SYMBOL	SOIL DESCRIPTION	DEPTH (m)	ELEVATION (m)	SHEAR STRENGTH (kPa)		WATER CONTENT (%)		SAMPLE NO.	SAMPLE TYPE	RECOVERY (%)	(new title)		WELL INSTALLATION	REMARKS
					N-VALUE (Blows/300mm)		PL W.C. LL					SV/TOV (ppm or %LEL)	LABORATORY TESTING		
		FILL loose, grey, moist sandy silt some gravel, some clay, trace organics	0 0.5 1 1.5 2 2.5 3 3.5 4 4.5	85.5 85 84.5 84 83.5 83 82.5 82 81.5	8 5 8		20.4 18.1 12.8		1 2 3	58 42 50				Bentonite 50 mm monitoring well was installed and the water level measured on November 24, 2023: 3.67 mbgs	
		Bedrock Cored to depth of 4.64 m. TCR(1) = 100% RQD(1) = 84%							R1 R2						
		END OF BOREHOLE													END OF BOREHOLE: 4.64 mbgs ELEV.(m) = 81.2
								LOGGED BY: UB				DRILLING DATE: 10-11-2023			
								INPUT BY: RR				MONITORING DATE: 24-11-2023			
								REVIEWED BY: TY				PAGE 1 OF 1			

CLIENT: Rohit Communities				PROJECT NO.: CO947.00				RECORD OF: BH6-7							
ADDRESS: Wateridge Village / Hemlock Road Area															
CITY/PROVINCE: Ottawa, ON				NORTHING (m): 5033564.86				EASTING (m): 450163.18		ELEV. (m) 86.75					
CONTRACTOR: George Downing Estate Drilling Ltd						METHOD:									
BOREHOLE DIAMETER (cm):			WELL DIAMETER (cm):			SCREEN SLOT #:		SAND TYPE:		SEALANT TYPE:					
SAMPLE TYPE		<input type="checkbox"/> AUGER		<input type="checkbox"/> DRIVEN		<input checked="" type="checkbox"/> CORING		<input type="checkbox"/> DYNAMIC CONE		<input type="checkbox"/> SHELBY		<input type="checkbox"/> SPLIT SPOON			
GWL (m)	SOIL SYMBOL	SOIL DESCRIPTION		DEPTH (m)	SHEAR STRENGTH (kPa)		WATER CONTENT (%)		SAMPLE NO.	SAMPLE TYPE	RECOVERY (%)	SV/TOV (ppm or %LEL)	LABORATORY TESTING	WELL INSTALLATION	REMARKS
					N-VALUE (Blows/300mm)		PL W.C. LL								
					40 80 120 160	20 40 60 80	20 40 60 80								
			FILL very dense, brown, moist sand and gravel some silt, trace clay	0 0.5 1 1.5	86.5	50	19.4			100					
			Bedrock Cored to depth of 1.80 m. END OF BOREHOLE		85	50/125	8.9			42					END OF BOREHOLE: 1.80 mbgs ELEV.(m) = 84.9
								LOGGED BY: UB		DRILLING DATE: 08-11-2023					
								INPUT BY: RR		MONITORING DATE:					
								REVIEWED BY: TY		PAGE 1 OF 1					

CLIENT: Canada Lands Company CLC Limited		METHOD: Hollow Stem Auger & Split Spoon		BH No.: 110							
PROJECT: Wateridge Village		PROJECT ENGINEER: VN	ELEV. (m) 86.374								
LOCATION: Rockcliffe, Ottawa		NORTHING: 5033554	EASTING: 450130	PROJECT NO.: CO682.00							
SAMPLE TYPE		AUGER	DRIVEN	CORING	DYNAMIC CONE	SHELBY	SPLIT SPOON				
GWL (m)	SOIL SYMBOL	SOIL DESCRIPTION	DEPTH (m)	ELEVATION (m)	Shear Strength (kPa) 40 80 120 160 N-Value (Blows/300mm) 20 40 60 80	Water Content (%) PL W.C. LL 20 40 60 80	SAMPLE NO.	SAMPLE TYPE	SPT (N)	Well Construction	REMARKS
		FROZEN GROUND	0	86.25							Borehole caved-in at 0.91 m bgs and dry on completion.
		very dense, damp, grey gravel, some sand (FILL)	0.25	86			1A		80		
		compact, damp to wet, brown sandy silt, some gravel, trace organics trace oxidization (FILL)	0.75	85.75			1B				
		compact to very dense, moist to wet, dark brown, silty gravel, trace sand, trace organics and rock fragments (FILL)	1.0	85.5			2A				
		END OF BOREHOLE	1.25	85.25	31		2B		31		Auger refusal at 1.40 m bgs.


CLIENT: Canada Lands Company CLC Limited			METHOD: Excavator				TP No.: 205										
PROJECT: Wateridge Village			PROJECT ENGINEER: VN		ELEV. (m) 85.810												
LOCATION: Rockcliffe, Ottawa			NORTHING: 5033606		EASTING: 450123		PROJECT NO.: CO682.00										
SAMPLE TYPE <input type="checkbox"/> AUGER <input checked="" type="checkbox"/> DRIVEN <input checked="" type="checkbox"/> CORING <input type="checkbox"/> DYNAMIC CONE <input type="checkbox"/> SHELBY <input type="checkbox"/> SPLIT SPOON																	
DEPTH (m)	INSTRUMENTATION DATA	REMARKS	Shear Strength (kPa)				Tip Resistance (kg/cm ²)				SOIL SYMBOL	SOIL DESCRIPTION	SAMPLE TYPE	SAMPLE NO.	SPT (N)	ELEVATION (m)	
			40	80	120	160	50	100	150	200							PL
0		On completion the test pit was dry and open.															85.75
0.25												moist, grey gravel some to trace sand (FILL)					85.5
0.5												damp, dark brown topsoil, trace rootlets (FILL)					85.25
0.75																	85
1																	84.75
1.25												damp, brown SANDY SILT trace clay, trace gravel					84.5
1.5		Refusal @ 1.64 m bgs on Limestone Bedrock															84.25
END OF TEST PIT																	

APPENDIX C

Geotechnical Laboratory Test Results

Particle Size Distribution Report

ASTM D422



	% +3"	% Gravel		% Sand		% Fines	
		Coarse	Fine	Silt	Clay		
○	0.0	8.7	7.6	13.9	26.6	43.2	

	LL	PL	D ₈₅	D ₆₀	D ₅₀	D ₃₀	D ₁₅	D ₁₀	C _c	C _u
○			0.5138	0.0211	0.0041					


Material Description			Test Date	USCS	NM
○ SANDY SILTY CLAY trace gravel			Dec 6/23		

Project No. CO947.00 Client: Rohit Communities Project: Wateridge Village ○ Sample Number: BH6-1 SS1A	Remarks: ○ Hydrometer Details: Sp. Grav. = 2.75(assumed); Vb=53cm ³ ; L2=13.8cm; L1=10.7cm; hs=0.16cm/Div; A=30.2cm ² ; Mass of Disp. Agent=40g/l
Terrapex	
Toronto, Ontario	
Figure 3	

Tested By: SC

Particle Size Distribution Report

ASTM D422



	% +3"	% Gravel		% Sand		% Fines	
		Coarse	Fine	Silt	Clay		
<input type="radio"/>	0.0	29.2	19.5	18.0	23.5	9.8	

	LL	PL	D ₈₅	D ₆₀	D ₅₀	D ₃₀	D ₁₅	D ₁₀	C _c	C _u
<input type="radio"/>			10.5867	0.7875	0.3832	0.0592	0.0085	0.0022	2.05	362.42


Material Description	Test Date	USCS	NM
<input type="radio"/> SILTY GRAVELLY SAND trace to some clay	Dec 6/23		

Project No. CO947.00 Client: Rohit Communities Project: Wateridge Village <input type="radio"/> Sample Number: BH6-1 SS1B	Remarks: <input type="radio"/> Hydrometer Details: Spc. Grav. = 2.75(assumed); Vb=53cm ³ ; L2=13.8cm; L1=10.7cm; hs=0.16cm/Div; A=30.2cm ² ; Mass of Disp. Agent=40g/l
Terrapex Toronto, Ontario	Figure 4

Tested By: SC

Particle Size Distribution Report

ASTM D422



	% +3"	% Gravel		% Sand		% Fines	
		Coarse	Fine	Silt	Clay		
○	0.0	6.0	2.3	5.5	25.4	60.8	

	LL	PL	D ₈₅	D ₆₀	D ₅₀	D ₃₀	D ₁₅	D ₁₀	C _c	C _u
○	58.3	30.2	0.0519	0.0019						


Material Description		Test Date	USCS	NM
○ SILTY CLAY trace sand trace gravel		Dec 6/23	CH	

Project No. CO947.00 Client: Rohit Communities Project: Wateridge Village ○ Sample Number: BH6-4 SS1	Remarks: ○ Hydrometer Details: Sp. Grav. = 2.75(assumed); Vb=53cm ³ ; L2=13.8cm; L1=10.7cm; hs=0.16cm/Div; A=30.2cm ² ; Mass of Disp. Agent=40g/l
Terrapex Toronto, Ontario	
Figure 5	

Tested By: SC

Particle Size Distribution Report

ASTM D422



	% +3"	% Gravel		% Sand		% Fines	
		Coarse	Fine	Silt	Clay		
<input type="radio"/>	0.0	7.3		3.0	4.5	24.6	60.6

	LL	PL	D ₈₅	D ₆₀	D ₅₀	D ₃₀	D ₁₅	D ₁₀	C _c	C _u
<input type="radio"/>			0.0700	0.0019						


Material Description	Test Date	USCS	NM
<input type="radio"/> SILTY CLAY trace sand trace gravel	Dec 6/23		

Project No. CO947.00 Client: Rohit Communities Project: Wateridge Village <input type="radio"/> Sample Number: BH6-5 SS2	Remarks: <input type="radio"/> Hydrometer Details: Spc. Grav. = 2.75(assumed); Vb=53cm ³ ; L2=13.8cm; L1=10.7cm; hs= 0.16cm/Div; A=30.2cm ² ; Mass of Disp. Agent=40g/l
Terrapex Toronto, Ontario	Figure 6

Tested By: SC

Particle Size Distribution Report

ASTM D422



	% +3"	% Gravel		% Sand		% Fines	
		Coarse	Fine	Silt	Clay		
<input type="radio"/>	0.0	12.1	21.1	36.3	12.7		


	LL	PL	D ₈₅	D ₆₀	D ₅₀	D ₃₀	D ₁₅	D ₁₀	C _c	C _u
<input type="radio"/>			2.8934	0.1598	0.0798	0.0228	0.0035			

Material Description	Test Date	USCS	NM
<input type="radio"/> SANDY SILT some gravel some clay	Dec 6/23		

Project No. CO947.00 Client: Rohit Communities Project: Wateridge Village <input type="radio"/> Sample Number: BH6-6 SS3	Remarks: <input type="radio"/> Hydrometer Details: Spc. Grav. = 2.75(assumed); Vb=53cm ³ ; L2=13.8cm; L1=10.7cm; hs= 0.16cm/Div; A=30.2cm ² ; Mass of Disp. Agent=40g/l
Terrapex Toronto, Ontario	Figure 7

Tested By: SC

LIQUID AND PLASTIC LIMITS TEST REPORT



	MATERIAL DESCRIPTION	LL	PL	PI	%<#40	%<#200	USCS
●	SILTY CLAY trace sand trace gravel	58.3	30.2	28.1	91.7	86.2	CH

Project No. CO947.00 Client: Rohit Communities
 Project: Wateridge Village
 ● Sample Number: BH6-4 SS1

Terrapex
 Toronto, Ontario

Remarks:
 ● Test Date: December 11, 2023

APPENDIX D
Certificate of Chemical Analysis

CLIENT NAME: TERRAPEX ENVIRONMENTAL LIMITED
90 SCARSDALE RD
TORONTO, ON M3B2R7
(905) 474-5265
ATTENTION TO: Reza Rafiee
PROJECT: CO947.00
AGAT WORK ORDER: 23T101726
SOIL ANALYSIS REVIEWED BY: Nivine Basily, Inorganic Team Lead
DATE REPORTED: Dec 12, 2023
PAGES (INCLUDING COVER): 6
VERSION*: 1

Should you require any information regarding this analysis please contact your client services representative at (905) 712-5100

*Notes

Disclaimer:

- *All work conducted herein has been done using accepted standard protocols, and generally accepted practices and methods. AGAT test methods may incorporate modifications from the specified reference methods to improve performance.*
- *All samples will be disposed of within 30 days after receipt unless a Long Term Storage Agreement is signed and returned. Some specialty analysis may be exempt, please contact your Client Project Manager for details.*
- *AGAT's liability in connection with any delay, performance or non-performance of these services is only to the Client and does not extend to any other third party. Unless expressly agreed otherwise in writing, AGAT's liability is limited to the actual cost of the specific analysis or analyses included in the services.*
- *This Certificate shall not be reproduced except in full, without the written approval of the laboratory.*
- *The test results reported herewith relate only to the samples as received by the laboratory.*
- *Application of guidelines is provided "as is" without warranty of any kind, either expressed or implied, including, but not limited to, warranties of merchantability, fitness for a particular purpose, or non-infringement. AGAT assumes no responsibility for any errors or omissions in the guidelines contained in this document.*
- *All reportable information as specified by ISO/IEC 17025:2017 is available from AGAT Laboratories upon request.*
- *For environmental samples in the Province of Quebec: The analysis is performed on and results apply to samples as received. A temperature above 6°C upon receipt, as indicated in the Sample Reception Notification (SRN), could indicate the integrity of the samples has been compromised if the delay between sampling and submission to the laboratory could not be minimized.*



Certificate of Analysis

AGAT WORK ORDER: 23T101726

PROJECT: CO947.00

5835 COOPERS AVENUE
 MISSISSAUGA, ONTARIO
 CANADA L4Z 1Y2
 TEL (905)712-5100
 FAX (905)712-5122
<http://www.agatlabs.com>

CLIENT NAME: TERRAPEX ENVIRONMENTAL LIMITED

ATTENTION TO: Reza Rafiee

SAMPLING SITE: WATERIDGE VILLAGE

SAMPLED BY: UB/JM

(Soil) pH and Sulphate in Soil

DATE RECEIVED: 2023-12-07

DATE REPORTED: 2023-12-12

		SAMPLE DESCRIPTION: BH4-2-SS1&2		BH5-1-SS2&3		BH6-5-SS2		BH6-6-SS3	
		SAMPLE TYPE: Soil		Soil		Soil		Soil	
		DATE SAMPLED: 2023-11-08		2023-11-08		2023-11-10		2023-11-10	
		08:50		12:50		09:40		10:25	
Parameter	Unit	G / S	RDL	5525935	5525936	5525937	5525938		
Sulphate (2:1)	µg/g		2	31	36	38	37		
pH (2:1)	pH Units		NA	7.97	8.64	7.88	8.09		

Comments: RDL - Reported Detection Limit; G / S - Guideline / Standard

5525935-5525938 pH and Sulphate were determined on the extract obtained from the 2:1 leaching procedure (2 parts DI water: 1 part soil).

Analysis performed at AGAT Toronto (unless marked by *)

Certified By:



Nvine Basly

Quality Assurance

 CLIENT NAME: TERRAPEX ENVIRONMENTAL LIMITED
 PROJECT: CO947.00
 SAMPLING SITE: WATERIDGE VILLAGE

 AGAT WORK ORDER: 23T101726
 ATTENTION TO: Reza Rafiee
 SAMPLED BY: UB/JM

Soil Analysis

RPT Date: Dec 12, 2023			DUPLICATE			Method Blank	REFERENCE MATERIAL			METHOD BLANK SPIKE			MATRIX SPIKE		
PARAMETER	Batch	Sample Id	Dup #1	Dup #2	RPD		Measured Value	Acceptable Limits		Recovery	Acceptable Limits		Recovery	Acceptable Limits	
								Lower	Upper		Lower	Upper		Lower	Upper

(Soil) pH and Sulphate in Soil

Sulphate (2:1)	5517672	1100	1110	0.9%	< 2	94%	70%	130%	95%	80%	120%	NA	70%	130%
pH (2:1)	5525010	7.68	7.61	0.9%	NA	96%	80%	120%						

Comments: NA signifies Not Applicable.
 pH duplicates QA acceptance criteria was met relative as stated in Table 5-15 of Analytical Protocol document.

Duplicate NA: results are under 5X the RDL and will not be calculated.

Certified By:





Time Markers

AGAT WORK ORDER: 23T101726

PROJECT: CO947.00

5835 COOPERS AVENUE
 MISSISSAUGA, ONTARIO
 CANADA L4Z 1Y2
 TEL (905)712-5100
 FAX (905)712-5122
<http://www.agatlabs.com>

CLIENT NAME: TERRAPEX ENVIRONMENTAL LIMITED

ATTENTION TO: Reza Rafiee

Sample ID	Sample Description	Sample Type	Date Sampled	Date Received
5525935	BH4-2-SS1&2	Soil	08-NOV-2023	07-DEC-2023

(Soil) pH and Sulphate in Soil

Parameter	Date Prepared	Date Analyzed	Initials
Sulphate (2:1)	08-DEC-2023	08-DEC-2023	LC
pH (2:1)	08-DEC-2023	08-DEC-2023	XL

5525936	BH5-1-SS2&3	Soil	08-NOV-2023	07-DEC-2023
---------	-------------	------	-------------	-------------

(Soil) pH and Sulphate in Soil

Parameter	Date Prepared	Date Analyzed	Initials
Sulphate (2:1)	08-DEC-2023	08-DEC-2023	LC
pH (2:1)	08-DEC-2023	08-DEC-2023	XL

5525937	BH6-5-SS2	Soil	10-NOV-2023	07-DEC-2023
---------	-----------	------	-------------	-------------

(Soil) pH and Sulphate in Soil

Parameter	Date Prepared	Date Analyzed	Initials
Sulphate (2:1)	08-DEC-2023	08-DEC-2023	LC
pH (2:1)	08-DEC-2023	08-DEC-2023	XL

5525938	BH6-6-SS3	Soil	10-NOV-2023	07-DEC-2023
---------	-----------	------	-------------	-------------

(Soil) pH and Sulphate in Soil

Parameter	Date Prepared	Date Analyzed	Initials
Sulphate (2:1)	08-DEC-2023	08-DEC-2023	LC
pH (2:1)	08-DEC-2023	08-DEC-2023	XL



Method Summary

CLIENT NAME: TERRAPEX ENVIRONMENTAL LIMITED

AGAT WORK ORDER: 23T101726

PROJECT: CO947.00

ATTENTION TO: Reza Rafiee

SAMPLING SITE: WATERIDGE VILLAGE

SAMPLED BY: UB/JM

PARAMETER	AGAT S.O.P	LITERATURE REFERENCE	ANALYTICAL TECHNIQUE
Soil Analysis			
Sulphate (2:1)	INOR-93-6004	modified from SM 4110 B	ION CHROMATOGRAPH
pH (2:1)	INOR 93-6031	modified from EPA 9045D and MCKEAGUE 3.11	PH METER


APPENDIX E

Field Infiltration Test Results

Constant Head Well Permeameter Test Report



Project: Rohit Wateridge Village
 Project Number: CO947
 Location Name: Inf 6-1
 Approximate Location: 450090.093 easting (metres)
 5033652.523 northing (metres)
 Approximate Depth Tested: 0.4 mbg
 85.0 masl



Field Measurements:

Elapsed Time (min)	Water Level (cm)	Water Level Change (cm)	Infiltration (cm/min)	Soil Description
0.17	39.6	-	-	moist sandy silty clay
0.50	38.5	1.10	3.30	
0.67	38.5	0.00	0.00	
0.83	38.5	0.00	0.00	
1.17	38.3	0.20	0.60	
1.67	37.6	0.70	1.40	
1.83	37.6	0.00	0.00	
2.00	37.5	0.10	0.60	
2.50	36.9	0.60	1.20	
3.00	35.5	1.40	2.80	
3.50	36.2	0.70	1.40	
4.00	35.6	0.60	1.20	
4.50	35.4	0.20	0.40	
5.00	35.2	0.20	0.40	
6.00	34.2	1.00	1.00	
7.00	33.1	1.10	1.10	
8.00	32.4	0.70	0.70	
9.00	31.9	0.50	0.50	
10.00	31.3	0.60	0.60	
15	26.8	4.50	0.90	
20	19.4	7.40	1.48	
25.00	13.6	5.80	1.16	
30.00	11.8	1.80	0.36	
35.00	7.5	4.30	0.86	
40.00	1.7	5.80	1.16	

Test Conditions:

Instrument: 1" stainless steel Solinst Drivepoint Instrument
 hole radius (a) = 6 cm
 Water column height in hole (H₁) = 5 cm
 Ambient Air Temperature at Testing = 4 °C

Interpretations:

Soil Capillary Type = Strong
 Soil Type Coefficient (α*) = 0.04 cm⁻¹
 Average Water Level Change (R₁) = 0.01 cm/s
 Steady Intake Water Rate (Q₁) = 0.50 cm³/s
 Shape factor for H₁/a = (C₁) = 0.54 -

Field Saturated Hydraulic Conductivity (K_{fs}):

K_{fs} = 3E-04 cm/s
 K_{fs} corrected to 4°C ('freshet')¹ = 3E-04 cm/s
 K_{fs} corrected to 24°C ('summer')¹ = 5E-04 cm/s


Date of Field Measurements: 20-Nov-23
 Field Representative: EB
 Reviewed: ZK
 Reviewed: ZK

¹ (Streeter and Wylie, 1975)
¹ (Reynolds, 2008 and 2015)

Constant Head Well Permeameter Test Report



Project: Rohit Wateridge Village
 Project Number: CO947
 Location Name: Inf 6-2
 Approximate Location: 450101.874 easting (metres)
 5033632.943 northing (metres)
 Approximate Depth Tested: 2.2 mbg
 85.2 masl



Field Measurements:

Elapsed Time (min)	Water Level (cm)	Water Level Change (cm)	Infiltration (cm/min)	Soil Description
0.20	100	-	-	moist sandy silty clay
0.55	160	60.00	171.43	
1.20	195	35.00	53.85	
1.95	200	5.00	6.67	
2.70	210	10.00	13.33	
4.28	220	10.00	6.32	
6.35	225	5.00	2.42	
7.63	230.8	5.80	4.52	
12.63	244	13.20	2.64	
17.63	254.6	10.60	2.12	
19.63	256.3	1.70	0.85	
21.72	258.2	1.90	0.91	
23.63	259.9	1.70	0.89	
25.63	261.8	1.90	0.95	
27.63	263.4	1.60	0.80	
29.63	265	1.60	0.80	
31.63	266.4	1.40	0.70	
36.63	268.2	1.80	0.36	
41.63	270.4	2.20	0.44	
46.633333	271.8	1.40	0.28	
51.633333	273.4	1.60	0.32	
57.13	274.9	1.50	0.27	

Test Conditions:

Instrument: 1" stainless steel Solinst Drivepoint Instrument
 hole radius (a) = 2.54 cm
 Water column height in hole (H₁) = 15.24 cm
 Ambient Air Temperature at Testing = 4 °C

Interpretations:

Soil Capillary Type = Strong
 Soil Type Coefficient (α*) = 0.04 cm⁻¹
 Average Water Level Change (R₁) = 0.01 cm/s
 Steady Intake Water Rate (Q₁) = 0.05 cm³/s
 Shape factor for H₁/a = (C₁) = 1.80 -

Field Saturated Hydraulic Conductivity (K_{fs}):

K_{fs} = 2E-05 cm/s
 K_{fs} corrected to 4°C ('freshet')¹ = 2E-05 cm/s
 K_{fs} corrected to 24°C ('summer')¹ = 4E-05 cm/s


Date of Field Measurements: 16-Nov-23
 Field Representative: EB
 Reviewed: ZK
 Reviewed: ZK

¹ (Streeter and Wylie, 1975)
¹ (Reynolds, 2008 and 2015)

Constant Head Well Permeameter Test Report



Project: Rohit Wateridge Village
 Project Number: CO947
 Location Name: Inf 6-3
 Approximate Location: 450119.334 easting (metres)
 5033599.579 northing (metres)
 Approximate Depth Tested: 1.5 mbg
 85.3 masl



Field Measurements:

Elapsed Time (min)	Water Level (cm)	Water Level Change (cm)	Infiltration (cm/min)	Soil Description
0.58	85.1	-	-	moist sandy silty clay
0.75	98	12.90	77.40	
0.85	105.7	7.70	77.00	
0.93	113.1	7.40	88.80	
1.33	135.6	22.50	56.25	
1.72	149.9	14.30	37.30	
1.93	154	4.10	18.92	
2.17	158.5	4.50	19.29	
2.50	162	3.50	10.50	
2.85	166.5	4.50	12.86	
3.17	169.5	3.00	9.47	
3.47	172.5	3.00	10.00	
3.80	175.5	3.00	9.00	
4.07	178.5	3.00	11.25	
4.40	181.5	3.00	9.00	
4.97	185	3.50	6.18	

Test Conditions:

Instrument: 1" stainless steel Solinst Drivepoint Instrument
 hole radius (a) = 2.54 cm
 Water column height in hole (H₁) = 15.24 cm
 Ambient Air Temperature at Testing = 4 °C

Interpretations:

Soil Capillary Type = Strong
 Soil Type Coefficient (α*) = 0.04 cm⁻¹
 Average Water Level Change (R₁) = 0.19 cm/s
 Steady Intake Water Rate (Q₁) = 0.97 cm³/s
 Shape factor for H₁/a = (C₁) = 1.80 -

Field Saturated Hydraulic Conductivity (K_{fs}):

K_{fs} = 4E-04 cm/s
 K_{fs} corrected to 4°C ('freshet')¹ = 4E-04 cm/s
 K_{fs} corrected to 24°C ('summer')¹ = 8E-04 cm/s


Date of Field Measurements: 16-Nov-23
 Field Representative: EB
 Reviewed: ZK
 Reviewed: ZK

¹ (Streeter and Wylie, 1975)
¹ (Reynolds, 2008 and 2015)

Constant Head Well Permeameter Test Report



Project: Rohit Wateridge Village
 Project Number: CO947
 Location Name: Inf 6-4
 Approximate Location: 450132.294 easting (metres)
 5033578.57 northing (metres)
 Approximate Depth Tested: 1.0 mbg
 84.5 masl



Field Measurements:

Elapsed Time (min)	Water Level (cm)	Water Level Change (cm)	Infiltration (cm/min)	Soil Description
0.00	33	-	-	moist sandy silty clay
0.17	43	10.00	60.00	
0.33	63	20.00	120.00	
0.42	83	20.00	240.00	
0.58	93	10.00	60.00	
0.75	103	10.00	60.00	
0.83	113	10.00	120.00	
1.00	123	10.00	60.00	
1.25	133	10.00	40.00	
1.75	143	10.00	20.00	
2.75	153	10.00	10.00	
4.25	163	10.00	6.67	
10.83	173	10.00	1.52	
21.92	183	10.00	0.90	
43.83	188	5.00	0.23	

Test Conditions:

Instrument: 1" stainless steel Solinst Drivepoint Instrument
 hole radius (a) = 2.54 cm
 Water column height in hole (H₁) = 15.24 cm
 Ambient Air Temperature at Testing = 10 °C

Interpretations:

Soil Capillary Type = Strong
 Soil Type Coefficient (α*) = 0.04 cm⁻¹
 Average Water Level Change (R₁) = 0.01 cm/s
 Steady Intake Water Rate (Q₁) = 0.07 cm³/s
 Shape factor for H₁/a = (C₁) = 1.80 -

Field Saturated Hydraulic Conductivity (K_{fs}):

K_{fs} = 3E-05 cm/s
 K_{fs} corrected to 4°C ('freshet')¹ = 3E-05 cm/s
 K_{fs} corrected to 24°C ('summer')¹ = 5E-05 cm/s

Date of Field Measurements: 16-Nov-23
 Field Representative: EB
 Reviewed: ZK
 Reviewed: ZK

¹ (Streeter and Wylie, 1975)
¹ (Reynolds, 2008 and 2015)


APPENDIX F

California Bearing Ratio Test Results

LABORATORY COMPACTION TEST

ASTM D698 Method C

FIGURE



Standard
Proctor Test Results

Sample:
INF 6-1

Max Dry Density:
2.091 Mg/m³

Optimum Water
Content: 8.5%

Natural Water
Content: N/A



CALIFORNIA BEARING RATIO TEST (CBR) ASTM D1883

PROJECT NUMBER	CA0011941.3280(3000)	SAMPLE NUMBER	INF6-1
PROJECT NAME	Terrapex/Lab Testing/Miss.	SAMPLE DEPTH (m)	-
BOREHOLE NUMBER	-	DATE	12/15/2023

TEST INFORMATION

STRAIN RATE, mm/min	1.27	PARTICLE SIZE, mm	<19
RAM AREA, cm ²	19.44	COMPACTION	ASTM D698 Method C
LOAD CELL NUMBER	234341	NUMBER OF LAYERS	3
SURCHARGE, kg	4.54	BLOWS PER LAYER	56
SOAKING TIME, hr	92.2	RELATIVE COMPACTION, %	99

SAMPLE INFORMATION

UNSOAKED		SOAKED			
SAMPLE HEIGHT, cm	11.63	11.88	DRY WEIGHT, g	4413.21	4413.21
SAMPLE DIAMETER, cm	15.22	15.22	WATER CONTENT, %	8.59	9.71
SAMPLE AREA, cm ²	181.94	181.94	UNIT WEIGHT, kN/m ³	22.20	21.96
SAMPLE VOLUME, cc	2115.92	2161.59	DRY UNIT WT., kN/m ³	20.45	20.01
WET WEIGHT, g	4792.30	4841.60			

PENETRATION


UNSOAKED			SOAKED		
Penetration (mm)	Load (kgf)	Bearing Stress (MPa)	Penetration (mm)	Load (kgf)	Bearing Stress (MPa)
0.0	-	0.00	0.0	0.00	0.00
0.5	-	0.00	0.5	7.81	0.04
1.0	-	0.00	1.0	30.78	0.16
1.5	-	0.00	1.5	73.51	0.37
2.0	-	0.00	2.0	110.73	0.56
2.5	-	0.00	2.5	151.63	0.76
3.0	-	0.00	3.0	193.90	0.98
3.5	-	0.00	3.5	240.76	1.21
4.0	-	0.00	4.0	287.63	1.45
4.5	-	0.00	4.5	348.28	1.76
5.0	-	0.00	5.0	398.37	2.01
5.5	-	0.00	5.5	449.37	2.27
6.0	-	0.00	6.0	501.29	2.53
6.5	-	0.00	6.5	551.83	2.78
7.0	-	0.00	7.0	600.99	3.03
7.5	-	0.00	7.5	653.38	3.30
8.0	-	0.00	8.0	704.84	3.56
8.5	-	0.00	8.5	754.00	3.80
9.0	-	0.00	9.0	809.14	4.08
9.5	-	0.00	9.5	871.63	4.40
10.0	-	0.00	10.0	918.95	4.64
10.5	-	0.00	10.5	965.82	4.87
11.0	-	0.00	11.0	1015.90	5.13
11.5	-	0.00	11.5	1058.63	5.34
12.0	-	0.00	12.0	1107.80	5.59
12.5	-	0.00	12.5	1138.12	5.74
13.0	-	0.00	13.0	1180.40	5.95

TEST RESULTS

WATER CONTENT AT PENETRATION POINT, %	SOAKED 10.03
SWELL, %	2.16
CORRECTED STRESS VALUE (at 2.5 mm), MPa	1.10
CORRECTED STRESS VALUE (at 5.0 mm), MPa	2.45
BEARING RATIO (at 2.5 mm), %	15.94
BEARING RATIO (at 5.0 mm), %	23.79

CALIFORNIA BEARING RATIO TEST (CBR)

Sample INF6-1
California Bearing Ratio Test - ASTM D1883



Project No: CA-0011941.3280(3000)

WSP Canada Inc.

Checked By: AH