



**REPORT**

# Phase Two Environmental Site Assessment

*Wateridge Village Phase 4, Part of 1076 Hemlock Private, Ottawa, Ontario*

Submitted to:

**Canada Lands Company**

1050-100 Queen Street  
Ottawa, Ontario  
K1P 1J9


Submitted by:

**WSP Canada Inc.**

1931 Robertson Road, Ottawa, Ontario, K2H 5B7, Canada

19124906

January 2023



## Distribution List

1 copy (.pdf) - Canada Lands Company

1 copy - WSP Canada Ltd.

# Table of Contents

|  |           |
|--|-----------|
| <b>1.0 EXECUTIVE SUMMARY .....</b>   | <b>1</b>  |
| <b>2.0 INTRODUCTION .....</b>  | <b>2</b>  |
| 2.1 Site Description .....   | 2         |
| 2.2 Property Ownership .....   | 3         |
| 2.3 Current and Proposed Future Uses .....                                   | 3         |
| 2.4 Applicable Site Condition Standard .....                                 | 3         |
| <b>3.0 BACKGROUND INFORMATION.....</b>                                       | <b>4</b>  |
| 3.1 Physical Setting.....  | 4         |
| 3.2 Past Investigation.....  | 5         |
| 3.2.1 DST 2004 Steam Line Decommissioning and Remediation Plan (figure)..... | 5         |
| 3.2.2 DST 2015 Phase One ESA.....  | 5         |
| 3.2.3 DST 2015 Phase Two ESA.....  | 6         |
| 3.2.4 DST 2016 Environmental Status Summary Letter.....                      | 7         |
| 3.2.5 DST 2017 Soil and Groundwater Remediation Volume 1 .....               | 7         |
| 3.2.6 Dillon 2019 Environmental Impact Statement.....                        | 7         |
| <b>4.0 SCOPE OF WORK.....</b>  | <b>8</b>  |
| <b>5.0 SCOPE OF THE INVESTIGATION.....</b>                                   | <b>8</b>  |
| 5.1 Overview .....   | 8         |
| 5.2 Media Investigated .....   | 9         |
| 5.3 Phase One ESA Conceptual Site Model.....                                 | 9         |
| 5.4 Deviation from Sampling and Analysis Plan .....                          | 11        |
| 5.5 Impediments.....   | 12        |
| <b>6.0 INVESTIGATION METHOD.....</b>   | <b>12</b> |
| 6.1 General.....   | 12        |
| 6.2 Borehole Drilling.....   | 12        |
| 6.3 Test Pit Excavation .....  | 12        |
| 6.4 Soil Sampling .....  | 13        |

6.5 Groundwater: Field Measurements for Water Quality Parameters ..... 13

6.6 Quality Assurance and Quality Control Measures ..... 14

**7.0 REVIEW AND EVALUATION ..... 15**

7.1 Geology ..... 15

7.2 Groundwater: Elevation and Flow Direction..... 15

7.3 Groundwater: Hydraulic Gradients and Velocity ..... 15

7.4 Fine-Medium Soil Texture ..... 15

7.5 Soil Quality ..... 16

7.6 Groundwater Quality ..... 16

7.7 Data Quality Review..... 16

**8.0 PHASE TWO CONCEPTUAL SITE MODEL ..... 17**

8.1 Physical Setting..... 18

**9.0 REMEDIATION ..... 25**

**10.0 CONCLUSIONS ..... 25**

**11.0 SIGNATURES ..... 26**

**TABLES (embedded)**

Table A: RSC Property Information ..... 2

Table B: RSC Property Owner’s Information..... 3

Table C: APECs and Associated PCAs Identified in the Phase One ESA..... 11

Table D: APECs and Associated PCAs Identified in the Phase One ESA..... 22

Table E: Phase Two ESA Investigation Results for Each APEC ..... 22

**FIGURES**

Figure 1: Site Plan with Former Buildings and Areas of Potential Environmental Concern

Figure 2: Groundwater Elevations, Interpreted Shallow Groundwater Flow Direction and Cross Section Locations

Figure 3A: Metals Analysis and Exceedances in Groundwater

Figure 3B: PAH Analysis and Exceedances in Groundwater

Figure 3C: PHC Analysis and Exceedances in Groundwater

Figure 4A: Metals Analysis and Exceedances in Soil

Figure 4B: PAH Analysis and Exceedances in Soil

Figure 4C: PHC Analysis and Exceedances in Soil

Figure 5A: Cross-Section A-A' (Interpreted geological and hydrogeological conditions) with metals analysis and exceedances in soil

Figure 5B: Cross-Section A-A' (Interpreted geological and hydrogeological conditions) with PAH analysis and exceedances in soil

Figure 5C: Cross-Section A-A' (Interpreted geological and hydrogeological conditions) with PHC analysis and exceedances in soil

Figure 6A: Cross-Section B-B' (Interpreted geological and hydrogeological conditions) with metals analysis and exceedances in soil

Figure 6B: Cross-Section B-B' (Interpreted geological and hydrogeological conditions) with PAH analysis and exceedances in soil

Figure 6C: Cross-Section B-B' (Interpreted geological and hydrogeological conditions) with PHC analysis and exceedances in soil

Figure 7: Conceptual Site Model Potential Receptor Pathways (Pre-Remediation)

## **APPENDICES**

### **APPENDIX A**

Survey Plan

### **APPENDIX B**

Sampling and Analysis Plan

### **APPENDIX C**

Record of Test Pits

### **APPENDIX D**

Laboratory Certificates

### **APPENDIX E**

Tables

### **APPENDIX F**

Rationale for Naturally Occurring Barium, Chromium, Cobalt and Vanadium in Ottawa Marine Clay Above Generic Standards to Support a Record of Site Condition (RSC)

### **APPENDIX G**

Remediation Report

## 1.0 EXECUTIVE SUMMARY

WSP Canada Inc. (formerly Golder Associates Ltd. (“Golder”) and hereafter referred to as “WSP”) was retained by Canada Lands Company (CLC) to conduct a Phase Two Environmental Site Assessment (ESA) of part of the former Canadian Forces Base (CFB) Rockcliffe (the “Site” or the “Phase Two Property”) in Ottawa, Ontario, specifically Phase 4, in the central part of the former base. The location of the Phase Two Property is provided in Figure 1.

WSP conducted a Phase One ESA in support of the Record of Site Condition (RSC) Property in June 2022 and based on the available information reviewed, it was identified that several areas of the Phase One ESA Property were underlain by fill and that historical investigation had identified three locations with documented exceedances in the fill, attributed to demolition of the near by former buildings. Although these impacts were reported to have been remediated in 2014 and 2015, for the purpose of the Phase One ESA, fill was retained as a potentially contaminating activity resulting in an Area of Potential Environmental Concern (APEC) across the Site. The findings of the historical Phase Two ESA and remediation have been incorporated into the current Phase Two ESA, as discussed below. A second APEC was identified as the potential for groundwater impacts from former fuel storage tanks associated with the swimming pool operation in former Building 137, located off-Site to the north of the central portion of the Site. This APEC was also remediated in 2014/15 but due to the documented residual groundwater contamination located off-Site, it was retained as resulting in an APEC on the RSC Property.

As such, the Phase One ESA for the RSC Property identified following two APECs:

- APEC 1: Potential for subsurface impacts resulting from the presence of poor quality of fill including building demolition materials across the Site.
- APEC 2: Potential for groundwater impacts on the Site from former off-Site fuel storage tanks and associated known off-Site groundwater contamination.

For context, the RSC Property was initially assessed as federal land along with the remainder of the CFB Rockcliffe as far back as the 1990s through a series of investigations culminating in remediation work undertaken in 2014 and 2015, including portions of the RSC property. WSP has reviewed the previous investigations and remedial work in comparison to the current Site Condition Standards and regulatory regime and has incorporated the historical data that was considered by the QP as reliable for use in the Phase Two ESA.

A historical Phase Two ESA was completed by others for the RSC Property and surrounding lands of the CFB Rockcliffe. The investigation identified fill quality related impacts (APEC 1) in the area with former buildings and structures on the RSC Property, where two samples (TP61 SGS1 and TP62 SGS1) indicated concentrations of PHCs and/or PAHs above the applicable site conditions standards in soil. In addition, two soil samples located off-Site (TP31 and BHMW15) also had exceedances of metals (TP31) and PHCs and PAHs (BHMW15), respectively. These off-Site soil impacts were subsequently remediated with the remediations extending onto the RSC property. PHC and PAH impacts were also identified in groundwater at BHMW15 (located north of the central portion of the RSC Property). Off-Site groundwater remediation was completed, however, residual PHC impacts were documented following the remedial activities at the southern limit of remedial excavation (MW137-3). These impacts were delineated off-Site to the north of the RSC Property during the Phase Two ESA completed in July 2020.

WSP completed a Phase Two ESA in accordance with O. Reg. 153/04 (as amended) at the Site in three stages to investigate the APECs identified in the Phase One ESA. The initial stage consisted of a test pit program to

evaluate fill quality at the RSC Property and surrounding lands, completed in July 2020. Seven of the test pits (TP4-01, TP4-02, TP4-10, TP4-12, TP4-13, TP4-15, TP4-16) completed were located on the RSC Property. The next stage of the investigation, conducted in July 2020, was a drilling program where five boreholes with monitoring wells were completed on the RSC Property to evaluate both the fill quality of APEC 1 and the groundwater quality within the APEC 2, positioned around the off-Site potential contaminating activity (PCA). Two of these boreholes identified soil impacts within the fill layer near / in a recently constructed storm sewer trench that crosses the RSC Property. These impacts were subsequently delineated in a third stage of investigation which included a test pitting program completed in October 2022 consisting of seven test pits (TP22-01 to TP22-07). Details of this test pit program and borehole investigation relevant to the RSC Property have been included in the Phase Two ESA Report.

Three small localized remediations were completed at the RSC Property between September 2014 and January 2015 to remove impacted soil (identified in investigations completed by others which have been incorporated in the Phase Two ESA report) from the Site followed by confirmatory sampling. In addition, a soil and groundwater remediation for the exceedance in BHMW15 (associated with former fuel storage tanks around former Building 137) was completed off-Site with a portion of the remedial soil excavation extending on to the RSC Property which was validated by clean sample. The sampling methodology and analytical data from these remediations which are relevant to the RSC Property have been discussed in the Remediation Report (Appendix G from the Phase Two ESA report). The remediation for soil impacts identified in the Phase Two ESA was completed between October and December 2022. This remediation work, completed with full time supervision by a WSP staff, included removal of all impacted soil (4,630 m<sup>3</sup>) from the RSC Property, collection and analysis of confirmatory samples, and backfilling of the excavation.

Based on the results of the soil (APEC 1 - fill) and groundwater (APEC 2 – off-site PHC and PAH exceedances in groundwater) samples submitted as part of this Phase Two ESA and following remediation, the reported concentrations of the contaminants of potential concern were below the applicable site condition standards as of the certification date (December 14, 2022). No risk assessment or remediation is required prior to the submission of an RSC.

## 2.0 INTRODUCTION

### 2.1 Site Description

WSP Canada Ltd. (formerly Golder Associates Ltd. at the time of the investigation), hereafter referred to as WSP, was retained by CLC to conduct a Phase Two ESA of the following property:

**Table A: RSC Property Information**

|                                       |  |
|---------------------------------------|--|
| <b>Municipal Address</b>              | Part of 1076 Hemlock Private, Ottawa, Ontario (formerly part of 335 St. Laurent Boulevard)             |
| <b>Property Identification Number</b> | Part of PIN 04273-1205 (LT)  |
| <b>Legal Description</b>              | Part of Lots 23 and 24, Concession 1 (Ottawa Front), Geographic Township of Gloucester, City of Ottawa |
| <b>Size of the Phase Two Property</b> | 4.89 hectares  |

The location of the RSC Property is provided in Figure 1. A plan of survey for the Site is provided in Appendix A. The boundaries of the Site, which are the same as the RSC property boundaries, are provided in Figure 1.

## 2.2 Property Ownership

The contact information for the Phase Two Property owner is as follows:

**Table B: RSC Property Owner's Information**

|   |   |   |
|---|---|---|
| <b>Owner:</b><br>Canada Lands Company CLC Limited | 100 Queen Street, Suite 1050<br>Ottawa, ON<br>K1P 1J9 | Katherine Constantine<br>Office: (613) 564-3017<br>Email: kconstantine@clc.ca |
|---|---|---|

## 2.3 Current and Proposed Future Uses

The Phase Two Property is currently vacant with no buildings. The proposed future use of the Phase Two Property is a residential subdivision. The most recent use on the property consisted of mixed land use including residential barracks, office buildings, ground telecom site and transmission tower.

## 2.4 Applicable Site Condition Standard

The analytical results of the samples collected for this Phase Two ESA were compared to the Table 1 Full Depth Background Site Condition standards (residential property use) presented in the MECP document "*Soil, Ground Water and Sediment Standards for Use Under Part XV.1 of the Environmental Protection Act*", dated April 15, 2011. The applicable site condition standards were selected based on the following rationale:

- The Phase Two Property and all other properties located, in whole or in part, within 250 metres of the Phase Two Property are supplied by the City of Ottawa municipal drinking water system. No wells were identified that are used or intended for use as a source of water.
- The Phase Two Property is not located in an area designated in a municipal official plan as a well-head protection area or other designation identified by the municipality for the protection of ground water.
- Based on field observations the native soil (silt and clays interbedded with sands and gravels) is considered to be a mixture of fine and coarse textured. As such coarse textured soils was selected for screening purpose.
- The average thickness of overburden at the Site is less than 2 metres below ground surface (mbgs). Hence, the RSC Property is considered a shallow soil property.
- The closest water body is the Ottawa River, located 950 metres (m") north of the Phase Two Property. There is also a stormwater pond 200 m northeast of the Site and associated stormwater ditches north of the Site. Stormwater pond and infrastructure (ditches) are not considered as water body under the Regulation and are therefore not considered in the selection of the standards.
- An area of natural significance was identified on or within 30m of the Site due to presence of bat habitat potentially used by endangered bat species (brown myotis) as well as documented butternut trees to the north and east of the Site. As such the RSC Property is considered an environmentally sensitive area.
- The pH of surface soil is  $5 \leq \text{pH} \leq 9$  and the pH of sub-surface soil meets the requirement that  $5 \leq \text{pH} \leq 11$ .
- The intended use for the Phase Two Property is residential.



### 3.0 BACKGROUND INFORMATION

This section presents the background conditions of the Phase Two Property including a description of the physical setting and a summary of past investigations conducted.

The objectives of the Phase Two ESA were to obtain information about environmental conditions in the soil and groundwater on, in or under the Site, and to develop the information necessary to complete a Record of Site Condition (RSC) for the property. The objectives of this Phase Two ESA were achieved by:

- Developing an understanding of the geological and hydrogeological conditions at the Phase Two Property.
- Conducting field sampling for all contaminants of concern (COCs) associated with each APEC identified in the Phase One ESA.

The Sampling and Analysis Plan (Appendix A), Record of Test Pits (Appendix B), Record of Boreholes (Appendix C) and Laboratory Certificates (Appendix D) are appended to this report.

#### 3.1 Physical Setting

The RSC Property consisted of a 4.89-hectare parcel of currently vacant land that consisted of a few old, paved roadways associated with the former CFB Rockcliffe military base. There were no structures currently present on the Site. Historically, the RSC Property was occupied by a series of buildings and structures associated with the former military base and were used for:

- Building 8: Office – Chaplain's office
- Building 9: Office – Special investigation department
- Building 10: Office – Eastern section investigation department
- Building 11: Ground telecom transmission site
- Building 70: Residential: Airwomens' barracks
- Building 71: Residential: NCO barracks
- Building 124: Office: ground training offices
- Building 126: transmission tower

The surrounding properties to the north, east and west are undeveloped and the properties to the south and southwest are under development for parkland and residential housing. Historically, the surrounding lands were also developed as part of the military activities associated with CFB Rockcliffe with buildings for commercial use including lounge (building 15), hospital (building 134), medical storage (building 176), other storage (buildings 178 and 179), and an indoor swimming pool (building 137).

An environmental impact statement completed to the east and northeast of the Phase Two Property, including a study area overlapping the east part of the Phase Two Property, identified presence of bat habitat potentially used by endangered bat species (brown myotis) as well as documented butternut trees to the north and east of the Site. As such the RSC Property is considered an environmentally sensitive area. The topography of the Phase Two Property and surrounding areas is generally uneven with an overall slope to the north. Beyond the north Site

limit there is a ridge with a steep slope to the north. The southern portion of the Site is generally at grade with the adjacent properties east and south.

## 3.2 Past Investigation

The following environmental reports related to the Site were provided to WSP and previously to Golder by CLC. Noteworthy findings are summarized below.

- “DST 2004 Steam Line Decommissioning and Remediation Plan”. CFB Rockcliffe Underground Steam Line Decommissioning and Site Remediation Plan. Prepared by DST Consulting Engineers, dated December 2004.
- “DST 2015 Phase One ESA”. Phase One Environmental Site Assessment, Former CFB Rockcliffe, Ottawa, Ontario. Prepared by DST Consulting Engineers for Canada Lands Company CLC Limited, dated May 2015.
- “DST 2015 Phase Two ESA”. Phase Two Environmental Site Assessment Update, Former CFB Rockcliffe, Ottawa, Ontario. Prepared by DST Consulting Engineers for Canada Lands Company CLC Limited, dated May 2015.
- “DST 2016 Environmental Status Summary Letter.” Environmental Status Summary Letter, May 2105, Soil and Groundwater Remediation, Former CFB Rockcliffe, Ottawa, Ontario. Prepared by DST Consulting Engineers for the City of Ottawa, dated May 11, 2016.
- “DST 2017 Soil and Groundwater Remediation Volume 1”. Soil and Groundwater Remediation Volume 1, Former CFB Rockcliffe, Ottawa, Ontario. Prepared by DST Consulting Engineers for Canada Lands Company CLC Limited, dated September 2017.
- “Dillon 2019 Environmental Impact Statement”. Wateridge Village Phase 2A and 2B, Environmental Impact Statement. Prepared by Dillon Consulting for Canada Lands Company, dated February 2019

### 3.2.1 DST 2004 Steam Line Decommissioning and Remediation Plan (figure)

This figure outlines the location of the steam distribution line throughout the base that was used to distribute steam heating from the central heating plant. The 2009 Phase II ESA makes a reference to testing completed from the fill along the steam line during its removal. In total there were nine samples of the twenty-five collected that were documented to exceed the provincial standards at that time and an additional three exceeding federal criteria. The parameters noted as exceedances are metals, PAHs, and PHCs. No details on the location of the exceedances were provided and as such all the fill through which the steam line passes are considered to be a PCA.

The steam line is present along the northern (north of former buildings 69, 70 and 71) and eastern side of the RSC Property boundary beside former Hurley Crescent. Additionally, the fill off-site is considered a PCA but is not considered to have resulted in an APEC to the RSC Property.

### 3.2.2 DST 2015 Phase One ESA

The 2015 Phase One ESA was done for the entire CFB Rockcliffe area including the RSC Property. In total the Phase One ESA identifies twenty-three (23) areas of environmental concern on the former base lands and two areas of concern associated with the off-site land uses for the Monfort Hospital and the National Research Council. The Montfort Hospital is outside the current RSC Study Area. The report indicates the property was first developed as a military base in 1937 and was previously owned by individual owners as either vacant land or part

of larger farmsteads. The site was occupied by a series of buildings throughout the operation of the base until being decommissioned and demolished prior to the completion of the Phase One ESA.

The following identified areas of concern are relevant to the RSC Property.

Petroleum hydrocarbon soil and groundwater impacts at the former swimming pool at building 137 associated with two former fuel storage tanks (one below and one above ground tank). Petroleum hydrocarbon impacts at the former communication building and transmitter tower at buildings 126 and 11 and metals impacts in fill in the northwest of the RSC Property (test pit TP31).

The report identified several off-Site PCAs within the study area including poor quality fill to the south and east, PHC remediations attributed to an automotive garage at Building 29 and possible fuel storage tanks at Building 22 as well as a fuel storage tank at Building 16 and Building 134. All off the off-site PCAs were subsequently remediated, with the exception of Building 134 to the west, and are therefore not considered as APECs to the RSC Property. Building 134 is 60 metres cross gradient to the RSC Property and the contamination was documented to be limited in extent and therefore is not considered to represent an APEC to the RSC Property.

### **3.2.3 DST 2015 Phase Two ESA**

The above report provides an updated summary of the Phase II ESA completed in 2004 and 2007 and presented in the report entitled “Phase II Environmental Site Assessment, Lands Associated with the Remediation of Various Building Sites at Canadian Forces Base Rockcliffe. Prepared by DST Consulting Engineers for Canada Lands Company and Public Works and Government Services, dated April 2009”. As the report does not introduce any significant new data and is a repackaging of the previous report including a comparison to the current MECP standards, only the 2015 report is discussed.

The report presents the findings of a Phase II ESA completed at the Site in 2009, much of which is carried over from a 2004 investigation, which included 26 boreholes/monitoring and 73 test pits. The 2015 update included the addition of four groundwater samples from existing monitoring wells and the installation and sampling of one new monitoring well. The investigation covers the entire CFB Rockcliffe property in addition to RSC Property.

The following summarizes the findings of the Phase Two ESA report with respect to the RSC Property.

The 2015 Phase Two ESA documents the findings of nineteen (19) test pits in the vicinity to buildings 11, 71, 69, 137 and 126 and included four borehole/monitoring wells. Of these investigation locations soil at eleven (11) of the locations reported exceedances. Zinc at TP31 in the shallow soil near building 71, PHCs and PAHs in shallow soils at TP126-1, TP61 and TP62 near building 126 and PHCs and PAHs in seven locations around building 137 extending up to 3.2 metres in depth. The impacts at building 137 are reported to be associated with a former gasoline UST and AST at the former indoor pool at this location. The impacts at the other areas are not associated with any specific PCA and are attributed to poor quality fill resulting from building demolition and filling and were limited to the upper 1.3 metres of soil.

Groundwater from monitoring well BHMW-15 at building 137 contained PHCs above the current standards, with the remaining monitoring wells meeting criteria.

The estimated quantity of contaminated soil was 4,425 m<sup>3</sup>, 432 m<sup>3</sup> and 258 m<sup>3</sup> for the areas near buildings 137, 71 (TP31) and building 126, respectively.

The poor-quality fill (on-Site PCA) and fuel storage tanks (off-Site PCA) are considered as APECs for the RSC Property, however were reported as having been remediated.

### **3.2.4 DST 2016 Environmental Status Summary Letter**

This document is a summary letter for the City of Ottawa on the status of the remediation works at the larger CFB Rockcliffe site and includes a summary of a post remediation groundwater sampling program. The letter states that a total of 62,000 m<sup>3</sup> of impacted soil and 2,300 m<sup>3</sup> of impacted groundwater was removed from the site from all areas, as of February 5, 2015 and that all the soils except one site (former Cannex gas station) met the MECP Table 3 residential standards. The Cannex site is outside the RSC Property. The letter indicates that there were two rounds of groundwater sampling completed across the site from all of the wells between March and August of 2015. Although the letter does not list the wells that were sampled it is assumed that the wells shown on the figure are the wells that were included in the program. An additional two rounds of groundwater sampling following additional groundwater remediation was completed at three sites (Buildings 29, 80 and 137). The information specific to the RSC Property is as follows.

The impacts identified at building 137, building 126/11 and TP31 are shown as having been remediated with the groundwater at building 137 shown as having ongoing remediation. Monitoring wells are present in each remediation area. Building 137 was shown to have elevated PHC (380 ug/L) in monitoring well 137-2 which resulted in additional groundwater remediation via pump and treat. Resampling completed 30 days after the additional remediation at this location was below the standards. It is noted that building 29, which is outside the RSC Property is shown as abutting the RSC Property and was also documented as having residual groundwater contamination and required additional groundwater remediation which reportedly was successful and are therefore the off-Site PCAs are not considered as APECs to the RSC Property.

### **3.2.5 DST 2017 Soil and Groundwater Remediation Volume 1**

This report documented the remediation completed for five APECs identified in the former RSC area 1, which includes current development Phases 3, 4 and 5. These include the remediation of former building 47 (former heating oil AST), former building 126 (hydrocarbon staining in the fill at a former transmitter building), 137 (former AST and UST associated with the former swimming pool) and a test pit TP31 (metals impacts in fill). Although each area was remediated, excluding groundwater at former building 137, they are each considered as PCAs for the RSC Property.

### **3.2.6 Dillon 2019 Environmental Impact Statement**

This report was prepared for the planning approvals process of the Site and included surveys for endangered and threatened species at the Site (SAR), including targeted surveys for select species. The findings of the assessment indicated there were SAR on the CFB Rockcliffe property, mainly in the north of the Site including the woodlands adjacent to the north property boundary. These included Category 2 retainable Butternut trees along the north boundary of the CFB Rockcliffe property and in the northwest part of the base property. There was also documented SAR bats present in the woodlots on and north of the base property.

## 4.0 SCOPE OF WORK

The objectives of the Phase Two ESA were to obtain information about environmental conditions in the soil and groundwater on, in or under the Site, and to develop the information necessary to complete a Record of Site Condition (“RSC”) for the property. The objectives of this Phase Two ESA were achieved by:

- Developing an understanding of the geological and hydrogeological conditions at the Phase Two Property; and,
- Conducting field sampling for all contaminants of concern (“COCs”) associated with each area of potential environmental concern (“APEC”) identified in the Phase One ESA.

## 5.0 SCOPE OF THE INVESTIGATION.

The Phase Two ESA also includes a summary of the remedial activities and validation testing to confirm the removal of the impacts identified by the Phase Two ESA, as presented in Appendix G.

### 5.1 Overview

The Phase Two ESA investigation activities were completed between July 7, 2020, and December 14, 2022, and included the following tasks:

- **Health and Safety Plan:** Preparation of a Health and Safety Plan for internal and subcontractor use prior to initiating any field work at the Site.
- **Utility Clearances:** Coordination of utility clearances with local utility companies along with retaining the services of a private locator to assess for possible services in the areas of the proposed test locations.
- **Borehole Advancement and Monitoring Well Installation:** The borehole drilling and monitoring well installation programs included drilling of boreholes, each completed as groundwater monitoring wells, all of which were used for groundwater sampling at the Site. The rationale for the selected location of the boreholes is provided in the Sampling and Analysis Plan provided in Appendix A. The location of the boreholes and monitoring wells are provided in Figure 1. The monitoring well construction details are presented in Table 1.
- **Soil Sampling:** Selected soil samples were collected from the boreholes. Soil samples were submitted for chemical analysis of one or more of the following: petroleum hydrocarbons (“PHCs”); benzene, toluene, ethylbenzene, xylene (“BTEX”); polycyclic aromatic hydrocarbons (“PAHs”); metals; and/or hydride-forming metals.
- **Groundwater Monitoring and Sampling:** Groundwater samples were collected and submitted for analysis of one or more of the following: PHCs, BTEX, PAHs, metals, and/or hydride-forming metals.
- **Surveying:** An elevation survey for the boreholes and monitoring wells advanced as part of the Phase Two ESA investigation was completed following completion of the field work.
- **Reporting:** WSP compiled and assessed the field and laboratory results from the above noted activities into this report.

The Phase Two ESA was carried out in general accordance with WSP’s standard operating procedures, which conform to the requirements of O. Reg. 153/04. The data from the Phase Two ESA investigation completed by WSP (and previously by Golder) at the Site were incorporated into a single Phase Two ESA report following the Phase Two ESA report format required by O. Reg. 153/04.

There were no impediments or access limitations that would affect the conclusions of this Phase Two ESA report.

## 5.2 Media Investigated

To address the potential environmental issues identified in the Phase One ESA, the Phase Two ESA field program included sampling of subsurface soil and of groundwater from wells screened within the bedrock at the Site. No sediment was present at the Site and therefore no sediment sampling was completed. A summary of media investigated, and the applicable contaminants of potential concern are provided in Tables 3 and 4. The sampling and analysis plan outlines the rationale for the field investigation activities carried out at the Site and the associated methodologies used to meet the objectives of this Phase Two ESA.

## 5.3 Phase One ESA Conceptual Site Model

The following key features (as required by O.Reg. 153/04) are presented in Figures 1 and 2:

- Existing buildings and structures
- Water bodies and areas of natural significance located in the Phase One Study Area
- Drinking water wells on the Phase One Property
- Roads (including names) within the Phase One Study Area
- Uses of properties adjacent to the Phase One Property
- Location of identified PCAs in the Phase One Study Area (including any storage tanks)

The following describes the Phase One ESA CSM based on the information obtained and reviewed as part of this Phase One ESA:

- At the time of the Site visit, conducted on June 10, 2022, the Phase One Property consisted of a 4.89-hectare parcel of currently undeveloped land that consisted of wood lot and a few old, paved roadways associated with the former CFB Rockcliffe military base. There were no structures currently present on the Site.
- The previous EIS reports identified an area of bat habitat on and within 30 m of the Site, specifically the endangered brown myotis. Additional ANSI, including more bat habitat and butternut trees are present on the ridgeline (NRC Woods) bordering the north of the Phase One Property. Therefore, the Site is considered an environmentally sensitive area.
- Potable water in the vicinity of the Phase One Property is provided by the City of Ottawa. No potable water wells were identified on the Phase One Property.
- At the time of the Phase One ESA, the surrounding properties to the north, east and west were undeveloped and the properties to the south and southwest were under development for parkland and residential housing.
- Historically, the Phase One Property has been occupied by a series of buildings and structures associated with the former CFB Rockcliffe. Buildings 8, 9, 10, 11, 70, 71, 124 and 126 were located on the Phase One Property. The buildings were occupied by:
  - Building 8: Office – Chaplain's office
  - Building 9: Office – Special investigation department

- Building 10: Office – Eastern section investigation department
  - Building 11: Ground telecom transmission site
  - Building 70: Residential: Airwomens' barracks
  - Building 71: Residential: NCO barracks
  - Building 124: Office: ground training offices
  - Building 126: transmission tower
- Previous subsurface investigation on-Site using test pits was completed in the vicinity of buildings 11, 69, 71 and 126. Exceedances of petroleum hydrocarbons (PHCs) polycyclic aromatic hydrocarbons (PAHs), and metals were identified in soil samples; however, these exceedances were attributed to poor fill quality likely resulting from various construction debris.
  - There is a potential for abandoned storm sewers and watermains to be present on the Phase One Property attributed to past development of the Site, primarily along the older former roadways. There is a newer stormwater sewer (circa 2015) that runs north-south through the Phase One Property which connects the new development to a stormwater pond north of the Site.
  - Historically, the surrounding lands were also developed with buildings for commercial use including lounge (building 15), hospital (building 134), medical storage (building 176), other storage (buildings 178 and 179), and an indoor swimming pool (building 137).
  - Former building 137, located adjacent north of the central portion of the Site and demolished in 1997, operated as a swimming pool and included two fuel storage tanks – one above ground storage tank (AST) and an underground storage tank (UST). Previous investigations completed by other consultants identified TPH gas/diesel in the soil and groundwater at the location of the former tanks. Subsequently, the soil impacts were excavated and remediated in 2014. The soil remediation of the petroleum hydrocarbon impacts was validated and backfilled with granular B. Post remediation groundwater sampling identified residual groundwater impacts within the bedrock present south of the former soil remediation. Delineation of these residual groundwater impacts were completed in 2020 and 2022 using monitoring wells located on all sides of the identified impacts and downgradient of the former source. As such these groundwater impacts were confirmed to be limited to the area south of the former remediation and outside the Phase One Property. Therefore, the potential presence of PHC-impacts associated with this off-Site PCA is considered as having a reduced potential to be an APEC on the Phase One Property, however, additional groundwater sampling may be required to confirm these off-Site conditions and as such the groundwater issue off-Site remains as an APEC to the Phase One Property.
  - Review of previous investigations completed in the vicinity of the Site (discussed under section 3.2) identified several off-Site PCAs within the study area including poor quality fill to the south and east, PHC remediations attributed to an automotive garage at Building 29 and possible fuel storage tanks at Building 22, as well as a fuel storage tank at Building 16 and Building 134. All off these off-site PCAs were subsequently remediated and validated except for Building 134 to the west, and are therefore these off-Site PCAs are not considered as resulting APECs to the Phase One Property. Building 134 is 60 metres cross gradient to the Phase One Property and the contamination was documented to be limited in extent and therefore is not considered to represent an APEC to the Phase One Property.

- The geological mapping that the overburden soils include alluvial deposits (medium grained stratified sand with some silt) and offshore marine deposits (clay, silty clay and silt). It also indicates there is no overburden soil in one area of the northern portion of the Site where bedrock is expected at surface.
- Bedrock consists of Bobcaygeon Formation (limestone with minor shale in the upper parts) on the southern portion of the Site and a mix of Rockcliffe Formation (sandstone, shale, limestone and dolostone) and Gull River Formation (limestone, with dolostone beds towards base).
- The nearest permanent watercourse is the Ottawa River which is located approximately 950 m north of the Site. A stormwater pond is located 200 m to the northeast.
- Local groundwater is anticipated to flow north towards the Ottawa River.
- Based on the available information reviewed, the only two APECs for the Site are associate with the presence of fill deposits across the entire parcel which include building demolition waste and the potential for migration of PHC impacted groundwater from off-Site building 137. There have been documented areas of soil impacts on-Site which were remediated and hence, are not considered APECs for the Site, but remain within the overall APEC associated with the fill. Other PCAs were located on surrounding lands to the Site, these off-Site PCAs were remediated and delineated to or before the Site boundary and therefore were not considered as APECs to the Phase One Property.

**Table C: APECs and Associated PCAs Identified in the Phase One ESA**

| PCA and Description of the Activity   | APEC   | Location of APEC on the Site (Figure 2) | Contaminants of Potential Concern    | Media Potentially Impacted (groundwater, soil and/or sediment) | Rationale for Potential Contribution of the PCA to an APEC  |
|---|--|---|--------------------------------------|--|---|
| Importation of fill material of unknown quality (PCA 30)<br>Use of imported fill during initial development and subsequent redevelopment activities at the Site   | <b>APEC 1</b> - Potential for subsurface impacts due to the presence of impacted fill on the Site.   | Site-wide                               | PHC F1 to F4, BTEX, PAHs, and metals | Soil   | Presence of imported fill of unknown quality across the Site makes this on-Site PCA an APEC.  |
| Gasoline and Associated Products Storage in Fixed Tanks (PCA 28)<br>Off-Site former fuel storage tanks (one AST and one UST) associated with swimming pool in former Building 137 as well as associated groundwater impacts | <b>APEC 2</b> - Potential for groundwater impacts migrating on to the Site from the off-Site former fuel storage tanks associated with the swimming pool operation in former Building 137. | Central portion of the Site             | PHC F1 to F4, BTEX, and PAHs         | Groundwater  | Presence of former fuel storage tanks within 50 m of the RSC Property as well as documented impacts to groundwater located upgradient of the Site makes this off-Site PCA an APEC for the Site. |

## 5.4 Deviation from Sampling and Analysis Plan

There were no material deviations to the Phase One ESA requirements set out in O.Reg. 153/04 that would cause uncertainty or absence of information that would affect the validity of the Phase One Conceptual Site Model or the findings of this Phase One ESA.



## 5.5 Impediments

No physical impediments to the Phase Two ESA investigation were encountered. Access to the Phase Two Property was not denied or restricted.

## 6.0 INVESTIGATION METHOD

### 6.1 General

The following sections describe the field investigation methodology employed during the Phase Two ESA. The field work was conducted in three sessions. The first investigation was between July 7-8, 2020; the second investigation took place between June 27-29, 2021; and the final investigation of this Phase Two ESA was completed between July 22 and December 15, 2022. Three small localized remediations were completed at the RSC Property between September 2014 and January 2015 to remove impacted soil (identified in investigations completed by others which have been incorporated in the Phase Two ESA report) from the Site followed by confirmatory sampling. In addition, a soil and groundwater remediation for the exceedance in BHMW15 (associated with former fuel storage tanks around former Building 137) was completed off-Site with a portion of the remedial soil excavation extending on to the RSC Property which was validated by clean samples. The sampling methodology and analytical data from these remediations which are relevant to the RSC Property have been discussed in the Remediation Report (Appendix G from the Phase Two ESA report). The remediation for soil impacts identified in the Phase Two ESA was completed between October and December 2022. This remediation work, completed with full time supervision by a WSP staff, included removal of all impacted soil from the RSC Property, collection and analysis of confirmatory samples, and backfilling of the excavation.

Prior to initiating the field work, a Site-specific protocol to protect the health and safety of its employees and subcontractors was developed and implemented through the preparation of a Site-specific Health and Safety Plan. An assessment of potential health and safety hazards at the Phase Two Property and those associated with the proposed work was completed each day of the field program. A health and safety tail gate meeting were held with the subcontractors each day prior to completion of the field work. The document was reviewed and signed on-Site by field personnel prior to commencing work. Additionally, prior to any intrusive investigations, including drilling, public and private utility clearances were also obtained.

### 6.2 Borehole Drilling

A total of five boreholes (22-02 to 22-06) were advanced within the RSC Property boundary in 2022 to depths ranging between 7.92 and 12.19 mbgs. In general, the subsurface soil conditions encountered in the boreholes consisted of surficial topsoil and fill with predominantly gravelly silty sand that extended to maximum depth of 3.05 mbgs at 22-04. This was underlain by glacial till consisting of layers of silty sand, silty clay to clay, and gravelly silty sand to silty sand and gravel. All other borehole locations only consisted of fill layers followed by bedrock.

Bedrock was encountered in all five boreholes advanced during the Phase Two ESA at depths ranging between 0.61 and 7.92 mbgs.

### 6.3 Test Pit Excavation

In 2020, soil samples were collected from test pits at seven locations (TP4-01, TP4-02, TP4-10, TP4-12, TP4-13, TP4-15, TP4-16). The locations of the test pits are shown on Figure 1. Where possible, the test pits were excavated to bedrock or native soil, where present, and extended to depths ranging between of 0.9 to 2.30 mbgs.

In 2022, soil samples were collected from test pits at seven locations (T22-01 to TP22-07). The locations of the test pits are shown on Figure 1. Locates were obtained prior to excavation. Each test pit was mechanically excavated by a track-mounted excavator equipped with a toothed bucket. Where possible, the test pits were excavated to bedrock or native soil, where present, and extended to depths ranging between 1.5 to 4.8 mbgs.

Locates were obtained prior to excavation of the test pits and each test pit was mechanically excavated by a track-mounted excavator equipped with a toothed bucket and operated by Glenn Wright Excavating Ltd.

## 6.4 Soil Sampling

Soil samples were collected from undisturbed locations and split in the field into two components, where sufficient. One component was placed into laboratory-prepared container with minimal headspace and stored in a cooler for potential laboratory analysis. The second component was placed inside a plastic bag for field screening, consisting of the soil description, and noting the presence of any staining, odour and/or debris. Groundwater: Sampling

All five boreholes advanced were completed with monitoring wells (22-02 to 2-06) with screens in bedrock. A total of five samples (including a field duplicate of from 22-04) were collected on July 18, 2022. The monitoring well associated with 22-03 was dry and hence no sample could be collected from this location.

Each monitoring well was purged prior to sample collection. During purging, qualitative observations were made of water colour, clarity, and the presence of hydrocarbon sheen or odour. Purged was completed by pumping at least three well volumes or, where the well was considered a “low-yield” monitoring well, by purging at least one half of the well volume.

Groundwater samples were placed in laboratory-prepared containers and stored in a cooler until delivery to the analytical laboratory under chain-of-custody procedures. A summary of the groundwater samples submitted for analysis is presented in Table 4.

## 6.5 Groundwater: Field Measurements for Water Quality Parameters

Groundwater indicator parameters including temperature, pH, conductivity, oxidation-reduction potential (“ORP”) and dissolved oxygen were measured prior to sampling to ensure adequate well development and purging. A YSI water quality meter was used to measure groundwater quality during monitoring well development and groundwater sampling. The instrument was calibrated using factory supplied solutions for electrical conductivity (1413 micro-Siemens per centimetre ( $\mu\text{S}/\text{cm}$ )) and pH (4.01 pH and 7.01 pH) parameters. Specifications for the water quality meter are summarized in the following table:

| Parameter        | Measurement Range | Precision  | Accuracy      |
|------------------|-------------------|------------|---------------|
| pH               | 0.00 to 14.00 pH  | 0.01 pH    | $\pm 0.2$ pH  |
| Conductivity     | 0.00 to 200 mS/cm | 0.01 mS/cm | $\pm 0.5\%$   |
| Temperature      | -5 to 45 °C       | 0.1 °C     | $\pm 0.15$ °C |
| Dissolved Oxygen | 0 to 50 mg/L      | 0.01 mg/L  | $\pm 2\%$     |

## 6.6 Quality Assurance and Quality Control Measures

WSP's quality assurance program for environmental investigations was implemented to ensure that analytical data obtained by the investigation were valid and representative. The quality assurance program included the following measures:

- The use of standard operating procedures for all field investigation activities.
- All monitoring wells were developed following installation to remove fine particles from the filter pack and any fluids introduced during drilling.
- Monitoring wells were appropriately purged prior to groundwater sample collection to remove stagnant water from the well bore and improve sample representativeness, minimizing sample agitation and aeration to the extent practicable.
- The collection of field duplicate samples at a minimum frequency of one duplicate for every ten samples.
- The collection of at least one trip blank for sampling events that include the analysis of volatile organic compounds in groundwater.
- Initial calibration of field equipment was performed at the start of each field day, with a daily check of calibration, as needed, using a standard of known concentration.
- Soil and groundwater samples were handled and stored in accordance with the sample collection and preservation requirement of the MECP "*Protocol for Analytical Methods Used in the Assessment of Properties Under Part XV.1 of the Environmental Protection Act*", July 1, 2011. Samples were collected directly into pre-cleaned, laboratory-supplied sample containers with the appropriate preservative for the analyte group. Upon collection, samples were placed in insulated coolers with ice for storage and transport to the analytical laboratory under chain-of-custody.
- Dedicated sampling equipment (tubing and foot valves) and clean disposable Nitrile™ gloves were used at each sampling location to prevent cross-contamination. All non-dedicated sampling equipment (e.g., water level meters, split spoons) was decontaminated between sampling locations. Sampling equipment in contact with soil, groundwater, or sediment was cleaned by mechanical means; washed with a phosphate-free, laboratory-grade detergent (e.g., LiquiNox) and, if necessary, an appropriate desorbing wash solution; and thoroughly rinsed with analyte-free water.
- Detailed field records documenting the methods and circumstances of collection for each field sample were prepared at the time of sample collection. Each sample was assigned a unique sample identification number recorded in the field notes, along with the date and time of sample collection, the sample matrix, and the requested analyses.
- The submission of samples to the analytical laboratory in accordance with standard chain of custody procedures.

## 7.0 REVIEW AND EVALUATION

### 7.1 Geology

In general, the subsurface soil conditions encountered in the boreholes and test pits consisted of surficial topsoil and fill of variable depths (up to 3.05 mbgs at borehole 22-04), with predominantly gravelly silty sand that extend to the maximum depth of investigation (7.92 mbgs at 22-04). At numerous investigation locations, silt and clays interbedded with sands and gravels were observed in the fill layer. A representative geologic cross-section of the Site is presented in section 6.2 as well as Figures 5A to 6C.

Bedrock was encountered in five of the six boreholes advanced during the Phase Two ESA with depth ranging between 0.61 and greater than 7.92 mbgs. Given that the average thickness of overburden at the Site is less than 2 m, the RSC Property is considered a shallow soil property as defined by O.Reg. 153/04 (as amended).

### 7.2 Groundwater: Elevation and Flow Direction

The local and regional groundwater flow direction is expected to be north following the considerable drop in ground surface elevation towards the Ottawa River to the north. It is anticipated that the storm and sanitary sewer may be influencing the groundwater elevations in the area near the sewer, and that localized flow towards the sewer maybe occurring.

Static groundwater levels were measured in the monitoring wells (except for 22-03 which was dry) located across the Site on July 18, 2022. Figure 2 shows groundwater elevations and the interpreted groundwater flow direction. Groundwater elevations ranged from 77.57 to 82.14 masl (7.33 to 9.44 mbgs), on July 18, 2022. Groundwater is contained within the bedrock aquifer.

### 7.3 Groundwater: Hydraulic Gradients and Velocity

The horizontal hydraulic gradient was estimated for groundwater conditions based on water levels collected on July 18, 2022, and the inferred groundwater contours are presented on Figure 2. The horizontal hydraulic gradient for groundwater conditions was 0.043 m/m. Vertical hydraulic gradients were not calculated as no COC were identified in groundwater exceeding the site condition standards and as such, no nested monitoring well pairs were installed.

Groundwater flow velocity was determined based on the hydraulic conductivity of  $1.5 \times 10^{-11}$  m/s (source: [https://structx.com/Soil\\_Properties\\_006.html](https://structx.com/Soil_Properties_006.html)) and assumed porosity of 20% for limestone (source: [http://worthingtongroundwater.com/?page\\_id=131#:~:text=Most%20flow%20in%20bedrock%20aquifers,in%20the%20orange%200.01%2D0.4](http://worthingtongroundwater.com/?page_id=131#:~:text=Most%20flow%20in%20bedrock%20aquifers,in%20the%20orange%200.01%2D0.4)), and the hydraulic gradient. The groundwater flow velocity within limestone was calculated to be  $3 \times 10^{-12}$  m/s. Note that the actual groundwater velocity may vary significantly not only because of the variability of the hydraulic gradient, but also because of the variability of the hydraulic conductivity due to presence of the sewer trench excavation on the RSC Property.

### 7.4 Fine-Medium Soil Texture

Based on field observations, more than 50% of particles (by mass) in the soil were equal to or greater than 75  $\mu\text{m}$  in mean diameter. Accordingly, soil at the Phase Two Property is considered to be coarse-textured.

## 7.5 Soil Quality

Table 2 provides a summary of the soil samples submitted for analysis and the associated test parameters. The analytical results of soil samples are presented in Tables 5A to 5C. The soil samples submitted for analysis are presented on Figures 4A through 6C and Figures G2A through G5B. Laboratory Certificates of Analysis for the soil samples are included in Appendix D.

A summary of the number of soil samples analyzed and the number of soil samples exceeding the Table 1 site condition standards is provided below:

- **Fill (soil)** – A total of thirty-five (35) fill/reworked native samples identified in Table 4 were analyzed for PHC F1 to F4, BTEX, PAHs and/or metals as part of the WSP 2022 Phase Two ESA. In addition, previous investigations included five samples that were analyzed for PHC F1 to F4, BTEX, PAHs and/or metals. Altogether, six of these samples exceeded applicable MECP Table 1 Standards for PHCs, and seven samples exceeded for various PAHs. The exceedances were limited to three distinct areas:
  - Two separate areas near former Building 126 on the east portion of the RSC Property.
  - One area in the recently constructed sewer trench, west of the former off-Site Building 137.

These impacts were located entirely within the fill materials and were found at depths up to 3.8 mbgs.

## 7.6 Groundwater Quality

Table 4 provides a summary of the groundwater samples submitted for analysis and the associated test parameters. The analytical results of groundwater samples are presented in Tables 6A to 6C. The soil samples submitted for analysis are presented on Figures 4A through 6C and Figures 3A through 3C. Laboratory Certificates of Analysis for the soil samples are included in Appendix D.

Groundwater quality assessment included sampling of 4 monitoring wells in 2022, which were installed around at the boundary of the RSC Property adjacent to the off-Site PCA. Table 4 summarized the groundwater analyses performed. Concentrations of PHC F1 to F4, BTEX, PAHs and metals in all the samples were below the applicable site condition standards.

### Summary of Current Site Condition – Post-Remediation

Following remediation, all contaminated soil was removed from the Site. The verification sampling program included the collection of samples as per the guidance for sampling and analysis frequency is provided in O. Reg 153/04, as amended, Schedule E, Table 3 (Minimum Confirmation Sampling Requirements for Excavation). All the validation samples met the applicable MECP Table 1 Standards. As a result, no contaminated soil above the applicable site conditions standards remains on the Site.

No groundwater remediation was required and completed at the Site.

Additional information on the remedial activities is presented in Appendix G.

## 7.7 Data Quality Review

The quality assurance assessment of the field duplicate sample results was conducted according to the MECP document “*Protocol for Analytical Methods Used in the Assessment of Properties under Part XV.1 of the Environmental Protection Act*”, March 9, 2004 (amended in July 2009 and effective as of July 1, 2011) (“Analytical Protocol”).

To determine the precision of the analytical methods and field sampling procedures, blind duplicate samples were collected during soil and groundwater sampling. Precision is determined by the relative percent difference (“RPD”) between the duplicate and original samples and was calculated as follows:

$$RPD = \frac{|x_1 - x_2|}{x_m}$$

Where

$x_1$  initial sample results  
 $x_2$  duplicate sample results  
 $x_m$  mean of  $x_1$ ,  $x_2$

The analytical results of the primary and duplicate soil and groundwater samples indicated a satisfactory correlation between the primary and duplicate samples and were within the 30% recommended control limit in the Analytical Protocol.

It is noted that the trip blank samples were found to have no detectable concentrations. The quality of the analytical results is further supported by analytical laboratory’s internal quality assurance program that includes laboratory blanks, spikes, surrogates and duplicate samples.

All certificates of analysis or analytical reports received pursuant to clause 47 (2) (b) of the regulation comply with subsection 47(3). A certificate of analysis or analytical report has been received for each sample submitted for analysis and is provided in Appendix D. The analytical laboratory did not qualify any of the analytical results.

Accordingly, the analytical data generated during the investigation are valid and representative and may be used in this Phase Two ESA without further qualification.

## 8.0 PHASE TWO CONCEPTUAL SITE MODEL

The Phase Two ESA Conceptual Site Model (CSM) described below is based on data from previous investigations and on the results of this Phase Two ESA. The CSM consists of diagrams, cross-sections and figures that show the current condition of the RSC Property. A narrative description is provided to explain the contents of the figures and an interpretation of the contaminant distribution.

The figures that comprise the Phase Two CSM include:

Figure 1: Site Plan with Former Buildings and Areas of Potential Environmental Concern

Figure 2: Groundwater Elevations, Interpreted Shallow Groundwater Flow Direction and Cross Section Locations

Figure 3A: Metals Analysis and Exceedances in Groundwater

Figure 3B: PAH Analysis and Exceedances in Groundwater

Figure 3C: PHC Analysis and Exceedances in Groundwater

Figure 4A: Metals Analysis and Exceedances in Soil

Figure 4B: PAH Analysis and Exceedances in Soil

Figure 4C: PHC Analysis and Exceedances in Soil

Figure 5A: Cross-Section A-A’ (Interpreted geological and hydrogeological conditions) with metals analysis and exceedances in soil.

- Figure 5B: Cross-Section A-A' (Interpreted geological and hydrogeological conditions) with PAH analysis and exceedances in soil.
- Figure 5C: Cross-Section A-A' (Interpreted geological and hydrogeological conditions) with PHC analysis and exceedances in soil.
- Figure 6A: Cross-Section B-B' (Interpreted geological and hydrogeological conditions) with metals analysis and exceedances in soil.
- Figure 6B: Cross-Section B-B' (Interpreted geological and hydrogeological conditions) with PAH analysis and exceedances in soil.
- Figure 6C: Cross-Section B-B' (Interpreted geological and hydrogeological conditions) with PHC analysis and exceedances in soil.
- Figure 7: Conceptual Site Model Potential Receptor Pathways (Pre-Remediation)

In addition, following figures are associated with the remediation report (included in Appendix G):

- Figure G1: Remedial Excavations at the RSC Property
- Figure G2a: Cross-Section C-C' with metals analysis and exceedances in soil at TP31 remediation
- Figure G3a: Cross-Section D-D' with metals analysis and exceedances in the sewer trench remediation
- Figure G3b: Cross-Section D-D' with PAH analysis and exceedances in the sewer trench remediation
- Figure G3c: Cross-Section D-D' with PHC analysis and exceedances in the sewer trench remediation
- Figure G4a: Cross-Section E-E' with PHC analysis and exceedances in soil at BLD 126-1 remediation
- Figure G5a: Cross-Section F-F' with PAH analysis and exceedances in soil at BLD 126-2 remediation
- Figure G5b: Cross-Section F-F' with PHC analysis and exceedances in soil at BLD 126-2 remediation

The figures were prepared using data from the RSC Property and supplemented with off-Site data from the remediation areas which spanned both on- and off-Site of the RSC Property.

## 8.1 Physical Setting

The RSC Property consisted of a 4.89-hectare parcel of currently vacant land that consisted of a few old, paved roadways associated with the former CFB Rockcliffe military base. There were no structures currently present on the Site. Historically, the RSC Property was occupied by a series of buildings and structures associated with the former military base and were used for:

- Building 8: Office – Chaplain's office
- Building 9: Office – Special investigation department
- Building 10: Office – Eastern section investigation department
- Building 11: Ground telecom transmission site
- Building 70: Residential: Airwomens' barracks
- Building 71: Residential: NCO barracks

- Building 124: Office: ground training offices
- Building 126: transmission tower

The surrounding properties to the north, east and west are undeveloped and the properties to the south and southwest are under development for parkland and residential housing. Historically, the surrounding lands were also developed as part of the military activities associated with CFB Rockcliffe with buildings for commercial use including lounge (building 15), hospital (building 134), medical storage (building 176), other storage (buildings 178 and 179), and an indoor swimming pool (building 137).

### Stratigraphy

A representative geologic cross-section of the Site is presented in Figures 5A to 6C. In general, the subsurface soil conditions encountered in the boreholes and test pits consisted of surficial topsoil and fill of variable depths (up to 3.05 mbgs at borehole 22-04), with predominantly gravelly silty sand that extend to the maximum depth of investigation (7.92 mbgs at 22-04). At numerous investigation locations, silt and clays interbedded with sands and gravels were observed in the fill and glacial till layers.

### Depth to Bedrock

Bedrock was encountered in five of the six boreholes advanced during the Phase Two ESA with depth ranging between 0.61 and greater than 7.92 mbgs. Given that the average thickness of overburden at the Site is less than 2 m, the RSC Property is considered a shallow soil property as defined by O.Reg. 153/04 (as amended).

### Subsurface Structures and Utilities

A storm and sanitary sewer line runs north-south through the RSC Property which connects the newly developed areas to the south of the Site to a stormwater pond north of the Site. Based on the review of a cross-section drawing, this sewer line excavation and associated backfill materials extends to a depth of approximately 9 mbgs or 78 masl. The drawing notes clay dykes were installed in the trench to reduce groundwater migration along the sewer trench.

At the time of the Phase Two ESA and remedial excavations, public and private utility locates were completed to clear the borehole and test pit locations. Underground utility drawings and review of previous subsurface investigation did not indicate presence of any other buried utilities within the RSC Property. In addition, no groundwater impacts were identified on the RSC Property indicating that migration of COCs via subsurface utilities and structure including the sewer trench is not considered an issue of concern for the Site. Furthermore the identified sewer does not extend or intersect the documented off-Site groundwater impacts at former building 137.

### Groundwater Levels and Flow Direction

The local and regional groundwater flow direction is expected to be north following the considerable drop in ground surface elevation towards the Ottawa River to the north. It is anticipated that the storm and sanitary sewer may be influencing the groundwater elevations in the area near the sewer, and that localized flow towards the sewer maybe occurring.

Static groundwater levels were measured in the monitoring wells (except for 22-03 which was dry) located across the Site on July 18, 2022. Figure 2 shows groundwater elevations and the interpreted groundwater flow direction. Groundwater elevations ranged from 77.57 to 82.14 masl (7.33 to 9.44 mbgs), on July 18, 2022. Groundwater is contained within the bedrock aquifer.



## Hydraulic Gradients

The horizontal hydraulic gradient was estimated for groundwater conditions based on water levels collected on July 18, 2022, and the inferred groundwater contours are presented on Figure 2. The horizontal hydraulic gradient for groundwater conditions was 0.043 m/m. Vertical hydraulic gradients were not calculated as no COC were identified in groundwater exceeding the site condition standards and as such, no nested monitoring well pairs were installed.

## Groundwater Velocity

Groundwater flow velocity was determined based on the hydraulic conductivity of  $1.5 \times 10^{-11}$  m/s (source: [https://structx.com/Soil\\_Properties\\_006.html](https://structx.com/Soil_Properties_006.html)) and assumed porosity of 20% for limestone (source: [http://worthingtongroundwater.com/?page\\_id=131#:~:text=Most%20flow%20in%20bedrock%20aquifers,in%20the%20range%200.01%2D0.4](http://worthingtongroundwater.com/?page_id=131#:~:text=Most%20flow%20in%20bedrock%20aquifers,in%20the%20range%200.01%2D0.4)), and the hydraulic gradient. The groundwater flow velocity within limestone was calculated to be  $3 \times 10^{-12}$  m/s. Note that the actual groundwater velocity may vary significantly not only because of the variability of the hydraulic gradient, but also because of the variability of the hydraulic conductivity due to presence of the sewer trench excavation on the RSC Property.

## SITE CONDITION STANDARDS

### Non-Potable Groundwater Standards

Non-potable groundwater standards are applicable to the Site as:

- Potable water at the Site and the surrounding area within 250 m of the RSC Property is provided by the City of Ottawa and no potable water wells were identified on the RSC Property or within 250 m of the RSC Property.
- The Site standards being applied are not agricultural or other type of property use.
- WSP has given written notice of the intention to apply the standards to the municipality and has not received any written notice that the municipality objects to the use of these standards of the request made more than 30 days ago. The request sent to the municipality is attachment to this report.

### Environmentally Sensitive Areas

An area of natural significance was identified on or within 30m of the Site due to presence of bat habitat potentially used by endangered bat species (brown myotis) as well as documented butternut trees to the north and east of the Site. As such the RSC Property is considered an environmentally sensitive area.

Two soil samples were submitted for pH analysis. The reported pH of all samples met the requirements that the pH of surface soil is  $5 \leq \text{pH} \leq 9$  and the pH of sub-surface soil is  $5 \leq \text{pH} \leq 11$ .

Accordingly, Section 41 of the Regulation applies to the RSC Property due to the presence of an environmentally sensitive area on and adjacent to the RSC Property.

### Shallow Soil Property or Water Body

Bedrock was encountered during the Phase Two investigation in five of the six borehole locations with depths ranging between 0.61 and 7.92 mbgs. Given that the average thickness of overburden at the Site is less than 2 m, the Site is considered to be a shallow soil property as defined by O.Reg. 153/04 (as amended). The deeper overburden was encountered within the suspected trench excavated for the sewer trench installation.

The property does not include all or part of a water body and is not adjacent to a water body or include land that is within 30 metres of a water body. Accordingly, Section 43.1 of the Regulation does not apply to the RSC Property.

### **Imported Soil**

As identified in the Phase One ESA, fill may be present under the entire footprint of the RSC Property, resulting from past development and demolition activities, primarily in the areas for previous buildings and infrastructure such as the sewer trench. This fill was present at time of the Phase Two ESA. Backfill imported to the RSC property during the remediation work included soil fill from elsewhere in the Wateridge development (Phase 7 to the east of the Site), as discussed in the remediation report in Appendix G. This fill was characterised and validated to the site condition standards following the required in sampling frequency required under Ontario Regulation 406/19 and 153/04, prior to being used on the RSC Property.

### **Proposed Buildings and Other Structures**

No renovations or modifications to the RSC Property has been proposed; however, the Canada Lands Company is considering disposition of the property and a future owner may wish to consider redevelopment of the Phase Two Property to a residential property use. The location of any proposed residential buildings and other structures is unknown.

### ***Naturally Occurring Metals - Reliance on 49.1 - Applicable Standards Deemed to be Met***

Exceedances of barium, chromium, cobalt, and vanadium in the soil samples were considered to have resulted from naturally occurring elevated concentrations due to the presence clay in the fill layer. The concentrations present were within the range of typical of the marine clays of eastern Ontario. As such the metals are considered to be natural in origin and within typical background levels for the Ottawa area and are therefore not an exceedance of the site condition standards. A rationale for such naturally occurring metals above the MECP Table 1 Standards is appended to this report (Appendix F). The qualified person has determined these exceedances do not exceed the naturally occurring range of concentrations typically found within the area where the property is located as outlined in Section 49.1.3 in O.Reg 153.

These locations and the associated concentrations are provided on Figure 4A and the relevant cross sections.

## **POTENTIAL SOURCES OF CONTAMINATION**

### **Potentially Contaminating Activities (PCAs) and Areas of Potential Environmental Concern (APECs)**

Based on the information obtained as part of the Phase One ESA, the following PCAs were identified that were inferred to result in APECs for the RSC Property, as shown in Figure 2:

**Table D: APECs and Associated PCAs Identified in the Phase One ESA**

| PCA and Description of the Activity   | APEC   | Location of APEC on the Site (Figure 2) | Contaminants of Potential Concern    | Media Potentially Impacted (groundwater, soil and/or sediment) | Rationale for Potential Contribution of the PCA to an APEC  |
|---|--|---|--------------------------------------|--|---|
| Importation of fill material of unknown quality (PCA 30)<br>Use of imported fill during initial development and subsequent redevelopment activities at the Site   | <b>APEC 1</b> - Potential for subsurface impacts due to the presence of impacted fill on the Site.   | Site-wide                               | PHC F1 to F4, BTEX, PAHs, and metals | Soil   | Presence of imported fill of unknown quality across the Site makes this on-Site PCA an APEC.  |
| Gasoline and Associated Products Storage in Fixed Tanks (PCA 28)<br>Off-Site former fuel storage tanks (one AST and one UST) associated with swimming pool in former Building 137 as well as associated groundwater impacts | <b>APEC 2</b> - Potential for groundwater impacts migrating on to the Site from the off-Site former fuel storage tanks associated with the swimming pool operation in former Building 137. | Central portion of the Site             | PHC F1 to F4, BTEX, and PAHs         | Groundwater  | Presence of former fuel storage tanks within 50 m of the RSC Property as well as documented impacts to groundwater located upgradient of the Site makes this off-Site PCA an APEC for the Site. |

**Findings of the Phase Two ESA with Respect to the APECs and Associated PCAs**

To address the APECs and PCAs identified at the Site, soil and groundwater sampling and analysis for potential COCs were completed as part of this Phase Two ESA and previous Phase Two ESAs. A summary of the findings of the Phase Two ESA with respect to the APECs and associated PCAs identified by the Phase One ESA with respect to the Site is provided in the table below.

**Table E: Phase Two ESA Investigation Results for Each APEC**

| APEC | PCA  | Summary of Phase Two ESA Program   | Summary of Exceedances (pre-remediation)   | Summary of Exceedances (post-remediation)   |
|------|--|--|--|---|
| #1   | #30. Importation of Fill Material of Unknown Quality | <p>In 2014, five samples (TP61 SGS1, TP62 SGS1, TP126-1 S1, TP126-2 S1, BHMW14 SS2) were analyzed for PHC F1 to F4, BTEX, PAHs and metals.</p> <p>In 2020, seven soil samples (TP4-01 SA1, TP4-02 SA1, TP4-10 SA1, TP4-12 SA1, TP4-13 SA1, TP4-15 SA1, TP4-16 SA1) from a test pit program were analyzed for PHC F1 to F4, BTEX, PAHs and metals.</p> <p>In 2022, seven soil samples (BH22-02 SA1, BH22-03 SA1, BH22-03 SA2, BH22-04 SA2, BH22-04 SA7, BH22-05 SA2, BH22-06 SA1) and a field duplicate of BH22-04 SA2 were analyzed for PHC F1 to F4, BTEX, PAHs and metals to investigate the identified APEC.</p> <p>During the delineation test pit program in October 2022, twenty (20) soil samples</p> | <p>Three samples (TP61 SGS1, TP62 SGS1, BHMW15 SS5) had exceedance of PHCs.</p> <p>Two samples (TP62 SGS1 and BHMW15 SS5) exceeded MECP Table 1 standards for several PAHs.</p> <p>No exceedances in the soil samples from 2020 for any of the parameters analyzed.</p> <p>BH22-03 SA2 and field duplicate of BH22-04 SA2 exceeded for several PAHs (anthracene, benz(a)anthracene, benzo(b)fluoranthene, fluoranthene, pyrene).</p> | <p>None, given all the samples with exceedances were subsequently removed and revalidated as part of the remediation.</p> <p>No exceedance for groundwater.</p> |

| APEC | PCA   | Summary of Phase Two ESA Program   | Summary of Exceedances (pre-remediation)   | Summary of Exceedances (post-remediation) |
|------|---|--|--|---|
|      |   | <p>were analyzed to delineate the impacted fill associated with the sewer trench. These samples included TP22-01 SA1, TP22-01 SA2, TP22-01 SA3, TP22-02 SA1, TP22-02 SA2, TP22-02 SA3, TP22-03 SA1, TP22-03 SA2, TP22-04 SA1, TP22-04 SA2, TP22-04 SA3, TP22-05 SA1, TP22-05 SA2, TP22-05 SA3, TP22-06 SA1, TP22-06 SA2, TP22-06 SA3, TP22-07 SA1, TP22-07 SA2, and TP22-07 SA3</p> <p>In July 2022, four groundwater samples (22-02, 22-04, 22-05 and 22-06) and a field duplicate of 22-04 in 2022 was analyzed for PHC F1 to F4, BTEX, PAHs and metals.</p> | <p>TP22-01 SA3 and TP22-02 SA2 exceeded for PHC F4 and F2, respectively.</p> <p>TP22-02 SA1, TP22-04 SA2 and TP22-06 SA3 had exceedances of acenaphthene, acenaphthylene, anthracene, benzo(a)anthracene, benzo(a)pyrene, benzo(b)fluoranthene, fluoranthene, and/or phenanthrene.</p> <p>No exceedances in any of the groundwater samples analyzed.</p> |   |
| #2   | #28 Gasoline and Associated Products Storage in Fixed Tanks | <p>Four groundwater samples (22-02, 22-04, 22-05 and 22-06) and a field duplicate of 22-04 in 2022 was analyzed for PHC F1 to F4, BTEX, PAHs and metals.</p>   | <p>No exceedances in any of the groundwater samples analyzed.</p>  | <p>No exceedance in groundwater.</p>      |

### Summary of Current Site Condition – Pre-Remediation

The summary of the soil and groundwater conditions at the Site based on the results of the Phase Two ESA, by stratigraphic layer and media, is presented below. The soil samples submitted for analysis are presented on Figures 4A through 6C and Figures G2A through G5B. The groundwater samples submitted for analysis are presented on Figures 3A to 3C.

- **Fill (soil)** – A total of thirty-five (35) fill/reworked native samples identified in Table 4 were analyzed for PHC F1 to F4, BTEX, PAHs and/or metals as part of the WSP 2022 Phase Two ESA. In addition, previous investigations included five samples that were analyzed for PHC F1 to F4, BTEX, PAHs and/or metals. Altogether, six of these samples exceeded applicable MECF Table 1 Standards for PHCs, and seven samples exceeded for various PAHs. The exceedances were limited to three distinct areas:
  - Two separate areas near former Building 126 on the east portion of the RSC Property.
  - One area in the recently constructed sewer trench, west of the former off-Site Building 137.

These impacts were located entirely within the fill materials and were found at depths up to 3.8 mbgs.

- **Groundwater** – Groundwater quality assessment included sampling of 4 monitoring wells in 2022, which were installed around at the boundary of the RSC Property adjacent to the off-Site PCA. Table 4 summarized the groundwater analyses performed. Concentrations of PHC F1 to F4, BTEX, PAHs and metals in all the samples were below the applicable site condition standards.

## Summary of Current Site Condition – Post-Remediation

Following remediation, all contaminated soil was removed from the Site. The verification sampling program included the collection of samples as per the guidance for sampling and analysis frequency is provided in O. Reg 153/04, as amended, Schedule E, Table 3 (Minimum Confirmation Sampling Requirements for Excavation). All the validation samples met the applicable MECP Table 1 Standards. As a result, no contaminated soil above the applicable site conditions standards remains on the Site.

No groundwater remediation was required and completed at the Site

## DELINEATION OF CONTAMINANT IMPACTS

### APEC Where Contaminants are Present at a Concentration Above the Applicable Site Condition Standard

The reported concentrations of all soil and groundwater samples submitted for analysis following the completion of the remedial excavation indicate that soil and groundwater quality meets the applicable site condition standards. Any soil sample with exceedance identified have been remediated and removed from the RSC Property. Impacts present before remediation were located within the fill and were above the groundwater table. The fill around and below each impacted sample was removed to either bedrock or validated clean excavation floor with validated clean excavation walls.

### Contaminant Distribution

No contaminants were present in soil, groundwater or sediment samples at a concentration greater than the applicable site condition standards following remediation. As indicated above, no groundwater impacts were present on the RSC Property and all of the remediated soil impacts were limited to the shallow fill, primarily in areas where former buildings and infrastructure were present.

### Potential Reason for Discharge into the Environment at the Site

Impacts at the property were limited to the fill and are the result of building demolition activities and resulting mixing of debris with the fill in areas where former buildings and infrastructure were present. Off-Site impacts originated from a historical release from off-Site fuel storage.

### Contaminant Migration

Fill impacts (pre-remediation) were delineated to the upper fill and not in contact with groundwater, nor found to be present in the groundwater and therefore were considered to be immobile. These have subsequently been remediated.

Off-Site, the PCA resulting in APEC 2 had resulted in localized soil impacts off-Site and was found to have entered bedrock up to the groundwater table. These impacts were found to have migrated to the north, east and west of the former tanks within the bedrock. As discussed, monitoring wells on the RSC Property confirmed the off-Site impacts in groundwater had not migrate onto the RSC Property and off-Site remediation work for these impacts was undertaken in 2022 and have removed these residual groundwater impacts and the potential for future migration onto the RSC Property.

### Meteorological and Climatic Considerations

Seasonal fluctuation in water levels on the Site should be expected. Given the limited number of monitoring events seasonal trends could not be identified. Shallow groundwater water levels are typically highest following the spring recharge and decline throughout the summer and fall months into the winter.

## Soil Vapour Intrusion Pathways

No contaminants in soil or groundwater were identified in exceedance of applicable MECP site condition standards following remediation activities and therefore vapour intrusion is not a concern for future buildings at the site.

## CROSS-SECTIONS

### Lateral and Vertical Distribution of Contaminants

A representative cross-section is presented in Figure 5A to 6C.

## POTENTIAL EXPOSURE PATHWAYS AND RECEPTORS

Following the remediation, no contaminants were present at concentrations greater than the applicable site condition standards and therefore potential release and transport mechanisms, exposure pathways and human and ecological receptors are not considered further.

## 9.0 REMEDIATION

Remediation of impacted soil (4,630 m<sup>3</sup>) identified on the RSC property was conducted and details of the remediation work including sampling density, soil removal and backfilling are included in Appendix G (Remediation Report). The validation sampling following removal of the impacted soil met the minimum sampling density requirements outlined in Table 3 of Schedule E of O.Reg. 153/04. No groundwater was observed entering the remedial excavation.

## 10.0 CONCLUSIONS

The Phase Two ESA investigated the two APECs identified in the Phase One ESA.

Based on the results of the soil (APEC 1 - fill) and groundwater (Apec 2 – off-site PHC and PAH exceedances in groundwater) samples submitted as part of this Phase Two ESA and following remediation, the reported concentrations of the contaminants of potential concern were below the applicable site condition standards as of the certification date (December 14, 2022). No risk assessment or further remediation is required prior to the submission of a RSC.

The data presented in this report follows the O. Reg. 153/04 Phase Two ESA report format.

## 11.0 SIGNATURES

The undersigned Qualified Person confirms that he/she was responsible for conducting and/or supervising this Phase Two ESA and the associated findings and conclusions.

We trust that you will find the contents of this report satisfactory for your current needs. Should you require clarification of the information provided, please do not hesitate to contact the undersigned.

**WSP Canada Ltd.**



Shihan Chowdhury, P.Eng.  
*Environmental Engineer*



Keith Holmes, BSc (Hons), I  
*Principal Geoscientist, Contaminated Sites*




SAC/LT/KPH/ha/sg

[https://golderassociates.sharepoint.com/sites/110705/project\\_files/6\\_deliverables/phase\\_two\\_esas/phase\\_two\\_esa\\_-\\_phase\\_4-1\\_rsc/phase\\_two\\_esa\\_report/19124906\\_clc\\_phase\\_two\\_esa\\_phase\\_4\\_rsc\\_final.docx](https://golderassociates.sharepoint.com/sites/110705/project_files/6_deliverables/phase_two_esas/phase_two_esa_-_phase_4-1_rsc/phase_two_esa_report/19124906_clc_phase_two_esa_phase_4_rsc_final.docx)

## Figures





- LEGEND**
- TEST PIT LOCATION (GOLDER/WSP, 2022)
  - MONITORING WELL LOCATION (GOLDER, 2022)
  - TEST PIT LOCATION (GOLDER, 2020)
  - MONITORING WELL LOCATION (GOLDER, 2019)
  - BOREHOLE/MONITORING WELL LOCATION (DST, 2015)
  - BOREHOLE/MONITORING WELL LOCATION (DST, 2009)
  - TEST PIT LOCATION (DST, 2009)
  - TEST PIT LOCATION (GREENBANK, 2004)
  - STORM SEWER ALIGNMENT
  - SANITARY SEWER ALIGNMENT
  - FORMER FUEL STORAGE TANKS (PCA #28): REMOVED IN 1992 AND LOCATION IS INFERRED BASED ON THE LEVEL OF CONTAMINATION OBSERVED
  - HISTORICAL RESIDENTIAL BUILDING FOOTPRINT
  - HISTORICAL BUILDING FOOTPRINT
  - PHASE TWO PROPERTY AND RSC BOUNDARY
  - 2022 REMEDIATION (WSP 2022)
  - HISTORICAL REMEDIATION (DST 2014/15)
  - APEC 1 (PCA #30)
  - APEC 2 (ASSOCIATED WITH PCA #28)

| Areas of Potential Environmental Concern ("APEC") |  |      |
|---|--|------|
| APEC#   | Detail   | PCA# |
| 1   | Fill of unknown quality, including building demolition waste, expected to be present across the entire Site.                                     | 30   |
| 2   | Former fuel storage tanks (one AST and one UST) associated with former swimming pool in Building 137 and associated soil and groundwater impacts | 28   |

**REFERENCE(S)**  
 1. COORDINATE SYSTEM: NAD 1983 MTM 9



CLIENT  
CLC LIMITED


PROJECT  
PHASE TWO ENVIRONMENTAL SITE ASSESSMENT, WATERIDGE VILLAGE PHASE 4, PART OF 1076 HEMLOCK PRIVATE, OTTAWA, ONTARIO

TITLE  
**SITE PLAN WITH FORMER BUILDINGS AND AREAS OF POTENTIAL ENVIRONMENTAL CONCERN**

CONSULTANT


|            |            |
|------------|------------|
| YYYY-MM-DD | 2023-01-20 |
| DESIGNED   | ----       |
| PREPARED   | JEM        |
| REVIEWED   | TL         |
| APPROVED   | KPH        |

PROJECT NO. 19124906 CONTROL 0015 REV. 0 FIGURE 1



Path: S:\Clients\Canada\_Lands\_Company\Wateridge\_Village\99\_FR001\19124906\_GLC\_Enviro\0015\_PhaseTwo\_ESA\_Phase4\_119124906\2015-HS-0001.mxd


25mm IF THIS MEASUREMENT DOES NOT MATCH WHAT IS SHOWN, THE SHEET SIZE HAS BEEN MODIFIED FROM:



**LEGEND**

- TEST PIT LOCATION (GOLDER/WSP, 2022)
- MONITORING WELL LOCATION (GOLDER, 2022)
- TEST PIT LOCATION (GOLDER, 2020)
- MONITORING WELL LOCATION (GOLDER, 2019)
- BOREHOLE/MONITORING WELL LOCATION (DST, 2015)
- BOREHOLE/MONITORING WELL LOCATION (DST, 2009)
- TEST PIT LOCATION (DST, 2009)
- TEST PIT LOCATION (GREENBANK, 2004)
- FLOOR VERIFICATION SAMPLE FROM 2022 REMEDIATION
- WALL VERIFICATION SAMPLE FROM 2022 REMEDIATION
- FLOOR VERIFICATION SAMPLE FROM 2014/15 REMEDIATION
- WALL VERIFICATION SAMPLE FROM 2014/15 REMEDIATION
- STORM SEWER ALIGNMENT
- SANITARY SEWER ALIGNMENT
- GROUNDWATER ELEVATION, mASL
- GROUNDWATER ELEVATION CONTOUR, mASL
- INTERPRETED GROUNDWATER FLOW DIRECTION
- CROSS-SECTION LOCATION
- PHASE TWO PROPERTY AND RSC BOUNDARY
- LOCATION WHERE 2022 REMEDIATION WAS TERMINATED ON BEDROCK
- 2022 REMEDIATION (WSP 2022)
- HISTORICAL REMEDIATION (DST 2014/15)

**REFERENCE(S)**  
 1. COORDINATE SYSTEM: NAD 1983 MTM 9



CLIENT  
 CLC LIMITED

PROJECT  
 PHASE TWO ENVIRONMENTAL SITE ASSESSMENT, WATERIDGE VILLAGE PHASE 4, PART OF 1076 HEMLOCK PRIVATE, OTTAWA, ONTARIO

TITLE  
**GROUNDWATER ELEVATIONS, INTERPRETED SHALLOW GROUNDWATER FLOW DIRECTION, AND CROSS-SECTION LOCATIONS**


|            |            |            |
|------------|------------|------------|
| CONSULTANT | YYYY-MM-DD | 2023-01-20 |
| DESIGNED   | ---        |            |
| PREPARED   | JEM        |            |
| REVIEWED   | TL         |            |
| APPROVED   | KPH        |            |



PROJECT NO. 19124906 CONTROL 0015 REV. 0 FIGURE 2

Path: S:\Clients\Canada\_Limits\_Company\Wateridge\_Village\00\_PRCO\19124906\_CLC\_Emvs\0015\_PhaseTwo\_ESA\_Phase4\_1\19124906-0015-HS-0002.mxd

IF THIS MEASUREMENT DOES NOT MATCH WHAT IS SHOWN, THE SHEET SIZE HAS BEEN MODIFIED FROM: 28mm




**LEGEND**

- MONITORING WELL LOCATION (GOLDER, 2022)
- MONITORING WELL LOCATION (GOLDER, 2019)
- BOREHOLE/MONITORING WELL LOCATION (DST, 2015)
- BOREHOLE/MONITORING WELL LOCATION (DST, 2009)
- MEETS MECP TABLE 1 STANDARDS
- STORM SEWER ALIGNMENT
- SANITARY SEWER ALIGNMENT
- 2022 REMEDIATION (WSP 2022)
- HISTORICAL REMEDIATION (DST 2014/15)
- PHASE TWO PROPERTY AND RSC BOUNDARY

**NOTE(S)**  
 1. ALL DATA IN µg/L  
 2. \*MONITORING WELL DECOMMISSIONED AS PART OF REMEDIAL WORK

**REFERENCE(S)**  
 1. COORDINATE SYSTEM: NAD 1983 MTM 9



CLIENT  
**CLC LIMITED**

PROJECT  
**PHASE TWO ENVIRONMENTAL SITE ASSESSMENT, WATERIDGE VILLAGE PHASE 4, PART OF 1076 HEMLOCK PRIVATE, OTTAWA, ONTARIO**

TITLE  
**METALS ANALYSIS AND EXCEEDANCES IN GROUNDWATER**

|            |            |            |
|------------|------------|------------|
| CONSULTANT | YYYY-MM-DD | 2023-01-16 |
|            | DESIGNED   | ---        |
|            | PREPARED   | JEM        |
|            | REVIEWED   | TL         |
|            | APPROVED   | KPH        |

|             |         |      |        |
|-------------|---------|------|--------|
| PROJECT NO. | CONTROL | REV. | FIGURE |
| 19124906    | 0015    | 0    | 3A     |

Path: S:\Clients\Canada\_Lands\_Company\Wateridge\_Village\00\_PRC\19124906\_CLC\_Env\0015\_PhaseTwo\_ESA\_Phase4\_1\19124906-0015-16-0003A.mxd

IF THIS MEASUREMENT DOES NOT MATCH WHAT IS SHOWN, THE SHEET SIZE HAS BEEN MODIFIED FROM: 28mm



|                           |           |
|---------------------------|-----------|
| Sample ID                 | BHMW15    |
| Date Sampled              | 3/14/2014 |
| Acenaphthene              | 4.2       |
| Anthracene                | 0.58      |
| 1-Methylnaphthalene       | 18        |
| Methylnaphthalene, 2-(1-) | 19        |
| Phenanthrene              | 0.97      |
| Pyrene                    | 0.39      |

**LEGEND**


- MONITORING WELL LOCATION (GOLDER, 2022)
- MONITORING WELL LOCATION (GOLDER, 2019)
- BOREHOLE/MONITORING WELL LOCATION (DST, 2015)
- BOREHOLE/MONITORING WELL LOCATION (DST, 2009)
- MEETS MECP TABLE 1 STANDARDS
- EXCEEDS MECP TABLE 1 STANDARDS
- STORM SEWER ALIGNMENT
- SANITARY SEWER ALIGNMENT
- PHASE TWO PROPERTY AND RSC BOUNDARY

|                           |           |
|---------------------------|-----------|
| Sample ID                 | BHMW15    |
| Date Sampled              | 3/14/2014 |
| Acenaphthene              | 4.2       |
| Anthracene                | 0.58      |
| 1-Methylnaphthalene       | 18        |
| Methylnaphthalene, 2-(1-) | 19        |
| Phenanthrene              | 0.97      |
| Pyrene                    | 0.39      |

EXCEEDANCE REMOVED DURING REMEDIATION

**NOTE(S)**  
1. ALL DATA IN µg/L

**REFERENCE(S)**  
1. COORDINATE SYSTEM: NAD 1983 MTM 9



CLIENT  
**CLC LIMITED**

PROJECT  
PHASE TWO ENVIRONMENTAL SITE ASSESSMENT, WATERIDGE VILLAGE PHASE 4, PART OF 1076 HEMLOCK PRIVATE, OTTAWA, ONTARIO

TITLE  
**PAH ANALYSIS AND EXCEEDANCES IN GROUNDWATER**

|            |            |            |
|------------|------------|------------|
| CONSULTANT | YYYY-MM-DD | 2023-01-16 |
|            | DESIGNED   | ----       |
|            | PREPARED   | JEM        |
|            | REVIEWED   | TL         |
|            | APPROVED   | KPH        |

PROJECT NO. 19124906 CONTROL 0015 REV. 0 FIGURE 3B

Path: S:\Clients\Canada\_Lands\_Company\Wateridge\_Village\99\_PRC\19124906\_GLC\_Enviro\0015\_PhaseTwo\_ESA\_Phase4\_119124906\0015-MS-0003B.mxd

25mm IF THIS MEASUREMENT DOES NOT MATCH WHAT IS SHOWN, THE SHEET SIZE HAS BEEN MODIFIED FROM:



**LEGEND**

- MONITORING WELL LOCATION (GOLDER, 2022)
- MONITORING WELL LOCATION (GOLDER, 2019)
- BOREHOLE/MONITORING WELL LOCATION (DST, 2015)
- BOREHOLE/MONITORING WELL LOCATION (DST, 2009)
- MEETS MECP TABLE 1 STANDARDS
- EXCEEDS MECP TABLE 1 STANDARDS
- STORM SEWER ALIGNMENT
- SANITARY SEWER ALIGNMENT
- 2022 REMEDIATION (WSP 2022)
- HISTORICAL REMEDIATION (DST 2014/15)
- PHASE TWO PROPERTY AND RSC BOUNDARY


|                 |           |                                       |
|-----------------|-----------|---------------------------------------|
| Sample ID       | BHMW15    |                                       |
| Date Sampled    | 3/20/2014 | EXCEEDANCE REMOVED DURING REMEDIATION |
| F2 (C10 to C16) | 15,000    |                                       |
| F3 (C16 to C34) | 8,200     |                                       |

|                 |           |                                       |
|-----------------|-----------|---------------------------------------|
| Sample ID       | BHMW15    |                                       |
| Date Sampled    | 3/20/2014 | EXCEEDANCE REMOVED DURING REMEDIATION |
| F2 (C10 to C16) | 15,000    |                                       |
| F3 (C16 to C34) | 8,200     |                                       |

**NOTE(S)**  
1. ALL DATA IN µg/L

**REFERENCE(S)**  
1. COORDINATE SYSTEM: NAD 1983 MTM 9

|                 |            |                                       |
|-----------------|------------|---------------------------------------|
| Sample ID       | 137-3      |                                       |
| Date Sampled    | 07/22/2022 | EXCEEDANCE REMOVED DURING REMEDIATION |
| F2 (C10 to C16) | 940        |                                       |
| F3 (C16 to C34) | 1,000      |                                       |



CLIENT  
**CLC LIMITED**

PROJECT  
**PHASE TWO ENVIRONMENTAL SITE ASSESSMENT, WATERIDGE VILLAGE PHASE 4, PART OF 1076 HEMLOCK PRIVATE, OTTAWA, ONTARIO**


TITLE  
**PHC ANALYSIS AND EXCEEDANCES IN GROUNDWATER**

|            |            |            |
|------------|------------|------------|
| CONSULTANT | YYYY-MM-DD | 2023-01-16 |
|            | DESIGNED   | ----       |
|            | PREPARED   | JEM        |
|            | REVIEWED   | TL         |
|            | APPROVED   | KPH        |

PROJECT NO. 19124906      CONTROL 0015      REV. 0      FIGURE 3C

Path: S:\Clients\Canada\_Lands\_Company\Wateridge\_Village\00\_PRC\19124906\_GLC\_Enviro\0015\_PhaseTwo\_ESA\_Phase4\_119124906\0015-HS-0003C.mxd

25mm IF THIS MEASUREMENT DOES NOT MATCH WHAT IS SHOWN, THE SHEET SIZE HAS BEEN MODIFIED FROM:



**LEGEND**

- TEST PIT LOCATION (GOLDER/WSP, 2022)
- MONITORING WELL LOCATION (GOLDER, 2022)
- TEST PIT LOCATION (GOLDER, 2020)
- MONITORING WELL LOCATION (GOLDER, 2019)
- BOREHOLE/MONITORING WELL LOCATION (DST, 2015)
- BOREHOLE/MONITORING WELL LOCATION (DST, 2009)
- TEST PIT LOCATION (DST, 2009)
- TEST PIT LOCATION (GREENBANK, 2004)
- FLOOR VERIFICATION SAMPLE FROM 2022 REMEDIATION
- WALL VERIFICATION SAMPLE FROM 2022 REMEDIATION
- FLOOR VERIFICATION SAMPLE FROM 2014/15 REMEDIATION
- WALL VERIFICATION SAMPLE FROM 2014/15 REMEDIATION
- MEETS MECP TABLE 1 STANDARDS
- EXCEEDS MECP TABLE 1 STANDARDS BUT INTERPRETED TO BE NATURALLY OCCURRING
- EXCEEDS MECP TABLE 1 STANDARDS
- STORM SEWER ALIGNMENT
- SANITARY SEWER ALIGNMENT
- 2022 REMEDIATION (WSP 2022)
- HISTORICAL REMEDIATION (DST 2014/15)
- PHASE TWO PROPERTY AND RSC BOUNDARY

**EXCEEDANCE REMOVED FROM SITE DURING REMEDIATION**


|              |            |
|--------------|------------|
| Sample ID    | VS-EST-F4  |
| Date Sampled | 2022-11-08 |
| Sample Depth | 2.0        |
| Molybdenum   | 6.1        |

**NOTE(S)**

- ALL DATA IN µg/g
- SAMPLE DEPTH IN METRES BELOW GROUND SURFACE
- <sup>(1)</sup> NO DATE WAS PROVIDED IN THE SOURCE REPORT

**REFERENCE(S)**

- COORDINATE SYSTEM: NAD 1983 MTM 9



**CLIENT**  
CLC LIMITED

**PROJECT**  
PHASE TWO ENVIRONMENTAL SITE ASSESSMENT, WATERIDGE VILLAGE PHASE 4, PART OF 1076 HEMLOCK PRIVATE, OTTAWA, ONTARIO


**TITLE**  
METALS ANALYSIS AND EXCEEDANCES IN SOIL

|            |            |            |
|------------|------------|------------|
| CONSULTANT | YYYY-MM-DD | 2023-01-20 |
| DESIGNED   | ----       |            |
| PREPARED   | JEM        |            |
| REVIEWED   | TL         |            |
| APPROVED   | KPH        |            |

PROJECT NO. 19124906 CONTROL 0015 REV. 0 FIGURE 4A

Path: S:\Clients\Canada\_Lands\_Company\Wateridge\_Village\015\_Phase2\015\_Phase2\ESAs\_Phase4\_119124906\015-HS-0004A.mxd

IF THIS MEASUREMENT DOES NOT MATCH WHAT IS SHOWN, THE SHEET SIZE HAS BEEN MODIFIED FROM: 25mm



|              |             |
|--------------|-------------|
| Sample ID    | VS-WST-WW-1 |
| Date Sampled | 10/27/2022  |
| Sample Depth | 0.9-1.1     |
| Fluoranthene | 0.78        |

|                      |              |
|----------------------|--------------|
| Sample ID            | BH22-04 DUP1 |
| Date Sampled         | 07/11/2022   |
| Sample Depth         | 2.1-2.7      |
| Anthracene           | 0.19         |
| Benz(a)anthracene    | 0.64         |
| Benzo(a)pyrene       | 0.46         |
| Benzo(b)fluoranthene | 0.69         |
| Fluoranthene         | 1.19         |
| Pyrene               | 1.06         |

|                        |            |             |
|------------------------|------------|-------------|
| Sample ID              | VS-EST-SW1 | VS-EST-DUP1 |
| Date Sampled           | 2022-11-03 | 2022-11-03  |
| Sample Depth           | 3.0        | 3.0         |
| Acenaphthene           | --         | 0.17        |
| Anthracene             | --         | 0.62        |
| Benz(a)anthracene      | 0.6        | 1.6         |
| Benzo(a)pyrene         | 0.49       | 1.2         |
| Benzo(b)fluoranthene   | 0.65       | 1.5         |
| Benzo(k)fluoranthene   | --         | 0.58        |
| Dibenz(a,h)anthracene  | --         | 0.17        |
| Fluoranthene           | 0.97       | 2.9         |
| Fluorene               | --         | 0.31        |
| Indeno(1,2,3-cd)pyrene | 0.29       | 0.61        |
| Naphthalene            | --         | 0.49        |
| Phenanthrene           | --         | 2           |
| Pyrene                 | --         | 2.4         |

|                      |             |
|----------------------|-------------|
| Sample ID            | TP22-04 SA2 |
| Date Sampled         | 10/19/2022  |
| Sample Depth         | 2.7-3.0     |
| Acenaphthene         | 0.074       |
| Anthracene           | 0.19        |
| Benz(a)anthracene    | 0.66        |
| Benzo(a)pyrene       | 0.58        |
| Benzo(b)fluoranthene | 0.78        |
| Fluoranthene         | 1.3         |
| Phenanthrene         | 0.74        |

|                   |             |
|-------------------|-------------|
| Sample ID         | TP22-02 SA1 |
| Date Sampled      | 10/19/2022  |
| Sample Depth      | 0.1-2.1     |
| Benz(a)anthracene | 0.39        |
| Benzo(a)pyrene    | 0.32        |
| Fluoranthene      | 0.85        |

|                      |             |
|----------------------|-------------|
| Sample ID            | BH22-03 SA2 |
| Date Sampled         | 07/12/2022  |
| Sample Depth         | 1.5-1.98    |
| Anthracene           | 0.23        |
| Benz(a)anthracene    | 0.6         |
| Benzo(a)pyrene       | 0.43        |
| Benzo(b)fluoranthene | 0.9         |
| Fluoranthene         | 1.47        |
| Pyrene               | 1.24        |

|                   |             |
|-------------------|-------------|
| Sample ID         | TP22-06 SA3 |
| Date Sampled      | 10/19/2022  |
| Sample Depth      | 3.1-3.8     |
| Anthracene        | 0.18        |
| Benz(a)anthracene | 0.41        |
| Benzo(a)pyrene    | 0.33        |
| Fluoranthene      | 0.91        |

|              |             |
|--------------|-------------|
| Sample ID    | BLD126-2 P2 |
| Date Sampled | 16-Sep-14   |
| Sample Depth | 1.0         |
| Acenaphthene | 0.11        |
| Anthracene   | 0.17        |
| Fluoranthene | 0.88        |
| Fluorene     | 0.12        |
| Phenanthrene | 0.94        |

|                |                   |
|----------------|-------------------|
| Sample ID      | BHMW15            |
| Date Sampled   | -- <sup>(1)</sup> |
| Sample Depth   | 2.4-3.0           |
| Acenaphthene   | 0.24              |
| Acenaphthylene | 0.2               |
| Fluorene       | 0.18              |
| Naphthalene    | 1.2               |

|                               |                   |
|-------------------------------|-------------------|
| Sample ID                     | TP62 SGS1         |
| Date Sampled                  | -- <sup>(1)</sup> |
| Sample Depth                  | 0.6-0.9           |
| 1 Methylnaphthalene           | 2                 |
| 2 Methylnaphthalene           | 2                 |
| 1 and 2 Methylnaphthalene (2) | 4                 |

**LEGEND**

- TEST PIT LOCATION (GOLDER/WSP, 2022)
- MONITORING WELL LOCATION (GOLDER, 2022)
- TEST PIT LOCATION (GOLDER, 2020)
- MONITORING WELL LOCATION (GOLDER, 2019)
- BOREHOLE/MONITORING WELL LOCATION (DST, 2015)
- BOREHOLE/MONITORING WELL LOCATION (DST, 2009)
- TEST PIT LOCATION (DST, 2009)
- TEST PIT LOCATION (GREENBANK, 2004)
- FLOOR VERIFICATION SAMPLE FROM 2022 REMEDIATION
- WALL VERIFICATION SAMPLE FROM 2022 REMEDIATION
- FLOOR VERIFICATION SAMPLE FROM 2014/15 REMEDIATION
- WALL VERIFICATION SAMPLE FROM 2014/15 REMEDIATION
- MEETS MECP TABLE 1 STANDARDS
- EXCEEDS MECP TABLE 1 STANDARDS
- STORM SEWER ALIGNMENT
- SANITARY SEWER ALIGNMENT
- 2022 REMEDIATION (WSP 2022)
- HISTORICAL REMEDIATION (DST 2014/15)
- PHASE TWO PROPERTY AND RSC BOUNDARY

**Sample ID** VS-WST-WW-1  
**Date Sampled** 10/27/2022  
**Sample Depth** 0.9-1.1  
**Fluoranthene** 0.78

**EXCEEDANCE REMOVED FROM SITE DURING REMEDIATION**

**NOTE(S)**  
 1. ALL DATA IN µg/g  
 2. SAMPLE DEPTH IN METRES BELOW GROUND SURFACE  
 3. <sup>(1)</sup> NO DATE WAS PROVIDED IN THE SOURCE REPORT

**REFERENCE(S)**  
 1. COORDINATE SYSTEM: NAD 1983 MTM 9

**SCALE**  
 0 15 30 60  
 1:1,500 METRES

**CLIENT**  
 CLC LIMITED

**PROJECT**  
 PHASE TWO ENVIRONMENTAL SITE ASSESSMENT, WATERRIDGE VILLAGE PHASE 4, PART OF 1076 HEMLOCK PRIVATE, OTTAWA, ONTARIO

**TITLE**  
 PAH ANALYSIS AND EXCEEDANCES IN SOIL


**CONSULTANT**  
 WSP

YYYY-MM-DD 2023-01-16  
 DESIGNED ----  
 PREPARED JEM  
 REVIEWED TL  
 APPROVED KPH

**PROJECT NO.** 19124906  
**CONTROL** 0015  
**REV.** 0  
**FIGURE** 4B

Path: S:\Clients\Canada\_Lands\_Comp\Wateridge\_Village\98\_FR00119124906\_G.C.C\_Energy\015\_PhaseTwo\_ESA\_Phase4\_119124906-015-HS-00048.mxd

IF THIS MEASUREMENT DOES NOT MATCH WHAT IS SHOWN, THE SHEET SIZE HAS BEEN MODIFIED FROM: 25mm



**LEGEND**

- TEST PIT LOCATION (GOLDER/WSP, 2022)
- MONITORING WELL LOCATION (GOLDER, 2022)
- TEST PIT LOCATION (GOLDER, 2020)
- MONITORING WELL LOCATION (GOLDER, 2019)
- BOREHOLE/MONITORING WELL LOCATION (DST, 2015)
- BOREHOLE/MONITORING WELL LOCATION (DST, 2009)
- TEST PIT LOCATION (DST, 2009)
- TEST PIT LOCATION (GREENBANK, 2004)
- FLOOR VERIFICATION SAMPLE FROM 2022 REMEDIATION
- WALL VERIFICATION SAMPLE FROM 2022 REMEDIATION
- FLOOR VERIFICATION SAMPLE FROM 2014/15 REMEDIATION
- WALL VERIFICATION SAMPLE FROM 2014/15 REMEDIATION
- MEETS MECP TABLE 1 STANDARDS
- EXCEEDS MECP TABLE 1 STANDARDS
- STORM SEWER ALIGNMENT
- SANITARY SEWER ALIGNMENT
- 2022 REMEDIATION (WSP 2022)
- HISTORICAL REMEDIATION (DST 2014/15)
- PHASE TWO PROPERTY AND RSC BOUNDARY

|                 |            |   |
|-----------------|------------|---|
| Sample ID       | VS-EST-NW1 | EXCEEDANCE REMOVED FROM SITE DURING REMEDIATION |
| Date Sampled    | 2022-11-01 |   |
| Sample Depth    | 2.0        |   |
| F4 (C34 to C50) | 130        |   |

**NOTE(S)**  
 1. ALL DATA IN µg/g  
 2. SAMPLE DEPTH IN METRES BELOW GROUND SURFACE  
 3. <sup>(1)</sup> NO DATE WAS PROVIDED IN THE SOURCE REPORT

**REFERENCE(S)**  
 1. COORDINATE SYSTEM: NAD 1983 MTM 9

|                 |             |
|-----------------|-------------|
| Sample ID       | TP22-01 SA3 |
| Date Sampled    | 10/19/2022  |
| Sample Depth    | 3.2-3.6     |
| F4 (C34 to C50) | 390         |

|                 |                   |
|-----------------|-------------------|
| Sample ID       | TP62 SGS1         |
| Date Sampled    | .. <sup>(1)</sup> |
| Sample Depth    | 0.6-0.9           |
| F2 (C10 to C16) | 2,500             |
| F3 (C16 to C34) | 23,000            |
| F4 (C34 to C50) | 15,000            |

|                 |                   |
|-----------------|-------------------|
| Sample ID       | TP61 SGS1         |
| Date Sampled    | .. <sup>(1)</sup> |
| Sample Depth    | 0.08-0.42         |
| F2 (C10 to C16) | 4,000             |
| F3 (C16 to C34) | 13,000            |
| F4 (C34 to C50) | 18,000            |

CLIENT  
CLC LIMITED

PROJECT  
PHASE TWO ENVIRONMENTAL SITE ASSESSMENT, WATERIDGE VILLAGE PHASE 4, PART OF 1076 HEMLOCK PRIVATE, OTTAWA, ONTARIO

TITLE  
PHC ANALYSIS AND EXCEEDANCES IN SOIL

|            |            |            |
|------------|------------|------------|
| CONSULTANT | YYYY-MM-DD | 2023-01-16 |
| DESIGNED   | ----       |            |
| PREPARED   | JEM        |            |
| REVIEWED   | TL         |            |
| APPROVED   | KPH        |            |



PROJECT NO. 19124906 CONTROL 0015 REV. 0 FIGURE 4C

Path: S:\Clients\Canada\_Lands\_Company\Wateridge\_Village\98\_FR0319124906\_GLC\_Enviro\015\_PhaseTwo\_ESA\_Phase4\_19124906\2015-HS-0004C.mxd

25mm IF THIS MEASUREMENT DOES NOT MATCH WHAT IS SHOWN, THE SHEET SIZE HAS BEEN MODIFIED FROM:




Path: \\pauler.golder.com\projects\19124906\19124906\_0015\19124906\_0015\_Phase4\_1\_1\_Fig Name: 19124906\_0015\_19124906.dwg



- LEGEND**
- PHASE TWO PROPERTY AND RSC BOUNDARY
  - SEWER TRENCH
  - TOPSOIL
  - CLAY
  - SAND and GRAVEL
  - BEDROCK
  - FILL
  - SILTY SAND
  - SAMPLE MEETS MECP TABLE 1 STANDARDS
  - SAMPLE EXCEEDS MECP TABLE 1 STANDARDS BUT INTERPRETED TO BE NATURALLY OCCURRING
  - SAMPLE EXCEEDS MECP TABLE 1 STANDARDS
  - AREA OF REMEDIAL EXCAVATION
  - FLOOR VERIFICATION SAMPLE FROM 2022 REMEDIATION
  - ⊗ WALL VERIFICATION SAMPLE FROM 2022 REMEDIATION
  - FLOOR VERIFICATION SAMPLE FROM 2014/15 REMEDIATION
  - ⊗ WALL VERIFICATION SAMPLE FROM 2014/15 REMEDIATION

**NOTE(S)**

1. ALL LOCATIONS ARE APPROXIMATE.
2. FOR DETAILED STRATIGRAPHY SEE RECORD OF BOREHOLE LOGS.
3. FOR CROSS-SECTION LOCATION SEE FIGURE 2.
4. SAMPLE DEPTH IN METRES BELOW GROUND SURFACE.
5. \*OFF-SITE DATA INCLUDED FOR REFERENCE PURPOSES ONLY



CLIENT  
**CLC LIMITED**

---

PROJECT  
PHASE TWO ENVIRONMENTAL SITE ASSESSMENT, WATERIDGE VILLAGE PHASE 4, PART OF 1076 HEMLOCK PRIVATE, OTTAWA, ONTARIO

TITLE  
**CROSS-SECTION A-A' (INTERPRETED GEOLOGICAL AND HYDROGEOLOGICAL CONDITIONS) WITH METALS ANALYSIS AND EXCEEDANCES IN SOIL**


|            |            |            |
|------------|------------|------------|
| CONSULTANT | YYYY-MM-DD | 2022-12-22 |
| DESIGNED   | ---        | ---        |
| PREPARED   | RS         | ---        |
| REVIEWED   | AW         | ---        |
| APPROVED   | KPH        | ---        |

---

|             |         |      |        |
|-------------|---------|------|--------|
| PROJECT NO. | CONTROL | REV. | FIGURE |
| 19124906    | 0015    | 0    | 5A     |

IF THIS MEASUREMENT DOES NOT MATCH WHAT IS SHOWN, THE SHEET SIZE HAS BEEN MODIFIED FROM A3/B1

Path: \\golder.com\projects\19124906\19124906\_015\19124906\_015\Phase\_4\_1\_1\19124906\_015\_02B.dwg



**LEGEND**

- BOREHOLE/MONITORING IDENTIFIER → 20-01
- GROUNDWATER LEVEL →
- STRATIGRAPHY →
- WELL SCREEN →
- PHASE TWO PROPERTY AND RSC BOUNDARY
- SEWER TRENCH
- TOPSOIL
- CLAY
- SAND and GRAVEL
- BEDROCK
- FILL
- SILTY SAND
- SAMPLE MEETS MECP TABLE 1 STANDARDS
- SAMPLE EXCEEDS MECP TABLE 1 STANDARDS
- ⊗ AREA OF REMEDIAL EXCAVATION
- FLOOR VERIFICATION SAMPLE FROM 2022 REMEDIATION
- ⊗ WALL VERIFICATION SAMPLE FROM 2022 REMEDIATION

**NOTE(S)**

1. ALL LOCATIONS ARE APPROXIMATE.
2. FOR DETAILED STRATIGRAPHY SEE RECORD OF BOREHOLE LOGS.
3. FOR CROSS-SECTION LOCATION SEE FIGURE 2.
4. SAMPLE DEPTH IN METRES BELOW GROUND SURFACE.
5. \*OFF-SITE DATA INCLUDED FOR REFERENCE PURPOSES ONLY

**CLIENT**  
CLC LIMITED

**PROJECT**  
PHASE TWO ENVIRONMENTAL SITE ASSESSMENT, WATERIDGE VILLAGE PHASE 4, PART OF 1076 HEMLOCK PRIVATE, OTTAWA, ONTARIO

**TITLE**  
**CROSS-SECTION A-A' (INTERPRETED GEOLOGICAL AND HYDROGEOLOGICAL CONDITIONS) WITH PAH ANALYSIS AND EXCEEDANCES IN SOIL**

|            |            |            |
|------------|------------|------------|
| CONSULTANT | YYYY-MM-DD | 2022-12-22 |
| DESIGNED   | ---        |            |
| PREPARED   | RS         |            |
| REVIEWED   | AW         |            |
| APPROVED   | KPH        |            |

1:100 VERTICAL METRES


1:1,250 HORIZONTAL METRES

**wsp GOLDER**

|             |         |      |        |
|-------------|---------|------|--------|
| PROJECT NO. | CONTROL | REV. | FIGURE |
| 19124906    | 0015    | 0    | 5B     |

IF THIS MEASUREMENT DOES NOT MATCH WHAT IS SHOWN, THE SHEET SIZE HAS BEEN MODIFIED FROM A3S1B


Path: \\golder\golder\clients\19124906\_CLC\_Env\19124906\_CLC\_Env\19124906\_Phase4\_ESA\_Phase4\_11\_Fig Name: 19124906\_0015\_H5-050C.dwg



**LEGEND**

- BOREHOLE/MONITORING IDENTIFIER → 20-01
- GROUNDWATER LEVEL →
- STRATIGRAPHY →
- WELL SCREEN →
- PHASE TWO PROPERTY AND RSC BOUNDARY
- SEWER TRENCH
- TOPSOIL
- CLAY
- SAND and GRAVEL
- BEDROCK
- FILL
- SILTY SAND
- SAMPLE MEETS MECP TABLE 1 STANDARDS
- SAMPLE EXCEEDS MECP TABLE 1 STANDARDS
- ⊗ AREA OF REMEDIAL EXCAVATION
- FLOOR VERIFICATION SAMPLE FROM 2022 REMEDIATION
- ⊗ WALL VERIFICATION SAMPLE FROM 2022 REMEDIATION

- NOTE(S)**
1. ALL LOCATIONS ARE APPROXIMATE.
  2. FOR DETAILED STRATIGRAPHY SEE RECORD OF BOREHOLE LOGS.
  3. FOR CROSS-SECTION LOCATION SEE FIGURE 2.
  4. SAMPLE DEPTH IN METRES BELOW GROUND SURFACE.
  5. \*OFF-SITE DATA INCLUDED FOR REFERENCE PURPOSES ONLY



CLIENT  
**CLC LIMITED**

---

PROJECT  
PHASE TWO ENVIRONMENTAL SITE ASSESSMENT, WATERIDGE VILLAGE PHASE 4, PART OF 1076 HEMLOCK PRIVATE, OTTAWA, ONTARIO

TITLE  
**CROSS-SECTION A-A' (INTERPRETED GEOLOGICAL AND HYDROGEOLOGICAL CONDITIONS) WITH PHC ANALYSIS AND EXCEEDANCES IN SOIL**


|            |            |            |
|------------|------------|------------|
| CONSULTANT | YYYY-MM-DD | 2022-12-22 |
|            | DESIGNED   | ---        |
|            | PREPARED   | RS         |
|            | REVIEWED   | AW         |
|            | APPROVED   | KPH        |

**wsp GOLDER**

|             |         |      |        |
|-------------|---------|------|--------|
| PROJECT NO. | CONTROL | REV. | FIGURE |
| 19124906    | 0015    | 0    | 5C     |

IF THIS MEASUREMENT DOES NOT MATCH WHAT IS SHOWN, THE SHEET SIZE HAS BEEN MODIFIED FROM A3/B

Path: \\golder.com\projects\19124906\19124906\_0015\19124906\_0015\19124906\_0015-08A.dwg



**LEGEND**

BOREHOLE/MONITORING IDENTIFIER → 20-01

GROUNDWATER LEVEL →

STRATIGRAPHY →

WELL SCREEN →

--- PHASE TWO PROPERTY AND RSC BOUNDARY

SEWER TRENCH

BEDROCK

FILL

SILT

CLAY


SAMPLE MEETS MECP TABLE 1 STANDARDS

SAMPLE EXCEEDS MECP TABLE 1 STANDARDS

AREA OF REMEDIAL EXCAVATION

**NOTE(S)**


1. ALL LOCATIONS ARE APPROXIMATE.
2. FOR DETAILED STRATIGRAPHY SEE RECORD OF BOREHOLE LOGS.
3. FOR CROSS-SECTION LOCATION SEE FIGURE 2.
4. SAMPLE DEPTH IN METRES BELOW GROUND SURFACE.



|   |            |            |
|---|------------|------------|
| CLIENT<br>CLC LIMITED   |            |            |
| PROJECT<br>PHASE TWO ENVIRONMENTAL SITE ASSESSMENT, WATERIDGE VILLAGE PHASE 4, PART OF 1076 HEMLOCK PRIVATE, OTTAWA, ONTARIO            |            |            |
| TITLE<br><b>CROSS-SECTION B-B' (INTERPRETED GEOLOGICAL AND HYDROGEOLOGICAL CONDITIONS) WITH METALS ANALYSIS AND EXCEEDANCES IN SOIL</b> |            |            |
| CONSULTANT  | YYYY-MM-DD | 2022-12-22 |
|   | DESIGNED   | ---        |
|   | PREPARED   | RS         |
|   | REVIEWED   | AW         |
|   | APPROVED   | KPH        |

IF THIS MEASUREMENT DOES NOT MATCH WHAT IS SHOWN, THE SHEET SIZE HAS BEEN MODIFIED FROM ANS/B

Path: \\golder.com\projects\19124906\19124906\_0015\Phase4\_ESA\_Phase4\_11\Fig Name: 19124906\_0015-15-08B.dwg



**LEGEND**

BOREHOLE/MONITORING IDENTIFIER → 20-01

GROUNDWATER LEVEL →

STRATIGRAPHY →

WELL SCREEN →

--- PHASE TWO PROPERTY AND RSC BOUNDARY

SEWER TRENCH

BEDROCK

FILL

SILT

CLAY

○ SAMPLE MEETS MECP TABLE 1 STANDARDS


● SAMPLE EXCEEDS MECP TABLE 1 STANDARDS

▨ AREA OF REMEDIAL EXCAVATION

● FLOOR VERIFICATION SAMPLE FROM 2014/15 REMEDIATION

⊗ WALL VERIFICATION SAMPLE FROM 2014/15 REMEDIATION

- NOTE(S)**
1. ALL LOCATIONS ARE APPROXIMATE.
  2. FOR DETAILED STRATIGRAPHY SEE RECORD OF BOREHOLE LOGS.
  3. FOR CROSS-SECTION LOCATION SEE FIGURE 2.
  4. SAMPLE DEPTH IN METRES BELOW GROUND SURFACE.




|  |            |            |
|--|------------|------------|
| CLIENT<br>CLC LIMITED  |            |            |
| PROJECT<br>PHASE TWO ENVIRONMENTAL SITE ASSESSMENT, WATERIDGE VILLAGE PHASE 4, PART OF 1076 HEMLOCK PRIVATE, OTTAWA, ONTARIO         |            |            |
| TITLE<br><b>CROSS-SECTION B-B' (INTERPRETED GEOLOGICAL AND HYDROGEOLOGICAL CONDITIONS) WITH PAH ANALYSIS AND EXCEEDANCES IN SOIL</b> |            |            |
| CONSULTANT   | YYYY-MM-DD | 2022-12-22 |
|  | DESIGNED   | ---        |
|  | PREPARED   | RS         |
|  | REVIEWED   | AW         |
|  | APPROVED   | KPH        |

|                         |                 |           |              |
|-------------------------|-----------------|-----------|--------------|
| PROJECT NO.<br>19124906 | CONTROL<br>0015 | REV.<br>0 | FIGURE<br>6B |
|-------------------------|-----------------|-----------|--------------|

IF THIS MEASUREMENT DOES NOT MATCH WHAT IS SHOWN, THE SHEET SIZE HAS BEEN MODIFIED FROM A4/B

Path: \\golder.com\projects\19124906\19124906\_Cross-Section\_B-B'.dwg




**LEGEND**

- BOREHOLE/MONITORING IDENTIFIER → 20-01
- GROUNDWATER LEVEL →
- STRATIGRAPHY →
- WELL SCREEN →
- PHASE TWO PROPERTY AND RSC BOUNDARY
- SEWER TRENCH
- BEDROCK
- FILL
- SILT
- CLAY
- SAMPLE MEETS MECP TABLE 1 STANDARDS
- SAMPLE EXCEEDS MECP TABLE 1 STANDARDS
- ⊗ AREA OF REMEDIAL EXCAVATION
- FLOOR VERIFICATION SAMPLE FROM 2014/15 REMEDIATION
- ⊗ WALL VERIFICATION SAMPLE FROM 2014/15 REMEDIATION

**NOTE(S)**

- ALL LOCATIONS ARE APPROXIMATE.
- FOR DETAILED STRATIGRAPHY SEE RECORD OF BOREHOLE LOGS.
- FOR CROSS-SECTION LOCATION SEE FIGURE 2.
- SAMPLE DEPTH IN METRES BELOW GROUND SURFACE.



CLIENT  
CLC LIMITED

---

PROJECT  
PHASE TWO ENVIRONMENTAL SITE ASSESSMENT, WATERIDGE VILLAGE PHASE 4, PART OF 1076 HEMLOCK PRIVATE, OTTAWA, ONTARIO


TITLE  
**CROSS-SECTION B-B' (INTERPRETED GEOLOGICAL AND HYDROGEOLOGICAL CONDITIONS) WITH PHC ANALYSIS AND EXCEEDANCES IN SOIL**

|            |            |            |
|------------|------------|------------|
| CONSULTANT | YYYY-MM-DD | 2022-12-22 |
| DESIGNED   | ---        |            |
| PREPARED   | RS         |            |
| REVIEWED   | AW         |            |
| APPROVED   | KPH        |            |

IF THIS MEASUREMENT DOES NOT MATCH WHAT IS SHOWN, THE SHEET SIZE HAS BEEN MODIFIED FROM A4/B

# Potential Receptor Pathways, RSC , Phase 4 Wateridge Village, Ottawa, Ontario

## FIGURE 7



Notes:

1. This diagram indicates all potential pathways which were considered to have the potential to result in exposure of contaminants by receptors at the Site pre-remediation.
2. Remediation at the Site consisted of the excavation of contaminated soil.
3. Post-remediation all soil related pathways are considered to be incomplete given that contaminated soil is no longer present at the Site, denoted by the "X".



**APPENDIX A**

**Survey Plan**



**PLAN OF SURVEY OF**  
**Part of PIN 04273-1205, Being**  
**PART OF LOTS 23 and 24**  
**CONCESSION 1 ( OTTAWA FRONT )**  
**Geographic Township of Gloucester**  
**CITY OF OTTAWA**  
 Surveyed by Annis, O'Sullivan, Vollebek Ltd.

Scale 1 : 1000

**Metric**  
 DISTANCES AND COORDINATES SHOWN ON THIS PLAN  
 ARE IN METRES AND CAN BE CONVERTED TO FEET BY  
 DIVIDING BY 0.3048.

**Surveyor's Certificate**  
 I CERTIFY THAT:  
 1. This survey and plan are correct and in accordance with the Surveys  
 Act and the Surveyors Act and the regulations made under them.  
 2. The survey was completed on the 13th day of October 2022.

October 13, 2022  
 Andrew J. Brotham  
 Ontario Land Surveyor

**Notes & Legend**

|       |        |                                  |
|-------|--------|----------------------------------|
| □     | Dentes | Survey Monument Planted          |
| •     | •      | Survey Monument Found            |
| SIB   | •      | Standard Iron Bar                |
| SSIB  | •      | Short Standard Iron Bar          |
| IB    | •      | Iron Bar                         |
| •     | •      | Horizontal Control Monument      |
| (WTT) | •      | Witness                          |
| (AOS) | •      | Annis, O'Sullivan, Vollebek Ltd. |
| M     | •      | Measured                         |
| (P1)  | •      | (AOG) Plan, September 27, 2021   |

Site Area = 4.890 Hectares

Distances shown on this plan are ground distances and can be converted to grid distances by multiplying by the combined scale factor of 0.999947.

Bearings are grid, derived from part of the northerly limit of Plan 4R-29378, shown to be N 66°08'50" E, thereon and are referred to the Central Meridian of MTM Zone 9 (76°30' West Longitude) NAD-83 (original).

Coordinates are derived from Can-Net 2016 Real Time Network GPS observations referenced to Specified Control Points 01919680105 and 01918434781, MTM Zone 9 (76°30' West Longitude) NAD-83 (original).

Coordinate values are to urban accuracy in accordance with O. Reg. 216/10.

|                |          |            |         |           |
|----------------|----------|------------|---------|-----------|
| • 01919680105  | Northing | 5024915.16 | Easting | 373971.65 |
| • 019196843781 | Northing | 5036178.12 | Easting | 372436.11 |
| • Point A      | Northing | 5035408.34 | Easting | 372044.89 |
| • Point B      | Northing | 5035544.74 | Easting | 372813.57 |
| • Point C      | Northing | 5035371.94 | Easting | 372538.16 |
| • Point D      | Northing | 5035214.58 | Easting | 372250.94 |

Caution: Coordinates cannot, in themselves, be used to re-establish corners or boundaries shown on this plan.


**Elevation Note:**

1. Elevations are geodetic, referred to City of Ottawa Vertical Bench Mark No. 396 (01919680138), having an elevation of 95.06 metres.

ASSOCIATION OF ONTARIO  
 LAND SURVEYORS  
 PLAN SUBMISSION FORM  
 V-36284

THIS PLAN IS NOT VALID UNLESS  
 IT IS AN EMBOSSED ORIGINAL  
 COPY ISSUED BY THE SURVEYOR  
 IN ACCORDANCE WITH  
 Regulation 1026, Section 25 (3)

**ANNIS, O'SULLIVAN, VOLLEBEK LTD.**  
 14 Concession Gate, Suite 500  
 Nepean, Ont. K2E 7S6  
 Phone: (613) 727-0850 Fax: (613) 727-1079  
 Email: [annis@annisvollebek.com](mailto:annis@annisvollebek.com)



Path: S:\Clients\Canada\_Lands\_Company\Weldridge\_Village\09\_PRCO1019124908\_CLC\_Empire0015\_PhasTwo\_ESA\_Phase4\_1\SurveyPlan.mxd

IF THIS MEASUREMENT DOES NOT MATCH WHAT IS SHOWN, THE SHEET SIZE HAS BEEN MODIFIED FROM: 28mm

**APPENDIX B**

**Sampling and Analysis Plan**

## SAMPLING AND ANALYSIS PLAN

**DATE** June 2022

**Project No.** 19124906

**REVIEWED BY** Keith Holmes, PGeo

**CC** Anthony Lyon, PEng

**PREPARED BY** Shihan Chowdhury, PEng

### SAMPLING AND ANALYSIS PLAN, PHASE 4-1, WATERIDGE VILLAGE DEVELOPMENT OTTAWA, ONTARIO

#### Objective

The intent of the current investigation is to further characterize the lateral and vertical extent of soil and groundwater impacts at the property.

#### Site Background

Surficial geology consists of fill overlying a native overburden consisting of sands, silts and clays. Bedrock was encountered at an average depth of 2 m bgs.

Shallow groundwater in the vicinity of the south property boundary is anticipated to flow north and is encountered between approximately 2.4 and 4.3 m of ground surface. The contaminants of potential concern are petroleum hydrocarbons (“PHCs”) and benzene, toluene, ethylbenzene and xylene (“BTEX”), polycyclic aromatic hydrocarbons (PAHs), and metals.

#### Site Access Requirements

| Access Concern                  | Information   |
|---------------------------------|---|
| Site Contact                    | Katherine Constantine – CLC<br>Phone: 613-668-4300  |
| Access                          | Montreal Road to Codd’s Road  |
| Hours of Work                   | No restrictions   |
| Site Check-in Procedure         | Check in with Shihan Chowdhury at the start and end of day; Secondary check-in Anthony Lyon at start and end of day, as needed. |
| Photography                     | No restrictions   |
| On-Site Orientation or Training | None required   |

## Drilling Program

- A total of five boreholes will be advanced and installed with monitoring wells. Two soil samples from each of these locations will be submitted for laboratory analysis.
- One soil sample will be collected in the fill material as described in Table 2. A second, deeper sample will be collected in encountered native material and submitted for analysis as needed (to establish a vertical delineation).
- Additional soil samples will be warranted by field observations.

**Table 1: Borehole Location and Soil Sampling Plan**

| Location                          | Borehole ID | Depth (m bgs) | Soil Samples  | Duplicate Sample                |
|-----------------------------------|-------------|---------------|---|---------------------------------|
| North-central portion of the Site | 22-02       | Approx. 8.0   | 2 x PHC, BTEX, PAHs, and metals (one for fill and one for native) | 1 x PHC, BTEX, PAHs, and metals |
| Northwest portion of the Site     | 22-03       | Approx. 10.0  | 2 x PHC, BTEX, PAHs, and metals (one for fill and one for native) |                                 |
| Northwest portion of the Site     | 22-04       | Approx. 10.0  | 2 x PHC, BTEX, PAHs, and metals (one for fill and one for native) |                                 |
| Center of Site (Bldg.16)          | 22-05       | Approx. 12.0  | 2 x PHC, BTEX, PAHs, and metals (one for fill and one for native) |                                 |
| Northeast of the Site (Bldg.140)  | 22-06       | Approx. 12.0  | 2 x PHC, BTEX, PAHs, and metals (one for fill and one for native) |                                 |

## Groundwater Monitoring

- A round of water level measurements using the water level meter will be collected before purging or sampling any wells.
- Collect groundwater samples from all 5 monitoring wells for the parameters in Table 3 below. Allow the water level to stabilize in the monitoring well before starting measurement of field parameters.

**Table 2: Groundwater Sampling Plan**

| Borehole ID                           | Field Parameter Measurements        | Groundwater Analyses to be Requested | QA/QC samples       |
|---------------------------------------|-------------------------------------|--------------------------------------|---------------------|
| 22-02, 22-03, 22-04, 22-05, and 22-06 | pH; EC; temp; DO; ORP, conductivity | PHCs, BTEX, PAHs, and metals         | Trip blank for VOCs |

## Surveying

- Surveyor to survey horizontal and vertical locations at new monitoring wells and select locations not previously surveyed (ground surface and top of pipe elevations). Top of pipe elevation to be measured at the reference point (notch cut into well pipe).

## Chain-of-Custody

| Chain-of-Custody Item                               | Information                               |
|---|---|
| Analytical Laboratory                               | AGAT                                      |
| Generic Site Condition Standards                    | Table 1 Residential, Coarse textured soil |
| Use Record of Site Condition analytical procedures? | Yes                                       |
| Turn-around Time                                    | Rush                                      |
| Golder Reporting Contact                            | Project Director                          |
| Project-Specific Quote Number (if applicable)       | None                                      |
| Golder Billing Contact                              | Keith Holmes (KHolmes@Golder.com)         |
| Is an EQuiS EDD Required?                           | Yes                                       |

## Management of Investigation Derived Waste

- Keep waste soil and water segregated into separate drums.
- Label drums for waste management purposes, include Golder Associates, project number, date and drum contents (soil, purge water).
- Discuss best location to store drums with on-Site demolition supervisor (should be secure as possible from public access).

## Special Instructions

- Check in with Shihan at start and end of each day.

**APPENDIX C**

**Record of Test Pits**

**Table 1: Test Pit Logs**

| Location | Date       | Soil Unit                     | Sample Name | Sample Depth (mbgs) | Description   |
|----------|------------|-------------------------------|-------------|---------------------|---|
| TP4-01   | 07/07/2020 | Fill (0.0-0.5 mbgs)           | SA1         | 0.3-0.5             | FILL - Sandy silt with gravel and angular boulders; dark grey brown   |
|          |            | Fill (0.5-0.7 mbgs)           | SA2         | 0.5-0.7             | FILL - Sandy silt with gravel and angular boulders; light yellowish brown   |
|          |            | Bedrock (0.7 mbgs)            | --          | --                  | BEDROCK - Refusal on limestone or sandstone at 0.7 mbgs.  |
| TP4-02   | 07/07/2020 | Fill (0.0-1.5 mbgs)           | SA1         | 0.75-1.00           | FILL - Sandy silt with large cobbles, boulders (angular) and gravel; dark to medium brown.                              |
|          |            | Native clay (1.5 - 1.75 mbgs) | --          | --                  | CLAY - Native clay at ~1.5 m; no debris noted.  |
| TP4-03   | 07/07/2020 | Fill (0.0-0.8 mbgs)           | SA1         | 0.60-0.80           | FILL - Silt with some clay and gravel; medium grey brown.   |
|          |            | Fill (0.8-1.2 mbgs)           | SA2         | 1.0                 | FILL - Silty sand; weathered orangey brown with some inclusions or clasts.  |
|          |            | Fill (1.2-1.8)                | --          | --                  | FILL - Sandy with some inclusions and/or light and dark weathered clasts; light yellowish grey brown.                   |
|          |            | Bedrock (1.75-1.80 mbgs)      | --          | --                  | BEDROCK - Refusal between 1.75-1.80 mbgs.   |
| TP4-04   | 07/07/2020 | Fill (0.0-0.5 mbgs)           | SA1         | 0-0.5               | FILL - Sand with some silt and trace gravel (sub-angular to angular); dark greyish brown.                               |
|          |            | Fill (0.5-0.8 mbgs)           | SA2         | 0.5-0.8             | FILL - Sand; light yellow beige; black potentially asbestos containing plastic water or sewer pipe located at 0.8 mbgs. |
| TP4-05   | 07/07/2020 | Fill (0.0-0.4 mbgs)           | --          | --                  | ASPHALT - Asphalt and granular material.  |
|          |            | Fill (0.4-0.85 mbgs)          | SA1         | 0.6-0.7             | FILL - Sand; dark brown sand from 0.4 to 0.5 mbgs, transitions to medium brown sand.                                    |
|          |            | Native (0.85-1.00 mbgs)       | SA2         | 0.85-1              | SAND - Sand with structures and darker weathered red-brown lenses; light brown.   |
| TP4-06   | 07/08/2020 | Fill (0.0-0.3 mbgs)           | --          | --                  | FILL - Silty sand; dark coloured.   |
|          |            | Fill (0.3-0.7 mbgs)           | SA1         | 0.5                 | FILL - Sand with some silt or clayey silt patches; light to medium brown.   |
|          |            | Native (0.7-0.8 mbgs)         | SA2         | 0.75                | CLAY - Native clay to silty clay; grey brown.   |
| TP4-07   | 07/08/2020 | Topsoil (0-0.65 mbgs)         | SA1         | 0.4                 | TOPSOIL - Sand with silt and trace gravel; dark brown.  |
|          |            | Bedrock (0.65 mbgs)           | --          | --                  | BEDROCK - Fractured bedrock.  |

| Location | Date       | Soil Unit              | Sample Name | Sample Depth (mbgs) | Description  |
|----------|------------|------------------------|-------------|---------------------|--|
| TP4-08   | 07/08/2020 | Topsoil (0-0.30 mbgs)  | --          | --                  | TOPSOIL - Sandy silt with gravel and cobbles; brown, dry.  |
|          |            | Fill (0.3-0.5 mbgs)    | SA1 / DUP-1 | 0.35-0.45           | FILL - Gravel with some sand and silt between 0.3-0.4 mbgs; medium to dark brown sandy silt from 0.4-0.5 mbgs. |
|          |            | Native (0.5-0.6 mbgs)  | --          | --                  | SILT - Fine, sandy silt; dark brown.   |
|          |            | Native (0.6-0.85 mbgs) | SA2         | 0.7-0.8             | CLAY - Native clay to silty clay; grey brown.  |
| TP4-09   | 07/07/2020 | Fill (0.0-0.9 mbgs)    | SA1         | 0.4-0.6             | FILL - Fine sand and silt with some gravel and clay cobbles; light brown.                                      |
|          |            | Fill (0.9-1.2 mbgs)    | --          | --                  | SANDY SILT - Fine; medium brown.   |
|          |            | Bedrock (1.2 mbgs)     | --          | --                  | BEDROCK - Refusal at 1.2 mbgs.   |
| TP4-10   | 07/07/2020 | Debris (0.0-0.5 mbgs)  | --          | --                  | DEBRIS - Trace brick debris.   |
|          |            | Fill (0.5-2.50 mbgs)   | SA1         | 1.75-2.00           | FILL - Silt with clay and some sand; grey brown; moist.  |
| TP4-11   | 07/07/2020 | Fill (0.0-1.05 mbgs)   | SA1         | 0.4-0.6             | FILL - Silty sand and some gravel; grey brown.   |
|          |            | Bedrock (1.05 mbgs)    | --          | --                  | BEDROCK - Refusal at 1.05 mbgs.  |
| TP4-12   | 07/07/2020 | Fill (0.0-0.5 mbgs)    | SA1         | 0.2-0.5             | FILL - Silty fine sand with gravel; dark brown; dry.   |
|          |            | Bedrock (0.5 mbgs)     | --          | --                  | BEDROCK - Refusal at 0.5 mbgs.   |
| TP4-13   | 2020-07-07 | Fill (0.0-0.65 mbgs)   | SA1         | 0-0.65              | FILL - Silty sand fill with debris (5%); blackish grey.  |
|          |            | Fill (0.65-1.0 mbgs)   | SA2         | 0.65-1.00           | FILL - Silty sand fill with cobbles; brown.  |
|          |            | Bedrock (1.0 mbgs)     | --          | --                  | BEDROCK - Refusal at 1.0 mbgs.   |
| TP4-15   | 07/07/2020 | Fill (0.0-1.2 mbgs)    | SA1         | 0.3-0.5             | FILL - Silty sand and some gravel; medium brown.   |
|          |            | Bedrock (1.2 mbgs)     | --          | --                  | BEDROCK - Refusal at 1.2 mbgs.   |
| TP4-16   | 07/07/2020 | Fill (0.0-1.2 mbgs)    | SA1         | 0.4-0.8             | FILL - Silty sand with large angular rock chunks (~30-40%); medium yellowish brown.                            |
|          |            | Fill (1.2-1.5 mbgs)    | --          | --                  | FILL - Sandy silt to fine sand and boulders; light beige with a rock ledge between 1.2-1.5mbgs.                |



**Table 1: Test Pit Logs**

| Location              | Date       | Soil Unit                 | Sample Name                    | Sample Depth (mbgs) | Description   |
|-----------------------|------------|---------------------------|--------------------------------|---------------------|---|
| TP4-37A               | 07/10/2020 | Fill<br>(0.0-2.0 mbgs)    | A                              | 1.0                 | FILL - Asphalt and gravel with boulders to clayey silt with some sand and trace gravel; dark to medium brown; dry to moist. |
| TP4-37B               | 07/10/2020 | Fill<br>(0.0-2.0 mbgs)    | B                              | 1.0                 | FILL - Clayey silt with some to minor sand and trace gravel; dark to medium brown; dry to moist.                            |
| TP22-01               | 19-Oct-22  | Topsoil<br>(0.0-0.3 mbgs) | --                             | --                  | TOPSOIL - Dark brown silty sand   |
|                       |            | Fill<br>(0.3-1.5 mbgs)    | SA1                            | 1.0                 | FILL - Sandy silt with gravel, cobbles and boulders, grey to brown; metal debris; dry                                       |
|                       |            | Fill<br>(1.5-3.2 mbgs)    | SA2                            | 2.1                 | FILL - Sandy clay some gravel, cobbles and boulders, grey to brown; asphalt debris; moist.                                  |
|                       |            |                           | SA3                            | 3.0                 |   |
|                       |            | Fill<br>(3.2-3.6 mbgs)    | --                             | --                  | FILL - Clay silt with sand lens; asphalt, metal, and glass debris; moist.   |
| Bedrock<br>(3.6 mbgs) | --         | --                        | BEDROCK - Refusal at 3.6 mbgs. |                     |   |
| TP22-02               | 19-Oct-22  | Topsoil<br>(0.0-0.1 mbgs) | --                             | --                  | TOPSOIL - Dark brown silty sand   |
|                       |            | Fill<br>(0.1-2.1 mbgs)    | SA1                            | 1.25-1.75           | FILL - Silty clay some sand and gravel, grey to brown; metal piece at 0.3m; dry.  |
|                       |            | Fill<br>(2.1-4.2 mbgs)    | SA2                            | 2.25-2.75           | FILL - Silty sand some gravel and boulders, brown; silt seem at 3.1 to 3.2 m; moist.  |
|                       |            |                           | SA3                            | 3.75-4.2            |   |
| Bedrock<br>(4.2 mbgs) | --         | --                        | BEDROCK - Refusal at 4.2 mbgs. |                     |   |
| TP22-03               | 19-Oct-22  | Topsoil<br>(0.0-0.1 mbgs) | --                             | --                  | TOPSOIL - Dark brown silty sand; some metal and brick debris  |
|                       |            | Fill<br>(0.1-0.4 mbgs)    | SA1                            | 0.1-0.4             | FILL - Silty clay trace gravel, grey; asphalt, metal and brick debris; moist.   |
|                       |            | Fill<br>(0.4-1.1 mbgs)    | SA2                            | 0.4-1.1             | FILL - Sand some silt, grey; moist.   |
|                       |            | Fill<br>(1.1-1.5 mbgs)    | --                             | --                  | FILL - Sandy silt, brown; moist.  |
|                       |            | Bedrock<br>(1.5 mbgs)     | --                             | --                  | BEDROCK - Refusal at 1.5 mbgs.  |

| Location           | Date      | Soil Unit              | Sample Name                    | Sample Depth (mbgs) | Description   |
|--------------------|-----------|------------------------|--------------------------------|---------------------|---|
| TP22-04            | 19-Oct-22 | Topsoil (0.0-0.1 mbgs) | --                             | --                  | TOPSOIL - Dark brown silty sand   |
|                    |           | Fill (0.1-2.2 mbgs)    | SA1                            | 1.5-1.7             | FILL - Silty sand, some gravel, grey; cloth debris at 0.3 m; moist.                             |
|                    |           | Fill (2.2-4.0 mbgs)    | SA2                            | 2.7-3.0             | FILL - Sandy silt, some gravel and boulders, brown; clay pocket from 2.5-3.0m; moist.           |
|                    |           |                        | SA3                            | 3.7-4.0             |   |
| Bedrock (4.0 mbgs) | --        | --                     | BEDROCK - Refusal at 4.0 mbgs. |                     |   |
| TP22-05            | 19-Oct-22 | Topsoil (0.0-0.3 mbgs) | --                             | --                  | TOPSOIL - Dark brown silty sand   |
|                    |           | Fill (0.3-2.7 mbgs)    | SA1                            | 0.9-1.2             | FILL - Silty silt, some sand, gravel and cobbles, grey; brick and cloth debris at 2.1 m; moist. |
|                    |           |                        | SA2                            | 2.3-2.5             |   |
|                    |           | Fill (2.7-4.0 mbgs)    | SA3                            | 3.8-4.0             | FILL - Silty sand, some clay and cobbles, brown; moist.   |
| Bedrock (4.0 mbgs) | --        | --                     | BEDROCK - Refusal at 4.0 mbgs. |                     |   |
| TP22-06            | 19-Oct-22 | Fill (0.0-0.6 mbgs)    | --                             | --                  | FILL - Sand and gravel, grey; dry.  |
|                    |           | Fill (0.6-1.7 mbgs)    | SA1                            | 1.5-1.7             | FILL - Clay with gravel, grey; moist.   |
|                    |           | Fill (1.7-3.1 mbgs)    | SA2                            | 2.2-2.4             | FILL - Silty clay, some gravel, cobble and boulders, grey; concrete debris and roots; moist.    |
|                    |           | Fill (3.1-3.8 mbgs)    | SA3                            | 3.4-3.6             | FILL - Silty clay, some gravel and boulders, grey; concrete debris and roots; moist.            |
|                    |           | Bedrock (3.8 mbgs)     | --                             | --                  | BEDROCK - Refusal at 3.8 mbgs.  |


**Table 1: Test Pit Logs**

| Location | Date      | Soil Unit                 | Sample Name | Sample Depth (mbgs) | Description  |
|----------|-----------|---------------------------|-------------|---------------------|--|
| TP22-07  | 19-Oct-22 | Topsoil<br>(0.0-0.2 mbgs) | --          | --                  | TOPSOIL - Dark brown silty sand  |
|          |           | Fill<br>(0.2-1.1 mbgs)    | SA1         | 1.5-1.7             | FILL - Sandy silt with gravel, brown; brick and asphalt debris; moist.                       |
|          |           | Fill<br>(1.1-3.1 mbgs)    | SA2         | 2.2-2.4             | FILL - Clay with silt some sand, gravel, and cobbles, grey; brick and asphalt debris; moist. |
|          |           | Fill<br>(3.1-4.8 mbgs)    | SA3         | 3.4-3.6             | FILL - Silty clay some sand, gravel, and boulders, grey; brick and asphalt debris; moist.    |
|          |           |                           | --          | --                  | End of TP at 4.8 mbgs.   |

**Notes:** TP = Test Pit  
 SA = Sample  
 mbgs = meters below ground surface

# LOG OF BOREHOLE BHMW126-1

|  |                                      |
|--|--------------------------------------|
| REF. No.: OE-OT-015358                           | <b>DST CONSULTING ENGINEERS INC.</b> |
| CLIENT: Canada Lands Company                     |                                      |
| PROJECT: Soil and Groundwater Remediation        | METHOD: CME 850                      |
| LOCATION: Former CFB Rockcliffe, Ottawa, Ontario | DIAMETER: 50.8 mm                    |
| SURFACE ELEVATION: metres                        | DATE: 3 March 2015                   |



GASTECBH OE-OT-015358.GPJ DST\_MIN.GDT 29/5/15




- Auger Sample
- Split Spoon
- Continuous Sample

\* - Total Vapour Concentration  
 NR - No Sample Recovery  
 ND - Not Detectable  
 Gastector 1238 ME

- Bentonite & Riser
- Sand Pack & Screen

# LOG OF BOREHOLE BHMW137-1

|  |                                      |
|--|--------------------------------------|
| REF. No.: OE-OT-015358                           | <b>DST CONSULTING ENGINEERS INC.</b> |
| CLIENT: Canada Lands Company                     |                                      |
| PROJECT: Soil and Groundwater Remediation        | METHOD: CME 850                      |
| LOCATION: Former CFB Rockcliffe, Ottawa, Ontario | DIAMETER: 50.8 mm                    |
| SURFACE ELEVATION: metres                        | DATE: 11 February 2015               |



GASTECOBH OE-OT-015358.GPJ DST\_MIN.GDT 29/15/15




- Auger Sample
- Split Spoon
- Continuous Sample

\* - Total Vapour Concentration  
 NR - No Sample Recovery  
 ND - Not Detectable  
 Gastector 1238 ME

- Bentonite & Risers
- Sand Pack & Screen

# LOG OF BOREHOLE BHMW137-2

|  |                                      |
|--|--------------------------------------|
| REF. No.: OE-OT-015358                           | <b>DST CONSULTING ENGINEERS INC.</b> |
| CLIENT: Canada Lands Company                     |                                      |
| PROJECT: Soil and Groundwater Remediation        | METHOD: CME 850                      |
| LOCATION: Former CFB Rockcliffe, Ottawa, Ontario | DIAMETER: 50.8 mm                    |
| SURFACE ELEVATION: metres                        | DATE: 25 February 2015               |




GASTECOBH OE-OT-015358.GPJ DST\_MIN.GDT 29/5/15



- Auger Sample
- Split Spoon
- Continuous Sample
- \* - Total Vapour Concentration
- NR - No Sample Recovery
- ND - Not Detectable
- Gastector 1238 ME
- Bentonite & Risers
- Sand Pack & Screen

# LOG OF BOREHOLE BHMW137-3

|  |                                      |
|--|--------------------------------------|
| REF. No.: OE-OT-015358                           | <b>DST CONSULTING ENGINEERS INC.</b> |
| CLIENT: Canada Lands Company                     |                                      |
| PROJECT: Soil and Groundwater Remediation        | METHOD: CME 850                      |
| LOCATION: Former CFB Rockcliffe, Ottawa, Ontario | DIAMETER: 50.8 mm                    |
| SURFACE ELEVATION: metres                        | DATE: 26 February 2015               |



GASTECBH OE-OT-015358.GPJ DST\_MIN.GDT 29/5/15

□ Auger Sample

▨ Split Spoon

▩ Continuous Sample

\* - Total Vapour Concentration

NR - No Sample Recovery

ND - Not Detectable

Gastector 1238 ME

▬ Bentonite & Riser

▧ Sand Pack & Screen

ENCLOSURE 5

# LOG OF BOREHOLE BHMW31-1

|  |                                      |
|--|--------------------------------------|
| REF. No.: OE-OT-015358                           | <b>DST CONSULTING ENGINEERS INC.</b> |
| CLIENT: Canada Lands Company                     |                                      |
| PROJECT: Soil and Groundwater Remediation        | METHOD: CME 850                      |
| LOCATION: Former CFB Rockcliffe, Ottawa, Ontario | DIAMETER: 50.8 mm                    |
| SURFACE ELEVATION: metres                        | DATE: 2 November 2015                |

| TVC *  |  |  |  | SAMPLES           |     |      |           | SUBSURFACE PROFILE      |                           |        |        | REMARKS |  |
|--|--|--|--|-------------------|-----|------|-----------|-------------------------|---------------------------|--------|--------|---------|--|
| ■ % LEL<br>20 40 60 80<br>○ PPM<br>200 400 600 800 |  |  |  | TVC Conc. PPM/LEL | No. | Type | SPT Value | SYMBL                   | MATERIAL DESCRIPTION      | DPTH m | ELEV m |         | WATER DATA   |
| SURFACE  |  |  |  |                   |     |      |           |                         |                           |        |        |         |  |
|  |  |  |  |                   |     |      |           | (Symbol for Granular)   | GRANULAR (BACKFILL ).     | 1      |        |         | - Flush mount protective casing.                         |
|  |  |  |  |                   |     |      |           | (Symbol for Silty Sand) | SILTY SAND - Some gravel. | 2      |        |         |  |
|  |  |  |  |                   |     |      |           | (Symbol for Bedrock)    | BEDROCK.                  | 3      |        |         |  |
|  |  |  |  |                   |     |      |           |                         |                           | 4      |        |         |  |
|  |  |  |  |                   |     |      |           |                         |                           | 5      |        |         | Groundwater level<br>4.87 m.b.g.s<br>(February 17, 2015) |
|  |  |  |  |                   |     |      |           |                         | End Of Borehole at 6.0 m. | 6      |        |         |  |
|  |  |  |  |                   |     |      |           |                         |                           | 7      |        |         |  |

GASTECOBH OE-OT-015358.GPJ DST\_MIN.GDT 29/05/15



- Auger Sample
- Split Spoon
- Continuous Sample


\* - Total Vapour Concentration  
 NR - No Sample Recovery  
 ND - Not Detectable  
 Gastector 1238 ME

- Bentonite & Riser
- Sand Pack & Screen



# LOG OF BOREHOLE BHMW47-1

|  |                                      |
|--|--------------------------------------|
| REF. No.: OE-OT-015358                           | <b>DST CONSULTING ENGINEERS INC.</b> |
| CLIENT: Canada Lands Company                     |                                      |
| PROJECT: Soil and Groundwater Remediation        | METHOD: CME 850                      |
| LOCATION: Former CFB Rockcliffe, Ottawa, Ontario | DIAMETER: 50.8 mm                    |
| SURFACE ELEVATION: metres                        | DATE: 11 February 2015               |



GASTECOBH OE-OT-015358.GPJ DST\_MIN.GDT 29/5/15

Auger Sample

Split Spoon

Continuous Sample

\* - Total Vapour Concentration

NR - No Sample Recovery

ND - Not Detectable

Gastector 1238 ME

Bentonite & Riser

Sand Pack & Screen

ENCLOSURE 11

PROJECT: 19124906

# RECORD OF BOREHOLE: 22-02

SHEET 1 OF 1

LOCATION: See Site Plan

BORING DATE: July 12, 2022

DATUM: Geodetic

SAMPLER HAMMER, 64kg; DROP, 760mm

PENETRATION TEST HAMMER, 64kg; DROP, 760mm

| DEPTH SCALE METRES | BORING METHOD           | SOIL PROFILE   |             | SAMPLES         |        | DYNAMIC PENETRATION RESISTANCE, BLOWS/0.3m |             |                        |    | HYDRAULIC CONDUCTIVITY, k, cm/s |    |                       |          | ADDITIONAL LAB. TESTING | PIEZOMETER OR STANDPIPE INSTALLATION |       |       |
|--------------------|-------------------------|--|-------------|-----------------|--------|--|-------------|------------------------|----|---------------------------------|----|-----------------------|----------|-------------------------|--------------------------------------|-------|-------|
|                    |                         | DESCRIPTION  | STRATA PLOT | ELEV. DEPTH (m) | NUMBER | TYPE                                       | BLOWS/0.30m | SHEAR STRENGTH Cu, kPa |    |                                 |    | WATER CONTENT PERCENT |          |                         |                                      |       |       |
|                    |                         |  |             |                 |        |  |             | 20                     | 40 | 60                              | 80 | nat V. +              | rem V. ⊕ |                         |                                      | Q - ● | U - ○ |
| 0                  |                         | GROUND SURFACE   |             | 0.00            |        |  |             |                        |    |                                 |    |                       |          |                         |                                      |       |       |
| 0.5                | Geoprobe<br>Direct Push | TOPSOIL/FILL - (SM) SILTY SAND, trace gravel; light brown with reddish spots, contains roots; dry to moist |             | 0.00            | 1      | SS   | -           |                        |    |                                 |    |                       |          |                         |                                      |       |       |
| 1.52               |                         | BEDROCK  |             | 1.52            |        |  |             |                        |    |                                 |    |                       |          |                         |                                      |       |       |
| 2                  |                         |  |             |                 |        |  |             |                        |    |                                 |    |                       |          |                         |                                      |       |       |
| 3                  |                         |  |             |                 |        |  |             |                        |    |                                 |    |                       |          |                         | Bentonite Seal                       |       |       |
| 4                  |                         |  |             |                 |        |  |             |                        |    |                                 |    |                       |          |                         |                                      |       |       |
| 5                  |                         |  |             |                 |        |  |             |                        |    |                                 |    |                       |          |                         | Silica Sand                          |       |       |
| 6                  |                         |  |             |                 |        |  |             |                        |    |                                 |    |                       |          |                         |                                      |       |       |
| 7                  |                         |  |             |                 |        |  |             |                        |    |                                 |    |                       |          |                         | Well Screen                          |       |       |
| 8                  |                         | End of Borehole  |             | 7.92            |        |  |             |                        |    |                                 |    |                       |          |                         |                                      |       |       |
| 9                  |                         |  |             |                 |        |  |             |                        |    |                                 |    |                       |          |                         |                                      |       |       |
| 10                 |                         |  |             |                 |        |  |             |                        |    |                                 |    |                       |          |                         |                                      |       |       |
| 11                 |                         |  |             |                 |        |  |             |                        |    |                                 |    |                       |          |                         |                                      |       |       |
| 12                 |                         |  |             |                 |        |  |             |                        |    |                                 |    |                       |          |                         |                                      |       |       |
| 13                 |                         |  |             |                 |        |  |             |                        |    |                                 |    |                       |          |                         |                                      |       |       |
| 14                 |                         |  |             |                 |        |  |             |                        |    |                                 |    |                       |          |                         |                                      |       |       |
| 15                 |                         |  |             |                 |        |  |             |                        |    |                                 |    |                       |          |                         |                                      |       |       |

MIS-BHS 001 19124906.GPJ GAL-MIS.GDT 6/5/23 JEM

DEPTH SCALE

1 : 75



LOGGED: PAK

CHECKED: KPH

PROJECT: 19124906

# RECORD OF BOREHOLE: 22-03

SHEET 1 OF 1

LOCATION: See Site Plan

BORING DATE: July 14, 2022

DATUM: Geodetic

SAMPLER HAMMER, 64kg; DROP, 760mm

PENETRATION TEST HAMMER, 64kg; DROP, 760mm

| DEPTH SCALE METRES | BORING METHOD           | SOIL PROFILE   |                         | SAMPLES         |        |      | HEADSPACE COMBUSTIBLE VAPOUR CONCENTRATIONS [PPM] ⊕ | HYDRAULIC CONDUCTIVITY, k, cm/s                 |   |  |  | ADDITIONAL LAB. TESTING | PIEZOMETER OR STANDPIPE INSTALLATION |  |
|--------------------|-------------------------|--|-------------------------|-----------------|--------|------|---|---|---|--|--|-------------------------|--------------------------------------|--|
|                    |                         | DESCRIPTION  | STRATA PLOT             | ELEV. DEPTH (m) | NUMBER | TYPE | BLOWS/0.30m   | ND = Not Detected                               | 10 <sup>-6</sup> 10 <sup>-5</sup> 10 <sup>-4</sup> 10 <sup>-3</sup> |  |  |                         |                                      |  |
|                    |                         |  |                         |                 |        |      |   | HEADSPACE ORGANIC VAPOUR CONCENTRATIONS [PPM] □ | WATER CONTENT PERCENT   |  |  |                         |                                      |  |
|                    |                         | GROUND SURFACE   |                         |                 |        |      | ND = Not Detected                                   | Wp       WI                                     |   |  |  |                         |                                      |  |
| 0                  | Geoprobe<br>Direct Push | TOPSOIL/FILL - (SM) SILTY SAND, trace to some gravel; brown, contains roots and broken glass; non-cohesive, moist to dry | [Cross-hatch pattern]   | 0.00            | 1      | SS   | ND  |   |   |  |  |                         |                                      |  |
| 1                  |                         | FILL - (SM) SILTY SAND, trace gravel; reddish with brown spots; non-cohesive, moist to dry                               | [Cross-hatch pattern]   | 1.52            | 2      | SS   | -   |   |   |  |  |                         |                                      |  |
| 2                  |                         | BEDROCK  | [Diagonal line pattern] | 1.98            |        |      |   |   |   |  |  |                         |                                      |  |
| 3                  |                         |  |                         |                 |        |      |   |   |   |  |  |                         |                                      |  |
| 4                  |                         |  |                         |                 |        |      |   |   |   |  |  | Bentonite Seal          |                                      |  |
| 5                  |                         |  |                         |                 |        |      |   |   |   |  |  |                         |                                      |  |
| 6                  |                         |  |                         |                 |        |      |   |   |   |  |  |                         |                                      |  |
| 7                  |                         |  |                         |                 |        |      |   |   |   |  |  | Silica Sand             |                                      |  |
| 8                  |                         |  |                         |                 |        |      |   |   |   |  |  |                         |                                      |  |
| 9                  |                         |  |                         |                 |        |      |   |   |   |  |  | Well Screen             |                                      |  |
| 10                 |                         | End of Borehole  |                         | 10.06           |        |      |   |   |   |  |  |                         |                                      |  |
| 11                 |                         |  |                         |                 |        |      |   |   |   |  |  |                         |                                      |  |
| 12                 |                         |  |                         |                 |        |      |   |   |   |  |  |                         |                                      |  |
| 13                 |                         |  |                         |                 |        |      |   |   |   |  |  |                         |                                      |  |
| 14                 |                         |  |                         |                 |        |      |   |   |   |  |  |                         |                                      |  |
| 15                 |                         |  |                         |                 |        |      |   |   |   |  |  |                         |                                      |  |

MIS-BHS 001 19124906.GPJ GAL-MIS.GDT 6/5/23 JEM

DEPTH SCALE

1 : 75



LOGGED: PAK

CHECKED: KPH

PROJECT: 19124906

# RECORD OF BOREHOLE: 22-04

SHEET 1 OF 1

LOCATION: See Site Plan

BORING DATE: July 14, 2022

DATUM: Geodetic

SAMPLER HAMMER, 64kg; DROP, 760mm

PENETRATION TEST HAMMER, 64kg; DROP, 760mm

| DEPTH SCALE METRES | BORING METHOD | SOIL PROFILE  |             | SAMPLES         |        |      | HEADSPACE COMBUSTIBLE VAPOUR CONCENTRATIONS [PPM] ⊕ |   |    |    | HYDRAULIC CONDUCTIVITY, k, cm/s |                       |    |    | ADDITIONAL LAB. TESTING | PIEZOMETER OR STANDPIPE INSTALLATION |  |
|--------------------|---------------|---|-------------|-----------------|--------|------|---|---|----|----|---------------------------------|-----------------------|----|----|-------------------------|--------------------------------------|--|
|                    |               | DESCRIPTION   | STRATA PLOT | ELEV. DEPTH (m) | NUMBER | TYPE | BLOWS/0.30m   | HEADSPACE ORGANIC VAPOUR CONCENTRATIONS [PPM] □ |    |    |                                 | WATER CONTENT PERCENT |    |    |                         |                                      |  |
|                    |               |   |             |                 |        |      |   | ND = Not Detected                               |    |    |                                 | Wp — W — Wi           |    |    |                         |                                      |  |
| 0                  |               | GROUND SURFACE  |             |                 |        |      | 20  | 40  | 60 | 80 | 20                              | 40                    | 60 | 80 |                         |                                      |  |
| 0.00               |               | TOPSOIL/FILL - (SM) SILTY SAND, trace gravel; brown to grey, contains roots; non-cohesive, dry                      |             |                 | 1      | SS   | -   |   |    |    |                                 |                       |    |    |                         |                                      |  |
| 1.50               |               | FILL - (MH/CH) CLAYEY SILT to SILTY CLAY, trace sand and gravel, low plasticity; brown; w-PL                        |             |                 | 2      | SS   | -   | ⊕   |    |    |                                 |                       |    |    |                         |                                      |  |
| 2.74               |               | FILL - (SM/ML) SILTY SAND, to sandy SILT, trace clay and gravel; black, contains organic matter, non-plastic, moist |             |                 | 3      | SS   | -   | ⊕   |    |    |                                 |                       |    |    |                         |                                      |  |
| 3.05               |               | FILL - (SM) gravelly SILTY SAND; brown, contains weathered shale/limestone; non-cohesive                            |             |                 | 4      | SS   | -   |   |    |    |                                 |                       |    |    |                         |                                      |  |
| 5.18               |               | FILL - (CL/CH) SILTY CLAY to CLAY; brown to dark grey; cohesive, w-PL   |             |                 | 6      | SS   | -   | □   |    |    |                                 |                       |    |    |                         |                                      |  |
| 7.47               |               | FILL - (SM) gravelly SILTY SAND to SILTY SAND and GRAVEL; brown; non-cohesive, moist                                |             |                 | 7      | SS   | -   | □   | ⊕  |    |                                 |                       |    |    |                         |                                      |  |
| 7.92               |               | BEDROCK   |             |                 | 8      | SS   | -   |   |    |    |                                 |                       |    |    |                         |                                      |  |
| 12.19              |               | End of Borehole   |             |                 |        |      |   |   |    |    |                                 |                       |    |    |                         |                                      |  |

DEPTH SCALE

1 : 75



LOGGED: PAK

CHECKED: KPH

MIS-BHS 001 19124906.GPJ GAL-MIS.GDT 6/5/23 JEM

PROJECT: 19124906

# RECORD OF BOREHOLE: 22-05

SHEET 1 OF 1

LOCATION: See Site Plan

BORING DATE: July 14, 2022

DATUM: Geodetic

SAMPLER HAMMER, 64kg; DROP, 760mm

PENETRATION TEST HAMMER, 64kg; DROP, 760mm

| DEPTH SCALE METRES | BORING METHOD           | SOIL PROFILE  |             | SAMPLES         |        | DYNAMIC PENETRATION RESISTANCE, BLOWS/0.3m |             |                        |    | HYDRAULIC CONDUCTIVITY, k, cm/s |    |                       |          | ADDITIONAL LAB. TESTING | PIEZOMETER OR STANDPIPE INSTALLATION |       |       |
|--------------------|-------------------------|---|-------------|-----------------|--------|--|-------------|------------------------|----|---------------------------------|----|-----------------------|----------|-------------------------|--------------------------------------|-------|-------|
|                    |                         | DESCRIPTION   | STRATA PLOT | ELEV. DEPTH (m) | NUMBER | TYPE                                       | BLOWS/0.30m | SHEAR STRENGTH Cu, kPa |    |                                 |    | WATER CONTENT PERCENT |          |                         |                                      |       |       |
|                    |                         |   |             |                 |        |  |             | 20                     | 40 | 60                              | 80 | nat V. +              | rem V. ⊕ |                         |                                      | Q - ● | U - ○ |
| 0                  | Geoprobe<br>Direct Push | GROUND SURFACE  |             |                 |        |  |             |                        |    |                                 |    |                       |          |                         |                                      |       |       |
| 0.00               |                         | TOPSOIL/FILL - (SM) SILTY SAND, trace gravel; black, contains organic matter and roots; non-cohesive, moist |             | 1               | SS     |  |             |                        |    |                                 |    |                       |          |                         |                                      |       |       |
| 0.30               |                         | FILL - (SM) gravelly SILTY SAND, non-plastic; light brown; non-cohesive                                     |             | 2               | SS     |  |             |                        |    |                                 |    |                       |          |                         |                                      |       |       |
| 0.61               |                         | BEDROCK   |             |                 |        |  |             |                        |    |                                 |    |                       |          |                         |                                      |       |       |
| 1                  |                         |   |             |                 |        |  |             |                        |    |                                 |    |                       |          |                         |                                      |       |       |
| 2                  |                         |   |             |                 |        |  |             |                        |    |                                 |    |                       |          |                         |                                      |       |       |
| 3                  |                         |   |             |                 |        |  |             |                        |    |                                 |    |                       |          |                         |                                      |       |       |
| 4                  |                         |   |             |                 |        |  |             |                        |    |                                 |    |                       |          |                         |                                      |       |       |
| 5                  |                         |   |             |                 |        |  |             |                        |    |                                 |    |                       |          |                         |                                      |       |       |
| 6                  |                         |   |             |                 |        |  |             |                        |    |                                 |    |                       |          |                         |                                      |       |       |
| 7                  |                         |   |             |                 |        |  |             |                        |    |                                 |    |                       |          |                         |                                      |       |       |
| 8                  |                         |   |             |                 |        |  |             |                        |    |                                 |    |                       |          |                         |                                      |       |       |
| 9                  |                         |   |             |                 |        |  |             |                        |    |                                 |    |                       |          |                         |                                      |       |       |
| 10                 |                         |   |             |                 |        |  |             |                        |    |                                 |    |                       |          |                         |                                      |       |       |
| 11                 |                         |   |             |                 |        |  |             |                        |    |                                 |    |                       |          |                         |                                      |       |       |
| 12                 |                         |   |             |                 |        |  |             |                        |    |                                 |    |                       |          |                         |                                      |       |       |
| 12.19              |                         | End of Borehole   |             |                 |        |  |             |                        |    |                                 |    |                       |          |                         |                                      |       |       |
| 13                 |                         |   |             |                 |        |  |             |                        |    |                                 |    |                       |          |                         |                                      |       |       |
| 14                 |                         |   |             |                 |        |  |             |                        |    |                                 |    |                       |          |                         |                                      |       |       |
| 15                 |                         |   |             |                 |        |  |             |                        |    |                                 |    |                       |          |                         |                                      |       |       |

MIS-BHS 001 19124906.GPJ GAL-MIS.GDT 6/5/23 JEM

DEPTH SCALE

1 : 75



LOGGED: PAK

CHECKED: KPH

PROJECT: 19124906

# RECORD OF BOREHOLE: 22-06

SHEET 1 OF 1

LOCATION: See Site Plan

BORING DATE: July 13, 2022

DATUM: Geodetic

SAMPLER HAMMER, 64kg; DROP, 760mm

PENETRATION TEST HAMMER, 64kg; DROP, 760mm

| DEPTH SCALE METRES | BORING METHOD | SOIL PROFILE  |             | SAMPLES         |        | HEADSPACE COMBUSTIBLE VAPOUR CONCENTRATIONS [PPM] ⊕ |   |  |  | HYDRAULIC CONDUCTIVITY, k, cm/s |   |  |  | ADDITIONAL LAB. TESTING | PIEZOMETER OR STANDPIPE INSTALLATION |  |
|--------------------|---------------|---|-------------|-----------------|--------|---|---|--|--|---------------------------------|---|--|--|-------------------------|--------------------------------------|--|
|                    |               | DESCRIPTION   | STRATA PLOT | ELEV. DEPTH (m) | NUMBER | TYPE  | ND = Not Detected                               |  |  |                                 | 10 <sup>-6</sup> 10 <sup>-5</sup> 10 <sup>-4</sup> 10 <sup>-3</sup> |  |  |                         |                                      |  |
|                    |               |   |             |                 |        |   | HEADSPACE ORGANIC VAPOUR CONCENTRATIONS [PPM] □ |  |  |                                 | WATER CONTENT PERCENT   |  |  |                         |                                      |  |
|                    |               |   |             |                 |        | ND = Not Detected                                   |   |  |  | Wp       WI                     |   |  |  |                         |                                      |  |
| 0                  |               | GROUND SURFACE  |             |                 |        |   |   |  |  |                                 |   |  |  |                         |                                      |  |
| 0.00               |               | TOPSOIL/FILL - (SM/SP) SILTY SAND to SAND, some gravel; light brown, contains roots; dry to moist |             | 0.00            | 1      | SS  |   |  |  |                                 |   |  |  |                         |                                      |  |
| 1.22               |               | BEDROCK   |             | 1.22            |        |   |   |  |  |                                 |   |  |  |                         |                                      |  |
| 12.19              |               | End of Borehole   |             | 12.19           |        |   |   |  |  |                                 |   |  |  |                         |                                      |  |

MIS-BHS 001 19124906.GPJ GAL-MIS.GDT 6/5/23 JEM

DEPTH SCALE

1 : 75



LOGGED: PAK

CHECKED: KPH

**APPENDIX D**

**Laboratory Certificates**



CLIENT NAME: GOLDER ASSOCIATES LTD  
1931 ROBERTSON ROAD  
OTTAWA, ON K2H5B7  
(613) 592-9600

ATTENTION TO: Keith Holmes

PROJECT: 19124906

AGAT WORK ORDER: 20Z613655

TRACE ORGANICS REVIEWED BY: Neli Popnikolova, Senior Chemist

DATE REPORTED: Jun 23, 2020

PAGES (INCLUDING COVER): 6

VERSION\*: 1

Should you require any information regarding this analysis please contact your client services representative at (905) 712-5100

\*Notes

*Disclaimer:*

- *All work conducted herein has been done using accepted standard protocols, and generally accepted practices and methods. AGAT test methods may incorporate modifications from the specified reference methods to improve performance.*
- *All samples will be disposed of within 30 days following analysis, unless expressly agreed otherwise in writing. Please contact your Client Project Manager if you require additional sample storage time.*
- *AGAT's liability in connection with any delay, performance or non-performance of these services is only to the Client and does not extend to any other third party. Unless expressly agreed otherwise in writing, AGAT's liability is limited to the actual cost of the specific analysis or analyses included in the services.*
- *This Certificate shall not be reproduced except in full, without the written approval of the laboratory.*
- *The test results reported herewith relate only to the samples as received by the laboratory.*
- *Application of guidelines is provided "as is" without warranty of any kind, either expressed or implied, including, but not limited to, warranties of merchantability, fitness for a particular purpose, or non-infringement. AGAT assumes no responsibility for any errors or omissions in the guidelines contained in this document.*
- *All reportable information as specified by ISO/IEC 17025:2017 is available from AGAT Laboratories upon request.*





## Certificate of Analysis

AGAT WORK ORDER: 20Z613655

PROJECT: 19124906

5835 COOPERS AVENUE  
MISSISSAUGA, ONTARIO  
CANADA L4Z 1Y2  
TEL (905)712-5100  
FAX (905)712-5122  
<http://www.agatlabs.com>

CLIENT NAME: GOLDER ASSOCIATES LTD

ATTENTION TO: Keith Holmes

SAMPLING SITE:

SAMPLED BY: ALB

### O. Reg. 153(511) - PHCs F1 - F4 (Water)

DATE RECEIVED: 2020-06-16

DATE REPORTED: 2020-06-23

| Parameter                      | Unit | SAMPLE DESCRIPTION: |            | 137-3      | 137-1      | Culvert    | MW12       | 29-1       | 29-2       |
|--------------------------------|------|---------------------|------------|------------|------------|------------|------------|------------|------------|
|                                |      | G / S               | RDL        | Water      | Water      | Water      | Water      | Water      | Water      |
| DATE SAMPLED:                  |      | 2020-06-16          | 2020-06-16 | 2020-06-16 | 2020-06-16 | 2020-06-16 | 2020-06-16 | 2020-06-16 | 2020-06-16 |
|                                |      | 08:55               | 09:20      | 09:40      | 10:40      | 11:00      | 11:15      |            |            |
|                                |      | 1202488             | 1202491    | 1202492    | 1202493    | 1202494    | 1202495    |            |            |
| Benzene                        | µg/L | 0.5                 | 0.20       | <0.20      | <0.20      | <0.20      | <0.20      | <0.20      | <0.20      |
| Toluene                        | µg/L | 0.8                 | 0.20       | <0.20      | <0.20      | <0.20      | <0.20      | <0.20      | <0.20      |
| Ethylbenzene                   | µg/L | 0.5                 | 0.10       | <0.10      | <0.10      | <0.10      | <0.10      | <0.10      | <0.10      |
| Xylenes (Total)                | µg/L | 72                  | 0.20       | <0.20      | <0.20      | <0.20      | <0.20      | <0.20      | <0.20      |
| F1 (C6 - C10)                  | µg/L | 420                 | 25         | 27         | <25        | <25        | <25        | <25        | <25        |
| F1 (C6 to C10) minus BTEX      | µg/L | 420                 | 25         | 27         | <25        | <25        | <25        | <25        | <25        |
| F2 (C10 to C16)                | µg/L | 150                 | 100        | 23000      | <100       | <100       | <100       | <100       | <100       |
| F3 (C16 to C34)                | µg/L | 500                 | 100        | 16000      | <100       | <100       | <100       | <100       | <100       |
| F4 (C34 to C50)                | µg/L | 500                 | 100        | <100       | <100       | <100       | <100       | <100       | <100       |
| Gravimetric Heavy Hydrocarbons | µg/L |                     | 500        | NA         | NA         | NA         | NA         | NA         | NA         |
| Sediment                       |      |                     |            | Trace      | No         | No         | No         | No         | No         |
| Surrogate                      | Unit | Acceptable Limits   |            |            |            |            |            |            |            |
| Terphenyl                      | %    | 60-140              |            | 91         | 97         | 103        | 93         | 86         | 85         |

Comments: RDL - Reported Detection Limit; G / S - Guideline / Standard: Refers to Table 1: Full Depth Background Site Condition Standards - Ground Water - All Types of Property Uses  
Guideline values are for general reference only. The guidelines provided may or may not be relevant for the intended use. Refer directly to the applicable standard for regulatory interpretation.

1202488-1202495 The C6-C10 fraction is calculated using Toluene response factor.  
Xylenes total is a calculated parameter. The calculated value is the sum of m&p-Xylene and o-Xylene.  
C6-C10 (F1 minus BTEX) is a calculated parameter. The calculated value is F1 minus BTEX.  
The C10 - C16, C16 - C34, and C34 - C50 fractions are calculated using the average response factor for n-C10, n-C16, and nC34.  
Gravimetric Heavy Hydrocarbons are not included in the Total C16 - C50 and are only determined if the chromatogram of the C34 - C50 Hydrocarbons indicated that hydrocarbons >C50 are present.  
The chromatogram has returned to baseline by the retention time of nC50.  
Total C6-C50 results are corrected for BTEX contribution.  
This method complies with the Reference Method for the CWS PHC and is validated for use in the laboratory.  
nC6 and nC10 response factors are within 30% of Toluene response factor.  
nC10, nC16 and nC34 response factors are within 10% of their average.  
C50 response factor is within 70% of nC10 + nC16 nC34 average.  
Linearity is within 15%.  
Extraction and holding times were met for this sample.  
Fractions 1-4 are quantified with the contribution of PAHs. Under Ontario Regulation 153/04, results are considered valid without determining the PAH contribution if not requested by the client.  
NA = Not Applicable

Analysis performed at AGAT Toronto (unless marked by \*)

Certified By:



# Guideline Violation

AGAT WORK ORDER: 20Z613655

PROJECT: 19124906

5835 COOPERS AVENUE  
MISSISSAUGA, ONTARIO  
CANADA L4Z 1Y2  
TEL (905)712-5100  
FAX (905)712-5122  
<http://www.agatlabs.com>

CLIENT NAME: GOLDER ASSOCIATES LTD

ATTENTION TO: Keith Holmes

| SAMPLEID | SAMPLE TITLE | GUIDELINE | ANALYSIS PACKAGE                        | PARAMETER       | UNIT | GUIDEVALUE | RESULT |
|----------|--------------|-----------|---|-----------------|------|------------|--------|
| 1202488  | 137-3        | ON T1 GW  | O. Reg. 153(511) - PHCs F1 - F4 (Water) | F2 (C10 to C16) | µg/L | 150        | 23000  |
| 1202488  | 137-3        | ON T1 GW  | O. Reg. 153(511) - PHCs F1 - F4 (Water) | F3 (C16 to C34) | µg/L | 500        | 16000  |

## Quality Assurance

CLIENT NAME: GOLDER ASSOCIATES LTD  
 PROJECT: 19124906  
 SAMPLING SITE:

AGAT WORK ORDER: 20Z613655  
 ATTENTION TO: Keith Holmes  
 SAMPLED BY: ALB

### Trace Organics Analysis

| RPT Date: Jun 23, 2020                  |         |           | DUPLICATE |        |     | Method Blank | REFERENCE MATERIAL |                   |       | METHOD BLANK SPIKE |                   |       | MATRIX SPIKE |                   |       |
|---|---------|-----------|-----------|--------|-----|--------------|--------------------|-------------------|-------|--------------------|-------------------|-------|--------------|-------------------|-------|
| PARAMETER                               | Batch   | Sample Id | Dup #1    | Dup #2 | RPD |              | Measured Value     | Acceptable Limits |       | Recovery           | Acceptable Limits |       | Recovery     | Acceptable Limits |       |
|   |         |           |           |        |     |              |                    | Lower             | Upper |                    | Lower             | Upper |              | Lower             | Upper |
| O. Reg. 153(511) - PHCs F1 - F4 (Water) |         |           |           |        |     |              |                    |                   |       |                    |                   |       |              |                   |       |
| Benzene                                 | 1207042 |           | < 0.20    | < 0.20 | NA  | < 0.20       | 96%                | 50%               | 140%  | 104%               | 60%               | 130%  | 94%          | 50%               | 140%  |
| Toluene                                 | 1207042 |           | < 0.20    | < 0.20 | NA  | < 0.20       | 99%                | 50%               | 140%  | 93%                | 60%               | 130%  | 116%         | 50%               | 140%  |
| Ethylbenzene                            | 1207042 |           | < 0.10    | < 0.10 | NA  | < 0.10       | 91%                | 50%               | 140%  | 98%                | 60%               | 130%  | 102%         | 50%               | 140%  |
| Xylenes (Total)                         | 1207042 |           | < 0.20    | < 0.20 | NA  | < 0.20       | 104%               | 50%               | 140%  | 96%                | 60%               | 130%  | 106%         | 50%               | 140%  |
| F1 (C6 - C10)                           | 1207042 |           | < 25      | < 25   | NA  | < 25         | 96%                | 60%               | 140%  | 86%                | 60%               | 140%  | 109%         | 60%               | 140%  |
| F2 (C10 to C16)                         | 1197236 |           | < 100     | < 100  | NA  | < 100        | 100%               | 60%               | 140%  | 115%               | 60%               | 140%  | 112%         | 60%               | 140%  |
| F3 (C16 to C34)                         | 1197236 |           | < 100     | < 100  | NA  | < 100        | 93%                | 60%               | 140%  | 124%               | 60%               | 140%  | 128%         | 60%               | 140%  |
| F4 (C34 to C50)                         | 1197236 |           | < 100     | < 100  | NA  | < 100        | 87%                | 60%               | 140%  | 124%               | 60%               | 140%  | 121%         | 60%               | 140%  |

Comments: When the average of the sample and duplicate results is less than 5x the RDL, the Relative Percent Difference (RPD) will be indicated as Not Applicable (NA).

Certified By: \_\_\_\_\_





## Method Summary

CLIENT NAME: GOLDER ASSOCIATES LTD  
PROJECT: 19124906  
SAMPLING SITE:

AGAT WORK ORDER: 20Z613655  
ATTENTION TO: Keith Holmes  
SAMPLED BY: ALB

| PARAMETER                      | AGAT S.O.P   | LITERATURE REFERENCE                   | ANALYTICAL TECHNIQUE |
|--------------------------------|--------------|--|----------------------|
| Trace Organics Analysis        |              |  |                      |
| Benzene                        | VOL-91-5010  | modified from EPA SW-846 5230B & 8260  | (P&T)GC/MS           |
| Toluene                        | VOL-91-5010  | modified from EPA SW-846 5030C & 8260D | P&T GC/MS            |
| Ethylbenzene                   | VOL-91-5010  | modified from EPA SW-846 5030C & 8260D | P&T GC/MS            |
| Xylenes (Total)                | VOL-91-5010  | modified from EPA SW-846 5030C & 8260D | P&T GC/MS            |
| F1 (C6 - C10)                  | VOL-91- 5010 | modified from MOE PHC-E3421            | P&T GC/FID           |
| F1 (C6 to C10) minus BTEX      | VOL-91-5010  | modified from MOE PHC-E3421            | P&T GC/FID           |
| F2 (C10 to C16)                | VOL-91-5010  | modified from MOE PHC-E3421            | GC/FID               |
| F3 (C16 to C34)                | VOL-91-5010  | modified from MOE PHC-E3421            | GC/FID               |
| F4 (C34 to C50)                | VOL-91-5010  | modified from MOE PHC-E3421            | GC/FID               |
| Gravimetric Heavy Hydrocarbons | VOL-91-5010  | modified from MOE PHC-E3421            | BALANCE              |
| Terphenyl                      | VOL-91-5010  | modified from MOE PHC-E3421            | GC/FID               |
| Sediment                       |              |  |                      |



### Laboratory Use Only

Work Order #: 202613655  
Cooler Quantity: 0 ice - on ice  
Arrival Temperatures: 16.0 | 15.9 | 16.1  
LT - 8.9 | 8.8 | 7.6  
Custody Seal Intact:  Yes  No  N/A  
Notes: (on ice)

## Chain of Custody Record

If this is a Drinking Water sample, please use Drinking Water Chain of Custody Form (potable water consumed by humans)

### Report Information:

Company: Golder  
Contact: Keith Holmes  
Address: 1931 Robertson Rd.  
Bells Corners  
Phone: 613-592-9600 Fax: \_\_\_\_\_  
Reports to be sent to: Keith-holmes@golder.com  
1. Email: \_\_\_\_\_  
2. Email: \_\_\_\_\_

### Regulatory Requirements:

(Please check all applicable boxes)  
 Regulation 153/04  Excess Soils R406  Regulation 558  
Table 1 Indicate One  Sewer Use  
 Ind/Com  Sanitary  Storm  
 Res/Park  Agriculture  CCME  Other  
Sample from APEC?  Yes  No  Stockpile  In-situ  
Soil Texture (Check One)  Coarse  Fine  In-situ  Other  
Region \_\_\_\_\_  
Indicate One \_\_\_\_\_

### Turnaround Time (TAT) Required:

**Regular TAT**  5 to 7 Business Days  
**Rush TAT (Rush Surcharges Apply)**  
 3 Business Days  2 Business Days  Next Business Day  
OR Date Required (Rush Surcharges May Apply): \_\_\_\_\_

### Project Information:

Project: 19124906  
Site Location: ALB  
Sampled By: \_\_\_\_\_  
AGAT Quote #: \_\_\_\_\_ PO: \_\_\_\_\_  
Please note: If quotation number is not provided, client will be billed full price for analysis.

### Is this submission for a Record of Site Condition?

Yes  No

### Report Guideline on Certificate of Analysis

Yes  No

### Invoice Information:

Bill To Same: Yes  No   
Company: \_\_\_\_\_  
Contact: \_\_\_\_\_  
Address: \_\_\_\_\_  
Email: \_\_\_\_\_

### Sample Matrix Legend

**B** Biota  
**GW** Ground Water  
**O** Oil  
**P** Paint  
**S** Soil  
**SD** Sediment  
**SW** Surface Water

| Sample Identification | Date Sampled | Time Sampled | # of Containers | Sample Matrix | Comments/<br>Special Instructions | Y/N | 0. Reg 153 |  | Metals & Inorganics, inc. EC/SAR | Metals - IC/PMS, <input type="checkbox"/> CrVI, <input type="checkbox"/> Hg, <input type="checkbox"/> HWSB BTEX, F1-F4 PHCs Analyze F4G if required <input type="checkbox"/> Yes <input type="checkbox"/> No | PAHs | PCBs | VOC | Landfill Disposal Characterization TCLP: TOLP: <input type="checkbox"/> M&I <input type="checkbox"/> VOCs <input type="checkbox"/> ABNs <input type="checkbox"/> E1(a)/P <input type="checkbox"/> PCBs | Excess Soils SPLP Rainwater Leach SPLP: <input type="checkbox"/> Metals <input type="checkbox"/> VOCs <input type="checkbox"/> SVOCs | Excess Soils Characterization Package pH, IC/PMS Metals, BTEX, F1-F4 | Salt - EC/SAR | Potentially Hazardous or High Concentration (Y/N) |  |
|-----------------------|--------------|--------------|-----------------|---------------|-----------------------------------|-----|------------|--|----------------------------------|--|------|------|-----|--|--|--|---------------|---|--|
|                       |              |              |                 |               |                                   |     |            |  |                                  |  |      |      |     |  |  |  |               |   |  |
| 137-3                 | 20/05/16     | 8:55 AM      | 5               | GD            |                                   | N   |            |  |                                  | X  |      |      |     |  |  |  |               |   |  |
| 137-1                 | ↓            | 9:20 AM      | 5               | ↓             |                                   | N   |            |  |                                  | X  |      |      |     |  |  |  |               |   |  |
| Culvert               | ↓            | 9:40 AM      | 5               | ↓             |                                   | N   |            |  |                                  | X  |      |      |     |  |  |  |               |   |  |
| MW19                  | ↓            | 10:40 PM     | 5               | ↓             |                                   | N   |            |  |                                  | X  |      |      |     |  |  |  |               |   |  |
| 29-1                  | ↓            | 11:00 PM     | 5               | ↓             |                                   | N   |            |  |                                  | X  |      |      |     |  |  |  |               |   |  |
| 29-2                  | ↓            | 11:15 PM     | 5               | ↓             |                                   | N   |            |  |                                  | X  |      |      |     |  |  |  |               |   |  |
|                       |              |              |                 |               |                                   |     |            |  |                                  |  |      |      |     |  |  |  |               |   |  |
|                       |              |              |                 |               |                                   |     |            |  |                                  |  |      |      |     |  |  |  |               |   |  |
|                       |              |              |                 |               |                                   |     |            |  |                                  |  |      |      |     |  |  |  |               |   |  |
|                       |              |              |                 |               |                                   |     |            |  |                                  |  |      |      |     |  |  |  |               |   |  |
|                       |              |              |                 |               |                                   |     |            |  |                                  |  |      |      |     |  |  |  |               |   |  |

|   |                          |                       |   |                              |                         |
|---|--------------------------|-----------------------|---|------------------------------|-------------------------|
| Samples Relinquished By (Print Name and Sign):<br><u>Aaron Bradshaw</u> | Date:<br><u>20/05/16</u> | Time:<br><u>12:20</u> | Samples Received By (Print Name and Sign):<br><u>by the let</u> | Date:<br><u>20/06/16</u>     | Time:<br><u>12h46</u>   |
| Samples Relinquished By (Print Name and Sign):<br><u>UPS to FedEx</u>   | Date:<br><u>20/06/16</u> | Time:<br><u>16h00</u> | Samples Received By (Print Name and Sign):<br><u>Sharmin</u>    | Date:<br><u>June 17/2020</u> | Time:<br><u>9:45 am</u> |
| Page <u>1</u> of <u>1</u>   |                          |                       |   |                              |                         |
| N <sup>o</sup> : <b>T 104835</b>  |                          |                       |   |                              |                         |



CLIENT NAME: GOLDER ASSOCIATES LTD  
1931 ROBERTSON ROAD  
OTTAWA, ON K2H5B7  
(613) 592-9600

ATTENTION TO: Keith Holmes

PROJECT: 19124906

AGAT WORK ORDER: 20Z624793

SOIL ANALYSIS REVIEWED BY: Jacky Zhu, Spectroscopy Technician

TRACE ORGANICS REVIEWED BY: Oksana Gushyla, Trace Organics Lab Supervisor

DATE REPORTED: Jul 23, 2020

PAGES (INCLUDING COVER): 34

VERSION\*: 1

Should you require any information regarding this analysis please contact your client services representative at (905) 712-5100

\*Notes

**Disclaimer:**

- All work conducted herein has been done using accepted standard protocols, and generally accepted practices and methods. AGAT test methods may incorporate modifications from the specified reference methods to improve performance.
- All samples will be disposed of within 30 days following analysis, unless expressly agreed otherwise in writing. Please contact your Client Project Manager if you require additional sample storage time.
- AGAT's liability in connection with any delay, performance or non-performance of these services is only to the Client and does not extend to any other third party. Unless expressly agreed otherwise in writing, AGAT's liability is limited to the actual cost of the specific analysis or analyses included in the services.
- This Certificate shall not be reproduced except in full, without the written approval of the laboratory.
- The test results reported herewith relate only to the samples as received by the laboratory.
- Application of guidelines is provided "as is" without warranty of any kind, either expressed or implied, including, but not limited to, warranties of merchantability, fitness for a particular purpose, or non-infringement. AGAT assumes no responsibility for any errors or omissions in the guidelines contained in this document.
- All reportable information as specified by ISO/IEC 17025:2017 is available from AGAT Laboratories upon request.



## Certificate of Analysis

AGAT WORK ORDER: 20Z624793

PROJECT: 19124906

5835 COOPERS AVENUE  
MISSISSAUGA, ONTARIO  
CANADA L4Z 1Y2  
TEL (905)712-5100  
FAX (905)712-5122  
<http://www.agatlabs.com>

CLIENT NAME: GOLDER ASSOCIATES LTD

ATTENTION TO: Keith Holmes

SAMPLING SITE:

SAMPLED BY:

### O. Reg. 153(511) - All Metals (Soil)

DATE RECEIVED: 2020-07-14

DATE REPORTED: 2020-07-23

| Parameter                     | Unit | SAMPLE DESCRIPTION: |      | TP4-01 SA1 | TP4-02 SA1 | TP4-03 SA1 | TP4-04 SA1 | TP4-05 SA1 | TP4-07 SA1 | TP4-09 SA1 | TP4-10 SA1 |
|-------------------------------|------|---------------------|------|------------|------------|------------|------------|------------|------------|------------|------------|
|                               |      | G / S               | RDL  | Soil       | Soil       | Soil       | Soil       | Soil       | Soil       | Soil       | Soil       |
| DATE SAMPLED:                 |      | 2020-07-07          |      | 1271650    | 1271695    | 1271696    | 1271697    | 1271698    | 1271699    | 1271700    | 1271701    |
| Antimony                      | µg/g | 7.5                 | 0.8  | 1.1        | <0.8       | <0.8       | <0.8       | <0.8       | <0.8       | <0.8       | <0.8       |
| Arsenic                       | µg/g | 18                  | 1    | 4          | 2          | 2          | 3          | 1          | 3          | 2          | 1          |
| Barium                        | µg/g | 390                 | 2    | 164        | 120        | 266        | 61         | 19         | 88         | 218        | 404        |
| Beryllium                     | µg/g | 4                   | 0.5  | 0.5        | <0.5       | 0.5        | <0.5       | <0.5       | <0.5       | 0.5        | 0.5        |
| Boron                         | µg/g | 120                 | 5    | 12         | 5          | <5         | <5         | <5         | <5         | 5          | <5         |
| Boron (Hot Water Extractable) | µg/g | 1.5                 | 0.10 | 0.17       | 0.27       | 0.14       | 0.21       | <0.10      | 0.28       | 0.22       | 0.17       |
| Cadmium                       | µg/g | 1.2                 | 0.5  | <0.5       | <0.5       | <0.5       | <0.5       | <0.5       | <0.5       | <0.5       | <0.5       |
| Chromium                      | µg/g | 160                 | 5    | 23         | 29         | 71         | 16         | 13         | 23         | 63         | 111        |
| Cobalt                        | µg/g | 22                  | 0.5  | 6.8        | 8.6        | 15.6       | 3.9        | 3.3        | 6.3        | 13.6       | 21.0       |
| Copper                        | µg/g | 140                 | 1    | 34         | 15         | 34         | 9          | 3          | 11         | 29         | 38         |
| Lead                          | µg/g | 120                 | 1    | 67         | 10         | 10         | 22         | 3          | 41         | 11         | 10         |
| Molybdenum                    | µg/g | 6.9                 | 0.5  | 1.3        | <0.5       | <0.5       | <0.5       | <0.5       | 0.6        | 0.6        | <0.5       |
| Nickel                        | µg/g | 100                 | 1    | 17         | 17         | 38         | 9          | 6          | 14         | 34         | 52         |
| Selenium                      | µg/g | 2.4                 | 0.4  | 0.6        | <0.4       | 0.4        | 0.5        | <0.4       | 0.6        | 0.4        | 0.6        |
| Silver                        | µg/g | 20                  | 0.2  | 0.2        | <0.2       | <0.2       | <0.2       | <0.2       | <0.2       | <0.2       | <0.2       |
| Thallium                      | µg/g | 1                   | 0.4  | <0.4       | <0.4       | <0.4       | <0.4       | <0.4       | <0.4       | <0.4       | 0.5        |
| Uranium                       | µg/g | 23                  | 0.5  | 0.8        | 0.7        | 0.8        | 0.6        | 0.5        | 0.5        | 0.9        | 1.3        |
| Vanadium                      | µg/g | 86                  | 1    | 27         | 38         | 70         | 21         | 19         | 31         | 63         | 100        |
| Zinc                          | µg/g | 340                 | 5    | 154        | 45         | 95         | 50         | 16         | 66         | 84         | 159        |
| Chromium, Hexavalent          | µg/g | 8                   | 0.2  | <0.2       | <0.2       | <0.2       | <0.2       | <0.2       | <0.2       | <0.2       | <0.2       |
| Mercury                       | µg/g | 0.27                | 0.10 | 0.13       | <0.10      | <0.10      | <0.10      | <0.10      | <0.10      | <0.10      | <0.10      |

Certified By:





## Certificate of Analysis

AGAT WORK ORDER: 20Z624793

PROJECT: 19124906

5835 COOPERS AVENUE  
MISSISSAUGA, ONTARIO  
CANADA L4Z 1Y2  
TEL (905)712-5100  
FAX (905)712-5122  
<http://www.agatlabs.com>

CLIENT NAME: GOLDER ASSOCIATES LTD

ATTENTION TO: Keith Holmes

SAMPLING SITE:

SAMPLED BY:

### O. Reg. 153(511) - All Metals (Soil)

DATE RECEIVED: 2020-07-14

DATE REPORTED: 2020-07-23

| Parameter                     | Unit | SAMPLE DESCRIPTION: |            | TP4-11 SA1 | TP4-12 SA1 | TP4-13 SA1 | TP7-29 SA1 | TP7-30 SA1 | TP7-31 SA2 | TP7-32 SA1 | TP7-33 SA2 |
|-------------------------------|------|---------------------|------------|------------|------------|------------|------------|------------|------------|------------|------------|
|                               |      | G / S               | RDL        | Soil       | Soil       | Soil       | Soil       | Soil       | Soil       | Soil       | Soil       |
| DATE SAMPLED:                 |      | 2020-07-07          | 2020-07-07 | 2020-07-07 | 2020-07-08 | 2020-07-08 | 2020-07-08 | 2020-07-08 | 2020-07-08 | 2020-07-08 | 2020-07-08 |
|                               |      | 12:00               | 12:00      | 12:00      | 12:00      | 12:00      | 12:00      | 12:00      | 12:00      | 12:00      | 12:00      |
|                               |      | 1271702             | 1271703    | 1271704    | 1271705    | 1271738    | 1271739    | 1271740    | 1271741    |            |            |
| Antimony                      | µg/g | 7.5                 | 0.8        | <0.8       | <0.8       | <0.8       | <0.8       | <0.8       | <0.8       | <0.8       | <0.8       |
| Arsenic                       | µg/g | 18                  | 1          | 1          | 4          | 3          | 3          | <1         | 2          | 4          | <1         |
| Barium                        | µg/g | 390                 | 2          | 161        | 117        | 242        | 98         | 21         | 80         | 91         | 76         |
| Beryllium                     | µg/g | 4                   | 0.5        | <0.5       | 0.5        | <0.5       | <0.5       | <0.5       | <0.5       | <0.5       | <0.5       |
| Boron                         | µg/g | 120                 | 5          | 5          | 9          | <5         | 6          | <5         | <5         | 6          | <5         |
| Boron (Hot Water Extractable) | µg/g | 1.5                 | 0.10       | 0.19       | 0.35       | 0.26       | 0.36       | <0.10      | <0.10      | 0.29       | <0.10      |
| Cadmium                       | µg/g | 1.2                 | 0.5        | <0.5       | <0.5       | <0.5       | <0.5       | <0.5       | <0.5       | <0.5       | <0.5       |
| Chromium                      | µg/g | 160                 | 5          | 32         | 23         | 59         | 26         | 9          | 29         | 19         | 16         |
| Cobalt                        | µg/g | 22                  | 0.5        | 10.0       | 8.5        | 12.3       | 9.6        | 2.7        | 7.3        | 5.7        | 5.0        |
| Copper                        | µg/g | 140                 | 1          | 21         | 30         | 38         | 18         | 7          | 14         | 14         | 11         |
| Lead                          | µg/g | 120                 | 1          | 6          | 38         | 24         | 15         | 2          | 9          | 47         | 5          |
| Molybdenum                    | µg/g | 6.9                 | 0.5        | <0.5       | 0.8        | 1.1        | 0.5        | <0.5       | <0.5       | 0.9        | <0.5       |
| Nickel                        | µg/g | 100                 | 1          | 19         | 16         | 31         | 16         | 4          | 17         | 12         | 10         |
| Selenium                      | µg/g | 2.4                 | 0.4        | <0.4       | 0.7        | 0.6        | 0.4        | <0.4       | <0.4       | 0.7        | <0.4       |
| Silver                        | µg/g | 20                  | 0.2        | <0.2       | <0.2       | <0.2       | <0.2       | <0.2       | <0.2       | <0.2       | <0.2       |
| Thallium                      | µg/g | 1                   | 0.4        | <0.4       | <0.4       | <0.4       | <0.4       | <0.4       | <0.4       | <0.4       | <0.4       |
| Uranium                       | µg/g | 23                  | 0.5        | 0.6        | 0.5        | 0.9        | 0.6        | <0.5       | 0.7        | 0.5        | 0.6        |
| Vanadium                      | µg/g | 86                  | 1          | 41         | 28         | 56         | 34         | 14         | 32         | 25         | 26         |
| Zinc                          | µg/g | 340                 | 5          | 44         | 45         | 106        | 54         | 10         | 42         | 57         | 25         |
| Chromium, Hexavalent          | µg/g | 8                   | 0.2        | <0.2       | <0.2       | <0.2       | <0.2       | <0.2       | <0.2       | <0.2       | <0.2       |
| Mercury                       | µg/g | 0.27                | 0.10       | <0.10      | <0.10      | <0.10      | <0.10      | <0.10      | <0.10      | <0.10      | <0.10      |

Certified By:







## Certificate of Analysis

AGAT WORK ORDER: 20Z624793

PROJECT: 19124906

5835 COOPERS AVENUE  
MISSISSAUGA, ONTARIO  
CANADA L4Z 1Y2  
TEL (905)712-5100  
FAX (905)712-5122  
<http://www.agatlabs.com>

CLIENT NAME: GOLDER ASSOCIATES LTD

ATTENTION TO: Keith Holmes

SAMPLING SITE:

SAMPLED BY:

### O. Reg. 153(511) - All Metals (Soil)

DATE RECEIVED: 2020-07-14

DATE REPORTED: 2020-07-23

| Parameter                     | Unit | SAMPLE DESCRIPTION: |         | TP7-34 SA2 | TP7-35 SA1 | TP7-36 SA1 | TP4-37A | TP4-37B | TP4-15 SA1 | TP4-16 SA1 | TP6A-17 SA1 |
|-------------------------------|------|---------------------|---------|------------|------------|------------|---------|---------|------------|------------|-------------|
|                               |      | G / S               | RDL     | Soil       | Soil       | Soil       | Soil    | Soil    | Soil       | Soil       | Soil        |
| DATE SAMPLED:                 |      | 2020-07-08          |         | 12:00      | 12:00      | 12:00      | 12:00   | 12:00   | 12:00      | 12:00      | 12:00       |
|                               |      | 1271742             | 1271743 | 1271744    | 1271745    | 1271746    | 1271749 | 1271750 | 1271751    |            |             |
| Antimony                      | µg/g | 7.5                 | 0.8     | <0.8       | <0.8       | <0.8       | <0.8    | <0.8    | <0.8       | <0.8       | <0.8        |
| Arsenic                       | µg/g | 18                  | 1       | 1          | 2          | 3          | 2       | 2       | 4          | 3          | 2           |
| Barium                        | µg/g | 390                 | 2       | 63         | 123        | 102        | 342     | 322     | 74         | 99         | 81          |
| Beryllium                     | µg/g | 4                   | 0.5     | <0.5       | <0.5       | <0.5       | 0.7     | 0.8     | <0.5       | <0.5       | <0.5        |
| Boron                         | µg/g | 120                 | 5       | <5         | 5          | 10         | 5       | 7       | 7          | 14         | <5          |
| Boron (Hot Water Extractable) | µg/g | 1.5                 | 0.10    | <0.10      | 0.14       | 0.18       | 0.11    | 0.12    | 0.27       | 0.14       | 0.11        |
| Cadmium                       | µg/g | 1.2                 | 0.5     | <0.5       | <0.5       | <0.5       | <0.5    | <0.5    | <0.5       | <0.5       | <0.5        |
| Chromium                      | µg/g | 160                 | 5       | 15         | 29         | 17         | 45      | 47      | 18         | 18         | 25          |
| Cobalt                        | µg/g | 22                  | 0.5     | 5.9        | 6.7        | 7.0        | 12.2    | 12.9    | 7.8        | 6.7        | 7.0         |
| Copper                        | µg/g | 140                 | 1       | 12         | 21         | 13         | 27      | 29      | 18         | 13         | 12          |
| Lead                          | µg/g | 120                 | 1       | 6          | 13         | 19         | 11      | 16      | 87         | 10         | 8           |
| Molybdenum                    | µg/g | 6.9                 | 0.5     | <0.5       | <0.5       | 0.5        | <0.5    | <0.5    | 1.0        | <0.5       | <0.5        |
| Nickel                        | µg/g | 100                 | 1       | 10         | 18         | 12         | 30      | 35      | 15         | 11         | 13          |
| Selenium                      | µg/g | 2.4                 | 0.4     | <0.4       | 0.7        | 0.5        | <0.4    | 0.4     | 0.4        | 0.4        | <0.4        |
| Silver                        | µg/g | 20                  | 0.2     | <0.2       | <0.2       | <0.2       | <0.2    | <0.2    | <0.2       | <0.2       | <0.2        |
| Thallium                      | µg/g | 1                   | 0.4     | <0.4       | <0.4       | <0.4       | <0.4    | <0.4    | <0.4       | <0.4       | <0.4        |
| Uranium                       | µg/g | 23                  | 0.5     | 0.6        | 1.2        | <0.5       | 0.7     | 0.7     | <0.5       | <0.5       | 0.5         |
| Vanadium                      | µg/g | 86                  | 1       | 25         | 27         | 22         | 52      | 73      | 26         | 20         | 33          |
| Zinc                          | µg/g | 340                 | 5       | 24         | 69         | 31         | 69      | 98      | 79         | 24         | 34          |
| Chromium, Hexavalent          | µg/g | 8                   | 0.2     | <0.2       | <0.2       | <0.2       | <0.2    | <0.2    | <0.2       | <0.2       | <0.2        |
| Mercury                       | µg/g | 0.27                | 0.10    | <0.10      | <0.10      | <0.10      | <0.10   | <0.10   | <0.10      | <0.10      | <0.10       |

Certified By:





## Certificate of Analysis

AGAT WORK ORDER: 20Z624793

PROJECT: 19124906

5835 COOPERS AVENUE  
MISSISSAUGA, ONTARIO  
CANADA L4Z 1Y2  
TEL (905)712-5100  
FAX (905)712-5122  
<http://www.agatlabs.com>

CLIENT NAME: GOLDER ASSOCIATES LTD

ATTENTION TO: Keith Holmes

SAMPLING SITE:

SAMPLED BY:

### O. Reg. 153(511) - All Metals (Soil)

DATE RECEIVED: 2020-07-14

DATE REPORTED: 2020-07-23

| Parameter                     | Unit | SAMPLE DESCRIPTION: |                     |                     |                     |                     |                     |                     |                     |                     |                     |
|-------------------------------|------|---------------------|---------------------|---------------------|---------------------|---------------------|---------------------|---------------------|---------------------|---------------------|---------------------|
|                               |      | G / S               |                     | TP6A-20 SA1         | TP6B-21 SA2         | TP6B-22 SA1         | TP6B-24 SA1         | TP6B-25 SA1         | TP6B-26 SA1         | TP7-27 SA1          | TP7-28 SA1          |
|                               |      | RDL                 | Soil                | Soil                | Soil                | Soil                | Soil                | Soil                | Soil                | Soil                | Soil                |
|                               |      |                     | 2020-07-08<br>12:00 | 2020-07-08<br>12:00 | 2020-07-08<br>12:00 | 2020-07-08<br>12:00 | 2020-07-08<br>12:00 | 2020-07-08<br>12:00 | 2020-07-08<br>12:00 | 2020-07-08<br>12:00 | 2020-07-08<br>12:00 |
|                               |      |                     | 1271752             | 1271753             | 1271754             | 1271755             | 1271756             | 1271757             | 1271758             | 1271759             |                     |
| Antimony                      | µg/g | 7.5                 | 0.8                 | <0.8                | <0.8                | <0.8                | <0.8                | <0.8                | <0.8                | <0.8                | <0.8                |
| Arsenic                       | µg/g | 18                  | 1                   | 2                   | 3                   | 2                   | 4                   | 1                   | 3                   | 4                   | 3                   |
| Barium                        | µg/g | 390                 | 2                   | 356                 | 256                 | 77                  | 112                 | 49                  | 228                 | 86                  | 113                 |
| Beryllium                     | µg/g | 4                   | 0.5                 | 0.7                 | <0.5                | 0.6                 | <0.5                | <0.5                | 0.7                 | 0.5                 | <0.5                |
| Boron                         | µg/g | 120                 | 5                   | <5                  | 5                   | 6                   | 5                   | <5                  | 5                   | 6                   | <5                  |
| Boron (Hot Water Extractable) | µg/g | 1.5                 | 0.10                | 0.14                | <0.10               | <0.10               | 0.14                | <0.10               | 0.11                | 0.26                | 0.10                |
| Cadmium                       | µg/g | 1.2                 | 0.5                 | <0.5                | <0.5                | <0.5                | <0.5                | <0.5                | <0.5                | <0.5                | <0.5                |
| Chromium                      | µg/g | 160                 | 5                   | 104                 | 56                  | 18                  | 19                  | 12                  | 54                  | 23                  | 33                  |
| Cobalt                        | µg/g | 22                  | 0.5                 | 20.6                | 11.5                | 6.2                 | 5.4                 | 5.9                 | 13.7                | 7.0                 | 9.3                 |
| Copper                        | µg/g | 140                 | 1                   | 46                  | 22                  | 6                   | 31                  | 14                  | 30                  | 18                  | 20                  |
| Lead                          | µg/g | 120                 | 1                   | 13                  | 10                  | 7                   | 24                  | 8                   | 20                  | 49                  | 20                  |
| Molybdenum                    | µg/g | 6.9                 | 0.5                 | 0.5                 | 0.8                 | <0.5                | 0.5                 | <0.5                | <0.5                | 0.6                 | 0.5                 |
| Nickel                        | µg/g | 100                 | 1                   | 52                  | 48                  | 11                  | 13                  | 9                   | 29                  | 15                  | 19                  |
| Selenium                      | µg/g | 2.4                 | 0.4                 | 0.4                 | 0.4                 | 0.5                 | <0.4                | <0.4                | 0.4                 | 0.5                 | <0.4                |
| Silver                        | µg/g | 20                  | 0.2                 | <0.2                | <0.2                | <0.2                | <0.2                | <0.2                | <0.2                | <0.2                | <0.2                |
| Thallium                      | µg/g | 1                   | 0.4                 | 0.4                 | <0.4                | <0.4                | <0.4                | <0.4                | <0.4                | <0.4                | <0.4                |
| Uranium                       | µg/g | 23                  | 0.5                 | 1.1                 | 0.6                 | <0.5                | 0.7                 | 0.7                 | 0.7                 | 0.6                 | 0.6                 |
| Vanadium                      | µg/g | 86                  | 1                   | 101                 | 43                  | 25                  | 26                  | 21                  | 60                  | 27                  | 38                  |
| Zinc                          | µg/g | 340                 | 5                   | 126                 | 40                  | 31                  | 187                 | 26                  | 199                 | 56                  | 83                  |
| Chromium, Hexavalent          | µg/g | 8                   | 0.2                 | <0.2                | <0.2                | <0.2                | <0.2                | <0.2                | <0.2                | <0.2                | <0.2                |
| Mercury                       | µg/g | 0.27                | 0.10                | <0.10               | <0.10               | <0.10               | <0.10               | <0.10               | <0.10               | 0.13                | 0.17                |

Certified By:





## Certificate of Analysis

AGAT WORK ORDER: 20Z624793

PROJECT: 19124906

5835 COOPERS AVENUE  
MISSISSAUGA, ONTARIO  
CANADA L4Z 1Y2  
TEL (905)712-5100  
FAX (905)712-5122  
<http://www.agatlabs.com>

CLIENT NAME: GOLDER ASSOCIATES LTD

ATTENTION TO: Keith Holmes

SAMPLING SITE:

SAMPLED BY:

### O. Reg. 153(511) - All Metals (Soil)

DATE RECEIVED: 2020-07-14

DATE REPORTED: 2020-07-23

SAMPLE DESCRIPTION: DUP2  
SAMPLE TYPE: Soil  
DATE SAMPLED: 2020-07-08  
12:00  
1271830

| Parameter                     | Unit | G / S | RDL  | 1271830 |
|-------------------------------|------|-------|------|---------|
| Antimony                      | µg/g | 7.5   | 0.8  | <0.8    |
| Arsenic                       | µg/g | 18    | 1    | <1      |
| Barium                        | µg/g | 390   | 2    | 20      |
| Beryllium                     | µg/g | 4     | 0.5  | <0.5    |
| Boron                         | µg/g | 120   | 5    | <5      |
| Boron (Hot Water Extractable) | µg/g | 1.5   | 0.10 | <0.10   |
| Cadmium                       | µg/g | 1.2   | 0.5  | <0.5    |
| Chromium                      | µg/g | 160   | 5    | 7       |
| Cobalt                        | µg/g | 22    | 0.5  | 3.1     |
| Copper                        | µg/g | 140   | 1    | 7       |
| Lead                          | µg/g | 120   | 1    | 2       |
| Molybdenum                    | µg/g | 6.9   | 0.5  | <0.5    |
| Nickel                        | µg/g | 100   | 1    | 4       |
| Selenium                      | µg/g | 2.4   | 0.4  | <0.4    |
| Silver                        | µg/g | 20    | 0.2  | <0.2    |
| Thallium                      | µg/g | 1     | 0.4  | <0.4    |
| Uranium                       | µg/g | 23    | 0.5  | 0.7     |
| Vanadium                      | µg/g | 86    | 1    | 19      |
| Zinc                          | µg/g | 340   | 5    | 11      |
| Chromium, Hexavalent          | µg/g | 8     | 0.2  | <0.2    |
| Mercury                       | µg/g | 0.27  | 0.10 | <0.10   |

Comments: RDL - Reported Detection Limit; G / S - Guideline / Standard: Refers to Table 3: Full Depth Generic Site Condition Standards in a Non-Potable Ground Water Condition - Soil - Residential/Parkland/Institutional Property Use - Coarse Textured Soils  
Guideline values are for general reference only. The guidelines provided may or may not be relevant for the intended use. Refer directly to the applicable standard for regulatory interpretation.

Analysis performed at AGAT Toronto (unless marked by \*)

Certified By:





## Certificate of Analysis

AGAT WORK ORDER: 20Z624793

PROJECT: 19124906

5835 COOPERS AVENUE  
MISSISSAUGA, ONTARIO  
CANADA L4Z 1Y2  
TEL (905)712-5100  
FAX (905)712-5122  
<http://www.agatlabs.com>

CLIENT NAME: GOLDER ASSOCIATES LTD

ATTENTION TO: Keith Holmes

SAMPLING SITE:

SAMPLED BY:

### O. Reg. 153(511) - Metals & Inorganics (Soil)

DATE RECEIVED: 2020-07-14

DATE REPORTED: 2020-07-23

| Parameter                     | Unit     | SAMPLE DESCRIPTION: |       | SPD-SA1             | SPD-SA2             | SPD-SA3             | SPD-SA4             | SPD-SA5             | SPD-SA6             | SPD-SA7             |
|-------------------------------|----------|---------------------|-------|---------------------|---------------------|---------------------|---------------------|---------------------|---------------------|---------------------|
|                               |          | G / S               | RDL   | Soil                | Soil                | Soil                | Soil                | Soil                | Soil                | Soil                |
|                               |          |                     |       | 2020-07-08<br>12:00 | 2020-07-08<br>12:00 | 2020-07-09<br>12:00 | 2020-07-09<br>12:00 | 2020-07-09<br>12:00 | 2020-07-09<br>12:00 | 2020-07-09<br>12:00 |
|                               |          |                     |       | 1271747             | 1271748             | 1271760             | 1271761             | 1271762             | 1271763             | 1271764             |
| Antimony                      | µg/g     | 7.5                 | 0.8   | <0.8                | <0.8                | <0.8                | <0.8                | <0.8                | <0.8                | <0.8                |
| Arsenic                       | µg/g     | 18                  | 1     | 2                   | 2                   | 2                   | 2                   | 1                   | 2                   | 2                   |
| Barium                        | µg/g     | 390                 | 2     | 374                 | 246                 | 348                 | 416                 | 317                 | 381                 | 327                 |
| Beryllium                     | µg/g     | 4                   | 0.5   | 1.0                 | 0.5                 | 0.8                 | 1.0                 | 0.7                 | 0.8                 | 0.9                 |
| Boron                         | µg/g     | 120                 | 5     | 5                   | <5                  | <5                  | <5                  | <5                  | <5                  | 5                   |
| Boron (Hot Water Extractable) | µg/g     | 1.5                 | 0.10  | 0.28                | 0.14                | 0.26                | 0.15                | <0.10               | <0.10               | 0.34                |
| Cadmium                       | µg/g     | 1.2                 | 0.5   | <0.5                | <0.5                | <0.5                | <0.5                | <0.5                | <0.5                | <0.5                |
| Chromium                      | µg/g     | 160                 | 5     | 113                 | 71                  | 111                 | 131                 | 98                  | 120                 | 101                 |
| Cobalt                        | µg/g     | 22                  | 0.5   | 21.8                | 13.6                | 21.4                | 26.7                | 19.9                | 25.6                | 17.9                |
| Copper                        | µg/g     | 140                 | 1     | 57                  | 37                  | 50                  | 59                  | 49                  | 59                  | 45                  |
| Lead                          | µg/g     | 120                 | 1     | 9                   | 13                  | 9                   | 8                   | 6                   | 8                   | 11                  |
| Molybdenum                    | µg/g     | 6.9                 | 0.5   | <0.5                | 0.5                 | <0.5                | <0.5                | <0.5                | 0.6                 | <0.5                |
| Nickel                        | µg/g     | 100                 | 1     | 58                  | 39                  | 56                  | 69                  | 53                  | 64                  | 46                  |
| Selenium                      | µg/g     | 2.4                 | 0.4   | 0.7                 | 0.5                 | 0.6                 | 0.4                 | <0.4                | 0.5                 | 0.9                 |
| Silver                        | µg/g     | 20                  | 0.2   | <0.2                | <0.2                | <0.2                | <0.2                | <0.2                | <0.2                | <0.2                |
| Thallium                      | µg/g     | 1                   | 0.4   | 0.5                 | <0.4                | 0.4                 | 0.5                 | 0.4                 | 0.5                 | 0.4                 |
| Uranium                       | µg/g     | 23                  | 0.5   | 1.7                 | 0.8                 | 1.1                 | 1.4                 | 0.9                 | 1.2                 | 2.1                 |
| Vanadium                      | µg/g     | 86                  | 1     | 102                 | 69                  | 100                 | 119                 | 90                  | 113                 | 94                  |
| Zinc                          | µg/g     | 340                 | 5     | 146                 | 131                 | 134                 | 152                 | 114                 | 136                 | 140                 |
| Chromium, Hexavalent          | µg/g     | 8                   | 0.2   | <0.2                | <0.2                | <0.2                | <0.2                | <0.2                | <0.2                | <0.2                |
| Cyanide, Free                 | µg/g     | 0.051               | 0.040 | <0.040              | <0.040              | <0.040              | <0.040              | <0.040              | <0.040              | <0.040              |
| Mercury                       | µg/g     | 0.27                | 0.10  | <0.10               | <0.10               | <0.10               | <0.10               | <0.10               | <0.10               | <0.10               |
| Electrical Conductivity (2:1) | mS/cm    | 0.7                 | 0.005 | 0.133               | 0.143               | 0.098               | 0.057               | 0.124               | 0.104               | 0.110               |
| Sodium Adsorption Ratio       | NA       | 5                   | NA    | 0.208               | 0.841               | 0.277               | 0.179               | 0.443               | 0.394               | 0.193               |
| pH, 2:1 CaCl2 Extraction      | pH Units | 5.0-9.0             | NA    | 7.46                | 7.64                | 7.20                | 7.09                | 7.42                | 7.49                | 7.32                |

Certified By:





**AGAT** Laboratories

# Certificate of Analysis

AGAT WORK ORDER: 20Z624793

PROJECT: 19124906

5835 COOPERS AVENUE  
MISSISSAUGA, ONTARIO  
CANADA L4Z 1Y2  
TEL (905)712-5100  
FAX (905)712-5122  
<http://www.agatlabs.com>

CLIENT NAME: GOLDER ASSOCIATES LTD

ATTENTION TO: Keith Holmes

SAMPLING SITE:

SAMPLED BY:

O. Reg. 153(511) - Metals & Inorganics (Soil)

DATE RECEIVED: 2020-07-14

DATE REPORTED: 2020-07-23

Comments: RDL - Reported Detection Limit; G / S - Guideline / Standard: Refers to Table 3: Full Depth Generic Site Condition Standards in a Non-Potable Ground Water Condition - Soil - Residential/Parkland/Institutional Property Use - Coarse Textured Soils

Guideline values are for general reference only. The guidelines provided may or may not be relevant for the intended use. Refer directly to the applicable standard for regulatory interpretation.

1271747-1271764 EC was determined on the DI water extract obtained from the 2:1 leaching procedure (2 parts DI water:1 part soil). pH was determined on the 0.01M CaCl2 extract prepared at 2:1 ratio. SAR is a calculated parameter.

Analysis performed at AGAT Toronto (unless marked by \*)

Certified By:





## Certificate of Analysis

AGAT WORK ORDER: 20Z624793

PROJECT: 19124906

5835 COOPERS AVENUE  
MISSISSAUGA, ONTARIO  
CANADA L4Z 1Y2  
TEL (905)712-5100  
FAX (905)712-5122  
<http://www.agatlabs.com>

CLIENT NAME: GOLDER ASSOCIATES LTD

ATTENTION TO: Keith Holmes

SAMPLING SITE:

SAMPLED BY:

### O. Reg. 153(511) - ORPs (Soil)

DATE RECEIVED: 2020-07-14

DATE REPORTED: 2020-07-23

|                          |          | SAMPLE DESCRIPTION: |     | TP4-15 SA1          | TP6A-17 SA1         | TP6B-21 SA2         | TP7-27 SA1          |
|--------------------------|----------|---------------------|-----|---------------------|---------------------|---------------------|---------------------|
|                          |          | SAMPLE TYPE:        |     | Soil                | Soil                | Soil                | Soil                |
|                          |          | DATE SAMPLED:       |     | 2020-07-08<br>12:00 | 2020-07-08<br>12:00 | 2020-07-08<br>12:00 | 2020-07-08<br>12:00 |
| Parameter                | Unit     | G / S               | RDL | 1271749             | 1271751             | 1271753             | 1271758             |
| pH, 2:1 CaCl2 Extraction | pH Units |                     | NA  | 7.54                | 7.28                | 7.62                | 7.42                |

Comments: RDL - Reported Detection Limit; G / S - Guideline / Standard

1271749-1271758 pH was determined on the 0.01M CaCl2 extract obtained from 2:1 leaching procedure (2 parts extraction fluid:1 part wet soil).

Analysis performed at AGAT Toronto (unless marked by \*)

Certified By:





## Certificate of Analysis

AGAT WORK ORDER: 20Z624793

PROJECT: 19124906

5835 COOPERS AVENUE  
MISSISSAUGA, ONTARIO  
CANADA L4Z 1Y2  
TEL (905)712-5100  
FAX (905)712-5122  
<http://www.agatlabs.com>

CLIENT NAME: GOLDER ASSOCIATES LTD

ATTENTION TO: Keith Holmes

SAMPLING SITE:

SAMPLED BY:

### O. Reg. 153(511) - PAHs (Soil)

DATE RECEIVED: 2020-07-14

DATE REPORTED: 2020-07-23

| Parameter                 | Unit | SAMPLE DESCRIPTION: |            | TP4-01 SA1 | TP4-02 SA1 | TP4-03 SA1 | TP4-04 SA1 | TP4-05 SA1 | TP4-07 SA1 | TP4-09 SA1 | TP4-10 SA1 |
|---------------------------|------|---------------------|------------|------------|------------|------------|------------|------------|------------|------------|------------|
|                           |      | G / S               | RDL        | Soil       | Soil       | Soil       | Soil       | Soil       | Soil       | Soil       | Soil       |
| DATE SAMPLED:             |      | 2020-07-07          | 2020-07-07 | 2020-07-07 | 2020-07-07 | 2020-07-07 | 2020-07-07 | 2020-07-07 | 2020-07-07 | 2020-07-07 | 2020-07-07 |
|                           |      | 12:00               | 12:00      | 12:00      | 12:00      | 12:00      | 12:00      | 12:00      | 12:00      | 12:00      | 12:00      |
|                           |      | 1271650             | 1271695    | 1271696    | 1271697    | 1271698    | 1271699    | 1271700    | 1271701    | 1271701    | 1271701    |
| Naphthalene               | µg/g | 0.6                 | 0.05       | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Acenaphthylene            | µg/g | 0.15                | 0.05       | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Acenaphthene              | µg/g | 7.9                 | 0.05       | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Fluorene                  | µg/g | 62                  | 0.05       | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Phenanthrene              | µg/g | 6.2                 | 0.05       | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Anthracene                | µg/g | 0.67                | 0.05       | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Fluoranthene              | µg/g | 0.69                | 0.05       | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | 0.05       | 0.06       |
| Pyrene                    | µg/g | 78                  | 0.05       | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | 0.08       | <0.05      | 0.05       |
| Benz(a)anthracene         | µg/g | 0.5                 | 0.05       | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Chrysene                  | µg/g | 7                   | 0.05       | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Benzo(b)fluoranthene      | µg/g | 0.78                | 0.05       | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Benzo(k)fluoranthene      | µg/g | 0.78                | 0.05       | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Benzo(a)pyrene            | µg/g | 0.3                 | 0.05       | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Indeno(1,2,3-cd)pyrene    | µg/g | 0.38                | 0.05       | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Dibenz(a,h)anthracene     | µg/g | 0.1                 | 0.05       | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Benzo(g,h,i)perylene      | µg/g | 6.6                 | 0.05       | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| 1 and 2 Methylnaphthalene | µg/g | 0.99                | 0.05       | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Moisture Content          | %    |                     | 0.1        | 11.4       | 13.2       | 20.9       | 10.9       | 4.8        | 10.1       | 14.6       | 26.6       |
| Surrogate                 | Unit | Acceptable Limits   |            |            |            |            |            |            |            |            |            |
| Naphthalene-d8            | %    | 50-140              |            | 67         | 61         | 78         | 62         | 86         | 71         | 82         | 64         |
| Acenaphthene-d10          | %    | 50-140              |            | 84         | 81         | 77         | 81         | 91         | 75         | 92         | 82         |
| Chrysene-d12              | %    | 50-140              |            | 74         | 74         | 80         | 77         | 116        | 76         | 100        | 75         |

Certified By:



## Certificate of Analysis

AGAT WORK ORDER: 20Z624793

PROJECT: 19124906

5835 COOPERS AVENUE  
MISSISSAUGA, ONTARIO  
CANADA L4Z 1Y2  
TEL (905)712-5100  
FAX (905)712-5122  
<http://www.agatlabs.com>

CLIENT NAME: GOLDER ASSOCIATES LTD

ATTENTION TO: Keith Holmes

SAMPLING SITE:

SAMPLED BY:

### O. Reg. 153(511) - PAHs (Soil)

DATE RECEIVED: 2020-07-14

DATE REPORTED: 2020-07-23

| Parameter                 | Unit | SAMPLE DESCRIPTION: |            | TP4-11 SA1 | TP4-12 SA1 | TP4-13 SA1 | TP7-29 SA1 | TP7-30 SA1 | TP7-31 SA2 | TP7-32 SA1 | TP7-33 SA2 |
|---------------------------|------|---------------------|------------|------------|------------|------------|------------|------------|------------|------------|------------|
|                           |      | G / S               | RDL        | Soil       | Soil       | Soil       | Soil       | Soil       | Soil       | Soil       | Soil       |
| DATE SAMPLED:             |      | 2020-07-07          | 2020-07-07 | 2020-07-07 | 2020-07-08 | 2020-07-08 | 2020-07-08 | 2020-07-08 | 2020-07-08 | 2020-07-08 | 2020-07-08 |
|                           |      | 12:00               | 12:00      | 12:00      | 12:00      | 12:00      | 12:00      | 12:00      | 12:00      | 12:00      | 12:00      |
|                           |      | 1271702             | 1271703    | 1271704    | 1271705    | 1271708    | 1271738    | 1271739    | 1271740    | 1271741    |            |
| Naphthalene               | µg/g | 0.6                 | 0.05       | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Acenaphthylene            | µg/g | 0.15                | 0.05       | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Acenaphthene              | µg/g | 7.9                 | 0.05       | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Fluorene                  | µg/g | 62                  | 0.05       | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Phenanthrene              | µg/g | 6.2                 | 0.05       | <0.05      | <0.05      | 0.05       | 0.11       | <0.05      | <0.05      | 0.05       | <0.05      |
| Anthracene                | µg/g | 0.67                | 0.05       | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Fluoranthene              | µg/g | 0.69                | 0.05       | 0.07       | <0.05      | 0.12       | 0.22       | <0.05      | <0.05      | 0.10       | <0.05      |
| Pyrene                    | µg/g | 78                  | 0.05       | 0.06       | <0.05      | 0.10       | 0.17       | <0.05      | <0.05      | 0.08       | <0.05      |
| Benz(a)anthracene         | µg/g | 0.5                 | 0.05       | <0.05      | <0.05      | 0.05       | 0.09       | <0.05      | <0.05      | <0.05      | <0.05      |
| Chrysene                  | µg/g | 7                   | 0.05       | <0.05      | <0.05      | 0.07       | 0.09       | <0.05      | <0.05      | 0.05       | <0.05      |
| Benzo(b)fluoranthene      | µg/g | 0.78                | 0.05       | <0.05      | <0.05      | 0.06       | 0.08       | <0.05      | <0.05      | 0.05       | <0.05      |
| Benzo(k)fluoranthene      | µg/g | 0.78                | 0.05       | <0.05      | <0.05      | <0.05      | 0.09       | <0.05      | <0.05      | <0.05      | <0.05      |
| Benzo(a)pyrene            | µg/g | 0.3                 | 0.05       | <0.05      | <0.05      | 0.05       | 0.07       | <0.05      | <0.05      | <0.05      | <0.05      |
| Indeno(1,2,3-cd)pyrene    | µg/g | 0.38                | 0.05       | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Dibenz(a,h)anthracene     | µg/g | 0.1                 | 0.05       | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Benzo(g,h,i)perylene      | µg/g | 6.6                 | 0.05       | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| 1 and 2 Methylnaphthalene | µg/g | 0.99                | 0.05       | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Moisture Content          | %    |                     | 0.1        | 18.4       | 5.9        | 11.4       | 5.9        | 3.7        | 10.2       | 6.8        | 12.5       |
| Surrogate                 | Unit | Acceptable Limits   |            |            |            |            |            |            |            |            |            |
| Naphthalene-d8            | %    | 50-140              |            | 67         | 79         | 78         | 78         | 85         | 74         | 71         | 91         |
| Acenaphthene-d10          | %    | 50-140              |            | 84         | 82         | 79         | 79         | 94         | 88         | 71         | 113        |
| Chrysene-d12              | %    | 50-140              |            | 78         | 96         | 76         | 85         | 93         | 91         | 77         | 94         |

Certified By:





## Certificate of Analysis

AGAT WORK ORDER: 20Z624793

PROJECT: 19124906

5835 COOPERS AVENUE  
MISSISSAUGA, ONTARIO  
CANADA L4Z 1Y2  
TEL (905)712-5100  
FAX (905)712-5122  
<http://www.agatlabs.com>

CLIENT NAME: GOLDER ASSOCIATES LTD

ATTENTION TO: Keith Holmes

SAMPLING SITE:

SAMPLED BY:

### O. Reg. 153(511) - PAHs (Soil)

DATE RECEIVED: 2020-07-14

DATE REPORTED: 2020-07-23

| Parameter                 | Unit | SAMPLE DESCRIPTION: |      | TP7-34 SA2 | TP7-35 SA1 | TP7-36 SA1 | TP4-37A    | TP4-37B    | SPD-SA1    | SPD-SA2    | TP4-15 SA1 |
|---------------------------|------|---------------------|------|------------|------------|------------|------------|------------|------------|------------|------------|
|                           |      | G / S               | RDL  | Soil       | Soil       | Soil       | Soil       | Soil       | Soil       | Soil       | Soil       |
|                           |      | DATE SAMPLED:       |      | 2020-07-08 | 2020-07-08 | 2020-07-08 | 2020-07-08 | 2020-07-08 | 2020-07-08 | 2020-07-08 | 2020-07-08 |
|                           |      |                     |      | 12:00      | 12:00      | 12:00      | 12:00      | 12:00      | 12:00      | 12:00      | 12:00      |
|                           |      |                     |      | 1271742    | 1271743    | 1271744    | 1271745    | 1271746    | 1271747    | 1271748    | 1271749    |
| Naphthalene               | µg/g | 0.6                 | 0.05 | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Acenaphthylene            | µg/g | 0.15                | 0.05 | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Acenaphthene              | µg/g | 7.9                 | 0.05 | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Fluorene                  | µg/g | 62                  | 0.05 | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Phenanthrene              | µg/g | 6.2                 | 0.05 | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Anthracene                | µg/g | 0.67                | 0.05 | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Fluoranthene              | µg/g | 0.69                | 0.05 | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | 0.08       | <0.05      |
| Pyrene                    | µg/g | 78                  | 0.05 | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | 0.06       | <0.05      |
| Benz(a)anthracene         | µg/g | 0.5                 | 0.05 | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Chrysene                  | µg/g | 7                   | 0.05 | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Benzo(b)fluoranthene      | µg/g | 0.78                | 0.05 | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Benzo(k)fluoranthene      | µg/g | 0.78                | 0.05 | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Benzo(a)pyrene            | µg/g | 0.3                 | 0.05 | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Indeno(1,2,3-cd)pyrene    | µg/g | 0.38                | 0.05 | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Dibenz(a,h)anthracene     | µg/g | 0.1                 | 0.05 | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Benzo(g,h,i)perylene      | µg/g | 6.6                 | 0.05 | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| 1 and 2 Methylnaphthalene | µg/g | 0.99                | 0.05 | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Moisture Content          | %    |                     | 0.1  | 24.4       | 14.6       | 8.6        | 23.7       | 22.3       | 24.9       | 23.7       | 8.8        |
| Surrogate                 | Unit | Acceptable Limits   |      |            |            |            |            |            |            |            |            |
| Naphthalene-d8            | %    | 50-140              |      | 91         | 77         | 74         | 77         | 74         | 73         | 73         | 79         |
| Acenaphthene-d10          | %    | 50-140              |      | 93         | 79         | 86         | 87         | 82         | 76         | 78         | 82         |
| Chrysene-d12              | %    | 50-140              |      | 101        | 79         | 91         | 91         | 88         | 78         | 78         | 84         |

Certified By:



## Certificate of Analysis

AGAT WORK ORDER: 20Z624793

PROJECT: 19124906

5835 COOPERS AVENUE  
MISSISSAUGA, ONTARIO  
CANADA L4Z 1Y2  
TEL (905)712-5100  
FAX (905)712-5122  
<http://www.agatlabs.com>

CLIENT NAME: GOLDER ASSOCIATES LTD

ATTENTION TO: Keith Holmes

SAMPLING SITE:

SAMPLED BY:

### O. Reg. 153(511) - PAHs (Soil)

DATE RECEIVED: 2020-07-14

DATE REPORTED: 2020-07-23

| Parameter                 | Unit | SAMPLE DESCRIPTION: |      | TP4-16 SA1 | TP6A-17 SA1 | TP6A-20 SA1 | TP6B-21 SA2 | TP6B-22 SA1 | TP6B-24 SA1 | TP6B-25 SA1 | TP6B-26 SA1 |
|---------------------------|------|---------------------|------|------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
|                           |      | G / S               | RDL  | Soil       | Soil        | Soil        | Soil        | Soil        | Soil        | Soil        | Soil        |
|                           |      | DATE SAMPLED:       |      | 2020-07-08 | 2020-07-08  | 2020-07-08  | 2020-07-08  | 2020-07-08  | 2020-07-08  | 2020-07-08  | 2020-07-08  |
|                           |      |                     |      | 12:00      | 12:00       | 12:00       | 12:00       | 12:00       | 12:00       | 12:00       | 12:00       |
|                           |      |                     |      | 1271750    | 1271751     | 1271752     | 1271753     | 1271754     | 1271755     | 1271756     | 1271757     |
| Naphthalene               | µg/g | 0.6                 | 0.05 | <0.05      | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       |
| Acenaphthylene            | µg/g | 0.15                | 0.05 | <0.05      | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       |
| Acenaphthene              | µg/g | 7.9                 | 0.05 | <0.05      | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       |
| Fluorene                  | µg/g | 62                  | 0.05 | <0.05      | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       |
| Phenanthrene              | µg/g | 6.2                 | 0.05 | <0.05      | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       |
| Anthracene                | µg/g | 0.67                | 0.05 | <0.05      | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       |
| Fluoranthene              | µg/g | 0.69                | 0.05 | <0.05      | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       |
| Pyrene                    | µg/g | 78                  | 0.05 | <0.05      | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       |
| Benz(a)anthracene         | µg/g | 0.5                 | 0.05 | <0.05      | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       |
| Chrysene                  | µg/g | 7                   | 0.05 | <0.05      | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       |
| Benzo(b)fluoranthene      | µg/g | 0.78                | 0.05 | <0.05      | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       |
| Benzo(k)fluoranthene      | µg/g | 0.78                | 0.05 | <0.05      | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       |
| Benzo(a)pyrene            | µg/g | 0.3                 | 0.05 | <0.05      | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       |
| Indeno(1,2,3-cd)pyrene    | µg/g | 0.38                | 0.05 | <0.05      | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       |
| Dibenz(a,h)anthracene     | µg/g | 0.1                 | 0.05 | <0.05      | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       |
| Benzo(g,h,i)perylene      | µg/g | 6.6                 | 0.05 | <0.05      | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       |
| 1 and 2 Methylnaphthalene | µg/g | 0.99                | 0.05 | <0.05      | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       |
| Moisture Content          | %    |                     | 0.1  | 8.2        | 8.1         | 21.5        | 11.1        | 7.5         | 4.8         | 5.3         | 12.7        |
| Surrogate                 | Unit | Acceptable Limits   |      |            |             |             |             |             |             |             |             |
| Naphthalene-d8            | %    | 50-140              |      | 81         | 105         | 85          | 70          | 95          | 73          | 76          | 74          |
| Acenaphthene-d10          | %    | 50-140              |      | 86         | 70          | 78          | 72          | 70          | 87          | 85          | 92          |
| Chrysene-d12              | %    | 50-140              |      | 86         | 73          | 75          | 82          | 74          | 72          | 70          | 81          |

Certified By:



## Certificate of Analysis

AGAT WORK ORDER: 20Z624793

PROJECT: 19124906

5835 COOPERS AVENUE  
MISSISSAUGA, ONTARIO  
CANADA L4Z 1Y2  
TEL (905)712-5100  
FAX (905)712-5122  
<http://www.agatlabs.com>

CLIENT NAME: GOLDER ASSOCIATES LTD

ATTENTION TO: Keith Holmes

SAMPLING SITE:

SAMPLED BY:

### O. Reg. 153(511) - PAHs (Soil)

DATE RECEIVED: 2020-07-14

DATE REPORTED: 2020-07-23

| Parameter                  | Unit | SAMPLE DESCRIPTION: |      | TP7-27 SA1 | TP7-28 SA1 | SPD-SA3    | SPD-SA4    | SPD-SA5    | SPD-SA6    | SPD-SA7    | DUP2       |
|----------------------------|------|---------------------|------|------------|------------|------------|------------|------------|------------|------------|------------|
|                            |      | G / S               | RDL  | Soil       | Soil       | Soil       | Soil       | Soil       | Soil       | Soil       | Soil       |
|                            |      | DATE SAMPLED:       |      | 2020-07-08 | 2020-07-08 | 2020-07-09 | 2020-07-09 | 2020-07-09 | 2020-07-09 | 2020-07-09 | 2020-07-08 |
|                            |      |                     |      | 12:00      | 12:00      | 12:00      | 12:00      | 12:00      | 12:00      | 12:00      | 12:00      |
|                            |      |                     |      | 1271758    | 1271759    | 1271760    | 1271761    | 1271762    | 1271763    | 1271764    | 1271830    |
| Naphthalene                | µg/g | 0.6                 | 0.05 | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Acenaphthylene             | µg/g | 0.15                | 0.05 | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Acenaphthene               | µg/g | 7.9                 | 0.05 | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Fluorene                   | µg/g | 62                  | 0.05 | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Phenanthrene               | µg/g | 6.2                 | 0.05 | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Anthracene                 | µg/g | 0.67                | 0.05 | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Fluoranthene               | µg/g | 0.69                | 0.05 | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | 0.09       | <0.05      | <0.05      |
| Pyrene                     | µg/g | 78                  | 0.05 | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | 0.08       | <0.05      | <0.05      |
| Benz(a)anthracene          | µg/g | 0.5                 | 0.05 | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Chrysene                   | µg/g | 7                   | 0.05 | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Benzo(b)fluoranthene       | µg/g | 0.78                | 0.05 | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Benzo(k)fluoranthene       | µg/g | 0.78                | 0.05 | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Benzo(a)pyrene             | µg/g | 0.3                 | 0.05 | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Indeno(1,2,3-cd)pyrene     | µg/g | 0.38                | 0.05 | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Dibenz(a,h)anthracene      | µg/g | 0.1                 | 0.05 | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Benzo(g,h,i)perylene       | µg/g | 6.6                 | 0.05 | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| 1 and 2 Methyl naphthalene | µg/g | 0.99                | 0.05 | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Moisture Content           | %    |                     | 0.1  | 27.7       | 7.2        | 26.2       | 23.8       | 25.9       | 26.5       | 23.8       | 8.0        |
| Surrogate                  | Unit | Acceptable Limits   |      |            |            |            |            |            |            |            |            |
| Naphthalene-d8             | %    | 50-140              |      | 93         | 82         | 72         | 85         | 84         | 78         | 84         | 71         |
| Acenaphthene-d10           | %    | 50-140              |      | 78         | 95         | 83         | 95         | 97         | 88         | 97         | 83         |
| Chrysene-d12               | %    | 50-140              |      | 83         | 80         | 85         | 102        | 99         | 93         | 92         | 89         |

Comments: RDL - Reported Detection Limit; G / S - Guideline / Standard: Refers to Table 3: Full Depth Generic Site Condition Standards in a Non-Potable Ground Water Condition - Soil - Residential/Parkland/Institutional Property Use - Coarse Textured Soils  
Guideline values are for general reference only. The guidelines provided may or may not be relevant for the intended use. Refer directly to the applicable standard for regulatory interpretation.

1271650-1271830 Results are based on the dry weight of the soil.

Note: The result for Benzo(b)Fluoranthene is the total of the Benzo(b)&j)Fluoranthene isomers because the isomers co-elute on the GC column.  
2- and 1-Methyl Naphthalene is a calculated parameter. The calculated value is the sum of 2-Methyl Naphthalene and 1-Methyl Naphthalene.

Analysis performed at AGAT Toronto (unless marked by \*)

Certified By:



## Certificate of Analysis

AGAT WORK ORDER: 20Z624793

PROJECT: 19124906

5835 COOPERS AVENUE  
MISSISSAUGA, ONTARIO  
CANADA L4Z 1Y2  
TEL (905)712-5100  
FAX (905)712-5122  
<http://www.agatlabs.com>

CLIENT NAME: GOLDER ASSOCIATES LTD

ATTENTION TO: Keith Holmes

SAMPLING SITE:

SAMPLED BY:

### O. Reg. 153(511) - PHCs F1 - F4 (with PAHs) (Soil)

DATE RECEIVED: 2020-07-14

DATE REPORTED: 2020-07-23

| Parameter                         | Unit | SAMPLE DESCRIPTION: |            | TP4-01 SA1 | TP4-02 SA1 | TP4-03 SA1 | TP4-04 SA1 | TP4-05 SA1 | TP4-07 SA1 | TP4-09 SA1 | TP4-10 SA1 |
|-----------------------------------|------|---------------------|------------|------------|------------|------------|------------|------------|------------|------------|------------|
|                                   |      | G / S               | RDL        | Soil       | Soil       | Soil       | Soil       | Soil       | Soil       | Soil       | Soil       |
| DATE SAMPLED:                     |      | 2020-07-07          | 2020-07-07 | 2020-07-07 | 2020-07-07 | 2020-07-07 | 2020-07-07 | 2020-07-07 | 2020-07-07 | 2020-07-07 | 2020-07-07 |
|                                   |      | 12:00               | 12:00      | 12:00      | 12:00      | 12:00      | 12:00      | 12:00      | 12:00      | 12:00      | 12:00      |
|                                   |      | 1271650             | 1271695    | 1271696    | 1271697    | 1271698    | 1271699    | 1271700    | 1271700    | 1271701    | 1271701    |
| Benzene                           | µg/g | 0.21                | 0.02       | <0.02      | <0.02      | <0.02      | <0.02      | <0.02      | <0.02      | <0.02      | <0.02      |
| Toluene                           | µg/g | 2.3                 | 0.05       | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Ethylbenzene                      | µg/g | 2                   | 0.05       | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Xylenes (Total)                   | µg/g | 3.1                 | 0.05       | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| F1 (C6 to C10)                    | µg/g | 55                  | 5          | <5         | <5         | <5         | <5         | <5         | <5         | <5         | <5         |
| F1 (C6 to C10) minus BTEX         | µg/g | 55                  | 5          | <5         | <5         | <5         | <5         | <5         | <5         | <5         | <5         |
| F2 (C10 to C16)                   | µg/g | 98                  | 10         | <10        | <10        | <10        | <10        | <10        | <10        | <10        | <10        |
| F2 (C10 to C16) minus Naphthalene | µg/g |                     | 10         | <10        | <10        | <10        | <10        | <10        | <10        | <10        | <10        |
| F3 (C16 to C34)                   | µg/g | 300                 | 50         | <50        | <50        | 88         | <50        | <50        | <50        | <50        | <50        |
| F3 (C16 to C34) minus PAHs        | µg/g |                     | 50         | <50        | <50        | 88         | <50        | <50        | <50        | <50        | <50        |
| F4 (C34 to C50)                   | µg/g | 2800                | 50         | <50        | <50        | 64         | <50        | <50        | <50        | <50        | <50        |
| Gravimetric Heavy Hydrocarbons    | µg/g | 2800                | 50         | NA         | NA         | NA         | NA         | NA         | NA         | NA         | NA         |
| Moisture Content                  | %    |                     | 0.1        | 11.4       | 13.2       | 20.9       | 10.9       | 4.8        | 10.1       | 14.6       | 26.6       |
| Surrogate                         | Unit | Acceptable Limits   |            |            |            |            |            |            |            |            |            |
| Terphenyl                         | %    | 60-140              |            | 77         | 109        | 74         | 103        | 107        | 86         | 86         | 62         |

Certified By:



## Certificate of Analysis

AGAT WORK ORDER: 20Z624793

PROJECT: 19124906

5835 COOPERS AVENUE  
MISSISSAUGA, ONTARIO  
CANADA L4Z 1Y2  
TEL (905)712-5100  
FAX (905)712-5122  
<http://www.agatlabs.com>

CLIENT NAME: GOLDER ASSOCIATES LTD

ATTENTION TO: Keith Holmes

SAMPLING SITE:

SAMPLED BY:

### O. Reg. 153(511) - PHCs F1 - F4 (with PAHs) (Soil)

DATE RECEIVED: 2020-07-14

DATE REPORTED: 2020-07-23

| Parameter                         | Unit | SAMPLE DESCRIPTION: |            | TP4-11 SA1 | TP4-12 SA1 | TP4-13 SA1 | TP7-29 SA1 | TP7-30 SA1 | TP7-31 SA2 | TP7-32 SA1 | TP7-33 SA2 |
|-----------------------------------|------|---------------------|------------|------------|------------|------------|------------|------------|------------|------------|------------|
|                                   |      | G / S               | RDL        | Soil       | Soil       | Soil       | Soil       | Soil       | Soil       | Soil       | Soil       |
| DATE SAMPLED:                     |      | 2020-07-07          | 2020-07-07 | 2020-07-07 | 2020-07-08 | 2020-07-08 | 2020-07-08 | 2020-07-08 | 2020-07-08 | 2020-07-08 | 2020-07-08 |
|                                   |      | 12:00               | 12:00      | 12:00      | 12:00      | 12:00      | 12:00      | 12:00      | 12:00      | 12:00      | 12:00      |
|                                   |      | 1271702             | 1271703    | 1271704    | 1271705    | 1271738    | 1271739    | 1271740    | 1271741    |            |            |
| Benzene                           | µg/g | 0.21                | 0.02       | <0.02      | <0.02      | <0.02      | <0.02      | <0.02      | <0.02      | <0.02      | <0.02      |
| Toluene                           | µg/g | 2.3                 | 0.05       | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Ethylbenzene                      | µg/g | 2                   | 0.05       | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Xylenes (Total)                   | µg/g | 3.1                 | 0.05       | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| F1 (C6 to C10)                    | µg/g | 55                  | 5          | <5         | <5         | <5         | <5         | <5         | <5         | <5         | <5         |
| F1 (C6 to C10) minus BTEX         | µg/g | 55                  | 5          | <5         | <5         | <5         | <5         | <5         | <5         | <5         | <5         |
| F2 (C10 to C16)                   | µg/g | 98                  | 10         | <10        | <10        | <10        | <10        | <10        | <10        | <10        | <10        |
| F2 (C10 to C16) minus Naphthalene | µg/g |                     | 10         | <10        | <10        | <10        | <10        | <10        | <10        | <10        | <10        |
| F3 (C16 to C34)                   | µg/g | 300                 | 50         | <50        | <50        | <50        | <50        | <50        | <50        | <50        | <50        |
| F3 (C16 to C34) minus PAHs        | µg/g |                     | 50         | <50        | <50        | <50        | <50        | <50        | <50        | <50        | <50        |
| F4 (C34 to C50)                   | µg/g | 2800                | 50         | <50        | <50        | <50        | <50        | <50        | <50        | <50        | <50        |
| Gravimetric Heavy Hydrocarbons    | µg/g | 2800                | 50         | NA         | NA         | NA         | NA         | NA         | NA         | NA         | NA         |
| Moisture Content                  | %    |                     | 0.1        | 18.4       | 5.9        | 11.4       | 5.9        | 3.7        | 10.2       | 6.8        | 12.5       |
| Surrogate                         | Unit | Acceptable Limits   |            |            |            |            |            |            |            |            |            |
| Terphenyl                         | %    | 60-140              |            | 82         | 102        | 97         | 80         | 112        | 75         | 120        | 64         |

Certified By:



## Certificate of Analysis

AGAT WORK ORDER: 20Z624793

PROJECT: 19124906

5835 COOPERS AVENUE  
MISSISSAUGA, ONTARIO  
CANADA L4Z 1Y2  
TEL (905)712-5100  
FAX (905)712-5122  
<http://www.agatlabs.com>

CLIENT NAME: GOLDER ASSOCIATES LTD

ATTENTION TO: Keith Holmes

SAMPLING SITE:

SAMPLED BY:

### O. Reg. 153(511) - PHCs F1 - F4 (with PAHs) (Soil)

DATE RECEIVED: 2020-07-14

DATE REPORTED: 2020-07-23

| Parameter                         | Unit | SAMPLE DESCRIPTION: |            | TP7-34 SA2 | TP7-35 SA1 | TP7-36 SA1 | TP4-37A    | TP4-37B    | SPD-SA1    | SPD-SA2    | TP4-15 SA1 |
|-----------------------------------|------|---------------------|------------|------------|------------|------------|------------|------------|------------|------------|------------|
|                                   |      | G / S               | RDL        | Soil       | Soil       | Soil       | Soil       | Soil       | Soil       | Soil       | Soil       |
| DATE SAMPLED:                     |      | 2020-07-08          | 2020-07-08 | 2020-07-08 | 2020-07-08 | 2020-07-08 | 2020-07-08 | 2020-07-08 | 2020-07-08 | 2020-07-08 | 2020-07-08 |
|                                   |      | 12:00               | 12:00      | 12:00      | 12:00      | 12:00      | 12:00      | 12:00      | 12:00      | 12:00      | 12:00      |
|                                   |      | 1271742             | 1271743    | 1271744    | 1271745    | 1271746    | 1271747    | 1271748    | 1271749    | 1271749    | 1271749    |
| Benzene                           | µg/g | 0.21                | 0.02       | <0.02      | <0.02      | <0.02      | <0.02      | <0.02      | <0.02      | <0.02      | <0.02      |
| Toluene                           | µg/g | 2.3                 | 0.05       | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Ethylbenzene                      | µg/g | 2                   | 0.05       | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Xylenes (Total)                   | µg/g | 3.1                 | 0.05       | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| F1 (C6 to C10)                    | µg/g | 55                  | 5          | <5         | <5         | <5         | <5         | <5         | <5         | <5         | <5         |
| F1 (C6 to C10) minus BTEX         | µg/g | 55                  | 5          | <5         | <5         | <5         | <5         | <5         | <5         | <5         | <5         |
| F2 (C10 to C16)                   | µg/g | 98                  | 10         | <10        | <10        | <10        | <10        | <10        | <10        | <10        | <10        |
| F2 (C10 to C16) minus Naphthalene | µg/g |                     | 10         | <10        | <10        | <10        | <10        | <10        | <10        | <10        | <10        |
| F3 (C16 to C34)                   | µg/g | 300                 | 50         | <50        | <50        | <50        | <50        | <50        | <50        | <50        | <50        |
| F3 (C16 to C34) minus PAHs        | µg/g |                     | 50         | <50        | <50        | <50        | <50        | <50        | <50        | <50        | <50        |
| F4 (C34 to C50)                   | µg/g | 2800                | 50         | <50        | <50        | <50        | <50        | <50        | <50        | <50        | <50        |
| Gravimetric Heavy Hydrocarbons    | µg/g | 2800                | 50         | NA         | NA         | NA         | NA         | NA         | NA         | NA         | NA         |
| Moisture Content                  | %    |                     | 0.1        | 24.4       | 14.6       | 8.6        | 23.7       | 22.3       | 24.9       | 23.7       | 8.8        |
| Surrogate                         | Unit | Acceptable Limits   |            |            |            |            |            |            |            |            |            |
| Terphenyl                         | %    | 60-140              |            | 80         | 112        | 120        | 99         | 128        | 114        | 121        | 74         |

Certified By:



## Certificate of Analysis

AGAT WORK ORDER: 20Z624793

PROJECT: 19124906

5835 COOPERS AVENUE  
MISSISSAUGA, ONTARIO  
CANADA L4Z 1Y2  
TEL (905)712-5100  
FAX (905)712-5122  
<http://www.agatlabs.com>

CLIENT NAME: GOLDER ASSOCIATES LTD

ATTENTION TO: Keith Holmes

SAMPLING SITE:

SAMPLED BY:

### O. Reg. 153(511) - PHCs F1 - F4 (with PAHs) (Soil)

DATE RECEIVED: 2020-07-14

DATE REPORTED: 2020-07-23

| Parameter                         | Unit | SAMPLE DESCRIPTION: |            | TP4-16 SA1 | TP6A-17 SA1 | TP6A-20 SA1 | TP6B-21 SA2 | TP6B-22 SA1 | TP6B-24 SA1 | TP6B-25 SA1 | TP6B-26 SA1 |
|-----------------------------------|------|---------------------|------------|------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
|                                   |      | G / S               | RDL        | Soil       | Soil        | Soil        | Soil        | Soil        | Soil        | Soil        | Soil        |
| DATE SAMPLED:                     |      | 2020-07-08          | 2020-07-08 | 2020-07-08 | 2020-07-08  | 2020-07-08  | 2020-07-08  | 2020-07-08  | 2020-07-08  | 2020-07-08  | 2020-07-08  |
|                                   |      | 12:00               | 12:00      | 12:00      | 12:00       | 12:00       | 12:00       | 12:00       | 12:00       | 12:00       | 12:00       |
|                                   |      | 1271750             | 1271751    | 1271752    | 1271753     | 1271754     | 1271755     | 1271756     | 1271757     | 1271757     | 1271757     |
| Benzene                           | µg/g | 0.21                | 0.02       | <0.02      | <0.02       | <0.02       | <0.02       | <0.02       | <0.02       | <0.02       | <0.02       |
| Toluene                           | µg/g | 2.3                 | 0.05       | <0.05      | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       |
| Ethylbenzene                      | µg/g | 2                   | 0.05       | <0.05      | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       |
| Xylenes (Total)                   | µg/g | 3.1                 | 0.05       | <0.05      | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       | <0.05       |
| F1 (C6 to C10)                    | µg/g | 55                  | 5          | <5         | <5          | <5          | <5          | <5          | <5          | <5          | <5          |
| F1 (C6 to C10) minus BTEX         | µg/g | 55                  | 5          | <5         | <5          | <5          | <5          | <5          | <5          | <5          | <5          |
| F2 (C10 to C16)                   | µg/g | 98                  | 10         | <10        | <10         | <10         | <10         | <10         | <10         | <10         | <10         |
| F2 (C10 to C16) minus Naphthalene | µg/g |                     | 10         | <10        | <10         | <10         | <10         | <10         | <10         | <10         | <10         |
| F3 (C16 to C34)                   | µg/g | 300                 | 50         | <50        | <50         | <50         | <50         | <50         | <50         | <50         | <50         |
| F3 (C16 to C34) minus PAHs        | µg/g |                     | 50         | <50        | <50         | <50         | <50         | <50         | <50         | <50         | <50         |
| F4 (C34 to C50)                   | µg/g | 2800                | 50         | <50        | <50         | <50         | <50         | <50         | <50         | <50         | <50         |
| Gravimetric Heavy Hydrocarbons    | µg/g | 2800                | 50         | NA         | NA          | NA          | NA          | NA          | NA          | NA          | NA          |
| Moisture Content                  | %    |                     | 0.1        | 8.2        | 8.1         | 21.5        | 11.1        | 7.5         | 4.8         | 5.3         | 12.7        |
| Surrogate                         | Unit | Acceptable Limits   |            |            |             |             |             |             |             |             |             |
| Terphenyl                         | %    | 60-140              |            | 110        | 120         | 110         | 101         | 120         | 70          | 70          | 80          |

Certified By:



## Certificate of Analysis

AGAT WORK ORDER: 20Z624793

PROJECT: 19124906

5835 COOPERS AVENUE  
MISSISSAUGA, ONTARIO  
CANADA L4Z 1Y2  
TEL (905)712-5100  
FAX (905)712-5122  
<http://www.agatlabs.com>

CLIENT NAME: GOLDER ASSOCIATES LTD

ATTENTION TO: Keith Holmes

SAMPLING SITE:

SAMPLED BY:

### O. Reg. 153(511) - PHCs F1 - F4 (with PAHs) (Soil)

DATE RECEIVED: 2020-07-14

DATE REPORTED: 2020-07-23

| Parameter                         | Unit | SAMPLE DESCRIPTION: |            | TP7-27 SA1 | TP7-28 SA1 | SPD-SA3    | SPD-SA4    | SPD-SA5    | SPD-SA6    | SPD-SA7    | DUP2       |
|-----------------------------------|------|---------------------|------------|------------|------------|------------|------------|------------|------------|------------|------------|
|                                   |      | G / S               | RDL        | Soil       | Soil       | Soil       | Soil       | Soil       | Soil       | Soil       | Soil       |
| DATE SAMPLED:                     |      | 2020-07-08          | 2020-07-08 | 2020-07-09 | 2020-07-09 | 2020-07-09 | 2020-07-09 | 2020-07-09 | 2020-07-09 | 2020-07-09 | 2020-07-08 |
|                                   |      | 12:00               | 12:00      | 12:00      | 12:00      | 12:00      | 12:00      | 12:00      | 12:00      | 12:00      | 12:00      |
|                                   |      | 1271758             | 1271759    | 1271760    | 1271761    | 1271762    | 1271763    | 1271764    | 1271765    | 1271766    | 1271830    |
| Benzene                           | µg/g | 0.21                | 0.02       | <0.02      | <0.02      | <0.02      | <0.02      | <0.02      | <0.02      | <0.02      | <0.02      |
| Toluene                           | µg/g | 2.3                 | 0.05       | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Ethylbenzene                      | µg/g | 2                   | 0.05       | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Xylenes (Total)                   | µg/g | 3.1                 | 0.05       | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| F1 (C6 to C10)                    | µg/g | 55                  | 5          | <5         | <5         | <5         | <5         | <5         | <5         | <5         | <5         |
| F1 (C6 to C10) minus BTEX         | µg/g | 55                  | 5          | <5         | <5         | <5         | <5         | <5         | <5         | <5         | <5         |
| F2 (C10 to C16)                   | µg/g | 98                  | 10         | <10        | <10        | <10        | <10        | <10        | <10        | <10        | <10        |
| F2 (C10 to C16) minus Naphthalene | µg/g |                     | 10         | <10        | <10        | <10        | <10        | <10        | <10        | <10        | <10        |
| F3 (C16 to C34)                   | µg/g | 300                 | 50         | <50        | <50        | <50        | <50        | <50        | <50        | <50        | <50        |
| F3 (C16 to C34) minus PAHs        | µg/g |                     | 50         | <50        | <50        | <50        | <50        | <50        | <50        | <50        | <50        |
| F4 (C34 to C50)                   | µg/g | 2800                | 50         | <50        | <50        | <50        | <50        | <50        | <50        | <50        | <50        |
| Gravimetric Heavy Hydrocarbons    | µg/g | 2800                | 50         | NA         | NA         | NA         | NA         | NA         | NA         | NA         | NA         |
| Moisture Content                  | %    |                     | 0.1        | 27.7       | 7.2        | 26.2       | 23.8       | 25.9       | 26.5       | 23.8       | 8.0        |
| Surrogate                         | Unit | Acceptable Limits   |            |            |            |            |            |            |            |            |            |
| Terphenyl                         | %    | 60-140              |            | 74         | 75         | 72         | 70         | 70         | 75         | 80         | 72         |

Certified By:





## Certificate of Analysis

AGAT WORK ORDER: 20Z624793

PROJECT: 19124906

5835 COOPERS AVENUE  
MISSISSAUGA, ONTARIO  
CANADA L4Z 1Y2  
TEL (905)712-5100  
FAX (905)712-5122  
<http://www.agatlabs.com>

CLIENT NAME: GOLDER ASSOCIATES LTD

ATTENTION TO: Keith Holmes

SAMPLING SITE:

SAMPLED BY:

O. Reg. 153(511) - PHCs F1 - F4 (with PAHs) (Soil)

DATE RECEIVED: 2020-07-14

DATE REPORTED: 2020-07-23

Comments: RDL - Reported Detection Limit; G / S - Guideline / Standard: Refers to Table 3: Full Depth Generic Site Condition Standards in a Non-Potable Ground Water Condition - Soil - Residential/Parkland/Institutional Property Use - Coarse Textured Soils  
Guideline values are for general reference only. The guidelines provided may or may not be relevant for the intended use. Refer directly to the applicable standard for regulatory interpretation.

1271650-1271830 Results are based on sample dry weight.  
The C6-C10 fraction is calculated using toluene response factor.  
Xylenes total is a calculated parameter. The calculated value is the sum of m&p-Xylene and o-Xylene.  
C6-C10 (F1 minus BTEX) is a calculated parameter. The calculated value is F1 minus BTEX.  
The calculated parameters are non-accredited. The parameters that are components of the calculation are accredited.  
The C10 - C16, C16 - C34, and C34 - C50 fractions are calculated using the average response factor for n-C10, n-C16, and n-C34.  
Gravimetric Heavy Hydrocarbons are not included in the Total C16-C50 and are only determined if the chromatogram of the C34 - C50 hydrocarbons indicates that hydrocarbons >C50 are present.  
The chromatogram has returned to baseline by the retention time of nC50.  
Total C6 - C50 results are corrected for BTEX and PAH contributions.  
C>10 - C16 (F2- Naphthalene) is a calculated parameter. The calculated value is F2 - Naphthalene.  
C>16 - C34 (F3-PAH) is a calculated parameter. The calculated value is F3-PAH (PAH: sum of Phenanthrene, Benzo(a)anthracene, Benzo(b)fluoranthene, Benzo(k)fluoranthene, Benzo(a)pyrene, Fluoranthene, Dibenzo(a,h)anthracene, Indeno(1,2,3-c,d)pyrene and Pyrene).  
This method complies with the Reference Method for the CWS PHC and is validated for use in the laboratory.  
nC10, nC16 and nC34 response factors are within 10% of their average.  
C50 response factor is within 70% of nC10 + nC16 + nC34 average.  
Linearity is within 15%.  
Extraction and holding times were met for this sample.

Analysis performed at AGAT Toronto (unless marked by \*)

Certified By:



# Guideline Violation

AGAT WORK ORDER: 20Z624793

PROJECT: 19124906

5835 COOPERS AVENUE  
MISSISSAUGA, ONTARIO  
CANADA L4Z 1Y2  
TEL (905)712-5100  
FAX (905)712-5122  
<http://www.agatlabs.com>

CLIENT NAME: GOLDER ASSOCIATES LTD

ATTENTION TO: Keith Holmes

| SAMPLEID | SAMPLE TITLE | GUIDELINE      | ANALYSIS PACKAGE                              | PARAMETER | UNIT | GUIDEVALUE | RESULT |
|----------|--------------|----------------|---|-----------|------|------------|--------|
| 1271701  | TP4-10 SA1   | ON T3 S RPI CT | O. Reg. 153(511) - All Metals (Soil)          | Barium    | µg/g | 390        | 404    |
| 1271701  | TP4-10 SA1   | ON T3 S RPI CT | O. Reg. 153(511) - All Metals (Soil)          | Vanadium  | µg/g | 86         | 100    |
| 1271747  | SPD-SA1      | ON T3 S RPI CT | O. Reg. 153(511) - Metals & Inorganics (Soil) | Vanadium  | µg/g | 86         | 102    |
| 1271752  | TP6A-20 SA1  | ON T3 S RPI CT | O. Reg. 153(511) - All Metals (Soil)          | Vanadium  | µg/g | 86         | 101    |
| 1271760  | SPD-SA3      | ON T3 S RPI CT | O. Reg. 153(511) - Metals & Inorganics (Soil) | Vanadium  | µg/g | 86         | 100    |
| 1271761  | SPD-SA4      | ON T3 S RPI CT | O. Reg. 153(511) - Metals & Inorganics (Soil) | Barium    | µg/g | 390        | 416    |
| 1271761  | SPD-SA4      | ON T3 S RPI CT | O. Reg. 153(511) - Metals & Inorganics (Soil) | Cobalt    | µg/g | 22         | 26.7   |
| 1271761  | SPD-SA4      | ON T3 S RPI CT | O. Reg. 153(511) - Metals & Inorganics (Soil) | Vanadium  | µg/g | 86         | 119    |
| 1271762  | SPD-SA5      | ON T3 S RPI CT | O. Reg. 153(511) - Metals & Inorganics (Soil) | Vanadium  | µg/g | 86         | 90     |
| 1271763  | SPD-SA6      | ON T3 S RPI CT | O. Reg. 153(511) - Metals & Inorganics (Soil) | Cobalt    | µg/g | 22         | 25.6   |
| 1271763  | SPD-SA6      | ON T3 S RPI CT | O. Reg. 153(511) - Metals & Inorganics (Soil) | Vanadium  | µg/g | 86         | 113    |
| 1271764  | SPD-SA7      | ON T3 S RPI CT | O. Reg. 153(511) - Metals & Inorganics (Soil) | Vanadium  | µg/g | 86         | 94     |

## Quality Assurance

CLIENT NAME: GOLDR ASSOCIATES LTD  
 PROJECT: 19124906  
 SAMPLING SITE:

AGAT WORK ORDER: 20Z624793  
 ATTENTION TO: Keith Holmes  
 SAMPLED BY:

| Soil Analysis          |       |           |           |        |     |                |              |                    |       |          |                    |       |              |                   |       |
|------------------------|-------|-----------|-----------|--------|-----|----------------|--------------|--------------------|-------|----------|--------------------|-------|--------------|-------------------|-------|
| RPT Date: Jul 23, 2020 |       |           | DUPLICATE |        |     |                | Method Blank | REFERENCE MATERIAL |       |          | METHOD BLANK SPIKE |       | MATRIX SPIKE |                   |       |
| PARAMETER              | Batch | Sample Id | Dup #1    | Dup #2 | RPD | Measured Value |              | Acceptable Limits  |       | Recovery | Acceptable Limits  |       | Recovery     | Acceptable Limits |       |
|                        |       |           |           |        |     |                |              | Lower              | Upper |          | Lower              | Upper |              | Lower             | Upper |

**O. Reg. 153(511) - All Metals (Soil)**

|                               |         |         |      |      |       |        |      |     |      |      |     |      |      |     |      |
|-------------------------------|---------|---------|------|------|-------|--------|------|-----|------|------|-----|------|------|-----|------|
| Antimony                      | 1271650 | 1271650 | 1.1  | 1.0  | NA    | < 0.8  | 124% | 70% | 130% | 107% | 80% | 120% | 108% | 70% | 130% |
| Arsenic                       | 1271650 | 1271650 | 4    | 4    | NA    | < 1    | 110% | 70% | 130% | 101% | 80% | 120% | 100% | 70% | 130% |
| Barium                        | 1271650 | 1271650 | 164  | 162  | 1.2%  | < 2    | 108% | 70% | 130% | 108% | 80% | 120% | 107% | 70% | 130% |
| Beryllium                     | 1271650 | 1271650 | 0.5  | 0.5  | NA    | < 0.5  | 86%  | 70% | 130% | 103% | 80% | 120% | 88%  | 70% | 130% |
| Boron                         | 1271650 | 1271650 | 12   | 12   | NA    | < 5    | 89%  | 70% | 130% | 93%  | 80% | 120% | 81%  | 70% | 130% |
| Boron (Hot Water Extractable) | 1271650 | 1271650 | 0.17 | 0.18 | NA    | < 0.10 | 89%  | 60% | 140% | 95%  | 70% | 130% | 95%  | 60% | 140% |
| Cadmium                       | 1271650 | 1271650 | <0.5 | <0.5 | NA    | < 0.5  | 104% | 70% | 130% | 100% | 80% | 120% | 104% | 70% | 130% |
| Chromium                      | 1271650 | 1271650 | 23   | 24   | NA    | < 5    | 95%  | 70% | 130% | 101% | 80% | 120% | 106% | 70% | 130% |
| Cobalt                        | 1271650 | 1271650 | 6.8  | 7.2  | 5.7%  | < 0.5  | 90%  | 70% | 130% | 99%  | 80% | 120% | 94%  | 70% | 130% |
| Copper                        | 1271650 | 1271650 | 34   | 37   | 8.5%  | < 1    | 91%  | 70% | 130% | 100% | 80% | 120% | 96%  | 70% | 130% |
| Lead                          | 1271650 | 1271650 | 67   | 65   | 3.0%  | < 1    | 106% | 70% | 130% | 105% | 80% | 120% | 102% | 70% | 130% |
| Molybdenum                    | 1271650 | 1271650 | 1.3  | 1.4  | NA    | < 0.5  | 105% | 70% | 130% | 107% | 80% | 120% | 105% | 70% | 130% |
| Nickel                        | 1271650 | 1271650 | 17   | 19   | 11.1% | < 1    | 90%  | 70% | 130% | 96%  | 80% | 120% | 93%  | 70% | 130% |
| Selenium                      | 1271650 | 1271650 | 0.6  | 0.6  | NA    | < 0.4  | 131% | 70% | 130% | 98%  | 80% | 120% | 100% | 70% | 130% |
| Silver                        | 1271650 | 1271650 | 0.2  | 0.2  | NA    | < 0.2  | 100% | 70% | 130% | 98%  | 80% | 120% | 95%  | 70% | 130% |
| Thallium                      | 1271650 | 1271650 | <0.4 | <0.4 | NA    | < 0.4  | 110% | 70% | 130% | 100% | 80% | 120% | 99%  | 70% | 130% |
| Uranium                       | 1271650 | 1271650 | 0.8  | 0.7  | NA    | < 0.5  | 110% | 70% | 130% | 99%  | 80% | 120% | 102% | 70% | 130% |
| Vanadium                      | 1271650 | 1271650 | 27   | 29   | 7.1%  | < 1    | 101% | 70% | 130% | 96%  | 80% | 120% | 100% | 70% | 130% |
| Zinc                          | 1271650 | 1271650 | 154  | 164  | 6.3%  | < 5    | 96%  | 70% | 130% | 102% | 80% | 120% | 109% | 70% | 130% |
| Chromium, Hexavalent          | 1271741 | 1271741 | <0.2 | <0.2 | NA    | < 0.2  | 90%  | 70% | 130% | 85%  | 80% | 120% | 94%  | 70% | 130% |
| Mercury                       | 1271650 | 1271650 | 0.13 | 0.13 | NA    | < 0.10 | 107% | 70% | 130% | 100% | 80% | 120% | 104% | 70% | 130% |

Comments: QA Qualifier for metals - Selenium: For a multi-element scan for lab control standards and matrix spikes, up to 10% of analytes may exceed the quoted limits by up to 10% absolute and it is considered acceptable.

**O. Reg. 153(511) - Metals & Inorganics (Soil)**

|                               |         |         |      |      |      |        |      |     |      |      |     |      |      |     |      |
|-------------------------------|---------|---------|------|------|------|--------|------|-----|------|------|-----|------|------|-----|------|
| Antimony                      | 1271747 | 1271747 | <0.8 | <0.8 | NA   | < 0.8  | 135% | 70% | 130% | 104% | 80% | 120% | 108% | 70% | 130% |
| Arsenic                       | 1271747 | 1271747 | 2    | 2    | NA   | < 1    | 108% | 70% | 130% | 100% | 80% | 120% | 95%  | 70% | 130% |
| Barium                        | 1271747 | 1271747 | 374  | 378  | 1.1% | < 2    | 101% | 70% | 130% | 100% | 80% | 120% | 94%  | 70% | 130% |
| Beryllium                     | 1271747 | 1271747 | 1.0  | 0.8  | NA   | < 0.5  | 98%  | 70% | 130% | 101% | 80% | 120% | 110% | 70% | 130% |
| Boron                         | 1271747 | 1271747 | 5    | 5    | NA   | < 5    | 79%  | 70% | 130% | 101% | 80% | 120% | 97%  | 70% | 130% |
| Boron (Hot Water Extractable) | 1271747 | 1271747 | 0.28 | 0.18 | NA   | < 0.10 | 92%  | 60% | 140% | 103% | 70% | 130% | 93%  | 60% | 140% |
| Cadmium                       | 1271747 | 1271747 | <0.5 | <0.5 | NA   | < 0.5  | 106% | 70% | 130% | 101% | 80% | 120% | 100% | 70% | 130% |
| Chromium                      | 1271747 | 1271747 | 113  | 118  | 4.3% | < 5    | 92%  | 70% | 130% | 95%  | 80% | 120% | 103% | 70% | 130% |
| Cobalt                        | 1271747 | 1271747 | 21.8 | 22.7 | 4.0% | < 0.5  | 88%  | 70% | 130% | 95%  | 80% | 120% | 85%  | 70% | 130% |
| Copper                        | 1271747 | 1271747 | 57   | 55   | 3.6% | < 1    | 85%  | 70% | 130% | 99%  | 80% | 120% | 78%  | 70% | 130% |
| Lead                          | 1271747 | 1271747 | 9    | 9    | 0.0% | < 1    | 107% | 70% | 130% | 108% | 80% | 120% | 103% | 70% | 130% |
| Molybdenum                    | 1271747 | 1271747 | <0.5 | <0.5 | NA   | < 0.5  | 105% | 70% | 130% | 101% | 80% | 120% | 97%  | 70% | 130% |
| Nickel                        | 1271747 | 1271747 | 58   | 59   | 1.7% | < 1    | 87%  | 70% | 130% | 91%  | 80% | 120% | 95%  | 70% | 130% |
| Selenium                      | 1271747 | 1271747 | 0.7  | 0.6  | NA   | < 0.4  | 130% | 70% | 130% | 94%  | 80% | 120% | 90%  | 70% | 130% |

## Quality Assurance

CLIENT NAME: GOLDER ASSOCIATES LTD  
 PROJECT: 19124906  
 SAMPLING SITE:

AGAT WORK ORDER: 20Z624793  
 ATTENTION TO: Keith Holmes  
 SAMPLED BY:

### Soil Analysis (Continued)

| RPT Date: Jul 23, 2020               |         |           | DUPLICATE |        |      |                | Method Blank | REFERENCE MATERIAL |       |          | METHOD BLANK SPIKE |       |          | MATRIX SPIKE      |       |  |
|--------------------------------------|---------|-----------|-----------|--------|------|----------------|--------------|--------------------|-------|----------|--------------------|-------|----------|-------------------|-------|--|
| PARAMETER                            | Batch   | Sample Id | Dup #1    | Dup #2 | RPD  | Measured Value |              | Acceptable Limits  |       | Recovery | Acceptable Limits  |       | Recovery | Acceptable Limits |       |  |
|                                      |         |           |           |        |      |                |              | Lower              | Upper |          | Lower              | Upper |          | Lower             | Upper |  |
| Silver                               | 1271747 | 1271747   | <0.2      | <0.2   | NA   | < 0.2          | 98%          | 70%                | 130%  | 99%      | 80%                | 120%  | 92%      | 70%               | 130%  |  |
| Thallium                             | 1271747 | 1271747   | 0.5       | 0.5    | NA   | < 0.4          | 102%         | 70%                | 130%  | 100%     | 80%                | 120%  | 98%      | 70%               | 130%  |  |
| Uranium                              | 1271747 | 1271747   | 1.7       | 1.6    | NA   | < 0.5          | 106%         | 70%                | 130%  | 102%     | 80%                | 120%  | 100%     | 70%               | 130%  |  |
| Vanadium                             | 1271747 | 1271747   | 102       | 106    | 3.8% | < 1            | 97%          | 70%                | 130%  | 94%      | 80%                | 120%  | 84%      | 70%               | 130%  |  |
| Zinc                                 | 1271747 | 1271747   | 146       | 145    | 0.7% | < 5            | 97%          | 70%                | 130%  | 99%      | 80%                | 120%  | 115%     | 70%               | 130%  |  |
| Chromium, Hexavalent                 | 1271761 | 1271761   | <0.2      | <0.2   | NA   | < 0.2          | 90%          | 70%                | 130%  | 85%      | 80%                | 120%  | 94%      | 70%               | 130%  |  |
| Cyanide, Free                        | 1271760 | 1271760   | <0.040    | <0.040 | NA   | < 0.040        | 102%         | 70%                | 130%  | 99%      | 80%                | 120%  | 93%      | 70%               | 130%  |  |
| Mercury                              | 1271747 | 1271747   | <0.10     | <0.10  | NA   | < 0.10         | 103%         | 70%                | 130%  | 99%      | 80%                | 120%  | 105%     | 70%               | 130%  |  |
| Electrical Conductivity (2:1)        | 1271747 | 1271747   | 0.133     | 0.134  | 0.7% | < 0.005        | 101%         | 80%                | 120%  |          |                    |       |          |                   |       |  |
| Sodium Adsorption Ratio              | 1271747 | 1271747   | 0.208     | 0.208  | 0.0% | NA             |              |                    |       |          |                    |       |          |                   |       |  |
| pH, 2:1 CaCl <sub>2</sub> Extraction | 1271761 | 1271761   | 7.09      | 7.03   | 0.8% | NA             | 100%         | 80%                | 120%  |          |                    |       |          |                   |       |  |

Comments: NA signifies Not Applicable.

If RPD value is NA, the results of the duplicates are less than 5x the RDL and the RPD will not be calculated.

QA Qualifier for metals - Antimony: For a multi-element scan for lab control standards and matrix spikes, up to 10% of analytes may exceed the quoted limits by up to 10% absolute and it is considered acceptable.

Certified By: \_\_\_\_\_



## Quality Assurance

CLIENT NAME: GOLDER ASSOCIATES LTD

AGAT WORK ORDER: 20Z624793

PROJECT: 19124906

ATTENTION TO: Keith Holmes

SAMPLING SITE:

SAMPLED BY:

| Trace Organics Analysis |       |           |           |        |     |                |              |                    |       |          |                    |       |          |                   |       |
|-------------------------|-------|-----------|-----------|--------|-----|----------------|--------------|--------------------|-------|----------|--------------------|-------|----------|-------------------|-------|
| RPT Date: Jul 23, 2020  |       |           | DUPLICATE |        |     |                | Method Blank | REFERENCE MATERIAL |       |          | METHOD BLANK SPIKE |       |          | MATRIX SPIKE      |       |
| PARAMETER               | Batch | Sample Id | Dup #1    | Dup #2 | RPD | Measured Value |              | Acceptable Limits  |       | Recovery | Acceptable Limits  |       | Recovery | Acceptable Limits |       |
|                         |       |           |           |        |     |                |              | Lower              | Upper |          | Lower              | Upper |          | Lower             | Upper |

|  |         |         |        |        |    |        |      |     |      |      |     |      |      |     |      |
|--|---------|---------|--------|--------|----|--------|------|-----|------|------|-----|------|------|-----|------|
| O. Reg. 153(511) - PHCs F1 - F4 (with PAHs) (Soil) |         |         |        |        |    |        |      |     |      |      |     |      |      |     |      |
| Benzene  | 1271745 | 1271745 | < 0.02 | < 0.02 | NA | < 0.02 | 82%  | 50% | 140% | 85%  | 60% | 130% | 83%  | 50% | 140% |
| Toluene  | 1271745 | 1271745 | < 0.05 | < 0.05 | NA | < 0.05 | 99%  | 50% | 140% | 112% | 60% | 130% | 96%  | 50% | 140% |
| Ethylbenzene                                       | 1271745 | 1271745 | < 0.05 | < 0.05 | NA | < 0.05 | 85%  | 50% | 140% | 90%  | 60% | 130% | 90%  | 50% | 140% |
| Xylenes (Total)                                    | 1271745 | 1271745 | < 0.05 | < 0.05 | NA | < 0.05 | 92%  | 50% | 140% | 88%  | 60% | 130% | 94%  | 50% | 140% |
| F1 (C6 to C10)                                     | 1271745 | 1271745 | < 5    | < 5    | NA | < 5    | 108% | 60% | 140% | 99%  | 60% | 140% | 91%  | 60% | 140% |
| F2 (C10 to C16)                                    | 1271745 | 1271745 | < 10   | < 10   | NA | < 10   | 118% | 60% | 140% | 104% | 60% | 140% | 72%  | 60% | 140% |
| F3 (C16 to C34)                                    | 1271745 | 1271745 | < 50   | < 50   | NA | < 50   | 97%  | 60% | 140% | 117% | 60% | 140% | 89%  | 60% | 140% |
| F4 (C34 to C50)                                    | 1271745 | 1271745 | < 50   | < 50   | NA | < 50   | 90%  | 60% | 140% | 117% | 60% | 140% | 98%  | 60% | 140% |
| O. Reg. 153(511) - PAHs (Soil)                     |         |         |        |        |    |        |      |     |      |      |     |      |      |     |      |
| Naphthalene  | 1271830 | 1271830 | < 0.05 | < 0.05 | NA | < 0.05 | 107% | 50% | 140% | 97%  | 50% | 140% | 70%  | 50% | 140% |
| Acenaphthylene                                     | 1271830 | 1271830 | < 0.05 | < 0.05 | NA | < 0.05 | 103% | 50% | 140% | 109% | 50% | 140% | 79%  | 50% | 140% |
| Acenaphthene                                       | 1271830 | 1271830 | < 0.05 | < 0.05 | NA | < 0.05 | 96%  | 50% | 140% | 108% | 50% | 140% | 79%  | 50% | 140% |
| Fluorene   | 1271830 | 1271830 | < 0.05 | < 0.05 | NA | < 0.05 | 106% | 50% | 140% | 111% | 50% | 140% | 81%  | 50% | 140% |
| Phenanthrene                                       | 1271830 | 1271830 | < 0.05 | < 0.05 | NA | < 0.05 | 111% | 50% | 140% | 108% | 50% | 140% | 85%  | 50% | 140% |
| Anthracene   | 1271830 | 1271830 | < 0.05 | < 0.05 | NA | < 0.05 | 103% | 50% | 140% | 113% | 50% | 140% | 89%  | 50% | 140% |
| Fluoranthene                                       | 1271830 | 1271830 | < 0.05 | < 0.05 | NA | < 0.05 | 112% | 50% | 140% | 105% | 50% | 140% | 97%  | 50% | 140% |
| Pyrene   | 1271830 | 1271830 | < 0.05 | < 0.05 | NA | < 0.05 | 107% | 50% | 140% | 105% | 50% | 140% | 95%  | 50% | 140% |
| Benz(a)anthracene                                  | 1271830 | 1271830 | < 0.05 | < 0.05 | NA | < 0.05 | 98%  | 50% | 140% | 93%  | 50% | 140% | 80%  | 50% | 140% |
| Chrysene   | 1271830 | 1271830 | < 0.05 | < 0.05 | NA | < 0.05 | 100% | 50% | 140% | 108% | 50% | 140% | 95%  | 50% | 140% |
| Benzo(b)fluoranthene                               | 1271830 | 1271830 | < 0.05 | < 0.05 | NA | < 0.05 | 100% | 50% | 140% | 99%  | 50% | 140% | 97%  | 50% | 140% |
| Benzo(k)fluoranthene                               | 1271830 | 1271830 | < 0.05 | < 0.05 | NA | < 0.05 | 92%  | 50% | 140% | 90%  | 50% | 140% | 94%  | 50% | 140% |
| Benzo(a)pyrene                                     | 1271830 | 1271830 | < 0.05 | < 0.05 | NA | < 0.05 | 108% | 50% | 140% | 97%  | 50% | 140% | 102% | 50% | 140% |
| Indeno(1,2,3-cd)pyrene                             | 1271830 | 1271830 | < 0.05 | < 0.05 | NA | < 0.05 | 84%  | 50% | 140% | 79%  | 50% | 140% | 76%  | 50% | 140% |
| Dibenz(a,h)anthracene                              | 1271830 | 1271830 | < 0.05 | < 0.05 | NA | < 0.05 | 85%  | 50% | 140% | 78%  | 50% | 140% | 86%  | 50% | 140% |
| Benzo(g,h,i)perylene                               | 1271830 | 1271830 | < 0.05 | < 0.05 | NA | < 0.05 | 83%  | 50% | 140% | 81%  | 50% | 140% | 82%  | 50% | 140% |
| O. Reg. 153(511) - PHCs F1 - F4 (with PAHs) (Soil) |         |         |        |        |    |        |      |     |      |      |     |      |      |     |      |
| F2 (C10 to C16)                                    | 1271830 | 1271830 | < 10   | < 10   | NA | < 10   | 100% | 60% | 140% | 114% | 60% | 140% | 99%  | 60% | 140% |
| F3 (C16 to C34)                                    | 1271830 | 1271830 | < 50   | < 50   | NA | < 50   | 101% | 60% | 140% | 119% | 60% | 140% | 90%  | 60% | 140% |
| F4 (C34 to C50)                                    | 1271830 | 1271830 | < 50   | < 50   | NA | < 50   | 95%  | 60% | 140% | 91%  | 60% | 140% | 85%  | 60% | 140% |
| O. Reg. 153(511) - PHCs F1 - F4 (with PAHs) (Soil) |         |         |        |        |    |        |      |     |      |      |     |      |      |     |      |
| Benzene  | 1271830 | 1271830 | < 0.02 | < 0.02 | NA | < 0.02 | 86%  | 50% | 140% | 89%  | 60% | 130% | 92%  | 50% | 140% |
| Toluene  | 1271830 | 1271830 | < 0.05 | < 0.05 | NA | < 0.05 | 89%  | 50% | 140% | 92%  | 60% | 130% | 108% | 50% | 140% |
| Ethylbenzene                                       | 1271830 | 1271830 | < 0.05 | < 0.05 | NA | < 0.05 | 91%  | 50% | 140% | 100% | 60% | 130% | 89%  | 50% | 140% |
| Xylenes (Total)                                    | 1271830 | 1271830 | < 0.05 | < 0.05 | NA | < 0.05 | 88%  | 50% | 140% | 100% | 60% | 130% | 90%  | 50% | 140% |
| F1 (C6 to C10)                                     | 1271830 | 1271830 | < 5    | < 5    | NA | < 5    | 94%  | 60% | 140% | 109% | 60% | 140% | 100% | 60% | 140% |

Comments: When the average of the sample and duplicate results is less than 5x the RDL, the Relative Percent Difference (RPD) will be indicated as Not Applicable (NA).



## Quality Assurance

CLIENT NAME: GOLDER ASSOCIATES LTD  
 PROJECT: 19124906  
 SAMPLING SITE:

AGAT WORK ORDER: 20Z624793  
 ATTENTION TO: Keith Holmes  
 SAMPLED BY:

### Trace Organics Analysis (Continued)

| RPT Date: Jul 23, 2020 |       |           | DUPLICATE |        |     | Method Blank | REFERENCE MATERIAL |                   | METHOD BLANK SPIKE |          | MATRIX SPIKE      |       |          |                   |       |
|------------------------|-------|-----------|-----------|--------|-----|--------------|--------------------|-------------------|--------------------|----------|-------------------|-------|----------|-------------------|-------|
| PARAMETER              | Batch | Sample Id | Dup #1    | Dup #2 | RPD |              | Measured Value     | Acceptable Limits |                    | Recovery | Acceptable Limits |       | Recovery | Acceptable Limits |       |
|                        |       |           |           |        |     |              |                    | Lower             | Upper              |          | Lower             | Upper |          | Lower             | Upper |
|                        |       |           |           |        |     |              |                    |                   |                    |          |                   |       |          |                   |       |

Certified By: \_\_\_\_\_

## QA Violation

 CLIENT NAME: GOLDER ASSOCIATES LTD  
 PROJECT: 19124906

 AGAT WORK ORDER: 20Z624793  
 ATTENTION TO: Keith Holmes

| RPT Date: Jul 23, 2020 |           |                    | REFERENCE MATERIAL |                   |       | METHOD BLANK SPIKE |                   |       | MATRIX SPIKE |                   |       |
|------------------------|-----------|--------------------|--------------------|-------------------|-------|--------------------|-------------------|-------|--------------|-------------------|-------|
| PARAMETER              | Sample Id | Sample Description | Measured Value     | Acceptable Limits |       | Recovery           | Acceptable Limits |       | Recovery     | Acceptable Limits |       |
|                        |           |                    |                    | Lower             | Upper |                    | Lower             | Upper |              | Lower             | Upper |

|                                      |         |            |      |     |      |     |     |      |      |     |      |
|--------------------------------------|---------|------------|------|-----|------|-----|-----|------|------|-----|------|
| O. Reg. 153(511) - All Metals (Soil) |         |            |      |     |      |     |     |      |      |     |      |
| Selenium                             | 1271650 | TP4-01 SA1 | 131% | 70% | 130% | 98% | 80% | 120% | 100% | 70% | 130% |

Comments: QA Qualifier for metals - Selenium: For a multi-element scan for lab control standards and matrix spikes, up to 10% of analytes may exceed the quoted limits by up to 10% absolute and it is considered acceptable.

|   |         |         |      |     |      |      |     |      |      |     |      |
|---|---------|---------|------|-----|------|------|-----|------|------|-----|------|
| O. Reg. 153(511) - Metals & Inorganics (Soil) |         |         |      |     |      |      |     |      |      |     |      |
| Antimony                                      | 1271747 | SPD-SA1 | 135% | 70% | 130% | 104% | 80% | 120% | 108% | 70% | 130% |

Comments: NA signifies Not Applicable.  
 If RPD value is NA, the results of the duplicates are less than 5x the RDL and the RPD will not be calculated.  
 QA Qualifier for metals - Antimony: For a multi-element scan for lab control standards and matrix spikes, up to 10% of analytes may exceed the quoted limits by up to 10% absolute and it is considered acceptable.



## Method Summary

CLIENT NAME: GOLDER ASSOCIATES LTD  
 PROJECT: 19124906  
 SAMPLING SITE:

AGAT WORK ORDER: 20Z624793  
 ATTENTION TO: Keith Holmes  
 SAMPLED BY:

| PARAMETER                            | AGAT S.O.P   | LITERATURE REFERENCE                               | ANALYTICAL TECHNIQUE    |
|--------------------------------------|--------------|--|-------------------------|
| Soil Analysis                        |              |  |                         |
| Antimony                             | MET-93-6103  | modified from EPA 3050B and EPA 6020B and ON MOECC | ICP-MS                  |
| Arsenic                              | MET-93-6103  | modified from EPA 3050B and EPA 6020B and ON MOECC | ICP-MS                  |
| Barium                               | MET-93-6103  | modified from EPA 3050B and EPA 6020B and ON MOECC | ICP-MS                  |
| Beryllium                            | MET-93-6103  | modified from EPA 3050B and EPA 6020B and ON MOECC | ICP-MS                  |
| Boron                                | MET-93-6103  | modified from EPA 3050B and EPA 6020B and ON MOECC | ICP-MS                  |
| Boron (Hot Water Extractable)        | MET-93-6104  | modified from EPA 6010D and MSA PART 3, CH 21      | ICP/OES                 |
| Cadmium                              | MET-93-6103  | modified from EPA 3050B and EPA 6020B and ON MOECC | ICP-MS                  |
| Chromium                             | MET-93-6103  | modified from EPA 3050B and EPA 6020B and ON MOECC | ICP-MS                  |
| Cobalt                               | MET-93-6103  | modified from EPA 3050B and EPA 6020B and ON MOECC | ICP-MS                  |
| Copper                               | MET-93-6103  | modified from EPA 3050B and EPA 6020B and ON MOECC | ICP-MS                  |
| Lead                                 | MET-93-6103  | modified from EPA 3050B and EPA 6020B and ON MOECC | ICP-MS                  |
| Molybdenum                           | MET-93-6103  | modified from EPA 3050B and EPA 6020B and ON MOECC | ICP-MS                  |
| Nickel                               | MET-93-6103  | modified from EPA 3050B and EPA 6020B and ON MOECC | ICP-MS                  |
| Selenium                             | MET-93-6103  | modified from EPA 3050B and EPA 6020B and ON MOECC | ICP-MS                  |
| Silver                               | MET-93-6103  | modified from EPA 3050B and EPA 6020B and ON MOECC | ICP-MS                  |
| Thallium                             | MET-93-6103  | modified from EPA 3050B and EPA 6020B and ON MOECC | ICP-MS                  |
| Uranium                              | MET-93-6103  | modified from EPA 3050B and EPA 6020B and ON MOECC | ICP-MS                  |
| Vanadium                             | MET-93-6103  | modified from EPA 3050B and EPA 6020B and ON MOECC | ICP-MS                  |
| Zinc                                 | MET-93-6103  | modified from EPA 3050B and EPA 6020B and ON MOECC | ICP-MS                  |
| Chromium, Hexavalent                 | INOR-93-6068 | modified from EPA 3060 and EPA 7196                | SPECTROPHOTOMETER       |
| Mercury                              | MET-93-6103  | modified from EPA 3050B and EPA 6020B and ON MOECC | ICP-MS                  |
| Cyanide, Free                        | INOR-93-6052 | modified from ON MOECC E3015 and SM 4500-CN- I     | TECHNICON AUTO ANALYZER |
| Electrical Conductivity (2:1)        | INOR-93-6036 | modified from MSA PART 3, CH 14 and SM 2510 B      | EC METER                |
| Sodium Adsorption Ratio              | INOR-93-6007 | McKeague 4.12 & 3.26 & EPA SW-846 6010C            | ICP/OES                 |
| pH, 2:1 CaCl <sub>2</sub> Extraction | INOR-93-6031 | modified from EPA 9045D and MCKEAGUE 3.11          | PH METER                |



## Method Summary

CLIENT NAME: GOLDER ASSOCIATES LTD

AGAT WORK ORDER: 20Z624793

PROJECT: 19124906

ATTENTION TO: Keith Holmes

SAMPLING SITE:

SAMPLED BY:

| PARAMETER                         | AGAT S.O.P  | LITERATURE REFERENCE                   | ANALYTICAL TECHNIQUE |
|-----------------------------------|-------------|--|----------------------|
| Trace Organics Analysis           |             |  |                      |
| Naphthalene                       | ORG-91-5106 | modified from EPA 3570 and EPA 8270E   | GC/MS                |
| Acenaphthylene                    | ORG-91-5106 | modified from EPA 3570 and EPA 8270E   | GC/MS                |
| Acenaphthene                      | ORG-91-5106 | modified from EPA 3570 and EPA 8270E   | GC/MS                |
| Fluorene                          | ORG-91-5106 | modified from EPA 3570 and EPA 8270E   | GC/MS                |
| Phenanthrene                      | ORG-91-5106 | modified from EPA 3570 and EPA 8270E   | GC/MS                |
| Anthracene                        | ORG-91-5106 | modified from EPA 3570 and EPA 8270E   | GC/MS                |
| Fluoranthene                      | ORG-91-5106 | modified from EPA 3570 and EPA 8270E   | GC/MS                |
| Pyrene                            | ORG-91-5106 | modified from EPA 3570 and EPA 8270E   | GC/MS                |
| Benz(a)anthracene                 | ORG-91-5106 | modified from EPA 3570 and EPA 8270E   | GC/MS                |
| Chrysene                          | ORG-91-5106 | modified from EPA 3570 and EPA 8270E   | GC/MS                |
| Benzo(b)fluoranthene              | ORG-91-5106 | modified from EPA 3570 and EPA 8270E   | GC/MS                |
| Benzo(k)fluoranthene              | ORG-91-5106 | modified from EPA 3570 and EPA 8270E   | GC/MS                |
| Benzo(a)pyrene                    | ORG-91-5106 | modified from EPA 3570 and EPA 8270E   | GC/MS                |
| Indeno(1,2,3-cd)pyrene            | ORG-91-5106 | modified from EPA 3570 and EPA 8270E   | GC/MS                |
| Dibenz(a,h)anthracene             | ORG-91-5106 | modified from EPA 3570 and EPA 8270E   | GC/MS                |
| Benzo(g,h,i)perylene              | ORG-91-5106 | modified from EPA 3570 and EPA 8270E   | GC/MS                |
| 1 and 2 Methylnaphthalene         | ORG-91-5106 | modified from EPA 3570 and EPA 8270E   | GC/MS                |
| Moisture Content                  | ORG-91-5106 | Tier 1 Method                          | BALANCE              |
| Naphthalene-d8                    | ORG-91-5106 | modified from EPA 3570 and EPA 8270E   | GC/MS                |
| Acenaphthene-d10                  | ORG-91-5106 | modified from EPA 3570 and EPA 8270E   | GC/MS                |
| Chrysene-d12                      | ORG-91-5106 | modified from EPA 3570 and EPA 8270E   | GC/MS                |
| Benzene                           | VOL-91-5009 | modified from EPA 5035C and EPA 8260D  | (P&T)GC/MS           |
| Toluene                           | VOL-91-5009 | modified from EPA SW-846 5035C & 8260D | P&T GC/MS            |
| Ethylbenzene                      | VOL-91-5009 | modified from EPA SW-846 5035C & 8260D | P&T GC/MS            |
| Xylenes (Total)                   | VOL-91-5009 | modified from EPA SW-846 5035C & 8260D | P&T GC/MS            |
| F1 (C6 to C10)                    | VOL-91-5009 | modified from CCME Tier 1 Method       | P&T GC/FID           |
| F1 (C6 to C10) minus BTEX         | VOL-91-5009 | modified from CCME Tier 1 Method       | P&T GC/FID           |
| F2 (C10 to C16)                   | VOL-91-5009 | modified from CCME Tier 1 Method       | GC/FID               |
| F2 (C10 to C16) minus Naphthalene | VOL-91-5009 | modified from CCME Tier 1 Method       | GC/FID               |
| F3 (C16 to C34)                   | VOL-91-5009 | modified from CCME Tier 1 Method       | GC/FID               |



## Method Summary

CLIENT NAME: GOLDER ASSOCIATES LTD

AGAT WORK ORDER: 20Z624793

PROJECT: 19124906

ATTENTION TO: Keith Holmes

SAMPLING SITE:

SAMPLED BY:

| PARAMETER                      | AGAT S.O.P  | LITERATURE REFERENCE             | ANALYTICAL TECHNIQUE |
|--------------------------------|-------------|----------------------------------|----------------------|
| F3 (C16 to C34) minus PAHs     | VOL-91-5009 | modified from CCME Tier 1 Method | GC/FID               |
| F4 (C34 to C50)                | VOL-91-5009 | modified from CCME Tier 1 Method | GC/FID               |
| Gravimetric Heavy Hydrocarbons | VOL-91-5009 | modified from CCME Tier 1 Method | BALANCE              |
| Moisture Content               | VOL-91-5009 | modified from CCME Tier 1 Method | BALANCE              |
| Terphenyl                      | VOL-91-5009 | modified from CCME Tier 1 Method | GC/FID               |



## Chain of Custody Record

If this is a Drinking Water sample, please use Drinking Water Chain of Custody Form (potable water consumed by humans)

### Report Information:

Company: Golden  
Contact: Keith Holmes  
Address: \_\_\_\_\_  
Phone: \_\_\_\_\_ Fax: \_\_\_\_\_  
Reports to be sent to: \_\_\_\_\_  
1. Email: kholmes@golden.com  
2. Email: \_\_\_\_\_

### Project Information:

Project: 19124906  
Site Location: \_\_\_\_\_  
Sampled By: \_\_\_\_\_  
AGAT Quote #: 337349 PO: \_\_\_\_\_  
Please note: If quotation number is not provided, client will be billed full price for analysis.

### Invoice Information:

Bill To Same: Yes  No   
Company: \_\_\_\_\_  
Contact: \_\_\_\_\_  
Address: \_\_\_\_\_  
Email: \_\_\_\_\_

### Regulatory Requirements:

(Please check all applicable boxes)

Regulation 153/04  Excess Soils R406  Regulation 558

Table 3 Indicate One  Sewer Use  Sanitary  Storm

Ind/Com  Region \_\_\_\_\_

Homes/Park  CCME

Agriculture  Sample from APEC?  Prov. Water Quality Objectives (PWQO)  Other

Soil Texture (Check One)  Yes  No  Stockpile  In-situ

Coarse  Fine Indicate One

### Is this submission for a Record of Site Condition?

Yes  No

### Report Guideline on Certificate of Analysis

Yes  No

### Sample Matrix Legend

**B** Biota  
**GW** Ground Water  
**O** Oil  
**P** Paint  
**S** Soil  
**SD** Sediment  
**SW** Surface Water

### Laboratory Use Only

Work Order #: 202624793  
Cooler Quantity: two - onice (melted)  
Arrival Temperatures: See attached  
Custody Seal Intact:  Yes  No  N/A  
Notes: \_\_\_\_\_

### Turnaround Time (TAT) Required:

**Regular TAT**  5 to 7 Business Days  
**Rush TAT (Rush Surcharges Apply)**  
 3 Business Days  2 Business Days  Next Business Day  
**OR Date Required (Rush Surcharges May Apply):** \_\_\_\_\_

Please provide prior notification for rush TAT  
\*TAT is exclusive of weekends and statutory holidays

For 'Same Day' analysis, please contact your AGAT CPM

| Sample Identification | Date Sampled | Time Sampled | # of Containers | Sample Matrix | Comments/<br>Special Instructions | Y / N | Metals <del>ICPMS, CVI, ICPMS</del> | Metals - ICPMS, CVI, ICPMS | BTEX, F1-F4 PHCs | Analyze F4G if required | PAHs | PCBs | VOC | Landfill Disposal Characterization TCLP: | TCLP: M&I, VOCs, ABNS, B(a)P, PCBs | Excess Soils SPLP Rainwater Leach | SPLP: Metals, VOCs, SVOCs | Excess Soils Characterization Package | pH, ICPMS Metals, BTEX, F1-F4 | Salt - EC/SAR | Potentially Hazardous or High Concentration (Y/N) |  |
|-----------------------|--------------|--------------|-----------------|---------------|-----------------------------------|-------|-------------------------------------|----------------------------|------------------|-------------------------|------|------|-----|--|------------------------------------|-----------------------------------|---------------------------|---------------------------------------|-------------------------------|---------------|---|--|
| TP4-01 SAI            | 7/7/20       | 12:00 AM     | 3               | S             | No Droughted<br>Just meths        |       | X                                   | X                          | X                | X                       |      |      |     |  |                                    |                                   |                           |                                       |                               |               |   |  |
| TP4-02 SAI            |              |              |                 |               |                                   |       |                                     |                            |                  |                         |      |      |     |  |                                    |                                   |                           |                                       |                               |               |   |  |
| TP4-03 SAI            |              |              |                 |               |                                   |       |                                     |                            |                  |                         |      |      |     |  |                                    |                                   |                           |                                       |                               |               |   |  |
| TP4-04 SAI            |              |              |                 |               |                                   |       |                                     |                            |                  |                         |      |      |     |  |                                    |                                   |                           |                                       |                               |               |   |  |
| TP4-05 SAI            |              |              |                 |               |                                   |       |                                     |                            |                  |                         |      |      |     |  |                                    |                                   |                           |                                       |                               |               |   |  |
| TP4-07 SAI            |              |              |                 |               |                                   |       |                                     |                            |                  |                         |      |      |     |  |                                    |                                   |                           |                                       |                               |               |   |  |
| TP4-09 SAI            |              |              |                 |               |                                   |       |                                     |                            |                  |                         |      |      |     |  |                                    |                                   |                           |                                       |                               |               |   |  |
| TP4-10 SAI            |              |              |                 |               |                                   |       |                                     |                            |                  |                         |      |      |     |  |                                    |                                   |                           |                                       |                               |               |   |  |
| TP4-11 SAI            |              |              |                 |               |                                   |       |                                     |                            |                  |                         |      |      |     |  |                                    |                                   |                           |                                       |                               |               |   |  |
| TP4-12 SAI            |              |              |                 |               |                                   |       |                                     |                            |                  |                         |      |      |     |  |                                    |                                   |                           |                                       |                               |               |   |  |
| TP4-13 SAI            |              |              |                 |               |                                   |       |                                     |                            |                  |                         |      |      |     |  |                                    |                                   |                           |                                       |                               |               |   |  |

|  |                       |                    |  |                         |                       |
|--|-----------------------|--------------------|--|-------------------------|-----------------------|
| Samples Relinquished By (Print Name and Sign): <u>Keith Holmes</u> | Date: <u>13/07/20</u> | Time: <u>5:30</u>  | Samples Received By (Print Name and Sign): <u>Gertmeijer</u> | Date: <u>20200714</u>   | Time: <u>11h06</u>    |
| Samples Relinquished By (Print Name and Sign): <u>Wendy Fedix</u>  | Date: <u>20200714</u> | Time: <u>16h00</u> | Samples Received By (Print Name and Sign): <u>SMK AN</u>     | Date: <u>July 19/20</u> | Time: <u>10:20 am</u> |
| Samples Relinquished By (Print Name and Sign): _____               | Date: _____           | Time: _____        | Samples Received By (Print Name and Sign): _____             | Date: _____             | Time: _____           |

No: **T 106448**



### Laboratory Use Only

Arrival Temperature: 20  
AGAT WO #: 202624793  
Lab Temperature: \_\_\_\_\_  
Notes: \_\_\_\_\_

## Chain of Custody Record

P: 905.712.5100 · F: 905.712.5122

### Client Information

Company: \_\_\_\_\_  
Contact: \_\_\_\_\_  
Address: \_\_\_\_\_  
Phone: \_\_\_\_\_ Fax: \_\_\_\_\_  
Project: \_\_\_\_\_ PO: \_\_\_\_\_  
AGAT Quotation #: \_\_\_\_\_  
**Please note, if quotation number is not provided, client will be billed full price for analysis.**

### Regulatory Requirements

Regulation 153/04 (reg. 511 Amend.)  
Table 3 Indicate one  
 Ind/Com  
 Res/Park  
 Agriculture  
**Soil Texture (check one)**  
 Coarse  Fine

Sewer Use  
Region \_\_\_\_\_ Indicate one  
 Sanitary  
 Storm

Regulation 558  
 CCME  
 Other (specify) \_\_\_\_\_  
 Prov. Water Quality Objectives (PWQO)  
 None

### Turnaround Time Required (TAT) Required\*

**Regular TAT**  
 5 to 7 Working Days  
**Rush TAT (please provide prior notification)**  
**Rush Surcharges Apply**  
 3 Working Days  
 2 Working Days  
 1 Working Day

**OR**  
Date Required (Rush surcharges may apply): \_\_\_\_\_  
*\*TAT is exclusive of weekends and statutory holidays*

### Invoice To

Company: \_\_\_\_\_ Same: Yes  No   
Contact: \_\_\_\_\_  
Address: \_\_\_\_\_

**Is this a drinking water sample?** (potable water intended for human consumption)  
 Yes  No  
If "Yes", please use the **Drinking Water Chain of Custody Form**

**Is this submission for a Record of Site Condition?**  
 Yes  No

### Legend Matrix

**GW** Ground Water **O** Oil  
**SW** Surface Water **P** Paint  
**SD** Sediment **S** Soil

### Report Information - reports to be sent to:

1. Name: \_\_\_\_\_ Email: \_\_\_\_\_  
2. Name: \_\_\_\_\_ Email: \_\_\_\_\_

| Sample Identification | Date Sampled | Time Sampled | Sample Matrix | # of Containers | Comments Site/Sample Information |
|-----------------------|--------------|--------------|---------------|-----------------|----------------------------------|
| TPZ-29 SA1            | 07/08/20     | 17:00        | S             | 3               |                                  |
| TPZ-30 SA1            |              |              |               |                 |                                  |
| TPZ-31 SA2            |              |              |               |                 |                                  |
| TPZ-32 SA1            |              |              |               |                 |                                  |
| TPZ-33 SA2            |              |              |               |                 |                                  |
| TPZ-34 SA2            |              |              |               |                 |                                  |
| TPZ-35 SA1            |              |              |               |                 |                                  |
| TPZ-36 SA1            |              |              |               |                 |                                  |
| TP4-37 A              |              |              |               |                 |                                  |
| TP4-37 B              |              |              |               |                 |                                  |
| SPD-SA1               |              |              |               |                 |                                  |
| SPD-SA2               |              |              |               |                 |                                  |

| Metals and Inorganics | Metal Scan | Hydride Forming Metals | Client Custom Metals | ORFs: <input type="checkbox"/> B-HWS <input type="checkbox"/> Cr <input type="checkbox"/> CN- <input type="checkbox"/> EC <input type="checkbox"/> FOC <input checked="" type="checkbox"/> Cr+6 <input type="checkbox"/> SAR <input type="checkbox"/> NO <sub>2</sub> /NO <sub>3</sub> <input type="checkbox"/> N-Total <input checked="" type="checkbox"/> Hg <input type="checkbox"/> pH | Nutrients: <input type="checkbox"/> TP <input type="checkbox"/> NH <sub>3</sub> <input type="checkbox"/> TKN <input type="checkbox"/> NO <sub>2</sub> <input type="checkbox"/> NO <sub>3</sub> /NO <sub>3</sub> | VOC: <input type="checkbox"/> VOC <input type="checkbox"/> THM <input checked="" type="checkbox"/> BTEX | CCME Fractions 1 to 4 | ABNs | PAHs | Chlorophenols | PCBs | Organochlorine Pesticides | TCLP Metals/Inorganics | Sewer Use |
|-----------------------|------------|------------------------|----------------------|--|---|---|-----------------------|------|------|---------------|------|---------------------------|------------------------|-----------|
|                       | 153        |                        |                      |  |   |   |                       |      |      |               |      |                           |                        |           |

Samples Relinquished By (Print Name and Sign): Kathy Holmes Date/Time: 12/07/20 3:30  
 Samples Received By (Print Name and Sign): UD Date/Time: 2020/07/14 11:00  
 Samples Relinquished By (Print Name and Sign): UD Date/Time: 2020/07/14 16:00  
 Samples Received By (Print Name and Sign): SIMRAN Date/Time: July 15/20

Pink Copy - Client  
Yellow Copy - AGAT  
White Copy - AGAT

Page 2 of 4  
N#: 42721



# AGAT Laboratories

5835 Coopers Avenue  
Mississauga, Ontario L4Z 1Y2  
Ph: 905.712.5100 Fax: 905.712.5122  
webearth.agatlabs.com

**Laboratory Use Only**  
Work Order #: 202624793  
Cooler Quantity: 20  
Arrival Temperatures: \_\_\_\_\_  
Custody Seal Intact:  Yes  No  N/A  
Notes: \_\_\_\_\_

## Chain of Custody Record

If this is a Drinking Water sample, please use Drinking Water Chain of Custody Form (potable water consumed by humans)

**Report Information:**  
Company: \_\_\_\_\_  
Contact: \_\_\_\_\_  
Address: \_\_\_\_\_  
Phone: \_\_\_\_\_ Fax: \_\_\_\_\_  
Reports to be sent to:  
1. Email: \_\_\_\_\_  
2. Email: \_\_\_\_\_

### Regulatory Requirements: No Regulatory Requirement

(Please check all applicable boxes)

Regulation 153/04  
 Sewer Use  
 Regulation 558

Table *Indicate One*  
 Ind/Com  
 Res/Park  
 Agriculture

Soil Texture *(Check One)*  
 Coarse  
 Fine

Sanitary  
 Storm  
 CCME  
 Prov. Water Quality Objectives (PWQO)  
 Other

Region \_\_\_\_\_ *Indicate One*  
 MISA  
\_\_\_\_\_ *Indicate One*

**Turnaround Time (TAT) Required:**  
**Regular TAT**  5 to 7 Business Days  
**Rush TAT** (Rush Surcharges Apply)  
 3 Business Days  2 Business Days  Next Business Day  
OR Date Required (Rush Surcharges May Apply): \_\_\_\_\_  
Please provide prior notification for rush TAT  
\*TAT is exclusive of weekends and statutory holidays  
For 'Same Day' analysis, please contact your AGAT CPM

**Project Information:**  
Project: \_\_\_\_\_  
Site Location: \_\_\_\_\_  
Sampled By: \_\_\_\_\_  
AGAT Quote #: \_\_\_\_\_ PO: \_\_\_\_\_  
*Please note: If quotation number is not provided, client will be billed full price for analysis.*

**Is this submission for a Record of Site Condition?**  
 Yes  No

**Report Guideline on Certificate of Analysis**  
 Yes  No

**Invoice Information:** Bill To Same: Yes  No   
Company: \_\_\_\_\_  
Contact: \_\_\_\_\_  
Address: \_\_\_\_\_  
Email: \_\_\_\_\_

**Sample Matrix Legend**

- B Biota
- GW Ground Water
- O Oil
- P Paint
- S Soil
- SD Sediment
- SW Surface Water

| Field Filtered - Metals, Hg, CrVI | O. Reg 153  |   | Full Metals Scan | Regulation/Custom Metals | Nutrients: TP, NH <sub>3</sub> , NO <sub>2</sub> , NO <sub>3</sub> , NO <sub>3</sub> +NO <sub>2</sub>                                       | Volatiles: VOC, BTEX, THM  | PHCs F1 - F4 | ABNS | PAHs | PCBs: Total, Aroclors  | Organochlorine Pesticides                          | TCLP: M&I, VOCs, ABNS, B(a)P, PCBs  | Sewer Use                          |
|-----------------------------------|---|---|------------------|--------------------------|---|--|--------------|------|------|--|--|---|------------------------------------|
|                                   | Metals and Inorganics   | 153 Metals (excl. Hydrides)   |                  |                          |   |  |              |      |      |  |  |   |                                    |
|                                   | <input type="checkbox"/> All Metals <input type="checkbox"/> 153 Metals (excl. Hydrides)                | <input checked="" type="checkbox"/> Hydride Metals  |                  |                          | <input type="checkbox"/> TP <input type="checkbox"/> NH <sub>3</sub> <input type="checkbox"/> TKN   | <input type="checkbox"/> VOC <input checked="" type="checkbox"/> BTEX <input type="checkbox"/> THM |              |      |      | <input type="checkbox"/> Total <input type="checkbox"/> Aroclors | <input type="checkbox"/> Organochlorine Pesticides | <input type="checkbox"/> M&I <input type="checkbox"/> VOCs <input type="checkbox"/> ABNS <input type="checkbox"/> B(a)P <input type="checkbox"/> PCBs | <input type="checkbox"/> Sewer Use |
|                                   | ORPs: <input checked="" type="checkbox"/> B-HWS <input type="checkbox"/> Cl <input type="checkbox"/> CN | <input checked="" type="checkbox"/> OC* <input type="checkbox"/> EC <input type="checkbox"/> FOC <input checked="" type="checkbox"/> Hg |                  |                          | <input type="checkbox"/> NO <sub>2</sub> <input type="checkbox"/> NO <sub>3</sub> <input type="checkbox"/> NO <sub>3</sub> +NO <sub>2</sub> |  |              |      |      |  |  |   | <input type="checkbox"/> Sewer Use |
|                                   | <input type="checkbox"/> pH <input type="checkbox"/> SAR  |   |                  |                          |   |  |              |      |      |  |  |   |                                    |

| Sample Identification | Date Sampled | Time Sampled | # of Containers | Sample Matrix | Comments/<br>Special Instructions | Y / N |
|-----------------------|--------------|--------------|-----------------|---------------|-----------------------------------|-------|
| TP4-15 SAI            | 8/07/20      | 12:00        | 3               | S             |                                   |       |
| TP4-16 SAI            |              |              |                 |               |                                   |       |
| TP6A-17 SAI           |              |              |                 |               |                                   |       |
| TP6A-20 SAI           |              |              |                 |               |                                   |       |
| TP6B-21 SAI           |              |              |                 |               |                                   |       |
| TP6B-22 SAI           |              |              |                 |               |                                   |       |
| TP6B-24 SAI           |              |              |                 |               |                                   |       |
| TP6B-25 SAI           |              |              |                 |               |                                   |       |
| TP6B-26 SAI           |              |              |                 |               |                                   |       |
| TP7-27 SAI            |              |              |                 |               |                                   |       |
| TP7-28 SAI            |              |              |                 |               |                                   |       |

|  |   |   |   |
|--|---|---|---|
| <b>Samples Relinquished By (Print Name and Sign):</b><br>Kerz/Holmes | <b>Date:</b> 8/7/20<br><b>Time:</b> 3:30      | <b>Samples Received By (Print Name and Sign):</b><br>VD/D   | <b>Date:</b> 2020/7/14<br><b>Time:</b> 11:06    |
| <b>Samples Relinquished By (Print Name and Sign):</b><br>to FedEx    | <b>Date:</b> 2020/07/14<br><b>Time:</b> 16:00 | <b>Samples Received By (Print Name and Sign):</b><br>JIMRAN | <b>Date:</b> July 15/20<br><b>Time:</b> 10:20am |

Page 3 of 4  
No: T085407



### Laboratory Use Only

Arrival Temperature: \_\_\_\_\_  
AGAT WO #: 202624793  
Lab Temperature: \_\_\_\_\_  
Notes: \_\_\_\_\_

## Chain of Custody Record

P: 905.712.5100 • F: 905.712.5122

### Client Information

Company: \_\_\_\_\_  
Contact: \_\_\_\_\_  
Address: \_\_\_\_\_  
Phone: \_\_\_\_\_ Fax: \_\_\_\_\_  
Project: \_\_\_\_\_ PO: \_\_\_\_\_  
AGAT Quotation #: \_\_\_\_\_

Please note, if quotation number is not provided, client will be billed full price for analysis.

### Regulatory Requirements

- Regulation 153/04 (reg. 511 Amend.)
- Table \_\_\_\_\_ Indicate one
- Ind/Com  
 Res/Park  
 Agriculture
- Soil Texture (check one)  
 Coarse  Fine
- Sewer Use
- Region \_\_\_\_\_ Indicate one
- Sanitary  
 Storm
- Regulation 558  
 CCME  
 Other (specify) \_\_\_\_\_
- Prov. Water Quality Objectives (PWQO)  
 None

### Turnaround Time Required (TAT) Required\*

- Regular TAT**
- 5 to 7 Working Days
- Rush TAT** (please provide prior notification)  
**Rush Surcharges Apply**
- 3 Working Days  
 2 Working Days  
 1 Working Day
- OR**
- Date Required (Rush surcharges may apply): \_\_\_\_\_

### Invoice To

Same: Yes  No

Company: \_\_\_\_\_  
Contact: \_\_\_\_\_  
Address: \_\_\_\_\_

Is this a drinking water sample?  
(potable water intended for human consumption)  
 Yes  No

If "Yes", please use the  
**Drinking Water Chain of Custody Form**

Is this submission for a Record of Site Condition?

Yes  No

\*TAT is exclusive of weekends and statutory holidays

### Legend Matrix

- GW** Ground Water **O** Oil  
**SW** Surface Water **P** Paint  
**SD** Sediment **S** Soil

### Report Information - reports to be sent to:

1. Name: \_\_\_\_\_  
Email: \_\_\_\_\_  
2. Name: \_\_\_\_\_  
Email: \_\_\_\_\_

| Sample Identification | Date Sampled | Time Sampled | Sample Matrix | # of Containers | Comments<br>Site/Sample Information | Metals and Inorganics | Metal Scan | Hydride Forming Metals | Client Custom Metals | ORPs: <input type="checkbox"/> H <sub>2</sub> S <input type="checkbox"/> Cl <sup>-</sup> <input type="checkbox"/> CN <sup>-</sup> <input type="checkbox"/> EC | FOC <input type="checkbox"/> TOC <input type="checkbox"/> SAR | NO <sub>2</sub> /NO <sub>3</sub> <input type="checkbox"/> N-Total <input type="checkbox"/> Hg <input type="checkbox"/> pH | Nutrients: <input type="checkbox"/> TP <input type="checkbox"/> NH <sub>4</sub> <input type="checkbox"/> TKN<br><input type="checkbox"/> NO <sub>3</sub> <input type="checkbox"/> NO <sub>2</sub> <input type="checkbox"/> NO <sub>3</sub> /NO <sub>2</sub> | VOC: <input type="checkbox"/> VOC <input type="checkbox"/> THM <input type="checkbox"/> BTX | CCME Fractions 1 to 4 | ABNS | PAHs | Chlorophenols | PCBs | Organochlorine Pesticides | TCLP Metals/Inorganics | Sewer Use |  |
|-----------------------|--------------|--------------|---------------|-----------------|-------------------------------------|-----------------------|------------|------------------------|----------------------|---|---|---|---|---|-----------------------|------|------|---------------|------|---------------------------|------------------------|-----------|--|
| SPD-54                | 9/07/20      | 12:00        | S             | 3               |                                     | X                     |            |                        |                      | X   |   |   |   |   | X                     |      |      |               |      |                           |                        |           |  |
| SPD-544               |              |              |               |                 |                                     |                       |            |                        |                      |   |   |   |   |   |                       |      |      |               |      |                           |                        |           |  |
| SPD-545               |              |              |               |                 |                                     |                       |            |                        |                      |   |   |   |   |   |                       |      |      |               |      |                           |                        |           |  |
| SPD-546               |              |              |               |                 |                                     |                       |            |                        |                      |   |   |   |   |   |                       |      |      |               |      |                           |                        |           |  |
| SPD-547               |              |              |               |                 |                                     |                       |            |                        |                      |   |   |   |   |   |                       |      |      |               |      |                           |                        |           |  |
| DUP 2                 | 7/07/20      | 12:00        | S             | 3               |                                     | X                     |            |                        |                      | X   |   |   |   |   | X                     |      |      |               |      |                           |                        |           |  |

|   |                                |   |                                |                     |                           |
|---|--------------------------------|---|--------------------------------|---------------------|---------------------------|
| Samples Relinquished By (Print Name and Sign):<br><u>W/D TO FedEx</u> | Date/Time:<br>2020/07/14/16:00 | Samples Received By (Print Name and Sign):<br><u>SIMRAN</u> | Date/Time:<br>2020/07/14/11:00 | White Copy - Client | Page <u>4</u> of <u>4</u> |
| Samples Relinquished By (Print Name and Sign):<br><u>W/D TO FedEx</u> | Date/Time:<br>2020/07/14/16:00 | Samples Received By (Print Name and Sign):<br><u>SIMRAN</u> | Date/Time:<br>July 15/20       | Yellow Copy - AGAT  | Nº: <u>42722</u>          |
|   |                                |   |                                | White Copy - AGAT   |                           |



## Sample Temperature Log

Client: Golden

COC# or Work Order #: 207624793

# of Coolers: two - ice (melted)  
 Arrival Temperatures - Branch/Driver

# of Submissions: amo  
 Arrival Temperatures - Laboratory

Cooler #1: 11.7 / 12.5 / 12.2

Cooler #1: 6.6 / 6.7 / 6.8

Cooler #2: 14.4 / 14.5 / 14.1

Cooler #2: 7.2 / 6.8 / 7.5

Cooler #3:     /    /    

Cooler #3:     /    /    

Cooler #4:     /    /    

Cooler #4:     /    /    

Cooler #5:     /    /    

Cooler #5:     /    /    

Cooler #6:     /    /    

Cooler #6:     /    /    

Cooler #7:     /    /    

Cooler #7:     /    /    

Cooler #8:     /    /    

Cooler #8:     /    /    

Cooler #9:     /    /    

Cooler #9:     /    /    

Cooler #10:     /    /    

Cooler #10:     /    /    

IR Gun ID: 1439003407

IR Gun ID: \_\_\_\_\_

Taken By: Linda B

Taken By: SIMRAN

Date (yyyy/mm/dd): 2020/07/14 Time: 11:06 AM / PM

Date (yyyy/mm/dd): 2020/07/15 Time: 10:20 AM / PM

**Instructions for use of this form:** 1) complete all fields of info including total # of coolers and # of submissions rec'd, 2) photocopy and place in each submission prior to giving a WO#, 3) Proceed as normal, write the WO# and scan ( please make sure to scan along with the COC)

**APPENDIX E**

**Tables**



**Table 1 - Monitoring Well Construction Details**

| Monitoring well ID | Date of well completion | Ground surface elevation (m) <sup>1</sup> | Monitoring well elevation (m) <sup>1</sup> | Borehole depth (mbgs) | Borehole depth elevation (m) <sup>1</sup> | Screen interval (mbgs) | Screen interval elevation (m) <sup>1</sup> | Screened media |
|--------------------|-------------------------|---|--|-----------------------|---|------------------------|--|----------------|
| BHMW14             | 16-Nov-04               | 90.20                                     | 90.93                                      | 6.2                   | 84.00                                     | 2.1 - 6.2              | 84.00-88.10                                | Bedrock        |
| BHMW126-1          | 03-Mar-15               | 90.54                                     | 91.47                                      | 6.2                   | 84.34                                     | 3.9 - 6.2              | 84.34-86.64                                | Bedrock        |
| BHMW31-1           | 02-Nov-15               | 82.91                                     | 83.87                                      | 6                     | 76.91                                     | 3.1 - 6                | 76.91-79.81                                | Bedrock        |
| 22-02              | 11-Jul-22               | 88.79                                     | 89.469                                     | 7.92                  | 80.87                                     | 4.88 - 7.92            | 83.91-80.87                                | Bedrock        |
| 22-03              | 12-Jul-22               | 86.22                                     | 86.959                                     | 10.06                 | 76.16                                     | 7.01 - 10.06           | 79.21-76.16                                | Bedrock        |
| 22-04              | 11-Jul-22               | 87.78                                     | 86.961                                     | 12.19                 | 75.59                                     | 9.14 - 12.19           | 78.64-75.59                                | Bedrock        |
| 22-05              | 13-Jul-22               | 90.27                                     | 91.027                                     | 12.19                 | 78.08                                     | 9.14 - 12.19           | 81.13-78.08                                | Bedrock        |
| 22-06              | 13-Jul-22               | 90.33                                     | 91.267                                     | 12.19                 | 78.14                                     | 9.14 - 12.19           | 81.19-78.14                                | Bedrock        |
|                    |                         |   |  |                       |   |                        |  |                |

**Notes:**

- m metres
- masl metres above sea level
- mbgs metres below ground surface
- Measurement not obtained.
- <sup>1</sup> Elevations are reported relative to a temporary bench mark (top bolt of fire hydrant located on Arthur Street South, adjacent to monitoring well BH-206) assigned an arbitrary elevation of 100 masl

**Table 2 - Summary of Soil Samples Submitted for Laboratory Analysis**

| Sampling Program                             | Sample Locations | Sample ID   | Sample Depth (mbgs) | Sample Analysis                                     |
|--|------------------|-------------|---------------------|---|
| Golder 2022 Sewer Trench Delineation Program | TP22-01          | TP22-01 SA1 | 0.9-1.1             | Metals, Cr, Cr VI, Hg, HWSB, PHCs F1-F4, PAHs, BTEX |
|  |                  | TP22-01 SA2 | 2.0-2.2             |   |
|  |                  | TP22-01 SA3 | 3.2-3.6             |   |
|  | TP22-02          | TP22-02 SA1 | 1.25-1.75           | Metals, Cr, Cr VI, Hg, HWSB, PHCs F1-F4, PAHs, BTEX |
|  |                  | TP22-02 SA2 | 2.25-2.75           |   |
|  |                  | TP22-02 SA3 | 3.75-4.2            |   |
|  | TP22-03          | TP22-03 SA1 | 0.1-0.4             | Metals, Cr, Cr VI, Hg, HWSB, PHCs F1-F4, PAHs, BTEX |
|  |                  | TP22-03 SA2 | 0.4-1.1             |   |
|  | TP22-04          | TP22-04 SA1 | 1.5-1.7             | Metals, Cr, Cr VI, Hg, HWSB, PHCs F1-F4, PAHs, BTEX |
|  |                  | TP22-04 SA2 | 2.7-3.0             |   |
|  |                  | TP22-04 SA3 | 3.7-4.0             |   |
|  | TP22-05          | TP22-05 SA1 | 0.9-1.2             | Metals, Cr, Cr VI, Hg, HWSB, PHCs F1-F4, PAHs, BTEX |
|  |                  | TP22-05 SA2 | 2.3-2.5             |   |
|  |                  | TP22-05 SA3 | 3.8-4.0             |   |
|  | TP22-06          | TP22-06 SA1 | 0.6-1.7             | Metals, Cr, Cr VI, Hg, HWSB, PHCs F1-F4, PAHs, BTEX |
|  |                  | TP22-06 SA2 | 1.7-3.1             |   |
|  |                  | TP22-06 SA3 | 3.1-3.8             |   |
|  | TP22-07          | TP22-07 SA1 | 0.8-1.0             | Metals, Cr, Cr VI, Hg, HWSB, PHCs F1-F4, PAHs, BTEX |
|  |                  | TP22-07 SA2 | 2.0-2.3             |   |
|  |                  | TP22-07 SA3 | 3.5-3.8             |   |
|  | TP22-08          | TP22-08 SA1 | 1.0-1.2             | Metals, Cr, Cr VI, Hg, HWSB, PHCs F1-F4, PAHs, BTEX |
|  |                  | TP22-08 SA2 | 1.8-2.0             |   |
|  |                  | TP22-08 SA3 | 2.8-3.0             |   |

**Table 2 - Summary of Soil Samples Submitted for Laboratory Analysis**

| Sampling Program                                 | Sample Locations | Sample ID                 | Sample Depth (mbgs) | Sample Analysis                                     |
|--|------------------|---------------------------|---------------------|---|
| Golder 2022 Sampling Program                     | 22-02            | 22-02 SA1                 | 0 - 1.52            | Metals, Cr, Cr VI, Hg, HWSB, PHCs F1-F4, PAHs, BTEX |
|  | 22-03            | 22-03 SA1                 | 0 - 1.52            | Metals, Cr, Cr VI, Hg, HWSB, PHCs F1-F4, PAHs, BTEX |
|  | 22-03            | 22-03 SA2                 | 1.52 - 1.98         | Metals, Cr, Cr VI, Hg, HWSB, PHCs F1-F4, PAHs, BTEX |
|  | 22-04            | 22-04 SA2;<br>22-04 DUP-1 | 2.13 - 2.74         | Metals, Cr, Cr VI, Hg, HWSB, PHCs F1-F4, PAHs, BTEX |
|  | 22-04            | 22-04 SA7                 | 7.0 - 7.46          | Metals, Cr, Cr VI, Hg, HWSB, PHCs F1-F4, PAHs, BTEX |
|  | 22-05            | 22-05 SA2                 | 0.3 - 0.61          | Metals, Cr, Cr VI, Hg, HWSB, PHCs F1-F4, PAHs, BTEX |
|  | 22-06            | 22-06 SA1                 | 0 - 1.22            | Metals, Cr, Cr VI, Hg, HWSB, PHCs F1-F4, PAHs, BTEX |
| Golder 2020 Sampling Program                     | TP4-01           | TP4-01 SA1                | 0.3-0.5             | Metals, Cr, Cr VI, Hg, HWSB, PHCs F1-F4, PAHs, BTEX |
|  | TP4-02           | TP4-02 SA1                | 0.75-1              | Metals, Cr, Cr VI, Hg, HWSB, PHCs F1-F4, PAHs, BTEX |
|  | TP4-10           | TP4-10 SA1                | 1.75-2              | Metals, Cr, Cr VI, Hg, HWSB, PHCs F1-F4, PAHs, BTEX |
|  | TP4-12           | TP4-12 SA1                | 0-0.5               | Metals, Cr, Cr VI, Hg, HWSB, PHCs F1-F4, PAHs, BTEX |
|  | TP4-13           | TP4-13 SA1                | 0.0-0.65            | Metals, Cr, Cr VI, Hg, HWSB, PHCs F1-F4, PAHs, BTEX |
|  | TP4-15           | TP4-15 SA1                | 0.3-0.5             | Metals, Cr, Cr VI, Hg, HWSB, PHCs F1-F4, PAHs, BTEX |
|  | TP4-16           | TP4-16 SA1                | 0-1.2               | Metals, Cr, Cr VI, Hg, HWSB, PHCs F1-F4, PAHs, BTEX |
| DST Soil and Groundwater Remediation Report 2017 | TP61             | TP61 SGS1                 | 0.1-0.4             | Metals, PHC F1-F4, BTEX, PAHs                       |
|  | TP62             | TP62 SGS1                 | 0.6-0.9             |   |
|  | TP126-1          | TP126-1 S1                | 0.0-0.8             | Metals, BTEX,                                       |
|  | TP126-2          | TP126-2 S1                | 0.0-0.8             |   |
|  | BHMW14           | BHMW14 SS2                | 0.6-1.0             | Metals, PHC F1-F4, BTEX, PAHs                       |

**Notes**

- mbgs                    metres below groundsurface
  - ppmv                   parts per million by volume
  - PHC                    petroleum hydrocarbons
  - VOC                    Volatile organic compounds
  - M                        Metals, hydride forming metals
  - ORP                    Other Regulated Parameters - hot water soluble boron, hexavalent chromium, mercury, cyanide, electrical conductivity, sodium absorption ratio and pH
  - PCB                    polychlorinated biphenyls
- Table to be read in conjunction with accompanying report

**Table 3 - Groundwater Levels and Elevations**

| Location ID | Ground surface elevation (masl) | Top of pipe elevation (masl) | Golder 2022 Investigation |                   |                              | 2015 DST Remediation   |                   |                       |                              |
|-------------|---------------------------------|------------------------------|---------------------------|-------------------|------------------------------|------------------------|-------------------|-----------------------|------------------------------|
|             |                                 |                              | 18-Jul-22                 |                   |                              | 2015-03-04             |                   |                       |                              |
|             |                                 |                              | Depth to water (mbtop)    | Well Depth (mbgs) | Groundwater Elevation (masl) | Depth to water (mbtop) | Well Depth (mbgs) | Depth to water (mbgs) | Groundwater Elevation (masl) |
| BHMW31-1    | 82.91                           | 83.87                        | --                        | --                | --                           | 5.89                   | 6.00              | 4.93                  | 77.98                        |
| BHMW126-1   | 90.54                           | 91.47                        | --                        | --                | --                           | 4.83                   | 6.20              | 3.82                  | 86.64                        |
| BHMW14      | 90.20                           | 90.93                        | --                        | --                | --                           | 4.19                   | 6.20              | 3.26                  | 86.74                        |
| 22-02       | 88.79                           | 89.469                       | 7.33                      | 7.92              | 82.14                        | --                     | --                | --                    | --                           |
| 22-03       | 86.22                           | 86.959                       | NA                        | 10.06             | NA                           | --                     | --                | --                    | --                           |
| 22-04       | 87.78                           | 86.961                       | 9.40                      | 12.19             | 77.57                        | --                     | --                | --                    | --                           |
| 22-05       | 90.27                           | 91.027                       | 9.17                      | 12.19             | 81.86                        | --                     | --                | --                    | --                           |
| 22-06       | 90.33                           | 91.267                       | 9.44                      | 12.19             | 81.83                        | --                     | --                | --                    | --                           |

**Notes:**

- m metres
  - masl metres above sea level
  - mbtop metres below top of pipe
  - mbgs metres below ground surface
  - NA not available
  - not applicable
- Table to be read in conjunction with accompanying report.

**Table 4 - Summary of Groundwater Samples Submitted for Laboratory Analysis**

| Sample Location | Monitoring Well | Well Depth (mbgs) | Screen Interval (mbgs) | Soil Description of Screened Interval | Sample ID     | Sampling Date | Groundwater Analysis                      |
|-----------------|-----------------|-------------------|------------------------|---------------------------------------|---------------|---------------|---|
| 22-02           | 22-02           | 7.92              | 4.88 - 7.92            | Bedrock                               | 22-02         | 07/18/2022    | Metals, Cr VI, Hg, PHCs F1-F4, PAHs, BTEX |
| 22-03           | 22-03           | 10.06             | 7.01 - 10.06           | Bedrock                               | NA            | NA            | NA  |
| 22-04           | 22-04           | 12.19             | 9.14 - 12.19           | Bedrock                               | 22-04; DUP 01 | 07/18/2022    | Metals, Cr VI, Hg, PHCs F1-F4, PAHs, BTEX |
| 22-05           | 22-05           | 12.19             | 9.14 - 12.19           | Bedrock                               | 22-05         | 07/18/2022    | Metals, Cr VI, Hg, PHCs F1-F4, PAHs, BTEX |
| 22-06           | 22-06           | 12.19             | 9.14 - 12.19           | Bedrock                               | 22-06         | 07/18/2022    | Metals, Cr VI, Hg, PHCs F1-F4, PAHs, BTEX |
| BHMW31-1        | BHMW31-1        | 6.0               | 3.1 - 6.0              | Bedrock                               | BHMW31-1      | 03/04/2015    | Metals                                    |
|                 |                 |                   |                        |                                       | BHMW31-1      | 03/20/2016    | Metals                                    |
| BHMW126-1       | BHMW126-1       | 6.2               | 3.9 - 6.2              | Bedrock                               | BHMW126-1     | 03/31/2015    | PHC F1-F4, BTEX, PAHs                     |
|                 |                 |                   |                        |                                       | BHMW126-1     | 03/20/2016    | PHC F1-F4, BTEX, PAHs                     |
| BHMW 14         | BHMW 14         | 6.2               | 2.1 - 6.2              | Bedrock                               | BHMW14        | 03/31/2015    | PHC F1-F4, BTEX, PAHs                     |
|                 |                 |                   |                        |                                       | BHMW14        | 03/20/2016    | PHC F1-F4, BTEX, PAHs                     |

| Sample Location                   | Unit | MECP Table 1 Standard (R/P/I/I/C/C) <sup>(1)</sup> | TP22-01                    |                            |                            | TP22-02     |             |             | TP22-03     |             |
|-----------------------------------|------|--|----------------------------|----------------------------|----------------------------|-------------|-------------|-------------|-------------|-------------|
| Sample ID                         |      |  | TP22-01 SA1 <sup>(2)</sup> | TP22-01 SA2 <sup>(2)</sup> | TP22-01 SA3 <sup>(2)</sup> | TP22-02 SA1 | TP22-02 SA2 | TP22-02 SA3 | TP22-03 SA1 | TP22-03 SA2 |
| Date Sampled                      |      |  | 10/19/2022                 | 10/19/2022                 | 10/19/2022                 | 10/19/2022  | 10/19/2022  | 10/19/2022  | 10/19/2022  | 10/19/2022  |
| Sample Depth (mbgs)               | mbgs |  | 0.3-1.5                    | 1.5-3.2                    | 3.2-3.6                    | 0.1-2.1     | 2.25-2.75   | 3.75-4.2    | 0.1-0.4     | 0.4-1.1     |
| Parameter                         |      |  |                            |                            |                            |             |             |             |             |             |
| Benzene                           | µg/g | 0.02   | <0.02                      | <0.02                      | <0.02                      | <0.02       | <0.02       | <0.02       | <0.02       | <0.02       |
| Toluene                           | µg/g | 0.20   | <0.02                      | <0.02                      | <0.02                      | <0.02       | <0.02       | <0.02       | <0.02       | <0.02       |
| Ethylbenzene                      | µg/g | 0.05   | <0.02                      | <0.02                      | <0.02                      | <0.02       | <0.02       | <0.02       | <0.02       | <0.02       |
| o-Xylene                          | µg/g | --   | <0.02                      | <0.02                      | <0.02                      | <0.02       | <0.02       | <0.02       | <0.02       | <0.02       |
| p+m-Xylene                        | µg/g | --   | <0.04                      | <0.04                      | <0.04                      | <0.04       | <0.04       | <0.04       | <0.04       | <0.04       |
| Xylenes (Total)                   | µg/g | 0.05   | <0.04                      | <0.04                      | <0.04                      | <0.04       | <0.04       | <0.04       | <0.04       | <0.04       |
| F1 (C6 to C10)                    | µg/g | 25   | <10                        | <10                        | <10                        | <10         | <10         | <10         | <10         | <10         |
| F1 (C6 to C10) minus BTEX         | µg/g | 25   | <10                        | <10                        | <10                        | <10         | <10         | <10         | <10         | <10         |
| F2 (C10 to C16)                   | µg/g | 10   | <10                        | <10                        | <10                        | <10         | <b>36</b>   | <10         | <10         | <10         |
| F2 (C10 to C16) minus Naphthalene | µg/g | 10   | --                         | --                         | --                         | --          | --          | --          | --          | --          |
| F3 (C16 to C34)                   | µg/g | 240  | <50                        | <50                        | 140                        | <50         | 54          | <50         | <50         | <50         |
| F3 (C16 to C34) minus PAHs        | µg/g | --   | --                         | --                         | --                         | --          | --          | --          | --          | --          |
| F4 (C34 to C50)                   | µg/g | 120  | 64                         | <50                        | <b>390</b>                 | <50         | <50         | <50         | <50         | <50         |
| Reached Baseline at C50           | --   | --   | Yes                        | Yes                        | Yes                        | Yes         | Yes         | Yes         | Yes         | Yes         |
| Gravimetric Heavy Hydrocarbons    | µg/g | --   | --                         | --                         | --                         | --          | --          | --          | --          | --          |
| Moisture Content                  | %    | --   | 21                         | 22                         | 13                         | 23          | 21          | 15          | 22          | 19          |

**Table 5a - Soil Analytical Results (Petroleum Hydrocarbons)**

| Sample Location                   | Unit | MECP Table 1 Standard (R/P/I/I/C/C) <sup>(1)</sup> | TP22-04     |             |             | TP22-05     |             |             |
|-----------------------------------|------|--|-------------|-------------|-------------|-------------|-------------|-------------|
| Sample ID                         |      |  | TP22-04 SA1 | TP22-04 SA2 | TP22-04 SA3 | TP22-05 SA1 | TP22-05 SA2 | TP22-05 SA3 |
| Date Sampled                      |      |  | 10/19/2022  | 10/19/2022  | 10/19/2022  | 10/19/2022  | 10/19/2022  | 10/19/2022  |
| Sample Depth (mbgs)               | mbgs |  | 1.5-1.7     | 2.7-3.0     | 3.7-4.0     | 0.9-1.2     | 2.3-2.5     | 3.8-4.0     |
| Parameter                         |      |  |             |             |             |             |             |             |
| Benzene                           | µg/g | 0.02   | <0.02       | <0.02       | <0.02       | <0.02       | <0.02       | <0.02       |
| Toluene                           | µg/g | 0.20   | <0.02       | <0.02       | <0.02       | <0.02       | <0.02       | <0.02       |
| Ethylbenzene                      | µg/g | 0.05   | <0.02       | <0.02       | <0.02       | <0.02       | <0.02       | <0.02       |
| o-Xylene                          | µg/g | --   | <0.02       | <0.02       | <0.02       | <0.02       | <0.02       | <0.02       |
| p+m-Xylene                        | µg/g | --   | <0.04       | <0.04       | <0.04       | <0.04       | <0.04       | <0.04       |
| Xylenes (Total)                   | µg/g | 0.05   | <0.04       | <0.04       | <0.04       | <0.04       | <0.04       | <0.04       |
| F1 (C6 to C10)                    | µg/g | 25   | <10         | <10         | <10         | <10         | <10         | <10         |
| F1 (C6 to C10) minus BTEX         | µg/g | 25   | <10         | <10         | <10         | <10         | <10         | <10         |
| F2 (C10 to C16)                   | µg/g | 10   | <10         | <10         | <10         | <10         | <10         | <10         |
| F2 (C10 to C16) minus Naphthalene | µg/g | 10   | --          | --          | --          | --          | --          | --          |
| F3 (C16 to C34)                   | µg/g | 240  | <50         | <50         | <50         | <50         | <50         | <50         |
| F3 (C16 to C34) minus PAHs        | µg/g | --   | --          | --          | --          | --          | --          | --          |
| F4 (C34 to C50)                   | µg/g | 120  | <50         | <50         | 54          | <50         | <50         | <50         |
| Reached Baseline at C50           | --   | --   | Yes         | Yes         | Yes         | Yes         | Yes         | Yes         |
| Gravimetric Heavy Hydrocarbons    | µg/g | --   | --          | --          | --          | --          | --          | --          |
| Moisture Content                  | %    | --   | 19          | 30          | 19          | 19          | 28          | 23          |

**Table 5a - Soil Analytical Results (Petroleum Hydrocarbons)**

| Sample Location                   | Unit | MECP Table 1 Standard (R/P/I/I/C/C) <sup>(1)</sup> | TP22-06     |             |             | TP22-07     |             |             | BH22-02     |
|-----------------------------------|------|--|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Sample ID                         |      |  | TP22-06 SA1 | TP22-06 SA2 | TP22-06 SA3 | TP22-07 SA1 | TP22-07 SA2 | TP22-07 SA3 | BH22-02 SA1 |
| Date Sampled                      |      |  | 10/19/2022  | 10/19/2022  | 10/19/2022  | 10/19/2022  | 10/19/2022  | 10/19/2022  | 07/11/2022  |
| Sample Depth (mbgs)               | mbgs |  | 0.6-1.7     | 1.7-3.1     | 3.1-3.8     | 0.8-1.0     | 2.0-2.3     | 3.5-3.8     | 0-1.4       |
| Parameter                         |      |  |             |             |             |             |             |             |             |
| Benzene                           | µg/g | 0.02   | <0.02       | <0.02       | <0.02       | <0.02       | <0.02       | <0.02       | <0.02       |
| Toluene                           | µg/g | 0.20   | <0.02       | <0.02       | <0.02       | <0.02       | <0.02       | <0.02       | <0.05       |
| Ethylbenzene                      | µg/g | 0.05   | <0.02       | <0.02       | <0.02       | <0.02       | <0.02       | <0.02       | <0.05       |
| o-Xylene                          | µg/g | --   | <0.02       | <0.02       | <0.02       | <0.02       | <0.02       | <0.02       | <0.05       |
| p+m-Xylene                        | µg/g | --   | <0.04       | <0.04       | <0.04       | <0.04       | <0.04       | <0.04       | <0.05       |
| Xylenes (Total)                   | µg/g | 0.05   | <0.04       | <0.04       | <0.04       | <0.04       | <0.04       | <0.04       | <0.05       |
| F1 (C6 to C10)                    | µg/g | 25   | <10         | <10         | <10         | <10         | <10         | <10         | <5          |
| F1 (C6 to C10) minus BTEX         | µg/g | 25   | <10         | <10         | <10         | <10         | <10         | <10         | <5          |
| F2 (C10 to C16)                   | µg/g | 10   | <10         | <b>96</b>   | <10         | <10         | <10         | <10         | <10         |
| F2 (C10 to C16) minus Naphthalene | µg/g | 10   | --          | --          | --          | --          | --          | --          | <10         |
| F3 (C16 to C34)                   | µg/g | 240  | <50         | 88          | 84          | <50         | <50         | <50         | <50         |
| F3 (C16 to C34) minus PAHs        | µg/g | --   | --          | --          | --          | --          | --          | --          | <50         |
| F4 (C34 to C50)                   | µg/g | 120  | <50         | <50         | 120         | <50         | <50         | <50         | <50         |
| Reached Baseline at C50           | --   | --   | Yes         | Yes         | Yes         | Yes         | Yes         | Yes         | Yes         |
| Gravimetric Heavy Hydrocarbons    | µg/g | --   | --          | --          | --          | --          | --          | --          | NA          |
| Moisture Content                  | %    | --   | 26          | 17          | 26          | 25          | 24          | 25          | 15.40       |



**Table 5a - Soil Analytical Results (Petroleum Hydrocarbons)**

| Sample Location                   | Unit | MECP Table 1 Standard (R/P/I/I/C/C) <sup>(1)</sup> | BH22-03     |             | BH22-04     |                                 |             |
|-----------------------------------|------|--|-------------|-------------|-------------|---------------------------------|-------------|
| Sample ID                         |      |  | BH22-03 SA1 | BH22-03 SA2 | BH22-04 SA2 | BH22-04 DUP1 (field dup of SA2) | BH22-04 SA7 |
| Date Sampled                      |      |  | 07/12/2022  | 07/12/2022  | 07/11/2022  | 07/11/2022                      | 07/11/2022  |
| Sample Depth (mbgs)               | mbgs |  | 0-1.5       | 1.5-2.0     | 2.1-2.7     | 2.1-2.7                         | 7-7.5       |
| Parameter                         |      |  |             |             |             |                                 |             |
| Benzene                           | µg/g | 0.02   | <0.02       | <0.02       | <0.02       | <0.02                           | <0.02       |
| Toluene                           | µg/g | 0.20   | <0.05       | <0.05       | <0.05       | <0.05                           | <0.05       |
| Ethylbenzene                      | µg/g | 0.05   | <0.05       | <0.05       | <0.05       | <0.05                           | <0.05       |
| o-Xylene                          | µg/g | --   | <0.05       | <0.05       | <0.05       | <0.05                           | <0.05       |
| p+m-Xylene                        | µg/g | --   | <0.05       | <0.05       | <0.05       | <0.05                           | <0.05       |
| Xylenes (Total)                   | µg/g | 0.05   | <0.05       | <0.05       | <0.05       | <0.05                           | <0.05       |
| F1 (C6 to C10)                    | µg/g | 25   | <5          | <5          | <5          | <5                              | <5          |
| F1 (C6 to C10) minus BTEX         | µg/g | 25   | <5          | <5          | <5          | <5                              | <5          |
| F2 (C10 to C16)                   | µg/g | 10   | <10         | <10         | <10         | <10                             | <10         |
| F2 (C10 to C16) minus Naphthalene | µg/g | 10   | <10         | <10         | <10         | <10                             | <10         |
| F3 (C16 to C34)                   | µg/g | 240  | <50         | <50         | <50         | <50                             | <50         |
| F3 (C16 to C34) minus PAHs        | µg/g | --   | <50         | <50         | <50         | <50                             | <50         |
| F4 (C34 to C50)                   | µg/g | 120  | <50         | <50         | <50         | <50                             | <50         |
| Reached Baseline at C50           | --   | --   | Yes         | Yes         | Yes         | Yes                             | Yes         |
| Gravimetric Heavy Hydrocarbons    | µg/g | --   | NA          | NA          | NA          | NA                              | NA          |
| Moisture Content                  | %    | --   | 16.70       | 23.60       | 21.00       | 16.30                           | 25.10       |

| Sample Location                   | Unit | MECP Table 1 Standard (R/P/I/I/C/C) <sup>(1)</sup> | BH22-05     | BH22-06     | TP4-01     | TP4-02     | TP4-10     | TP4-12     | TP4-13     | TP4-15     | TP4-16     |
|-----------------------------------|------|--|-------------|-------------|------------|------------|------------|------------|------------|------------|------------|
| Sample ID                         |      |  | BH22-05 SA2 | BH22-06 SA1 | TP4-01 SA1 | TP4-02 SA1 | TP4-10 SA1 | TP4-12 SA1 | TP4-13 SA1 | TP4-15 SA1 | TP4-16 SA1 |
| Date Sampled                      |      |  | 07/13/2022  | 07/13/2022  | 07/07/2020 | 07/07/2020 | 07/07/2020 | 07/07/2020 | 07/07/2020 | 07/08/2020 | 07/08/2020 |
| Sample Depth (mbgs)               | mbgs |  | 0.3-0.6     | 0-1.2       | 0.3-0.5    | 0.75-1     | 1.75-2     | 0-0.5      | 0-0.7      | 0.3-0.5    | 0-1.2      |
| Parameter                         |      |  |             |             |            |            |            |            |            |            |            |
| Benzene                           | µg/g | 0.02   | <0.02       | <0.02       | <0.02      | <0.02      | <0.02      | <0.02      | <0.02      | <0.02      | <0.02      |
| Toluene                           | µg/g | 0.20   | <0.05       | <0.05       | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Ethylbenzene                      | µg/g | 0.05   | <0.05       | <0.05       | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| o-Xylene                          | µg/g | --   | <0.05       | <0.05       | --         | --         | --         | --         | --         | --         | --         |
| p+m-Xylene                        | µg/g | --   | <0.05       | <0.05       | --         | --         | --         | --         | --         | --         | --         |
| Xylenes (Total)                   | µg/g | 0.05   | <0.05       | <0.05       | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| F1 (C6 to C10)                    | µg/g | 25   | <5          | <5          | <5         | <5         | <5         | <5         | <5         | <5         | <5         |
| F1 (C6 to C10) minus BTEX         | µg/g | 25   | <5          | <5          | <5         | <5         | <5         | <5         | <5         | <5         | <5         |
| F2 (C10 to C16)                   | µg/g | 10   | <10         | <10         | <10        | <10        | <10        | <10        | <10        | <10        | <10        |
| F2 (C10 to C16) minus Naphthalene | µg/g | 10   | <10         | <10         | <10        | <10        | <10        | <10        | <10        | <10        | <10        |
| F3 (C16 to C34)                   | µg/g | 240  | <50         | <50         | <50        | <50        | <50        | <50        | <50        | <50        | <50        |
| F3 (C16 to C34) minus PAHs        | µg/g | --   | <50         | <50         | <50        | <50        | <50        | <50        | <50        | <50        | <50        |
| F4 (C34 to C50)                   | µg/g | 120  | <50         | <50         | <50        | <50        | <50        | <50        | <50        | <50        | <50        |
| Reached Baseline at C50           | --   | --   | Yes         | Yes         | Yes        | Yes        | Yes        | Yes        | Yes        | Yes        | Yes        |
| Gravimetric Heavy Hydrocarbons    | µg/g | --   | NA          | NA          | NA         | NA         | NA         | NA         | NA         | NA         | NA         |
| Moisture Content                  | %    | --   | 7.50        | 7.70        | 11.4       | 13.2       | 26.6       | 5.9        | 11.4       | 8.8        | 8.2        |

| Sample Location                   | Unit | MECP Table 1 Standard (R/P/I/I/C/C) <sup>(1)</sup> | TP61              | TP62              | TP126-1           | TP126-2           | BHMW14            | BHM15                     |
|-----------------------------------|------|--|-------------------|-------------------|-------------------|-------------------|-------------------|---------------------------|
| Sample ID                         |      |  | TP61 SGS1         | TP62 SGS1         | TP126-1 S1        | TP126-2 S1        | BHMW14 SS2        | BHMW15 SS5 <sup>(2)</sup> |
| Date Sampled                      |      |  | -- <sup>(4)</sup> | -- <sup>(4)</sup> | -- <sup>(4)</sup> | -- <sup>(4)</sup> | -- <sup>(4)</sup> | -- <sup>(4)</sup>         |
| Sample Depth (mbgs)               | mbgs |  | 0.1-0.4           | 0.6-0.9           | 0.0-0.8           | 0.0-0.8           | 0.6-1.0           | 2.4-3.0                   |
| Parameter                         |      |  |                   |                   |                   |                   |                   |                           |
| Benzene                           | µg/g | 0.02   | --                | --                | <0.001            | <0.001            | <0.05             | <0.05                     |
| Toluene                           | µg/g | 0.20   | --                | --                | <0.002            | <0.002            | <0.05             | <0.05                     |
| Ethylbenzene                      | µg/g | 0.05   | --                | --                | <0.002            | <0.002            | <0.05             | <0.05                     |
| o-Xylene                          | µg/g | --   | --                | --                | <0.002            | <0.002            | <0.05             | <0.05                     |
| p+m-Xylene                        | µg/g | --   | --                | --                | <0.002            | <0.002            | <0.1              | <0.1                      |
| Xylenes (Total)                   | µg/g | 0.05   | --                | --                | <0.002            | <0.002            | <0.15             | --                        |
| F1 (C6 to C10)                    | µg/g | 25   | <20               | <20               | --                | --                | <20               | 40                        |
| F1 (C6 to C10) minus BTEX         | µg/g | 25   | --                | --                | --                | --                | --                | --                        |
| F2 (C10 to C16)                   | µg/g | 10   | 4000              | 2500              | --                | --                | <10               | 2,200                     |
| F2 (C10 to C16) minus Naphthalene | µg/g | 10   | --                | --                | --                | --                | --                | --                        |
| F3 (C16 to C34)                   | µg/g | 240  | 13000             | 23000             | --                | --                | <10               | 930                       |
| F3 (C16 to C34) minus PAHs        | µg/g | --   | --                | --                | --                | --                | --                | --                        |
| F4 (C34 to C50)                   | µg/g | 120  | 18000             | 15000             | --                | --                | <10               | <10                       |
| Reached Baseline at C50           | --   | --   | --                | --                | --                | --                | --                | Yes                       |
| Gravimetric Heavy Hydrocarbons    | µg/g | --   | --                | --                | --                | --                | --                | --                        |
| Moisture Content                  | %    | --   | --                | --                | --                | --                | --                | --                        |

**Notes:**

G / S     Guideline / Standard  
 --        Not analyzed

|              |  |
|--------------|--|
| <b>Value</b> | Parameters exceeds Table 1 criteria.   |
| <u>Value</u> | RDL exceeds Table 1 criteria   |
|              | Sample location has been excavated and removed from site.  |
| (1)          | Ontario Reg 153/04 (2011) Table 1: Full Depth Background Site Condition Standards, Residential/Parkland/Institutional/Industrial/Commercial/Community Property Use for Soil. |
| (2)          | Off-site sample location included for reference purposes only  |
| (3)          | Location of sample not provided in source report   |
| (4)          | No date was provided in the source report.   |

| Sample Location               | Unit | MECP Table 1 Standard (R/P/I/I/C/C) <sup>(1)</sup> | TP22-01                    |                            |                            | TP22-02     |             |             |
|-------------------------------|------|--|----------------------------|----------------------------|----------------------------|-------------|-------------|-------------|
| Sample ID                     |      |  | TP22-01 SA1 <sup>(3)</sup> | TP22-01 SA2 <sup>(3)</sup> | TP22-01 SA3 <sup>(3)</sup> | TP22-02 SA1 | TP22-02 SA2 | TP22-02 SA3 |
| Date Sampled                  |      |  | 10/19/2022                 | 10/19/2022                 | 10/19/2022                 | 10/19/2022  | 10/19/2022  | 10/19/2022  |
| Sample Depth (mbgs)           | mbgs |  | 0.3-1.5                    | 1.5-3.2                    | 3.2-3.6                    | 0.1-2.1     | 2.25-2.75   | 3.75-4.2    |
| Parameter                     |      |  |                            |                            |                            |             |             |             |
| Acenaphthene                  | µg/g | 0.072  | 0.0051                     | ND                         | ND                         | 0.043       | 0.016       | ND          |
| Acenaphthylene                | µg/g | 0.093  | 0.005                      | ND                         | ND                         | 0.024       | 0.008       | ND          |
| Anthracene                    | µg/g | 0.16   | 0.014                      | ND                         | 0.075                      | 0.14        | 0.042       | ND          |
| Benz(a)anthracene             | µg/g | 0.36   | 0.056                      | 0.0079                     | 0.25                       | <b>0.39</b> | 0.11        | 0.012       |
| Benzo(a)pyrene                | µg/g | 0.3  | 0.047                      | 0.0069                     | 0.22                       | <b>0.32</b> | 0.086       | 0.011       |
| Benzo(b)fluoranthene          | µg/g | 0.47   | 0.067                      | 0.0092                     | 0.29                       | 0.4         | 0.12        | 0.017       |
| Benzo(g,h,i)perylene          | µg/g | 0.68   | 0.028                      | ND                         | 0.12                       | 0.16        | 0.045       | 0.0075      |
| Benzo(k)fluoranthene          | µg/g | 0.48   | 0.021                      | ND                         | 0.11                       | 0.15        | 0.037       | 0.0058      |
| Chrysene                      | µg/g | 2.8  | 0.045                      | 0.0065                     | 0.22                       | 0.32        | 0.091       | 0.011       |
| Dibenz(a,h)anthracene         | µg/g | 0.1  | 0.0064                     | ND                         | ND                         | 0.036       | 0.011       | ND          |
| Fluoranthene                  | µg/g | 0.56   | 0.12                       | 0.017                      | 0.48                       | <b>0.85</b> | 0.24        | 0.026       |
| Fluorene                      | µg/g | 0.12   | 0.0063                     | ND                         | ND                         | 0.083       | 0.026       | ND          |
| Indeno(1,2,3-cd)pyrene        | µg/g | 0.23   | 0.028                      | ND                         | 0.12                       | 0.16        | 0.048       | 0.0075      |
| 1 Methlynaphthalene           | µg/g | 0.59 <sup>(2)</sup>                                | ND                         | ND                         | ND                         | 0.015       | ND          | ND          |
| 2 Methlynaphthalene           | µg/g | 0.59 <sup>(2)</sup>                                | ND                         | ND                         | ND                         | 0.02        | 0.0059      | ND          |
| 1 and 2 Methlynaphthalene (2) | µg/g | 0.59   | --                         | --                         | --                         | --          | --          | --          |
| Naphthalene                   | µg/g | 0.09   | ND                         | ND                         | ND                         | 0.058       | 0.015       | ND          |
| Phenanthrene                  | µg/g | 0.69   | 0.056                      | 0.0093                     | 0.29                       | 0.61        | 0.17        | 0.015       |
| Pyrene                        | µg/g | 1  | 0.096                      | 0.015                      | 0.38                       | 0.66        | 0.19        | 0.022       |

| Sample Location               | Unit | MECP Table 1 Standard (R/P/I/I/C/C) <sup>(1)</sup> | TP22-03     |             | TP22-04     |              |             | TP22-05     |             |             |
|-------------------------------|------|--|-------------|-------------|-------------|--------------|-------------|-------------|-------------|-------------|
| Sample ID                     |      |  | TP22-03 SA1 | TP22-03 SA2 | TP22-04 SA1 | TP22-04 SA2  | TP22-04 SA3 | TP22-05 SA1 | TP22-05 SA2 | TP22-05 SA3 |
| Date Sampled                  |      |  | 10/19/2022  | 10/19/2022  | 10/19/2022  | 10/19/2022   | 10/19/2022  | 10/19/2022  | 10/19/2022  | 10/19/2022  |
| Sample Depth (mbgs)           | mbgs |  | 0.1-0.4     | 0.4-1.1     | 1.5-1.7     | 2.7-3.0      | 3.7-4.0     | 0.9-1.2     | 2.3-2.5     | 3.8-4.0     |
| Parameter                     |      |  |             |             |             |              |             |             |             |             |
| Acenaphthene                  | µg/g | 0.072  | ND          | ND          | 0.0069      | <b>0.074</b> | 0.0062      | ND          | ND          | ND          |
| Acenaphthylene                | µg/g | 0.093  | ND          | ND          | 0.013       | ND           | 0.0051      | ND          | ND          | ND          |
| Anthracene                    | µg/g | 0.16   | ND          | ND          | 0.026       | <b>0.19</b>  | 0.021       | 0.014       | ND          | ND          |
| Benz(a)anthracene             | µg/g | 0.36   | 0.006       | ND          | 0.069       | <b>0.66</b>  | 0.1         | 0.037       | ND          | 0.007       |
| Benzo(a)pyrene                | µg/g | 0.3  | 0.0061      | ND          | 0.06        | <b>0.58</b>  | 0.085       | 0.03        | ND          | 0.0067      |
| Benzo(b)fluoranthene          | µg/g | 0.47   | 0.0091      | 0.0058      | 0.078       | <b>0.78</b>  | 0.12        | 0.041       | ND          | 0.0085      |
| Benzo(g,h,i)perylene          | µg/g | 0.68   | ND          | ND          | 0.031       | 0.29         | 0.043       | 0.018       | ND          | ND          |
| Benzo(k)fluoranthene          | µg/g | 0.48   | ND          | ND          | 0.024       | 0.29         | 0.036       | 0.013       | ND          | ND          |
| Chrysene                      | µg/g | 2.8  | 0.0056      | ND          | 0.055       | 0.56         | 0.082       | 0.03        | ND          | 0.0054      |
| Dibenz(a,h)anthracene         | µg/g | 0.1  | ND          | ND          | 0.0073      | 0.072        | 0.01        | ND          | ND          | ND          |
| Fluoranthene                  | µg/g | 0.56   | 0.013       | 0.0067      | 0.16        | <b>1.3</b>   | 0.19        | 0.082       | ND          | 0.014       |
| Fluorene                      | µg/g | 0.12   | ND          | ND          | 0.015       | 0.085        | 0.0088      | 0.0063      | ND          | ND          |
| Indeno(1,2,3-cd)pyrene        | µg/g | 0.23   | ND          | ND          | 0.033       | <b>0.3</b>   | 0.045       | 0.017       | ND          | ND          |
| 1 Methlynaphthalene           | µg/g | 0.59 <sup>(2)</sup>                                | ND          | ND          | ND          | ND           | ND          | ND          | ND          | ND          |
| 2 Methlynaphthalene           | µg/g | 0.59 <sup>(2)</sup>                                | ND          | ND          | ND          | ND           | ND          | ND          | ND          | ND          |
| 1 and 2 Methlynaphthalene (2) | µg/g | 0.59   | --          | --          | --          | --           | --          | --          | --          | --          |
| Naphthalene                   | µg/g | 0.09   | ND          | ND          | ND          | ND           | ND          | ND          | ND          | ND          |
| Phenanthrene                  | µg/g | 0.69   | 0.0051      | ND          | 0.1         | <b>0.74</b>  | 0.085       | 0.048       | ND          | 0.0057      |
| Pyrene                        | µg/g | 1  | 0.011       | 0.0057      | 0.12        | 1            | 0.15        | 0.066       | ND          | 0.013       |

| Sample Location               | Unit | MECP Table 1 Standard (R/P/I/I/C/C) <sup>(1)</sup> | TP22-06     |             |             | TP22-07     |             |             | BH22-02     |
|-------------------------------|------|--|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Sample ID                     |      |  | TP22-06 SA1 | TP22-06 SA2 | TP22-06 SA3 | TP22-07 SA1 | TP22-07 SA2 | TP22-07 SA3 | BH22-02 SA1 |
| Date Sampled                  |      |  | 10/19/2022  | 10/19/2022  | 10/19/2022  | 10/19/2022  | 10/19/2022  | 10/19/2022  | 07/11/2022  |
| Sample Depth (mbgs)           | mbgs |  | 0.6-1.7     | 1.7-3.1     | 3.1-3.8     | 0.8-1.0     | 2.0-2.3     | 3.5-3.8     | 0-1.4       |
| Parameter                     |      |  |             |             |             |             |             |             |             |
| Acenaphthene                  | µg/g | 0.072  | ND          | 0.0074      | 0.05        | ND          | ND          | ND          | <0.05       |
| Acenaphthylene                | µg/g | 0.093  | ND          | ND          | 0.056       | ND          | 0.0076      | ND          | <0.05       |
| Anthracene                    | µg/g | 0.16   | ND          | 0.016       | <b>0.18</b> | 0.0051      | 0.0061      | ND          | <0.05       |
| Benz(a)anthracene             | µg/g | 0.36   | 0.012       | 0.05        | <b>0.41</b> | 0.019       | 0.033       | ND          | <0.05       |
| Benzo(a)pyrene                | µg/g | 0.3  | 0.011       | 0.041       | <b>0.33</b> | 0.016       | 0.025       | ND          | 0.05        |
| Benzo(b)fluoranthene          | µg/g | 0.47   | 0.015       | 0.06        | 0.43        | 0.023       | 0.036       | ND          | 0.05        |
| Benzo(g,h,i)perylene          | µg/g | 0.68   | 0.0066      | 0.025       | 0.16        | 0.0086      | 0.013       | ND          | <0.05       |
| Benzo(k)fluoranthene          | µg/g | 0.48   | ND          | 0.018       | 0.14        | 0.0072      | 0.011       | ND          | <0.05       |
| Chrysene                      | µg/g | 2.8  | 0.011       | 0.038       | 0.3         | 0.016       | 0.025       | ND          | <0.05       |
| Dibenz(a,h)anthracene         | µg/g | 0.1  | ND          | 0.0055      | 0.039       | ND          | ND          | ND          | <0.05       |
| Fluoranthene                  | µg/g | 0.56   | 0.025       | 0.11        | <b>0.91</b> | 0.041       | 0.042       | ND          | 0.11        |
| Fluorene                      | µg/g | 0.12   | ND          | 0.0073      | 0.093       | ND          | ND          | ND          | <0.05       |
| Indeno(1,2,3-cd)pyrene        | µg/g | 0.23   | 0.0063      | 0.026       | 0.18        | 0.0091      | 0.014       | ND          | <0.05       |
| 1 Methlynaphthalene           | µg/g | 0.59 <sup>(2)</sup>                                | ND          | ND          | 0.016       | ND          | ND          | ND          | --          |
| 2 Methlynaphthalene           | µg/g | 0.59 <sup>(2)</sup>                                | ND          | ND          | 0.018       | ND          | ND          | ND          | --          |
| 1 and 2 Methlynaphthalene (2) | µg/g | 0.59   | --          | --          | --          | --          | --          | --          | <0.05       |
| Naphthalene                   | µg/g | 0.09   | ND          | ND          | 0.054       | ND          | ND          | ND          | <0.05       |
| Phenanthrene                  | µg/g | 0.69   | 0.012       | 0.054       | 0.55        | 0.021       | 0.013       | ND          | 0.07        |
| Pyrene                        | µg/g | 1  | 0.022       | 0.086       | 0.73        | 0.034       | 0.035       | ND          | 0.09        |

| Sample Location               | Unit | MECP Table 1 Standard (R/P/I/I/C/C) <sup>(1)</sup> | BH22-03     |             | BH22-04     |                                 |             | BH22-05     | BH22-06     |
|-------------------------------|------|--|-------------|-------------|-------------|---------------------------------|-------------|-------------|-------------|
| Sample ID                     |      |  | BH22-03 SA1 | BH22-03 SA2 | BH22-04 SA2 | BH22-04 DUP1 (field dup of SA2) | BH22-04 SA7 | BH22-05 SA2 | BH22-06 SA1 |
| Date Sampled                  |      |  | 07/12/2022  | 07/12/2022  | 07/11/2022  | 07/11/2022                      | 07/11/2022  | 07/13/2022  | 07/13/2022  |
| Sample Depth (mbgs)           | mbgs |  | 0-1.5       | 1.5-2.0     | 2.1-2.7     | 2.1-2.7                         | 7.50        | 0.3-0.6     | 0-1.2       |
| Parameter                     |      |  |             |             |             |                                 |             |             |             |
| Acenaphthene                  | µg/g | 0.072  | <0.05       | <0.05       | <0.05       | <0.05                           | <0.05       | <0.05       | <0.05       |
| Acenaphthylene                | µg/g | 0.093  | <0.05       | <0.05       | <0.05       | <0.05                           | <0.05       | <0.05       | <0.05       |
| Anthracene                    | µg/g | 0.16   | <0.05       | <b>0.23</b> | <0.05       | <b>0.19</b>                     | <0.05       | <0.05       | <0.05       |
| Benz(a)anthracene             | µg/g | 0.36   | <0.05       | <b>0.6</b>  | <0.05       | <b>0.64</b>                     | 0.08        | <0.05       | <0.05       |
| Benzo(a)pyrene                | µg/g | 0.3  | <0.05       | <b>0.43</b> | <0.05       | <b>0.46</b>                     | <0.05       | <0.05       | <0.05       |
| Benzo(b)fluoranthene          | µg/g | 0.47   | <0.05       | <b>0.9</b>  | <0.05       | <b>0.69</b>                     | <0.05       | <0.05       | <0.05       |
| Benzo(g,h,i)perylene          | µg/g | 0.68   | <0.05       | 0.20        | <0.05       | 0.15                            | <0.05       | <0.05       | <0.05       |
| Benzo(k)fluoranthene          | µg/g | 0.48   | <0.05       | 0.39        | <0.05       | 0.38                            | <0.05       | <0.05       | <0.05       |
| Chrysene                      | µg/g | 2.8  | <0.05       | 0.58        | <0.05       | 0.51                            | 0.09        | <0.05       | <0.05       |
| Dibenz(a,h)anthracene         | µg/g | 0.1  | <0.05       | <0.05       | <0.05       | <0.05                           | <0.05       | <0.05       | <0.05       |
| Fluoranthene                  | µg/g | 0.56   | <0.05       | <b>1.47</b> | <0.05       | <b>1.19</b>                     | 0.23        | <0.05       | <0.05       |
| Fluorene                      | µg/g | 0.12   | <0.05       | <0.05       | <0.05       | <0.05                           | <0.05       | <0.05       | <0.05       |
| Indeno(1,2,3-cd)pyrene        | µg/g | 0.23   | <0.05       | 0.15        | <0.05       | 0.12                            | <0.05       | <0.05       | <0.05       |
| 1 Methlynaphthalene           | µg/g | 0.59 <sup>(2)</sup>                                | --          | --          | --          | --                              | --          | --          | --          |
| 2 Methlynaphthalene           | µg/g | 0.59 <sup>(2)</sup>                                | --          | --          | --          | --                              | --          | --          | --          |
| 1 and 2 Methlynaphthalene (2) | µg/g | 0.59   | <0.05       | <0.05       | <0.05       | <0.05                           | <0.05       | <0.05       | <0.05       |
| Naphthalene                   | µg/g | 0.09   | <0.05       | <0.05       | <0.05       | <0.05                           | <0.05       | <0.05       | <0.05       |
| Phenanthrene                  | µg/g | 0.69   | <0.05       | 0.67        | <0.05       | 0.51                            | 0.16        | <0.05       | <0.05       |
| Pyrene                        | µg/g | 1  | <0.05       | <b>1.24</b> | <0.05       | <b>1.06</b>                     | 0.19        | <0.05       | <0.05       |



| Sample Location               | Unit | MECP Table 1 Standard (R/P/I/I/C/C) <sup>(1)</sup> | TP4-01     | TP4-02     | TP4-10     | TP4-12     | TP4-13     | TP4-15     | TP4-16     |
|-------------------------------|------|--|------------|------------|------------|------------|------------|------------|------------|
| Sample ID                     |      |  | TP4-01 SA1 | TP4-02 SA1 | TP4-10 SA1 | TP4-12 SA1 | TP4-13 SA1 | TP4-15 SA1 | TP4-16 SA1 |
| Date Sampled                  |      |  | 07/07/2020 | 07/07/2020 | 07/07/2020 | 07/07/2020 | 07/07/2020 | 07/08/2020 | 07/08/2020 |
| Sample Depth (mbgs)           | mbgs |  | 0.3-0.5    | 0.75-1     | 1.75-2     | 0-0.5      | 0.0-0.65   | 0.3-0.5    | 0-1.2      |
| Parameter                     |      |  |            |            |            |            |            |            |            |
| Acenaphthene                  | µg/g | 0.072  | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Acenaphthylene                | µg/g | 0.093  | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Anthracene                    | µg/g | 0.16   | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Benz(a)anthracene             | µg/g | 0.36   | <0.05      | <0.05      | <0.05      | <0.05      | 0.05       | <0.05      | <0.05      |
| Benzo(a)pyrene                | µg/g | 0.3  | <0.05      | <0.05      | <0.05      | <0.05      | 0.05       | <0.05      | <0.05      |
| Benzo(b)fluoranthene          | µg/g | 0.47   | <0.05      | <0.05      | <0.05      | <0.05      | 0.06       | <0.05      | <0.05      |
| Benzo(g,h,i)perylene          | µg/g | 0.68   | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Benzo(k)fluoranthene          | µg/g | 0.48   | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Chrysene                      | µg/g | 2.8  | <0.05      | <0.05      | <0.05      | <0.05      | 0.07       | <0.05      | <0.05      |
| Dibenz(a,h)anthracene         | µg/g | 0.1  | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Fluoranthene                  | µg/g | 0.56   | <0.05      | <0.05      | 0.06       | <0.05      | 0.12       | <0.05      | <0.05      |
| Fluorene                      | µg/g | 0.12   | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Indeno(1,2,3-cd)pyrene        | µg/g | 0.23   | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| 1 Methlynaphthalene           | µg/g | 0.59 <sup>(2)</sup>                                | --         | --         | --         | --         | --         | --         | --         |
| 2 Methlynaphthalene           | µg/g | 0.59 <sup>(2)</sup>                                | --         | --         | --         | --         | --         | --         | --         |
| 1 and 2 Methlynaphthalene (2) | µg/g | 0.59   | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Naphthalene                   | µg/g | 0.09   | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Phenanthrene                  | µg/g | 0.69   | <0.05      | <0.05      | <0.05      | <0.05      | 0.05       | <0.05      | <0.05      |
| Pyrene                        | µg/g | 1  | <0.05      | <0.05      | 0.05       | <0.05      | 0.10       | <0.05      | <0.05      |

**Table 5b - Soil Analytical Results (PAHs)**

| Sample Location               | Unit | MECP Table 1 Standard (R/P/I/I/C/C) <sup>(1)</sup> | TP31                     |                          |                          | TP61              | TP62              | BHMW14            | BHMW15                    |
|-------------------------------|------|--|--------------------------|--------------------------|--------------------------|-------------------|-------------------|-------------------|---------------------------|
| Sample ID                     |      |  | TP31 SGS2 <sup>(3)</sup> | TP31 SGS3 <sup>(3)</sup> | TP31 SGS5 <sup>(3)</sup> | TP61 SGS1         | TP62 SGS1         | BHMW14 SS2        | BHMW15 SS5 <sup>(3)</sup> |
| Date Sampled                  |      |  | -- <sup>(6)</sup>        | -- <sup>(6)</sup>        | -- <sup>(6)</sup>        | -- <sup>(6)</sup> | -- <sup>(6)</sup> | -- <sup>(6)</sup> | -- <sup>(6)</sup>         |
| Sample Depth (mbgs)           | mbgs |  | <b>0.4</b>               | <b>0.9</b>               | <b>1.2</b>               | <b>0.1-0.4</b>    | <b>0.6-0.9</b>    | <b>0.6-1.0</b>    | <b>2.4-3.0</b>            |
| Parameter                     |      |  |                          |                          |                          |                   |                   |                   |                           |
| Acenaphthene                  | µg/g | 0.072  | <0.02                    | <0.02                    | <0.02                    | <0.01             | <1                | <0.02             | <b>0.24</b>               |
| Acenaphthylene                | µg/g | 0.093  | <0.02                    | <0.02                    | <0.02                    | <0.01             | <1                | <0.02             | <b>0.2</b>                |
| Anthracene                    | µg/g | 0.16   | <0.02                    | <0.02                    | <0.02                    | <0.01             | <1                | <0.02             | <0.02                     |
| Benz(a)anthracene             | µg/g | 0.36   | <0.02                    | <0.02                    | 0.1                      | <0.01             | <1                | <0.02             | <0.02                     |
| Benzo(a)pyrene                | µg/g | 0.3  | <0.02                    | <0.02                    | 0.08                     | <0.01             | <1                | <0.02             | <0.02                     |
| Benzo(b)fluoranthene          | µg/g | 0.47   | <0.02                    | <0.02                    | 0.08                     | <0.01             | <1                | <0.02             | <0.02                     |
| Benzo(g,h,i)perylene          | µg/g | 0.68   | <0.02                    | <0.02                    | 0.06                     | <0.01             | <1                | <0.02             | <0.02                     |
| Benzo(k)fluoranthene          | µg/g | 0.48   | <0.02                    | <0.02                    | 0.04                     | <0.01             | <1                | <0.02             | <0.02                     |
| Chrysene                      | µg/g | 2.8  | <0.02                    | <0.02                    | 0.1                      | <0.01             | <1                | <0.02             | <0.02                     |
| Dibenz(a,h)anthracene         | µg/g | 0.1  | <0.02                    | <0.02                    | <0.02                    | 0.02              | <1                | <0.02             | <0.02                     |
| Fluoranthene                  | µg/g | 0.56   | 0.02                     | <0.02                    | 0.24                     | <0.01             | <1                | <0.02             | <0.02                     |
| Fluorene                      | µg/g | 0.12   | <0.02                    | <0.02                    | <0.02                    | <0.01             | <1                | <0.02             | <b>0.18</b>               |
| Indeno(1,2,3-cd)pyrene        | µg/g | 0.23   | <0.02                    | <0.02                    | 0.06                     | 0.02              | <1                | <0.02             | <0.02                     |
| 1 Methlynaphthalene           | µg/g | 0.59 <sup>(2)</sup>                                | 0.02                     | <0.02                    | <0.02                    | <0.01             | <b>2</b>          | <0.02             | 0.1                       |
| 2 Methlynaphthalene           | µg/g | 0.59 <sup>(2)</sup>                                | 0.04                     | <0.02                    | <0.02                    | <0.01             | <b>2</b>          | <0.02             | 0.08                      |
| 1 and 2 Methlynaphthalene (2) | µg/g | 0.59   | 0.06                     | --                       | --                       | --                | <b>4</b>          | --                | --                        |
| Naphthalene                   | µg/g | 0.09   | 0.02                     | <0.02                    | <0.02                    | <0.01             | <1                | <0.02             | <b>1.2</b>                |
| Phenanthrene                  | µg/g | 0.69   | 0.02                     | <0.02                    | 0.14                     | 0.02              | <1                | <0.02             | <0.02                     |
| Pyrene                        | µg/g | 1  | 0.02                     | <0.02                    | 0.2                      | <0.01             | <1                | <0.02             | <0.02                     |

**Notes:**

G / S Guideline / Standard

-- Not analyzed

ND Not detected

**Value** Parameters exceeds Table 1 criteria.

Value RDL exceeds Table 1 criteria

Sample location has been excavated and removed from site.

(1) Ontario Reg 153/04 (2011) Table 1: Full Depth Background Site Condition Standards, Residential/Parkland/Institutional/Industrial/Commercial/Community Property Use for Soil.

(2) The methylnapthalene standards are applicable to both 1-methylnapthalene and 2-methylnapthalene, with the provision that if both are detected, the sum of the two must not exceed the standard.

(3) Off-site sample location included for reference purposes only

(4) Location of sample not provided in source report

(5) As noted in DST Remediation Report, exceedance remediated with confirmatory sample BLD 126-2 SS30 (2017 DST Remediation Report)

(6) No date was provided in the source report.

**Table 5c - Soil Analytical Results (Metals and Inorganics)**

| Sample Location               | Unit     | MECP Table 1 Standard (R/P/I/I/C/C) <sup>(1)</sup> | TP22-01                    |                            |                            | TP22-02     |             |             |
|-------------------------------|----------|--|----------------------------|----------------------------|----------------------------|-------------|-------------|-------------|
|                               |          |  | TP22-01 SA1 <sup>(2)</sup> | TP22-01 SA2 <sup>(2)</sup> | TP22-01 SA3 <sup>(2)</sup> | TP22-02 SA1 | TP22-02 SA2 | TP22-02 SA3 |
| Date Sampled                  |          |  | 10/19/2022                 | 10/19/2022                 | 10/19/2022                 | 10/19/2022  | 10/19/2022  | 10/19/2022  |
| Sample Depth (mbgs)           | mbgs     |  | 0.3-1.5                    | 1.5-3.2                    | 3.2-3.6                    | 0.1-2.1     | 2.25-2.75   | 3.75-4.2    |
| Antimony                      | µg/g     | 1.3  | <0.2                       | <0.2                       | <0.2                       | <0.2        | <0.2        | <0.2        |
| Arsenic                       | µg/g     | 18   | 1.5                        | 1.4                        | 1.9                        | 1.6         | 2.4         | 2.3         |
| Barium                        | µg/g     | 220  | 190                        | 200                        | 140                        | 180         | 220         | 80          |
| Beryllium                     | µg/g     | 2.5  | 0.62                       | 0.64                       | 0.5                        | 0.57        | 0.84        | 0.42        |
| Boron                         | µg/g     | 36   | 5.5                        | 6.2                        | 6.2                        | 6.5         | 7.4         | <5          |
| Boron (Hot Water Extractable) | µg/g     | --   | --                         | --                         | --                         | --          | --          | --          |
| Cadmium                       | µg/g     | 1.2  | 0.13                       | 0.14                       | 0.12                       | 0.12        | 0.1         | 0.12        |
| Calcium                       | µg/g     | --   | --                         | --                         | --                         | --          | --          | --          |
| Chromium (Total)              | µg/g     | 70   | 55                         | 62                         | 40                         | 55          | 55          | 25          |
| Cobalt                        | µg/g     | 21   | 15                         | 15                         | 11                         | 14          | 17          | 8.8         |
| Copper                        | µg/g     | 92   | 28                         | 31                         | 23                         | 29          | 31          | 18          |
| Iron                          | µg/g     | --   | --                         | --                         | --                         | --          | --          | --          |
| Lead                          | µg/g     | 120  | 10                         | 13                         | 12                         | 12          | 8.2         | 13          |
| Molybdenum                    | µg/g     | 2  | <0.5                       | 0.5                        | 0.63                       | 0.57        | <0.5        | 0.65        |
| Nickel                        | µg/g     | 82   | 33                         | 38                         | 27                         | 34          | 34          | 18          |
| Selenium                      | µg/g     | 1.5  | <0.5                       | <0.5                       | <0.5                       | <0.5        | <0.5        | <0.5        |
| Silver                        | µg/g     | 0.5  | 0.26                       | <0.2                       | <0.2                       | <0.2        | <0.2        | <0.2        |
| Sodium                        | µg/g     | NA   | --                         | --                         | --                         | --          | --          | --          |
| Thallium                      | µg/g     | 1  | 0.29                       | 0.3                        | 0.23                       | 0.29        | 0.32        | 0.17        |
| Uranium                       | µg/g     | 2.5  | 0.75                       | 0.7                        | 0.62                       | 0.72        | 0.63        | 0.55        |
| Vanadium                      | µg/g     | 86   | 61                         | 65                         | 48                         | 58          | 72          | 30          |
| Zinc                          | µg/g     | 290  | 87                         | 87                         | 56                         | 74          | 98          | 39          |
| Chromium, Hexavalent          | µg/g     | 70   | --                         | --                         | --                         | --          | --          | --          |
| Cyanide, Free                 | µg/g     | 0.051  | --                         | --                         | --                         | --          | --          | --          |
| Mercury                       | µg/g     | 0.27   | --                         | --                         | --                         | --          | --          | --          |
| Electrical Conductivity (2:1) | mS/cm    | 0.57   | --                         | --                         | --                         | --          | --          | --          |
| Sodium Adsorption Ratio       | NA       | --   | --                         | --                         | --                         | --          | --          | --          |
| pH, 2:1 CaCl2 Extraction      | pH Units | --   | --                         | --                         | --                         | --          | --          | --          |

| Sample Location               | Unit     | MECP Table 1 Standard (R/P/I/I/C/C) <sup>(1)</sup> | TP22-03     |             | TP22-04     |             |             | TP22-05     |             |             |
|-------------------------------|----------|--|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Check the master sheet        |          |  | TP22-03 SA1 | TP22-03 SA2 | TP22-04 SA1 | TP22-04 SA2 | TP22-04 SA3 | TP22-05 SA1 | TP22-05 SA2 | TP22-05 SA3 |
| Date Sampled                  |          |  | 10/19/2022  | 10/19/2022  | 10/19/2022  | 10/19/2022  | 10/19/2022  | 10/19/2022  | 10/19/2022  | 10/19/2022  |
| Sample Depth (mbgs)           | mbgs     |  | 0.1-0.4     | 0.4-1.1     | 1.5-1.7     | 2.7-3.0     | 3.7-4.0     | 0.9-1.2     | 2.3-2.5     | 3.8-4.0     |
| Antimony                      | µg/g     | 1.3  | <0.2        | <0.2        | <0.2        | <0.2        | <0.2        | <0.2        | <0.2        | <0.2        |
| Arsenic                       | µg/g     | 18   | 1.6         | 2           | 1.7         | 1.5         | 1.9         | 1.7         | 1.4         | <1          |
| Barium                        | µg/g     | 220  | 250         | 82          | 200         | 190         | 81          | 210         | 260         | 140         |
| Beryllium                     | µg/g     | 2.5  | 0.68        | 0.56        | 0.65        | 0.68        | 0.44        | 0.63        | 0.7         | 0.41        |
| Boron                         | µg/g     | 36   | <5          | <5          | 6.3         | 7.8         | <5          | 6.7         | 5.3         | <5          |
| Boron (Hot Water Extractable) | µg/g     | --   | --          | --          | --          | --          | --          | --          | --          | --          |
| Cadmium                       | µg/g     | 1.2  | 0.15        | 0.17        | 0.17        | <0.1        | 0.14        | 0.11        | <0.1        | <0.1        |
| Calcium                       | µg/g     | --   | --          | --          | --          | --          | --          | --          | --          | --          |
| Chromium (Total)              | µg/g     | 70   | 76          | 38          | 64          | 68          | 25          | 66          | 69          | 37          |
| Cobalt                        | µg/g     | 21   | 17          | 11          | 16          | 16          | 8           | 16          | 18          | 9.8         |
| Copper                        | µg/g     | 92   | 36          | 17          | 31          | 32          | 14          | 32          | 36          | 18          |
| Iron                          | µg/g     | --   | --          | --          | --          | --          | --          | --          | --          | --          |
| Lead                          | µg/g     | 120  | 10          | 12          | 12          | 9.6         | 11          | 11          | 7.1         | 5.6         |
| Molybdenum                    | µg/g     | 2  | 0.71        | 0.5         | 0.62        | 0.64        | <0.5        | 0.56        | 0.66        | 0.57        |
| Nickel                        | µg/g     | 82   | 44          | 25          | 39          | 41          | 17          | 40          | 40          | 21          |
| Selenium                      | µg/g     | 1.5  | <0.5        | <0.5        | <0.5        | <0.5        | <0.5        | <0.5        | <0.5        | <0.5        |
| Silver                        | µg/g     | 0.5  | <0.2        | <0.2        | <0.2        | <0.2        | <0.2        | <0.2        | <0.2        | <0.2        |
| Sodium                        | µg/g     | NA   | --          | --          | --          | --          | --          | --          | --          | --          |
| Thallium                      | µg/g     | 1  | 0.34        | 0.16        | 0.3         | 0.3         | 0.15        | 0.3         | 0.35        | 0.17        |
| Uranium                       | µg/g     | 2.5  | 0.77        | 0.59        | 0.73        | 0.79        | 0.57        | 0.79        | 0.89        | 0.67        |
| Vanadium                      | µg/g     | 86   | 76          | 36          | 67          | 69          | 31          | 65          | 85          | 46          |
| Zinc                          | µg/g     | 290  | 98          | 43          | 83          | 80          | 36          | 80          | 100         | 49          |
| Chromium, Hexavalent          | µg/g     | 70   | --          | --          | --          | --          | --          | --          | --          | --          |
| Cyanide, Free                 | µg/g     | 0.051  | --          | --          | --          | --          | --          | --          | --          | --          |
| Mercury                       | µg/g     | 0.27   | --          | --          | --          | --          | --          | --          | --          | --          |
| Electrical Conductivity (2:1) | mS/cm    | 0.57   | --          | --          | --          | --          | --          | --          | --          | --          |
| Sodium Adsorption Ratio       | NA       | --   | --          | --          | --          | --          | --          | --          | --          | --          |
| pH, 2:1 CaCl2 Extraction      | pH Units | --   | --          | --          | --          | --          | --          | --          | --          | --          |

**Table 5c - Soil Analytical Results (Metals and Inorganics)**

| Sample Location               | Unit     | MECP Table 1 Standard (R/P/I/I/C/C) <sup>(1)</sup> | TP22-06     |             |             | TP22-07     |             |             | BH22-02     |
|-------------------------------|----------|--|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
|                               |          |  | TP22-06 SA1 | TP22-06 SA2 | TP22-06 SA3 | TP22-07 SA1 | TP22-07 SA2 | TP22-07 SA3 | BH22-02 SA1 |
| Date Sampled                  |          |  | 10/19/2022  | 10/19/2022  | 10/19/2022  | 10/19/2022  | 10/19/2022  | 10/19/2022  | 07/11/2022  |
| Sample Depth (mbgs)           | mbgs     |  | 0.6-1.7     | 1.7-3.1     | 3.1-3.8     | 0.8-1.0     | 2.0-2.3     | 3.5-3.8     | 0-1.4       |
| Antimony                      | µg/g     | 1.3  | <0.2        | <0.2        | <0.2        | <0.2        | <0.2        | <0.2        | <0.8        |
| Arsenic                       | µg/g     | 18   | 1.3         | 1.7         | 1.5         | 1.2         | ND          | 2           | 3           |
| Barium                        | µg/g     | 220  | <b>260</b>  | 190         | 210         | <b>280</b>  | <b>260</b>  | 200         | 76.8        |
| Beryllium                     | µg/g     | 2.5  | 0.65        | 0.62        | 0.61        | 0.72        | 0.68        | 0.68        | 0.6         |
| Boron                         | µg/g     | 36   | <5          | 6.4         | 5.3         | 5.2         | <5          | 6.1         | 9           |
| Boron (Hot Water Extractable) | µg/g     | --   | --          | --          | --          | --          | --          | --          | 0.11        |
| Cadmium                       | µg/g     | 1.2  | 0.14        | 0.13        | 0.15        | 0.16        | 0.11        | <0.1        | <0.5        |
| Calcium                       | µg/g     | --   | --          | --          | --          | --          | --          | --          | --          |
| Chromium (Total)              | µg/g     | 70   | <b>75</b>   | 53          | 54          | <b>91</b>   | <b>81</b>   | 50          | 26          |
| Cobalt                        | µg/g     | 21   | 18          | 16          | 15          | 21          | 18          | 15          | 8.8         |
| Copper                        | µg/g     | 92   | 37          | 28          | 31          | 43          | 39          | 30          | 15.8        |
| Iron                          | µg/g     | --   | --          | --          | --          | --          | --          | --          | --          |
| Lead                          | µg/g     | 120  | 14          | 14          | 17          | 10          | 11          | 7.8         | 24          |
| Molybdenum                    | µg/g     | 2  | 0.6         | 0.81        | 0.71        | 0.56        | 0.67        | 0.59        | 0.6         |
| Nickel                        | µg/g     | 82   | 43          | 35          | 33          | 54          | 46          | 31          | 17          |
| Selenium                      | µg/g     | 1.5  | <0.5        | <0.5        | <0.5        | <0.5        | <0.5        | <0.5        | <0.8        |
| Silver                        | µg/g     | 0.5  | <0.2        | <0.2        | <0.2        | <0.2        | <0.2        | <0.2        | <0.5        |
| Sodium                        | µg/g     | NA   | --          | --          | --          | --          | --          | --          | --          |
| Thallium                      | µg/g     | 1  | 0.34        | 0.31        | 0.3         | 0.39        | 0.35        | 0.3         | <0.5        |
| Uranium                       | µg/g     | 2.5  | 0.89        | 0.73        | 0.79        | 0.93        | 0.9         | 0.85        | 0.55        |
| Vanadium                      | µg/g     | 86   | 81          | 58          | 67          | <b>90</b>   | 83          | 73          | 35          |
| Zinc                          | µg/g     | 290  | 110         | 75          | 90          | 120         | 100         | 93          | 34          |
| Chromium, Hexavalent          | µg/g     | 70   | --          | --          | --          | --          | --          | --          | <0.2        |
| Cyanide, Free                 | µg/g     | 0.051  | --          | --          | --          | --          | --          | --          | --          |
| Mercury                       | µg/g     | 0.27   | --          | --          | --          | --          | --          | --          | 0.14        |
| Electrical Conductivity (2:1) | mS/cm    | 0.57   | --          | --          | --          | --          | --          | --          | --          |
| Sodium Adsorption Ratio       | NA       | --   | --          | --          | --          | --          | --          | --          | --          |
| pH, 2:1 CaCl2 Extraction      | pH Units | --   | --          | --          | --          | --          | --          | --          | --          |

| Sample Location               | Unit     | MECP Table 1 Standard (R/P/I/I/C/C) <sup>(1)</sup> | BH22-03     |             | BH22-04     |                                 |             | BH22-05     |
|-------------------------------|----------|--|-------------|-------------|-------------|---------------------------------|-------------|-------------|
| Check the master sheet        |          |  | BH22-03 SA1 | BH22-03 SA2 | BH22-04 SA2 | BH22-04 DUP1 (field dup of SA2) | BH22-04 SA7 | BH22-05 SA2 |
| Date Sampled                  |          |  | 07/12/2022  | 07/12/2022  | 07/11/2022  | 07/11/2022                      | 07/11/2022  | 07/13/2022  |
| Sample Depth (mbgs)           | mbgs     |  | 0-1.5       | 1.5-2.0     | 2.1-2.7     | 2.1-2.7                         | 7-7.5       | 0.3-0.6     |
| Antimony                      | µg/g     | 1.3  | <0.8        | <0.8        | <0.8        | <0.8                            | <0.8        | <0.8        |
| Arsenic                       | µg/g     | 18   | 2           | 4           | 2           | 2                               | 2           | 3           |
| Barium                        | µg/g     | 220  | 239         | 106         | 221         | 106                             | 434         | 122         |
| Beryllium                     | µg/g     | 2.5  | 0.7         | 0.6         | 0.4         | 0.5                             | 0.9         | 0.4         |
| Boron                         | µg/g     | 36   | 8           | 9           | 5           | 22                              | 10          | 13          |
| Boron (Hot Water Extractable) | µg/g     | --   | 0.12        | 0.18        | 0.13        | 0.59                            | 1.1         | <0.1        |
| Cadmium                       | µg/g     | 1.2  | <0.5        | <0.5        | <0.5        | <0.5                            | <0.5        | <0.5        |
| Calcium                       | µg/g     | --   | --          | --          | --          | --                              | --          | --          |
| Chromium (Total)              | µg/g     | 70   | 59          | 28          | 58          | 29                              | 118         | 25          |
| Cobalt                        | µg/g     | 21   | 14.3        | 10.1        | 14          | 11.8                            | 27.1        | 8.6         |
| Copper                        | µg/g     | 92   | 30          | 18.7        | 30.1        | 19.1                            | 57.2        | 12.8        |
| Iron                          | µg/g     | --   | --          | --          | --          | --                              | --          | --          |
| Lead                          | µg/g     | 120  | 12          | 17          | 10          | 14                              | 8           | 10          |
| Molybdenum                    | µg/g     | 2  | 0.6         | 0.9         | 0.8         | 0.7                             | 1.2         | 0.5         |
| Nickel                        | µg/g     | 82   | 35          | 21          | 35          | 25                              | 75          | 18          |
| Selenium                      | µg/g     | 1.5  | <0.8        | <0.8        | <0.8        | <0.8                            | <0.8        | <0.8        |
| Silver                        | µg/g     | 0.5  | <0.5        | <0.5        | <0.5        | <0.5                            | <0.5        | <0.5        |
| Sodium                        | µg/g     | NA   | --          | --          | --          | --                              | --          | --          |
| Thallium                      | µg/g     | 1  | <0.5        | <0.5        | <0.5        | <0.5                            | 0.5         | <0.5        |
| Uranium                       | µg/g     | 2.5  | 0.67        | 0.53        | 0.75        | 0.52                            | 2.27        | 0.55        |
| Vanadium                      | µg/g     | 86   | 66.2        | 32.7        | 61.2        | 32.3                            | 125         | 29.3        |
| Zinc                          | µg/g     | 290  | 81          | 48          | 75          | 35                              | 152         | 43          |
| Chromium, Hexavalent          | µg/g     | 70   | <0.2        | <0.2        | <0.2        | <0.2                            | <0.2        | <0.2        |
| Cyanide, Free                 | µg/g     | 0.051  | --          | --          | --          | --                              | --          | --          |
| Mercury                       | µg/g     | 0.27   | 0.2         | 0.14        | 0.14        | 0.22                            | 0.1         | <0.1        |
| Electrical Conductivity (2:1) | mS/cm    | 0.57   | --          | --          | --          | --                              | --          | --          |
| Sodium Adsorption Ratio       | NA       | --   | --          | --          | --          | --                              | --          | --          |
| pH, 2:1 CaCl2 Extraction      | pH Units | --   | --          | --          | --          | --                              | --          | --          |

| Sample Location               | Unit     | MECP Table 1 Standard (R/P/I/I/C/C) <sup>(1)</sup> | BH22-06     | TP4-01     | TP4-02     | TP4-10     | TP4-12     | TP4-13     | TP4-15     | TP4-16     |
|-------------------------------|----------|--|-------------|------------|------------|------------|------------|------------|------------|------------|
| Check the master sheet        |          |  | BH22-06 SA1 | TP4-01 SA1 | TP4-02 SA1 | TP4-10 SA1 | TP4-12 SA1 | TP4-13 SA1 | TP4-15 SA1 | TP4-16 SA1 |
| Date Sampled                  |          |  | 07/13/2022  | 07/07/2020 | 07/07/2020 | 07/07/2020 | 07/07/2020 | 07/07/2020 | 07/07/2020 | 07/08/2020 |
| Sample Depth (mbgs)           | mbgs     |  | 0-1.2       | 0.3-0.5    | 0.75-1     | 1.75-2     | 0-0.5      | 0.0-0.65   | 0.3-0.5    | 0-1.2      |
| Antimony                      | µg/g     | 1.3  | <0.8        | 1.10       | <0.8       | <0.8       | <0.8       | <0.8       | <0.8       | <0.8       |
| Arsenic                       | µg/g     | 18   | 4           | 4          | 2          | 1          | 4          | 3          | 4          | 3          |
| Barium                        | µg/g     | 220  | 83.9        | 164        | 120        | 404        | 117        | 242        | 74         | 99         |
| Beryllium                     | µg/g     | 2.5  | 0.4         | 0.5        | <0.5       | 0.5        | 0.5        | <0.5       | <0.5       | <0.5       |
| Boron                         | µg/g     | 36   | 13          | 12         | 5          | <5         | 9          | <5         | 7          | 14         |
| Boron (Hot Water Extractable) | µg/g     | --   | <0.1        | 0.17       | 0.27       | 0.17       | 0.35       | 0.26       | 0.27       | 0.14       |
| Cadmium                       | µg/g     | 1.2  | <0.5        | <0.5       | <0.5       | <0.5       | <0.5       | <0.5       | <0.5       | <0.5       |
| Calcium                       | µg/g     | --   | --          | --         | --         | --         | --         | --         | --         | --         |
| Chromium (Total)              | µg/g     | 70   | 20          | 23         | 29         | 111        | 23         | 59         | 18         | 18         |
| Cobalt                        | µg/g     | 21   | 7.9         | 7          | 9          | 21         | 9          | 12         | 8          | 7          |
| Copper                        | µg/g     | 92   | 12.1        | 34         | 15         | 38         | 30         | 38         | 18         | 13         |
| Iron                          | µg/g     | --   | --          | --         | --         | --         | --         | --         | --         | --         |
| Lead                          | µg/g     | 120  | 28          | 67         | 10         | 10         | 38         | 24         | 87         | 10         |
| Molybdenum                    | µg/g     | 2  | 0.6         | 1.3        | <0.5       | <0.5       | 0.8        | 1.1        | 1.0        | <0.5       |
| Nickel                        | µg/g     | 82   | 14          | 17         | 17         | 52         | 16         | 31         | 15         | 11         |
| Selenium                      | µg/g     | 1.5  | <0.8        | 0.6        | <0.4       | 0.6        | 0.7        | 0.6        | 0.4        | 0.4        |
| Silver                        | µg/g     | 0.5  | <0.5        | 0.20       | <0.2       | <0.2       | <0.2       | <0.2       | <0.2       | <0.2       |
| Sodium                        | µg/g     | NA   | --          | --         | --         | --         | --         | --         | --         | --         |
| Thallium                      | µg/g     | 1  | <0.5        | <0.4       | <0.4       | 0.50       | <0.4       | <0.4       | <0.4       | <0.4       |
| Uranium                       | µg/g     | 2.5  | 0.51        | 0.8        | 0.7        | 1.3        | 0.5        | 0.9        | <0.5       | <0.5       |
| Vanadium                      | µg/g     | 86   | 25.2        | 27         | 38         | 100        | 28         | 56         | 26         | 20         |
| Zinc                          | µg/g     | 290  | 61          | 154        | 45         | 159        | 45         | 106        | 79         | 24         |
| Chromium, Hexavalent          | µg/g     | 70   | <0.2        | <0.2       | <0.2       | <0.2       | <0.2       | <0.2       | <0.2       | <0.2       |
| Cyanide, Free                 | µg/g     | 0.051  | --          | --         | --         | --         | --         | --         | --         | --         |
| Mercury                       | µg/g     | 0.27   | 0.11        | 0.13       | <0.1       | <0.1       | <0.1       | <0.1       | <0.1       | <0.1       |
| Electrical Conductivity (2:1) | mS/cm    | 0.57   | --          | --         | --         | --         | --         | --         | --         | --         |
| Sodium Adsorption Ratio       | NA       | --   | --          | --         | --         | --         | --         | --         | --         | --         |
| pH, 2:1 CaCl2 Extraction      | pH Units | --   | --          | --         | --         | --         | --         | --         | 7.54       | 7.28       |



| Sample Location               | Unit     | MECP Table 1 Standard (R/P/I/I/C/C) <sup>(1)</sup> | TP61              | TP62              | TP126-1           | TP126-2           | BHMW14            | BHMW15                    | TP31              |                   |                   |
|-------------------------------|----------|--|-------------------|-------------------|-------------------|-------------------|-------------------|---------------------------|-------------------|-------------------|-------------------|
| Check the master sheet        |          |  | TP61 SGS1         | TP62 SGS1         | TP126-1 S1        | TP126-2 S1        | BHMW14 SS2        | BHMW15 SS5 <sup>(2)</sup> | TP31 SGS2         | TP31 SGS3         | TP31 SGS5         |
| Date Sampled                  |          |  | -- <sup>(3)</sup> | -- <sup>(3)</sup> | -- <sup>(3)</sup> | -- <sup>(3)</sup> | -- <sup>(3)</sup> | -- <sup>(3)</sup>         | -- <sup>(3)</sup> | -- <sup>(2)</sup> | -- <sup>(2)</sup> |
| Sample Depth (mbgs)           | mbgs     |  | 0.1-0.4           | 0.6-0.9           | 0.0-0.8           | 0.0-0.8           | 0.6-1.0           | 2.4-3.0                   | 0.40              | 0.90              | 1.20              |
| Antimony                      | µg/g     | 1.3  | <1                | <1                | <0.8              | <0.8              | <1                | <1                        | <1                | <1                | <1                |
| Arsenic                       | µg/g     | 18   | 2                 | 1                 | 3.7               | 2.9               | 1                 | <1                        | 1                 | <1                | <1                |
| Barium                        | µg/g     | 220  | 20                | <10               | 123               | 88.9              | 130               | 330                       | 70                | 20                | 30                |
| Beryllium                     | µg/g     | 2.5  | <0.5              | <0.5              | 0.5               | 0.7               | <0.5              | 0.5                       | <0.5              | <0.5              | <0.5              |
| Boron                         | µg/g     | 36   | --                | --                | --                | --                | --                | --                        | --                | --                | --                |
| Boron (Hot Water Extractable) | µg/g     | --   | --                | --                | --                | --                | --                | --                        | --                | --                | --                |
| Cadmium                       | µg/g     | 1.2  | <0.5              | <0.5              | 0.7               | <0.2              | <0.5              | <0.5                      | <0.5              | <0.5              | <0.5              |
| Calcium                       | µg/g     | --   | 2400              | 600               | --                | --                | 4600              | 39,000                    | 7200              | 4000              | 7000              |
| Chromium (Total)              | µg/g     | 70   | 5                 | <5                | 39.2              | 24.1              | 25                | 70                        | 15                | <5                | 5                 |
| Cobalt                        | µg/g     | 21   | 5                 | 5                 | 9.6               | 9.2               | 10                | 15                        | 5                 | <5                | <5                |
| Copper                        | µg/g     | 92   | <5                | <5                | 29.1              | 18.9              | 15                | 35                        | 15                | 10                | 10                |
| Iron                          | µg/g     | --   | 3800              | 800               | --                | --                | 22000             | 35,000                    | 13000             | 6800              | 7800              |
| Lead                          | µg/g     | 120  | 4                 | <1                | 23.1              | 13.5              | 14                | 12                        | 22                | 2                 | 10                |
| Molybdenum                    | µg/g     | 2  | 1                 | <1                | 0.5               | 0.5               | <1                | <1                        | <1                | <1                | <1                |
| Nickel                        | µg/g     | 82   | 40                | 35                | 31.4              | 20.6              | 20                | 40                        | 15                | <5                | 5                 |
| Selenium                      | µg/g     | 1.5  | <1                | <1                | <0.4              | <0.4              | <1                | <1                        | <1                | <1                | <1                |
| Silver                        | µg/g     | 0.5  | <0.3              | <0.3              | <0.2              | <0.2              | <0.3              | <0.3                      | <0.3              | <0.3              | <0.3              |
| Sodium                        | µg/g     | NA   | <200              | <200              | --                | --                | <200              | 1,200                     | <200              | <200              | <200              |
| Thallium                      | µg/g     | 1  | <1                | <1                | 0.2               | 0.2               | <1                | <1                        | <1                | <1                | <1                |
| Uranium                       | µg/g     | 2.5  | --                | --                | --                | --                | --                | --                        | --                | --                | --                |
| Vanadium                      | µg/g     | 86   | <10               | <10               | 49.7              | 27.4              | 30                | 70                        | 20                | 10                | 10                |
| Zinc                          | µg/g     | 290  | <20               | <20               | 81.8              | 33.1              | 20                | 80                        | 520               | <20               | 460               |
| Chromium, Hexavalent          | µg/g     | 70   | --                | --                | --                | --                | --                | --                        | --                | --                | --                |
| Cyanide, Free                 | µg/g     | 0.051  | --                | --                | --                | --                | --                | --                        | --                | --                | --                |
| Mercury                       | µg/g     | 0.27   | --                | --                | --                | --                | --                | --                        | --                | --                | --                |
| Electrical Conductivity (2:1) | mS/cm    | 0.57   | --                | --                | --                | --                | --                | --                        | --                | --                | --                |
| Sodium Adsorption Ratio       | NA       | --   | --                | --                | --                | --                | --                | --                        | --                | --                | --                |
| pH, 2:1 CaCl2 Extraction      | pH Units | --   | --                | --                | --                | --                | --                | --                        | --                | --                | --                |

**Notes:**

G / S      Guideline / Standard  
 --          Not analyzed

- Value**      Parameters exceeds Table 1 criteria.
- Value      RDL exceeds Table 1 criteria
- Sample location has been excavated and removed from site.
- Exceedance interpreted to be naturally occurring
- (1)            Ontario Reg 153/04 (2011) Table 1: Full Depth Background Site Condition Standards, Residential/Parkland/Institutional/Industrial/Commercial/Community Property Use for Soil.
- (2)            Off-site sample location included for reference purposes only
- (3)            No date was provided in the source report.

| Sample Description<br>Date Sampled | Unit | MECP Table 1<br>Standard (1) | 22-02      | 22-04      | DUP-01<br>(dup of 22-04) | 22-05      | 22-06      | Trip Blank | Field Blank |
|------------------------------------|------|------------------------------|------------|------------|--------------------------|------------|------------|------------|-------------|
|                                    |      |                              | 07/18/2022 | 07/18/2022 | 07/18/2022               | 07/18/2022 | 07/18/2022 | 07/18/2022 | 07/18/2022  |
| Benzene                            | µg/L | 0.5                          | <0.20      | <0.20      | <0.20                    | <0.20      | <0.20      | <0.20      | <0.20       |
| Toluene                            | µg/L | 0.8                          | <0.20      | <0.20      | <0.20                    | 0.23       | 0.20       | <0.20      | <0.20       |
| Ethylbenzene                       | µg/L | 0.5                          | <0.10      | <0.10      | <0.10                    | <0.10      | <0.10      | <0.10      | <0.10       |
| Xylenes (Total)                    | µg/L | 72                           | <0.20      | <0.20      | <0.20                    | <0.20      | <0.20      | <0.20      | <0.20       |
| F1 (C6 - C10)                      | µg/L | 420                          | <25        | <25        | <25                      | <25        | <25        | <25        | <25         |
| F1 (C6 to C10) minus BTEX          | µg/L | 420                          | <25        | <25        | <25                      | <25        | <25        | <25        | <25         |
| F2 (C10 to C16)                    | µg/L | 150                          | <100       | <100       | <100                     | <100       | <100       | <100       | <100        |
| F3 (C16 to C34)                    | µg/L | 500                          | <100       | <100       | <100                     | <100       | <100       | <100       | <100        |
| F4 (C34 to C50)                    | µg/L | 500                          | <100       | <100       | <100                     | <100       | <100       | <100       | <100        |
| Gravimetric Heavy Hydrocarbons     | µg/L |                              |            |            |                          |            |            |            |             |

| Sample Description<br>Date Sampled | Unit | MECP Table 1<br>Standard (1) | Equipment<br>Blank | BHMW14     | BHMW14     | BHMW14       | BHMW126-1  | BHMW126-1  | 22-01 <sup>(2)</sup> |
|------------------------------------|------|------------------------------|--------------------|------------|------------|--------------|------------|------------|----------------------|
|                                    |      |                              | 07/18/2022         | 03/20/2016 | 03/31/2015 | 3/19-20/2014 | 03/20/2016 | 03/31/2015 | 07/18/2022           |
| Benzene                            | µg/L | 0.5                          | <0.20              | <0.20      | <0.20      | <0.20        | <0.20      | <0.20      | <0.20                |
| Toluene                            | µg/L | 0.8                          | <0.20              | <0.20      | <0.20      | <0.20        | <0.20      | <0.20      | 0.26                 |
| Ethylbenzene                       | µg/L | 0.5                          | <0.10              | <0.20      | <0.20      | <0.20        | <0.20      | <0.20      | <0.10                |
| Xylenes (Total)                    | µg/L | 72                           | <0.20              | <0.40      | <0.40      | <0.40        | <0.40      | <0.40      | <0.20                |
| F1 (C6 - C10)                      | µg/L | 420                          | <25                | <25        | <25        | <25          | <25        | <25        | <25                  |
| F1 (C6 to C10) minus BTEX          | µg/L | 420                          | <25                | <25        | <25        | <25          | <25        | <25        | <25                  |
| F2 (C10 to C16)                    | µg/L | 150                          | <100               | <100       | <100       | <100         | <100       | <100       | <100                 |
| F3 (C16 to C34)                    | µg/L | 500                          | <100               | <200       | <200       | <200         | <200       | <200       | <100                 |
| F4 (C34 to C50)                    | µg/L | 500                          | <100               | <200       | <200       | <200         | <200       | <200       | <100                 |
| Gravimetric Heavy Hydrocarbons     | µg/L |                              |                    | NA         | NA         |              | NA         | NA         |                      |

| Sample Description<br>Date Sampled | Unit | MECP Table 1<br>Standard (1) | DUP 01<br>(dup of 22-01) <sup>(2)</sup> | 137-3 <sup>(2)</sup> | 137-1 <sup>(2)</sup> | 14-01 <sup>(2)</sup> | 14-02 <sup>(2)</sup> | BHMW15 <sup>(2)</sup> |
|------------------------------------|------|------------------------------|---|----------------------|----------------------|----------------------|----------------------|-----------------------|
|                                    |      |                              | 07/18/2022                              | 07/22/2022           | 08/05/2021           | 09/09/2020           | 08/05/2020           | 3/20/2014             |
| Benzene                            | µg/L | 0.5                          | <0.20                                   | <0.20                | <0.20                | <0.20                | <0.20                | <0.20                 |
| Toluene                            | µg/L | 0.8                          | <0.20                                   | <0.20                | <0.20                | <0.20                | <0.20                | <0.20                 |
| Ethylbenzene                       | µg/L | 0.5                          | <0.10                                   | <0.10                | <0.10                | <0.10                | <0.10                | <0.20                 |
| Xylenes (Total)                    | µg/L | 72                           | <0.20                                   | <0.20                | <0.20                | <0.20                | <0.20                | <0.40                 |
| F1 (C6 - C10)                      | µg/L | 420                          | <25                                     | <25                  | <25                  | <25                  | <25                  | <25                   |
| F1 (C6 to C10) minus BTEX          | µg/L | 420                          | <25                                     | <25                  | <25                  | <25                  | <25                  | <25                   |
| F2 (C10 to C16)                    | µg/L | 150                          | <100                                    | <b>940</b>           | <100                 | <100                 | <100                 | <b>15,000</b>         |
| F3 (C16 to C34)                    | µg/L | 500                          | <100                                    | <b>1,000</b>         | <100                 | <100                 | <100                 | <b>8,200</b>          |
| F4 (C34 to C50)                    | µg/L | 500                          | <100                                    | <100                 | <100                 | <100                 | <100                 | <200                  |
| Gravimetric Heavy Hydrocarbons     | µg/L |                              |   |                      | NA                   | NA                   | NA                   |                       |

**Notes:**

G / S      Guideline / Standard  
--          Not analyzed

- Value**      Parameters exceeds Table 1 criteria.
- Value      RDL exceeds Table 1 criteria
- Value**      Sample location has been excavated and removed from site.
- (1)          Ontario Reg 153/04 (2011) Table 1: Full Depth Background Site Condition Standards,  
Residential/Parkland/Institutional/Industrial/Commercial/Community Property Use for Groundwater
- (2)          Off-site sample location included for reference purposes only

| Sample Description<br>Date Sampled | Unit | MECP Table<br>1 Standard<br>(1) | 22-02      | 22-04      | DUP-01<br>(dup of 22-04) | 22-05      | 22-06      | Trip Blank | BHMW14     | BHMW14     |
|------------------------------------|------|---------------------------------|------------|------------|--------------------------|------------|------------|------------|------------|------------|
|                                    |      |                                 | 07/18/2022 | 07/18/2022 | 07/18/2022               | 07/18/2022 | 07/18/2022 | 07/18/2022 | 07/18/2022 | 03/20/2016 |
| Acenaphthene                       | µg/L | 4.1                             | <0.20      | <0.20      | <0.20                    | <0.20      | <0.20      | <0.20      | <0.050     | <0.050     |
| Acenaphthylene                     | µg/L | 1                               | <0.20      | <0.20      | <0.20                    | <0.20      | <0.20      | <0.20      | <0.050     | <0.050     |
| Anthracene                         | µg/L | 0.1                             | <0.10      | <0.10      | <0.10                    | <0.10      | <0.10      | <0.10      | <0.050     | <0.050     |
| Benzo(a)anthracene                 | µg/L | 0.2                             | <0.20      | <0.20      | <0.20                    | <0.20      | <0.20      | <0.20      | <0.050     | <0.050     |
| Benzo(a)pyrene                     | µg/L | 0.01                            | <0.01      | <0.01      | <0.01                    | <0.01      | <0.01      | <0.01      | <0.010     | <0.010     |
| Benzo(b/j)fluoranthene             | µg/L | 0.1                             | <0.10      | <0.10      | <0.10                    | <0.10      | <0.10      | <0.10      | <0.050     | <0.050     |
| Benzo(g,h,i)perylene               | µg/L | 0.2                             | <0.20      | <0.20      | <0.20                    | <0.20      | <0.20      | <0.20      | <0.050     | <0.050     |
| Benzo(k)fluoranthene               | µg/L | 0.1                             | <0.10      | <0.10      | <0.10                    | <0.10      | <0.10      | <0.10      | <0.050     | <0.050     |
| Chrysene                           | µg/L | 0.1                             | <0.10      | <0.10      | <0.10                    | <0.10      | <0.10      | <0.10      | <0.050     | <0.050     |
| Dibenz(a,h)anthracene              | µg/L | 0.2                             | <0.20      | <0.20      | <0.20                    | <0.20      | <0.20      | <0.20      | <0.050     | <0.050     |
| Fluoranthene                       | µg/L | 0.4                             | <0.20      | <0.20      | <0.20                    | <0.20      | <0.20      | <0.20      | <0.050     | <0.050     |
| Fluorene                           | µg/L | 120                             | <0.20      | <0.20      | <0.20                    | <0.20      | <0.20      | <0.20      | <0.050     | <0.050     |
| Indeno(1,2,3-cd)pyrene             | µg/L | 0.2                             | <0.20      | <0.20      | <0.20                    | <0.20      | <0.20      | <0.20      | <0.050     | <0.050     |
| 1-Methylnaphthalene                | µg/L | 2                               | --         | --         | --                       | --         | --         | --         | <0.050     | <0.050     |
| 2-Methylnaphthalene                | µg/L | 2                               | --         | --         | --                       | --         | --         | --         | <0.050     | <0.050     |
| Methylnaphthalene, 2-(1-)          | µg/L | 2                               | <0.20      | <0.20      | <0.20                    | <0.20      | <0.20      | <0.20      | <0.071     | <0.071     |
| Naphthalene                        | µg/L | 7                               | <0.20      | <0.20      | <0.20                    | <0.20      | <0.20      | <0.20      | <0.050     | <0.050     |
| Phenanthrene                       | µg/L | 0.1                             | <0.10      | <0.10      | <0.10                    | <0.10      | <0.10      | <0.10      | <0.030     | <0.030     |
| Pyrene                             | µg/L | 0.2                             | <0.20      | <0.20      | <0.20                    | <0.20      | <0.20      | <0.20      | <0.050     | <0.050     |

| Sample Description<br>Date Sampled | Unit | MECP Table<br>1 Standard<br>(1) | BHMW14    | BHMW126-1  | BHMW126-1  | BHMW15 <sup>(2)</sup> | 137-1 <sup>(2)</sup> | DUP1<br>(dup of 137-1) <sup>(2)</sup> | 137-3 <sup>(2)</sup> |
|------------------------------------|------|---------------------------------|-----------|------------|------------|-----------------------|----------------------|---------------------------------------|----------------------|
|                                    |      |                                 | 3/14/2014 | 03/20/2016 | 03/31/2015 | 3/14/2014             | 03/04/2015           | 03/04/2015                            | 03/04/2015           |
| Acenaphthene                       | µg/L | 4.1                             | <0.050    | <0.050     | <0.050     | 4.2                   | 0.050                | 0.550                                 | <0.050               |
| Acenaphthylene                     | µg/L | 1                               | <0.050    | <0.050     | <0.050     | <1.0                  | <0.050               | <0.050                                | <0.050               |
| Anthracene                         | µg/L | 0.1                             | <0.050    | <0.050     | <0.050     | 0.58                  | <0.050               | <0.050                                | <0.050               |
| Benzo(a)anthracene                 | µg/L | 0.2                             | <0.050    | <0.050     | <0.050     | <0.050                | <0.050               | <0.050                                | <0.050               |
| Benzo(a)pyrene                     | µg/L | 0.01                            | <0.010    | <0.010     | <0.010     | <0.010                | <0.010               | <0.010                                | <0.010               |
| Benzo(b/j)fluoranthene             | µg/L | 0.1                             | -         | <0.050     | <0.050     | -                     | <0.050               | <0.050                                | <0.050               |
| Benzo(g,h,i)perylene               | µg/L | 0.2                             | <0.050    | <0.050     | <0.050     | <0.050                | <0.050               | <0.050                                | <0.050               |
| Benzo(k)fluoranthene               | µg/L | 0.1                             | <0.050    | <0.050     | <0.050     | <0.050                | <0.050               | <0.050                                | <0.050               |
| Chrysene                           | µg/L | 0.1                             | <0.050    | <0.050     | <0.050     | 0.055                 | <0.050               | <0.050                                | <0.050               |
| Dibenz(a,h)anthracene              | µg/L | 0.2                             | <0.050    | <0.050     | <0.050     | <0.050                | <0.050               | <0.050                                | <0.050               |
| Fluoranthene                       | µg/L | 0.4                             | <0.050    | <0.050     | <0.050     | 0.15                  | <0.050               | <0.050                                | <0.050               |
| Fluorene                           | µg/L | 120                             | <0.050    | <0.050     | <0.050     | 3.0                   | <0.050               | <0.050                                | <0.050               |
| Indeno(1,2,3-cd)pyrene             | µg/L | 0.2                             | <0.050    | <0.050     | <0.050     | <0.050                | <0.050               | <0.050                                | <0.050               |
| 1-Methylnaphthalene                | µg/L | 2                               | <0.050    | <0.050     | <0.050     | 18                    | <0.050               | <0.050                                | <0.050               |
| 2-Methylnaphthalene                | µg/L | 2                               | <0.050    | <0.050     | <0.050     | 0.83                  | <0.050               | <0.050                                | <0.050               |
| Methylnaphthalene, 2-(1-)          | µg/L | 2                               | <0.071    | <0.071     | <0.071     | 19                    | <0.071               | <0.071                                | <0.071               |
| Naphthalene                        | µg/L | 7                               | <0.050    | <0.050     | <0.050     | <2.0                  | <0.050               | <0.050                                | <0.050               |
| Phenanthrene                       | µg/L | 0.1                             | <0.030    | <0.030     | <0.030     | 0.97                  | <0.030               | <0.030                                | <0.030               |
| Pyrene                             | µg/L | 0.2                             | <0.050    | <0.050     | <0.050     | 0.39                  | <0.050               | <0.050                                | <0.050               |



**Notes:**

G / S     Guideline / Standard  
 --        Not analyzed

- Value**     Parameters exceeds Table 1 criteria.
- Value     RDL exceeds Table 1 criteria
- Sample location has been excavated and removed from site.
- (1)        Ontario Reg 153/04 (2011) Table 1: Full Depth Background Site Condition Standards, Residential/Parkland/Institutional/Industrial/Commercial/Community Property Use for Groundwater
- (2)        Off-site sample location included for reference purposes only

**Table 6c - Groundwater Analytical Results - Metals**

| Sample ID                 | Unit | MECP Table 1 Standard | 22-02      | 22-04      | DUP-01 (dup of 22-04) | 22-05      | 22-06      | Trip Blank | BHMW14    | BHMW15    | BHMW31-1   | BHMW31-1   |
|---------------------------|------|-----------------------|------------|------------|-----------------------|------------|------------|------------|-----------|-----------|------------|------------|
| Date Sampled              |      | (1)                   | 07/18/2022 | 07/18/2022 | 07/18/2022            | 07/18/2022 | 07/18/2022 | 07/18/2022 | 3/14/2014 | 3/14/2014 | 03/04/2015 | 03/20/2016 |
| Dissolved Antimony (Sb)   | µg/L | 1.5                   | <1.0       | <1.0       | <1.0                  | <1.0       | <1.0       | <1.0       | <0.50     | <0.50     | <0.50      | <0.5       |
| Dissolved Arsenic (As)    | µg/L | 13                    | <1.0       | <1.0       | <1.0                  | <1.0       | <1.0       | <1.0       | <1.0      | <1.0      | <1.0       | <1         |
| Dissolved Barium (Ba)     | µg/L | 610                   | 127        | 38.1       | 37.9                  | 92.8       | 104        | <2.0       | 120.0     | 130.0     | 100        | 40         |
| Dissolved Beryllium (Be)  | µg/L | 0.5                   | <0.5       | <0.5       | <0.5                  | <0.5       | <0.5       | <0.5       | <0.50     | <0.50     | <0.50      | <0.5       |
| Dissolved Boron (B)       | µg/L | 1700                  | 104        | 194        | 197                   | 220        | 227        | <10.0      | 26.0      | 26.0      | 60         | 51         |
| Dissolved Cadmium (Cd)    | µg/L | 0.5                   | <0.20      | <0.20      | <0.20                 | <0.20      | <0.20      | <0.20      | <0.10     | <0.10     | <0.10      | <0.1       |
| Dissolved Chromium (Cr)   | µg/L | 11                    | <2.0       | <2.0       | <2.0                  | <2.0       | <2.0       | <2.0       | <5.0      | <5.0      | <5.0       | <5         |
| Dissolved Cobalt (Co)     | µg/L | 3.8                   | 0.53       | 0.63       | 0.57                  | 0.56       | <0.50      | <0.50      | <0.50     | <0.50     | 2.8        | <0.5       |
| Dissolved Copper (Cu)     | µg/L | 5                     | 2.4        | 1.7        | 1.6                   | 1.3        | 1.4        | <1.0       | 1.4       | <1.0      | 2.7        | 2          |
| Dissolved Lead (Pb)       | µg/L | 1.9                   | <0.50      | 0.77       | 0.64                  | <0.50      | <0.50      | <0.50      | <0.50     | <0.50     | <0.50      | <0.5       |
| Dissolved Molybdenum (Mo) | µg/L | 23                    | 1.47       | 2.49       | 2.35                  | 1.13       | 1.7        | <0.50      | <0.50     | <0.50     | 5.6        | <0.5       |
| Dissolved Nickel (Ni)     | µg/L | 14                    | 3.5        | 8          | 7.9                   | 3.4        | 1          | <1.0       | <1.0      | <1.0      | 8.3        | 8          |
| Dissolved Selenium (Se)   | µg/L | 5                     | 1.2        | <1.0       | <1.0                  | <1.0       | <1.0       | <1.0       | <2.0      | <2.0      | <2.0       | <2         |
| Dissolved Silver (Ag)     | µg/L | 0.3                   | <0.20      | <0.20      | <0.20                 | <0.20      | <0.20      | <0.20      | <0.10     | <0.10     | <0.10      | <0.1       |
| Dissolved Sodium (Na)     | µg/L | -                     | -          | -          | -                     | -          | -          | -          | 19000     | 44000     | 61000      | 83000      |
| Dissolved Thallium (Tl)   | µg/L | 0.5                   | <0.30      | <0.30      | <0.30                 | <0.30      | <0.30      | <0.30      | <0.050    | <0.050    | <0.050     | <0.5       |
| Dissolved Uranium (U)     | µg/L | 8.9                   | 1.75       | 2.02       | 2.07                  | 0.99       | 0.96       | <0.50      | 0.3       | <0.10     | 0.95       | 1          |
| Dissolved Vanadium (V)    | µg/L | 3.9                   | 0.46       | <0.40      | <0.40                 | <0.40      | <0.40      | <0.40      | <0.50     | <0.50     | <0.50      | <0.5       |
| Dissolved Zinc (Zn)       | µg/L | 160                   | <5.0       | <5.0       | <5.0                  | <5.0       | <5.0       | <5.0       | 8.4       | 8.8       | 37         | 7          |
| Mercury                   | µg/L | 0.1                   | <0.02      | <0.02      | <0.02                 | <0.02      | <0.02      | <0.02      | -         | -         | -          | -          |
| Chromium IV               | µg/L | 25                    | <2         | <2         | <2                    | <2         | <2         | <2         | -         | -         | -          | -          |

**Notes:**

G / S     Guideline / Standard  
 --        Not analyzed

- Value**     Parameters exceeds Table 1 criteria.
- Value     RDL exceeds Table 1 criteria
- Sample location has been excavated and removed from site.
- (1)        Ontario Reg 153/04 (2011) Table 1: Full Depth Background Site Condition Standards, Residential/Parkland/Institutional/Industrial/Commercial/Community Property Use for Groundwater
- (2)        Off-site sample location included for reference purposes only

**APPENDIX F**

**Rationale for Naturally Occurring Barium, Chromium,  
Cobalt and Vanadium in Ottawa Marine Clay  
Above Generic Standards to Support a  
Record of Site Condition (RSC)**



## TECHNICAL MEMORANDUM

**DATE** January 18, 2023

**Project No.** 19124906

**TO** Katherine Constantine  
Canada Lands Company (CLC)

**FROM** Keith Holmes, MSc, PGeo

**EMAIL** keith.p.holmes@wsp.com

### **INTENT TO APPLY SECTION 49.1 – NATURAL BACKGROUND METALS, WATERIDGE DEVELOPMENT, FORMER CFB ROCKCLIFFE, OTTAWA, ONTARIO**

WSP Canada Inc. (WSP, formerly Golder Associates Ltd.) has prepared this memorandum in support of the Record of Site Condition (RSC) filing for the development of the Wateridge Development, consisting of part of the former CFB Rockcliffe, Ottawa, ON (Subject Property), including the RSC Property. The objective of this document is to provide the necessary lines of evidence required to demonstrate that the concentrations of select metals present in the subsurface within the RSC area are of natural origin and not to be considered an exceedance in the context of regulation 153/04 (Section 49.1).

## **1.0 BACKGROUND**

### **1.1 Phase Two ESA Results**

Elevated naturally occurring metals over the site condition standards were found in several locations evaluated as part of the Phase Two ESA. Barium, chromium, cobalt, and vanadium concentrations were identified over the MECP Table 1 Standards.

The Subject Property and surrounding Subject Area is typified by a layer of mixed fills over a thin deposit of native clay over glacial till. In many areas on the former CFB Rockcliffe property, the native soils have been reworked and mixed with other imported granular fills during historical development resulting in a variable and mixed fill layer over glacial till or bedrock. Samples collected during the Phase Two ESA where elevated metals were found are typically found where the observed clay and silt content was a larger component of the soil.

Given that the concentration of barium, chromium, cobalt, and vanadium are known to occur locally across Ottawa Area at elevated levels as a result of natural deposition of marine clays of eastern Ontario it is the QPs opinion that these concentrations are of natural origin and thus not considered an exceedance in the context of Ontario Regulation 153/04. The following sections presents the multiple lines of evidence required to support this opinion.

## **2.0 PHASE ONE ESA – POTENTIAL FOR SOURCES OF BARIUM, CHROMIUM, COBALT AND VANADIUM**

A Phase One ESA was completed for the Subject Property which identified the presence of fill as the one potentially contaminating activity (PCA) on the RSC Property. No PCAs associated with the generation of metals were identified in the Phase One ESA. There were no areas of metal fabrication, steel manufacturing, electroplating, electronics manufacturing, metal working, scrap yards, slag or other mining residues identified on the Site that may have contributed to metals impacts at the Site, specifically barium, chromium cobalt, and vanadium.

### 3.0 CHAMPLAIN SEA CLAY

The silty clay soils that underlie eastern Ontario and western Quebec, including the Ottawa area, were deposited about 10,000 years ago in a marine (salt water) environment within what is known as the Champlain Sea, after the retreat of the last glacier advance. Because of the marine environment, Champlain Sea clay has a particular mineralogical composition, structure and physical properties and physio-chemical characteristics, which are very different than (for example) the glacial silty clay till that was deposited in a fresh-water environment and underlies much of southern and southwestern Ontario. After the Champlain Sea receded and the land re-emerged, the upper portion of the clay deposit was leached by fresh water that reduced its salinity (salt content), which altered the properties of this portion of the deposit. Over geologic time, in most areas where the silty clay soil forms the upper part of the soil profile and the water table has been at some depth below ground surface, the upper two to four metres has been weathered to form a stiff brown crust, which again altered the clay's physical and mineralogical characteristics. Below this weathered zone, the clay is grey in colour and it has essentially not been altered by the weathering process. It is also the marine depositional environment and subsequent processes that the silty clay soil has experienced that defines the types and concentrations of metals that are naturally occurring in these soils.

Clay is typically formed by the weathering of rocks and soil, specifically in the case of the Champlain Sea deposits, the physical abrasion of Precambrian bedrock by the glaciation process. The weathering process involves physical disaggregation and chemical decomposition that change original minerals to clay minerals (USGS, <http://pubs.usgs.gov/info/clays/>). Given this, comparing typical metal concentrations in bedrock to the Ottawa Regional Data (and Site data) can provide additional context on the source of barium, chromium, cobalt and vanadium. In Canada (as well as outside of Canada), standard mining industry practice is to evaluate metal enrichment of mine waste rock and overburden by comparing results to typical elemental abundances in continental crust (Turekian and Wedepohl (1961)). Using a similar approach, the observed metal concentrations in Ottawa Region clay are compared to typical elemental abundances in continental crust, and those in marine clay in Table 1 below.

**Table 1: Comparison of Barium, Chromium and Vanadium Concentrations in Clay to Crustal Abundance:**

| Data   | Average Barium Concentration (µg/g) | Average Chromium Concentration (µg/g) | Average Cobalt Concentration (µg/g) | Average Vanadium Concentration (µg/g) |
|--|-------------------------------------|---------------------------------------|-------------------------------------|---------------------------------------|
| Typical Crustal Abundance of Continental Crust/Marine Clay | 425/2300                            | 22/90                                 | 25/74                               | 120/120                               |

As shown in Table 1, the typical continental crustal and marine clays indicate an abundance of these metals within values for chromium and vanadium in marine clays being very similar to what was observed on the Subject Property with the barium and cobalt on the Site being closer to the typical crustal abundance. It is noted that the ratios of the metals to also be similar to what was found on the Subject Property and are likely a product of natural deposition.

## 4.0 SUPPORTING STUDIES

The following section presents the findings of supporting studies completed on the Site and within the Ottawa Region of similar soils.

In addition to these studies, a previous Phase Two ESA and RSC application for neighbouring section the CFB Rockcliffe property (Phase3/5) was obtained that relied on the O.Reg 49.1 exception (RSC#229794 filed on October 13, 2021). This RSC was filed by WSP (Golder) using the rationale as outlined in this memo.

### 4.1 Evaluation of Background Concentrations of Selected Metals in Soil, Wateridge Development, Former CFB Rockcliffe, Ottawa, Ontario. DST, March 2019

As part of the previous Phase Two ESA and RSC applications for the CFB Rockcliffe property (including RSCs # 223850 and 224146, that relied on the O.Reg 49.1 exception), including the Subject Site, DST Consulting Engineers Inc. completed a study of natural background metals specific to the Subject Property, including the RSC Property. This study included a literature review of regional studies as well as site-specific background soil quality testing of the clays on the Subject Property. The on-Site evaluation included the collection and analysis of 40 site specific background soil samples of the clays on the Subject Property followed by the calculation of the 90<sup>th</sup> percentile concentration of barium, cobalt and vanadium. DST then used the site-specific testing and literature review to develop a site-specific background concentration for barium, cobalt and vanadium, which is presented in Table 2 below.

**Table 2: DST Site Specific Metals Concentrations**

| Data                                | Average Barium Concentration (µg/g) | Average Cobalt Concentration (µg/g) | Average Vanadium Concentration (µg/g) |
|-------------------------------------|-------------------------------------|-------------------------------------|---------------------------------------|
| DST Local Background Concentrations | 437                                 | 29                                  | 130                                   |

As part of the study DST evaluated the historical activities in the areas of the identified elevated metals and concluded that none of the activities in the vicinity of the elevated metals could be attributed to the concentration of barium, cobalt, or vanadium.

### 4.2 Elevated Background Metals Concentrations in Fine-Grained Champlain Sea Deposits Eastern Ontario – Ottawa Region. Geofirma and Dillon, Feb. 2018

Geofirma and Dillon were retained by the City of Ottawa to undertake a review of available datasets of clay soils across the Ottawa Region and Eastern Ontario. The study included a statistical analysis of 364 individual data points collected from the regional Champlain Sea Deposits. The results of the assessment are presented in Table 3 below.

**Table 3: Geofirma and Dillon Dataset**

| Data  | Average Barium Concentration (µg/g) | Average Chromium Concentration (µg/g) | Average Cobalt Concentration (µg/g) | Average Vanadium Concentration (µg/g) |
|---|-------------------------------------|---------------------------------------|-------------------------------------|---------------------------------------|
| Geofirma and Dillon Dataset Average (98 <sup>th</sup> percentile) | 460                                 | 145                                   | 27.9                                | 123                                   |

### 4.3 WSP Dataset

WSP completed a review of fourteen project sites across the City where similarly identified natural metals in clay were identified, these sites include rural sites with no historical industry, commercial retail sites on previously vacant land as well as project sites local to the Subject Property and consists of approximately 100 individual samples taken from native clay. The average barium, chromium, cobalt and vanadium results are presented below.

**Table 4: Ottawa Area Datasets**


| Data                        | Average Barium Concentration (µg/g) | Average Chromium Concentration (µg/g) | Average Cobalt Concentration (µg/g) | Average Vanadium Concentration (µg/g) |
|-----------------------------|-------------------------------------|---------------------------------------|-------------------------------------|---------------------------------------|
| WSP Ottawa Regional Dataset | 371                                 | 111                                   | 23                                  | 106                                   |

WSP has included a figure showing the location and average concentrations of these metals for each site data set. The figure demonstrates the geographical extent and separation of the data sets.

### 5.0 RATIOS BETWEEN METALS

As presented in the graphic below, the ratios between each of the metals from the 14 WSP sites show a consistent ratio between the concentration of barium, chromium, cobalt and vanadium. For example, in all data sets, an increase in vanadium over the MECP Table 1 background always resulted in a proportional increase in the other three metals.





**Figure 1: Average Concentrations of Select Metals in Local (Ottawa) Area Marine Clay**

It would be expected that an anthropogenic source of metals would be unlikely to fall within a similar ratio due to the expected prevalence of one of the contaminants, which is not the case for the Subject Property which compares very closely to the regional average.

## 6.0 CONCLUSION

Based on the review of the Subject Property concentrations of barium, chromium, cobalt, and vanadium in comparison to the literature review discussed above, including a site-specific background study, it is concluded that the metals concentrations on the Subject Property are present at similar concentrations to those found in the natural background conditions local to the Ottawa Area. This is more noticeable for the sample mainly consisting of silt and clay. Where silty clay has been mixed (diluted with sandy soils) the metals are lower in concentration but found at similar ratios to those found in the background metal (i.e. corresponding increases in chromium, cobalt, and vanadium where the barium was found above background).

When combined with the Phase One ESA findings which did not identify a source for these specific compounds, it is considered that the application of the Section 49.1 of Ontario Regulation 153/04 for naturally occurring compounds is considered appropriate in this instance and are therefore not an exceedance of the site condition standards.

## 7.0 CLOSURE

We trust that the above document provides sufficient lines of evidence to demonstrate that the concentration of barium, chromium, cobalt and vanadium found on the RSC Property is of natural origin and result of natural depositional process and are not considered an exceedance of the site condition standards.

### WSP Canada Inc.



Keith Holmes, MSc, PGeo  
*Senior Principal Geoscientist – Contaminated Sites*



Tony Lyon, PEng  
*Environmental Engineer*

KPH/TL/sg

[https://golderassociates.sharepoint.com/sites/110705/project files/6 deliverables/phase two esas/phase two esa - phase 4-1\\_rsc/appendix f - naturally occurring metals/19124906-tm-natural met - final.docx](https://golderassociates.sharepoint.com/sites/110705/project%20files/6%20deliverables/phase%20esas/phase%20esa%20-%20phase%204-1_rsc/appendix%20f%20-%20naturally%20occurring%20metals/19124906-tm-natural%20met%20-%20final.docx)

Attachments: Figure 1 - Ottawa Area Natural Concentrations of Select Metals in Clay

## 8.0 REFERENCES

**DST, May 2015.** Phase One Environmental Site Assessment, Wateridge Development, Former CFB Rockcliffe, Ottawa, Ontario.


**DST, May 2015.** Phase Two Environmental Site Assessment, Wateridge Development, Former CFB Rockcliffe, Ottawa, Ontario.

**Turekian and Wedepohl (1961).** Distribution of the Elements in some major units of the Earth's crust. *Geological Society of America, Bulletin 72: 175-192*.

**DST, March 2019.** Evaluation of Background Concentrations of Selected Metals in Soil, Wateridge Development, Former CFB Rockcliffe, Ottawa, Ontario.

**Geofirma and Dillon, Feb. 2018.** Elevated Background Metals Concentrations in Fine-Grained Champlain Sea Deposits Eastern Ontario – Ottawa Region.

**WSP Canada Inc. (formerly Golder Associates Ltd.)** data set sourced from multiple Phase Two ESA and Excess soils projects for various private and public clients between 2015 and 2022.



**LEGEND**

● APPROXIMATE SAMPLING LOCATION

0 1,500 3,000 6,000  
1:150,000 METRES

**NOTE(S)**  
1. ALL LOCATIONS ARE APPROXIMATE

**REFERENCE(S)**  
1. CONTAINS INFORMATION LICENSED UNDER THE OPEN GOVERNMENT LICENCE - ONTARIO  
2. COORDINATE SYSTEM: NAD 1983 UTM ZONE 18N, PROJECTION: TRANSVERSE MERCATOR, DATUM: NORTH AMERICAN 1983

**CLIENT**  
CANADA LANDS COMPANY

**PROJECT**  
NATURALLY OCCURRING METALS MEMO  
1076 HEMLOCK PRIVATE, OTTAWA, ONTARIO

**TITLE**  
**OTTAWA AREA NATURAL CONCENTRATIONS OF SELECT METALS IN CLAY**

**CONSULTANT**

|            |            |
|------------|------------|
| YYYY-MM-DD | 2023-01-11 |
| DESIGNED   | ----       |
| PREPARED   | JEM        |
| REVIEWED   | TL         |
| APPROVED   | KPH        |

**wsp GOLDER**

|             |         |      |        |
|-------------|---------|------|--------|
| PROJECT NO. | CONTROL | REV. | FIGURE |
| 19124906    | 0016    | 0    | 1      |

PATH: S:\Client\Canada\_Lands\_Company\Wetlands\_Village09\_PROJ\19124906\_0016\HS\0001.mxd PRINTED ON: 2023-01-11 AT: 11:29:05 AM  
 IF THIS MEASUREMENT DOES NOT MATCH WHAT IS SHOWN, THE SHEET SIZE HAS BEEN MODIFIED FROM: ANSI B

**APPENDIX G**

**Remediation Report**



**APPENDIX G**

# Remediation Report

*Wateridge Village Phase 4, Part of 1076 Hemlock Private, Ottawa, Ontario*

Submitted to:

**Canada Lands Canada**

1050-100 Queen Street  
Ottawa, Ontario  
K1P 1J9


Submitted by:

**WSP Canada Inc.**

1931 Robertson Road, Ottawa, Ontario, K2H 5B7, Canada

19124906

January 2023



## Table of Contents

|            |  |          |
|------------|--|----------|
| <b>1.0</b> | <b>HISTORICAL REMEDIATION</b>                                    | <b>4</b> |
| 1.1        | Remediation at Building 137                                      | 5        |
| 1.2        | Remediation at Building 126                                      | 6        |
| 1.2.1      | Remediation BLD 126-1  | 6        |
| 1.2.2      | Remediation BLD 126-2  | 6        |
| 1.2.3      | Groundwater Quality at Building 126                              | 7        |
| 1.3        | Remediation at TP31 (north of Building 71)                       | 7        |
| <b>2.0</b> | <b>2022 REMEDIAL ACTIONS</b>                                     | <b>7</b> |
| 2.1        | Description of Soil Excavation Activities                        | 8        |
| 2.1.1      | Rationale and Methodology for Soil Removal and Treatment         | 8        |
| 2.1.2      | Soil Treatment   | 8        |
| 2.1.3      | Location of Remedial Action                                      | 8        |
| 2.2        | Quantities of Soil Removed from the Property                     | 8        |
| 2.3        | Groundwater Removal and Treatment                                | 8        |
| 2.3.1      | Rationale and Methodology for Groundwater Removal and Treatment  | 8        |
| 2.3.2      | Groundwater Treatment  | 8        |
| 2.3.3      | Location of Remedial Action                                      | 9        |
| 2.3.4      | Quantities of Groundwater Removed from the Property              | 9        |
| 2.4        | Sediment Removal and Treatment                                   | 9        |
| 2.4.1      | Rationale and Methodology for Sediment Removal and Treatment     | 9        |
| 2.4.2      | Sediment Treatment   | 9        |
| 2.4.3      | Location of Remedial Action                                      | 9        |
| 2.4.4      | Quantities of Sediment Removed from the Property                 | 9        |
| 2.5        | Permits  | 9        |
| 2.6        | Contaminants Introduced to the Property                          | 9        |
| 2.7        | Baseline Conditions and Monitoring for Increases in Contaminants | 10       |

---

|            |   |           |
|------------|---|-----------|
| 2.8        | Groundwater Monitoring Well Selection.....                                  | 10        |
| <b>3.0</b> | <b>FREE FLOWING PRODUCT .....</b>   | <b>10</b> |
| 3.1        | Observations during Remediation.....  | 10        |
| 3.2        | Volume of Product Present and Removed.....                                  | 10        |
| 3.3        | Product Recovery and Remediation .....                                      | 10        |
| <b>4.0</b> | <b>RESULTS OF CONFIRMATORY SAMPLING AND ANALYSIS.....</b>                   | <b>10</b> |
| 4.1        | Description of Confirmatory Sampling .....                                  | 10        |
| 4.1.1      | Description of Confirmatory Sampling for Historical Remediation.....        | 10        |
| 4.1.2      | Description of Confirmatory Sampling for 2022 Remediation.....              | 11        |
| 4.2        | Rationale and Methodology for Confirmatory Sampling – 2022 Remediation..... | 11        |
| 4.2.1      | Contaminants of Concern (COCs).....   | 11        |
| 4.2.2      | Sampling Frequency, Number of Verification Samples .....                    | 11        |
| 4.2.3      | Sampling Locations and Depths .....   | 12        |
| 4.3        | Excavation Dimensions and Number of Confirmatory Samples .....              | 12        |
| 4.4        | Quarterly Groundwater Sampling .....  | 12        |
| 4.4.1      | Groundwater Levels and Well Construction Details .....                      | 12        |
| 4.5        | Quality Assurance and Quality Control Results .....                         | 12        |
| 4.5.1      | Precision .....   | 13        |
| 4.5.2      | Accuracy .....  | 14        |
| 4.5.3      | Completeness .....  | 14        |
| 4.5.4      | Representativeness .....  | 15        |
| 4.5.5      | Comparability .....   | 15        |
| <b>5.0</b> | <b>SOIL BROUGHT TO THE PHASE TWO PROPERTY.....</b>                          | <b>15</b> |
| <b>6.0</b> | <b>CONCLUSIONS .....</b>  | <b>16</b> |



**TABLES**

- Table G1: Verification Samples Analytical Results  
Table G2: Backfill Analytical Results

**FIGURES**

- Figure G1: Remedial Excavations at the RSC Property  
Figure G2a: Cross-Section C-C' with metals analysis and exceedances in soil at TP31 remediation  
Figure G3a: Cross-Section D-D' with metals analysis and exceedances in the sewer trench remediation  
Figure G3b: Cross-Section D-D' with PAH analysis and exceedances in the sewer trench remediation  
Figure G3c: Cross-Section D-D' with PHC analysis and exceedances in the sewer trench remediation  
Figure G4a: Cross-Section E-E' with PHC analysis and exceedances in soil at BLD 126-1 remediation  
Figure G5a: Cross-Section F-F' with PAH analysis and exceedances in soil at BLD 126-2 remediation  
Figure G5b: Cross-Section F-F' with PHC analysis and exceedances in soil at BLD 126-2 remediation

## REMEDIATION REPORT

This report describes the methods and results of the remediation of a parcel of land located on the central portion of the property located at the former Canadian Forces Base (CFB) Rockcliffe in Ottawa, Ontario (hereafter referred to as the “Site” or “RSC Property”).

The Site has been considered as a single parcel of land in this remediation report and is part of 1076 Hemlock Private. The Site has been identified as “RSC Property” as shown in Figure G1. This remediation report should be read in conjunction with the Phase Two ESA report (*Phase Two Environmental Site Assessment, Wateridge Village, Phase 4, Part of 1076 Hemlock Private, Ottawa, Ontario*).

Three areas of the RSC Property were remediated between September 2014 and January 2015 by another consultant for impacts identified, discussed under Section 1.0. In 2022, another remediation was completed to remove impacts associated with poor quality fill, discussed under Section 2.0.

### 1.0 HISTORICAL REMEDIATION

Based on findings of a historical Phase Two ESA, three areas of the RSC Property were identified as having exceedances of the Site Condition Standards and were remediated. These remediated areas were associated with the following APECs:

- Petroleum hydrocarbon related soil and groundwater impacts (as indicated by blue polygon in Figure G1), associated with two former fuel storage tanks (one below and one above ground tank), at the former swimming pool at Building 137. This building and storage tanks (demolished in 1997) were located off-Site, north of the central portion of the RSC Property. Remediation to address the identified soil and groundwater impacts took place off-Site with only a small portion of the remedial excavation encroaching on to the RSC Property (discussed in Section 1.1).
- Identified metals impacts in fill on the northwest portion of the RSC Property (test pit TP31 as shown in Figure G1). The initial test pit with the exceedance TP31 was located off-Site, but the remediation extended onto the Site.
- Petroleum hydrocarbon related soil impacts in two areas (BLD126-1 and BLD-126-2 as shown in Figure G1) in the vicinity of the former Building 126. BLD126-1 was located at the southeast portion of the former building footprint, while BLD126-2 was located southwest of the former building footprint.

During the remediation work associated with above APECs, excavated soil was screened and separated into impacted soil exhibiting staining and/or distinct petroleum odors, which was immediately loaded and transported to licensed waste disposal facilities (BFI Canada and Lafleche Environmental Inc.) and non-impacted soil which was stockpiled on Site for subsequent evaluation. Stockpile samples were collected from each stockpile following the required testing density, as defined under Ontario Regulation 153/04 for laboratory analysis of respective contaminants of concern (COCs) to determine the suitability of stockpiled soil for use as backfill material.

Interim and confirmatory wall and floor samples were collected from each excavation to confirm if the impacted material was removed. Excavation walls were sampled using grids of approximately 3 m<sup>2</sup>, while excavation floors were sampled using grids of approximately 9 m<sup>2</sup>. Samples from each excavation were submitted for laboratory analysis of COCs and were selected based on field screening results. Based on laboratory analytical results, excavations were extended laterally and/or vertically as necessary in the areas of reported until final confirmatory

sampling indicated that no contaminated soil remained within the limits of the excavations and clean remedial excavation boundaries were established.

For each excavation, the final number of confirmatory soil samples, from the remedial limit and stockpiles, submitted for laboratory analyses was equal to or greater than the minimum requirements set out in Table 3 of Schedule E, O.Reg. 153/04 (as amended). Soil samples were collected in accordance with the Ontario Ministry of Environment, Conservation and Parks (MECP) sampling guidelines: “Guidance on Sampling and Analytical Methods for Use at Contaminated Sites in Ontario”, December 1996 (as amended) as well as Ontario Regulation 153/04 Records of Site Condition (as amended).

## 1.1 Remediation at Building 137

The contaminants of concern associated with Building 137, identified during previous subsurface investigations discussed in the Phase Two ESA report, included polycyclic aromatic hydrocarbons (PAHs), petroleum hydrocarbons (PHC) fractions F1 – F4 and benzene, toluene, ethylbenzene and xylenes (BTEX). Soil excavated from 0 – 1.7 meters below ground surface (mbgs) was disposed off-Site at licensed waste disposal facilities (BFI Canada and Lafleche Environmental Inc.). Approximately 1,648 m<sup>3</sup> of soil were removed

Following the remediation of the soil impacts, confirmatory samples were collected from the north wall, east wall and west wall to assess the presence and depth of contamination in the excavation walls and floor. A large portion of the south wall and floor of the excavation was exposed bedrock, and as such only limited confirmatory samples were collected in these areas (from the sections that were not bedrock). The locations of exposed bedrock were inspected for staining and olfactory evidence of PHC contamination and excavated where contamination was identified. Clean remedial excavation boundaries were established for each wall and floor of the excavation.

Guidance for soil sampling frequency in remedial excavations is provided in Ontario Regulation 153/04, as amended, Schedule E, Table 3 (Minimum Confirmation Sampling Requirements for Excavation); however, the largest excavation size on the table is listed as 750 to 1,000 m<sup>2</sup>. As such, this table was extrapolated and used as guide for the remedial sampling frequency. For a 1,000 m<sup>2</sup> excavation, the regulation requires 5 floor and 8 sidewall samples, which equates to one floor sample every 200 m<sup>2</sup> (i.e., 1,000 divided by 5) of floor area, or one sidewall sample every 125 m<sup>2</sup> of floor space (i.e., 1,000 divided by 8). Based on this guidance and final excavation floor area of 3,662 m<sup>2</sup>, a total of 19 floor samples and 30 sidewall samples are required to meet the soil sampling frequency provided in Ontario Regulation 153/04. In total, ninety-six (96) wall samples, two (2) floor samples and fifty (50) stockpile samples were collected and screened. Sixty-two (62) of the collected and screened confirmatory samples including thirty-five (35) sidewall samples, two (2) floor samples, and twenty-five (25) stockpile samples were submitted to the laboratory for analysis of COCs. Given impacted soil was excavated to bedrock, only limited floor samples could be collected for laboratory analysis. As such, the soil sampling frequency meets the requirements of the O.Reg 153/04. Of these, three wall validation samples (BLD137 WW SS1, BLD137 WW SS19 and BLD137 WW SS30) and a field duplicate were located within the RSC Property; however, location of sample BLD137 WW SS1 was not provided in the source report, but it is assumed to be on-Site as the western wall (WW) is located on-Site. Figures 4A to 4C show the sample locations for BLD137 WW SS19 and BLD137 WW SS30 with respect to the RSC Property boundary.

Following completion of the remedial excavation and based on results of validation sampling, it was confirmed that all impacted soil above MECP table 3 Standards\* has been removed and impacted soil above MECP Table 1 Standards was removed from the RSC property. The total mass of excavated soil disposed was 32,958 metric tonnes.

\* After the historic remediations were completed, an area of natural and scientific interest was identified within 30 m of the Site due to endangered bat habitat and butternut trees to the north and east of the Site. As such the RSC Property is considered an environmentally sensitive area and MECP Table 1 now applies.

Groundwater infiltrating into the remedial excavation for Building 137 had evidence of petroleum hydrocarbon sheen and odors. This was treated using a mobile water treatment system supplied by Clean Water Works (MOECC Registration 3664-6GGPRM). The pumped/treated groundwater was sampled for compliance as per the requirements of the sanitary sewer agreement between the City of Ottawa and the contractor. To evaluate the groundwater quality in the vicinity of Building 137, three monitoring wells (BHMW 137-1 to BHMW 137-3) were installed using a CME 850 drill rig to depths ranging between 3.47 and 4.38 mbgs. Following development of these wells (located outside the RSC Property boundary), three groundwater samples and a field duplicate were collected from these wells and analyzed for PHCs F1 to F4, BTEX and PAHs. Analytical results indicated that the sample from BHMW 137-2 exceeded applicable site condition standards for benzo(a)pyrene and PHC F2.

The residual groundwater exceedances at BHMW 137-2 were delineated off-Site using subsequent wells installed in 2022 on the RSC Property adjacent to the off-Site residual impacts (2022 monitoring wells 22-02, 22-04, 22-05 and 22-06, as shown in Figure 3A to 3C and discussed in the Phase Two CSM).

## **1.2 Remediation at Building 126**

### **1.2.1 Remediation BLD 126-1**

Based on identified impacts, the COCs at BLD 126-1 included PHC F1 – F4 and BTEX. Remedial activities were completed on September 16, 2014, and clean remedial excavation boundaries were established, as described earlier. In total, twenty-one (21) wall samples and twenty-three (23) floor samples were collected and screened. Of the samples collected and screened, nine (9) confirmatory samples, including five (5) wall samples and four (4) floor samples, were submitted to the laboratory for analysis. As per soil sampling frequency in remedial excavations provided in Ontario Regulation 153/04, a floor area of 235 m<sup>2</sup> requires a minimum of 3 floor and 5 sidewall samples to be analyzed, hence, the minimum sampling requirement mentioned in the O.Reg 153/04 was met.

Based on the results of the confirmatory samples, it was confirmed that all impacted soil has been removed from the RSC Property with 470 metric tonnes of impacted soil disposed at a licensed waste facility. The excavation was backfilled using 235 m<sup>3</sup> crushed stone (Granular B) from Lafarge Bearbrook quarry between October 14 and 16, 2014.

### **1.2.2 Remediation BLD 126-2**

Based on the identified impacts, the COCs at BLD 126-2 included PHC F1 – F4, BTEX, and PAHs. Remedial activities were completed on September 16 and September 24, 2014 and clean remedial excavation boundaries were established. In total, twenty-one (21) walls samples and twenty (22) floor samples were collected and screened. Of the samples collected and screened, nine (9) confirmatory samples, including five (5) wall samples and four (4) floor samples, were submitted to the laboratory for analysis. Given that surface area of 220 m<sup>2</sup>

requires a minimum of 3 floor and 5 sidewall samples to be analyzed, the minimum sampling requirement mentioned in the O.Reg. 153/04 was fulfilled for BLD 126-2.

Based on the results of the confirmatory samples, it was confirmed that all impacted soil has been removed from the RSC Property with 440 metric tonnes of impacted soil disposed at a licensed waste facility. The excavation was backfilled using crushed stone (Granular B) obtained from Lafarge Bearbrook quarry.

### **1.2.3 Groundwater Quality at Building 126**

To evaluate groundwater quality in the vicinity of excavations BLD 126-1 and BLD 126-2, a monitoring well (BHMW 126-1) was installed on March 3, 2015, using a CME 850 drill rig to a depth of 5.43 mbgs. Following development of BHMW 126-1 and an existing well (BHMW 14), groundwater samples were collected and analyzed for PHCs F1 to F4, BTEX and PAHs. Analytical results indicated that each parameter concentration was below respective laboratory detection limits. No visual or olfactory evidence of petroleum impacts were observed during purging or sampling. As such no groundwater remediation was required or completed.

## **1.3 Remediation at TP31 (north of Building 71)**

The metal impacts identified at TP31 were located adjacent north of the RSC Property (off-Site); however, the remedial excavation completed on September 16, 2014, encroached on to the RSC Property. In total, twenty-one (21) wall samples and twenty-three (23) floor samples were collected and screened. Of the samples collected and screened, eight (8) confirmatory samples, including five (5) wall samples and three (3) floor samples, were submitted for laboratory analysis. Given that surface area of 159 m<sup>2</sup> requires a minimum of 3 floor and 5 sidewall samples to be analyzed, the minimum sampling requirement mentioned in the O.Reg. 153/04 was fulfilled for this excavation.

Based on the results of the confirmatory samples, clean remedial excavation boundaries were established and 440 metric tons of impacted soil was disposed at a licensed waste facility. The excavation was backfilled between October 14 and 17, 2014.

To evaluate groundwater quality in the vicinity of this excavation, a monitoring well (BHMW 31-1) was installed on February 11, 2015, using a high torque track-mounted CME 850 drill rig to a depth of 4.87 mbgs. Following development of the newly installed monitoring well, a sample was collected and analyzed for metals. Analytical results indicated that each parameter concentrations were below the applicable site conditions standards. No visual or olfactory evidence of petroleum impacts were observed during purging or sampling. As such no groundwater remediation was required or completed.

## **2.0 2022 REMEDIAL ACTIONS**

The remedial actions described below occurred between October 19 and December 15, 2022. The objective of the remedial excavation was to remove impacted soil located on the RSC Property, as identified during the subsurface investigation completed in July 2022. The impacts were inferred to have been introduced during the backfilling of the sewer trench, running north-south along the western portion of the Site.

The quantities of soil removed as part of this remediation and the verification samples that were collected are presented hereafter in this report. Groundwater was identified as meeting the applicable site condition standards in the Phase Two ESA and was therefore not part of the remedial actions.

## 2.1 Description of Soil Excavation Activities

### 2.1.1 Rationale and Methodology for Soil Removal and Treatment

The Site was remediated by excavating and removing the impacted fill identified in the Phase Two ESA (test pit and drilling program) and disposing it off-Site. Contaminants of Concern (COCs) identified in the fill were petroleum hydrocarbons (PHCs), BTEX, polycyclic aromatic hydrocarbons (PAHs) and metals. A total of eight samples (including a field duplicate) from the test pits and five boreholes exceeded applicable MECP Table 1 standards for PHCs or PAHs. Three samples exceeding PHC guidelines were located between 1.7 and 3.6 mbgs, whereas another five samples exceeding concentrations for various PAHs were between 0.1 and 3.8 mbgs. The estimate limits of the impacts were based on the delineation completed as part of the Phase II ESA. All these exceedances were excavated, removed and validated by clean samples as part of the remedial work.

Excavated overburden was hauled to the Waste Management West Carleton Environmental Centre landfill for disposal. No separation of soil or reuse of soil on the Site was carried out. No on-site treatment of excavated soil took place as part of this remediation work.

The bulk of the 2022 remediation occurred on-Site, however, the eastern most section of the remediation extended off-Site.

### 2.1.2 Soil Treatment

No treatment of the soil was completed.

### 2.1.3 Location of Remedial Action

The impacted overburden was excavated and removed from the Site as indicated on Figure G1. Samples from the floor and sidewalls of the excavation were collected to confirm compliance with applicable site condition standards. The RSC Property is defined on the Survey Plan provided in Appendix E of the Phase Two ESA report and the location of this remedial excavation is shown on Figures 4A through 4C and cross sections figures 5A to 5C, 6A to 6C, and G2A through G5B.

## 2.2 Quantities of Soil Removed from the Property

9,261.44 metric tonnes (approximately 4630.72 cubic metres) of impacted soil were removed from the Site. The excavation floor area was approximately 900 m<sup>2</sup> and was excavated to a depth ranging from 2 mbgs (in the western area where bedrock was encountered) to 5 mbgs in the southeast corner of the excavation. Sidewalls were sloped at 1:1 ratio at a minimum.

## 2.3 Groundwater Removal and Treatment

As discussed in the Phase Two ESA, no groundwater contamination was present at the Site and therefore there was no remediation or treatment of groundwater.

### 2.3.1 Rationale and Methodology for Groundwater Removal and Treatment

No groundwater removal was required associated with this remedial excavation.

### 2.3.2 Groundwater Treatment

No treatment of groundwater was required or completed.

### 2.3.3 Location of Remedial Action

No remedial actions for groundwater were completed.

### 2.3.4 Quantities of Groundwater Removed from the Property

Not applicable, given no groundwater was removed from the Site.

## 2.4 Sediment Removal and Treatment

### 2.4.1 Rationale and Methodology for Sediment Removal and Treatment

No sediment existed on the Site, and as such no treatment or remediation of sediment was required.

### 2.4.2 Sediment Treatment

No treatment of sediment was completed.

### 2.4.3 Location of Remedial Action

No remedial actions for sediment were completed.

### 2.4.4 Quantities of Sediment Removed from the Property

No sediment was removed from the property.

## 2.5 Permits

No permits were issued for this remediation work.

Contaminated soil from the Site was hauled and disposed by R.W. Tomlinson Limited (Tomlinson) at the Waste Management West Carleton Environmental Centre landfill, which operates under a Certificate of Approval with the Ontario Ministry of the Environment.

## 2.6 Contaminants Introduced to the Property

No significant spills, leaks or releases were noted during the remediation process. No other contaminants were introduced to the Site.

To mitigate the accidental introduction of contaminants to the Site during the remediation process, the following control measures were implemented:

- Best practices were used for storage or handling of fuels and oils;
- Refueling procedures for machinery involved fuelling in non-remediated areas to more easily allow for cleanup of any potential spills;
- Validation of remediation completed in sections that did not require further vehicle traffic; and,
- Visual inspection of areas of the Site for any potential signs of contamination.

## **2.7 Baseline Conditions and Monitoring for Increases in Contaminants**

The analytical baseline condition for the Site used to monitor any increase in contaminants was the Phase Two ESA groundwater sampling results. Given no exceedances above the applicable site condition standards were identified in the groundwater samples for any parameters analyzed, no additional groundwater sampling was conducted at the end of the soil remediation. In addition, no groundwater was encountered and no seepage into the excavation was observed during this remediation work.

Furthermore, a WSP Canada Inc. (WSP, formerly Golder Associates Ltd.) technician was on Site full time during the remediation and monitored and documented any unexpected conditions throughout the remediation.

## **2.8 Groundwater Monitoring Well Selection**

The monitoring wells installed on the RSC Property were completed for the Phase Two ESA. As described in the Phase Two ESA, the groundwater at the RSC Property did not exceed the applicable criteria and as such no remediation of the groundwater was required. The rationale for the monitoring locations is described in the Phase Two ESA report.

## **3.0 FREE FLOWING PRODUCT**

### **3.1 Observations during Remediation**

No free product was noted during the remediation process within the RSC Property.

### **3.2 Volume of Product Present and Removed**

No flowing product was observed or removed during the remediation process.

### **3.3 Product Recovery and Remediation**

No flowing product was recovered from the Site during the remediation process.

## **4.0 RESULTS OF CONFIRMATORY SAMPLING AND ANALYSIS**

Upon completion of the remedial excavation, all soil on the RSC Property met the applicable Ontario Ministry of the Environment, Conservations and Parks (MECP) Soil, Ground Water and Sediment Standards for Use Under Part XV.1 of the Environmental Protection Act Table 1: Generic Site Condition Standards for Residential Property Use, coarse-textured soil, dated April 15, 2011 (MECP Table 1 Standards). A limited number of confirmation samples had concentrations of one or more of barium, chromium (total), cobalt, or vanadium above the MECP Table 1 Standards, which were interpreted to be natural background metals.

Refer to Appendix F of the Phase Two ESA report provided in the attachments for further details.

### **4.1 Description of Confirmatory Sampling**

#### **4.1.1 Description of Confirmatory Sampling for Historical Remediation**

Confirmatory soil samples (including duplicates) were collected during the various remedial excavations in 2014 (discussed in Section 1) at the RSC Property. Of these, eleven (11) confirmatory soil samples were collected from final grade of the excavation for vertical delineation and eighteen (18) confirmatory soil samples were collected from different sidewalls to confirm lateral delineation on the impacts. Please refer to Section 1.0 for details.



#### 4.1.2 Description of Confirmatory Sampling for 2022 Remediation

A total of fourteen (14) confirmatory soil samples were collected during the 2022 remediation that met MECP Table 1 Standards; ten (10) wall samples and four (4) floor samples. Due to the eastern wall being excavated past the RSC Property boundary, six (6) of these samples were located off-Site.

In addition to the fourteen (14) confirmation samples that met MECP Table 1 Standards, eleven (11) additional samples were collected that exceeded MECP Table 1 which were further excavated. In the southeast corner of the excavation, three iterations of a sample being collected which exceeded MECP Table 1 criteria (one sample exceeded followed by further excavation and resampling). Ultimately in this area further excavation was completed until bedrock was encountered.

Soil samples were collected by hand directly from the excavation at all locations using a cleaned stainless steel hand trowel. Disposable nitrile gloves were worn by WSP personnel during soil sampling and gloves were changed between samples. Soil samples were placed in glass jars and vials supplied by the analytical laboratory for chemical analysis of PHC F1 to F4, BTEX, PAHs and metals. Soil samples were kept on ice and were delivered to the analytical laboratory, Bureau Veritas Laboratories (BV).

Details regarding the collection and screening of soil samples have been discussed under respective remedial tasks (sections 1 and 2). Details of soil samples submitted for laboratory analysis, including quality assurance/quality control (QA/QC) samples, are provided in the Phase Two ESA laboratory report tables.

Given no groundwater was encountered during the remedial excavations at the RSC Property, no groundwater samples were collected or analyzed.

### 4.2 Rationale and Methodology for Confirmatory Sampling – 2022 Remediation

#### 4.2.1 Contaminants of Concern (COCs)

Confirmatory sampling was conducted to ensure that all contaminated soil was removed from the Site. As documented in the Phase Two ESA, the COCs for the Site are PHCs, PAHs and metals for soil.

#### 4.2.2 Sampling Frequency, Number of Verification Samples

The verification sampling program included the collection of samples as per the guidance for sampling and analysis frequency is provided in O. Reg 153/04, as amended, Schedule E, Table 3 (Minimum Confirmation Sampling Requirements for Excavation). A visual screening for debris (such as asphalt, concrete, glass, etc.) was conducted and the suspected worst case sample was collected. The 2022 remedial excavation for the sewer trench had a floor area of 900 m<sup>2</sup>, and hence required 5 confirmation floor samples and 8 confirmation sidewall samples, however, the westernmost third of the excavation was terminated on bedrock, so the area of the excavation not terminated on bedrock was 600 m<sup>2</sup>, which would require four (4) floor samples. A total of ten (10) sidewall and four (4) floor confirmatory samples analyzed met the applicable site conditions standards.

Therefore, the sample frequency meets the minimum soil sampling frequency target for the remediation.

### **4.2.3 Sampling Locations and Depths**

Sampling locations are shown on the site plan and cross sections contained in Figures G2A to G5B of this remediation report. Generally, the samples are described as follows:

**Floor Samples:** Four (4) floor samples were collected which meet applicable site conditions standards. Each confirmatory samples were collected from the base of the remedial excavation when bedrock was not encountered, and the maximum sample depth was 4.2 mbgs.

**Wall Samples:** Ten (10) wall samples were collected which meet applicable site conditions standards. Sidewall sample depths ranged between 1.0 and 2.5 mbgs.

Given no exceedances were identified in the groundwater samples analyzed as part of the Phase Two ESA, no sampling for validation of groundwater quality following the remedial excavation was completed.

Copies of the Laboratory Certificates of Analysis are provided in Appendix B of the Phase Two ESA report and analytical results are summarized in Table G1.

### **4.3 Excavation Dimensions and Number of Confirmatory Samples**

The final extent of the remedial excavation was approximately 900 m<sup>2</sup> and was excavated to a depth ranging from 2 mbgs (in the western area where bedrock was encountered) to 5 mbgs in the southeast corner of the excavation.

As stated previously a total of fourteen (14) confirmatory samples were collected which meet applicable site conditions standards.

Cross sections from the Phase Two ESA were updated to reflect post-remediation conditions and show typical cross sections (Figures 5A through 6C) of the remedial excavation. Remediation specific cross-sections are provided in Figures G2A to G5B.

### **4.4 Quarterly Groundwater Sampling**

As discussed in the Phase Two ESA, groundwater at the RSC Property was not found to have any exceedances of the applicable MECP Table 1 Standards at the time of sampling. Therefore, no quarterly sampling was completed or required as there have never been any documented exceedances of groundwater samples collected from the Site.

#### **4.4.1 Groundwater Levels and Well Construction Details**

Groundwater sampling was not required to validate the remediation as such there are no well construction details included in the remediation report. Details of the monitoring wells installed as part of the Phase Two ESA and associated groundwater levels are provided in the appendices of the Phase Two ESA report.

### **4.5 Quality Assurance and Quality Control Results**

The data collected as part of the remediation field program was evaluated according to the following criteria to evaluate its validity: precision, accuracy, completeness, representativeness and comparability. A discussion of each criterion as it relates to the QA/QC program is provided below.

### 4.5.1 Precision

Precision is a measurement of the repeatability of the methods employed, i.e., sampling methods. Precision is evaluated through the testing of blind field duplicate samples. As such, WSP implemented the following laboratory analytical quality control measures:

- Collection of 2 duplicate soil samples from samples and submission for analyses of PHC F1-F4, BTEX, PAHs and/or metals, detailed as follows:

| Field duplicate ID | Original soil sample ID | Parameters analyzed              |
|--------------------|-------------------------|----------------------------------|
| VS-WST-DUP-1       | VS-WST-WW2              | PHC F1-F4, BTEX, PAHs and metals |
| VS-EST-DUP1        | VS-EST-SW1              |                                  |

To determine the precision of the duplicate and original soil sample results, the relative percent difference (RPD) was calculated according to the following equation:

$$RPD = \frac{|x_2 - x_1|}{\left(\frac{x_1 + x_2}{2}\right)} \times 100$$

Where,  $x_1$  and  $x_2$  are the original and duplicate concentrations. RPDs are calculated only if the concentrations of a parameter are greater than the laboratory RDL in both the duplicate and original samples. In addition, lower precision in the RPD calculation is expected when the average of the concentrations of the analytes is less than 5 times the RDL. Therefore, RPDs were calculated for the original and duplicate sample only in cases where the average of the measured concentrations of analytes was five (5) times greater than the RDL.

The following RPD limits were considered reasonable and are based on the MECP Protocol for Analytical Methods Used in the Assessment of Properties under Part XV.1 of the Environmental Protection Act and the laboratory recommended ranges (these ranges are two times the laboratory criterion as per Canadian Council of Ministers of the Environment [CCME] recommendations):

- RPDs in soil: 60% for PHCs, 100% for BTEX, 80% for PAHs, and 60% for metals

**Soil RPD**

Each of the calculated RPD values was within the acceptable range with the exceptions shown in the table below.

| Soil Sample and Duplicate  | Parameters in Soil   | ROD (%) |
|----------------------------|----------------------|---------|
| VS-EST-SW1 and VS-EST-DUP1 | Acenaphthene         | 148.7   |
|                            | Anthracene           | 130.7   |
|                            | Benz(a)anthracene    | 90.9    |
|                            | Benzo(a)pyrene       | 84.0    |
|                            | Benzo(k)fluoranthene | 82.9    |
|                            | Chrysene             | 90.9    |
|                            | Fluoranthene         | 99.7    |
|                            | Fluorene             | 149.3   |
|                            | 1 Methlynaphthalene  | 159.5   |
|                            | 2 Methlynaphthalene  | 170.9   |
|                            | Naphthalene          | 179.8   |
|                            | Phenanthrene         | 130.6   |
|                            | Pyrene               | 100.0   |

The heterogeneous nature of the soil from the fill layer is likely the cause of the variability in the lab results between the original sample and the duplicate. Hence, the integrity of the analytical methods is considered acceptable. Furthermore, the higher concentration of the two results between the original and field duplicate samples was considered as a conservative approach.

**4.5.2 Accuracy**

Accuracy is a measure of how close a measured value is to the true value. The accuracy of the laboratory data is generally evaluated by the laboratory through the use of matrix spikes or surrogate recoveries.

A review of the laboratory spikes and recoveries show that all were within acceptable ranges.

In addition, the laboratory QA/QC program included lab duplicates, spiked blanks and method blanks. The analytical results for the laboratory quality assurance samples indicate that the results of the internal quality control program were within the laboratory’s specified control limits with a few exceptions for which it was indicated that the overall quality meets acceptability criteria.

Based on the above, the laboratory data presented herein are considered to be accurate.

**4.5.3 Completeness**

Completeness is evaluated by comparing the planned sampling program with the sampling program that was actually completed and evaluating discrepancies. WSP completed all planned sampling and analytical work for this remedial program (i.e., met the minimal sampling verification frequency and parameter analysis list), so the information is considered to be complete.

#### 4.5.4 Representativeness

Representativeness is the degree to which the samples collected during the remediation represent the soil conditions from which they were collected. As part of the remediation, WSP implemented the following measures to ensure that representative data was obtained:

- An appropriate and representative number of samples were analyzed;
- Use of dedicated or cleaned sampling equipment between samples;
- Use of appropriate laboratory supplied sampling jars and bottles;
- Analysis within an acceptable holding time as specified in the MECP document “*Protocol for Analytical Methods Used in the Assessment of Properties under Part XV.1 of the Environmental Protection Act*”, March 9, 2004 (amended as of July 1, 2011);
- Delivery of samples under a Chain of Custody; and,
- Laboratory analysis by SCC accredited laboratory (BV Labs).

Based on the above, it is considered that the data collected at the Property during the remediation is representative of the Property environmental conditions at the time the work was completed.

#### 4.5.5 Comparability

Comparability describes how well collected data can be compared to other sample results. Consistent field procedures and analytical methods can assure comparison of the data obtained. Field procedures and analytical methods followed by previous consultant and WSP were industry-approved standards to allow for comparison of data with the applicable MOECC standards.

Based on the above information, data collected as part of the remediation field program are considered to be comparable.

Accordingly, the analytical data generated during the investigation are valid and representative and may be used in this remediation report without further qualification.

### 5.0 SOIL BROUGHT TO THE PHASE TWO PROPERTY

To backfill the remedial excavation, soil and rock was taken from the adjacent off-Site property where remedial activities (excavation for groundwater treatment) were occurring concurrent to the remediation of the Site as well as a clean soil stockpile from the nearby development parcel (Phase 7) east of the RSC Property but within the same Wateridge Village development property.

Soil and rock originating from the adjacent remediation was sourced from clean soil and bedrock located above the groundwater water table which was separated and stockpiled on the adjacent property. Prior to the importation and use of these stockpiles were characterized as discussed below. In total 640.3 m<sup>3</sup> of soil and 1,598.50 m<sup>3</sup> of rock were used to backfill the remediation.

Approximately 2,300 m<sup>3</sup> of additional backfill was sourced from soil that had been stockpiled on the adjacent parcel (Phase 7) of the development originating from ongoing development activities (houses and infrastructure) elsewhere in the subdivision where Records of Site Condition were already in place.

Both stockpiles were sampled in accordance with the stockpile frequency under O.Reg 153/04 (as required under O.Reg 406/19 for ex-situ stockpile characterization) and analysed for metals, PAH, and PHC+BTEX. This included eight samples and one duplicate from the adjacent groundwater remediation and thirty nine samples plus 3 duplicates from the other stockpile on the development property. Each of the samples was found to meet the MECP Table 1 Standards. Analytical results of the backfill used on Site are shown on Table G2.

Both stockpiles were located on the Wateridge Village development property, with the address of 1076 Hemlock Private, Ottawa, Ontario.

## 6.0 CONCLUSIONS

The remediation of the Site included removal of all impacted soil from the RSC Property. This was completed by mechanical means using hydraulic excavators. Following the excavation, soil verification samples were collected and submitted to BV Labs for the Contaminants of Concern. Based on the verification samples, all of which met the MECP Table 1 Standards and the fact that the groundwater was found to meet the Site standards during the Phase Two ESA, it is concluded that all media on the RSC Property satisfied the MECP Table 1 Standards following remediation.

## Signature Page

WSP Canada Inc.



Shihan Chowdhury, P.Eng.  
*Environmental Engineer*



Keith Holmes, BSc (Hons), MSc., P. Geo.  
*Associate, Project Manager, Geoscientist*

SAC/LT/KPH/sg

[https://golderassociates.sharepoint.com/sites/110705/project files/6 deliverables/phase two esas/phase two esa - phase 4-1\\_rsc/appendix g - remediation/app g rsc\\_rem parcel 4-final.docx](https://golderassociates.sharepoint.com/sites/110705/project%20files/6%20deliverables/phase%20esas/phase%20esa%20-%20phase%204-1_rsc/appendix%20g%20-%20remediation/app%20g_rsc_rem%20parcel%204-final.docx)

## Tables



| Sample Location                     | Unit | MECP Table 1 Standard (R/P/I/I/C/C) <sup>(1)</sup> | Western Sewer Trench |             |             |             |             |            |  |            |            |
|-------------------------------------|------|--|----------------------|-------------|-------------|-------------|-------------|------------|--|------------|------------|
|                                     |      |  | VS-WST-NW-1          | VS-WST-NW-2 | VS-WST-SW-1 | VS-WST-SW-2 | VS-WST-WW-1 | VS-WST-WW2 | VS-WST-DUP-1 (Duplicate of VS-WST-WW2) | VS-WST-WW3 | VS-WST-WW4 |
| Date Sampled                        |      |  | 10/27/2022           | 10/27/2022  | 10/27/2022  | 10/27/2022  | 10/27/2022  | 2022-11-01 | 2022-11-01                             | 2022-11-01 | 2022-11-07 |
| Sample Depth (mbgs)                 | mbgs |  | 1.9-2.1              | 1.0-1.2     | 2.0-2.1     | 1.3-1.4     | 0.9-1.1     | 1.5        | 1.5                                    | 2.0        | 2.0        |
| Parameter                           |      |  |                      |             |             |             |             |            |  |            |            |
| Benzene                             | µg/g | 0.02   | <0.02                | <0.02       | <0.02       | <0.02       | <0.02       | <0.02      | <0.02                                  | <0.02      | <0.02      |
| Toluene                             | µg/g | 0.20   | <0.02                | <0.02       | <0.02       | <0.02       | <0.02       | <0.02      | <0.02                                  | <0.02      | <0.02      |
| Ethylbenzene                        | µg/g | 0.05   | <0.02                | <0.02       | <0.02       | <0.02       | <0.02       | <0.05      | <0.05                                  | <0.05      | <0.05      |
| o-Xylene                            | µg/g | --   | <0.02                | <0.02       | <0.02       | <0.02       | <0.02       | <0.02      | <0.02                                  | <0.02      | <0.02      |
| p+m-Xylene                          | µg/g | --   | <0.04                | <0.04       | <0.04       | <0.04       | <0.04       | <0.04      | <0.04                                  | <0.04      | <0.04      |
| Xylenes (Total)                     | µg/g | 0.05   | <0.04                | <0.04       | <0.04       | <0.04       | <0.04       | <0.04      | <0.04                                  | <0.04      | <0.04      |
| F1 (C6 to C10)                      | µg/g | 25   | <10                  | <10         | <10         | <10         | <10         | <10        | <10                                    | <10        | <10        |
| F1 (C6 to C10) minus BTEX           | µg/g | 25   | <10                  | <10         | <10         | <10         | <10         | <10        | <10                                    | <10        | <10        |
| F2 (C10 to C16)                     | µg/g | 10   | <10                  | <10         | <10         | <10         | <10         | <10        | <10                                    | <10        | <10        |
| F2 (C10 to C16) minus Naphthalene   | µg/g | 10   | --                   | --          | --          | --          | --          | --         | --                                     | --         | --         |
| F3 (C16 to C34)                     | µg/g | 240  | <50                  | <50         | <50         | <50         | <50         | <50        | <50                                    | <50        | <50        |
| F3 (C16 to C34) minus PAHs          | µg/g | --   | --                   | --          | --          | --          | --          | --         | --                                     | --         | --         |
| F4 (C34 to C50)                     | µg/g | 120  | <50                  | <50         | <50         | <50         | <50         | <50        | <50                                    | <50        | <50        |
| Reached Baseline at C50             | --   | --   | Yes                  | Yes         | Yes         | Yes         | Yes         | Yes        | Yes                                    | Yes        | Yes        |
| Gravimetric Heavy Hydrocarbons      | µg/g | --   | --                   | --          | --          | --          | --          | --         | --                                     | --         | --         |
| Moisture Content                    | %    | --   | 10                   | 31          | 23          | 17          | 18          | 24         | 22                                     | 30         | 14         |
| TPgH (Gas C5-C10)                   | µg/g | --   | 95                   | 87          | 91          | 89          | 87          | --         | --                                     | --         | --         |
| TEH (Diesel, C10-C24)               | µg/g | --   | --                   | --          | --          | --          | --          | --         | --                                     | --         | --         |
| TPH (Gas/Diesel)                    | µg/g | --   | --                   | --          | --          | --          | --          | --         | --                                     | --         | --         |
| Petroleum Hydrocarbons (heavy oils) | µg/g | --   | --                   | --          | --          | --          | --          | --         | --                                     | --         | --         |



| Sample Location                     | Unit | MECP Table 1 Standard (R/P/I/I/C/C) <sup>(1)</sup> | Eastern Sewer Trench      |            |            |                                       |                           |                           |                           |                           |                           |
|-------------------------------------|------|--|---------------------------|------------|------------|---------------------------------------|---------------------------|---------------------------|---------------------------|---------------------------|---------------------------|
| Sample ID                           |      |  | VS-EST-NW1 <sup>(2)</sup> | VS-EST-NW2 | VS-EST-SW1 | VS-EST-DUP1 (Duplicate of VS-EST-SW1) | VS-EST-SW2 <sup>(2)</sup> | VS-EST-EW1 <sup>(2)</sup> | VS-EST-EW2 <sup>(2)</sup> | VS-EST-EW3 <sup>(2)</sup> | VS-EST-EW4 <sup>(2)</sup> |
| Date Sampled                        |      |  | 2022-11-01                | 2022-11-07 | 2022-11-03 | 2022-11-03                            | 2022-11-08                | 2022-11-01                | 2022-11-01                | 2022-11-03                | 2022-11-09                |
| Sample Depth (mbgs)                 | mbgs |  | 2.0                       | 2.0        | 3.0        | 3.0                                   | 2.0                       | 2.5                       | 2.5                       | 3.0                       | 2.0                       |
| Parameter                           |      |  |                           |            |            |                                       |                           |                           |                           |                           |                           |
| Benzene                             | µg/g | 0.02   | <0.02                     | <0.02      | <0.02      | 0.02                                  | <0.020                    | <0.02                     | <0.02                     | <0.02                     | <0.020                    |
| Toluene                             | µg/g | 0.20   | <0.02                     | <0.02      | <0.02      | 0.20                                  | <0.020                    | <0.02                     | <0.02                     | <0.02                     | <0.020                    |
| Ethylbenzene                        | µg/g | 0.05   | <0.05                     | <0.05      | <0.05      | 0.05                                  | <0.020                    | <0.05                     | <0.05                     | <0.05                     | <0.020                    |
| o-Xylene                            | µg/g | --   | <0.02                     | <0.02      | <0.02      | <0.02                                 | <0.020                    | <0.02                     | <0.02                     | <0.02                     | <0.020                    |
| p+m-Xylene                          | µg/g | --   | <0.04                     | <0.04      | <0.04      | <0.04                                 | <0.040                    | <0.04                     | <0.04                     | <0.04                     | <0.040                    |
| Xylenes (Total)                     | µg/g | 0.05   | <0.04                     | <0.04      | <0.04      | <0.04                                 | <0.040                    | <0.04                     | <0.04                     | <0.04                     | <0.040                    |
| F1 (C6 to C10)                      | µg/g | 25   | <10                       | <10        | <10        | <10                                   | <10                       | <10                       | <10                       | <10                       | <10                       |
| F1 (C6 to C10) minus BTEX           | µg/g | 25   | <10                       | <10        | <10        | <10                                   | <10                       | <10                       | <10                       | <10                       | <10                       |
| F2 (C10 to C16)                     | µg/g | 10   | <10                       | <10        | <10        | <10                                   | <10                       | <10                       | <10                       | <10                       | <10                       |
| F2 (C10 to C16) minus Naphthalene   | µg/g | 10   | --                        | --         | --         | --                                    | --                        | --                        | --                        | --                        | --                        |
| F3 (C16 to C34)                     | µg/g | 240  | <50                       | <50        | 83         | 100                                   | <50                       | <50                       | <50                       | 51                        | <50                       |
| F3 (C16 to C34) minus PAHs          | µg/g | --   | --                        | --         | --         | --                                    | --                        | --                        | --                        | --                        | --                        |
| F4 (C34 to C50)                     | µg/g | 120  | 130                       | <50        | 71         | 86                                    | 78                        | <50                       | <50                       | 150                       | 120                       |
| Reached Baseline at C50             | --   | --   | Yes                       | Yes        | Yes        | Yes                                   | Yes                       | Yes                       | Yes                       | Yes                       | Yes                       |
| Gravimetric Heavy Hydrocarbons      | µg/g | --   | --                        | --         | --         | --                                    | --                        | --                        | --                        | --                        | --                        |
| Moisture Content                    | %    | --   | 25                        | 22         | 19         | 21                                    | 22                        | 17                        | 21                        | 12                        | 16                        |
| TPgH (Gas C5-C10)                   | µg/g | --   | --                        | --         | --         | --                                    | --                        | --                        | --                        | --                        | --                        |
| TEH (Diesel, C10-C24)               | µg/g | --   | --                        | --         | --         | --                                    | --                        | --                        | --                        | --                        | --                        |
| TPH (Gas/Diesel)                    | µg/g | --   | --                        | --         | --         | --                                    | --                        | --                        | --                        | --                        | --                        |
| Petroleum Hydrocarbons (heavy oils) | µg/g | --   | --                        | --         | --         | --                                    | --                        | --                        | --                        | --                        | --                        |



| Sample Location                     | Unit | MECP Table 1 Standard (R/P/I/I/C/C) <sup>(1)</sup> | Sewer Trench Floor |            |                          |                          |                          |                          |                          |
|-------------------------------------|------|--|--------------------|------------|--------------------------|--------------------------|--------------------------|--------------------------|--------------------------|
|                                     |      |  | VS-ST-F1           | VS-ST-F2   | VS-EST-F1 <sup>(2)</sup> | VS-EST-F2 <sup>(2)</sup> | VS-EST-F3 <sup>(2)</sup> | VS-EST-F4 <sup>(2)</sup> | VS-EST-F5 <sup>(2)</sup> |
| Date Sampled                        |      |  | 2022-12-07         | 2022-12-08 | 2022-11-01               | 2022-11-01               | 2022-11-03               | 2022-11-08               | 2022-12-01               |
| Sample Depth (mbgs)                 | mbgs |  | 4-4.2              | 3.8-4.2    | 3.8-4.2                  | 3.8-4.2                  | 4.0                      | 2.0                      | 4.0-4.3                  |
| Parameter                           |      |  |                    |            |                          |                          |                          |                          |                          |
| Benzene                             | µg/g | 0.02   | <0.020             | <0.020     | <0.02                    | <0.02                    | <0.02                    | <0.020                   | <0.020                   |
| Toluene                             | µg/g | 0.20   | <0.020             | <0.020     | <0.02                    | <0.02                    | <0.02                    | <0.020                   | <0.020                   |
| Ethylbenzene                        | µg/g | 0.05   | <0.020             | <0.020     | <0.05                    | <0.05                    | <0.05                    | <0.020                   | <0.020                   |
| o-Xylene                            | µg/g | --   | <0.020             | <0.020     | <0.02                    | <0.02                    | <0.02                    | <0.020                   | <0.020                   |
| p+m-Xylene                          | µg/g | --   | <0.040             | <0.040     | <0.04                    | <0.04                    | <0.04                    | <0.040                   | <0.040                   |
| Xylenes (Total)                     | µg/g | 0.05   | <0.040             | <0.040     | <0.04                    | <0.04                    | <0.04                    | <0.040                   | <0.040                   |
| F1 (C6 to C10)                      | µg/g | 25   | <10                | <10        | <10                      | <10                      | <10                      | <10                      | <10                      |
| F1 (C6 to C10) minus BTEX           | µg/g | 25   | <10                | <10        | <10                      | <10                      | <10                      | <10                      | <10                      |
| F2 (C10 to C16)                     | µg/g | 10   | <10                | <10        | <10                      | <10                      | <10                      | <10                      | <10                      |
| F2 (C10 to C16) minus Naphthalene   | µg/g | 10   | --                 | --         | --                       | --                       | --                       | --                       | --                       |
| F3 (C16 to C34)                     | µg/g | 240  | <50                | <50        | <50                      | <50                      | 69                       | <50                      | 110                      |
| F3 (C16 to C34) minus PAHs          | µg/g | --   | --                 | --         | --                       | --                       | --                       | --                       | --                       |
| F4 (C34 to C50)                     | µg/g | 120  | <50                | 61         | <50                      | <50                      | 170                      | 59                       | 240                      |
| Reached Baseline at C50             | --   | --   | Yes                | Yes        | Yes                      | Yes                      | Yes                      | Yes                      | No                       |
| Gravimetric Heavy Hydrocarbons      | µg/g | --   | --                 | --         | --                       | --                       | --                       | --                       | 810                      |
| Moisture Content                    | %    | --   | 16                 | 16         | 24                       | 39                       | 9.8                      | 6.7                      | 14                       |
| TPgH (Gas C5-C10)                   | µg/g | --   | --                 | --         | --                       | --                       | --                       | --                       | --                       |
| TEH (Diesel, C10-C24)               | µg/g | --   | --                 | --         | --                       | --                       | --                       | --                       | --                       |
| TPH (Gas/Diesel)                    | µg/g | --   | --                 | --         | --                       | --                       | --                       | --                       | --                       |
| Petroleum Hydrocarbons (heavy oils) | µg/g | --   | --                 | --         | --                       | --                       | --                       | --                       | --                       |

| Sample Location                     | Unit | MECP Table 1 Standard (R/P/I/I/C/C) <sup>(1)</sup> | BLD137                        |                               |                                |                                |                                |                                |                                |                                |                                |                                |
|-------------------------------------|------|--|-------------------------------|-------------------------------|--------------------------------|--------------------------------|--------------------------------|--------------------------------|--------------------------------|--------------------------------|--------------------------------|--------------------------------|
| Sample ID                           |      |  | BLD 137 NW SS3 <sup>(2)</sup> | BLD 137 NW SS4 <sup>(2)</sup> | BLD 137 NW SS13 <sup>(2)</sup> | BLD 137 NW SS34 <sup>(2)</sup> | BLD 137 NW SS53 <sup>(2)</sup> | BLD 137 NW SS60 <sup>(2)</sup> | BLD 137 NW SS79 <sup>(3)</sup> | BLD 137 NW SS96 <sup>(3)</sup> | BLD 137 SW SS46 <sup>(2)</sup> | BLD 137 EW SS47 <sup>(2)</sup> |
| Date Sampled                        |      |  | 2014-09-10                    | 2014-10-16                    | 2014-10-16                     | 2014-10-16                     | 2014-11-12                     | 2014-11-12                     | 2014-12-12                     | 2014-12-12                     | 2014-11-10                     | 2014-12-12                     |
| Sample Depth (mbgs)                 | mbgs |  | 0.5                           | 1                             | 0.3                            | 2.9                            | 1.2                            | 0.85                           | 0-1.5                          | 0-1.5                          | 4.3                            | 2.1                            |
| Parameter                           |      |  |                               |                               |                                |                                |                                |                                |                                |                                |                                |                                |
| Benzene                             | µg/g | 0.02   | <0.020                        | <0.020                        | <0.020                         | <0.020                         | <0.020                         | <0.020                         | <0.020                         | <0.020                         | <0.020                         | <0.020                         |
| Toluene                             | µg/g | 0.20   | <0.020                        | <0.020                        | <0.020                         | <0.020                         | <0.020                         | <0.020                         | <0.020                         | <0.020                         | <0.020                         | <0.020                         |
| Ethylbenzene                        | µg/g | 0.05   | <0.020                        | <0.020                        | <0.020                         | <0.020                         | <0.020                         | <0.020                         | <0.020                         | <0.020                         | <0.020                         | <0.020                         |
| o-Xylene                            | µg/g | --   | <0.020                        | <0.020                        | <0.020                         | <0.020                         | <0.020                         | <0.020                         | <0.020                         | <0.020                         | <0.020                         | <0.020                         |
| p+m-Xylene                          | µg/g | --   | <0.040                        | <0.040                        | <0.040                         | <0.040                         | <0.040                         | <0.040                         | <0.040                         | <0.040                         | <0.040                         | <0.040                         |
| Xylenes (Total)                     | µg/g | 0.05   | <0.040                        | <0.040                        | <0.040                         | <0.040                         | <0.040                         | <0.040                         | <0.040                         | <0.040                         | <0.040                         | <0.040                         |
| F1 (C6 to C10)                      | µg/g | 25   | <10                           | <10                           | <10                            | <10                            | <10                            | <10                            | <10                            | <10                            | <10                            | <10                            |
| F1 (C6 to C10) minus BTEX           | µg/g | 25   | <10                           | <10                           | <10                            | <10                            | <10                            | <10                            | <10                            | <10                            | <10                            | <10                            |
| F2 (C10 to C16)                     | µg/g | 10   | <10                           | <10                           | <10                            | <10                            | <10                            | <10                            | <10                            | <10                            | <10                            | <10                            |
| F2 (C10 to C16) minus Naphthalene   | µg/g | 10   | --                            | --                            | --                             | --                             | --                             | --                             | --                             | --                             | --                             | --                             |
| F3 (C16 to C34)                     | µg/g | 240  | <10                           | <10                           | <50                            | <50                            | <10                            | <10                            | <10                            | <10                            | <10                            | <10                            |
| F3 (C16 to C34) minus PAHs          | µg/g | --   | --                            | --                            | --                             | --                             | --                             | --                             | --                             | --                             | --                             | --                             |
| F4 (C34 to C50)                     | µg/g | 120  | <10                           | <10                           | <50                            | <50                            | <10                            | <10                            | <10                            | <10                            | <10                            | <10                            |
| Reached Baseline at C50             | --   | --   | Yes                           | Yes                           | Yes                            | Yes                            | Yes                            | Yes                            | Yes                            | Yes                            | Yes                            | Yes                            |
| Gravimetric Heavy Hydrocarbons      | µg/g | --   | NA                            | NA                            | NA                             | NA                             | --                             | --                             | --                             | --                             | --                             | --                             |
| Moisture Content                    | %    | --   | --                            | --                            | --                             | --                             | --                             | --                             | --                             | --                             | --                             | --                             |
| TPgH (Gas C5-C10)                   | µg/g | --   | --                            | --                            | --                             | --                             | --                             | --                             | --                             | --                             | --                             | --                             |
| TEH (Diesel, C10-C24)               | µg/g | --   | --                            | --                            | --                             | --                             | --                             | --                             | --                             | --                             | --                             | --                             |
| TPH (Gas/Diesel)                    | µg/g | --   | --                            | --                            | --                             | --                             | --                             | --                             | --                             | --                             | --                             | --                             |
| Petroleum Hydrocarbons (heavy oils) | µg/g | --   | --                            | --                            | --                             | --                             | --                             | --                             | --                             | --                             | --                             | --                             |

| Sample Location                     | Unit | MECP Table 1 Standard (R/P/I/I/C/C) <sup>(1)</sup> | BLD137                         |                                |                                |                                |                                |                                |                               |  |                 |                 |
|-------------------------------------|------|--|--------------------------------|--------------------------------|--------------------------------|--------------------------------|--------------------------------|--------------------------------|-------------------------------|--|-----------------|-----------------|
| Sample ID                           |      |  | BLD 137 SW SS62 <sup>(2)</sup> | BLD 137 EW SS64 <sup>(2)</sup> | BLD 137 EW SS68 <sup>(2)</sup> | BLD 137 EW SS76 <sup>(2)</sup> | BLD 137 EW SS11 <sup>(3)</sup> | BLD 137 EW SS31 <sup>(2)</sup> | BLD 137 WW SS1 <sup>(3)</sup> | BLD 137 WW DUP1 (Dup of WW SS1) <sup>(3)</sup> | BLD 137 WW SS19 | BLD 137 WW SS30 |
| Date Sampled                        |      |  | 2014-11-10                     | 2014-12-12                     | 2014-12-12                     | 2014-12-12                     | 2014-11-04                     | 2014-11-04                     | 2014-11-10                    | 2014-11-10                                     | 2014-11-10      | 2014-11-10      |
| Sample Depth (mbgs)                 | mbgs |  | 4                              | 1.3                            | 1                              | 0.8                            | 1                              | 1.9                            | 3.7                           | 3.7  | 1.4             | 2               |
| Parameter                           |      |  |                                |                                |                                |                                |                                |                                |                               |  |                 |                 |
| Benzene                             | µg/g | 0.02   | <0.020                         | <0.020                         | <0.020                         | <0.020                         | <0.020                         | <0.020                         | <0.020                        | <0.020   | <0.020          | <0.020          |
| Toluene                             | µg/g | 0.20   | <0.020                         | <0.020                         | <0.020                         | <0.020                         | <0.020                         | <0.020                         | <0.020                        | <0.020   | <0.020          | <0.020          |
| Ethylbenzene                        | µg/g | 0.05   | <0.020                         | <0.020                         | <0.020                         | <0.020                         | <0.020                         | <0.020                         | <0.020                        | <0.020   | <0.020          | <0.020          |
| o-Xylene                            | µg/g | --   | <0.020                         | <0.020                         | <0.020                         | <0.020                         | <0.020                         | <0.020                         | <0.020                        | <0.020   | <0.020          | <0.020          |
| p+m-Xylene                          | µg/g | --   | <0.040                         | <0.040                         | <0.040                         | <0.040                         | <0.040                         | <0.040                         | <0.040                        | <0.040   | <0.040          | <0.040          |
| Xylenes (Total)                     | µg/g | 0.05   | <0.040                         | <0.040                         | <0.040                         | <0.040                         | <0.040                         | <0.040                         | <0.040                        | <0.040   | <0.040          | <0.040          |
| F1 (C6 to C10)                      | µg/g | 25   | <10                            | <10                            | <10                            | <10                            | <10                            | <10                            | <10                           | <10  | <10             | <10             |
| F1 (C6 to C10) minus BTEX           | µg/g | 25   | <10                            | <10                            | <10                            | <10                            | <10                            | <10                            | <10                           | <10  | <10             | <10             |
| F2 (C10 to C16)                     | µg/g | 10   | <10                            | <10                            | <10                            | <10                            | <10                            | <10                            | <10                           | <10  | <10             | <10             |
| F2 (C10 to C16) minus Naphthalene   | µg/g | 10   | --                             | --                             | --                             | --                             | --                             | --                             | --                            | --   | --              | --              |
| F3 (C16 to C34)                     | µg/g | 240  | <10                            | <10                            | <10                            | <10                            | <10                            | <10                            | 54                            | <10  | <10             | <10             |
| F3 (C16 to C34) minus PAHs          | µg/g | --   | --                             | --                             | --                             | --                             | --                             | --                             | --                            | --   | --              | --              |
| F4 (C34 to C50)                     | µg/g | 120  | <10                            | <10                            | <10                            | 86                             | <10                            | <10                            | 13                            | <10  | <10             | <10             |
| Reached Baseline at C50             | --   | --   | Yes                            | Yes                            | Yes                            | Yes                            | Yes                            | Yes                            | Yes                           | Yes  | Yes             | Yes             |
| Gravimetric Heavy Hydrocarbons      | µg/g | --   | --                             | --                             | --                             | --                             | NA                             | --                             | --                            | --   | --              | --              |
| Moisture Content                    | %    | --   | --                             | --                             | --                             | --                             | --                             | --                             | --                            | --   | --              | --              |
| TPgH (Gas C5-C10)                   | µg/g | --   | --                             | --                             | --                             | --                             | --                             | --                             | --                            | --   | --              | --              |
| TEH (Diesel, C10-C24)               | µg/g | --   | --                             | --                             | --                             | --                             | --                             | --                             | --                            | --   | --              | --              |
| TPH (Gas/Diesel)                    | µg/g | --   | --                             | --                             | --                             | --                             | --                             | --                             | --                            | --   | --              | --              |
| Petroleum Hydrocarbons (heavy oils) | µg/g | --   | --                             | --                             | --                             | --                             | --                             | --                             | --                            | --   | --              | --              |



| Sample Location                     | Unit | MECP Table 1 Standard (R/P/I/I/C/C) <sup>(1)</sup> | BLD126      |             |             |             |             |             |              |               |               |                             |
|-------------------------------------|------|--|-------------|-------------|-------------|-------------|-------------|-------------|--------------|---------------|---------------|-----------------------------|
| Sample ID                           |      |  | BLD126-1 P1 | BLD126-1 P2 | BLD126-1 P3 | BLD126-1 P4 | BLD126-1 P5 | BLD126-1 P6 | BLD126-1 SS7 | BLD126-1 SS19 | BLD126-1 SS35 | BLD126-1 DUP1 (dup of SS35) |
| Date Sampled                        |      |  | 2014-09-16  | 2014-09-16  | 2014-09-16  | 2014-09-16  | 2014-09-16  | 2014-09-16  | 2014-09-24   | 2014-09-24    | 2014-09-24    | 2014-09-24                  |
| Sample Depth (mbgs)                 | mbgs |  | 0.7         | 0.3         | 0.2         | 0.8         | 1           | 1           | 0.45         | 1             | 1             | 1                           |
| Parameter                           |      |  |             |             |             |             |             |             |              |               |               |                             |
| Benzene                             | µg/g | 0.02   | <0.02       | <0.02       | <0.02       | <0.02       | <0.02       | <0.02       | <0.02        | <0.02         | <0.02         | <0.02                       |
| Toluene                             | µg/g | 0.20   | <0.02       | <0.02       | <0.02       | <0.02       | <0.02       | <0.02       | <0.02        | <0.02         | <0.02         | <0.02                       |
| Ethylbenzene                        | µg/g | 0.05   | <0.02       | <0.02       | <0.02       | <0.02       | <0.02       | <0.02       | <0.02        | <0.02         | <0.02         | <0.02                       |
| o-Xylene                            | µg/g | --   | <0.02       | <0.02       | <0.02       | <0.02       | <0.02       | <0.02       | <0.02        | <0.02         | <0.02         | <0.02                       |
| p+m-Xylene                          | µg/g | --   | <0.04       | <0.04       | <0.04       | <0.04       | <0.04       | <0.04       | <0.04        | <0.04         | <0.04         | <0.04                       |
| Xylenes (Total)                     | µg/g | 0.05   | <0.04       | <0.04       | <0.04       | <0.04       | <0.04       | <0.04       | <0.04        | <0.04         | <0.04         | <0.04                       |
| F1 (C6 to C10)                      | µg/g | 25   | <10         | <10         | <10         | <10         | <10         | <10         | <10          | <10           | <10           | <10                         |
| F1 (C6 to C10) minus BTEX           | µg/g | 25   | <10         | <10         | <10         | <10         | <10         | <10         | <10          | <10           | <10           | <10                         |
| F2 (C10 to C16)                     | µg/g | 10   | <10         | <10         | <10         | <10         | <10         | <10         | <10          | <10           | <10           | <10                         |
| F2 (C10 to C16) minus Naphthalene   | µg/g | 10   | --          | --          | --          | --          | --          | --          | --           | --            | --            | --                          |
| F3 (C16 to C34)                     | µg/g | 240  | <10         | <10         | <10         | 46          | <10         | 140         | <10          | <10           | <10           | <10                         |
| F3 (C16 to C34) minus PAHs          | µg/g | --   | --          | --          | --          | --          | --          | --          | --           | --            | --            | --                          |
| F4 (C34 to C50)                     | µg/g | 120  | <10         | <10         | <10         | 25          | <10         | 81          | <10          | <10           | <10           | <10                         |
| Reached Baseline at C50             | --   | --   | Yes         | Yes         | Yes         | Yes         | Yes         | Yes         | Yes          | Yes           | Yes           | Yes                         |
| Gravimetric Heavy Hydrocarbons      | µg/g | --   | --          | --          | --          | --          | --          | --          | --           | --            | --            | --                          |
| Moisture Content                    | %    | --   | --          | --          | --          | --          | --          | --          | --           | --            | --            | --                          |
| TPgH (Gas C5-C10)                   | µg/g | --   | --          | --          | --          | --          | --          | --          | --           | --            | --            | --                          |
| TEH (Diesel, C10-C24)               | µg/g | --   | --          | --          | --          | --          | --          | --          | --           | --            | --            | --                          |
| TPH (Gas/Diesel)                    | µg/g | --   | --          | --          | --          | --          | --          | --          | --           | --            | --            | --                          |
| Petroleum Hydrocarbons (heavy oils) | µg/g | --   | --          | --          | --          | --          | --          | --          | --           | --            | --            | --                          |

| Sample Location                     | Unit | MECP Table 1 Standard (R/P/I/I/C/C) <sup>(1)</sup> | BLD126      |             |             |             |             |             |              |               |               |               |
|-------------------------------------|------|--|-------------|-------------|-------------|-------------|-------------|-------------|--------------|---------------|---------------|---------------|
| Sample ID                           |      |  | BLD126-2 P1 | BLD126-2 P2 | BLD126-2 P3 | BLD126-2 P4 | BLD126-2 P5 | BLD126-2 P6 | BLD126-2 SS7 | BLD126-2 SS17 | BLD126-2 SS25 | BLD126-2 SS30 |
| Date Sampled                        |      |  | 2014-09-16  | 2014-09-16  | 2014-09-16  | 2014-09-16  | 2014-09-16  | 2014-09-16  | 2014-09-26   | 2014-09-26    | 2014-09-26    | 2014-09-26    |
| Sample Depth (mbgs)                 | mbgs |  | 1           | 1           | 0.5         | 0.45        | 0.3         | 0.5         | 0.25         | 1             | 1             | 1             |
| Parameter                           |      |  |             |             |             |             |             |             |              |               |               |               |
| Benzene                             | µg/g | 0.02   | <0.02       | <0.02       | <0.02       | <0.02       | <0.02       | <0.02       | <0.02        | <0.02         | <0.02         | <0.02         |
| Toluene                             | µg/g | 0.20   | <0.02       | <0.02       | <0.02       | <0.02       | <0.02       | <0.02       | <0.02        | <0.02         | <0.02         | <0.02         |
| Ethylbenzene                        | µg/g | 0.05   | <0.02       | <0.02       | <0.02       | <0.02       | <0.02       | <0.02       | <0.02        | <0.02         | <0.02         | <0.02         |
| o-Xylene                            | µg/g | --   | <0.02       | <0.02       | <0.02       | <0.02       | <0.02       | <0.02       | <0.02        | <0.02         | <0.02         | <0.02         |
| p+m-Xylene                          | µg/g | --   | <0.04       | <0.04       | <0.04       | <0.04       | <0.04       | <0.04       | <0.04        | <0.04         | <0.04         | <0.04         |
| Xylenes (Total)                     | µg/g | 0.05   | <0.04       | <0.04       | <0.04       | <0.04       | <0.04       | <0.04       | <0.04        | <0.04         | <0.04         | <0.04         |
| F1 (C6 to C10)                      | µg/g | 25   | <10         | <10         | <10         | <10         | <10         | <10         | <10          | <10           | <10           | <10           |
| F1 (C6 to C10) minus BTEX           | µg/g | 25   | <10         | <10         | <10         | <10         | <10         | <10         | <10          | <10           | <10           | <10           |
| F2 (C10 to C16)                     | µg/g | 10   | <10         | <10         | <10         | <10         | <10         | <10         | <10          | <10           | <10           | <10           |
| F2 (C10 to C16) minus Naphthalene   | µg/g | 10   | --          | --          | --          | --          | --          | --          | --           | --            | --            | --            |
| F3 (C16 to C34)                     | µg/g | 240  | <10         | <10         | <10         | <10         | <10         | <10         | <50          | <50           | <50           | <50           |
| F3 (C16 to C34) minus PAHs          | µg/g | --   | --          | --          | --          | --          | --          | --          | --           | --            | --            | --            |
| F4 (C34 to C50)                     | µg/g | 120  | <10         | <10         | <10         | <10         | <10         | <10         | <50          | <50           | <50           | <50           |
| Reached Baseline at C50             | --   | --   | Yes         | Yes         | Yes         | Yes         | Yes         | Yes         | Yes          | Yes           | Yes           | Yes           |
| Gravimetric Heavy Hydrocarbons      | µg/g | --   | --          | --          | --          | --          | --          | --          | --           | --            | --            | --            |
| Moisture Content                    | %    | --   | --          | --          | --          | --          | --          | --          | --           | --            | --            | --            |
| TPgH (Gas C5-C10)                   | µg/g | --   | --          | --          | --          | --          | --          | --          | --           | --            | --            | --            |
| TEH (Diesel, C10-C24)               | µg/g | --   | --          | --          | --          | --          | --          | --          | --           | --            | --            | --            |
| TPH (Gas/Diesel)                    | µg/g | --   | --          | --          | --          | --          | --          | --          | --           | --            | --            | --            |
| Petroleum Hydrocarbons (heavy oils) | µg/g | --   | --          | --          | --          | --          | --          | --          | --           | --            | --            | --            |

**Notes:**

G / S      Guideline / Standard  
 --          Not analyzed

- Value**      Parameters exceeds Table 1 criteria.
- Value      RDL exceeds Table 1 criteria
- Sample location has been excavated and removed from site.
- (1)          Ontario Reg 153/04 (2011) Table 1: Full Depth Background Site Condition Standards, Residential/Parkland/Institutional/Industrial/Commercial/Community Property Use for Soil.
- (2)          Off-site sample location included for reference purposes only
- (3)          Location of sample not provided in source report
- (4)          No date was provided in the source report.



| Sample Location               | Unit | MECP Table 1 Standard (R/P/I/I/C/C) <sup>(1)</sup> | Western Sewer Trench |             |             |             |             |            |  |            |            |
|-------------------------------|------|--|----------------------|-------------|-------------|-------------|-------------|------------|--|------------|------------|
| Sample ID                     |      |  | VS-WST-NW-1          | VS-WST-NW-2 | VS-WST-SW-1 | VS-WST-SW-2 | VS-WST-WW-1 | VS-WST-WW2 | VS-WST-DUP-1 (Duplicate of VS-WST-WW2) | VS-WST-WW3 | VS-WST-WW4 |
| Date Sampled                  |      |  | 10/27/2022           | 10/27/2022  | 10/27/2022  | 10/27/2022  | 10/27/2022  | 2022-11-01 | 2022-11-01                             | 2022-11-01 | 2022-11-07 |
| Sample Depth (mbgs)           | mbgs |  | 1.9-2.1              | 1.0-1.2     | 2.0-2.1     | 1.3-1.4     | 0.9-1.1     | 1.5        | 1.5                                    | 2.0        | 2.0        |
| Parameter                     |      |  |                      |             |             |             |             |            |  |            |            |
| Acenaphthene                  | µg/g | 0.072  | <0.005               | <0.005      | <0.005      | <0.005      | 0.054       | ND         | ND                                     | ND         | <0.0050    |
| Acenaphthylene                | µg/g | 0.093  | <0.005               | <0.005      | <0.005      | 0.013       | 0.0051      | ND         | 0.0063                                 | ND         | <0.0050    |
| Anthracene                    | µg/g | 0.16   | <0.005               | <0.005      | <0.005      | 0.01        | 0.13        | ND         | ND                                     | ND         | 0.0056     |
| Benz(a)anthracene             | µg/g | 0.36   | <0.005               | 0.0087      | <0.005      | 0.055       | 0.32        | 0.015      | 0.02                                   | ND         | 0.025      |
| Benzo(a)pyrene                | µg/g | 0.3  | <0.005               | 0.008       | <0.005      | 0.051       | 0.25        | 0.015      | 0.02                                   | ND         | 0.024      |
| Benzo(b)fluoranthene          | µg/g | 0.47   | <0.005               | 0.011       | <0.005      | 0.072       | 0.33        | 0.025      | 0.031                                  | ND         | 0.037      |
| Benzo(g,h,i)perylene          | µg/g | 0.68   | <0.005               | 0.0053      | <0.005      | 0.034       | 0.14        | 0.012      | 0.014                                  | ND         | 0.017      |
| Benzo(k)fluoranthene          | µg/g | 0.48   | <0.005               | <0.005      | <0.005      | 0.027       | 0.13        | 0.0077     | 0.011                                  | ND         | 0.012      |
| Chrysene                      | µg/g | 2.8  | <0.005               | 0.0074      | <0.005      | 0.048       | 0.24        | 0.015      | 0.017                                  | ND         | 0.023      |
| Dibenz(a,h)anthracene         | µg/g | 0.1  | <0.005               | <0.005      | <0.005      | 0.0091      | 0.041       | ND         | ND                                     | ND         | <0.050     |
| Fluoranthene                  | µg/g | 0.56   | <0.005               | 0.018       | <0.005      | 0.099       | <b>0.78</b> | 0.035      | 0.04                                   | ND         | 0.06       |
| Fluorene                      | µg/g | 0.12   | <0.005               | <0.005      | <0.005      | <0.005      | 0.06        | ND         | ND                                     | ND         | <0.30      |
| Indeno(1,2,3-cd)pyrene        | µg/g | 0.23   | <0.005               | 0.0052      | <0.005      | 0.034       | 0.15        | 0.012      | 0.015                                  | ND         | 0.018      |
| 1 Methlynaphthalene           | µg/g | 0.59 <sup>(2)</sup>                                | <0.005               | <0.005      | <0.005      | <0.005      | <0.005      | ND         | ND                                     | ND         | <0.050     |
| 2 Methlynaphthalene           | µg/g | 0.59 <sup>(2)</sup>                                | <0.005               | <0.005      | <0.005      | <0.005      | <0.005      | ND         | ND                                     | ND         | <0.070     |
| 1 and 2 Methlynaphthalene (2) | µg/g | 0.59   | --                   | --          | --          | --          | --          | ND         | ND                                     | ND         | <0.0071    |
| Naphthalene                   | µg/g | 0.09   | <0.005               | <0.005      | <0.005      | <0.005      | <0.005      | ND         | ND                                     | ND         | <0.0050    |
| Phenanthrene                  | µg/g | 0.69   | <0.005               | 0.0066      | <0.005      | 0.031       | 0.57        | 0.017      | 0.018                                  | ND         | 0.03       |
| Pyrene                        | µg/g | 1  | <0.005               | 0.017       | <0.005      | 0.084       | 0.55        | 0.027      | 0.032                                  | ND         | 0.047      |



| Sample Location               | Unit | MECP Table 1 Standard (R/P/I/I/C/C) <sup>(1)</sup> | Eastern Sewer Trench      |            |            |                                       |                           |                           |                           |                           |                           |
|-------------------------------|------|--|---------------------------|------------|------------|---------------------------------------|---------------------------|---------------------------|---------------------------|---------------------------|---------------------------|
| Sample ID                     |      |  | VS-EST-NW1 <sup>(3)</sup> | VS-EST-NW2 | VS-EST-SW1 | VS-EST-DUP1 (Duplicate of VS-EST-SW1) | VS-EST-SW2 <sup>(3)</sup> | VS-EST-EW1 <sup>(3)</sup> | VS-EST-EW2 <sup>(3)</sup> | VS-EST-EW3 <sup>(3)</sup> | VS-EST-EW4 <sup>(3)</sup> |
| Date Sampled                  |      |  | 2022-11-01                | 2022-11-07 | 2022-11-03 | 2022-11-03                            | 2022-11-08                | 2022-11-01                | 2022-11-01                | 2022-11-03                | 2022-11-09                |
| Sample Depth (mbgs)           | mbgs |  | 2.0                       | 2.0        | 3.0        | 3.0                                   | 2.0                       | 2.5                       | 2.5                       | 3.0                       | 2.0                       |
| Parameter                     |      |  |                           |            |            |                                       |                           |                           |                           |                           |                           |
| Acenaphthene                  | µg/g | 0.072  | ND                        | <0.0050    | 0.025      | 0.17                                  | 0.0056                    | ND                        | ND                        | ND                        | <0.050                    |
| Acenaphthylene                | µg/g | 0.093  | 0.0059                    | 0.0089     | 0.015      | 0.029                                 | <0.0050                   | ND                        | 0.0053                    | ND                        | <0.050                    |
| Anthracene                    | µg/g | 0.16   | 0.0067                    | <0.0050    | 0.13       | 0.62                                  | 0.016                     | ND                        | 0.012                     | ND                        | <0.050                    |
| Benz(a)anthracene             | µg/g | 0.36   | 0.02                      | 0.015      | 0.6        | 1.6                                   | 0.061                     | 0.015                     | 0.045                     | ND                        | <0.050                    |
| Benzo(a)pyrene                | µg/g | 0.3  | 0.017                     | 0.021      | 0.49       | 1.2                                   | 0.057                     | 0.012                     | 0.038                     | ND                        | <0.050                    |
| Benzo(b)fluoranthene          | µg/g | 0.47   | 0.024                     | 0.03       | 0.65       | 1.5                                   | 0.076                     | 0.019                     | 0.053                     | ND                        | <0.050                    |
| Benzo(g,h,i)perylene          | µg/g | 0.68   | 0.013                     | 0.026      | 0.26       | 0.52                                  | 0.042                     | 0.0086                    | 0.025                     | ND                        | <0.050                    |
| Benzo(k)fluoranthene          | µg/g | 0.48   | 0.0079                    | 0.01       | 0.24       | 0.58                                  | 0.028                     | 0.0062                    | 0.017                     | ND                        | <0.050                    |
| Chrysene                      | µg/g | 2.8  | 0.014                     | 0.013      | 0.45       | 1.2                                   | 0.05                      | 0.011                     | 0.035                     | ND                        | <0.050                    |
| Dibenz(a,h)anthracene         | µg/g | 0.1  | ND                        | <0.050     | 0.074      | 0.17                                  | 0.0097                    | ND                        | 0.0054                    | ND                        | <0.050                    |
| Fluoranthene                  | µg/g | 0.56   | 0.041                     | 0.032      | 0.97       | 2.9                                   | 0.13                      | 0.03                      | 0.089                     | ND                        | <0.050                    |
| Fluorene                      | µg/g | 0.12   | ND                        | <0.30      | 0.045      | 0.31                                  | 0.0063                    | ND                        | ND                        | ND                        | <0.050                    |
| Indeno(1,2,3-cd)pyrene        | µg/g | 0.23   | 0.011                     | 0.02       | 0.29       | 0.61                                  | 0.036                     | 0.008                     | 0.025                     | ND                        | <0.050                    |
| 1 Methlynaphthalene           | µg/g | 0.59 <sup>(2)</sup>                                | ND                        | <0.050     | 0.0071     | 0.063                                 | <0.0050                   | ND                        | ND                        | ND                        | <0.050                    |
| 2 Methlynaphthalene           | µg/g | 0.59 <sup>(2)</sup>                                | ND                        | <0.070     | 0.0094     | 0.12                                  | <0.0050                   | ND                        | ND                        | ND                        | <0.050                    |
| 1 and 2 Methlynaphthalene (2) | µg/g | 0.59   | ND                        | <0.050     | 0.016      | 0.18                                  | <0.0071                   | ND                        | ND                        | ND                        | <0.071                    |
| Naphthalene                   | µg/g | 0.09   | ND                        | <0.050     | 0.026      | 0.49                                  | <0.0050                   | ND                        | ND                        | ND                        | <0.050                    |
| Phenanthrene                  | µg/g | 0.69   | 0.02                      | 0.0089     | 0.42       | 2                                     | 0.062                     | 0.013                     | 0.039                     | ND                        | <0.050                    |
| Pyrene                        | µg/g | 1  | 0.034                     | 0.033      | 0.8        | 2.4                                   | 0.1                       | 0.025                     | 0.072                     | ND                        | <0.050                    |



| Sample Location               | Unit | MECP Table 1 Standard (R/P/I/I/C/C) <sup>(1)</sup> | Sewer Trench Floor |            |                          |                          |                          |                          |                          |
|-------------------------------|------|--|--------------------|------------|--------------------------|--------------------------|--------------------------|--------------------------|--------------------------|
| Sample ID                     |      |  | VS-ST-F1           | VS-ST-F2   | VS-EST-F1 <sup>(3)</sup> | VS-EST-F2 <sup>(3)</sup> | VS-EST-F3 <sup>(3)</sup> | VS-EST-F4 <sup>(3)</sup> | VS-EST-F5 <sup>(3)</sup> |
| Date Sampled                  |      |  | 2022-12-07         | 2022-12-08 | 2022-11-01               | 2022-11-01               | 2022-11-03               | 2022-11-08               | 2022-12-01               |
| Sample Depth (mbgs)           | mbgs |  | 4-4.2              | 3.8-4.2    | 3.8-4.2                  | 3.8-4.2                  | 4.0                      | 2.0                      | 4.0-4.3                  |
| Parameter                     |      |  |                    |            |                          |                          |                          |                          |                          |
| Acenaphthene                  | µg/g | 0.072  | 0.008              | <0.0050    | ND                       | ND                       | ND                       | <0.0050                  | ND                       |
| Acenaphthylene                | µg/g | 0.093  | <0.0050            | <0.0050    | ND                       | ND                       | ND                       | 0.014                    | ND                       |
| Anthracene                    | µg/g | 0.16   | 0.017              | <0.0050    | ND                       | ND                       | ND                       | 0.021                    | ND                       |
| Benz(a)anthracene             | µg/g | 0.36   | 0.054              | <0.0050    | ND                       | ND                       | ND                       | 0.075                    | ND                       |
| Benzo(a)pyrene                | µg/g | 0.3  | 0.05               | <0.0050    | ND                       | ND                       | ND                       | 0.068                    | ND                       |
| Benzo(b)fluoranthene          | µg/g | 0.47   | 0.07               | <0.0050    | ND                       | ND                       | ND                       | 0.081                    | ND                       |
| Benzo(g,h,i)perylene          | µg/g | 0.68   | 0.03               | <0.0050    | ND                       | ND                       | ND                       | 0.041                    | ND                       |
| Benzo(k)fluoranthene          | µg/g | 0.48   | 0.026              | <0.0050    | ND                       | ND                       | ND                       | 0.031                    | ND                       |
| Chrysene                      | µg/g | 2.8  | 0.044              | <0.0050    | ND                       | ND                       | ND                       | 0.051                    | ND                       |
| Dibenz(a,h)anthracene         | µg/g | 0.1  | 0.0071             | <0.0050    | ND                       | ND                       | ND                       | 0.012                    | ND                       |
| Fluoranthene                  | µg/g | 0.56   | 0.12               | <0.0050    | 0.019                    | 0.019                    | ND                       | 0.13                     | ND                       |
| Fluorene                      | µg/g | 0.12   | 0.0071             | <0.0050    | ND                       | ND                       | ND                       | <0.0050                  | ND                       |
| Indeno(1,2,3-cd)pyrene        | µg/g | 0.23   | 0.031              | <0.0050    | ND                       | ND                       | ND                       | 0.041                    | ND                       |
| 1 Methlynaphthalene           | µg/g | 0.59 <sup>(2)</sup>                                | <0.0050            | <0.0050    | ND                       | ND                       | ND                       | <0.0050                  | ND                       |
| 2 Methlynaphthalene           | µg/g | 0.59 <sup>(2)</sup>                                | <0.0050            | <0.0050    | ND                       | ND                       | ND                       | <0.0050                  | ND                       |
| 1 and 2 Methlynaphthalene (2) | µg/g | 0.59   | <0.071             | <0.071     | ND                       | ND                       | ND                       | <0.0071                  | ND                       |
| Naphthalene                   | µg/g | 0.09   | <0.0050            | <0.0050    | ND                       | ND                       | ND                       | <0.0050                  | ND                       |
| Phenanthrene                  | µg/g | 0.69   | 0.073              | <0.0050    | 0.014                    | 0.014                    | ND                       | 0.025                    | ND                       |
| Pyrene                        | µg/g | 1  | 0.096              | <0.0050    | 0.015                    | 0.015                    | ND                       | 0.12                     | ND                       |

| Sample Location               | Unit | MECP Table 1 Standard (R/P/I/I/C/C) <sup>(1)</sup> | BLD137                        |                                |                                |                                |  |                                |                                |                                |                               |                                |
|-------------------------------|------|--|-------------------------------|--------------------------------|--------------------------------|--------------------------------|--|--------------------------------|--------------------------------|--------------------------------|-------------------------------|--------------------------------|
| Sample ID                     |      |  | BLD 137 NW SS4 <sup>(3)</sup> | BLD 137 NW SS34 <sup>(3)</sup> | BLD 137 NW SS44 <sup>(3)</sup> | BLD 137 NW SS48 <sup>(4)</sup> | BLD 137 NW DUP1 (Dup. of NW SS48) <sup>(4)</sup> | BLD 137 NW SS53 <sup>(3)</sup> | BLD 137 NW SS60 <sup>(3)</sup> | BLD 137 NW SS66 <sup>(3)</sup> | BLD 137 SW SS6 <sup>(4)</sup> | BLD 137 SW SS37 <sup>(4)</sup> |
| Date Sampled                  |      |  | 16-Oct-14                     | 16-Oct-14                      | 16-Oct-14                      | 06-Nov-21                      | 06-Nov-21  | 12-Nov-14                      | 12-Nov-14                      | 12-Nov-14                      | 10-Nov-14                     | 10-Nov-14                      |
| Sample Depth (mbgs)           | mbgs |  | 1.0                           | 2.9                            | 2.1                            | 0.7                            | 0.7  | 1.2                            | 0.9                            | 2.0                            | 5.2                           | 3.8                            |
| Parameter                     |      |  |                               |                                |                                |                                |  |                                |                                |                                |                               |                                |
| Acenaphthene                  | µg/g | 0.072  | 0.024                         | <0.005                         | <0.005                         | 0.015                          | 0.011  | <0.0050                        | <0.0050                        | 0.0073                         | 0.030                         | 0.0092                         |
| Acenaphthylene                | µg/g | 0.093  | 0.013                         | <0.005                         | <0.005                         | 0.012                          | 0.0097   | <0.0050                        | 0.0072                         | <0.0050                        | <0.0050                       | <0.0050                        |
| Anthracene                    | µg/g | 0.16   | 0.066                         | <0.005                         | <0.005                         | 0.05                           | 0.036  | <0.0050                        | 0.0077                         | 0.018                          | 0.031                         | 0.020                          |
| Benz(a)anthracene             | µg/g | 0.36   | 0.19                          | <0.005                         | 0.099                          | 0.13                           | 0.10   | 0.0083                         | 0.036                          | 0.056                          | 0.029                         | <0.0050                        |
| Benzo(a)pyrene                | µg/g | 0.3  | 0.15                          | <0.005                         | 0.077                          | 0.11                           | 0.082  | 0.0088                         | 0.037                          | 0.05                           | 0.023                         | <0.0050                        |
| Benzo(b)fluoranthene          | µg/g | 0.47   | 0.21                          | <0.005                         | 0.012                          | 0.16                           | 0.12   | 0.017                          | 0.051                          | 0.069                          | 0.034                         | <0.0050                        |
| Benzo(g,h,i)perylene          | µg/g | 0.68   | 0.082                         | <0.005                         | 0.0055                         | 0.065                          | 0.048  | 0.0088                         | 0.022                          | 0.03                           | 0.018                         | <0.0050                        |
| Benzo(k)fluoranthene          | µg/g | 0.48   | 0.077                         | <0.005                         | <0.005                         | 0.053                          | 0.040  | <0.0050                        | 0.017                          | 0.022                          | 0.011                         | <0.0050                        |
| Chrysene                      | µg/g | 2.8  | 0.16                          | <0.005                         | 0.083                          | 0.13                           | 0.099  | 0.013                          | 0.039                          | 0.055                          | 0.033                         | <0.0050                        |
| Dibenz(a,h)anthracene         | µg/g | 0.1  | 0.022                         | <0.005                         | <0.005                         | 0.017                          | 0.012  | <0.0050                        | 0.0053                         | 0.0087                         | <0.0050                       | <0.0050                        |
| Fluoranthene                  | µg/g | 0.56   | 0.41                          | <0.005                         | 0.023                          | 0.32                           | 0.23   | 0.020                          | 0.064                          | 0.12                           | 0.070                         | 0.0056                         |
| Fluorene                      | µg/g | 0.12   | 0.025                         | <0.005                         | <0.005                         | 0.015                          | 0.011  | <0.0050                        | <0.0050                        | 0.0053                         | 0.037                         | 0.017                          |
| Indeno(1,2,3-cd)pyrene        | µg/g | 0.23   | 0.09                          | <0.005                         | 0.0055                         | 0.069                          | 0.052  | 0.0083                         | 0.023                          | 0.031                          | 0.016                         | <0.0050                        |
| 1 Methlynaphthalene           | µg/g | 0.59 <sup>(2)</sup>                                | <0.005                        | <0.005                         | <0.005                         | <0.050                         | <0.050   | <0.0050                        | <0.0050                        | <0.0050                        | 0.0096                        | 0.0092                         |
| 2 Methlynaphthalene           | µg/g | 0.59 <sup>(2)</sup>                                | <0.005                        | <0.005                         | <0.005                         | <0.050                         | <0.050   | <0.0050                        | <0.0050                        | <0.0050                        | 0.017                         | 0.0066                         |
| 1 and 2 Methlynaphthalene (2) | µg/g | 0.59   | <0.005                        | <0.005                         | <0.005                         | --                             | --   | --                             | --                             | --                             | 0.0266                        | 0.0158                         |
| Naphthalene                   | µg/g | 0.09   | 0.0056                        | <0.005                         | <0.005                         | <0.050                         | <0.050   | <0.0050                        | <0.0050                        | <0.0050                        | <0.020                        | 0.012                          |
| Phenanthrene                  | µg/g | 0.69   | 0.28                          | <0.005                         | 0.014                          | 0.15                           | 0.10   | 0.012                          | 0.023                          | 0.062                          | 0.073                         | 0.0066                         |
| Pyrene                        | µg/g | 1  | 0.32                          | <0.005                         | 0.18                           | 0.26                           | 0.18   | 0.017                          | 0.057                          | 0.096                          | 0.059                         | 0.016                          |



| Sample Location               | Unit | MECP Table 1 Standard (R/P/I/I/C/C) <sup>(1)</sup> | BLD137                         |                                |                                |                                |                                |                                |                               |                 |                 |                                |
|-------------------------------|------|--|--------------------------------|--------------------------------|--------------------------------|--------------------------------|--------------------------------|--------------------------------|-------------------------------|-----------------|-----------------|--------------------------------|
| Sample ID                     |      |  | BLD 137 SW SS46 <sup>(3)</sup> | BLD 137 SW SS62 <sup>(3)</sup> | BLD 137 SW SS79 <sup>(4)</sup> | BLD 137 SW SS96 <sup>(4)</sup> | BLD 137 EW SS11 <sup>(4)</sup> | BLD 137 EW SS31 <sup>(3)</sup> | BLD 137 WW SS9 <sup>(4)</sup> | BLD 137 WW SS19 | BLD 137 WW SS30 | BLD 137 WW SS50 <sup>(4)</sup> |
| Date Sampled                  |      |  | 10-Nov-14                      | 10-Nov-14                      | 12-Dec-14                      | 12-Dec-14                      | 04-Nov-14                      | 04-Nov-14                      | 10-Nov-14                     | 10-Nov-14       | 10-Nov-14       | 15-Jan-15                      |
| Sample Depth (mbgs)           | mbgs |  | 4.3                            | 4.0                            | 1.5                            | 0 to 1.5                       | 1.0                            | 1.9                            | 4.0                           | 1.4             | 2.0             | 5.0                            |
| Parameter                     |      |  |                                |                                |                                |                                |                                |                                |                               |                 |                 |                                |
| Acenaphthene                  | µg/g | 0.072  | <0.0050                        | <0.0050                        | <0.0050                        | <0.0050                        | <0.0050                        | <0.0050                        | 0.01                          | 0.0083          | <0.0050         | <0.02                          |
| Acenaphthylene                | µg/g | 0.093  | <0.0050                        | <0.0050                        | <0.0050                        | <0.0050                        | 0.058                          | <0.0050                        | 0.0064                        | 0.0065          | <0.0050         | <0.02                          |
| Anthracene                    | µg/g | 0.16   | <0.0050                        | <0.0050                        | <0.0050                        | <0.0050                        | 0.032                          | <0.0050                        | 0.062                         | 0.018           | <0.0050         | 0.03                           |
| Benz(a)anthracene             | µg/g | 0.36   | <0.0050                        | <0.0050                        | <0.0050                        | 0.0071                         | 0.11                           | <0.0050                        | 0.24                          | 0.056           | <0.0050         | 0.10                           |
| Benzo(a)pyrene                | µg/g | 0.3  | <0.0050                        | <0.0050                        | <0.0050                        | 0.0071                         | 0.14                           | <0.0050                        | 0.19                          | 0.051           | <0.0050         | 0.10                           |
| Benzo(b)fluoranthene          | µg/g | 0.47   | <0.0050                        | 0.0066                         | <0.0050                        | 0.011                          | 0.20                           | <0.0050                        | 0.27                          | 0.075           | <0.0050         | 0.15                           |
| Benzo(g,h,i)perylene          | µg/g | 0.68   | <0.0050                        | <0.0050                        | <0.0050                        | 0.0071                         | 0.17                           | <0.0050                        | 0.14                          | 0.034           | <0.0050         | 0.09                           |
| Benzo(k)fluoranthene          | µg/g | 0.48   | <0.0050                        | <0.0050                        | <0.0050                        | <0.0050                        | 0.075                          | <0.0050                        | 0.091                         | 0.025           | <0.0050         | 0.09                           |
| Chrysene                      | µg/g | 2.8  | <0.0050                        | 0.0066                         | <0.0050                        | 0.0065                         | 0.098                          | <0.0050                        | 0.19                          | 0.061           | <0.0050         | 0.14                           |
| Dibenz(a,h)anthracene         | µg/g | 0.1  | <0.0050                        | <0.0050                        | <0.0050                        | <0.0050                        | 0.035                          | <0.0050                        | 0.041                         | 0.010           | <0.0050         | 0.02                           |
| Fluoranthene                  | µg/g | 0.56   | <0.0050                        | 0.11                           | <0.0050                        | 0.015                          | 0.18                           | <0.0050                        | 0.41                          | 0.13            | <0.0050         | 0.24                           |
| Fluorene                      | µg/g | 0.12   | <0.0050                        | <0.0050                        | <0.0050                        | <0.0050                        | <0.0050                        | <0.0050                        | 0.012                         | 0.0071          | <0.0050         | <0.02                          |
| Indeno(1,2,3-cd)pyrene        | µg/g | 0.23   | <0.0050                        | <0.0050                        | <0.0050                        | <0.0050                        | 0.17                           | <0.0050                        | 0.14                          | 0.037           | <0.0050         | 0.05                           |
| 1 Methlynaphthalene           | µg/g | 0.59 <sup>(2)</sup>                                | <0.0050                        | <0.0050                        | <0.0050                        | <0.0050                        | <0.0050                        | <0.0050                        | <0.0050                       | <0.0050         | <0.0050         | <0.02                          |
| 2 Methlynaphthalene           | µg/g | 0.59 <sup>(2)</sup>                                | <0.0050                        | <0.0050                        | <0.0050                        | <0.0050                        | <0.0050                        | <0.0050                        | <0.0050                       | <0.0050         | <0.0050         | <0.02                          |
| 1 and 2 Methlynaphthalene (2) | µg/g | 0.59   | <0.0050                        | --                             | --                             | --                             | --                             | --                             | <0.0050                       | <0.0050         | <0.0050         | --                             |
| Naphthalene                   | µg/g | 0.09   | <0.0050                        | <0.0050                        | <0.0050                        | <0.0050                        | <0.0050                        | <0.0050                        | <0.0050                       | 0.0053          | <0.0050         | 0.010                          |
| Phenanthrene                  | µg/g | 0.69   | <0.0050                        | 0.0073                         | <0.0050                        | 0.0065                         | 0.041                          | <0.0050                        | 0.21                          | 0.087           | <0.0050         | 0.15                           |
| Pyrene                        | µg/g | 1  | <0.0050                        | 0.0086                         | <0.0050                        | 0.012                          | 0.15                           | <0.0050                        | 0.34                          | 0.10            | <0.0050         | 0.21                           |

| Sample Location               | Unit | MECP Table 1 Standard (R/P/I/I/C/C) <sup>(1)</sup> | BLD126     |                           |            |            |            |            |               |               |                |                |
|-------------------------------|------|--|------------|---------------------------|------------|------------|------------|------------|---------------|---------------|----------------|----------------|
| Sample ID                     |      |  | BLD126-2P1 | BLD126-2P2 <sup>(5)</sup> | BLD126-2P3 | BLD126-2P4 | BLD126-2P5 | BLD126-2P6 | BLD126-2 SS 7 | BLD126-2 SS17 | BLD126-2 SS 25 | BLD126-2 SS 30 |
| Date Sampled                  |      |  | 16-Sep-14  | 16-Sep-14                 | 16-Sep-14  | 16-Sep-14  | 16-Sep-14  | 16-Sep-14  | 16-Sep-14     | 26-Sep-14     | 26-Sep-14      | 26-Sep-14      |
| Sample Depth (mbgs)           | mbgs |  | 1.0        | 1.0                       | 0.5        | 0.5        | 0.3        | 0.5        | 0.3           | 1.0           | 1.0            | 1.0            |
| Parameter                     |      |  |            |                           |            |            |            |            |               |               |                |                |
| Acenaphthene                  | µg/g | 0.072  | <0.0050    | 0.11                      | <0.0050    | <0.0050    | <0.0050    | <0.0050    | <0.0050       | <0.0050       | <0.0050        | <0.0050        |
| Acenaphthylene                | µg/g | 0.093  | <0.0050    | <0.0050                   | <0.0050    | <0.0050    | 0.0062     | <0.0050    | <0.0050       | <0.0050       | <0.0050        | <0.0050        |
| Anthracene                    | µg/g | 0.16   | <0.0050    | 0.17                      | <0.0050    | <0.0050    | <0.0050    | <0.0050    | <0.0050       | <0.0050       | <0.0050        | <0.0050        |
| Benz(a)anthracene             | µg/g | 0.36   | 0.019      | 0.32                      | 0.016      | <0.0050    | 0.024      | 0.017      | 0.016         | <0.0050       | <0.0050        | <0.0050        |
| Benzo(a)pyrene                | µg/g | 0.3  | 0.019      | 0.2                       | 0.015      | 0.0052     | 0.029      | 0.022      | 0.015         | <0.0050       | <0.0050        | <0.0050        |
| Benzo(b)fluoranthene          | µg/g | 0.47   | 0.029      | 0.27                      | 0.022      | 0.0088     | 0.042      | 0.027      | 0.028         | 0.0076        | <0.0050        | 0.0075         |
| Benzo(g,h,i)perylene          | µg/g | 0.68   | 0.014      | 0.073                     | 0.010      | <0.0050    | 0.021      | 0.014      | 0.012         | <0.0050       | <0.0050        | <0.0050        |
| Benzo(k)fluoranthene          | µg/g | 0.48   | 0.011      | 0.11                      | 0.0077     | <0.0050    | 0.017      | 0.011      | 0.0088        | <0.0050       | <0.0050        | <0.0050        |
| Chrysene                      | µg/g | 2.8  | 0.02       | 0.26                      | 0.019      | 0.0062     | 0.024      | 0.017      | 0.023         | 0.0061        | <0.0050        | <0.0050        |
| Dibenz(a,h)anthracene         | µg/g | 0.1  | <0.0050    | 0.03                      | <0.0050    | <0.0050    | 0.0057     | <0.0050    | <0.0050       | <0.0050       | <0.0050        | <0.0050        |
| Fluoranthene                  | µg/g | 0.56   | 0.03       | 0.88                      | 0.029      | 0.0098     | 0.031      | 0.028      | 0.035         | 0.0052        | <0.0050        | <0.0050        |
| Fluorene                      | µg/g | 0.12   | <0.0050    | 0.12                      | <0.0050    | <0.0050    | <0.0050    | <0.0050    | <0.0050       | <0.0050       | <0.0050        | <0.0050        |
| Indeno(1,2,3-cd)pyrene        | µg/g | 0.23   | 0.014      | 0.092                     | 0.0093     | <0.0050    | 0.021      | 0.015      | 0.012         | <0.0050       | <0.0050        | <0.0050        |
| 1 Methlynaphthalene           | µg/g | 0.59 <sup>(2)</sup>                                | 0.021      | 0.017                     | 0.039      | <0.0050    | <0.0050    | <0.0050    | <0.0050       | <0.0050       | <0.0050        | <0.0050        |
| 2 Methlynaphthalene           | µg/g | 0.59 <sup>(2)</sup>                                | 0.019      | 0.017                     | 0.036      | <0.0050    | <0.0050    | <0.0050    | <0.0050       | <0.0050       | <0.0050        | <0.0050        |
| 1 and 2 Methlynaphthalene (2) | µg/g | 0.59   | 0.04       | 0.034                     | 0.075      | --         | --         | --         | --            | --            | --             | --             |
| Naphthalene                   | µg/g | 0.09   | 0.011      | 0.015                     | 0.020      | <0.0050    | <0.0050    | <0.0050    | <0.0050       | <0.0050       | <0.0050        | <0.0050        |
| Phenanthrene                  | µg/g | 0.69   | 0.029      | 0.94                      | 0.047      | 0.0077     | 0.0099     | 0.017      | 0.018         | <0.0050       | <0.0050        | <0.0050        |
| Pyrene                        | µg/g | 1  | 0.027      | 0.61                      | 0.025      | 0.0088     | 0.027      | 0.024      | 0.028         | <0.0050       | <0.0050        | <0.0050        |



**Notes:**

G / S Guideline / Standard

-- Not analyzed

ND Not detected

**Value** Parameters exceeds Table 1 criteria.

Value RDL exceeds Table 1 criteria

Sample location has been excavated and removed from site.

- (1) Ontario Reg 153/04 (2011) Table 1: Full Depth Background Site Condition Standards, Residential/Parkland/Institutional/Industrial/Commercial/Community Property Use for Soil.
- (2) The methylnaphthalene standards are applicable to both 1-methylnaphthalene and 2-methylnaphthalene, with the provision that if both are detected, the sum of the two must not exceed the standard.
- (3) Off-site sample location included for reference purposes only
- (4) Location of sample not provided in source report
- (5) As noted in DST Remediation Report, exceedance remediated with confirmatory sample BLD 126-2 SS30 (2017 DST Remediation Report)
- (6) No date was provided in the source report.

Table G1c - Verification Samples Analytical Results (Metals and Inorganics)

| Sample Location               | Unit     | MECP Table 1 Standard (R/P/I/I/C/C) <sup>(1)</sup> | Western Sewer Trench |             |             |             |             |            |  |            |            |
|-------------------------------|----------|--|----------------------|-------------|-------------|-------------|-------------|------------|--|------------|------------|
|                               |          |  | VS-WST-NW-1          | VS-WST-NW-2 | VS-WST-SW-1 | VS-WST-SW-2 | VS-WST-WW-1 | VS-WST-WW2 | VS-WST-DUP-1 (Duplicate of VS-WST-WW2) | VS-WST-WW3 | VS-WST-WW4 |
| Date Sampled                  |          |  | 10/27/2022           | 10/27/2022  | 10/27/2022  | 10/27/2022  | 10/27/2022  | 2022-11-01 | 2022-11-01                             | 2022-11-01 | 2022-11-07 |
| Sample Depth (mbgs)           | mbgs     |  | 1.9-2.1              | 1.0-1.2     | 2.0-2.1     | 1.3-1.4     | 0.9-1.1     | 1.5        | 1.5                                    | 2.0        | 2.0        |
| Antimony                      | µg/g     | 1.3  | <0.2                 | <0.2        | <0.2        | <0.2        | <0.2        | <0.2       | <0.2                                   | <0.2       | 0.23       |
| Arsenic                       | µg/g     | 18   | 1.7                  | 1.1         | 2.1         | 2.7         | 3.4         | 4          | 3.9                                    | 4.1        | 2.9        |
| Barium                        | µg/g     | 220  | 65                   | 410         | 220         | 94          | 82          | 76         | 83                                     | 90         | 78         |
| Beryllium                     | µg/g     | 2.5  | 0.44                 | 1.1         | 0.69        | 0.4         | 0.48        | 0.45       | 0.41                                   | 0.52       | 0.48       |
| Boron                         | µg/g     | 36   | ND                   | 6.4         | ND          | 5.3         | 5.7         | 5.6        | 5.4                                    | 6.4        | 5.6        |
| Boron (Hot Water Extractable) | µg/g     | --   | --                   | --          | --          | --          | --          | --         | --                                     | --         | --         |
| Cadmium                       | µg/g     | 1.2  | 0.12                 | 0.2         | 0.15        | 0.22        | 0.27        | 0.3        | 0.26                                   | 0.24       | 0.21       |
| Calcium                       | µg/g     | --   | --                   | --          | --          | --          | --          | --         | --                                     | --         | --         |
| Chromium (Total)              | µg/g     | 70   | 24                   | 120         | 60          | 21          | 24          | 22         | 22                                     | 29         | 24         |
| Cobalt                        | µg/g     | 21   | 8.5                  | 24          | 15          | 8.2         | 9.3         | 8.4        | 8.6                                    | 11         | 8.9        |
| Copper                        | µg/g     | 92   | 11                   | 43          | 35          | 16          | 17          | 22         | 14                                     | 43         | 17         |
| Iron                          | µg/g     | --   | --                   | --          | --          | --          | --          | --         | --                                     | --         | --         |
| Lead                          | µg/g     | 120  | 10                   | 13          | 11          | 23          | 24          | 18         | 16                                     | 21         | 24         |
| Molybdenum                    | µg/g     | 2  | 0.64                 | 0.7         | 0.58        | 0.53        | 0.8         | 0.56       | 0.6                                    | 0.83       | 0.74       |
| Nickel                        | µg/g     | 82   | 16                   | 68          | 42          | 16          | 18          | 18         | 17                                     | 23         | 18         |
| Selenium                      | µg/g     | 1.5  | ND                   | ND          | ND          | ND          | ND          | 0.52       | 0.55                                   | ND         | <0.5       |
| Silver                        | µg/g     | 0.5  | ND                   | ND          | ND          | ND          | ND          | <0.2       | ND                                     | ND         | <0.2       |
| Sodium                        | µg/g     | NA   | --                   | --          | --          | --          | --          | --         | --                                     | --         | --         |
| Thallium                      | µg/g     | 1  | 0.14                 | 0.49        | 0.29        | 0.15        | 0.16        | 0.16       | 0.14                                   | 0.21       | 0.19       |
| Uranium                       | µg/g     | 2.5  | 0.54                 | 1.7         | 0.75        | 0.42        | 0.48        | 0.39       | 0.4                                    | 0.54       | 0.54       |
| Vanadium                      | µg/g     | 86   | 31                   | 100         | 57          | 26          | 30          | 28         | 26                                     | 32         | 30         |
| Zinc                          | µg/g     | 290  | 31                   | 160         | 56          | 50          | 50          | 500        | 420                                    | 48         | 49         |
| Chromium, Hexavalent          | µg/g     | 70   | --                   | --          | --          | --          | --          | --         | --                                     | --         | --         |
| Cyanide, Free                 | µg/g     | 0.051  | --                   | --          | --          | --          | --          | --         | --                                     | --         | --         |
| Mercury                       | µg/g     | 0.27   | --                   | --          | --          | --          | --          | --         | --                                     | --         | --         |
| Electrical Conductivity (2:1) | mS/cm    | 0.57   | --                   | --          | --          | --          | --          | --         | --                                     | --         | --         |
| Sodium Adsorption Ratio       | NA       | --   | --                   | --          | --          | --          | --          | --         | --                                     | --         | --         |
| pH, 2:1 CaCl2 Extraction      | pH Units | --   | --                   | --          | --          | --          | --          | --         | --                                     | --         | --         |





Table G1c - Verification Samples Analytical Results (Metals and Inorganics)

| Sample Location               | Unit     | MECP Table 1 Standard (R/P/I/I/C/C) <sup>(1)</sup> | Eastern Sewer Trench      |            |            |                                       |                           |                           |                           |                           |                           |
|-------------------------------|----------|--|---------------------------|------------|------------|---------------------------------------|---------------------------|---------------------------|---------------------------|---------------------------|---------------------------|
|                               |          |  | VS-EST-NW1 <sup>(2)</sup> | VS-EST-NW2 | VS-EST-SW1 | VS-EST-DUP1 (Duplicate of VS-EST-SW1) | VS-EST-SW2 <sup>(2)</sup> | VS-EST-EW1 <sup>(2)</sup> | VS-EST-EW2 <sup>(2)</sup> | VS-EST-EW3 <sup>(2)</sup> | VS-EST-EW4 <sup>(2)</sup> |
| Sample ID                     |          |  | 2022-11-01                | 2022-11-07 | 2022-11-03 | 2022-11-03                            | 2022-11-08                | 2022-11-01                | 2022-11-01                | 2022-11-03                | 2022-11-09                |
| Date Sampled                  |          |  |                           |            |            |                                       |                           |                           |                           |                           |                           |
| Sample Depth (mbgs)           | mbgs     |  | 2.0                       | 2.0        | 3.0        | 3.0                                   | 2.0                       | 2.5                       | 2.5                       | 3.0                       | 2.0                       |
| Antimony                      | µg/g     | 1.3  | <0.2                      | ND         | <0.2       | <0.2                                  | <0.2                      | <0.2                      | <0.2                      | <0.2                      | <0.2                      |
| Arsenic                       | µg/g     | 18   | 1.4                       | 1.4        | 1.6        | 1.4                                   | 1.4                       | 1.6                       | 1.4                       | 1                         | 1.1                       |
| Barium                        | µg/g     | 220  | 240                       | 250        | 230        | 250                                   | 140                       | 150                       | 190                       | 110                       | 250                       |
| Beryllium                     | µg/g     | 2.5  | 0.65                      | 0.67       | 0.65       | 0.69                                  | 0.54                      | 0.53                      | 0.56                      | 0.3                       | 0.67                      |
| Boron                         | µg/g     | 36   | 6.2                       | 5.9        | 5.6        | 5.5                                   | 7.2                       | 6.5                       | 6.4                       | ND                        | 6.5                       |
| Boron (Hot Water Extractable) | µg/g     | --   | --                        | --         | --         | --                                    | --                        | --                        | --                        | --                        | --                        |
| Cadmium                       | µg/g     | 1.2  | 0.12                      | 0.11       | 0.19       | 0.13                                  | <0.1                      | 0.1                       | 0.13                      | <0.1                      | 0.15                      |
| Calcium                       | µg/g     | --   | --                        | --         | --         | --                                    | --                        | --                        | --                        | --                        | --                        |
| Chromium (Total)              | µg/g     | 70   | 80                        | 80         | 72         | 76                                    | 42                        | 50                        | 54                        | 29                        | 69                        |
| Cobalt                        | µg/g     | 21   | 18                        | 18         | 17         | 18                                    | 12                        | 14                        | 14                        | 7.8                       | 17                        |
| Copper                        | µg/g     | 92   | 36                        | 37         | 35         | 37                                    | 24                        | 25                        | 29                        | 15                        | 36                        |
| Iron                          | µg/g     | --   | --                        | --         | --         | --                                    | --                        | --                        | --                        | --                        | --                        |
| Lead                          | µg/g     | 120  | 9.4                       | 9.3        | 15         | 13                                    | 13                        | 10                        | 11                        | 7.2                       | 13                        |
| Molybdenum                    | µg/g     | 2  | 0.62                      | 0.66       | 0.64       | 0.63                                  | 0.59                      | 0.57                      | 0.54                      | <0.5                      | 0.73                      |
| Nickel                        | µg/g     | 82   | 47                        | 46         | 43         | 45                                    | 28                        | 32                        | 33                        | 16                        | 41                        |
| Selenium                      | µg/g     | 1.5  | ND                        | <0.5       | <0.5       | <0.5                                  | <0.5                      | ND                        | ND                        | <0.5                      | <0.5                      |
| Silver                        | µg/g     | 0.5  | ND                        | <0.2       | <0.2       | <0.2                                  | <0.2                      | ND                        | ND                        | <0.2                      | <0.2                      |
| Sodium                        | µg/g     | NA   | --                        | --         | --         | --                                    | --                        | --                        | --                        | --                        | --                        |
| Thallium                      | µg/g     | 1  | 0.32                      | 0.37       | 0.31       | 0.34                                  | 0.23                      | 0.25                      | 0.27                      | 0.12                      | 0.33                      |
| Uranium                       | µg/g     | 2.5  | 0.86                      | 0.85       | 0.93       | 0.92                                  | 0.71                      | 0.71                      | 0.84                      | 0.6                       | 0.95                      |
| Vanadium                      | µg/g     | 86   | 77                        | 76         | 74         | 77                                    | 46                        | 52                        | 59                        | 35                        | 77                        |
| Zinc                          | µg/g     | 290  | 90                        | 91         | 100        | 110                                   | 57                        | 60                        | 76                        | 34                        | 140                       |
| Chromium, Hexavalent          | µg/g     | 70   | --                        | --         | --         | --                                    | --                        | --                        | --                        | --                        | --                        |
| Cyanide, Free                 | µg/g     | 0.051  | --                        | --         | --         | --                                    | --                        | --                        | --                        | --                        | --                        |
| Mercury                       | µg/g     | 0.27   | --                        | --         | --         | --                                    | --                        | --                        | --                        | --                        | --                        |
| Electrical Conductivity (2:1) | mS/cm    | 0.57   | --                        | --         | --         | --                                    | --                        | --                        | --                        | --                        | --                        |
| Sodium Adsorption Ratio       | NA       | --   | --                        | --         | --         | --                                    | --                        | --                        | --                        | --                        | --                        |
| pH, 2:1 CaCl2 Extraction      | pH Units | --   | --                        | --         | --         | --                                    | --                        | --                        | --                        | --                        | --                        |



| Sample Location               | Unit     | MECP Table 1 Standard (R/P/I/I/C/C) <sup>(1)</sup> | Sewer Trench Floor |            |                          |                          |                          |                          |                          |
|-------------------------------|----------|--|--------------------|------------|--------------------------|--------------------------|--------------------------|--------------------------|--------------------------|
| Sample ID                     |          |  | VS-ST-F1           | VS-ST-F2   | VS-EST-F1 <sup>(2)</sup> | VS-EST-F2 <sup>(2)</sup> | VS-EST-F3 <sup>(2)</sup> | VS-EST-F4 <sup>(2)</sup> | VS-EST-F5 <sup>(2)</sup> |
| Date Sampled                  |          |  | 2022-12-07         | 2022-12-08 | 2022-11-01               | 2022-11-01               | 2022-11-03               | 2022-11-08               | 2022-12-01               |
| Sample Depth (mbgs)           | mbgs     |  | 4-4.2              | 3.8-4.2    | 3.8-4.2                  | 3.8-4.2                  | 4.0                      | 2.0                      | 4.0-4.3                  |
| Antimony                      | µg/g     | 1.3  | <0.2               | <0.2       | <0.2                     | <0.2                     | <0.2                     | <0.2                     | <0.2                     |
| Arsenic                       | µg/g     | 18   | 1.4                | <1.0       | 2.3                      | 1.2                      | <1.0                     | 5.3                      | 2                        |
| Barium                        | µg/g     | 220  | 150                | 150        | 110                      | 360                      | 65                       | 70                       | 150                      |
| Beryllium                     | µg/g     | 2.5  | 0.52               | 0.39       | 0.4                      | 0.78                     | 0.27                     | 0.3                      | 0.45                     |
| Boron                         | µg/g     | 36   | 5.2                | <5.0       | ND                       | 6.9                      | <5.0                     | 9.2                      | 8.4                      |
| Boron (Hot Water Extractable) | µg/g     | --   | --                 | --         | --                       | --                       | --                       | --                       | --                       |
| Cadmium                       | µg/g     | 1.2  | 0.29               | <0.1       | 0.13                     | 0.15                     | <0.1                     | <0.1                     | 0.13                     |
| Calcium                       | µg/g     | --   | --                 | --         | --                       | --                       | --                       | --                       | --                       |
| Chromium (Total)              | µg/g     | 70   | 46                 | 37         | 28                       | 120                      | 22                       | 17                       | 25                       |
| Cobalt                        | µg/g     | 21   | 11                 | 9.5        | 8.8                      | 25                       | 6.5                      | 11                       | 12                       |
| Copper                        | µg/g     | 92   | 25                 | 19         | 15                       | 54                       | 8.5                      | 13                       | 18                       |
| Iron                          | µg/g     | --   | --                 | --         | --                       | --                       | --                       | --                       | --                       |
| Lead                          | µg/g     | 120  | 16                 | 6.5        | 9.1                      | 9                        | 5.4                      | 26                       | 19                       |
| Molybdenum                    | µg/g     | 2  | <0.5               | <0.5       | ND                       | 0.96                     | <0.5                     | 6.1                      | 0.87                     |
| Nickel                        | µg/g     | 82   | 29                 | 21         | 18                       | 67                       | 14                       | 18                       | 24                       |
| Selenium                      | µg/g     | 1.5  | <0.5               | <0.5       | ND                       | ND                       | <0.5                     | <0.5                     | <0.5                     |
| Silver                        | µg/g     | 0.5  | <0.2               | <0.2       | ND                       | ND                       | <0.2                     | <0.2                     | <0.2                     |
| Sodium                        | µg/g     | NA   | --                 | --         | --                       | --                       | --                       | --                       | --                       |
| Thallium                      | µg/g     | 1  | 0.25               | 0.17       | 0.16                     | 0.47                     | 0.089                    | 0.3                      | 0.3                      |
| Uranium                       | µg/g     | 2.5  | 0.69               | 0.6        | 0.59                     | 1.1                      | 0.47                     | 0.74                     | 0.65                     |
| Vanadium                      | µg/g     | 86   | 49                 | 41         | 36                       | 110                      | 24                       | 18                       | 25                       |
| Zinc                          | µg/g     | 290  | 80                 | 41         | 45                       | 130                      | 39                       | 26                       | 39                       |
| Chromium, Hexavalent          | µg/g     | 70   | --                 | --         | --                       | --                       | --                       | --                       | --                       |
| Cyanide, Free                 | µg/g     | 0.051  | --                 | --         | --                       | --                       | --                       | --                       | --                       |
| Mercury                       | µg/g     | 0.27   | --                 | --         | --                       | --                       | --                       | --                       | --                       |
| Electrical Conductivity (2:1) | mS/cm    | 0.57   | --                 | --         | --                       | --                       | --                       | --                       | --                       |
| Sodium Adsorption Ratio       | NA       | --   | --                 | --         | --                       | --                       | --                       | --                       | --                       |
| pH, 2:1 CaCl2 Extraction      | pH Units | --   | --                 | --         | --                       | --                       | --                       | --                       | --                       |

| Sample Location               | Unit     | MECP Table 1 Standard (R/P/I/I/C/C) <sup>(1)</sup> | TP31       |            |                         |                          |                          |                          |   |                          |                          |                          |                          |                          |
|-------------------------------|----------|--|------------|------------|-------------------------|--------------------------|--------------------------|--------------------------|---|--------------------------|--------------------------|--------------------------|--------------------------|--------------------------|
|                               |          |  | TP31 SS1   | TP31 SS5   | TP31 SS9 <sup>(2)</sup> | TP31 SS14 <sup>(2)</sup> | TP31 SS20 <sup>(2)</sup> | TP31 SS28 <sup>(2)</sup> | TP31 DUP1 (dup of TP31 SS28) <sup>(2)</sup> | TP31 SS30 <sup>(2)</sup> | TP31 SS36 <sup>(2)</sup> | TP31 SGS2 <sup>(2)</sup> | TP31 SGS3 <sup>(2)</sup> | TP31 SGS5 <sup>(2)</sup> |
| Date Sampled                  |          |  | 2014-09-16 | 2014-09-16 | 2014-09-16              | 2014-09-16               | 2014-09-16               | 2014-09-16               | 2014-09-16                                  | 2014-09-16               | 2014-09-16               | 2014-09-16               | 2014-09-16               | 2014-09-16               |
| Sample Depth (mbgs)           | mbgs     |  | 0.35       | 1.00       | 1.30                    | 1.10                     | 0.45                     | 1.10                     | 1.10  | 1.30                     | 1.40                     | 0.40                     | 0.90                     | 1.20                     |
| Antimony                      | µg/g     | 1.3  | <0.2       | <0.2       | <0.2                    | 0.25                     | <0.2                     | <0.2                     | <0.2  | <0.2                     | 0.26                     | <1                       | <1                       | <1                       |
| Arsenic                       | µg/g     | 18   | 2.0        | 2.7        | 1.9                     | 3.3                      | 4.5                      | 1.7                      | 2.2   | 1.8                      | 5.4                      | 1                        | <1                       | <1                       |
| Barium                        | µg/g     | 220  | 77         | 88         | 57                      | 78                       | 120                      | 72                       | 89  | 75                       | 83                       | 70                       | 20                       | 30                       |
| Beryllium                     | µg/g     | 2.5  | 0.49       | 0.30       | 0.30                    | 0.45                     | 0.60                     | 0.47                     | 0.51  | 0.29                     | 0.40                     | <0.5                     | <0.5                     | <0.5                     |
| Boron                         | µg/g     | 36   | <5.0       | 5.5        | <5.0                    | 6.9                      | 6.8                      | 5.4                      | 6.4   | <5.0                     | 5.3                      | --                       | --                       | --                       |
| Boron (Hot Water Extractable) | µg/g     | --   | --         | --         | --                      | --                       | --                       | --                       | --  | --                       | --                       | --                       | --                       | --                       |
| Cadmium                       | µg/g     | 1.2  | 0.11       | 0.14       | <0.1                    | 0.49                     | 0.28                     | <0.1                     | 0.23  | 0.13                     | 0.14                     | <0.5                     | <0.5                     | <0.5                     |
| Calcium                       | µg/g     | --   | --         | --         | --                      | --                       | --                       | --                       | --  | --                       | --                       | 7200                     | 4000                     | 7000                     |
| Chromium (Total)              | µg/g     | 70   | 12         | 11         | 15                      | 21                       | 20                       | 18                       | 18  | 12                       | 14                       | 15                       | <5                       | 5                        |
| Cobalt                        | µg/g     | 21   | 5.8        | 5.0        | 5.7                     | 7.1                      | 9.2                      | 7.1                      | 9.6   | 5.3                      | 6.5                      | 5                        | <5                       | <5                       |
| Copper                        | µg/g     | 92   | 8.9        | 8.8        | 12                      | 12                       | 16                       | 8.6                      | 12  | 11                       | 12                       | 15                       | 10                       | 10                       |
| Iron                          | µg/g     | --   | --         | --         | --                      | --                       | --                       | --                       | --  | --                       | --                       | 13000                    | 6800                     | 7800                     |
| Lead                          | µg/g     | 120  | 7.4        | 13         | 6.4                     | 18                       | 22                       | 11                       | 12  | 13                       | 15                       | 22                       | 2                        | 10                       |
| Molybdenum                    | µg/g     | 2  | 0.54       | 0.75       | <0.5                    | 1.5                      | 1.7                      | <0.5                     | 0.61  | 0.69                     | 1.4                      | <1                       | <1                       | <1                       |
| Nickel                        | µg/g     | 82   | 12         | 11         | 9.6                     | 16                       | 18                       | 13                       | 15  | 11                       | 14                       | 15                       | <5                       | 5                        |
| Selenium                      | µg/g     | 1.5  | <0.5       | <0.5       | <0.5                    | <0.5                     | <0.5                     | <0.5                     | <0.5  | <0.5                     | <0.5                     | <1                       | <1                       | <1                       |
| Silver                        | µg/g     | 0.5  | <0.2       | <0.2       | <0.2                    | <0.2                     | 0.25                     | <0.2                     | <0.2  | <0.2                     | <0.2                     | <0.3                     | <0.3                     | <0.3                     |
| Sodium                        | µg/g     | NA   | --         | --         | --                      | --                       | --                       | --                       | --  | --                       | --                       | <200                     | <200                     | <200                     |
| Thallium                      | µg/g     | 1  | 0.12       | 0.13       | 0.10                    | 0.15                     | 0.21                     | 0.11                     | 0.14  | 0.12                     | 0.16                     | <1                       | <1                       | <1                       |
| Uranium                       | µg/g     | 2.5  | 0.20       | 0.40       | 0.47                    | 0.48                     | 0.49                     | 0.39                     | 0.39  | 0.48                     | 0.51                     | --                       | --                       | --                       |
| Vanadium                      | µg/g     | 86   | 15         | 16         | 23                      | 26                       | 25                       | 22                       | 23  | 19                       | 21                       | 20                       | 10                       | 10                       |
| Zinc                          | µg/g     | 290  | 22         | 32         | 19                      | 280                      | 56                       | 35                       | 38  | 39                       | 42                       | 520                      | <20                      | 460                      |
| Chromium, Hexavalent          | µg/g     | 70   | --         | --         | --                      | --                       | --                       | --                       | --  | --                       | --                       | --                       | --                       | --                       |
| Cyanide, Free                 | µg/g     | 0.051  | --         | --         | --                      | --                       | --                       | --                       | --  | --                       | --                       | --                       | --                       | --                       |
| Mercury                       | µg/g     | 0.27   | --         | --         | --                      | --                       | --                       | --                       | --  | --                       | --                       | --                       | --                       | --                       |
| Electrical Conductivity (2:1) | mS/cm    | 0.57   | --         | --         | --                      | --                       | --                       | --                       | --  | --                       | --                       | --                       | --                       | --                       |
| Sodium Adsorption Ratio       | NA       | --   | --         | --         | --                      | --                       | --                       | --                       | --  | --                       | --                       | --                       | --                       | --                       |
| pH, 2:1 CaCl2 Extraction      | pH Units | --   | --         | --         | --                      | --                       | --                       | --                       | --  | --                       | --                       | --                       | --                       | --                       |



**Notes:**

G / S      Guideline / Standard  
 --          Not analyzed

|              |  |
|--------------|--|
| <b>Value</b> | Parameters exceeds Table 1 criteria.   |
| <u>Value</u> | RDL exceeds Table 1 criteria   |
|              | Sample location has been excavated and removed from site.  |
|              | Exceedance interpreted to be naturally occurring   |
| (1)          | Ontario Reg 153/04 (2011) Table 1: Full Depth Background Site Condition Standards, Residential/Parkland/Institutional/Industrial/Commercial/Community Property Use for Soil. |
| (2)          | Off-site sample location included for reference purposes only  |
| (3)          | No date was provided in the source report.   |

| Sample Location                     | Unit | MECP Table 1 Standard (R/P/I/I/C/C) <sup>(1)</sup> | SGP-SP1    | SGP-SP2    | SGP-SP3    | SGP-SP4    | SGP-SP5    |                                    | SGP-SP6    | SGP-SP7    | SGP-SP8    |
|-------------------------------------|------|--|------------|------------|------------|------------|------------|------------------------------------|------------|------------|------------|
| Sample ID                           |      |  | SGP-SP1    | SGP-SP2    | SGP-SP3    | SGP-SP4    | SGP-SP5    | SGP-SP-DUP1 (Duplicate of SGP-SG5) | SGP-SP6    | SGP-SP7    | SGP-SP8    |
| Date Sampled                        |      |  | 2022-11-10 | 2022-11-10 | 2022-11-10 | 2022-11-10 | 2022-11-10 | 2022-11-10                         | 2022-11-10 | 2022-11-10 | 2022-11-10 |
| Sample Depth (mbgs)                 | mbgs |  | 0.15       | 0.15       | 0.15       | 0.15       | 0.15       | 0.15                               | 0.15       | 0.15       | 0.15       |
| Parameter                           |      |  |            |            |            |            |            |                                    |            |            |            |
| Benzene                             | µg/g | 0.02   | <0.020     | <0.020     | <0.020     | <0.020     | <0.020     | <0.020                             | <0.020     | <0.020     | <0.020     |
| Toluene                             | µg/g | 0.20   | <0.020     | <0.020     | <0.020     | <0.020     | <0.020     | <0.020                             | <0.020     | <0.020     | <0.020     |
| Ethylbenzene                        | µg/g | 0.05   | <0.020     | <0.020     | <0.020     | <0.020     | <0.020     | <0.020                             | <0.020     | <0.020     | <0.020     |
| o-Xylene                            | µg/g | --   | <0.020     | <0.020     | <0.020     | <0.020     | <0.020     | <0.020                             | <0.020     | <0.020     | <0.020     |
| p+m-Xylene                          | µg/g | --   | <0.040     | <0.040     | <0.040     | <0.040     | <0.040     | <0.040                             | <0.040     | <0.040     | <0.040     |
| Xylenes (Total)                     | µg/g | 0.05   | <0.040     | <0.040     | <0.040     | <0.040     | <0.040     | <0.040                             | <0.040     | <0.040     | <0.040     |
| F1 (C6 to C10)                      | µg/g | 25   | <10        | <10        | <10        | <10        | <10        | <10                                | <10        | <10        | <10        |
| F1 (C6 to C10) minus BTEX           | µg/g | 25   | <10        | <10        | <10        | <10        | <10        | <10                                | <10        | <10        | <10        |
| F2 (C10 to C16)                     | µg/g | 10   | <10        | <10        | <10        | <10        | <10        | <10                                | <10        | <10        | <10        |
| F2 (C10 to C16) minus Naphthalene   | µg/g | 10   | --         | --         | --         | --         | --         | --                                 | --         | --         | --         |
| F3 (C16 to C34)                     | µg/g | 240  | <50        | <50        | 55         | <50        | <50        | <50                                | <50        | <50        | <50        |
| F3 (C16 to C34) minus PAHs          | µg/g | --   |            |            |            |            |            |                                    |            |            |            |
| F4 (C34 to C50)                     | µg/g | 120  | 55         | <50        | 90         | <50        | <50        | <50                                | <50        | <50        | <50        |
| Reached Baseline at C50             | --   | --   | Yes        | Yes        | Yes        | Yes        | Yes        | Yes                                | Yes        | Yes        | Yes        |
| Gravimetric Heavy Hydrocarbons      | µg/g | --   |            |            |            |            |            |                                    |            |            |            |
| Moisture Content                    | %    | --   | 5          | 8.3        | 15         | 3          | 7.5        | 7.7                                | 11         | 7.8        | 20         |
| TPgH (Gas C5-C10)                   | µg/g | --   | --         | --         | --         | --         | --         | --                                 | --         | --         | --         |
| TEH (Diesel, C10-C24)               | µg/g | --   | --         | --         | --         | --         | --         | --                                 | --         | --         | --         |
| TPH (Gas/Diesel)                    | µg/g | --   | --         | --         | --         | --         | --         | --                                 | --         | --         | --         |
| Petroleum Hydrocarbons (heavy oils) | µg/g | --   | --         | --         | --         | --         | --         | --                                 | --         | --         | --         |

| Sample Location                     |      | MECP Table 1 Standard (R/P/I/I/C/C) <sup>(1)</sup> | Golder 2020 Stockpile investigation |            |            |            |            |                            |            |            |            |            |            |
|-------------------------------------|------|--|-------------------------------------|------------|------------|------------|------------|----------------------------|------------|------------|------------|------------|------------|
| Sample ID                           | Unit |  | SA-1S                               | SA-1D      | SA-2S      | SA-2D      | SA-3S      | DUP-1 (field DUP of SA-3S) | SA-3D      | SA-4S      | SA-4D      | SA-5S      | SA-5D      |
| Date Sampled                        |      |  | 2021-02-19                          | 2021-02-19 | 2021-02-19 | 2021-02-19 | 2021-02-19 | 2021-02-19                 | 2021-02-19 | 2021-02-19 | 2021-02-19 | 2021-02-19 | 2021-02-19 |
| Sample Depth (mbgs)                 | mbgs |  | --                                  | --         | --         | --         | --         | --                         | --         | --         | --         | --         | --         |
| Parameter                           |      |  |                                     |            |            |            |            |                            |            |            |            |            |            |
| Benzene                             | µg/g | 0.02   | <0.02                               | <0.02      | <0.02      | <0.02      | <0.02      | <0.02                      | <0.02      | <0.02      | <0.02      | <0.02      | <0.02      |
| Toluene                             | µg/g | 0.20   | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05                      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Ethylbenzene                        | µg/g | 0.05   | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05                      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| o-Xylene                            | µg/g | --   | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05                      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| p+m-Xylene                          | µg/g | --   | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05                      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Xylenes (Total)                     | µg/g | 0.05   | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05                      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| F1 (C6 to C10)                      | µg/g | 25   | <5                                  | <5         | <5         | <5         | <5         | <5                         | <5         | <5         | <5         | <5         | <5         |
| F1 (C6 to C10) minus BTEX           | µg/g | 25   | <5                                  | <5         | <5         | <5         | <5         | <5                         | <5         | <5         | <5         | <5         | <5         |
| F2 (C10 to C16)                     | µg/g | 10   | <10                                 | <10        | <10        | <10        | <10        | <10                        | <10        | <10        | <10        | <10        | <10        |
| F2 (C10 to C16) minus Naphthalene   | µg/g | 10   | <10                                 | <10        | <10        | <10        | <10        | <10                        | <10        | <10        | <10        | <10        | <10        |
| F3 (C16 to C34)                     | µg/g | 240  | <50                                 | <50        | <50        | <50        | <50        | <50                        | <50        | <50        | <50        | <50        | <50        |
| F3 (C16 to C34) minus PAHs          | µg/g | --   | <50                                 | <50        | <50        | <50        | <50        | <50                        | <50        | <50        | <50        | <50        | <50        |
| F4 (C34 to C50)                     | µg/g | 120  | <50                                 | <50        | <50        | <50        | <50        | <50                        | <50        | <50        | <50        | <50        | <50        |
| Reached Baseline at C50             | --   | --   | --                                  | --         | --         | --         | --         | --                         | --         | --         | --         | --         | --         |
| Gravimetric Heavy Hydrocarbons      | µg/g | --   | --                                  | --         | --         | --         | --         | --                         | --         | --         | --         | --         | --         |
| Moisture Content                    | %    | --   | 22.8                                | 30.7       | 12.1       | 11.5       | 4.7        | 7.5                        | 21         | 26         | 32.9       | 29.7       | 29.9       |
| TPgH (Gas C5-C10)                   | µg/g | --   | --                                  | --         | --         | --         | --         | --                         | --         | --         | --         | --         | --         |
| TEH (Diesel, C10-C24)               | µg/g | --   | --                                  | --         | --         | --         | --         | --                         | --         | --         | --         | --         | --         |
| TPH (Gas/Diesel)                    | µg/g | --   | --                                  | --         | --         | --         | --         | --                         | --         | --         | --         | --         | --         |
| Petroleum Hydrocarbons (heavy oils) | µg/g | --   | --                                  | --         | --         | --         | --         | --                         | --         | --         | --         | --         | --         |

| Sample Location                     |      | MECP Table 1 Standard (R/P/I/I/C/C) <sup>(1)</sup> | Golder 2020 Stockpile investigation |            |            |            |            |            |            |            |            |            |                             |
|-------------------------------------|------|--|-------------------------------------|------------|------------|------------|------------|------------|------------|------------|------------|------------|-----------------------------|
| Sample ID                           | Unit |  | SA-6S                               | SA-6D      | SA-7S      | SA-7D      | SA-8S      | SA-8D      | SA-9S      | SA-9D      | SA-10S     | SA-10D     | DUP-2 (field DUP of SA-10D) |
| Date Sampled                        |      |  | 2021-02-19                          | 2021-02-19 | 2021-02-19 | 2021-02-19 | 2021-02-19 | 2021-02-19 | 2021-02-19 | 2021-02-19 | 2021-02-19 | 2021-02-19 | 2021-02-19                  |
| Sample Depth (mbgs)                 | mbgs |  | --                                  | --         | --         | --         | --         | --         | --         | --         | --         | --         | --                          |
| Parameter                           |      |  |                                     |            |            |            |            |            |            |            |            |            |                             |
| Benzene                             | µg/g | 0.02   | <0.02                               | <0.02      | <0.02      | <0.02      | <0.02      | <0.02      | <0.02      | <0.02      | <0.02      | <0.02      | <0.02                       |
| Toluene                             | µg/g | 0.20   | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05                       |
| Ethylbenzene                        | µg/g | 0.05   | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05                       |
| o-Xylene                            | µg/g | --   | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05                       |
| p+m-Xylene                          | µg/g | --   | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05                       |
| Xylenes (Total)                     | µg/g | 0.05   | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05                       |
| F1 (C6 to C10)                      | µg/g | 25   | <5                                  | <5         | <5         | <5         | <5         | <5         | <5         | <5         | <5         | <5         | <5                          |
| F1 (C6 to C10) minus BTEX           | µg/g | 25   | <5                                  | <5         | <5         | <5         | <5         | <5         | <5         | <5         | <5         | <5         | <5                          |
| F2 (C10 to C16)                     | µg/g | 10   | <10                                 | <10        | <10        | <10        | <10        | <10        | <10        | <10        | <10        | <10        | <10                         |
| F2 (C10 to C16) minus Naphthalene   | µg/g | 10   | <10                                 | <10        | <10        | <10        | <10        | <10        | <10        | <10        | <10        | <10        | <10                         |
| F3 (C16 to C34)                     | µg/g | 240  | <50                                 | <50        | <50        | <50        | <50        | <50        | <50        | <50        | <50        | <50        | <50                         |
| F3 (C16 to C34) minus PAHs          | µg/g | --   | <50                                 | <50        | <50        | <50        | <50        | <50        | <50        | <50        | <50        | <50        | <50                         |
| F4 (C34 to C50)                     | µg/g | 120  | <50                                 | <50        | <50        | <50        | <50        | <50        | <50        | <50        | <50        | <50        | <50                         |
| Reached Baseline at C50             | --   | --   | --                                  | --         | --         | --         | --         | --         | --         | --         | --         | --         | --                          |
| Gravimetric Heavy Hydrocarbons      | µg/g | --   | --                                  | --         | --         | --         | --         | --         | --         | --         | --         | --         | --                          |
| Moisture Content                    | %    | --   | 29                                  | 27.9       | 26.4       | 24.3       | 27.4       | 26         | 24.7       | 25.1       | 27.5       | 29         | 30                          |
| TPgH (Gas C5-C10)                   | µg/g | --   | --                                  | --         | --         | --         | --         | --         | --         | --         | --         | --         | --                          |
| TEH (Diesel, C10-C24)               | µg/g | --   | --                                  | --         | --         | --         | --         | --         | --         | --         | --         | --         | --                          |
| TPH (Gas/Diesel)                    | µg/g | --   | --                                  | --         | --         | --         | --         | --         | --         | --         | --         | --         | --                          |
| Petroleum Hydrocarbons (heavy oils) | µg/g | --   | --                                  | --         | --         | --         | --         | --         | --         | --         | --         | --         | --                          |

| Sample Location                     |      | MECP Table 1 Standard (R/P/I/I/C/C) <sup>(1)</sup> | Golder 2020 Stockpile investigation |            |            |            |            |            |            |            |            |            |            |
|-------------------------------------|------|--|-------------------------------------|------------|------------|------------|------------|------------|------------|------------|------------|------------|------------|
| Sample ID                           | Unit |  | SA-11S                              | SA-11D     | SA-12S     | SA-12D     | SA-13S     | SA-13D     | SA-14S     | SA-14D     | SA-15S     | SA-15D     | SA-16S     |
| Date Sampled                        |      |  | 2021-02-19                          | 2021-02-19 | 2021-02-19 | 2021-02-19 | 2021-02-19 | 2021-02-19 | 2021-02-19 | 2021-02-19 | 2021-02-19 | 2021-02-19 | 2021-02-19 |
| Sample Depth (mbgs)                 | mbgs |  | --                                  | --         | --         | --         | --         | --         | --         | --         | --         | --         | --         |
| Parameter                           |      |  |                                     |            |            |            |            |            |            |            |            |            |            |
| Benzene                             | µg/g | 0.02   | <0.02                               | <0.02      | <0.02      | <0.02      | <0.02      | <0.02      | <0.02      | <0.02      | <0.02      | <0.02      | <0.02      |
| Toluene                             | µg/g | 0.20   | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Ethylbenzene                        | µg/g | 0.05   | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| o-Xylene                            | µg/g | --   | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| p+m-Xylene                          | µg/g | --   | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Xylenes (Total)                     | µg/g | 0.05   | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| F1 (C6 to C10)                      | µg/g | 25   | <5                                  | <5         | <5         | <5         | <5         | <5         | <5         | <5         | <5         | <5         | <5         |
| F1 (C6 to C10) minus BTEX           | µg/g | 25   | <5                                  | <5         | <5         | <5         | <5         | <5         | <5         | <5         | <5         | <5         | <5         |
| F2 (C10 to C16)                     | µg/g | 10   | <10                                 | <10        | <10        | <10        | <10        | <10        | <10        | <10        | <10        | <10        | <10        |
| F2 (C10 to C16) minus Naphthalene   | µg/g | 10   | <10                                 | <10        | <10        | <10        | <10        | <10        | <10        | <10        | <10        | <10        | <10        |
| F3 (C16 to C34)                     | µg/g | 240  | <50                                 | <50        | <50        | <50        | <50        | <50        | <50        | <50        | <50        | <50        | <50        |
| F3 (C16 to C34) minus PAHs          | µg/g | --   | <50                                 | <50        | <50        | <50        | <50        | <50        | <50        | <50        | <50        | <50        | <50        |
| F4 (C34 to C50)                     | µg/g | 120  | <50                                 | <50        | <50        | <50        | <50        | <50        | <50        | <50        | <50        | <50        | <50        |
| Reached Baseline at C50             | --   | --   | --                                  | --         | --         | --         | --         | --         | --         | --         | --         | --         | --         |
| Gravimetric Heavy Hydrocarbons      | µg/g | --   | --                                  | --         | --         | --         | --         | --         | --         | --         | --         | --         | --         |
| Moisture Content                    | %    | --   | 25.9                                | 25.4       | 26.6       | 31.3       | 25.9       | 26.2       | 6.6        | 4.4        | 23.5       | 24.6       | 23.5       |
| TPgH (Gas C5-C10)                   | µg/g | --   | --                                  | --         | --         | --         | --         | --         | --         | --         | --         | --         | --         |
| TEH (Diesel, C10-C24)               | µg/g | --   | --                                  | --         | --         | --         | --         | --         | --         | --         | --         | --         | --         |
| TPH (Gas/Diesel)                    | µg/g | --   | --                                  | --         | --         | --         | --         | --         | --         | --         | --         | --         | --         |
| Petroleum Hydrocarbons (heavy oils) | µg/g | --   | --                                  | --         | --         | --         | --         | --         | --         | --         | --         | --         | --         |



| Sample Location                     | Unit | MECP Table 1 Standard (R/P/I/I/C/C) <sup>(1)</sup> | Golder 2020 Stockpile investigation |            |            |            |            |            |            |            |            |
|-------------------------------------|------|--|-------------------------------------|------------|------------|------------|------------|------------|------------|------------|------------|
| Sample ID                           |      |  | DUP-3 (field DUP of SA-16S)         | SA-16D     | SA-17S     | SA-17D     | SPD-SA3    | SPD-SA4    | SPD-SA5    | SPD-SA6    | SPD-SA7    |
| Date Sampled                        |      |  | 2021-02-19                          | 2021-02-19 | 2021-02-19 | 2021-02-19 | 2020-07-09 | 2020-07-09 | 2020-07-09 | 2020-07-09 | 2020-07-09 |
| Sample Depth (mbgs)                 | mbgs |  | --                                  | --         | --         | --         | 0.75       | 0.75       | 0.75       | 0.75       | 0.75       |
| Parameter                           |      |  |                                     |            |            |            |            |            |            |            |            |
| Benzene                             | µg/g | 0.02   | <0.02                               | <0.02      | <0.02      | <0.02      | <0.02      | <0.02      | <0.02      | <0.02      | <0.02      |
| Toluene                             | µg/g | 0.20   | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Ethylbenzene                        | µg/g | 0.05   | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| o-Xylene                            | µg/g | --   | <0.05                               | <0.05      | <0.05      | <0.05      | --         | --         | --         | --         | --         |
| p+m-Xylene                          | µg/g | --   | <0.05                               | <0.05      | <0.05      | <0.05      | --         | --         | --         | --         | --         |
| Xylenes (Total)                     | µg/g | 0.05   | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| F1 (C6 to C10)                      | µg/g | 25   | <5                                  | <5         | <5         | <5         | <5         | <5         | <5         | <5         | <5         |
| F1 (C6 to C10) minus BTEX           | µg/g | 25   | <5                                  | <5         | <5         | <5         | <5         | <5         | <5         | <5         | <5         |
| F2 (C10 to C16)                     | µg/g | 10   | <10                                 | <10        | <10        | <10        | <10        | <10        | <10        | <10        | <10        |
| F2 (C10 to C16) minus Naphthalene   | µg/g | 10   | <10                                 | <10        | <10        | <10        | <10        | <10        | <10        | <10        | <10        |
| F3 (C16 to C34)                     | µg/g | 240  | <50                                 | <50        | <50        | <50        | <50        | <50        | <50        | <50        | <50        |
| F3 (C16 to C34) minus PAHs          | µg/g | --   | <50                                 | <50        | <50        | <50        | <50        | <50        | <50        | <50        | <50        |
| F4 (C34 to C50)                     | µg/g | 120  | <50                                 | <50        | <50        | 55         | <50        | <50        | <50        | <50        | <50        |
| Reached Baseline at C50             | --   | --   | --                                  | --         | --         | --         | --         | --         | --         | --         | --         |
| Gravimetric Heavy Hydrocarbons      | µg/g | --   | --                                  | --         | --         | --         | --         | --         | --         | --         | --         |
| Moisture Content                    | %    | --   | 22.4                                | 24.7       | 20.2       | 18.8       | 26.2       | 23.8       | 25.9       | 26.5       | 23.8       |
| TPgH (Gas C5-C10)                   | µg/g | --   | --                                  | --         | --         | --         | --         | --         | --         | --         | --         |
| TEH (Diesel, C10-C24)               | µg/g | --   | --                                  | --         | --         | --         | --         | --         | --         | --         | --         |
| TPH (Gas/Diesel)                    | µg/g | --   | --                                  | --         | --         | --         | --         | --         | --         | --         | --         |
| Petroleum Hydrocarbons (heavy oils) | µg/g | --   | --                                  | --         | --         | --         | --         | --         | --         | --         | --         |

**Notes:**

G / S      Guideline / Standard  
--          Not analyzed

**Value**      Parameters exceeds Table 1 criteria.

Value      RDL exceeds Table 1 criteria

Sample location has been excavated and removed from site.

(1)          Ontario Reg 153/04 (2011) Table 1: Full Depth Background Site Condition Standards, Residential/Parkland/Institutional/Industrial/Commercial/Community Property Use for Soil.

| Sample Location               | Unit | MECP Table 1 Standard (R/P/I/I/C/C) <sup>(1)</sup> | SGP-SP1    | SGP-SP2    | SGP-SP3    | SGP-SP4    | SGP-SP5    |                                    | SGP-SP6    | SGP-SP7    | SGP-SP8    |
|-------------------------------|------|--|------------|------------|------------|------------|------------|------------------------------------|------------|------------|------------|
| Sample ID                     |      |  | SGP-SP1    | SGP-SP2    | SGP-SP3    | SGP-SP4    | SGP-SP5    | SGP-SP-DUP1 (Duplicate of SGP-SG5) | SGP-SP6    | SGP-SP7    | SGP-SP8    |
| Date Sampled                  |      |  | 2022-11-10 | 2022-11-10 | 2022-11-10 | 2022-11-10 | 2022-11-10 | 2022-11-10                         | 2022-11-10 | 2022-11-10 | 2022-11-10 |
| Sample Depth (mbgs)           | mbgs |  | 0.15       | 0.15       | 0.15       | 0.15       | 0.15       | 0.15                               | 0.15       | 0.15       | 0.15       |
| Parameter                     |      |  |            |            |            |            |            |                                    |            |            |            |
| Acenaphthene                  | µg/g | 0.072  | <0.0050    | <0.0050    | <0.0050    | <0.0050    | <0.0050    | <0.0050                            | <0.0050    | <0.0050    | <0.0050    |
| Acenaphthylene                | µg/g | 0.093  | <0.0050    | <0.0050    | <0.0050    | 0.005      | 0.0061     | 0.0052                             | 0.006      | <0.0050    | <0.0050    |
| Anthracene                    | µg/g | 0.16   | 0.0052     | 0.0053     | <0.0050    | 0.0075     | 0.0053     | <0.0050                            | 0.0093     | 0.0059     | <0.0050    |
| Benz(a)anthracene             | µg/g | 0.36   | 0.019      | 0.021      | 0.022      | 0.033      | 0.027      | 0.019                              | 0.046      | 0.023      | 0.0089     |
| Benzo(a)pyrene                | µg/g | 0.3  | 0.026      | 0.018      | 0.022      | 0.027      | 0.036      | 0.027                              | 0.053      | 0.023      | 0.0091     |
| Benzo(b)fluoranthene          | µg/g | 0.47   | 0.039      | 0.028      | 0.032      | 0.04       | 0.047      | 0.037                              | 0.07       | 0.03       | 0.013      |
| Benzo(g,h,i)perylene          | µg/g | 0.68   | 0.018      | 0.014      | 0.026      | 0.021      | 0.038      | 0.033                              | 0.045      | 0.019      | 0.01       |
| Benzo(k)fluoranthene          | µg/g | 0.48   | 0.013      | 0.0089     | 0.011      | 0.013      | 0.016      | 0.012                              | 0.024      | 0.01       | <0.0050    |
| Chrysene                      | µg/g | 2.8  | 0.025      | 0.019      | 0.023      | 0.028      | 0.024      | 0.018                              | 0.04       | 0.022      | 0.0084     |
| Dibenz(a,h)anthracene         | µg/g | 0.1  | <0.0050    | <0.0050    | <0.0050    | 0.0053     | 0.0071     | 0.0059                             | 0.0098     | <0.0050    | <0.0050    |
| Fluoranthene                  | µg/g | 0.56   | 0.031      | 0.038      | 0.046      | 0.062      | 0.037      | 0.031                              | 0.065      | 0.047      | 0.016      |
| Fluorene                      | µg/g | 0.12   | <0.0050    | <0.0050    | <0.0050    | <0.0050    | <0.0050    | <0.0050                            | <0.0050    | <0.0050    | <0.0050    |
| Indeno(1,2,3-cd)pyrene        | µg/g | 0.23   | 0.016      | 0.012      | 0.019      | 0.019      | 0.032      | 0.026                              | 0.042      | 0.017      | 0.0075     |
| 1 Methlynaphthalene           | µg/g | 0.59 <sup>(2)</sup>                                | <0.0050    | <0.0050    | <0.0050    | <0.0050    | <0.0050    | <0.0050                            | <0.0050    | <0.0050    | <0.0050    |
| 2 Methlynaphthalene           | µg/g | 0.59 <sup>(2)</sup>                                | <0.0050    | <0.0050    | <0.0050    | <0.0050    | <0.0050    | <0.0050                            | <0.0050    | <0.0050    | <0.0050    |
| 1 and 2 Methlynaphthalene (2) | µg/g | 0.59   | <0.0071    | <0.0071    | <0.0071    | <0.0071    | <0.0071    | <0.0071                            | <0.0071    | <0.0071    | <0.0071    |
| Naphthalene                   | µg/g | 0.09   | <0.0050    | <0.0050    | <0.0050    | <0.0050    | <0.0050    | <0.0050                            | <0.0050    | <0.0050    | <0.0050    |
| Phenanthrene                  | µg/g | 0.69   | 0.019      | 0.021      | 0.03       | 0.025      | 0.017      | 0.018                              | 0.034      | 0.027      | 0.008      |
| Pyrene                        | µg/g | 1  | 0.034      | 0.033      | 0.038      | 0.05       | 0.035      | 0.028                              | 0.057      | 0.037      | 0.015      |



| Sample Location               | Unit | MECP Table 1 Standard (R/P/I/I/C/C) <sup>(1)</sup> | Golder 2020 Stockpile investigation |            |            |            |            |                            |            |            |            |            |            |
|-------------------------------|------|--|-------------------------------------|------------|------------|------------|------------|----------------------------|------------|------------|------------|------------|------------|
| Sample ID                     |      |  | SA-1S                               | SA-1D      | SA-2S      | SA-2D      | SA-3S      | DUP-1 (field DUP of SA-3S) | SA-3D      | SA-4S      | SA-4D      | SA-5S      | SA-5D      |
| Date Sampled                  |      |  | 2021-02-19                          | 2021-02-19 | 2021-02-19 | 2021-02-19 | 2021-02-19 | 2021-02-19                 | 2021-02-19 | 2021-02-19 | 2021-02-19 | 2021-02-19 | 2021-02-19 |
| Sample Depth (mbgs)           | mbgs |  | --                                  | --         | --         | --         | --         | --                         | --         | --         | --         | --         | --         |
| Parameter                     |      |  |                                     |            |            |            |            |                            |            |            |            |            |            |
| Acenaphthene                  | µg/g | 0.072  | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05                      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Acenaphthylene                | µg/g | 0.093  | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05                      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Anthracene                    | µg/g | 0.16   | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05                      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Benz(a)anthracene             | µg/g | 0.36   | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05                      | <0.05      | 0.06       | <0.05      | <0.05      | <0.05      |
| Benzo(a)pyrene                | µg/g | 0.3  | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05                      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Benzo(b)fluoranthene          | µg/g | 0.47   | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05                      | <0.05      | 0.087      | <0.05      | <0.05      | <0.05      |
| Benzo(g,h,i)perylene          | µg/g | 0.68   | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05                      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Benzo(k)fluoranthene          | µg/g | 0.48   | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05                      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Chrysene                      | µg/g | 2.8  | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05                      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Dibenz(a,h)anthracene         | µg/g | 0.1  | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05                      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Fluoranthene                  | µg/g | 0.56   | 0.095                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05                      | <0.05      | 0.153      | 0.075      | <0.05      | <0.05      |
| Fluorene                      | µg/g | 0.12   | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05                      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Indeno(1,2,3-cd)pyrene        | µg/g | 0.23   | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05                      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| 1 Methlynaphthalene           | µg/g | 0.59 <sup>(2)</sup>                                | --                                  | --         | --         | --         | --         | --                         | --         | --         | --         | --         | --         |
| 2 Methlynaphthalene           | µg/g | 0.59 <sup>(2)</sup>                                | --                                  | --         | --         | --         | --         | --                         | --         | --         | --         | --         | --         |
| 1 and 2 Methlynaphthalene (2) | µg/g | 0.59   | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05                      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Naphthalene                   | µg/g | 0.09   | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05                      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Phenanthrene                  | µg/g | 0.69   | 0.051                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05                      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Pyrene                        | µg/g | 1  | 0.071                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05                      | <0.05      | 0.127      | 0.065      | <0.05      | <0.05      |



| Sample Location               | Unit | MECP Table 1 Standard (R/P/I/I/C/C) <sup>(1)</sup> | Golder 2020 Stockpile investigation |            |            |            |            |            |            |            |            |            |                             |
|-------------------------------|------|--|-------------------------------------|------------|------------|------------|------------|------------|------------|------------|------------|------------|-----------------------------|
| Sample ID                     |      |  | SA-6S                               | SA-6D      | SA-7S      | SA-7D      | SA-8S      | SA-8D      | SA-9S      | SA-9D      | SA-10S     | SA-10D     | DUP-2 (field DUP of SA-10D) |
| Date Sampled                  |      |  | 2021-02-19                          | 2021-02-19 | 2021-02-19 | 2021-02-19 | 2021-02-19 | 2021-02-19 | 2021-02-19 | 2021-02-19 | 2021-02-19 | 2021-02-19 | 2021-02-19                  |
| Sample Depth (mbgs)           | mbgs |  | --                                  | --         | --         | --         | --         | --         | --         | --         | --         | --         | --                          |
| Parameter                     |      |  |                                     |            |            |            |            |            |            |            |            |            |                             |
| Acenaphthene                  | µg/g | 0.072  | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05                       |
| Acenaphthylene                | µg/g | 0.093  | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05                       |
| Anthracene                    | µg/g | 0.16   | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05                       |
| Benz(a)anthracene             | µg/g | 0.36   | <0.05                               | <0.05      | 0.111      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05                       |
| Benzo(a)pyrene                | µg/g | 0.3  | <0.05                               | <0.05      | 0.071      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05                       |
| Benzo(b)fluoranthene          | µg/g | 0.47   | <0.05                               | <0.05      | 0.133      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05                       |
| Benzo(g,h,i)perylene          | µg/g | 0.68   | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05                       |
| Benzo(k)fluoranthene          | µg/g | 0.48   | <0.05                               | <0.05      | 0.086      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05                       |
| Chrysene                      | µg/g | 2.8  | <0.05                               | <0.05      | 0.088      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05                       |
| Dibenz(a,h)anthracene         | µg/g | 0.1  | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05                       |
| Fluoranthene                  | µg/g | 0.56   | 0.081                               | <0.05      | 0.256      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05                       |
| Fluorene                      | µg/g | 0.12   | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05                       |
| Indeno(1,2,3-cd)pyrene        | µg/g | 0.23   | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05                       |
| 1 Methlynaphthalene           | µg/g | 0.59 <sup>(2)</sup>                                | --                                  | --         | --         | --         | --         | --         | --         | --         | --         | --         | --                          |
| 2 Methlynaphthalene           | µg/g | 0.59 <sup>(2)</sup>                                | --                                  | --         | --         | --         | --         | --         | --         | --         | --         | --         | --                          |
| 1 and 2 Methlynaphthalene (2) | µg/g | 0.59   | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05                       |
| Naphthalene                   | µg/g | 0.09   | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05                       |
| Phenanthrene                  | µg/g | 0.69   | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05                       |
| Pyrene                        | µg/g | 1  | 0.069                               | <0.05      | 0.229      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05                       |

| Sample Location               | Unit | MECP Table 1 Standard (R/P/I/I/C/C) <sup>(1)</sup> | Golder 2020 Stockpile investigation |            |            |            |            |            |            |            |            |            |            |
|-------------------------------|------|--|-------------------------------------|------------|------------|------------|------------|------------|------------|------------|------------|------------|------------|
| Sample ID                     |      |  | SA-11S                              | SA-11D     | SA-12S     | SA-12D     | SA-13S     | SA-13D     | SA-14S     | SA-14D     | SA-15S     | SA-15D     | SA-16S     |
| Date Sampled                  |      |  | 2021-02-19                          | 2021-02-19 | 2021-02-19 | 2021-02-19 | 2021-02-19 | 2021-02-19 | 2021-02-19 | 2021-02-19 | 2021-02-19 | 2021-02-19 | 2021-02-19 |
| Sample Depth (mbgs)           | mbgs |  | --                                  | --         | --         | --         | --         | --         | --         | --         | --         | --         | --         |
| Parameter                     |      |  |                                     |            |            |            |            |            |            |            |            |            |            |
| Acenaphthene                  | µg/g | 0.072  | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Acenaphthylene                | µg/g | 0.093  | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Anthracene                    | µg/g | 0.16   | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Benz(a)anthracene             | µg/g | 0.36   | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | 0.056      | 0.112      | <0.05      |
| Benzo(a)pyrene                | µg/g | 0.3  | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | 0.089      | <0.05      |
| Benzo(b)fluoranthene          | µg/g | 0.47   | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | 0.068      | 0.091      | <0.05      |
| Benzo(g,h,i)perylene          | µg/g | 0.68   | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Benzo(k)fluoranthene          | µg/g | 0.48   | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | 0.059      | 0.07       | <0.05      |
| Chrysene                      | µg/g | 2.8  | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | 0.074      | <0.05      |
| Dibenz(a,h)anthracene         | µg/g | 0.1  | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Fluoranthene                  | µg/g | 0.56   | <0.05                               | <0.05      | 0.079      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | 0.143      | 0.232      | <0.05      |
| Fluorene                      | µg/g | 0.12   | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Indeno(1,2,3-cd)pyrene        | µg/g | 0.23   | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| 1 Methlynaphthalene           | µg/g | 0.59 <sup>(2)</sup>                                | --                                  | --         | --         | --         | --         | --         | --         | --         | --         | --         | --         |
| 2 Methlynaphthalene           | µg/g | 0.59 <sup>(2)</sup>                                | --                                  | --         | --         | --         | --         | --         | --         | --         | --         | --         | --         |
| 1 and 2 Methlynaphthalene (2) | µg/g | 0.59   | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Naphthalene                   | µg/g | 0.09   | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Phenanthrene                  | µg/g | 0.69   | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | 0.065      | <0.05      |
| Pyrene                        | µg/g | 1  | <0.05                               | <0.05      | 0.061      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | 0.118      | 0.183      | <0.05      |

| Sample Location               | Unit | MECP Table 1 Standard (R/P/I/I/C/C) <sup>(1)</sup> | Golder 2020 Stockpile investigation |            |            |            |            |            |            |            |            |
|-------------------------------|------|--|-------------------------------------|------------|------------|------------|------------|------------|------------|------------|------------|
| Sample ID                     |      |  | DUP-3 (field DUP of SA-16S)         | SA-16D     | SA-17S     | SA-17D     | SPD-SA3    | SPD-SA4    | SPD-SA5    | SPD-SA6    | SPD-SA7    |
| Date Sampled                  |      |  | 2021-02-19                          | 2021-02-19 | 2021-02-19 | 2021-02-19 | 2020-07-09 | 2020-07-09 | 2020-07-09 | 2020-07-09 | 2020-07-09 |
| Sample Depth (mbgs)           | mbgs |  | --                                  | --         | --         | --         | 0.75       | 0.75       | 0.75       | 0.75       | 0.75       |
| Parameter                     |      |  |                                     |            |            |            |            |            |            |            |            |
| Acenaphthene                  | µg/g | 0.072  | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Acenaphthylene                | µg/g | 0.093  | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Anthracene                    | µg/g | 0.16   | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Benz(a)anthracene             | µg/g | 0.36   | <0.05                               | <0.05      | <0.05      | 0.054      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Benzo(a)pyrene                | µg/g | 0.3  | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Benzo(b)fluoranthene          | µg/g | 0.47   | <0.05                               | <0.05      | 0.057      | 0.096      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Benzo(g,h,i)perylene          | µg/g | 0.68   | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Benzo(k)fluoranthene          | µg/g | 0.48   | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Chrysene                      | µg/g | 2.8  | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Dibenz(a,h)anthracene         | µg/g | 0.1  | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Fluoranthene                  | µg/g | 0.56   | 0.077                               | 0.06       | 0.092      | 0.149      | <0.05      | <0.05      | <0.05      | 0.09       | <0.05      |
| Fluorene                      | µg/g | 0.12   | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Indeno(1,2,3-cd)pyrene        | µg/g | 0.23   | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| 1 Methlynaphthalene           | µg/g | 0.59 <sup>(2)</sup>                                | --                                  | --         | --         | --         | --         | --         | --         | --         | --         |
| 2 Methlynaphthalene           | µg/g | 0.59 <sup>(2)</sup>                                | --                                  | --         | --         | --         | --         | --         | --         | --         | --         |
| 1 and 2 Methlynaphthalene (2) | µg/g | 0.59   | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Naphthalene                   | µg/g | 0.09   | <0.05                               | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Phenanthrene                  | µg/g | 0.69   | <0.05                               | <0.05      | <0.05      | 0.052      | <0.05      | <0.05      | <0.05      | <0.05      | <0.05      |
| Pyrene                        | µg/g | 1  | 0.066                               | 0.051      | 0.07       | 0.118      | <0.05      | <0.05      | <0.05      | 0.08       | <0.05      |



**Notes:**

G / S Guideline / Standard

-- Not analyzed

ND Not detected

**Value** Parameters exceeds Table 1 criteria.

Value RDL exceeds Table 1 criteria

Sample location has been excavated and removed from site.

(1) Ontario Reg 153/04 (2011) Table 1: Full Depth Background Site Condition Standards, Residential/Parkland/Institutional/Industrial/Commercial/Community Property Use for Soil.

(2) The methyl-naphthalene standards are applicable to both 1-methyl-naphthalene and 2-methyl-naphthalene, with the provision that if both are detected, the sum of the two must not exceed the standard.



| Sample Location               | Unit     | MECP Table 1 Standard (R/P/I/I/C/C) <sup>(1)</sup> | SGP-SP1    | SGP-SP2    | SGP-SP3    | SGP-SP4    | SGP-SP5    |                                    | SGP-SP6    | SGP-SP7    | SGP-SP8    |
|-------------------------------|----------|--|------------|------------|------------|------------|------------|------------------------------------|------------|------------|------------|
| eck the master sh             |          |  | SGP-SP1    | SGP-SP2    | SGP-SP3    | SGP-SP4    | SGP-SP5    | SGP-SP-DUP1 (Duplicate of SGP-SG5) | SGP-SP6    | SGP-SP7    | SGP-SP8    |
| Date Sampled                  |          |  | 2022-11-10 | 2022-11-10 | 2022-11-10 | 2022-11-10 | 2022-11-10 | 2022-11-10                         | 2022-11-10 | 2022-11-10 | 2022-11-10 |
| Sample Depth (mbgs)           | mbgs     |  | 0.15       | 0.15       | 0.15       | 0.15       | 0.15       | 0.15                               | 0.15       | 0.15       | 0.15       |
| Antimony                      | µg/g     | 1.3  | <0.2       | <0.2       | <0.2       | <0.2       | <0.2       | <0.2                               | <0.2       | <0.2       | <0.2       |
| Arsenic                       | µg/g     | 18   | 2.3        | 2.6        | 2.3        | 2          | 2          | 2.1                                | 2.2        | 1.2        | 1.2        |
| Barium                        | µg/g     | 220  | 98         | 160        | 200        | 180        | 160        | 170                                | 110        | 300        | 230        |
| Beryllium                     | µg/g     | 2.5  | 0.32       | 0.33       | 0.56       | 0.3        | 0.31       | 0.31                               | 0.34       | 0.74       | 0.59       |
| Boron                         | µg/g     | 36   | 13         | 11         | 9.1        | 12         | 11         | 11                                 | 12         | 5          | 6.8        |
| Boron (Hot Water Extractable) | µg/g     | --   | --         | --         | --         | --         | --         | --                                 | --         | --         | --         |
| Cadmium                       | µg/g     | 1.2  | <0.1       | <0.1       | 0.12       | <0.1       | 0.12       | <0.1                               | 0.12       | 0.11       | <0.1       |
| Calcium                       | µg/g     | --   | --         | --         | --         | --         | --         | --                                 | --         | --         | --         |
| Chromium (Total)              | µg/g     | 70   | 15         | 13         | 50         | 11         | 13         | 13                                 | 14         | 85         | 60         |
| Cobalt                        | µg/g     | 21   | 6.7        | 8.4        | 14         | 7.6        | 7.7        | 8.1                                | 7.2        | 20         | 15         |
| Copper                        | µg/g     | 92   | 10         | 12         | 28         | 11         | 11         | 11                                 | 11         | 42         | 32         |
| Iron                          | µg/g     | --   | --         | --         | --         | --         | --         | --                                 | --         | --         | --         |
| Lead                          | µg/g     | 120  | 13         | 15         | 16         | 11         | 15         | 16                                 | 19         | 11         | 9.5        |
| Molybdenum                    | µg/g     | 2  | <0.5       | 0.71       | 0.57       | 0.66       | 0.62       | 0.51                               | 0.5        | 0.54       | <0.5       |
| Nickel                        | µg/g     | 82   | 12         | 16         | 33         | 13         | 14         | 14                                 | 13         | 50         | 37         |
| Selenium                      | µg/g     | 1.5  | <0.5       | <0.5       | <0.5       | <0.5       | <0.5       | <0.5                               | <0.5       | <0.5       | <0.5       |
| Silver                        | µg/g     | 0.5  | <0.2       | <0.2       | <0.2       | <0.2       | <0.2       | <0.2                               | <0.2       | <0.2       | <0.2       |
| Sodium                        | µg/g     | NA   | --         | --         | --         | --         | --         | --                                 | --         | --         | --         |
| Thallium                      | µg/g     | 1  | 0.13       | 0.21       | 0.27       | 0.15       | 0.15       | 0.16                               | 0.15       | 0.4        | 0.31       |
| Uranium                       | µg/g     | 2.5  | 0.28       | 0.32       | 0.55       | 0.22       | 0.25       | 0.25                               | 0.27       | 0.74       | 0.61       |
| Vanadium                      | µg/g     | 86   | 15         | 15         | 50         | 12         | 14         | 15                                 | 16         | 85         | 62         |
| Zinc                          | µg/g     | 290  | 25         | 30         | 64         | 23         | 20         | 21                                 | 26         | 100        | 76         |
| Chromium, Hexavalent          | µg/g     | 70   | --         | --         | --         | --         | --         | --                                 | --         | --         | --         |
| Cyanide, Free                 | µg/g     | 0.051  | --         | --         | --         | --         | --         | --                                 | --         | --         | --         |
| Mercury                       | µg/g     | 0.27   | --         | --         | --         | --         | --         | --                                 | --         | --         | --         |
| Electrical Conductivity (2:1) | mS/cm    | 0.57   | --         | --         | --         | --         | --         | --                                 | --         | --         | --         |
| Sodium Adsorption Ratio       | NA       | --   | --         | --         | --         | --         | --         | --                                 | --         | --         | --         |
| pH, 2:1 CaCl2 Extraction      | pH Units | --   | --         | --         | --         | --         | --         | --                                 | --         | --         | --         |



| Sample Location               | Unit     | MECP Table 1 Standard (R/P/I/I/C/C) <sup>(1)</sup> | Golder 2020 Stockpile investigation |             |            |            |            |                            |            |            |             |             |             |
|-------------------------------|----------|--|-------------------------------------|-------------|------------|------------|------------|----------------------------|------------|------------|-------------|-------------|-------------|
|                               |          |  | SA-1S                               | SA-1D       | SA-2S      | SA-2D      | SA-3S      | DUP-1 (field DUP of SA-3S) | SA-3D      | SA-4S      | SA-4D       | SA-5S       | SA-5D       |
|                               |          |  | 02/19/2021                          | 02/19/2021  | 02/19/2021 | 02/19/2021 | 02/19/2021 | 02/19/2021                 | 02/19/2021 | 02/19/2021 | 02/19/2021  | 02/19/2021  | 02/19/2021  |
| Sample Depth (mbgs)           | mbgs     |  | --                                  | --          | --         | --         | --         | --                         | --         | --         | --          | --          | --          |
| Antimony                      | µg/g     | 1.3  | <0.8                                | <0.8        | <0.8       | <0.8       | <0.8       | <0.8                       | <0.8       | <0.8       | <0.8        | <0.8        | <0.8        |
| Arsenic                       | µg/g     | 18   | 1                                   | 2           | 1          | 1          | 1          | <1                         | 2          | 2          | 2           | 2           | 2           |
| Barium                        | µg/g     | 220  | <b>338</b>                          | <b>331</b>  | 80.3       | 171        | 119        | 63.6                       | <b>227</b> | <b>351</b> | <b>344</b>  | <b>421</b>  | <b>407</b>  |
| Beryllium                     | µg/g     | 2.5  | <0.4                                | <0.4        | <0.4       | <0.4       | <0.4       | <0.4                       | <0.4       | <0.4       | <0.4        | <0.4        | <0.4        |
| Boron                         | µg/g     | 36   | <5                                  | <5          | <5         | <5         | <5         | <5                         | <5         | <5         | <5          | <5          | <5          |
| Boron (Hot Water Extractable) | µg/g     | --   | --                                  | --          | --         | --         | --         | --                         | --         | --         | --          | --          | --          |
| Cadmium                       | µg/g     | 1.2  | <0.5                                | <0.5        | <0.5       | <0.5       | <0.5       | <0.5                       | <0.5       | <0.5       | <0.5        | <0.5        | <0.5        |
| Calcium                       | µg/g     | --   | --                                  | --          | --         | --         | --         | --                         | --         | --         | --          | --          | --          |
| Chromium (Total)              | µg/g     | 70   | <b>98</b>                           | <b>97</b>   | 22         | 39         | 32         | 18                         | 65         | <b>106</b> | <b>97</b>   | <b>116</b>  | <b>114</b>  |
| Cobalt                        | µg/g     | 21   | 20.5                                | <b>21.6</b> | 6          | 8.9        | 7.7        | 5                          | 14.3       | 20.3       | 18.3        | <b>22.7</b> | <b>24.9</b> |
| Copper                        | µg/g     | 92   | 42.6                                | 42.2        | 10.2       | 17.6       | 14.2       | 7.5                        | 29.4       | 45.3       | 40.4        | 49.5        | 51.3        |
| Iron                          | µg/g     | --   | --                                  | --          | --         | --         | --         | --                         | --         | --         | --          | --          | --          |
| Lead                          | µg/g     | 120  | 7                                   | 12          | 3          | 4          | 3          | 2                          | 6          | 12         | 7           | 8           | 8           |
| Molybdenum                    | µg/g     | 2  | <0.5                                | <0.5        | <0.5       | <0.5       | <0.5       | <0.5                       | <0.5       | <0.5       | <0.5        | <0.5        | 0.5         |
| Nickel                        | µg/g     | 82   | 58                                  | 55          | 16         | 24         | 20         | 13                         | 39         | 56         | 51          | 64          | 65          |
| Selenium                      | µg/g     | 1.5  | <0.8                                | <0.8        | <0.8       | <0.8       | <0.8       | <0.8                       | <0.8       | <0.8       | <0.8        | <0.8        | <0.8        |
| Silver                        | µg/g     | 0.5  | <0.5                                | <0.5        | <0.5       | <0.5       | <0.5       | <0.5                       | <0.5       | <0.5       | <0.5        | <0.5        | <0.5        |
| Sodium                        | µg/g     | NA   | --                                  | --          | --         | --         | --         | --                         | --         | --         | --          | --          | --          |
| Thallium                      | µg/g     | 1  | <0.5                                | <0.5        | <0.5       | <0.5       | <0.5       | <0.5                       | <0.5       | <0.5       | <0.5        | <0.5        | <0.5        |
| Uranium                       | µg/g     | 2.5  | 0.93                                | 1.06        | 1.65       | <0.50      | <0.50      | <0.50                      | 0.82       | 1.22       | 0.98        | 1.13        | 1.13        |
| Vanadium                      | µg/g     | 86   | <b>95.1</b>                         | <b>93.3</b> | 24         | 39.4       | 32.7       | 19.9                       | 65.9       | <b>102</b> | <b>93.9</b> | <b>113</b>  | <b>110</b>  |
| Zinc                          | µg/g     | 290  | 114                                 | 117         | 40         | 56         | 49         | 35                         | 86         | 135        | 108         | 129         | 128         |
| Chromium, Hexavalent          | µg/g     | 70   | <0.2                                | <0.2        | <0.2       | <0.2       | <0.2       | <0.2                       | <0.2       | <0.2       | <0.2        | <0.2        | <0.2        |
| Cyanide, Free                 | µg/g     | 0.051  | --                                  | --          | --         | --         | --         | --                         | --         | --         | --          | --          | --          |
| Mercury                       | µg/g     | 0.27   | <0.10                               | <0.10       | <0.10      | <0.10      | <0.10      | <0.10                      | <0.10      | <0.10      | <0.10       | <0.10       | <0.10       |
| Electrical Conductivity (2:1) | mS/cm    | 0.57   | --                                  | --          | --         | --         | --         | --                         | --         | --         | --          | --          | --          |
| Sodium Adsorption Ratio       | NA       | --   | --                                  | --          | --         | --         | --         | --                         | --         | --         | --          | --          | --          |
| pH, 2:1 CaCl2 Extraction      | pH Units | --   | --                                  | --          | --         | --         | --         | --                         | --         | --         | --          | --          | --          |



| Sample Location               | Unit     | MECP Table 1 Standard (R/P/I/I/C/C) <sup>(1)</sup> | Golder 2020 Stockpile investigation |            |            |            |            |            |            |            |            |            |                             |
|-------------------------------|----------|--|-------------------------------------|------------|------------|------------|------------|------------|------------|------------|------------|------------|-----------------------------|
|                               |          |  | SA-6S                               | SA-6D      | SA-7S      | SA-7D      | SA-8S      | SA-8D      | SA-9S      | SA-9D      | SA-10S     | SA-10D     | DUP-2 (field DUP of SA-10D) |
|                               |          |  | 02/19/2021                          | 02/19/2021 | 02/19/2021 | 02/19/2021 | 02/19/2021 | 02/19/2021 | 02/19/2021 | 02/19/2021 | 02/19/2021 | 02/19/2021 | 02/19/2021                  |
| Sample Depth (mbgs)           | mbgs     |  | --                                  | --         | --         | --         | --         | --         | --         | --         | --         | --         | --                          |
| Antimony                      | µg/g     | 1.3  | <0.8                                | <0.8       | <0.8       | <0.8       | <0.8       | <0.8       | <0.8       | <0.8       | <0.8       | <0.8       | <0.8                        |
| Arsenic                       | µg/g     | 18   | 2                                   | 2          | 2          | 2          | 2          | 1          | 2          | 1          | 1          | 2          | 1                           |
| Barium                        | µg/g     | 220  | 335                                 | 403        | 303        | 433        | 463        | 427        | 434        | 418        | 359        | 390        | 356                         |
| Beryllium                     | µg/g     | 2.5  | <0.4                                | <0.4       | <0.4       | <0.4       | <0.4       | <0.4       | <0.4       | <0.4       | <0.4       | 0.5        | 0.5                         |
| Boron                         | µg/g     | 36   | <5                                  | <5         | <5         | <5         | <5         | <5         | <5         | <5         | <5         | <5         | <5                          |
| Boron (Hot Water Extractable) | µg/g     | --   | --                                  | --         | --         | --         | --         | --         | --         | --         | --         | --         | --                          |
| Cadmium                       | µg/g     | 1.2  | <0.5                                | 0.5        | <0.5       | <0.5       | <0.5       | <0.5       | <0.5       | <0.5       | <0.5       | <0.5       | <0.5                        |
| Calcium                       | µg/g     | --   | --                                  | --         | --         | --         | --         | --         | --         | --         | --         | --         | 105                         |
| Chromium (Total)              | µg/g     | 70   | 93                                  | 112        | 86         | 117        | 129        | 117        | 118        | 116        | 105        | 114        | --                          |
| Cobalt                        | µg/g     | 21   | 20.1                                | 23.3       | 17.5       | 22.6       | 24.9       | 22.6       | 24.4       | 22.9       | 20.8       | 22.8       | 21.5                        |
| Copper                        | µg/g     | 92   | 39.3                                | 51.8       | 37.3       | 47         | 56.8       | 47.9       | 49.4       | 46.9       | 36.3       | 39.4       | 37.6                        |
| Iron                          | µg/g     | --   | --                                  | --         | --         | --         | --         | --         | --         | --         | --         | --         | --                          |
| Lead                          | µg/g     | 120  | 17                                  | 9          | 9          | 9          | 8          | 7          | 9          | 9          | 9          | 8          | 8                           |
| Molybdenum                    | µg/g     | 2  | 0.5                                 | <0.5       | <0.5       | <0.5       | <0.5       | <0.5       | <0.5       | <0.5       | <0.5       | <0.5       | <0.5                        |
| Nickel                        | µg/g     | 82   | 52                                  | 62         | 49         | 64         | 70         | 63         | 65         | 64         | 54         | 59         | 55                          |
| Selenium                      | µg/g     | 1.5  | <0.8                                | <0.8       | <0.8       | <0.8       | <0.8       | <0.8       | <0.8       | <0.8       | <0.8       | 1          | <0.8                        |
| Silver                        | µg/g     | 0.5  | <0.5                                | <0.5       | <0.5       | <0.5       | <0.5       | <0.5       | <0.5       | <0.5       | <0.5       | <0.5       | <0.5                        |
| Sodium                        | µg/g     | NA   | --                                  | --         | --         | --         | --         | --         | --         | --         | --         | --         | --                          |
| Thallium                      | µg/g     | 1  | <0.5                                | <0.5       | <0.5       | <0.5       | 0.5        | <0.5       | <0.5       | <0.5       | <0.5       | 0.7        | <0.5                        |
| Uranium                       | µg/g     | 2.5  | 1.14                                | 1.01       | 0.94       | 1.06       | 0.94       | 0.96       | 1.04       | 1.22       | 1.49       | 1.53       | 1.65                        |
| Vanadium                      | µg/g     | 86   | 89.6                                | 106        | 81.8       | 112        | 127        | 111        | 116        | 112        | 96         | 100        | 93.7                        |
| Zinc                          | µg/g     | 290  | 127                                 | 132        | 103        | 133        | 142        | 138        | 138        | 131        | 132        | 140        | 137                         |
| Chromium, Hexavalent          | µg/g     | 70   | <0.2                                | <0.2       | <0.2       | <0.2       | <0.2       | <0.2       | <0.2       | <0.2       | <0.2       | <0.2       | <0.2                        |
| Cyanide, Free                 | µg/g     | 0.051  | --                                  | --         | --         | --         | --         | --         | --         | --         | --         | --         | --                          |
| Mercury                       | µg/g     | 0.27   | <0.10                               | <0.10      | <0.10      | <0.10      | <0.10      | <0.10      | <0.10      | <0.10      | <0.10      | 0.11       | <0.10                       |
| Electrical Conductivity (2:1) | mS/cm    | 0.57   | --                                  | --         | --         | --         | --         | --         | --         | --         | --         | --         | --                          |
| Sodium Adsorption Ratio       | NA       | --   | --                                  | --         | --         | --         | --         | --         | --         | --         | --         | --         | --                          |
| pH, 2:1 CaCl2 Extraction      | pH Units | --   | --                                  | --         | --         | --         | --         | --         | --         | --         | --         | --         | --                          |



| Sample Location               | Unit     | MECP Table 1 Standard (R/P/I/I/C/C) <sup>(1)</sup> | Golder 2020 Stockpile investigation |            |            |            |            |            |            |            |            |            |                             |            |
|-------------------------------|----------|--|-------------------------------------|------------|------------|------------|------------|------------|------------|------------|------------|------------|-----------------------------|------------|
|                               |          |  | SA-11S                              | SA-11D     | SA-12S     | SA-12D     | SA-13S     | SA-13D     | SA-14S     | SA-14D     | SA-15D     | SA-16S     | DUP-3 (field DUP of SA-16S) | SA-16D     |
|                               |          |  | 02/19/2021                          | 02/19/2021 | 02/19/2021 | 02/19/2021 | 02/19/2021 | 02/19/2021 | 02/19/2021 | 02/19/2021 | 02/19/2021 | 02/19/2021 | 02/19/2021                  | 02/19/2021 |
| Sample Depth (mbgs)           | mbgs     |  | --                                  | --         | --         | --         | --         | --         | --         | --         | --         | --         | --                          | --         |
| Antimony                      | µg/g     | 1.3  | <0.8                                | <0.8       | <0.8       | <0.8       | <0.8       | <0.8       | <0.8       | <0.8       | <0.8       | <0.8       | <0.8                        | <0.8       |
| Arsenic                       | µg/g     | 18   | 2                                   | 2          | 2          | 2          | 2          | 2          | 1          | <1         | 2          | 2          | 2                           | 2          |
| Barium                        | µg/g     | 220  | 487                                 | 419        | 329        | 397        | 341        | 308        | 254        | 384        | 408        | 391        | 358                         | 444        |
| Beryllium                     | µg/g     | 2.5  | 0.5                                 | 0.4        | 0.5        | 0.4        | 0.4        | <0.4       | <0.4       | <0.4       | 0.4        | 0.5        | 0.4                         | 0.5        |
| Boron                         | µg/g     | 36   | <5                                  | <5         | <5         | <5         | <5         | <5         | <5         | <5         | <5         | <5         | <5                          | <5         |
| Boron (Hot Water Extractable) | µg/g     | --   | --                                  | --         | --         | --         | --         | --         | --         | --         | --         | --         | --                          | --         |
| Cadmium                       | µg/g     | 1.2  | <0.5                                | <0.5       | <0.5       | <0.5       | <0.5       | <0.5       | <0.5       | <0.5       | <0.5       | <0.5       | <0.5                        | <0.5       |
| Calcium                       | µg/g     | --   | --                                  | --         | --         | --         | --         | --         | --         | --         | --         | --         | --                          | --         |
| Chromium (Total)              | µg/g     | 70   | 146                                 | 127        | 101        | 121        | 105        | 95         | 75         | 37         | 126        | 113        | 109                         | 130        |
| Cobalt                        | µg/g     | 21   | 29.3                                | 24.1       | 20.2       | 24.6       | 19.9       | 19.4       | 15.3       | 8.5        | 24.7       | 23.4       | 22.6                        | 28.5       |
| Copper                        | µg/g     | 92   | 65.5                                | 55.4       | 45.2       | 49.7       | 45.4       | 40         | 32.8       | 16.6       | 55.8       | 48.1       | 45.8                        | 54.4       |
| Iron                          | µg/g     | --   | --                                  | --         | --         | --         | --         | --         | --         | --         | --         | --         | --                          | --         |
| Lead                          | µg/g     | 120  | 8                                   | 7          | 11         | 8          | 7          | 8          | 9          | 3          | 8          | 11         | 12                          | 8          |
| Molybdenum                    | µg/g     | 2  | 0.6                                 | <0.5       | 0.5        | 0.5        | <0.5       | <0.5       | <0.5       | <0.5       | <0.5       | 0.6        | 0.6                         | 0.7        |
| Nickel                        | µg/g     | 82   | 81                                  | 70         | 56         | 65         | 57         | 52         | 42         | 23         | 69         | 62         | 59                          | 72         |
| Selenium                      | µg/g     | 1.5  | <0.8                                | <0.8       | <0.8       | <0.8       | <0.8       | <0.8       | <0.8       | <0.8       | <0.8       | <0.8       | <0.8                        | <0.8       |
| Silver                        | µg/g     | 0.5  | <0.5                                | <0.5       | <0.5       | <0.5       | <0.5       | <0.5       | <0.5       | <0.5       | <0.5       | <0.5       | <0.5                        | <0.5       |
| Sodium                        | µg/g     | NA   | --                                  | --         | --         | --         | --         | --         | --         | --         | --         | --         | --                          | --         |
| Thallium                      | µg/g     | 1  | 0.6                                 | <0.5       | <0.5       | <0.5       | <0.5       | <0.5       | <0.5       | <0.5       | <0.5       | <0.5       | <0.5                        | 0.5        |
| Uranium                       | µg/g     | 2.5  | 1.22                                | 1.1        | 1.04       | 1.22       | 1.02       | 1.15       | 0.75       | 0.53       | 1.09       | 1.27       | 1.51                        | 1.95       |
| Vanadium                      | µg/g     | 86   | 133                                 | 116        | 95.7       | 112        | 97.7       | 90.6       | 72.6       | 37.1       | 120        | 109        | 102                         | 120        |
| Zinc                          | µg/g     | 290  | 162                                 | 142        | 121        | 135        | 133        | 129        | 95         | 54         | 146        | 139        | 138                         | 153        |
| Chromium, Hexavalent          | µg/g     | 70   | <0.2                                | <0.2       | <0.2       | <0.2       | <0.2       | <0.2       | <0.2       | <0.2       | <0.2       | <0.2       | <0.2                        | <0.2       |
| Cyanide, Free                 | µg/g     | 0.051  | --                                  | --         | --         | --         | --         | --         | --         | --         | --         | --         | --                          | --         |
| Mercury                       | µg/g     | 0.27   | <0.10                               | <0.10      | <0.10      | <0.10      | <0.10      | <0.10      | <0.10      | <0.10      | <0.10      | <0.10      | <0.10                       | <0.10      |
| Electrical Conductivity (2:1) | mS/cm    | 0.57   | --                                  | --         | --         | --         | --         | --         | --         | --         | --         | --         | --                          | --         |
| Sodium Adsorption Ratio       | NA       | --   | --                                  | --         | --         | --         | --         | --         | --         | --         | --         | --         | --                          | --         |
| pH, 2:1 CaCl2 Extraction      | pH Units | --   | --                                  | --         | --         | --         | --         | --         | --         | --         | --         | --         | --                          | --         |



| Sample Location               | Unit     | MECP Table 1 Standard (R/P/I/I/C/C) <sup>(1)</sup> | Golder 2020 Stockpile investigation |            |            |            |            |            |            |            |            |
|-------------------------------|----------|--|-------------------------------------|------------|------------|------------|------------|------------|------------|------------|------------|
|                               |          |  | SA-17S                              | SA-17D     | SPD-SA1    | SPD-SA2    | SPD-SA3    | SPD-SA4    | SPD-SA5    | SPD-SA6    | SPD-SA7    |
|                               |          |  | 02/19/2021                          | 02/19/2021 | 07/08/2020 | 07/08/2020 | 07/09/2020 | 07/09/2020 | 07/09/2020 | 07/09/2020 | 07/09/2020 |
| Sample Depth (mbgs)           | mbgs     |  | --                                  | --         | 0.75       | 0.75       | 0.75       | 0.75       | 0.75       | 0.75       | 0.75       |
| Antimony                      | µg/g     | 1.3  | <0.8                                | <0.8       | <0.8       | <0.8       | <0.8       | <0.8       | <0.8       | <0.8       | <0.8       |
| Arsenic                       | µg/g     | 18   | 4                                   | 6          | 2          | 2          | 2          | 2          | 1          | 2          | 2          |
| Barium                        | µg/g     | 220  | 116                                 | 157        | 374        | 246        | 348        | 416        | 317        | 381        | 327        |
| Beryllium                     | µg/g     | 2.5  | 0.5                                 | 0.5        | 1          | 0.5        | 0.8        | 1          | 0.7        | 0.8        | 0.9        |
| Boron                         | µg/g     | 36   | 11                                  | 11         | 5          | <5         | <5         | <5         | <5         | <5         | 5          |
| Boron (Hot Water Extractable) | µg/g     | --   | --                                  | --         | 0.28       | 0.14       | 0.26       | 0.15       | <0.10      | <0.10      | 0.34       |
| Cadmium                       | µg/g     | 1.2  | <0.5                                | <0.5       | <0.5       | <0.5       | <0.5       | <0.5       | <0.5       | <0.5       | <0.5       |
| Calcium                       | µg/g     | --   | --                                  | --         | --         | --         | --         | --         | --         | --         | --         |
| Chromium (Total)              | µg/g     | 70   | 18                                  | 33         | 113        | 71         | 111        | 131        | 98         | 120        | 101        |
| Cobalt                        | µg/g     | 21   | 8.3                                 | 12.4       | 21.8       | 13.6       | 21.4       | 26.7       | 19.9       | 25.6       | 17.9       |
| Copper                        | µg/g     | 92   | 11.7                                | 19.1       | 57         | 37         | 50         | 59         | 49         | 59         | 45         |
| Iron                          | µg/g     | --   | --                                  | --         | --         | --         | --         | --         | --         | --         | --         |
| Lead                          | µg/g     | 120  | 11                                  | 16         | 9          | 13         | 9          | 8          | 6          | 8          | 11         |
| Molybdenum                    | µg/g     | 2  | 0.6                                 | 0.8        | <0.5       | 0.5        | <0.5       | <0.5       | <0.5       | 0.6        | <0.5       |
| Nickel                        | µg/g     | 82   | 15                                  | 24         | 58         | 39         | 56         | 69         | 53         | 64         | 46         |
| Selenium                      | µg/g     | 1.5  | <0.8                                | <0.8       | 0.7        | 0.5        | 0.6        | 0.4        | <0.4       | 0.5        | 0.9        |
| Silver                        | µg/g     | 0.5  | <0.5                                | <0.5       | <0.2       | <0.2       | <0.2       | <0.2       | <0.2       | <0.2       | <0.2       |
| Sodium                        | µg/g     | NA   | --                                  | --         | --         | --         | --         | --         | --         | --         | --         |
| Thallium                      | µg/g     | 1  | <0.5                                | <0.5       | 0.5        | <0.4       | 0.4        | 0.5        | 0.4        | 0.5        | 0.4        |
| Uranium                       | µg/g     | 2.5  | <0.50                               | 0.65       | 1.7        | 0.8        | 1.1        | 1.4        | 0.9        | 1.2        | 2.1        |
| Vanadium                      | µg/g     | 86   | 21                                  | 35.2       | 102        | 69         | 100        | 119        | 90         | 113        | 94         |
| Zinc                          | µg/g     | 290  | 33                                  | 55         | 146        | 131        | 134        | 152        | 114        | 136        | 140        |
| Chromium, Hexavalent          | µg/g     | 70   | <0.2                                | <0.2       | <0.2       | <0.2       | <0.2       | <0.2       | <0.2       | <0.2       | <0.2       |
| Cyanide, Free                 | µg/g     | 0.051  | --                                  | --         | <0.040     | <0.040     | <0.040     | <0.040     | <0.040     | <0.040     | <0.040     |
| Mercury                       | µg/g     | 0.27   | <0.10                               | <0.10      | <0.10      | <0.10      | <0.10      | <0.10      | <0.10      | <0.10      | <0.10      |
| Electrical Conductivity (2:1) | mS/cm    | 0.57   | --                                  | --         | 0.133      | 0.143      | 0.098      | 0.057      | 0.124      | 0.104      | 0.11       |
| Sodium Adsorption Ratio       | NA       | --   | --                                  | --         | 0.208      | 0.841      | 0.277      | 0.179      | 0.443      | 0.394      | 0.193      |
| pH, 2:1 CaCl2 Extraction      | pH Units | --   | --                                  | --         | 7.46       | 7.64       | 7.2        | 7.09       | 7.42       | 7.49       | 7.32       |




**Notes:**

G / S      Guideline / Standard  
 --          Not analyzed

- Value**      Parameters exceeds Table 1 criteria.
- Value      RDL exceeds Table 1 criteria
- Sample location has been excavated and removed from site.
- Exceedance interpreted to be naturally occurring
- (1)          Ontario Reg 153/04 (2011) Table 1: Full Depth Background Site Condition Standards, Residential/Parkland/Institutional/Industrial/Commercial/Community Property Use for Soil.

## Figures




**LEGEND**

- MONITORING WELL LOCATION (GOLDER, 2022)
- MONITORING WELL LOCATION (GOLDER, 2019)
- BOREHOLE/MONITORING WELL LOCATION (DST, 2015)
- BOREHOLE/MONITORING WELL LOCATION (DST, 2009)
- STORM SEWER ALIGNMENT
- SANITARY SEWER ALIGNMENT
- 2022 REMEDIATION (WSP 2022)
- HISTORICAL REMEDIATION (DST 2014/15)
- PHASE TWO PROPERTY AND RSC BOUNDARY

**NOTE(S)**  
 1. ALL DATA IN µg/L  
 2. \*MONITORING WELL DECOMMISSIONED AS PART OF REMEDIAL WORK

**REFERENCE(S)**  
 1. COORDINATE SYSTEM: NAD 1983 MTM 9



CLIENT  
**CLC LIMITED**

PROJECT  
**PHASE TWO ENVIRONMENTAL SITE ASSESSMENT, WATERIDGE VILLAGE PHASE 4, PART OF 1076 HEMLOCK PRIVATE, OTTAWA, ONTARIO**

TITLE  
**REMEDIAL EXCAVATIONS AT THE RSC PROPERTY**

|            |            |            |
|------------|------------|------------|
| CONSULTANT | YYYY-MM-DD | 2023-01-16 |
|            | DESIGNED   | ---        |
|            | PREPARED   | JEM        |
|            | REVIEWED   | TL         |
|            | APPROVED   | KPH        |


PROJECT NO. 19124906 CONTROL 0015 REV. 0 FIGURE **G1**

Path: S:\Clients\Canada\_Lands\_Company\Wateridge\_Village\00\_PRC\19124906\_CLC\_Emvs\0015\_PhaseTwo\_ESA\_Phase4\_19124906-0015-16-0001.mxd

IF THIS MEASUREMENT DOES NOT MATCH WHAT IS SHOWN, THE SHEET SIZE HAS BEEN MODIFIED FROM: 28mm



Path: \\gpc\p\proj\19124906\_CLC\_Env\env\001E\_PhaseTwo\_ESA\_Phase4\_1 | File Name: 19124906\_001E\_HS\_G2A.dwg



**LEGEND**

BOREHOLE/MONITORING IDENTIFIER → 20-01

GROUNDWATER LEVEL →

STRATIGRAPHY

WELL SCREEN

--- PHASE TWO PROPERTY AND RSC BOUNDARY

BEDROCK

FILL

SILTY SAND

SAMPLE MEETS THE TABLE 1 STANDARD


SAMPLE EXCEEDS THE TABLE 1 STANDARD

AREA OF REMEDIAL EXCAVATION

FLOOR VERIFICATION SAMPLE FROM 2014/15 REMEDIATION


WALL VERIFICATION SAMPLE FROM 2014/15 REMEDIATION

- NOTE(S)**
1. ALL LOCATIONS ARE APPROXIMATE.
  2. FOR DETAILED STRATIGRAPHY SEE RECORD OF BOREHOLE LOGS.
  3. FOR CROSS-SECTION LOCATION SEE FIGURE 2.
  4. SAMPLE DEPTH IN METRES BELOW GROUND SURFACE
  5. \*OFF-SITE DATA INCLUDED FOR REFERENCE PURPOSES ONLY



|   |            |            |
|---|------------|------------|
| <b>CLIENT</b>   |            |            |
| CLC LIMITED   |            |            |
| <b>PROJECT</b>  |            |            |
| PHASE TWO ENVIRONMENTAL SITE ASSESSMENT, WATERIDGE VILLAGE PHASE 6, PART OF 1076 HEMLOCK PRIVATE, OTTAWA, ONTARIO |            |            |
| <b>TITLE</b>  |            |            |
| CROSS-SECTION C-C' WITH METALS ANALYSIS AND EXCEEDANCES IN SOIL AT REMEDIATION TP-31                              |            |            |
| <b>CONSULTANT</b>   |            |            |
|   | YYYY-MM-DD | 2021-12-17 |
|   | DESIGNED   | ---        |
|   | PREPARED   | RS         |
|   | REVIEWED   | AW         |
|   | APPROVED   | KPH        |

IF THIS MEASUREMENT DOES NOT MATCH WHAT IS SHOWN, THE SHEET SIZE HAS BEEN MODIFIED FROM ANSIB 28 mm



**LEGEND**

BOREHOLE/MONITORING IDENTIFIER → 20-01

GROUNDWATER LEVEL →

STRATIGRAPHY →

WELL SCREEN →

--- PHASE TWO PROPERTY AND RSC BOUNDARY

SEWER TRENCH

TOPSOIL

BEDROCK

FILL

○ SAMPLE MEETS THE TABLE 1 STANDARD

● SAMPLE EXCEEDS THE TABLE 1 STANDARD


⊗ AREA OF REMEDIAL EXCAVATION

● FLOOR VERIFICATION SAMPLE FROM 2022 REMEDIATION

⊗ WALL VERIFICATION SAMPLE FROM 2022 REMEDIATION

**NOTE(S)**

1. ALL LOCATIONS ARE APPROXIMATE.
2. FOR DETAILED STRATIGRAPHY SEE RECORD OF BOREHOLE LOGS.
3. FOR CROSS-SECTION LOCATION SEE FIGURE 2.
4. SAMPLE DEPTH IN METRES BELOW GROUND SURFACE.



CLIENT  
**CLC LIMITED**


---

PROJECT  
PHASE TWO ENVIRONMENTAL SITE ASSESSMENT, WATERIDGE VILLAGE PHASE 4, PART OF 1076 HEMLOCK PRIVATE, OTTAWA, ONTARIO

---


TITLE  
**CROSS-SECTION D-D' WITH METALS ANALYSIS AND EXCEEDANCES IN THE SEWER TRENCH REMEDIATION**

---

|   |            |            |
|---|------------|------------|
| CONSULTANT  | YYYY-MM-DD | 2022-12-22 |
|  | DESIGNED   | ---        |
|   | PREPARED   | RS         |
|   | REVIEWED   | AW         |
|   | APPROVED   | KPH        |

Path: \\gpc\p\proj\19124906\19124906\_CLC\_Env\env\001E\_PhaseTwo\_ESA\_Phase4\_11\_File Name: 19124906\_001E\_HS\_G3A.dwg

IF THIS MEASUREMENT DOES NOT MATCH WHAT IS SHOWN, THE SHEET SIZE HAS BEEN MODIFIED FROM ANSIB 28 mm



**LEGEND**

BOREHOLE/MONITORING IDENTIFIER → 20-01

GROUNDWATER LEVEL →

STRATIGRAPHY →

WELL SCREEN →

--- PHASE TWO PROPERTY AND RSC BOUNDARY

SEWER TRENCH

TOPSOIL

BEDROCK

FILL

○ SAMPLE MEETS THE TABLE 1 STANDARD


● SAMPLE EXCEEDS THE TABLE 1 STANDARD

◌ AREA OF REMEDIAL EXCAVATION

● FLOOR VERIFICATION SAMPLE FROM 2022 REMEDIATION

⊗ WALL VERIFICATION SAMPLE FROM 2022 REMEDIATION

- NOTE(S)**
1. ALL LOCATIONS ARE APPROXIMATE.
  2. FOR DETAILED STRATIGRAPHY SEE RECORD OF BOREHOLE LOGS.
  3. FOR CROSS-SECTION LOCATION SEE FIGURE 2.
  4. SAMPLE DEPTH IN METRES BELOW GROUND SURFACE.



CLIENT  
**CLC LIMITED**

PROJECT  
PHASE TWO ENVIRONMENTAL SITE ASSESSMENT, WATERIDGE VILLAGE PHASE 4, PART OF 1076 HEMLOCK PRIVATE, OTTAWA, ONTARIO


TITLE  
**CROSS-SECTION D-D' WITH PAH ANALYSIS AND EXCEEDANCES IN THE SEWER TRENCH REMEDIATION**

|            |            |            |
|------------|------------|------------|
| CONSULTANT | YYYY-MM-DD | 2022-12-22 |
|            | DESIGNED   | ---        |
|            | PREPARED   | RS         |
|            | REVIEWED   | AW         |
|            | APPROVED   | KPH        |

PROJECT NO. 19124906      CONTROL 0015      REV. 0      FIGURE G3B

Path: \\gpc\p\proj\19124906\19124906\_CLC\_Env\env\001E\_PhaseTwo\_ESA\_Phase4\_11\_File Name: 19124906\_001E\_HS\_G3B.dwg


IF THIS MEASUREMENT DOES NOT MATCH WHAT IS SHOWN, THE SHEET SIZE HAS BEEN MODIFIED FROM ANSIB 28 mm



**LEGEND**

- BOREHOLE/MONITORING IDENTIFIER → 20-01
- GROUNDWATER LEVEL →
- STRATIGRAPHY →
- WELL SCREEN →
- PHASE TWO PROPERTY AND RSC BOUNDARY
- SEWER TRENCH
- TOPSOIL
- BEDROCK
- FILL
- SAMPLE MEETS THE TABLE 1 STANDARD
- SAMPLE EXCEEDS THE TABLE 1 STANDARD
- AREA OF REMEDIAL EXCAVATION
- FLOOR VERIFICATION SAMPLE FROM 2022 REMEDIATION
- ⊗ WALL VERIFICATION SAMPLE FROM 2022 REMEDIATION

- NOTE(S)**
- ALL LOCATIONS ARE APPROXIMATE.
  - FOR DETAILED STRATIGRAPHY SEE RECORD OF BOREHOLE LOGS.
  - FOR CROSS-SECTION LOCATION SEE FIGURE 2.
  - SAMPLE DEPTH IN METRES BELOW GROUND SURFACE.



CLIENT  
**CLC LIMITED**


---

PROJECT  
PHASE TWO ENVIRONMENTAL SITE ASSESSMENT, WATERIDGE VILLAGE PHASE 4, PART OF 1076 HEMLOCK PRIVATE, OTTAWA, ONTARIO

---

TITLE  
**CROSS-SECTION D-D' WITH PHC ANALYSIS AND EXCEEDANCES IN THE SEWER TRENCH REMEDIATION**

---

|   |            |            |
|---|------------|------------|
| CONSULTANT  | YYYY-MM-DD | 2022-12-22 |
|  | DESIGNED   | ---        |
|   | PREPARED   | RS         |
|   | REVIEWED   | AW         |
|   | APPROVED   | KPH        |


---

|                         |                 |           |                      |
|-------------------------|-----------------|-----------|----------------------|
| PROJECT NO.<br>19124906 | CONTROL<br>0015 | REV.<br>0 | FIGURE<br><b>G3C</b> |
|-------------------------|-----------------|-----------|----------------------|


Path: \\gpc\gpc\comp\scad\office\Ontario\GIS\McClelland\Canada\_Lands\_Company\Wateridge\_Village\09\_FRO\_19124906\_CLC\_Env\env001E\_PhaseTwo\_ESA\_Phase4\_11\_File Name: 19124906\_0015\_HS\_G3C.dwg

IF THIS MEASUREMENT DOES NOT MATCH WHAT IS SHOWN, THE SHEET SIZE HAS BEEN MODIFIED FROM ANS/B 28 mm

Path: \\gpc\projects\19124906\_19124906\_CLC\_Ervin\001E\_PhaseTwo\_ESA\_Phase4\_11\_Files\Name - 19124906\_001E-HS-G4A.dwg




LEGEND



- FILL
- SAMPLE MEETS THE TABLE 1 STANDARD
- SAMPLE EXCEEDS THE TABLE 1 STANDARD
- AREA OF REMEDIAL EXCAVATION
- FLOOR VERIFICATION SAMPLE FROM 2014/15 REMEDIATION
- WALL VERIFICATION SAMPLE FROM 2014/15 REMEDIATION

NOTE(S)

1. ALL LOCATIONS ARE APPROXIMATE.
2. FOR DETAILED STRATIGRAPHY SEE RECORD OF BOREHOLE LOGS.
3. FOR CROSS-SECTION LOCATION SEE FIGURE 2.
4. SAMPLE DEPTH IN METRES BELOW GROUND SURFACE.



CLIENT  
CLC LIMITED

PROJECT  
PHASE TWO ENVIRONMENTAL SITE ASSESSMENT, WATERIDGE VILLAGE PHASE 6, PART OF 1076 HEMLOCK PRIVATE, OTTAWA, ONTARIO


TITLE  
**CROSS-SECTION E-E' WITH PHC ANALYSIS AND EXCEEDANCES IN SOIL AT BUILDING 126-1 REMEDIATION**

|            |            |            |
|------------|------------|------------|
| CONSULTANT | YYYY-MM-DD | 2021-12-17 |
|            | DESIGNED   | ---        |
|            | PREPARED   | RS         |
|            | REVIEWED   | AW         |
|            | APPROVED   | KPH        |

|                         |                 |           |               |
|-------------------------|-----------------|-----------|---------------|
| PROJECT NO.<br>19124906 | CONTROL<br>0015 | REV.<br>0 | FIGURE<br>G4A |
|-------------------------|-----------------|-----------|---------------|

IF THIS MEASUREMENT DOES NOT MATCH WHAT IS SHOWN, THE SHEET SIZE HAS BEEN MODIFIED FROM: A4/B

Path: \\gpc\p\proj\19124906\_CLC\_Env\env\001E\_PhaseTwo\_ESA\_Phase4\_1 | File Name: 19124906\_001E\_HS\_G5A.dwg



**LEGEND**

BOREHOLE/MONITORING IDENTIFIER → 20-01

GROUNDWATER LEVEL →

STRATIGRAPHY

WELL SCREEN

FILL

CLAY

SAMPLE MEETS THE TABLE 1 STANDARD

SAMPLE EXCEEDS THE TABLE 1 STANDARD


AREA OF REMEDIAL EXCAVATION

FLOOR VERIFICATION SAMPLE FROM 2014/15 REMEDIATION

WALL VERIFICATION SAMPLE FROM 2014/15 REMEDIATION

**NOTE(S)**

- ALL LOCATIONS ARE APPROXIMATE.
- FOR DETAILED STRATIGRAPHY SEE RECORD OF BOREHOLE LOGS.
- FOR CROSS-SECTION LOCATION SEE FIGURE 2.
- SAMPLE DEPTH IN METRES BELOW GROUND SURFACE.



CLIENT  
**CLC LIMITED**

PROJECT  
PHASE TWO ENVIRONMENTAL SITE ASSESSMENT, WATERIDGE VILLAGE PHASE 6, PART OF 1076 HEMLOCK PRIVATE, OTTAWA, ONTARIO


TITLE  
**CROSS-SECTION F-F' WITH PAH ANALYSIS AND EXCEEDANCES IN SOIL AT BLD 126-2 REMEDIATION**

|            |            |            |
|------------|------------|------------|
| CONSULTANT | YYYY-MM-DD | 2021-12-17 |
|            | DESIGNED   | ---        |
|            | PREPARED   | JEM        |
|            | REVIEWED   | AW         |
|            | APPROVED   | KPH        |

PROJECT NO. 19124906      CONTROL 0015      REV. 0      FIGURE G5A

IF THIS MEASUREMENT DOES NOT MATCH WHAT IS SHOWN, THE SHEET SIZE HAS BEEN MODIFIED FROM ANS/B

Path: \\gpc\p\proj\19124906\_CLC\_E\env\001E\_PhaseTwo\_ESA\_Phase4\_1 | File Name: 19124906\_001E\_HS\_G5B.dwg



**LEGEND**

BOREHOLE/MONITORING IDENTIFIER → 20-01

GROUNDWATER LEVEL →

STRATIGRAPHY

WELL SCREEN

FILL

CLAY

SAMPLE MEETS THE TABLE 1 STANDARD

SAMPLE EXCEEDS THE TABLE 1 STANDARD


AREA OF REMEDIAL EXCAVATION

FLOOR VERIFICATION SAMPLE FROM 2014/15 REMEDIATION

WALL VERIFICATION SAMPLE FROM 2014/15 REMEDIATION

**NOTE(S)**

- ALL LOCATIONS ARE APPROXIMATE.
- FOR DETAILED STRATIGRAPHY SEE RECORD OF BOREHOLE LOGS.
- FOR CROSS-SECTION LOCATION SEE FIGURE 2.
- SAMPLE DEPTH IN METRES BELOW GROUND SURFACE.



CLIENT  
**CLC LIMITED**

PROJECT  
PHASE TWO ENVIRONMENTAL SITE ASSESSMENT, WATERIDGE VILLAGE PHASE 6, PART OF 1076 HEMLOCK PRIVATE, OTTAWA, ONTARIO

TITLE  
**CROSS-SECTION F-F' WITH PHC ANALYSIS AND EXCEEDANCES IN SOIL AT BLD 126-2 REMEDIATION**

|            |            |            |
|------------|------------|------------|
| CONSULTANT | YYYY-MM-DD | 2021-12-17 |
|            | DESIGNED   | ---        |
|            | PREPARED   | JEM        |
|            | REVIEWED   | AW         |
|            | APPROVED   | KPH        |

PROJECT NO. 19124906      CONTROL 0015      REV. 0      FIGURE G5B

IF THIS MEASUREMENT DOES NOT MATCH WHAT IS SHOWN, THE SHEET SIZE HAS BEEN MODIFIED FROM ANSIB 28 mm



**WSP.com**