

200 mm — 🔫 🗖 $| \bigcirc \bigcirc |$ _____ $| \bigcirc \bigcirc |$ _____ TOP VIEW SIDE ELEVATION FRONT ELEVATION

07 BIKE RACK


SCALE NTS

L200 / TYPE

Y	QTY	BOTANICALNAME	COMMON NAME	SIZE	CONDITION	NOTES
	JS TRE					
AC	1	Amelanchier canadensis	Shadblow Serviceberry	2000mm ht	B&B	Multi-ster
AF	6	Acer x freemanii 'Autumn Blaze'	Freeman's Maple	60mm dia.	B&B	
AP	1	Acer pensylvanicum	Striped Maple	7 gal pot	Potted	Single lead
CO	3	Celtis occidentalis	Common Hackberry	60mm dia.	B&B	
GP	4	Ginkgo biloba 'Autumn Gold'	Maiden Tree 'Autumn Gold'	60mm dia.	B&B	
MS	1	Magnolia stellata 'Royal Star'	Star Magnolia	2000mm ht	B&B	Multi-ster
OV	1	Ostrya virginiana	Eastern Hop Hornbeam	60mm dia.	B&B	
QP	1	Quercus palustris	Pin Oak	60mm dia.	B&B	
SK	5	Gleditsia triacanthos var. inermis 'Draves	s'Streetkeeper Honeylocust	60mm dia.	B&B	
ONIFEF	ROUS S	HRUBS				
TMD	35	Taxus X Media 'Densiformis'	Dense Spreading Yew	500mm spr	Potted	1200mm c
TOF	18	Thuja occidentalis 'Fastigiata'	Pyramidal Cedar	1500mm ht	Potted	1000mm c
	JS SHR	IRS				
BTR	47	Berberis thunbergii 'Royal Burgundy'	Japanese Barberry	400mm ht	Potted	800mm o
CPR		Campsis radicans	Trumpet Vine	2 gal pot	Potted	000111110
CAF	70	Cornus sericea 'Farrow' Artic Fire	Arctic Fire Red Twig Dogwood	600mm ht	Potted	1000mm (
EAC	17	Euonymus alatus 'Compactus'	Dwarf Burning Bush	600mm ht	Potted	1200mm
	3	Humulus lupulus	Commun Hop	2 gal pot	Potted	120011111
	42	Hydrangea arborescens 'Annabelle'	Annabelle Hydrangea	2 gal pot	Potted	1000mm
HPK				2 gai pot 600mm ht		1000mm
	2	Hydrangea paniculata 'Kyushu'	Kyushu Hydrangea		Potted	
	17	Hydrangea paniculata 'Limelight'	Limelight Hydrangea	600mm ht	Potted	1000mm
	22	Rhus aromatica 'Gro-Low'	Fragant Sumac	400mm ht	Potted	800mm c
SBT	58	Spiraea betulifolia 'Tor'	Birch Leaf Spirea	400mm ht	Potted	800mm o
SMP	9	Syringa meyeri 'Palibin'	Dwarf Korean Lilac	600mm ht	Potted	1200mm
SSS	87	Sorbaria sorbifolia 'Sem'	Sem False Spirea	400mm ht	Potted	800mm (
SXA		Spirea x arguta 'Compacta'	Dwarf Garland Spirea	600mm ht	Potted	1200mm
TOS	8	Thuja Occidentalis 'Smaragd'	Emerald Green Arborvitea	1500mm ht	Potted	800mm (
RNEME		GRASSES				
hma	140	Hakonechloa macra 'Aureola'	Hakone Grass 'Aureola'	1L pot	Potted	400mm (
pvs	92	Panicum virgatum 'Shenandoah'	Switch Grass 'Shenandoah'	1L pot	Potted	400mm (
sla	103	Sesleria autumnalis	Autumn Moor Grass	1L pot	Potted	350mm (
RENN	ALS					
asc	60	Anemone x hybrida 'September Charm'	Japanese Anemone	1L pot	Potted	450mm (
gao	65	Galium odoratum	Sweet Woodruff	1L pot	Potted	400mm (
grz	52	Geranium 'Rozanne'	Hardy Geranium Rozanne	1L pot	Potted	450mm (
haw	283	Hemerocallis 'Alice in Wonderland'	Alice in Wonderland Daylily	1L pot	Potted	400mm (
nba	48	Hosta 'Blue Angel'	Large Blue Hosta	1 gal pot	Potted	500mm (
ngu	68	Hosta 'Guacamole'	Guacamole Hosta	1 gal pot	Potted	500mm (
nrw	92	Nepeta racemosa 'Walker's Low'	Nepeta' Walker's Low Catmint	1L pot	Potted	450mm d
pst	338	Pachysandra terminalis	Japanese Spurge	1L pot	Potted	300mm (
pov	26	Polygonatum odoratum 'Variegatum'	Solomon's Seal	1L pot	Potted	400mm d
tss	143	Tiarella cordifolia 'Sugar and Spice'	Foam Flower 'Suger and Spice'	1L pot	Potted	300mm 0

PROPOSED PLANT LIST : ORNAMENTAL GRASSES AND PERENNIALS FOR ROOF GARDEN COMMON NAME SIZE CONDITION WIDTH CODE QTY BOTANICAL NAME

ORNEMENTAL GRASSES							
pvs	gA	20	Panicum virgatum 'Shenandoah'	Switch Grass 'Shenandoah'	1L pot	Potted	400mm o.c
SCS	gB	16	Schizachyrium scoparium	Little Bluestem	1gal pot	Potted	500mm o.c
sbh	gC	31	Sporobolus heterolepis	Prairie Dropseed	1L pot	Potted	450mm o.c
PERENNIAL	S						
aml	A	45	Achillea millefolium	White Yarrow	1L pot	Potted	400mm o.c
als	В	49	Allium schoenoprasum	Chives	1L pot	Potted	300mm o.c
epm	С	49	Echinacea purpurea 'Magnus'	Magnus Coneflower	1L pot	Potted	450mm o.c
saj	D	45	Sedum 'Autumn Joy'	Stonecrop 'Herbstfreude'	1L pot	Potted	450mm o.c
skc	E	66	Sedum kamtschaticum	Orange Stonecrop	1L pot	Potted	300mm o.c
srf	F	35	Solidago rugosa 'Fireworks'	Rough Goldenrod	1gal pot	Potted	500mm o.c



AND MATERIALS DEVELOPED FOR WINTER PROTECTION SHALL REMAIN IN THE POSSESSION OF THE

. AT THE TIME OF FINAL WARRANTY ACCEPTANCE, ALL MATERIAL MUST BE IN A HEALTHY AND VIGOROUS CONDITION. BEDS AND TREE PITS MUST BE FRESHLY CULTIVATED AND FREE OF WEEDS, RUBBISH AND


DEBRIS. ALL STAKES, WIRES, HOSE AND OTHER ACCESSORIES MUST BE REMOVED UPON FINAL

CUSTOMER AFTER THE WARRANTY PERIOD OF THE WORK.

ACCEPTANCE, EXCEPT FOR PLANT MATERIAL UNDER WARRANTY.

FORUM ASSET MANAGEMENT EAST PODIUM, 2ND FLOOR 181 BAY STREET TORONTO, ON, M5J 2T3

T. 416-947-0389 WWW.forumam.com



MECHANICAL & ELECTRICAL

7405 East Danbro Crescent

Mississauga, ON, L5N 6P8

www.jainconsultants.com

2611 Queensview Drive

Ottawa, ON, K2B 8K2

T. 613-829-2800

www.wspgroup.com

Jain Sustainability

T. 905-285-9900

2nd Floor

STRUCTURAL D+M Structural Engineering

333 Preston Street Ottawa, ON, K1S 5N4 T. 613-651-9490 www.dm-structural.ca LANDSCAPE

Lemav Saint-Jacques Street Montreal, QC H4C 1H2

T. 514-932 5101 www.lemay.com

SURVEYOR Annis, O'Sullivan, Vollebekk Ltd. Suite 500

14 Concourse Gate Nepean, ON, K2E 7S6


T. 613-727-0850 www.aovltd.com

NOTES

- CONTRACTOR TO CHECK AND VERIFY ALL DIMENSIONS PRIOR TO COMMENCING WORK.
- CONTRACTOR TO COMPLY WITH ALL BUILDING CODES, REGULATIONS, AND ORDINANCES OF AUTHORITIES HAVING
- JURISDICTION. THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION UNLESS STAMPED ISSUED FOR CONSTRUCTION BY LEMAY
- ARCHITECTURE AND DESIGN LTD. 4. DO NOT SCALE DRAWING. 5. THIS DRAWING MAY NOT BE COPIED, ALTERED, OR DISTRIBUTED
- IN WHOLE OR IN PART WITHOUT WRITTEN PERMISSION. COPYRIGHT © LEMAY ARCHITECTURE AND DESIGN LTD. 6. REPORT ANY ERRORS AND OMISSIONS TO THE CONSULTANT
- IMMEDIATELY BEFORE COMMENCING WORK. DEVIATIONS FROM THE CONTRACT DOCUMENTS WITHOUT WRITTEN APPROVAL FROM CONSULTANT ARE SUBJECT TO
- CORRECTIONS AT CONTRACTOR EXPENSE. 8. DIMENSIONS ARE IN METRIC (MM) UNLESS NOTED OTHERWISE

LIMIT OF PROPERTY

		7.5m SETBACK GEOTECHNICAL REQUIREMENT
		3m SETBACK GEOTECHNICAL REQUIREMENT
		EXISTING TREE TO REMAIN AND PROTECT REFER TO L100 FOR SPECIES
+	-)	PROPOSED DECIDOUS TREE
++++	+	PROPOSED DECIDOUS SHRUBS
		PROPOSED CONIFEROUS SHRUBS
		PROPOSED BIKE RACKS
		PROPOSED FREESTANDING BENCH WITH BACK AND ARM RESTS
		PROPOSED BENCH
		PROPOSED LOW LEVEL LIGHT BOLLARD (REFER TO APPENDIX A_PHOTOMETRY)
o	-00-	PROPOSED METAL GUARDRAIL
		PROPOSED METAL HAND RAIL
╼゠		PROPOSED ROOT BARRIER "DEEPROOT" UB 48-2 MODEL
+ + + + + + + + + + + + + + + + + + + +	+ + + + + +	PROPOSED SODDED AREAS
		PROPOSED SEEDED AREA (ROOF)
		PROPOSED PERENNIALS / ORNEMENTAL GRASSES
		PROPOSED CRUSHED STONE OR LIGHT MATERIAL
		PROPOSED PRECAST CONCRETE PAVERS (PEDESTRIAN)
		PROPOSED PRECAST CONCRETE PAVERS (VEHICULAR)
		PROPOSED PRECAST CONCRETE PAVERS ON ROOF
		PROPOSED PEA GRAVEL FOR MAINTENANCE STRIP
		PROPOSED PRECAST CONCRETE STAIRS / WALL / SEAT WALLS
		PROPOSED CAST IN PLACE CONCRETE PAVEMENT
V		BUILDING ACCES OR EGRESS
SSUE		



3 2024-11-27 ISSUED FOR SPA RESUBMISSION - REVISION 2 2 2024-11-13 ISSUED FOR SPA RESUBMISSION - REVISION 1

DESCRIPTION

2024-09-06 ISSUED FOR SPA RESUBMISSION


24-0353 - 15(17) OBLATS AVENUE, OTTAWA

SHEET NAME PLANTING PLAN

SHEET SIZE - ARCH E (914.4X1219.2mm) (36"X48")

DATE

1. PLEASE REFER TO 03-L200 LANDCAPE PLAN FOR SPACING



DATE / TIME STAMP 11/27/2024 1:05:13 PM

> SHEET NUMBER 200

> > #18846