

SITE AREA	17,615.32 m ² (1.76 ha)
PAVED AREA	5874m ² (33.34%)
LANDSCAPED AREA	7057.08 m ² (40.06%)
TOTAL BUILDING COVERAGE	4684.2325 m ² (26.592%)
TOTAL GROSS FLOOR AREA	17,617,5428 m ²
DENSITY (UPH)	111 UPH
ZONE CATEGORY	R4(2)

DWELLING BLOCK	DWELLING TYPE	GROSS FLOOR AREA (m ²)	UNITS
BLOCKS 8 - 10	24 UNITS STACKED DWELLING		48
BLOCKS 4 - 5 - 6 - 7 - 9	20 UNITS STACKED DWELLING		100
BLOCKS 1 - 2 - 3	16 UNITS STACKED DWELLING		48
TOTAL UNITS			196

ZONE PROVISION - PLANNED UNIT DEVELOPMENT		REQUIRED	PROPOSED
162A(2)	Min. Lot Area (m ²)	1400 m ²	17615.32 m ²
162A(2)	Min. Lot Width (m)	18	223.9
162A(2)	Min. Front Yard Setback (m)	3	>3.4
162B.6	Min. Rear Yard Setback (m)	6	4.5
162B(2)	Min. Corner side setback	3	3
162A(2)	Max building Height (m)	15	13.5
161	Landscaped Area	30%	39%
131.1	Min. Width of Private Way / Parking Aisle (m)	6	6.1
131.4a	Min. Setback for Any Wall of a Residential Building Within a Planned Unit Development	1.2	5
131.2	Min. setback for any wall of a residential use building to a private way	1.8	>4.5
137	AMENITY AREA		
137.6	Total min. amenity area (4m ² per unit)	1176 m ²	4903.67 m ²
137.6	Min. Communal Amenity Area m ² (Min. 50% area)	588 m ²	248.42 m ²
45	PERMITTED PROJECTION INTO REQUIRED YARDS		
65.5.i	Fire escapes, Open Stairways, Stoop (m)	>0.6m to lot line	0.5 m
65.6.a(i)	Covered or Uncovered Balcony, Porch and Deck line	2m no closer than 1 to a lot line	2m no closer than 1.74 to a lot line

PARKING REQUIREMENTS		REQUIRED	PROPOSED
101 (Table R10)	Resident Parking - 1.2 spaces/unit	235	19% (1.0)
102 (Table column III)	Visitor Parking - 0.2 spaces/unit	39	22 (0.11)
106.1	Min. Perpendicular Parking Space Size (m)	2.4 x 5.2	2.6 x 5.2
107 (Table 107.d)	Min. Requires Aisle Width	6.0	6.1
BARRIER FREE PARKING			
Traffic and Parking By-law Section 111	Min. Barrier Free Parking **	1	1
111	BICYCLE STORAGE		
111B	Min. bicycle parking space dimension, horizontal (m)	Width: 0.6m Length: 1.8m	0.6 1.8
111A(b)	Min. Bicycle parking space access aisle Width (m)	1.5	1.5
111.1.1	Min. Bicycle Parking 0.5 spaces/unit	98	100
110(a)(b)	LANDSCAPE AREA SURROUNDING PARKING LOT		
110.a	Abutting a Street (m)	3	>16m
110.b	Not Abutting a street (m)	3	>3m
110.1.b	Min. % of parking lot landscape	15%	>19%
110	REFUSE COLLECTION AREAS		
110.3b	Min. Waste collection setback to lot line	3	>30m
110.3.c/d	Opaque Screen Min. Height (m)	2	2***

GARBAGE:		PH X			
REQUESTED BY ZONING:					
GARBAGE: 0.231 CUBIC YARD /UNIT	0.231 X 196= 45.27 CUBIC YARD (6.5 CU.YD./BIN)	= 7 BINS	PROPOSED: 8 BINS		
RECYCLING (GMP) 0.018 CUBIC YARD /UNIT	0.018 X 196 = 3.54 CUBIC YARDS (6.5 CU.YD./BIN)	= 1 BIN	PROPOSED: 1 BINS		
RECYCLING (FIBRE) 0.042 CUBIC YARD /UNIT	0.042 X 196 = 12.15 CUBIC YARDS (6.5 CU.YD./BIN)	= 2 BINS	PROPOSED: 2 BINS		
ORGANIC 240L PER 50 UNITS	240 L X 3.92 = 940 L (240 L /BIN)	= 4 BINS	PROPOSED: 4 BINS		
		TOTAL BINS = 14 BINS	TOTAL PROPOSED: 15 BINS		

**Per the 2015 Guide Accessibility Design Standards - Section 3.1.1 Design of Public Parking, 4% of parking spaces provided for public use must be accessible. 1 of the provided 21 visitor spaces have been designed to be barrier-free. 1 Type A site provided.

***Section 110(3)(d) where an in-ground refuse container is provided, the screening requirement of Section (3)(c) above may be achieved with soft landscaping (Bylaw 2020-299)

- SITE PLAN NOTES
1. DO NOT SCALE DRAWINGS FOR PRINT.
 2. THIS DRAWING IS THE EXCLUSIVE PROPERTY OF Q4 ARCHITECTS AND CAIVAN . COPYRIGHT RESERVED.
 3. WALKWAYS AND CURBS TO BE TIED INTO PUBLIC ROW WHERE APPLICABLE.
 4. REFERENCE CITY OF OTTAWA T.W.S.I. DETAIL SC7.3

Q4A
ARCHITECTS

Q4 ARCHITECTS INC.

4110 YONGE STREET
Suite 602, Toronto ON.
M2P 2B7

T: 416.322.6334
F: 416.322.7294
E: info@q4architects.com

The contractor / builder must verify all dimensions on the job and report any discrepancy to the designer before proceeding with the work.

Drawings are NOT to be scaled. All drawings and specifications are instruments of service and the copyright property of the designer and must be returned upon request.

Q4 Architects Inc. retains the copyright in all drawings, plans, sketches, and all digital information. They may not be copied or used for any other projects or purposes or distributed without the written consent of Q4 Architects Inc.

LEGEND

STACKED TOWNS	NO PARKING
ENTRANCE	BARRIER FREE PARKING
BALCONY	BARRIER FREE PARKING SIGNAGE
PORCH	V VISITOR PARKING
PROJECTION (STAIRS)	BKE RACKS
PAVERS	EARTH BIN (6.5 yd ⁻¹)
HEAVY DUTY CONCRETE PAVING	HYDRO TRANSFORMER
LIGHT DUTY ASPHALT PAVING	LIGHT POLE
CROSSWALK	S.S. SHOW STORAGE AREA
CURB (0.2m)	L/A LANDSCAPED AREA
DEPRESSED CURB	MEDIUM DECIDUOUS TREE*
TACTILE WALKING SURFACE INDICATOR	SMALL DECIDUOUS TREE*
BLOCK BOUNDARY	DECIDUOUS SHRUB*
WASTE ENCLOSURE FENCE	CONIFEROUS SHRUB*
WOOD PRIVACY FENCE	GRASSES/PERENNIALS*

ATTACHED A1 PLAN, FROM THE SURVEYED PLAN SEPT 13, XREF INTO DRAWING

*TREES AND SHRUB LOCATIONS TO BE CONFIRMED ON LANDSCAPE PLAN

13	SPI - CITY RESUBMISSION	2025.01.24 JM/CT
12	ADDITIONAL COMMENT- ISSUED TO CLIENT	2024.12.10 JM/CT
11	NEW LAYOUT- ISSUED TO CLIENT	2024.11.27 JM/CT
10	ADDITIONAL COMMENTS- ISSUED TO CLIENT	2024.08.27 JM/CT
9	ADDITIONAL COMMENTS- ISSUED TO CLIENT	2024.08.26 JM/CT
8	ADDITIONAL COMMENTS- ISSUED TO CLIENT	2024.08.16 JM/CT
7	ADDITIONAL COMMENTS- ISSUED TO CLIENT	2024.08.06 JM/CT
6	ADDITIONAL SITE STATS- ISSUED TO CLIENT	2024.07.25 JM/CT
5	REVISED AS PER CITY AND CLIENT COMMENTS	2024.07.17 JM/CT
4	REVISED GARBAGE LAYOUT	2024.07.16 JM/CT
3	SPI-2 AFTER CITY'S COMMENTS	2024.07.15 JM/CT
2	ADD HYDRO TRANSFORMER	2024.07.05 JM/CT
1	G4A SPI1	2024.06.27 JM/CT

Issued / Revision Chart

Project Title

CONSERVANCY STACKED TOWNS

3285 Borrisokane Rd
Location OTTAWA, ON.

Plan No. 18754 and File No. D07-12-24-0097

Part of Lot 14, Concession 3 (Rideau From 1), Geographic Township of Nepean

Legal Name Part of PIN 04595-4929 (LT)

Client CAIVAN

Project No.

Scale 1:500

Drawn By CT

Checked By CT

OVERALL SITE PLAN

SP1