Report

Project: 30282806-6.4.3

# 8201 CAMPEAU DRIVE SERVICING BRIEF



## **Table of Contents**

1	INTRO	ODUCTION	
•	1.1	Guidelines and Standards	
	1.2	Pre-Consultation Meeting	
	1.3	Geotechnical Concerns	
_	\A/ A T F	ER DISTRIBUTION	•
2	2.1	Existing Conditions	
	2.1	Design Criteria	
	2.2	2.2.1 Water Demands	
		2.2.2 System Pressures	
		2.2.3 Fire Flow Rate	
		2.2.4 Boundary Conditions	
	2.3	Proposed Water Plan	
_			
3		TEWATER	
	3.1	Existing Conditions	
	3.2	Proposed Sewers	
		3.2.1 Design Flow:	
		3.2.2 Population Density:	
4	SITE	STORMWATER MANAGEMENT	10
	4.1	Existing Conditions	10
	4.2	Design Criteria Error! Bookmark	not defined
	4.3	Stormwater Management	
		4.3.1 Water Quantity Control	14
5	SEDI	MENT AND EROSION CONTROL PLAN	16
	5.1	General	16
	5.2	Trench Dewatering	16
	5.3	Bulkhead Barriers	16
	5.4	Seepage Barriers	16
	5.5	Surface Structure Filters	16
6	CONC	CLUSIONS & RECOMMENDATIONS	13
•	6.1	Conclusions	
	6.2	Recommendations	17

### List of Appendices

**APPENDIX A** 

Site Plan for 8201 Campeau Drive

City of Ottawa Pre-Consultation Meeting Notes City of Ottawa Study and Plan Identification Checklist

30282806-001 General Plan of Services

**APPENDIX B** 

**Boundary Conditions** 

Water Demand Calculations

FUS Calculations Water Model Results

**APPENDIX C** 

Sanitary Sewer Design Sheet

30282806-400 Sanitary Drainage Area Plan

**APPENDIX D** 

Storm Sewer Design Sheet

30282806-500 Storm Drainage Area Plan Modified Rational Method SWM Calculations

Runoff Coefficient Calculations Infiltration Gallery Calculations

EZ Storm Underground Storage Detail Sheets

**APPENDIX E** 

30282806-900 Erosion and Sediment Control Plan

30282806-010 Notes and Legends 30282806-200 Grading Plan

July 2025 iii

#### 1 INTRODUCTION

8201 Campeau Drive is located at the South-East intersection of Campeau Drive and Taggart Road in Ottawa, Ontario. This site is Phase 1 of a larger development consisting of residential dwelling units, commercial units and greenspace amenity spaces. The site is comprised of two buildings with a communal link separating the two buildings and is abutted by Campeau Drive to the North, Taggart Road to the East and existing undeveloped land to the East and South. Vehicle access to the site will be provided on Taggart Road. Pedestrian access to the building entrances will be provided from Campeau Drive and Taggart Road.

Arcadis Professional Services (Canada) Inc. (formerly IBI Group) has been retained by 8201 Campeau Drive Inc. to provide professional engineering services for 8201 Campeau Drive. The subject site including the parkland is approximately 1.40 ha and consists of 176 apartment units in building 1 and 147 apartment units in building 2 for a total of 323 dwelling units. Refer to key plan on **Figure 1.1** for Site location.



Figure 1.1 Site Location

The proposed servicing design conforms to current City of Ottawa and MECP design criteria.

#### 1.1 Guidelines and Standards

This evaluation takes into consideration the City of Ottawa Sewer Design Guidelines (OSDG) (October 2012), and the February 2014 Technical Bulletin ISDTB-2014-01, the September 2016 Technical Bulletin PIEDTB-2016-01, the June 2018 Technical Bulletin ISTB-2018-04, October 2019 Technical Bulletin 2019-01, and the July Technical Bulletin 2019-02.

It also considers the City of Ottawa Water Distribution Design Guidelines (OWDDG), and the 2010 Technical Bulletin 2010-02, the 2014 Technical Bulletin 2014-02, the 2018 Technical Bulletin 2018-02 and the 2020 Technical Bulletin 2020-02.

All specifications are as per current City of Ottawa standards and specifications, and Province of Ontario (OPSS/D) standards, specifications and drawings.

#### 1.2 Pre-Consultation Meeting

The City of Ottawa hosted a pre-consultation meeting on March 11<sup>th</sup>, 2025. Notes of the meeting and City of Ottawa Planning Checklist are provided in **Appendix A**. There were no major engineering concerns flagged in this meeting.

#### 1.3 Geotechnical Concerns

A geotechnical report entitled "Geotechnical Investigation – Proposed Development – 8201 Campeau Drive – Ottawa, Ontario" Report PG6934-1 dated October 4, 2024 by Paterson Group Inc. has been prepared for the subject site.

The objective of the investigation report include:

- Determination of the subsoil and groundwater conditions;
- Provision of geotechnical recommendations pertaining to the design and development of the subject site including construction considerations.

Among other items, the report comments on the following:

- Site grading;
- Foundation design;
- Pavement structure;
- Infrastructure construction;
- Groundwater control;

The report concludes that the subject site is considered suitable for the proposed development.

#### 2 WATER DISTRIBUTION

#### 2.1 Existing Conditions

8201 Campeau Drive will be serviced with potable water from the City of Ottawa's existing watermains. There is an existing 203 mm diameter PVC watermain on Taggart Road and a 600mm diameter watermain on Campeau Drive. For the purpose of this development, only connections to Taggart Road will be considered.

#### 2.2 Design Criteria

#### 2.2.1 Water Demands

The proposed development consists of 323 apartment units, split into two buildings. In order to calculate water demand rates, the per unit population density and consumption rates are taken from Tables 4.1 and 4.2 of the Ottawa Design Guidelines – Water Distribution were used and are summarized as follows:

•	1 Bedroom Apartment	1.4 person per average apartment		
•	2 Bedroom Apartment	2.1 person per average apartment		
•	3 Bedroom Apartment	3.1 persons per average apartment		

•	Average Day Demand	280 l/cap/day
•	Peak Daily Demand	700 l/cap/day
•	Peak Hour Demand	1.540 l/cap/day

A water demand calculation sheet is included in **Appendix B** and the total water demands are summarized as follows:

•	Average Day	1.59 l/s
•	Maximum Day	3.99 l/s
•	Peak Hour	8.77 l/s

#### 2.2.2 System Pressures

The 2010 City of Ottawa Water Distribution Guidelines states that the preferred practice for the design of a new distribution system is to have normal operating pressures range between 345 kPa (50 psi) and 552 kPa (80 psi) under maximum daily flow conditions. Other pressure criteria identified in the guidelines are as follows:

Minimum Pressure	Minimum system pressure under peak hour demand conditions shall not be less than 276 kPa (40 psi).

Fire Flow During the period of maximum day demand, the system pressure shall not be less than 140 kPa (20 psi) during a fire flow event.

Maximum Pressure

Maximum pressure at any point in the distribution system in unoccupied areas shall not exceed 689 kPa (100 psi). In accordance with the Ontario Building/Plumbing Code the maximum pressure should not exceed 552 kPa (80 psi) in occupied areas. Pressure reduction controls may be required for buildings when it is not possible/feasible to maintain the system pressure below 552 kPa.

#### 2.2.3 Fire Flow Rate

The Fire Underwriters Survey was used to determine the fire flow for the site. The calculations result in a fire flow of 18,000 L/min (300.0 L/s) based on wood frame building construction. A copy of the FUS calculation is included in **Appendix B**.

#### 2.2.4 Boundary Conditions

The City of Ottawa has provided a hydraulic boundary condition at the connection locations off Taggart Road. A copy of the boundary condition received June 11<sup>th</sup>, 2025 is included in **Appendix B** and is summarized as follows:

BOUNDARY CONDITIONS			
SCENARIO Connection 1 HGL (m) Connectio			
Existing Condition (Pre-SUC Pressure Zone Reconfiguration)			
Average Day	162.0	162.0	
Peak Hour	155.8	155.8	
Max Day + Fire Flow (183 l/s)	133.5	132.2	

#### 2.3 Proposed Water Plan

The site will be serviced by several connections to the existing 200 mm watermain on Taggart Road. One connection will be included to the East entrance of Building A at the intersection to the existing Kanata Commons commercial site. An existing connection has previously been installed in anticipation of the proposed residential development and will have a double service to meet water demands.

Building B will be serviced by extending a new 200mm diameter watermain in J way to accommodate future buildings. One service will be provided from J Way and include an additional connection within the shared parking garages in order to accommodate a double service connection to meet water demands.

There is one hydrant proposed on site, there are two existing hydrants on Campeau Drive adjacent to buildings A and B.

A hydraulic model has been created for the subject site using the InfoWater 12.4 program. The model includes the hydraulic boundary condition and the existing main on Taggart Road. The hydraulic model was run under basic day, maximum day with fire flows and under peak hour conditions, watermains are sized to provide sufficient pressure and to deliver the required fire flow, the watermains on site are 200mm in diameter in order to provide the required pressures. Results of the hydraulic analysis for the site is included in **Appendix B** and is summarized as follows:

SCENARIO	RESULTS
Basic Day (Max HGL) Pressure (kPa)	641.8-651.6 kPa
Maximum Day plus Fire Flow	
Design Fire Flow @ 140 kPa (20 psi) Residual Pressure	184.7 l/s
Peak Hour Pressure (kPa)	580.8-590.8 kPa

A comparison of the results and design criteria is summarized as follows:

Maximum Pressure Under Basic Day all nodes have pressure that exceeds 552 kPa (80

psi), therefore pressure reducing control is required for the buildings. There is no area where the pressure exceeds the

maximum level of 689 kPa (100 psi) in unoccupied areas.

Minimum Pressure The lowest minimum pressure during peak hour conditions is 580.8

kPa which exceeds the minimum 276 kPa (40 psi) requirement.

Fire Flow For the proposed hydrant at the southeast corner of the site, the

maximum design flow is 184.7 l/s which is below the 300 l/s rate from the FUS calculation. The design flow is expected to increase to over 300 l/s once the watermain is looped back to the Taggart Road watermain. The two hydrants on Campeau Drive are expected to have fire flows at 300 l/s as they are fed from an existing 600 mm watermain. Further analysis of the hydrants can be conducted to determine the actual design fire flow and the on site hydrant can be

looped back to the Taggart Road watermain.

#### 3 WASTEWATER

#### 3.1 Existing Conditions

The proposed site at 8201 Campeau Drive is located within the City of Ottawa where sanitary flows ultimately to the Ottawa Wastewater Treatment Plant at 395 Terry Fox Drive. There is an existing 200mm sanitary sewer bulkhead in Taggart Road at the property line that was previously installed in anticipation of the subject site, which will be utilized to service the dwelling units in Building A. It is proposed to extend the sanitary sewer further South to the intersection of Taggart Road and J Way, and continue East along J Way to the site limits. This proposed sanitary sewer extension along Taggart Road and J Way will provide a separate service connection directly to Building B and has been sized to accommodate future development capacity.

#### 3.2 Proposed Sewers

All on-site sewers have been designed to City of Ottawa and MECP design criteria which include but are not limited to the below listed criteria. The detailed sanitary sewer design sheet which is included in **Appendix C** illustrates the population densities and sewers which provide the necessary outlets. The design wastewater criteria for this analysis area:

#### 3.2.1 Design Flow:

Average Residential Flow - 280 I/cap/day

Peak Residential Factor - Modified Harmon Formula

Infiltration Allowance - 0.33 l/sec/Ha

Minimum Pipe Size - 200mm diameter

#### 3.2.2 Population Density:

1 Bedroom Apartments - 1.4 people per unit
2 Bedroom Apartments - 2.1 people per unit
3 Bedroom Apartments - 2.5 people per unit
Average Apartments - 1.8 people per unit

In order to calculate the projected average dwelling units and capacity requirements in future phases, a criteria of 1.8 people per unit was used for the total estimated unit count.

#### 4 SITE STORMWATER MANAGEMENT

#### 4.1 Existing Conditions

The subject site is currently undeveloped with no known stormwater management control measures. Stormwater currently flows overland to the South-West of the site.

An existing 300mm storm sewer stub, complete with temporary catch basin, is located within the site from the previous Kanata Commons commercial development. The stub will be utilized to service Building A. This stub was designed and installed in anticipation of this proposed development.

It is proposed that a new storm maintenance hole will be installed at the intersection of J Way and extended to the Eastern site limits in order to service Building B and future development separately. This proposed storm extension has been designed in anticipation of future overall development loads.

Catchment areas can be referenced in the Storm Drainage Area Plan in Appendix D.

#### 4.2 Design Criteria

The stormwater system for the subdivision was designed following the principles of dual drainage, making accommodations for both major and minor flow.

Some of the key criteria include the following:

Design Storm 1:2-year return (Ottawa)

Rational Method Sewer Sizing

Initial Time of Concentration 10 minutes

Runoff Coefficients

Softscape AreasHardscape AreasC = 0.20C = 0.90

• Pipe Velocities 0.80 m/s to 3.0 m/s

Minimum Pipe Size 250 mm diameter

#### 4.2.1 Infiltration

The Taggart-Loblaws Design Brief, dated June 2013, maintained the infiltration targets established within previous studies completed for the Kanata West Area, namely the Kanata West Master Servicing Study. The targets provided within the KWMSS design brief indicated that a range of 50-70 mm/year of runoff be infiltrated from the area. The infiltration target for this site is therefore to be considered as 70mm/year.

The design of the infiltration gallery is to be as per MECP requirements and the bottom of storage media will be minimum 1m above the high groundwater. The lowest bottom of media storage is 94.425m (94.575m header pipe elevation – 0.15m depth of clear stone base), or approximately 1.4m deep. Based on the geotechnical report the current groundwater table onsite is approximately 4.9-5.5m deep.

The proposed infiltration gallery has been sized to maximize infiltration potential for the site. The sizing was based on the amenity area catchment, and daily precipitation data (using wet year and dry year to establish overflow volume based on measured historical data). The maximum potential infiltration of the gallery was estimated using gallery size and precipitation norms for the area [920mm] and the overflow was then subtracted. Infiltration was assumed through the bottom surface area, with percolation rates established based on geotechnical investigation of the site determining that area generally ranges from silty sand to silty clay. The sizing of the gallery has been tailored for the proposed catchment area. The below table provides summary of the infiltration calculations for the site, further details of the infiltration galleries are provided within the servicing drawing. Also, detailed design calculations are provided within **Appendix D**. These calculations are discussed in-depth in Section 4.2.2 of this report.

Table 4.2.1 - Infiltration Gallery Calculations Summary on Annual Basis

GALLERY	TRIB	ANNUAL RUNOFF	AVERAGE	AVERAGE ANNUAL
	AREA	VOLUME (M3)	OVERFLOW	VOLUME INFILTRATED
	(M2)		VOLUME (M3)	(M3)
Amenity Area	2200	1214	30	1184

#### Where:

- Annual Runoff Volume is based on catchment area and 60% of the annual precipitation from the catchment available as runoff (920mm annual precipitation)
- Overflow Volume is based on building specific infiltration gallery sizing

The required infiltration will be provided by an infiltration gallery. The infiltration gallery will provide an estimated 1184m³ of infiltration on an annual basis, or 95.5mm/year for the 1.24ha site, above the required post-development rate of 70mm/year.

#### 4.2.2 Infiltration Detailed Calculations

The Appendix C calculations have been broken down step-by-step below. The volume of the infiltration gallery can be calculated as follows:

```
Volume = Width x Length x Depth x No. of Cells x Void Ratio
= 4m x 34.4m x 0.81m x 1 x 0.38
= 42.35m3
```

The depth has been considered to be the height of the underground storage system (0.66m) plus the clear stone base (0.15m). In order to establish a range of function for the proposed infiltration gallery, precipitation data for a wet year and a dry year was used. Daily precipitation data was provided by the Government of Canada Climate Normals Data for Station Ottawa CDA. The data that was provided includes rainfall amounts from April 1st through October 31st. This rainfall (in mm) was converted into an average rainfall intensity (mm/hr) by taking the amount of rain and dividing by 24 hours. The rainfall available to the infiltration gallery was then determined to be the average rainfall intensity multiplied by the captured area (2200m2) by the effective runoff percent (60%). To be conservative, the volume into the infiltration gallery was then capped at the volume of the gallery (42.35m3) and assumed any overage would outlet through the overflow pipe.

The amount of water that can infiltrate through the gallery from the bottom per day is as follows:

```
Infiltration = Surface Area of Infiltration Gallery x No. of Cells x Percolation Rate = (4m x 34.4m) x 1 x 0.3495m/day = 48.09 m3/day
```

Therefore the maximum infiltration that the gallery can provide in one day is 48.09m3. Since this value is above our conservative capped volume, the calculations will only show up to 48.09m3/day of infiltration.

These calculations were applied to each "wet year" and "dry year" day's rainfall quantities on the catchment area and the infiltration gallery's overflow was tracked to be 53 m3 and 0 m3, respectively.

The function of the infiltration gallery during a wet year can then be determined as follows:

```
Runoff Percent = Overflow Volume / Precipitation Volume
= 53 m3 / 1056 m3
= 5.00%
```

Therefore, during a wet year it can be expected that 5.00% of the water that enters the infiltration gallery will overflow without being infiltrated. The same calculations were done for a "dry year" and yielded a result of 0.00% (no overflow). On average, it can be expected that 2.50% of the water that enters the infiltration gallery will overflow and not be infiltrated.

Since the data only ranges from April to October, we cannot take the wet year Precipitation Volume of 1056 m3 and Overflow Volume of 53 m3 as the entire year's volumes. The overflow percentage must be applied to the Available Volume for an annual precipitation. The annual precipitation is 920mm as provided by the Government of Canada Climate Normals Data for Station Ottawa CDA. The Available Volume can be calculated as follows:

```
Available Volume = Area of Catchment x (Annual Precipitation x Effective Runoff) = 2200m2 x (920mm x 0.60 / 1000mm/m) = 1214.4 m3
```

It is then possible to determine the overflow volume for a full wet year or dry year, as shown below for a wet year:

Overflow Volume = Available Volume x Overflow Percent = 1214.4 m3 x 5.00% = 60.7 m3

The infiltration volume is then the difference between the Available Volume and the Overflow Volume, or  $1214.4m3 - 60.7m3 = 1153.7 \, \text{m}^3/\text{year}$ . Repeating the same calculations for a dry year yields an infiltration volume of  $1214.4 \, \text{m}^3/\text{year}$  (0% overflow). On average, the infiltration gallery is expected to infiltrate  $1184.1 \, \text{m}^3/\text{year}$ , or  $95.5 \, \text{mm}/\text{year}$  for the  $1.24 \, \text{ha}$  site, which is above the target post-development rate of  $70 \, \text{mm}/\text{year}$ .

There will be some years with high intensity precipitation (similar to the "wet year" used in these calculations) where the target will not be reached as the intensity will flow through the gallery before it has a chance to infiltrate, however the target has been met for an average year as required.

#### 4.3 Stormwater Management

This site is designed to have minimal impact on adjacent properties grading, drainage, access, circulation, and privacy. This will be achieved by means of Water Quantity Controls.

#### 4.3.1 Water Quantity Control

Per the McIntosh Perry Assessment of Adequacy of Public Services Report – 8201 Campeau Drive & 303 Didsbury Road (CCO-24-3115), the subject site will be limited to a maximum minor system release rate of 105.40 L/s during a 100-year storm. (see storm drainage plan in **Appendix D**). This release rate was calculated using the recommended 85.0 L/s/ha in the aforementioned report. This will be achieved through a combination of inlet control devices (ICD's), underground storage and surface storage where possible.

Surface flows in excess of the site's allowable release rate will be stored on site and gradually released into the minor system to respect the site's allowable release rate. The surface flows and ponding allocated to this site plan are shown in the grading plan located in **Appendix E**.

Along the Northern perimeter of the site, the opportunity to capture and store runoff is limited due to grading constraints and building geometry. These areas will discharge uncontrolled to Campeau Drive. These areas are located at the perimeter of the site where it is necessary to tie into public boulevards and adjacent properties or in areas where ponding stormwater is undesirable.

Based on the proposed site plan, the total uncontrolled area has been calculated to be 0.09 Ha. The runoff calculations for these uncontrolled areas have been calculated and provided in **Appendix D**. For the detailed storm drainage area plan for the site, refer to Drawing 500 in **Appendix D**.

Based on a 1:100-year event, the flow from the 0.09 Ha uncontrolled areas can be determined as:

```
Q_{uncontrolled} = 2.78 \times C_{100yr} \times i_{100yr} \times A \qquad \text{where:}
```

**C** = Average runoff coefficient (100-year C-value, max 1.00)

 $i_{100yr}$  = Intensity of 100-year storm event (mm/hr)

= 1735.688 x ( $T_c + 6.014$ )<sup>0.820</sup> = 178.56 mm/hr; where  $T_c$  = 10 minutes

**A** = Uncontrolled Area

Therefore, the uncontrolled release rates can be determined as:

```
Quncontrolled1 = 2.78 x C<sub>100yr</sub> x i<sub>100yr</sub> x A
= 2.78 x 0.85 x 178.56 x 0.09
= 37.97 L/s
```

The Maximum allowable release rate from the site can be determined by subtracting the Uncontrolled release rate from the minor system restricted flow rate.

```
Q_{max} = Q_{restricted} - Q_{uncontrolled1} - Q_{uncontrolled2} - Q_{uncontrolled3}
Q_{max} = 105.40 \text{ L/s} - 37.97 \text{ L/s}
Q_{max} = 67.43 \text{ L/s}
```

Therefore, the total restricted flow rate through the minor system will be the design flow rate of **67.43 L/s**. This will be achieved using Inlet Control Devices. A summary of the ICD's, their corresponding storage requirements, storage availability, and associated drainage areas have been provided below.

DRAINAGE AREA	ICD RESTRICTED FLOW (L/s)	100 YEAR STORAGE REQUIRED (m³)	2 YEAR STORAGE REQUIRED (m³)	STORAGE PROVIDED (m³)
ROOF A	4.00	96.33	28.02	106.88
ROOF B	4.00	96.33	28.02	106.88
ROOF C	2.00	15.34	3.85	22.50
CB108	6.00	87.15	21.88	94.95
CBMH104	10.00	82.42	19.41	94.42
CICB100B	20.00	26.11	3.86	36.52
CB99	20.00	50.94	9.53	51.43
TOTAL	66.00	454.62	114.55	513.57

Detailed stormwater management calculations for the 2-year event, 100-year event, and stress test (100-year plus 20%) event can be found in **Appendix D**.

There will be no surface ponding for the 2-year storm event per the rational method calculations, noting that a minimum concentration time of 10 min was considered for 2-year ponding. A 0.3m freeboard from downstream high points/maximum ponding elevations to first floor building openings is maintained in all scenarios including emergency overflow conditions.

Refer to geotechnical report for information regarding foundation drainage. Foundation drainage systems are to be independent and connected to the storm service downstream of any stormwater management control device.

#### 5 SEDIMENT AND EROSION CONTROL PLAN

#### 5.1 General

During construction, existing stream and conveyance systems can be exposed to significant sediment loadings. Although construction is only a temporary situation, it is proposed to introduce a number of mitigative construction techniques to reduce unnecessary construction sediment loadings. These will include:

- groundwater in trench will be pumped into a filter mechanism prior to release to the environment;
- bulkhead barriers will be installed at the nearest downstream manhole in each sewer which connects to an existing downstream sewer;
- seepage barriers will be constructed in any temporary drainage ditches; and
- silt sacks will remain on open surface structure such as manholes and catchbasins until these structures are commissioned and put into use.

#### 5.2 Trench Dewatering

During construction of municipal services, any trench dewatering using pumps will be discharged into a filter trap made up of geotextile filters and straw bales similar in design to the OPSD 219.240 Dewatering Trap. These will be constructed in a bowl shape with the fabric forming the bottom and the straw bales forming the sides. Any pumped groundwater will be filtered prior to release to the existing surface runoff. The contractor will inspect and maintain the filters as needed including sediment removal and disposal and material replacement as needed.

#### 5.3 Bulkhead Barriers

At the first manhole constructed immediately upstream of an existing sewer, a ½ diameter bulkhead will be constructed over the lower half of the outletting sewer. This bulkhead will trap any sediment carrying flows, thus preventing any construction –related contamination of existing sewers. The bulkheads will be inspected and maintained including periodic sediment removal as needed.

#### 5.4 Seepage Barriers

These barriers will consist of both the Light Duty Straw Bale Barrier as per OPSD 219.100 or the Light Duty Silt Fence Barrier as per OPSD 219.110 and will be installed in accordance with the sediment and erosion control drawing. The barriers are typically made of layers of straw bales or geotextile fabric staked in place. All seepage barriers will be inspected and maintained as needed.

#### 5.5 Surface Structure Filters

All catchbasins, and to a lesser degree manholes, convey surface water to sewers. However, until the surrounding surface has been completed these structures will be covered to prevent sediment from entering the minor storm sewer system. Until rear yards are sodded or until streets are asphalted and curbed, all catchbasins and manholes will be equipped with geotextile filter socks. These will stay in place and be maintained during construction and build until it is appropriate to remove them.

#### 6 CONCLUSIONS & RECOMMENDATIONS

#### 6.1 Conclusions

This report and the accompanying working drawings clearly indicate that the proposed development meets the requirements of the stakeholder regulators, including the City of Ottawa. The proposed development is also in general conformance with the recommendations made by the Pre-consultation Meeting Notes.

There is a reliable water supply available adjacent to the proposed development; a wastewater outlet is available adjacent to the site and local storm sewers have been installed adjacent to the site.

#### 6.2 Recommendations

It is recommended that the regulators review this submission with an aim of providing the requisite approvals to permit the owners to proceed to the construction stage of the subject site.

Report prepared by:

**ARCADIS** 



Samantha E. Labadie, P. Eng Civil Engineer Matt Anderson Petitpas Engineering Technologist

# **Appendix A**



ISSUES				
No.	DESCRIPTION	DATE		
01	ISSUED FOR SPC	2025-XX-XX		

	30259723		
DRAWN BY:	CHECKED BY:		
PROJECT MGR:	APPROVED BY:		
SHEET TITLE	SCALE		
	1.400		



File No.: PC2025-0048

March 21, 2025

Scott Alain
Fotenn Planning + Design
Via email: alain@fotenn.com

**Subject:** Pre-Consultation: Meeting Feedback

Proposed Application – 8201 Campeau Drive

Please find below information regarding next steps as well as consolidated comments from the above-noted pre-consultation meeting held on March 11, 2025.

#### **Pre-Consultation Preliminary Assessment**

. —		• 🗖		
1	9	3 IXI	1 1	5   1
	<b>∠</b> ⊔	<b>O</b> 🖂	<b>, ,</b> , , , , , , , , , , , , , , , , ,	J 🗆

One (1) indicates that considerable major revisions are required while five (5) suggests that the proposal appears to meet the City's key land use policies and guidelines. This assessment is purely advisory and does not consider technical aspects of the proposal or in any way guarantee application approval.

#### Next Steps

- 1. A review of the proposal and materials submitted for the above-noted preconsultation has been undertaken. Should you choose, proceed to complete a Phase 2 / Phase 3 Pre-consultation Application Form. Please submit this information together with the necessary studies and/or plans to planningcirculations@ottawa.ca.
- 2. In your subsequent pre-consultation submission, please ensure that all comments or issues detailed herein are addressed. A detailed cover letter stating how each issue has been addressed is requested with the submission materials. Please coordinate the numbering of your responses within the cover letter with the comment number(s) herein.
- Please note, if your development proposal changes significantly in scope, design, or density it is recommended that a subsequent pre-consultation application be submitted.
- 4. If the Urban Design Review Panel (UDRP) Report is listed as a required submission material in the Study and Plan Identification List, the applicant must visit the UDRP prior to formally submitting the planning application. The UDRP report is required for the application to be considered complete.

#### **Supporting Information and Material Requirements**



- 1. The attached **Study and Plan Identification List** outlines the information and material that has been identified, during this phase of pre-consultation, as either required (R) or advised (A) as part of a future complete application submission.
  - a. The required plans and studies must meet the City's Terms of Reference (ToR) and/or Guidelines, as available on Ottawa.ca. These ToR and Guidelines outline the specific requirements that must be met for each plan or study to be deemed adequate.

#### **Consultation with Technical Agencies**

1. You are encouraged to consult with technical agencies early in the development process and throughout the development of your project concept. A list of technical agencies and their contact information is enclosed.

#### **Planning**

#### Comments:

- 2. **OP:** Schedule B5 -Suburban West Transect, Neighbourhood (with Overlay),
- 3. **Zoning:** MC11[74] H(34)
- 4. **Future Zoning:** Present draft Zoning By-law has it listed as a Hub(H)[74] H(34) and Minor Corridor(CM) [74] H(34).
- 5. **TOD:** Didsbury LRT Station is part of the Ultimate Transit Network (Sch.C2); However, it is not a funded station.
  - From a policy perspective, it is in proximity to a future LRT Station (which is still supportive of a mix of uses in higher densities); BUT, the future context is not intended as a Hub function.
- 6. Section 37 requirements / Community Benefits Charge
  - a. The former Section 37 regime has been replaced with a "Community Benefits Charge", By-law No. 2022-307, of 4% of the land value. This charge will be required for ALL buildings that are 5 or more storeys and 10 or more units and will be required at the time of building permit unless the development is subject to an existing registered Section 37 agreement. Questions regarding this change can be directed to Ranbir.Singh@ottawa.ca.
- 7. Please observe the <u>Urban Desing Guidelines for High-rise Buildings</u> in any future Site Plan Application in determining appropriate lotting.



- 8. Landscape requirements
  - a. A landscape plan is required prior to early servicing.
- 9. The comments provided in the 2023 preconsult are largely still applicable.
  - a. Size of the blocks are still of concern for us, for scale the building façade along Campeau is a similar length as the strip mall. I think that the development could benefit from further refining both the block and building sizes.
- 10. Will need confirmation of deeded access to this private ROW on the west.
- 11. When assessing this application, I'll push for them to treat this as a corner lot line
- 12. E-W private ROW will need to be included in the Phase 1 lands and detailed further.
- 13. We would like to get further detail on what is targeted for the interior courtyard. Consider:
  - The shadow impacts on this space there may be many reasons to have Building A split up into two buildings.
  - The 'back of house' condition that may be present in areas adjacent to amenity areas.
  - The issues that the surface parking lot may have for perspective commercial tenants which will have difficulty managing two entrances.

#### **Urban Design**

#### Comments:

- Urban Design Brief required please refer to the attached Terms of Reference.
- Staff appreciate that the Applicant is hoping to move ahead with the Phase 1
  development leveraging as-of-right zoning permissions, however, it would be
  best if the plans were viewed in the context of a larger master plan.
- As supported by Parks, the park block should be larger and more regularly shaped with adequate frontage on public roads. Microclimate conditions (future) should inform the position of the park.
- Public roads a critical part of the development of this very large site. Staff
  appreciate the ongoing discussions being had with the adjacent neighbour as
  well as the addition of a public road link through the center of the property.



- Staff appreciate that the proposed 6 storey form will relate back to the scale of development anticipated along the Minor Corridor.
- Staff also appreciate that the Applicant is thinking about ground floor animation in the form of retail along Campeau and grade-related units and amenity along the remainder of the streets.
- Ground floor units facing out onto a private walkway and landscaping should also be provided along-side the proposed park for further animation.
- Staff also appreciate that the Applicant is looking at a robust amenity strategy to support the future residents of the Phase 1 development.
- Staff feel that that the development block as proposed cuts off the balance of the future development from Campeau and that the development would benefit from a mid-block connection into the site.
- Built form should be reorganized to support a semi-public connection to Campeau.
- Short term parking areas should be screened from the public realm.
- If connection between the buildings is important a second or third level bridge connection can be supported.
- Staff look forward to reviewing future public realm treatments for Campeau as well as new public and private roads anticipated through the property.
- High level concept (draft) included below to stimulate workshop discussions which we anticipate will occur in the coming weeks:





14. Feel free to contact Nader Kadri, Urban Designer, for follow-up questions.

#### **Engineering**

- 15. Existing public infrastructure:
  - a. Campeau
    - i. 600mm backbone watermain (new connections not permitted)
    - ii. 675mm concrete sanitary
    - iii. 525mm concrete storm
  - b. Didsbury (30 cm reserve must be lifted for frontage on Didsbury)
    - i. 203mm PVC watermain
    - ii. 450mm concrete sanitary
    - iii. 300mm pvc storm
  - c. Private service stubs may be available on servicing block between 8201 Campeau Drive and 8231 Campeau Drive. Legal access to the easement will be required.



16. The preferred connection location for new service laterals will be via the private roadway access shared between 8231 Campeau Drive and 8201 Campeau Drive. Legal access will be required. Alternatively, if a private or public roadway is proposed to transect the site, servicing via the new roadway alignment would be a preferred option.

#### 17. Water

- a. Boundary conditions: Civil consultant must request boundary conditions from the City's assigned Project Manager prior to first submission.
  - Water boundary condition requests must include the location of the service(s) and the expected loads required by the proposed developments. Please provide all the following information:
    - Location of service(s)
    - Type of development and the amount of fire flow required (as per FUS, 2020)

•	Average daily demand: L/s	
•	Maximum daily demand: L/s	3
•	Maximum hourly daily demand:	L/s

- ii. Fire protection (Fire demand, Hydrant Locations)
- b. A District Metering Area Chamber (DMA) is required for services 150mm or greater in diameter.
- c. Service areas with a basic demand greater than 50 m3/day shall be connected with a minimum of two water services, separated by an isolation valve, to avoid the creation of a vulnerable service area. If a private watermain network is proposed within the subject site, the private watermain will require two connections to the public watermain network, separated by an isolation valve. Watermain connections to the 600mm backbone watermain on Campeau Drive will not be permitted.
- d. Existing water services that are not to be used must be decommissioned as per City Standards.
- 18. The sanitary sewer release rate, for the subject site, is to be in accordance with the following reports:
  - a. Kanata West Master Servicing Study (KWMSS), Stantec Consulting Ltd and IBI. Group, June 2006
  - Taggart Loblaws Subdivision, Kanata West, Servicing Report, Stantec Consulting Ltd., June 2013



#### Stormwater Management

- 19. The storm sewer release rate and stormwater management criteria, for the subject site, is to be in accordance with the following reports:
  - a. Kanata West Master Servicing Study (KWMSS), Stantec Consulting Ltd and IBI. Group, June 2006
  - Taggart Loblaws Subdivision, Kanata West, Servicing Report, Stantec Consulting Ltd., June 2013
  - c. Taggart-Loblaws Subdivision Stormwater Management Facility Design Brief, Stantec Consulting Ltd, June 2013
- 20. Quality Control: SWMP 3 is designed to treat 80% TSS from the minor system. Additional stormwater quality treatment is not required.
- 21. Water Balance: The subject site must provide infiltration measures in order to meet the 70mm/yr infiltration rate indicated in the KWMSS, and further the Taggart Loblaws Subdivision Stormwater Management Facility Design Brief (June 2013). Detailed calculations will be required to demonstrate that this requirement can be achieved.
- 22. When both underground and above ground storage is utilized, the release rate from the system will significantly differ than when solely one level storage is being used (i.e. greater range of head vs smaller change of head during storm event). If both levels of storage are to be accounted for then there are two options for SWM calculations: 1) use a dynamic computer model or 2) use an assumed average flow rate of half (50%) of the controlled peak flow rate of the area(s) utilizing two levels of storage.

#### Geotechnical

- 23. The site is subject to water balance requirements through infiltration. All soil assumptions made in the servicing report should be supported by the geotechnical report.
- 24. If a road cut is proposed on Campeau, the geotechnical report should provide construction recommendations for work around the critical infrastructure within the ROW.

#### **Environmental Compliance Application**

- 25. The development will be exempt from an ECA assuming it continues to meet the O.Reg 525/98 exemption criteria.
  - O.Reg 525/98 ECA exemption criteria:



- (a) is designed to service one lot or parcel of land;
- (b) discharges into a storm sewer that is not a combined sewer;
- (c) does not service industrial land or a structure located on industrial land; and
- (d) is not located on industrial land.

Feel free to contact Julie Candow, Project Manager, for follow-up questions.

#### **Noise**

#### Comments:

- 26. Noise Impact Studies required for the following:
  - a. Road, as the subject development is located within 100m proximity of Campeau Road, and within 500m of Highway 417.
  - b. Rail, site is within 100m of the future LRT ROW.
  - c. Stationary, due to the proximity to neighboring exposed mechanical equipment and/or if there will be any exposed mechanical equipment due to the proximity to neighboring noise sensitive land uses.
  - d. Vibration Assessment is required as the subject development is located within 75m from the LRT ROW.
  - e. Feel free to contact Rochelle Fortier-Lesage, Transportation Project Manager, for follow-up questions.

#### **Transportation**

#### Comments:

- 27. Follow Transportation Impact Assessment Guidelines:
  - a. A Transportation Impact Assessment is required. Please submit the Scoping report to <u>rochelle.fortier@ottawa.ca</u> at your earliest convenience. The applicant is responsible to submit the Scoping Report and must allow for a 14 day circulation period and sign-off prior to proceeding to the Strategy Report.
  - b. The Strategy Report must be submitted for review at the latest with the formal submission package. The applicant is still encouraged to submit the Strategy Report to the TMP before submission and allow for a 14 day circulation period.



- c. If an RMA is required to support the proposed development, the functional plan and/or RMA plans must be submitted with the formal submission to deem complete. Request base mapping asap if RMA is required. Contact Engineering Services.
- 28. Ensure that the development proposal complies with the Right-of-Way protection requirements See <u>Schedule C16 of the Official Plan</u>.
  - a. Corner triangles on the final plan will be required (measure on the property line/ROW protected line; no structure above or below this triangle). The City requires the following corner triangles at these locations:
    - i. Arterial/Local, or Collector/Local: a 3 metre x 9 metre triangle, with the longer portion on the higher road segment
    - ii. Local/Local, or Public Lane/Local: a 3 metre x 3 metre triangle
  - b. ROW must be unincumbered and conveyed at no cost to the City. Note that conveyance of the ROW will be required prior to registration of the SP agreement. Additional information on the conveyance process can be provided upon request.
  - c. Any requests for exceptions to ROW protection requirements <u>must</u> be discussed with Transportation Planning and concurrence provided by Transportation Planning management.
- 29. Site is partially within MTO permit control area which requires an MTO Building and Land Use Permit. Coordination with MTO staff is required to determine their TIS requirements.
- 30. Corner clearances should follow minimum distances set out within TAC Figure 8.8.2.
- 31. Please note that there is a new transit pad along the Campeau Drive frontage.
- 32.TMP includes:
  - a. LRT from Moodie Drive to Kanata (Ultimate Network Concept), with new station at Didsbury
  - b. The City is proceeding with the extension of Earl Grey Drive west to Didsbury Road, with the construction of a segment of road approximately 140 metres in length. The extension will pass under Terry Fox Drive and requires the construction of a new bridge structure as well as an upgrade to the Terry Fox Drive and Didsbury Road intersection in order to meet the requirements of the City's protected intersection guidelines.



33. AODA legislation applies for all areas accessible to the public. Please consider using the City's <u>Accessibility Design Standards</u>, which provide a summary of AODA requirements.

#### 34. On site plan:

- a. Ensure site accesses meet the <u>City's Private Approach Bylaw</u> and all driveways/aisles meet the requirements outlined in <u>Section 107 of the Zoning By-law</u>.
- b. Show all details of the roads abutting the site; include such items as pavement markings, accesses and/or sidewalks.
- c. Turning movement diagrams required for all accesses showing the largest vehicle to access/egress the site.
- d. Turning movement diagrams required for internal movements (loading areas, garbage).
- e. Show all curb radii measurements; ensure that all curb radii are reduced as much as possible and fall within TAC guidelines (Figure 8.5.1).
- f. Show dimensions for site elements (i.e. lane/aisle widths, access width and throat length, parking stalls, sidewalks, pedestrian pathways, etc.)
- g. Sidewalks are to be continuous across accesses as per City Specification 7.1.
- h. Show proposed and required parking rates.
- i. Show slope of garage ramps on site plan. Note that underground ramps should be limited to a 12% grade and must contain a subsurface melting device when exceeding 6%. Ramp grades greater than 15% can be psychological barriers to some drivers.
- j. Parking stalls at the end of dead-end parking aisles require adequate turning around space
- k. Grey out any area that will not be impacted by this application.

Feel free to contact Rochelle Fortier-Lesage, Transportation Project Manager, for follow-up questions.

#### **Environment**

Comments:



- 35. There are no triggers for an Environmental Impact Study.
- 36. Bird-Safe Design Guidelines Please review and incorporate bird safe design elements. Some of the risk factors include glass and related design traps such as corner glass and fly-through conditions, ventilation grates and open pipes, landscaping, light pollution. More guidance and solutions are available in the guidelines which can be found here:

  <a href="https://documents.ottawa.ca/sites/documents/files/birdsafedesign\_guidelines\_en.pdf">https://documents.ottawa.ca/sites/documents/files/birdsafedesign\_guidelines\_en.pdf</a>
- 37. Please consider if there are features that can be added reduce the urban heat island effect (see OP 10.3.3). For example, this impact can be reduced by adding large canopy trees, green roofs or vegetation walls, or incorporating building with low heat absorbing materials.

38.

Feel free to contact Matthew Hayley, Environmental Planner, for follow-up questions.

#### **Forestry**

#### Comments:

- 39. The park should be situated to include retention of the existing conifer stand, which is a remnant from the former farm and laneway that were on this parcel.
- 40. The design including the setbacks from underground parking should allow for retention of as many of the newly planted trees along Campeau and Didsbury as possible, and for replacement of any which must be removed.
- 41. A TCR and Landscape Plan are required including all elements within the associated guidelines and Terms of Reference.
- 42. The LP must include trees on all frontages and for screening between the park and building B, toward the Official Plan goal of 40% canopy cover.

Feel free to contact Nancy Young, Forester, for follow-up questions.

#### **Parkland**

43. Parkland dedication is required in accordance with the Parkland Dedication Bylaw (2022-280) and Planning Act. The applicable parkland dedication rate for residential development is 1 ha per 600 units, to a maximum of 15% of the site area, per application. The parcel size is 6.16 ha based on GeoOttawa. If looked at comprehensively, the maximum parkland dedication that can be taken for the residential use of the site is 0.924 ha.



- 44. Pervious conversations with the applicant included discussion of a parkland dedication based on a Transit Oriented Development Zone. Staff advise that the site does not currently benefit from such a TOD zone, and so policies in Section 5 of the Parkland Dedication By-law are not applicable at this time.
- 45. Based on the TIA submitted with the pre-con application package, 350 units are considered for phase 1, and so the site plan application generates a parkland dedication requirement of approximately 0.583 ha. As more details of the mixed-use nature of the development are provided, this calculation may be slightly refined.
- 46. Parks and Facilities Planning encourages that the applicant provide a park block through the phase 1 site plan application that will serve the entire site, i.e. the 0.924 ha park block size. This should provide greater clarity in planning in planning the remainder of the community.
- 47. A park block 0.924 ha in size is classified as a "parkette" within the hierarchy of parks in the City of Ottawa. Parkettes are small parks, rectangular in shape, that are located within walking distance of residents, they provide a central greenspace and social gathering space. Parkettes are to be located on local streets with a minimum of 50% public road frontage. Staff do not think it is appropriate to locate a parkette abutting Campeau Drive. PFP suggest that the parkette would be better located with greater frontage abutting Didsbury Road and the new public road to the south. PFP supports the park location shown in the sketch provided within the urban design comments.
- 48. The ultimate concept of the full site proposes residential towers to the south of park block resulting in possible concerns for wind and shade. Ensuring the park has 50% or more road frontage on local roads may help mitigate the effects on park users of feeling squeezed between towers.
- 49. Prior to site plan approval, the Owner is required to submit a Facility Fit Plan for the 0.583 ha park block, and/or the 0.924 ha park block in accordance with the submission requirements for a Facility Fit Plan (<a href="Park Development Manual">Park Development Manual</a> page 60). The Facility Fit plan is a planning exercise to ensure the size and configuration of the park block is acceptable. It identifies any existing vegetation or special feature in the park which may be preserved.
- 50. Forestry has noted that there is a line of mature conifer trees located near to the proposed park site perpendicular to Didsbury. The ideal park location will allow for the retention of those trees and inclusion of them in the Facility Fit Plan.
- 51. As a starting point, I suggest that the appropriate amenities for include in the Fit Plan for this parkette are a junior and senior play structures, swings, splash pad, shaded seating and a basketball court, along with open space and plantings. This Fit Plan must include a cost estimate corresponding with the park design



- and construction budget. Park amenities and design will be further refined through the park detail design process which includes public consultation.
- 52. Staff are available to discuss the developer-built park process. The applicant is encouraged to ask if they are unfamiliar or have questions about the process expectations. The applicant should make clear their intentions to provide and/or construct the park block in one or more phases. The city encourages the developer to construct the park block in conjunction with Phase 1 to ensure it is made available to residents at the soonest opportunity.
- 53. Parks staff will also be looking at details of the façade of Building B or any proposed building abutting the park to ensure it is compatible.

Feel free to contact Anissa.mcalpine@ottawa.ca, Parks Planner, for follow-up questions.

#### **Other**

- 54. The High Performance Development Standard (HPDS) is a collection of voluntary and required standards that raise the performance of new building projects to achieve sustainable and resilient design and will be applicable to Site Plan Control and Plan of Subdivision applications.
  - a. The HPDS was passed by Council on April 13, 2022, but is not in effect at this time, as Council has referred the 2023 HPDS Update Report back to staff with the direction to bring forward an updated report to Committee at a later date. The timing of an updated report to Committee is unknown at this time, and updates will be shared when they are available.
  - b. Please refer to the HPDS information at ottawa.ca/HPDS for more information.
- 55. Under the Affordable Housing Community Improvement Plan, a Tax Increment Equivalent Grant (TIEG) program was created to incentivize the development of affordable rental units. It provides a yearly fixed grant for 20 years. The grant helps offset the revenue loss housing providers experience when incorporating affordable units in their developments.

To be eligible for the TIEG program you must meet the following criteria:

- a. the greater of five units OR 15 per cent of the total number of units within the development must be made affordable
- b. provide a minimum of 15 per cent of each unit type in the development as affordable
- c. enter into an agreement with the city to ensure the units maintain affordable for a minimum period of 20 years at or below the city-wide



average market rent for the entire housing stock based on building form and unit type, as defined by the Canada Mortgage and Housing Corporation

- d. must apply after a formal Site Plan Control submission, or Building Permit submission for projects not requiring Site Plan Control, and prior to Occupancy Permit issuance
- a. Please refer to the TIEG information at <u>Affordable housing community</u> <u>improvement plan / Plan d'améliorations communautaires pour le</u> <u>logement abordable</u> for more details or contact the TIEG coordinator via email at affordablehousingcip @ottawa.ca.

#### **Submission Requirements and Fees**

- 1. Complex Site Plan Control & Plan of Subdivision Applications
  - a. Additional information regarding fees related to planning applications can be found <a href="here">here</a>.
- 2. The attached **Study and Plan Identification List** outlines the information and material that has been identified as either required (R) or advised (A) as part of a future complete application submission.
  - a. The required plans and studies must meet the City's Terms of Reference (ToR) and/or Guidelines, as available on <u>Ottawa.ca</u>. These ToR and Guidelines outline the specific requirements that must be met for each plan or study to be deemed adequate.
- 3. <u>All</u> of the above comments or issues should be addressed to ensure the effectiveness of the application submission review.

Should there be any questions, please do not hesitate to contact myself or the contact identified for the above areas / disciplines.

Yours Truly, John Bernier, MCIP RPP



#### APPLICANT'S STUDY AND PLAN IDENTIFICATION LIST

#### Proposed Site Plan and Subdivision Applications – 8201 Campeau Drive – PC2025-0048

Legend: **R** = Required, the study or plan is required with application submission

A = Advised, the study or plan is advised to evaluate the application or satisfy a condition of approval/draft approval

1 - OPA, 2 - ZBA, 3 - Plan of Subdivision, 4 - Plan of Condominium, 5 - SPC

Core studies required for certain applications all the time (Remaining studies are site specific)

For information and guidance on preparing required studies and plans refer <a href="here:">here:</a>

ENGINEERING									
R A		Study/ Dlan Name	Description	When Required					Applicable Study Components
Κ	A	Study/ Plan Name	Description	1	2	3	4	5	& Other Comments
		Assessment (Phase 1	Ensures development only takes place on sites where the environmental conditions are suitable for the proposed use	$\boxtimes$	$\boxtimes$	$\boxtimes$	$\boxtimes$	$\boxtimes$	Record of Site Condition
				Study Tr All cases	igger Deta	ails:	Yes □ No □		
			Geotechnical design	$\boxtimes$	$\boxtimes$	$\boxtimes$	$\boxtimes$	$\boxtimes$	
		2. Geotechnical Study	requirements for the subsurface conditions	Study Tr All cases	igger Deta	ails:			
		3. Grading and	Grading relationships between connecting (or abutting)			$\boxtimes$		$\boxtimes$	
		Drainage Plan	properties and surface runoff control	Study Tr All cases	igger Deta	ails:			
		Terrain Analysis geology, terrain, affected	A scientific study or evaluation			$\boxtimes$	$\boxtimes$	$\boxtimes$	Reasonable Use Study
			When de	igger Deta eveloping o evelopmen private sei	on private at is in clos	Yes □ No □  Groundwater Impact Study  Yes □ No □			
$\boxtimes$			Potential impacts of noise on a development	$\boxtimes$	$\boxtimes$	$\boxtimes$	$\boxtimes$	$\boxtimes$	Vibration Chief
				Study Trigger Details: See Terms of Reference for full details.					Vibration Study Yes ⊠ No □

				$\boxtimes$	$\boxtimes$	$\boxtimes$		
$\boxtimes$	6. Rail Proximity Study	Development on land adjacent to all Protected Transportation Corridors and facilities shown on Schedule C2 of the Official Plan, to follow rail safety and risk mitigation best practices	Study Trigger Details: Within the Development Zone of Influence for existing and future rapid transit stations and corridors, as shown on Annex 2 of the OP OR on land adjacent to all Protected Transportation Corridors and facilities shown on Schedule C2 of the Official Plan					Rail Safety Report Yes □ No □  O-Train Network Proximity Study Yes □ No □
								Fluvial Geomorphological Report Yes □ No □
								Assessment of Adequacy of Public Services Yes □ No □
		Provides servicing details based on proposed scale of development with an engineering						Servicing Options Report Yes □ No □
	7. Site Servicing Study	overview taking into consideration surrounding developments and connections.	Study Trigger Details: All cases				Erosion and Sediment Control Plan / Brief Yes ⊠ No □	
					Hydraulic Water Main Analys Yes ⊠ No □	Hydraulic Water Main Analysis Yes ⊠ No □		
								Stormwater Management Report and Detailed Design Brief Yes ⊠ No □
		Accomment of along atability and		$\boxtimes$		$\boxtimes$	$\boxtimes$	
	8. Slope Stability Study	Assessment of slope stability and measures to provide safe set-back.	Study Trigger Details: Where the potential for Hazard Lands exists on a site.					Retrogressive Landslide Analysis Yes □ No □
				$\boxtimes$	$\boxtimes$	$\boxtimes$	$\boxtimes$	
	9. Transportation Impact Assessment	Identify on and off-site measures to align a development with City transportation objectives.	If the der or more;	rigger Deta velopment or if the d Trigger; o	generate evelopme	nt is İocat	ed in a	Roadway Modification Functional Design Yes   No

				$\boxtimes$	$\boxtimes$	$\boxtimes$	$\boxtimes$
] [	10. Water Budget Assessment	Identify impact of land use changes on the hydrologic cycle and post-development mitigation targets.	May be applicati and / or sensitive required assessn	rigger Deta required for lons for site proximity to a areas. Do to integra ments into a ment plans	or site plar es with pri to hydroge traft plans te water b supporting	vate servi eologically of subdivi udget g stormwa	ision are
] [	11. Wellhead Protection Study	Delineate a Wellhead Protection Area (WHPA) and characterize vulnerability for new communal residential drinking water well systems, in accordance with Technical Rules under Clean Water Act.	Study Trigger Details: Required for all new communal residential drinking water well systems; including new municipal wells, new private communal wells (small water works) that require a Municipal Responsibility Agreement (MRA), expansions or increased water takings from an existing municipal well or existing private communal wells.				

			P	LANNIN	IG				
R	Α	Study/Plan Name	Description	Applicable Study Components					
IX.		Study/Flail Name	Description	1	2	3	4	5	& Other Comments
		12. Agrology and Soil Capability Study	Confirm or recommend alterations to mapping of agricultural lands in the City.	For the edidentification is demonstrated in the edge of the edge o	rigger Deta expansion ation of a ra a comprel nstrated the irements f	of a settle new settle hensive re nat the lan	ment area eview; or v d does no		
				×	$\boxtimes$	$\boxtimes$	$\boxtimes$		
		13. Archaeological Assessment	Discover any archaeological resources on site, evaluate cultural heritage value and conservation strategies	When the archaeo archaeo Archaeo Study in outside of any ar	rigger Deta e land has logical site logical Re dicates ar of the histe rchaeolog	s either: a e; or the p es; or whe esource Po chaeologi oric core; ical resou	otential to re the Cit otential M cal potent or upon d rce during	y's apping tial, iscovery	
				$\boxtimes$	$\boxtimes$				
$\boxtimes$		14. Building Elevations	Visual of proposed development to understand facing of building including direction of sunlight, height, doors, and windows.	Study Trigger Details: Site Plan: for residential buildings with 25 or more residential units; or for residential buildings with less than 25 residential units, if the units are within the Urban area or the High-performance Development Standard threshold in the rural area.  Official Plan or Zoning By-law: if staff deem it necessary to determine compliance with OP policies, the Zoning By-law or City of Ottawa Urban Design Guidelines.					

				$\boxtimes$	$\boxtimes$		$\boxtimes$	
	15. Heritage Impact Assessment	Determine impacts of proposed development on cultural heritage resources.	Where of the Onta adjacen 30 metro for any of Canal U	rigger Deta developme ario Herita t to, acros es of a pro developme NESCO V ped buffer	ent or an a ge Act is p s the stree otected he ent adjace Vorld Heri	proposed et from or ritage proent to the f	Conservation Plan Yes □ No □	
				$\boxtimes$	$\boxtimes$	$\boxtimes$	$\boxtimes$	
	16. Heritage Act Acknowledgement Report	A submission requirement to demonstrate that the <i>Ontario Heritage Act</i> requirements have been satisfied, to ensure that multiple applications are considered currently.	Where t Heritage submit a (designa Heritage to demo	rigger Deta he subject Register a Heritage ated herita Register lish or ren ted proper	t property and the a Permit Ap ge proper or provide nove a bu	pplicant noplication ty listed of le notice colling (nor	nust In the of intent	Heritage Permit Application Yes □ No □  Notice of Intent to Demolish Yes □ No □
		Mineral aggregate extraction activities; and to protect	$\boxtimes$	$\boxtimes$	$\boxtimes$	$\boxtimes$	$\boxtimes$	
	17. Impact Assessment Study – Mineral Aggregate	known high quality mineral aggregate resources from development and activities that would preclude or hinder their existence (ability to be extracted) or expansion.	New De within the metres of	rigger Det velopmen e Bedrock of lands w ee Area Ov	t within 50 c Overlay ithin the S	, or within	300	
		To identify or confirm known mineral deposits or petroleum		$\boxtimes$	$\boxtimes$			
	18. Impact Assessment Study – Mining Hazards	resources and significant areas of mineral potential.  To protect mineral and petroleum resources from development and activities which would preclude or hinder the establishment of new operations or access to the resources.		rigger Det pplication ns.		nity to mir	ning	

		To identify or confirm known		$\boxtimes$	$\boxtimes$	$\boxtimes$	$\boxtimes$	
	19. Impact Assessment Study – Waste Disposal Sites / Former Landfill Sites	proximity of existing or former waste disposal sites.  To ensure issues of public health, public safety and environmental impact are addressed.  Study Trigger Details: For the establishment of any new Solid Waste Disposal Site or for a footprint expansion of an operating Solid Waste Disposal Site; or development within three kilometers of an operating or non-operating Waste Disposal Site.						
			$\boxtimes$	$\boxtimes$	$\boxtimes$	$\boxtimes$	$\boxtimes$	
	20. Landscape Plan	A plan to demonstrate how the canopy cover, urban design, health, and climate change objectives of Official Plan will be met through tree planting and other site design elements.	Site Plai Condom it is dem compon- review of A high-le be requi	ninium: alvalonstrated ent of a proof the applicated concerned to supplicated to supplicate to supplicate to supplicate the supplicated to supplicated to supplicate the supplicated to supplicated the supplicated to supplicate the supplicated to supplicated the supplicated to supplicate the supplicated to supplicated the supplicated to supplicate the supplicated the supplicate	Subdivision  vays requing that the languities the languistic state of the languist state	red, exce andscape of relevan dscape P ng By-law	pt where t to the lan may and	
				$\boxtimes$				
	21. Mature Neighbourhood Streetscape Character Analysis	Neighbourhoods a Streetscape Character Analysis is required to determine the applicable zoning requirements.	Streetscape Character Analysis is required to etermine the applicable  Zoning By-law amendment application in areas covered by the Mature Neighbourhoods zoning overlay for applications of residential					
		Provincial land use planning	$\boxtimes$	$\boxtimes$	$\boxtimes$	$\boxtimes$	$\boxtimes$	
	22. Minimum Distance Separation	tool that determines setback distances between livestock barns, manure storages or anaerobic digesters and surrounding land uses, with the objective of minimizing land use conflicts and nuisance complaints related to odour.	setback vestock ges or and s, with nizing d  Study Trigger Details: Applications in the Rural Area, outside of a village.					

		A tool to assess the			$\boxtimes$	$\boxtimes$		
	23. Parking Plan	sufficiency of on-street parking in plans of subdivision.		rigger Deta or revised reets.		subdivisio	n with	
	24. Plan of Survey	A Plan of Survey depicts legal boundaries and is a specialized map of a parcel of land and it delineates boundary locations, building locations, physical features and other items of spatial importance.						
				$\boxtimes$	$\boxtimes$			
$\boxtimes$	25. Plan of Subdivision	Proposed subdivision layout to be used for application approval	Study Trigger Details: Always required with the submission of plan of subdivision application.  Only required with a Zoning By-law Amendment application, where such ZBLA is in response to enable a subdivision.					
		Proposed condominium				$\boxtimes$		
	26. Plan of Condominium	layout to be used for application approval	yout to be used for Study Trigger Details:					
		Provides the planning	$\boxtimes$	$\boxtimes$	$\boxtimes$			
	27. Planning Rationale	justification in support of the Planning Act application and to assist staff and the public in the review of the proposal.	Study Trigger Details: For all Official Plan amendment, Zoning By- law amendment, or plan of subdivision applications.					Integrated Environmental Review Summary Yes □ No □
		A checklist that shows a			$\boxtimes$		$\boxtimes$	
$\boxtimes$	28. Preliminary Construction Management Plan	development proposal's anticipated impacts to all modes of transportation and all elements in the right of way during construction.	on and ht of Study Trigger Details:  Study Trigger Details: For all Site Plan and plan of subdivision			on		


			$\boxtimes$	$\boxtimes$	$\boxtimes$	$\boxtimes$	$\boxtimes$	
	29. Public Consultation Strategy	Proposal to reach and collect public input as part of development application.	Official I Amenda required Condom Site Plai lead in c	rigger Detail Plan Amerinent and St.  ninium: Van: At the deconsultational Support	ndment, Z Subdivisio cant Land iscretion on with the	n: Always only of the City Business		
				$\boxtimes$				
	30. Shadow Analysis	A visual model of how the proposed development will cast its shadow.	When the massing commer Two trig 1. Inside develop meters), storeys in heigh proximit shadow 2. Outside develop meters) sensitive develop shadow develop	e the Gree ment is ov . If a devel or less, bu t and/or m y to a sha analysis r de the Gre ment is ov and is in o e area. Wh ment is no sensitive ment) the is over 5	increase in differ a residence use.  Inbelt: proper 5 store opment pout is proportassing and dow sensimal be received a proper a	posed ys in heig roposal is sing an in d is in clo tive area, quested. roposed ys in heig imity to a posed proximity industrial a shadov	tht (≤15 5 ocrease se a ht (≤9 shadow to a	
		A Site Plan is a visual drawing that illustrates the	Study T	⊠ rigger Det	ails.			Site Plan Yes □ No □
	31. Site Plan	proposed development of a site in two dimensions.	Site Pla		<u>uii3</u> .			Concept Plan Yes □ No □
		S.C. III (III GIIII GIIII)	Other ap	oplications	: where a	layout of	the	100 - 110 -

			densities provides sites provides sites pro with mul more bu and/or a sites with (such as vehicula sites whadjacent	ealm, build s or massing changes posing mu- tiple lando ildings, on new publi h proposed active tra r circulation ere the de properties integrated	ng of the plant to the plant to the plant to the park of corprivate the corportation or accepted the corportation of the corp	ext; es ro or n, ); ctivity ss, sit); on by or	Facility Fit Plan Yes □ No □	
	32. Urban Design Brief	Illustrate how a development proposal represents high-quality and context sensitive design that implements policies of the Official Plan, relevant secondary plans, and Council approved plans and guidelines.	Study Trigger Details: For all Official Plan amendment, Zoning Bylaw amendment, and plan of subdivision applications.  For SPC applications: proposals for residential buildings with 25 or more residential units, or for proposals for residential buildings with less than 25 residential units, if the units are within the Urban area or the High-performance Development Standard threshold in the rural area where OP Policy 11.3 (3) is relevant; for non-residential and mixed-use proposals.					
	33. Urban Design Review Panel Report	Demonstrates that a development proposal has attended an Urban Design Review Panel formal review meeting, received, and responded to the associated recommendations, if applicable	Study Trigger Details: Required for all planning act applications subject to UDRP review, in accordance with the UDRP Panel Terms of Reference.					
	34. Wind Analysis	A visual model and a written evaluation of how a proposed development will impact pedestrian-level wind conditions.	Study Trigger Details: Applications seeking an increase in height and/or massing which is either: a tall building(s), 10 storeys or more or a proposed building that is more than twice the height of					

			five store existing	or planned	ouildings a ght and is d low rise er bodies a	adjacent t developm	o ent,	
		The purpose of the Zoning		$\boxtimes$			$\boxtimes$	
	35. Zoning Confirmation Report	Confirmation Report (ZCR) is to identify all zoning compliance issues, if any, at the outset of a planning application.		rigger Deta d for all Si	ails: PC and ZE	BLA applic	ations.	

			ENVI	RONME	NTAL				
D		Study / Dian Name	Description		Wh	en Requi	Applicable Study Components		
R	Α	Study / Plan Name	Description	1	2	3	4	5	& Other Comments
			Includes a community energy analysis, alongside						
		36. Community Energy Plan	mitigation measures, and other associated information. The community energy analysis refers to the overall assessment process to identify on and off-site measures to align the design of the development with City climate objectives.	gation measures, and er associated ormation. The community ergy analysis refers to the erall assessment process dentify on and off-site assures to align the eign of the development					
			The Energy Modeling Report is a Site Plan Control						
		37. Energy Modelling Report	application submission requirement to show how climate change mitigation, and energy objectives will be met through exterior building design elements.	NOT I	MPLEMEI	NTED & N	JIRED		
			Assessment of environmental impacts of a	$\boxtimes$	$\boxtimes$	$\boxtimes$		$\boxtimes$	Assessment of Landform Features
		38. Environmental Impact Study	project and documents the existing natural features, identifies the potential environmental impacts,	Is require	igger Deta ed when d n is propos	levelopme			Yes □ No □  Integrated Environmental Review Yes □ No □


		recommends ways to avoid and reduce the negative impacts, and proposes ways to enhance natural features and functions.	designa the City' hazardo The EIS Environi provides features EIS is re	d distance ted lands, is Natural I pus forest to Decision mental Impersion and adjace equired to sions under	natural he Heritage S ypes for w Tool (Apponent Study st of the national areas support de	eritage fea System, or vildland fir endix 2 of Guideling atural her within whevelopmen	Protocol for Wildlife Protection during Construction Yes □ No □  Significant Woodlands Guidelines for Identification, Evaluation, and Impact Assessment Yes □ No □	
	39. Environmental Management Plan	A comprehensive environmental planning document that identifies, evaluates, and mitigates the potential impacts of proposed development on the natural environment and its ecological functions at local planning stage.	Official I (area-sp where: t condition based; t planned subdivisimpact c subdivisimplications)	rigger Deta Plan amen pecific polic here is sig ns upon where are p infrastruct ion that wo on the infra ion within ble Class E I has expir	dments for secondificant chair the or roposed could have structure the EMP structure the EMP structure	ndary pla nange in the riginal stuchanges to ed to serve a signification needs of study area		
	40. High-performance Development Standard	A collection of voluntary and required standards that raise performance of new building projects to achieve sustainable and resilient design	NOT IMPLEMENTED & NOT REQUIRED					
	41. Tree Conservation Report	Demonstrates how tree cover will be retained and protected on the site, including mature trees, stands of trees, and hedgerows.	Study Trigger Details: Where there is a tree of 10 centimeters in diameter or greater on the site and/or if there is a tree on an adjacent site that has a Critical Root Zone (CRZ) extending onto the development site.					



250 mm ø STM 0.830 m CLEARANCE OVER 200 mm ø W/M

250 mm ø STM 1.670 m CLEARANCE OVER 250 mm ø SAN

250 mm ø STM 0.700 m CLEARANCE OVER 200 mm ø W/M




# **Appendix B**

## Boundary Conditions 8201 Campeau Drive – 2025 Update

## **Provided Information**

Scenario	Dem	nand
Scenario	L/min	L/s
Average Daily Demand	95	1.59
Maximum Daily Demand	238	3.96
Peak Hour	524	8.74
Fire Flow Demand #1	18,000	300.00

## **Location**



#### **Results**

#### **Connection 1**

Demand Scenario	Head (m)	Pressure <sup>1</sup> (psi)
Maximum HGL	162.0	93.9
Peak Hour	155.8	85.1
Max Day plus Fire Flow #1	133.5	53.5

<sup>&</sup>lt;sup>1</sup> Ground Elevation = 95.9 m

#### **Connection 2**

Demand Scenario	Head (m)	Pressure <sup>1</sup> (psi)
Maximum HGL	162.0	93.9
Peak Hour	155.8	85.1
Max Day plus Fire Flow #1	132.2	51.6

<sup>&</sup>lt;sup>1</sup> Ground Elevation = 95.9 m

#### **Notes**

- 1. The IWSD has recently updated their water modelling software. Any significant difference between previously received BC results and newly received BC results could be attributed to this update.
- 2. As per the Ontario Building Code in areas that may be occupied, the static pressure at any fixture shall not exceed 552 kPa (80 psi.) Pressure control measures to be considered are as follows, in order of preference:
  - If possible, systems to be designed to residual pressures of 345 to 552 kPa (50 to 80 psi) in all occupied areas outside of the public right-of-way without special pressure control equipment.
  - Pressure reducing valves to be installed immediately downstream of the isolation valve in the home/ building, located downstream of the meter so it is owner maintained.

#### **Disclaimer**

The boundary condition information is based on current operation of the city water distribution system. The computer model simulation is based on the best information available at the time. The operation of the water distribution system can change on a regular basis, resulting in a variation in boundary conditions. The physical properties of watermains deteriorate over time, as such must be assumed in the absence of actual field test data. The variation in physical watermain properties can therefore alter the results of the computer model simulation. Fire Flow analysis is a reflection of available flow in the watermain; there may be additional restrictions that occur between the watermain and the hydrant that the model cannot take into account.

WATERMAIN DEMAND CALCULATION SHEET

WATERMAIN DEMAND CALCULATION SHEET

8201 Campeau Drive | Patry Group / Theberge Homes 147814 -6.0 | Rev #2 | 2025-06-06 Prepared By: MAP | Checked By: SEL

ARCADIS ARCADIS IBI GROUP

500-333 Preston Street Ottawa, Ontario K1S 5N4 Canada

**IBI GROUP** arcadis.com

		RESID	ENTIAL		NON-RESIDENTIAL (ICI)			AVERAGE DAILY DEMAND (I/s)			MAXIMUM DAILY DEMAND (I/s)			MAXIMUM HOURLY DEMAND (I/s)			
NODE	1 Bedroom Apartment	2 Bedroom Apartment	3 Bedroom Apartment	POPULATION	INDUST. (ha)	COMM. (m2)	INSTIT.	RESIDENTIAL	ICI	TOTAL	RESIDENTIAL	ICI	TOTAL	RESIDENTIAL	ICI	TOTAL	FIRE DEMAND (I/min)
Building A + B	297	12	16	490.6				1.59		1.59	3.97		3.97	8.74		8.74	18,000
											-			-			

POPULATION DENSITY		WATER DEMAND RATE	<u>S</u>	PEAKING FACTORS		FIRE DEMANDS
1 Bedroom Apartment	1.4 persons/unit	Residential	280 l/cap/day	Maximum Daily		Single Family
2 Bedroom Apartment	2.1 persons/unit	Commercial Shopping Ce	enter	Residential Commercial	2.5 x avg. day 1.5 x avg. day	Semi Detached &
3 Bedroom Apartment	3.1 persons/unit	Institutional	2,500 L/(1000m2)/day 75 l/cap/day	Maximum Hourly Residential Commercial	2.2 x avg. day 1.8 x avg. day	Townhouse 15,000 l/min (250.0 l/s)  Medium Density 15,000 l/min (250 l/s)

WATERMAIN DEMAND CALCULATION SHEET

WATERMAIN DEMAND CALCULATION SHEET

8201 Campeau Drive | Patry Group / Theberge Homes 147814 -6.0 | Rev #2 | 2025-06-06 Prepared By: MAP | Checked By: SEL

ARCADIS ARCADIS IBI GROUP

500-333 Preston Street Ottawa, Ontario K1S 5N4 Canada

**IBI GROUP** arcadis.com

		RESID	ENTIAL		NON-RESIDENTIAL (ICI)			AVERAGE DAILY DEMAND (I/s)			MAXIMUM DAILY DEMAND (I/s)			MAXIMUM HOURLY DEMAND (I/s)			
NODE	1 Bedroom Apartment	2 Bedroom Apartment	3 Bedroom Apartment	POPULATION	INDUST. (ha)	COMM. (m2)	INSTIT.	RESIDENTIAL	ICI	TOTAL	RESIDENTIAL	ICI	TOTAL	RESIDENTIAL	ICI	TOTAL	FIRE DEMAND (I/min)
Building A + B	297	12	16	490.6				1.59		1.59	3.97		3.97	8.74		8.74	18,000
											-			-			

POPULATION DENSITY		WATER DEMAND RATE	<u>S</u>	PEAKING FACTORS		FIRE DEMANDS
1 Bedroom Apartment	1.4 persons/unit	Residential	280 l/cap/day	Maximum Daily		Single Family
2 Bedroom Apartment	2.1 persons/unit	Commercial Shopping Ce	enter	Residential Commercial	2.5 x avg. day 1.5 x avg. day	Semi Detached &
3 Bedroom Apartment	3.1 persons/unit	Institutional	2,500 L/(1000m2)/day 75 l/cap/day	Maximum Hourly Residential Commercial	2.2 x avg. day 1.8 x avg. day	Townhouse 15,000 l/min (250.0 l/s)  Medium Density 15,000 l/min (250 l/s)



500-333 Preston Street

Ottawa, Ontario K1S 5N4 Canada arcadis.com

#### FIRE UNDERWRITERS SURVEY

8201 Campeau Drive | Patry Group / Theberge Homes 147814 -6.0 | Rev #2 | 2025-06-06 Prepared By: MAP | Checked By: SEL

STEP	Contents	Description		Adjustment F	actor	Res	ult
	Building A (AA)	Floor 1	1452	Floors	1	1452	m2
	6-storey residential	Floors 2-6	1404	Floors	5	7020	m2
1							
	Total Effective Floor Area					8472	m2
		Type V Wood Frame	1.5				
2	Type of Construction	Type III Ordinary Construction	1.0	Type V Wood	1.5		
	<b>3</b>	Type II Noncombustible Construction	0.8	Frame			
		Type I Fire Resistive Construction	0.6				
3	Required Fire Flow	RFF = 220C√A, rounded to nearest 1000 L/min		T		30000	L/min
		Noncombustible Contents	-25%				
	0	Limited Conbustible Contents	-15%	Limited	450/	4500	. , .
4	Occupancy and Contents	Combustible Contents	0%	Conbustible Contents	-15%	-4500	L/min
		Free Burning Contents	15%	Contents			
		Rapid Burning Contents	25%				
	Fire Flow					25500	L/min
		Automatic Sprinkler Conforming to NFPA 13	-30%	Yes	-30%	-7650	L/min
	Automatic Sprinkler Protection	Standard Water Supply for both the system	-10%	Yes	-10%	-2550	L/min
5		and Fire Department Hose Lines			1070	2000	L/
		Fully Supervised System	-10%	No			
	Total Sprinkler Adjustment					-10200	L/min
	Exposure Adjustment	Based on <b>Table 6</b> Exposure Adjustement Cha	rges for Sub	ject Building			
		Separation (m)					
	North	Length X Height Factor (m.storeys)		Firewall	10%	2550	L/min
		Construction Type					
		Separation (m)	>30				
	South	Length X Height Factor (m.storeys)				0	L/min
6		Construction Type					
		Separation (m)	>30				
	East	Length X Height Factor (m.storeys)				0	L/min
		Construction Type					
		Separation (m)	>30				
	West	Length X Height Factor (m.storeys)				0	L/min
		Construction Type					
	Total Exposure Adjustment					2550	L/min
7	Total Required Fire Flow					17850	L/min
′	i otal Nequileu File Flow	Rounded to Nearest 1000 L/min				18000	L/min

Notes 1. Fire flow calculation are based on Fire Underwriters Survey version 2020.

<sup>2.</sup> If any vertical opening in the building are unprotected (e.g. interconnected floor spaces, elevators etc.), consider the two largest adjoining floor area plus 50% of all floors immediately above them up to a maximum of eight.



FIRE UNDERWRITERS SURVEY

500-333 Preston Street Ottawa, Ontario K1S 5N4 Canada arcadis.com 8201 Campeau Drive | Patry Group / Theberge Homes 147814 -6.0 | Rev #2 | 2025-06-06 Prepared By: MAP | Checked By: SEL

STEP	Contents	Description		Adjustment Fa	ctor	Res	ult
	Building A (AB) + LINK	Floor 1	1432	Floors	1	1432	m2
	6-storey residential	Floors 2-6	986	Floors	5	4930	m2
1							
	Total Effective Floor Area					6362	m2
		Type V Wood Frame	1.5				
2	Type of Construction	Type III Ordinary Construction	1.0	Type V Wood	1.5		
_	.,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	Type II Noncombustible Construction	8.0	Frame			
		Type I Fire Resistive Construction	0.6				
3	Required Fire Flow	RFF = 220C√A, rounded to nearest 1000 L/mi				26000	L/min
		Noncombustible Contents	-25%				
		Limited Conbustible Contents	-15%	Limited			
4	Occupancy and Contents	Combustible Contents	0%	Conbustible	-15%	-3900	L/min
-		Free Burning Contents	15%	Contents			
		Rapid Burning Contents	25%				
	Fire Flow					22100	L/min
		Automatic Sprinkler Conforming to NFPA 13	-30%	Yes	-30%	-6630	L/min
	Automatic Sprinkler Protection	Standard Water Supply for both the system	-10%	Yes	-10%	-2210	L/min
5		and Fire Department Hose Lines		163	-10 /0	-2210	
		Fully Supervised System	-10%	No		0	L/min
	Total Sprinkler Adjustment					-8840	L/min
	Exposure Adjustment	Based on Table 6 Exposure Adjustement Cha	rges for Sub	ject Building			
		Separation (m)	>30				
	North	Length X Height Factor (m.storeys)				0	L/min
		Construction Type					
		Separation (m)					
	South	Length X Height Factor (m.storeys)		Firewall	10%	2210	L/min
_		Construction Type					
6		Separation (m)					
	East	Length X Height Factor (m.storeys)		Firewall	10%	2210	L/min
		Construction Type					
		Separation (m)	28.6				
	West	Length X Height Factor (m.storeys)	21.1	With unprotected opening	0%	0	L/min
		Construction Type	, ,			ĺ	
	Total Exposure Adjustment	Constitution Type	турстп	i		4420	L/min
						17680	L/min
7	Total Required Fire Flow	Rounded to Nearest 1000 L/min				18000	L/min
1	i e e e e e e e e e e e e e e e e e e e	Rodrided to Nedicat 1000 E/IIIII				10000	<u>-////////////////////////////////////</u>

Notes 1. Fire flow calculation are based on Fire Underwriters Survey version 2020.

<sup>2.</sup> If any vertical opening in the building are unprotected (e.g. interconnected floor spaces, elevators etc.), consider the two largest adjoining floor area plus 50% of all floors immediately above them up to a maximum of eight.



500-333 Preston Street

Ottawa, Ontario K1S 5N4 Canada arcadis.com

#### **FIRE UNDERWRITERS SURVEY**

8201 Campeau Drive | Patry Group / Theberge Homes 147814 -6.0 | Rev #2 | 2025-06-06 Prepared By: MAP | Checked By: SEL

STEP	Contents	Description		Adjustment F	actor	Res	ult
	Building B (BA)	Floor 1	1251	Floors	1	1251	m2
	6-storey residential	Floors 2-6	1089	Floors	5	5445	m2
1							
	Total Effective Floor Area					6696	m2
		Type V Wood Frame	1.5				
2	Type of Construction	Type III Ordinary Construction	1.0	Type V Wood	1.5		
	. , , , , , , , , , , , , , , , , , , ,	Type II Noncombustible Construction	0.8	Frame			
_		Type I Fire Resistive Construction	0.6				
3	Required Fire Flow	RFF = 220C√A, rounded to nearest 1000 L/mir		ī		27000	L/min
		Noncombustible Contents	-25%				
	0	Limited Conbustible Contents	-15%	Limited	450/	4050	1 /:
4	Occupancy and Contents	Combustible Contents Free Burning Contents	0% 15%	Conbustible Contents	-15%	-4050	L/min
		Rapid Burning Contents	25%	Contents			
	Fire Flow	Rapid Burning Contents	23 /0			22950	L/min
	FIFE FIOW			I			
		Automatic Sprinkler Conforming to NFPA 13	-30%	Yes	-30%	-6885	L/min
ا ۔ ا	Automatic Sprinkler Protection	Standard Water Supply for both the system	-10%	Yes	-10%	-2295	L/min
5		and Fire Department Hose Lines	-10%	N-			
	Total Sprinkler Adjustment	Fully Supervised System	-10%	No		-9180	L/min
_	Exposure Adjustment	Based on <b>Table 6</b> Exposure Adjustement Char	waa fan Cub	in at Divilalina		-9100	L/min
	Exposure Adjustment	•	>30	Ject Building			
	North	Separation (m)	>30			0	L/min
	NOTH	Length X Height Factor (m.storeys)				U	L/111111
		Construction Type					
		Separation (m)	>30				
	South	Length X Height Factor (m.storeys)				0	L/min
6		Construction Type					
		Separation (m)					
	East	Length X Height Factor (m.storeys)		Firewall	10%	2295	L/min
		Construction Type					
		Separation (m)					
	West	Length X Height Factor (m.storeys)		Firewall	10%	2295	L/min
		Construction Type					
	Total Exposure Adjustment					4590	L/min
7	Total Required Fire Flow			<u> </u>		18360	L/min
'	rotal Required Fire Flow	Rounded to Nearest 1000 L/min				18000	L/min

Notes 1. Fire flow calculation are based on Fire Underwriters Survey version 2020.

<sup>2.</sup> If any vertical opening in the building are unprotected (e.g. interconnected floor spaces, elevators etc.), consider the two largest adjoining floor area plus 50% of all floors immediately above them up to a maximum of eight.



500-333 Preston Street

Ottawa, Ontario K1S 5N4 Canada arcadis.com


#### FIRE UNDERWRITERS SURVEY

8201 Campeau Drive | Patry Group / Theberge Homes 147814 -6.0 | Rev #2 | 2025-06-06 Prepared By: MAP | Checked By: SEL

STEP	Contents	Description		Adjustment F	actor	Res	ult
	Building B (BB)	Floor 1	844	Floors	1	844	m2
	6-storey residential	Floors 2-6	747	Floors	5	3735	m2
1							
	Total Effective Floor Area					4579	m2
		Type V Wood Frame	1.5				
2	Type of Construction	Type III Ordinary Construction	1.0	Type V Wood	1.5		
	<b>3</b>	Type II Noncombustible Construction	0.8	Frame			
		Type I Fire Resistive Construction	0.6				
3	Required Fire Flow	RFF = 220C√A, rounded to nearest 1000 L/mir				22000	L/min
		Noncombustible Contents	-25%				
	0	Limited Conbustible Contents	-15% 0%	Limited Conbustible	4.50/	2222	1 /!
4	Occupancy and Contents	Combustible Contents	0% 15%	Condustible	-15%	-3300	L/min
		Free Burning Contents Rapid Burning Contents	25%	Contents			
	Fire Flow	Rapid Burning Contents	25 /0			18700	L/min
-	FIFE FIOW	A	222/				
		Automatic Sprinkler Conforming to NFPA 13	-30%	Yes	-30%	-5610	L/min
5	Automatic Sprinkler Protection	Standard Water Supply for both the system	-10%	Yes	-10%	-1870	L/min
l °		and Fire Department Hose Lines Fully Supervised System	-10%	No			
	Total Sprinkler Adjustment	Fully Supervised System	-1070	INO		-7480	L/min
-	Exposure Adjustment	Based on <b>Table 6</b> Exposure Adjustement Cha	race for Sub	iost Building		-/400	L/IIIIII
	Exposure Aujustment	Separation (m)	>30				
	North	. , ,	/30			0	L/min
	North	Length X Height Factor (m.storeys)				0	L/111111
		Construction Type	. 00				
	Courth	Separation (m)	>30			0	L/min
	South	Length X Height Factor (m.storeys)				U	L/min
6		Construction Type					
	F	Separation (m)	>30				. , .
	East	Length X Height Factor (m.storeys)				0	L/min
		Construction Type					
		Separation (m)					
	West	Length X Height Factor (m.storeys)		Firewall	10%	1870	L/min
		Construction Type					
	Total Exposure Adjustment					1870	L/min
7	Total Required Fire Flow					13090	L/min
	•	Rounded to Nearest 1000 L/min				13000	L/min

Notes 1. Fire flow calculation are based on Fire Underwriters Survey version 2020.

<sup>2.</sup> If any vertical opening in the building are unprotected (e.g. interconnected floor spaces, elevators etc.), consider the two largest adjoining floor area plus 50% of all floors immediately above them up to a maximum of eight.



	ID	Demand (L/s)	Elevation (m)	Head (m)	Pressure (kPa)
1	J1	0.00	95.55	162.00	651.16
2	J10	0.00	95.50	162.00	651.64
3	J12	0.00	95.65	162.00	650.17
4	J14	0.00	95.70	162.00	649.68
5	J16	0.72	96.50	162.00	641.84
6	J2	0.00	95.55	162.00	651.16
7	J3	0.44	95.80	162.00	648.71
8	J4	0.44	95.80	162.00	648.71

Date: Thursday, July 17, 2025, Page 1

	ID	Demand (L/s)	Elevation (m)	Head (m)	Pressure (kPa)
1	J1	0.00	95.55	155.80	590.39
2	J10	0.00	95.50	155.79	590.78
3	J12	0.00	95.65	155.78	589.24
4	J14	0.00	95.70	155.78	588.75
5	J16	3.94	96.50	155.77	580.81
6	J2	0.00	95.55	155.80	590.39
7	J3	2.45	95.80	155.80	587.93
8	J4	2.45	95.80	155.80	587.93

	ID	From Node	To Node	Length (m)	Diameter (mm)	Roughness	Flow (L/s)	Velocity (m/s)	Headloss (m)	HL/1000 (m/k-m)	Status	Flow Reversal Count
1	P11	J1	J2	3.90	204.00	110.00	1.84	0.06	0.00	0.04	Open	0
2	P13	J16	J12	74.05	204.00	110.00	-3.94	0.12	0.01	0.14	Open	0
3	P15	J12	J14	4.02	204.00	110.00	0.00	0.00	0.00	0.00	Open	0
4	P17	J12	J10	50.00	204.00	110.00	-3.94	0.12	0.01	0.14	Open	0
5	P19	J10	J2	68.87	204.00	110.00	-3.94	0.12	0.01	0.14	Open	0
6	P21	J1	BC1	9.45	204.00	110.00	-4.29	0.13	0.00	0.17	Open	0
7	P23	J2	BC2	9.19	204.00	110.00	-4.55	0.14	0.00	0.19	Open	0
8	P25	J2	J4	6.63	204.00	110.00	2.45	0.07	0.00	0.06	Open	0
9	P27	J1	J3	6.76	204.00	110.00	2.45	0.07	0.00	0.06	Open	0

Date: Thursday, July 17, 2025, Page 1

	ID	Capacity Assessment	Total Demand (L/s)	Hydrant Available Flow (L/s)	Critical Node ID for Design Run	Critical Node Pressure at Available Flow (kPa)	Critical Node Pressure at Fire Demand (kPa)	Critical Pressure for Design Run (kPa)	Hydrant Design Flow (L/s)	Hydrant Pressure at Design Flow (kPa)
1	J14	FAIL	300.00	184.70	J14	139.96	-180.54	139.96	184.70	139.96


# **Appendix C**

SANITARY SEWER DESIGN SHEET

ARCADIS PROFESSIONAL SERVICES (CANADA) INC. 500-333 Preston Street Ottawa, Onlain k15 SN4 Canada arcadis.com

8201 Campeau Drive 8201 Campeau Drive Inc. CITY OF OTTAWA

	LOCATION			1				RESID	ENTIAL								ICI A	AREAS				INFILT	RATION ALL	OWANCE	EWED !		TOTAL			PROPO	SED SEWER	DESIGN		$\overline{}$
	LUCATION			AREA		UNIT	TYPES		AREA	POPU	LATION	RES	PEAK				A (Ha)			ICI	PEAK	ARE	A (Ha)	FLOW	FIXED	LOW (L/s)	FLOW	CAPACITY	LENGTH	DIA	SLOPE	VELOCITY	AVAI	ILABLE
STREET	AREA ID	FROM	TO	w/ Units	AVG	1 Bed	2 Bed	3 Bed	w/o Units	IND	CUM	PEAK	FLOW	INSTI	TUTIONAL	COMN	IERCIAL	INDU	STRIAL	PEAK		IND	CUM	(L/s)	IND	CUM	(L/s)	(L/s)		4	49/3	(full)	CAP	PACITY
SIREEI	AREA ID	MH	MH	(Ha)	AVG	APT	APT	APT	(Ha)	IND	CUM	FACTOR	(L/s)	IND	CUM	IND	CUM	IND	CUM	FACTOR	(L/s)	IND	COM	(L/S)	IND	CUM	(L/S)	(L/S)	(m)	(mm)	(%)	(m/s)	L/s	(%)
																																		$\overline{}$
FUTURE DEV.		FUT	BLK110A	2.80	3000					5400.0				0.00			0.0	0.00	0.0			2.80	2.8	0.92	0.00	0.0	49.42	57.20	31.00	250	0.85	1.129	7.78	13.60%
J WAY		BLK110A	MH101A	0.01						0.0	5400.0	2.77	48.49	0.00	0.0	0.00	0.0	0.00	0.0	1.00	0.00	0.01	2.8	0.93	0.00	0.0	49.42	57.20	42.90	250	0.85	1.129	7.78	13.59%
									ı																									, ,
PHASE 2	BLDG B	BLDG B	MH102A	0.66		134	7	6		217.3	217.3	3.51	2.47	0.00	0.0	0.00	0.0	0.00	0.0	1.00	0.00	0.66	0.7	0.22	0.00	0.0	2.69	57.20	16.00	250	0.85	1.129	54.51	95.30%
	MH102A	MH102A	MH101A	0.01						0.0	217.3	3.51	2.47	0.00	0.0	0.00	0.0	0.00	0.0	1.00	0.00	0.01	0.0	0.00	0.00	0.0	2.47	57.20	16.00	250	0.85	1.129	54.72	95.68%
J WAY	MH101A	MH101A	MH100A	0.06						0.0	5617.3	2.76	50.21	0.00	0.0	0.00	0.0	0.00	0.0	1.00	0.00	0.06	3.5	1.16	0.00	0.0	51.38	57.20	55.00	250	0.85	1.129	5.82	10.18%
	MH100A																																	
TAGGART ROAD	MH100A	MH100A	EXMH10	0.09						0.0	5617.3	2.76	50.21	0.00	0.0	0.00	0.0	0.00	0.0	1.00	0.00	0.09	3.6	1.19	0.00	0.0	51.41	57.20	77.88	250	0.85	1.129	5.79	10.12%
TAGGART ROAD	BLDG A	CAP	FXMH10	0.34	-	155	11	10		265 1	265.1	0.40	2.99	0.00	0.0	0.00	0.0	0.00	0.0	1.00	0.00	0.34	0.3	0.11	0.00	0.0	3.10	43.87	20.00	250	0.50	0.866	40.77	92 93%
TAGGART RUAD	DLUG A	CAP	EXMH10	0.34		155	- 11	10		265.1	265.1	3.48	2.99	0.00	0.0	0.00	0.0	0.00	0.0	1.00	0.00	0.34	0.3	0.11	0.00	0.0	3.10	43.87	20.00	250	0.50	0.866	40.77	92.93%
								_						_				_	-			-				-		-						+1
								_						_				_	-			-				-		-						+1
		+	ł	1	+					+				+	_					+	-		-	-	1	+	<b>+</b>		-	-				+
				1					1	1				1							_													-
										-				+					_					-										+
			1		+					1														1		1	1			1				+
			1		+					1														1		1	1			1				1
														1																				<del>+</del>
Design Parameters:				Notes:						•		Designed		MAP			No.							Revision								Date		
				1. Manning	s coefficient (	n) =		0.013				_					1.						Servicing Bri	ef - Submission	on No. 1							2025-07-18		$\overline{}$
Residential		ICI Areas		2. Demand	(per capita):			L/day	200	L/day																								-
AVG 1.8 p/p/u				3. Infiltration	n allowance:			3 L/s/Ha				Checked:		SEL																				
1 Bed 1.4 p/p/u	INST 28,00	0 L/Ha/day		4. Resident	tial Peaking F	actor:																												
2 Bed 2.1 p/p/u	COM 28,00				Harmon Fo	rmula = 1+(1	14/(4+(P/10	000)^0.5))0.	В																					1				
3 Bed 2.5 p/p/u	IND 35,00		MOE Chart		where K = 0							Dwg. Refe	erence:	3028280	6-400																			
Other 60 p/p/Ha	1700	0 L/Ha/day		5. Commerc	cial and Institu	itional Peak I	Factors bas	sed on total	area,									ile Referen							Date:							Sheet No:		
1				1.5 if greate	r than 20%, o	therwise 1.0	)										30	282806-6.0	14.04						2025-07-1	8						1 of 1		




# **Appendix D**

**ARCADIS** 

ARCADIS PROFESSIONAL SERVICES (CANADA) INC. 500-333 Preston Street Ottawa, Ontario K1S 5N4 Canada arcadis.com STORM SEWER DESIGN SHEET
8201 Campeau Drive
8201 Campeau Drive Inc.
CITY OF OTTAWA

	LOCATION						A	REA (Ha)											RATIO	NAL DESIG	N FLOW										S	EWER DAT	Ά			
STREET	AREA ID	FROM	то	C=	C=	C=	C= C:	= C=	C= (	:= C:	= C=	IND	CUM	INLET	TIME	TOTAL	i (2)	i (5)	i (10)	i (100)	2vr PEAK	5vr PEAK	10vr PEAH	100yr PEAK	FIXED	FLOW	DESIGN	CAPACITY	LENGTH		PIPE SIZE (m	m)	SLOPE	VELOCITY	AVAIL	CAP (2vr)
SIREEI	AREAID	FROM	10	0.20	0.25	0.57	0.61 0.6	0.64	0.69 0	72 0.8	81 0.9	0 2.78A	2.78AC	(min)	IN PIPE	(min)	(mm/hr)	(mm/hr)	(mm/hr)					) FLOW (L/s)		CUM	FLOW (L/s)	(L/s)	(m)	DIA	w	´ H	(%)	(m/s)	(L/s)	(%)
				ļ								_																								
				-				_				_					-														_					
SITE PLAN	ROOF B1, ROOF B2, CB10	DI 164.00	MH102	1	_	-	0.19	_	-	_	0.44	0 000	0.00	10.00	0.99	40.00	70.04	104.19	400.44	470.50	04.00	83 10	07.40	142.42	0.00	0.00	61.26	400.04	56.57	375	-		0.35	0.949	10.05	43.39%
SITE PLAN	ROOF B1, ROOF B2, CB10	BLK103	MH102	1		1	0.19	_		_	0.13	9 0.80	0.80	10.00	0.99	10.99	76.81	104.19	122.14	1/8.56	61.26	83.10	97.42	142.42	0.00	0.00	61.26	108.21	56.57	3/5	+		0.35	0.949	46.95	43.39%
SITE PLAN	CB106	CB106	CB105	1		0.09						0.14	0.14	10.00	0.41	10.41	76.81	104.19	122 14	178 56	10.95	14.86	17 42	25.47	0.00	0.00	10.95	41.80	20.46	250			0.45	0.825	30.85	73.80%
SITE PLAN	CB105	CB105	CBMH10	4					0	07		0.14	0.28	10.41	0.34	10.76	75.25	102.06	119.63	174.87	21.28	28.85	33.82	49.44	0.00	0.00	21.28	41.66	16.90	250			0.45	0.822	20.39	48.93%
				ļ								_																								
SITE PLAN	CBMH104	CBMH104	MH102	-				_	0.05			0.10	0.38	10.76	0.10	10.86	74.02	100.36	117.63	171.93	28.03	38.00	44.54	65.10	0.00	0.00	28.03	58.86	6.92	250			0.90	1.162	30.83	52.38%
SITE PLAN		MH102	MH101	1		1		_		_		0.00	1 10	10.99	0.39	11 20	72 10	99.22	116 20	160.06	96.00	116 71	126 70	199.91	0.00	0.00	86.09	109 21	21.94	375	+		0.35	0.949	22.12	20.45%
SHE PLAN		MIT IUZ	MHIUI	1-						_		0.00	1.10	10.99	0.39	11.30	73.19	99.22	110.29	109.90	00.09	110.71	130.70	199.91	0.00	0.00	00.09	100.21	21.84	3/3	+		0.33	0.949	22.12	20.45%
J WAY	EXT	BLK110	MH101							3.3	38	7.61	7.61	13.60	0.13	13.73	65.28	88.36	103.51	151.19	496.82	672.54	787.79	1.150.73	0.00	0.00	496.82	687.10	11.96	750			0.35	1.507	190.28	27.69%
J WAY	CICB100A	CICB100A						0.02						10.00				104.19				3.71		6.35		0.00	2.73		12.90	250			2.09			96.95%
			CICB100									0.00	0.04	10.12	0.02	10.14	76.34	103.56	121.39	177.46	2.72	3.68	4.32	6.31	0.00	0.00	2.72	62.04	1.50	250			1.00	1.224	59.32	95.62%
	CICB100B	CICB100E	STM	-				_	0.09			0.17	0.21	10.14	0.04	10.18	76.26	103.45	121.27	177.27	15.88	21.54	25.25	36.91	0.00	0.00	15.88	61.88	3.15	250			1.00	1.221	46.00	74.34%
JWAY		MI1404	MH100	1	_	-		_	-	_	_	0.00	0.00	10.70	0.57	14.24	64.02	07.00	402.04	450.20	E04.04	700 EE	025.00	1.352.58	0.00	0.00	584.04	885.93	E4.07	825	-		0.25	1.606	201.00	24.000/
JWAT		MITTUI	MILION	1				_				0.00	9.00	13.73	0.57	14.31	04.93	07.00	102.94	130.36	304.04	790.55	925.99	1,332.30	0.00	0.00	304.04	000.93	34.97	1500	+		0.33	1.000	301.80	34.00%
				1								1					1										1	1		7300						
TAGGART ROAD	CB97	CB97	CB98							0.0	08	0.18	0.18	10.00	0.26	10.26	76.81	104.19	122.14	178.56	13.84	18.77	22.00	32.17	0.00	0.00	13.84	62.04	18.93	250			1.00	1.224	48.20	77.70%
TAGGART ROAD	CB98	CB98	UGS						0	02				10.26				102.85						38.80	0.00	0.00	16.70	62.04	2.84	250			1.00		45.34	73.09%
TAGGART ROAD		UGS												10.30		10.32				175.89		22.60			0.00	0.00	16.66	62.04	1.50	250			1.00	1.224		73.14%
TAGGART ROAD	CB99	CB99	STM						0	05		0.10	0.32	10.32	0.11	10.43	75.61	102.55	120.21	175.71	24.21	32.84	38.50	56.27	0.00	0.00	24.21	62.04	8.37	250			1.00	1.224	37.82	60.97%
				1								_																		1500						
				-				_				_					-																			
		_		1		1		_		_		+										-									+					
				1-						_		+																			+					
Definitions:	1	1	·	Notes	:		1 1	- '		- '	- '		·	Designed:	1	MAP	1		·	No.						Revi	ision	-			•			Date		
Q = 2.78CiA. where:				1. Mar	nninas c	oefficien	t (n) = 0.0	13												1.					Servicina E	Brief - Submi	ssion No. 1							2025-07-18		
Q = Peak Flow in Litr				1	9		. ,	-																												
A = Area in Hectares	(Ha)													Checked:		SEL																				
	in millimeters per hour (r	nm/hr)		1																																
[i = 732.951 / (TC+		2 YEAR		1																																
[i = 998.071 / (TC+	6.053)^0.814]	5 YEAR		1										Dwg. Refe	rence:	30282806	-500																			
[i = 1174.184 / (TC		10 YEAR		1																	File R	eference:					Dat							Sheet No:		
[i = 1735.688 / (TC	C+6.014)^0.820]	100 YEAR	₹	1										I							302828	806-6.04.04					2025-0	7-18						1 of 1		



500-333 Preston Street Ottawa, Ontario K1S 5N4 Canada arcadis.com

STORMWATER MANAGEMENT

8201 Campeau Drive | 8201 Campeau Drive Inc. 30282806-6.0 | Rev #1 | 2025-07-18 Prepared By: MAP | Checked By: SEL

#### Formulas and Descriptions

$$\begin{split} i_{2yr} &= 1:2 \text{ year Intensity} = 732.951 \, / \, \left( T_c {+}6.199 \right)^{0.810} \\ i_{6yr} &= 1:5 \text{ year Intensity} = 998.071 \, / \left( T_c {+}6.053 \right)^{0.814} \end{split}$$

 $l_{\rm byr}$  = 1:0: year Intensity = 998.07.1 ([1,+6.053)^{o.1.00}  $l_{\rm 100yr}$  = 1:100 year Intensity = 1735.688 / ( $T_{\rm c}$ +6.014)<sup>0.000</sup>  $T_{\rm c}$  = Time of Concentration (min) C = Average Runoff Coefficient A = Area (Ha) Q = Flow = 2.78CiA (L/s)

#### Maximum Allowable Release Rate

#### Restricted Flowrate

Per McIntosh Perry Assesment of Adequacy of Public Services Report - 8201 Campeau Drive & 303 Didsbury Road (CCO-24-3115) dated 12 January 2024 Calculated at 85 L/sha with 1.24ha for this site (excluding park land)

105.40 L/s

Uncontrolled Release (Q uncontrolled = 2.78\*C\*i 100yr \*A uncontrolled)

0.85 10 min 178.56 mm/hr 0.09 Ha 37.97 L/s

Maximum Allowable Release Rate (Q max allowable = Q restricted - Q uncontrolled)

Q<sub>max allowable</sub> =

#### MODIFIED RATIONAL METHOD (100-Year, 5-Year & 2-Year Ponding)

Drainage Area	ROOF A							
Area (Ha)	0.190	Restricted Flow ICD Ac	tual (L/s)=	4.00				
C =	1.00	Restricted Flow Q <sub>r for so</sub>	<sub>vm calc</sub> (L/s)=	4.00	50% reduction if s	ub-surface storage		
		100-Year Pondi	ing			100-Y	ear +20% Pc	nding
T <sub>c</sub> Variable	i <sub>100yr</sub>	Peak Flow Q <sub>p</sub> =2.78xCi <sub>100yr</sub> A	Q,	Q <sub>p</sub> -Q <sub>r</sub>	Volume 100yr	100YRQ <sub>p</sub> 20%	Qp - Qr	Volume 100+20
(min)	(mm/hour)	(L/s)	(L/s)	(L/s)	(m³)	(L/s)	(L/s)	(m³)
105	36.50	19.28	4.00	15.28	96.25			
110	35.20	18.59	4.00	14.59	96.32			
115	34.01	17.96	4.00	13.96	96.33	21.55	17.55	121.12
120	32.89	17.38	4.00	13.38	96.30			
125	31.86	16.83	4.00	12.83	96.22			

	s	torage (m3)				100+20	
Overflow	Required	Surface	Sub-surface	Balance	Overflow	Required	Balance
0.00	96.33	106.88	0	0.00	0.00	121.12	14.25
					convert to flow	with peak Tc (L/s)	2.06

Sub-surface	Balance	Overtiow	Requirea	Balance	
0	0.00	0.00	121.12	14.25	
		convert to flow	with peak Tc (L/s)	2.06	

	Storage (m²)												
Overflow	Required	Surface	Sub-surface	Balance	Т								
0.00	28.02	106.88	0	0.00									
			overflows to:	0.00									

2-Year Ponding

Peak Flow Q<sub>p</sub>=2.78xCi<sub>2vr</sub>A

2-Year Ponding
Peak Flow

 $Q_p = 2.78xCi_{2yr}A$ 

Q.

Q.-Q.

Q<sub>p</sub>-Q<sub>r</sub>

2.00

overflows to: 0.00

 $Q_p - Q_r$ 

28.00 28.01 28.02 28.02 28.01

Volume

2yr (m³)

Drainage Area	ROOF B	1						
Area (Ha)	0.190	Restricted Flow ICD A	ctual (L/s)=	4.00	1			
C =	1.00	Restricted Flow Q <sub>r for s</sub>	wm calc (L/s)=	4.00	50% reduction if s	ub-surface storage		
		100-Year Pond	ing			100-Y	ear +20% Po	onding
T c Variable	i <sub>100yr</sub>	Peak Flow Q p = 2.78xCi 100vr A	Q,	Q <sub>p</sub> -Q <sub>r</sub>	Volume 100yr	100YRQ <sub>p</sub> 20%	Qp - Qr	Volume 100+20
(min)	(mm/hour)	(L/s)	(L/s)	(L/s)	(m³)	(L/s)	(L/s)	(m³)
105	36.50	19.28	4.00	15.28	96.25			
110	35.20	18.59	4.00	14.59	96.32			
115	34.01	17.96	4.00	13.96	96.33	21.55	17.55	121.12
120	32.89	17.38	4.00	13.38	96.30			
125	31.86	16.83	4.00	12.83	96.22			

	s	torage (m3)				100+20	
Overflow	Required	Surface	Sub-surface	Balance	Overflow	Required	Balance
0.00	96.33	106.88	0	0.00	0.00	121.12	14.25
					convert to flow	with peak Tc (L/s)	2.06
			overflows to:				

100+20				St	orage (m <sup>3</sup> )		
N	Required 121.12	Balance 14.25	Overflow 0.00	Required 28.02	Surface 106.88	Sub-surface	Balance 0.00
o flov	with peak Tc (L/s)	2.06	0.00	20.02	100.00	U	
						overflows to:	0.00

ROOF C

i<sub>2yr</sub>

ROOF B

i<sub>2yr</sub>

ROOF A

i<sub>2yr</sub>

Drainage Area

T <sub>c</sub> Variable

Drainage Area

T c Variable

Drainage Area

ea (Ha)

Drainage Area	ROOF C							
Area (Ha)		Restricted Flow ICD Ac		2.00				
C =	1.00	Restricted Flow Q <sub>r for so</sub>	wm calc (L/s)=	2.00	50% reduction if su	ub-surface storage		
		100-Year Pondi	ing			100-Y	ear +20% Pc	onding
T c Variable (min)	i <sub>100yr</sub> (mm/hour)	Peak Flow Q <sub>D</sub> =2.78xCi <sub>100vr</sub> A (L/s)	Q , (L/s)	Q <sub>p</sub> -Q <sub>r</sub> (L/s)	Volume 100yr (m³)	100YRQ , 20% (L/s)	Qp - Qr (L/s)	Volume 100+20 (m <sup>3</sup> )
40	75.15	8.36	2.00	6.36	15.25	(2.0)	(2.0)	· , ,
45	69.05	7.68	2.00	5.68	15.33			
50	63.95	7.11	2.00	5.11	15.34	8.53	6.53	19.60
55	59.62	6.63	2.00	4.63	15.28			
60	55 89	6.22	2 00	4 22	15 18			

-	33.03	0.22	2.00	4.22	13.10			
		St	orage (m3)				100+20	
	Overflow	Required	Surface	Sub-surface	Balance	Overflow	Required	Balance
	0.00	15.34	22.50	0	0.00	0.00	19.60	0.00
						convert to flow	w with peak Tc (L/s)	0.00
				overflows to:				

Storage (m³)												
21	50.48	5.05	2.00	3.05	3.85							
20	52.03	5.21	2.00	3.21	3.85							
19	53.70	5.37	2.00	3.37	3.85							
18	55.49	5.55	2.00	3.55	3.84							

2-Year Ponding
Peak Flow
Q = 2.78xCi 2vr A

Q,

Drainage Area	CB108	TCB01, TCB02, TCB	03, TCB04, TC	B05, ECB06	_			
Area (Ha)	0.220	Restricted Flow ICD ,	cted Flow ICD Actual (L/s)=					
C =	0.75	Restricted Flow Q <sub>r for</sub>	<sub>swm calc</sub> (L/s)=	3.00	50% reduction if so	ub-surface storage		
		100-Year Pond	ling			100-Y	ear +20% Pc	nding
T <sub>c</sub> Variable (min)	i <sub>100yr</sub> (mm/hour)	Peak Flow Q <sub>p</sub> = 2.78xCi <sub>100yr</sub> A (L/s)	Q, (L/s)	Q <sub>p</sub> -Q <sub>r</sub> (L/s)	Volume 100yr (m³)	100YRQ <sub>p</sub> 20% (L/s)	Qp - Qr (L/s)	Volume 100+20 (m <sup>3</sup> )
120	32.89	15.09	3.00	12.09	87.04	(L/3)	(123)	( )
125	31.86	14.62	3.00	11.62	87.11			
130	30.90	14.17	3.00	11.17	87.15	17.01	14.01	109.26
135	30.00	13.76	3.00	10.76	87.15			
140	29.15	13.37	3.00	10.37	87.12			

30.00	13.76	3.00	10.76	87.15				48	28.88
29.15	13.37	3.00	10.37	87.12				49	28.45
	S	torage (m3)				100+20			
Overflow	Required	Surface	Sub-surface	Balance	Overflow	Required	Balance	=	Overflo
0.00	87.15	7.77	87.18	0.00	0.00	109.26	14.31		0.00
					convert to flow	with peak Tc (L/s)	1.83		
			overflows to:	CBMH104					

Drainage Area	CB108				
Area (Ha)	0.220				
C =	0.60	Restricted Flow Q <sub>r</sub> (L	/s)=	3.00	1
		2-Year Ponding	3		
T <sub>c</sub> Variable	i <sub>2yr</sub>	Peak Flow Q <sub>p</sub> =2.78xCi <sub>2yr</sub> A	Q,	$Q_p$ - $Q_r$	Volume 2yr
(min)	(mm/hour)	(L/s)	(L/s)	(L/s)	(m³)
45	30.24	11.10	3.00	8.10	21.86
46	29.77	10.92	3.00	7.92	21.87
47	29.32	10.76	3.00	7.76	21.88
48	28.88	10.60	3.00	7.60	21.88
49	28.45	10.44	3.00	7.44	21.88

Required 21.88

Sub-surface 87.18 Balance 0.00 123.75



ARCADIS PROFESSIONAL SERVICES (CANADA) INC. 500-333 Preston Street
Ottawa. Ontario K1S 5N4 Canada arcadis.com

STORMWATER MANAGEMENT
8201 Campeau Drive | 8201 Campeau Drive Inc.
30282806-6.0 | Rev #1 | 2025-07-18
Prepared By: MAP | Checked By: SEL

Drainage Area	CBMH104	CB106, CB105, CBN	1H104					
Area (Ha)	0.218	Restricted Flow ICD A	uctual (L/s)=	10.00				
C =	0.81	Restricted Flow Q <sub>r for s</sub>	swm calc (L/s)=	5.00	ub-surface storage			
	100-Year Ponding						ear +20% Pc	nding
T c Variable	i <sub>100yr</sub>	Peak Flow Q <sub>D</sub> =2.78xCi <sub>100vr</sub> A	Q,	Q <sub>p</sub> -Q <sub>r</sub>	Volume 100yr	100YRQ <sub>p</sub> 20%	Qp - Qr	Volume 100+20
(min)	(mm/hour)	(L/s)	(L/s)	(L/s)	(m³)	(L/s)	(L/s)	(m³)
75	47.26	23.28	5.00	18.28	82.26			
80	44.99	22.16	5.00	17.16	82.39			
85	42.95	21.16	5.00	16.16	82.42	25.39	20.39	104.00
90	41.11	20.25	5.00	15.25	82.36			
95	39.43	19.43	5.00	14.43	82.23			

Area (na)	0.218				
C =	0.65	Restricted Flow Q <sub>r</sub> (L	/s)=	5.00	
		2-Year Pondin	g		
T c Variable	i <sub>2yr</sub>	Peak Flow Q <sub>p</sub> =2.78xCi <sub>2vr</sub> A	Q,	Q <sub>p</sub> -Q,	Volume 2yr
(min)	(mm/hour)	(L/s)	(L/s)	(L/s)	(m³)
28	41.93	16.52	5.00	11.52	19.36
29	40.96	16.14	5.00	11.14	19.39
30	40.04	15.78	5.00	10.78	19.41
31	39.17	15.44	5.00	10.44	19.41
32	38.34	15.11	5.00	10.11	19.41

Drainage Area CBMH104

Drainage Area CICB100B

	S	torage (m3)				100+20		
Overflow	Required	Surface	Sub-surface	Balance	Overflow	Required	Balance	
0.00	82.42	38.46	55.96	0.00	0.00	104.00	9.58	
					convert to flow	with peak Tc (L/s)	1.88	
			overflows to: 4	CICRANOR				

		31	orage (III )			
Ī	Overflow	Required	Surface	Sub-surface	Balance	
	0.00	19.41	122.68	55.96	0.00	
				overflows to: (	CICB100B	

Drainage Area	CICB100B	CICB100A, CICB100	)B		_			
Area (Ha)	0.110	Restricted Flow ICD ,	Actual (L/s)=	20.00				
C =	0.86	Restricted Flow Q <sub>r for</sub>	swm calc (L/s)=	10.00	50% reduction if s	ub-surface storage		
		100-Year Pond	ling			100-Y	ear +20% Po	onding
T <sub>c</sub> Variable	i <sub>100yr</sub>	Peak Flow Q <sub>D</sub> =2.78xCi <sub>100vr</sub> A	Q,	Q <sub>p</sub> -Q,	Volume 100yr	100YRQ <sub>p</sub> 20%	Qp - Qr	Volume 100+20
(min)	(mm/hour)	(L/s)	(L/s)	(L/s)	(m³)	(L/s)	(L/s)	(m³)
15	142.89	37.71	10.00	27.71	24.94			
20	119.95	31.65	10.00	21.65	25.99			
25	103.85	27.40	10.00	17.40	26.11	32.89	22.89	34.33
30	91.87	24.24	10.00	14.24	25.64			
35	82.58	21.79	10.00	11.79	24.76			

Area (Ha)	0.110	)			
C =	0.69	Restricted Flow Q <sub>r</sub> (L	/s)=	10.00	
		2-Year Ponding	g		
T <sub>c</sub> Variable	i <sub>2yr</sub>	Peak Flow Q <sub>p</sub> =2.78xCi <sub>2vr</sub> A	Q,	Q <sub>p</sub> -Q <sub>r</sub>	Volume 2yr
(min)	(mm/hour)	(L/s)	(L/s)	(L/s)	(m³)
6	96.64	20.40	10.00	10.40	3.74
7	90.66	19.14	10.00	9.14	3.84
8	85.46	18.04	10.00	8.04	3.86
9	80.87	17.07	10.00	7.07	3.82
10	76.81	16.21	10.00	6.21	3.73

	s	torage (m3)				100+20	
Overflow	Required	Surface	Sub-surface	Balance	Overflow	Required	Balance
0.00	26.11	8.95	27.57	0.00	0.00	34.33	0.00
					convert to flow	with peak Tc (L/s)	0.00
			overflows to:	CICB100A			

Storage (m <sup>3</sup> )									
Overflow	Required	Surface	Sub-surface	Balance					
0.00	3.86	61.91	27.57	0.00					
			overflows to: (	CICB100A					

Drainage Area	CB99	CB97, CB98, CB99			_				
Area (Ha)	0.149	Restricted Flow ICD A	ctual (L/s)=	20.00					
C =	1.00	Restricted Flow Q <sub>r for s</sub>	wm calc (L/s)=	10.00	50% reduction if s	ub-surface storage			
		100-Year Pond	ing					+20% Ponding	
T <sub>c</sub> Variable	i <sub>100yr</sub>	Peak Flow Q <sub>p</sub> =2.78xCi <sub>100yr</sub> A	Q,	Q <sub>p</sub> -Q,	Volume 100yr	100YRQ <sub>p</sub> 20%	Qp - Qr	Volume 100+20	
(min)	(mm/hour)	(L/s)	(L/s)	(L/s)	(m³)	(L/s)	(L/s)	(m³)	
25	103.85	43.08	10.00	33.08	49.62				
30	91.87	38.11	10.00	28.11	50.60				
35	82.58	34.26	10.00	24.26	50.94	41.11	31.11	65.33	
40	75.15	31.17	10.00	21.17	50.82				
45	69.05	28.65	10.00	18.65	50.34				

Drainage Area	CB99	Ì			
Area (Ha)	0.149				
C =	0.80	Restricted Flow Q <sub>r</sub> (L	/s)=	10.00	
		2-Year Pondin	g		
T <sub>c</sub> Variable	i <sub>2yr</sub>	Peak Flow Q <sub>p</sub> =2.78xCi <sub>2yr</sub> A	Q,	Q <sub>p</sub> -Q <sub>r</sub>	Volume 2yr
(min)	(mm/hour)	(L/s)	(L/s)	(L/s)	(m³)
11	73.17	24.28	10.00	14.28	9.43
12	69.89	23.20	10.00	13.20	9.50
13	66.93	22.21	10.00	12.21	9.53
14	64.23	21.32	10.00	11.32	9.51
15	61.77	20.50	10.00	10.50	9.45

	s	torage (m3)				100+20		
Overflow	Required	Surface	Sub-surface	Balance	Overflow	Required	Balance	
0.00	50.94	3.77	47.66	0.00	0.00	65.33	13.90	
						N	0.00	

Storage (m <sup>3</sup> )				
Overflow	Required	Surface	Sub-surface	Balance
0.00	9.53	83.94	47.66	0.00

	convert to flow with peak Tc (L/s)	6.62		
aggart Commons			verflows to: 7	Taggart Commo

	Stormwater Management Summary Table					
Drainage Area	ICD Restricted Flow (L/s)	100 Year Storage Required (m3)	2 Yr Storage Required (m3)	Storage Provided		
ROOF A	4.00	96.33	28.02	106.88		
ROOF B	4.00	96.33	28.02	106.88		
ROOF C	2.00	15.34	3.85	22.50		
CB108	6.00	87.15	21.88	94.95		
CBMH104	10.00	82.42	19.41	94.42		
CICB100B	20.00	26.11	3.86	36.52		
CB99	20.00	50.94	9.53	51.43		
TOTAL	66.00	454.62	114.55	513.57		

5-yr Max Allowable: 67.43 L/s 100-yr Overflow: 100-yr Total Release Rate: 0.00 L/s 66.00 L/s

# 8201 CAMPEAU DRIVE RUNOFF COEFFICIENT CALCULATION SHEET

#### RESTRICTED

#### la (

#### GROUPED DRAINAGE AREAS

На

0.22

0.11

ROOF A1	Area (m²)	С	
Softscape	0.00	0.20	
Hardscape	1414.26	0.90	
Total	1414.26	0.90	0.14

ROOF A2	Area (m²)	С	
Softscape	0.00	0.20	
Hardscape	986.47	0.90	
Total	986.47	0.90	0.10

LINK	Area (m²)	С	
Softscape	0.00	0.20	
Hardscape	385.22	0.90	
Total	385.22	0.90	0.04

ROOF B1	Area (m²)	С	
Softscape	0.00	0.20	
Hardscape	960.53	0.90	
Total	960.53	0.90	0.10

ROOF B2	Area (m²)	С	
Softscape	0.00	0.20	
Hardscape	878.19	0.90	
Total	878.19	0.90	0.09

CICB100A	Area (m²)	С	
Softscape	82.97	0.20	
Hardscape	142.75	0.90	
Total	225.72	0.64	0.02

CICB100B	Area (m²)	С	
Softscape	249.40	0.20	
Hardscape	625.47	0.90	
Total	874.87	0.70	0.09

CBMH104	Area (m²)	С	
Softscape	155.31	0.20	
Hardscape	358.90	0.90	
Total	514.21	0.69	0

CB106	Area (m²)	С	
Softscape	438.95	0.20	
Hardscape	497.60	0.90	
Total	936.55	0.57	0.09

CBMH104	Area (m²)	С
CB106	936.6	0.57
CB105	730.2	0.72
CBMH104	514.2	0.69
Total	2181.0	0.65

 CICB100B
 Area (m²)
 C

 CICB100A
 225.7
 0.64

 CICB100B
 874.9
 0.70

 Total
 1100.6
 **0.69**

CB99	Area (m²)	С
CB97	769.4	0.83
CB98	241.4	0.77
CB99	481.5	0.76
Total	1492.3	0.80

Total area ( $m^2$ ) = 12424.67 Total area (ha) = 1.24 0.15

	3		
CB105	Area (m²)	С	
Softscape	190.53	0.20	
Hardscape	539.67	0.90	
Total	730.20	0.72	

CB108	Area (m²)	С	
Softscape	928.89	0.20	
Hardscape	1242.64	0.90	
Total	2171.53	0.60	0.22

UNC1	Area (m²)	С	
Softscape	268.69	0.20	
Hardscape	585.95	0.90	
Total	854.64	0.68	0.09

CB97	Area (m²)	С	
Softscape	72.33	0.20	
Hardscape	697.05	0.90	
Total	769.38	0.83	0.08

CB98	Area (m²)	С	
Softscape	44.72	0.20	
Hardscape	196.71	0.90	
Total	241.43	0.77	0.02

CB99	Area (m²)	С	
Softscape	97.21	0.20	
Hardscape	384.26	0.90	
Total	481.47	0.76	0.05

# SUMMARY OF INFILTRATION GALLERY CALCULATIONS AVERAGE SILTY CLAY PERCOLATION RATE

annual precipitation (mm) 920 60% available runoff (mm) 552

area (ha) 1.24

		,														
									on Gallery Ove	erflow (%)	Ove	flow Volume	(m <sup>3</sup> )	Infiltr	ation Volume	e (m³)
	Available l	Runoff	Gallery	Width	Length	Area	Depth									
Building ID	Area (m²) Volume (m	า <sup>3</sup> )	ID	(m)	(m)	(m2)	(m)	WET YEAR	DRY YEAR	<b>AVERAGE</b>	WET YEAR	DRY YEAR	<b>AVERAGE</b>	WET YEAR	DRY YEAR	AVERAGE
Roof	2200	1214	1	1 4	1 34.4	137.6	0.81	5.00%	31.02%	18.01%	61	377	7 219	1154	838	996
TOTAL		1214											219			996

AVERAGE INFILTRATION RATE 80.30 REQUIRED INFILTRATION RATE 70

5.00%

### INFILTRATION GALLERY SIZING CALCULATION

WET YEAR CALCULATION

PRECIPITATION DATA APRIL 1 TO OCTOBER 31 (WET YEAR)
TOT PRECIP DEPTH 800.4 mm
TOTAL PRECIP VOLUME 1056 m3

Structure 2200 m<sup>2</sup>
Effective Runoff 0.6 %
Percolation 0.3495 (m/day, avg silty clay)
INFILTRATION GALLERY SIZING 4 m 34.4 m DEVELOPMENT AREA 1.24 ha Width

Length depth Number Cells 0.81 m OVERFLOW VOL 53 m3/year RUNOFF VOLUME OVERFLOW

0.38 void ratio 42.35328 TOTAL DRYCELL VOL

DATE	RAINFALL	RAINFALL INTENSITY (AVG)	RAINWATER	VOLUME INFLOW TO DRYCELL	VOLUME IN DRY CELL	VOLUMI PASSIN CELL	G DRY FF		INFILTRATION FROM SIDES (BOTTOM 1/3)	BALANCE IN	
	[MM]	[MM/HR]	[M <sup>3</sup> ]	[M <sup>3</sup> ]	[M <sup>3</sup> ]	[M <sup>2</sup>	<sup>3</sup> 1	[M <sup>3</sup> ]	[M <sup>3</sup> ]	[M <sup>3</sup> ]	
01-Ap	or 0.2	0.008	0		0	0	0	0	(	)	0
02-Ap 03-Ap					1 0	1 0	0 0	1	(		0 0
04-Ap 05-Ap					0	0	0 0	0		) )	0
06-Ap	or 7.8	0.325	10	1		10	0	10	(	)	0
07-Ap					4 6	4 6	0 0	4		) )	0
09-Ap	or 4.2	0.175	6		6	6	0	6	(	)	0
10-Ap					0 0	0	0 0	0		) )	0
12-Ap	or C	0.000	0		0	0	0	0	(	)	0
13-Ap 14-Ap					0 0	0	0 0	0			0
15-Ap					0	0	0 0	0		) )	0
17-Ap	or C	0.000	0		0	0	0	0	(	)	0
18-Ap					0 0	0	0 0	0		) )	0
20-Ap	or 8.2	0.342	11	1	1	11	0	11	(	)	0
21-Ap 22-Ap					4 0	4 0	0 0	4			0
23-Ap 24-Ap					0 0	0	0 0	0			0
25-Ap	or C	0.000	0		0	0	0	0	(	)	0
26-Ap 27-Ap					0 0	0	0 0	0		) )	0
28-Ap	or C	0.000	0		0	0	0	0	(	)	0
29-Ap 30-Ap	or C	0.000	0		0 0	0	0 0	0	(	)	0
01-Ma 02-Ma					2 0	12 0	0 0	12 0		) )	0
03-Ma	y C	0.000	0		0	0	0	0	(	)	0
04-Ma 05-Ma					3 1	3 11	0 0	3 11	(		0
06-Ma	y 1	0.042			1	1	0	1			0
07-Ma 08-Ma	y 0.8	0.033			2 1	2 1	0 0	2 1		) )	0
09-Ma 10-Ma					0 0	0	0 0	0		) )	0
11-Ma	y C	0.000	0		0	0	0	0	(	)	0
12-Ma 13-Ma					0 0	0	0 0	0		) )	0
14-Ma 15-Ma	y C	0.000	0		0	0	0	0	(	)	0
16-Ma	y 17.4	0.725	23	2		1 23	0	23	(		0
17-Ma 18-Ma				1	0 5	0 15	0 0	0 15			0
19-Ma	y 30.2	1.258	40	4	0 4	10	0	40	(	)	0
20-Ma 21-Ma	y 5.9	0.246		3	9 ; 8	39 8	0 0	39 8			0
22-Ma 23-Ma	y 26.9	1.121	36	3	6	36 15	0 0	36 15	(		0
24-Ma	y 0.4	0.017	1		1	1	0	1	(	)	0
25-Ma 26-Ma					0 0	0	0 0	0			0
27-Ma	y 7.8	0.325	10	1	0	10	0	10	(	)	0
28-Ma 29-Ma	y C	0.000			0 0	0	0 0	0			0
30-Ma 31-Ma					0 0	0	0 0	0			0
01-Ju	n 10.6	0.442	14	1	4	14	0	14	(	)	0
02-Ju 03-Ju					0 0	0	0 0	0			0
04-Ju 05-Ju					0 2	0 2	0 0	0 2			0
06-Ju	n (	0.000	0		0	0	0	0	(	)	0
07-Ju 08-Ju		0.208 0.008			7 0	7 0	0 0	7 0			0
09-Ju	n (	0.000	0		0	0	0	0	(	)	0
10-Ju 11-Ju	n 4.8	0.200	6		0 6	0 6	0 0	0 6	(	)	0
12-Ju 13-Ju				3	5 ; 1	35 1	0 0	35 1			0
14-Ju	n (	0.000	0		0	0	0	0	(	)	0
15-Ju 16-Ju					0 7	0 7	0 0	0 7			0
17-Ju 18-Ju					0 0	0	0 0	0		)	0
19-Ju	n 4	0.167	5		5	5	0	5	(	)	0
20-Ju 21-Ju					0 0	0	0 0	0			0
22-Ju 23-Ju	n C	0.000	0		0	0	0	0	(	)	0
24-Ju	n 27.2	1.133	36	3	6 :	36	0	36	(	)	0
25-Ju 26-Ju		_			0 0	0	0 0	0			0
27-Ju	n 29	1.208	38	3	8 ;	38	0	38	(	)	0
28-Ju 29-Ju	n 0.2	0.008	0		0 0	0	0 0	0		) )	0
30-Ju 01-Ju	n (	0.000	0		0 0	0	0 0	0	(	) )	0 0
02-Ju	ıl 10	0.417	13	1	3	13	0	13	(	)	0
03-Ju				2	0 2	20 10	0 0	20 10	(		0
05-Ju	ıl 14.8	0.617	20	2		20 0	0	20	(	)	0
07-Ju					0	0	0	0		)	0

08-Jul	0	0.000	0	0	0	0	0	0	0
09-Jul	0	0.000	0	0	0	0	0	0	0
10-Jul 11-Jul	0	0.000 0.000	0	0	0 0	0 0	0	0	0
12-Jul	0	0.000	0	0	0	0	0	0	0
13-Jul 14-Jul	10.6 0.4	0.442 0.017	14 1	14 1	14 1	0 0	14 1	0	0 0
15-Jul	0	0.000	0	0	0	0	0	0	0
16-Jul 17-Jul	0	0.000 0.000	0 0	0 0	0 0	0 0	0	0 0	0
18-Jul		0.000	0	0	0	0	0	0	0
19-Jul 20-Jul		0.000 0.258	0 8	0 8	0 8	0 0	0 8	0 0	0
21-Jul 22-Jul	0	0.000 0.000	0	0 0	0	0	0	0 0	0
23-Jul	0	0.000	0	0	0	0	0	0	0
24-Jul 25-Jul	3.6	0.000 0.150	0 5	0 5	0 5	0 0	0 5	0 0	0
26-Jul	31.6	1.317	42	42	42	0	42	0	0
27-Jul 28-Jul	0	0.000 0.000	0	0	0	0 0	0	0	0
29-Jul	42.4	1.767	56	42	42	14	42	0	0
30-Jul 31-Jul	2.4	0.100 0.000	3 0	3 0	3 0	0 0	3 0	0	0
01-Aug 02-Aug		0.025	1	1	1	0	1	0	0
02-Aug 03-Aug		0.450 0.000	14 0	14 0	14 0	0 0	14 0	0 0	0
04-Aug 05-Aug		0.000 0.017	0 1	0	0 1	0	0	0 0	0
06-Aug	4	0.167	5	1 5	5	0	5	0	0
07-Aug 08-Aug		0.050 0.117	2 4	2 4	2 4	0 0	2 4	0	0
09-Aug	11	0.458	15	15	15	0	15	0	0
10-Aug 11-Aug		0.000 0.000	0	0 0	0 0	0 0	0	0	0
12-Aug	0	0.000	0	0	0	0	0	0	0
13-Aug 14-Aug		0.000 0.000	0 0	0 0	0 0	0	0 0	0 0	0
15-Aug	2	0.083	3	3	3	0	3	0	0
16-Aug 17-Aug	0	0.000 0.000	0 0	0 0	0 0	0 0	0 0	0 0	0
18-Aug 19-Aug	14.2	0.592 0.000	19 0	19 0	19 0	0	19 0	0	0
20-Aug	0	0.000	0	0	0	0	0	0	0
21-Aug 22-Aug		0.650 0.000	21 0	21 0	21 0	0 0	21 0	0	0
23-Aug	6.6	0.275	9	9	9	0	9	0	0
24-Aug 25-Aug		0.033 0.000	1 0	1 0	1	0 0	1	0	0
26-Aug	3.8	0.158	5	5	5	0	5	0	0
27-Aug 28-Aug		1.008 0.033	32 1	32 1	32 1	0 0	32 1	0 0	0
29-Aug 30-Aug	0	0.000 0.000	0	0 0	0	0	0	0	0
31-Aug	0	0.000	0	0	0	0	0	0	0
01-Sep 02-Sep		0.000 0.017	0 1	0 1	0	0 0	0 1	0 0	0
03-Sep	] 0	0.000	0	0	0	0	0	0	0
04-Sep 05-Sep	1.9 5.8	0.079 0.242	3 8	3 8	3 8	0 0	3 8	0	0
06-Sep	0	0.000	0	0	0	0	0	0	0
07-Sep 08-Sep		0.000 0.000	0	0	0	0 0	0	0	0
09-Sep	0	0.000	0	0	0	0	0	0	0
10-Sep 11-Sep		0.267 2.575	8 82	8 42	8 42	0 39	8 42	0 0	0
12-Sep 13-Sep	20.6 5.8	0.858 0.242	27 8	27 8	27 8	0 0	27 8	0 0	0
14-Sep	0	0.000	0	0	0	0	0	0	0
15-Sep 16-Sep	8.1 2.3	0.338 0.096	11 3	11 3	11 3	0 0	11 3	0	0
17-Sep	0	0.000	0	0	0	0	0	0	0
18-Sep 19-Sep		0.000 0.000	0 0	0	0 0	0 0	0	0	0
20-Sep	0.8	0.033	1	1	1	0	1	0	0
21-Sep 22-Sep	0 0	0.000 0.000	0 0	0 0	0 0	0	0 0	0 0	0
23-Sep 24-Sep		0.542 0.000	17 0	17 0	17 0	0	17 0	0 0	0
25-Sep	0	0.000	0	0	0	0	0	0	0
26-Sep 27-Sep	0 0	0.000 0.000	0 0	0 0	0 0	0 0	0 0	0 0	0
28-Sep	1.3	0.054	2	2	2	0	2	0	0
29-Sep 30-Sep	25.2	0.588 1.050	19 33	19 33	19 33	0	19 33	0 0	0
01-Oct 02-Oct	] 0	0.000 0.017	0	0	0	0	0	0	0
03-Oct	7.8	0.325	10	10	10	0	10	0	0
04-Oct 05-Oct		0.325 0.250	10 8	10 8	10 8	0	10 8	0 0	0
06-Oct	0.4	0.017	1	1	1	0	1	0	0
07-Oct 08-Oct	0 1	0.000 0.042	0 1	0 1	0 1	0 0	0 1	0 0	0
09-Oct	1.2	0.050	2	2	2	0	2	0	0
10-Oct 11-Oct	0	0.000 0.000	0 0	0 0	0 0	0	0 0	0 0	0
12-Oct 13-Oct	] 0	0.000 0.433	0 14	0 14	0 14	0	0 14	0	0
14-Oct	9	0.375	12	12	12	0	12	0	0
15-Oct 16-Oct	] 0	0.000 0.008	0 0	0 0	0 0	0 0	0 0	0 0	0
17-Oct	1.6	0.067	2	2	2	0	2	0	0
18-Oct 19-Oct		0.000 0.000	0 0	0 0	0 0	0 0	0 0	0	0
20-Oct	0	0.000	0	0	0	0	0	0	0
21-Oct 22-Oct		0.242 0.000	8 0	8 0	8 0	0	8 0	0 0	0 0
23-Oct	] 1	0.042	1	1	1	0	1	0	0
24-Oct 25-Oct	0	0.000 0.000	0 0	0 0	0 0	0 0	0 0	0 0	0
26-Oct 27-Oct	1.3	0.054 0.454	2 14	2 14	2 14	0	2 14	0 0	0
28-Oct	] 0	0.000	0	0	0	0	0	0	0
29-Oct 30-Oct		0.542 0.000	17 0	17 0	17 0	0 0	17 0	0 0	0
31-Oct		0.000	0	0	0	0	0	0	0

#### INFILTRATION GALLERY SIZING CALCULATION

DRY YEAR CALCULATION

PRECIPITATION DATA APRIL 1 TO OCTOBER 31 (DRY YEAR)
TOT PRECIP DEPTH 405.1 mm
TOTAL PRECIP VOLUME 535 m3

Roof 2200 m<sup>2</sup>
Effective Runoff 0.6 %
Percolation 0.3495 (m/day, avg silty clay)
INFILTRATION GALLERY SIZING 4 m 34.4 m Width

0.15 m

OVERFLOW VOL 166 m3/year

1.24 ha

DEVELOPMENT AREA

Length depth Number Cells 0.38 RUNOFF VOLUME OVERFLOW void ratio 31.02%

7.8432 TOTAL DRYCELL VOL

DATE	RAINFALL	RAINFALL INTENSITY (AVG)	RAINWATER AVAILABLE	VOLUME INFLOW TO DRYCELL	VOLUME IN DRY CELL		VOLUME INFILT PASSING DRY FROM CELL BOTTO	FI	NFILTRATION ROM SIDES BALA BOTTOM 1/3) DRY	
	[MM]	[MM/HR]	[M <sup>3</sup> ]	[M <sup>3</sup> ]	$[M^3]$			M <sup>3</sup> ]	[M <sup>3</sup> ]	[M <sup>3</sup> ]
	01-Apr 02-Apr	0.000 0 0.000			0	0	0 0	0 0	0 0	0
	03-Apr	0.000	) (	)	0	0	0	0	0	0
	04-Apr 05-Apr	0.625 0 0.000			8 0	8 0	12 0	8 0	0 0	0
	06-Apr	0.000 0.3 0.013			0	0	0 0	0 0	0	0
	08-Apr	0.000	) C	)	0	0	0	0	0	0
	09-Apr 10-Apr	0.000			0	0	0 0	0 0	0 0	0
	11-Apr	0.000	) C	)	0	0	0	0	0	0
-	12-Apr 13-Apr 1	1 0.042 .6 0.067			1 2	1 2	0 0	1 2	0 0	0
	14-Apr 5	0.246	; 8	3	8	8	0	8	0	0
	15-Apr 2 16-Apr	0.096			3	3 0	0 0	3 0	0 0	0
	17-Apr 18-Apr	0.000			0	0	0 0	0 0	0	0
	19-Apr	0.000	) (	)	0	0	0	0	0	0
	20-Apr 21-Apr	0.000			0	0	0	0 0	0	0
	22-Apr 6	0.288	9	)	8	8	1	8	0	0
		8 0.200 0.3 0.013			6 0	6 0	0 0	6 0	0 0	0
	25-Apr 26-Apr	0.000	) (		0	0	0 0	0 0	0	0
	27-Apr	0.000	) (	)	0	0	0	0	0	0
	28-Apr 10	0.000 0.8 0.450			0 8	0 8	0 6	0 8	0	0
	30-Apr 1	.6 0.067	' 2	2	2	2	0	2	0	0
	01-May 3 02-May	0.158 0 0.000	) (	)	5 0	5 0	0 0	5 0	0	0
	03-May 11 04-May		15	<b>i</b>	8	8	7 0	8	0	0
	05-May	0.000	) C	)	0	0	0	0	0	0
	06-May 4 07-May	0.171 3 0.125			5 4	5 4	0 0	5 4	0 0	0
	08-May	0.000	) C	)	0	0	0	0	0	0
	09-May 23 10-May 0	0.975 0.5 0.021			8 1	8 1	23 0	8 1	0 0	0
	11-May 12-May 22	0.000			0	0 8	0 22	0 8	0	0
	13-May	0.000	) C	)	0	0	0	0	0	0
	14-May 2	0.000 0.3 0.096			0	0 3	0 0	0 3	0 0	0
	16-May C	0.013	S C	)	0	0	0	0	0	0
	17-May 18-May	0.000			0	0	0 0	0 0	0 0	0
	19-May 20-May	0.000	) C	)	0	0	0 0	0 0	0	0
	21-May	0.000	) (	)	0	0	0	0	0	0
		0.350 10 0.417			8	8 8	3 5	8 8	0 0	0
	24-May 3	0.142	! 4	ļ	4	4	0	4	0	0
		.9 0.258 .9 0.079			8	8 3	0 0	8 3	0 0	0
	27-May C	0.013 0.054			0 2	0 2	0 0	0 2	0	0
	29-May 1	.1 0.046	; 1		1	1	0	1	0	0
	30-May 31-May 10	0.000 0.9 0.454			0 8	0 8	0 7	0 8	0	0
	01-Jun	0.000	) (	)	0	0	0	0	0	0
	03-Jun	0.021 0 0.000	) (	)	0	1 0	0 0	1 0	0 0	0
	04-Jun 05-Jun	0.000			0	0	0 0	0 0	0	0
	06-Jun	0.000	) (	)	0	0	0	0	0	0
	07-Jun 08-Jun	0.000			0	0	0 0	0 0	0 0	0
	09-Jun 10-Jun	0.000	) (		0	0 0	0 0	0 0	0	0
	11-Jun	0.000	) C	)	0	0	0	0	0	0
	12-Jun 0 13-Jun 12	0.013 0.508			0	0 8	0 8	0 8	0 0	0
	14-Jun C	0.013	C	)	0	0	0	0	0	0
	16-Jun 11		! 16	3	2 8	2 8	0 8	2 8	0 0	0
		0.267 0.8 0.033			8	8 1	1 0	8 1	0	0
	19-Jun	0.000	) C	)	0	0	0	0	0	0
-	20-Jun 5 21-Jun 3	0.217 0.2 0.133			7 4	7 4	0	7 4	0 0	0
	22-Jun	0.000	) (	)	0	0	0	0	0	0
		0.000 0.3 0.013	, C	)	0	0 0	0 0	0 0	0 0	0
	25-Jun 26-Jun	0.000			0	0	0 0	0 0	0	0
	27-Jun	0.000	) (	)	0	0	0	0	Ö	0
	28-Jun 29-Jun	0.000			0	0	0 0	0 0	0 0	0
	30-Jun 1	.1 0.046	; 1		1	1	0	1	0	0
	02-Jul 6	0.021 0.1 0.254		3	1 8	1 8	0 0	1 8	0 0	0
	03-Jul	0.000 3.4 0.267	) C	)	0	0 8	0 1	0 8	0	0
	05-Jul C	0.033	1		1	1	0	1	0	0
	06-Jul 07-Jul	0.000			0	0 0	0 0	0 0	0 0	0
	-	-								

08-Jul	0	0.000	0	0	0	0	0	0	0
09-Jul	6.7	0.279	9	8	8	1	8	0	0
10-Jul 11-Jul	0	0.000 0.000	0 0	0 0	0 0	0 0	0 0	0 0	0 0
12-Jul 13-Jul	0	0.000 0.000	0 0	0	0	0	0 0	0 0	0 0
14-Jul	0	0.000	0	0	0	0	0	0	0
15-Jul 16-Jul	0	0.000 0.000	0 0	0 0	0 0	0 0	0 0	0 0	0 0
17-Jul 18-Jul		0.000 0.871	0 28	0 8	0 8	0 20	0 8	0	0
19-Jul	11.5	0.479	15	8	8	7	8	0	0
20-Jul 21-Jul	0	0.000 0.000	0 0	0	0	0	0	0	0
22-Jul	0	0.000	0	0	0	0	0	0	0
23-Jul 24-Jul	6.9 9.2	0.288 0.383	9 12	8 8	8 8	1 4	8 8	0 0	0
25-Jul 26-Jul	0.3	0.000 0.013	0 0	0	0	0	0	0 0	0
27-Jul	1.3	0.054	2	2	2	0	2	0	0
28-Jul 29-Jul	1.1	0.000 0.046	0 1	0 1	0 1	0 0	0 1	0	0
30-Jul 31-Jul		0.013 0.171	0 5	0 5	0 5	0 0	0 5	0	0
01-Aug	0	0.000	0	0	0	0	0	0	0
02-Aug 03-Aug	8.9 11.5	0.371 0.479	12 15	8 8	8 8	4 7	8 8	0	0
04-Aug	0.8	0.033	1	1	1	0	1	0	0
05-Aug 06-Aug	0	0.000 0.000	0 0	0 0	0 0	0 0	0 0	0 0	0 0
07-Aug 08-Aug	0.8	0.000 0.033	0 1	0	0 1	0 0	0 1	0	0
09-Aug	0	0.000	0	0	0	0	0	0	0
10-Aug 11-Aug	0	0.000 0.000	0 0	0	0	0 0	0	0	0
12-Aug 13-Aug	1.3	0.054 0.000	2	2	2	0 0	2	0	0
14-Aug	0	0.000	0	0	0	0	0	0	0
15-Aug 16-Aug	0	0.000 0.000	0 0	0 0	0	0	0	0	0
17-Aug	0.6	0.025	1	1	1	0	1	0	0
18-Aug 19-Aug	0 5.5	0.000 0.229	0 7	0 7	0 7	0 0	0 7	0 0	0 0
20-Aug 21-Aug	0	0.000 0.000	0 0	0	0	0	0 0	0 0	0 0
22-Aug	0	0.000	0	0	0	0	0	0	0
23-Aug 24-Aug	0.8	0.033 0.000	1 0	1 0	1 0	0 0	1 0	0 0	0
25-Aug 26-Aug	0	0.000 0.000	0 0	0	0	0 0	0	0	0
27-Aug	3.3	0.138	4	4	4	0	4	0	0
28-Aug 29-Aug	0	0.000 0.000	0 0	0	0	0	0	0	0
30-Aug	0	0.000	0	0	0	0	0	0	0
31-Aug 01-Sep	0.8	0.033 0.000	1 0	1 0	1 0	0 0	1 0	0 0	0 0
02-Sep 03-Sep	0.9 8.4	0.038 0.350	1 11	1 8	1 8	0 3	1 8	0	0
04-Sep	0	0.000	0	0	0	0	0	0	0
05-Sep 06-Sep	0	0.000 0.000	0 0	0	0	0	0	0	0
07-Sep 08-Sep	0	0.000 0.000	0	0	0	0	0	0	0
09-Sep	0.6	0.025	1	1	1	0	1	0	0
10-Sep 11-Sep	4.4 0	0.183 0.000	6 0	6 0	6 0	0	6 0	0	0
12-Sep 13-Sep	3.5 11.7	0.146 0.488	5 15	5	5	0	5	0	0
14-Sep	0	0.000	0	0	0	0	8 0	0	0
15-Sep 16-Sep	0	0.000 0.000	0 0	0	0 0	0	0	0	0
17-Sep	1.1	0.046	1	1	1	0	1	0	0
18-Sep 19-Sep	0	0.000 0.000	0 0	0 0	0 0	0 0	0 0	0	0 0
20-Sep 21-Sep	3.1 1.4	0.129 0.058	4 2	4 2	4 2	0	4 2	0 0	0
22-Sep	0.6	0.025	1	1	1	0	1	0	0
23-Sep 24-Sep	0	0.000 0.000	0 0	0	0 0	0 0	0 0	0	0
25-Sep 26-Sep	4.9 0.3	0.204 0.013	6 0	6 0	6 0	0 0	6 0	0	0
27-Sep	0	0.000	0	0	0	0	0	0	0
28-Sep 29-Sep	3.9 2.1	0.163 0.088	5 3	5 3	5 3	0 0	5 3	0 0	0 0
30-Sep 01-Oct	0	0.000	0	0	0	0	0	0	0
02-Oct	4.5	0.188	6	6	6	0	0	0	0
03-Oct 04-Oct	0	0.000 0.000	0 0	0	0 0	0	0	0	0 0
05-Oct	0	0.000	0	0	0	0	0	0	0
06-Oct 07-Oct	0 3	0.000 0.125	0 4	0 4	0 4	0 0	0 4	0 0	0
08-Oct 09-Oct	0	0.000 0.000	0 0	0	0 0	0 0	0 0	0	0 0
10-Oct	2	0.083	3	3	3	0	3	0	0
11-Oct 12-Oct	0 1.8	0.000 0.075	0 2	0 2	0 2	0 0	0 2	0 0	0 0
13-Oct 14-Oct	0 8.9	0.000 0.371	0 12	0 8	0 8	0 4	0 8	0	0
15-Oct	0	0.000	0	0	0	0	0	0	0
16-Oct 17-Oct	0 6.8	0.000 0.283	0 9	0 8	0 8	0 1	0 8	0 0	0 0
18-Oct	0	0.000	0	0	0	0	0	0	0
19-Oct 20-Oct	0	0.000 0.000	0 0	0 0	0 0	0 0	0 0	0 0	0 0
21-Oct 22-Oct	0	0.000 0.000	0	0	0	0	0	0	0
23-Oct	0	0.000	0	0	0	0	0	0	0
24-Oct 25-Oct	0 6.6	0.000 0.275	0 9	0 8	0 8	0 1	0 8	0 0	0 0
26-Oct	0	0.000	0	0	0	0	0	0	0
27-Oct 28-Oct	0	0.000 0.000	0 0	0 0	0 0	0 0	0 0	0 0	0 0
29-Oct 30-Oct	0 5.5	0.000 0.229	0 7	0 7	0 7	0 0	0 7	0 0	0 0
31-Oct	0.3	0.013	0	0	0	0	0	0	0



Project details:

Campeau

Project description : Date :

7/16/2025

Location:

Ottawa, ON


Client details:

Contact:

E-mail:


EZstorm configuration				
EZstorm application	Infiltration			
Load type	Heavy traffic			
Height	0.66 m			
Length	34.40 m			
Width	4.00 m			
EZstorm storage volume	87.18 m³			
Total storage volume	87.18 m <sup>3</sup>			

Fill materiel	
Fill materiel	3/4" clear stone
Storage in stone	No
Stone porosity	-
Stone above system	-
Perimeter stone	-
Stone below system	_
Storage in stone	



Total storage volume provided :	87.18 m <sup>3</sup>
EZstorm storage volume	87.18 m³
Storage in stone	_
Stone quantity (fill) required for this project :	67.35 m³





EZstorm m	naterial list	Qty
1970)		
	EZstorm half blocs	0
	EZstorm lateral side grid	96
9	EZstorm access chimney (frame and cover included)	0
-111	EZaccess (frame and cover included)	1
	Geotextile surface area required	782.13
	Geomembrane surface area required	0.00





Contact:


Project details: Client details:

Project description: 8201 Campeau Drive - J Way Date: 7/16/2025 Location: Ottawa, Ontario

Matt Petitpas E-mail: matt.petitpas@arcadis.com


EZstorm configuration	
EZstorm application	Retention / Detention
Load type	No traffic
Height	1.32 m
Length	13.60 m
Width	1.60 m
EZstorm storage volume	27.57 m³
Total storage volume	27.57 m³

Fill materiel	
Fill materiel	3/4" granular fill / Sand
Storage in stone	No
Stone porosity	_
Stone above system	_
Perimeter stone	_
Stone below system	_
Storage in stone	<u>-</u>



Total storage volume provided :	27.57 m <sup>3</sup>
EZstorm storage volume	27.57 m³
Storage in stone	_
Stone quantity (fill) required for this project :	16.70 m³





EZstorm material list				
***				
	EZstorm half blocs	0		
	EZstorm lateral side grid	76		
1	EZstorm access chimney (frame and cover included)	0		
	EZaccess (frame and cover included)	0		
	Geotextile surface area required	200.76		
	Geomembrane surface area required	92.01		



Project details : Client details :

Project description : Project description :


Date : 7/16/2025

Location : null, null

Contact: Matt Petitpas
E-mail: matt.petitpas@arcadis.com


<b>EZstorm configuration</b>	
EZstorm application	Retention / Detention
Load type	Light traffic
Height	0.66 m
Length	18.40 m
Width	4.80 m
EZstorm storage volume	55.96 m³
Total storage volume	55.96 m³

Fill materiel	
Fill materiel	3/4" granular fill / Sand
Storage in stone	No
Stone porosity	-
Stone above system	-
Perimeter stone	-
Stone below system	_
Storage in stone	-



Total storage volume provided :	55.96 m <sup>3</sup>
EZstorm storage volume	55.96 m³
Storage in stone	_
Stone quantity (fill) required for this project :	42.80 m³





EZstorm material list		Qty
***		
	EZstorm half blocs	0
	EZstorm lateral side grid	58
1	EZstorm access chimney (frame and cover included)	0
	EZaccess (frame and cover included)	0
	Geotextile surface area required	497.43
	Geomembrane surface area required	227.99



#### Project details:


Project descripti**8**201 Campeau Drive - Taggart Road
Date: 7/18/2025
Location: Ottawa, Ontario

#### Client details:

Contact: Matt Petitpas
E-mail: matt.petitpas@arcadis.com


EZstorm configuration	
EZstorm application	Retention / Detention
Load type	Light traffic
Height	1.01 m
Length	30.40 m
Width	1.60 m
EZstorm storage volume	47.16 m³
Total storage volume	47.16 m <sup>3</sup>

Fill materiel	
Fill materiel	3/4" granular fill / Sand
Storage in stone	No
Stone porosity	-
Stone above system	_
Perimeter stone	-
Stone below system	-
Storage in stone	_




Total storage volume provided :	47.16 m <sup>3</sup>
EZstorm storage volume	47.16 m³
Storage in stone	_
Stone quantity (fill) required for this project :	33.12 m³






EZstorm material list		Qty
NAMES A.		
	EZstorm half blocs	76
	EZstorm lateral side grid	80
	EZstorm lateral side grid (half blocs)	80
	EZstorm cover plates	76
•	EZstorm access chimney (frame and cover included)	0
	EZaccess (frame and cover included)	0
	Geotextile surface area required	388.61
	Geomembrane surface area required	178.11

# **Appendix E**



#### **GENERAL LEGEND**



#### SERVICING LEGEND

MH118A 200mmØ SAN	SANITARY MANHOLE
MH109	SANITARY SEWER
O MH118	STORM MANHOLE
825mmØ STM 900mmØ STM	STORM SEWER - LESS THAN 900Ø
COOMING CTW	STORM SEWER - 900Ø AND GREATER
200Ø WATERMAIN	WATERMAIN
■ CB100 T/G 104.10	STREET CATCHBASIN C/W TOP OF GRATE
G/G 104.25	CURB INLET CATCHBASIN C/W GUTTER GRADE
DCB100 T/G 104.10	DOUBLE CATCHBASIN C/W TOP OF GRATE
DCICB101 G/G 104.25	DOUBLE CURB INLET CATCHBASIN C/W GUTTER GRADE
■ DI101 T/G 103.59	DITCH INLET MANHOLE C/W TOP OF GRATE
CBMH101 T/G 103.59	CATCHBASIN MANHOLE C/W TOP OF GRATE
RYCB T/G 104.35	REAR YARD CATCHBASIN IN ROAD CONNECTING STRUCTURE C/W SOLID GRATE
T/G 104.35 NV 103.35	REAR YARD "TEE" CATCHBASIN (300Ø) C/W TOP OF GRATE AND INVERT OUT
OT/G 104.50 INV 103.50	REAR YARD "END" CATCHBASIN (300Ø) C/W TOP OF GRATE AND INVERT OUT
T/G 104.35 INV 103.35	REAR YARD "CUSTOM ANGLED " CATCHBASIN (450Ø) C/W TOP OF GRATE AND INVERT OUT
T/G 104.35 NV 103.35	REAR YARD "THREE WAY" CATCHBASIN (450Ø) C/W TOP OF GRATE AND INVERT OUT
	PERFORATED REAR YARD SUBDRAIN
300mmØ CSP	CSP CULVERT C/W DIAMETER
<b>⊗</b> VB	VALVE AND VALVE BOX
<b>⊗</b> V&VC	VALVE AND VALVE CHAMBER
<b>-</b>	PARK VALVE CHAMBER C/W SERVICE POST
◆ HYD 104.35	FIRE HYDRANT C/W BOTTOM OF FLANGE ELEVATION
200Ø WMRED 150Ø WM	WATERMAIN REDUCER
2 VBENDS	VERTICAL BEND LOCATION
\$	SIAMESE CONNECTION (IF REQUIRED)
M	METER (IF REQUIRED)
(RM)	REMOTE METER (IF REQUIRED)
<u> </u>	WATERMAIN IDENTIFICATION (IF REQUIRED)
⊕ ⊕	PIPE CROSSING IDENTIFICATION (IF REQUIRED)
$\triangleleft$	SINGLE SERVICE LOCATION
	DOUBLE SERVICE LOCATION
<b>~</b>	SINGLE SERVICE LOCATION (REQUIRES FOUNDATION SLEEVE)
BH 12 102.00	INFERRED REFUSAL (SEE GEOTECHNICAL REPORT)
<i>\$28462646</i> HGL	100 YEAR STORM HYDRAULIC GRADE LINE AT MANHOLE
101.79 USF	UNDERSIDE OF FOOTING ELEVATION
101.79	SUBLICIBLE OF FOOTING ELEVATION

#### NOTES:

- 1. ALL MATERIALS AND CONSTRUCTION IS TO BE IN ACCORDANCE WITH THE CURRENT CITY OF OTTAWA STANDARD DRAWINGS & SPECIFICATIONS OR OPSD/OPSS IF CITY DRAWINGS AND SPECIFICATIONS DO NOT APPLY
- 2. THE POSITION OF UNDERGROUND AND ABOVE GROUND SERVICE, UTILITIES AND STRUCTURES ARE NOT NECESSARILY SHOWN ON THE CONTRACT DRAWINGS, AND WHERE SHOWN, THE ACCURACY OF THE POSITION OF SUCH SERVICE, UTILITIES AND STRUCTURES IS NOT GUARANTEED. THE CONTRACTOR IS RESPONSIBLE FOR DETERMINING THE EXACT LOCATION, SIZE, MATERIAL AND ELEVATION OF ALL EXISTING SERVICES AND UTILITIES PRIOR TO CONSTRUCTION.
- 3. THE CONTRACTOR SHALL REPORT ALL CONFLICTS, DISCOVERIES OF ERROR AND DISCREPANCIES TO THE ENGINEER.
- 4. THE CONTRACTOR SHALL BE RESPONSIBLE TO PROTECT AND ASSUME RESPONSIBILITY FOR ALL UTILITIES WHETHER OR NOT SHOW ON THESE DRAWINGS.
- 5. THE CONTRACTOR SHALL BE RESPONSIBLE TO PROTECT ALL LANDS BEYOND THE SITE LIMITS. ANY AREAS BEYOND THE SITE LIMITS, WHICH ARE DISTURBED DURING CONSTRUCTION, SHALL BE REPAIRED AND RESTORED TO ORIGINAL CONDITION OR BETTER, TO THE SATISFACTION OF THE ADJACENT LAND OWNER, THE OWNER, THE OWNERS REPRESENTATIVES AND/OR THE AUTHORITY HAVING JURISDICTION AT THE EXPENSE OF THE CONTRACTOR.
- 6. WHERE NECESSARY, THE CONTRACTOR SHALL IMPLEMENT A TRAFFIC MANAGEMENT PLAN TO THE SATISFACTION OF THE CITY OF OTTAWA. ALL CONSTRUCTION SIGNAGE MUST CONFORM TO THE LATEST VERSION OF THE M.T.O. MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES. ALL TEMPORARY TRAFFIC CONTROL MEASURES MUST BE REMOVED UPON THE COMPLETION OF THE WORKS.
- 7. SHOULD ANY BURIED ARCHAEOLOGICAL REMAINS BE FOUND ON THE PROPERTY DURING CONSTRUCTION ACTIVITIES, THE CONTRACTOR SHALL NOTIFY THE OWNER TO CONTACT THE HERITAGE OPERATIONS UNIT OF THE ONTARIO MINISTRY OF CULTURE MUST BE NOTIFIED IMMEDIATE, AND WORK WITHIN THE AREA SHALL BE CEASED UNTIL FURTHER NOTICE.
- 8. FOR GEOTECHNICAL INFORMATION REFER TO GEOTECHNICAL REPORT PG6934-1 PREPARED BY PATERSON

ACCESS LANES AND HEAVY LOADING AREA: (540mm)
40mm - SUPERPAVE 12.5 ASPHALTIC CONCRETE
50mm - SUPERPAVE 19.0 ASPHALTIC CONCRETE
150mm - OPSS GRANULAR "A" CRUSHED STONE
300mm - OPSS GRANULAR "B" TYPE II

 FOR GEODETIC BENCHMARK AND GEOMETRIC LAYOUT OF STREET AND LOTS, REFER TO TOPOGRAPHICAL SURVEY AND PLAN OF SUBDIVISION PREPARED BY FARLEY, SMITH & DENIS SURVEYING Ltd. BENCHMARK BASED ON CAN--NET VIRTUAL REFERENCE SYSTEM NETWORK.

10. FOR SITE PLAN INFORMATION, REFER TO SITE PLAN PREPARED BY ARCADIS

11. THESE DRAWINGS ARE NOT TO BE SCALED OR USED FOR LAYOUT PURPOSES

- 12. ROADWAY SECTIONS REQUIRING GRADE RAISE TO PROPOSED SUB GRADE LEVEL TO BE FILLED WITH ACCEPTABLE NATIVE EARTH BORROW OR IMPORTED OPSS SELECTED SUBGRADE MATERIAL IF NATIVE MATERIAL IS DEFICIENT AS PER RECOMMENDATION OF GEOTECHNICAL ENGINEER.
- 13. IN AREAS WHERE EXISTING GROUND IS BELOW THE PROPOSED ELEVATION OF SEWER AND WATERMAINS, GRADE RAISING AND FILLING IS TO BE IN ACCORDANCE WITH THE RECOMMENDATIONS OF THE GEOTECHNICAL REPORT. AS PER CITY GUIDELINES ALL WATERMAINS IN FILL AREAS ARE TO BE TIED WITH RESTRAINING JOINTS AND THRUST BLOCKS.
- 14. THE CONTRACTOR SHALL IMPLEMENT THE EROSION AND SEDIMENT CONTROL PLAN PRIOR TO THE COMMENCEMENT OF ANY SITE CONSTRUCTION. ALL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE INSTALLED TO THE SATISFACTION OF THE ENGINEER, OR ANY REGULATORY AGENCY. ALL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE MAINTAINED UNTIL VEGETATION IS ESTABLISHED OR UNTIL THE START OF A SUBSPOLIENT PHASE.
- 15. CONTRACTORS SHALL BE RESPONSIBLE FOR KEEPING CLEAN ALL ROADS WHICH BECOME COVERED IN DUST, DEBRIS AND/OR MUD AS A RESULT OF ITS CONSTRUCTION OPERATIONS.
- 16. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY ADDITIONAL BEDDING OR ADDITIONAL STRENGTH PIPE SHOULD THE MAXIMUM OPSD TRENCH WIDTH BE EXCEEDED.
- 17. ALL PIPE, CULVERTS, STRUCTURES REFER TO NOMINAL INSIDE DIMENSIONS.

TO EXCAVATE, BACKFILL, COMPACT AND REINSTATE.

- 18. SHOULD CLAY SEALS BE REQUIRED, THEY SHALL BE INSTALLED AS PER THE RECOMMENDATIONS WITHIN
- THE GEOTECHNICAL REPORT.

  19. UNLESS SPECIFICALLY NOTED OTHERWISE, PIPE MATERIALS SHALL BE AS FOLLOWS;
- . UNLESS SPECIFICALLY NOTED OTHERWISE, PIPE MATERIALS SHALL BE AS FOLLOWS;
  -WATERMAINS TO BE PVC DR18
  -SANITARY SEWER TO BE PVC DR35
- -SANITARY SEWER TO BE PVC DR35
  -PERFORATED STORM SEWERS IN REAR YARDS AND LANDSCAPE AREAS TO BE HDPE
  -STORM SEWERS 375mm DIAMETER AND LESS TO BE PVC DR35
  -STORM SEWERS 450mm DIAMETER AND GREATER TO BE CONCRETE, CLASS AS PER OPSD 807.010 OR 807.030. OR HIGHER
- FOR SHALLOW SEWERS, REFER TO CITY STANDARD S35.

  20. ALL CONNECTIONS TO EXISTING WATERMAINS ARE TO BE COMPLETED BY CITY FORCES. CONTRACTOR IS
- 21. ANY WATERMAIN WITH LESS THAN 2.4m AND ANY SEWER WITH LESS THAN 2.0m DEPTH OF COVER REQUIRES THERMAL INSULATION AS PER CITY OF OTTAWA STANDARD W22 OR AS APPROVED BY THE
- ENGINEER.
- 22. ALL FIRE HYDRANTS AS PER CITY STANDARD W19, c/w 150mmØ LEAD UNLESS OTHERWISE SPECIFIED.
- 23. ALL STUBBED SEWERS SHALL HAVE PRE-MANUFACTURED CAPS INSTALLED.
- 24. ALL CATCHBASINS SHALL HAVE A 600mm SUMP. ALL CATCHBASIN MANHOLES, AND ALL STORM MANHOLES WITH OUTLETTING PIPE SIZES LESS THAN 900mm, SHALL HAVE A 300mm SUMP.
- 25. ALL SANITARY MANHOLES IN PONDING AREAS SHALL BE EQUIPPED WITH A WATERTIGHT COVER.
- 26. ALL LEADS FOR STREET CATCHBASIN'S AND CURB INLET CATCHBASIN'S CONNECTED TO MAIN SHALL BE 200mmø PVC DR35 @ MIN 2% SLOPE UNLESS NOTED OTHERWISE. ALL LEADS FOR RYCB'S CONNECTED TO MAIN SHALL BE 200mmø PVC DR35 @ MIN 1% SLOPE UNLESS NOTED OTHERWISE.
- 27. UNLESS SPECIFICALLY NOTED OTHERWISE, ALL STREET CATCHBASINS SHALL BE INSTALLED WITH TWO 3.0m MINIMUM SUBDRAINS INSTALLED LONGITUDINALLY, PARALLEL WITH THE CURB. ALL CATCHBASINS IN ASPHALT AREAS, NOT ADJACENT TO A CURB, SHALL BE INSTALLED WITH FOUR 3.0m MINIMUM SUBDRAINS INSTALLED ORTHOGONALLY.
- 28. INLET CONTROL DEVICES SHALL BE INSTALLED PRIOR TO COMPLETING THE ROAD BASE (GRANULAR A).
- 29. ALL SEWER SERVICE LATERALS WITH MAINLINE CONNECTIONS DEEPER THAN 5.0m REQUIRE A CONTROLLED SETTLEMENT JOINT.
- 30. EACH BUILDING SHALL BE EQUIPPED WITH A SANITARY AND STORM SEWER BACKWATER VALVE AND CLEAN-OUT ON ITS PRIMARY SERVICE IF REQUIRED BY ONTARIO BUILDING CODE REQUIREMENTS (BY OTHERS)
- 31. THE SUBGRADE OF ALL STRUCTURES, PIPE, ROADS, SIDEWALKS, WALKWAYS, AND BUILDINGS SHALL BE INSPECTED BY THE GEOTECHNICAL ENGINEER PRIOR TO PROCEEDING WITH CONSTRUCTION.
- 32. TOP COURSE ASPHALT SHALL NOT BE PLACED UNTIL THE FINAL CCTV INSPECTION AND NECESSARY REPAIRS HAVE BEEN COMPLETED TO THE SATISFACTION OF THE ENGINEER AND THE CITY OF OTTAWA.
- 33. ALL RETAINING WALLS GREATER THAN 1.0m IN HEIGHT SHALL BE DESIGNED BY A QUALIFIED STRUCTURAL
- 34. ALL RETAINING WALLS GREATER THAN 0.6m IN HEIGHT REQUIRE A GUARD. ANY GUARD ON A RETAINING WALL GREATER THAN 1.0m IN HEIGHT SHALL BE DESIGNED BY THE QUALIFIED STRUCTURAL ENGINEER RESPONSIBLE FOR THE WALL DESIGN.
- 35. UPON COMPLETION OF THE RETAINING WALL, THE CONTRACTOR SHALL REQUEST A CONFORMANCE CERTIFICATE FROM THE QUALIFIED ENGINEER RESPONSIBLE FOR THE WALL DESIGN.

8201 CAMPEAU DRIVE Inc.

COPYRIGHT

CLIENT

This drawing has been prepared solely for the intended use, thus any reproduction or distribution for any purpose other than authorized by Arcadis is forbidden. Written dimensions shall have precedence over scaled dimensions. Contractors shall verify and be responsible for all dimensions and conditions on the job, and Arcadis shall be

conformance before proceeding with fabrication.

Arcadis Professional Services (Canada) Inc.

informed of any variations from the dimensions

and conditions shown on the drawing. Shop

drawings shall be submitted to Arcadis for general

iomion) ibi cicap i reisseichal cornece (canada) me.		
ISSUES		
No.	DESCRIPTION	DATE
1	SUBMISSION 1 FOR CITY REVIEW	2025-07-18



AL





333 Preston Street - Suite 500 Ottawa ON K1S 5N4 Canada tel 613 225 1311 www.arcadis.com

PROJECT

8201 CAMPEAU DRIVE

PROJECT NO: 30282806	
DRAWN BY: C.C.	CHECKED BY: T.B.
PROJECT MGR: S.L.	APPROVED BY: S.L.
·	

SHEET TITLE

NOTES & LEGEND

SHEET NUMBER 010

ISSUE

