



STATION	FINISHED GRADE	TOP W/M	ITEM
+0+00	97.60	95.200	200mmØ x 200mmØ TEE
+0+06.8	97.94	95.540	22" x HORIZONTAL BEND
+0+08.5	98.10	95.700	200mmØ VALVE AND BOX
+0+10.0	98.10	95.700	45° VERTICAL BEND
+0+11.5	98.10	95.400	45° VERTICAL BEND
+0+014.5	97.95	95.250	45° HORIZONTAL BEND
+0+20	97.93	95.230	TOP OF WATERMAIN
+0+37.3	97.95	95.250	200mmØ x 200mmØ TEE
+0+40.3	97.77	95.070	200mmØ VALVE AND BOX
+0+60	97.75	95.050	200mmØ VALVE AND BOX
+0+80	97.65	94.950	TOP OF WATERMAIN
+0+85	97.70	95.000	200mmØ CAP AND THRUST BLOCK

SEWER AND WATER CROSSING TABLE							
CROSSING	STM INV	STM OBV	SAN INV	SAN OBV	WTR TOP	WTR BTM	COMMENTS
	x	x	x	x	x	x	REFER TO DWG
	94.82	95.19	94.28	94.48	95.85	95.70	WATERMAIN CROSSING PER W25.2. INSULATE PER W22
			94.28	94.48	95.28	95.13	
	95.54	95.74	93.90	94.10	96.44	96.24	WATERMAIN CROSSING PER W25.2. INSULATE PER W22
	95.23	95.53	94.85	95.05	x	x	
	x	x	93.99	94.19	95.40	95.20	
	93.94 (93.80)	95.14 (95.28)	94.36	94.56	95.98	95.78	WATERMAIN CROSSING PER W25.2. INSULATE PER W22
	93.87 (93.73)	95.07 (95.21)	94.53	94.73	95.91	95.71	WATERMAIN CROSSING PER W25.2. INSULATE PER W22
	x	x	x	x	x	x	REFER TO DWG
	95.01	95.21	93.14	93.34	95.91	95.71	WATERMAIN CROSSING PER W25.2. INSULATE PER W22
	94.76	95.21	93.25	93.45	95.91	95.71	WATERMAIN CROSSING PER W25.2. INSULATE PER W22
	94.78 (94.70)	95.23 (95.31)	93.33	93.53			
	95.14	95.52	93.44	93.64	X	X	
	95.17	95.55	93.53	93.73	96.25	96.05	WATERMAIN CROSSING PER W25.2. INSULATE PER W22

SCHEDULE OF INLET CONTROL DEVICES					
ORIFICE NAME	TRIBUTARY AREA ID	ICD TYPE	2yr HEAD(m)	2yr FLOW (L/s)	100yr FLOW (L/s)
C101A-2IC	C101A	CIRCULAR (83mm ORIFICE)	1.04	14.58	21.33
C103A-2IC	C103A	CIRCULAR (83mm ORIFICE)	1.41	17.11	21.06
C201A-1IC	C201A	CIRCULAR (83mm ORIFICE)	0.60	10.96	20.85
C201B-1IC	C201B	CIRCULAR (83mm ORIFICE)	0.69	11.75	22.17
C202A-1IC	C202A	CIRCULAR (83mm ORIFICE)	1.45	17.32	21.47
C203A-1IC	C203A	CIRCULAR (83mm ORIFICE)	0.69	11.77	22.22
C204A-1IC	C204A	CIRCULAR (83mm ORIFICE)	1.36	16.79	21.52
C205A-1IC	C205A	CIRCULAR (83mm ORIFICE)	0.76	12.43	21.72



- ## Notes
1. FINAL METER AND REMOTE METER LOCATIONS TO BE CONFIRMED BY MECHANICAL CONSULTANT.
 2. FINAL BUILDING SERVICE SIZES TO BE REVIEWED AND CONFIRMED BY MECHANICAL CONSULTANT.
 3. THE LOCATION AND ELEVATION OF SEWERS, WATERMAIN AND UTILITIES IS APPROXIMATE ONLY AND THE EXACT LOCATION AND ELEVATIONS SHOULD BE DETERMINED BY CONSULTING THE MUNICIPAL AUTHORITIES AND UTILITY COMPANIES CONCERNED. THE CONTRACTOR SHALL PROVIDE THE LOCATION AND ELEVATION OF SEWERS, WATERMAINS AND UTILITIES AND SHALL BE RESPONSIBLE FOR THEIR PROTECTION AND THE IMPLEMENTATION OF ANY NECESSARY PROTECTION. ANY DISCREPANCY WITH THE INFORMATION SHOWN ON THESE PLANS SHALL BE REPORTED TO THE ENGINEER PRIOR TO CONTINUING WITH CONSTRUCTION. EXISTING SEWER INFORMATION PROVIDED FROM ENGINEERING DESIGN DRAWINGS PREPARED BY STATKAT KANATA WEST - PHASE 1, AS-BUILT DRAWING FEB 28, 2022.

0	ISSUED FOR SPA	JP	AMP	25.07.29.2013
Revision		By	Appd.	YY.MM.DD
File Name: 160402165-D8.dwg		JP	AMP	JP
		Dwn.	Chkd.	Dsgn.
				YY.MM.DD

Permit-Seal

Client/Project

RICH CRAFT HOMES

KANATA WEST - BLOCK 1
MAPLE GROVE RD./ROGER GRIFFITHS AVE.
OTTAWA, ON

Title
SITE SERVICING PLAN

Project No. 160402165

Scale 0 3 9 15m
1:300



SSP-1 2 of 7 0