



September 3, 2025

PH5075-LET.01

W.O. Stinson & Sons Ltd.
4728 Bank Street
Ottawa, Ontario
K1T 3W7

Attention: **Scott Stinson**

Subject: **Hydrogeological Assessment and Terrain Analysis**
Proposed Industrial Development
301 Somme Street, Ottawa, Ontario

Consulting Engineers

9 Auriga Drive
Ottawa, Ontario
K2E 7T9
Tel: (613) 226-7381

Geotechnical Engineering
Environmental Engineering
Hydrogeology
Materials Testing
Building Science
Rural Development Design
Retaining Wall Design
Noise and Vibration Studies

patersongroup.ca

INTRODUCTION

Further to your request, Paterson has conducted a Hydrogeological Assessment and Terrain Analysis in support of a Site Plan Control Application (hereby referred to as a Site Plan application) for the proposed industrial development located at 301 Somme Street in Ottawa. Please refer to the Figure 1 - Key Plan attached for the approximate site location.

The purpose of this work has been to determine the suitability of the water supply aquifer underlying the site to support the Site Plan application as well as determining the suitability of the subject site to attenuate sewage system impacts. A Hydrogeological Assessment for a different Site Plan application for the same property was completed in 2022 by GHD Ltd (GHD) and was titled Hydrogeological and Impact Assessment Report (HIAR) dated September 22, 2022. The GHD HIAR has been used to support this assessment. Supplemental hydrogeological fieldwork was performed by Paterson to confirm the water quality which was encountered in the GHD HIAR report.

The Subject Site consists of a 6.09 ha lot which is largely brush-covered, with an engineered pad extending across the central portion of the site. The property is generally flat until the northern and western property boundaries, where it then slopes into abutting ditches. A mapped watercourse (GeoOttawa) flows from southwest to northeast along the northern property boundary.



The suitability of the aquifer to supply the subject site was assessed using the methodology provided in City of Ottawa Hydrogeological and Terrain Analysis Guidelines (HTAG).

HYDROGEOLOGICAL PRE-CONSULTATION

A Hydrogeological pre-consultation was completed with a City of Ottawa Hydrogeologist on July 11, 2025. It was proposed to use the data collected as part of GHD's HIAR to support this site plan application. During the Hydrogeological pre-consultation, the City Hydrogeologist indicated that the collection and submission of a water quality sample would be required to confirm the water quality encountered in the GHD HIAR. The intent behind the additional sampling is to confirm that the water quality is still similar to the water quality from the pumping test completed in support of the GHD HIAR.

DESCRIPTION OF SUBJECT SITE

The subject site is an approximately 6.09 ha undeveloped lot which is covered with grassed areas and brush. An engineered pad is located in the area of the proposed building from the previous Site Plan application. Please refer to Figure-1 Key Plan and Hobin Architecture Drawing No. A1.00 Vehicle Service & Storage Yard Site Plan attached for the proposed site location and site layout.

The subject site is currently vacant and will be serviced by a private water supply and sewage system. A drilled well was installed onsite on July 27, 2022, and is hereafter referred to as Test Well 1 (TW1). TW1 is the well which will be the service well for the proposed development.

The site is bordered to the north by Rideau Road, to the east by vacant properties, and to the south and west by Somme Street. The properties to the west of Somme Street remain undeveloped, while the property south of Somme Street consist of an industrial development. The subject site itself and the surrounding industrial areas are zoned RH for Rural Heavy Industrial Zone (GeoOttawa).

POTENTIAL KARST

Based on available Ontario Geological Survey (OGS) mapping (GRS005), the subject site is not within an area of known, potential or inferred karst.

RAISIN-SOUTH NATION SOURCE PROTECTION PLAN

The Raisin-South Nation Source Protection Plan (RSNSPP) provides guidance as to which policies apply to a given property, municipality or specific activity and if there are specific designations that apply to the area. The subject site and surrounding areas have been designated as a Highly Vulnerable Aquifer (HVA within the RSNSPP), Significant Groundwater Recharge Area (SGRA) and Intake Protection Zone 3 (IPZ 3) and is identified as three of four groundwater related vulnerable areas identified within the Clean



Water Act (2006). The four vulnerable areas consist of SGRA, HVA, IPZ, and wellhead protection area (WHPA).

Based upon the designation, the RSNSPP provides a list of activities that are prohibited, managed or encouraged to change/educate dependent upon the vulnerable area type. There are no restrictions of land uses on the subject site based upon its proposed usage.

Therefore, there are no related requirements for an HVA, SGRA or IPZ 3 at this location.

FIELDWORK PROGRAM

Well Testing – GHD HIAR – August 9, 2022

As a means to demonstrate the adequacy of the aquifer underlying the subject lands with respect to water quality and quantity, TW1 was installed in July of 2022 and submitted to a pumping test as part of GHD's HIAR. TW1 has a Water Well Record (WWR) Well ID of A342117. TW1 has a 152.4 mm diameter steel casing that extends to 15.9 m below ground surface (bgs) with a 0.7 m stick up. The well itself extends to a depth of 42.7 m bgs. Based on available geological mapping, the drift thickness at TW1 varies from 0 to 2 m. Refer to Hobin Architecture Drawing A1.00 Vehicle Service & Storage Yard Site Plan, attached, for the approximate location of TW1 (referred to as existing well).

As a means to evaluate the water supply aquifer intercepted by the well, the well was subjected to a 12-hour constant rate pumping test at a rate of 38 L/min. The pumping test was conducted on August 9, 2022 by GHD. Details of the pumping test can be found in the Hydrogeological and Impact Assessment completed by GHD (September 22, 2022).

The selected rate of 38 L/min provides approximately 6.7 times the Total Daily Design Sanitary Sewage Flow (TDDSSF) volume of 4,077 L/day during the 12-hour pumping test performed by GHD. Recovery data was collected from the well following the completion of the pumping in 2022. The well was noted to have achieved 100% recovery approximately 7 hours after the completion of the 12-hour pumping test.

Supplemental Well Testing – August 12, 2025

On August 12, 2025, Paterson completed supplemental geochemical testing on TW1 where TW1 was purged at a rate of 38 L/min for 6 hours, after which a water sample was obtained. The purpose of the supplemental testing was to confirm that the water quality of the aquifer accessed by TW1 is consistent with the results from the pumping test performed by GHD in 2022.

A submersible pump was installed by Air Rock Drilling Co Ltd and used for the 6-hour purge. The well purge was carried out at a pumping rate of 38 L/min for a duration of 6 hours. The water was discharged in a manner where the discharge water would not flow back towards the well. During the well purging, the pumping rate was measured using the timed volume correlation method. The pumping rate was maintained within 5% of the



selected pumping rate. An electric datalogger (VanEssen TD-Diver) was installed in the test well prior to the start of the well purge, and the static water level was periodically recorded manually.

The selected rate of 38 L/min provides approximately 3.4 times the Total Daily Design Sanitary Sewage Flow (TDDSSF) volume of 4,077 L/day, and equates to approximately 22 well volumes.

A series of field tests of the pumped water were carried out at the well head at the end of the 6-hour well purge. The parameters tested at the well head included: pH, total dissolved solids, conductivity, turbidity, true colour, hydrogen sulfide, and temperature. Calibration / confirmation of calibration of all field-testing equipment was performed in Paterson's laboratory the day prior to the pumping test. Values are then confirmed again onsite prior to the start of the pumping test.

Groundwater samples were collected at 6 hours after the start of the purging. Prior to collection of the groundwater samples, the free chlorine residual was verified as non-detectable. The water samples were submitted for comprehensive testing of bacteriological, chemical, and physical water quality parameters consistent with the standard "Subdivision Supply" suite of parameters plus trace metals, and Volatile Organic Compounds (VOCs).

All samples were collected unfiltered and unchlorinated and were placed directly into clean bottles supplied by the analytical laboratory. Samples were placed immediately into a cooler with ice and were transported directly to Environmental Testing Canada Inc. (Eurofins) laboratory in Ottawa. All samples were received by the laboratory within 24 hours of collection.

Aquifer Analysis

The parameters encountered in the samples collected by Paterson after the well purge are similar to those found in GHD's HIAR (2022). Based on a comparison of the water quality results, there are no significant changes in water quality compared to the pumping test performed in 2022 by GHD as part of the HIAR, and therefore the pumping test completed by GHD in support of the HIAR can be considered representative for this assessment.

Water Quantity

Pumping test data was analyzed by GHD and is presented below:





AQUIFER PARAMETER	RESULT OF ANALYSIS
Transmissivity (m ² /day)	26.7
Pumping Rate (L/min)	38
Pre-test Static Water Level (m)	7.9
Post-test Static Water Level (m)	8.7
Available Drawdown (m)	31.5
% Drawdown During Pumping Test (%)	2.5
Specific Capacity (L/min/m drawdown)	48.5

The drawdown data was analyzed in GHD's HIAR and aquifer transmissivity was estimated to be 33.4 m²/day based on the drawdown and 26.7 m²/day based on the recovery.

The pumping test results from GHD's HIAR shows that TW1 has a high yield to support the water demands that may be required. Overall maximum drawdown at a constant pumping rate of 38 L/min, for a period of 12 hours was approximately 0.8 m (2.5% of the available drawdown). Full Recovery was attained within 7 hours after pumping ceased.

The total volume of water pumped during the 12-hour pumping event was approximately 27,360 L. This is approximately 6.7 times the maximum total daily design volume of water (4,077 L/d) required to support the Site Plan Control Application.

Based on the information summarized in Table 1, it is readily apparent that the water supply well has intercepted an adequately strong water supply aquifer which has sufficient quantity to service the proposed Site Plan Control Application.

The suitability of the aquifer to supply the proposed Site Plan Application for the proposed industrial development was assessed using the methodology provided in the City of Ottawa Hydrogeological and Terrain Analysis Guidelines (HTAG).

Given the analyses presented and summarized above, it is our opinion that there is an adequate supply of water to support the proposed Site Plan Control Application. Available water well records (WWR) of the neighboring properties on the MECP Well Record mapping website indicated that the wells were screened in limestone. Surrounding WWRs are attached to this report.



Water Quality

Laboratory Data

During Paterson's well purge, a total of 13,680 L was discharged. This is approximately 3.4 times the TDDSSF, and equates to approximately 22 well volumes.

A HACH Pocket Colorimeter II chlorine reader was used to measure the free chlorine residual level. No chlorine residual was detected in the discharge water prior to the collection of the water sample at the end of Paterson's well purge.

Hydrogen sulfide was not detected olfactorily during Paterson's well purge. Hydrogen sulfide levels were measured using the HACH Hydrogen Sulfide Test Kit, Model HS-C, (# 2537800).

The Subdivision Package suite of parameters and trace metals laboratory water quality obtained from the 12-hour pumping test sample collected by GHD (HIAR), along with the geochemical results from the sample collected at the end of Paterson's well purge (August 12, 2025), are presented in Tables 3a and 3b below. The laboratory analyses reports can be found attached. VOC laboratory analytical testing was completed on the sample collected at the end of Paterson's well purge and was found to be non-detect in the sample results. All laboratory test results can be found attached to this report.





TABLE 3a: GROUNDWATER MICROBIOLOGY & GENERAL GEOCHEMISTRY					
PARAMETER	UNITS	ODWS		TW1	
		LIMIT	TYPE	A342117 (12hr)	TW1 GW1 (6 hr)
				2022-08-09	2025-08-12
MICROBIOLOGICAL					
Escherichia Coli (E.Coli)	ct/100mL	0	MAC	0	0
Total Coliforms	ct/100mL	0	MAC	3	0
GENERAL CHEMICAL - HEALTH RELATED					
Fluoride (F)	mg/L	1.5	MAC	-	2.20
Ammonia (N-NH ₃)	mg/L	-	-	0.17	0.240
Nitrite (N-NO ₂)	mg/L	1	MAC	<0.003	<0.5
Nitrate (N-NO ₃)	mg/L	10	MAC	<0.006	<0.5
Total Kjeldahl Nitrogen	mg/L	-	-	0.16	0.332
Turbidity (Field)	NTU	1.0 (5.0)	MAC/AO	-	0.86
Turbidity (Laboratory)	NTU	1.0 (5.0)	MAC/AO	4.21	2.3
GENERAL CHEMICAL - AESTHETIC RELATED					
Alkalinity (as CaCO ₃)	mg/L	30-500	OG	261	306
Chloride (Cl)	mg/L	250	AO	68	79
Colour (Laboratory - True)	TCU	5	AO	<2	<2
Colour (Field - True)	TCU	5	AO	-	0
Conductivity	uS/cm	-	-	1350	1,210
Dissolved Organic Carbon	mg/L	5	AO	2	2.2
Hardness (as CaCO ₃)	mg/L	100	OG	511	567
Ion Balance	unitless	-	-	-	1.01
pH	unitless	6.5-8.5	AO	8.23	8.2
Phenols	mg/L	-	-	-	<0.001
Sulphate (SO ₄)	mg/L	500	AO	400	285
Sulphide (S ₂ ⁻)	mg/L	0.05	AO	<0.02	<0.01
Tannin & Lignin	mg/L	-	-	0.4	0.10
Total Dissolved Solids	mg/L	500	AO	914	787

- ODWS identifies the following types of parameters:
 - MAC = Maximum Allowable Concentration
 - AO = Aesthetic Objective
 - OG = Operational Guideline
2. Shaded Concentration Indicates an Exceedance of the ODWS Objective



TABLE 3b: GROUNDWATER GEOCHEMISTRY - METALS					
PARAMETER	UNITS	ODWS		TW1	
		LIMIT	TYPE	A342117 (12hr)	TW1 GW1 (6 hr)
				2022-08-09	2025-08-12
METALS					
Aluminum (Al)	mg/L	0.1	OG	<0.001	<0.01
Antimony (Sb)	mg/L	0.006	IMAC	<0.0009	<0.0005
Arsenic (As)	mg/L	0.01	IMAC	0.0004	<0.001
Barium (Ba)	mg/L	1.0	MAC	0.0988	0.09
Beryllium (Be)	mg/L	-	-	0.000011	<0.0005
Boron (B)	mg/L	5.0	IMAC	0.216	0.24
Cadmium (Cd)	mg/L	0.005	MAC	0.00002	<0.0001
Calcium (Ca)	mg/L	-	-	117	128
Chromium (Cr)	mg/L	0.05	MAC	<0.00008	<0.001
Cobalt (Co)	mg/L	-	-	0.000082	<0.0002
Copper (Cu)	mg/L	1.0	AO	<0.0002	<0.001
Iron (Fe)	mg/L	0.3	AO	0.48	0.55
Lead (Pb)	mg/L	0.01	MAC	<0.00009	<0.001
Magnesium (Mg)	mg/L	-	-	53.5	60
Manganese (Mn)	mg/L	0.05	AO	0.171	0.18
Mercury (Hg)	mg/L	0.001	MAC	<0.00001	<0.0001
Molybdenum (Mo)	mg/L	-	-	0.03188	0.018
Nickel (Ni)	mg/L	-	-	0.0012	<0.005
Potassium (K)	mg/L	-	-	7.39	8
Selenium (Se)	mg/L	0.05	MAC	0.00011	<0.001
Silver (Ag)	mg/L	-	-	<0.00005	<0.0001
Sodium (Na)	mg/L	200	AO	57	65
Strontium (Sr)	mg/L	-	-	5.92	6.25
Thallium (Tl)	mg/L	-	-	<0.000005	<0.0001
Uranium (U)	mg/L	0.02	MAC	0.000219	<0.001
Vanadium (V)	mg/L	-	-	0.00009	<0.001
Zinc (Zn)	mg/L	5.0	AO	<0.002	<0.01

- ODWS identifies the following types of parameters:
 MAC = Maximum Acceptable Concentration
 IMAC = Interim Maximum Acceptable Concentration
 AO = Aesthetic Objective
 OG = Operational Guideline
- Shaded Concentration Indicates an Exceedance of the ODWS Objective

The bacteriological test results from Paterson's Well purge (Certificate of Analysis – Report No. 4432589) indicated that the test samples at the 6-hour point were non-detect (0 ct/100 mL) for E.Coli and Total Coliforms.

The water quality of the subject water supply well meets all the Ontario Drinking Water Standards Maximum Acceptable Concentrations (MAC). The water meets all of the Aesthetic Objectives (AO) and Operational Guidelines (OG) with the exception of the following:

- Hardness (as CaCO₃)
- Fluoride (F)
- Total Dissolved Solids (TDS)
- Iron (Fe)
- Manganese (Mn)



Each of these groundwater parameters are discussed in detail below. Should any water treatment be desired by the owner, it is recommended that a water treatment specialist be retained to ensure that water treatment occurs in a safe manner.

Hardness as CaCO₃

Hardness, expressed as calcium carbonate, is an operational guideline and does not appear in the ODWS. Rather, it appears in the Technical Support Documents for Ontario Drinking Water Standards, Objectives and Guidelines as a parameter with an operational guideline at 100 mg/L. At the measured concentrations of 567 mg/L, the water is considered to be very hard, and it is above the Ontario Drinking Water Objective (ODWO) of 500 mg/L specified in Table 3 of the MOECC guidance document Procedure D-5-5 (1996).

The Langelier Saturation Index (LSI) calculation provided an LSI of 0.5. Based on the evaluation of the result, the water is super saturated and tends to precipitate a scale layer of calcium carbonate (slightly scale forming and slightly corrosive). Based on the range of stability in the positive direction, there are no mitigative measures needed. See Langelier Saturation Index Calculation attached for calculation details.

It is recommended that water hardness be treated using conventional technologies such as water softening or reverse osmosis, if desired by the owner. Without treating hardness, scaling can occur which can result in discolouration and residue buildup on water fixtures, or reduction in boiler efficiency due to scale build-up. According to Health Canada's *Guidelines for Canadian Drinking Water Quality - Summary Tables*, "Although hardness may have significant aesthetic effects, a guideline has not been established because public acceptance of hardness may vary considerably according to the local conditions; major contributors to hardness (calcium and magnesium) are not of direct public health concern".

Fluoride

Fluoride can be naturally occurring in groundwater and has been added to drinking water in concentrations of 0.5 to 0.8 mg/L to control tooth decay. Fluoride was present in concentrations of 2.2 mg/L. The MAC for fluoride is 1.5 mg/L, however, concentrations up to 2.4 mg/L are considered acceptable where the fluoride is naturally occurring.

According to the Technical Support Document for Ontario Drinking Water Standards, Objectives and Guidelines (TSDODWSOG), when fluoride concentrations are above 1.5 mg/L but less than 2.4 mg/L the Ministry of Health and Long Term Care recommends that an approach through local boards of health be used to raise public and professional awareness to control for excessive exposure to fluoride. Although no treatment is required for fluoride, it must be reported to the local Medical Officer of Health.



Total Dissolved Solids (TDS)

Total Dissolved Solids (TDS) refers to the concentration of inorganic substances dissolved in water. The main constituents are typically chloride, sulphates, calcium, magnesium, and bicarbonates. The TDS concentration of 787 mg/L exceeds the Aesthetic Objective of 500 mg/L. At concentrations above 500 mg/L, some consumers may find the taste objectionable, however, as the objective is an aesthetic objective, no treatment is required. It is recommended that a point of use reverse osmosis unit be installed, if the owner desires, for drinking purposes. As such, no taste problems will occur when the system is used.

The Langelier calculation provided an LSI of 0.5. Based on the evaluation of the result, the water is super saturated and tends to precipitate a scale layer of calcium carbonate (slightly scale forming and slightly corrosive). Based on the range of stability in the positive direction, there are no mitigative measures needed for TDS. See Langelier Saturation Index Calculation attached for calculation details.

Iron

Concentrations of iron above 0.3 mg/L can contribute to staining of fixtures and a metallic taste at higher concentrations. Precipitation of iron can promote the growth of iron bacteria in pipes. The concentration of iron in the groundwater in TW1 was measured to be 0.55 mg/L. The concentration of iron in the groundwater is considered to be reasonably treatable in accordance with Procedure D-5-5. It is recommended that a water softener or manganese greensand filter be used to reduce the levels of iron and reduce the potential for excessive precipitate occurring in the water supply system, if desired by the property owner. If treatment is not used, negative impacts such as discolouration of water fixtures, precipitation of iron and staining may occur.

Manganese

The manganese concentration results from the laboratory test samples yielded a value of 0.18 mg/L in the onsite well, which is above the aesthetic objectives in the ODWSOG of 0.05 mg/L. The Health Canada Federal Drinking Water Guidelines have suggested a health related MAC of 0.12 mg/L due to potential adverse effects on the central nervous system primarily in infants due to chronic exposure, however this guideline has not been implemented by Ontario as of the writing of this report. Furthermore, this is an industrial development that is not raising infants.

According to the Guidelines for Canadian Drinking Water Quality: Guideline Technical Document – Manganese, section 3: “Specific guidance related to the implementation of drinking water guidelines should be obtained from the appropriate drinking water authority in the affected jurisdiction.”. The applicable regulations which apply to the development approval process for this site are the HTAG and MECP Procedure D-5-5, which does not have a MAC for manganese.



Procedure D-5-5 gives a maximum concentration considered reasonably treatable for manganese as 1.0 mg/L. It is recommended that a reverse osmosis system, ion exchange, water softeners and / or an oxidizing filter be used to reduce the manganese concentration, if desired by the owner.

As the concentration of manganese is elevated above the Health Canada Federal Drinking Water Guidelines, a notice regarding the elevated levels of manganese in the aquifer accessed by TW1 is recommended to be registered on title so that future owners are made aware.

The City of Ottawa (Ottawa Public Health) has prepared a Manganese in drinking Water Factsheet, which can be found attached to this report.

Sodium

Sodium (Na), an aesthetic parameter, was detected in the laboratory test sample at concentrations of 65 mg/L, which does not exceed the ODWS aesthetic objective of 200 mg/L. Although sodium is not toxic and no maximum acceptable concentration has been set, concentrations above 20 mg/L require that the Medical Officer of Health be notified of the water quality results, so that this information may be passed on to local physicians for use in treatment of those requiring a sodium-restricted diet. It should be noted that some water treatment technologies, such as water softeners, can increase the sodium concentration so care should be given if such treatment technologies are used.



Terrain Analysis

Surficial Geology

A series of boreholes were put down on the subject parcel to delineate the subsurface soil conditions. Onsite investigations were completed by Paterson in 2025, 2021 and 2019 with further investigations completed by others in 2021, 2020, and 2008. The boreholes were distributed in a manner to provide general coverage of the subject site, taking into consideration underground services and available site access. The locations of the test holes on the property are delineated on the Test Hole Location Plan, drawing PG7327-1, attached.

The borehole locations were recorded and the subsurface conditions, including the soil morphology and depth to the groundwater table (if encountered), were carefully observed and recorded. The soils encountered were classified texturally in the field and later reviewed in the laboratory.

Generally, the subsurface profile at the borehole locations were observed to consist of topsoil followed by an approximate 2.3 to 10 m thickness of fill material followed by a layer of clayey silt to silty clay and/or silty sand. Generally, the fill material consisted of silty sand and/or silty clay with varying amounts of organics, gravel, asphalt, concrete and bedrock fragments. The boreholes were advanced to a maximum depth of 14.3 m below ground surface (bgs).

Reference should be made to the test pit logs appended to this report for the details of the soil profiles encountered at each test hole location. The client should be aware that any information pertaining to soils are furnished as a matter of general information only and borehole descriptions are not to be interpreted as descriptive of conditions at locations other than those described by the boreholes themselves.

Hydrogeological Sensitivity of the Site

The subject site is currently vacant and undeveloped aside from an engineered pad. The subject site is to be serviced by a private well and sewage system. The site is bordered by Rideau Road to the north, by vacant lands to the east, and by Somme Street to the west and south. All surrounding properties are on private services.

The overburden at the test hole locations generally consists of topsoil followed by an approximate 2.3 to 10 m thickness of fill material followed by a layer of clayey silt to silty clay and/or silty sand overlying bedrock. The WWR for TW1 indicates that bedrock was encountered at 14.0 m bgs. According to available geological mapping, the drift thickness within the site varies from 0 to 2 m bgs.

According to the geotechnical field investigation, the overburden thickness was observed to be greater than 2 m. As such, the site is not considered to be hydrogeologically sensitive and, therefore, mitigating measures are not required.



Conceptual Lot Development Plan

A vehicle service building, a storage building, a cardlock fueling area and propane storage tanks along with infrastructure is proposed to be constructed onsite. The location of the proposed structure can be found on the attached Hobin Architecture Drawing A1.00 Vehicle Servicing & Storage Yard Site Plan, attached to this report.

Proposed Sewage System

A sewage system design was completed by Paterson and submitted to the Ottawa Septic System Office (OSSO) for a Sewage System Installation Permit (SSIP). The sewage flows for the proposed development are based on Part 8 of the Ontario Building Code (OBC). The Total Daily Design Sanitary Sewage Flow (TDDSSF) volume was calculated to be 4,077 L/day.

The approved OSSO SSIP includes an Advantex AX25-RT treatment system, which is an NSF 245 approved sewage treatment system capable of reducing total nitrogen levels by at least 50 %.

The OSSO approved SSIP will be submitted separately as part of the Site Plan application.

Predictive Nitrate Impact Assessment

Nitrate is considered to be a critical parameter of concern when assessing impacts to groundwater quality downgradient of an onsite sewage system. The City's HTAG, including the annotated MECP Procedure D-5-4 applies for the proposed development. For the purpose of this guideline, the Ontario Drinking Water Objective of 10 mg/L of nitrate is used as an indicator of groundwater impact potential.

Under this guideline, where the average lot size is one hectare or larger and the minimum lot size is 0.8 ha or greater, a detailed impact assessment may not be required. It has been the City of Ottawa's policy that where the lot size of 0.8 ha or larger, a detailed assessment is typically not required since it is considered to be a low-risk development.

The subject site is located within the Hawthorne Industrial Park industrial subdivision (Golder Associates 08-1122-0215-3, September 2011). The subject site is 6.09 ha in size, while the industrial subdivision has an average lot size of 3.15 ha, with lot sizes ranging from 0.8 – 11.04 ha. As such, a detailed nitrate impact assessment (NIA) would not typically be necessary. An NIA was completed below to corroborate our opinion that the property can adequately support the proposed development without having adverse impacts on the underlying bedrock aquifer should the minimum separation distances, well construction, and sewage system be completed as per the recommendations of this report and the OBC. The values shown in the Predictive Nitrate Impact Assessment attached to this report are summarized below.



<input type="checkbox"/> Site area	6.09 ha
<input type="checkbox"/> Impervious area (%)	80 %
<input type="checkbox"/> Daily sewage flow	4.1 m ³ /d
<input type="checkbox"/> Concentration of nitrate in effluent with treatment (Value based on nitrate reduction system (Advantex AX25RT Series) with 50 % nitrate reduction)	20 mg/L
<input type="checkbox"/> Surplus Water (The surplus water value was estimated based on Environment Canada Climate Office values with a soil type comprised of clay (Urban Lawns) and anthropogenic sources.)	361 mm/yr
<input type="checkbox"/> Combined infiltration factor based on:	0.50
• Topography infiltration factor	0.20
• Soil texture infiltration factor	0.20
• Cover infiltration factor	0.10

The topography infiltration factor of 0.20 is based upon a rolling land with an average slope of 2.8 to 3.8 m/km. The soil texture infiltration factor was based upon a material which consisted of a silty sand to silty clay, which is a medium combination of clay and loam with a value of 0.2. This is a reasonable generalization of the overburden. The “cover infiltration factor” was calculated at 0.10 based upon a conservative cultivated land type cover.

There are numerous tertiary treatment technologies that are NSF/ANSI 245 and/or BNQ certified for 50% nitrate reduction, resulting in an effluent nitrate concentration of less than 20 mg/L. The proposed sewage system consists of an Advantex AX25-RT treatment system, which is NSF 245 certified and is therefore capable of providing a minimum of 50 % nitrate reduction. When using an effluent nitrate concentration of 20 mg/L, the predicted nitrate concentration at the property boundary is **8.09 mg/L**. This is below the limit of 10 mg/L of nitrate at the property boundary.

Based on the results of the predicted nitrate impact assessment, it is our opinion that the property can adequately support the proposed industrial development without having an adverse impact on the underlying bedrock aquifer, provided that a NSF/ANSI 245 and/or BNQ certified 50% nitrate reduction technology is used in the sewage system.



CONCLUSIONS

Based on the information contained within the body of this report the following conclusions can be drawn:

1. The water supply aquifer intercepted by the existing well is considered to be adequate to support the water quantity demands for the proposed industrial development.
2. The groundwater contains elevated concentrations of hardness, fluoride, TDS, iron and manganese. The noted parameters can be treated to functional concentrations with current readily available water conditioning equipment, if desired by the owner.
3. Elevated concentrations of manganese were encountered in the water supply intercepted by TW1. Although only regulated for aesthetic reasons in Ontario (AO of 0.05 mg/L), the federal government of Canada has a MAC of 0.12 mg/L due to potential adverse effects on the central nervous system primarily in infants due to chronic exposure. This guideline has not been implemented by Ontario as of the writing of this report. As the concentration of manganese is elevated above the Health Canada Federal Drinking Water Guidelines, a notice regarding the elevated levels of manganese in the aquifer accessed by TW1 is recommended to be registered on title so that future owners are made aware.
4. If desired by the property owner, a residential grade water softener can be used to facilitate the reduction of the hardness concentration and reduce scaling. If a water softener is used for the proposed development, the owner should be made aware that additional sodium will be added to the water to reduce hardness. Note that elevated hardness is above the MCCRT, however, the MCCRT for hardness is related to aesthetic reasons. If desired, a point-of-use reverse osmosis system can be used to provide a drinking tap source without increasing sodium levels.
5. The sodium concentration was measured to be above the 20 mg/L reporting limit and, as such, the Medical Officer of Health for the City of Ottawa should be informed to assist area physicians in the treatment of local residents on sodium reduced diets. It should be noted that some water treatment equipment may further increase the sodium concentration.



6. The predicted nitrate concentrations at the property boundary is calculated to be below the required 10 mg/L threshold when an NSF/ANSI 245 and/or certified BNQ system with a minimum of 50 % nitrate reduction tertiary treatment system is used.
7. A Sewage System Permit and Building Permit need to be issued prior to the commencement of construction on the proposed industrial building or the proposed sewage system.
8. The results of the Hydrogeological Assessment and Terrain Analysis have provided satisfactory evidence that the subject site can support the proposed building addition with respect to water quantity and sewage system placement.

We trust that the current submission satisfies your immediate requirements.

Best Regards,

Paterson Group Inc.

Alexander Schopf, PhD, EIT



Erik Ardley, P. Geo

Attachments:


- Key Plan
- Hobin Architecture A1.00 Vehicle Service & Storage Yard Site Plan
- MECP Water Well Records
- Eurofins Certificate of Analysis
- Paterson Borehole Logs
- Nitrate Impact Assessment Calculations
- Langelier Saturation Index (LSI) Calculation
- City of Ottawa Manganese in Drinking Water Factsheet
- Paterson Drawing PG7567-1 - Test Hole Location Plan
- GHD Ltd. *Hydrogeological and Impact Assessment Report*, September 22, 2022





FIGURE 1

KEY PLAN



LEGAL DESCRIPTION:
 PART OF LOT 26; CONVESSION 6 (RIDEAU FRONT) GEOGRAPHIC TOWNSHIP OF GLOUCESTER and PARK OF BLOCKS 5 AND 14, REGISTERED PLAN 4M-1388 CITY OF OTTAWA

CIVIL ADDRESS:
 301 SOMME STREET, OTTAWA

ZONING NOTES:
 OFFICIAL PLAN DESIGNATION: RURAL ZONING - RH - RURAL HEAVY INDUSTRIAL
 ABUTTING - RH - RURAL HEAVY INDUSTRIAL

Owner
 W.O. STINSON & SON LTD.
 4128 Bank Street, Ottawa, ON K1T 3W1
 Attn: Scott Stinson - 613-822-1400

Architect/Agent
 HOBIN ARCHITECTURE INC.
 63 Pamela Street, Ottawa, ON K1S 3K7
 Attn: Doug van den Ham - 613-238-1200 x 115

Survey
 ANNIS O'SULLIVAN VOLLEBEKK LTD
 113 Prescott Street, Box 1340, Kemptville, Ontario K0G1J0
 Attn: Emmett Ketchum - 613-258-1111

Civil
 STANTEC OTTAWA
 300 - 1331 Clappe Avenue Ottawa ON K2C 3K4
 Attn: Peter Moroz P.Eng - 613-244-2851


Structural
 NOT YET CONTRACTED

Electrical
 NOT YET CONTRACTED

Landscape
 NOT YET CONTRACTED

Traffic
 PARSONS ENGINEERING
 1223 Michael St., Suite 100, Ottawa, ON K1J 1T2
 Attn: Jake Berube - 613-641-1862

ZONE: RH	REQUIRED	PROVIDED
PERMITTED USE (AMONG OTHERS)	AUTOMOBILE SERVICE STATION, DRIVE-THROUGH FACILITY, GAS BAR/PARKING LOT, SERVICE & REPAIR SHOP, STORAGE YARD, WAREHOUSE	ALL PERMITTED USES
MIN. LOT AREA	8,000 sq.m.	60,843sq.m.
MIN. LOT WIDTH	50m	00m
MIN. FRONT YARD SETBACK	15 m	15 m
MIN. REAR YARD SETBACK	15 m	15 m
MIN. INTERIOR SIDE YARD SETBACK (I) ABUTTING INDUSTRIAL ZONE (II) OTHER	3m / 10m	3m / 10m
MIN. CORNER SIDE YARD SETBACK	15m	15m
MAX. PRINCIPAL BUILDING HEIGHT	15m	15m
MAX. LOT COVERAGE (%)	50%	8.7%
PARKING SPACES (STAFF)	00 / 100 = 00	60
BICYCLE PARKING	1 / 1500 = 2	2 PROVIDED INDOORS
OUTDOOR STORAGE	NOT PERMITTED IN ANY REQUIRED FRONT OR CORNER SIDE YARD, MUST BE SCREENED FROM ADJACENT RESIDENTIAL OR PUBLIC ROADS BY A 1.8M HIGH OPAQUE SCREEN	



LEGEND:

B.F. PARKING STALL c/w B.F. SIGNAGE	
DEPRESSED CURB c/w TWSI	
150mm DIA., 6mm THK. GALV. STEEL BOLLARD (MIN. 1.5m HIGH & 1.5m BELOW GRADE)	
300mm DIA., 6mm THK. GALV. STEEL BOLLARD (MIN. 1.5m HIGH & 1.5m BELOW GRADE)	
PRECAST CONCRETE PAVING	
CAST IN PLACE CONCRETE SIDEWALK/ REFER TO GEOTECH. REPORT	
HEAVY DUTY ASPHALT	
ASPHALT SIDEWALK	
PAINTED LINE STOP BAR	
ROLLED CONCRETE CURB	
SITE SIGNAGE	
PAINTED LINES	
BIKE RACK	
EXTERIOR LIGHTING/ REFER TO ELEC. DWGS. FOR TYPES	
CHAIN LINK FENCE	
FIRE ROUTE SIGNAGE	

no.	date	revision
8	AUG 13, 2025	ISSUED FOR COORDINATION
7	JULY 17, 2025	ISSUED FOR COORDINATION
6	JULY 16, 2025	ISSUED FOR CONCEPT REVIEW
5	MAY 28, 2025	SITEPLAN - EXISTING WELL
4	APR 15, 2025	SITEPLAN PRE-CONSULTATION
3	MAR 20, 2025	ISSUED FOR CONCEPT REVIEW
2	MAR 06, 2025	ISSUED FOR CONCEPT REVIEW
1	FEB 27, 2025	ISSUED FOR CONCEPT REVIEW

It is the responsibility of the appropriate contractor to check and verify all dimensions on site and report all errors and/or omissions to the architect.

All contractors must comply with all pertinent codes and by-laws.

Do not scale drawings.

This drawing may not be used for construction until signed.

Copyright reserved.

Hobin Architecture Incorporated
 63 Pamela Street
 Ottawa, Ontario
 Canada K1S 3K7
 T: 613-238-7200
 F: 613-235-2005
 E: mail@hobinarc.com
 hobinarc.com

PROJECT/LOCATION:
 W.O. Stinson & Son Ltd.
 Somme Street Truck Yard
 301 Somme Street

DRAWING TITLE:
 VEHICLE SERVICE & STORAGE YARD SITE PLAN

DRAWN BY: DV	DATE: FEB 2025	SCALE: AS NOTED
PROJECT: 2502		DRAWING NO.: A1.00
REVISION NO.:		

1 SITE PLAN
 A1.00 SCALE: 1:500

Measurements recorded in: Metric Imperial

Well Owner's Information

First Name: Consolidated Fastfrate (Ottawa) Holdings Inc. Last Name/Organization: Consolidated Fastfrate (Ottawa) Holdings Inc. E-mail Address: _____
 Mailing Address (Street Number/Name): 330 Preston Street, 7th Floor, Ottawa, Ont K1R 5N4 Municipality: Ottawa Province: Ontario Postal Code: K1R 5N4 Telephone No. (inc. area code): _____

Well Location

Address of Well Location (Street Number/Name): # 301 SOMME STREET Township: GLOUCESTER Lot: P/L26407 Concession: 6 R.F.
 County/District/Municipality: OTTAWA-CARLETON City/Town/Village: GLOUCESTER Province: Ontario Postal Code: _____
 UTM Coordinates: Zone: 18 Easting: 456582 Northing: 5017208 Municipal Plan and Sublot Number: 4M-1388 Other: _____

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

General Colour	Most Common Material	Other Materials	General Description	Depth (m)
	Gravel, Hard Pan, Boulders			0' 46'
	Grey Black limestone w/ white sandstone mix			46' 140'

Annular Space

Depth Set at (m)	Type of Sealant Used (Material and Type)	Volume Placed (m ³)
52' 0'	Neat Cement Slurry	12.48

Method of Construction

<input type="checkbox"/> Cable Tool	<input type="checkbox"/> Diamond	<input checked="" type="checkbox"/> Public	<input type="checkbox"/> Commercial	<input type="checkbox"/> Not used
<input type="checkbox"/> Rotary (Conventional)	<input type="checkbox"/> Jetting	<input checked="" type="checkbox"/> Domestic	<input type="checkbox"/> Municipal	<input type="checkbox"/> Dewatering
<input type="checkbox"/> Rotary (Reverse)	<input type="checkbox"/> Driving	<input type="checkbox"/> Livestock	<input type="checkbox"/> Test Hole	<input type="checkbox"/> Monitoring
<input type="checkbox"/> Boring	<input type="checkbox"/> Digging	<input type="checkbox"/> Irrigation	<input type="checkbox"/> Cooling & Air Conditioning	
<input checked="" type="checkbox"/> Air percussion		<input type="checkbox"/> Industrial		
<input type="checkbox"/> Other, specify _____		<input type="checkbox"/> Other, specify _____		

Construction Record - Casing

Inside Diameter (cm/in)	Open Hole OR Material (Galvanized, Fibreglass, Concrete, Plastic, Steel)	Wall Thickness (cm/in)	Depth (m/ft)		Status of Well
			From	To	
6 1/4"	Steel	.188"	0'	52'	<input checked="" type="checkbox"/> Water Supply <input type="checkbox"/> Replacement Well <input type="checkbox"/> Test Hole <input type="checkbox"/> Recharge Well <input type="checkbox"/> Dewatering Well <input type="checkbox"/> Observation and/or Monitoring Hole <input type="checkbox"/> Alteration (Construction) <input type="checkbox"/> Abandoned, Insufficient Supply <input type="checkbox"/> Abandoned, Poor Water Quality <input type="checkbox"/> Abandoned, other, specify _____ <input type="checkbox"/> Other, specify _____
6"	Open Hole		52'	140'	

Construction Record - Screen

Outside Diameter (cm/in)	Material (Plastic, Galvanized, Steel)	Slot No.	Depth (m/ft)	
			From	To

Water Details

Water found at Depth (m/ft)	Kind of Water: <input type="checkbox"/> Fresh <input checked="" type="checkbox"/> Untested	Depth (m/ft)	Diameter (cm/in)
128 (m/ft)	<input type="checkbox"/> Gas <input checked="" type="checkbox"/> Other, specify _____	0' 52'	9 3/4"
134 (m/ft)	<input type="checkbox"/> Gas <input checked="" type="checkbox"/> Other, specify _____	52' 140'	6"

Well Contractor and Well Technician Information

Business Name of Well Contractor: Airlock Drilling Co Ltd Well Contractor's Licence No.: C7681
 Business Address (Street Number/Name): 6659 Franktown Road Richmond Municipality: Richmond
 Province: Ont Postal Code: K0A0R0 Business E-mail Address: _____
 Bus. Telephone No. (inc. area code): 6138382170 Name of Well Technician (Last Name, First Name): HANNA Jeremy
 Well Technician's Licence No.: T3632 Signature of Technician and/or Contractor: _____ Date Submitted: 20200831

Results of Well Yield Testing

After test of well yield, water was:
 Clear and sand free
 Other, specify _____

If pumping discontinued, give reason: X

Pump intake set at (m/ft): 100'

Pumping rate (l/min/GPM): 20

Duration of pumping: 1 hrs + 0 min

Final water level end of pumping (m/ft): 30' 7"

If flowing give rate (l/min/GPM): X


Recommended pump depth (m/ft): 100'

Recommended pump rate (l/min/GPM): 20

Well production (l/min/GPM): 20

Disrupted? Yes No

Time (min)	Draw Down (m/ft)		Time (min)	Recovery (m/ft)	
	Water Level (m/ft)	Static Level (m/ft)		Water Level (m/ft)	Static Level (m/ft)
	28.2'	30.7'			
1	29.3		1	29.2	
2	29.4		2	29.1	
3	29.5		3	29.1	
4	29.6		4	29.1	
5	29.7		5	29.	
10	29.9		10	28.2	
15	30.1		15	28.2"	
20	30.3		20		
25	30.4		25		
30	30.5		30		
40	30.6		40		
50	30.7		50		
60	30.74		60		



Comments: 1 HP 20 GPM Set @ 100 FT

Well owner's information package delivered: Yes No

Date Package Delivered: 20200728

Date Work Completed: 20200727

Ministry Use Only

Audit No.: 2379047

Received: NOV 22 2022

UTM 1182 4564010 E

9R 50168710 N


Elev. 9R 02910

Basin 25



ONTARIO

15 No 2342



The Well Drillers Act
Department of Mines, Province of Ontario

Water Well Record

Location: CARLETON Township, Village, Town or City Gloucester
Town or City
Address: WEITMILL
Date Completed: 10/10/51 Cost of well (excluding pump)

Pipe and Casing Record

Pumping Test

Casing diameter(s) 5"
Length(s) of casing(s) WEEL DEEPENED FROM 27' TO 57'
Type of screen
Length of screen
Distance from top of screen to ground level
Is well a gravel-wall type?
Date
Static level 13'
Pumping level 18'
Pumping rate 8 G.P.M.
Duration of test 30 MIN.
Distance from cylinder or bowls to ground level

Water Record

Kind (fresh or mineral) Fresh
Quality (hard, soft, contains iron, sulphur, etc.) hard
Appearance (clear, cloudy, coloured) clear
For what purpose(s) is the water to be used? Farm supply
How far is well from possible source of contamination? 45'
What is the source of contamination? Low stable
Enclose a copy of any mineral analysis that has been made of water

Table with 3 columns: Depth(s) to Water Horizon(s), Kind of Water, No. of Water F. Row 1: 57, Fresh, 44'

Well Log

Overburden and Bedrock Record

From

To

Previous well

0 ft.

27 ft.


SANDSTONE

27'

57'

Location of Well

In diagram below show distances of well from road and lot line. Indicate north by arrow.



Situation: Is well on upland, in valley, or on hillside? hillside
Drilling Firm: F. H. NICHOLSON S.O.M.
Address: 137 THAMES ST.
Name of Driller: M. RENVIEU
Date: Nov. 20/51
Licence Number



WATER WELL RECORD

316/5a

1. PRINT ONLY IN SPACES PROVIDED
2. CHECK CORRECT BOX WHERE APPLICABLE

11 1514733-15002 RF 06

10 14 15 22 23 24

COUNTY OR DISTRICT: [redacted] TOWNSHIP, BOROUGH, CITY, TOWN, VILLAGE: Gloucester Redem Front. CON., BLOCK, TRACT, SURVEY, ETC.: 5RF

DATE COMPLETED: DAY 15 MO. 04 YR. 75

1.6.698 RC 4 ELEVATION 0330 RC 4 BASIN CODE 26

LOG OF OVERBURDEN AND BEDROCK MATERIALS (SEE INSTRUCTIONS)

GENERAL COLOUR	MOST COMMON MATERIAL	OTHER MATERIALS	GENERAL DESCRIPTION	DEPTH - FEET	
				FROM	TO
Brown	Sandy soil			0	2
Brown	shale			2	10
grey	limestone		hard	10	116

31 000260228 0010617 0116215

32

41 WATER RECORD

WATER FOUND AT - FEET	KIND OF WATER
0112	1 <input checked="" type="checkbox"/> FRESH 3 <input type="checkbox"/> SULPHUR 2 <input type="checkbox"/> SALTY 4 <input type="checkbox"/> MINERAL
15-18	1 <input type="checkbox"/> FRESH 3 <input type="checkbox"/> SULPHUR 2 <input type="checkbox"/> SALTY 4 <input type="checkbox"/> MINERAL
20-23	1 <input type="checkbox"/> FRESH 3 <input type="checkbox"/> SULPHUR 2 <input type="checkbox"/> SALTY 4 <input type="checkbox"/> MINERAL
25-28	1 <input type="checkbox"/> FRESH 3 <input type="checkbox"/> SULPHUR 2 <input type="checkbox"/> SALTY 4 <input type="checkbox"/> MINERAL
30-33	1 <input type="checkbox"/> FRESH 3 <input type="checkbox"/> SULPHUR 2 <input type="checkbox"/> SALTY 4 <input type="checkbox"/> MINERAL

51 CASING & OPEN HOLE RECORD

INSIDE DIAM. INCHES	MATERIAL	WALL THICKNESS INCHES	DEPTH - FEET	
			FROM	TO
05	1 <input checked="" type="checkbox"/> STEEL 2 <input type="checkbox"/> GALVANIZED 3 <input type="checkbox"/> CONCRETE 4 <input type="checkbox"/> OPEN HOLE	188	0	18
05	1 <input type="checkbox"/> STEEL 2 <input type="checkbox"/> GALVANIZED 3 <input type="checkbox"/> CONCRETE 4 <input checked="" type="checkbox"/> OPEN HOLE			0116
24-25	1 <input type="checkbox"/> STEEL 2 <input type="checkbox"/> GALVANIZED 3 <input type="checkbox"/> CONCRETE 4 <input type="checkbox"/> OPEN HOLE			27-30

SCREEN

SIZE(S) OF OPENING (SLOT NO.)	DIAMETER INCHES	LENGTH FEET

MATERIAL AND TYPE: _____ DEPTH TO TOP OF SCREEN: 41-44 FEET

61 PLUGGING & SEALING RECORD

DEPTH SET AT - FEET		MATERIAL AND TYPE (CEMENT GROUT, LEAD PACKER, ETC.)
FROM	TO	
10-13	14-17	
18-21	22-25	
26-29	30-33	

71 PUMPING TEST

PUMPING TEST METHOD: 1 PUMP 2 BAILER

PUMPING RATE: 0010 GPM DURATION OF PUMPING: 01 HOURS 20 MINS


STATIC LEVEL	WATER LEVEL END OF PUMPING	WATER LEVELS DURING PUMPING				RECOVERY
19-21 FEET	22-24 FEET	15 MINUTES	30 MINUTES	45 MINUTES	60 MINUTES	
040	065	060	065	065	065	

IF FLOWING, GIVE RATE: _____ PUMP INTAKE SET AT: 110 FEET WATER AT END OF TEST: 1 CLEAR 2 CLOUDY

RECOMMENDED PUMP TYPE: SHALLOW DEEP

RECOMMENDED PUMP SETTING: 090 FEET RECOMMENDED PUMPING RATE: 0005 GPM

50-53 000.4 GPM./FT. SPECIFIC CAPACITY



FINAL STATUS OF WELL

1 WATER SUPPLY 5 ABANDONED, INSUFFICIENT SUPPLY
2 OBSERVATION WELL 6 ABANDONED, POOR QUALITY
3 TEST HOLE 7 UNFINISHED
4 RECHARGE WELL

WATER USE

05 1 DOMESTIC 5 COMMERCIAL
2 STOCK 6 MUNICIPAL
3 IRRIGATION 7 PUBLIC SUPPLY
4 INDUSTRIAL 8 COOLING OR AIR CONDITIONING
 OTHER 9 NOT USED

METHOD OF DRILLING

1 CABLE TOOL 6 BORING
2 ROTARY (CONVENTIONAL) 7 DIAMOND
3 ROTARY (REVERSE) 8 JETTING
4 ROTARY (AIR) 9 DRIVING
5 AIR PERCUSSION

CONTRACTOR

NAME OF WELL CONTRACTOR: Maurice Cayer LICENCE NUMBER: 1517
ADDRESS: Casselman Ont
NAME OF DRILLER OR BORER: _____ LICENCE NUMBER: _____
SIGNATURE OF CONTRACTOR: Maurice Cayer SUBMISSION DATE: _____ DAY _____ MO. _____ YR. _____

OFFICE USE ONLY

DATA SOURCE: 1 CONTRACTOR: 1517 DATE RECEIVED: 08 07 75
DATE OF INSPECTION: _____ INSPECTOR: _____
REMARKS: _____ P
WI

1527048

MUNICIPALITY: 15002 CON. NO.: 06

1. PRINT ONLY IN SPACES PROVIDED
2. CHECK CORRECT BOX WHERE APPLICABLE

COUNTY OR DISTRICT: **Ottawa Carleton** TOWNSHIP, BOROUGH CITY TOWN VILLAGE: **Gloucester** CON. BLOCK, TRACT, SURVEY ETC: **6** LOT: **26**
OWNER (SURNAME FIRST): **Beaver Road Builders Ltd.** ADDRESS: **P.O. Box 4208 st. "E" Ottawa, Ontario K1S 5B2** DATE COMPLETED: DAY **19** MO **4** YR **93**

21 ZONE EASTING NORTHING RC ELEVATION RC BASIN CODE II III IV

LOG OF OVERBURDEN AND BEDROCK MATERIALS (SEE INSTRUCTIONS)					
GENERAL COLOUR	MOST COMMON MATERIAL	OTHER MATERIALS	GENERAL DESCRIPTION	DEPTH - FEET	
				FROM	TO
Brown	Sandy Clay	Broken Rock	Fill	0	9
Gray	Hardpan	Boulders		9	15
Gray	Limestone		Soft	15	33
White & Gray	Sandstone		Hard	33	135

31 32

41 WATER RECORD

WATER FOUND AT - FEET	KIND OF WATER
56	1 FRESH 3 SULPHUR 2 SALTY 4 MINERALS 6 GAS
120	1 FRESH 3 SULPHUR 2 SALTY 4 MINERALS 6 GAS
	NOT TESTED

51 CASING & OPEN HOLE RECORD

INSIDE DIAM INCHES	MATERIAL	WALL THICKNESS INCHES	DEPTH - FEET	
			FROM	TO
6 1/4	STEEL GALVANIZED CONCRETE OPEN HOLE PLASTIC	.188	0	31
6 1/8	STEEL GALVANIZED CONCRETE OPEN HOLE PLASTIC		31	75
6	STEEL GALVANIZED CONCRETE OPEN HOLE PLASTIC		75	135

SCREEN

SIZE OF OPENING (SLOT NO)	DIAMETER INCHES	LENGTH FEET
	34.38	39.40

MATERIAL AND TYPE: _____ DEPTH TO TOP OF SCREEN: 41.44 FEET


61 PLUGGING & SEALING RECORD

DEPTH SET AT - FEET	MATERIAL AND TYPE (CEMENT GROUT LEAD PACKER ETC)
FROM	TO
31	0
18-21	22-25
26-29	30-33

Grouted - Cement (18)

71 PUMPING TEST

PUMPING TEST METHOD	PUMPING RATE	DURATION OF PUMPING
1 <input checked="" type="checkbox"/> PUMP 2 <input type="checkbox"/> BAILER	15-20 GPM	1 HOURS
STATIC LEVEL: 31 FEET	WATER LEVELS DURING:	1 PUMPING 2 RECOVERY
WATER LEVEL END OF PUMPING: 130 FEET	15 MINUTES: 40 FEET	30 MINUTES: 32 FEET
	45 MINUTES: 31 FEET	60 MINUTES: 31 FEET
RECOMMENDED PUMP TYPE: <input checked="" type="checkbox"/> SHALLOW <input checked="" type="checkbox"/> DEEP	RECOMMENDED PUMP SETTING: 125 FEET	RECOMMENDED PUMPING RATE: 5 GPM



FINAL STATUS OF WELL

1 WATER SUPPLY 5 ABANDONED, INSUFFICIENT SUPPLY
2 OBSERVATION WELL 6 ABANDONED POOR QUALITY
3 TEST HOLE 7 UNFINISHED
4 RECHARGE WELL DEWATERING

WATER USE

1 DOMESTIC 5 COMMERCIAL
2 STOCK 6 MUNICIPAL
3 IRRIGATION 7 PUBLIC SUPPLY
4 INDUSTRIAL 8 COOLING OR AIR CONDITIONING
 OTHER 9 NOT USED

METHOD OF CONSTRUCTION

1 CABLE TOOL 6 BORING
2 ROTARY (CONVENTIONAL) 7 DIAMOND
3 ROTARY (REVERSE) 8 JETTING
4 ROTARY (AIR) 9 DRIVING
5 AIR PERCUSSION DIGGING OTHER

CONTRACTOR

NAME OF WELL CONTRACTOR: **Capital Water Supply Ltd.** WELL CONTRACTOR'S LICENCE NUMBER: **1558**
ADDRESS: **P.O. Box 490 Stittsville, Ontario K2S 1A6**
NAME OF WELL TECHNICIAN: **S. Miller** WELL TECHNICIAN'S LICENCE NUMBER: **T0097**
SIGNATURE OF TECHNICIAN/CONTRACTOR: _____ SUBMISSION DATE: DAY **20** NO. **4** YR **93**

OFFICE USE ONLY

DATA SOURCE: **1558** CONTRACTOR: **1558** DATE RECEIVED: **MAY 06 1993**
DATE OF INSPECTION: _____ INSPECTOR: _____
REMARKS: _____

1. PRINT ONLY IN SPACES PROVIDED

2. CHECK CORRECT BOX WHERE APPLICABLE

11

1527383

MUNICIP 15002

CON. CON.

106

COUNTY OR DISTRICT: [redacted] TOWNSHIP, BOROUGH, CITY, TOWN, VILLAGE: **Windsor** CON. BLOCK, TRACT, SURVEY ETC: **6** LOT: **25-27** **26**

DATE COMPLETED: DAY **16** MO **8** YR **93**

Box 4208 stn. "E" Ottawa, Ontario K1S 5B2

LOG OF OVERBURDEN AND BEDROCK MATERIALS (SEE INSTRUCTIONS)

GENERAL COLOUR	MOST COMMON MATERIAL	OTHER MATERIALS	GENERAL DESCRIPTION	DEPTH - FEET	
				FROM	TO
Brown	Sand	Stone		0	5
Gray	Hardpan	Boulders		5	28
Gray	Sandstone		Hard	28	100

31

32

41 WATER RECORD

WATER FOUND AT - FEET	KIND OF WATER
58	1 <input type="checkbox"/> FRESH 3 <input type="checkbox"/> SULPHUR 2 <input type="checkbox"/> SALTY 4 <input type="checkbox"/> MINERALS 6 <input type="checkbox"/> GAS
88	1 <input type="checkbox"/> FRESH 3 <input type="checkbox"/> SULPHUR 2 <input type="checkbox"/> SALTY 4 <input type="checkbox"/> MINERALS 6 <input type="checkbox"/> GAS
20-23	NOT TESTED
25-28	1 <input type="checkbox"/> FRESH 3 <input type="checkbox"/> SULPHUR 2 <input type="checkbox"/> SALTY 4 <input type="checkbox"/> MINERALS 6 <input type="checkbox"/> GAS
30-33	1 <input type="checkbox"/> FRESH 3 <input type="checkbox"/> SULPHUR 2 <input type="checkbox"/> SALTY 4 <input type="checkbox"/> MINERALS 6 <input type="checkbox"/> GAS

51 CASING & OPEN HOLE RECORD

INSIDE DIAM. INCHES	MATERIAL	WALL THICKNESS INCHES	DEPTH - FEET	
			FROM	TO
6 1/4	1 <input checked="" type="checkbox"/> STEEL 2 <input checked="" type="checkbox"/> GALVANIZED 3 <input type="checkbox"/> CONCRETE 4 <input type="checkbox"/> OPEN HOLE 5 <input type="checkbox"/> PLASTIC	.188	0	39
5 15/16	1 <input type="checkbox"/> STEEL 2 <input type="checkbox"/> GALVANIZED 3 <input type="checkbox"/> CONCRETE 4 <input type="checkbox"/> OPEN HOLE 5 <input type="checkbox"/> PLASTIC		39	100

SCREEN

SIZE (S) OF OPENING (SLOT NO.)	DIAMETER INCHES	LENGTH FEET

MATERIAL AND TYPE: _____ DEPTH TO TOP OF SCREEN: _____

61 PLUGGING & SEALING RECORD


DEPTH SET AT - FEET	MATERIAL AND TYPE (CEMENT GROUT LEAD PACKER ETC)
37.5	Cement - Grouted

71 PUMPING TEST

PUMPING TEST METHOD	PUMPING RATE	DURATION OF PUMPING
1 <input checked="" type="checkbox"/> PUMP 2 <input type="checkbox"/> BAILER	20 GPM	1 15-16 HOURS 17-18 MINS

STATIC LEVEL	WATER LEVEL END OF PUMPING	WATER LEVELS DURING
7'6" FEET	14'6" FEET	15 MINUTES: 13'11" FEET 30 MINUTES: 14 FEET 45 MINUTES: 14'4" FEET 60 MINUTES: 14'6" FEET

RECOMMENDED PUMP TYPE: SHALLOW DEEP
RECOMMENDED PUMP SETTING: 50 FEET
RECOMMENDED PUMPING RATE: 5 GPM



FINAL STATUS OF WELL

1 WATER SUPPLY 5 ABANDONED, INSUFFICIENT SUPPLY
2 OBSERVATION WELL 6 ABANDONED POOR QUALITY
3 TEST HOLE 7 UNFINISHED
4 RECHARGE WELL DEWATERING

WATER USE

1 DOMESTIC 5 COMMERCIAL
2 STOCK 6 MUNICIPAL
3 IRRIGATION 7 PUBLIC SUPPLY
4 INDUSTRIAL 8 COOLING OR AIR CONDITIONING
 OTHER 9 NOT USED

METHOD OF CONSTRUCTION

1 CABLE TOOL 6 BORING
2 ROTARY (CONVENTIONAL) 7 DIAMOND
3 ROTARY (REVERSE) 8 JETTING
4 ROTARY (AIR) 9 DRIVING
5 AIR PERCUSSION DIGGING OTHER

CONTRACTOR

NAME OF WELL CONTRACTOR: **Capital Water Supply Ltd.** WELL CONTRACTOR'S LICENCE NUMBER: **1558**

ADDRESS: **Box 490 Stittsville, Ontario K2S 1A6**

NAME OF WELL TECHNICIAN: **S. Miller/T. Harrison** WELL TECHNICIAN'S LICENCE NUMBER: **T0097/T2251**

SIGNATURE OF TECHNICIAN/CONTRACTOR: _____ SUBMISSION DATE: DAY **18** MO **8** YR **93**

OFFICE USE ONLY

DATA SOURCE: **1558** CONTRACTOR: **1558** DATE RECEIVED: **SEP 21 1993**

DATE OF INSPECTION: _____ INSPECTOR: _____

REMARKS: _____

A 018916
A 018916

Instructions for Completing Form

- For use in the Province of Ontario only. This document is a permanent legal document. Please retain for future reference.
- All Sections must be completed in full to avoid delays in processing. Further instructions and explanations are available on the back of this form.
- Questions regarding completing this application can be directed to the Water Well Management Coordinator at 416-235-6203.
- All metre measurements shall be reported to 1/10th of a metre.
- Please print clearly in blue or black ink only.

Well Owner's Information and Location of Well Information

Ministry Use Only										
MUN	15000	CON	01	01	01	01	01	01	01	LOT

RR#/Street Number/Name: **OTAWA CARLETON**
3500 RIDEAU ROAD

City/Town/Village: **GLOUCESTER** Site/Compartment/Block/Tract etc.: **2 S**

GPS Reading: NAD **83** Zone **18** Easting **456298** Northing **5016953** Unit Make/Model: **MASELAN** Mode of Operation: Undifferentiated Averaged Differentiated, specify

Log of Overburden and Bedrock Materials (see instructions)

General Colour	Most common material	Other Materials	General Description	Depth From	Metres To
	GRAVEL + EARTH			0	1.21
	GREY + WHITE SANDSTONE			1.21	35.05
	GREY LIMESTONE w/ GREY SANDSTONE			35.05	42.67


Hole Diameter		
Depth From	Metres To	Diameter Centimetres
0	42.67	15.23

Construction Record					
Inside diam centimetres	Material	Wall thickness centimetres	Depth From	Metres To	
Casing					
15.88	<input checked="" type="checkbox"/> Steel <input type="checkbox"/> Fibreglass <input type="checkbox"/> Plastic <input type="checkbox"/> Concrete <input type="checkbox"/> Galvanized	.48	0	6.70	
Screen					
Outside diam	<input type="checkbox"/> Steel <input type="checkbox"/> Fibreglass <input type="checkbox"/> Plastic <input type="checkbox"/> Concrete <input type="checkbox"/> Galvanized	Slot No.			
No Casing or Screen					
<input checked="" type="checkbox"/> Open hole			6.09	42.67	

Test of Well Yield					
Pumping test method	Draw Down		Recovery		
	Time min	Water Level Metres	Time min	Water Level Metres	
Subpump					
Pump intake set at - (metres) 41.16	Static Level	14.18			
Pumping rate - (litres/min) 75.71	1	15.26	1	14.62	
Duration of pumping 1 hrs + 0 min	2	15.31	2	14.62	
Final water level end of pumping 15.85 metres	3	15.35	3	14.62	
Recommended pump type <input type="checkbox"/> Shallow <input checked="" type="checkbox"/> Deep	4	15.39	4	14.62	
Recommended pump depth 41.16 metres	5	15.42	5	14.57	
Recommended pump rate 75.71 (litres/min)	10	15.57	10	14.44	
If flowing give rate - (litres/min)	15	15.64	15	14.36	
	20	15.69	20	14.31	
	25	15.72	25	14.27	
	30	15.74	30	14.23	
	40	15.78	40	14.20	
	50	15.82	50	14.18	
	60	15.85	60	14.18	

Water Record	
Water found	Kind of Water
36.26 m	<input type="checkbox"/> Fresh <input type="checkbox"/> Sulphur <input type="checkbox"/> Gas <input type="checkbox"/> Salty <input type="checkbox"/> Minerals <input type="checkbox"/> Other: NOT TESTED
37.92 m	<input type="checkbox"/> Fresh <input type="checkbox"/> Sulphur <input type="checkbox"/> Gas <input type="checkbox"/> Salty <input type="checkbox"/> Minerals <input type="checkbox"/> Other: NOT TESTED
After test of well yield, water was <input checked="" type="checkbox"/> Clear and sediment free <input type="checkbox"/> Other, specify: NOT TESTED	
Chlorinated: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	

Plugging and Sealing Record			
Depth set at - Metres From	Metres To	Material and type (bentonite slurry, neat cement slurry) etc.	Volume Placed (cubic metres)
6.09	0	NEAT CEMENT SLURRY	.1362



Method of Construction

Cable Tool Rotary (air) Diamond Digging
 Rotary (conventional) Air percussion Jetting Other
 Rotary (reverse) Boring Driving

Water Use

Domestic Industrial Public Supply Other
 Stock Commercial Not used
 Irrigation Municipal Cooling & air conditioning

Final Status of Well

Water Supply Recharge well Unfinished Abandoned, (Other)
 Observation well Abandoned, insufficient supply Dewatering
 Test Hole Abandoned, poor quality Replacement well

Audit No. **Z 19099** Date Well Completed **2004 10 27**

Was the well owner's information package delivered? Yes No Date Delivered **2004 10 28**

Well Contractor/Technician Information

Name of Well Contractor: **AIR ROCK DRILLING CO. LTD** Well Contractor's Licence No.: **1119**

Business Address (street name, number, city etc.): **RR#1 RICHMOND, ONT K0A 2T0**

Name of Well Technician (last name, first name): **HOGAN DAN** Well Technician's Licence No.: **T3058**

Signature of Technician/Contractor: *[Signature]* Date Submitted **2004 11 16**

Ministry Use Only

Data Source: Contractor **1119**

Date Received **NOV 26 2004** Date of Inspection **2004 11 28**

Remarks: Well Record Number **1535203**

Address of Well Location (Street Number/Name) **TW #5 - Rideau** Township **Gloucester** 26 Province **6** Postal Code _____
 County/District/Municipality **Ottawa Carleton** City/Town/Village **Gloucester** Ontario
 UTM Coordinates Zone Easting Northing Municipal Plan and Sublot Number Other
 NAD **83184570435016848**

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

General Colour	Most Common Material	Other Materials	General Description	Depth (m/ft)	
				From	To
Brown	Soil	Stones	Fill	0	1.21
Gray	Sandy Soil	Stones	Wet	1.21	3.96
Gray	Sandstone		Very Hard	3.96	29.86

Annular Space

Depth Set at (m/ft)	Type of Sealant Used (Material and Type)	Volume Placed (m³/ft³)
From: 12.80 To: 0	Grouted Cement	.525m³

Results of Well Yield Testing

After test of well yield, water was: <input checked="" type="checkbox"/> Clear and sand free <input type="checkbox"/> Other, specify _____	Draw Down		Recovery	
	Time (min)	Water Level (m/ft)	Time (min)	Water Level (m/ft)
If pumping discontinued, give reason: Pump intake set at (m/ft) 22.85 Pumping rate (l/min / GPM) 54.6 Duration of pumping 6 hrs + _____ min Final water level end of pumping (m/ft) 9.99 If flowing give rate (l/min / GPM) _____	Static Level	6.85		
	1	8.03	1	8.97
	2	8.35	2	8.69
	3	8.60	3	8.55
	4	8.76	4	8.46
	5	8.88	5	8.40
10	9.20	10	8.23	
15		15		
20	9.49	20	8.04	
25	9.62	25	7.99	
30	9.68	30	7.93	
40	9.82	40	7.84	
50	9.91	50	7.77	
60	9.99	60	7.69	

Method of Construction

Cable Tool Diamond Public Commercial Not used
 Rotary (Conventional) Jetting Domestic Municipal Dewatering
 Rotary (Reverse) Air Driving Livestock Test Hole Monitoring
 Boring Digging Irrigation Cooling & Air Conditioning
 Air percussion Industrial
 Other, specify _____ Other, specify **Test Well**

Construction Record - Casing

Inside Diameter (cm/in)	Open Hole OR Material (Galvanized, Fibreglass, Concrete, Plastic, Steel)	Wall Thickness (cm/in)	Depth (m/ft)		Status of Well
			From	To	
15.86	Steel	.48	+ .45	12.80	<input checked="" type="checkbox"/> Water Supply <input type="checkbox"/> Replacement Well <input type="checkbox"/> Test Hole <input type="checkbox"/> Recharge Well <input type="checkbox"/> Dewatering Well <input type="checkbox"/> Observation and/or Monitoring Hole <input type="checkbox"/> Alteration (Construction) <input type="checkbox"/> Abandoned, Insufficient Supply <input type="checkbox"/> Abandoned, Poor Water Quality <input type="checkbox"/> Abandoned, other, specify _____ <input type="checkbox"/> Other, specify _____

Construction Record - Screen

Outside Diameter (cm/in)	Material (Plastic, Galvanized, Steel)	Slot No.	Depth (m/ft)	
			From	To

Water Details

Water found at Depth (m/ft)	Kind of Water: <input type="checkbox"/> Fresh <input checked="" type="checkbox"/> Untested	Depth (m/ft)	Diameter (cm/in)
27.12	<input type="checkbox"/> Gas <input type="checkbox"/> Other, specify _____	0	15.86
		12.80	29.86

Well Contractor and Well Technician Information

Business Name of Well Contractor: **Capital Water Supply Ltd.** Well Contractor's Licence No.: **1 5 5 8**
 Business Address (Street Number/Name): **Box 490** Municipality: **Stittsville**
 Province: **Ontario** Postal Code: **K 2 S 1 A 6** Business E-mail Address: **office@capitalwater.ca**

Well Technician's Licence No.: **6 1 3 8 3 6 1 7 6 6** Name of Well Technician (Last Name, First Name): **Miller, Stephen**
 Signature of Technician and/or Contractor: _____ Date Submitted: **2008/10/10**

Map of Well Location

Please provide a map below following instructions on the back.

Comments: _____

Ministry Use Only

Audit No. **Z 84410**
 Received **DEC 02 2008**

Well owner's information package delivered: Yes No
 Date Package Delivered: **20081007**
 Date Work Completed: **20080926**

Address of Well Location (Street Number/Name)		Township	Lot	Concession
TW #6 - Rideau Rd.		Gloucester	26	6
County/District/Municipality		City/Town/Village	Province	Postal Code
Ottawa Carleton		Gloucester	Ontario	
UTM Coordinates	Zone	Easting	Northing	Municipal Plan and Sublot Number
NAD	83	18457102	5017690	

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)					
General Colour	Most Common Material	Other Materials	General Description	Depth (m/ft)	
				From	To
Brown	Clay		Packed	0	3.65
Gray	Clay	Stones	Sticky	3.65	9.14
Gray	Shale		Soft	9.14	42.66
Gray	Limestone		Medium Soft	42.66	83.20

Annular Space			
Depth Set at (m/ft)	Type of Sealant Used (Material and Type)	Volume Placed (m ³ /ft ³)	
From: 17.67 To: 0	Grouted Cement	.525m ³	

Method of Construction	Well Use
<input type="checkbox"/> Cable Tool <input type="checkbox"/> Rotary (Conventional) <input checked="" type="checkbox"/> Rotary (Reverse Air) <input type="checkbox"/> Boring <input checked="" type="checkbox"/> Air percussion <input type="checkbox"/> Other, specify _____	<input type="checkbox"/> Public <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Livestock <input checked="" type="checkbox"/> Industrial <input type="checkbox"/> Other, specify Test Well

Construction Record - Casing				Status of Well	
Inside Diameter (cm/in)	Open Hole OR Material (Galvanized, Fibreglass, Concrete, Plastic, Steel)	Wall Thickness (cm/in)	Depth (m/ft)		<input checked="" type="checkbox"/> Water Supply <input type="checkbox"/> Replacement Well <input type="checkbox"/> Test Hole <input type="checkbox"/> Recharge Well <input type="checkbox"/> Dewatering Well <input type="checkbox"/> Observation and/or Monitoring Hole <input type="checkbox"/> Alteration (Construction) <input type="checkbox"/> Abandoned, Insufficient Supply <input type="checkbox"/> Abandoned, Poor Water Quality <input type="checkbox"/> Abandoned, other, specify _____ <input type="checkbox"/> Other, specify _____
			From	To	
15.86	Steel	.48	+ .60	17.67	

Construction Record - Screen				
Outside Diameter (cm/in)	Material (Plastic, Galvanized, Steel)	Slot No.	Depth (m/ft)	
			From	To

Water Details		Hole Diameter	
Water found at Depth (m/ft)	Kind of Water: <input type="checkbox"/> Fresh <input type="checkbox"/> Untested <input type="checkbox"/> Gas <input type="checkbox"/> Other, specify _____	Depth (m/ft)	Diameter (cm/in)
0		From: 0 To: 17.67	15.86
17.67		From: 17.67 To: 83.20	15.23

Well Contractor and Well Technician Information			
Business Name of Well Contractor		Well Contractor's Licence No.	
Capital Water Supply Ltd.		1 5 5 8	
Business Address (Street Number/Name)		Municipality	
Box 490		Stittsville	
Province	Postal Code	Business E-mail Address	
Ontario	K 2 S 1 A 6	office@capitalwater.ca	
Bus. Telephone No. (inc. area code)		Name of Well Technician (Last Name, First Name)	
6 1 3 8 3 6 1 7 6 6		Miller, Stephen	
Well Technician's Licence No.		Signature of Technician and/or Contractor	
0 0 9 7		Date Submitted	
		20081010	

Results of Well Yield Testing					
After test of well yield, water was:		Draw Down		Recovery	
<input checked="" type="checkbox"/> Clear and sand free <input type="checkbox"/> Other, specify _____		Time (min)	Water Level (m/ft)	Time (min)	Water Level (m/ft)
If pumping discontinued, give reason:		Static Level	3.18		
Pump intake set at (m/ft)		1	3.24	1	
Pumping rate (l/min / GPM)		2	4.23	2	
Duration of pumping		3	5.19	3	
6 hrs + _____ min		4		4	
Final water level end of pumping (m/ft)		5	6.53	5	
30.57		10	8.06	10	
If flowing give rate (l/min / GPM)		15	9.99	15	22.80
Recommended pump depth (m/ft)		20	11.53	20	19.40
60.95		25	12.92	25	17.12
Recommended pump rate (l/min / GPM)		30	14.08	30	15.13
13.65		40		40	11.82
Well production (l/min / GPM)		50		50	9.47
Disinfected?		60		60	7.94
<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No					

Map of Well Location	
Please provide a map below following instructions on the back.	
Comments:	

Well owner's information package delivered		Date Package Delivered		Ministry Use Only	
<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No		20081006		Audit No. Z 84412	
		Date Work Completed		DEC 02 2008	
		20080926		Received	

Master Well Owner's and Land Owner's Information

First Name: [Redacted] Last Name: Tomlinson
 Mailing Address (Street Number/Name, RR): Orgaworld Canada Real Estate via Services Inc. 5597 Power Road
 Municipality: Ottawa Province: ON Postal Code: K1G3N4 Telephone No. (inc. area code): 613 822 1067

Location and Construction of the Master Well in the Cluster

Address of Well Location (Street Number/Name, RR): Hawthorne Road at Rideau Road
 Township: [Redacted] Lot: 26:27 Concession: 6
 County/District/Municipality: [Redacted] City/Town/Village: Ottawa Province: Ontario Postal Code: [Redacted]

UTM Coordinates: NAD 83 Zone Easting Northing: 18 45640050 16859
 GPS Unit Make Model: Garmin Etrex
 Mode of Operation: Undifferentiated Averaged
 Differentiated, specify

Overburden and Bedrock Materials (see instructions on the back of this form)

General Colour	Most Common Material	Other Materials	General Description	Depth (Metres)	
				From	To
Gray/Brown	Very fine sand + silt		dense, moist	0	0.8
Brown	Fill - sand/silt/clay/gravels			0.8	4.7
Gray/Brown	Sand with silt		compact oxidized	4.7	6.0
Brown	Till - silty sand, gravel			6.0	7.6

Hole Details

Depth (Metres)		Diameter (Centimetres)
From	To	
0	7.6	20

Water Use

Public Industrial Not used Other, specify
 Domestic Commercial Dewatering
 Livestock Municipal Monitoring
 Irrigation Test Hole Cooling & Air Conditioning

Method of Construction

Cable Tool Air Percussion Digging
 Rotary (Conventional) Diamond Boring
 Rotary (Reverse) Jetting Other, specify HSA
 Rotary (Air) Driving

Status of Well

Test Hole Abandoned, Insufficient Supply
 Replacement Well Abandoned, Poor Water Quality
 Dewatering Well Other, specify
 Alteration (Construction) Abandoned, other, specify

No Casing and Screen Used Yes No

Static Water Level Test
 Open Hole: [Redacted] Metres

Screen

Galvanized Steel Fibreglass Concrete Plastic

Outside Diameter (Centimetres): 5.8 Slot No.: 10

Water Details

Water found at Depth: [Redacted] Metres Gas Fresh Salty Sulphur Minerals

Water found at Depth: [Redacted] Metres Gas Fresh Salty Sulphur Minerals

Water found at Depth: [Redacted] Metres Gas Fresh Salty Sulphur Minerals

Disinfected Yes No If no, provide reason: Monitoring well
 Date Master Well Completed (yyyy/mm/dd): 2008/07/14

Cluster Information (Please also fill out the additional Cluster Well Information for Well Construction for each parcel of land and cluster.)

Total Wells in Cluster: 10
 Please indicate Number of Cluster Well Information Log Sheets Submitted: 1

Location of Well Cluster

Detailed Map must be provided as an attachment no larger than legal size (8.5" x 14"). Sketches are not allowed.
 Check box to confirm detailed map is provided as per Section 11.1 (3)

Consent to release additional information concerning the cluster to the Director upon request

Signature of Technician/Contractor: [Redacted] Date (yyyy/mm/dd): 2008/10/20
 Master Well Owner's/Land Owner's consent to use Cluster Form: [Redacted]

Construction Details

Inside Diameter (Centimetres)	Material (steel, plastic, fibreglass, concrete, galvanized)	Wall Thickness	Depth (Metres)	
			From	To
5.1	PVC	Sched 40	0	3.0

Annular Space/Abandonment Sealing Record

Depth Set at (Metres) From	To	Type of Sealant Used (Material and Type)	Volume Used (Cubic Metres)
0.6	2.4	Bentonite	606 Kgs

Well Contractor and Well Technician Information

Business Name of Well Contractor: George Downing Estate Drilling
 Well Contractor's Licence No.: 1844
 Business Address (Street No./Name, number, RR): 410 Rue Principale Grenville-sur-la-Rouge
 Municipality: [Redacted]
 Province: QC Postal Code: J0V1B0 Business E-mail Address: downing@xplornet.com
 Name of Well Technician (Last Name, First Name): Downing, Bruce
 Signature of Technician: [Redacted] Date Submitted (yyyy/mm/dd): 2008/10/20

Ministry Use Only

Audit No.: M 02897 Well Contractor No.: [Redacted]
 Date Received (yyyy/mm/dd): NOV 26 2008 Date of Inspection (yyyy/mm/dd):
 Remarks:

Property Owner's Information

First Name: Orgaworld Canada Real Estate Last Name: Tomlinson Mailing Address (Street No./Name, RR): 5597 Power Road Municipality: Ottawa
 Province: Ontario Postal Code: K1G3N4 E-mail Address: rtomlinson@tomlinsongroup.com Telephone No. (inc. area code): 6138221867

Cluster Well Information

Address of Well Location (Street Number/Name, RR): Hawthorne Road at Rideau Road Lot: 26127 Concession: 6 Township: _____ County/District/Municipality: _____
 City/Town/Village: Ottawa Province: Ontario Postal Code: K1G3N4 GPS Unit Make: _____ Model: _____ Unit Mode of Operation: Undifferentiated Averaged Differentiated, specify: _____

Co...
 Pr...
 Signature of Technician/Contractor: Bruce Downing Date (yyyy/mm/dd): 2008/10/20

Well # on Sketch	UTM Coordinates		Full Depth of Hole (metres)	Hole Diameter (cm)	Method of Construction	Casing Material	Casing Length (metres)	Screen Interval (metres)		Annular Space Sealant Used	Static Water Level (metres)	Abandonment Sealant Used	Comments	Date of Completion (yyyy/mm/dd)
	Zone	Easting						Northing	From					
MW 1-08	18	45683150	16712	2.97	20	HSA	PVC	1.5	1.5	2.97	Bentonite	1.3		2008/07/07
MW 2-08	18	45679950	16553	2.77	10	DIA		0.6	0.6	2.77			Overburden from 0 to 0.18	2008/07/08
MW 3-08	18	45653350	16411	17.37	10	DIA		2.13	2.13	17.37			" " 0 to 0.30	2008/07/09
MW 4-08	18	45647450	16604	2.84	10/20	HSA/DIA		1.22	1.22	2.8				2008/07/08
MW 5-08	18	45659850	16675	2.77	20	HSA		1.5	1.5	2.77				2008/07/07
MW 7-08	18	45662250	17219	6.98	20	HSA		3.0	3.0	6.10				2008/07/14
MW 8-08	18	45668750	17036	4.72	20	HSA		3.0	3.0	4.2				2008/07/15
MW 9-08	18	45708650	17625	3.66	20	HSA		1.5	1.5	3.0				2008/07/15
MW 10-08	18	45720650	17303	2.90	20	HSA		1.37	1.37	2.90				2008/07/15

Well Contractor and Well Technician Information

Business Name of Well Contractor: George Downing Estate Drilling Ltd. Business Address (Street Number/Name, RR): 410 Rue Principale Municipality: Grenville-sur-la-Rouge Province: QC
 Postal Code: J0V1B0 Business Telephone No. (inc. area code): 8192426469 Well Contractor's Licence No.: 1844 Business E-mail Address: downing@xplornet.com
 Name of Well Technician (First Name, Last Name): Bruce Downing Well Technician's Licence No.: 2173 Date Submitted (yyyy/mm/dd): 2008/10/20 Signature of Technician: Bruce Downing

Date 1st Well in Cluster Constructed (yyyy/mm/dd): 2008/07/07 Date Last Well in Cluster Constructed (yyyy/mm/dd): 2008/07/15

Ministry Use Only

Date Received (yyyy/mm/dd): NOV 26 2008 Date Inspected (yyyy/mm/dd): _____
 Audit No.: C 01984 Remarks: m02897




figure 2.1
 TEST PIT AND MONITORING WELL LOCATION PLAN
 PHASE II ENVIRONMENTAL SITE ASSESSMENT
 LOT 26 AND 27, CONCESSION 6, OTTAWA, ONTARIO
 R.W. Tomlinson Ltd.

C-1844 m02897 c01984

NOV 26 2008




figure 2.1
 SAMPLE LOCATION PLAN
 PHASE II ENVIRONMENTAL SITE ASSESSMENT
 3429 HAWTHORNE RD., OTTAWA, ONTARIO
 CoorsTek, Inc.



053403-04(007)GN-OT001 AUG 20/2008

NOV 26 2008

C-1844 m02888 c03068

Master Well Owner's and Land Owner's Information

First Name: [Redacted] Last Name: Tomlinson
 Mailing Address (Street Number/Name, RR): Orgaworld Canada Real Estate via Services Inc. 5597 Power Road
 Municipality: Ottawa Province: ON Postal Code: K1G3N4 Telephone No. (inc. area code): 613 822 1067

Location and Construction of the Master Well in the Cluster

Address of Well Location (Street Number/Name, RR): Hawthorne Road at Rideau Road
 Township: [Redacted] Lot: 26:27 Concession: 6
 County/District/Municipality: [Redacted] City/Town/Village: Ottawa Province: Ontario Postal Code: [Redacted]

UTM Coordinates: NAD 83 Zone Easting Northing: 18 45640050 16859
 GPS Unit Make Model: Garmin Etrex
 Mode of Operation: Undifferentiated Averaged
 Differentiated, specify

Overburden and Bedrock Materials (see instructions on the back of this form)

General Colour	Most Common Material	Other Materials	General Description	Depth (Metres)	
				From	To
Gray/Brown	Very fine sand + silt		dense, moist	0	0.8
Brown	Fill - sand/silt/clay/gravels			0.8	4.7
Gray/Brown	Sand with silt		compact oxidized	4.7	6.0
Brown	Till - silty sand, gravel			6.0	7.6

Hole Details

Depth (Metres)		Diameter (Centimetres)
From	To	
0	7.6	20

Water Use

Public Industrial Not used Other, specify
 Domestic Commercial Dewatering
 Livestock Municipal Monitoring
 Irrigation Test Hole Cooling & Air Conditioning

Method of Construction

Cable Tool Air Percussion Digging
 Rotary (Conventional) Diamond Boring
 Rotary (Reverse) Jetting Other, specify
 Rotary (Air) Driving HSA

Status of Well

Test Hole Abandoned, Insufficient Supply
 Replacement Well Abandoned, Poor Water Quality
 Dewatering Well Other, specify
 Alteration (Construction) Abandoned, other, specify

No Casing and Screen Used Yes No

Static Water Level Test
 Open Hole: [Redacted] Metres

Screen

Galvanized Steel Fibreglass Concrete Plastic

Outside Diameter (Centimetres): 5.8 Slot No.: 10

Water Details

Water found at Depth: [Redacted] Metres Gas Fresh Salty Sulphur Minerals

Water found at Depth: [Redacted] Metres Gas Fresh Salty Sulphur Minerals

Water found at Depth: [Redacted] Metres Gas Fresh Salty Sulphur Minerals

Disinfected Yes No If no, provide reason: Monitoring well Date Master Well Completed (yyyy/mm/dd): 2008/07/14

Cluster Information (Please also fill out the additional Cluster Well Information for Well Construction for each parcel of land and cluster.)

Total Wells in Cluster: 10 Please indicate Number of Cluster Well Information Log Sheets Submitted: 1

Total Wells on this Property: unknown

Location of Well Cluster

Detailed Map must be provided as an attachment no larger than legal size (8.5" x 14"). Sketches are not allowed.
 Check box to confirm detailed map is provided as per Section 11.1 (3)

Consent to release additional information concerning the cluster to the Director upon request

Signature of Technician/Contractor: Bruce Downing Date (yyyy/mm/dd): 2008/10/20
 Master Well Owner's/Land Owner's consent to use Cluster Form: [Redacted]

Construction Details

Inside Diameter (Centimetres)	Material (steel, plastic, fibreglass, concrete, galvanized)	Wall Thickness	Depth (Metres)	
			From	To
5.1	PVC	Sched 40	0	3.0

Annular Space/Abandonment Sealing Record

Depth Set at (Metres) From	To	Type of Sealant Used (Material and Type)	Volume Used (Cubic Metres)
0.6	2.4	Bentonite	606 Kgs

Well Contractor and Well Technician Information

Business Name of Well Contractor: George Downing Estate Drilling Well Contractor's Licence No.: 1844
 Business Address (Street No./Name, number, RR): 410 Rue Principale Grenville-sur-la-Rouge
 Province: QC Postal Code: J0V1B0 Business E-mail Address: downing@xplornet.com
 Name of Well Technician (Last Name, First Name): Downing, Bruce
 Signature of Technician: Bruce Downing Date Submitted (yyyy/mm/dd): 2008/10/20

Ministry Use Only

Audit No.: **M 02897** Well Contractor No.: [Redacted]
 Date Received (yyyy/mm/dd): **NOV 26 2008** Date of Inspection (yyyy/mm/dd):
 Remarks:

Property Owner's Information

First Name: Orgaworld Canada Real Estate Last Name: Tomlinson Mailing Address (Street No./Name, RR): 5597 Power Road Municipality: Ottawa
 Province: Ontario Postal Code: K1G3N4 E-mail Address: rtomlinson@tomlinsongroup.com Telephone No. (inc. area code): 6138221867

Cluster Well Information

Address of Well Location (Street Number/Name, RR): Hawthorne Road at Rideau Road Lot: 26127 Concession: 6 Township: _____ County/District/Municipality: _____
 City/Town/Village: Ottawa Province: Ontario Postal Code: K1G3N4 GPS Unit Make: _____ Model: _____ Unit Mode of Operation: Undifferentiated Averaged Differentiated, specify: _____

Co...
 Pr...
 Signature of Technician/Contractor: Bruce Downing Date (yyyy/mm/dd): 2008/10/20

Well # on Sketch	UTM Coordinates		Full Depth of Hole (metres)	Hole Diameter (cm)	Method of Construction	Casing Material	Casing Length (metres)	Screen Interval (metres)		Annular Space Sealant Used	Static Water Level (metres)	Abandonment Sealant Used	Comments	Date of Completion (yyyy/mm/dd)
	Zone	Easting						Northing	From					
MW 1-08	18	45683150	16712	2.97	20	HSA	PVC	1.5	1.5	2.97	Bentonite	1.3		2008/07/07
MW 2-08	18	45679950	16553	2.77	10	DIA		0.6	0.6	2.77			Overburden from 0 to 0.18	2008/07/08
MW 3-08	18	45653350	16411	17.37	10	DIA		2.13	2.13	17.37			" " 0 to 0.30	2008/07/09
MW 4-08	18	45647450	16604	2.84	10/20	HSA/DIA		1.22	1.22	2.8				2008/07/08
MW 5-08	18	45659850	16675	2.77	20	HSA		1.5	1.5	2.77				2008/07/07
MW 7-08	18	45662250	17219	6.98	20	HSA		3.0	3.0	6.10				2008/07/14
MW 8-08	18	45668750	17036	4.72	20	HSA		3.0	3.0	4.2				2008/07/15
MW 9-08	18	45708650	17625	3.66	20	HSA		1.5	1.5	3.0				2008/07/15
MW 10-08	18	45720650	17303	2.90	20	HSA		1.37	1.37	2.90				2008/07/15


Well Contractor and Well Technician Information

Business Name of Well Contractor: George Downing Estate Drilling Ltd. Business Address (Street Number/Name, RR): 410 Rue Principale Municipality: Grenville-sur-la-Rouge Province: QC
 Postal Code: J0V1B0 Business Telephone No. (inc. area code): 8192426469 Well Contractor's Licence No.: 1844 Business E-mail Address: downing@xplornet.com
 Name of Well Technician (First Name, Last Name): Bruce Downing Well Technician's Licence No.: 2173 Date Submitted (yyyy/mm/dd): 2008/10/20 Signature of Technician: Bruce Downing

Date 1st Well in Cluster Constructed (yyyy/mm/dd): 2008/07/07 Date Last Well in Cluster Constructed (yyyy/mm/dd): 2008/07/15

Ministry Use Only

Date Received (yyyy/mm/dd): NOV 26 2008 Date Inspected (yyyy/mm/dd): _____
 Audit No.: C 01984 Remarks: m02897



C-1844 m02897 c01984

NOV 26 2008




figure 2.1
 SAMPLE LOCATION PLAN
 PHASE II ENVIRONMENTAL SITE ASSESSMENT
 3429 HAWTHORNE RD., OTTAWA, ONTARIO
 CoorsTek, Inc.



053403-04(007)GN-OT001 AUG 20/2008

NOV 26 2008

C-1844 m02888 c03068

Measurements recorded in: Metric Imperial

A082844

A 082844

ion 903 Ontario Water Resources Act

Page _____ of _____

Well Owner's Information

First Name	Last Name / Organization Orgaworld	E-mail Address	<input type="checkbox"/> Well Constructed by Well Owner
Mailing Address (Street Number/Name) c/o 400-179 Colonnade Road		Municipality Ottawa	Province Ontario
		Postal Code K2E 7J4	Telephone No. (inc. area code) 613 727 0510

Well Location

Address of Well Location (Street Number/Name) TW #7 Hawthorne Road		Township Gloucester	Lot 27	Concession 6
County/District/Municipality Ottawa Carleton		City/Town/Village Gloucester	Province Ontario	Postal Code
UTM Coordinates	Zone 18	Easting 456879	Northing 5016752	Municipal Plan and Sublot Number
				Other

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

General Colour	Most Common Material	Other Materials	General Description	Depth (m/ft)	
				From	To
Brown	Soil Stones		Packed	0	4.26
Grey & White	Sandstone		Very Hard	4.26	29.86

Annular Space		
Depth Set at (m/ft)	Type of Sealant Used (Material and Type)	Volume Placed (m³/ft³)
From: 6.40 To: 0	Grouted Cement	.21m³

Method of Construction	Well Use
<input type="checkbox"/> Cable Tool <input type="checkbox"/> Rotary (Conventional) <input checked="" type="checkbox"/> Rotary (Reverse) <input type="checkbox"/> Boring <input checked="" type="checkbox"/> Air percussion <input type="checkbox"/> Other, specify _____	<input type="checkbox"/> Public <input type="checkbox"/> Commercial <input type="checkbox"/> Not used <input type="checkbox"/> Domestic <input type="checkbox"/> Municipal <input type="checkbox"/> Dewatering <input type="checkbox"/> Livestock <input type="checkbox"/> Test Hole <input checked="" type="checkbox"/> Monitoring <input type="checkbox"/> Irrigation <input type="checkbox"/> Cooling & Air Conditioning <input type="checkbox"/> Industrial <input type="checkbox"/> Other, specify _____

Construction Record - Casing				Status of Well	
Inside Diameter (cm/in)	Open Hole OR Material (Galvanized, Fibreglass, Concrete, Plastic, Steel)	Wall Thickness (cm/in)	Depth (m/ft)		<input checked="" type="checkbox"/> Water Supply <input type="checkbox"/> Replacement Well <input type="checkbox"/> Test Hole <input type="checkbox"/> Recharge Well <input type="checkbox"/> Dewatering Well <input checked="" type="checkbox"/> Observation and/or Monitoring Hole <input type="checkbox"/> Alteration (Construction) <input type="checkbox"/> Abandoned, Insufficient Supply <input type="checkbox"/> Abandoned, Poor Water Quality <input type="checkbox"/> Abandoned, other, specify _____ <input type="checkbox"/> Other, specify _____
			From	To	
15.86	Steel	.48	+4.45	6.40	

Construction Record - Screen				
Outside Diameter (cm/in)	Material (Plastic, Galvanized, Steel)	Slot No.	Depth (m/ft)	
			From	To

Water Details		Hole Diameter	
Water found at Depth (m/ft)	Kind of Water: <input type="checkbox"/> Fresh <input checked="" type="checkbox"/> Untested <input type="checkbox"/> Gas <input type="checkbox"/> Other, specify _____	Depth (m/ft)	Diameter (cm/in)
9.14-12.19		From: 0 To: 6.40	15.86
18.28-21.33		6.40	29.86

Well Contractor and Well Technician Information			
Business Name of Well Contractor Capital Water Supply Ltd.		Well Contractor's Licence No. 1 5 5 8	
Business Address (Street Number/Name) Box 490		Municipality Stittsville	
Province Ontario	Postal Code K2S 1A6	Business E-mail Address office@capitalwater.ca	
Bus. Telephone No. (inc. area code) 613 836 1766		Name of Well Technician (Last Name, First Name) Miller, Stephen	
Well Technician's Licence No. 0 0 9 7		Signature of Technician and/or Contractor 	
		Date Submitted 2 0 1 0 0 5 2 8	

Results of Well Yield Testing				
After test of well yield, water was: <input checked="" type="checkbox"/> Clear and sand free <input type="checkbox"/> Other, specify _____	Draw Down		Recovery	
	Time (min)	Water Level (m/ft)	Time (min)	Water Level (m/ft)
If pumping discontinued, give reason: Pump intake set at (m/ft) 24.38 Pumping rate (l/min / GPM) 27.3 Duration of pumping 6 hrs + _____ min Final water level end of pumping (m/ft) 7.01 If flowing give rate (l/min / GPM) Recommended pump depth (m/ft) 24.38 Recommended pump rate (l/min / GPM) 27.3 Well production (l/min / GPM) Disinfected? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	Static Level	4.41		
	1	5.20	1	6.07
	2	5.57	2	5.68
	3	5.78	3	5.46
	4	5.94	4	5.33
	5	6.05	5	5.25
10	6.37	10	5.01	
15	6.52	15	4.89	
20	6.60	20	4.81	
25	6.68	25	4.76	
30	6.72	30	4.72	
40	6.81	40	4.65	
50	6.86	50	4.61	
60	6.89	60	4.58	

Map of Well Location	
Please provide a map below following instructions on the back.	
Comments:	

Well owner's information package delivered		Date Package Delivered		Ministry Use Only	
<input type="checkbox"/> Yes	<input checked="" type="checkbox"/> No	2 0 1 0 0 5 2 7	2 0 1 0 0 5 2 7	Audit No. Z 101832	
		Date Work Completed 2 0 1 0 0 5 2 5		Received AUG 04 2010	

Measurements recorded in: Metric Imperial

Well Owner's Information

First Name: _____ Last Name / Organization: **APEX DEVELOPMENTS INC.** E-mail Address: **info@apexdevco.com** Well Constructed by Well Owner

Mailing Address (Street Number/Name): **206-900 Morrison Drive** Municipality: **Ottawa** Province: **ON** Postal Code: **K2H8K7** Telephone No. (inc. area code): **613 422 6757**

Well Location

Address of Well Location (Street Number/Name): **35 Sappers Ridge** Township: _____ Lot: _____ Concession: _____

County/District/Municipality: _____ City/Town/Village: **Ottawa** Province: **Ontario** Postal Code: _____

UTM Coordinates: Zone: **18** Easting: **757533** Northing: **104518131** Municipal Plan and Sublot Number: _____ Other: _____

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

General Colour	Most Common Material	Other Materials	General Description	Depth (m/ft)	
				From	To
grey	Fill Clay limestone.	gravel	loose packed	0	8
				8	24
				24	155

Annular Space

Depth Set at (m/ft)	Type of Sealant Used (Material and Type)	Volume Placed (m ³)
40 0	High Early Cement	13.95

Method of Construction

Cable Tool Diamond Rotary (Conventional) Jetting Rotary (Reverse) Driving Boring Digging Air percussion Other, specify _____

Well Use

Public Commercial Not used Domestic Municipal Dewatering Livestock Test Hole Monitoring Irrigation Cooling & Air Conditioning Industrial Other, specify _____

Construction Record - Casing

Inside Diameter (cm/in)	Open Hole OR Material (Galvanized, Fibreglass, Concrete, Plastic, Steel)	Wall Thickness (cm/in)	Depth (m/ft)		Status of Well
			From	To	
5 5/8	Steel	1.88	40	+2.	<input type="checkbox"/> Water Supply <input type="checkbox"/> Replacement Well <input type="checkbox"/> Test Hole <input type="checkbox"/> Recharge Well <input type="checkbox"/> Dewatering Well <input type="checkbox"/> Observation and/or Monitoring Hole <input type="checkbox"/> Alteration (Construction) <input type="checkbox"/> Abandoned, Insufficient Supply <input type="checkbox"/> Abandoned, Poor Water Quality <input type="checkbox"/> Abandoned, other, specify _____ <input type="checkbox"/> Other, specify _____

Construction Record - Screen

Outside Diameter (cm/in)	Material (Plastic, Galvanized, Steel)	Slot No.	Depth (m/ft)	
			From	To

Water Details

Water found at Depth (m/ft)	Kind of Water:	Hole Diameter
135 (m/ft)	<input checked="" type="checkbox"/> Fresh <input checked="" type="checkbox"/> Untested <input type="checkbox"/> Gas <input type="checkbox"/> Other, specify _____	From: 0 To: 40 Diameter: 10 5/8
		From: 40 To: 155 Diameter: 6 7/8

Well Contractor and Well Technician Information

Business Name of Well Contractor: **J.R. Drilling Co. Ltd.** Well Contractor's Licence No.: **3 7 4 9**

Business Address (Street Number/Name): **C23 Mitchem Rd., R.R.#5** Municipality: **Shawville**

Province: **QC** Postal Code: **J0X 2Y0** Business E-mail Address: **info@jrwaterwelldrilling.com**

Bus. Telephone No. (inc. area code): **819 647 5184** Name of Well Technician (Last Name, First Name): **Moloughney, Brady**

Well Technician's Licence No.: **3 6 4 1** Signature of Technician and/or Contractor: _____ Date Submitted: **20130808**

Results of Well Yield Testing

After test of well yield, water was: Clear and sand free Other, specify _____

If pumping discontinued, give reason: _____

Pump intake set at (m/ft): **130**

Pumping rate (l/min / GPM): **10**

Duration of pumping: **1** hrs + **0** min

Final water level end of pumping (m/ft): **34'**

If flowing give rate (l/min / GPM): _____

Recommended pump depth (m/ft): **130**


Recommended pump rate (l/min / GPM): _____

Well production (l/min / GPM): **15**

Disinfected? Yes No

Draw Down		Recovery	
Time (min)	Water Level (m/ft)	Time (min)	Water Level (m/ft)
Static Level	25'		
1	27'	1	31.8
2	28'	2	30.5
3	29'4"	3	29.5
4	30'	4	29.0
5	30'2"	5	28.6
10	31'4"	10	28.3
15	32'2"	15	28.0
20	32'7"	20	27.5
25	33'2"	25	27.0
30	33'5"	30	26.0
40	34'	40	25.0
50	34'6"	50	25.0
60	34'	60	25.0

Map of Well Location



Comments: _____

Well owner's information package delivered: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	Date Package Delivered: 20130806	Ministry Use Only Audit No.: Z 103282
	Date Work Completed: 20130718	

Received: **AUG 12 2013**



Measurements recorded in: Metric Imperial

A296142

Tag#: A296142

S-25542

HILL EQUITY PARTNERS LTD

Address of Well Location (Street Number/Name): **60 Sappers Ridge**

County/District/Municipality: **Ottawa** City/Town/Village: **Ottawa** Province: **Ontario** Postal Code:

UTM Coordinates: Zone **18Q** Easting **456521** Northing **5016904** Municipal Plan and Sublot Number: Other:

General Colour	Most Common Material	Other Materials	General Description	Depth (m/ft) From	Depth (m/ft) To
GRY	gravel	sand	100%	0	.31
BRN	sand	silt, stones	dense	.31	2.44
BLK	peat	sand, silt	soft	2.44	4.57

Annular Space		
Depth Set at (m/ft) From	To	Type of Sealant Used (Material and Type)
0	.31	concrete/plushromant
.31	1.22	benstone
1.22	4.57	filter sand

Results of Well Yield Testing				
After test of well yield, water was:	Draw Down		Recovery	
	Time (min)	Water Level (m/ft)	Time (min)	Water Level (m/ft)
<input type="checkbox"/> Clear and sand free <input type="checkbox"/> Other, specify				
If pumping discontinued, give reason:	Static Level			
	1		1	
Pump intake set at (m/ft)	2		2	
Pumping rate (l/min / GPM)	3		3	
Duration of pumping hrs + min	4		4	
Final water level end of pumping (m/ft)	5		5	
	10		10	
If flowing give rate (l/min / GPM)	15		15	
	20		20	
Recommended pump depth (m/ft)	25		25	
Recommended pump rate (l/min / GPM)	30		30	
Well production (l/min / GPM)	40		40	
	50		50	
Disinfected? <input type="checkbox"/> Yes <input type="checkbox"/> No	60		60	


Method of Construction		Well Use	
<input type="checkbox"/> Cable Tool	<input type="checkbox"/> Diamond	<input type="checkbox"/> Public	<input type="checkbox"/> Commercial
<input type="checkbox"/> Rotary (Conventional)	<input type="checkbox"/> Jetting	<input type="checkbox"/> Domestic	<input type="checkbox"/> Municipal
<input type="checkbox"/> Rotary (Reverse)	<input type="checkbox"/> Driving	<input type="checkbox"/> Livestock	<input checked="" type="checkbox"/> Test Hole
<input type="checkbox"/> Boring	<input type="checkbox"/> Digging	<input type="checkbox"/> Irrigation	<input type="checkbox"/> Cooling & Air Conditioning
<input checked="" type="checkbox"/> Air percussion		<input type="checkbox"/> Industrial	<input type="checkbox"/> Not used
<input type="checkbox"/> Other, specify		<input type="checkbox"/> Other, specify	<input type="checkbox"/> Dewatering
			<input checked="" type="checkbox"/> Monitoring

Construction Record - Casing			Status of Well	
Inside Diameter (cm/in)	Open Hole OR Material (Galvanized, Fibreglass, Concrete, Plastic, Steel)	Wall Thickness (cm/in)	Depth (m/ft) From	To
5.20	PVC	.390	0	1.57

Construction Record - Screen			
Outside Diameter (cm/in)	Material (Plastic, Galvanized, Steel)	Slot No.	Depth (m/ft) From To
6.03	PVC	10	1.57 4.57

Water Details		Hole Diameter	
Water found at Depth (m/ft)	Kind of Water: <input type="checkbox"/> Fresh <input type="checkbox"/> Untested <input type="checkbox"/> Gas <input type="checkbox"/> Other, specify	Depth (m/ft) From	To
		0	4.57
			11.43

Well Contractor and Well Technician Information	
Business Name of Well Contractor: Strata Drilling Group	Well Contractor's Licence No.: 72241
Business Address (Street Number/Name): 179 Ringwood Dr.	Municipality: Stonerville
Province: ON Postal Code: L4A 8C1	Business E-mail Address: wrrecorder@stratasol.com
Bus. Telephone No. (inc. area code): 905 940 7919	Name of Well Technician (Last Name, First Name): Mc Coy, JAMES
Well Technician's Licence No.: 7101	Signature of Technician and/or Contractor: <i>[Signature]</i>
	Date Submitted: 2020 09 04



Well owner's information package delivered: <input type="checkbox"/> Yes <input type="checkbox"/> No	Date Package Delivered: 2020 08 27	Date Work Completed: 2020 08 27
--	---	--

Ministry Use Only	
Audit No.: 2333475	Received: OCT 06 2020



Measurements recorded in: Metric Imperial

124641

Tag#: A296141

S-25542 Page ____ of ____

Address of Well Location (Street Number/Name) **60 Sappers Ridge** Township _____ Lot _____ Concession _____

County/District/Municipality _____ City/Town/Village **Ottawa** Province **Ontario** Postal Code _____

UTM Coordinates Zone **18** Easting **456497** Northing **5016052** Municipal Plan and Sublot Number _____ Other _____

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)				
General Colour	Most Common Material	Other Materials	General Description	Depth (m/ft) From To
GRY	gravel	sand	loose	0 .31
BRN	sand	silt, stones	dense	.31 2.44
BLK	peat	sand, silt	soft	2.44 4.57

Annular Space		
Depth Set at (m/ft) From To	Type of Sealant Used (Material and Type)	Volume Placed (m³/ft³)
0 .31	concrete/flushmount	
.31 1.22	bentonite	
1.22 4.57	filter sand	

Method of Construction	Well Use
<input type="checkbox"/> Cable Tool	<input type="checkbox"/> Public
<input type="checkbox"/> Rotary (Conventional)	<input type="checkbox"/> Commercial
<input type="checkbox"/> Rotary (Reverse)	<input type="checkbox"/> Municipal
<input type="checkbox"/> Boring	<input checked="" type="checkbox"/> Test Hole
<input checked="" type="checkbox"/> Air percussion	<input type="checkbox"/> Cooling & Air Conditioning
<input type="checkbox"/> Other, specify _____	<input type="checkbox"/> Not used
	<input type="checkbox"/> Dewatering
	<input type="checkbox"/> Monitoring
	<input type="checkbox"/> Industrial
	<input type="checkbox"/> Other, specify _____


Construction Record - Casing			Status of Well		
Inside Diameter (cm/in)	Open Hole OR Material (Galvanized, Fibreglass, Concrete, Plastic, Steel)	Wall Thickness (cm/in)	Depth (m/ft) From To		
5.20	PVC	340	0 1.52	<input type="checkbox"/> Water Supply	
				<input checked="" type="checkbox"/> Replacement Well	
				<input type="checkbox"/> Test Hole	
				<input type="checkbox"/> Recharge Well	
				<input type="checkbox"/> Dewatering Well	
				<input checked="" type="checkbox"/> Observation and/or Monitoring Hole	
				<input type="checkbox"/> Alteration (Construction)	
				<input type="checkbox"/> Abandoned, Insufficient Supply	
				<input type="checkbox"/> Abandoned, Poor Water Quality	
				<input type="checkbox"/> Abandoned, other, specify _____	
				<input type="checkbox"/> Other, specify _____	

Construction Record - Screen			
Outside Diameter (cm/in)	Material (Plastic, Galvanized, Steel)	Slot No.	Depth (m/ft) From To
6.03	PVC	10	1.52 4.57

Water Details		Hole Diameter	
Water found at Depth (m/ft)	Kind of Water: <input type="checkbox"/> Fresh <input type="checkbox"/> Untested <input type="checkbox"/> Gas <input type="checkbox"/> Other, specify _____	Depth (m/ft) From To	Diameter (cm/in)
		0 4.57	11.43

Well Contractor and Well Technician Information			
Business Name of Well Contractor Strata Drilling Group		Well Contractor's Licence No. 7241	
Business Address (Street Number/Name) 129 Ringwood Dr.		Municipality Stouffville	
Province ON	Postal Code L4A 8C1	Business E-mail Address wrecords@strata501.com	
Bus. Telephone No. (inc. area code) 905 940 7919		Name of Well Technician (Last Name, First Name) McLoy, James	
Well Technician's Licence No. 7107		Signature of Technician and/or Contractor <i>[Signature]</i>	
		Date Submitted 20200904	

Results of Well Yield Testing					
After test of well yield, water was:		Draw Down		Recovery	
<input type="checkbox"/> Clear and sand free		Time (min)	Water Level (m/ft)	Time (min)	Water Level (m/ft)
<input type="checkbox"/> Other, specify _____					
If pumping discontinued, give reason:		Static Level			
		1		1	
Pump intake set at (m/ft)		2		2	
Pumping rate (l/min / GPM)		3		3	
Duration of pumping ____ hrs + ____ min		4		4	
Final water level end of pumping (m/ft)		5		5	
		10		10	
If flowing give rate (l/min / GPM)		15		15	
		20		20	
Recommended pump depth (m/ft)		25		25	
Recommended pump rate (l/min / GPM)		30		30	
Well production (l/min / GPM)		40		40	
		50		50	
Disinfected? <input type="checkbox"/> Yes <input type="checkbox"/> No		60		60	



Well owner's information package delivered		Date Package Delivered		Ministry Use Only	
<input type="checkbox"/> Yes	<input type="checkbox"/> No	Y Y Y Y	M M D D	Audit No.	2333474
		Date Work Completed		Received	
		20200917		20200917	



Measurements recorded in: Metric Imperial

A296140

Tag#: A296140

S-25542 Page of

SIGNAL HILL EQUITY PARTNERS LTD.

Address of Well Location (Street Number/Name) 60 Sappers Ridge Township _____ Lot _____ Concession _____

County/District/Municipality _____ City/Town/Village Starkville Province **Ontario** Postal Code _____

UTM Coordinates: Zone 18Q Easting 456436 Northing 5016842 Municipal Plan and Sublot Number _____ Other _____

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)				
General Colour	Most Common Material	Other Materials	General Description	Depth (m/ft) From To
GRY	gravel	sand	loose	0 .31
BRN	sand	silt, stones	dense	.31 1.52
GRY	silt	sand	soft	1.52 4.57
BRN	silt	clay	soft	4.57 5.18

Annular Space		
Depth Set at (m/ft) From To	Type of Sealant Used (Material and Type)	Volume Placed (m³/ft³)
0 .31	concrete/plushment	
.31 1.83	bentonite	
1.83 5.18	filter sand	

Method of Construction	Well Use
<input type="checkbox"/> Cable Tool	<input type="checkbox"/> Public
<input type="checkbox"/> Rotary (Conventional)	<input type="checkbox"/> Commercial
<input type="checkbox"/> Rotary (Reverse)	<input type="checkbox"/> Municipal
<input type="checkbox"/> Boring	<input type="checkbox"/> Livestock
<input checked="" type="checkbox"/> Air percussion	<input type="checkbox"/> Irrigation
<input type="checkbox"/> Other, specify _____	<input type="checkbox"/> Industrial
	<input type="checkbox"/> Other, specify _____
	<input type="checkbox"/> Not used
	<input type="checkbox"/> Dewatering
	<input checked="" type="checkbox"/> Test Hole
	<input checked="" type="checkbox"/> Monitoring
	<input type="checkbox"/> Cooling & Air Conditioning


Construction Record - Casing				Status of Well	
Inside Diameter (cm/in)	Open Hole OR Material (Galvanized, Fibreglass, Concrete, Plastic, Steel)	Wall Thickness (cm/in)	Depth (m/ft)		<input type="checkbox"/> Water Supply <input type="checkbox"/> Replacement Well <input checked="" type="checkbox"/> Test Hole <input type="checkbox"/> Recharge Well <input type="checkbox"/> Dewatering Well <input checked="" type="checkbox"/> Observation and/or Monitoring Hole <input type="checkbox"/> Alteration (Construction) <input type="checkbox"/> Abandoned, Insufficient Supply <input type="checkbox"/> Abandoned, Poor Water Quality <input type="checkbox"/> Abandoned, other, specify _____ <input type="checkbox"/> Other, specify _____
			From	To	
5.20	PVC	.390	0	2.13	

Construction Record - Screen				
Outside Diameter (cm/in)	Material (Plastic, Galvanized, Steel)	Slot No.	Depth (m/ft)	
			From	To
6.03	PVC	10	2.13	5.18

Water Details		Hole Diameter	
Water found at Depth (m/ft)	Kind of Water: <input type="checkbox"/> Fresh <input type="checkbox"/> Untested <input type="checkbox"/> Gas <input type="checkbox"/> Other, specify _____	Depth (m/ft) From To	Diameter (cm/in)
		0 5.18	11.43

Well Contractor and Well Technician Information	
Business Name of Well Contractor <u>Stark Drilling Group</u>	Well Contractor's Licence No. <u>72411</u>
Business Address (Street Number/Name) <u>129 Ringwood Dr.</u>	Municipality <u>Starkville</u>
Province <u>ON</u>	Postal Code <u>L4A8C1</u>
Business E-mail Address <u>wrecords@starksoil.com</u>	
Bus. Telephone No. (inc. area code) <u>9059407919</u>	
Name of Well Technician (Last Name, First Name) <u>M. JAMES</u>	
Well Technician's Licence No. <u>7107</u>	Signature of Technician and/or Contractor <i>[Signature]</i>
Date Submitted <u>20200904</u>	

Results of Well Yield Testing					
After test of well yield, water was:		Draw Down		Recovery	
<input type="checkbox"/> Clear and sand free <input type="checkbox"/> Other, specify _____		Time (min)	Water Level (m/ft)	Time (min)	Water Level (m/ft)
If pumping discontinued, give reason:		Static Level			
Pump intake set at (m/ft)		1		1	
Pumping rate (l/min / GPM)		2		2	
Duration of pumping hrs + min		3		3	
Final water level end of pumping (m/ft)		4		4	
If flowing give rate (l/min / GPM)		5		5	
Recommended pump depth (m/ft)		10		10	
Recommended pump rate (l/min / GPM)		15		15	
Well production (l/min / GPM)		20		20	
Disinfected? <input type="checkbox"/> Yes <input type="checkbox"/> No		25		25	
		30		30	
		40		40	
		50		50	
		60		60	



Comments:

Well owner's information		Date Package Delivered		Ministry Use Only	
Information package delivered	<input type="checkbox"/> Yes <input type="checkbox"/> No	Y Y Y Y M M D D		Audit No.	<u>2333473</u>
		Date Work Completed	<u>20200917</u>	Received	<u>OCT 06 2020</u>



Measurements recorded in: Metric Imperial

A251312 MWI

Page 1 of 1

Well Owner's Information

First Name Last Name / Organization E-mail Address Well Constructed by Well Owner

Mailing Address (Street Number/Name) Municipality Province Postal Code Telephone No. (inc. area code)

100 CITIGATE DRIVE OTTAWA ON K2J6K7 613 822 18167

Well Location

Address of Well Location (Street Number/Name) Township Lot Concession

300 SOMME STREET OTTAWA Ontario

UTM Coordinates Zone Easting Northing Municipal Plan and Sublot Number Other

NAD 83 18 45 66 85 50 17 4 23

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

Table with columns: General Colour, Most Common Material, Other Materials, General Description, Depth (m/ft) From, To. Row 1: BACKFILL, 0, 4.62

Annular Space and Results of Well Yield Testing tables. Annular Space: Depth Set at (m/ft) From 0 To 2.4, Type of Sealant Used BENTONITE, Volume Placed. Results of Well Yield Testing: Draw Down and Recovery table with 6 rows.

Method of Construction and Well Use tables. Method of Construction: Cable Tool, Rotary, Boring, etc. Well Use: Public, Commercial, Monitoring, etc.

Construction Record - Casing and Status of Well tables. Construction Record - Casing: Inside Diameter 5.08, Material PVC, Wall Thickness SCHED 40, Depth 0 to 3.05. Status of Well: Water Supply, Replacement Well, etc.


Construction Record - Screen and Map of Well Location. Construction Record - Screen: Outside Diameter 5.88, Material PVC, Slot No. 25, Depth 3.05 to 4.57. Map of Well Location: Hand-drawn map showing well location relative to RIDGWAY ROAD and SOMME ST.

Water Details and Hole Diameter tables. Water Details: Water found at Depth 2.34 (m/ft), Kind of Water: Fresh. Hole Diameter: Depth 0 to 4.62, Diameter 20.3.

Well Contractor and Well Technician Information. Bl George Downing Estate Drilling #1844, 410 rue Principale Grenville-sur-la-Rouge, QC J0V 1B0, (819) 242-6469, Downing, Stephen.

Well Technician's Licence No. 33216, Signature of Technician and/or Contractor, Date Submitted 20200918.

Ministry Use Only. Audit No. Z340902, Received OCT 16 2020.



OCT 16 2000
C-1844
E340902

Measurements recorded in: Metric Imperial

Well Owner's Information

First Name: _____ Last Name/Organization: **TECHO-BLOC INC.** E-mail Address: _____ Well Constructed by Well Owner

Mailing Address (Street Number/Name): **#5255 Albert Millichamp** Municipality: **Saint-Hubert** Province: **Quebec** Postal Code: **J3H 8Z8** Telephone No. (inc. area code): _____

Well Location

Address of Well Location (Street Number/Name): **5123 Hawthorne Road** Township: **Gloucester** Lot: **27** Concession: **6**

County/District/Municipality: **Ottawa Carleton** City/Town/Village: **Ottawa** Province: **Ontario** Postal Code: _____

UTM Coordinates Zone: **18** Easting: **457054** Northing: **5016813** Municipal Plan and Sublot Number: **4M-1388 Part 23-4/4R-32280 Block 2**

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

General Colour	Most Common Material	Other Materials	General Description	Depth (m)
				From To
	Sandy clay & Gravel			0' 15'
Grey	Limestone			15' 80'
Grey & White	Sandstone			80' 83'
Grey & White	Sandstone			83' 116'
Grey & White	Sandstone			116' 122'

Annular Space

Depth Set at (m)	Type of Sealant Used (Material and Type)	Volume Placed (m ³)
From To		
41' 31'	Neat cement	18.7
31' 0'	Bentonite slurry	16.8

Method of Construction

Cable Tool Diamond Public Commercial Not used

Rotary (Conventional) Jetting Domestic Municipal Dewatering

Rotary (Reverse) Driving Livestock Test Hole Monitoring

Boring Digging Irrigation Cooling & Air Conditioning

Air percussion Industrial Other, specify _____

Construction Record - Casing

Inside Diameter (cm)	Open Hole OR Material (Galvanized, Fibreglass, Concrete, Plastic, Steel)	Wall Thickness (cm)	Depth (m)	Status of Well
			From To	
6 1/4"	Steel	.188"	+2' 41'	<input checked="" type="checkbox"/> Water Supply
6"	Open Hole		41' 122'	<input type="checkbox"/> Replacement Well

Construction Record - Screen

Outside Diameter (cm/in)	Material (Plastic, Galvanized, Steel)	Slot No.	Depth (m)
			From To

Water Details

Water found at Depth (m)	Kind of Water: <input type="checkbox"/> Fresh <input checked="" type="checkbox"/> Untested	Depth (m)	Diameter (cm/in)
		From To	
83 (m)	<input checked="" type="checkbox"/> Gas <input type="checkbox"/> Other, specify _____		
116 (m)	<input checked="" type="checkbox"/> Gas <input type="checkbox"/> Other, specify _____	0' 41'	1 3/4"
	<input type="checkbox"/> Fresh <input type="checkbox"/> Untested	41' 122'	6"

Well Contractor and Well Technician Information

Business Name of Well Contractor: **Air Rock Drilling Co. Ltd.** Well Contractor's Licence No.: **7881**

Business Address (Street Number/Name): **6659 Franktown Road** Municipality: **Richmond**

Province: **ON** Postal Code: **K0A 2Z0** Business E-mail Address: **air-rock@sympatico.ca**

Bus. Telephone No. (inc. area code): **613-8382170** Name of Well Technician (Last Name, First Name): **Hogan, Dan**

Well Technician's Licence No.: **T3058** Signature of Technician and/or Contractor: _____ Date Submitted: **2020 08 31**

Results of Well Yield Testing

After test of well yield, water was: Clear and sand free Other, specify **Not tested**

If pumping discontinued, give reason: _____

Pump intake set at (m): **100**

Pumping rate (l/min): **20**

Duration of pumping: _____ hrs + _____ min

Final water level end of pumping (m): **33.5**

If flowing give rate (l/min/GPM): _____


Recommended pump depth (m): **100'**

Recommended pump rate (l/min/GPM): **20**

Well production (l/min/GPM): **20**

Disinfected? Yes No

Time (min)	Draw Down		Recovery	
	Water Level (m)	Time (min)	Water Level (m)	Time (min)
1	26.5	1	26.5	
2	30.5	2	26.5	
3	30.8	3	26.5	
4	31.1	4	26.5	
5	31.3	5	26.5	
10	31.9	10	26.5	
15	32.3	15	26.5	
20	32.6	20	26.5	
25	32.9	25	26.5	
30	33.1	30	26.5	
40	33.3	40	26.5	
50	33.5	50	26.5	
60	33.5	60	26.5	



Comments: **3/4 HP - 15 GPM Set @ 100 FT**

Well owner's information package delivered: Yes No

Date Package Delivered: **2020 08 20**

Date Work Completed: **2020 08 20**

Ministry Use Only

Audit No.: **2344019**

Received: **OCT 30 2020**

Measurements recorded in: Metric Imperial

A305146

Page of

Well Owner's Information

First Name, Last Name/Organization (COPART), E-mail Address, Mailing Address (14185 Dallas Parkway Suite 300), Municipality (Dallas, Texas), Province (USA), Postal Code (75254), Telephone No.

Well Location

Address of Well Location (300 Somme Street), Township (Gloucester), Lot (P11 26027 6 R.F.), Concession (Ontario), County/District/Municipality (Ottawa Carleton), UTM Coordinates (Zone 18, Easting 456627, Northing 5017085, Municipal Plan and Sublot Number 4M-1388)

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

Table with columns: General Colour, Most Common Material, Other Materials, General Description, Depth From, Depth To. Rows include Sand, Clay, and Gravel, and Sandstone w/ Grey limestone mix.

Annular Space table with columns: Depth Set at (m), Type of Sealant Used (Neat cement, Bentonite slurry), Volume Placed (m³).

Results of Well Yield Testing table with columns: Time (min), Water Level (m), Recovery Time (min), Water Level (m). Includes pumping rate (20 GPM) and static level (25.5').


Method of Construction and Well Use checkboxes. Includes Cable Tool, Rotary, Boring, Air percussion, and various well uses like Domestic, Commercial, etc.

Construction Record - Casing table with columns: Inside Diameter, Open Hole OR Material, Wall Thickness, Depth (From/To). Rows for 6 1/4" Steel and 6 1/8" Open Hole.

Construction Record - Screen table with columns: Outside Diameter, Material, Slot No., Depth (From/To).

Water Details and Hole Diameter tables. Water found at depths 103m, 134m. Hole diameters 9 3/4" and 6 1/8".

Well Contractor and Well Technician Information. Contractor: Air Rock Drilling Co. Ltd. Technician: Hogan, Dan. License No. T3058.



Comments: 3/4 HP 15 GPM Set @ 100 FT. Ministry Use Only section with Audit No. 2344053 and Date Work Completed 2020 09 02.

Measurements recorded in: Metric Imperial

A295342

Page ___ of ___

Well Owner's Information

First Name, Last Name/Organization (Paul Lalonde Holdings Inc), E-mail Address, Mailing Address (5146 Bank Street), Municipality (Ottawa), Province (ON), Postal Code (K1X 1G8), Telephone No.

Well Location

Address of Well Location (5123 Hawthorne Road), Township (Gloucester), Lot (27), Concession (6), County/District/Municipality (Ottawa Carleton), City/Town/Village (Ottawa), Province (Ontario), UTM Coordinates, Municipal Plan and Sublot Number (4M-1388), Other (Parts 2,3,4)

Overburden and Bedrock Materials/Abandonment Sealing Record

Table with columns: General Colour, Most Common Material, Other Materials, General Description, Depth From, Depth To. Includes entries for Sandy Till & Boulders, Limestone, Sandstone.

Annular Space table with columns: Depth Set at From, To, Type of Sealant Used, Volume Placed. Includes entries for Neat cement and Bentonite slurry.

Method of Construction and Well Use section with checkboxes for Cable Tool, Rotary, Boring, Air percussion, and various well uses like Domestic, Commercial, etc.


Construction Record - Casing table with columns: Inside Diameter, Open Hole OR Material, Wall Thickness, Depth From, To, Status of Well. Includes entries for Steel and Open Hole casings.

Construction Record - Screen table with columns: Outside Diameter, Material, Slot No., Depth From, To.

Water Details and Hole Diameter section with columns for water found at depth, kind of water, and hole diameter.

Well Contractor and Well Technician Information section with fields for Business Name, Licence No., Address, and Technician Name.

Results of Well Yield Testing table with columns: Time, Water Level, Recovery. Includes pumping test data and static level.



Comments: 1 HP - 20 GPM SET @ 100 FT

Bottom section with fields for Well owner's information, Date Package Delivered, Date Work Completed, and Ministry Use Only (Audit No. 2344069, Received OCT 30 2020).

Measurements recorded in: Metric Imperial

Well Owner's Information

First Name: CONSOLIDATED WATER (OTTAWA) (P/O TOMLINSON) E-mail Address: [] Well Constructed by Well Owner

Mailing Address (Street Number/Name): 100 CITIGARE DRIVE Municipality: OTTAWA Province: ON Postal Code: K2J 6K7 Telephone No. (inc. area code):

Well Location

Address of Well Location (Street Number/Name): 301 SOMME ST. Township: GLOUCESTER (RF) Lot: 26 Concession: 6

County/District/Municipality: OTTAWA City/Town/Village: OTTAWA Province: Ontario Postal Code: K1G 3W4

JTM Coordinates: Zone Easting Northing NAD 83: SEE TAG BELOW Municipal Plan and Sublot Number: Other:

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

Table with columns: Well, DIA (mm), STATIC WATER LEVEL (m), GPS EASTING, GPS NORTHING, DEPTH (m). Rows 1-4 with data for well diameters (50mm, 50mm, 150mm, 50mm) and depths (3.13, 3.3A, 6.74, 6.70).

Annular Space table with columns: Depth Set at (m/ft) From To, Type of Sealant Used (Material and Type), Volume Placed (m³/ft³). Includes handwritten notes: SEE ABOVE, PEZ PLUG & HOLE PLUG, BENTONITE GROUT.

Method of Construction and Well Use table with checkboxes for Cable Tool, Rotary, Boring, etc., and Public, Commercial, Municipal, etc.

Construction Record - Casing table with columns: Inside Diameter (cm/in), Open Hole OR Material, Wall Thickness (cm/in), Depth (m/ft) From To. Includes handwritten note: SEE ABOVE.


Construction Record - Screen table with columns: Outside Diameter (cm/in), Material (Plastic, Galvanized, Steel), Slot No., Depth (m/ft) From To. Includes handwritten note: SEE ABOVE.

Water Details and Hole Diameter table with columns: Water found at Depth (m/ft), Kind of Water, Hole Diameter (m/ft) From To, Diameter (cm/in). Includes handwritten note: SEE ABOVE.

Well Contractor and Well Technician Information: Business Name of Well Contractor: STANTON DRILLING INC. Well Contractor's Licence No.: 4875 Business Address: 157 FIVE ARCHES DR, BOX 29, Pakenham, ON N2A 2X0 Business E-mail Address: scambn.dntl@icbell.net

Name of Well Technician (Last Name, First Name): STANTON, PETER Well Technician's Licence No.: 0086 Signature of Technician: [Signature] Date Submitted: 2022/10

Results of Well Yield Testing table with columns: Draw Down (Time, Water Level), Recovery (Time, Water Level). Includes handwritten notes: SEE ABOVE, Pump intake set at 2m, etc.



Well owner's information package delivered: [] Yes [x] No Date Package Delivered: YYY Y M M D D Date Work Completed: 20220625 Ministry Use Only: Audit No: 3375700

OFFICIAL CERTIFICATE OF ANALYSIS : 4432589

WORK REQUEST : 100377108

Report Date : 2025-08-20

Paterson Group

9 Auriga Dr
Nepean, Ontario
K2E 7T9
Attention : Alex Schopf

Reception Date : 2025-08-12

Project : PH5075

Sampler : NA

PO Number : 63782

Temperature : 9 °C

Analysis	Quantity	External Method
Alkalinity (Water, Automated)	1	Modified from SM 2320 B
Ammonia, Total (Water, Colorimetry)	1	Modified from EPA 350.1
Chloride (Water, IC)	1	Modified from SM 4110 B and C
Colour, True (Water, Spectrophotometry)	1	Modified from SM 2120 C
Conductivity (Water, Automated)	1	Modified from SM 2510 B
DOC (Water, IR)	1	Modified from SM 5310 B
Escherichia coli (DC Plate)	1	Modified from MECP E3407
Fluoride (Water, Auto/ISE)	1	Modified from SM 4500-F A and 4500-F C
Hardness (Water, Calculation Only)	1	SM 2340 B
Ion Balance (Water, Calculation)	1	Modified from SM1030 E
Metals Scan (Water, ICP/MS)	1	Modified from EPA 200.8
Metals Scan (Water, ICP/OES)	1	Modified from SM 3120 B
Nitrate (Water, IC)	1	Modified from SM 4110 B and C
Nitrite (Water, IC)	1	Modified from SM 4110 B and C
pH (25°C) (Water, Automated)	1	Modified from SM 4500-H+ B
Phenols (Water, Colorimetry)	1	Modified from EPA 420.2
Sulphate (Water, IC)	1	Modified from SM 4110 B and C
Sulphide (Water, Colorimetry)	1	Modified from SM 4500-S2 D
Tannin and Lignin (Water, Spec)	1	Modified from SM 5550 B
TDS (Estimated)	1	Modified from SM 2510 A
Total Coliforms (DC Plate)	1	Modified from MECP E3407
Total Kjeldahl Nitrogen (Water, Colorimetry)	1	Modified from EPA 351.2
Turbidity (Water, Turbidimeter)	1	Modified from SM 2130 B
VOCs (Water, GC/MS)	1	Modified from EPA 8260

Criteria :

A : Ontario Regulation 169/03 (Non-Regulated Drinking Water)

Sample status upon receipt :

8908634

Compliant

Certificate Comments :

Revision 1: This is an amendment and supersedes certificate 4431403. Full VOC scan added as per client's request.

8908634

N-NO2 and N-NO3 MRL increased due to matrix interference, dilution was done.

Notes :

- All analysis is completed at Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) unless otherwise stated.
- Eurofins Environment Testing Canada Inc. is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on the scope of accreditation. The scope is available at <https://directory.cala.ca/>
- Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline or regulatory limits listed on this report are provided for ease of use (informational purposes) only. Eurofins recommends consulting the official guideline or regulation as required. Unless otherwise stated, measurement uncertainty is not taken into account when determining guideline or regulatory exceedances.

Legend :

RL : Reporting limit

N/A : Not applicable

* : Analysis conducted by external subcontracting

QC : Reference material (QC)

1 : Results in annex

^ : Analysis not accredited

OFFICIAL CERTIFICATE OF ANALYSIS - EXCEEDENCE SUMMARY

 Client : Paterson Group
 Project : PH5075

Reception Date : 2025-08-12

Eurofins Sample No	Client Sample Identification	Analyte	Result	Units	Exceeded Criteria		
					A	B	C
Hardness (Water, Calculation Only)							
8908634	TW1 - GW1	Hardness as CaCO3 (Calculation)	567	mg/L	80-100		
Metals Scan (Water, ICP/MS)							
8908634	TW1 - GW1	Iron	0.55	mg/L	0.3		
8908634	TW1 - GW1	Manganese	0.18	mg/L	0.05		
TDS (Estimated)							
8908634	TW1 - GW1	TDS (Estimated)^	787	mg/L	500		

OFFICIAL CERTIFICATE OF ANALYSIS - RESULTS

Client : Paterson Group
Project : PH5075

Reception Date: 2025-08-12

		Eurofins Sample No :		8908634					
		Matrix :		Groundwater					
		Sampling Date :		2025-08-12					
		Client Sample Identification :		TW1 - GW1					
Anions	RL	Unit	Criteria						
			A	B	C				
Chloride	0.5	mg/L	250			78.8			
Sulphate	1	mg/L	500			285			

		Eurofins Sample No :		8908634					
		Matrix :		Groundwater					
		Sampling Date :		2025-08-12					
		Client Sample Identification :		TW1 - GW1					
Calculations	RL	Unit							
Ion Balance (Calculation)^	0.1		1.01						

		Eurofins Sample No :		8908634					
		Matrix :		Groundwater					
		Sampling Date :		2025-08-12					
		Client Sample Identification :		TW1 - GW1					
General Chemistry	RL	Unit	Criteria						
			A	B	C				
Alkalinity (as CaCO3)	5	mg/L	500			306			
Colour (True)	2	TCU				<2			
Conductivity @ 25°C	5	µS/cm				1210			
Dissolved Organic Carbon	0.5	mg/L	5			2.2			
Fluoride	0.1	mg/L	1.5			0.35			
Hardness as CaCO3 (Calculation)	1	mg/L	80-100			567			
pH @ 25°C	1		6.5-8.5			8.20			
Phenols-4AAP	0.001	mg/L				<0.001			
Sulphide (S2-)	0.01	mg/L	0.05			<0.01			
Tannin and Lignin	0.1	mg/L				0.1			
TDS (Estimated)^	5	mg/L	500			787			
Turbidity	0.1	NTU	5			2.3			

OFFICIAL CERTIFICATE OF ANALYSIS - RESULTS

Client : Paterson Group
Project : PH5075

Reception Date: 2025-08-12

		Eurofins Sample No :		8908634					
		Matrix :		Groundwater					
		Sampling Date :		2025-08-12					
		Client Sample Identification :		TW1 - GW1					
Metals	RL	Unit	Criteria						
			A	B	C				
Metals Scan (Water, ICP/MS)									
Aluminum	0.01	mg/L	0.1			<0.01			
Antimony	0.0005	mg/L	0.006			<0.0005			
Arsenic	0.001	mg/L	0.01			<0.001			
Barium	0.001	mg/L	1			0.087			
Beryllium	0.0005	mg/L				<0.0005			
Boron	0.01	mg/L	5			0.24			
Cadmium	0.0001	mg/L	0.005			<0.0001			
Chromium	0.001	mg/L	0.05			<0.001			
Cobalt	0.0002	mg/L				<0.0002			
Copper	0.001	mg/L	1			<0.001			
Iron	0.03	mg/L	0.3			0.55			
Lead	0.001	mg/L	0.01			<0.001			
Manganese	0.01	mg/L	0.05			0.18			
Mercury	0.0001	mg/L	0.001			<0.0001			
Molybdenum	0.005	mg/L				0.018			
Nickel	0.005	mg/L				<0.005			
Selenium	0.001	mg/L	0.05			<0.001			
Silver	0.0001	mg/L				<0.0001			
Strontium	0.001	mg/L				6.25			
Thallium	0.0001	mg/L				<0.0001			
Uranium	0.001	mg/L	0.02			<0.001			
Vanadium	0.001	mg/L				<0.001			
Zinc	0.01	mg/L	5			<0.01			
Metals Scan (Water, ICP/OES)									
Calcium	1	mg/L				128			
Magnesium	1	mg/L				60			
Potassium	1	mg/L				8			
Sodium	1	mg/L	200			65			

		Eurofins Sample No :		8908634					
		Matrix :		Groundwater					
		Sampling Date :		2025-08-12					
		Client Sample Identification :		TW1 - GW1					
Microbiology	RL	Unit	Criteria						
			A	B	C				
Escherichia coli (DC)	0	CFU/100mL	0			0			
Total Coliforms (DC)	0	CFU/100mL	0			0			

OFFICIAL CERTIFICATE OF ANALYSIS - RESULTS

Client : Paterson Group
 Project : PH5075

Reception Date: 2025-08-12

			Eurofins Sample No :			8908634				
			Matrix :			Groundwater				
			Sampling Date :			2025-08-12				
			Client Sample Identification :			TW1 - GW1				
Nutrients	RL	Unit	Criteria							
			A	B	C					
Ammonia (Total, as Nitrogen)	0.02	mg/L				0.240				
Nitrate (as Nitrogen)	0.1	mg/L	10.0			<0.5				
Nitrite (as Nitrogen)	0.1	mg/L	1.0			<0.5				
Total Kjeldahl Nitrogen	0.1	mg/L				0.332				

OFFICIAL CERTIFICATE OF ANALYSIS - RESULTS

Client : Paterson Group
Project : PH5075

Reception Date: 2025-08-12

			Eurofins Sample No : 8908634						
			Matrix : Groundwater						
			Sampling Date : 2025-08-12						
			Client Sample Identification : TW1 - GW1						
Volatile Organic Compounds	RL	Unit	Criteria						
			A	B	C				
VOCs (Water, GC/MS)									
1,1,1,2-Tetrachloroethane	0.5	ug/L				<0.5			
1,1,1-Trichloroethane	0.4	ug/L				<0.4			
1,1,2,2-Tetrachloroethane	0.5	ug/L				<0.5			
1,1,2-Trichloroethane	0.4	ug/L				<0.4			
1,1-Dichloroethane	0.4	ug/L				<0.4			
1,1-Dichloroethene	0.5	ug/L	14			<0.5			
1,2,4-Trichlorobenzene	0.5	ug/L				<0.5			
1,2-Dibromoethane	0.2	ug/L				<0.2			
1,2-Dichlorobenzene	0.4	ug/L	200			<0.4			
1,2-Dichloroethane	0.2	ug/L	5			<0.2			
1,2-dichloroethene, cis + trans^	0.5	ug/L				<0.5			
1,2-Dichloropropane	0.5	ug/L				<0.5			
1,3,5-Trimethylbenzene	0.3	ug/L				<0.3			
1,3-Dichlorobenzene	0.4	ug/L				<0.4			
1,3-Dichloropropene, cis + trans	0.5	ug/L				<0.5			
1,4-Dichlorobenzene	0.4	ug/L	5			<0.4			
Acetone	5	ug/L				<5			
Benzene	0.5	ug/L	1			<0.5			
Bromodichloromethane	0.3	ug/L				<0.3			
Bromoform	0.4	ug/L				<0.4			
Bromomethane	0.5	ug/L				<0.5			
Carbon tetrachloride	0.2	ug/L	2			<0.2			
Chloroethane	0.5	ug/L				<0.5			
Chloroform	0.5	ug/L				<0.5			
Chloromethane	0.2	ug/L				<0.2			
cis-1,2-Dichloroethene	0.4	ug/L				<0.4			
cis-1,3-Dichloropropene	0.5	ug/L				<0.5			
Dibromochloromethane	0.3	ug/L				<0.3			
Dichlorodifluoromethane	0.5	ug/L				<0.5			
Dichloromethane	4	ug/L	50			<4			
Diethyl ether	5	ug/L				<5			
Ethylbenzene	0.5	ug/L	140			<0.5			
Hexane	5	ug/L				<5			
m/p-Xylene	0.4	ug/L				<0.4			
Methyl butyl ketone (MBK)	5	ug/L				<5			
Methyl ethyl ketone (MEK)	2	ug/L				<2			
Methyl isobutyl ketone (MIBK)	5	ug/L				<5			
Methyl tert-butyl ether (MTBE)	2	ug/L				<2			
Monochlorobenzene	0.5	ug/L	80			<0.5			
o-Xylene	0.4	ug/L				<0.4			
Styrene	0.5	ug/L				<0.5			
Tetrachloroethylene (PCE)	0.3	ug/L	10			<0.3			
Toluene	0.4	ug/L	60			<0.4			
trans-1,2-dichloroethene	0.4	ug/L				<0.4			
trans-1,3-dichloropropene	0.5	ug/L				<0.5			


OFFICIAL CERTIFICATE OF ANALYSIS - RESULTS

Client : Paterson Group
Project : PH5075


Reception Date: 2025-08-12


		Eurofins Sample No :		8908634					
		Matrix :		Groundwater					
		Sampling Date :		2025-08-12					
		Client Sample Identification :		TW1 - GW1					
Volatile Organic Compounds	RL	Unit	Criteria						
			A	B	C				
Trichloroethylene (TCE)	0.3	ug/L	5			<0.3			
Trichlorofluoromethane	0.5	ug/L				<0.5			
Vinyl chloride	0.2	ug/L	1			<0.2			
Xylene (Total)	0.5	ug/L	90			<0.5			
1,2-dichloroethane-d4 (surrogate)	0	%				85			
4-bromofluorobenzene (surrogate)	0	%				111			
Toluene-d8 (surrogate)	0	%				115			

Approved by :


Adrine Thomas,
Inorganic supervisor, Ottawa

Approved by :


Patrick Jacques, B.Sc., C.Chem,
Environmental Chemist, Ottawa



OFFICIAL CERTIFICATE OF ANALYSIS - QUALITY CONTROL

Client : Paterson Group
Project : PH5075

Reception Date: 2025-08-12

Parameter	Unit	RL	Blank	QC		Matrix Spike		Duplicate	
				Recovery %	Range %	Recovery %	Range %	RPD %	Range %
Alkalinity (Water, Automated)									
<i>Method : Alkalinity (water, titration to pH 4.5, automated). Internal method: OTT-I-AT-WI45398.</i>									
Alkalinity (as CaCO3)	mg/L	5	<5	97	95-105			2	0-20
Associated Samples : 8908634								Prep Date: 2025-08-15 Analysis Date: 2025-08-18	
Ammonia, Total (Water, Colorimetry)									
<i>Method : Ammonia (Water, Colorimetry). Internal method: OTT-I-NUT-WI46201.</i>									
Ammonia (Total, as Nitrogen)	mg/L	0.02	<0.020	98	80-120	105	80-120	2	0-20
Associated Samples : 8908634								Prep Date: 2025-08-13 Analysis Date: 2025-08-13	
Chloride (Water, IC)									
<i>Method : Anions (Water, Ion Chromatography). Internal method: OTT-I-IC-WI45985.</i>									
Chloride	mg/L	0.5	<0.5	106	80-120	106	80-120	2	0-20
Associated Samples : 8908634								Prep Date: 2025-08-14 Analysis Date: 2025-08-14	
Colour, True (Water, Spectrophotometry)									
<i>Method : Colour (Water, Spectrophotometric). Internal method: OTT-I-SPEC-WI45980.</i>									
Colour (True)	TCU	2	<2	91	78-116			-	0-40
Associated Samples : 8908634								Prep Date: 2025-08-13 Analysis Date: 2025-08-13	
Conductivity (Water, Automated)									
<i>Method : Conductivity (Water, Autotitrator). Internal Method: OTT-I-AT-WI45398.</i>									
Conductivity @ 25°C	uS/cm	5	<5	99	98-102			1	0-20
Associated Samples : 8908634								Prep Date: 2025-08-15 Analysis Date: 2025-08-18	
DOC (Water, IR)									
<i>Method : Organic carbon (water, IR, combustion). Internal method: OTT-I-DEM-WI46148.</i>									
Dissolved Organic Carbon	mg/L	0.5	<0.5	96	88-112	92	80-120	-	0-15
Associated Samples : 8908634								Prep Date: 2025-08-13 Analysis Date: 2025-08-14	
Escherichia coli (DC Plate)									
<i>Method : Total Coliforms and E.Coli by MF (Water, DC plate). Internal method: OTT-M-BAC-WI45296.</i>									
Escherichia coli (DC)	CFU/100mL	0	0					-	0-30
Associated Samples : 8908634								Prep Date: 2025-08-12 Analysis Date: 2025-08-13	
Fluoride (Water, Auto/ISE)									
<i>Method : Fluoride by autotitrator, ion selective electrode. Internal method: OTT-I-AT-WI45398.</i>									
Fluoride	mg/L	0.1	<0.10	96	90-110			1	0-20
Associated Samples : 8908634								Prep Date: 2025-08-15 Analysis Date: 2025-08-18	

OFFICIAL CERTIFICATE OF ANALYSIS - QUALITY CONTROL

Client : Paterson Group
Project : PH5075

Reception Date: 2025-08-12

Parameter	Unit	RL	Blank	QC		Matrix Spike		Duplicate	
				Recovery %	Range %	Recovery %	Range %	RPD %	Range %
Metals Scan (Water, ICP/MS)									
<i>Method : Metals (Water, ICP/MS). Internal method: AMMTFQE1.</i>									
Aluminum	mg/L	0.01	<0.01	100	80-120	103	70-130	9	0-20
Antimony	mg/L	0.0005	<0.0005	86	80-120	80	70-130	-	0-20
Arsenic	mg/L	0.001	<0.001	99	80-120	92	70-130	-	0-20
Barium	mg/L	0.001	<0.001	100	80-120	71	70-130	8	0-20
Beryllium	mg/L	0.0005	<0.0005	105	80-120	109	70-130	-	0-20
Boron	mg/L	0.01	<0.01	100	80-120	110	70-130	-	0-20
Cadmium	mg/L	0.0001	<0.0001	104	80-120	95	70-130	-	0-20
Chromium	mg/L	0.001	<0.001	110	80-120	95	70-130	-	0-20
Cobalt	mg/L	0.0002	<0.0002	104	80-120	89	70-130	-	0-20
Copper	mg/L	0.001	<0.001	100	80-120	84	70-130	12	0-20
Iron	mg/L	0.03	<0.03	100	80-120	81	70-130	11	0-20
Lead	mg/L	0.001	<0.001	100	80-120	86	70-130	-	0-20
Manganese	mg/L	0.01	<0.01	100	80-120	91	70-130	-	0-20
Mercury	mg/L	0.0001	<0.0001	107	80-120	100	70-130	-	0-20
Molybdenum	mg/L	0.005	<0.005	90	80-120	90	70-130	-	0-20
Nickel	mg/L	0.005	<0.005	100	80-120	88	70-130	-	0-20
Selenium	mg/L	0.001	<0.001	100	80-120	94	70-130	-	0-20
Silver	mg/L	0.0001	<0.0001	92	80-120	92	70-130	-	0-20
Strontium	mg/L	0.001	<0.001	100	80-120	88	70-130	7	0-20
Thallium	mg/L	0.0001	<0.0001	104	80-120	86	70-130	-	0-20
Uranium	mg/L	0.001	<0.001	100	80-120	86	70-130	-	0-20
Vanadium	mg/L	0.001	<0.001	100	80-120	95	70-130	-	0-20
Zinc	mg/L	0.01	<0.01	110	80-120	90	70-130	-	0-20
Associated Samples : 8908634								Prep Date: 2025-08-13 Analysis Date: 2025-08-13	
Metals Scan (Water, ICP/OES)									
<i>Method : Metals (Water, ICP/OES). Internal method: OTT-I-MET-WI48491.</i>									
Calcium	mg/L	1	<1	103	86-115	100	70-130	0	0-20
Magnesium	mg/L	1	<1	100	91-109	103	70-130	7	0-20
Potassium	mg/L	1	<1	101	87-113	106	70-130	-	0-20
Sodium	mg/L	1	<1	103	85-115	102	70-130	-	0-20
Associated Samples : 8908634								Prep Date: 2025-08-13 Analysis Date: 2025-08-12	
Nitrate (Water, IC)									
<i>Method : Anions (Water, Ion Chromatography). Internal method: OTT-I-IC-WI45985.</i>									
Nitrate (as Nitrogen)	mg/L	0.1	<0.1	107	80-120	109	80-120	-	0-20
Associated Samples : 8908634								Prep Date: 2025-08-14 Analysis Date: 2025-08-14	
Nitrite (Water, IC)									
<i>Method : Anions (Water, Ion Chromatography). Internal method: OTT-I-IC-WI45985.</i>									
Nitrite (as Nitrogen)	mg/L	0.1	<0.1	104	80-120	115	80-120	-	0-20
Associated Samples : 8908634								Prep Date: 2025-08-14 Analysis Date: 2025-08-14	
pH (25°C) (Water, Automated)									
<i>Method : pH (Water, Automated Meter). Internal method: OTT-I-AT-WI45398.</i>									
pH @ 25°C		1	7.25	100	97-103			1	0-20
Associated Samples : 8908634								Prep Date: 2025-08-15 Analysis Date: 2025-08-18	

OFFICIAL CERTIFICATE OF ANALYSIS - QUALITY CONTROL

Client : Paterson Group
Project : PH5075

Reception Date: 2025-08-12

Parameter	Unit	RL	Blank	QC		Matrix Spike		Duplicate	
				Recovery %	Range %	Recovery %	Range %	RPD %	Range %
Phenols (Water, Colorimetry)									
<i>Method : Phenols (Water, Colorimetry). Internal method: OTT-I-4AAP-WI46150.</i>									
Phenols-4AAP	mg/L	0.001	<0.001	104	75-125	106	70-130	-	0-20
Associated Samples : 8908634								Prep Date: 2025-08-14 Analysis Date: 2025-08-15	
Sulphate (Water, IC)									
<i>Method : Anions (Water, Ion Chromatography). Internal method: OTT-I-IC-WI45985.</i>									
Sulphate	mg/L	1	<1	100	90-110	98	80-120	2	0-20
Associated Samples : 8908634								Prep Date: 2025-08-14 Analysis Date: 2025-08-14	
Sulphide (Water, Colorimetry)									
<i>Method : Sulphide, S2- (Water, Colorimetry). Internal method: OTT-I-SPEC-WI45931.</i>									
Sulphide (S2-)	mg/L	0.01	<0.01	94	80-120			-	0-20
Associated Samples : 8908634								Prep Date: 2025-08-13 Analysis Date: 2025-08-13	
Tannin and Lignin (Water, Spec)									
<i>Method : Tannin and Lignin (Water, Spec), Internal method: OTT-I-SPEC-WI57693.</i>									
Tannin and Lignin	mg/L	0.1	<0.1	94	80-120			-	0-20
Associated Samples : 8908634								Prep Date: 2025-08-19 Analysis Date: 2025-08-19	
Total Coliforms (DC Plate)									
<i>Method : Total Coliforms and E.Coli by MF (Water, DC plate). Internal method: OTT-M-BAC-WI45296.</i>									
Total Coliforms (DC)	CFU/100mL	0	0					-	0-30
Associated Samples : 8908634								Prep Date: 2025-08-12 Analysis Date: 2025-08-13	
Total Kjeldahl Nitrogen (Water, Colorimetry)									
<i>Method : TKN (Water, colorimetry). Internal method: OTT-I-NUT-WI46201.</i>									
Total Kjeldahl Nitrogen	mg/L	0.1	<0.100	98	70-130	95	70-130	-	0-20
Associated Samples : 8908634								Prep Date: 2025-08-13 Analysis Date: 2025-08-13	
Turbidity (Water, Turbidimeter)									
<i>Method : Turbidity (Water, Turbidimeter). Internal method: OTT-I-TUR-WI46288.</i>									
Turbidity	NTU	0.1	<0.1	102	80-120			4	0-30
Associated Samples : 8908634								Prep Date: 2025-08-14 Analysis Date: 2025-08-15	

OFFICIAL CERTIFICATE OF ANALYSIS - QUALITY CONTROL

Client : Paterson Group
Project : PH5075

Reception Date: 2025-08-12

Parameter	Unit	RL	Blank	QC		Matrix Spike		Duplicate	
				Recovery %	Range %	Recovery %	Range %	RPD %	Range %
VOCs (Water, GC/MS)									
<i>Method : Volatile Organic Compounds (Water, GC/MS). Internal method: AMVOMSE8.</i>									
1,1,1,2-Tetrachloroethane	ug/L	0.5	<0.5	112	70-130	112	70-130	-	0-30
1,1,1-Trichloroethane	ug/L	0.4	<0.4	119	70-130	119	70-130	-	0-30
1,1,1,2,2-Tetrachloroethane	ug/L	0.5	<0.5	130	70-130	130	70-130	-	0-30
1,1,2-Trichloroethane	ug/L	0.4	<0.4	121	70-130	121	70-130	-	0-30
1,1-Dichloroethane	ug/L	0.4	<0.4	87	70-130	87	70-130	-	0-30
1,1-Dichloroethene	ug/L	0.5	<0.5	70	70-130	70	70-130	-	0-30
1,2,4-Trichlorobenzene	ug/L	0.5	<0.5	91	70-130	91	70-130	-	0-30
1,2-Dibromoethane	ug/L	0.2	<0.2	121	70-130	121	70-130	-	0-30
1,2-Dichlorobenzene	ug/L	0.4	<0.4	86	70-130	86	70-130	-	0-30
1,2-Dichloroethane	ug/L	0.2	<0.2	91	70-130	91	70-130	-	0-30
1,2-dichloroethene, cis + trans ^A	ug/L	0.5	<0.5				-		-
1,2-Dichloropropane	ug/L	0.5	<0.5	121	70-130	121	70-130	-	0-30
1,3,5-Trimethylbenzene	ug/L	0.3	<0.3	119	70-130	119	70-130	-	0-30
1,3-Dichlorobenzene	ug/L	0.4	<0.4	117	70-130	117	70-130	-	0-30
1,3-Dichloropropene, cis + trans	ug/L	0.5	<0.5				-		-
1,4-Dichlorobenzene	ug/L	0.4	<0.4	111	70-130	130	70-130	-	0-30
Acetone	ug/L	5	<5	101	70-130	101	70-130	-	0-30
Benzene	ug/L	0.5	<0.5	109	70-130	109	70-130	-	0-30
Bromodichloromethane	ug/L	0.3	<0.3	112	70-130	112	70-130	-	0-30
Bromoform	ug/L	0.4	<0.4	112	70-130	112	70-130	-	0-30
Bromomethane	ug/L	0.5	<0.5	119	70-130	119	70-130	-	0-30
Carbon tetrachloride	ug/L	0.2	<0.2	130	70-130	130	70-130	-	0-30
Chloroethane	ug/L	0.5	<0.5	129	70-130	129	70-130	-	0-30
Chloroform	ug/L	0.5	<0.5	79	70-130	79	70-130	-	0-30
Chloromethane	ug/L	0.2	<0.2	81	70-130	81	70-130	-	0-30
cis-1,2-Dichloroethene	ug/L	0.4	<0.4	100	70-130	100	70-130	-	0-30
cis-1,3-Dichloropropene	ug/L	0.5	<0.5	100	70-130	100	70-130	-	0-30
Dibromochloromethane	ug/L	0.3	<0.3	112	70-130	112	70-130	-	0-30
Dichlorodifluoromethane	ug/L	0.5	<0.5	102	70-130	102	70-130	-	0-30
Dichloromethane	ug/L	4	<4	119	70-130	119	70-130	-	0-30
Diethyl ether	ug/L	5	<5	117	70-130	117	70-130	-	0-30
Ethylbenzene	ug/L	0.5	<0.5	127	70-130	127	70-130	-	0-30
Hexane	ug/L	5	<5	121	70-130	121	70-130	-	0-30
m/p-Xylene	ug/L	0.4	<0.4	100	70-130	100	70-130	-	0-30
Methyl butyl ketone (MBK)	ug/L	5	<5	120	70-130	120	70-130	-	0-30
Methyl ethyl ketone (MEK)	ug/L	2	<2	102	70-130	102	70-130	-	0-30
Methyl isobutyl ketone (MIBK)	ug/L	5	<5	119	70-130	119	70-130	-	0-30
Methyl tert-butyl ether (MTBE)	ug/L	2	<2	130	70-130	130	70-130	-	0-30
Monochlorobenzene	ug/L	0.5	<0.5	118	70-130	118	70-130	-	0-30
o-Xylene	ug/L	0.4	<0.4	100	70-130	100	70-130	-	0-30
Styrene	ug/L	0.5	<0.5	71	70-130	71	70-130	-	0-30
Tetrachloroethylene (PCE)	ug/L	0.3	<0.3	85	70-130	85	70-130	-	0-30
Toluene	ug/L	0.4	<0.4	96	70-130	96	70-130	-	0-30
trans-1,2-dichloroethene	ug/L	0.4	<0.4	100	70-130	100	70-130	-	0-30
trans-1,3-dichloropropene	ug/L	0.5	<0.5	100	70-130	100	70-130	-	0-30
Trichloroethylene (TCE)	ug/L	0.3	<0.3	102	70-130	102	70-130	-	0-30
Trichlorofluoromethane	ug/L	0.5	<0.5	112	70-130	112	70-130	-	0-30

OFFICIAL CERTIFICATE OF ANALYSIS - QUALITY CONTROL

Client : Paterson Group
 Project : PH5075

Reception Date: 2025-08-12

Parameter	Unit	RL	Blank	QC		Matrix Spike		Duplicate	
				Recovery %	Range %	Recovery %	Range %	RPD %	Range %
VOCs (Water, GC/MS)									
<i>Method : Volatile Organic Compounds (Water, GC/MS). Internal method: AMVOMSE8.</i>									
Vinyl chloride	ug/L	0.2	<0.2	130	70-130	130	70-130	-	0-30
Xylene (Total)	ug/L	0.5	<0.5				-		-
Associated Samples : 8908634								Prep Date: 2025-08-20 Analysis Date: 2025-08-20	

Where RPD % is reported as "-" the calculation is not available because one or both of the duplicates is within 5 times the RL.

COORD. SYS.: MTM ZONE 9 **EASTING:** 379013.78 **NORTHING:** 5019022.56 **ELEVATION:** 91.31

PROJECT: Proposed Commercial Development **FILE NO.:** PG7567

ADVANCED BY: CME-55 Low Clearance Drill

REMARKS: **DATE:** June 2, 2025 **HOLE NO.:** BH 1-25

SAMPLE DESCRIPTION	STRATA PLOT	DEPTH (m)	SAMPLE				PEN. RESIST. (BLOWS/0.3m) DCPT (50mm DIA. CONE)			MONITORING WELL CONSTRUCTION	ELEVATION (m)	
			TYPE AND NO.	RECOVERY (%)	N OR RQD	WATER CONTENT (%)	20	40	60			80
							△	REMOULDED SHEAR STRENGTH (kPa)				
							▲	UNDRAINED SHEAR STRENGTH (kPa)				
				PL (%)		WATER CONTENT (%)		LL (%)				
				20		40		60		80		
GROUND SURFACE												
FILL: Gravel and crushed stone, trace sand 0.15m [91.16m]	[Pattern]	0.15	AU 1								91	
FILL: Compact to very dense, brown silty sand, with gravel, crushed stone, concrete and ash	[Pattern]	1	SS 2	50	10-10-15-21						90	
	[Pattern]	2	SS 3	27	5-50-/-/ 50/0.13						89	
	[Pattern]	3	SS 4	50	12-9-8-9 17						88	
	[Pattern]	4	SS 5	42	4-6-6-11 12					3.44 m	88	
	[Pattern]	5	SS 6	46	4-20-52-21 72					4.09m	87	
5.26m [86.05m]	[Pattern]	6	SS 7	37	2-20-10-5 30						86	
FILL: Brown silty sand to sandy silt, some gravel, cobbles and boulders	[Pattern]	7	SS 8	42	2-3-5-13 8					5.61m	86	
	[Pattern]	8	SS 9	71	11-23-15-25 38						85	
6.78m [84.53m]	[Pattern]	9	SS 10	46	9-12-12-23 24						84	
GLACIAL TILL: Loose to dense, silty sand to sandy silt, some gravel, cobbles and boulders	[Pattern]	10	SS 11	33	6-15-12-16 27						83	
	[Pattern]	11	SS 12	37	11-12-15-12 27						82	
	[Pattern]	12	SS 13	43	7-18-22-50 40						81	
10.26m [81.05m]	[Pattern]	13	SS 14	51	10-51-50-/- 101/0.2						81	
End of Borehole		14									80	
Practical refusal to augering at 10.26 m depth (GWL at 3.44 m depth - June 5, 2025)		15									79	
		16									78	


DISCLAIMER: THE DATA PRESENTED IN THIS SHEET IS THE PROPERTY OF PATERSON GROUP AND THE CLIENT FOR WHOM IT WAS PRODUCED. THIS SHEET SHOULD BE READ IN CONJUNCTION WITH ITS CORRESPONDING REPORT. PATERSON GROUP IS NOT RESPONSIBLE FOR THE UNAUTHORIZED USE OF THIS DATA.

COORD. SYS.: MTM ZONE 9 **EASTING:** 379026.72 **NORTHING:** 5019097.92 **ELEVATION:** 91.06

PROJECT: Proposed Commercial Development **FILE NO. :** PG7567

ADVANCED BY: CME-55 Low Clearance Drill

REMARKS: **DATE:** June 2, 2025 **HOLE NO. :** BH 2-25



DISCLAIMER: THE DATA PRESENTED IN THIS SHEET IS THE PROPERTY OF PATERSON GROUP AND THE CLIENT FOR WHOM IT WAS PRODUCED. THIS SHEET SHOULD BE READ IN CONJUNCTION WITH ITS CORRESPONDING REPORT. PATERSON GROUP IS NOT RESPONSIBLE FOR THE UNAUTHORIZED USE OF THIS DATA.

P:/AutoCAD Drawings/Test Hole Data Files/PG7567/data/sqlite 2025-06-23, 14:56 Paterson_Template_AA

COORD. SYS.: MTM ZONE 9 **EASTING:** 379085.67 **NORTHING:** 5019059.58 **ELEVATION:** 90.73

PROJECT: Proposed Commercial Development **FILE NO.:** PG7567
ADVANCED BY: CME-55 Low Clearance Drill
REMARKS: **DATE:** June 2, 2025 **HOLE NO.:** BH 3-25

SAMPLE DESCRIPTION	STRATA PLOT	DEPTH (m)	SAMPLE				PEN. RESIST. (BLOWS/0.3m) DCPT (50mm DIA. CONE)			PIEZOMETER CONSTRUCTION	ELEVATION (m)	
			TYPE AND NO.	RECOVERY (%)	N OR RQD	WATER CONTENT (%)	20	40	60			80
							△ REMOULDED SHEAR STRENGTH (kPa)					
						▲ UNDRAINED SHEAR STRENGTH (kPa)						
GROUND SURFACE												
TOPSOIL and organics 0.08m [90.65m]		0	AU 1							90.73		
FILL: Compact to very dense, brown silty sand, some clay, trace gravel, crushed stone and asphalt 1.68m [89.05m]		1	SS 2	43	3-10-50-/ 60/0.25					90.00		
End of Borehole		2	SS 3	48	50-/-/-/ 50/0.15					89.05		
Practical refusal to augering at 1.63 m depth		2								89.05		
		3								88.00		
		4								87.00		
		5								86.00		
		6								85.00		
		7								84.00		
		8								83.00		
		9								82.00		
		10								81.00		
		11								80.00		
		12								79.00		
		13								78.00		
		14								77.00		

DISCLAIMER: THE DATA PRESENTED IN THIS SHEET IS THE PROPERTY OF PATERSON GROUP AND THE CLIENT FOR WHOM IT WAS PRODUCED. THIS SHEET SHOULD BE READ IN CONJUNCTION WITH ITS CORRESPONDING REPORT. PATERSON GROUP IS NOT RESPONSIBLE FOR THE UNAUTHORIZED USE OF THIS DATA.

COORD. SYS.: MTM ZONE 9 **EASTING:** 379084.55 **NORTHING:** 5019060.27 **ELEVATION:** 90.64


PROJECT: Proposed Commercial Development **FILE NO. :** PG7567
ADVANCED BY: CME-55 Low Clearance Drill
REMARKS: **DATE:** June 2, 2025 **HOLE NO. :** BH 3A-25

SAMPLE DESCRIPTION	STRATA PLOT	DEPTH (m)	SAMPLE				PEN. RESIST. (BLOWS/0.3m) DCPT (50mm DIA. CONE)			PIEZOMETER CONSTRUCTION	ELEVATION (m)	
			TYPE AND NO.	RECOVERY (%)	N OR RQD	WATER CONTENT (%)	20	40	60			80
							△ REMOULDED SHEAR STRENGTH (kPa)					▲ UNDRAINED SHEAR STRENGTH (kPa)
					PL (%)	WATER CONTENT (%)	LL (%)					
GROUND SURFACE												
0.94m [89.70m]		1								90		
End of Borehole		1								89		
Practical refusal to augering at 0.94 m depth		2								88		
		3								87		
		4								86		
		5								85		
		6								84		
		7								83		
		8								82		
		9								81		
		10								80		
		11								79		
		12								78		
		13								77		
		14								76		

DISCLAIMER: THE DATA PRESENTED IN THIS SHEET IS THE PROPERTY OF PATERSON GROUP AND THE CLIENT FOR WHOM IT WAS PRODUCED. THIS SHEET SHOULD BE READ IN CONJUNCTION WITH ITS CORRESPONDING REPORT. PATERSON GROUP IS NOT RESPONSIBLE FOR THE UNAUTHORIZED USE OF THIS DATA.

COORD. SYS.: MTM ZONE 9 **EASTING:** 379087.71 **NORTHING:** 5019059.84 **ELEVATION:** 90.80

PROJECT: Proposed Commercial Development **FILE NO. :** PG7567
ADVANCED BY: CME-55 Low Clearance Drill
REMARKS: **DATE:** June 2, 2025 **HOLE NO. :** BH 3B-25



COORD. SYS.: MTM ZONE 9 **EASTING:** 379135.75 **NORTHING:** 5019162.49 **ELEVATION:** 92.18

PROJECT: Proposed Commercial Development **FILE NO. :** PG7567

ADVANCED BY: CME-55 Low Clearance Drill

REMARKS: **DATE:** June 3, 2025 **HOLE NO. :** BH 4-25

SAMPLE DESCRIPTION	STRATA PLOT	DEPTH (m)	SAMPLE				PEN. RESIST. (BLOWS/0.3m) DCPT (50mm DIA. CONE)			MONITORING WELL CONSTRUCTION	ELEVATION (m)	
			TYPE AND NO.	RECOVERY (%)	N OR RQD	WATER CONTENT (%)	20	40	60			80
							△ REMOULDED SHEAR STRENGTH (kPa)		▲ UNDRAINED SHEAR STRENGTH (kPa)			
			PL (%)		WATER CONTENT (%)		LL (%)					
GROUND SURFACE												
FILL: Stiff brown silty clay, some gravel, trace sand - trace organics to 0.08 m depth		1	AU 1							92		
1.22m [90.96m]		1	SS 2	33	3-5-5-25 10					91		
FILL: Compact, brown silty sand, with gravel, trace topsoil and organics		2	SS 3	75	11-13-11-11 24					90		
2.21m [89.97m]		2	SS 4	25	2-5-2-3 7					89		
FILL: Stiff, brown silty clay, with gravel, some crushed stone and sand		3	SS 5	42	1-4-4-4 8					88		
2.97m [89.21m]		3	SS 6	12	1-2-2-4 4					87		
FILL: Loose, brown silty sand, some clay, trace wood and topsoil		4	SS 7	31	2-2-50-/ 52/0.25					86		
3.73m [88.45m]		4	SS 8	25	1-2-2-2 4					85		
FILL: Firm, brown silty clay, with gravel, some sand and crushed stone		5	SS 9	29	1-2-4-4 6					84		
6.02m [86.16m]		5	SS 10	46	1-2-1-1 3					83		
FILL: Firm, grey silty clay, with gravel, cobbles and boulders, trace crushed stone and asphalt		6	SS 11	58	1-3-2-2 5					82		
8.69m [83.49m]		6	SS 12	71	1-2-2-6 4					81		
TOPSOIL and organics		7	SS 13	62	5-11-8-/ 19					80		
8.99m [83.19m]		7	SS 14	83	1-1-1-1 2					79		
Compact, grey SILTY SAND to SANDY SILT		8	SS 15	100	1-1-1-2 2					78		
9.45m [82.73m]		8	SS 16	83	0-0-0-0 0					77		
GLACIAL TILL: Firm to stiff, brown clayey silt, trace gravel and sand		9	SS 17	100	P					76		
8.69m [83.49m]		9	SS 18	100	1-2-3-1 5					75		
FILL: Firm, grey silty clay, with gravel, cobbles and boulders, trace crushed stone and asphalt		10	SS 19	29	1-2-4-4 6					74		
6.02m [86.16m]		10	SS 20	46	1-2-1-1 3					73		
FILL: Firm, brown silty clay, with gravel, some sand and crushed stone		11	SS 21	58	1-3-2-2 5					72		
3.73m [88.45m]		11	SS 22	71	1-2-2-6 4					71		
TOPSOIL and organics		12	SS 23	62	5-11-8-/ 19					70		
8.99m [83.19m]		12	SS 24	83	1-1-1-1 2					69		
GLACIAL TILL: Firm to stiff, brown clayey silt, trace gravel and sand		13	SS 25	100	1-1-1-2 2					68		
8.69m [83.49m]		13	SS 26	83	0-0-0-0 0					67		
FILL: Firm, brown silty clay, with gravel, some sand and crushed stone		14	SS 27	100	P					66		
6.02m [86.16m]		14	SS 28	29	1-2-4-4 6					65		
FILL: Firm, grey silty clay, with gravel, cobbles and boulders, trace crushed stone and asphalt		15	SS 29	46	1-2-1-1 3					64		
8.69m [83.49m]		15	SS 30	58	1-3-2-2 5					63		
TOPSOIL and organics		16	SS 31	71	1-2-2-6 4					62		
8.99m [83.19m]		16	SS 32	62	5-11-8-/ 19					61		
GLACIAL TILL: Firm to stiff, brown clayey silt, trace gravel and sand		17	SS 33	83	1-1-1-1 2					60		
9.45m [82.73m]		17	SS 34	100	1-1-1-2 2					59		
FILL: Firm, brown silty clay, with gravel, some sand and crushed stone		18	SS 35	83	0-0-0-0 0					58		
6.02m [86.16m]		18	SS 36	100	P					57		
FILL: Firm, brown silty clay, with gravel, some sand and crushed stone		19	SS 37	25	1-2-2-2 4					56		
6.02m [86.16m]		19	SS 38	29	1-2-4-4 6					55		
FILL: Firm, grey silty clay, with gravel, cobbles and boulders, trace crushed stone and asphalt		20	SS 39	46	1-2-1-1 3					54		
8.69m [83.49m]		20	SS 40	58	1-3-2-2 5					53		
TOPSOIL and organics		21	SS 41	71	1-2-2-6 4					52		
8.99m [83.19m]		21	SS 42	62	5-11-8-/ 19					51		
GLACIAL TILL: Firm to stiff, brown clayey silt, trace gravel and sand		22	SS 43	83	1-1-1-1 2					50		
9.45m [82.73m]		22	SS 44	100	1-1-1-2 2					49		
FILL: Firm, brown silty clay, with gravel, some sand and crushed stone		23	SS 45	83	0-0-0-0 0					48		
6.02m [86.16m]		23	SS 46	100	P					47		
FILL: Firm, brown silty clay, with gravel, some sand and crushed stone		24	SS 47	25	1-2-2-2 4					46		
6.02m [86.16m]		24	SS 48	29	1-2-4-4 6					45		
FILL: Firm, grey silty clay, with gravel, cobbles and boulders, trace crushed stone and asphalt		25	SS 49	46	1-2-1-1 3					44		
8.69m [83.49m]		25	SS 50	58	1-3-2-2 5					43		
TOPSOIL and organics		26	SS 51	71	1-2-2-6 4					42		
8.99m [83.19m]		26	SS 52	62	5-11-8-/ 19					41		
GLACIAL TILL: Firm to stiff, brown clayey silt, trace gravel and sand		27	SS 53	83	1-1-1-1 2					40		
9.45m [82.73m]		27	SS 54	100	1-1-1-2 2					39		
FILL: Firm, brown silty clay, with gravel, some sand and crushed stone		28	SS 55	83	0-0-0-0 0					38		
6.02m [86.16m]		28	SS 56	100	P					37		
FILL: Firm, brown silty clay, with gravel, some sand and crushed stone		29	SS 57	25	1-2-2-2 4					36		
6.02m [86.16m]		29	SS 58	29	1-2-4-4 6					35		
FILL: Firm, grey silty clay, with gravel, cobbles and boulders, trace crushed stone and asphalt		30	SS 59	46	1-2-1-1 3					34		
8.69m [83.49m]		30	SS 60	58	1-3-2-2 5					33		
TOPSOIL and organics		31	SS 61	71	1-2-2-6 4					32		
8.99m [83.19m]		31	SS 62	62	5-11-8-/ 19					31		
GLACIAL TILL: Firm to stiff, brown clayey silt, trace gravel and sand		32	SS 63	83	1-1-1-1 2					30		
9.45m [82.73m]		32	SS 64	100	1-1-1-2 2					29		
FILL: Firm, brown silty clay, with gravel, some sand and crushed stone		33	SS 65	83	0-0-0-0 0					28		
6.02m [86.16m]		33	SS 66	100	P					27		
FILL: Firm, brown silty clay, with gravel, some sand and crushed stone		34	SS 67	25	1-2-2-2 4					26		
6.02m [86.16m]		34	SS 68	29	1-2-4-4 6					25		
FILL: Firm, grey silty clay, with gravel, cobbles and boulders, trace crushed stone and asphalt		35	SS 69	46	1-2-1-1 3					24		
8.69m [83.49m]		35	SS 70	58	1-3-2-2 5					23		
TOPSOIL and organics		36	SS 71	71	1-2-2-6 4					22		
8.99m [83.19m]		36	SS 72	62	5-11-8-/ 19					21		
GLACIAL TILL: Firm to stiff, brown clayey silt, trace gravel and sand		37	SS 73	83	1-1-1-1 2					20		
9.45m [82.73m]		37	SS 74	100	1-1-1-2 2					19		
FILL: Firm, brown silty clay, with gravel, some sand and crushed stone		38	SS 75	83	0-0-0-0 0					18		
6.02m [86.16m]		38	SS 76	100	P					17		
FILL: Firm, brown silty clay, with gravel, some sand and crushed stone		39	SS 77	25	1-2-2-2 4					16		
6.02m [86.16m]		39	SS 78	29	1-2-4-4 6					15		
FILL: Firm, grey silty clay, with gravel, cobbles and boulders, trace crushed stone and asphalt		40	SS 79	46	1-2-1-1 3					14		
8.69m [83.49m]		40	SS 80	58	1-3-2-2 5					13		
TOPSOIL and organics		41	SS 81	71	1-2-2-6 4					12		
8.99m [83.19m]		41	SS 82	62	5-11-8-/ 19					11		
GLACIAL TILL: Firm to stiff, brown clayey silt, trace gravel and sand		42	SS 83	83	1-1-1-1 2					10		
9.45m [82.73m]		42	SS 84	100	1-1-1-2 2					9		
FILL: Firm, brown silty clay, with gravel, some sand and crushed stone		43	SS 85	83	0-0-0-0 0					8		
6.02m [86.16m]		43	SS 86	100	P					7		
FILL: Firm, brown silty clay, with gravel, some sand and crushed stone		44	SS 87	25	1-2-2-2 4					6		
6.02m [86.16m]		44	SS 88	29	1-2-4-4 6					5		
FILL: Firm, grey silty clay, with gravel, cobbles and boulders, trace crushed stone and asphalt		45	SS 89	46	1-2-1-1 3					4		
8.69m [83.49m]		45	SS 90	58	1-3-2-2 5					3		
TOPSOIL and organics		46	SS 91	71	1-2-2-6 4					2		
8.99m [83.19m]		46	SS 92	62	5-11-8-/ 19					1		
GLACIAL TILL: Firm to stiff, brown clayey silt, trace gravel and sand		47	SS 93	83	1-1-1-1 2					0		
9.45m [82.73m]		47	SS 94	100	1-1-1-2 2					-1		
FILL: Firm, brown silty clay, with gravel, some sand and crushed stone		48	SS 95	83	0-0-0-0 0					-2		
6.02m [86.16m]		48	SS 96	100	P					-3		
FILL: Firm, brown silty clay, with gravel, some sand and crushed stone		49	SS 97	25	1-2-2-2 4					-4		
6.02m [86.16m]		49	SS 98	29	1-2-4-4 6					-5		
FILL: Firm, grey silty clay, with gravel, cobbles and boulders, trace crushed stone and asphalt		50	SS 99	46	1-2-1-1 3					-6		
8.69m [83.49m]		50	SS 100	58	1-3-2-2 5					-7		
TOPSOIL and organics		51	SS 101	71	1-2-2-6 4					-8		
8.99m [83.19m]		51	SS 102	62	5-11-8-/ 19					-9		
GLACIAL TILL: Firm to stiff, brown clayey silt, trace gravel and sand		52	SS 103	83	1-1-1-1 2					-10		
9.45m [82.73m]		52	SS 104	100	1-1-1-2 2	</						



BOREHOLE No.: BH1-21
ELEVATION: 91.07 m

CLIENT: Consolidated Fastfrate (Ottawa) Holdings Ltd.
 PROJECT: ConFastfrate, New Warehouse & Offices
 LOCATION: Somme Street, Ottawa, ON
 DESCRIBED BY: J. Scott CHECKED BY: Leandro Ramos
 DATE (START): 26 July 2021 DATE (FINISH): 27 July 2021

- LEGEND**
- ☒ SS Split Spoon
 - ▨ ST Shelby Tube
 - ▮ RC Rock Core
 - ▼ Water Level
 - Water content (%)
 - ┌ Atterberg limits (%)
 - N Penetration Index based on Split Spoon sample
 - N Penetration Index based on Dynamic Cone sample
 - △ Cu Shear Strength based on Field Vane
 - Cu Shear Strength based on Lab Vane
 - S Sensitivity Value of Soil
 - ▲ Shear Strength based on Pocket Penetrometer

File: \\GHDNET\GHD\CA\PETERBOROUGH\PROJECTS\66211231101\WORKSHARE\FIELD\GINT LOG\11231101 LOGS.GPJ Library File: 11231101 GHD_GEOTECH_V10.GLB Report: 11231101 BOREHOLE LOG Date: 12/9/21

SCALE		STRATIGRAPHY			SAMPLE DATA			
Depth BGS	Elevation (m)	Stratigraphy	DESCRIPTION OF SOIL AND BEDROCK	State	Type and Number	Recovery	Blows per 6 in. / 15 cm	Penetration Index / RQD %
metres	91.07		GROUND SURFACE			%		N
	90.99	▨	TOPSOIL (75 mm) FILL - SILTY SAND , trace gravel, trace clay, dark grey, moist, compact		SS1	96	7-15-10-9	25
1.0	90.20	▨	FILL - SAND , trace silt, trace gravel, brown, moist, loose Gravel - 17%, Sand - 60%, Silt - 19%, Clay - 4%		SS2A SS2B	71	9-6-3-4 --	9
2.0	89.54	▨	FILL - SILTY SAND , with clay, trace gravel, dark grey, moist, dense cobble encountered at 1.83 mbgs		SS3	71	7-13-33-40	46
3.0			with organics and wood fragments		SS4 SS5A SS5B	42 67	5-2-3-50/76 mm 8-8-5-3 --	5 13
4.0			augers grinding at 3.96 mbgs, inferred boulders or construction debris		SS6	0	50/51 mm	50/51 mm
5.0	86.49	▨	SILTY SAND - trace gravel, trace clay, brown, moist, dense to very dense		SS7	83	10-21-37 50/127 mm	58
6.0	85.27	▨	grey, very moist, augers grinding at 9.85 mbgs, inferred boulder		SS8A SS8B	100	43-31-36-47 --	67
7.0			cobble encountered at 6.86 mbgs		SS9 SS10	83 75	24-23-18-26 13-11-15-12	41 26
8.0					SS11	71	6-4-12-23	16
9.0					SS12	67	50-15-15-18	30
10.0	81.21	▨	Gravel - 16%, Sand - 32%, Silt - 36%, Clay - 16%		SS13	67	13-17-19-17	36
11.0		▮	LIMESTONE - interbedded sandstone, grey, poor to excellent quality based on RQD - highly weathered from 9.86 mbgs to 9.93 mbgs		RC1	58	38	38
			silty sand seam at 10.92 mbgs					

NOTES:
 mbgs: meters below ground surface
 RQD: Rock Quality Designation



BOREHOLE No.: BH1-21
ELEVATION: 91.07 m

Page 36
BOREHOLE LOG
 Page: 2 of 2

CLIENT: Consolidated Fastfrate (Ottawa) Holdings Ltd.
 PROJECT: ConFastfrate, New Warehouse & Offices
 LOCATION: Somme Street, Ottawa, ON
 DESCRIBED BY: J. Scott CHECKED BY: Leandro Ramos
 DATE (START): 26 July 2021 DATE (FINISH): 27 July 2021

- LEGEND**
- SS Split Spoon
 - ST Shelby Tube
 - RC Rock Core
 - Water Level
 - Water content (%)
 - Atterberg limits (%)
 - N Penetration Index based on Split Spoon sample
 - N Penetration Index based on Dynamic Cone sample
 - △ Cu Shear Strength based on Field Vane
 - Cu Shear Strength based on Lab Vane
 - S Sensitivity Value of Soil
 - ▲ Shear Strength based on Pocket Penetrometer

File: \\GHDNET\GHD\CA\PETERBOROUGH\PROJECTS\66211231101\WORKSHARE\FIELD\GINT LOG\11231101 LOGS.GPJ Library File: 11231101 GHD_GEOTECH_V10.GLB Report: 11231101 BOREHOLE LOG Date: 12/2/21

SCALE		STRATIGRAPHY			SAMPLE DATA			
Depth BGS	Elevation (m)	Stratigraphy	DESCRIPTION OF SOIL AND BEDROCK	State	Type and Number	Recovery	Blows per 6 in. / 15 cm	Penetration Index / RQD %
metres	91.07		GROUND SURFACE			%		N
12.0			vertical fracture at 11.58 mbs		RC2	98	95	95
13.0					RC3	95	58	58
14.0	77.25		Borehole terminated at 13.82 mbs					
15.0			Note: Borehole Coordinate - UTM Zone 18 - Northing: 5017223.9 - Easting: 456487.2					
16.0								
17.0								
18.0								
19.0								
20.0								
21.0								
22.0								

SCALE FOR TEST RESULTS
 50kPa 100kPa 150kPa 200kPa
 10 20 30 40 50 60 70 80 90

NOTES:
 mbs: meters below ground surface
 RQD: Rock Quality Designation



BOREHOLE No.: BH2-21
ELEVATION: 90.79 m

Page 37
BOREHOLE LOG
 Page: 1 of 2

CLIENT: Consolidated Fastrate (Ottawa) Holdings Ltd.
 PROJECT: ConFastrate, New Warehouse & Offices
 LOCATION: Somme Street, Ottawa, ON
 DESCRIBED BY: J. Scott CHECKED BY: Leandro Ramos
 DATE (START): 27 July 2021 DATE (FINISH): 27 July 2021

- LEGEND**
- ☒ SS Split Spoon
 - ▨ ST Shelby Tube
 - ▮ RC Rock Core
 - ▼ Water Level
 - Water content (%)
 - ┌ Atterberg limits (%)
 - N Penetration Index based on Split Spoon sample
 - N Penetration Index based on Dynamic Cone sample
 - △ Cu Shear Strength based on Field Vane
 - Cu Shear Strength based on Lab Vane
 - S Sensitivity Value of Soil
 - ▲ Shear Strength based on Pocket Penetrometer

File: \\GHDNET\GHD\CA\PETERBOROUGH\PROJECTS\66211231101\WORKSHARE\FIELD\GINT LOG\11231101 LOGS.GPJ Library File: 11231101 GHD_GEOTECH_V10.GLB Report: 11231101 BOREHOLE LOG Date: 12/6/21

SCALE		STRATIGRAPHY			SAMPLE DATA			
Depth BGS	Elevation (m)	Stratigraphy	DESCRIPTION OF SOIL AND BEDROCK	State	Type and Number	Recovery	Blows per 6 in. / 15 cm	Penetration Index / RQD %
metres	90.79		GROUND SURFACE			%		N
	90.71	▨	TOPSOIL (75 mm)	▨	SS1A	92	3-12-11-15	23
	90.33	▨	FILL - SILTY SAND, trace clay, trace bricks, trace asphalt, brown to black, moist, compact	▨	SS1B	--	--	
1.0	90.03	▨	FILL - SAND AND GRAVEL, trace silt, brown, moist, compact	▨	SS2	88	6-14-17-15	31
		▨	FILL - SILTY SAND, with gravel, trace clay, brown to grey, moist, dense	▨	SS3A	46	7-9-6-6	15
2.0			with clay at 1.65 mbgs	▨	SS3B	--	--	
			trace clay at 2.89 mbgs	▨	SS4	67	28-13-12-38	25
3.0				▨	SS5	63	8-7-5-12	12
			asphalt at 3.35 mbgs	▨	SS6A	67	3-1-1-1	2
4.0	86.93	▨	ORGANIC	▨	SS6B	--	--	
	86.88	▨	FILL - SILTY SAND, trace gravel, trace clay, brown, wet, loose	▨	SS6C	--	--	
			with topsoil at 4.57 mbgs	▨	SS7A	88	2-3-7-8	10
5.0			with clay, bricks fragments at 4.72 mbgs	▨	SS7B	--	--	
	85.45	▨	SILTY SAND - with clay, trace gravel, brown, moist to wet, compact to dense	▨	SS8	83	8-19-22-40	41
6.0			grey at 6.10 mbgs	▨	SS9	54	9-14-12-13	26
7.0				▨	SS10	79	5-3-5-6	8
8.0				▨	SS11	75	5-7-8-10	15
9.0			Gravel - 20%, Sand - 38%, Silt - 33%, Clay - 9%	▨	SS12	63	6-10-11-17	21
			wet at 9.14 mbgs	▨	SS13	71	11-18-18-21	36
10.0				▨	SS14	71	19-50/25 mm	50/25 mm
			augers grinding at 10.08 mbgs, inferred boulder	▨	SS15	25	11-14-15-21	29

NOTES:
 mbgs: meters below ground surface
 RQD: Rock Quality Designation



BOREHOLE No.: BH2-21
ELEVATION: 90.79 m

Page 38
BOREHOLE LOG
 Page: 2 of 2

CLIENT: Consolidated Fastfrate (Ottawa) Holdings Ltd.
 PROJECT: ConFastfrate, New Warehouse & Offices
 LOCATION: Somme Street, Ottawa, ON
 DESCRIBED BY: J. Scott CHECKED BY: L. Ramos
 DATE (START): 27 July 2021 DATE (FINISH): 27 July 2021

- LEGEND**
- ☒ SS Split Spoon
 - ▨ ST Shelby Tube
 - ▬ RC Rock Core
 - ▽ Water Level
 - Water content (%)
 - ┌─┐ Atterberg limits (%)
 - N Penetration Index based on Split Spoon sample
 - N Penetration Index based on Dynamic Cone sample
 - △ Cu Shear Strength based on Field Vane
 - Cu Shear Strength based on Lab Vane
 - S Sensitivity Value of Soil
 - ▲ Shear Strength based on Pocket Penetrometer

SCALE		STRATIGRAPHY			SAMPLE DATA			
Depth BGS	Elevation (m)	Stratigraphy	DESCRIPTION OF SOIL AND BEDROCK	State	Type and Number	Recovery	Blows per 6 in. / 15 cm	Penetration Index / RQD %
metres	90.79		GROUND SURFACE			%		N
	79.36		SAND - trace silt, grey, wet, dense		SS16A	92	11-15-18-31	23
	12.0		SILTY CLAY - with sand, trace gravel reddish brown, moist, hard		SS16B		-	
	79.23				SS17	0	21-31-31-40	62
	13.0				SS18	100	9-21-38-50/127 mm	59
	14.0				SS19	100	17-26-48-50/127 mm	59
	15.0		LIMESTONE - interbedded sandstone, grey, good quality based on RQD		RC1	100	78	78
	16.0		UCS = 139.1 MPa		RC2	98	76	76
	17.0				RC3	100	89	89
	18.0							
	19.0		Borehole terminated at 18.87 mbgs					
	76.01							
	71.92							

SCALE FOR TEST RESULTS
 10 20 30 40 50 60 70 80 90
 50kPa 100kPa 150kPa 200kPa

File: G:\11231101\WORKSHARE\FIELD\GINT\LOG\11231101 LOGS - COPY.GPJ Library File: 11231101 GHD_GEO TECH_V10.GLB Report: 11231101 BOREHOLE LOG Date: 24/1/22

NOTES:
 m bgs: meters below ground surface
 RQD: Rock Quality Designation



BOREHOLE No.: BH3-21
ELEVATION: 90.55 m

Page 39
BOREHOLE LOG
 Page: 1 of 1

CLIENT: Consolidated Fastrate (Ottawa) Holdings Ltd.
 PROJECT: ConFastrate, New Warehouse & Offices
 LOCATION: Somme Street, Ottawa, ON
 DESCRIBED BY: J. Scott CHECKED BY: L. Ramos
 DATE (START): 26 July 2021 DATE (FINISH): 26 July 2021

- LEGEND**
- ☒ SS Split Spoon
 - ▨ ST Shelby Tube
 - ▬ RC Rock Core
 - ▼ Water Level
 - Water content (%)
 - ┌ Atterberg limits (%)
 - N Penetration Index based on Split Spoon sample
 - N Penetration Index based on Dynamic Cone sample
 - △ Cu Shear Strength based on Field Vane
 - Cu Shear Strength based on Lab Vane
 - S Sensitivity Value of Soil
 - ▲ Shear Strength based on Pocket Penetrometer

SCALE		STRATIGRAPHY			SAMPLE DATA			
Depth BGS	Elevation (m)	Stratigraphy	DESCRIPTION OF SOIL AND BEDROCK	State	Type and Number	Recovery	Blows per 6 in. / 15 cm	Penetration Index / RQD %
metres	90.55		GROUND SURFACE			%		N
	90.48	TOPSOIL (75 mm)						
		FILL - SILTY SAND, with gravel, trace clay, brown, moist, compact			SS1	71	2-6-4-10	10
1.0	89.64	with presence of organics/topsoil			SS2A	42	5-5-7-14	12
					SS2B	-	-	
2.0					SS3	33	5-5-6-15	11
		with to trace clay at 2.5 m bgs			SS4	42	7-6-4-3	10
3.0		grey at 3.0 m bgs moist			SS5	86	2-2-8-27	10
	87.20	ASPHALT						
4.0	87.15	FILL - SANDY GRAVEL, dark grey, wet, compact			SS6	46	12-12-5-7	17
	86.74	SILTY SAND - trace gravel, some clay, brown, moist, compact						
5.0		loose at 4.75 m bgs			SS7	0	3-2-3-4	5
6.0		compact to very dense at 5.5 m bgs Gravel - 19%, Sand - 49%, Silt - 26%, Clay - 6%			SS8	73	10-16-21-46	37
	WL6.2 2021-07-26				SS9	100	13-26-27-41	53
7.0	83.54	with clay, trace gravel, trace cobbles, grey, moist, compact			SS10A	100	9-11-11-15	22
					SS10B	-	-	
8.0					SS11	71	8-13-20-28	33
9.0					SS12	79	5-10-16-36	26
		wet at 9.14 m bgs			SS13	80	18-50/102 mm	100+
10.0	81.11	Borehole terminated due to auger refusal at 9.45 mbgs. Bedrock or boulder inferred						
11.0		Noted: Borehole Location - UTM Zone 18N - Northing: 5017286.1 - Easting: 456612.6						

SCALE FOR TEST RESULTS
 50kPa 100kPa 150kPa 200kPa
 10 20 30 40 50 60 70 80 90

File: G:\11231101\WORKSHARE\FIELD\GINT\LOG\11231101 LOGS - COPY.GPJ Library File: 11231101 GHD_GEOTECH_V10.GLB Report: 11231101 BOREHOLE LOG Date: 24/1/22

NOTES:
 m bgs: meters below ground surface
 RQD: Rock Quality Designation



BOREHOLE No.: BH4-21
ELEVATION: 90.23 m

Page 40
BOREHOLE LOG
 Page: 1 of 2

CLIENT: Consolidated Fastrate (Ottawa) Holdings Ltd.
 PROJECT: ConFastrate, New Warehouse & Offices
 LOCATION: Somme Street, Ottawa, ON
 DESCRIBED BY: J. Scott CHECKED BY: L. Ramos
 DATE (START): 8 July 2021 DATE (FINISH): 28 July 2021

- LEGEND**
- ☒ SS Split Spoon
 - ▨ ST Shelby Tube
 - ▮ RC Rock Core
 - ▽ Water Level
 - Water content (%)
 - ┌ Atterberg limits (%)
 - N Penetration Index based on Split Spoon sample
 - N Penetration Index based on Dynamic Cone sample
 - △ Cu Shear Strength based on Field Vane
 - Cu Shear Strength based on Lab Vane
 - S Sensitivity Value of Soil
 - ▲ Shear Strength based on Pocket Penetrometer

SCALE		STRATIGRAPHY			SAMPLE DATA			
Depth BGS	Elevation (m)	Stratigraphy	DESCRIPTION OF SOIL AND BEDROCK	State	Type and Number	Recovery	Blows per 6 in. / 15 cm	Penetration Index / RQD %
metres	90.23		GROUND SURFACE			%		N
	90.16		TOPSOIL (75 mm)					
			FILL - SILTY SAND, with clay, trace rootlets, brown to grey, moist, stiff		SS1	43	1-2-7.4	9
1.0			asphalt at 0.8 m bgs		SS2	54	7-8-4.9	12
			cobble at 0.9 m bgs					
2.0			cobble at 1.5 m bgs		SS3	21	9-10-7.5	17
					SS4	0	4-2-1.2	3
3.0								
	87.19		FILL - very loose fill mixed with organics/top soil and wood fragments - dark brown, moist		SS5	67	2-1-1.4	2
4.0					SS6	13	5-1-0.1	1
					SS7	17	2-1-1.2	2
5.0					SS8	42	2-1-2.2	3
6.0					SS9A	83	1-3-2.3	5
					SS9B	-	-	
7.0			SILTY SAND - with clay, trace rootlets, brown, moist		SS10	42	4-11-11-15	22
			wet at 6.86 mbgs					
			trace gravel, rootlets stopped at 7.01 mbgs		SS11	83	5-10-12-11	22
8.0			brown with grey mottling, moist at 7.62 m bgs					
					SS12	100	21-27-31-30	58
9.0			wet at 8.69 mbgs					
					SS13	0	22-22-19-36	41
10.0					SS14	71	8-21-20-31	41
					SS15	67	20-16-25-25	41
11.0			moist at 10.82 mbgs					

SCALE FOR TEST RESULTS
 50kPa 100kPa 150kPa 200kPa
 10 20 30 40 50 60 70 80 90

File: G:\11231101\WORKSHARE\FIELD\GINT\LOG\11231101 LOGS - COPY.GPJ Library File: 11231101 GHD_GEO TECH_V10.GLB Report: 11231101 BOREHOLE LOG Date: 24/1/22

NOTES:
 m bgs: meters below ground surface
 RQD: Rock Quality Designation




BOREHOLE No.: BH4-21
ELEVATION: 90.23 m

CLIENT: Consolidated Fastfrate (Ottawa) Holdings Ltd.
 PROJECT: ConFastfrate, New Warehouse & Offices
 LOCATION: Somme Street, Ottawa, ON
 DESCRIBED BY: J. Scott CHECKED BY: Leandro Ramos
 DATE (START): 8 July 2021 DATE (FINISH): 28 July 2021

- LEGEND**
- SS Split Spoon
 - ST Shelby Tube
 - RC Rock Core
 - Water Level
 - Water content (%)
 - Atterberg limits (%)
 - Penetration Index based on Split Spoon sample
 - Penetration Index based on Dynamic Cone sample
 - Shear Strength based on Field Vane
 - Shear Strength based on Lab Vane
 - Sensitivity Value of Soil
 - Shear Strength based on Pocket Penetrometer

File: \\GHDNET\GHD\CA\PETERBOROUGH\PROJECTS\66211231101\WORKSHARE\FIELD\GINT LOG\11231101 LOGS.GPJ Library File: 11231101 GHD_GEOTECH_V10.GLB Report: 11231101 BOREHOLE LOG Date: 12/2/21

SCALE		STRATIGRAPHY			SAMPLE DATA			
Depth BGS	Elevation (m)	Stratigraphy	DESCRIPTION OF SOIL AND BEDROCK	State	Type and Number	Recovery	Blows per 6 in. / 15 cm	Penetration Index / RQD %
metres	90.23		GROUND SURFACE			%		N
	78.80		SILTY CLAY - with sand, trace gravel, reddish brown, moist, hard		SS16	100	13-24-26-22	50
	78.19		Borehole terminated due to auger refusal at 12.04 mbgs. Bedrock or boulder inferred					
			Note: Borehole Coordinate - UTM 18 Zone - Northing: 5017343.6 - Easting: 456673.6					
	12.0							
	13.0							
	14.0							
	15.0							
	16.0							
	17.0							
	18.0							
	19.0							
	20.0							
	21.0							
	22.0							



NOTES:
 mbgs: meters below ground surface
 RQD: Rock Quality Designation



BOREHOLE No.: BH5-21
ELEVATION: 90.39 m

CLIENT: Consolidated Fastfrate (Ottawa) Holdings Ltd.
 PROJECT: ConFastfrate, New Warehouse & Offices
 LOCATION: Somme Street, Ottawa, ON
 DESCRIBED BY: J. Scott CHECKED BY: Leandro Ramos
 DATE (START): 26 July 2021 DATE (FINISH): 26 July 2021

- LEGEND**
- ☒ SS Split Spoon
 - ▨ ST Shelby Tube
 - ▬ RC Rock Core
 - ▼ Water Level
 - Water content (%)
 - ┌ Atterberg limits (%)
 - N Penetration Index based on Split Spoon sample
 - N Penetration Index based on Dynamic Cone sample
 - △ Cu Shear Strength based on Field Vane
 - Cu Shear Strength based on Lab Vane
 - S Sensitivity Value of Soil
 - ▲ Shear Strength based on Pocket Penetrometer

File: \\GHDNET\GHD\CA\PETERBOROUGH\PROJECTS\66211231101\WORKSHARE\FIELD\GINT LOG\11231101 LOGS.GPJ Library File: 11231101 GHD_GEOTECH_V10.GLB Report: 11231101 BOREHOLE LOG Date: 12/6/21

SCALE		STRATIGRAPHY			SAMPLE DATA			
Depth BGS	Elevation (m)	Stratigraphy	DESCRIPTION OF SOIL AND BEDROCK	State	Type and Number	Recovery	Blows per 6 in. / 15 cm	Penetration Index / RQD %
metres	90.39		GROUND SURFACE			%		N
	90.32	▨	TOPSOIL (75 mm) FILL - SILTY CLAY, trace sand, grey, moist, very soft	SS1	21	1-0-0-1	0	●
1.0	89.48	▨	FILL - SANDY SILT, trace clay, trace gravel, dark brown, moist, compact loose at 1.52 mbgs Gravel - 25%, Sand - 38%, Silt - 29%, Clay - 8% with clay, some gravel at 2.29 mbgs	SS2A SS2B	24	2-5-6-7	11	● ○
2.0		▨	shale cobble at 3.2 mbgs	SS3	24	12-5-4-6	9	●
3.0		▨		SS4	24	5-4-2-5-6	6	● ○
4.0		▨		SS5	24	4-3-6-7	9	● ○
5.0	85.82	▨	SILTY SAND - trace clay, trace gravel, brown, moist, compact to very dense Gravel - 10%, Sand - 38%, Silt - 41%, Clay - 11% wet at 5.03 mbgs moist, containing cobbles at 5.33 mbgs	SS7	24	3-5-8-9	13	●
6.0		▨	grey at 6.1 mbgs	SS8	24	14-20-42-42	62	○ ●
7.0		▨	wet, with clay at 6.86 mbgs	SS9	24	8-16-20-20	36	○ ●
8.0	82.52	▨	moist at 7.62	SS10	16	15-34-50/102 mm	84/254 mm	○
8.0	82.52	▨	SANDY SILT - trace clay, grey, moist, very loose	SS11A SS11B	15	23-40-50/76 mm	90/229 mm	○
	82.39		Borehole terminated due to auger refusal at 8.0 mbgs. Bedrock or boulder inferred					
9.0			Note: Borehole Coordinate - UTM 18 Zone - Northing: 5017293.2 - Easting: 456532.1					
10.0								
11.0								

NOTES:
 mbgs: meters below ground surface
 RQD: Rock Quality Designation



BOREHOLE No.: BH1
ELEVATION: 90.21 m

BOREHOLE LOG

Page: 1 of 2

CLIENT: Consolidated Fastrate (Ottawa) Holdings Ltd.
 PROJECT: New Warehouse
 LOCATION: Somme Street, Ottawa, ON
 DESCRIBED BY: RVT CHECKED BY: BV
 DATE (START): 6 August 2020 DATE (FINISH): 6 August 2020

- LEGEND**
- ☒ SS Split Spoon
 - ▬ GS Auger Sample
 - ▨ ST Shelby Tube
 - ▽ Water Level
 - Water content (%)
 - ┌ Atterberg limits (%)
 - N Penetration Index based on Split Spoon sample
 - N Penetration Index based on Dynamic Cone sample
 - △ Cu Shear Strength based on Field Vane
 - Cu Shear Strength based on Lab Vane
 - S Sensitivity Value of Soil
 - ▲ Shear Strength based on Pocket Penetrometer

SCALE		STRATIGRAPHY		MONITOR WELL	SAMPLE DATA			
Depth BGS	Elevation (m)	Stratigraphy	DESCRIPTION OF SOIL AND BEDROCK		Type and Number	Recovery	OVC	Penetration Index / RQD
meters	90.21		GROUND SURFACE			%	ppm	N
90.1			TOPSOIL (75 mm thickness)					
0.5			FILL - Silty sand, trace gravel, loose, brown, damp		SS1	50		5
89.4			FILL - Gravel, trace sand, possible cobble/boulder, compact to dense, grey, damp		SS2	50		47
1.5			FILL - Silty sand, some clay, trace gravel, compact, brown and grey, damp	Riser	SS3	42		20
2.5				Cuttings	SS4	58		19
3.0			FILL - Silty clay, some sand, trace gravel, very stiff, brown and grey, damp		SS5	33		10
3.5			becoming sandy at 3.8 mbgs					
4.0			FILL - Clayey silty sand, compact, grey and brown, moist	WL 3.99	SS6	58		14
4.5				4.57				
5.0				Bentonite	SS7	21		14
5.5				5.18				
5.5				5.49	SS8	46		12
6.0			SILTY SAND - some clay, trace to some gravel, compact, brown and grey, moist	Sand				
6.5				Screen	SS9	54		12

SCALE FOR TEST RESULTS
 50kPa 100kPa 150kPa 200kPa
 10 20 30 40 50 60 70 80 90

BOREHOLE LOG 11215612-A2-BH LOGS.GPJ INSPEC_SOL.GDT 4/9/20

NOTES:
 mbgs: meters below ground surface
 RQD: Rock Quality Designation



BOREHOLE No.: BH1
ELEVATION: 90.21 m

BOREHOLE LOG

Page: 2 of 2

LEGEND

- SS Split Spoon
- GS Auger Sample
- ST Shelby Tube
- Water Level
- Water content (%)
- Atterberg limits (%)
- Penetration Index based on Split Spoon sample
- Penetration Index based on Dynamic Cone sample
- Shear Strength based on Field Vane
- Shear Strength based on Lab Vane
- Sensitivity Value of Soil
- Shear Strength based on Pocket Penetrometer

CLIENT: Consolidated Fastrate (Ottawa) Holdings Ltd.
 PROJECT: New Warehouse
 LOCATION: Somme Street, Ottawa, ON
 DESCRIBED BY: RVT CHECKED BY: BV
 DATE (START): 6 August 2020 DATE (FINISH): 6 August 2020

SCALE		STRATIGRAPHY		MONITOR WELL	SAMPLE DATA					
Depth BGS	Elevation (m)	Stratigraphy	DESCRIPTION OF SOIL AND BEDROCK		State	Type and Number	Recovery	OVC	Penetration Index / RQD	
meters	90.21		GROUND SURFACE				%	ppm	N	
			Refusal encountered at 7.2 mbgs	7.01		SS10	71		50+	
7.5			Cobbles and boulders encountered from 7.3 to 8.2 mbgs			RC1	49			
8.0	82.0		LIMESTONE - interbedded sandstone, grey, fair becoming good quality with depth based on RQD			RC2	94		73	
8.5										
9.0							RC3	100		82
9.5										
10.0						RC4	100		90	
10.5										
11.0										
11.5	78.9		Borehole terminated at 11.3 mbgs							
12.0										
12.5										
13.0										
13.5										

SCALE FOR TEST RESULTS
 50kPa 100kPa 150kPa 200kPa
 10 20 30 40 50 60 70 80 90

NOTES:
 mbgs: meters below ground surface
 RQD: Rock Quality Designation

BOREHOLE LOG 11215612-A2-BH LOGS.GPJ INSPEC_SOL.GDT 4/9/20



BOREHOLE No.: BH2
ELEVATION: 89.80 m

BOREHOLE LOG

Page: 1 of 2

CLIENT: Consolidated Fastrate (Ottawa) Holdings Ltd.
 PROJECT: New Warehouse
 LOCATION: Somme Street, Ottawa, ON
 DESCRIBED BY: RVT CHECKED BY: BV
 DATE (START): 6 August 2020 DATE (FINISH): 6 August 2020

- LEGEND**
- ☒ SS Split Spoon
 - ⊔ GS Auger Sample
 - ▨ ST Shelby Tube
 - ▽ Water Level
 - Water content (%)
 - ┌ Atterberg limits (%)
 - N Penetration Index based on Split Spoon sample
 - N Penetration Index based on Dynamic Cone sample
 - △ Cu Shear Strength based on Field Vane
 - Cu Shear Strength based on Lab Vane
 - S Sensitivity Value of Soil
 - ▲ Shear Strength based on Pocket Penetrometer

SCALE		STRATIGRAPHY			SAMPLE DATA			
Depth BGS	Elevation (m)	Stratigraphy	DESCRIPTION OF SOIL AND BEDROCK	State	Type and Number	Recovery	OVC	Penetration Index / RQD
meters	89.80		GROUND SURFACE			%	ppm	N
89.7		TOPSOIL (75 mm thickness)						
0.5		FILL - Silty clay, firm to stiff, grey, moist			SS1	58		2
1.0					SS2	100		2
1.5					SS3	100		1
2.0					SS4	100		WH
2.5								
3.0								
3.5								
3.5					FV5			
3.5								
4.0	86.0	FILL - Clayey sand, some gravel, organics, loose, grey and brown, moist			SS6	75		5
4.5								
4.5	85.2	FILL - Gravelly sandy silt, compact to very dense, brown and grey, saturated			SS7	83		33
5.0								
5.5					SS8	63		70
6.0								
6.0	83.7	SILTY SAND- some gravel, compact to very dense, grey, moist to saturated			SS9	100		27
6.5								

SCALE FOR TEST RESULTS
 50kPa 100kPa 150kPa 200kPa
 10 20 30 40 50 60 70 80 90

NOTES:
 mbgs: meters below ground surface
 RQD: Rock Quality Designation

BOREHOLE LOG 11215612-A2-BH LOGS.GPJ INSPEC_SOL.GDT 4/9/20



BOREHOLE No.: BH2
ELEVATION: 89.80 m

BOREHOLE LOG

Page: 2 of 2

LEGEND

- SS Split Spoon
- GS Auger Sample
- ST Shelby Tube
- Water Level
- Water content (%)
- Atterberg limits (%)
- Penetration Index based on Split Spoon sample
- Penetration Index based on Dynamic Cone sample
- Shear Strength based on Field Vane
- Shear Strength based on Lab Vane
- Sensitivity Value of Soil
- Shear Strength based on Pocket Penetrometer

CLIENT: Consolidated Fastrate (Ottawa) Holdings Ltd.
PROJECT: New Warehouse
LOCATION: Somme Street, Ottawa, ON
DESCRIBED BY: RVT CHECKED BY: BV
DATE (START): 6 August 2020 DATE (FINISH): 6 August 2020

SCALE		STRATIGRAPHY			SAMPLE DATA			
Depth BGS	Elevation (m)	Stratigraphy	DESCRIPTION OF SOIL AND BEDROCK	State	Type and Number	Recovery	OVC	Penetration Index / RQD
meters	89.80		GROUND SURFACE			%	ppm	N
7.5		Cobbles and boulders encountered from 8.4 to 9.3 mbgs		X	SS10	83		57
8.0				X	SS11	91		70
8.5				X	SS12	100		50+
9.0				X	SS13	100		50+
9.5	80.5		Refusal encountered at 9.3 mbgs	X				
9.5		LIMESTONE- interbedded sandstone, grey, fair to good quality based on RQD			RC1	100		85
11.0					RC2	100		83
12.0	77.6					RC3	100	
12.2			Borehole terminated at 12.2 mbgs					

SCALE FOR TEST RESULTS
50kPa 100kPa 150kPa 200kPa
10 20 30 40 50 60 70 80 90

BOREHOLE LOG 11215612-A2-BH LOGS.GPJ INSPEC_SOL.GDT 4/9/20

NOTES:
mbgs: meters below ground surface
RQD: Rock Quality Designation



BOREHOLE No.: BH3

ELEVATION: 90.88 m

BOREHOLE LOG

Page: 1 of 3

CLIENT: Consolidated Fastrate (Ottawa) Holdings Ltd.

PROJECT: New Warehouse

LOCATION: Somme Street, Ottawa, ON

DESCRIBED BY: RVT CHECKED BY: BV

DATE (START): 7 August 2020 DATE (FINISH): 7 August 2020

LEGEND

- SS Split Spoon
- GS Auger Sample
- ST Shelby Tube
- Water Level
- Water content (%)
- Atterberg limits (%)
- Penetration Index based on Split Spoon sample
- Penetration Index based on Dynamic Cone sample
- Shear Strength based on Field Vane
- Shear Strength based on Lab Vane
- Sensitivity Value of Soil
- Shear Strength based on Pocket Penetrometer

SCALE		STRATIGRAPHY			SAMPLE DATA			
Depth BGS	Elevation (m)	Stratigraphy	DESCRIPTION OF SOIL AND BEDROCK	State	Type and Number	Recovery	OVC	Penetration Index / RQD
meters	90.88		GROUND SURFACE			%	ppm	N
	90.8		TOPSOIL (125 mm thickness)					
0.5			FILL - Clayey silty sand, trace to some gravel, compact, brown and grey, damp		SS1	63		11
1.0	90.0		FILL - Crushed limestone, asphalt, compact, grey and black, damp		SS2	58		42
1.5	89.4		FILL - Sand, trace gravel, clay pockets, asphalt, compact, grey and black, damp to moist		SS3	38		15
2.0								
2.5	88.6		FILL - Silty sand, some gravel, trace clay, possible cobbles/boulders, compact, grey, moist		SS4	33		54
3.0	87.8		FILL - Clayey sand, asphalt, loose to compact, grey and brown, moist		SS5	33		22
3.5								
4.0					SS6	4		8
4.5	86.3		FILL - Silty sand, trace gravel, trace to some clay, dense to very dense, brown and grey, damp to moist, possible cobbles/boulders		SS7	50		54
5.0								
5.5					SS8	33		44
6.0	84.8		SANDY SILT - some gravel, compact to very dense, grey, damp		SS9	83		31
6.5								

SCALE FOR TEST RESULTS
 50kPa 100kPa 150kPa 200kPa
 10 20 30 40 50 60 70 80 90

NOTES:
 mbgs: meters below ground surface
 RQD: Rock Quality Designation

BOREHOLE LOG 11215612-A2-BH LOGS.GPJ INSPEC_SOL.GDT 4/9/20



BOREHOLE No.: BH3
ELEVATION: 90.88 m


BOREHOLE LOG

Page: 2 of 3

CLIENT: Consolidated Fastrate (Ottawa) Holdings Ltd.
 PROJECT: New Warehouse
 LOCATION: Somme Street, Ottawa, ON
 DESCRIBED BY: RVT CHECKED BY: BV
 DATE (START): 7 August 2020 DATE (FINISH): 7 August 2020

- LEGEND**
- SS Split Spoon
 - GS Auger Sample
 - ST Shelby Tube
 - Water Level
 - Water content (%)
 - Atterberg limits (%)
 - Penetration Index based on Split Spoon sample
 - Penetration Index based on Dynamic Cone sample
 - Shear Strength based on Field Vane
 - Shear Strength based on Lab Vane
 - Sensitivity Value of Soil
 - Shear Strength based on Pocket Penetrometer

SCALE		STRATIGRAPHY			SAMPLE DATA			
Depth BGS	Elevation (m)	Stratigraphy	DESCRIPTION OF SOIL AND BEDROCK	State	Type and Number	Recovery	OVC	Penetration Index / RQD
meters	90.88		GROUND SURFACE			%	ppm	N
7.5			Possible cobbles/boulders encountered from 7.6 to 9.1 mbgs		SS10	83		28
8.0					SS11	83		24
8.5					SS12	25		80
9.0					SS13	100		42
9.5			Refusal encountered at 10 mbgs					
10.0			Cobbles and boulders encountered from 10.0 to 11.9 mbgs					
10.5					RC1	32		
11.0								
11.5								
12.0	79.0		LIMESTONE - interbedded sandstone, grey, poor to fair quality based on RQD					
12.5					RC2	100		57
13.0								
13.5			Rock core mechanical breaks during coring from 13.4 to 14.9 mbgs					



BOREHOLE LOG 11215612-A2-BH LOGS.GPJ INSPEC_SOL.GDT 4/9/20

NOTES:
 mbgs: meters below ground surface
 RQD: Rock Quality Designation



BOREHOLE No.: BH3
ELEVATION: 90.88 m

BOREHOLE LOG
 Page: 3 of 3

LEGEND

- SS Split Spoon
- GS Auger Sample
- ST Shelby Tube
- Water Level
- Water content (%)
- Atterberg limits (%)
- N Penetration Index based on Split Spoon sample
- N Penetration Index based on Dynamic Cone sample
- △ Cu Shear Strength based on Field Vane
- Cu Shear Strength based on Lab Vane
- S Sensitivity Value of Soil
- ▲ Shear Strength based on Pocket Penetrometer

CLIENT: Consolidated Fastrate (Ottawa) Holdings Ltd.
 PROJECT: New Warehouse
 LOCATION: Somme Street, Ottawa, ON
 DESCRIBED BY: RVT CHECKED BY: BV
 DATE (START): 7 August 2020 DATE (FINISH): 7 August 2020

SCALE		STRATIGRAPHY			SAMPLE DATA			
Depth BGS	Elevation (m)	Stratigraphy	DESCRIPTION OF SOIL AND BEDROCK	State	Type and Number	Recovery	OVC	Penetration Index / RQD
meters	90.88		GROUND SURFACE			%	ppm	N
	75.9		Borehole terminated at 14.9 mbgs		RC3	92		37
14.5								
15.0								
15.5								
16.0								
16.5								
17.0								
17.5								
18.0								
18.5								
19.0								
19.5								
20.0								
20.5								

SCALE FOR TEST RESULTS
 50kPa 100kPa 150kPa 200kPa
 10 20 30 40 50 60 70 80 90

BOREHOLE LOG 11215612-A2-BH LOGS.GPJ INSPEC_SOL.GDT 4/9/20

NOTES:
 mbgs: meters below ground surface
 RQD: Rock Quality Designation



BOREHOLE No.: BH4
ELEVATION: 90.44 m

BOREHOLE LOG

Page: 1 of 2

CLIENT: Consolidated Fastrate (Ottawa) Holdings Ltd.
PROJECT: New Warehouse
LOCATION: Somme Street, Ottawa, ON
DESCRIBED BY: RVT CHECKED BY: BV
DATE (START): 7 August 2020 DATE (FINISH): 7 August 2020

- LEGEND**
- SS Split Spoon
 - GS Auger Sample
 - ST Shelby Tube
 - ▽ Water Level
 - Water content (%)
 - ┌ Atterberg limits (%)
 - N Penetration Index based on Split Spoon sample
 - N Penetration Index based on Dynamic Cone sample
 - △ Cu Shear Strength based on Field Vane
 - Cu Shear Strength based on Lab Vane
 - S Sensitivity Value of Soil
 - ▲ Shear Strength based on Pocket Penetrometer

SCALE		STRATIGRAPHY			SAMPLE DATA			
Depth BGS	Elevation (m)	Stratigraphy	DESCRIPTION OF SOIL AND BEDROCK	State	Type and Number	Recovery	OVC	Penetration Index / RQD
meters	90.44		GROUND SURFACE			%	ppm	N
	90.3		TOPSOIL (125 mm thickness)					
0.5			FILL - Gravelly sand, compact, grey, damp		SS1	63		33
1.0	89.7		FILL - Sand and gravel, compact, grey, damp		SS2	50		17
1.5			Asphalt encountered at 1.5 mbgs		SS3	54		27
2.0					SS4	58		28
3.0	87.4		FILL - Silty sand, trace clay, trace to some gravel, possible cobbles/boulders, brown and grey, damp to moist		SS5	100		50+
4.0			Wood encountered at 3.8 mbgs		SS6	17		19
5.0					SS7	0		4
5.5					SS8	75		29
6.0	84.3		SILTY SAND- trace to some gravel, trace clay, compact to dense, grey and brown, moist		SS9	79		49
6.5								

SCALE FOR TEST RESULTS
50kPa 100kPa 150kPa 200kPa
10 20 30 40 50 60 70 80 90

BOREHOLE LOG 11215612-A2-BH LOGS.GPJ INSPEC_SOL.GDT 4/9/20

NOTES:
mbgs: meters below ground surface



BOREHOLE No.: BH4
ELEVATION: 90.44 m

BOREHOLE LOG

Page: 2 of 2

LEGEND

- SS Split Spoon
- GS Auger Sample
- ST Shelby Tube
- Water Level
- Water content (%)
- Atterberg limits (%)
- Penetration Index based on Split Spoon sample
- Penetration Index based on Dynamic Cone sample
- Shear Strength based on Field Vane
- Shear Strength based on Lab Vane
- Sensitivity Value of Soil
- Shear Strength based on Pocket Penetrometer

CLIENT: Consolidated Fastrate (Ottawa) Holdings Ltd.
 PROJECT: New Warehouse
 LOCATION: Somme Street, Ottawa, ON
 DESCRIBED BY: RVT CHECKED BY: BV
 DATE (START): 7 August 2020 DATE (FINISH): 7 August 2020

SCALE		STRATIGRAPHY			SAMPLE DATA			
Depth BGS	Elevation (m)	Stratigraphy	DESCRIPTION OF SOIL AND BEDROCK	State	Type and Number	Recovery	OVC	Penetration Index / RQD
meters	90.44		GROUND SURFACE			%	ppm	N
7.5		Soil		X	SS10	4		32
8.0				X	SS11	58		18
8.5				X	SS12	58		44
9.0				X	SS13	67		50
9.5				X	SS14	88		50+
11.0	79.3		Borehole terminated at refusal at 11.1 mbgs					

SCALE FOR TEST RESULTS
 50kPa 100kPa 150kPa 200kPa
 10 20 30 40 50 60 70 80 90

NOTES:
 mbgs: meters below ground surface

BOREHOLE LOG 11215612-A2-BH LOGS.GPJ INSPEC_SOL.GDT 4/9/20



BOREHOLE No.: DCPT5

ELEVATION: 90.76 m


BOREHOLE LOG

Page: 1 of 1

CLIENT: Consolidated Fastrate (Ottawa) Holdings Ltd.
 PROJECT: New Warehouse
 LOCATION: Somme Street, Ottawa, ON
 DESCRIBED BY: RVT CHECKED BY: BV
 DATE (START): 7 August 2020 DATE (FINISH): 7 August 2020

- LEGEND**
- SS Split Spoon
 - GS Auger Sample
 - ST Shelby Tube
 - ▽ Water Level
 - Water content (%)
 - └ Atterberg limits (%)
 - N Penetration Index based on Split Spoon sample
 - N Penetration Index based on Dynamic Cone sample
 - △ Cu Shear Strength based on Field Vane
 - Cu Shear Strength based on Lab Vane
 - S Sensitivity Value of Soil
 - ▲ Shear Strength based on Pocket Penetrometer

SCALE		STRATIGRAPHY			SAMPLE DATA					
Depth BGS	Elevation (m)	Stratigraphy	DESCRIPTION OF SOIL AND BEDROCK	State	Type and Number	Recovery	OVC	Penetration Index / RQD		
meters	90.76		GROUND SURFACE			%	ppm	N		
0.5			Dynamic Cone Penetration test from surface to refusal encountered at 5.9 mbgs							
1.0										
1.5										
2.0										
2.5										
3.0										
3.5										
4.0										
4.5										
5.0										
5.5										
6.0	84.8									
6.5										



NOTES:
mbgs: meters below ground surface

BOREHOLE LOG 11215612-A2-BH LOGS.GPJ INSPEC_SOL.GDT 4/9/20

DATUM Ground surface elevations provided R. W. Tomlinson Limited.


REMARKS

BORINGS BY CME 55 Power Auger

DATE 2019 May 14

FILE NO. **PE4621**

HOLE NO. **BH 1**



100 200 300 400 500
RKI Eagle Rdg. (ppm)
▲ Full Gas Resp. △ Methane Elim.

SOIL PROFILE AND TEST DATA

Phase II - Environmental Site Assessment
Part of 5123 Hawthorne Road - Part 1
Ottawa, Ontario

DATUM Ground surface elevations provided R. W. Tomlinson Limited.

FILE NO. **PE4621**

REMARKS

HOLE NO. **BH 2**

BORINGS BY CME 55 Power Auger

DATE 2019 May 15

SOIL DESCRIPTION	STRATA PLOT	SAMPLE				DEPTH (m)	ELEV. (m)	Photo Ionization Detector				Monitoring Well Construction
		TYPE	NUMBER	RECOVERY %	N VALUE or RQD			● Volatile Organic Rdg. (ppm)				
GROUND SURFACE								○ Lower Explosive Limit %				
								20	40	60	80	
		AU	1			0	92.38					
FILL: Dark brown clayey sand												
0.91		SS	1	70		1	91.38					
FILL: Dark grey gravelly clay, some shale												
1.52		SS	2	70		2	90.38					
FILL: Dark grey gravelly silty sandy clay with shale and cobbles												
2.30		SS	3	90		3	89.38					
Stiff to firm, grey SILTY CLAY		SS	4	90		4	88.38					
		SS	5			5	87.38					
		SS	6									
5.30												
End of Borehole												
Practical refusal to augering at 5.30m depth												
(GWL @ 3.82m - May 28, 2019)												
								100	200	300	400	500
								RKI Eagle Rdg. (ppm)				
								▲ Full Gas Resp. △ Methane Elim.				

DATUM Ground surface elevations provided R. W. Tomlinson Limited.


REMARKS

BORINGS BY CME 55 Power Auger

DATE 2019 May 14

FILE NO. **PE4621**

HOLE NO. **BH 3**





BOREHOLE No.: B5-1
ELEVATION: 90.48 m

BOREHOLE LOG

Page: 1 of 1

CLIENT: R.W.Tomlinson Ltd.
 PROJECT: Geotechnical Investigation
 LOCATION: Lot 26 and 27, concession 6, Ottawa, Ontario
 DESCRIBED BY: B.Beveridge CHECKED BY: J.Bennett
 DATE (START): October 30, 2008 DATE (FINISH): October 30, 2008

- LEGEND**
- ☒ SS Split Spoon
 - ▨ ST Shelby Tube
 - ▭ RC Rock Core
 - ▽ Water Level
 - Water content (%)
 - ← Atterberg limits (%)
 - N Penetration Index based on Split Spoon sample
 - N Penetration Index based on Dynamic Cone sample
 - △ Cu Shear Strength based on Field Vane
 - Cu Shear Strength based on Lab Vane
 - S Sensitivity Value of Soil
 - ▲ Shear Strength based on Pocket Penetrometer

SCALE		STRATIGRAPHY		MONITOR WELL	SAMPLE DATA			
Depth BGS	Elevation (m)	Stratigraphy	DESCRIPTION OF SOIL AND BEDROCK		Type and Number	Recovery	Organic Vapour ppm or %LEL	Penetration Index / RQD
meters	90.48		GROUND SURFACE	91.70 - 91.60 -	State	%	ppm	N
1.0		▨	FILL - silty clay, some sand, gravel, concrete, asphalt and organics, loose to dense, green/brown/grey, moist		SS1	46		6
2.0		▨			SS2	25		10
3.0		▨			SS3	50		4
4.0		▨			SS4	50		9
5.0		▨			SS5	75		50+
6.0	85.15	▨	SANDY SILT- some sand, gravel, trace oxidation, very stiff, greenish brown, moist		SS6	59		10
7.0	83.62	▨	SANDY CLAY- some gravel, trace oxidation, very soft, red / green / grey, moist	6.98 -	SS7	67		50+
8.0	83.16	▨	SILTY CLAY- some gravel, very stiff, grey, moist	7.29 -	SS8	25		50+
9.0		▨		WL 7.63	SS9	42		50+
10.0	80.45	▨	End of Borehole Auger Refusal Assumed Bedrock	8.81 -	SS10	0		R
11.0				10.03 -	SS11	50		R
12.0					SS12	46		R
13.0					SS13	17		R

SCALE FOR TEST RESULTS
 50kPa 100kPa 150kPa 200kPa
 10 20 30 40 50 60 70 80 90

BOREHOLE LOG T020556-A1-BH(OCT-31-08).GPJ INSPEC SOL.GDT 5/12/09

NOTES:



BOREHOLE No.: B5-2
ELEVATION: 90.78 m

BOREHOLE LOG

Page: 1 of 1


CLIENT: R.W.Tomlinson Ltd.
 PROJECT: Geotechnical Investigation
 LOCATION: Lot 26 and 27, concession 6, Ottawa, Ontario
 DESCRIBED BY: B.Beveridge CHECKED BY: J.Bennett
 DATE (START): October 23, 2008 DATE (FINISH): October 23, 2008

- LEGEND**
- SS Split Spoon
 - ST Shelby Tube
 - RC Rock Core
 - ▼ Water Level
 - Water content (%)
 - └ Atterberg limits (%)
 - N Penetration Index based on Split Spoon sample
 - N Penetration Index based on Dynamic Cone sample
 - △ Cu Shear Strength based on Field Vane
 - Cu Shear Strength based on Lab Vane
 - S Sensitivity Value of Soil
 - ▲ Shear Strength based on Pocket Penetrometer

SCALE		STRATIGRAPHY			SAMPLE DATA			
Depth BGS	Elevation (m)	Stratigraphy	DESCRIPTION OF SOIL AND BEDROCK	State	Type and Number	Recovery	Organic Vapour ppm or %LEL	Penetration Index / RQD
meters	90.78		GROUND SURFACE			%	ppm	N
			FILL - silty clay, some asphalt, sand and gravel, trace organics, compact to dense, brown/black, moist		SS1	92		49
1.0					SS2	55		12
2.0					SS3	75		50+
3.0					SS4	63		17
4.0					SS5	71		32
5.0	86.21		SILTY CLAY - some gravel, trace oxidation, firm to stiff, brown/grey, moist to wet		SS6	38		2
6.0					SS7	100		7
7.0	84.07		End of Borehole		SS8	84		R
8.0								
9.0								
10.0								
11.0								
12.0								
13.0								

NOTES:

BOREHOLE LOG T020556-A1-BH(OCT-31-08)GPJ INSPEC SOL.GDT 5/12/09





BOREHOLE No.: B5-3
ELEVATION: 90.51 m

BOREHOLE LOG

Page: 1 of 1

CLIENT: R.W.Tomlinson Ltd.
 PROJECT: Geotechnical Investigation
 LOCATION: Lot 26 and 27, concession 6, Ottawa, Ontario
 DESCRIBED BY: B.Beveridge CHECKED BY: J.Bennett
 DATE (START): October 23, 2008 DATE (FINISH): October 23, 2008

- LEGEND**
- ☒ SS Split Spoon
 - ▨ ST Shelby Tube
 - ▭ RC Rock Core
 - ▼ Water Level
 - Water content (%)
 - Atterberg limits (%)
 - N Penetration Index based on Split Spoon sample
 - N Penetration Index based on Dynamic Cone sample
 - △ Cu Shear Strength based on Field Vane
 - Cu Shear Strength based on Lab Vane
 - S Sensitivity Value of Soil
 - ▲ Shear Strength based on Pocket Penetrometer

SCALE		STRATIGRAPHY			SAMPLE DATA			
Depth BGS	Elevation (m)	Stratigraphy	DESCRIPTION OF SOIL AND BEDROCK	State	Type and Number	Recovery	Organic Vapour ppm or %LEL	Penetration Index / RQD
meters	90.51		GROUND SURFACE			%	ppm	N
1.0	89.75	▨	FILL- concrete and asphalt fragments, some sand, trace organics	▨	SS1	42		50+
	88.99	▨	FILL- silty clay, some gravel, trace oxidation, stiff, brown, moist	▨	SS2	58		15
2.0	88.22	▨	FILL- sandy silt, some gravel, trace clay, organics, very stiff, brownish green, moist	▨	SS3	50		38
		▨	FILL- silty clay, some asphalt, gravel and sand, trace organics, hard, brown, moist	▨	SS4	59		13
4.0	86.70	▨	FILL- silty clay, trace organics, oxidation, gravel, sand, hard, moist	▨	SS5	21		17
5.0			-becoming trace to some gravel	▨	SS6	84		32
			-becoming more asphalt fragments, hard to very stiff	▨	SS7	71		22
6.0	84.41	▨	SILTY CLAY- some sand, trace organics, firm, grey, moist	▨	SS8	25		7
7.0			-becoming very stiff	▨	SS9	59		39
8.0	82.89		End of Borehole					
9.0								
10.0								
11.0								
12.0								
13.0								

SCALE FOR TEST RESULTS
 50kPa 100kPa 150kPa 200kPa
 10 20 30 40 50 60 70 80 90

BOREHOLE LOG T020556-A1-BH(OCT-31-08).GPJ INSPEC SOL.GDT 5/12/09

NOTES:

PREDICTIVE NITRATE IMPACT ASSESSEMENT		
Infiltration Factors		
Topography	0.20	
Soil	0.20	
Cover	0.10	
Total	0.50	
Site Characteristics		
Area of Site :	60893	m ²
Total of roof areas:	5312	m ²
Total area of paved driveway areas:	43365	m ²
Roof + paved driveway areas	48677	m ²
Impervious Area	48677	m ²
Percent Impervious Area =	80	%
Infiltration Area =	12216	m ²
Septic Effluent		
Concentration of Effluent (Cs) =	20	mg/L
Daily Sewage Flow (Qs)=	4.1	m ³
See Notes below.		
Infiltration Calculation		
Nitrate concentration in precipitation (C _i) =	0	mg/L
Surplus Water (Environment Canada)	361	mm/yr
Factored Water Surplus =	181	mm/yr
Infiltration % due to stormwater management measures	-	%
Infiltration rate from stormwater management measures =	0	mm/yr
Infiltration Flow Entering the System (Q _i) =	6	m ³ /day
Mass Balance Model (MOEE, 1995)		
$C_T = (Q_b C_b + Q_e C_e + Q_i C_i) / (Q_b + Q_e + Q_i)$ = Cumulative Nitrate Concentration		
Q _b = flow entering the system across the upgradient area	0	m ³ /day
C _b = background nitrate concentration	0	mg/L
Q _e = flow entering the system from the septic drainfield	4.1	m ³ /day
C _e = concentration of nitrates in the septic effluent	20	mg/L
Q _i = flow entering the system from infiltration	6	m ³ /day
C _i = Concentration of nitrates in the infiltrate	0	mg/L
C_T =	8.09	mg/L
Estimate Number of Lots	1	lots
<i>Notes: Site characteristic values were measured as approximate values from the available site plan. Daily Sewage Flow volume was calculated by Paterson Group as a preliminary design flow.</i>		

MW1 inputs			
pH	8.2	A	0.19
TDS	787	B	2.35
Calcium	128	C	1.71
Alkalinity	306	D	2.49
Temp.	11.4		
		pHs =	7.651109829

Langelier Saturation Index (LSI) Calculation		(Langelier, 1936)
LSI = pH - pHs	A = (Log10 [TDS] - 1) / 10	
pHs = (9.3 + A + B) - (C + D)	B = -13.12 x Log10 (oC + 273) + 34.55	
Where:	C = Log10 [Ca2+ as CaCO3] - 0.4	
	D = Log10 [alkalinity as CaCO3]	
		LSI = 0.5
LSI	Effect	
0.5 to 2	Water is super saturated and tends to precipitate a scale layer of calcium carbonate (scale forming but non-corrosive)	
0 to 0.5	Water is super saturated and tends to precipitate a scale layer of calcium carbonate (slightly scale forming and corrosive).	
0	Water is saturated (in equilibrium) with calcium carbonate. A scale layer of calcium carbonate is neither precipitated nor dissolved.	
0 to -0.5	Water is under saturated and tends to dissolve solid calcium carbonate (slightly corrosivebut non-scale forming).	
-0.5 to -2	Water is under saturated and tends to dissolve solid calcium carbonate (seriously corrosive).	



Manganese in Drinking Water Fact Sheet

WHAT IS MANGANESE?

Manganese is a naturally occurring element that is an essential nutrient for humans and animals. It is found in many foods, as well as in air, water, soil, and rocks.¹ Manganese makes up 0.1% of the Earth's crust, and can be found as a component of other minerals like sulfides, oxides, carbonates, and silicates.² Manganese is used in the manufacture of various products including iron and steel alloys, batteries, glass, fireworks, fertilizers, cosmetics, paints, and cleaning and disinfection products.^{1,2} Manganese can also be purchased as a nutritional supplement.²

HOW DOES MANGANESE GET INTO DRINKING WATER?

Manganese is naturally occurring in many surface and ground waters. Manganese can also be dissolved from soils, sand and rocks to enter surface and ground waters.¹ Human activities like mining, industrial discharges, or landfills may also contribute to manganese in surface and ground waters.^{1,2} In general, manganese can be found at higher concentrations in groundwater compared to surface water.² Some lakes and reservoirs can also have higher levels of manganese due to natural water chemistry.²

Permanganate, a compound that contains manganese, may also be added to water during the treatment of drinking water to remove other chemicals (e.g., for the removal of iron).^{2,3}

HOW DOES MANGANESE INTAKE AFFECT MY HEALTH?

Too much or too little manganese in your body can lead to health problems.

Manganese deficiency: Manganese deficiency is rare and symptoms are not well defined. Health effects observed in individuals with diets very low in manganese include skin rashes, slow nail growth, reduced bone density, loss of pigmentation in hair, and low cholesterol levels.²

Manganese excess: There are few reports of adverse health effects from people who ingest too much manganese from food and water.¹ Recent evidence reviewed by Health Canada indicates that high levels of manganese in drinking water may impact memory and learning, behaviour, and fine motor control in infants and young children.^{2,4} Formula-fed infants may be more susceptible to health risks if water with high concentrations of manganese is used to prepare formula. This is because infant brains are rapidly developing, they drink more water in proportion to their body weight, and they absorb more manganese and are less able to remove

it from their bodies compared to other age groups.³ For adults and older children, short term exposure to manganese in drinking water at levels slightly above the guideline is unlikely to cause negative health effects.³

Health Canada notes that exposure to manganese while showering (either through breathing in water vapour or absorption through skin) is likely to be negligible.²

WHAT ARE THE LEVELS OF MANGANESE FOUND IN CANADIANS?

For most Canadians, diet is the main source of manganese. The Canadian Health Measures Survey (CHMS) is a national survey that collects information about the general health of Canadians and includes measurements of chemicals in blood and urine samples.⁵ The objective of the chemical measurements in the CHMS survey is to establish baseline levels in the Canadian population. Given that manganese is an essential trace element, its presence in the blood and urine of Canadians is expected. Manganese in blood and urine can be interpreted as an indicator of exposure, but does not necessarily mean that health effects will occur.⁵ Data collected from 2007 to 2011 for the CHMS found that the average levels of manganese measured in the blood of people in the Canadian population (aged 3 to 79) ranged from 8.8 – 11 µg/L.⁶ More information on the CHMS and the levels of manganese in Canadians can be obtained by visiting the Canadian Biomonitoring Dashboard.⁶

ARE THERE STANDARDS FOR MANGANESE IN DRINKING WATER?

The Ontario Drinking Water Standard (ODWS) published in 2006 sets an aesthetic objective for manganese in drinking water at 0.05 mg/L.⁷ The aesthetic objective is not intended to prevent health effects (e.g., not a health-based standard), but instead is intended to prevent the discolouration and staining of fixtures, and the undesirable taste caused by higher levels of manganese in water.

The Canadian Drinking Water Guideline for manganese developed by Health Canada stipulates a maximum acceptable concentration (MAC) in drinking water of 0.12 mg/L and an aesthetic objective of 0.02 mg/L.² The MAC is a health-based value intended to be protective of neurological effects in infants, the most sensitive population, and therefore it is also protective for chronic exposure in children and adults.²

ARE THERE OTHER STANDARDS OR GUIDELINE VALUES FOR MANGANESE?

The main source of exposure to manganese is via food, with grains, nuts and vegetables contributing the most to a person's daily intake of manganese. The average dietary intakes of manganese across all age groups according to the Canadian Total Diet Study (TDS) were estimated to range between 44.0 to 61.3 µg/kg of bodyweight per day (based on data gathered from different Canadian cities for the TDS).² Health Canada has also established Adequate Intake Levels for manganese ranging with age or lifestage from 0.003 to 2.6 mg/day and Tolerable Upper Intake Levels ranging from 2 to 11 mg/day.⁸

Infant formula sold in Canada is regulated to contain a minimum of 5 µg of manganese per 100 available kilocalories (equivalent to 3.33 µg per 100 mL of ready-to-feed formula); a maximum amount of manganese has not been set for infant formula.⁹

HOW CAN I TELL IF MY DRINKING WATER HAS HIGH MANGANESE LEVELS?

Water testing is the only way to know if manganese is present. Although water with elevated levels of manganese may impart a bitter metallic taste, tint water purplish brown or black (water discolouration may occur at concentrations as low as 0.005 to 0.02 mg/L), and stain laundry and plumbing fixtures;^{2,10,11} but these issues can also be caused by other chemicals.

WHAT SHOULD I DO IF A HIGH LEVEL OF MANGANESE IS FOUND IN MY WELL WATER?

For households who do not obtain their drinking water from a municipal source, a residential drinking water treatment device may be an option to reduce manganese concentrations in drinking water. Options can be explored with professionals specialized in water treatment, but examples of treatment processes effective at removing manganese include reverse osmosis, ion exchange (including water softeners and other cation exchange systems) and oxidizing filters.² As with any water treatment system, it is important to follow the manufacturer's recommendations for operation and maintenance (e.g., replacement of filter media).

REFERENCES


1. United States Environmental Protection Agency (US EPA). Drinking Water Health Advisory for Manganese [Internet]. 2004. Available from: https://www.epa.gov/sites/default/files/2014-09/documents/support_cc1_magnese_dwreport_0.pdf
2. Health Canada. Guidelines for Canadian Drinking Water Quality: Guideline Technical Document – Manganese [Internet]. 2019. Available from: <https://www.canada.ca/en/health-canada/services/publications/healthy-living/guidelines-canadian-drinking-water-quality-guideline-technical-document-manganese.html>
3. Health Canada. Water Talk - Manganese in drinking water [Internet]. 2023. Available from: <https://www.canada.ca/en/health-canada/services/environmental-workplace-health/reports-publications/water-quality/water-talk-manganese.html>
4. HealthLink British Columbia. Manganese in Drinking Water [Internet]. Available from: <https://www.healthlinkbc.ca/healthlinkbc-files/manganese-drinking-water>
5. Health Canada. Second Report on Human Biomonitoring of Environmental Chemicals in Canada: Manganese [Internet]. 2013. Available from: <https://www.canada.ca/en/health-canada/services/environmental-workplace-health/reports-publications/environmental->

contaminants/second-report-human-biomonitoring-environmental-chemicals-canada-health-canada-2013.html#a8.9

6. Government of Canada. Canadian Biomonitoring Dashboard [Internet]. 2024. Available from: <https://health-infobase.canada.ca/biomonitoring/about.html>
7. Ontario Ministry of the Environment, Conservation and Parks. Technical Support Document for Ontario Drinking Water Standards, Objectives and Guidelines [Internet]. 2006. Available from: <https://wccw.ca/wp-content/uploads/2021/08/Technical-Support-Document-for-Ontario-Drinking-Water-Standards-Objectives-and-Guidelines.pdf>
8. Health Canada. Dietary reference intakes tables: Reference values for elements [Internet]. 2023. Available from: <https://www.canada.ca/en/health-canada/services/food-nutrition/healthy-eating/dietary-reference-intakes/tables/reference-values-elements.html#tbl2>
9. Government of Canada. Food and Drug Regulations (C.R.C., c. 870) [Internet]. Available from: https://lois-laws.justice.gc.ca/eng/regulations/C.R.C.%2C_c._870/page-53.html
10. United States Environmental Protection Agency (US EPA). Secondary Drinking Water Standards: Guidance for Nuisance Chemicals [Internet]. 2024. Available from: <https://www.epa.gov/sdwa/secondary-drinking-water-standards-guidance-nuisance-chemicals>
11. World Health Organization (WHO). Manganese in drinking-water: Background document for development of WHO Guidelines for drinking-water quality [Internet]. 2021. Available from: <https://www.who.int/publications/i/item/WHO-HEP-ECH-WSH-2021.5>

Please note: This fact sheet was created by Ottawa Public Health in consultation with Public Health Ontario.

Manganese in Drinking Water Fact Sheet [Last updated: September 12, 2024]



- LEGEND:**
- BOREHOLE LOCATION
 - BOREHOLE WITH MONITORING WELL LOCATION
 - BOREHOLE LOCATION (PATERSON GROUP REPORT: PE4621, MAY 2019)
 - BOREHOLE WITH MONITORING WELL LOCATION (PATERSON GROUP REPORT: PE4621, MAY 2019)
 - BOREHOLE LOCATION (GHD, JULY 2021)
 - BOREHOLE LOCATION (GHD, AUGUST 2020)
 - BOREHOLE LOCATION (INSPECSOL, 2008)
 - SURVEY SHOT LOCATION (DECEMBER 8, 2023)
 - SURVEY SHOTS LOCATION (JUNE 3, 2025)
 - SLOPE STABILITY CROSS SECTION
 - 92.85 GROUND SURFACE ELEVATION (m)
 - {79.40} PRACTICAL REFUSAL TO AUGERING ELEVATION (m)
 - (89.90) PRACTICAL DCPT REFUSAL ELEVATION (m)

CONCEPTUAL PLAN PREPARED BY HOBIN ARCHITECTURE

GROUND SURFACE ELEVATION AT PATERSON 2019 BOREHOLE LOCATIONS WERE PROVIDED BY R.W. TOMLINSON LIMITED.

SCALE: 1:1500



NO.	REVISIONS	DD/MM/YYYY	INITIAL
1	UPDATED TO NEW CONCEPTUAL PLAN	14/08/2025	SD

W.O. STINSON & SON LTD.
GEOTECHNICAL INVESTIGATION
PROPOSED COMMERCIAL DEVELOPMENT
301 SOMME STREET

OTTAWA, ONTARIO

Title: **TEST HOLE LOCATION PLAN**

Scale:	1:1500	Date:	07/2025
Drawn by:	ZS	Report No.:	PG7567-1
Checked by:	PB	Dwg. No.:	PG7567-1
Approved by:	SD	Revision No.:	1



Hydrogeological and Impact Assessment Report

**Proposed Commercial Development, 301
Somme Street, Ottawa, Ontario**

Consolidated Fastfrate (Ottawa) Holdings Inc.

September 22, 2022

→ **The Power of Commitment**



Contents

1.	Introduction	1
2.	Background	2
2.1	Site Description	2
2.2	Regional Setting	2
2.3	Previous Investigations	2
3.	Methodology	3
3.1	Existing Local Water Supplies	3
3.2	Health and Safety	4
3.3	Site Inspection and Well Survey	5
3.4	Aquifer Performance Testing	5
3.4.1	Test Well Information	5
3.4.2	Pumping Test Methodology	6
4.	Geology and Hydrogeology	6
4.1	Site Geology	6
4.2	Site Hydrogeology	7
4.2.1	Hydrostratigraphic Units	7
4.2.2	Groundwater Levels	7
4.3	Aquifer Performance Assessment	8
4.3.1	Pumping Test	8
4.3.2	Summary of Aquifer Performance	8
4.3.3	Water Quality	9
4.3.3.1	Water Treatment	13
4.3.4	Well Interference	13
4.3.4.1	Interference Assessment	14
4.4	Septic Waste Disposal	15
5.	Water Quality Impact Assessment	15
6.	Construction Dewatering	16
6.1.1	Groundwater Sampling for Construction Dewatering	16
7.	Summary and Recommendations	16
8.	References	18
9.	Statement of Limitations	19

Table Index

Table 3.1	Summary of MECP Well Record Data	4
Table 4.1	Water Level Summary	7
Table 4.2	Aquifer Performance Testing Summary	8
Table 4.3	Test Well Water Quality Summary	9
Table 4.4	Distance Between Pumping Well and Observation Wells	14
Table 4.5	Maximum Drawdowns in Pumping and Observation Wells	14

Figure Index

Figure 1	Site Location Plan.....	21
Figure 2	Concept Plan	22
Figure 3	Regional Topography	23
Figure 4	Physiography	24
Figure 5	Surficial Geology.....	25
Figure 6	Quaternary Geology	26
Figure 7	Bedrock Geology	27
Figure 8	Well Locations	28

Appendices

Appendix A	MECP Well Records
Appendix B	Photographs
Appendix C	Well Record A342117 and WSP Well Certificate
Appendix D	Calibration Records
Appendix E	Aquifer Performance Testing
Appendix F	Water Well Certificates of Analyses
Appendix G	MacLellan Water Treatment Recommendations
Appendix H	Observation Well Hydrographs
Appendix I	Storm Sewer Use Certificate of Analysis

1. Introduction

GHD Limited (GHD) was retained by Consolidated Fastfrate (Ottawa) Holdings Inc. to conduct a hydrogeological impact assessment in support of a proposed commercial development at the intersection of Rideau Road and Somme Street in Ottawa (the Site). The municipal address is 301 Somme Street, Ottawa, Ontario and is geographically located at Lot 26, Gloucester Concession 6 from the Rideau River. The Site encompasses an area on the order of 7.0 ha (17.4 acres) and is currently vacant of structures. The development will be privately serviced with a well and septic system. The location of the Site is provided on the **Site Location Plan, Figure 1**.

The purpose of this hydrogeological and impact assessment was to assess the groundwater conditions to evaluate that sufficient drinking water supply exists for the proposed development in accordance with the City of Ottawa Hydrogeological and Terrain Analysis Guidelines (HTAG). Groundwater conditions were assessed through a constant rate pumping test and data collection to evaluate potential impacts to the local groundwater regime (quality and quantity).

The scope of work included a desktop review of available geological and groundwater mapping; a review of the Ministry of the Environment, Conservation and Parks (MECP) well records; a water well survey within 500 m of the development; and a 12-hour, constant rate pumping test with recovery measurements.

This report is organized into the following sections:

Section 1.0 – Introduction: Outlines the purpose, objectives and scope of work, and presents the report organization.

Section 2.0 – Background: Provides a description of the existing Site conditions, background information and surrounding land uses, as well as an outline of the proposed development. The regional environmental setting, including the physiography, topography, surface water features in the vicinity, and the surficial geology is presented.

Section 3.0 – Methodology: Describes the field activities and methodologies used to assess the groundwater supply and quality and to evaluate potential impacts associated with the undertaking.

Section 4.0 – Geology and Hydrogeology: Provides a detailed description of the Site geology, hydrogeology, and the hydraulic properties of the underlying stratigraphy and aquifer.

Section 5.0 – Water Quality Impact Assessment: Provides information regarding the water quality impact related to the proposed septic system.

Section 6.0 – Construction Dewatering: Provides a summary of the shallow groundwater quality compared to the Ottawa Storm Sewer Use By-Law 2003-514, which addresses discharge to the Municipal sewage system for potential construction dewatering.

Section 7.0 – Summary and Conclusions: Provides a summary of the assessment findings. Sections 8 and 9 provide a Statement of Limitations and References. The Figures and Appendices are provided following the text of this report, as indicated in the Table of Contents. Tabulated data is presented in tables within the text.

The factual data, interpretations and recommendations contained in this report pertain to a specific project as described in the report and are not applicable to any other project or site location. This report should be read in conjunction with the Statement of Limitations appended to this report. The reader's attention is specifically drawn to this information, as it is essential for the proper use and interpretation of this report.

2. Background

2.1 Site Description

The Site is located at the intersection of Rideau Road and Somme Street in Ottawa, Ontario. The parcel has the municipal address of 301 Somme Street and currently vacant of structures. Surrounding lots consisted of commercial / industrial lots to the west and south, undeveloped and forested lands and a few residential lots. The lands to the north, east and south are privately serviced for water and sanitary services; with municipally services lots located to the west of the Site. Findlay Creek flows from west to east along the northern Site boundary on the south side of Rideau Road.

The proposed development is to consist of a one-storey warehouse with office space and various amenities covering a total building area of 8,641 square metres (m²) with a projected occupancy of 36 staff. The Site will also have asphalt parking, a stormwater pond and septic bed area as depicted in the **Concept Plan, Figure 2**. The drilled water well location is also shown on **Figure 2** and will service the development.

2.2 Regional Setting

The Site is relatively flat with the regional topography sloping generally towards the east / northeast. Topographic relief is on the order of 3 to 4 metres across the Site. Regional topography is provided as **Figure 3**. Excess surface water is directed towards ditches alongside the Site with drainage generally to the east / northeast.

The Site is situated within the physiographic region known as the Russell and Prescott Sand Plains. In the United Counties of Prescott and Russell, and the Regional Municipality of Ottawa-Carleton, there is a group of large sand plains separated by the clays of the lower Ottawa Valley. The plains cover an area of nearly 1500 square kilometers and a level surface of about 85 metres above sea level. The plains were originally a continuous delta that was built by the Ottawa River into the Champlain Sea. The plains are as thick as 6 to 10 m in some areas (Chapman and Putnam, 1984). The local physiography is illustrated on **Figure 4** showing the Site is within a sand plains with Peat and Muck to the north and Limestone Plains to the west.

Surficial geology mapping on **Figure 5** indicates the Site is a mix of organic deposits, coarse textured glaciolacustrine deposits and Paleozoic bedrock. Based upon GHD's previous geotechnical work (GHD, 2020), the upper soils are comprised of fill. Underlying the fill is native silty sand / sandy silt followed by a glacial till (GHD, 2020).

The Quaternary geology (**Figure 6**) suggests carbonate and clastic sedimentary rock exposed at surface or covered by a discontinuous thin layer of drift. Bedrock outcrops are common in the area; however, were not observed on the Site.

The bedrock is Dolostone / Sandstone of the Beekmantown group (**Figure 7**). Based upon water well records, bedrock was found varying from 8.5 metres below ground surface (mbgs) to 14.0 mbgs at the Site. Golder's report also outlined the Gloucester Fault, a major northwest-southeast trending, steeply dipping structural feature in close proximity and northeast of the Site.

2.3 Previous Investigations

GHD and others have completed various studies at the Site. GHD has considered them, where applicable, in this report. The studies include:

- GHD Limited, November 2, 2021. Hydrogeological Assessment – Large Sewage Disposal System. Rideau Road and Somme Street. Ottawa Ontario. Project No. 12565773-01
- GHD Limited, April 12, 2021. Terrain Analysis. Septic Assessment and Percolation Rate Evaluation. Proposed Commercial Development – Rideau Road and Somme Street. Gloucester Con 6 from Rideau River, Lot 26, Ottawa Ontario. Project No. 11220832-01

- GHD Limited, January 19, 2021. Hydrogeological Assessment Report. Proposed Commercial Development – Rideau Road and Somme Street. Gloucester Con 6 from Rideau River, Lot 26, Ottawa Ontario. Project No. 11220832-01;
- GHD Limited, September 10, 2020. Geotechnical Investigation. Warehouse and Offices. Intersection of Rideau Street and Somme Street, Ottawa Ontario. Project No. 11215612-01;
- Stormwater Management Report. Hawthorne Industrial Park, Report Reference. No. JLR 20983, by J.L. Richards & Associates Limited, dated February 2009 (Revised May 2009);
- Geotechnical Study Subdivision Plan, Hawthorne Industrial Park, Report Reference No. T020556-A1, by Inspec-Sol, dated May 4, 2009;
- Phase II Environmental Site Assessment and Hydrogeological Assessment, Report Reference No. 045804 (12), by Conestoga-Rovers & Associates, dated September 2008; and
- Hydrogeological Investigation, Terrain Analysis and Impact Assessment, Proposed Industrial Subdivision, Report Reference. No. 08-1122-0215, by Golder Associates, dated December 2008.

3. Methodology

To achieve the purpose and objectives of this assessment, the following activities were undertaken:

- Review of existing local water supplies by reviewing MECP water well records within 500 m of the Site;
- Completion of a Health and Safety Plan for field activities;
- Site inspection and well survey of local water wells within approximately 500 m of the pumping test wellhead;
- Aquifer performance testing and water level monitoring of observation wells

3.1 Existing Local Water Supplies

The Site and areas surrounding the Site are generally privately serviced with municipal services present to the west of the Site. Physical and hydraulic data are presented on MECP well records (**Appendix A**). The well records indicate a mix of overburden materials (fill, sand, clay, gravel etc.) overlying bedrock including shale, sandstone, limestone and quartz. Based upon the well records, there is one (1) primary bedrock aquifer in this immediate area that is tapped by drilled wells. Of the 17 records, seven (7) are for monitoring wells and will not be considered further within this discussion.

The groundwater was generally described as “fresh” in the well records reviewed. The information from the MECP data indicates that all ten (10) wells were drilled bedrock wells averaging a depth of about 41 m. The bedrock wells encountered water at an average depth of 31 m with pumping rates averaging nearly 100 L/min. No flowing artesian wells were reported.

No dug / bored well records were reviewed. Shallow dug / bored wells are susceptible to large seasonal fluctuations in the groundwater. The result is that shallow wells are also more prone to becoming dry in the winter and summer months. From a quality perspective, shallow dug / bored wells are generally difficult to seal at the surface and therefore considered to be susceptible to shallow sources of contamination and are not recommended for this commercial development.

Table 3.1 summarizes the data reviewed in the well records within 500 m of the Site:

Table 3.1 Summary of MECP Well Record Data

Total Number of Wells Inventoried: 17 Dug/Bored Wells: 0 (0%) Drilled Wells (Overburden): 0 (0%) Drilled Wells (Bedrock): 10 (59%) NOT INCLUDED IN STATISTICAL SUMMARY: Abandonments, Monitoring Wells, Unknown Wells: 7 (41%)				
Parameters	Statistical Summary			
	Drilled – Overburden		Drilled– Bedrock	
WELL YIELDS				
Range	--	--	19 to 680 L/min	5 to 180 USgpm
Average	--	--	99.1 L/min	26.2 USgpm
REPORTED YIELDS	Frequency		Frequency	
Not Reported	0	0%	0	0%
Dry	0	0%	0	0%
0 to 1 USgpm	0	0%	0	0%
2 to 4 USgpm	0	0%	0	0%
5 to 9 USgpm	0	0%	6	60%
≥10 USgpm	0	0%	4	40%
STATIC WATER LEVELS				
Range	--	--	2.3 to 14.2 m	7.5 to 46.6 ft
Average	--	--	8.4 m	27.6 ft
WATER ENCOUNTERED				
Range	--	--	9.1 to 75.0 m	30 to 246 ft
Average	--	--	31.2 m	103.5 ft
WELL DEPTH				
Range	--	--	17.4 to 75.6 m	57 to 248 ft
Average	--	--	40.8 m	133.9 ft

Notes:

Data based on MECP well record information (refer to **Appendix A** for well information).

*Abandonments, well upgrades and unknown well records are not included in the statistical data summarized in **Table 3.1**

3.2 Health and Safety

A Site-specific Health and Safety Plan (HASP) was prepared for implementation during the field investigation program. The HASP presents the visually observed Site conditions to identify potential physical hazards to field personnel. Required personal protective equipment was also listed in the HASP. It is mandatory for all GHD personnel involved in the field program, to read and have a copy of the HASP available at the Site during the investigative work. Health and Safety requirements in the HASP were implemented during the field investigation program.

In addition to the abovementioned safety measures, GHD’s safety protocol related to COVID-19 issues was implemented and preventive measures were reinforced.

3.3 Site Inspection and Well Survey

The field work was conducted on August 9 and 10, 2022 by GHD to observe the general surficial characteristics of the Site, neighbouring lands and complete the well survey and pumping test. The Site consists of undeveloped lands. Photographs are provided in **Appendix B**.

GHD observed the drilled water well and a monitoring well on the Site. Other water wells in the vicinity of the Site were also observed. No surface water was observed on the Site.

The well survey was conducted on August 9, 2022 and involved collecting water levels from local area wells. There is one home within 500 m of the Site located at 4885 Hawthorne Road. This residential dwelling utilizes a drilled well that was measured by GHD to be 15 metres deep. The owner did not indicate any issues with water quantity or quality. The owner also provided authorization to use the well for monitoring purposes during our pumping test.

GHD also collected information from commercial properties located at 3500 Rideau Road to the west (MECP tag no. A018916), 5213 Hawthorne Road to the south (MECP tag no. A342260) and 300 Somme Street to the south (MECP tag no. A305146). No issues were communicated to GHD regarding the wells from these commercial properties. These wells were also monitored during GHD's pumping test. The locations of the various water wells / observation wells utilized for monitoring in this assessment and included in the well survey is provided on the **Well Location Plan, Figure 8**. The MECP tag numbers are referenced on **Figure 8**.

3.4 Aquifer Performance Testing

3.4.1 Test Well Information

An onsite drilled well was utilized for assessment of the local aquifer via a pumping test. The well was constructed by Air Rock Drilling Co Ltd with drilling completed on July 27, 2022. The well has a MECP well tag number of A342117 and its location is shown on **Figure 2**. The water well record and Certificate of Well Compliance is provided in **Appendix C**.

A summary of the information presented on the water well record, is as follows:

- Drilled to total depth of 42.7 m (140 feet). The well record indicates overburden materials consisting of gravel, hardpan and boulders to 14 m (46 feet) followed by grey and black limestone with white sandstone mix to the depth of the well. The well is considered to be a confined well within the sandstone;
- Water was encountered at 39 m and 40.8 m (128 and 134 feet) and was not tested. The static water level was 8.6 m resulting in an available drawdown of 34.1 m to the bottom of the well;
- Construction was completed on July 27, 2022. Constructed with steel casing to 15.8 m (52 feet) then open hole to the bottom of the well. From grade to 15.8 m, the annular space was grouted and sealed with neat cement slurry with a total volume of about 0.4 cubic metres (~12.5 cubic feet). As per previous recommendations, the well was constructed with greater than 6 m of casing and 2 m into the bedrock;
- The well was tested by the drillers at 75.6 litres per minute or L/min (20 gallons per minute or gpm) resulting in a drawdown of 0.7 m or about 2% of the available drawdown. The well is recommended for pumping at 75.6 L/min; and
- The well is drilled 4 m from the proposed building and 3 m from a proposed paved walkway. The ground surface is to be positively sloped away from the water well in all directions (refer to the inset illustrated on **Figure 2**).

Adjacent water wells, monitoring well MW22-1 and a residential well that were monitored during testing are illustrated on **Figure 8**.

3.4.2 Pumping Test Methodology

GHD completed a constant rate pumping test of well A342117 on August 9, 2022 to assess aquifer conditions and evaluate the availability of a suitable groundwater resource for the proposed commercial development. The pumping test was conducted for twelve (12) hours at a constant rate of 37.8 L/min (10 gpm). Recovery measurements were collected after the pumping was completed.

A submersible pump was installed in the well to conduct the testing. Water levels in the pumped water well, adjacent observation wells and an onsite shallow monitoring well were monitored throughout the aquifer performance testing. Measurements were collected manually and through the use of data loggers to evaluate drawdown, recovery and the potential of mutual interference with adjacent wells. The discharge water was directed away from the pumped well a distance of about 30 m downgradient and also away from observation wells. This practice safeguards against artificial recharge of the well from occurring during the pumping test.

The pumped water well was chlorinated in advance of the pumping test. Non-detect chlorine levels were confirmed in the field prior to bacteria sampling conducted at the water well.

Water samples were collected throughout the testing and submitted to SGS Environmental Laboratories (SGS), a CALA accredited analytical laboratory for the testing. Water samples were collected for the following parameters:

- Polycyclic aromatic hydrocarbons (sampled after 12 hours of pumping);
- Volatile organic compounds (sampled after 12 hours of pumping);
- Petroleum hydrocarbons fractions F1 – F4 (sampled after 12 hours of pumping);
- Trace metals (filtered) (sampled after 12 hours of pumping);
- Bacteriological parameters including total coliform; E.coli, fecal coliform (sampled after 1, 6 and 12 hours of pumping); and
- General chemistry, Ottawa subdivision package and D-5-5 parameters.

Field measurements of methane, pH, temperature, free chlorine, turbidity, and conductivity were completed with a turbidity meter, Hach Pocket Pro+ Multi 2 and chlorine meter. Water levels were collected from the pumped water well using a dedicated, audible water level meter and a data logger. Water levels were also collected from neighbouring wells using an audible water level meter. Calibration of these instruments / equipment was completed prior to the pumping test. The calibration records are provided in **Appendix D**.

4. Geology and Hydrogeology

The following sections provide a detailed description of the geology and hydrogeology of the Site, based on the results of the investigations completed and on the available background information.

4.1 Site Geology

Based upon information reviewed within GHD's geotechnical report, the following are the predominant surficial materials and geologic deposits that underlie the Site:

- Ground Cover and Fill (ground surface up to 6 m thick) – topsoil, silty sand to gravel to silty clay fill
- Native sandy silt / silty sand (depths ranging from 8.2 to 11.9 mbgs)
- Bedrock (8.2 to 14.0 mbgs)

The depths of the materials listed above vary within the Site and have been simplified for purposes of this report.

4.2 Site Hydrogeology

4.2.1 Hydrostratigraphic Units

The primary hydrostratigraphic units (i.e. aquifer/aquitard units) underlying the Site include the following:

- Shallow, unconfined unit of fill and native soil and upper bedrock zone
 - Shallow groundwater found within the fill
 - Shallow unit is not suitable as a water supply
- Deeper confined aquifer within the sandstone bedrock generally at depths between about 25 m and 40 mbgs. This is the aquifer tapped by the drilled well on the Site.

4.2.2 Groundwater Levels

Water levels were obtained from the new supply well (MECP tag no. A342117), a monitoring well installed on the Site (MW22-1), and the nearby commercial and residential wells shown in **Table 4.1** on August 9, 2022 prior to the commencement of the pumping test. The data is summarized in **Table 4.1**. Based upon the water levels obtained from these wells, the groundwater flow tapped by the drilled wells is generally in an easterly direction including northeast and southeast components (note: groundwater elevations are based upon regional topographic contours and are for the purposes of evaluation potentiometric elevations only). Shallow groundwater flow tapped by monitoring wells was not assessed.

Table 4.1 Water Level Summary

Location	Description	Ground Elevation* (m)	Depth of Well (mbgs)	Water Level (mbgs)	Potentiometric Elevation (masl)
				August 9, 2022	
A342117	New Site water well	91.1	42.7	7.31	85.8
MW22-1	New Site monitoring well	91.4	3.7	2.05	89.4
4885 Hawthorne Rd	Residential well	85	15.2	0.95	84.1
3500 Rideau Rd	A018916 – Commercial property	100	35.4	11.80	88.2
5213 Hawthorne Rd	A342260 – Commercial property	95	>30	10.60	84.4
TW-5	A295342	90	29.9	6.70	83.3
300 Somme St	A305146 – Commercial property	85	42.7	7.42	77.6

Notes:

masl = metres above sea level

*Elevations estimated from regional topographic contours provided on Figure 3; and elevations on the Site are based upon a topographic elevations provided to GHD. The elevations provided are for the purposes of evaluating potentiometric elevations and should not be relied upon as a legal survey or topographic elevation survey.

4.3 Aquifer Performance Assessment

The following sections discuss the pumping test results and coefficients, well interference and water quality.

4.3.1 Pumping Test

The pumping test was commenced on August 9, 2022. The results of the constant rate pumping test including field testing data are graphically presented in **Appendix E**.

The water level during the pumping test at A342117 is illustrated on **Figures E-1** and **E-2** showing water level versus time. The plot shows a slow, minimal drawdown of the water level over the course of the 12-hour test at 37.8 L/min. After 12 hours of pumping, the water level was 8.7 metres below top of pipe (mbtp). The maximum drawdown was about 0.8 m over the course of the testing with about 30.3 m of available drawdown above the pump remaining. Approximately 2.5% of the available drawdown was used during the pumping test. A total groundwater volume of about 27,215 L was pumped during the testing. Based upon the septic design flow calculations, about 12,000 L/day has been estimated. Actual groundwater usage is expected to be much less than 12,000 L/day for the warehouse and offices.

Recovery measurements were collected manually for 60 minutes after pumping ceased. The water level recovered about 50% in one (1) hour and fully recovered 100% in seven (7) hours. The estimated transmissivity for the pumped water well was 33.4 m²/day (2238 gpd/ft) based on the drawdown and 26.7 m²/day (1791 gpd/ft) based on the recovery period and represents a high transmissivity. The specific capacity for this well is calculated to be 48.5 L/min/m based upon the pumping test completed.

The plotted data indicates the aquifer that this well is tapped into can safely provide long-term quantities of groundwater at a pumping rate of 37.8 L/min (10 gpm) based upon the pumping test completed.

Pumping tests were completed previously within a test well located on the Site (i.e. TW2) within the same sandstone aquifer. The test well, TW2, was pumped in 1994, 2008 and in 2020 at 67 L/min, 55 L/min, and 60 L/min, respectively. The drawdowns of these tests were similar to our drawdown at the new well ranging from about 1.1 m to 1.2 m. Static water levels from TW-2 were also similar ranging from 3.15 mbgs in 1994 to 6.90 mbgs in 2020, indicating that development in this area including quarries on nearby properties has not resulted in significant negative effects to the underlying water supply aquifer.

4.3.2 Summary of Aquifer Performance

The following **Table 4.2** summarizes the data and coefficients obtained from the pumping test.

Table 4.2 Aquifer Performance Testing Summary

Well No.	Step No.	Yield		Test Type	Time min	Maximum drawdown		Available Drawdown*		Specific Capacity		Estimated Transmissivity	
		gpm	L/min			feet	metres	feet	metres	gpm/ft	L/min/m	gpd/ft	m ² /day
A342117	1	0	0	Static	0	0	0	103.3	31.5	--	--	--	--
	2	10	37.8	Const.	720	2.6	0.8	100.7	30.7	3.9	48.5	2238	33.4
	3	0	0	Recvy.	50% recovery in 1 hour; 100% recovery in 7 hours							1791	26.7

Notes:

gpm = gallons per minute; gpd/ft = gallons per day per foot

"Recvy" refers to Recovery measurements; "Const" refers to the Constant Rate test conducted for 720 minutes.

*Available Drawdown refers to the height of water in the well above the pump.

Static water level at the pumped well A342117 was 7.96 metres below top of pipe (7.31 metres below ground surface) at the start of the testing.

4.3.3 Water Quality

Groundwater samples from the pumped well were obtained for laboratory testing during the course of the pumping test for the purpose of water quality analyses. The well was sampled after one (1) hour; at six (6) hours; and at the end of the constant rate test on August 9, 2022. The water samples were delivered to SGS laboratories in Lakefield, ON. Certificates of chemical analyses are presented in **Appendix F**. The water quality data are summarized and compared with the Ontario Drinking Water Standards (ODWS)¹ in **Table 4.3**. Regulation 153/04 parameters are also compared with the Table 2 Standards in a Potable Ground Water Condition for all property uses including a commercial property use². For the Regulation 153/04 parameters, the most stringent standard was used for comparison purposes.

Table 4.3 Test Well Water Quality Summary

Parameter	Pumped Water Well A342117			O.Reg. 153 – Table 2	ODWS	
	1 hr	6 hrs	12 hrs		MAC / IMAC	AO/OG
Bacteriological (Colony Forming Units)						
Total Coliform	--	--	3	NS	<6*	NS
E.coli	--	--	0	NS	0	NS
Fecal coliform	--	--	0	NS	0	NS
Background	--	--	33	NS	NS	NS
Heterotrophic Plate Count	--	--	55	NS	NS	NS
Semi-Volatile Organic Compounds (µg/L)						
Acenaphthene	--	--	<0.1	4.1	NS	NS
Acenaphthylene	--	--	<0.1	1	NS	NS
Anthracene	--	--	<0.1	2.4	NS	NS
Benzo(a)anthracene	--	--	<0.1	1	NS	NS
Benzo(a)pyrene	--	--	<0.01	0.01	0.01	NS
Benzo(b+j)fluoranthene	--	--	<0.1	NS	NS	NS
Benzo(ghi)perylene	--	--	<0.2	0.2	NS	NS
Benzo(k)fluoranthene	--	--	<0.1	0.1	NS	NS
Chrysene	--	--	<0.1	0.1	NS	NS
Dibenzo(a,h)anthracene	--	--	<0.1	0.2	NS	NS
Fluoranthene	--	--	<0.1	0.41	NS	NS
Fluorene	--	--	<0.1	120	NS	NS
Indeno(1,2,3-cd)pyrene	--	--	<0.2	0.2	NS	NS
1-Methylnaphthalene	--	--	<0.5	3.2	NS	NS
2-Methylnaphthalene	--	--	<0.5		NS	NS
Naphthalene	--	--	<0.5	11	NS	NS
Phenanthrene	--	--	<0.1	1	NS	NS
Pyrene	--	--	<0.1	4.1	NS	NS

¹ Technical Support Document for Ontario Drinking Water Standards, Objectives and Guidelines. June 2003, revised June 2006.

² Ministry of the Environment, April 15, 2011. Soil, Ground Water and Sediment Standards for Use Under Part XV.1 of the Environmental Protection Act.

Parameter	Pumped Water Well A342117			O.Reg. 153 – Table 2	ODWS	
	1 hr	6 hrs	12 hrs		MAC / IMAC	AO/OG
<i>Volatile Organic Compounds (µg/L)</i>						
Acetone	--	--	<30	2700	NS	NS
Bromomethane	--	--	<0.5	0.89	NS	NS
Carbon tetrachloride	--	--	<0.2	0.79	5	NS
Chlorobenzene	--	--	<0.5	30	NS	NS
Chloroform	--	--	<0.5	2.4	NS	NS
1,2-Dichlorobenzene	--	--	<0.5	3	20	3
1,3-Dichlorobenzene	--	--	<0.5	59	NS	NS
1,4-Dichlorobenzene	--	--	<0.5	1	5	1
Dichlorofluoromethane	--	--	<2	590	NS	NS
1,1-Dichloroethane	--	--	<0.5	5	NS	NS
1,2-Dichloroethane	--	--	<0.5	1.6	5	NS
1,1-Dichloroethylene	--	--	<0.5	1.6	NS	NS
trans-1,2-Dichloroethane	--	--	<0.5	1.6	NS	NS
cis-1,2-Dichloroethane	--	--	<0.5	1.6	NS	NS
1,2-Dichloropropane	--	--	<0.5	5	NS	NS
cis-1,3-Dichloropropane	--	--	<0.5	NS	NS	NS
trans-1,3-Dichloropropane	--	--	<0.5	NS	NS	NS
1,3-Dichloropropene	--	--	<0.5	0.5	NS	NS
Ethylene Dibromide	--	--	<0.2	0.2	NS	NS
Hexane	--	--	<1	51	NS	NS
Methyl Ethyl Ketone	--	--	<20	1000	NS	NS
Methyl Isobutyl Ketone	--	--	<20	400	NS	NS
Methyl Tert-Butyl Ether	--	--	<2	15	NS	NS
Methylene Chloride	--	--	<0.5	50	NS	NS
Styrene	--	--	<0.5	5.4	NS	NS
Tetrachloroethylene	--	--	<0.5	1.6	30	NS
1,1,1,2-Tetrachloroethane	--	--	<0.5	1.1	NS	NS
1,1,2,2-Tetrachloroethane	--	--	<0.5	1	NS	NS
1,1,1-Trichloroethane	--	--	<0.5	200	NS	NS
1,1,2-Trichloroethane	--	--	<0.5	4.7	NS	NS
Trichloroethylene	--	--	<0.5	1.6	5	NS
Trichlorofluoromethane	--	--	<5	150	NS	NS
Vinyl Chloride	--	--	<0.2	0.5	2	NS
Benzene	--	--	<0.5	5	5	NS
Toluene	--	--	<0.5	24	NS	24
Ethylbenzene	--	--	<0.5	2.4	NS	2.4

Parameter	Pumped Water Well A342117			O.Reg. 153 – Table 2	ODWS	
	1 hr	6 hrs	12 hrs		MAC / IMAC	AO/OG
Xylenes	--	--	<0.5	300	NS	300
Bromodichloromethane	--	--	<0.5	16	NS	NS
Bromoform	--	--	<0.5	25	NS	NS
Dibromochloromethane	--	--	<0.5	25	NS	NS
<i>Petroleum Hydrocarbons</i>						
PHC F1 (C ₆ – C ₁₀)	--	--	<25	750	NS	NS
PHC F2 (C ₁₀ – C ₁₆)	--	--	<100	150	NS	NS
PHC F3 (C ₁₆ – C ₃₄)	--	--	<200	500	NS	NS
PHC F4 (C ₃₄ – C ₅₀)	--	--	<200	500	NS	NS
PHC F4 Gravimetric	--	--	Yes ¹	500	NS	NS
<i>Trace Metals (dissolved) (mg/L)</i>						
Aluminum	<0.001	<0.001	<0.001	NS	NS	0.1
Arsenic	0.0006	0.0004	0.0004	0.25	0.025	NS
Boron	0.199	0.216	0.216	5	5	NS
Barium	0.09451	0.09889	0.09880	1	1	NS
Beryllium	<0.000007	<0.000007	0.000011	0.004	NS	NS
Cobalt	0.000094	0.0000910	0.000082	0.0038	NS	NS
Calcium	103	112	117	NS	NS	NS
Cadmium	0.000016	0.000017	0.000020	0.0027	0.005	NS
Copper	<0.0002	<0.0002	<0.0002	0.087	NS	1
Chromium	0.00012	<0.00008	<0.00008	0.05	0.05	NS
Iron	0.369	0.276	0.481	NS	NS	0.3
Magnesium	47.8	53.4	53.5	NS	NS	NS
Manganese	0.175	0.173	0.171	NS	NS	0.05
Mercury	<0.00001	<0.00001	<0.00001	0.00029	0.001	NS
Molybdenum	0.02195	0.02931	0.03188	0.07	NS	NS
Nickel	0.0014	0.0013	0.0012	0.1	NS	NS
Sodium	54.5	57.4	57.0	490	NS	200 (20*)
Lead	<0.00009	<0.00009	<0.00009	0.01	0.01	NS
Silver	<0.00005	<0.00005	<0.00005	0.0015	NS	NS
Strontium	5.15	5.91	5.92	NS	NS	NS
Thallium	<0.000005	<0.000005	<0.000005	0.002	NS	NS
Antimony	<0.0009	<0.0009	<0.0009	0.006	0.006	NS
Selenium	0.00015	0.00020	0.00011	0.01	0.01	NS
Uranium	0.000219	0.000227	0.000219	0.02	0.02	NS
Vanadium	0.00011	0.00008	0.00009	0.0062	NS	NS
Zinc	<0.002	<0.002	<0.002	1.1	NS	5

Parameter	Pumped Water Well A342117			O.Reg. 153 – Table 2	ODWS	
	1 hr	6 hrs	12 hrs		MAC / IMAC	AO/OG
General Chemistry Parameters (units listed per parameter)						
Tannin + Lignin (mg phenol/L)	0.32	0.34	0.40	NS	NS	NS
Alkalinity (mg/L as CaCO ₃)	265	261	261	NS	NS	30 – 500
Carbonate (mg/L as CaCO ₃)	<2	<2	<2	NS	NS	NS
Bicarbonate (mg/L as CaCO ₃)	265	261	261	NS	NS	NS
pH	8.14	8.20	8.23	NS	NS	6.5 – 8.5
Conductivity (µS/cm)	1180	1290	1350	NS	NS	NS
Total Dissolved Solids (mg/L)	763	914	914	NS	NS	500
Colour (TCU)	3	<3	<3	NS	NS	5
Turbidity (NTU)	2.5	2.89	4.21	NS	NS	5
Organic Nitrogen (mg/L)	<0.05	<0.05	<0.05	NS	NS	0.15
Total Kjeldahl Nitrogen (mg/L)	0.18	0.17	0.16	NS	NS	NS
Ammonia + Ammonium (mg/L)	0.19	0.17	0.17	NS	NS	NS
Nitrite (as N mg/L)	<0.003	<0.003	<0.003	NS	1	NS
Nitrate (as N mg/L)	<0.006	<0.006	<0.006	NS	10	NS
Chloride (mg/L)	62	66	68	790	NS	250
Hydrogen Sulphide	<0.02	<0.02	<0.02	NS	NS	0.05
Sulphide (mg/L)	<0.02	<0.02	<0.02	NS	NS	NS
Sulphate (mg/L)	300	370	400	NS	NS	500
Dissolved Organic Carbon (mg/L)	2	2	2	NS	NS	5
Hardness (mg/L as CaCO ₃)	453	500	511	NS	NS	80 – 100
Ryznar Stability Index	6.4	6.2	6.2	NS	NS	NS
Potassium	7.16	7.56	7.39	NS	NS	NS

Notes:

"1" denotes that PHC F4 gravimetric returned to baseline

"<" indicates concentrations are less than laboratory reporting limits

MAC = maximum acceptable concentration; IMAC – Interim MAC; AO / OG = aesthetic objective / operational guideline

Bold / shaded indicates the concentration exceeds the ODWS AO / OG. There are no exceedances of MAC or IMAC (health related).

*The aesthetic objective for sodium in drinking water is 200 mg/L. When the sodium concentration exceeds 20 mg/L, this information should be communicated to those on sodium restricted diets.

The laboratory analyses confirmed that there were no health-related parameter exceedances of the ODWS. VOCs, PAHs and PHCS were reported below detection limits and meet all Ontario Regulation Table 2 Standards for the parameters tested in a potable groundwater condition for all property uses.

In general, the test results indicate the majority of parameters meet the ODWS with the exception of the aesthetic objectives for:

- Hardness;
- Total Dissolved Solids;
- Manganese; and
- Iron.

Elevated hardness is related to the overburden materials containing calcium and to a lesser extent, magnesium. Elevated hardness, iron and manganese are common traits of groundwater supplies in Southern Ontario and can be

treated using commercially available treatment equipment such as a water softener. The iron and manganese are within treatable limits. Although hardness in excess of 500 mg/L is considered very hard, a maximum treatable value is not provided within the D-5-5 Guideline. Treatment for hardness (and other parameters) is provided in the following sub-section.

Total dissolved solids (TDS) were also elevated above its aesthetic objective of 500 mg/L. TDS may be the result of hard water including calcium and/or magnesium as well as other constituents such as sodium and chloride. Treatment consideration is provided in the following sub-section. The Ryznar Stability Index was calculated to be between 6.2 and 6.4 which is within the neutral range and therefore incrustation and corrosion are not considered to be problematic due to the elevated TDS.

Turbidity was reported as less than 5 NTU in the laboratory samples and ranged from 3.25 to 1.2 NTU at the wellhead. These values indicated acceptable turbidity.

The bacteriological results were three (3) colony forming units per 100 mL (CFU) for total coliform which is acceptable for raw water as fecal coliform and E.coli are zero CFU. The residual chlorine residual was measured in the field at the wellhead prior to testing and confirmed to be non-detect.

As a proactive measure, GHD recommends that bacteriological treatment (i.e. ultraviolet (UV) treatment) be used at a minimum. As it is anticipated that this well system will be regulated and will require treatment to meet appropriate standards to ensure potable water is available to employees and visitors.

To supplement the analytical data, field measurements were obtained throughout the pumping test by GHD. At the end of the pump test, the groundwater at the well head had a conductivity of 1.35 mS/cm, a water temperature of 16.0 degrees Celsius, a pH of 7.82, a chlorine residual of 0 mg/L and turbidity of 1.2 NTU. There was no methane detected within the water.

4.3.3.1 Water Treatment

MacLellan Water Treatment (MacLellan) was contacted to provide water treatment based upon the pumped well chemistry. Based upon the chemistry provided from the pumping test, MacLellan provided recommendations for water treatment. Their report is provided in **Appendix G** and summarized below:

- a. Installation of a filtration system for iron that utilizes a manganese greensand filter with chlorine regeneration. This filter would also remove a certain amount of manganese.
- b. Installation of an activated carbon filter to remove residual chlorine and organically-complexed metals.
- c. Install a water softener to soften the water to improve the aesthetics of the water and protect the water disinfection system and water-using appliances (hot water tanks, etc.) in the facility from fouling due to hard water scale. A twin alternating system was recommended to ensure that softening is uninterrupted.
- d. Disinfection of the water will be provided with ultraviolet (UV) disinfection. The unit will be sized to allow adequate flow to the facility and will be equipped with turbidity-reducing cartridge-style prefilters to screen out particles that bacteria might shelter behind while passing through the UV light.
- e. As the concentration of sodium in the water is already slightly high, the use of a water softener will increase the sodium content of the treated water by about 300 mg/L. Therefore, one or more point of use reverse osmosis (RO) units will be installed to remove sodium at locations (like lunch rooms) where staff will actually consume the water. The RO units will be equipped with small storage tanks so that pre-treated water will be ready on demand.

Based upon the MacLellan report, the water can be treated for use at the proposed commercial facility.

4.3.4 Well Interference

In order to assess the potential for hydraulic connection between the pumped water well A342117 and neighbouring wells were monitored during the pumping test. Data logger water levels were installed at each of the observation wells during the pumping test and the data is provided in **Appendix H**. Manual water levels at TW-5, A305146, A342260

and A018916 were collected prior to and after the pumping test was conducted between August 3 and August 18, 2022. The data illustrates the water level conditions during this time as well as during the pumping test.

The approximate linear distances between the pumped water well and observation wells are provided in **Table 4.4** based upon the locations plotted on **Figure 8**.

Table 4.4 Distance Between Pumping Well and Observation Wells

Location	Distances between Pumped Water Well A342117 and Observation Wells (metres)					
	MW22-1	4885 Hawthorne Rd.	TW-5	A305146	A018916	A342260
Pumped well A342117	45	630	570	140	475	640

Notes:

Distances based upon locations identified on **Well Locations, Figure 8**.

MW = monitoring well

The following table provides the manual water levels collected during the pumping test at the observation wells monitored during the pumping test.

Table 4.5 Maximum Drawdowns in Pumping and Observation Wells

Location	Water Level (start of test) mbgs	Water Level (end of test) mbgs	Drawdown (m)
A342117 (pumped water well)	7.31	8.11	-0.80
MW22-1	2.05	1.95	+0.10
4885 Hawthorne Road	0.95	0.93	+0.02
TW-5	6.70	6.71	-0.01
A305146	7.42	7.69	-0.27
A018916	11.85	11.81	+0.04
A342260	10.62	10.59	+0.03

Notes:

Negative drawdown (denoted by minus sign and RED text) indicates water level lowered during the testing

Positive drawdown (denoted by plus sign and BLACK text) indicates water level was rising during the testing

4.3.4.1 Interference Assessment

Prior to the pumping test, data loggers were installed within the adjacent wells including TW-5, A305146, 4885 Hawthorne Road, A342260 and A018916 to collect background water levels. Water levels were also collected from these locations during the pumping test and after the pumping test was completed. The data was collected was used to evaluate groundwater level trends and to aid in assessing hydraulic connection between the overburden and bedrock aquifer, and, within the bedrock aquifer itself.

There was no drawdown attributable to pumping at the pumped well within the monitoring well MW22-1 indicating that there is no vertical hydraulic connection between the overburden groundwater and confined bedrock aquifer that A342117 draws from.

There was no drawdown measured at water wells A018916, A342260 or 4885 Hawthorne Road and minimal drawdown within TW-5 throughout the duration of the pumping test. The drawdown at TW-5 was about one (1) cm based upon the data logger readings and is considered negligible. No impacts are expected at these wells as a result of future usage of the water well on the Site.

The results of the interference monitoring did illustrate a hydraulic connection between the pumping well A342117 and A305146 about 140 m to the south. Both wells are drilled to 42.7 m (140 feet) and are expected to tap into the same aquifer unit. The drawdown at this well was manually measured to be about 27 cm during the pumping test and the

data logger shows a similar water level response in A305146, albeit to a lower magnitude, as the pumped well. The data confirms that these wells are confined within the same aquifer unit and are hydraulically connected. With the drawdown of 27 cm (less than 1% of the available drawdown within this well), about 35 m of available drawdown remains within the well.

The testing showed that the pumping of nearly 30,000 L resulted in the usage of about 2.5% of the available drawdown of the pumped well. As daily usage is expected to be below 10,000 L/day, the pump test results indicate that there is sufficient water quantity below the Site for the planned development with without significant interference to future and existing neighbouring wells. In our professional opinion, the risk of interference is minimal.

4.4 Septic Waste Disposal

The septic waste disposal system is being designed by others. The septic will be about 25 m from the water well, maintaining the minimum 15 m horizontal buffer as per the Ontario Building Code.

5. Water Quality Impact Assessment

Procedure D-5-4 provides a methodology for assessing potential impact to downgradient groundwater resources as a result of the installation of private sewage disposal systems on a development property. The procedure is to consider the following:

- Lot Size Considerations
- System Isolation Considerations
- Contaminant Attenuation Considerations

Using D-5-4 as a guide, the proponent is to determine the background nitrate concentration in the receiving groundwater; demonstrate that the area is not hydrogeologically sensitive; and, demonstrate that the maximum nitrate limit prescribed by the procedure will not be exceeded in the receiving groundwater at the downgradient site boundary.

However, this guideline does not apply to Large Subsurface Sewage Disposal Systems (i.e. septic effluent of greater than 10,000 L/day). The projected design septic effluent for this Site is on the order 12,000 L/day. If the septic effluent from the Site was to be less than 10,000 L/day, then the Procedure would also not be applicable as the development area is greater than one (1) hectare

GHD completed a hydrogeological assessment for a large subsurface septic system (GHD report dated November 2, 2021). Based upon the impact assessment, tertiary treatment will be required. Based upon the impact assessment, the proposed sewage system will have no significant impact on the groundwater aquifer, shallow water or any downgradient receptors that utilize groundwater.

6. Construction Dewatering

A water sample was collected from the monitoring well (MW22-1) for purposes of establishing the water quality should excavations extend into the shallow groundwater and require dewatering. Depending upon the construction activities, dewatering to remove groundwater seepage, surface water runoff and precipitation may be required to ensure safe and dry working conditions.

6.1.1 Groundwater Sampling for Construction Dewatering

On August 9, 2022, a groundwater sample was collected from MW22-1 (referred to “Piezo” in the certificate of analysis). The sample was submitted to SGS for analysis of parameters described in City of Ottawa By Law 2003-514, which addresses discharge to the Municipal sewage system. The analytical results are summarized within the certificates of analysis in **Appendix I**.

Based upon the analytical results, and upon comparison with the City of Ottawa criteria, the following parameters exceeded the criteria:

- Total suspended solids; and,
- Manganese.

The results represent total concentrations including dissolved and sorbed particulate. Based on these observations, the water discharged from an excavation would require treatment (i.e. filtration) to minimize the particulate and reduce the total concentrations to meet the City of Ottawa criteria. The discharge would be expected to be a combination of groundwater, surface water runoff and precipitation into the excavation and would require further assessment to verify its quality. City of Ottawa approval, sewer-use discharge permit and pre-treatment will be required prior to discharge to a drainage ditch or sewer.

7. Summary and Recommendations

Supporting data upon which our conclusions and recommendations are based have been presented in the foregoing sections of this report. The following conclusions and recommendations are governed by the physical properties of the subsurface materials that were encountered at the Site and assume that they are representative of the overall Site conditions. It should be noted that these conclusions and recommendations are intended for use by the designers only. Contractors bidding on or undertaking any work at the Site should examine the factual results of the assessment, satisfy themselves as to the adequacy of the information for construction, and make their own interpretation of this factual data as it affects their proposed construction techniques, equipment capabilities, costs, sequencing, and the like. Comments, techniques, or recommendations pertaining to construction should not be construed as instructions to the contractor.

Based on the results of the hydrogeological and impact assessment, the pumped water well has sufficient water of good quality and quantity to provide ample supply of potable groundwater for the proposed commercial development while preserving the long-term water quality of the aquifer complex. In the certification letter WSP has indicated that the new water well, A342117, was properly constructed and adequately sealed in accordance with Ontario Regulation 903. The well will have adequate separation from the proposed building and future septic area. Based upon the pumping test, there was marginal interference between an adjacent well; however, the interference is not considered significant to impact the operation of the wells. Based on the data collected no vertical hydraulic connection between the shallow overburden groundwater and the bedrock aquifer unit was identified. In the long-term, it is our opinion that the bedrock aquifer tested can support the commercial development with minimal to negligible impact to neighbouring wells.

The water quality, as indicated in the MacLellan report, can be treated to meet the needs of the proposed facility. The treatment is to consist of filters, water softening, UV disinfection and RO at selected point(s) of consumption such as lunch room(s).

Based upon the impact assessment, water quality impacts are not expected provided that the waste disposal system is properly constructed. The waste disposal system will be a large subsurface system that, based upon the daily design, will exceed 10,000 L/day of septic effluent. The actual daily septic effluent is expected to be much less than 10,000 L/day. No impact is anticipated on downgradient baseline water quality functions or to the existing water bearing aquifers.

Should construction dewatering of shallow water be required, filtration of the pumped water will be required to remove particulate and ensure that total suspended solids and manganese concentrations meet the City of Ottawa storm sewer use by-law criteria. No significant impacts from construction dewatering are anticipated.

It is our opinion that the results of this hydrogeologic and impact assessment support the development of the proposed commercial development.

All of Which is Respectfully Submitted,

GHD



Jason Gerald, M.Sc., C.Chem.
Project Manager



Robert Neck, P.Ge. (Limited)
Senior Geoscientist



Steve Gagné, H.B.Sc.
Associate, Project Director

8. References

- Chapman and Putnam, 1966. The Physiography of Southern Ontario, 2nd Edition. University of Toronto Press.
- Chapman and Putnam, 1984. The Physiography of Southern Ontario, 3rd Edition. Ministry of Natural Resources.
- City of Ottawa, March 2021. Hydrogeological and Terrain Analysis Guidelines.
- Conestoga-Rovers & Associates, September 2008. Phase II Environmental Site Assessment and Hydrogeological Assessment. Report Ref. No. 045804 (12)
- Environmental Protection Act, R.S.O. 1990, and associated regulations.
- Fetter, C.W., 1994. Applied Hydrogeology, 3rd Edition.
- Freeze, R.A. and J.A. Cherry. 1979. Groundwater.
- GHD Limited, November 2, 2021. Hydrogeological Assessment – Large Sewage Disposal System. Rideau Road and Somme Street. Ottawa Ontario. Proj. No. 12565773-01
- GHD Limited, April 12, 2021. Terrain Analysis. Septic Assessment and Percolation Rate Evaluation. Proposed Commercial Development – Rideau Road and Somme Street. Gloucester Con 6 from Rideau River, Lot 26, Ottawa Ontario. Proj. No. 11220832-01
- GHD Limited, January 19, 2021. Hydrogeological Assessment Report. Proposed Commercial Development – Rideau Road and Somme Street. Gloucester Con 6 from Rideau River, Lot 26, Ottawa Ontario. Proj. No. 11220832-01;
- GHD Limited, September 10, 2020. Geotechnical Investigation. Warehouse and Offices. Intersection of Rideau Street and Somme Street, Ottawa Ontario. Proj. No. 11215612-01.
- Golder Associates, December 2008. Hydrogeological Investigation, Terrain Analysis and Impact Assessment, Proposed Industrial Subdivision, Report Ref. No. 08-1122-0215.
- Inspec-Sol, May 4, 2009. Geotechnical Study Subdivision Plan, Hawthorne Industrial Park, Report Ref. No. T020556-A1.
- J.L. Richards & Associates Limited, February 2009 (Revised May 2009). Stormwater Management Report. Hawthorne Industrial Park, Report Ref. No. JLR 20983.
- Occupational Health and Safety Act, R.S.O. 1990, and associated regulations.
- Ontario Geological Survey, 2003. Surficial Geology of Southern Ontario.
- Ontario Ministry of the Environment, 2011. Ontario Regulation 153/04: Records of Site Condition Part XV.1 of the Act (*Environmental Protection Act* 153/04, as amended).
- Ontario Ministry of the Environment. June 2003. Revised June 2006. Technical Support Document for Ontario Drinking Water Standards, Objectives and Guidelines.
- Ontario Ministry of the Environment and Energy. August 1996. D-5-4 Individual On-Site Sewage Systems: Water Quality Impact Risk Assessment.
- Ontario Ministry of the Environment and Energy. August 1996. D-5-5 Private Wells: Water Supply Assessment.

9. Statement of Limitations

This report is intended solely for Consolidated Fastfrate (Ottawa) Holdings Inc. in assessing the hydrogeological aspects of the Site (301 Somme Street, Ottawa, Ontario) and is prohibited for use by others without GHD's prior written consent. This report is considered GHD's professional work product and shall remain the sole property of GHD. Any unauthorized reuse, redistribution of or reliance on the report shall be at the Client and recipient's sole risk, without liability to GHD. Client shall defend, indemnify and hold GHD harmless from any liability arising from or related to Client's unauthorized distribution of the report. No portion of this report may be used as a separate entity; it is to be read in its entirety and shall include all supporting drawings and appendices.


The recommendations made in this report are in accordance with our present understanding of the project, the current site use, ground surface elevations and conditions, and are based on the work scope approved by the Client and described in the report. The services were performed in a manner consistent with that level of care and skill ordinarily exercised by members of hydrogeological engineering professions currently practicing under similar conditions in the same locality. No other representations, and no warranties or representations of any kind, either expressed or implied, are made. Any use which a third party makes of this report, or any reliance on or decisions to be made based on it, are the responsibility of such third parties.

All details of design and construction are rarely known at the time of completion of a hydrogeological study. The recommendations and comments made in the study report are based on our subsurface investigation and resulting understanding of the project, as defined at the time of the study. We should be retained to review our recommendations when the drawings and specifications are complete. Without this review, GHD will not be liable for any misunderstanding of our recommendations or their application and adaptation into the final design.

Figures




CITY OF OTTAWA



LEGEND

- Study Property Limit
- 500 m Radius

Service Layer Credits: © 2020 Microsoft Corporation © 2020 Maxar ©CNES (2020)
Distribution Airbus DS © 2020 HERE



Consolidated Fastfrate (Ottawa) Holdings Inc.
RIDEAU ROAD & SOMME STREET
CITY OF OTTAWA
ONTARIO

Project No. 12580314-01
Revision No. 1
Date September 2022

**HYDROGEOLOGY ASSESSMENT
SITE LOCATION PLAN**




FIGURE 1

Created by: Will Pridham

ATTRIBUTION STATEMENTS

Produced by GHD Limited under Licence with the Ontario Ministry of Natural Resources and Forestry © Queen's Printer for Ontario, 2020 (2020).

K:\GIS_PROJECTS\GHD\CA-




Map Projection: Transverse Mercator
 Horizontal Datum: North American 1983
 Grid: NAD 1983 UTM Zone 18N

Consolidated Fastrate (Ottawa) Holdings Inc.
 301 Somme Street, Ottawa, ON
 City of Ottawa

Project No. 12580314
 Revision No.
 Date Sep 19, 2022

Concept Plan


Figure 2



LEGEND

- Study Property Limit
- 500 m Radius
- Contour (5 m)

Service Layer Credits: © 2020 Microsoft Corporation © 2020 Maxar ©CNES (2020)
Distribution Airbus DS © 2020 HERE



ATtribution STATEMENTS

- ▶ MRD128-REV. Ontario Geological Survey 2010. Surficial geology of southern Ontario, Ontario Geological Survey, Miscellaneous Release—Data 128 – Revised.
- ▶ Produced by GHD Limited under Licence with the Ontario Ministry of Natural Resources and Forestry © Queen's Printer for Ontario, 2020 (2020).




Consolidated Fastfrate (Ottawa) Holdings Inc.
RIDEAU ROAD & SOMME STREET
CITY OF OTTAWA
ONTARIO

**HYDROGEOLOGY ASSESSMENT
REGIONAL TOPOGRAPHY**

Project No. 12580314-01
Revision No. -
Date September 2022

FIGURE 3

Created by: Will Pridham




LEGEND

- Study Property Limit
- 500 m Radius
- Lower Tier Municipal Boundary
- Study Property Area

MRD228 - PHYSIOGRAPHY OF SOUTHERN ONTARIO
(Ministry of Northern Development & Mines)

- 17 Peat and Muck
- 11 Sand Plains
- 9 Limestone Plains

Service Layer Credits: © 2020 Microsoft Corporation © 2020 Maxar ©CNES (2020)
Distribution Airbus DS © 2020 HERE



ATtribution STATEMENTS

- ▶ MRD228-REV. Chapman, L.J. and Putnam, D.F. 2007. Physiography of southern Ontario, Ontario Geological Survey, Miscellaneous Release—Data 228.
- ▶ Produced by GHD Limited under Licence with the Ontario Ministry of Natural Resources and Forestry © Queen's Printer for Ontario, 2020 (2020).




Consolidated Fastfrate (Ottawa) Holdings Inc.
RIDEAU ROAD & SOMME STREET
CITY OF OTTAWA
ONTARIO

**HYDROGEOLOGY ASSESSMENT
PHYSIOGRAPHY**

Project No. 12580314-01
Revision No. -
Date September 2022

FIGURE 4

Created by: Will Pridham




LEGEND

- Study Property Limit
- 500 m Radius
- Landslide Scar
- Beach

MRD128 - SURFICIAL GEOLOGY (Ministry of Northern Development & Mines)

- 3** Paleozoic Bedrock
- 10** Fine-textured glaciomarine deposits
 - 10a Massive to well laminated
- 11** Coarse-textured glaciolacustrine deposits: sand, gravel, minor silt and clay
 - 11b Littoral deposits
 - 11c Foreshore and basinal deposits
- 17** Eolian deposits: fine to very fine sand and silt
- 20** Organic Deposits: peat, muck, marl
- 5b** Till: Silty sand to sand-textured till on Precambrian terrain
 - 5b Stone-poor, sandy silt to silty sand-textured till on Paleozoic terrain

Service Layer Credits: © 2020 Microsoft Corporation © 2020 Maxar ©CNES (2020) Distribution Airbus DS © 2020 HERE



ATtribution STATEMENTS

- ▶ MRD128-REV. Ontario Geological Survey 2010. Surficial geology of southern Ontario, Ontario Geological Survey, Miscellaneous Release—Data 128 – Revised.
- ▶ Produced by GHD Limited under Licence with the Ontario Ministry of Natural Resources and Forestry © Queen's Printer for Ontario, 2020 (2020).




Consolidated Fastfrate (Ottawa) Holdings Inc.
 RIDEAU ROAD & SOMME STREET
 CITY OF OTTAWA
 ONTARIO

**HYDROGEOLOGY ASSESSMENT
 SURFICIAL GEOLOGY**

Project No. 12580314-01
Revision No. -
Date September 2022

FIGURE 5

Created by: Will Pridham




LEGEND

- Study Property Limit
- 500 m Radius
- Landslide Scar
- Beach

EDS014 - QUATERNARY GEOLOGY (Ministry of Northern Development & Mines)

- | | | |
|---|---|--|
| <p> 32 Organic deposits:
peat, muck and marl</p> <p> 27 Glaciomarine and marine deposits:
sand, gravelly sand and gravel nearshore and beach deposits</p> | <p> 22 Glaciofluvial ice-contact deposits:
gravel and sand minor till includes esker, kame, end moraine, ice-marginal delta and subaqueous fan deposits</p> <p> 2 Bedrock:
undifferentiated carbonate and clastic sedimentary rock, exposed at surface or covered by a discontinuous, thin layer of drift</p> | |
|---|---|--|

Service Layer Credits: © 2020 Microsoft Corporation © 2020 Maxar ©CNES (2020)
Distribution Airbus DS © 2020 HERE



ATtribution STATEMENTS

- ▶ EDS014-REV. Ontario Geological Survey, 1997. Quaternary geology, seamless coverage of the province of Ontario: Ontario Geological Survey, Data Set 14.
- ▶ Produced by GHD Limited under Licence with the Ontario Ministry of Natural Resources and Forestry © Queen's Printer for Ontario, 2020 (2020).




Consolidated Fastfrate (Ottawa) Holdings Inc.
RIDEAU ROAD & SOMME STREET
CITY OF OTTAWA
ONTARIO

**HYDROGEOLOGY ASSESSMENT
QUATERNARY GEOLOGY**

Project No. 12580314-01
Revision No. -
Date September 2022

FIGURE 6

Created by: Will Pridham



LEGEND

- Study Property Limit
- 500 m Radius
- Landslide Scar
- Beach

MRD126 - BEDROCK GEOLOGY (Ministry of Northern Development & Mines)


ORDOVICIAN (443.7 Ma to 488.3 Ma)
 UPPER ORDOVICIAN

55 Shale, limestone, dolostone, siltstone

53 Dolostone, sandstone: Beekmantown Gp.

55b Georgian Bay Fm.; Blue Mountain Fm.; Billings Fm.;
 Collingwood Mb.; Eastview Mb.

Service Layer Credits: © 2020 Microsoft Corporation © 2020 Maxar ©CNES (2020)
 Distribution Airbus DS © 2020 HERE



ATtribution STATEMENTS

- ▶ MRD126-REV. Ontario Geological Survey 2011. 1:250 000 scale bedrock geology of Ontario; Ontario Geological Survey, Miscellaneous Release---Data 126-Revision
- ▶ Produced by GHD Limited under Licence with the Ontario Ministry of Natural Resources and Forestry © Queen's Printer for Ontario, 2020 (2020).



Consolidated Fastfrate (Ottawa) Holdings Inc.
 RIDEAU ROAD & SOMME STREET
 CITY OF OTTAWA
 ONTARIO




**HYDROGEOLOGY ASSESSMENT
 BEDROCK GEOLOGY**

Project No. 12580314-01
Revision No. -
Date September 2022

FIGURE 7



Created by: Will Pridham

Legend

-  Well Locations
-  500 m Radius
-  Property Limit



Data Disclaimer
 Produced by GHD Limited under Licence with the Ontario Ministry of Natural Resources and Forestry © Queen's Printer for Ontario, 2022.



Consolidated Fastrate (Ottawa) Holdings Inc.
 301 Somme Street, Ottawa, ON
 City of Ottawa

Project No. 12580314
 Revision No.
 Date Sep 19, 2022

Map Projection: Transverse Mercator
 Horizontal Datum: North American 1983
 Grid: NAD 1983 UTM Zone 18N

Well Locations



Figure 8

Appendices




Appendix A


MECP Well Records

Legend



-  500 m Radius
-  Property Limit

MECP Well Locations by Status

-  Test Hole
-  Water Supply
-  No Data; Not A Well



Data Disclaimer
 Produced by GHD Limited under Licence with the Ontario Ministry of Natural Resources and Forestry © Queen's Printer for Ontario, 2022.



Consolidated Fastrate (Ottawa) Holdings Inc.
 301 Somme Street, Ottawa, ON
 City of Ottawa

Project No. 12580314
 Revision No.
 Date Sep 19, 2022

MECP Well Locations

Appendix A

MECP WELL RECORD LISTINGS

Ministry of the Environment, Conservation & Parks (MECP)
 © Water Well Information System (WWIS). Ministry of the Environment, Conservation, and Parks. 2021.
 Powered by Location Intelligence



DISCLAIMER: All effort has been taken to ensure the accuracy of the data is the same as the source. There are instances where the original PDF document is different and in those cases, the PDF should be used instead.

18	Easting:	456430.80	Latitude: 45.30598 Longitude: -75.555767	Well ID: 1502342
	Northing:	5017092.00		
	Elev (masl):	87.74		

LOCATION	Lot: 026 Con: 06 Municipality: OTTAWA-CARLETON Township: GLOUCESTER TOWNSHIP Street: City: n/a	Tag: Audit No: Contractor License: 3504 Well Completion Date: 11/30/1950 Received Date: 12/06/1951
WELL	Well Status: Water Supply Prim. Use: n/a Sec. Use: Domestic Boring Method: Cable Tool	Well Depth (m): 17.3736 Depth to Bedrock (m): 27 Depth to Water: ft Water Kind: FRESH
PUMP TEST	Test Method: CLEAR Pump Set (m): n/a SWL (ft): 13 Final Level: 18 ft Pump Rate: 1 GPM Recom. Rate: n/a GPM	Pipe ID: 10572955 Pump Test ID: 991502342 Flowing: N Pump Duration (hr): 0 Pump Duration (m): 30

CASING DETAILS

Layer Value of "0" denotes a Null value and cannot be stratified and ordered.

Layer	Case ID	Casing Diamter	Diamter Units	Material	Top Depth	Bottom Depth
1	930041541	5	inch	STEEL	n/a	27 ft
2	930041542	5	inch	OPEN HOLE	n/a	57 ft

FORMATION DETAILS

Layer Value of "0" denotes a Null value and cannot be stratified and ordered.

Layer	Material	Material 2	Material 3	Colour	Top Depth	Bottom Depth
1	PREV. DRILLED	n/a	n/a	n/a	0	27 ft
2	SANDSTONE	n/a	n/a	n/a	27	57 ft

End of Record

18	Easting:	456090.80	Latitude: 45.304248 Longitude: -75.560087	Well ID: 1509625
	Northing:	5016902.00		
	Elev (masl):	103.27		

LOCATION	Lot: 026 Con: 05 Municipality: OTTAWA-CARLETON Township: GLOUCESTER TOWNSHIP Street: City: n/a	Tag: Audit No: Contractor License: 3002 Well Completion Date: 05/04/1968 Received Date: 06/12/1968
WELL	Well Status: Water Supply Prim. Use: n/a Sec. Use: n/a Boring Method: Cable Tool	Well Depth (m): 58.5216 Depth to Bedrock (m): 0 Depth to Water: ft Water Kind: FRESH
PUMP TEST	Test Method: CLEAR Pump Set (m): n/a SWL (ft): 36 Final Level: 63 ft Pump Rate: 180 GPM Recom. Rate: 180 GPM	Pipe ID: 10580227 Pump Test ID: 991509625 Flowing: N Pump Duration (hr): 24 Pump Duration (m): 0

CASING DETAILS

Layer Value of "0" denotes a Null value and cannot be stratified and ordered.

Layer	Case ID	Casing Diamter	Diamter Units	Material	Top Depth	Bottom Depth
1	930055956	10	inch	STEEL	n/a	18 ft
2	930055957	9	inch	OPEN HOLE	n/a	192 ft

FORMATION DETAILS

Layer Value of "0" denotes a Null value and cannot be stratified and ordered.

Layer	Material	Material 2	Material 3	Colour	Top Depth	Bottom Depth
1	SANDSTONE	n/a	n/a	BROWN	0	52 ft
2	QUARTZITE	n/a	n/a	GREY	52	72 ft
3	SANDSTONE	n/a	n/a	WHITE	72	160 ft
4	SANDSTONE	n/a	n/a	GREY	160	192 ft

End of Record

18	Easting:	456210.80
	Northing:	5016920.00
	Elev (masl):	99.42

Latitude: 45.304418
Longitude: -75.558558

Well ID: **1514733**

LOCATION
WELL
PUMP TEST

Lot: 026
Con: 05
Municipality: OTTAWA-CARLETON
Township: GLOUCESTER TOWNSHIP
Street:
City: n/a

Well Status: Water Supply
Prim. Use: n/a
Sec. Use: n/a
Boring Method: Cable Tool

Test Method: CLOUDY
Pump Set (m): n/a
SWL (ft) 40
Final Level: 65 ft
Pump Rate: 10 GPM
Recom. Rate: 5 GPM

Tag:
Audit No:
Contractor License: 1517
Well Completion Date: 04/15/1975
Received Date: 07/08/1975

Well Depth (m): 35.3568
Depth to Bedrock (m): 2
Depth to Water: ft
Water Kind: FRESH

Pipe ID: 10585273
Pump Test ID 991514733
Flowing: N
Pump Duration (hr): 1
Pump Duration (m): 20

CASING DETAILS

Layer Value of "0" denotes a Null value and cannot be stratified and ordered.

Layer	Case ID	Casing Diamter	Diamter Units	Material	Top Depth	Bottom Depth
1	930064874	5	inch	STEEL	n/a	18 ft
2	930064875	5	inch	OPEN HOLE	n/a	116 ft

FORMATION DETAILS

Layer Value of "0" denotes a Null value and cannot be stratified and ordered.

Layer	Material	Material 2	Material 3	Colour	Top Depth	Bottom Depth
1	TOPSOIL	SAND	n/a	BROWN	0	2 ft
2	SHALE	n/a	n/a	BROWN	2	10 ft
3	LIMESTONE	n/a	n/a	GREY	10	116 ft

End of Record

18	Easting:	456104.80
	Northing:	5016929.00
	Elev (masl):	101.82

Latitude: 45.304492
Longitude: -75.559911

Well ID: **1514908**

LOCATION
WELL

Lot: 026
Con: 05
Municipality: OTTAWA-CARLETON
Township: GLOUCESTER TOWNSHIP
Street:
City: n/a

Well Status: Water Supply
Prim. Use: n/a
Sec. Use: Domestic
Boring Method: Air Percussion

Tag:
Audit No:
Contractor License: 1558
Well Completion Date: 08/15/1975
Received Date: 09/11/1975

Well Depth (m): 75.5904
Depth to Bedrock (m): 0
Depth to Water: ft
Water Kind: Not stated

PUMP TEST

Test Method:
Pump Set (m): n/a
SWL (ft): 40
Final Level: 100 ft
Pump Rate: 15 GPM
Recom. Rate: 5 GPM

Pipe ID:
Pump Test ID: 991514908
Flowing: N
Pump Duration (hr): 1
Pump Duration (m): 0

CASING DETAILS

Layer Value of "0" denotes a Null value and cannot be stratified and ordered.

Table with 7 columns: Layer, Case ID, Casing Diameter, Diameter Units, Material, Top Depth, Bottom Depth. Rows 1 and 2.

FORMATION DETAILS

Layer Value of "0" denotes a Null value and cannot be stratified and ordered.

Table with 7 columns: Layer, Material, Material 2, Material 3, Colour, Top Depth, Bottom Depth. Rows 1 to 4.

End of Record

Table with 2 columns: Easting, Northing, Elev (masl). Row 18.

Latitude: 45.309274
Longitude: -75.546472

Well ID: 1527048

LOCATION

Lot: 026
Con: 06
Municipality: OTTAWA-CARLETON
Township: GLOUCESTER TOWNSHIP
Street:
City: n/a

Tag:
Audit No: 130025
Contractor License: 1558
Well Completion Date: 04/19/1993
Received Date: 05/06/1993

WELL

Well Status: Water Supply
Prim. Use: n/a
Sec. Use: n/a
Boring Method: Air Percussion

Well Depth (m): 41.148
Depth to Bedrock (m): 0
Depth to Water: ft
Water Kind: Not stated

PUMP TEST

Test Method: n/a
Pump Set (m): n/a
SWL (ft): 31
Final Level: 130 ft
Pump Rate: 15 GPM
Recom. Rate: 5 GPM

Pipe ID: 10597297
Pump Test ID: 991527048
Flowing: N
Pump Duration (hr): 1
Pump Duration (m): 0

CASING DETAILS

Layer Value of "0" denotes a Null value and cannot be stratified and ordered.

Table with 7 columns: Layer, Case ID, Casing Diameter, Diameter Units, Material, Top Depth, Bottom Depth. Rows 1 to 3.

FORMATION DETAILS

Layer Value of "0" denotes a Null value and cannot be stratified and ordered.

Table with 7 columns: Layer, Material, Material 2, Material 3, Colour, Top Depth, Bottom Depth. Rows 1 to 4.

End of Record

Table with 2 columns: Easting, Northing, Elev (masl). Row 18.

Latitude: 45.309274
Longitude: -75.546472

Well ID: 1527383

LOCATION

Lot: 026
Con: 06
Municipality: OTTAWA-CARLETON
Township: GLOUCESTER TOWNSHIP
Street:

Tag:
Audit No: 135946
Contractor License: 1558
Well Completion Date: 08/16/1993
Received Date:

L	City:	n/a	09/21/1993
WELL	Well Status:	Water Supply	Well Depth (m): 30.48
	Prim. Use:	n/a	Depth to Bedrock (m): 28
	Sec. Use:	n/a	Depth to Water: ft
	Boring Method:	Air Percussion	Water Kind: Not stated
PUMP TEST	Test Method:	CLOUDY	Pipe ID: 10597603
	Pump Set (m):	n/a	Pump Test ID: 991527383
	SWL (ft)	7	Flowing: N
	Final Level:	15 ft	Pump Duration (hr): 1
	Pump Rate:	20 GPM	Pump Duration (m): 0
	Recom. Rate:	5 GPM	

CASING DETAILS

Layer Value of "0" denotes a Null value and cannot be stratified and ordered.

Layer	Case ID	Casing Diameter	Diameter Units	Material	Top Depth	Bottom Depth
1	930085613	6	inch	STEEL	n/a	39 ft
2	930085614	6	inch	OPEN HOLE	n/a	100 ft

FORMATION DETAILS

Layer Value of "0" denotes a Null value and cannot be stratified and ordered.

Layer	Material	Material 2	Material 3	Colour	Top Depth	Bottom Depth
1	SAND	STONES	n/a	BROWN	0	5 ft
2	HARDPAN	BOULDERS	n/a	GREY	5	28 ft
3	SANDSTONE	HARD	n/a	GREY	28	100 ft

End of Record

18	Easting:	457162.00	Latitude: 45.309274	Well ID: 1527384	
	Northing:	5017453.00			Longitude: -75.546472
	Elev (masl):	82.18			

LOCATION	Lot:	026	Tag:	
	Con:	06	Audit No:	135944
	Municipality:	OTTAWA-CARLETON	Contractor License:	1558
	Township:	GLOUCESTER TOWNSHIP	Well Completion Date:	08/16/1993
WELL	Street:		Received Date:	09/21/1993
	City:	n/a		
	Well Status:	Water Supply	Well Depth (m):	30.48
	Prim. Use:	n/a	Depth to Bedrock (m):	0
PUMP TEST	Sec. Use:	n/a	Depth to Water:	ft
	Boring Method:	Air Percussion	Water Kind:	Not stated
	Test Method:	CLOUDY	Pipe ID:	10597604
	Pump Set (m):	n/a	Pump Test ID:	991527384
	SWL (ft)	22	Flowing:	N
	Final Level:	24 ft	Pump Duration (hr):	1
Pump Rate:	15 GPM	Pump Duration (m):	0	
Recom. Rate:	5 GPM			

CASING DETAILS

Layer Value of "0" denotes a Null value and cannot be stratified and ordered.

Layer	Case ID	Casing Diameter	Diameter Units	Material	Top Depth	Bottom Depth
1	930085615	6	inch	STEEL	n/a	22 ft
2	930085616	6	inch	OPEN HOLE	n/a	100 ft

FORMATION DETAILS

Layer Value of "0" denotes a Null value and cannot be stratified and ordered.

Layer	Material	Material 2	Material 3	Colour	Top Depth	Bottom Depth
1	SANDSTONE	HARD	n/a	GREY	0	100 ft

End of Record

18	Easting:	456298.00	Latitude: 45.30472	Well ID: 1535203	
	Northing:	5016953.00			Longitude: -75.557449
	Elev (masl):	90.37			

LOCATION
WELL
PUMP TEST

Lot: 06
 Con: 06
 Municipality: OTTAWA-CARLETON
 Township: GLOUCESTER TOWNSHIP
 Street: 3500 RIDEAU ROAD
 City: GLOUCESTER

Tag: A018916
 Audit No: Z19099
 Contractor License: 1119
 Well Completion Date: 10/27/2004
 Received Date: 11/26/2004

Well Status: Water Supply
 Prim. Use: n/a
 Sec. Use: n/a
 Boring Method: Air Percussion

Well Depth (m): 42.67
 Depth to Bedrock (m): 4
 Depth to Water: r3
 Water Kind:

Test Method: CLEAR
 Pump Set (m): 41.16
 SWL (ft): 14.18
 Final Level: 15.8m
 Pump Rate: 75.7LPM
 Recom. Rate: 75.7LPM

Pipe ID: 11181474
 Pump Test ID: 11189805
 Flowing: n/a
 Pump Duration (hr): 1
 Pump Duration (m): 0

CASING DETAILS

Layer Value of "0" denotes a Null value and cannot be stratified and ordered.

Layer	Case ID	Casing Diameter	Diameter Units	Material	Top Depth	Bottom Depth
1	930843335	15.88	cm	STEEL	0	6.7 m
2	930843336	n/a	cm	OPEN HOLE	6.09	42.67 m

FORMATION DETAILS

Layer Value of "0" denotes a Null value and cannot be stratified and ordered.

Layer	Material	Material 2	Material 3	Colour	Top Depth	Bottom Depth
1	GRAVEL	TOPSOIL	n/a	n/a	0	1.21 m
2	SANDSTONE	n/a	n/a	GREY	1.21	35.05 m
3	LIMESTONE	SANDSTONE	n/a	GREY	35.05	42.67 m

End of Record

17	Eastings:	436883.00
	Northing:	4794755.00
	Elev (masl):	87.38

Latitude: 45.303821
 Longitude: -75.547937

Well ID: **7115711**

LOCATION
WELL
PUMP TEST

Lot: 026
 Con: 06
 Municipality: OTTAWA-CARLETON
 Township: GLOUCESTER TOWNSHIP
 Street: TW #5
 City: GLOUCESTER

Tag: A068335
 Audit No: Z84410
 Contractor License: 1558
 Well Completion Date: 09/26/2008
 Received Date: 12/02/2008

Well Status: Water Supply
 Prim. Use: n/a
 Sec. Use: Industrial
 Boring Method: Rotary (Air)

Well Depth (m): 29.86
 Depth to Bedrock (m): n/a
 Depth to Water: r2
 Water Kind: Untested

Test Method: CLEAR
 Pump Set (m): 22.85
 SWL (ft): 6.85
 Final Level: 9.99m
 Pump Rate: 54.6LPM
 Recom. Rate: 45.6LPM

Pipe ID: 1002442328
 Pump Test ID: 1002442329
 Flowing: n/a
 Pump Duration (hr): 6
 Pump Duration (m): 0

CASING DETAILS

Layer Value of "0" denotes a Null value and cannot be stratified and ordered.

Layer	Case ID	Casing Diameter	Diameter Units	Material	Top Depth	Bottom Depth
1	1002442337	15.86	cm	STEEL	-0.45	12.8 m

FORMATION DETAILS

Layer Value of "0" denotes a Null value and cannot be stratified and ordered.

Layer	Material	Material 2	Material 3	Colour	Top Depth	Bottom Depth
1	TOPSOIL	STONES	FILL	BROWN	0	1.21 m
2	TOPSOIL	STONES	SANDY	GREY	1.21	3.96 m
3	SANDSTONE	n/a	HARD	GREY	3.96	29.86 m

End of Record

17	Eastings:	555808.00
	Northings:	4809940.00
	Elev (masl):	85.10

Latitude: 45.303818
Longitude: -75.556139

Well ID: **7115790**

LOCATION
Lot: 026
Con: 06
Municipality: OTTAWA-CARLETON
Township: GLOUCESTER TOWNSHIP
Street: HAWTHORNE ROAD AT RIDEAU ROAD
City: Ottawa

Tag: A074584
Audit No: M02897
Contractor License: 1844
Well Completion Date: 07/15/2008
Received Date: 11/26/2008

WELL
Well Status: Test Hole
Prim. Use: n/a
Sec. Use: n/a
Boring Method: n/a

Well Depth (m): 7.6
Depth to Bedrock (m): n/a
Depth to Water:
Water Kind:

PUMP TEST
Test Method: n/a
Pump Set (m): n/a
SWL (ft): 1.7
Final Level: n/a m
Pump Rate: n/a
Recom. Rate: n/a

Pipe ID: 1002782586
Pump Test ID: 1002782562
Flowing: n/a
Pump Duration (hr): n/a
Pump Duration (m): n/a

CASING DETAILS

Layer Value of "0" denotes a Null value and cannot be stratified and ordered.

Layer	Case ID	Casing Diameter	Diameter Units	Material	Top Depth	Bottom Depth
0	1002782579	n/a	n/a	PLASTIC	n/a	3 m
0	1002782525	n/a	n/a	PLASTIC	n/a	1.5 m
0	1002782570	n/a	n/a	PLASTIC	n/a	3 m
0	1002782597	n/a	n/a	PLASTIC	n/a	1.37 m
0	1002782561	n/a	n/a	PLASTIC	n/a	1.5 m
0	1002782588	n/a	n/a	PLASTIC	n/a	1.5 m
0	1002782552	n/a	n/a	PLASTIC	n/a	1.22 m
0	1002782534	n/a	n/a	PLASTIC	n/a	0.6 m
0	1002782543	n/a	n/a	PLASTIC	n/a	2.13 m

FORMATION DETAILS

Layer Value of "0" denotes a Null value and cannot be stratified and ordered.

Layer	Material	Material 2	Material 3	Colour	Top Depth	Bottom Depth
1	FINE SAND	SILT	DENSE	GREY	0	0.9 m
2	FILL	SAND	SILT	BROWN	0.9	4.7 m
3	SAND	SILT	n/a	GREY	4.7	6 m
4	TILL	SAND	GRAVEL	BROWN	6	7.6 m

End of Record

n/a	Eastings:	<null>
	Northings:	<null>
	Elev (masl):	94.41

Latitude: 45.302584
Longitude: -75.55063

Well ID: **7115790**

LOCATION
Lot: 026
Con: 06
Municipality: OTTAWA-CARLETON
Township: GLOUCESTER TOWNSHIP
Street: HAWTHORNE ROAD AT RIDEAU ROAD
City: Ottawa

Tag: A074584
Audit No: M02897
Contractor License: 1844
Well Completion Date: 07/15/2008
Received Date: 11/26/2008

WELL
Well Status: Test Hole
Prim. Use: n/a
Sec. Use: n/a
Boring Method: n/a

Well Depth (m): 0
Depth to Bedrock (m): n/a
Depth to Water:
Water Kind:

PUMP TEST
Test Method: n/a
Pump Set (m): n/a
SWL (ft): 1.3
Final Level: n/a m
Pump Rate: n/a
Recom. Rate: n/a

Pipe ID: 1002782595
Pump Test ID: 1002782535
Flowing: n/a
Pump Duration (hr): n/a
Pump Duration (m): n/a

CASING DETAILS

Layer Value of "0" denotes a Null value and cannot be stratified and ordered.

Layer	Case ID	Casing Diamter	Diamter Units	Material	Top Depth	Bottom Depth
0	1002782588	n/a	n/a	PLASTIC	n/a	1.5 m
0	1002782570	n/a	n/a	PLASTIC	n/a	3 m
0	1002782543	n/a	n/a	PLASTIC	n/a	2.13 m
0	1002782561	n/a	n/a	PLASTIC	n/a	1.5 m
0	1002782525	n/a	n/a	PLASTIC	n/a	1.5 m
0	1002782534	n/a	n/a	PLASTIC	n/a	0.6 m
0	1002782597	n/a	n/a	PLASTIC	n/a	1.37 m
0	1002782552	n/a	n/a	PLASTIC	n/a	1.22 m
0	1002782579	n/a	n/a	PLASTIC	n/a	3 m

FORMATION DETAILS

Layer Value of "0" denotes a Null value and cannot be stratified and ordered.

Layer	Material	Material 2	Material 3	Colour	Top Depth	Bottom Depth
1	FINE SAND	SILT	DENSE	GREY	0	0.9 m
2	FILL	SAND	SILT	BROWN	0.9	4.7 m
3	SAND	SILT	n/a	GREY	4.7	6 m
4	TILL	SAND	GRAVEL	BROWN	6	7.6 m

End of Record

n/a	Easting:	<null>
	Northing:	<null>
	Elev (masl):	103.53

Latitude: 45.302237
Longitude: -75.553598

Well ID: **7115790**

LOCATION
Lot: 026
Con: 06
Municipality: OTTAWA-CARLETON
Township: GLOUCESTER TOWNSHIP
Street: HAWTHORNE ROAD AT RIDEAU ROAD
City: Ottawa

Tag: A074584
Audit No: M02897
Contractor License: 1844
Well Completion Date: 07/08/2008
Received Date: 11/26/2008

WELL
Well Status: Test Hole
Prim. Use: n/a
Sec. Use: n/a
Boring Method: n/a

Well Depth (m): 0
Depth to Bedrock (m): n/a
Depth to Water:
Water Kind:

PUMP TEST
Test Method: n/a
Pump Set (m): n/a
SWL (ft): 3.6
Final Level: n/a m
Pump Rate: n/a
Recom. Rate: n/a

Pipe ID: 1002782586
Pump Test ID: 1002782535
Flowing: n/a
Pump Duration (hr): n/a
Pump Duration (m): n/a

CASING DETAILS

Layer Value of "0" denotes a Null value and cannot be stratified and ordered.

Layer	Case ID	Casing Diamter	Diamter Units	Material	Top Depth	Bottom Depth
0	1002782552	n/a	n/a	PLASTIC	n/a	1.22 m
0	1002782597	n/a	n/a	PLASTIC	n/a	1.37 m
0	1002782543	n/a	n/a	PLASTIC	n/a	2.13 m
0	1002782525	n/a	n/a	PLASTIC	n/a	1.5 m
0	1002782579	n/a	n/a	PLASTIC	n/a	3 m
0	1002782561	n/a	n/a	PLASTIC	n/a	1.5 m
0	1002782534	n/a	n/a	PLASTIC	n/a	0.6 m
0	1002782570	n/a	n/a	PLASTIC	n/a	3 m
0	1002782588	n/a	n/a	PLASTIC	n/a	1.5 m

FORMATION DETAILS

Layer Value of "0" denotes a Null value and cannot be stratified and ordered.

Layer	Material	Material 2	Material 3	Colour	Top Depth	Bottom Depth
1	FINE SAND	SILT	DENSE	GREY	0	0.9 m
2	FILL	SAND	SILT	BROWN	0.9	4.7 m
3	SAND	SILT	n/a	GREY	4.7	6 m
4	TILL	SAND	GRAVEL	BROWN	6	7.6 m

End of Record

n/a	Easting:	<null>
	Northing:	<null>
	Elev (masl):	

Latitude: 45.307135
Longitude: -75.55334

Well ID: **7115790**

103.53

LOCATION
Lot: 026
Con: 06
Municipality: OTTAWA-CARLETON
Township: GLOUCESTER TOWNSHIP
Street: HAWTHORNE ROAD AT RIDEAU ROAD
City: Ottawa

WELL
Well Status: Test Hole
Prim. Use: n/a
Sec. Use: n/a
Boring Method: n/a

PUMP TEST
Test Method: n/a
Pump Set (m): n/a
SWL (ft) 1.7
Final Level: n/a m
Pump Rate: n/a
Recom. Rate: n/a

Tag: A074584
Audit No: M02897
Contractor License: 1844
Well Completion Date: 07/15/2008
Received Date: 11/26/2008

Well Depth (m): 0
Depth to Bedrock (m): n/a
Depth to Water:
Water Kind:

Pipe ID: 1002782532
Pump Test ID: 1002782571
Flowing: n/a
Pump Duration (hr): n/a
Pump Duration (m): n/a

CASING DETAILS

Layer Value of "0" denotes a Null value and cannot be stratified and ordered.

Layer	Case ID	Casing Diameter	Diameter Units	Material	Top Depth	Bottom Depth
0	1002782588	n/a	n/a	PLASTIC	n/a	1.5 m
0	1002782597	n/a	n/a	PLASTIC	n/a	1.37 m
0	1002782561	n/a	n/a	PLASTIC	n/a	1.5 m
0	1002782579	n/a	n/a	PLASTIC	n/a	3 m
0	1002782525	n/a	n/a	PLASTIC	n/a	1.5 m
0	1002782534	n/a	n/a	PLASTIC	n/a	0.6 m
0	1002782543	n/a	n/a	PLASTIC	n/a	2.13 m
0	1002782552	n/a	n/a	PLASTIC	n/a	1.22 m
0	1002782570	n/a	n/a	PLASTIC	n/a	3 m

FORMATION DETAILS

Layer Value of "0" denotes a Null value and cannot be stratified and ordered.

Layer	Material	Material 2	Material 3	Colour	Top Depth	Bottom Depth
1	FINE SAND	SILT	DENSE	GREY	0	0.9 m
2	FILL	SAND	SILT	BROWN	0.9	4.7 m
3	SAND	SILT	n/a	GREY	4.7	6 m
4	TILL	SAND	GRAVEL	BROWN	6	7.6 m

End of Record

n/a	Easting:	<null>
	Northing:	<null>
	Elev (masl):	94.41

Latitude: 45.305492
Longitude: -75.552495

Well ID: **7115790**

LOCATION
Lot: 026
Con: 06
Municipality: OTTAWA-CARLETON
Township: GLOUCESTER TOWNSHIP
Street: HAWTHORNE ROAD AT RIDEAU ROAD
City: Ottawa

WELL
Well Status: Test Hole
Prim. Use: n/a
Sec. Use: n/a
Boring Method: n/a

PUMP TEST
Test Method: n/a
Pump Set (m): n/a
SWL (ft) 1.3
Final Level: n/a m
Pump Rate: n/a
Recom. Rate: n/a

Tag: A074584
Audit No: M02897
Contractor License: 1844
Well Completion Date: 07/14/2008
Received Date: 11/26/2008

Well Depth (m): 0
Depth to Bedrock (m): n/a
Depth to Water:
Water Kind:

Pipe ID: 1002782595
Pump Test ID: 1002782544
Flowing: n/a
Pump Duration (hr): n/a
Pump Duration (m): n/a

CASING DETAILS

Layer Value of "0" denotes a Null value and cannot be stratified and ordered.

Layer	Case ID	Casing Diameter	Diameter Units	Material	Top Depth	Bottom Depth
0	1002782525	n/a	n/a	PLASTIC	n/a	1.5 m
0	1002782597	n/a	n/a	PLASTIC	n/a	1.37 m

0	1002782534	n/a	n/a	PLASTIC	n/a	0.6	m
0	1002782588	n/a	n/a	PLASTIC	n/a	1.5	m
0	1002782579	n/a	n/a	PLASTIC	n/a	3	m
0	1002782552	n/a	n/a	PLASTIC	n/a	1.22	m
0	1002782570	n/a	n/a	PLASTIC	n/a	3	m
0	1002782543	n/a	n/a	PLASTIC	n/a	2.13	m
0	1002782561	n/a	n/a	PLASTIC	n/a	1.5	m

FORMATION DETAILS

Layer Value of "0" denotes a Null value and cannot be stratified and ordered.

Layer	Material	Material 2	Material 3	Colour	Top Depth	Bottom Depth
1	FINE SAND	SILT	DENSE	GREY	0	0.9 m
2	FILL	SAND	SILT	BROWN	0.9	4.7 m
3	SAND	SILT	n/a	GREY	4.7	6 m
4	TILL	SAND	GRAVEL	BROWN	6	7.6 m

End of Record

n/a	Easting:	<null>
	Northing:	<null>
	Elev (masl):	84.01

Latitude: 45.307865
Longitude: -75.558653

Well ID: **7115790**

LOCATION
Lot: 026
Con: 06
Municipality: OTTAWA-CARLETON
Township: GLOUCESTER TOWNSHIP
Street: HAWTHORNE ROAD AT RIDEAU ROAD
City: Ottawa

Tag: A074584
Audit No: M02897
Contractor License: 1844
Well Completion Date: 07/14/2008
Received Date: 11/26/2008

WELL
Well Status: Test Hole
Prim. Use: n/a
Sec. Use: n/a
Boring Method: n/a

Well Depth (m): 0
Depth to Bedrock (m): n/a
Depth to Water:
Water Kind:

PUMP TEST
Test Method: n/a
Pump Set (m): n/a
SWL (ft): 1
Final Level: n/a m
Pump Rate: n/a
Recom. Rate: n/a

Pipe ID: 1002782599
Pump Test ID: 1002782589
Flowing: n/a
Pump Duration (hr): n/a
Pump Duration (m): n/a

CASING DETAILS

Layer Value of "0" denotes a Null value and cannot be stratified and ordered.

Layer	Case ID	Casing Diamter	Diamter Units	Material	Top Depth	Bottom Depth
0	1002782588	n/a	n/a	PLASTIC	n/a	1.5 m
0	1002782525	n/a	n/a	PLASTIC	n/a	1.5 m
0	1002782543	n/a	n/a	PLASTIC	n/a	2.13 m
0	1002782534	n/a	n/a	PLASTIC	n/a	0.6 m
0	1002782561	n/a	n/a	PLASTIC	n/a	1.5 m
0	1002782579	n/a	n/a	PLASTIC	n/a	3 m
0	1002782552	n/a	n/a	PLASTIC	n/a	1.22 m
0	1002782597	n/a	n/a	PLASTIC	n/a	1.37 m
0	1002782570	n/a	n/a	PLASTIC	n/a	3 m

FORMATION DETAILS

Layer Value of "0" denotes a Null value and cannot be stratified and ordered.

Layer	Material	Material 2	Material 3	Colour	Top Depth	Bottom Depth
1	FINE SAND	SILT	DENSE	GREY	0	0.9 m
2	FILL	SAND	SILT	BROWN	0.9	4.7 m
3	SAND	SILT	n/a	GREY	4.7	6 m
4	TILL	SAND	GRAVEL	BROWN	6	7.6 m

End of Record

n/a	Easting:	<null>
	Northing:	<null>
	Elev (masl):	88.61

Latitude: 45.302947
Longitude: -75.550021

Well ID: **7149254**

LOCATION

Lot:
 Con:
 Municipality: OTTAWA-CARLETON
 Township: GLOUCESTER TOWNSHIP
 Street: TW#7 HOAWTHORNE RD.
 City: GLOUCESTER

Tag: A082844
 Audit No: Z101832
 Contractor License: 1558
 Well Completion Date: 05/25/2010
 Received Date: 08/04/2010

WELL

Well Status: Water Supply
 Prim. Use: n/a
 Sec. Use: n/a
 Boring Method: Rotary (Reverse)

Well Depth (m): 29.86
 Depth to Bedrock (m): n/a
 Depth to Water: m!
 Water Kind: Untested

PUMP TEST

Test Method: CLEAR
 Pump Set (m): 23.38
 SWL (ft): 4.41
 Final Level: 7.01m
 Pump Rate: 27.3LPM
 Recom. Rate: 27.3LPM

Pipe ID: 1003263559
 Pump Test ID: 1003263560
 Flowing: n/a
 Pump Duration (hr): 6
 Pump Duration (m): 0

CASING DETAILS

Layer Value of "0" denotes a Null value and cannot be stratified and ordered.

Layer	Case ID	Casing Diameter	Diameter Units	Material	Top Depth	Bottom Depth
1	1003263568	15.86	cm	STEEL	-0.45	6.4 m

FORMATION DETAILS

Layer Value of "0" denotes a Null value and cannot be stratified and ordered.

Layer	Material	Material 2	Material 3	Colour	Top Depth	Bottom Depth
1	TOPSOIL	STONES	PACKED	BROWN	0	4.26 m
2	SANDSTONE	n/a	HARD	GREY	4.26	29.86 m

End of Record

n/a

Easting:	<null>
Northing:	<null>
Elev (masl):	89.57

Latitude: 45.302183
 Longitude: -75.551672

Well ID: **7206093**

LOCATION

Lot: 027
 Con: 06
 Municipality: OTTAWA-CARLETON
 Township: GLOUCESTER TOWNSHIP
 Street: 35 SAPPERS RIDGE
 City: Ottawa

Tag: A089801
 Audit No: Z103282
 Contractor License: 3749
 Well Completion Date: 07/18/2013
 Received Date: 08/12/2013

WELL

Well Status: <null>
 Prim. Use: n/a
 Sec. Use: n/a
 Boring Method: Rotary (Convent.)

Well Depth (m): 47.244
 Depth to Bedrock (m): n/a
 Depth to Water: ft
 Water Kind: FRESH

PUMP TEST

Test Method: CLEAR
 Pump Set (m): 130
 SWL (ft): 25
 Final Level: 34 ft
 Pump Rate: 10 GPM
 Recom. Rate: n/a GPM

Pipe ID: 1004977760
 Pump Test ID: 1004977761
 Flowing: n/a
 Pump Duration (hr): 1
 Pump Duration (m): n/a

CASING DETAILS

Layer Value of "0" denotes a Null value and cannot be stratified and ordered.

Layer	Case ID	Casing Diameter	Diameter Units	Material	Top Depth	Bottom Depth
1	1004977768	5.625	inch	STEEL	40	-2 ft

FORMATION DETAILS

Layer Value of "0" denotes a Null value and cannot be stratified and ordered.

Layer	Material	Material 2	Material 3	Colour	Top Depth	Bottom Depth
1	FILL	n/a	LOOSE	n/a	0	8 ft
2	CLAY	GRAVEL	PACKED	GREY	8	24 ft
3	LIMESTONE	n/a	n/a	n/a	24	155 ft

End of Record

Appendix B

Photographs



Photo 1 - View of drilled water well on the Site used during pumping test and proposed building area showing ground improvement.



Photo 2 - View of ground improvement area.



Site Photographs



Photo 3 - Wellhead at pumped water well A342117.



Photo 4 - Observation well (ID A305146) used during pumping test for monitoring of potential interference effects.



Site Photographs



Photo 5 - Observation well (ID A295342) used during pumping test for monitoring of potential interference effects.



Photo 6 - Observation well (ID A342260) used during pumping test for monitoring of potential interference effects.



Site Photographs




Photo 7 - Observation well (ID A018916) used during pumping test for monitoring of potential interference effects.



Photo 8 - Observation well at 4885 Hawthorne Road used during pumping test for monitoring of potential interference effects.



Site Photographs

Appendix C

**Well Record A342117 and WSP Well
Certificate**

CERTIFICATE OF WELL COMPLIANCE



I (Jeremy Hanna) AIR ROCK DRILLING CO. LTD. - DO HEREBY CERTIFY

that I am licensed to drill water wells in the Province of Ontario, and that I have

supervised the drilling of the water well on the property of:

CONSOLIDATED FASTFRATE (OTTAWA)
OWNER: HOLDINGS INC.

Location: # 301 SOMME STREET, GLOUCESTER

Part 26+
LOT: 27 CON: 6 R.F. PLAN # 4M-1388 S/L # X

Ottawa-Carleton / Geographical Township of GLOUCESTER

I CERTIFY FURTHER that, I am aware of the well drilling requirements, the guidelines, recommendations and regulations of the Ministry of the Environment governing well installations in the Province of Ontario, and the standards specified in any subdivision agreement and hydrogeological report applicable to this site and City Standards.

AND DO HEREBY CERTIFY THAT the said well has been drilled, cased, grouted (cement or bentonite) as applicable and constructed in strict conformity with the standards required.

Signed this 27th Day of JULY, 2022


Jeremy Hanna (T3632)

Air Rock Drilling Co. Ltd. (C-7681)

The Engineer on behalf of the Landowner set out above, Certifies that he/she has inspected the well and it was constructed in accordance with the specifications in O.Reg 903, this report and the Hydrogeological Report with regards to casing length and grouting requirements.

Signed this 16th day of Aug 2022

(Engineer)



2022511
TAGA342117



Measurements recorded in: Metric Imperial

Page _____ of _____

Well Owner's Information

First Name: Consolidated Last Name/Organization: FastRate (Ottawa) Holdings Inc. E-mail Address: _____
 Mailing Address (Street Number/Name): 330 Preston Street, 7th Floor, Ottawa, Ont. K1P 5N4 Municipality: _____ Province: _____ Postal Code: _____ Telephone No. (inc. area code): _____

Well Location

Address of Well Location (Street Number/Name): # 301 SOMME STREET Township: GLOUCESTER Lot: P/L26407 Concession: 6 R.F.
 County/District/Municipality: OTTAWA-CARLETON City/Town/Village: GLOUCESTER Province: Ontario Postal Code: _____
 UTM Coordinates: Zone: 18Q UTM Easting: 50172008 UTM Northing: 4M-1388

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

General Colour	Most Common Material	Other Materials	General Description	Depth (m)
				From To
	Gravel, Hard Pan, Boulders			0' 46'
	Grey Black limestone w/ white sandstone mix			46' 140'

Annular Space

Depth Set at (m)	Type of Sealant Used	Volume Placed (m ³)
From To	(Material and Type)	(m ³)
52' 0'	Neat cement slurry	12.48

Method of Construction

Cable Tool Rotary (Conventional) Rotary (Reverse) Boring Air percussion Other, specify _____

Well Use

Public Commercial Not used Domestic Municipal Dewatering Livestock Test Hole Monitoring Irrigation Cooling & Air Conditioning Industrial Other, specify _____

Construction Record - Casing

inside Diameter (cm/in)	Open Hole OR Material (Galvanized, Fibreglass, Concrete, Plastic, Steel)	Wall Thickness (cm/in)	Depth (m/ft)	Status of Well
			From To	<input type="checkbox"/> Water Supply <input type="checkbox"/> Replacement Well <input type="checkbox"/> Test Hole <input type="checkbox"/> Recharge Well <input type="checkbox"/> Dewatering Well <input type="checkbox"/> Observation and/or Monitoring Hole <input type="checkbox"/> Alteration (Construction) <input type="checkbox"/> Abandoned, Insufficient Supply <input type="checkbox"/> Abandoned, Poor Water Quality <input type="checkbox"/> Abandoned, other, specify _____ <input type="checkbox"/> Other, specify _____
6 1/4"	Steel	.188"	42' 52'	<input checked="" type="checkbox"/> Discontinued? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
6"	Open hole		52' 140'	

Construction Record - Screen

Outside Diameter (cm/in)	Material (Plastic, Galvanized, Steel)	Slot No.	Depth (m/ft)
			From To

Water Details

Water found at Depth (m/ft)	Kind of Water: <input type="checkbox"/> Fresh <input type="checkbox"/> Untested <input type="checkbox"/> Gas <input type="checkbox"/> Other, specify _____	Hole Diameter
		Depth (m/ft) From To Diameter (cm/in)
128 (m/ft)		0' 52' 9 3/4"
134 (m/ft)		52' 140' 6"

Well Contractor and Well Technician Information

Business Name of Well Contractor: Air Pack Drilling Co Ltd Well Contractor's Licence No.: C7681
 Business Address (Street Number/Name): 6659 Franktown Road Richmond Municipality: _____
 Province: Ont Postal Code: K0A0R0 Business E-mail Address: _____

Bus. Telephone No. (inc. area code): 038382170 Name of Well Technician (Last Name, First Name): HANNA Jeremy
 Well Technician's Licence No.: T3632 Signature of Technician and/or Contractor: _____ Date Submitted: 20200831


Results of Well Yield Testing

After test of well yield, water was: Clear and sand free Other, specify _____

If pumping discontinued, give reason: _____

Time (min)	Draw Down (m)	Water Level (m)	Recovery Time (min)	Water Level (m)
1	28.2	28.2	1	29.2
2	29.3	29.3	2	29.1
3	29.4	29.4	3	29.1
4	29.5	29.5	4	29.1
5	29.6	29.6	5	29.1
10	29.7	29.7	10	29.1
15	29.9	29.9	15	28.2
20	30.1	30.1	20	28.2
25	30.3	30.3	25	
30	30.4	30.4	30	
40	30.5	30.5	40	
50	30.6	30.6	50	
60	30.7	30.7	60	

Pump intake set at (m/ft): 120'
 Pumping rate (l/min/GPM): 20
 Duration of pumping: 1 hrs + 0 min
 Final water level end of pumping (m): 30.7"
 Recommended pump depth (m/ft): 100'
 Recommended pump rate (l/min/GPM): 20
 Well production (l/min/GPM): 20
 Discontinued? Yes No



Comments: 1 HP 20 GPM Set @ 100 FT

Well owner's information package delivered: Yes No

Date Package Delivered: 20200728
 Date Work Completed: 20200727

Ministry Use Only
 Audit No.: Z379047
 Receiver: _____

Appendix D

Calibration Records

Control number: PET-TE-19 Project number: 12580314
 Date (mm/dd/yyyy): 08/09/2022 Project name: Consolidated Fastfrate,
 HydroG Assessment
 User (print name): Jason Gerald Location: 301 Somme Street, Ottawa

Additional equipment control numbers and descriptions: Hach Pocket Colorimeter II
(S/N 15100E283721)

Field procedure before use:

	Check when completed
<ul style="list-style-type: none"> • Check batteries are charged. Replace AAA batteries if needed. • Review applicable MSDS sheets for the DPD foil pillows (21055-69 & 21056-69 – in equipment case). • Proceed with a Spec $\sqrt{\text{TM}}$ Secondary Standard repeatability test if required. Please note that this test is done at the shop. Please see pages 1-43 and 1-44 (Pocket Colorimeter) or 1-47 and 1-48 (Pocket Colorimeter II) of instruction manual. • Proceed with a User-Entered Calibration if the project requires it. This is usually done at the shop. Please see pages 2-15 to 2-27 in instruction manual. 	<input checked="" type="checkbox"/> <input checked="" type="checkbox"/> <input checked="" type="checkbox"/> <input checked="" type="checkbox"/>

Filing: Field file

Signature: _____



Control number: PET-TE-3
 Date (mm/dd/yyyy): 08/09/2022
 User (print name): Jason Gerald

Project number: 12580314
 Project name: Consolidated Fastfrate
HydroG Assessment
 Location: 301 Somme Street,
Ottawa

Additional equipment control numbers and descriptions: Gastech NP-204 natural gas
detector used for methane detection at wellhead.

Field procedure before use:

	Check when completed
<ul style="list-style-type: none"> • Check for damages • Ensure the instrument has been properly calibrated <p>Note: The equipment does not require a data entry sheet, so only one page will print out.</p>	<p style="text-align: center;">☒</p> <p style="text-align: center;">☒</p>

Filing: Field file

Signature:



Control number:	<u>PET-WL-25</u>	Project number:	<u>12580314</u>
Date (mm/dd/yyyy):	<u>08/09/2022</u>	Project name:	<u>Consolidated Fastfrate</u>
User (print name):	<u>Jason Gerald</u>		<u>HydroG Assessment</u>
		Location:	<u>301 Somme Street,</u> <u>Ottawa</u>


Additional equipment control numbers and descriptions: Heron Instruments, Dipper-T 100 m,
S/N 4009-T

Field procedure before use:

	Check when completed
<ul style="list-style-type: none"> • Check for broken or missing parts. • Check battery • Check operation of buzzer. • Check operation of signal light. • Test probe in water to ensure unit operates, both visually and audibly. • Check cable. 	 <input checked="" type="checkbox"/> <input checked="" type="checkbox"/> <input checked="" type="checkbox"/> <input checked="" type="checkbox"/> <input checked="" type="checkbox"/>

Filing: Field file

Signature:



Control number: <u>PET-WL-34</u> Date (mm/dd/yyyy): <u>08/09/2022</u> User (print name): <u>Jason Gerald</u>	Project number: <u>12580314</u> Project name: <u>Consolidated Fastfrate HydroG Assessment</u> Location: <u>301 Somme Street, Ottawa</u>
---	--

Additional equipment control numbers and descriptions: Waterra, WS-2 Closed Reel,
S/N WS2-00518

Field procedure before use:

	Check when completed
<ul style="list-style-type: none"> • Check for broken or missing parts. • Check battery • Check operation of buzzer. • Check operation of signal light. • Test probe in water to ensure unit operates, both visually and audibly. • Check cable. 	 <input checked="" type="checkbox"/> <input checked="" type="checkbox"/> <input checked="" type="checkbox"/> <input checked="" type="checkbox"/> <input checked="" type="checkbox"/>

Filing: Field file


Signature: _____



Appendix E

Aquifer Performance Testing

PUMP HISTORY CURVE
Well A342117: August 9-10, 2022



PUMP HISTORY CURVE

Drilled Water Well
MECP Well ID: A342117
Static Level = 7.96 mbtp (7.31 mbgs)

Note: m = metres; mbtp = metres below top of pipe; mbgs = metres below ground surface

DATE: SEPTEMBER 2022

LOCATION: 301 Somme Street, Ottawa, ON


JOB NUMBER: 12580314-01

DRAWING NUMBER: E-1



347 PIDO ROAD, UNIT 29
PETERBOROUGH, ON K9J 6X7
www.ghd.com

CONSTANT RATE TEST: WATER LEVEL vs LOG TIME
Well A342117: August 9-10, 2022



CONSTANT RATE

Drilled Water Well
 MECP Well ID: A342117
 Static Level = 7.96 mbtp (7.31 mbgs)

Note: m = metres; mbtp = metres below top of pipe; mbgs = metres below ground surface

DATE: SEPTEMBER 2022

LOCATION: 301 Somme Street, Ottawa, ON


JOB NUMBER: 12580314-01

DRAWING NUMBER: E-2



347 PIDO ROAD, UNIT 29
 PETERBOROUGH, ON K9J 6X7
 www.ghd.com

CONSTANT RATE DRAWDOWN, RECOVERY AND TESTING DETAILS
Well A342117: August 9-10, 2022



CONSTANT RATE DRAWDOWN

Drilled Water Well
 MECP Well ID: A342117
 Static Level = 7.96 mbtp (7.31 mbgs)


Note: m = metres; mbtp = metres below top of pipe; mbgs = metres below ground surface

DATE: SEPTEMBER 2022
LOCATION: 301 Somme Street, Ottawa, ON
JOB NUMBER: 12580314-01
DRAWING NUMBER: E-3



347 PIDO ROAD, UNIT 29
 PETERBOROUGH, ON K9J 6X7
 www.ghd.com

CONSTANT RATE: DRAWDOWN and RECOVERY VS LOG TIME
Well A342117: August 9-10, 2022



TRANSMISSIVITY

Drilled Water Well
 MECP Well ID: A342117

Static Level = 7.96 mbtp (7.31 mbgs)

Note: m = metres; mbtp = metres below top of pipe; mbgs = metres below ground surface

DATE: SEPTEMBER 2022

LOCATION: 301 Somme Street, Ottawa, ON

JOB NUMBER: 12580314-01

DRAWING NUMBER: E-4



347 PIDO ROAD, UNIT 29
 PETERBOROUGH, ON K9J 6X7
 www.ghd.com

Appendix F

Water Well Certificates of Analyses



SGS Canada Inc.

P.O. Box 4300 - 185 Concession St.
Lakefield - Ontario - K0L 2H0
Phone: 705-652-2000 FAX: 705-652-6365

Project : 12580314-01

17-August-2022

GHD Limited - 735

Attn : Jason Gerald

347 Pido Rd., Unit #29
Peterborough, ON
K9J 6Z8, Canada

Phone: 705-749-3317
Fax:705-749-9248

Date Rec. : 10 August 2022
LR Report: CA15144-AUG22
Reference: PO#:735-003858,
12580314-01, Jason
Gerald

Copy: #1

CERTIFICATE OF ANALYSIS

Final Report

Analysis	1: Analysis Start Date	2: Analysis Start Time	3: Analysis Completed Date	4: Analysis Completed Time	6: A342117 12hr
Sample Date & Time					09-Aug-22 19:07
Temp Upon Receipt [°C]	***	***	***	***	***
Total Coliform [cfu/100mL]	11-Aug-22	14:01	15-Aug-22	15:25	3
E.coli [cfu/100mL]	11-Aug-22	14:01	15-Aug-22	15:25	0
Fecal Coliform [cfu/100mL]	11-Aug-22	14:01	15-Aug-22	15:25	0
Background [cfu/100mL]	11-Aug-22	14:01	15-Aug-22	15:25	33
HPC [cfu/1mL]	11-Aug-22	14:01	15-Aug-22	15:25	55

MAC - Maximum Acceptable Concentration
AO/OG - Aesthetic Objective / Operational Guideline
NR - Not reportable under applicable drinking water regulations as per client.

Temperature of Sample upon Receipt: 13 degrees C
Cooling Agent Present: Yes
Custody Seal Present: Yes

Chain of Custody Number: 024625

Jill Campbell, B.Sc., GISAS
Project Specialist,
Environment, Health & Safety



SGS Canada Inc.
P.O. Box 4300 - 185 Concession St.
Lakefield - Ontario - KOL 2H0
Phone: 705-652-2000 FAX: 705-652-6365

GHD Limited - 735
Attn : Jason Gerald

347 Pido Rd., Unit #29
Peterborough, ON
K9J 6Z8, Canada

Phone: 705-749-3317
Fax: 705-749-9248

Project : 12580314-01

22-September-2022

Date Rec. : 10 August 2022
LR Report: CA15142-AUG22
Reference: PO#:735-003858, 12580314-01,
Jason Gerald

Copy: 2

CERTIFICATE OF ANALYSIS

Final Report - Revised

Analysis	1: Analysis Start Date	2: Analysis Start Time	3: Analysis Completed Date	4: Analysis Completed Time	5: MAC	6: AO/OG	7: A342117 1hr	8: A342117 6hr	9: A342117 12hr
Sample Date & Time							09-Aug-22 08:07	09-Aug-22 13:07	09-Aug-22 19:07
Temp Upon Receipt [°C]	***	***	***	***	***	***	***	***	***
Tannin+Lignin [mg phenol/L]	16-Aug-22	13:12	17-Aug-22	13:09			0.32	0.34	0.40
Alkalinity [mg/L as CaCO3]	15-Aug-22	15:41	17-Aug-22	12:21	---	30-500	265	261	261
CO3 [mg/L as CaCO3]	15-Aug-22	15:41	17-Aug-22	12:21	---	---	< 2	< 2	< 2
HCO3 [mg/L as CaCO3]	15-Aug-22	15:41	24-Aug-22	10:32			265	261	261
Temperature @ pH [°C]	15-Aug-22	15:41	24-Aug-22	10:32			21.9	21.7	20.5
pH [No unit]	15-Aug-22	15:41	17-Aug-22	12:21	---	6.5-8.5	8.14	8.20	8.23
Conductivity [uS/cm]	15-Aug-22	15:41	17-Aug-22	12:21			1180	1290	1350
TDS [mg/L]	15-Aug-22	08:47	17-Aug-22	12:04			763	914	914
Colour [TCU]	15-Aug-22	11:22	16-Aug-22	12:52			3	< 3	< 3
Turbidity [NTU]	10-Aug-22	17:53	11-Aug-22	09:56	1	5	2.50	2.89	4.21
Organic N [mg/L]	15-Aug-22	16:28	19-Aug-22	14:07			< 0.05	< 0.05	< 0.05
TKN [as N mg/L]	15-Aug-22	16:28	17-Aug-22	09:37	---	---	0.18	0.17	0.16
NH3+NH4 [as N mg/L]	18-Aug-22	19:31	19-Aug-22	14:07			0.19	0.17	0.17
NO2 [as N mg/L]	16-Aug-22	11:08	16-Aug-22	13:46	1	---	<0.003	<0.003	<0.003
NO3 [as N mg/L]	16-Aug-22	11:08	16-Aug-22	13:46	10	---	<0.006	<0.006	<0.006
NO2+NO3 [as N mg/L]	16-Aug-22	11:08	16-Aug-22	13:46			<0.006	<0.006	<0.006
Cl [mg/L]	17-Aug-22	14:11	18-Aug-22	16:18			62	66	68



SGS Canada Inc.
P.O. Box 4300 - 185 Concession St.
Lakefield - Ontario - K0L 2H0
Phone: 705-652-2000 FAX: 705-652-6365

Project : 12580314-01
LR Report : CA15142-AUG22

Analysis	1: Analysis Start Date	2: Analysis Start Time Completed	3: Analysis Date Completed	4: Analysis Time Completed	5: MAC	6: AO/OG	7: A342117 1hr	8: A342117 6hr	9: A342117 12hr
SO4 [mg/L]	17-Aug-22	14:37	18-Aug-22	16:18			300	370	400
DOC [mg/L]	15-Aug-22	12:00	16-Aug-22	08:37			2	2	2
Hardness [mg/L as CaCO3]	16-Aug-22	11:55	22-Aug-22	10:47			453	500	511
Al (tot) [mg/L]	16-Aug-22	11:55	17-Aug-22	14:03			0.016	0.004	0.001
Al (diss) [mg/L]	16-Aug-22	11:55	22-Aug-22	10:47	---	0.1	< 0.001	< 0.001	< 0.001
As (tot) [mg/L]	16-Aug-22	11:55	17-Aug-22	14:03			0.0006	0.0006	0.0005
As (diss) [mg/L]	16-Aug-22	11:55	22-Aug-22	10:47	0.025	---	0.0006	0.0004	0.0004
B (tot) [mg/L]	16-Aug-22	11:55	17-Aug-22	14:03			0.188	0.192	0.194
B (diss) [mg/L]	16-Aug-22	11:55	22-Aug-22	10:47	5	---	0.199	0.216	0.216
Ba (tot) [mg/L]	16-Aug-22	11:55	17-Aug-22	14:03			0.08335	0.08734	0.09029
Ba (diss) [mg/L]	16-Aug-22	11:55	22-Aug-22	10:47	1	---	0.09451	0.09889	0.09880
Be (tot) [mg/L]	16-Aug-22	11:55	17-Aug-22	14:03			< 0.000007	< 0.000007	< 0.000007
Be (diss) [mg/L]	16-Aug-22	11:55	22-Aug-22	10:47	---	---	< 0.000007	< 0.000007	0.000011
Co (tot) [mg/L]	16-Aug-22	11:55	17-Aug-22	14:03			0.000100	0.000084	0.000061
Co (diss) [mg/L]	16-Aug-22	11:55	22-Aug-22	10:47	---	---	0.000094	0.000091	0.000082
Ca (tot) [mg/L]	16-Aug-22	11:55	17-Aug-22	14:03			135	156	161
Ca (diss) [mg/L]	16-Aug-22	11:55	22-Aug-22	10:48	---	---	103	112	117
Cd (tot) [mg/L]	16-Aug-22	11:55	17-Aug-22	14:04			0.000016	0.000025	0.000021
Cd (diss) [mg/L]	16-Aug-22	11:55	22-Aug-22	10:48	0.005	---	0.000016	0.000017	0.000020
Cu (tot) [mg/L]	16-Aug-22	11:55	17-Aug-22	14:04			0.0006	0.0003	< 0.0002
Cu (diss) [mg/L]	16-Aug-22	11:55	22-Aug-22	10:48	---	1	< 0.0002	< 0.0002	< 0.0002
Cr (tot) [mg/L]	16-Aug-22	11:55	17-Aug-22	14:04			0.00040	0.00035	0.00010
Cr (diss) [mg/L]	16-Aug-22	11:55	22-Aug-22	10:48	0.05	---	0.00012	< 0.00008	< 0.00008
Fe (tot) [mg/L]	16-Aug-22	11:55	17-Aug-22	14:04			0.653	0.881	0.656
Fe (diss) [mg/L]	16-Aug-22	11:55	22-Aug-22	10:48			0.369	0.276	0.481
K (tot) [mg/L]	16-Aug-22	11:55	22-Sep-22	12:28	---	---	8.73	9.15	9.50
K (diss) [mg/L]	16-Aug-22	11:55	22-Sep-22	12:53	---	---	7.16	7.56	7.39
Mg (tot) [mg/L]	16-Aug-22	11:55	17-Aug-22	14:04			58.5	66.0	69.8
Mg (diss) [mg/L]	16-Aug-22	11:55	22-Aug-22	10:48			47.8	53.4	53.5
Mn (tot) [mg/L]	16-Aug-22	11:55	17-Aug-22	14:04			0.172	0.187	0.192
Mn (diss) [mg/L]	16-Aug-22	11:55	22-Aug-22	10:48			0.175	0.173	0.171
Mo (tot) [mg/L]	16-Aug-22	11:55	17-Aug-22	14:04			0.02270	0.03083	0.03435
Mo (diss) [mg/L]	16-Aug-22	11:55	22-Aug-22	10:48	---	---	0.02195	0.02931	0.03188
Ni (tot) [mg/L]	16-Aug-22	11:55	17-Aug-22	14:04			0.0007	0.0007	0.0006
Ni (diss) [mg/L]	16-Aug-22	11:55	22-Aug-22	10:48	---	---	0.0014	0.0013	0.0012
Na (tot) [mg/L]	16-Aug-22	11:55	17-Aug-22	14:04			60.4	64.3	67.6

OnLine LIMS

0003057687



SGS Canada Inc.
P.O. Box 4300 - 185 Concession St.
Lakefield - Ontario - KOL 2HO
Phone: 705-652-2000 FAX: 705-652-6365

Project : 12580314-01
LR Report : CA15142-AUG22

Analysis	1: Analysis Start Date	2: Analysis Start Time Completed	3: Analysis Date Completed	4: Analysis Time Completed	5: MAC	6: AO/OG	7: A342117 1hr	8: A342117 6hr	9: A342117 12hr
Na (diss) [mg/L]	16-Aug-22	11:55	22-Aug-22	10:48	20*	200	54.5	57.4	57.0
Pb (tot) [mg/L]	16-Aug-22	11:55	17-Aug-22	14:04			< 0.00009	< 0.00009	< 0.00009
Pb (diss) [mg/L]	16-Aug-22	11:55	22-Aug-22	10:48	0.01	---	< 0.00009	< 0.00009	< 0.00009
Ag (tot) [mg/L]	16-Aug-22	11:55	17-Aug-22	14:04			< 0.00005	< 0.00005	< 0.00005
Ag (diss) [mg/L]	16-Aug-22	11:55	22-Aug-22	10:49	---	---	< 0.00005	< 0.00005	< 0.00005
Sr (tot) [mg/L]	16-Aug-22	11:55	17-Aug-22	14:04			5.66	6.35	6.65
Sr (diss) [mg/L]	16-Aug-22	11:55	22-Aug-22	10:49	---	---	5.15	5.91	5.92
Tl (tot) [mg/L]	16-Aug-22	11:55	17-Aug-22	14:04			< 0.000005	< 0.000005	< 0.000005
Tl (diss) [mg/L]	16-Aug-22	11:55	22-Aug-22	10:49	---	---	< 0.000005	< 0.000005	< 0.000005
Sb (tot) [mg/L]	16-Aug-22	11:55	17-Aug-22	14:05			< 0.0009	< 0.0009	< 0.0009
Sb (diss) [mg/L]	16-Aug-22	11:55	22-Aug-22	10:49	0.006	---	< 0.0009	< 0.0009	< 0.0009
Se (tot) [mg/L]	16-Aug-22	11:55	17-Aug-22	14:05			< 0.00004	< 0.00004	< 0.00004
Se (diss) [mg/L]	16-Aug-22	11:55	22-Aug-22	10:49	0.01	---	0.00015	0.00020	0.00011
U (tot) [mg/L]	16-Aug-22	11:55	17-Aug-22	14:05			0.000166	0.000201	0.000204
U (diss) [mg/L]	16-Aug-22	11:55	22-Aug-22	10:49	0.02	---	0.000219	0.000227	0.000219
V (tot) [mg/L]	16-Aug-22	11:55	17-Aug-22	14:05			0.00021	0.00016	0.00014
V (diss) [mg/L]	16-Aug-22	11:55	22-Aug-22	10:49	---	---	0.00011	0.00008	0.00009
Zn (tot) [mg/L]	16-Aug-22	11:55	17-Aug-22	14:05			< 0.002	< 0.002	< 0.002
Zn (diss) [mg/L]	16-Aug-22	11:55	22-Aug-22	10:49	---	5	< 0.002	< 0.002	< 0.002
Cation Sum [meq/L]					---	---	14.37	16.23	16.93
Anion Sum [meq/L]					---	---	13.29	14.78	15.46
Anion-Cation Balance [% difference]					---	---	3.9	4.67	4.53
Ion Ratio					---	---	1.08	1.1	1.09
TDS (calculated) [mg/L]					---	---	775	879	923
Conductivity (calc) [uS/cm]					---	---	1383	1550	1619
Langelier's Index [@ 4° C]					---	---	0.7	0.81	0.85
Saturation pH [pHs @ 4° C]					---	---	7.44	7.39	7.38
Ryznar Stability Ind [no unit]	09-Sep-22	10:04	09-Sep-22	10:04	---	---	6.4	6.2	6.2

MAC - Maximum Acceptable Concentration
AO/OG - Aesthetic Objective / Operational Guideline
NR - Not reportable under applicable Provincial drinking water regulations as per client.

Total phosphorous includes all Ortho-phosphates as well as Organics and hydrolyzable Phosphorous.

Temperature of Sample upon Receipt: 13 degrees C
Cooling Agent Present: Yes
Custody Seal Present: Yes

Chain of Custody Number: 015249

Ryzner Stability Index calculated as per the following link with an assumed water temperature of 20 °C.

<https://www.lenntech.com/calculators/ryznar/index/ryznar.htm>

Revision 1 - total and dissolved potassium data included. Only dissolved hardness reported



Brad Moore Hon. B.Sc
Project Specialist,
Environment, Health & Safety



SGS Canada Inc.
P.O. Box 4300 - 185 Concession St.
Lakefield - Ontario - KOL 2H0
Phone: 705-652-2000 FAX: 705-652-6365

Project : 12580314-01

18-August-2022

GHD Limited - 735

Attn : Jason Gerald

347 Pido Rd., Unit #29
Peterborough, ON
K9J 6Z8, Canada

Phone: 705-749-3317
Fax: 705-749-9248

Date Rec. : 10 August 2022
LR Report: CA15143-AUG22
Reference: PO#:735-003858,
12580314-01, Jason
Gerald

Copy: 1

CERTIFICATE OF ANALYSIS

Final Report

Analysis	1: Date Extracted / Digested	3: Analysis Completed Date	6: RL	7: A342117 12hr
Sample Date & Time				09-Aug-22 19:07
1.1.8 PAHs (sVOC)	***	***	***	***
Acenaphthene [µg/L]	15-Aug-22	17-Aug-22	0.1	< 0.1
Acenaphthylene [µg/L]	15-Aug-22	17-Aug-22	0.1	< 0.1
Anthracene [µg/L]	15-Aug-22	17-Aug-22	0.1	< 0.1
Benzo(a)anthracene [µg/L]	15-Aug-22	17-Aug-22	0.1	< 0.1
Benzo(a)pyrene [µg/L]	15-Aug-22	17-Aug-22	0.01	< 0.01
Benzo(b+)fluoranthene [µg/L]	15-Aug-22	17-Aug-22	0.1	< 0.1
Benzo(ghi)perylene [µg/L]	15-Aug-22	17-Aug-22	0.2	< 0.2
Benzo(k)fluoranthene [µg/L]	15-Aug-22	17-Aug-22	0.1	< 0.1
Chrysene [µg/L]	15-Aug-22	17-Aug-22	0.1	< 0.1
Dibenzo(a,h)anthracene [µg/L]	15-Aug-22	17-Aug-22	0.1	< 0.1
Fluoranthene [µg/L]	15-Aug-22	17-Aug-22	0.1	< 0.1
Fluorene [µg/L]	15-Aug-22	17-Aug-22	0.1	< 0.1
Indeno(1,2,3-cd)pyrene [µg/L]	15-Aug-22	17-Aug-22	0.2	< 0.2
1-Methylnaphthalene [µg/L]	15-Aug-22	17-Aug-22	0.5	< 0.5
2-Methylnaphthalene [µg/L]	15-Aug-22	17-Aug-22	0.5	< 0.5
Methylnaphthalene, 2 [µg/L]	15-Aug-22	17-Aug-22	0.5	< 0.5
Naphthalene [µg/L]	15-Aug-22	17-Aug-22	0.5	< 0.5
Phenanthrene [µg/L]	15-Aug-22	17-Aug-22	0.1	< 0.1
Pyrene [µg/L]	15-Aug-22	17-Aug-22	0.1	< 0.1
Surrogates - SVOCs	***	***	***	***
Surr 2-Methylnaphtha [Surr Rec %]	15-Aug-22	17-Aug-22		86
Surr Fluoranthene-D1 [Surr Rec %]	15-Aug-22	17-Aug-22		97
Surr 2-Fluorobipheny [Surr Rec %]	15-Aug-22	17-Aug-22		82
Surr 4-Terphenyl-d14 [Surr Rec %]	15-Aug-22	17-Aug-22		92

Analysis	1: Date Extracted / Digested	3: Analysis Completed Date	6: RL	7: A342117 12hr
1.1.10 VOC	***	***	***	***
Acetone [µg/L]	13-Aug-22	15-Aug-22	30	< 30
Bromomethane [µg/L]	13-Aug-22	15-Aug-22	0.5	< 0.5
Carbon tetrachloride [µg/L]	13-Aug-22	15-Aug-22	0.2	< 0.2
Chlorobenzene [µg/L]	13-Aug-22	15-Aug-22	0.5	< 0.5
Chloroform [µg/L]	13-Aug-22	15-Aug-22	0.5	< 0.5
1,2-Dichlorobenzene [µg/L]	13-Aug-22	15-Aug-22	0.5	< 0.5
1,3-Dichlorobenzene [µg/L]	13-Aug-22	15-Aug-22	0.5	< 0.5
1,4-Dichlorobenzene [µg/L]	13-Aug-22	15-Aug-22	0.5	< 0.5
Dichlorodifluorometh [µg/L]	13-Aug-22	15-Aug-22	2	< 2
1,1-Dichloroethane [µg/L]	13-Aug-22	15-Aug-22	0.5	< 0.5
1,2-Dichloroethane [µg/L]	13-Aug-22	15-Aug-22	0.5	< 0.5
1,1-Dichloroethylene [µg/L]	13-Aug-22	15-Aug-22	0.5	< 0.5
trans-1,2-Dichloroet [µg/L]	13-Aug-22	15-Aug-22	0.5	< 0.5
cis-1,2-Dichloroethe [µg/L]	13-Aug-22	15-Aug-22	0.5	< 0.5
1,2-Dichloropropane [µg/L]	13-Aug-22	15-Aug-22	0.5	< 0.5
cis-1,3-Dichloroprop [µg/L]	13-Aug-22	15-Aug-22	0.5	< 0.5
trans-1,3-Dichloropr [µg/L]	13-Aug-22	15-Aug-22	0.5	< 0.5
1,3-dichloropropene [µg/L]	13-Aug-22	15-Aug-22	0.5	< 0.5
Ethylenedibromide [µg/L]	13-Aug-22	15-Aug-22	0.2	< 0.2
n-Hexane [µg/L]	13-Aug-22	15-Aug-22	1	< 1
MEK [µg/L]	13-Aug-22	15-Aug-22	20	< 20
MIBK [µg/L]	13-Aug-22	15-Aug-22	20	< 20
MtBE [µg/L]	13-Aug-22	15-Aug-22	2	< 2
Methylene Chloride [µg/L]	13-Aug-22	15-Aug-22	0.5	< 0.5
Styrene [µg/L]	13-Aug-22	15-Aug-22	0.5	< 0.5
Tetrachloroethylene [µg/L]	13-Aug-22	15-Aug-22	0.5	< 0.5
1,1,1,2-Tetrachloroe [µg/L]	13-Aug-22	15-Aug-22	0.5	< 0.5
1,1,2,2-Tetrachloroe [µg/L]	13-Aug-22	15-Aug-22	0.5	< 0.5
1,1,1-Trichloroethan [µg/L]	13-Aug-22	15-Aug-22	0.5	< 0.5
1,1,2-Trichloroethan [µg/L]	13-Aug-22	15-Aug-22	0.5	< 0.5
Trichloroethylene [µg/L]	13-Aug-22	15-Aug-22	0.5	< 0.5
Trichlorofluorometha [µg/L]	13-Aug-22	15-Aug-22	5	< 5
Vinyl Chloride [µg/L]	13-Aug-22	15-Aug-22	0.2	< 0.2
1.1.11 BTEX	***	***	***	***
Benzene [µg/L]	13-Aug-22	15-Aug-22	0.5	< 0.5
Ethylbenzene [µg/L]	13-Aug-22	15-Aug-22	0.5	< 0.5
Toluene [µg/L]	13-Aug-22	15-Aug-22	0.5	< 0.5
Xylene (total) [µg/L]	13-Aug-22	15-Aug-22	0.5	< 0.5
m-p-xylene [µg/L]	13-Aug-22	15-Aug-22	0.5	< 0.5
o-xylene [µg/L]	13-Aug-22	15-Aug-22	0.5	< 0.5
1.1.9 THMs (VOC)	***	***	***	***

Analysis	1: Date Extracted / Digested	3: Analysis Completed Date	6: RL	7: A342117 12hr
Bromodichloromethane [µg/L]	13-Aug-22	15-Aug-22	0.5	< 0.5
Bromoform [µg/L]	13-Aug-22	15-Aug-22	0.5	< 0.5
Dibromochloromethane [µg/L]	13-Aug-22	15-Aug-22	0.5	< 0.5
Surrogates (VOCs)	***	***	***	***
Surr 1,2-Dichloroeth [Surr Rec %]	13-Aug-22	15-Aug-22		101
Surr 2-Bromo-1-Chlor [Surr Rec %]	13-Aug-22	15-Aug-22		85
Surr 4-Bromofluorobe [Surr Rec %]	13-Aug-22	15-Aug-22		90
1.1.6 PHCs	***	***	***	***
F1 (C6-C10) [µg/L]	12-Aug-22	15-Aug-22	25	< 25
F1-BTEX (C6-C10) [µg/L]	12-Aug-22	15-Aug-22		< 25
F2 (C10-C16) [µg/L]	15-Aug-22	18-Aug-22	100	< 100
F3 (C16-C34) [µg/L]	15-Aug-22	18-Aug-22	200	< 200
F4 (C34-C50) [µg/L]	15-Aug-22	18-Aug-22	200	< 200
Baseline at nC50 [Yes / No]	15-Aug-22	18-Aug-22		YES

CCME Method Compliance: Analyses were conducted using analytical procedures that comply with the Reference Method for the CWS for Petroleum Hydrocarbons in Soil and have been validated for use at the SGS Laboratory, Lakefield, ON site.

Quality Compliance: Instrument performance / calibration quality criteria were met and extraction and analysis limits for holding times were met.

nC6 and nC10 response factors within 30% of response factor for toluene: YES

nC10, nC16 and nC34 response factors within 10% of the average response for the three compounds: YES

C50 response factors within 70% of nC10 + nC16 + nC34 average: YES

Linearity is within 15%: YES

Benzo(b)fluoranthene results for comparison to the standard are reported as benzo(b+j)fluoranthene. Benzo(b)fluoranthene and benzo(j)fluoranthene co-elute and cannot be reported individually by the analytical method used.

Temperature of Sample upon Receipt: 13 degrees C

Cooling Agent Present: Yes

Custody Seal Present: Yes

Chain of Custody Number: 024624

Methylene Chloride LCS; Recovery is outside control limits; the overall quality control for this analysis has been assessed and was determined to be acceptable.

Acetone matrix spike; recovery for this parameter is outside control limits; the overall quality control for this analysis has been assessed and was determined to be acceptable.

F3(C16-C34) Dup RPD is outside control limits. The average of the two duplicates is less than five times the RL, therefore greater uncertainty is expected.




SGS Canada Inc.

P.O. Box 4300 - 185 Concession St.
Lakefield - Ontario - K0L 2H0
Phone: 705-652-2000 FAX: 705-652-6365

Project : 12580314-01

LR Report : CA15143-AUG22

*Jill Campbell, B.Sc., GISAS
Project Specialist,
Environment, Health & Safety*



FINAL REPORT

CA14875-SEP22 R1

12580314-01

Prepared for

GHD Limited - 735

First Page

CLIENT DETAILS

LABORATORY DETAILS

Client	GHD Limited - 735	Project Specialist	Brad Moore Hon. B.Sc
Address	347 Pido Rd., Unit #29 Peterborough, ON K9J 6Z8. Canada	Laboratory	SGS Canada Inc.
Contact	Jason Geraldi	Address	185 Concession St., Lakefield ON, K0L 2H0
Telephone	705-749-3317	Telephone	705-652-2143
Facsimile	705-749-9248	Facsimile	705-652-6365
Email	Jason.Geraldi@ghd.com	Email	brad.moore@sgs.com
Project	12580314-01	SGS Reference	CA14875-SEP22
Order Number		Received	09/21/2022
Samples	Ground Water (3)	Approved	09/27/2022
		Report Number	CA14875-SEP22 R1
		Date Reported	09/27/2022

COMMENTS

MAC - Maximum Acceptable Concentration
 AO/OG - Aesthetic Objective / Operational Guideline
 NR - Not reportable under applicable Provincial drinking water regulations as per client.

Temperature of Sample upon Receipt: 13 degrees C
 Cooling Agent Present: Yes
 Custody Seal Present: Yes

Chain of Custody Number: 015249

SIGNATORIES

Brad Moore Hon. B.Sc




TABLE OF CONTENTS

First Page.....	1
Index.....	2
Results.....	3
Exceedance Summary.....	4
QC Summary.....	5-6
Legend.....	7
Annexes.....	8



FINAL REPORT

CA14875-SEP22 R1

Client: GHD Limited - 735

Project: 12580314-01

Project Manager: Jason Gerald

Samplers: Jason Gerald

MATRIX: WATER

Sample Number	7	8	9
Sample Name	A342117 1HR	A342117 6HR	A342117 12HR
Sample Matrix	Ground Water	Ground Water	Ground Water
Sample Date	09/08/2022	09/08/2022	09/08/2022

L1 = ODWS_AO_OG / WATER / - - Table 4 - Drinking Water - Reg O.169_03

L2 = ODWS_MAC / WATER / - - Table 1,2 and 3 - Drinking Water - Reg O.169_03

Parameter	Units	RL	L1	L2	Result	Result	Result
General Chemistry							
Hydrogen Sulphide	mg/L	0.02	0.05		< 0.02	< 0.02	< 0.02
Metals and Inorganics							
Sulphide	mg/L	0.02			< 0.02	< 0.02	< 0.02
Other (ORP)							
Mercury (dissolved)	mg/L	0.00001		0.001	< 0.00001	< 0.00001	< 0.00001

EXCEEDANCE SUMMARY

No exceedances are present above the regulatory limit(s) indicated



FINAL REPORT

CA14875-SEP22 R1

QC SUMMARY

Mercury by CVAAS

Method: EPA 7471A/SM 3112B | Internal ref.: ME-CA-IENVISPE-LAK-AN-004

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Mercury (dissolved)	EHG0048-SEP22	mg/L	0.00001	< 0.00001	ND	20	101	80	120	121	70	130

Sulphide by SFA

Method: SM 4500 | Internal ref.: ME-CA-IENVISFA-LAK-AN-008

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Sulphide	SKA0224-SEP22	mg/L	0.02	<0.02	ND	20	100	80	120	NA	75	125

QC SUMMARY

Method Blank: a blank matrix that is carried through the entire analytical procedure. Used to assess laboratory contamination.

Duplicate: Paired analysis of a separate portion of the same sample that is carried through the entire analytical procedure. Used to evaluate measurement precision.

LCS/Spike Blank: Laboratory control sample or spike blank refer to a blank matrix to which a known amount of analyte has been added. Used to evaluate analyte recovery and laboratory accuracy without sample matrix effects.

Matrix Spike: A sample to which a known amount of the analyte of interest has been added. Used to evaluate laboratory accuracy with sample matrix effects.

Reference Material: a material or substance matrix matched to the samples that contains a known amount of the analyte of interest. A reference material may be used in place of a matrix spike.

RL: Reporting limit

RPD: Relative percent difference

AC: Acceptance criteria

Multielement Scan Qualifier: as the number of analytes in a scan increases, so does the chance of a limit exceedance by random chance as opposed to a real method problem. Thus, in multielement scans, for the LCS and matrix spike, up to 10% of the analytes may exceed the quoted limits by up to 10% absolute and the spike is considered acceptable.

Duplicate Qualifier: for duplicates as the measured result approaches the RL, the uncertainty associated with the value increases dramatically, thus duplicate acceptance limits apply only where the average of the two duplicates is greater than five times the RL.

Matrix Spike Qualifier: for matrix spikes, as the concentration of the native analyte increases, the uncertainty of the matrix spike recovery increases. Thus, the matrix spike acceptance limits apply only when the concentration of the matrix spike is greater than or equal to the concentration of the native analyte.

LEGEND

FOOTNOTES

NSS Insufficient sample for analysis.
RL Reporting Limit.
 ↑ Reporting limit raised.
 ↓ Reporting limit lowered.
NA The sample was not analysed for this analyte
ND Non Detect

Results relate only to the sample tested.

Data reported represent the sample as submitted to SGS. Solid samples expressed on a dry weight basis.

"Temperature Upon Receipt" is representative of the whole shipment and may not reflect the temperature of individual samples.

Analysis conducted on samples submitted pursuant to or as part of Reg. 153/04, are in accordance to the "Protocol for Analytical Methods Used in the Assessment of Properties under Part XV.1 of the Environmental Protection Act and Excess Soil Quality" published by the Ministry and dated March 9, 2004 as amended.

SGS provides criteria information (such as regulatory or guideline limits and summary of limit exceedances) as a service. Every attempt is made to ensure the criteria information in this report is accurate and current, however, it is not guaranteed. Comparison to the most current criteria is the responsibility of the client and SGS assumes no responsibility for the accuracy of the criteria levels indicated.

SGS Canada Inc. statement of conformity decision rule does not consider uncertainty when analytical results are compared to a specified standard or regulation.

This document is issued, on the Client's behalf, by the Company under its General Conditions of Service available on request and accessible at http://www.sgs.com/terms_and_conditions.htm.

The Client's attention is drawn to the limitation of liability, indemnification and jurisdiction issues defined therein. Any other holder of this document is advised that information contained hereon reflects the Company's findings at the time of its intervention only and within the limits of Client's instructions, if any. The Company's sole responsibility is to its Client and this document does not exonerate parties to a transaction from exercising all their rights and obligations under the transaction documents. Reproduction of this analytical report in full or in part is prohibited.

This report supersedes all previous versions.

-- End of Analytical Report --

Appendix G

MacLellan Water Treatment Recommendations



Telephone: (613) 386-0550
Toll-Free: 1-800-200-0865
Fax: 613-386-9889
Website: www.mwater.ca
Email: info@mwater.ca

Address: 388 Millhaven Road
P.O. Box 392
Odessa, ON K0H 2H0

Report for GHD – Ottawa Warehouse Project

September 21, 2022

Introduction

This report has been prepared based on water quality information that was provided to MacLellan Water. The principal purpose of this report is to make recommendations for a water treatment system for the warehouse facility. Maximum use is estimated at 10 000 L per day although 5000 L per day is expected to be a more typical use.

Water Quality

Several sets of water quality information were provided, corresponding to samples collected at different times during pumping of the well. Although there was some variation among the samples, the results were broadly similar. We have used the last set of samples when discussing specific numbers in this report. The following parameters returned noteworthy values:

Turbidity

Turbidity is a measure of the “cloudiness” of the water. Turbidity is a concern because the materials that cause turbidity can interfere with disinfection efforts. The operational limit for turbidity is 1 NTU. The turbidity of this water was measured at 4.21 NTU.

Hardness

Water is considered hard when the hardness exceeds 100 mg/L. This water was measured with a hardness of 689 mg/L.

Iron

The aesthetic limit for iron is 0.3 mg/L. Above this limit, it can cause problems with colour, staining, and taste in the water. The concentration of iron in this water was measured at 0.481 mg/L. A further 0.175 mg/L of iron was present in a form where it is bound up with organic matter.

Manganese

The aesthetic limit for manganese is 0.05 mg/L. Above this limit, it can cause problems with colour, staining, and taste similar to those caused by iron. The concentration of manganese in this water was measured at 0.171 mg/L.

Sodium

People consuming water with a sodium content above 20 mg/L are encouraged to inform their physician. This is so that the physician can take the sodium content of the drinking water into consideration should it ever become necessary to prescribe a low sodium diet for medical reasons.

Above 200 mg/L sodium has a negative aesthetic effect in that it imparts a disagreeable, salty tang to the water.

The concentration of sodium in this water was measured at 67.6 mg/L.

Langelier's Index

The Langelier's Index (LI) is a calculation that assesses the "character" of the water. Water with an LI below -0.5 is aggressive and will tend to corrode metal pipes, fixtures, and appliances. Water with an LI from -0.5 to +0.5 is neutral. Water with an LI of more than +0.5 will tend to form hard water scale at an appreciably accelerated rate.

The LI is temperature dependent. The LI of this water was calculated at +0.85 at 4°C. It will actually be even higher for water that has warmed up to room temperature while sitting inside the building.

Recommendations

The following items are presented for your consideration. It is assumed that they would be carried out at the appropriate time in the construction of the facility. MacLellan Water would be happy to provide price estimates to carry out the recommended work.

1. A submersible pump should be installed in the well and connected to the building with pipe and wire that are run inside protective conduit. An appropriate pressure system will need to be installed inside the building.
2. A filtration system for iron should be installed. There are a number of options for this, but the best would be a manganese greensand filter with chlorine regeneration. The filter will also remove a certain amount of manganese.
3. An activated carbon filter should be installed to both remove residual chlorine and organically-complexed metals.
4. A water softener should be used to soften the water. This will improve the aesthetics of the water. More importantly, it will protect the water disinfection system and water-using appliances (hot water tanks, etc.) in the facility from fouling due to hard water scale.

A twin alternating softener system will be used. With this system, one tank remains in service until its capacity is exhausted. The second tank then takes over softening duties while the first tank regenerates. This ensures an uninterrupted supply of softened water and allows the use of smaller, less expensive softening equipment than a single tank model.

5. Disinfection of the water will be provided with ultra violet (UV) disinfection. Depending on preferences for redundancy, this may involve one or two units. Depending on preferences, these may be fairly straight forward units or units equipped with sensors and automatic fail-safe shutoffs.

Regardless, the unit(s) will be sized to allow adequate flow to the facility and will be equipped with turbidity-reducing cartridge-style prefilters to screen out particles that bacteria might shelter behind while passing through the UV light.

6. The concentration of sodium in the water is already slightly high. The use of a water softener will increase the sodium content of the treated water by about 300 mg/L to a total of about 360 mg/L.

One or more point of use reverse osmosis (RO) units will be installed to remove sodium at locations (like lunch rooms) where people will actually consume the water. This is done in preference to treating all the water in the facility because the output of RO units is slow. The RO units will be equipped with small storage tanks so that pre-treated water will be ready on demand.

7. MacLellan Water will arrange a servicing schedule to ensure that all the equipment remains in proper working order.

Conclusion

We hope that this report contains all the information you require. Please do not hesitate to contact me with any questions. We would be happy to provide price estimates for this work once a few additional details have been established.


Sincerely,

William Vander Wilp
MacLellan Water Treatment and Pumps
1-800-200-0865 x 24

Appendix H

Observation Well Hydrographs

OBSERVATION WELL HYDROGRAPHS
August 3-18, 2022



Observation Well Water Levels

Drilled Water Well
MECP Well ID: A342117
Static Level = 7.96 mbtp (7.31 mbgs)

Note: m = metres; mbtp = metres below top of pipe; mbgs = metres below ground surface

DATE: SEPTEMBER 2022

LOCATION: 301 Somme Street, Ottawa, ON

JOB NUMBER: 12580314-01

DRAWING NUMBER: H-1



347 PIDO ROAD, UNIT 29
PETERBOROUGH, ON K9J 6X7
www.ghd.com

Appendix I

Storm Sewer Use Certificate of Analysis



SGS Canada Inc.

P.O. Box 4300 - 185 Concession St.
Lakefield - Ontario - K0L 2H0
Phone: 705-652-2000 FAX: 705-652-6365

Project : 12580314-01

18-August-2022

GHD Limited - 735

Attn : Jason Gerald

347 Pido Rd., Unit #29
Peterborough, ON
K9J 6Z8, Canada

Phone: 705-749-3317
Fax:705-749-9248

Date Rec. : 10 August 2022
LR Report: CA15141-AUG22
Reference: PO#:735-003858,
12580314-01, Jason
Gerald

Copy: #1

CERTIFICATE OF ANALYSIS
Final Report

Table with 7 columns: Analysis, 1: Analysis Start Date, 3: Analysis Completed Date, 5: Ottawa Storm By-law Limit, 6: RL, 7: Piezo. Rows include various chemical and physical parameters like Ecoli, pH, BOD5, TSS, and heavy metals.

SGS Canada Inc.

P.O. Box 4300 - 185 Concession St.
 Lakefield - Ontario - KOL 2H0
 Phone: 705-652-2000 FAX: 705-652-6365

Project : 12580314-01

LR Report : CA15141-AUG22

Analysis	1: Analysis Start Date	3: Analysis Completed Date	5: Ottawa Storm By-law Limit	6: RL	7: Piezo
Benzo(b+j)fluoranthene [mg/L]	16-Aug-22	17-Aug-22	---	0.0001	0.0002
Benzo[e]pyrene [mg/L]	16-Aug-22	17-Aug-22	---	0.0001	0.0001
Benzo(ghi)perylene [mg/L]	16-Aug-22	17-Aug-22	---	0.0002	0.0003
Benzo(k)fluoranthene [mg/L]	16-Aug-22	17-Aug-22	---	0.0001	< 0.0001
Chrysene [mg/L]	16-Aug-22	17-Aug-22	---	0.0001	< 0.0001
Dibenzo(a,h)anthracene [mg/L]	16-Aug-22	17-Aug-22	---	0.0001	< 0.0001
Dibenzo(a,i)pyrene [mg/L]	16-Aug-22	17-Aug-22	---	0.0001	< 0.0001
Dibenzo(a,j)acridine [mg/L]	16-Aug-22	17-Aug-22	---	0.0001	< 0.0001
Fluoranthene [mg/L]	16-Aug-22	17-Aug-22	---	0.0001	0.0002
Perylene [mg/L]	16-Aug-22	17-Aug-22	---	0.0005	< 0.0005
Phenanthrene [mg/L]	16-Aug-22	17-Aug-22	---	0.0001	0.0001
Pyrene [mg/L]	16-Aug-22	17-Aug-22	---	0.0001	0.0002
Naphthalene [mg/L]	16-Aug-22	17-Aug-22	0.0064	0.0005	< 0.0005
Hexachlorobenzene [mg/L]	16-Aug-22	17-Aug-22	0.00004	0.0001	< 0.0001
Benzene [mg/L]	16-Aug-22	17-Aug-22	0.002	0.0005	< 0.0005
Chloroform [mg/L]	16-Aug-22	17-Aug-22	0.002	0.0005	< 0.0005
1,2-Dichlorobenzene [mg/L]	16-Aug-22	17-Aug-22	0.0056	0.0005	< 0.0005
1,4-Dichlorobenzene [mg/L]	16-Aug-22	17-Aug-22	0.0068	0.0005	< 0.0005
cis-1,2-Dichloroethane [mg/L]	16-Aug-22	17-Aug-22	0.0056	0.0005	< 0.0005
trans-1,3-Dichloropropane [mg/L]	16-Aug-22	17-Aug-22	0.0056	0.0005	< 0.0005
Ethylbenzene [mg/L]	16-Aug-22	17-Aug-22	0.002	0.0005	< 0.0005
Methylene Chloride [mg/L]	16-Aug-22	17-Aug-22	0.0052	0.0005	< 0.0005
1,1,2,2-Tetrachloroethane [mg/L]	16-Aug-22	17-Aug-22	0.017	0.0005	< 0.0005
Tetrachloroethylene [mg/L]	16-Aug-22	17-Aug-22	0.0044	0.0005	< 0.0005
Toluene [mg/L]	16-Aug-22	17-Aug-22	0.002	0.0005	< 0.0005
Trichloroethylene [mg/L]	16-Aug-22	17-Aug-22	0.0076	0.0005	< 0.0005
Xylene (total) [mg/L]	16-Aug-22	17-Aug-22	0.0044	0.0005	< 0.0005
m-p-xylene [mg/L]	16-Aug-22	17-Aug-22	---	0.0005	< 0.0005
o-xylene [mg/L]	16-Aug-22	17-Aug-22	---	0.0005	< 0.0005
Nonylphenol [mg/L]	15-Aug-22	17-Aug-22	0.001	0.001	< 0.001
Nonylphenol Ethoxylate [mg/L]	15-Aug-22	17-Aug-22	0.01	0.01	< 0.01
Nonylphenol diethoxy [mg/L]	15-Aug-22	17-Aug-22	---	0.01	< 0.01
Nonylphenol monoethoxy [mg/L]	15-Aug-22	17-Aug-22	---	0.01	< 0.01

RL - SGS Reporting Limit

Nonyl phenol Ethoxylate is the sum of nonyl phenol monoethoxylate and nonyl phenol diethoxylate.

Temperature of Sample upon Receipt: 10 degrees C
 Cooling Agent Present: Yes
 Custody Seal Present: Yes

Chain of Custody Number: 015194



SGS Canada Inc.

P.O. Box 4300 - 185 Concession St.
Lakefield - Ontario - K0L 2H0
Phone: 705-652-2000 FAX: 705-652-6365

Ottawa Storm Bylaw 2003-514

Project : 12580314-01

LR Report : CA15141-AUG22

*Jill Campbell, B.Sc., GISAS
Project Specialist,
Environment, Health & Safety*



ghd.com

→ **The Power of Commitment**