

Legend

- 99.99
99.99
2.0%
FFE=100.00
USF=97.00
E.F.
3:1
DIRECTION OF OVERLAND FLOW
PROPOSED VALVE BOX
PROPOSED VALVE CHAMBER
PROPOSED FIRE HYDRANT
PROPOSED SANITARY SEWER MANHOLE
PROPOSED STORM SEWER MANHOLE
PROPOSED CATCHBASIN
PROPOSED DEPRESSED CURB LOCATION
PROPOSED BARRIER CURB
PROPOSED HEAVY DUTY ASPHALT
OVERLAND SPILL LOCATION
TWS LOCATION AS PER CITY STD

Notes

- PAVEMENT STRUCTURE - LIGHT VEHICLE PARKING
40mm SUPERPAVE 12.5 FC2 ASPHALTIC CONCRETE
50mm SUPERPAVE 19.0 ASPHALTIC CONCRETE
150 OPSS GRANULAR 'A' BASE
300 OPSS GRANULAR 'B' TYPE II
- PAVEMENT STRUCTURE - ACCESS LANES AND HEAVY TRUCK
40mm SUPERPAVE 12.5 FC2 ASPHALTIC CONCRETE
50mm SUPERPAVE 19.0 ASPHALTIC CONCRETE
150 OPSS GRANULAR 'A' BASE
400 OPSS GRANULAR 'B' TYPE II

2	REVISED AS PER CITY COMMENTS	MJS	PM	25.04.22	
1	REVISED AS PER CITY COMMENTS	MJS	PM	24.09.04	
0	ISSUED FOR SPA	MJS	PM	23.06.01	
Revision		By	Appd.	YY.MM.DD	
File Name: 160401697 DB.dwg		MJS	DT	23.05.01	
		Dwn.	Chkd.	Dsgn.	YY.MM.DD

Permit-Seal

Client/Project

BRIGIL HOMES

1299 RICHMOND ROAD
MIXED USE TOWER DEVELOPMENT
OTTAWA, ON, CANADA

Title

GRADING PLAN

Project No.	Scale	0 2.5 7.5 12.5m
160401697	1:250	
Drawing No.	Sheet	Revision

GP-1

4 of 7

2

PLAN # 19038

