


### Table 1 - Existing Tree Inventory

Tag #	Species	Common Name	Diameter at Breast Height (DBH) cm or range (cm)	Drip Line Radius (cm)	Multistem Tree	Overall Condition	Recommended Action	Notes	Ownership
1	Acer negundo	Manitoba Maple	10	480		Good	Remove - Due to grading and infrastructure improvement Remove - Due to grading	Hard lean to south	Private on adjoining site  Private on adjoining site
2	Ulmus americana	American Elm	22	280		Fair	and infrastructure improvement	Lean to south	
3	Acer platanoides	Norway Maple	11	250		Poor	Remove - Due to grading and infrastructure improvement  Remove - Due to grading		Private on site  Private on site
4	Acer platanoides	Norway Maple	11	200		Good	and infrastructure improvement Remove - Due to grading		Private on adjoining site
5	Malus spp.	Apple spp.	11	200		Good	and infrastructure improvement		B. A. B. C.
6	Juglans nigra	Black Walnut	26	500		Good	Remove - Due to grading and infrastructure improvement		Private on adjoining site  Private on site
7	Acer negundo	Manitoba Maple	11	350		Fair	Remove - Due to grading and infrastructure improvement		
8	Ulmus americana	American Elm	25	350		Poor	Remove - Due to grading and infrastructure improvement		Private on site
9	Acer platanoides	Norway Maple	13	490		Very Good	Remove - Due to building construction and excavation		Private on site  Private on site
10	Acer negundo	Manitoba Maple	11	370		Good	Remove - Due to building construction and excavation		Private on site
11	Acer negundo	Manitoba Maple	37	850		Very Good	Remove - Due to grading and infrastructure improvement  Remove - Due to grading		Private on site
12	Acer platanoides	Norway Maple	17	360		Very Good	and infrastructure improvement		Private on site
13	Acer negundo	Manitoba Maple	12	280		Poor	Remove - Due to grading and infrastructure improvement		
14	Ulmus americana	American Elm	15	50		Poor	Remove - Due to building construction and excavation		Private on site
15	Acer negundo	Manitoba Maple	19	440		Poor	Remove - Due to building construction and excavation		Private on site
16	Unknown	Unknown	19	240		Dead	Remove - Due to building construction and excavation		Private on site
							Remove - Due to grading and infrastructure improvement		City Tree
17	Acer platanoides	Norway Maple	19	580		Very Good	Remove - Due to grading and infrastructure		City Tree
18	Rhamnus cathartica	Common Buckthorn	10	730		Good	improvement  Remove - Due to building construction and excavation	Hard lean north	Private on site
19	Acer negundo	Manitoba Maple	25	1220		Very Good	Remove - Due to grading and infrastructure		Private on site
20	Acer negundo	Manitoba Maple	35	640		Good	improvement  Remove - Due to grading and infrastructure		City Tree
21	Tilia americana	Basswood	11	520	Yes	Poor	improvement  Remove - Due to grading		City Tree
22	Tilia americana	Basswood	12	540	Yes	Good	and infrastructure improvement  Remove - Due to grading		City Tree
23	Acer platanoides	Norway Maple	15	360		Very Good	and infrastructure improvement  Remove - Due to grading		City Tree
24	Acer negundo	Manitoba Maple	35	1090	Yes	Poor	and infrastructure improvement		City Tree
25	Ulmus americana	American Elm	20	470		Good	Remove - Due to grading and infrastructure improvement		-
26	Ulmus americana	American Elm	16	440		Good	Remove - Due to grading and infrastructure improvement		City Tree
27	Juglans nigra	Black Walnut	20	1040		Good	Remove - Due to grading and infrastructure improvement		City Tree
28	Tilia americana	Basswood	14	0		Dead	Remove - Due to grading and infrastructure improvement		City Tree
29	Acer negundo		18	710		Good	Remove - Due to grading and infrastructure improvement		City Tree
		Manitoba Maple					Remove - Due to grading and infrastructure		City Tree
30	Acer negundo	Manitoba Maple	19	350		Very Good	improvement  Remove - Due to grading and infrastructure		City Tree
31	Acer negundo	Manitoba Maple	15	410		Good	improvement  Remove - Due to grading and infrastructure		City Tree
32	Acer negundo	Manitoba Maple	11	0		Dead	improvement  Remove - Due to grading and infrastructure		City Tree
33	Rhamnus cathartica	Common Buckthorn	11	810		Very Good	improvement  Remove - Due to grading and infrastructure		City Tree
34	Tilia americana	Basswood	28	430		Poor	improvement  Remove - Due to grading		City Tree
35	Acer negundo	Manitoba Maple	12	0		Dead	and infrastructure improvement  Remove - Due to grading		City Tree
36	Acer platanoides	Norway Maple	11	30		Very Good	and infrastructure improvement Remove - Due to grading		City Tree
37	Acer negundo	Manitoba Maple	27	810	Yes	Poor	and infrastructure improvement  Remove - Due to grading		City Tree
38	Acer negundo	Manitoba Maple	14	450	Yes	Very Good	and infrastructure improvement  Remove - Due to grading		City Tree
39	Quercus macrocarpa	Burr Oak	22	220	Yes	Very Good	and infrastructure improvement		-



TREE PROTECTION SPECIFICATION

TO BE IMPLEMENTED FOR RETAINED TREES, BOTH ON SITE AND ON ADJACENT SITES, PRIOR TO ANY TREE REMOVAL OR SITE WORKS AND MAINTAINED FOR THE DURATION OF WORK ACTIVITIES ON SITE.

DATE: MARCH 2021 DRAWING NO.: 1 of 1

**ANDREW MCCREIGHT** 

MANAGER, DEVELOPMENT REVIEW CENTRAL PLANNING, DEVELOPMENT & BUILDING SERVICES **DEVELOPMENT DEPARTMENT, CITY OF OTTAWA** 

> APPROVED By Andrew McCreight at 11:51 am, Oct 30, 2025

# CHURCHILL PROPERTIES INC.

5-145 SELECT AVE., TORONTO, ONTARIO

COPYRIGHT

This drawing has been prepared solely for the intended use, thus any reproduction or distribution for any purpose other than authorized by Arcadis is forbidden. Written dimensions shall have precedence over scaled dimensions. Contractors shall verify and be responsible for all dimensions and conditions on the job, and Arcadis shall be informed of any variations from the dimensions and conditions shown on the drawing. Shop drawings shall be submitted to Arcadis for general conformance before proceeding with fabrication.

Arcadis Professional Services (Canada) Inc. formerly IBI Group Professional Services (Canada) Inc.

ISSUES							
No.	DESCRIPTION	DATE					
2	ISSUED FOR ZBA & SPA REVIEW	2023-03-24					
3	ISSUED FOR ZBA & SPA REVIEW	2024-08-12					
4	ISSUED FOR ZBA & SPA REVIEW	2024-10-11					
5	ISSUED FOR SPA	2025-08-08					





FILE NO. D07-12-22-0152 PLAN NO. 18881



410 Albert Street - Suite 101 Waterloo ON N2L 3V3 Canada tel 519 585 2255 www.arcadis.com

PROJECT

424 Churchill Ave

CITY OF OTTAWA

PROJECT NO: 139413	
DRAWN BY: E.L	CHECKED BY: M.P.
PROJECT MGR:	APPROVED BY:

SHEET TITLE

TREE PRESERVATION PLAN

SHEET NUMBER TPP-2

6

<b>ANTING</b>	SCHEDULE	

				CALIPER		CONDITION	IVITIN. U.C.	
KEY	QTY.	BOTANICAL NAME	COMMON NAME	(mm)	SIZE (cm)	FORM	SPACING (m)	SPECIES %
DECIDUO	OUS TREE	:S						
Ac	3	Amelanchier canadensis	Serviceberry	50		W.B.	10	15%
ArR	3	Acer rubrum 'Red Rocket'	Red Rocket Maple	50		W.B.	10	15%
Co	2	Celtis occidentalis	Hackberry	50		W.B.	10	10%
Pv	2	Prunus virginiana	Chokecherry	50		W.B.	10	10%
Qp	2	Quercus palustris	Pin Oak	50		W.B.	10	10%
QpG	2	Quercus palustris 'Green Pillar'	Green Pillar Oak	50		W.B.	10	10%
Srl	4	Syringa reticula 'Ivory Silk'	Ivory Silk Tree Lilac	50		W.B.	10	20%
TcC	2	Tilia cordata 'Corinthian'	Corinthian Linden	50		W.B.	10	10%
TOTAL:	20						·	100%
OLIDILD!	_							

CALIDER

CONDITION/ MIN O C

2HKOR2	)						
BmP	44	Buxus microphylla 'Pincushion'	Pincushion Boxwood	50	3 Gal.	1	28%
CoS	10	Chamaecyparis obtusa 'Spiralis'	Spiral Hinoki cypress	50	3 Gal.	1	6%
HpF	39	Hydrangea paniculata 'Fire Light Tidbit'	Fire Light Tidbit Hydrangea	50	3 Gal.	1	25%
lv	3	llex verticillata	Winterberry	50	3 Gal.	1	2%
JhB	4	Juniperus horizontalis 'Blue Chip'	Creeping Juniper	50	3 Gal.	1	3%
JhP	16	Juniperus horizontalis 'Plumosa Compacta	Compact Andorra Juniper	50	3 Gal.	1	10%
Js	14	Juniperus sabina	Juniperus sabina	50	3 Gal.	1	9%
SnS	14	Spiraea nipponica 'Snowmound'	Snowmound Spirea	50	3 Gal.	1	9%
Tc	11	Taxus canadensis	Canada Yew	50	3 Gal.	1	7%
TOTAL:	155						100%

CeA		28
TOTA	۱L:	28

**GRASSES** Carex elata 'Aurea' 0.3 Bowles Golden Sedge 100%



**ANDREW MCCREIGHT** MANAGER, DEVELOPMENT REVIEW CENTRAL PLANNING, DEVELOPMENT & BUILDING SERVICES **DEVELOPMENT DEPARTMENT, CITY OF OTTAWA** 

> **APPROVED** By Andrew McCreight at 11:51 am, Oct 30, 2025

#### LANDSCAPE NOTES:

- 1. ALL WORK TO BE CARRIED OUT IN ACCORDANCE WITH BY-LAWS AND CODES HAVING JURISDICTION OVER SITE
- 2. COMPLETE ALL WORK TO THE SATISFACTION OF THE LANDSCAPE ARCHITECT. 3. REPORT ANY CHANGES, DISCREPANCIES OR SUBSTITUTIONS TO THE LANDSCAPE ARCHITECT FOR REVIEW. OBTAIN
- APPROVAL FROM THE
- LANDSCAPE ARCHITECT BEFORE PROCEEDING. 4. IT IS THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE EXISTING SERVICE LOCATIONS.
- 5. EXACT LOCATIONS OF PLANT MATERIAL WILL BE DETERMINED BY PLACEMENT OF SITE SERVICES SUCH AS HYDRO UTILITIES ROOF RAIN WATER LEADERS, DRIVEWAYS, LIGHT STANDARDS, ETC.
- 6. ALL PLANT MATERIAL LOCATIONS TO BE STAKED OR MARKED OUT AND APPROVED BY LANDSCAPE ARCHITECT
- SUPPLY ALL PLANT MATERIAL IN ACCORDANCE WITH THE CANADIAN STANDARDS FOR NURSERY STOCK (8th Ed.).
- 8. INSTALL PLANT MATERIAL ACCORDING TO DETAILS SHOWN. 9. DISTURBED SOIL AREAS AROUND TREES AND SHRUBS ARE TO BE COVERED WITH SHREDDED CONIFER BARK
- 'CANADA RED' OR 'GRO-BARK' SPM MULCH, OR APPROVED EQUIVALENT. ALTERNATIVE MULCHES MUST BE APPROVED BY THE
- LANDSCAPE ARCHITECT. 10. CONTRACTOR TO UTILIZE LAYOUT DIMENSIONS WHERE PROVIDED.
- 11. PROVIDE PLANTING BED AREA AS NOTED ON THE DRAWING OR TO ACCOMMODATE MATURE SIZE OF PLANT
- 12. ALL SUPPORT SYSTEMS MUST BE REMOVED BY THE CONTRACTOR AT TIME OF FINAL ACCEPTANCE. NO EXTRAS WILL BE PAID TO COMPLETE THIS WORK.
- 13. SUPPLY AND PLACE TOPSOIL IN ACCORDANCE WITH OPSS 570 TO A MINIMUM DEPTH OF 150MM UNLESS OTHERWISE SPECIFIED.
- 15. SUPPLY AND PLACE SEED IN ACCORDANCE WITH OPSS 572 UNLESS OTHERWISE SPECIFIED. ALL 5:1 OR GREATER SLOPES TO BE SEEDED WITH TACIFIER. CONTRACTOR TO PROVIDE NECESSARY EROSION CONTROL PROTECTION
- AS REQUIRED TO ENSURE SOIL STABILIZATION AND PROPER SEED GERMINATION. 16. ALL DIMENSIONS IN METRES UNLESS OTHERWISE NOTED. 17.IF DISCREPANCIES ARISE BETWEEN PLANT MATERIAL COUNT SHOWN ON DRAWING AND PLANT LIST, THE DRAWING
- SHALL BE CONSIDERED CORRECT. 18. CONTRACTOR TO PROVIDE MINIMUM TWO (2) YEAR WARRANTY FROM DATE ACCEPTED ON ALL WORK UNLESS
- 19. ANY SITE PLAN OR GRADING AND SERVICING SHOWN IS FOR INFORMATION ONLY. REFER TO APPROVED DRAWINGS
- 20.NOT FOR CONSTRUCTION UNLESS STAMPED, SIGNED AND DATED BY LANDSCAPE ARCHITECT. 21.DRAWINGS NOT TO BE REPRODUCED WITHOUT WRITTEN CONSENT FROM LANDSCAPE ARCHITECT.

14. SUPPLY AND PLACE SOD IN ACCORDANCE WITH OPSS 571 UNLESS OTHERWISE SPECIFIED.

22.APPROVAL OF LANDSCAPE PLAN TO BE OBTAINED FROM MUNICIPALITY. 23.FOR GRADING AND SERVICING INFORMATION REFER TO THE CONSULTING ENGINEER'S DRAWINGS. 24.FOR LIGHTING INFORMATION AND POWER DISTRIBUTION REFER TO THE ELECTRICAL CONSULTANT'S DRAWINGS.

### PLANTING NOTES

ARCHITECT FOR DIRECTION.

- 1. THE CONTRACTOR MUST NOTIFY THE LANDSCAPE ARCHITECT PRIOR TO THE COMMENCEMENT OF ANY PLANTING. THE CONTRACTOR SHALL SUPPLY ALL PLANTS AND MATERIALS IN QUANTITIES SUFFICIENT TO COMPLETE THE WORK SHOWN ON THIS DRAWING. ANY DISCREPANCIES BETWEEN QUANTITIES SHALL BE REPORTED TO THE
- ALL LANDSCAPE WORKS WILL BE WARRANTIED FOR A PERIOD OF TWO YEARS FOLLOWING INSPECTION AND WRITTEN NOTICE OF START OF WARRANTY PERIOD AS DETERMINED AND PROVIDED BY THE LANDSCAPE ARCHITECT. PLANT MATERIAL, WHICH IS NOT IN A HEALTHY, VIGOROUS GROWING CONDITION AT THE END OF THE WARRANTY PERIOD, SHALL BE REPLACED TO THE SATISFACTION OF THE LANDSCAPE ARCHITECT / OWNER.
- THE LANDSCAPE ARCHITECT RESERVES THE RIGHT TO EXTEND CONTRACTOR'S WARRANTY RESPONSIBILITIES FOR AN ADDITIONAL YEAR IF, AT THE END OF INITIAL WARRANTY PERIOD, LEAF DEVELOPMENT AND GROWTH IS NOT SUFFICIENT TO ENSURE FUTURE SURVIVAL AS DETERMINED BY THE LANDSCAPE ARCHITECT.
- THE CONTRACTOR IS TO IDENTIFY WITH LANDSCAPE ARCHITECT/OWNER ANY MAINTENANCE REQUIREMENTS NECESSARY FOR WARRANTY PURPOSES.
- 5. PLANT MATERIALS SPECIFIED FOR THIS PROJECT WILL CONFORM TO THE CANADIAN NURSERY LANDSCAPE ASSOCIATION (C.N.L.A.) FOR SIZE, VARIETY AND CONDITION AS INDICATED ON THE PLANT SCHEDULE SHOWN ON THESE DRAWINGS. ANY PLANT MATERIALS WHICH DO NOT CONFORM WILL BE PROMPTLY REMOVED FROM THE SITE AND REPLACED BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE PROJECT.
- THE LANDSCAPE ARCHITECT IS TO BE CONTACTED FOR INSPECTION AND WRITTEN APPROVAL PRIOR TO PLANT MATERIAL ARRIVING ON SITE. THE LANDSCAPE ARCHITECT RESERVED THE RIGHT TO REJECT ANY PLANT MATERIALS THAT HAVE NOT BEEN INSPECTED AND APPROVED.
- THE LANDSCAPE ARCHITECT RESERVES THE RIGHT TO REFUSE ACCEPTANCE OF ANY PLANT DISPLAYING POOR WILL BE PROMPTLY REMOVED FROM THE SITE AND REPLACED WITH MATERIAL OF ACCEPTABLE QUALITY AT NO ADDITIONAL CHARGE TO THE PROJECT.
- 8. PLANT MATERIALS COLLECTED FROM WILD SOURCES WILL NOT BE ACCEPTED WITHOUT WRITTEN APPROVAL OF THE LANDSCAPE ARCHITECT. THE LANDSCAPE ARCHITECT RESERVES THE RIGHT TO REQUIRE THAT SUPPLIER INVOICES BE SUBMITTED FOR INSPECTION AND APPROVAL PRIOR TO ACCEPTANCE.
- ON-SITE LAYOUT OF THE PLANT MATERIALS TO BE APPROVED BY THE LANDSCAPE ARCHITECT PRIOR TO INSTALLATION. MINOR FIELD ADJUSTMENTS TO PLANT MATERIAL LOCATIONS MAY BE NECESSARY TO RESPOND TO THE LOCATIONS OF EXISTING PLANTS AND SITE CONDITIONS. THE CONTRACTOR TO REVIEW WITH LANDSCAPE ARCHITECT WHERE RELOCATIONS ARE NECESSARY. THE CONTRACTOR MUST RECEIVE APPROVAL FROM LANDSCAPE ARCHITECT PRIOR TO INSTALLATION.
- 10. PLANTS ARE NOT TO BE INSTALLED DURING EXTREME HEAT, DROUGHT, OR OTHER UNDESIRABLE CONDITIONS. THOROUGHLY WATER ALL PLANTS IMMEDIATELY AFTER INSTALLATION. THE CONTRACTOR SHALL REGULARLY MONITOR SITE CONDITIONS AND WATER AS REQUIRED TO ENSURE HEALTHY GROWTH CONDITIONS THROUGHOUT
- THE DURATION OF THE WARRANTY PERIOD. 11. DO NOT PLANT DIRECTLY IN CENTERLINE OF DRAINAGE SWALES OR DEPRESSION AREAS. WHERE PROPOSED PLANTING LOCATIONS CONFLICT WITH CONSTRUCTED SWALES OR LOW-LYING WET AREAS, CONTACT LANDSCAPE
- 12. ALL PLANTS ARE TO BE PLANTED IN ACCORDANCE WITH THE PLANTING DETAILS SHOWN ON THIS DRAWING. ALL PLANTS ARE TO BE INSTALLED VERTICAL AND PLUMB, REGARDLESS OF GROUND SLOPE.
- 13. SUPPLY AND PLACE TOPSOIL IN ACCORDANCE WITH OPSS 802 TO A MINIMUM DEPTH OF 150MM IN SEED/SOD AREAS AND 600MM IN PLANTING BEDS UNLESS OTHERWISE SPECIFIED. EACH SOURCE OF TOPSOIL, IMPORTED OR NATIVE TO BE APPROVED BY LANDSCAPE ARCHITECT PRIOR TO USE. SUBMIT TOPSOIL ANALYSIS/TEST RESULTS TO LANDSCAPE ARCHITECT PRIOR TO ORDER OR DELIVERY TO SITE. TESTING TO BE IN ACCORDANCE WITH CONTRACT SPECIFICATIONS. PREPARED TOPSOIL SHALL BE 4 PARTS TOPSOIL TO ONE PART WELL-ROTTED
- 14. MULCH: TO BE SPREAD UNIFORMLY AROUND THE BASE OF TREES AND SHRUBS TO A MINIMUM DEPTH OF 100 MM. DO NOT PLACE MULCH IN DIRECT CONTACT WITH TRUNK OR STEM(S). ALLOW A 100 MM MULCH FREE ZONE AT
- TRUNK/STEMS. SHRUBS TO BE IN CONTINUOUSLY MULCHED PLANTING BEDS UNLESS OTHERWISE SPECIFIED. 15. SUPPLY AND PLACE SEED IN ACCORDANCE WITH OPSS 804 UNLESS OTHERWISE SPECIFIED. ALL 5:1 OR GREATER SLOPES TO BE SEEDED WITH TACKIFIER. ALL SLOPES GREATER THAN 3:1 SHALL BE MATTED WITH AN EROSION
- CONTROL BLANKET. SUPPLY AND PLACE SOD IN ACCORDANCE WITH OPSS 803 UNLESS OTHERWISE SPECIFIED. 16. THE CONTRACTOR IS TO REMOVE DEAD OR DAMAGED BRANCHES ON TREES OR SHRUBS. ALL PRUNING SHALL BE PERFORMED IN ACCORDANCE WITH STANDARD HORTICULTURAL PRACTICES AND APPROPRIATE TIMING FOR EACH
- 17. ALL STAKES AND ASSOCIATED TIES ARE TO BE REMOVED AFTER THE FIRST FULL GROWING SEASON. RODENT GUARDS ARE TO BE REMOVED AT THE CONCLUSION OF THE WARRANTY PERIOD. IF UTILIZED, GATORBAGS ARE TO BE REMOVED FOR WINTER MONTHS.

### CHURCHILL PROPERTIES INC.

5-145 SELECT AVE., TORONTO, ONTARIO


COPYRIGHT


This drawing has been prepared solely for the intended use, thus any reproduction or distribution for any purpose other than authorized by Arcadis is forbidden. Written dimensions shall have precedence over scaled dimensions. Contractors shall verify and be responsible for all dimensions and conditions on the job, and Arcadis shall be informed of any variations from the dimensions and conditions shown on the drawing. Shop drawings shall be submitted to Arcadis for general conformance before proceeding with fabrication.

Arcadis Professional Services (Canada) Inc.

ISSUES						
No.	DESCRIPTION	DATE				
2	ISSUED FOR ZBA & SPA REVIEW	2023-03-24				
3	ISSUED FOR ZBA & SPA REVIEW	2024-08-12				
4	ISSUED FOR ZBA & SPA REVIEW	2024-10-24				
5	ISSUED FOR SPA	2025-08-08				
6	ISSUED FOR SPA	2025-09-18				







PROPOSED ANNUALS

FILE NO. D07-12-22-0152 PLAN NO. 18881

PRIME CONSULTANT **ARCADIS** 

410 Albert Street - Suite 101 Waterloo ON N2L 3V3 Canada tel 519 585 2255 www.arcadis.com

PROJECT 424 Churchill Ave

CITY OF OTTAWA

PROJECT NO: 139413 DRAWN BY: CHECKED BY: PROJECT MGR: APPROVED BY: T.O.


SHEET TITLE LANDSCAPE PLAN

SHEET NUMBER


ISSUE

18881


5



BALLED & BURLAPPED/WIRE BASKET DECIDUOUS/CONIFEROUSTREE




BALLED AND BURLAPPED/POTTED SHRUB




1. SOIL MIXTURE: FOUR (4) PARTS NATIVE SOIL, ONE (1) PART WELL ROTTED COMPOST. 2. STAKING SCHEDULE; < 2500mm HT. - ONE STAKE > 2500mm HT. - TWO STAKES SPADED TREES - THREE STAKES OR GUY WIRES DO NOT PRUNE LEADER BRANCH REMOVE ALL NURSERY TAGS AND RIBBON FROM IF REQUIRED, PLASTIC TREE GUARD TO BE PLACED FROM LOWEST BRANCH TO SOIL SURFACE. SET ROOT FLARE OF TREE 50mm HIGHER THAN SURROUNDING GRADE TO ALLOW FOR SETTLEMENT 100mm HIGH SAUCER 100mm COMPACTED MULCH ABOVE FINISHED GRADE, 100mm AWAY FROM TRUNK PROVIDE CLEAN AND CONTINUOUS SPADE CUT ALONG ALL BED EDGES CUT AND REMOVE ALL WIRE, BURLAP, ROPE AND TWINE FROM TOP <sup>2</sup>/<sub>3</sub> OF ROOT BALL PLANTING SOIL TO BE 4 PARTS TOPSOIL, 1 PART WELL ROTTED COMPOST BACKFILL IN 150mm LIFTS AND MIX IN LAYERS TO PREVENT AIR POCKETS PLACE TREE ON UNDISTURBED SUBGRADE OR BUILD UP WITH COMPACTED SOIL TO RAISE TREE TO PROPER PLANTING GRADE AND AVOID

BALLED & BURLAPPED/WIRE BASKET CONIFEROUS TREE


SETTLEMENT




FURNITURE SURFACE MOUNT (TYP.)



CONCRETE SIDEWALK







**APPROVED** By Andrew McCreight at 11:51 am, Oct 30, 2025



5-145 SELECT AVE., TORONTO, ONTARIO

COPYRIGHT

This drawing has been prepared solely for the intended use, thus any reproduction or distribution for any purpose other than authorized by Arcadis is forbidden. Written dimensions shall have precedence over scaled dimensions. Contractors shall verify and be responsible for all dimensions and conditions on the job, and Arcadis shall be informed of any variations from the dimensions and conditions shown on the drawing. Shop drawings shall be submitted to Arcadis for general conformance before proceeding with fabrication.

Arcadis Professional Services (Canada) Inc.

ISSUE	ISSUES						
No.	DESCRIPTION	DATE					
2	ISSUED FOR ZBA & SPA REVIEW	2023-03-24					
3	ISSUED FOR ZBA & SPA REVIEW	2024-08-12					
4	ISSUED FOR ZBA & SPA REVIEW	2024-10-24					
5	ISSUED FOR SPA	2025-08-08					
6	ISSUED FOR SPA	2025-09-18					





FILE NO. D07-12-22-0152 PLAN NO. 18881

PRIME CONSULTANT **ARCADIS** 

410 Albert Street - Suite 101 Waterloo ON N2L 3V3 Canada tel 519 585 2255

PROJECT

www.arcadis.com

424 Churchill Ave

CITY OF OTTAWA

PROJECT NO: 139413				
DRAWN BY: E.L	CHECKED BY: M.P			
PROJECT MGR: M.P	APPROVED BY: T.O.			

LANDSCAPE DETAILS

SHEET NUMBER

ISSUE

18881


-22-0152




TEXTURE: HD<sup>2</sup> SMOOTH


SHAPE AND SIZE: 2 3/8 X 19 1/2 X 32 1/2

LAYOUT POSSIBILITIES: 03 LINEAR PATTERN










## 1 UNIT PAVING PATTERN TYPE 1 - SUPPLIED BY TECHO-BLOC


LD-2 N.T.S.



3 RIVER STONE LD-2 N.T.S.




5 UNIT PAVING PATTERN TYPE 2 - SUPPLIED BY TECHO-BLOC LD-2 N.T.S.




ALL DIMENSIONS IN MILLIMETERS UNLESS OTHERWISE NOTED. 2. CONTRACTOR TO PROVIDE INSPECTION AND VERIFICATION CERTIFICATE OF SUB-BASE PRIOR TO GRANULAR INSTALLATION.

2 UNIT PAVING WITH CONCRETE BASE LD-2 N.T.S.



4 MINIMUM STANDARDS FOR ACCESSIBLE CURB RAMP & TACTILE WARNING STRIP



5 MAGLIN-200 BIKE RACK LD-2 N.T.S.



5-145 SELECT AVE., TORONTO, ONTARIO

COPYRIGHT

**ANDREW MCCREIGHT** 

MANAGER, DEVELOPMENT REVIEW CENTRAL

**PLANNING, DEVELOPMENT & BUILDING SERVICES** 

**DEVELOPMENT DEPARTMENT, CITY OF OTTAWA** 

By Andrew McCreight at 11:51 am, Oct 30, 2025

**APPROVED** 

This drawing has been prepared solely for the intended use, thus any reproduction or distribution for any purpose other than authorized by Arcadis is forbidden. Written dimensions shall have precedence over scaled dimensions. Contractors shall verify and be responsible for all dimensions and conditions on the job, and Arcadis shall be informed of any variations from the dimensions and conditions shown on the drawing. Shop drawings shall be submitted to Arcadis for general conformance before proceeding with fabrication.

Arcadis Professional Services (Canada) Inc. formerly IBI Group Professional Services (Canada) Inc.

ISSUES					
No.	DESCRIPTION	DATE			
2	ISSUED FOR ZBA & SPA REVIEW	2023-03-24			
3	ISSUED FOR ZBA & SPA REVIEW	2024-08-12			
4	ISSUED FOR ZBA & SPA REVIEW	2024-10-24			
5	ISSUED FOR SPA	2025-08-08			
6	ISSUED FOR SPA	2025-09-18			



FILE NO. D07-12-22-0152 PLAN NO. 18881

ARCADIS

410 Albert Street - Suite 101 Waterloo ON N2L 3V3 Canada tel 519 585 2255 www.arcadis.com

PROJECT

424 Churchill Ave

CITY OF OTTAWA

PROJECT NO: 139413 DRAWN BY: CHECKED BY: PROJECT MGR: APPROVED BY: T.O.

SHEET TITLE

LANDSCAPE DETAILS

SHEET NUMBER LD-2

6

ISSUE

18881

-22-0152