



Site Servicing and Stormwater Management Report 1015 Tweddle Road, Ottawa, ON

Client:

Trim 1 GP Inc.
7 de Tellier
Gatineau, QC J8T 8C2

Submitted for:

Site Plan Application (SPA)

Project Name:

1015 Tweddle Road

Project Number:

OTT-00259629-A0

Prepared By:

EXP
2650 Queensview Drive
Ottawa, ON K2B 8H8
t: +1.613.688.1899
f: +1.613.225.7337

Date Submitted:

May 30, 2025
Rev 1 September 25, 2025
Rev 2 November 18, 2025

Site Servicing and Stormwater Management Report 1015 Tweddle Road, Ottawa, ON

Client:

Trim 1 GP Inc.
7 de Tellier
Gatineau, QC J8T 8C2

Submitted for:

Site Plan Application (SPA)

Project Name:

1015 Tweddle Road

Project Number:

OTT-00259629-A0

Prepared By:

EXP
2650 Queensview Drive
Ottawa, ON K2B 8H8
t: +1.613.688.1899
f: +1.613.225.7337

Prepared by:

Approved by:

Jason Fitzpatrick, P.Eng.
Project Engineer

Bruce Thomas, P.Eng.
Senior Project Manager

Date Submitted:

May 30, 2025
Rev 1 September 25, 2025
Rev 2 November 18, 2025

Table of Contents

| | | |
|-------|--|----|
| 1 | Introduction | 1 |
| 1.1 | Overview | 1 |
| 2 | Existing Conditions..... | 2 |
| 2.1 | Site Topography..... | 2 |
| 3 | Existing Infrastructure..... | 3 |
| 4 | Pre-Consultation / Permits / Approvals..... | 4 |
| 5 | Water Servicing..... | 5 |
| 5.1 | Water Servicing Design Criteria | 5 |
| 5.2 | Water Servicing Proposal..... | 5 |
| 5.3 | Estimated Water Demands..... | 6 |
| 5.4 | Boundary Conditions | 6 |
| 5.5 | Fire Flow Requirements..... | 7 |
| 5.6 | Review of Hydrant Spacing | 7 |
| 5.7 | Water Servicing Design | 8 |
| 6 | Sanitary Sewage Servicing | 10 |
| | Sanitary Sewage Design Criteria..... | 10 |
| 6.1 | Proposed Sewage Conditions | 10 |
| 6.2 | Offsite Sanitary Sewer Review | 11 |
| 7 | Storm Servicing & Stormwater Management..... | 13 |
| 7.1 | Design Criteria..... | 13 |
| 7.1.1 | Minor System Design Criteria | 13 |
| 7.1.2 | Major System Design Criteria | 13 |
| 7.2 | Runoff Coefficients | 13 |
| 7.3 | Pre-Development Release Rate | 14 |
| 7.4 | Post-Development Stormwater Management Scheme..... | 14 |
| 7.5 | Stormwater Model Development..... | 14 |
| 7.6 | Rainfall Data..... | 15 |
| 7.7 | Proposed Stormwater System | 16 |
| 7.8 | Flow Attenuation & Storage | 17 |
| 7.9 | Stormwater Model Results | 17 |
| 7.10 | Quality Control..... | 17 |

| | | |
|------|--|----|
| 7.11 | Jeanne-d’Arc Blvd Drainage Catchment | 18 |
| 7.12 | Tweddle Road Drainage Catchment | 21 |
| 8 | Erosion & Sediment Control | 23 |
| 9 | Conclusions and Recommendations..... | 24 |

List of Figures

| | |
|--|----|
| Figure 1-1 - Site Location | 1 |
| Figure 2-1 - Site Topography..... | 2 |
| Figure 5-1 – Review of Hydrant Spacing | 9 |
| Figure 7-1: Hydraulic Grade Lines of 2-yr and 100-yr Storms of Jeanne-d’Arc Storm Sewers | 20 |
| Figure 7-2: Flows and Water Depths at 500mm Culvert | 22 |
| Figure A1 – Post-Development Subcatchments | A |
| Figure A2 – JDA Subcatchments | A |
| Figure A3 – Tweddle Subcatchments..... | A |

List of Tables

| | |
|---|----|
| Table 5-1 - Summary of Water Supply Design Criteria | 5 |
| Table 5-2 : Water Demand Summary | 6 |
| Table 5-3 - Summary of Design Parameters Used in Calculating Required Fire Flows (RFF) Using FUS..... | 7 |
| Table 5-4 –Fire Flows Based on Hydrant Spacing | 8 |
| Table 6-1 – Summary of Wastewater Design Criteria / Parameters..... | 10 |
| Table 6-2 – Summary of Anticipated Sewage Rates | 11 |
| Table 7-1 – Summary of Stormwater Peak Flows..... | 14 |
| Table 7-2 : Subcatchment Parameters | 14 |
| Table 7-3 : Summary of Rainfall Data (From City of Ottawa SDG002)..... | 16 |
| Table 7-4 – Summary of Post-Development Storage | 17 |
| Table 7-5 : Summary of Post-Development Flows at Outfall #1..... | 17 |
| Table 7-6 – Design Parameters Used for Oil Grit Separator Sizing..... | 18 |
| Table 7-7 : Discharge Rates for Standard IPEX Tempests Type A | 19 |
| Table 7-8 : Summary of Post-Development Flows at Outfall #2..... | 20 |
| Table 7-9 : Summary of Post-Development Flows at Outfall #2..... | 21 |
| Table B1 – Water Demand Chart | B |
| Table B2 – Summary of Required Fire Flows (RFFs) | B |
| Table B3 – Fire Flow Requirements Based on Fire Underwriters Survey (FUS) – Tower B1..... | B |
| Table B4 – Fire Flow Requirements Based on Fire Underwriters Survey (FUS) – Tower B2..... | B |
| Table B5 – Fire Flow Requirements Based on Fire Underwriters Survey (FUS) – Tower B3..... | B |

| | |
|---|---|
| Table B6 – Fire Flow Requirements Based on Fire Underwriters Survey (FUS) – Tower B4..... | B |
| Table B7 – Fire Flow Requirements Based on Hydrant Spacing | B |
| Table B8 – Sanitary Sewer Design Sheet..... | B |
| Table B9 – Storm Sewer Design Sheet | B |
| Table B10 – Calculation of Average Runoff Coefficients for Pre-Development Conditions | B |
| Table B11 – Calculation of Catchment Time of Concentration for Pre-Development Conditions | B |
| Table B12 – Calculation of Peak Runoff for Pre-Development Conditions..... | B |
| Table B13 – Average Runoff Coefficients for Post-Development..... | B |
| Table B14 – Summary of Post-Development Peak Flows (Uncontrolled and Controlled) | B |
| Table B15 – Summary of Storage..... | B |
| Table B16 – Storage Volumes for 2-year, 5-year and 100-Year Storms (MRM) Tower B1..... | B |
| Table B17 – Storage Volumes for 2-year, 5-year and 100-Year Storms (MRM) Tower B2 | B |
| Table B18 – Storage Volumes for 2-year, 5-year and 100-Year Storms (MRM) Tower B3 | B |
| Table B19 – Storage Volumes for 2-year, 5-year and 100-Year Storms (MRM) Tower B4..... | B |
| Table B20 – Summary of Roof Drains and Roof Storage | B |
| Table B21 – Estimation of Roof Storage and Outflow – Tower B1 | B |
| Table B22 – Estimation of Roof Storage and Outflow – Tower B2 | B |
| Table B23 – Estimation of Roof Storage and Outflow – Tower B3 | B |
| Table B24 – Estimation of Roof Storage and Outflow – Tower B4 | B |

List of Appendices

| | |
|--|---|
| Appendix A – Figures | A |
| Appendix B – Design Tables | B |
| Appendix C – Manufacturers Information..... | C |
| Appendix D – Consultation / Correspondence | D |
| Appendix E – Drawings | E |
| Appendix F - PCSWMM Results..... | F |

1 Introduction

1.1 Overview

EXP Services Inc. (EXP) was retained by Trim 1 GP Inc. to prepare a Site Servicing and Stormwater Management Report for the proposed development of 1015 Tweddle Road in support of the Site Plan Application.

The site is situated at the north-east corner of Tweddle Road and Jeanne D'Arc Boulevard North as illustrated in [Figure 1-1](#) below. The site is within the City of Ottawa urban boundary and situated in Orleans Ward (Ward 1).



Figure 1-1 - Site Location

The overall property area is 3.42 ha. The proposed development will occupy 1.28 ha of the total property parcel. The proposed development will consist of four high-rise buildings. Tower B1 and B3 both will be 28 storey, tower B2 will be 32 storey and tower B4 will be 24 storeys high. All four towers will be constructed above underground parking. Proposed development will have total 1,258 residential units and around 2,471 m² of commercial/retail space. Tower B1 will have 326 units, Tower B2 will have 372 units, Tower B3 will have 324 units and Tower B4 will have 2236 units.

This report will discuss the adequacy of the adjacent municipal watermain, sanitary sewers and storm sewers to provide the required water supply, convey the sewage and stormwater flows that will result from the proposed development.

2 Existing Conditions

2.1 Site Topography

The site is currently undeveloped. The site is bounded to the west by Tweddle Road, to the south by Jeanne-D'Arc Boulevard North to the east by undeveloped land, and to the north by the Ottawa River. **Figure 2-1** below illustrates the topography of the site which slopes in a northerly direction towards the Ottawa River.




Figure 2-1 - Site Topography

Within the site the topography ranges from $\pm 52\text{m}$ down to $\pm 42\text{m}$. A digital terrain model (DTM) was derived from 2019-2020 Ottawa Gatienau LIDAR Derived DTM (Land Inventory Ontario) and is shown in **Figure 2-1**. The normal water surface elevation within the adjacent Ottawa River is approximately $\pm 42.0\text{m}$, with a 100-year flood elevation being 45.0m . The Topographic Survey in **Appendix E** shows Ottawa River Normal High Water Mark, Edge of Wetlands, Ottawa River 100-Yr Regulatory Floodplain, Limit of Hazard Lands, Top of Slope Line, 15m Setback from Top of Slope and 30m Setback from Wetlands.

3 Existing Infrastructure

From review of the sewer and watermain mapping, as-built drawings and the City's GeoOttawa mapping, the following summarizes the onsite and adjacent offsite infrastructure:

Within property

- Subject property is currently undeveloped with no services or utilities

Within Jeanne-D'Arc Boulevard North, opposite the site

- 406 mm watermain and fire hydrants
- 300mm sanitary sewer
- Open drainage ditches on east side of Trim Road and along the north side of Jeanne D'Arc Boulevard North
- Enbridge Consumers Gas
- Overhead hydro lines and communication cables

Within Tweddle Road

- 75 mm watermain
- 75mm sewage forcemain
- Overhead Hydro and communication

4 Pre-Consultation / Permits / Approvals

A pre-consultation meeting was held with the City prior to design commencement. This meeting, held August 1, 2024, outlined the submission requirements and provided information to assist with the development proposal.

The proposed site is located within the Rideau Valley Conservation Authority (RVCA) jurisdiction, therefore signoff from the RVCA will be required. From previous development consultation on the property, the RVCA has noted that enhanced protection (80% TSS removal) is required. The RVCA has been contacted to confirm the stormwater management quality control requirements.

Stormwater management quantity control will not be required for the portion of the development that will be discharging directly to the Ottawa River. Additional information on this will be provided in proceeding sections.

An Environmental Compliance Approval (ECA) will be required from the Ministry of Environment, Conservation and Parks (MECP), for the upsizing of the sanitary sewer and the proposed storm sewer within Jeanne D'Arc Boulevard. A MECP ECA will also be required for the stormwater discharge from the site to the Ottawa River. Design Guidelines

Various design guidelines were referred to in preparing the current report including:

- Bulletin ISDTB-2012-4 (20 June 2012)
 - Technical Bulletin ISDTB-2012-04
 - Technical Bulletin ISDTB-2014-01
 - Technical Bulletin PIETB-2016-01
 - Technical Bulletin ISDTB-2018-01
 - Technical Bulletin ISDTB-2018-03
 - Technical Bulletin ISDTB-2018-04
 - Technical Bulletin ISDTB-2019-02
 -
- Ottawa Design Guidelines – Water Distribution, July 2010 (WDG001), including:
 - Technical Bulletin ISDTB-2010-02
 - Technical Bulletin ISDTB-2014-02
 - Technical Bulletin ISTB-2018-02
 - Technical Bulletin ISTB-2021-03
- Stormwater Management Planning and Design Manual, Ontario Ministry of the Environment and Climate Change, March 2003 (SMPDM).
- Design Guidelines for Drinking-Water Systems, Ontario Ministry of the Environment and Climate Change, 2008 (GDWS).
- Fire Underwriters Survey, Water Supply for Public Fire Protection (FUS), 2020.
- Ontario Building Code 2012, Ministry of Municipal Affairs and Housing.

5 Water Servicing

5.1 Water Servicing Design Criteria

Table 5-1 below summarizes the Design Criteria that was used to establish the water demands and the required fire flows, based on the proposed building uses. The design parameters that apply to this project and used for calculations are identified below.

Table 5-1 - Summary of Water Supply Design Criteria

| Design Parameter | Value | Applies |
|---|-----------------------------------|---------|
| Population Density – Single-family Home | 3.4 persons/unit | |
| Population Density – Semi-detached Home | 2.7 persons/unit | |
| Population Density – Townhome or Terrace Flat | 1.8 persons/unit | |
| Population Density – Bachelor Apartment | 1.4 persons/unit | |
| Population Density – Bachelor + Den Apartment | 1.4 persons/unit | |
| Population Density – One Bedroom Apartment | 1.4 persons/unit | ✓ |
| Population Density – One Bedroom plus Den Apartment | 1.4 persons/unit | ✓ |
| Population Density – Two Bedroom Apartment | 2.1 persons/unit | ✓ |
| Population Density – Two Bedroom plus Den Apartment | 2.1 persons/unit | |
| Population Density – Three Bedroom Apartment | 3.1 persons/unit | ✓ |
| | | |
| Average Day Demands – Residential | 280 L/person/day | ✓ |
| Average Day Demands – Commercial / Institutional | 5 L/m ² floor area/day | ✓ |
| Average Day Demands – Light Industrial / Heavy Industrial | 35,000 or 55,000 L/gross ha/day | |
| | | |
| Maximum Day Demands – Residential | 2.5 x Average Day Demands | ✓ |
| Maximum Day Demands – Commercial / Institutional | 1.5 x Average Day Demands | ✓ |
| Peak Hour Demands – Residential | 5.5 x Average Day Demands | ✓ |
| Peak Hour Demands – Commercial / Institutional | 2.7 x Average Day Demands | ✓ |
| | | |
| Fire Flow Requirements Calculation | FUS | ✓ |
| Depth of Cover Required | 2.4m | ✓ |
| Maximum Allowable Pressure | 551.6 kPa (80 psi) | ✓ |
| Minimum Allowable Pressure | 275.8 kPa (40 psi) | ✓ |
| Minimum Allowable Pressure during fire flow conditions | 137.9 kPa (20 psi) | ✓ |

5.2 Water Servicing Proposal

The proposed development will include 1,258 residential units and 2,471 square meters of level 1 and level 2 retail space housed within the four towers.

Architectural plans and rendering of the proposed building along with building statistics are provided in **Appendix E**.

It is proposed that the water supply for the site will be provided by two twin 200mm watermains supplied from the existing 406mm watermain on Jeanne D'Arc Boulevard North. The development will require independent and twin watermain services, which is the result of the average day water demands exceeding 50 m³/day. The watermain feeds from the underground parking level will connect directly to the existing 406mm watermain on Jeanne D'Arc Boulevard and will have an isolation valve between them, consistent with City of Ottawa Water Design Guidelines.

The buildings will be protected by an automatic sprinkler system. Fire department connections (or siamese) will be located within 45 metres of existing adjacent municipally owned fire hydrants for towers B2, B3 and B4. In existing conditions there are no fire hydrants within Tweddle Road in near proximity of Tower B1. A new fire hydrant and lead are required on Tweddle Road to service Tower B1. Hence, it is proposed to extend a municipal 200mm diameter watermain within Tweddle Road to be capped north of the new fire hydrant.

5.3 Estimated Water Demands

The following **Table 5-2** below summarizes the anticipated water demands for the proposed development based on following:

- 4 towers having total 1,258 residential units. Estimated residential population of 2,069 persons.
- Commercial & Amenity spaces on level 1 and 2. Estimated area of 4,200 m².

Table 5-2 : Water Demand Summary

| Water Demand Conditions | Tower B1 Water Demands (L/sec) | Tower B2 Water Demands (L/sec) | Tower B3 Water Demands (L/sec) | Tower B4 Water Demands (L/sec) | Total Water Demands (L/sec) |
|-------------------------|--------------------------------|--------------------------------|--------------------------------|--------------------------------|-----------------------------|
| Average Day | 2.22 | 2.45 | 2.11 | 1.28 | 8.07 |
| Max Day | 5.07 | 5.65 | 4.88 | 3.20 | 18.80 |
| Peak Hour | 10.43 | 11.71 | 10.14 | 7.04 | 39.32 |

5.4 Boundary Conditions

Hydraulic Grade Line (HGL) boundary conditions were obtained from the City for design purposes. A copy of the correspondence received from the City is provided in **Appendix D**.

The following hydraulic grade line (HGL) boundary conditions were provided:

- Maximum HGL (Average Day) = 113.6 m
- Peak Hour HGL = 106.7 m
- Max Day Plus Fire Flow 1 = 112.0 m (100 L/sec)
- Max Day Plus Fire Flow 2 = 102.9 m (167 L/sec)

The provided HGL ranges of 106.7 m – 113.6 m were used to estimate pressures at the building. Under Max Day Plus fire flow conditions, the lower HGL of 102.9 m was used, whereas for Peak Hour conditions the HGL of 106.7 m was used. Based on a ground elevation of approximately 51.9 m at the boundary condition location this results in a system water pressure of 54.8 m or 78.0 psi during peak hour conditions, and 61.7 m or 87.8 psi at a maximum value (Average Day demand). Therefore, the use of pressure reducing valves should be considered by the mechanical consultant during the design of interior water systems of each new proposed tower.

5.5 Fire Flow Requirements

Water for fire protection will be available utilizing the proposed fire hydrants located along on Jeanne D'Arc Boulevard. The required fire flows for the proposed buildings were calculated based on typical values as established by the Fire Underwriters Survey 2020 (FUS).

The following equation from the Fire Underwriters document "Water Supply for Public Fire Protection", 2020, was used for calculation of the on-site supply rates required to be supplied by the hydrants:

$$F = 200 * C * \sqrt{A}$$

where:

| | | |
|---|---|---|
| F | = | Required Fire flow in Litres per minute |
| C | = | Coefficient related to type of Construction |
| A | = | Total Floor Area in square metres |

The proceeding **Table 5-3** summarizes the parameters used for estimating the Required Fire Flows (RFF) based on the Fire Underwriters Survey (FUS) and the latest City of Ottawa Technical Bulletins. The RFFs were estimated in accordance with ISTB-2018-02, and based on floor areas provided by the architect, which are illustrates in **Appendix E**.

Detailed calculation of Required Fire Flow (RFF) for proposed buildings can be found in **Table B3** to **Table B6** in **Appendix B**.

Table 5-3 - Summary of Design Parameters Used in Calculating Required Fire Flows (RFF) Using FUS

| Building # | No of Storeys | Fire Flow, F (L/min) | Type of Constr. Coeff, C | Reduction Due to Occupancy (%) | Reduction Due to Sprinklers (%) | Total Increase due to Exposures (%) | Required Fire Flow in | |
|------------|---------------|----------------------|--------------------------|--------------------------------|---------------------------------|-------------------------------------|-----------------------|---------|
| | | | | | | | (L/min) | (L/sec) |
| Tower B1 | 28 | 15,000 | 0.8 | -15% | -50% | 5% | 7,000 | 117 |
| Tower B2 | 32 | 14,000 | 0.8 | -15% | -50% | 10% | 7,000 | 117 |
| Tower B3 | 28 | 14,000 | 0.8 | -15% | -50% | 10% | 7,000 | 117 |
| Tower B4 | 24 | 13,000 | 0.8 | -15% | -50% | 5% | 6,000 | 100 |

5.6 Review of Hydrant Spacing

A review of the hydrant spacing was completed to ensure compliance with Appendix I of Technical Bulletin ISTB-2018-02. As per Section 3 of Appendix I all hydrants within 150 metres were reviewed to assess the total possible available flow from these contributing hydrants. For each hydrant the distance to the proposed building was determined to arrive at the contribution of fire flow from each. All hydrants are expected to be of Class AA as per Section 5.1 of Appendix I. For each hydrant the straight-line distance, distance measured along a fire route or roadway, whether its location is accessible, and its contribution to the required fire flow.

Figure 5-1 below illustrates all the hydrants that are within the 75 metre and 150 metre offsets from the subject property. Fire hydrants that are denoted with a number having a HP versus H represents a PRIVATE hydrant rather than a CITY owned hydrant. All hydrants were reviewed to determine if they were accessible or non-accessible. For example, a hydrant would not be accessible if they were located on the opposite side of a median, limiting fire truck access. A summary table of the total fire flows available versus the required fire flows (RFFs) is presented in **Table 5-4** below.

Table 5-4 –Fire Flows Based on Hydrant Spacing

| Building | Required Fire Flow (L/min) | Available Fireflow Based on Hydrant Spacing as per ISTB-2018-02 (L/min) |
|----------|----------------------------|---|
| Tower B1 | 7,000 (or 100 L/sec) | 13,300 |
| Tower B2 | 7,000 (or 117 L/sec) | 19,000 |
| Tower B3 | 7,000 (or 117 L/sec) | 13,300 |
| Tower B4 | 6,000 (or 100 L/sec) | 9,500 |

Detailed calculations of the available fire flows based on hydrant spacing is provided in **Table B7** found in **Appendix B**. Therefore, the available flows from hydrants exceed each building's fire flow requirements as identified in Appendix I of Technical Bulletin ISTB-2018-02.


5.7 Water Servicing Design

The water servicing requirements for the proposed building is designed in accordance with the City Design Guidelines (July 2010). The following steps indicate the basic methodology that was used in our analysis:

- Estimated water demands under average day, maximum day and peak hour conditions. As the total population estimate is greater than 500, standard residential peaking factors were used.
- Estimated the required fire flow (RFF) based on the Fire Underwriters Survey (FUS).
- Reviewed the available flows from hydrants within 150m of the buildings, based on the City's WDG002 and compared to the required fire flows (RFFs) based on the Fire Underwriters Survey (FUS).
- Obtained hydraulic boundary conditions (HGL) from the City, based on the above water demands and required fire flows.
- Boundary condition data and water demands were used to estimate the pressure at the proposed building, and this was compared to the City's design criteria.

Since the average day demand exceed 50 m³ per day, two watermain feeds for the development will be necessary as per Section 4.31 of the WDG001. Please refer to **Table B1** in **Appendix B** for detailed calculations of the total water demands.

Figure 5-1 – Review of Hydrant Spacing



Based on the hydraulic grade line (HGL) provided from the City it is evident that high pressures exist in the water distribution system at the property. Static pressures of ± 70 psi – 90 psi are typically available. This is due to the lower elevation relative to the reservoir.

Based on the results, the installation of two twin 200mm watermains with a shut-off valve between them is proposed. As the maximum hydraulic grade line (HGL) provided by the city indicates pressures greater than 80 psi, pressure reducing measures will be required.

6 Sanitary Sewage Servicing

Sanitary Sewage Design Criteria

The sanitary sewer system is designed based on a population flow and an area-based infiltration allowance. The flows were calculated using City sewer design guidelines (SDG002). **Table 6-1** below summarizes the design parameters used.

Table 6-1 – Summary of Wastewater Design Criteria / Parameters

| Design Parameter | Value | Applies |
|--|--------------------------------------|---------|
| Population Density – Single-family Home | 3.4 persons/unit | |
| Population Density – Semi-detached Home | 2.7 persons/unit | |
| Population Density – Duplex | 2.3 persons/unit | |
| Population Density – Townhome (row) | 2.7 persons/unit | |
| Population Density – Bachelor Apartment | 1.4 persons/unit | |
| Population Density – Bachelor + Den Apartment | 1.4 persons/unit | |
| Population Density – One Bedroom Apartment | 1.4 persons/unit | ✓ |
| Population Density – One Bedroom plus Den Apartment | 1.4 persons/unit | ✓ |
| Population Density – Two Bedroom Apartment | 2.1 persons/unit | ✓ |
| Population Density – Two Bedroom plus Den Apartment | 2.1 persons/unit | ✓ |
| Population Density – Three Bedroom Apartment | 3.1 persons/unit | ✓ |
| Average Daily Residential Sewage Flow | 280 L/person/day | ✓ |
| Average Daily Commercial / Institutional Flow | 28,000 L/gross ha/day | ✓ |
| Average Light / Heavy Industrial Daily Flow | 35,000 / 55,000 L/gross ha/day | |
| Residential Peaking Factor – Harmon Formula (Min = 2.0, Max =4.0, with K=0.8) | $M = 1 + \frac{14}{4 + P^{0.5}} * k$ | ✓ |
| Commercial Peaking Factor | 1.5 | ✓ |
| Institutional Peaking Factor | 1.5 | |
| Industrial Peaking Factor | As per Table 4-B (SDG002) | |
| Unit of Peak Extraneous Flow (Dry Weather / Wet Weather) | 0.05 or 0.28 L/s/gross ha | |
| Unit of Peak Extraneous Flow (Total I/I) | 0.33 L/s/gross ha | ✓ |

6.1 Proposed Sewage Conditions

It is proposed that the mechanical piping from each building discharge into a sanitary manhole onsite, which will then discharge to the existing sanitary sewer on Jeanne-D’Arc Boulevard. This manhole will be installed near the property line and be used as a monitoring manhole.

Two 300mm diameter sanitary service laterals are proposed to service the full development. The estimated peak sanitary flow rate from the proposed property is **±21.14/sec** based on City Design Guidelines. Sewage rates include a total infiltration allowance of 0.33 L/ha/sec based on the total gross site area.

Table 6-2 below summarizes the sewage anticipated peak sewage flows for the proposed site.

Table 6-2 – Summary of Anticipated Sewage Rates

| Sewage Condition | Sanitary Sewage Flow (L/sec) |
|--|------------------------------|
| Peak Residential Flow (for 2,069 persons) | 20.52 |
| Peak Commercial Flow (for 4,200 m ²) | 0.20 |
| Infiltration Flow (for 1.28 ha) | 0.42 |
| Peak Design Flow | 21.14 |

6.2 Offsite Sanitary Sewer Review

The sanitary sewer run on Jeanne D’Arc Boulevard North (from Tweddle Road easterly to municipal limits) was designed and constructed to allow for the development of Phase I (Tower 1) of Brigil’s Petrie’s Landing II to proceed. Approximately 320 metres of sanitary sewer was extended from the Tweddle Road (Formerly Trim Road) intersection easterly to service Petrie’s Landing II. A review of previous reports by David MacManus (DME) for Phase 1, and EXP Services (EXP) for Phase 2, confirmed that the sanitary sewer system on Jeanne D’Arc Boulevard North was sized, not only for the 3.9-hectare Petrie’s Landing development site, but also for an additional 9.9 hectares of commercial development along Jeanne D’Arc Boulevard North. The commercial flow allowance established was 50,000 L/ha/day and included an additional infiltration allowance at 0.28 L/ha/sec.

As taken from the DME report, the total peak sanitary flows from both Petrie’s Landing development (all 5 phases) and the additional 9.9 hectares was 34.7 L/sec, which included ± 23.4 L/sec from Petrie’s Landing and ± 11.4 L/sec from the additional area along Jeanne D’Arc Boulevard North. At the time of the design of Tower 1 by DME, this was based on a residential population of 1512 persons.

In 2016, during the design of Tower 2 by EXP Services Inc (EXP), further refinement of the sanitary sewage flows from the Petrie’s II Landing development was completed, based on number of proposed residential units. A revised population of 1822 persons was used and included the same offsite commercial flow allowance for the 9.9-hectares along Jeanne D’Arc Boulevard North. The peak flow was updated to 39.2 L/sec with 27.8 L/sec from Petrie’s Landing development and 11.4 L/sec from the offsite areas.

The review of all sanitary sewer runs on Jean D’Arc Boulevard North were completed based on the most up to date information. A sanitary sewer design sheet was compiled based on data from the Petrie’s Landing II project and based on the City’s most recent Technical Bulletins. It should be noted that March 2018, revisions to the City’s SDG002, were made to residential flow allowances as noted in Technical Bulletin ISTB-2018-01. The per capita flow allowance was lowered from 350 L/p/day to 280 L/p/day, along with the addition of the correction factors of 0.8 to the Harmon Formula Peaking Factors. These revised allowances were used to review sanitary sewer capacities.

Table B8 in **Appendix B** summarizes the anticipated peak sewage flows in all sanitary sewers runs up to the Tweddle Road (formerly Trim Road) intersection, whereas *Sanitary Drainage Area Plan C500* illustrates the sanitary drainage areas tributary to this sewer run.

It should be noted that the developer has proposed to acquire Part 9 of Plan 50R-5818 – Jeanne D’Arc ROW at the north-east corner of Jeanne D’Arc Boulevard North and Tweddle Road (formerly Trim Road), from the City. Sanitary manhole #MHSA22037 is proposed to be relocated outside the property line and sanitary manhole MH#54993 is proposed to be relocated further east. With this relocation, the structures can be used for monitoring sanitary discharge from the development as sanitary laterals are proposed to connect to the relocated structures. It is also

proposed to upsize the pipes between MHSA22037 & MHSA54992 from 300mm dia. to 375mm dia. as shown on *Site Servicing Plan C100*.

Table B8 in **Appendix B** shows that the most restricted proposed 375 sanitary sewer will run at 56% capacity at 0.17% slope, with full flow capacity of ± 79.53 L/sec.

For the site at 1015 Tweddle Road (formerly 1009 Trim Road), two 375mm diameter PVC sewer laterals having a minimum slope of 2.0% are proposed to service the development. The estimated capacity of a 375mm pipe at 2% is ± 272 L/sec. A lateral at this slope would permit 8,300 fixture units as per OBC. Further detail and coordination with mechanical consultant will be advanced as the project progresses.

7 Storm Servicing & Stormwater Management

7.1 Design Criteria

The subject property is located within the Rideau Valley subwatershed; therefore, stormwater works are subject to both the Rideau Valley Conservation Authority (RVCA) and City of Ottawa (COO) approval.

The RVCA has noted that (80% TSS removal) quality control requirements for the site will be required.

Also clarified during the pre-consultation meeting, the requirements related to stormwater quantity control are noted as follows:

- *No quantity control is required for this development ONLY if it is discharging to the river.*
- *Please contact the City if this development will require municipal stormwater servicing.*

The proposed stormwater system is designed in conformance with the latest version of the City of Ottawa Design Guidelines (October 2012). Section 5 “Storm and Combined Sewer Design” and Section 8 “Stormwater Management”. A summary of the design criteria that relates to this design report is the proceeding sections below.

7.1.1 Minor System Design Criteria

- The storm sewer sizing will be based on the Rational Method and Manning’s Equation under free flow conditions for the 2-year storm using a 10-minute inlet time.
- Minimum sewer slopes to be based on minimum velocities for storm sewers of 0.80 m/sec.

7.1.2 Major System Design Criteria

- Any onsite stormwater detention (if used) will be estimated based on the 100-year design storm. It is proposed that roof top storage be incorporated where possible.
- Onsite detention will be estimated using the Modified Rational Method (MRM).
- Emergency overland flow routes are provided.
- The vertical distance from the spill elevation on the street and the ground elevation at the buildings is at least 150mm.
- The emergency overflow spill elevation is at least 30 cm below the lowest building opening.

7.2 Runoff Coefficients

Runoff coefficients used were based on actual areas taken from CAD. Runoff coefficients for impervious surfaces (roofs, asphalt, and concrete) were taken as 0.90, whereas those for pervious surfaces (grass/landscaping) were taken as 0.20. Runoff coefficient for gravel surface was taken as 0.75. Average runoff coefficients were calculated for catchments (or drainage areas) using the area-weighting method in Excel or spatial-weighting in PCSWMM. The runoff coefficients for all pre-development and post-development catchments are provided in **Table B10** and **Table B13**, respectively.

7.3 Pre-Development Release Rate

The proposed development will occupy 1.28 ha out of 3.42 ha of total site area. Pre-development runoff coefficient for 1.28 ha site area was estimated to be 0.29. The calculated time of concentration was 3.58 mins. Therefore, the pre-development discharge rates during 2-year, 5-year and 100-year storm events were estimated with average runoff coefficient of 0.29 and time of concentration of 10 mins as per the City of Ottawa guidelines, summarized in Table 7-1 below. Detailed calculation of pre-development peak runoff rate can be found in **Table B12** in **Appendix B**.

Table 7-1 – Summary of Stormwater Peak Flows

| Development | Pre-Development Discharge Rates (L/sec) | | |
|--|---|--------|----------|
| | 2-year | 5-year | 100-year |
| 1015 Tweddle Road (formerly 1009 Trim Road) | 79.1 | 107.3 | 229.9 |

7.4 Post-Development Stormwater Management Scheme

As noted above, the City of Ottawa permitted no quantity control of post-development runoff due to the sites proximity to the Ottawa River, if stormwater system is discharging directly into the Ottawa river. The portion of development discharging to the City ROW would be controlled to 5-year pre-development discharge rates with maximum runoff coefficient of 0.5. However, at this stage, the whole site is proposed to discharge via one outlet to the north into the Ottawa River. Therefore, no quantity control has been proposed.

7.5 Stormwater Model Development

PCSWMM was used to create a hydrologic/hydraulic model of the stormwater system. The model includes both the minor system (storm sewer), for estimating peak flows and runoff volumes and the major system (roads and swales, etc.). Calculations of runoff was completed based on the PCSWMM's EPA SWM 5 engine.

PCSWMM is an advanced software application for stormwater, wastewater, watershed, and water distribution system modelling. PCSWMM was developed by Computational Hydraulics International (CHI) <https://www.chiwater.com/Home> and is based on the EPA storm water management model (SWMM), which is a dynamic rainfall-runoff-routing simulation model used for single event or long-term (continuous) simulation of runoff. PCSWMM was used to determine peak runoff rates and provide hydraulic profiles of the depth of runoff during various storm events. PCSWMM calculates runoff based on the non-linear reservoir model for subcatchments. The model conceptualizes a subcatchment as a rectangular surface that has a uniform slope and a width that drains to a single outlet. The subcatchments receive inflow from precipitation and losses from evaporation and infiltration. The net excess volume ponds atop the subcatchment surface. Pondered water above the depression storage depth, can become runoff outflow. Depression storage accounts for initial rainfall abstractions such as surface ponding, interception by flat roofs and vegetation and surface wetting.

Subcatchment parameters were taken from City of Ottawa's SDG002 Design parameters. The following design parameters and assumptions are noted in

Table 7-2 below:

Table 7-2 : Subcatchment Parameters

| Parameter | PCSWMM Parameter | Value |
|--|------------------|------------|
| Infiltration Loss Method | | Horton |
| Maximum Infiltration Rate | Max. Infil. Rate | 76 mm/hr |
| Minimum Infiltration Rate | Min. Infil. Rate | 13.2 mm/hr |
| Decay Constant (1/hr) | Decay Constant | 4.14 |
| Manning N (Impervious) | N Impev | 0.013 |
| Manning N (Pervious) | N Perv | 0.25 |
| Depression Storage – Impervious Surfaces | Dstore Imperv | 1.57 mm |
| Depression Storage – Pervious Surfaces | Dstore Perv | 4.67 mm |
| Zero Percent Impervious | Zero Imper | varies |
| Subcatchment Slopes | Slope | varies |

The following design parameters and assumptions are noted as follows:

- Subcatchment areas were derived tributary to each surface inlet (catchbasin).
- Runoff coefficient for all subcatchments were determined using area weighting routine and based on actual hard and soft surface areas. Runoff coefficients were calculated from the impervious levels using the relationship $C = (IMP \times 0.7) + 0.20$.
- Subcatchment widths are determined using PCSWMM. A Flow-Path layer was created in PCSWMM, and flow paths were created for each subcatchment. The software averages the flow path lengths to calculate the subcatchment widths. The width is equal to the subcatchment area divided by the overland flow path length.
- 2-year, 3-hour Chicago storm used to review minor system design based on Rational Method.
- 3-hr, 2-year, 5-year, 100-year, and 100-year +20% storms were used to assess the impact of major event and determine peak flows and depth of runoff.

7.6 Rainfall Data

Rainfall used for stormwater modelling and calculations were based on data provided in the City of Ottawa's Sewer Design Guidelines (SDG002). Generation of storm hyetographs for use in hydraulic/hydraulic modelling were derived from the total rainfall depths for various storm durations noted in the **Table 7-3** below. Chicago storm distributions were established using PCSWMM's Design Storm Creator using a,b,c IDF parameters taken from Section 5.4.2 of the SDG002.

Table 7-3 : Summary of Rainfall Data (From City of Ottawa SDG002)

| Duration | Rainfall Amounts (mm) for Specified Return Period | | | | | |
|----------|---|--------|---------|---------|---------|----------|
| | 2-year | 5-year | 10-year | 25-year | 50-year | 100-year |
| 5 mins | 9.8 | 13.1 | 15.2 | 17.9 | 19.9 | 21.8 |
| 10 mins | 12.1 | 16.2 | 18.7 | 22.1 | 24.5 | 26.9 |
| 15 mins | 13.7 | 18.3 | 21.2 | 24.9 | 27.7 | 30.4 |
| 30 mins | 16.9 | 22.5 | 26.1 | 30.7 | 34.1 | 37.4 |
| 1 hour | 20.8 | 27.7 | 32.1 | 37.8 | 42.0 | 46.1 |
| 2 hours | 25.6 | 34.2 | 39.6 | 46.6 | 51.8 | 56.8 |
| 6 hours | 35.4 | 47.4 | 55.2 | 64.8 | 72.0 | 79.2 |
| 12 hours | 44.4 | 58.8 | 68.4 | 80.4 | 85.2 | 97.2 |
| 24 hours | 55.2 | 72.0 | 84.0 | 98.4 | 110.4 | 120.0 |

Four (4) storm events were modeled including:

- 3-hour 2-year Chicago storm. (10 min timestep), with total rainfall of 31.88mm.
- 3-hour 5-year Chicago storm. (10 min timestep), with total rainfall of 42.54mm.
- 3-hour 100-year Chicago storm. (10 min timestep), with total rainfall of 71.58mm.
- 3-hour 100-year + 20% Chicago storm. (10 min timestep), with total rainfall of 85.9mm.

7.7 Proposed Stormwater System

Stormwater runoff from the proposed site will drain from a combination of controlled and uncontrolled areas. A storm drainage plan is illustrated on Figure A1. A total of eleven (11) subcatchments (or drainage areas) are shown on this drawing with average runoff coefficients calculated for each drainage area. The stormwater works shall consist of the following elements:

- For Towers B1, B2, B3 and B4, Flow-control roof drains to be provided.
- Runoff from surface areas surrounding the proposed towers (S104) will be collected by area drains and discharge to internal drainage piping in the underground parking structure. This in turn discharges directly to an oil-grit separator manhole, prior to discharging to the Ottawa River.
- Runoff from the lower landscaped areas (S015 & S106) along the river front to the north will discharge into the Ottawa River by overland flow.
- Runoff from the lower landscaped areas (S100 & S101) along the Jeanne D' Arc Blvd will be collected by the proposed storm sewer system and discharge into the Ottawa River at new Outfall #2. Detailed discussions of modeled peak runoffs from S100 & S101 are included in **Section 7.11**.
- Runoff from the lower landscaped areas (S102 & S103) along east side of Tweddle Rd will be collected and conveyed by the street gutter on Tweddle Rd and eventually discharge to Ottawa River. Detailed discussions of modeled peak runoffs from S102 & S103 are included in **Section 7.12**.
- All roof area will utilize flow-controlled weirs and based on the roof areas an estimate of the number of roof drains was completed. WATTS ACCUTROL weirs were used to determine the total discharge rates from the roof areas based on the estimated number of drains. In addition, the total cumulative prism volumes on the roofs were calculated at a maximum permitted depth of 150mm. Information on the estimated 100-year volumes on each roof is provided in Table B20 – Summary of Roof Drains and Roof Storage
- Table B21 to Table B24 in **Appendix B**.

Drawing C401 shows the existing storm drainage area for the 3 existing culverts along Jeanne D'Arc Boulevard near the proposed site. The existing culvert at the intersection on Jeanne D'Arc Boulevard and Tweddle Road is proposed to be rerouted as shown on servicing plan drawing to allow for the proposed development and to maintain the existing storm drainage pattern.

7.8 Flow Attenuation & Storage

The attenuation of stormwater will be achieved by utilizing roof storage. Using the release rates estimated on the roofs to determine the 2-year, 5-year, and 100-year volumes that will occur for corresponding release rates.

Table B16 through **Table B19**, provide the storage volumes necessary on the roof to attenuate the controlled release rates. **Table B15** summarizes the combined controlled and uncontrolled flows leaving the subject site. A summary of release rates, storage volume requirements, and provided storage volumes are identified in **Table 7-4** below.

Table 7-4 – Summary of Post-Development Storage

| Area | Location | Release Rate (L/s) | | | Storage Required (m ³) | | | Available Storage (m ³) |
|--------------|---------------|--------------------|-------------|-------------|------------------------------------|-------------|--------------|-------------------------------------|
| | | 2-yr | 5-yr | 100-yr | 2-yr | 5-yr | 100-yr | |
| B1 | Tower B1 roof | 2.9 | 4.0 | 7.6 | 11.5 | 15.4 | 29.0 | 46.4 |
| B2 | Tower B2 roof | 2.9 | 4.0 | 7.6 | 11.5 | 15.4 | 29.0 | 46.4 |
| B3 | Tower B3 roof | 2.9 | 4.0 | 7.6 | 11.5 | 15.4 | 29.0 | 46.4 |
| B4 | Tower B4 roof | 2.9 | 4.0 | 7.6 | 9.0 | 12.1 | 22.9 | 39.5 |
| Total | | 11.7 | 16.0 | 30.3 | 43.4 | 58.2 | 109.9 | 178.7 |

7.9 Stormwater Model Results

Table 7-5 summarizes the modeled peak flows at Outfall #1, resulting from controlled roof drains (Tower B1, B2, B3, & B4), uncontrolled runoff from low raise roofs and landscaping area (S104), and overland flows from the landscaped area along river front (S105 & S106).

Table 7-5 : Summary of Post-Development Flows at Outfall #1

| Storm Event | Peak Flow (L/sec) at Outfall #1 |
|------------------------|---------------------------------|
| Chicago_3h_2yr | 222.4 |
| Chicago_3h_5yr | 320.4 |
| Chicago_3h_100yr | 572.7 |
| Chicago_3h_100yr + 20% | 687.9 |

7.10 Quality Control

As a total suspended solids (TSS) removal efficiency of 80% is required, it is proposed to provide an oil grit separator for quality control. The following summarizes the design parameters used in the sizing of the Stormceptor manhole.

Table 7-6 – Design Parameters Used for Oil Grit Separator Sizing

| Parameter | Value Used |
|---|---------------|
| Drainage Area | 1.05 hectares |
| Runoff Coefficient | 0.85 |
| Target TSS Removal Requirements | 80 % |
| Target Runoff Volume Capture | 90 % |
| Flow attenuation upstream of OG separator (taken as 100-yr discharge & storage upstream of OG) | none |
| Particle distribution | fine |

Output from the PCSWMM for Stormceptor program is provided in **Appendix E** for reference. A Stormceptor model **EF05** is necessary to meet the required TSS removal of 80%. The EF05 will provide an approximate TSS removal of 83%.

7.11 Jeanne-d’Arc Blvd Drainage Catchment

Urbanization is planned along Jeanne D’Arc Boulevard, as indicated on drawing #EJV-S00174-RWY-DWG-3915 received from the City. As a result of urbanization and proposed development at 1015 Tweddle Road, a storm sewer is proposed under Jeanne D’Arc Boulevard. To allow for the development, the existing culvert and associated upstream drainage area will need to be rerouted to discharge into the proposed storm sewer.

The proposed storm sewer system for Jeanne D’Arc Blvd includes 244 m of storm sewers, with diameter ranging from 300mm to 525 mm. the system also consists of three manholes, three catchbasins, and one outfall structure (Outfall #2). Additionally, the existing 375mm diameter CSP culvert crossing Jeanne-d’Arc Blvd west of Trim Rd will be connected to the proposed storm sewer.

The contributing drainage subcatchments to the Jeanne D’Arc storm sewer system are illustrated in **Figure A2** of **Appendix A**. Six (6) subcatchments have been identified and analyzed with average runoff coefficients calculated for each drainage area.

- Runoff from Jeanne-d’Arc Blvd Right-Of-Way (S200, S201, &S202).
- Runoff from the development site (S100 & S101).
- Runoff from the existing drainage subcatchments south of Jeanne-d’Arc Blvd (S202 & S203).

Inlet control devices (ICD) will be installed in the proposed catch basins of the Jeanne-d’Arc storm sewer system to manage flows and prevent ponding during the 2-year storm event. There are six (6) primary inlet control devices used in the City of Ottawa for the control of runoff at catchbasins. The standard ICD discharge rates at 1.2 m hydraulic head are 13.4 L/sec, 19.8 L/sec, 28.1 L/sec 36.7 L/sec, 53.2 L/sec and 70.8 L/sec for Pedro Plastics Type X, and IPEX Tempests Type A, B, C, D, and F respectively. Type A was selected for use at most locations based on its suitability for the estimate runoffs and to avoid surface ponding at the ROW and development areas.

Table 7-7 below summarizes the discharge rates of IPEX Tempests Type A inlet control devices used. Please refer to the Storm Drainage Plan and Site Servicing Plans for the ICD types at each catchbasin.

Table 7-7 : Discharge Rates for Standard IPEX Tempests Type A

| Head (m) | Discharge (L/s) |
|----------|-----------------|
| 0.00 | 0.0 |
| 0.10 | 5.7 |
| 0.20 | 8.1 |
| 0.30 | 9.9 |
| 0.40 | 11.5 |
| 0.50 | 12.8 |
| 0.60 | 14.0 |
| 0.70 | 15.1 |
| 0.80 | 16.2 |
| 0.90 | 17.2 |
| 1.00 | 18.1 |
| 1.20 | 19.8 |
| 1.40 | 21.4 |
| 1.60 | 22.9 |
| 1.80 | 24.3 |
| 2.00 | 25.6 |
| 2.50 | 28.6 |
| 3.00 | 31.4 |

The storm sewer system has been designed to convey the runoff up to the 2-year storm event. For larger storm events (e.g. 100-year), excess runoff is managed by the major system. This includes overland flow routes such as swales and streets, which will convey flows toward Tweddle Road and ultimately discharge into the Ottawa River.

The major system was modeled using irregular conduits based on a half-street cross-section. The transect editor in PCSWMM was used to establish this transect, which was applied to the majority of the major system.

Table 7-8 summarizes the modeled peak flows at Outfall #2. These flows include:

- Controlled runoff from Jeanne-d’Arc ROW (S200, S201, & S204),
- Uncontrolled runoffs from existing subcatchments south of Jeanne-d’Arc Blvd (S202 & S203), and
- Overland flows from the development site (S100 & S101).

Table 7-8 : Summary of Post-Development Flows at Outfall #2

| Storm Event | Peak Flow (L/sec) at Outfall #2 |
|------------------------|---------------------------------|
| Chicago_3h_2yr | 206.0 |
| Chicago_3h_5yr | 282.9 |
| Chicago_3h_100yr | 332.6 |
| Chicago_3h_100yr + 20% | 354.7 |

Figure 7-1 below illustrates a profile of the Jeanne-d'Arc storm sewer from its starting point to Outfall #2. Plotted on this figure is the 2-yr and 100-yr HGL.




Figure 7-1: Hydraulic Grade Lines of 2-yr and 100-yr Storms of Jeanne-d'Arc Storm Sewers

Based on this analysis, we can confirm that the Jeanne-d'Arc storm sewer system will handle the runoffs from the 2-year storm without surcharging, and the maximum 100-year HGL will increase but no significant impact on the sewer capacity.

7.12 Tweddle Road Drainage Catchment

In response to comments received during the pre-consultation meeting, Tweddle Road north of Jeanne-d’Arc Blvd will be re-constructed to reduce the longitudinal slope and provide access to proposed development at 1015 Tweddle Road.

Additionally, the existing 900 mm diameter culvert crossing Jeanne-d’Arc Blvd near Tweddle Rd will be removed. As a result, runoff from the existing drainage catchment located at the southeast corner of the intersection of Jeanne-d’Arc Blvd and Tweddle Rd will be redirected to the roadside ditch along south of Jeanne-d’Arc Blvd. a new 500mm diameter HDPE culvert will be installed to convey this flow across Tweddle Rd to the existing roadside ditch, ultimately discharging to the Ottawa River.

Six (6) subcatchments are shown on **Figure A3** with average runoff coefficients calculated for each drainage area.

- Runoff from the existing drainage subcatchment southeast of the intersection of Jeanne-d’Arc and Tweddle (S205), will be redirected to the existing roadside ditch east of Tweddle Rd and will be discharged to the Ottawa River at Taylor Creek outfall (Outfall #3). This will be facilitated by the installation of a 500 mm diameter HDPE culvert crossing Tweddle Rd.
- Runoff from the development site (S102 & S103) will overflow toward Tweddle Rd and discharge to the Ottawa River at Outfall #1A.
- Runoff from west half of Tweddle Rd (S300) will be collected by the street gutters and discharge to the Ottawa River at Outfall #4.
- Runoff from east half of Tweddle Rd (S301 & S303) will be collected by the street gutters and discharge to the Ottawa River at Outfall #1A.

Table 7-9 summarizes the modeled peak flows at the key outfalls under various design storm events.

Table 7-9 : Summary of Post-Development Flows at Outfalls #1A, 3, and 4

| Storm Event | Peak Flow (L/sec) | | |
|------------------------|-------------------|------------|------------|
| | Outfall #1A | Outfall #3 | Outfall #4 |
| Chicago_3h_2yr | 42.0 | 50.3 | 13.9 |
| Chicago_3h_5yr | 88.1 | 74.0 | 18.9 |
| Chicago_3h_100yr | 426.3 | 153.1 | 32.3 |
| Chicago_3h_100yr + 20% | 636.8 | 196.4 | 38.8 |

Figure 7-2 below illustrates flows and water depths at the proposed 500 mm diameter HDPE culvert crossing Tweddle Rd.




Figure 7-2: Flows and Water Depths at 500mm Culvert

Modeling results indicated that the proposed 500mm diameter HDPE culvert has sufficient capacity to convert runoffs from the drainage subcatchment to the existing road ditch west of Tweddle Rd.

8 Erosion & Sediment Control

During all construction activities, erosion and sedimentation shall be controlled by the following techniques:

- Filter cloth shall be installed between the frame and cover of all adjacent catch basins and catch basin manhole structures.
- Heavy duty silt fencing will be used to control runoff around the construction area. Silt fencing locations are identified on the site grading and erosion control plan.
- A mud mat will be installed at the construction entrance to help avoid mud from being transported to offsite roads.
- Visual inspection shall be completed daily on sediment control barriers and any damage repaired immediately. Care will be taken to prevent damage during construction operations.
- In some cases, barriers may be removed temporarily to accommodate the construction operations. The affected barriers will be reinstated at night when construction is completed.
- Sediment control devices will be cleaned of accumulated silt as required. The deposits will be disposed of as per the requirements of the contract.
- During the course of construction, if the engineer believes that additional prevention methods are required to control erosion and sedimentation, the contractor will install additional silt fences or other methods as required to the satisfaction of the engineer.
- Construction and maintenance requirements for erosion and sediment controls are to comply with Ontario Provincial Standard Specification (OPSS) OPSS 805 and City of Ottawa specifications.

9 Conclusions and Recommendations

This Functional Servicing & Stormwater Report outlines the rationale which will be used to service the proposed development. The following summarizes the servicing requirements for the site:

Water

- Two twin 200mm watermains are proposed to service the development, as the average day demands exceed 50 m³ per day, which is mandatory as per Section 4.31 of the WDG001.
- The Required Fire Flows (RFFs) were estimated at **7,000 L/min** (117 L/sec) for Tower B1, **7,000 L/min** (117 L/sec) for Tower B2, **7,000 L/min** (117 L/sec) for Tower B3 and **6,000 L/min** (100 L/sec) for Tower B4. The total minimum available flows for firefighting purposes, based on the contribution from hydrants, was estimated at **7,600 L/min, 15,200 L/min, 13,300 L/min and 9,500 L/min** for each building, respectively.
- Based on hydraulic boundary conditions (HGL) provided by the City of Ottawa, the maximum HGL indicates pressures greater than 80 psi, exceeding the City's guideline, therefore pressure reducing measures will be required.

Sewage

- Estimated peak sewage flows of **21.14 L/sec** are anticipated. A review of the sanitary sewers on Jeanne D'Arc Boulevard was completed. It was determined that the sanitary main between MHSA 22037 and MHSA 54993 will be re-routed and upsized from 300mm diameter to 375mm diameter pipes to match with the downstream pipes.

Stormwater

- Total pre-development discharge rate from the development area of the site was calculated based on a runoff coefficient of 0.29 and a time of concentration of 10 minutes. Pre-development discharge rates from the 1.28 ha development area were estimated to be **79.1 L/sec, 107.3 L/sec and 229.9 L/sec** during 2-year, 5-year and 100-year storm events, respectively.
- Post-development release rates were calculated by estimating C_{AVG} based on the proposed development. Post-development C_{AVG} for the 1.28 ha development was estimated to be 0.75. Post-development discharge rates from 1.28 ha development area were estimated to **151.9 L/sec, 206.1 L/sec and 437.8 L/sec** during 2-year, 50-year and 100-year storm events, respectively.
- The City did not impose onsite quantity control due to the proximity to the Ottawa River. This is contingent on using a direct connection to the river rather than discharging to a storm sewer. Although runoff does not need to be detained onsite, stormwater control and storage will be provided on building roof using flow control roof drains.
- Runoff on the building roofs will be controlled using flow-controlled roof drains. Each roof-drain is equipped with WATTS ACCUTROL weirs and set at the OPEN position and having maximum discharge rate of 30 gpm at 150mm depth. Each tower's roof will have 4 roof drains, resulting in a total combined maximum 100-year discharge rate of **30.4 L/sec** (Towers B1, B2, B3, B4). It was calculated that a total of **109.9m³** of storage will be required on the roofs to attain these flows.
- The remaining areas will not have flow controls with 100-yr anticipated peak flows of **407.5 L/sec**.
- An oil-grit separator (OG) is required to meet the TSS removal efficiency of 80%. A Stormceptor Model EF05 was selected which is estimated to have a removal efficiency of **83%**.

Legal Notification

This report was prepared by EXP Services Inc. for the account of Trim 1 GP Inc.

Any use which a third party makes of this report, or any reliance on or decisions to be made based on it, are the responsibility of such third parties. EXP Services Inc. accepts no responsibility for damages, if any, suffered by any third party as a result of decisions made or actions based on this project.

Appendix A – Figures

Figure A1 – Post-Development Subcatchments

Figure A2 – JDA Subcatchments

Figure A3 – Tweddle Subcatchments



FIG A1: POST-DEVELOPMENT SUBCATCHMENT



FIG A2: JDA SUB-CATCHMENTS



Appendix B – Design Tables

Table B1 – Water Demand Chart

Table B2 – Summary of Required Fire Flows (RFFs)

Table B3 – Fire Flow Requirements Based on Fire Underwriters Survey (FUS) – Tower B1

Table B4 – Fire Flow Requirements Based on Fire Underwriters Survey (FUS) – Tower B2

Table B5 – Fire Flow Requirements Based on Fire Underwriters Survey (FUS) – Tower B3

Table B6 – Fire Flow Requirements Based on Fire Underwriters Survey (FUS) – Tower B4

Table B7 – Fire Flow Requirements Based on Hydrant Spacing

Table B8 – Sanitary Sewer Design Sheet

Table B9 – Storm Sewer Design Sheet

Table B10 – Calculation of Average Runoff Coefficients for Pre-Development Conditions

Table B11 – Calculation of Catchment Time of Concentration for Pre-Development Conditions

Table B12 – Calculation of Peak Runoff for Pre-Development Conditions

Table B13 – Average Runoff Coefficients for Post-Development

Table B14 – Summary of Post-Development Peak Flows (Uncontrolled and Controlled)

Table B15 – Summary of Storage

Table B16 – Storage Volumes for 2-year, 5-year and 100-Year Storms (MRM) Tower B1

Table B17 – Storage Volumes for 2-year, 5-year and 100-Year Storms (MRM) Tower B2

Table B18 – Storage Volumes for 2-year, 5-year and 100-Year Storms (MRM) Tower B3

Table B19 – Storage Volumes for 2-year, 5-year and 100-Year Storms (MRM) Tower B4

Table B20 – Summary of Roof Drains and Roof Storage

Table B21 – Estimation of Roof Storage and Outflow – Tower B1

Table B22 – Estimation of Roof Storage and Outflow – Tower B2

Table B23 – Estimation of Roof Storage and Outflow – Tower B3

Table B24 – Estimation of Roof Storage and Outflow – Tower B4



TABLE B1: Water Demand Chart

[illegible]

TABLE B2

SUMMARY OF REQUIRED FIREFLOWS (RFFs)

| Building # | Description | ¹ No of Storeys | Fire Flow, F (L/min) | ² Type of Constr. Coeff, C | ³ Reduction Due to Occupancy (%) | ⁴ Reduction Due to Sprinklers (%) | ⁵ Total Increase due to Exposures (%) | ⁶ Required Fire Flow in | |
|------------|-----------------|----------------------------|----------------------|---------------------------------------|---|--|--|------------------------------------|---------|
| | | | | | | | | (L/min) | (L/sec) |
| Tower B1 | high-rise condo | 28 | 15,000 | 0.8 | -15% | -50% | 5% | 7,000 | 117 |
| Tower B2 | high-rise condo | 32 | 14,000 | 0.8 | -15% | -50% | 10% | 7,000 | 117 |
| Tower B3 | high-rise condo | 28 | 14,000 | 0.8 | -15% | -50% | 10% | 7,000 | 117 |
| Tower B4 | high-rise condo | 24 | 13,000 | 0.8 | -15% | -50% | 5% | 6,000 | 100 |

Notes

1 - If basements are included (<50% below grade) then denoted as +.

2 -Types of constructions: 0.8 for non-combustible, 1.0 for ordinary construction, 1.5 for wood frame construction.

3 - Reductions due to Occupancy are -25% for non-combustible or -15% for limited combustible.

4 - Reductions due to Sprinkler Systems

5 – Increase due to exposures were calculated based on FUS 2020.

6 – Required Fire Flows are rounded to nearest 1,000 L/min.

TABLE B3 (Tower B1
FIRE FLOW REQUIEIMENTS BASED ON FIRE UNDERWRITERS SURVEY(FUS) 2020
PROJECT: 1015 Tweddle Road
Building No: Tower B1



An estimate of the Fire Flow required for a given fire area may be estimated by:

F = 220 * C * SQRT(A)

where: F = required fire flow in litres per minute
A = total floor area in m² (including all storeys, but excluding basements at least 50% below grade)
C = coefficient related to the type of construction

| Task | Options | Multiplier | Input | | | | Value Used | Fire Flow Total (L/min) |
|--------------------------------|---|------------|------------------------------|--------|-----------|--|-----------------------|-------------------------|
| Choose Building Frame (C) | Wood Frame | 1.5 | Non-combustible Construction | | | | 0.8 | |
| | Ordinary Construction | 1 | | | | | | |
| | Non-combustible Construction | 0.8 | | | | | | |
| | Fire Resistive Construction | 0.6 | | | | | | |
| Input Building Floor Areas (A) | | | Area | % Used | Area Used | Comment | 6982.0 m ² | |
| | Floor 11 to 28 | | 928.0 | 0 | 0.0 | Two largest adjoining floors + 50% of floors above (up to eight) | | |
| | Floor 10 | | 928.0 | 50% | 464.0 | | | |
| | Floor 9 | | 928.0 | 50% | 464.0 | | | |
| | Floor 8 | | 928.0 | 50% | 464.0 | | | |
| | Floor 7 | | 928.0 | 50% | 464.0 | | | |
| | Floor 6 | | 928.0 | 50% | 464.0 | | | |
| | Floor 5 | | 928.0 | 50% | 464.0 | | | |
| | Floor 4 | | 928.0 | 50% | 464.0 | | | |
| | Floor 3 | | 928.0 | 50% | 464.0 | | | |
| | Floor 2 | | 1570.0 | 100% | 1570.0 | | | |
| | Floor 1 (Main Level) | | 1700.0 | 100% | 1700.0 | | | |
| | Basement (At least 50% below grade, not included) | | | 0% | 0.0 | | | |
| Fire Flow (F) | F = 220 * C * SQRT(A) | | | | | | | 14,706 |
| Fire Flow (F) | Rounded to nearest 1,000 | | | | | | | 15,000 |

Reductions/Increases Due to Factors Effecting Burning

| Task | Options | Multiplier | | | Input | | | | | Value Used | Fire Flow Change (L/min) | Fire Flow Total (L/min) | |
|--|--|---------------------|------|---------------------|--|---------------------|---------------|----------------------|--------------|------------|--------------------------|-------------------------------|-------|
| Choose Combustibility of Building Contents | Non-combustible | -25% | | | Limited Combustible | | | | | -15% | -2,250 | 12,750 | |
| | Limited Combustible | -15% | | | | | | | | | | | |
| | Combustible | 0% | | | | | | | | | | | |
| | Free Burning | 15% | | | | | | | | | | | |
| | Rapid Burning | 25% | | | | | | | | | | | |
| Choose Reduction Due to Sprinkler System | Adequate Sprinkler Conforms to NFPA13 | -30% | | | Adequate Sprinkler Conforms to NFPA13 | | | | | -30% | -3,825 | 8,925 | |
| | No Sprinkler | 0% | | | Standard Water Supply for Fire Department Hose Line and for Sprinkler System | | | | | -10% | -1,275 | 7,650 | |
| | Standard Water Supply for Fire Department Hose Line and for Sprinkler System | -10% | | | | | | | | | | | |
| | Not Standard Water Supply or Unavailable | 0% | | | | | | | | | | | |
| | Fully Supervised Sprinkler System | -10% | | | | | | | | | | | |
| | Not Fully Supervised or N/A | 0% | | | Fully Supervised Sprinkler System | | | | | -10% | -1,275 | 6,375 | |
| Choose Structure Exposure Distance | Exposures | Separation Dist (m) | Cond | Separation Conditon | Exposed Wall type | Exposed Wall Length | | | | | | | |
| | | | | | | Length (m) | No of Storeys | Length-Height Factor | Sub-Conditon | Charge (%) | Total Charge (%) | Total Exposure Charge (L/min) | |
| | Side 1 (west) | 46 | 5 | 30.1 to 45 | Type IV-III (U) | 0 | 0 | 0 | 6 | 0% | 5% | 638 | 7,013 |
| | Side 2 (east) | 25 | 4 | 20.1 to 30 | Type IV-III (U) | 38 | 28 | 1064 | 4F | 5% | | | |
| | Front (north) | 46 | 5 | 30.1 to 45 | Type IV-III (U) | 0 | 0 | 0 | 6 | 0% | | | |
| | Back (south) | 46 | 5 | 30.1 to 45 | Type IV-III (U) | 0 | 0 | 0 | 6 | 0% | | | |
| Obtain Required Fire Flow | Total Required Fire Flow, Rounded to the Nearest 1,000 L/min = | | | | | | | | | | | 7,000 | |
| | Total Required Fire Flow, L/s = | | | | | | | | | | | 117 | |

Exposure Charges for Exposing Walls of Wood Frame Construciton (from Table G5)

| | |
|-----------------|--|
| Type V | Wood Frame |
| Type IV-III (U) | Mass Timber or Ordinary with Unprotected Openings |
| Type IV-III (P) | Mass Timber or Ordinary with Protected Openings |
| Type II-I (U) | Noncombustible or Fire Resistive with Unprotected Openings |
| Type II-I (P) | Noncombustible or Fire Resistive with Protected Openings |

Conditons for Separation

| Separation Dist | Condition |
|-----------------|-----------|
| 0m to 3m | 1 |
| 3.1m to 10m | 2 |
| 10.1m to 20m | 3 |
| 20.1m to 30m | 4 |
| > 30.1m | 5 |

TABLE B4 (Tower B2)
FIRE FLOW REQUIREMENTS BASED ON FIRE UNDERWRITERS SURVEY(FUS) 2020
PROJECT: 1015 Tweddle Road
Building No: Tower B2



An estimate of the Fire Flow required for a given fire area may be estimated by:

F = 220 * C * SQRT(A)

where: F = required fire flow in litres per minute
A = total floor area in m² (including all storeys, but excluding basements at least 50% below grade)
C = coefficient related to the type of construction

| Task | Options | Multiplier | Input | | | | Value Used | Fire Flow Total (L/min) |
|--------------------------------|---|-----------------------|------------------------------|--------|-----------|--|------------|-------------------------|
| Choose Building Frame (C) | Wood Frame | 1.5 | Non-combustible Construction | | | | 0.8 | |
| | Ordinary Construction | 1 | | | | | | |
| | Non-combustible Construction | 0.8 | | | | | | |
| | Fire Resistive Construction | 0.6 | | | | | | |
| Input Building Floor Areas (A) | | | Area | % Used | Area Used | Comment | 6668.0 m² | |
| | Floor 11 to 32 | | 928.0 | 0 | 0.0 | Two largest adjoining floors + 50% of floors above (up to eight) | | |
| | Floor 10 | | 928.0 | 50% | 464.0 | | | |
| | Floor 9 | | 928.0 | 50% | 464.0 | | | |
| | Floor 8 | | 928.0 | 50% | 464.0 | | | |
| | Floor 7 | | 928.0 | 50% | 464.0 | | | |
| | Floor 6 | | 928.0 | 50% | 464.0 | | | |
| | Floor 5 | | 928.0 | 50% | 464.0 | | | |
| | Floor 4 | | 928.0 | 50% | 464.0 | | | |
| | Floor 3 | | 928.0 | 50% | 464.0 | | | |
| | Floor 2 | | 1478.0 | 100% | 1478.0 | | | |
| | Floor 1 (Main Level) | | 1478.0 | 100% | 1478.0 | | | |
| | Basement (At least 50% below grade, not included) | | | 0% | 0.0 | | | |
| | Fire Flow (F) | F = 220 * C * SQRT(A) | | | | | | |
| Fire Flow (F) | Rounded to nearest 1,000 | | | | | | | 14,000 |

Reductions/Increases Due to Factors Effecting Burning

| Task | Options | Multiplier | | | Input | | | | | Value Used | Fire Flow Change (L/min) | Fire Flow Total (L/min) | |
|--|--|---------------------|------|---------------------|--|---------------------|---------------|----------------------|---------------|------------|--------------------------|-------------------------------|-------|
| Choose Combustibility of Building Contents | Non-combustible | -25% | | | Limited Combustible | | | | | -15% | -2,100 | 11,900 | |
| | Limited Combustible | -15% | | | | | | | | | | | |
| | Combustible | 0% | | | | | | | | | | | |
| | Free Burning | 15% | | | | | | | | | | | |
| | Rapid Burning | 25% | | | | | | | | | | | |
| Choose Reduction Due to Sprinkler System | Adequate Sprinkler Conforms to NFPA13 | -30% | | | Adequate Sprinkler Conforms to NFPA13 | | | | | -30% | -3,570 | 8,330 | |
| | No Sprinkler | 0% | | | | | | | | | | | |
| | Standard Water Supply for Fire Department Hose Line and for Sprinkler System | -10% | | | Standard Water Supply for Fire Department Hose Line and for Sprinkler System | | | | | -10% | -1,190 | 7,140 | |
| | Not Standard Water Supply or Unavailable | 0% | | | | | | | | | | | |
| | Fully Supervised Sprinkler System | -10% | | | Fully Supervised Sprinkler System | | | | | -10% | -1,190 | 5,950 | |
| | Not Fully Supervised or N/A | 0% | | | | | | | | | | | |
| Choose Structure Exposure Distance | Exposures | Separation Dist (m) | Cond | Separation Conditon | Exposed Wall type | Exposed Wall Length | | | | | | | |
| | | | | | | Length (m) | No of Storeys | Length-Height Factor | Sub- Conditon | Charge (%) | Total Charge (%) | Total Exposure Charge (L/min) | |
| | Side 1 (west) | 25 | 4 | 20.1 to 30 | Type IV-III (U) | 42 | 28 | 1176 | 4F | 5% | 10% | 1,190 | 7,140 |
| | Side 2 (east) | 25.6 | 4 | 20.1 to 30 | Type IV-III (U) | 40 | 28 | 1120 | 4F | 5% | | | |
| | Front (north) | 46 | 5 | 30.1 to 45 | Type IV-III (U) | 0 | 0 | 0 | 6 | 0% | | | |
| | Back (south) | 46 | 5 | 30.1 to 45 | Type IV-III (U) | 0 | 0 | 0 | 6 | 0% | | | |
| Obtain Required Fire Flow | Total Required Fire Flow, Rounded to the Nearest 1,000 L/min = | | | | | | | | | | | 7,000 | |
| | Total Required Fire Flow, L/s = | | | | | | | | | | | 117 | |

Exposure Charges for Exposing Walls of Wood Frame Construciton (from Table G5)

Type V Wood Frame
Type IV-III (U) Mass Timber or Ordinary with Unprotected Openings
Type IV-III (P) Mass Timber or Ordinary with Protected Openings
Type II-I (U) Noncombustible or Fire Resistive with Unprotected Openings
Type II-I (P) Noncombustible or Fire Resistive with Protected Openings

Conditons for Separation

| Separation Dist | Condition |
|-----------------|-----------|
| 0m to 3m | 1 |
| 3.1m to 10m | 2 |
| 10.1m to 20m | 3 |
| 20.1m to 30m | 4 |
| > 30.1m | 5 |

TABLE B5 (Tower B3)
FIRE FLOW REQUIEIMENTS BASED ON FIRE UNDERWRITERS SURVEY(FUS) 2020
PROJECT: 1015 Tweddle Road
Building No: Tower B3



An estimate of the Fire Flow required for a given fire area may be estimated by:

F = 220 * C * SQRT(A)

where: F = required fire flow in litres per minute
A = total floor area in m² (including all storeys, but excluding basements at least 50% below grade)
C = coefficient related to the type of construction

| Task | Options | Multiplier | Input | | | | Value Used | Fire Flow Total (L/min) |
|--------------------------------|---|------------|------------------------------|--------|-----------|--|------------|-------------------------|
| Choose Building Frame (C) | Wood Frame | 1.5 | Non-combustible Construction | | | | 0.8 | |
| | Ordinary Construction | 1 | | | | | | |
| | Non-combustible Construction | 0.8 | | | | | | |
| | Fire Resistive Construction | 0.6 | | | | | | |
| Input Building Floor Areas (A) | | | Area | % Used | Area Used | Comment | 6730.0 m² | |
| | Floor 11 to 28 | | 928.0 | 0 | 0.0 | Two largest adjoining floors + 50% of floors above (up to eight) | | |
| | Floor 10 | | 928.0 | 50% | 464.0 | | | |
| | Floor 9 | | 928.0 | 50% | 464.0 | | | |
| | Floor 8 | | 928.0 | 50% | 464.0 | | | |
| | Floor 7 | | 928.0 | 50% | 464.0 | | | |
| | Floor 6 | | 928.0 | 50% | 464.0 | | | |
| | Floor 5 | | 928.0 | 50% | 464.0 | | | |
| | Floor 4 | | 928.0 | 50% | 464.0 | | | |
| | Floor 3 | | 928.0 | 50% | 464.0 | | | |
| | Floor 2 | | 1405.0 | 100% | 1405.0 | | | |
| | Floor 1 (Main Level) | | 1613.0 | 100% | 1613.0 | | | |
| | Basement (At least 50% below grade, not included) | | | 0% | 0.0 | | | |
| Fire Flow (F) | F = 220 * C * SQRT(A) | | | | | | | 14,438 |
| Fire Flow (F) | Rounded to nearest 1,000 | | | | | | | 14,000 |

Reductions/Increases Due to Factors Effecting Burning

| Task | Options | Multiplier | | | Input | | | | | Value Used | Fire Flow Change (L/min) | Fire Flow Total (L/min) | |
|--|--|---------------------|------|---------------------|--|---------------------|---------------|----------------------|--------------|------------|--------------------------|-------------------------------|-------|
| Choose Combustibility of Building Contents | Non-combustible | -25% | | | Limited Combustible | | | | | -15% | -2,100 | 11,900 | |
| | Limited Combustible | -15% | | | | | | | | | | | |
| | Combustible | 0% | | | | | | | | | | | |
| | Free Burning | 15% | | | | | | | | | | | |
| | Rapid Burning | 25% | | | | | | | | | | | |
| Choose Reduction Due to Sprinkler System | Adequate Sprinkler Conforms to NFPA13 | -30% | | | Adequate Sprinkler Conforms to NFPA13 | | | | | -30% | -3,570 | 8,330 | |
| | No Sprinkler | 0% | | | | | | | | | | | |
| | Standard Water Supply for Fire Department Hose Line and for Sprinkler System | -10% | | | Standard Water Supply for Fire Department Hose Line and for Sprinkler System | | | | | -10% | -1,190 | 7,140 | |
| | Not Standard Water Supply or Unavailable | 0% | | | | | | | | | | | |
| | Fully Supervised Sprinkler System | -10% | | | Fully Supervised Sprinkler System | | | | | -10% | -1,190 | 5,950 | |
| | Not Fully Supervised or N/A | 0% | | | | | | | | | | | |
| Choose Structure Exposure Distance | Exposures | Separation Dist (m) | Cond | Separation Conditon | Exposed Wall type | Exposed Wall Length | | | | | | | |
| | | | | | | Length (m) | No of Storeys | Length-Height Factor | Sub-Conditon | Charge (%) | Total Charge (%) | Total Exposure Charge (L/min) | |
| | Side 1 (west) | 25.6 | 4 | 20.1 to 30 | Type IV-III (U) | 31 | 28 | 868 | 4F | 5% | 10% | 1,190 | 7,140 |
| | Side 2 (east) | 22 | 4 | 20.1 to 30 | Type IV-III (U) | 26 | 24 | 624 | 4F | 5% | | | |
| | Front (north) | 46 | 5 | 30.1 to 45 | Type IV-III (U) | 0 | 0 | 0 | 6 | 0% | | | |
| | Back (south) | 46 | 5 | 30.1 to 45 | Type IV-III (U) | 0 | 0 | 0 | 6 | 0% | | | |
| Obtain Required Fire Flow | Total Required Fire Flow, Rounded to the Nearest 1,000 L/min = | | | | | | | | | | | 7,000 | |
| | Total Required Fire Flow, L/s = | | | | | | | | | | | 117 | |

Exposure Charges for Exposing Walls of Wood Frame Construciton (from Table G5)

| | |
|-----------------|--|
| Type V | Wood Frame |
| Type IV-III (U) | Mass Timber or Ordinary with Unprotected Openings |
| Type IV-III (P) | Mass Timber or Ordinary with Protected Openings |
| Type II-I (U) | Noncombustible or Fire Resistive with Unprotected Openings |
| Type II-I (P) | Noncombustible or Fire Resistive with Protected Openings |

Conditons for Separation

| Separation Dist | Condition |
|-----------------|-----------|
| 0m to 3m | 1 |
| 3.1m to 10m | 2 |
| 10.1m to 20m | 3 |
| 20.1m to 30m | 4 |
| > 30.1m | 5 |

TABLE B6 (Tower B4)
FIRE FLOW REQUIEIMENTS BASED ON FIRE UNDERWRITERS SURVEY(FUS) 2020
PROJECT: 1015 Tweddle Road
Building No: Tower B4



An estimate of the Fire Flow required for a given fire area may be estimated by:

F = 220 * C * SQRT(A)

where: F = required fire flow in litres per minute
A = total floor area in m² (including all storeys, but excluding basements at least 50% below grade)
C = coefficient related to the type of construction

| Task | Options | Multiplier | Input | | | | Value Used | Fire Flow Total (L/min) |
|--------------------------------|---|------------|------------------------------|--------|-----------|--|------------|-------------------------|
| Choose Building Frame (C) | Wood Frame | 1.5 | Non-combustible Construction | | | | 0.8 | |
| | Ordinary Construction | 1 | | | | | | |
| | Non-combustible Construction | 0.8 | | | | | | |
| | Fire Resistive Construction | 0.6 | | | | | | |
| Input Building Floor Areas (A) | | | Area | % Used | Area Used | Comment | 5279.0 m² | |
| | Floor 11 to 28 | | 900.0 | 0 | 0.0 | Two largest adjoining floors + 50% of floors above (up to eight) | | |
| | Floor 10 | | 900.0 | 50% | 450.0 | | | |
| | Floor 9 | | 900.0 | 50% | 450.0 | | | |
| | Floor 8 | | 900.0 | 50% | 450.0 | | | |
| | Floor 7 | | 900.0 | 50% | 450.0 | | | |
| | Floor 6 | | 900.0 | 50% | 450.0 | | | |
| | Floor 5 | | 900.0 | 50% | 450.0 | | | |
| | Floor 4 | | 900.0 | 50% | 450.0 | | | |
| | Floor 3 | | 900.0 | 50% | 450.0 | | | |
| | Floor 2 | | 897.0 | 100% | 897.0 | | | |
| | Floor 1 (Main Level) | | 782.0 | 100% | 782.0 | | | |
| | Basement (At least 50% below grade, not included) | | | 0% | 0.0 | | | |
| Fire Flow (F) | F = 220 * C * SQRT(A) | | | | | | | 12,788 |
| Fire Flow (F) | Rounded to nearest 1,000 | | | | | | | 13,000 |

Reductions/Increases Due to Factors Effecting Burning

| Task | Options | Multiplier | | | Input | | | | | Value Used | Fire Flow Change (L/min) | Fire Flow Total (L/min) | |
|--|--|---------------------|------|---------------------|--|---------------------|---------------|----------------------|---------------|------------|--------------------------|-------------------------------|-------|
| Choose Combustibility of Building Contents | Non-combustible | -25% | | | Limited Combustible | | | | | -15% | -1,950 | 11,050 | |
| | Limited Combustible | -15% | | | | | | | | | | | |
| | Combustible | 0% | | | | | | | | | | | |
| | Free Burning | 15% | | | | | | | | | | | |
| | Rapid Burning | 25% | | | | | | | | | | | |
| Choose Reduction Due to Sprinkler System | Adequate Sprinkler Conforms to NFPA13 | -30% | | | Adequate Sprinkler Conforms to NFPA13 | | | | | -30% | -3,315 | 7,735 | |
| | No Sprinkler | 0% | | | Standard Water Supply for Fire Department Hose Line and for Sprinkler System | | | | | -10% | -1,105 | 6,630 | |
| | Standard Water Supply for Fire Department Hose Line and for Sprinkler System | -10% | | | | | | | | | | | |
| | Not Standard Water Supply or Unavailable | 0% | | | | | | | | | | | |
| | Fully Supervised Sprinkler System | -10% | | | | | | | | | | | |
| | Not Fully Supervised or N/A | 0% | | | Fully Supervised Sprinkler System | | | | | -10% | -1,105 | 5,525 | |
| Choose Structure Exposure Distance | Exposures | Separation Dist (m) | Cond | Separation Conditon | Exposed Wall type | Exposed Wall Length | | | | | | | |
| | | | | | | Length (m) | No of Storeys | Length-Height Factor | Sub- Conditon | Charge (%) | Total Charge (%) | Total Exposure Charge (L/min) | |
| | Side 1 (west) | 46 | 4 | 20.1 to 30 | Type IV-III (U) | 35 | 24 | 840 | 4F | 5% | 5% | 553 | 6,078 |
| | Side 2 (east) | 25 | 5 | 30.1 to 45 | Type IV-III (U) | 0 | 0 | 0 | 6 | 0% | | | |
| | Front (north) | 46 | 5 | 30.1 to 45 | Type IV-III (U) | 0 | 0 | 0 | 6 | 0% | | | |
| | Back (south) | 46 | 5 | 30.1 to 45 | Type IV-III (U) | 0 | 0 | 0 | 6 | 0% | | | |
| Obtain Required Fire Flow | Total Required Fire Flow, Rounded to the Nearest 1,000 L/min = | | | | | | | | | | | 6,000 | |
| | Total Required Fire Flow, L/s = | | | | | | | | | | | 100 | |

Exposure Charges for Exposing Walls of Wood Frame Construciton (from Table G5)

| | |
|-----------------|--|
| Type V | Wood Frame |
| Type IV-III (U) | Mass Timber or Ordinary with Unprotected Openings |
| Type IV-III (P) | Mass Timber or Ordinary with Protected Openings |
| Type II-I (U) | Noncombustible or Fire Resistive with Unprotected Openings |
| Type II-I (P) | Noncombustible or Fire Resistive with Protected Openings |

Conditons for Separation

| Separation Dist | Condition |
|-----------------|-----------|
| 0m to 3m | 1 |
| 3.1m to 10m | 2 |
| 10.1m to 20m | 3 |
| 20.1m to 30m | 4 |
| > 30.1m | 5 |

FIRE FLOW REQUIREMENTS BASED ON HYDRANT SPACING

FIRE FLOW REQUIREMENTS BASED ON HYDRANT SPACING

TABLE B8
SANITARY SEWER CALCULATION SHEET

| LOCATION | | | | RESEDENTIAL AREAS AND POPULAITONS | | | | | | | | | | | | | | COMMERCIAL | | | | | INFILTRATION | | | TOTAL FLOW (L/s) | SEWER DATA | | | | | | | | |
|---|-----------|-----------|------------|-----------------------------------|-------------------|-----------------|-------|------------------------------------|---------------|---------------|---------------------|----------------------|---------------|----------------|------------|---|----------------|-------------------------|-----------|--------------|---------------|------------------------|-------------------------|---|--------|------------------------|-------------------------|---|-----------------------|------|--------------|---------------|---------------------|---------------------------|---------------------------|
| Street | U/S MH | D/S MH | Desc | Area (ha) | ACCU Area (ha) | NUMBER OF UNITS | | | | | | | | Total Units | POPULATION | | Peak Factor | Peak Flow (L/sec) | AREA (ha) | | | Comm Peak Factor | Peak Flow (L/sec) | AREA (ha) | | | INFILT FLOW (L/s) | Nom Dia (mm) | Actual Dia (mm) | Type | Slope (%) | Length (m) | Capacity (L/sec) | Q/Q _{CAP} (%) | Full Velocity (m/s) |
| | | | | | | Single | Semis | Towns | Batch Apt. | 1-Bed Apt. | 1-Bed + Den Apt. | 2-Bed Apt. | 3-Bed Apt. | | INDIV | ACCU | | | INDIV | ACCU | % of total | | | INDIV | ACCU | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Petrie's Landing | | MHSA54989 | Towers 1-6 | | 3.919 | | | | 132 | 721 | | 365 | 14 | 1232 | 2004.1 | 2004.1 | 3.07 | 19.94 | 0.301 | 0.301 | 8% | 1.0 | 0.10 | 3.92 | 3.919 | 1.29 | 21.33 | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Jeane D'Arc Blvd North | MHSA54989 | MHSA54990 | | | 3.919 | | | | | | | | | | 2004.1 | 3.07 | 19.94 | | 0.301 | | | | | 3.919 | 1.29 | 21.23 | 300 | 299.36 | PVC | 0.15 | 79.36 | 37.24 | 0.57 | 0.52 | |
| | MHSA54990 | MHSA54991 | | | 3.919 | | | | | | | | | | 2004.1 | 3.07 | 19.94 | | 0.301 | | | | | 3.919 | 1.29 | 21.23 | 300 | 299.36 | PVC | 0.29 | 34.70 | 51.62 | 0.41 | 0.73 | |
| | MHSA54991 | MHSA54992 | | | 3.919 | | | | | | | | | | 2004.1 | 3.07 | 19.94 | | 0.301 | | | | | 3.919 | 1.29 | 21.23 | 300 | 299.36 | PVC | 0.16 | 85.00 | 39.02 | 0.54 | 0.55 | |
| | MHSA54992 | SAMH101 | EXT-1 | 1.1350 | 5.054 | | | | | | | | | | 2004.10 | 3.07 | 19.94 | | 0.301 | | | | 1.135 | 5.054 | 1.67 | 21.61 | | | | | | | | | |
| | | | EXT-2 | 4.8806 | 9.934 | | | | | | | | | | 2004.10 | 3.07 | 19.94 | 4.881 | 5.182 | 49% | 1.5 | 2.52 | 4.881 | 9.934 | 3.28 | 25.74 | | | | | | | | | |
| | | | Towers B4 | 0.3204 | 10.2548 | | | | | 51 | 167 | 105 | 1 | 324 | 528.8 | 2532.90 | 3.00 | 24.63 | | 5.182 | | | | 0.320 | 10.255 | 3.38 | 28.01 | | | | | | | | |
| | | | Towers B3 | 0.2196 | 10.4744 | | | | | | 144 | 92 | | 236 | 394.8 | 2927.70 | 2.96 | 28.08 | 0.123 | 5.305 | 56% | 1.5 | 2.58 | 0.220 | 10.474 | 3.46 | 34.12 | 375 | 388.62 | PVC | 0.15 | 26.18 | 74.68 | 0.46 | 0.62 |
| | SAMH101 | SAMH100 | Towers B2 | 0.3153 | 10.7897 | | | | | 62 | 186 | 123 | 1 | 372 | 608.6 | 3536.30 | 2.90 | 33.23 | 0.148 | 5.453 | 47% | 1.5 | 2.65 | 0.315 | 10.790 | 3.56 | 39.45 | | | | | | | | |
| | | | Towers B1 | 0.4224 | 11.2121 | | | | | 53 | 163 | 107 | 3 | 326 | 536.4 | 4072.70 | 2.86 | 37.75 | 0.149 | 5.602 | 35% | 1.5 | 2.72 | 0.422 | 11.212 | 3.70 | 44.17 | 375 | 388.62 | PVC | 0.17 | 71.30 | 79.51 | 0.56 | 0.67 |
| | SAMH100 | MHSA22037 | | | 11.2121 | | | | | | | | | | 4072.70 | 2.86 | 37.75 | | 5.602 | | | | | 11.212 | 3.70 | 41.45 | 375 | 388.62 | PVC | 0.16 | 24.85 | 77.13 | 0.54 | 0.65 | |
| | MHSA22037 | MHSA22036 | | | 11.2121 | | | | | | | | | | 4072.7 | 2.86 | 37.75 | | 5.602 | | | | | 11.212 | 3.70 | 41.45 | 375 | 381 | CONC | 0.30 | 44.00 | 100.18 | 0.41 | 0.87 | |
| | MHSA22036 | MHSA22035 | | | 11.2121 | | | | | | | | | | 4072.7 | 2.86 | 37.75 | | 5.602 | | | | | 11.212 | 3.70 | 41.45 | 375 | 381 | CONC | 0.30 | 104.40 | 100.18 | 0.41 | 0.87 | |
| | MHSA22035 | MHSA22028 | | | 11.2121 | | | | | | | | | | 4072.7 | 2.86 | 37.75 | | 5.602 | | | | | 11.212 | 3.70 | 41.45 | 375 | 381 | CONC | 0.31 | 104.50 | 101.84 | 0.41 | 0.89 | |
| | MHSA22028 | MHSA22027 | | | 11.2121 | | | | | | | | | | 4072.7 | 2.86 | 37.75 | | 5.602 | | | | | 11.212 | 3.70 | 41.45 | 375 | 381 | CONC | 0.38 | 5.30 | 112.75 | 0.37 | 0.98 | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | 11.2121 | | | | | 132 | 887 | 660 | 792 | 19 | 2490 | 4072.7 | | | | 5.602 | | | | | 11.212 | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | 843.9 | | | | | | | | | |
| Residential Avg. Daily Flow, q (L/p/day) = | | | | 280 | | | | Commercial Peak Factor = | | | | 1.5 (when area >20%) | | | | Peak Population Flow, (L/sec) = | | | | Persons/Unit | | | | Designed: | | | | Project: | | | | | | | |
| Commercial Avg. Daily Flow (L/gross ha/day) = | | | | 28,000 | | | | | | | | 1.0 (when area <20%) | | | | Peak Extraneous Flow, (L/sec) = | | | | 3.4 | | | | Jason Fitzpatrick, P.Eng. | | | | 1015 Tweddle Road (Formerly 1009 Trim Road) | | | | | | | |
| or L/gross ha/sec = | | | | 0.324 | | | | | | | | | | | | Residential Peaking Factor, M = | | | | 5.7 | | | | | | | | | | | | | | | |
| Institutional Avg. Daily Flow (L/s/ha) = | | | | 28,000 | | | | Institutional Peak Factor = | | | | 1.5 (when area >20%) | | | | A _c = Cumulative Area (hectares) | | | | 2.7 | | | | Checked: | | | | Location: | | | | | | | |
| or L/gross ha/sec = | | | | 0.324 | | | | | | | | 1.0 (when area <20%) | | | | P = Population (thousands) | | | | 1.4 | | | | | | | | | | | | | | | |
| Light Industrial Flow (L/gross ha/day) = | | | | 35,000 | | | | | | | | | | | | | | | | 1.4 | | | | Bruce Thomas, P.Eng. | | | | Ottawa, Ontario | | | | | | | |
| or L/gross ha/sec = | | | | 0.405092593 | | | | Residential Correction Factor, K = | | | | 0.80 | | | | | | | | 1.4 | | | | | | | | | | | | | | | |
| Light Industrial Flow (L/gross ha/day) = | | | | 55,000 | | | | Manning N = | | | | 0.013 | | | | | | | | 2.1 | | | | File Reference: | | | | Page No: | | | | | | | |
| or L/gross ha/sec = | | | | 0.637 | | | | Peak extraneous flow, I (L/s/ha) = | | | | 0.33 (Total I/I) | | | | | | | | 3.1 | | | | 259629 Sanitary - Sewer Design Sheet, May 2025.xlsx | | | | 1 of 1 | | | | | | | |

Notes
0.59 Existing sewer runs with velocity less than 0.60 m/sec (Section 6.1.2.2 of SDG002)

TABLE B9
STORM SEWER CALCULATION SHEET

Return Period Storm =
Default Inlet Time=
Default Inlet Time=
Manning Coefficient =

2-year

10
15
0.013

(frontyard/row)
(rearyard)

| Street | Storm MH No: | | AREA INFO | | | | PEAK FLOWS (UNRESTRICTED - RATIONAL METHOD) | | | | | | | SEWER DATA | | | | | | | | | | | | | | | | | |
|--|--------------|------|---------------|-----------|------------------|-----------------|---|-----------------|-----------|----------|-------------|---------------|---------|------------------------|-----|------|-----------|------------|------------------------------------|----------------|------|------------------------|--------------------|---|--|--|--|--|-----------|--|--|
| | U/S | D/S | Catchment No: | Area (ha) | Accum. Area (ha) | Runoff Coeff, C | Indiv. 2.78*A*R | Accum. 2.78*A*R | Tc (mins) | I (mm/h) | Indiv. Flow | Return Period | Q (L/s) | Diameter (mm) | | Type | Slope (%) | Length (m) | Capacity, Q _{CAP} (L/sec) | Velocity (m/s) | | Time in Pipe, Tt (min) | Hydraulic Ratios | | | | | | | | |
| | | | | | | | | | | | | | | Act | Nom | | | | | Vf | Va | | Q/Q _{CAP} | Va/Vf | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Jeane D'Arc Blvd | ndn | 201 | S200 | 0.2265 | 0.2265 | 0.71 | 0.4471 | 0.4471 | 10.00 | 76.81 | 34.3 | 2-year | 34.3 | | | | | | | | | | | | | | | | | | |
| | | | S100 | 0.0691 | 0.2956 | 0.63 | 0.1210 | 0.5681 | 10.00 | 76.81 | 9.3 | 2-year | 43.6 | 299.4 | 300 | PVC | 0.65 | 72.00 | 77.52 | 1.10 | 0.78 | 1.54 | 0.56 | 0.71 | | | | | | | |
| | 201 | 202 | S201 | 0.1793 | 0.4749 | 0.72 | 0.3589 | 0.9270 | 10.00 | 76.81 | 27.6 | 2-year | 71.2 | | | | | | | | | | | | | | | | | | |
| | | | S101 | 0.0372 | 0.5121 | 0.65 | 0.0672 | 0.9942 | 11.54 | 71.37 | 4.8 | 2-year | 71.0 | 366.4 | 375 | PVC | 0.30 | 80.78 | 90.28 | 0.87 | 0.85 | 1.58 | 0.79 | 0.98 | | | | | | | |
| | 202 | 203 | S202 | 1.3325 | 1.8446 | 0.55 | 2.0374 | 3.0316 | 10.00 | 76.81 | 156.5 | 2-year | 232.8 | | | | | | | | | | | | | | | | | | |
| | | | S203 | 0.3195 | 2.1641 | 0.44 | 0.3908 | 3.4224 | 10.00 | 76.81 | 30.0 | 2-year | 262.9 | | | | | | | | | | | | | | | | | | |
| | | | S204 | 0.0366 | 2.2007 | 0.90 | 0.0916 | 3.5140 | 13.12 | 66.60 | 6.1 | 2-year | 234.0 | 533.0 | 525 | CONC | 0.30 | 74.00 | 245.25 | 1.09 | 1.13 | 1.09 | 0.95 | 1.04 | | | | | | | |
| | 203 | HW 1 | | | 2.2007 | | | 3.5140 | 14.21 | 63.71 | | 2-year | 223.9 | 533.0 | 525 | CONC | 0.27 | 16.61 | 232.66 | 1.03 | 1.07 | 0.26 | 0.96 | 1.04 | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| TOTALS = | | | 2.2007 | | | | 0.57 | | 3.514 | | 268.6 | | | | | | | | | | | | | | | | | | | | |
| <div>Definitions: Q = 2.78*AIR, where Q = Peak Flow in Litres per second (L/s) A = Watershed Area (hectares) I = Rainfall Intensity (mm/h) R = Runoff Coefficients (dimensionless)</div> | | | | | | | | | | | | | | Designed: | | | | | | | | | | Project: | | | | | | | |
| | | | | | | | | | | | | | | J. Fitzpatrick, P.Eng. | | | | | | | | | | 1015 Tweedle Rd | | | | | | | |
| | | | | | | | | | | | | | | Checked: | | | | | | | | | | Location: | | | | | | | |
| | | | | | | | | | | | | | | B. Thomas, P.Eng. | | | | | | | | | | 1015 Tweedle Rd | | | | | | | |
| | | | | | | | | | | | | | | Dwg Reference: | | | | | | | | | | File Ref: | | | | | Sheet No: | | |
| | | | | | | | | | | | | | | Drawing C401 | | | | | | | | | | 259629 Storm - Sewer Design Sheet, Sept 2025.xlsx | | | | | 1 of 1 | | |
| <div>Ottawa Rainfall Intensity Values from Sewer Design Guidelines, SDG002</div> | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | 2-year | | | | | | | | | | 732.9516.1990.810 | | | | | | | |
| | | | | | | | | | | | | | | 5-year | | | | | | | | | | 998.0716.0530.814 | | | | | | | |
| | | | | | | | | | | | | | | 100-year | | | | | | | | | | 1735.6886.0140.820 | | | | | | | |

TABLE B14
SUMMARY OF POST-DEVELOPMENT PEAK FLOWS (Uncontrolled and Controlled)

| Area No | Area (ha) | Time of Conc, Tc (min) | Storm = 2 yr | | | | Storm = 5 yr | | | | Storm = 100 yr | | | | Outlet Location | Comments |
|--|-----------|------------------------|------------------|------------------------|-----------|--------------------------|------------------|------------------------|-----------|--------------------------|------------------|--------------------------|-----------|--------------------------|--------------------------|------------------------------|
| | | | C _{AVG} | I ₂ (mm/hr) | Q (L/sec) | Q _{CAP} (L/sec) | C _{AVG} | I ₅ (mm/hr) | Q (L/sec) | Q _{CAP} (L/sec) | C _{AVG} | I ₁₀₀ (mm/hr) | Q (L/sec) | Q _{CAP} (L/sec) | | |
| B1 | 0.0928 | 10 | 0.90 | 76.81 | 17.8 | (2.9) | 0.90 | 104.19 | 24.2 | (4.0) | 1.00 | 178.56 | 46.1 | (7.6) | Roof Drains | Building B1 roof |
| B2 | 0.0928 | 10 | 0.90 | 76.81 | 17.8 | (2.9) | 0.90 | 104.19 | 24.2 | (4.0) | 1.00 | 178.56 | 46.1 | (7.6) | Roof Drains | Building B2 roof |
| B3 | 0.0928 | 10 | 0.90 | 76.81 | 17.8 | (2.9) | 0.90 | 104.19 | 24.2 | (4.0) | 1.00 | 178.56 | 46.1 | (7.6) | Roof Drains | Building B2 roof |
| B4 | 0.0790 | 10 | 0.90 | 76.81 | 15.2 | (2.9) | 0.90 | 104.19 | 20.6 | (4.0) | 1.00 | 178.56 | 39.2 | (7.6) | Roof Drains | Building B3 roof |
| S100 | 0.0691 | 10 | 0.63 | 76.81 | 9.3 | 9.3 | 0.63 | 104.19 | 12.6 | 12.6 | 0.79 | 178.56 | 27.0 | 27.0 | Jeanne D'Arc Blvd ROW | Uncontrolled to ROW |
| S101 | 0.0372 | 10 | 0.65 | 76.81 | 5.2 | 5.2 | 0.65 | 104.19 | 7.0 | 7.0 | 0.81 | 178.56 | 15.0 | 15.0 | Jeanne D'Arc Blvd ROW | Uncontrolled to ROW |
| S102 | 0.0612 | 10 | 0.73 | 76.81 | 9.5 | 9.5 | 0.73 | 104.19 | 12.9 | 12.9 | 0.91 | 178.56 | 27.7 | 27.7 | Area Drains to Ott River | Uncontrolled to Ottawa River |
| S103 | 0.0686 | 10 | 0.36 | 76.81 | 5.3 | 5.3 | 0.36 | 104.19 | 7.2 | 7.2 | 0.45 | 178.56 | 15.3 | 15.3 | Tweedle Rd ROW | Uncontrolled to ROW |
| S104 | 0.6319 | 10 | 0.80 | 76.81 | 107.9 | 107.9 | 0.80 | 104.19 | 146.4 | 146.4 | 1.00 | 178.56 | 313.7 | 313.7 | Area Drains to Ott River | Uncontrolled to Ottawa River |
| S105 | 0.0346 | 10 | 0.20 | 76.81 | 1.5 | 1.5 | 0.20 | 104.19 | 2.0 | 2.0 | 0.25 | 178.56 | 4.3 | 4.3 | Overland to Ottawa River | Uncontrolled to Ottawa River |
| S106 | 0.0359 | 10 | 0.20 | 76.81 | 1.5 | 1.5 | 0.20 | 104.19 | 2.1 | 2.1 | 0.25 | 178.56 | 4.5 | 4.5 | Overland to Ottawa River | Uncontrolled to Ottawa River |
| | | | | | | | | | | | | | | | | |
| Total (All) | 1.2959 | | | | 208.9 | 151.9 | | | 283.4 | 206.1 | | | | 584.9 | 437.8 | |
| <div>Notes</div> <div>2-yr Storm Intensity, I = 732.951/(Tc+6.199)^0.810 (City of Ottawa)</div> <div>5-yr Storm Intensity, I = 998.071/(Tc+6.035)^0.814 (City of Ottawa)</div> <div>100-yr Storm Intensity, I = 1735.688/(Tc+6.014)&^0.820 (City of Ottawa)</div> <div>Time of Concentration (min), Tc = 10</div> <div>For Flows under column Qcap which are shown in brackets (0.0) , denotes flows that are controlled</div> | | | | | | | | | | | | | | | | |

TABLE B15
SUMMARY OF STORAGE

| Area No | Release Rate (L/s) | | | Storage Required (m ³) (MRM) | | | Storage Provided (m ³) | | Control Method | Area Desc |
|-------------|--------------------|-------|--------|--|------|--------|------------------------------------|---------|-----------------------------|------------------|
| | 2-yr | 5-yr | 100-yr | 2-yr | 5-yr | 100-yr | Roof | Surface | | |
| B1 | 2.9 | 4.0 | 7.6 | 11.5 | 15.4 | 29.0 | 46.4 | | Flow Controlled Roof Drains | Building B1 roof |
| B2 | 2.9 | 4.0 | 7.6 | 11.5 | 15.4 | 29.0 | 46.4 | | Flow Controlled Roof Drains | Building B2 roof |
| B3 | 2.9 | 4.0 | 7.6 | 11.5 | 15.4 | 29.0 | 46.4 | | Flow Controlled Roof Drains | Building B2 roof |
| B4 | 2.9 | 4.0 | 7.6 | 9.0 | 12.1 | 22.9 | 39.5 | | Flow Controlled Roof Drains | Building B3 roof |
| S100 | 9.3 | 12.6 | 27.0 | | | | | | none | |
| S101 | 5.2 | 7.0 | 15.0 | | | | | | none | |
| S102 | 9.5 | 12.9 | 27.7 | | | | | | none | |
| S103 | 5.3 | 7.2 | 15.3 | | | | | | none | |
| S104 | 107.9 | 146.4 | 313.7 | | | | | | none | |
| S105 | 1.5 | 2.0 | 4.3 | | | | | | none | |
| S106 | 1.5 | 2.1 | 4.5 | | | | | | none | |
| | | | | | | | | | | |
| Total (All) | 151.9 | 206.1 | 437.8 | 43.4 | 58.2 | 109.9 | 178.7 | | | |

| | | | | | | | | | | | | | | | |
|---|--|-------------------|----------------------|----------------------|--------------|--|-------------------|----------------------|----------------------|--------------|---|-------------------|----------------------|----------------------|--------------|
| <div> <div> <div>Area No: TOWER A</div> <div> <div>C_{AVG} = 0.90 (2-yr)</div> <div>C_{AVG} = 0.90 (5-yr)</div> <div>C_{AVG} = 1.00 (100-yr, Max 1.0)</div> <div>Time Interval = 2.00 (mins)</div> <div>Drainage Area = 0.0928 (hectares)</div> <div>Intensity Incr (%) = 0% (Use 20% for Climate Change)</div> </div> </div> <div> <div>Actual Release Rate (L/sec) = 7.6</div> <div>Percentage of Actual Rate (City of Ottawa requirement) = 100% (Set to 50% when U/G storage used)</div> <div>Release Rate Used for Estimation of 100-year Storage (L/sec) = 7.6</div> </div> </div> | | | | | | | | | | | | | | | |
| Duration (min) | <div> <div>Release Rate = 2.9 (L/sec)</div> <div>Return Period = 2.0 (years)</div> <div>IDF Parameters, A = 733.0, B = 0.810</div> <div>(I = A/(T_c+C) , C = 6.199</div> </div> | | | | | <div> <div>Release Rate = 4.0 (L/sec)</div> <div>Return Period = 5.0 (years)</div> <div>IDF Parameters, A = 998.1, B = 0.814</div> <div>(I = A/(T_c+C) , C = 6.053</div> </div> | | | | | <div> <div>Release Rate = 7.6 (L/sec)</div> <div>Return Period = 100.0 (years)</div> <div>IDF Parameters, A = 1735.7, B = 0.820</div> <div>(I = A/(T_c+C) , C = 6.014</div> </div> | | | | |
| | Rainfall Intensity, I (mm/hr) | Peak Flow (L/sec) | Release Rate (L/sec) | Storage Rate (L/sec) | Storage (m³) | Rainfall Intensity, I (mm/hr) | Peak Flow (L/sec) | Release Rate (L/sec) | Storage Rate (L/sec) | Storage (m³) | Rainfall Intensity, I (mm/hr) | Peak Flow (L/sec) | Release Rate (L/sec) | Storage Rate (L/sec) | Storage (m³) |
| 0 | 167.2 | 38.8 | 2.9 | 35.9 | 0.0 | 230.5 | 53.5 | 4.0 | 49.5 | 0.0 | 398.6 | 102.8 | 7.6 | 95.3 | 0.0 |
| 2 | 133.3 | 31.0 | 2.9 | 28.0 | 3.4 | 182.7 | 42.4 | 4.0 | 38.4 | 4.6 | 315.0 | 81.3 | 7.6 | 73.7 | 8.8 |
| 4 | 111.7 | 25.9 | 2.9 | 23.0 | 5.5 | 152.5 | 35.4 | 4.0 | 31.4 | 7.5 | 262.4 | 67.7 | 7.6 | 60.1 | 14.4 |
| 6 | 96.6 | 22.4 | 2.9 | 19.5 | 7.0 | 131.6 | 30.5 | 4.0 | 26.6 | 9.6 | 226.0 | 58.3 | 7.6 | 50.7 | 18.3 |
| 8 | 85.5 | 19.8 | 2.9 | 16.9 | 8.1 | 116.1 | 27.0 | 4.0 | 23.0 | 11.0 | 199.2 | 51.4 | 7.6 | 43.8 | 21.0 |
| 10 | 76.8 | 17.8 | 2.9 | 14.9 | 8.9 | 104.2 | 24.2 | 4.0 | 20.2 | 12.1 | 178.6 | 46.1 | 7.6 | 38.5 | 23.1 |
| 12 | 69.9 | 16.2 | 2.9 | 13.3 | 9.6 | 94.7 | 22.0 | 4.0 | 18.0 | 13.0 | 162.1 | 41.8 | 7.6 | 34.3 | 24.7 |
| 14 | 64.2 | 14.9 | 2.9 | 12.0 | 10.1 | 86.9 | 20.2 | 4.0 | 16.2 | 13.6 | 148.7 | 38.4 | 7.6 | 30.8 | 25.9 |
| 16 | 59.5 | 13.8 | 2.9 | 10.9 | 10.4 | 80.5 | 18.7 | 4.0 | 14.7 | 14.1 | 137.5 | 35.5 | 7.6 | 27.9 | 26.8 |
| 18 | 55.5 | 12.9 | 2.9 | 10.0 | 10.7 | 75.0 | 17.4 | 4.0 | 13.4 | 14.5 | 128.1 | 33.0 | 7.6 | 25.5 | 27.5 |
| 20 | 52.0 | 12.1 | 2.9 | 9.1 | 11.0 | 70.3 | 16.3 | 4.0 | 12.3 | 14.8 | 120.0 | 30.9 | 7.6 | 23.4 | 28.0 |
| 22 | 49.0 | 11.4 | 2.9 | 8.5 | 11.2 | 66.1 | 15.4 | 4.0 | 11.4 | 15.0 | 112.9 | 29.1 | 7.6 | 21.5 | 28.4 |
| 24 | 46.4 | 10.8 | 2.9 | 7.8 | 11.3 | 62.5 | 14.5 | 4.0 | 10.5 | 15.2 | 106.7 | 27.5 | 7.6 | 19.9 | 28.7 |
| 26 | 44.0 | 10.2 | 2.9 | 7.3 | 11.4 | 59.3 | 13.8 | 4.0 | 9.8 | 15.3 | 101.2 | 26.1 | 7.6 | 18.5 | 28.9 |
| 28 | 41.9 | 9.7 | 2.9 | 6.8 | 11.4 | 56.5 | 13.1 | 4.0 | 9.1 | 15.4 | 96.3 | 24.8 | 7.6 | 17.3 | 29.0 |
| 30 | 40.0 | 9.3 | 2.9 | 6.4 | 11.5 | 53.9 | 12.5 | 4.0 | 8.5 | 15.4 | 91.9 | 23.7 | 7.6 | 16.1 | 29.0 |
| 32 | 38.3 | 8.9 | 2.9 | 6.0 | 11.5 | 51.6 | 12.0 | 4.0 | 8.0 | 15.4 | 87.9 | 22.7 | 7.6 | 15.1 | 29.0 |
| 34 | 36.8 | 8.5 | 2.9 | 5.6 | 11.4 | 49.5 | 11.5 | 4.0 | 7.5 | 15.3 | 84.3 | 21.7 | 7.6 | 14.2 | 28.9 |
| 36 | 35.4 | 8.2 | 2.9 | 5.3 | 11.4 | 47.6 | 11.0 | 4.0 | 7.1 | 15.3 | 81.0 | 20.9 | 7.6 | 13.3 | 28.8 |
| 38 | 34.1 | 7.9 | 2.9 | 5.0 | 11.3 | 45.8 | 10.6 | 4.0 | 6.7 | 15.2 | 77.9 | 20.1 | 7.6 | 12.5 | 28.6 |
| 40 | 32.9 | 7.6 | 2.9 | 4.7 | 11.3 | 44.2 | 10.3 | 4.0 | 6.3 | 15.1 | 75.1 | 19.4 | 7.6 | 11.8 | 28.4 |
| Max = | 11.5 | | | | | | | | | | | | | | |

TABLE B18
Storage Volumes for 2-year, 5-Year and 100-Year Storms (MRM)

Area No: **TOWER C**

C_{AVG} = 0.90 (2-yr)

C_{AVG} = 0.90 (5-yr)

C_{AVG} = 1.00 (100-yr, Max 1.0)

Time Interval = 3.00 (mins)

Drainage Area = 0.0928 (hectares)

Intensity Incr (%) = 0% (Use 20% for Climate Change)

Actual Release Rate (L/sec) = 7.6

Percentage of Actual Rate (City of Ottawa requirement) = 100% (Set to 50% when U/G storage used)

Release Rate Used for Estimation of 100-year Storage (L/sec) = 7.6

| Duration (min) | Release Rate = 2.9 (L/sec) Return Period = 2.0 (years) IDF Parameters, A = 733.0, B = 0.810 (I = A/(T _c +C), C = 6.199) | | | | | Release Rate = 4.0 (L/sec) Return Period = 5.0 (years) IDF Parameters, A = 998.1, B = 0.814 (I = A/(T _c +C), C = 6.053) | | | | | Release Rate = 7.6 (L/sec) Return Period = 100.0 (years) IDF Parameters, A = 1735.7, B = 0.820 (I = A/(T _c +C), C = 6.014) | | | | |
|----------------|---|-------------------|----------------------|----------------------|---------------------------|---|-------------------|----------------------|----------------------|---------------------------|--|-------------------|----------------------|----------------------|---------------------------|
| | Rainfall Intensity, I (mm/hr) | Peak Flow (L/sec) | Release Rate (L/sec) | Storage Rate (L/sec) | Storage (m ³) | Rainfall Intensity, I (mm/hr) | Peak Flow (L/sec) | Release Rate (L/sec) | Storage Rate (L/sec) | Storage (m ³) | Rainfall Intensity, I (mm/hr) | Peak Flow (L/sec) | Release Rate (L/sec) | Storage Rate (L/sec) | Storage (m ³) |
| 0 | 167.2 | 38.8 | 2.9 | 35.9 | 0.0 | 230.5 | 53.5 | 4.0 | 49.5 | 0.0 | 398.6 | 102.8 | 7.6 | 95.3 | 0.0 |
| 3 | 121.5 | 28.2 | 2.9 | 25.3 | 4.5 | 166.1 | 38.6 | 4.0 | 34.6 | 6.2 | 286.0 | 73.8 | 7.6 | 66.2 | 11.9 |
| 6 | 96.6 | 22.4 | 2.9 | 19.5 | 7.0 | 131.6 | 30.5 | 4.0 | 26.6 | 9.6 | 226.0 | 58.3 | 7.6 | 50.7 | 18.3 |
| 9 | 80.9 | 18.8 | 2.9 | 15.8 | 8.6 | 109.8 | 25.5 | 4.0 | 21.5 | 11.6 | 188.3 | 48.6 | 7.6 | 41.0 | 22.1 |
| 12 | 69.9 | 16.2 | 2.9 | 13.3 | 9.6 | 94.7 | 22.0 | 4.0 | 18.0 | 13.0 | 162.1 | 41.8 | 7.6 | 34.3 | 24.7 |
| 15 | 61.8 | 14.3 | 2.9 | 11.4 | 10.3 | 83.6 | 19.4 | 4.0 | 15.4 | 13.9 | 142.9 | 36.9 | 7.6 | 29.3 | 26.4 |
| 18 | 55.5 | 12.9 | 2.9 | 10.0 | 10.7 | 75.0 | 17.4 | 4.0 | 13.4 | 14.5 | 128.1 | 33.0 | 7.6 | 25.5 | 27.5 |
| 21 | 50.5 | 11.7 | 2.9 | 8.8 | 11.1 | 68.1 | 15.8 | 4.0 | 11.8 | 14.9 | 116.3 | 30.0 | 7.6 | 22.4 | 28.3 |
| 24 | 46.4 | 10.8 | 2.9 | 7.8 | 11.3 | 62.5 | 14.5 | 4.0 | 10.5 | 15.2 | 106.7 | 27.5 | 7.6 | 19.9 | 28.7 |
| 27 | 43.0 | 10.0 | 2.9 | 7.0 | 11.4 | 57.9 | 13.4 | 4.0 | 9.5 | 15.3 | 98.7 | 25.5 | 7.6 | 17.9 | 29.0 |
| 30 | 40.0 | 9.3 | 2.9 | 6.4 | 11.5 | 53.9 | 12.5 | 4.0 | 8.5 | 15.4 | 91.9 | 23.7 | 7.6 | 16.1 | 29.0 |
| 33 | 37.5 | 8.7 | 2.9 | 5.8 | 11.5 | 50.5 | 11.7 | 4.0 | 7.8 | 15.4 | 86.0 | 22.2 | 7.6 | 14.6 | 29.0 |
| 36 | 35.4 | 8.2 | 2.9 | 5.3 | 11.4 | 47.6 | 11.0 | 4.0 | 7.1 | 15.3 | 81.0 | 20.9 | 7.6 | 13.3 | 28.8 |
| 39 | 33.5 | 7.8 | 2.9 | 4.8 | 11.3 | 45.0 | 10.4 | 4.0 | 6.5 | 15.1 | 76.5 | 19.7 | 7.6 | 12.2 | 28.5 |
| 42 | 31.8 | 7.4 | 2.9 | 4.4 | 11.2 | 42.7 | 9.9 | 4.0 | 5.9 | 15.0 | 72.6 | 18.7 | 7.6 | 11.1 | 28.1 |
| 45 | 30.2 | 7.0 | 2.9 | 4.1 | 11.0 | 40.6 | 9.4 | 4.0 | 5.5 | 14.7 | 69.1 | 17.8 | 7.6 | 10.2 | 27.7 |
| 48 | 28.9 | 6.7 | 2.9 | 3.8 | 10.9 | 38.8 | 9.0 | 4.0 | 5.0 | 14.5 | 65.9 | 17.0 | 7.6 | 9.4 | 27.1 |
| 51 | 27.6 | 6.4 | 2.9 | 3.5 | 10.7 | 37.1 | 8.6 | 4.0 | 4.6 | 14.2 | 63.0 | 16.3 | 7.6 | 8.7 | 26.6 |
| 54 | 26.5 | 6.2 | 2.9 | 3.2 | 10.5 | 35.6 | 8.3 | 4.0 | 4.3 | 13.9 | 60.4 | 15.6 | 7.6 | 8.0 | 26.0 |
| 57 | 25.5 | 5.9 | 2.9 | 3.0 | 10.2 | 34.2 | 7.9 | 4.0 | 4.0 | 13.6 | 58.1 | 15.0 | 7.6 | 7.4 | 25.3 |
| 60 | 24.6 | 5.7 | 2.9 | 2.8 | 10.0 | 32.9 | 7.6 | 4.0 | 3.7 | 13.2 | 55.9 | 14.4 | 7.6 | 6.8 | 24.7 |
| Max = | 11.5 | | | | | 15.4 | | | | | 29.0 | | | | |

Notes

1) Peak flow is equal to the product of 2.78 x C x I x A

2) Rainfall Intensity, I = A/(T_c+C)^{0.820}

3) Release Rate = Min (Release Rate, Peak Flow)

4) Storage Rate = Peak Flow - Release Rate

5) Storage = Duration x Storage Rate

6) Maximum Storage = Max Storage Over Duration

7) Parameters a,b,c are for City of Ottawa

IDF curve equations (Intensity in mm/hr)

100 year Intensity = 1735.688 / (Time in min + 6.014)^{0.820}

50 year Intensity = 1569.580 / (Time in min + 6.014)^{0.820}

25 year Intensity = 1402.884 / (Time in min + 6.018)^{0.819}

Storage Volumes for 2-year, 5-Year and 100-Year Storms (MRM)

Area No: **TOWER D**

C_{AVG} = 0.90 (2-yr)

C_{AVG} = 0.90 (5-yr)

C_{AVG} = 1.00 (100-yr, Max 1.0)

Time Interval = 2.00 (mins)

Drainage Area = 0.0790 (hectares)

Intensity Incr (%) = 0% (Use 20% for Climate Change)

Actual Release Rate (L/sec) = 7.6

Percentage of Actual Rate (City of Ottawa requirement) = 100% (Set to 50% when U/G storage used)

Release Rate Used for Estimation of 100-year Storage (L/sec) = 7.6

| Duration (min) | Release Rate = 2.9 (L/sec) Return Period = 2.0 (years) IDF Parameters, A = 733.0, B = 0.810 (I = A/(T _c +C), C = 6.199) | | | | | Release Rate = 4.0 (L/sec) Return Period = 5.0 (years) IDF Parameters, A = 998.1, B = 0.814 (I = A/(T _c +C), C = 6.053) | | | | | Release Rate = 7.6 (L/sec) Return Period = 100.0 (years) IDF Parameters, A = 1735.7, B = 0.820 (I = A/(T _c +C), C = 6.014) | | | | |
|----------------|---|-------------------|----------------------|----------------------|---------------------------|---|-------------------|----------------------|----------------------|---------------------------|--|-------------------|----------------------|----------------------|---------------------------|
| | Rainfall Intensity, I (mm/hr) | Peak Flow (L/sec) | Release Rate (L/sec) | Storage Rate (L/sec) | Storage (m ³) | Rainfall Intensity, I (mm/hr) | Peak Flow (L/sec) | Release Rate (L/sec) | Storage Rate (L/sec) | Storage (m ³) | Rainfall Intensity, I (mm/hr) | Peak Flow (L/sec) | Release Rate (L/sec) | Storage Rate (L/sec) | Storage (m ³) |
| 0 | 167.2 | 33.1 | 2.9 | 30.1 | 0.0 | 230.5 | 45.6 | 4.0 | 41.6 | 0.0 | 398.6 | 87.5 | 7.6 | 80.0 | 0.0 |
| 2 | 133.3 | 26.4 | 2.9 | 23.4 | 2.8 | 182.7 | 36.1 | 4.0 | 32.1 | 3.9 | 315.0 | 69.2 | 7.6 | 61.6 | 7.4 |
| 4 | 111.7 | 22.1 | 2.9 | 19.2 | 4.6 | 152.5 | 30.1 | 4.0 | 26.2 | 6.3 | 262.4 | 57.6 | 7.6 | 50.1 | 12.0 |
| 6 | 96.6 | 19.1 | 2.9 | 16.2 | 5.8 | 131.6 | 26.0 | 4.0 | 22.0 | 7.9 | 226.0 | 49.6 | 7.6 | 42.1 | 15.1 |
| 8 | 85.5 | 16.9 | 2.9 | 14.0 | 6.7 | 116.1 | 23.0 | 4.0 | 19.0 | 9.1 | 199.2 | 43.7 | 7.6 | 36.2 | 17.4 |
| 10 | 76.8 | 15.2 | 2.9 | 12.2 | 7.3 | 104.2 | 20.6 | 4.0 | 16.6 | 10.0 | 178.6 | 39.2 | 7.6 | 31.6 | 19.0 |
| 12 | 69.9 | 13.8 | 2.9 | 10.9 | 7.8 | 94.7 | 18.7 | 4.0 | 14.7 | 10.6 | 162.1 | 35.6 | 7.6 | 28.0 | 20.2 |
| 14 | 64.2 | 12.7 | 2.9 | 9.8 | 8.2 | 86.9 | 17.2 | 4.0 | 13.2 | 11.1 | 148.7 | 32.7 | 7.6 | 25.1 | 21.1 |
| 16 | 59.5 | 11.8 | 2.9 | 8.8 | 8.5 | 80.5 | 15.9 | 4.0 | 11.9 | 11.4 | 137.5 | 30.2 | 7.6 | 22.6 | 21.7 |
| 18 | 55.5 | 11.0 | 2.9 | 8.0 | 8.7 | 75.0 | 14.8 | 4.0 | 10.8 | 11.7 | 128.1 | 28.1 | 7.6 | 20.6 | 22.2 |
| 20 | 52.0 | 10.3 | 2.9 | 7.4 | 8.8 | 70.3 | 13.9 | 4.0 | 9.9 | 11.9 | 120.0 | 26.3 | 7.6 | 18.8 | 22.5 |
| 22 | 49.0 | 9.7 | 2.9 | 6.8 | 8.9 | 66.1 | 13.1 | 4.0 | 9.1 | 12.0 | 112.9 | 24.8 | 7.6 | 17.2 | 22.7 |
| 24 | 46.4 | 9.2 | 2.9 | 6.2 | 9.0 | 62.5 | 12.4 | 4.0 | 8.4 | 12.1 | 106.7 | 23.4 | 7.6 | 15.9 | 22.8 |
| 26 | 44.0 | 8.7 | 2.9 | 5.8 | 9.0 | 59.3 | 11.7 | 4.0 | 7.8 | 12.1 | 101.2 | 22.2 | 7.6 | 14.6 | 22.9 |
| 28 | 41.9 | 8.3 | 2.9 | 5.4 | 9.0 | 56.5 | 11.2 | 4.0 | 7.2 | 12.1 | 96.3 | 21.1 | 7.6 | 13.6 | 22.8 |
| 30 | 40.0 | 7.9 | 2.9 | 5.0 | 9.0 | 53.9 | 10.7 | 4.0 | 6.7 | 12.0 | 91.9 | 20.2 | 7.6 | 12.6 | 22.7 |
| 32 | 38.3 | 7.6 | 2.9 | 4.6 | 8.9 | 51.6 | 10.2 | 4.0 | 6.2 | 12.0 | 87.9 | 19.3 | 7.6 | 11.7 | 22.5 |
| 34 | 36.8 | 7.3 | 2.9 | 4.3 | 8.9 | 49.5 | 9.8 | 4.0 | 5.8 | 11.8 | 84.3 | 18.5 | 7.6 | 10.9 | 22.3 |
| 36 | 35.4 | 7.0 | 2.9 | 4.1 | 8.8 | 47.6 | 9.4 | 4.0 | 5.4 | 11.7 | 81.0 | 17.8 | 7.6 | 10.2 | 22.1 |
| 38 | 34.1 | 6.7 | 2.9 | 3.8 | 8.7 | 45.8 | 9.1 | 4.0 | 5.1 | 11.6 | 77.9 | 17.1 | 7.6 | 9.5 | 21.8 |
| 40 | 32.9 | 6.5 | 2.9 | 3.6 | 8.6 | 44.2 | 8.7 | 4.0 | 4.8 | 11.4 | 75.1 | 16.5 | 7.6 | 8.9 | 21.4 |
| Max = | 9.0 | | | | | 12.1 | | | | | 22.9 | | | | |

Notes

1) Peak flow is equal to the product of 2.78 x C x I x A

2) Rainfall Intensity, I = A/(T_c+C)^B

3) Release Rate = Min (Release Rate, Peak Flow)

4) Storage Rate = Peak Flow - Release Rate

5) Storage = Duration x Storage Rate

6) Maximum Storage = Max Storage Over Duration

7) Parameters a,b,c are for City of Ottawa

IDF curve equations (Intensity in mm/hr)

100 year Intensity = 1735.688 / (Time in min + 6.014)^{0.820}

50 year Intensity = 1569.580 / (Time in min + 6.014)^{0.820}

25 year Intensity = 1402.884 / (Time in min + 6.018)^{0.819}

10 year Intensity = 11

TABLE B20
SUMMARY OF ROOF DRAINS & ROOF STORAGE

| Building | Area | | | Location | Roof Drain | | Flow Controlled | | | Ponding (Yes/No) | # Drains per Area | Area Available for Ponding | | Estimated Volume for Ponding (m3) |
|----------|-------------------|--------|--------|---------------------|------------|------------|-----------------|----------|----------------------|---------------------|----------------------|-------------------------------|-----------|--|
| | (m ²) | (ha) | % Roof | | Manuf | Model | Yes / No | Method | Peak Flow (L/sec) | | | % of Area | Area (m2) | |
| Tower B1 | 928 | 0.0928 | 54% | High Roof | WATTS | RD-100 | Yes | ACCUTROL | 7.6 | Yes | 4 | 90 | 835 | 46.4 |
| | 676 | 0.0676 | 39% | Terrace - 3rd Floor | WATTS | RD-100-BEM | No | | | No | 5 | | | |
| | 116 | 0.0116 | 7% | Terrace - 2nd Floor | WATTS | RD-100-BEM | No | | | No | 4 | | | |
| Tower B2 | 928 | 0.0928 | 59% | High Roof | WATTS | RD-100-BEM | Yes | ACCUTROL | 7.6 | Yes | 4 | 90 | 835 | 46.4 |
| | 598 | 0.0598 | 38% | Terrace - 3rd Floor | WATTS | RD-100-BEM | No | | | No | 5 | | | |
| | 60 | 0.006 | 4% | Terrace - 2nd Floor | WATTS | RD-100-BEM | No | | | No | 1 | | | |
| Tower B3 | 928 | 0.0928 | 50% | High Roof | WATTS | RD-100 | Yes | ACCUTROL | 7.6 | Yes | 4 | 90 | 835 | 46.4 |
| | 822 | 0.0822 | 45% | Terrace - 3rd Floor | WATTS | RD-100-BEM | No | | | No | 5 | | | |
| | 89 | 0.0089 | 5% | Terrace - 2nd Floor | WATTS | RD-100-BEM | No | | | No | 2 | | | |
| Tower B4 | 790 | 0.079 | 84.5% | High Roof | WATTS | RD100 | Yes | ACCUTROL | 7.6 | Yes | 4 | 90 | 711 | 39.5 |
| | 145 | 0.0145 | 15.5% | Podium | WATTS | RD-100-BEM | No | | | No | 4 | | | |

TABLE B21

BUILDING ROOF INFORMATION:

TABLE B21

Subcatchment Number

Total Roof Area (m2) **928**

Minimum Number of Drains Required

2*Minimum of 1 drain every 900 square metres (OBC 7.4.10.4)
(OBC Supp SB-1)*

15-min Rainfall Factor for Ottawa (mm)

23

Max Permitted Load from All Drains (Litres)

21,344

Max Permitted Load from All Drains (L/sec)

23.7*Hydraulic Load expressed in L/sec (OBC Section 7.4.10.3)*

Estimated Distance from roof edge to drains (m)

6*Not more than 15m from Edge of Roof and 30m to Adjacent Drains (OBC Section 7.4.10.3)*

Estimated area per drain (m2)

144

Estimated No. of Drains Required

7*Based on Total Roof Area / Area per Drain*

Actual No. of Drains Used

4*Use if known*

Effective Roof Percentage (%)

90.0%*Allowance for Mechanical units on roof*

Effective Total Roof Area (m2)

835

Area per Drain (m2)

209*Based on Effective Roof Area / Actual Number of Drains Used*

Max Depth of Ponding at Drains (mm)

150

Estimated Total Volume for Ponding on Roof (m3)

46.4*Prism formula, $V = 1/3 \cdot A \cdot d$*

Maximum release rate per drain at 150mm (L/s)

1.893*Based on 1 Wier Per Drain and Fully Open Position*

Max Release Rate from Total Roof (L/sec)

7.6*Based on Maximum Depth of Ponding of 150mm***RATING CURVE FOR ROOF**

| DISCHARGE VERSUS DEPTH | | | | AREA VERSUS DEPTH | | | | |
|------------------------|--------------------------------|-----------------------------------|-------------------------------------|-------------------|---------------------------|---------------------------|-----------------------------|-----------------------------|
| Ponding Depth (m) | Discharge Rate Per Drain (gpm) | Discharge Rate Per Drain (m3/sec) | Total Discharge All Drains (m3/sec) | Ponding Depth (m) | Ponding Area (Indiv) (m2) | Ponding Area (Total) (m2) | Ponding Volume (Indiv) (m3) | Ponding Volume (Total) (m3) |
| 0.000 | 0 | 0.00 | 0.00000 | 0.000 | 0.0 | 0.0 | 0.0 | 0.0 |
| 0.025 | 5 | 0.32 | 0.00126 | 0.025 | 5.8 | 23.2 | 0.0 | 0.2 |
| 0.050 | 10 | 0.63 | 0.00252 | 0.050 | 23.2 | 92.8 | 0.4 | 1.5 |
| 0.075 | 15 | 0.95 | 0.00379 | 0.075 | 52.2 | 208.8 | 1.3 | 5.2 |
| 0.100 | 20 | 1.26 | 0.00505 | 0.100 | 92.8 | 371.2 | 3.1 | 12.4 |
| 0.125 | 25 | 1.58 | 0.00631 | 0.125 | 145.0 | 580.0 | 6.0 | 24.2 |
| 0.150 | 30 | 1.89 | 0.00757 | 0.150 | 208.8 | 835.2 | 10.4 | 41.8 |

Weir Position = **6 Full**

| RATING CURVE FOR MODELLING OUTLET | |
|-----------------------------------|-----------------|
| Head or Ponding Depth (m) | Outflow (L/sec) |
| 0.000 | 0.00 |
| 0.025 | 1.26 |
| 0.050 | 2.52 |
| 0.075 | 3.79 |
| 0.100 | 5.05 |
| 0.125 | 6.31 |
| 0.150 | 7.57 |

| RATING CURVE FOR MODELLING ROOF STORAGE | |
|---|-------------------|
| Head or Ponding Depth (m) | Ponding Area (m2) |
| 0.000 | 0 |
| 0.025 | 23 |
| 0.050 | 93 |
| 0.075 | 209 |
| 0.100 | 371 |
| 0.125 | 580 |
| 0.150 | 835 |

WATTS ADJ ACCUTROL WEIR FLOW RATES (Flow Rates at Various Depths)

| Depth | Weir Position | | | | | |
|-------|--------------------------------------|----------|------------|------------|------------|--------|
| | 1 None | 2 Closed | 3 1/4 open | 4 1/2 open | 5 3/4 open | 6 Full |
| | Max Flow Rate per wier @150mm in gpm | | | | | |
| 0.000 | 0 | 0 | 0 | 0 | 0 | 0 |
| 0.025 | 0 | 5 | 5 | 5 | 5 | 5 |
| 0.050 | 0 | 5 | 10 | 10 | 10 | 10 |
| 0.075 | 0 | 5 | 11.25 | 12.35 | 13.75 | 15 |
| 0.100 | 0 | 5 | 12.5 | 15 | 17.5 | 20 |
| 0.125 | 0 | 5 | 13.75 | 17.5 | 21.25 | 25 |
| 0.150 | 0 | 5 | 15 | 20 | 25 | 30 |

WATTS ADJ ACCUTROL WEIR FLOW RATES (Data From Manufacturer's Catalog)

| Weir Position | Flow (gpm) per depth | | | | | | | Max Flow Rate per Weir @150mm |
|---------------|----------------------|-------|------|-------|------|-------|------|-------------------------------|
| | 0 | 25 | 50 | 75 | 100 | 125 | 150 | |
| | 0 | 0.025 | 0.05 | 0.075 | 0.1 | 0.125 | 0.15 | |
| 1 None | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0.000 |
| 2 Closed | 0 | 5 | 5 | 5 | 5 | 5 | 5 | 0.315 |
| 3 1/4 open | 0 | 5 | 10 | 11.25 | 12.5 | 13.75 | 15 | 0.946 |
| 4 1/2 open | 0 | 5 | 10 | 12.35 | 15 | 17.5 | 20 | 1.262 |
| 5 3/4 open | 0 | 5 | 10 | 13.75 | 17.5 | 21.25 | 25 | 1.577 |
| 6 Full | 0 | 5 | 10 | 15 | 20 | 25 | 30 | 1.893 |

0.0631


GRAPH OF FLOW RATE VERSUS DEPTH FOR VARIOUS WEIR POSITIONS

TABLE B22

BUILDING ROOF INFORMATION:

TABLE B22

| | | |
|---|--------|---|
| Subcatchment Number | | |
| Total Roof Area (m2) | 928 | |
| Minimum Number of Drains Required | 2 | Minimum of 1 drain every 900 square metres (OBC 7.4.10.4) (OBC Supp SB-1) |
| 15-min Rainfall Factor for Ottawa (mm) | 23 | |
| Max Permitted Load from All Drains (Litres) | 21,344 | |
| Max Permitted Load from All Drains (L/sec) | 23.7 | Hydraulic Load expressed in L/sec (OBC Section 7.4.10.3) |
| Estimated Distance from roof edge to drains (m) | 6 | Not more than 15m from Edge of Roof and 30m to Adjacent Drains (OBC Section 7.4.10.3) |
| Estimated area per drain (m2) | 144 | |
| Estimated No. of Drains Required | 7 | Based on Total Roof Area / Area per Drain |
| Actual No. of Drains Used | 4 | Use if known |
| Effective Roof Percentage (%) | 90.0% | Allowance for Mechanical units on roof |
| Effective Total Roof Area (m2) | 835 | |
| Area per Drain (m2) | 209 | Based on Effective Roof Area / Actual Number of Drains Used |
| Max Depth of Ponding at Drains (mm) | 150 | |
| Estimated Total Volume for Ponding on Roof (m3) | 46.4 | Prism formula, $V = 1/3 \cdot A \cdot d$ |
| Maximum release rate per drain at 150mm (L/s) | 1.893 | Based on 1 Wier Per Drain and Fully Open Position |
| Max Release Rate from Total Roof (L/sec) | 7.6 | Based on Maximum Depth of Ponding of 150mm |

RATING CURVE FOR ROOF

| DISCHARGE VERSUS DEPTH | | | | AREA VERSUS DEPTH | | | | |
|------------------------|--------------------------------|-----------------------------------|-------------------------------------|-------------------|---------------------------|---------------------------|-----------------------------|-----------------------------|
| Ponding Depth (m) | Discharge Rate Per Drain (gpm) | Discharge Rate Per Drain (m3/sec) | Total Discharge All Drains (m3/sec) | Ponding Depth (m) | Ponding Area (Indiv) (m2) | Ponding Area (Total) (m2) | Ponding Volume (Indiv) (m3) | Ponding Volume (Total) (m3) |
| 0.000 | 0 | 0.00 | 0.00000 | 0.000 | 0.0 | 0.0 | 0.0 | 0.0 |
| 0.025 | 5 | 0.32 | 0.00126 | 0.025 | 5.8 | 23.2 | 0.0 | 0.2 |
| 0.050 | 10 | 0.63 | 0.00252 | 0.050 | 23.2 | 92.8 | 0.4 | 1.5 |
| 0.075 | 15 | 0.95 | 0.00379 | 0.075 | 52.2 | 208.8 | 1.3 | 5.2 |
| 0.100 | 20 | 1.26 | 0.00505 | 0.100 | 92.8 | 371.2 | 3.1 | 12.4 |
| 0.125 | 25 | 1.58 | 0.00631 | 0.125 | 145.0 | 580.0 | 6.0 | 24.2 |
| 0.150 | 30 | 1.89 | 0.00757 | 0.150 | 208.8 | 835.2 | 10.4 | 41.8 |

Weir Position = 6 Full

| RATING CURVE FOR MODELLING OUTLET | |
|-----------------------------------|-----------------|
| Head or Ponding Depth (m) | Outflow (L/sec) |
| 0.000 | 0.00 |
| 0.025 | 1.26 |
| 0.050 | 2.52 |
| 0.075 | 3.79 |
| 0.100 | 5.05 |
| 0.125 | 6.31 |
| 0.150 | 7.57 |

| RATING CURVE FOR MODELLING ROOF STORAGE | |
|---|-------------------|
| Head or Ponding Depth (m) | Ponding Area (m2) |
| 0.000 | 0 |
| 0.025 | 23 |
| 0.050 | 93 |
| 0.075 | 209 |
| 0.100 | 371 |
| 0.125 | 580 |
| 0.150 | 835 |

WATTS ADJ ACCUTROL WEIR FLOW RATES (Flow Rates at Various Depths)

| Depth | Weir Position | | | | | |
|-------|--------------------------------------|----------|------------|------------|------------|--------|
| | 1 None | 2 Closed | 3 1/4 open | 4 1/2 open | 5 3/4 open | 6 Full |
| | Max Flow Rate per wier @150mm in gpm | | | | | |
| 0.000 | 0 | 0 | 0 | 0 | 0 | 0 |
| 0.025 | 0 | 5 | 5 | 5 | 5 | 5 |
| 0.050 | 0 | 5 | 10 | 10 | 10 | 10 |
| 0.075 | 0 | 5 | 11.25 | 12.35 | 13.75 | 15 |
| 0.100 | 0 | 5 | 12.5 | 15 | 17.5 | 20 |
| 0.125 | 0 | 5 | 13.75 | 17.5 | 21.25 | 25 |
| 0.150 | 0 | 5 | 15 | 20 | 25 | 30 |

WATTS ADJ ACCUTROL WEIR FLOW RATES (Data From Manufacturer's Catalog)

| Weir Position | Flow (gpm) per depth | | | | | | | Max Flow Rate per Weir @150mm |
|---------------|----------------------|-------|------|-------|------|-------|------|-------------------------------|
| | 0 | 25 | 50 | 75 | 100 | 125 | 150 | |
| | 0 | 0.025 | 0.05 | 0.075 | 0.1 | 0.125 | 0.15 | |
| 1 None | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0.000 |
| 2 Closed | 0 | 5 | 5 | 5 | 5 | 5 | 5 | 0.315 |
| 3 1/4 open | 0 | 5 | 10 | 11.25 | 12.5 | 13.75 | 15 | 0.946 |
| 4 1/2 open | 0 | 5 | 10 | 12.35 | 15 | 17.5 | 20 | 1.262 |
| 5 3/4 open | 0 | 5 | 10 | 13.75 | 17.5 | 21.25 | 25 | 1.577 |
| 6 Full | 0 | 5 | 10 | 15 | 20 | 25 | 30 | 1.893 |

0.0631

GRAPH OF FLOW RATE VERSUS DEPTH FOR VARIOUS WEIR POSITIONS




TABLE B23

BUILDING ROOF INFORMATION:

TABLE B23

Subcatchment Number

Total Roof Area (m2) **928**

Minimum Number of Drains Required

2*Minimum of 1 drain every 900 square metres (OBC 7.4.10.4)
(OBC Supp SB-1)*

15-min Rainfall Factor for Ottawa (mm)

23

Max Permitted Load from All Drains (Litres)

21,344

Max Permitted Load from All Drains (L/sec)

23.7*Hydraulic Load expressed in L/sec (OBC Section 7.4.10.3)*

Estimated Distance from roof edge to drains (m)

6*Not more than 15m from Edge of Roof and 30m to Adjacent Drains (OBC Section 7.4.10.3)*

Estimated area per drain (m2)

144

Estimated No. of Drains Required

7*Based on Total Roof Area / Area per Drain*

Actual No. of Drains Used

4*Use if known*

Effective Roof Percentage (%)

90.0%*Allowance for Mechanical units on roof*

Effective Total Roof Area (m2)

835

Area per Drain (m2)

209*Based on Effective Roof Area / Actual Number of Drains Used*

Max Depth of Ponding at Drains (mm)

150

Estimated Total Volume for Ponding on Roof (m3)

46.4*Prism formula, $V = 1/3 \cdot A \cdot d$*

Maximum release rate per drain at 150mm (L/s)

1.893*Based on 1 Wier Per Drain and Fully Open Position*

Max Release Rate from Total Roof (L/sec)

7.6*Based on Maximum Depth of Ponding of 150mm***RATING CURVE FOR ROOF**

| DISCHARGE VERSUS DEPTH | | | | AREA VERSUS DEPTH | | | | |
|------------------------|--------------------------------|-----------------------------------|-------------------------------------|-------------------|---------------------------|---------------------------|-----------------------------|-----------------------------|
| Ponding Depth (m) | Discharge Rate Per Drain (gpm) | Discharge Rate Per Drain (m3/sec) | Total Discharge All Drains (m3/sec) | Ponding Depth (m) | Ponding Area (Indiv) (m2) | Ponding Area (Total) (m2) | Ponding Volume (Indiv) (m3) | Ponding Volume (Total) (m3) |
| 0.000 | 0 | 0.00 | 0.00000 | 0.000 | 0.0 | 0.0 | 0.0 | 0.0 |
| 0.025 | 5 | 0.32 | 0.00126 | 0.025 | 5.8 | 23.2 | 0.0 | 0.2 |
| 0.050 | 10 | 0.63 | 0.00252 | 0.050 | 23.2 | 92.8 | 0.4 | 1.5 |
| 0.075 | 15 | 0.95 | 0.00379 | 0.075 | 52.2 | 208.8 | 1.3 | 5.2 |
| 0.100 | 20 | 1.26 | 0.00505 | 0.100 | 92.8 | 371.2 | 3.1 | 12.4 |
| 0.125 | 25 | 1.58 | 0.00631 | 0.125 | 145.0 | 580.0 | 6.0 | 24.2 |
| 0.150 | 30 | 1.89 | 0.00757 | 0.150 | 208.8 | 835.2 | 10.4 | 41.8 |

Weir Position = **6 Full**

| RATING CURVE FOR MODELLING OUTLET | |
|-----------------------------------|-----------------|
| Head or Ponding Depth (m) | Outflow (L/sec) |
| 0.000 | 0.00 |
| 0.025 | 1.26 |
| 0.050 | 2.52 |
| 0.075 | 3.79 |
| 0.100 | 5.05 |
| 0.125 | 6.31 |
| 0.150 | 7.57 |

| RATING CURVE FOR MODELLING ROOF STORAGE | |
|---|-------------------|
| Head or Ponding Depth (m) | Ponding Area (m2) |
| 0.000 | 0 |
| 0.025 | 23 |
| 0.050 | 93 |
| 0.075 | 209 |
| 0.100 | 371 |
| 0.125 | 580 |
| 0.150 | 835 |

WATTS ADJ ACCUTROL WEIR FLOW RATES (Flow Rates at Various Depths)

| Depth | Weir Position | | | | | |
|-------|--------------------------------------|----------|------------|------------|------------|--------|
| | 1 None | 2 Closed | 3 1/4 open | 4 1/2 open | 5 3/4 open | 6 Full |
| | Max Flow Rate per wier @150mm in gpm | | | | | |
| 0.000 | 0 | 0 | 0 | 0 | 0 | 0 |
| 0.025 | 0 | 5 | 5 | 5 | 5 | 5 |
| 0.050 | 0 | 5 | 10 | 10 | 10 | 10 |
| 0.075 | 0 | 5 | 11.25 | 12.35 | 13.75 | 15 |
| 0.100 | 0 | 5 | 12.5 | 15 | 17.5 | 20 |
| 0.125 | 0 | 5 | 13.75 | 17.5 | 21.25 | 25 |
| 0.150 | 0 | 5 | 15 | 20 | 25 | 30 |

WATTS ADJ ACCUTROL WEIR FLOW RATES (Data From Manufacturer's Catalog)

| Weir Position | Flow (gpm) per depth | | | | | | | Max Flow Rate per Weir @150mm |
|---------------|----------------------|-------|------|-------|------|-------|------|-------------------------------|
| | 0 | 25 | 50 | 75 | 100 | 125 | 150 | |
| | 0 | 0.025 | 0.05 | 0.075 | 0.1 | 0.125 | 0.15 | |
| 1 None | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0.000 |
| 2 Closed | 0 | 5 | 5 | 5 | 5 | 5 | 5 | 0.315 |
| 3 1/4 open | 0 | 5 | 10 | 11.25 | 12.5 | 13.75 | 15 | 0.946 |
| 4 1/2 open | 0 | 5 | 10 | 12.35 | 15 | 17.5 | 20 | 1.262 |
| 5 3/4 open | 0 | 5 | 10 | 13.75 | 17.5 | 21.25 | 25 | 1.577 |
| 6 Full | 0 | 5 | 10 | 15 | 20 | 25 | 30 | 1.893 |

0.0631


GRAPH OF FLOW RATE VERSUS DEPTH FOR VARIOUS WEIR POSITIONS

TABLE B24

BUILDING ROOF INFORMATION:

TABLE B24

| | | |
|---|--------|---|
| Subcatchment Number | | |
| Total Roof Area (m2) | 790 | |
| Minimum Number of Drains Required | 1 | Minimum of 1 drain every 900 square metres (OBC 7.4.10.4) (OBC Supp SB-1) |
| 15-min Rainfall Factor for Ottawa (mm) | 23 | |
| Max Permitted Load from All Drains (Litres) | 18,170 | |
| Max Permitted Load from All Drains (L/sec) | 20.2 | Hydraulic Load expressed in L/sec (OBC Section 7.4.10.3) |
| Estimated Distance from roof edge to drains (m) | 6 | Not more than 15m from Edge of Roof and 30m to Adjacent Drains (OBC Section 7.4.10.3) |
| Estimated area per drain (m2) | 144 | |
| Estimated No. of Drains Required | 6 | Based on Total Roof Area / Area per Drain |
| Actual No. of Drains Used | 4 | Use if known |
| Effective Roof Percentage (%) | 90.0% | Allowance for Mechanical units on roof |
| Effective Total Roof Area (m2) | 711 | |
| Area per Drain (m2) | 178 | Based on Effective Roof Area / Actual Number of Drains Used |
| Max Depth of Ponding at Drains (mm) | 150 | |
| Estimated Total Volume for Ponding on Roof (m3) | 39.5 | Prism formula, $V = 1/3 \cdot A \cdot d$ |
| Maximum release rate per drain at 150mm (L/s) | 1.893 | Based on 1 Weir Per Drain and Fully Open Position |
| Max Release Rate from Total Roof (L/sec) | 7.6 | Based on Maximum Depth of Ponding of 150mm |

RATING CURVE FOR ROOF

| DISCHARGE VERSUS DEPTH | | | | AREA VERSUS DEPTH | | | | |
|------------------------|--------------------------------|-----------------------------------|-------------------------------------|-------------------|---------------------------|---------------------------|-----------------------------|-----------------------------|
| Ponding Depth (m) | Discharge Rate Per Drain (gpm) | Discharge Rate Per Drain (m3/sec) | Total Discharge All Drains (m3/sec) | Ponding Depth (m) | Ponding Area (Indiv) (m2) | Ponding Area (Total) (m2) | Ponding Volume (Indiv) (m3) | Ponding Volume (Total) (m3) |
| 0.000 | 0 | 0.00 | 0.00000 | 0.000 | 0.0 | 0.0 | 0.0 | 0.0 |
| 0.025 | 5 | 0.32 | 0.00126 | 0.025 | 4.9 | 19.8 | 0.0 | 0.2 |
| 0.050 | 10 | 0.63 | 0.00252 | 0.050 | 19.8 | 79.0 | 0.3 | 1.3 |
| 0.075 | 15 | 0.95 | 0.00379 | 0.075 | 44.4 | 177.8 | 1.1 | 4.4 |
| 0.100 | 20 | 1.26 | 0.00505 | 0.100 | 79.0 | 316.0 | 2.6 | 10.5 |
| 0.125 | 25 | 1.58 | 0.00631 | 0.125 | 123.4 | 493.8 | 5.1 | 20.6 |
| 0.150 | 30 | 1.89 | 0.00757 | 0.150 | 177.8 | 711.0 | 8.9 | 35.6 |

Weir Position = 6 Full

| RATING CURVE FOR MODELLING OUTLET | |
|-----------------------------------|-----------------|
| Head or Ponding Depth (m) | Outflow (L/sec) |
| 0.000 | 0.00 |
| 0.025 | 1.26 |
| 0.050 | 2.52 |
| 0.075 | 3.79 |
| 0.100 | 5.05 |
| 0.125 | 6.31 |
| 0.150 | 7.57 |

| RATING CURVE FOR MODELLING ROOF STORAGE | |
|---|-------------------|
| Head or Ponding Depth (m) | Ponding Area (m2) |
| 0.000 | 0 |
| 0.025 | 20 |
| 0.050 | 79 |
| 0.075 | 178 |
| 0.100 | 316 |
| 0.125 | 494 |
| 0.150 | 711 |

WATTS ADJ ACCUTROL WEIR FLOW RATES (Flow Rates at Various Depths)


| Depth | Weir Position | | | | | |
|-------|--------------------------------------|----------|------------|------------|------------|--------|
| | 1 None | 2 Closed | 3 1/4 open | 4 1/2 open | 5 3/4 open | 6 Full |
| | Max Flow Rate per weir @150mm in gpm | | | | | |
| 0.000 | 0 | 0 | 0 | 0 | 0 | 0 |
| 0.025 | 0 | 5 | 5 | 5 | 5 | 5 |
| 0.050 | 0 | 5 | 10 | 10 | 10 | 10 |
| 0.075 | 0 | 5 | 11.25 | 12.35 | 13.75 | 15 |
| 0.100 | 0 | 5 | 12.5 | 15 | 17.5 | 20 |
| 0.125 | 0 | 5 | 13.75 | 17.5 | 21.25 | 25 |
| 0.150 | 0 | 5 | 15 | 20 | 25 | 30 |

WATTS ADJ ACCUTROL WEIR FLOW RATES (Data From Manufacturer's Catalog)

| Weir Position | Flow (gpm) per depth | | | | | | | Max Flow Rate per Weir @150mm |
|---------------|----------------------|-------|------|-------|------|-------|------|-------------------------------|
| | 0 | 25 | 50 | 75 | 100 | 125 | 150 | |
| | 0 | 0.025 | 0.05 | 0.075 | 0.1 | 0.125 | 0.15 | |
| 1 None | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0.000 |
| 2 Closed | 0 | 5 | 5 | 5 | 5 | 5 | 5 | 0.315 |
| 3 1/4 open | 0 | 5 | 10 | 11.25 | 12.5 | 13.75 | 15 | 0.946 |
| 4 1/2 open | 0 | 5 | 10 | 12.35 | 15 | 17.5 | 20 | 1.262 |
| 5 3/4 open | 0 | 5 | 10 | 13.75 | 17.5 | 21.25 | 25 | 1.577 |
| 6 Full | 0 | 5 | 10 | 15 | 20 | 25 | 30 | 1.893 |

0.0631

GRAPH OF FLOW RATE VERSUS DEPTH FOR VARIOUS WEIR POSITIONS



Appendix C – Manufacturers Information

Watts ACCUTROL Flow Control Specification

Stormceptor Sizing Report

Stormceptor EF Brochure

Stormceptor EF05 Detail



Adjustable Accutrol Weir

Tag: _____

Adjustable Flow Control for Roof Drains

ADJUSTABLE ACCUTROL (for Large Sump Roof Drains only)



For more flexibility in controlling flow with heads deeper than 2", Watts Drainage offers the Adjustable Accutrol. The Adjustable Accutrol Weir is designed with a single parabolic opening that can be covered to restrict flow above 2" of head to less than 5 gpm per inch, up to 6" of head. To adjust the flow rate for depths over 2" of head, set the slot in the adjustable upper cone according to the flow rate required. Refer to Table 1 below.

Note: Flow rates are directly proportional to the amount of weir opening that is exposed.

EXAMPLE:

For example, if the adjustable upper cone is set to cover 1/2 of the weir opening, flow rates above 2" of head will be restricted to 2-1/2 gpm per inch of head.

Therefore, at 3" of head, the flow rate through the Accutrol Weir that has 1/2 the slot exposed will be:
[5 gpm (per inch of head) x 2 inches of head] + 2-1/2 gpm (for the third inch of head) = 12-1/2 gpm.



1/2 Weir Opening Exposed Shown Above

TABLE 1. Adjustable Accutrol Flow Rate Settings

| Weir Opening Exposed | 1" | 2" | 3" | 4" | 5" | 6" |
|----------------------|--------------------------------|----|-------|------|-------|----|
| | Flow Rate (gallons per minute) | | | | | |
| Fully Exposed | 5 | 10 | 15 | 20 | 25 | 30 |
| 3/4 | 5 | 10 | 13.75 | 17.5 | 21.25 | 25 |
| 1/2 | 5 | 10 | 12.5 | 15 | 17.5 | 20 |
| 1/4 | 5 | 10 | 11.25 | 12.5 | 13.75 | 15 |
| Closed | 5 | 5 | 5 | 5 | 5 | 5 |

Job Name _____

Contractor _____

Job Location _____

Contractor's P.O. No. _____

Engineer _____

Representative _____

Watts product specifications in U.S. customary units and metric are approximate and are provided for reference only. For precise measurements, please contact Watts Technical Service. Watts reserves the right to change or modify product design, construction, specifications, or materials without prior notice and without incurring any obligation to make such changes and modifications on Watts products previously or subsequently sold.

USA: Tel: (800) 338-2581 • Fax: (828) 248-3929 • Watts.com
Canada: Tel: (905) 332-4090 • Fax: (905) 332-7068 • Watts.ca
Latin America: Tel: (52) 81-1001-8600 • Fax: (52) 81-8000-7091 • Watts.com



A Watts Water Technologies Company

Stormceptor® EF



Stormceptor® EF Overview

About Imbrium® Systems

Imbrium® Systems is dedicated to protecting Canada's waterways. Based on our knowledge and experience in the Canadian stormwater industry, we have the ability to provide the most effective stormwater treatment technologies that capture and retain harmful pollutants from urban runoff before it enters our streams, rivers, lakes, and oceans.

Imbrium's engineered treatment solutions have been third-party tested and verified in accordance with the ISO 14034 Environmental Technology Verification (ETV) protocol to ensure performance in real-world conditions as designed. Our team of highly skilled engineers and partners provide the highest level of service from design to installation and long-term maintenance.

By working with Imbrium and our partners, you can expect superior treatment technology, unparalleled customer service, compliance with local stormwater regulations, and cleaner water. To find your local representative, please visit www.imbriumsystems.com/localrep.



Learn About the Stormceptor® EF

Go online and watch our animation to learn how the Stormceptor EF works. The animation highlights important features of the Stormceptor EF including:

- Functionality
- Applications
- Inspection and Maintenance

To view the Stormceptor EF animation, visit www.imbriumsystems.com/stormceptoref



Stormceptor® EF


A CONTINUATION AND EVOLUTION OF THE MOST GLOBALLY RECOGNIZED OIL GRIT SEPARATOR (OGS) STORMWATER TREATMENT TECHNOLOGY

Stormceptor EF effectively targets sediment (TSS), free oils, gross pollutants and other pollutants that attach to particles, such as nutrients and metals. Stormceptor EF's independently tested and verified, patent- pending treatment and scour prevention platform ensures pollutants are captured and contained during all rainfall events.

Stormceptor EF also offers design flexibility in one platform, accepting flow from a single inlet pipe, multiple inlet pipes, and from the surface through an inlet grate. Stormceptor EF can also accommodate a 90-degree inlet to outlet bend angle, and tailwater conditions.

Ideal Uses


- Sediment (TSS) removal
- Hydrocarbon control and hotspots (Stormceptor EF)
- Debris and small floatables capture
- Pretreatment for filtration, detention/retention systems, ponds, wetlands, and bioretention
- Retrofit and redevelopment projects



Stormceptor EF and Stormceptor EFO have been verified in accordance with ISO 14034 Environment Management - Environmental Technology Verification (ETV) protocol.

How the Stormceptor® EF Works

- Flow enters the Stormceptor through one or more inlet pipes or an inlet grate.
- A specially designed insert reduces influent velocity by creating a pond upstream of the weir, allowing sediments to begin settling.
- Swirling flow sweeps water and pollutants across the sloped insert surface to the drop pipe, where a strong vortex draws water, sediment, oil, and debris down the drop pipe cone and into the lower chamber.
- Flow exits the drop pipe through two large rectangular openings, while also diffusing through perforations in multiple directions. This reduces stream velocities and increases pollutant removal efficiency while preventing resuspension and washout of previously captured pollutants.
- Floatables, such as oil and gross pollutants, rise up and are trapped beneath the insert.
- Sediment settles to the sump.
- Treated stormwater discharges to the top side of the insert downstream of the weir, where it exits through the outlet pipe.
- During intense storm events excess influent passes over the weir and exits through the outlet pipe. The pond continues to separate sediment from all incoming flows, while full treatment in the lower chamber continues at the maximum flow rate, without scour of previously captured pollutants.




* Fiberglass system is an option

Stormceptor® EF Features & Benefits




EASY TO INSTALL

Small footprint saves time and money with limited disruption to your site.



SEAMLESS

Minimal drop between inlet and outlet pipes makes Stormceptor ideal for retrofits and new development projects.




FLEXIBLE

Multiple inlets can connect to a single unit. Can be used as a bend structure.

| FEATURES | BENEFITS |
|--|---|
| Patent-pending enhanced flow treatment and scour prevention technology | Superior, third-party verified performance |
| Third-party verified light liquid capture and retention (EFO version) | Proven performance for fuel/oil hotspot locations |
| Functions as bend, junction or inlet structure | Cost savings and design flexibility |
| Minimal drop between inlet and outlet | Site installation ease |
| Large diameter outlet riser for inspection and maintenance | Easy maintenance access from grade |



Stormceptor® EF Standard Configurations



OPTIONS & ACCESSORIES

The following options and accessories are available for specific functions and site conditions:

- **Tailwater/Submerged Site** – For sites with standing water during dry weather periods, weir modifications can be implemented to ensure optimal performance.
- **Additional Sediment Storage Volume** – For sites with high pollutant loads or remote sites, additional sediment storage volume can easily be added.
- **Oil Alarm** – To mitigate spill liability, a monitoring system can be employed to trigger a visual and audible alarm when an oil or fuel spill occurs.
- **Additional Oil Capture** – A draw-off tank can be incorporated to increase spill storage capacity.
- **High Load** – Standard design loading is CHBDC or AASHTO H-20. Specialized loading can be designed to withstand very high loadings typical of airports and port facilities.
- **Lightweight** – Sites that required lightweight or above ground units are available as complete fiberglass systems.



Optional Oil Alarm

For any of these options or accessories, please contact your Stormceptor representative for design assistance.

Stormceptor® EFO

Accidents and spills happen, whether it is a fueling station, port, industrial site, or general hot spot with daily vehicle traffic. Protect the environment and your site from potentially costly clean-up, remediation, litigation and fines with the Stormceptor EFO configuration.

The Stormceptor EFO has been third-party tested to ensure oil capture, and retention during high flow events. The hydraulics of the Stormceptor EFO have been optimized to enhance oil and hydrocarbon capture.

STORMCEPTOR EFO – HYDROCARBON SPILL PROTECTION

- Stormceptor EFO configuration has been third-party performance tested for safe oil capture and retention.
- Patent-pending technology ensures captured oil and sediment are retained even during the largest rain events, for secure storage, environmental protection and easy removal.
- Stormceptor EFO provides double wall containment for captured hydrocarbons.
- Stormceptor EFO is ideal for gas stations, fuel depots, ports, garages, loading docks, industrial sites, fast food locations, high-collision intersections and other hotspots with spill-prone areas.
- Stormceptor EFO can accommodate an optional oil alarm and additional storage to increase spill storage capacity.

Stormceptor® Inspection & Maintenance

Conducted at grade, the Stormceptor EF design makes inspection and maintenance an easy and inexpensive process. Once maintained, the Stormceptor EF is functionally restored as designed, with full pollutant capture capacity.

MAINTENANCE RECOMMENDATIONS:

- Inspect every six months for the first year to determine the pollutant accumulation rate.
- In subsequent years, inspections can be based on observations or local requirements.
- Inspect the unit immediately after an oil, fuel or chemical spill. A licensed waste management company should remove oil and sediment, and dispose responsibly.



Stormceptor maintenance is performed at grade with a standard vacuum truck



FILTERRA BIORETENTION

The Filterra® Bioretention System is an engineered biofiltration device with components that make it similar to bioretention in pollutant removal and application, but has been optimized for high volume/flow treatment in a compact system.



JELLYFISH FILTER

The Jellyfish® Filter is a stormwater treatment technology featuring pretreatment and membrane filtration in a compact stand-alone treatment system that removes a high level and a wide variety of stormwater pollutants.



LITTATRAP CATCH BASIN

The LittaTrap™ is a simple and effective solution to remove sediment and trash from stormwater systems at its source. The LittaTrap sits inside the storm drain and captures and retains sediment and trash before it enters stormwater infrastructure, effectively pretreating downstream structures and aiding in pollutant removal.

LEARN MORE

- Access project profiles, photos, videos, and more online at www.imbriumsystems.com/stormceptoref.

REQUEST DESIGN ASSISTANCE

- Call us at (888) 279-8826 or 301-279-8827 to talk to one of our engineers for technical support or design assistance.

START A PROJECT

- Submit your system requirements on our product Design Worksheet at www.imbriumsystems.com/pdw.

FIND A LOCAL REPRESENTATIVE

- Visit www.imbriumsystems.com/localrep for contact information for your local Imbrium representative.



© 2019 Imbrium Systems Inc.

+1 416-960-9900

www.imbriumsystems.com

All Rights Reserved. Printed in the USA.

Imbrium® Systems is an engineered stormwater treatment company that designs and manufactures stormwater treatment solutions that protect water resources from harmful pollutants. By developing technologies to address the long-term impact of urban runoff, Imbrium ensures our clients' projects are compliant with government water quality regulations. For information, visit www.imbriumsystems.com or call +1 416-960-9900.

Get Social With Us!



IB-Stormceptor EF Bro 5/19 PDF

NOTHING IN THIS CATALOG SHOULD BE CONSTRUED AS AN EXPRESSED WARRANTY OR AN IMPLIED WARRANTY OF MERCHANTABILITY OR FITNESS FOR ANY PARTICULAR PURPOSE. SEE THE IMBRIUM STANDARD CONDITIONS OF SALE (VIEWABLE AT WWW.IMBRIUMSYSTEMS.COM/TERMS-OF-USE) FOR MORE INFORMATION.

Stormceptor® EF Sizing Report

Imbrium® Systems

ESTIMATED NET ANNUAL SEDIMENT (TSS) LOAD REDUCTION

05/29/2025

| | | | |
|---------------------------|-------------------|-------------------|-------------------|
| Province: | Ontario | Project Name: | 1015 Tweddle |
| City: | Ottawa | Project Number: | 67908 |
| Nearest Rainfall Station: | OTTAWA CDA RCS | Designer Name: | amr salem |
| Climate Station Id: | 6105978 | Designer Company: | exp |
| Years of Rainfall Data: | 20 | Designer Email: | amr.salem@exp.com |
| | | Designer Phone: | 613-688-1899 |
| Site Name: | 1015 Tweddle Road | EOR Name: | |
| | | EOR Company: | |
| Drainage Area (ha): | 1.05 | EOR Email: | |
| Runoff Coefficient 'c': | 0.85 | EOR Phone: | |

| | |
|---|-------|
| Particle Size Distribution: | Fine |
| Target TSS Removal (%): | 80.0 |
| Required Water Quality Runoff Volume Capture (%): | 90.00 |
| Estimated Water Quality Flow Rate (L/s): | 28.81 |
| Oil / Fuel Spill Risk Site? | No |
| Upstream Flow Control? | No |
| Peak Conveyance (maximum) Flow Rate (L/s): | |
| Influent TSS Concentration (mg/L): | 200 |
| Estimated Average Annual Sediment Load (kg/yr): | 1087 |
| Estimated Average Annual Sediment Volume (L/yr): | 884 |

Net Annual Sediment (TSS) Load Reduction Sizing Summary

| Stormceptor Model | TSS Removal Provided (%) |
|-------------------|--------------------------|
| EF4 | 78 |
| EF5 | 83 |
| EF6 | 87 |
| EF8 | 92 |
| EF10 | 95 |
| EF12 | 97 |

Recommended Stormceptor EF Model: **EF5**
 Estimated Net Annual Sediment (TSS) Load Reduction (%): **83**
 Water Quality Runoff Volume Capture (%): **> 90**

THIRD-PARTY TESTING AND VERIFICATION

► **Stormceptor® EF and Stormceptor® EFO** are the latest evolutions in the Stormceptor® oil-grit separator (OGS) technology series, and are designed to remove a wide variety of pollutants from stormwater and snowmelt runoff. These technologies have been third-party tested in accordance with the Canadian ETV **Procedure for Laboratory Testing of Oil-Grit Separators** and performance has been third-party verified in accordance with the **ISO 14034 Environmental Technology Verification (ETV)** protocol.

PERFORMANCE

► **Stormceptor® EF and EFO** remove stormwater pollutants through gravity separation and floatation, and feature a patent-pending design that generates positive removal of total suspended solids (TSS) throughout each storm event, including high-intensity storms. Captured pollutants include sediment, free oils, and sediment-bound pollutants such as nutrients, heavy metals, and petroleum hydrocarbons. Stormceptor is sized to remove a high level of TSS from the frequent rainfall events that contribute the vast majority of annual runoff volume and pollutant load. The technology incorporates an internal bypass to convey excessive stormwater flows from high-intensity storms through the device without resuspension and washout (scour) of previously captured pollutants. Proper routine maintenance ensures high pollutant removal performance and protection of downstream waterways.

PARTICLE SIZE DISTRIBUTION (PSD)

► The **Canadian ETV PSD** shown in the table below was used, or in part, for this sizing. This is the identical PSD that is referenced in the Canadian ETV **Procedure for Laboratory Testing of Oil-Grit Separators** for both sediment removal testing and scour testing. The Canadian ETV PSD contains a wide range of particle sizes in the sand and silt fractions, and is considered reasonably representative of the particle size fractions found in typical urban stormwater runoff.

| Particle Size (µm) | Percent Less Than | Particle Size Fraction (µm) | Percent |
|--------------------|-------------------|-----------------------------|---------|
| 1000 | 100 | 500-1000 | 5 |
| 500 | 95 | 250-500 | 5 |
| 250 | 90 | 150-250 | 15 |
| 150 | 75 | 100-150 | 15 |
| 100 | 60 | 75-100 | 10 |
| 75 | 50 | 50-75 | 5 |
| 50 | 45 | 20-50 | 10 |
| 20 | 35 | 8-20 | 15 |
| 8 | 20 | 5-8 | 10 |
| 5 | 10 | 2-5 | 5 |
| 2 | 5 | <2 | 5 |


Stormceptor®EF Sizing Report

| Rainfall Intensity (mm / hr) | Percent Rainfall Volume (%) | Cumulative Rainfall Volume (%) | Flow Rate (L/s) | Flow Rate (L/min) | Surface Loading Rate (L/min/m²) | Removal Efficiency (%) | Incremental Removal (%) | Cumulative Removal (%) |
|--|-----------------------------|--------------------------------|-----------------|-------------------|---------------------------------|------------------------|-------------------------|------------------------|
| 0.50 | 8.6 | 8.6 | 1.24 | 74.0 | 41.0 | 100 | 8.6 | 8.6 |
| 1.00 | 20.3 | 29.0 | 2.48 | 149.0 | 82.0 | 98 | 20.0 | 28.6 |
| 2.00 | 16.2 | 45.2 | 4.96 | 298.0 | 164.0 | 88 | 14.3 | 43.0 |
| 3.00 | 12.0 | 57.2 | 7.44 | 447.0 | 245.0 | 81 | 9.7 | 52.7 |
| 4.00 | 8.4 | 65.6 | 9.92 | 595.0 | 327.0 | 78 | 6.5 | 59.2 |
| 5.00 | 5.9 | 71.6 | 12.41 | 744.0 | 409.0 | 74 | 4.4 | 63.6 |
| 6.00 | 4.6 | 76.2 | 14.89 | 893.0 | 491.0 | 72 | 3.4 | 67.0 |
| 7.00 | 3.1 | 79.3 | 17.37 | 1042.0 | 573.0 | 71 | 2.2 | 69.2 |
| 8.00 | 2.7 | 82.0 | 19.85 | 1191.0 | 654.0 | 70 | 1.9 | 71.1 |
| 9.00 | 3.3 | 85.3 | 22.33 | 1340.0 | 736.0 | 70 | 2.3 | 73.4 |
| 10.00 | 2.3 | 87.6 | 24.81 | 1489.0 | 818.0 | 69 | 1.6 | 75.0 |
| 11.00 | 1.6 | 89.2 | 27.29 | 1638.0 | 900.0 | 68 | 1.1 | 76.1 |
| 12.00 | 1.3 | 90.5 | 29.77 | 1786.0 | 982.0 | 68 | 0.9 | 77.0 |
| 13.00 | 1.7 | 92.2 | 32.25 | 1935.0 | 1063.0 | 69 | 1.2 | 78.2 |
| 14.00 | 1.2 | 93.5 | 34.74 | 2084.0 | 1145.0 | 70 | 0.9 | 79.0 |
| 15.00 | 1.2 | 94.6 | 37.22 | 2233.0 | 1227.0 | 72 | 0.8 | 79.9 |
| 16.00 | 0.7 | 95.3 | 39.70 | 2382.0 | 1309.0 | 73 | 0.5 | 80.4 |
| 17.00 | 0.7 | 96.1 | 42.18 | 2531.0 | 1391.0 | 75 | 0.6 | 80.9 |
| 18.00 | 0.4 | 96.5 | 44.66 | 2680.0 | 1472.0 | 72 | 0.3 | 81.2 |
| 19.00 | 0.4 | 96.9 | 47.14 | 2829.0 | 1554.0 | 68 | 0.3 | 81.5 |
| 20.00 | 0.2 | 97.1 | 49.62 | 2977.0 | 1636.0 | 65 | 0.1 | 81.6 |
| 21.00 | 0.5 | 97.5 | 52.10 | 3126.0 | 1718.0 | 62 | 0.3 | 81.9 |
| 22.00 | 0.2 | 97.8 | 54.59 | 3275.0 | 1800.0 | 59 | 0.1 | 82.1 |
| 23.00 | 1.0 | 98.8 | 57.07 | 3424.0 | 1881.0 | 56 | 0.6 | 82.6 |
| 24.00 | 0.3 | 99.1 | 59.55 | 3573.0 | 1963.0 | 54 | 0.1 | 82.8 |
| 25.00 | 0.0 | 99.1 | 62.03 | 3722.0 | 2045.0 | 52 | 0.0 | 82.8 |
| 30.00 | 0.9 | 100.0 | 74.43 | 4466.0 | 2454.0 | 43 | 0.4 | 83.2 |
| 35.00 | 0.0 | 100.0 | 86.84 | 5210.0 | 2863.0 | 38 | 0.0 | 83.2 |
| 40.00 | 0.0 | 100.0 | 99.25 | 5955.0 | 3272.0 | 33 | 0.0 | 83.2 |
| 45.00 | 0.0 | 100.0 | 111.65 | 6699.0 | 3681.0 | 29 | 0.0 | 83.2 |
| Estimated Net Annual Sediment (TSS) Load Reduction = | | | | | | | | 83 % |


Climate Station ID: 6105978 Years of Rainfall Data: 20

Stormceptor®EF Sizing Report

RAINFALL DATA FROM OTTAWA CDA RCS RAINFALL STATION



INCREMENTAL AND CUMULATIVE TSS REMOVAL FOR THE RECOMMENDED STORMCEPTOR® MODEL



Stormceptor® EF Sizing Report

Maximum Pipe Diameter / Peak Conveyance

| Stormceptor EF / EFO | Model Diameter | | Min Angle Inlet / Outlet Pipes | Max Inlet Pipe Diameter | | Max Outlet Pipe Diameter | | Peak Conveyance Flow Rate | |
|-------------------------|----------------|------|-----------------------------------|----------------------------|------|-----------------------------|------|------------------------------|-------|
| | (m) | (ft) | | (mm) | (in) | (mm) | (in) | (L/s) | (cfs) |
| EF4 / EFO4 | 1.2 | 4 | 90 | 609 | 24 | 609 | 24 | 425 | 15 |
| EF5 / EFO5 | 1.5 | 5 | 90 | 762 | 30 | 762 | 30 | 710 | 25 |
| EF6 / EFO6 | 1.8 | 6 | 90 | 914 | 36 | 914 | 36 | 990 | 35 |
| EF8 / EFO8 | 2.4 | 8 | 90 | 1219 | 48 | 1219 | 48 | 1700 | 60 |
| EF10 / EFO10 | 3.0 | 10 | 90 | 1828 | 72 | 1828 | 72 | 2830 | 100 |
| EF12 / EFO12 | 3.6 | 12 | 90 | 1828 | 72 | 1828 | 72 | 2830 | 100 |

SCOUR PREVENTION AND ONLINE CONFIGURATION


► **Stormceptor® EF and EFO** feature an internal bypass and superior scour prevention technology that have been demonstrated in third-party testing according to the scour testing provisions of the Canadian ETV **Procedure for Laboratory Testing of Oil-Grit Separators**, and the exceptional scour test performance has been third-party verified in accordance with the ISO 14034 ETV protocol. As a result, Stormceptor EF and EFO are approved for online installation, eliminating the need for costly additional bypass structures, piping, and installation expense.

DESIGN FLEXIBILITY


► **Stormceptor® EF and EFO** offers design flexibility in one simplified platform, accepting stormwater flow from a single inlet pipe or multiple inlet pipes, and/or surface runoff through an inlet grate. The device can also serve as a junction structure, accommodate a 90-degree inlet-to-outlet bend angle, and can be modified to ensure performance in submerged conditions.

OIL CAPTURE AND RETENTION

► While Stormceptor® EF will capture and retain oil from dry weather spills and low intensity runoff, **Stormceptor® EFO** has demonstrated superior oil capture and greater than 99% oil retention in third-party testing according to the light liquid re-entrainment testing provisions of the Canadian ETV **Procedure for Laboratory Testing of Oil-Grit Separators**. Stormceptor EFO is recommended for sites where oil capture and retention is a requirement.



Stormceptor® EF Sizing Report



INLET-TO-OUTLET DROP

Elevation differential between inlet and outlet pipe inverts is dictated by the angle at which the inlet pipe(s) enters the unit.

0° - 45° : The inlet pipe is 1-inch (25mm) higher than the outlet pipe.

45° - 90° : The inlet pipe is 2-inches (50mm) higher than the outlet pipe.

HEAD LOSS

The head loss through Stormceptor EF is similar to that of a 60-degree bend structure. The applicable K value for calculating minor losses through the unit is 1.1.

For submerged conditions the applicable K value is 3.0.

Pollutant Capacity

| Stormceptor EF / EFO | Model Diameter | | Depth (Outlet Pipe Invert to Sump Floor) | | Oil Volume | | Recommended Sediment Maintenance Depth * | | Maximum Sediment Volume * | | Maximum Sediment Mass ** | |
|----------------------|----------------|------|--|------|------------|-------|--|------|---------------------------|-------|--------------------------|--------|
| | (m) | (ft) | (m) | (ft) | (L) | (Gal) | (mm) | (in) | (L) | (ft³) | (kg) | (lb) |
| EF4 / EFO4 | 1.2 | 4 | 1.52 | 5.0 | 265 | 70 | 203 | 8 | 1190 | 42 | 1904 | 5250 |
| EF5 / EFO5 | 1.5 | 5 | 1.62 | 5.3 | 420 | 111 | 305 | 10 | 2124 | 75 | 2612 | 5758 |
| EF6 / EFO6 | 1.8 | 6 | 1.93 | 6.3 | 610 | 160 | 305 | 12 | 3470 | 123 | 5552 | 15375 |
| EF8 / EFO8 | 2.4 | 8 | 2.59 | 8.5 | 1070 | 280 | 610 | 24 | 8780 | 310 | 14048 | 38750 |
| EF10 / EFO10 | 3.0 | 10 | 3.25 | 10.7 | 1670 | 440 | 610 | 24 | 17790 | 628 | 28464 | 78500 |
| EF12 / EFO12 | 3.6 | 12 | 3.89 | 12.8 | 2475 | 655 | 610 | 24 | 31220 | 1103 | 49952 | 137875 |

*Increased sump depth may be added to increase sediment storage capacity

** Average density of wet packed sediment in sump = 1.6 kg/L (100 lb/ft³)

| Feature | Benefit | Feature Appeals To |
|---|---|---|
| Patent-pending enhanced flow treatment and scour prevention technology | Superior, verified third-party performance | Regulator, Specifying & Design Engineer |
| Third-party verified light liquid capture and retention for EFO version | Proven performance for fuel/oil hotspot locations | Regulator, Specifying & Design Engineer, Site Owner |
| Functions as bend, junction or inlet structure | Design flexibility | Specifying & Design Engineer |
| Minimal drop between inlet and outlet | Site installation ease | Contractor |
| Large diameter outlet riser for inspection and maintenance | Easy maintenance access from grade | Maintenance Contractor & Site Owner |

STANDARD STORMCEPTOR EF/EFO DRAWINGS

For standard details, please visit <http://www.imbriumsystems.com/stormwater-treatment-solutions/stormceptor-ef>

STANDARD STORMCEPTOR EF/EFO SPECIFICATION

For specifications, please visit <http://www.imbriumsystems.com/stormwater-treatment-solutions/stormceptor-ef>

STANDARD PERFORMANCE SPECIFICATION FOR “OIL GRIT SEPARATOR” (OGS) STORMWATER QUALITY TREATMENT DEVICE

PART 1 – GENERAL

1.1 WORK INCLUDED

This section specifies requirements for selecting, sizing, and designing an underground Oil Grit Separator (OGS) device for stormwater quality treatment, with third-party testing results and a Statement of Verification in accordance with ISO 14034 Environmental Management – Environmental Technology Verification (ETV).

1.2 REFERENCE STANDARDS & PROCEDURES

ISO 14034:2016 Environmental management – Environmental technology verification (ETV)

Canadian Environmental Technology Verification (ETV) Program’s **Procedure for Laboratory Testing of Oil-Grit Separators.**

1.3 SUBMITTALS

1.3.1 All submittals, including sizing reports & shop drawings, shall be submitted upon request with each order to the contractor then forwarded to the Engineer of Record for review and acceptance. Shop drawings shall detail all OGS components, elevations, and sequence of construction.

1.3.2 Alternative devices shall have features identical to or greater than the specified device, including: treatment chamber diameter, treatment chamber wet volume, sediment storage volume, and oil storage volume.

1.3.3 Unless directed otherwise by the Engineer of Record, OGS stormwater quality treatment product substitutions or alternatives submitted within ten days prior to project bid shall not be accepted. All alternatives or substitutions submitted shall be signed and sealed by a local registered Professional Engineer, based on the exact same criteria detailed in Section 3, in entirety, subject to review and approval by the Engineer of Record.

PART 2 – PRODUCTS

2.1 OGS POLLUTANT STORAGE

The OGS device shall include a sump for sediment storage, and a protected volume for the capture and storage of petroleum hydrocarbons and buoyant gross pollutants. The **minimum** sediment & petroleum hydrocarbon storage capacity shall be as follows:

| | | |
|-------|-------------------------------------|---|
| 2.1.1 | 4 ft (1219 mm) Diameter OGS Units: | 1.19 m ³ sediment / 265 L oil |
| | 5 ft (1524 mm) Diameter OGS Units: | 1.95 m ³ sediment / 420L oil |
| | 6 ft (1829 mm) Diameter OGS Units: | 3.48 m ³ sediment / 609 L oil |
| | 8 ft (2438 mm) Diameter OGS Units: | 8.78 m ³ sediment / 1,071 L oil |
| | 10 ft (3048 mm) Diameter OGS Units: | 17.78 m ³ sediment / 1,673 L oil |
| | 12 ft (3657 mm) Diameter OGS Units: | 31.23 m ³ sediment / 2,476 L oil |

PART 3 – PERFORMANCE & DESIGN

3.1 GENERAL

The OGS stormwater quality treatment device shall be verified in accordance with ISO 14034:2016 Environmental management – Environmental technology verification (ETV). The OGS stormwater quality treatment device shall remove oil, sediment and gross pollutants from stormwater runoff during frequent wet weather events, and retain these pollutants during less frequent high flow wet weather events below the insert within the OGS for later removal during maintenance. The Manufacturer shall have at least ten (10) years of local experience, history and success in engineering design, manufacturing and production and supply of OGS stormwater quality treatment device systems, acceptable to the Engineer of Record.

3.2 SIZING METHODOLOGY

The OGS device shall be engineered, designed and sized to provide stormwater quality treatment based on treating a minimum of 90 percent of the average annual runoff volume and a minimum removal of an annual average 60% of the sediment (TSS) load based on the Particle Size Distribution (PSD) specified in the sizing report for the specified device. Sizing of the OGS shall be determined by use of a minimum ten (10) years of local historical rainfall data provided by Environment Canada. Sizing shall also be determined by use of the sediment removal performance data derived from the ISO 14034 ETV third-party verified laboratory testing data from testing conducted in accordance with the Canadian ETV protocol Procedure for Laboratory Testing of Oil-Grit Separators, as follows:

3.2.1 Sediment removal efficiency for a given surface loading rate and its associated flow rate shall be based on sediment removal efficiency demonstrated at the seven (7) tested surface loading rates specified in the protocol, ranging 40 L/min/m² to 1400 L/min/m², and as stated in the ISO 14034 ETV Verification Statement for the OGS device.

3.2.2 Sediment removal efficiency for surface loading rates between 40 L/min/m² and 1400 L/min/m² shall be based on linear interpolation of data between consecutive tested surface loading rates.

3.2.3 Sediment removal efficiency for surface loading rates less than the lowest tested surface loading rate of 40 L/min/m² shall be assumed to be identical to the sediment removal efficiency at 40 L/min/m². No extrapolation shall be allowed that results in a sediment removal efficiency that is greater than that demonstrated at 40 L/min/m².

3.2.4 Sediment removal efficiency for surface loading rates greater than the highest tested surface loading rate of 1400 L/min/m² shall assume zero sediment removal for the portion of flow that exceeds 1400 L/min/m², and shall be calculated using a simple proportioning formula, with 1400 L/min/m² in the numerator and the higher surface loading rate in the denominator, and multiplying the resulting fraction times the sediment removal efficiency at 1400 L/min/m².


The OGS device shall also have sufficient annual sediment storage capacity as specified and calculated in Section 2.1.

3.3 CANADIAN ETV or ISO 14034 ETV VERIFICATION OF SCOUR TESTING

The OGS device shall have Canadian ETV or ISO 14034 ETV Verification of third-party scour testing conducted in accordance with the Canadian ETV Program's **Procedure for Laboratory Testing of Oil-Grit Separators**.


3.3.1 To be acceptable for on-line installation, the OGS device must demonstrate an average scour test effluent concentration less than 10 mg/L at each surface loading rate tested, up to and including 2600 L/min/m².






FOR SITE SPECIFIC DRAWINGS PLEASE CONTACT YOUR LOCAL STORMCEPTOR REPRESENTATIVE. SITE SPECIFIC DRAWINGS ARE BASED ON THE BEST AVAILABLE INFORMATION AT THE TIME. SOME FIELD REVISIONS TO THE SYSTEM LOCATION OR CONNECTION PIPING MAY BE NECESSARY BASED ON AVAILABLE SPACE OR SITE CONFIGURATION REVISIONS. ELEVATIONS SHOULD BE MAINTAINED EXCEPT WHERE NOTED ON BYPASS STRUCTURE (IF REQUIRED).

- A. ANY SUB-BASE, BACKFILL DEPTH, AND/OR ANTI-FLOTATION PROVISIONS ARE SITE-SPECIFIC DESIGN CONSIDERATIONS AND SHALL BE SPECIFIED BY ENGINEER OF RECORD.
- B. CONTRACTOR TO PROVIDE EQUIPMENT WITH SUFFICIENT LIFTING AND REACH CAPACITY TO LIFT AND SET THE STRUCTURE (LIFTING CLUTCHES PROVIDED)
- C. CONTRACTOR WILL INSTALL AND LEVEL THE STRUCTURE, SEALING THE JOINTS, LINE ENTRY AND EXIT POINTS (NON-SHRINK GROUT WITH APPROVED WATERSTOP OR FLEXIBLE BOOT)
- D. CONTRACTOR TO TAKE APPROPRIATE MEASURES TO PROTECT THE DEVICE FROM CONSTRUCTION-RELATED EROSION RUNOFF.
- E. DEVICE ACTIVATION, BY CONTRACTOR, SHALL OCCUR ONLY AFTER SITE HAS BEEN STABILIZED AND THE STORMCEPTOR UNIT IS CLEAN AND FREE OF DEBRIS.





407 FARMWAY DRIVE, WHITBY, ON L1N 3A9
TF 800-585-4801 CA 415-860-2600 INTL. +1-416-260-2600

THE GUARANTEEORS ARE NOT PROVIDERS OF ONE OF THE FOLLOWING SERVICES:
 • Commercial Insurance (See Section 10.1.1.1) • Financial Services (See Section 10.1.1.2)
 • Construction Management (See Section 10.1.1.3) • Construction Management at Risk (See Section 10.1.1.4)
 • Construction Management in Name Only (See Section 10.1.1.5) • Construction Management in Name Only (See Section 10.1.1.6)
 • Construction Management in Name Only (See Section 10.1.1.7) • Construction Management in Name Only (See Section 10.1.1.8)
 • Construction Management in Name Only (See Section 10.1.1.9) • Construction Management in Name Only (See Section 10.1.1.10)

| | |
|---|---------------------------|
| DATE: 8/22/2024 | |
| DESIGNED: JSK | DRAWN: EC |
| CHECKED: BSF | APPROVED: |
| PROJECT No.: EFO5 | SEQUENCE No.: * |
| SHEET: <div style="display: flex; justify-content: space-around; font-size: 24px; font-weight: bold;">1 OF 1</div> | |

| | | | |
|------|----------|----------------------|------|
| 0 | 08/22/24 | INITIAL RELEASE | EC |
| MARK | DATE | REVISION DESCRIPTION | BY |
| #### | #### | #### | #### |
| #### | #### | #### | #### |
| #### | #### | #### | #### |
| #### | #### | #### | #### |

Stormceptor® EF

SCALE = NTS

The design and information shown on this drawing is provided as a service to the project owner, engineer and contractor by Imbrium Systems ("Imbrium"). Neither this drawing, nor any part thereof, may be used, reproduced or modified in any manner without the prior written consent of Imbrium. Failure to comply is done at the user's own risk and Imbrium expressly disclaims any liability or responsibility for such use.

If discrepancies between the supplied information upon which this drawing was based and actual site conditions are discovered, the user shall be responsible for any discrepancies that must be reported to Imbrium immediately for re-evaluation of the design. Imbrium accepts no liability for designs based on missing, incomplete or inaccurate information supplied by others.

Appendix D – Consultation / Correspondence

City of Ottawa Water System Boundary Conditions

Boundary Conditions 1009 Trim Road

Provided Information

| Scenario | Demand | |
|----------------------|--------|--------|
| | L/min | L/s |
| Average Daily Demand | 342 | 5.70 |
| Maximum Daily Demand | 852 | 14.20 |
| Peak Hour | 1,866 | 31.10 |
| Fire Flow Demand #1 | 6,000 | 100.00 |
| Fire Flow Demand #2 | 10,020 | 167.00 |

Location



Results

Connection 1 – Jeanne D’Arc Blvd.

| Demand Scenario | Head (m) | Pressure ¹ (psi) |
|---------------------|----------|-----------------------------|
| Maximum HGL | 113.6 | 88.5 |
| Peak Hour | 106.7 | 78.6 |
| Max Day plus Fire 1 | 112.0 | 86.2 |
| Max Day plus Fire 2 | 102.9 | 73.3 |

¹ Ground Elevation = 51.4 m

Connection 2 – Jeanne D’Arc Blvd.

| Demand Scenario | Head (m) | Pressure ¹ (psi) |
|---------------------|----------|-----------------------------|
| Maximum HGL | 113.6 | 89.2 |
| Peak Hour | 106.7 | 79.3 |
| Max Day plus Fire 1 | 107.7 | 80.7 |
| Max Day plus Fire 2 | 102.9 | 74.0 |

¹ Ground Elevation = 50.9 m

Notes

1. A second connection to the watermain is required to decrease vulnerability of the water system in case of breaks.
2. As per the Ontario Building Code in areas that may be occupied, the static pressure at any fixture shall not exceed 552 kPa (80 psi.) Pressure control measures to be considered are as follows, in order of preference:
 - a. If possible, systems to be designed to residual pressures of 345 to 552 kPa (50 to 80 psi) in all occupied areas outside of the public right-of-way without special pressure control equipment.
 - b. Pressure reducing valves to be installed immediately downstream of the isolation valve in the home/ building, located downstream of the meter so it is owner maintained.

Disclaimer


The boundary condition information is based on current operation of the city water distribution system. The computer model simulation is based on the best information available at the time. The operation of the water distribution system can change on a regular basis, resulting in a variation in boundary conditions. The physical properties of watermains deteriorate over time, as such must be assumed in the absence of actual field test data. The variation in physical watermain properties can therefore alter the results of the computer model simulation. Fire Flow analysis is a reflection of available flow in the watermain; there may be additional restrictions that occur between the watermain and the hydrant that the model cannot take into account.

Appendix E – Drawings

Architectural Plans

Plan of Topographic Survey

| 13383 | | 1015 TWIDDLE RD - AMENITY AREAS (ZONING) | | | | | | | | | | | | | | | | | | | | | | | | 2025-05-29 | |
|-------------------------|------|--|------------|-----------------------|------------|----------------------|------------|-----------------------|------------|----------------------|------------|-----------------------|------------|----------------------|------------|-----------------------|------------|--------------------|-----------------------------|--------------------|------|--|--|--|--|------------|--|
| STATISTICS / STATISTICS | | B1 | | | | B2 | | | | B3 | | | | B4 | | | | TOTAL PRIVATE AREA | | TOTAL AMENITY AREA | | | | | | | |
| | | PRIVATE AMENITY AREA | | COMMUNAL AMENITY AREA | | PRIVATE AMENITY AREA | | COMMUNAL AMENITY AREA | | PRIVATE AMENITY AREA | | COMMUNAL AMENITY AREA | | PRIVATE AMENITY AREA | | COMMUNAL AMENITY AREA | | TOTAL PRIVATE AREA | TOTAL COMMUNAL AMENITY AREA | | | | | | | | |
| | | sq ft | sq ft / B1 | sq ft / B1 | sq ft / B1 | sq ft | sq ft / B2 | sq ft / B2 | sq ft / B2 | sq ft | sq ft / B3 | sq ft / B3 | sq ft / B3 | sq ft | sq ft / B4 | sq ft / B4 | sq ft / B4 | sq ft | sq ft / B1 | sq ft / B1 | | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0.00 | 0.00 | | | | | | |
| 35a Drage - 2nd Floor | 0.00 | 0.00 | 0.00 | 0.00 | 16 | 165 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00</ | | | | | | | | | | | |



PROMOTEUR Developer
Vuze Construction
Lapierre Ave 1600, Ottawa ON K1Z 8P5
T 819 664 4195 Vuzeconstruction.com


PLANIFICATEUR Planner
Fotenn Planning and Design
420 O'Connor Street, Ottawa ON K2P 0P4
T 613 730 5709 Fotenn.com

ARCHITECTURE DE PAYSAGE Landscape Architect
Projet Paysage
24 Mont-royal West Suite 801, Montreal QC H2T 2S2
T. 514. 849. 7700 Projetpaysage.com

CIVIL Civil
EXP
1001 Boulevard De Maisonneuve Ouest, Bureau 800, Montreal
H3A 2E4

ARCHITECTES Architect
NEUF architect(e)s
630, boul. René-Lévesque O. 32e étages, Montréal QC H3B 1
T. 514 947 1517 NEUF.ca

SCEAU / Seq



- PIN 14538
- LOT 30 CONCESSION 1 (OLD SURVEY) GEOGRAPHIC TOWNSHIP OF CUMBERLAND CITY OF OTTAWA, PREPARED BY ANNIS, O'SULLIVAN, VOLLEBKCK LTD., DATED OCTOBER 15TH, 2024.
- PROPERTY BOUNDARY INFORMATION AND PIN AS WELL AS DETILED ENCL. P53H 30m Buffer, PATERSON TOP OF SLOPE, 15m SETBACK AND HAZARD LANDS LIMITS DERIVED FROM PLAN OF SURVEY DATED OCTOBER 15TH, 2024 11n, AMENDED APRIL 30TH, 2025, BY ANNIS, O'SULLIVAN, VOLLEBKCK LTD. PLAN 25483-24 M Chener PL L30 C1 C5 Cumberland CDS.
- FOR PEDESTRIAN WALKING AREAS AND SURFACE MATERIALS REFER TO LANDSCAPE PLAN BY PROJECT PAYSCAPE.
- FOR WASTE MANAGEMENT CALCULATIONS AND ENLARGED PLANS REFER TO DESIGN BRIEF PAGES 46-50.


NO RÉVISION DATE (aa-mm-)

**Préliminaire
NE PAS UTILISER POUR
CONSTRUCTION**


DESSINÉ PAR Drawn by
AT
DATE (aa.mm.jj)
25.05.30
VÉRIFIÉ PAR Checked by
AC
ÉCHELLE Scale
As
indicated

SITE PLAN

REVISION Revision NO. DESSIN Dwg Number
A100







Plan étage type - Niveau 7

ÉCHELLE = 1 : 500

1015 TWEDDLE ROAD ZONING GROSS FLOOR AREA


[illegible]

| 13383_1015 TWEDDLE ROAD - STATISTICS - TOWER B1 | | | | | | | | | | | | | | | | | | | | | | Date | 2025-04-02 |
|---|--|-----------|--|-----------|---|------------------------------------|---------|-------------------------------|---------|---------------------------------------|---------|--|---------|---------------------------------------|------------------------------|-----------|-------------------------|-----------------|---------------------|------------------------|---------------------|------------------------|---------------------|
| | Aire brute par plancher (construction) / Gross area per floor (construction) | | Superficie nette estimée / Estimated Net Area (0.91) | | Espaces de stationnement Interieur / Parking spaces | Aire Commerciale / Commercial Area | | Aire d'agrément /Amenity Area | | Aire non-vendable / Non sellable area | | Aire Résidentielle Brute/ Gross Residential Area | | Efficiency ratio / Ratio d'efficacité | UNITÉS TOTALES / TOTAL UNITS | UNIT MIX | | | | | | | |
| | m² / m² | pi² / ft² | m² / m² | pi² / ft² | | | m² / m² | pi² / ft² | m² / m² | pi² / ft² | m² / m² | pi² / ft² | m² / m² | | | pi² / ft² | Gross Residential / GFA | studio bachelor | 1 chambre 1 bedroom | 1 ch + den 1 bed + den | 2 chambre 2 bedroom | 2 ch + den 2 bed + den | 3 chambre 3 bedroom |
| TOTAL | 37278 | 366806 | 27845 | 299718 | 229 | 885 | 9526 | 607 | 6529 | 3953 | 42552 | 21953 | 236304 | | 326 | 0 | 53 | 163 | 107 | 0 | 3 | 0 | |
| ABOVE GRADE | 27398 | 297908 | 24932 | 268370 | 0 | | | | | | | | | | | 0.00% | 16.26% | 50.00% | 32.82% | 0.00% | 0.92% | 0.00% | |
| UNDER GRADE | 9601 | 103346 | | | 229 | | | | | | | | | | | | | | | | | | |
| PCV | 22838 | 245830 | | | 3 | niveau parking | | | | | | | | | | | | | | | | | |
| Ratio | | 83% | | | 0.70 | 2.21% | | | | | 14.43% | | | | 0.83 | | | | | | | | |
| Mechanical | 278 | 2997 | | | | | | | | | | | | | | | | | | | | | |
| 28th Floor | 928 | 9989 | 844 | 9090 | | 0 | 0 | 0 | 0 | 131 | 1410 | 797 | 8579 | 0.86 | 12 | 0 | 2 | 6 | 4 | 0 | 0 | 0 | |
| 27th Floor | 928 | 9989 | 844 | 9090 | | 0 | 0 | 0 | 0 | 131 | 1410 | 797 | 8579 | 0.86 | 12 | 0 | 2 | 6 | 4 | 0 | 0 | 0 | |
| 26th Floor | 928 | 9989 | 844 | 9090 | | 0 | 0 | 0 | 0 | 131 | 1410 | 797 | 8579 | 0.86 | 12 | 0 | 2 | 6 | 4 | 0 | 0 | 0 | |
| 25th Floor | 928 | 9989 | 844 | 9090 | | 0 | 0 | 0 | 0 | 131 | 1410 | 797 | 8579 | 0.86 | 12 | 0 | 2 | 6 | 4 | 0 | 0 | 0 | |
| 24th Floor | 928 | 9989 | 844 | 9090 | | 0 | 0 | 0 | 0 | 131 | 1410 | 797 | 8579 | 0.86 | 12 | 0 | 2 | 6 | 4 | 0 | 0 | 0 | |
| 23rd Floor | 928 | 9989 | 844 | 9090 | | 0 | 0 | 0 | 0 | 131 | 1410 | 797 | 8579 | 0.86 | 12 | 0 | 2 | 6 | 4 | 0 | 0 | 0 | |
| 22nd Floor | 928 | 9989 | 844 | 9090 | | 0 | 0 | 0 | 0 | 131 | 1410 | 797 | 8579 | 0.86 | 12 | 0 | 2 | 6 | 4 | 0 | 0 | 0 | |
| 21st Floor | 928 | 9989 | 844 | 9090 | | 0 | 0 | 0 | 0 | 131 | 1410 | 797 | 8579 | 0.86 | 12 | 0 | 2 | 6 | 4 | 0 | 0 | 0 | |
| 20th Floor | 928 | 9989 | 844 | 9090 | | 0 | 0 | 0 | 0 | 131 | 1410 | 797 | 8579 | 0.86 | 12 | 0 | 2 | 6 | 4 | 0 | 0 | 0 | |
| 19th Floor | 928 | 9989 | 844 | 9090 | | 0 | 0 | 0 | 0 | 131 | 1410 | 797 | 8579 | 0.86 | 12 | 0 | 2 | 6 | 4 | 0 | 0 | 0 | |
| 18th Floor | 928 | 9989 | 844 | 9090 | | 0 | 0 | 0 | 0 | 131 | 1410 | 797 | 8579 | 0.86 | 12 | 0 | 2 | 6 | 4 | 0 | 0 | 0 | |
| 17th Floor | 928 | 9989 | 844 | 9090 | | 0 | 0 | 0 | 0 | 131 | 1410 | 797 | 8579 | 0.86 | 12 | 0 | 2 | 6 | 4 | 0 | 0 | 0 | |
| 16th Floor | 928 | 9989 | 844 | 9090 | | 0 | 0 | 0 | 0 | 131 | 1410 | 797 | 8579 | 0.86 | 12 | 0 | 2 | 6 | 4 | 0 | 0 | 0 | |
| 15th Floor | 928 | 9989 | 844 | 9090 | | 0 | 0 | 0 | 0 | 131 | 1410 | 797 | 8579 | 0.86 | 12 | 0 | 2 | 6 | 4 | 0 | 0 | 0 | |
| 14th Floor | 928 | 9989 | 844 | 9090 | | 0 | 0 | 0 | 0 | 131 | 1410 | 797 | 8579 | 0.86 | 12 | 0 | 2 | 6 | 4 | 0 | 0 | 0 | |
| 13th Floor | 928 | 9989 | 844 | 9090 | | 0 | 0 | 0 | 0 | 131 | 1410 | 797 | 8579 | 0.86 | 12 | 0 | 2 | 6 | 4 | 0 | 0 | 0 | |
| 12th Floor | 928 | 9989 | 844 | 9090 | | 0 | 0 | 0 | 0 | 131 | 1410 | 797 | 8579 | 0.86 | 12 | 0 | 2 | 6 | 4 | 0 | 0 | 0 | |
| 11th Floor | 928 | 9989 | 844 | 9090 | | 0 | 0 | 0 | 0 | 131 | 1410 | 797 | 8579 | 0.86 | 12 | 0 | 2 | 6 | 4 | 0 | 0 | 0 | |
| 10th Floor | 928 | 9989 | 844 | 9090 | | 0 | 0 | 0 | 0 | 131 | 1410 | 797 | 8579 | 0.86 | 12 | 0 | 2 | 6 | 4 | 0 | 0 | 0 | |
| 9th Floor | 928 | 9989 | 844 | 9090 | | 0 | 0 | 0 | 0 | 131 | 1410 | 797 | 8579 | 0.86 | 12 | 0 | 2 | 6 | 4 | 0 | 0 | 0 | |
| 8th Floor | 928 | 9989 | 844 | 9090 | | 0 | 0 | 0 | 0 | 131 | 1410 | 797 | 8579 | 0.86 | 12 | 0 | 2 | 6 | 4 | 0 | 0 | 0 | |
| 7th Floor | 928 | 9989 | 844 | 9090 | | 0 | 0 | 0 | 0 | 131 | 1410 | 797 | 8579 | 0.86 | 12 | 0 | 2 | 6 | 4 | 0 | 0 | 0 | |
| 6th Floor | 928 | 9989 | 844 | 9090 | | 0 | 0 | 0 | 0 | 131 | 1410 | 797 | 8579 | 0.86 | 12 | 0 | 2 | 6 | 4 | 0 | 0 | 0 | |
| 5th Floor | 928 | 9989 | 844 | 9090 | | 0 | 0 | 0 | 0 | 131 | 1410 | 797 | 8579 | 0.86 | 12 | 0 | 2 | 6 | 4 | 0 | 0 | 0 | |
| 4th Floor | 928 | 9989 | 844 | 9090 | | 0 | 0 | 0 | 0 | 131 | 1410 | 797 | 8579 | 0.86 | 12 | 0 | 2 | 6 | 4 | 0 | 0 | 0 | |
| 3rd Floor | 928 | 9989 | 844 | 9090 | | 0 | 0 | 0 | 0 | 131 | 1409 | 797 | 8580 | 0.86 | 12 | 0 | 2 | 6 | 4 | 0 | 0 | 0 | |
| 2nd Floor (Podium) | 1570 | 16899 | 1429 | 15378 | | 0 | 0 | 117 | 1255 | 222 | 2391 | 1231 | 13254 | 0.78 | 14 | 0 | 1 | 7 | 3 | 0 | 3 | 0 | |
| Ground Floor 1 | 1700 | 18301 | 1547 | 16654 | | 885 | 9526 | 490 | 5274 | 325 | 3500 | 0 | 0 | 0.00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Basement 1 | 3200 | 34449 | 2912 | 31348 | 75 | 42.7 | | | | | | | | | | | | | | | | | |
| Basement 2 | 3200 | 34449 | | | 76 | 42.1 | | | | | | | | | | | | | | | | | |
| Basement 3 | 3200 | 34449 | | | 78 | 41.0 | | | | | | | | | | | | | | | | | |

#REF!


| 13383_1015 TWEDDLE ROAD - STATISTICS - TOWER B3 | | | | | | | | | | | | | | | | | | | | | | Date | 2025-04-02 |
|---|---|-----------|--|-----------|---|---------------------------------------|-----------|-----------------------------------|-----------|--|-----------|---|-----------|--|---------------------------------|--------------------|------------------------|---------------------------|------------------------|---------------------------|------------------------|---------------------------|------------|
| | Aire brute par plancher (construction) / Gross area per floor (construction) | | Superficie nette estimée (0.91) / Estimated Net Area (0.91) | | Espaces de stationne ment Interieur / Parking spaces | Aire Commerciale / Commercial Area | | Aire d'agrément / Amenity Area | | Aire non-vendable / Non sellable area | | Aire Résidentielle Brute/ Gross Residential Area | | Efficiency ratio / Ratio d'efficacit é | UNITÉS TOTALES / TOTAL UNITS | UNIT MIX | | | | | | | |
| | m² / m² | pi² / ft² | m² / m² | pi² / ft² | | m² / m² | pi² / ft² | m² / m² | pi² / ft² | m² / m² | pi² / ft² | m² / m² | pi² / ft² | Gross Residential / GFA | | studio bachelor | 1 chambre 1 bedroom | 1 ch + den 1 bed + den | 2 chambre 2 bedroom | 2 ch + den 2 bed + den | 3 chambre 3 bedroom | 3 ch + den 3 bed + den | |
| TOTAL | 34466 | 373980 | 24702 | 265894 | 210 | 425 | 4575 | 808 | 8697 | 4862 | 52329 | 21051 | 226591 | | 324 | 0 | 51 | 167 | 105 | 0 | 1 | 0 | |
| ABOVE GRADE | 27146 | 295188 | 24702 | 265894 | 0 | | | | | | | | | | | 0.00% | 15.74% | 51.54% | 32.41% | 0.00% | 0.31% | 0.00% | |
| UNDER GRADE | 7320 | 78792 | | | 210 | | | | | | | | | | | | | | | | | | |
| PCV | 21476 | 231166 | | | 3 | niveau parking | | | | | | | | | | | | | | | | | |
| Ratio | | 78% | | | 0.65 | 2.98% | | | | | 17.91% | | | | 0.80 | | | | | | | | |
| Mechanical | 278 | 2997 | | | | | | | | | | | | | | | | | | | | | |
| 28th Floor | 928 | 9989 | 844 | 9090 | | 0 | 0 | 0 | 0 | 148 | 1593 | 780 | 8396 | 0.84 | 12 | 0 | 2 | 6 | 4 | 0 | 0 | 0 | |
| 27th Floor | 928 | 9989 | 844 | 9090 | | 0 | 0 | 0 | 0 | 148 | 1593 | 780 | 8396 | 0.84 | 12 | 0 | 2 | 6 | 4 | 0 | 0 | 0 | |
| 26th Floor | 928 | 9989 | 844 | 9090 | | 0 | 0 | 0 | 0 | 148 | 1593 | 780 | 8396 | 0.84 | 12 | 0 | 2 | 6 | 4 | 0 | 0 | 0 | |
| 25th Floor | 928 | 9989 | 844 | 9090 | | 0 | 0 | 0 | 0 | 148 | 1593 | 780 | 8396 | 0.84 | 12 | 0 | 2 | 6 | 4 | 0 | 0 | 0 | |
| 24th Floor | 928 | 9989 | 844 | 9090 | | 0 | 0 | 0 | 0 | 148 | 1593 | 780 | 8396 | 0.84 | 12 | 0 | 2 | 6 | 4 | 0 | 0 | 0 | |
| 23rd Floor | 928 | 9989 | 844 | 9090 | | 0 | 0 | 0 | 0 | 148 | 1593 | 780 | 8396 | 0.84 | 12 | 0 | 2 | 6 | 4 | 0 | 0 | 0 | |
| 22nd Floor | 928 | 9989 | 844 | 9090 | | 0 | 0 | 0 | 0 | 148 | 1593 | 780 | 8396 | 0.84 | 12 | 0 | 2 | 6 | 4 | 0 | 0 | 0 | |
| 21st Floor | 928 | 9989 | 844 | 9090 | | 0 | 0 | 0 | 0 | 148 | 1593 | 780 | 8396 | 0.84 | 12 | 0 | 2 | 6 | 4 | 0 | 0 | 0 | |
| 20th Floor | 928 | 9989 | 844 | 9090 | | 0 | 0 | 0 | 0 | 148 | 1593 | 780 | 8396 | 0.84 | 12 | 0 | 2 | 6 | 4 | 0 | 0 | 0 | |
| 19th Floor | 928 | 9989 | 844 | 9090 | | 0 | 0 | 0 | 0 | 148 | 1593 | 780 | 8396 | 0.84 | 12 | 0 | 2 | 6 | 4 | 0 | 0 | 0 | |
| 18th Floor | 928 | 9989 | 844 | 9090 | | 0 | 0 | 0 | 0 | 148 | 1593 | 780 | 8396 | 0.84 | 12 | 0 | 2 | 6 | 4 | 0 | 0 | 0 | |
| 17th Floor | 928 | 9989 | 844 | 9090 | | 0 | 0 | 0 | 0 | 148 | 1593 | 780 | 8396 | 0.84 | 12 | 0 | 2 | 6 | 4 | 0 | 0 | 0 | |
| 16th Floor | 928 | 9989 | 844 | 9090 | | 0 | 0 | 0 | 0 | 148 | 1593 | 780 | 8396 | 0.84 | 12 | 0 | 2 | 6 | 4 | 0 | 0 | 0 | |
| 15th Floor | 928 | 9989 | 844 | 9090 | | 0 | 0 | 0 | 0 | 148 | 1593 | 780 | 8396 | 0.84 | 12 | 0 | 2 | 6 | 4 | 0 | 0 | 0 | |
| 14th Floor | 928 | 9989 | 844 | 9090 | | 0 | 0 | 0 | 0 | 148 | 1593 | 780 | 8396 | 0.84 | 12 | 0 | 2 | 6 | 4 | 0 | 0 | 0 | |
| 13th Floor | 928 | 9989 | 844 | 9090 | | 0 | 0 | 0 | 0 | 148 | 1593 | 780 | 8396 | 0.84 | 12 | 0 | 2 | 6 | 4 | 0 | 0 | 0 | |
| 12th Floor | 928 | 9989 | 844 | 9090 | | 0 | 0 | 0 | 0 | 148 | 1593 | 780 | 8396 | 0.84 | 12 | 0 | 2 | 6 | 4 | 0 | 0 | 0 | |
| 11th Floor | 928 | 9989 | 844 | 9090 | | 0 | 0 | 0 | 0 | 148 | 1593 | 780 | 8396 | 0.84 | 12 | 0 | 2 | 6 | 4 | 0 | 0 | 0 | |
| 10th Floor | 928 | 9989 | 844 | 9090 | | 0 | 0 | 0 | 0 | 148 | 1593 | 780 | 8396 | 0.84 | 12 | 0 | 2 | 6 | 4 | 0 | 0 | 0 | |
| 9th Floor | 928 | 9989 | 844 | 9090 | | 0 | 0 | 0 | 0 | 148 | 1593 | 780 | 8396 | 0.84 | 12 | 0 | 2 | 6 | 4 | 0 | 0 | 0 | |
| 8th Floor | 928 | 9989 | 844 | 9090 | | 0 | 0 | 0 | 0 | 148 | 1593 | 780 | 8396 | 0.84 | 12 | 0 | 2 | 6 | 4 | 0 | 0 | 0 | |
| 7th Floor | 928 | 9989 | 844 | 9090 | | 0 | 0 | 0 | 0 | 148 | 1593 | 780 | 8396 | 0.84 | 12 | 0 | 2 | 6 | 4 | 0 | 0 | 0 | |
| 6th Floor | 928 | 9989 | 844 | 9090 | | 0 | 0 | 0 | 0 | 148 | 1593 | 780 | 8396 | 0.84 | 12 | 0 | 2 | 6 | 4 | 0 | 0 | 0 | |
| 5th Floor | 928 | 9989 | 844 | 9090 | | 0 | 0 | 0 | 0 | 148 | 1593 | 780 | 8396 | 0.84 | 12 | 0 | 2 | 6 | 4 | 0 | 0 | 0 | |
| 4th Floor | 928 | 9989 | 844 | 9090 | | 0 | 0 | 0 | 0 | 148 | 1593 | 780 | 8396 | 0.84 | 12 | 0 | 2 | 6 | 4 | 0 | 0 | 0 | |
| 3rd Floor | 928 | 9989 | 844 | 9090 | | 0 | 0 | 36 | 388 | 171 | 1841 | 721 | 7761 | 0.78 | 11 | 0 | 1 | 6 | 4 | 0 | 0 | 0 | |
| 2nd Floor (Podium) | 1405 | 15121 | 1278 | 13760 | | 0 | 0 | 215 | 2314 | 360 | 3873 | 830 | 8934 | 0.59 | 13 | 0 | 0 | 11 | 1 | 0 | 1 | 0 | |
| Ground Floor 1 | 1613 | 17359 | 1468 | 15797 | | 425 | 4575 | 557 | 5995 | 631 | 6789 | 0 | 0 | 0.00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Basement 1 | 2440 | 26264 | | | 70 | 34.9 | | | | | | | | | | | | | | | | | |
| Basement 2 | 2440 | 26264 | | | 70 | 34.9 | | | | | | | | | | | | | | | | | |
| Basement 3 | 2440 | 26264 | | | 70 | 34.9 | | | | | | | | | | | | | | | | | |


| 13383_1015 TWEDDLE ROAD - STATISTICS - TOWER B4 | | | | | | | | | | | | | | Date 2025-04-02 | | | | | | | | |
|---|---|-----------|--|-----------|--|---------------------------------------|-----------|-----------------------------------|-----------|--|-----------|---|-----------|--|---------------------------------|--------------------|------------------------|---------------------------|------------------------|---------------------------|------------------------|---------------------------|
| | Aire brute par plancher (construction) / Gross area per floor (construction) | | Superficie nette estimée (0.91) / Estimated Net Area (0.91) | | Espaces de stationne ment Interieur / Parking spaces | Aire Commerciale / Commercial Area | | Aire d'agrément / Amenity Area | | Aire non-vendable / Non sellable area | | Aire Résidentielle Brute/ Gross Residential Area | | Efficiency ratio / Ratio d'efficacit é | UNITÉS TOTALES / TOTAL UNITS | UNIT MIX | | | | | | |
| | m² / m² | pi² / ft² | m² / m² | pi² / ft² | | m² / m² | pi² / ft² | m² / m² | pi² / ft² | m² / m² | pi² / ft² | m² / m² | pi² / ft² | Gross Residential / GFA | | studio bachelor | 1 chambre 1 bedroom | 1 ch + den 1 bed + den | 2 chambre 2 bedroom | 2 ch + den 2 bed + den | 3 chambre 3 bedroom | 3 ch + den 3 bed + den |
| TOTAL | 27420 | 298048 | 18834 | 202732 | 147 | 0 | 0 | 0 | 0 | 5225 | 56238 | 16255 | 174965 | | 236 | 0 | 0 | 144 | 92 | 0 | 0 | 0 |
| ABOVE GRADE | 21480 | 234110 | 18834 | 202732 | 0 | | | | | | | | | | | 0.00% | 0.00% | 61.02% | 38.98% | 0.00% | 0.00% | 0.00% |
| UNDER GRADE | 5940 | 63938 | | | 147 | | | | | | | | | | | | | | | | | |
| PCV | 16255 | 174965 | | | 3 | niveau parking | | | | | | | | | | | | | | | | |
| Ratio | | 75% | | | 0.62 | 0.00% | | | | | 24.32% | | | | 0.76 | | | | | | | |
| Mechanical | 270 | 2906 | | | | | | | | | | | | | | | | | | | | |
| 24th Floor | 900 | 9688 | 819 | 8816 | | 0 | 0 | 0 | 0 | 220 | 2368 | 680 | 7319 | 0.76 | 10 | 0 | 0 | 6 | 4 | 0 | 0 | 0 |
| 23rd Floor | 900 | 9688 | 819 | 8816 | | 0 | 0 | 0 | 0 | 220 | 2368 | 680 | 7319 | 0.76 | 10 | 0 | 0 | 6 | 4 | 0 | 0 | 0 |
| 22nd Floor | 900 | 9688 | 819 | 8816 | | 0 | 0 | 0 | 0 | 220 | 2368 | 680 | 7319 | 0.76 | 10 | 0 | 0 | 6 | 4 | 0 | 0 | 0 |
| 21st Floor | 900 | 9688 | 819 | 8816 | | 0 | 0 | 0 | 0 | 220 | 2368 | 680 | 7319 | 0.76 | 10 | 0 | 0 | 6 | 4 | 0 | 0 | 0 |
| 20th Floor | 900 | 9688 | 819 | 8816 | | 0 | 0 | 0 | 0 | 220 | 2368 | 680 | 7319 | 0.76 | 10 | 0 | 0 | 6 | 4 | 0 | 0 | 0 |
| 19th Floor | 900 | 9688 | 819 | 8816 | | 0 | 0 | 0 | 0 | 220 | 2368 | 680 | 7319 | 0.76 | 10 | 0 | 0 | 6 | 4 | 0 | 0 | 0 |
| 18th Floor | 900 | 9688 | 819 | 8816 | | 0 | 0 | 0 | 0 | 220 | 2368 | 680 | 7319 | 0.76 | 10 | 0 | 0 | 6 | 4 | 0 | 0 | 0 |
| 17th Floor | 900 | 9688 | 819 | 8816 | | 0 | 0 | 0 | 0 | 220 | 2368 | 680 | 7319 | 0.76 | 10 | 0 | 0 | 6 | 4 | 0 | 0 | 0 |
| 16th Floor | 900 | 9688 | 819 | 8816 | | 0 | 0 | 0 | 0 | 220 | 2368 | 680 | 7319 | 0.76 | 10 | 0 | 0 | 6 | 4 | 0 | 0 | 0 |
| 15th Floor | 900 | 9688 | 819 | 8816 | | 0 | 0 | 0 | 0 | 220 | 2368 | 680 | 7319 | 0.76 | 10 | 0 | 0 | 6 | 4 | 0 | 0 | 0 |
| 14th Floor | 900 | 9688 | 819 | 8816 | | 0 | 0 | 0 | 0 | 220 | 2368 | 680 | 7319 | 0.76 | 10 | 0 | 0 | 6 | 4 | 0 | 0 | 0 |
| 13th Floor | 900 | 9688 | 819 | 8816 | | 0 | 0 | 0 | 0 | 220 | 2368 | 680 | 7319 | 0.76 | 10 | 0 | 0 | 6 | 4 | 0 | 0 | 0 |
| 12th Floor | 900 | 9688 | 819 | 8816 | | 0 | 0 | 0 | 0 | 220 | 2368 | 680 | 7319 | 0.76 | 10 | 0 | 0 | 6 | 4 | 0 | 0 | 0 |
| 11th Floor | 900 | 9688 | 819 | 8816 | | 0 | 0 | 0 | 0 | 220 | 2368 | 680 | 7319 | 0.76 | 10 | 0 | 0 | 6 | 4 | 0 | 0 | 0 |
| 10th Floor | 900 | 9688 | 819 | 8816 | | 0 | 0 | 0 | 0 | 220 | 2368 | 680 | 7319 | 0.76 | 10 | 0 | 0 | 6 | 4 | 0 | 0 | 0 |
| 9th Floor | 900 | 9688 | 819 | 8816 | | 0 | 0 | 0 | 0 | 220 | 2368 | 680 | 7319 | 0.76 | 10 | 0 | 0 | 6 | 4 | 0 | 0 | 0 |
| 8th Floor | 900 | 9688 | 819 | 8816 | | 0 | 0 | 0 | 0 | 220 | 2368 | 680 | 7319 | 0.76 | 10 | 0 | 0 | 6 | 4 | 0 | 0 | 0 |
| 7th Floor | 900 | 9688 | 819 | 8816 | | 0 | 0 | 0 | 0 | 220 | 2368 | 680 | 7319 | 0.76 | 10 | 0 | 0 | 6 | 4 | 0 | 0 | 0 |
| 6th Floor | 900 | 9688 | 819 | 8816 | | 0 | 0 | 0 | 0 | 220 | 2368 | 680 | 7319 | 0.76 | 10 | 0 | 0 | 6 | 4 | 0 | 0 | 0 |
| 5th Floor | 900 | 9688 | 819 | 8816 | | 0 | 0 | 0 | 0 | 220 | 2368 | 680 | 7319 | 0.76 | 10 | 0 | 0 | 6 | 4 | 0 | 0 | 0 |
| 4th Floor | 900 | 9688 | 819 | 8816 | | 0 | 0 | 0 | 0 | 220 | 2368 | 680 | 7319 | 0.76 | 10 | 0 | 0 | 6 | 4 | 0 | 0 | 0 |
| 3rd Floor | 900 | 9688 | 819 | 8816 | | 0 | 0 | 0 | 0 | 220 | 2368 | 680 | 7319 | 0.76 | 10 | 0 | 0 | 6 | 4 | 0 | 0 | 0 |
| 2nd Floor (Podium) | 897 | 9657 | 816 | 8788 | | 0 | 0 | 0 | 0 | 109 | 1177 | 788 | 8480 | 0.88 | 10 | 0 | 0 | 7 | 3 | 0 | 0 | 0 |
| Ground Floor 1 | 782 | 8421 | | 0 | | 0 | 0 | 0 | 0 | 275 | 2964 | 507 | 5457 | 0.65 | 6 | 0 | 0 | 5 | 1 | 0 | 0 | 0 |
| Basement 1 | 1980 | 21313 | | | 47 | 42.1 | | | | | | | | | | | | | | | | |
| Basement 2 | 1980 | 21313 | | | 49 | 40.4 | | | | | | | | | | | | | | | | |
| Basement 3 | 1980 | 21313 | | | 51 | 38.8 | | | | | | | | | | | | | | | | |



MATERIALS LEGEND


- (A) Brick
Manufacturer: TBD
Colour: TBD
- (B) Clear Glass
Manufacturer: TBD
- (C) Concrete
Manufacturer: TBD
Colour: TBD





MATERIALS LEGEND

- (A) Brick
Manufacturer: TBD
Colour: TBD
- (B) Clear Glass
Manufacturer: TBD
Colour: TBD
- (C) Concrete
Manufacturer: TBD
Colour: TBD



DETAIL SCALE 1:250

EAST HALF OF LOT 30

CONCESSION 1 (OLD SURVEY) (CUMBERLAND)

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

PIN 14538 - 0222

Lines provided by others have not been verified by AOV

Stations are set at right angles to the bearing line

ELEVATION NOTES

1. All elevations are in feet above sea level

2. A level of 100 feet above sea level is indicated by a dashed line

3. A level of 100 feet above sea level is indicated by a solid line

4. A level of 100 feet above sea level is indicated by a dotted line

5. A level of 100 feet above sea level is indicated by a dash-dot line

6. A level of 100 feet above sea level is indicated by a long-dash line

7. A level of 100 feet above sea level is indicated by a short-dash line

8. A level of 100 feet above sea level is indicated by a wavy line

9. A level of 100 feet above sea level is indicated by a zigzag line

10. A level of 100 feet above sea level is indicated by a cross-hatch pattern

11. A level of 100 feet above sea level is indicated by a diagonal line

12. A level of 100 feet above sea level is indicated by a horizontal line

13. A level of 100 feet above sea level is indicated by a vertical line

14. A level of 100 feet above sea level is indicated by a 45-degree line

15. A level of 100 feet above sea level is indicated by a 135-degree line

16. A level of 100 feet above sea level is indicated by a 225-degree line

17. A level of 100 feet above sea level is indicated by a 315-degree line

18. A level of 100 feet above sea level is indicated by a 0-degree line

19. A level of 100 feet above sea level is indicated by a 90-degree line

20. A level of 100 feet above sea level is indicated by a 180-degree line

21. A level of 100 feet above sea level is indicated by a 270-degree line

22. A level of 100 feet above sea level is indicated by a 360-degree line

23. A level of 100 feet above sea level is indicated by a 450-degree line

24. A level of 100 feet above sea level is indicated by a 540-degree line

25. A level of 100 feet above sea level is indicated by a 630-degree line

26. A level of 100 feet above sea level is indicated by a 720-degree line

27. A level of 100 feet above sea level is indicated by a 810-degree line

28. A level of 100 feet above sea level is indicated by a 900-degree line

29. A level of 100 feet above sea level is indicated by a 990-degree line

30. A level of 100 feet above sea level is indicated by a 1080-degree line

31. A level of 100 feet above sea level is indicated by a 1170-degree line

32. A level of 100 feet above sea level is indicated by a 1260-degree line

33. A level of 100 feet above sea level is indicated by a 1350-degree line

34. A level of 100 feet above sea level is indicated by a 1440-degree line

35. A level of 100 feet above sea level is indicated by a 1530-degree line

36. A level of 100 feet above sea level is indicated by a 1620-degree line

37. A level of 100 feet above sea level is indicated by a 1710-degree line

38. A level of 100 feet above sea level is indicated by a 1800-degree line

39. A level of 100 feet above sea level is indicated by a 1890-degree line

40. A level of 100 feet above sea level is indicated by a 1980-degree line

41. A level of 100 feet above sea level is indicated by a 2070-degree line

42. A level of 100 feet above sea level is indicated by a 2160-degree line

43. A level of 100 feet above sea level is indicated by a 2250-degree line

44. A level of 100 feet above sea level is indicated by a 2340-degree line

Notes & Legend

Survey Monument

Standard Iron Bar

Short Standard Iron Bar

Standard Iron Pipe

Standard Iron Stake

Standard Iron Nail

Standard Iron Wire

Standard Iron Chain

Standard Iron Tape

Standard Iron Rope

Standard Iron Cord

Standard Iron String

Standard Iron Thread

Standard Iron Yarn

Standard Iron Fabric

Standard Iron Paper

Standard Iron Ink

Standard Iron Oil

Standard Iron Grease

Standard Iron Wax

Standard Iron Resin

Standard Iron Gum

Standard Iron Sugar

Standard Iron Salt

Standard Iron Pepper

Standard Iron Spice

Standard Iron Herb

Standard Iron Flower

Standard Iron Fruit

Standard Iron Seed

Standard Iron Leaf

Standard Iron Stem

Standard Iron Root

Standard Iron Bark

Standard Iron Wood

Standard Iron Bone

Standard Iron Hair

Standard Iron Skin

Standard Iron Claw

Standard Iron Nail

Standard Iron Hoof

Standard Iron Tusk

Standard Iron Horn

Standard Iron Antler

Standard Iron Claw

Standard Iron Nail

TOPOGRAPHIC PLAN OF SURVEY OF

PART OF LOT 30

CONCESSION 1 (OLD SURVEY)

Geographic Township of Cumberland

CITY OF OTTAWA

Surveyed by Amos, O'Sullivan, Vollebek Ltd.

Plan amended January 22, 2025 to add revised CIMA Wetland

Plan amended January 24, 2025 to add revised CIMA PSW 30m

Plan amended February 3, 2025 to add Topographical Features

Plan amended March 17, 2025 to add Topographical Features on

the western limit of Trim Road.

Plan amended April 30, 2025 to add Topographical Features

along Jean d'Arc Boulevard North, east and west of subject land.

Scale 1:400

NOTES SHOWN ON THIS PLAN ARE IN METRIC AND CAN BE CONVERTED TO FEET BY DIVIDING BY 0.3048

Surveyor's Certificate

1. This survey and plan are correct and in accordance with the Survey

1. This survey and plan are correct and in accordance with the Survey

1. This survey and plan are correct and in accordance with the Survey

1. This survey and plan are correct and in accordance with the Survey

1. This survey and plan are correct and in accordance with the Survey

1. This survey and plan are correct and in accordance with the Survey

1. This survey and plan are correct and in accordance with the Survey

1. This survey and plan are correct and in accordance with the Survey

1. This survey and plan are correct and in accordance with the Survey

1. This survey and plan are correct and in accordance with the Survey

1. This survey and plan are correct and in accordance with the Survey

1. This survey and plan are correct and in accordance with the Survey

1. This survey and plan are correct and in accordance with the Survey

1. This survey and plan are correct and in accordance with the Survey

1. This survey and plan are correct and in accordance with the Survey

1. This survey and plan are correct and in accordance with the Survey

1. This survey and plan are correct and in accordance with the Survey

1. This survey and plan are correct and in accordance with the Survey

1. This survey and plan are correct and in accordance with the Survey

1. This survey and plan are correct and in accordance with the Survey

1. This survey and plan are correct and in accordance with the Survey

1. This survey and plan are correct and in accordance with the Survey

1. This survey and plan are correct and in accordance with the Survey

1. This survey and plan are correct and in accordance with the Survey

1. This survey and plan are correct and in accordance with the Survey

1. This survey and plan are correct and in accordance with the Survey

1. This survey and plan are correct and in accordance with the Survey

1. This survey and plan are correct and in accordance with the Survey

1. This survey and plan are correct and in accordance with the Survey

1. This survey and plan are correct and in accordance with the Survey

1. This survey and plan are correct and in accordance with the Survey

Appendix F – PCSWMM Results

PCSWMM Report

Prop_Rev4_SPA_2025_Report
Model Prop_Rev4_SPA_2025.inp

exp Services Inc.
May 30, 2025

Table of Contents

Summaries

| | |
|---|---|
| Summary 1A: Subcatchment attributes | 3 |
| Summary 1B: Subcatchment attributes | 5 |
| Summary 2A: Outfall attributes | 7 |
| Summary 2B: Outfall attributes | 7 |

Profiles

| | |
|--|---|
| Figure 1: Node STMMH_200 to Node OUTFALL_2 | 8 |
|--|---|

Tables

| | |
|------------------------------|----|
| Table 1: Subcatchments | 9 |
| Table 2: Outfalls | 9 |
| Table 3: Junctions | 10 |
| Table 4: Storages | 10 |
| Table 5: Conduits | 10 |

DRAFT

Summary 1A: Subcatchment attributes

| Name | Prop_Rev4_SPA_2025 | Chicago_3hr_31.9mm_2yr | Chicago_3hr_42.54mm_5yr |
|--------------------|--------------------|------------------------|-------------------------|
| B1 - Area (ha) | 0.0912 | 0.0912 | 0.0912 |
| B2 - Area (ha) | 0.0928 | 0.0928 | 0.0928 |
| B3 - Area (ha) | 0.0927 | 0.0927 | 0.0927 |
| B4 - Area (ha) | 0.0794 | 0.0794 | 0.0794 |
| S100 - Area (ha) | 0.0691 | 0.0691 | 0.0691 |
| S101 - Area (ha) | 0.0372 | 0.0372 | 0.0372 |
| S102 - Area (ha) | 0.0612 | 0.0612 | 0.0612 |
| S103 - Area (ha) | 0.0686 | 0.0686 | 0.0686 |
| S104 - Area (ha) | 0.6319 | 0.6319 | 0.6319 |
| S105 - Area (ha) | 0.0346 | 0.0346 | 0.0346 |
| S106 - Area (ha) | 0.0359 | 0.0359 | 0.0359 |
| S200 - Area (ha) | 0.2265 | 0.2265 | 0.2265 |
| S201_2 - Area (ha) | 0.1793 | 0.1793 | 0.1793 |
| S202 - Area (ha) | 1.3325 | 1.3325 | 1.3325 |
| S203 - Area (ha) | 0.3195 | 0.3195 | 0.3195 |
| S204 - Area (ha) | 0.0366 | 0.0366 | 0.0366 |
| S205 - Area (ha) | 0.4653 | 0.4653 | 0.4653 |
| S300 - Area (ha) | 0.0653 | 0.0653 | 0.0653 |
| S301 - Area (ha) | 0.1325 | 0.1325 | 0.1325 |
| S303 - Area (ha) | 0.0719 | 0.0719 | 0.0719 |
| B1 - Slope (%) | 1.5 | 1.5 | 1.5 |
| B2 - Slope (%) | 1.5 | 1.5 | 1.5 |
| B3 - Slope (%) | 1.5 | 1.5 | 1.5 |
| B4 - Slope (%) | 1.5 | 1.5 | 1.5 |
| S100 - Slope (%) | 2 | 2 | 2 |
| S101 - Slope (%) | 2 | 2 | 2 |
| S102 - Slope (%) | 1.5 | 1.5 | 1.5 |
| S103 - Slope (%) | 2 | 2 | 2 |
| S104 - Slope (%) | 1.5 | 1.5 | 1.5 |
| S105 - Slope (%) | 2 | 2 | 2 |
| S106 - Slope (%) | 2 | 2 | 2 |
| S200 - Slope (%) | 2 | 2 | 2 |
| S201_2 - Slope (%) | 2 | 2 | 2 |
| S202 - Slope (%) | 1.5 | 1.5 | 1.5 |
| S203 - Slope (%) | 2.1 | 2.1 | 2.1 |
| S204 - Slope (%) | 2 | 2 | 2 |
| S205 - Slope (%) | 1.5 | 1.5 | 1.5 |
| S300 - Slope (%) | 5 | 5 | 5 |
| S301 - Slope (%) | 5 | 5 | 5 |

Summary 1A: Subcatchment attributes (continued...)

| Name | Prop_Rev4_SPA_2025 | Chicago_3hr_31.9mm_2yr | Chicago_3hr_42.54mm_5yr |
|-----------------------------|--------------------|------------------------|-------------------------|
| S303 - Slope (%) | 5 | 5 | 5 |
| B1 - Imperv. (%) | 100 | 100 | 100 |
| B2 - Imperv. (%) | 100 | 100 | 100 |
| B3 - Imperv. (%) | 100 | 100 | 100 |
| B4 - Imperv. (%) | 100 | 100 | 100 |
| S100 - Imperv. (%) | 61.2 | 61.2 | 61.2 |
| S101 - Imperv. (%) | 63.6 | 63.6 | 63.6 |
| S102 - Imperv. (%) | 76 | 76 | 76 |
| S103 - Imperv. (%) | 22.2 | 22.2 | 22.2 |
| S104 - Imperv. (%) | 86.4 | 86.4 | 86.4 |
| S105 - Imperv. (%) | 0 | 0 | 0 |
| S106 - Imperv. (%) | 0 | 0 | 0 |
| S200 - Imperv. (%) | 73.2 | 73.2 | 73.2 |
| S201_2 - Imperv. (%) | 73.9 | 73.9 | 73.9 |
| S202 - Imperv. (%) | 49.3 | 49.3 | 49.3 |
| S203 - Imperv. (%) | 33.8 | 33.8 | 33.8 |
| S204 - Imperv. (%) | 100 | 100 | 100 |
| S205 - Imperv. (%) | 50.7 | 50.7 | 50.7 |
| S300 - Imperv. (%) | 100 | 100 | 100 |
| S301 - Imperv. (%) | 99.1 | 99.1 | 99.1 |
| S303 - Imperv. (%) | 100 | 100 | 100 |
| B1 - Peak Runoff (L/s) | 45.16 | 19.45 | 26.39 |
| B2 - Peak Runoff (L/s) | 45.95 | 19.79 | 26.86 |
| B3 - Peak Runoff (L/s) | 45.90 | 19.77 | 26.83 |
| B4 - Peak Runoff (L/s) | 39.31 | 16.93 | 22.98 |
| S100 - Peak Runoff (L/s) | 32.24 | 9.53 | 16.54 |
| S101 - Peak Runoff (L/s) | 17.46 | 5.34 | 9.13 |
| S102 - Peak Runoff (L/s) | 28.43 | 10.03 | 14.89 |
| S103 - Peak Runoff (L/s) | 28.98 | 3.85 | 11.16 |
| S104 - Peak Runoff (L/s) | 306.09 | 117.76 | 170.69 |
| S105 - Peak Runoff (L/s) | 13.72 | 0.36 | 4.18 |
| S106 - Peak Runoff (L/s) | 14.60 | 0.44 | 4.76 |
| S200 - Peak Runoff (L/s) | 106.30 | 36.02 | 55.46 |
| S201_2 - Peak Runoff (L/s) | 84.34 | 28.78 | 44.19 |
| S202 - Peak Runoff (L/s) | 439.67 | 140.95 | 209.31 |
| S203 - Peak Runoff (L/s) | 114.80 | 23.87 | 44.19 |
| S204 - Peak Runoff (L/s) | 18.12 | 7.81 | 10.59 |
| S205 - Peak Runoff (L/s) | 154.73 | 50.54 | 74.57 |
| S300 - Peak Runoff (L/s) | 32.33 | 13.93 | 18.90 |

Summary 1A: Subcatchment attributes (continued...)

| Name | Prop_Rev4_SPA_2025 | Chicago_3hr_31.9mm_2yr | Chicago_3hr_42.54mm_5yr |
|---------------------------|--------------------|------------------------|-------------------------|
| S301 - Peak Runoff (L/s) | 65.51 | 28.14 | 38.24 |
| S303 - Peak Runoff (L/s) | 35.60 | 15.34 | 20.81 |

Summary 1B: Subcatchment attributes

| Name | Chicago_3hr_71.58mm_100yr | Chicago_3hr_85.9mm_100yr+20% |
|--------------------|---------------------------|------------------------------|
| B1 - Area (ha) | 0.0912 | 0.0912 |
| B2 - Area (ha) | 0.0928 | 0.0928 |
| B3 - Area (ha) | 0.0927 | 0.0927 |
| B4 - Area (ha) | 0.0794 | 0.0794 |
| S100 - Area (ha) | 0.0691 | 0.0691 |
| S101 - Area (ha) | 0.0372 | 0.0372 |
| S102 - Area (ha) | 0.0612 | 0.0612 |
| S103 - Area (ha) | 0.0686 | 0.0686 |
| S104 - Area (ha) | 0.6319 | 0.6319 |
| S105 - Area (ha) | 0.0346 | 0.0346 |
| S106 - Area (ha) | 0.0359 | 0.0359 |
| S200 - Area (ha) | 0.2265 | 0.2265 |
| S201_2 - Area (ha) | 0.1793 | 0.1793 |
| S202 - Area (ha) | 1.3325 | 1.3325 |
| S203 - Area (ha) | 0.3195 | 0.3195 |
| S204 - Area (ha) | 0.0366 | 0.0366 |
| S205 - Area (ha) | 0.4653 | 0.4653 |
| S300 - Area (ha) | 0.0653 | 0.0653 |
| S301 - Area (ha) | 0.1325 | 0.1325 |
| S303 - Area (ha) | 0.0719 | 0.0719 |
| B1 - Slope (%) | 1.5 | 1.5 |
| B2 - Slope (%) | 1.5 | 1.5 |
| B3 - Slope (%) | 1.5 | 1.5 |
| B4 - Slope (%) | 1.5 | 1.5 |
| S100 - Slope (%) | 2 | 2 |
| S101 - Slope (%) | 2 | 2 |
| S102 - Slope (%) | 1.5 | 1.5 |
| S103 - Slope (%) | 2 | 2 |
| S104 - Slope (%) | 1.5 | 1.5 |
| S105 - Slope (%) | 2 | 2 |
| S106 - Slope (%) | 2 | 2 |
| S200 - Slope (%) | 2 | 2 |
| S201_2 - Slope (%) | 2 | 2 |

Summary 1B: Subcatchment attributes (continued...)

| Name | Chicago_3hr_71.58mm_100yr | Chicago_3hr_85.9mm_100yr+20% |
|---------------------------|---------------------------|------------------------------|
| S202 - Slope (%) | 1.5 | 1.5 |
| S203 - Slope (%) | 2.1 | 2.1 |
| S204 - Slope (%) | 2 | 2 |
| S205 - Slope (%) | 1.5 | 1.5 |
| S300 - Slope (%) | 5 | 5 |
| S301 - Slope (%) | 5 | 5 |
| S303 - Slope (%) | 5 | 5 |
| B1 - Imperv. (%) | 100 | 100 |
| B2 - Imperv. (%) | 100 | 100 |
| B3 - Imperv. (%) | 100 | 100 |
| B4 - Imperv. (%) | 100 | 100 |
| S100 - Imperv. (%) | 61.2 | 61.2 |
| S101 - Imperv. (%) | 63.6 | 63.6 |
| S102 - Imperv. (%) | 76 | 76 |
| S103 - Imperv. (%) | 22.2 | 22.2 |
| S104 - Imperv. (%) | 86.4 | 86.4 |
| S105 - Imperv. (%) | 0 | 0 |
| S106 - Imperv. (%) | 0 | 0 |
| S200 - Imperv. (%) | 73.2 | 73.2 |
| S201_2 - Imperv. (%) | 73.9 | 73.9 |
| S202 - Imperv. (%) | 49.3 | 49.3 |
| S203 - Imperv. (%) | 33.8 | 33.8 |
| S204 - Imperv. (%) | 100 | 100 |
| S205 - Imperv. (%) | 50.7 | 50.7 |
| S300 - Imperv. (%) | 100 | 100 |
| S301 - Imperv. (%) | 99.1 | 99.1 |
| S303 - Imperv. (%) | 100 | 100 |
| B1 - Peak Runoff (L/s) | 45.16 | 54.19 |
| B2 - Peak Runoff (L/s) | 45.95 | 55.14 |
| B3 - Peak Runoff (L/s) | 45.90 | 55.08 |
| B4 - Peak Runoff (L/s) | 39.31 | 47.18 |
| S100 - Peak Runoff (L/s) | 32.24 | 39.28 |
| S101 - Peak Runoff (L/s) | 17.46 | 21.22 |
| S102 - Peak Runoff (L/s) | 28.43 | 34.82 |
| S103 - Peak Runoff (L/s) | 28.98 | 36.59 |
| S104 - Peak Runoff (L/s) | 306.09 | 369.52 |
| S105 - Peak Runoff (L/s) | 13.72 | 17.73 |
| S106 - Peak Runoff (L/s) | 14.60 | 18.64 |
| S200 - Peak Runoff (L/s) | 106.30 | 129.71 |

Summary 1B: Subcatchment attributes (continued...)

| Name | Chicago_3hr_71.58mm_100yr | Chicago_3hr_85.9mm_100yr+20% |
|-----------------------------|---------------------------|------------------------------|
| S201_2 - Peak Runoff (L/s) | 84.34 | 102.83 |
| S202 - Peak Runoff (L/s) | 439.67 | 568.36 |
| S203 - Peak Runoff (L/s) | 114.80 | 151.59 |
| S204 - Peak Runoff (L/s) | 18.12 | 21.75 |
| S205 - Peak Runoff (L/s) | 154.73 | 199.35 |
| S300 - Peak Runoff (L/s) | 32.33 | 38.80 |
| S301 - Peak Runoff (L/s) | 65.51 | 78.64 |
| S303 - Peak Runoff (L/s) | 35.60 | 42.72 |

Summary 2A: Outfall attributes

| Name | Prop_Rev4_SPA_2025 | Chicago_3hr_31.9mm_2yr | Chicago_3hr_42.54mm_5yr |
|-------------------------------|--------------------|------------------------|-------------------------|
| OUTFALL_1 - Max. Flow (L/s) | 572.97 | 222.48 | 320.53 |
| OUTFALL_1A - Max. Flow (L/s) | 480.73 | 46.84 | 99.84 |
| OUTFALL_2 - Max. Flow (L/s) | 336.63 | 207.42 | 289.25 |
| OUTFALL_3 - Max. Flow (L/s) | 153.64 | 50.34 | 74.10 |
| OUTFALL_4 - Max. Flow (L/s) | 32.33 | 13.93 | 18.90 |

Summary 2B: Outfall attributes

| Name | Chicago_3hr_71.58mm_100yr | Chicago_3hr_85.9mm_100yr+20% |
|-------------------------------|---------------------------|------------------------------|
| OUTFALL_1 - Max. Flow (L/s) | 572.97 | 688.13 |
| OUTFALL_1A - Max. Flow (L/s) | 480.73 | 683.31 |
| OUTFALL_2 - Max. Flow (L/s) | 336.63 | 358.94 |
| OUTFALL_3 - Max. Flow (L/s) | 153.64 | 197.50 |
| OUTFALL_4 - Max. Flow (L/s) | 32.33 | 38.80 |




Figure 1: Node STMMH_200 to Node OUTFALL_2

Table 1: Subcatchments

| Name | Imperv. (%) | CAVG | Area (ha) |
|--------|-------------|------|-----------|
| B1 | 100 | 0.9 | 0.0912 |
| B2 | 100 | 0.9 | 0.0928 |
| B3 | 100 | 0.9 | 0.0927 |
| B4 | 100 | 0.9 | 0.0794 |
| S100 | 61.2 | 0.63 | 0.0691 |
| S101 | 63.6 | 0.65 | 0.0372 |
| S102 | 76 | 0.73 | 0.0612 |
| S103 | 22.2 | 0.36 | 0.0686 |
| S104 | 86.4 | 0.8 | 0.6319 |
| S105 | 0 | 0.2 | 0.0346 |
| S106 | 0 | 0.2 | 0.0359 |
| S200 | 73.2 | 0.71 | 0.2265 |
| S201_2 | 73.9 | 0.72 | 0.1793 |
| S202 | 49.3 | 0.55 | 1.3325 |
| S203 | 33.8 | 0.44 | 0.3195 |
| S204 | 100 | 0.9 | 0.0366 |
| S205 | 50.7 | 0.55 | 0.4653 |
| S300 | 100 | 0.9 | 0.0653 |
| S301 | 99.1 | 0.89 | 0.1325 |
| S303 | 100 | 0.9 | 0.0719 |

Table 2: Outfalls

| Name | Tag | Inflows | Invert Elev. (m) | Rim Elev. (m) | Tide Gate | Type | Fixed Stage (m) |
|------------|---------|---------|------------------|---------------|-----------|------|-----------------|
| OUTFALL_1 | POST | NO | 43 | 44 | NO | FREE | 0 |
| OUTFALL_1A | TWEDDLE | NO | 43 | 44 | NO | FREE | 0 |
| OUTFALL_2 | JDA | NO | 47.76 | 48.92 | NO | FREE | 0 |
| OUTFALL_3 | TWEDDLE | NO | 50.05 | 51 | NO | FREE | 0 |
| OUTFALL_4 | TWEDDLE | NO | 43.2 | 43.2 | NO | FREE | 0 |

Table 3: Junctions

| Name | Invert Elev. (m) | Rim Elev. (m) | Depth (m) |
|-----------|------------------|---------------|-----------|
| EX_DI_1 | 50 | 52.32 | 2.32 |
| EX_DI_2 | 49.8 | 52.15 | 2.35 |
| J01 | 50.11 | 50.26 | 0.15 |
| J02 | 44.13 | 44.28 | 0.15 |
| J03 | 50.11 | 50.26 | 0.15 |
| J04 | 45.3 | 45.45 | 0.15 |
| STMMH_200 | 49.01 | 51.06 | 2.05 |
| STMMH_201 | 48.47 | 51.71 | 3.24 |
| STMMH_202 | 48.07 | 52.13 | 4.06 |
| STMMH_203 | 47.81 | 52.33 | 4.52 |
| SU1 | 50.15 | 51.35 | 1.2 |

Table 4: Storages

| Name | Invert Elev. (m) | Rim Elev. (m) | Depth (m) | Storage Curve |
|---------|------------------|---------------|-----------|---------------|
| CB_1 | 49.5 | 51.05 | 1.55 | TABULAR |
| CB_2 | 50.62 | 52.17 | 1.55 | TABULAR |
| CB_3 | 50.68 | 52.23 | 1.55 | TABULAR |
| OGS | 48.3 | 52.1 | 3.8 | TABULAR |
| ROOF_B1 | 142 | 142.15 | 0.15 | TABULAR |
| ROOF_B2 | 142 | 142.15 | 0.15 | TABULAR |
| ROOF_B3 | 142 | 142.15 | 0.15 | TABULAR |
| ROOF_B4 | 142 | 142.15 | 0.15 | TABULAR |

Table 5: Conduits

| Name | Inlet Node | Outlet Node | Length (m) | Roughness | Inlet Elev. (m) | Outlet Elev. (m) | Cross-Section | Geom1 (m) |
|------|------------|-------------|------------|-----------|-----------------|------------------|---------------|-----------|
| C01 | SU1 | OUTFALL_3 | 35.94 | 0.024 | 50.15 | 50.05 | CIRCULAR | 0.5 |
| C02 | STMMH_200 | STMMH_201 | 72.004 | 0.013 | 49.01 | 48.54 | CIRCULAR | 0.3 |
| C03 | STMMH_201 | STMMH_202 | 80.797 | 0.013 | 48.47 | 48.22 | CIRCULAR | 0.375 |
| C04 | STMMH_202 | STMMH_203 | 74 | 0.013 | 48.07 | 47.85 | CIRCULAR | 0.525 |
| C05 | STMMH_203 | OUTFALL_2 | 17.909 | 0.013 | 47.81 | 47.76 | CIRCULAR | 0.525 |
| C06 | CB_3 | CB_2 | 90.647 | 0.013 | 52.08 | 52.02 | IRREGULAR | 0 |
| C07 | J01 | J02 | 117.008 | 0.013 | 50.11 | 44.13 | IRREGULAR | 0 |
| C08 | OGS | OUTFALL_1 | 39.565 | 0.013 | 48.3 | 43 | CIRCULAR | 0.6 |

Table 5: Conduits (continued...)

| Name | Inlet Node | Outlet Node | Length (m) | Roughness | Inlet Elev. (m) | Outlet Elev. (m) | Cross-Section | Geom1 (m) |
|------|------------|-------------|------------|-----------|-----------------|------------------|---------------|-----------|
| C09 | CB_2 | CB_1 | 94.246 | 0.013 | 52.02 | 50.9 | IRREGULAR | 0 |
| C10 | EX_DI_2 | STMMH_202 | 13.896 | 0.024 | 49.8 | 49.2 | CIRCULAR | 0.375 |
| C11 | EX_DI_1 | EX_DI_2 | 37.18 | 0.024 | 50 | 49.8 | CIRCULAR | 0.375 |
| C12 | CB_1 | J01 | 23.03 | 0.013 | 50.9 | 50.11 | IRREGULAR | 0 |
| C13 | J02 | OUTFALL_1A | 50.682 | 0.035 | 44.13 | 43 | TRAPEZOIDAL | 0.5 |
| C14 | J03 | J04 | 91.427 | 0.013 | 50.11 | 45.3 | IRREGULAR | 0 |
| C15 | J04 | OUTFALL_4 | 14.75 | 0.035 | 45.3 | 43.2 | TRAPEZOIDAL | 0.5 |
| C17 | EX_DI_1 | CB_2 | 37.03 | 0.013 | 52.17 | 52.02 | RECT_OPEN | 0.15 |

DRAFT