



**St. Lawrence Testing
& Inspection Co. Ltd.**

P.O. Box 997, Cornwall, ON, Canada K6H 5V1
814 Second Street W., Phone (613) 938-2521
E-mail: gib@stlawrencetesting.com Fax (613) 938-7395

March 24, 2025

Mr. Jordan Lupovici
Halo Car Wash
1010 Ontario Street
Stratford, ON
N5A 6Z3

**RE: Halo Car Wash 585 West Hunt Club Rd., Nepean, Ontario
Geotechnical Subsurface Investigation
Report No. 25C038R3**

Dear Mr. Lupovici:

As requested by you, this report is submitted on the geotechnical subsurface investigation at the property just North of West Hunt Club Rd. in Ottawa, Ontario.

A) DESCRIPTION OF FIELD WORK

Prior to starting the field drilling, locates were requested through Ontario One Call. When we initially visited the site, the whole site was covered with more than 300 mm of snow throughout.

The drilling was done on March 18, 2025. At the time of drilling, a lot of the snow had melted but there were still drifts of snow over close to half of the site. The drill was from Eastern Ontario Diamond Drilling or Hawkesbury, Ontario. Supervision was by the undersigned geotechnical engineer.

A total of 4 boreholes were put down at the site. The boreholes were advanced by split spoon sampling. Standard Penetration tests were carried out along with the split spoon sampling. The recovered samples were placed in glass jars while on the site. The jars were returned to our lab for later detailed lab examination and one gradation test. While on site we paid close attention for potential fuel contamination odours. None were noted.

A sketch showing the borehole locations is attached to this report.

B) STRATIGRAPHY

The stratigraphy at the 4 boreholes is fairly similar.

The surface is covered with 50 mm of asphalt. Below the asphalt is gravel fill that extends between 0.48 to 0.53 m.

Below the gravel is a brown, moist, compact silty sand. With depth the brown becomes grey brown, generally around 1.5 m and grey, generally around 2.3 m. The moisture becomes very moist generally between 1.8 m to 2.3 m. The silty sand was noted to be wet between 2.3 m to 3.0 m at Boreholes 2, 3 and 4. The ground water was noted at 2.3 m at Boreholes 2 and 3 and at 3.0 m at Boreholes 1 and 4.

We hit bedrock at 3.28 m at Borehole 2 and 2.44 m at Borehole 3.

For the specific information at each borehole, the borehole logs should be referred to.

C) GEOTECHNICAL DISCUSSION

1. General

It is our understanding that a one storey car wash building is to be built near the centre of the lot in an East West direction.

2. Foundations

The foundations for the building can be footings designed with a bearing capacity of 150 KPa S.L.S. and 225 KPa U.L.S at 1.5 m below the surface. The seismic factor is Site Class C. The building design frost depth in this area is 1.5 m below the final exterior surface.

3. Slab on Grade

The soil conditions are acceptable for a normal slab on grade.

The upper asphalt should be removed. The upper gravel should also be lowered.

The gravel below the new slab should be 150 mm of Granular "A" compacted to 95% Standard Proctor Density. If the loading will exceed 25 KPa S.L.S. the compaction should be to 100% Standard Proctor Density.

4. New Sewers and Watermain

The bedrock depths at Boreholes 2 and 3 should be noted in case the sewers or watermains are coming in from the West end. The frost design depth in asphalted areas is 2.3 m.

For any new sewers and watermains, the sewers and watermains must be just below 2.3 m.

All bedrock removal must be done by hoe ramming.

The bedding for the services should be 150 mm of Granular "A" compacted to 95% Standard Proctor Density. The cover material should be 150 mm of Granular "A" compacted to 95% Standard Proctor Density.

The backfill for the trench can be the site silty sand. This should be compacted in maximum 300 mm lifts to 95% Standard Proctor Density.

When it is time to restore the gravel subbase and base in the trench areas, the subgrade should be recompact to 95% Standard Proctor Density prior to applying the subbase course.

5. Dewatering Plan

It has come to our attention that the deepest proposed excavation area may reach the local water table. It is expected that the water table will fluctuate in depth depending on the season and as such, it should be

anticipated that dewatering is likely. It is recommended that surface water from the adjoining asphalt covered roads and properties be diverted to catch basins to prevent entering the excavation. Any infiltrated groundwater will need to be removed from the excavation.

If construction site dewatering involves more than 50,000 L/day and less than or equal to 400,000 L/day of ground water the project must be registered with the Ministry of Environment, Conservation and Parks (MOECP) in the Environmental Activity Sector Registry (EASR). If the volume of water to be removed is more than 400,000 L/day, then a permit to take water is required. We anticipate that the groundwater infiltration will not exceed 50,000 L/day and an EAS registration nor a permit to take water will be necessary. However, an EASR approval will be obtained in accordance with provincial requirements if dewatering is required above the noted 50,000 L/day volume.

The creation of sumps within the excavated area will be required to collect and contain any infiltrated groundwater and possible surface water. It will be necessary to have the volume of groundwater collected in the sumps be measured and recorded in addition to having the water analyzed to confirm it satisfies The City of Ottawa's By-Law 2025-94 Schedule A parameters prior to leaving the construction site. If the accumulated groundwater does not meet the By-Law conditions, then the accumulated groundwater will need to be removed from the construction site via a tanker truck or be treated using a mobile water treatment contractor. If a mobile water treatment contractor is used, the treated water will require testing to confirm it satisfies the By-Law Schedule A (Tables 1 to 4) parameters prior to release into the

sanitary/combined sewer system and the Table 5 storm sewer discharges (By-Law 2025-239).

6. New Parking Lot

For light vehicle parking areas, the subbase should consist of 300 mm of Granular "B" Type 2 and the base should consist of 150 mm of Granular "A" each compacted to 100% Standard Proctor Density.

The asphalt should consist of 50 mm of HL3 compacted to 96% Marshall Density.

For heavy duty access roads, the subbase should consist of 400 mm of Granular "B" Type 2 and the base should consist of 150 mm of Granular "A" each compacted to 100% Standard Proctor Density.

The asphalt should consist of 50 mm of HL4 base and 40 mm of HL3 surface, each compacted to 96% Marshall Density.

D) CONSTRUCTION CONTROL

In order to ensure that the recommendations for footings, backfill and compaction are adhered to, it is recommended that our firm be retained to inspect, test and report accordingly.

**St. Lawrence Testing
& Inspection Co. Ltd.**

Report No. 25C038R3
Continued


Page 7

Respectfully submitted,

ST. LAWRENCE TESTING & INSPECTION CO. LTD.



G.G. McIntee, P. Eng.
GGM:mm





REPORT NO. 25C038

BOREHOLE NO. 1NE

BOREHOLE NO.

DATE OF WL READING March 18, 2025

CASING HS Auger

DATE OF BORING March 18, 2025

DATE OF WL READING March 18, 2025

DATUM

[illegible]

CLIENT Halo Car Wash

LOCATION 585 West Hunt Club Rd., Nepean

DATE OF BORING March 18, 2025

DATE OF WL READING March 18, 2025

REPORT NO. 25C038

BOREHOLE NO. 2NW

CASING HS Auger

DATUM

[illegible]



**St. Lawrence Testing
& Inspection Co. Ltd.**

OFFICE BOREHOLE RECORD

REPORT NO. 25C038

CLIENT Halo Car Wash

BOREHOLE NO. 3SW

LOCATION 585 West Hunt Club Rd., Nepean

CASING HS Auger

DATE OF BORING March 18, 2025

DATE OF WL READING March 18, 2025

DATUM _____

SOIL PROFILE

SAMPLES

LABORATORY
TESTS
PERFORMED

LAB

TEST

RESULTS

WATER CONTENT & ATTERBERG LIMITS.

WP

W

WL

DYNAMIC PENETRATION TEST BLOWS PER FOOT. . . K . . .

0 20 40 60 80

DEPTH
ELEVATION
DEPTH

SOIL DESCRIPTION

STRAT. PLOT

WATER
CONDITIONS

CONDITION

TYPE

NUMBER

RECOVERY

N - VALUE

50 mm Asphalt
Gravel Fill

0.51 Silty Sand
Brown, moist,
compact, becoming
grey below 1.5 m and
very moist below
1.8 m and wet below
2.3 m

2.3
▽
=

2.44 Sampler and auger
refusal on bedrock

APPENDIX



GRAVEL	SAND				SILT	CLAY
	FINE GRAVEL	Coarse	Medium	Fine		

U.S. BUREAU SOIL CLASSIFICATION

HYDROMETER
EQUIVALENT GRAIN SIZE (MM)

U.S. STANDARD SIEVE SIZE (MESHES/IN)

U.S. STANDARD SIEVE OPENINGS IN INCHES

