

## Zoning Confirmation Report Checklist

A. Project Information			
<b>Review Date:</b>	December 18, 2025	<b>Reviewed Plans:</b>	Site Plan (Drawing A001), prepared by Chamberlain Architects, dated 2025-11-25.
<b>Municipal Address(es):</b>	2055 Robertson Road	<b>Official Plan designation:</b>	Outer Urban Transect, Mainstreet Corridor, Evolving Neighbourhood Overlay
<b>Legal Description:</b>	PARCEL A-8, SECTION M65 PT BLK A PLAN M65, PT 1 4R2795; EXCEPT PT 1 4R4596 NEPEAN SUBJECT TO AN EASEMENT IN GROSS OVER PART 1 ON PLAN 4R24255 AS IN OC1148302		
<b>Scope of Work:</b>	Site Plan Control		
<b>Existing Zoning Code:</b>	AM – Arterial Mainstreet / IP1 – Business Park Industrial, Subzone 1	<b>By-law Number:</b>	2008-250
<b>Schedule 1 / 1A Area:</b>	C / C	<b>Overlays Applicable:</b>	N/A

B. Zoning Review				
For Zoning By-law Amendments, please use the proposed zone and subzone requirements, if different than existing.				
<b>Proposed Zone/Subzone (Zoning By-law Amendments only):</b>	N/A			
Zoning Provisions	Applicable Section, Exception or Schedule Reference	By-law Requirement	Proposal	Compliant (Y/N)
<b>Principal Land Use(s)</b>	Section 185 (1)	Hotel	Hotel	YES
<b>Lot Width</b>	Section 185, Table 185 (b)	No minimum	61 m	YES
<b>Lot Area</b>	Section 185, Table 185 (a)	No minimum	10,084.06 m <sup>2</sup>	YES
<b>Front Yard Set Back</b>	Section 185, Table 185 (c)(i)	No minimum	3.0 m	YES
<b>Interior Side Yard Setback</b>	Section 185, Table 185 (d)(ii)	No minimum	4.5 m	YES
<b>Rear Yard Setback</b>	Section 185, Table 185 (e)(iv)	No minimum	165.2 m	YES
<b>Lot Coverage Floor Space Index (F.S.I.)</b>	Section 185, Table 185 (g)(ii)	None	N/A	YES
<b>Building Height</b>	Section 185, Table 185 (f)(vi)	30 metres – in no case greater than 9 storeys	6 storeys	YES
<b>Projections into Height Limit Section 64</b>	Section 64	Parapet	Parapet	YES

<b>Required Parking Spaces Section 101</b>	Section 101, Table 101, Row N44, Column IV	1 per guest unit  (1 x 145 units = <b>145 spaces</b> )	<b>108 spaces</b>  (0.75 x 145 units = <b>108 spaces</b> )	<b>NO</b>
<b>Size of Space Section 106</b>	Section 106 (1)	At least 2.6m wide, not more than 3.1m wide, and at least 5.2m long.	5.2 m x 2.6 m	YES
<b>Driveway Width Section 107</b>	Section 107 (1)(a)(ii)	6.0 m	6.7 m	YES
<b>Aisle Width Section 107</b>	Section 107, Table 107 (d)	6.7 m	6.7 m	YES
<b>Location of Parking Section 109</b>	Section 109 (2)	No parking permitted in the required front yard, required corner side yard, or the extension of a required corner side yard into a rear yard.	Parking provided in interior side yard and rear yard.	YES
<b>Landscaping Provisions for Parking Lots Section 110</b>	Section 110 (1)	Minimum parking lot landscaping – 15% of parking lot area (435 m <sup>2</sup> )	30% of parking lot area (892 m <sup>2</sup> )	YES
	Section 110, Table 110, Row (b), Column IV	Minimum landscape buffer – 3.0 m	East parking buffer: 3.0 m  <b>West parking buffer: 1.0 m</b>  Rear parking buffer: 109.10 m	<b>NO</b>
<b>Refuse Collection Section 110</b>	Section 110 (3)(d)	Screening – Minimum 2 m high opaque screen required.  May provide screening through soft landscaping where in-ground refuse container provided.	Earth Bins (in-ground refuse container) provided.	YES

<b>Bicycle Parking Rates Section 111</b>	Section 111, Table 111A (g)	1 per 1000m <sup>2</sup> of gross floor area  (1,317.66 m <sup>2</sup> / 1000 m <sup>2</sup> = <b>1.3 spaces</b> )  Note: 1,317.66 m <sup>2</sup> is the total GFA for the proposed addition	8 spaces	YES
	Section 111, Table 111B, Row (a), Column II, Column II	0.6 m x 1.8 m	0.8 m x 1.8 m	YES
	Section 111 (9)	A bicycle parking space must have access from an aisle having a minimum width of 1.5 m	1.8 m	YES
<b>Other applicable relevant Provision(s)</b>				
<b>Loading Space Rates and Provisions Section 113</b>	Section 113, Table 113A (d), Column VI	1  Note: 1 loading space is required for the 1,317.66 m <sup>2</sup> proposed addition. The reduced number of loading spaces for the existing building is legally non-conforming.	1	NO
	Section 113, Table 113B (c), Column II	3.5 m	6 m	YES
	Section 113, Table 113B (d)(ii), Column II	7 m	7 m	YES

## C. Draft List of Recommended Zoning

By-law Requirement or Applicable Section	Requirement	Proposed
<b>Required Parking Spaces:</b> Section 101, Table 101, Row N44, Column IV	1 per guest unit  (1 x 145 units = 145 spaces)	108 spaces  (0.75 x 145 = 108 spaces)
<b>Landscaping Provisions for Parking Lots:</b> Section 110, Table 110, Row (b), Column IV	3.0 m	1.0 m

\*A proposed Minor Variance or Zoning By-law Amendment will be submitted.



Engineers, Planners & Landscape Architects

If you have any questions or comments, please do not hesitate to contact me.

Yours truly,

**NOVATECH**

Prepared By:

*N. Thomson*

Nicole Thomson, BES (Planning)  
Planner | Planning & Development

Reviewed By:

*S. Soor*

Simran Soor, MCIP, RPP  
Project Planner | Planning & Development